Sewage disposal / report of a committee appointed by the President of the Local Government Board to inquire into the several modes of treating town sewage.

Contributors

Great Britain. Local Government Board. University of Glasgow. Library

Publication/Creation

London: H.M.S.O., 1876.

Persistent URL

https://wellcomecollection.org/works/ctj4ap25

Provider

University of Glasgow

License and attribution

This material has been provided by This material has been provided by The University of Glasgow Library. The original may be consulted at The University of Glasgow Library. Where the originals may be consulted. This work has been identified as being free of known restrictions under copyright law, including all related and neighbouring rights and is being made available under the Creative Commons, Public Domain Mark.

You can copy, modify, distribute and perform the work, even for commercial purposes, without asking permission.




Wellcome Collection 183 Euston Road London NW1 2BE UK T +44 (0)20 7611 8722 E library@wellcomecollection.org https://wellcomecollection.org



Glasgow University Library







Digitized by the Internet Archive in 2015

SEWAGE DISPOSAL.

This Whiteride Hime

REPORT OF A COMMITTEE

APPOINTED BY THE

PRESIDENT OF THE LOCAL GOVERNMENT BOARD

TO INQUIRE INTO THE SEVERAL

MODES OF TREATING TOWN SEWAGE.

Presented to both Houses of Parliament by Command of Her Majesty.



LONDON:

PRINTED BY GEORGE E. EYRE AND WILLIAM SPOTTISWOODE,
PRINTERS TO THE QUEEN'S MOST EXCELLENT MAJESTY.

FOR HER MAJESTY'S STATIONERY OFFICE.

HEPPIMMOD A TO THOUTH

THE YE OFFICER

GIELOS TRIMINISTOS JADOJ SEPT TO TRICIPADO

макатив или отиг антори от

MODES OF TREATING TOWN SEWAGE.

aliante and in summand of incommittees to assume find at vehicles

: NOUNO1

THOUSE MARKING OWN STREET STREET, WORLD TO STREET, STREET, WORLD TO STREET, ST

BO913/6

GLASGOW
VAIVERSITY
LIBRARY:

CONTENTS.

	PAGE
Instructions for Inquiry	- ix
LIST OF TOWNS INSPECTED	- xi
Conclusions	- xii
Report	xiii
VOLUME AND CONSTITUENTS OF SEWAGE ARE MODIFIED	xiv
ESTIMATE OF TOWN SEWAGE NOT ITS VALUE TO A FARMER	xv
Town Scavenging	. ,,
Town Sewering and House Draining	. xvi
SEWAGE VARIES IN QUALITY	xvii
SEWAGE DIFFICULT TO DEAL WITH	,,,
PROPORTION OF SEWAGE TO EXCRETA BY VOLUME AND WEIGHT	xviii
SEWAGE NOT PROFITABLE TO THE EXTENT ESTIMATED -	- xix
SEWAGE NOT TO BE STORED IN CESSPOOLS	,,
MECHANICAL POWER OF WATER	xx
GENERAL REMARKS ON SEWAGE	,,
SEWAGE IRRIGATION PROVEN NOT TO BE INJURIOUS TO HEALTH	xxi
Money Returns from Sewage contingent on Local Condi-	
TIONS	,,
THE PNEUMATIC SYSTEM	xxii
REMARKS ON THE PNEUMATIC SYSTEM	xxiv
TOWN SEWAGE—ITS TREATMENT AND CHARACTERISTICS -	xxv
Unventilated Foul Sewers and Sewage Tanks dangerous	xxvi
CARELESSLY CLEANSING SEWERS DURING PERIODS OF SICKNESS	
DANGEROUS -	"
DETAILS OF THE MODES OF DEALING WITH SEWAGE -	xxvii
RENT OF LAND USED FOR SEWAGE-IRRIGATION EXCESSIVE	"
Examples of Sewage-irrigation	>>
Area of Land required for a Sewage-Farm will depend on Local Conditions	xxix
ITALIAN RYE-GRASS THE BEST CROP UNDER SEWAGE	,,
A PORTION OF A SEWAGE-FARM TO BE DEEP DRAINED TO ACT AS	
A LAND-FILTER	XXX
DRAINS AND WATERCLOSETS	,,
CLARIFICATION OF SEWAGE	xxxi
DETAILS AS TO IRRIGATION BY TOWN SEWAGE	xxxii

ABSTRACTS

FROM SPECIAL REPORTS.

ZDA'I	PAGE
Cost of dealing with Sewage by Irrigation :-	27324
0 73 10 5	xxxvii
3. Blackburn	xxxviii
4. Cheltenham	- xxxix
5. Chorley, Lancashire	x l
7. Harrogate	xli xlii
8. Leamington	xliii
9. Merthyr-Tydfil	- xliv
10. Rugby	xlv
12. Warwick	xlvi
13. Wolverhampton	. ,,
14. West Derby	xlviii xlix
10. Wiexham	XIIX
Treatment of Sewage by Land-Filtration:	
16. Kendal	1
the	
Precipitation of Sewage-sludge in Tanks :—	David St
17. Birmingham	i
Treatment of Sewage by Chemicals:-	
18. Coventry	lii
19. Bolton-le-Moors	liii
20. Leeds	liv lv
RECERCIÓ ED SCOLLAG ARLAGO (SERVICE DESCRICADO)	10
Treatment of Excreta by the Pail System :-	
22. Halifax	lv
23. Rochdale	lvi
Comparison of the Loss of disposing of Town Sewage in proportion	
to the annual rateable value of the Town By Irrigation plus Scavenging	lviii
By Chemicals plus Scavenging	"
By Pail System at Rochdale; the crude Sewage flows into the River	- >>
By Land-filtration at Kendal	"
Analyses of Sewage-sludge as treated and Fortified with	
CHEMICALS. Report by Dr. Voelcker, F.R.S., on the Fertilizing and	CLASS T
Commercial Value of Town Sewage and Night-soil Manures Theoretical or estimated money value of one ton of the treated	lx
Sewage-sludge	lxi
Practical or market value of one ton of the treated sludge	lxiii

APPENDICES.

	APPI	ENDIX N	No. 1.				D
SEWAGE-FARMS :-							PAGI
1. Edinburgh -	-	-	-	-	-	-	- 1
2. Banbury -	-	-	-	-	-	-	3
3. Bedford -	-	-	-	-		-	6
4. Blackburn -	-	-	-	-	•		9
5. Cheltenham -	-	-	-	-		-	11 13
6. Chorley - 7. Doncaster -		-	-	-	-	-	14
8. Harrogatê -							17
9. Leamington -				-		-	19
10. Merthyr-Tydfil			-	-	-	-	23
11. Rugby	-		-	-		-	25
12. Tunbridge Wells	-		-	-	-	-	26
13. Warwick -	-		-	-	-	-	29
14. West Derby -	-	-	-	-	-	-	30
	ADDE	MDIV X	To 0				
LAND FILTRATION ;-	APPE	NDIX N	0. 2.				
							00
15. Kendal -	-		•	-	-	-	32
	APP	ENDIX	No. 3.				
PRECIPITATION, CHEMI				PROCE	SSES -		
16. Birmingham -							33
17. Bolton-le-Moors				-			36
18. Bradford -	-		-	-	-	-	41
19. Coventry -	-		-	-	-	-	46
20. Leeds	-	-	-	-	-	-	49
21. Halifax -	-	-	-	-	-	-	53
22. Rochdale -	-	-	-	-	-	-	56
			-				
	1 DDE	VINTY M					
		NDIX No					
THE PNEUMATIC SYSTI						BED	
BY THE LOCAL AUTH	IORITIES	OF THE	Towns	VISIT	ED:-		
Leyden	-		-	-		-	61
Amsterdam -	-	-		-	-	-	62
Statement by the			Works		-	-	63
Badhoeve Farm, H	laarlemn	nermier	-	-	-	-	67
Paris Sewage-farm -	2015	_	-	-	-	-	68
Berlin do. do		-	-	-	-	-	70

APPENDIX No. 5.

	PAGE						
EPIDEMIC DISEASE	- 71						
The privy system	- 73						
THE CONDITIONS OF TOWNS, VILLAGES, AND HOUSES IN GRI	EAT						
Britain at this date, 1876	- 74						
SEWAGE IRRIGATION, EXAMPLES OF:-							
1. Edinburgh, Sewage Meadows at	- 78						
Raw and Effluent Sewage at	- 78						
2. Barking, Lodge Farm at	- 81						
Raw and Effluent Sewage at	- 81 - 83						
3. Aldershot, Sewage-Farm at Raw and Effluent Sewage at	- 84						
4. Carlisle, Sewage-Farm at	- 84						
Raw and Purified Sewage at	- 85						
5. Penrith, Sewage-Farm at	- 85						
Raw and Effluent Sewage at 6. Rugby, Sewage-Farm at	- 85 - 86						
Raw and Effluent Sewage at	- 86						
7. Banbury, Sewage-Farm at	- 87						
Raw and Effluent Sewage at	- 88						
Receipts and Expenditure	- 88						
8. Warwick, Sewage-Farm at Raw and Effluent Sewage at	- 89 - 89						
9. Worthing, Sewage-Farm at	- 90						
Receipts and Expenses	- 90						
Raw and Effluent Sewage at	- 91						
10. Bedford, Sewage-Farm at	- 91						
Raw and Effluent Sewage at Receipts and Expenditure at	- 92 - 93						
11. Norwood, Sewage-Farm at	- 93						
Receipts and Expenditure at	- 93						
Raw and Effluent Sewage at	- 94						
Effluent Water at	- 95						
12. Croydon, Sewage-Farm at Raw and Effluent Sewage at	- 96 - 97						
Effluent Water at	- 98						
Purification of Sewage by Irrigation, influence of Sea	son						
upon the	- 99						
13. Woking Convict Prison, Experiments at	- 100						
NFLUENCE OF SEWAGE IRRIGATION ON HEALTH	- 102						
CROYDON (SOUTH NORWOOD) SEWAGE-FARM	- 103						
CROYDON (BEDDINGTON) SEWAGE-FARM	- 103						
SEWAGE-GROWN GRASS PROVED TO BE WHOLESOME -	- 104						
DEWAGE-GROWN GRASS PROVED TO BE WHOLESOME	- 104						
APPENDIX No. 6.							
LIST of PATENTS connected with SEWAGE and MANURES from 18	356						
to 1875	- 105						
- CONTROL ASWO'L NEW SO EXPERIENCE AND A							
ADDUNDIN N. A							
APPENDIX No. 7.							
ABSTRACTS from the REPORTS OF ROYAL COMMISSION, and others,							
who have inquired into the best modes of distributing the Sew of Towns, and of applying it to beneficial and profitable uses	age - 116						
Extracts from the Reports of the Royal Commission made 185							
1865:	10-						
Precipitation of the solid matter of sewage	- 116						

]	PAGE
PRELIMINARY REPORT	г, Ма	RCH 185	8:					
Conclusions	-	-		-	-	-	-	120
SECOND REPORT, 186	1:							
Conclusions	-	-	-	-	-	-	-	121
RECOMMENDATION	-	-	-	-	-	-	-	123
THIRD REPORT, 1865	:							
Conclusions	-	-	-	-	-			124
Extracts from a Rei	PORT	by HENE	RY Aus	TIN, Es	a., C.E.	-	-	125
Conclusions	-	-	-	-	-	-	-	125
Conclusions from the								
Analysis of Evidence	-	-		-	-	-	-	128
REPORT on the RESU HEALTH and SEWA							e on	129

EXPLANATION OF THE TERMS USED IN THIS REPORT.

SEWAGE.—The fluid refuse of a town.

SEWER .- The main conduit for sewage laid within a town.

Drain.—The tributary conduit for sewage from houses to sewers.

Sewerage.—A system of sewers.

RAW OR CRUDE SEWAGE.—Sewage as it flows untreated from a sewer.

CLARIFIED SEWAGE. -- Sewage deprived of solids and flocculent matters in tanks.

PURIFIED SEWAGE.—Sewage filtered through land sufficiently to have neutralized the salts.

EXCRETA, used as a singular noun.—Fæces and urine combined.

Dust.—The ashes and other dry refuse from houses.

THE A. B. C. PROCESS .- Sewage treated with Alum, Blood, and Clay, &c.

M. AND C. PROCESS.—Initials of the patentees. The ingredients used are lime, carbon, soda, per-chloride of iron, and ashes.

THE PAIL AND GOUX SYSTEMS.—Moveable vessels placed beneath privy seats prepared to receive excreta.

LIST OF MAPS AND DETAILS OF SEWAGE-FARMS.

		**						N	lo.
Bedford -	-		-	-	-	-	L	-	1
Doncaster -	-	-	-	-		- 1	-	-	2
Wolverhampton	-	-	-	-	-	-		-	3
Tunbridge Wells,	North 1	Farm	-		-	-	-	-	4
North Farm Sewa	ge Tanl	k Details	-	-	-	-		-	5
Tunbridge Wells,	South	Farm	-		-	-	-	-	6
South Farm Sewa	ge Tanl	k Details	-	-	-		-	-	7
West Derby	-	-	-	-	-	-	-	-	
Kendal, General 1	Plan and	d Details	-	-	-		9, 10), 11,	12
Wimbledon		-		-		-	-	13,	14

SEWAGE DISPOSAL.

The Maps referred to in this Report will be found in a separate cover.

Maps missing. Aw 10.3.72

SEWAGE DISPOSAL.

in a separate cores.

INSTRUCTIONS FOR INQUIRY.

(Copy.)

Local Government Board,

Whitehall, S.W.,

SIR,

June 19th, 1875.

I AM desired by the President to enclose, for your information, a copy of a minute of the Board, dated 17th instant, directing an inquiry into the practical efficiency of the chief systems of sewage disposal now in operation, and for which loans have been sanctioned by this Department.

The President considers it desirable that the proposed inquiry should be undertaken as soon as possible, and I am therefore to request that you will be good enough to make the necessary arrangements for entering upon it in conjunction with the other gentlemen nominated by him. The principal points to which it is important that your attention should be directed are fully stated in the Minute.

I am, Sir,

Your obedient servant,

(Signed)

JOHN LAMBERT,

Robert Rawlinson, Esq., C.B., C.E.

Secretary.

&c. &c. &c.

SEWAGE DISPOSAL.

The attention of the Board has for some time past been directed to the great difficulties experienced by sanitary authorities in devising means for the disposal of the sewage of their districts; and, having regard to the frequent applications which are made to them for advice on this subject, they have deemed it expedient that special inquiry should be made under their direction into the practical efficiency of the chief systems of sewage disposal now in operation, and for which loans have been sanctioned by them. The systems, to which the Board refer, are those for the disposal of sewage;

By sewage-farms,
 By land-filtration,

3. By precipitation and by chemical processes:

And in order that they may obtain reliable information as to the results of each of these processes, they have determined that Mr. C. S. Read, M P., one of their secretaries, and Mr. Rawlinson, C.B., their chief engineering inspector, in conjunction with Mr. Smith, the secretary to the late Rivers Pollution Commission, as their assistant, shall, as early as practicable, visit a limited number of localities in which the processes in question are in operation, and report fully to the Board thereon.

The points to which attention must be directed and upon which the Board are desirous of obtaining information, are mainly the

following :-

1. The nature and character of the works and their actual cost; the rateable value of the district, and the population for which the works are available.

2. The length of time during which they have been in operation.

3. The effect of the works on the sanitary condition of the

district, so far as it can be ascertained generally.

4. The efficiency or non-efficiency of the works as a means of disposing of the sewage of the district, and the quality of the effluent water in relation to its purification and deodorization.

5. Whether any nuisance is or has been occasioned by the

works.

6. The annual outlay required for their maintenance and working, as distinguished from repayments of principal and interest, which should be shown separately.

7. In the case of sewage-farms, the acreage, description of soil, system of cultivation, the kind of crops, and the financial results.

8. In other cases the amount realized by the sale of the sewage. The Board consider that at least four examples of each system should be included in the inquiry; and they are desirous that the separate reports should be accompanied by a general report on the merits of the different systems.

(Signed) G. SCLATER-BOOTH,
Local Government Board,
President.
June 17th, 1875.

TO THE RIGHT HON. GEORGE SCLATER-BOOTH, M.P.,
PRESIDENT OF THE LOCAL GOVERNMENT BOARD.

SIR,

Having in June 1875 received instructions to inspect examples of main sewerage outfall-works, so as to be enabled to report on the same, and to ascertain the facts as to sewage irrigation, we have visited Edinburgh, Wrexham, Chorley, Blackburn, Doncaster, Harrogate, Wolverhampton, Leamington, Warwick, Rugby, Banbury, Bedford, Croydon, Norwood, Reigate, Worthing, Aldershott, Romford, Tunbridge-Wells, Cheltenham, Merthyr-Tydfil, Barking, Norwich, and Enfield; Kendal, where the downward intermittent principle is carried out; Leeds, Bolton, Coventry, Tottenham, Edmonton, and Hertford, where sewage is treated by a chemical process; Bradford, Birmingham, and Luton, where sewage-sludge is precipitated by the addition of lime; and Halifax, Rochdale, Salford, and Manchester, where the pail system is partially used for dealing with excreta. We also visited Leyden and Amstersdam, where the pneumatic system is partially in operation; Paris, where only a portion of the sewage is utilised in irrigation; and Brussels and Berlin, where the sewage is about to be disposed of in irrigation.

We have obtained returns from the several towns visited as to their population, annual rateable value, the costs of the works connected with sewage treatment, the volume of sewage dealt with, and other details relating to the several points referred to in your instructional minute. The particulars thus obtained will be found in the following Report and Appendices 1, 2, 3, and 4.

The several Local Authorities, both at home and abroad, readily furnished such information as they had, and we required, and to them our best thanks are due.

Having examined the different modes of dealing with refuse, solid and fluid, in the several towns now reported upon, we beg to submit the following conclusions.

CONCLUSIONS.

- 1. That the scavenging, sewering, and cleansing of towns are necessary for comfort and health; and that, in all cases, these operations involve questions of how to remove the refuse of towns in the safest manner and at the least expense to the ratepayer.
- 2. That the retention for any lengthened period of refuse and excreta in privy-cesspits or in cesspools or at stables, cowsheds, slaughter-houses, or other places in the midst of towns, must be utterly condemned; and that none of the (so-called) dry-earth or pail-systems, or improved privies can be approved, other than as palliatives for cesspit-middens, because the excreta is liable to be a nuisance during the period of its retention, and a cause of nuisance in its removal; and, moreover, when removed leaves the crude-sewage, unless otherwise dealt with by filtration through land, to pollute any watercourse or river into which such sewage may flow. We have no desire, however, to condemn the dry earth or pail systems for detached houses, or for public institutions in the country, or for villages, provided the system adopted is carefully carried out.
 - 3. That the sewering of towns and the draining of houses must be considered a prime necessity under all conditions and circumstances, so that the sub-soil water may be lowered in wet districts, and may be preserved from pollution, and that waste-water may be removed from houses without delay; and, that the surfaces and channels of streets, yards, and courts may be preserved clean.
 - 4. That most rivers and streams are polluted by a discharge into them of crude-sewage, which practice is highly objectionable.
 - 5. That, as far as we have been able to ascertain, none of the existing modes of treating town-sewage by deposition and by chemicals in tanks appear to effect much change beyond the separation of the solids, and the clarification of the liquid. That the treatment of sewage in this manner, however, effects a considerable improvement, and, when carried to its greatest perfection, may in some cases be accepted.
 - 6. That, so far as our examinations extend, none of the manufactured manures made by manipulating town's refuse, with or without chemicals, pay the contingent costs of such modes of treatment; neither has any mode of dealing separately with excreta, so as to defray the cost of col-

- lection and preparation by a sale of the manure, been brought under our notice.
- 7. That town-sewage can best and most cheaply be disposed of and purified by the process of land irrigation for agricultural purposes, where local conditions are favourable to its application, but that the chemical value of sewage is greatly reduced to the farmer by the fact that it must be disposed of day-by-day throughout the entire year, and that its volume is generally greatest when it is of the least service to the land.
- 8. That land irrigation is not practicable in all cases; and, therefore, other modes of dealing with sewage must be allowed.
- 9. That towns, situate on the sea-coast, or on tidal estuaries, may be allowed to turn sewage into the sea or estuary, below the line of low-water, provided no nuisance is caused; and, that such mode of getting rid of sewage may be allowed and justified on the score of economy.

ROBERT RAWLINSON.
CLARE SEWELL READ.

S. J. SMITH, Assistant, 21st July 1876.

REPORT.

A statement of facts connected with the treatment of sewage at any one town or district can only have a certain limited value, which will be in proportion to the efficiency of the system and the accuracy of the description; but any single example may not have much value outside of the special conditions of the locality. We have investigated examples of the waste of sewage into the sea, of its treatment in depositing tanks without chemicals, of its treatment in depositing tanks with a use of chemicals, of its application to land in irrigation, by gravitation, and of its application to land by pumping. We have also examined several modes of removing excreta in pails, as at Rochdale. Reports more or less in detail of the several processes are given in the Appendices Nos. 1 to 4.

Modifications in the Volume and Constituents of Sewage.

The volume and constituents of sewage are modified by :-

1. The surface contour and local rainfall;

The geological character of the substrata, the mode of forming the surface roads and streets, and the amount of local traffic;

The volume of water-supply, the mode in which it is applied, and the volume of subsoil-water taken into the

drains and sewers;

 The mode and efficiency of the main-sewering, housedraining, and the way in which waste-water and excreta are disposed of;

5. The efficiency, or otherwise, of surface scavenging and sewer

and drain flushing.

Steep surface gradients and roads and streets macadamized, defectively scavenged, and over which roads and streets there is an excess of quick traffic, as cabs, omnibuses, and vans, will send much detritus into the sewers. Birmingham is an example of all the above-named conditions, and consequently also an example where the solids washed down to the outlet are in excess.

The volume of water supplied and passed into sewers, with the volume of subsoil-water entering them, will, during all ordinary periods, constitute the volume of sewage to be dealt with; and as drains and sewers usually receive a portion of the rain, there will, in wet periods, be this volume extra to provide for.

Sewers and drains which have been properly designed and well executed transmit sewage day by day as generated, so that it is fresh, and not putrid; and in the treatment of sewage by any process it is of the utmost importance to deal with it fresh, as there will be less cost in chemicals (if such are used) and less nuisance on the surface of the land if the sewage is applied in irrigation.

In a town properly sewered and drained, well supplied with water on constant service, and wholly water-closeted, the sewage will be in the richest state, and may be dealt with at the least cost and with the greatest safety to health, either by chemicals or

by irrigation over land.

In a well sewered town the character of the sewage will vary in proportion to the time of day and to the habits of the population, as it will be richest in the morning, at noon, and in the evening. From midnight to early morning, for six or eight hours, the sewers will contain little more than subsoil-water and waste from

defective water-supply fittings.

Towns which are defectively sewered, and in which there are many privies and ashpits drained into the rudely-formed sewers, have sewage in its most offensive and dangerous form; and if such sewers are defectively ventilated, there will be the greatest element of danger to health. To connect dwelling-houses with such sewers by drains, especially if the drains are not ventilated, is to incur the greatest risk of danger to health.

Towns in which the so-called dry modes of treatment, or the pail systems prevail, retain human excreta for a longer or a shorter period, as where the pails are said to be removed and emptied each week (that is 52 emptyings each year); or as in portions of Edinburgh, where the pails are said to be removed from room tenements each day, or (excluding Sundays) 312 times in the year. The wholesomeness of this treatment must depend more upon the absolute and perfect cleansing of the tubs or pails at each removal than upon the time of retention, as foul pails will become putrid, and the leaven of putridity will be communicated to the refuse as it is deposited in the pail, or tub. The cost of collecting and replacing the pails is necessarily in proportion to the convenience for removal and the distance of the depôt. The yearly cost of collecting the pails in Rochdale and of working the contents into a solid manure is about 11s. 1¼d. per ton.

The yearly costs of manipulating the solids of sewage by mechanical and chemical means are set forth in the abstracts from the reports on Coventry, Birmingham, Bradford, Halifax,

and Leeds.*

CHEMISTS' ESTIMATE OF TOWN SEWAGE NOT ITS VALUE TO A FARMER.

With respect to the laboratory value of town refuse and of sewage, or of the manipulated solids of sewage, we do not know of a single case where it is sold at a profit; and, as a consequence, there has been local disappointment and accumulations of several thousands of tons of manufactured manure, asserted to be worth from one to several pounds sterling per ton, which prices are not realized; consequently there are these vast heaps encumbering the premises where manipulated. In the case of town sewage, we find that its unceasing flow and the great volume of water to be disposed of day by day, detract from the undoubted manurial value which there is in it, so that sewage containing ammonia, representing a manurial value of 2d. per ton, has to be given away. or has to be wasted into the sea. With respect to the solid manure made from town refuse and extracted from sewage, its bulk and weight reduce its value, and, as, like sewage, the production goes on all the year round, it must be heaped up until farmers can be induced to remove it—the inducement for them to do so being a price far below the cost of production.

See Analyses, pages lxi, lxii, lxiii.

TOWN SCAVENGING.

Town refuse, both fluid and solid, must be got rid of, and the more completely and rapidly the process is effected the better will it be for the inhabitants. The cost of any process should, however, be a secondary question—always provided that due skill has been, and is used in devising the local works, and proper care has been, and is exercised in supervision and labour.

^{*} Note.—The tank mode of treatment costs about 150%, per annum for 100,000 gallons of sewage per day so treated, plus the interest on the cost of tanks and apparatus.

With respect to town scavenging, the ashes and other waste refuse will have most value when retained dry, and that town will be best served where the removal is regular, and at short intervals, by dust-carts, into which the dust is discharged direct. It is a dirty process to empty dust on to the street-surface to be shovelled up by the men after some of it may have been blown about.

Town Sewering and House Draining.

Town sewering and house draining are as ancient as civilization. Drain-tubes of earthenware have been found under the mounds of the ruins of the cities of Asia. The Romans sewered their cities and towns, and drained their temples, baths, and public

buildings, and the sewage polluted the adjoining rivers.

Sanitary progress in Great Britain is recent, and the first rude sewers were more mischievous than beneficial. The earliest Norman castles were not sewered, but were sinks of filth both within and without. One of the earliest improvements was the Guarderobe turret or tower, constructed in an external wall, the floor being carried over the outer face upon corbells. This floor was dished from the sides to a central opening from which excreta could fall outwards to the base of the castle wall. Some of these Guarderobe towers were removed from Windsor Castle since 1840. About the beginning of this century waterclosets were re-invented and were introduced into better class residences, the drainage from them being to the nearest sewer or from the house to some ditch or watercourse or to a pit, or even over the surface of the ground or into the side-channel of a public road. In London and some other towns the nuisance arising from waterclosets was found to be so great that Improvement Acts were obtained in which clauses prohibiting a use of public sewers for waterclosets were inserted. The old sewers were large, rude in construction irregular in gradient, having flat bottoms and being unventilated, so that every form of refuse passed into them remained to putrify, ferment, and exhale gases of a deadly strength, and on some occasions men on entering to cleanse them fell dead. The comfort and convenience of waterclosets having been experienced parties using them did not like to give them up, and as they were not to use the sewers, they were ordered to construct absorbing cesspools into which the contents from the waterclosets were to be emptied, and cesspools were constructed within the basements, yards, and gardens of London houses by tens of thousands, some larger houses having several. In course of time an overflow from a cesspool, cesspit, or ashpit, was permitted to connect with a sewer. This is the position of things now in Birmingham, Manchester, and most of the large towns of Lancashire and Yorkshire. At Windsor Castle, so recently as 1850, there were 53 cesspools within the basement all full and overflowing. This cesspool plan is in favour and full practice in continental cities and towns, as at Paris, at Brussels at Ostend, and at many other continental towns. In Holland, the rivers and

canals are the main-sewers, as, also the main sources of water-

supply for domestic purposes.

At Paris and at Brussels main intercepting-sewers have been constructed, in both of which cities as in London, the sewage flows into the rivers to their serious pollution.

In Holland the pneumatic system has been partially adopted. Frankfort on the Maine has been sewered, and the houses are being drained on the English plan. In the suburbs of Paris sewage irrigation has been partially established, and more complete works of sewage utilization are contemplated. In Brussels there is a very small trial work, and Dantzic has also been sewered on the English plan, and the sewage is applied in irrigation for agricultural purposes. See Appendix No. 5, page 73, Privy system.

SEWAGE VARIES IN QUALITY.

There have been many hundred analyses made of town sewage, and its value is stated to be in proportion to the ammonia found in it. Samples of sewage vary from less than 2½ to upwards of 15 grains per gallon, and the chemist's value is one fourth of a penny per ton of sewage for each grain of ammonia in one gallon. The most important element in sewage is the nitrogen, in the state of ammoniacal salts; or, in combination with organic matters as nitrogenous matter. The nitrogen of ammonia is, however, immediately available to vegetation, whilst that which is combined with organic matter only becomes so gradually, through decomposition. Sewage is rich or poor in proportion to the number of waterclosets used and connected with the sewers, and the state of dilution. An extravagant use or waste of water and an excess of subsoilwater seriously increase dilution. Admission of surface-water will also tend to further dilution. But water has value when applied to land in irrigation, and there are cases where extreme dilution of the sewage is not objectionable; as where the land irrigated is highly absorbent, is of sufficient area, and is under grass. Pumping to a moderate elevation—50 feet or under—is not necessarily costly, as we see that 977,470 tons are pumped at Doncaster to a head of 52 feet at an annual working sum of about 300l.

SEWAGE DIFFICULT TO DEAL WITH.

Sewage as it flows from well-constructed drains and sewers contains much flocculent matter and solid detritus, which in some cases, as at Birmingham, is separated in tanks, to the extent of 109,500 tons per annum, and which sludge is difficult to manipulate, impracticable to dry, and unsaleable. Precipitation by the use of chemicals is carried on at Leeds, Bradford, Halifax, Bolton,* and at other places, as detailed in this report. In some cases there is little or no separation, as at Aldershot and Chorley, where the sewage flows direct on to the land; and at Leamington, Warwick, Bedford, Banbury, Worthing, and Doncaster, where crude sewage is pumped and delivered by carriers over the irrigated lands.† Where

^{*} Note.—Appendix No. 3, pages 33 to 56. † See Appendix 1, pages 1 to 30.

the permanent sewage-carriers are duly proportioned to the volume of sewage, and are of iron, of earthenware, of concrete, or of other solid material, there is no retention of sediment, and consequently, no permanent nuisance as is the case in the large, rude, and foul open sewage-carriers at Edinburgh.

Proportion of Sewage to Excreta by Volume and Weight.

A population of 100,000, exclusively using waterclosets and producing 2,500,000 gallons of sewage daily, may be contrasted as under, to show the relative volume and weight of the sewage, the urine, and the fæces. In a mixed population of both sexes and all ages the excreta of each person per day has been found by experiment to weigh 2½ lbs. A gallon of sewage weighs, say, 10 lbs.; 2,500,000 gallons therefore equal 25,000,000 lbs., and the excreta of 100,000 persons equals 250,000 lbs., or the proportion is as 1 to 100. The urine of 100,000 persons weighs 234,380 lbs., and the fæces 15,620 lbs.; the solids (fæces) being by weight and volume to the sewage in the proportion of 1 to 1,600. The so-called solid portion is to the fluid or urine as 1 to 16, that is, ounces to pounds.

Where human excreta is retained within houses and towns until it is removed by hand labour, or even by special contrivances, there must be a certain amount of inconvenience experienced which will be annoying; and as there is and must be a vast amount of labour expended to remove such refuse, the process will be costly, the relative cost being set forth at page 68 of the Appendix.

In all the so-called dry processes (which are not dry) there is with the excreta a considerable volume of urine and water. This is so in the pail system, and in every form of improved privy.

The advocates of these systems declare that they are aware that town sites must be sewered and that houses must be drained, if only to remove subsoil-water, surface-water, the waste-water used by the inhabitants, and the drainage from stables and privy ashpits. This subsoil-water, surface-water, and waste-water from dwelling-houses, stables, cow-sheds, slaughter-houses, and local manufactures must be treated in the same manner as sewage, before it can be permitted to flow into streams and rivers. The excreta is, however, separated under the idea that there will be more value obtained as manure. and that there will be less pollution at the outlet of the sewers. Experience and analyses show that such conclusions are erroneous. There are in manufacturing towns many sources of pollution other than the drainage of houses, of ashpits and cesspools, of cowsheds, of stables, and the washing of the streets' surface; and in many cases this liquid will have to be provided for in the sewers, as at Coventry, at Kendal, and at other places. Sewers ought, in fact, to receive all water polluted by ordinary processes, as analysis proves that sewage is very little less polluted by the exclusion of human fæces. The Rivers Pollution Commissioners state (pages 29 and 30, Report, Mersey and Ribble

Basins) that 12 tons of average sewage from a midden and privy town will in round numbers equal 10 tons of sewage from a watercloseted town in manurial value, so that the mischief, cost, and intolerable nuisance of a retention of the privy system—and this also is applicable to all so-called dry systems—only reduces the strength of the sewage by two sixths.*

SEWAGE NOT PROFITABLE TO THE EXTENT ESTIMATED.

In 100 tons (224,000 gallons) of sewage, having the equivalent of eight grains of ammonia to the gallon, the ingredients are estimated as having a manurial value of 17s. 7d. The suspended matter, which will subside when at rest or which chemicals will assist to precipitate, is worth 2s. $2\frac{1}{2}d$.; other dissolved matter which remains in the clarified water being worth 15s. $4\frac{1}{2}d$. This makes the value 2·1 penny per ton, or say 2d. per ton, the Royal Commission (1858 to 1865) accepting this estimate of 2d. per ton after a set of exhaustive experiments fully recorded in their three Reports,† came to the conclusion that a farmer having to take and dispose of sewage day-by-day all the year round would not give more than a halfpenny per ton, if even this could be afforded. An examination of the abstracts in this report will show that sewage has very generally been used in irrigation at a loss.

Although this estimate appears so favourable we find that it fails to be commercially productive in practice, and we may again repeat that no chemical or other treatment of town-sewage with which we are acquainted is a commercial success; the suspended solids may be precipitated and the sewage so far clarified by these processes, but the sewage is not purified nor does the sludge appear to be increased in value as a manure so as to command a sale sufficient to pay the costs of production.

The pail system, as practised at Rochdale and other places, does not produce a solid manure of sufficient value to repay the contingent expenses, and command a ready sale.

SEWAGE NOT TO BE STORED IN CESSPOOLS.

Sewage should not be stored in cesspools beneath houses, or near to houses within a town, neither should it be allowed to rest stagnant in badly formed sewers, nor, indeed, in any sewers; but all waste-water and excreta should pass to the drains unperceived, and should then flow in an unceasing stream; and, if practicable, at once over and through land properly prepared for its reception and agricultural use.

MECHANICAL POWER OF WATER.

Water is a purifier, a cleanser, a dissolver, and a mechanical power, and will carry along down an incline the solid ingredients

† Note .- See Appendix No. 7.

^{*} Note.—There are recent privy arrangements to intercept urine. The game will not, however, be worth the candle.

of town sewage, with road detritus, such as grit and silt; the moving power of water being in proportion to the volume, the vertical depth, and the gradient down which the flow is directed. Flushing by volume and head artificially formed will remove detritus from sewers of low gradients where accumulation may have taken place. A velocity in the sewage of two feet six inches per second will remove any solids likely to be passed into drains and sewers.

The weight of detritus and silt moved along with and by the metropolitan sewage is not so great as in some other towns, such, for instance, as Birmingham and Leeds; because in London much of the sludge is removed from the street gulleys and much is removed from the old flat-bottomed sewers by hand labour. In the aggregate a large weight of detritus is, however, swept along to the outlets, and is discharged into the Thames at Crossness and at Barking.

GENERAL REMARKS ON SEWAGE.

The mode of utilising sewage with economy must depend upon local conditions, and a waste of sewage (which is manure) can only be justified when it would cost less to waste it harmlessly than to utilise it, as at Edinburgh, Liverpool, and Brighton, for instance. At Edinburgh the Craigentinny meadows afford the strongest example of pecuniary success in the rough and ready use of crude sewage to produce rank crops of grass; and at Edinburgh also, in the Water of Leith intercepting-sewer we have an example, on a greater scale, of a waste of sewage into the sea at the Black Rocks outlet. The cases must, however, be considered with all their surroundings. At the Craigentinny meadows crude sewage flows down from the older part of Edinburgh without stint or charge towards land having little value in its natural state, as it is for the most part blown sand from the adjoining estuary. This sewage is received at a point sufficiently elevated to allow of its gravitating on to the land to be irrigated. It flows into rudely formed open carriers, to the highest points of the estate, from whence it gravitates by cheaply formed sub-carriers over the land below, the effluent escaping down to the boundary line of the sewage farm, which is the sea. The land is of low value as agricultural land; the sewage is abundant, far more than is required for the area irrigated; it costs nothing to the proprietor of the land; and its use, its abuse, or its waste is under no local control; it is applied in the cheapest way, and the crops are put up to auction in one acre plots each year, the purchaser cutting and removing the grass at his own cost. The mode of irrigation is uncleanly and rude, and there is undoubtedly at times an offensive smell from the carriers, from the rudely drenched irrigated surface, and from the effluent water. During winter the sewage is allowed to flow direct into the sea.

SEWAGE IRRIGATION PROVED NOT TO BE INJURIOUS TO HEALTH.

There is no record of any special outbreak of disease at or near the sewage farm. The men working on the land and amongst the sewage are reported to be healthy, the men cutting the grass are healthy, and the cows fed upon the grass are also as healthy as other cows, producing wholesome milk; and with respect to tapeworm, the medical men who attend the Edinburgh hospitals do not find any exceptional excess of this disease amongst their cases; but, on the contrary, less than in other hospitals. The Craigentinny meadows were made the subject of an exhaustive inquiry by the War Department during the time that Lord Macaulay was member for Edinburgh and Parliamentary Secretary for that department. Complaints were made that the proximity of the irrigated meadows and the efflusium from them produced disease in excess amongst soldiers quartered in the neighbouring barracks. Official inquiry was made by army medical officers, who took the returns of health and mortality for 20 years back from barracks situate in different parts of Great Britain where troops similar in numbers and performing similar duties had been quartered, and these returns were tabulated, the results obtained proving that the barracks adjoining the Edinburgh sewaged meadows had the lowest sick and death rate in the list, so that the allegations against the Craigentinny meadows fell to the ground.* It must not, however, be supposed that rough and ready sewage irrigation is advocated, as the evidence should only be taken as proving that the application to land of putrid and crude sewage in the most gross form does not necessarily breed a local pestilence, though such mal-arrangements may produce an offensive nuisance which ought not to be continued. But we have no evidence that these Edinburgh meadows are a nuisance injurious to health; we are, however, satisfied that the work of irrigation may be carried on in a manner much more cleanly by a construction of settlingtanks to separate the solids and by the construction of permanent main-carriers, which could be regularly cleansed. The utilisation of sewage should, in all cases, be carried on in such manner as, in the vicinity of dwellings, to be the least offensive, although additional costs may, in some cases, be incurred to pay for more complete purification.

Money Returns from Sewage contingent on Local Conditions.

The tabulated statements now made from experiments with sewage on a great scale show that money returns are contingent upon local peculiarities and management. Where the works necessary to treat sewage are simple in their construction and the treatment is unfettered by patents, there is least loss. Purification of sewage is not, however, effected by any use of chemicals which has been brought to our notice, the result in all cases having been

^{*} See also Appendix No. 5, pages 102, 103.

clarification only; that is, a better separation of solids and flocculent matters held in suspension; seven-eighths of the salts of sewage remaining in the clarified water, so that the pollution of a small river or watercourse would not be prevented, however perfectly the sewage may be clarified, as was proven at Leamington, Blackburn, and Cheltenham, where the salts in the clarified sewage combining with the earthy matters on the beds of the streams, fermenting gave out offensive gases sending to the surface a black and putrid scum. We have no reliable evidence that the solids extracted and made into a portable manure have any paying commercial value. At Birmingham, as will be seen by the returns, there is now no serious attempt to sell the sewage-sludge, but it is at great cost, 14l. 10s. per acre, dug into a portion of the farmland at a rate of about one acre per week, or at a loss of about 750l. a year. At Leeds, Bradford, Bolton, and at Coventry thousands of tons of extracted sewage-sludge remain to cumber the works.

At Halifax and Rochdale, where the pail system is in operation and the excreta is collected by hand and mixed with house-ashes, there are also thousands of tons of the prepared manure in store,

because a ready sale of it cannot be effected.

At London, about 600,000 tons per day of the richest sewage in England is poured into the River Thames; at Edinburgh, the Water of Leith sewage is wasted into the sea, and this is also the case at Liverpool, at Brighton, and at most of the large towns in England and Wales which stand upon a river-estuary, or fronting the sea, as at Swansea, at Scarborough, at Sunderland, and Newcastle-upon-Tyne, and at other places.

THE PNEUMATIC SYSTEM.

One of the most complicated and costly processes for dealing with the solid of human excreta (not with town sewage), is the system known by the name of the inventor, CAPT. LIERNUR.

The pneumatic system has been partially introduced at Leyden, Amsterdam, and Dordrecht, where we have seen it working. These towns are flat and are intersected by canals and open watercourses. The towns are not sewered on the English plan, but have surface gutters along the margins of the footwalks into which surface water flows and the inhabitants throw their waste water and liquid household refuse. There are inhabited basements below the level of the streets and gutters—in some streets the gutter is square on section—close to the basement entrance, and covered by a lid of timber which can be raised by the householder for the purpose of discharging slop-water into the channel which communicates at short intervals with a river, canal, or watercourse, as one or the other may be available. There are also small and short surface-drains opening into the watercourses as above described.

At present the excreta in these towns passes from the housedrains into the rivers, canals, and watercourses; the ashes and vegetable refuse being collected from tubs and boxes by what we in London term dust carts. The rivers, canals and watercourses bordering and intersecting the Dutch towns are made into open sewers. Waterclosets on the English plan are used to a limited extent. A modified privy is however generally arranged within the houses over a vertical shaft which drops the refuse to a drain below. In many cases chamber utensils are used. The Dutch towns are deficient in water supply, so that, almost throughout the country, water from rivers, canals, or the watercourses is used for all domestic purposes, however much tainted it may be.

The country being so flat, so intersected by rivers, canals, and watercourses, and the land and street surfaces so little above the general level of the water, has induced the municipal authorities of Holland to come to the conclusion that main-sewers and housedrains, as constructed in English towns, are impracticable; hence

the resort to the pneumatic system.

Capt. Liernur acknowledges that towns should have the subsoil water lowered, that they must be sewered, that houses must be drained, and that the fluid refuse of manufactures must be provided for, but insists that human excreta must be removed by separate and costly apparatus, consisting of steam-engines, air-pumps, iron tanks, and cast-iron pipes of five inches internal diameter-none more, none less-these pipes to be jointed as if for carrying water under high pressure. These pipes are not, however, laid in level and right-line lengths, but in the form of saw teeth extended, so as to break the line of pipes vertically into long downward slopes of 1 in 250, and short upward slopes of 1 in 5, the long slope and its short upward slope forming a sort of inverted syphon, where sewage must rest and block the pipe, to be sucked upwards and forwards by the partial vacuum. The soil-pans are not much unlike English waterclosets; they are fixed beneath a seat, have a syphon bottom outlet, and are specially ventilated. These pans are fixed within buildings as waterclosets are fixed, and are used as waterclosets are used; the prime difference being that the user of the pneumatic closet has no power of emptying the pan. In some cases, where a closet is liable to be much used, the pan has been filled above the brim, and the air-suction failed to empty it. In all cases the closet is a fixed receptacle, amenable to no control by the users, but dependent for its action upon a perambulating turncock. If servants disobey rules and pour in slops or the contents of chamber utensils, and the pan is full before the time of turning on the vacuum comes round, full it must remain; and if there is overflow the nuisance must be endured. This would be found intolerable in English houses, where the perfect control of the watercloset rests with the user. Capt. Liernur proposes refinements, such as a moveable lining to his pan, that it may be cleaned, which is unnecessary in the English closet. Additions to the receptacle, in the form of a self-acting shallow pan apparatus to contain a small volume of water, is to be added; this shallow pan to hang vertically when not in use, but to rise into a horizontal position so as to form a false bottom when in use. Standing in front of the seat is to raise the pan and fill it with

water; moving from the seat is to permit it to fall down again and discharge the contents. Our experience is that self-acting apparatus soon ceases to have any action. The excreta which is pumped to the central station is in a fluid state necessarily, and is put into barrels and sent away to the country, involving trouble, cost, and inconvenience in several forms. The manure is too rich to distribute over grass-land in very dry weather without dilution, and it is too bulky to carry long distances. It is proposed to dry it; this process must, however, greatly reduce any remuneration to be obtained by sale. At present farmers have tried the manure, and have paid at a rate of 8d. per 32 gallons, or 6s. 8d. per ton; but this price was soon abandoned, the price being reduced to 2d. per 32 gallons, or 1s. 8d. per ton; and ultimately, after further trial, this arrangement ceased, as it was found to be necessary to remove the excreta daily or at other short intervals, because it was not convenient for the farmer either to store it or to use it; and in winter, during frost, the barrels in store were frozen and burst.*

REMARKS ON THE PNEUMATIC SYSTEM.

Captain Liernur has been particularly fortunate in having the manure which his system produces tried in Holland, as the use, application, and storage of liquid-manure is much better understood there than in England. A considerable number of the farmers in Holland grow no straw, consequently, the manure made by the cattle in winter has to be utilized in a liquid state. In England this liquid-manure is generally absorbed by the straw, or by other bedding upon which the cattle stand. Some 20 years ago there was a general movement amongst English farmers for applying the drainage from farm-yards to the land, and tanks, pumps, and liquid-manure carts were, for a time, in great request; but the application of this farm-sewage produced so little result in proportion to the cost, that pumps and carts for this purpose are now seldom used upon arable farms. We are confident that the liquid which is collected at such cost in barrels would find no ready sale in England, even at a very low price, and we further believe that any English farmer agreeing to take it continuously from any town would not only not pay anything for it, but would certainly charge something considerable for his trouble and for the expence of removal.

If the towns of Holland, or portions of such towns, by reason of peculiarities of site and climate, cannot be sewered on English principles, and if the pneumatic system is as cheap as any of the moveable pail systems, it may be the best under such conditions for Holland, because if worked in accordance with the rules laid down the excreta will be removed daily without the intervention, trouble, and dirt involved in the pail system. The pneumatic system only deals, however, with a small fraction of the refuse to be removed from houses leaving all other forms of refuse to be dealt with in the ordinary way, so that Dutch town-sewage must flow into the rivers and canals as now, to pollute the water-supply; or,

^{*} Note.—See Appendix No. 4, pages 61 to 70.

some complicated mode of intercepting it must be provided at an additional cost to the local authorities.

The pneumatic system is ingenious, but it is complicated in its construction and working arrangements; and, consequently it is liable to derangements which are sometimes difficult to mend. We do not know one English town in which the apparatus if

adopted would be other than a costly toy.

As may be imagined, when the nature of the arrangements and complications are considered, the pneumatic apparatus gets out of order, the slightest crack in any pipe or pipe-joint will reduce the force of the partial vacuum, and even where all the apparatus remains sound the closet-pans may not be emptied; and, in fact, neither the pipes nor the pans ever are entirely emptied. The power of air and water to remove solids through pipes being as their relative weights and velocity, and air is to water, by weight, about as 800 to 1.

TOWN SEWAGE: ITS TREATMENT AND CHARACTERISTICS.

Town sewage is water holding in solution and having in suspension certain ingredients which render the water objectionable to the senses of sight and smell and unfit for domestic purposes.

The volume of sewage in any town is in proportion to the water used and expended for domestic and manufacturing purposes, with

subsoil-water and occasional dilution by rain.

Where waterclosets are in general use human excreta is added; but though this in itself is rich in manurial ingredients and is also liable to become highly polluting, it must ever be a small fraction

of the whole volume of sewage—about one hundredth.

In the manufacturing districts sewage is largely mixed with the waste ingredients used. Skinners, tanners, dyers, bleachers, brewers, brassfounders, tinplate makers, japanners, wool and woollen goods washing and scouring, chemical works, and paper works, with other forms of manufactures, pollute large volumes of water, to the extent of entire rivers, as in the Aire and Calder in the West Riding of Yorkshire, and in the Mersey and Ribble basins of Lancashire. In the 6th Report of the Rivers Pollution Commission, 1874; a map shows the several localities.

All chemical treatment of sewage, by patented processes or otherwise, aims at deodorisation; that is, at clarification and purification. The processes are reported to take from sewage turbidity, colour, and scent; but no such process has ever restored sewage water to its original purity, though most of the suspended solids may have been removed, the salts of sewage remain, and generally

some of the chemicals, mixed with the water.

The sewage of a town, in which there are no manufactures or dyeworks, is a turbid liquid, bluish grey in colour, having the scent of stale cabbage water rather than of human excrement; in warm weather stagnant sewage becomes offensive, having the stench of rotten eggs; when allowed to stand exposed it does not become clear, but ferments, and if confined in sewers or covered

tanks becomes dangerous to human health, though not to such an extent as the offensiveness may be taken to indicate. When at its worst, on being brought into the open air, men work amongst it without any apparent injury to their health. The only safe way to utilize sewage is, however, by a daily application of it to land whilst it is comparatively fresh, as at Bedford, Aldershot, Carlisle, Doncaster, Chorley in Lancashire, Leamington, Rugby, and other places where sewage irrigation has been established and the sewers transmit in a continuous stream the daily volume.

Receiving sewage in tanks to abstract the solids will add to the impurity and offensiveness of the fluid if there is any lengthened retention, or if the tanks are not rigidly cleansed at short intervals, so as to remove any of the leaven of putridity from the surfaces. All sewage-tanks should be simple in form and construction, the material should be either of a vitreous character on the surfaces, such as glazed bricks, or of Portland concrete; no sewage-tank should be arched or vaulted over. There may be an open-sided shed louvered at the ridge, and the area of land occupied by both yard and tanks should be fenced in.

The sludge separated from sewage contains from 80 to 90 per cent. of water, and if deposited on the surface in this state it will not dry in any reasonable length of time, but will skin over and remain wet. Artificial drying is not practicable on account of the cost. Mixing with dry ashes and street-sweepings appears to answer best.

UNVENTILATED FOUL SEWERS AND SEWAGE TANKS DANGEROUS.

Foul sewers and foul vaulted sewage-tanks, if unventilated, will contain carbonic acid gas, and will give off sulphuretted hydrogen, both of these gases being generated from decaying vegetable and animal matters. A complete and perfect disinfection of sewage and sewage deposit by the addition of any known materials, solid or fluid, would be so costly as to be impracticable, and the materials so disinfected would have no equivalent increase in commercial value. To completely disinfect one cubic foot of sewage-sludge and excreta would cost, in the materials, about 1s. or 27s. per ton.*

CARELESSLY CLEANSING SEWERS DURING PERIODS OF SICKNESS DANGEROUS.

Cleansing the putrid refuse from unventilated sewers or from covered tanks is a dangerous process, men having fallen dead during the operation. A sewer or tank full of refuse is dangerous, but when first emptied, and for some time after, there may be the greatest danger, as the sides and bottom are coated with putrid leaven and the increased cubic space within is filled by highly concentrated gases and effluvium, consisting partly of floating particles suspended in the air. When there are foul sewers and cesspools where disease, such as typhus or typhoid, breaks out, it is then most dangerous to attempt cleansing unless the sick are first removed and the greatest precautions in disinfecting are taken.

DETAILS OF THE MODES OF DEALING WITH SEWAGE.

The application of town sewage to land is shown in this report to be the cheapest mode of disposing of it. The first cost of purchasing land for a sewage farm, of preparing this land to receive and filter sewage, and of constructing the necessary works and machinery, may require a rate in aid during the term allowed for repayment of the capital; but in most cases; where the sewage can be applied at a reasonable cost, by gravitation, so far as our investigations have been extended, there will be an available income from the farm at the termination of the temporary debt.

Sewage irrigation should in all cases be practised where there is land to be obtained, and the prospect of a balance of income in its favour, as sewage-grown grass is wholesome, and when used for dairy-cow feeding produces good milk, and affords employment

to a large number of labourers.

The application of sewage to land need not in any case produce a swamp, nor generate malaria, as the volume of sewage applied at any period should be delivered in a thin film, such as the land can absorb at once; that is, within a few hours of its delivery.

Sewage should not in any case drench the land to which it is applied as is usual with water irrigations, where extensive areas are laid under water for several days at a time. The volume of sewage from any town being known, the sewage-farm should be from 10 to 15 per cent. greater than the area required for one week, and no more than one tenth of the area of a sewage-farm should ever be under sewage at one time.

A wet season is not, as a rule, detrimental to a sewage-farm. In a wet season the value of sewage grown grass is, however, reduced in value because there is more difficulty in removing crops

from the ground.

RENT OF LAND USED FOR SEWAGE IRRIGATION EXCESSIVE.

At Croydon some 515 acres of land are under irrigation, the population being about 56,000. This is at a rate of near 10 acres for each 1,000; or about one acre to 100. The land in use had an average rental of 26s. to 30s. before the Croydon Local Board of Health required it; the rent now paid averages 10l. per acre per annum.*

Examples of Sewage Irrigation.

Analyses of crude and purified sewage, at the places named, are given in Appendix No. 5, pages Nos. 77-102:—

Edinburgh, Craigentinny	Banbury.
Meadows.	Warwick.
Barking, Lodge Farm.	Worthing.
Aldershot Farm.	Norwood.
Carlisle.	Croydon.
Penrith.	Woking.
Rughy	

^{*} Note.—A sewage-farm will not bear a rent of 10l. per acre. About half this sum is as much as should be paid if the income is to cover the expenditure.

Analyses of town sewage having been so recently made for the special purpose of informing Parliament, that we did not consider it necessary to again incur the costs of special analyses being made for our Report; but we have deemed it proper to have samples of the most recent specimens of manipulated sewage-sludge analysed, and the results will be found in the Report by Dr. A. Voelcker, F.R.S., pages 40-43, and in Appendices Nos. 1, 2, 3, 4.

A sewage-farm should be so laid out and managed that a sufficient area of land shall be under sewage every day in the year, winter and summer; and as town-sewage is seldom below 40 degrees in temperature, irrigation can be carried on. And if sewage should freeze on the surface of land which is without crop no injury is done, and when thaw sets in absorption takes place.

The mode of laying out a sewage-farm cannot be fully described in this report, but see the maps and diagrams for partial elucidation. As a rule it may be stated that the works should be simple in character that they may be cheap in construction. Good examples may be seen at Doncaster, at Bedford, at Leamington, and at Aldershot.

Permanent sewage-carriers should contain the land and be laid so as to be level, the grade of the land being provided for by vertical steps regulated by stops, overflows, and wash-outs; sidejunctions to be provided on the lower sides of the carriers to draw off sewage for distribution over the land. If a permanent sewagecarrier is laid with a fall, it will be impracticable to block the flow at any point and preserve an even surface, as sewage blocked in a sloping channel would flood over the point of stoppage; hence the necessity for level lines at the surface.

Tributary-carriers may be made by a plough, the cross-sectional form and the gradient being suited to the character of the soil; the larger carriers may have a grade of 1 in 400; the smaller or "herring-bone lines" may have a grade of 1 in 300. These temporary carriers will be broken up with the plough at intervals,

and be renewed as required.

Crude sewage can be used under certain conditions to warp the land; that is, the sewage with all the sediment it will carry may be passed along the carriers to be incorporated with the soil by being ploughed in, and the water of sewage may in some cases be made to carry an extra weight of silt.

The solids of sewage, as also manure made on the farm at the cattle sheds, may be used on some farms with advantage, as it does not follow that liquid sewage will in all cases supply manure

sufficient.

During dry seasons the whole of the water applied in irrigation of free soils is absorbed or evaporated, the drains being absolutely free from any outflow. At all periods evaporation and absorption dispose of a large percentage of the water; and if the land is deep drained and well cultivated, the outflowing water from the drains is free from colour and scent; and if passed into a water-course does not taint the bed of the stream nor produce sewage growth so offensive in sewage polluted streams.

Where the area and surface slope of a sewage farm is favourable, intercepting drains may bring the once filtered sewage to the surface and so allow of a second or a third filtration. In a dry season there will be an advantage in this arrangement. Where the land is marl or clay this mode of irrigation will be specially advantageous, as the main purpose of a sewage-farm is to act as a sewage-filter and purifier, and the more completely this filtering is performed the better will be the results.

Land may be prepared to filter sewage, as suggested by the Rivers Pollution Commissioners. (Mersey and Ribble Basins, 1st Report, pp. 60-70.) Where small areas of land are alone available this mode of purifying sewage will be advantageous. The crude sewage should have suspended solids separated in tanks that the clarified fluid may more readily filter through the least area. A good example of sewage filtering through land on a working scale

may be seen at Kendal.

AREA OF LAND REQUIRED FOR A SEWAGE-FARM WILL DEPEND ON LOCAL CONDITIONS.

The area of land required for a sewage-farm will be governed in a great measure by the character of the subsoil, as if it is very porous or otherwise; as also by the volume of sewage and subsoil-water in proportion to the population. At Doncaster, with a sewage-farm of 264 acres and a population of 20,000, the average 160 here daily flow of sewage being about 600,000 gallons, 120 acres of land of a light sandy and open character have for three years absorbed the entire sewage, only about five acres at any one time being under sewage, and one acre has occasionally absorbed the entire volume of one day. At Croydon about one acre to each 100 of population has been provided. For a population of 60,000 there are about 15,000 waterclosets in use; or, one to four of the inhabitants. There are the contents of 25 waterclosets in 20 tons of sewage each day; or, about 7,000 tons of sewage per acre per annum.

Small fields enclosed by large fences will be detrimental to sewage farming; land which is open and without inner fences. having a uniform surface and gentle slope to the south, will be most advantageous. Good roads will, of course, as in any other case, be an advantage; but it will neither be desirable nor necessary to construct many roads of a permanent character through and over a sewage-farm, as the land, if well laid out and properly

drained, may be carted upon to remove the crops.

ITALIAN RYE-GRASS THE BEST CROP UNDER SEWAGE.

Italian-rye-grass is probably in all respects the most advantageous crop to be grown under sewage, as it absorbs the largest volume of sewage, occupies the soil so as to choke down weeds, comes early into the market in spring, continues through the summer and autumn, bearing from five to as many as seven cuttings in the year, and producing from 30 to 50 tons of wholesome grass upon each acre. The area placed under this crop must,

however, have reference to local means of consumption, as the young grass will not keep nor bear long carriage. It is most profitable for feeding milch cows. A dairy and a sewage farm should, therefore, wherever practicable, be associated. In a dry and warm summer good hay may be made, which will be sweet and wholesome.* For full details of experiments with sewage grown grass, meadow and Italian, and for analyses of the milk produced, see the Official Report, Royal Commission appointed to inquire into the best mode of distributing the sewage of towns and applying it to beneficial and profitable uses. See also Appendix No. 7.

A Portion of a Sewage-farm should be deep drained to act as a Land-filter.

A portion of each farm should be specially deep-drained and prepared for land-filtering the sewage during winter or wet weather. When these filters are laid out in raised beds, some roots and vegetables can be cultivated with success, as the sewage generally flows down the channels. But in times of flood and storms the sewage may rise above the beds, so that it appears oziers, which would not be damaged by being flooded for days, may be the safest and therefore the most profitable crops to grow upon them.

Experience has proved that each day's sewage may be disposed of throughout the year so as not to cause any nuisance. Land well drained, properly laid out and managed, does not swamp at the surface, neither does it choke in the subsoil, as in fallow-land oxydation goes on betwixt the intervals of irrigation, and at any time the few grains of matter extracted from the sewage-waters are only a homeopathic dose to the land compared with the bulk of soil, six feet in depth. It is a few grains of salt and organic matter extracted from the sewage which remain for the use of the plants, the water evaporating or flowing from the drains. In dry seasons, for weeks at a time, the drains deliver very little water.

DRAINS AND WATERCLOSETS.

Drains must not traverse the basements of houses, but must commence at an outside wall and be fully ventilated. Water-closets must not be within the body of a house, but against an external wall, the soil-pipe being ventilated above the roof, with an open top, so as to ventilate fully, the watercloset room having full and free ventilation at the ceiling. The main sewers must be true in line, having smooth and even gradients, and be fully ventilated. The water supply must be constant and abundant, laid on to each house and to each watercloset; contamination by sewage gas within dwelling-houses will then be practically impossible.

Sewage is the waste-water from towns and the polluted water and liquids from manufactures. Where the privy, cesspit, and cesspool are retained the corrupted fluids from these pass into the

^{*} Note.—July 1876. On the Doncaster sewage-farm 18 acres of Italian rye-grass have been cut (about 9 tons green) and made into hay (about $2\frac{1}{2}$ tons per acre), or some 45 tons of hay from one cutting alone.

Where waterclosets are used drains and sewers remove the contents at once.

Sewage is injurious in proportion to its age and putridity. Fresh sewage, if removed day by day, does not, in that time, become putrid; and, consequently, is not so injurious to health as

putrid sewage is.

In towns completely sewered and drained, and fully supplied with water and waterclosets, there is an unceasing flow along the sewers to the outlet, and the strength of the sewage varies during the day in proportion to the use of water and of waterclosets. The flow is greatest in the morning, at noon, and in the evening. At night the sewers deliver almost pure water, consisting of waste

from leaking pipes and taps, with subsoil water.

Where waterclosets are in full use, as in London (about 700,000), in Croydon (15,000), in Leamington (about 8,370), in Harrogate (about 1,620), in Cheltenham (about 8,500), and in like proportion in some other towns, the entire of the polluted fluids, with the effete matter of the watercloset, passes at once to the common outlet. The London sewage is at present wasted into the river Thames; but at Croydon, Leamington, Harrogate, and Cheltenham the sewage is purified by irrigation, in each case

producing useful crops of grass and vegetables.

Where towns are situate on the sea or on the estuaries of tidal rivers sewage is wasted, as at Brighton, at Liverpool, at Sunderland, and even at Edinburgh, where the Water of Leith intercepting sewer discharges the sewage from a population of about 100,000 by a cast-iron outlet direct into the Frith of Forth. When sewage shall be wasted in preference to utilising it, must depend upon local conditions. The waste of sewage must not, however, produce a nuisance injurious to health, and this wasting of it certainly ought to be cheaper than using it under any of the precipitating and chemical or irrigating processes at present known.

CLARIFICATION OF SEWAGE.

Clarification by deposition in tanks and treatment by chemicals remove detritus and suspended matters from sewage, but, as explained, will not fully purify the fluid. This removal of the solids will, however, be an advantage, as a vast mass of matter liable to choke the bed and banks of a stream or river will be removed, which, when allowed to accumulate, becomes putrid and offensive. The streams in Lancashire and Yorkshire are so fully occupied, and water is of such importance, that the manufacturers must have it, though dirty; steam-boilers being specially constructed to enable steam to be generated from dirty water. The cost of treating sewage in tanks and by chemicals appears to be about 1,500l. per annum for each 1,000,000, or 150l. for each 100,000 gallons per day. The cost is therefore in round numbers about 3ths of a farthing per ton of the sewage so treated. Any income realised by the sale of the extracted and treated sludge will be in diminution of this cost.

The gross cost of purifying sewage by irrigation is, per ton, at Doncaster $\frac{2}{6}\frac{3}{4}$ of a penny, at Bedford $\frac{5}{6}\frac{1}{4}$ of a penny, at Leamington $\frac{3}{6}\frac{8}{4}$ of a penny, at Cheltenham $\frac{19}{64}$ of a penny, and at Banbury $\frac{4}{6}\frac{8}{4}$ of a penny. These farms may be accepted as fair samples of thus

utilising sewage.

The use of sewage in agriculture is comparatively new, and the best mode has not in all cases been practised. We, however, indicate Aldershot, Bedford, Doncaster, Learnington, Wolverhampton, and Wrexham as good examples. At Lemington Lord Warwick leases the sewage to be used upon a portion of his estate, and at Aldershot, Wrexham, and at Doncaster the sewage and the land are leased, and are worked independently by gentlemen of intelligence, who make such experiments as they think proper and vary their modes of culture as best suits the sewage, the land, and the crops to be grown, There is also the incentive to make the most of the land, which is not always the case where a farm is managed through the intervention of a committee; we therefore look for a fuller development of sewage farming in this direction; namely, letting both sewage and land on favourable terms, under restrictions to purify the sewage and cause no nuisance.

Examples of tank precipitation and chemical treatment at Birmingham, Bradford, Coventry, and Leeds, and of the pail system at Rochdale, Halifax, and at other places are described in this Report, Appendix No. 3, pages 52–59. The pneumatic system is described by the authorities of Amsterdam, Appendix

No. 4, pages 62-66.

The attempts to economise in town scavenging and sewering by removing human excreta separately has been a failure; by the dry-earth system, the Goux system, the Rochdale pail system, or by any other of the patented systems, so far as are known to us; the local costs have been largely increased, and the local nuisances also, in proportion to the time of retention of the excreta before removal; there is also the inconvenience suffered by trespass on the privacy of the household.

DETAILS AS TO IRRIGATION BY TOWN SEWAGE.

As we recommend the application of town sewage to land, we at the same time wish to guard against some extravagant expectations of the agricultural benefits it will confer, which are held and

advocated by a few zealous and enthusiastic theorists.

The continuous application of town sewage to all soils is by no means an unalloyed benefit; as in some cases and seasons, and especially upon clay-land, it may be rather injurious than otherwise. Very few crops are actually benefited by the direct application of sewage upon a stiff and retentive soil; indeed, Italian rye-grass, cabbage, and mangold-wurtzel, seem to be the only farm crops that persistently flourish upon any soils, heavy or light, under continual doses of town sewage.

No growing crop, save natural grass, should be sewaged during

the depth of winter; and for potatoes, turnips, most vegetables, and certainly for all pulse and cereals, the land ought rather to be enriched by frequent irrigation in the preceding season, than treated with sewage when these crops are growing; except in times of great drought, and even then care is requisite. A very limited experience soon teaches us that the purification of a constant flow of sewage, and which is frequently greatest when least wanted on the farm must bring certain difficulties in its train. The cultivation of sewaged land, for instance, requires more than double the amount of manual labour which is usually employed upon arable land, and more horses must be kept than upon an ordinary farm. The amount of capital, even where the produce is sold off as soon as grown, must be greatly in excess of that required for the general ordinary cultivation of the soil; while to properly stock and work a sewage-farm upon which the main produce is consumed, quite five times the usual amount of money will be needed. One of the greatest difficulties is to keep the sewaged land clean, as not only does every seed and the minutest portion of a root-weed grow, but sewage itself often contains the seeds of numerous weeds which have been washed down from the fodder and straw of stables and cowhouses in towns.

There can be no doubt now, after the experience of some years, that the land best adapted for sewage irrigation is a warm friable loam. The only instance in which town sewage irrigation is a decided financial success is that of the Craigentinny Meadows, at Edinburgh. These meadows are, however, in reality for the most part only a deposit of sea sand, washed and blown from the adjoining estuary, and the main produce grown is nothing more nor less than luxuriant couch-grass. The enormous amount of coarse forage which is produced from such a naturally sterile soil shows the fertilizing properties of town-sewage, and also points still more distinctly to the fact that a sewage-farm should consist of land through which the sewage can readily filter. It is strange that although deluges of crude town-sewage have been poured upon portions of these Craigentinny Meadows for 200 years, the discoloration of the sandy soil only extends a few inches below the surface, and that at the depth of a foot the sand appears as bright and clean as that upon the adjoining sea shore.

It has been contended that if more land is allowed for a given volume of sewage, clay soils, when properly drained, will be equally adapted for town sewage irrigation. No doubt, if similar volumes of sewage are filtered slowly through a large area of well-drained clay, and quickly through a small area of sand or gravel, a more thorough absorption of the manurial elements from the sewage will be made by the clay than by the porous soils. But clay lands are naturally cold, they dislike wet, and will be at the best only poor filter-beds; and when sodden with rain-water the added sewage is apt to pond on the surface rather than to soak gradually into the already heavily wetted soil. After heavy dressings of sewage in parching weather

the surface of clay lands may be so baked and case-hardened as considerably to retard the growth of any plant; and if there is no crop upon the ground the land becomes solidified, and may then be seen coated with a nasty greasy film that is almost impervious to water; or, at other times, the clay cracks so that the crude-sewage passes in small streams directly into the under drains

without being even clarified.

This brings us to consider the various methods of underdraining as practised at different sewage-farms we have inspected. In one instance we found that common farm underdrains which had been laid in a retentive soil were being taken up, as the crude sewage too readily found access to them, and flowed out unpurified. Upon another sewage-farm some stiff clay land which had been recently drained 6 feet deep was so cracked by heat and drought, that the sewage flowed from the surface into the drains without effecting any practical irrigation; and, although intercepted and brought to the top again, the sewage as rapidly disappeared, and at the land drains outlet the effluent was hardly distinguishable in colour and smell from that of the sewage when first applied to the land.

There seems no doubt that even the lightest soils should have a few deep underdrains, as at Doncaster, and Heathcote farm, Warwick, so as to prevent the sewage-water from lodging in the subsoil. All land of medium staple should be thoroughly underdrained, and clays require the drains to be multiplied, so that the interval between them shall not be more than 15 feet; and care should be taken that the drains are so formed that no sewage-water can flow vertically into them. To prevent this, upon the top of the drain-pipes, a foot of the most retentive portion of the soil should be damped or puddled, and tightly rammed down, so that the sewage-water after percolating through the subsoil shall flow horizontally into the drains, and not rush into the drain-pipes through the loose mould or cracked clay directly from the surface.

As already observed, the chief produce of a large sewage-farm, which is to earn the most money, must be Italian rye-grass; because it is a plant which luxuriates in moisture, and feeds with singular avidity upon all kinds of liquid-manure: and the quantity of such liquid-manure given need only be limited by the means at hand for its ready disposal. But the demand for cut grass is so variable, that this is not a very easy task. Rye-grass, even when heavily sewaged, grows most rapidly in wet weather: consequently when there is much rain, a greater crop is produced, when it is most difficult to deal with; and, as there is at such times a more plentiful supply of similar green food on other farms in the district, the demand for the rye-grass of the sewage-farm is not so extensive. In a damp season it is next to impossible to make sewage-grown grass into hay, as the soil is sodden with rain-water and sewage, and the young undergrowth of grass so soon springs up that the land must be cleared of the cut grass to enable the next crop to grow; and any removal of the cut grass to other ground for the purpose of making hay, even if a suitable site is conveniently situated, will be very costly. It therefore appears to us that upon an extensive sewage-farm, where a constant demand for all the rye-grass grown cannot be depended on, a machine for making hay by artificial means should be

provided.

Drying heavy crops of sewage-grown grass by artificial heat must; however, be a slow, costly, and tiresome process, and should never be resorted to unless necessity compelled this form of dealing with it, and when it appears to be the only way to prevent the total loss of the crop during continuous wet weather. We believe the best machine for the purpose is one which is the invention of Mr. W. A. Gibbs, of Gilwell Park, Essex, to whom the gold medal of the Society of Arts was awarded a few years ago for the ingenious apparatus which bears his name.

The length of time which a plant of irrigated Italian rye-grass lasts varies considerably. On some farms it has been ploughed up after one year's cropping. On other farms the practice has been to keep it down so long as there is a good plant, and it can be kept free from weeds. By fresh seed being sown among the old plants, Italian rye-grass thus treated, has lasted seven or eight years. Its more usual duration is, however, from two to three years, and as there seems to be a common belief that this plant can only produce a certain weight of grass, it may follow that the quicker the growth the more readily the plant will be exhausted.

It was a matter of pleasure and some surprise to us to find how town sewage benefited two such distinctly different forage plants as Italian rye-grass and lucerne. The latter, it is well known, grows with one deep tap-root, while the rye-grass has a dense mass of fibrous rootlets, which extend upon and over the surface At Paris the favourite green crop for sewage appeared to be lucerne, which at the time of our inspection seemed to flourish remarkably well under sewage irrigation, and to produce heavy crops of the most valuable provender. The gravelly soil and the warm climate of the district no doubt are particularly adapted for sewage irrigation, and this may be the reason why a direct application of sewage to the growth of vegetables seems to answer better than with us. The culture of Italian rye-grass has only recently been introduced on the Paris sewage-farm, but its success is so marked that it may possibly take the place of lucerne as the staple green crop.

English farmers have by some been considered over cautious in not embarking their capital in the costly cultivation of sewage-farms, but on our inspection of the Paris farms it appeared much more strange to us that so many French cultivators, whose little patches of land intersect the Paris sewage-farm, had not all availed themselves of the free use of the sewage. Many, no doubt, have done so, but it was difficult to comprehend how some of the farmers preferred to grow their miserably small crops when the adjoining

land upon which the sewage flowed was producing the most

abundant yield.

It may be quite true that town sewage contains all the manure that most plants require, but as these elements of fertility are dispersed through a volume of water many times greater than any crop can absorb, and certainly much larger than it naturally requires, it follows that the manure is not presented to the plant in the most acceptable form. We have been also assured by a gentleman of vast experience that the long continued application of sewage to the same land fails to produce the like beneficial effect as when it was first used. It, therefore, appears most desirable that the application of sewage should occasionally be supplemented with some solid manure. Cows are the most suitable and best paying animals for consuming the produce and manufacturing manure upon a sewage-farm, and cows should always form the chief portion of its live stock. The successful management of animals, and the proper cultivation of crops under ordinary circumstances, require a fair amount of intelligence and experience; but successfully to carry out all the details of these matters upon a sewage-farm, where there is so little to guide the practical farmer, and so much to confound his past experience and upset his previous calculations, is indeed a hard task. And as most sewage-farms are at present under the control of everchanging town councils and local boards whose members must as a rule be ignorant of practical agriculture, and whose theories upon the subject may be wild and visionary—is it surprising that such poor returns have hitherto resulted from the application of town-sewage to the growth of crops?

Disappointment has therefore been expressed at the poor financial results of sewage-farms. Agriculture is never a specially lucrative business, and during the last few years it is probable that strictly accurate accounts would prove that very little profit has been derived from the ordinary cultivation of arable land. Farms to which town-sewage is applied have invariably many The rent, except unfavourable circumstances to contend with. where the local authority has land of its own, is certain to be extravagant; the application of sewage is often too costly; the management is frequently changeable and faulty, and the prejudice against the produce of the farm is, in some districts, obstinate and widespread. But where a fair rent is charged for suitable land, the sewage is cheaply and regularly delivered, and a good market is close at hand, there is no reason to doubt that the return for capital judiciously expended upon sewage-farms will produce a higher rate of interest than the money invested by the

majority of the tillage farmers throughout the country.

ABSTRACTS

From separate Reports. See Appendices Nos. 1, 2, 3.

The relative costs of sewage irrigation, where the sewage gravitates to the farms, are shown in the abstracts from the reports on Edinburgh, Blackburn, Cheltenham, Chorley (Lancashire), Harrogate, Merthyr-Tydfil, Tunbridge-Wells, Rugby, Wolverhampton, West Derby, and Wrexham. The relative cost of sewage irrigation, where sewage is pumped, is shown in abstracts from reports on Banbury, Bedford, Doncaster, Leamington, and Warwick, whilst the cost of land filtration and irrigation is shown as practised at Kendal, and the cost of the precipitating chemical and mechanical processes are shown in the abstracts from the reports on Kendal, Birmingham, Bolton, Bradford, Coventry, Leeds, Halifax, and Rochdale.

The abstracts contain statistics to which attention should be given. The returns are not however perfect, as the local works are not yet complete, and we could not, in all cases, obtain accurate returns of the costs of scavenging; the weight of refuse removed; or, the cost of removal:—

COST OF DEALING WITH SEWAGE BY IRRIGATION.

	B	ANBUR	Y.			
Population (about)	-	-	-	-	-	12,000
Rateable value	-	-	-	-	1	234,104
Houses -	-	-	-	-	-	3,485
Waterclosets -	-	-	-	-	-	2,485
Expenses in	curred t	to DISP	ose of	the Sew	AGE.	
Outlet works, tanks,	and pur	nping 1	nain	-	-	£5,500
The YEARLY C						
Capital 5,500l. at 6' interest. Yearly in Cost of pumping sev	stalmen	it -		-	-	£330
expenses of farm		-	-	-	-	1,281
Less produce o	f farm	-	2			1,611 1,451
				4		£160

The mean daily flow of the sewage is about 320,000 gallons = 1,429 tons, or 521,585 tons yearly. The annual cost to the Local Board in disposing of the sewage is 1,611l., or at the rate of $\frac{48}{64}$ ths of a penny per ton; they

^{*} Money is advanced by the Public Works Loan Commissioners at $3\frac{1}{2}$ per cent., which, to be repaid in 30 years, amounts to 5l. 8s. 9d. per cent. Six per cent. is however here used for the sake of uniformity and the purpose of comparison to cover incidentals and depreciation.

Local Boards do not necessarily borrow from the Public Works Loan Commissioners, neither do they, in all cases, repay the debt in 30 years, as the Local Government Act, 1875, provides for a term not exceeding 60 years, and this lengthened term, when accepted, will lower the rate of interest, but the cost of maintenance cannot be ascertained with accuracy.

receive for the produce 1,451l., an amount equal to $\frac{4.4}{6.4}$ ths of a penny per ton of sewage, and consequently lose 160l., or about $\frac{4.4}{6.4}$ ths of a penny per ton, or at the rate of 3d. per head of the population, or about 1d. in the pound on the rateable value of the town.

The capital, 5,500l, will be paid off, and then the annual payment of 330l will cease, and the rates will thus be relieved to the extent of about $2\frac{1}{4}d$ in the

pound on the present rateable value.

The volume of sewage is at a rate of 27 gallons per head of the population, or about eight persons to every ton of sewage.

BEDFORD.

Population (about) Rateable value		18,000 65,000	
Houses	mile	3,500 3,000	
Capital Expended on Works to dispose of Outlet works, pumping station, and laying out fa			
The YEARLY COST of DISPOSING of the S	EWAGE.		
Capital 9,2001. at 6 per cent. to be repaid in year instalments		s. d.	
Paid for labour, tradesmen bills, coals, &c. in wor ing sewage farm, including amount of rent, rat and taxes, and also cost of seed -		7 8	
BANBURY.	3,832	7 8	
Less amount received for sale of stock and crops	-3,461 £371	$\begin{array}{c c} 6 & 0 \\ \hline 1 & 8 \end{array}$	

The daily mean flow of sewage is about 700,000 gallons = 3,125 tons, or

1,140,625 tons yearly.

The annual cost to the Corporation in disposing of the sewage is 3.832l.7s.8d., or at a rate of $\frac{51}{64}$ of a penny per ton; they receive for the produce 3.461l.6s., an amount equal to $\frac{46}{64}$ of a penny per ton of sewage, and consequently lose 371l.1s.8d., or about $\frac{5}{64}$ of a penny per ton; or at the rate of $4\frac{3}{4}d.$ per head of the population, or 1d. in the pound on the rateable value of the borough.

The volume of sewage is at the rate of 39 gallons per head of the population,

or about six persons to every ton of sewage.

The capital 9,200*l*, will be paid off when the rates will be relieved to the extent of about 2*d*, in the pound on the present rateable value.

	BLA	CKBU	RN.			
Population (about)	-		-	-	-	90,000
Rateable value		-			£	235,127
Houses	-		-	-	-	16,700
Waterclosets -	-	-	-	o de en	-	730
Privies and middens		-		11/21/4	-	10,574
Privies on "pail" syst	em		The state of	61 17 box	0.70	2,690
Ashpits -	A . 10 m	= 011	0/10 7/10	1 (11	-	5,287
The yearly cost of clear	nsing th	e priv	ries on b	oth		
systems is -	-	-		- £5	,641	
Amount received for t	he refus	e	no Anno	- 1	,806	an service in
				-		
Consequent loss on rea	moval		10000	- £3	,835	
				_	_	

Or at a rate of $10\frac{1}{4}d$. per head of the population, or about $3\frac{3}{4}d$. in the pound on the rateable value of the borough.

CAPITAL EXPENDED in DISPOSING of the SEWAGE.

Damages and cost in Chancery suit, and action at la	w-	£12,000
Cost of obtaining private Act	-	6,500
Costs of outfall sewer, and laying out sewage-farm	at	
Pleasington	-	11,600
Purchase of land at Samlesbury, including expenses	of	
arbitration and easements	-	*69,500
Cost of laying out this farm for sewage irrigation	-	*7,650
* * *		£ $107,250$

N.B.—* The sums marked thus are for land and works which have not come into profitable use at present.

The YEARLY COST of DISPOSING of the SEWAGE.

Capital 107,250%. at 6 per cer	it., to	repay	principa	l and	
interest. Yearly instalmen	it -	-		-	£6,435
Rent of farm at Pleasington		-	-	-	484
Working expenses of farm	-		-	-	6,523
					13,442
Less sale of produce	-	-	-	-	5,781
					£7,661

The mean daily flow of the sewage is 1,500,000 gallons = 6,696 tons, or 2,444,040 tons yearly. The annual cost to the Town Council in disposing of the sewage is 13,442l., or at a rate of $\frac{84}{64}$ ths per ton; they receive for it in sale of produce 5,781l., an amount equal to $\frac{36}{64}$ ths of a penny per ton of sewage, and consequently lose 7,661l., an amount equal to about $\frac{45}{64}$ ths of a penny per ton, or at a rate of 1s. $8\frac{1}{4}d$. per head of population.

The yearly loss in cleansing privies - - £3,835 ,, ,, disposing of the sewage - 7,661 £11,496

or at a rate of 2s. $6\frac{1}{2}d$. per head of population, or $11\frac{1}{2}d$. in the pound on the

rateable value of the borough.

or

The borrowed capital amounting to 107,250l, and which involves an annual payment of 6,435l, will cease when the terms have been accomplished, so that the rates will be relieved (at the existing rateable value) to the extent of about $6\frac{1}{2}d$, in the pound.

The volume of sewage is at the rate of 17 gallons per head of the population,

or 14 persons to every ton of sewage.

CHELTENHAM.

Population (ab	out) -		-	-	-		15,000
Rateable value			-	-	-	- £21	17,849
Houses			-	-	-	-	8,725
Waterclosets (a	about) -		-	-	-	-	8,500
Quantity of re		oved v	early fro	om ashp	its (cub	ic	
vards)			- '		-	-	3,234
Cost of removi	ng ashes	veariv		-	-	-	£324
at the rate of 2s	. per cubi	ic yard	or abou	it 13d. p	er head	of po	pulation.

CAPITAL EXPENDED for DISPOSING of the SEWAGE.

Purchase of farm and cost of construction of works for sewage utilization - - - £18,000 The YEARLY COST of DISPOSING of the SEWAGE.

Capital 18,000l. at 6 per cent. to repay principal and interest in 30 years - Yearly instalment Cost of applying sewage to farm	£1,080
Rates and taxes	50
Cost of cleaning out sewage tanks	296
The state of the s	£1,576
Less rent obtained for the farm £800	
Amount for sewage applied to land adjoining	
the sewage carriers 156	
Amount received for sludge mixed with house-	
ash 348	
9:96 to cooling 020,007 limited by comments to interest	£1,304
Consequent loss	- £272

The daily mean flow of the sewage is 1,250,000 = 5,580 tons or 2,036,700 tons yearly. The annual cost to the Improvement Commissioners in disposing of the sewage is 1,576l., or at the rate of $\frac{19}{64}$ ths of a penny per ton; they receive for it 1,304l., an amount equal to $\frac{16}{64}$ ths of a penny per ton of sewage, and consequently lose 272l. or about $\frac{3}{64}$ ths of a penny per ton, or at a rate of $1\frac{1}{4}d$. per head of the population.

The yearly loss in cleansing ashpits - - £324 ,, ,, in disposing of the sewage - - £596

or at a rate of $3\frac{1}{4}$ per head of the population or about three-fourths of a penny in the £ on the rateable value of the district.

The volume of sewage is at the rate of 28 gallons per head of the population,

or 8 persons contribute to every ton of sewage.

The capital of 18,000*l*. will be paid off and then the annual payment of 1,080*l*. will cease, and the rates will be relieved to the extent of about $1\frac{1}{4}d$. in the pound on the present rateable value.

CHOPLEY	(Lancashire).
CHURLET	Lancasiii C).

	-		1				
Population (abo	out)	- July 1	- 3 1	et annu	water 1		20,000
Rateable value	-	-	-	-	-	-£	54,407
Houses -	-	- 3H 3G	-	- 18	-	-	4,000
Waterclosets	- 7.00	-	-	-	-	-	200
Privies and mid		-	-	-	-	-	1,600
Privies "pail"	system	(about)	-	-	-	-	700
The yearly cost	of clea	nsing th	e privi	es on b	oth sys	tems	
is -	217 115	15 17/00	-	-		-	£709
Amount receive	d for th	ne refuse	-	- Conta	WE NO	-	186
0 11		THE PERSON					0500
Consequent los	s on rei	noval	- Verna	HI-DINI	-	1700 -	£523

or at a rate of $6\frac{1}{4}d$. per head of the population or about $2\frac{1}{4}d$. in the pound on the rateable value.

EXPENSES incurred in DISPOSING of the SEWAGE.

	£6,450
Outfall sewer, laying out farm and erecting farm- buildings	4,800
Purchase and laying out of part of Kingsley's farm -	w 000
the property of the property of the second state of the second sta	£16,550

The Yearly Cost of disposing of the Sewage	
Capital 16,550l. at 6 per cent. to repay principal and interest - Yearly instalment The working expenses of the farm	£993 927
Less amount for produce sold 847 ,, rent received for part of Kingsley's farm with sewage 90	£1,920
with strage	£937 £983

The daily mean flow of the sewage is about 500,000 gallons = 2,232 tons or 814,680 tons yearly. The annual cost to the Improvement Commissioners in disposing of the sewage is 1,920l. or at the rate of $\frac{3.2}{6.4}$ ths per ton; they receive for the produce of the farm, 937l., an amount equal to about $\frac{1.5}{6.4}$ ths per ton of sewage, and consequently lose 983l. or about 17ths per ton, or at a rate of 1s. per head of the population.

The yearly loss on cleansing privies -" in disposing of the sewage £1,506

or at a rate of about 1s. 6d. per head of the population, or about 7d. in the pound on the rateable value of the district.

The volume of sewage is at a rate of 25 gallons per head of the population,

or about nine persons contribute to every ton of sewage.

The capital 16,550l. will be paid off and then the annual payment of 993l. will cease, when the rates will be relieved to the extent of about 44d. in the pound on the present rateable value.

					-		
		Don	CASTI	ER.			
Population (abo	out)		-	-	-		- 20,000
Rateable value	-	-	-	-	-		£68,721
Houses -	-	-	-	-	-		- 4,300
Waterclosets		-	-	-	-		- Not known.
Privies -	-		-	-	-		- 3,078
Quantity of refu	use ren	noved fr	om pri	ivies ye	early (t	ons) .	
Cost of cleansin	o privi	es vearly	v orat	the ra	te of		
$2s. 5\frac{1}{4}d.$ per to		- y carr	- 01 40	-	-	£539	()
Amount receive		efuse	-			310	
Amount receive	4 101 1	crusc	- A	- 5		010	
Consequent los	ss on r	emoval	_	-	-	229	
Or at the rate				or 21d	ner :		
head of the							
pound on t	he rata	ble valu	e of th	e boro	ngh.		

EXPENS							77.7
Outfall works,	inclu	ding p	oumpin	ig-stati	on, e		
pumps, pump	ping-m	ain, and	l layin	g out f	arm*		£20,000
The YEA	ARLY (Cost of	DISPO	SING	of the S	SEWAG	E.
Capital 20,0001.							
and interest.	Venr	ly inetal	ment	., 1	chaj bi	merpa	£1,200
Annual cost of				farm	- 3		300
Annual cost of	pump	ing sewa	ige to	latin	-		- 300
							1,500
Loss improved	mont fo	n form					
Less improved	rent 10	Tarm	-	•	-		- 470
							1,030

^{*} The land is part of a much larger estate which is the property of the corporation.

The daily mean flow of the sewage is about 600,000 gallons = 2,678 tons, or 977,470 tons yearly. This is pumped to a height of 52 feet. The gross annual cost to the Town Council in disposing of the sewage is 1,500l., or at a rate of about $\frac{2.3}{6.4}$ ths of a penny per ton; they receive for it (i.e., improved rent of farm) 470l., an amount equal to $\frac{7}{64}$ ths of a penny per ton of sewage, and consequently lose 1,030l. or $\frac{1.6}{64}$ ths of a penny per ton, or at a rate of 1s, $0\frac{1}{4}d$. per head of the population, or $3\frac{1}{2}d$. in the pound on the rateable value.

The yearly	loss in cl	eansing p	rivies	m- va	1 -	-	£229
,,	,, di	sposing o	f the sev	vage	11-11	-	1,030
	Total	-	-	-	-		£1.259

Or at the rate of 1s. $2\frac{3}{4}d$. per head of the population, or $4\frac{1}{2}d$. in the pound on the rateable value of the borough.

The volume of sewage is at a rate of 30 gallons per head of the population,

or about eight persons contribute to every ton of sewage.

The capital of 29,000l. will be paid off and then the annual payments of 1,740l. will cease, and the rates will be relieved to the extent of about $4\frac{1}{4}d$. in the pound on the present rateable value.

HARROGATE.			
Population (average)		12,0 50,0 1,5 1,6	000
Expenses incurred to dispose of the Sewage		rt 15	131
Outlet works, and laying out 47 acres of land at Jenny Plain Purchase of Knox Bleachfields Purchase of land at Wetherby Lane Outlet works, and laying out 13½ acres of land at Wetherby Lane Estimated cost of laying out farm of 247 acres Damages and costs in Chancery suit (about) Total	ð	£1,1 2,2 1,0 3,4 3,2 9,5	00 00 84 216 00
Total		20,5	50
The Yearly Cost for Disposing of Sewage			
Capital 20,550l. at 6 per cent. to be repaid with interest. Yearly instalment £1,23 Rent of farm of 247 acres 30 Rent and expenses of treating the sewage on the 47 acres 28	00	0 0 10	0 0 5
Less sale of produce - £569 13 1 Rent of land with sewage at Wetherley	.5	10	5
Lane 52 0 0	21	13	1
Marine la fibribility respected characteristic for the Angle of Least)3	17	4

The daily mean flow of the sewage is about 210,000 gallons, equal to 9371

tons, or about 342,187 tons yearly.

The annual cost to the Commissioners in disposing of the sewage is 1,815l. 10s. 5d., or at the rate of $\frac{81}{64}$ ths per ton; they receive for the produce 621l. 13s. 1d., an amount equal to $\frac{28}{64}$ ths of a penny per ton of sewage, and consequently lose 1,193l. 17s. 4d., or about $\frac{53}{64}$ ths of a penny per ton, or at the rate of 1s. $11\frac{3}{4}d$. per head of the population, or about $5\frac{3}{4}d$. in the pound on the rateable value of the town.

The volume of sewage is at the rate of 18 gallons per head of the population,

or about 13 persons contribute to every ton of sewage.

The capital 20,550l. will be paid off and then the annual payment of 1,233l. will cease, and the rates will thus be relieved to the extent of about 6d. in the pound on the present rateable value.

LEAMINGTON.	
Population (including the districts of Lillington and	
Milverton)	24,700
Rateable value of the borough of Leamington - £ Inhabited houses	113,400
Waterclosets, average two to a house	4,500 8,370
Quantity of refuse from privies removed yearly (cubic	0,070
yards)	3,000
Cost of cleansing privies yearly, or at the rate of	
5s. $2\frac{1}{4}d$. per cubic yard, or $7\frac{1}{2}d$. per head of the popu-	
lation, or 12d. in the pound in the rateable value -	£780
Amount received for refuse	Nil.
Capital Expended on Sewage Works.	
Outfall works	8,000
Pumping station, including engines and pumps, &c	16,239
Cleansing river	1,500
Law costs	5,000
Total	€30,739
The Yearly Cost of disposing of the Sewage	
Capital 30,7391., at 6 per cent., to repay principal &	s. d.
and interest. Yearly instalment 1,844	$6 9\frac{1}{2}$
The annual cost of pumping the sewage - 1,035	0 0
2,879	6 91
Less yearly amount received for the sewage - 450	
£2,429	6 9½
£2,429	0 92

The daily mean flow of the sewage is about 700,000 gallons, equal to 3,125 tons, or about 1,140,625 tons yearly. This sewage is pumped 130 feet high.

The gross annual cost to the Town Council in disposing of the sewage is 2,879l. 6s. $9\frac{1}{2}d$., or at a rate of $\frac{3}{6}\frac{8}{4}$ ths of a penny per ton. They receive for it 450l., an amount equal to $\frac{6}{6}\frac{4}{4}$ ths of a penny per ton of sewage, and consequently lose 2,429l. 6s. $9\frac{1}{2}d$. annually, or $\frac{3}{6}\frac{2}{4}$ ths per ton, or at a rate of 1s. $11\frac{1}{2}d$. per head of the population, or 5d. in the pound on the rateable value of the borough.

Yearly loss on cleansing the privies, per hear Yearly cost on disposing of the sewage, per		:	$\begin{array}{ccc} s. & d. \\ 0 & 7\frac{1}{4} \\ 1 & 11\frac{1}{2} \end{array}$
			$2 6\frac{3}{4}$
The yearly loss by cleansing the privies disposing of the sewage	:	-	£780 2,430
			£2,210

or about 2s. 7d. per head of the population, or $6\frac{1}{2}d$. in the pound on the rateable value of the borough.

The volume of sewage is at the rate of 28 gallons per head of the population, or about eight persons contribute to every ton of sewage.

The capital, 30,739l., will be paid off and then the annual payment of 1,844l. will cease, and the rates will thus be relieved to the extent of about 4d. in the pound on the present rateable value.

		MER	THYR-T	YDFIL.			
Population ab	out	-	-	11-7-59	Un- Un	1121	55,000
Rateable valu	е		-		-	-£	2135,000
Houses	-	-	-	-	-	-	10,778
Waterclosets	-	-	-	-	-	-	8,000
Privies	-			-	-		2.800

The privies are cleansed at the expense of the occupiers of the houses to which they belong.

CAPITAL EXPENDED on Works to DIS	POSE of the S	EWAGE.
Outfall sewer from Troedyrhiew to Ynyse	cadudug -	£16,003
Building subsidence tanks	ANY CONTRACTOR OF THE PARTY OF	388
Laying out filters and land for irrigat	ion, including	
drainage and carriers, at Troedyrhiew	Maria Santa Sa	6,015
Purchase and laying out, draining, and fe	neing common	
land at Navigation	0.200300000230	4,365
Purchase and laying out land at Ynyscad	ludug -	14,387
Purchase of Tyrybout estate	-	3,002
Purchase of Park Newydd estate -	-	9,170
(View letters and the second s		
Total -		£53,330

The YEARLY COST for DISPOSING of the SEWAG	E.
Capital, 53,330l. at 6 per cent., to repay principal and interest. Yearly instalment	£3,200
Cost of distributing the sewage, including working expenses of farm	2,392 298
Less produce of the farm	5,890 1,623
	£4,267

The mean daily flow of the sewage is 1,200,000 gallons = 5,357 tons or 1,955,305 tons yearly. The annual cost to the Local Board in disposing of the sewage is 5,890l., or at a rate of about $\frac{4.6}{6.4}$ ths of a penny per ton. They receive for the produce 1,623l., an amount equal to about $\frac{1.2}{6.4}$ ths of a penny per ton of sewage, and consequently lose 4,267l., or about $\frac{3.2}{6.4}$ ths of a penny per ton, or at the rate of about 1s. $6\frac{1}{2}d$. per head of the population, or about $7\frac{1}{2}d$. in the pound on the rateable value of the district.

The volume of sewage is at the rate of 22 gallons per head of the population,

or about 10 persons contribute to every ton of sewage.

The capital of 53,330l will be paid off and then the annual payment of 3,199l will cease, and the rates will be relieved to the extent of about $5\frac{3}{4}d$ in the pound on the present rateable value.

			RUGBY			
Population (a	bout)	-	-	-		- 8,400
Rateable valu	e	10-11	10 7-7-1	0.0 - 30		£45,000
Houses	-			11 - 1		- 1,700
Waterclosets	-	-	-	-	-	- 1,400

Capital Expended on Works for disposing of the Sewage.

Outlet works and tanks and laying out farm - £5,800

The YEARLY COST of DISPOSING of the SEWAGE.

Capital 5,800l. at 6 per c Yearly instalment	ent.,	to be repai	d w	vith inte	rest. £348	0	0
Rent of 65 acres of land			-		290	0	0
Rent of 13 acres of land	-	-	-	-	54	0	0
Less rent of land sublet	with t	he sewage		£ - 350 79	692	0	0
					429	0	0
					£263	0	0

The mean daily flow of the sewage is about 400,000 gallons = 1,785 tons, or 651,525 tons yearly. The annual cost to the Local Board of Health in disposing of the sewage is 692l., or at a rate of $\frac{17}{64}$ ths of a penny per ton; they receive an improved rent for the sewage farm, 429l., an amount equal to about $\frac{1}{64}$ ths of a penny per ton of sewage per year, and consequently lose 263l., or about $\frac{6}{64}$ ths of a penny per ton, or at a rate of $7\frac{1}{2}d$. per head of the population, or about $1\frac{1}{2}d$. in the pound on the rateable value of the district.

The volume of sewage is at the rate of 48 gallons per head of population, or

about five persons contribute to every ton of sewage.

The capital 5,800l. will be paid off, and then the annual payment of 348l. will cease, and the rates will thus be relieved to the extent of about 2d. in the pound on the present rateable value.

TUNBRIDGE-WELLS.

Population (abo	ut)	-		_	-	-	23,000
Rateable value	100000	-	-	-	-	£	142,914
Houses	-	-	-	-	-	-	5,750
Waterclosets	-	-		-	-	-	5,635

CAPITAL EXPENDED ON WORKS to DISPOSE of the SEWAGE.

Purchase of farms, law costs, arbitration penses, and compensation to tenants and of laying out farms to receive the sewage Cost of cleaning out Summer Hill Lake Costs of the Chancery suit	cost	£87,243 744 3,000	17	8
		£90,987	17	8

The YEARLY COST of DISPOSING of the SEWAGE.

Capital 90,988l. borrowed at repaid with interest. Year Cost of disposing of the sewage	ly insta	alment	-		5	0
expenses of both farms	-	-	-	8,199	0	0.
Less produce of both farms				£13,658 7,671		
				£5,987	5	0

The mean daily flow of the sewage over both farms is 650,000 gallons=2,902 tons, or 1,059,230 tons yearly. The annual cost to the Local Board in disposing of the sewage is 13,659l, or at the rate of 3d, per ton; they receive for the produce 7,671l, an amount equal to $1\frac{3}{4}d$, per ton of sewage, and consequently lose 5,988l, or about $1\frac{1}{4}d$, per ton, or at the rate of 5s, $2\frac{5}{4}d$, per head of the population, or about 10d, in the pound on the rateable value of the township.

The volume of sewage is at the rate of 28 gallons per head of the population,

or eight persons contribute to every ton of sewage.

The capital 90,988*l*. will be paid off, and then the annual payment of 5,459*l*. will cease, and the rates will thus be relieved to the extent of about $8\frac{1}{2}d$. in the pound on the present rateable value.

		- 1	WARWI	CK.			
Population (ab	out)	-	-	-	-	-	11,000
Rateable value		-		-	-		£43,339
Houses	-		-	-	-	-	2,400
Waterclosets	-	-			-	-	2,000

Capital expended to dispose of the Sewage.

Outlet works, including pumping station, engines,
pumping main, and laying out farm - £10,084 18 1

The YEARLY COST of DISPOSING of the SEWAGE.

Capital 10,084l. 18s. 1d. at 6 per cent., to repaid with interest. Yearly instalment Cost of pumping sewage	be -	£604 572		
		£1,177	9	$10\frac{1}{2}$

The mean daily flow of sewage is about 700,000 gallons = 3,125 tons, or 1,140,625 tons yearly. The annual cost to the Corporation of Warwick in disposing of the sewage has been 1,177l. 9s. $10\frac{1}{2}d$., or at the rate of three-eighths of a penny per ton, and as they do not receive any profit rent for the farm which they have sublet, they consequently lose the whole of that amount, or about 2s. $1\frac{1}{2}d$. per head of the population, or $6\frac{1}{2}d$. in the pound on the rateable value of the borough.

The volume of sewage is at a rate of 64 gallons per head of the population,

or about four persons contribute to every ton of sewage.

The capital 10,085*l*. will be paid off, when the annual payment of 605*l*. will cease, and the rates will thus be relieved to the extent of about $3\frac{1}{4}d$. in the pound on the rateable value.

WOLVERHAMPTON.

Population (about)	-	-	-	-	-	71,000
Rateable value -	-	-	-	-	- £2	210,000
Houses		-			-	14,000
Waterclosets -	-	-	-	-	-	750
Privies (about)	N. ONE	orere.	O.THOD	Tale Ist	4.00	5,000
Quantity of refuse rer Cost of cleansing the Or at a rate of 1s. 94d. per	privies ((yearly)		- £3	,200	36,000 tons.
Amount received for t	he refus	se	-	- 1	,600	
Consequent loss on re	moval		faring .	- £1	,600	

Or at a rate of $10\frac{3}{4}d$. per ton, or near 6d. per head of population.

CAPITAL EXPENDED to DISPOSE of the SEWAGE.

Purchase of farm Cost of reservoirs a	nd other	works on fa	arm -	- £32,000 - 6,000
				£38,000

The YE Capital 38,000							
Yearly insta Working expe	lment	-	-	ay prin	-		£2,280 4,451
working cape	11303	or sewas	c rarin				6,731
Less receipts for dead stock		e of pro	duce an	d valus	tion of 1	ive and	5,097
Annual loss	-	-	-	-	-		£1,634

The mean daily flow of the sewage is 2,500,000 gallons = 11,160 tons, or 4,073,400 tons yearly. The annual cost to the Corporation in disposing of the sewage is 6,731l. or at a rate of three-eighths of a penny per ton—they receive for it 5,097l., an amount equal to two-eighths of a penny per ton of sewage, and consequently lose 1,634l. or about one-eighth of a penny per ton, or at a rate of $5\frac{1}{2}d$. per head of the population, or about 2d. in the 1l. on the rateable value.

The yearly loss on cleansing privies - £1,600 - £1,634

£3,234

or at a rate of $10\frac{3}{4}d$. per head of the population, or about $3\frac{1}{2}d$. in the 1*l*. on the rateable value of the Borough.

The volume of the sewage is at the rate of 35 gallons per head of the popu-

lation, or about 6 persons contribute to every ton of sewage.

The capital, 38,000l., will be paid off, and then the annual payment of 2,280l. will cease, and the rates will thus be relieved to the extent of about $2\frac{3}{4}d$. in the 1l. on the present rateable value.

REPORT OF THE WOLVERHAMPTON SEWERAGE COMMITTEE ON THE RESULT OF FARMING OPERATIONS AT BARNHURST.*

1st MAY, 1876.

Appended is a statement of receipts and expenditure in connexion with the

farming operations at Barnhurst, for the year ended Lady-day last.

In reviewing the experience of the past year, it may be remarked that although contagious diseases amongst cattle have been prevalent in the district the corporation stock has been entirely free from this form of disease, and that the losses in live stock comprise only one beast from gripes, one sheep and lamb drowned, and three young pigs which died from inflammation.

The past year generally has been unfavourable to successful sewage farming, owing to the extraordinary and frequent heavy falls of rain. Consequent on this the Barnhurst Estate suffered considerably from floods, causing great damage to the grain crops, decreasing the yield, and injuring the quality; still, with all these drawbacks, your Committee have the satisfaction of presenting a balance sheet showing a profit on the year's working of 1,048l. 16s. 5d. equal to 84s. 7d. per acre on the 248 acres of land under cultivation, or an increase of 52°/o on

last year's experience.

In conclusion, your Committee beg to draw the serious attention of the Council and the public to the great damage sustained to crops through acids being allowed to run into the sewers from manufactories in the Borough. This subject was particularly referred to in the Annual Report of your Committee, in November last, and they cannot now too strongly urge upon the manufacturers the importance of neutralizing the acids and other injurious refuse from their works before allowing them to flow or pass into the drains, or of altogether preventing the same from entering the sewers; and unless some such steps are taken your Committee will reluctantly be compelled to ask the Council to instruct the Town Clerk to take proceedings against offending parties, under the 95th section of the Wolverhampton Improvement Act, 1869.

J. Hawksford, Chairman.

^{*} In this report no notice is taken of the interest on the capital expended, 38,000*l.*, amounting to 2,280*l.* per annum, or $2\frac{3}{4}d$. in the pound on the rateable value of the district.

BARNHURST FARM ACCOUNT, year ended March 25th, 1876.

BARNHURST FARM ACCOUNT	, year ended March 25th, 1876.
RECEIPTS. 1875. March 25. & s. d. & s. d. 1876. March 25. & s. d. & s. d. 1876. March 25. To Wheat sold 176 2 6 " Barley 181 0 0 " Oats 77 2 6 " Rye grass 442 14 10 " Live stock 1,542 7 8 " Hay, straw, &c 67 15 9 " Mangolds, cabbages, &c 127 15 4 " Stock taken into Ley - 41 4 0 " Miscellaneous receipts, wool, team hire, rents, &c. 186 9 3 - 2,842 11 10	1875. EXPENDITURE. March 25. By Balance due to treasurer and others - 2,533 5 0 1876. March 25. By Labourers' wages - 544 14 11 ", Rates, taxes, and bank interest - 146 15 6 ", Tradesmen's bills - 161 3 1 ", Corn and seeds - 106 11 5 ", Hay, straw, &c 255 19 0 ", Manure - 50 6 0 ", Live stock - 854 2 0 ", Turnips and cabbages - 9 0 0 ", Balances in bailiffs' and other hands - 191 3 5 Receipts year ended 25th March 1876 - 2,842 11 10 Valuation at Lady Day, 1876, as per Mr. T. J. Barnett's valuation - 2,800 2 0 £5,642 13 10 4,593 17 5 Profit for the year ending Lady day, 1876 - £1,048 16 5
ah 346 dashe belangarar pedaha-1	there are the residence raise. Allow he
Live Stock Hay, straw, corn, and off-going tenants share of Implements (at 10 per cent, under actual cost) John Bryan, Accountant Clerk.	of labour performed - 1.051 5 0
West	DERBY.
Population, about - Annual rateable value - Daily volume of sewage about Number of waterclosets about Number of ashpit middens About two privies to each mide Area of sewage farm -	31,400 - £163,000 - gallons 750,000 - 3,220 - 1,630
	301., or at a rate of about 3061. per acre. 344 tons per day, or about 1,220,560 tons
63,350 <i>l</i> . capital at 6 per cent. Annual working expenses	per annum £3,800 2,335
Total Less total income -	£6,135 3,350
Total annual cost -	£2,785
6,135l., equals a rate of 3,350l. received, equals 2,785l., the annual loss	1¼d. per ton. ¾d. ,, - ½d. ,,

There are about 24 gallons of sewage per head, or about nine persons to each ton of sewage.

The annual cost is about 1s. 9d. per head, and 41d. in the pound.

17,000 tons of privy midden refuse is removed at an annual cost of 700l., or at a rate of $9\frac{3}{4}d$. per ton. The refuse is the property of the contractor.

WREXHAM.

Population	-	2	-	-	-	- 10,000
Houses		-	-	-	-	- 2,000
Waterclosets	-	-	-	-	-	- 1,200
Annual rateable	value	-	-	-	-	£32,000

The sewage flows on to the farm by gravitation, the farmer can take in water from the brook, and does so in dry seasons occasionally.

Area of sewage farm, 84 acres. Leased by corporation at 320l. a year. Colonel Jones pays 350l., and rents other land, 20 acres, at 40s. per acre, or 40l. per annum.

104 acres at an annual rental, 390l. The tenant only puts sewage on 86 acres. Dry weather sewage, about 300,000 gallons per day. Wet weather passed to the farm, about 500,000. Flood-waters pass to the river.

Sewage has been applied to the land about six years; Colonel Jones has worked it about four years. Land is open, having a sub-soil of sand and gravel. About five acres are usually under sewage at one time.

Colonel Jones considers that he could with advantage dispose of 500,000 gallons per day all the year round.

Will cultivate about 20 acres of Italian rye-grass. Commenced with three acres, then eight, increased to 17, this next year will be 20. The average cuttings per season have been seven to eight, about 40 tons per season. A single crop has on a portion of the land been 12 tons per acre. The price obtained has been on an average 9d. per cwt., or 15s. per ton on the ground.

Mangolds, about five acres, 46 tons per acre, sells at 20s. per ton. Through the winter the land is dressed with sewage, and some of it warped with the sludge. Ordinarily the sludge is extracted in depositing tanks, four of 180 feet in length, about nine feet wide at top, and three feet deep. Two at a time are in use. The sludge is sold at about 1s. 6d. per ton.

There is about 1,800 tons of sewage per day, or 657,000 tons per annum.

The corporation main sewerage works cost about 11,080l., this expenditure must not however be charged to the sewage-farm, as it is repaid out of the district rate.

The net profit on the sewage-farm to the corporation is 30l., or about one-ninetieth of a penny per ton, as the value of the sewage to the ratepayers of Wrexham. Colonel Jones considers that the sewage ought to be given.

Colonel Jones has laid down 1,215 lineal yards of 12-inch pipe carriers, at a cost of about 2s. 6d. per yard, or about 152l.

The capital laid out by Colonel Jones is 7001.

About 40 head of stock are kept on the farm, milch cows.

Colonel Jones considers that there is more certainty in sewage farming than in ordinary farming, as there is the moisture available at all times. The trouble in wet seasons is in selling and in removing the crop from the land.

There is more produce on sewaged land in wet seasons than in dry seasons; but there is not so good a demand because there is also more grass on unsewaged land, which, in a dry season, is burnt up and consequently is for the time unproductive.

HAFOD-Y-WERN FARM.

1874-5.—84 acres gross measurement: Rent and taxes, &c. at 51. per acre. Profit and Loss Account.

25 25 29	Rent and taxes account - Barley crop, couch field* account 1873 crops account - INTEREST. One year on floating capital, 5 per cent on 1,830l PAYMENT INTO SINKING FUND. 5 per cent. on 479l	0 9 15 18 3 17 91 10	0 8 6 3½ 0	1875. Feb. 1. By Balance	CR. Italian rye-grass account Mangolds Filter beds (market garden) account Permanent pasture acct. Oat crop Wheat crop Potato Carrots Dairy Tank sludge Couch field farm, Dr. Side	5 4 41 2½ 6 2 1½ 1 6	184 1 46 20 1 58	5 10½ 5 10½ 8 4 5 6 0 11 6 4 7 9 5 7
	a epocation at 320L a year	414 3		gross measu	es on de los comos de la como esta de la como	=	2444	3 0

1876. DR. Feb. 1. To Balance of sundries and implement account	1875. CR. Feb. 1. Acres. £ s. d. By Balance Italian rye-grass account 17 275 1 1 "Mangolds ", 5 28 0 3 "Filter beds (market garden) account - 4 17 19 3½ "Permanent pasture - 56 30 14 4 "Oat crop acct 4 6 12 6 "Barley crop ", 4½ 23 15 9 "Odd crops" (potatoes, turnips, and carrots) - 5 9 2 10½ "Dairy account 67 13 6½ "Tank sludge account 13 3 4 "Rent " - 4 15 0 Couch field farm - 6 Total acres in crop - 100½
£476 17 11§	£476 17 11½

* This field lies above sewage tanks level, so can get no liquid.
† The main part of dairy stock was handed over to Mr. George Jackson on 15th May 1875 by valuation, and hence the dairyman's profit for nine months, being an unknown quantity, is in addition to this balance. He seems content.

(Signed) Alfred S. Jones, Lieut.-Colonel.

TREATMENT OF SEWAGE BY LAND FILTRATION.

Kendal.	
a o patient a conjunt of the control	13,700
	44,600
Houses 1241 - node so they say the 1241	2,727
Waterclosets	450
Privies cleansed at the expense of the owners of the	
houses to which they belong	
Expenses incurred to dispose of the Sewage.	
Purchase of sewage farm, repairs, cost of outlet works tanks, preparing filter beds, and levelling land - £	18,871
The Yearly Cost of disposing of the Sewage. Capital, 18,871l., borrowed at 6 per cent., to be repaid	
with interest in 30 years. Yearly instalment - #	21,132
Paid for labour and materials in working sewage farm -	110
	21,242
Less receipts from sale of produce	495
	-07/7
	2141
	CONTRACTOR OF THE PARTY OF THE

The mean daily flow of the sewage is about 750,000 gallons, equal to 3,348 tons, or 1,222,098 tons yearly. The annual cost to the Town Council in disposing of the sewage is 1,242l. 5s. $2\frac{1}{2}d$., or at a rate of three-eighths of a penny per ton. They receive for the produce 495l., an amount equal to one-eighth of a penny per ton of sewage, and consequently lose 747l. 5s. $2\frac{1}{2}d$. or about one-fourth of a penny per ton, or at a rate of 1s. 1d. per head of the population, or 4d. in the pound on the rateable value of the borough.

The volume of sewage is at the rate of 55 gallons per head of the population,

or about four persons contribute to every ton of sewage.

The capital, 18,871*l*., will be paid off, and then the annual payment of 1,132*l*. will cease, and the rates will thus be relieved to the extent of about 6*d*. in the pound on the present rateable value.

PRECIPITATION OF SEWAGE-SLUDGE IN TANKS.

BIRMINGHAM.		
Population (about) 33	50,000	
	29,844	
	33,420	
	8,000	
	35,000	
,, pail system	7,000	
	25,000	
Quantity of refuse removed in 1875 from the privies	28,512	
Removing contents £: Cost of cleansing privies and ashpits yearly, and	35,180	
	5,885	
Amount received for refuse	0,000	
Consequent loss on removal, or at the rate of 4s. $6\frac{3}{4}d$.		
per ton, or 1s. 8d. per head of the population, or $5\frac{1}{2}d$.	29,295	
in the pound on the rateable value of the borough - £	29,290	
Expenses incurred to dispose of the Sewage.		
Purchase of land (farm)	45,400	
	11,250	
	58,880	
	10,644	
Compensation to Right Hon. Sir C. B. Adderley, M.P.	6,000	
_		
£1;	32,174	
The YEARLY COST of DISPOSING of the SEWAGE.		
Capital, 132,174l., at 6 per cent., to repay principal and interest. Yearly instalment - £7,930	8 9	L
	8 9	2
	0 0	
Yearly expense of cleansing tanks, removing and digging in 109,500 tons of sludge - 12,778	0 0	
	0 0	
	0 0	
Yearly working expense of farm - 2,547	0 0	
£24,442	8 91	-
T		
Less amount received for portion		
of sludge sold £202 10 0		
Amount received for cement sold		
(General Scott's process) - 179 0 0		
Amount received for sale of farm	10 0	
produce 2,130 0 0 2,511	10 0	
£21,930	18 91	

The daily mean flow of the sewage is about 12,000,000 gallons, = 53,571 tons, or 19,553,415 tons yearly. The annual cost to the Town Council in disposing of the sewage is 24,442l. 8s. $9\frac{1}{2}d$., or at the rate of about nine

thirty-seconds of a penny per ton. They receive for it 2,511l. 10s. 0d., an amount equal to about one thirty-seconds of a penny per ton of sewage, and consequently lose 21,930l. 18s. 9½d., or about one-fourth of a penny per ton, or at the rate of 1s. 3d. per head of the population.

Loss per head of the population in cleansing privies - 1 8 , disposing of sewage - 1 3

Total loss - 2 11

or 4½d. in the pound on the rateable value of the borough.

The yearly loss by cleansing the privies - £29,295 , disposing of the sewage - 21,931

Total - £51,226

or about 2s. 11d. per head of the population, or about 10d. in the pound on the rateable value of the borough.

The volume of sewage is at a rate of 34 gallons per head of the population,

or about 6 persons contribute to every ton of sewage.

The capital, 132,174l., will be paid off, when the rates will be relieved to the extent of about $1\frac{1}{2}d$. in the pound on the present rateable value.

TREATMENT OF SEWAGE BY CHEMICALS.

COVENTRY. Population (about) 40,000 Rateable value - --£101,438 Houses 10,400 Waterclosets (about) - -5,000 Privies -800 Quantity of refuse removed yearly (loads) 6,600 Cost of cleansing privies yearly and removing contents £1.050 110 Amount received for refuse -£940 Consequent loss on removal

or at the rate of 2s. 10d. per load, or $5\frac{3}{4}d$. per head of population.

EXPENSES incurred to DISPOSE of the SEWAGE.

Purchase of farm for irrigation at Whitley, not used	for	024 000
that purpose, but let at an annual rent of 7181.	41.	£27,000
The yearly cost to the corporation of disposing of	tne	Nil
sewage is	-	Nil.

The YEARLY COST to the GENERAL SEWAGE AND MANURE COMPANY is as under:

Cost of works and plant -	-		-	£12,000
Capital 12,000l. at 6 per cent. to interest. Annual instalment Working expenses of the proce sewage 122½ hours weekly inste	ss for	treating	-	720 2,850 £3,570
				20,070

The daily mean flow of the sewage is 2,000,000 gallons = 8,938 tons or 3,258,370 tons yearly. The annual cost to the General Sewage and Manure Company in disposing of the sewage is 3,570l., and as there is not a sale for the manure produced from the process carried out by the company, the consequent loss is the above named amount equal to about one-fourth of a penny per ton of sewage, or at the rate of 1s. $9\frac{1}{4}d$. per head of the population.

The yearly loss on the cleansing of the privies The yearly loss in disposing of the sewage	-	,:	£940 3,570
			£4,510

or at a rate of about 2s. 3d. per head of the population or about $9\frac{1}{2}d$. in the pound on the rateable value of the city.

The volume of sewage is at a rate of 50 gallons per head of the population, or about 5 persons contribute to every ton of sewage.

D		
Bolton-le-Moors.		
Population (about)	-	93,100
Rateable value	- £	311,563
Houses	-	18,249
Waterclosets	-	758
Privies and middens	-	10,380
Privies, "pail system"	-	700
Weight of refuse removed yearly from privies on	both	
systems (tons)	-	51,290
Yearly cost of cleansing privies on both systems		
removing contents	- /	£6,645
Amount received for refuse	-	4,494
Consequent loss on removal or at the rate of 10	d. per	
ton, or $5\frac{1}{2}d$. per head of population		£2,151
CAPITAL EXPENSES incurred to DISPOSE of the	he Sewi	6.6
	HE BEWA	
Intercepting sewers	-	10,286
Sewage defæcating works	-	16,578
		20000
	£	26,864
The YEARLY COST of DISPOSING of the S	EWAGE.	
Capital 26,864l. at 6 per cent. to repay principal	£	s. d.
and interest. Yearly instalment	1,609	
Cost of treating the sewage by the M. C. process	.,000	10 14
for only 57½ hours a week, instead of continu-		
ously for 168 hours in every week of seven		
days	1,006	17 0
	-,000	-, -
	£8,616	$15 4\frac{3}{4}$
	,,,,,,,	

The daily mean flow of the sewage is about 2,500,000 gallons = 11,161 tons or 4,073,765 tons yearly. The annual cost to the Town Council in disposing of the sewage is 2,616l. 15s. $4\frac{3}{4}d$. or at the rate of about one-eighth of a penny per ton, or $6\frac{3}{4}d$. per head of population, and this is the consequent loss as there is no sale for the "sludge," the residuum of the process. If the sewage was treated for the whole of the 24 hours, and for every day in the week by this process, the loss would be at the rate of about three-eighths of a penny per ton, or 1s. $8\frac{1}{4}d$. per head of the population, and this, too, for only about one-half of the sewage of the borough, for the other half flows direct into the river.

The yearly loss in cleansing the privies - £2,151 - 2,617 $\frac{2}{4,768}$

or at a rate of 1s. $0\frac{1}{4}d$. per head of the population or $3\frac{1}{2}d$. in the pound on the rateable value of the borough.

The volume of sewage is at a rate of 27 gallons per head of the population, or eight persons contribute to every ton of sewage.

The capital, 26,864l. will be paid off in 30 years, and then the rates will be relieved to the extent of about $1\frac{1}{4}d$. in the pound on the present rateable value.

	dod of	LEEDS.				
Population (about)	Te I'm	02 10 1	hi- a t	W 15-357	West -	285;000
Rateable value -	- 20	sel to	7-01	of relation		£945,141
Houses (about)	-	-	-	-	-	57,000
Waterclosets (about)		-	-		-	8,000
Privies and middens	-	-	-	-	-	15,598
Quantity of refuse r	emoved	yearly	from			
middens -	-	-	-	-	loads	80,000
Cost of cleansing p	rivies a	nd mic	ldens	yearly,	and	count!
removing contents	- "	-	- 7	-		£27,000
Less amount received	for the	refuse	-	10000	East In	9,000
Consequent loss on re	emoval	al glan	C.Do a	HEE OF		£18,000

or at the rate of 4s. 6d. per load; or about 1s. $2\frac{3}{4}d$. per head of the population; or $4\frac{1}{2}d$. in the pound on the rateable value of the borough.

EXPENSES incurred to DISPOSE of the SEWAGE.

process -	permanent works s for drying sludge -	-	В.	C. - £57,000 - 4,000
362.01 - 10.2%				£61,000

The YEARLY COST of DISPOSING of the SEWAGE.

Capital, 61,000l. at 6 per cent. to repay principal and interest. Yearly instalment Yearly cost of treating the sewage by A. B. C. process	£3,660 15,000
resting the newton by the M. C. presses	£18,660

The daily mean flow of the sewage is about 12,000,000 gallons, = 53,571 tons, or 19,553,415 tons yearly. The annual cost to the town council in disposing of the sewage is 18,660l., or at the rate of about one-fourth of a penny per ton, or 1s. $3\frac{1}{2}d$, per head of the population, or about $4\frac{3}{4}d$. in the pound on the rateable value of the borough, and this is the consequent loss, there being no sale for the "sludge," the residuum of the process.

Loss per head in cleansing privies Loss per head in disposing of the sewage			$\begin{array}{cccc} s. & d. \\ - & 1 & 2\frac{3}{4} \\ - & 1 & 3\frac{1}{2} \end{array}$
The yearly loss on cleansing the privies The yearly loss in disposing of the sewage	to be all the solution of the beauty of the solution of the side o	d way	2 6¼ £18,000 18,660 £36,660

or at the rate of 2s. $6\frac{1}{4}d$. per head of the population, or $9\frac{1}{4}d$. in the pound on the rateable value of the borough.

The volume of sewage is at a rate of 42 gallons per head of population, or

about six persons contribute to every ton of sewage.

The capital, 61,000l., will be paid off, and then the rates will be relieved to the extent of about 1d. in the pound on the present rateable value.

	В	RADFO	RD.			
Population (about) -	-	-	-	-	173,723
Rateable value -	-	-	-	-	1	2745,671
Houses -	-	-	-	-	-	34,000
Waterclosets -	-	-	-	-	-	4,050
Privies	-	-	-	-	-	11,500
Ashpits -	-	-	-		-	16,500
Weight of refuse	removed y	early fr	om pri	vies on	both	
systems -		-	-		tons	56,200
The yearly cost of	f cleansing refuse whi	g the p	orivies a	and ash	pits,	
contractor -	-	-			-	£8,000
Railway waggons	for carryi	ng ref	use, cos	t 4,800	l. at	
6 per cent., to re	p ay princip	al and	interest	in 30 ye	ears -	288
Consequent loss o	n removal	-	-	-	-	£8,288

or at the rate of $11\frac{1}{2}d$. per head of the population, or about $2\frac{3}{4}d$. in the pound on the rateable value of the borough.

Expenses incurred to dispose of the Sewage.

Outfall works, tanks, and so-called filters - £60,000

The Yearly Cost of disposing of this Sewage.

Capital 60,000l. at 6 per cent. to repay principal and interest. Yearly instalment - - £3,600

Yearly cost of defæcating the sewage - - 6,276

Total - - £9,876

The mean daily flow of sewage is about 8,000,000 gallons, = 35,714 tons, or 13,035,610 tons yearly. The annual cost to the corporation in disposing of the sewage is 9,876l., or at a rate of about one-sixth of a penny per ton, or 1s. $1\frac{5}{8}d$. per head of the population, or about $3\frac{1}{4}d$ in the pound on the rateable value of the borough, and as there is no sale for about 7,000 tons of sludge yearly produced, the consequent loss to the borough is the above stated sum.

Yearly loss in cleansing privies
Yearly loss in disposing of sewage

Total

- £8,288
- 9,786
- £18,074

or at a rate of 2s. 1d. per head of the population, and about 6d. in the pound on the rateable value.

The volume of sewage is at a rate of 46 gallons per head of the population, or about five persons contribute to every ton of sewage.

The capital, 60,000l., when paid off, will relieve the rates to the extent of about $3\frac{1}{4}d$. in the pound on the present rateable value.

			HALIFA	XX.			
Population (a)	bout)	-	-	-	-	-	68,000
Rateable value		-	-	-	-	1	262,581
Houses -	-	-	-	-	-	-	11,218
Waterclosets	-	-	-	-	-	-	2,600
Privies on old	syster	n -	-	-	-	-	1,500
Privies on the			tem	-	-	-	- 3,159
Yearly cost to				cleansing	"Got	1x "	
privies	-	-	-	-	-	-	£1,896.
Yearly cost t	o the	corpora	ation of	cleansing	comi	mon	
privies	-	-	-	-	-	-	1,100
17.11							
							£2,996
							_

The content is the property of the company and the contractor, and the consequent loss to the corporation is 2,996l., or at the rate of about $10\frac{3}{4}d$. per head of the population.

EXPENSES incurred to DISPOSE of the SEWAGE.

Outfall works and tanks	-		-	- £15,954
Cost of chancery suit -	-	-	-	- 4,100
				£20,054
				1000

The YEARLY COST of DISPOSING of the SEWAGE by SUBSIDENCE only.

Capital 20,0541. at 6 per cent., to interest.—Yearly instalment Cost of cleaning out tanks	repay	principal	and	£1,202 213
				£1,415

The mean daily flow of the sewage is 2,500,000 gallons, = 11,160 tons, or 4,073,400 yearly. The annual cost to the town council in disposing of the sewage is 1,415l.; the sewage is not utilized, and they consequently lose the above amount.

							£2,996	
		in dispos	ing of	the	sewage	by subsid		
cnly	-	-	-	-	- 45 V V - 1	- 01 (II - 22 II	-	1,415
		-						£4,411

or at a rate of 1s. 32d. per head of the population, or 4d. in the pound on the present rateable value of the borough.

The volume of sewage is at a rate of 37 gallons per head of the population,

or about six persons contribute to every ton of sewage.

The capital, 20,054l., will be paid off, and then the annual payment of 1,202l. will cease, when the rates will be relieved to the extent of about 1d. in the pound on the present rateable value.

TREATMENT OF EXCRETA BY THE PAIL SYSTEM.

ROCHDALE.

Population (about)	-	-	-	-	- 67,000
Rateable value -	-	-	-	-	- £222,000
Houses -	-	- 10		-	- 14,388
Waterclosets -	-		-	-	- 350
Privies on old system	-	-	-	-	- 2,844
Privies on the "pail"	system	-	-	-	- 5,462

EXPENSES incurred to CLEANSE PRIVIES constructed on "pail" system.

Cost of works and plant (about)		-		£10,000
Weight of excreta removed in 1	875, from	privies	on	-
"pail" system (tons) - Weight of house ash removed to b	1000	-	-	4,224
(tons)	-	-	-	7,650
				11,874

The YEARLY COST of CLEANSING the PAIL PRIVIES.

Capital 10,0001. at 6 per cent. to repay principal and	int	erest in
30 years. Yearly instalment	-	£600
Or at the rate of 1s. per ton of excreta and ash. Cost of collection—11,874 tons of excreta and ash		3,405
Or at a rate of $5s$. $8\frac{3}{4}d$. per ton.	1000	0,100
Cost of manufacturing manure	-	3,651
Or at a rate of 5s. $4\frac{1}{2}d$. per ton.		4
		7,656
Or together 12s. 14d. per ton.		
Less 2,002 tons manure sold at the estimated value	01	2,002
The per ton		
		£5,654
		-

There is not a ready sale for the manure; consequently there is in stock at the works about 7,000 tons, and none of the excreta have since April 1875 been manufactured into manure.

The YEARLY COST of CLEANSING the PRIVIES and MIDDENS.

Weight of refuse ren	noved (tons)	-	-	-	13,736
Cost of cleansing	-			-	-	£1,919
Or at a rate of 2s. 9½d. p Amount received for	er ton. r 5,73	6 tons	sold, th	e rema	inder	
8,000 tons are thr	own aw	ay on "	tips"	-	-	549
Consequent loss	-	-	-	-	-	£1,370

Or at a rate of about 2s. per ton, or about $4\frac{3}{4}d$. per head of the population. Expenses incurred to only intercept the sewage, and not defæcate it, and to discharge it into the river below the town mill-weir—

Cost of sewer - - - 20,000l. Capital 20,000l. at 6 per cent. to repay principal and interest. Yearly instalment - - 1,200l.

The daily mean flow of the sewage is 1,250,000 gallons = 5,580 tons or 2,036,700 tons yearly. The annual loss to the Corporation in constructing the intercepting sewer is 1,200l. or at a rate of one-fourth of a penny per ton of sewage, or $4\frac{1}{4}d$. per head of the population.

The yearly loss on cleansing the privies "pail" system is
The yearly loss on cleansing the privies and middens The yearly loss in constructing the intercepting sewer
1,370
1,200
£8,220

Or at a rate of 2s. $5\frac{1}{2}d$. per head of the population, or $8\frac{3}{4}d$. in the 1l. on the rateable value of the Borough.

The borrowed capital 10,000*l*. for the pail system, which involves an annual payment of 600*l*., will cease at the end of the term for which this sum has been borrowed.

The volume of sewage is at a rate of 19 gallons per head of the population, or about 12 persons contribute to every ton of sewage.

Comparison of the Loss of disposing of Town Sewage in proportion to the Annual Rateable Value of the Town.

By IRRIGATION PLUS SCAVENGING.

- BY IRE	RIGATION	PLUS SCAVENG	ING.					
Name of Town.	HIM CONTRACTOR	Annual Rateable Value.	Annual Cost in the Pound.					
1. Banbury		£34,104	1d. in the pound.					
2. Bedford		65,000	1d. ", "					
3. Blackburn -	okamino-e	235,127	$11\frac{1}{2}d.$, ,					
4. Cheltenham -		217,849	$\frac{3}{4}d.$,, ,,					
5. Chorley, Lancashire		54,407	7d. ,, ,,					
6. Doncaster	2000	68,721	$3\frac{1}{2}d$. ,, ,,					
7. Harrogate -		50,000	$5\frac{3}{4}d.$,, ,,					
8. Leamington -	a Talk	113,400	$6\frac{1}{2}d.$,, ,,					
9. Merthyr Tydfil -		135,000	$7\frac{1}{2}d.$,, ,,					
10. Rugby		45,000	$1\frac{1}{2}d$. ,, ,,					
11. Tunbridge Wells -	الوطناني فالمه	142,914	10d. ", "					
12. Warwick		43,339	$6\frac{1}{2}d.$,, ,,					
13. Wolverhampton -		210,000	3½d. " "					
14. West Derby -	og thiệt du	163,000	$5\frac{1}{4}d.$,, ,,					
15. Wrexham		32,000	Nil.					
Ву Сн	EMICALS	PLUS SCAVENGI	NG.					
16. Birmingham -	ne O artic	£1,229,844	10d. in the pound.					
17. Coventry, by a company	fing " exhi t box sains	101,438	To the corporation, Nil for disposing of sewage; but at $5\frac{1}{4}d$. in the pound					
18. Bolton-le-Moors -	The same	311,563	for scavenging. $3\frac{1}{2}d$. in the pound.					
19. Leeds		945,141	$9\frac{1}{4}d$. ,, ,,					
20. Bradford	distinger.	745,671	6d. ", "					
BY THE PAIL SYSTEM AT ROCHDALE. The Crude Sewage flows into the River.								
21. Halifax	awas lo u	262,581	4d. in the pound. The crude sewage flows into the river.					
22. Rochdale		£222,000	8\frac{3}{4}d. in the pound.					
By La	ND FILTR	ATION AT KEN	DAL.					
23. Kendal	- 1	£44,600	4d. in the pound.					

This abstract is not in all respects a fair comparison of the relative costs the local rates will have to bear in some of the towns named, as in the case of Bolton, where not half of the sewage is dealt with, and even this is done in a manner which will not be sanctioned under a Rivers Pollution Prevention Act. At Rochdale the crude sewage of the town flows direct into the river, a state of things which certainly cannot be continued, and only a portion of the town is at present supplied with pails; and, as we have shown by working out the figures furnished in the local return, not quite one fourth of the excreta of the population said to be supplied with pails is accounted for.

Those towns which have purchased, or leased, land for sewage-farms, as Banbury, Bedford, Wrexham, Wolverhampton, Cheltenham, and Doncaster, show the best results, and levy the lowest rates, and we consider that longer experience will produce even much better results, and in time will show an available income. At Chorley, West-Derby, and Tunbridge-Wells there are good estates to set off against the money expended, the value of which estates will not diminish. At Leeds, Bradford, and Halifax there are only sewage-mud-tanks and so-called filters, with some unprofitable machinery which will not improve in value, and much larger costs must be incurred in these towns before all the sewage can be clarified in the best practicable manner. At Birmingham a large additional purchase of land upon which to purify the sewage is contemplated, and such expenditure will be the best yet made by the local authority. Birmingham is an instance of a town which would not move voluntarily; and then, being driven to extremities by legal restraints, worked unwillingly, bit-by-bit, and in sewering arrangements throwing the town back in its health returns, by compelling a retention of excreta upon the premises in the vain hope by such means to so lessen the polluting property of the sewage at the outlet as to avoid further litigation. Experience has, however, shown that stopping house drainage and discountenancing waterclosets has only slightly diminished the polluting property of the sewage, but not to any appreciable degree which can be accepted as a purification of the river water.

We have explained in this report that sewage, with or without the excreta from waterclosets is sewage, and that the entire excreta of a town population added to the waste-water is, by volume, only about as 1 to 100, consequently the capacity of sewers need not be enlarged; steam pumping power (if required) need not be increased, nor need the area of the land upon which to treat the sewage be added to; neither need there be one shilling more expended per annum on any process connected with the disposal of the sewage; but, on the

contrary, the land irrigated will be made more profitable.

At Doncaster, Leamington, and Warwick the rates levied are for the purpose of paying the interest and instalments to redeem the large sums which have been expended upon steam-pumping establishments and cast-iron sewage-mains. At Tunbridge-Wells, West-Derby, and Merthyr-Tydfil, local conditions have necessitated large outlays of capital on the estates and the works for conducting the sewage to the sites, preparing the grounds, and constructing permanent sewage-carriers. These works have been very costly. Longer experience in working the farms will, we anticipate, by improving the income from the produce to be grown, very much lessen the present rates in aid.

It may be noted in the details of the several towns described, as at Blackburn, Harrogate, and at Tunbridge Wells, that very large sums have been paid in parliamentary and legal costs, and we have charged these items to the capital accounts in each case as against sewage irrigation, which of course increases the local rate, but it may fairly be said that such items are not necessarily parts of the expenses to be incurred in providing sewage-farms. Some towns suffer much more than others by reason of local opposition, and litigation before parliamentary committees, or, under the powers of the Lands Clauses Act, by arbitration. Land rented at 20s. or 30s. per acre, when required for a sewage-farm, is sometimes valued at several hundreds of pounds per acre, and in the case of Blackburn, portions of the land obtained for sewage irrigation purposes has cost about one hundred and fifty years' purchase. These difficulties and excessive charges very much retard local improvements and tend to throw the question of sewage irrigation back; it is, however, only a

repetition of opposition which every improvement in civilization has had to

fight through.

The list of patents taken out to deal with town sewage (Appendix No. 6) shows how much interest the question has excited, and now excites, but large as this list is it furnishes only indirect evidence as to the vast sums of money expended and lost in working some of these patents. It would appear that to learn the lesson that money cannot be made out of sewage-sludge is very difficult, as over and over again it has been proven that there is no commercial value in it. The Leicester works proved this many years since, and every independent chemist of known repute has stated the fact when called upon to analyse sewage-mud. Neither is this mud capable of being fortified by an admixture of chemicals which shall give it a paying commercial value. The sludge is coarse, crude, sloppy, heavy, and very retentive of the water with which it is combined. In 100 tons of sewage-sludge, as it is removed from the tanks, there is not less than 90 tons of water, which in this form is worthless. and by itself the mud will not readily dry, but mixed with ashes, and other forms of towns refuse, it can be made portable and may then, in some cases, be sold to farmers at a low rate, say from 1s. to 2s. per ton. When the cost of carting is taken into account this will be its full agricultural value.

At Banbury the mixed sewage sludge, ashes, and street sweepings are given

away, although the town is situate in an agricultural district.

At Learnington about 3,000 cube yards of solid refuse, costing 7801. to

collect per annum, is also given away.

At Doncaster, Bedford, and Leamington, where the lands irrigated are light and free, the crude sewage is pumped direct to the land as it comes from the sewers, and being distributed from temporarily formed carriers, which at intervals are ploughed up. There is no nuisance, but the lands are benefited by the amount of warping they get. At Chorley the crude sewage is also

placed on heavy land, which has however been drained.

At Cheltenham the sewage-farm is clay, and the area is small in proportion to the population, but dressings of sewage are sold to the adjoining farmers at a price per acre of 7s., or as may be agreed upon; and in this direction we anticipate that many towns when they have established sewage-farms will find relief. In a dry season the contrast of the green fields of a sewage-farm with the parched, bare, and brown meadows adjoining is very striking. In the early spring the sewage farmer may have grass many weeks before there is any to cut upon ordinary meadows, and the weight of grass obtained is far in excess of any unirrigated crops.

We furnish plans of the sewage farms at Bedford, Doncaster, Tunbridge Wells, Wolverhampton, and West Derby. The details of sewage carriers, and modes of distribution can, however, only be learned to advantage by personal

inspection.

Kendal is peculiarly situated, as the land upon which the sewage is clarified is light, open, and washed on its margins by the river, which conditions permit of land filtration over a small area, in comparatively large volumes, at a reasonable cost.

Analyses of Sewage-Sludge as treated and fortified with Chemicals.*

In order to ascertain the value of the fertilizing properties of sewage and excreta, and also of the manures manufactured therefrom, and of their commercial value to the farmer, we collected samples at Bolton, Bradford, Leeds, Coventry, Rochdale, and Halifax, and caused them to be analyzed by Dr. A. Voelcker, F.R.S., and the following is his report thereon:—

REPORT by Dr. VOELCKER, F.R.S.—On the Fertilizing and Commercial Value of Sewage and Night-soil Manures.

The fertilizing and commercial value of sewage-sludge and of portable manures prepared from sewage, night-soil manures, and of common farmyard manure, chiefly depends upon the proportions of phosphate of lime, potash, and nitrogen which these fertilizers contain.

^{*} See also Appendices Nos. 1, 2, 3, 4.

These fertilizing constituents of manures can be bought at the present time in the form of concentrated artificial manures, such as guano, bone-dust, sulphate of ammonia, &c. at the following rates:

Phosphate of lime at - - 1d. per lb.
Potash - - - 2d. ,,
Nitrogen calculated as ammonia at - 8d. ,,

I need hardly say that in such concentrated forms phosphate of lime, potash, and ammonia have a much greater value than they possess in the shape of manures, the bulk of which mainly consists of materials without value and occurring in abundance in almost every kind of soil.

I would, however, direct attention to the fact that according to my own experience, and that of others, sewage manures, night-soil manures, and ordinary farmyard manure contain but little ready formed ammonia, and that by far the largest proportion of the nitrogen in these manures occurs in them in the shape of nitrogenous organic matters, in which form nitrogen is less efficaceous; and, in consequence less valuable than in the form of ready formed ammonia; or, salts of ammonia.

In estimating the theoretical value of manures, the nitrogen is generally assumed to be present in sewage and similar bulky manures in the form of ammonia; or, at all events, to have the same value as the nitrogen in the salts of ammonia. This, in my opinion, is a mistake, and the nitrogenous constituents of sewage manures are valued at too high a rate, if their nitrogen is calculated into ammonia, and 8d. allowed for each lb. of the calculated amount of ammonia. In order to avoid the charge of having put too low an estimate upon the fertilizing constituents of sewage-manures, I have allowed in the estimate 8d. per lb. for the calculated amount of ammonia, which the nitrogenous matters, in a ton of manure, are capable of gradually producing under the most favourable circumstances on their final decomposition.

The following tabular statement shows at a glance the theoretical or calculated money value of the different sewage manures which were submitted to me for analysis:—

THEORETICAL OR ESTIMATED MONEY VALUE OF ONE TON OF THE TREATED SEWAGE-SLUDGE.

	4	s.	d.	
(1.) Bolton sludge, from the M. and C. sewage process* -	0	-	81	
(2.) The same dried, leaving 15 per cent. of moisture in			370	
the sludge	1	1	1	
(3.) Solids drained from sewage before the liming process				
at Bradford	0	11	$0\frac{1}{2}$	
(4.) The same with 15 per cent. of moisture	0	19	3	
(5.) Bradford Corporation Sewage Outfall Works sludge				
	0	4	8	
(6.) The same, with 15 per cent. of moisture	1	0	01	
(7.) Deposit from the sewage of Leeds treated by the				
A. B. C. process†	0	8	$4\frac{1}{2}$	
(8.) The same with 15 per cent. of moisture	0	16	81	
(9.) Manure produced by the General Sewage Manure				
Company at Coventry	0	16	$9\frac{1}{2}$	
(10.) Rochdale manure	0	15	111	
(11.) Manure manufactured by the Goux Company at			-	
Halifax	0	17	7	

According to the most reliable statements the separation of the suspended matters of sewage by precipitation and filtration, and the production of one ton of dried sewage deposits, apart from the costs of the precipitation agents which are used, entails an expense of about 30s. for each ton of portable dried sewage

^{*} M. and C. are the initials of the patentees. The ingredients used are lime, carbon, house-ashes, soda, and per-chloride of iron.

† A. B. C. are the initials of the chief ingredients used in this process, as Alum, Blood, and Clay.

manure. It is evident, therefore, that the cost of manufacture considerably exceeds the theoretical or calculated money value of every one of the sewage deposit manures, the composition of which is given in the results of analysis in Appendices Nos. 1, 2, 3, pages 39, 43, 44, 48, 51, 54, and 59. The estimated money value of sewage and night-soil manures, as has been stated already, does not fairly represent their real commercial value. The bulk of all the samples submitted to me for analysis consists of matters which occur in abundance in almost all soils, and which at any rate have no commercial value, or rather, have a negative value, inasmuch as carriage has to be paid for them, and the application of bulky manures necessarily is more expensive than that of concentrated manures, such as guano or bone-dust. It is, therefore, manifestly practically wrong to estimate the money value of such bulky and poor manures by the same standard of prices at which the commercial value of guano, bone-dust, sulphate of ammonia, and similar concentrated artificial manures are estimated. A more rational and correct estimate of the true value of sewage and night-soil manures is obtained by comparing them with ordinary farmyard manure, and the price which is paid

Good farmyard manure, I find, contains on an average in the ton $6\frac{1}{2}$ lbs. of soluble phosphate of lime, $8\frac{1}{2}$ lbs. of insoluble phosphate of lime, 13 lbs. of potash, and nitrogen equal to $17\frac{1}{2}$ lbs. of ammonia.

By allowing for soluble phosphate of lime 2d. per lb., the same price for potash, 1d. per lb. for insoluble phosphate of lime, and 8d. per lb. for ammonia, the calculated money value of a ton of farmyard manure amounts to 15s. $7\frac{1}{2}d$., as will be seen from the following figures:—

$6\frac{1}{2}$ lbs. of soluble	phosphate	of lime, wo	rth, at 2	l. per lb.		d. 1
8½ lbs. insoluble	,	, ,,	10	l. "	0	$8\frac{1}{2}$
13 lbs. potash	, mining,					2
Nitrogen equal to monia at 8d. per	17½ lbs. of r lb	ammonia,	calculat	ing am-	11	8
Total calculat	ed money	value of a	ton of f	armyard	15	71/2

It thus appears that if we estimate the money value of good farmyard manure, according to the same rules at which the principal fertilizing constituents in the dung can be bought in concentrated manures, one ton of farmyard manure would be worth, in round numbers, 15s. However, good dung can be bought in many places at 5s. per ton, or one-third its estimated money value; and practically the highest price which a farmer can afford to pay for good dung, if he has to cart it even a few miles, would not exceed 7s. 6d. per ton, one half its estimated money value. The difference between the estimated money value of farmyard manure (calculated at the market rate of the constituents, when sold as concentrated artificial manures), and the actual market price, may be fairly taken to represent the difference in practical value caused by the greater expense of the carriage and application of farmyard manure, and the less vigorous action of organic nitrogenous compounds as compared with ammonia salts.

In estimating the commercial value of sewage and night-soil manure, the calculated value of which does not exceed 1l. ls. per ton, precisely the same circumstances have to be taken into account, which affect so largely the market value of ordinary farmyard manure. Accordingly the price which the farmer can afford to pay for the sewage and night-soil manures, analysed by me, or their real money value, will be only from one third to one half that of the calculated estimates given on the basis of their analyses.

The following table shows the market price or real money value of the various sewage and night-soil manures, samples of which were submitted to me for analysis:—

PRACTICAL OR MARKET VALUE OF ONE TON OF THE TREATED SLUDGE.

	8.	. d.	8.	d.
(1.) Bolton sludge from the M. and C. sewage process	3	3 to	4	10
(2.) The same sludge 15 per cent. of moisture -	7	0 ,,	10	6
(3.) Solids drained from sewage before the liming				
process, at Bradford	3	8 ,,	5	6
(4.) The same with 15 per cent. of moisture -	6	5 ,,	9	6
(5.) Bradford Corporation Sewage Outfall Works.				
Sludge from drying pits without artificial				
heat	1	6 ,,	2	4
(6.) The same dried with 15 per cent. of moisture -	6	8 ,,	10	0
(7.) Deposit from the sewage of Leeds treated by				
the A. B. C. process	2	9 ,,	4	2
(8.) The same sludge with 15 per cent. of moisture	5	6 ,,	8	4
(9.) Manure produced by the General Sewage				
Manure Company at Coventry	5	6 ,,	8	4
(10.) Rochdale manure	5	4 ,,	8	0
(11.) Manure manufactured by the Goux Company				
	5	10 "	8	9

In my judgment this tabular statement fairly represents the money value of 11 different samples sent to me for analysis at the place where the manures were produced.

Some of the products are worth a good deal less than an equal weight of common dung, which fully explains the circumstance that most sewage manures find no ready sale, even at a low price, and that in many works such manures accumulate to an inconvenient extent.

Indeed comparatively few farmers are so situated that they can afford the expense of carting semi-dried sewage sludge containing from 60 to 70 per cent. of moisture from the works to their fields. The refusal to accept such sludge as a gift in not a few instances rather shows sound discrimination than ignorance on the part of the farmers.

(Signed) Augustus Voelcker.

A presentation of the language of the surface of th the contract of the contract o

APPENDICES.

APPENDIX No. I.—SEWAGE FARMS.

Abstracts from these separate Reports of the different systems are given in our Report.

EDINBURGH.

The city of Edinburgh has a population of about 196,979, living in 10,559 houses, in which there are 41,615 separate dwellings on the The volume of sewage is about 5,900,000 gallons "flat" system. per day. Sewerage works have from time to time been carried out the old sewers being of rude construction in which sewage stagnates, hence its black and foul condition at the several outlets. Main-sewering is stated to have been commenced about the year 1778, and the system has been extended from time to time, especially in the New-town as it has increased, and works of a better class are still in progress. The oldest main-sewers are built of rough stone, with flat stone bottoms and stone covers, having a sectional area of 18 feet (6 feet by 3 feet); the cost of the older sewerage has been 69,000%. Since 1853 main-sewerage works have been greatly extended at a further cost of 80,000l. and in the valley of the water of Leith, a sewer has been constructed to intercept sewage and the refuse from paper and other mills, and pass the same by a cast-iron outlet-pipe (costing with the other works 85,000%, into the Frith of Forth at "Black Rocks." These works serve for a population of about 100,000. The sewers of Edinburgh are not regularly flushed, and are not at present sufficiently ventilated : several springs were tapped during the execution of the main-sewerage works, the water being taken into the sewers, and it is estimated that the daily volume from this source is equal to about 40,000 gallons.

There are in Edinburgh at present many waterclosets, and in the older and more crowded parts of the city, 9 Macfarlane's latrines and 35 public privies; but the excreta and other refuse of the inhabitants in the Old-town are chiefly collected in pails or pans, placed in the living rooms; these receptacles are said to be taken down every morning into the streets, and their contents emptied into the corporation carts and

39260.

se removed. The waterclosets and latrines are connected with the sewers; the privies are emptied by men employed by the corporation. The annual gross cost of cleansing the city of this excremental matter and house refuse is 23,645*l*., the corporation receiving 7,458*l*. for 36,637 tons, which is sold to farmers to be used as manure. The sewage is not treated by lime or by any other disinfectant, nor is it filtered, and by far the larger portions from the southern and western parts of the city flow into the Jordon, Broughton, and Lochrin burns, and from thence, unutilized, into the Frith of Forth.

The sewage of certain districts of the city has long been used in rough and rude irrigation, in some cases since 1760, the lands irrigated being known as the "Craigentinny meadows" which have an area of about 220 acres, "Lochend meadows" about 28 acres, "Lochrin-on-Dalry meadows" about 40 acres, and "Brigend and Cairntows meadows" about 35 acres, making a total of 323 acres. There are about 250 acres of the Craigentinny and Lochend meadows under sewage irrigation; of these 200 acres are permanent pasture grasses, and 50 acres Italian rye grass. About 2,500,000 gallons of crude sewage, every 24 hours, flows through the "Foul Burn" on to the meadows. The grass is sold by public roup at the beginning of April in each year in allotments of from half a statute acre to one acre in area, at prices varying from 201. to 401. per acre per annum; one allotment (acre) sold last year for 441.15s. The permanent grass is used for cow feeding and is bought by dairymen at Musselburgh, Portobello, Leith, and Edinburgh, who have to cut and remove it; this is done about four times in the season, and yields an aggregate crop of about 40 tons to the acre. The Italian rye grass is cut five times a year and produces occasionally 60 tons to the acre. The irrigation is carried on in the cheapest and rudest way by the owners of the land adjoining the streams into which the sewage flows; no cost having been incurred in providing permanent carriers of either wood, iron, stoneware, or brickwork. A considerable portion of the sewage is absorbed by the "sea sand" of which the irrigated meadows of Craigentinny farm is composed, and thus the soakage of sewage from this land into the "Frith of Forth" is only partially purified.

The area of the meadows under irrigation is not sufficient to utilize the whole of the sewage brought down by the "Foul Burn," consequently a greater extent of crop might be obtained if the sewage could be applied to other portions of the farm or to the adjoining lands.

The annual cost of applying the sewage and receipts for the produce are,—

RECEIPTS. 250 statue acres of grass at average of 30l, per acre	£ 7,500	EXPENDITURE. Wages of watermen three in summer and one in winter, and cost of clean-	£
test and the second sec	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	ing out carriers	180
		Estimated rent of land 250 acres at 2l.	
		per annum *	500
		Balance	6,820
	-	tupo a comes sint proti sumlay vind	1
	7,500	The second secon	7,500
	==	maken an uguodantal at ean east	=

The effluent water was flowing into the "Frith of Forth" at the date of our visit in August 1875.

^{*} This is a price far above its agricultural value without the sewage. See analysis by Dr. Voelcker.

If the 2,500,000 gallons of sewage were used in irrigation on these 250 acres of land, each acre would receive upwards of 16,000 tons in the year, and this, valued at 1d. per ton, would be worth 67l.

We have caused an analysis to be made by Dr. A. Voelcker, F.R.S.,

of the Craigentinny meadows soil, and the following is the result:

RESULTS by Analysis of a Sample of Soil taken from the Craigentinny Meadows, Edinburgh.

Dried at 212 F. the	soil con	tained	in 100	parts:-			
*Organic matter	-	-		-	-	-	1.60
Oxide of iron and al	lumina	-	-	-	-	_	1.04
Phosphoric acid	-	-	-	-	-	-	0.06
Sulphuric acid	-	-	-	-	-	-	traces
Lime	-	-	_	-	-	-	0.08
Magnesia -	-	-	-	-	-	-	0.25
Potash -	-	-	-	-	-	-	0.08
Soda	-	-	-	-	-	-	0.13
Chloride of sodium	-	-	-	-	-	-	0.02
Silica (as white fine	sand)	-	-	-	-	-	96.80
							100.06
*Containing nitroge	n	-	_	-	_	-	0.039
Equal to ammonia	-	-	-	-	-	-	0.047

This soil, it will be seen, contains but very little lime, potash, and phosphoric acid, and thus is poor in all the more valuable mineral soil constituents.

It contains in round numbers only $1\frac{1}{2}$ per cent. of organic matter in the perfectly dried soil, and in that state nearly 97 per cent. of fine white sand. The organic matter was present mainly in the shape of roots and vegetable fibres remaining in the land from the crops grown upon it. It is hardly necessary for me to state that the soil from the Craigentinny meadows, Edinburgh, analysed by me is one characterized by extreme natural sterility. The entire value is in the sewage, and the amount realised by the crop is about one halfpenny per ton, less the rent of the land and the cost of the labour.—See pages 78, 79, and 80 as to raw and effluent sewage.

BANBURY.

Population (about)		_	-	-	2	-	12,000
Rateable value	-	-	-	-	-	-	£34,104
Houses -	-	-	-	-	-	-	3,485
Waterclosets	-	-	-	-	-	-	2,485
Cost of main sewer	S	-	-	-	-	-	£6,400
Cost of outlet work	s and	laying	out sewa	age farm	-	-	£5,500
Volume of sewage	every	24 hou	rs -	-	(gal	ions)	320,000
Cost of pumping se	wage	and we	orking ex	cpenses o	of farm	4	£1,281
Amount received for			-	-	-	-	£1,451

Banbury.—This town of 12,000 inhabitants, living in 3,485 houses distributed over an area of 3,920 acres, and having a rateable value of 34,104l., has finally adopted irrigation as a remedy for the pollution

caused to the River Cherwell by the unpurified sewage of the town flowing into it. The town was sewered in 1856, and 2,485 waterclosets were connected with the system; the main outfall being into the River Cherwell. In order to prevent the coarser suspended matters of the sewage from flowing direct into the river, subsidence-tanks were constructed, and through these tanks the sewage flowed before it reached the river, but this did not remove the soluble matters of the sewage, causing serious annoyance to Mr. John Spokes of Tyford, whose mill is on the Cherwell, about five miles below Banbury, he complained of the nuisance, and meeting with no redress, filed a bill in the Court of Chancery on the 20th June 1864, and on the hearing of the cause, the Vice-Chancellor, Sir W. Page Wood, issued an injunction to restrain the Banbury Local Board from causing or permitting the main sewers of the town and district to discharge the sewage into the Cherwell. The Local Board were advised "that the sewage should be treated by per-chloride of iron and caustic lime in the state of so-called 'milk,' and in the proportion of 20 grains of the former and 10 grains of the latter to every gallon of liquid sewage, and the treated sewage be allowed to flow slowly through the tanks to enable the mechanically suspended and chemically separated matters to be effectually deposited, and the supernatant liquid to pass off clear and nearly colourless; and they were advised that there would then be little likelihood of the sewage becoming again putrescent after its admission into the water of the flowing river." On receipt of this report the Local Board caused additional tanks to be built, so that the sewage after treatment might remain in nearly quiescent state for about four hours before it flowed into the river; and the above process recommended by Mr. T. Hawkesley and Dr. H. Letheby was carefully carried on for some time, but failed to purify the sewage, and the Court, on the application of the Plaintiff, issued an order of sequestration. The Local Board then, as better advised, took on lease, from 11th day of October 1866, for 28 years, a farm at Warkworth, of 138 acres, the soil being a stiff loam upon a clay subsoil and had it laid out to receive the sewage, but, owing to the configuration of the land, it had to be pumped to a height of 21 feet; and 320,000 gallons) has been daily pumped on to the land ever since the farm was laid out, in winter as well as in summer. Subsequently, the Local Board received sanction to pur chase the before-mentioned land and an additional area of 100 acres, making together 238 acres, costing the sum of 23,400%. There is storeage in the tanks at the pumping station for eight hours flow of sewage; these tanks are cleaned out every six weeks, and the refuse mixed with the dry house ashes and street sweepings, was formerly sold at 6d. per ton, but, in consequence of an accumulation of nearly 2,000 tons, and there being no sale for it, the refuse with the street sweepings are now allowed to be taken away from the depôt free of charge.

The privies are cleansed at the cost of the occupiers of the houses to which they belong.

The rainfall on the roofs and the surface of the streets flows into the sewage-drains, and thence to the outfall, and has to be pumped to the farm, except in heavy rainfall, and then the storm water flows by the storm-outlet into the Cherwell. The sewers are ventilated at present, partially and imperfectly, by down spouts from the roofs of houses, and also by a few grids on the surface of the street. The cost

of the main sewers was 6,400l.; of the tanks and buildings 1,500l.; and of pumping-station, rising-main and laying out farm 4,000l.

The accounts of the receipt and expenditure for the year 1875 are as follows:—

BANBURY LOCAL BOARD OF HEALTH SEWAGE FARM SALES, &c., 1875.

			- 1000	
Name of Field and Date of Sale.	Description of Crop.	Quantity sold.	Product of Sales.	Amount per Acre.
Great between Brooks. April 30 1st cutting - June 11 2nd ,, July 30 3rd ,, September 17 4th ,,	Rye grass	Acres Chains 6 3 5 9½ 5 9 5 7	£ s. d. 28 19 0 41 13 0 42 16 0 11 18 0	£ s. d. 4 11 11 7 0 0 7 5 1 2 1 9
May 14	" " " " " " " " " " " " " " " " " " "	$\begin{array}{cccccccccccccccccccccccccccccccccccc$	41 18 0 55 13 0 39 18 0 6 0 0	5 2 2 6 15 9 5 8 2 1 0 2
West between Brooks. May 28 1st cutting - July 16 2nd September 3 3rd ,,	" " " "	$ \begin{array}{cccccccccccccccccccccccccccccccccccc$	40 18 0 37 9 0 18 0 0	5 19 5 5 1 10 3 0 10
October 22	{ Mangold wurtzel }	2 0	17 15 0	8 17 6
East between Brooks. October 22 Horse Stub.	$\left\{\begin{array}{c} \text{Mangold} \\ \text{wurtzel} \end{array}\right\}$	11 11/4	162 6 0	14 11 8
August 13	Wheat Oats	8 5 8 7½	102 0 0 122 10 0 224 10 0	12 0 3 14 0 0 26 0 0
May 28 1st cutting - August 13 2nd ,, - September 17 ,, ,, -	Mowing grass ,,, Aftermath	24 5 24 5 24 5	132 2 6 58 0 0 12 5 0	5 7 10 2 7 4 0 10 0
Little Bolland. May 28 1st cutting - August 13 2nd ,, - September 17 ,, ,, -	Mowing grass	13 0 13 0 13 0	79 12 6 40 12 6 14 19 0	6 2 6 3 2 6 1 3 0
			135 4 0	10 8 0

	ield and Date of Sale.		Description of Crop.		antity sold.		duct ales.			nour r Ac	
Upper Ple	ain.			Acre	s Chains	£	s.	d.	£	s.	d.
May 28	1st cutting	-	Mowing grass	14	0	75	5	0	5		6
August 13	2nd "	-		14	0	28	0	0	2	0	0
September 1	7 ,, ,,	-	Aftermath	14	0	11	14	0	0	16	0
			-0.00			114	19	0	8	3	6
Middle P	lain.		blox	Jps:			E	48)			
May 28	1st cutting		Mowing grass	13	5	62	8	9	4	12	6
August 13	2nd "	-	,, ,,	13	5	27	0	0	2	0	0
October -	A - A	-	Aftermath	13	5	6	10	0	0	9	7
				73		95	18	9	7	2	1
Lower Pla	tin.		a Line of the					diam	beed	mai	in:
May 28	1st cutting		Mowing grass	12	5	57	16	3	4	12	6
September 3	2nd "	-		12	5	22	10	0	1	16	0
,, 1	- "	-	Aftermath"	12	5	5	12	6	0	9	0
						85	18	9	6	17	6
Right of sho	oting for the	se	ason -	-	-	4	0	0	ti	illiy	110
Keep of four	horses .			-	-	43	8	0			
					Total £	1450	19	0			

The whole of the crops are sold standing, the Board being at no expense of cutting or carting.

Receipts.			SUMMA	RY.	Expenditure.
	Area.	Product of sales.	Average per acre.	Alana J	was a south
Permanent pasture - Rye grass (including horse keep). Wheat - Oats - Mangold wurtzel - Right of shooting -	77 5 24 4½ 8 5 8 7½ 13 1½	£ s. d. 633 18 0 408 10 0 102 0 0 122 10 0 180 1 0 4 0 0	£ s. d. 8 3 7 16 14 2 12 0 0 14 0 0 13 14 4	Rent (less Property tax) Rates and taxes Superintendence and manu (including engine driver). Oil seed, &c. Coal Own horse labour (about) Manager's salary Commission, &c.	£ s. d 622 0 0 - 39 12 5 al labour 247 14 8 - 76 7 3 - 147 4 5 - 30 0 0 - 72 11 0
Total area of farm (including roads).	A. R. P. 138 0 38	1450 19 0	10 9 11	transler - Discounting the Contract of the Con	£1,280 9 9

Mr. Thomas Garrett, the town surveyor and manager of the farm, has been successful in carrying off several silver cups and money prizes for the roots grown by sewage of the farm.

Note.—See pages 87 and 88.

BEDFORD.

Population (about) -	-	-	-	-		18,000
Rateable value	-	-	-	-	-	-	£65,000
Houses -	-	-	-	-	-	-	3,500
Waterclosets	-		-	-	-		3,000
Cost of main sewe	rs	-	-	-	-	-	£19,000
Cost of outlet wor	ks, p	umping stat	ion,	and laying	out	sewage	
farm	-	-	-		-	-	£9,200
Volume of sewage	eve	ry 24 hours	-	-	(9	gallons)	700,000
Rent, labour, and	expe	ense of work	ing	farm -	-	-	£3,280
Amount received	for p	roduce	-	-	-		£3,461

Bedford. This is an instance of a town which, without being forced by the expensive machinery of the Court of Chancery to get rid of the nuisance caused to the river by sewage pollution, has endeavoured to utilize its sewage by applying it to profitable use in irrigation. Local Board District of Bedford has an area of 2,200 acres, and a rateable value of 65,000l., with a population of about 18,000 living in 3,500 houses, to which are attached at least 3,000 waterclosets, and as there are no privies, this may truly be termed a watercloset town. A thorough system of sewerage has been carried out, commenced in 1864 and finished in 1868 at a cost of 19,000l. The old sewers are used as surface and storm-water conduits, and these have three outlets into the The whole of the sewage proper is intercepted from the river by the new sewers, and gravitates to a point at Newnham, about a mile from the town, where it flows into a sewage-well, and is thence pumped on to 155 acres of land, a small portion of which is the property of the corporation. The larger part is leased from the Duke of Bedford, the Rev. J. W. C. Campion, and Captain Polhill Turner. soil of the farm is a rich loam with a gravelly sub-soil, well adapted for the purpose to which it is devoted, and the surface has been especially laid out for irrigation. The permanent carriers are stone-ware pipes, with sidejunctions at proper intervals for regulating the flow of sewage on to the plots of land required to be irrigated. The volume of sewage which has to be pumped, is estimated at 700,000 gallons every 24 hours, but of this 300,000 gallons is sub-soil water. The main outfall sewer is 5 feet 3 inches by 3 feet 9 inches in sectional area, three quarters of a mile long; is laid at a gradient of 1 in 3,520, and serves as a The sewage-well, at the pumping-station, is of small storage-tank. capacity, and to prevent choking the pumps by the coarser particles of sewage, the suction-pipe is protected by iron screens.

The outfall-sewer is cleaned out occasionally, and the deposit which is

little more than detritus is carted away.

The cost of preparing the land, constructing carriers, erecting pump-

ing station, and fitting it with machinery was 7,2001.

By the courtesy of the town clerk we are enabled to give a copy of the General Account and Balance Sheet for the year ended 31st December 1874, and also proceeds from sales of crops for the year ended 31st December 1875. The Urban Sanitary Authority for the Borough of Bedford.—
Irrigation Farm.—General Account and Balance Sheet at
Stock-taking 31st December 1874.

STOCK-TAKING SIST DECEMBER	10/4.
100	
Dr.	Cr.
Stock, December 1873 - 431 0 0 Working plant, Dec. 1873 222 4 0 653 4 0	£ s. d. Sale of Crops 2515 13 10 Stock in hand and purchased, 1874 - 544 8 0 Working Plant and Live and Dead 269 9 0
Labour, manager, and engineer - 667 17 2 Trademen's bills, &c 780 10 9	Stock. Sewage Works 24 2 8
Rent 917 4 0 Rates and taxes 113 14 7	Hay 48 2 6 Beans 59 10 0
Permanent works 24 2 8 Oats 16 5 0	107 12 6
Hay 48 2 6	The state of the s
Beans 59 10 0 107 12 6	a first and the same of the sa
Balance for 1874 180 15 4	The state of the s
£3,461 6 0	£3,461 6 0
N 0 1 (23 9	
Corn &c., for live stock.—	
Corn purchased, (see expenditure) Hay from farm) 40 8 9 48 2 6
Oats	16 5 0
Beans	59 10 0
	£164 6 3
£ s. d.	£ s. d.
Labour 492 9 7 Manager 112 11 1	By Sale of Crops, Mr. Stafford - 1,933 1 1 Manager 582 12 1
Engineer 62 16 6	ER, Riseres to the supplied of
£667 17 2	£2,515 13 10
and his distalna from Prince Hostonia and	Stook in hand and numbered 1974
Tradesmen's bills paid 79 11 7	Stock in hand and purchased, 1874— 30 tons of hay, 5l 150 0 0
Tradesmen's bills owing - 30 10 2 Coals - 260 2 7	26 loads of beans, 28/ 38 8 0 2 acres of mangolds, 20l 40 0 0
Coals owing 32 8 0	6 tons of potatoes, 4l 24 0 0
Horse corn, &c 40 8 9 Manure purchased 10 0 0	16 acres of growing wheat, 50/- 40 0 0 Bean, barley, and oat straw - 15 0 0
Horse and bullocks purchased - 133 10 0	Rye grass hay 10 0 0
Seeds 102 8 4 Hire of Horses for ploughing - 30 3 0	Pickling cabbages 12 0 3 Carrots 25 0 0
Mr. Stafford's commission and 114 12 6	12 oats, 26/- per qr 16 5 0
expenses.	6 acres of growing cabbage, 5 <i>l</i> 30 0 0 94 acres of growing rye grass, 50/ 23 15 0
Deduct bills owing 1873 - 53 4 2	8 bullocks, 15l 120 0 0
Charles when the series of the	£544 8 0
£780 10 9	organization signaturally by party organization
Rents-	Working plant and live and dead stock.
The Rev. Campion - 126 14 11 Captain Polhill Turner - 421 11 3	4 horses 175 0 0 3 carts, 8l 24 0 0
Duke of Bedford 244 8 2	1 horse roll 7 10 0
Corporation of Bedford 123 9 8 L. & N. W. RySewer under 1 0 0	1 single ditto 1 10 0
railway.	1 horse hoe 4 0 0 1 scuffler 4 0 0
£917 4 0	2 sets of harrows 2 0 0
THE STATE OF THE S	1 pulper 2 10 0 1 chaff cutter 4 0 0
Poor Rates 92 0 3 Income Tax 18 3 2	1 bean mill 2 10 0 6 wheelbarrows 1 4 0
Land Tax 3 1 2	4 sets of Harness 6 0 0
Insurance 0 10 0	1 cultivator 2 15 0 3 cow cribs 3 0 0
£113 14 7	Office furniture 2 10 0
and sometimes of the second	Coals in stock 24 0 0
Permanent works 24 2 8	£269 9 0
in court had the court of the properties	The first state of the state of
hims two servening sould go still Res S	J. E. CUTCLIFFE,
	W. ROFF, HARRY THODY, Farming
	THOMAS HALL BARKHAM,
A THE PARTY OF THE	Jas. Thos. Hobson,

Borough of Bedford. Urban Sanitary Authority Irrigation Farm.

Account of Proceeds from Sales of Crops, year ending 31st December 1875.

		-				Area under cultivation.			Amount.			
						Α.	R.	P.	£	s.	d.	
Italian rye grass	-	-	-	-	-	22	0	0	399	0	6	
Potatoes -	-	-	-	-	-	25	1	0	140	16	6	
Mangolds -	-	-	-	-	-	40	2	20	599	6	6	
Onions -	-	-	-	-	-	10	0	20	287	0	0	
Carrots -	-	-	-	-	-	7	3	0	116	1	0	
Cucumbers	-	-	-	-	-	1	0	0	16	1	0	
Vegetable marrov	ws	-	-	-	-	0	0	10	1	6	3	
Asparagus	-	-	-	-	-	0	0	20	2	11	0	
Rhubarb -	-	-	-	-	-	0	0	20	5	0	0	
Cabbage -	-	-	-	-	-	6	1	10	87	12	0	
Pickling cabbage	-	-	-	-	-	1	1	0	34	18	8	
Cauliflowers	-	-	-	-	-	6	0	0	60	0	0	
Oats -	-	-	-	-	- 1	14	0	0	135	0	0	
Wheat -	-	-	-	-	-	16	1	10	228	13	9	
Permanent pastur	e	-	-	-	-	30	0	0	181	10	6	
						180	3	30	£2,294	17	8	

Note.—See pages 91, 92, 93, as to raw and effluent sewage.

BLACKBURN.

Population (about)	-	-	-	-	-	-	90,000
Rateable value	-	-	-	-	-	-	£235,127
Houses -	-	-	-	-	-	-	16,700
Waterclosets	-	-	-	-	-	-	730
Volume of sewage	every	24 hour	s -	-	(gal	lons)	1,500,000
Privies and midden	ıs	-	-	-	-	-	10,574
Privies, "pail" sys	tem	-	-	-	-	-	2,690
Ashpits -	-	-	-	-	-	-	5,287
Yearly cost of clear			on both	systems	-	-	£5,641
Amount received for	or refu	ise	-	-	-	-	£1,806

The rateable value of *Blackburn* is 235,127*l*., and a population of about 90,000 is here grouped together in 16,700 houses on an area of 3,620 acres. There are at present only 730 waterclosets in the borough, and the fæcal waste of the inhabitants is therefore principally disposed of by 10,574 of the "old Lancashire middens," and by 2,690 privies of more modern construction on the "pail" system; there are also 5,287 ashpits for collecting this form of house waste.

The borough has been sewered; the works were commenced in 1850, and finished in 1873, at a cost, including subsidence-tanks, of 78,2451.

The old drains have been utilized to convey the rainfall off roads and streets by 10 outlets into the river; whereas, the new drains are used for the sewage proper, and as all the old middens are drained into the new sewers, the composition of the sewage of Blackburn is very similar to that discharged from an entirely water-closeted town, the proportion of putrescible organic matter in solution in the sewage being slightly less, whilst the organic matter in suspension is somewhat greater.

The Rivers Pollution Commissioners caused numerous samples of the sewage of both midden towns and watercloset towns to be analysed in their laboratory, and from the results of these analyses, they were enabled to say:—"The retention of the solid excrements in 'middens' is not therefore attended with any considerable diminution in the strength of the sewage, although the volume even in manufacturing towns is somewhat reduced. It seems hopeless, therefore, to anticipate any substantial reduction of sewage pollution by dealing with solid excrementitious matters only."

In 1865 the main outfall sewer discharged direct into the "Blake-water," and caused serious pollution, not only to that river, but also to the Darwen into which the Blakewater emptied; the nuisance was complained of by the riparian owners, and a Bill was filed in the Court of Chancery by Sir William Fielden, Bart. (of Feniscowles), praying that the corporation might be restrained from polluting the river Darwen

with the sewage of Blackburn, and an injunction was granted.

The defendants applied for time to enable them to cause remedial works to be constructed, and the Court gave the time asked for. The corporation then directed subsidence tanks to be built near the river Blakewater on the eastern boundary of the town, and caused the sewage to flow through these tanks and to be treated by the "lime-process" (i.e., adding a certain proportion of "milk of lime" to facilitate deposition) before the sewage entered the river; but this did not sufficiently mitigate the nuisance, and although the supernatant liquid flowed off comparatively clear, the method failed to purify the sewage so as to render it admissible into the river, for at a short distance from the outlet of the sewage-tanks the river was still in a most offensive condition of putrefaction. The plaintiff then brought an action in the Court of Queen's Bench and laid the damages at 20,0001.; the case came on for trial and was referred to Mr. Manisty, Q.C., who found for the plaintiff, but only awarded to him 1,250l. damages, and costs; the cost of the suit in Chancery and the damages and costs in the action at law amounted however to about 12,000l.

The corporation then, as advised, determined to adopt sewage irrigation, and for this purpose promoted a Bill of Parliament in the session of 1870; there was great opposition to this Bill, but it was passed and it empowered the corporation to acquire 1,090 acres of land, in the townships of Pleasington, Houghton, and Samlesbury. The cost of obtaining the Act was 6,500l. In 1872 the corporation took on a lease, for 20 years, at the yearly rent of 484l. 179 acres of land in the townships of Pleasington and Houghton, and directed the outfall sewer to be extended to Higher Park, Pleasington, and 90 acres of the 179 acres, upon which the sewage would gravitate, to be drained and especially laid out to receive it. The works have been carried out a cost of 11,600l., and about 1,500,000 gallons of sewage every 24 hours have flowed on to the farm, and have been used in irrigation ever since the works were completed. The 90 acres have been cropped this year (1875) 74 acres with Italian rye grass, and 10 acres with mangolds and turnips, whilst the remaining six acres of the land were in fallow and roads. In order to dispose of the produce without loss, the corporation purchased The total expenditure for the year ended 31st December 1875, including working expenses, purchase of stock, and also a sum of 4801., the cost of permanent improvements, was 6,523l. 2s. 9d., and the receipts for the same period, including sale of fat stock, were 5,7811. 6s., 10d. It is believed that this year (1876) the receipts will more than cover

In order to extend their irrigation the corporation, in 1875, concluded

the purchase of 475 acres of land at Samlesbury, at a cost of 69,500*l*., including expenses of arbitration, easements, &c., being at a rate of about 100 years purchase of the present rents, and they have directed their engineer to extend the sewage conduit on to this newly acquired land at an estimated cost of 7,650*l*., to which the cost of draining and preparing the land must be added. The farm at Pleasington and Houghton has a light loamy soil upon a gravelly subsoil; it has been under drained to a depth of 4 feet, the drains being 18 feet apart. It is intended to drain the land at Samlesbury, which is partly loam and partly stiff clay.

In addition to the cost of disposing of the sewage in irrigation, there is the cost of cleansing the "middens" and the privies on the "pail" system; this amounts to 5,641*l*. 2s. 8d. yearly, and the annual receipts for

the refuse from both kinds of privies is only 1,805l. 12s. 5d.

CHELTENHAM.

Population (about) -	-	-	-	-	-	45,000
Rateable value	-	-	-	-	-	-	£217,849
Houses -	-	-	-	-	-	-	8,725
Waterclosets	-	-	-	-	-	-	8,500
Cost of outfall wor	rks, pu	irchase ai	nd layi	ng out o	f farm	-	£18,000
Volume of sewage	every	24 hours	3	-	- (gall	ons)	1,250,000

Privies are cleansed at the expense of the occupiers of the houses to which they belong.

Cheltenham.—The sewage of this township, which has an area of about 2,000 acres and a resident population, including portions of Charlton-Kings, Leckampton, and Prestbury, of about 45,000, living in 8,725 houses, and a rateable value of 217,8491, is disposed of in irrigation. The natural drainage of the district is into three streams flowing from east to west, i.e., Wyman's Brook on the north, the Chelt in the centre, and the Hatherley Brook to the south; all the sewage, however, runs towards the Chelt and the Hatherley Brook, near which streams the subsidence-tanks have been constructed, from which it flows, by gravitation through earthenware pipes to the farm. The local authority have in contemplation to conduct by pipes in a northerly direction a portion of the sewage from the tank near the Chelt on to land in the parish of Elmstone-Hardwicke, abutting on Wyman's Brook, and if the proposal be carried out, a great object will be obtained in bringing under sewage irrigation an extended area of land admirably adapted for the purpose; and as the owner and tenant of the land are willing to join in an agreement for 14 years, a degree of permanence will be assured; the tenant will take the responsibility of dealing with the sewage on his own land so as not to occasion nuisance or injury to others; he will also pay a fair rent for it. The watercloset system is generally adopted, there being about 8,500 in the town. The average volume of sewage every 24 hours is 1,250,000 gallons, and as stated above, this flows from the main outfall-sewer into subsidence-tanks, which are constructed with transverse divisions to intercept matters in suspension, and by an arrangement the sewage as it flows through the tanks works a turbine and chain pump; by this means the "sludge" is pumped up, and mixed with the house refuse and ashes, (about

3,234 cubic yards). There is no permanent accumulation of this refuse. The cost of cleansing the tanks and the receipts for the last three years are—

Year.	Cost of cleansing work	tank s the	and incidental reto.	Receipts for sale of sludge, mixed with ashes, from domestic fires.				
1873	£ 237	s. 9	d. 8	£ 293	s. 7			
1874	278	0	2	271	16	0		
1875	296	6	1	347	5	0		

Before irrigation was adopted, proceedings were threatened against the Improvement Commissioners, but no action arose, and in 1870 they purchased a farm of 131 acres (6 acres arable and 125 acres in permanent pasture) at Boddington on the western side of the town, and distant therefrom about two miles; the soil is a stiff clay, and the land has a gentle slope from east to west. The sewage is delivered by the earthenware conduit from the tanks on to the high part of the farm, it is occasionally applied to 200 acres of land adjacent to the conduit, for which the tenants pay to the Improvement Commissioners 7s. per acre for each dressing of sewage, amounting last year to the sum of 156l. whole of the land at the farm, with a trifling exception, can be irrigated from the summit; there are various branch-pipes for the delivery of the sewage to different parts, and these branches are to a great extent laid in cuttings of a moderate depth, open-carriers having been found objectionable as the cattle trod them out of form, the land being grazed during the greater part of the year. The undulating form of the land, and the arrangement of the branch conduits at different levels afford facilities for passing the sewage again over the lower portion of the farm when it has been over the higher portion of it, and thus is insured more perfect purification of the water before it flows into the Chelt and Hatherley Brook. The sewage-farm has been let at a yearly rent varying from 815l. to 861l., and is now let at a rent of 800l. per annum, subject to the Improvement Commissioners undertaking the duty of applying the sewage, at a cost in labour of 150l. a year, to which must be added the amount of rates and taxes which they also pay of about 50l. a year. There are only three residences. two homesteads, and about 20 scattered cottages near the farm. Previous to the adoption of irrigation, a process of treating the sewage by lime, per-chloride of iron and Bird's powder was tried, but the result was unsatisfactory. No complaint has ever been substantiated since the adoption of irrigation, and there is not now, even in hot summer weather, any nuisance caused by the effluent from the sewage farm. The cost of the sewerage works has been to the present time 53,400l., including purchase and laying out of farm and building tanks.

CHORLEY.

Population (about	t) -	-	-	-	-	-	20,000
Rateable value	-	-	-	-	-	-	£54,407
Houses -	-	-	-	-	-	-	4,000
Waterclosets		-	-	-	-	-	200
Cost of outlet w	orks, p	urchase,	and	laying o	ut farn	as at	
Common Bar	nk and	Plymouth	Bri	dge -	-	-	£16,550
Volume of sewage	e every	24 hours	-	-	(gal	lons)	500,000
Privies and midde	ens	-	-	-	-	-	1,600
Privies, "pail" sy		-	-	-	-	-	700
Cost of cleansing			system	ms	-	-	£709
Amount received	for refu	ise	-	-	-	-	£186

Chorley (Lancashire). - Area of the district 3,613 acres, population about 20,000; annual rateable value, 54,4071. There are about 4,000 houses, 200 waterclosets, and 1,600 privies, but these latter are being gradually abolished and the "pail" system introduced, and about 700 privies are now reconstructed on this system. The district, with the exception of a small area at Cowling and Botany, was sewered in 1855, at a cost of 17,000l., and the sewage then gravitated to one outfall in the river Chor. Complaints were repeatedly made to the Improvement Commissioners by the Reverend J. Sparkling, Mr. Henry Alison, Mr. R. Townley Parker, Mr. E. E. Silvester, and Mr. Randolphus de Trafford, riparian owners, of the nuisance caused by the sewage of the town being discharged into the river Chor and thence carried down into the river Yarrow, which polluted and rendered offensive the water of the Yarrow from the confluence of the Chor to below the village of Croston, and in July 1867 Mr. Edward Silvester and Mr. Henry Alison filed a bill of complaint in Chancery and prayed, "That the " defendants be restrained by injunction from causing or allowing the " sewage to be discharged, or to flow into the river Yarrow so as to be " a nuisance and pollute the said river." The defendants (the Chorley Commissioners) by their counsel admitted that the discharge of sewage into the Yarrow, by means of the Chor, had polluted the river, and that the works constructed by them had become a nuisance. A perpetual injunction was issued to restrain the defendants from continuing the same, such injunction not to take effect until the expiration of 12 months from the date of the decree, 23rd November 1867, or until the expiration of such further period as the Court should from time to time direct. With the intention of diverting the sewage from the Chor and Yarrow and utilizing it in irrigation the Improvement Commissioners, on the 21st October 1867, took on lease for 21 years, at a yearly rent of 1301., a farm of 87 acres, at "Common Bank," about a mile to the West of Chorley, and subsequently, in 1870, purchased it for 6,450l., and caused it to be laid out to receive sewage. The outfall-sewer was extended and continued on to the farm by cast-iron pipes; permanent carriers to distribute the sewage were also constructed of brickwork, stoneware-pipes and wood; and suitable farm buildings, were also erected; these works cost 4,800l. As soon as the works were completed, the sewage, which is estimated to be about 500,000 gallons every 24 hours, 200,000 of this being subsoil water, flowed continuously over the farm. The land, which is for the most part poor vegetable soil, with a stiff clay subsoil, has been underdrained to

a depth of 3 feet 6 inches, the drains being 16 feet apart. The local authority obtained power in 1871 to acquire additional land for the purpose of sewage utilization, and in 1875 purchased and laid out an area of 46 acres, part of "Kingsley's farm," at Plymouth Bridge, at a cost of 5,300l.; this land has a clay subsoil, and is arranged for the purpose of receiving the sewage of the Chorley Moor district. The Improvement Commissioners have since let this land with the sewage, at an annual rent of 90l., the tenant undertaking to distribute and cleanse the sewage, so as not to cause a nuisance.

The sewers are ventilated by 120 open grids, in the surface of the streets near the manholes, by rain-water pipes from the eaves of buildings, by pipes carried up at the gable ends of buildings, and by connexion with the chimney-shaft of the Water Street mill. No complaint has been made of the state of the purified effluent water flowing

from the sewage farm into the Yarrow.

The working of the "pail" system is an annual loss, costing more than cleansing privies and middens, but it is believed that the removal, once a week, of the excreta under the "pail" system, will improve the health of the inhabitants. The expense of cleansing the privies, and "pails" for the year ended 31st May 1875, was 708l. 15s. 4d., and the

receipts for the refuse were 1861. 3s.

The sewage farm was cropped in 1875, with oats 20 acres, Italian rye grass 20 acres, wheat 3 acres, Swedes 7 acres, while of permanent pasture and meadow there were 39 acres, and osiers 1 acre. The meadow land produced two tons of hay per acre, which sold at 7l. per ton; the Italian rye grass, in four cuttings, 10 tons per acre, and realized 16s. 8d. per ton; the oats yielded 50 bushels and 2 tons of straw per acre sold for 3s. 6d. per bushel and 70s. per ton; the swedes 15 tons per acre, and sold for 1l. per ton, and the 1 acre of osier realized 11l. There is a dairy of 11 cows kept on the farm; there are also 2 bullocks 24 young stock, and 5 pigs feeding. The farm is worked by 3 horses.

DONCASTER.

Population about 20,000.

Waterclosets are not generally used.

The town is sewered, and the houses are drained.

The volume of sewage flowing to the sewage pumps is about 600,000 gallons per day; or about 219,000,000 gallons per annum.

Flood-water from the surface of the town overflows to the rivers.

The 600,000 gallons of sewage is pumped daily on to the land of the Sewage Farm.

The works to store and pump the sewage have cost 20,000l.

The lift is 52 feet.

The Sewage Farm is 264 statute acres of light sandy land.

The rent was 25s. per statute acre.

The corporation pump the sewage, and obtain a rental of 800%, per annum, or about 3%. per acre.

The land has been three years under sewage cultivation; but only about 115 acres have received dressings of sewage in this time.

The entire pumping of one day, 600,000 gallons, has been disposed

of over one acre.

The usual course is to distribute this volume of sewage over 5 acres.

Italian rye grass has received per acre in one year at a rate of 13,000 tons, or a vertical depth of sewage of 130 inches. The land during the season would readily have disposed of double this volume of sewage, 260 inches,—if it had been desirable so to dispose of it. The 130 inches were actually required by the grass.

Doncaster.—This borough has an area of 1,690 acres, a population of about 20,000, and a rateable value of 68,721l. 10s. There are in the borough 4,300 inhabited houses; the existing water supply is defective, consequently waterclosets are not generally used. The town has been sewered, but not more than one half of the excreta of the inhabitants flows to the pumping-station at the outfall-works. The main-sewers are of brickwork, and the branch mains of sanitary pipes. The sewers are ventilated by means of open grids in the covers of manholes at the street surface; and, in some instances, by pipes carried up the gable ends of the houses above the roofs. The sewerage works were completed in 1870, under the advice and superintendence of Mr. B. S. Brundell, C.E., and the sewage then flowed by an existing outlet into the river Don navigation. The proprietors of that navigation, in the autumn of 1870, filed a Bill of Complaint in Chancery, and obtained an injunction. The corporation, as advised, not having a defence, consented thereto, asked for time to be given in which to carry out remedial works, and the Court granted two years. The corporation then directed Mr. Brundell to examine and report on the best means of disposing This he did, and reported in favour of irrigation. advising that the sewage should be intercepted from the river and pumped on to land, the property of the Corporation at Long Sandall. Subsequently, the works, as designed, were carried out, at a cost, of 20,000l. The whole of the sewage of Doncaster, with the exception of that part of the town known as Bennetthorpe, consisting of about 80 houses, gravitates to a point on the north side of the town, and flows into a sewage-well, first passing through iron screens fixed across the well to prevent choking of the pumps by cotton-waste, rags, and shavings thrown into the sewers. A volume of crude-sewage. varying from 500,000 to 800,000, or an average of 600,000 gallons, is pumped daily from 6 a.m. to 11 a.m., and from 1 p.m. to 5.30 p.m. The outfall-sewer is of sufficient capacity (6 feet in diameter) to hold the dryweather sewage flowing during the night; but in wet weather the sewage can be pumped, at night, into a tank on the farm, capable of holding 1,000,000 gallons. There is also a storm-outlet, by which the sewage, when extremely diluted by heavy rain-fall, can be pumped direct into the "flood drain." The sewage-farm is on the road leading to Thorne, on the north side of, and about two miles from, Doncaster; the corporation are owners of a considerable estate in this neighbourhood, and the "Wheatly Hills Farm," of 264 acres of land (partly light open soil and partly clay) has been laid out as a sewage farm, and has been let with the sewage. together with a suitable house and farm buildings, on lease for 14 years, at a yearly rent of 800%, the corporation undertaking to pump and deliver the sewage of Doncaster on to the farm at the yearly cost of about 3001. The clay-land is underdrained; but the light open land is only underdrained in the valleys and low places, and it is found that the purified drainage water finds its way readily through the light soil from long distances to these subsoil drains. There are five acres of land, especially laid out, and deep under-drained, which can be used as a filter on the "Downward Intermittent" principle, as proposed by the Rivers Pollution Commission. Up to the present time, however, the sewage has been utilised, and it has not as yet been found necessary to use the "filter" as an auxiliary to the irrigation process. The Sewage-Farm has now been in operation three years, no nuisance having arisen either at the pumping-station or on the farm. The distribution of the sewage over the land is judiciously managed, as none of it is allowed to stagnate, and thereby cause nuisance, and destroy the crop. The whole of the sewage of the night and following morning is pumped on to the farm by 11 o'clock in the forenoon, and the longest period during which the sewage is allowed to be at rest in the main outfall-sewer is between 6 p.m. and 6 a.m.

The crops grown this year (1875) to which the sewage has been applied, are: beans, 13 acres; peas, 6 acres; oats, 7 acres; barley, 35 acres; wheat, 51 acres; Italian rye grass, 35 acres; mangolds, 34 acres; swedes, 16 acres; potatoes, 8 acres; white turnips, 6 acres; hay, from permanent grass, 7 acres; permanent grass fed off, 22 acres; market garden produce, 12 acres; and there were also in fallow 8 acres.

The bean crop was a good one; the pea crop, which was partly good, and sold green, produced 10l. 10s. 0d. per acre; the oats were light, owing to the drought in March, April, and May; the wheat made excellent straw, but the crop was damaged by the heavy rain in June and July, and gave only an average yield; the four cuttings of Italian rye grass produced 30 tons to the acre, and sold for 16s. 8d. per ton; the mangolds were, owing to the drought and deficiency of sewage, late in starting, but as soon as the sewage was applied they grew well, but did not, however, produce more than 26 tons to the acre, and sold on the ground for 151. 15s. Od. per acre, the buyer to "pull and lead off;" the swedes also only yielded a light crop, and sold for 71. 10s. 0d. per acre; the potatoes gave a good crop, and sold for 201. an acre, the buyer to get and cart them off the farm; the market garden produced very excellent crops, which commanded good prices, and were highly successful, especially that portion (3 acres) planted with fruit trees, the currants being exceedingly fine.

In addition to the waterclosets in use in the borough, there are 2,553 ashpits, having privies connected with them, and 525 separate ashpits; these are emptied by scavengers employed by the corporation, at a yearly cost of 539*l*., and 310*l*. is received for 4,400 tons of refuse removed yearly, and sold to farmers in the neighbourhood, who use it

as manure.

PARTICULARS OF MACHINERY.

Power of Engine and Sort of Engine.

Two compound beam engines, of 35 nominal horse power each with crank and fly-wheel; slide-valves worked by eccentrics; double expansion slides on high-pressure cylinder.

Cost of Engine and Boilers complete.

5,4051. Cannot give engines and boilers separately.

Gallons per hour lifted. 80,000 gallons (7th April 1873).

Head.

Nett, including friction, 56.5 feet.

Fuel Consumed.

(Coal; inferior Barnsley, somewhat weathered in trial (7th April 1873). 107 lbs. per hour.

Diameter of Pump.

Double acting; 20 inches diameter.

Length of Stroke of Engine.

Low-pressure cylinder, 4' 6" stroke. High-pressure do. 3' 1\frac{1}{2}" do.

Number of Strokes per Minute. 22 revolutions.

Trial of one Engine for One Week, from 23rd February 1874 to 1st March 1874.

Time of pumping, $45\frac{3}{4}$ hours. Coal consumed, 3 tons=147 lbs. per hour of actual pumping. Number of stoppages, 11. Gallons pumped, 3,843,000. Tons pumped, $17,156\frac{1}{4}=375$ tons per hour.

HARROGATE.

Population (average	(e)	-	-	-	-	-	12,000
Rateable value	-	-	-	-	-	-	£50,000
Houses -	-	-	-	-	-	-	1,500
Waterclosets	_	-	-	-	-	-	1,620
Cost of main sewer	S	-	-	-	-	-	£15,583
Cost of outlet work	s and	laying o	out land	at Jenn	y Plain	-	£1,150
Purchase of land at	outle	et works	at Wet	herby L	ane	-	£4,484

Harrogate.—This is essentially a water-closeted town; the area of the district is about 1,300 acres. Resident population, about 8,000. augmented in the season, from the months of May to October, to about 16,000; the annual rateable value is 50,000l. There are 1,500 inhabited houses, and 1,620 waterclosets in the township, and very few common privies. The waterworks belong to a private company. The "Coppice" stream, a tributary of the "Oak Beck," flows through the town, and that portion of the river-channel in the town has been covered over: into this stream several of the old sewers discharge. In 1867 complaint was made by a bleacher (Mr. Wood, of Rawden, near Leeds), whose bleachfields are on the "Oak Beck," of the fouling of the stream by the sewage of the township, and proceedings at law were threatened. The Improvement Commissioners compromised the matter by paying 580l., undertaking "not to discharge any more sewage into the stream." In order to give effect to this agreement, they directed their surveyor to prepare plans of main sewerage works for the township; these works were, in 1869, carried out at a cost of 15,5831., and to cleanse the daily and nightly volume of sewage, which is estimated at about 168,000 gallons (inclusive of about 83,000 gallons of spring water), the Improvement Commissioners obtained a lease of 47 acres of land, a stiff clay soil at Jenny Plain, one mile from the town. This land they caused to be specially laid out, and subsidence-tanks to be constructed into which the outfall-sewer should discharge, the sewage to flow from thence through stoneware pipe carriers on to the land, and the effluent water run off into the "Oak Beck." The cost of these works was 1,150l. In April 1869, about two months after receiving the 580l.

and while the works of sewerage and irrigation were in progress, Mr. Wood commenced a suit in Chancery against the Improvement Commissioners, and in January 1875 obtained an injunction to restrain them from polluting the "Coppice" stream and "Oak Beck" with the sewage of the township. From the decree of Vice-Chancellor Bacon the Commissioners appealed, but the Lords Justices affirmed the decision of the Court below, and on application by the defendants the time for carrying out the remedial measures was extended to April 1st, 1875. In February 1875 additional intercepting sewers were commenced for diverting the sewage from the "Coppice Stream," and conveying it to the irrigation works, but it was found impossible to complete these works by the 1st of April 1875, and an application was made to the Court for a further extension of time, and it was extended to the 1st of July 1875. In June the Improvement Commissioners applied for a still further extension, but the Court refused to grant it. In April 1875, the Improvement Commissioners purchased, at a cost of 2,2001., the Knox bleachfields, in the occupation of the plaintiff, Mr. Wood, subject to a lease he held for an unexpired term of four years, and on the 4th October 1875 they took on lease, for a term of 20 years, from the Ecclesiastical Commissioners, at the yearly rent of 300%, a farm of 247 acres, for the purpose of further purifying the sewage. This farm (of which only 120 acres are available for sewage irrigation) is situated on the north side of

the "Oak Beck," opposite to the present irrigation fields.

In December 1875, the Plaintiff applied to the Vice-Chancellor to issue an order of sequestration, this the Court did, but suspended the operation of it for two months. The Improvement Commissioners then directed their surveyor to prepare plans and estimates for a pipe sewer to intercept the effluent water from the irrigated fields and convey it into the "Oak Beck" at a point below the plaintiff's bleachfields, this having come to the knowledge of the plaintiff, he made overtures for a compromise, and after a conference with a deputation from the Improvement Commissioners he offered to withdraw from the suit, if they would pay to him the sum of 5,000l. and taxed costs; the Improvement Commissioners accepted his offer, but he subsequently varied it and asked for the whole of the costs "in and incidental to the suit;" this, however, the Improvement Commissioners declined to accept, and they have since directed their surveyor to continue the main outfall-sewer, by a syphon under the "Oak Beck," on to the new farm of 247 acres, and at once to lay out the land at an estimated cost of 3,216l., to receive the sewage. It is hoped that the area proposed to be irrigated will be found sufficient to cleanse effectually the whole of the sewage of the district, and thus, the Commissioners will be enabled to obey the order of the Court. The cost of the suit amounted to about 3,9201. The subsidencetanks are cleansed out of every three months, the deposit being mixed with the street sweepings and sold to farmers.

Upon the present sewage farm of 47 acres, there was grown, in 1875, 600 tons of Italian rye grass, and it sold for 10s. per ton. The cost of dealing with and distributing the sewage in 1874, including rent of land, was 2821. 10s. 5d., exclusive of interest and cost of works, and the

receipts for the grass were 562l. 11s. 1d.

The effluent water from the sewage farm was on our inspection clear and inoffensive; and the "Oak Beck," into which it flows has the external characteristics of a clean and pure stream, there being no appearances of sewage deposit on the banks or bed of the brook, and the vegetation on the margin of the stream being free from the peculiar brown fungoid growth the result of the presence of sewage.

To prevent the sewage of High Harrogate from polluting the watercourses which have their outfall in the "Nidd," the river from which the inhabitants of Knaresborough obtain their water-supply, the Improvement Commissioners have purchased, at a cost of 1,000*l.*, $13\frac{1}{2}$ acres of land at Wetherby Lane, and have caused this to be laid out as irrigation ground, and the sewage of that portion of the township, estimated at 42,000 gallons daily, is utilised thereon. The cost of the outlet-works for this portion and laying out the land was 3,484*l*. The Commissioners have let the land $(13\frac{1}{2} \text{ acres})$ with the sewage at a yearly rent of 52*l*., the tenant undertaking to dispose of the sewage so as not to cause a nuisance.

LEAMINGTON.

Population	, includ	ling th	e district	s of Li	llington a	and Mil	lver-	
ton	-	-	-	-		-	-	24,700
Rateable v	alue of	the be	orough	-	-	-	-	£113,400
Houses	-	-	-	-	-	-	-	4,500
Waterclose		-	-	-	-	-	-	8,370
Cost of ma			-	-	-	-	-	£16,239
Cost of out						inery	-	£24,239
Volume of	sewage	every	24 hours	s, upwa	ards of	(gall	ons)	800,000
Yearly exp					-	-	_	£1,035
Yearly am	ount rec	ceived	for sewag	ge -	-	-	-	£450

The royal borough of Leamington-Spa has an area of about 1,571 acres, a population of about 24,700, and 4,500 houses; the rateable value is 113,400l. Waterclosets are principally used, there being 8,370 in the town. The house refuse and ashes are removed from the ashpits by men and carts employed by the corporation, and about 3,000 cubic yards of this house-waste is collected annually, at a cost of 780l., and given away to farmers, there being no sale for it. A system of sewerage works was commenced in 1859 and finished in 1861, but additions are made from time to time, the total cost of their works being 16,239l. The sewers are ventilated by 157 grids in the covers of the manholes, and 200 additional ventilators are at once to be put to the mains sewers. On completion of the sewerage works in 1861, the sewage, which formerly flowed direct into the river Leam, was intercepted by subsidence-reservoirs constructed near the bank of the river on the west side of the town. The costs of these reservoirs. The precipitation of the sustank, and outfall-works was 8,000l. pended matters of the sewage was accelerated by mixing with it as it arrived at the tank a certain proportion of the "milk" of lime, and violently agitating the sewage as it flowed from the tank on its way to the reservoirs of subsidence. In these reservoirs a large quantity of highlyputrescible mud was deposited and the supernatant liquid flowed into the river, carrying with it, especially in heavy rainfall, considerable portions of this mud. The annual expense of working the lime process was 5001., and it failed to purify the sewage; the offensive state of the river became gradually intensified by the impure sewage of the town flowing into it, and eventually, after repeated complaints by Lord Warwick, Mr. Richard Heath, and Mr. W. Field, riparian owners, Mr. Richard Heath, on the 25th November 1864, filed a Bill of Complaint in the Court

of Chancery, and on the 1st June 1866, obtained an "interim injunction" to restrain the local board from polluting the river Leam with the sewage of Leamington. The local authority did not satisfy the Court that they were taking proper means to abate the nuisance, and an order of sequestration was, on the 2nd August 1867, issued, but suspended from time to time. Subsequently, in 1868, the local board caused the bed of the river to be cleansed, and paid the costs of this work, amounting to 1,500l., and also the costs of the suit, 5,000l. About the same time Lord Warwick caused an offer to be made to the Local Board to take from them on lease for 21 years the sewage of Leamington, and pay 450l. a year, provided it was delivered on to the Heathcote farms, a distance of 2 miles from the town. The local board accepted the offer on the 5th April 1870, and directed a cast-iron rising main to be laid from the works to the farm and pumping works to be erected and fitted with suitable machinery capable of pumping a volume of upwards of 800,000 gallons of sewage daily on to the farm; these works were finished and the pumping of the sewage to the "Heathcote Farm" commenced on the 5th October 1871, and the entire volume, except in heavy rainfall, has been pumped daily ever since that date. The soil of the farm is a fine loam on a sub-soil of gravel; the flood-water flows by a storm outlet into the Leam. The annual cost of pumping, including labour and materials, is 1,0351.

While the works were in progress the A.B.C. or Native Guano Company, on the 19th October 1868, made an offer to the local board to treat, free of cost, the sewage of the town by their process; and the local board, on the 4th March 1869, accepted their offer and permitted them to use the sheds, tanks, and outfall works for that purpose on condition that the company should remove the whole of the plant, which they proposed to erect on the site of the pumping station, when required to do so. The A.B.C. Company carried out their process until October 1871, and although it removed a large portion of the suspended impurities from the sewage, it, however, only took away therefrom a small proportion of the soluble polluting matters, and the effluent sewage was very little better than that which was obtained by allowing the raw sewage to settle in subsidence-tanks without chemical treatment.

The extraction of the "sludge" and drying it, especially in hot weather, in order to convert it into a manure, was attended with a nauseous odour and caused an intolerable nuisance, an extreme annoyance to the residents of Milverton, a populous and fashionable suburb of Leamington, who made repeated complaints to the local board of the "suffering they endured day and night from the offensive smell caused by "the method adopted by the company for drying of the sewage mud."

THE SEWAGE FARM.

The effluent water on the date of our visit to the farm, August 18th, 1875, was sufficiently purified to be admitted into the river, as not a trace of sewage could be detected in the clear and inodorous stream which flowed from the meadows into the watercourses. By the kindness of Mr. D. Tough (bailiff to the Right Honourable the Earl of Warwick), we are enabled to give a statement showing the cropping of the farm and quantity of sewage applied thereon for the past four years. Mr. Tough also sent to us the following very satisfactory account of last year's experience.

"The farm is about 370 acres, and the whole of this area except 96 acres has been irrigated with sewage. We have also supplied sewage to

ACHEAGE and CHOPPING of the Earl OF WARWICK'S HEATHCOTE FARM, with QUANTITY of SEWAGE and NUMBER of DRESSINGS applied to each Capp, from 1871 to 1875.

No. of Field on Plus.	Account.	Description of Crop. 1811.	Description of Crop, 1872.	Quantity of Sorage applied.	No. of Dress- ings.	Description of Grep, 1879.	Quantity of Sowage applied.	No. of Divers-	Description of Coop, 1874.	Quantity of Screnge applied.	No. of Dress- ings.	Description of Coop, 1973.	Quantity of Sowago applied.	No. of Dress- ings.	Requests.
13	a. r. p. 12 2 16	Not in occupation -		Tons. 30,109‡		Barley and cabbage	Tons. 35,737 ¹ / ₂ 23,497	-	6s, 2r, 6p. I. R. grass 4a, 0r, 16p. cabbage	Tons. 102,493 11,034	31 6	8a. 2r. 0p. I. R. grass	Tons. 58,317 2,903	18 2	Light loss and gravel subsail.
20, 21, 22	14 "0 31	Wheat and potatoes	Cabbage, parsaips, onlone, and	75,340	10	Wheat barley	=	=	8a. Or. Op. spring cabbuge -	33,095}	9	I. R. grass	29,280 158,265]	15 97	Ditto. —
				-	-	8a. 0r. 0p. spring cabbage planted after corn crop.	2,474)	-	6a, 0r. 51p. I. R. grass	54,290]	20	6a. Or. 31p. fallow for mangold after grass.	23,036}	8	-
23, 29 24	15 2 16		Wheat Potatoes	=	Ξ	Potators and mangold 3a. 0r. 0p. cabbage	8,637	=	Ternips after cabbage Wheat	5,584§ 3,945}	2 - 2	Beans I. Il. grass	140,075)	- 12	Clay, farmyard manured.
25	10 1 17	Barley	I. R. grass	104,883}	26	2a. 1r. 12p. peas	152,317}	29	Grass sown at Michaelmas -	18,894	29	9a. Ir. 17p. cabbago	32,708}	47	Light leam, and gravel subsoil. Light leam, and gravel subsoil.
26, 30, 52, 68	22 3 37	Permanent pasture	Permanent pasturo	=	=	Ilemanent pasture	=	Ξ	In. 0r. 0p. cabbage plants - 10a. 1r. 17p. cabbage after grass - Permanent pasture	12,294	12	Permanent pasture	2,4101	-	
27, 28	13 3 3	Peas	L.R. grass	122,832}	-	I. R. grass, 4 cuttings	126,518 93,830}	19 15	Ta. Sr. Sp. savoys	15,642} 37,407 38,289	12	L. R. grass	279,010	42	Clay,—farmyard manared. Light loam, gravel, and clay subsoil.
2	-			=	=		=		6a. 2c. 5p. wheat	24,895	13	Ε Ε	Ξ	Ξ	=
42, 45, 46, 67	8 3 0	Mangold	Permanent pasture Wheat	53,692]	3	Personent pasture I. R. grass	9,7353	1 17	sown at Michaelmas. Permanent pasture L. R. grass	37,174 67,2973	4 20	Permanent pasture	66,635	7	Clay, and marl.
43	9 0 4	Swedes	Barley Grass sown at Michaelmas -	16,152}	-		-		I. R. grass	121,483	29		117,460}	18	Cley, and gravel. Light leam and gravel subsoil.
44	6 3 17	Mangold -		Wheat, 22,120}	-	L.R. grass	126,603}	3	Fallow for roots after grass Beans	6,907		Fallow for roots (No. 43) - Wheat (grass grown at Michael-	18,0502	-	Dista.
47 48	10 0 32	Burley	Outs Coro.	45,095 }	7	Clover	51,136} 161,136	11	Wheat (grass at Michaelmas) - I. R. grass	17,937	4	ILR. grass Bears	166,470	16	Ditto.
49, 55, 56	23 2 8	Wheat :	Grass sown at Michaelman	20,886}	4	Wheat	=	1	Oats	= '	=	19a, 2r. 8p. swedes and turnips -	Ξ	=	Beavy siay.
50, 53	10 3 24	Permanent postere	Permanent pasture	66,383	2	Permanent pasture	=	=	Permanent pastere Brans	=	-	4s. 0v. 0p. mangold Permanent pasture Wheat	7,352	-	Farmyard manured. Farmyard manured, clay and mark. Heavy least, clay and mark solved.
54			Beans, 4 acres sewaged -	1,932		Wheat	30,407	-	I. R. grass	119,094}	19	L. R. grass	98,734	23	farmy and managed. Light learn, clay subsoil.
58,59	20 0 15	Peas, swedes, and turnips -	Wheat -	18,216)	2	Mangold and sweden	28,7792	4	Wheat	13,771)	2	Besns	=	=	Heavy clay, farmyard seasoned. Heavy loam, clay subsoil. Farmyard managed.
61 62	5 1 30	Barley	Swedes	=	=	Wheat	Ξ	1	Beans	=	-	Wheat Clover Potatoes	=	-	Ditto. Ditto. Light loam, farmyard manurol
64	10 1 34	Permanent posture L. R. grass	Permanent posture, 4 acres sewaged I. R. grass	2,276) 92,439±	18	Permanent pasture, 4 acres sewaged Wheat	12,489	8	Permanent pasture 4 seres follow for carrets and parsnips.	100	-	Permanent pasture Ta. Or. Op. cabbage	11,350	-	Done. Light loam, and clay subsoil.
*	"			-	-		-	-	4 acres follow for carrots and parsnips.	4,861		2s. 1r. 54p. mangold -	4,559}	4	
6		I. R. grass	L. R. grass	111,394	21	Wheat	27,886\	=	6a. Ir. 34p. petatocs Mangold	63,529	15	In. Or. Op. rhubarb strawberries Wheat Fallow for mangold	9,176)		Ditto.
65	9 2 3	Barley Not in occupation	Clover	29,5201	2	Wheat	3,455)	- 2	Mangold	=	-	Oats	= .	=	Cley, farmyard massized, Ditto.
71	7 2 36	Not in occupation	Swodes : : : :	3,000}		Sa. Sr. Sp. fallow Wheat	=	=	Turnips	=	=	Barley	=	=	Light loam, clay-subsoil, farmyard
72	9 1 36	Da	Wheat Sewage supplied to farmers -	104,641]	=	Swedes	344,196]	Ξ	Sewage supplied to farmers	270,133}	-	Clover	13,866 205,628	4	=
	370 3 29	Acresge of firm.	Total for 1872	927,961		Total for 1873	1,291,441}	-	Total for 1874	1,318,618}		Total for 1875 -	1,452,927		

the adjoining farmers on about 80 acres of land for which we received from 20s. to 30s. per acre. The sewage of Leamington is pumped to the farm daily, and is used in winter on fallow or grass-land, and in summer on grass, cabbage, carrots, parsnips, onions, mangolds and turnips. We never apply any sewage to the root crops, with the exception of cabbage, until May or June; but this latter crop is sewaged in the spring as soon as the weather will permit. We have tried sewage on corn crop, but found it difficult to apply it while the crop is growing, in fact sewage ought not to be applied to corn crops. The last season we had excellent crops of everything grown on the farm. The farm is worked with 13 horses which are all fed on the sewage produce and do remarkably well."

"We have also a dairy of 40 cows, the milk is sold on the farm at 11d. per gallon the cows are all stall fed in summer on grass, and in winter on turnips, mangolds, and hay and straw, cut into chaff, and a little artificial food. The calves are reared and sold when two or three years old; we also keep a few sheep on the farm. During the last two years we have gained 10 silver cups and a great many money prizes for

roots grown by sewage."

MERTHYR TYDFIL.

Population (about) -	-	-	-	-	-	55,000
Rateable value	-	-	-	-	-	-	£135,000
Houses -	-	-	-	-	-	-	10,778
Waterclosets	-	-	-	-	-	-	8,000
Cost of outlet se	wer, p	urchase	and la	ying out	t of land	l as	
filters, and as se	wage	farms	-	-	-	-	£53,330
Yearly rent of 59	acres	of land	held on	lease	-	-	£298
Volume of sewage	every	24 hou	rs, abou	t -	(gallons) -	1,200,000
Privies (2,800)	are	cleansed	at the	expense	of the o	ecupi	ers of the
houses to which t	hey be	elong.				- 1	

Merthyr Tydfil.—This urban sanitary district has an area of 17,714 acres, a population of about 55,000, and a rateable value of 135,000l. There are 10,200 inhabited and 578 uninhabited houses; connected with these are about 8,000 waterclosets and the drainage from about 2,800 privies. In 1864, the waterworks were completed, and it then became necessary to provide for the disposal of the used water which greatly augmented the volume of the sewage. Plans were prepared by Mr. S. Harpur, the engineer, to the local authority for the disposal of the sewage, and approved; the works were commenced in November 1865, but owing to the failure of the contractor, were not completed till 1868, at a cost of 28,0001.; the crude-sewage was then discharged into the Taff. Soon after the works were completed a Bill of Complaint was filed in the Court of Chancery by Messrs. Nixon and Company, colliery proprietors, Ynysowen, to restrain the local authority from polluting the Taff, and an interim injunction, afterwards made perpetual, was granted. In April 1869, the engineer to the local authority submitted a comprehensive scheme for disposal of the sewage by irrigation; this was sanctioned, it embraced the taking and laying out at Troedyrhiew, within the parish of Merthyr, 75 acres of land; also 60 acres of common land, and 240 acres of enclosed land in the parishes of Llanfabon and Llanwonno, at

from 8 to 11 miles from Merthyr, all in the basin of the Taff; these farms have a fine loamy soil with a gravelly soil. The outfall-works, consisting of 19,000 lineal yards of brick, timber, iron, and earthenwareconduit (from 12 to 24 inches in diameter) were completed in 1873. While these works were in progress the Master of the Rolls directed that means should be adopted for mitigating the nuisance in the Taff, by separating the coarser solid particles of sewage and prevent them flowing into the river; the local authority then ordered filter-tanks to be constructed near the outfall, and caused the sewage to be filtered through a medium of furnace ashes 3 feet deep, a small quantity of cream of lime being added to the sewage before filtration; this method not having satisfied his lordship he issued an order of sequestration, and from that order the local authority appealed. The Lords Justices of Appeal in July 1870 directed Mr. J. Bailey Denton, C.E., to examine and report on the best means of preventing the nuisance complained of, and he recommended that 20 acres of the 75 acres of land at Troedyrhiew should be laid out as land filters, and used on the intermittent principle proposed by the Rivers Pollution Commission; these works were subsequently carried out under his superintendence, and worked up to early in the year 1872. The addition of lime to the sewage was then discontinued, and the land-filter-beds have since been treated as ordinary irrigation ground, and are now so used, together with 230 acres of the other portions of the land, as a sewage irrigation farm. The average dry weather flow of the sewage is 1,200,000 gallons. There are fine storm outlets into the Taff. The cost of the several works was as follows: — Outfall-sewer from Troedyrhiew to the Ynyscadudug Farm, 16,002l. 2s. 10d.; building subsidence tanks, 387l. 15s. 1d.; laying out land-filtering areas (including drainage and the carriers upon 20 acres), 4,606l. 12s. 4d.; forming, draining, and making carriers on the remaining 55 acres at Troedyrhiew, 1,408l. 6s. 5d.; purchase and laying out, draining, and fencing the common land at Navigation Farm, 4365l. 11s. 5d.; purchase, laying out, and draining land at Ynyscadudug Farm, 14,3871. 6s. 0d.; purchase of Tyrybent estate, 30 acres, at Troedyrhiew, 3,0021. 2s. 6d.; purchase of Park Newydd estate of 67 acres, 9,170l. Total, 53,329l. 16s. 7d.

The sewage flows by gravitation on to the farms, and the annual cost of cropping the land and applying the sewage is 2,391l. 5s. 10d.; to this must be added the yearly rent paid by the local authority for that portion of the land held on lease (viz.) 298l. The accounts of the year have not been made up, but it is feared that the receipts will not cover the expenditure. The Troedyrhiew Farm of 70 acres, of which there are about 2 acres of roads, has this year produced the following crops: Italian rye grass, 34\frac{1}{2} acres; permanent grass, 5 acres; cabbage, 8 acres; mangolds, 6 acres; swedes, 5 acres; red wheat, 3 acres; beans, 4 acres; rhubarb, 1 acre; seed beds, 2 acres. The Navigation Farm (60 acres of common land, of which roads occupy one acre) produced Italian rye-grass, 15 acres; white oats, 35 acres; willows, 3 acres; mangolds, 1 acre; and swedes, 1 acre. Ynyscadudug Farm (93 acres only bore crops) produced hay from 83 acres of permanent grass; Italian rye grass, 4 acres; white oats, 4 acres; and swedes, 1 acre. There were very good crops of hay on the land at Ynyscadudug which realized 61. per acre (the land before the sewage was applied was let at 15s. per acre). The Italian rye grass realised 71. per acre on common land which was formerly worth 2s. 6d. per acre. The oats were sown late and only yielded a light crop. The wheat produced 25 bushels to the acre and a large quantity of fine straw. The mangolds and swedes produced each

30 tons to the acre. The Italian rye grass at Troedyrhiew was cut six times and gave an average of 6 tons per acre at each cutting, and fetched 11. per ton on the farm; the pickling cabbage sold for 501. per acre, and the other cabbage for 301. per acre.

In addition to the sewage 30 tons of stable dung was used on the Troedyrhiew Farm, which is situate within 250 yards of the village. No complaints have been made of nuisance arising from the farm, or of the condition of the effluent water flowing into the river, as it has invariably been bright and pure. The tanks are cleaned out every fortnight, and the "sludge" is mixed with the house refuse and dug or ploughed into the land.

The inhabitants living near portions of the sewage-farms speak of

them as the "gardens."

RUGBY.

Population (abou	it)	-	-	-	-	-	8,400
Rateable value	-	-	-	-	-	-	£45,000
Houses -	-	-	-	-	-	-	1,700
Waterclosets	-	-	-	-	-	-	1,400
Cost of outlet we	orks and	laying o	out farm	-	-	-	£5,800

This Local Board of Health district has an area of 1,617 acres, and a rateable value of 45,000l. The sewage of 8,400 inhabitants of Rugby, living in 1,700 houses, is disposed of in irrigation. There are 1,400 waterclosets, very few privies, and no cesspools. A system of sewerage has been carried out at a cost of 5,7641.; the works were commenced in 1852, and the main-outfall was into the river Avon. pletion of the works the late Mr. Walker applied to the local board to be allowed to divert the sewage from the river, and to use it on his own adjoining land, and concession having been granted to him, a reservoir was constructed, and the sewage was pumped therefrom through cast-iron pipes, laid over the entire farm, on which were fixed a number of hydrants, in suitable situations, and the sewage was distributed from thence, as required, by a flexible hose and jet.* The outlet into the Avon was then only used for storm-water, or when the application of the sewage to the land was from any cause interrupted. This mode of irrigation was carried on for some time; but as Mr. Walker did not deal with the whole of the sewage, the river became polluted, and an action at law was, in August 1855, commenced against the local authority by Mr. Charles Caldecott, of Holbrook Grange, a riparian proprietor, but a technical objection having been taken, the action was abandoned. The local board then discussed the best means of disposing of the sewage, and decided in 1857 to hire from Mr. Walker 65 acres of land, at the yearly rent of 2901, including rates and taxes, to construct subsiding tanks, and to cause the farm to be laid out on the surface irrigation principle, at a cost of 5,800/. A volume of 400,000 gailons of sewage every 24 hours (150,000 gallons being subsoil water,) has

^{*} The cast-iron pipes were extended over an area much larger than could be supplied with sewage, and the cost of pumping and of irrigation by hose and jet proved to be too expensive and was consequently abandoned.

flowed continuously since that date over the land. No complaints have been made of the state of the effluent from the farm into the river. The local board at Lady-day, 1874, sublet the land hired of Mr. Walker, to Mr. J. A. Campbell, at a yearly rent of 350l., the local board maintaining their right to dispose of the sewage upon the land, and paying the labour cost of the distribution. In 1871, in order to utilize the sewage of another portion of the district, the local authority hired of the rector of Rugby, about 13 acres of land, at the yearly rent of 54l., and caused the sewer to be extended, and the sewage to flow on to this land; they have since sublet it, with the sewage, for 79l. per annum.

Mr. J. A. Campbell has kindly given to us the following in formation:—

Acreage of Sewage Farm under Crop, 57a. 0r. 19p. Crops, 1874.

					a.	r.	p.
Wheat	100 1 10	-		-	21	3	22
Beans -	ornamo)	200	Tall His	-	4	2	29
Oats -		LOUE LO	True in the	-	8	2	2
Italian rye	grass	2 10		-	22	0	11
NAME OF STREET	NA III					-	
			Total	-	57	0	24
							_
Cash produ	ice of far	m -	-	-	701	11	11
Expenses, i			601.)	-	725	13	
			1000				
	Bala	ance aga	inst farm	-	£24	2	81

Note.—See pages 86, 87, as to raw and effluent sewage.

TUNBRIDGE WELLS.

Population (about)	-	-	Thous Land	-		23,000
Rateable value	-	The state of	-	oper specific	-	Nymba .	£142,914
Houses -			-	-	-	District!	5,750
Waterclosets	-	401-1102	-		-		5,635
Cost of outlet work				aying out of	fai	rms -	£87,243
Volume of sewage	eve	ry 24 hours	S	-	-	(gallo	ns) 650,000

Tunbridge Wells, an urban sanitary district in the counties of Sussex and Kent, disposes of the sewage of its 23,000 resident inhabitants by irrigation. The district has an area of 3,352 acres, and a rateable value of 142,914l. 10s.; the town portion is drained by main sewers of irregular form constructed of brick, the branch sewers are of stoneware pipes. Waterclosets are chiefly used, the number being 5,635 in the town. The sewage was formerly allowed to run direct into the Calverley Brook.

On the 24th November 1865, an injunction was obtained by Mr. Frederick David Goldsmid of Summer Hill Park to restrain the Improvement Commissioners from polluting the "brook," and the latter having failed to satisfy the court that they had rendered the sewage inoffensive, an order of sequestration was subsequently granted; this order, however, was suspended from time to time, and finally discharged

on 2nd July 1874, on the Commissioners undertaking to intercept the sewage, and practically purify it before it flowed into the brook; to defray the expense of cleaning out the Summer Hill Lake which amounted to 744l. 17s. 8d.; and also to pay the costs of the suit, about 3,000l.

To satisfy these conditions, the Improvement Commissioners caused intercepting sewers and outfall works to be constructed, and they also purchased two farms, one of 120 acres of stiff loamy soil 13 mile to the north, and the other of 165 acres of light open soil 31 miles to the south of the town. These farms are prepared and laid out for irrigation, and the sewage, which is not treated by any chemical process, flows by gravitation through subsidence-tanks, and a daily volume of about 414,000 gallons is thus delivered on to an area of 118 acres at the South Farm, and about 236,000 gallons on to an area of 100 acres at the North Farm, the solid refuse is removed from the tanks when necessary and sold to farmers, who clean out the tanks, remove the deposited material, and pay 65l. a year for it. The effluent water from the North Farm flows into the Calverley Brook, and that from the South Farm into the Brodwater Brook, and the County Ditch, which are tributaries of the Medway. Samples of this water are collected every fortnight by the farm bailiffs, and summitted to the Sewage Outfalls Committee. No complaint has been made of the state of the effluent water since the removal of the order of sequestration. The crops produced this year were, on the

NORTH FARM.

Italian Rye Grass, 30 acres.	Pasture and Meadow, 20 acres.	Wheat, 15 acres.	Oats, 10 acres.	Beans, 9 acres.	Barley, 3 acres.	Winter Oats, 5 acres.	Mangolds, 34 acres.	Swede Turnips, 3 acres.	Carrots and Cab- bage, 1\frac{1}{2} acres.
Per acre. 65 tons in five cuttings.	Per acre. A heavy crop of coarse hay stacked on the farm.	Per acre. — 5 qrs.	Per acre. 9 qrs.	Per acre. — 4 qrs.	Per acre. — 5 qrs.	Per acre. — 9 qrs.	Per acre	Per acre. — 25 tons	Per acre.

SOUTH FARM.

Italian Rye Grass, 21 acres.	Pasture and Meadow, 30 acres.	Hops, 22 acres.	Wheat, 17 acres.	Oats, 14 acres.	Beans, 4 acres.	Mangolds, 3 acres.	Swede Turnips, 5 acres.	Clover, 2 acres.
Per acre. 40 tons	Per acre. Cut for hay or pastured.	Per acre.	Per acre.	Per acre. 6 qrs.	Per acre. 3 qrs.	Per acre. 40 tons.	Per acre. 30 tons.	Per acre.

The cost of the sewage works (purchase of and laying out of farms, law costs and arbitration, expenses relating to purchase of farms, and compensation to tenants) has been 87,243*l*.

NORTHERN SEWAGE FARM.

PROFIT and Loss Account for the Year ending the 25th of March 1876.

RECEI	PTS.				Expenditure.	Cu
Dr. To sale of 11 cattle (8 steers 2 cows, and a calf	213 4 113 10 26 0 462 3 314 17 102 0 4 8 88 6 15 15 1 12 9 6 87 12	9 6 5 6 6 6 6 7 1,00	52 14	1	" purchase of 40 sheep " 40 0 0 2 horses 132 6 0 0 132 6 0 0 0 132 6 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	1,251 13
", hay, straw, and roots " corn " cultivations and young seeds " implements of hus- bandry " man applying sewage	96 5 231 15 119 9 254 2 29 18		76 19	6	" balance	471 19

Southern Sewage Farm.

PROFIT and Loss Account for the Year ending the 25th of March 1876.

RECEIPTS.	Expenditure.
Dr. & s. d. & s. d. To sale of 67 cattle (44 steers, 12 heifers, and 11 calves)1,110 5 3 , sale of 63 sheep - 160 15 10 , do. rye grass - 155 18 6 , do. wheat and oats 204 3 0 , do. mangolds, &c. 61 18 0	By valuation on the 25th March, 1875, brought forward - 2,370 0 9 "purchase of 65 cattle (47 steers, 11 cows, and 7 calves) - 727 11 0 "purchase of 76 sheep 154 13 0 "do. 1 horse 55 0 0
" do. manure - 30 0 0 " do. straw - 2 6 0 " do. hops (less commission, &c.) -1,363 5 2 " sale of hop-pole fagots 3 0 0 " do. cottage rents - 49 9 0 " outstanding accounts 83 3 7 " do. stock, 12 " sheep sold to E. Carey 31 4 0 AUSTEN'S VALUATION MADE TO 25TH MARCH, 1876. To 7 horses - 279 0 0 " 27 store beasts 534 0 0 " 12 sheep 32 8 0 " manures - 71 8 0 " hay and straw - 32 10 0 " cultivations and	", farm implements and smiths' work - 41 13 7
young seeds - 112 10 0 "hop-poles, manure, and labour - 505 0 0 "implements of husbandry - 234 2 6 "man applying sewage 29 18 0 2,007 11 6	" balance - <u>56 7 8</u>

WARWICK.

Area (acres)	-	-		-	-	-	
Population (about)		-	-	-	-	-	11,000
Rateable value	-	-	-	-	-	-	£43,339
Houses -	-	-	-	-	-	-	2,400
Waterclosets	-	-	-	-	-	-	2,000
Cost of main sewer:	S	-	-	-	-	-	£6,400
Cost of outlet work	s, pum	ping stat	ion, and	laying	out farm	1 -	£10,085
Volume of sewage	every 2	4 hours	-	-	(gallon:	s)	700,000

This borough has a rateable value of 43,339l., and a population of about 11,000 residing in 2,400 houses to which are attached 2,000 waterclosets; there are very few privies. Sewerage works were commenced in 1856 and finished in 1857, at a cost of 6,400l., and the sewage then flowed by two main outfalls into the Avon. The river soon became badly polluted and the riparian proprietors, Miss Ryland, Mr. Edward Greenway, M.P., and Mr. John Staunton, complained of the nuisance and threatened proceedings to compel the corporation to abate it. The outfall sewers were, in 1869, extended to a farm on the Stratford Road about 11 miles from the town. This farm of 135 acres, of stiff clay land, was taken on lease for 21 years at a yearly rent, for the first five years, of 404l., and for the remainder 16 years of the term at 4711. 10s. The corporation directed the farm to be laid out to receive the sewage, and a volume estimated at 700,000 gallons (one third being subsoil water) has been pumped every 24 hours to a height of 64 feet and distributed in irrigation over the land. The old sewers have been made available as conduits for surface water with outlets direct into the river. The sewers are being ventilated by pipes with swanneck tops carried up near to the surface of the streets into small detritus pits covered over with iron grids. The outlet sewage works, including engines, pumps, and pumping-main and laying out the farm cost 10,084l. 18s. 1d. The working expenses are 572l. 11s. 6d. per annum. From 1869 to September 1875 the corporation worked the farm, but have since leased it to a limited company for 21 years at the annual rent of 4711. 10s., and have assigned as reasons for so doing that there is an annual loss on the farm, that the corporation have had no capital to properly carry it on, and that the working expenses are taken out of the general district rate.

During the 12 months ended September 1875, the farm has been cropped with oats, 5 statute acres, swedes 6 acres, mangolds 15 acres, beans 3 acres, celery, cabbage and potatoes 4 acres, Italian rye grass 39 acres, and permanent grass 49 acres; besides these crops there was in fallow and roads an area of about 14 acres. The oats produced a very fair crop; the swedes were good and gave about 20 tons to the acre. The mangolds were a fair average crop of about 40 tons to the acre. Some of the Italian rye grass was excellent, especially that grown on the land which had been drained, this being cut six times. There was also a very good crop of hay got off the permanent pasture; the company propose to stock the farm and to under-drain the whole of it; the drains will be 12 feet apart, and at depths varying from 3 feet 6 inches to four feet; they also propose to erect suitable farm buildings.

The expenditure on the sewage-farm for 1873, including rent, labour, &c. was 1,369l. 6s., and the receipts from the sale of the produce was 907l. 6s. 10 $\frac{1}{2}d$; whilst in 1874 the expenditure was 1,494l. 18s. 8d., and the receipts were 1,071l. 10s. 4d.

Note.—See page 89 as to raw and effluent sewage.

WEST DERBY.

Public Offices, Stoneycroft, near Liverpool. 24th April 1876.

WE now furnish the information asked for in letter of the 31st ultimo as to this Board's sewage farm, &c.

For the sake of convenience we have set out the inquiries below, and against them have placed the answers seriatim:—

Area in acres of land used and to be used for the utilization and purification of the sewage of the district. 207 statute acres. A plan is sent herewith.

- 1. If purchased, the cost?
- The nett amount paid owners for the land has been 30,325l. 2s. 0d. The total amount paid for tenants' compensation and for the costs of the owners and tenants is 3,916l. 1s. 9d., or about 166l. per acre.
- 2. If leased, the terms and rental?
- 3. The cost of preparing the

land?

- The nett amount paid for "laying out" the land only has been 8,934l. 9s. 8d., which includes wages, piece work, drain tiles and pipes; carting tiles and rock for roads; timber, lime, cement, cinders, horse keep, and such like, or about 43l. per acre.
- 4. The estimated annual working costs?
- For the year ending 25th March 1875 (the last year for which the accounts have been audited), the cost of cropping, cultivating, and applying sewage was 2,334l. 15s. 3d.

This amount does not include the instalments of the loan and the interest.

- 5. The daily volume of sewage in gallons to be applied?
- At 30 gallons per head per day. Population into eastern and western sewers, 24,100 = 723,000 gallons per day.

Remainder of population, 7,300, goes into corporation sewers.

- 6. The local population? -
- The population, whose sewage is already applied to the farm, is 18,600 persons; the sewage of 5,500 more persons will shortly be diverted into the tanks which are now being constructed at the farm, and are almost completed, and will thence be pumped on to the farm land.

The sewage of the remainder of the population of the district, viz., 7,300 persons, passes into the sewers of the corporation of Liverpool.

- 7. The number of waterclosets in use?
- 3,000 in western area, and 220 in eastern area.

 This is exclusive of waterclosets draining into corporation sewers.
- 8. The number of privies and ashpits?

In western area about 1,042 middens, and in eastern area about 591 middens. In the majority of cases there are two privies to each midden.

This is exclusive of those in corporation area.

9. The annual cost of cleansing these?

700l. a year. The work is done by a contractor. This includes those in corporation area.

10. The weight in tons of the refuse?

The probable weight from middens and dry ashpits to be removed per annum is about 17,000 tons in the whole of the district.

11. The price per ton obtained if sold? The refuse is the property of the contractor.

12. The total cost of the works and land and preparation of this land for use as a sewage farm is required? To 24th March 1876, 61,873l. 5s. 9d., which includes the items referred to in answers to the first and third queries; the surveying, engineering, and legal expenses, and all other costs and expenses.

The amount estimated still to be expended to wholly complete the works at the farm is 1,476l. 14s. 3d., making the total cost 63,350l. 0s. 0d.

13. The annual cost of working the Sewage Farm? See answer to query No. 4 above.

14. The estimated income to be obtained from the Sewage Farm? The total income of every description for the year ending 25th March 1875 (the last year for which the accounts have been audited) was 3,349l. 10s. 10d.

15. Is the land yet in use as a sewage farm, and, if so, what crops have been grown, and what did they sell for? Yes, and all but 30 acres has had sewage applied to it. In the year ending 25th March 1875, the crops and the amounts they realized, being the produce of the farm, were as follows:—

				£	s.	d.
Rye grass	-	-	-	1,135	17	4
Vetches	-	-	-	26	10	8
Mangel wurzel	-	-	-	228	16	2
Turnips	-	-	-	106	17	8
Carrots	-	-	-	121	9	7
Peas -	-	-	-	334	4	5
Barley -	-	-	-	55	17	0
Oats -	-	-	-	63	0	3
Cabbages and	savoys	-	-	109	15	7
*Potatoes	-	-	-	351	15	7
*Willows	-	-	-	12	10	8
						_

Total £2,546 14 11

(Signed) RADCLIFFE AND LAYTON, Clerks to the Board.

Note.—This farm had not been brought fully into operation when this return was made.

^{*} The land on which the potatoes and part of the willows were grown has had no sewage applied to it.

APPENDIX No. II. FILTRATION.

KENDAL.	
Area (acres)	410
Population, about -	- 13,700
Annual rateable value	- £44,600
Houses	2,727
Waterclosets	450
Sewerage works, cost	- £18,000
Sewage farm, cost	- £16,371
Repairs to buildings, cost	- £700
Laying out of filter beds on farm (cost) -	- £1,400
Cost, yearly, of disposing of sewage -	- £110
Receipts for corps and grazing	£495
Volume of sewage every 24 hours (gallons)	- 750,000

Kendal, an ancient market town and modern borough of about 13,700 inhabitants in Westmoreland, 262 miles north-west by north from London, is situate on the banks of the river Kent, and on the borders of the Lake district; it has a moist climate, the local rainfall being about the heaviest throughout the year of any town in England, ranging from 60 to 80 inches. Woollen cloth has been manufactured from the time of the reign of Edward III. There are at present large woollen manufactories, common Brussels and Kidderminster carpets, large tannaries, paper mills, and marble works. The waste and polluted water from these several works is now diverted from the river by the

new intercepting sewers.

This borough has adopted the process suggested by the Rivers Pollution Commission (i.e.) "downward intermittent land filtration," combined with irrigation, adapted to cleanse the filthy sewage produced by 13,700 inhabitants and the liquids polluted by manufacturers. The borough has an area of 410 acres and a rateable value of 44,600l. A system of sewerage was carried out between the years 1868 and 1872 at a cost of 18,000l. Connected with this system there are 2,727 houses, 450 waterclosets, and the overflow from about 1,600 common privies. The sewage flows by gravitation to the "Wattsfield Estate," an area of 66 statute acres, which the local authority purchased for 16,371l., about 248l. per acre. Subsidence-tanks were built at the outfall of the main-sewer into which sewage is discharged, and from thence flows over 16 acres of the land which had been levelled at a cost of 400l., or 25l. per acre. The area so prepared has, however, been found to be insufficient to purify the sewage, the effluent flowing from the land into the river having caused a nuisance, which was complained of by Captain Braithwaite Wilson and other riparian owners. The local authority then called in Mr. J. Bailey Denton, who advised that the whole of the 16 acres should be laid out as land-filter-beds at a cost of 1,000l., or upwards of 60l. per acre. The Board did not, however, consider that the work could be done for that sum, and directed that 5 acres only be so laid out, and this area has cost 1,400l., or 280l. per acre. A volume of sewage every 24 hours of about 750,000 gallons (of which about 350,000 gallons is subsoil water from springs tapped during the execution of the sewerage works) has flowed continuously on to the 5 acres of land-filter-beds, and occasionally, as required, on to the remaining 11 acres of land. This small area clarifies the sewage so as not to be a nuisance; but in practise it is found too limited for crops to be successfully grown upon it, and, therefore, the corporation have caused an additional area of 5 acres to be prepared for the reception of the sewage, and it is believed that upon the 10 acres of filter-beds not only will the foul waste of the

inhabitants and refuse from manufactures and dye works be properly cleansed, but that sufficient crops will be grown upon the land-filter-beds to pay the annual expenses of thus utilizing the sewage. During the year 1875, there has been grown on the present land-filter-beds (5 acres) cabbage, mangolds, carrots, celery, and rhubarb, which sold for 100*l*., on the other 5 acres oats, vetches, and Italian rye-grass, which realised 75*l*., and on the remaining 6 acres a good crop of hay which sold for 45*l*., and this plot has been fed off since the hay was got. The yearly costs of applying the sewage to the 16 acres is 110*l*., including 35*l*., the cost of cleaning the subsidence-tanks. The remaining portion of the farm, to which the sewage is not applied, has farm buildings upon it and the corporation spent last year in the repairs to these buildings 700*l*.; this land is let out as grazing ground and produces 275*l*. yearly.

The soil of the farm is a very fine sandy loam upon a subsoil of gravel, and the effluent water filtering through this into the river is bright and clear. The cleansing of privies is not done by the local board, but by

and at the cost of the occupier, and the refuse is sold to farmers.

APPENDIX No. III.

PRECIPITATION, CHEMICAL, AND MECHANICAL PROCESSES.

		BIR	MINGH	AM.			
Area -	-	-	-	-	(acres)	-	8,420
Population about	-	-	-	-	-	-	350,000
Rateable value	-	-	-	-	-	-	£1,229,844
Inhabited houses	-	-	-	-	-	-	83,420
Waterclosets, above	ut	-	-	-	-	-	8,000
Value of sewage,	every 2	4 hour	s (gallons) -	-	-	12,000,000
Privies "old syst	em"	-	-	-	-	-	35,000
Privies "pail sys	tem "	-	-	-	-	-	7,000
Ashpits -	-	-	-	-	-	-	25,000
Yearly cost of clea	unsing p	rivies	for 1875	-	-	-	£35,180
Refuse (128,512 t	ons) sel	ls for	-	-	-	-	£5,885

The borough has been sewered at a cost of about 250,000*l*., the sewage gravitating to a point at Saltley. In the first instance it was discharged direct into the river Tame, a small stream, which at a few miles from the works flowed through the estates of Sir Charles Bowyer Adderley, K.C.M.G., M.P. He complained of the nuisance caused in the river by the sewage, and in 1858, on his application, an injunction was granted by the Court of Chancery to restrain the corporation from discharging sewage into the Tame, but the Court granted time in which the corporation were to construct works to abate the nuisance. The corporation caused subsidence-tanks to be constructed near the main sewers outfall and the sewage to be diverted from the river; processes of sand-filtration, and also of upward-filtration were tried but were abandoned.

In 1861, the corporation purchased, at a cost of 8,000*l.*, 28\frac{1}{4} acres of land in order to obtain access to canal and railway, and for affording additional facilities for dealing with the mud arrested in the tanks. In 1866, Sir Charles Adderley again complained of the state of the river, and the corporation, in 1867, took on lease 128 acres of land in addition, at a yearly rent of 855*l.* with the object of cleansing a portion of the sewage by irrigation. They caused this farm to be levelled, laid out, and drained, and the necessary roads and bridges constructed at a cost of 11,250*l.*, or at a rate of 75*l.* per acre, but, in 1870 Sir Charles

Adderley again invoked the aid of the Court of Chancery, and obtained

an order of sequestration.

About the same date certain other owners of property near the subsidence-tanks also moved the Court to hinder the corporation from depositing on the ground sewage-sludge arrested in the tanks and the Court, in this case also, granted the injunction prayed for. Whereupon the council either removed the sludge or dug it into a portion of the farm-lands. Thus restrained on all sides, instructions were given to the borough surveyor, early in 1871, to submit surveys and levels of any lands he considered most suitable for dealing with the sewage by irrigation, and to employ such assistance as he considered necessary. In June of that year a comprehensive report was jointly prepared by Messrs. Blackburn, J. Chalmers Morton, Lawson, and Mansergh, and Doctors Voelcker and Hill, recommending the taking 2,000 to 2,500 acres of land near Kingsbury, about eight miles below the present outlet, and the construction of sewage-conduits for conveying the sewage thereto. This report was laid before the council, but the scheme being considered too costly, a special committee was instructed to again consider the whole question of sewage disposal, and acting on their advice the corporation promoted a Bill in Parliament in session 1872 to acquire powers to extend the main-sewer to a portion of the land before described at Kingsbury, and there to obtain 800 acres, on which to purify the whole of the sewage, partly by intermittent downward filtration, and partly by irrigation. The Bill passed through committee of the Commons after a lengthy opposition, but was thrown out on the third reading. The costs incurred to the corporation in promoting this Bill amounted to 10,644l. 7s. 10d., and not having passed placed the town in a dilemma; however, in order to satisfy the requirements of the Court of Chancery, the corporation purchased 24 acres of land, formerly held on lease, for the sum of 8,000%. and subsequently further increased the area of the farm at Saltley by adding to it a purchase of 101 acres, at a cost of 29,4001.; acting on the advice of Thomas Hawkesley, Esq., C.E., as to the best method of treating the sewage at the outlet-works (under their limited powers). The town council, in accordance with his recommendations, caused four additional sets of subsidence-tanks to be constructed, and the sewage to be treated by the lime process. A volume of about 12,000,000 gallons every 24 hours is thus, by the addition of 13 tons of lime, to a certain extent clarified and an average of 365 cubic yards, or about 300 tons of the suspended matters of sewage, are deposited in the tanks, or about 110,000 tons per annum. The total cost of the outlet works and tanks has been 58,8801. The corporation have permitted Major-General Scott, C.B., R.E., to carry on experimentally his process for treating sewage and converting the "sludge" into cement, but this has not been done to any great extent, because it is not remunerative. The corporation are now making arrangements for carrying the water, clarified by the lime process on to the adjoining lands at Saltley for irrigation and filtration, and it is expected that by these means a more complete purification of the polluted liquid will be effected.

The "sludge," amounting to 365 cubic yards daily from the subsidence tanks, is removed and dug into land, a portion of the farm, at a cost of 14l. 10s. per acre, at a rate of about one acre per week, or, in the whole, 56 acres during the year. With reference to the suit instituted by Sir Charles B. Adderley, it was in 1875 arranged that the order of sequestration should be discharged, and that the injunction should be varied so as admit of the corporation constructing new sewers within the town which they had been prevented doing for some years, as also that the sum of 6,000l. should be paid to Sir Charles Adderley in settlement of

damages, costs, and all claims to the date of order; and that all proceed ings in the cause should be stayed for five years from the date of order, on the corporation undertaking "not to construct new sewers too quickly."

The liquid sewage only represents a portion of the facal waste of the inhabitants, as a considerable portion of the solid excrement, mixed with urine and ashes, is received into the 35,000 old privies and 25,000 ashpits. There are also the 7,000 privies constructed on the "pail system," distributed over the borough, and the contents of these receptacles have to be dealt with by the scavenger, and last year (1875) 128,512 tons of this refuse were removed and sent to country depôts to be afterwards disposed of to farmers. Statements of income and expenditure on sewage farm, outlet and interception works, also on Major-General Scott's cement process, and further on the collection and disposal of excreta and house waste and ashes for the year 1875, and an approximate estimate for these services for the present year are given below, together with results of analysis of a sample of the effluent water flowing to the farm during March 1875.

INCOME and EXPENDITURE for the year 1875.

Income.	d.	Expenditure.	8.	d.
Interception Department :		Interception Department :		
Amount received for con-		Expense of cleansing		
tents of privies and		and removing con-		
"pails" 5,885 0	0	tents of privies and		
		"pails" 35,186	0	0
Outlet Department:		Outlet Department :		
Amount received for sale		Expense of cleansing		
of a portion of sludge - 202 10	0	tanks, removing and		
		disposing sludge - 12,778	8 0	0
Major - General Scott's		Major - General Scott's		
cement process 179 0	0	cement process - 33:	2 0	0
Farm produce sold - 2,130 0	0	Working expense of farm 2,54	7 0	0

Borough Surveyor's Office, Birmingham, January 24th, 1876.

Estimates of Income and Expenditure for the year 1876.

Income.	8.	d.	Expenditure.	e	d.
Interception Department :	-		Interception Department :	٥.	er.
Amount received for the			Expense of cleansing		
contents of privies and			and removing con-		
"pails"7,000	0	0	tents of privies and		
			"pails" 36,190	0	0
Outlet Department :			Outlet Department :		
Amount received for sale			Expense of cleansing		
of a portion of sludge - 200	0	0	sludge-tanks, remov-		
The state of the s			ing and disposing		
			sludge 12,825	0	0
Major - General Scott's			Major - General Scott's		
cement process 150	0	0	cement process - 300	0	0
Farm produce sold 2,550	0	0	Working expenses of farm 2,960	0	0

Borough Surveyor's Office, Birmingham, January 24th, 1876. CHEMICAL LABORATORY, Corporation Sewage Works, Birmingham.— CERTIFICATE—Sample of effluent water from new precipitating tanks at above, taken March 1875.—Examined for general impurities.—Copy; January 26th 1876.

			ovienes el a	Grains per
			de male con	Imperial gallon.
Total solid residue	containing	the borons	nove Tested	- 58.10
Mineral matter		alt vid steller	the best out	- 57.10
Volatile matter	- Car Policy	their side of a	with-Batiful S	- 7.00
Suspended matter	30-2 MO	Profit let-To	hard-roll of	1.68
Soluble matter	van - de farine	Mary Selection	The state of	- 49.42
Silica -	nels-sell frame.	second Inc.	- Commission	- 0.84
Alumina, oxide of	iron, and p	hosphates	Aut bring about	- 0.14
Lime -			The second	- 12.22
Sulphuric acid	Maria de Tra	Tele lance Parcet	the - drive	- 17:38
Chlorine -	1	TO THE REAL PROPERTY.	anin-S. confi	9.52
Free ammonia		101 HOSBIE	Silvino trans	1.218
Albuminoid ammor	nia .			0.042
=disintegrated an		O HOTETTA	hea agenz	0.420
Appearance -	imai Teruse			· Clear.
Appearance -			ROOME	
Smell -		A 2		Slightly
A stien on test was	doingeardel			ammoniacal
Action on test pap	er -	-	and the com-	Alkaline.

Owing to the construction of new tanks and other works, as well as the large area of land used for digging in the "sludge," the farm is much sacrificed. The valley, too, in which it is situated is an excessively cold one, consequently market gardening does not answer, the crops being late. Italian-rye-grass has been found to yield the best result; but the demand for this produce has not been large.

Notwithstanding the expense incurred by the corporation in clarifying their sewage prior to its discharge into the river Tame, the sewage of adjacent townships, with large and rapidly increasing populations, is being poured daily into the Tame, or into its tributaries, without any attempt at clarification. Recently the Council have convened a meeting of representatives of adjacent boards, and at such meeting it was determined to appoint a joint committee to consider and report with reference to the formation of a combined drainage district.

BOLTON-LE-MOORS.

The borough of Bolton has a rateable value of 311,5631. and a population of about 93,100, inhabiting 18,249 houses, which are spread over an area of 2,002 acres. There are only about 758 waterclosets, and the fæcal matters of the population are chiefly disposed of by the 10,380 "middens," and 700 privies on the "pail" system. The "middens" are drained into the sewers, consequently no inconsiderable portion of the solid excrement, partly in solution and partly in suspension, drains into the sewerage system. The borough has been sewered, but the whole of the sewage has not been intercepted, as four of the principal connexions between the main-sewers on each side of the Croal have yet to be made. The cost of the works up to this date (January 1876)

has been about 70,000*l*. The rainfall from the roofs of buildings and surface of streets ordinarily flows into the sewers, but in heavy storms the flood water is discharged by 18 storm-outlets direct into the river.

Before any intercepting sewers were constructed, the sewage flowed by about 100 outlets direct into the river, causing a nuisance and serious annoyance to the inhabitants living adjacent and near to the Mill Lodge of the Springfield paper-works. A memorial having been presented to Mr. Secretary Bruce by the owners and occupiers of property (being ratepayers) in the township of Bolton, he directed an inquiry, under the 29th and 30th Victoria, chapter 90, section 49, "as to the " alleged default of the corporation of Bolton in not having provided its "district with proper sewers, and polluting the river Croal." This inquiry was held on 19th August 1868 by Mr. Arnold Taylor, one of the inspectors of the Local Government Act Office. On receipt of his report, dated 17th December 1868, the Secretary of State directed that a copy of it should be sent to the corporation. After the lapse of nearly a year, no decisive steps having been taken in the meantime to abate the nuisance complained of, the Secretary of State directed (28th June 1869) that the plans and estimates of the borough engineer of Bolton (Mr. J. Baylis), in reference to the diversion of the sewage of the borough from the river Croal, together with any alternative plans that may have been prepared by instructions of the town council be sent to the Local Government Act Office for approval without further delay. These plans and estimates were submitted and approved, but a further delay having taken place in carrying out the works, the Secretary of State, being satisfied that the town council had been guilty of default, issued an order under his hand the 21st day of July 1869, directing that the works necessary for the diversion of the sewage should be commenced within 14 days from the date of the order, and that the works so commenced should be continued without intermission until completion. The intercepting sewers which have been constructed have cost 10,286l. In June 1870 the corporation entered into an agreement with the "A. B. C. (Native Guano Company)," whereby they contracted to erect works at Burden, near the southern boundary of the borough, at a cost of 16,578l., and the company, on their part, undertook to defæcate and purify the sewage, so as to render it fit to be admitted into the river; and in consideration for the use of the patents of the company, the corporation agreed to pay the working expenses of the process, and to deliver to the company one-fourth part of the manure manufactured at The volume of sewage which the works from the sewage-sludge. flows to the works every 24 hours is about 2,500,000 gallons; but, in addition to this, there is a further volume of 1,000,000 gallons also intercepted, which is at present discharged by one outlet into the river, as the four syphons under the river to connect this sewer with the main outfall are not finished. There is also an additional volume of about 500,000 gallons of sewage yet to be intercepted, which now passes by several outlets direct into the river.

The A. B. C. process was carried on up to June 1873, but was then abandoned, owing to the great expense of working it, and also because the manure manufactured from the sludge could not be sold.

We were furnished by the manager of the works (27th January 1876) with the cost of labour and materials required to treat 1,035,000 gallons (about half the present daily flow of the sewage of Bolton,) for a period of 57½ hours by the A. B. C. process, *i.e.*)

		£	s.	d.
Manager (Mr. Graham). Salary	-	2	17	31
Engine driver. (Wages.) -	=	1	10	0
Alum preparer. Do	-	1	4	0
Mixture grinder. Do	-	1	2	0
4 Labourers, each 11. 1s. 0d. (Wages)	-	4	4	0
Watchman on Sunday	-	0	2	0
Extra for overtime	-	0	8	0
71 cwt. of sulphate of alumina, at 1s. 81	d.			
per cwt.	-	6	1	4
132 cwt. of clay, at 4s. per ton -	-	1	6	2
81 cwt. of carbon (waste product of pru	s-			
siate of potash manufacture) -	-	1	4	31
Blood	-	0	1	0
8 tons of engine coal, 7s. 6d. per ton	-	3	0	0
Oil, tallow, packing, &c	-	0	6	0
Water and gas	-	0	12	0
		-		_
	£	23	18	1
	-	-		=

To this amount must be added contingencies and the cost of repairs to and deprecation of works and plant. (See also special report on this process by the Rivers Pollution Commission, 1870). The corporation have not been required (up to this date 27th January 1876) to deliver any manure to the order of the patentees, but there is, and has been for the last two years, stored at the works awaiting the order of the company 700 tons of this manure. The sewage is now only treated from 8 a.m. to 6 p.m. on week days and not at all on Sundays, and the whole of the sewage from 6 p.m. to 8 a.m. flows on Snndays untreated direct into the river. The process now used is also a patent one, known as the M. and C. method, and it was stated to us to be identical with the process of Mr. Goodall, which had been tried at Leeds. In carrying out the M. and C. process there is added to the sewage to be purified a mixture consisting of the following ingredients: lime, carbon (a waste product of the prussiate of potash manufacture), house ashes, soda, and per-chloride of iron. The materials are mixed in a "pit" and lifted therefrom by means of a dredger into a second mixing pit, from which the mixture is discharged slowly into the sewage as it flows through the works into two depositing tanks, each divided into three compartments, after which the treated sewage flows for a short distance along an open conduit and thence into the River Croal. The tanks are cleaned out every fortnight, and about 70 tons of "sludge" are removed therefrom and thrown into heaps at the side of the tanks to part with the moisture which it contains, but it has been found impossible to dry it without applying artificial heat. The cost of working the M. and C. process is stated by the manager to be less than that of the A. B. C. process, and we here append the statement which he supplied to us:

"To the chairman and members of the Bolton Corporation Investigation Committee.

> "Bolton Corporation Sewage Works, January 14th, 1875.

Gentlemen,

I beg to submit to you a statement of the cost for labour and materials required for the treatment of 2,500,000 gallons daily of sewage-water for a period of $57\frac{1}{2}$ hours, (i.e., 10 hours for five days, and $7\frac{1}{2}$ hours for one day in the week."

Cost of treating Sewage by the M. and C. process.

						£	s.	d.
Wages, &c.	per weel	k	-	-		2	14	0
One laboure			mixture,	&c.	-	1	6	0
Two ,,	at 11.			-	-	2	4	0
Two "	at 11.			-	-	2	2	0
Extra for ov			-	-	-	0	5	0
Lime, 7 tons	3 cwt.	, at	18s. 6d. p	er ton	-	6	12	3
Refuse carbo	The state of the s				per			
ton -			-	-	-	0	16	6
Salts, &c.			-	-	-	0	15	0
Coal, 5 tons		d.	-		-	1	17	6
Oil tallow pa			-		-	0	5	0
Water and g			-	-	-	0	10	0
								_
					£	19	7	3 "
								_

It will be observed that this volume of 2,500,000 gallons of sewage is the daily flow to the works, and that when the intercepting sewers are completed, the volume will be augmented to about 5,000,000 gallons, and as the works have been constructed for treating only 3,000,000 gallons a day of 10 hours, they will have to be considerably enlarged.

In February and April 1873, the corporation sold to Mr. John Higginbotham of Manchester, 50 tons of the manure manufactured by the A. B. C. process at 55s. per ton, but the persons to whom he afterwards sold it, complained of the quality of it, and he refused to pay for it, and the corporation had to commence proceedings against him to recover the amount.

The sewers in the town are ventilated by open grids in the manhole covers and also by 228 separate shafts carried up from the sewers to the surface of the streets and covered by open grids.

Besides the yearly cost of dealing with the present limited volume of liquid sewage, there is the further expense of cleansing the 10,380 "middens," the 700 privies on the "pail" system, and the yearly cost of this is 6,645*l*., but this is not all loss as the corporation receive for 51,290 tons of refuse removed from these receptacles, 4,494*l*.

The corporation in order to get rid of the sludge caused some of it to be mixed with the refuse from the middens, and have sold 100 tons of this mixture at 1s. per ton. There is, however, about 2,500 tons of the prepared sludge now lying at the works.

The M. and C. process, like its twin the A. B. C. process, merely removes the grosser parts of the suspended matters in sewage, but fails to remove the putrescible organic matters in solution, and therefore the clarified sewage cannot be admitted into rivers without causing pollution, this is conclusively proved by the following result of analysis of a sample of the effluent water by Dr. Henry E. Roscoe, F.R.S., Professor of Chemistry, the Owens' College, Manchester, which has been furnished to us by the town clerk.

The Owens' College, Manchester,
To the Town Clerk of Bolton.

January 22nd, 1874.
Sir,

"I beg herewith to send you results of careful analysis (1) of effluent water and (2) of manure, sent from the sewage department of the borough of Bolton by Mr. John Forster on the 27th of December last."

(1) EFFLUENT WATER.

				Grains	Parts
			pe	er gallon.	per 100,000.
Total residue -	-		-19	62.65	89.5
Loss on ignition	-335	out zio	200210	5.25	7.5
Nitrogen as nitrites ar	nd nitr	rates		0.23	0.3292
Free ammonia -	-	00	. 01	1.75	2.5
Albumenoid ammonia	-	-	-	0.448	0.64
Chlorine -	04 399	40.00	15-16	4.20	6.00
Temporary hardness	0. 10	street o	1 820	16·2°	to hall
Permanent ,,	-			20·0°	mol
Total ",	-	-	-	36·2°	55 , SI_S

"As regards the results of this analysis it appears that the water, as compared with London sewage, contains about half as much animal refuse or products of animal decomposition. As regards the inorganic portion, this water contains considerably more than the London sewage does. These animal impurities are not completely got rid of by oxidation: and, on keeping, the water has a putrescent smell, it cannot therefore be said that the process, whatever it may be that the sewage has undergone, has done much to render the effluent water innocuous."

(2) THE MANURE.

Total nitrogen	-	- Marin	-	0.76°/
Insoluble phosphate	-	es con tenue	-	0.93°/
Soluble phosphate	-	not be and	-	None.
Moisture -	-	orn still in	10.00	26.67°/
Loss on ignition	-	cools on he	-	49.80°/°

"From the preceding analysis of the manure in which I have only determined the constituents of importance, it will be seen that the quantity of total nitrogen and phosphates is so small that the value of the manure is certainly not greater than 11. per ton.

" (Signed) HENRY E. ROSCOE.

" To the Town Clerk, Bolton-le-Moors."

We collected a sample of the sludge of the M. and C. process, and caused it to be analysed by Dr. A. Voelcker, F.R.S.

Results of analysis of sample of the sludge from the M. and C. process carried out at Bolton-le-Moors.

This sludge in the condition in which it was received by me contained in 100 parts—

Water	-10	Oliver 1	Benezi.	60.83
*Organic matter	-	mus and	07020	14.66
Oxide of iron and alumina	150	0338470	bell and	3.81
Tribasic phosphate of lime	841 0	mna 🚅 🤞		0.69
Carbonate of lime -	10	tille self	o oligin	8.18
Sulphate of lime	W.C	salt - The	Rious!	0.59
Alkaline salts, magnesia -	1.17.0	p and Aq	en ch	1.70
Containing potash			0.30	
and chloride of sodium	-		0.04	
Insoluble siliceous matter (sand	and	clay)	TEN-D	9.54
		-1 (1)		-
			DIAM A	100.00

* Containing nitrogen - - - 0.41 Equal to ammonia - - 0.49

In the sample of Bolton sludge there is in a ton:	8.	d.
$15\frac{1}{2}$ lbs of phosphates, which at 1d. per lb. are worth	1	31
$6\frac{7}{10}$ lbs. of potash ,, $2d$. ,,		1
Nitrogen equal to 11 lbs. of ammonia which, calculating		
ammonia at 8d. per lb., is worth	7	4
	_	
Total estimated money value of 1 ton of Bolton sludge	9	81

If the sludge were dried sufficiently to leave only 15 per cent. of moisture in the material it would have the following composition:

	Moisture	-	-	-	-	-	15.	00		
	*Organic matter	-	-	-	-	-	31.	82		
	Oxide of iron a		a	-	-	-	8.	52		
	Tribasic phospl			-	-	-	1.	49		
	Carbonate of li		-	-	-	-	17.	75		
	Sulphate of lim		-	-	-	-	1.	27		
	Alkaline salts		esia	-	-	-	3.	68		
		ing potasl		-	-	0.64				
		oride of so		-	-	0.08				
	Insoluble silice			-	-	-	20.	47		
							100	00		
							100			
	*Containing	ng nitrogen		-	-	0.89		1000000		
		ammonia	-	-	-	1.08				
A	ton of Bolton slu	dge dried	to th	at extent	t cont	ains:		£	s.	d.
	s. of phosphate o	100				-	-	0	2	9
	s. of potash	,		2d. ,,		-	-	0	2	4
	gen equal to 24				per lb).	-	0	16	0

Total estimated money value of 1 ton of dried Bolton sludge £1 1 1

For selling value, see page lxiii.

The cost to dry the sludge is not given; but experience indicates that the money expended would be wasted, as dried sand and earthy material has no greater value than when wet. There is less weight to cart and that is all.

BRADFORD.									
Area -	-	-	-	-	- (a	cres)	7,221		
Population, about	-	-	-	-	-	-	173,723		
Rateable value	-	-	-	-	-	-	£745,671		
Sewerage works co	ost .		-	-	-	-	£70,000		
Sewage defæcation	wo	rks cost	-		-		£60,000		
Waterclosets about		-	-	-	-	-	4,050		
Daily dry weather	vol	ume of sew	age	-	(gal	lons)	8,000,000		
The cost of defæca				-	-	-	£8,000		
Privies -	-	-	-	-	-	-	11,500		
Ashpits -	-	-	-	-	-	-	16,500		
Yearly cost of clea	nsir	g privies a	and ash	pits	-	-	£8,000		
Quantity of refuse				-	- (tons)	56,200		
First cost of railwa				ying refu	ise	-	£4,800		

The borough of Bradford has been sewered at a cost of 70,000*l*., and the 4,050 waterclosets and 11,500 privies and cesspits used by its 173,723 inhabitants are drained into the system which comprises about 48 miles of main and tributary sewers. The main sewerage works were commenced in 1862 and finished in 1875. In 1868 the entire volume of sewage

(about 8,000,000 gallons per day) flowed direct into the Bradford Beck, then a black and offensive stream. The Rivers Pollution Commission . designated it "the most filthy stream they had met with, surpassing the " worst examples in Lancashire." Although the sewage was not worse in appearance than the water of the "Beck," into which it flowed, Mr. William Crompton Stansfield of Esholt Hall, near Apperley Bridge, considered himself aggrieved by the additional pollution which the sewage caused to the stream, and on the 28th of August 1868, he filed a Bill of Complaint in the Court of Chancery to restrain the corporation from causing or permitting to pass any sewage, filth, or other offensive matter, solid or liquid, into the Bradford Beck in such a manner that the same might pass therefrom into the river Aire to his injury, and prayed that damages might be awarded for all injuries suffered. On the 1st September 1868, the corporation was served with an interim injunction obtained ex parte from the Master of the Rolls, prohibiting them under a penalty of 10,000%, from opening or permitting to be opened any additional main or branch-sewer, or any house-drain or sewer into the outfall-sewer or into the Bradford Beck, or any sewer communicating therewith or emptying itself therein. An answer to the bill was filed, but negociations between the corporation and the Plaintiff ended in an arrangement whereby the injunction was dissolved upon terms, one of which was that the corporation should, on or before the 11th of January, take steps to defecate the sewage passing through the public sewers. The corporation being convinced that any works merely dealing with the sewage of the town would fail to produce any appreciable improvement in the condition of the river Aire, they, in conjunction with other corporations and local boards in the watersheds of the Aire and Calder, introduced a Bill into Parliament during the Session of 1871 called the "Aire and Calder Conservancy Bill," which proposed to deal in a comprehensive manner with the sewage of the two Violent opposition to this Bill was threatened, and it was watersheds. consequently withdrawn. The same year the "Peat Engineering and Sewage Filtration Company," made an offer to the corporation to apply their system to the sewage of Bradford. Arrangements were made by which the corporation agreed to lease the sewage to this company for a term of 21 years, and to provide lands and buildings in which the operations were to be carried on; and the Company, on their part, agreed to purify the sewage, estimated at a daily volume of 8,000,000 gallons at their own expense, the residuum to become the property of the company. The company were also to have free use, for the first three years, of the buildings and plant to be constructed by the corporation; but after that period they were to pay the corporation a rent for the use thereof. These works were subsequently erected at a cost of 60,000l., including land and incidental expenses. The company however failed to carry out the contract, and legal proceedings were commenced by the corporation against the company and their sureties to enforce the contract; but the company collapsed, and the corporation in 1874 took possession of the works.

The defection works are situate in a valley between Frizinghall and Massingham, and were specially constructed for carrying out the process of filtration by peat charcoal. This process failed, because the sediment, choked the filters; and as the filtering medium required to be constantly replaced, the cost was ruinous, and the process had consequently to be abandoned. The corporation then made such alterations to the works as to carry on a combined process of precipitation and filtration; and this method has for some time past been in operation for defecting the sewage, which gravitates to the works, and flows into four subsidence tanks, from these tanks it passes along an

open conduit, across which iron screens are fixed to hold back any flocculent matters. Below the floor of the building, which is 700 feet long and 32 feet wide, there are 22 tanks, each tank 30 ft. × 32 ft. × 9ft. deep, and these, with the exception of the two middle ones, are used as precipitation tanks for the sludge. At the deepest point of these tanks connexions are made to a 9-inch cast-iron sewer pipe, through which the sediment is passed to "sludge-pits," one at each end of the building. The two middle tanks receive sewage from an "open conduit," and the coarser particles subside. After flowing through these tanks, lime, in the state of "milk of lime," is mixed with the sewage, which then flows along another open conduit into other precipitation tanks, of which there are 34. These tanks are each 22 feet wide by 24 feet long, and of an average depth of 5 feet, and are capable of holding about 18,000 gallons each, or together 612,000 gallons. The bottom of the tanks slope towards the filters, and after the sewage has been allowed to subside from 20 to 30 minutes, the supernatant liquid passes through a self-acting float-valve on to 34 filters; these are each 22 feet long by 12 feet wide by 2 feet deep, and are filled with coke. From these filters the clarified water passes into another open conduit, called the "effluent canal;" this runs along the entire length of the filter tanks, and is also partly filled with coke, and from this canal the treated sewage flows into the Bradford Beck. The sewage is allowed a period of from 20 to 30 minutes for subsidence in each tank, and as it only takes 15 minutes to fill a tank and 15 minutes for the clear liquid to run off, each tank, as constructed, is capable of defecating 18,000 gallons per hour, and the 34 tanks 612,000 gallons per hour. The "sludge" from the tanks flows through a sewer to the sludge-pits, situate at either end of the main building; from these pits it is pumped into the tanks under the building, where it has an opportunity of parting with a portion of its moisture, and is thence removed to open sheds; and although it is there exposed to the air, it only loses a small quantity of its water, and the corporation propose to adopt artificial means to dry the sludge, of which about 22 tons are daily produced from the sewage of the town. The works have a railway siding to the Midland Railway on the one side, and are bounded by the Leeds Canal on the other, so that great facilities are afforded for the removal of the manure.

The quantity of lime required for precipitation of the sewage is one ton to every million gallons of sewage, but on Sundays, when the sewage contains no dye water, half a ton to every million gallons is found to be sufficient. The mixing and other machinery is at present driven by three portable steam engines of 10-horse power each, one in the centre of the building and one at each end.

The estimate for defecating the sewage for the year 1876 is as follows:—

" Salary and Wages."

0.0000000000000000000000000000000000000									
	£	s.	d.	£	s.	d.	£	s.	d.
Manager (G. Alsing) -	-		-	300	0	0			
Foreman (James Lees) per week	2	2	8	109	4	0			
Night do. (John Duxbury) do.				78	0	0			
1 joiner do.		12		83	4	0			
6 engine tenters (each) do.	1	5	0	390	0	0			
18 labourers (day), with extra									
time, say 61 weeks do.	1	4	0	1,317	12	0			
10 do. night do. do.	1	4	0	732	0	0			
					_	_	3,010	0	0

	-	Brought	forwa	rd	-	£3,010 0 0
" Materials and I	Misc	ellaneor	is Exp	ense	's."	
			£	s.	d.	
3,000 tons of lime -	-	-	1,875	0	0	
2,000 tons of breeze for filters	-		125	0	0	
1,040 tons of coke for fuel	-	-	637	0	0	
5 tons of coals	-	-	5	0	0	
Gas	-	-	120	0	0	
150 gallons of engine oil	-	-	32	10	0	
224 lbs. cotton waste -	-		6	10	0	
220 lbs. candles	-	admir.	5	10	0	
Timber for keeping up plant, n	nach	inery,				
and buildings	-		50	0	0	
Repair of engines, machinery, &	c.	-	50	0	0	
Alterations and additions	-	- 11	100	0	0	and while time and
Office requisites	-		10	0	0	successful Man or
Rates, taxes, and sundries		and the	250	0	0	
amounted or sold led by a Statement con-			-		_	3,266 10 0

The corporation has not as yet been enabled to sell any of the sludge which consequently accumulates at the works.

£6,276 10 0

In addition to the cost of defæcating the sewage, the annual cost of cleansing the 11,500 privies and 16,500 ashpits is 8,000l., and the whole of the refuse removed therefrom becomes the property of the contractor

and is disposed of by him.

Abs	tract.			
Annual cost of treating sewage	hade no		- £6,276 10 ()
Annual cost of cleansing privies	mitte (L	in the same	- 8,000 0 0)
Total	4 -122	- Jersofe	- £14,276 10 0)

We collected samples of the solids extracted from the sewage before, and also of the sewage-sludge after treatment, and the following are the results of Dr. Voelcker's analyses.

Sludge from drying pits, no artificial heat being used.

On analysis the sludge as received, and calculated with 15 per cent. of moisture, furnished the following results :-

outress hits and all the same as well on		1					and the sale	Calculated with
								15 per cent.
								of moisture.
Water		-		-		-	82.41	15.00
*Organic matter -		-		-		-	7.54	36.44
Oxide of iron and alumina		-		-		-	0.78	3.77
Tribasic phosphate of lime		2010		41.		-	0.69	3.34
Carbonate of lime -		-		-		-	5.66	27.36
Sulphate of lime		-		-	1 100	-	0.49	2.36
Alkaline salts and magnesia		-		2001		-	0.73	3.52
Containing—Potash		81		.5.5	0.1	6		0.77
and chloride of sodium		-1		.=b	0.1	1		0.52
Insoluble siliceous matter	0	-					1.70	8.21
							100.00	100.00
* Containing nitrogen			-		-	-	0.14	0.67
Equal to ammonia	-		-		-	-	0.17	0.81

In a ton of the wet sludge there are $17\frac{1}{2}$ lbs. of phosphate £ s. d. of lime, worth at 1d. per lb 0 1 $5\frac{1}{2}$ 3 $\frac{1}{2}$ lbs. of potash worth at 2d. per lb 0 0 7 Nitrogen equal to 4 lbs. of ammonia at 8d 0 2 8
Total estimated money value of 1 ton of wet sludge $20 ext{4} ext{8} ext{1}{2}$
The dried sludge contains in 1 ton 75 lbs. of phosphate of lime, worth at 1d. per lb 0 6 3 $17\frac{1}{4}$ lbs. of potash, worth at 2d. per lb 0 1 $10\frac{1}{2}$ Nitrogen equal to 18 lbs. of ammonia at 8d. per lb 0 12 0
Total estimated money value of 1 ton of dried sludge For the selling value, see page lxiii. £1 0 1½
Solids drained from Sewage before the Liming Process at Bradford.
A sample received in a partially dried condition had the following composition:—
Water 51·41 15·00 * Organic matter 23·94 41·88 Oxide of iron and aluminia 2·63 4·61 Tribasic phosphate of lime 0·69 1·21 Carbonate of lime 4·07 7·11 Sulphate of lime 0·42 0·73 Alkaline salts and magnesia 1·28 2·24
Containing—Potash 0.47 0.82 and chloride of sodium 0.03 0.05 Insoluble siliceous matter 15.56 27.22
100.00 100.00
* Containing nitrogen 0.44 0.77 Equal to ammonia 0.53 0.93
According to the preceding analytical results the sample with 51.41 per cent. of moisture contains in 1 ton—
15 $\frac{1}{2}$ lbs. of phosphate of lime, worth at 1d. per lb 0 1 $3\frac{1}{2}$ lbs. of potash ,, 2d. per lb 0 1 9 Nitrogen, equal to 12 lbs. of ammonia at 8d. per lb 0 8 0
Making a total estimated value of 1 ton £0 11 01
The same material with 15 per cent. of moisture contains in a ton-
27 lbs. of phosphate of lime, worth at 1d. per lb 0 2 3 18 lbs. of potash ,, 2d. per lb 0 3 0 Nitrogen equal to 21 lbs. of ammonia at 8d. per lb 0 14 0
Total estimated value of 1 ton £0 19 3
For the probable value, see page lxiii.

COVENTRY.

Area (acres)		-	11 7- 16	19 - 6 -	01/F = 1/	1,600
Population (about)	-		100 THE 18	Bigging .	To beg	40,000
Rateable value		AB In-el	distinct to	H4 - 1 - 0	Design	£101,438
Inhabited houses		-	and the state of	1125 101	-	10,400
Waterclosets	- Single in	F W Del	Figure of F	79-100i	line.co	5,000
Cost of the main se	werage we	orks -	on handline	4- 0	-	£33,000
Volume of sewage e	very 24 h	ours, abo	ut (gallons	5) -	-	2,000,000
Privies -	sode 1 -	ed) #15-		-	-	800
Cost of cleansing p	rivies (yea	arly) -	-	-	-	£1,050

Cost of farm for sewage irrigation, 27,000l. The farm has been let in consequence of the offer from the "General Manure and Sewage Company, Limited," freeing the corporation (for the time) from the

responsibility of purifying the sewage.

The city of Coventry has been sewered; the works were commenced in 1853 and finished in 1855, at a cost of 33,000l. The whole of the sewage flows to one outfall at Whitley into the river Sherbourne, which is a small and rather sluggish stream. There are in the city 10,400 houses, and the excrements of the 40,000 persons who inhabit them are conveyed into the sewers by about 5,000 waterclosets, and consequently into the river into which the sewers discharge themselves, as there are only 800 privies. The sewers are ventilated by open grids in the covers of the 500 manholes, which are formed on the lines of sewers; they are also ventilated by being connected to fourteen factory chimney shafts, and further by the rain-water stacks from the eaves of houses. The whole of the rain-fall on the roofs and surface of the streets flows into the sewers, and from thence in heavy storms into the river by an overflow outlet specially provided for that purpose situate near Shut Mill Lane. Several springs were tapped while the sewerage works were being constructed, and a volume of about 500,000 gallons from this source enters the sewers daily. The waterworks belong to a private company, and 720,000 gallons of potable water are daily delivered for the use of consumers. There are also 21 public wells and a great many private wells from which a considerable number of the inhabitants obtain water for domestic purposes.

In 1860, complaints having been made by riparian owners of the pollution caused to the river Sherburne, the corporation directed subsidence tanks to be constructed near the river, and the outfall to be diverted so that the sewage might be discharged into the tanks, and afterwards filtered through a medium of gravel 3 feet in thickness before it entered the river. The tanks and so-called filters were a failure as regards purifying the sewage; they only partially extracted the suspended matters, and left the putrescible organic matters in solution, and although this somewhat mitigated the nuisance, it did not produce any substantial diminution of the polluting quality of the liquid.

Further complaints having been made of the condition of the river, the corporation, as advised in 1869, purchased 262 acres of land at Whitley at a cost of 27,000l., and instructed Mr. T. Hawkesley, M. Inst., C.E., to prepare a scheme for laying it out as an irrigation farm; and he subsequently submitted plans and an estimate of the proposed works. The sewage would, owing to the configuration of the land, have to be pumped on to the farm, and this circumstance, in addition to the great cost of the proposed works, caused the corporation to postpone carrying out the scheme. In August 1870, the A. B. C. or "Native "Guano Company," made an offer to the corporation to treat the sewage of the city by their process, but the terms proposed by the corporation

were not accepted by the company. On the 25th September 1871, Mr. H. M. Jackson, a riparian owner, filed a bill of complaint in Chancery and applied for an interlocutory injunction to restrain the corporation from passing sewage into the river, but the court declined to grant the injunction and the suit was abandoned.

In 1872, the "Peat Engineering and Sewage Filtration Company," made an offer to the corporation to deal with the sewage by their

process, but this offer the corporation did not entertain.

On the 25th of October in the same year, the corporation entered into a contract with the "General Sewage and Manure Company, Limited," whereby a messuage and 28 acres of land at the outfall works were leased by the corporation to the company for 14 years at a rent of 75l. per annum, together with the sewage of the city. The company covenanted to erect the necessary buildings; to furnish the requisite machinery and plant; to effectually deodorize and purify the whole of the sewage of the city, and to pass the clarified water therefrom into the river Sherburne, and they further covenanted that if default is made, after six weeks' notice, in carrying out the conditions of the lease, the corporation shall have power of re-entry and to put an end to the lease; whereupon all buildings and works shall become the property of the corporation without payment or compensation to the company; and the corporation are also to have the option of buying the steam engines, machinery, and other effects on the works at a valuation.

The company were to commence to treat the sewage on the 29th of September 1873, but it was not until May 1874 that the works were

sufficiently completed to enable them to do so.

The "General Sewage and Manure Company Limited" was formed in 1872, with a primary object of working on a practical scale the process for the purification of town sewage patented by Dr. Anderson, but the company have also acquired other patents for improving this process. The works erected by the company at Coventry, at a cost, including machinery and plant, of 12,000l., are situated on the right bank of the River Sherburne about two miles from the city. The sewage, estimated at 2,000,000 gallons every 24 hours, is weak owing to the large volume of subsoil water which mingles with it on its passage through the sewers. On the sewage reaching the works it passes through "extractors" which remove the coarser parts of the suspended matters, and it then flows into circular mixing tanks, constructed beneath the floor of the first block of buildings, to these tanks are affixed "agitators" driven by steam power for thoroughly mixing the compound which is here added to the sewage in such quantities as from time to time is required. This mixture consists of a saturated solution of crude sulphate of alumina, which has been heated to the boiling point, and this is prepared at the works from ordinary clay, or from shale of the coal measures, treated with concentrated sulphuric acid (an aluminous shale is at present used). From the mixing pits the sewage flows into another series of tanks under the floor of the second block of buildings, and in these tanks "lime" in the condition of so-called "milk" is added to the sewage which is here also continuously agitated by machinery."

From the "liming-tanks" the defæcated sewage flows into uncovered subsidence-tanks; these are four in number, and each tank is cleaned out every fourth day. The supernatant liquid flows from these tanks in a tolerably clear condition into a conduit which discharges it on to an area of about 4½ acres of loamy soil adjoining the works. This land has been roughly laid out as a land-filter and drained about five feet deep with an outlet at the extreme end of the land into the river Sher-

borne. On the date of our visit to the works the effluent water flowing from this outlet was clear and inodorous. The sludge precipitated into the tanks amounts to about 30 tons daily, and this, after being passed through a further straining process, is placed in heaps at the works to lose a still further portion of its moisture. We observed a large accumulation of this deposit. In order to convert the semi-dried sludge into a manure it is further dried by artificial heat by the use of Messrs. Milward's sewage mud-drying machines.

The company treat by their process the sewage flowing to the works between the hours of 5.30 a.m. and 11 p.m., but the sewage of the night (i.e., from 11 p.m. to 5.30 a.m.) flows through the tanks, and on to the filtering area without chemical treatment. The company say that the sewage during that period is chiefly subsoil water, and it only needs to be passed through the tanks mixed with the chemically treated sewage which they contain, and then flow on to the filter beds."

By the courtesy of Messrs. J. C. Melliss and E. F. Coddington, the engineer and the manager of the works, we are enabled to give the working expenses of the company.

WORKING EXPENSES, WEEKLY.

			£	8.	d.
22 tons of coal, at 10s. 6d. per ton -	4/10	-	11	11	0
27 cwt. of sulphuric acid, at 76s. 6d. per ton	200	-	5	3	3
9 tons of sulphate of alumina, 27s. 6d. per ton	2011	211	12	7	6
4½ tons of lime, at 16s. 2d. per ton -	210	647	3	12	9
Labour (12 men)	2009	-11	16	0	0.
Contingencies	200	34	1	5	6
to enable them to do on.			-	10.00	_
			50	0	0
			-		-

This amounts yearly to a sum of 2,600*l*.; to this must be added the salary of the manager, 250*l*., and also a sum for repairs and depreciation of works and plant, also the interest on capital expended, say 600*l*., per annum.

Abstract.

Annual cost of treating the sewage	Property.	E AMMAS	619011	£2,600	0	0
Manager's salary	-	444	-	250	0	0
Interest on capital expended -	and the second	o street	20320	600	0	0
Total	resources	infent :	-	£3,450	0	0

There is difficulty in getting rid of the sludge, as also of selling the manure when manufactured, but in January of this year (1876) owing to the exertions of the bailiff of the company's farm, the farmers in the neighbourhood have purchased and given orders for 350 tons; of the sludge to be taken direct from subsidence-tanks at 3s. per ton, this sludge, costing 4s. 10d. a ton to produce, when not at once removed, is placed in heaps about the works exposed to the atmosphere, to get rid of some of its water, afterwards if dried by artificial heat it costs in addition 1l. 8s. 9d. per ton, but if there was a demand for the manure, necessitating its being passed through a filter, and also artificial heat being applied to dry it, the cost would be 2l. 10s. per ton.

The manure thus produced in a dry state is then ground to powder,

for sale to farmers.

We collected a sample of the sludge from a heap on the works, and have caused it to be analyzed by Dr. A. Voelcker, F.R.S., and the following are the results.

Analysis of Manure prepared by the General Sewage Manure Company at Coventry.

A sample of the Coventry	sewage	manure	was	found	of the	following
composition:-						7
Moisture		-	_	-	-	47.36
*Organic matter -	-	-	-	-	-	15.95
Oxide of iron and alumina	-	-	-	-	-	5.17
Tribasic phosphate of lime	-	-	-	-	-	1.81
Carbonate of lime -		-	-	-	-	7.32
Sulphate of lime -	-	-	-	-	-	1.19
Alkaline salts and magnesia	ı	-	-	-	-	2.38
Containing potash	-	-	-	-	0.50	
and chloride of sodium	-	-	-	-	0.05	
Insoluable siliceous matter	-	-	-	-	-	18.85
						100.00
						100 00
40						
*Containing—Nitrog	gen -	-	-	-	-	- 0.69
Equal to ammonia		-	- 1		6.4	- 0.69 - 0.84
Equal to ammonia According to the prece	ding ana	: lytical r	esult	s 1 ton		- 0.69 - 0.84 Coventry
According to the precesewage manure contains:	ding ana					- 0.69 - 0.84 Coventry
According to the precesewage manure contains:—40½lbs. of phosphate of	ding ana	orth at	1 <i>d</i> . p			- 0.69 - 0.84 Coventry s. d. 3 4½
According to the precesewage manure contains:— 40½lbs. of phosphate of 4½lbs. of potash	ding ana	orth at	1d. p	er lb.	8	- 0.69 - 0.84 • Coventry s. d. 3 4½ 9 9
According to the precesewage manure contains:—40½lbs. of phosphate of	ding ana	orth at	1 <i>d</i> . p	er lb.		- 0.69 - 0.84 • Coventry s. d. 3 4½ 9 9
According to the precesewage manure contains:— 40½lbs. of phosphate of 4½lbs. of potash Nitrogen equal to 19lbs. of	ding ana lime, w	orth at	1d. p	er lb.	15 -	- 0.69 - 0.84 Coventry s. d. 3 4½ 0 9 2 8
According to the precesewage manure contains:— 40½lbs. of phosphate of 4½lbs. of potash	ding ana lime, w ammonis	vorth at	1 <i>d</i> . p 2 <i>d</i> . 8 <i>d</i> .	er lb.	8	- 0.69 - 0.84 Coventry s. d. 3 4½ 0 9 2 8

These works have, from the first, been carried on at a loss of not less than 1,500*l*. per annum for each million gallons of sewage per day treated; and, apparently, this rate of loss must continue, so long as this mode of treatment is continued.

The Corporation cleanse about 800 privies annually, removing 6,600 loads of refuse, at a cost of 1,050*l*.

			L	EEDS				
Area	-	-	-	-	-	(acre	es)	22,000
Population	(about)		-	-	-	- `	-	285,000
Rateable va	alue	-	-	-	-	-	-	£945,141
Waterclose	ts (abou	it)	-	-	-	-	-	8,000
Main sewer				-	-	-	-	£240,000
Estimated						(Gallon	is)	12,000,000
Estimated	quantity	of "sl	udge "	produc	ed daily	(ton	is)	40
Or about Experimen the Borwick's	tal and outfall I	permane Knostro	ent wor p, cost	ks for	-	process	at -	£47,000 £4,000
Tot	al cost	-	-	-	-	-	-	£51,000
Annual cos	st of tres	ating se	wage b	y A. B	. C. proce	ess	-	£15,000
Number of				-	-	-	-	15,598
Annual cos						-	-	£27,000
Amount re	ceived f	or abou	t 80,00	O loads	s of refuse	e remove	d	£9,000
(13)	1 0	T 1 1						

The borough of Leeds has been sewered, and the main outfalls were, until 1852, direct into the river Aire. The sewage was then inter-

cepted and conveved to one outfall at "Knostrop." Waterclosets are connected with the sewers, and the privy cess-pits and ash-middens are also drained into them; the sewage is however weak as compared with the sewage of London. The Rivers Pollution Commissioners collected samples of the Leeds sewage, flowing from the works at Knostrop, and submitted them to analyses, and in speaking of the result said. "The Leeds sewage contained a large portion of suspended matters; but it was very deficient in soluble fertilizing ingredients, containing only about one third of the proportion present, in average London sewage. This latter circumstance is due partly to the discharge of much slightly polluting water from factories into the sewers, and partly to the circumstance that 'springs were tapped during the execution of the sewerage works.' It is, however, probable that the sewage was exceptionally weak, at the time our sample was collected (1.30 p.m.) since Glasgow, with a daily water supply of more than 50 gallons her head, furnishes sewage twice as rich in fertilizing ingredients as that of Leeds." The nuisance caused to the river by the sewage is aggravated by the entire volume being discharged through one outfall, at Knostrop, and Sir Charles Hugh Lowther, Bart., and Mr. J. T. Leather, riparian owners, whose lands are situated a short distance below the outfall works, filed on the 5th November 1869, a Bill of Complaint in Chancery, and obtained a perpetual injunction to restrain the corporation from polluting the river Aire by the sewage, at Knostrop; the Court on application of the defendants granted two years from the date of the decree, in which period the corporation were to devise and carry out a scheme for abating the nuisance; but the time not proving sufficient to enable them thoroughly to investigate the various remedial processes proposed for consideration, they made further applications to the Court, and on three occasions the time was extended, the last extension was to 1st March 1874. In 1870 the A. B. C. or "Native Guano Company" made an offer to the corporation to treat by their process (for a limited period) the sewage discharged from the works at Knostrop, and also to pay the costs of the materials and labour required to carry on the process, provided that the corporation would bear the cost of erecting experimental works and supplying the necessary machinery for the purpose; this the corporation agreed to do, and the works, fitted with the necessary plant, were erected at a cost of 10,000%. The company carried on the process for some time; but the corporation had no control over the quantity of the chemicals used. On 17th August 1870 an agreement was entered into between the corporation and the A. B. C. Company, by which the corporation undertook to erect permanent works according to plans furnished by the company, for treating the entire volume of sewage (estimated at 12,000,000 gallons daily), and the company, on their part, undertook to be at the expense of successfully purifying and deodorising that volume of sewage, and to manufacture the "sludge" into a manure, and out of any profits from the sale of such manure to pay to the corporation 15 per cent. of the profits. The works were commenced in 1872 and finished in 1875, at a cost of 47,0001. Before the completion of the permanent works the company applied to the corporation to release them from the penalties of the contract, and they alleged as a reason for this request that they could not sell the manure which they had already manufactured at the experimental works, and offered, as a consideration for being released, to allow the corporation, without paying royalty, to use all the patents obtained by the company for "treating sewage water and matters." Eventually, the corporation consented to cancel the agreement, and on this being done the A. B. C. Company vacated the works. Some time after Major-General Scott, C.B., and afterwards Mr. Rupert Goodall, and finally Mr. Sylvester Fulda were permitted to carry on experiments with their several processes at the sewage works; the result was that Goodall's process (i.e., treating the sewage with lime, ground coal ashes, nitrate of iron, and carbon, a waste product from the manufacture of prussiate of potash) promised the best effect. The cost of this process for treating the entire volume of the night and day sewage flowing from the works at Knostrop was estimated at 19s. per hour, and arrangements were subsequently (in August 1874) made by the corporation with Mr. Goodall to carry on the work for a period of six months; but at the end of that time it was found that the sewage could be clarified on a larger scale at a cheaper rate than it had been done at the smaller works, and it was considered advisable to try the process of the A. B. C. Company at the large works, which were originally built for the A. B. C. process, and from January 1875 to January 15th, 1876, the A. B. C. method was carried out at a cost during this year (for lime, carbon, alum, clay, and carbolic-sulphide, inclusive of labour, fuel, oil, tallow, &c.) of 15,0001. This amount is exclusive of the cost of drying the deposit and converting it into a manure, which has not as yet been done.

The corporation have recently (January 1876) arranged with Mr. John Hanson, a manufacturing chemist of Savill Town, near Dewsbury, to treat the sewage by a process for which he has obtained a patent, and he proposes to use, in treating 12,000,000 gallons daily,—

\pounds s. d.
4 7 0
2 16 0
no information
2 9 0
£9 12 0
no information

Or at a rate of 16s. per million gallons per day for chemicals alone. To this must be added the cost of labour, coal, and other materials, also the expense of cleaning out the sludge-tanks, and of artificially drying the "sludge" and converting it into a manure. It is estimated that the quantity of suspended and precipitable matters in the Leeds sewage amounts to 40 tons daily, or about 15,000 tons per annum, and not any of this has been sold, which consequently accumulates at the works.

For the purpose of artificially drying the mud and manufacturing a manure therefrom the corporation are erecting two of Borthwick's drying cylinders; these will cost about 4,000*l*.

The Rivers Pollution Commission carefully investigated the A. B. C. process, and in their second Report, 1870, submitted the conclusions regarding it to which their inquiries, observations, and analyses had led them. They say, "As therefore the inevitable conclusion is unfavourable to the A. B. C. process, in respect of its alleged power to hinder the pollution of rivers by town sewage, so also is it altogether unfavourable to the value of the manure which it manufactures. The one statement is, indeed, in some sense the complement of the other, for just in proportion to the largeness of the amount of fertilising matter which escapes must be the comparative worthlessness of the small remainder which is retained."

We collected a sample of the sludge from the A. B. C. process and caused it to be analysed by Dr. A. Voelcker, F.R.S., and the following are the results of the analysis:—

DEPOSIT from the SEWAGE of LEEDS treated by the A. B. C. process.

This deposit in the state in which it was received, and calculated for 15 per cent, of moisture, had the following composition:—

15 per cent. of moisture, had the fo	llowing composition :-	
	and and a tentant	Calculated with
		15 per cent.
Moisture	DITTO MODITOR OFFICE SELECTION	of moisture.
	- 57.20	15.00
*Organic matter	- 9.45	18.77
Oxide of iron and alumina -	- 8.10	16.09
Tribasic phosphate of lime -	0.76	1:51
Carbonate of lime	- 5.60	11.12
Sulphate of lime	- 0.45	0.89
Alkaline salts and magnesia -	- 1.40	2.78
Containing—Potash	- 0.39	0.77
and chloride of sodium -	- 0.02	0.04
Insoluble siliceous matter -	- 17:04	33.84
	ed comporting it into a	tion the sea
	100.00	100.00
* Containing nitrogen	- vila-10:31	0.61
Equal to ammonia -	- 0:37	0.74
which he has obtained a patous, and		£ s. d.
The partially dried deposit contain	ning 57:20 per cent of	
moisture contains in 1 ton 17 l	he of phoenhate of lime	esendont an
	os. or phosphate of time,	
worth at 1d. per lb	of their and the Vol. net to	0 1 5
83 lbs. of potash, worth at 2d. per I		$0 1 5\frac{1}{2}$
Nitrogen equal to $8\frac{1}{4}$ lbs. of ammon	a at 8d. per 1b.	0 5 6
0.00	· multiple of the fact	-
Total estimated money value per tor	1	£0 8 $4\frac{1}{2}$
		-
In a ton of the deposit, with 15	per cent, of moisture, we	
have—	,	£ s. d.
34 lbs. of phosphate of lime, worth :	at 1d per lb	0 2 10
$17\frac{1}{4}$ lbs. of potash, worth at $2d$. per		0 2 10
		44
Nitrogen equal to $16\frac{1}{2}$ lbs. of ammor	na at ou. per 10.	0 11 0
Total estimated money value of 1 to	n	£0 16 81
For the true value,		

The cost of treating the sewage in this case is not less than 1,500*l*. per annum for each million gallons per day, and there is no probability of reduction if the present mode is continued. The Committee of Works persist in expecting 1*l*. per ton for the manipulated sludge, which they do not obtain; recently (July 1876) they assert that it is selling at 10*s*. per ton.

In addition to the expense of clarifying the sewage by chemical treatment, there is the cost to the corporation of cleansing the 15,598 privies and middens, removing the refuse (about 80,000 loads) at a cost of 27,000l. The expense of cleansing and removing is partly recouped by sale of the refuse, which realizes 9,000l, or at a rate of 2s. $2\frac{1}{2}d$. a load, leaving a deficit of 18,000l. The refuse is bought by farmers to be used for manure.

The sewers are ventilated, and, in 1873, 15,000 gullies were converted into ventilators. In the construction of all new sewers ventilating-shafts are built, the gullies are also ventilated, and arrangements are also made for flushing the sewers.

HALIFAX.

Area -	-	-	-	-	-	(ac	eres) 3,768
Population, about	-	-	-	-	-	-	68,000
Rateable value	-	-	-	-	-	-	£262,581
Inhabited houses	-	-	-	-	-	-	11,218
Waterclosets	-	-	-	-	-	-	2,600
Sewerage works co		-	-	-	-	-	£77,000
Outfall works and t	anks cos	t	-	-	-	-	£15,954
Estimated volume of					is)	-	2,500,000
Yearly cost of clean			emoving	refuse	-	-	£213
Privies on the Gour			-	-	-	-	3,159
Yearly cost to corp	oration o	of cleans	sing thes	e recept	acles	-	£1,896
Privies with midder				-	-	-	1,500
Yearly cost to corpo	oration o	of cleans	ing thes	e "mide	lens"	-	£1,100

The borough of Halifax has been sewered; the main sewers are built of stone and brickwork, and the branch sewers are formed of stoneware pipes, the main outfall being into the Hebble at Salter Hebble. The sewers are ventilated by means of side chambers built to each manhole; these are carried up to the surface of the streets and are covered by open grids. The Hebble, a small stream, in its passage through the town is considerably discoloured by refuse from mills and dye works; and, in 1869, it was greatly polluted by sewage. In the month of May of that year, Messrs. J. Holdsworth and Company, whose mill is on the stream about a quarter of a mile from the outfall sewer, filed a bill of complaint in the Court of Chancery, and in July of the same year an injunction was granted to restrain the corporation, from and after the 1st of June. 1870, from causing or permitting the sewage of the borough to flow into the Hebble Brook until the same had been sufficiently purified In February 1870, the late Mr. John Lawson. and deodorised. C. E. (Lawson and Mansergh) at the instance of the corporation, visited Halifax, and after an examination of the district submitted a report on the best mode of disposing of the sewage thereof; he recommended that "an irrigation scheme on a comprehensive scale should be carried " out, and he considered that the 475 acres of land proposed to be pur-" chased by the corporation would probably be sufficient for the "thorough utilization and purification of the sewage of Halifax": he also stated that "tanks or screeners would be required to take out the " suspended matters, and the sewerage could be delivered on to the " greater part of the land by gravitation." The recommendation of Mr. Lawson was not adopted by the corporation, who in the autumn of 1869 called in Mr. J. Bateman, C.E. to advise them, and he recommended that subsidence tanks should be constructed, and that an intercepting sewer of cast-iron pipes, from 18 inches to 30 inches in diameter, should be laid to convey the sewage of Halifax and discharge it into the tanks and thence into the stream at a point below the plaintiff's works; the intercepting sewer and tanks were completed before the 1st of June 1870, and this satisfied the Plaintiffs in the suit. The cost of these works was 15,954l. The volume of sewage flowing through the outlet is estimated at 2,500,000 gallons every 24 hours, and in this volume is included about 500,000 gallons of subsoil water. The sewage is not treated by any chemical agent, but flows into the subsidence tanks where the coarser matters and detritus are arrested, but the raw sewage, loaded with the foul matters in solution, passes from the tanks into the Hebble Brook.

In 1871 the Goux Manure and Sanitary Company, Limited, applied to the corporation to be allowed to introduce their dry system into the borough; and offered free of cost to cleanse all the privies which were or would be constructed on the plan they laid down, (i.e.) "The ashpits and excrement pits under the privy seats were to be thoroughly cleansed, and filled in with dry rubbish to the level of the floor, and the privy seat was to be made removable so that it could be lifted up to place in, or take away, the 'receiver' or 'tub'; these tubs were to be 30 inches in diameter and 16 inches deep, and in them a certain quantity of absorbent, either of vegetable or animal fibrous matter, was to be placed, a core was to be inserted around which was to be filled in a further quantity of absorbent matters, and the core was then to be removed. The tubs so prepared were to be placed under the privy seat to receive the excreta, and were to be removed and replaced every eight days; the tubs were, when full, to be taken to the depôt, and their contents emptied and mixed together."

The corporation accepted the offer of the company, and the company erected temporary works and plant on land belonging to the corporation at Stone Dam in the borough, but as this land was subsequently required for other purposes, the corporation in March 1873 let to the company land at Salter Hebble, close to the sewage outfall works, at which place the company erected sheds, stables, and offices, for carrying on the

process.

About this time the company represented to the corporation that they could not sell the manure manufactured by their process, and that they were losing by the work; and the corporation agreed to pay to the company 7s. per annum for every Goux closet cleansed, and if the contract remained in force after the 1st of January 1875, this amount was to be increased to 12s. per closet, subject to three months' notice on the part of the corporation, and 12 months' notice on the part of the company. The company gave notice to the corporation in January 1875 to terminate the contract in January 1876, and the corporation are now considering whether they will or not carry on the system.

The company under their contract with the corporation removed about 500 tubs daily from the closets to the works; these tubs were about two thirds full of excreta, and after being emptied of their contents ought to have been thoroughly washed before being prepared for re-use, and although the company professed to have this necessary work done, we saw on the day of our visit to the works, January 16th, 1876, the tubs being lined with the absorbent, and prepared to be used

again, without having first been properly cleansed.

The company used at Halifax the refuse shoddy as an absorbent lining for the tubs for which they paid 9s. per ton; the contents of the tubs were, when taken to the works, mixed and turned over in a pit, and afterwards thrown into a heap in the store shed. We saw at least 2,000 tons of this feeble manure stored in that shed, the Company not being able to sell it at the price they asked for it, viz., 15s. per ton.

For carrying out their system at Halifax the company expended in erecting sheds, buildings, and cottages, and also in making a road to the works, the sum of 2,000*l*., and a further sum of 500*l*. in providing the

necessary horses, waggons, carts, and barrows.

The receipts and expenditure of the company at Halifax for 1875 were as follows:—

	RECE	EIPTS.				Expenses.			
Received of the tion for cleans closets - Sale of manure Balance (loss)		,159	£ 1,895 700 911	s. 0 0 0	d. 0 0 0 0	1 manager 1 inspector 1 foreman 10 collectors 8 drivers 4 emptiers and packers 1 boy Keep of 7 horses - Hire of 8 ditto -	-£	s. 0	d. 0
						400 tons of shoddy -	180	0	0
	I.	ž	£3,506	0	0	Gypsum and charcoal -	£3,506	0	0

The Rivers Pollution Commissioners, in referring to this process said:—

"It must be remembered, as regards this, and similar expedients, not only that it is but a part of the excrementitious matters which is dealt with, but that even as regards that portion of the excrement which they do remove, they so entirely depend upon efficient cleanly superintendence and direction, that wherever they have merely had the average man to work them, they have failed. Moreover, this very frequent collection of filth by hand from houses, and its removal sometimes through the cottages themselves, almost necessarily under the eye and nose of the household, whatever may be the importance of the economic object aimed at, is universally condemned by our domestic habits as nasty and offensive."

The yearly cost to the corporation of cleansing the old middens, of which there are 1,500, is 1,100*l*.; the refuse becomes the property of the contractor.

We collected a sample of the manure manufactured by the Goux Company from the store-shed on the works at Halifax, and have caused it to be analysed by Dr. A. Voelcker, F.R.S., and the following are the results:—

MANURE manufactured by the Goux Company at Halifax.

A sample of this manure	on ar	nalysis gav	e the f	ollowir	ig result	:
Moisture	-	-	-	-	-	51.65
*Organic matter -	-	-	-	-	-	22.70
Oxide of iron and alumina	-	-	-	-	-	3.96
Tribasic phosphate of lime	-	-	-	-	-	0.96
Sulphate of lime -	-	-	-	-	-	0.81
Alkaline salts and magnesia	-	-	-	-	-	2.37
Containing—potash	-	-	-	-	0.30	
and cholride of sodium	-	-	-	-	0.38	
Insoluble siliceous matter	-	-	-	-	-	17.55
						100.00
*Containing-Nitrogen -			-	-	-	- 0.67
Equal to ammonia -			-	-	-	- 0.82

A ton of this manure contains—	s.	d.
211 lbs. of phosphate of lime, worth at 1d. per lb	1	91
$6\frac{3}{4}$ lb. of potash ,, $2d$. ,, -	1	11
Nitrogen equal to 18 lbs. of ammonia, at 8d. per lb	12	$5\frac{1}{2}$
	_	
	15	41/2
For the true value, see page lxiii.	_	

ROCHDALE.

Area		4,136
Population (about)		67,000
Rateable value		£222,000
Inhabited houses	1	14,288
Waterclosets		350
Cost of sewage, manure, works, and plant -	-	£10,000
Volume of sewage every 24 hours	(gallons)	1,250,000
Privies, "middens"	1 1	2,844
Privies, "pail system"	-	5,462
Yearly cost of cleansing privies on pail system	nealment en	£3,405
Excreta removed yearly	- (tons)	4,224
Manufactured into manure	- (tons)	3,741
Manure sold	- (tons)	2,000
Yearly cost of cleansing "middens" -		£1,919
	1	
Refuse removed	- (tons)	13,736
Refuse, 5,736 tons, sold for	- 100	£549
ATTEMPT OF THE PROPERTY OF THE		

Rochdale has adopted the "pail" system for the disposal of the excrements of its 67,000 inhabitants living in 14,388 houses distributed over an area of 4,136 acres, as there were in use on the 28th of January 1876, 5,462 privies on the "pail" system, 2,844 "middens," and only 350 waterclosets, and we were informed that the "middens" are being converted into privies on the "pail" system, at the rate of 20 per week.

The borough has been sewered and these works have been greatly

increased since 1853.

In 1853 the corporation obtained an Improvement Act, and the 96th section of that Act provides that it shall not be lawful for the corporation to cause any new sewer to open or drain into the River Roch at any point above the Town Mill Weir, or the stream called the Lord Burn; but, as the town rapidly extended, new sewers were constructed, and this greatly augmented the volume of sewage flowing into the Roch and seriously polluted it. On the 6th of October 1869 a Bill of Complaint was filed in the Court of Chancery, by Mrs. Sophia Holt (widow), and Messrs. Oliver Holt and William Holt, praying that the corporation be restrained from permitting the new sewers then being laid down in Yorkshire Street or any other new sewer from emptying into the Roch above the Town Mill Weir or into the Lord Burn. On the hearing of the cause, 3rd of January 1870, Vice-Chancellor James granted an injunction as prayed. In order to satisfy the Court, and also with a view of intercepting the sewage and preventing it from polluting the Roch, the corporation, in session 1872, introduced a Bill in Parliament and sought certain powers, one of which was to acquire 1,000 acres of land and on this area to utilize the sewage by irrigation. The land is situate in the township of Unsworth about 5 miles from Rochdale, and is the property of the Right Honourable the Earl of Derby. There was great opposition to the Bill and the clauses relating to the land for irrigation were struck out. The corporation then caused

plans to be prepared of an intercepting sewer to divert the sewage from the Roch, and this work is now being carried out a cost of 20,000l. The intercepting sewer commences at Ashbrook Valley on the eastern boundary of the borough, and from that point to Heybrook Valley, it is 4 feet in diameter and laid at a gradient of 1 in 250; from Heybrook Valley to George Street it is increased to 5 feet in diameter; from thence to Duke Street it is further increased to 6 feet in diameter; from thence to the Spodden Valley, it is 6 feet in diameter, but laid at a gradient of 1 in 1,000; and from the Spodden Valley to the outfall into the Roch, below Oaken Rod Weir, it is 9 feet in diameter; laid at a gradient of 1 in 1,000.

When these works are completed there will still be 12 overflow-outlets into the Roch, above the Town Mill Weir, to relieve the main sewers

of flood water during heavy storms of rain.

The sewers are ventilated by open grids in the covers of the lampholes and manholes; these are placed on the lines of sewers and are not more than 150 feet apart. Owing to the configuration of the town the sewers have steep gradients, and it was found that a considerable volume of sewer gas ascended to the highest points of the system; to remedy this, self-acting valves (as recommended in the published suggestions of the Local Government Board, pages 7, 8, 9,) are placed in each manhole, and this has had a beneficial effect; it has prevented the sewer-gas accumulating at the higher points and has facilitated its escape through the gratings in the surface of the streets.

The volume of sewage entering the Roch, Spodden, Hey-Brook, and Sudden Brook, by the numerous outlets, is about 1,250,000 gallons

every 24 hours.

In 1869, the corporation of Rochdale decided that they would not continue the contract for cleansing middens and removal of the contents; and, after some consideration as to the best form of privy and ash place, they adopted the "pail," or that now known as the "Rochdale system."

The corporation have erected buildings as a depôt on a site within the borough, and purchased the necessary plant, horses, and rolling-stock for collecting the excreta and refuse at short intervals. The cost of the works, plant, and stock, up to the 28th of January 1876, has been about

10,000%.

The mode of collection is as follows:—"The town is divided into six districts, and each pail-privy is numbered consecutively in a district register, so that in case of any contagious or infectious disease arising in the town, the numbers of the pail-privies in connexion with the houses in which the disease exists can be communicated to the local authority, when arrangements can be made for the daily disinfection of

such pail-privies, and for the isolation of such excreta."

"As a rule all pail-privies are empted once a week, to ensure which, the driver of the collecting van, on his return to the works, gives in a list showing the number of each pail-privy from which he has collected; this is posted in a book, in such a form that it can be seen at a glance whether any have been neglected, and on every Monday morning a list of those overlooked (if any) is made, and a supplemental van is then sent out to make good the week's collection; the entire onus of removal rests upon the corporation."

"The pail-privies are supplied at each collection with a fresh pail, which has been well washed, and in which has been placed a liquid

deodorizer and disinfectant."

"The collections, according, to the regulations, should be made between

the hours of 7 a.m. and 5.30 p.m."

To prevent any nuisance arising from the collecting van when passing through the streets on its return to the works, air-tight lids are placed upon each pail; the doors of the van also close against india-rubber beads fixed in the rebates, so as to be air-tight.

The ash and refuse-tubs are also emptied systematically, attention being secured to them by the weekly visits which are paid to the privies.

In emptying the tubs the ashes are not thrown on the ground, but are emptied directly into a cart, and before placing the tub again in position the floor of the ash-place is swept.

The process of manufacturing the manure is as follows:—the wethouse refuse is tipped from the carts on to drying floors, and when thoroughly dry is, with the other refuse, passed through a riddling machine worked by steam power, which holds back the paper, vegetable, and other refuse, and separates the cinders in two sizes from the ash; the ash is then removed to any part of the sheds where required, and the cinders are removed and used on the works for generating steam, heating the drying floors, and also for firing the boilers at the public baths; and some of the cinders remain for sale. All refuse, such as scrap-iron, obtained by this riddling is disposed of; the vegetable refuse is burnt, and the ash used in the manure.

The excreta, upon its arrival at the works, is emptied into a trench formed by banks of ash, previously brought into the shed from the riddling machine; when this trench is full a quantity of ash is thrown upon the excreta, and the contents are treated with sulphuric-acid, in the proportion of 24 lbs. of acid to each ton of excreta.

The proportion in weight of the excreta and ashes thus treated are about equal. Trench after trench are formed and filled until the whole floor of the shed is covered. When seven days have elapsed since the formation of the first trench and the ash there used has become sufficiently dry to be again used as an absorbent, new trenches are made in the banks of ash deposited to form the sides of the first trenches, and these are filled with excreta and the ash covered over them and again treated with sulphuric acid, as in the first instance. In this latter case, as ash is only required to cover the excreta, and not to form the banks of the trenches, only 5 cwts. of ash are used to 20 cwts. of excreta. When this second course has covered the area of the shed, the process is repeated in another shed, leaving the first shed at rest for fourteen days, after which it is again treated for a third and also for a fourth time with the like quantity of excreta and ash used in the second course. The total quantities thus treated having become 35 cwts. of ash to 80 cwts. of excreta, the mass is undisturbed for fourteen days, after which it is turned over and remains another seven days, when it is again turned over and for a second time allowed to remain undisturbed for seven days. By this time the mass has become a powdery manure, and is in a condition to be bagged for sale.

In 1875, the cost of collection of the pail-refuse and manufacture of the manure, together with the estimated value of the manure manufactured, was as follows:—

Cost of collection	1 - 1781	£ - 3,405	Value of manure manufactured
Cost of manufacture	-	- 3,651	estimated at 1 <i>l</i> . per ton - 4,420 Loss 2,636
		£7,056	£7,056

Note.—The Rochdale manure is not readily taken away from the yard at the estimated price of 1l. per ton, but gradually accumulates. This is the experience in all cases within our knowledge of this and similar modes of dealing with excreta.

We saw at the works about 7,000 tons of this manure. There is not a ready sale for it. Only 2,000 tons were sold in 1875; the corporation in consequence caused the manufacture to cease. Since April of that year, 1875, the excrements have merely been mixed with house-refuse and ashes, but there is great difficulty in getting rid of the mixture although the corporation undertake to deliver it to the purchaser at 2s. 6d. per ton, and this appears to be the true value to farmers.

The cost of cleaning the middens and removing the contents is 1,919*l*. per annum, and of the 13,736 tons of refuse removed 8,000 tons are deposited in "tips" within the borough, and for the remaining 5,736

tons the corporation receive the sum of 549l. 2s. 11d.

With reference to the 8,000 tons of "midden" refuse thrown away on "tips," we quote the remarks of the Rivers Pollution Commissioners on the "Collyhurst Tip" at Manchester (see Report Mersey and Ribble Basins, p. 24) "The contents of these ashpits are divided by the scavengers into so-called dry and wet; and it is a matter of serious importance that it is the latter or obviously filthy part alone which is carried to the manure depôt, the dry rubbish being carried to any place that may be in course of levelling in the outskirts of the town. Of course such a division is most imperfectly made under such circumstances; and it follows that the land is thus filled up with the most objectionable stuff; and as building extends, the surface is gradually covered with houses which, on such foundation, cannot fail to be unwholesome dwelling places. There is now a "tip" in a ravine at Collyhurst, on the north side of Manchester, where land is thus being raised fifteen to twenty feet over many acres, by the gradual accumulation of filthy rubbish. A sample of water from a pool at the foot of this tip on the outer side of the Queen's Road, which here crosses the ravine, taken a few minutes after rain, so that it represented the drainage water of this bank, and thus fairly indicated the nature of the stuff it had trickled through, and another sample taken at a later date yielded the following results on analysis.

"Composition of Drainage Water from Collyhurst "Tip."

"Results of Analysis expressed in Parts per 100,000.

Dates of collection of samples.	Total solid Matters in Solution.	Organic Car- bon.	Organic Ni- trogen.	Ammonia.	Nitrogen as Nitrates and Nitrites.	Total com- bined Nitro- gen.	Chlorine.	Matters in Suspension.	Organic Mat- ters in Sus- pension.
June 12, 186 July 21, 1869	1643·5 2310·4	32·278 22·591	3°C31 5°257	29·525 15·440	0	27·946 17·972	331·5 440·0	16.88 54.36	13°48 26°52

"It will be seen from the above numbers that these liquids contained a very large proportion of highly offensive organic matter. They were, in fact, much richer in putrescible matters than any watercloset sewage we have met with. The whole of the made land, indeed, here smells most offensively and can never be built upon without great risk to the health of those who shall occupy the houses. And this is no exceptional example connected with the midden system. What to do with the fouled ashes, which it accumulates—filthy stuff, too poor for use as manure—is one of the great difficulties of the local authorities almost everywhere in Lancashire."

Results of Analysis of Pail and Ash Manure.

We collected at the depôt a sample of the manure manufactured from the refuse of the "pails," and have caused it to be analysed by Dr. A. Voelcker, F.R.S., and the following are the results:—

This manure is prepared at the Sanitary Manure Works belonging to the corporation of Rochdale, from the contents of pails in which human excreta are collected; these are dried up with finely-sifted coal ashes, and delivered to farmers in a more or less dried condition.

A sample of the Rochdale manure as received contained the following ingredients:—

Moisture	anorthi bala de	achilianne	Affe to			1.	5.13
*Organic matter (including	carbonaceous	matter	from i	finel	y	0.3	
sifted cinders) -	Indiana rakan har	PRIMEIR	O OF A		-,	30	0.62
Oxide of iron and alumina .	Meeting minutes and	-	-		-	1'	7.27
Tribasic phosphate of lime	a vession end a	All The Later of	-		-		0.76
Sulphate of lime -		-	-		-		4.82
Alkaline salts and magnesia	The same of the same of	and the state of			-	-	2.29
Containing potash -	and the same	-	0.75				
and chloride of sodium	and the second little	de la constante de la constant	0.53	3			
Insoluble siliceous matter	and the same of the same	de la lace	-		-	2	9.11
						100	2.00
						100	0.00
*Containing nitrogen -	rep gang ten	organit w	inionel o	100		(b	0.69
Equal to ammonia -	to ald my	Na day us	sidder.	·ylli	III.	100	0.84
					e	s.	7
1 ton of the Rochdale manur	e contains 117	lbs. of	phosph	ate	~	0.	u.
of lime, worth at 1d. per l	A RESIDENCE OF THE PROPERTY OF	-	-	-	0	1	5
17 lbs. of potash, worth at 26		-	-	-	0	2	10
Nitrogen equal to 18 3 th lbs		t 8d. pe	r lb.	-	0	12	21
- 10		1			-		
For the true	value, see pa	ge lxiii.			60	16	51
							-

Mr. Alderman Taylor in a recent return (1876) set forth that a population of 52,000 in Rochdale is supplied with 5,644 pails, from which, in the year 1875 was collected 5,398 tons of excreta. This gives about 9.2 persons, and about 19.1 cwt. of excreta to each tub.

The excreta of one person on an average of an entire population is $2\frac{1}{2}$ lbs. per day, or $8\cdot 1$ cwts. per year, which, taking $9\cdot 2$ persons to each tub, gives $74\cdot 52$ cwts., or 3 tons 14 cwts. per pail; 5,644 pails, at 3 tons 14 cwt. per pail, gives 21,024 tons, as the weight due, if the pails are used by the population to which the statement apportions them, so that about one-fourth of the excreta of the 52,000 persons is alone accounted for. One form of reply may be, that for parts of the day the inhabitants are from home, at work, and use other privies, this, no doubt, is an explanation so far as it goes; the statement however gives no indication of such contingency, neither would such explanation be satisfactory if it had been made; as we see that not more than one-fourth of the excreta is accounted for.

APPENDIX No. IV.

THE LIERNUR PNEUMATIC SYSTEM OF TREATING EXCRETA.

In September 1875 we visited the cities of Leyden and Amsterdam.

LEYDEN.

At Leyden, accompanied by the town clerk (Mr. Kist) and one of the aldermen, we inspected the pumping station and in answer to our

inquiries received the following information.

The city of Leyden is built upon about 50 islands formed by the affluents of the Rhine. Here a population of about 39,869 is congregated in about 5,000 houses. Their potable water is derived chiefly from the canals which intersect the city and in some cases at points near the outlets of drains from the houses. These canals are, in fact, not only the main sewers of the city, but the main source of water supply; a large quantity of solid refuse is also discharged into them; this has to be constantly dredged out, and the operation conducted in hot summer weather

is very offensive.

The house property drained by the Pneumatic system stands upon an area of about four acres, and consists of a poor-house an orphan-asylum and 146 private houses adjacent thereto, situated at the south of the city in Saint Jakob's Gracht, Koerpoort Gracht, Keifhoet, Gaarmand, Hoef Straadt and Raamsteeg, near to a large canal, and this district is occupied by a population, including 140 inmates of poor-house and asylum, of 1,197, who have in use 156 Pneumatic privies. The entire cost of the works i.e., erecting pumping-station, providing 8-horse power steam engine, air pumps, 5,560 feet of 5-inch cast-iron pipes laid under streets from pumping station to the houses, cocks, valves, and funnels to privies, was 2,833l., or 18l. 3s. $2\frac{1}{4}d$. per privy, or 2l. 7s. 6d. per head of population. The costs were defrayed by the city council, and we were informed by the town clerk that the council did not propose to extend the system because of the great expense. The engine at the pumping station is only worked for three hours on four days in each week for the purpose of removing the excrements to the pumping station, and the yearly cost of this service, including labour of engine-driver and two turncocks, fuel, and materials was in 1872 333l., or 5s. $6\frac{3}{4}d$. per head; in 1873 182l., or $3s. 0\frac{1}{4}d$. per head, and in 1874 259l., or $4s. 3\frac{3}{4}d$. per head of the population using this service. In May 1875, Mr. M. D. von der Hoef of Oegstgeest near Leyden, entered into an agreement with the Municipal Council to send by his barge, when the canals were open, twenty-five 36-gallon old petroleum barrels twice every week to the pumping station to remove the feecal matter, and to pay for it at the rate of $2\frac{1}{2}d$. per 32 gallons; but, in winter, when the canals are frozen, the municipality are to pay the carriage to his farm, which will amount to 5d. per 36-gallon barrel.

We visited the dairy farm of 40 cows belonging to Mr. M. D. von der Hoef and saw the mode he adopted of distributing the fœcal matter over his farm, the greater part of which is in meadow, a fine rich loam on a sandy subsoil; six of the barrels unloaded from the barge were placed on a low wheel dray, and drawn by one horse about a quarter of a mile on to the meadow required to be irrigated; the contents of three of the barrels were emptied into a tank on four wheels, which was then drawn about by a horse from place to place as required, whilst a man with a scoop threw the excrements, which were very dilute, over the meadows. Three men are engaged two days a week in removing the fœcal matter from the city and applying it to the land, and this cost 16s. per week, in addition to the sum paid for it. In reply to our further inquiries Mr. van der Hoef said: "I don't know what I shall do with the excreta in

winter (two months) when it is frozen in the barrels. I suppose I must store it in the shed until the frost has gone; I have only had the manure since May 1875, and my experience of its utility is very limited."

AMSTERDAM.

Amsterdam.—In this city we inspected three of the principal blocks of buildings drained by the Liernur pneumatic pipes, and also saw the working of the system. The Director of Public Works (Mr. J. Kalff) and Mr. J. G. van Niftrik, Stads Ingenieur, accompanied us and gave

to us the following information.

Amsterdam lies at the influx of the river Amstel into the Y, as this arm of the Zuider Zee, which forms the harbour is called. Canals of various sizes intersect the city in several directions, and divide it into about 90 islands which are connected by means of nearly 300 bridges. It has a population of about 286,932 living in about 30,000 houses. The entire want of spring water at Amsterdam is a serious disadvantage to so large a city. The houses are provided with cisterns for rainwater, which is used by the inhabitants for culinary purposes. The potable water is obtained from a gathering ground situated in the Dunes 13½ miles from the city, impounded in a reservoir which has an area of seven acres, and a mean depth of 20 feet. The city was formerly supplied from a small river, the Vecht, abstracted at a point above Weesp, about nine miles from the city by means of "leggers," or water-barges, constructed for the purpose, and are still used in exceptionally dry seasons.

The whole of the sewage flows into the river and canals, which here, as at Leyden, are the main sewers of the city. The drains for carrying off the fæcal matter and house refuse are mere surface-carriers continued along the edge of the footpaths in the streets; covered over with deal flaps hung to the timber kerbing, and discharging into the river and

canals, some of these drains were in a very foul condition.

The Amstel is nine feet in depth, the canals generally three to four feet only, and the thick layer of mud which covers the beds is stirred up by the passing barges Dredging machines are engaged in removing this mud, and this is found to be a nuisance in hot weather. In order to prevent the entire stagnation of the large volume of sewage poured into the river and canals, a supply of clean water is introduced through a sluice into the canals from the Zuider Zee.

The Pneumatic System as described by the Director of Public Works.

The Pneumatic system was, on the date of our visit to Amsterdam, in operation in nine blocks of buildings, partially in the old city and partially in the new town, situated at—

(1, 2). Marnixkade,

(3.) Willemstraat,

(4.) Pieter Cornelisz Hoofstraat,

(5.) Stadhonderskade and Jacob van Campenstraat,

(6.) Bonwkas,

(7.) Focke, Simonszstraat (formerly Looÿersloot,)(8.) Sarphatistraat and Audueszkade, and

(9.) Heerengracht.

The blocks 1, 2, and 3 are brought in to communication with a central

tank placed between blocks 1 and 2 at the waterside; this tank is distant from the farthest privies in the blocks Nos. 1 and 2 311 metres, and from those in block No. 3, 288 metres. The pipes in block 3 are syphoned under the Lÿnbaausgracht canal.

The length of the pipes in block No. 4 is 725 metres from the

extreme point to the canal side, where there is a steamboat.

The greatest length of pipes in block No. 5 is 344 metres; in No. 6, 467 metres; in No. 7, 355 meters; in No. 8, 567 metres, and in block No. 9, 18 metres. The pipes are all of cast iron, and for the blocks 1 and 2 their diameter is 6 inches; the joints are made with caoutchouc rings and tightened with iron collars. In all the other blocks the pipes are five inches in diameter and the joints are made in the ordinary manner with lead.

The depth of the pipes beneath the ground varies from 0.50 to 1.50 metres; the greatest depth is the syphon under the Lÿnbaausgracht

canal which is laid at a depth of nearly three metres.

A special form of privy-funnel is connected with the "fall" or soil pipes by syphons; there are about 1,100 of these "privies" in use, by 4,837 persons.

The system was applied in 1871 to blocks 6 and 7, in 1872 to

blocks 1 and 2, and to the other blocks in 1873 and 1874.

In block No. 7, the city council not only paid the cost of the works inside the houses, but also the cost of the works in the streets; in the whole of the other blocks, however, they only paid the cost of the works in the streets. The entire cost of the work is therefore not known, but the Director of Public Works informed us that he estimates the cost of the works in the streets at 2l. per head of the population, and the cost of the works inside the houses at a like sum, or 4l. per head, but the costs of these latter works will greatly depend on the numbers of floors and numbers of privies in each house.

With the exception of the above-named block, No. 7, the work inside has been executed by the owners, and no control has been exercised over the work done; this latter circumstance is much to be regretted, because the good working of a whole system of pipes depends on the proper execution of the works in the several houses. There are consequently places where, from defective house fitting, the system does not work well, so that in some houses the privies do not act as intended.

Supervision of any new work within the houses is now enforced.

FURTHER STATEMENT BY THE DIRECTOR OF PUBLIC WORKS.

The Director of Public Works in a letter addressed to us, dated 29th September 1875, says:—

"We are afraid that we shall not be able to get rid of the whole production of excreta collected from blocks 1-9; it is evident that this cannot be done when the canals and rivers are frozen over, because the transport, per cart, for great distances cannot pay for refuse stuff of that

worth and weight."

"Fixed engines do the work of blocks Nos. 1, 2, 3, and 8, but all the other stations are worked by moveable engines; a steamboat, if the

canals are not frozen."

"Many stoppages have occurred in the street-pipes; and in some cases it has been found necessary to disjoint the pipes to remove the obstruction, when it has taken occasionally as much as three days to remedy the defect; stoppages have been caused by towels, rags, chignons, pieces of meat, and solid substances thrown into the privies. Ball-valves are used in blocks 1, 2, 3, 6, and 7; these balls, on becoming fixed, cause very

frequent but less important stoppages. The total quantity of excreta removed weekly is about 75 tons, and two thirds of that quantity is water; enough to prove that the prescribed rule, not to throw water into the privies, is not observed, but not enough to give ground for the opinion that all the slop water from the houses is thrown in."

"Until September last (1874), the fæcal refuse was leased by a gentleman farmer residing at some distance from the town who paid for each ton delivered at his farm 4s.; the delivery of it cost the municipality 3s. 2d. per ton, and although the lease did not terminate before the end of 1875, the gentleman disengaged himself some months before the

expiration of the term. He said the stuff was too dilute."

"The cost of working amounts to at least 5s. per head per year, but what we are doing here with our eight different points of working; using steamboat and locomotive, is not a fair trial of the costs of working a good application of the system, as, take a compact block of the town, say 50 or 100 hectares, with a fixed engine in the centre, and the working costs would be reduced."

"Besides these costs of working you have to add the interest on the

cost of the plant."

"Though we have not had a very severe winter since the Liernur system has been in operation, I think no other serious difficuly would be met with than the freezing of the diluted fæces in the barrels, which would make it impossible to get the stuff out of them. Captain Liernur pretends that the fæces ought not to freeze, but we know by experience that the diluted fæces do and the Pneumatic system does not produce other than diluted fæcal matter."

"To get rid of the stuff we have sold it, in the spring of this year, for 3d. and even for 2d. per barrel of 340 lbs. to different customers. This did very well till June or July, when we could not sell any more, the farmers not wanting manure before the end of the first harvest. We hoped to have the same customers in August, if not before, but until now, the end of September, we have had but few of them. They write that they will return in the spring, and we hope and think so, but you see it is a poor bargain to sell only a few months in the year when you are producing the whole year. So that the question of getting rid of the

stuff at a fair price wants still a solution."

"Captain Liernur pretends that a former administration has paid no attention to the conducting of the house and kitchen water in separate pipes, and even his friends have insinuated that for that water there was no separate sewer at all, so that people were obliged to throw the water into the Pneumatic pipes. Now, this is not the case, where the Pneumatic system is executed at Amsterdam, there is in the streets a separate system of drains for the rain and house water; in and near each house there are sinks, and in each kitchen there is the kitchen-sink or sewer; but Captain Lieurnur is so far right that in the blocks Nos. 2 and 3 there are privies in the kitchen; this is an abominable arrangement, and besides is a constant allurement for the cook to throw water into the privy instead of into the sink, the small dimensions of the waste pipe does not afford the servant such a good occasion for emptying her pail at once. However, Captain Liernur goes farther and deems it now necessary that on each floor, in or near the privies there should be a separate sink, the waste-pipe from which should be as large in diameter as the soil-pipe of the privy, so that there should be not the least inducement for the servant to prefer the privy to the sink. Captain Liernur has had occasion to prescribe all these new arrangements, for it is he who projected all the contrivances inside the houses. That he did not prescribe proper fittings in the first instance is his own fault, and it is a poor excuse for him now to say that this was the mistake of the administration, who had nothing to do with the inside fittings,

as they only paid for the works in the streets.

"But what is much more serious and to the point is this, that what Captain Lieurnur proposes now, and what is partly done at Leyden, is to my mind in flagrant disaccordance with the principles of the whole system; there is not the least doubt but that if there were more convenient ways of getting rid of the house and wash water of the upper floors than by the privy, this (the privy) would not be used, as it is now, for the removing of waste house water; but it is not the less evident that the privy, in that case, would not receive all the fluid excreta of the night, which would find its way with the wash water down the more convenient sinks. Captain Liernur himself states that perhaps now and then the contents of a chamber-pot will be thrown into his privy-pan, as into a sink.

"Now the quantity of the fluid excreta of the night (the blowing off at night and morning before going to sleep and before rising) is estimated at 4/7th part or more of the fluid excreta of the twenty-four hours, and as the fluid excreta does contain seven times as much nitrogenous or putrescible substances as the solid excreta, it results thereby that the making of convenient sinks in or near the privy closets includes the gathering of, about one half of all the excreta in the expensive iron pipes, and the losing, at least the other half of these substances, down the sinks and the earthenware pipes, which are not destined for that use, so that there is the danger of infection, which the whole Liernur

system professes to remove.

"In the 'Times' of the 23rd of September 1874, it is estimated that with the Liernur system waterclosets can be used without losing any of the agricultural value of the excreta by dilution. Now this may be the theoretical notion, but practically it is the reverse. Suppose the privy closets combined with the Pneumatic pipes, even arranged as Captain Liernur proposes, so that only a limited quantity of water is thrown in the privy closet each time it is used. He estimates the needed quantity of water at 2 lbs., and I cannot estimate it less; it is known that, on the average, each person uses a closet, or urinal, four times in the twenty-four hours, children do this more frequently. Each time the closet is used, however small the quantity of the excreta may be, 2 lbs. of water is to be thrown into the closet; that is, 8lbs. in the 24 hours. On the average, the production of excreta per head is 21 lbs. in the twenty-four hours; thereby it results that, even if the contents of the chamber-pot be thrown away elsewhere, the excreta will be diluted with four times their weight of water; that is, you will obtain a ponderous mass of no practical agricultural value; as is proved in Amsterdam, where the diluting with only twice the weight of water suffices to make the manure very difficult to sell at any price, because of the bulk and cost of removal, and in winter of storage. For the same reason, it is not true, what is said in the same paper, the 'Times,' that the system is independent of the house-dwellers, and yet it is stated that these by their inadvertence or mismanagement cause the city much loss by throwing water down the privy, or solids, such as towels and chignons, whereby stoppages occur in the pipes, as is proved by experience. It is said, that the management is in our hands, and that perfect working depends a great deal on the goodwill of the householders and their servants, and a strict observance of given rules, which are in practice grossly neglected. We, however, in Amsterdam dispute this, as we consider that the fault is in the system. We do not think

stoppages can be prevented, neither do I believe that there is a city in the world where the Pneumatic system can yield a good return upon the capital employed. I, however, for my part, don't think this necessary if the hygienic object of the system can be obtained, but I disapprove very strongly of misrepresentation; the system does cost a great deal of money, and therefore must burden the town with taxes.

"In Amsterdam the system is not used by more than some 6,500

inhabitants."

"It is not true that the expense of the Pneumatic system in Amsterdam has only been at a rate of 2l, per head of the population, including the changing of the existing privies and all other charges. The 21. per head may suffice for the outside, or street works, if you can use the existing sewers for the rain and house water; but you may reckon at least another 21. per head as the average for the changes inside the houses; or, in the whole, a cost of 4l. per head of the population. Of course in new quarters there is no changing; and, therefore less outlay, and the costs of changing in the existing parts of the town differ greatly in various quarters by the construction of the houses, the number of floors, and the number of the house-dwellers. I think, however, that even with a well-arranged system the annual working expenditure for a town of 20,000 inhabitants will exceed 2,000l. I know very well that what we are now doing at Amsterdam, though it is done under the advice of Captain Liernur, is not in all respects a fair trial as to the annual expenditure, because the system costs yearly about 1,2001. for not quite 5,000 inhabitants; this amount can be lessened much in new works, by not following our example of constructing works in eight different and separated parts of the town, as a compact arrangement would be more economical. However, I think that, basing my opinion on practical experience, it would cost not less than 3,000l. a year to carry out the system completely in a town of say 20,000 inhabitants. This would not however signify much if really the promised 10,000l. were to be got for the fæcal waste, as stated in the 'Times' newspaper, but we did not get more than 2d. for 340 lbs., and the party who had leased the whole for that price abandoned the bargain as soon as he could do so, on the pretence of the excremental matter being too dilute. Now suppose we had sold twice as much water as excreta, then we should have got for the production 1s. 6d. per head per year, and this for 20,000 inhabitants would be 1,500l. a year. If we could realize such an income we should think ourselves very lucky, and we hope the market we are trying to find would continue such an income. The pastures round this town are used principally, if not exclusively, for milch cows, and these meadows don't want such rank manure; but it is not less true, that as long as the canals are not frozen, there is no town situated so advantageously as ours, as, from every point of the city, we can convey, per vessel, this production to other parts of the country.

"I don't think there can be obtained any financial result by the making of poudrette, but we have no experience of that as none has been manufactured here. The city of Dordrecht will, it is said, try it in a few months. It is a great fault of Captain Liernur and his friends to awake high expectations about the returns to be expected from the

sale of the manure.

"If there is any worth in the system, it is in the hygienic side of the question, and I think that, in some cases, it may do much to lessen, if not fully to remove, a great existing nuisance. But I don't think it possible to apply the Pneumatic system, for instance, to London."

BADHOEVE FARM, HAARLEMMERMIER.

We visited the farm of Mr. J. P. Amersfoordt, at Badhoeve Haarlemmermeer, and that gentleman courteously gave to us the following information:—

"My farm has an area of 450 acres, of which 325 acres are meadow, 75 arable, and 50 timber and plantations; the soil is a rich loam upon a sandy subsoil. I keep a dairy of 45 milch cows, also about 100 oxen and young stock, and about 300 sheep. From January 1873 to December 1874, I received, from Amsterdam, the fæcal matter collected by the Pneumatic system, and the following account gives the quantity delivered each month, and the amount paid for it:—

Months.			Weight in Kilogrammes.	Price paid in Guilders and Cents.				
187	3.							
May -	-	-	111,180	300.18				
June -		-	154,730	417.71				
July -	-	-	119,420	322.43				
August -	-	-	94,255	254.48				
September	-	-	146,490	395-52				
October =	-	-	166,615	449.86				
November	-	-	146,170	394.65				
December	-	-	198,135	534.96				
187	4		100000000000000000000000000000000000000					
January -	4.	_	215,740	582.49				
February -	-	-	168,100	453.87				
March -			230,765	623.06				
April -	0.700		224,345	605.73				
May -		-	230,285	621.76				
June -	-	_	250,685	676.84				
July -			305,440	844.68				
August -	0200		364,130	983 · 15 7				
	-			I refused to have any more because it				
September	-		143,530	was so dilute, and the carriage was ex-				
October -	-	-	363,275	cessive, and it was delivered on to the				
November	-	-	296,430	farm during these four months without				
December	-	-	91,670	any charge being made for it.				
	To	tal -	4,021,390					

Or about 4,022 tons of fæcal matter delivered in 20 months, for which

I paid the municipality 905l. or at the rate of 4s. per ton.

"The excreta was sent to me by barges, and about 100 old petroleum barrels, holding about 36 gallons each, were delivered every day, Sunday included. On arrival at Badhoeve, the barrels were unloaded and carted on to the farm; the contents of five barrels were then emptied into a liquid manure-cart, and drawn over the meadow required to be irrigated; this method of applying the excrements did very well in fine weather, but after rain the surface of the meadows was so soft that it was very difficult to get the cart over the land, even with a smaller load, (i.e., the contents of two barrels at a time.) I found after using the excreta for some time, that the meadows gave little or no indication of being manured, and on my complaining to the municipal authorities of Amsterdam, they caused samples of the fæcal matter to be analysed by Mr. J. W. Gunning, Professor of Chemistry of the University of Amsterdam, and the following are the results:—

"In six samples of excreta, each sample being the mean of a series of samples collected during one week, we detected in each case nitrogen

per cent., No. 1,—0·348; No. 2,—0·366; No. 3,—0·400; No. 4,—0·349; No. 5,—0·336; and No. 6,—0·618, the mean of the six samples being —0·403.

"The municipality had guaranteed that the fæcal matter should contain, -0.9 of nitrogen per cent. After this I declined to take any more of the manure. The barrels contained all kinds of refuse which had been emptied into the privies, such as old rags, shoes, broken utensils, and corks. I should be willing to take the sewage; that is, the whole of the solid and liquid excrements combined, if regularly delivered on to my farm by sewer-pipes, but not in the irregular manner in which it has been delivered. The cost of the fæcal matter and the cost of distributing it over a portion of my farm came to nearly 4l. per acre per annum for the land thus manured. Butter being the chief produce of the farm, my milch cows did not graze the meadows which were manured with the excreta, because I knew by experience that it would have given a taste to the butter; and we, in this district, are celebrated for making very fine butter; but oxen, young stock, horses, and sheep fed in these meadows on which the excreta had been put preferred that to any other portion of the pasture.

"The whole of the farm is under-drained to a depth of three feet, the drains are 30 feet apart, and the drain-pipes are so arranged that they can be used for upward, or subsoil irrigation, the water being introduced

by means of a syphon laid under the adjoining dam."

ABSTRACT.

These Dutch statements show that the first cost of the pneumatic apparatus is very great, being at a rate of 4l. per head of the population, and that the annual expenses are at a rate of 2s. per head. This is all in excess of ordinary sewers and drains, and ordinary scavenging. The

income, it will be noted, is at present unsettled and uncertain.

The Director of Public Works at Amsterdam, on page 66, states that in his opinion it would cost yearly 3,000*l*. to carry out the Pneumatic system in a town of 20,000 inhabitants, and that the apparatus would cost not less than 4*l*. per head, or a total of 80,000*l*., which at 6 per cent. is 4,800*l*. per annum, or an annual total of 7,800*l*. If, therefore, London, with its 3,600,000 inhabitants, were to have its excreta removed by this system at a proportionate cost, the annual expenditure would amount to 1,404,000*l*., and all other main sewerage costs would remain as at present.

PARIS.

The city of Paris has a population of 1,851,792.

Formerly the southern part of the city drained into the Seine and Bièrve; and the northern part into the Seine and Menilmontant; but the whole of the sewage has been intercepted, and now flows to a point at Clichy when it is pumped through iron mains four feet in diameter, carried by the Pont Clichy across the river Seine to Asnières; and thence it flows over a portion of the plain of Gennevilliers. To this land also is conducted, through iron pipes laid beneath the carriageway of Ponts St. Ouen and St. Denis, a considerable volume of sewage from the districts of Montmartre, Belleville, St. Owen, and St. Denis.

The sewerage system of Paris consists of seven principal and fifteen secondary collectors. On the right bank of the Seine there are three principal collectors, converging to a chief one under the Rue Royale; (which conveys the sewage to Clichy); there are also three on the left bank of the river, and these communicate, with the chief one, by means of two syphons under the Seine.

The chief collector is 16 feet in height, 18 feet in breadth, and about three miles in length; the aggregate length of the main-sewers already

completed is about 354 miles.

The Plain of Gennevilliers is well adapted for sewage utilization, as it consists of a light open soil on a gravelly subsoil of considerable depth; and it, therefore, serves the purpose of a natural filter; but at the date of our visit, in September 1875, only about 400 acres were under irrigation.

In outline, the Plain very much resembles, although on a larger scale, the sewage meadows of Carlisle bounded by the Eden; and also the

Kendal sewage farm bounded by the Kent.

The principal main sewage-carriers are formed of brickwork, and are 7 feet wide and 3 feet deep, the branch-carriers being 3 feet 6 inches wide and 2 feet deep.

The daily volume of the sewage of Paris is equal to 343,700 tons, but only a limited portion of this (i.e., about 28,000 tons) is used on the land required to be irrigated, the remainder flows into the river Seine

at Clichy.

The whole of the solid excrements of the population are not allowed to go into the sewers; these and the contents of cesspools are collected and removed to the Forest of Bondy, and are there manufactured into poudrette; but as the streets are cleansed daily and the droppings of horses and surface dirt are swept and flushed through the gullies into the sewers, the sewage contains a large quantity of solid matter, not only

in suspension but also in solution.

In 1869 the municipality of Paris, having laid down the carriers, sub-carriers, conduits, and pipes for distributing the sewage over the land at Gennevilliers, conceded to the owners, and also to the lessees of the allotments, the free use of it until 1880, after which time, if they continue to use it, a rent is to be paid. At first there was a great prejudice against the use of sewage as a manure, and also the produce grown by its aid, but this has gradually died out, and the number of allottees who use the sewage increases every year, and the owners and occupiers are much pleased with the result.

The allotments are very numerous, and are let on lease for terms

varying from 3 to 15 years.

The crops grown under sewage-irrigation have been a perfect success; they comprised absinthe, artichokes, asparagus, beans, beetroot, cabbage, cordon, carrots, celery, chevil, chicory, cohl-rabi, cucumbers, leeks, melons, onions, parsnips, peppermint, potatoes, pumpkins, spinach, tomatoes, turnips, lucerne, clover, Italian rye-grass, mangolds, wheat, oats, and Indian corn.

The market-garden produce yielded very abundant crops. The asparagus is grown in nursery-beds as plants, and afterwards sold to gardeners, who force it for use of consumers. The Indian corn was of exceedingly luxuriant growth, 9 to 10 feet high. The potatoes gave a very good crop; the sewage is applied to the land before planting potatoes, and not to the growing crop, except in drought. The Italian ryegrass and lucerne yielded five cuttings for hay and two cuttings green for cattle feeding. It is found that the application of sewage to lucerne more than doubles the weight of the crop. A meadow of natural grass (principally cocksfoot) under sewage treatment, yielded three crops of hay in the year, and these realized 151. 15s. per acre. Application of

sewage to young fruit trees has also been very successful. The average yearly rainfall is 20 inches. The hot and dry plain of Gennevilliers is capable of absorbing a very large volume of sewage, especially in the summer season. It is found that the sewage does not readily freeze, and therefore can be applied continuously to the land. The available area of land at Gennevilliers is insufficient to receive the daily volume of the Paris sewage, and we were informed that it is in contemplation to extend the main conduit to St. Germain, and to irrigate the land lying on the edge of the forest, and also the forest itself if necessary.

The effluent water after percolating through the gravelly subsoil flows into the river Seine, and at the date of our visit it was clean, bright, and

inodorous.

BERLIN.

The sewage at present flows into large open channels or gutters by the side of the footpaths in the streets; these are principally lined with stone or bricks, and, where they cross the streets, are covered with deals; the gutters are swept by the scavengers daily, and the solid refuse removed therefrom, but the liquid flows from thence into the river

Spree and the canals.

A system of sewers is being carried out on the English plan, and for this purpose the city has been divided into five drainage districts, with a separate pumping station to each. The main and branch sewers are built of brickwork, egg-shaped in form; they vary in height from 4 to 7 feet; the subsidiary sewers are formed of stoneware-pipes of of from 9 to 24 inches in diameter. The sewers are chiefly laid at gradients of 1 in 500, the flattest being 1 in 2,400. Each of the five pumping stations will have six engines of 60 horse power each, four "Galloways" boilers, and two locomotive boilers as auxiliaries for getting up steam in emergency. The total pumping power will be 1,800 horse. Each of the pumping stations is estimated to cost 50,000*l*., and the entire cost of the sewerage works, pumping stations, and pumping mains is estimated at 2,000,000*l*. sterling.

No. III. works are nearly completed, and we were informed that the sewerage works in this district would be finished, and pumping at this

station commenced in 1876.

The sewers will receive, in addition to the sewage proper, the whole of the rainfall upon the houses and streets; arrangements having been made by which, in heavy storms, more than 4/5ths of the flood-water will escape by specially provided overflows direct into the river. The average yearly rainfall is 22 inches.

The municipal council propose to utilize the sewage in irrigation, and to enable them to do so, they have purchased, at a cost of 400,000*l*. (or about 100*l*. per English acre) 2,000 acres of land, a sandy soil, lying to the north, and 2,000 acres to the south of the city, distant there from about 10 English

miles, and these farms are being prepared to receive the sewage.

The sewage will have to be pumped through cast-iron mains, two to each farm, each 3 feet 6 inches in diameter, to a height of 130 feet.

It is estimated that the mean daily volume of sewage thus to be dealt with will be 28,000,000 of gallons; of this volume 16,000,000 of gallons will be delivered over the North Farm, and 12,000,000 of gallons over the South Farm; and, from the nature of the soil, it is expected that the whole of the sewage will be absorbed and completely oxidized.

Subsidence-tanks will not be constructed, but the sewage will flow direct from the pumping-main into the carriers, and thence over the

land required to be irrigated.

The estimated yearly cost of pumping the sewage is 12,000l.

One of the pumping-mains is already laid to the South Farm, and

upon this farm it is proposed to grow Italian rye-grass, roots, tobacco,

all kinds of esculent vegetables, but no cereals.

It is also proposed to lay down a branch line of railway from this farm to Marienfelde Station, which is about two miles distant, and by this means to bring the grass and vegetables into Berlin, and, if a ready sale is not found for them, the municipal council propose to keep a dairy of milch cows at their farm, and convey the milk to the city; they also propose to carry on the farms until they are in good working order, and then to let them with the sewage; but they do not propose to sell sewage en route, as they expect to make a better bargain by letting the farms and sewage together.

APPENDIX No. V.

EPIDEMIC DISEASE.

Epidemic disease will probably be a means of bringing about the greatest modern improvements in civil and social life, as inquiry and investigation make it more and more apparent that neglect of sanitary requirements in past ages has tended to generate plague and pestilence; and, in modern days, to bring about their occasional revival, with typhoid and cholera added. There are in the cycle of time wholesome and unwholesome seasons, periods of excessive wet, long continued generating malaria, and seasons of parching drought producing famine, the depressing influences in both cases lowering the public health and so exposing the human body to other influences immediately surrounding it which aggravate disease. Wet seasons deteriorate vegetation, and tend to produce disease in animals, so that the food of man becomes unwholesome; dry seasons reduce the produce of vegetation or destroy it altogether, so that man and beast perish. These influences should not be left out of sight in considering causes of disease, neither should they be made too much of; that is, excess of disease should not in all cases be imputed to climate, to seasons, or to the weather, if other causes more potent and deadly can be discovered and which causes can be removed. There are vague notices of great epidemics in remote ages in Ethiopia, Egypt, and India; notices more in detail of the plague in Athens 430 years before Christ; and there are histories of the Middle Age pestilences, plague, sweating-sickness, and black death, with our modern reports on typhoidfever and cholera. That which we know of parts of Asia and Europe as to the causes of disease we may infer of India, China, and the other inhabited portions of the surface of the globe; namely, that aggregated populations living amidst filth, devouring unwholesome food, drinking impure water, and living immoral lives, suffer from virulent disease, consequently existence is unwholesome, miserable, and short. Some of the prime causes of disease may be inferred from descriptions of towns, houses, and domestic habits and modes of living during the Middle Ages. Towns were crowded on to the least space possible to afford means for fortifications, the streets were narrow, the houses projecting storey over storey so as to shut out sunlight and diminish the circulation of air, the streets were unsewered and were irregularly paved with large and small boulder stones; if there was a gutter it was down the centre, and over the surface filth from the adjoining houses was scattered and lay there till it rotted. Within the dwelling houses filth also abounded. "The basement floors were mud, over which, in those of the better classes, were spread straw or rushes, and on to which went urine of animals and man, spittle, vomit, sloppings of beer, scraps of meat, bones, refuse from fish, and other filthiness not to be named, which were never thoroughly cleansed, the accumulations going on through long intervals." Such is a brief description of muni^cipal neglect in England about the time of Henry the VIIIth. A student need not, however, trouble himself to read history to learn how men consented to live amidst filth and neglect of all sanitary precautions in past ages, as in these days of rapid communication he may within the range of Europe visit and inspect towns, dwellings, and populations existing not very much if any below the horrible conditions described by the old historian; but even in Great Britain at this day the description may be accepted as partially true of vast masses of the populations resident not only in the slums of our great cities and towns, but also in our rural villages, the Common Lodging Houses Act and the more recent Artizan and Labourers Dwellings Act having, however, been passed to provide remedies.

În 1848 there was passed the Public Health Act, consolidated into the Public Health Act of 1875, and under this latter Act sanitary work is proceeding. The prime block to more rapid progress being dread of

local rating and ignorance of the cost of continued neglect.

As there is no value without human life it follows that healthy human life must be of most value, and consequently that any rates which are necessary to secure health and long life must be worth providing. Past history shows that disease in most horrible forms has from time to time destroyed populations living amidst filth indescribable of their own making. Recent inquiries show that modern diseases of malignant types, such as typhus and cholera, generate out of putrid refuse and gross neglect of sanitary works and operations. Modern civilization aggregates populations, and necessitates modern sanitary improvements, and that form of improvement will be best which permanently produces

the most favourable results at the least pecuniary cost.

In cleansing towns, fluid and solid refuse has to be removed; its removal must, therefore, be specially provided for. Rain-water may in some cases flow over the surface by natural channels, and in other cases by channels formed for the surface-water. Towns require to be scavenged, and the solids, ashes and vegetable refuse, have to be removed by carts. Human excreta must also be removed, either in pails or by some other system, wet or dry, or by waterclosets, drains, and sewers. That system which can be established and carried out at the least first cost, and can be worked with the most complete efficiency, will be the best-efficiency implying comfort and wholesomeness. To remove the waste-water from houses and towns as fast as used there must be drains and sewers, as cesspools and water-carts would be im-Through properly constructed drains and sewers water will flow to any required distance, and will wash to the outlet all effete matter from the population at once without any secondary intervention or cost. The sewering of towns and the draining of houses is comparatively new, and there is much imperfect work. There are also numerous mal-arrangements, such as drains and ashpits within house basements, and unventilated waterclosets within the body of the houses and crowded betwixt bed rooms; consequently there are nuisances and fevers, all of which may be prevented. In every form of dry method (there is, however, no such thing as a "dry method") or pail-system, there must be retention, for a time, of the excreta; and there must be fetching, carrying, and returning of the boxes, tubs, pails, or whatever the apparatus may be in which the excreta is received, and the nuisance caused will be in proportion to the time of retention of the excreta within or near the dwelling house, the capacity of the tub or pail to receive the contents without slopping; the regularity, care, and cleanliness in removal; and the treatment of the refuse at the yard or station. If unceasing attention is given to the removal, and rigid cleansing of the tubs and pails at each emptying, and the intervals of removal are short (never to exceed one week), the terrible nuisance of the old privy

and midden system will be abated in some measure; but a week's retention of excreta within or near to dwelling houses must constitute a nuisance. The returns obtained and tabulated in this report show that the cost of tub and pail removal is considerable, and that in no case can the manure be sold to a profit. A rate must, therefore, be levied sufficient to pay the interest on capital and working expenses. The cost of sewering and draining must also be paid for by a rate, but along drains and sewers the excreta will pass without any retention or secondary intervention at once to the outlet, there to be disposed of. Deposition in tanks and chemical treatment of the sewage will remove the suspended solids, but will not produce a pure effluent, neither will the deposited material, sewage-sludge, produce a manure having commercial value. must, therefore, be a rate in aid to work the best known chemical process as yet tried, or the parties working such processes must lose money. In irrigating land with sewage there is both clarification and purification, in proportion to the strength of the sewage, the volume used over any given area at one time, and the adaptability of the land for the purpose; no mode of treating sewage by deposition and chemicals producing such favourable results. Where sewage can gravitate to land obtainable at its fair agricultural value, there is the least present loss to the community; and, in nearly all cases when the works have been paid for, there will be an available income, a result not attainable by any other known mode of dealing with sewage.

THE PRIVY SYSTEM.

"However perfect in theory the ash-pit privy may be as a means of house scavenging in towns, in practice it has been abominable, and though latterly improved by better organisation and more vigorous superintendence, and the gradual adoption of various ingenious contrivances, it can never be otherwise than highly objectionable—land must get soaked with the drainage water from these cesspools; the air must get fouled with their stinking vapours; the sewers must carry from them to the river that which is most filthy and yet most valuable.

"It was a good suggestion by an opponent of the system, that its friends should picture to themselves the sites of Manchester and Salford, with all their dwelling-houses removed and only the privies left-nearly 60,000 of them-rows, and streets, and crowds of themscattered about almost as thickly in places as the heaps of manure upon a field that has just received a dressing from the dung cart, each heap, however, no mere deposit by a barrow-load, once a year, but a constant collection and continual soakage of filth, which has for years been polluting every corner to which air or water could have access. Is this the site upon which to build a healthy town? would it not be the first desire of every sensible man to sweep this filth away, to drain and aërate; and, if possible, sweeten this land before a single dwelling -place was built; at any rate, to put a final stop to the process which has accumulated so much dirt, to which, indeed, one may fairly attribute much of the responsibility for the high death-rate disclosed by the returns of the Registrar-General, from the South Lancashire towns. Those returns show that typhoid fever, scarlatina, diarrhea, and other zymotic diseases, commit fearful ravages amongst the populations exposed to such pestiferous influences.

"The relative polluting effect of sewage from midden towns, as compared with that from watercloset towns, is no mere matter of opinion founded on à priori argument. It has been made the subject of direct investigation." (Rivers Pollution Commission Report, Mersey and

Ribble Basins, 1870, pp. 28, 29.)

"The proportion of putrescible organic matter in solution in midden

towns is but slightly less than in watercloset towns, whilst the organic matter in suspension is somewhat greater in the former than in the For agricultural purposes, 10 tons of average watercloset sewage may, in round numbers, be taken to be equal to 12 tons of average privy sewage. The average quantity of chlorine in 100,000 parts of watercloset sewage is 10.66, while in midden sewage it is 11.54. This difference is very significant; it shows that, assuming (which is probably approximately the case) all the urine to reach the sewers in both classes of towns, a larger number of individuals contribute to a given volume of sewage in midden than in watercloset towns. Chlorine in these cases represents common salt, and the latter again indicates the proportion of the urine in the sewage. The proportion of chlorine, therefore, ought to give the proportion of average individuals (men, women, and childen) contributing to each kind of sewage, and from this it would follow that the populations producing equal volumes of sewage in midden and watercloset towns are as follows:-

In watercloset towns - - - 1,066 In midden towns - - - 1,154

The cause of this difference in the volume of sewage per head of population in the two classes of towns is obviously to be sought for in the somewhat increased quantity of water needed by and supplied to the former."*

The Conditions of some Towns, Villages, and Houses in Great Britain at this date, 1876.

1. There are towns, villages, and houses in Great Britain entirely without sewers, house-drains, or even common privies; the condition of the streets, roads, and lanes, indicating to sight and smell the habits of such populations.—See Health of Towns Reports, 1842, and the Reports of the Superintending Inspectors of the Board of Health 1848, White-haven for instance.

2. There are other towns, villages, and houses where there are cesspits, cesspools, and privies, for portions of the population; the privies and ashpits being in all sorts of improper public places, crowded against houses, with some beneath occupied rooms; and those in open and exposed places having shattered doors, broken seats, rude ruinous cesspits; the places and all about them being filthy beyond description.

3. There are other towns and districts situate in porous but water-logged sites, where there are wells and cesspools side by side; the subsoil-water, according to the season, rising or falling simultaneously in both wells and cesspools, the water of the wells being dangerously tainted

by sewage from the cesspool.

4. There are some towns and districts imperfectly drained by rudely formed stone drains, originally made to remove surface-water, but which the inhabitants now use for sewage; consequently creating a nuisance.

5. There are towns and districts partially sewered and where waterclosets are partially used, the larger proportion of the population, however, still using common privies and cesspits, whilst many of the inhabitants have no sort of privy accommodation provided, but chamber utensils are used by the females; the yards, roads, and lanes, being fouled by the males and children.

6. There are towns and districts fully sewered upon correct principles, but the houses are not drained, and, as there is no public water-supply, there are only a few waterclosets—common privies and cesspit-middens

remaining.

^{*} Extracted from the First and Second Reports of the Rivers Pollution Commissioners, Mersey and Ribble Basins, pages 24, 25.

7. There are towns and districts which are completely sewered, drained, and have a full water-supply. Cesspools and cesspits having been abolished, waterclosets substituted, and the sewage at the outlet being applied to land for agricultural uses. But even in such towns there are grave defects, as neither sewers nor drains are fully ventilated; and many of the waterclosets are situate in improper parts of the house and are also defectively ventilated.

The defects stated in the above seven cases have been described over and over again in the Sanitary Reports of the last twenty-five years, and there has been, and now is, considerable movement to obviate some of the most glaring evils enumerated. But the local authorities, in many cases, shrink from incurring the first costs of main-sewers, house-drains, the abolition of cesspits and privies, and the establishment of waterworks; the substitution of waterclosets and providing land for sewage irrigation. Hence the adoption of patented schemes of various kinds, dry and wet, for the removal of excreta, all of which are costly failures. The prohibition against polluting streams with sewage has also brought in patented modes of dealing with sewage, the inventors professing to purify it, and to make a portable manure out of the sediment which shall have commercial value. Every such scheme, up to this time, having, however, failed even to purify the sewage, as well as failed to pay working

expenses by the sale of any manure made.

Sewering, draining, a public supply of water, and scavenging, are necessary to the comfort and health of town communities, and a purification of the sewage outside of the town is necessary to the health of the country, and so far no form of portable apparatus, wet or dry, dry-earth closet, or Rochdale, pail, can dispense with sewers, drains, and a public water-supply. So far, then, all are agreed. The waste water from houses, streets, yards, and manufactures must flow away through sewers to some common outlet; and, as this fluid is polluted by every form of pollution within a town, though excreta is absolutely excluded, it is, in fact, sewage; it must, therefore, necessarily come under any laws and regulations enacted against polluting streams with sewage. These facts are either not appreciated or are not understood by those persons who adopt the various moveable apparatus and work them at so great a cost to the ratepayers. As to the so-called "dry-systems" there is no such system, because all are necessarily more or less wet. The pails do not receive and remove all the urine, as is shown by the returns of the weights removed by the pails used at Rochdale in proportion to the Captain Lienur, in his most complicated and costly pneumatic system, does not profess to remove all the urine, but insists upon special provision being made for the reception and removal of waste-water. As side-by-side with his pneumatic privy-pan-closet, he states that there must be a sink for waste-water and the contents of chamber-utensils entirely distinct from his apparatus. This must also be the case with dry-earth closets, as also with moveable pans, tubs, or pails; either on the Rochdale plan, or indeed on any other such system. These facts being so, where is the advantage gained by all the extra intervention, labour, and costs incurred? The pleas used in favour of these several modes of removing excreta are, their advocates say, greater comfort to the householder, extra cleanliness, freedom from nuisance, and absolute freedom from any form of pollution sufficient to cause disease. This most desirable result unfortunately depends, however, upon so much perfection in the working establishments as to prove, practically, to be unattainable. A dry-earth closet in summer, if not attended to, becomes a small cesspit. And this attention involves daily removal, effective cleansing of the box, and renewal of dry-earth. I have seen dry-earth closets most disgustingly dirty through misuse and neglect. The several portable tubs and pails are also liable to similar contingencies

of neglect, as the tubs and pails are at times left too long on the premises, and they then become over full and slop over and flood the surrounding surface with matter most offensive to sight and smell; the removal of the wet tubs and pails is dirty work, as there is frequently slopping over the street-surfaces from the vans during removal, and some of the stores, depôts, or yards, to which the pails are removed are reported to be very filthy and offensive. The mixing and making into manure is costly and does not pay. The removal of excreta in this manner is encumbered with the removal to and from the houses and the depôt by van and horse, so that for each ton of excreta there is at the least two tons of dead weight to move backwards and forwards with all the labour besides the wear-and-tear involved. In the Liernur system the apparatus draws the excreta to the pumping establishment, but from this point it is loaded into barrels for transmission into the country, where, as we learn, it becomes a nuisance in winter, as the tubs freeze and burst.

With respect to the practical value of any of these concentrated manures, that is concentrated when compared with town sewage, it is difficult to arrive at a reliable estimate, as experience so far tends to prove that the chemist's laboratory estimate of value is not accepted by farmers. The mixed excreta, that is the mixture with ashes, reduces the selling price to 2s. 6d. per ton, and even at this price there are large accumulations during those portions of the year when farmers are busy with sowing, haymaking, or harvesting. In some towns the mixed manure is given. Whatever may be the demand for portable sewage manure in the future, the several modes of manufacture have so far failed to secure for the patentees any profit. The cost of any really effective mode of dealing with excreta should not be sufficient to condemn it, as means of cleanliness, comfort, and health, are worth paying for; and, if the means used are, under all local conditions, the best for that district, or the ratepayers choose to consider them the best, then they must pay the necessary costs. The promoters of these dry-earth and moevable wet-tub and pail processes are not however contented to perfect and advocate their own special schemes, but they condemn all other modes of dealing with excreta in unmeasured terms,—especially the watercloset,—as this, they say, taints alike the atmosphere both of the town and of the houses. With respect to the use of the watercloset, the case may be thus stated, All parties admit that towns must be sewered, and that houses must be drained to remove surface-water and waste-water from dwelling-houses and factories; this being the case, these sewers and drains must be of cross-sectional dimensions sufficient to remove not less than 30 gallons per day, in dry weather from each inhabitant, and the capacity ought not to be less than five times this to provide for occasional rain. All sewers and drains receive more or less of sediment, washed from roofs, vards, sinks, channels, stables, slaughter-houses, cow-sheds, and manufactories, and along sewers truly formed the entire contents pass day by day to the outlet, and where waterclosets are used the entire excreta, solid and fluid, with the contents from the chamber utensils and sloppail, pass at once silently and imperceptibly with the sewage to the outlet, there to be dealt with under one set of operations, avoiding every form of secondary intervention involved in a use of dry-earth pan and pail. The entire of the excreta, in proportion to the sewage in dry weather being, by volume, as 1 of excreta to from 100 to 150 of sewage; and in wet weather, the proportion is of course much greater, consequently, in every portable form of dealing with excreta by the dry-earth or tub and pail systems, the bulk and weight is formidable, and the removal costly, whilst in the water drainage system this bulk is unimportant, because it is only fractional. With respect to the supposed nuisance and danger arising from waterclosets, proper construction and

use render any atmospheric or other taint within the house absolutely impossible, and the sewage flowing daily in a fresh state from the closet-pans along fully ventilated sewers gives no injurious taint. There must, however, be no drains nor openings into drains within the houses. Sink-pipes must discharge over or into a drain outside, and waterclosets must be against an external wall, connected with a soil-pipe, which is carried above the roof; the upper end to be fully open, and the watercloset rooms must have a day-light window, and fixed means for permanent ventilation to the external air at the ceiling. With such arrangements, and a good supply of water, one of the best waterclosets will work with perfect safety, and may be, what such places should in all cases be-private. The mode of dealing with the sewage, at the outlet, is in no way complicated nor rendered more difficult to deal with by the addition of the excreta from the watercloset; indeed, if the sewage is used in irrigation, it is dealt with to much better advantage; as the fluid is richer by so much manure. Bedford, Leamington, Croydon, and Cheltenham are cases in point, where the entire populations use waterclosets, and the sewage is also used in irrigation for purposes of agriculture.

That waterclosets can be used on the greatest scale by an entire population, is further proved in the case of London, where, for 3,600,000 population there is, on an average, one watercloset to each 5.5 of the

inhabitants, or about 700,000 waterclosets are in use.*

The excreta passed daily from London may be estimated at 4,000 tons, and to remove this in tubs or pails to a distance of five miles, would cost about 1,000*l*. per diem, or 365,000*l*. per annum. The daily volume of sewage and excreta of London weighs about 600,000 tons, and this flows along the drains and sewers to the outlet at no cost but that of pumping, which is about 36,000*l*. per annum. In many towns this cost would not be necessary, as the sewage will flow to the outlet, but in every case of the dry-earth tub or pail systems there must be the cost of hand removal and carting.†

EXAMPLES OF SEWAGE IRRIGATION.

EXTRACTED from the FIRST REPORT of the COMMISSIONERS appointed in 1868 to inquire into the best means of preventing the Pollution of Rivers.—Mersey and Ribble Basins.

The information extracted from this rivers pollution report bears so intimately on the questions discussed in our Sewage Report, and the several analyses are so full and complete, that we have considered it

* With respect to waterclosets, soil-pans, and urinals, no watercloset, soil-pan, nor urinal should be supplied with water through a screw-down cock, stool cock, or lever-handle, direct from the water-main, but through a service-box or water-waste preventer.

[†] The late Dr. Parkes, F.R.S., made exhaustive experiments with disinfectants, and found that it would cost about threepence for the chemicals to disinfect one gallon of putrid excreta, so that the disinfection of 4,000 tons per day of London refuse would cost 11,200l., or at a rate of 4,088,000l. per annum, leaving the 600,000 tons of sewage per day (or 219,000,000 tons per annum) untreated. These figures only serve to show the extravagance of disinfectants; as, also, that the small doses of Condy's fluid, or of any other fluid, or solid, passed down sinks, waterclosets, drains, and sewers, can practically have no beneficial effect. Foul drains and sewers can only be disinfected at a cost proportionate to the weight and volume of excreta and sewage in the drains and sewers, and this we see would be enormous; they must be flushed with water. Disinfectants may be used with advantage in hospitals, in sick rooms, and in stables; they may also be used by butchers and by others, but they will be practically useless in cesspools, if only small doses are applied; and it is to this fact attention is intended to be directed. The vestries are only wasting parish rates when they send round carbolic-acid to be poured down street gullies by tablespoonfulls. The foul gullies, drains, and main-sewers, may require cleansing, and if so, should be cleansed by flushing, as a use of chemicals for the purpose will be out of the question, on account of the enormous cost of such applications.

advisable to repeat them, rather than to have incurred the great cost and delay which must have taken place if we had obtained new analyses, which could not in any serious degree have furnished more reliable information than this we have extracted. The questions relative to town-sewage, and the best modes of dealing with it, have been so far exhausted that new experiments are not so much required as condensation of ascertained facts put into the plainest language and the least space. Town-sewage is stronger or it is weaker in proportion to the density of the population, the number of waterclosets in use, and the volume of water with which the excreta is diluted. There are three sources of dilution, as, the volume of water supplied to the inhabitants from waterworks; the volume of subsoil-water which leaks into the sewers; and the volume of rain or surface-water which is admitted to the drains and sewers during wet seasons. In manufacturing districts there may be both further dilution and pollution if all the fluid refuse is admitted into sewers. This is, however, a question for municipal regulation. The extracts which follow are given to show town-sewage in its crude state and after filtration through land :-

1. The Sewage Meadows near Edinburgh.—These have long been quoted as an example of the largest produce known to agriculture, yielding grass of a somewhat coarse and "washy" character, but perfectly well adapted for cow food. These meadows cannot, however, be named as a good example of the agricultural remedy for the nuisance created by town sewage; for it is poured over them in such enormous quantity that the soil has not fair play given to it as a cleanser, and the water therefore leaves the grass land still filthy and offensive. Even here, however, we have a remarkable illustration of the purifying power of soil and plant. Thus, on April 16th, 1869, when the early crop of grass was being cut, and the meadow land was in full spring growth, three samples of the sewage were taken, No. 1 being of the water in the Foul Burn, as it poured, probably 700 tons an hour, over plot No. 11, on the map of the Craigentinny Estate. No. 2 was taken at the foot of this same bed, the water having poured at that rate in half an hour over less than an acre of land. No. 3 was taken at the foot of beds Nos. 45 and 46, the tail water of No. 11, which poured on at their head, having in the meantime taken about an hour to traverse one and a half acres of land. This sample represents the water of the Foul Burn as it flowed into the sea. It was not by any means clean, but how much of its filth had been removed during irrigation by the action, for an hour and a half, of two and a half acres of land on many hundred tons of very foul sewage is plain from the following table :-

RAW AND EFFLUENT SEWAGE.—EDINBURGH.
RESULTS OF ANALYSIS expressed in parts per 100,000.

Date and Number of	olid Matters Solution.	Carbon.	Nitrogen.	Ammonia.	n as Nitrites Nitrates.	Combined trogen.	Susper	ided Matt	ters.
Sample.	Total Solid in Solut	Organic	Organic	Ашт	Nitrogen and N	Total C Nitr	Mineral.	Organic.	Total.
No. 1, April 16/69	62·20 65·50 51·60	6·106 4·797 3·340	3.613 2.086 682	9:510 10:579 1:989	0 0 0	11:445 10:798 2:320	11:32 9:76 1:28	28:08 16:64 4:24	39:40 26:40 5:52
No. 4, April 17/69 - 5, ", ", -	55.00 54.80	5.061 4.061	2.842 1.988	7.865 3.100	0	9°319 4°541	28.72 5.56	29.88 7.40	58:60 12:96

On the following day, after a night's rain, when the sewage therefore was more dilute, a sample, No. 4 in the above table, was taken from the Foul Burn at Lochend just as it left the pumps, at the rate of about 20 tons an hour, pouring over a plot of Italian ryegrass, 40 yards wide and 44 yards down the slope. It was taking about an hour to traverse this plot of one-third an acre. A second sample, No. 5 in the above table, was taken at the foot of this plot. The composition of these samples is given above; and comparing No. 1 with No. 3, and No. 4 with No. 5, the cleansing agency of the soil, however incomplete, is very apparent. In point of fact, more than three-fourths of the whole filth, soluble and suspended, was taken out of the water of the Foul Burn by one hour and a half of irrigation in the first case, and nearly two-thirds of the filth in 20 tons of sewage was taken out of it in the latter case, by irrigation over about one-third part of an acre of the light sandy soil of the Lochend Farm.

The Edinburgh experience, however, is rather one of agricultural profit from the use of sewage than of that perfect abatement of its waste and nuisance, which, in the interest of rivers, we desire to see. This arises from the enormous quantity of the sewer water and the small area of land on which it is used. At Lochend and Craigentinny, on the north and east of Edinburgh, about 230 acres receive the whole drainage of 80,000 people, being at the rate of 350 people per acre. At Grange, on the south side of the city, 16 acres get the drainage of a comparatively small number. At Dalry, on the west, 60 acres or thereabouts receive a very large quantity of filthy sewage, which they are unable perfectly to clean; and there are one or two plots similarly treated on the road to Leith. Here, however, altogether are only 400 acres, whereas the population whose drainage they receive must largely exceed 100,000, and it is not, therefore, surprising that the drainage

water leaves the land by no means perfectly cleansed.

The Foul Burn which waters the Craigentinny meadows passes first through Lochend farm, where about 20 acres of permanent grass and 8 acres of Italian ryegrass receive as much of it as the tenant chooses to apply. The quantity is, probably, often as much as 10,000 or 15,000 tons per acre during the growing season, besides an indefinite quantity during winter; and, of course, a very small proportion of the filth which it brings down from Edinburgh is deposited here. The stream flows on in almost undiminished foulness to the meadows lower down. In addition to the 20 acres of permanent grass land, there are 12 acres arable at Lochend (of which 8 acres are every year in first and second vear's Italian ryegrass) commanded by a self-acting pumping apparatus. A water-wheel, driven by the stream, works a four-fold pump, delivering, when in perfect order, about 1,000 cubic feet per hour, a quantity which, as it works night and day during eight months of the year, corresponds to nearly 20,000 tons, or, even assuming that only half duty is accomplished, is 10,000 tons per acre. In either case it is plain that an enormous quantity is applied-much beyond the needs of the largest possible crop of grass.

The grass of Lochend meadows has averaged, during nine of the spring sales at which it is disposed of by auction, 27l. 12s. 2d. per statute acre. During the past year the highest price attained was 41l. 17s. 6d. per acre; and from that down to 19l. an acre has been realised. The Italian ryegrass on the same farm has varied in price from 32l. an acre for the first year's cuttings to 25l. an acre for the

second year's cuttings.

Leaving Lochend the Foul Burn pursues its course to the sea on the Portobello side of Leith; but it has for many years been diverted, right and left, to a considerable distance from the original watercourse, and a fan-shaped farm of more than 200 acres, widening out as it gets near the coast, has been thus laid out for irrigation at a cost of about 5,000l. This Craigentinny farm includes within its limits land of excellent natural fertility, but it terminates at its lower end in a wide belt of sheer sea sand, which, though now equal in its annual produce to any of the originally superior plots, old men still remember as a barren shore. There is here too a portion of higher land of excellent natural quality watered by a pump, in this instance driven by steam power. The area this year watered thus is eight acres, and as the engine is driven only 300 hours during the six or eight dressings which this land annually receives, the pump, delivering from 60 to 80 tons an hour, does not distribute more than 3,000 tons per acre annually, a quantity which at 1d. per ton, if ordinary sewage be taken to be worth so much, many ordinary agricultural crops would easily repay. These eight acres of Italian ryegrass have been sold during the past year at from 25l. to 36l. an acre,-prices equal to those obtained at Lochend, where four times the quantity of sewage is applied. It would seem therefore, that the enormous surplusage of foul water used at the latter place fails to be of

any agricultural service.

In the lower Craigentinny meadows 190 acres receive probably ninetenths of the Foul Burn, and, a night and day waterman being constantly employed in its distribution, it flows constantly over one plot after another; a single dressing of five or six hours being given between the several cuttings of grass to each of the 250 plots, or thereabouts, into which the whole area is divided. The summer's grass of these beds, varying from two to five roods each, is sold by auction to the Leith and Edinburgh cowkeepers every spring, and the maximum value reached last year was 361. 15s. per statute acre. The quantity of grass for which such prices are obtained is believed to vary from 50 to 70 tons per acre. And as the means are perfected of distributing the sewage more evenly, and as the subsoil drainage of the land improves, the quantity and price are both increasing year by year. No exhaustion is apparent anywhere. The sewage brings down more than the plants require of every necessary constituent of their food, so that even the poor sea sand is as fertile as the rest, and the land is getting richer year by year, notwithstanding the enormous crops it yields. Taking the average price of the whole 240 acres to be 24l. an acre, we have a total annual produce of 5,760l. a year extracted by the land and grass from the drainage of 80,000 people, or 1s. 5d. from each person annually certainly not $\frac{1}{3}d$, a ton over the enormous quantity of sewage which is here applied.

But the area is not sufficient to take up the whole of the filth brought down by the water. A much larger extent of crop could be obtained from the use of it if there were any land convenient on which it could be applied, or if there were a sufficient demand for the produce of it. The Edinburgh experience, therefore, must be quoted not as a successful example of sewage cleansed by irrigation, but rather as an instance of the largest produce raised my means of it from a limited area of land.

2. Lodge Farm, near Barking.—We turn now to an example of another kind, where the supply of sewage is limited and where the object has been, from this limited supply, by means of an ample extent of land,

to obtain the largest annual produce. Neither at Edinburgh nor at the farm near Barking in the occupation of the Metropolis Sewage Company has the sanitary result or the purity of the water been the object aimed at. In the latter case, however, it has incidentally been secured. The object having been to obtain by agricultural use the largest return from the sewage used, it became necessary to make it as clean as possible before letting it go. At Lodge Farm, near Barking, the Metropolis Sewage Company in 1866 took about 200 acres, for the most part a light gravelly soil, (an analysis of which is given at page 67,) for the purpose of illustrating thereon the value of North London sewage, of which they hold the concession for a term of years. The land had been accordingly laid out in beds varying from 50 to 150 feet in width, with a central carrier down the middle of each, and having a slope from this carrier on either side, down which the sewage trickles to a midway furrow. The carriers are, as nearly as the general slope of the land allows, horizontal; the slope on either side varying from 1 in 20 to 1 in 60. The sewage is pumped from the outfall on the Thames, near Barking, through a 15-inch pipe to a reservoir on the highest part of the farm, and from that it is conducted in open ditches to the ridge-line carriers of these lands. These carriers, being stopped at intervals by the spade of the waterman, overflow; and the sewage, passing over and through the soil to the furrows, is by them conveyed to the lower slopes of the farm, over which it is distributed until it either sinks altogether into the land, or flows finally off the surface at the foot of the farm. The soil is too pervious and has too hollow and open a subsoil to permit the water to travel far upon the surface, so that after 50 yards at most of surface flow it sinks to reappear only at the mouth of the main drain of the farm; which, nearly dry in ordinary weather, pours a full flow within an hour or two of the sewage being applied to the fields. Samples of water taken here represent therefore properly enough the effect of soil and plant upon the London sewage under such circumstances as the Lodge Farm supplies. The following table gives the composition of successive series of samples taken (1) at the carrier, (2) after 50 or 60 yards of surface flow, (3) after a further surface flow; and (a) at the foot of the farm where the main drain pours it into a stream.

RAW AND EFFLUENT SEWAGE.—LODGE FARM, BARKING.
RESULTS OF ANALYSIS expressed in Parts per 100,000.

Date and Number	Solid tters.	Organic Carbon.	Organic Nitrogen.	Ammonia.	nas Nitrates Nitrites.	Combined trogen.	Susper	nded Matt	ers.
of Sample.	Total Solid Matters.	Organic	Organie	Amı	Nitrogen:	Total C	Mineral.	Organic.	Total.
* { 1. April 22, 1868 - 2. " " a. " " a. " "	112.50 90.55 91.75 79.25	12:182 4:331 2:768 1:366	3.664 1.872 .624 .329	4.000 2.250 2.500 800	0 1026 1032 21955	6.958 3.751 2.715 3.943	=	=	Ξ
1. June 23rd, 1869 2. " " a. ", "	65°30 74°30 79°50	2.596 2.028 887	1.715 1.285 .236	4.000 2.437 425	0 •693 2•535	5.009 3.985 3.121	18 48 3 06 trace.	27.80 3.40 trace.	46.28 6.46 trace.

^{*} In this series of samples the suspended matters were not separated, but the liquids, just as collected, were submitted to analysis.

Comparing 1, 2, 3, with (a) in the first, and 1, 2, with (a) in the second of these examples, we observe the cleansing effect of land and soil in two separate instances, in both of which about 2,000 tons of sewage passed in the course of nine or ten hours over five or six acres of land; but in neither of them had the sample received more than an hour's treatment from soil and plant together. The soil of the farm is indeed too hollow and porous to allow the most to be made of the manure. Sinking away even in the channels which carry it from the reservoir, much of the sewage is wasted before it reaches the plant; and the remainder which trickles over the surface of the grass remains there too short a time for the entire extraction of the fertilising matter which it conveys.

It will be seen, however, that the effluent waters marked (a) in the

two series of trials were to a great extent purified.

Turning now to the produce of the sewage, here considered not as a nuisance but as a valuable manure, it appears that 300,430 tons were, in 1867, used over 56 acres of land, and 2,480 tons of Italian ryegrass were cut off that area. Of the sewage, however, no doubt a great deal was lost in the channels and on the land in first starting the process; and, as regards the grass, we are informed that a large proportion was killed by the unusual frost of January 1867, only 13 acres, in fact, of the whole extent having been in full bearing; and these yielded 62 tons of grass per acre. It appears, therefore, upon the whole experience, that for every 100 tons of sewage applied one ton of grass per acre was obtained over and above the natural produce of the soil and climate. In 1868 and 1869, experiments over a considerable extent of land have been made with other crops than grass, to which alone, or to equally succulent growths, so dilute a manure as sewage appears at first sight to be adapted. A field of 13 acres of poor gravel that was in wheat in 1867, yielding then about 31 quarters per acre, was sown in 1868 in the following manner: -43 acres with wheat early in November, 21 acres with winter oats, 4 acres with rye, and 2 acres were planted with cabbages in October, which were taken off in March, and mangold sown in their place. The wheat was twice flooded with sewage, in March and in April, 450 to 500 tons to the acre being applied in the two dressings. The crop produced 51 quarters, and three loads of straw to the acre. The winter oats were three times flooded in March and in April, over the whole, and over a part in June, receiving in all about 500 tons to the acre. These oats yielded eight quarters of corn, with three loads of straw per acre. The rye was flooded twice, in March and in April, in all with about 450 to 500 tons per acre; it was cut in July, and thrashed in the field, yielding six quarters, with three loads of

If it be urged that in such an unnsually dry season as 1868, good results would necessarily follow irrigation with town sewage, it must be remembered that although these crops no doubt benefited in common with those of the whole country by the lengthened fine weather, the soil is a dry burning gravel, and no sewage was applied to either wheat or rye after the month of April, up to which time there was the ordinary amount of wet weather, without any unusual heat. The same field has been again in wheat and oats and barley, and the experience of 1869, with a cold May and June, equally with that of the hot and dry season of the previous year, bears ample testimony to the power of sewage upon this soil as a manure for corn crops. The wheat has yielded 4 quarters per acre, the winter oats no less than 11 quarters per acre, the barley

ripening unkindly only $4\frac{1}{2}$ quarters per acre; but it must be remembered in all these cases that the field, naturally a poor gravelly soil, was then yielding its third successive grain crop. Most satisfactory results also continued to be reported last year* from Lodge Farm in the cultivation of potatoes, cabbages, beet, mangold-wurtzel, and other green crops. The Lodge Farm experience, confining it to its growth of grass, may be said to represent a return of 5s. annually from every individual contributing to the sewage used upon it. Supposing the water supply to be over 30 gallons a head, each person will make 50 tons of sewage annually, corresponding to the production of 10 cwt. of grass, worth 10s. a ton.

The experience here, combined with the tabular statement, page , of the analyses of the clear effluent water, pouring from the farm into the neighbouring brook, is sufficiently encouraging for those who are

interested in the cleanliness of both town and river.

We turn now to a large number of instances of irrigation, where the object has been not only to make a profit but to abate a nuisance. Such are the cases of Aldershot, Banbury, Bedford, Croydon, Norwood, Rugby, Warwick, and Worthing.

3. Aldershot Farm.—The case of Aldershot may be placed first upon the list, because here land has been taken for irrigation, not by the authorities, but by a tenant who, bound no doubt to cleanse the sewage of the camp, yet has for his principal object the extraction of a profit from its use, so that he comes more nearly under the same class with the example last named. Mr. Blackburn here receives the drainage of the North and South Camps, i.e., of a population which is fairly represented by a constant number of 7,000 adults. During winter the drainage of this population, amounting to about 700 tons a day throughout the year, is poured in succession over the several fields of the farm, 80 acres in all, one half being in one and two years old Italian ryegrass, and the other half growing crops of potatoes, mangold-wurtzel, cabbages, &c. During the summer the crops upon the arable half take but little of the drainage of the camp, and it is then poured almost exclusively over the Italian ryegrass land. The soil is the poor sand of the Aldershot waste (consisting of almost pure silica), prepared at considerable expense by levelling and deep grubbing, so as both to provide a uniform slope over which the water may flow evenly, and to remove the ferruginous "pan" which everywhere underlies the soil, and would hinder the even distribution of fertilizing matter downwards. A few deep drains serve to draw off the water which sinks beneath the surface.

The first set of samples A., taken in the afternoon of July 16th, 1869, were, (1) from the reservoir into which the camp drainage flows; (2) from the lower carrier or surface drain of a plot of about an acre in extent, over a width of 50 yards of which it had slowly trickled amidst a growing crop of ryegrass; and (3) from the mouth of a drain the only effluent water from the farm. The sewage was unusually offensive at the time, and the effluent water was apparently clear. The difference of composition indicated by the analyses shows that while the water (1) just poured on had, in its first passage over a surface already richly manured, apparently dissolved and carried with it some of the stuff left by a previous dressing, so that after its 50 yards of passage the sample (2) exhibited in its composition an even larger quantity of filthy matter in solution, yet in the end, and after passing through the land, the organic nitrogen and ammonia as shown in sample (3) had to a large extent disappeared.

39260.

^{*} Notes upon the Sewage Cultivation of Lodge Farm, Barking, by the Hon. H. W. Petre.—(Effingham Wilson, Royal Exchange).

RAW AND EFFLUENT SEWAGE.—ALDERSHOT FARM.
RESULTS OF ANALYSIS expressed in Parts per 100,000.

only be said	d Matters in Solution.	. Carbon.	Nitrogen.	n as Nitrites Nitrates.	Ammonia.	Combined.	Chlorine.	Suspe	pended Matters.		
de manally, 10s a tot. 10 page . et	Solid M Solu	Organic	Organic	Nitrogen and N	Атп	Total C	Chl	Mineral.	Organic	Total.	
A. \begin{cases} 1. July 16/69 \\ 2. \\ 3. \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\	46.6 47.4 18.6	5.878 7.936 665	2:052 3:053 :132	0 0 1.152	9:025 8:267 486	9:484 9:861 1:684	9.45 9.00 3.55	6.72 1.76 .68	14:28 6:84 :66	21:00 8:60 1:34	
B. {1. May 1/68 2. " "	93:40 39:00	16:335 :504	2:694 :129	1.312	13:054 :622	13:444 1:953	=	5.30	17:90	23:20 :40	

The set of samples marked B. in the above table were taken on May 1st. 1868. No. 1 was raw sewage, as it passed upon the land, and No. 2 was effluent water from the drain. They indicate an immense reduction in the quantity of all the dissolved polluting materials in sewage by the process of irrigation. The organic carbon was reduced from 16.3 to .5, and the organic nitrogen from 2.7 to .1 in 100,000 parts. The above figures show, however, that the whole of this amelioration must not be attributed to the purifying action of the soil and crop, for the solid matters in solution in both series, and the chlorine in series A., point unmistakeably to the admixture of the effluent water with about double its volume of unpolluted spring or subsoil water. All that can be safely inferred from the above analytical results is, that in the series A. the organic impurities, soluble and insoluble, were reduced to less than one-fifth, and in series B. to one-eighteenth, the original sewage in the latter case being much stronger than in the former. Even after this deduction has been made from the observed effect, the result is a very satisfactory one.

In this case the extreme natural poverty of the soil does not seem to have been a hindrance to the efficiency of the process of cleansing by irrigation. The farm, well managed, is covered with a capital plant of vigorous growth, to be fed by the filthy water, which accordingly is greatly purified by the process. Mr. Blackburn lets portions of his land to neighbouring cowkeepers, at 201. an acre; and here the grass, cut in regular rotation, was in the heat of July, when everything was withered and burned up around it, a perfect oasis of luxuriant green, yielding annually its four or five crops of eight to ten tons a piece per acre. The Aldershot farm appears the more satisfactory as an example of the sewage nuisance abated, at the same time that its filthy contents are converted into valuable produce, from the circumstance that a previous attempt to deal with it by subsidence and filtration tanks had been a complete failure.

Supposing 40 acres here to yield 20*l*. an acre, and other 40 acres to owe one-half of their crops, or 10*l*. an acre, to the winter sewaging, we have here a return of 1,200*l*. from the waste of 7,000 adults, or 3*s*. 4*d*. per head per annum.

4. Carlisle.—The sewage of Carlisle finds its way, for the most part, into the Eden through the main sewer beneath the alluvial pasture land bordering the river. It is delivered in the middle of the river channel through a submerged iron pipe. On the town side of the meadow a pumping station has been erected by Mr. McDougal, to whom the land (about 100 acres) is let; and a quantity is thus

lifted, deodorized by treatment with carbolic acid, and distributed over the land by means of light portable iron troughs. These are shifted from place to place by the man in charge, and in this way the sewage pours on at one place after another, distributing itself with more or less regularity, according to the natural surface of the land, which has not been levelled,—flowing here, ponding there, soaking everywhere. There is an obvious increase in this way to the natural fertility of the land; and a larger quantity of stock is kept upon it than it would naturally maintain. There is no surface drainage from the land to the river, and our sample for analysis was taken by digging a hole three feet deep, close to where the sewage had been lying on the previous day, and taking the water to which we at length came.

RAW AND PURIFIED SEWAGE.—CARLISLE.
RESULTS OF ANALYSIS expressed in Parts per 100,000.

Description.	Solid Matters Solution.	Carbon.	Organic Nitrogen.	mmonia.	n as Nitrates Nitrites.	Combined trogen.	Chlorine.	Susper	ided Matt	ers.
	Total Soli in Soli Organic	Organic	пш	Nitrogen and N	Total C Nitr	Chlo	Mineral.	Organic.	Total	
Raw sewage, Sept. 23, 1868.	44.9	2.673	.505	1.912	0	2.080	-	5.24	4.64	9.88
Water from hole dug in irrigated meadow, Sept. 23, 1868.	28.8	.591	204	.025	0	•225	3.18	0	0	0

As there is properly speaking no effluent water from this meadow, the whole of the sewage applied being absorbed by the sandy soil and there being no drain outlet, the result is not quite so trustworthy as in other cases; nevertheless we may fairly conclude from it that the soakage from the irrigated land into the neighbouring river is effectually purified.

5. Penrith.—Here the drainage of a town of 8,000 people, only partly provided with waterclosets, is received on 80 acres of good meadow land near the Eamont. A little more has been done here than at Carlisle to distribute the water by means of permanent carriers; but the treatment is otherwise the same, and the result is very similar. A very large stock of cattle and sheep is kept upon the land to graze down the abundant growth of grass which is obtained.

RAW AND EFFLUENT SEWAGE.—PENRITH.
RESULTS OF ANALYSIS expressed in Parts per 100,000.

Description.	id Matters ution.	Carbon.	Nitrogen.	Ammonia.	m as Nitrates Nitrites.	Total combined Nitrogen.	Chlorine.	Susper	nded Matt	ters.
Description	Total Solid in Soluti	Organic	Organic	Апп	Nitrogen: and N	Total c	Chlo	Mineral.	Organic.	Total.
Raw sewage, Sept. 24, 1868.	53.2	5.111	1.899	10.392	0	10.460	-	5.88	11.88	17.76
Effluent water from drain as it enters the Eamont, Sept. 24, 1868.	21.9	*320	*108	'001	0	.169	2.68	0	0	0

Here, as at Carlisle, the whole of the sewage is absorbed into a porous sandy soil, but the drain passing beneath the irrigated land, and alluded to in the table, pours out a considerable and clear stream into the *Eamont*, and from this the sample of effluent water whose analysis is given was taken. The comparatively small proportions of solid matters in solution, and especially of chlorine in the effluent water, point to the admixture of unpolluted subsoil water with the true effluent sewage, and the figures in the above table indicate that no less than three volumes of this pure subsoil water mingled with one volume of the real effluent sewage. But even after making this deduction from the purifying effect of the irrigation the result is still satisfactory. The whole of the suspended impurity was removed whilst a reduction of the organic matter in solution was effected to the extent of 75 per cent. of organic carbon and 77.2 per cent. of organic nitrogen.

6. Rugby.—At Rugby, a town of more than 8,000 inhabitants, the Board of Health have taken a lease of 65 acres of land for a term of 31 years, at a rental which, with rates and taxes, amounts to 41. 10s. per acre; and, confident in the powers of their somewhat gravelly soil (lying upon a clay subsoil) to cleanse their town drainage, and to convert it into valuable produce, they have laid out nearly 5,0001. on the works required for the distribution of the sewage water over it. An intercepting sewer takes the drainage of all the upper part of the town by natural gravitation to the top of the farm; and, by a deep and costly tunnel drain, the waste of all the lower part of the town is made to flow (along with the tail water of the upper fields) over about 16 acres of

the lower part of the farm.

The quantity of sewage at command is about 900 tons a day, or nearly 4,000 tons per annum for every acre of the farm. The land has been in hand for only one year, and much of it was sown with Italian ryegrass for the first time in the spring of 1869, so that the best results can hardly have been yet realized. The third and fourth cuttings (both heavy crops) were, however, ready in the following month of July, and a sale was being obtained for the grass at 8s. a ton upon the land. A considerable portion had been let at 10l. an acre; and the 16 acres at the lower end of the farm had supported throughout the spring and summer 54 head of cattle, consuming at least four tons of its grass produce daily; and a considerable extent of the crop on these 16 acres had been made into hay. In illustration of the cleansing power of land and plant at Rugby, three samples taken about mid-day, July 13, have been analysed; No. 1 was raw sewage taken from the hydrant as it poured over the top of the farm; No. 2 was the same sewage taken at the foot of 11 acre of land in Italian ryegrass over which it had passed 150 yards down the slope. Thence it flowed along a surface channel about 300 yards to another acre of Italian ryegrass; and No. 3 was taken at the foot of this grass plot about 80 yards from the carrier which supplied it. The following table gives the results :-

RAW AND EFFLUENT SEWAGE.—RUGBY.
RESULTS OF ANALYSIS expressed in Parts per 100,000.

Rugby Samples.	d Matters Solution, mic Carbon.		ic Nitrogen.		Ammonia.	Combined trogen.	Chlorine.	Suspe	nded Mat	Matters.	
	Solid in Se	Organic	Organic	Nitrogen and N	Ашп	Total C	СЪ	Mineral	Organic.	Total.	
1. July 13/69 - 2. " " - 3. " " -	52.60 55.70 68.20	5:505 2:547 1:526	2·322 ·506 ·164	.000 .000 .000	7:276 2:772 :420	8:314 2:789 :510	8·25 10·20 10·50	3°48 °72 °88	8:96 :28 :36	12:44 1:00 1:24	

Here then is a case in which the nuisance of the sewage is entirely abated, and so much produce realized as to make it probable that the remedy, which has been here an expensive one, will yet prove profitable,

The following account of the experience of 1869 at this place has been communicated to us by Mr. T. M. Wratislaw, Clerk of the

Local Board of Health :-

"The gross produce of the sewage-farm, for the year ending 31st December, has been 544l. 16s. 8d. The total expenses, so far as the payments (including wages for the year) have been made, stand at 458l. 8s. 5d., and I do not apprehend much addition."

"I am not aware of the actual number of persons contributing to the

sewage utilized, but should estimate 7,800."

 Banbury.—A population of about 11,000 people here drain into tanks, from which, through a 12-inch pipe, the sewage is driven by steam power a mile or more to the upper end of a farm of 136 acres, a lease of which has been taken for 21 years, at a rent of 4l. 10s. per acre. The quantity thus applied amounts to about 300,000 gallons a day, or about 4,000 tons per acre per annum over that part of the farm which is under irrigation. The sewage settles to some extent in the tanks from which the pumps lift it, and both mud and scum are here taken from it, and mixed with the street sweepings and other scavenging refuse of the town; and 2,000 tons of this compost were sold last year, for which a sum of about 100l. was received at the depôt, the material being loaded by the purchaser into barges on the canal close by. The liquid part, delivered on the highest part of the farm, having about 17 feet of fall before it reaches the river Cherwell, flows twice or thrice over successive fields before it is finally dismissed, and the extreme filthiness of the river formerly complained of is now satisfactorily abated.

The following samples illustrate the cleansing process which the sewage thus undergoes. The series A. was taken at our visit to Banbury on October 17th, 1868; No. 1 being the sewage which had accumulated in the pumping well from 10 a.m. to 2 p.m., and No. 2 the effluent water as it left the meadows at 1 p.m. The series B. was collected on July 14th, 1869. No. 1 was taken at 10 a.m. and at noon, being raw sewage taken partly from the upper carrier on the farm and partly from the pump well. No. 2 was the water after it had passed over 200 yards in length, and four acres in extent of a field of Italian ryegrass, at the rate of, probably, 70 tens an hour. No. 3 was taken after this tail water had travelled half a mile in an open carrier, and then distributed itself over a flat meadow of permanent grass land. It was passing from the underground drain of the field in question, and represents the sewage as it reached the river. The farm is for the most part a very stiff soil, and the greater part of it is still in old grass land, and neither circumstance is favourable to its efficiency; the former because the soil tends to crack in dry weather, thus given the sewage direct access to underground drains, and thence to the river before it has been properly acted upon by the soil; and the latter because the surface of the land not being specially and evenly laid out for irrigation, the water tends to collect in shallow ponds or puddles, to the injury of the produce, without being itself materially cleansed. The accounts given of the produce of the land are satisfactory, and it is believed that the farm will soon repay rent, and costs, and loan, so that the nuisance hitherto created by the town will be ultimately abated without any serious permanent charge upon the inhabitants.

The produce of Italian ryegrass and of the meadow land is sold by auction as the successive cuttings are ready for the scythe; and prices varying from 3l. to 5l. an acre have been obtained per cutting. The following are the results of our analyses:—

RAW AND EFFLUENT SEWAGE.—BANBURY. RESULTS OF ANALYSIS expressed in Parts per 100,000.

Banbury Samples.	olid Matters Solution.	c Carbon.	Nitrogen.	in Nitrites litrates.	Ammonia.	Combined trogen.	Chlorine,	Susper	ided Mat	ters.
Banoury Samples	Total Solid in Solu	Organic	Organic	Nitrogen i and Ni	Ашп	Total C Nitr	Chlo	Mineral.	Organic.	Total.
Λ. {1. Oct. 17/68 - 2. " " -	111.5 70.9 92.4 66.5 51.8	6:246 2:241 8:269 2:670 1:008	2·764 ·549 2·386 1·127 ·207	.000 .000 .000 .000	13:590 2:282 6:702 3:112 :725	13:956 2:428 7:905 3:690 1:472	13:25 8:75 6:75 5:50	3:90 :52 9:56 1:68 :94	8:62 :84 20:12 3:84 :80	12:52 1:36 29:68 5:52 1:74

The Banbury sewage, owing to a deficient water supply, is sometimes much above the average strength, and consequently its efficient cleansing is then a more difficult operation; nevertheless the above results are by no means unsatisfactory; and they are improving, both as regards the cleanness of the effluent water and the returns from the use of it,

The following account of receipts and expenses, in respect of the sewage-farm here, for the year ending Lady-day 1869, has been supplied to us by Mr. T. Pain, the town clerk:—

Receipts.						
Market and the changing party and and the				£	s.	d.
Amount realised from sale of ryegrass -	-		-	561	16	6
" mowing grass -	-		-	347	18	2
" oats			-	198	0	0
" " aftermath -	-		-	166	11	8
Right of shooting over farm, and sundries	-		-	6	1	6
						_
				1,280	7	10
Payments.						
	£	8.	d.			
Mr. Tomline, a year's rent less property tax	605	3	1			
Rates and taxes for the year	57	4	7			
Coals for engine	111	16	0			
Labour expended in cultivation of farm -	216	2	0			
Seeds, implements, &c	82	0	6			
Manager's salary	45	0	0			
Auctioneer's expenses of sale, including com-						
mission	73	6	11			
solet act a month by the stall a mil too takes		-81	-11	1,190	13	1
Profit on farm -	-		e di	89	14	9
				-		
Instalment of principal and interest in respect	of le	oan	of			
4,000l. borrowed to carry out the irrigation	work	2		250	0	0

The produce of the summer of 1869, when we were over the farm, bid fair to at least maintain the satisfactory character of the account on

the previous page.

 Warwick, a town of 11,000 inhabitants, occupying 2,400 houses, of which upwards of 2,000 are connected with the sewers, has lately poured its sewage over a clay-land farm of 100 acres, about a mile away. The quantity thus pumped, and which formerly fouled the Avon, amounts to about 600,000 gallons a day, double the water supply of the town, or nearly 1,000,000 tons a year, corresponding to 10,000 tons per acre annually. A large quantity of very dilute drainage water thus flows over a very stiff and therefore less appropriate soil. What the result is, as regards its cleansing powers, appears from the following analyses: -No. 1 is a sample of raw sewage taken from the receiving tank by the pump at 4 p.m. on July 14th, 1869. No. 2 is the sewage after flowing over seven acres of recently-cut Italian ryegrass taken at the foot of a field of red clay soil down which it had flowed probably 200 yards at the rate of 80 or 100 tons an hour. No. 3 is the same water after a second cleansing over three acres of Italian ryegrass in a field of similar soil. The results here may be taken to represent the powers of plant growth and of mere surface action of clay soil, for none of the water apparently had sunk into the land or been absorbed. Here the filth in about 150 tons of dilute sewage had been satisfactorily reduced by probably two hours' irrigation treatment, under what must be pronounced unfavourable circumstances. Moreover the sewage, and consequently the residual impurities had obviously undergone concentration by evaporation, as is seen from the continuous increase of chlorine in the successive samples.

RAW AND EFFLUENT SEWAGE.—WARWICK.

RESULTS OF ANALYSIS expressed in Parts per 100,000.

		id Matters lution.	carbon.	Nitrogen.	as Nitrites litrates.	Ammonia.	Total Combined Nitrogen.	Chlorine.	Susper	nded Mat	ters.
		Total Solid in Soluti	Organie	Organic	Nitrogen as Nitri and Nitrates.	Аши	Total C Nitr	Chl	Mineral.	Organie.	Total.
1. July 14/69 -		66.90	5.133	1.680	.000	2.439	3.689	6:30	2.64	3.36	6.00
2. " -		69.70	2.727	.575	.000	1.705	1.979	7.70	3.30	.78	4.08
3. " -		66.10	1.454	175	·137	.839	1.003	8.15	Trace.	Trace.	Trace.

The farm has been in hand for two years. Pumping commenced only in the autumn of 1868, and it was not continuously carried on until the following year. This, together with the difficulty which the low and flat part of the farm presents to the proper drainage from it of so large a quantity of water, has hitherto delayed the satisfactory financial result which is looked for. Nevertheless the nuisance is sufficiently abated, and large crops of Italian ryegrass have been obtained, for which a ready sale at 10s. and 12s. a ton upon the ground has latterly been obtained. The farm must, we understand, pay at least 1,600l. a a year to replace the costs which the town has already incurred and still bears in respect of rent, pumping, and works.

9. Worthing, containing about 8,000 inhabitants, has hitherto fouled a stream running into the sea two miles to the eastward of it. The town drainage now runs to a tank from which it may flow as heretofore, and still does run during the night, so that a good deal of very offensive filth even now lodges in the bed of the stream. During the day it is pumped and flows upon the land of the Worthing Land Improvement Company, who have about 100 acres on which to receive it. The soil is a good free loam perfectly well adapted for their purpose, and the natural slopes are quite sufficient for the easy distribution of the water. There are on the lower part of the farm upwards of 40 acres of an alluvial flat of natural grass on which the effluent drainage of the higher arable land received before it leaves the farm. Mr. W. Hugh Dennett, solicitor to the Worthing Land Improvement Company, has communicated to us the following account of the gross receipts and working expenses of the sewage-farm for the year 1869:—

"In the above expenditure is included a sum of 51l. 13s. 11d. for a 'Level' rate, made for the protection of various lands from the encroachments of the sea, which is a special and not an ordinary parochial rate. There is also included a sum of 50l. for the rent of $8\frac{1}{2}$ acres of the land referred to and comprised in the area stated below. A steam engine on the farm was used for about three months at a cost of about 25l.

"The population of Worthing is about 7,600.

"The engineer reports that the average volume of sewage pumped each day of 24 hours to the farm is about 480,000 gallons (of which about 130,000 gallons are spring or surface water). In addition to this, about 80,000 gallons of water per day flow into the *Treville* stream.

"The extent over which the sewage flows is about 83 acres.

"The whole farm consists of about 96 acres, a portion of which is

not sewaged; 42 acres are pasture land.

"I cannot say that the pollution has altogether ceased, because although it is stated that the 80,000 gallons of sewage flowing into the stream per day is top water, yet it flows from the sewage-well, and must be necessarily polluted with sewage. However, the actual pumping of the sewage into the stream ceased some months ago, and the communication has been removed. The Local Board of Health have also cleansed the stream, and there is reason to believe that all the sewage pumped goes upon the land, though materially diluted by spring and surface water."

Our samples of the Worthing sewage were taken on July 15th, 1869, about 3 p.m., (1) from the head carrier, (2) from a carrier 150 yards lower down at the foot of a field of Italian ryegrass, over three or four acres of which the sewage was passing at about the rate of 60 tons an hour, and (3) from the effluent stream at the foot of the farm after it had further spread over two or three acres of the flat alluvial grass plot by the river. The following results were obtained on alalysis:—

RAW AND EFFLUENT SEWAGE.—WORTHING.

RESULTS OF ANALYSIS expressed in Parts per 100,000.

1000	l Solid Matters n Solution.		Carbon.	Organic Nitrogen.	n in Nitrites Nitrates.	Ammonia.	Combined trogen.	Chlorine.	Suspen	ded Matt	ers.
		Total Sol in So	Organic	Organic	Nitrogenin and Nitr	Ашп	Total Combin Nitrogen.	Chl	Mineral.	Organic.	Total.
1. July 15/69 2. " " 3. " "		57.6 58.8 59.8	2·312 1·164 1·324	2·021 ·226 ·334	·000 1·105 ·248	3·717 ·801 ·591	5.082 1.991 1.069	10.75 11.40 11.00	1.86 Trace.	4.74 Trace,	6.60 Trace.

The sewage, which was somewhat weak at the time of our visit, was sufficiently cleaned by passing over the first plot; indeed it was cleaner than another sample from the effluent stream which was probably carrying into the river the purified water from the stronger morning sewage. Close proximity to the sea affects the proportion of common salt in the Worthing sewage. The proportion of chlorine in all the samples is much higher than the strength of the sewage would lead us to anticipate. Some of the streets are watered with sea water.

10. Bedford.—At Bedford, which contains about 15,000 inhabitants, large sums have been recently laid out under the direction of Mr. John Lawson, C.E., on both its water supply and its drainage system. The sewers here receive not only the fouled water-supply of the town, together with a certain proportion of the rainfall on its houses and yards, but an immense quantity of land-water from the gravel site on which the town is built. Thus, though the water-supply does not much exceed 150,000 gallons daily, the quantity of drainage which reaches the pumping station, about a mile below the town, is as much as 500,000 or 600,000 gallons daily. Each of the two 12-horse power engines here stationed is, however, capable of lifting 2,000 gallons a minute to a height of 20 feet, so that either of them can master the ordinary dryweather sewage of the place.

During the night the comparatively pure water which then drains away is stored in the outfall sewer and tank at the pumping station. In the daytime it is delivered by an 18-inch iron pipe to the irrigated land 400 or 500 yards off, flowing thence into a small circular tank, and afterwards by two 15-inch pipes, along either side of the nearly flat land which has been laid out in transverse beds for its reception. These beds are about 70 feet wide on the side, with a fall of 8 or 10 inches from the central carrier to the midway furrow. The carriers are either 5-inch pipe tiles with open longitudinal slit, or 8-inch half round tiles; and a

fall of about 1 in from 300 to 800 is given to them.

The beds were sown in 1868 with Italian ryegrass, and have yielded heavy crops. Up to the middle of July three crops had been cut off 20 acres, besides one crop off 15 acres sown in 1869, and the sales amounted to nearly 330l. A much larger area of land is about to be taken in hand for irrigation purposes by the Corporation. The extent at present rented is about 50 acres, but a farm of about 200 acres will ultimately be under their management. The cost of pumping, which amounts to 4l. per acre of the land now irrigated, will then be reduced

to a rentcharge of about 20s. an acre, which will be more easily repaid. And as the houses become more generally connected with the sewers, both the need of the greater area, and the produce derived from so large a supply of fertilizing matter, will increase. At present, as the following analyses show, the sewage is very weak, but the cleansing process is satisfactory. The samples of raw sewage (1, in the following table) were taken from the above-mentioned tank upon the farm; the effluent water (2) was taken from a ditch, which is dry except when the sewage is pouring on the land, but which was then flowing rapidly, being supplied from the subsoil drainage of the field which was being irrigated.

Samples were taken by us on three occasions. Series A. was collected on Sept. 10th, 1868, series B. on Oct. 10th, 1868, and series C. on July 24th, 1869.

RAW AND EFFLUENT SEWAGE.—BEDFORD.

RESULTS OF ANALYSIS expressed in Parts per 100,000.

Times of Collection.	Solid Matters Solution.		Nitrogen.	n in Nitrites Nitrates.	Ammonia.	Combined brogen.	Chlorine.	Susper	ided Matt	ers.
San habit falsons schole	Total Sol in So	Organic	Organic	Nitrogen and N	Λшл	Total Combin Nitrogen.	Chl	Mineral.	Organic.	Total.
A. { 1., 4.45 P.M	74·8 76·8	2:732 :575	.668 .163	.000 .398	2:700 :023	2:891 :580	7.15	13.26	13.14	26:40
B. {1., 12.30 P.M. 2., 1.30 ,, .	79.4 78.3	1:877 :742	1:304 :381	.000	4:300 :010	4.845 .989	7.25	5.28	5.50	11:08
C. {1., 4.50 P.M	76°1 81°7	2:256 :558	1:301 :034	.000 .505	3:100	3°854 '617	10.90 8.12	8.16	13.68	21.84

The undertaking here is thus shown to be sufficient as a sanitary agency, and its ultimate profitableness appears probable from the character of the crops we saw growing on the land. The Italian ryegrass must have weighed 12 to 14 tons per acre. The mangold-wurtzel and kohl-rabi were tolerably promising. The prices obtained by auction for the former crop were improving at the successive sales, as the prejudice against sewage-grown cattle food was dying out. The difficulties connected with the even distribution of the liquid will also diminish every year as the settlement of the moved land enables the necessary corrections of the surface to be made, so as to ensure a more uniform flow of water over it. The following report for 1869 has been furnished by Mr. John Lawson, C.E.:—

"The land leased by the Corporation from the Duke of Bedford contains 54a. 3r. 7p. Of this area 47 acres have been irrigated by sewage.

"Two fields, containing about 22 acres, were sown with Italian ryegrass in 1868, and the produce sold from this land in the year 1869 was about 420*l*.

Of the remaining portion of the land irrigated 15a. 2r. were sown with Italian ryegrass in the spring of 1869, and the remainder with mangold-wurtzel and other root crops. The sales from this portion amount to about 227l. 10s. 4d., making a total of 647l. 10s. 4d.

11	No train their such such							£	s.	d.
**	Produce in the year	1869	as sol	d by a	uction	1	-	647	10	4
					£	S.	d.			
	Rent, 55 acres at 41	. 10s		-	247	10	0			
	Auctioneers commis	ssion	-	-	33	8	6			
	Printing -	-	-	-	22	9	0			
	Seeds and plants	_	-	-	33	19	0			
	Labour, including s	alary	of mar	nager	213	4	0			
	Taxes -		-	-	17	14	8			
	Sundry expenses	-	-	-	11	19	0			
							_	580	4	2
								£67	6	2 "
								December of	-	-

 Norwood. The history of the facts connected with sewage irrigagation at Norwood and at Croydon has been sufficiently prolonged to make it now thoroughly trustworthy and instructive. At the former place about 30 acres of low-lying clay land, with sufficient slope for natural surface drainage, have been well laid out for irrigation by Mr. Baldwin Latham, C.E. The drainage of about 4,000 people is received into a subsidence tank at the upper end, and thence flows along surface carriers, arranged both nearly in contour and down the slope. The fall in these carriers varies from 1 in 100 to 1 in 1,000, and the water stopped at intervals in their course flows over their edges, and so finds its way over the surface of the land. Plots varying in size from one to three acres are irrigated at once, according to the abundance of the supply, which, especially in summer time, when it is most wanted, is barely sufficient for the proper irrigation of the land. Nevertheless, very good crops of Italian ryegrass are cut five or six times a year; and a ready sale is obtained for the produce, at prices varying from 9d. to 1s. 3d. per rod, or 6l. to 10l. per acre, and the Croydon Board of Health have in this way obtained a revenue of 22l, per acre during nine months of 1868, and 25l. per acre in 1869, which spread over the population to whose drainage it is due, amounts to about 3s. 9d. per head per annum. Mr. Baldwin Latham has furnished the following satisfactory report of the past year's experience :s. d.

" The total amount received for the produce in the 741 0 6 year was The expenditure has been as follows:— £ d. S. Rent after deducting income tax -292 16 Wages for cutting produce, attending to the distribution of the sewage, re-digging and otherwise 196 preparing the land for crops 2 17 63 15 3 Taxes, rates, and tithes 2 3 0 Printing -20 16 Sundry bills

Balance - £148 5 9

592 14

"The area under irrigation is 30 acres. Previous to the Local Board becoming the tenants of the land, the rent paid was 18s. per acre. The adjoining agricultural land is let at less than 1l. per acre rent. The average population draining to this area during the last year has been about 4,000. During the last month or two we have made provision to bring in a much larger area to this outfall, and in order to make provision for the increased population the Board has taken a sufficient area of land adjoining the present irrigation works at a rent of 10l. per acre. This will nearly double the existing area under sewage. It may also be interesting to the Commissioners to know that when the existing works at South Norwood were completed they were let to a tenant for three years, at a rent of 2001. per annum. The Board at this time paid the cost of distributing the sewage, so that as long as the works were let, there was a clear loss to the Board of 180l. per annum, but since they have taken them into their own hands a profit has accrued as will be seen from the foregoing figures."

A series of samples of raw sewage and effluent water has been taken

from this land, giving the following results :-

RAW AND EFFLUENT SEWAGE.—Norwood.

RESULTS of ANALYSIS expressed in Parts per 100,000.

Suprage continu	town out in party			Ni-	and	a.	Com- Ni- n.		Suspe	nded M	atters.
Date of Sam	ple.	Total solid Matter in Solution.	Organic Car- bon.	Organic	Nitrogen Nitrites Nitrates	Ammonia	Total C bined trogen	Chlorine.	Mineral.	Organic.	Total.
February 25, 1869 March 12, 1869 March 25, 1869	Tail Head Tail Head	91.70 73.20 117.80 83.10 75.30 97.80	1:577 5:407 1:294 3:275	*699 *391 2*294 *184 1*765 *189	*000 *423 *000 *381 *000 *462	2:030 :988 8:970 :965 7:097 :342	2:371 1:628 9:681 1:360 7:610 :933	8:60 5:70 8:87 8:87 8:50 7:50	3.68 Trace. 4.08 Trace. 5.88 Trace.	6°36 Trace. 14°96 Trace. 8°36 Trace.	10.04 Trace. 19.04 Trace. 14.24 Trace.

The relative cleansing which sewage undergoes by employment for irrigation at different seasons of the year has not yet received any sufficient elucidation. The proximity of Norwood and Croydon to London afforded a favourable opportunity of submitting the effluent water from the two sewage-farms to frequent investigation at all seasons of the year. Arrangements were, therefore, made for the periodical collection of samples for an entire year by our own laboratory man, in order to ascertain how far the efficient cleansing of sewage by this method is affected by the vigour or otherwise of vegetation, and especially whether the process could be relied upon during the winter months when plant life is in a comparatively dormant condition.

The following table contains the results of our periodical analysis of

the effluent water from the sewage-farm at Norwood :-

Effluent Water.—Irrigated Meadows, Norwood. Results of Analysis expressed in Parts per 100,000.

Ammonia. Nitrogen as Nitrogen as Nitrogen as Nitrogen as Nitrogen as Nitrates. Total Combined Nitrogen. Temporany. Temporany. Temporany.	6.032 .000 6.554 8.66 —— 9.93 17.68 16.70 34.38 10.08 10.70 —— 9.93 17.68 16.70 34.38 10.08 10.70 34.38 10.70 10.70 10.70 34.38 10.70 10.70 34.38 10.70 11.80 22.90 34.70 34.38 10.29 34.70 34.78 34.70 34.78 34.70 34.78 34.70 34.73 34.70 34.73 34.70 34.
Organic Car. Organic Ni- trogen.	3.972 1.586 1.621 -214 1.516 -214 1.572 1.473 -285 1.280 -108 1.291 -265 1.173 -265 1.173 -265 1.173 -109 1.280 -107 1.602 -221 1.602 -221 1.602 -221 1.603 -221 1.603 -221 1.605 -274 1.605
Total solid in Matters in Solution,	88 88 7 88 88 7 88 88 88 88 88 88 88 88
Description and Date of Collection.	Average composition of the sewage before irrigation Effluent water, September 24, 1868 " " " " " " " " " " " " " " " " " " "
Description	Average composition of the se Effluent water, September 24, 1868 " " " " " 22, " " " 31, " " 31, " " 31, " " 31, " " 31, " 31, " 31, " " 31, " " 31,

These results, extending over an entire year, show that the effluent sewage was, except in a few instances, so far cleansed, even upon this heavy clay soil, as to be admissible into running water without nuisance. Two of these instances are instructive, since they occurred consecutively during and immediately after seven nights' frost, viz., in the samples collected on January 25th and January 28th, 1869. The frost was by no means severe, yet the organic nitrogen rose from '098 to '419 per 100,000 parts of effluent water, showing that the removal of offensive nitrogenous organic matter was partially arrested, and indicating that during a severe winter the purification of sewage upon a non-absorptive clay soil may be seriously interfered with. It is fortunate, however, that the admission of putrescible organic matter into streams during frosty weather is far less objectionable than it is when the temperature is higher, since the organic matter does not render the water offensive so long as a low temperature is maintained.

It is more difficult to account for the emission of exceptionally impure water from the Norwood Farm at other periods of the year, viz., on December 3rd, 1868, and February 25th, April 8th, May 6th and 20th, August 12th and 26th, and September 24th, 1869, but it probably arose, in some cases at least, from unpurified sewage gaining access to the

drains through cracks in the soil.

The hardness of the effluent water was not excessive, although it exceeded considerably that of the water supplied to Norwood. It never contained more than traces of suspended matters.

12. Croydon.—At the Beddington meadows below Croydon, 260 acres of an open soil upon a gravelly subsoil have for the last seven years received the drainage water of from 30,000 to 40,000 people. The water-supply of Croydon and the copious land drainage of the place altogether yield a quantity of sewage equal to at least 3,000,000, somctimes exceeding 5,000,000 gallons daily. This passes through tanks where great pains were formerly taken to remove the solid and floating filth which it carried down, but less attention is now paid to this preliminary process, and the stream flows on very nearly as it leaves the town to the meadows in the occupation of Mr. Marriage, who, paying the rent at which the Board of Health have hired or bought the land, pays also a profit rent of 11. per acre per annum for the use of the sewage. The success of sewage irrigation here as a deodorizing and cleansing process is complete, as the analyses show. There is never any lack of water, the soil is open, and has just slope enough to render easy the distribution of the liquid over it and through it, and there is sufficient fall between the top and bottom of the farm to allow the tail water of the upper fields to be spread a second time over fields below before it drains finally away. Very heavy crops of Italian ryegrass have been grown here. As much as 14 to 16 tons per acre are cut early in the month of May, and four or five cuttings a year are obtained, averaging from 8 to 10 tons each per acre. Mr. Marriage has also successfully used dressings of sewage in the cultivation of mangold wurzel; and when wheat has been grown after sewaged grass, he has irrigated the field with advantage, even so late as the month of July, when the crop has appeared to be flagging and apparently suffering during a drought. Watercresses too have proved here an excellent crop for sewaging, not only from the profit derived from them, but from their cleansing powers upon the dirty liquid. The greater part of the land here irrigated is, however, in grass. That being the only crop which can be continuously watered with advantage, it is necessary to retain the greater part of the farm in grass in order that the enormous quantity of dirty water here passing over the land may be changed from field to field often enough, and cleansed sufficiently before it leaves the land. Latterly, much of the land has been laid down to permanent grasses, which are better adapted for ordinary grazing purposes, and a large herd of feeding cattle have been successfully grazed upon these lands; being moved from field to field as the water drains off them. This was, however, we presume, a temporary arrangement intended to diminish the tenant's costs as the expiry of his lease approaches, and not intended as an example of the best method of converting the fertilizing matter of sewage into valuable produce.

The following results of analysis illustrate the effect of irrigation when carried out upon the porous gravelly soil of the Beddington meadows. It will seen that the sewage as it flows upon the land possesses scarcely half the strength of average London sewage. The effluent water, even in the month of December, was satisfactorily cleansed and contained but mere traces of suspended matters.

RAW AND EFFLUENT SEWAGE.—CROYDON.

RESULTS of ANALYSIS expressed in Parts per 100,000.

a de la constante de la consta	Solid srs in ion.	Car-	N.	13.	as assand	· Ni-		Susper	ided Ma	tters.
Description.	Total S Matter Soluti	Organic bon.	Organic trogen.	Ammonia.	Nitrogen Nitrates Nitrites.	Total C bined trogen	Chlorine.	na l.	Organic.	Total.
Sewage as it flowed upon land, Dec. 23, 1869.	48.0	2.076	.749	2.684	0	2.959	4.39	1.96	6.64	8.60
Effluent water, Dec. 23, 1869	52:3	·795 2·882	1.269	.265	1.164	1:454 3:493	3.70	Trace.	Trace. 10.80	Trace.
Sewage as it flowed upon land, Dec. 30, 1869.	48.0	June	1 209	2.700						
Effluent water, Dec. 39, 1869	45.0	-772	.076	.230	.678	1.190	2.95	Trace.	Trace.	Trace.

The following table contains the results of our periodical analyses of the effluent water from these meadows, extending over an entire year:—

27.58 26.80 30.12 30.12 30.12 30.12 30.45 25.41 26.01 28.41 26.91 24.81 29.93 20.44 Total. Hardness. 4.93 7.70 7.70 7.70 7.70 7.70 6.71 6.15 6.15 6 · 52 7 · 70 7 · 69 7 · 69 7 · 69 11 · 92 10 · 67 17 · 84 10 · 67 17 · 84 8.47 6.49 nent. Perma-21.06 19.10 22.57 22.57 17.50 20.82 20.82 21.13 18.50 21.96 20.24 13.58 19.64 19.61 20.42 $\begin{array}{c} 21.98 \\ 21.04 \\ 18.40 \\ 18.54 \\ 20.05 \\ 21.08 \\ 20.93 \end{array}$ 21.03 . VLET Tempo-4.23 Chlorine. trogon, 3.527 .506 .151 .459 896. 1.502 1.264.836 .335 .946 .472 .354 .361 .117 .378 1-147 .654 690 benid Com-Total 0 0 0. Nitrogen as Nitrates and Nitrites, .353 .589 .210 968. 241 .651 989. .425 .538 .284 .183 000. 301 .325 000 .091 . 201 3.005 900. 548 246 .150 .124 .062 045 .005 800 130 991. 466 165 .125 860. 060. .050 050 800 060. 534 . sinemmA .120 .127 124 690. 186 235 .093 .138 680 160-.077 .122 .129 .083 080 .036 385 1.576 trogen. oingaro. -IN 508 635 605 .605 .644 .801 .766 604 bon. Organic Car-0 45.7 34.5 89.9 37.3 38.8 36.5 33.9 38.1 Solution. 49.0 39.9 40.2 44.7 45.1 38.4 39.1 29.1 32.1 39.1 30. 35. ut Matter Bilos IntoT 1 1 1 1 1 1 1 Average composition of the sewage before irrigation Effluent water, September, 24, 1868 - - after seven nights' frost-1 1 after two nights' frost 1 1 1 1 1 1 1 1 1 Description and Date of Collection. 21, ", 25, 1869, 28, ", : . .. : . 11 = . : 33,55,58 14, "September November December ". February January. October April August March. June 3 May.

RESULTS OF ANALYSIS expressed in Parts per 100,000.

These numerous analyses show that the sewage of Croydon is much more efficiently purified than that of Norwood. Only on one occasion (August 12th, 1869) during the entire year was the effluent water discharged in a somewhat unsatisfactory condition. On all other occasions the organic carbon and nitrogen were present in proportions considerably below those necessary to render the effluent water an offensive addition to a stream at any season of the year. Suspended matters were never present, except in minute quantity. It must be noticed, however, that during the continuance of the seven nights' frost in January 1869, the purification here, as at Norwood, became markedly impaired, the organic nitrogen increasing from '186 part in 100,000, at which it stood before the frost, to '242 part, whilst the assimilation of ammonia by the vegetation was also retarded, as is seen from the increased quantity of ammonia in the effluent water. Unfortunately, the winter of 1868-69 was too mild to permit of this point being satisfactorily tested, and it will therefore be desirable to resume these experiments should there be a longer continuance of frost during the winter of 1869-70. In order to show more clearly the condition of the effluent water from the Norwood and Beddington meadows at different seasons of the year, the following table has been prepared :-

Influence of Season upon the Purification of Sewage by Irrigation Results of Analysis expressed in Parts per 100,000.

Average composition of effluent Sewage Water.			Total Solid Matters in Solution.	Organic Carbon.	Organic Nitro- gen.	Am- monia.	Nitrogen as Nitrates and Nitrites.	Total Com- bined Nitro- gen.	Chlo- rine.	
Spring:										
Norwood	-	-	-	88.1	1.200	.303	.816	*220	1.194	8:37
Croydon	-	-	-	35.4	*594	*104	.072	*225	*388	2.35
Summer:				Same I		100000	l'annual de			
Norwood		-	-	88.6	1.883	.315	*462	*657	1.361	11.03
Croydon			-	35.4	:607	.126	.069	*155	.300	2.57
Autumn:										
Norwood		-	-	87.0	1.349	.203	*835	.734	1.629	8:94
Croydon			-	43.1	.690	.138	*185	*589	.792	3.20
Winter:			1000	127.02		7233		****		
Norwood				87.0	1.271	.273	*876	*313	1.255	7:71
Oroydon				40.6	.612	145	.204	*533	.846	2.72
After sever	dav	s'fro	st:	0.500	1				010	- 1-
Norwood	-			88.8	1:356	.413	1.145	*156	1.534	8.84
Croydon			-	45.6	.591	.239	.371	*448	.992	2.88

It will be seen from the above table that the total solid matters in solution are remarkably uniform at all seasons; but in estimating the degree of purification effected at different seasons on the two farms, it is necessary to bear in mind the relative strength of the sewage employed in each season, since the purity of the effluent water is considerably affected by the proportion of polluting ingredients in the original sewage; in other words by the strength of that sewage. The strength of sewage is approximately given by the proportion of chlorine which it contains. Estimated by this standard the sewage of Norwood was strongest in summer, whilst the organic elements in the effluent water were also present in largest proportion during the same season. In winter, when the sewage was weakest, the effluent water was purest. At the Croydon farm, on the other hand, the sewage was strongest in autumn and winter, and the effluent water was also less pure in those seasons. In summer, when the sewage was weaker, the effluent water was also purer, whilst in spring, with a still more dilute sewage, the

water leaving the farm attained its highest degree of purity. It follows therefore that the cleansing of sewage is, in the absence of actual frost, less dependent upon season than upon the quality of the sewage itself. It is, however, far otherwise as regards the inorganic (and consequently non-polluting) fertilising constituents,—ammonia, nitrates, and nitrites. These compounds are, as might be expected, removed with greater avidity by vegetation in spring and summer than in autumn and winter. This is clearly seen from the following table, which shows the amount of nitrogen in these three forms left in 100,000 parts of the effluent waters in each of the four seasons, especially if the varying strength of the sewage above mentioned be taken into consideration:—

NITROGEN as NITRATES, NITRITES, and AMMONIA IN EFFLUENT SEWAGE.

ossalt geografie	inter to to to		Telser i	Spring.	Summer.	Autumn.	Winter.
Norwood - Croydon -		2	ufo i	·892 ·284	1:026 :212	1:422 :741	1.011

Note.—Details of the Croydon Sewage-Farms obtained 26th July 1876.

District in which the Lands are situate. —	Area in Statute Acres.			
	Irrigated.	Not irrigated.		
South Norwood, leased at 10l. 0s. 0d. per acre rental.	55	5		
Beddington Farm, leased at 10l. 0s. 0d. per acre rental.	392	63		
	447	68		

ABSTRACT.

Acres irrigated - Do. not irrigated	rital	en said l	arl a	447 68
Charles and the same and	The state of	grang s	pill y	
Total area	-	- 15	-	515

515 acres of land at per acre rent 10l. = 5,150l.

Population of the districts, about 56,000.

Annual rateable value of the districts, about 275,000l.

Dry-weather flow of sewage used per day, about 3,500,000 gallons.

Storm-water flow, about 15,000,000 gallons.

N.B.—The rental paid for the land for ordinary agricultural purposes was from 26s, to 30s, per acre.

The crops grown are Italian ryegrass, mangold wurzle, cabbages, and other

vegetables. The gross annual income has been about 8,000l.

The annual loss or costs in working the farms has been about 2,750l., exclusive of the interest on the expenditure for laying out the farms.

13. Woking.—We refer, in conclusion, to an experiment in sewage irrigation on the slopes of poor sandy soil below the invalid prison at Woking. A population of more than 1,000 adults there receive a watersupply of upwards of 20 gallons a head, equal to about one ton daily to every 10 persons. The whole drainage of the place passes through a tank capable of holding about 1,500 cubic feet, or 40 tons of water; and thence it has hitherto flowed almost entirely to waste, being used, however, in an unsystematic way, to fertilize the grass fields at the foot of the hill. Two acres upon the slope, in four consecutive plots apiece, were laid out in the spring of 1869, so that a tank-full could at any time be poured upon the upper or any other plot of the series, the tail water being directed on any other plot of the series lower down. The four plots of one acre were sown with Italian ryegrass in March, and three crops averaging more than 12 tons each were cut during the following summer, the plant having been repeatedly sewaged during the intervals. The other acre, lying in fallow, was sewaged in the same way, and samples of the effluent water have occasionally been taken both from plots growing ryegrass and from plots without a crop, in the hope that we should ascertain the increased power of a surface covered with a growing crop as compared with one which depended solely on the soil as a filter. The second acre has subsequently been planted with cabbages, potatoes, and mangold-wurtzel, and these crops have received sewage when the plants required. The difficulty of applying the results obtained here to the circumstances of any other case arises from the extreme hollowness and porosity of the Woking soil. A dressing of 40 tons of sewage, poured in three-quarters of an hour from the upper carrier of one of these quarter-acre plots, is, notwithstanding the steepness of the slope, almost all absorbed before it reaches the foot of the plot. It is only when the land is saturated with rain-water, and thus loses its power of absorption, that the sewage-water poured on at top, and conducted over the four plots in succession of the acre then being treated, will reach the bottom of the field. In the interests of the crop it has been therefore necessary to irrigate each plot in succession with raw sewage. The plan has generally been to give each acre so much sewage in the week as to make the result correspond to the allotment of an acre to every 100 persons throughout the year; and in the further prosecution of the experiment here, when the soil shall have become more clogged with root fibre and with sediment, it is hoped that the effect of the whole acre upon a specified quantity of sewage may be realized and observed. The experiment has also to be extended to other places in order that we may learn from it, if possible, the maximum powers of various soils in cleansing sewage, getting results of the same definiteness in regard to irrigation, as our laboratory experiments have already given us with reference to filtration. Our results at Woking are still incomplete, and must be reserved till the issue of a later report: but it may be stated as regards the fertilising power of sewage water thus applied, that Italian ryegrass sown in March on poor Woking sand, yielded between July and October three crops of grass, averaging more than 12 tons per acre each; and that on plots of similar soil the heaviest and most luxuriant growth of savoys, kale, and cabbage has taken place. A bed on which 20 tons of Woking peat had been laid one foot deep and watered in like manner, yielded as abundantly as the rest; and the result is sufficiently encouraging to justify the prosecution of the experiment on a larger scale, and on peat of a less questionable character, in order to ascertain, in the interests of the great Lancashire towns, whether sewage upon a true bog peat will feed succulent vegetable growth as successfully as it is found to do on all other kinds of soil.

The Rivers Pollution Commissioners conclude their remarks on some chemical modes of treating town-sewage as under. Irrigation is the only power of cleansing sewage which has stood the test of experience, and, unless it be extensively adopted, there is but little hope of any

substantial improvement in our sewage-polluted rivers.

Contrast the chemical methods with the efficiency of irrigation as a utiliser of the manure ingredients of town-sewage. All these ingredients are in this case taken to the land; and three-fourths of them in winter, four-fifths or five-sixths of them in summer, are left there for the use of growing plants; the remainder being rendered unoffensive. These manure materials are thus carried, distributed, and buried; and thus, without the costly labour of the dung cart, manure distributor, or plough, they are brought to the very roots they are to feed; and the fertility they accordingly produce is unexampled otherwise in English agricultural experience. The process can be carried on without offence to any but those who go close to the tanks or channels; and it can be conducted, as the experience of many years at Edinburgh and Croydon proves (see Report on Mersey and Ribble basins, Vol. I., p. 90), without injury to health. We have therefore no hesitation in recommending irrigation as the only plan of dealing with the sewage difficulty at present known to us which at once abates a nuisance and turns to profitable account an otherwise valueless material.

INFLUENCE OF SEWAGE IRRIGATION ON HEALTH.

It has often been asserted that sewage irrigation has a detrimental influence on the health of persons living near to or working upon sewage-farms; but nowhere have we found instances of ill-health that are properly attributable to malaria or other causes due to irrigation; and the evidence of Dr. Littlejohn, medical officer to the Board of Supervision in Scotland; Sir Robert Christison, Bart., M.D.; Dr. Ligertwood, staff surgeon; Dr. Alfred Cresswell, and Dr. Alfred Carpenter, given before the Rivers Pollution Commission (see Report, Mersey and Ribble Basins, 1870, pp. 90-91), fully confirms this.

The Craigentinny Meadows .- After bearing testimony to the health of the village of Restalrig, which is surrounded by the sewage meadows of Lochend and Craigentinny, Dr. Littlejohn says:-"I expected that the first part of Edinburgh (Regent Terrace and Carlton Terrace), against which the wind blowing over these meadows impinges, would have exhibited evidence of infection in the shape of cholera or typhoid fever; but I have totally failed to find it so. There are also at Marionville, which is in the very centre of the meadows, a collection of children of the poorest class, who have been kept under the auspices of Dr. Guthrie. Thus the soldiers in the barracks (on the one side, the old people at Restalrig midway, and the very young children with debilitated constitution on the other side) are healthy, With these three delicate tests, including Regent Terrace and Carlton Terrace, we have failed to show that the meadows are prejudicial to health; in fact, opposite evidence might be obtained of a very strong kind."

Dr. Littlejohn informed one of us in January 1876 that he had not anything to add to or retract from the evidence he gave before the Rivers Pollution Commission.

Sir Robert Christison, Bart., M.D., President of the Royal Society

of Edinburgh, in an address on public health in October 1863, speaking of the influence of sewage irrigation on health, said :- "The irrigated meadows in the immediate neighbourhood of Edinburgh, with foul water, are ague-free. They might with reason be strongly suspected, for as managed they present that frequent alternation of considerable moisture and approach to dryness, that rankness of vegetation, and that abundance of decaying organic matter which are thought when combined eminently to foment intermittent and remittent fevers in countries liable to these diseases; but if there be any doubt as to the general salubrity of the now famous meadows of Craigentinny, there is none at least as to the total absence of ague among the inhabitants. I have recently been making careful inquiry respecting this famous and somewhat unsavoury institution. Many years ago my own prejudices were all against the meadows. I have been compelled to surrender them. I am satisfied that neither typhus or enteric fever, nor dysentery nor cholera is to be encountered in or around them, whether in epidemic or non-epidemic seasons, more than in any other agricultural district of the neighbourhood. I think it right in reference to the late introduction of the Craigentinny system of irrigation into the vicinity of other large towns, that these precise facts should be known."

Sir Robert Christison writes to the Secretary to the Commission on the 4th of February 1870, "I have nothing to add to or subtract from the extract from my Social Science address in 1863, quoted above."

CROYDON (SOUTH NORWOOD) SEWAGE-FARM.

"Dr. Alfred Cresswell in his evidence says:—I have resided in the neighbourhood of the South Norwood Sewage Farm since 1866, and have the largest practice there, especially attending the families of those who work on the farm, and who live in houses within 150 yards of the sewage fields. There is also a large school for girls near to the farm. In this school, in which there are more than 30 inmates. there has not been a single case of illness from preventible diseases, and my last quarter's bill was 5s. 6d. I have not been able to trace a single case of illness to the sewage fields. An unpleasant effluvia does exist, but it is so seldom perceptible that a house built within 200 or 300 yards would command the same rent as if half a mile off. My investigations and independent observations during the last three years have made me an advocate for this method of utilising sewage matter; and as an instance of how perfectly the watery portion is purified, I can state that the water flowing over these fields and thence conducted into the brook is frequently drank by persons who are ignorant of its source. It is clear, pellucid, and tasteless. Therefore, after watching the working of these fields, my opinion is that when the system of sewage irrigation is well managed the health of the inhabitants in the immediate vicinity is in no way influenced by it."

CROYDON (BEDDINGTON) SEWAGE-FARM.

"Dr. Alfred Carpenter says:—The visitor to Beddington will see a number of villas which have been occupied for some years, with irrigated fields both in front and rear, whilst not a trace of enteric disease has appeared in any of them, though I think the Beddington farm is capable of much improvement. It is a farm of nearly 300

acres, lying to the west of the town, and is within 500 yards of a populous portion of it, and also within 900 yards of the centre of the place; and yet I can safely say that the continuance of a west wind is always accompanied by a diminished amount of ordinary sickness in the place, and our ordinary mortality is generally below 20 per 1,040 At Norwood the population is much greater and much nearer to the fields than at Beddington, probably 400 persons living within 200 or 300 yards of the farm. Previously to its establishment in that district fever abounded; since then that disease has all but disappeared and the mortality of the district has steadily declined."

SEWAGE-GROWN GRASS IS WHOLESOME.

On the Liability to Disease which has been alleged to exist from the Consumption of the Milk and Flesh of Cattle fed on Sewage-grown Vegetables.

Dr. Henry D. Littlejohn, in his evidence before the Rivers Pollution Commission at Edinburgh, on September 23rd, 1870, said:—"There are a considerable number of cows kept in Edinburgh and the immediate neighbourhood, and a large quantity of milk is consumed, chiefly obtained from these cows. They are fed with grass that is grown on the Craigentinny meadows. I was of opinion that such grass might be of inferior quality, but I have failed to detect any bad effects resulting from its use. Entozoic disease is remarkably rare in Edinburgh, and tapeworm is hardly ever heard of, except in the cases of persons coming from other places to reside here. Many of the cows which have been fed upon sewage-grown grass are used as food. They are not fattened, because they are always kept in such capital condition; but the cows which have been so fed find their way to our slaughterhouses, where they are examined by inspectors and myself, and, so far as my observations have gone, the use of sewage grass for the food of animals is unobjectionable. Trichiniasis is not known in Edinburgh. If there had been anything in the idea that sewage grass would lead indirectly to entozoic disease, it has had plenty of time to develope itself, and Edinburgh is not only the seat of a great medical school, but medical observation is carried to the highest point so that it could not fail of being detected."

APPENDIX No. VI.

LIST OF PATENTS MORE OR LESS CONNECTED WITH SEWAGE AND MANURES.

Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1856	- 6	Alexander Cochrane -	Conveying and collecting sewage water, &c.
"	212	Edward Vincent Gardner -	Apparatus for heating, drying, evaporating, &c.
>>	974	Thomas Squire and Charles Frederick Claus.	Artificial manure.
2)	1288	William Needham and James Kite.	Expressing moisture from sub- stances.
>>	1579	James Alexander Manning -	Manure.
"	1815	Thomas Wicksteed -	Sewage.
"	1982	George Warriner	Compound for preserving, deo- dorizing, and fertilizing.
22	2003	Charles Durand Gardissal -	Manure.
22	2159	Stanislas Chodzko	Manure.
22	2273	Jean Francois Victor Lar- naudes.	Antiseptic and disinfecting mix- ture.
,,,	2289 2333	Duncan Bruce	Manure.
>>	0.0000000000000000000000000000000000000	John Gedge Francis Cook Matthews -	Mineral manure. Manure.
"	2560 2689	Edward Money	Manure.
"	2918	Anne Marie Macé -	Manure.
"	2924	Frederick Oldfield Ward	Manures.
33	100000	and Frederick Wynaut.	Manufacture of manure.
22	3000	Joseph Bower	Manufacture of manure.
1857	49	Frederick Herbert Maberly -	Receptacles for sewerage.
"	114	Sir James Murray	Deodorizing sewage matters, manu- facture and distribution of manures, &c.
	443	James Taylor	Manure.
"	862	John Ward	Manure.
"	983	Jean Francois Victor Larnaudès.	Disinfecting and deodorizing animal and vegetable substances.
22	992	Jasper Wheeler Rogers -	Apparatus for the collection of night soil and drainage of houses.
22	1004	Augustus Edward Schmersahl	Treating bones to obtain gelatine, size, glue, &c.
,,	1069	Thomas Richardson and Manning Prentice.	Manure.
22	1591	Frederick Oldfield Ward and Frederick Wynauts.	Manufacture of manure, &c.
"	2206	Robert Clark Gist	Manufacture of manure.
"	2220	John McMaster and William Wilson.	Manufacture of manure.
"	2438	Richard Archibald Brooman	Decomposing soapy wash waters, &c.
22	2627	Edward Owen	Manure.
"	2645	Charles Walker	Manufacture of manure.
"	2949 2980	William Thomas Manning - Jean Baptiste Cony -	Treatment of sewerage, &c. Manufacture of manure and disin-
			fection of animal and vegetable matters.

-			
Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1055	2002	Frederick Oldfield Ward -	Manufacture of manual & c
1857	3023 3131	Frederick Oldfield Ward - Francis Taylor	Manufacture of manure, &c. Closets or privies.
"	Towns Ann	2.000	der auch bereichte Copus
1858	61	James Alexander Manning	Treatment of sewage and other
	171	Charles Neillon	polluted liquids. Manufacture of manure from sewage
"	111	Charles Nemon	matters.
,,	179	James Alexander Manning	Manufacture of manure.
"	188	William Edward Newton -	Obtaining and applying com-
	199	Leon Salles de la Magdaleine	pounds of nitrogen. Manure.
"	287	George Lindsey Blyth -	Manure.
,,	354	Edward Toynbee	Manufacture of manure.
,,	400	John Hadfield	Manufacture of manure and other
	eer.	I D I I I D	products from sewage matters.
"	665 703	Isaac Brown and John Brown Thomas Greenshields	Manure. Treating ammoniacal liquor, &c.
"	733	Herman Schwietzer, Joseph	Manure.
"	100	Holder, and John Broughton.	
,,	1245	Robert Owen	Waterclosets, night commodes, &c.
,,	1456	James Cane Coombe -	Manufacture of manure from fœcal
		*	and other matters.
"	1499	John Chisholm	Treating sewage and other matters,
	1549	Constantine Nicolaus Kottula	Manufacture of manure.
"	1616	Richard Archibald Brooman	Apparatus for the reception and
	Light Inch	British hid Page (O.)	treatment of sewage.
,,	1620	Charles Fréderic Vasserot -	Manure.
,,	1664	William Parsons	Separating the solid matter from
	1793	Charles Felton Kirkman -	sewage waters. Treating sewage, &c.
"	1817	Thomas Pickford	Manure.
,,	2073	Jean Baptiste Adolphe	Separating solids from liquids for
		Dugléré.	the purpose of disinfection.
,	2451	Charles Finlay Oliphant Glassford.	Manure.
,,	2977	Thomas Pickford	Manure.
		-	Commence of the commence of th
1859	183	Thomas Richardson -	Manure.
"	184	Samuel Osler and John Barton Balcombe.	Manure.
,,	195	André Jacques Amand Gau-	Manure.
	1	tier, Jean Gilbert Dumay,	and the second second
	-	and Jean Theodore Persin	rosilianarocii) (Ale
- 33	313	Alexander Gopsell Pooley -	Apparatus for manufacturing
	447	Prederick William Emerson	Treating ores of lead, &c.
"	539	The Rev. Henry Moule -	Apparatus for the evaporation of
,,		AND PARTY OF THE P	sewage and other waters, &c.
,,	648	John Samuel Dawes -	Collecting night-soil for agricul-
	778	Thomas Carr	tural purposes. Machinery for disintegrating arti-
,,,	110	Thomas Carr	ficial manures, &c.
,,	879	Marc Antoine François	Treatment of mineral phosphates.
150	dimensional	Mennons.	
"	1220	William Edward Gedge -	Manure.
"	1280	Joseph Gibbs	Treatment of coal, &c. for the
	1368	John Henry Johnson -	manufacture of manure. Machinery for reducing solid sub-
"	1000	John Henry Johnson -	stances to powder.
			The state of the s
,,	1388	William Bryer Nation -	Manufacture of superphosphate of
"	1388 1559	William Bryer Nation - Thomas Bell	Manufacture of superphosphate of lime. Manure.

Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1859	1567	Bridge Standen	Manure.
,,	1843	John Dyer Bryant -	Superphosphate of lime.
"	1944	Michael John Stark -	Manure.
"	2107	Nathaniel Heckford -	Purifying rivers and treating night-
,,	2157	John Dales	Purification of sewage and other waters, &c.
,,	2200	Patrick Robertson	Manure.
,,	2218	William Henry Buckland -	Preparation of peat.
"	2270	George Long and James Archer.	Manure.
,,	2450	John Armour	Apparatus for measuring and regu- lating the supply of substances in preparing mixtures or com- pounds.
"	2460	Henry Phillips and James Bannehr.	Manure.
,,	2526	William Mannix	Manure.
"	2545	William Clark	Compound for preserving and dis-
	Sales a		infecting organic substances.
"	2958	Alexander McDougall -	Preparation of disinfecting and antiseptic substances.
1860	23	Marc Antoine François Mennons.	Fertilizing compounds.
,,	73	Archibald Brounlie -	Treatment of sewerage matters.
,,	232	Thomas Walker	Cleansing sewage and other waters.
,,	404	Joseph Arnold	Manure.
"	703	Thomas Richardson -	Treating organic substances con- taining phosphate of lime.
,	908	Jasper Wheeler Rogers -	Collecting excrement and facilitating drainage.
>>	1343	James Alexander Manning	Treating sewage, &c.
,,	1463	Richard Archibald Brooman	Desiccating fecal matters, &c.
,,	2023	William Clark	Manure.
,,	2246	William Edward Gedge -	Manure.
,,	2296	Thomas Richardson Man- ning Prentice.	Treating phosphotic matters, &c.
"	2482	Jasper Wheeler Rogers -	Apparatus for collecting excrement and draining houses.
,,	2777	Mathieu Louis Henrionnet and Leopold Octave Bob- lique.	Treating mineral phosphates of lime.
,,	2848	George Henry Cail -	Manure.
1861	249	Henry Phillips and James Bannehr.	Urinals; manufacture of manure.
>>	424	Thomas Richardson -	Manure.
,,	684	Jacob Jervell	Manure.
,,	876	Francis Taylor	Apparatus for receiving, drying, and deodorizing human excrement.
"	1019	Charles Stevens	Artificial manure.
,,	1276	Frederick Oldfield Ward -	Manure, &c.
,,	2159	Alexandre Jaille	Manure.
,,	2229	Charles Felton Kirkman -	Obtaining manure from sewage.
,,	2351	John Oliver, John Grantham, William Linnock, and Montague Richard Lever- son.	Obtaining chemical substances; treatment of vegetable fibre, &c.
-	2525	Thomas Tidmarsh	Manure.
"	2540	Charles Noyes Kernot and	Obtaining ammoniacal salts, &c.
"	2010	Martin Diederich Rucker.	o standard and saids, wer

Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1861	2871	Frederick Robert Hughes	Treating saline compounds.
	3265	and Thomas Richardson. Thomas Pickford	Manure.
1862	338	Mare Antoine François	Treating phosphates of lime.
TORIO 70	378	Mennons. Ditto.	Disinfecting animal excretions.
"	587	Bridge Standen	Manure, &c.
"	807	Michael Henry	Kilns, ovens, and furnaces.
"	908	William Clark	Manure.
"	1188	William Edward Newton -	Fertilizing composition.
"	1409	James House	Crushing and reducing substances.
,,	1623	William Footman	Treating sewage.
>>	2073	Alexander Morrison Fell -	Manufacture of sulphate of am- monia and manure.
,,	2082	Joseph Daniels	Artificial manure.
"	2097	William Clark	Manure.
"	2201	John Richard Nichol -	Utilizing and disposing of the sewage of towns and villages.
27	2669	John Harrop and James Wadsworth.	Deodorizing refuse and feeal mat ters for manure.
"	2712	John Beale and Mary Anne Beale.	Manure.
	3011	William Clark	Utilizing refuse azoted matters.
"	3132	Thomas Walker	Utilizing sewage, &c.
"	3317	Edward Toynbee	Extracting oils and fatty matters
STELLW T	dio fine	man antennal i	from shoddy, &c. and producing
4	20,000	ampalit !	artificial manure.
008 (COOL	3449	John Platt and William Richardson.	Disinfecting or pulverizing artificial manures, &c.
uniterifie	of Louisian or	Ancesta - 1 - Delination execut	talend III mount to the
1863	132	John Harrop	Manure.
22	321	James Alexander Manning -	Treating night-soil, &c.
12	606	Thomas Henry Morrell and Joseph Williamson.	Purifying noxious vapours from night-soil, &c.
	731	William Lorberg	Treating rags.
"	761	William Clark	Preparation of manure, &c.
.0000	967	Robert Calvert Clapham -	Treating waste liquors.
,,	1362	William Clark	Manure.
"	1435	Henry Martin	Manure.
"	2208	Thomas Henry Baker and	Treating excrementitious and
"	The second	George Friend.	sewage matters.
>>	2294	William Lorberg -	Treating rags.
29	2724	Guillaume Ville	Treating natural phosphates of lime
			for agricultural purposes.
,,,	2731	Jean Augustin Barral and	Manure.
	2947	Louise Adolph Cochery. Thomas Carr	Amalgamating, agitating, and dis-
"		.onundi - moto	solving materials.
,,	3152	John Wright	Manufacture of superphosphate of lime.
,,	3264	John Maynes	Manure.
1004	500	Edward Rishon and William	Evaporating the water from forcel
1864	592	Edward Bishop and William Bailey.	Evaporating the water from fœcal matter.
.02670	595	James Lee Norton	Manure.
"	597	John Thomas Way -	Manure.
"	773	James Robbins	Treating substances for producing
23	110	Salt-rived time	manure.
	955	James Cane Coombe -	Manure.
"	1024	George Jarvis Worssam	Expressing liquids and moisture
- "	ST TINTE	Material Wall 1882 Second	from substances.
"	1191	Thomas Walker	Utilizing sewage.

Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1864	1408	Thomas Walker	Preparing phosphates of ammonia
"	2072	Francis Taylor	&c. Apparatus for receiving, drying and deodorizing human excre
"	2329	Thomas Walker and Thomas Ferdinand Walker.	ment. Utilizing sewage.
	2788	James Alexander Manning -	Collecting and treating night-soil.
"	2832	George Edward Noone -	Deodorizing and utilizing sewage.
,,	2840	Jacques Jules Renous Céré	Manure.
22	3115	William Bardwell	Utilizing sewage, &c.
22	3160	Henry Bird	Treating sewage matters.
"	3161	Stephen Pierre André de Brocalde D' Elüza.	Manure.
"	3256	Thomas Richardson -	Manure.
1865	202	Benjamin King	Manure.
"	451	Richard Smith	Treating sewage and ventilating sewers.
,,	512	William Edward Newton -	Artificial manures.
,,	893	William Moxon Fuller -	Reducing waste for manure.
,,	1877	Donald McCrummen -	Artificial guano.
"	1935	Thomas Spencer	Compounds for promoting vegeta
22	2626	John Linton	Utilizing sewage.
"	2808	Henry Young Darracott Scott.	Treating and deodorizing sewag
23	2830	George Bartlett	Artificial manure.
>>	3115	John Thomlinson	Disinfectants.
1866	101 191	Francis Sutton Adolphe Francois Mineur -	Treating sewage and urine. Manure.
>>	642	Victor Larnaudès	Disinfecting and preserving fluid.
"	773	Alfred George Lock -	Manure.
27	898	Charles Thieme Liernur -	Collecting sewage, &c.
"	921	James Davis	Utilizing and preventing decon position of substances.
,,	949	Alfred George Lock -	Manure.
"	1026	George William Skinner -	Utilizing sewage.
>>	1163	George Edward Noone -	Deodorizing and treating sewag &c.
33	2107	Adolph Kühne	Purifying water, &c.
22	2218	Robert Irvine	Treating and purifying water.
,,	2606 2750	George William Skinner -	Utilizing sewage.
"	2730	Francis Taylor	Apparatus for receiving, drying and deodorizing human excre ment.
**	2926	Henri Adrien Bonnneville -	Manure.
"	2988	James Conyers Morrell -	Dry closets, &c.
,,	3296	Thomas Hoey	Flushing waterclosets, &c.
,,	3401	William Bradburn	Treating excrementitious matter &c.
1867	119	Ernst Süvern	Purifying factory and sewag
,,	579	William Parry and John Frearson.	waters. Treating sewage.
	729	James Conyers Morrell -	Dry closets.
"	788	Alfred Henry Hart and William Parry.	Treating sewage.
	933	William Clark	Manure.
1)	1229	Emile Grienin	Disinfecting fecal matters.

Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1867	2549	Frederick Tolhausen -	Disinfecting fecal and manuring matters, &c.
",	2894	Thomas Henry Baker and Thomas Woodroffe.	Treating and purifying sewage.
,,	2918	James Bannehr	Supplying deodorizing material to closets, and treating liquid
,,,	3566	Alexander Melville Clark -	Extracting ammonia from fer- mented and other liquids, &c.
1868	510	William John Bennett and John Jobson.	Filtering sewage, &c.
,,	566	Pierre Nicholas Goux -	Treating and utilizing excreta.
"	744 1954	William Knox Stuart - William Cameron Sillar,	Treating and utilizing sewage.
"	1334	Robert George Sillar, and George William Wigner.	Deodorizing sewage for manure.
,,	2666	John Yule	Removing sewage.
"	2667	William Shang	Separating sewage.
"	2883	William Henry Hughan - Edward Henry Prentice -	Treating and deodorizing sewage, &c.
"	3087	James Dewar	Treating sewage, &c. Manure.
"	3203	Gavin Chapman	Treating sewage.
,,	3341	Sigismund-Schuman -	Waterclosets.
"	3390	Alexander Melville Clark -	Filtering sewage, &c.
"	3457 3562	Charles Jones Thomas Smith and John	Treating sewage. Deodorizing and manufacturing
"	0002	Van Norden Bazalgette.	manures from sewage, &c.
27	3714	Alexander Melville Clark -	Compound for disinfecting sew- age, &c.
"	3914	Josiah George Jenning -	Treating sewage and irrrigating land.
1869	506	Frederic Delbreil	Removing sewage, &c.
,,	791	Josiah George Jennings -	Preparing sewage for irrigating.
	815	James Carter	Disinfecting and deodorizing fecal matters, &c.
"	826	John Thomas Darke -	Treating sewage.
"	982 1103	Joseph Caldwell Lee Edward Charles Cortis Stan- ford.	Collecting and treating excreta. Applying, treating, and utilizing materials for deodorising.
- ,,	1352	Charles Thieme Liernur -	Removing and utilizing sewage.
"	2016	John Hart	Separating, distributing, and uti- lizing sewage.
"	2269 2623	John Henry Johnson - Friedrich Wicke, Julius	Manure.
. "	2020	Brönner, Theodor Peter- sen, and Johann Georg	Treating excreta for manure.
		Zehfuss.	w Esical Dione Necket v
,,	3129	Francis Taylor	Drying excrement.
, ,,	3550	Mark French Anderson -	Treating sewage for manure.
1870	67	William Henry Hughan -	Treating sewage, &c.
00.00	239	Maxwell Anketell and Oli- ver Frederick Anketell.	Manufacturing manure and fuel
	364	George William Wigner -	from sewage, &c. Treating and purifying sewage.
,,,	506	John Leopard	Treating and filtering sewage.
22	580	Alexander Bobrownicki and	Fuel and manure.
		Alfred Didier Marie Mes-	
"	607	David Forbes and Astley Paston Price.	Treating sewage.

Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1870	630	James Conyers Morrell -	Treating sewage.
,,	679	George William Wigner -	Centrifugal drying machines.
"	1061	Thomas James Smith -	Treating sewage, &c.
	1137	David Forbes and Astley	Treating sewage and producing
"		Paston Price.	manure.
	1200	Ludwig Schad	Treating excrement.
33	1311	Robert Weare	Treating sewage, &c.
"	1314	Astley Paston Price -	Treating sewage.
"	1354	George William Wigner -	Deodorizing and purifying sewage,
"			&c.
"	1706	Bevan George Sloper -	Treating sewage.
,,	1949	Peter Spence	Treating sewage.
,,	2032	Henry Malcolm Ramsay -	Treating sewage, &c.
"	2047	John Hughes Lloyd -	Utilizing and deodorizing sewag
	2048	Charles Bartholomew -	Treating sewage.
"	2297	Joseph Judge Harp -	Purifying and utilizing sewage.
,,	2534	Ferrar Fenton and Samuel	Treating sewage, &c.
"		Hollins.	
,,	2653	Charles Felton Kirkman -	Treating sewage.
,,	2832	William Frost Sweetland	Purifying sewage.
	Name of the last	and John Merfield.	
,,	2838	Joseph Judge Harp -	Treating sewage.
,,	3107	Amos Bryant and Samuel	Deodorizing and treating sewage,
		Hall Culley.	&c.
,,	3167	Fritze Hillé	Manufacture of deodorizing and disinfecting compounds, treatmen of sewage, &c.
,,	3169	Henry Young, Darracott Scott.	Treatment of sewage, &c.
,,	3269	Frederick Ludewig, Hahn	Treating of sewage.
	0000	Danchell.	
"	3399	Christopher Rawson, Philip Ovenden, James Wylde, William McCree and Henry	Deodorizing and purifying sewage, &c.
		Hill.	
1871	297	Proctor Sherwin and John Maude Sutton.	Treating sewage matters, &c.
,,	329	Bevan George Sloper and Felix Jean Joseph Washer.	Treating sewage.
2000	351	Charles Baly	Treating sewage, &c.
"	804	Richard Dover	Treating sewage.
"	1269	Frans Julius Fahlman -	Disinfecting fecal matter.
"	1469		Separating solid from liquid excreta
"	707777	Adolphus Videky	
"	1897 1969	Ferrar Fenton Edward Taylor	Treating sewage, &c. Treating excreta, &c. for manu-
,,	2109	James Beckett and John James Cam.	facturing manure. Treating sewage.
	2140	James Irvine Lupton -	Treating sewage.
"	2243	Henry Young Darracott Scott.	Treating sewage.
	2274		Drying sewage, &c.
"		- B	Drying sewage, &c. Drying precipitated sewage, &c.
"	2481	Francis Parry	
"	2495	James Banks and William Walker.	Treating and filtering sewage water, &c.
,,	2567	Charles De Chastelain -	Collecting and filtering sewage.
,,	2569	James Burrow	Treating sewage, &c.
"	2696	Robert Milburn and Thomas Browning.	Drying and treating sewage deposit &c.
. 0000	2760	James Brough Pow -	Treating sewage.
22	# F 00	CHILLS AND CHARLE A CHI	

			Purpose of Patent.
1871	2841	Daniel Wilks	Collecting and utilizing animal refuse, sewage, &c.
,,	2878	Bendedict John Angell -	Treating seaweed.
"	2926	Adolphe Pierre Vassard -	Treating liquid sewage, &c.
"	2975	Job Cole and William Ab-	Treating and utilizing sewage. &c.
	2005	bott.	The street is a second of the street in the
"	2997	Hugh Smith	Treating sewage.
,,	3060	William Henry Hughan - François Jules Fahlman -	Manure.
"	3233 3436	James Alfred Wanklyn -	Apparatus for treating sewage, &c Utilizing sewage ammonia.
"	3515	Henry Young Darracott	Treating sewage water
"	0010	Scott.	The state of the s
1872	379	Francis Gerard Prange and William Whitthread.	Utilizing sewage.
,,	388	Alexander Melville Clarke-	Treating sewage, &c.
"	448	Silvester Fulda	Clarifying waters, &c.
22	465	David Carter	Dry earth closets.
22	575	William Cameron Sillar and	Treating sewage.
		Robert George Sillar.	m
22	671	Robert Blackburn	Treating sewage.
12	742	John Bailey Denton and Rogers Field.	Regulating intermittent filtration of sewage and irrigation.
"	849	Henry Young Darracott Scott.	Treating sewage water.
	926	Arthur Charles Henderson -	Distilling and filtering fecal matters.
"	944	Dugald Campbell	Treating sewage, &c.
"	955	William Weldon Symington	Measuring the flow of sewage, &c.
"	1065	Leos Antoine Badin -	Manure.
,,	1327	Thomas Christy the younger	Treating ammoniacal liquor, &c.
,,	1421	James Robey	Filtering medium, &c.
,,	1577	Andrew John Murray -	Treating sewage deposits.
"	1806	William Cameron Sillar,	Treating animal matters.
-538FF	a galatia	Robert George Sillar, and	
,,	2141	Christopher Rawson Henry Syed Copland -	Apparatus for mixing and preci- pitating sewage, &c.
,,	2266 .	Robert Milburn and Henry Jackson.	Drying and pulverising manure cement, &c.
,,	2279	Isaac Brown	Treating sewage.
"	2496	Millington Henry Synge -	Deodorizing apparatus.
,,	2538	Henry Young Darracott Scott.	Treating sewage.
"	2687	Bridge Baron Standen	Collecting and treating excremen- titious matters.
,,	2991	William Ashop	Drying sewage.
"	3028	Henry Young Darracott Scott.	Treating sewage.
,,	3215	John Lewis Felix Target -	Receivers for waterclosets.
"	3348	Rogers Field	Sewage tanks.
"	3355	Henry Young Darracott Scott.	Treating sewage deposits, &c.
"	3356	James Alexander Manning	Treating fecal matters.
22	3412	Gustav Alsing	Treating night-soil, &c.
"	3464	Edwin Hills and Benjamin Biggs.	Treating sewage.
"	3529	David Curror and James Dewar.	Purifying fluids and manufacturing manures.
"	3670	Henry Young Darracott Scott and Thomas Wal- ker Scott.	Preparing lime for treating sewage.
"	3734	William Hart and James Hart.	Drying sewage precipitates, cement, pulp, &c.

Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1872	3755	Henry Young Darracott	Treating and utilizing sewage
,,	3788	Scott. Charles Denton Abel -	water. Conveying sewage from cesspools, &c.
"	3805	John Rendall and William Rendall.	Slop carts.
"	3821	John Lewis Felix Target -	Collecting and disinfecting sewage exereta.
,,	3843	George Haseltine	Rendering and drying animal matter, &c.
,,	3882	William White Fereday -	Treating excreta for conversion into manure.
"	3913	Leos Antoine Badine -	Closets and apparatus for collecting feeal matters.
1873	154	Henry Young Darracott	Treating sewage.
	168	Scott. John Lewis Felix Target -	Treating excreta and sewage.
"	187	Edward Charles Hamilton,	Manure.
		William Richard Preston, and Henry Jones.	
,,	230	James Robey	Charcoal for purifying sewage, &c.
"	266	Frederick Jacobsen -	Treating sewage.
"	331 499	Baldwin Latham George Frederick Chantrell	Purifying sewage. Receptacle for house refuse, &c.
"	513	Hugh Campbell	Manufacture of manure.
"	556	Francis Henry Atkins -	Filtering apparatus.
"	570	Henry Young Darracott Scott.	Treating excreta.
,,	712	Thomas Hoey	Watercloset apparatus.
"	912	Robert Stevenson Symington	Apparatus for dealing with sewage &c.
"	957	James Robey and George Frederick Chantrell.	Filtering and deodorizing medium
"	1319	Gustav Alsing	Treating sewage, &c.
"	1445	Henry Young Darracott Scott.	
,,,	1509 1555	Do Walter Brown	Do. Treatment of sewage.
	1686	Eugene Moriarty	Treating sewage.
"	1885	Benjamin Green	Storing and treatment of sewage.
,,	1967	Joseph Townsend	Treating sewage.
"	2071	John Leigh	Treating sewage, &c.
"	2317	Jeremiah Marsden and John Collins.	Treating sewage.
"	2442	Robert Knott	Treating sewage, &c.
"	2450	Edward Charles Hamilton and William Richard Preston.	Artificial manure.
	2454	Frederick Jacobsen -	Purification of sewage, &c.
"	2532	William White	Treating sewage.
,,	2534	James Robey	Do.
,,	2581	John Stephens	Treating excreta, &c.
,,	2638	John Leigh	Manufacture of manure.
,,	2662	Christopher Rawsen, William Cameron Sillar, John William Slater, and Thomas Sinling Wilson	Manufacture of manure.
	2760	Thomas Sipling Wilson.	Treating sewage
"	2791	William Henry Hughan - Rupert Goodall	m
	3168	Charles Thieme Liernur -	Pneumatic drainage works.

Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1873	3169	William Whitthread -	Disinfectant and oxydizing agent.
	3331	John Towle	Treating sewage.
33	3541	John Hewitt Milnes -	Utilizing sewage.
"	3632	Alexander Colvin Fraser	
"	0002	and William Watson.	Treating and utilizing sewage.
"	3742	Henry Young Darracott Scott.	Treating sewage water.
"	3781	William White	Precipitating sewage and other four waters, &c.
,,	3833	Benjamin Green	Storing and treating sewage.
"	4092	Henry Malcolm Ramsay -	Treating sewage.
"	4284	John James Bodmer -	Drying peat, sewage deposit, &c.
1874	50	William Alfred Gibbs -	Drying apparatus.
"	160	Augustus Edward Schmer- sahl.	Treating sewage.
"	283	Henry Young Darracott Scott and John Berger	Treating sewage, &c.
,,	653	Spence. Henry Young Darracott Scott.	Treating sewage for manure.
,,	848	Rupert Goodall	Purifying foul water or sewage.
	1171	Thomas Short	Purifying sewage.
"	1415	William Robert Lake -	Deodorizing and utilizing sewage.
"	1426	John Towle	Collecting, treating, and distributin sewage.
"	1453	Daniel Kinnear Clark -	Disintegrating and straining ap
,,	1689	Gustav Alsing	Utilizing sewage for manufacturing artificial fuel.
"	1764	John Howard Kidd -	Deodorising sewage and making
,,	1826	Rupert Goodall	Clarifying sewage, &c.
"	1916	John Henry Johnson -	Filtering sewage, &c.
,,	1959	William Henry Hughan -	Treatment of sewage, &c.
	2408	Samuel Hallsworth and	Clarifying waste water, sewage, &c
"		Richard Bailes. Augustus Edward Schmer-	Treating sewage.
"	2439	sahl.	
22	2446	William Alexander Lyttle -	Treating sewage.
"	2450	Henry Young Darracott Scott.	Recovering ammonia for sewage.
"	2461	William Spence	Treating sewage.
"	2567	Feorge Willett, Robert James Harris, and James	Filtering sewage.
	State of the last	Lund.	
"	2676	James Alexander Manning -	Dry closets, &c.
,,	3122	Bridge Baron Standen -	Treating excrement.
"	3199	John Howard Kidd -	Treating sewage for manufacturing manure.
,,	3225	James Mc. Intyre	Purifying sewage waters.
,,	3326	Francis Thomas Bond -	Treating liquid refuse, &c.
,,	3384	Francois Alcidi Bonnefin -	Treating excrementa.
"	3459	Samuel Hallsworth and Richard Bailes.	Treating and clarifying sewage, &c
,,	3751	George Mackay	Purifying liquids.
"	3784	Burton Henry Valle -	Treating sewage.
,,	4158	Rupert Goodall	Clarifying impure water or sewage
	4247	James Conyers Morrell -	Sewer pipes, &c.
"	4305	Henry Young Darracott Scott.	Treatment of sewage.

Date.	Number of Patent.	Name of Patentee.	Purpose of Patent.
1875	150	George Rydill	Purifying sewage, &c.
22	214	John Box, Edouard Aubertin, Leopold Boblique, and Hypolite Leplay.	Disinfection of sewage, &c.
,,	373	Henry Young Darracott Scott.	Manures.
,,	399	George Rydill	Treating sewage.
"	573	Samuel Hallsworth and Richard Bailles.	Clarifying sewage, &c.
"	1195	Francis George Whitwharn	Treating excreta.
,,	1216	William Edward Newton -	Treating fecal matters, &c.
,,	1335	William Morgan-Brown -	Treating sewage.
,,	1625	Thomas Pape	Filtering and deodorizing sewage.
"	1759	John Yale	Barge for receiving and conveyin sewage.
,,	1845	Mark French Anderson -	Treating sewage.
,,	1954	Joseph James Coleman -	Treating sewage.
39	1972	Daniel Wilks	Collecting and treating sewage.
"	2358	James Odams and Robert Blackburn.	Apparatus for treating sewage.
,,	2557	Frederick William Granham	Filters.
22	2621	David Gill	Deodorizing sewer gas.
,,	2675	John Hanson	Treating sewage.
22	2798	Joseph Robinson	Discharge of sewage from towns.
,,	2829	Thomas Stevens	Treating sewage.
22	3162	Alexander Melville Clark -	Treating sewage.

APPENDIX No. VII.

Abstracts from the Reports of Royal Commission, and others, who have inquired into the best Modes of Distributing the Sewage of Towns and of applying it to beneficial and profitable Uses.

The following extracts are taken from published reports which are now out of print, and which consequently cannot be made generally available. On referring to them, it will be seen that there are detailed statements, as also conclusions and recommendations, which have as much value now as at the time they were made. Our more recent examinations of towns, sewage farms, and the several modes of treating sewage, confirm the conclusions almost to the letter. We therefore point to these extracts as justifying our own conclusions.

EXTRACTS from the REPORTS of the ROYAL COMMISSION.

PRECIPITATION of the SOLID MATTER of SEWAGE.

Of the different processes that have been proposed for the precipitation of sewage, that by lime is the simplest. It is also the only one that has hitherto been put into practical operation to any considerable extent, and we may be therefore allowed, without disparagement to other

methods, to select it as a type for illustration of the whole.

The use of lime to separate the solid matters of sewage is founded on the following circumstances. Sewage of itself, from the slimy, glutinous character of the matter floating in it, and from the specific weight of that matter being so nearly the same with water, will only separate very imperfectly, and after a length of time, into a clear liquid and a solid deposit.

The addition of lime, however, by the chemical changes which it induces, but which we need not here describe, causes a separation of the solid suspended matter in a state of flocculence, in the same way that

white of egg clears coffee or isinglass fines beer.

The result is that the sewage rapidly changes its character, separating readily into a deposit, which falls to the bottom, leaving a clear liquid. This is essentially the process that is carried on at Leicester, Tottenham, and other places, the two named being the most important. The clear liquid after subsidence of the solid matter is considered comparatively pure and unobjectionable, and is allowed to flow into the rivers. The solid is drained, as far as possible, and finally dried, and then offered for sale as manure.

We may state our belief that, as far as present knowledge goes, that is, up to 1858, this very simple process offers as much prospect of commercial advantage in respect to the manufacture of a solid manure from sewage as any patent process that has been proposed up to this date.

But with reference to the prospect of obtaining any very large profit from the treatment of sewage, we see no reason to dissent from the view that has been individually held and promulgated by several of our members, namely, that neither the lime process nor any other existing method of precipitating sewage is likely to be commercially advantageous to those who engage in it. We consider that this is, however, not the light in which the matter should be viewed. The great problem is to get rid of sewage advantageously to agriculture, if it may be; if not, at the least expense to the community at large.

Throughout the discussions that have hitherto occurred upon this question, the real issue has been left comparatively in abeyance. The

primary consideration is not whether sewage can be made serviceable to agriculture, but whether or not there exists any method which, consistently with a fair expenditure of money, falling on those who ought in justice to bear it, will practically rid us of the nuisance and danger

attendant upon town sewage.

The object must be accomplished, and the question is, simply, how its accomplishment can most satisfactorily be attained. All other considerations are secondary to this. The process of precipitation by lime, as carried out at Tottenham, and on a larger scale at Leicester, is satisfactory up to a certain point. The solid matter of the sewage is effectually separated, and a clear and comparatively innocuous liquid is run off. We shall presently consider the objections that have been urged against this liquid, but we wish now to point out that any nuisance which is chargeable to works such as those at Leicester and Tottenham is due, not to the act of precipitation, but to the process employed for drying the solid matter into a condition fit for sale. At both the establishments in question the sewage is received and treated in closed or covered tanks, and, as the lime considerably diminishes the smell of the sewage, the whole operation can be carried on, and the clear liquid run off, without offence. But the solid deposit which settles down in the form of a thick sludge must be removed, and must in some way be dried. This part of the operation is very difficult; it requires much space, and the value of the product is too small to allow of the drying being entirely effected by artificial heat. Consequently, both at Tottenham and Leicester, we found great pits and mounds of this sludge undergoing a gradual process of draining and drying in the open air; and it is to these accumulations of the precipitated matter of sewage, exposed to the sun and other agencies, that the offensive smells must be attributed, which sometimes, but not always, are perceptible from the works.

As an inexpensive means of avoiding nuisance, we may here advert to the simple process adopted by the Local Board of Health at Cheltenham for separating and disposing of the solid matters of sewage in conjunction with the use of lime, which has been attended with considerable success. This method seems likely to be made available

in many other places with advantage.

The chief portion of the solid matter is separated in tanks by deposition and a coarse filtration or straining process, the liquid flowing off is then treated with lime in order to diminish the smell and to precipitate the finer particles in suspension in the water before it is allowed to flow into the stream. The deposit or sludge first obtained is mixed with ashes and scavenger's refuse of the town, and thus a solid manure is formed which has been bought by the farmers in the neighbourhood at 2s. 6d. per cubit yard. A charge of 3s. 6d. per cubic yard would pay all working expenses and interest on the outlay, and it is thought that this price might be obtained for it; but one most desirable and necessary thing is to have a regular and speedy removal from the ground.

With regard to the liquid which results from the operation of liming sewage, its frequent examination by different chemists has proved, what would in fact have been anticipated, that it contains a considerable quantity of dissolved matter of a vegetable and animal origin which the lime is incapable of separating; a certain amount of smell also remains, although by no means the same in kind or degree as the crude

sewage.

In the report of Dr. Hoffman and Mr. Witt, addressed to the referees on metropolitan drainage, the subject of these precipitating processes has been discussed at some length. These gentlemen have arrived at the conclusion that, inasmuch as a quantity of "putrescible" matter is left in the liquid resulting from liming the sewage, and that this liquid when kept during warm weather is liable to become a second time offensive to the senses and consequently dangerous to health, such process is not admissible in the case of the metropolis. But we submit that the question is not whether, in the abstract, sewage after treatment with lime contains vegetable and animal matters in solution, and is liable to further putrefaction, but whether such treatment so far destroys the noxious character of sewage that practically it may be thrown into rivers without danger.

Without going so far as to say that the precipitation by lime is a perfect process, or that it can in all cases be adopted, we feel satisfied that it does to a great extent fulfil the purpose for which it is employed, so far, at least, as the purification of rivers is concerned.

By far the largest amount of nuisance and danger arising from the pollution of rivers by sewage is due to the solid suspended matters which give off noxious effluvia throughout the period of their decomposition. This is especially the case in our tidal rivers, where these deposits form sheals and cover the banks, and at low water offer a vast surface of offensive matter for the contamination of the air. The lime process does effectually remove this gross solid suspended matter, and in so far accomplishes a great and manifest good. It also destroys the immediate influence of the noxious gases in sewage, and although it may, in the abstract, be open to the objection of still leaving matter capable of further putrefaction in the liquid, we are of opinion that wherever this liquid is thrown into a body of water considerably larger than itself (not less than 20 times the volume of the clarified sewage) no evil results will practically be experienced.

Our conclusion, then, is, that in the absence of means for a direct application of sewage to land, the methods of precipitation at command by lime do actually offer remedial measures of a satisfactory character. It remains to consider whether these remedial measures are within the fair limits to which a town population may be taxed for the suppression

of the sewage nuisance.

We have already stated our belief that unless some new process of greater efficiency should be discovered, the formation of a solid manure from sewage will not be remunerative; that is to say, that the amount realized by the sale of the manure will fall short of the cost of its production. Neither is this to be considered as a condition dependent on the want of appreciation of the manure, which time and better information on the part of the consumer will remove; on the contrary, the tendency has been hitherto to put the price above the value which a sound acquaintance with the nature of manures would attach to it. It is even questionable whether, in some instances, any money at all would be given for this deposit, and in considering the practicability of carrying into effect plans for the precipitation of sewage we must be prepared for this eventuality.

It will therefore be placing the matter in a necessary, although the least favourable, light, if we consider that the manure when made possesses only so much value as to induce farmers to cart it away without paying for it. It may be desirable, however, that we should here advert to a plan by which the expenses attendant on these precipitating processes would be very materially reduced, and the necessity for works for this purpose in the vicinity of towns, and the possible nuisance or fear of nuisance to which they might give rise, would be entirely obviated. This plan is to limit the process to the precipitation of sewage, and after allowing the clear liquid to run off, to pump the sludge or mixture of deposited matter and water directly on to the fields

through pipes.

Remarks.—This process of pumping sewage-sludge direct from the tanks where it is deposited to the land is practised at Birmingham. The sludge is spread over land to the extent of one statute acre per week, and is trenched or dug in at a cost of 14l. 10s. per acre. In this position the water absorbs or evaporates, and leaves the dried earthy matter in the soil. After the interval of a year the land can be used for farming purposes. The sludge as pumped contains about 90 per cent. of water, which dries away in about 12 months' time.

It has already been stated that the chief source of nuisance, or liability to nuisance, in such works consists in the necessity for drying the sludge, and a very large portion of the original outlay for works and the area required for such works, and of the daily expenses, is involved in this part of the operation. By the plan above mentioned all these difficulties would be materially reduced, the works would be confined to the precipitating tanks and the engine for pumping, and neither the sewage nor the deposit would see the light of day before the clarified water was discharged in a comparatively innocuous state into the rivers, and the sludge was deposited on the fields.

It has been calculated that the quantity of sludge to be pumped would not exceed 5 per cent. of the whole sewage, so that the cost of applying it would be small in comparison with that of distributing the whole

sewage on the land.

Remarks.—The Commissioners did not apparently anticipate the cost of digging in the sludge at 141. 10s. per acre, and the loss of at

least one year's rent of the land.

We have already stated that the processes for separating the solid matter do not realize the agricultural value of the sewage. It has long been understood that at least four fifths of the substances valuable in relation to vegetation pass away with the water; the solid matter, therefore, which in this plan would be pumped on the land, would not fertilize so large an area as the whole sewage; but in relation to the necessary disposal of sewage, which it is our duty to keep steadily in view, this circumstance would offer some advantages, inasmuch as it would in many cases be much easier for town authorities to find the smaller area of land upon which it might be applied than that extensive space which the whole sewage would require. Other modifications in carrying out this system will readily present themselves.

The two methods for the disposal of sewage, that is to say, by direct application to land, or by precipitating processes, have been, perhaps, sufficiently considered. It is almost unnecessary to add that they can be worked conjointly, and in some cases such a plan would be attended with advantage. Thus, for instance, where opportunities occurred for the disposal of a part of the sewage for direct application, though the whole could not immediately be so got rid of, the remainder might be treated

by methods of precipitation.

The erection of works for the latter purpose would obviate the present nuisance, and give time for that change of opinion which will ultimately

cause the sewage to be sought after by agriculturists.

Moreover, in many cases the previous separation of the solid matter may increase the facilities for liquid application, allowing of the use of large quantities by open irrigation on a limited area without the risk of nuisance.

Remarks.—The land filtering process will enable large volumes of clarified sewage to be filtered on small areas, 2,000 persons to one acre.

It remains now only to revert to one point in relation to the character of the liquid after these precipitations of sewage have been effected.

It has been already mentioned that objections have been taken to lime

and other similar processes, on the score that the liquid is liable to become again putrid. We have stated that we believe this circumstance to be practically unimportant, but, as it is a wise policy in all cases to avoid even the occasion of offence, it is very desirable that even this objection should be overcome. If, after the separation of the solid matters by lime or other precipitants, any further treatment of the clear liquid would place it in a condition in which ulterior change involving the production of offensive and noxious smells would be impossible, the problem, both in a theoretical and practical sense, would be most completely solved.

We are of opinion that the accomplishment of this object is quite within the means of chemical science, and we feel ourselves justified in expressing this conviction from the results of experiments which have already been made in presence of some members of the Commission,

although our investigation of this point is not yet complete.

From the whole of our inquiry we have arrived at the following conclusions:—

PRELIMINARY REPORT, MARCH 1858.

Conclusions.

1st. That the increasing pollution of the rivers and streams of the country is an evil of national importance, which urgently demands the application of remedial measures; that the discharge of sewage and other noxious refuse of factories into rivers is a source of nuisance and danger to health; that it acts injuriously not only on the locality where it occurs, but also on the population of the districts through which the polluted rivers flow; that it poisons the water, which in many cases forms the sole supply of the population for all purposes; that it destroys fish; and, generally, that it impairs the value and the natural advantages derived from rivers and streams of water.

2nd. That this evil has largely increased with the growing cleanliness and internal improvements of towns as regards water-supply and drainage; that its increase will continue to be in direct proportion to such improvements, and that as these improvements are yet very partial, the nuisance of sewage, already very sensibly felt, is extremely slight as compared to what it will become when sewerage and drainage works

have been carried into full effect.

3rd. That, in many towns, measures for improved water-supply and sewerage are retarded from the difficulties of disposing of the increased sewage which would result from them; that the law which regulates the rights of outfall is in an anomalous and undefined condition; that judicial decisions of a conflicting character have been arrived at in different instances; and, that consequently the authorities of towns have

constantly before them the fear of harassing litigation.

4th. That the methods which have been adopted with the view of dealing with sewage are of two kinds: the one being the application of the whole sewage in its crude state to land; and the other, that of treating it by chemical processes, to separate its most offensive portions; that the direct application of sewage to land favourably situated, if judiciously carried out, and confined to a suitable area, is profitable to persons so employing it; that where the conditions are unfavourable, a small payment on the part of the local authorities will restore the balance.

5th. That this method of sewage application, conducted with moderate care, is not productive of nuisance or injury to health.

6th. That when circumstances prevent the disposal of crude sewage

by direct application to land, the processes of precipitation will greatly ameliorate and practically obviate the evils of sewage-outfalls, where there is the sea, or a large river for the discharge of the liquid; that such methods of treating sewage do not retain more than a comparatively small portion of the fertilising matter; and, that although in some cases the sale of the manure may repay a portion of the cost of production, solid manure manufacture is not likely to be successful commercially.

7th. That, considered merely as the means of mitigating a nuisance, these precipitating processes are satisfactory; that the cost of them in any case is such as town populations may reasonably be called upon to meet; that the necessary works need not, if properly conducted, be a source of nuisance, and that, by modifications of the existing methods,

even the slightest risk of nuisance may be entirely obviated.

Sth. That the employment of the one or other method of disposing of sewage, or of both conjoined, must depend upon locality, levels, markets, and a variety of other circumstances, and that the case of each town must be considered upon its own peculiarities.

9th. That there is good ground for believing that the methods yet proposed for dealing with sewage are not the best that can be devised, and that further investigation will probably result in the discovery of processes more thoroughly equal to the suppression of nuisance, and at the same time calculated to give more valuable products.

10. That the magnitude of a town presents no real difficulty to the effectual treatment of its sewage, provided it be considered as a collection

of smaller towns.

As, however, the conditions under which the evil may be best removed will differ greatly in different localities, we think it would be desirable, before any legislation takes place on this subject, that investigation should be made into the state of the outfalls of different classes of towns, and of the condition of rivers in populous districts, with the view to advise as to the general legislative measures that might safely be adopted.

Westminster, 26th March 1858.

SECOND REPORT, 1861.

Conclusions.

WE submit the following conclusions as the result of these our further investigations:—

1. That the pollution of the rivers of the country is so great and

general as to have become a national evil.

2. That this pollution has progressively increased in recent years, is still rapidly increasing, and, unless arrested, must necessarily continue to do so in proportion to the increase of population, the progress of town sewering and house drainage, and the extension of manufactures.

3. That although one of the chief causes of this pollution is the practice of discharging crude sewage, as it comes from towns, into the nearest rivers or watercourses, thus converting them into sewers, yet, the pollution from this cause is by no means confined to towns which have adopted systematic measures for improved sewerage. Nor is the amount of pollution in proportion exclusively to the completeness of such works; for, in many of the towns in which the bulk of the foul refuse is still retained in cesspools and middens, the neighbouring rivers are in a highly offensive and noxious condition,—even where the cesspool

system is maintained on the alleged ground of preserving the local rivers from contamination.

4. That besides the pollution of rivers by the discharge of sewage into them, they are in general made the common and ready receptacles of an immense amount of offensive matter from factories, dye-works, gasworks, iron foundries, mills and other establishments, while cinder-heaps and masses of rubbish of every description that cover their banks, and the large stones and other refuse that obstruct the beds, testify to the general neglect and ill-usage of rivers.

5. That by far the greater part of the solid matter which is held in suspension in water is readily deposited in rivers, covering the banks with mud, permanently raising the beds, gradually destroying the scouring power of the water, and partially silting such rivers up; and that in some instances these deposits have accumulated to such an extent as to impede navigation, to render the surrounding country subject to

floods, and to entail a vast expense in periodic cleansing.

6. That however the appearance of the water may be improved after these deposits have taken place, yet the deposited matters, lying in the bed of the current, are under conditions favourable for putrefaction. And when the foul mud is disturbed by the prevalence of rain, and during floods, it sends forth its effluvia amidst the populations which are near, and even in the course of the rivers far distant.

7. That this condition of rivers is a public and national nuisance; it interferes with the convenience and comfort of all classes of the people; it damages various and important interests, as those connected with manufacturing establishments, canals, fisheries, and so on; it deteriorates property to a large extent; and, as interfering with a main source of

water supply, is of serious detriment to the public health.

8. That this state of things has grown up in consequence of the anomaly that while important powers of river conservancy have from time immemorial been conferred on local authorities, while special powers have been vested in Improvement Commissioners and companies for isolated local improvement, for drainage, for navigation, and so on, and while even private water-rights and ownerships in streams have been recognized and conferred, no general jurisdiction whatever has been exercised over the whole waters of the country; no protection has been accorded to the many great and varied interests connected with rivers.

9. That the only way of restoring rivers to their original purity is to prevent the discharge of foul matters into them, and especially the discharge of sewage and other refuse of large towns; but that, in various cases where this treatment has been deemed inadmissible, expedients for the purpose of depriving the sewage of its offensive and noxious properties have been brought into practical operation, and have been

attended with more or less success.

10. That among those methods of which experience is most satisfactory no one is suited to the circumstances of all towns, some towns presenting much greater difficulties than others; yet the more this subject has been investigated the more convincing is the evidence that there is no town which might not, with reasonable care and at moderate cost, greatly mitigate existing evils where it may not be practicable wholly to remove them.

11. That, for example, the chief part of the nuisance arising from the discharge of sewage into rivers and streams may be obviated at once by simply arresting the solid matter in suspension in the liquid, particularly in towns of small populations where the sewers discharge into considerable streams of water. In these cases it may be practically sufficient to adopt simple means of deposit, combined with mechanical

appliances for arresting solid matters, and these may be of the most inexpensive character; in other cases, however, and especially during summer, the addition of chemical agents may be required for the more complete separation of solids, and the deodorising of liquid sewage. But although, by such means as the above, sewage may be rendered inoffensive to smell, we cannot guarantee that, even after the best practicable application of such means, sewage can be allowed to flow into any brooks or rivers without rendering the waters unsafe and improper for drinking.

12. That among deodorizers, the material which up to the present time has been found the best for this purpose is *perchloride of iron*, the only objection to its general use being its comparatively high price; but in many cases the employment of the cheaper material, lime, may

suffice.

13. That the value of the solid portions of sewage being small, all attempts at realizing profits from its preparation as manure have signally failed; but, mixed with ashes, sweepings, and other dry refuse of towns, sale is found for it at 2s. or 3s. per ton, which is sufficient to pay a

proportion of the necessary working expenses of mixing.

14. That the cost of the operation has in various instances ranged from $\frac{1}{2}d$, to 3d, per head of the population per annum, including interest on the outlay for works; there can therefore be no difficulty on the ground of expense in requiring the adoption of adequate means for a removal of nuisance in every case in which injury or inconvience is shown to arise.

15. That the most beneficial and most profitable method of disposing of sewage, where circumstances will admit of this use of it, is by direct application in the liquid form to land; where such applications can only be conveniently effected near habitations, it may be desirable to employ some deodorizing agent; but usually, if proper arrangements are made for conveying sewage on the land, this expense need not be incurred.

There is reason to hope that trials and experiments instituted by the Commission, and still in progress, in relation to the irrigation of land with sewage, will remove some doubts and difficulties which have hitherto prevailed in retarding a more general adoption of this desirable mode of disposing of and utilising the sewage of towns.

Recommendation.

Having now fully stated our conclusions as to the means of disposing of the sewage of towns, and shown that the remedies for the evils which are experienced, although various, are both practicable and economical, we beg to repeat our conviction that the only security for a general and continued employment of such means will be the establishment of responsible conservancies throughout the country, armed with adequate powers for prventing damage and for effecting improvements. We believe that these powers would be best vested in independent local authorities, such as the present Commissioners of Sewers; acting under certain Government regulations in respect to borrowing money, and other matters. Our inquiry, however, has of necessity been of too imperfect a character to enable us to set forth for consideration any decided measures in detail on so large and important a question. There are many subjects to be inquired into, and vast interests to be considered, which are beyond our present power or our province to enter upon. We can only respectfully but earnestly recommend that such inquiries should be instituted into the various points bearing on the subject, so that measures may be submitted which will enable Parliament to deal with the existing evils in a way most conducive to public interests.

Whitehall, August 1861.

THIRD REPORT of the ROYAL COMMISSION. CONCLUSIONS.

To the Lords Commissioners of Her Majesty's Treasury.

May it please Your Lordships, March 1865.

WE, the undersigned, whom Her Majesty's Commission, bearing date 5th January 1857, appointed to inquire into the best mode of distributing the sewage of towns, and applying it to beneficial and profitable uses, have now again, according to our instructions, the honour of reporting to your Lordships our further progress in the matter committed to us for inquiry.

Since the date of our last Report (August 1861) we have, through a committee of our number consisting of Mr. Lawes and Professor Way, continued at Rugby the experiments which were undertaken in 1861 on the application of sewage to land. The report of that committee, which

we append, contains the results for the three years 1862-4.

Your Lordships will observe that these experiments have not been confined to the application of sewage in different quantities to land, but have extended to the consumption by cattle of the produce so obtained, and to the production of meat and milk, and have been accompanied by a careful record of the quantities and market value of the products, and by numerous analysis of the sewage before and after irrigation, as also of the grass and of the milk.

It appears to us that these experiments have solved many of the difficulties which have hitherto attached to the question of the agricultural application of sewage, and that they leave no reasonable doubt of the practicability and advantage of so employing the sewage of

towns.

We have also continued to give our best attention to all kindred experiments and inquiries which have been going on elsewhere.

As the results of our labours, extending over eight years, we have confidence in submitting to your Lordships the following conclusions:—

 The right of way to dispose of town sewage is to apply it continuously to land, and it is only by such application that the

pollution of rivers can be avoided.

2. The financial results of a continuous application of sewage to land differ under different local circumstances; first, because in some places irrigation can be effected by gravity, while in other places more or less pumping must be employed; secondly, because heavy soils (which in given localities may alone be available for the purpose) are less fit than light soils for continuous irrigation by sewage.

3. Where local circumstances are favourable, and undue expenditure is avoided, towns may derive profit, more or less considerable, from applying their sewage in agriculture. Under opposite circumstances, there may not be a balance of profit; but even in such cases a rate in aid, required to cover any loss, needs not

be of large amount.

Finally, on the basis of the above conclusions, we further beg leave

to express to your Lordships that, in our judgment, the following two principles are established for legislative application:—

First, that wherever rivers are polluted by a discharge of town sewage into them, the towns may reasonably be required to desist from

causing that public nuisance:

Second, that where town populations are injured or endangered in health by a retention of cesspool matter among them, the towns may reasonably be required to provide a system of sewers for its removal.

And should the law, as it stands, be found insufficient to enable towns to take land for sewage application, it would, in our opinion, be expedient that the Legislature should give them powers for that purpose.

Whitehall, 1865.

EXTRACT from a REPORT by HENRY AUSTIN, Esq., C.E., prepared for the ROYAL SEWAGE COMMISSION.

Mr. Henry Austin, Chief Inspector of the Board of Health, was also a member of the Royal Sewage Commission, and was requested to prepare a Report for the Commission, of which these are the conclusions:—

As the result of my inquiries, and of the best attention which I have been enabled to afford to this important subject, I beg to submit the following conclusions:—

Conclusions.

1. That although from the earliest agitation of the question of sanitary reform, and of the complete drainage of towns, the mischief from pollution of rivers on the one hand, and the waste of valuable manure on the other, by the direct discharge of the sewage, was insisted upon, no conception was at any time formed of the extent of

the evil which now so imperatively calls for remedy.

2. That although the means of remedy by deodorization appear to be as yet but imperfectly understood, and demand further investigation, various processes have for a long time been in more or less successful use for this purpose. That the employment of some of these, known to be destructive of the fertilizing power of sewage, would involve expense without any return, and although such expense, if unavoidable, should unhesitatingly be incurred to avoid any permanent danger to the population, it appears that other deodorizing materials are not destructive of that fertilizing power. That it is most important, therefore, to determine whether the fertilizing elements in the refuse are presented in such form as to be practically available for agriculture, either in the solid state or in the liquid form, so as to avoid the injurious consequences and enormous waste of throwing away the sewage.

3. That the nature and value of the chemical constituents of the feecal matter in sewage having long been known to physiologists and chemists, and admitted to contain all the elements necessary for the food of plants, the recent discussions as to its practical value for agriculture have not arisen from any doubts on that point, but from the uncertainty whether, being diluted in the large bodies of water employed

for the drainage of towns, that value is realizable.

4. That chemical research has not yet arrived at any satisfactory

method of economically arresting from solution the fertilizing ingredients in sewage, while the analyses of solid sewage manures, manufactured under various patents, show that, although for the most part possessing a certain low value, they do not justify the high prices at which they have been offered to the public; nor does there appear to be evidence of any agricultural results derived from their use which will support such a view of their value.

5. That the manufacture from excrement of a dry portable manure, as practised at Paris, although realising results of greater value, is applicable only where the cesspool system prevails, and leads to an aggravation of the nuisance of that system, which due regard for the public health would not tolerate.

6. That the separate system of drainage, frequently proposed as a solution of the sanitary and agricultural difficulties of the sewage question, would increase immensely the cost of drainage works, would add to the sources of danger to the public health, and would tend to a waste

of fertilizing power.

7. That the practical experience obtained during many years at Edinburgh and Milan has shown the great value of sewer-water on grass lands, although applied in a state of great dilution; while valuable experiments have shown the power of soils to remove from solution, and retain for vegetation, the fertilizing elements.

8. That notwithstanding the enormous quantities of sewage-water which have been applied to the land at Edinburgh, the produce is said to be always in corresponding ratio to such quantity, and that the limits of quantity to be applied, and of produce to be realised, have not yet been

ascertained.

9. That the precise value of the manure in a given quantity of sewerwater may be readily determined, and, therefore, that the corresponding quantity of water which must be applied to convey a certain required quantity of such manuring elements on to the land may be at any time known.

10. That although such immense agricultural results have been obtained from irrigation with sewage-water at Edinburgh, the method employed has given rise to much complaint of nuisance. That this arises for the most part from foul deposits in wide ditches, and from the large evaporating surfaces of the sewage constantly exposed in the channels of irrigation.

11. That all such sources of nuisance and danger are preventible, and should not be tolerated. That no ditches should be used, and that the sewage should be exposed only during the act of irrigation of each portion of the land, when it would be immediately absorbed and

deodorized by the soil.

12. That in order to avoid all further risk of injury to health, whether from discharge of the sewage into the rivers and streams, or from its application to the land, it appears desirable that the solid matter should in every case be separated from the liquid sewage at the outfall, and that a cheap, portable manure should be manufactured therefrom for use in the immediate neighbourhood, as practised at Cheltenham. That it should be mixed with the ashes of the town, or such other deodorizing material as may be most suitable for application to the surrounding land, and prepared, if desirable, with other manuring ingredients for particular crops.

13. That it appears probable that such operation will, in most places, pay its own expenses; but that as some such measure is absolutely necessary for the public health, even though involving some expense, it

should be the duty of local boards and other governing bodies to carry it out, just as much as arrangements devolving upon them for removal of dust or other refuse from the town. It should form, in fact, part of

such service, and might be combined in the same contract.

14. That the liquid portion of the sewage, thus cleared of its solid matter, but still retaining its chief value as manure, might then be applied with benefit to the neighbouring lands in any quantity; but that all land upon which this method of application of the sewage is practised should, if not naturally porous, be artificially drained, as the liquid, if allowed to become stagnant, would, as in common irrigation, be likely to engender disease in the neighbouring inhabitants or in cattle exposed to its influence.

15. That the distribution of manures in the liquid state by the hose and jet, from a system of underground pipes on the land, has been found, by the experience of several years upon farms in England and Scotland, most advantageous, and that the outlay for such works is considered by eminent agriculturists who have had experience of their benefits, as a very profitable outlay, irrespective altogether of the question of sewage

distribution.

16. That although the adoption of the the same system at Rugby and other places for the distribution of liquid sewage has been found decidedly successful, the great Edinburgh results are not attainable by this method, unless conjoined with more ample and ready means for getting much larger quantities of sewage on a given area, in less time, and with less labour and expense than can be done with the hose.

17. That upon grass lands, for which the application is best adapted, these larger quantities of the liquid sewage, deprived of its grosser particles, may be economically distributed, especially upon the lower levels, by a combination of the underground pipe system with the subsidiary open irrigation by small contour gutters, practised by Mr. Bickford.

18. That this work, being of a commercial or speculative nature, and not so much required for the safety of the public health, would fall rather within the province of local companies or proprietors than of the local authorities, and to those parties all facilities should be granted for

carrying it out.

19. That the solid sewage manure, prepared and deodorized as above proposed, may be anywhere used, and any quantity of the liquid applied on absorbent or properly drained land, without any risk of injury to health, and without any of the offensiveness constantly experienced from

farmyard and other solid manures applied as top dressings.

20. That in any neighbourhoods, however, where no opportunity exists for this beneficial irrigation, the liquid sewage, before being discharged into rivers or streams, should, after separation of the solid matter, be treated with lime or other deodorizing and precipitating agents; a duty which should devolve upon the Local Board or other governing body, as a precaution in which the public health is materially concerned.

Lastly, that it is an object of immense public concern that the poisonous accumulations of our towns, now fast becoming the sources of pollution of our rivers and streams, should without delay be rendered powerless for further mischief, and applied as nature's law demands for reproductive uses. That by this means the greatest sanitary problem will be solved, and the greatest advancement of agricultural prosperity secured.

In drawing this report to a close, I venture to express a hope that the attention I have been enabled to give to the subject may have added some little to our information; but impressed with its great importance

and its difficulties, extending as it does into so many branches of inquiry, I feel strongly my own inability to do justice to it. It is a subject of study not for engineers alone, but for agriculturists, physiologists, and chemists of the highest attainments and experience.

I have, &c.

Henry Austin,

Chief Superintending Inspector.

Whitehall, March 1857.

Conclusions from the First and Second Reports of the Select Committee on the Sewage of Towns. Dated 10th April 1862.

Analysis of Evidence.

1. The evidence proves that sewage contains the elements of every crop which is grown.

2. That as compared with solid manure there are advantages in the

application of sewage manure to land.

3. The evidence proves that town sewage contains a large amount of heat, which in itself is beneficial in stimulating vegetation.

4. The evidence also proves that the water alone of sewage is of

great benefit for agricultural purposes.

5. The evidence further proves that one ton (224 gallons) of average town sewage contains an amount of manure which, if extracted and dried, would be worth a little over 2d., taking Peruvian guano (at 11l. per ton) as the standard.

6. A judicious use of town sewage permanently improves land.

7. Sewage may be applied to common grass, Italian rye-grass, and also to roots and grain crops, with great advantage, dressings with sewage hastening vegetation.

8. Sewage-grown grass has a great effect in increasing the quantity and richness of the milk of cows, as well as improving the condition of

the cattle, which prefer sewaged grass to all others.

9. The earth possesses the power of absorbing from sewage all the manure which it contains, if the dressings in volume are proportioned to the depth and quality of the soil.

10. Those who use sewage should have full control over it, that they

may apply it when and in what quantities they may require it.

11. Heavy dressings of sewage (8,000 to 9,000 tons per acre) are wasteful; less dressings (500 to 2,000 tons per acre) when more carefully applied, produce better results. The enormous dressings recommended by some witnesses would be agriculturally useless, as the sewage would flow over and off the surface unchanged.

12. When the sewage of our cities, towns, and villages is utilized to the best advantage over suitable areas, little or no imported or manu-

factured manures would be required in such districts.

13. Sewage may be applied with advantage to every description of

soil which is naturally or artificially drained.

- 14. The most profitable returns, as in the case of all other manures, will be obtained when sewage is judiciously applied to the best class of soils.
- Sewage may be advantageously applied to land throughout the entire year.
 - 16. Some matters used in manufactures which enter town sewers,

such as waste acids, would be in themselves injurious if applied to vegetation; but bearing as they do so small a proportion to the entire volume of sewage into which they are turned, they are rendered harmless.

17. Fresh sewage at the outfall of the sewers, even in the hottest weather, is very slightly offensive; and if applied to the land in this state, in such dressings as can at once be absorbed by the earth, fear of nuisance need not be felt, as the soil possesses the power to deodorize and separate from liquids all the manure which they contain.

18. Large dressings and an over-taxed soil may pollute surface

streams, subsoils, and shallow wells.

19. Solid manure cannot be manufactured from town sewage with commercially profitable results.

REPORT on the RESULTS of the SOCIETY OF ARTS CONFERENCE ON HEALTH and SEWAGE of TOWNS, June 1876.

Conclusions.

The chairman of the Conference and the Executive Committee, after having carefully considered the information furnished from the various localities as well as the facts brought forward during the Conference, have to submit the following as the conclusions to which such information

appears to lead :---

1. In certain localities where land at a reasonable price can be procured with favourable natural gradients, with soil of a suitable quality and in sufficient quantity, a sewage farm, if properly conducted, is apparently the best method of disposing of water-carried sewage. It is essential, however, to bear in mind that a profit should not be looked for by the locality establishing the

sewage farm, and only a moderate one by the farmer.

2. With regard to the various processes based upon subsidence, precipitation, or filtration, it is evident that by some of them a sufficiently purified effluent can be produced for discharge without injurious result into water-courses and rivers of sufficient magnitude for its considerable dilution; and that for many towns where land is not readily obtained at a moderate price those particular processes afford the most suitable means of disposing of water-carried sewage. It appears, further, that the sludge, in a manurial point of view, is of low and uncertain commercial value, that the cost of its conversion into a valuable manure will preclude the attainment of any adequate return on the outlay and working expenses connected therewith, and that means must therefore be used for getting rid of it without reference to possible profit.

3. In towns where a water-carried system is employed, a rapid flow, thorough ventilation, a proper connexion of the house drains and pipes with the sewers, and their arrangement and maintenance in an efficient condition, are absolutely essential as regards health; hitherto sufficient precautions have rarely been taken for efficiently

ensuring all the foregoing conditions.

4. With regard to the various dry systems where collection at short intervals is properly carried out, the result appears to be satisfactory, but no really profitable application of any one of them appears as yet to have been accomplished.

5. The old midden or privy system, in populous districts, should be

discontinued, and prohibited by law.

6. Sufficient information was not brought forward at the Conference to enable the Committee to express an opinion in regard to any

of the foreign systems.

7. It was conclusively shown that no one system for disposing of sewage could be adopted for universal use; that different localities require different methods to suit their special peculiarities, and also that, as a rule, no profit can be derived at present from sewage utilization.

8. For health's sake, without consideration of commercial profit,

sewage and excreta must be got rid of at any cost.

The Executive Committee, whilst abstaining from submitting any extensive measures, have no hesitation in recommending that the prevention of dangerous effects from sewage gases should receive the immediate attention of the Legislature, and they submit the following

resolutions as the basis of petitions to Parliament:—

1. That the protection of public health from typhoid and other diseases demands that an amending Act of Parliament be passed, as soon as possible, to secure that all house drains connected with public sewers in the metropolis and towns having an urban authority should be placed under the inspection and control of local sanitary authorities, who shall be bound to see to the effective construction and due maintenance of all such house drains, pipes, and connexions. Provisions having this object in view already exist in the Act constituting the Commissioners of Sewers in the City of London, in the Metropolis Local Management Act, 1855, and in the Public Health Act, 1875, but practically they seem scarcely sufficient for the purpose.

2. That plans of such drains and connexions be deposited in the charge of the respective local authorities, who shall be bound to exhibit them and supply copies of them to the public on payment

of a moderate fee.

3. That the owners of houses be compelled by law to send to the respective local authorities, within a specified time after the passing of the Act, plans of all house drains on an appointed scale.

Signed by—

The Right Hon. James Stanfield, M.P., Chairman of the Conference.

LORD ALFRED S. CHURCHILL, Chairman of the Council.

F. A. Abel, F.R.S., President of the Chemical Society.

SIR HENRY COLE, K.C.B.


Capt. Douglas Galton, R.E., C.B., F.R.S.

Lieut.-Colonel E. F. Du-Cane, R.E. C.B., Surveyor General of Prisons.

Members of the Executive Committee.

LONDON:

Printed by George E. Eyre and WILLIAM SPOTTISWOODE, Printers to the Queen's most Excellent Majesty. For Her Majesty's Stationery Office.



LIBRAR



