A text-book of pharmacology, therapeutics and materia medica / by T. Lauder Brunton ; adapted to the United States Pharmacopoeia by Francis H. Williams.

Contributors

Brunton, Thomas Lauder, Sir, 1844-1916.
Williams, Francis H. 1852-1936.
University of Leeds. Library

Publication/Creation

London : Macmillan, 1887.

Persistent URL

https://wellcomecollection.org/works/fps99xbv

Provider

Leeds University Archive

License and attribution


This material has been provided by This material has been provided by The University of Leeds Library. The original may be consulted at The University of Leeds Library. where the originals may be consulted.
This work has been identified as being free of known restrictions under copyright law, including all related and neighbouring rights and is being made available under the Creative Commons, Public Domain Mark.

You can copy, modify, distribute and perform the work, even for commercial purposes, without asking permission.

wellcome collection

Wellcome Collection
183 Euston Road
London NW1 2BE UK
T +44 (0)20 7611 8722
E library@wellcomecollection.org
https://wellcomecollection.org

The University Library
Leeds



Medical and Dental
Library

STACK
QV 4
BRU


30106 004075999

Digitized by the Internet Archive
in 2015

https://archive.org/details/b21507211

MEDICAL DEPARTMENT
YORKSHIRE COLLEGE
VICTORIA UNIVERSITY

PHARMACOLOGY, THERAPEUTICS AND MATERIA MEDICA

A TEXT-BOOK

OF

PHARMACOLOGY, THERAPEUTICS

AND

MATERIA MEDICA

BY

T. LAUDER BRUNTON, M.D., D.Sc., F.R.S.

FELLOW OF THE ROYAL COLLEGE OF PHYSICIANS; ASSISTANT-PHYSICIAN AND LECTURER ON MATERIA MEDICA AT ST BARTHOLOMEW'S HOSPITAL; EXAMINER IN MATERIA MEDICA IN THE UNIVERSITIES OF OXFORD AND OF LONDON; LATE EXAMINER IN THE UNIVERSITY OF EDINBURGH, IN THE VICTORIA UNIVERSITY, AND IN THE ROYAL COLLEGE OF PHYSICIANS, LONDON

ADAPTED TO THE

United States Pharmacopoeia

BY

FRANCIS H. WILLIAMS, M.D. BOSTON, MASS.

THIRD EDITION

London

MACMILLAN AND CO.

AND NEW YORK

1887

The right of translation is reserved

PRINTED BY
SPOTTISWOODE AND CO., NEW-STREET SQUARE
LONDON

UNIVERSITY OF LEEDS
MEDICAL LIBRARY.

600041

UNIVERSITY OF LEEDS MEDICAL AND DENTAL LIBRARY

TO

The Memory of

SIR ROBERT CHRISTISON, BART. &c.

HIS HONOURED TEACHER

AND TO

CARL LUDWIG

HIS BELOVED MASTER

THIS BOOK IS GRATEFULLY DEDICATED

BY

THE AUTHOR

PREFACE

TO

THE THIRD EDITION.

The rapid exhaustion of the second edition of this work has prevented me from making as many improvements in the present edition as I could have desired. At the same time I have tried, as far as the short time at my disposal would allow, to amend the imperfections of former editions, as well as to bring the work up to date and render it more useful by the introduction of new matter.

The treatment of one of the most important portions of Pharmacology, viz. the Connection between Chemical Constitution and Physiological Action, is still very meagre, because I find that the size of this work would be too much increased were I to treat the subject fully, and I am therefore preparing a small text-book upon it.

The struggle for existence between microbes and the living organism, which in the first edition was only illustrated by a single diagram of a bacillus and amœba, is now fully illustrated by woodcuts copied from Metschnikoff's paper. The views of Hughlings Jackson on the nervous system have been illustrated by a diagram which, when covered with successive layers of thin and semi-transparent paper, exhibits the effect of anæsthetics and narcotics in successively abolishing various faculties. The recent work of Kühne and Politzer on the mode of action of curare has been noticed, and the pathology of tremor discussed. The section on the action of drugs upon the eye has been carefully revised. The section on antipyretics has been rendered somewhat fuller, and some diagrams illustrating the pathology of fever and the mode of action of antipyretics have been introduced; but it is very difficult in the present state of our knowledge to deal satisfactorily with this subject. Paragraphs on the

treatment of cough and on the pathology and treatment of asthma have been introduced. The researches of Adami on diuretics have been noticed, but they have not necessitated any essential change in the text, as the communication between the portal vein of the kidney and the renal artery had been already allowed for in describing Nussbaum's researches in the first edition. The views expressed in the first edition regarding the mode of action of caffeine have been confirmed and extended by the observations of Schroeder and Munk. The researches of Jendràssik on the diuretic action of calomel and the explanation advanced by Locke have been noticed.

The arrangement of the Vegetable Materia Medica has been almost entirely remodelled on Hooker's plan, and a short introduction has been added to it, in which I have tried to show the use of botanical arrangement, as well as to protest against the abuse of it in the examination of students in Materia Medica.

By the use of small type for matters which are of practically little interest to general students, and yet are occasionally wanted for reference, a certain amount of space has been gained, at the same time that the general student is enabled at a glance to distinguish the parts which are of little or no interest to him. Notwithstanding my efforts to condense it, the present edition contains about 120 pages more than the second, but by using thinner paper the bulk of the volume has been little, if at all, increased.

The General Index has been carefully revised. The Index of Diseases and Remedies has been revised to a certain extent, but it still remains a mere skeleton of what it ought to be. It is little more than a list of drugs which have been recommended by somebody or other at some time or other in the treatment of certain diseases. In a few instances the conditions supposed to indicate the use of one drug in preference to another have been given, but I have not yet been able to sift the statements which have been made regarding the different drugs. The only use of the Index at present is simply to remind the practitioner who is treating a disease of the names of drugs which have been proposed as remedies for it. Thus, under the head of Hydrophobia I have mentioned a number of remedies which have been used or proposed, because those who may have to treat a case of this disease may wish to try some remedy, although my own experience leads me to think that almost all well-marked cases will have a fatal issue whatever the drugs employed may be.

The idea of a Therapeutic Index was taken from that in Ringer's 'Therapeutics,' and I wished to make one still more full and complete by comparing his index with those of Bartholow and H. C. Wood, with Waring's 'Therapeutics,' and with the wonderful 'Medical Digest' of Dr. Neale. After I had begun to do this, I found that a similar idea had occurred to Dr. S. O. L. Potter, who had already published an index of 'Comparative Therapeutics,' in which he gave a list of remedies taken from the works of Aitken, Bartholow, Niemeyer, Phillips, Piffard, Ringer, Stillé, Tanner, Trousseau, H. C. Wood, Waring, and some others. After finding that Dr. Potter had already compared together more works than I expected to do, I used his list, along with Naphey's 'Medical Therapeutics' and Neale's 'Medical Digest,' in preparing my Index. I was unable, however, even with the aid of these works, to make the Index anything more than a mere list of names, excepting in a few instances. So imperfect was it, indeed, that up to the last moment I intended to cancel it, and would have done so had not a case occurred in my own practice which showed me that even a mere list of drugs may sometimes be desirable. I was not unmindful of the old adage that 'Fools and children should not see half-done things,' but I felt confident that the majority of my readers would not belong to either of these classes, and so I allowed the Index to remain. My intention to cancel it, however, led me to omit an acknowledgment of my indebtedness to Dr. Potter, and I have pleasure in acknowledging it now.

My use of Dr. Potter's book has led me to include in the Therapeutic Index one remedy which the homœopaths claim as theirs. His book contains a list of remedies taken from homœopathic works as well as from those I have already named. The two classes of remedies are kept apart in different columns; but I find that, in one instance at least, the amanuensis whom I employed to copy out a number of the drugs from Dr. Potter's book has made a mistake in the column, and has taken 'Apis' as a remedy for tonsillitis from the Homœopathic column. To the best of my knowledge this is the only remedy I have taken from a homœopathic source. If any other remedies claimed as 'homœopathic' have been introduced, they have, I think, been copied from the works of one or other of the authors already mentioned, and in Dr. Phillips's work there are some remedies mentioned without references. But as I intended up to the last moment to cancel the whole list, my revision of it was hasty and

imperfect; and as I omitted to expurgate 'Apis,' I may also possibly have overlooked other remedies. If any such omission has occurred I am sincerely sorry, and I can assure the homœopaths that it is perfectly unintentional.

Perhaps it may be well to take this opportunity of saying a few words in regard to homœopathic remedies and homœopathy generally.

The mere fact that a drug in small doses will cure a disease exhibiting symptoms similar to those produced by a large dose of the drug does not constitute it a homœopathic medicine, for this rule was known to Hippocrates, and the rule *similia similibus curantur* was recognised by him as true in some instances. But Hippocrates was not a homœopath, and he recognised the fact that, while this rule was sometimes true, it was not invariably so.

It seems to me that, in founding the system of homœopathy, Hahnemann has proceeded with his facts as he did with his medicines—diluting his active drugs with inert matter, and diluting his facts with much nonsense.

In what I am about to say, I may be to some extent open to correction, for I cannot claim to know his doctrines so thoroughly as those who believe in and follow him. So far, however, as I know his doctrines, it seems to me that they consist in raising the rule *similia similibus curantur* to the rank of a regular law; in claiming a curative power for infinitesimal doses, and in believing that the diminution in the dose of the drug was made up for by the potency conferred upon it through prolonged trituration. It is no doubt true that in some instances the power of a drug may be increased by trituration, inasmuch as fine subdivision either makes it more easily absorbed or alters its chemical composition, as in the case of mercurial compounds, where the prolonged exposure to the air and friction involved in the trituration may greatly increase the power of the drug by oxidising it, and changing it from a mercurous to a mercuric salt. But in both cases the increased activity conferred upon the drug is strictly limited, although it may be great in the case of the salts of mercury. To suppose it to be exerted *ad infinitum* is sheer nonsense, and the absurdity of infinitesimal doses has been so often demonstrated that it is useless to say more about it.

I think one is justified in describing Hahnemann's experiment with cinchona bark as the foundation-stone of his doctrine of homœopathy; for Dr. Nankivell, in his Presidential Address to

the British Homœopathic Congress at Norwich, says, with regard to the action of quinine in ague, that 'it was this very instance of successful empirical treatment, of specific medicinal action, that led Hahnemann first to investigate the actions of drugs on the healthy human frame, and thus to lay the foundation of the most complete and lucid system of scientific therapeutics that the world has yet seen.' But I have shown in the body of this work (p. 52) that, although Hahnemann's observations were in all probability perfectly correct, the conclusions he drew from them were utterly erroneous.

But there is another side to the question which I think it is only fair to consider also. While Hahnemann's theory was certainly bad, there can, I think, be little doubt that he, like Paracelsus and Priessnitz, has done good service to medical practice. Paracelsus gathered information from shepherds, wise women, and quacks of all sorts, and thereby obtained a knowledge of popular remedies, not generally employed by the profession, but which were nevertheless useful.

Priessnitz did not invent the use of cold water as a remedy, for it was known nearly eighteen hundred years before his time. Musa saved the life of Augustus by the cold bath, but, not knowing exactly how and when to employ it, he killed the nephew of the Emperor by it, and such failures brought the treatment by water into discredit. Priessnitz revived it, and now in the use of cold sponging, wet packs, baths and douches we have a powerful means of treating fever and curing disease.

Hahnemann also did good, and the system which he founded has done great service by teaching us the curative power of unaided Nature, the use of diet and regimen in treating disease, and the more than inutility, the actual hurtfulness, of powerful drugs in many instances. The physician is bound to do the very utmost he can for his patient, and his very anxiety has frequently led him to do harm. He has been afraid to leave the cure of disease to Nature, and by the administration of powerful drugs has frequently injured instead of benefited his patient. The use of infinitesimal doses which could not affect the body of the patient one way or the other, but kept the mind of both patient and physician easy, and allowed the *vis medicatrix naturæ* free scope, has helped us to a more perfect knowledge of the natural course of disease. The use of infinitesimal doses has also led to much care being bestowed by those who use them upon diet and regimen. When a physician administered a large dose

of tartar emetic or of salts and senna, he knew that his remedies would produce vomiting or purgation respectively with considerable certainty, whatever the diet or regimen of the patient might be; but the case was quite different with infinitesimal doses. If a patient was being treated with *carbo vegetabilis* in the thirtieth dilution, the utmost care was necessary in regard to his diet, for if he happened to eat a single piece of burned toast at breakfast, he would consume at the one meal as much vegetable charcoal as would, when properly diluted, have served him for medicine during the remainder of his natural life.

Moreover, the homœopathic practice of giving only one drug has tended greatly to diminish the practice of polypharmacy, and the tinctures, powders, and globules they employ show us a good example in regard to the administration of remedies in an agreeable form. But, although this mode of practice may be employed by homœopaths, it is not homœopathic. We are not homœopaths because we use a single drug at a time and give half an ounce of infusion of digitalis to a patient suffering from heart-disease without thinking it necessary to mix it with broom, squill, or spirit of nitrous ether. Nor are we homœopaths because we use 1–50th of a grain of digitalin instead of the infusion of digitalis. Nor are we homœopaths even if we get a manufacturing chemist to make up the digitalin into a globule with a quarter of a grain of sugar of milk instead of with five grains of extract of liquorice. Nor do we become homœopaths merely because we may employ a small dose instead of a large one, and begin with ten drops of the infusion of digitalis instead of half an ounce.

It is not the use of a single drug at a time, of a small dose, of a globule, nor even, as we have already seen, of a drug which may produce symptoms similar to those of the disease, that constitutes homœopathy. The essence of homœopathy, as established by Hahnemann, lies in the infinitesimal dose and the universal application of the rule *similia similibus curantur*. But the infinitesimal doses are so absurd that I believe they have been discarded by many homœopaths. To such men all that remains of homœopathy is the universality of the rule *similia similibus curantur*, and the only difference between them and rational practitioners lies in the fact that the latter regard the rule as only of partial application. At first sight this difference may seem to be only slight, but it is not so in reality; for while the rational practitioner, refusing to be bound by any 'pathy,' whether it be allopathy, antipathy, or homœopathy, seeks to

trace each symptom back to the pathological change which caused it, and, by a knowledge of the action of drugs on each tissue and organ of the body, to counteract these pathological changes, the homœopath professes to be in possession of a rule which will enable him to select the proper remedy in each case by a consideration of the symptoms, without reference to the pathological condition. He may thus dispense with anatomy, physiology, pathology, and pharmacology. All that is necessary is a list of morbid symptoms on the one hand, and a list of the symptoms produced in healthy men by various drugs on the other.

It is the falsity of the claim which homœopathy makes to be in possession, if not of the universal panacea, at least of the only true rule of practice, that makes homœopathy a system of quackery; yet this arrogant claim constitutes the essence of the system, and the man who, leaving Hahnemann and going back to Hippocrates, regards the rule *similia similibus curantur* as only of partial and not of universal application, has no longer any right to call himself a homœopath.

Yet we hear some leading homœopaths say, 'We do not claim any exclusiveness for our method,' [1] and then complain that they are excommunicated by the medical profession. If they have renounced the errors of Hahnemann's system, they ought not to retain its name, but frankly acknowledge their error and return to rational medicine, of which Hippocrates is regarded as the father. As a medical man is bound to do his utmost for the good of his patient, it is obvious that, although he may employ baths or packs as a mode of treatment, he cannot, without becoming untrue to his profession, throw aside all other means of treatment and become a hydropath; nor can he consult on equal terms with those who, either through ignorance or wilful blindness, deny the use of other means of cure and limit themselves to the application of water. What is true of hydropathy is true of homœopathy. I dislike controversy extremely, and should not have taken up so much of the preface with controversial matter had I not been forced to defend myself by the attacks which certain homœopaths have made upon me.

I may now turn to the pleasanter task of acknowledging my indebtedness to many friends who have helped me in the preparation of this edition. In addition to some of those who helped me with former editions, I have to thank Dr. Hughlings

[1] Preface by Richard Hughes to *The Medical Treatment of our Time*. London: Unwin Brothers, Ludgate Hill.

Jackson for assistance in the construction of the diagram which illustrates his views of the nervous system; Mr. W. H. Jessop and Mr. Tweedy for much aid and many suggestions in revising the section on diseases of the eye; and I am especially grateful to my friend, Dr. Thin, who has greatly added to the value of the book by writing an account of the uses of various remedies in skin diseases. I am indebted to Mr. Whitehead, Dr. Halliburton, and especially to Dr. Sidney Martin, for their assistance in passing this edition through the press. To Dr. Martin I am also indebted for many valuable suggestions, and for such an amount of help that, but for him, the preparation of this edition would certainly have been delayed for many months.

T. LAUDER BRUNTON.

March, 1887.

PREFACE

TO

THE FIRST EDITION.

Some apology is required for the long delay in the appearance of this work, for a number of years have now elapsed since it was advertised as being in the press. More than fifteen years ago, I had a work on *Materia Medica* completely written out and ready for the printer. Some time afterwards, all the arrangements had been made for its publication, and in the course of a few weeks it was to have been issued from the press. Just as I was about to send it to the printer, however, I asked for a little delay in order that I might make some improvements and remove some redundancies, for the work as it then stood was considerably larger than the present one.

As I went through it, I found so many unsatisfactory statements and uncertainties regarding the mode of action of drugs, which I thought I could decide by a few experiments, that I wished for a little time in order that those doubtful points might be settled; but as I went on the labour grew, other engagements became pressing, and longer and longer delay was required. From greater experience as a teacher and examiner also, I came to the conclusion that the plan of the work might be altered with advantage; and so finally the whole manuscript was thrown aside, and the book entirely re-written.

In the original work I discussed the physiological and therapeutical actions of each drug separately, in the same way as in the third part of the present work, though on a much more extended scale. I found, however, that this plan necessitated a good deal of repetition regarding the experimental methods by which the action of the drugs had been ascertained.

Moreover, the physician does not want to know only what the actions of any one drug are; he rather requires a knowledge of

classes of drugs, and of the manner in which the actions of the individual members of a class differ from each other. He requires, in fact, a knowledge of the ways in which the various functions of the body can be influenced by drugs both in health and disease, in order that he may restore health to his patients.

It has appeared to me, therefore, better to devote a complete section of the work to a discussion of the methods by which the action of drugs is determined; to the manner in which each function of the body can be modified by drugs; and to the general *rationale* of the use of drugs in disease, *i.e.* to devote a section to general pharmacology and general therapeutics.

Considerable experience both in teaching and examining has shown me that students sometimes find a difficulty in applying physiology to pharmacology and therapeutics, and I find that many others are, like myself, apt to forget those parts of physiology which they are not constantly studying. I have therefore thought it well, for the sake both of students and practitioners, to give a short account of the normal functions of the different parts of the body, before proceeding to discuss the alterations which are produced in them by drugs, or which they undergo in disease. In the case of the heart and the kidneys also, where the action of drugs is complicated and difficult, I have found it necessary to enter a little more fully into the physiology of these organs than is done in the ordinary text-books.

I have found that a similar difficulty occurs with pathology as with physiology, and I have therefore occasionally discussed pathological questions when I have thought that by doing so I could render the action of drugs in disease more intelligible, and thus aid the student of rational therapeutics.

In the second part of the work on general pharmacy, I have classed together the various pharmaceutical preparations, and given lists of them for reference. It is by no means my intention that these should be learned by heart by any student, and indeed I think it is well to take this opportunity of protesting against the injustice of the demands which are sometimes made upon the memories of students.

It is probable that the majority of the best and most successful practitioners would be very much puzzled if they were required to state the exact quantity of every ingredient in each pill or each ointment that they prescribe, or the exact quantity of the crude drug from which the infusions or tinctures which they use have been made. They know the action of the pill or ointment, they

know the action of the infusion or tincture, and they do not trouble themselves about details which are only useful to the chemist who is making up the preparation.

It is very greatly to be regretted, for it is a stumbling-block in the way of true progress, that students who have afterwards to become medical practitioners and not pharmaceutical chemists, should be asked at examinations the quantities of crude drugs from which particular preparations are made—quantities which even the manufacturing chemist himself would never dream of carrying in his memory, but would obtain by reference to his books whenever he required them. As the late Professor Sharpey used very truly to say, 'You may as well require of a medical student a knowledge of the whole art of cutlery before you set him to dissect.' Medical science is now advancing in every direction, and unless we cut off some of the less useful kinds of information, which medical students were formerly obliged to acquire, it becomes impossible for them to learn all that is truly valuable. In Materia Medica we now oblige them to learn the physiological action of drugs, a subject regarding which, until quite recently, little or nothing was known, and to oblige them to learn all this, in addition to what they were formerly expected to know, is to treat them as Pharaoh treated the Israelites, and compel them to make the same number of bricks, while giving them no straw.

I am so much impressed with the necessity of lessening the amount of unnecessary work sometimes required as a preparation for examinations, that at first I omitted from this book all reference to the composition of pharmaceutical preparations. But as it is intended not only as a text-book for students, but also for the use of practitioners, I afterwards considered that it might be convenient to have the composition of some pharmaceutical preparations, at least, for the purpose of reference. I have omitted the composition of such preparations as are like to be got ready-made from a chemist, but have inserted the composition of infusions which often need to be prepared when required. I have also given the composition of various compound pills, but only for the purpose of reference.

In consequence of this change in the plan of the work while it was passing through the press, the preparations of rhubarb have been omitted from their proper place at page 924, and are to be found at page 1005.

In the preparation of this work I have to acknowledge my

obligations to the admirable works of Bartholow, Binz, Buchheim, Dujardin-Beaumetz, Edes, Husemann, Nothnagel and Rossbach, Ringer, Schmiedeberg, and H. C. Wood. Messrs. Chapman, Soutter, Spencer, Spry,[1] Steinthal, Stubbs, Walsh,[1] Wells, and Wright for the excellent notes they took of my lectures; to Dr. D'Arcy Power for the verification of references; to Dr. Mitchell Bruce, Mr. T. W. Shore, and Mr. H. W. Gardner for much kind assistance in the preparation of the work, and to Prof. Matthew Hay, of Aberdeen, whose criticisms and suggestions have been invaluable. To Dr. Francis H. Williams, of Boston, Mass., I am indebted for the adaptation of this work to the United States Pharmacopœia, which by tending to familiarise medical men on each side of the Atlantic with the preparations employed in both countries may, I trust, tend to facilitate the introduction of an International Pharmacopœia.

T. LAUDER BRUNTON.

March, 1885.

[1] These names were inadvertently omitted in the preface to the first edition, but were mentioned in the preface to the second.

Articles and Preparations included in the British Pharmacopœia of 1885, which were not in that of 1867 nor in the 'Additions' of 1874.

Acidum Boricum.
Acidum Carbolicum Liquefactum.
Acidum Chromicum.
Acidum Hydrobromicum Dilutum.
Acidum Lacticum.
Acidum Lacticum Dilutum.
Acidum Meconicum.
Acidum Oleicum.
Acidum Phosphoricum Concentratum.
Acidum Salicylicum.
Alcohol Ethylicum.
Aloin.
Anisi Fructus.
Anisi Stellati Fructus.
Apomorphinæ Hydrochloras.
Aqua Anisi.
Argenti et Potassii Nitras.
Arsenii Iodidum.
Bismuthi Citras.
Bismuthi et Ammonii Citras.
Butyl-Chloral Hydras.
Caffeina.
Caffeinæ Citras.
Calamina Preparata.
Calcii Sulphas.
Calx Sulphurata.
Chrysarobinum.
Cimicifugæ Rhizoma.
Cinchonidinæ Sulphas.
Cinchoninæ Sulphas.
Coca.
Cocainæ Hydrochloras.
Codeina.
Collodium Vesicans.
Cupri Nitras.
Elaterinum.
Ergotinum.
Extractum Belladonnæ Alcoholicum.
Extractum Cascaræ Sagradæ.
Extractum Cascaræ Sagradæ Liquidum.
Extractum Cimicifugæ Liquidum.
Extractum Cocæ Liquidum.
Extractum Gelsemii Alcoholicum.
Extractum Jaborandi.
Extractum Rhamni Frangulæ.
Extractum Rhamni Frangulæ Liquidum.
Extractum Taraxaci Liquidum.
Gelsemium.
Glycerinum Aluminis.
Glycerinum Plumbi Subacetatis.
Glycerinum Tragacanthæ.
Infusum Jaborandi.
Injectio Apomorphinæ Hypodermica.
Injectio Ergotini Hypodermica.
Iodoformum.
Jaborandi.
Lamellæ Atropinæ.
Lamellæ Cocainæ.
Lamellæ Physostigminæ.
Liquor Acidi Chromici.
Liquor Ammonii Acetatis Fortior.
Liquor Ammonii Citratis Fortior.
Liquor Arsenii et Hydrargyri Iodidi.
Liquor Calcii Chloridi.
Liquor Ferri Acetatis.
Liquor Ferri Acetatis Fortior.
Liquor Ferri Dialysatus.
Liquor Morphinæ Bimeconatis.
Liquor Sodii Ethylatis.
Lupulinum.
Menthol.
Morphinæ Sulphas.
Oleatum Hydrargyri.
Oleatum Zinci.
Oleo-Resina Cubebæ.
Oleum Eucalypti.
Oleum Pini Sylvestris.
Oleum Santali.

Paraffinum Durum.
Paraffinum Molle.
Physostigmina.
Pilocarpinæ Hydrochloras.
Potassii Cyanidum.
Quininæ Hydrochloras.
Rhamni Frangulæ Cortex.
Rhamni Purshiani Cortex.
Salicinum.
Sodii Bromidum.
Sodii Iodidum.
Sodii Salicylas.
Sodii Sulphis.
Sodii Sulphocarbolas.
Sodium.
Spiritus Ætheris Compositus.
Spiritus Cinnamomi.
Staphisagriæ Semina.
Suppositoria Iodoformi.
Tabellæ Nitroglycerini.
Thymol.
Tinctura Chloroformi et Morphinæ.
Tinctura Cimicifugæ.
Tinctura Gelsemii.
Tinctura Jaborandi.
Tinctura Podophylli.
Trochisci Acidi Benzoici.
Trochisci Santonini.
Unguentum Acidi Borici.
Unguentum Acidi Carbolici.
Unguentum Acidi Salicylici.
Unguentum Calaminæ.
Unguentum Chrysarobini.
Unguentum Eucalypti.
Unguentum Hydrargyri Nitratis Dilutum.
Unguentum Iodoformi.
Unguentum Staphisagriæ.
Unguentum Zinci Oleati.
Vapor Olei Pini Sylvestris.
Zinci Sulphocarbolas.

Articles and Preparations included in the British Pharmacopœia of 1867 or in the 'Additions' of 1874, but omitted in the British Pharmacopœia of 1885.

Areca.
Cadmii Iodidum.
Castoreum.
Decoctum Ulmi.
Digitalinum.
Dulcamara.
Enema Tabaci.
Ferri Iodidum.
Ferri Oxidum Magneticum.
Ferri Peroxidum Humidum.
Hydrargyri Iodidum Viride.
Infusum Dulcamaræ.
Liquor Atropiæ.
Mistura Gentianæ.
Pilula Quiniæ.
Rhamni Succus.
Sodæ Acetas.
Stramonii Folia.
Syrupus Rhamni.
Tinctura Castorei.
Ulmi Cortex.
Unguentum Cadmii Iodidi.

Articles and Preparations the Names of which have been altered.

Former Names, 1867 or 1874.	Present Names, 1885.
Aconitia	Aconitina.
Albumen Ovi	Ovi Albumen.
Ammoniæ Benzoas	Ammonii Benzoas.
Ammoniæ Carbonas	Ammonii Carbonas.
Ammoniæ Nitras	Ammonii Nitras.
Ammoniæ Phosphas	Ammonii Phosphas.
Arnicæ Radix	Arnicæ Rhizoma.

Former Names, 1867 or 1874.	Present Names, 1885.
Assafœtida	Asafœtida.
Atropia	Atropina.
Atropiæ Sulphas	Atropinæ Sulphas.
Berberiæ Sulphas	Beberinæ Sulphas
Calcis Carbonas Præcipitata	Calcii Carbonas Precipitata.
Calcis Hydras	Calcii Hydras.
Calcis Hypophosphis	Calcii Hydrophosphis.
Calcis Phosphas	Calcii Phosphas.
Calx Chlorata	Calx Chlorinata.
Canellæ Albæ Cortex	Canellæ Cortex.
Cardamomum	Cardamomi Semina.
Cataplasma Sodæ Chloratæ	Cataplasma Sodæ Chlorinatæ.
Catechu Pallidum	Catechu.
Cinchonæ Flavæ Cortex	Cinchonæ Cortex.
Cinchonæ Pallidæ Cortex	Cinchonæ Cortex.
Decoctum Cinchonæ Flavæ	Decoctum Cinchonæ [Rubræ].
Ecbalii Fructus	Ecballii Fructus.
Emplastrum Cerati Saponis	Emplastrum Saponis Fuscum.
Enema Assafœtidæ	Enema Asafœtidæ.
Enema Magnesiæ Sulphatis	Enema Magnesii Sulphatis.
Extractum Cinchonæ Flavæ Liquidum	Extractum Cinchonæ [Rubræ] Liquidum.
Ferri et Ammoniæ Citras	Ferri et Ammonii Citras.
Ferri et Quiniæ Citras	Ferri et Quininæ Citras.
Hydrargyri Sulphas	Hydrargyri Persulphas.
Infusum Cinchonæ Flavæ	Infusum Cinchonæ [Rubræ] Acidum.
Liquor Ammoniæ Acetatis	Liquor Ammonii Acetatis.
Liquor Ammoniæ Citratis	Liquor Ammonii Citratis.
Liquor Atropiæ Sulphatis	Liquor Atropinæ Sulphatis.
Liquor Bismuthi et Ammoniæ Citratis	Liquor Bismuthi et Ammonii Citratis.
Liquor Calcis Chloratæ	Liquor Calcis Chlorinatæ.
Liquor Magnesiæ Carbonatis	Liquor Magnesii Carbonatis.
Liquor Magnesiæ Citratis	Liquor Magnesii Citratis.
Liquor Morphiæ Acetatis	Liquor Morphinæ Acetatis.
Liquor Morphiæ Hydrochloratis	Liquor Morphinæ Hydrochloratis.
Liquor Potassæ Permanganatis	Liquor Potassii Permanganatis.
Liquor Sodæ Arseniatis	Liquor Sodii Arseniatis.
Liquor Sodæ Chloratæ	Liquor Sodæ Chlorinatæ.
Liquor Strychniæ	Liquor Strychninæ Hydrochloratis.
Lithiæ Carbonas	Lithii Carbonas.
Lithiæ Citras	Lithii Citras.
Magnesia	Magnesia Ponderosa.
Magnesiæ Carbonas	Magnesii Carbonas Ponderosa.
Magnesiæ Carbonas Levis	Magnesii Carbonas Levis.
Magnesiæ Sulphas	Magnesii Sulphas.
Morphiæ Acetas	Morphinæ Acetas.
Morphiæ Hydrochloras	Morphinæ Hydrochloras.
Physostigmatis Faba	Phosostigmatis Semen.
Pilula Aloes et Assafœtidæ	Pilula Aloes et Asafœtidæ.
Pilula Assafœtidæ Composita	Pilula Asafœtidæ Composita.
Podophylli Radix	Podophylli Rhizoma.
Potassæ Acetas	Potassii Acetas.
Potassæ Bicarbonas	Potassii Bicarbonas.
Potassæ Bichromas	Potassii Bichromas.

Former Names, 1867 or 1874.	Present Names, 1885.
Potassæ Carbonas	Potassii Carbonas.
Potassæ Chloras	Potassii Chloras.
Potassæ Citras	Potassii Citras.
Potassæ Nitras	Potassii Nitras.
Potassæ Permanganas	Potassii Permanganas.
Potassæ Prussias Flava	Potassii Ferrocyanidum.
Potassæ Sulphas	Potassii Sulphas.
Potassæ Tartras	Potassii Tartras.
Potassæ Tartras Acida	Potassii Tartras Acida.
Quiniæ Sulphas	Quininæ Sulphas.
Serpentariæ Radix	Serpentariæ Rhizoma.
Sodæ Arsenias	Sodii Arsenias.
Sodæ Bicarbonas	Sodii Bicarbonas.
Sodæ Carbonas	Sodii Carbonas.
Sodæ Carbonas Exsiccata	Sodii Carbonas Exsiccata.
Sodæ Citro-tartras Effervescens	Sodii Citro-tartras Effervescens.
Sodæ Hypophosphis	Sodii Hypophosphis.
Sodæ Nitras	Sodii Nitras.
Sodæ Phosphas	Sodii Phosphas.
Sodæ Sulphas	Sodii Sulphas.
Sodæ Valerianas	Sodii Valerianas.
Strychnia	Strychnina.
Suppositoria Morphiæ	Suppositoria Morphinæ.
Suppositoria Morphiæ cum Sapone	Suppositoria Morphinæ cum Sapone.
Tinctura Assafœtidæ	Tinctura Asafœtidæ.
Tinctura Quiniæ	Tinctura Quininæ.
Tinctura Quiniæ Ammoniata	Tinctura Quininæ Ammoniata.
Trochisci Morphiæ	Trochisci Morphinæ.
Trochisci Morphiæ et Ipecacuanhæ	Trochisci Morphinæ et Ipecacuanhæ.
Trochisci Potassæ Chloratis	Trochisci Potassii Chloratis.
Trochisci Sodæ Bicarbonatis	Trochisci Sodii Bicarbonatis.
Unguentum Aconitiæ	Unguentum Aconitinæ.
Unguentum Atropiæ	Unguentum Atropinæ.
Unguentum Veratriæ	Unguentum Veratrinæ.
Valerianæ Radix	Valerianæ Rhizoma.
Vapor Coniæ	Vapor Coninæ.
Veratria	Veratrina.
Veratri Viridis Radix	Veratri Viridis Rhizoma.
Vinum Quiniæ	Vinum Quininæ.

Substitutions.

Antimonium Nigrum Purificatum	*for*	Antimonium Nigrum.
Cinchonæ Rubræ Cortex (in preparations)	,,	Cinchonæ Flavæ Cortex. Cinchonæ Pallidæ Cortex.
Pulvis Elaterini Compositus	,,	Pulvis Elaterii Compositus.
Tinctura Cinchonæ [Rubræ]	,,	Tinctura Cinchonæ Flavæ.
Unguentum Glycerini Plumbi Subacetatis	,,	Unguentum Plumbi Subacetatis Compositum.

Preparations the Composition of which has been altered.

(Minor alterations are not included.)

Acidum Sulphurosum.
Alumen.
Antimonium Sulphuratum.
Extractum Cinchonæ Liquidum.
Infusum Cinchonæ Acidum.
Injectio Morphinæ Hypodermica.
Liquor Epispasticus.
Liquor Iodi.
Oleum Phosphoratum.
Pilula Phosphori.
Pulvis Glycyrrhizæ Compositus.
Tinctura Quininæ.
Unguentum Hydrargyri Ammoniati.
The fatty basis of the four suppositories of B.P. 1867 is now oil of theobroma only.
In some of the ointments paraffins have been substituted for lard.
Scammony Resin has been substituted for Scammony in most preparations of Scammony.

The strengths of the following preparations have been altered from 1 *in* 109 *to* 1 *in* 100.

Liquor Arsenicalis.
Liquor Arsenici Hydrochloricus.
Liquor Atropinæ Sulphatis.
Liquor Morphinæ Acetatis.
Liquor Morphinæ Hydrochloratis.
Liquor Potassii Permanganatis.
Liquor Sodii Arseniatis.
Liquor Strychninæ Hydrochloratis.

CONTENTS.

PAGE

INTRODUCTION 3

SECTION I.

GENERAL PHARMACOLOGY AND THERAPEUTICS.

CHAPTER I.

GENERAL RELATIONS BETWEEN THE ORGANISM AND SUBSTANCES AFFECTING IT, pp. 9–32.

List of Elements 9
Nature of Elements 11
Classification of Elements 15
Mendelejeff's Classification of the Elements 19
Organic Radicals 20
Chemical Reactions and Physiological Reactions 24
Relation between Isomorphism and Physiological Action 26
„ „ Spectroscopic Characters and Physiological Action . . . 27
„ „ Atomic Weight and Physiological Action 28
Connection between Chemical Constitution and Physiological Action . . 30

CHAPTER II.

CIRCUMSTANCES WHICH AFFECT THE ACTION OF DRUGS ON THE ORGANISM, pp. 33–56.

Local and Remote Action 33
Interaction of Various Functions 33
Direct and Indirect Action 34
Selective Action of Drugs 34
Primary and Secondary Action 35
Relation of Effect to Quantity of the Drug 36
Homœopathy 36
Dose 37
Size 37
Mode of Administration 38
Absorption of Drugs 39
Duration of Action 41

PAGE

Cumulative Action 41
Effect of Different Preparations 42
„ Fasting 43
„ Conditions of the Stomach 43
„ Habit 43
„ Temperature 44
„ Climate 48
„ Time of Day 48
„ Season 48
„ Disease 49
Use of Experiments 49
Comparative Pharmacology 50
Idiosyncrasy 51
Experiments upon Healthy Men 51
Fallacies of Experiment upon Man 52
Experiments in Disease 52
Objections to Experiment 53
Erroneous Deductions from Experiments 55

CHAPTER III.

ACTION OF DRUGS ON PROTOPLASM, BLOOD, AND LOW ORGANISMS, pp. 57–108.

Action of Drugs on **Albumin** 57
„ „ **Protoplasmic Movements** 59
Method of Experimentation 59
Amœbæ 60
Leucocytes 61
Effect of Drugs on Leucocytes 61
Movements of Leucocytes in the Blood-vessels 62
„ Red Blood Corpuscles 63
Action of Drugs on Infusoria 63
Relations of Motion and Oxidation 65
Oxidation of Protoplasm 67
Oxygen-carrying Power of Protoplasm 68
Ozonising Power of Protoplasm 69
Action of Drugs on Oxidation 69
Reduction by Protoplasm 70
Action of Drugs on Blood 70
Catalysis—Fermentation—Inorganic Ferments 73
Ferments, Organic and Organised 74
Action of Drugs on Enzymes 76
Zymogens 80
Organised Ferments 80
Yeasts 81
Moulds 82
Bacteria 82
Struggle for Existence between the Organism and Microbes 85
Action of Drugs on the Movements of Bacteria 88
„ „ Reproduction of Bacteria 89
„ „ „ „ Mode of Experimenting on . . 89
„ „ Particular Species of Bacilli 92
„ „ „ „ Mode of Experimenting on . 92

PAGE

Action of Drugs on Development and Growth of Bacilli 95
Influence on Antiseptics of the Solvent 96
" " " Admixture 96
" " " Temperature 96
Alterations in Bacteria by Heat and Soil 96
Possible Identity of different Forms of Bacteria 97
Action of Bacteria and their Products on the Animal Body 98
Alkaloids formed by Putrefaction—**Ptomaïnes** 99
" " " Leucomaïnes 101
Effect of Drugs on the Action of Bacteria in the Animal Body 102
Antiseptics—Antizymotics—Disinfectants—Deodorizers 103
Uses of Antiseptics 104
Disinfectants 106
Deodorizers 106
Antiperiodics 107

CHAPTER IV.

ACTION OF DRUGS ON INVERTEBRATA, pp. 109–116.

Action of Drugs on Medusæ 109
" " Mollusca 114
" " Ascidians 114
" " Annulosa 114

CHAPTER V.

ACTION OF DRUGS ON MUSCLE, pp. 117–143.

Action of Drugs on **Voluntary Muscle** 117
Irritability of Muscle 119
Contraction of Muscle 119
Latent Period of Muscle 120
Summation of Stimuli 122
Contraction of Muscle 122
Fatigue 123
Contracture 124
Tetanus 125
Muscular Poisons 126
Massage 131
Propagation of the Contraction Wave in Muscle 131
Rhythmical Contraction of Muscle 131
Pathology of Tremor 133
Treatment of Tremor 134
Connection between Chemical Constitution and Physiological Action on Muscle 134
Action of Drugs on Muscle is Relative and not Absolute 136
" " on **Involuntary Muscular Fibre** 137
Effect of Stimuli 138
Relation of Contractile Tissue to the Nerves 139
Propagation of Contraction Waves 139
Artificial Rhythm 140
Hypothetical Considerations regarding the Action of Drugs on Muscle . . 141

CHAPTER VI.

ACTION OF DRUGS ON NERVES, pp. 144–158.

PAGE
General Action of Drugs on the Nervous System 144
Action of Drugs on **Motor Nerves** 146
Methods of Experiment 147
Paralysis of Motor Nerve-Endings by Drugs 147
Advantage of the Method of Local Protection 149
Paralysers of Motor Nerves 150
Exact Localisation of the Action of Curare 151
Action of Drugs in Increasing Excitability of Motor Nerves 153
Irritation of Motor Nerve-Endings 154
Action of Drugs on the Trunks of Motor Nerves 154
,, ,, **Sensory Nerves** 155
Local Sedatives and Local Anæsthetics 157
Stimulating Action of Drugs on the Peripheral Ends of Sensory Nerves . . 157

CHAPTER VII.

ACTION OF DRUGS ON THE SPINAL CORD, pp. 159–182.

Action on the Conducting Power of the Cord 159
Action of Drugs on Reflex Action 163
Direct, Indirect, and Inhibitory Paralysis of the Spinal Cord by Drugs . . 164
Indirect Paralysis 164
Direct ,, ... 164
Spinal Depressants and their Uses 165
Inhibitory Paralysis 165
Nature of Inhibition 167
Interference in Nervous Structures 169
Effect of Altered Rate of Transmission 169
Opposite Conditions produce Similar Effects 170
The Same Conditions may cause Opposite Effects 170
Stimulation and Inhibition merely Consequences of Relation 170
Test of the Truth of the Author's Hypothesis regarding Inhibition . . 171
Explanation of the Action of Certain Drugs on this Hypothesis 171
Stimulating Action of Drugs on the Reflex Powers of the Cord . . . 177
Localisation of the Action of Strychnine by Magendie 177
Spinal Stimulants 181

CHAPTER VIII.

ACTION OF DRUGS ON THE BRAIN, pp. 183–215.

Functions of the Brain in the Frog 183
,, ,, ,, Mammals 184
Depressant Action of Drugs on Motor Centres in the Brain 187
Irritant ,, ,, ,, ... 188
Convulsions 188
Action of Drugs on the Sensory and Psychical Centres in the Brain . . 191
Drugs which Increase the Functional Activity of the Brain 192
Nerve Stimulants 192
Cerebral Stimulants 192
Drugs which Lessen the Functional Activity of the Brain 195

PAGE

Hypnotics or Soporifics 196
Narcotics 200
Anodynes or Analgesics 201
Adjuncts to Anodynes 203
Anæsthetics 203
Stages of their Action 206
Uses of Anæsthetics 207
Dangers of Anæsthetics 207
Mode of Administering Anæsthetics 209
Anæsthesia in Animals 210
History of the Discovery of Anæsthesia 211
Antispasmodics 212
Action of Drugs on the Cerebellum 215

CHAPTER IX.

ACTION OF DRUGS ON THE ORGANS OF SPECIAL SENSE, pp. 216–231.

Action of Drugs on the **Eye** 216
" " " Conjunctiva 216
" " " Lacrimal Secretion 217
Projection of the Eyeball 217
Action of Drugs on the Pupil 217
" " " Accommodation 223
" " " Intra-ocular Pressure 224
Uses of Mydriatics and Myotics 225
Action of Cocaine 226
Action of Drugs on the Sensibility of the Eye 227
" " in Producing Visions 228
" " on **Hearing** 228
" " on **Smell** 230
" " on **Taste** 230

CHAPTER X.

ACTION OF DRUGS ON RESPIRATION, pp. 232–261.

Respiratory Stimulants and Depressants 232
Comparative Anatomy of the Respiratory Centre 232
Action of Drugs on the " " 240
" " " Respiratory Nerves 244
Sternutatories or Errhines 245
Pulmonary Sedatives 246
Pathology of Cough 247
Remedies which Lessen Irritation 249
Pulmonary Sedatives 250
Expectorants 250
Action of Drugs on the Bronchial Secretion 252
" " " Expulsive Mechanism 254
Adjuncts 255
Arrest of Colds 256
Selection of Remedies in Treatment of Cough 257
Action of Drugs on the Bronchi 259
Pathology of Bronchial Asthma 259
Treatment of " " 260

CHAPTER XI.

ACTION OF DRUGS ON THE CIRCULATION, pp. 262–339.

PAGE

Arteries and **Veins** 262
Blood-pressure 263
Fainting and Shock 264
Scheme of the Circulation 265
Circulation in the Living Body 267
Mode of Ascertaining the Blood-pressure 268
Fallacies 269
Alterations in Blood-pressure 270
Relation of Pulse-rate and Arterioles to Blood-pressure 271
Effect of the Arterioles on Pulse Curves 275
Investigation of the Action of Drugs on the Arterioles 277
Method of Measurement by Rate of Flow 281
Action of Drugs on Vaso-motor and Vaso-dilating Nerves 283
Action of Other Parts on the Blood-pressure 285
Reflex Contraction of Vessels 285
Action of Drugs on Reflex Contraction of Vessels 286
Comparative Effect of Heart and Vessels on Blood-pressure in Different Animals 287
Influence of Nerves on Blood-pressure 289
Action of the Heart on Blood-pressure 292
Causes of Alteration in Blood-pressure and Pulse-rate 293
Effect of Drugs on the Pulse-rate 295
Action of Drugs on the Cardio-inhibitory Action of the Vagus 295
Reflex Stimulation of the Vagus 296
Causes of Quickened Pulse 297
Action of Drugs on Vagus-Roots 297
Action on Accelerating Nerves 298
Stimulating Effect of Asphyxial Blood on the Medulla 298
Stimulation of the Heart by Increased Blood-pressure 298
Palpitation 299
The **Heart** of the Frog 299
Action of Drugs on the Heart of the Frog 301
" " its Muscular Substance 305
Differences between the Heart Apex and the Heart 308
Action of Drugs on the Vagus of the Frog 310
Action of Drugs on Inhibition of the Heart 310
Theories Regarding the Mode of Action of Drugs on the Heart . . 312
Drugs which Act on the Cardiac Muscle 316
" " " Motor Ganglia 316
" " " Inhibitory Ganglia 317
" " " Vagus-Ends in the Heart 317
" " " Vagus-Centre 317
" " " Accelerating Centre 318
" " " Capillaries 318
" " " Vaso-motor Nerves 318
" " " " Centre 319
Stannius's Experiments 319
General Considerations regarding the Heart 322
Regulating Action of the Nervous System 324

PAGE
Hypothesis regarding the Action of the Vagus 325
Inhibition in the Heart 326
Therapeutic Uses of Drugs acting on the Circulation 328
Cardiac Stimulants 328
Vascular ,, ... 330
Cardiac Tonics 331
Risks attending the Administration of Digitalis and other Cardiac Tonics . 335
Vascular Tonics 335
Pathology of Dropsy 336
Cardiac Sedatives 338
Vascular ,, ... 339

CHAPTER XII.

REMEDIES ACTING ON THE SURFACE OF THE BODY, pp. 340–351.

Irritants and Counter-irritants 340
Rubefacients 344
Vesicants 345
Pustulants 346
Caustics 346
Emollients and Demulcents 347
Astringents 349
Styptics 350

CHAPTER XIII.

ACTION OF DRUGS ON THE DIGESTIVE SYSTEM, pp. 352–409.

Action of Drugs on the Teeth 352
,, ,, ,, **Salivary Glands** 353
Sialagogues 353
,, Reflex 357
,, Mixed 357
,, Specific 357
Excretion by the Saliva 358
Refrigerants 360
Pathology of Thirst 360
Anti-sialics 360
Action of Drugs on the **Stomach** 361
Gastric Tonics 361
Appetite 362
Action of Drugs on Secretion in the Stomach 363
,, ,, the Movements of the Stomach 365
Absorption from the Stomach 368
Antacids 369
Emetics 370
Anti-emetics and Gastric Sedatives 376
Carminatives 378
Action of Drugs on the **Intestines** 379
Intestinal Movements and Secretion 379
Paralytic Secretion 380
Constipation 384
Action of Drugs on Absorption from the Intestines 386
Intestinal Astringents 387

PAGE
Purgatives 389
Action of Purgatives 390
Uses of Purgatives 394
Action of **Irritant Poisons** 395
Peculiarities in the Action of different Irritant Poisons 397
Secondary Effects of Irritant Poisoning 398
Action of Drugs on the **Liver** 399
Hepatic Stimulants 402
Cholagogues 404
Adjuncts to Cholagogues 406
Uses of Hepatic Stimulants and Cholagogues 407
Hepatic Depressants 407
Action of Drugs on the **Pancreas** 407
Anthelmintics 408

CHAPTER XIV.

DRUGS ACTING ON TISSUE-CHANGE, pp. 410–421.

Tonics 410
Hæmatinics 412
Alteratives 413
Antipyretics—Febrifuges 416

CHAPTER XV.

ACTION OF DRUGS ON EXCRETION, pp. 422–446.

Action of Drugs on the **Kidneys** 422
Circumstances Modifying the Secretion of Urine 427
Mode of Action of Diuretics 431
Adjuvants to Diuretics 434
Action of Drugs on Albuminuria 434
Lithontriptics 436
Action of Drugs on the **Skin** 437
Diaphoretics and Sudorifics 437
Excretion by the Sweat Glands 439
Relation between Sweat Glands and Kidneys 439
Action of the Skin in Regulating Temperature 440
Antihidrotics or Anhidrotics 441
Pathology of Night Sweats 442
Action of Drugs on the **Bladder** 443
Urinary Sedatives and Astringents 445

CHAPTER XVI.

ACTION OF DRUGS ON THE GENERATIVE SYSTEM, pp. 447–456.

Aphrodisiacs and Anaphrodisiacs 447
Aphrodisiacs 449
Anaphrodisiacs 451
Emmenagogues 452
Ecbolics 454
Action of Drugs upon the Mammary Glands 455

CHAPTER XVII.

METHODS OF ADMINISTERING DRUGS, pp. 457–485.

PAGE

Application of Drugs by the Skin 457
Epidermic Application 457
Baths 459
Cold Bath 460
„ Pack 463
„ Sponging 463
„ Douches 463
Local Application of Cold 464
Cold Sitz Bath 464
„ Foot Bath 464
„ Compresses 464
Tepid Baths 466
Warm „ 466
Hot „ 467
„ Foot Bath 467
„ Sitz Bath 467
Poultices 468
Medicated Baths 469
Sea-bathing 469
Carbonic-acid Bath 469
Acid Bath 469
Alkaline Bath 470
Sulphurous Bath 470
Mustard Bath 470
Pine Bath 470
Vapour Baths 470
Calomel Fumigation 471
Air Baths—Turkish Bath 471
Friction and Inunction 472
Massage 472
Inunction 473
Endermic Application of Drugs 474
Hypodermic Administration of Drugs 474
Objections to Hypodermic Injections 476
Application of Drugs to the Eye 477
„ „ Ear 477
„ „ Nose 478
„ „ Larynx 479
„ „ Lungs 481
„ „ Mouth and Pharynx 482
Masticatories—Gargles 482
Application of Drugs to the Stomach 482
Stomach-pump 483
Gastric Syphon 483
Application of Drugs to the Intestine 484
Enemata 484
Suppositories 484
Application of Drugs to the Urethra 484
„ „ Vagina and Uterus 485

CHAPTER XVIII.

ANTIDOTES, pp. 486–491.

PAGE

Antidotes to Poisonous Gases 486
„ Acids 487
„ Alkalies 487
„ Alkaloids, &c. 488

CHAPTER XIX.

ANTAGONISTIC ACTION OF DRUGS, pp. 492–496.

CHAPTER XX.

DOSAGE, p. 497.

SECTION II.

GENERAL PHARMACY.

CHAPTER XXI.

PHARMACEUTICAL PREPARATIONS, pp. 501–534.

Abstracta—Abstracts 503
Aceta—Vinegars 503
Alkaloidea—Alkaloids 503
Aquæ—Waters 505
Cataplasmata—Poultices 506
Cerata—Cerates 506
Chartæ—Papers 506
Collodia—Collodions 507
Confectiones—Confections—Electuaries 507
Decocta—Decoctions 507
Elixiria—Elixirs 508
Emplastra—Plasters 508
Enemata—Injections—Enemas—Clysters 508
Essentiæ—Essences 509
Extracta—Extracts 509
Glycerina—Glycerita—Glycerines 513
Infusa—Infusions 513
Injectiones Hypodermicæ—Hypodermic Injections 514
Lamellæ—Gelatine Discs 515
Linimenta—Liniments—Embrocations 515
Liquores—Solutions 517
Lotiones—Lotions 518
Massæ—Masses 518
Mellita—Honeys 518
Misturæ—Mixtures 518
Mucilagines—Mucilages 519

PAGE

Olea—Oils, Fixed and Volatile 519
Oleata—Oleates 521
Oleoresinæ—Oleoresins 521
Oxymel 521
Pilulæ—Pills 524
Pulveres—Powders 524
Resinæ—Resins 525
Spiritus—Spirits 526
Suppositoria—Suppositories 526
Succi—Juices 527
Syrupi—Syrups 528
Tabellæ—Tablets 528
Tincturæ—Tinctures 531
Triturationes—Triturations 531
Trochisci—Lozenges 532
Unguenta—Ointments 533
Vapores—Vapours—Inhalations 534
Vina—Wines 534

SECTION III.

INORGANIC MATERIA MEDICA.

CHAPTER XXII.

HYDROGEN, OXYGEN, OZONE, CARBON, SULPHUR, AND THE HALOGENS, pp. 537–564.

Hydrogen 537
Oxygen 537
Ozone 539
Peroxide of Hydrogen 540
Carbon 541
Sulphur 543
Sulphuretted Hydrogen 545
Halogen Elements—General Source and Characters 547
Mode of Preparation 548
General Action 549
Chlorine 549
Chlorinated Lime 550
„ Soda 551
Bromine 552
Bromide of Potassium 553
„ Sodium 555
„ Ammonium 556
„ Lithium 556
„ Calcium 556
„ Zinc (*vide* p. 672) 556
Iodine 557
Iodide of Sulphur 557
Action of Iodine 558
Iodide of Potassium 559

PAGE

Iodide of Sodium 563
„ Ammonium 563
„ Zinc (*vide* p. 673) 564
„ Silver (*vide* p. 680) 564
„ Mercury, Red (*vide* p. 696) 564
„ „ Green (*vide* p. 696) 564
„ Lead (*vide* p. 705) 564

CHAPTER XXIII.

ACIDS, pp. 565–591.

General Characters of Acids 565
„ Preparations of Acids 565
„ Action „ 567
Sulphuric Acid 570
Sulphurous „ 571
Hydrochloric Acid 572
Hydrobromic „ 573
Hydriodic Acid (Syrup) 574
Nitric „ 574
Nitro-hydrochloric Acid 575
Acetic „ 576
Phosphoric „ 578
Tartaric „ 580
Citric „ 580
Oxalic „ 581
Boric or Boracic „ 581
Chromic „ 582
Carbonic „ 583
Hydrocyanic „ 586
Lactic „ 589
Oleic „ 590
Arsenious „ (*vide* p. 719) 591
Benzoic „ (*vide* p. 964) 591
Carbolic „ (*vide* p. 813) 591
Chrysophanic „ (*vide* p. 909) 591
Gallic „ (*vide* p. 1033) 591
Pyrogallic „ (*vide* p. 819) 591
Salicylic „ (*vide* p. 819) 591
Tannic „ (*vide* p. 1031) 591

CHAPTER XXIV.

METALS, pp. 592–643.

General Classification of the Metals 592
General Tests for Acid Radicals in Metallic Salts 593
Metals of the Alkalis. Their Characters and Reactions 596
General Physiological Action of the Alkalis 596
„ „ „ Alkaline Group of Salts 597
„ „ „ Chlorides „ „ 599
„ „ „ Sulphates „ „ 602

PAGE

Comparative Action of the Alkaline Metals 602
Monad Metals, Group I., Potassium, Sodium, Lithium 603
Potassium, General Sources and Reactions of its Salts 603
Preparation of **Potassium** Salts 604
General Action of „ „ 605
Characters, Actions and Uses of Officinal Potassium Salts . . . 607–617
Sodium, General Sources and Reactions of its Salts 617
Preparations of its Salts 618
General Impurities, Tests and Action 619
Characters, Actions and Uses of Sodium Salts 619–630
Lithium, Sources and Reactions of its Salts 630
Impurities, Tests and General Action of Lithium Salts 630
Characters, Actions and Uses of Officinal Lithium Salts 631–633
Monad Metals, Group II., **Ammonium** 633
Nature of Ammonium Salts 633
Sources and Reactions 634
Impurities and Tests 634
Preparation 635
General Action 635
Characters, Actions and Uses of Officinal Ammonium Salts . . . 637–643

CHAPTER XXV.

METALS (*continued*), CLASS II., DYAD METALS—GROUPS I. AND II., METALS OF THE ALKALINE EARTHS AND OF THE EARTHS, pp. 644–661.

Reactions of the Metals in Class II. 645
Class II., Group I., **Metals of the Alkaline Earths** 645
General Action of „ „ „ „ 645
Calcium, Reactions, Preparation, Impurities and Tests of its Salts . 646, 647
Characters, Action and Uses of Officinal Calcium Salts 647–653
Class II., Group I., Appendix—**Aluminium** 654
General Sources, Preparation, Reactions, Impurities and Tests of Aluminium Salts 654
Characters, Actions and Uses of Officinal Aluminium Salts . . 654–657
Cerium, Action and Uses of its Oxalate 657
Class II., Group II., **Magnesium** 658
Sources, Reactions and Preparations of Magnesium Salts 658
Impurities, Tests and Action „ „ „ 659
Characters, Actions and Uses „ „ „ 659–661

CHAPTER XXVI.

METALS (*continued*), THE HEAVY METALS, CLASS II., GROUPS III. AND IV., AND CLASS IV., pp. 662–706.

General Actions of **Heavy Metals** 662
„ „ Class II., Group III., Zinc, Copper, Cadmium and Silver . 665
Zinc, its Sources, General Reactions and Preparations of Zinc Salts . . 667
Impurities, Tests and Action of Zinc Salts 668
Characters, Action and Uses of Officinal Zinc Salts 669–674
Copper, its Sources, Reactions, Impurities and Tests 674
Characters, Action and Uses of Officinal Salts of Copper . . . 674–676

PAGE
Silver, Characters, Action and Uses of its Salts 676–680
Class II., Group IV., **Mercury** 680
General Sources and Reactions of Salts of Mercury 680
„ Impurities, Tests and Action of Salts of Mercury 681
Characters, Actions and Uses of Officinal „ „ 686–697
Class IV., Tetrad Metals, Lead and Tin 698
General Actions 698
Lead, its Sources, Reactions, Impurities 698
Tests and Action of Lead 699
Characters, Actions and Uses of Officinal Salts of Lead 702–705
Tin, Action and Uses of its Chloride 706

CHAPTER XXVII.

CLASS V., PENTAD ELEMENTS—NITROGEN, PHOSPHORUS, ARSENIC, ANTIMONY, AND BISMUTH, pp. 707–734.

Nitrogen and its Compounds 707
Nitrous Oxide 708
Phosphorus, its Preparation, Characters and Action 709, 710
Uses of Phosphorus 712
Arsenic, its Sources and Tests 712
General Action of Arsenic 713
Probable Mode of Action of Arsenic in Phthisis 717
Characters, Actions and Uses of Officinal Preparations of Arsenic . 719–721
Antimony, its Sources and Reactions 721
General Action and Uses 722
Characters, Action and Uses of its Officinal Preparations . . . 727–730
Bismuth, its Sources and Reactions 730
General Action and Uses of its Salts 731
Character, Action and Uses of its Officinal Preparations . . . 732–734

CHAPTER XXVIII.

METALS (*continued*), CLASS VIII., IRON, MANGANESE, pp. 735–755.

Iron, its Sources and Reactions 735
Impurities, Tests and Preparation of its Salts 736
General Action 738
Character, Action and Uses of its Officinal Preparations . . . 740–752
Manganese 753
Class VIII., Group II., Gold and Platinum 753
Gold, Preparation and Characters of its Chloride 754
Platinum, Preparation, Uses and Action of its Chloride . . . 754, 755

SECTION IV.

ORGANIC MATERIA MEDICA.

CHAPTER XXIX.

CARBON COMPOUNDS—FATTY SERIES, pp. 759–806.

	PAGE
Series of Carbon Compounds	759
General Action of Carbon Compounds	760
Bisulphide of Carbon	760
Hydro-Carbons	761
Benzin	762
Petrolatum (Vaseline)	763
Paraffin, Hard	763
,, Soft	764
Alcohols of the Series $C_2H_{2n+1}OH$	764
General Action	764
Methyl Alcohol	766
Ethyl Alcohol: General Sources, Preparation and General Impurities	767
Tests and General Action	767
Effect of Impurities on its Action	770
Chronic Alcoholic Poisoning	770
Causes and Treatment of Alcoholism	772
Uses of Alcohol	773
Alcohol as a Stimulant	774
Officinal Alcoholic Preparations	775–778
Aldehydes, Acetic aldehyde and Paraldehyde	778
Ketones, Hypnone	779
Simple **Ethers**, Ether	780–783
Saline Ethers	783
Ethereal Oil and Hoffman's Anodyne	783
Acetic Ether	783
Nitrites of Ethyl and Amyl	784
Nitro-Glycerine—Tablets of Nitro-Glycerine	788
Liquor Sodii Ethylatis (*vide* p. 619)	789
Haloid Compounds	789
Bromide of Ethyl	789
Iodide of Ethyl	790
Chloral Hydrate, its Preparations and Characters	790
Its Action	791
Treatment of Chloral Poisoning	793
Butyl-Chloral Hydrate	794
Bromal Hydrate	794
Bichloride of Methylene	795
Chloroform, its Preparation, Characters, Impurities and Tests	795
Action of Chloroform	796
Dangers of ,,	799
Precautions in using Chloroform	800
Uses of Chloroform	802
Iodoform	804
Methylal (*vide* Appendix)	806
Urethane (*vide* Appendix)	806
Iodol (*vide* Appendix)	806

CHAPTER XXX.

CARBON COMPOUNDS—AROMATIC SERIES, pp. 807–826.

PAGE
General Chemistry of the Aromatic Series 807
General Action „ „ „ 811
Carbolic Acid 812
Its Action 813
Uses 815
Sodii Sulpho-carbolas (*vide* p. 626) 817
Zinci Sulpho-carbolas (*vide* p. 671) 817
Creasote 817
Resorcin 818
Hydroquinone 818
Pyrocatechin 819
Pyrogallic Acid 819
Salicylic Acid 819
Naphthalin 821
Naphthol 822
Hydrochlorate of Rosaniline 822
Pyridine 823
Chinoline 823
Kairin 824
Antipyrin 824
Antifebrin 825
Saccharine 825

SECTION V.

VEGETABLE MATERIA MEDICA.

INTRODUCTION 829

CHAPTER XXXI.

SUB-KINGDOM I., PHANEROGAMÆ.

DIVISION I., ANGIOSPERMÆ; CLASS I., DICOTYLEDONES POLYPETALÆ; SUB-CLASS I., THALAMIFLORÆ, pp. 831–875.

Ranunculaceæ 831
Aconite 831
Staphisagria 836
Pulsatilla 836
Adonis Vernalis 837
Cimicifuga 837
Podophyllum 838
Hydrastis 839
Magnoliaceæ 840
Star-Anise—Illicium 840
Oil of Anise 840
Menispermaceæ 840
Menispermum 840
Calumba 840
Pareira 841
Picrotoxin 842

PAGE

Berberidaceæ 842
Caulophyllum 842
Papaveraceæ 843
Poppy Capsules 843
Opium 844
Preparations of Opium 844
Meconic Acid 846
Morphine 846
Apomorphine 848
Codeine 849
Action of Opium 851
Diagnosis of Opium Poisoning 852
Treatment „ „ 853
Circumstances Modifying the Action of Opium 856
Action of the Alkaloids of Opium 858
Uses of Opium 859
Rhœas—Red Poppy 862
Sanguinaria—Blood Root 863
Chelidonium—Celandine 863
Cruciferæ 864
Sinapis—Mustard 864
Armoracia—Horseradish 866
Violarieæ 866
Viola—Pansy 866
Canellaceæ 867
Canella Alba 867
Polygalaceæ 867
Senega 867
Krameria—Rhatany 868
Guttiferæ 869
Cambogia—Gamboge 869
Ternströmiaceæ 869
Tea 869
Caffeine 870
Malvaceæ 872
Gossypium—Cotton 873
Pyroxylin—Gun Cotton 874
Collodion 874
Althæa—Marshmallow 875
Sterculiaceæ (Byttneriaceæ) 875
Theobroma—Cacao 875

CHAPTER XXXII.

PHANEROGAMÆ (*continued*).

CLASS I., DICOTYLEDONES POLYPETALÆ; SUB-CLASS II., DISCIFLORÆ, pp. 876–898.

Lineæ 876
Linseed—Flaxseed 876
Erythroxyleæ 877
Coca—Erythroxylum 877
Cocaine 877
Action of Cocaine 878

PAGE

Zygophyllaceæ 880
Guaiacum 880
Geraniaceæ 881
Geranium—Cranesbill 881
Rutaceæ 881
Ruteæ 881
Oil of Rue 881
Cusparia 881
Diosmeæ 882
Buchu 882
Xanthoxylinæ 883
Xanthoxylum—Prickly Ash 883
Jaborandi—Pilocarpus 883
Pilocarpine 883
Action of Pilocarpine 884
Aurantieæ 887
Orange 887
Oil of Bergamot 889
Lemon 890
Bael Fruit 891
Simarubaceæ 892
Quassia 892
Burseraceæ or Amyridaceæ 893
Myrrh 893
Elemi 893
Meliaceæ 894
Azedarach 894
Ilicineæ (Aquifoliaceæ) 894
Prinos—Black Alder 894
Celastrinæ 894
Euonymus—Wahoo 894
Rhamneæ 895
Cascara Sagrada—Rhamnus Purshianus 895
Rhamnus Frangula—Buckthorn 895
Ampelidæ (Vitaceæ) 896
Uvæ—Raisins 896
Vinum Xericum 896
Vinum Rubrum 896
Sapindaceæ 897
Guarana 897
Anacardiaceæ (Terebinthaceæ) 897
Mastiche 897
Rhus Glabra—Sumach 898
Rhus Toxicodendron—Poison Ivy 898

CHAPTER XXXIII.

PHANEROGAMÆ (*continued*).

CLASS I., DICOTYLEDONES POLYPETALÆ; SUB-CLASS III., CALYCIFLORÆ, pp. 899–938.

Leguminosæ 899
Papilionaceæ 899
Glycyrrhiza—Liquorice 899

PAGE

Scoparius—Broom 900
Tragacanth 900
Pterocarpus—Santalum—Red Sandal-wood or Red Saunders . . 901
Kino 902
Balsam of Peru 902
Balsam of Tolu 903
Abrus—Jequirity 903
Physostigma—Calabar Bean 904
Hæmatoxylon—Logwood 908
Chrysarobinum—Chrysophanic Acid—Goa Powder 908
Cæsalpinæ 909
Senna 909
Cassia—Purging Cassia 911
Tamarind 911
Copaiba—Copaiva 912
Piscidia Erythrina—Jamaica Dogwood 913
Mimoseæ 913
Acacia 913
Catechu 914
Erythrophlœum—Casca—Sassy 915
Indigo 915
Rosaceæ 915
Pruneæ 915
Amygdala Dulcis—Sweet Almond 915
Amygdala Amara—Bitter Almond 917
Prunum—Prune 917
Prunus Virginiana—Wild Cherry 917
Laurocerasus—Cherry Laurel 918
Quillajeæ 918
Quillaia—Soap Bark 919
Rubeæ 919
Rubus—Blackberry 919
Rubus Idæus—Raspberry 920
Roseæ 920
Oil of Rose 920
Rosa Centifolia—Cabbage Rose—Pale Rose 920
Rosa Gallica—Red Rose 920
Rosa Canina—Dog Rose 921
Cusso—Brayera 921
Pomeæ 921
Cydonium—Quince 922
Myrtaceæ 922
Caryophyllus—Cloves 923
Pimenta—Allspice 923
Cheken 924
Oleum Myrti—Oil of Myrtle 924
Oleum Cajuputi—Oil of Cajuput 925
Eucalyptus—Oil of Eucalyptus 926
Granatum—Pomegranate 927
Papayaceæ 927
Papayotin—Papain 927
Cucurbitaceæ 927
Colocynth 927

PAGE
Ecballium—Elaterium 928
Pepo—Pumpkin 930
Bryonia—Bryony 930
Umbelliferæ 930
Campylospermæ 930
Conium 931
Orthospermæ 932
Asafœtida—Asafetida 932
Galbanum 933
Ammoniacum 933
Fœniculum—Fennel 934
Anisum—Anise 935
Anethum—Dill 936
Carum—Caraway 936
Sumbul 937
Cœlospermæ 937
Coriander 937
Cornaceæ 938
Cornus—Dogwood 938

CHAPTER XXXIV.

PHANEROGAMÆ (*continued*).

CLASS II., DICOTYLEDONES GAMOPETALÆ (COROLLIFLORÆ), pp. 939–1008.

Caprifoliaceæ 939
Sambucus 939
Viburnum 939
Rubiaceæ (Cinchonaceæ) 939
Cinchoneæ 939
Cinchona Flava—Yellow Cinchona 940
„ Rubra—Red „ 940
Quinine and its Salts 942
Cinchonine 943
Ixoreæ (Coffeæ) 948
Ipecacuanha 948
Caffea—Coffee 950
Catechu (Pale) 951
Valerianaceæ 951
Valerian 951
Compositæ 952
Pyrethrum 952
Absinthium—Wormwood 953
Tanacetum—Tansy 953
Santonica—Santonin 954
Anthemis—Chamomile 955
Matricaria—German Chamomile 956
Eupatorium—Thoroughwort 956
Taraxacum—Dandelion 956
Lactuca—Lettuce 957
Arnica 957
Calendula—Marygold 959

PAGE
959
Grindelia 959
Inula—Elecampane 960
Lappa—Burdock 960
Campanulaceæ (Lobeliaceæ) 960
Lobelia 961
Ericaceæ 961
Uva Ursi—Bearberry 962
Chimaphila—Pipsissewa 962
Oleum Gualtheriæ—Oil of Wintergreen 963
Sapotaceæ 963
Gutta-percha 963
Styracaceæ 963
Benzoin—Benzoic Acid 965
Oleaceæ 965
Olive Oil 966
Hard Soap 966
Soft Soap 966
Glycerin 968
Manna 968
Apocynaceæ 968
Apocynum—Canadian Hemp 969
Quebracho 970
Asclepiadaceæ 970
Asclepias—Pleurisy Root 970
Asclepias Incarnata—White Indian Hemp 970
Hemidesmus 970
Condurango 971
Loganiaceæ 971
Nux Vomica 971
Ignatia 972
Strychnine 976
Curare 977
Gelsemium 978
Spigelia—Pinkroot—Maryland Pink 979
Gentianaceæ 979
Gentian 979
Chiretta 980
Convolvulaceæ 980
Scammony 982
Jalap 983
Solanaceæ 983
Dulcamara 984
Capsicum 984
Atropeæ 984
Belladonna—Atropine 990
Hyoscyamus 991
Stramonium 992
Tobacco 994
Scrophulariaceæ 994
Digitalis 1001
Leptandra 1002
Pedalineæ 1002
Oleum Sesami—Benné oil 1002

PAGE

Verbenaceæ 1002
Lippia Mexicana 1002
Labiatæ 1002
Rosemary 1002
Lavender 1003
Peppermint—Menthol 1004
Spearmint 1005
Thymol 1005
Hedeoma—Pennyroyal 1006
Marrubium—Horehound 1007
Melissa—Balm 1007
Origanum—Wild Marjoram 1007
Salvia—Sage 1008
Scutellaria—Skull-cap 1008

CHAPTER XXXV.

PHANEROGAMÆ (*continued*).

CLASS III., DICOTYLEDONES MONOCHLAMYDEÆ (APETALÆ), pp. 1009–1035.

Chenopodiaceæ 1009
Chenopodium—American Wormseed 1009
Oleum Chenopodii 1009
Phytolaccaceæ 1009
Phytolacca—Poke berry 1009
Polygonaceæ 1010
Rheum—Rhubarb 1010
Rumex—Yellow Dock 1011
Aristolochiaceæ 1012
Serpentary 1012
Asarabacca 1012
Piperaceæ 1012
Pepper—Piperine 1012
Cubebs 1013
Matico 1014
Myristicaceæ 1015
Myristica—Nutmeg 1015
Macis—Mace 1016
Laurineæ 1016
Cinnamon 1016
Coto 1017
Parocoto 1017
Camphor 1018
Monobromated Camphor 1019
Sassafras 1020
Nectandra—Bebeeru 1021
Santalaceæ 1021
Oleum Santali 1021
Thymelaceæ 1022
Mezereon 1022
Euphorbiaceæ 1022
Cascarilla 1022

PAGE
Stillingia 1022
Croton Oil 1023
Castor Oil 1024
Kamala 1025
Urticaceæ 1025
Ulmeæ 1025
Ulmus 1025
Cannabineæ 1026
Cannabis Indica—Indian Hemp 1026
Cannabis Americana—American Cannabis 1026
Humulus—Lupulus—Hop 1027
Moreæ 1028
Morus—Mulberry 1028
Artocarpeæ 1028
Ficus—Fig 1028
Juglandaceæ 1029
Juglans—Butternut 1029
Hamamelaceæ 1029
Hamamelis 1029
Balsamifloræ 1030
Styrax 1030
Cupuliferæ 1030
Quercus—Oak 1030
Galls 1031
Tannic Acid 1031
Gallic Acid 1033
Castanea—Chestnut 1034
Salicaceæ 1034
Salix—Salicin 1034

CHAPTER XXXVI.

PHANEROGAMÆ (*continued*).

CLASS IV., MONOCOTYLEDONES, pp. 1036–1056.

Orchidaceæ 1036
Vanilla 1036
Cypripedium 1036
Scitamnaceæ (Zingiberaceæ) 1036
Zingiber—Ginger 1036
Turmeric 1037
Cardamoms 1038
Irideæ 1038
Crocus—Saffron 1038
Iris 1038
Liliaceæ 1039
Allium—Garlic 1039
Convallaria 1040
Squill 1040
Aloe 1041
Veratrum Viride 1045

PAGE
Cevadilla—Sabadilla—Veratrine 1046
Colchicum 1049
Liliaceæ (Smilaceæ) 1051
Sarsaparilla 1051
Palmaceæ 1052
Areca 1052
Aroideæ 1052
Calamus—Sweet Flag 1052
Gramineæ 1053
Wheat—Flour—Bread—Starch 1053
Couch Grass 1054
Pearl Barley 1054
Malt 1054
Sugar 1055
Treacle 1055
Oatmeal 1056

CHAPTER XXXVII.

PHANEROGAMÆ (*continued*).

DIVISION II., GYMNOSPERMÆ, pp. 1057–1065.

Coniferæ 1057
Terebinthina Canadensis—Canada Balsam 1057
Thus Americanum—Common Frankincense 1057
Turpentine 1057
Oil of Turpentine 1058
Oil of Scotch Fir 1059
Terebene 1060
Sanitas 1060
Oleum Succini—Oil of Amber 1060
Resin 1061
Larch Bark 1061
Burgundy Pitch 1062
Canada Pitch 1062
Tar 1062
Oil of Tar 1063
Thuja—Arbor Vitæ 1063
Juniper 1063
Savin 1064

CHAPTER XXXVIII.

SUB-KINGDOM II., CRYPTOGAMÆ, pp. 1066–1073.

. 1066
Filices 1066
Male Fern 1067
Lichenes 1067
Cetraria—Iceland Moss 1067
Litmus 1067

PAGE
. . . 1067
Fungi . . . 1067
Muscarine . . . 1068
Agaricus Albus . . . 1068
Ergot—Ergotin . . . 1073
Ustilago . . . 1073
Beer Yeast . . . 1073
Algæ . . . 1073
Chondrus—Irish Moss

SECTION VI.

ANIMAL KINGDOM.

CHAPTER XXXIX., pp. 1077–1099.

. . . 1077
Class **Mammalia** . . . 1077
Order Rodentia . . . 1077
Castor . . . 1077
Order Ruminantia . . . 1077
Musk . . . 1078
Suet . . . 1078
Lanolin . . . 1079
Curd Soap . . . 1079, 1080
Milk—Koumiss—Képhir . . . 1080
Milk Sugar . . . 1081
Pepsin . . . 1081
Ox Gall . . . 1083
Keratin . . . 1084
Order Pachydermata . . . 1084
Lard . . . 1085
Order Cetaceæ . . . 1085
Spermaceti . . . 1085
Class **Aves** . . . 1085
Order Gallinæ . . . 1085
Egg-Albumen and Yolk . . . 1086
Class **Pisces** . . . 1086
Order Sturiones . . . 1086
Isinglass—Ichthyocolla . . . 1087
Order Teleosteæ—Family Gadidæ . . . 1087
Cod Liver Oil . . . 1089
Class **Insecta** . . . 1089
Order Hymenoptera . . . 1089
Honey . . . 1089
Wax . . . 1090
Order Hemiptera . . . 1090
Coccus—Cochineal . . . 1091
Order Coleoptera . . . 1091
Cantharis—Spanish Flies . . . 1095
Class **Annelida** . . . 1095
Hirudo—the Leech

APPENDIX.

PAGE
Methylal 1097
Urethane 1097
Iodol 1099
Strophanthus hispidus—Strophanthin 1099
Dead Space 1100

GENERAL INDEX 1103

INDEX OF DISEASES AND REMEDIES 1177

BIBLIOGRAPHICAL INDEX 1239

Errata.

P. 192.—Last line : *after* shown *insert* (2).

„ Note : *after* (1) *read* Lauder Brunton on the Physiological Action of Alcohol, *Practitioner*, 1876, vol. xvi., p. 127.

Before François-Frank *insert* (2).

P. 261.—Line 5 : *after* nicotine *insert* alone.

„ Line 7 : *after* substances *insert* which resemble nicotine in action and are present along with it in the smoke.

P. 362.—7 lines from bottom : *for* D *read* G.

P. 545.—Line 20 : *for* $2CaS_5$ *read* CaS_5.

„ Line 22 : *for* $2CaS_5$ *read* CaS_5.

P. 550.—11 lines from bottom : *for* 551 *read* 533.

P. 551.—20 lines from bottom : *for* 551 *read* 533.

P. 586.—Line 31 : *for* $AgNo_3$ *read* $AgNO_3$.

P. 667.—17 lines from bottom : *for* $Fe_2Cl_6 + 3ZnCo_3 + O$ *read* $Fe_2Cl_6 + 3ZnCO_3 + 3H_2O$.

P. 686.—5 lines from bottom : *for* Subchloridi *read* Subchloridum.

P. 728.—Line 19 : *for* $2Sb_2S_3 + 2S_2 + 6NaHO$ *read* $2Sb_2S_3 + S_2 + 6NaHO$.

„ Line 33 : *for* $2Na_3SbS_3 + 3H_2SO_4$ *read* $2Na_3SbO_3 + 3H_2SO_4$.

„ Line 37 : *for* $\left\{\begin{matrix}3Na_3SbO_4 + 3H_2SO_4 = \\ 3NaSO_4 + Sb_2O_5 + 3H_2O\end{matrix}\right\}$ *read* $\left\{\begin{matrix}2Na_3SbO_4 + 3H_2SO_4 = \\ 3Na_2SO_4 + Sb_2O_5 + 3H_2O.\end{matrix}\right.$

P. 867.—Line 2 : *for* Canellæ Albæ Cortex *read* Canella Cortex.

„ Line 2 : *for* Canella Alba Bark *read* Canella Bark.

P. 1177.—Line 3 : *for* Ringer's *Therapeutics*, 2 ; Bartholow's *Therapeutics*, 3, *read* Bartholow's *Therapeutics*, 2 ; Ringer's *Therapeutics*, 3.

Addenda.

Page 52, line 17, *after* 'Hahnemann' *insert* 'who had suffered from ague.'[1]

Foot note to page 52:

[1] *History of Homœopathy.* By Wilhelm Ameke, M.D. Translated by Alfred E. Drysdale, M.B. Edited by R. E. Dudgeon, M.D. London. Published for the British Homœopathic Society, by E. Gould & Son, 59 Moorgate Street. 1885.

MEDICAL DEPARTMENT,
YORKSHIRE COLLEGE,
VICTORIA UNIVERSITY.

MATERIA MEDICA AND THERAPEUTICS.

INTRODUCTION.

By **Materia Medica** we understand a knowledge of the remedies employed in medicine. This knowledge may be subdivided into several divisions: Materia Medica proper, Pharmacy, Pharmacology, and Therapeutics.

By **Materia Medica proper** we mean an acquaintance with the remedies used in medicine, the places whence they come, the crude substances, plants or animals which yield them, the methods by which they are obtained, and the means of distinguishing their goodness or purity, or of detecting fraudulent adulteration.

By **Pharmacy** we mean the methods by which drugs are prepared and combined for administration.

By **Pharmacology** we mean a knowledge of the mode of action of drugs upon the body generally, and upon its various parts. It is of comparatively recent growth, but is now one of the most important subdivisions of Materia Medica.

By **Therapeutics** we understand a knowledge of the uses of medicines in disease.

Therapeutics may be either *empirical* or *rational*. By **empirical** we mean that drugs are tried haphazard, or with little knowledge of their action in some cases, and, being found successful, are again administered in other cases which seem to be similar.

Perhaps the best example of the empirical use of a remedy is that of quinine in ague. We do not know with certainty what the pathological conditions are in this disease, nor how quinine acts upon them; all we know is that it has proved useful in cases of ague before, and therefore we give it again.

Rational therapeutics consists in the administration of a drug because we know the pathological conditions occurring in the disease, and know also that the pharmacological action of the drug is such as to render it probable that it will remove or counteract these conditions.

Rational therapeutics is the highest branch of medicine. Its advance is necessarily slow, because it is based upon pathology on the one hand and pharmacology on the other, and both of these rest upon physiology, which in its turn rests upon physics and chemistry. It is only with the development of the

fundamental sciences that those which rest upon them can grow; and when we consider that chemistry as a science is not much more than a hundred years old, and when we see the advances it has already made, we cannot but be hopeful for the future of therapeutics.

Occasionally we hear the question asked, 'What is the use of knowing the action of all sorts of drugs upon the different parts of the animal body, and what is the use of knowing the alterations in the muscles, vessels, or nerves which occur under pathological conditions, seeing that in many instances such a knowledge cannot be utilised for the treatment of disease?' As well might we ask, on seeing a half-built bridge, 'What is the use of laying the foundations and building the piers, seeing no one can walk across from one end to the other?'

As an example of rational therapeutics, we may take the use of nitrite of amyl in certain forms of angina pectoris. The obvious symptoms in this disease are intense pain in the region of the heart, and fear of impending death. Sphygmographic tracings of the pulse taken during this condition show that the tension within the heart and vessels begins to increase as the pain comes on, and reaches such a height that the heart can barely empty itself. Observations on animals have shown that nitrite of amyl lessens the tension of the blood in the vessels; and we therefore give it in angina pectoris with the expectation that it will diminish the tension and remove the pain, and we find that it succeeds.

But this example shows us only the first stage of rational therapeutics. We have removed by a remedy the pathological condition which immediately gives rise to the pain and danger of the patient, but the antecedent alterations of the heart, bloodvessels, and nervous system, which led to the occurrence of the pain, are unaltered by the remedy. In order that our therapeutics should be completely successful, we must seek still further for something which will restore the circulation and nervous system to its normal condition and bring the patient back to a state of perfect health.

Sometimes we are able to do this. For example, we occasionally meet with a kind of pain in the cardiac region which closely resembles angina pectoris, and is probably a form of it. Acting on the general principle that pain is due to irritation somewhere, though not necessarily at the place where the pain is felt, we seek for the irritant. We find swelling and tenderness over the sternum at the junction of the manubrium and the body, and we look upon this as the irritant which is exciting the cardiac pains. Judging this swelling to be syphilitic, we give iodide of potassium; the swelling subsides, and the angina-like pain completely disappears.

But sometimes it is impossible to remove the cause of the

disease, and all that we can do is to alleviate symptoms. The organic changes which have occurred in the course of the disease may be so great that we can hardly hope that any remedy will ever be discovered sufficiently powerful to remove them. We must therefore try to prevent them.

Preventive medicine, or **prophylaxis**, is daily becoming more important, and, possibly before the end of this century, medical men will be employed more to prevent people from becoming ill than to cure them when disease has become fairly established.

This may at least be the case in regard to the contagious and infectious diseases, which attack people as it were by accident, and are totally unconnected with their ordinary work or pleasure. It is too much to hope that other diseases which depend upon hereditary tendencies, overwork, or over-indulgence, will disappear, for there can be little doubt that men in the future will, as in the past, knowingly sacrifice, not only their health, but their life, to ambition, duty, or pleasure.

The advance of this branch of medicine has been greatly aided by the recent increase in our knowledge of the life-history of microbes and their action in causing disease. Our power to prevent disease will become greater when we know accurately the action of various drugs in destroying these microbes or preventing their growth.

Pharmacology has made such rapid advances of late years that it is exceedingly difficult for many men who are engaged in practice to understand thoroughly either the methods by which it is studied, or its results. Many students also, although they may be able to pass a good examination in physiology, find it difficult to apply their physiological knowledge to pharmacology; and therefore in discussing the action of drugs upon the various functions of the body, I have sometimes entered more fully into the physiology of those functions than may seem to some at all either necessary or advisable.

In discussing pharmacological questions, we are accustomed to speak of the **action** of a drug on the body or on its various parts; but we must remember the effect produced is not due to a one-sided action—that what we actually mean is the **re-action** between the drug and the various parts of the body.

In some instances we know that the drug itself is changed in the body, as well as the function of the body modified by the drug; and even in those cases where the drug itself is eliminated from the body apparently unaltered, it is probable that it has entered into various chemical combinations within the body while circulating in the blood or present in the tissues.

SECTION I.

GENERAL PHARMACOLOGY AND THERAPEUTICS.

CHAPTER I.

GENERAL RELATIONS BETWEEN THE ORGANISM AND SUBSTANCES AFFECTING IT.

In discussing the inter-action between the animal organism and the substances which act upon it, it may be well to take a slight glance first at the substances which compose its environment, although these will be afterwards considered more in detail.

Of the **elements** composing the earth on which we live we at present know about seventy-two whose existence appears well-established. They are given in the accompanying table. The atomic weights assigned to them cannot be regarded as absolutely correct. There are sometimes considerable discrepancies between those given by different authorities, and those which are accepted to-day may require to be altered again in accordance with the more exact knowledge which future observations may supply. There are slight differences between several of them as given in the British and United States Pharmacopœias.

TABLE OF ELEMENTS.

Element	Symbol	Valency or Atomicity	Atomic Weight, B.P.	Atomic Weight, U.S. P.	Atomic Weight very accurately determined [1]
*Aluminium	Al	II. & IV.	27·0	27·0	27·009
*Antimony (Stibium)	Sb	III. & V.	120·0	120·0	119·555
Arsenicum	*As*	III. & V.	75·0	74·9	74·918
*Barium	Ba	II.	137·0	136·8	136·763
Beryllium or Glucinum	Be or G	II.	9·0	9·0	9·085
*Bismuth	Bi	III. & V.	209·0	210·0	207·523
Boron	*B*	—	11·0	11·0	10·941
Bromine	*Br*	I.	80·0	79·8	79·768
Cadmium	Cd	II.	111·8	111·8	111·835
Cæsium	Cs	I.	133·0	132·6	132·583
*Calcium	Ca	II.	40·0	40·0	39·99
Carbon	*C*	II. & IV.	12·0	12·0	11·9736
*Cerium	Ce	IV.	141·0	141·0	140·424
Chlorine	*Cl*	I.	35·5	35·4	35·37
*Chromium	Cr	II. & IV.	52·5	52·4	52·009
Cobalt	Co	II. & IV.	58·9	58·9	58·887

Those marked with * are contained, either simply or in combination, in the British Pharmacopœia. Those printed in italics are non-metallic elements. Their atomic weights are given as in the B. P.

[1] From Ira Remsen's *Principles of Theoretical Chemistry*.

TABLE OF ELEMENTS—*continued.*

Element	Symbol	Valency or Atomicity	Atomic Weight, B.P.	Atomic Weight, U.S. P.	Atomic Weight very accurately determined
Columbium *vide* Niobium					
*Copper (Cuprum)	Cu.	II.	63·4	63·2	63·173
Didymium	Di.	IV.	145·4	144·6	145·4
Erbium	Er or Eb[1] or E	—	166·0	165·9	165·891
Fluorine	*F*	I.	19·0	19·0	18·984
Gallium	Ga	IV.	70·0	68·8	69·9
*Gold (Aurum)	Au	I. & III.	196·5	196·2	196·155
Glucinum *vide* Beryllium					
Holmium		—	—	—	—
**Hydrogen*	*H*	I.	1·0	1·0	1·0
Indium	In	I. & III.	113·4	113·4	113·398
**Iodine*	*I*	I.	127·0	126·6	126·557
Iridium	Ir	II. & IV.	192·7	192·7	192·651
*Iron (Ferrum)	Fe.	II. & IV.	56·0	55·9	55·913
Lanthanum	La.	IV.	139·0	138·5	138·526
*Lead (Plumbum)	Pb.	II. & IV.	207·0	206·5	206·471
*Lithium	Li.	I.	7·0	7·0	7·0073
*Magnesium	Mg	II.	24·0	24·0	23·959
*Manganese	Mn	II. & IV.	55·0	54·0	53·906
*Mercury (Hydrargyrum)	Hg	II.	200·0	199·7	199·712
Molybdenum	Mo		95·5	95·5	95·527
Nickel	Ni.	II. & IV.	58·0	58·0	57·928
Niobium or Columbium	Nb	V.	94·0	94·0	—
**Nitrogen*	*N*	III. & V.	14·0	14·0	14·021
Osmium	Os.	II. & IV.	198·5	198·5	198·494
**Oxygen*	*O*	II.	16·0	16·0	15·9633
Palladium	Pd.	II. & IV.	105·7	105·7	105·737
**Phosphorus*	*P*	III. & V.	31·0	31·0	30·958
*Platinum	Pt.	II. & IV.	195·0	194·4	194·415
*Potassium (Kalium)	K	I.	39·0	39·0	39·019
Rhodium	Rh	II. & IV.	104·0	104·1	104·055
Rubidium	Rb	I.	85·3	85·3	85·251
Ruthenium	Ru	II. & IV.	104·2	104·2	104·217
Samarium	Sm	—	150·0	—	150·021
Scandium	Sc.	—	44·0	44·0	43·98
Selenium	*Se*	II.	78·8	78·8	78·797
Silicon	*Si*	IV.	28·0	28·0	28·195
*Silver (Argentum)	Ag.	I. (? II.)	108·0	107·7	107·7
*Sodium (Natrium)	Na	I.	23·0	23·0	22·998
Strontium	Sr.	II.	87·4	87·4	87·374
**Sulphur*	*S*	II.	32·0	32·0	31·984
Tantalum	Ta.	III. & V.	182·0	182·0	182·144
Tellurium	*Te*	II.	128·0	128·0	127·96
Terbium		—	—	—	—
Thallium	Tl or Th	III.	203·7	203·7	203·715
Thorium	Th	IV.	233·0	233·0	233·414
Thulium		—	—	—	—

[1] Er, Roscoe and Schorlemmer, *Treatise on Chemistry*, vol. i. p. 54. Eb, Fownes, edited by Watts, 12th ed. vol. i. p. 401. E, Ira Remsen's *Principles of Theoretical Chemistry*.

TABLE OF ELEMENTS—*continued.*

Element	Symbol	Valency or Atomicity	Atomic Weight, B.P.	Atomic Weight, U.S. P.	Atomic Weight very accurately determined
*Tin (Stannum) .	Sn .	II. & IV.	118·0	117·7	117·698
Titanium . .	Ti .	IV.	49·8	48·0	49·846
Tungsten . .	W .	VI.	184·0	183·6	183·61
Uranium . .	U .	IV. & VI.	240·0	238·5	239·8
Vanadium . .	V .	III. & V.	51·3	51·3	51·256
Ytterbium . .	Yb.	—	172·8	172·7	172·761
Yttrium . .	Y .	IV.	89·8	89·8	89·816
*Zinc . .	Zn .	II.	65·0	64·9	64·9045
Zirconium . .	Zr.	IV.	90·0	90·0	89·367

Nature of the Elements.

Considerable additions have been made to the number of elements during late years. The reason of this is that the spectroscope has indicated the presence of metals previously unknown, and by the use of proper means they have been obtained in a separate condition. These substances are termed elements because we do not at present know how to split them up in such a manner as to prove that they are compounds. But it is not improbable that they are compounds, just as we now know that potash and soda are compounds; although before Sir Humphry Davy split them up into oxygen and a metal they were supposed to be elements. Indeed, recently much evidence has been brought to show that the substances which we call elements are really compounds.

It is from an examination of the spectroscopic character of the elements at different degrees of temperature that Lockyer has been able to obtain sufficient data to justify the definite formulation of the **hypothesis** that all the **elements** we know are really compounds, or, to speak perhaps more precisely, are really **different forms** of aggregation of one kind **of matter.**[1] According to this hypothesis the matter of which the universe is composed was at one time equally distributed through space, and uniform in kind. The atoms then coalesced in various groups of two, three, or more; and these, again grouping themselves together still further, formed aggregates of more and more complex composition. These aggregates are, it is supposed, the elements with which we are acquainted. Most of those complex molecules are perfectly stable at ordinary temperatures; and so their composition remains constant under the conditions usual at the surface of this earth.

But when they are subjected to increased temperatures in the laboratory, rising from that of the Bunsen lamp to the electric arc, and then to the electric spark or to still higher temperatures in the sun, their spectroscopic appearances give evidence of decomposition into simpler molecules. When the elements are subjected to cold and pressure the molecules which compose them come closer together, and we get them forming a solid substance. Heat tends, by communicating vibrations to them, to shake the molecules further apart, and to produce a liquid condition. Still greater heat shakes the molecules further apart still, and produces a gaseous condition.

In all those conditions the molecules of the element become more complex by reduction of temperature or increase of pressure, and simpler by increase in temperature or reduction in pressure.[2] Exceedingly great heat or electricity appears to shake apart still further the constituents of the element, so as to resolve it into simpler combinations of the elementary substance of which, according to the hypothesis, it is composed.

This shaking apart of the component elements is known to exist in com-

[1] Lockyer, *Phil. Trans.* 1874, p. 492 *et seq.*

[2] According to another hypothesis, bodies are supposed to have molecules of one degree of complexity, and the difference between solid, liquid, and gaseous bodies is

pounds, and to it the name of **dissociation** has been given. Thus when chalk or limestone is exposed to the action of heat it becomes dissociated into carbonic acid and lime, $CaCO_3 = CaO + CO_2$. This process is readily reversible by reversing the conditions. Thus the lime and carbonic acid which are dissociated by heat readily recombine in the cold $CaO + CO_2 = CaCO_3$.

When matter is **solid** the molecules of which it is composed are supposed to be large and close together. When in the state of vapour or **gas,** these molecules are smaller and much further apart.

Solid, liquid, or densely gaseous matter, when its molecules are agitated by heat, gives a continuous spectrum. Gaseous and vaporous matters, when their molecules are agitated at lower pressures or higher temperatures by heat or electricity, give a discontinuous spectrum consisting of bands or lines.

Between those extremes we have, as a rule, three other intermediate kinds of spectra: first, a continuous spectrum in the red; next, a continuous spectrum in the blue; next, a fluted spectrum, and after that the line spectrum already mentioned.

In all those kinds of spectrum, however, we are supposing that the elementary molecules are still intact; they are only more or less separated.

Compound bodies, like simple bodies, give definite spectra. The spectrum of a simple metal consists of lines which increase in number and thickness as the pressure of the vapour or its quantity in a given space is increased. The spectrum of a compound body consists chiefly of channelled spaces and bands which increase in the same manner. The greater the number of molecules in a cubic inch or cubic millimetre, and the more violently they are agitated, the more complex is the spectrum until it becomes continuous.

The smaller the number of molecules in a given space, the more simple is the spectrum, which then consists of a few lines only.

When a compound is exposed to heat, so as to dissociate it into its component parts the spectroscopic bands characteristic of the compound become thinner, and the lines of the metal increase in number, as shown in the accompanying diagram where the bands exhibited by calcium chloride in the flame of a Bunsen's burner, disappear, and are replaced by lines only, when




FIG. 1.—Spectrum of calcium chloride. (1) In the flame of a Bunsen's burner, showing the channelled spaces and bands of a compound. (2) In an electric spark, showing the lines of the element calcium. (After Roscoe.)

an electric spark is used. When an element is treated with more and more heat and electricity it likewise gives exactly the same kind of evidence of dissociation—bands disappearing, and lines becoming thinner. Besides this, new lines make their appearance with every large increase of temperature.

This behaviour of the element appears to show that it also is a compound, but that it is stable under ordinary conditions, and is only dissociated at a high temperature.

Other proofs of this hypothesis are derived from a comparison of the spectra of the elements as observed in our laboratories with their spectra in the sun.

A comparison of the two hypotheses shows us that as on the old hypothesis each element represents a species and is unvariable, its spectrum ought to be always the same in our laboratories and in the sun: and the same in sun-spots as in prominences, and the same at all periods of the sun's activity.

---

supposed to depend on the difference in the free path of the molecule. But according to the new view, the difference in the complexity of the molecule itself is sufficient to explain the phenomena.

Under the new hypothesis the spectra of metals in our laboratories and in the sun should not resemble each other; they should be different in sun-spots and in prominences, because the spot is cooler than the prominence; and they should vary at the time of the sun's activity because the sun is hotter at the maximum of the sun-spot period, and therefore there should be a greater amount of dissociation amongst the elements at that period.

As a matter of fact we find that the spectra in our laboratories and in the sun do not resemble each other (Fig. 2); that those of the same element




FIG. 2.—Diagram of the spectrum of lithium under various conditions of temperature. (After Lockyer, *Roy. Soc. Proc.* Dec. 12, 1878.)

in the sun-spot and prominences are as dissimilar as of any two elements; and that the spectra of the elements in the sun do vary with the maximum of the sun-spot period.

On the old hypothesis the spectra of prominences should also consist of lines familiar to us in our laboratories, because solar and terrestrial elements are the same, while, according to the new hypothesis, the spectra of prominences should be unfamiliar, because the prominences represent outpourings from a body hot enough to prevent the atoms of which our elements are composed from coming together.

As a matter of fact, the lines in the prominences, with the exception of those of hydrogen, magnesium, calcium, and sodium, are either of unknown origin, or are feeble lines in the spectra of known elements. **Spectroscopic observation, therefore, leads to the belief that the so-called elements are really compounds,** the component parts of which are kept apart by high temperatures in the sun and stars, but unite when the temperature decreases.

By the powerful vibrations imparted to them by the electric spark, they may be dissociated in the laboratory; but, as no means has yet been devised of separating the components, they again unite to form the original body, just as hydrogen and oxygen, into which steam is dissociated by passing it through a strongly heated tube, almost instantly combine again to form water unless they are separated by means of the more rapid diffusion of hydrogen through a porous tube.

The difficulty in accepting this evidence lies in the fact that we have hitherto been unable to isolate the substances into which the elements are supposed to be dissociated; as these after their dissociation at once recombine and again form the original substance.

One proof, however, that the supposed components of the element calcium may remain permanently separated, is afforded by the fact that in the spectra of two stars, Sirius (Fig. 3) and α Lyræ, which are very bright, and probably very hot, only one of the ultra-violet lines of calcium is represented.





FIG. 3.—Diagram of the spectrum of calcium under various conditions of temperature. In the spectrum of Sirius the line K is absent, while it is very strongly marked in the solar spectrum.

But we have also other evidence of the compound nature of the elements, which, although it was not sufficient of itself to force us to abandon our old ideas of their simple nature, is yet strongly corroborative of the spectroscopic evidence. Thus we find that **oxygen** is broken up by electricity, and that the atoms of which its molecules are composed, rearrange themselves so as to form what is to all intents and purposes a new element, ozone, having a much closer resemblance to chlorine than to oxygen in its activity,

although its compounds with metals appear to be identical with those of oxygen.



a *b*

FIG. 4.—Diagram to illustrate the formation of ozone by electricity. *a* represents oxygen, through which a spark is passing; *b* after it has passed. The double rings are intended to represent molecules of oxygen, each containing two atoms. As the electric spark passes through the oxygen it breaks up the first molecule, carrying one atom on to join the second molecule of oxygen, and form one of ozone. The atom which is left joins another molecule of oxygen, and also forms ozone. (After Lockyer.)

At a high temperature its atoms are again dissociated, and recombine to form ordinary oxygen. When it combines with other substances, the heat of combination appears to be sufficient to dissociate the atoms of ozone (O_3), so that in the compound we meet with simple oxygen, O.

When **sulphur** is simply melted and cooled, it solidifies as a yellow brittle substance, but if it is heated to 200° it becomes brownish and thick, and if it be suddenly cooled, by throwing it into water, it solidifies as a transparent reddish plastic and elastic substance. The ordinary brittle and yellow, and the reddish plastic sulphur, appear to be quite different substances. But if the plastic sulphur be left for some hours, it becomes reconverted into ordinary sulphur; and if either ordinary or plastic sulphur be volatilised, the vapour condenses in the form of ordinary sulphur; but if the vapour is quickly cooled, the sulphur, while retaining its ordinary appearance, may yet undergo a certain change evidenced by its becoming insoluble in bisulphide of carbon. On the new hypothesis we explain these phenomena by supposing that the different forms of sulphur are different compounds, or perhaps we should rather say different aggregates, for their components may not differ in kind like those of calcium, but only in number like those of oxygen or ozone.

Indeed we are almost driven to such a conclusion by the behaviour of sulphur in regard to its vapour density, for only at very high temperatures does the specific gravity of the vapour follow the general rule, and at lower temperatures it is three times as great as it ought to be, indicating that at these lower temperatures the molecule of sulphur contains six atoms instead of two.

Phosphorus also affords us an example of an element which occurs in two forms, so different that we should call them distinct bodies, were it not that we find that one can be transformed into the other.

The two forms, red and yellow phosphorus, differ from each other, not only in their colour, but in their density, specific heat, readiness of combustion, and heat of combustion. They differ also in the fact that yellow phosphorus is exceedingly poisonous, whereas the red phosphorus is not poisonous. They are in many respects, then, different bodies, but we have hitherto been content to call them allotropic forms of the same element.

In combination we find that phosphorus is sometimes *pentad* and sometimes *triad*; that its compounds with oxygen are sometimes poisonous, at other times not. Thus orthophosphoric acid, H_3PO_4, is not poisonous; pyrophosphoric acid, $H_4P_2O_7$, and metaphosphoric acid, HPO_3, are both poisonous.

The most striking example, however, is **carbon**, which we not only find

in three forms, differing enormously from each other, as diamond, charcoal, and graphite, but which we find in various compounds playing the most varied parts. This we at present explain by saying that carbon unites with itself in the formation of the various radicals; and thus comes to form what are practically new elements.

Another example is afforded us by **ammonia**, the salts of which are just as well characterised as those of potash or soda. The amalgam which it forms with mercury possibly indicates that we have in it also a real metal, ammonium, corresponding to sodium or potassium, though this is uncertain.

The three metals, sodium, potassium, and ammonium (if it exist), agree in the readiness with which they are oxidised, so that it is difficult to preserve the pure metal, although the oxide is stable. They differ, however, in the oxides of potassium and sodium being solid, and that of ammonium gaseous. Ammonium has not been isolated, and it is put down in the text-books as a hypothetical substance, but ammonium salts are tangible enough, and the question which we have to keep before us is, whether potassium, sodium, and all the other so-called elements, are not in reality compounds like ammonium.

Some people still regard species as immutable, and look upon Darwin's hypothesis of evolution as unproven.

The evidence in favour of the evolution of elements from one simple form of matter, is as yet, perhaps, much less strong than that in support of the evolution of species; but the hypothesis has this advantage, that it explains certain phenomena which have hitherto been very perplexing.

It may be at least convenient in discussing the physiological action of drugs to bear this hypothesis in mind, and to remember that what we have hitherto been accustomed to call elements may be really constituted like the so-called organic radicals, with this difference, that we can split up organic radicals with tolerable facility, while we cannot do this—at least to any great extent—with elements.

It also shows us that we must as pharmacologists pay attention to **molecular** as well as to **empirical composition**, and take into consideration crystalline form and physical aggregation in all observations regarding the relations between elements or compounds and living organisms. It is not sufficient, for example, to speak of the action of phosphorus on the organism as if this were invariable, for it varies with the molecular composition of the body in the red or yellow form, and isomeric organic substances may be utterly different in action.

Classification of the Elements.

The vegetable and animal kingdoms are divided into various groups. Formerly, men tried to arrange them in linear succession so that there should be an unbroken line from the lowest to the highest members of the vegetable kingdom, thence to the lowest member of the animal, and onwards up to the highest member of the animal kingdom. Such an arrangement as this, however, was found to be unnatural. Instead of the highest members of the vegetable kingdom being connected with the lowest members of the animal kingdom, it is found that the lowest members of each kingdom are closely connected and that the divergence becomes greater as development proceeds towards the highest members in each kingdom. The doctrine of **evolution** at once rendered this arrangement natural and easily understood.

Starting from one common point of origin in structureless protoplasm, the various organisms became more and more unlike in each successive stage of development, their resemblance being only recognisable at all in their embryonic condition.

Various attempts have been made to arrange inorganic substances in natural orders. One mode of **arrangement** is according to their **atomic weight**—as in the following table:—[1]

[1] In this and the following Tables the atomic weights have been corrected.

Element	Atomic Weight	Difference	Element	Atomic Weight	Difference	Element	Atomic Weight	Difference	Element	Atomic Weight	Difference
H	1		K	39	3·5	Y	89·8	2·4	Ce	141	2
Li	7	6	Ca	40	1	Zr	90	0·2	Di	145·4	3·6
Gor }	9	2	Ti	49·8	9·8	Nb	94	4	Ta	182	36·6
Be }			V	51·3	1·5	Mo	95·5	1·5	W	184	2
B	11	2	Cr	52·5	1·2	Rh	104	8·5	Ir	192·7	8·7
C	12	1	Mn	55	2·5	Ru	104·2	0·2	Pt	195	2·3
N	14	2	Fe	56	1	Pd	105·7	1·5	Au	196·5	1·5
O	16	2	Ni	58	2	Ag	108	2·3	Os	198·5	2
Fl	19	3	Co	58·9	0·9	Cd	111·8	3·8	Hg	200	1·5
Na	23	4	Cu	63·4	4·5	Sn	118	6·2	Tl	203·7	3·7
Mg	24	1	Zn	65	1·6	Sb	120	2	Pb	207	4
Al	27	3	As	75	10	I	127	7	Bi	209	3
Si	28	1	Se	78·8	3·8	Te	128	1	Th	233	24
P	31	3	Br	80	1·2	Cs	133	5	U	240	7
S	32	1	Rb	85·3	5·3	Ba	137	4			
Cl	35·5	3·5	Sr	87·4	2·1	La	139	2			

From this it will be seen that the atomic weights of the different elements form a series, the members of which in most cases differ from one another by 1, 2, 3, or 4. There are few exceptions in which the differences are much greater, and these probably represent blanks which may yet be filled up as our knowledge of the elements increases. This mode of classification, however, reminds us of the Linnæan system in plants, and is artificial rather than natural. In it, the elements which are placed close together possess very different properties, whereas those which are separated from each other present considerable resemblances.

Newland's Table.

Member of a Group having Lowest Equivalent	One immediately above the preceding	Difference	
		H = I	O = I
Magnesium . 24	Calcium . . 40	16	1
Oxygen . . 16	Sulphur . . 32	16	1
Lithium . . 7	Sodium . . 23	16	1
Carbon . . 12	Silicon . . 28	16	1
Fluorine . . 19	Chlorine . . 35·5	16·5	1·031
Nitrogen . . 14	Phosphorus . 31	17	1·062
Lowest term of Triad	Highest term of Triad		
Lithium . . 7	Potassium . 39	32	2
Magnesium . 24	Cadmium . 112	88	5·5
Molybdenum . 96	Tungsten . 184	88	5·5
Phosphorus . 31	Antimony . 120	89	5·687
Chlorine . . 35·5	Iodine . . 127	91·5	5·718
Potassium . 39	Cæsium . . 141	102	5·875
Sulphur . . 32	Tellurium . 128	96	6·062
Calcium . . 40	Barium . . 137	97	6·062

The first important attempt at a **natural classification** of the elements was made by Newlands in 1864.[1] He then arranged them in **groups,** between the members of which there was a close connection in regard to their chemical properties, and a curious relation in regard to their atomic weights. These presented differences which were generally multiples of the atomic weight of hydrogen, and generally equal to, or multiples of, that of oxygen.

A curious relationship had also been pointed out by M. Dumas [2] between the members of the potassium group, their atomic weights being equal to multiples of those of lithium and potassium added together.

Li + K = 2Na,	or in figures,	7 + 39 = 46
Li + 2K = Rb	,,	7 + 78 = 85
2Li + 3K = Cs (133) [3]	,,	14 + 117 = 131
Li + 5K = Tl (203·7)	,,	7 + 195 = 202
3Li + 5K = 2Ag	,,	21 + 195 = 216

A similar relation was also pointed out by Mr. Newlands between lithium and the calcium group; as follows:—

Li + Ca = 2Mg (48),	or in figures,	7 + 40 = 47
Li + 2Ca = Sr	,,	7 + 80 = 87
2Li + 3Ca = Ba (137)	,,	14 + 120 = 134
Li + 5Ca = Pb	,,	7 + 200 = 207

But Mr. Newland's most important table is the following one, in which he has arranged the elements in ten **series**:—

			Triad			
			Lowest term	Mean	Highest term	
I.		Li 7	+17 = Mg 24	Zn 65	Cd 111·8	
II.		B 11				Au 196
III.		C 12	+16 = Si 28		Sn 118	
IV.		N 14	+17 = P 31	As 75	Sb 120	+88 = Bi 210
V.		O 16	+16 = S 32	Se 78·8	Te 128	+70 = Os 199
VI.		F 19	+16·5 = Cl 35·5	Br 80	I 127	
VII.	Li 7	+16 = Na 23	+16 = K 39	Rb 85·3	Cs 133	+70 = Tl 203
VIII.	Li 7	+17 = Mg 24	+16 = Ca 40	Sr 87·4	Ba 137	+70 = Pb 207
IX.			V 51·3		W 184	
X.			Mo 95·5		Pt 195	
			Pd 105·7			

Seven of these series nearly correspond in their first members with those of Mendelejeff, to whom and to Lothar Meyer we owe the complete development of this mode of classification. Mr. Newlands also pointed out that the eighth element starting from a given one, was a kind of repetition of the first, like the eighth note of an octave in music.[4]

Mendelejeff has not only greatly developed this system of classification, but has afforded convincing proof of its value by not only predicting the existence of an unknown element, but actually describing its physical characters and chemical reactions—a prediction the correctness of which was proved by the discovery of gallium, and by the agreement of its characters and reactions with those which Mendelejeff had foretold.

The various members of the animal kingdom can all be arranged in a few series: Protozoa, Coelenterata, Annuloida, Annulosa, Molluscoida, Mollusca, and Vertebrata. These series all differ more or less from one another, but a

[1] Newlands, *Chemical News*, July 30, 1864.

[2] Dumas, quoted by Newlands, *op. cit.*

[3] The newer atomic weights of Cs, Fl, Mg, and Ba do not correspond so exactly as their old ones with the sum of the other elements.

[4] *Chem. News*, Aug. 20, 1864, p. 94.

certain agreement is observed between their members, and similarly the **elements** may be arranged in **series.**

Mendelejeff points out, that if we take those elements having the lowest atomic weight, and omit hydrogen, between which and lithium there is a great gap, the seven elements, lithium, glucinum, boron, carbon, nitrogen, oxygen, and fluorine, may be regarded as typical elements forming a series representing the lowest members of seven groups. The next seven elements may be arranged in a similar way :—

Li = 7 : G = 9·4 : B = 11 : C = 12 : N = 14 : O = 16 : F = 19 :
Na = 23 : Mg = 24 : Al = 27 : Si = 28 : P = 31 : S = 32 : Cl = 35·5.

To each group of seven elements Mendelejeff gives the name of a **small period** or **series.** In each series the characters of the elements vary gradually and regularly as their atomic weights increase. This variation is periodical, *i.e.* varies in the same way in each series, so that the elements which have corresponding places in each series, correspond also to a certain extent in their properties, and form similar compounds. The atomicity is least in the first, and greatest in the last members of each series. Thus the first members of the series form monochlorides, the second dichlorides, the third trichlorides, and so on.

In the accompanying table R represents radical or element, and R^{i} indicates that the element is monatomic, so that one atom combines with one of Cl to form a monochloride, RCl. R^{ii} indicates that the element is diatomic, and so on.

But a difference is to be observed between the even and the uneven series. Corresponding members of even series, such as the fourth and sixth, agree with each other, and members of uneven series like the fifth and seventh agree. This agreement is greater than between the members of an even series, such as the fourth, and those of an uneven series like the fifth, although the fifth is more closely placed to the fourth than the sixth is. Thus Ca and Sr belonging to the fourth and sixth series have a greater resemblance to each other than they have to Zn or Cd, which belong to the fifth and seventh series, and these metals on the other hand have a greater resemblance to each other than they have to Ca or Sr. The members of even series are less metalloidal or more metallic than those of uneven series, *e.g.* Mn of the fourth series is less metalloidal than Br of the fifth series. In the even series the metallic or basic character predominates, whilst the corresponding members of the uneven series rather exhibit acid properties. The members of the even series, so far as we know, form no volatile compounds with hydrogen or alcohol radicals, while the corresponding members of the uneven series do form such compounds.

The last members of the even series resemble in many respects (in their lower oxides, etc.), the first members of the uneven series; thus chromium and manganese in their basic oxides are analogous to copper and zinc. But there are great differences between the last members of the uneven series (haloids), and the first members of the next even series (alkali metals). Now between the last members of the even series there occur, according to the order of atomic weights, all those elements which cannot be included in the small periods. Thus between Cr and Mn in the one series, and Cu and Zn in the next, there come the elements Fe, Co, Ni, and in a similar way after the sixth series come Ru, Rh, Pd, and after the tenth Os, Ir, Pt. Mendelejeff gives the name of a **long period** to two such series with three intervening members, forming seventeen in all.

From the difficulty of arranging all the elements in this system, it cannot be regarded as yet perfect, but the fact that Mendelejeff was able so correctly to foretell the properties of gallium, shows that it must contain a large element of truth. At the time that he drew up his table there was a blank in the third group of the fifth series.

The relationships of the metal which Mendelejeff believed would fill this

MENDELEJEFF'S CLASSIFICATION OF THE ELEMENTS.

Series	Group I. $R^{I}_{2}O$ $R^{I}Cl$	Group II. $R^{II}O$ $R^{II}Cl_2$	Group III. $R^{III}_{2}O_3$ $R^{III}Cl_3$	Group IV. $R^{IV}H_4$ $R^{IV}O_2$ $R^{IV}Cl_4$	Group V. $R^{V}H_3$ $R^{V}_{2}O_5$ $R^{V}Cl_5$	Group VI. $R^{VI}H_2$ $R^{VI}O_3$ $R^{VI}Cl_6$	Group VII. $R^{VII}H$ $R^{VII}_{2}O_7$ $R^{VII}Cl_7$	Group VIII. — $R^{VIII}O_4$ $R^{VIII}Cl_8$
1	H = 1							
2	Li = 7	G or Be = 9·4	B = 11	C = 12	N = 14	O = 16	F = 19	
3	Na = 23	Mg = 24	Al = 27·3	Si = 28	P = 31	S = 32	Cl = 35·5	
4	K = 39	Ca = 40	— = 44	Ti = 48	V = 51	Cr = 52	Mn = 55	Fe = 56 Co = 54 Ni = 59 Cu* = 63
5	(Cu* = 63)	Zn = 65	—† = 68	— = 72	As = 75	Se = 78	Br = 80	
6	Rb = 85	Sr = 87	? Yt = 89	Zr = 90	Nb = 94	Mo = 96	— = 100	Ru = 104 Rh = 104 Pd = 106 Ag* = 108
7	(Ag* = 108	Cd = 112	In = 113	Sn = 118	Sb = 122	Te = 125	I = 127	
8	Cs = 133	Ba = 137	? Di = 138	? Ce = 140	—	—	—	— — — —
9	(—)	—	—	—	—	—	—	
10	(—)	—	Yb = 173	La = 180	Ta = 182	W = 184	—	Os = 199 Ir = 193 Pt = 195 Au* = 196
11	(Au* = 196	Hg = 200	Tl = 204	Pb = 206·5	Bi = 208	—	—	
12	—	—	—	Th = 231	—	U = 240	—	—

* Cu, Ag, and Au are included in Group I. on account of their forming cuprous, argentous, and aurous oxides, but on account of their resemblance in many respects to the metals in Group VIII. they are also included in it. † This blank has now been filled up by the discovery of gallium.

gap will be more easily seen by omitting the even series on either side of it, and taking only the odd series with which it will, as already mentioned, the more closely correspond.

Series.	Group II.	Group III.	Group IV.	Group V.
3	Mg	Al	Si	P
5	Zn	—	—	As
7	Cd	In	Sn	Sb

As it stands between zinc with an atomic weight of sixty-five, and arsenic with one of seventy-five, while it is separated from the latter by a blank, its atomic weight must be about sixty-eight. As it is atom-analogous with Al, its salts should have a similar constitution. It should form an oxide x_2O_3, and a sulphide x_2S_3. It will be precipitated from its solution by ammonium sulphide. The metal should be easily reduced by carbon or sodium, it should have a specific gravity of 5·9, and decompose water at a red heat. As it belongs to an odd series, it should, like zinc, form volatile compounds with organic radicals, and form also anhydrous chlorides.

On the discovery of the metal gallium, it was found to agree in almost every respect with the prediction of Mendelejeff, and this fact is not interesting to chemists only, but also to pharmacologists. For the great **object of pharmacology** is to obtain such a knowledge of the relations between the physical and chemical characters of bodies, and their actions upon the living organism, that we may be able to predict their **actions** with certainty, and to know the modifications which alterations in their physical and chemical characters will produce on their physiological action.

Mendelejeff's present classification is imperfect, because we find that by it the members of some natural groups, such as those of the earthy metals, are separated from one another, although they agree in their chemical characters.

We find also that metals having similar pharmacological actions, as copper, zinc and silver, do not fall naturally together in this arrangement. But, on the other hand, we find also that by this classification, elements are brought together which do not at first seem to have any resemblance to each other, and are yet found by recent investigations to have a physiological connection. Thus mercury and calcium do not appear to resemble one another, yet Prevost has shown that, in acute poisoning by mercury, the calcareous matter disappears from the bones, and in the process of elimination by the kidneys produces calcification of these organs.[1]

Organic Radicals.—Whether the so-called elements be compounds or not, it is certain that several of them have the power of uniting with themselves and with others in such a way as to form bodies called compound radicals which resemble elements in many respects. These groups of atoms may enter into and again pass out of combination with other substances, just as elements do.

For example, when compounds of the elements unite, an interchange of elements takes place. Thus when calcium oxide (CaO) and hydrochloric acid (HCl) combine, the oxygen leaves the calcium to combine with the hydrogen and form water, while the chlorine leaves the hydrogen and combines with the calcium to form calcium chloride.


$$CaO + 2\,HCl = CaCl_2 + H_2O.$$

[1] Prevost, *Revue Médicale de la Suisse Romande*, p. 553, Nov. 15; p. 605, Dec. 15, 1882; p. 5, Jan. 15, 1883.

But when ethylic alcohol (C_2H_6O) is treated with hydrochloric acid (HCl), it is not oxygen which leaves the alcohol and is replaced by chlorine. The alcohol does not split up into the group C_2H_6 and the element oxygen, but into the two groups OH and C_2H_5.

$$C_2H_6O + HCl = C_2H_5Cl + H_2O\,;$$

or, as it may also be represented—




To the group OH the name of hydroxyl has been given, and to the group C_2H_5 that of ethyl.

Similarly, when acetic acid ($C_2H_4O_2$) is treated with phosphorus trichloride (PCl_3) the three atoms of chlorine leave the phosphorus, and are replaced by three hydroxyl (OH) groups.

$$3\,C_2H_4O_2 + PCl_3 = 3\,C_2H_3OCl + PO_3H_3\,;$$

or, as it might be represented—



This mode of representation is awkward and cumbrous, although it is clear, and the same reactions may be represented more shortly thus :

$$3\,C_2H_3O.\,OH + PCl_3 = 3\,C_2H_3O.\,Cl + P\,.\,(OH)_3.$$

Here again it is not oxygen, but hydroxyl (OH), which breaks off from the acetic acid, just as it did from alcohol ; but instead of the group C_2H_5 (ethyl) being left behind, we have another group, C_2H_3O (acetyl).

It is evident that such groups of atoms or radicals, as they are termed, as hydroxyl, ethyl, acetyl, &c., behave in combination just like elements. They are not known in a free state.

In order to exhibit the valency and probable relationships of radicals, they are sometimes expressed by graphic formulas, in which the affinities are shown by a —, as well as in the ways already shown.

As the position of the radicals in some compounds, *e.g.* in the organic alkaloids, is probably of great importance in regard to their action, although the subject is not well understood at present, the most important radicals are given below, with their graphic as well as their ordinary formula.

Hydroxyl, OH, or —O—H. This is a monad radical, consisting of one atom of dyad oxygen, —O—, with one of its

two affinities saturated by an atom of hydrogen, and the other affinity free. It was at one time called water-residue, as it is the residue left after the removal of one atom of hydrogen from water, which may be regarded as the hydride of the radical.

Hydroxyl is an important constituent of alcohols, regarding the chemical constitution of which two views may be taken. They may either be looked on as water in which one atom of hydrogen is replaced by organic radicals, or as compounds of the radicals with hydroxyl. The constitution of water and alcohol may be represented graphically, R standing for a monad organic radical—

H—O—H water;

R—O—H alcohol, *e.g.*, (Ethyl)—O—H; (Phenyl)—O—H

Ethyl-alcohol. Phenyl-alcohol, or Phenol.

The presence of the hydroxyl group in certain substances, and also its position in them,[1] appear to be of great importance in regard to their physiological action.[2]

By replacing the hydrogen in one atom of hydroxyl by a monad, or in two atoms by a dyad element, other radicals are formed, *e.g.*

Potassoxyl, KO, or —O—K.

Zincoxyl, OZnO, or —O\ /Zn.
—O/

When united to carbonyl, hydroxyl forms a very important radical carboxyl.

Carbonyl, CO or $-C(=O)-$, is a dyad radical consisting of tetrad carbon, in which two affinities are saturated by dyad oxygen, and two left free. It exists in aldehydes, ketones, and acids, although in aldehydes it is combined with hydrogen, and in acids with hydroxyl, to form other radicals. In ketones both its free affinities are saturated by organic radicals, which may either be of the same kind or of different kinds.


R—C(=O)—R, *e.g.* (Methyl)—C(=O)—(Methyl) (Phenyl)—C(=O)—(Methyl)

Acetone. Phenyl-methyl-acetone.


Aldehyde Group, CHO, or $-C(=O)-H$. When the free affinity

[1] Efron, *Pflüger's Archiv*, xxxvi. p. 467.
[2] Stolnikow, *Zeitschr. f. physiol. Chem.*, 1884, viii. pp. 235 and 271.


of this group is saturated by a monatomic radical, we get aldehydes; thus—





Ethyl-aldehyde.




Benzoic aldehyde
(oil of bitter almonds).

Carboxyl, CO.OH, or $\left.\begin{matrix}CO\\H\end{matrix}\right\}O$, or . This is a monad radical. When its free affinity is saturated by an organic radical, it forms monad organic acids, in which the hydrogen of the hydroxyl is readily replaced by a basic element.



R—C—H—O, *e.g.*




Acetic acid.



Benzoic acid.





Sodium acetate.




Sodium benzoate.

Carbon forms an immense number of radicals by union with itself and with hydrogen, *e.g.*



Methyl.



Ethyl.


Phenyl.

Nitrogen gives origin also to a number of most important radicals.

Nitroxyl, NO_2.

Amidogen, NH_2, or .

Imidogen, NH or .

Phosphorus, arsenic, and **antimony** give origin also to a number of radicals similar to those of nitrogen.

PH_2, or $-P\langle^{H}_{H}$; SbH_2, or $-Sb\langle^{H}_{H}$; AsH_2, or $-As\langle^{H}_{H}$

PH, or $-P\langle^{H}$; SbH, or $-Sb\langle^{H}$; AsH, or $-As\langle^{H}$

Sulphur also gives origin to some important radicals.

Sulphuryl (sulphon), SO_2, or $\rangle S\langle^{O}_{O}$; Sulphin, SO, or $-S\langle^{O}$

Chemical Reactions and Physiological Reactions.—Each element and each of its compounds has chemical reactions special to itself, by which it can be recognised and distinguished from all others. The number of these chemical reactions is therefore very great, but there are a few reactions which are common to a great number of the elements. We shall find that something similar occurs in their physiological reactions.

The number of possible actions which may be exerted on the body by the elements and their compounds is very great, yet we shall find that there are certain physiological reactions which are common to so many that their repetition under the head of each drug becomes monotonous.

Chemical Reactions.—Although the chemical reactions of the metallic elements are numerous and varied, yet there are certain reactions which are common to a very large number, and by these the class of metallic elements may be subdivided into sub-classes. Other reactions again are common to a few elements only, and by these the sub-classes may be subdivided into groups. Other reactions again are peculiar to each individual element, and by them it may be distinguished from all others.

Thus, by the use of hydrogen sulphide, or ammonium sulphide, we at once divide the class of metallic elements into two sub-classes:

A. Metals which give a precipitate with one or other of these reagents.

B. Metals which give no precipitate with either.

Physiological Reactions.—It is probable that, if our knowledge of physiological chemistry were sufficient, we might be able to classify physiological reactions according to the chemical relation between substances introduced into the organism and the various constituents of the organism itself. At present we

are quite unable to do this; but, as albuminous substances form an essential part of all living organisms, we may roughly divide the elements physiologically, by their relation to albumen, just as we do it chemically, by their relation to sulphur, into two sub-classes:

A. Those which precipitate albumen.

B. Those which do not.

Just as in the case of sulphides, we might further sub-divide sub-class A into two sections:

(*a*) Those which precipitate albumen in acid solutions.

(*b*) ,, ,, ,, in neutral or alkaline solutions.

Section (*b*) may be further sub-divided into groups according to the kind of albuminous bodies which its members precipitated, *e.g.*, myosin, globulin, serum-albumen, albumoses, peptones, &c.

We might also divide sub-class B in two sections:

(*a*) Substances which, though they do not precipitate albumen, have a marked affinity for fatty substances or other constituents of the organism, and especially of the nervous system (p. 144).

(*b*) Substances having no such action.

It is evident that such a classification as this, although it might form the groundwork of a system to be perfected at some future time, is at present so imperfect that it is generally more convenient to divide physiological reactions according to the organs affected: e.g., muscles, nerve-centres, respiration, circulation, secretion, &c.

A. This group contains substances which **paralyse muscles** and **motor nerves.** The number of these substances is very great (p. 126 *et seq.*, p. 150).

This large group can again be subdivided into those which (*a*) paralyse muscle, while affecting the nerves but slightly, or (*b*) paralyse the nerves and leave the muscle uninjured.

B. Another large group is that which acts specially on **nerve-centres,** and has little effect either on muscles or motor nerves. This contains sub-groups of substances which affect the brain, medulla, or spinal cord by exciting, paralysing, or disturbing the functions of each.

C. Another group is that which affects the **secretions,** with sub-groups of substances affecting the secretions from the sweat and mammary glands, salivary, gastric, or intestinal glands, liver, or kidneys.

D. Another group still is that which acts chiefly upon the **circulation.**

These groups are all more or less distinct, although they, to a certain extent, may run into, or overlap, each other.

Individual members of the same group may differ very widely in their physiological action, even when they all finally paralyse

muscle, nerves, and nerve-centres. For while they may produce the same final result, the course of their action will be different, and the symptoms they occasion will depend very greatly upon the part of the organism which they affect first. Thus atropine and curare both completely paralyse motor or efferent nerves, but, while a very large dose of curare is required to paralyse the cardiac and vascular nerves, a very small dose paralyses those going to the muscles, and produces increasing weakness, gradually passing into death. On the other hand, an enormous dose of atropine is required to paralyse the motor nerves of muscles, but very small doses are sufficient to affect the nerves of the heart and other involuntary muscles, and thus we get rapid circulation, dilated pupil, and restless delirium.

The physiological action of any drug depends to a great extent, not merely on its general affinities for classes of tissues, but upon its particular affinity, or power of acting on one tissue or organ first. The organ first affected may, through its functional activity, greatly alter the effects of the drug upon the others.

As an example of this we may take the effects produced by very large and by moderate doses of veratrine on the frog. A moderate dose will produce great stiffness of the muscles, while a very large dose may have comparatively little effect. Yet if the large dose were applied directly to the muscles it would act more powerfully than the moderate dose. The reason that it does not do so in the living body is that the large dose paralyses the heart so quickly that the circulation stops, and therefore the poison, not being conveyed to the muscles, has no action upon them.

Relation between Isomorphism and Physiological Action.—From a number of experiments made by Dr. Blake, he concluded that when inorganic salts were injected directly into the circulation, the intensity of their physiological action increased in proportion to their molecular weight, but only in those groups of elements where the salts were isomorphic, or in other words, crystallised in the same forms. Thus groups whose salts were crystallised in different forms had quite different physiological actions. He adopts Mitscherlich's division of the elements into nine groups, and considers that the physiological action of the different groups differs in kind, whilst that of the individual members of the same group agrees in kind but differs in degree. Thus he states [1] that the salts of the first group increase in activity in the order mentioned, silver being the most active, and lithium the least.

---

[1] Blake, *American Journal of Science and Arts*, vol. vii., March 1874 (corrected reprint).

These groups are as follows:—

Group 1. Lithium, sodium, rubidium, thallium, cæsium, and silver. According to him they produce death by acting on the lungs and impeding the pulmonary circulation. None of them affect the nervous system excepting cæsium; nor do any affect the pulmonary circulation excepting silver.

Group 2. Magnesia, ferrous salts, manganous salts, nickel, cobalt, copper, zinc, and cadmium are increasingly lethal in the order mentioned. They kill by arresting the action of the heart.

Group 3. Beryllium, alumina, yttria, cerium, and ferric salts both impede the systemic and pulmonary circulation.

Group 4. Calcium, strontium, barium, and lead salts kill by paralysing the ventricles of the heart.

Group 5. Palladium, platinum, osmium, and iridium act on the heart, respiration, circulation, and blood.

Group 6. Ammonia and potash paralyse the heart and cause convulsions.

Group 7. Hydrochloric, hydriodic, bromic, and iodic acids impede the circulation and kill by arresting the circulation.

Group 8. Phosphoric acid, arsenic acid, and antimony kill by arresting the pulmonary circulation.

Group 9. Sulphuric and selenic acid impede the pulmonary circulation.

The author's statements regarding the mode of action of the elements show that their physiological action has not been fully investigated, and his results as to the lethal dose are probably only approximate and may want re-investigation; but while we cannot accept at present all his results or conclusions as final, yet his last and chief conclusion is one of great interest—viz., that in living matter we possess a reagent capable of aiding us in our investigations on the molecular properties of substances.

Relation between Spectroscopic Characters and Physiological Action.

The quickness with which a pendulum oscillates is less or greater according to its length, a long one oscillating slowly, and a short one quickly. The vibrations of a string or pipe are also slow or quick, and the note which it yields is low or high, according as it is long or short.

Similarly, according to Lecoq de Boisbaudran, the rate of vibrations of molecules, and the wave-lengths of the light which they emit, are determined by their weight. When the molecular weight is high, the vibrations of the molecules are slow, and the light which they emit has long wave-lengths, and is situated towards the red end of the spectrum. When the weight is low the vibration of the molecules is rapid; and the light they emit lies towards the violet end of the spectrum.

In the same family of elements the mean length of the wave of light which they emit is a function of their atomic weight, so that for bodies of the same chemical type the general form of the spectrum persists, but is gradually modified by the mass of the molecules. As the atomic weight diminishes, the spectrum will tend to ascend towards the violet, and as it increases the spectrum will tend to descend towards the red.

Until recently, our observations on the spectra of bodies were limited to the visible spectrum, but the application of photography now enables us to extend our observations both above and below the visible spectrum, and to ascertain the presence of definite spectra in the ultra-red and ultra-violet, when nothing of the sort is visible to the eye. In most musical sounds besides the fundamental note we have a number of harmonics having a much greater rapidity of vibration than it. Similarly, in the spectrum there appear harmonics as well as the fundamental spectral lines, and so instead of one

line or band there may be a number. According to the author already quoted, the corresponding harmonics in a series of analogous spectra have mean wave-lengths which increase in proportion to the weight of the molecules.

It might appear, therefore, that a relation might be observed between the spectroscopic characters and physiological action of an element, and this idea was propounded by Papillon. His idea was, however, to a great extent based on the experiments of Rabuteau referred to later on, and just as no definite relation can be at present traced between the atomic weight and the toxic action of a metal, so no definite relation can be observed between its spectroscopic characters and its physiological action.

Further consideration, however, will show us that this is not at all to be wondered at, for in physiological experiments we are not working with the same molecules which yield the spectrum.

In spectrum-analysis, when line spectra are in question, according to one view we are in presence of phenomena produced by the chemical atom, whereas this atom exists only molecularly combined at lower temperatures. According to another view, that put forward by Lockyer, we are in presence of phenomena produced by a series—possibly a long series—of simplifications, brought about by the temperature employed, and this simplification can begin at very low temperatures, and is indeed indicated by Dalton's law of multiple proportions.

Such molecular simplifications and differences are represented by ozone and oxygen, ordinary and amorphous phosphorus, the various forms of sulphur and so on, and it is therefore at this lower range of temperature—where the phenomena are to be studied by absorption, and not by radiation—that we must look for connections between molecular structure and physiological action if any such connection exists.[1]

Some of the absorption bands which occur in the spectra of bodies at ordinary temperatures may be in the visible spectrum, like those observed in alcoholic and aromatic substances;[2] but others may be quite invisible, and only recognisable by the aid of photography in the ultra-red or ultra-violet.[3]

Relation between Atomic Weight and Physiological Action.

From experiments made on the toxic action of the chloride, bromide, and iodide of potassium, Bouchardat and Stewart Cooper came to the conclusion that a relation existed between the physiological activity of elements and their atomic weight, the activity being inversely as their atomic weight, *e.g.* fluorine (atomic weight, 19) being more active than chlorine (atomic weight, 35·5).

In 1867, Rabuteau made a number of experiments from which he concluded that Bouchardat was correct in saying that the physiological activity of the monatomic metalloids was in inverse proportion to their atomic weight, while that of the diatomic metalloids increased directly with their atomic weight: selenium being more active than sulphur.

He considered also that he had discovered a new law regarding the relation between the atomic weight and the physiological activity of metals: viz., that the activity of metals increases with their atomic weight. He afterwards qualified this statement by saying that the poisonous action increased with the atomic weight amongst elements belonging to the same group. Thus potassium (atomic weight, 39) is more poisonous than sodium (23), and barium (137) than calcium (40). But it has been shown by Husemann that lithium is much more poisonous than sodium, and his results have been confirmed by Richet.

In the following table the lethal activity of various metals is given as

[1] *See* Hartley, *Phil. Trans.*, Part II. 1885.

[2] Russell and Lapraik, *Journ. Chem. Soc.*, April 1881.

[3] Abney and Festing, *Phil. Trans.*, 1882, p. 887.

determined by Richet, and of the metals belonging to the groups of the alkalis and earths as determined by Richet, by Cash and myself, and by Botkin, jun. Where the position of the metals in the tables is different the symbols are printed in italics. The most active, Hg, is first; the least active, Na or Ca, last.

Richet	Brunton and Cash	Botkin, junr.	Atomic Weight	Richet	Brunton and Cash	Botkin, junr.	Atomic Weight
Hg	—	—	200	—	Cs	Cs	133
Cu	—	—	63·4	Li	Li	Li	7
Zn	—	—	65	Mn	—	—	55
Fe	—	—	56	*Ba*	—	—	137
Cd	—	—	111·2	Mg	—	—	24
NH_4	—	—	18	—	La	—	139
K	K	K	39	—	Di	—	145·4
—	Be	—	9	—	Er	—	166
—	Rb	Rb	85·3	Sr	Sr	—	87·4
Ni	—	—	58	—	Yt	—	89·8
Co	—	—	58	*Ca*	*Na*	—	40 | 23
—	*Ba*	—	137	*Na*	*Ca*	—	23 | 40
—	NH_4	—	18				

Richet's experiments were made upon fish, and the substances were added to the water in which the animals were swimming. The experiments of Cash and myself were made upon frogs, and the substances were injected subcutaneously. Botkin's experiments [1] were made upon dogs, and the substances were injected directly into the circulation.

It is possible that the differences observed were due to the differences in the animals on which the experiments were made, or in the way of applying the poison. Botkin's table, so far as it goes, agrees perfectly with Cash's and mine, and there is a general correspondence also between Richet's results and ours, although there are several differences in particulars.

It is thus evident that the relationship between atomic weight and physiological action is no simple one. But indeed, on looking into the matter more closely, we could hardly expect it would be. For the toxic action of an element may depend upon its effect on the muscles, nerves, nerve-centres, blood, or on the digestive or excretory systems. These differ from one another in their composition, and while it is possible that the elements belonging to a certain group may have relations varying with their atomic weight to individual organs or structures, we can hardly expect those relationships to be the same to all organs.

Thus an element with one atomic weight may prove fatal, by affecting the muscular power of an animal, while another with an atomic weight either higher or lower, may be still more deadly by affecting the nervous system or heart.

What we want, therefore, is not a general relationship between atomic weight and toxic action, but a knowledge of the particular relationships of each group of elements to each organ and tissue of the body.

Relation of Atomic Weight and Smell.

The idea has been put forward by Ramsay that the sense of smell is excited by vibrations of a lower period than those which give rise to the sense of light or heat. These vibrations are conveyed by gaseous molecules

[1] S. Botkin, junr.: 'Zur Frage über den Zusammenhang der physiologischen Wirkung mit den chemischen Eigenschaften der Alkalimetalle der ersten Gruppe nach Mendelejeff,' *Centralb. für die med. Wissenschaft.* No. 48, 1885.

to the surface network of nerves in the nasal cavity. The difference of smells is caused by the rate and by the nature of such vibrations, just as difference in tone of musical sounds depends upon the rate and on the nature of the vibration—the nature being influenced by the number and pitch of the harmonics. Just as the eye and ear are capable only of appreciating sight or sound vibrations occurring within a limited range, so the nose is unable to appreciate a smell the result of the rapid vibrations produced by substances of low molecular weight. Hydrocyanic acid appears to be at the lowest limit, as one in five are, according to him, unable to detect its odour. It is fifteen times the molecular weight of hydrogen, and he concludes that to produce the sensation of smell a substance must have a molecular weight at least fifteen times that of hydrogen. The intensity of smell in bodies of similar constitution increases with the molecular weight; thus, methyl-alcohol is odourless, but the intensity of smell increases with the molecular weight of each succeeding member of the alcohol group, until the limit of volatility is reached, and they become changed into solids with such a low vapour tension that they give off no appreciable amount of vapour at the ordinary tension.[1]

Relation of Atomic Weight to Taste.

Haycraft considers[2] that 'quality' in taste depends upon the nature of the atoms found in the sapid molecule. A study of the periodic law demonstrates that similar tastes are produced by combinations which contain elements such as lithium, sodium, potassium, which show a periodic recurrence of ordinary physical properties. Among the carbon compounds, those which produce similar tastes are found to contain a common 'group' of elements. Thus organic acids contain the group CO.OH, the sweet substances CH_2.OH. There is no relation between quality of sensation and gross molecular weight, except that substances of either very small or very great molecular weight are not tasted at all.

Connection between Chemical Composition and Physiological Action.

In considering this subject and other subjects allied to it, we must carefully distinguish between chemical composition and chemical constitution; between the mere elements of which a compound is formed and the manner in which these elements are put together. Thus the cyanides, or nitriles, and the isonitriles, or carbamines, both contain carbon and nitrogen, and contain them in equal proportions; but the manner in which the carbon is united with the nitrogen probably differs in the two classes, and their physiological action is different. Their chemical composition is the same, but their chemical constitution is different.

It was pointed out by Blake in 1841 that a close connection exists between the chemical constitution and physiological action of salts; their physiological action on animal organisms appearing to depend chiefly on the base. Yet the physiological action of any salt is not dependent entirely upon the base. It may be, and sometimes is, modified to a very great extent by the acid; moreover, we find that the salts which the same inorganic base

[1] *Nature*, June 22, 1882, p. 187.
[2] *Ibid.*, Oct. 8, 1885, p. 562.

may form with different acids may present very different physiological actions, as in the case of the carbonate, bromide, and cyanide of potassium. The same is the case with organic bases, and Richardson, in 1865, drew attention to an example of the relation between the action of the base and acid in the amyl compounds. He found that amyl-hydride had an anæsthetic effect; the introduction of oxygen, as in amyl-alcohol or amyl-acetate, added spasm to this action; amyl-iodide produced a large excretion of fluid from the body, while amyl-nitrite had a great effect on the circulation. Thus, the base remaining the same, different acid radicals modified the action of the compound.[1]

The fact is that sometimes the action is determined chiefly by the base (whether it be inorganic or organic), and sometimes chiefly by the acid. The action of the whole salt may differ to a great extent from that of the substances composing it, and it may agree to some extent with other salts, which differ from it both in regard to the base and acid composing them; thus—the sulphate of magnesium and the sulphate of sodium are both purgative, and in this property they agree not only with the sulphate of potassium, in which the base is different although the acid is the same, but with the bitartrate of potassium, in which both the base and the acid are different. This fact confirms what has already been said regarding the necessity for taking into consideration crystalline form and physical aggregation, as well as chemical composition (p. 15).

Physiological Action of the Constituents of a Drug.—In the case of acids and bases, the physiological action of each is modified by their union, *e.g.* when caustic soda and hydrochloric acid unite, the caustic action of each is destroyed, and we obtain sodium chloride and water, which have different physiological actions, as well as different chemical characters, from either the acid or the base.

But if we examine a series of salts of the same base with different acids, or of the same acid with different bases, we find that both the acid and the base modify the physiological action of the compound.

Different Acids.			Different Bases.		
Sodium	hydrate	*caustic.*	Sodium	chloride	*neutral in action.*
,,	bicarbonate	*antacid.*	Potassium	,,	*muscular poison.*
,,	sulphate	*purgative.*	Zinc	,,	*caustic.*
,,	benzoate	*antilithic.*	Barium	,,	*muscular poison.*
,,	salicylate	*antipyretic.*	Silver	,,	*inert.*
,,	cyanide	*powerful poison.*	Iron	,,	*astringent, hæmatinic.*
			Mercuric	,,	*corrosive, antiseptic.*

This modification is in some cases due to a change in the

[1] *Brit. Assoc. Reports*, 1865, p. 280.

physical conditions, and especially in the solubility of the compound. Thus the chloride of silver is inert so long as it remains in the form of a chloride, because it is insoluble. It thus differs much from the corrosive chloride of zinc, while if we were to compare the action of the nitrate of silver and zinc we should find considerable similarity.

Another cause of difference is the different **proportion of the acid to the base.**

Thus the proportion of sodium (Na=23) to the acid radical in the following sodium salts is as follows: in the hydrate as 23 to 18; in the bicarbonate as 23 to 61; in the sulphate as 23 to 96; in the benzoate as 23 to 121; in the salicylate as 23 to 137.

In this connection, too, the degree of **saturation of the acid** by the base must be considered. If, for example, the acid is not saturated, part of the action of the compound is due to its acid chemical properties; and if, on the other hand, a weak acid be combined with a strong base, this action is partly due to the alkaline chemical property.

Relation between Physiological Action and Chemical Constitution.

An immense step has been made of late years in our knowledge of the relation between chemical constitution and physiological action by the discoveries of Crum-Brown, Fraser, and Schroff, who have shown that by modifying artificially the chemical constitution of a drug it is possible to modify also its physiological action. And not only so, but they have shown that similar modifications in the chemical constitution of various drugs induce similar modifications in the action of their derivatives; thus they have found that by introducing methyl into the molecule of strychnine, brucine, and thebaine, the convulsive action exerted by these substances on the spinal cord was changed into a paralysing one exerted on the ends of the motor nerves. Other alkaloids, also, which do not exhibit a convulsive action, nevertheless exhibit a paralysing one when their constitution is altered by means of methyl; thus methyl-codeine, methyl-morphine, methyl-nicotine, methyl-atropine, methyl-quinine, methyl-veratrine, and several others, all exhibit this paralysing action (p. 150).

As a general rule, most of the compound radicals formed by the union of amidogen with the radicals of the marsh-gas series possess a paralysing action on motor nerves.

The subject of the connection between chemical constitution and physiological action is the most important one in pharmacology, and we shall have to return to it in considering the actions of various groups of organic substances.

CHAPTER II.

CIRCUMSTANCES WHICH AFFECT THE ACTION OF DRUGS ON THE ORGANISM.

One of the most important circumstances affecting the action of any drug is the mode in which it is brought into contact with the various parts of the organism.

Local and Remote Action.—The **local** action of a drug is that which it exerts on the part to which it is applied. Thus sulphuric acid has a direct irritant or destructive action, and when applied to the skin or mucous membrane will produce local redness, inflammation, or sloughing. When swallowed, it produces weakness of the circulation, stoppage of the heart, and death.

This effect on the circulation is not due to the direct action of the acid upon the heart, the vessels, or the nervous system, after its absorption: it is due to the reflex action exerted upon them by the irritation of the nerves of the stomach which the sulphuric acid produces. This action on different parts through the nervous system is termed its **remote** action, in contradistinction to the local action of the acid upon the gastric mucous membrane.

The Interaction of various functions in the body is one of the greatest difficulties in the way of our readily understanding the action of drugs.

One function alters another, and the second reacts upon the first, so that in some cases it is almost impossible to say precisely how far the alteration in any function is due to the direct effect of the drug upon it, and how far to some indirect action. Thus curare when applied to a wound usually kills without producing any convulsion whatever. It paralyses the ends of the motor nerves, so that all the muscles in the body become powerless. But when it is given by the stomach, and excretion through the kidneys prevented, death is preceded by convulsions. These convulsions are not caused by any direct irritating action of the curare itself upon the nerve-centres; they are due to irritation of these centres by a venous condition of the blood. This venosity of the blood is due to imperfect respiration, produced by paralysis

of the respiratory muscles through the action of curare on the motor nerves.[1]

The effect of curare is a purely paralysing one, both when the animal dies quietly and when it dies with convulsions. In both cases it paralyses the motor nerves of the respiratory muscles and of the extremities. In both cases it causes death by arresting the respiration and producing asphyxia. But in the latter case the motor nerves of the extremities being only partially paralysed when asphyxia occurs, they respond by convulsive movements to the irritation of the nerve-centres, which the venous blood produces. In the former, the paralysis of the limbs being complete, the muscles remain perfectly quiet, notwithstanding the irritation of the nerve-centres.

Convulsions also sometimes occur previous to death from narcotic poisons: and in a description of the action of these poisons we frequently meet with the phrase, 'coma, convulsions, and death.' In such cases the convulsions are also caused by the irritation of the nerve-centres by asphyxial blood.

The drug causes the coma; the coma causes imperfect respiration; imperfect respiration renders the blood venous; and the venous blood causes convulsions.

Direct and Indirect Action.—The **direct** action of a drug is the effect it produces on any organ with which it comes in contact. Thus sulphuric acid applied to the skin, or taken into the stomach, will, according to its degree of concentration, irritate or destroy the mucous membrane which it touches. Its *direct* action upon them is therefore that of an irritant or caustic.

Curare, when applied to the ends of a motor nerve in a muscle, paralyses them. It does this either when the muscle is soaked in a solution of curare, or when the curare is carried through the substance of the muscle by means of the blood circulating in it.

Paralysis is therefore the direct effect of curare on the motor nerves.

The convulsions which sometimes occur in poisoning by curare are caused by its **indirect** action. It has no stimulating effect on the nerve-centres, when applied to them directly or caried to them by the blood, but by paralysing the muscles of respiration, and thus causing asphyxia, it indirectly irritates the nerve-centres, and causes convulsions.

Selective Action of Drugs.—Drugs sometimes seem to affect only one part of the body and to leave the other organs unaffected; although the drugs may be carried equally by the blood to every part of the body, they appear to combine with some and not with others. Many dye-stuffs will not attach

[1] Hermann, *Arch. f. Anat. u. Physiol.*, 1867, 64, 650.

themselves to cotton fabrics, but will do so readily to wool or silk; and we find that different tissues, and even different parts of the same tissue, have very unequal attractions for stains: thus some anilin colours will deeply stain a nucleus, while leaving the cell in which it is contained entirely uncoloured. Although the different organs of the body contain many substances in common, yet their chemical composition varies within wide limits, and the products of the tissue-waste are also different. Even in the same organs the cells may have different properties, and even individual parts of the same cell may differ. Some have a reducing, and others an oxidising action; some an alkaline, and others—as may be ascertained from their action on anilin colours[1]—an acid, reaction (p. 70). We would therefore expect that, just as the tissues exert a selective action upon dye-stuffs which we are able to see, they will also have a selective action on many organic substances, although this action may not be visible to our senses.

Primary and Secondary Action.—I have already stated (p. 5) that the so-called action of a drug is not one-sided: it is the reaction between the drug and the organism. While drugs are circulating in the body they may modify the chemical nature and the physiological functions of various organs. In some cases the drug, after doing this, may again leave the organs and be eliminated without undergoing any essential change; but in other cases the chemical character of the drug itself undergoes an essential change during its sojourn in the body. Some organic substances undergo complete combustion, and are converted into carbonates, while others are converted into substances having a powerful physiological action, but perfectly different from that of the substance originally introduced into the body. These products of the decomposition of the drug may then, while circulating in the blood, or during the process of excretion, exert upon the organism a marked physiological action quite different from that of the original substance. Perhaps one of the most marked examples of this is to be found in morphine. Morphine lessens the irritability of nerve-centres, producing sleep, and having a marked sedative action upon the stomach in allaying vomiting, either when introduced directly into the stomach or injected into the circulation. This is its primary action; but in the body morphine undergoes certain alterations and becomes partly converted into oxy-dimorphine, which appears to counteract the soporific action of morphine, and probably either oxy-dimorphine or some other product of the decomposition of morphine has an emetic action. The effect of these secondary products will manifest itself after the original

[1] P. Ehrlich, 'Ueber die Methylenblaureaction der lebenden Nervensubstanz.' *Deutsche med. Wochenschrift*, 1886, No. 4. *Ibid.* 1885.

dose of morphine has either been eliminated or undergone conversion into the products already mentioned; and thus the secondary action will be quite different from the primary, and instead of narcosis and quietness of the stomach, there will be excitement, and nausea or vomiting, which may require to be again counteracted by a larger dose of the original drug.

It is evident that the relation between the primary and secondary effects of a drug will, if this explanation be correct, vary very much according to the relative solubility of the drug originally administered, and of the products of its decomposition. If the products of decomposition be more soluble, and more readily eliminated, than the drug itself, they will leave the organism before it, and their action will hardly appear; but if they are less soluble, and more slowly eliminated, their action may persist for a considerable length of time.

Relation of Effect to Quantity of the Drug.—The effect of drugs varies very much according to the quantity employed. Sometimes this is due to the interaction of different parts of the body on one another, as already mentioned in regard to veratrine (p. 26). Sometimes it is due to the different effects upon individual cells or tissues. Thus we find, very generally, that any substance or form of energy, whether it be acid or alkali, heat or electricity, which in moderate quantity increases the activity of cells, destroys it when excessive.

But varying doses do not always produce opposite effects. We sometimes find that exceedingly small and exceedingly large doses have a similar effect, which differs from that produced by moderate doses. Thus very minute quantities of atropine render the pulse somewhat slow; larger quantities make it exceedingly rapid, and very large quantities again render it slow.

Moderate quantities of digitalis slow the pulse, larger quantities quicken it, and still larger quantities render it slow again. We find a similar effect produced by variation in temperature. Great cold disturbs the mental faculties, so that men exposed to it present symptoms which cannot be distinguished from those of intoxication. Ordinary temperatures do not disturb the functions of the brain, but high temperatures do, as we see in the delirium of fever, which in many cases immediately ceases when the temperature of the patient is reduced by cold baths.

Homœopathy.—This opposite action of large and small doses seems to be the basis of truth on which the doctrine of homœopathy has been founded. The irrational practice of giving infinitesimal doses has of course nothing to do with the principle of homœopathy—*similia similibus curantur:* the only requisite is that mentioned by Hippocrates, when he recommended mandrake in mania; viz. that the dose be smaller than would be

sufficient to produce in a healthy man symptoms similar to those of the disease. Now in the case of some drugs this may be exactly equivalent to giving a drug which produces symptoms opposite to those of the disease; and then we can readily see the possibility of the morbid changes being counteracted by the action of the drug, and benefit resulting from the treatment. For example, large doses of digitalis render the pulse extremely rapid, but moderate ones slow it.[1] The moderate administration, when there is a rapid pulse, is sometimes beneficial: this might be called *homœopathic* treatment, inasmuch as the dose administered is smaller than that which would make the pulse rapid in a healthy man; but it might also be called *antipathic*, inasmuch as the same dose administered to a healthy person would also slow the pulse.

Homœopathy can therefore not be looked upon as a universal rule of practice, and the adoption of any such empirical rule must certainly do harm by leading those who believe in it to rest content in ignorance instead of seeking after a system of rational therapeutics.

Dose.—The amount of a drug, which actually comes in contact with and affects the tissues, depends upon several conditions —(1) the **quantity** actually given; (2) its **proportion** to the body-weight; (3) the rapidity of its **absorption** by the blood from the place of introduction; (4) the condition of the **circulation** in various parts of the body, which determines the quantity of the drug carried to each; (5) the rate of its absorption by the **tissues**; (6) the rapidity of **excretion.**

The word **dose**, as employed in medicine, usually means the quantity given at one time, but sometimes this may be very different from what actually produces any effect. It is the amount of the drug existing in the blood at any given time, or rather the proportion of it that actually comes in contact with or is absorbed by the tissues, which really acts. We must therefore consider more in detail the circumstances which affect this proportion.

Size.—As the action which a drug has on the body is not dependent on its absolute amount, but on the proportion it bears to the body on which it is to act, an amount which is a small dose for one person is a very large one for another.[2] Thus if a grain of some active substance be injected at the same time into the veins of a full-grown man and into those of a boy of only half his weight, it will be distributed through twice as much blood in the man as in the boy, and each tissue will only receive half as much of it. The dose of a drug must therefore be regulated by the weight of the patient; and thus women, being

[1] *Vide* Traube, *Med. Centr. Ztg.* xxx. p. 94, 1861, and Brunton *On Digitalis*, p. 21.
[2] Buchheim, *Arzneimittellehre*, 3rd edit. p. 54.

lighter, require a smaller amount than men, and children less than adults. Though it would be more exact, it is not always convenient, to weigh patients; but in experiments on animals we usually weigh the animal carefully, and describe the dose in terms of the body-weight. For example, in describing the lethal dose of physostigmine we do not say that it is so many grains for an animal, but that it is 0·04 grain per pound weight of a rabbit. This relation, however, is not always an exact one, and other circumstances must be taken into account. Thus the **species** of the animal must be considered, for the same dose which would kill one kind of animal will not kill another. In animals of the same species the state of **nutrition** must be taken into account, for two animals of the same species, which would be nearly of the same size when equally nourished, may have very different weights if the one is fat and the other is lean. But the fat is a comparatively inert tissue, and if we give to each animal a dose regulated by its body-weight, the vital organs, brain, heart, and spinal cord of the fat animal will get a larger share in proportion than those of the lean one.

In testing the action of poisons on frogs, also, it must be remembered that a female frog with a quantity of spawn will be very heavy, but the spawn, like the fat, is not to be reckoned as tissue; so that a dose given in proportion to the actual weight would be much larger than the same proportion given to the frog after spawning.

Mode of Administration.—If a substance be **injected** into the **veins**, the whole of it mixes with the blood and becomes active immediately, and the maximum effect is thus at once obtained and will again diminish as the substance is excreted. But the case is different if it be injected **subcutaneously**, and if it be given by the **stomach** or any other **mucous cavity** the difference is still greater; for as soon as some of it is absorbed excretion begins, and thus one portion of the drug is passing out of the blood while another portion is being taken in. The amount in the blood is, then, only the difference between that absorbed and that excreted in a given time (Fig. 6). Absorption may be so slow, or excretion so quick, that there is never a sufficient amount of the substance in the blood to produce any effect. Thus Bernard found that a dose of curare which would certainly paralyse an animal when injected into the veins, or even subcutaneously, would have no effect when introduced into the stomach;[1] and showed that this was due to the kidneys excreting the poison as fast as it was absorbed from the stomach, by extirpating the kidneys,[2] when the animal became paralysed as surely as if the poison had been introduced at once into the

[1] Bernard, *Leçons sur les Effets des Substances Toxiques*, p. 282.
[2] Bernard, *Revue des Cours Scientifiques*, 1865.

veins, though not so quickly. Hermann also discovered, without being acquainted with Bernard's observations, that curare taken into the stomach would produce paralysis if excretion were prevented by ligature of the renal vessels.




FIG. 5.—Diagram to illustrate absorption and excretion. The arrows show the direction of the currents. The absorbents from which the blood passes directly into the general circulation are represented diagrammatically by the veins of the lungs and of the general body surface in the figure. The absorbents by which the drug must pass through the liver, and possibly be partly excreted or destroyed, are represented by the veins of the stomach and intestine. The excreting channels by which the drug may pass directly from the body without re-absorption occurring are represented by the vessels of the lung and by the ureter. Those by which excretion takes place into cavities from which much re-absorption may occur are represented by the arteries to the intestine and the stomach.

The **absorption** of drugs from the stomach and intestines may be considerably retarded, and their action diminished, by the liver. Before reaching the general circulation, drugs absorbed from the intestinal canal must all pass through the liver (Fig. 5). In their passage they may be partly arrested and excreted again into the intestine along with the bile. They may be also partially destroyed. A larger quantity of a drug may thus be necessary to produce similar effects when introduced by the stomach than when injected directly into the circulation or under the skin—(1) because it may be absorbed more slowly by the vessels of the gastric or intestinal mucous membrane; (2) because a part of it may be arrested in the liver and excreted into the intestine along with the bile; (3) because a part of it may be actually destroyed in the liver.

The more rapid the absorption, or the slower the excretion, of any drug, the greater will be its effect. Thus the effect produced by the same dose of a medicine will be in proportion to the rapidity of its absorption from the different parts to which it has been applied, unless the differences be so slight that there has not been time for the excretion of any considerable quantity from the blood during the process. On this account we must diminish the dose of a medicine in order to obtain the same effect, according to the rapidity of absorption from the place to which we apply it. Absorption is quickest from serous membranes, next from intercellular tissue, and slowest from mucous

membranes. The vascularity and rate of absorption from intercellular tissue is greater on the temples, breast, and inner side




FIG. 6.—Diagram to illustrate the differences produced in the amount of a drug present in the organism by alterations in the rate of absorption and excretion. The lower funnel represents the organism. A represents the condition when a drug is rapidly introduced, as by injection into a vein. In this case the drug, *e.g.* curare, comes to be present in large quantities in the organism, and produces its full physiological effect. This is represented by the fulness of the lower funnel. And it does this notwithstanding the rapidity of excretion, which causes the drug to be quickly eliminated and to appear copiously in the urine, as represented by the fulness of the beaker into which the fluid flows from the lower funnel. B represents the condition when a drug is slowly absorbed and rapidly excreted, as when curare is given by the stomach. In this case the quantity present in the blood at any one time is very minute, as represented by the empty condition of the lower funnel. C represents the condition when absorption is rather quicker than excretion, as when a dose of morphine is given by the stomach. D represents the condition where absorption is moderate but excretion is interfered with, leading to accumulation in the blood, as where an active drug is given by the mouth and the kidneys are much degenerated.

of the arms and legs than on their outer surfaces, or on the back.[1] It should not be forgotten that any drug introduced into the stomach, but not absorbed into the blood, is as much outside the body as if it were in the hand, for any effect it will have on




FIG. 7.—Diagrammatic representation of the body. A is a box to represent the tissues. B is an inner tube to represent the intestinal canal. It is obvious that anything which is merely in the inner tube is outside the box, and, similarly, anything which is merely in the intestinal canal is outside the body.

the system, provided always it have no local action on the gastric walls. But if it act directly on the walls of the stomach, it may have an effect which it would not have when held in the hand

[1] Eulenburg, *Hypodermatische Injection der Arzneimittel*, 3rd edit. p. 65.

or applied to the skin. Thus mustard, which would produce redness and burning of the skin, will cause vomiting when swallowed; but opium, which does not act on the stomach itself, except by diminishing its sensibility, produces no apparent effect until after it has been absorbed.

By the difference between absorption and excretion under different circumstances or in different individuals,[1] the cumulative action of drugs, the effect of idiosyncrasy, habit, climate, condition of body, as fasting, &c., disease, and form of administration, can, to a certain extent, though not entirely, be explained; but experiments on some of these points are deficient, and the explanations now given are to some extent theoretical.

Duration of Action of Drugs.—When a soluble drug is introduced into the stomach, it will undergo absorption, and the whole of it may possibly be absorbed without any portion of it even passing into the intestine. After absorption into the blood it will either remain in the plasma or form a compound with the corpuscles. It will thus be carried to the liver, where part of it may be retained (*vide* p. 39). Such portions as pass through the liver will then be carried to the right side of the heart, to the pulmonary circulation, and then, passing to the left side of the heart, will be distributed to all parts of the body. As absorption continues, the quantity of the drug in the stomach will gradually diminish, while that in the circulation will increase to a certain extent; this extent, however, will depend upon the activity of the eliminating organs. The drug will be carried to all parts of the body, both to the eliminating organs and to those connected with the other functions of the organism. It will enter into combination, more or less firm, with all those organs which have any attraction for it, and will more or less modify their functional activity. In the processes of tissue-change, which are constantly going on, the combination between the drug and the organs will be gradually destroyed; and, being again returned to the circulation, it will undergo gradual elimination. The method in which elimination occurs will also depend, to a certain extent, on the selective action of the eliminating organs; thus soluble substances are usually eliminated most readily by the kidneys, while salts of the heavy metals, which form insoluble compounds with albumen, are eliminated to a great extent by mucous membranes.

Cumulative Action.—If a substance be naturally so slowly excreted from the body that the whole of the dose in ordinary use is not excreted before another is given, the amount present in the body will gradually increase, just like the curare in Hermann's experiment, and will produce an increasing or cumulative effect. Examples of this are to be found in metallic preparations,

[1] Children absorb more quickly than adults, so opium is more dangerous to them. Marx, *Lehre von den Giften*, vol. ii. p. 117.

such as those of mercury or lead, which are excreted very slowly; or in some of the organic alkaloids, if given in sufficiently large and frequent doses. The sparingly soluble alkaloids which form stable compounds with the tissues and are thus slowly eliminated are more liable to prove cumulative. The size of the dose and the frequency with which it must be repeated in order to produce a cumulative effect will differ according to the rapidity with which the drug is excreted; for, if excretion be rapid, a larger dose or more frequent repetition will be required.

Sometimes the symptoms of the physiological action of a drug instead of increasing gradually may do so suddenly, and it is to this kind of action that the term cumulative action is most usually applied. This may sometimes be due to a sparingly soluble drug accumulating in the intestinal canal, and being suddenly dissolved and absorbed on account of some change occurring in the intestinal contents; at other times it may be due to arrest of excretion, as in the case of the two vegetable active principles, digitalin and strychnine, to which an especial cumulative action is ascribed. After moderate doses of these drugs have been taken for some time, it is found that instead of the effects they produce increasing gradually, as we would expect from a gradual accumulation in the blood, the symptoms of poisoning become suddenly developed, in somewhat the same way as if the dose had been suddenly increased. It is evident that a diminution in the quantity excreted will produce this effect as readily as an increase in the quantity taken, and this is probably the true cause of the phenomenon. When digitalin has been taken for some time and accumulated to a certain extent in the blood, it causes a diminution in the amount of urine excreted, and this diminution is either accompanied or quickly followed by the other symptoms of poisoning.[1] The effect, indeed, seems exactly the same as Hermann would have obtained in his experiment if he had only partially compressed the renal arteries instead of ligaturing them completely. For digitalin appears to diminish the secretion of urine by causing a powerful contraction of the renal vessels,[2] and in large doses may completely arrest the secretion of urine,[3] and probably also the circulation through the kidneys. Strychnine has a similar action on the vessels.[4]

Effect of different Preparations.—When a drug is given in a soluble form, and in small bulk, it is more quickly absorbed and will have greater effect than when given in a less soluble

---

[1] Brunton, *On Digitalis*, p. 39.

[2] Brunton and Power, *Proceedings of Royal Soc.*, 1874, No. 153, and *Centralblatt f. d. Med. Wiss.*, 1874, p. 497.

[3] Christison, *Edin. Med. Journ.*, vii. 149.

[4] Grützner, *Pflüger's Archiv*, 1876, Bd. xi. p. 601. Gärtner, *Separat-Abdruck a. d.* lxxx. *Bd. d. k. Akad. d. Wiss.* III. Abt., Dec. Heft, Jahrg. 1879.

form or much diluted. Thus drugs given in solution as tinctures will act, as a rule, more quickly than when given in the form of pill or powder.

Effect of Fasting.—When a drug is given upon an empty stomach, it is usually absorbed much more rapidly. Thus the same quantity of alcohol which would have no effect on a man if taken during or after dinner, might intoxicate him if taken on an empty stomach, and especially if he were thirsty, so that absorption occurred rapidly. Curare, although it is usually inert when placed in the stomach, is sometimes absorbed so rapidly from an empty stomach as to produce a certain amount of paralysis.

Besides the alterations in absorption we have to consider also the local action on the stomach itself, and the reflex effects which may be produced through the gastric nerves on other organs. Thus where we give a drug for its local action on the stomach itself, it is administered with the greatest effect during fasting, as it will come in contact with all parts of the gastric mucous membrane. An example of this is the use of a small dose of arsenic for gastric neuralgia or lientery.

But when we wish to prevent local action on the stomach—as, for example, when we give arsenic for its general effect on the system, in cases of skin-disease—we administer it after meals, so that it may be diluted by the food, and not irritate the stomach too much.

Effect of Conditions of the Stomach.—In some conditions of the nervous system, absorption takes place much more slowly than others; indeed, both digestion and absorption appear to be sometimes totally arrested. Thus in persons in whom a sick headache comes on some time after a meal the contents of the stomach are vomited after a while and the food is found to have undergone digestion but not absorption. If the meal be taken after the headache has come on it will be found, in some persons at least, that the food is vomited almost unchanged, both digestion and absorption appearing to be arrested. This condition exists also in delirium tremens, and in a case of this disease I have seen pieces of food thrown up in an undigested condition although they have been swallowed, as the patient has informed me, three or four days before. It is probable that in these conditions drugs are also not absorbed, and I think it is not improbable that the harmlessness of large doses of digitalis given in cases of delirium tremens is due to the non-absorption of the drug.

Effect of Habit.—The tissues seem to have a certain power of adapting themselves to changes in their surroundings. Thus salt-water amœbæ will die when placed at once in fresh water, but if the fresh water be added very gradually, they may by-and-by become accustomed to live in it. Fresh-water amœbæ also

have the power of becoming gradually accustomed to increasing quantities of salt gradually added to the water in which they live, and which would at once kill them if added suddenly. A similar power seems to be possessed by the tissues of the higher animals, in regard to some drugs at least. Thus the arsenic-eaters of Styria are able to consume—not only without injury, but with apparent benefit to themselves—a quantity of arsenic which would prove fatal to one unaccustomed to it. The same is the case with opium and morphine. With these latter drugs there seems to be hardly any limit to the quantity which can be taken after the habit has been once established, and after a certain dose has been exceeded.

It is possible, however, that in addition to a process of accommodation going on in the tissues, there is a slower absorption, and perhaps more rapid excretion, going on at the same time; for it is observed in the case of opium that sometimes the effect is not only diminished, but the time which elapses before it occurs is lengthened when persons have become accustomed to the drug.

In regard to the possibility of very slow absorption we must remember the power of the liver to arrest and excrete or to destroy poisons, especially as it is chiefly in the case of vegetable poisons that their power is lessened by habit, which has much less influence on the effect of inorganic substances. The **tolerance** of some inorganic drugs, and especially of tartar emetic in disease or after repeated doses, may be due to fever or the drug itself lessening the acidity of the stomach, and consequently the action of the drug, which acts most strongly in presence of an acid.

The Effect of Temperature.—Chemical reactions, as a rule, go on more rapidly the higher the temperature, excepting when very high temperatures are reached and dissociation occurs. The effect of drugs upon living organisms may be regarded as being to a great extent due to chemical union between the drugs and the organism, and therefore we should expect that alterations in temperature would greatly affect the action of drugs and that, as a rule, we should find that they would act with greater quickness when the temperature is high unless some other factor should be brought into operation by the increasing temperature. Experience confirms this expectation, and, as a matter of fact, the effect of temperature on the action of drugs is very great. At different temperatures the administration of the same drug may be followed by different results, and it is probable that a great number of the **contradictory observations** which we find in works on Pharmacology are due to this most important factor having been neglected in making the experiments. It is of the greatest importance to the physician also, as many of the cases of disease which he has to treat are accompanied by a rise in

temperature which may have a very important effect upon the action of the drugs which he administers.

The alteration produced in the effect of drugs by warmth, was first noticed by Alexander von Humboldt, who observed that warmth not only acted as a stimulant to the heart in increasing the power and rapidity of its contractions, but noticed that warmth increased the rapidity with which alcohol destroyed the irritability of a nerve, and potassium sulphide that of a muscle. Bernard observes generally that poisons act slightly on frogs when cooled down, and become more active the higher the temperature. The effect of warmth in stimulating the movements of **protoplasmic structures**, such as amœbæ and cilia, was investigated by Kühne; and, in an important research, Luchsinger experimented on the influence of warmth on the action of poisons on many organs, and found that the ciliary motion in the pharynx of the frog became paralysed by chloral, potassium carbonate, and tartrate of copper and sodium more and more quickly in proportion to the rise in temperature. On cooling down the ciliary movement again returned.

Dr. Cash and I have found that the action of veratrine or barium on **muscle** is very much altered by heat and cold. At ordinary temperatures contraction is greatly prolonged, but under the influence of either great heat or great cold the contraction again becomes nearly or quite normal.

Many, if not all, muscular poisons act more quickly with increased temperature; and frogs poisoned with chloral, copper, manganese, potash, and zinc are paralysed more quickly when the temperature is high, than when it is low, whether the alterations be produced artificially, or be due to differences in the season at which the experiments are made.

Rabbits poisoned with copper or potash also die more quickly when placed in a warm chamber than when left at the ordinary temperature.

The terminations of **motor nerves** in the muscles are also greatly affected by temperature.

Guanidine produces in the frog fibrillary twitchings of the muscles, which persist even in excised muscles, but are removed by curare, and are therefore in all probability dependent on an affection of the terminal ends of the motor nerves in the muscle. Luchsinger found that when four frogs are poisoned in this way, and one is placed in ice-water, another in water at 18°, a third at 25°, and a fourth at 32°, the fibrillary twitchings soon disappear from the muscles of the frog at 0°, and only return when its temperature is raised to about 18°. In the one at 18° convulsions occur, which are still greater in the one at 25°. In the frog at 32°, on the other hand, no abnormal appearance is to be remarked, and five times the dose may be given without doing it any harm.

This poison then resembles veratrine in acting only at ordinary temperatures, and in its action being abolished by excess of heat or cold.

The effect of temperature on **secreting nerves** is well marked. When the sciatic is stimulated in an animal, the corresponding foot usually begins to sweat, but the sweating is very much less if the foot is cooled down than if it is warm. A similar action is exerted by temperature upon the sweating produced by pilocarpine—a drug which appears to act by stimulating the ends of the secreting nerves. When the animal is cooled, this drug is much less powerful than when it is warm.

Overheating appears to have an opposite action, and when the foot is heated up to a certain temperature it does not secrete nearly so readily, even though the glands themselves are not injured, and secretion may commence after the lapse of a little time.

The influence of poisons on the **heart** of the frog is also modified by temperature. Kronecker found that its beats were arrested by ether easily and quickly when the temperature was high, but with great difficulty when it was low. Ringer found that a small dose of veratrine greatly affects the ventricle at a moderate or high temperature, but at a low temperature produces no effect.[1]

Luchsinger noticed that when the frog's heart had been arrested by passing dilute solutions of chloral, copper, or potassium carbonate through at 25° C., the pulsations again began when the temperature was reduced to 15° C. When, on the contrary, the heart had been arrested in a similar manner, at a temperature of 5° C., pulsations could then be induced by warming it to 15°.

Some extraordinary observations on the effect of temperature upon the action of drugs on the **spinal cord** have been made by Kunde and Foster, who have found that, in a number of frogs poisoned with strychnine and exposed to different temperatures, raising the temperature diminishes the convulsions, while cold increases them if small doses are employed. Raising the temperature, indeed, may not only diminish but entirely abolish the convulsions, while putting a frog in ice may bring them on when they would not otherwise appear, and cause them to last for no less than twenty-four hours. When large doses are employed the opposite effect is produced; raising the temperature then increases the convulsions, while cooling the frog down to 0° abolishes them.

An observation similar in some respects, though differing in others, has been made on the effect of temperature on the action of picrotoxin by Luchsinger.[2] When this poison is given to three

---

[1] Ringer, *Archives of Medicine*, vol. vii. Feb. 1882, p. 5.

[2] Luchsinger, *Physiologische Studien*, Leipzig, 1882.

frogs, and they are then placed in water at 0°, 15°, and 32°, in a few minutes the convulsions occur in the one at 32°, shortly afterwards in that at 15°, while the one at 0° remains for a long time completely unaffected, and only exhibits signs of convulsion when the dose has been very great indeed, or when it is taken out of the cold bath.

The effect of warmth in **accelerating death** from muscular poisons has already been mentioned.

The power of warmth to **preserve life** in narcotic poisoning was observed by Hermann in relation to alcohol, which rabbits bear better when they are somewhat warmed.[1] Its extraordinary effect in preventing death in animals poisoned with chloral was noticed by Stricker, and more thoroughly worked out by myself at his suggestion.[2] Death by chloral appeared from my experiments to be in a great measure due to continued loss of heat from the animal. This seems to be the case also in metallic poisoning by copper, manganese, mercury, platinum, potassium, thallium, tungsten, and zinc. Its cause appears to be twofold: (1) the poisons lessen combustion in the body, and the amount of heat produced, as is shown by their diminishing the amount of carbonic acid excreted; (2) besides disturbing the production they also disturb the regulation of heat, so that animals poisoned by them have less power of resisting the influence of external temperature, and therefore the temperature rises more quickly when they are put in a warm chamber, as well as sinks more quickly when they are exposed to cold.

All these observations show that the **definition** of the **action of a drug**, already given (p. 5), must be still further modified, and we must define it as the reaction between the drug and the various parts of the body **at a certain temperature.**

Thomas[3] found that digitalis has sometimes no action on the pulse in pneumonia. As the slowing of the pulse produced by this drug is to some extent effected through the vagi, it occurred to me that its want of action in this disease might be due to the paralysis of these nerves by heat. On testing the action of heat, however, on the vagus, in rabbits deeply chloralised, I found that it was not paralysed at a temperature just sufficient to kill the animal.[4] Cash and I, however, have found that though the peripheral ends of the vagi are not completely paralysed by high temperature, the roots of the vagus in the medulla appear to be so, and probably the want of action of digitalis, when the temperature is high, is due to this paralysis (*vide* Digitalis).

The abnormal effect which opium has in some cases of fever —causing excitement instead of sleep—is occasionally most

---

[1] Hermann, *Arch. f. Anat. u. Physiol.* 1867, p. 64.
[2] Lauder Brunton, *Journal of Anatomy and Physiology*, vol. viii.
[3] *Arch. f. Heilk.*, vol. iv. 329, 1865.
[4] *St. Bartholomew's Hospital Reports*, 1871, p. 216.

distressing to the physician. It is possible that this may be partly due to the temperature, and that the combination of tartar emetic with the opium may owe some of its utility to its effect in lowering temperature, although not improbably both it and another useful combination with chloral also act more perfectly on account of the depressing action on the circulation. These are points, however, on which further observations are greatly needed.

Climate.—It is said that the action of narcotic drugs is greater in warm climates than in cold, and that smaller doses are therefore required to produce a similar effect. If this statement be true, it may be due to the higher temperature, for Crombie has shown that in India the average temperature of the body is about half a degree higher than in England. It may, however, be due to the slower elimination of the drug by the urine; because in hot climates the secretion of the skin is apt to be much greater, and the secretion of urine and elimination by it consequently less.

Time of Day.—In healthy persons fluctuations of the body-temperature occur. The lowest temperatures occur at night between 10 P.M. and 1 A.M., and in the early morning between 6 and 8 A.M. The highest temperature occurs between 4 and 5 in the afternoon.

The action of drugs may be partially altered by the slight variations in temperature which occur within the body, and perhaps still more by the variations in tissue-change, of which these fluctuations of temperature are the indication. Thus the necessity for great attention to the administration of stimulants in the early hours of the morning in cases of threatening collapse has long been recognised.

Effect of Season.—The action of drugs is altered by the changes in temperature due to the seasons. Galen supposed that the quantity of blood in the body was increased in spring, and in this country, till within recent years, it was a common custom for people to be regularly bled every spring. Purgatives were not unfrequently administered also at the same time. There are, no doubt, changes corresponding with the seasons in the human organisation, although these are better marked in the lower animals; *e.g.* deer, in which the antlers bud regularly in spring and reach perfection just at the breeding season. It is possible that the abolition of the practice of bleeding in spring and the changes in other plans of treatment formerly adopted, may not be altogether due, as some suppose, to increased knowledge on our part, but rather to the occurrence of **a change of type** not only in diseases but also in slight ailments, and to the need for such treatment having disappeared. Formerly, before the introduction of coaches, and still more of railways, locomotion was difficult and transportation was expensive; in consequence

of this, the food consumed by the generality of people was different in character, loaf bread being very little used, and salt meat often used for weeks and months together during the winter, with comparatively few vegetables. Such a diet might naturally lead to a condition of body which would be benefited by bleeding and purgatives.

Effect of Disease.—The direct and indirect, the local and remote action of drugs upon the complicated mechanism of a mammalian body is so perplexing that the attempt to ascertain the precise mode of action of a drug by its mere administration, either to a healthy man or to healthy animals, and observation of its effect upon them, is hopeless.

Moreover, the object that we really wish to attain is the power to relieve human suffering, and to avert the premature death due to disease. But in disease we have new factors; changes are produced by it in the functions of the body, and the reaction of the diseased organism to the drugs which we administer is oftentimes different from that of a healthy one. To a man suffering from cholera, for example, enormous doses of drugs have been given without the least effect; and, in the wakefulness of fever, the opium which ought to produce sleep may simply cause excitement and delirium.

Use of Experiments.

As we have seen, the problems put before us are too complicated to be solved directly, and we must therefore simplify them.

This is done in four ways:—

1st, by observation of the effects of drugs on animals with a **simpler organism** than our own, such as amœbæ or frogs;

2ndly, by **applying** the drug to some **part** of an animal body more or less completely **separated** from the rest, such as, for example, the muscle and nerve, or the heart of a frog separated from the body; and

3rdly, by **preventing** the drug from **reaching one part** of the body while it acts on the others, as by ligaturing an artery, as in Bernard's or Kölliker's experiments on curare.

4thly, by producing artificial **changes** in the **relations** of the various parts of the body of higher animals, either before or after administration of a drug, as, for example, by dividing the vagi, in order to ascertain how far the change produced in the beats of the heart by a drug is due to its action upon it through these nerves.

Comparative Pharmacology.—It may seem almost absurd to those unacquainted with the subject, that so much attention should be devoted to experiments on the effect of drugs on the lower animals, when our object is, as we have just stated, to ascertain their action upon human beings, and their mode of employment in the diseases of man.

But in the study of Pharmacology, just as in Histology, very much is to be learned by comparative studies. In his lectures, Ranvier admirably defines General Anatomy as Comparative Histology limited to a single organism. He illustrates this by showing that the different modes of movement which occur in some of the lower classes of the animal kingdom are to be found united in the highest. Thus leucocytes of the blood move about like amœbæ. The epithelium of the respiratory passages is provided, like infusoria, with cilia; and while some muscles have the power of rapid contraction, others contract slowly, like those of some invertebrata.[1]

We have thus in certain parts of the bodies of the higher animals and of man, anatomical elements whose functions are performed in a way resembling that of organisms low in the scale of existence, and by examining the effects of drugs upon these low organisms we acquire knowledge which aids us in determining the action of drugs upon similar anatomical elements in the human body.

In his admirable lecture on Elemental Pathology, Sir James Paget draws attention to the distinction between the conditions of life and the essential properties of living things; and to the fact that, while the various parts of a complicated organism like the human body are closely connected together, and made to work in harmony for the common good of the organism in health, yet each part retains its own mode of life, and may sometimes develop to an excessive extent at the expense of the rest, and may destroy the organism, and itself as well. We see the power which each part possesses of carrying on individual life apart from the rest best in lower organisms or in inorganic substances, where the parts are less dependent on the welfare of the whole.

Thus, in crystals, a chip which has been broken off is replaced, and the form of the crystal restored, by putting it in a solution which will yield it the proper kind of material required. When a hydra is cut in two, each part grows into a perfect individual: a tail growing to the head part, and a head growing to the tail part. When a claw has been broken off a crab or lobster, a new one will by-and-by grow; but if the animal be divided in two, unlike the hydra it will die.

---

[1] *Leçons d'anatomie générale sur le système musculaire*, par L. Ranvier. Paris, 1880, p. 46.

As we ascend in the scale of existence the power of repair becomes less perfect. But even in the human being we see that the different parts retain their individual life, and if put into proper conditions may live, although the original body from which they were obtained were to die. Teeth, for example, which have been extracted from one person have been transplanted and grown in the jaws of another; and the transplantation of hair, skin, or of periosteum is perfectly practicable.

Idiosyncrasy.—In their onward development from the lowest forms of life, man and the higher animals have not only permanently retained in their bodies certain parts which resemble organisms low in the scale of existence, but every now and again a tendency to reversion appears in certain individuals, and we thus get anatomical abnormalities and malformations.

These were formerly inexplicable, but the doctrine of evolution has thrown much light on their probable causation.

Now and again we also meet with peculiarities in the reaction between drugs and parts of the human body in certain individuals.

Some persons, for example, are like pigeons—only slightly affected by opium—and can take enormous doses of it without any apparent effect. Others, again, are peculiarly sensitive to the action of certain medicines, and a dose of a mercurial preparation, which would have but a slight purgative action on one, will produce intense salivation in another.

These personal peculiarities in regard to the action of drugs, or idiosyncrasies, as they are termed, have been, and are still, very perplexing to the medical practitioner. It is probable, however, that a more complete study of comparative pharmacology will enable us, to some extent at least, to recognise these, and thus to avoid the inconvenience which they occasion.

Experiments upon Healthy Man.—As the action of drugs upon animals is to a certain extent different from that on man, it is undoubtedly desirable to ascertain the action of drugs by experiments upon healthy man. This is all the more necessary because by experiments upon animals we are able to discover only the ruder differences between drugs, and we cannot ascertain the finer shades of action, both because it is in man alone that these finer differences occur, and because it is he alone who can give information regarding slight changes which he can perceive in his own organism, but which are imperceptible to others who may be observing him. There is no doubt that many observers of this sort, several of whom have been homœopathists, have done good service to medicine by carefully noting and carefully comparing the symptoms produced by various drugs. These observations, however, are liable to fallacies, as I will presently mention.

Fallacies of Experiment upon Man.—But the high development of the nervous system in man, its susceptibility to various influences, and the power of expression which man possesses—the very qualities which render him such a valuable subject for experiment make experiments upon him all the more liable to fallacy. Thus we find that in the experiments of Heinrich and Dworzak aconite was found to cause neuralgic pains in the face; but unfortunately these observers have not mentioned whether any carious teeth were present, and so we cannot ascertain whether the neuralgia was due to the action of the aconite itself upon healthy nerves, or to alterations in the circulation of the alveoli lodging decayed teeth.

One of the most marked examples of the fallacies occurring in experiments upon man, and of the errors to which such fallacies may lead, is to be found in the provings which Hahnemann made of cinchona bark, and which led him to formulate the doctrine of homœopathy. Hahnemann, for the sake of experiment, took for several days 4 drachms of good cinchona bark twice a day, and then began to suffer from all the ordinary symptoms of intermittent fever. On leaving off the drug he soon became quite well. He therefore concluded that cinchona bark, which was well known to be a remedy for ague, could also produce it.

Everyone who has an extended experience of ague knows well that even when patients have been free from any symptoms of the disease for a considerable length of time, they may be caused to reappear by various conditions, and more especially by anything that irritates the stomach or intestines. I have not myself seen a case of ague brought on by the administration of cinchona bark, but I have seen it occur after a succession of heavy dinners in a patient who had been long free from it. Powdered cinchona is certainly irritant, and Jörg found that in two-drachm doses it might cause flatulence, irritation, and nausea. Hahnemann took it in double this dose, and in all probability the ague which it brought on was simply due to gastric irritation, and not to any specific action of the cinchona. Had Hahnemann taken any other irritant which disagreed with him—say tartar emetic, or perhaps even pork-pie—he might have suffered in the same way, and yet pork-pie could hardly be said to be a specific for ague.

Experiments in Disease.—In the present state of medicine every attempt which we make to treat disease by the administration of medicine partakes more or less of the nature of experiment, because we can rarely be absolutely certain that the drug will have precisely the effect which we desire. As the phrase is, 'We try one medicine, and then we try another.' If human life were not so valuable, we might pursue a series of systematic experiments, and gain valuable information; but it is impossible

for a physician to treat the patient who calls upon him for aid in any other way than that which seems likely to be the best for the patient's welfare. Here again the homœopathists have done good service, because by administering to the patient medicines in which they believed, but which could neither do good nor harm, they have taught us the natural course of some diseases, which we could not otherwise have learned.

Objections to Experiment.—Some people object entirely to experiments upon animals. They do this chiefly on two grounds. The first is that such experiments are useless, and the second is that, even if they were useful, we have no right to inflict pain upon animals.

The first objection is due to ignorance. Almost all our exact knowledge of the action of drugs on the various organs of the body, as well as the physiological functions of these organisms themselves, has been obtained by experiments on animals.

The second objection is one which, if pushed to its utmost limits and steadily carried out, would soon drive man off the face of the earth.

The struggle for existence is constantly going on, not only between man and man, but between man, the lower animals and plants, and man's very being depends upon his success.

We kill animals for food. We destroy them when they are dangerous like the tiger or cobra, or destructive like the rat or mouse. We oblige them to work for us, for no reward but their food; and we urge them on by whip and spur when they are unwilling or flag. No one would think of blaming the messenger who should apply whip and spur to bring a reprieve, and thus save the life of a human being about to die on the scaffold, even although his horse should die under him at the end of the journey. Humane people will give an extra shilling to a cab-man in order that they may catch the train which will take them to soothe the dying moments of a friend, without regarding the consequences to the cab-horse. Yet if one-tenth of the suffering which the horse has to endure in either of the cases just mentioned were to be inflicted by a physiologist in order to obtain the knowledge which would help to relieve the suffering and lengthen the life, not of one human being only, but of thousands, many persons would exclaim against him. Such objections as these are due either to want of knowledge or want of thought on the part of the people who make them. They either do not know the benefits which medicine derives from experiment, or they thoughtlessly (sometimes, perhaps, wilfully) ignore the evidence regarding the utility of experiment.

One of the most important objections that has been raised to this mode of experiment is that the action of drugs on the lower animals is quite different from their action on man. This objection has a certain amount of truth, but is in the main

groundless. The action of drugs on man differs from that on the lower animals chiefly in respect to the brain, which is so much more greatly developed in man.

Where the structure of an organ or tissue is nearly the same in man and in the lower animals, the action of drugs upon it is similar. Thus we find that carbonic oxide and nitrites produce similar changes in the blood of frogs, dogs, and man, that curare paralyses the motor nerves alike in them all, and veratrine exerts upon the muscles of each its peculiar stimulant and paralysing action.

Where differences exist in the structure of the various organs, we find, as we would naturally expect, differences in their reaction to drugs. Thus the heart of the frog is simpler than that of dogs or men, and less affected by the central nervous system. We consequently find that while such a drug as digitalis has a somewhat similar action upon the hearts of frogs, dogs, and men, there are certain differences between its effect upon the heart of a frog and that of mammals. In all it seems to affect the muscular substance and cause increased contraction. But while the frog almost invariably dies with the heart in a state of tetanic contraction, this is not the case with dogs or men, where the heart sometimes is found in diastole after death.

Ipecacuanha or tartar emetic will cause vomiting in man, but does not do so in rabbits. The reason of this is that the position of the stomach in the rabbit is different from that in man, and is such that the animal cannot vomit. In dogs, however, the position of the stomach agrees with that of man, and tartar emetic or ipecacuanha causes vomiting in both. Belladonna offers another example of apparent difference in action—a considerable dose of belladonna will produce almost no apparent effect upon a rabbit, while a smaller dose in a dog or a man would cause the rapidity of the pulse to be nearly doubled. Yet in all three—rabbits, dogs, and men—belladonna paralyses the power of the vagus over the heart. The difference is, that in rabbits the vagus normally exerts but little action on the heart, and the effect of its paralysis is consequently slight or hardly appreciable, the pulse being normally almost as quick as it is after the vagus is paralysed. In dogs and men, on the contrary, the vagus is constantly exerting considerable restraining power over the heart, and the effects of its paralysis at once attract attention.

An example of the apparent difference in the effect of a drug on different animals is afforded by nitrite of amyl. If we measure the pressure of the blood in the arteries of a rabbit and of a dog, and then cause them to inhale nitrite of amyl, we find that the small vessels have become widened and allow the blood to pass easily out of the arterial system into the veins, so that the pressure sinks considerably in the rabbit, whereas it sinks only

slightly in the dog. The action seems at first sight different; but when we examine it more closely, we find that the heart of the dog is no longer beating slowly, but very quickly, so as to keep up the pressure, notwithstanding the rapid flow of the blood through the widened vessels, while the heart of the rabbit was going so fast before that it could not go much more quickly. If we cut the vagi in the dog, so that the heart goes as quickly as in the rabbit before it begins to inhale, the blood-pressure sinks during the inhalation, just as it does in the rabbit.[1]

One of the most marked differences between the action of a drug upon lower animals and upon man is to be found in the effect of morphine upon frogs and upon pigeons. In frogs it causes convulsions; on pigeons, even in large doses, it produces no apparent effect. But although its effects are not appreciable to the eye, they exist nevertheless, and on applying the thermometer it is found that morphine lowers the temperature of pigeons many degrees. On comparing the effect of the drug on frogs with its effect on man, we see that in the frog the cerebral hemispheres are very slightly developed indeed as compared with man, and in the latter the effects of the drug upon the spinal cord are usually completely concealed by the narcotic effect of the drug upon the brain. In children, however, and in some races of man where the cerebral hemispheres are less developed than in Europeans, the convulsant action of morphine manifests itself. Occasionally we find individuals who are almost proof against the action of morphine, and who take large doses of it without any apparent effect. Whether in these persons it lowers the temperature as it does in pigeons is a point which remains to be ascertained.

By means of experiments upon animals, then, we are able to ascertain the action of drugs upon those organs of the body which are alike in man and animals; and the very differences which exist between the various sorts of animals, help us to understand the action of drugs more thoroughly.

Erroneous Deductions from Experiments.—A great fault—and one which is only too common in the works of experimental pharmacologists—is that of drawing **general conclusions from limited data.**

One experimenter tries the effect of a drug, let us say tartar emetic, upon rabbits. He finds that they do not vomit, and instead of drawing the only warrantable conclusion, viz. that tartar emetic does not cause vomiting in rabbits, he draws the general one—that tartar emetic does not cause vomiting in animals. Another tries it upon dogs, and he finds they all vomit. Instead of the limited conclusion that tartar emetic makes dogs vomit,

---

[1] Lauder Brunton, 'Action of Nitrite of Amyl on the Circulation,' *Journal of Anatomy and Physiology*, vol. v. p. 95.

he draws the general conclusion that it makes animals in general vomit. The two observers are equally positive in regard to their facts—each is assured that he himself is right, and that the other is totally wrong. The reason of the discrepancy is simply that the conditions under which the experiments have been performed were different, but the observers have not taken these differences into account when drawing their conclusions. A third observer then comes, perhaps, and by further experiments reconciles the apparently contradictory statements. Thus one experimenter tries the effect of caffeine upon frogs; he finds that it produces rigor mortis in the muscles. Another tries the same drug, and finds no such result. These two observations are completely contradictory, until a third tries the effect of the drug upon two species of frog, and finds that while the muscles of the *rana esculenta* are but slightly affected, those of the *rana temporaria* are rendered rigid.[1]

These apparent contradictions in the results of different observers are exceedingly puzzling to the student, but nothing is more instructive to those who are actually working at the subject.

The **utility** of **apparent exceptions** was fully recognised by Claude Bernard, who says: 'In physiological studies we must always carefully note any fact which does not accord with received ideas. It is always from the examination and the discussion of this exceptional fact that a discovery will be made, if there is one to make.'[2]

---

[1] Schmiedeberg, *Arch. f. exper. Path. u. Pharmak.*, Bd. ii. p. 62.
[2] Bernard, *Liquides de l'organisme*, tom. i. p. 258.

CHAPTER III.

ACTION OF DRUGS ON PROTOPLASM, BLOOD, AND LOW ORGANISMS.

Action of Drugs on Albumin.

In all living bodies we find that the protoplasm is of a more or less albuminous nature.

Albuminous substances possess a very complex inter-molecular grouping, and very high atomic weights. Many different forms are found in animals, and along with albumins we must associate bodies like mucin, which probably have a very important relation to it, inasmuch as a body nearly, if not quite, identical with mucin forms the nucleus of the red blood-corpuscles in fowls,[1] and a substance of an allied nature also occurs in the circulating fluid which represents the blood in the echinodermata.[2] The albumin of serum may be taken as a representative of such substances; it is soluble in water, but, at a certain temperature, is **coagulated** and precipitated. It is coagulated also by alcohol, but if the coagulum is quickly placed in water it redissolves; if allowed to remain for some time exposed to the action of the alcohol it becomes permanent and insoluble. An insoluble precipitate also falls on the addition of tannic acid, both lead acetates, and mercuric chloride. The reagents just mentioned precipitate all the albumins, even from somewhat dilute solutions; in strong solutions precipitates are also formed by silver nitrate, copper sulphate, and zinc chloride.

When these are added to albumin containing only a small quantity of water, as, for example, the white of an egg, they form with it a solid mass of **albuminate**. A small quantity of strong potash added to the white of egg produces a solid transparent jelly of albuminate of potash, and a similar but opaque jelly is formed by the use of caustic lime or baryta in the place of potash: these albuminates are, however, soluble in water.

Albumin dissolves in alkalies, and may be partly precipitated by neutralising. The alkaline solution is not coagulated by heat, and, in fact, the substance present in the solution is no longer serum albumin, but a compound of the albumin with the alkali, or **alkali-albuminate**.

---

[1] Lauder Brunton after Kühne, *Journ. of Anat. and Physiol.* Nov. 1869.

[2] Schäfer, *Proc. Roy. Soc.*, vol. xxxiv., p. 370.

Albumin is precipitated by a small quantity and dissolved by excess of most mineral acids, forming with them **acid-albuminates**; thus a watery solution of albumin is precipitated by concentrated nitric, sulphuric, or hydrochloric acid. It is also precipitated by acetic acid along with a considerable quantity of a neutral salt of an alkali or alkaline earth, or of gum arabic or dextrin. This precipitation is perhaps best marked with nitric acid, but it only occurs with moderate quantities of nitric acid. When a minute quantity only of the acid is added, no precipitation takes place, and the solution remains clear; but a nitric-acid-albuminate containing a small quantity of acid is formed, and if the solution is now boiled no coagulum will form. On the addition of more acid, however, a second nitric-acid-albuminate, insoluble in water, is produced, and a precipitate falls. On the addition of more acid still, the precipitate is redissolved, and a third nitric-acid-albuminate is formed, soluble in water, and not precipitated on boiling.

The temperature at which albumin coagulates is altered by acids and alkalies. Alkalies generally tend to raise the temperature of coagulation, and when added in large quantities prevent it altogether.

Very dilute acetic and phosphoric acid, on the other hand, tend to lower the coagulating point, although large quantities may interfere with coagulation.

Neutral salts, such as sodium chloride or sulphate, also lower the coagulating point.

The **organic alkaloids** which have such a powerful action on the animal body appear to resemble acids rather than alkalies in their effect upon albumin, because, according to Rossbach, they lower considerably instead of raising the point of coagulation.

Albumin undergoes an extraordinary change in consequence of the action of ozone, and becomes, after exposure to it, uncoagulable by boiling, and by acids, excepting in large quantities, and by metallic salts, with the exception of basic acetate of lead, and of alcohol.

The action of alkaloids upon this ozonised albumin is even more remarkable than upon ordinary albumin, for when mixed with it in small quantity, they restore its coagulability to the albumin, and cause it to coagulate far under the boiling-point. When added to the albumin before exposure to a stream of ozone, they prevent the albumin being altered by it, in the way which it would otherwise be, and it remains coagulable by heat, in the same way as if it had not been exposed to the action of ozone at all. It is therefore evident that the alkaloids not only increase the coagulability of ordinary albumin at a high temperature, but that they act upon it at ordinary temperatures (30°–40° C.) and destroy its affinity for ozone. This action will naturally interfere

with the processes of oxidation in protoplasm; but the methods of examining this action will be described later on (p. 69).

When a solution of pure albumin is added to a mixture of guaiac and vegetable protoplasm, it greatly lessens the blue colour, which would otherwise be produced. The cause of this appears to be that albumins or albuminous substances have such an affinity for ozone that they take it up instead of allowing it to act on the guaiac. This affinity for ozone is diminished by the action of alkaloids.

This is shown by taking several tubes containing an albuminous solution of a certain strength. Reserving one as a standard, the alkaloids are added to the others, and after a certain time has elapsed, so as to allow the alkaloid to affect the albumin, a small quantity of lettuce water is mixed with each, and then a little guaiac. In the standard one the colour will be least, because the albumin not having been acted upon by the alkaloids will interfere with the reaction of the lettuce water and the guaiac upon each other. In the others a blue colour will appear with greater or less intensity, according as the albumin has been more or less affected by the alkaloid. This experiment, however, is not free from fallacy, because there is to be considered not merely the action of the alkaloid upon the albumin, but its action on the protoplasm as well, and it is therefore advisable to use it in a quantity which is small as compared with the amount of albumin employed.[1]

Action of Drugs on Protoplasmic Movements.

The **amœba** consists of a small mass of structureless protoplasm, without any distinct cell-wall.

It contains numerous granules and nucleus, with nucleolus, as well as one or more vacuoles, which appear to be small spaces filled with fluid.

Some amœbæ live in salt water, others in fresh water; and, although it may be impossible with the microscope to detect any marked difference between them, they exhibit a great difference in their reactions to drugs—the salt-water amœbæ being only slightly affected by them, while fresh-water amœbæ are readily susceptible to their action.

The amœba is nourished by simply adhering to any particle of food, closing over it and digesting it, and afterwards opening and ejecting the residue.

This protoplasmic mass is almost constantly altering in shape, pushing out projections at one point, and drawing them in at another. By this means, also, it moves about from place to place.

Method of Experimentation on Amœbæ and Leucocytes.—In experimenting on amœbæ, take a drop of slimy sediment, such as is found in the tanks of hothouses, and place it on the covering-glass of a microscope; this may then either be put on an object-glass, and the excess of water removed by filter-paper, or, still better, it may be inverted over the opening of a Stricker's warm stage.

[1] Rossbach, *Verhandl. d. phys. med. Ges. zu Würzburg*, N.F., Band iii. p. 346.

When it is simply laid on the object-glass, a solution of the drug is added by putting a drop across the edge of the covering-glass, and allowing it to be drawn gradually underneath by capillary attraction.

Gases are best applied by means of a Stricker's stage, which is also convenient for experiments on solutions.

In experimenting on **leucocytes** with the aid of this stage, a covering-glass is applied to the cut surface of a newt's tail, or to the surface of a drop of blood, so that a very minute quantity of blood adheres to it.

The drug to be tested is kept dissolved in a ·65–·75 per cent. solution of common salt (Na Cl). The salt solution of this strength is often called simply *normal* salt solution, and is used instead of water, because water itself has a very destructive action on those forms of protoplasm, which are usually nourished by saline solutions, like blood or serum.

A drop of the salt solution containing the drug is placed over the blood on the covering-glass, and inverted over the warm stage as already described. If the experiment is to continue long, a rim of oil should be drawn around the edge of the covering-glass with a camel-hair pencil, so as to prevent evaporation.

The advantage of using such a small quantity of blood is, first, that it mixes rapidly and perfectly with the solution; and secondly, that it does not dilute the solution of the drug, and we thus know the strength of the drug used.

If we used a large drop of blood, we should have to employ a solution of the drug twice the strength we desire, so that when a drop of equal size was added to the blood, the mixture would contain the proper proportion.

Amœbæ.—The **effect** of **heat** and **cold** upon the movements is very marked, cold rendering them slow, or arresting them altogether. Heat at first greatly quickens their movements, but when raised to 35° C. it causes them to fall into a state of tetanic contraction and assume a spherical form.

This state is one of heat-tetanus, and if the temperature be now reduced, the movements will again reappear.

At a temperature of 40° C. they also become spherical and motionless. But their movements do not return when the temperature is reduced; they are in a state of heat-rigor, the high temperature having coagulated the protoplasm.

Slight **electrical** shocks from a coil increase the rapidity of the protoplasmic movements; stronger ones cause tetanic contraction; and numerous or powerful ones produce coagulation.

Common **salt** in very small quantity (a drop of 1 per cent. solution slowly added) first quickens the protoplasmic movements and then causes sudden tetanic contraction, and the expulsion of any food they may contain at the moment, and sometimes even expulsion of the nucleus.

When **water** is added so as again to dilute the mixture the amœbæ resume their movements.

Both **acids** and **alkalies**, when very dilute, increase the protoplasmic movements and afterwards arrest them.

Hydrochloric acid has a more powerful action than a solution of potash of a similar strength. It causes the amœba to contract and form a ball with a sharp double contour. In it, twitching movements first occur, which expel any food present. It then becomes pale and lumpy, and breaks up.

Potash causes them to swell up and assume the form of large pale vesicles, which quickly burst.

A **constant current** of **electricity** causes contraction and imperfect tetanus; and, if powerful and long kept up, the positive pole produces in the amœbæ near it the same changes as dilute hydrochloric acid, and the negative pole the same changes as are produced by an alkali such as potash.

Oxygen appears to be necessary for their life; its removal by means of hydrogen deprives the amœbæ of their power of motion, and finally causes contraction and coagulation.

Carbonic acid alone has a similar action to removal of oxygen and produces this effect both in the presence and absence of oxygen, but takes a longer time to do so when oxygen is present.[1]

Leucocytes.—In their appearance and movements leucocytes strongly resemble amœbæ: they are affected in a similar manner by heat, electricity, and drugs. Their resistance to the action of drugs varies somewhat in different animals. Those obtained from the blood of the newt, for example, are more resistant than those of the guinea-pig, and those of the female newt more resistant than those of the male, to the action of quinine.[2] Heat and cold affect the movements of leucocytes in very much the same way as those of amœbæ.

The movements of leucocytes, like those of amœbæ, are of **two kinds**, viz. movements of the protoplasmic pseudopods, while the leucocyte remains *in situ*. The pseudopods in this instance are generally of a waxy look and knoblike form.

Secondly, movements of migration from place to place; these movements are accompanied, or accomplished, through the projection of numerous fine filaments.

Effect of Drugs.— Cinchona alkaloids—quinine, quinidine, cinchonine, and cinchonidine have a remarkable power of arresting these movements in the proportion of 1 in 1,500. They quickly stop the migratory movements of leucocytes from the newt, and in a much larger proportion will arrest the movements of the knoblike pseudopods.

No very marked difference is observed in the strength of the cinchona alkaloids, though quinine seems to be somewhat the most powerful.

Sulphate of bebeerine is almost as powerful as the cinchona alkaloids.

Strychnine is very much less powerful than any of the alkaloids mentioned.

Potassium picrate and æsculin have but little action.[3]

---

[1] Kühne, *Protoplasma und Contractilität*, pp. 28–53.
[2] Geltowsky, *Practitioner*, vol. viii. pp. 325–330.
[3] Buchanan Baxter, *Practitioner*, vol. xi. p. 321.

Movements of Leucocytes in the Blood-vessels.—In the processes of **inflammation** leucocytes pass in great numbers through the walls of the capillaries.

The effect of quinine in arresting their movements, when mixed with them directly, naturally leads one to expect that it may arrest their migration from the capillaries, when injected into the blood, and this anticipation has been realised in the experiments of Professor Binz.

To observe this phenomenon the brain of a frog is to be destroyed, and a little curare injected under the skin, in order to abolish any spinal reflex movements. It is then laid on a piece of cork, such as that shown in Fig. 8, with a hole at one side, over which a piece of glass is fastened about




FIG. 8.—Apparatus for examining the mesentery of the frog under the microscope.

half an inch higher, by means of two other pieces of cork and some sealing-wax. On this a piece of sheet cork of the form shown in the figure, and a round piece of glass are cemented so as to form a channel, in which the intestine lies. The body of the frog is fixed to the cork, the abdomen opened, the intestines drawn out, and the mesentery fastened with very fine pins over the aperture. In half an hour, or two hours, the leucocytes pass rapidly through the walls of the capillaries, and afterwards wander through the tissues.

The drug may then be injected into the lymph-sac, or locally applied to the mesentery.

When quinine is applied locally to the mesentery in this condition it arrests the movements of the leucocytes, which have




FIG. 9.—Diagram to illustrate the action of quinine on leucocytes, modified from Binz (*Das Wesen der Chininwirkung*. Berlin, 1868). The thick lines represent the walls of the blood-vessel, and numerous leucocytes are shown both inside it and outside distributed through the adjoining tissues. *a* represents the vessel before, and *b* after, the *local* application of quinine. The leucocytes outside the vessel have their movements arrested, and cannot wander on through the tissues, while those inside are not affected and continue to emigrate. *c* represents the effect of quinine injected into the circulation or lymph-sac. The leucocytes inside the vessel are here affected first, and their emigration stopped, while those outside still continue to travel onwards.

already emerged, but does not prevent those which are still within the vessels from going out; they therefore form a dense accumulation around the vessel (Fig. 9, *b*). When injected into

the circulation, on the contrary, the leucocytes which are in the vessels are prevented from passing from the capillaries, while those which have already passed out continue to wander onwards, and thus a clear space is left outside the vessel (Fig. 9, *c*).

The quantity of quinine necessary to produce this effect is $\frac{1}{25000}$th to $\frac{1}{20000}$th of the animal's weight.

If quinine were given to stop the exit of leucocytes from the vessels in peritonitis, three or four grammes would be required to be given within a short time, to a man weighing 150 lbs.

In guinea-pigs a dose of quinine sufficient to kill the animal does not stop the movements of the leucocytes in its blood, which are seen to go on, when a drop of it is examined after death.

Red Blood Corpuscles.—The size of the red corpuscles is diminished by carbonic acid, by morphine, or by warmth, either applied locally on the hot stage of a microscope, or acting on them in the vessels of an animal suffering from fever.

It is increased by oxygen, hydrocyanic acid, quinine, or cold; and an increase occurs also in cases of anæmia.[1]

The red corpuscles pass out of the capillaries like the white, but they do so very slowly indeed, and in small numbers, under ordinary circumstances. Excess of sodium chloride in the blood causes them to pass out much more quickly;[2] and rattle-snake poison, when locally applied, produces such sudden extravasation that it is impossible to follow the process: the whole field of the microscope becoming suddenly covered with blood.[3]

Action of Drugs on Infusoria.

Among the infusoria, like the amœbæ, each individual consists of a single mass of protoplasm, and not of a number of distinct cells; but the protoplasm is differentiated. Round the greater part of the animal it seems to be somewhat harder, so as to form a sort of skin, excepting at one place which is softer than the rest, serving for the ingress of food and the egress of egesta.

Instead of throwing out pseudopods, the body is either covered entirely with cilia or they are arranged round the mouth. Once it has entered by the mouth, the food finds its way all through the protoplasm of the body.

A contractile vesicle exists, which pulsates rhythmically.

Mode of Experimentation. — For the purpose of examining the action of drugs upon infusoria an infusion of hay is prepared some days previously. Two small pipettes are then made, which will deliver drops of equal size.

This is done by heating a piece of glass tubing in the middle, drawing it out, and cutting it across by a scratch with a triangular file (Fig. 10). With one of these a drop of hay-infusion is placed on the covering-glass, which is inverted on a Stricker's stage and examined. In order to ascertain

---

[1] Manassein, *Ueber die Dimensionen der Blutkörperchen unter verschiedenen Einflüssen.* Tübingen, 1872.

[2] Prussak, *Wiener Akad. Sitzungsber.* lvi., 1876 (Abth. 2), p. 13.

[3] Brunton and Fayrer, *Proc. Roy. Soc.*, February 1875, p. 271.

the lethal strength of a drug, a drop of a solution of the poison of a definite strength is then mixed with it, and the infusoria are examined again after a certain time.




FIG. 10.—Diagram to show the way of making small pipettes.

If they continue moving, another experiment is made with a stronger solution; but if they have completely stopped, it is repeated with a weaker one until the solution is of such a strength that the movements become very slight and cease almost immediately after mixing, and cannot be restored by the addition of water. As the two drops of fluid were of equal size, the lethal strength of the solution is just one half of that which was last added. By repeating the experiments in exactly the same way with different drugs, their relative poisonous properties are ascertained.

Heat increases the rapidity both of the rhythmical contractions of the vesicle and of the ciliary motion and consequently of the movements from place to place of the infusoria. It seems as if the cilia were not equally affected by heat, those which produce a longitudinal movement appearing to be acted upon more quickly than those which cause a movement of rotation. Both kinds are first stimulated and then paralysed.

At temperatures between 25° and 30° C. the contractions of the vesicle are greatly quickened, and the animal moves with great rapidity in the longitudinal direction.

Between 30° and 35° its movements are still very rapid, but it seems to have lost the power of direction; all the cilia seem in full action, and the movements of the individual are determined simply by their anatomical arrangement.

Above 40° the cilia, which act longitudinally, appear to have stopped and the animal rotates, at first very rapidly, then slower and slower until all movements cease, and the protoplasm appears to become fluid; but when the heat is still further raised it coagulates.[1]

Cold lessens the quickness of the rhythmical contractions of the vesicle, of the ciliary motion and of the movements from place to place. Weak **electrical currents** first quicken the ciliary motion and cause movements of rotation, then swelling of the protoplasm, slower movements, and finally apparent solution of the protoplasm.

Moderate currents produce a tetanic contraction of the protoplasm and of the cilia, while the contractile vesicle is unaffected.

Strong currents cause liquefaction of the protoplasm.

Saline solutions appear rather, if we may say so, to alter the conditions under which the infusoria live than to affect the protoplasm itself. Strong solutions cause them to shrivel and

[1] Rossbach, 'Die rhythmischen Bewegungserscheinungen der einfachsten Organismen,' *Verh. d. Würzburger physik. med. Gesellsch.* A.N.F., Bd. ii., Separat-Abdruck, S. 23. This work contains a number of exceedingly interesting and valuable observations on the subject.

then to swell up and become motionless. This effect appears to be due to the solution altering the quantity of water which the protoplasm contains.

Weaker saline solutions, on the contrary, quicken their movements, and, instead of causing them to shrivel, make them swell up at once. Chloride of sodium, chloride, bromide, and chlorate of potassium, as well as alum, all have this effect.

Acids in minute quantities cause contraction both of the body and of the vesicle. The ciliary motion is at first quickened and then retarded; the rate of contraction of the vesicle is at once diminished.

Moderate quantities cause coagulation of the protoplasm with swelling and liquefaction after death.

Strong acids at once destroy the protoplasm.

Alkalies in minute quantities cause swelling of the protoplasm, dilatation and slowness of the contractile vesicle.

Moderate quantities at once arrest the movements, cause liquefaction of the protoplasm, and destroy its differentiation, the contractile vesicles and vacuoles disappearing. They then cause swelling, and finally solution.

In large quantities they produce immediate liquefaction of the whole body.

Other drugs appear to affect the protoplasm itself, and arrest its movements without producing any apparent change in it.

The most active are chlorine, bromine, corrosive sublimate, iodine, permanganate of potassium, and creasote.

Quinine is much less powerful than these, though it is much more so than most other organic alkaloids. Strychnine has only one-fourth the power of quinine.

Cobra poison at first greatly quickens the movements of infusoria and then arrests them, causing just before death a contraction of the protoplasm, which then expands to its ordinary size.

Relations of Motion and Oxidation.

All animals, from the lowest to the highest, evidence their life by motion at one time or another; and the energy required for this motion is maintained by processes of combustion.

The materials for this combustion, viz. oxygen, and fuel of some sort, or food, are derived from the external medium in which the animal lives; and in order to enable these substances to be available for each part of the animal body, we must have some kind of respiration and circulation going on in it.

In unicellular organisms, consisting of a single mass of protoplasm, the oxygen is derived from the water in which they swim, and both it and the nutritive material derived from the digestion

of enclosed masses are circulated through the protoplasm by contractile vacuoles.

In sponges, where the organism no longer consists of one but of several cells united into a community, some of these are furnished with cilia, in order to send a current containing oxygen and food to the other cells having a less favoured position.

In higher animals, where many cells are built up to form one organism, we find a circulatory and respiratory apparatus fully developed.

The medium in which unicellular organisms live is the water in which they swim. The medium in which the cells composing the main parts of the bodies of higher animals, such as man, live, is not the air which surrounds the body, but the intercellular fluid in which the cells themselves are bathed.

As Claude Bernard points out with his usual clearness, the cells of the human body and the lowest unicellular organisms alike live in a liquid medium. From the layer of fluid surrounding it, the cell takes up the oxygen and food which this layer can yield. The supply being exhausted, a unicellular organism can move on elsewhere, but the cells in higher animals, being fixed and unable to move, require fresh portions of oxygen and of nutritive fluid to be brought to them.

This is effected by the slow circulation of the lymph in which the cells themselves are bathed and by the supply to the lymph of oxygen and nutritive material from the blood.

The circulation of the lymph is aided in many lower organisms by the motion of cilia, and this is found persisting in some parts of the higher animals, *e.g.* the central canal of the spinal cord.

Between the blood and the lymph an interchange goes on, oxygen passing from the blood to the lymph or intercellular fluid, and carbonic acid from the lymph to the blood.

This interchange of gases between the blood, the intercellular fluid, and the cells is termed **internal respiration.**

In order to maintain this, a constant current of blood must take place; and when its circulation is locally arrested it becomes deprived of oxygen and loaded with carbonic acid, so that the cells in the district in which the stagnation occurs suffer from local asphyxia, while the other parts of the body may be perfectly healthy.

When the general circulation is arrested by stoppage of the heart, by obstruction of the pulmonary arteries, or by the rupture of an aneurism draining the blood away, the whole body suffers in a similar manner from general asphyxia by the cessation of internal respiration.

If oxygen were simply dissolved in the blood, the quantity which would be conveyed to the tissues would be too small for their wants, and we therefore have as an oxygen-carrier a sub-

stance capable of taking up a large quantity of oxygen, of readily forming a loose compound with it, and of again giving it off readily to oxidisable substances.

In man and mammals and many of the lower animals this substance is hæmoglobin containing iron. In some annelids it is a green substance, chlorocruorin; and in the octopus and some crustaceans it is a blue body, hæmocyanin, containing copper.[1]

In order to remove carbonic acid taken up from the tissues and obtain a fresh supply of oxygen, an interchange takes place between the blood and the external air in the lungs; this is **external respiration.** Without any direct influence being exerted upon the cells of the animal body themselves, they may be affected and their **nutrition** greatly **modified** by:

1st. Alterations in the circulation of the intercellular fluid or lymph in which they are bathed.

2nd. In the greater or less rapidity of circulation of blood locally.

3rd. In the circulation generally, from changes in the heart and blood-vessels generally.

4th. Changes in the oxygen-carrying power of the blood, either from alterations in its power to take up or give off oxygen.

5th. Changes in the external respiration.

All these conditions may be altered by drugs, or at least by therapeutic measures. Thus the circulation of lymph in a part may be increased by shampooing, and its accumulation in a case of dropsy may be removed by incision, by puncture, or by drainage.

The circulation of blood may be arrested locally and gangrene induced by the continuous use of ergot. It may be increased by the use of local stimulants or irritants.

The circulation generally may be affected by the large class of vascular stimulants and depressants, to be afterwards discussed, and sometimes by stoppage of the pulmonary circulation through minute emboli.

Alterations in the oxygen-carrying power of the blood will be discussed presently, and those in the external respiration subsequently.

Oxidation of Protoplasm.—The movements of protoplasm are intimately connected with processes of oxidation going on in it.

By these processes chemical energy is converted into the mechanical energy exhibited in the movements, and this is sometimes very considerable.

The oxygen which takes part in these processes is not always derived from the surrounding medium at the exact moment when

[1] For further details see *Physiological Chemistry*, by A. Gamgee, vol. i., 1880, p. 130.

the movements take place; it may have been obtained some time before, and the movements may continue for a little while after all oxygen has been removed.

It therefore appears that protoplasm has the power of absorbing and storing up within itself, in some manner or other, oxygen, which it can afterwards utilise for the purpose of liberating mechanical energy.

This **storage of oxygen** takes place not only in the protoplasm of unicellular organism, but also in the tissues of the higher animals, *e.g.* the muscles.

The exact way in which storage occurs is not known, but it has been well compared by Professor Ludwig to the storage of oxygen in gunpowder. The oxygen is there contained in the nitrate of potassium, a compound which is readily decomposable by the application of heat, and then gives rise to the evolution of mechanical energy; and this it does perfectly well in an enclosed space, like a gun-barrel, where no air is present.

The power of storing up oxygen is very limited, and although protoplasmic movements continue for a little while after all external oxygen has been removed, yet they will not continue long.

A convenient way of ascertaining this fact has been devised by Kühne, who adds a small quantity of blood or of hæmoglobin solution to a drop of water containing protoplasmic organisms or cells placed on a covering-glass. This is then observed with a micro-spectroscope. The hæmoglobin solution exhibits the two bands characteristic of oxy-hæmoglobin. When all the oxygen is removed by means of a stream of hydrogen, kept up for some time, the spectrum of oxy-hæmoglobin passes into that of reduced hæmoglobin.

The occurrence of this change indicates the moment when all the oxygen has disappeared from the liquid. By reckoning from this moment onwards, we are able to estimate the length of time during which the movements continue in the absence of oxygen.

Oxygen-carrying Power of Protoplasm.—Not only does protoplasm possess the power of taking up oxygen readily and assimilating it to itself, but it has also the power of taking up and giving off oxygen to other substances when these substances would be unable to take it themselves.

We may understand this action better by comparing it in a very rough way with that of a man whose greater strength enables him to seize fruit or break off pieces of sweatmeat and give them to his child, which thus enjoys what it could not have obtained for itself, however desirous of them it might be.

Method of Experimenting.—Guaiac resin, when finely divided and oxidised, becomes of a blue colour. It has, however, only a slight power of attracting oxygen to itself from the air, or from water in which the oxygen is dissolved, and thus the blue colour is developed slowly.

On the addition of protoplasm to the water containing the guaiac, the blue colour is developed rapidly. The reason of this possibly is, that the protoplasm has taken up oxygen from the water and given it over to the guaiac. This process reminds us of the action of spongy platinum in causing oxidation of hydrogen or formic acid.

Ozonising Power of Protoplasm.—It has been supposed that, in addition to its power of oxidising such substances as guaiac by giving to them oxygen which it has already taken up, protoplasm has the power of actually breaking up the molecules of oxygen and forming ozone.

The rapid oxidation which protoplasm causes has been attributed to this power. A similar action to this is observed during the slow oxidation of phosphorus. Phosphorus appears to break up the molecule of oxygen, taking to itself one atom and freeing another, which unites with two more in order to form ozone.

Action of Drugs on Oxidation.—A convenient way of testing the effect of drugs upon oxidation is to use the protoplasm of potato, of lettuce, or of dandelion. The most active part of the potato lies just under the skin, as is seen by pouring some freshly prepared tincture of guaiac over its cut surface. A ring of blue first forms close to the skin, and is always darkest there, although it may extend over the whole of the cut surface. The ammoniated tincture of the British Pharmacopœia will not answer. The tincture must be made with spirit only. When potato is used, the whole of the potato may be pounded with water, or, still better, the peel alone may be cut off and rubbed up with water in a mortar and then filtered through linen. When lettuce or dandelion is used, the fresh leaves are triturated




FIG. 11.—Test-glasses for examining the action of drugs on oxidation.

in a mortar with five or ten times their bulk of water, and the solution is then filtered. A row of test-tubes or test-glasses having been prepared, a measured quantity of water is put into the first. In this glass the protoplasm is not mixed with any foreign substance, and it therefore serves as the standard with which to compare the others; and into the others is put a similar quantity of solutions of the drugs to be tested. Each test-glass is distinguished by a label bearing either a number or the name of the drug which it contains attached to it. To each glass a measured quantity of the lettuce-water is added and the contents mixed by shaking. All are allowed to stand for a period varying from a few minutes to some hours. Then a small drop of freshly-prepared tincture of guaiac is added to each, mixed by shaking, and allowed to stand for one or two minutes; the glasses are then arranged in the order of depth of colour.

In this way it is found that many drugs greatly lessen or almost completely abolish the oxidising power of protoplasm, so that while the lettuce-water in the standard glass assumes a dark-blue colour, that in the others exhibits varying shades of blue, or may even retain the creamy-white colour caused by the guaiac without showing any blue whatever.

The colour is deeper and the reaction is more readily obtained when the tincture of guaiac is mixed with some substance capable of giving off oxygen readily, such as a solution of peroxide of hydrogen in ether, usually called ozonic ether.

A number of experiments made with potato-water by Cash and myself showed that oxidation in potato solution was diminished most powerfully by strychnine, then by quinine and coniïne; next by morphine, codeine, cinchonine, and atropine, each of which had almost exactly the same action;

next by nicotine, and then veratrine. Aconitine seemed neither to retard nor accelerate oxidation, and presented exactly the same degree of coloration as the standard solution. Caffeine, picrotoxin, and digitalin appeared somewhat to hasten oxidation.[1]

Reduction by Protoplasm.—Ehrlich[2] has shown, in an interesting manner, the properties of oxidation and reduction possessed by protoplasm. Methylene-blue, alizarin-blue, and indo-phenol are coloured bodies which become colourless on being reduced. After injecting methylene-blue into the veins, he found that most of the parenchymatous tissues became coloured, the heart, brain, cortex of kidney, the voluntary muscles, &c., while the lungs and the liver were normal and only a small amount of colouring matter could be obtained by prolonged exposure to the air. Ehrlich concluded that the indifferent paraplasma of the cells excretes the unchanged matter, while the protoplasm, which is greedy for oxygen, excretes the reduced colouring stuff.

Action of Drugs on Blood.

The hæmoglobin of blood has also the power of taking up oxygen readily and giving it freely off again. Hæmoglobin free from oxygen, or, as it is sometimes called, **reduced hæmoglobin**, is recognised by the simple band which it gives between D and E, when examined spectroscopically.

Hæmoglobin combined with oxygen, or **oxyhæmoglobin**, gives two bands, situated in nearly the same portion of the field of the spectroscope. These are separated from one another by a clear space, and are more sharply defined and darker than the spectrum of hæmoglobin.

The oxygen of oxyhæmoglobin may be replaced by other gases. Thus:—**Carbonic oxide** drives out the oxygen from oxyhæmoglobin and forms carbonic oxide hæmoglobin (CO-hæmoglobin). This is a comparatively stable compound. It presents spectroscopic bands nearly the same as those of oxyhæmoglobin, but which are slightly nearer to the violet end of the spectrum. This compound, being stable, circulates in the blood without performing the functions of respiration. It neither takes up oxygen in the lungs nor gives off oxygen to the tissues.

Animals poisoned by CO therefore die of asphyxia, the internal respiration being arrested, and their blood remains for a long time of a florid colour.

Hydrocyanic acid appears also to form a compound with hæmoglobin, which is much less stable than that of carbonic oxide. There has been a good deal of discussion about this

[1] *St. Bartholomew's Hospital Reports*, 1882.

[2] Ehrlich, 'Zur biologischen Verwertung des Methylen-Blau,' *Centralblatt f. die med. Wissenschaft.* 1885, No. 8.

compound, and its existence, indeed, has been denied. The spectrum of this compound consists of a single band resembling reduced hæmoglobin, but nearer the violet end of the spectrum.

Solutions of hæmoglobin when boiled are completely decomposed into hæmatin and a proteid body or bodies.

Hæmatin gives a single band, which differs according as the solution is alkaline or acid, and according as the solvent is water or ether.

Acids split up hæmoglobin into hæmatin and a proteid. It is sometimes possible to get these to recombine and to again form hæmoglobin, but this is far from being always the case.

Methæmoglobin appears either to be a product of the incomplete decomposition of hæmoglobin or of its excessive oxidation. Some think that it contains more oxygen than hæmoglobin, but less than oxyhæmoglobin. Others think that it is a peroxyhæmoglobin containing more oxygen than oxyhæmoglobin. At all events the oxygen is more firmly combined in methæmoglobin than it is in oxyhæmoglobin.

This body is distinguished by a spectroscopic band nearly in the same place as that of the acid hæmatin.

When the solution is made alkaline by ammonia this band disappears, and is replaced by another fine one near D.

Methæmoglobin appears to be converted again into hæmoglobin by the action of reducing agents and subsequent oxidation. When its solution is treated with reducing agents, it shows the spectrum of reduced hæmoglobin; and on shaking this with air oxyhæmoglobin is formed, as shown by the appearance of its characteristic bands.

When blood is allowed to stand for a length of time, it assumes a brownish colour and gives the bands of methæmoglobin. When **nitrites** are mixed with freshly-drawn blood, they impart to it a chocolate colour, and it then exhibits the bands of methæmoglobin.

As the oxygen in methæmoglobin is more firmly combined with it than in oxyhæmoglobin, substances such as the nitrites interfere with internal respiration, and thus in large doses will cause symptoms of asphyxia; but their action differs from that of carbonic oxide in one very important particular, viz., that it is altered by asphyxia; whilst that of carbonic oxide is not. Reducing substances are constantly present in the blood and tissues, and these accumulate to a greater extent during the process of asphyxia. Carbonic-oxide hæmoglobin, being a stable compound, remains unaffected by these, and the blood continues to circulate unchanged.

But methæmoglobin, which is produced by the action of the nitrites, becomes reduced by these substances and forms the normal reduced hæmoglobin ordinarily present in venous blood. When this reaches the lungs it again takes up oxygen, forming

normal arterial blood, by which the internal respiration is again restored. Thus, unless new supplies of nitrites are constantly added to the blood, the asphyxia they occasion quickly passes away. That caused by carbonic oxide, on the contrary, is much more permanent. It is not removed by artificial respiration, and in order to save the life of the animal or person poisoned by it, a quantity of the poisoned blood must be withdrawn from the veins and healthy blood introduced by transfusion.




FIG. 12.—Chart showing the spectroscopic absorption-bands of hæmoglobin and its derivatives. (After McMunn.)

A method of ascertaining the effect of drugs on **oxidation** in the **blood** consists in estimating the rate at which **acid** is developed in it after its removal from the body.

In this way Binz and his scholars, Zuntz, Scharrenbroich, and Schulte, have found that both quinine and sodium nitropicrate stop the formation of acid; cinchonine lessened it.[1]

The alterations effected in the **interchange** between **blood** and the **air** have also been observed by simply allowing the blood mixed with the drug to stand for a certain time in a closed receiver, partially filled with air, and afterwards analysing the gases which the receiver contains at the end of the experiment.

By this mode of experimentation, Harley [2] found that hydrocyanic acid diminished or arrested the processes of oxidation in the blood. Alcohol, chloroform, quinine, morphine, nicotine, strychnine, and brucine, all had a similar action, though varying in extent, all of them diminishing both the amount of oxygen absorbed and of carbonic acid given out.

Uric acid and snake poison had a contrary effect, increasing

[1] A very complete list of the literature of this subject is given by Binz in his work, *Das Chinin*, Berlin, 1875.

[2] Harley, *Phil. Trans.*, 1865, p. 678.

the absorption of oxygen and the evolution of carbonic acid. Curare appeared to lessen the absorption of oxygen, but increased the evolution of carbonic acid. Mercuric chloride lessened the carbonic acid, but increased the absorption of oxygen. Arsenious acid and tartar emetic diminished the absorption of oxygen, but arsenious acid appeared also to lessen the evolution of carbonic acid, while tartar emetic appeared to increase it.

Catalysis.—Fermentation.—Inorganic Ferments.

There are many examples of chemical reactions which only occur between two bodies when a third is present, which may nevertheless be found unchanged at the end of the process. Notwithstanding the fact that the third body is found unchanged at the end of the process, it may have undergone changes during the continuance of the process. Thus alcohol is not converted into ether and water by boiling alone, but it does undergo this conversion by boiling with sulphuric acid. The acid is found unchanged at the end of the process, but is changed during it into ethyl-sulphuric acid, which, combining with alcohol, again yields sulphuric acid along with ether.

In other cases, however, we cannot show that the substance has undergone change. Thus starch is converted into dextrin and sugar and cane-sugar into grape sugar by boiling with acids, but we do not at present know that the acid has undergone any change during the process as it does in the preparation of ether. Peroxide of hydrogen is rapidly decomposed by finely divided platinum or silver, and finely divided platinum will, on the other hand, cause oxygen and hydrogen to unite rapidly. Such actions, where the third substance seems to act by its mere contact with the other substances, and without undergoing change itself, are called **catalytic**. They are probably due to an attraction of some kind bordering both on chemical and physical between the molecules.

Thus some organic substances would resist the oxidising action of the air for a considerable time, but they are readily oxidised by charcoal. It is usually said that the charcoal has the power of attracting oxygen and condensing this gas upon its surface. It does not unite with the oxygen chemically so as to form CO_2, but merely attracts it, holds it for a while, and then gives it off readily to any oxidisable substance. Platinum, palladium, rhodium, and iron absorb hydrogen, palladium doing so to an enormous extent, especially when it is in a spongy form. The hydrogen is supposed by some to be simply condensed within the metal, while others think that the hydrogen and metal unite to form a hydride. The hydrogen is given off from the metal in a nascent form, and has very strong affinities.

Thus palladium-hydrogen readily reduces ferric to ferrous salts, the hydrogen taking oxygen from the ferric salt and forming water. But when the hydrogen is liberated from palladium or rhodium in presence of oxygen, it appears to convert the oxygen into ozone, and greatly increases its oxidising power. Thus palladium-hydrogen with oxygen colours a mixture of potassium iodide and starch paste blue, and oxidises hæmoglobin to met-hæmoglobin and ammonia to nitric acid. Spongy rhodium, or iridium saturated with hydrogen, cause formic acid to be oxidised to carbonate, calcium formate being changed into calcium carbonate. Exactly the same action is possessed by an organic ferment, and in the conversion of the formic into carbonic acid the ferment and the spongy rhodium or iridium are alike unchanged. Spongy platinum, palladium, rhodium, and iridium may thus be regarded as **inorganic ferments.**[1]

Ferments Organic and Organised.

The mechanical energy displayed in the movements of protoplasm is supplied by processes of chemical change, and chiefly of oxidation.

By these processes some of the substances contained in the protoplasm are destroyed, and their place must be supplied by fresh material. This material is obtained from the food, but, in order to render it available for the protoplasm, its atoms must be more or less disintegrated in order that they may again be assimilated. As Hermann very well puts it, the bricks of which the old house is built must be pulled asunder before they can be




FIG. 13.—An amœba figured at two different periods during movement. *n*, nucleus ; *i*, ingested bacillus.

built up again into the new. In the present case, the bricks are the atoms of protoplasm in some other organism living or dead, which is being used as food by some larger mass of protoplasm, as, for example, a bacillus which has been absorbed by an amœba. (Fig. 13.)

In order to render the protoplasm in the bacillus available for the nutrition of the amœba, the atoms of which it is composed

[1] Hoppe-Seyler, *Ber. d. deutsch. chem. Gesellsch.*, 1883, Feb. 12, p. 117.

must be, to some extent, decomposed. This process appears to be effected by enzymes or, as they are sometimes called, organic ferments.

Ferments are bodies which split up carbon compounds at moderate temperatures and lead to the formation of other carbon compounds, most of which are of a simpler constitution than the first.

In this definition we require to introduce the term 'moderate temperature,' because excessive heat alone will cause the atoms of a complex carbon compound to fly asunder and form simpler compounds, as in the process of dry distillation. A less heat than this, but aided by the action of powerful chemicals, will also produce the same effect. For example, fibrine heated with diluted hydrochloric acid under pressure yields peptones; but the same change is effected at the temperature of the mammalian body by the aid of pepsin. Trypsin from the pancreas effects a similar change when mixed with water alone without the aid of an acid, though its action is certainly aided by alkalies. Neither pepsin nor trypsin are alive, but they contain carbon, and are therefore called **organic ferments.** But this term easily leads to confusion with ordinary living or organised ferments, and so the term **enzymes** has been lately introduced to signify ferments such as diastase, ptyalin, and pepsin, which, though they contain carbon and are therefore called organic, are not alive and have no definite structure, or, in other words, are not organised. The term **unformed ferments** has also been applied to them.

By **organised ferments** we mean minute living organisms, which in the course of their life-processes cause decomposition of the substances in which they live. They have also been called **formed** ferments. Examples of these are yeast and bacteria.

The processes of **fermentation** have been divided by Hoppe-Seyler into **two kinds**:—

(1) Those in which water is taken up; and (2) those in which oxygen is transferred from the hydrogen to the carbon atom.

The hydration in the **first** case is produced by the ferment acting either (*a*) like a dilute mineral acid at a high temperature, as in diastatic and invertive ferments and in the decomposition of glucosides; or (*b*) like caustic alkalies at a high temperature, as in the splitting up of fats or the decomposition of amide compounds. These processes of fermentation by hydration are chiefly carried on by enzymes.

The **second** class of fermentative changes by the transference of oxygen from the hydrogen to the carbon, as in lactic and alcoholic fermentation and in putrefactive processes, are chiefly produced through the agency of organised ferments. The action of the latter may be to a certain extent imitated by spongy platinum, which absorbs oxygen readily, and readily gives it off again to oxidisable substances. Thus acetic fermentation usually

produced by an organised ferment may be also brought about by spongy platinum.

The **products** formed by the action of organised ferments on the media in which they live are poisonous to them; and when these products accumulate above a certain proportion, they kill the ferments. Just as a fire will be smothered in its own ashes, or an animal in a confined space will be poisoned by the carbonic acid which it has itself produced, so the yeast plant, when living in a solution of sugar, is killed by the alcohol which it produces, as soon as this amounts to 20 per cent.; and other organised ferments have their lives limited in a similar way.

Action of Drugs on Enzymes.—Although, with the exception of a kind of pepsin in the naked protoplasm of *Æthalium septicum*, a species of myxomycetes,[1] enzymes have not been shown to be present in the protoplasm of the lowest organisms, it is probable that the processes of life in all living beings from the lowest to the highest are carried on by their means. A ferment, which is evidently of the greatest importance in the animal economy, has been recently discovered in the blood by Schmiedeberg. He has given to it the name of Histozyme, and he believes that its function is to split up nitrogenous substances preparatory to their oxidation.[2] The chief enzymes are the following:—

Diastatic or Amylolytic	Which convert starch and amyloids into maltose	Diastase from malt. Ptyalin from saliva. Amylopsin from pancreas. Other ferments having a similar action from other parts of the body.
	Which convert maltose into glucose	From small intestine.
Inversive Ferments	Which convert cane sugar into dextrose and levulose	Invertin from the intestinal juice. ,, ,, mucus of the mouth. ,, ,, tissue of the testis.
	Which decompose glucosides	Emulsin from bitter almonds. Myrosin from mustard.
	Decomposing sugar	Rennet.
	Decomposing fats	From stomach. From pancreas (Stearopsin).
Proteolytic Ferments	Which decompose proteids and form peptones	Pepsin from stomach. Trypsin from pancreas. Others from saliva. Histozyme.

The action of drugs on enzymes is ascertained by taking two portions of a solution containing the enzyme and the substance to be acted upon. To one of these a quantity of the drug to be tested is added, the other acts as a standard with which to compare it. If the drug is in solution, a corresponding quantity of water must be added to the standard solution in order that both may be alike. They are then placed in a warm chamber and the rapidity of digestion is noted.

[1] Krukenberg, *Untersuch. a. d. physiol. Inst. d. Univ. Heidelberg*, Bd. II., 1878, p. 273.

[2] Schmiedeberg, *Arch. f. exper. Path. u. Pharm.*, Bd. xiv. S. 379.

The effect of some of the more important drugs on the action of enzymes will be readily seen from the following table from Wernitz, quoted by Meyer.[1] In it the proportion is shown of the drugs which arrest in watery solution the action of enzymes; thus, one part of chlorine in 8,540 parts of a watery solution will arrest the action of ptyalin upon starch paste, while creasote has no action on it even in saturated solution, and corrosive sublimate is so enormously destructive as to arrest its action, even in one part in 52,000.

[1] Hermann Meyer, 'Ueber das Milchsäureferment u. sein Verhalten gegen Antiseptica,' *Inaug. Diss.* Dorpat, 1880.

	Emulsin	Myrosin	Diastase	Invertin	Ptyalin	Pepsin	Pancreatin	Rennet
Chlorine	1:35614	1:38888	1:7411	1:5980	1:8540	1:27167	—	—
Corrosive sublimate	1:65000	1:13000	1:50000	1:17500	1:52000	1:1766	1:21600	1:720
Iodine	1:5500	1:24070	1:4125	1:1000	1:4166	1:7817	—	—
Hydrochloric acid	—	—	—	—	—	—	—	—
Eucalyptus oil	1:100	Acted only in excess		—	—	—	—	—
Bromine	1:12654	1:28490	1:5070	1:2840	1:5580	1:16777	—	1:31100
Mustard oil	Only lessens action in saturated solution			—	—	—	—	—
Copper sulphate	1:11000	1:8100	1:6500	—	1:7500	1:110	1:6600	1:200 Has no action
Salicylic acid	1:7600	1:2600	1:5100	1:166	1:1250	1:250	1:9000	1:333 No action
Sulphurous acid	1:21666	1:20485	1:8600	1:1940	1:8600	1:1317	—	—
Benzoic acid	1:2100	1:1100	1:1025	1:400	1:2600	1:200	1:2600	1:300 Has no action
Chloride of lime	1:36713	1:34333	1:6613	1:4950	1:6613	—	—	1:28400
Creasote	1:60	No action even in saturated solution				1:65	—	—
Thymol	1:100	Slight action, or none, even in saturated solution				—	—	—
Carbolic acid	1:20	1:33	1:30	1:34	1:25	1:50	—	1:100
Borax	1:100	1:110	1:100	1:3580	1:100	—	—	1:1000
Benzoate of soda	1:100	1:20	1:100	1:65	1:86	—	—	1:50
Turpentine water	1:2	Only weakens —	—	—	—	—	—	—
Chloroform	Little or no action, even in saturated solution			—	—	1:60	—	—
Alcohol	1:28	1:35	1:3	1:10	—	1:6	1:3	—
Glycerine	1:3	1:2	1:2 Weakens	1:2 Weakens	1:3 Weakens only	1:3	—	—
Acetate of aluminium	1:50 Weakens	1:50 No action	1:380 No action	1:100 Weakens	No action	—	—	—

The different action which the same drug exerts upon formed and unformed ferments is of great importance, because upon it depends our power to use the drug in the practice of medicine. Thus creasote, which appears from the preceding table not to destroy the digestive power of ptyalin and to have but a weak action upon that of pepsin, has been found by Werneke to destroy yeast in a dilution of one part to 500 of water; and by Bucholtz to kill bacteria in a dilution of one part to 1,000 of water. This difference enables us to arrest fermentation in the stomach depending on the presence of low organisms, while the digestive action of the pepsin is not interfered with, or only very slightly. The following diagram shows the action of drugs on enzymes and on the lactic ferment, which is a bacillus.




FIG. 14.—Diagram to show the different action of drugs on different enzymes. The nature of the line showing the action of each drug is shown under its name.

Zymogens.

As several enzymes act readily in neutral or slightly alkaline fluids, it is evident that if they existed free in every part of the animal body, they would soon lead to its speedy destruction. Accordingly, we find that they do not normally exist free, except at the times and places they are required.

This fact was first discovered by Kühne in relation both to the stomach and pancreas, and was announced by him in the course of lectures which he delivered at Amsterdam in 1868-69, which I attended. In my note-books of those lectures I find that he stated that there seems to exist 'a pepsin-giving substance,' because if a 'slice of stomach is thrown directly into dilute HCl of 4 parts to 1,000 of water at 40° C. no digestion takes place,' [1] a fact which shows that pepsin is not always present in it. In regard to the pancreas, he not only recognised the existence of a ferment-yielding body, but described a mode of obtaining ferment from it in the following words :—'Glands which have no action on fibrine can be made active by digesting in very dilute acid and then neutralising or alkalising, there seeming to exist a *ferment-forming* substance in the pancreas.'

Kühne's discovery of the existence of ferment-yielding bodies does not seem to have become widely known, and it was again made independently by Liversedge [2] in regard to the amylolytic ferment of the pancreas, and by Heidenhain in regard to trypsin. These observers found that when glands which did not contain ferment were exposed to the air ferments were formed.

Heidenhain [3] also investigated more fully these ferment-forming substances, and gave to them the name of zymogens.

The methods by which we **obtain ferments from zymogens** are, therefore, exposure to air and treatment with acids.

Organised Ferments.

The chief organised ferments are the **yeast**-plant, which produces alcohol and carbonic acid from grape sugar, and various kinds of **bacteria**, one of which produces butyric, another lactic, and another acetic fermentation. Both yeast and bacteria belong to the lowest class of plants, the protophytes. To this class also belong moulds, the action of drugs upon which is sometimes important, inasmuch as moulds give rise to some skin diseases.

Yeasts, moulds, and bacteria have been variously classified by different authors, and the classification is apt to undergo changes as our knowledge of the life-history of these different organisms increases.

At present it is not certainly known whether the various

---

[1] Just after this there is unfortunately a blank in my notes, but Professor Kühne has kindly supplied the deficiency, and informs me that he was then speaking of slices taken from the external surface of the stomach, and therefore containing the lower ends only of the gastric glands.

[2] Liversedge (Nov. 1872), *Journ. of Anat. and Physiol.*, Nov. 1873, p. 23.

[3] Heidenhain, *Pflüger's Archiv*, Bd. xi. p. 557.

kinds of bacteria, for example, are generically or specifically different, or whether they can, by altered cultivation, be transformed into one another or not.

Koch, who has cultivated them by the dry process on gelatine instead of in liquid, and has thus been able to avoid admixture of different kinds of bacteria, has come to the conclusion that each kind possesses distinctive characters; but Klein has shown that, even when cultivated in this way, bacteria may vary much in form. Thus the bacillus anthracis may form torula-like cells, from which ordinary bacilli are again produced.

The numerous names used in treatises on the subject of organised ferments are apt to lead to confusion, hence some of the names are given here simply for the purpose of reference. Thus Brefeld's classification is:—

(1) Phycomycetes = algoid fungi; (2) Mycomycetes = true higher fungi; (3) Myxomycetes = gelatinous fungi; (4) Blastomycetes = yeast fungi; (5) Schizomycetes = bacteria.

The classification into yeasts, moulds, and bacteria which I have followed may not be botanically correct, but it is convenient for our present purpose.

Yeasts.—The yeast-plant, to which various names have been given, as torula cerevisiæ, saccharomyces, consists of ovoid cells, which multiply by budding. The buds may remain attached, forming torula-chains, but when they attain the size of the parent cell they fall off and begin to multiply anew. When placed in saccharine solutions the plant, during the process of growth, decomposes the sugar and forms alcohol and carbonic acid.

In this process oxygen is usually absorbed from the air in considerable quantities, but fermentation can occur in saccharine solutions even when oxygen is excluded, though under such conditions the torula grows slowly. When plenty of oxygen is present, and the layer of fluid shallow, the torula grows luxuriantly, but there is very little fermentative change; while, on the other hand, when free oxygen is excluded the torula grows slowly, but there is marked fermentation.

Another plant nearly allied to yeast is the mycoderma vini, the ferment which changes alcohol into acetic acid. The mycoderma is not regarded by Naegeli as a species distinct from torula, and it is considered by Grawitz to be the same as the fungus found in the aphthous patches which occur about the mouth and throat of children suffering from thrush, although this fungus is usually said to be an oïdium.

To test the action of drugs on alcoholic fermentation, equal quantities of a solution of grape sugar with yeast are introduced into two test-tubes, and to one of them a little of the substance to be tried is added. These are then inverted over mercury and kept in a warm place for several days. The amount of gas developed is then measured, and the power of the drug to prevent fermentation is estimated by the diminution in the amount of carbonic acid produced, as compared with the standard.

Mould Fungi, or **Hyphomycetes.**—These form long filaments or hyphæ, which become agglomerated into a mycelium or mass of compact tufts. They multiply not only by gemmation, but by the formation of spores.

These moulds vary considerably according to the soil in which they grow, and the amount of oxygen present. Thus, if the spores of the common white mould, *Mucor mucedo*, are sown in a liquid containing sugar and exposed to the air, they grow on the surface, forming branched hyphæ without septa, and the liquid absorbs oxygen. But if the mycelium be immersed, or the oxygen withdrawn, septa develop in the hyphæ, and they break up into segments which multiply by budding, forming a kind of yeast with large cells, and, like the true yeast, decomposing sugar into alcohol and carbonic acid.

They may be trained to thrive on substances on which they do not usually grow by gradually altering the composition of the soil. Thus, the commonest of all moulds, *Penicillium glaucum*, although it does not usually grow on blood, may be trained to do so by transplanting it from bread to peptone, and then to blood.

Heat destroys these fungi, but a much higher temperature is required to kill the spores than the perfect plant, and in order to destroy the spores a temperature of 110°–115° C., kept up for an hour, is requisite.

The mould-fungi cause some local diseases in the body, and especially skin diseases such as favus, tinea tonsurans, tinea versicolor, tinea sycosis, onychomycosis, and the madura-foot or fungus-foot of India. They also occur in the fur of the tongue.

Bacteria, or **Schizomycetes.**—Bacteria are every day becoming more and more important on account of the relation in which they are found to stand to various **diseases.** Anthrax, diphtheria, phthisis, and typhoid fever, are probably all due to various species of bacteria introduced into the body, and affecting various organs in it. It is, therefore, of the greatest possible importance that their life-history should be learned, and that we should know what the conditions are under which they thrive best, and what the conditions are which will destroy their life and prevent their development.

They appear to increase in two ways: first, by simple multiplication of their parts, and secondly, by forming spores.

Bacteria require water, organic matter, and salts, for their life. Some of them also require the presence of free oxygen; others do not; hence they have been divided by Pasteur into two classes: **aërobious** and **anaërobious.** To the anaërobious bacteria oxygen is not merely unnecessary but hurtful, and even the aërobious bacteria, although they require oxygen in a certain quantity, are injured or destroyed by it when it is in excess.



FIG. 15.

- **Blastomycetes, or Yeasts**
  - Torula,
  - or Saccharomyces (Fig. 15),
  - or Mycoderma.




FIG. 16.

- **Hyphomycetes, or Moulds**
  - Mucor.
  - Penicillium.
  - Oïdium.
  - Achorion.
  - Trichophyton.
  - Microsporon.




FIG. 17.

- **Schizomycetes, or Bacteria**
  - **Sphaerobacteria** (globular cells)
    - Micrococcus (1 (*a* & *b*) & 2, Fig. 16).
    - Sarcina (3).
  - **Microbacteria, or Bacteria proper** (small, rod-like cells)
    - Bacterium
      - Bacterium termo (4).
      - B. lineola (5).
  - **Desmobacteria, or Filobacteria** (larger rod-like or thread-like cells)
    - Bacillus (straight)
      - B. subtilis (6).
      - B. anthracis (7).
      - B. septicæmia.
      - B. malariæ (8).
      - B. tuberculosis (12).
      - B. lepræ.
    - Vibrio (wavy)
      - Vibrio serpens (9).
  - **Spirobacteria** (twisted or spiral cells)
    - Spirochæta (long, flexible, close-wound spirals)
      - Spirochæta. Obermeyeri (10).
    - Spirillum (short, stiff, open spirals)
      - S. volutans (11).

The soil which is most favourable to different classes of bacteria varies with each class. A **struggle for existence** goes on between bacteria and other organised ferments, and between different kinds of bacteria themselves, in the same way as amongst higher plants. Just as an abundant crop of one kind of higher plants will occupy a whole field and choke other plants, so that kind of bacterium which grows most readily in a particular soil will choke others and prevent them growing at the same time with itself. During their growth they alter the soil or substance in which they grow, either by exhausting the nutriment it affords, or by forming in it new substances which are injurious to themselves, and thus they gradually die out.

But the soil which is no longer suitable for one kind of bacterium then becomes suitable for another, and their spores, which may have lain without germinating during the time the first kind was growing, now begin to grow actively.

Thus, if a number of germs of different classes of fungi be added at the same time to a saccharine solution, the bacteria only will grow and set up lactic fermentation. If a small quantity of tartaric acid be now added (½ per cent.) the yeast alone will grow and alcoholic fermentation begins. If more tartaric acid be added (4–5 per cent.) the alcoholic fermentation stops, and mould begins to grow. In this process neither the bacteria nor the yeast are killed by the addition of tartaric acid, which, in different proportions, merely renders the liquid more favourable for the growth of the yeast and mould respectively, and enables them to flourish best, although the others are still present.

In fresh grape-juice many germs are present, but the composition of the liquid being more favourable to the growth of the yeast-plant than to other fungi, it alone grows. When it has converted the sugar into alcohol its growth stops, and bacteria may then multiply and convert the alcohol into acetic acid. This in turn checks the growth of the bacteria, and mould-fungi then find the soil favourable. In their growth they consume the lactic acid, and the liquid once more affords a favourable soil for bacteria, which may then grow and cause putrefaction.

The same struggle for existence occurs between the different species of bacteria themselves. Thus micrococci may be prevented from growing by micro-bacteria, and bacilli may be killed by bacterium termo when the supply of oxygen is insufficient for both.[1]

It is to be noted, however, that in the struggle for existence the formation of poisonous products by bacteria may be, and probably is, beneficial to them. No doubt these poisonous products check their own growth and finally destroy them; but

[1] Ziegler's *Pathological Anatomy*, translated and edited by MacAlister, p. 272. This work contains a very lucid and complete account of disease-germs.

in the struggle for existence between bacteria and living tissues these poisons may be beneficial to the bacteria by killing the tissues, and thus giving the bacteria a more ample supply of nutriment.

In investigating any problem it is always best to take the simplest case, and if we look at the struggle for existence between bacilli and an amœba, or white blood-corpuscle, we shall see that the formation of poisonous products by the bacteria may enable them to destroy the amœba or leucocyte instead of their being destroyed by it (Fig. 25, p. 87).

These **poisonous products** in fact may prepare the soil for bacteria, and this supposition is confirmed by the observations of Rossbach and Rosenberger. Rossbach found that when papain was injected into the vessels, micrococci developed in the blood with extraordinary rapidity, the ferment seeming to have altered the blood to such an extent that it became an exceptionally favourable soil for the micrococci. A similar result was observed by Rosenberger from the injection of sterilised septic blood. In this blood the bacteria themselves were destroyed, but the poisonous substances which they had formed were present, and these seemed to have a similar action to the papain.

The struggle for existence between the Organism and the Microbes which invade it.—This has been found by Metschnikoff to occur both in the blood and the tissues. In the daphne, or water-flea, where the tissues are transparent, he has been able to observe the spores of a kind of yeast passing from the intestinal canal into the body-cavity (Figs. 18, 19). As they pass through they are attacked by leucocytes—sometimes by one, sometimes by many. These leucocytes occasionally coalesce so as to form a plasmodium. When they are sufficiently powerful they digest and destroy the spores (Figs. 19, 20, and 21). Sometimes the spores may be left sufficiently long intact to germinate and give off buds, which become free in the body-cavity, and may also, like the parent spores, be attacked and digested by leucocytes.

When there are many spores they destroy the leucocytes instead of being destroyed by them (Fig. 25).

The connective-tissue cells also take up and destroy the microbes, and, from the property the cells possess of eating up the microbes, Metschnikoff names them phagocytes.[1] He finds that bacillus anthracis is eaten up in a similar way by white blood-corpuscles ;[2] and Fodor[3] has observed that various kinds of bacteria, viz. bacterium termo, bacillus subtilis, and bacterium megatherium, as well as the spores of the latter, disappear in four hours after they are injected into the blood of living rabbits;

[1] *Virchow's Archiv*, vol. xcvi., p. 177. [2] *Idem*, vol. xcvii., p. 502.
[3] *Arch. für Hygiene*, Bd. 34, p. 129.




FIG. 18.—A piece of the anterior part of the body of a Daphne, with a number of spores, some of which are still in the intestinal canal, others are penetrating the intestinal wall, and others are free in the abdominal cavity, where they are attacked by leucocytes.




FIG. 19.

1. A spore which has penetrated the intestinal wall and entered the abdominal cavity, where four leucocytes have surrounded its end. *m*, the muscular layer of the intestine ; *e*, epithelial layer ; *s*, the serous layer.
2. A spore surrounded by leucocytes from the abdominal cavity of a Daphne.
3. Confluent leucocytes enveloping a spore.
4. A spore, of which one end is being digested by a leucocyte.




FIG. 20.—Different stages of the changes undergone by spores through the action of phagocytes.




FIG. 21.—A germinating spore with leucocyte adherent to it.




FIG. 22.—A spore germinating and forming conidia, which drop off and become free in the abdominal cavity.




FIG. 23.—*a* and *b*, two stages in the process of a leucocyte eating up two conidia.



FIG. 24.—A leucocyte enclosing conidia.




FIG. 25.—A group of conidia which have caused the leucocytes surrounding a spore to dissolve, leaving only an empty vesicle and fine detritus.




FIG. 26.—A connective-tissue phagocyte, containing three fungi-cells.



FIG. 27.—Leucocyte of a frog from the neighbourhood of a piece of the lung of a mouse infected with anthrax about forty-two hours after the piece of lung had been placed under the skin of the frog's back. The leucocyte is in the act of eating up an anthrax bacillus.




FIG. 28.—The same leucocyte, a few minutes later, after it has completely enveloped the bacillus.

but if the animals are weak, or depressed by hunger or cold, they have much less power of destroying the foreign organisms, and so a longer time elapses before the bacteria disappear.

When only a small number of pathogenic bacteria, such as the bacillus anthracis, is injected into the blood at once, they are destroyed in the organism; but when they are in larger numbers, they have the best of the struggle, and the organism itself is destroyed. It is probable that bacteria are constantly entering the organisms of men and animals from the lungs and digestive canal, but unless they are excessive in number, and virulent in their nature, they are quickly destroyed.[1]

The **septic poisoning** which occurs from wounds is not due merely to bacteria entering the blood from them, but is due chiefly to the absorption of the poisons which the bacteria have formed in the wound. The dead or enfeebled tissues which occur in the wound afford a soil favourable to the growth of the bacteria, and for the formation of their deadly products. When these are absorbed they not only poison the tissues generally, but, by doing so, convert the whole body into a soil suitable for the growth and development of bacteria, as is shown by the fact that the tissues of animals killed by the injection of sepsin decompose very quickly, and swarm with bacteria shortly after death.

Action of Drugs on the Movements of Bacteria.

Mode of Experimenting.—In order to test the effect of a drug on the movements of bacteria already developed, a drop of the solution containing bacteria may be mixed, under the microscope, with a drop of the solution of a drug in the way already described at page 63, and the strength of solution necessary to destroy their movements estimated in the same manner.

In order to combine experiments on the movements, and on the reproduction, so as to ascertain whether the bacteria which have been rendered motionless by heat or drugs are really dead, or are only torpid, the covering-glass in the experiment just described is taken up with a pair of sterilised forceps, and dropped into some sterilised Cohn's solution (*vide* p. 72). It is then put along with the standard solution into a warm chamber, and left for a day or two. If the bacteria have been destroyed, it will remain clear like the standard solution, but if they have only become torpid, it will be more or less opalescent or milky.

In performing this experiment, great care must be taken that the solution of the drug has been sterilised by boiling; and that the covering-glass, glass slide, all the instruments, and indeed everything used in the experiments, have been also thoroughly sterilised by heating.

A **temperature** of 66° to 70° C. usually arrests the movements of bacteria, and if continued for an hour destroys adult organisms, though not the spores. A temperature of 100° C. usually destroys the spores as well, but this is not always the case.

If the bacteria are moist, this temperature generally kills them, but not if they happen to be dry, and a much higher tem-

[1] Fodor, op. cit. p. 147.

perature is then required. They may become dry, before being killed, by a little solution containing them having flowed or spurted into the higher part of the tube or flask, where the water evaporates and leaves them dry before the temperature has been sufficiently raised to destroy them.

The bacteria grown in different fluids are not all equally sensitive to drugs.

The most destructive substances to bacteria are corrosive sublimate, chlorine, bromine, and iodine. Quinine and the other cinchona alkaloids also destroy bacteria, their power diminishing in the following order :—quinine, quinidine, cinchonidine, and lastly cinchonine.

Bebeerine is nearly as powerful, and potassium picrate is even superior to quinine when used with Cohn's solution. When bacteria are cultivated in beef-tea instead of Cohn's solution, potassium picrate is less powerful.

Sulphocarbolates and strychnine have considerable power, though a good deal less than quinine; berberin and æsculin have hardly any power to destroy bacteria at all. Sodium hyposulphite has very little action; sodium sulphate has a destructive action, but is about ten times less strong than quinine.[1]

Action of Drugs on the Reproduction of Bacteria in general.

The spores of bacteria have an enormous power of resisting agents destructive to their vitality, very much greater than that of the fully-developed bacteria. Thus it happens that a quantity of an antiseptic, which is quite sufficient not only to prevent the spores of bacteria from developing so long as they remain in it, but to destroy fully-formed bacteria, will not destroy the vitality of the spores or hinder them from germinating as soon as they are removed from the influence of the antiseptic and transferred to a proper soil.

Yet the power to destroy the vitality of the spores completely is what is required in an antiseptic, for we wish to destroy the infectious material, and prevent it from causing disease, rather than to administer substances to an animal which will hinder the germs from developing in the blood after their introduction into it; although this may be desirable when infection has already taken place.

It is therefore necessary to test the effect of drugs in destroying the germs completely.

Method of Experimenting.—This is done by adding to a fluid, containing bacteria and their spores, varying quantities of an antiseptic, and allowing the mixture to stand for a longer or shorter time. A drop of this

[1] Buchanan Baxter, *Practitioner*, vol. i. pp. 343, 350.

fluid is then introduced by a sterilised platinum wire or glass pipette into some sterilised Cohn's fluid or beef-tea. This is watched, to see whether bacteria will develop in it or not. If they do develop, it is clear that the spores have not been killed by the admixture with the disinfectant in the original fluid; if they do not develop, then the disinfectant has been sufficiently powerful to destroy them.

The plan usually employed is to take a number of test-tubes, plug their orifices with cotton-wool, and destroy any germs that may be attached to them by thoroughly heating them to about 300° F. in a hot chamber, or in the flame of a Bunsen's lamp. They are then allowed to cool, and a small quantity of a liquid (about 5 cc.) in which bacteria readily grow is placed in each. This also must be previously thoroughly boiled, in order to destroy any germs which may be present in it. The **liquid** recommended by **Cohn** consists of ammonium tartrate one gramme, potassium phosphate and magnesium sulphate of each five grammes, calcium phosphate ·05 gramme, distilled water 100 cc. This is filtered and boiled before use. To the tubes the different agents to be tested are added, the solutions of each having been carefully sterilised by boiling, and the pipette used being superheated in each case before it is employed. If the drugs are added in solution, a similar quantity of boiled water must be added to the first tube, which is to serve as a standard. To each of them is then added a single drop of a liquid containing bacteria.

The mouths of the tubes are then stopped with the cotton-wool and placed for a few days in a warm chamber at about 40° C. The standard liquid will then be found to be opalescent or milky. The degree of the opalescence in the other tubes will be less according to the effect of the drug which has been added, in preventing the development of bacteria.

Where it has completely hindered the development, the solution will remain quite clear, and as its strength diminishes, the opalescence will become greater until it is equal to that of the standard.

In performing this experiment it is best to use one definite form of bacterium, instead of a mixture of several unknown kinds. This is referred to again in speaking of the experiments of Dr. Koch, who generally employs the micrococcus prodigiosus as an example of an organism easily acted upon, and the spores of bacillus anthracis, or of a bacillus found in earth, as examples of resistant organisms.

It is found by this mode of experiment that a smaller quantity of **poison** will prevent the development of bacteria than will destroy them after they are developed.

By experiments on the comparative action of different drugs on bacteria the results contained in the following table have been obtained by N. de la Croix, and these have been to a considerable extent confirmed by Koch.

It will be seen by looking at the table that the exact limit of the power of each drug to destroy bacteria is not determined, but that two concentrations of each antiseptic are given, one of which is sufficient to do it, and the other is insufficient. The disinfecting limit therefore lies between the two experiments. But the limit of disinfection is not an invariable one for each drug, as its power to destroy bacteria is modified not only by the concentration of the solution employed, but by the length of **time** during which it acts, and by the **temperature**.

	Prevent the development of bacteria taken from meat infusion.	Do not.	Prevent the reproduction of undeveloped bacteria.	Do not.	Kill developed bacteria.	Do not.	Prevent the reproduction of developed bacteria.	Do not.	Prevent development of spores in boiled meat infusion.	Do not.	Prevent reproduction of spores.	Do not.	Prevent development of spores in unboiled meat infusion.	Do not.	Prevent reproduction.	Do not.
Corrosive sublimate	1:25250	1:50250	1:10250	1:12750	1:5805	1:6500	1:1250	1:5250	1:10250	1:12750	1:6500	1:10250	1:7168	1:8358	1:2525	1:3358
Chlorine	1:30208	1:37649	1:4911	1:6824	1:22768	1:30208	1:431	1:460	1:28881	1:34589	1:1008	1:1027	1:15606	1:23182	1:1061	1:1364
Chlorinated lime	1:111135	1:13092	1:488	1:578	1:3720	1:4460	1:170	1:258	1:3148	1:4716	1:109	1:134	1:286	1:519	1:153	1:286
Sulphurous acid	1:5448	1:8515	1:135	1:223	1:2009	1:4985	1:190	1:273	1:8515	1:12649	1:325	1:422	1:12649	1:16782	1:135	1:223
Bromine	1:6308	1:7844	1:769	1:1912	1:2550	1:4050	1:336	1:550	1:13931	1:20875	1:493	1:603	1:5597	1:8375	1:875	1:1153
Sulphuric acid	1:5734	1:8020	1:205	1:306	1:2020	1:3353	1:116	1:205	1:5734	1:8020	1:306	1:420	1:3353	1:5734	1:72	1:116
Iodine	1:5020	1:6687	—	1:2010	1:1548	1:2010	1:410	1:510	1:10020	1:20020	1:510	1:724	1:2010	1:2867	5:843	1:919
Aluminium acetate	1:4268	1:5435	1:59	1:80	1:427	1:835	1:64	1:92	1:4268	1:4778	1:937	1:1244	1:6310	1:7535	1:478	1:584
Oil of mustard	1:3353	1:5734	1:220	1:306	1:591	1:820	1:28	1:40	1:3353	1:5734	1:77 ?	1:108 ?	1:3353	1:5734	1:40 ?	1:60 ?
Benzoic acid	1:2867	1:4020	1:50	1:77	1:410	1:510	1:121	1:210	1:2877	1:4020	1:50	1:77	1:1439	1:2010	1:77	1:121
Borosalicylate of sodium	1:2860	1:3777	1:303	1:394	1:72	1:110	1:30	1:50	1:1343	1:1694	1:35	1:50	1:2860	1:3777	1:35	1:50
Picric acid	1:2005	1:3041	1:706	1:841	1:1001	1:1433	1:150	1:200	1:2005	1:3041	1:200	1:300	1:2005	1:3041	1:100	1:117
Thymol	1:1340	1:2229	1:109	1:212	1:109	1:212	1:20	1:36	1:1340	1:2229	1:109	1:212	1:1340	1:2229	1:20	1:36
Salicylic acid	1:1003	1:1121	1:343	1:454	1:60	1:78	—	1:35	1:3003	1:6004	1:603	1:1003	1:1121	1:1677	1:343	1:450
Permanganate of potassium	1:1001	1:1433	1:100	1:150	1:150	1:200	1:150	1:200	1:2005	1:3041	1:101	1:150	1:300	1:403	1:35	1:50
Carbolic acid	1:669	1:1002	1:22	1:42	1:22	1:42	1:266	1:4	1:402	1:502	1:22	1:42	1:502	1:669	—	1:10
Chloroform	1:90	1:112	—	1:08	1:112	1:134	—	1:08	—	—	—	—	1:103	1:134	—	1:122
Borax	1:62	1:77	—	1:14	1:48	1:69	—	1:12	1:30	1:43	—	1:14	1:107	1:161	—	1:37
Alcohol	1:21	1:35	1:44	1:8	1:44	1:6	—	1:118	1:11	1:21	1:177	1:203	1:21	1:30	—	1:142
Eucalyptol	1:14	1:20	—	1:203	1:116	1:205	—	1:583	1:20	1:29	—	1:14	1:205	1:308	—	1:30
Chlorate of potassium	—	1:30	—	—	—	—	—	—	—	—	—	—	—	1:13	—	—

Action of Drugs on particular species of Bacilli.

In these experiments of De la Croix, however, the nature of the bacteria experimented on was not determined, and there might be a mixture of several sorts. Koch has therefore sought to ascertain the action of disinfectants upon definite forms of microzymes by cultivating them in pure crops before applying the disinfectant. Those which he has chiefly experimented on are the red micrococcus prodigiosus, the bacteria of blue pus, and the bacillus anthracis.

The first two do not form spores, and are easily destroyed by disinfectants. The bacillus anthracis forms spores, and was therefore employed to test the action of disinfectants upon them.

Mode of Experimenting on the Action of Drugs on Reproduction of Bacilli.—In order to avoid admixture with other species, Koch cultivated the first two on slices of potato, instead of in a solution. Upon one piece of potato the unaltered microzymes were sown (control specimen), and upon the others similar microzymes which had been exposed to the action of disinfectants. If the microzymes had been destroyed by the disinfectants, no result occurred, but if not, then a crop was obtained which, in comparison with the control specimen, was more or less abundant, according as the action of the disinfectant had been less or more complete.

For the cultivation of the anthrax bacillus, Koch used as a soil gelatine mixed with some other nutritive substance, usually meat infusion and peptone sterilised and spread upon a slip of purified glass, and exposed to such a heat as just to solidify it. Koch did not use his solidified blood-serum in these experiments. This could be placed under the microscope, and the growth of bacilli observed from day to day. Middle-sized test-tubes were then partially filled with the disinfecting solutions, and silk threads, steeped in a fluid containing bacilli and then dried, were placed in them; from time to time a thread was removed from the tubes by means of a previously heated platinum wire and placed on the slide, which was then subjected to microscopical observation. In this way it was easy to determine what strength of solution, and what time of exposure to its action, were required to destroy the spores.

The results of experiments made in this way with carbolic acid were very surprising. It was to be expected that carbolic acid would readily destroy the spores, but this was not the case. A 1 per cent. watery solution had almost no action upon them even after they had been exposed to it for 15 days; 2 per cent. slightly retarded their growth, but it did nothing more; 3 per cent. killed the spores in 7 days; 4 per cent. in 3 days; and 5 per cent. in 1 day.

This comparatively slight action of carbolic acid on spores and the long time that it requires to destroy them show that it cannot be relied upon as a universal disinfectant. But it has nevertheless great power in destroying microzymes which have not formed spores.

The fresh blood of an animal which has died from anthrax contains only bacilli and no spores. When it is mixed with its own bulk of a 1 per cent. solution of carbolic acid, it can very

soon afterwards be injected into an animal without producing any marked symptoms. A ½ per cent. solution will not do this, so that the limit lies between ·5 and ·25 per cent. of the mixture (*v.* p. 97).

The action of carbolic acid on other fully-developed microzymes, or on the spores, is almost the same as on the anthrax bacilli.

The following table gives the result of Koch's experiments with other substances, the figures indicating the number of days during which the spores had been submitted to the action of the antiseptic previous to cultivation. The black-faced figures indicate that the spores were destroyed, and their germination prevented by exposure to the disinfectant for that number of days; a * indicates that their vitality was diminished, and that the crop from them was scanty; a † indicates that their growth was retarded; *† that it was both scanty and retarded. The disinfectants are divided into three groups. The first contains the group of fluids; the second of solutions in water; and the third of solutions in alcohol, ether, or oil.

GROUP I.—FLUIDS.

Distilled water	7	15	20	35	90						
Alcohol (absolute)	1	3	5	10	12	20	30	40	50	65	110
Alcohol (1 to 1 of water)	1	3	20	30	40	50	65	110			
Alcohol (1 to 2 of water)	1	3	20	30	40	50	65	110			
Ether	1	5	8*	**30**							
Acetone	2	5*									
Glycerine	1	3	10	20	30	40	50	65	110		
Butyric acid	1	5									
French salad oil	5	30	90								
Bisulphide of carbon	1	5	10	20							
Chloroform	1	3	10	20	100						
Benzol	1	5	10	20							
Petroleum ether	1	5									
Turpentine oil	1*	**5**	**10**								

GROUP II.—SOLUTIONS IN WATER.

Chlorine water (freshly made)	**1**	**5**					
Bromine (2 p. c. in water)	**1**	**5**					
Iodine water (1 in 7,000)	**1**						
Hydrochloric acid (2 p. c. in water)	1	5	**10**				
Ammonia	1	5	10				
Ammonium chloride (5 p. c. in water)	1	5	10	25			
Common salt (saturated solution)	1	5	10	20			0
Calcium chloride (saturated solution)	1	5	20	40			
Barium chloride (5 p. c. in water)	5	10	45	100			
Ferric chloride (5 p. c. in water)	2†	**6**					
Potassium bromide (5 p. c. in water)	5	10	25				
Potassium iodide (5 p. c. in water)	5	10	25	80			
Corrosive sublimate (1 p. c. in water)	**1**	**2**					
Arsenic (1 p. c. in water)	1	6	**10**				
Lime water	5	10	15*†	20*†			
Chloride of lime (5 p. c. in water)	1†	2*†	**5**				
Sulphuric acid (1 p. c. in water)	1	3	10*	20*			
Zinc sulphate (5 p. c. in water)	1	5*	10*				
Copper sulphate (5 p. c. in water)	1	5*	10*				
Ferrous sulphate (5 p. c. in water)	2	6					
Sulphate of aluminium (5 p. c. in water)	1	5	12				

Alum (4 p. c. in water)	1	5	12		
Potassium chromate (5 p. c. in water)	1	2			
Potassium bichromate (5 p. c. in water)	1	2			
Chrome alum (5 p. c. in water)	1	2			
Chromic acid (1 p. c. in water)	1	2			
Potassium permanganate (5 p. c. in water)	1				
Do. do. (1 p. c. in water)	1	2			
Potassium chlorate (5 p. c. in water)	2	6			
Osmic acid (1 p. c. in water)	1				
Boracic acid (5 p. c. in water) not quite dissolved	1	2	6†	10†	
Borax (5 p. c. in water)	5	10	15		
Sulphuretted hydrogen water	1	5*			
Ammonium sulphide	1	2	5		
Oil of mustard with water	1	5	10*		
Formic acid (sp. gr. 1·120)	1	2	4	10	
Acetic acid (5 p. c. in water)	1	5			
Potassium acetate (saturated solution)	1	4	10		
Lead acetate (5 p. c. in water)	1	5	12		
Soft (potash) soap (2 p. c. in water)	1	5	12		
Lactic acid (5 p. c. in water)	1	2	5		
Tannin (5 p. c. in water)	1	5	10		
Trimethylamine (5 p. c. in water)	1	5	12		
Chloropicrin (5 p. c. in water)	1	2	6	12	
Benzoic acid (saturated solution in water	1	5	10	45	90
Benzoate of sodium (5 p. c. in water)	1	2	5	10	
Cinnamic acid (2 p. c. in water 60 and alcohol 40 parts)	1	3	5	10	
Indol (in excess in water)	1	5	10	25	80
Skatol (in excess in water)	1	5	10	25	80
Leucin (½ p. c. in water)	1	5	10		
Quinine (2 p. c. in water and 40 alcohol 60 parts)	1*†	5*†			
Quinine (1 p. c. in water with HCl)	1	5	10		

GROUP III.—SOLUTIONS IN ALCOHOL, OR ETHER, OR OIL.

Iodine (1 p. c. in alcohol)	1*	2*			
Valerianic acid (5 p. c. in ether)	1	5			
Palmitic acid (5 p. c. in ether)	1	5			
Stearic acid (5 p. c. in ether)	1	5			
Oleic acid (5 p. c. in ether)	1	5			
Xylol (5 p. c. in alcohol)	1	5	30	50	90
Thymol (5 p. c. in alcohol)	1	6	10	15	
Salicylic acid (5 p. c. in alcohol)	1	6	10	15	
Salicylic acid (2 p. c. in oil)	5	10	20	80	
Oleum animale (Dippel's oil, 5 p. c. in alcohol)	1	5	12		
Oleum menthæ piperitæ (5 p. c. in alcohol)	1	5	12		

From this table it appears that the ordinary method of separating between formed and unformed ferments by precipitation with alcohol and solution in glycerine cannot be relied upon as a trustworthy means of separating them, since neither alcohol nor glycerine destroys the activity of formed ferments.

It is remarkable that ether and turpentine oil, which are both ozone carriers, should have such a marked action in comparison with other fluids. This is in harmony with some recent observations of Paul Bert and Regnard, who found that oxygenated water in sufficient quantity destroys the bacteria of anthrax.

The spores of anthrax bacilli resist in an extraordinary way the action of certain substances which usually are fatal to life, as hydrochloric acid (2 per cent.), salicylic acid (1 per cent.), con-

entrated solutions of chloride of sodium, chloride of calcium, metallic solutions, borax, boric acid, chloride of potassium, benzoic acid, benzoate of sodium, cinnamic acid, and quinine.

Action of Drugs on the Development and Growth of Bacilli.—In order to test the action of disinfectants on the development and growth of bacteria, Koch put into a number of small watch-glasses, or rather crystallisation-glasses with flat bottoms, a few drops of blood-serum, or a solution of extract of meat and peptone, mixed with varying quantities of the disinfectant. Into each of these a silk thread, which had been dipped in the fluid containing bacteria and dried, was placed. In one glass serum alone, without any disinfectant, was placed, in order to ascertain, by comparison with the growth which takes place in it, how the disinfectant in the other glasses had interfered with the growth of the bacilli.

In experiments of this sort a difference was found between anthrax bacilli and other microzymes. A dilution of carbolic acid, 1 in 1,250 and 1 in 850, sufficed to prevent the growth of anthrax bacilli, while a strength of 1 in 500 was required to prevent the growth of others.

Other species are therefore more resistant than anthrax bacilli to the action of carbolic acid. The following table shows the strength of various disinfectants required to hinder or entirely prevent the development of anthrax bacilli:—

Solution	Hinders	Prevents
Iodine	1 to 5,000	—
Bromine	1 to 1,500	—
Chlorine	1 to 1,500	—
Osmic acid	1 to 1,500	—
Permanganate of potassium	1 to 3,000	—
Corrosive sublimate	1 to 1,000,000	1 to 300,000
Allyl alcohol	1 to 167,000	—
Oil of mustard	1 to 330,000	1 to 33,000
Thymol	1 to 80,000	—
Peppermint oil	1 to 33,000	—
Oil of turpentine	1 to 75,000	—
Oil of cloves	1 to 5,000	—
Arsenite of potassium	1 to 100,000	1 to 10,000
Chromic acid	1 to 10,000	1 to 5,000
Picric acid	1 to 10,000	—
Hydrocyanic acid	1 to 40,000	1 to 8,000

The following are about the same strength as carbolic acid:—

Fluid	Hinders	Prevents
Boric acid	1 to 1,250	1 to 800
Borax	1 to 2,000	1 to 700
Hydrochloric acid	1 to 2,500	1 to 1,700
Salicylic acid	1 to 3,300	1 to 1,500
Benzoic acid	1 to 2,000	—
Camphor	1 to 2,500	—
Eucalyptol	1 to 2,500	—
Soft soap	1 to 500	1 to 5,000
Quinine	1 to 830	1 to 625
Hydrate of chloral	1 to 1,000	—
Chlorate of potassium	1 to 250	—
Acetic acid	1 to 250	—
Benzoate of sodium	1 to 200	—
Alcohol	1 to 100	1 to 12·5
Acetone	1 to 50 No action	—
Chloride of sodium	1 to 64	—

Influence of the Solvent.—Although a 5 per cent. solution of carbolic acid in water has a well-marked destructive action on the spores, and a strong destructive action on fully-developed anthrax bacilli, a solution of the same strength in oil or alcohol has not the least disinfectant action. A similar influence with regard to iodine is observable in the previous tables.

Effect of the Fluid with which Disinfectants are mixed.—This is sometimes very marked, especially in the case of free iodine, bromine, or chlorine. These in watery solutions are powerful disinfectants, but when mixed with fluids which contain alkalies, e.g. blood-serum, they are converted into bromides, iodides, and chlorides, and their action is very greatly diminished. The action of corrosive sublimate, however, and of ethereal oils is not altered.

Influence of Temperature on the Action of Antiseptics.—The action of antiseptics is greatly increased by a high temperature. Spores of anthrax bacilli exposed to the vapour of carbolic acid at 15°–20° C. remain unchanged even after 45 days' exposure. When exposed to the vapour of carbolic acid at a temperature of 55° C. the case is very different. Half an hour's exposure does not seem to harm them at this temperature, but many are destroyed by an exposure of an hour and a half, and very few will stand 3 hours' exposure, so that probably an exposure of 5 or 6 hours would destroy the whole of them.

Alterations in Bacteria by Heat and Soil.—By careful cultivation through successive generations of a slip taken from a wild fruit-tree, the chemical processes of growth may be so modified in it that the fruit will lose its acrid character and become edible and pleasant. What is true of higher plants is true also of lower in this respect, and bacilli are much modified by the conditions under which they are cultivated; for example, Pasteur has found that the bacilli of anthrax develop and multiply in beef-tea best at 25°–40° C. Their development is retarded at lower or higher temperatures than these, and is completely arrested at 15° or 45° C. When cultivated at a temperature where development occurs with difficulty, such as 42°–43°, the bacilli no longer form resting spores, but only grow into long threads.

Fresh bacilli injected into an animal rapidly cause death from anthrax, but the longer they have been previously kept at this high temperature the more does their virulence decrease, and at the end of four or six weeks they die.

When some of the first crop of bacilli are put into fresh beef-tea, the second crop retains the degree of virulence of the first, and the third crop taken from the second, and again grown in fresh beef-tea, has exactly the same morbific power, and so on.

When the bacilli are cultivated at 35°, the microzymes not only multiply quickly, but they form spores of a definite degree of virulence, and these spores may be kept unaltered for years in

sealed tubes, whereas the threads of developed bacilli die when air is excluded.

When an animal is inoculated with anthrax bacilli whose virulence has been diminished by cultivation at a high temperature, they produce merely temporary illness instead of death. By the growth of these non-virulent bacteria in the body, its constitution appears to undergo some alteration, and virulent bacteria subsequently injected have a much less powerful action on it. If the first injection be made with bacteria having a very slight amount of virulence, the animal may still die if injected a second time with virulent bacteria, but if inoculated first with non-virulent bacteria and a second time with bacteria rather more powerful, a slight disturbance is produced by each inoculation, and a subsequent injection of virulent bacteria no longer causes death.

The changes which are produced by **inoculation** with modified anthrax or with vaccine matter in the blood and tissues, although probably very slight, are sufficient to confer on the organism **immunity** from further infection. This is usually permanent, although the immunity may diminish with the course of years, unless the advancing age of the animal in itself tends to lessen its liability to infection.

A similar immunity against infection with different bacilli is sometimes conferred by **age**. Thus young dogs are easily infected with anthrax, but old ones are not.

A difference of **species** also confers immunity. Thus rats and field-mice are not liable to infection with anthrax, while house-mice are highly so. Algerian sheep also resist infection with anthrax, while French sheep do not.

The experiments of Cash seem to show that it may be possible by the action of drugs to alter the blood and tissues in such a way as to render the animal proof against infection by pathogenic bacteria; for he has found that by the continued administration of minute doses of corrosive sublimate to animals he can render them capable of resisting the lethal effects of anthrax subsequently inoculated.[1] This is a direction in which further research is likely to yield interesting results.

Possible Identity of Different Forms of Bacteria.

It has already been mentioned that we are not quite certain whether all the species, genera, or even orders of bacteria are natural divisions, or whether the same organism under various conditions of nutrition and development may not present such different appearances as to be included in different orders and

[1] Cash: *Proceedings of the Physiological Society*, Dec. 12, 1885. *Journal of Physiology*, vol. vii.

under different names. Yet this is a matter of very great importance in regard to the causation of disease, for if it be true that organisms which are usually innocuous may undergo an opposite process to that which occurs in anthrax bacilli by cultivation, and may in certain conditions of soil be changed from innocuous into pathogenous forms, we can understand how diseases may appear to originate *de novo*.

It has been stated by Naegeli that bacteria may be so modified by cultivation as to form entirely different fermentative products. Thus he says that the bacterium which produces lactic acid fermentation in milk may be changed by cultivating it in extract of meat and sugar, so that it will no longer produce a lactic but an ammoniacal decomposition in milk. He considers also that innocuous may be transformed into virulent bacteria, and back again into an innocuous form, and Buchner thinks that he has succeeded in transforming the ordinary hay-bacillus (bacillus subtilis) into anthrax bacillus by cultivating it for a number of generations in Liebig's meat extract, peptone, and sugar. This observation is denied by Klein [1] and others, but observations which partly support Buchner and partly Klein have been made by F. Köhler,[2] who finds that while the ordinary hay-bacillus (bacillus subtilis) is not altered in its appearance by repeated cultivations, it acquires a progressive virulence which renders it so fatal to animals as to resemble the anthrax bacillus in its deadly properties.

H. C. Wood and Formad [3] have also come to the conclusion that the micrococci found in diphtheria resemble those on furred tongues in all respects excepting in their greater tendency to grow. When cultivated successively, they lose their contagious power and grow less readily. These authors, therefore, consider that circumstances outside the body are capable of converting the slower growing or common micrococcus into the rapidly growing micrococcus of diphtheria, which, when cultivated again, reverts to the common type.

Action of Bacteria and their Products on the Animal Body.—When bacteria are injected into the animal body, they produce **different effects** according to the original **nature** of the bacteria or bacilli, the conditions under which they have been cultivated, and the quantity introduced. There is probably another factor of no less importance, which, however, still requires to be investigated, viz. the **condition of the body** (p. 97) into which they are introduced. In considering the effect of an injection into the living body of a solution containing bacilli, we must be careful to distinguish between the effect of the bacilli themselves, after their introduction into the circulation, upon the

[1] Klein, *Quarterly Journ. of Microscopic Science*, Jan. 1883.
[2] *Inaugural Dissertation* (Göttingen), 1881.
[3] *National Board of Health Bulletin, Supplement* No. 17, Jan. 21, 1882.

tissues and organs of the body, and the effect of the substances which they have already formed in the solution before their injection.

We must distinguish between those two things in the same way as we would have to distinguish between the effects of the particles of the yeast-plant and the effects of the alcohol which it had formed, if we were to inject a solution in which yeast was growing into the veins of an animal. The yeast or the bacteria would have one effect upon the animal, the alcohol or the septic products of the bacteria would have another.

Solutions of putrid organic matter containing numerous bacteria cause high fever and often death.

The course of the fever depends on the specific nature of the bacteria, e.g. septic bacteria, anthrax bacilli, &c.

It is difficult at present to ascertain exactly how far all the following diseases are due to the presence of microbes or their products; but it has been found that micrococci cause erysipelas, acute necrosis, gonorrhœa, gonorrhœal ophthalmia, contagious ophthalmia, ophthalmia neonatorum, and are present in pyæmia, puerperal fever, ulcerative endocarditis, infective myositis, and contagious pneumonia. When malignant œdema or traumatic gangrene occur, bacilli are usually found. Micrococci are also supposed by some to be the cause of vaccinia and of diphtheritic inflammation. The bacillus anthracis produces anthrax; bacillus septicæmiæ, blood-poisoning; bacillus malariæ, ague and malarious diseases; bacillus tuberculosis, phthisis; bacillus lepræ, leprosy; and another bacillus is the cause of glanders. In relapsing fever the spirochæta Obermeyeri is found in the blood, and is probably the cause of the disease.

Alkaloids formed by Putrefaction. Ptomaïnes.—From decomposing organic matter substances can be separated which have all the characters of alkaloids.

The alkaloids produced by putrefaction are usually known by the name of **ptomaïnes.** It was at one time supposed that they were different in their chemical nature from the alkaloids which occur in plants, and they were supposed to have a much greater reducing power than the latter. It was therefore proposed to distinguish between ptomaïnes and other alkaloids by the addition of potassium ferricyanide: if the alkaloid changed this into ferrocyanide, so that a precipitate of prussian blue was obtained on the addition of ferric chloride, it was supposed to belong to the class of ptomaïnes; whereas non-reduction was supposed to show that it belonged to the vegetable alkaloids. It was soon found, however, that this test was not trustworthy, for such important alkaloids as morphine and veratrine produced reduction. Later researches, especially those of Brieger, have shown that some at least of the so-called ptomaïnes are identical with vegetable alkaloids.

We may indeed now regard alkaloids as products of albuminous decomposition, whether their albuminous precursor be contained in the cells of plants and altered during the process of growth, or whether the albuminous substances undergo decomposition from the presence of microbes, either outside or inside the animal body, or by the simple process of digestion by unorganised ferments such as pepsine.

The alkaloidal products formed by the putrefaction of albuminous substances, vary according to the stage of decay at which they are produced. At first the poisonous action of these products may be slight. As decomposition advances, the poisons become more virulent; but after a longer period they appear to become broken up and lose to a great extent their poisonous power.

Muscarine, which is the poisonous alkaloid of some mushrooms, has been made synthetically by Schmiedeberg and Harnack from choline; and Brieger has obtained from decomposing albuminous substances several well-defined chemical bodies—dimethylamine, trimethylamine, triethylamine, ethylenediamine, choline, neurine, neuridine, muscarine, gadinine, cadaverine, putrescine, saprine, and mydaleïne, as well as some substances to which he has given no name. Muscarine, neurine, and choline all have a similar action, their power diminishing in the order just mentioned, choline being much weaker than the other two. They all produce salivation, diarrhœa, vomiting, dyspnœa, paralysis, and death. Muscarine and neurine in frogs produce complete stoppage of the heart in diastole; in mammals they only weaken its action. Neurine, cadaverine, putrescine, and saprine have no marked physiological action; but one alkaloid which Brieger has isolated from human cadavers in an advanced stage of decomposition appears to affect the intestine, causing enormous peristalsis, continuous diarrhœa, lasting for days, and extreme weakness. Mydaleïne, obtained from a similar source, is interesting, inasmuch as it causes a rise of temperature; for frequently we find in cases of acute disease that the rise of temperature coincides with the constipation, and is removed by purgation, so that the question arises how far the rise of temperature in such cases may be due to the absorption of poison from the intestine. Mydaleïne causes dilatation of the pupil, enormous secretion of tears, saliva, and sweat, vomiting, diarrhœa, paralysis, convulsions, twitching, dyspnœa, coma, and death.

Sepsine, which was isolated by Bergmann and Schmiedeberg from putrefying yeast, causes vomiting, diarrhœa, and bloody stools; but Nicati and Rietsch [1] have produced choleraic symptoms in animals by cultivations of Koch's comma bacillus from which the organisms themselves had been removed; and somewhat

[1] *Compt. rend.*, xc. 928.

similar results were obtained several years ago by Lewis and Douglas Cunningham with cholera stools in which any organisms present had been destroyed by boiling.

The extract from putrefied maize has a tetanic and narcotic action, which appears to be due to two different substances. These are not present in the same proportion, so that sometimes the tetanising action, and at other times the narcotic action, is most marked.

Another alkaloid, resembling atropine in its action, has been separated by Sonnenschein and Zuelzer from decomposing animal matter; and this has also been found in the bodies of persons dying from typhus fever.

Another which resembles curare in its action has been separated by Guareschi and Mosso[1] from putrefying brain.

Another substance causing tetanic symptoms has also been obtained from animal matter.

Leucomaïnes.—Gautier, to whom much of our knowledge regarding alkaloids produced by albuminous decomposition is due, has given the name of leucomaïnes to alkaloids which are not produced by putrefaction due to bacteria, but are formed by the decomposition of albuminous matters in the normal processes of waste in the living animal tissues. Amongst these he reckons various substances formed in muscles and allied to xanthine and creatine.[2]

Brieger has shown that during the digestion of fibrin by pepsin an alkaloid has been formed, to which he gives the name of peptotoxin.

Absorption and Elimination of Ptomaïnes and Leucomaïnes.—It is probable that a considerable production of alkaloids takes place in the intestine, both when the digestive processes are normal and more especially when they are disordered; at the same time alkaloids are being formed in the muscles, and possibly also in other tissues. Were all the alkaloids to be retained in the body, poisoning would undoubtedly ensue, and Bouchard considers that the alkaloids formed in the intestine of a healthy man in twenty-four hours would be sufficient to kill him if they were all absorbed and excretion stopped. He finds that the poisonous activity of even healthy human fæces is very great, and a substance obtained from them by dialysis produced violent convulsions in rabbits. When the functions of the kidney are impaired, so that excretion is stopped, uræmia occurs, and Bouchard would give the name of stercoræmia to this condition, because he believes it to be due to alkaloids absorbed from the intestines. He also thinks that the nervous disturbance which occurs in cases of dyspepsia is due to poisoning by ptomaïnes. That

[1] *Les Ptomaïnes*, Turin, 1883.

[2] *Sur les alcaloïdes dérivés de la destruction bactérienne ou physiologique des tissus animaux.* Paris: G. Masson. 1886.

alkaloids are excreted by the urine has been shown by Bocci, who has found in the urine a substance having an action like that of curare.

Effect of Drugs on the Action of Bacteria in the Animal Body.

So long as bacteria are outside the body, we may use drugs of any strength we please to destroy them, but the case is quite different when they have once gained entrance and are no longer outside but inside the body, because then the nature of the drug and the amount we can employ is limited by its effect on the organism itself, and we cannot administer very large doses of antiseptics lest we should injure or kill the patient at the same time that we destroy the bacteria which are causing the disease. All that we can hope to do is to **turn the scale**, if possible, in favour of the organism in the struggle for existence between the cells which compose it and the bacteria which have invaded it (*vide* pp. 86 and 89).

Our hope of doing this rests on the fact that drugs which may be injurious both to the tissue and to the bacteria are **not** equally so to each. Thus excess of temperature is injurious to the organism, but it is also destructive to bacteria; and, as Fokker[1] has pointed out, the febrile reaction which occurs on the introduction of bacteria into the blood may be a means of destroying the microbes and preserving the animal. There is often a germ of truth in apparently foolish plans of treatment, and the old practice of treating scarlet fever, small-pox, and measles by warm drinks, hot rooms, and abundant clothing may have been a blind effort to aid the natural processes of cure, just as the irritating ointment of the Middle Ages seems to have been an attempt at antiseptic surgery. The extraordinary destructive power of corrosive sublimate, and the fact that it continues to act in blood-serum just as it does in distilled water, seem to indicate that it might be used to destroy bacilli in the body, especially as Schlesinger has found that it may be injected subcutaneously into rabbits and dogs daily for several months without doing them any harm, even in doses of 5 milligrammes, 1 cc. of a ½ per cent. solution. Koch's experiments on this point, by the administration of sublimate after inoculation with anthrax, led to a negative result, the animals inoculated with anthrax dying of the disease, notwithstanding the injection of the sublimate. On the other hand, Cash has succeeded in preventing death from anthrax by administering corrosive sublimate for some time previous to inoculation (p. 97).

The extraordinary effect of **allyl alcohol**, and the less power-

[1] International Medical Congress, 1881.

ful but still great action of **ethereal oils**, indicate, however, that we may look forward with hope to the discovery of some organic substances which may so hinder the development of bacteria in the body after their inoculation, as to allow of their gradual destruction in the organism, and prevent the sickness or death which they would otherwise have occasioned.

In relation to this, the observations of the late Dr. W. Farr in his Report are very interesting: 'Alcohol appears to arrest the action of zymotic diseases, as it prevents weak wines from fermenting; like camphor, alcohol preserves animal matter—this is not now disputed. But may it not do more? May it not prevent the infection of some kinds of zymotic disease?'

Experiments have shown that alcohol itself has but a slight power in destroying bacilli, but it is possible that even the slight traces of the ethers which are present in wine or spirits may have some beneficial action in cases of septic poisoning.

Antiseptics, Antizymotics, Disinfectants, Deodorizers.

These classes of remedies are often confounded together. It is well, however, to distinguish their meanings:—

Antizymotics are remedies which arrest fermentation.

It has already been mentioned (p. 73 *et seq.*) that fermentative processes may depend upon either enzymes or organised ferments, and that organised ferments may be subdivided into several classes, such as those consisting of yeast, innocuous bacteria, and pathogenic bacteria.

The class of antizymotics includes all substances which arrest fermentative processes due to these bodies. It contains two subclasses: antiseptics and disinfectants.

Antiseptics are remedies which arrest putrefaction. They do this by preventing the development, or completely destroying the bacilli on which septic decomposition depends.

Disinfectants are remedies which destroy the specific poisons of communicable diseases. Many of those poisons, perhaps all of them, belong to the class of microbes, and so disinfectants may be regarded as a sub-class of antizymotics.

Deodorizers or **deodorants** are remedies which destroy disagreeable smells. Such smells often accompany the decomposition of various organic substances, which septic organisms cause. These foul-smelling products may be injurious to health in themselves by acting as poisons; but they are not to be confounded with the bacteria which produce them. Moreover, the disagreeable nature of the smell is not always to be relied upon as an index of its poisonous nature. M. Gustav le Bon made some experiments with hashed meat and water, over which he put some small animals. As the meat decomposed, the liquid teemed with organisms, was very fatal when injected into an animal,

and emitted a very foul smell, which, however, did not seem to be very injurious. Afterwards the organisms present in the liquid died, and the foul smell became much less disagreeable; but the emanations from the liquid appeared to become much more poisonous, although the liquid itself, when injected into an animal, had no longer the same virulent power as at first.

Uses of Antiseptics.—Antiseptics are employed externally in order to destroy microbes before their entrance into the body, and are administered internally with a like object, or for the purpose of at least preventing the free development and multiplication of the microbes.

They are employed externally in **surgical operations**, with the object of destroying any organisms which might find a nidus in the wound, and there give rise to the formation of poisonous substances. Both these substances and the bacteria themselves will not only have an injurious local action in the wound, but by undergoing absorption may prove injurious or fatal to the organism as a whole. The antiseptic plan of treatment has been empirically practised in a limited manner for a very long period without its principle being recognised: for the well-known Friar's balsam has antiseptic properties. It is to Lister that we owe the introduction of such a mode of treatment, not based upon mere empiricism, but upon scientific knowledge. The reason why it had fallen into disuse probably was that some of the antiseptic substances used for dressing wounds in the Middle Ages were irritants as well as antiseptics. Those who employed them did not know the reason why they were beneficial, and supposed that their virtue was due to their irritating properties. The ointments were accordingly made more and more irritating: and thus more harm than good was done, until they were discarded by Ambrose Paré. The antiseptic most commonly employed is carbolic acid. Not only are all the instruments to be employed disinfected by a watery solution, but the operation itself is conducted under a spray of the dilute acid, so as to render innocuous any organisms which may be present in the air. The wound is then covered with an antiseptic dressing. Whenever this requires to be removed it must always be done under the spray. The reason of these great precautions is obvious: if any germs, however few, gain an entrance they will soon multiply and prove as deadly as a great number, the only difference being one of time.

The great danger which may arise from an exceedingly minute portion of septic matter renders great caution necessary on the part of those who might, by a little indiscretion, convey it from one to another. Thus a number of years ago a medical man was nearly driven mad by an epidemic of puerperal fever which he had in his practice: one patient dying after the other. In order to get rid of any infection, he burnt all his clothes and went away for three months. During his absence everything

went well. On his return the epidemic again broke out: on careful investigation he found the only thing he had forgotten to burn was his gloves, and these had acted as a reservoir of infection. The hands, imperfectly cleansed in the first instance, had conveyed the septic matter into the gloves, and there it remained, re-infecting the hands every time the gloves were put on. In the same way a thermometer may prove a cause of continual infection unless the thermometer be carefully washed, and, if necessary, disinfected, each time it is used and before it is put into the case. In a similar manner it has been found that gonorrhœal matter may remain in the vagina and infect several persons without the woman herself ever suffering. One of the best antiseptics for disinfection in such cases is permanganate of potassium. This may be used to wash out abscesses, if there is any fear of danger from absorption of carbolic acid; and also as a lotion for ulcers or wounds about the mouth, the urethra, or anus, where the carbolic acid might be too irritating; as is evident from Koch's experiment, however (*vide* p. 92), a solution of the strength ordinarily used—one per cent., i.e. four grains to the ounce—is not sufficient to destroy the septic organism, although one of five times the strength will do so.

Another way in which septic poisoning may be produced is by the introduction of a catheter into the bladder, where this cannot be completely emptied naturally on account either of paralysis, enlarged prostate, or stricture. So long as the contents of the bladder have not come in contact with any foreign matter they may remain in the bladder for some time without undergoing decomposition, but if a dirty catheter should be passed, and thus a few organisms introduced into the bladder, decomposition may set up in the urine and septic poisoning ensue. A solution of carbolic acid in oil is sometimes trusted to for the disinfection of catheters, but, as Koch's experiments (p. 96) show that such a solution has little or no antiseptic power, the catheters should be disinfected by a strong solution of carbolic acid in water, and afterwards oiled before their introduction.

The use of antiseptics **internally** is limited by the resistance of the organism itself, as already mentioned (p. 102). In the stomach antiseptics are used for the purpose of preventing decomposition, and by thus lessening the production of irritating products they diminish irritation of the stomach and arrest vomiting. Those which are chiefly employed for this purpose are creasote, carbolic acid, sulpho-carbolates, salicylic and sulphurous acids. In the intestine antiseptics are useful in arresting putrefaction, and thus preventing the harm caused locally to the intestine by the products of decomposition as well as the injury due to their subsequent reabsorption. They therefore tend to check diarrhœa and dysentery. It is probably to its antiseptic action

that corrosive sublimate owes its curative power in cases of infantile dysentery, and it is not improbable that the beneficial action of calomel is due to a similar action, for it has been found by Wassilieff greatly to retard the decomposition due to low organisms.

The beneficial action of mercurials in such cases may be partly due to their antiseptic power not being as greatly diminished by admixture with fæcal matters as that of other antiseptics. After absorption into the blood, antiseptics are chiefly employed in febrile conditions, in order, if possible, both to lessen the growth of the septic organism and to remove the danger to the individual which the fever itself would occasion. The principal antiseptics used for this purpose are alcohol, eucalyptol, quinine, salicin, salicylic acid, and salicylates. Carbolic acid and creasote can hardly be used, as their action on the organism is too poisonous, but hydroquinone, cresotinic acid, kairin, pyrocatechin, antipyrin, and resorcin are not markedly poisonous, and are antipyretic. They may thus be useful, and antipyrin is now largely employed (*vide* also Antipyretics). Eucalyptol has sometimes appeared to me to be more beneficial in cases of septic poisoning than quinine ; at any rate, I have seen patients recover under its use who had not been benefited by quinine.

Disinfectants.—These are generally employed in order to destroy the germs of disease in the excreta of a patient suffering from an infectious disease, or those germs which may be adhering to articles of clothing or to furniture or to the walls of a room in which the patient has been lying. Probably the most efficient and generally applicable to articles of clothing is heat. The heat employed is usually from 230° to 250° F., but as a general rule it should be as hot as the fabrics will bear without injury, and should be continued as long as is necessary to raise the central parts of the articles to be disinfected to the temperature of the chamber in which they are placed. As the presence of **moisture** aids the destructive action of heat upon septic organisms, superheated steam appears to be the best disinfectant under ordinary circumstances. The only disinfectant that seems to be really trustworthy for destroying septic organisms when it is simply washed over them is corrosive sublimate : even in a dilution of one to a thousand it appears to destroy microzymes and their spores by a single application for a few minutes.

Deodorizers.—Deodorizers are mainly strong oxidizing and deoxidizing substances, as chlorine and its oxides, sulphurous acid, nitrous acid, ozone, peroxide of hydrogen, permanganate of potassium. Charcoal, in addition to oxidizing, absorbs and condenses the foul-smelling gas. Those which are most commonly used as deodorizers for the air of rooms are chlorine or its oxides set free from chlorinated lime.

For removing smells from the hands, carbolic acid is to be

preferred to others, and for deodorizing fæcal matters, permanganate of potassium, carbolic acid, or charcoal. A mixture of eight or nine parts calcined dolomite (magnesia and lime) with one or two of peat or wood charcoal is not only an excellent deodorizer, but increases the value of the fæcal matters as manure.

Antiperiodics.

These are remedies which lessen the severity or prevent the return of attacks of certain diseases which tend to recur periodically.

The chief of these are :—

Cinchona bark and its alkaloids :—

Quinine.	Arsenic.
Cinchonine.	Salicylic acid.
Quinidine.	Salicylates.
Cinchonidine.	Salicin.

Bebeeru bark and its alkaloid :—

Bebeerine.	Eucalyptol.

Action.—The mode in which antiperiodics act is not at present definitely ascertained, nor indeed is the pathology of the diseases which they prevent. Remittent fever, however, has been shown to depend upon the presence of a spirillum in the blood, and there is considerable evidence for considering that malarious conditions are connected with the presence of a bacillus. The periodical return of the attacks in such diseases would appear, then, to be associated with the growth of successive crops of these protophytes, and the action of antiperiodics might be explained by supposing that they interfere with the development of these pathogenic organisms.

Uses.—Quinine and cinchona bark are often regarded as almost specific in the various affections due to malarious poisoning, i.e. intermittent fevers, periodic headaches, neuralgias, etc. In tropical remittent fever of malarious origin, quinine is also the best remedy we possess. It must be given in very large doses, however, and is less certainly curative than in intermittent fever. The other cinchona alkaloids have a similar action to quinine, but are not quite so powerful : they, as also quinine, may be used as prophylactics in order to prevent the recurrence of ague in persons travelling through or living in malarious districts as well as for the purpose of curing malarious conditions already present.

Arsenic is sometimes even more powerful than quinine, but as a rule it answers best in malarious conditions which are some-

times known as masked or latent malaria, and which manifest themselves in neuralgia and nervous or digestive disturbance rather than in well-marked ague fits.

Adjuncts.—Emetics and purgatives aid the action of antiperiodics, and sometimes, indeed, can replace them and cure ague without their aid. Antiperiodics rarely succeed if the functions of the liver are disturbed unless they are aided by emetics or purgatives, and especially by cholagogues.

CHAPTER IV.

ACTION OF DRUGS ON INVERTEBRATA.

The study of the action of drugs on invertebrata has not been carried out methodically to any great extent, but it offers a very promising field for investigation, and probably in the course of a few years may yield very valuable results.

Action of Drugs upon Medusæ.

This subject has been worked at, almost exclusively by Romanes [1] and Krukenberg.[2] At present it has little practical bearing, but it promises to be of great service by enabling us to understand better the action of drugs on contractile structures generally, and on the heart in particular.

In medusæ the swimming organ consists of a bell-shaped mass of contractile substance, within which the polyp hangs like the clapper. Around the margin of this bell are a number of ganglia connected with one another by nervous filaments, and forming a peripheral ring.




Fig. 29.—Medusa (Sarsia), natural size.

In the normal state of the animal, the bell alternately contracts and dilates rhythmically, so that the animal is propelled through the water.

When the marginal strip containing the ganglia is removed, the bell becomes entirely motionless. The bell thus resembles, as we shall see afterwards, the ventricle of the frog's heart, both in the relation of ganglia to it, and in its rhythmical movements. Oxygen accelerates, and carbonic acid slows and finally stops, the rhythmical movements.

When the bell, paralysed by the removal of the ganglia which supply its normal stimulus to motion, is momentarily stimulated by a single induction shock, it invariably responds by a single contraction.

---

[1] Romanes, *Phil. Trans.* vol. clxvi. part 1, and vol. clxvii. part 2, 1866 and 1867.
[2] Krukenberg, *Vergleichend. physiologische Studien*, Heidelberg, 1880.

When successive shocks are employed at regular intervals the effect of each increases until the maximum is reached (Fig. 30, cf. pp. 122 and 123).




FIG. 30.—Shows the increasing contractions of the tissue of the medusa when stimulated by repeated weak induction shocks of the same intensity. The first two shocks had no apparent effect, and the first feeble contraction seen in the figure was caused by the third shock. (From a paper by Romanes in *Phil. Trans.*)

But if an additional **constant stimulus** is supplied to it by the addition of acid to the water in which it is floating; by the passage of a constant or of an interrupted electrical current through it; or by alcohol or glycerine dropped upon its surface, it commences to beat regularly, rhythmically, and continuously. When rhythmical action is thus artificially induced in the paralysed bell, its rate is increased by raising the **temperature,** and reduced by cooling it. Temperatures below 20° or above 85° arrest the rhythm.

When the marginal strip containing the ganglia is cut off and left attached only at one point, a stimulus applied to its end travels along the strip and finally causes the bell to contract. The **stimuli** which pass along may be



FIG. 31.—Diagram of a medusa (tiaropsis), about one-third natural size, with a strip of contractile tissue cut from the bell, but left attached at one end.

of two kinds—they may occur separately or together. The first kind is a wave of contraction in the **contractile tissue** of the strip itself. If the stimulus is applied to a portion of the strip the contraction will pass along like a wave until it reaches the bell, which it excites to contraction. The second is a rudimentary form of **nervous** activity. This may occur along with the contraction wave, and when this is the case it is seen to pass along in front of the contractile wave. But it may also occur when no wave of contraction takes place. Its occurrence is rendered visible by the movements of the tentacles which fringe the strip and are much more sensitive than the contractile tissue of the strip itself. This wave of stimulation without contraction passing along the strip will cause the bell to contract on reaching it, provided there is a marginal ganglion in the bell, but not if the bell is paralysed. The wave of stimulation is more easily excited than that of contraction, so that it may occur from stimuli too weak to excite a wave of contraction. The passage of stimuli along the strip may be impeded or prevented altogether by compressing the strip, by making transverse incisions into it so as to narrow the band of tissue by which the wave is transmitted, or by injuring the tissue

by straining. Sometimes the contraction wave may be **blocked** by the injury before the stimulus wave, and sometimes the stimulus wave may be blocked before the contraction wave. When the block is only partial it frequently happens that two or three waves will pass along the strip up to the block without being able to cross it, but after a long time their effect appears to penetrate so that a wave at last crosses it.

As Gaskell has shown, a similar occurrence takes place in the frog's heart, and stimuli proceeding from the auricle to the ventricle may also be blocked by compression.

The influence of **poisons** can be studied either upon the bell containing the ganglia, or upon this marginal strip.

In healthy medusæ chloroform first arrests the spontaneous movements of the bell. When now irritated it answers by a single contraction, instead of by a series, to such stimulation.

After the bell has ceased to respond, nipping its margin causes the polyp to contract.

After stimulation of any part of the bell ceases to produce response in any part of the organism, the polyp will respond to stimuli directly applied to it. Nitrite of amyl also produces effects which in many respects are similar to those of chloroform. There are, however, certain exceptions; the first is that, before the spontaneous movements are abolished, the rhythm becomes quickened, and the strength of the pulsations is diminished. The movements also die out more gradually than under chloroform, and before they entirely cease they become localised to the muscular tissue close to the margin. When the dose is large, spasmodic contractions are produced which obliterate the gradual paralysing action of the drug.

Caffeine first causes an increase in the rate of pulsation, and diminishes its strength after a few seconds. This condition passes off, and the spontaneous movements become gradually abolished. They still remain for a long time sensitive to stimulation, and at first respond by *several* feeble contractions to each stimulus; afterwards by a single response; and afterwards they do not respond at all.

As medusæ paralysed by removal of the ganglia never respond to a single stimulus with more than a single contraction, the increased number of contractions which at first appear after the application of the stimulus, are probably due to increased reflex irritability.

Caffeine causes the tentacles and polypi to lose their tonus, and become relaxed, which is not the case with chloroform. Medusæ anæsthetised with chloroform when put into a solution of caffeine also lose their tonus, but their irritability is restored, though their spontaneity is not.

The effects of strychnine differ in different species of medusæ. In Sarsia it accelerates the rhythmical contractions which occur in groups separated by intervals of quiescence. This quiescence finally becomes continuous, and during it the animal does not respond to irritation of the tentacle, but does so to direct muscular stimulation.

Veratrine first increases the number and power of the contractions; afterwards it diminishes both.

Digitalin first quickens them, then renders them regular, causes persistent spasms, and produces death in strong systole.

Atropine causes first acceleration, then convulsions, then feeble contractions, and finally death in systole.

Nicotine causes violent and continuous spasm, with numerous minute rapid contractions superimposed upon it. These latter soon die away, leaving the bell in strong systole.

After spontaneous movements have disappeared, the bell no longer responds to stimulation of the tentacles, but responds to direct stimulation.

Alcohol first greatly increases the rapidity of the contractions, so much so that the bell has no time to expand properly between them, and they are in consequence feeble and gradually die out. The reflex stimulation shortly ceases to produce any effect, but muscular irritability is longer maintained.

Cyanide of potassium first quickens and then enfeebles the contractions; spontaneous movements rapidly cease, and the bell soon becomes irresponsive either to irritation of the tentacles, or to direct irritation. For a long time after it has become irresponsive, the nervous connections between the tentacles and polyp remain intact, as also do the nervous connections of these organs with all parts of the bell. The sensory organs are therefore not paralysed by this drug.

The effects of poisons on medusæ were localised by Romanes in two ways. One way was to divide the medusa almost into two halves, connected only by a narrow strip of tissue. These halves were plunged into two beakers filled with sea-water, pure in one and poisoned in the other. The connecting strip



FIG. 32.—Diagrammatic representation of the method of localising the action of poisons on medusæ. One vessel contains normal sea-water; another contains poisoned sea-water, which is shaded in order to distinguish it.

rested upon the edges of the beaker. When curare was employed as a poison in this way, it was found to have an action similar to that which it exerts on mammals: apparently paralysing the motor nerves, while it left the sensory nerves capable of action. Thus, on nipping the half of a medusa which was plunged in the curare solution, it remained absolutely motionless, while the other half at once responded by a peculiar contraction to the stimulus. Here, also, however, just as in mammals, the sensory fibres are also paralysed by a large dose, so that if much poison be used, irritation of the poisoned part will have no effect either upon it or upon the unpoisoned part. When experimenting in this way with strychnine, Krukenberg found that the excitability of the poisoned part was increased, so that when he touched the connecting strip lightly with a needle no effect was produced on the unpoisoned half, but the poisoned half responded by several energetic contractions. Veratrine had a similar action to that of curare, so that irritation of the poisoned half caused no movement in it, but caused movement in the unpoisoned half. The irritability of the contractile tissue is also diminished so that it no longer reacts so readily in the poisoned half to electrical stimuli.

Nicotine appears to paralyse the ganglionic structures and not the nerves.

It has already been mentioned that the rhythmical movements of medusæ depend upon the ganglia: when these are all cut off the movements cease, but if only one be left the movements continue. In the medusa divided into two halves, as already described, it is evident that if the ganglia are removed from one half, or one half rendered functionally inactive by poison, that half will still continue to contract, so long as it remains connected with the other half, but will cease to move when it is completely divided from the half which still contains ganglia. The effect of nicotine is such as one would expect if the poison paralyses the ganglia, for it is found that when one half of a medusa is steeped in water containing nicotine, both halves still continue to pulsate rhythmically; so soon as the connecting band of tissue is divided, the poisoned half at once ceases to move, while the other half continues to pulsate.

The second way in which Romanes localised the action of poisons on medusæ was by applying them to a strip of contractile tissue. He found that various poisons applied to the strip, or injected into it, caused a blockage of contractile waves, preceded by a progressive slowing of the rate of transmission along the poisoned part. Chloroform, ether, alcohol, morphine, strychnine, and curare, all have this effect.

General Results.—The most marked results of experiments on medusæ are, that the contractile tissue **contracts rhythmically** when stimulated by ganglia. It ceases to do so when the ganglia are removed and the contractile tissue left under ordinary conditions, but a constant stimulus, either chemical or electrical, applied to it after the removal of the ganglia, will cause it to beat rhythmically just as if the ganglia were present. This appears to show that the rhythmical contractile power is a function of the contractile tissue and not merely of the ganglia. Besides its power of contracting once on the application of a single stimulus, or rhythmically from continued stimulation, the contractile tissue also possesses the power to **conduct** stimuli. This is seen in the passage of the contraction wave along a strip of medusa which, on reaching the bell, causes it to contract. When two contraction waves travelling along the contractile strip in opposite directions meet one another they arrest each other. This mutual extinction may be regarded either as a process of **inhibition** or interference, or as a consequence of exhaustion of the tissue which possibly may be unable to contract twice with such a short interval between.

The power of the contractile tissue to transmit stimuli is diminished or destroyed by cutting it more or less completely across, by compression, by stretching, by very high or low temperatures, and by poisons such as chloroform, morphine, nitrite of amyl, caffeine, strychnine, curare, and indeed almost any foreign substance added to the water in which the strip is immersed.

There are, however, **two conducting channels**, along which stimuli may be transmitted; the first, already mentioned, is the **contractile tissue**; the second is the **nervous tissue**. The passage of stimuli along the second is rendered evident by the movements of the tentacles. These nervous or tentacular waves and the contractile waves may exist either together or separately. The nervous waves are excited by stimuli which are too weak to excite contraction waves, and it is to be particularly remarked that when this is the case they only travel at half the rate at which a contraction wave travels, although, when the stimulus is strong enough to excite a contraction wave also, both the nervous and the contractile wave travel at the same rate, the nervous one being a little ahead of the other. The passage of nervous stimuli may also be diminished or completely blocked by section or compression just as in the case of contraction waves.

The transmission of stimuli along nerves is also affected by poisons. It appears to be destroyed by anæsthetics, though more slowly than that of the contractile tissue. The ganglia may be paralysed, e.g. by nicotine, before the transmission of nervous stimuli from them is diminished. The contractile tissue alone may be paralysed.

Action of Drugs on Mollusca.

In the **lamellibranchiata,** instead of a chain of ganglia, as in the medusæ, we have three pairs of ganglia: cerebral at the mouth, pedal in the foot, and parietal-splanchnic supplying the bronchial apparatus and viscera. The heart has distinct chambers, but apparently consists of protoplasmic substance without distinct nerves or ganglia. The application to it of an interrupted current will arrest the rhythmical pulsation and cause stoppage in diastole.[1] This effect is prevented by atropine. Warmth up to 104° quickens the heart; when raised higher it destroys reflex movement in the animal, and afterwards arrests the heart also. Pure water without salts quickly paralyses the muscles and causes death in salt-water molluscs. Curare in small doses has no effect, large doses quicken, but do not abolish movement, and do not affect the heart. Strychnine somewhat stimulates movement, and may cause some local contractions, but never any general tetanus. Nicotine acts in a similar way, but in large doses appears to paralyse the muscles and cause death; it also appears to cause contraction of the vessels, so that the heart becomes more bulky and beats more quickly. Veratrine has a similar action. Digitalis has no action, excepting when applied to the heart directly, and then it renders the beats slower and sometimes stops them. Antiarine, like digitalis, has no general action, but stops the heart if applied to it directly. Muscarine generally causes muscular contractions in the body: first acceleration, quickly followed by retardation of the cardiac beats. Sulphocyanide of potassium diminishes reflex action, but has little effect on the excitability of the nerves. A small dose somewhat quickens the cardiac action; a large dose stops the heart in diastole, and if it is directly applied to the heart the stoppage is permanent.

Action of Drugs on Ascidians.

The heart in ascidians consists of a tube open at both ends, and which, by its contraction, drives the visceral fluid alternately towards the viscera and away from them. Its action does not seem to depend on the nervous ganglion lying between the oral and anal sac, or indeed upon nervous influence at all.

The application of an induced current causes it to beat for some time in one direction instead of alternately, but does not arrest its pulsations.[2] According to Krukenberg it is not affected either by atropine or muscarine. It is paralysed by veratrine, quinine, and strychnine: these poisons rendering the beats gradually weaker and more irregular. No evidences of tetanus are to be seen from the action of strychnine. The mode of action of the heart is affected by helleborin and nicotine: helleborin increases the number of the advisceral beats while nicotine diminishes them. Camphor and strychnine have possibly an action in this respect resembling helleborin.

Action of Drugs on Annulosa.

In annulosa the nervous system consists of ganglia in each segment united together by nervous bundles. These bundles in general appearance correspond with the gangliated cord of the sympathetic in higher animals. The spinal cord is absent: we might therefore expect that drugs which act specially on the spinal cord in vertebrates would not have the same

---

[1] M. Foster, Pflüger's *Archiv*, v. 191.

[2] Dew-Smith, *Proc. Roy. Soc.*, March 18, 1875, p. 336.

marked action on annelida, and this appears to be the case. It was found by Moseley that strychnine had no action on cockroaches;[1] and leeches, when placed in water containing strychnine, become elongated but do not exhibit signs of tetanus. Some years ago I noticed that ants sprinkled with insect-powder died in violent convulsions, and it occurred to me that possibly substances which excite movements of the intestine in the higher animals might have a somewhat convulsant action on invertebrates. I therefore tried the effect of oil of peppermint on leeches, and it produced in them violent excitement. This appears to be of a somewhat convulsant nature: the animal at first flying rapidly hither and thither through the water, and afterwards, when it becomes quiet and nearly exhausted, there is a constant rhythmical twitching movement in the body which appears to last nearly until death. But if my idea had been correct, all carminatives should excite convulsions in annulosa. This is not the case, for the oils of peppermint, caraway, and anise have no apparent effect on black-beetles other than that of making them sluggish.

Chloroform, ether, and other substances belonging to the alcohol group, act as anæsthetics on mammals, temporarily abolishing the functional activity of the brain, spinal cord, and medulla. On annulosa they have a similar action, although Krukenberg[2] supposed they had a different effect, coagulating the muscular substance and rendering it stiff and hard before affecting the nerves. The experiment by which he thought this was




FIG. 33.—Krukenberg's apparatus for investigating the action of chloroform, &c., on annulosa. *a* is a shallow vessel containing a little water. *b* is a beaker containing water, saturated with chloroform, or ether, and covered with a piece of millboard *c*, in which are two holes. Through these holes the head and tail of a leech, *d*, are drawn and fastened by ligatures held by two clamps. *e* is a bell-jar covering the whole.

proved consisted in applying chloroform to the middle part of a leech while the two ends of the animal were protected from the action of the vapour. The middle part then became stiff and rigid, but the movements of the two ends of the animal were perfectly co-ordinated, so that its actions were that of a single animal having a stiff girdle surrounding its middle. Ether and alcohol had a similar result. The co-ordination of the two ends showed that although the muscles had been rendered rigid by chloroform, the nerves which passed through the middle part of the body were still functionally active. When the middle part of the body was coagulated by the application of hot water, the muscles became rigid but the nerves were also destroyed, and the movements of the two ends of the animal were no longer co-ordinated, so that they appeared like two distinct animals connected by a rigid cylinder. Luchsinger[3] repeated Krukenberg's experiments, and found that although the muscles were affected by the chloroform, yet the nervous system was still more sensitive than the muscles.

[1] Moseley, unpublished experiment made in C. Ludwig's laboratory.
[2] Krukenberg, *Vergleichend. physiologische Studien*, Abtg. I., p. 77.
[3] Luchsinger *und* Guillebeau, *Pflüger's Archiv*, xxviii., p. 61.

Atropine has a similar action to chloroform, ether, and alcohol, on the muscles of the leech. Veratrine appears to some extent to affect the muscles, so that after contraction they relax slowly. It appears also, however, to affect the nerve-centres, and, according to Krukenberg, paralyses more especially the sensory centres. Camphor, strychnine, morphine, caffeine, copper sulphate, and mercuric chloride act chiefly on the nervous system of leeches, although they also affect the muscles when applied for a length of time. Caffeine renders the muscles in the leech also rigid.

CHAPTER V.

ACTION OF DRUGS ON MUSCLE.

Action of Drugs on Voluntary Muscle.

In the bodies of animals we find the protoplasmic masses or cells of which they are composed variously modified, in order to perform special functions.

In some the power of nutrition is chiefly developed: and this we find in glands. In others the power of contractility is developed: and this we find in muscles, striated and non-striated.

In the course of special development towards the fulfilment of a particular function, the protoplasm of the muscular cells undergoes marked changes. But it must always be borne in mind that the protoplasmic elements of the body, however different from one another, always tend more or less to retain all the functions which are seen in an organism consisting of a single cell, a reference to which may sometimes throw much light upon the mode of life of the more highly organised tissues.

In amœbæ or leucocytes the protoplasm contracts in any direction and when strongly contracted in tetanus they become spherical.

In muscle the protoplasm is specially modified and contracts chiefly in one direction, viz. that of its length, and, indeed, it is usually assumed that muscular fibre, either voluntary or involuntary, contracts in the direction of its length only.

But the probability of its contraction in a transverse direction also is to be borne in mind, and there are some phenomena which it is very hard to explain except on the *supposition that muscle contracts transversely as well as longitudinally*.[1]

We distinguish in muscle its **elasticity**, a physical property; and its **contractility**, a vital property.

[1] Thus Weber found that when a muscle is loaded with a weight too great for it to lift, instead of shortening, it elongates. The usual explanation of this is that the elasticity of the muscle then becomes diminished; but according to Wundt the elasticity is not changed. If we suppose that stimulation tends to make the muscle contract transversely as well as longitudinally, the explanation is easy, for in this case, longitudinal contraction being prevented, the transverse contraction tends to elongate the muscle.

The word elasticity is applied to the tendency of the body both to resist change of its form, and to regain it when this change has been effected: so that ivory may be taken as the type of a very strongly elastic body. Indiarubber, on the other hand, is regarded as a feebly elastic body, because it does not strongly resist changes of form, although it tends very strongly to regain its original form after such changes. It is, however, popularly regarded as the perfect type of an elastic body. In talking of the elasticity of muscle, confusion is apt to occur; it is better, then, to avoid the term elasticity and to use the words suggested by Marey—extensibility and retractility. The **extensibility** of muscle is of two kinds—immediate and supplementary. When a weight is attached to it, it extends considerably; this is its immediate extensibility; it then goes on slowly and gradually lengthening for a considerable time, and this is supplementary extensibility. When the weight is removed the retractile power of the muscle again becomes evident, and there is immediate **retractility** and supplementary retractility, the muscle at once contracting to a considerable extent, and then continuing to do so slowly and gradually for some time afterwards.

The extensibility of a muscle is increased by stimulation, so that if a weight be hung on a muscle while it is contracted in consequence of stimulation, it will produce a greater extension than it would if applied to the same muscle in a state of rest; and if a muscle be loaded with a weight too great for it to raise, stimulation, instead of causing contraction, causes elongation.[1] Heat renders the muscle less extensible and more retractile; cold has an opposite effect, rendering it more extensible and less




FIG. 34.—Shows the action on muscle of caustic soda, 1 in 2,500, once renewed in 25 minutes, followed by the action of lactic acid, 1 in 500, once renewed in 25 minutes. (Brunton and Cash.)




FIG. 35.—Shows the action on muscle of caustic potash, 1 in 2,500, twice renewed for 13 minutes, succeeded by the action of lactic acid, 1 in 500, for 18 minutes, and this by the action of caustic potash for 17·5 minutes. (Cf. Fig. 50, p. 132.) (Brunton and Cash.)

retractile. Section of the nerve has a similar effect to that of cold. Fatigue increases the extensibility. Alkalis (potash or

[1] *Vide* footnote, p. 117.

soda), in very dilute solutions, diminish extensibility; dilute acids (lactic acid) increase it. By the alternate application of




FIG. 36.—Shows the action of caustic potash, 1 in 1,500, on muscle for 18 minutes, succeeded by the action of lactic acid for 24 minutes. 1 is the contraction of normal muscle; 2, 3, 4, contractions of alkali-muscle; 5, 6, 7, contractions of acid-muscle on stimulation. (Brunton and Cash.)

alkalis and acids the muscle may be made to yield curves which, when recorded on a very slowly-revolving cylinder, are similar in form to the normal contraction curve recorded on a rapidly-revolving cylinder.[1] Fig. 34.

Irritability of Muscle.—In order to ascertain the irritability of muscle itself or the readiness with which it responds to various stimuli independently of the nerves within it, the muscle is first poisoned by curare, and then exposed to various conditions, or to the action of drugs. The muscle thus poisoned by curare, woorara, woorali, or urari (for the poison has all these names), is much less sensitive to the action of faradaic currents. The readiest way of testing its excitability is by the making and breaking of a constant current, the strength of which can be estimated very exactly by using du Bois Reymond's rheochord. The excitability of muscles is **increased** by heat and **diminished** by cold. It is increased by physostigmine and diminished by most poisons which paralyse muscle.[2]

Contraction.—When the ends of the muscle are not kept apart by force too great for it to overcome, and it is stimulated by heat, mechanical injury, chemical irritants, or electricity, it contracts and then relaxes.

The form of this contraction varies according to the species of animal, and the particular muscle tested.

In cold-blooded animals, as a rule, the contraction is slower than in warm-blooded animals. It is not alike in all the muscles of the body of mammals. Thus in the rabbit there are two kinds of muscles—red and white; the white muscles contract more quickly and relax more quickly than the red ones. The muscle usually employed in experiments is the gastrocnemius of the frog, freshly prepared, with the nerve and end of the femur attached to it.

---

[1] Brunton and Cash, *Phil. Trans.*, 1884, p. 197.
[2] Harnack and Witkowski, *Arch. f. exp. Path. u. Pharm.* v. 1876, p. 402.

The femur is fixed in a clamp, and the lower end of the muscle is attached to a writing lever usually loaded with a weight (Fig. 37). The end of this lever writes upon a revolving




FIG. 37.—Apparatus for registering muscular contraction. It consists of an upright stand on which two horizontal bars may be moved by a rack and pinion. The upper bar ends in a clamp, the lower carries a delicate lever, the part near the hinge being of metal, and the part beyond of light wood tipped with quill or tinfoil. *a*, *a*, wires for exciting muscle; *b*, muscle; *c*, writing lever. In the figure no arrangement is shown for exciting the nerve, and for the sake of simplicity the weight is shown directly under the muscle. In actual experiment, however, the weight should be applied close to the axle, or on it, so as to lessen oscillation due to the inertia of the lever.

cylinder (Fig. 38), which is made to rotate with greater or less rapidity. The rate of revolution is usually ascertained by marking the time upon it by means of an electro-magnet (Fig. 39) communicating with a clock or metronome, or, when the revolution is quick, with a large tuning-fork vibrating 100 times or more per second. When the cylinder is not in motion each contraction of the lever makes a straight line upon it (Figs. 40 *a* and 46); when the cylinder is moving, the lever describes a curve which is more or less elongated, according to the rapidity of the cylinder's rotation (Figs. 40 and 41).

Latent Period of the Muscle.—The mechanical energy developed by muscle during its contraction is derived from chemical energy liberated by changes in the constituents of the muscle itself. These are of the nature of oxidation, and during them oxygen is used up, and carbonic acid is liberated. But the oxygen is not necessarily present either around the muscle, or in the blood circulating through the muscle; it is stored up in some loose form of combination within the muscle.[1]

[1] It would appear that this force-yielding substance, or muscle-dynamite, as we may call it, is not present, at least in large quantity, in the muscles in a form in which it can be at once fired off. There appears rather to exist a substance yielding it, or dynamogen, which may be looked upon as corresponding to the zymogen of the glands, while the muscle-dynamite may be regarded as corresponding to the ferments of glands. Irritation of a nerve appears both to liberate muscle-dynamite

The form in which it is stored up has been compared by Ludwig to gunpowder, a small quantity of which is fired off at each contraction.

One of the final products is carbonic acid; but there are intermediate products, one of them being sarcolactic acid; and these products tend to cause muscular fatigue.




FIG. 38.—Revolving cylinder for recording movements. The screws at the top are for fixing the cylinder in position. The brass pin is for making or breaking a current at a given time in the revolution. It does this by striking against a small key. The curve is described by the lever, Fig. 37. The abscissa, or zero line, is drawn by a fixed point, and serves to show the height of the contraction.

When they are washed out of the muscle by a current of blood, or of simple saline solution, the fatigue of the muscle is removed; and this removal is effected even more perfectly when the internal oxidation is rendered more complete by adding permanganate of potassium to the solution, or by the addition of minute quantities of potash. A mere trace of veratrine has also a similar effect in restoring the muscle after fatigue.

---

and to explode it, if we may so term it. The passage of a constant current through the muscle appears to liberate the muscle-dynamite from the dynamogen, but causes no expulsion except at the moment when the current is made or broken, or its strength altered. It must be carefully borne in mind that the idea of a muscle-dynamogen is at present simply theoretical, and must be looked upon not as a fact but rather as a means of remembering facts. According to A. Schmidt, however, the contraction and relaxation of muscle is closely connected with the formation and destruction of a ferment.

We find that the muscle does not immediately respond to a stimulus, but that a period elapses between the stimulus and the commencement of the contraction, which is on the average about the 100th of a second. This is termed the **latent period.**

During this period a chemical change is probably going on in the muscle, and it is evidenced by an electrical change known as the negative variation, or diminution in the natural current which passes from the longitudinal to the transverse section of the muscle.

The latent period is altered by fatigue. Loading the muscle shortens the latent period, until the load is just sufficient to extend the muscle. An increase of load above this, lengthens the latent period. Cold lengthens it; heat shortens it. Small doses of strychnine or veratrine shorten the latent period. Large doses of strychnine or veratrine, and also curare, lengthen it.

Summation of Stimuli.—During the latent period, the stimulus applied to a muscle excites chemical changes which result in contraction; but if the stimulus be very small, the




FIG. 39.—Electro-magnet (after Marey) for recording time on a cylinder. When used to record time, the current is made and broken alternately by clockwork or by a tuning-fork. It may be used also to record the time of irritating or dividing a nerve, or of injecting a poison, &c.

chemical changes may be so slight that contraction does not occur. If the stimulus, however, be repeated several times, the changes which it induces in the muscle become sufficient to produce at first a slight contraction, and then one greater and greater, until the maximum effect is produced—this is called **summation.** It occurs not only in voluntary muscles, but in other contractile tissues, such as those of the medusa (*vide* Fig. 30, p. 110). A similar phenomenon occurs also in the heart, and has there received the name of 'the staircase.'

Contraction of Muscle.—In the muscular curve we notice (1) the rapidity of its rise, which indicates the rapidity of contraction of the muscle; (2) its length, indicating the duration of contraction; (3) its height, indicating power of contraction; and (4) slowness of fall, indicating the condition of extensibility.

The muscular contraction is modified by numerous conditions.

One of these is the **strength of stimulus.**

The stimulus usually applied is electricity, as its strength can be more easily regulated, and it does not destroy the muscle so readily as mechanical or chemical irritants.

With a weak current, making (closing) has no action on the muscle, but breaking (opening) causes contraction.




FIG. 40.—Muscle curves, showing the different appearances they present according to the rate at which the recording cylinder revolves. *a* is a curve with a very slowly revolving cylinder; *b*, *c*, and *d* are curves with increasing speed of rotation. *c* is written with a lever pointing in the opposite direction from that with which *a* and *b* are recorded, and the curve therefore inclines to the other side.

A moderate current gives contraction both in making and breaking, but that of making is comparatively small (Fig. 41). With a strong current no difference is observed.



FIG. 41.—Shows effect of making and breaking shocks. These are normal muscle curves with a still quicker rotating cylinder than in Fig. 40*d*. The first is caused by irritating the muscle by making (closing) a constant current, and the second by breaking (opening) it.

The more intense the stimulus, the higher and longer is the curve. The increase in height is shown in Fig. 42.




FIG. 42.—Tracing of the contractions of a muscle with stimuli of varying strength. The numbers indicate the distance in centimetres of the secondary from the primary coil in the induction apparatus. *As* and *Des* indicate the ascending and descending direction of the current.

Cold renders contraction slower, lower, and more prolonged (Fig. 43 *b*).

Heat renders it quicker, higher, and shorter (Fig. 43 *a*).

Fatigue.—Fatigue makes the ascent slow, the height less, and the descent slow (Fig. 44).

Exhaustion of the animal has a similar action; and dilute acids applied to the muscle produce the same effect (Fig. 36).

The effect of fatigue is probably due in a considerable measure to the accumulation of acid products of muscular waste.




FIG. 43.—Effect of heat and cold. In *a* the muscle has been artificially warmed, and in *b* it has been cooled.

When these are washed out by passing a weak solution of chloride of sodium through the vessels of the muscle, or partially removed by kneading, it regains to a great extent its normal power of contraction.




FIG. 44.—Effect of fatigue.

Oxidising agents, such as permanganate of potassium, added to the salt solution, increase its power, and restore the muscle even more quickly and completely.[1]

Deprivation of blood has a similar action on the muscle to fatigue; and free circulation of blood tends to remove the effects of fatigue.

Contracture.—When the stimulation is exceedingly strong, the relaxation after contraction may become very slow, and the descent of the curve may be divided into two parts. At first it descends for a short time pretty quickly, and then falls very slowly indeed. This long contraction of the muscle is known as **contracture.** It is very strongly marked in muscles poisoned by veratrine or barium. It occurs, though to a less extent, in muscles poisoned by salts of calcium and strontium, by ammonia, and by the chloride, iodide, nitrite, nitrate, and cyanide of ammonium.[2]

The cause of contracture is not known; it is considered not to be a tetanic contraction, because unlike an ordinary tetanised muscle it does not give rise to secondary tetanus in another frog's muscle, when the nerve of the latter is placed upon it. It is, however, an active contraction, not a mere alteration in the elasticity of the muscle preventing its relaxation; for, as Fick and Boehm have shown, a much greater amount of heat is

[1] Kronecker, Ludwig's *Arbeiten*, 1871, p. 183.
[2] Brunton and Cash, *Proc. Roy. Soc.*, 1883.

developed during the long-continued contracture than in an ordinary contraction. Sometimes, and indeed not unfrequently, the contracture, instead of consisting of a single prolonged contraction, appears in the form of a prolonged contraction added on to an ordinary contraction before relaxation has had time to occur. This gives rise to a peculiar hump in the curve, as is well seen in the middle curve in Fig. 49. This appears to show that the contracture is really a double phenomenon, like the two contractions observed after a single stimulation in the muscle of




FIG. 45.—Secondary contraction in the muscle of a crayfish. The thick part of the lower line shows the time during which the muscle was irritated by a tetanising current. It will be noticed that the secondary contraction occurs after the irritation has ceased, and after the tetanus caused by it has relaxed. It is not a simple continuous rise, but exhibits several waves indicative of a kind of rhythm. (After Richet.)

the crayfish by Richet (Fig. 45). How far the contracture may depend upon irritation of the muscle by its own current has yet to be determined.

Tetanus.—If instead of a single stimulation a number of stimuli rapidly succeeding each other are applied either directly to the muscle itself or to its motor nerve, we get, in place of a single contraction, a continued contraction or tetanus. As this is due to a fresh contraction of the muscle occurring before the previous one has had time to relax, it is evident that the number of stimuli requisite to produce this will vary with the length of each single contraction in a muscle. Thus in the muscles of the tortoise, which contract and relax very slowly, tetanus may be produced by 3 stimuli per second, while in the white muscles of rabbits 20 may be necessary, and in some muscles of birds 70 stimuli per second are insufficient. It has been said that with as rapid stimuli as 250 per second the tetanus ceases, and after a single initial contraction a muscle goes to rest just as if a constant instead of an interrupted current had been used. Kronecker and Stirling have shown that, with no less than 22,000 interruptions per second, tetanus is still obtained; but when such extremely rapid stimuli are applied, the muscle still contracts about the ordinary rate of 20 per second; and this is also the

case when chemical stimuli are applied to the nerve, or when the muscle is irritated by the nerve-centres, either voluntarily or by artificial stimuli applied to them. It seems therefore probable that the number of contractions of the muscles in tetanus are not due to the number of stimuli sent down from the nerve centres, but that the rate is determined either by the ends of the nerve in the muscle or by the muscle itself.[1]

The form of a tetanus curve may be modified very considerably by the action of drugs: thus substances which diminish the contractile power of muscle cause the tetanus curve to fall very rapidly notwithstanding the continued application of stimuli either to the muscle itself or to its nerve (*vide* Ammonia).

Muscular Poisons.—We may distinguish several groups of muscular poisons, but at present the classification is difficult, and the division into six groups based on that of Kobert, which I have adopted, although it possesses some advantages, is far from satisfactory, and can only be regarded as temporary.

GROUP I.—Leaves the irritability of the muscle unaffected, but diminishes the total amount of work it is able to do.

GROUP II.—Diminishes the excitability of the muscle as well as its capacity for work.

GROUP III.—Diminishes the capacity for work, and produces marked irregularity in its excitability.

GROUP IV.—Alters the form of the muscular curve.

GROUP V.—Increases the excitability.

GROUP VI.—Increases the capacity for work.




FIG. 46.—Tracings showing the gradual loss of contractile power from fatigue in a normal muscle, *a*, and in one poisoned by carbolic acid, *b*. Each section, 0'—1', &c., shows the contractions in one minute. (After Gies.)

The poisons in Group I. do not alter the muscle curve, so that if the action of the poison were tested by a single contraction only, it would be supposed that the muscle was unaffected; they lessen, however, the amount of work which the muscle can yield.

The amount of work is estimated by the weight which a muscle raises multiplied into the number of times it is lifted and the height it is raised each time. These are ascertained by

[1] Wedenskii, *Archiv f. Anat. u. Physiol.* Phys. Abthlg. 1883, p. 325.

registering the contractions on a slowly revolving drum, as in Fig. 46, which shows the rapid exhaustion of a muscle poisoned by carbolic acid as compared with a normal one. The rapid exhaustion of muscles may also be observed in the form of the tetanus curve which, under the influence of such poisons, falls much more rapidly in height than that of the normal muscle.

This group contains a number of drugs having an emetic action.[1] These are: apomorphine, asclepiadine, cyclamine, delphinine, sanguinarine, and saponine, copper, zinc, and cadmium. Antimony has a somewhat similar action, but only in large doses, and after a great length of time. Arsenic, platinum, and probably mercury, act in the same way as antimony.[2] Tin, nickel,[3] cobalt,[3] manganese,[2] aluminium, and magnesium, have little or no action on muscle. Large doses of iron are nearly as powerful as arsenic, but in small doses it rather increases the amount of work the muscle can do.

Carbonic oxide at the atmospheric pressure does not affect muscular contractility, but abolishes it at a pressure of five atmospheres.

Perhaps we may take as a subdivision of this group those poisons which lessen the contractile power of the muscle without




FIG. 47.—(After Harnack.) Shows the action of lead on muscle. *a* shows the contraction of a normal muscle after eighty stimulations; *b*, the irregular contractions of a muscle poisoned by lead after ten to fifty stimulations; *c* shows the slow relaxation of the muscle after contraction in a muscle poisoned by lead after numerous stimulations.

altering its irritability. When a muscle poisoned by one of these is stimulated, it may contract quite as readily as a normal muscle, provided the weight that it has to raise is but slight, but it cannot raise such a heavy weight as a normal muscle. This is tested by loading it with a given weight, and the slightest contraction is ascertained by adjusting the lever of the myograph in such a way that if raised in the very least it breaks a connection in an electrical current and causes a bell to ring. By this means contractions quite imperceptible to the eye are readily appreciated. Digitalis has an action of this sort, as I found in some experiments carried on under the direction of Professor J. Rosenthal in 1868, but not published.

Group II. contains salts of potassium, lithium, ammonium,

[1] Harnack, *Archiv f. exp. Path. u. Pharm.*, Bd. ii. p. 299, and iii. p. 44.
[2] Kobert, *Arch. f. exp. Path. u. Pharm.*, Bd. xv. p. 22, and xvi. p. 361.
[3] Anderson Stuart, *Journ. of Anat. and Physiol.*, vol. xvii. p. 89.

quinine, cinchonine, oil of mace, alcohol in large doses, chloroform, &c.

Chloral, chloroform, and ether also belong to this group, but they might also be reckoned as belonging to Group IV., for they slow the ascent, lessen the height, and prolong the descent of the curve. Curare has a similar action.

It is usually stated that curare, while it paralyses motor nerves, leaves the excitability of the muscles unaffected, but this appears not to be quite correct, for, when very weak currents are employed, the muscle loses its excitability by them before the nerve, and the contractions of the muscle at the same time become unequal. It is perhaps not yet perfectly certain how far these appearances are due to the curare, and how far to the gradual death of the muscle.[1]

Group III. contains poisons of which lead is a typical example. These poisons cause the muscular contractions to become very unequal, although the stimuli are equal and regular. Emetine and cocaine have a similar action to lead. This action is probably due only to the gradual death of the muscle. It is produced also by ptomaïnes, and it may occur in muscles which are simply dying without being poisoned at all.[2]

Group IV. contains poisons which alter the form of the curve to a marked extent.

The action of veratrine is very peculiar: it does not lessen the rapidity of contraction, and even increases the height of the curve, but it prolongs the descent to an enormous extent.




FIG. 48.—Tracing of the contraction curve of a muscle poisoned by veratrine, showing enormous prolongation of the contraction, the recording cylinder making many complete revolutions before the muscle is completely relaxed.

This action of veratrine is most marked at moderate temperatures.

It is much diminished, and sometimes entirely removed, by cold; and it disappears also when the temperature of the muscle is considerably raised. When the muscle which has been cooled or heated is again brought back to a moderate temperature, the contracture sometimes returns, but occasionally does not, the

[1] Marey, *Travaux du Laboratoire*, 1878, p. 157.
[2] Mosso, *Les Ptomaïnes*, Turin, 1883.

effect of veratrine on the muscle appearing to be sometimes, but by no means always, destroyed by the heat or cold to which the muscle has been exposed.[1]

The result of this exceedingly prolonged contraction is that a frog poisoned with veratrine is able to jump with considerable power, but the extensor muscles, by which the movement is executed, remain contracted instead of relaxing. The animal therefore lies extended and stiff, and is only able very slowly to draw its legs up towards the body. After they have been drawn up, the flexors in their turn remain contracted for a while, and so the animal is unable to jump until some time further has elapsed.

Another remarkable point about the action of veratrine on muscle is, that although a single contraction lasts so long as seriously to interfere with the power of co-ordinated movement, yet, if the muscle is made to contract a few times in rapid succession, the effect of the veratrine disappears, and it again acts normally. After a short rest the effect of veratrine again reappears.

A similar action to that of veratrine is exerted by salts of barium, which, when locally applied, cause the muscle to describe




FIG. 49.—Tracing of the contraction curves of a muscle poisoned by veratrine, showing the peculiarly elongated curve at a moderate temperature, and its restoration nearly to the normal by cooling and heating.

a curve resembling that of veratrine, not only in its form, but in the alterations produced by temperature and in its temporary disappearance after repeated contractions. A similar action is exerted also, though to a less extent, by strontium and calcium. Salts of potassium may at first increase the height of contraction, but afterwards both moderate and large doses

[1] Brunton and Cash, *Journ. of Physiol.*, vol. iv. p. 1, and *Centralblatt f. d. med. Wiss.*, 1883, No. 6.

shorten the muscular curve, and lessen its height, so as finally to abolish its contractile power altogether. When applied to a muscle poisoned by veratrine, barium, strontium, or calcium, salts of potassium remove the excessive prolongation of the contraction which these drugs occasion, and restore the muscular curve again to its normal.[1]

Although veratrine alters the form of the muscular curve so greatly, it does not (excepting in large doses) paralyse the muscle, so that when a poisoned muscle is made to contract at regular intervals for a length of time, it is able to do as much work as a normal one.

Nearly allied to this is another group of muscular poisons, some of which have already been mentioned as a sub-division of Group I. It contains: digitalin, digitalein, digitaleresin, digitoxin, toxiresin, scillain, helleborein, oleandrin, adonidin, neriodorin, and neriodorein. Tanghinia, thevetin, and frynin, or toad poison, probably also belong to this class.

These drugs do not lessen the irritability of muscle, but appear to alter somewhat the form of the muscle curve, somewhat in the same way, but to a less extent than substances of the veratrine group. Some of them when applied in a concentrated form directly to the muscle cause a condition of rigor. This is especially the case with caffeine and digitalin. This rigor is well marked in the *rana temporaria*, and only to a comparatively slight extent in the *rana esculenta*. Although caffeine in concentrated solution produces *rigor mortis* in the muscle, yet in very dilute solutions it is a muscular stimulant, and as such is included in the sixth group.

Group V. contains physostigmine, which increases the excitability of muscle to slight stimuli, but does not increase the amount of work it can do; on the contrary, in large doses it diminishes it.

Group VI.—Poisons belonging to this group in small doses increase muscular work, and cause the muscle to recover rapidly after exhaustion. Creatin has this power to a great extent; hypoxanthin has it also, though less powerfully. The effect of these substances is very interesting, because they are products of muscular waste. They also occur in beef-tea, and their action appears to show that beef-tea assists muscular power, as well as acts as a nervous stimulant.

Other members of this group are caffeine and glycogen: these have great power to increase muscular work. The relation of caffeine to hypoxanthin is very interesting. Xanthin, which is another substance derived from muscles, differs from hypoxanthin in containing one atom more oxygen. Theobromine, the active principle of cocoa, is dimethylxanthine; and caffeine, the

[1] Brunton and Cash, *Proc. Roy. Soc.*, 1883.

active principle of tea and coffee, is trimethylxanthine. The restorative effects of beef-tea, coffee, tea, and cocoa have long been recognised empirically, although their action could not be explained. It now seems not at all improbable that it may be partly due to their restorative effect on the muscle.

Massage.—The effect of kneading a muscle so as to remove the waste products from it is very extraordinary.

When the muscles of an uninjured frog are stimulated to contraction by the rhythmic application of maximal induction currents until they are exhausted and no longer contract, kneading them, or massage, restores their contractility so that their contractions are nearly as powerful as at first, while simple rest without massage has very little restorative effect. In man also, while a rest of fifteen minutes after exhausting labour had very little restorative action, massage during the same period increased double the work that could be done. Massage has a similar action to very complete and perfect circulation through the muscle, in removing the waste products and restoring its power.[1]

Propagation of the Contraction Wave in Muscle.—When a muscle is irritated at one point, the contraction wave which occurs at that point is conducted along the muscle in both directions.

This contraction wave, like that which occurs in the contractile tissue of the medusa, is independent of the nervous system. The completeness with which it is conducted, and the quickness with which it subsides at each point, are closely connected with the rapidity of the conduction, and they are also injuriously affected by anything which impairs it. It diminishes during the death of the muscle, and it is lessened also by fatigue, by cold, and by injury, such as excessive stimulation. Certain poisons also lessen it, as cyanide of potassium, veratrine, and upas antiar.[2]

Heat increases the rapidity of the conduction.

Rhythmical Contraction of Muscle.—Rhythmical contraction is frequently regarded as a function of involuntary muscular fibre only; this, however, is not the case, for it is observed also in voluntary muscles. Rhythmical contraction of involuntary muscle is seen in the trachea,[3] and is well marked in the heart and blood-vessels. It is very distinct in the intestines and bladder, and becomes still more marked after the influence of the central nervous system has been destroyed. In the case of the sphincter ani, for example, the rhythm is strong and regular, especially after the nerves have

[1] Zabludowski, *Central. f. d. med. Wiss.*, 1883, No. 14, p. 241.

[2] Aeby, *Untersuchungen über die Fortpflanzungsgeschwindigkeit der Reizungen der quergestreiften Muskelfaser.* Braunschweig, 1862, p. 52.

[3] Horwath, *Pflüger's Archiv*, 1875, vol. xiii. p. 508.

been divided and the muscle subjected to some mechanical distension by the introduction of the finger.

In voluntary muscle the tendency to large rhythmical pulsations is slight, although we see rapid contractions occurring in tetanus.

The number of impulses sent down to the muscles along the motor nerves, from the spinal cord, is about 10 per second in the dog. If more numerous impulses are sent down from the cerebral cortex, or corona radiata, or if more numerous stimuli are applied to the spinal cord itself, summation appears to occur in the cells of the spinal cord, and only 10 impulses per second are sent out.[1]

From the observations of Wedenskii, that irritation of the motor nerve of a muscle by exceedingly rapid stimuli still produces the same number of contractions in the muscle, it seems probable that this rate of contraction is due to the constitution




FIG. 50.—Tracing of the contraction curve of a muscle poisoned by veratrine and exposed to a high temperature. The poison tends to cause prolonged contraction, and the high temperature to cause rapid relaxation of the muscle. The result is a somewhat rhythmical spontaneous contraction. The muscle was only irritated at the very beginning of the first contraction.

either of the muscle itself, or of the nerve-endings within it. Under certain circumstances, however, the voluntary muscle may be made to contract with a slow rhythmical movement of considerable extent, and closely resembling that of involuntary muscular fibre.

Thus voluntary muscle treated by veratrine tends to remain contracted for a length of time like an involuntary muscle: heat has a tendency to cause its relaxation, and sometimes, as is seen in the accompanying figure (Fig. 50), these contending influences produce in the voluntary muscle a tendency to marked rhythmical contraction.

A still more remarkable phenomenon has been noticed by Kühne,[2] who finds that when the uninjured sartorius of a frog is placed in a solution of 5 grammes NaCl, and 2·5 grammes of common alkaline crystallised phosphate of sodium in a litre of

[1] Horsley and Schäfer, *Proc. Roy. Soc.*, vol. xxxix. p. 406.

[2] *Untersuchungen aus dem Physiologischen Institute der Universität Heidelberg.* Sonderabdruck, 1879, p. 16.

water, it begins to contract at once, and after it has been transversely divided it beats with the regularity of the heart.

The effect of various substances on the rhythmic action of muscle treated in this way has been investigated by Biedermann. He finds that the best fluid for the sartorius is 5 grammes NaCl, 2–2·5 grammes of Na_2HPO_4, ·04–·05 gramme of Na_2CO_3. A low temperature, not rising above 10° C., is best. The lower the temperature the slower is the rhythm and the more extensive the contraction. Heat quickens the rhythm and lessens the contraction. At about 18° to 20° C. the contractions become rapid and indistinct. When caustic soda is used instead of carbonate, the effect is similar, but the muscle dies much more quickly. Potassium carbonate and other potassium salts only cause pulsations when greatly diluted. Lactic acid stops the pulsations; alkaline NaCl solution again restores them. Veratrine and digitalin in a solution of NaCl also cause pulsations.[1]

Schönlein finds that, with a certain strength of current interrupted about 880 times in a second, the muscles of the water beetle are not tetanised, but contract rhythmically from two to six times in a second.[2]

Biedermann has succeeded in making a voluntary muscle, such as the sartorius, contract rhythmically by applying a solution of sodium bicarbonate (2 per cent.) to the tibial end, and then passing a constant ascending current through the muscle.[3]

Pathology of Tremor.

Rapid alternation of contraction and relaxation, or tremor, may be observed to affect either—(*a*) a few bundles of muscular fibres, (*b*) a single muscle, or (*c*) groups of muscles.

The tremors affecting a few bundles of fibres, or fibrillary twitchings, may occur in excised muscles, and are probably due to some conditions of the muscular fibre allied to those which have already been considered (p. 132). They may occur also in muscles which still remain in the living animal after the nerve has been cut, more especially in the muscles of the tongue after section of the hypoglossal nerve, or in the muscles of the face after section of the facial nerve.[4]

Tremors affecting groups of muscles occur, in some cases, when the limbs are at rest, and cease during voluntary movement, as in paralysis agitans; or may cease entirely when the limb is at rest, and only come on when the muscles are put in

[1] *Sitzungsber. d. Wiener Akad.*, Abth. lxxxii. p. 257–275.
[2] Schönlein, du Bois Reymond's *Archiv*, 1882, p. 357.
[3] *Sitzungsber. d. Wien. Akad.*, Bd. lxxxvii., Abt. iii., March 1883.
[4] They may possibly be regarded as due to disturbance of the normal relations between longitudinal and transverse contraction in muscular substance.

action, as in disseminated sclerosis and in mercurial tremor. As already mentioned, a certain number of motor impulses per second are required to keep a muscle steadily contracted.

It is evident that, if the stimuli proceeding to the muscles from the nerve-centre should be too few, tremor, and not steady contraction, of the muscle will occur. And the same will be the case if any change in the muscle itself should render the duration of each single contraction less than usual.

But in all co-ordinated movements a number of muscles, the actions of which are antagonistic to each other, are brought into play; and it is by the proper adjustment of these antagonistic actions that the performance of delicate movements becomes possible. Unless the amount of contraction of each of these muscles is exactly graduated, there will be a tendency to oscillatory movement. As the amount of contraction in each muscle, or group of muscles, is regulated by the stimuli sent down to it from the nerve-centres, it is evident that if the motor cells supplying one group of muscles be affected more than those which supply the antagonistic or regulating muscles, inco-ordination, and possibly tremor, will occur. The pathology of tremor is still, however, very obscure.

Treatment of Tremor.—If tremor should depend upon insufficient rapidity of the stimuli passing to the muscles from the nerve-centres, it is evident that any drug which, like veratrine, will increase the duration of each individual contraction, is likely to be of use. Acting upon this idea, Dr. Ferris has used veratrine in cases of tremor due to alcoholism, disseminated sclerosis, and weakness after typhoid fever. Although this treatment was successful in all these diseases, it does not seem quite certain that the utility of the medicine may not be partially due to its action on the spinal cord as well as on the muscles themselves. In one case of tremor, occurring at the commencement of general paralysis, I have given salts of calcium with the same object with the apparent result of arresting the tremor. I had intended to use barium, but the tremor ceasing for many months with calcium, I have not proceeded to use anything else.

Connection between Chemical Constitution and Physiological Action on Muscle.

I have already mentioned (p. 29) that one can hardly look for a general relation between the atomic weights of metals and their lethal activity, so that what we want is really a knowledge of the particular relationship of each group of elements to the organs and tissues of the body.

In such an investigation it seems natural to take the muscles first, then the motor nerves, afterwards the nerve-centres and individual organs. A number of experiments have been made by

Cash and myself in order to do this for the alkalis and alkaline earths, and we have found that the contractile power of muscle, as shown by the height of the curve, is increased by rubidium, ammonium, potassium, and cæsium. It is slightly increased or unaffected by sodium, excepting in large doses, and is almost invariably diminished by lithium.

The duration of contraction, as shown by the length of the curve, is increased by rubidium in large doses, ammonium, sodium, and cæsium. It is shortened by ammonium, lithium, rubidium in small doses, and by potassium.

The contracture, or viscosity, is increased by rubidium in large doses, ammonium, lithium, and sodium. It is diminished by rubidium in small doses, ammonium, cæsium, and potassium.


Both ammonium and rubidium have two actions on muscle of an opposite character, sometimes increasing and sometimes diminishing both the duration of the contraction and of the contracture, or viscosity, which remains after the ordinary contraction has ceased. In the case of rubidium this appears to depend upon the dose, but we were not satisfied that it was so entirely in the case of ammonium salts.

In regard to the action of the alkaline-earths and earths, we found that the contractile power of muscle is increased by barium, erbium, and lanthanum. It is sometimes increased and sometimes diminished by yttrium and calcium. It is diminished by didymium, strontium, and beryllium.

The duration of contraction is increased by barium, calcium, strontium, yttrium, and erbium. It is unaffected, or slightly diminished, by beryllium, didymium, and lanthanum.

Contracture is increased by barium, calcium, strontium, yttrium, and beryllium.

The contracture produced by barium is enormous, resembling that produced by veratrine. It is, like that of veratrine, diminished by heat, cold, and potash, and may be abolished by these



agents. It is by no means so well marked when the drug is injected into the circulation as when locally applied to the muscle.

The action of some of the more important of those drugs can

be graphically represented by a spiral, the terminal members of which are potassium and barium, and these two are, to a certain extent, connected by ammonium as an intermediate link.

The effect of one member of one of these groups may be diminished or increased by the subsequent application of another. Potassium shortens the elongated curves caused by barium, calcium, sodium in large doses, and lithium, and reduces the contracture which these substances cause. The veratrine-like curve of barium is counteracted by almost all the substances which produce a shorter curve than itself.

Action of Drugs on Muscle is Relative and not Absolute.

In considering the action of drugs on muscle, the first point which comes clearly out is that the action of a drug on the muscle is not absolute, but merely relative. Thus veratrine and salts of barium are not to be regarded as absolute muscle-poisons—they are only poisons under certain conditions of quantity and of temperature. An exceedingly small dose of veratrine, instead of acting as a poison to muscle, acts rather as a food, and restores it when exhausted. Caffeine likewise in small doses has a restorative action, while in large doses it is a powerful poison. Veratrine and barium in moderate doses and at moderate temperatures are powerful muscular poisons, but at low temperatures and at high temperatures their action is to a great extent, or even completely, abolished. Nay more, moderate quantities of barium salts at moderate temperatures are poisonous to the normal muscle, but they are restorative to the muscle whose composition and functions have been already altered by rubidium. Acids and alkalis also produce an effect on muscle, but their effect depends upon whether they are applied to the normal muscle or to one previously treated with a substance having an opposite reaction.

It is evident, then, that the whole question of the action of drugs on muscle is one involving the relation of the drug to the muscle at the time of application, and we must expect that if the temperature is different from the normal, or if the composition of the muscle should vary, the action of the drug will vary likewise. Now the composition of all the muscles in the body is not the same, as has been shown by Toldt and Nowak,[1] and the composition of the ash obtained by the combustion of different animals is also different, as has been shown by Lawes and Gilbert.[2] We may therefore expect that muscular poisons will not act alike at the normal temperature and in febrile conditions, nor alike upon all the muscles of an animal; nor will they

[1] Quoted by Seegen, *Wien. Akad. Ber.* lxiii. Abt. ii., 11-43.
[2] *Proc. Roy. Soc.*, xxxv., p. 344.

always have the same action upon different animals—the relations being different, the effects will be different. The effect of poisons upon muscles will also vary according to the chemical composition of the tissue at the time. This composition may probably, to a certain extent, be altered by feeding—at least as far as regards the proportions of inorganic ingredients. We know that the quantity of sodium chloride in the body can be increased, for if an animal be fed with a larger quantity of salt than usual, it does not at once begin to excrete, but stores it up for two or three days, and then the excretion increases. After the administration of the salt has been stopped the excretion continues large for two or three days, and then returns again to the lower standard. It seemed probable that similar retention would take place with potash, and if this were so, we might expect to counteract to a great extent the effect of barium by feeding an animal on potash for some time before administering the barium. On trying this, Cash and I have found that this is the case to a certain extent, and although we have not been able completely to counteract the effect of a large dose of barium so as to prevent death from a lethal dose, we have been able to modify and diminish its action by the administration of potash for several days previously, so that the characteristic symptoms of barium poisoning do not occur until some hours after they would otherwise do so, and thus life is prolonged though not preserved.

Action of Drugs on Involuntary Muscular Fibre.

Contraction.—Involuntary muscles, with the exception of the heart, differ from voluntary not only in their anatomical structure but in their functional activity: instead of contracting or relaxing rapidly, both their contraction and relaxation are slow. We have seen that although voluntary muscle occasionally exhibits spontaneous rhythmical contractions, yet these occur only under exceptional circumstances, and but rarely. Involuntary muscle, on the other hand, has a much greater tendency to rhythmical contraction, although it may be regarded as doubtful whether some stimulus, however slight, is not required to induce this rhythm even in involuntary muscle. It has been already mentioned that the contractile tissue of medusa will beat rhythmically so long as it is connected with motor ganglia. When these ganglia are removed, the contractions cease, but will again reappear, notwithstanding the absence of the ganglia, if a constant stimulus be applied to the contractile tissue itself. This shows that the conditions for rhythm are contained in contractile tissue itself—that the rhythm may be independent of the ganglia with which the contractile tissue is connected (p. 113). The same appears to be the case with involuntary muscular fibre generally.

The ventricle of the frog's heart, containing ganglia, will beat rhythmically for a length of time after its removal from the body. If the ganglia which lie close to the auriculo-ventricular groove be cut off, the rhythmical action will cease just as in the medusa when the marginal ganglia are removed; but if a constant stimulus be applied to the apex of the heart, as for example by passing a constant current through it, or by distending it with serum, its rhythmical movement will again commence, mechanical distension appearing to have upon it the same exciting action that a little acid added to the water has upon the nerveless bell of the medusa.

The excitability of involuntary muscular fibre appears to be increased by small doses of atropine; for when the ganglia of the frog's heart are removed the apex, instead of stopping immediately, will give a few beats before it stops if atropine has been previously given, and mechanical stimuli cause more beats in the atropinised than in the normal apex.[1]

Effect of Stimuli.—Mechanical distension appears to be one of the most powerful of all stimuli to excite rhythmical contraction in involuntary muscular fibre.

Luchsinger observed distinct pulsation in the veins of a bat's wing twenty hours after the death of the animal, if artificial circulation was kept up. This appears to show that the power of rhythmical contraction resides in the muscular fibres of the veins, as it does in the nerveless apex of the frog's heart, and the contractile tissue of the medusa; but here also an external stimulus appears to be required to induce contraction. When the pressure by which artificial circulation was maintained fell to zero, the pulsation stopped, but if it were raised to forty or fifty centimetres of water, so as to distend the vascular wall, rhythmical pulsation again commenced. It appears possible, however, that when involuntary muscular fibre is perfectly healthy and possesses the highest degree of irritability, it may contract rhythmically without any extra stimulus. Thus Engelmann[2] observed that the ureter, in which he could find no nerves at all, contracted rhythmically when freshly exposed, although it was not distended or subjected to any mechanical irritation; but if artificial respiration has been long kept up, and the animal is exhausted, so that the excitability of the ureter is diminished, then the effect of minimum distension in increasing its rhythm becomes very evident.

Cold causes the isolated non-striated muscles of animals to relax. **Heat** causes them to contract.[3]

The influence of heat and cold, however, does not seem to be constant, and in the non-striated muscle of frogs they have an

[1] Langendorff, *Archiv f. Anat. u. Phys.* Physiolog., Abtg. 1886, p. 267.
[2] *Pflüger's Archiv*, 1869, Bd. 11, p. 251.
[3] Luchsinger and Sokoloff, *Pflüger's Archiv*, Bd. 26, p. 465.

opposite connection to that just described. It is probable that the different results may depend to a great extent upon the amount of heat or cold applied, and its relation to the condition of the tissues at the time of application; for mechanical stimulation has also an opposite effect, according to its amount; and while gentle stimulation of involuntary muscular fibre, such as that of the small blood-vessels, causes dilatation, more powerful irritation produces contraction.[1]

The influence of various drugs upon involuntary muscular fibre, as seen in the contraction of the blood-vessels, will be described when considering the circulation.

The Relation of the Contractile Tissue to the Nerves is different in voluntary and involuntary muscular fibre. In the latter there are no end plates, but the terminal twigs form a plexus around the fibres. The motor nerves of involuntary muscular fibre appear to be affected by atropine and its congeners in a similar way to those of voluntary muscle by curare. There appears also to be a certain relationship between the atropine and curare group. Small doses of atropine paralyse the motor nerves of involuntary muscle, while very large doses of curare are required. The converse is the case with voluntary muscle. These effects are usually supposed to be due to a definite paralysing action on the nerves themselves. There are difficulties, however, in the way of this hypothesis, and a more probable one, perhaps, is that these drugs disturb the relations between the nerves and the muscular fibres which they excite. On the idea of a specific action it seems hard to explain the results obtained by Szpilman and Luchsinger,[2] who found that atropine produces paralysis of the motor fibres of the vagi supplying the œsophagus, only in those parts of it where involuntary muscular fibre is present. Thus the œsophagus of the frog and the crop of birds consist of involuntary muscular fibre, and atropine destroys the motor power of the vagus over them. The œsophagus of the dog and rabbit contains striated muscular fibre, and atropine does not paralyse the motor nerves. The œsophagus of the cat contains striated muscular fibres in its upper three-fourths, and non-striated in its lower fourth; atropine destroys the motor action of the vagus upon the lower fourth, but not upon the upper part.[3]

Propagation of Contraction Waves.—Although involuntary muscular fibre consists of short cells and not of long fibres like voluntary muscle, yet the contraction wave may be propagated along a strip of involuntary muscular tissue in both directions from the point of irritation, just as in voluntary muscle or in the contractile tissue of medusæ. This wave is transmitted

[1] Sigmund Meyer, *Hermann's Handb. d. Physiol.*, Bd. 5, Theil ii., p. 476.
[2] Szpilman and Luchsinger, *Pflüger's Archiv*, Bd. 26, p. 459.
[3] *Ibid.* p. 249.

more slowly in involuntary than in voluntary muscle; and its rate in the involuntary muscle of the heart, though slower than in ordinary striated muscle, is quicker than in unstriated muscle, so that in this respect the heart is intermediary between the two.[1]

The passage of contraction waves in involuntary muscular fibre is affected by the same conditions as voluntary muscle, the conduction of the contractile wave being rendered slower by fatigue and cold, while it is quickened by heat.

Cold and fatigue also render the rhythmical pulsations smaller and longer, while heat has an opposite effect. The passage of the contraction wave may also be diminished or arrested by section or pressure, just as in the contractile tissue of medusæ,[2] so that instead of each contraction wave passing the block produced by the sections or compression, only one out of several, or none at all, may pass. The proportion passing the block depends upon its completeness. If the tissue forming the bridge be dry as well as narrow, the block becomes more complete, and may be again diminished by moistening. Variations in the strength of the stimulus do not affect the passage of the contraction wave over the block, so that it would appear that the injury caused by the section, along with the narrowing of the conduction path, retards the re-establishment of the conductive power.

In experiments made upon the heart of a tortoise cut into a strip, it has been found by Gaskell that stimulation of the **vagus** removes the block, quickens the recovery of the tissue, and causes every contraction wave to pass. The effect upon the muscle therefore seems to be trophic.

A **weak interrupted current** applied to the muscle directly has the same action as stimulation of the vagus, i.e. it increases the conducting power of the muscle. Sometimes, however, both the vagus and a weak interrupted current have an opposite effect, and diminish instead of increasing the conducting power.

An **artificial rhythm** may be induced in a strip of involuntary muscular fibre cut from the heart of the tortoise by passing a weak interrupted current through it and then stimulating it at one end by induction shocks, at intervals of about five seconds. After a while, if the induction shocks are discontinued, the muscle still continues to contract rhythmically at the same rate. These contractions, at first weak, afterwards become strong, and may last for many hours. Both the conducting and the contractile power of the muscle are diminished by muscarine. When a strip of it is stimulated by induction-shocks applied to one end, the contraction wave passes quickly along; but muscarine appears to

[1] *Hermann's Handbuch d. Physiologie*, Bd. 1, p. 56.

[2] Engelmann, *Pflüger's Archiv*, 1875, Bd. 11, p. 465; Gaskell, *Journal of Physiology*, vol. iii. p. 367.

block its transmission, so that while the part of the muscle between the electrodes contracts at every shock, the rest of the muscle contracts only at every second one. A weak interrupted current then sent through the muscle may lower its conducting power and still further reduce the force of the contractions, and not only block the passage of most of the contraction waves from the point of excitation, but may even prevent the contraction of the excited part itself.

Atropine has an opposite action and appears to increase the conducting power of involuntary muscle, so that when applied to a strip of the heart, the conducting power of which has been diminished by muscarine, the contractility is at once increased, and each contraction wave passes over the whole muscular strip each time that a single point is irritated. Large doses, however, appear to have a depressant action on the muscle.

Hypothetical Considerations regarding the Action of Drugs on Muscle.

The modifications which drugs produce in the functions of the animal body and of its parts are so numerous and varied that we are unable fully to explain them on the basis of our present physiological knowledge. The results of pharmacological experiments furnish us indeed with a number of additional facts regarding the functions of organs and tissues which will ultimately lead us to a more correct and thorough knowledge of their physiology. At present, however, we can only explain them hypothetically, and, indeed, in many cases we can do little more than guess at the explanation.

The advantage to be gained from hypothetical explanations is that hypotheses not only lead to further experiment, but serve as guides for experiments, by which, if false, they may be soon disproved, or, if true, may be maintained.

The disadvantage of hypotheses is that they are sometimes apt to be taken for facts, and being made use of as bases for further speculation, may lead more and more astray from the truth. While bearing in mind the danger of speculation, it may be useful to make some guesses at the mode of action of drugs upon the muscle as guides to further research.

The most striking point about muscle is the motor function which it exercises by contracting, and the nature of its contraction must engage our attention. Throughout the universe we find that motion of nearly all sorts resolves itself into a series of vibrations, and the question arises whether the motion of muscle cannot be explained in the same way.

When a muscle is stimulated it contracts and relaxes once, describing a wave-like curve upon the revolving cylinder. Frequently this first wave is followed by a second, and sometimes even by a third, which are usually ascribed to the simple elasticity of the muscle. Sometimes we can notice that the single contraction wave appears really to consist of two or more partially superimposed on each other, and sometimes we may find two distinct waves arise from one stimulation.

When a muscle is in a state of tetanic contraction it appears to the eye to be perfectly quiet, yet we know that during this period of apparent rest the muscle is in a state of vibration, alternately tending to contract and elongate. These vibrations may succeed one another with a rapidity such that the muscle appears to the eye to be motionless, while a tracing taken upon the revolving cylinder shows distinct successive waves. If the vibrations are still more rapid, the waves may disappear, and we get the muscle describing a straight line. But even when a muscle is entirely relaxed, its parts may

be in a state of vibration quite as continuous as in tetanic contraction. This is seen by examining muscular fibre under the microscope. The phenomenon which then presents itself was described by Porret and is often known by his name. On passing a constant current through a thin muscular slip a contraction is seen when the current is closed. During the whole time of the passage of the current, the muscle, to the naked eye, appears to be perfectly at rest, but under the microscope its parts are seen to be in constant motion, presenting an appearance almost exactly similar to the waving of a field of corn on a windy day, or to the motion of rows of cilia. At the same time an actual transference of material takes place in the muscle: the end next the positive pole growing smaller, and the end next the negative pole growing larger. When the current is suddenly reversed, a sudden contraction of the whole muscle takes place, and it then returns to apparent rest; but microscopic observation shows the same cilia-like motion as before, but in an opposite direction.

This phenomenon reminds one very strongly of the crowding together of carriages in a railway train when it is set in motion or stopped by the locomotive pushing behind or stopping in front. We know that the apparent steady movement of the train is due to the backward and forward vibration of the piston in the cylinders of the locomotive, and the question occurs whether the contraction of the muscle as a whole at the moment of opening and breaking the current, is not due to an interference with the rhythmical vibration of its parts. The question also arises whether these vibrations are not to a great extent dependent upon the molecular weight of its constituents. This seems to a certain extent to be indicated by the curious relations between the effects of the alkalis, alkaline earths, and certain metals upon muscle. Thus Cash and I have found that potassium and calcium neutralise the action of each other upon muscle, and if the hypothesis just expressed be correct we should expect that metals having a similar molecular weight to a mixture of calcium and potassium would have no action upon muscle. This appears to be the case. In researches made in Professor Schmiedeberg's laboratory, Anderson Stewart found that nickel and cobalt had no action upon muscle, and White found that tin also had little or none. On comparing then the atomic weights of potassium (39), calcium (40), nickel (59), cobalt (59), and tin (118), we get the following relationships:

$$K_2\ (78) + Ca\ (40) = Ni_2\ (118),\ or,\ Co_2\ (118),\ or,\ Sn\ (118.)$$

Sodium in large doses lengthens the curve and increases the contracture when applied to a normal muscle. It adds to the length of the long curves caused by calcium and strontium. Rubidium in large doses produces a long curve with enormous contracture almost like that of barium. One would naturally have expected that the rubidium and barium would have increased each other's effect like sodium, calcium, or strontium; but the reverse is the case, for the abnormal curve caused by rubidium is reduced to the normal by the application of barium. If barium be applied to a greater extent than is sufficient to antagonise rubidium, it first abolishes the prolonged rubidium curve, reducing it to the normal, and then again elongates it, producing its own characteristic curve. Calcium and strontium, which also prolong the curve, though to a less extent than barium, do not antagonise one another's effect—they rather increase it; but calcium reduces the barium curve to the normal before causing its own peculiar curve. At first sight these results seem to be independent of any rule, but a curious relation is to be observed between the atomic weights of these substances. Thus we have seen that rubidium in large doses has the same effect as barium in causing a veratrine-like curve, but barium destroys the effect of rubidium before producing its own effect. On comparing the atomic weights of these elements we find that eight atoms of rubidium have nearly the same weight as five of barium, and by subtracting one from the other we get almost no remainder. Thus,

$$\begin{aligned} Ba\ 137 \times 5 &= 685 \\ Rb\ 85{\cdot}4 \times 8 &= 683{\cdot}2 \end{aligned}$$

Potassium is, as we know, an important constituent of muscle, and it seems possible that the reduction in the barium-curve which calcium causes may be due to their union having resulted in a substance whose molecular weight is a multiple of that of potassium. Thus,

Ba 137 × 2 = 274 — Ca 40 = 234
K 39 × 6 = 234

The alterations which occur in voluntary muscle from the action of such substances as calcium or barium appear to approximate it to some extent to involuntary muscle. Voluntary muscle is chiefly characterised by sudden and rapid contraction and relaxation. Involuntary muscle usually contracts and relaxes slowly. In the slowness of its relaxation, at least, the muscle poisoned by barium or calcium approaches involuntary muscle.

The power of summation which contractile tissues possess is strongly suggestive of the idea that rhythmical vibrations of gradually increasing intensity are going on within the tissue even before any movement becomes visible. A pendulum very gently struck at proper intervals will gradually begin to oscillate through a larger and larger arc. If touched on one side while oscillating, the effect of the touch will depend upon the time at which the touch is applied, for at one period of oscillation it will tend to impede, and at another to assist the oscillation. Possibly some unseen rhythm in the muscle itself may be the cause of the curious variations in excitability observed in dying muscles and in muscles poisoned by lead. Two pendulums connected together will swing harmoniously if their rate of oscillation is the same, but if one be loaded so as to alter its rate of oscillation they will interfere with each other. Possibly the effect of poisons in paralysing nerves may be due rather to alteration in the relative rhythms of the nerve and muscle than to any specific destructive power on the terminations of the nerve itself.

The opposite effects which Gaskell has noticed the vagus nerve and a weak induced current to produce upon the conducting power of the cardiac muscle, sometimes increasing and sometimes diminishing it, may be due to the interference or coincidence of rhythm such as are discussed more fully farther on under the head of Inhibition.

It is impossible to say at present what the true cause of the curious rhythmical contractions of voluntary muscle is, but if we suppose that there is a transverse as well as a longitudinal contraction in muscle, we might regard the rhythmical contractions as resulting from the action of these two opposing forces.

It must be borne in mind that the considerations contained in this section are purely hypothetical, and their only use is to indicate the direction in which we may possibly look for an explanation of the action of medicines on muscle.

CHAPTER VI.

ACTION OF DRUGS ON NERVES.

General Action of Drugs on the Nervous System.

In low organisms the contractile protoplasm fulfils the functions of both nerve and muscle, but as we ascend in the scale differentiation becomes more and more complete. From their original common origin, however, we might expect that the poisons which act on the muscles would also act on the motor nerves, and *vice versâ*, and we should hardly expect any poison to act entirely on the one without affecting the other. This is to a considerable extent the case, for very many substances paralyse them both. But, as one would also expect from the differentiation they have undergone, muscle and nerve are not equally affected in the higher animals. Thus we find that although most of the salts of ammonium, and the iodides, chlorides, and sulphates of the compound ammonias into which methyl and ethyl enter, paralyse both muscle and nerve, yet they paralyse the nerve before the muscle. In some cases the nerve is affected so much before the muscle that at first sight it might appear that the nerve alone was paralysed and the muscle left unaffected. More careful observation, however, shows us that most of the compound ammonias, and probably most of the organic alkaloids, affect muscle, motor nerves, and nerve-centres, and, if their action can be continued long enough, will paralyse all three. The symptoms they produce may, however, be entirely different, because these depend upon the order in which the different parts of the nervous system are affected, as has already been pointed out at p. 26. The symptoms produced, for example, by strychnine and methyl-strychnine are utterly different, the former causing tetanic convulsions, and the latter gradually-increasing torpor, weakness, and paralysis. Strychnine stimulates the spinal cord, and methyl-strychnine paralyses the motor nerves; yet if their action continue long enough it is found that both of them will ultimately cause paralysis of both spinal cord and motor nerves. The final result is thus the same in both cases, but the order in which the various parts of the nervous system are affected is different.

In the example just given, the drugs appear to exert a selective influence on the spinal cord and motor nerves respectively, and consequently produce very different symptoms. But we find that a number of drugs appear to act upon muscles, motor nerves, and nerve-centres, in a given order, although there may be slight variations in the action of the individual drugs. These substances are generally found to act as protoplasmic poisons, arresting the movements of amœbæ and white blood-corpuscles, as well as proving fatal to higher animals.

In the protoplasm of these minute organisms we are unable at present to distinguish any evidences of differentiation. As we ascend in the animal kingdom we find a differentiation between




FIG. 51.—Diagram to illustrate Hughlings Jackson's views of the nervous system.

muscle, nerve, and nerve-centre; and the higher up we ascend in the scale the more complex do the nerve-centres become. As Hughlings Jackson has well put it, 'evolution is a passage from the most simple to the most complex, from the lowest to the highest centres.' It is a passage from the most automatic to the most voluntary; but the lowest centres are at the same time the most stable, or, as Jackson calls it, the 'most organised centres'; while the highest centres are the most unstable or least organised. This is represented diagrammatically in Fig. 51, where the centres for the heart and respiratory apparatus and for the

sphincters are represented as very simple in their organisation, but very stable, as indicated by the size of the ganglia and thickness of the nerves in the diagram. The spinal cord is represented as more complex, but with thinner lines, in order to show its lesser stability; while the high complexity and small stability of the cerebral cortex is indicated by the great number and thinness of the lines in the figure. According to Jackson, the lowest nervous centre extends from the aqueduct of Sylvius to the lower end of the spinal cord; and in this all parts of the body are directly represented, so that a discharge of nervous energy from any part of it only requires to overcome the resistance in the motor nerves and the muscles themselves. What he regards as the middle motor centres are evolved out of the lowest, and re-represent all parts of the body in more complex and special combinations. The highest centres evolved out of the middle re-re-represent all parts of the body in still more complex and special combinations. A discharge from the highest centres, in order to act on the periphery, has to overcome the resistance of the middle and lowest centres, as well as of the muscles.

In the action of such poisons as alcohol, the nervous system appears to be paralysed in inverse order of its development: the highest centres going first, next the middle, and then the lowest. After this comes paralysis of the motor nerves, and lastly of the muscles themselves. In the case of alcohol, the dose required to paralyse motor nerves and muscles is so great that, as a rule, we can only observe its effect by directly applying the drug to the nerves and muscles themselves. To such a process of paralysis as this, Jackson applies the term of dissolution.

In the case of drugs which excite nervous centres, we also notice a certain similarity of action. Thus strychnine not only causes convulsions by its stimulating action on the medulla spinalis, but stimulates also the nerve-centres for the respiration and circulation in the medulla oblongata and in the heart itself.

Action of Drugs on Motor Nerves.

The readiness with which a muscle responds to a stimulus depends both on the condition of the muscle itself, and on the terminations of motor nerves within it. A faradaic current readily stimulates the nerve-endings, but does not act at all readily on the muscle. The making and breaking of a constant current, on the other hand, has comparatively slight action on the nerves, but a powerful action on the muscle. One of the questions which arises most constantly in connection with the action of drugs is:—whether or not they paralyse the end of the motor nerves in muscle. This question was fully worked out by Bernard, and also independently by Kölliker, in relation to curare.

The same **methods of experiment** were adopted by both. They were twofold, and consisted:

1. In applying the poison to that part of the body alone which seemed affected by it, and seeing whether it produced its usual action.

2. In preventing it from reaching that part, and seeing whether its usual effect was then absent.

The first of these methods consisted in the local application of the drug to the muscles and motor nerves themselves (Figs. 52 and 53). The second consisted in ligaturing the artery of one leg in a frog, so as to prevent the poison from reaching the muscles and motor nerves in that leg (Fig. 54).

The advantage of the first method, viz. that of local application, is that it allows us to deal with only one organ at a time, and the results are therefore less complicated than those of the second method. In some respects it is better to begin with the second method and work back to the simpler from the more complex organs (p. 149).

Paralysis of Motor Nerve-endings.—Curare produces symptoms of paralysis. **Paralysis may be due to** the action of the drug on the **muscles** themselves, on the **motor nerves** which set them in action, or on the **nerve-centres** which originate motor impulses. In order to decide this, Bernard applied electricity to the nerves and to the muscles of a frog poisoned by curare administered subcutaneously. He thus found that when the nerve was irritated no effect was produced on the muscles; but that when the muscle itself was stimulated, it contracted readily. In order to decide whether this loss of irritability in the nerve was due to a change in the nerve-trunk, or in the terminations within the muscle, Bernard employed the first method, that of **local application.** He placed a solution of curare in two watch-glasses. In one he immersed the trunk of the nerve (Fig.




FIG. 52.—Shows the method of applying a drug in solution locally to the trunk of a nerve.

52), and in the other the muscle, so that the solution penetrating between the fibres could reach the nerve-endings (Fig. 53). He




FIG. 53.—Shows the method of applying a drug in solution locally to a muscle and the ends of motor nerves within it.

then irritated the nerve attached to both muscles, and found that irritation caused contraction readily enough in the case

where the nerve-trunk had been steeped in the solution of curare, but had no effect when the curare had been allowed to reach the nerve-ends by immersion of the muscle in the solution. The irritability of the muscle itself to mechanical stimuli, or to the making and breaking of a constant current directly applied to it, remained quite unaltered, so that the muscular fibre had evidently not been affected by the action of the poison.

The second mode of testing the action of drugs upon motor nerves, viz. that of **local protection**, consists, as has been stated, in allowing the drug to be carried to the muscles and nerve-endings




FIG. 54.—Diagram of the mode of experimenting on motor and sensory nerves in the frog.—The shaded part shows where the poison has been carried by the circulation. The unshaded left leg shows where the tissues have been protected from the poison by ligature of the artery just above the knee. The unbroken lines with arrows pointing to the spinal cord indicate the sensory nerves. The broken line with arrows pointing outwards indicates the motor nerve to the unpoisoned leg.

by the circulating blood in one leg of a frog, while it is prevented from reaching the other either by ligaturing (Fig. 54) the blood-vessels alone, or ligaturing the whole leg with the exception of the sciatic nerve. After some time has elapsed, the sciatic nerve is stimulated on each side. If the muscles of the poisoned limb do not contract at all or do so more feebly than in the unpoisoned limb, it is evident that the poison has paralysed either them or the motor nerves. In order to decide whether the nerves or the muscles are paralysed the muscle is next stimulated directly; if it then contracts normally it is evident that the paralysis observed when the nerve was irritated is due to the action of the

drug on the nerve-endings. If the muscle is completely paralysed, no definite conclusion can be drawn regarding the nerve-endings, but if the muscle shows only partial paralysis, and the paralysis is greater when the nerve is stimulated than when the muscle is stimulated directly, we conclude that the drug has acted upon both the muscular substance itself and the motor nerve-endings within it.

The effect of drugs in paralysing motor nerves is chiefly investigated in frogs as the action comes out much more distinctly in them.

Warm-blooded animals may die from paralysis of the motor nerves while the nerves still respond readily to faradaic stimuli applied to them, the faradaic stimulus being much greater than that normally sent along the nerves from the nerve-centres. Thus after an animal has been killed by paralysing it with curare, its muscles will still respond readily to electrical stimulation of the motor nerves.

A **fallacy** to be guarded against in experiments on the results of preventing a poison from reaching one part of the body is that caused by diffusion. Even when the circulation is stopped in a frog's leg by ligature of the artery, poison introduced into the dorsal lymph-sac may pass down the limb by diffusion and affect the parts below the ligature. This may be to a great extent prevented by ligaturing the whole limb *en masse*, at the same time carefully excluding the sciatic nerve from the ligature. Diffusion may also occur although the circulation has been stopped throughout the whole body by removal of the heart and other viscera, and the anterior part of the spinal cord may be affected before the posterior when the poison is injected into the dorsal lymph-sac.

Advantage of the Method of Local Protection.—The advantage of this method is that it affords information regarding the action of the poison upon other parts of the nervous system, viz. the nerve-centres and sensory nerves, as well as upon the motor nerves. It also gives the order in which the poison affects the various nervous structures, and shows whether the quantity of poison conveyed to the nerves by the circulation is sufficient to paralyse them or not. For some substances, directly applied to the ends of the motor nerves, may paralyse them, although they do not have this effect when injected into the blood: the reason being that the quantity applied to the nerves directly may be much greater than that which reaches them through the circulation.

The muscles and ends of the motor nerves being protected in the ligatured leg from the action of the poison while it still remains in connection with the nerve-centres by means of the sciatic nerve, this method serves as an index to show what is going on in the nerve-centres. Thus in a frog poisoned by

curare it is found that the ligatured leg moves on irritation of the sensory nerves, while all the poisoned parts remain perfectly still. This shows that the afferent nerves are still capable of conveying impressions to the spinal cord, and the cord itself of reflex action, although the poisoned limbs give no indication of the changes which are occurring in the nerve-centres. By-and-by irritation of a sensory nerve or root ceases to produce any movement even in the ligatured limb. This effect is shown to be due to paralysis of the nerve-centres by observing the effect of irritation of the nerves in the ligatured limb, for the muscles still respond readily to irritation of the nerve by a moderate stimulus. We may conclude with tolerable certainty that the motions have ceased in the limbs because the nerve-centres have become paralysed.

Paralysers of Motor Nerves.—Many other drugs have an action somewhat similar to that of curare upon the motor nerves:—

Ammonium cyanide.[1]
„ iodide.
Ethyl ammonium chloride.[1]
Amyl ammonium chloride.[1]
„ „ iodide.[1]
Amyl ammonium sulphate.[1]
Phenyl-di-methyl-ethyl ammonium iodide.[13]
Phenyl-di-methyl-amyl ammonium iodide.[13]
Phenyl-di-methyl-amyl ammonium hydrate.[13]
Phenyl-tri-ethyl ammonium iodide.[13]
Tri-methyl ammonium iodide.[2]
Tri-ethyl „ chloride.
„ „ iodide.
„ „ sulphate.
Methyl-tri-ethyl stibonium iodide.[14]
Methyl-tri-ethyl „ hydrate.[14]
Toluyl-tri-ethyl ammonium iodide.[13]
Di-toluyl-di-ethyl „ „ [13]
Toluyl-di-ethyl-amyl „ „ [13]
Toluyl-tri-ethyl „ hydrate.[13]
Tetra-methyl „ iodide.
Tetra-ethyl „ „
Tetra-methyl „ iodide.[13]
Tetra-amyl „ „ [13]
Tetra-ethyl phosphonium iodide.[14]
Tetra-ethyl arsonium iodide.[14]
Tetra-ethyl arsonium and zinc double iodide.[14]
Tetra-ethyl arsonium and cadmium double iodide.[14]
Anchusa.[3]
Methyl anilin.[4]
Ethyl „ [4]
Amyl „ [4]
Methyl-atropine.[2]
Methyl-brucine.[2]
Ethyl-brucine.[3]
Camphor.
Methyl-cinchonine.[3]
Amyl „ [3]
Chloroxethylene.
Methyl-codeine.[2]
Collidine.
Coniïne.
Di-methyl-coniïne.[2]
Cotarnine.[3]
Cynaglossine.[5]
Di-methyl ammonium chloride.[1]
„ „ iodide.[1]
„ „ sulphate.[1]
Di-ethyl „ chloride.[1]
„ „ iodide.[1]
„ „ sulphate.[1]
Curarine.[6]
Curare.[7]
Ditaïne.[8]
Methyl-delphinine.[3]
Echium.[3]
Erythrina corallodendron.[9]

---

[1] Brunton and Cash, *Proc. Roy. Soc.*
[2] Crum-Brown and Fraser, *Trans. of Roy. Soc. of Edinburgh.*
[3] Buchheim and Loos, Eckhard's *Beiträge*, Bd. v.
[4] Jolyet and Cahours, *Compt. Rend.*, lxvi. p. 1181.
[5] Diedülin, *Med. Centralbl.*, 1868, p. 211.
[6] Preyer, *Göttinger Ztschr. f. Chemie*, 1, p. 381.
[7] Bernard and Kölliker.
[8] Harnack, *Arch. f. exp. Path. u. Pharm.*, vii. p. 126.

Guachamachà.[10]
Lobeline.
Methyl-morphine.[2]
Methyl-nicotine.[2]
Ethyl „ [3]
Ptomaïnes.[11]
Methyl-quinine.[3]
„ quinidine.[2]
Methyl-piperidine.
Saponine.
Sparteine.
Methyl-strychnine.[2], [12]
Ethyl „ [2]
Methyl-thebaïne.[2]
Methyl-veratrine.[3]
Amyl „ [3]

Although the substances mentioned in the above list have all the power of paralysing motor nerves, they do not possess the same power as curare. In the case of the salts of ammonium and the compound ammonias, the curare-like action is accompanied by a paralysing effect upon the muscular substance and on the nerve-centres. When salts of these substances are employed, their effect is somewhat modified by their acid radical, although this is not the case to the same extent in the salts of the compound ammonias, and in the salts of ammonium itself. Thus the iodide of ammonium has a much stronger paralysing action on the nerves than bromide, chloride, sulphate, or phosphate, and this is observed also, though to a less extent, in the salts of the compound ammonias.[1]

Exact Localisation of the Action of Curare.

The experiments already described have shown that curare does not paralyse the trunks of motor nerves (p. 148), nor the muscular substance (p. 148), and does paralyse the peripheral terminations of the motor nerves within the muscles: but they do not show what the exact part of the peripheral terminations is on which the drug exerts its action.

When a nerve enters a muscle it divides and subdivides dichotomously until the fibres become single, and, losing their myelin sheath, the axis-cylinders enter the muscular fibres. There they end in the nerve-plates, from which the ultimate branches pass to the muscular substance.

The paralysis produced by curare may be due to its action on:

(*a*) The single nerve-fibrillæ before they completely lose their myelin sheath;

(*b*) The axis-cylinders;

(*c*) The end plates;

(*d*) The ultimate branches.

As curare acts so much more readily on the nerves passing

[9] Harnack, Buchheim's *Pharmacologie*, 3rd ed. p. 615.
[10] Sachs, *Archiv f. Physiol.*, 1877, p. 91: Schiffer, *Deutsch. med. Wochenschr.*, 1882, No. 28.
[11] Several authors quoted by Guareschi and Mosso, *Les Ptomaïnes*. 1883.
[12] Schroff, *Wochenblatt d. Ztschr. d. Aertze zu Wien*, No. 14, 1866.
[13] Rabuteau, *Traité élémentaire de Thérapeutique*, 4me ed. p. 536 *et seq.*
[14] Vulpian, *Arch. de Physiologie*, 1868.

to voluntary than on those passing to involuntary muscles, and the most marked anatomical difference between these two kinds of




FIG. 55.—Curve showing the excitability in different parts of the sartorius of a frog in a normal and curarised muscle.

muscles consists in the termination of the former in end plates, it is natural to suppose that curare acts upon these plates.




FIG. 56.—Shows the distribution of the nerves in the gastrocnemius of the frog and the curve of excitability in different parts of the muscle. It will be observed that the excitability is greatest in those parts where there are most nerve-endings.

Moreover, this supposition appears to receive confirmation from the observation of Kühne—that the end plates undergo a certain alteration in poisoning by curare, their outlines becoming more

distinct than in the normal condition. This slightly increased sharpness of outline may be regarded as indicating a slight physical change, which might, however, be associated with such profound chemical changes in the end plates as to destroy their power of conducting stimuli from the nerve to the muscle.

But recent researches by Kühne and one of his pupils, Politzer, appear to render it probable that some of the nerve-structures within the muscle retain their functional activity even in profound poisoning by curare; and Politzer supposes that the part of the nerve which is acted on by curare is the nerve-fibril before it has quite lost its medullary sheath, and that the poison destroys the conducting power of the nerve by acting on the cement-substance at Ranvier's nodes. The grounds on which this supposition is based are that, even in profound poisoning by curare, those parts of the sartorius of the frog which contain nerve-endings are more irritable than those which contain none (Fig. 56), and that the irritability increases or diminishes in proportion to the number of nerve-endings, just as it does in the normal muscle, although the excitability of all the parts containing nerves is less than normal in curare-poisoning.

That this variation in irritability in different parts of the muscle is due to nervous structures, and not to variations in the muscular fibres themselves, is shown by the fact that, when the excitability of the nerve is depressed by throwing it into a state of anelectrotonus, these variations in the excitability of the muscle disappear.

It is just possible that the nervous structures which retain a certain amount of excitability in curare-poisoning may be the ultimate terminations which pass from the motor plate to the muscular fibre: but Politzer appears to throw this possibility aside, and considers that the amount of nervous excitability retained shows that all the parts beyond the last node of Ranvier still possess their functions.

Should Politzer's supposition—that curare paralyses motor nerves by acting on the cement at Ranvier's nodes—be correct, it may perhaps serve to explain, not only the difference between its action on motor nerves going to voluntary and those going to involuntary muscular fibre, but also the difference between the action of curare, or poisons having a similar action, and of atropine on the inhibitory fibres of the vagus.

Action of Drugs in Increasing Excitability of Motor Nerves.

It is not so easy to prove positively that a drug has increased as that it has diminished the excitability of motor nerves. The fact that the nerves of the poisoned leg are found to be more excitable than those of the ligatured one in such experiments as those just described, does not prove it, for it must be borne in

mind that the arrest of the circulation in the ligatured leg lessens the excitability of the muscles and the nerves in it. This effect of the ligature strengthens the proof that a drug has produced paralysis when we find that, in spite of the freer circulation, the poisoned leg is less irritable than the ligatured one; but it prevents our concluding that the drug has increased excitability when we find that the poisoned leg responds more readily to stimuli than the ligatured one.

To try whether a drug increases excitability we treat two muscles with saline solution, and after ascertaining that their excitability is alike we add the drug to be tested to the saline solution in which one muscle is steeped, and after some time test the excitability again. If the muscle in the poisoned saline solution becomes more excitable than the other, we conclude that the increase is due to the action of the drug.

Irritation of Motor Nerve-endings by Drugs.—The peripheral terminations of motor nerves in muscle appear to be irritated by certain poisons, so that the excised muscle exhibits fibrillary twitchings. This might be due to irritation of the muscular structure itself, but as they are gradually abolished by curare they are supposed to depend upon irritation of the terminations of motor nerves. The poisons which produce this effect are: aconitine, camphor, guanadine, nicotine, pilocarpine, pyridine. Physostigmine produces it most markedly in warm-blooded animals, but does not seem to cause it in frogs.

Action of Drugs on the Trunks of Motor Nerves.—Nerve-trunks are, as a rule, very much less affected by poisons than the end-plates; but they may, nevertheless, be also acted upon by strong solutions of a poison. It appears necessary to apply the poison locally to them, and they are probably little if at all affected by poisons introduced into the system generally. The action of poisons is tested by placing a small piece of gutta-percha tissue under the nerve-trunk, usually the sciatic of the frog, and applying the poison directly to it, or dipping the nerve into a weak solution of common salt, or of sodium phosphate, to which the poison has been added, and comparing the poisoned nerve with one dipped into a similar saline solution without the poison.

There are two methods of comparison. The first consists in using the contraction of the corresponding muscle as an index of the functional power of the nerve; the second in ascertaining the effect of the poison on the normal electrical current in the nerve.

The motor fibres of a nerve appear to have their excitability abolished more readily than that of sensory nerves by changes in the body generally, and sometimes also by the local application of drugs to them. Thus in wounded nerves the motor function may be destroyed, while the sensory function is little altered,

and where both sensibility and motion have been destroyed by a bruise of the nerve-trunk, the sensibility may reappear, while the motor power does not. In rheumatic neuralgia there is not unfrequently motor paralysis with exaggerated sensibility. When a solution of physostigmine is applied locally to the nerve-trunk for a while, and the nerve is then irritated beyond the point of application, it is found that it will produce reflex movements of the body after it has ceased to do so in the limb supplied by the nerve, which shows that the sensory fibres can still conduct impressions, though the motor fibres cannot. Longer application of the poison will destroy the sensory fibres also. When a paste of theine is applied to the sciatic nerve, or the nerve is dipped in a solution of opium, similar results are observed.

By dipping nerves in a solution of the poison Mommsen finds that atropine diminishes the irritability of the nerves, affecting first the intramuscular endings, and afterwards the trunks. Alcohol, ether, and chloroform first increase and then diminish the irritability.

Action of Drugs on Sensory Nerves.

The general action of a drug on sensory nerves is much more difficult to ascertain with precision than its effect upon motor nerves, because the evidences of sensation we have in the lower animals are cries, and movements either of the limbs or involuntary muscles, such as the iris, arteries, or bladder, which ensue on irritation of sensory nerves.

In the production of these movements or cries, many structures are concerned, viz. sensory nerves, nerve-centres, spinal or cerebral motor nerves, and muscles. It is comparatively easy to ascertain the local action of the drug upon sensory nerves, for in this case these other structures are not affected. By applying the substance to one part of the body, either by painting it upon, or injecting it under, the skin, and then comparing the effect of stimulation produced by pinching or by the application of heat or electricity upon that and other parts of the surface, we can see whether or not the sensibility of the sensory nerves has been affected by the drug.

But when the drug is absorbed into the circulation, it may affect all the other structures already mentioned, as well as the sensory nerves, and thus it may be impossible to decide with certainty whether these nerves are affected or not. But even here definite results are sometimes obtainable, as in the case of curare. The method of experimenting is that of local protection, arresting the circulation in one leg of a frog by applying a ligature to the sciatic artery. The animal is then poisoned with curare, or any drug the action of which is to be ascertained. The poison is carried by the circulation to all other parts of the body excepting the ligatured leg.

In the case of curare the motor nerves are paralysed by the drug, and it would be impossible to ascertain whether irritation of the sensory nerve produced any effect at all, were it not that the ligatured limb, retaining its irritability, serves as an index to the condition of the nerve-centres. At first it is found that pinching the poisoned foot will cause movements in the non-poisoned leg. This shows that the sensory nerves retain their irritability and transmit the stimulation up to the spinal cord, whence it is reflected down the motor nerves to the non-poisoned foot.

As the poisoning becomes deeper, however, pinching the poisoned leg produces much less effect.

This might be due to paralysis of the spinal cord, but it is shown that this is not the case by pinching the ligatured leg just above and below the ligature.

It is found that a pinch just below the ligature causes marked reaction, while a pinch just above has little or no effect.

In this experiment all the structures concerned in the movement have been alike subjected to the action of curare with the exception of the ends of the sensory nerves below the ligature. It is thus evident that the diminished reaction from pinching above the ligature is due to paralysis of the ends of the sensory nerve, in the part of the body to which the poison has had access, and which is shaded dark in the engraving (Fig. 54).

In the experiment just mentioned, the second of the two methods already described (p. 147) in the reference to motor nerves is employed, and the action of the drug on the ends of sensory nerves is ascertained by preventing the poison from reaching them; but the first method may also be employed and the action ascertained by applying the poison to the ends of the sensory nerves, while the nerve-trunks and nerve-centres are protected from its action. Thus, in the experiments of Liégeois and Hottot upon the action of aconitine on the sensory nerves, they ligatured the vein and injected the poison into the artery of a frog's leg; the poison was thus carried to the ends of the sensory nerves in the skin, while it was prevented from reaching the nerve-centres. In this way they found that irritation of the poisoned skin ceased to produce any reflex action, while stimulation of the trunk of the nerve distributed to that leg still caused well-marked reflex action. Normally the terminations of a sensory nerve in the skin are much more sensitive than the trunk of the nerve; and this experiment therefore proves that aconitine paralyses the ends of the sensory nerves.

The local action of drugs on the sensory nerves in man is ascertained by producing, when applied locally, either diminution in pain which may be present at the time, or insensibility, which is usually ascertained by the æsthesiometer. This instrument is simply a pair of compasses with blunt points and a scale

by which the distance of the points from one another can be read off.

When the sensation is acute, the points are distinctly felt as two, even when they are but slightly separated from one another; but when the sensation is blunt, they are felt as one when they are at a considerable distance apart.

In frogs the local action on sensation is ascertained by dipping one leg for some time in the solution to be tested, and then comparing the effect of irritating corresponding points in the two feet or legs by pinching, by the application of acids, or by a faradaic current. In this way it has been ascertained that hydrocyanic acid has a powerful local action in paralysing sensory nerves. Where the drug is very powerful, its action on the nerve-centres might complicate the result, if a sufficient quantity should be absorbed into the blood. This fallacy may be avoided by arresting the circulation entirely through excision or ligature of the heart.

Local Sedatives and Local Anæsthetics.—Local sedatives are substances which diminish, and local anæsthetics are substances which destroy, the sensibility of the skin for the time being.

Local Sedatives.	Local Anæsthetics.
Aconite.	Extreme cold.
Atropine.	Ice.
Belladonna.	Ether spray.
Carbolic acid.	Carbolic acid.
Chloroform.	Cocaine.
Chloral.	Kawa-resin.[1]
Morphine.	
Opium.	
Veratrine.	

Action.—Their effect in some degree is due to a paralysing action upon the terminal branches of the cutaneous nerves. It is probably, to some extent, also due to an effect upon the vessels and tissues analogous to that which is produced by rubbing or scratching, which, as everyone knows, gives temporary relief to itching. Sweating also relieves the itching, which is sometimes felt just before it begins.

Uses.—Local sedatives are employed to relieve itching and to lessen pain, whether it be due to neuralgia or inflammation. Local anæsthetics are employed temporarily to abolish the sensibility of the skin, and allow slight incisions or operations to be made painlessly.

Stimulating Action of Drugs on the Peripheral Ends of Sensory Nerves.—The peripheral terminations of sensory nerves appear to become more sensitive when the supply of blood

[1] Lewin, *Ueber Piper methysticum* (*Kawa*). Berlin, 1886.

to the part is increased. This is markedly seen, not only in inflammation, where the part becomes exceedingly tender, but in cases where turgescence of the vessels occurs under physiological conditions. Besides the class of irritants which act on the peripheral terminations of sensory nerves so as to cause pain when locally applied, there are several drugs which appear to have a special irritant action on the ends of sensory nerves when introduced into the circulation: these are aconite and aconitine, which give rise to a peculiar tingling and numbness in the tongue, lips, cheeks, and indeed in all parts supplied by the fifth nerve. Veratrine also causes peculiar sensations in the sensory nerves when taken internally, but these are felt more in the fingers and toes, and in the joints, than in the tongue.[1]

[1] Von Schroff, *Pharmacologie*, 4th ed. p. 584.

CHAPTER VII.

ACTION OF DRUGS ON THE SPINAL CORD.

In the spinal cord we have to distinguish three functions: that of **conduction**, that of **reflex action**, and that of **origination** of nerve-force, as in the sweat-centres, &c., contained in it.

The spinal cord **transmits** sensory or afferent impulses **upwards** to the medulla and brain; and motor impulses **downwards** to the muscles, as well as other efferent impulses to the glands. It transmits reflex impulses **across**, either from behind forwards, or laterally from one half of the cord to the other. Transmission from behind forwards occurs when the impulse passes from the sensory to the motor columns on the same side, as in the case of reaction of a sensory stimulus on the same side of the body. It occurs laterally when the sensory stimulus produces motion, not on the same side, but on the opposite side of the body.

Action on the Conducting Power of the Cord.—Its **conducting** power for **motor** impulses is assumed to be impaired when it is noticed that any drug causes partial paralysis of the hinder extremities of an animal before the anterior extremities.

It is usually tested by irritating the spinal cord at its upper end, either mechanically with the point of a needle, or by a galvanic or faradaic current passed through electrodes inserted into it close together, and observing whether irritation of the cord itself in this way causes contraction in the muscles of the legs.

When no contraction is produced by irritation of the cord itself, while direct irritation of the motor nerves can still produce vigorous contraction, it is evident that the cause of the paralysis must be that the spinal cord has lost its power to conduct motor impulses.

These experiments may be made in a frog, the cerebrum of which has been previously destroyed; and they may be confirmed in warm-blooded animals where sensibility has been destroyed by a section of the cord, just below the medulla, and respiration is kept up artificially. The spinal cord is then exposed, and the anterior columns are irritated in the ways already mentioned.

The power of the cord to **conduct sensory impressions** is ascertained by exposing it under anæsthetics and allowing their influence to pass so far off that the animal is capable of giving

evidence of sensation. The posterior roots are then irritated before and after the injection of the poison into the circulation.

When it is found that after the poison is injected the irritation of the posterior roots which previously caused evidence of sensation no longer produces any effect, while irritation of the anterior columns still produces motion, the conclusion appears to be just, that the poison has paralysed the conducting power of the sensory columns of the cord.

This action appears to be possessed by caffeine, for Bennett found that while irritation of the posterior roots of the cord caused violent struggles and loud cries in a rabbit before the injection of caffeine into the circulation, similar irritation, after the injection, caused only a slight quiver. That this effect was not due to motor paralysis was shown by the fact that irritation of the anterior columns caused violent muscular contractions after the injection as well as before it.[1]




FIG. 57.—Diagram to show the effect of chloroform, chloral, and other anæsthetics on conduction of painful impressions in the spinal cord.

Ordinary impressions of touch, temperature, and muscular action are transmitted through the posterior roots of the spinal cord to the ganglia of the posterior horn of the grey substance, and thence upwards by the fibres of the lateral columns. Painful sensations, however, appear to be transmitted upwards through the grey substance of the cord. The afferent nerves, which transmit impressions from one part of the cord to another, so as to produce co-ordinated reflex movement, are contained in the posterior columns of the cord.

It is evident that any injury or poison which chiefly affects the grey matter so as to diminish its conducting power may abolish pain while reflex action still persists. This condition may be produced by division of the grey matter of the cord, and it occurs also at a certain stage of the action of anæsthetics such as chloroform and ether.

The action of drugs on the power of the spinal cord to **conduct reflex stimuli** both transversely and longitudinally has been carefully investigated by Wundt. He first ascertains the

[1] Hughes-Bennett, *Edin. Med. Journ.*, Oct. 1873.

time which elapses between the application of a stimulus to a motor nerve and the contraction of a muscle, the nerve used being the sciatic, and the muscle the gastrocnemius of a frog. This time, which includes that requisite for the stimulus to travel down the motor nerve and to set the muscle in action, he terms the **direct latency.** He next stimulates a sensory root of the spinal nerve at the same level and on the same side as the motor nerve, taking care that the stimulus does not act on the motor nerve directly, but only reflexly through the cord. The time between the application of the stimulus and the commencement of contraction he terms the **total latency.** By deducting the direct latency from the total latency, he ascertains the time required for the stimulus to pass through the grey matter of the cord from the posterior to the anterior horn of the same side. This he calls the **reflex time.**

The time required for **transverse** conduction is ascertained by applying the stimulus to a posterior root on the other side and comparing the latency with that of stimulation to a posterior root on the same side.

The time required for **longitudinal** conduction is ascertained by applying a stimulus to the brachial nerve, so that it has to travel down the greater part of the length of the spinal cord before it can excite the sciatic nerve. By comparing the latent




FIG. 58.—Diagram to show the method of investigating reflex and transverse conduction in the spinal cord. The motor nerve is first irritated at 1. As the cylinder revolves at a known rate, and a mark is made upon it by an electro-magnet at the instant the nerve is irritated, the distance between this mark and the commencement of the muscle curve indicates the time required for the irritation to travel down the motor nerve to the muscle and set it in action. The irritation is next applied to the posterior root on the same side (2). The distance between the commencement of contraction in this case and in that where the motor nerve was irritated gives the time required for simple reflex transmission of the stimulus from the posterior to the anterior horn of the cord. The stimulus is then applied to the posterior root on the opposite side at 3, and the distance between the commencement of the consequent contraction and that of the curve obtained by irritating at 2 gives the time required for transmission across the cord.

period of excitation in the brachial nerve with that of the sciatic on the same side[1] the length of time required for longitudinal

[1] For convenience sake both the sciatic and the brachial nerves are taken in this experiment on the opposite side from the muscle, so that the time of longi-

transmission of stimuli in the cord is ascertained. The mode of ascertaining the time of ordinary reflex and transverse transmission in the cord is shown diagrammatically in Fig. 58.

The differences in the latent period and in the form of the muscle curve obtained by irritation of the motor nerve, and by simple transverse, and longitudinal reflex stimulation, are shown diagrammatically in Fig. 59. Wundt found that when a motor




FIG. 59.—Diagram to show the difference between the length of the latent period and form of the curve in contraction induced, B, by direct irritation of the motor nerve; C, by simple reflex from irritation of the cord on the same side; and D, by cross reflex from irritation of the cord on the opposite side to that from which the motor nerve proceeds, as shown in Fig. 58. E shows combined transverse and longitudinal reflex; A indicates the moment at which the stimulus was applied in each case.

nerve was irritated at a point distant from the muscle the resulting contraction had not only a longer latent period, but was less in height and longer in duration than when the nerve was irritated close to the muscle. From a comparison of the curves it will be seen that a **small portion of grey matter** has a **similar effect** upon the stimulus which passes through it that a **great length of nerve-fibre** would have. In all reflex actions, therefore, in the normal animal, the contraction of the muscle has a longer latent period, less height, and longer duration than that produced by direct irritation of the motor nerve. The increase in the latent period, diminution in height, and longer duration are greater in the case of transverse than of simple reflex, and greater still in the case of combined transverse and longitudinal reflex.

In the normal frog a stronger stimulus is necessary to produce reflex contraction than would be sufficient if it were applied directly to the motor nerve, and strong and weak stimuli will produce strong and weak muscular contractions. The spinal cord has a power of **summation** similar to that already referred to in the case of contractile tissue of medusæ, so that a stimulus which would be powerless to produce a reflex contraction if applied once to a posterior root or to a sensory nerve will be effectual if repeated several times in close succession.

Strychnine has an effect on the conducting power of the spinal cord which we should hardly expect, and so have other convulsant poisons. It increases the excitability so much that slighter stimuli than before will produce reflex action, and it destroys to a considerable extent the power of summation, so that instead of each stimulus producing a contraction in propor-

tudinal conduction is ascertained by deducting the transverse from the combined transverse and longitudinal conduction.

tion to its strength, all have the same effect—a weak one, which is just strong enough to produce an effect at all causing as great a contraction as the most powerful. The time required for the transmission of stimuli through the cord is enormously increased, so that the latent period of ordinary reflex, and still more of transverse and longitudinal reflexes, is greatly increased, sometimes, indeed, to as much as ten times the normal. The retardation of transverse conduction is not absolutely greater than of longitudinal conduction; but, as the distance through which the stimulus has to pass in the former case is much less than in the latter, it follows that strychnine increases the resistance more transversely than longitudinally. Morphine in small doses has no very marked action upon the cord, but larger doses have an action almost exactly like that of strychnine, causing increased reflex irritability, tetanic contractions, and prolonged latency. Veratrine has a similar action. Nicotine and coniine in small doses have a similar action to strychnine, but this is quickly masked by the rapid appearance of paralysis. When large doses are used, paralysis occurs almost immediately, and is usually accompanied by fibrillary twitchings. Atropine has at first an action similar to strychnine in causing increased excitability, prolonged latency, and tetanic contraction. It differs from strychnine in causing more rapid diminution in the irritability of the grey substance of the spinal cord and in diminishing the conducting power of peripheral nerves. In consequence of this, irritation of the sciatic nerve in a frog poisoned by atropine causes two contractions, one direct and one reflex, separated from each other by a distinct interval, whereas, in a frog poisoned by strychnine, these two contractions begin almost at the same moment and appear superimposed upon each other.[1]

Effect of Drugs on the Reflex Action of the Cord.—The effect of drugs upon the reflex action of the spinal cord is usually estimated by the time which elapses between the application of a stimulus and the occurrence of reflex action, before and after the administration of a drug. Longer time indicates diminished, and shorter time increased, excitability of the cord.

Method of Experimenting.—Since the spinal cord in mammals quickly loses its excitability when deprived of oxygenated blood (as shown by Stenson's experiment, p. 164), frogs are used for experiment. The method usually employed is called Türck's method. The cerebral lobes in a frog are destroyed, and after sufficient time has elapsed to allow it to recover from the shock, it is suspended either by the head or fore-legs, so that the hind-legs hang down. A very dilute solution of sulphuric acid, the acid taste of which can be little more than perceived by the tongue, is put in a small beaker and raised until one foot of the frog is completely immersed in it.

[1] According to W. Stirling, the latent period of reflex action in the spinal cord is increased by the chloride and bromide of potassium and ammonium, by lithium salts, and by chloral and butyl-chloral; it is decreased by the chloride, bromide, and iodide of sodium.—*Stirling and Landois' Physiology*, 2nd ed., vol. ii. p. 909.

The time is then counted by means of a metronome, between the immersion of the foot in the acid solution and the time when the leg is drawn up out of it. As soon as the foot is drawn up, the acid is carefully washed off with some fresh water in order to prevent any injury to the skin, and after a minute or two, the experiment may be repeated. When the time seems constant the drug is injected into the lymph-sac, and the experiment is repeated again. The greater or less time which is required for the withdrawal of the foot from the acid after the injection of the poison, as compared with the time required before, shows the extent to which the reflex action of the spinal cord has been diminished or increased by the poison.

Direct, Indirect, and Inhibitory Paralysis of the Spinal Cord by Drugs.—When it is found that the reflex action of the cord is greatly diminished or apparently entirely abolished, it must not be at once concluded that this is necessarily due to the **direct** paralysing action of the drug itself upon the nervous substance of the cord. This may be the case, and is so when methyl-coniine is employed, but it may be due to the **indirect** action of the drug upon the heart, weakening the circulation, and lessening the function of the cord by interfering with its blood-supply.

In order to ascertain whether this is the case or not, it is usual to take two frogs as nearly alike as possible, to destroy the brain in each, and after waiting until they have recovered from the immediate shock of the operation, to inject into one the drug to be tested, and, at the moment when it stops the beating of the heart, to tie a ligature around the heart of the other. The persistence of reflex action is then tested in the usual manner, and if it is found that it disappears much sooner in the poisoned frog than in the other one in which the heart has been ligatured, it is concluded the drug has paralysed the substance of the cord itself.

Indirect Paralysis.—The spinal cord is very rapidly paralysed in mammals if the blood-supply to it is stopped. This is readily shown by Stenson's experiment of gently compressing the abdominal aorta in a rabbit with the thumb or finger, so as to arrest the circulation for four or five minutes. On releasing the animal its hinder extremities are found to be paralysed, and this paralysis, though it may be partly due to interference with the blood-supply of the muscles and nerves of the lower extremities themselves, is chiefly due to the arrest of circulation in the spinal cord. The spinal cord in frogs is less rapidly affected, but if the circulation be arrested for half an hour or so symptoms of paralysis usually begin to appear, the time varying, however, with the temperature and other conditions. Indirect paralysis is produced by aconitine, digitalin, and large doses of quinine, which arrest the circulation. It is frequently difficult to decide how far paralysis is due to the action of a drug on the circulation, and how far to its direct action on the spinal cord itself.

Direct Paralysis.—Paralysis of reflex movement is produced by a number of substances, some of which produce little or no previous excitement; others, however, markedly increase the excitability of the spinal cord first, and are thus classed as spinal stimulants.

Spinal Depressants.—The following drugs belong to this class :—

Depress without marked previous excitement.	Excite first and afterwards paralyse.
Antimony.	Ammonia.
Emetin.	Apomorphine.
Ergot.	Alcohol (through circulation.
Hydrocyanic acid.	Arsenic.
Methylconiine.	Camphor.
Saponine.	Morphine group.[1]
Physostigmine.	Carbolic acid.
Turpentine.	Chloral.
Zinc.	Nicotine.
Silver.	Potassium salts.
Sodium.	Veratrine.
Lithium.	Mercury.
Cæsium.	
Alcohol group[1] (action on nervous substance).	

Uses of Spinal Depressants.—Such substances as morphine, chloral, &c., which diminish the conducting power of the grey matter of the cord for painful impressions, are useful as anodynes, though their action in lessening pain is probably often due to their effect on the brain as well as on the spinal cord. Spinal depressants which lessen reflex action are employed in diseases where there seems to be increased excitability of various parts of the cord, as evidenced by spasm, either tonic or clonic. They are therefore employed in tetanus, trismus neonatorum, chorea, writer's cramp, and paralysis agitans. The pathology of many nervous diseases is imperfectly known, and as the action of spinal depressants is frequently a complex one of combined stimulation and depression, some of the drugs included in this class are used in paraplegia due to myelitis, locomotor ataxy, and general paralysis.

They are also used as antagonists in cases of poisoning by spinal stimulants like strychnine.

Inhibitory Paralysis. — The higher parts of the nervous system have the power of lessening the action of the lower, and in the frog this power seems to be especially marked in the optic lobes. Irritation of these either mechanically by a needle, chemically by a grain of salt laid upon them, or electrically, will lessen or entirely abolish the reflex action in the cord; but this again returns when the irritation is removed, or when its influence is destroyed by cutting the cord across, below the point of irritation. This fact was discovered by Setschenow, and thus parts of the

[1] Schmiedeberg, *Arzneimittellehre*, p. 34.

optic lobes concerned in this inhibitory action are known as Setschenow's centres.

An inhibitory action appears to be exerted by the cranial centres in higher animals also, for McKendrick observed that on decapitating a pigeon the body lies comparatively still for a second or two, and then violent convulsions set in. If the body be held firmly during these convulsions, and a moderately strong faradaic current be applied to the upper part of the spinal cord, the convulsions may be altogether arrested while it continues, again commencing when it stops. In this experiment the application of the current to the cut end of the cord is regarded as supplying a stimulus in place of that which would normally pass downwards from the brain.

Quinine causes great depression of reflex excitability, and this was stated by Chaperon to be due to the action of the drug on Setschenow's centres.




FIG. 60.—Nervous system of a frog, showing the cerebral and optic lobes, the medulla oblongata, and the spinal cord with nerve-roots. The brain is shown on a larger scale at p. 184.

Almost immediately after injection of quinine into the dorsal lymph-sac, the reflex excitability of the frog becomes very greatly reduced or almost entirely abolished, but if the spinal cord be now cut across at its upper part just below the medulla oblongata, the reflex excitability becomes as great, or even greater, than the normal.

This loss of excitability has been ascribed by Binz to the action of quinine on the heart, causing weakening of the circulation, and thus indirectly producing paralysis of the cord. This kind of paralysis does occur with large doses and after considerable time, but it is quite different from the inhibitory paralysis described by Chaperon, which comes on almost immediately after the injection of the drug into the lymph-sac, and disappears immediately on section of the cord below the medulla.

I have repeated Chaperon's experiments, and can fully confirm their accuracy. In doing so, however, it struck me that the result was most marked when a solution of quinine was concentrated and somewhat strongly acid. It therefore appeared probable that the inhibition was not due to the direct action of the quinine upon Setschenow's centres after it had been carried to them by the blood, but only to its reflex action upon them. It irritates locally the sensory nerves of the lymph-sac into which it is in-

jected, and this stimulus being transmitted to the optic lobes excites them so that they produce inhibition of that reflex action which would usually occur in the cord when the foot is irritated by acid. On testing this hypothesis by injecting acid alone into the lymph-sac, Mr. Pardington and I found that it also caused reflex inhibition like that produced by quinine. We may therefore conclude that there is nothing special in the action of quinine upon the inhibitory centres; it merely acts like other irritants on sensory nerves.[1] Probably digitalis and sanguinaria also act in a similar way.

NATURE OF INHIBITION.

Inhibition and the action of drugs on inhibitory centres play a very important part indeed in pharmacology, and on the present hypothesis they are very puzzling.

By inhibition we mean the power of restraining action which some parts of the nervous centres possess. At present it is usually supposed that certain parts of the nerve-centres, instead of having a sensory or motor function, have an inhibitory one peculiar to themselves. It is found, however, that inhibitory powers are not confined to Setschenow's centres, already mentioned (p. 166), but that almost any part of the nervous system may have an inhibitory action on other parts, so that it becomes almost necessary to abandon the old hypothesis. It is found, for example, that not only is reflex action more active in the frog when the optic lobes are removed, but that when the spinal cord is taken away in successive slices from above downwards, the reflex action in the part below goes on increasing. On the old hypothesis we are almost obliged to assume that each nerve-cell has two others connected with it, one of which has the function of increasing or stimulating, and the other of inhibiting its action. Most of the phenomena which we find can be explained in a much simpler way by supposing that nervous stimuli consist of vibrations in the nerve-fibres or nerve-cells, just as sound consists of vibrations.




FIG. 61.—Diagram to show increased intensity of vibration by coincidence of waves.




FIG. 62.—Diagram to show abolition of vibration by interference of waves.

Interference.—In the case of both sound and light we find that if two waves should fall upon one another so that their crests

[1] *St. Bartholomew's Hospital Reports*, 1876, p. 155.

coincide, the intensity of the sound or light is increased (Fig. 61), while if they fall on each other so that the crest of one wave fills up the trough of the other, they interfere so as to destroy each other's effect (Fig. 62); and thus two sounds produce silence, or two waves of light darkness. This is shown in the case of sound by a tube (Fig. 63), which divides into two branches, and these again re-unite. The length of one branch may be altered at




FIG. 63.—Diagram of apparatus for demonstrating the interference of waves of sound. A and B, branches of a tube; C, sliding piece by which the branch B can be lengthened or shortened at will; D, tuning-fork; E, the ear.

will, so that the sound travelling through one branch has further to go than the other. It may thus be retarded so far as to throw it half a wave-length behind the other, and silence is produced. If lengthened still further, so as to throw the one sound a whole wave-length behind the other, the crests again coincide, and the sound is again heard. Increasing the length still further, so that the one sound is thrown a wave-length and a half behind the other, they again interfere, and silence is again a second time produced. This may be repeated *ad infinitum*, silence occurring whenever the one sound falls behind the other by an odd number of half wave-lengths.




FIG. 64.—Diagram showing the beats or alternate increase and diminution of the wave-heights by the interaction of two systems of waves of different wave-lengths. At A, two systems, having a relation to each other of 3 to 1, are indicated separately by dotted and complete lines. At B the resultant of the interaction of the two systems is shown. With such a relation as that shown in the diagram, and with those of a vibrating rod generally, such as n, 3n, 5n, &c., the interference of the systems is not complete, and silence cannot be produced by the interference of sounds. (From Ganot's *Physics.*)

In the case just mentioned, the waves are of the same length, but if they are of different lengths, instead of constantly rein-

forcing and interfering with others, they may sometimes strengthen and sometimes weaken each other. The result is more or less rhythmical increase and diminution of action, or as it is termed 'beats.' This is shown in the accompanying diagram (Fig. 64).

Instances of rhythm occur in the body, which strongly remind us of this condition; for example, the different rhythms of the heart under various conditions.

Interference in Nervous Structures.—Supposing nervous stimuli to consist of vibrations like those of light or sound, the action which any nerve-cell would have upon the others connected with it would be stimulant or inhibitory according to its position in relation to them. If its relation be such that a stimulus passing from it to another cell will there meet with a stimulus from another quarter in such a way that the waves of which they consist coincide, the nervous action will be doubled; but if they interfere the nervous action will be abolished. If they meet so as neither completely to coincide nor to interfere, the nervous action will be somewhat increased, or somewhat diminished, according to the degree of coincidence or interference between the crests of the wave.

Thus if the relations of the nerve-cells S, S′ and M, M′ in the diagram (Fig. 65) are such that when a stimulus passes from a




FIG. 65.—Diagram to illustrate inhibition in the spinal cord. *s*, *s′*, and *s″* are sensory nerves, *m*, *m′*, and *m″* are motor nerves, S, S′, and S″ are sensory cells, M, M′, and M″ are motor cells in the spinal cord, SB is a sensory, and MB a motor cell in the brain.

sensory nerve *s* to a motor nerve *m*, one part of it travels along the path *s*, S, M, *m*, and another along *s*, S, S′, M, *m*, or *s*, S, S′, M′, M, *m*, at such a rate that the crests of the waves coincide at the motor cell M, they will increase each other's effect. If they interfere, the effect of both will be diminished or destroyed, i.e. inhibition will occur.

Effect of Altered Rate of Transmission.—But it is evident that the coincidence or interference of nervous stimuli travelling along definite nerve-paths, will vary according to the rate at which they travel, so that when stimuli which ordinarily interfere with one another, are made to travel more slowly, one may be

thrown a whole wave-length, instead of half a wave-length, behind the other: and thus we get coincidence and stimulation, instead of interference and inhibition. When stimuli, whose waves ordinarily coincide and strengthen each other's action, are made to travel more slowly, one may be thrown half a wave-length behind the other, and thus we shall have interference and inhibition instead of stimulation.

On the other hand, when the stimuli travel more quickly, the one which was half a wave-length behind the other, and interfered with it, may be thrown only a small fraction of a wave-length behind it. It will thus, to a great extent, coincide and cause stimulation, while the one which normally coincides with and helps another may, by travelling with increased rapidity, get half a wave-length in front of the other, and cause inhibition.

Opposite Conditions produce Similar Effects. — We see then that results, apparently exactly the same, may be produced by two opposite conditions, increased rapidity or greater slowness of transmission of stimuli.

The Same Conditions may cause Opposite Effects.—We see also that the same conditions may produce entirely opposite effects, by acting more or less intensely. Thus, the application of cold, or of any agent which will render the transmission of stimuli along nervous channels slower than usual, may throw one which ordinarily coincided with another a small fraction of a wave-length behind it, then half a wave-length, then three-quarters, next a whole wave-length, and then in addition to the whole wave-length it will throw it, as at first, a small fraction or a half wave-length behind, and so on.

We shall thus have the normal stimulation passing into partial, then into complete inhibition, which will gradually pass off as the crests of the waves come more nearly together, until they coincide, when we shall again have stimulation as at first. As the action proceeds, this second stimulation will again pass into inhibition. In the same way a gradual retardation of transmission will cause impulses, which normally interfere, gradually to coincide until inhibition gives place to complete stimulation, and this again passes into inhibition. By quickening the transmission and throwing one wave more or less in advance of another, various degrees of heat will likewise produce opposite effects.

Stimulation and Inhibition on this Hypothesis are merely Consequences of Relation.—Stimulation and Inhibition are not due to any particular stimulating or inhibitory centres; they are merely dependent on the wave-length of nervous stimuli or the rapidity of transmission, and on the lengths of the paths along which they have to travel. Any nerve-cell may therefore exercise an inhibitory or stimulating action on any other nerve-cell, and the nature of this action will be merely a question of

the length and arrangement of its connections, and the rapidity with which stimuli travel along them.

Test of the Truth of the Hypothesis.—If the hypothesis be true we ought to be able to convert inhibition into stimulation, and *vice versâ*, by either quickening or slowing the transmission of stimuli. We can quicken transmission by heat, and we can render it slower by cold.

On this hypothesis we would expect to find that either excessive quickening or excessive slowing of the passage of stimuli between the cells of the nerve-centres might cause a number of stimuli which would ordinarily interfere to coincide and produce convulsions. This is what actually does occur, for extreme heat and extreme cold both cause convulsions. But it is unsafe to lay too much stress upon this point, as the cause of convulsion may be very complex. We find, however, as we should expect on this hypothesis, that the inhibitory action of the vagus is destroyed by cold.[1]

Explanation of the Actions of Certain Drugs on this Hypothesis.

There are certain phenomena connected with the action of drugs on the spinal cord which are almost inexplicable on the ordinary hypothesis, but which are readily explained on that of interference. Thus belladonna when given to frogs causes gradually increasing weakness of respiration and movement, until at length voluntary and respiratory movements are entirely abolished, and the afferent and efferent nerves are greatly weakened. Later still, both afferent and efferent nerves are completely paralysed, and the only sign of vitality is an occasional and hardly perceptible beat of the heart, and retention of irritability in the striated muscles. The animal appears to be dead, and was believed to be dead, until Fraser made the observation that if allowed to remain in this condition for four or five days, the apparent death passed away and was succeeded by a state of spinal excitement. The fore-arms pass from a state of complete flaccidity to one of rigid tonic contraction. The respiratory movements reappeared; the cardiac action became stronger, and the posterior extremities extended. In this condition a touch upon the skin caused violent tetanus, usually opisthotonic, lasting from two to ten seconds, and succeeded by a series of clonic spasms. A little later still the convulsions change their character and become emprosthotonic. These symptoms are due to the action of the poison upon the spinal cord itself, for they continue independently in the parts connected with each segment of the cord when it has been divided.

[1] Horwath, *Pflüger's Archiv*, 1876, xii. p. 278.

This action may be imitated by a combination of a drug which will paralyse the motor nerves with one which will excite the spinal cord. Fraser concludes that the effects of large doses of atropine just described are due to a combined stimulant action of this substance on the cord, and a paralysing one on the motor nerves. The stimulant action on the cord is masked by the paralysis of the motor nerves, and only appears after the paralysis has passed off. He thinks that the difference in the relations of these effects to each other, which are seen in different species of animals, may be explained by this combination acting on special varieties of organisation. In support of his views he administered to frogs a mixture of strychnine which stimulates the spinal cord, and of methyl-strychnine, which paralyses the motor nerves, and found that the mixture produced symptoms similar to those of atropine. Notwithstanding this apparently convincing proof, it would appear that the paralysis in the frog is due to the action of the atropine on the spinal cord, and not to a paralysing effect on the motor nerves. For Ringer and Murrell have found that when the ends of the motor nerves in one leg are protected from the action of the poison by ligature of the artery there is no difference between it and the unpoisoned leg, while if Fraser's ideas were correct the unpoisoned leg ought to be in a state of violent spasm.

A condition very nearly similar to that caused by atropine is produced by morphine. When this substance is given to a frog, its effects are exactly similar to those produced by the successive removal of the different parts of the nervous system from above downwards. Goltz has shown that when the cerebral lobes are removed from the frog it loses the power of voluntary motion, and sits still; when the optic lobes are removed it will spring when stimulated, but loses the power of directing its movements. When the cerebellum is removed, it loses the power of springing at all; and when the spinal cord is destroyed, reflex action is abolished.

Now these are exactly the effects produced by morphine, the frog poisoned by it first losing voluntary motion, next the power of directing its movements, next the power of springing at all, and lastly, reflex action. But after reflex action is destroyed by morphine, and the frog is apparently dead, a very remarkable condition appears, the general flaccidity passes away, and is succeeded by a stage of excitement, a slight touch causing violent convulsions just as if the animal had been poisoned by strychnine.[1]

The action of morphine here appears to be clearly that of destroying the function of the nerve-centres from above downwards, causing paralysis first of the cerebral lobes, next of the optic

[1] Marshall Hall, *Memoirs on the Nervous System*, p. 7 (London, 1837). Witkowski, *Archiv für exper. Path. und Pharm.*, Band vii. p. 247.

lobes, next of the cerebellum, and next of the cord. But it seems probable that the paralysis of the cord first observed is only apparent and not real; and in order to explain it on the ordinary hypothesis we must assume that during it the inhibitory centres in the cord are intensely excited, so as to prevent any motor action, that afterwards they become completely paralysed, and thus we get convulsions occurring from slight stimuli.

Ammonium bromide also causes, first, complete loss of voluntary movement and reflex action, but at a later stage in the poisoning convulsions.

On the hypothesis of interference, the phenomena produced both by atropine and by morphine can be more simply explained. These drugs, acting on the nervous structures, gradually lessen the functional activity of the nerve-fibrils which connect the nerve-cells together; the impulses are retarded, and thus the length of nervous connection between the cells of the spinal cord, which is calculated to keep them in proper relation in the normal animal just suffices at a certain stage to throw the impulses half a wave-length behind the other, and thus to cause complete inhibition and apparent paralysis.

As the action of the drug goes on, the retardation becomes still greater, and then the impulses are thrown very nearly, but not quite, a whole wave-length behind the other, and thus they coincide for a short time, but gradually again interfere, and therefore we get, on the application of a stimulus, a tonic convulsion followed by several clonic ones, and then by a period of rest. This explanation is further borne out by the fact observed by Fraser, that the convulsions caused by atropine occurred more readily during winter, when the temperature of the laboratory is low, and the cold would tend to aid the action of the drug in retarding the transmission of impulses.[1]

The effect of strychnine in causing tetanus is very remarkable; a very small dose of it administered to a frog first renders the animal most sensitive to reflex impulses, so that slight impressions which would normally have no effect, produce reflex action. As the poisoning proceeds, a slight stimulus no longer produces a reflex action limited to a few muscles, but causes a general convulsion throughout all the body, all the muscles being apparently put equally on the stretch. In man the form assumed by the body is that of a bow, the head and the heels being bent backwards, the hands clenched, and the arms tightly drawn to the body.

My friend Dr. Ferrier has shown that this position is due to the different strengths of the various muscles in the body. All being contracted to their utmost, the stronger overpower the weaker, and thus the powerful extensors of the back and muscles

[1] *Transactions of the Royal Society of Edinburgh*, vol. xxv. p. 467.

of the thighs keep the body arched backwards and the legs rigid, while the adductors and flexors of the arms and fingers clench the fist and bend the arms, and draw them close to the body.[1] The convulsions are not continuous, but are clonic; a violent convulsion coming on and lasting for a while, and then being succeeded by an interval of rest, to which after a little while another convulsion succeeds. The animal generally dies either of asphyxia during a convulsion, or of stoppage of the heart during the interval.

When the animal is left to itself, the convulsions—at least in frogs—appear to me to follow a certain rhythm, the intervals remaining for some little time of nearly the same extent.

A slight external stimulus, however, applied during the interval—or at least during a certain part of it—will bring on the convulsion. But this is not the case during the whole interval. Immediately after each convulsion has ceased I have observed a period in which stimulation applied to the surface appears to have no effect whatever.

It is rather extraordinary, also, that although touching the surface produces convulsions, irritation of the skin by acid does not do so.[2]

The cause of those convulsions was located in the spinal cord by Magendie in an elaborate series of experiments, which will be described later on (p. 177).

Other observers have tried to discover whether any change in the peripheral nerves also took part in causing convulsion; but from further experiments it appears that the irritability of the sensory nerves is not increased.[3]

According to Rosenthal, strychnine does not affect the rate at which impulses are transmitted in peripheral nerves; he, however, states that it lessens the time required for reflex actions. Wundt came to the conclusion that the reflex time was on the contrary increased.

In trying to explain the phenomenon of strychnine-tetanus on the hypothesis of interference, one would have been inclined by Rosenthal's experiments to say that strychnine quickened the transmission of impulses along those fibres in the spinal cord which connect the different cells together.

The impulses which normally, by travelling further round, fell behind the simple motor ones by half a wave-length, and thus inhibited them, would now fall only a small fraction of a wave-length behind, and we should have stimulation instead of inhibition.

Wundt's conclusion, on the other hand, would lead to the

---

[1] *Brain*, vol. iv. p. 313.

[2] Eckhard, Hermann's *Handb. d. Physiol.*, Band ii. Th. 2, p. 43.

[3] Bernstein, quoted by Eckhard, *op. cit.* p. 40. Walton, Ludwig's *Arbeiten*, 1882.

same result by supposing that the inhibitory wave was retarded so as to fall a whole wave-length behind the motor one. On the assumption, however, that the fibres which pass transversely across from sensory to motor cells, and those that pass upwards and downwards in the cord connecting the cells of successive strata in it, are equally affected, we do not get a satisfactory explanation of the rhythmical nature of the convulsions. By supposing, however, that these are not equally affected, but that the resistance in one—let us say that in the transverse fibres—is more increased than in the longitudinal fibres, we shall get the impulses at one time thrown completely upon each other, causing intense convulsion, at another half a wave-length behind, causing complete relaxation, which is exactly what we find.

This view is to some extent borne out by the different effect produced by a constant current upon these convulsions, according as it is passed transversely or longitudinally through the spinal cord. Ranke found that when passed transversely it has no effect, but when passed longitudinally in either direction it completely arrests the strychnine convulsions, and also the normal reflexes which are produced by tactile stimuli.

Ranke's observations have been repeated by others with varying result, and this variation may, I think, be explained by the effect of temperature.

The effect of warmth and cold upon strychnine-tetanus is what we would expect on the hypothesis of interference. With small doses of strychnine, warmth abolishes the convulsions, while cold increases them. When large doses are given, on the contrary, warmth increases the convulsions, and cold abolishes them.[1]

We may explain this result on the hypothesis of interference in the following manner:—

If a small dose of strychnine retard the transmission of nervous impulses so that the inhibitory wave is allowed to fall rather more than half a wave-length, but not a whole wave-length, behind the stimulant wave, we should have a certain amount of stimulation instead of inhibition. Slight warmth, by quickening the transmission of impulses, should counteract this effect, and should remove the effect of the strychnine. Cold, on the other hand, by causing still further retardation, should increase the effect. With a large dose of strychnine, the transmission of the inhibitory wave being still further retarded, the warmth would be sufficient to make the two waves coincide, while the cold would throw back the inhibitory wave a whole wave-length, and thus again abolish the convulsions.

The effect of temperature on the poisonous action of guanidine is also very extraordinary, and is very hard to explain on the

[1] Kunde and Virchow, quoted by Eckhard, *op. cit.* p. 44; Foster, *Journal of Anatomy and Physiology*, November 1873, p. 45.

ordinary hypothesis, although the phenomena seem quite natural when we look at them as cases of interference due to alterations in the rapidity with which the stimuli are transmitted along nervous structures.

Another cause of tetanus that is difficult to understand on the ordinary hypothesis of inhibitory centres is the similar effect of absence of oxygen and excess of oxygen. When an animal is confined in a closed chamber without oxygen, it dies of convulsions; when oxygen is gradually introduced before the convulsions become too marked, it recovers. But when the pressure of oxygen is gradually raised above the normal, the animal again dies of convulsions. This is evidently not the effect of mere increase in atmospheric pressure, but the effect of the oxygen on the animal, inasmuch as twenty-five atmospheres of common air are required to produce the oxygen-convulsions, while three atmospheres of pure oxygen are sufficient. This effect is readily explained on the hypothesis of interference by supposing that the absence of oxygen retards the transmission of impulses in the nerve-centres; so that we get those which ought ordinarily to inhibit one another coinciding and causing convulsions. Increased supply of oxygen gradually quickens the transmission of impulses until the waves first reach the normal relation, and then, the normal rate being exceeded, the impulses once more nearly coincide, and convulsions are produced a second time.[1]

The effect of various agents also in arresting or inhibiting muscular action suggests the possibility that such inhibition is due to interference with vibrations in muscle. The vibrations of the parts which occur in the muscle during the passage of a constant current have already been mentioned. When a constant current is passed for a length of time and then stopped, tetanic contraction of the muscle occurs and lasts for some time, but it can be at once arrested by again passing the constant current through the muscle.

The idea that coincidence or interference of contractile waves in muscle have much to do with the presence or absence of contraction of a muscle has been advanced by Kühne, in order to explain the phenomenon observed by A. Ewald. When the sartorius of a frog is stimulated at each end by electric currents passing transversely through the ends, the secondary contraction which can be obtained from it is strongest in the middle of the muscle, while the points exactly intermediate between the middle and the end do not produce any secondary contraction at all. This absence of secondary contraction Kühne thinks is due to

[1] For other observations on interference as a cause of inhibition, *vide* Wundt, *Untersuchungen zur Mechanik der Nerven und Nervencentren*. 1876. (Stuttgart: T. Enke); Ranvier, *Leçons d'Anatomie Générale*. *Année* 1877–78. (Paris: J. B. Baillière et Fils); and Lauder Brunton 'On the Nature of Inhibition and the Action of Drugs upon it' (*Nature*, March 1883, and reprint).

interference, and the powerful secondary contraction from the middle to coincidence of waves.[1]

Inhibition may also be produced by direct irritation of involuntary muscular fibre. Thus I have noticed, under Ludwig's direction, that stimulation of veins as a rule very frequently causes dilatation at the point of irritation, and if the muscular fibre of a frog's heart be injured by pinching at one point, that point is apt to remain dilated when the rest is contracted. Protoplasmic structures appear to be similarly affected, and the passage of an interrupted current through the heart of a snail will arrest its rhythmical pulsations, although the heart in this animal appears to be a continuous protoplasmic structure and destitute of nerves.[2]

Stimulating Action of Drugs on the Reflex Powers of the Cord.

The reflex action of the cord is greatly increased by certain drugs, more especially by ammonia and by strychnine. The action of strychnine was first investigated by Magendie, and his research is not only the first example of the systematic investigation of the physiological action of a drug leading to its therapeutical employment, but is such a model of this method of research that it is worth giving in detail.

He first introduced a little of the upas poison, of which strychnine was the essential ingredient, under the skin of the thigh of a dog, and found that for the first three minutes no symptoms at all were produced. Then the action of the poison began to manifest itself by general malaise, succeeded by marked symptoms. The animal took shelter in a corner of the laboratory; and almost immediately afterwards convulsive contraction of all the muscles of the body occurred, the fore-feet quitting the ground for a moment on account of the sudden extension of the spine. This contraction was only momentary, and almost immediately afterwards ceased; the animal remained calm for several seconds, and was then seized with a second convulsion, more marked and prolonged than the first. These convulsions succeeded each other at short intervals, gradually becoming more severe. The respiration was hurried, the pulse quick, and it was observed that each time the animal was touched a convulsion immediately followed. Finally, death occurred at an interval increasing with the age and strength of the animal.

These symptoms suggested to Magendie the following explanation of the action of the poison.

It was, he thought, absorbed from the wound into the blood,

[1] *Untersuchungen a. d. Physiolog. Inst.*, Heidelberg, 1879. *Sonderabdruck*, p. 40.

[2] M. Foster, *Pflüger's Archiv*.

by which it was carried to the heart, and thence to all the organs of the body. On arriving at the spinal cord, it acted upon it as a violent excitant, producing the same symptoms as mechanical irritation or the application of electricity. Magendie was not content until he had tested his theory by experiment. The first question to be settled was **whether the poison was absorbed or not.**


To test this supposition he applied the poison first to the serous membranes, the peritoneum and pleura, from which, as he had learned by previous experience, absorption takes place with extreme rapidity. The result showed that his supposition was correct. The symptoms appeared almost immediately after the injection of the poison into the pleura, and within twenty seconds after it had been injected into the peritoneum. In order to ascertain whether absorption took place from mucous as well as from serous surfaces, he isolated a loop of small intestine by means of two ligatures, and injected a little of the poison into the part between them. In six minutes, symptoms of poisoning appeared, showing that absorption had occurred, but they were less intense than when the poison was applied to the serous surface.

Further experiments showed that absorption took place from the large intestine, from the bladder, and from the vagina; but that it was comparatively feeble and slow. When introduced into the stomach along with food, upas invariably caused death; but the symptoms did not appear until half an hour after it had been taken. This delay might have been due either to absorption from the stomach having taken place very slowly or not at all, so that the drug had passed on to the small intestine, and thence been absorbed into the blood. To determine this point, he isolated the stomach by ligatures applied to its cardiac and pyloric orifices, and then injected a little poison into its cavity.

Under such conditions, symptoms of poisoning were only observed after the lapse of an hour. This showed that while absorption from the stomach did occur, it was much slower than from the small intestine.

The second question was, **Does the poison act through the circulation?** If so, reasoned Magendie, the first symptoms of the action of the poison will come on more slowly when it has far to travel to the spinal cord from the point of introduction and *vice versâ*. On testing this by experiment, he found that when the poison was injected into the jugular vein, tetanus occurred almost instantaneously, and death took place in less than three minutes, for the upas had only to pass through the pulmonary circulation and heart to the arteries of the cord. When injected into the femoral artery (at D, Fig. 66) the distance to be travelled before reaching the cord would be greatly increased, for the poison must first pass through the artery itself

hrough the capillaries, and along the vena cava, traversing the vhole distance marked D A B in Fig. 66 before it reached the oint where it entered the circulation when it was injected into he jugular. Under these conditions the action should be slow, nd experiment showed this to be actually the case, for no ymptoms appeared until seven minutes after the injection. lthough these experiments of Magendie's appear to prove com-letely that the upas poison acts through the circulation, a umber of persons nevertheless considered that the symptoms ere produced through the nervous system by means of so-called ympathy. In order to remove their doubts, Magendie narcotised dog by means of opium, and then divided all the structures of ne leg with the exception of the artery and vein. Into this



G. 66.—Diagram illustrating Magendie's method of investigating the mode of action of upas (strychnine). A, femoral vein; B, peritoneum; C, pleura; D, femoral artery; E, F, G, spinal cord, to which small arteries are seen passing from the aorta. At F is indicated a point of section of the cord.

lmost isolated limb he then introduced a little of the poison. his was followed by the usual symptoms almost exactly as if ne limb had been intact. By pressing upon the vein which assed from the limb to the body when the symptoms of tetanus ppeared he was able to arrest their further development, and by eleasing the vessel and allowing the circulation to have free ourse the symptoms reappeared. Lest by any chance the oison might have acted through nerves or lymphatics contained n the walls of the artery and vein, he divided these structures lso, connecting their several ends by means of quills through hich circulation then took place. When the poison was applied o the severed limb connected with the body only by these quills, ne same succession of phenomena occurred as when the limb as uninjured. The possibility of the action being due to ympathy between the nervous system and the point of applica-on of the poison was thus completely excluded, and the opera-on of the poison through the circulation triumphantly demon-rated.

The next question was **whether the convulsions were aused by the action of the drug on the brain or the cord.**

To ascertain its action upon the brain, a little of the solution was injected into the carotid artery. The effects produced were the same as those of any irritating liquid. The intellectual faculties disappeared, the head was laid between the paws, and the animal rolled over and over like a ball. These effects passed off as the circulating blood removed a quantity of the drug from the brain, and were succeeded by the ordinary tetanic convulsions when sufficient time had elapsed for it to reach the spinal cord. The question **whether it really acted upon the cord** still remained to be put to a crucial test. If its effects were really due to its action upon the spinal cord they ought to cease upon the destruction of that part of the nervous system, and to occur when the drug was applied to it alone. The cord was therefore destroyed by running a piece of whalebone down the vertebral canal at the moment of injection. When this was done, no tetanus occurred. In another experiment, Magendie waited until the tetanic spasms had been induced by the upas, and then destroyed the spinal cord by slowly pushing the whalebone down the vertebral canal. As the whalebone advanced, the tetanus disappeared, first in the fore-legs, when the dorsal part of the cord was destroyed, and then in the hind-legs, when the whalebone had reached the lumbar vertebræ.

In another experiment, an animal was narcotised by means of opium, and the spinal canal laid freely open. The upas was then directly placed on a part of the spinal cord. Tetanus immediately occurred in that part of the body, and in that part only to which the nerves arising from this portion of the cord were distributed. When the poison was successively applied to other parts of the cord, the convulsions spread to the corresponding regions of the body.

The question **whether a drug exercises a convulsant action through the brain or spinal cord** is now frequently tested, not by destroying the whole cord as Magendie did, but simply by dividing the spinal cord transversely between the occiput and the atlas. Convulsions depending upon stimulation of the motor centres in the brain and medulla oblongata then cease after section, while those dependent upon the spinal cord do not.

The experiment of dividing the spinal cord transversely about its middle is also sometimes performed in order to test whether the convulsions are of really spinal origin. If they are, they should persist in both the anterior and posterior parts of the body, but if they are of cerebral origin, they occur in the anterior but not in the posterior part.

The effect of strychnine and allied substances upon the cord is usually ascribed to increased excitability of the nerve-cells, but it is not improbably due partly to alteration in the comparative rate at which stimuli are transmitted from one cell to another

but this subject has already been more fully discussed under 'Inhibition' (*q.v.*, p. 173 *et seq.*).

Some curious results obtained by Dr. A. J. Spence may be explained on the latter hypothesis which would be inexplicable on the former. After removing the blood from the body of a frog, and exposing the brain, he placed some nux vomica upon it, so that it could gradually diffuse along the spinal cord. As it passed downwards he observed that, at first, irritation of the fore-feet caused spasm only in them; later it caused spasm of both front and hind-feet, while irritation of the hind-feet still produced the ordinary reflex; and later still irritation of the fore-feet caused no spasm in the hind-legs while irritation of the hind-feet would still cause spasm in the fore-legs.[1]

The action of strychnine on the conducting power of the spinal cord has already been discussed. It **diminishes** or abolishes the power of **summation**, but **increases** the **reflex** excitability, so that stimuli will produce reflex action which are too feeble to do so when the spinal cord is in its normal condition. The difference between the reaction to strong and weak stimuli is also to a great extent abolished, and both produce tetanic contractions. This condition, however, is absent for a short time after the application of each stimulus, and then strong and weak stimuli produce corresponding strong and weak action, much as in the normal cord.[2]

The effect of nicotine as a spinal stimulant is very extraordinary; for Freusberg found that when frogs had been decapitated for twenty-four hours, and reflex action was almost entirely gone, the injection of a small quantity of the poison increased the reflex excitability so much that irritation of the skin caused well-marked movements. This increase lasted from one to three days, and the bodies of frogs poisoned by nicotine retained a fresh appearance for a long time.

Spinal Stimulants.

Spinal stimulants are remedies which increase the functional activity of the spinal cord.

Ammonia.	Thebaine.
Strychnine.	Gelsemine.
Brucine.	Buxine.
Absinthe.	Calabarine.
Nicotine.	Caffeine.

The most marked of these are strychnine, brucine, and thebaine, which in small and moderate doses greatly increase the

[1] *Edin. Med. Journ.*, July 1866.
[2] Ludwig and Walton, *Ludwig's Arbeiten*, 1882.

reflex excitability, and in large doses cause tetanic convulsions. Besides these there are some others, such as opium, morphine, and belladonna, which, although they appear at first to have a sedative action, when given in very large doses produce convulsions.

Uses.—The want of an exact knowledge of the intimate pathology of diseases of the spinal cord renders the rational use of spinal stimulants difficult. They are employed in the cases of general debility without any evidence of distinct disease, and in paralysis where there is no evidence of inflammation: this paralysis may be local, or affect the whole side of the body, as in hemiplegia, or the lower half, as in paraplegia.

When strychnine is given in cases of paralysis until it begins to exhibit its physiological action in slight muscular twitches these twitches begin soooner and are more marked in the paralysed than the healthy parts.

CHAPTER VIII.

ACTION OF DRUGS ON THE BRAIN.

We are able to judge to a certain extent of the order and kind of action of drugs upon the different parts of the nerve-centres by watching their effect upon the movements of animals after their injection.

Functions of the Brain in the Frog.

By removal of successive portions of the nervous system in the frog, Goltz has shown that the **cerebral lobes** have the function of voluntary movement, so that when they are removed, the animal lies quiet, unless acted upon by some external stimulus.

The **optic lobes**, which correspond to the corpora quadrigemina of the higher animals, have the function of directing and co-ordinating movements, but not of originating them, so that a frog in which they are uninjured, but from which the cerebral lobes have been removed, will remain perfectly quiet, except on the application of an external stimulus, when it will leap like a normal frog.

As the optic lobes have the power of directing and co-ordinating movements, when they are destroyed the animal will jump, but will be unable to direct its movements.

The **cerebellum** has also the power of co-ordination, so that when it is removed the animal cannot jump at all, although one leg may answer by a kick or other motion to the application of a stimulus. But even when all those parts have been removed, the frog will still recover its ordinary position after it has been laid upon its back.

The co-ordination requisite for this power of retaining or recovering its ordinary position appears to be situated in the medulla oblongata, for when this is removed the frog will lie upon its back, and will not attempt to recover its ordinary position.

The legs will still respond by movements to irritation applied to the foot, but when the **spinal cord** is now destroyed these reflex movements also cease.

In frogs poisoned by opium, the movements are gradually

abolished in the order just mentioned, and we therefore conclude that opium affects the nerve-centres in the order of their development, the highest being paralysed first, and the lowest last (p. 172). This order is usually not quite the same in higher animals, inasmuch as the last centre to be paralysed by opium or other anæsthetics is usually the medulla oblongata, and more especially that part of it which keeps up the respiratory movements. As we shall afterwards see, however, the respiratory centre is really a lower or more fundamental centre than either the brain or spinal cord.

Functions of the Brain in Mammals.

In higher animals, such as rabbits and guinea-pigs, the cerebral hemispheres are comparatively much more developed than in the frog, and their removal interferes very much with the animal's motions. At first it is utterly prostrate, but after some time its power of movement returns to some extent, though it




FIG. 67.—Diagram of the higher nerve-centres of the frog.

remains much less than in the normal animal. As we should expect, the weakness is most marked in those parts of the body that are most under the control of the cerebrum, and least in those whose movements are regulated by the lower centres. Thus in rabbits the fore-paws are capable of being used for complex motions at the will of the animal, such as washing the face, holding food, and so on, and in them the weakness caused by removal of the cerebrum is much more marked than in the hind limbs, which are simply used for progression. After the operation the animal can still stand, although it is unsteady, and the fore-legs tend to sprawl out. When pinched it bounds forward, but, unlike the frog, it is unable to avoid any obstacle in its path.

FIG. 68.—Brain of monkey, showing the position of the motor and sensory centres as ascertained by Ferrier. The actions all occur on the side of the body opposite to the part of the brain irritated.

If it be pinched at all severely, it not only moves, but will cry loudly and plaintively, and this condition is frequently noticed in rabbits under chloroform, although they have received no injury whatever. The pupils contract on the stimulus of light, and the eyes wink if the finger is brought near them. Bitter substances cause movements of the tongue and mouth, and ammonia applied to the nostrils may cause the head to be drawn back, or the animal to rub its nostrils with its toes.[1]

Where the cerebral hemispheres are still more developed, as in cats, dogs, and monkeys, their removal causes so much prostration, and interferes so greatly with motor power as almost entirely to destroy equilibrium and co-ordinated progression.

The motor and sensory centres of the brain have been more exactly localised in monkeys by Ferrier, Fritsch, Hitzig, and others, and the results of their experiments, especially those of Ferrier, agree so well with those of pathological observation in men that we may assume that there is a general agreement between the position of the centres in man and monkey.

The **motor centres** are arranged along the two sides of the fissure of Rolando, the order of their arrangement being exactly what is required for the purpose of (1) seeing food; (2) conveying it to the mouth; (3) masticating it; (4) throwing away the refuse; and (5) advancing to get more[2] (*vide* Fig. 68, brain of monkey).

The **sensory centres** lie in the posterior and lower parts of the brain. The centre for sight is situated in the angular gyrus and is marked 14 and 15 in the diagram; that for hearing is situated in the superior temporo-sphenoidal and is marked 16 in the diagram; those for smell and taste lie at the tip of the temporo-sphenoidal lobe, and the centre for general sensation appears to be towards the interior of the brain, in the hippocampal region.

When the motor centres in the monkey are slightly irritated by a faradaic current, a single co-ordinated movement is produced, but if the irritation be continued longer, and especially if a strong current be used, epileptiform convulsions may occur, succeeded by choreic movements after the current has ceased. Epileptic convulsions are easily produced by irritation of the cerebral cortex in the cat and dog as well as the monkey. It is difficult to produce them by cortical irritation in the guinea-pig or rabbit, and impossible in birds, frogs, and fishes.[3]

---

[1] Ferrier, *Functions of the Brain*, p. 38.

[2] Lauder Brunton 'On the Position of the Motor Centres in the Brain in regard to the Nutritive and Social Functions,' *Brain*, vol. iv. p. 1.

[3] François-Franck and Pitres, *Arch. de Physiol.*, July 1883, p. 39.

Depressant Action of Drugs on the Motor Centres.

The **excitability of the brain** may be altered either by conditions which modify the nerve-cells or the circulation. A deficient circulation greatly depresses the excitability, and it is very low when much hæmorrhage has occurred.

One method of investigating the action of drugs on the excitability of the brain consists in trephining so as to expose the cortical substance and then stimulating it by a faradaic current before and after the administration of a drug either by inhalation or injection. Another method has been employed by Albertoni, who first trephines on one side, and having estimated the strength of current sufficient to produce an epileptic convulsion when applied to a motor centre, he allows the wound to heal, and then gives for a length of time the drug on which he wishes to experiment. He then exposes the corresponding motor area on the other side and observes whether the strength of current required to produce an epileptic convulsion is greater or less than before.

The excitability of the motor centres is greatly lowered by anæsthetics, so that as anæsthesia becomes deeper, irritation of the motor centres has less and less effect, and when anæsthesia is very profound, such irritation has no action whatever.[1] The motor centres, however, are less affected than the sensory ones by anæsthetics, so that they will still react to faradaic irritation when the sensation of pain has been completely abolished.

Alcohol also diminishes the excitability of the motor centres, so that the epileptic convulsions which usually follow the application of strong currents to the cortex are less readily produced after its administration, as well as after ether and chloroform.[2] Chloral for a time diminishes the excitability of the brain, lengthening the latent period, so that stronger currents or more numerous stimuli must be used to produce a result: it will temporarily abolish the excitability. Cold (not freezing) greatly lowers or destroys excitability, and this may be followed by a period of increased excitability with a shorter latent period.[3]

Bromide of potassium, according to Albertoni, when given for several weeks together, greatly diminishes the excitability of the motor centres, so that when dogs are thoroughly under its influence it is almost impossible to produce epileptic convulsions by

[1] This was observed in the case of ether by Hitzig, *Untersuchungen über das Gehirn*, Berlin, 1874. I have had several opportunities of observing the same thing in regard to chloroform when assisting my friend Dr. Ferrier in experiments on the brain.

[2] François-Franck and Pitres, *op. cit.*

[3] De Varigny, *Recherches expérimentales sur l'excitabilité électrique des circonvolutions cérébrales et sur la période d'excitation latente du cerveau.* Paris, 1884, p. 138.

irritation of the cortical substance. Atropine in small doses increases the excitability of the brain in monkeys, but in large doses paralyses it. It greatly increases the tendency to epileptic convulsions in dogs, so that they can be produced by very much slighter stimuli than usual, and strychnine, absinthe, and cannabin have a similar action in this respect.[1] Physostigmine appears to increase the excitability of motor centres in the brain; for when guinea-pigs have been rendered epileptic by section of a sciatic nerve, the administration of physostigmine greatly increases the number of fits.

Irritant Action of Drugs on Motor Centres in the Brain.

Certain drugs when administered to animals or taken by man produce **convulsions.** The muscular actions which occur in these convulsive movements may be induced by (*a*) irritation of the motor centres in the spinal cord, (*b*) the motor centres in the medulla oblongata and pons Varolii, or (*c*) cerebral cortex. These centres may be irritated directly by the action of the drug upon them, or they may be stimulated indirectly by the drug causing the blood in them to become venous through its action on the respiratory or circulatory organs. Convulsions of this sort, although caused by the administration of a poison, are really asphyxial, and are similar in character to those produced by suffocation.

Convulsions are usually ascertained to be of **spinal** origin by dividing the cord either at the occiput or lower down in its course and finding that they still persist in those parts of the body which derive their innervation from the spinal cord below the point of section. If they cease in parts of the body innervated by the spinal cord alone, but continue in the parts which retain their nervous connection with the brain, they are regarded as of **cerebral** origin (*v.* p. 179).

It has already been mentioned that irritation of the motor areas in the cortex of the brain will produce epileptic convulsions, but it is probable that such cortical irritation acts through lower ganglionic centres and especially through the medulla oblongata and pons Varolii. Epileptic convulsions can be still more readily produced by irritation of this part of the brain than by irritation of the cerebral cortex, and may be induced by a slight lesion of the pons and medulla by a needle. It is to irritation of this part of the brain by venous blood that asphyxial convulsions are due, for they can still be induced by suffocation or by ligature or compression of all the arteries leading to the brain after all the parts of the brain above the pons have been removed, and they cease when the spinal cord is divided just below the medulla, or the medulla itself

[1] François-Franck and Pitres, *op. cit.*

divided at its lower end. It is evident that, if the spinal cord be paralysed, the convulsions will not occur though the medulla and pons be irritated; and it has been found that, if its blood-supply is stopped at the same time as the circulation in the pons by ligaturing the aorta in place of the cerebral vessels alone, convulsions do not occur. Probably the absence of convulsions in slow asphyxia is due, at least in some degree, to gradual paralysis of the cord by the long-continued circulation of venous blood through it.

The centre for convulsions in the frog appears to be in the medulla oblongata.

Asphyxial convulsions are usually of an opisthotonic character, because, all the muscles being stimulated at once by the action of the venous blood on the motor centres, the stronger overpower the weaker, and the extensor muscles of the back being more powerful than the flexors bend the spine backwards. Asphyxial convulsions only occur in warm-blooded animals and not in frogs, where the respiratory processes are slow, and entire stoppage of the respiration for a length of time does not render the blood sufficiently venous to act as a powerful irritant. If any drug therefore produces convulsions in the higher animals and not in frogs, the probability is that its convulsive action is indirect and the convulsions it produces are asphyxial. If, on the other hand, it produces convulsions in frogs as well as higher animals, its convulsive action is in all probability due to the direct effect of the drug upon the nerve-centres. In order to ascertain this definitely, however, the usual plan is to see (1) whether the convulsions which occur after the drug has been injected disappear when artificial respiration is commenced, and (2) whether these convulsions are prevented by artificial respiration begun before the injection of the drug and kept up during its action. But even this does not entirely show whether the convulsive action of a drug is direct or indirect, for artificial respiration will not prevent asphyxial convulsions if these should depend upon the action of the drug in stopping the heart and thus arresting the circulation. If it is found that the convulsions occur very shortly after the heart stops, the usual plan is to paralyse the vagus in the heart by atropine, and ascertain whether the convulsive action then occurs. If the drug still produces convulsions when respiration is kept up and the heart is not stopped, it is almost certain that its action is direct upon the nerve-centres.

Experiments to ascertain whether convulsions are asphyxial or not may be conveniently made upon fowls, for the venous or arterial condition of the blood is readily ascertained by the colour of the comb. Thus, in fowls killed by cobra poison, the convulsions come on at the moment the comb becomes livid, and when artificial respiration is begun the convulsions disappear as the comb again regains its normal colour. It is evident that the

colour of the comb will indicate the condition of the blood supplying the brain, even though a venous condition of it should be due to stoppage of the heart and not to failure of the circulation.

Camphor has a curious exciting action both upon the brain and upon the medulla. It produces first rapid succession of ideas, great desire to move, hallucinations which are generally agreeable, and a wish to dance and laugh. In animals it has a similar action, causing wild excitement and constant motion, succeeded by clonic epileptiform convulsions, during which death often occurs. Usually, if they survive the convulsions, they recover; but in man the convulsive stage may be succeeded by paralysis, coma, and death, the parts of the nervous system which are first excited being apparently finally paralysed. The action upon frogs is different from that on warm-blooded animals, for in them it produces such rapid paralysis both of the spinal and motor nerves that convulsions do not occur.

Among other drugs having a powerful convulsant action due to irritation either of the cortical centres or of the medulla and pons are picrotoxin (the active principle of *Anamirta cocculus* or *Cocculus indicus*), cicutoxine (the active principle of *Cicuta virosa*), and the active principle of the nearly-allied *Œnanthe crocata*, coriamyrtin (from *Coriaria myrtifolia*), digitaliresin and toxiresin, which are products of the decomposition of the active principles of digitalis.

The **method of localising** the parts of the brain upon which certain drugs exert a **convulsant action**, consists in **extirpating** some of the **motor centres** and then giving these drugs, such as picrotoxin, cinchonidine, and quinine,[1] which produce epileptic convulsions.[2] The results of these experiments are that the epileptic convulsions produced by these poisons appear to have a twofold origin, (*a*) in the brain, and (*b*) in the medulla, the centre in the brain being the most sensitive to the action of the poison. In consequence of this, when the poison is given after the destruction of the motor centres on one side in such quantities as not to cause general convulsions, the weakness of the opposite side, due to the lesions, becomes still more evident, probably from the motor excitability of the sound side being increased. When convulsions are produced they are unsymmetrical. Those of the sound side are much stronger, are generally clonic, and apparently arise from irritation of the cerebral centres. Those of the paralysed side are much weaker, are more tonic, and apparently arise from irritation of the medulla.

---

[1] I have seen a case in which an epileptic convulsion appeared to be caused by medicinal doses of quinine.

[2] Rovighi e Santini, *Publicazioni del R. Instit. di stud. superiori in Firenze. Sezione di scienze fisiche natur.* 1882, s. 1.

ACTION OF DRUGS ON THE SENSORY AND PSYCHICAL CENTRES IN THE BRAIN.

The effect of drugs upon the higher mental functions can only be ascertained satisfactorily in man. These functions vary in complexity from simple choice to the highest efforts of genius.

The effect of drugs upon the **time required** for **mental processes** is observed by ascertaining, first, the time required for the performance before and after the administration of a drug, and comparing these two times with one another.

The processes generally investigated are, (*a*) the time required for simple reaction; (*b*) for discrimination; (*c*) for decision. The **simple reaction** is ascertained by marking on a chronograph the time when a signal is made, such as, for example, the exhibition of a coloured flag. As soon as this is seen by the individual experimented upon he marks the time upon the same chronograph by placing a finger upon a key which is connected with the registering electro-magnet. The difference of time between the exhibition of the flag and the time registered by the electro-magnet is equal to the time required for the transmission of the sensory impulse to the brain, for its transmission from the sensory to the motor tracts of the brain, for its passage down the motor nerves, and the latent period of the muscles.

The time required for selection is ascertained in the same way, but either a red or blue flag may be shown, and the person experimented upon has to discriminate between them, and only to press when the one previously agreed upon is shown. The difference between the time of this experiment and the former gives the time required for **discrimination**.

The time required for **decision** is ascertained in the same way as the previous one, excepting that a different signal is to be made on the appearance of the red and of the blue.

Simple reaction has been found by Kraepelin[1] to be little affected by nitrite of amyl: sometimes it is a little quicker and sometimes a little slower than normal. It is rendered slower by ether and much slower by chloroform, although exceptionally it may be quickened by chloroform, probably when used in small doses.

The time required for discrimination is not definitely affected by nitrite of amyl, being sometimes increased and sometimes diminished. It is generally increased, though it may be diminished, by small doses of ether and also by chloroform.

The time for decision is sometimes increased and sometimes diminished by nitrite of amyl. It is increased by ether and also

[1] Kraepelin, *Ueber die Einwirkung einiger medicamentosen Stoffe auf die Dauer einfacher psychischer Vorgänge*, 1882. Abstract in *Rivista Sperimentale di Freniatria*, anno ix. 1883, p. 124.

by chloroform; and if the quantity given be great, the increase may be very large.

The influence of alcohol upon psychical processes is curious; for while it renders them much slower, the individual under its influence believes them to be much quicker than usual.

Drugs which increase the Functional Activity of the Brain.

Nerve Stimulants.

These are remedies which **increase** the **nervous activity** of the cerebro-spinal system. They are subdivided into those which act on the cerebrum, or cerebral stimulants, and those which affect the spinal cord, or spinal stimulants. Spinal stimulants have been already discussed (p. 181).

Cerebral Stimulants.

In popular language, the name of stimulant is generally applied to drugs which have the power to increase the activity of the brain. From their producing a feeling of comfort and mirth they are also called **exhilarants**. The functional activity of the brain, like that of other organs, depends upon the tissue-change which goes on in the cells and fibres which compose it, and the amount of tissue-change is regulated to a great extent by the quantity and quality of the blood supplied to the organ. A free supply of blood to the brain may be obtained by general excitement of the circulation, i.e. more powerful and rapid action of the heart and contraction of the vessels in other parts of the body driving blood into the brain, or by local dilatation of the cerebral arteries allowing blood more ready access to the brain, or by a combination of these factors.

Free circulation through the cerebral arteries may be induced to some extent by **posture**: thus, some men can think best when the head is low, and almost everyone naturally assumes the sitting posture with the head bowed down and held between the hands when suffering from the effects of mental depression. This posture is not, as is often supposed, merely consequent on the depressed condition of the nerve-centres, it is voluntarily assumed because it affords an actual sense of relief. In eager conversation also the body generally stoops forward and the head is held low so as to allow of a free supply of blood to the brain.[1]

This effect of posture on the human brain is admirably shown

[1] François-Franck et Brissaud, *Marey's Travaux*, 1877, tome iii. p. 147.

by a tracing taken from a patient with an aperture in the skull by François-Franck and Brissaud (Fig. 69).




FIG. 69.—Tracing showing the increased circulation in the brain caused by inclining the head and body forwards. The tracing was taken by Brissaud and François-Franck, from the parietal region of a woman who had lost a large piece of bone from syphilis.[1]

Local dilatation of the arteries of the brain appears to be produced in animals by the movements of **mastication** (Fig. 70) and probably also by savoury food or irritating substances in the mouth.




FIG. 70.—Tracing to show the increased rapidity of circulation in the carotid of a horse during mastication. (After Marey.)

It is probably on this account that so many substances are **chewed** for their stimulant action, such as tobacco, betel nut, cola nut, and raisins. The effect of smoking is probably to a great extent due also to its action on the cerebral circulation through the stimulating effect of the smoke on the nerves of the mouth and nares, and so is the use of alcohol in sips by men, such as jour-




FIG. 71.—Pulsations of the fontanelle (F) in an infant six weeks old while sucking. R shows a simultaneous tracing of the thoracic respiration. The breast was offered to the child at the beginning of the tracing. At the time indicated by the third respiratory wave, which has a flattened top, the child began to take the breast. It will be noticed that the line of the tracing F rises, indicating increased circulation on the brain. (After Salathé.)[2]

nalists, who are engaged in writing. It is probable that tea and coffee also cause local dilatation of the arteries supplying the

[1] *Marey's Travaux* for 1877, p. 147.
[2] Salathé, *Marey's Travaux*, 1876, p. 354.

brain. Suction also causes an increased supply of blood to the brain (Fig. 71).[1]

The effect of local dilatation of the cerebral vessels is very greatly increased, if in addition to it the general circulation is increased and the blood-pressure raised by contraction of the arterioles in the body generally, or by more vigorous action of the heart.

General excitement of the circulation is induced by **exercise** short of fatigue, and a brisk walk will sometimes remove a condition of low spirits. Sometimes the supply of blood to the brain is but slightly increased during continuous exercise, as a large portion of the blood is then diverted to the muscles, but after the exertion is over the excitement of the circulation continues for some time, and then the supply to the brain is increased. In some persons a cold wind acts as an exhilarant, causing contraction of the vessels, with consequent increase in the general blood-pressure and increased circulation in the brain. In persons who are debilitated and feeble, on the contrary, the cold may have an opposite effect, by depressing the action of the heart.

Some men can think best when walking about, on account of the excitement in the circulation which the exertion produces; but many such people, when they come to a very difficult point, will stand still or sit down, so as to allow the blood to flow more to the head and less to the muscles.

Where the circulation is feeble, so that the heart is not much stimulated by walking about, men often find that they can think better when lying down, or sitting with their head in their hands (Fig. 69), so as to gain the advantage of the greater flow of blood to the head in these positions.

Stimulation of the mucous membrane of the nose by smelling the vapour of strong ammonia, carbonate of ammonium, or acetic acid, raises the blood-pressure generally throughout the body by reflexly stimulating the vaso-motor centre, and thus increases the circulation of blood in the brain. Smelling salts or aromatic vinegar are therefore frequently employed, not only to enable people to attend more readily to any subject in which they are engaged, and to prevent them from falling asleep, but also to arouse them from syncope.

The action of **sipping** is a powerful stimulant to the circulation, for, as Kronecker has shown, the inhibitory action of the vagus on the heart is abolished while the sipping continues, and the pulse-rate is very greatly increased. A glass of cold water slowly sipped will produce greater acceleration of the pulse for a time than a glass of wine or spirits taken at a draught. Sipping cold water has been recommended to allay the craving for alcohol in drunkards endeavouring to reform, and probably its use is owing to this stimulant action on the heart. It is sometimes said that a single glass of ale sucked through a straw will intoxi

[1] Salathé, *op. cit.*

cate a man, although three times the quantity would not do so if taken in large draughts. If this be true, the more rapid intoxication caused by sucking is probably due to the conjoined effects of the alcohol and of temporary paralysis of the vagus caused by the suction, possibly aided by the direct effect of suction on the cerebral circulation (Fig. 71, p. 193).

One of the most typical stimulants is **alcohol**. In small quantities it increases the arterial tension by locally stimulating, first the sensory nerves of the mouth, and afterwards those of the stomach, and thus causing reflex contraction of the vessels and reflex acceleration of the beats of the heart. This effect occurs before its absorption, and is best marked when the alcohol is strong, and is but slightly marked when it is diluted. It is possible that by inducing local dilatation of the cerebral arteries while the heart still continues active, it may have a stimulant action on the cerebral functions, besides that which it induces by merely exciting the circulation generally.

Any stimulant action on the brain beyond what may be explained in this way is very slight, if indeed it exist at all. Its further actions are those of paralysis exerted on the nerve-centres in the order of their development, the higher centres being paralysed first (see p. 146).

At or about this point the stimulating action ceases and the narcotic action commences. The **exhilarating** effect of alcohol, however, may be most marked just at this point, because just here, while the circulation in the brain generally remains increased, the restraining or inhibitory parts of it begin to be paralysed. Thus, imagination and emotion are more readily excited and expression is free and unrestrained; external circumstances are less attended to, and a boyish or childish hilarity occurs.

It is probable that some substances, such as strychnine, increase the mental powers by a direct action on the brain-tissue itself, and possibly caffeine may do so also.

Drugs which lessen the Functional Activity of the Brain.

These drugs are soporifics or hypnotics; narcotics; anodynes or analgesics; and anæsthetics.

Most of the substances belonging to those classes have a certain resemblance to one another in their action. Most of them stimulate the mental functions when given in very small doses. In larger doses they have also a stimulating action at first, i.e. while a small quantity only has been absorbed, but later on they diminish or abolish the mental faculties. The same drug—as, for example, opium or alcohol—in different doses may thus act as stimulant, narcotic, soporific, and anæsthetic.

In a certain stage of their action opium and alcohol do not

merely lessen the functional activity of the brain, but they **disturb** the normal **relations** of one part to another, so as to produce disorder of the mental functions. Bromide of potassium, on the other hand, appears simply to lessen the functional activity of the brain without disturbing the relation of one part to another. We do not know what the causes of this difference in their action are, but with some degree of probability we may consider that such substances as bromide of potassium, or the normal products of tissue-waste, such as lactic acid, simply diminish the functional activity of the nerve-cells without disturbing the nervous paths by which they communicate with one another, so that we have merely a general and even diminution of the mental faculties, as in natural sleep. Such substances as alcohol, on the other hand, may be supposed not only to diminish the functional activity of the cells, but also to disturb the rate at which the impulses pass from one cell to another, or to alter the direction in which these impulses are sent, so that instead of the mental activity being lessened in degree but natural in kind, as after the administration of bromide of potassium, we have a disturbance of the functions resembling that which we find in delirium or madness.

Hypnotics or Soporifics.

These are remedies which **induce sleep.** Although many of them are also narcotic, yet we may distinguish between hypnotics and narcotics. Pure hypnotics are substances which in the doses necessary to produce sleep do not disturb the normal relationship of the mental faculties to the external world.

In sleep the cerebro-spinal system, with the exception of the medulla oblongata, is to a great extent functionally inactive, and even the respiratory centre and the vaso-motor centre in the medulla, undergo a diminution in their functional activity, so that the respiration becomes slower, the vessels of the surface dilate, and the arterial tension falls.

Certain parts of the nervous system may still remain functionally active, so that, for example, when the nose is tickled with a hair, reflex movements of the face or hand may occur without awakening the sleeper; and certain parts of the brain may also be active so that dreams occur, which may be afterwards remembered as distinctly as real occurrences, or may produce at the time various movements of the body.

But while individual parts may be active, the **whole cerebro-spinal system** is **not active together**, and thus any co-ordination which may occur between either sensations or motions is incomplete; the dreams are incoherent, and the motions do not affect the whole body, as is seen in sleeping dogs, where the legs make a movement of running, but the animal continues to lie on its side. The functional inactivity of the whole or of the greater

part of the cerebro-spinal system is associated with a condition of **anæmia**, and probably depends to a certain extent upon it. At the same time it is probable that sleep depends also on functional inactivity of the cerebral cells due to accumulation of the products of tissue-waste in or around them.

The arteries of the brain during sleep are contracted, the brain is anæmic, and its bulk is small. On awakening, the arteries become dilated, the circulation becomes rapid, and the brain increases in bulk. Where parts of the brain are active, as in dreaming, increased circulation occurs, but probably this is local and not general.

In considering the **circulation** of the brain, however, a marked distinction must be drawn between the condition of the arteries and veins. So long as the blood is in the arteries it is available for the nutrition of the nervous structures; but once it is in the veins it is no longer available, and its accumulation there will tend to impair nutrition, both by the pressure it exerts on the nervous structures, and by its interference with the supply of arterial blood.

In **normal sleep** the arteries and veins are both contracted, and the brain appears anæmic. In the very act of waking the brain may slightly contract, and this has been thought by Mosso, to whom we owe the observation, to show that sleep does not depend upon anæmia of the brain; but this contraction may be due to the removal of venous blood, preparatory to further arterial supply.

Observations on the brain by trephining appear to show that during ordinary sleep, whether it has come on naturally, or has been induced by narcotics, such as a small dose of opium, the brain is anæmic. During functional activity, either of the whole or of its parts, there is arterial dilatation, with a free supply of blood. During **coma** the veins become dilated and the brain congested.[1] This congestion, however, is utterly different from the arterial congestion of functional activity, for in coma the blood, though abundant in quantity, is stagnating in the veins, and useless for the tissues.

In order to produce sleep, then, two things are necessary:—

1st. To lessen the circulation in the brain as much as possible by diverting blood from it or quieting cardiac action.

2nd. To lessen the functional activity of the organ.

Blood may be **diverted** from the brain by dilating the vessels elsewhere. In weak conditions of the body, with feeble vascular tone, this may occur simply from **position**, and such persons become drowsy when standing or walking about, or when sitting. As soon as they lie down, however, the cerebral vessels having little or no tone, the blood floods the brain, and they are unable to sleep. In such persons, sleep may be sometimes obtained by

[1] Hammond, *On Wakefulness*, 1866, p. 20.

raising the head with high pillows. In such cases, also, vascular tonics, such as **digitalis**, by increasing the contractile power of the arteries leading to the brain, may enable them to resist the increased pressure in the recumbent position, and thus prevent the brain being flooded with blood and allow sleep to be obtained.




FIG. 72.—Tracings from the brain of a dog after trephining, showing the influence of position on the cerebral circulation. In the upper tracing the vertical line shows when the head of the dog was lowered, and in the lower tracing when the head was raised. (Salathé.)[1]

The largest vascular area into which the blood may be drawn away from the brain is that of the intestinal canal. When the vessels in the intestine are contracted, it is almost impossible to obtain sleep. Consequently both man and animals, when exposed to cold, which acting through the thin abdominal walls would cause contraction of the intestinal vessels and drive the blood to the brain, instinctively keep the intestines warm by curling themselves up before going to sleep, and thus covering the abdomen with the thick muscles of the thighs.

Warmth to the abdomen by means of a large poultice outside will also tend to produce sleep; or, in place of a poultice, a wet compress, consisting of linen or flannel wrung out of cold water, and covered with oil-silk, and with two thicknesses of dry flannel placed above it, tends greatly to induce sleep and is most useful for this purpose, especially in children.

Warmth to the interior of the stomach has a somewhat similar action, but it differs from warmth to the exterior in this, that it may, to a certain extent, stimulate the heart as well as dilate the abdominal vessels. Stimulation of the heart is of course objectionable, as it tends to maintain the activity of the brain.

On this account the food or drink should be tolerably warm, but not very hot. Warm milk, either alone, or with bread soaked in it, warm gruel, thin corn-flour, or ground rice, sago, or tapioca, warm beef-tea or soup, or a glass of hot wine and water or spirits and water at bed-time, may all act as soporifics by withdrawing the blood from the brain to the stomach. In the sleeplessness of fever a **wet pack**, by restraining the movements and by diverting blood from the brain to the body generally, is often an efficient soporific.

[1] *Marey's Travaux*, 1876, p. 397.

Cold feet also tend to keep up the tension in the vessels and prevent sleep, and therefore they ought to be warmed either by the use of an india-rubber bag filled with hot water, and covered with flannel, or by rubbing them briskly in cold water and drying them thoroughly before going to bed, or by both means combined.

Cardiac excitement may be lessened by sedatives, one of the most useful of which is **cold**. After hours of weary tossing sleep may sometimes be induced by walking about in a night-dress until cool, or by sponging the surface either with cold or hot water.

The **chief hypnotics** or soporifics are—

Opium.	Hypnone.
Morphine.	Bromide of potassium.
Chloral-hydrate.	Bromide of sodium.
Butyl-chloral-hydrate (croton-chloral).	Bromide of calcium.
Hyoscyamus.	Bromide of zinc.
Cannabis.	Monobromo-camphor.
Paraldehyde.	Hop.
Urethane.	Lettuce.
	Lactic acid.

The most powerful **hypnotics** that we possess are undoubtedly opium and morphine, and they seem to act by depressing the functional activity of the brain itself, although along with this depression an anæmic condition of the organ sets in. Besides their action in producing sleep, even in health opium and morphine have the power of lessening pain and thus removing the effect which painful stimuli have in maintaining a wakeful condition. Bromide of potassium and bromide of ammonium in large doses have also a hypnotic action, and even in smaller doses, when they would not of themselves produce sleep, they appear to lessen cerebral excitement, and allow sleep to come on when other conditions are favourable. Chloral probably causes sleep both by acting on the brain itself and by causing dilatation of the vessels generally. It is therefore a useful hypnotic in persons suffering from Bright's disease, in which there is high tension of the vessels and consequently a tendency to sleeplessness.

A **combination** of hypnotics sometimes answers much better than any one singly. Thus morphine or opium alone sometimes simply cause excitement; but when chloral is given, either along with, or after them, the excitement is quieted and sleep occurs.

A combination also of small quantities, such as five or ten minims, of solution of opium or morphine with five grains of chloral and ten to thirty of bromide of potassium, is sometimes more useful than any one of the three used alone.

Indian hemp also is sometimes used to procure sleep, and

lettuce and lactucarium are also said to have a hypnotic action. Lettuce certainly does seem to have such an action, but how much of it depends upon the juice and how much upon the mechanical effect of the indigestible fibres of the lettuce upon the stomach in drawing blood to it, it would be hard to say. Hops are said to be hypnotic, and their combination with lettuce in the form of a supper consisting chiefly of beer and salad has sometimes a very marked soporific action.

Narcotics.

Narcotics are substances which lessen our relationships with the external world. They are closely related, as I have already stated, to stimulants; and alcohol in the various stages of its action affords us a good example of both stimulant and narcotic action. Alcohol at first excites the cerebral circulation and then begins to paralyse various parts of the brain in the inverse order of their development.

But this order differs in different individuals; for in watching the growth of children we find that the order of development of the nerve-centres in them is not always the same: some talking before they can walk, and others walking before they can talk. In all, however, the powers of judgment and self-restraint are among the last to be completely developed.

While the circulation of the brain is still active, the restraining or depressing effect of present external circumstances, and the restraining effect of training, during previous life, which are stored up as it were in the inhibitory centres, are lessened. The fancy is thus allowed free play and a condition of joyousness and volubility like that of a child occurs. The imagination and memory fail next in some, while the emotions become prominent, and to this follows paralysis or paresis of the power of co-ordination. In others the power of co-ordination is impaired before the mental faculties are much affected, the speech becomes thick and the walking becomes staggering and uncertain. At this stage reflex action still persists, but afterwards it is diminished, then abolished, and finally paralysis of the respiratory centre occurs. The effect of other drugs, such as ether and chloroform, is much the same as that of alcohol.

In the case of opium and Indian hemp, however, there is but little excitement of the circulation, and their effects appear to be due more to alterations in the relative functions of the different parts of the brain.

Belladonna, hyoscyamus, stramonium, and their allies, have a curious effect. They produce delirium of an active character, the patient having a constant desire to speak, move about, or be doing something, while at the same time he feels great languor. It is probable that this effect is due to the combined stimulant

action of these drugs on the nerve-centres in the brain and spinal cord and their paralysing action on the peripheral ends of motor nerves.

Anodynes or Analgesics.

Anodynes are remedies which **relieve pain** by lessening the excitability of nerves or of nerve-centres. They are divided into local or general:—

Local Anodynes.	General Anodynes.
Cold—	Anæsthetics in small doses.
Cold water.	Atropine.
Ice-bags.	Belladonna.
Warmth—	Butyl-chloral.
Poultices.	Chloral.
Fomentations.	Conium.
Aconite.	Coniïne.
Acupuncture.	Gelsemium.
Atropine.	Hyoscyamus.
Belladonna.	Hyoscyamine.
Blood-letting—	Lupulus.
Leeches.	Lupulin.
Cupping.	Morphine.
Carbolic acid.	Opium.
Carbonic acid.	Stramonium.
Cocaine.	
Conium.	
Creasote.	
Gelsemium.	
Hydrocyanic acid.	
Morphine.	
Opium.	
Veratrine.	

Action.—The sensation of pain is due to a change in some part of the cerebrum, and is usually excited by injury to some part of the body.

According to Ferrier the hippocampal region is the seat of sensation. Pain may be of **central** origin; for if these convolutions should from any cause undergo changes similar to what usually take place in them on the application of a painful stimulus to a nerve, pain will be felt, even although no injury whatever has been done to the body. Something of this sort appears to occur in certain cases of hysteria.

Conversely, if the changes which ordinarily occur in these convolutions on severe irritation of a sensory nerve are prevented from taking place, pain will not be felt, however great the stimulus to the nerve may be.

The sensory nerves of the head pass directly to the brain, but

all other sensory nerves have to pass for a greater or less distance along the spinal cord before they reach the brain.

The transmission of painful impressions along the spinal cord occurs in the grey matter, and the effect of anæsthetics in preventing the transmission of painful impressions while tactile stimuli are still conducted has been already discussed.

Pain may be occasioned by irritation applied to nerves anywhere between the brain and the periphery; and whatever its point of application may be, it is usually referred to the **peripheral** distribution of the nerve. Sometimes irritation of a nerve, instead of being referred by the brain to the proper spot, is referred to a branch of the same nerve going to a different point.

Pain may be **caused** by violent stimulation of the peripheral distribution of a nerve, of its trunk, of the spinal cord through which the fibres pass to the brain, or of the encephalic centres themselves.

Pain may be **relieved** by (*a*) removing the source of irritation, (*b*) by preventing the irritation from affecting the cerebrum. Thus, if necrosis of the jaw should give rise to intense pain, the pain will at once cease on dividing the sensory nerve by which the impulses are transmitted to the brain. It may be relieved, also, while the source of irritation still remains, by lessening the excitability of the peripheral terminations of the sensory nerves which receive the painful impression; or of the nerve-trunks; or of the spinal cord along which the impression travels; or of the cerebral centres in which it is perceived.

Opium probably acts on them all, diminishing the excitability of the cerebral centre, of the spinal cord, and of the sensory nerves; and bromide of potassium is also supposed to affect all these structures, though to a much less degree than opium.

Chloral, butyl-chloral, lupulin, gelsemium, and cannabis indica probably act on the **cerebral centres.**

Belladonna and atropine lessen the excitability of the sensory nerves, and probably this is effected also by hyoscyamus, stramonium, aconite, aconitine, and veratrine.

Uses.—It is evident that if the nerve-centre by which pain is perceived is deadened, the pain will cease wherever its seat may be; and therefore opium and morphine are used to relieve pain whatever may be its cause. Cannabis indica and bromide of potassium, having likewise a central action, may also be employed, but they are very much less efficient than opium. Chloral and butyl-chloral have an anæsthetic action when given in very large doses, but in moderate doses their power to relieve pain is not so marked as their hypnotic action. Butyl-chloral, however, seems to have a special sedative action on the fifth nerve, and so has gelsemium: consequently both of them are used in the treatment of facial neuralgia.

As cocaine, belladonna, aconite, and veratrine have a **local** action on the peripheral ends of the sensory nerves, they are usually applied directly to the painful part in the form of lotion, ointment, liniment, or plaster. Local injections of cocaine, morphine, atropine, or ether, in the neighbourhood of the painful part, are often of the greatest service.

Adjuncts to Anodynes.—As pain depends on the condition of the cerebral centre by which it is perceived, as well as on irritation of sensory nerves, it is obvious that it may vary with the condition of these centres, although the irritation remains. Thus a decayed tooth does not always cause toothache, and when the toothache comes on, it may frequently be removed by means of a brisk **purgative**, even although the tooth be not extracted. It is possible that the purgative may act partly by lessening congestion around the tooth, but partly also by altering the condition of the cerebral centres. When the **attention** is fixed upon other things, also, the pain may be to a great extent, or even completely, abolished, as in mesmerism or hypnotism. The sensory stimuli, also, which would usually produce pain may be diverted voluntarily or involuntarily into motor channels. Thus, during the heat of action, the pain of a wound is not felt; and the pain felt during the extraction of a tooth is lessened by the employment of violent muscular effort, as in grasping the arms of the dentist's chair. Other most powerful adjuncts are **electricity** applied along the course of the nerves, and **counter-irritation**, especially by means of the actual cautery to the painful part, and, when other means fail, stretching the nerve may succeed.

Cold also, applied to the surface over a painful part, will relieve pain, and so may dry **heat**, applied by a sand-bag or hot cloth, or moist heat in the form of a poultice; for the mode of action of these *vide* 'ACTION OF IRRITANTS.'

Pain has been ascribed by Mortimer Granville to **vibrations of nerves** or of the sheaths; and, in order to lessen it, he proposes to produce vibrations of a different nature: this he does by percussing over the painful nerve with a small hammer, worked either by clockwork or electricity. For a dull heavy pain he uses quick and short vibrations of the hammer, and for a sharp lancinating pain he uses large and slow vibrations.

Anæsthetics.

Anæsthetics are remedies which **destroy sensation.**

It has already been mentioned that both sensation and pain require for their perception a certain condition of the cerebral centres and of the sensory nerves and spinal cord, by which impressions are conveyed to these centres.

The difference between anæsthetics and anodynes is to a great extent one of degree. Anodynes affect more particularly the

cerebral centres by which pain is perceived, or the conducting paths by which painful impressions are transmitted, and thus in moderate doses lessen pain without destroying reflex action. They only affect the ordinary centres for reflex action when the dose is considerably increased. Anæsthetics, on the other hand, affect the cerebral and spinal centres more equally, and so abolish pain, ordinary sensation, and reflex excitability more nearly at the same time, though their abolition is by no means completely simultaneous.

According to Eulenberg, in chloroform-narcosis the patellar reflex is abolished first, then reflex from the skin, then from the conjunctiva, and lastly from the nose. As the anæsthesia passes off they return in the inverse order, patellar reflex being the last to reappear. A stage of excitement generally precedes the disappearance of patellar reflex, both in man and animals.

Narcosis by ether differs from that of chloroform in the much greater increase of patellar and other tendon reflexes, both in extent and duration.

Chloral hydrate and potassium bromide have an action like chloroform, but much weaker. Like chloroform, they paralyse the patellar reflex before the corneal reflex, but butyl-chloral (croton-chloral) paralyses the corneal reflex before the patellar.

In ordinary sleep, reflexes disappear in the same order as in chloroform narcosis, but in mesmeric sleep the reflexes are increased as in narcosis from ether. In hysterical conditions diminution of the cerebral reflexes from the nose and cornea with persistence of the patellar reflex has been observed.

The reflex power of the vaso-motor centre is very quickly paralysed by chloroform, so that irritation of a sensory nerve will no longer raise the blood-pressure. Its reflex power is much less affected by ether.[1]

Anæsthetics may be divided into local and general. The **local** are those which abolish the sensibility of the peripheral nerves of a particular area. The **general** are those which act on the central nervous system in the way already described, and abolish sensation throughout the whole body.

The chief **local anæsthetics** are cold, cocaine, carbolic acid, iodoform.

For the purpose of producing local anæsthesia, cold is generally applied by means of ether spray, until the part is all but frozen and is insensible, when slight operations may be made without the patient feeling any pain. The ether may perhaps have itself a certain amount of physiological effect in diminishing sensibility when applied in this manner. Carbolic acid painted over the surface also causes it to become white and to lose its sensibility, and may thus be used to lessen the pain of opening an abscess.

[1] H. P. Bowditch and C. S. Minot, *Boston Med. and Surg. Journ.*, May 21, 1874.

General anæsthetics are—

Nitrous oxide.	Trichlorhydrin.
Ether.	Bi-chloride of methylene.
Chloroform.	Paraldehyde.
Bromoform.	Bi-chloride of ethidene.
Tetrachloride of carbon.	Bromide of ethyl.

With the exception of nitrous oxide they all belong to the class of alcohols and ethers, and the substitution-compounds having an anæsthetic action are probably almost indefinite in number. Even alcohol itself produces general anæsthesia when volatilised and inhaled.

General Anæsthetics may destroy the sensibility of the nerve-centres indirectly or directly. Anæsthesia is induced indirectly by **stopping** the **circulation** in the brain and thus arresting the process of oxidation and tissue-change in the nerve-cells which are necessary for their functional activity.

This result may be produced by draining the blood from the head into other parts of the body. Thus in some of the hospitals at Paris, before anæsthetics were introduced, a plan was sometimes employed of rendering a patient insensible before an operation, by laying him flat on the ground, and then lifting him very suddenly to a standing posture by the united efforts of six or eight men (*cf.* pp. 193, 198).

Local arrest of the circulation to the brain by ligatures or by compression of the arteries has a similar effect. Waller has recommended diminution of the cerebral circulation, by the combined effects of simultaneous pressure on the carotid arteries and vagus nerves, as an easy means of producing anæsthesia for short operations.

Slight anæsthesia, usually accompanied by some giddiness, may be produced by taking a number of deep breaths in rapid succession. This may be used in order to lessen the irritability of the pharynx in laryngoscopic examinations, and to lessen the pain of opening boils or abscesses. The anæsthesia thus produced may perhaps depend on anæmia of the brain, although this is not certain.

Anæsthesia may also be produced by **diminishing** the **internal respiration** of the nerve-cells through a gradually increasing venous condition of the blood. Thus gradual suffocation by charcoal fumes or carbon monoxide causes complete insensibility, and the inhalation of nitrogen and of nitrous oxide has a similar action.

Anæsthesia may be caused by the direct action of **drugs** on the **nerve-cells** themselves. Chloroform, ether, and other allied substances belonging to the alcohol series appear to act in this way. Although their action is generally exerted through the blood by which they are conveyed to the brain when inhaled, yet

they will also produce a similar action if locally applied to the nerve-centres. Thus Prevost[1] found that chloroform applied directly to the brain of a frog narcotises it when the aorta is tied. When the aorta is again unligatured, so that the current of blood can again wash the chloroform away, the narcosis disappears. Chloroform and ether when inhaled appear to act like alcohol, producing paralysis of the nerve-centres, commencing with the highest and proceeding downwards. The rate of paralysis, though the same in order, is more rapid than that caused by alcohol.

These anæsthetics are, however, not nerve-poisons only; they are **protoplasmic poisons** affecting simple organisms, such as amœbæ and leucocytes, and destroying also the irritability of muscular fibre.

This action of anæsthetics and especially that of chloroform upon muscular fibre is one of considerable importance in reference to the occasional stoppage of the heart and consequent death during the administration of anæsthetics.

The **action of anæsthetics** may be divided into **four stages**:—

1st. The stimulant stage.
2nd. The narcotic and anodyne stage.
3rd. Anæsthetic stage.
4th. Paralytic stage.

Stimulant Stage.—Chloroform and ether, as already mentioned, resemble alcohol in their action, and, like it, in small doses will produce a condition of stimulation and acceleration of the circulation passing gradually into one of narcosis, in which the action of the higher nervous centres is more or less abolished, while that of the lower centres still remains.

In small quantities chloroform and ether are sometimes taken, either internally or by inhalation, for their stimulant effect. They are useful in lessening pain and spasm, as in neuralgia, and biliary, renal, or intestinal colic, when given till the stimulant is just passing into the narcotic stage.

Narcotic Stage.—When pushed still further, sensibility becomes more impaired, reflex action still continues, and sometimes, just as in drunkenness, there is a form of wild delirium and great excitement. This is much less marked in feeble or debilitated persons than in strong men. In the latter, the struggles which occur in this condition are sometimes exceedingly violent, the patient raising himself forcibly from the couch, his muscles being in a state of violent contraction, the face livid, the veins turgid, and eyeballs protruding. Usually this condition quickly subsides and passes into the third stage—that of complete anæsthesia.

---

[1] Prevost *Practitioner* July 1881.

In order to lessen the pains of labour, anæsthesia is usually carried to the commencement of the second stage.

Anæsthetic Stage.—The third stage differs from the second, in the function of the spinal cord being abolished, as well as those of the brain; ordinary reflex is consequently abolished, and the most common way of ascertaining whether this stage has set in or not is by drawing up the eyelid and touching the conjunctiva. If no reflex contraction of the eyelid occurs, the anæsthesia is complete. By careful and judicious administration of the anæsthetic this condition may be kept up for a length of time even for hours, or days; but if the inhalation be carried too far, the anæsthetic passes into the fourth stage.

The third stage is the one employed for surgical operations.

Paralytic Stage.—In the fourth the respiratory centre becomes paralysed, respiration ceases, and the beats of the heart become feebler and may cease altogether.

Uses of Anæsthetics.

Anæsthetics are used not only to lessen pain but to relax muscular action and spasm. They are chiefly employed to lessen pain in surgical operations, in labour, and in biliary and renal colic. They are used to lessen muscular action and spasm in tetanus, in poisoning by strychnine, in hydrophobia, and in the reduction of dislocations, fractures, and hernia. They are also of assistance in diagnosis, by allowing careful examination to be made of parts which are too tender or painful to be examined without it, and by causing the phantom tumours due to spasmodic contraction of the muscles to disappear.

Dangers of Anæsthetics.—(1) One danger is that just mentioned, of **paralysis** of the **respiration** from an overdose. This, however, is one of the least of the dangers, and if the enfeeblement of the respiration be observed in time, it is generally possible to save the patient by stopping inhalation, and keeping up artificial respiration for a little while if necessary.

(2) Another danger is from **paralysis** of the **heart** by a too concentrated chloroform vapour. This is indicated by a sudden stoppage of the heart, paleness of the face, and dilatation of the pupil while the respiration may continue.

If this accident should occur, the body of the patient should be inclined so that the head should be lower than the feet, and artificial respiration should be kept up briskly but regularly, the expiratory movements being made by pressure on the thorax and especially over the cardiac region, so that the mechanical pressure should stimulate the heart, if possible, to renewed action. The vapour of nitrite of amyl may also be administered by holding a piece of blotting-paper or cloth on which a few drops have been sprinkled before the nose, while artificial respiration is kept up.

The inspiratory movements may be made by drawing the arms backwards over the head, as in Sylvester's plan.

(3) A third danger arises from stoppage of the heart by a combination of chloroform-narcosis and **shock**. This is one of the most dangerous conditions. It may occur even during full chloroform-narcosis in animals from operations on the stomach; but it is much more common in men from **imperfect anæsthesia**. In very many cases of so-called death from chloroform during operations, we find it noted as a matter of surprise that death should have occurred as the quantity of chloroform given was so small. The reason that death occurred probably was because the quantity of chloroform given was so small. Had the patient been completely anæsthetised, the risk would have been very much less. The reason why imperfect anæsthesia is so dangerous is, that chloroform **does not paralyse all** the reflexes **at the same time**. A very large proportion of the deaths from chloroform occur during the extraction of teeth, and we may take this operation as a typical one in regard to the mode of action, both of the sensory irritation and of the chloroform. When a tooth is extracted in a waking person, the irritation of the sensory nerve produced by the operation has two effects:—1st, it may, acting reflexly through the vagus, cause stoppage of the heart and a consequent tendency to syncope. 2nd, it causes reflex contraction of the arterioles, which tends to raise the blood-pressure and counteract any tendency to syncope which the action of the vagus might have produced.

In complete anæsthesia all these reflexes are paralysed, and thus irritation of the sensory nerves by the extraction of the teeth has **no effect** either upon the vagus or upon the arterioles. In imperfect anæsthesia, however, the reflex centre for the arterioles may be paralysed (*vide* p. 204), while the vagus centre is still unaffected. The irritation caused by the extraction of the tooth may then cause stoppage of the heart, and there being nothing to counteract the tendency to faint, syncope occurs and may prove fatal.

With nitrous oxide there is very much less danger, inasmuch as the nitrous oxide causes a venous condition of the blood, with consequent contraction of the arterioles and rise in the blood-pressure, so that any tendency to syncope through vagus-irritation is efficiently counteracted.

With ether, also, the danger is very much less, probably because it has a more equal effect on the centres (*vide* p. 204).

(4) Another danger is that of **suffocation** from blood passing into the trachea in operations about the mouth or nose, or from the contents of the stomach being drawn into the larynx when vomiting has occurred during partial anæsthesia. In consequence of this, it is better, instead of giving chloroform or ether during the whole of an operation on the mouth or nose, to give it

only at the commencement, and to administer along with it, or before it, a hypodermic injection of one-sixth to one-third of a grain of **morphine.** The chloroform anæsthesia thus passes into the morphine narcosis, and the operation can be finished without pain, and without danger.

To **prevent** the occurrence of **vomiting**, it is advisable not to give solid food for some hours before an operation, though if necessary a little beef-tea or stimulant may be given half an hour or so before the administration of the anæsthetic.

Mode of administering Anæsthetics.—In order to obtain the **first stages** of the action of anæsthetics, as in cases of intestinal, biliary, or renal colic, intense neuralgia, or in parturition, the best means of administration is one for the account of which I am indebted to Mr. W. J. Image, of Bury St. Edmunds. It consists of a tumbler, at the bottom of which is placed a piece of blotting-paper or linen thoroughly wetted with chloroform or ether. The patient holds the tumbler to the nose with his, or her, own hand. On account of the form of the tumbler, sufficient air always gets in at the sides, and the patient cannot inhale the vapour in too concentrated a condition. As soon as the anæsthetic begins to take effect, the hand drops, and the inhalation ceases. As the effect again passes off, the patient resumes the inhalation. In employing anæsthetics in this way, however, great care must be taken that the **bottle** containing the chloroform is never entrusted to the patient, but is always kept on a table at some little distance from the bed, and that the blotting-paper or lint in the tumbler is supplied with fresh chloroform by an attendant. If the bottle itself be entrusted to the patient, as the anæsthetic takes effect and produces stupidity, the stopper may fall out, the whole contents of the bottle may be sucked up by the pillow, bolster, bed, or bedclothes, and the vapour being inhaled, fatal suffocation may ensue.

Another method of administering chloroform, which is very convenient when complete anæsthesia is required for a length of time, and when the supply of chloroform is limited, was devised by Sir James Simpson: it consists of either a cup-shaped inhaler, formed of a wire framework covered with flannel, or else simply of a single fold of a pocket-handkerchief thrown over the face: the chloroform is dropped upon the flannel or handkerchief just under the nostrils in single drops at a time. Another plan is to pour some chloroform on to a folded towel or pocket-handkerchief, and then place it over the patient's face, taking care that it does not come so close over the nose as to interfere with a free admixture of air with the chloroform vapour. There is this difference between ether and chloroform, that whereas it is highly inadvisable to give chloroform vapour in a concentrated condition, it is requisite to give the ether vapour very strong, in order to produce an anæsthetic effect. A combined administration of

nitrous oxide and ether is now used to a considerable extent: the nitrous oxide producing rapid anæsthesia, which is kept up by the ether.

Anæsthesia in Animals.

In the course of many investigations into the action of drugs on animals it is necessary to perform experiments which would be painful unless the animals were anæsthetised. The easiest way of doing this with frogs or small animals, such as mice, rats, or rabbits, is to put them under a bell-jar with an opening at the top. Into this opening a piece of cotton-wool or blotting-paper is put, and chloroform dropped on it. The vapour being heavier than air falls to the bottom, and the animal soon becomes insensible. The best way of anæsthetising cats, small dogs, or very large rabbits, is to put them into a wooden box or tin pail, and stretch a towel tightly over the top. An assistant then pours some chloroform on the towel and anæsthesia is quickly produced. Rats are most readily anæsthetised by completely covering the cage, in which they are, with a towel, and dropping chloroform upon it.

Rabbits may be very quickly anæsthetised by the plan employed by Pasteur. It consists in putting a piece of cloth or blotting-paper soaked in chloroform round the animal's nose so as to exclude air. At once the rabbit ceases to breathe, and remains without breathing for about a minute. It then begins to struggle, and if the anæsthetic be kept closely applied the respiratory movements shortly become steady and regular and the animal completely insensible.

For very large or savage dogs an old packing-case without a lid may be simply placed over the animal and held firmly down, or one of the sides may be furnished with hinges so as to convert the case into a sort of kennel. After the dog is safely housed large pieces of blotting-paper or of cloth on which chloroform is poured are pushed through cracks in the top of the case or holes specially made for the purpose. The outer ends of the blotting-paper or cloth remaining outside, fresh quantities of chloroform can be introduced as required until complete anæsthesia is produced. Anæsthesia may be maintained for almost any length of time that is required, by putting a piece of cloth loosely round the animal's nose and dropping chloroform upon it. This requires careful attention, however, in order to prevent danger from an overdose on the one hand, or partial recovery on the other. I find the most convenient way of maintaining the anæsthesia induced by chloroform in the way already mentioned is to put a cannula in the trachea and connect it with a flask containing ether, so that the inspired air passes over the surface of the ether, and carries a quantity of the vapour with it into the lungs of the

animal. By means of a peculiar stopcock, the construction of which is indicated in the diagram (Fig. 73), pure air or air loaded with ether vapour or a mixture of both may be given.

The advantages of employing this method and of using ether rather than chloroform are that complete anæsthesia may be kept



FIG. 73.—Diagram of a stopcock by which air or vapour, or two kinds of gas, may be given alone, or mixed together in any proportion.

up for hours together with little or no attention on the part of the operator, and without the respiration or blood-pressure being seriously affected by the anæsthetic.

Another plan of maintaining anæsthesia for a length of time is to inject some laudanum or liquid extract of opium into a vein after anæsthesia has been induced by chloroform. Before the effect of the chloroform has passed off, such complete narcosis is produced by the opium that no procedure, however painful it might otherwise be, will produce the slightest evidence of sensation. When the effect of the anæsthetic or of the opium would interfere with the investigation of the action of a drug on the circulation or reflex action, the animal may be anæsthetised by chloroform, and the crura cerebri divided. The channels by which painful impressions are conveyed to the brain being thus destroyed no pain can be felt, although the reflex action of the cord again returns after the effects of the chloroform have passed off.

History of the Discovery of Anæsthesia.

This is a subject of considerable interest, and has given rise to much discussion. The starting-point of the discovery seems to have been Sir Humphry Davy's observations on the properties of nitrous oxide, regarding which he said, 'as nitrous oxide in its extensive operation seems capable of destroying physical pain, it may probably be used with advantage during surgical operations.' The property of this gas and also of ether vapour to produce excitement when inhaled, caused these substances to be used in sport, and during their action bruises were frequently received, but not felt. This circumstance excited the attention of Dr. Crawford W. Long, of Athens, Georgia, and, in 1842, he anæsthetised a patient with ether in order to remove a tumour. He was encouraged to do this by the fact that Dr. Wilhite, in a frolic, had rendered a negro boy completely insensible without any bad results. Mr. Horace Wells, without

knowing what Dr. Long had done, used nitrous oxide as an anæsthetic in 1844. His pupil, Mr. Morton, wishing to use it also, asked him how to make it, and was referred to a scientific chemist, Dr. Jackson. Jackson advised Morton to use sulphuric ether, as it had similar properties to nitrous oxide and was easier to get. Acting on this suggestion Morton used ether in dentistry, and induced Drs. Warren, Haywood, and Bigelow to perform important surgical operations on patients whom he anæsthetised by it. From this time onwards anæsthesia has been regularly used in medical operations. Shortly afterwards, Sir J. Y. Simpson discovered the use of chloroform as an anæsthetic, and it has been chiefly employed in Great Britain, but in America ether has always retained its original place.

Antispasmodics.

These are remedies which **prevent** or **relieve spasm.**

Spasm is contraction of voluntary or involuntary muscles, in a way that is unnecessary or injurious to the organism generally. The spasmodic contraction of muscles may sometimes be excessive in degree, as in the calves of the legs in cramp, or in the fibres of the intestinal walls in colic. Sometimes it is not excessive in degree, but are merely out of place, as, for example, in the slight twitchings of the face or fingers which occur in mild cases of chorea.

Spasm may affect single muscles, or it may affect groups of muscles and the nerve-centres by which they are set in action; these centres may sometimes be very limited in extent, but sometimes a great number, or indeed most of the motor centres in the body, may be involved, as in the convulsions of hysteria. Spasm is, indeed, a kind of insubordination in which the individual muscles or nerve-centres act for themselves without reference to those higher centres which ought to co-ordinate their action for the general good of the organism. It may be due, therefore, either to excess of action in the muscles or local centres, or diminished power of the higher co-ordinating centres. As a rule it is due to diminished action of the co-ordinating or inhibitory centres, rather than to excess of action in the motor centres; it is, therefore, a disease rather of **debility** and deficient co-ordination than of excessive strength.

Cramps in the muscles may come on from their exhaustion by excessive exertion, the waste products of their functional activity appearing to act as local irritants. This is relieved by the removal of these waste products; as, for example, by shampooing. In the intestine, cramp may be due to the presence of a local irritant, which ought in the normal condition to produce increased peristalsis, and thus ensure the speedy removal of the offending substance. From some abnormal condition the muscular fibres

around the irritant contract excessively, and do not pass on the stimulus to those adjoining. From this want of co-ordination painful and useless spasm occurs. In order to remove it we apply **warmth** to the abdomen so as to increase the functional activity, both of the muscular fibres and of the ganglia of the intestine (pp. 138, 140). Peristalsis then occurring instead of cramp, the pain disappears, and the offending body is passed onwards and removed. Or we give internally aromatic oils, which will have a tendency to increase the regular peristalsis; or yet again, we may give opium for the purpose of lessening the sensibility of the irritated part, or the nerves connected with it, and thus again bringing it into relationship with other parts of the body.

General antispasmodics may **act** either

(1) By increasing the power of the higher nervous centres to keep the lower ones and the muscles in proper subordination, or—

(2) By lessening the activity of over-excited muscles or lower nervous centres.

On this account we find stimulants and antispasmodics very much classed together. Those drugs which **stimulate** the circulation and increase the nutrition of the higher nerve-centres and the **co-ordinating power**, tend to prevent spasm. Thus, small quantities of alcohol and ether, by acting in this way, tend to prevent general spasm, as in hysteria, nervous agitation, or trembling, or remove local spasm, as in colic.

Camphor, which is frequently used as an antispasmodic, has a stimulant action on the brain, spinal cord, circulation, and respiration. It is probable that such antispasmodic powers as it possesses are due to its exciting the higher centres, and increasing their inhibitory powers over the lower (p. 214). Bromo-camphor has a somewhat similar action.

Valerian, asafœtida, musk, castor, and other aromatic substances, have an antispasmodic action which we do not understand. It is possible that they affect some part of the brain particularly, so as to increase its regulating power, in much the same way as camphor.

Other antispasmodics, such as bromide of potassium, **lessen** the **irritability** of motor centres. Borneol and menthol have a depressing and finally paralysing effect upon motor, sensory, and reflex centres in the brain and spinal cord. In this respect they differ greatly from ordinary camphor, which has an exciting action upon these structures, though they may perhaps be still more useful as antispasmodics.

Other antispasmodics, instead of lessening the irritability of nerve-centres, may **paralyse** the structures through which the nerves act. Thus, nitrite of amyl appears to arrest the spasm of the vessels in angina pectoris, by causing paralysis of the vessels themselves or of the peripheral ends of the vaso-motor nerves.

Adjuvants.—As spasm is usually an indication of deficient nervous power, tonics, as quinine, iron, cod-liver oil, arsenic, sulphur, cold baths, and moderate exercise, are useful as adjuvants.

It has already been mentioned, that a healthy condition of the various parts of the body depends on proper nutrition and proper removal of waste. Therefore, when there is a tendency to spasm, the diet should be plain, but nutritious. Those conditions which tend to cause excessive waste should be avoided, such as exciting emotions, excessive bodily or mental work, a close atmosphere, and late hours. Attention must be paid also to the proper removal of all waste, by the use of purgatives, cholagogues, or diuretics if necessary.

Great irritability of the nervous system is usually observed in gouty subjects before an attack of gout comes on. It is uncertain to what this irritability is due, but it may not improbably be caused by the retention within the body of the products of tissue-waste. Some years ago there was considerable discussion regarding the active ingredient of bromide of potassium, some attributing its antispasmodic action to the bromine, and others to the potassium. It occurred to me that possibly its action might be partly due simply to its action as a saline leading the patient to drink more water, and thus assisting the elimination of the products of tissue-waste. I accordingly tried 30-grain doses of chloride of sodium in cases of epilepsy. In some it did little or no good, but in a few it appeared to have nearly as powerful an action as bromide of potassium.

Uses.—Antispasmodics are used in convulsive diseases.

The antispasmodics used in hysteria may be divided into substances which exert on the higher nerve-centres a sedative, tonic, or stimulant action, thus :

I. Sedatives	Alkaline bromides.	
II. Tonics	Zinc salts.	
III. Stimulants, which have a powerful odour, and probably act on the higher centres through the olfactory organs, either by direct application or during their elimination (p. 41).	Musk, Castor	Derived from the genital organs of animals.
	Sumbul, Valerian	Similar in the nature of their odour to the above, though derived from plants.
	Asafœtida, Ammoniacum, Galbanum	Containing sulphur oils.

In epilepsy, laryngismus stridulus, and infantile convulsions, bromides of potassium, sodium, ammonium, and calcium, nitrite of sodium, salts of silver, zinc, and copper.

In chorea, arsenic, conium, the salts of copper and zinc.

In spasmodic asthma, lobelia, stramonium.

In spasm of the blood-vessels, nitrite of amyl and other nitrites.

Action of Drugs on the Cerebellum.

The chief function of the cerebellum appears to be the maintenance of equilibrium. Symmetrical lesions on both sides of the organ or division of it down the centre from before backwards, cause very little disturbance of the equilibrium, but when a lesion is unsymmetrical the equilibrium is disordered.

According to Ferrier, if the lesion affects the whole of a lateral lobe, there is a tendency for the animal to roll over towards the affected side. In an animal standing on all fours or lying on the ground, we regard the centre of the back as the point of movement, but in a man standing upright we usually take the face, and therefore what we should regard in an animal as rolling towards the affected side, would be equivalent in man to a rotation towards the sound side. If the lesion is limited to one part of the lateral lobe, it may not cause rotation, but only falling towards the opposite side. When the anterior part of the middle lobe of the cerebellum is injured, the animal tends to fall forward, and in walking usually stumbles, or falls on its face. When the posterior part of the middle lobe of the cerebellum is injured, the head is drawn backwards and there is a continual tendency to fall backwards when moving.[1]

Injuries of the cerebellum are frequently associated with a certain amount of nystagmus, and in all probability the complete or partial inability to walk or stand which alcohol produces, is due to its action on the cerebellum.

Different kinds of spirit appear to have a tendency to affect different parts of the cerebellum, for good wine or beer is said to make a man fall on his side, whisky, and especially Irish whisky, on his face, and cider or perry on his back.[2] These disturbances of the equilibrium correspond exactly with those caused by injury to the lateral lobes, and to the anterior and posterior part of the middle lobe of the cerebellum respectively. Apomorphine in large doses appears also to have an action on the cerebellum or corpora quadrigemina, as the animal poisoned by it does not vomit, but moves round and round in a circle.

The action of alcohol on frogs is peculiar and differs from that of other narcotics, inasmuch as it appears to affect unequally the two sides of the nervous apparatus by which the equilibrium is maintained, so that in a certain stage of alcohol-poisoning they excite similar *manège* movements to those which occur after division of the corpora quadrigemina on one side.[3]

---

[1] Ferrier, *Functions of the Brain*, p. 94.

[2] Shorthouse, Baily's *Magazine of Sports*, 1880, vol. xxxv. p. 396.

[3] Wilhelm Wundt: *Untersuchungen zur Mechanik der Nerven und Nervencentren.* Zweite Abtheilung, 1876. Stuttgart.

CHAPTER IX.

ACTION OF DRUGS ON THE ORGANS OF SPECIAL SENSE.

Action of Drugs on the Eye.

Action on the Conjunctiva. — Before light can reach the retina, it has to pass through the cornea, which is covered by epithelium continuous with that of the conjunctiva. Alterations in either or both of these textures are therefore very important in regard to the integrity of vision. The chief drugs employed in the local treatment of diseases of the cornea and conjunctiva are warmth, moist and dry, anæsthetics, anodynes, antiphlogistics, antiseptics, and astringents. The chief **astringents** are perchloride of mercury, oxide of mercury, and nitrate of silver. The chief **antiseptics** are perchloride of mercury, quinine, boric acid, and sulphocarbolate of sodium. The chief **sedatives** are hydrocyanic acid, opium, belladonna, atropine, and cocaine. There are two astringents in common use which ought to be avoided, these are solutions of lead and of alum. Lead salts are objectionable, because if there is any ulceration on the cornea they may form an insoluble albuminate and cause permanent opacity. Salts of alum are said by Tweedy to be perhaps still more objectionable, because alum has the power of dissolving the cement by which the fibrillæ of the cornea are held together, and this is very apt to give rise to perforation of the cornea whenever the epithelium is removed by injury or inflammation. Tweedy also thinks that strong solutions of common salt, ten per cent. or more, and solution of permanganate of potassium also dissolve the corneal cement and should therefore be avoided in inflammation of the conjunctiva or of the cornea. He considers that sulphate of zinc should be avoided, for the same reason, but it is largely used by others. The best astringent is probably perchloride of mercury, $\frac{1}{64}$th to $\frac{1}{16}$th of a grain to an ounce of water, and coloured with cochineal. The next best is an aqueous solution of boric acid, containing 3 to 8 grains of it with 3 to 10 grains of sulphocarbolate of sodium per ounce.

The chief effects which drugs produce on the eye, besides those just described, are alterations in the size of the pupil, in

the power of accommodation, in the intra-ocular pressure, in the sensitiveness of the retina to impressions, and in the apparent colour of objects.

Action of Drugs on the Lacrimal Secretion.—The great power of certain volatile oils, such as those of onion or mustard, to irritate the eyes and cause secretion of tears is well known. The prolonged action of atropine diminishes the secretion. Eserine abolishes the action of atropine, and quickly increases the secretion.[1]

Projection of the Eyeball.—The non-striated muscular fibres which are contained in the orbital membrane and in both eyelids push the eyeball forward and draw the eyelids back when they contract. Like the dilator pupillæ they are innervated by the sympathetic, and consequently some degree of protrusion of the eyeball is frequently produced by such substances as dilate the pupil, and especially by cocaine. Excessive pain, or an asphyxial condition of the blood, has a powerful action in producing this effect, so that in men subjected to torture in the Middle Ages protrusion of the eyeballs was noticed; and both in animals and men dying from rapid asphyxia the eyeballs may seem as if starting from the head.

Action on the Pupil.—The iris is usually said to consist of two muscles, the sphincter, which has circular fibres and contracts the pupil, and the dilator, which has radial fibres and dilates the pupil. All observers are agreed regarding the sphincter muscle of the eyes, but some deny the existence of the dilator muscle. In the following description, however, I shall take the view which is usually accepted.[2]

The sphincter receives its motor nervous supply from the third nerve, and the dilator from the cervical sympathetic. The nervous centre for the contraction of the pupil probably lies in the corpora quadrigemina; the nerve-centre for the dilatation of the pupil lies in the medulla oblongata, but there seems to be another dilating centre, situated in the floor of the front part of the aqueduct of Sylvius.[3] The contracting nerves are contained in the third nerve, and pass to the ciliary ganglion, and thence to the eye. Along with them motor fibres pass also to the ciliary muscle. This muscle when contracted lessens the tension of the suspensory ligament on the lens, allowing the latter to become

---

[1] Maynard, *Virchow's Archiv*, vol. lxxxix. p. 258.

[2] At present it is generally assumed that muscular fibres, either voluntary or involuntary, contract only in the direction of their length. If we suppose that they can contract either in the direction of their length or their width, the movements of the iris might be more readily explained. At present we assume the presence of a dilator muscle, which is almost certainly absent in many animals, in order to explain phenomena which might be explained just as readily by the supposition that the muscular fibres which are present can contract in two directions (*see* p. 117).

[3] Foster's *Physiology*, 4th ed.

more spherical, and thus accommodating the eye for near objects. Such accommodation and contraction of the pupil generally accompany one another. The arrangement of the nerves of the eye is very diagrammatically shown in Fig. 74. A few of the dilating fibres are contained in the fifth nerve, but most of them pass down the spinal cord to the cilio-spinal region in the lower cervical and upper dorsal part of the cord, and thence through the second dorsal nerve in monkeys and probably in man, or through the inferior cervical and superior dorsal nerves in the rabbit, into the cervical sympathetic, in which they again ascend to the eye.




FIG. 74.—Diagram to show the nervous supply of the eye. *a*, nerves to the ciliary muscle regulating accommodation; *b*, nerves to the contracting fibres, and *c*, nerves to the dilating fibres of the iris; *d*, vaso-motor nerves to the vessels of the eye. The iris is put apparently behind instead of in front of the lens for convenience in showing the passage of nerves to it.

Along with the dilating fibres others pass to supply the orbital muscle at the back of the orbit, which causes protrusion of the eyeball, as already mentioned. There are also other fibres from the sympathetic (vaso-motor) which supply the muscular coats of the arteries of the ciliary vessels.

The dilating centre may be stimulated directly by venous blood circulating in it. In consequence of this the pupils usually dilate much when the respiration is imperfect, as during dyspnœa; but when the asphyxia becomes complete the centre again becomes paralysed and the size of the pupil diminishes. It may be stimulated reflexly by irritation of sensory nerves, so that dilatation of the pupil has been used as an indication of sensation in animals paralysed by curare. It seems to be readily stimulated by irritation of the genital organs. This is probably the reason why dilatation of the pupil frequently occurs in persons suffering from irritation of the genital organs. It is probably also readily stimulated by irritation of the intestinal canal, and such irritation may be the cause of dilatation of the pupil in children suffering from worms, and in cases of poisoning by drugs which irritate the gastro-intestinal canal, like aconite.

The drugs which act upon the iris are divided into two classes: **Mydriatics** which dilate, and **Myotics** which contract the pupil. The most important of these are such drugs as have a local action

on the eye, and they alone are used in ophthalmic medicine. They are indicated in the following list by an *.

Mydriatics.	Myotics.
General anæsthetics—chloroform, ether, &c.	General anæsthetics—chloroform, ether, &c.
*Atropine.	*Calabar bean.
*Belladonna.	
Belladonnine.	
Benzoyltropine.	
Cocaine.	
Daturine.	
*Duboisine.	
Gelsemine locally.	Gelsemine internally.
*Homatropine (oxytoluylic-acid-tropine).	Jaborandi.
	Lobeline internally.
Hyoscyamine.	Morphine internally.
Muscarine locally (?).	Muscarine internally.
	,, locally.
Narcissine.	Nicotine locally.
Piturine.	Opium.
Scopalein.	*Physostigmine (eserine).
Stramonium.	Pilocarpine.
	Thebaine.

Anæsthetics occur in both classes, because they cause contraction towards the commencement of their action, while later on they cause dilatation. The probable reason of this is that at first they lessen reflex action, so that the reflex dilatation of the pupil by stimulation of sensory nerves is abolished. Later on, when they begin to paralyse the respiration, the accumulation of venous blood causes irritation of the dilating centre and widens the pupil. Dilatation of the pupil during the administration of anæsthetics is therefore to be regarded as a sign of imperfect aëration of the blood, due either to embarrassed or failing respiration (p. 218) or failing circulation (p. 207).

The contraction caused by morphine is also central, and probably due to a similar cause.

It is possible that the local application of drugs to the eyes may have an action on the pupil due merely to their effect as irritants, and independent of any special action on the iris, for E. H. Weber [1] found that local irritation at the margin of the cornea causes partial dilatation. Irritation in the middle of the cornea causes rather contraction of the pupil. Localised irritation at the margin of the iris may cause dilatation at that part.

The reason why muscarine has been found by Ringer and

[1] Quoted by Landois, *Physiologie*, 1880, p. 799.

Morshead to dilate the pupil when applied locally is probably that the solution they used was very irritating, either from its strength or for some other reason, while Schmiedeberg and Harnack found it to contract the pupil both when given internally and applied locally.

The contraction of the pupil noticed by Rossbach in rabbits immediately after the application of atropine, may also have been due to local irritation. The occurrence of dilatation in one case and of contraction in the other may possibly have been due to the solution being dropped into the eye in a different way in the two cases.

The commonest and most important **local mydriatic** and **myotic** are respectively atropine and physostigmine (eserine).

From ten to twenty minutes after a solution of atropine has been dropped on the eye, the pupil dilates and the ciliary muscle becomes paralysed, so that the accommodation for near objects is no longer possible, and the eye remains focussed for distant objects. When a solution of physostigmine is dropped into the eye, the pupil contracts and the ciliary muscle becomes spasmodically contracted, so that the eye is accommodated for near objects.

It is very difficult to explain the **mode of action** of these drugs satisfactorily, and authorities are by no means agreed regarding it. That the action is local is shown by the fact that when either atropine or physostigmine is applied to one eye its action is limited to it and the other remains unaffected. If care be taken to limit the application of a solution of atropine to one side of the margin of the cornea, local dilatation of the corresponding part of the pupil may be produced.

Dilatation of the pupil may be due to

(1) Paralysis of the sphincter, or

(2) Excessive action of the dilator, or

(3) Both conditions combined.

Paralysis of the sphincter may be due to (*a*) imperfect action or paralysis of the oculo-motor centre in the corpora quadrigemina, (*b*) to paralysis of the ends of the third nerve in the sphincter iridis, or (*c*) to the action of the drug upon the muscular fibres of the sphincter itself, or to a combination of two or more of these factors.

Along with the factors just mentioned might be associated excessive contraction of the dilator muscle, which may be due to stimulation (1) of the sympathetic centre in the medulla, (2) of the ends of the sympathetic in the dilator muscle, or (3) of the dilator muscle itself.

Excluding for the present the question of excessive action of the dilator muscle and confining ourselves to the causes of paralysis, we see that paralysis of the cerebral oculo-motor centre as a factor in dilatation of the pupil by atropine is excluded by the local action of the drug, by the experiments of Bernard and

others, which show that dilatation occurs from the local action of atropine when the ciliary ganglion is extirpated and all the nerves of the eye have been divided, and by the mydriatic action of atropine even in the exsected eye. We can now limit its action either to paralysis of the ends of the oculo-motor nerve, or paralysis of the muscular fibres of the sphincter.

That the ends of the oculo-motor nerve in the sphincter iridis are paralysed is shown by the experiment that when the pupil is under the full action of atropine, irritation of the third nerve will not produce any contraction in it, although the sphincter will still contract when stimulated directly.

Here also we find the same relation between the action of atropine on nerves supplying striated and non-striated muscle that we have already noticed in the case of the œsophagus (p. 139), for in most animals the iris consists of unstriated muscular fibre, and atropine causes dilatation; but in birds the iris consists of striated muscular fibre, and atropine causes no dilatation. Paralysis of the ends of the oculo-motor nerve in the iris itself may be looked upon as one of the factors in dilatation by atropine, and similar paralysis of the fibres supplying the ciliary muscle may be regarded as the cause of loss of accommodation.

In addition to this, however, when the dose of atropine is large, the muscular fibres of the sphincter themselves become paralysed, and fail to contract even when directly irritated.

The question now arises whether in addition to paralysis of the oculo-motor nerve there is not also excessive action of the dilator muscle. That such action of the dilator is actually present appears to be shown by the following fact, viz. that the dilatation caused by atropine does not appear to be merely passive, but occurs with such force as to tear the iris away from the lens, and break down inflammatory adhesions which may have formed between them. This conclusion has been considered to be supported also by the facts:—(*a*) That when the oculo-motor nerve is divided the pupil does not dilate nearly to the same extent as it does from the application of atropine. This is shown both by a comparison of measurements of the eye under the two conditions and by the observation that after the nerves have been divided and partial dilatation produced, atropine causes the pupil to dilate still more. And similarly in dilatation due to paralysis atropine increases the mydriasis. (*b*) When the pupil is dilated by atropine, section of the sympathetic in the neck lessens the dilatation.

We may consider, then, with tolerable certainty, that dilatation caused by atropine is due to increased action of the dilator as well as diminished action of the sphincter muscles of the iris.

Contraction of the pupil may be due to

(1) Excessive action of the sphincter, or

(2) Paralysis of the dilator.

That the contraction caused by physostigmine is not due to paralysis of the dilator is shown by the pupil dilating somewhat when shaded, even when the drug is exerting a well-marked action. Excessive action of the sphincter must therefore be regarded as the cause of the myosis. Such action may be due to stimulation (1) of the oculo-motor cerebral centre, (2) of the ends of the oculo-motor nerve in the sphincter, or (3) to increased action of the muscular fibres in the sphincter from the direct effect of the drug upon them. The local action of physostigmine upon the eye excludes the cerebral centre, and leaves for our consideration stimulation of the ends of the nerves and of the muscular fibres themselves.

These two structures seem to be specially affected by different drugs—so that **local myotics** may be divided into two classes—

1st. Those which act upon the peripheral ends of the oculo-motor nerve.

2nd. Those which affect the muscular fibre of the sphincter iridis.

The first class includes muscarine, pilocarpine,[1] and nicotine, whereas physostigmine belongs to the second.

Muscarine, pilocarpine, and nicotine, when applied to the eye, cause contraction of the pupil and spasm of accommodation. Atropine, as we have already seen, not only paralyses the ends of the oculo-motor nerve, which these drugs stimulate, but has also an action on the muscular fibre itself. Its subsequent application will therefore remove the effect of these drugs, and they will not act when atropine has been applied first. As physostigmine stimulates the muscular fibre itself, it will cause contraction in an eye which is dilated by atropine unless the action of the atropine has been carried to such an extent as to paralyse the muscular fibre.

The contraction produced by muscarine in the eye of the cat is so great as to reduce the pupil to a mere slit, and is much greater than that caused by physostigmine, for muscarine, acting only on the ends of the oculo-motor, produces spasm in the sphincter without affecting the dilator, while physostigmine, acting on the muscular fibres, is said to stimulate those of the dilator as well as the sphincter, and thus to render the contraction less complete.[2]

It has already been pointed out, however, that the action of atropine is not confined to the ends of the oculo-motor nerve, but affects the muscular fibre itself, and thus it will counteract the effect of physostigmine, which it would not do if it acted only on the nerves.

Atropine consists of the combination of a base, tropine, with

[1] Schmiedeberg, *Arzneimittellehre*, p. 71. [2] Schmiedeberg, *op. cit.*

ropic acid. Tropine itself has no mydriatic action, but when an tom of hydrogen in it is displaced by an acid residue it acquires his action. A number of combinations of tropine with different cids have been artificially prepared by Ladenberg, who terms hem tropeïnes. Amongst these are homatropine, in which the ropine is combined with oxytoluylic acid, and also benzoyl-tropine. Atropine appears to be identical with daturine. Hyoscyamine is also a combination of tropine with tropic acid, but it appears to be only isomeric with and not identical with atropine, though it seems to be identical with duboisine.

Action of Drugs on Accommodation.—The accommodation of the eye depends upon the ciliary muscle. When the eye is at rest the lens is flattened by the elastic tension of the zonule of Zinn. During accommodation for near objects the ciliary muscle draws the zonule forward and allows the lens to become more convex. The ciliary muscle is innervated by the third nerve: the centre for it appears to be in the posterior part of the floor of the third ventricle. Those drugs which affect the iris, also affect the power of accommodation. Their action on the iris and on accommodation do not, however, always begin at the same time, nor have they the same duration. The action of physostigmine and atropine on accommodation usually begins after, and passes away long before, the affection of the pupil.

Action on intra-ocular pressure.—The intra-ocular pressure depends greatly on the amount of fluid contained in the vitreous, and this in turn is determined by two factors :—

(1) The amount of fluid secreted by the ciliary body.

(2) The freedom with which fluid escapes at the angle of the anterior chamber.

The aqueous humour and the fluid which nourishes the vitreous and crystalline lens are chiefly secreted by the ciliary processes. It ultimately passes out from the anterior chamber of the eye by a number of small openings (*f*, Fig. 75) close to the junction of the cornea and iris into the canal of Schlemm (*c*, *s*, Fig. 75), thence into the anterior ciliary veins. Some of it also passes into the perichoroidal space, and out through the lymphatics.

The intra-ocular pressure may be increased by (*a*) more rapid secretion from the ciliary processes, or (*b*) interference with its outward flow from the eye, or (*c*) by increased quantity of blood in the vessels of the iris. It may be diminished by the contrary conditions.

More rapid secretion from the ciliary process probably takes place under nervous conditions which are not at present well known. Interference with the flow of the aqueous humour out of the anterior chamber may occur in aquo-capsulitis, in which the openings from the anterior chamber into the spaces of Fontana are occluded by a coating of inflammatory lymph ; also

in glaucoma where these openings are shut by the iris being pressed forward against the cornea, as in Fig. 75, and in iritis where the iris is much congested and the communication between the posterior and anterior chambers is interrupted by complete adhesion of the pupillary edge of the iris to the anterior capsule of the lens (total posterior synechia). The secretion is probably diminished by the action of atropine. In glaucomatous states where the periphery of the iris lies in contact with the cornea the outward flow through the spaces of Fontana may often be increased by Calabar bean, which, by causing contraction of the circular fibres of the iris, flattens the arch of the iris and, drawing it away from the cornea, reopens the contracted angle between the cornea and iris, and permits the passage of fluid through the spaces of Fontana.[1]

There are few or no experiments on the tension in the vitreous humour of the eye, though by the term intra-ocular tension is usually intended the pressure in the vitreous humour. The




FIG. 75.—This diagram (which I owe to the kindness of Mr. J. Tweedy) represents a section through the corneo-scleral region, ciliary body and iris, of a healthy eye (left side), and of a glaucomatous eye (right side) : *k*, cornea ; *s*, sclerotica ; *i*, iris ; *f*, spaces of Fontana ; *c s*, canal of Schlemm. In the glaucomatous eye the ciliary body is atrophied, and the iris lies against the cornea, preventing the escape of fluids through the spaces of Fontana and canal of Schlemm.

degree of intra-ocular tension is usually ascertained by pressing the finger *secundum artem* upon the eye and observing whether it is harder or softer than usual, or by pressing upon the sclerotic with an ivory point attached to a registering spring, and noticing the pressure required to produce an indentation. These methods of experiment are valuable clinically, but the tension can be more exactly ascertained in animals by passing a small trocar into the anterior chamber and connecting it with a manometer. The results of experiments even by this method are not entirely in accordance. The most recent ones by Graser [2] appear to show that the tension depends to a great extent upon the height of the blood-pressure generally : contraction of the pupil diminishes, and dilatation increases the intra-ocular tension. Eserine causes temporary increase at first, but after contraction of the pupil comes on, the tension is diminished. Atropine in doses sufficient

[1] J. Tweedy, *Practitioner*, Nov. 1883, vol. xxxi. p. 321.
[2] Graser, *Archiv f. exp. Path. u. Pharm.*, Bd. xvii. Heft 5.

o dilate the pupil increases the tension. The precise effect of tropine on intra-ocular tension in man is disputed. From linical observation the truth would seem to be that in a perectly healthy eye and in ordinary iritis atropine and other nydriatics diminish tension, whereas they increase the tension when the anterior chamber is shallow from narrowing of the ridic angle. In glaucomatous states atropine and other mydriatics almost always rapidly increase tension. This action of tropine and its allies not only makes them dangerous in cases of glaucoma, but where this disease has been impending it has been at once brought on by their use. From its power to diminish tension eserine is useful in glaucoma.

Uses of Mydriatics and Myotics.—Belladonna is employed locally for its sedative action, to relieve pain and allay irritation and inflammation in the conjunctiva, cornea, choroid, or iris.

Mydriatics and myotics are used not only for their action upon the pupil but for their action upon accommodation and intra-ocular pressure.

Mydriatics are employed to dilate the **pupil** for the purpose of facilitating ophthalmoscopic examination, assisting the detection of cataract commencing in the periphery of the lens, or allowing the patient to see past the edge of a cataract or corneal opacity when this is central in position, and obstructs the vision with a pupil of normal size. They are used to prevent prolapse of the iris, or to restore it to its normal position when already prolapsed in cases of perforating ulcer or mechanical lesion of the cornea. They are employed in iritis to afford rest to the inflamed tissues of the eye, and to keep the iris as far as possible off the surface of the lens and prevent adhesions of its posterior surface to the anterior surface of the lens.

Mydriatics are employed to paralyse the ciliary muscle, and thus destroy the power of **accommodation** in order to test the condition of the refractive media of the eye in cases of astigmatism, or in cases where the patients either suffer from spasm of the ciliary muscle or are unable voluntarily to relax the accommodation.

Myotics are used to counteract the effect of mydriatics which have been previously employed, or in mydriasis following a blow or paralysis of the third nerve. They are used also to counteract deficiency in tone of the ciliary muscle, as in paralysis of accommodation consequent on diphtheria, asthenopia, a blow on the eye, &c.

Myotics are useful in cases of threatening and commencing glaucoma and often even in more advanced cases of glaucoma, from their power to lessen intra-ocular tension. As a temporary expedient they are often of the greatest service in cases of acute glaucoma. So, also, if perchance the instillation of atropine have induced glaucoma, myotics will not only counteract the

mydriasis, but often rapidly restore the intra-ocular tension to the normal standard.[1]

Mydriatics and myotics may be employed alternately in order to ascertain the presence of any adhesions of the iris, and to break them down if present.

In glaucoma the intra-ocular tension within the anterior chamber is greatly increased, and the increase, according to Tweedy, is due to the natural channel of escape for the aqueous humour through the spaces of Fontana and the canal of Schlemm being obstructed by the iris lying against the cornea. This condition is relieved by myotics, which, by causing contraction of the pupil, draw the iris away from the cornea, and thus allow the fluid to escape through the spaces of Fontana. When the anterior chamber of the eye is shallow and the iris is lying close to the cornea, so as nearly, though not quite, to obstruct the spaces of Fontana, atropine may induce an attack of glaucoma by dilating the pupil and thus packing the tissue of the iris into the angle between it and the cornea, so as to render the obstruction to the spaces of Fontana complete.

Action of Cocaine.—Cocaine, when applied locally to the eye, has several actions. It produces local anæsthesia, dilatation of the pupil, and relaxation with more or less complete paralysis of the ciliary muscle. When two to three drops of a 4-per cent. solution are applied to the eye at intervals of five minutes, such complete local **anæsthesia** of the cornea, conjunctiva, and iris is produced in twenty to thirty minutes as to allow operations to be performed on the eye. At the same time the cocaine causes constriction of the superficial vessels, producing blanching of the conjunctiva. The **dilatation** of the **pupil** is great, is quickly attained, and differs from that produced by atropine in the fact that the cocainised pupil reacts to light and accommodation. The mydriasis is probably due to stimulation of the ends of the sympathetic in the iris, for cocaine will not produce any mydriatic effect after the cervical sympathetic has been cut for such a length of time as to allow degeneration of the peripheral ends to occur, nor has stimulation of the cervical sympathetic any effect in increasing the *ad maximum* cocaine mydriasis. That the third nerve is not paralysed is shown by the fact that stimulation of it produces contraction in the cocainised pupil. A similar effect follows local stimulation of the sphincter pupillæ. That the action of cocaine is exerted on the peripheral ends and not on the centres of the sympathetic is shown by the fact that section of the cervical sympathetic does not alter the pupil which is fully dilated by cocaine, and cocaine induces mydriasis in an exsected eye.[2]

Action of Drugs on the Retina.—By a comparison of the retina of a frog kept in darkness with one exposed to light, it has

[1] Tweedy, *loc. cit.*

[2] Jessop, *Proc. Roy. Soc.*, 1885.

been found that light causes not only the internal segments of the cones [1] and rods [2] but also the pigment-cells of the retina to contract, so that the external parts of the rods and cones as well as the pigment are drawn away from the external towards the internal limiting membrane of the retina (Fig. 76*b*). A similar effect is produced by heat.[2] The retina of a frog which has been tetanised by strychnine in complete darkness has an appearance




FIG. 76.—Shows the position of the rods and pigment-cells in the retina of the frog: *a*, after the animal has been kept in complete darkness for one or two days; *b*, after it has been exposed to diffused daylight for five or ten minutes, after being kept in darkness for twenty-four hours; *c*, after exposure to light as in *b*, but for half an hour instead of a few minutes. This also represents the position of the rods and pigment-cells in strychnine tetanus.

similar to that of a retina which has been exposed to full daylight, the strychnine having caused extreme contraction of the rods, cones, and pigment-cells (Fig. 76*c*). A similar effect is produced by tetanising the eye itself either by induced currents in the dark, or while it is still in the head or immediately after its excision. Curare neither hinders this action nor produces it.

Action of Drugs on the Sensibility of the Eye.—The sensitiveness of the eye to impressions is increased by strychnine, the field of vision becoming larger, and the sight more acute, so that objects can be distinctly observed at a greater distance, and the field of colour is increased for blue. This action appears to be to a certain extent local, as it occurs more distinctly on that side where the strychnine has been injected hypodermically. The sense of colour is affected in a remarkable way by santonin, which at first causes objects to appear somewhat violet and afterwards of a greenish-yellow. The yellow colour has been ascribed to staining of the media of the eye by santonin, as it becomes yellow when exposed to the light; others again have supposed

[1] Engelmann (and von Genderen Stort), *Pflüger's Archiv*, xxxv. p. 498.
[2] Gradenigo, jun., *Allg. Wiener med. Ztg.*, 1885, No. 29.

the alteration in the apparent colour of objects to be due, first to a stimulation, and then to a paralysis of those constituents of the retina by which the violet colour is perceived.

The sensibility of the eye for red and green appears to be sometimes diminished by physostigmine.

Action of Drugs in Producing Visions.—It may be well here to mention the effect of some drugs in causing subjective sensations of sight, although these probably depend rather upon the action of the drugs on the brain, than on the eye itself. The centres for sight, according to Ferrier, are the angular gyrus (14 and 15, Fig. 68, p. 185), and the occipital lobes. In delirium tremens arising from alcoholic excess the patients often complain much of visions of the most disagreeable character, which often take the form of demons or of animals.

Cannabis indica produces in some persons, though not in all, visions which may be pleasant or laughable. These chiefly occur just before sleep.[1]

Salicylate of sodium in some persons tends to cause most disagreeable visions whenever the eyes are shut, and I have seen it have this effect even in such a small dose as five grains. Large doses of digitalis may cause subjective sensations of light, and after taking nearly one grain of digitalin in the course of forty-eight hours I suffered from the centre of the field of vision being occupied by a bright spot surrounded by rainbow colours. Digitalin when introduced into the eye locally causes at first smarting and lacrimation, which soon passes off, but after four or five hours, when a light is looked at, a halo is seen surrounding it, which is not improbably due to some opalescence in the cornea.[2]

Toxic Amblyopia.—Belladonna taken internally in sufficient quantity causes dilatation of the pupil and misty vision. Alcohol, tobacco, quinine, and lead all cause failure of the power of vision for form and for certain colours, as well as limitation of the field of vision either in the centre or the periphery. These symptoms are at first functional, but if not relieved they may be the precursors of actual anatomical changes.

Action of Drugs on Hearing.

The sense of hearing depends on the transmission of sonorous vibrations from the air to the auditory nerve by means of the membrana tympani and the ossicles of the ear, and upon the perception of those vibrations by the brain.

The centre for hearing, according to Ferrier, is in the

[1] Compare Schroff, *Pharmacologie*, 4th ed. p. 535, and Wood, *Materia Medica*, 3rd ed. p. 236.

[2] Lauder Brunton, *On Digitalis*, &c.

superior temporo-sphenoidal convolution (16, Fig. 68, p. 185). It is probable that subjective sounds not depending on disturbance of the auditory apparatus, such as the sounds of voices, &c., heard in delirium or mania, or as the prodromata of an epileptic fit in certain individuals, or during intoxication by cannabis indica, are due to irritation of these centres.

The sense of hearing may be dulled by any interference with the passage of the sound into the ear, as by wax in the auditory meatus, by disease of the auditory nerve or of the brain itself.

The hearing may be rendered more acute by the removal of any obstacle in the way of transmission of sound to the auditory nerve, or by drugs which increase the excitability of the auditory nerve or of the brain; thus the wax may be removed by simply syringing; thickness and catarrh of the Eustachian tube which interfere with vibrations in the middle ear may be lessened by the inhalation of camphor and ammonia, or by the application of a solution of ammonium chloride and sodium bi-carbonate to the posterior nares either by the spray or nasal douche. The excitability of the auditory nerve or of the brain is increased by strychnine, which renders the hearing more acute.

Subjective noises in the ear, such as humming, buzzing, or ringing, are often very troublesome. Bubbling noises may be due to mucus in the Eustachian tube. Buzzing or humming are probably generally caused by vascular congestion either of the external meatus, of the middle ear, or of the Eustachian tube. Where the bubbling noises are due to the presence of mucus they may be to a considerable extent removed by washing out the mucus with a solution of carbonate of sodium applied by a nasal douche. Noises in the ears due to hyperæmia may be lessened or removed by cholagogue purgatives and by hydrobromic acid. Where chronic thickening of the membrane is present, relief is usually afforded by iodide of potassium or iodide of ammonium, both applied locally and taken internally. Subjective noises in the ears are caused by quinine in large doses, and also by salicylate of sodium. Both of these drugs have their effect upon the ear to a great extent neutralised by hydrobromic acid, and ergot [1] is said to have a similar power to prevent or remove the unpleasant singing. It is uncertain whether the singing caused by quinine and salicylates is due to their action on the auditory apparatus, or the cerebral centres; but the fact that in larger doses they may cause delirium indicates that even the earlier symptom of buzzing in the ears may be due, in part at least, to their action on the cerebral centres.

[1] Schilling, *Aertzl. Intelligenzblatt*, 1883.

Action of Drugs on Smell.

Many drugs, such as musk and ethereal oils, have a marked and characteristic smell, due to their effect upon the terminal branches of the olfactory nerve. This nerve is soon exhausted, so that in a very short time the smell is no longer perceived with anything like the intensity it was at first. Such smells as these just mentioned cannot be perceived by persons suffering from anosmia, but certain drugs, such as ammonia or acetic acid, can be recognised by them. The reason of this is that although such persons are incapable of perceiving any true smell, the nasal branches of the fifth nerve are irritated by pungent vapours, and thus produce a certain kind of sensation. The power of distinguishing smells seems to be increased by strychnine; which appears at the same time to render such disagreeable odours as those of asafœtida, garlic, and valerian agreeable. This effect may be due to the action of strychnine on the olfactory apparatus, but it is very probably due rather to the action of the drug on the cerebral centre for smell, which, according to Ferrier, is situated at the tip of the temporo-sphenoidal lobe. The power to distinguish smells is diminished by such drugs as lessen the sensibility of the brain, or by those which cause alterations in the nasal mucous membrane, as, for example, iodide of potassium given in such doses as to produce coryza.

Action of Drugs on Taste.

Most of the substances used in medicine have a strong taste, and many a very unpleasant taste.

What is usually termed taste frequently depends on a mixture of taste and smell, and if the sense of smell is abolished for the time being, the characteristic taste of the substance cannot be distinguished. This is the reason why castor-oil, which owes its nauseous taste almost entirely to its odour, can be swallowed without being so readily distinguished if the nose is held during the act of swallowing. In addition to the taste they produce in the mouth, certain substances leave an impression termed 'after taste' on the tongue after they have been swallowed or ejected; and this is sometimes quite different from that of the taste of the substance itself: thus bitters leave a sweet after-taste in the mouth. If quinine is taken in a nearly neutral solution, it leaves a persistent bitter taste from the sparingly soluble alkaloid being precipitated on the tongue and remaining there for a length of time, but if the quinine be taken with excess of acid, so as to keep it entirely in solution, and washed out of the mouth immediately with a draught of water, it leaves a sweet after-taste.

Some substances after their entrance into the blood are excreted by the saliva and may cause a somewhat persistent taste in the mouth; this is observable in the case of iodide of potassium.

Iodine appears also to have the power of causing other substances to be excreted by the saliva, when they are combined with it, and thus Bernard found that iodide of iron was secreted by the saliva, though lactate of iron was not; and I have sometimes thought that iodine has a similar effect upon quinine, because I have very frequently noticed patients complain of a persistent bitter taste in their mouth when I have given quinine combined with iodide of potassium, although they did not complain of this when either of the drugs has been given without the other.

CHAPTER X.

ACTION OF DRUGS ON RESPIRATION.

Respiratory Stimulants and Depressants.

It is usually supposed by naturalists that in the descent of man from some organism low in the scale of existence, he has passed, at a remote period, through a stage resembling the Ascidians or Tunicata. In these animals respiration is maintained by water being driven through a perforated sac in the meshes of which the nutritive fluids of the animal circulate. The contractile motions of the sac by which the circulation of fluid is maintained probably depend on a **nervous ganglion** situated between the oral and anal apertures as represented in the diagram (Fig. 77). We do not know whether or not this ganglion may influence the circulation which is maintained by the rhythmical contractions of the simple tube which serves as a heart. These drive the fluid first in one direction, and then after a while the action of the tube is reversed, and its contractions drive the fluid in the opposite direction. This ganglion in its functions would correspond with the **medulla oblongata** in the vertebrata, and thus the medulla oblongata may be looked upon as a lower and more **fundamental centre** than the brain or spinal cord.

We see this more distinctly perhaps by looking at the two diagrams (Figs. 78 and 79) representing an amphioxus and a fish. In the amphioxus respiration is kept up in much the same way as in the ascidian, the water passing from the pharyngeal to the atrial sac and through the atrial aperture or abdominal pore. There is no head and no organs of special sense, and so we have no brain whatever. But the body is elongated so as to remind us of an ascidian, having its ganglion and the part of the body-wall containing it so much extended as to remove the anal considerably from the oral aperture. The muscles of this elongated body require innervation, and thus the ganglionic mass is elongated into a cord called the myelon, which represents the spinal cord as well as the medulla oblongata. In ascidians then we have a mass corresponding to the medulla; in the amphioxus we have a mass corresponding to medulla and spinal cord.

In a fish the pharyngeal or branchial sac, instead of opening into the atrial sac, opens directly into the surrounding water.




FIG. 77.—Diagram of an Ascidian.




FIG. 78.—Diagram of Amphioxus. The water enters the oral aperture, passes through the openings in the pharyngeal sac into another cavity, whence it escapes by the abdominal pore.




FIG. 79.—Diagram of fish.

We have a head and organs of special sense, and therefore we have a large nervous mass or brain.

In these three members of the animal kingdom, therefore, we have the medulla as the lowest or fundamental centre, next the spinal cord, and lastly the brain. We might therefore expect that notwithstanding the apparently higher position and greater nearness of the **medulla** to the brain than to the spinal cord, the medulla would be **less** readily **affected by** many **drugs than** the **cord** or the **brain**, and this is what we find in the case of such drugs as alcohol, ether, or morphine, which appear to paralyse the nervous centres in the inverse order of their development—the brain first, spinal cord next, and medulla last.

There are some drugs, however, e.g. aconite, gelsemium, and

hydrocyanic acid, which seem to have a special paralysing action on the respiratory centre.

If we look at the ganglionic mass in an ascidian, represented in the diagram, we shall see that it sends some fibres to the pharyngeal sac and some to the anal sac. If these two sacs were to contract together they would oppose each other's action, and thus the passage of water through the branchial apertures would be stopped, and respiration consequently arrested. They must therefore act alternately, and this alternate action is regulated by the ganglion. This ganglion consists of numerous nerve-cells and fibres. As some of these have a more special connection with the pharynx, the group which they form may be called the pharyngeal centre or inspiratory centre.

Similar arrangements occur in higher animals, and the terms used in regard to their nervous system may lead to some confusion of thought; thus we speak of the respiratory, of the inspiratory, of the expiratory, and of the vomiting centres.

By **nerve-centres** we simply mean the **groups** of **cells** and fibres which are concerned in the **performance** of certain **acts**. They are not necessarily entirely distinct from one another, and the same group of ganglionic cells may form a part of several centres. Thus in the accompanying diagram (Fig. 80), the **respiratory** centre includes both **inspiratory** and **expiratory** centres, and the vomiting centre includes some ganglionic groups which form part of the inspiratory, and others forming part of the expiratory centres, besides other ganglion groups which are concerned with the simultaneous dilatation of the cardiac orifice of the stomach. On analysing this subject still further we find also that the inspiratory centre affects many muscles, and that it does not always affect them to the same extent. Thus in men the diaphragm takes a more active share in inspiration during the day than the thoracic muscles. During sleep the diaphragm takes a much less active part, and may be entirely quiet, while the thoracic muscles are more active, and the chest rises and falls more than during walking.

The **inspiratory** centre might be thus still further divided into **thoracic** inspiratory centre, and **diaphragmatic** inspiratory centre.

Such subdivisions appear absurd if we imagine that each centre represents a distinct nervous mass, and we become puzzled to understand how the medulla oblongata can contain so many distinct centres in a small bulk. But if we remember that the word '**centre**' simply indicates a group of cells and fibres connected with the performance of a particular act, and that two centres may be formed by the same ganglionic groups and differ from one another only by having a few ganglion cells more or less which alter the function they perform, no harm is done by the use of the term.

The act of **respiration** consists in the alternate enlargement and diminution of the thoracic cavity, so that the air is alternately inspired and expired.




FIG. 80.—Diagrammatic representation of various groups of ganglion cells, or 'centres,' in the medulla oblongata. The arrows indicate the directions in which the nerve-currents pass. Those pointing to the cells indicate sensory, those pointing from the cells indicate motor, nerves.

The **muscles** by which this is effected in ordinary respiration are the diaphragm and intercostal and scaleni muscles. The diaphragm descends, and the intercostal and scaleni muscles raise the ribs during **inspiration.**

Expiration is normally a **passive** act,[1] and is not performed by muscular action, but simply by the tendency of the diaphragm and thoracic walls to return to the position of the equilibrium from which they had been removed during inspiration, and by the contraction of the elastic walls of the air-vesicles distended by inspiration.

When the supply of oxygen is deficient, other muscles are called in to aid the inspiration. Expiration appears to be a passive act, not merely in ordinary respiration, but even in dyspnœa caused by the absence of oxygen. In some experiments by Bernstein[2] the inspiration and expiration were equally increased in a rabbit, when the air which it had breathed was replaced by hydrogen. But expiratory efforts are required both for the production of voice, and for the removal of irritants from the air-passages by coughing or sneezing; and forcible expira-

[1] Bernstein, *Archiv f. Anat. u. Physiol.*, 1882, p. 322.
[2] *Ibid., op. cit.*

tion is produced when an irritant is applied to the mucous membrane of the nose, of the larynx, trachea, or bronchi. As every one who has drunk a bottle of soda-water knows, carbonic acid is an irritant of considerable power to these mucous membranes, and when it is breathed instead of air or hydrogen the expiration becomes much more powerful, and is no longer a passive action, but an active one, performed by active muscular exertion.

The chief **respiratory centre** is situated in the medulla oblongata close to the end of the calamus scriptorius, at the point designated *nœud vital* by Flourens, because destruction of this point arrests the respiration and causes death.

It extends equally on both sides of the middle line in the medulla, each half regulating the breathing on the same side of the body. It has been supposed to be double, and to consist of inspiratory and expiratory centres which act alternately, but it would appear that in ordinary respiration the inspiratory centre only is active.

When the centre is injured by a puncture, as in Flourens' experiment, or when one half of it is destroyed, breathing usually stops entirely, but if the respiration be kept up artificially for several hours, the normal breathing again becomes established; and the prolonged continuance of artificial respiration has been recommended by Schiff in apoplexy.

When the connection between this centre and the respiratory muscles is cut off by dividing the spinal cord just below the medulla, respiration usually ceases entirely, so that at first sight it would seem that the respiratory centre is limited to the medulla.

The effects of strychnine show that this is not the case. This drug greatly increases the excitability of the respiratory centre, and when it is injected into the blood before division of the spinal cord, the respiratory movements still continue to some extent after the cord has been divided. When it is injected after section of the cord, the respiratory movements which had ceased again recommence to a slight degree.

The reason appears to be that the **respiratory centre** is not limited to the **medulla**, but extends to the upper part of the **spinal cord**, though the spinal portion is of itself too weak to keep up the respiratory movements, except when stimulated by strychnine.

The **amount of respiratory work** which this centre excites appears to **depend** to a great extent, though not entirely, upon the condition of the **centre** itself.

The **distribution** of the work is chiefly determined by the irritation of one or other of the afferent **nerves**, and these nerves also influence the amount of work.

The **centre** is stimulated, and the amount of work it does increased by a venous condition of the blood circulating in it.

An arterial condition of its blood lessens or completely abolishes its activity, so that when the blood is highly aërated by forced artificial respiration, a condition of **apnœa** is produced, in which no spontaneous respiratory movements occur.

This condition is much more readily induced when the excitability of the respiratory centre is lessened by drugs. In an animal poisoned by chloral, for example, it is very easy to induce it, and it lasts for a long time.

When the respiratory centre is excited, as by the injection of emetine or apomorphine into the circulation, it is difficult or impossible to produce this condition.

It is uncertain whether the stimulation which the venosity of the blood produces is due chiefly to the absence of oxygen or to the presence of carbonic acid. Possibly it may also be due to the products of imperfect combustion in the venous blood. Or all these three causes may share in the stimulation, though to what extent each does so is not known.

According to Bernstein, want of oxygen appears to stimulate the inspiratory and the presence of carbonic acid to stimulate the expiratory centre.[1]

As the blood becomes venous the activity of the respiratory centre increases, the respirations becoming quicker and deeper, and the accessory respiratory muscles are thrown into action. This condition is called **dyspnœa**. Finally the excitement extends to all the muscles of the body and we get general **convulsions**, which have usually an opisthotonic character. The eyeballs very often protrude during these convulsions, and the blood-pressure rises greatly from stimulation of sympathetic and vaso-motor centres in the medulla.

After the convulsions cease, the animal usually lies motionless, and the heart as a rule continues to beat for a short time after the respirations have ceased.

The excessive venosity of the blood in this condition has paralysed the nerve-centres, but if artificial respiration be now commenced and the blood becomes gradually aërated, the conditions just described are again passed through in the reverse order: convulsions first reappearing, then dyspnœa, next normal breathing, and, if the respiration be pushed far enough, apnœa.

Asphyxial convulsions only occur in warm-blooded animals, and not in frogs, and when we find that any drug produces convulsions in mammals and not in frogs we usually assume that the convulsions are due to asphyxia produced by the action of the drug on the respiration or circulation, and not to a direct irritant action upon the motor centres. If, on the other hand, we find that the convulsions occur in frogs as well as in mammals, the presumption is in favour of their being due to the direct irritant action of the drug on motor centres.

[1] Bernstein, *op. cit.* p. 324.

Blood becomes venous when the external respiration or interchange of gases between it and the external air is arrested while internal respiration continues.

Internal respiration or interchange of gases occurs between the blood and the tissues outside the vessels which are consuming oxygen and deriving it from the blood. But the blood although fluid is itself a tissue and likewise consumes oxygen, so that it will become venous if left to itself in a thoroughly-stoppered glass bottle.

External respiration may be arrested or diminished by—

(1) Interfering with the access of air to the blood; or
(2) ,, ,, ,, ,, ,, blood to the air; or
(3) ,, ,, ,, power of the blood to take up and give off oxygen.

The access of air to the blood may be prevented by obstruction to the air-passages or alteration in the structure of the lung; thus anæsthetics may obstruct respiration by allowing vomited matters to enter the trachea and plug it mechanically. Apomorphine may lead to obstruction of the bronchi by profuse secretion from the mucous membrane, and large doses of antimony may cause consolidation of the lung.

Air may be prevented from reaching the blood by any obstruction in the respiratory passages.

The respiratory passages may be obstructed by spasmodic closure of the glottis or of the nostrils in rabbits when an irritating vapour is inspired. This source of obstruction is easily avoided by putting a cannula into the trachea and allowing the vapour to be inspired through it. Another source of obstruction is the formation of plugs of mucus or clots of blood in the trachea or in the cannula, which has been introduced into it. Occasionally a plug of mucus, and sometimes a clot of blood, forms in the tracheal cannula and seriously impedes the respiration, whether natural or artificial, without being perceived by the experimenter. In order to be sure that such an occurrence has not taken place and vitiated the results, it is always advisable, on removing the cannula from the trachea at the end of an experiment, to blow through it and see that its lumen is perfectly unobstructed.

Access of air to the blood may be prevented also by paralysis of the muscles of respiration; thus curare will produce it by paralysing the ends of the motor nerves, hydrocyanic acid by paralysing the respiratory centre, and snake poison by paralysing both.

The blood may be prevented from reaching the lungs by arrest of the circulation either local or general, and may thus become venous, either locally or generally.

The **venosity** of the blood circulating in the medulla may be altered **locally** without any change in the rest of the body. Thus if the carotid and vertebral arteries are tied, the blood stagnates in the vessels of the medulla, and there becoming venous causes dyspnœa and convulsions, which again disappear when the ligatures are loosened and the circulation re-established.

Dyspnœa and convulsions are likewise produced by alteration in the **general** circulation, e.g. by loss of blood, as is seen when an animal is bled to death, or when the supply of blood in the arteries is greatly diminished by ligature of the portal vein, which causes the blood to accumulate and stagnate in the capacious veins of the intestine.

Stoppage of the **heart**, either by ligature directly applied to it or by the action of drugs upon it, causes asphyxia and convulsions.

Arrested circulation through the **pulmonary** vessels by emboli has a similar action. This sometimes leads to error in regard to the action of drugs when these are injected, as is often done, into the jugular vein.

If they contain solid particles, these may give rise to embolism in the pulmonary arteries and lead to the belief that the drug has a tetanising action, when, as a matter of fact, it has nothing of the kind. Thus, in making an experiment on condurango, I injected an infusion into the jugular vein of a rabbit, and it rapidly died with symptoms resembling those of strychnine-poisoning. The cause of this, however, was simply embolism of the pulmonary vessels, due to undissolved particles in the infusion, and when this was avoided by injecting the drug into the peritoneal cavity, no symptom whatever was produced. Gianuzzi, in his experiments on this drug, appears to have fallen into the same error as I did at first.

Altered condition of the **blood** also gives rise to dyspnœa, as is seen in the breathlessness of anæmia, where the blood is unable to take up the quantity of oxygen necessary for any exertion, and the patient pants violently after any quick movement, such as going up stairs.

Dyspnœa and even convulsions are also caused by nitrites, e.g. nitrite of amyl or sodium, which lessen the power of the blood to give off oxygen, and by carbonic oxide, which replaces the oxygen in the blood.

It must be remembered, however, that, whatever may be the remote cause of dyspnœa, its direct cause is the condition of the nerve-cells in the medulla, and if these are unable to take up oxygen, and give off carbonic acid to the blood, dyspnœa may occur, although the blood itself circulating in the medulla contains abundance of oxygen.

In the case of carbonic-oxide poisoning the blood cannot take up oxygen from the lungs, although there is abundance of oxygen present; and in a similar way the nerve-cells of the medulla may possibly be rendered by certain drugs unable to take up oxygen from the blood circulating through the medulla.

In simple suffocation the **internal respiration** of the nerve-cells in the medulla is arrested by the general venous condition of the blood; in carbonic-oxide poisoning by the oxygen being absent

from the hæmoglobin; in nitrite poisoning by the oxygen being locked up in methæmoglobin. In all those cases the condition of the blood is betrayed to the eye by the appearance of the mucous membranes, which in suffocation and in nitrite poisoning become dark and livid, and in carbonic-oxide poisoning of a cherry-red colour. Perhaps the change is most conveniently seen in the comb of a cock poisoned by these substances; in it the alteration in the colour of the blood produced by artificial respiration is readily observed. The dependence of convulsions upon the blood is also easily observed: the convulsions appearing as the comb becomes livid, and again disappearing when artificial respiration has been employed, and the colour of the comb becomes bright. In poisoning by hydrocyanic acid, however, I have observed that convulsions come on while the mucous membranes are still of a bright colour, so that we may conclude that they are not due to a venous condition of the blood, as in ordinary suffocation. They might be due to the formation of a compound between the hydrocyanic acid and the blood, as in poisoning by nitrites or carbonic oxide; but accurate analyses have shown that hydrocyanic acid does not displace the oxygen in hæmoglobin like carbonic acid, nor lock it up in the form of methæmoglobin like the nitrites. We are therefore obliged to consider the possibility that the dyspnœa and convulsions produced by hydrocyanic acid are not due so much to its effect upon the blood circulating in the medulla as to an action on the cells of the medulla itself, by which it prevents the ordinary internal respiration taking place in them.

Action of Drugs on the Respiratory Centre.

A useful method of testing the action of the drug itself on the respiratory centre is to perform artificial respiration vigorously so as to produce apnœa, to allow the respiration to become normal again, then to inject the drug and again try to produce apnœa. If the drug has excited the respiratory centre, apnœa will be much more difficult to produce after its injection than before, and will last a shorter time; if it has depressed it, apnœa will be more easily produced, and will last longer.

Apnœa lasting for a short time may be readily produced by taking five or six very deep breaths, and the effect of drugs on the respiratory centre may be readily tried by anyone in the following way. Laying a watch before him, shutting his mouth and holding his nose, let him first ascertain how many seconds he can hold his breath after previous ordinary respiration. Next let him produce a certain amount of apnœa by six or more deep respirations, and again ascertain how long he can hold his breath. After repeating these observations several times, let him take the drug to be tested and repeat them again, taking care that all the circumstances should be the same as before.

The **activity** of the **respiratory centre** is augmented by heat, so that the respirations become both quicker and deeper, and more respiratory work is done. Strychnine, ammonia, atropine, duboisine, brucine, thebaine, apomorphine, emetine,

nembers of the digitalis group, salts of zinc and copper, have a imilar action.

It appears to be first excited and then depressed by caffeine, olchicin, nicotine, quinine, and saponine.

It is diminished by cold, so that the respirations become low and shallow. Chloral, chloroform, ether, alcohol, opium, physostigmine, muscarine, gelsemine, aconite, and veratrine in large doses, all have a similar action.

The action of drugs on the respiratory centre is one of great mportance, not only as giving us a definite basis on which to found a plan of treatment in respiratory diseases, but as helping us to preserve life in cases of poisoning—drugs which stimulate being antagonised by those which depress the respiratory centre, and *vice versâ*.

The chief **afferent nerves**, by which the distribution of the respiratory movements is altered, may be divided into two classes —those having an inspiratory and those having an expiratory action.

The **expiratory** are the nasal branches of the fifth, the superior laryngeal, the inferior laryngeal, and the cutaneous nerves, especially of the breast and belly.

The chief **inspiratory** are the branches of the vagus going to the lung, but all sensory nerves when slightly stimulated appear also to have an inspiratory action.

The vagus appears, however, to contain both expiratory and inspiratory fibres, which are alternately stimulated by the condition of the lung. Expansion of the lung appears to stimulate mechanically the inhibitory or expiratory fibres; while its collapse stimulates the accelerating or inspiratory fibres.

When the **expiratory** nerves are stimulated, the respiratory movements become **slower** and deeper; and if the stimulation be strong they may stop altogether in expiration, with the diaphragm in complete relaxation.

Stimulation of the **inspiratory** nerves causes the respiration to become **quicker** and shallower, and at length to stop in inspiration, the diaphragm being in a state of tetanic contraction.

These are the general **results**, but they are **not** quite **constant**. The reason for this inconstancy may be either that all the nerves contain both inspiratory and expiratory fibres, or that the same fibres may stimulate either the inspiratory or expiratory centres, according to the strength of the stimulus and the condition of the animal. Thus, when the vagus is divided, the stimulus which is conveyed to the respiratory centre being removed, the respirations usually become very slow; when the central end of the divided nerve is irritated they become quick, and a very strong current may stop them in inspiration. But this is not always so: when the nerve is very much exhausted, irritation by a strong current may have an entirely **opposite** effect,

and cause the respiration to stop in expiration instead of inspiration.

The probability that the same nervous fibres may, under different conditions, excite either inspiration, expiration, or the two alternately, is rendered still greater when we consider some other experiments; and the contradictory results which have been obtained by various observers in regard to the action of drugs may depend to a great extent on the strength of the stimulus they have used and the state of exhaustion of the animal. Thus Langendorf has found that all sensory nerves in the body when slightly stimulated have an inspiratory, but when stimulated more strongly have an expiratory action. Rosenthal found that irritation of the crural nerves caused alternately deep inspiration and expiration in animals which were not narcotised. In narcotised animals, Langendorf, on slight irritation, observed an inspiratory effect, indicated by quickening of the respiration or slight inspiratory tetanus; but when the experiment was continued long, or the irritation was increased, the contrary or expiratory effect was observed, indicated by a slowing of the respiration.

On the hypothesis that the various actions of respiration depend upon individual centres, inspiratory, expiratory, and in-




FIG. 81.—Diagram showing the position of the respiratory centre, and the afferent nerves which influence it. Inspiratory nerves are indicated by plain, and expiratory by dotted, lines.

hibitory, it is exceedingly difficult, or impossible, to understand the contradictory results of various experimenters; but the question seems much less intricate when we regard it as due to th

nterference of stimuli passing at different rates in different irections, or to different distances, according to the strength of ne stimulus and the irritability or exhaustion of the nervous ystem.

In regard then to inhibitory or slowing, and to stimulating or ccelerating nerves or fibres, it must be carefully borne in mind hat the same fibres may possibly have either the one or the other ction, according to the conditions under which they are acting.

If we keep this carefully in view we may continue to use the erms accelerating and slowing or inspiratory and expiratory nerves as convenient means of expression. These are shown n the accompanying diagram (Fig. 81).

The movements of respiration are most easily counted, and their depth nd the relation of inspiration to expiration are best noted by causing hem to register themselves on a revolving cylinder. Various means of doing this have been suggested by different authors. One of the simplest consists of a needle pushed into the diaphragm, and connected by a thread with one of Marey's levers. Marey's pneumograph consists of a cylinder of soft indiarubber, enclosing a spiral spring, whose extremities are connected with two pieces of metal which form the ends of the cylinder. A band is passed round the thorax of the animal, and attached o the ends of the cylinder. The interior of the cylinder is brought into communication with one of Marey's levers, and as each respiratory movement draws the ends of the cylinders wider apart, or allows them to approach, he air is rarefied or compressed, and a corresponding movement is transmitted to the lever. Bert has modified this, and made it more sensitive by making the cylinder itself of metal, and its ends of indiarubber. Another method—one more ordinarily employed—is to introduce one limb of a T-tube into the nostril or trachea of an animal, or connect it with a tracheal cannula. The respired air passes through the other end, and the third limb is connected with one of Marey's levers.

In the attempt to find out whether the alteration in respiration produced by any drug is due to its action on the respiratory centre, or on some of the nerves which influence it, we may find the following table useful by showing at a glance the chief ways in which the respirations may be rendered **quicker** or **slower**:—

- The respiratory movements may be **quickened** by
  - Excitement of nerves.
    - Stimulation of the vagus.
    - Stimulation of optic nerve.
    - Stimulation of acoustic nerve.
  - Greater excitement of respiratory centre.
    - Action of brain (voluntary).
    - Increased temperature of blood.
    - Increased venosity of blood.
    - Action of drugs.
- The respiratory movements may be rendered **slow** by
  - Diminished excitement of respiratory centre.
    - Diminished venosity of blood.
    - Action of drugs.
    - Action of brain (voluntary).
  - Nervous influences.
    - Paralysis of vagi.
    - Stimulation of superior laryngeal nerves.
    - Stimulation of inferior laryngeal nerves.
    - Stimulation of nasal nerves.
    - Stimulation of cutaneous nerves.
    - Stimulation of splanchnic nerves.

If the drug to be experimented on be injected subcutaneously or into the veins, the actions on the respiratory centre and on the vagi are the chief points which require attention; but if we are experimenting with a vapour, its local action on the nasal, laryngeal, and possibly, also, on the pharyngeal nerves [1] must be carefully attended to, as it may greatly modify its general action on the respiratory centres. Thus Kratschmer has found that tobacco-smoke inhaled by a rabbit through its nostrils, or blown upward into the nasal cavity from an aperture in the trachea, will cause arrest of breathing in a state of expiration from the irritating effect of the vapour of the nasal branches of the fifth, while it has no such effect when blown into the lungs. Ammonia, when inhaled, also arrests the respiratory movements in the same way; but Knoll [2] has observed that if it be blown into the lungs while the nostrils are carefully protected from its influence, it causes accelerated and shallow breathing, alternating with slow and deep respirations, and occasional stoppages in the position of expiration, obviously from its action on the different fibres of the vagi.

Action of Drugs on the Respiratory Nerves.

In experiments regarding the effect of drugs upon the respiration, the voluntary influence of the brain is excluded by the use of ether, chloroform, opium, or chloral, or by section of the crura cerebri. In the case of such poisons as cause sickness, allowance must be made for the effect of gastric irritation. It will usually be found that before vomiting occurs the respiratory movements are very rapid, but they become slower after vomiting has taken place. As the chief afferent fibres from the stomach are contained in the vagus, the effect of irritation of the gastric, as well as of other fibres contained in these nerves, is prevented by their division. Sometimes the action of a drug on the peripheral ends of the vagus and upon its roots in the medulla may produce exactly opposite effects upon the respiration. Thus atropine appears to lessen the excitability of the respiratory fibres of the vagus, while it stimulates the respiratory centre. Such an action may be to a certain extent inferred from the respiration becoming slower almost immediately after the injection of the drug into the jugular vein, and while it is still passing through the lungs, and by this slowing being quickly succeeded by acceleration when the drug begins to circulate through the medulla.

There are two kinds of experiment by which such a conclusion may be tested. The one is to apply the drug first to the

[1] Brown-Séquard, *Archives of Scientific and Practical Medicine*, p. 94.
[2] *Sitzungsber. der Wien. Acad.*, vol. lxviii. Abt. 3, p. 255.

medulla by injecting it into the carotid artery, and seeing whether acceleration occurs at once and afterwards becomes less when the drug has had time to pass round again to the lungs. The other way is to divide the vagi before the injection and observe the effect. Any alteration in the respiration in the way of either quickening or slowing which the drug produced in the uninjured animal should remain the same after division of the vagi if its effect were due to its action on the medulla, but will be absent if it were due to an action upon the peripheral ends of the vagi.

This method was introduced into pharmacological research by Von Bezold in his admirable research on atropine, and it is the one usually employed.

There is one fallacy, however, which must not be entirely lost sight of, which is, that after division of the vagi the nerves which remain in connection with the respiratory centre have chiefly a slowing action on the respiration; and thus a drug which really renders the respiratory centre more susceptible to reflex influences might seem to have a depressing action upon it.

While atropine injected into the jugular vein seems to produce first a slowing of the respiration, due to its paralysing action on the vagus ends, and afterwards a progressive quickening as more of it is carried out of the lungs into the medulla, physostigmine, muscarine, and veratrine have an opposite action, quickening the respiration at first by their stimulating action on the vagus ends, and afterwards slowing it by their action on the medulla.

In the action of veratrine upon the pulmonary branches of the vagus we may notice a resemblance to the stimulant action which, as already mentioned, it exerts upon the nerves of ordinary sensation. If the sensory branches of the vagus are affected by drugs in a somewhat similar way to those of ordinary sensation, as the action of veratrine might lead us to imagine, we should expect them to be much stimulated also by aconite, and, indeed, according to Boehm and Ewers, this is the case. The respiratory changes produced by aconite are regarded by them as due, in part, to irritation of the peripheral ends of the vagus, and disappear on section of the vagi or the administration of atropine.

Sternutatories or Errhines.

These are drugs which cause **sneezing** and increased secretion from the nose when locally applied to it. The drugs must be in a pulverised condition. The chief are:—

Tobacco (snuff).	Euphorbium.
Veratrum album.	Sassy bark.
Ipecacuanha.	Saponine.

Irritation applied to the nose is transmitted by the nasal branches of the fifth to the **respiratory** centre in the medulla oblongata, and excites the sudden and forcible expiratory movements of sneezing. At the same time, however, the stimulus is transmitted to the vaso-motor centre, and the **blood-pressure** becomes considerably increased by the contraction of small vessels throughout the body, even when no sneezing occurs. When sneezing takes place, the pressure is still further increased by the muscular efforts which occur in the act. It is probable that there is not only general rise in blood-pressure but also that local dilatation of the **cerebral** vessels is reflexly produced by the nasal irritation, and thus a **stimulant** effect is produced on the brain. Snuff is therefore employed as a luxury giving a feeling of comfort and enabling the snuff-taker to think more clearly—'clearing the head' as it is often termed (*vide* p. 193).

Uses.—Though comparatively little used now, sternutatories were formerly employed in failure of memory, deafness, and severe persistent headache. From the violent expulsive efforts which they induce, they were given also to cause the expulsion of foreign bodies from the air-passages, and to hasten the expulsion of the child in cases of lingering labour where no obstruction was present, but where expulsive force was deficient. They were given also in order to try and check diseases at the commencement, by what was termed 'shock to the system.'

One curious thing is to be remarked, that stimulation of one part of the respiratory tract may arrest abnormal actions in another. Thus Marshall Hall has shown that actual sneezing may frequently be prevented, after the inspiration by which it is usually preceded has occurred, by forcibly rubbing the end of the nose or by tightly compressing the nostrils. In a similar way irritation of the interior of the nose by snuff will sometimes arrest obstinate hiccough.

Contraindications.—On account of the high blood-pressure which they produce their use is by no means free from danger in persons affected with atheroma or a tendency to pulmonary hæmorrhage or apoplexy, as they may cause rupture of a vessel; and in those who suffer from hernia or from prolapsus of the uterus, they may seriously increase the gravity of these affections.

Respiratory Sedatives.

These are substances which diminish **cough** and spasmodic difficulty of breathing.

They may be divided into drugs which—

(1) Tend to **remove** the **irritation** which acts as the exciting cause of the cough.

(2) Tend to **lessen irritability of** { (*a*) the **afferent nerves** in the lungs; (*b*) the **respiratory centre.**

Pathology of cough.—Cough consists in a deep inspiration followed by a forcible expiration with closed glottis, so that the air is driven rapidly through the larynx, carrying with it foreign substances, liquid or solid, which may be present in the air-passages. As it is a modified respiratory act, the nerve-centre by which the muscles employed in it are co-ordinated is situated in the medulla oblongata.

The afferent fibres by which cough may be excited are chiefly branches of the vagus. One of the most powerful is the superior




FIG. 82.—Diagram of the afferent nerves by which cough may be excited. These nerves are shown passing to the respiratory centre in the following order from above downward—from the auditory meatus, pharynx, upper part of œsophagus, larynx and trachea, bronchi, lung, costal pleura, liver and spleen.

laryngeal nerve distributed to the glosso-epiglottidean folds and to the whole of the interior of the larynx, and this being a special expiratory nerve we find that irritation of the larynx and also of the trachea is usually characterised by a cough with very violent expulsive efforts. Irritation of the mucous membrane of the trachea especially at the bifurcation of the bronchi, and irritation of the substance of the lung, also give rise to cough; and irritation of the costal pleura and of the œsophagus does so also.[1] Irritation of the auditory meatus at the point to which the auricular branch of the vagus is distributed will also cause coughing; and cough appears to be also induced by irritation of certain parts of the interior of the nose. These are the surfaces of the inferior and middle turbinated bones, the most sensitive

[1] Kohts, *Virchow's Archiv*, 66, 191.

part being the posterior end of the inferior turbinated bone and the portion of the septum immediately opposite.[1] The sudden application of cold to the skin on various parts of the body will sometimes cause coughing. Probably the cough in this case is not due to the stimulus being conveyed directly to the respiratory centre by the cutaneous nerves, but to its causing congestion of the air-passages, as in Rossbach's experiments (p. 252). The congestion then causes irritation of the sensory nerves of the bronchi, and occasions cough.

I have seen irritation of the liver and spleen, induced by percussion over them, in a man suffering from chronic enlargement due to malaria, likewise cause coughing.[2] In addition to those nerves, however, it appears that irritation of the glosso-pharyngeal branches distributed to the **pharynx**, where the digestive and respiratory tracts coincide as they cross one another, may not only excite coughing, but may also act as an auxiliary to irritation of the branches of the vagus. The combined action of the two may thus induce cough, when irritation of the vagus alone would not do so. Thus we find that many persons begin to cough as soon as they lie down, but that sometimes by lying round partially on the face, the cough ceases. In these persons the uvula is often found to be long and much congested, and the tickling which it produces as it rests upon the pharynx or pillars of the fauces seems to aid the irritation in the respiratory passages, and produce cough.

Cough due to irritation of those parts of the respiratory tract where the nerves are chiefly expiratory, as the pharynx, larynx, trachea, and large bronchi, is usually, as might be expected, loud, explosive, and prolonged; while cough due to irritation of those parts where the nerves are chiefly inspiratory is short and hacking (Fig. 82).

Cough produced by irritation of the pharynx where the respiratory and digestive passages cross one another, is not only violent, noisy, and barking, but, as we would naturally expect, is not unfrequently accompanied by retching or vomiting.

Pharyngeal irritation may accompany dyspepsia, and it is probably the origin of the so-called **stomach-cough**. Irritation of the stomach itself, or of its nerves, causes vomiting, but does not produce cough.

Nevertheless there is a *rationale* for the common expression 'stomach-cough.' In some experiments on the reflex origin of cough, R. Meyer[3] has noticed that when some part, from which

---

[1] *On Nasal Cough*, by John N. Mackenzie, M.D., reprint from *The American Journal of the Medical Sciences*, July 1883.

[2] These observations were made in January and April 1879, but not published. Naunyn, in a paper published in the *Deutsch. Archiv f. klin. Med.* in March 1879, recorded similar observations.

[3] R. Meyer, *Correspondenzblatt d. Schweizer Aerzte*, No. 1, 1876.

cough can be reflexly induced, is already in a state of irritation, cough can be brought on with great ease by irritation of a neighbouring part which would not by itself cause cough. Something of this kind appears to occur with the stomach, for although irritation of the stomach alone will not cause coughing, yet it will do so if irritation of the larynx and trachea are already present. Thus I have observed violent spasms of coughing occur, along with acidity and heartburn, some time after a meal, in a person suffering from congestion of the pharynx, larynx, or trachea. The connection between the cough and the acidity was shown by the cough ceasing as soon as the acidity was relieved by a dose of alkali and the consequent removal of the irritation to the stomach, which the acidity had produced.

Remedies which Lessen Irritation.

Soothing remedies applied to the pharynx greatly relieve cough, although they do not reach so far down as the epiglottis. Mucilaginous remedies are very useful for this purpose, and they may either be employed alone or as vehicles for the local application of sedatives such as morphine. Thus, a piece of extract of liquorice allowed to dissolve in the mouth, a marsh-mallow lozenge, a gum-jujube, or a sip of linseed-tea, by covering the back of the throat with a mucilaginous coating, will lessen cough to a great extent. Such remedies are especially useful where the cough depends on congestion of the pharynx and trachea. In such cases no abnormal sound at all may be heard in auscultation, and the cough being due to irritation of the parts supplied by the superior laryngeal nerve, has a peculiarly convulsive expiratory character often termed 'barking.'

Other remedies lessen cough by **diminishing congestion** of the respiratory passages, and thus lessening the irritation which causes the cough. Many of these also, however, come under the class of **expectorants** (p. 250), inasmuch as the diminished congestion is frequently associated with increase of the expectoration. Others, again, although they diminish cough, are included rather under the head of '**cardiac tonics**,' or sedatives. Digitalis is an example of this. In the congestion due to cardiac disease, and even in that due to bronchitis, digitalis, by strengthening the heart and by contracting the vessels, may lessen the congestion in the lungs, and give the patient relief. Squill and a number of other drugs have an action on the blood-vessels similar to that of digitalis.

Other remedies, such as the vapour of hydrocyanic acid, conium, stramonium, and tobacco, have a **local sedative** action on the lung, and may lessen cough; they also are used in order to diminish local spasm of the bronchioles, and thus to relieve spasmodic asthma.

Pulmonary Sedatives.

These are remedies which lessen the irritability of the respiratory centre or of the nerves connected with it. The chief drugs which diminish the excitability of the **respiratory centre** are opium and its principal alkaloid, morphine. Morphine and opium have a double action in lessening cough: they not only **lessen** the excitability of the respiratory centre, but they diminish the secretion of mucus in the bronchial tubes, and probably thus also lessen the irritation. Hydrocyanic acid has also a sedative action on it, but it is by no means so powerful as the others.

Belladonna and stramonium have a rather peculiar action stimulating the respiratory centre, and at the same time appearing to lessen the excitability of the ends of the vagi in the lungs. Atropine has but a very slight and uncertain action on the respiratory centre in preventing cough, if indeed it has any at all. It has, however, a powerful effect—much more powerful than that of opium,—in completely **arresting** the **secretion** from the bronchial tubes. The cases in which it is useful are therefore those where the cough depends upon excessive secretion. In cases where the mucous membrane is already too dry it would be injurious rather than beneficial.

When apomorphine and morphine are given together they do not destroy each other's action, so that from the combination we get increased secretion from the mucous membrane, with diminished irritability of the respiratory centre, and consequently lessened cough. The cases in which this combination, then, is useful, are those where there is difficulty of breathing, continual cough, and thick tenacious mucus. When morphine and atropine are given together, also, they do not destroy each other's action and thus dryness of the mucous membrane is produced, along with diminished irritability of the centre for coughing. This combination is therefore useful in cases of catarrh, emphysema and phthisis, where there is copious secretion of mucus. In phthisis it is especially indicated on account of the beneficial action of atropine in also lessening sweating. Where the copious expectoration depends upon the presence of a cavity, and not on excessive secretion from the bronchi, it will not be much affected by the use of these remedies.

Expectorants.

Expectorants are remedies which facilitate the **removal** of **secretions** from the **air-passages.** The secretion may be rendered more easy of removal, either by an alteration in its character rendering it less adhesive and more easily detached

from the air-passages, or by increased activity of the expulsive mechanism.

Our knowledge of the use of expectorants is founded chiefly on empiricism. We are almost entirely indebted to the recent experiments of Rossbach for any precise information as to their mode of action.[1]

The secretion from the air-passages, like other secretions, depends partly upon the condition of the circulation, and partly on the secreting cells themselves.

In healthy conditions the increased secretion and increased circulation of blood in the mucous membrane go together, but just as in the case of the sweat-glands, these two factors may occur independently of each other, and secretion may take place rapidly when the circulation is diminished and the mucous membrane is anæmic, and, on the other hand, it may stop altogether when the vessels are dilated and the mucous membrane is congested. The latter happens both in cases of disease and in animals poisoned by atropine.

The **secretion** from the normal respiratory mucous membrane consists of a thin solution of mucin which dries very slowly, and is only secreted in sufficient quantity to keep the mucous membrane moist. It is slightly adhesive, and any particles of dust, &c., which may have found their way into the trachea, will stick to the walls of the air-passages, and will be gradually moved up towards the mouth by the **cilia** with which the cells of the mucous membrane are furnished. Any excess of mucus secreted in consequence of irritation will also be moved upwards by the cilia in a similar manner. In the ciliated cells of the mucous membrane we recognise a structure which is frequently met with in animals lower down the scale of existence, and the mucous membrane of the respiratory passages appears to resemble the parts of lower organisms, in being very slightly controlled by the central nervous system. When not irritated it secretes slowly and regularly; when irritated locally the secretion is increased, but irritation of the nerves passing to it, such as the vagus, the superior or inferior laryngeal, or the sympathetic, does not cause any increase as it does in the case of the submaxillary gland. These nerves, however, can influence it indirectly through the circulation, for when they are divided an increased dilatation of the vessels occurs in the mucous membrane of the trachea, a freer circulation of blood occurs, and increased secretion is thus indirectly produced. When they are irritated, however, and anæmia of the trachea produced, the secretion is not arrested, but continues.

The **circulation** in the mucous membrane is readily affected reflexly by irritation of other parts of the body. When, for

[1] *Festschrift der Julius-Maximilian-Universität zu Würzburg*, Leipzig.

example, a warm poultice is laid for five or ten minutes on the belly of an animal, and then afterwards replaced by ice, the mucous membrane of the trachea and larynx becomes in half a minute deadly pale from the contraction of its vessels. Though the ice is still allowed to remain on the belly, the tracheal mucous membrane quickly changes colour, and to the paleness succeeds first slight redness, then deep red congestion, and in five or ten minutes lividity. This lividity shows that the congestion is not arterial but venous, and that the circulation, instead of being quicker is really slower. Along with the increase of congestion in the mucous membrane, the amount of **mucus** secreted increases. When the ice is removed for half an hour, and again replaced by the warm poultice, the bluish-red colour of the mucous membrane almost immediately disappears and gives place to a rosy colour which is, however, redder than normal. Ice again applied will cause a second contraction of the vessels and paleness, though much less than before. These experiments show how sensitive is the mucous membrane of the trachea to reflex stimulation of other parts of the body by heat or cold, and enable us to understand more readily how a draught of cold air on some part of the body should cause inflammation of the respiratory organs.

Action of Drugs on the Secretion.—Alkalies, such as carbonate of sodium, injected into the blood, lessen, or in large quantity completely arrest, the secretion of mucus from the trachea.

This experimental result is in contradiction to the teaching of clinical experience, which shows us that alkalies increase the amount of secretion, and render it more fluid. The results of clinical observation are quite as certain as those of Rossbach's experiments, for we may not only remark the greater quantity of expectoration, and its greater fluidity in persons taking alkalies, but we may note the alteration which they occasion in the amount and nature of the moist *râles* heard within the lungs. This can be observed most readily in persons suffering from phthisis, especially round the margin of the cavity. After catching a slight cold an extension of consolidation may be remarked, in which moist *râles* readily occur on the administration of dilute alkalies. When these are continued until the expectoration has been free for a day or two and the *râles* diminish, acids may be given with advantage, so as to dry up the expectoration still more. But if the acid is given too soon the expectoration diminishes, but the cough increases and becomes troublesome to the patient.

In all probability the difference between the results of clinical observation and Rossbach's experiments depends upon the difference of dose, the quantity usually given to a patient being proportionately much smaller than that which he employed. We

are able to observe a similar difference between the effects of small and large doses in the case of iodide of potassium; a small dose of a grain and a half, taken by a healthy man three times a day, will almost certainly cause the nose to run freely, while if the dose be increased to ten, twenty, or thirty grains the excessive secretion will almost certainly be arrested.

The local application of one to two per cent. solution of sodium carbonate has very little action. The local application of strong liquor ammoniæ causes both congestion and increased secretion of mucus. Very strong solutions cause a croupous exudation from the surface of the mucous membrane. The local application of dilute acetic acid (three per cent. solution) has a similar action to weak solutions of ammonia: the mucous membrane becoming redder and secreting more mucus.

When acetic acid was given internally, Rossbach observed in one case that the mucus, which was before watery and clear, became gelatinous and opalescent. This result agrees with what one finds clinically, that acids dry up the secretion and make it harder to expectorate.

Among **astringents** Rossbach tried tannin, alum, and nitrate of silver; the first two when locally applied made the mucous membrane appear paler by altering the epithelium and rendering it opaque, so that the vessels underneath could hardly be seen; at the same time they arrested the secretion of mucus almost entirely. A four per cent. solution of nitrate of silver also caused opacity of the epithelium, arrest of secretion, and dryness of the mucous membrane. There appears to be a difference in the action of nitrate of silver on the mucous membrane of the nose and on the trachea, as when the inside of the nose is touched by it, it causes a profuse secretion, whereas it causes dryness in the trachea.

The vapour of oil of turpentine mixed with air arrests the secretion of mucus, whilst a current of air alone, without admixture with oil of turpentine, will act as an irritant to the mucous membrane and increase secretion. Here again, however, a marked difference is to be seen in the effect of small and large doses, for when a watery solution containing from one to two per cent. of oil of turpentine was dropped directly on the mucous membrane, it became less vascular, but the secretion was at once increased, instead of being diminished, as it was by the vapour.

This action of oil of turpentine is of great therapeutical importance, inasmuch as in many cases of bronchitis we have profuse secretion with vascular congestion, a condition likely to be removed by the vapour of oil of turpentine.

Apomorphine, emetine, and pilocarpine, when given internally, all cause a great increase of the secretion of mucus, but they do not alter the vascularity of the mucous membrane. The

most powerful of all these is pilocarpine, and after it come apomorphine and emetine. One would therefore expect that pilocarpine would be the best remedy in catarrhal conditions, but this is not the case, for its other actions on the salivary and sweat glands and on the heart render its administration unpleasant for the patient. Sometimes also in children œdema of the lungs has followed its use. Apomorphine, on the contrary, has been found by Rossbach to be of the greatest service in catarrh of the larynx, trachea, and bronchi, both in adults and in children. Ipecacuanha has long been recognised as one of the most useful expectorants, but the dose given is often too small.

Rossbach's experiments have shown that the consequence of sudden changes of heat and cold applied to a part of the body is congestion of the respiratory mucous membrane with diminished circulation and stagnation of blood in the veins. A similar condition occurs in many cases of chronic bronchitis, and in them we not unfrequently find great benefit from **vascular tonics** such as digitalis, which, in addition to stimulating the vaso-motor centre, increase the activity of the heart, and thus tend to maintain the pulmonary circulation.

In what way cod-liver oil affects the bronchial mucous membrane it is perhaps hard to say, but there is no doubt whatever that it is one of the most efficient expectorants that we possess, and in cases of chronic bronchitis it affords more relief than any of the ordinary expectorants. It is possible that, being a form of fat which is readily assimilated, it is taken up by the young epithelial cells of the respiratory mucous membrane, and thus enables them to grow and maintain their attachment to the mucous membrane, instead of being at once shed in an undeveloped form as pus-cells in the expectoration.

Action of Drugs on the Expulsive Mechanism.—The expectorants which act by increasing the activity of the expulsive apparatus may be divided into—

(1) Those which increase the rapidity of the **ciliary motion** in the tracheal mucous membrane.

(2) Those which increase the activity of the **respiratory centre.**

We have no direct experiments or observations on the rapidity of the ciliary motion in the bronchial mucous membrane of the higher animals, but ammonia has been found to increase its rapidity in the mucous membrane of the frog.

The remedies which increase the activity of the respiratory centre are: strychnine, ammonia, emetine, ipecacuanha, belladonna, atropine, senega, and saponine. They are used more especially in cases of bronchitis where the expectoration is imperfect.

The chief expectorants have been divided into depressant and stimulant. They are as follows:—

Depressant Expectorants.

Generally tending to depress
he heart, lessen blood-pressure,
nd increase secretion.

- Antimonial preparations.
  - Tartar emetic.
- Alkalies.
- Ipecacuanha.
  - Emetine.
- Lobelia.
  - Lobeline.
- Jaborandi.
  - Pilocarpine.
- Apomorphine.
- Quebracho.
  - Quebrachine
- Potassium iodide.

Stimulating Expectorants.

Generally stimulating the heart, increasing blood-pressure, and diminishing secretion.

- Acids.
- Ammonium salts: chloride; carbonate; hydrate (Ammonia).
- Nux vomica.
  - Strychnine.
- Senega.
  - Saponine.
- Squill.
- Balsams: Benzoin; Benzoic acid; Balsam of Tolu; Balsam of Peru.
- Terebinthinates: Wood tar; Terebene; Turpentine; Oleum Pini Sylvestris; Oleum Pini Pumilionis.
- Sulphur.
- Sulphur oils: Onion; Garlic.
- Saccharine substances: Syrups; Liquorice.

Adjuncts.—One of the most powerful adjuncts to expectorants
s an **emetic**, which frequently will clear the lungs and save life
n cases of chronic bronchitis with impending suffocation, when
ordinary expectorants have completely failed.

One of the emetics most commonly employed in such cases is
pecacuanha, either alone or combined with squill, e.g. half a fluid
ounce each of ipecacuanha wine and oxymel of squills. When
here is great depression, however, and the circulation is very
eeble, carbonate of ammonium is to be preferred.

Another powerful adjunct is **warmth** and **moisture** in the
oom in which the patient is living, and this is best secured by
means of steam brought well into the room from a kettle placed
upon the hob. The kettle used should either be furnished with a
very long spout, as in the case of the ordinary **bronchitis kettle**,
or a long tube made of a piece of stout brown paper tied around
with a string may be used to convey steam into the room from
the nozzle of an ordinary kettle.

Respirators are also serviceable, by preventing the entrance of cold air into the trachea. Many persons, forgetting that the mouth is part of the digestive tract, and that the nose is the proper entrance to the respiratory tract, breathe through their mouth; the consequence is, that the cold air passes down the trachea without being previously warmed. In the nose we have a special arrangement for warming the air. The turbinated bones present an enormous warming surface, like some recently-invented stoves, and moreover, a special arrangement is made for allowing a free flow of blood through this mucous membrane by its being loosely instead of firmly attached to the turbinated bones. Its vessels are therefore capable of great and rapid distension, so as to allow the air to be readily warmed in cold weather.

Most respirators are made simply to go over the mouth, and their advantage is that they force people to breathe through their nose, or warm the air if they cannot do so, and continue to breathe through the mouth. In many persons the same end may be gained by forcing them to wear an invisible respirator. An instrument is sold bearing this name, consisting of a thin plate of metal; but what is perhaps quite as good, or better, is a sovereign or half-sovereign placed between the lips and teeth. Patients are thus forced to keep the mouth shut in order to prevent it from falling out, and its value makes them careful about losing it.

It is often forgotten too that passages and disused rooms are nearly as cold as the external air, and many delicate people who would never dream of going outside in cold weather will, without thinking, walk through cold passages and in rooms without fires. **Warm clothing**, especially over the shoulders, neck, and chest, is very useful, and its utility is recognised by the common employment of so-called chest protectors made of chamois leather and red flannel.

Other adjuncts are **friction** to the chest with stimulating **liniments**; mustard leaves, warm **poultices** and the application of **plasters**; the emplastrum calefaciens (B.P.) or emplastrum picis cum cantharide (U.S.P.) is especially useful in chronic bronchitis.

Arrest of Colds.—Catarrhal affections of the respiratory passages may be excited by irritants of various kinds, and it is probable that these irritants are frequently living organisms. The form of coryza usually called hay-fever is probably due to irritation of the nasal mucous membrane by pollen-grains commencing to grow on it and sending pollen-tubes into its substance.

Other forms of respiratory catarrh, e.g. measles and influenza, are probably associated with specific microbes.

When the respiratory mucous membrane is perfectly healthy it is probable that the invading organisms are quickly expelled or destroyed (p. 85) so that no injury results. But when the resisting power of the mucous membrane is weak, either on account of general constitutional tendencies, or from local and

emporary condition of congestion due to a chill (p. 252), the microbes may begin to grow and cause great irritation.

Among the remedies useful in arresting colds we may recognise **antiseptics**, which destroy microbes, and also **sedatives**, which remove congestion.

Hay-fever has been treated by Binz with a watery solution of quinine in order to stop the growth of organisms in the nose. In some cases this treatment is successful. There is a form of cold sometimes known as influenza-cold. Like true influenza it is extremely infectious and is easily communicated, not only by one member of a family to another, but even by casual visitors. It sometimes begins as a cold in the head, passes down the throat to the trachea and bronchi, leading to severe bronchitis with much depression and occasionally also to gastro-intestinal catarrh. Sometimes it begins in the throat and spreads upwards into the nostrils and downwards into the air-passages. It may frequently be arrested or rendered less severe by the use of dilute carbolic acid applied to the nostrils in the form of spray or by a syringe or nasal douche when the cold begins in the head. When the cold begins in the throat it may be arrested by the use of a carbolic acid gargle, and such a gargle is also useful when the cold begins in the head and is spreading down the throat.

Inhalations of carbolic acid and ammonia appear to be frequently useful in arresting colds. It seems probable that their effect may be due partly to an antiseptic action and partly to their lessening congestion. Carbolic acid inhalations appear to be useful in whooping-cough, probably from an antiseptic action.

Camphor inhaled and also taken internally is useful in arresting colds, though it may be rather hard to give an explanation of its *modus operandi*.

The sedatives which remove congestion of the nasal mucous membrane may be either general or local. Amongst the local may be mentioned bismuth, bismuth and morphine, and cocaine; and amongst the general, preparations of opium, especially Dover's powder, and aconite.

Selection of Remedies in the Treatment of Cough.

Cough, as I have already said, is a reflex act which is performed by means of a reflex mechanism, and is adopted for the purpose of expelling foreign bodies from the air-passages. It is evident that, when the source of irritation may be removed by efforts at coughing, these efforts are useful, and require to be sustained rather than prevented; but if the irritant cannot be removed, the effort of coughing is injurious rather than beneficial, and the same is the case when the amount of effort is disproportionately great to the good that it effects. In these cases we must try to lessen the cough.

The **source of irritation** in the respiratory passages may either be **free** in the lumen of the bronchial tubes, or may be situated in the **mucous membrane** lining the bronchi, or in the substance of the **lung** itself. Thus we may have foreign substances, such as dust, which have been inhaled, or mucus secreted from the bronchi, resting on the surface of the mucous membrane, and leading to irritation. Such foreign matter may be expelled by coughing, and so may purulent matter lying in a cavity, and the cough may be useful by expelling them.

But if the irritation be simply due to a congested condition of the bronchial mucous membrane; to congestion or consolidation of the lung-tissue itself; to a caseous or calcareous nodule which is firmly embedded in the lung; or to inflammation of the pleura it is evident that the efforts at coughing will not remove the irritant, but will rather tend to produce exhaustion; and consequently we must either try to remove the source of irritation by other means, or to lessen the irritability of the nervous mechanism by which coughing is produced. Where the cough is due to irritation caused by indigestion we may give alkalies to relieve acidity, but we sometimes find that a blue pill and a black draught are amongst the most efficient remedies for coughs of this character, by the permanently beneficial action they exert on the digestion. When there is irritation of the pharynx, as well as of the trachea, mucilaginous substances, such as jujubes or linseed tea, are exceedingly useful.

Where cough depends on congestion of the mucous membrane of the trachea or bronchi, we not unfrequently find that the inhalation of cold air, by causing contraction of the vessels, and lessening the congestion, will arrest the cough, so that patients are able to walk out on a cold frosty morning for a length of time without coughing. On coming into a warm room the vessels of the respiratory mucous membrane again dilate: the mucous membrane becomes congested, and the congestion leads to violent and prolonged efforts at coughing. In such cases counter-irritation over the neck, upper part of the chest, and between the shoulders is useful, probably by causing contraction of the vessels (p. 252), and thus lessening congestion. But congestion, not only of the trachea and bronchi, but also of the smaller bronchial tubes, may be relieved, not only by counter-irritation, but by inducing secretion. Congestion of the smaller bronchi indicated by loud whistling *râles* all over the chest, is often accompanied by great shortness of breath. The inhalation of hot aqueous vapour tends to relieve the congestion by inducing secretion, but more powerful agents still are antimony, ipecacuanha, and apomorphine. In such a condition as the one just mentioned, where secretion is absent and congestion is great, one or other of these drugs should be given frequently until secretion occurs freely, as indicated by abundant moist *râles* in the chest.

Along with these depressant expectorants, some preparation of opium should be given, in order to lessen the cough, which at this stage is of no advantage. It is advisable not to stop the administration of these expectorants immediately on the occurrence of secretion, but to continue them for some time longer, and gradually to lessen their amount. When secretion has become copious, either from the administration of depressant expectorants or from the natural course of the disease, we have resort to such drugs as will tend to cause its expulsion, and also to lessen its formation. Amongst those which tend to lessen its formation are balsams and terebinthinates (p. 255), and those which tend to assist expulsion have already been mentioned (p. 254). Along with these we generally combine some preparation of opium if the cough is disproportionately severe, and in chronic bronchitis cod-liver oil (p. 254) is perhaps the most efficient of all remedies.

Action of Drugs on the Bronchi.—The bronchi contain muscular fibres in their walls, which appear to maintain a state of tonic contraction similar to that of the arteries. The motor fibres which supply these muscles are contained in the vagi. When one vagus is cut the bronchi of the corresponding lung expand, and when the peripheral end of the cut vagus is stimulated, the bronchi contract so much as sometimes almost to close completely; but the vagi appear to contain bronchial-dilating fibres, as well as bronchial-constricting, so that irritation of the peripheral end of a cut vagus may sometimes cause marked dilatation instead of contraction, and sometimes primary contraction followed by dilatation. The vagi also contain afferent fibres, passing from the bronchi to the nerve-centres, and these afferent fibres have also a twofold action, so that when the central end of one cut vagus is irritated, the irritation may cause either reflex contraction or reflex dilatation of the bronchi in the other lung. It is probable that there are two cerebro-spinal centres: one producing dilatation and the other contraction. Atropine completely paralyses either the constricting fibres of the vagus or their terminations in the bronchi, so that after a very small dose stimulation of the peripheral end of the cut vagus no longer causes contraction. Ether probably paralyses the cerebro-spinal centre for contraction, so that irritation of the central ends of a divided vagus causes expansion instead of contraction in the bronchi of the other lung. Small doses of nicotine have a powerful effect in expanding the bronchi, but the mode of action of the drug has not been determined.[1]

Pathology of Bronchial Asthma.—The attacks of dyspnœa which occur in spasmodic asthma in all probability depend upon spasmodic contraction of the unstriped muscular fibres in the

[1] Roy and Graham Brown, *Journ of Phys.* vol. vi.

bronchi. In some cases no definite cause can be assigned for the occurrence of these attacks, though a gouty tendency in the patient, or the imperfect elimination of waste products, as in renal diseases, increases the tendency to their occurrence. In other cases they appear to be occasioned by irritation, either in the mucous membrane of the respiratory tract or irritation of some other part of the body. Thus they appear sometimes to be brought on reflexly, by irritation of the nose by polypi, by certain odours, or the inhalation of irritating dust, especially pollen of grass, or by congestion of the mucous membrane in ordinary coryza. Sometimes irritation of the pharynx by enlarged tonsils appears to bring them on, and they frequently arise from bronchial catarrh. At other times they may occur in consequence of indigestion, constipation, of worms in the intestine, of disease of the uterus or ovaries, or of pregnancy.

Treatment of Asthma.—In cases where the cause of the attacks can be ascertained, the cause is to be removed. Thus in gouty patients the free use of water as a beverage, and the administration of iodide and bromide of potassium or of salicylate of sodium may be useful. In renal asthma the diet must be chiefly farinaceous and fatty, meat and beef-tea being sparingly given so as to avoid the accumulation of waste products in the system and caffeine (pp. 433, 434) may be given to aid their elimination. The asthma of dyspepsia, and also that of constipation, may possibly be due partly to the presence of abnormal digestive products in the blood, as well as to irritation of the mucous membrane of the stomach or intestine. In dyspeptic asthma pepsin has proved very useful; emetics are sometimes of service, probably by removing irritating substances (p. 255), and ipecacuanha may possibly have some special action of its own on the mucous membrane, in addition to its emetic action. Constipation is to be treated by laxatives (p. 388) and cholagogues (p. 404), and worms by vermifuges (p. 408). Polypi in the nose and enlarged tonsils are to be removed, and for congestion of the mucous membrane of the nose or throat, carbolic acid lotion may be used (p. 257).

The medicine most usually employed to prevent recurrence of the attack is lobelia inflata. The exact mode of action of the drug is not known, but the general symptoms produced by it closely resemble those of tobacco that it is often known as Indian tobacco, and possibly its action on the bronchial tubes may be somewhat the same as those of nicotine. During the attacks of spasmodic asthma more relief is usually afforded by the inhalation of smoke of various kinds than by any other means. The smoke of tobacco, of the leaves of various species of datura, of paper impregnated with potassium nitrate, or with a mixture of potassium nitrate and chlorate; of pastiles and of various powders which probably are principally composed of powdered datura

leaves, mixed with powdered nitre, and perhaps, also, with ipecacuanha, all prove useful. The action of all these smokes is probably the same as that of nicotine, for Vohl and Eulenberg[1] have shown that the active principles in tobacco-smoke really are not nicotine, but are the products of the dry distillation of tobacco-leaves, consisting chiefly of pyridine, collidine, and allied substances. The same products, but in different proportions, are obtained by the dry distillation of other organic bodies. The proportion in which the different bases are present depends both on the nature of the substances subjected to dry distillation, and on the amount of oxygen present during the process. When much oxygen is present, bodies of higher atomic weight and less volatile than those lower in the series are formed, much collidine being produced when tobacco is smoked as a cigar, while pyridine is the chief product when it is smoked in a pipe. It is probable that the admixture of nitre with paper or with powdered leaves acts beneficially by producing a different mixture of organic bases than would be produced by burning the paper or the leaves alone, and that we must look to bodies allied to collidine for the relief of asthma.

---

[1] *Arch. Pharm.* (2), 1873, vol. cxlvii. 130–166.

CHAPTER XI.

ACTION OF DRUGS ON THE CIRCULATION.

It has already been mentioned that the cells of which higher organisms are composed live in the intercellular fluid or lymph which bathes them.

This nutritive fluid is continually being renewed by fresh supplies exuding from the blood-vessels into the lymph-spaces which surround the cells, the excess being removed by absorption either by the veins or by the lymphatics. Besides this, an interchange of gases (internal respiration) and of solids takes place by diffusion between the lymph and the blood.

When the circulation stops, internal respiration is arrested, and the cells die. But they do not all die at the same time, for some are able to live longer without fresh supplies of oxygen than others. The order in which they die is (1) the cells of the initiative nerve-centres, as the brain; (2) those of the automatic and reflex centres; (3) nerve-fibres (which are modified nerve-cells); (4) unstriated muscles; (5) striated muscles.

Arteries and Veins.—It is important in this respect to remember that it is only so long as blood is in the arteries that it is available for the nutrition of cells. Once in the veins it is useless for nutrition; and were it not that it readily passes from the veins into the arteries again, it might as well be outside the body for any purposes of nutrition.

The veins are very capacious, and when dilated to their utmost, they can alone hold all the blood the body contains, and more. During life they are constantly kept more or less in a state of contraction by the action of the nervous system, but when they become completely dilated, as after death, all the blood flows into them, leaving the arteries empty. It is therefore possible, as Ludwig has well expressed it, to bleed an animal into its own veins. Schiff has shown that when the blood-vessels relax as they do after section of the medulla oblongata, the whole of the blood of another animal as large as the one experimented upon must be introduced in addition to its own, in order to raise the pressure within the vessels to the normal. Even this is insufficient to keep up the pressure, for the vessels go on still dilating, and the pressure falls, notwithstanding the large quan-

ity of blood which is present in them. It is therefore evident hat the normal action of the **vaso-motor centres** is more than equivalent, for the purposes of circulation, to as much blood gain as the animal possesses. Weakened power of these centres s to a certain extent equivalent to bleeding, and increased power has a similar effect to an increase in the quantity of blood in the essels.

Blood-pressure.—The continuity of the circulation of blood hrough the capillaries is not maintained by the heart alone: he elastic pressure of the arteries on the blood within them plays a most important part, and indeed during the cardiac diastole the circulation is maintained entirely by this elastic pressure.

If the arterioles or capillaries through which the arterial system empties itself into the veins are much contracted, so that the blood can flow only slowly through them, the heart may stop, and yet the blood-pressure may remain for many seconds almost unchanged. But if the arterioles or capillaries are dilated, the arteries quickly empty themselves into the veins, arterial pressure rapidly falls, and circulation soon stops.




FIG. 83.—Diagram to illustrate the effects of the horizontal and vertical position on the circulation of the frog in shock. *a*, normal circulation in the upright position. *b*, circulation after dilatation of the veins has been produced by a blow on the intestines. The blood does not reach the heart, and it beats empty, so that the circulation stops. *c* shows the circulation in a horizontal position after the veins have been dilated, as in *b*. The veins are still dilated, but the blood reaches the heart, and the circulation is carried on. Fig. *c* is perhaps too diagrammatic, as it appears to show an empty space or air in the veins. In reality the veins, being very thin-walled, collapse. Fig. *b* is open to the same objection, but if we suppose ourselves to be looking at the vein from the front instead of in section, *b* represents almost exactly what I have myself seen in repeating Goltz's experiment.

I use the words arterioles and capillaries as synonymous, because it is almost certain that the capillaries do contract. In most cases where contraction has occurred in the peripheral vessels, it is difficult or impossible to say whether its seat is in the capillaries or arterioles.

The action of the heart is to pump the blood out of the veins into the arteries, and this it can only do when the blood reaches it. If the veins are much dilated and the animal is in an upright position, no blood may reach the heart, or so little blood that its pulsations are practically useless. This is seen in the frog when dilatation of the large veins has been reflexly produced by striking the intestines (Fig. 83*b*). When the animal is laid flat, the blood flows into the heart, and then it works normally. It is probable that a similar condition occurs in man, as one of the factors in shock; and in this condition, as well as in fainting, or failure of the heart's action from the effect of drugs,

as chloroform, or other causes, the person should be laid flat, with the limbs raised so that the blood may flow out of them into the heart, and with the head low (either perfectly level with the body or depressed below it), in order to permit of an increased supply of blood to the intra-cranial nerve-centres.

Fainting and Shock.—In **fainting** there is sudden unconsciousness, which appears to be caused by sudden arrest of the supply of blood to the brain. This arrest may be due to a rapid fall in blood-pressure, either from stoppage of the heart, rapid dilatation of the arterioles, or sudden removal of pressure from the larger vessels. It is possible that these conditions may be associated with spasmodic contraction not only of the vessels of the face and surface generally, but of those supplying the brain itself. The effect of sudden change from a horizontal to an upright posture in producing syncope has already been mentioned (p. 205). Sudden removal of external pressure from the great vessels acts upon both arteries and veins. It removes external support from the arteries, and allows them to yield more readily to the influence of the blood-pressure, and by their dilatation to lessen it. It allows the large veins also to dilate, and blood to stagnate in them. Its influence is readily seen when fluid is removed too suddenly from the abdomen, and external pressure by a bandage not supplied in its place, as in cases of ascites.

It is seen, perhaps, even more strikingly, where the bladder has been allowed to become distended and is suddenly emptied. The effect of this is shown in Fig. 84. In *a* the bladder is repre-




FIG. 84.—Diagram to show the effects on the cerebral circulation of rapidly emptying the bladder.

sented as full, and, the pressure within the abdomen being considerable, the veins are prevented from dilating, the heart is well supplied with blood, and the circulation in the brain is active. In *b*, the bladder is represented as empty, and the abdominal contents being diminished, so that the intra-abdominal pressure is lessened, not only do the aorta and other vessels become lax from loss of the external pressure, but the veins dilate, the heart

is imperfectly supplied with blood, the cerebral circulation fails, and syncope ensues. This occurs more readily just after waking, before the vaso-motor centre has recovered its usual tone, so that one of the most favourable conditions for its occurrence is when a man jumps suddenly into the upright position and empties his bladder immediately on waking. The consequence of this sometimes is that he falls down suddenly, quite insensible, during the act of micturition. I have seen one case in which the tendency appeared to be increased by the practice of opium-eating, probably from the diminished excitability of the vaso-motor centre produced by the drug. It is evident that the danger will be increased if the intervals between the systoles of the heart are prolonged, and it is the combination of the natural tendency to syncope, produced by large doses of digitalis, with that caused by the sudden assumption of the upright posture, and by the rapid emptying of the bladder, which renders micturition in the upright posture so excessively dangerous in persons under the action of digitalis, and leads so frequently to death.

It is evident that **fainting** may be **prevented** by increasing the blood-pressure in the brain locally, or throughout the body generally. To increase it locally the head of a fainting person should be allowed to lie level with the body, or a little below it, and on no account raised even by pillows. A fainting fit may indeed often be prevented by sitting with the head hanging between the knees. It may also be prevented or removed by such conditions as raise the general blood-pressure, e.g. a draught of cold water, which causes contraction of the gastric vessels, or a sniff of ammonia or acetic acid, which stimulates the nasal nerves, and causes reflex contraction of the vessels generally. In some parts of India the natives are accustomed to bring persons round from a faint by compressing the nostrils and holding the hand over the mouth, so as completely to stop respiration. The accumulation of carbonic acid in the blood irritates the vaso-motor centre, raises the blood-pressure, and thus probably tends to bring the person round.

In **shock** there is no unconsciousness, but the failure of the circulation is even more profound than in syncope. Its pathology is not perhaps exactly ascertained, but it probably depends to a great extent on a paralytic distension of the great veins, as in Goltz's experiments. I have found that in shock produced in a similar manner in a rabbit the blood-pressure could be raised from two inches up to two and a half by the inhalation of ammonia.

Schema of the Circulation.—In order to understand the action of drugs on the circulation it is absolutely necessary to have a clear idea regarding the effect of the heart and capillaries in maintaining the blood-pressure. This is best obtained by using a schema which can be easily made from a spray-apparatus (Fig. 85). By removing the glass or metal tube from one of these,

and attaching a nozzle with a small stopcock to the india-rubber tube in its stead, we obtain a very good schema of the circulation; and, by imitating on it the changes which occur in the heart and vessels, we may form a much clearer idea of them than we could otherwise do. The india-rubber ball will represent the heart; the elastic bag, surrounded by netting, will represent the elastic aorta and larger arteries; and the stopcock, which regulates the size of the aperture through which the air escapes, will represent the small arteries and capillaries, whose contraction or dilatation regulates the flow of blood from the arteries into the veins. We may judge of the tension in the arteries by the distension of the bag, or still better, we may connect the tube between it and the stopcock with a mercurial manometer, and estimate the tension by the height of the mercurial column which it sustains. If we turn the stopcock so as to present some resistance to the escape of air, and then compress the india-rubber ball, very little air will issue from the




FIG. 85.—Simple schema of the circulation, consisting of a spray-producer, bladder, and mercurial manometer. The elastic ball represents the heart; the elastic bag, covered with netting to prevent too great distension, represents the aorta and arterial system, and the bladder represents the venous system.

stopcock even while we are squeezing the ball; the greater part of it goes to distend the bag; and, when we cease to compress the ball, very little air passes through the stopcock. At the next squeeze, the bag becomes a little more distended; and a little more air passes through the stopcock, not only while we are compressing the ball, but even when we relax our grasp. At each squeeze of the ball, the elastic bag becomes tighter, till it is so tense, and contracts so strongly on the air inside, that it can press all the extra amount of air, forced into it when the ball was compressed, through the stopcock during the time when the ball is relaxed. When this is the case, every time we squeeze the ball we see the bag become a little fuller, and air issue more quickly from the nozzle. At each relaxation, while the ball is refilling, the bag gets a little slacker, and the air passes out of the nozzle a little more slowly, but never stops entirely. During the time the ball is filling, the valves between it and the bag and nozzle are closed, and cut it off from any connection with them. All this time, then, the stream of air from the nozzle must be entirely independent of the ball; it is produced by the contraction of the elastic bag, and by it alone. The bag may be stretched, and the tension of its walls increased in consequence, in two ways: first, by working the ball more quickly or compressing it more completely; second, by lessening the opening of the nozzle, and thus hindering the passage of air through it. One trial will, I think, be enough to show how much easier it is to alter the pressure by changing the size of the nozzle than by any alteration in the working of the ball, and to prove that alterations in blood-pressure

probably depend much more on alterations in the lumen of the small arteries than on changes in the action of the heart.

But our schema, as it at present exists, is not a perfect representation of the heart and vessels; for it draws its air from an inexhaustible reservoir, the atmosphere, and is not obliged each time to use that amount alone which it had previously driven through the nozzle; while the heart can only use the blood which has been forced by it through the capillaries and returned to it by the veins. In order to make our schema complete, we must connect its two ends by tying them into a bladder or large thin caoutchouc bag (such as is used, after inflation, as a toy for children), so that the air shall pass into it from the nozzle and be sucked out of it by the elastic ball. This will represent the veins. If we then repeat the experiment just described, we shall find that, when we begin to work the ball and stretch the elastic bag representing the arteries, the bladder representing the veins becomes empty and collapsed; and just in proportion as we fill the bag do we empty the bladder. If we now stop, the air will gradually escape from the bag to the bladder, till the air in both is of equal tension, as at first.

Circulation in the Living Body.—The phenomena of the circulation in the heart and vessels are very much the same as in the schema. When the heart stands still (as when the vagus is strongly galvanised), the blood flows from the arteries into the veins until the arteries are nearly empty and the pressure within them falls to zero. If the heart now begin to beat, it forces blood into the elastic aorta and arteries at each systole, and distends them, just like the elastic bag of the schema; while at the same time it takes blood from the veins, and they become empty in proportion as the arteries become full. During every diastole of the heart, the distended aorta and other arteries, in virtue of their elasticity, contract on the blood they contain, and keep it flowing on through the capillaries till another systole occurs; the heart, meanwhile, being completely shut off from the aorta by the sigmoid valves (just as the ball of the schema was shut off from the elastic bag). In general, the diastole is longer than the systole; so that for the greater part the circulation through the capillaries is carried on by the elasticity of the arteries, and not directly by the heart. The arteries, which we have supposed to be at first empty, gradually become distended by the heart, just as the elastic bag was by the ball, and exert more and more pressure on the blood in them (so that it would spout higher and higher if one of them were cut), till they are able during the diastole to press the same amount of blood through the capillaries into the veins as had been pumped into them during the systole. The more tensely they are stretched, the greater is the pressure they exert on the blood they contain; and the amount of this is termed the **arterial tension** or **blood-pressure**. These two terms mean the same thing, and we use one or other just as the fancy strikes us. At each systole, the fresh supply of blood pumped in by the heart stretches them more; that is, the arterial tension rises. During each diastole, the blood escapes into the wide and dilatable veins, and the arteries

become less stretched; that is, the arterial tension falls. This alternation of rise and fall constitutes the **pulse.**

Besides the **oscillations** which take place in the blood-pressure at each beat of the **heart,** a rise and fall in the form of a long wave occurs at each **respiration.** The wave begins to rise just after inspiration has begun, reaches its maximum just after the beginning of expiration, and then begins to fall again till a new wave succeeds it. The heart-beats are generally quicker during inspiration, and slower during expiration.

The blood-pressure thus oscillates up and down at each heart-beat and rises and falls with each respiration, and the average between the highest and lowest points is called the mean arterial tension or **mean blood-pressure.**

Besides the oscillations in blood-pressure due to the pulse and to the respiration, there are slowly rising and falling waves to which the name of **Traube's curves** is given. These are due to alternate contraction and relaxation of the arterioles and capillaries. Rhythmical contraction of the arterioles has been observed in almost all parts of the body of rabbits, and probably occurs both in the lower animals and in man.

The blood-pressure is not equal throughout the whole arterial system. It is greater in the large and less in the smaller arteries, in which it becomes diminished by the friction between the blood and the arterial walls. It is also modified by gravity, so that the position of a limb may alter the pressure in its arteries.

Method of ascertaining the Blood-Pressure.


The blood-pressure is usually estimated in animals by connecting a large artery, such as the carotid or femoral, with a bent tube containing mercury by means of a connecting tube, which is filled with a solution of carbonate of sodium to prevent coagulation. The pressure is estimated by the height at which the mercury stands in the outer limb of the tube. The height may either be read off with the eye, or, what is much better, it may be registered on a revolving cylinder by means of a long float which rests upon the surface of the mercury, and bears on its upper end a brush or pen. This method, which is important both in itself and as being the introduction of the graphic method into physiology, we owe to C. Ludwig. The apparatus is known as the **kymograph.**

Tracings may be taken upon paper with a varying speed: it is usual to take them upon paper travelling rapidly, so that quick and small oscillations due to the cardiac beats may not be lost or obscured by fusion. The great disadvantage of this is that it is impossible to use the curves directly: they must be reduced, and this is a work requiring much time and labour. When taken on a slowly revolving cylinder we get the general results of the action of a drug on the blood-pressure shown us at a glance; and its effects on the form and rapidity of the pulse may by a little arrangement be recorded from time to time on another cylinder revolving more rapidly.

This method gives us both the blood-pressure and the oscillations which it undergoes on account of the cardiac pulsations and respiration. If we wish to get the mean blood-pressure unaffected by these oscillations, it

done by simply narrowing at one point the calibre of the tube containing the mercury, either by a stopcock, or by reducing the tube to a capillary bore.

Fallacies of Mercurial Manometers.—The oscillating mercurial column does not give the variations in blood-pressure quite truly, because the oscillations are compounded of these variations and of the oscillations due to the inertia of the mercury itself. In order to obtain the exact form of variation we employ Fick's kymograph (Fig. 86), or Roy's tonometer, in which the apparatus is made very light, and all oscillations due to its own inertia are as far as possible avoided.



IG. 86.—Fick's kymograph. It consists of a flat metal tube, bent into a nearly circular form, filled with alcohol, and connected with the artery by means of a leaden tube, filled with a solution of sodium carbonate. When the pressure increases within it, the tube straightens, and when the pressure diminishes it bends. These changes are magnified and recorded on a cylinder by a light lever. The vibrations of the lever are lessened by a piston, which works in a tube filled with glycerine.

Fallacies from Anæsthetics.—Even if the instrument be free from llacy, we still have difficulty in ascertaining the real action of the drug on ne circulation, inasmuch as the blood-pressure is much affected by move- nents, and by anæsthetics. If the animal is not anæsthetised we may get ntrustworthy results from the straining or movements it may make, and if is anæsthetised, the anæsthetic may greatly alter the power of the heart, or ne sensibility of the nerve-centres either to the direct action of the drug pon them, or to its reflex action through the afferent nerves. In order to et rid of movement, and at the same time to prevent the vascular centres om being much depressed, curare is sometimes used instead of an anæsthetic. erhaps, almost equally good results may be obtained by using ether as the næsthetic, carefully regulating the supply so as to abolish sensation without reatly affecting the medulla. The reasons why this is possible are discussed p. 204. In order to regulate the supply of ether, we use a stopcock, by hich pure ether, or pure air, or an admixture of both in any desired propor- on, can be passed into the lungs (Fig. 73, p. 211).

Other fallacies arise from the mode of injecting the drug, and this has metimes led to false results: thus drugs are not unfrequently injected into e jugular vein, as it is very conveniently situated for the purpose. In this ay, however, they are carried directly to the heart, and act much more rongly upon it, than they would do if absorbed from other parts of the dy. In the case of irritant salts, for example, time is not afforded for their ritant properties becoming lessened by chemical combination with the con- tuents of the blood. If the solution injected contain particles which will

not pass through the pulmonary capillaries, or if it is likely to cause coagulation of the blood, it may plug up the pulmonary vessels and give rise to dyspnœa and convulsions.

Both these objections are avoided when the drug is injected under the skin, or into the peritoneal cavity. Absorption from the skin is slower than from the peritoneum. In some experiments this is a disadvantage: in others however, it is an advantage.

Another fallacy sometimes arises from the solution of carbonate of sodium used to prevent coagulation. In order to prevent the blood from passing too far into the tube connecting the artery with the kymograph, it is usual to introduce the solution of carbonate of sodium into the tube by a syringe (*vide* Fig. 86) or otherwise, under a pressure very little less than the usual blood-pressure of the animal experimented on. If the blood-pressure be lowered much by stoppage of the heart or dilatation of the vessels, the solution of carbonate, or bicarbonate of sodium, runs into the arteries and may cause convulsions and death. Thus stoppage of the heart by irritation of the vagus or by the action of a drug, may sometimes appear to be followed by results which are not really due to it, but only to the conditions under which the experiment has been made.

Alterations in Blood-pressure.

In speaking of blood-pressure, arterial blood-pressure is always meant, unless otherwise stated.

As the blood-pressure depends on the difference between the quantity pumped into the arterial system by the heart at one end, and the quantity flowing out through the arterioles into the veins at the other in a given time, it is evident that—

The **blood-pressure** will remain **constant** when these quantities remain equal to each other.

It will **rise** when—

(*a*) More blood is pumped in by the heart.

(*b*) When less flows out through the arterioles in a given time.

It will **fall**—

(*a*) When less is pumped in by the heart; or,

(*b*) More flows out through the arterioles; or, to look at it another way:—

Heart	more active.	Blood-pressure	rises.
	less ,,	,,	falls.
Arterioles	contract	,,	rises.
	dilate	,,	falls.

The heart may throw more blood into the arteries, either by pulsating more rapidly, or by pulsating more vigorously and more completely, so that at each contraction a larger amount of blood is expelled. But increased activity can only affect the blood-pressure so long as there is a free supply of blood entering the heart. If there exist any obstruction to its entrance the increased cardiac action will have no effect. Hence obstruction of the pulmonary circulation will also lower the blood-pressure.

The causes of alteration in the blood-pressure may be tabulated as follows:—

Blood-Pressure

May be raised—	May be lowered—
1. By the heart beating more quickly.	1. By the heart beating more slowly.
2. By the heart beating more vigorously and more completely, and sending more blood into the aorta at each beat.	2. By the heart beating less vigorously and completely, and sending less blood into the aorta at each beat.
3. By contraction of the arterioles, retaining the blood in the arterial system.	3. By dilatation of the arterioles, allowing the blood to flow more quickly into the veins.
	4. By deficient supply of blood to the left ventricle, as from contraction of the pulmonary vessels, or obstruction to the passage of blood through them, or from stagnation of blood in the large veins, e.g., in shock.

The influences on the pressure exerted by (*a*) the number of beats, and (*b*) by the amount of blood sent out by the heart at each beat, to a certain extent, though by no means completely, counteract each other; for, when the heart is beating quickly, it has not time to fill completely, and so sends out little blood at each beat: but, when beating slowly, it becomes quite full during each diastole, and sends out a larger quantity of blood at each contraction.

It is evident that the amount of blood which the heart can send into the arteries at each beat will depend also upon the completeness with which the ventricle relaxes during diastole. If the relaxation be incomplete very little blood will enter the ventricle, and thus a drug which increases the contractile power of the heart may, by unnecessarily prolonging the systole, lower the blood-pressure as much as a drug which paralyses the heart and prevents the ventricle from expelling its contents.

Relation of Pulse-rate and Arterioles to Blood-pressure.

Although we are unable, from the mere fact that the blood-pressure rises or falls after the administration of a drug, to say whether the result is due to the action of the drug on the heart or on the arterioles, yet we can come to some general conclusion regarding its mode of action by comparing the alterations which

it has produced in the blood-pressure with those which occur in the pulse-rate. For in the normal condition of an animal, when all the nerves are intact, a rise in the blood-pressure renders the pulse slow by increasing the normal tone of the vagus centre in the medulla, and a fall of blood-pressure quickens the pulse by diminishing the tone. This mechanism tends in the normal animal to keep the blood-pressure more or less constant.

We find, therefore, that when alterations in blood-pressure and pulse-rate are depicted graphically, so that a rise in one curve indicates a rise in blood-pressure, and a rise in the other




FIG. 87.—Diagram of a pulse and blood-pressure curve, where the alterations are due at first to the action of a drug on the heart, as in the case of atropine. The unbroken line indicates the blood-pressure, and the dotted line the pulse. After the injection shown by the vertical line the vagus is paralysed, the pulse becomes very rapid, and the blood-pressure rises. At A the vaso-motor centre becomes paralysed, the arterioles dilate, and the pressure falls. From *a* to *b* the action of the heart continues nearly uniform, notwithstanding the fall in blood-pressure, but at *b* the heart begins to become paralysed, and the pulse-rate and blood-pressure both continue to fall steadily till death.

indicates quickening of the pulse, the two curves run in opposite directions if the alteration in blood-pressure is due to the arterioles, but they run parallel when the alteration is due to the heart (Fig. 87). Thus, if the vagi be cut, we find that the pulse-rate rises, and in consequence of this the blood-pressure also rises. Here the alteration in pressure is due to the heart, and the two curves are therefore parallel. If the vagi be irritated the pulse-rate falls, and in consequence of this the blood-pressure also falls. Here again the alteration is due to the heart, and the two curves are parallel.





FIG. 88.—Diagram of pulse and blood-pressure curves, where the alterations are due at first to the action of a drug on the arterioles. The unbroken line indicates the blood-pressure, the dotted line indicates the pulse. The upright line indicates the time of injection of the poison. The is followed by contraction of the arterioles and consequent rise of blood-pressure. This stimulates the vagus roots, and causes slowness of the pulse. At *b* the vagus becomes paralysed the pulse becomes quick, and the pressure rises still higher between A and B. At B the vaso-motor centre becomes paralysed, the arterioles dilate, and the pressure falls, notwithstanding the rapidity of the pulse. At *c* the heart itself begins to be paralysed, its beats become slow and both pulse and pressure fall steadily till death.

If, on the other hand, the arterioles are made to contract the pressure rises, but the increased pressure stimulates the vagus roots in the medulla and the pulse-rate falls, so that the curve

un in opposite directions. If the arterioles dilate the pressure alls, and the vagus tone being lessened the pulse-rate rises; so he curves are again in opposite directions (Fig. 88).

An example of this is seen in the accompanying curve (Fig. 89), hich illustrates the action of erythrophlœum—a substance similar n action to digitalis—on the circulation. After the injection of he drug the vessels contract, and the blood-pressure consequently ises and produces some slowness of the pulse. In a little while he vagus becomes paralysed, the pulse becomes quicker, and



IG. 89.—Curve of the pulse and blood-pressure in a cat after division of the spinal cord at the atlas and injection of erythrophlœum. (From a paper by Brunton and Pye, *Phil. Trans.* vol. 167.)

he pressure rises still further. At a later stage the heart becomes slow, apparently from the action of the drug upon it, and he blood-pressure then falls again. At first then, where the alteration of pressure depends upon the state of the vessels, we have the two curves running in opposite directions, but when he alterations depend upon the condition of the heart we have hem running parallel.[1] It will be noticed that in the latter part of the curve, although the blood-pressure and the pulse sink

[1] Although the rise in blood-pressure which accompanies that of the pulse is partly due to the heart, it is very probable that the contraction of the arterioles which caused the rise at first is not only continuing but increasing.

together, they do not sink quite parallel; the pulse falling ver rapidly and the blood-pressure very slowly. From this fact w may conclude that the arterioles are still contracted, and thi affords an illustration of another way in which we judge of th effect of drugs upon the arterioles. This conclusion would no be warranted by the data contained in Fig. 89 alone. For th slowness with which the blood-pressure falls in this experimen might possibly be due to the heart beating more perfectly, at th same time that it begins to beat more slowly. An examinatio of the original tracings of the blood-pressure shows that this i not the case and that the beats of the heart became feeble at th same time that they became slow.

The mutual regulating power of the pulse and blood-pressur only exists when the vagi are working normally. If they shoul be paralysed, either by section or by the action of a drug, in creased arterial pressure will no longer slow the pulse; it ma even quicken it, and therefore the pulse-rate and blood-pressur may, in such a condition, run parallel even though the increase pressure should be dependent upon alterations in the arterioles.

But if the vagi are not paralysed, and we find on comparin the curves of blood-pressure and pulse-rate that they run paralle a fall in the blood-pressure and slowness of pulse occurrin together, or a rise in pressure and quickness of pulse accom panying each other, we may conclude that the alterations i such a case are due to changes in the action of the heart.

If, however, we find that the curves run in opposite direction the pressure rising and the pulse falling, it is highly probabl that the rise is due to contraction of the arterioles, and that th fall of the pulse is caused by the rise of pressure acting as stimulus to the vagus roots. This is, however, not quite certain as it might be due to the action of the drug upon the vagus, an the proper method of ascertaining this would be that employe by Ludwig, of allowing a quantity of blood to flow out into bladder connected with a blood-vessel, so that the pressur should fall. If the pulse still continued slow in spite of the fa of pressure, it would be evident that the slowness was due to th action of the drug upon the vagus, and not to indirect actio through the blood-pressure. By employing a bladder in th manner the blood can be quickly introduced again into th vessels after the effect of its withdrawal has been ascertained.

We not unfrequently find that, owing to the action of a dru the pulse, which has become slow during the rise of the bloo pressure, suddenly becomes very rapid notwithstanding that th pressure continues high. This is usually due to **paralysis** of th **vagus-ends** in the heart, and, when this occurs, the correctne of the conclusion which we draw from the occurrence may l ascertained by stimulating the vagus in the neck by a farada current, and seeing whether any slowing or stoppage of the hea

curs. Frequently we find that after the pulse has become uick from paralysis of the vagus, the pressure which the quick ulse had raised begins to fall again from paralysis of the terioles. The pulse may continue quick and weak almost till eath and then cease suddenly, or it may become gradually slow s well as weak from paralysis of the heart itself.

Effect of the Arterioles on Pulse-curves.—The influence of he arterioles upon the blood-pressure in a living animal can be a great extent ascertained by the rapidity or slowness of the ll of the blood-pressure during the diastole of the heart. When he heart is beating slowly the diastole may be long enough to how distinctly the curve which the blood-pressure describes dur- g its descent; but if the heart is beating quickly the diastole ay be so short that this curve cannot be exactly obtained. It is hen necessary to prolong the diastole artificially by stimulation the vagi.


The reason why the part which the arterioles play in main- ining the blood-pressure can be ascertained by the way in hich it falls during cardiac diastole, natural or artificial, is that the healthy heart the aortic valves close during the diastole so s to separate the aorta completely from the ventricle.

In considering the blood-pressure during the diastole, we may herefore disregard the heart entirely, and look upon the aorta nd its branches as an elongated elastic bag closed at its cardiac nd, but open at its capillary end. This bag is distended with lood, which in consequence of the elastic pressure exerted upon by the arterial walls tends to flow out into the veins. The ate at which it does this will depend—

1st, on the elastic pressure or arterial tension; and,

2ndly, on the size or degree of contraction of the arterioles or apillaries.

If we connect a manometer with this elongated bag as in ig. 90, and place on the mercurial column a float by which its



G. 90.—Diagram of the circulation. *a*, the heart, completely shut off by the valves during diastole from *b*, the arteries. *c*, the capillaries. *d*, the veins. *e*, mercurial manometer. *f*, a float. *g*, a recording cylinder.

eight can be recorded on a revolving cylinder, it is evident that he pressure-curve will fall more quickly to zero when the capil- aries are dilated, and more slowly when they are contracted.

With capillaries of the same size, the rate of flow will vary

with the arterial pressure. If the pressure be high the curv will fall more rapidly than when it is low, for the greater bloo pressure will drive the blood more rapidly through the ope arterioles. If we find that with a normal pressure the pressur curve falls more slowly than usual during the diastole, we ma conclude that the arterioles are contracted; and if we find th the fall is slower, notwithstanding that the pressure is high than usual, the proof that the arterioles are contracted is much the stronger.

This is what Meyer and I [1] observed in the case of digitali where we found, as in the accompanying figure (Fig. 91), th the fall of the blood-pressure during the cardiac diastole in dog is much slower after than before the injection of digital into the circulation.

In observations of this sort it must always be borne in mi that a great difference exists between the vessels of the intestin




FIG. 91.—Tracing showing the blood-pressure and form of the pulse-wave before and after the jection of digitalis in the dog. The thin line shows the blood-pressure before, and the th one after, the injection. The curve sinks more slowly after the injection, notwithstanding greater pressure in the vessels.

on the one hand, and those of the muscles on the other. T former are readily controlled by the vaso-motor centre, a when this is stimulated they contract greatly. Those of t muscles appear to be but slightly influenced by the vaso-mot centre, so that when it is stimulated they hardly contract at a and indeed the flow of blood through them becomes accelerat on account of the contraction of the vessels elsewhere. Wh the vaso-motor centre is stimulated at the same time that t vagus is irritated, the blood-pressure appears to fall nearly quickly as when the vagus alone is irritated. It seems possib however, that this result may be really due to some extent actual dilatation of the vessels in the muscles, for stimulation the motor nerves of muscle appears to produce a vaso-dilati effect on their blood-vessels (Gaskell and others).

The want of power of the vaso-motor centre over the vess

[1] Brunton and Meyer, *Journal of Anatomy and Physiology*, vol. vii. 1872, p. 1 The experiments described in the paper were performed in 1868.

the muscles is probably of considerable pathological importnce. John Hunter [1] noticed, when he was bleeding a lady from vein in the arm, that the blood, which previously had been ark and venous, became bright scarlet, like arterial blood, when he fainted, and remained so during the continuance of the faint. his seems to indicate that during syncope, although the supercial vessels are empty and contracted, the arterioles of the uscles are dilated like those of an actively secreting salivary and.

If we find, then, that after the injection of a drug the bloodessure remains constantly high, during stoppage of the heart, e may conclude that the vessels of the muscles are contracted s well as those of the intestine. Such a condition occurs after he injection both of digitalin and of erythrophlœum, in which he pressure sometimes remains high for many seconds, or even r a minute or more, after the heart has finally ceased to beat Fig. 89).

Investigation of the Action of Drugs on the Arterioles.

The arterioles become contracted by the action of the involunary muscular fibre contained in their walls; they dilate partly y their own elasticity and partly by the pressure of fluid within hem.

The capillaries also appear to have the power of contraction. Both arterioles and capillaries are induced to contract by the ffect upon them of the nerves which pass to them from vasootor centres. The blood-vessels may also dilate actively from rritation of vaso-inhibitory nerves. The exact mode of action f these nerves is not ascertained; they are generally looked pon as entirely separate from vaso-motor, but it seems not improbable that here also the difference between vaso-motor and aso-inhibitory nerves is a mere question of relation, and some erves produce contraction and dilatation according to the point here they are stimulated. Thus Dastre and Morat have found hat the cervical sympathetic, which produces contraction of the essels in the rabbit's ear when irritated between the ear and the irst thoracic ganglion, causes dilatation instead of constriction hen it is irritated at a point below the ganglion, in which case he stimulus has to pass through the ganglion before it reaches he ear.

In considering the action of drugs on the vessels, we have, herefore, to examine—

1. Their direct effect upon—
   A. The contractile walls of the vessels themselves with their
      a, muscular fibres,
      b, motor ganglia;

[1] John Hunter's works, edited by Palmer, 1837, vol. iii. p. 91.

B. Nerve-fibres
   a, vaso-motor,
   b, vaso-dilating;
C. Nerve-centres
   a, vaso-motor,
   b, vaso-dilating.

2. Their reflex effect on the nerve-centres just mentioned.

There are two **modes of estimating the contraction** of the arterioles: 1st, by direct observation and measurement under the microscope; 2nd, by ascertaining the quantity of blood or other fluid which will pass through them in a given time.

Each of these methods may be used in several ways, according as we wish to ascertain the action of a drug—1st, on the contractile walls of the vessels alone; 2nd, on the walls together with the vascular nerves but without the nerve-centres; and 3rd on the vessels in connection with the nerve-centres.

The method of direct observation of the arterioles may be practised in either frogs or mammals.

The part of the **frog** usually selected is the web, the mesentery, the mylo-hyoid muscle, the tongue, or the lung. The parts usually observed in **mammals** are the wing of the bat and the ear of the rabbit.[1]

In observing the effect of various conditions on the lung, it is necessary to inflate it. This is easily done by means of a small cannula with a bulging end which is tied into the larynx. Over the other end is slipped a small piece of india-rubber tubing, and by clamping this after the lung has been inflated the escape of air is prevented.

An apparatus for this purpose is described by Holmgren. The accompanying engraving (Fig. 92) shows one which I used in 1870 for the purpose of investigating the action of heat and cold upon the lung.[3]

By means of the india-rubber ball I directed upon the lung a stream of air which was previously passed either through hot water or through iced water. The pulmonary capillaries, when treated in this way, contract under the influence of cold by one third of their diameter. McKendrick, Coats, and Newman, in an investigation on the action of anæsthetics on the pulmonary circulation, found that chloroform, ethidene, and ether, all stop the pulmonary circulation, the action of chloroform being greatest and that of ether least.[4]

In observing the **effects** of drugs on the **vessels** alone, it is necessary to destroy the influence of the nerve-centres over them


[1] For observing the vessels of the rabbit's ear one of Brücke's lenses is very convenient. It resembles a telescope in its construction, but has a very short focus.

[2] Ludwig's *Festgabe*.

[3] *British Medical Journal*, Feb. 13, 1875, p. 204.

[4] *Ibid.* Dec. 18, 1880.

his is usually done in a frog by destroying the brain and spinal ord. In the rabbit's ear it is done by dividing as far as possible ll the nerves going to one ear, then injecting the drug into the eneral circulation and comparing its effect upon the two ears.



G. 92.—Apparatus for ascertaining the effect of heat and cold on the vessels of the frog's lungs. A, a piece of cork to which the frog is fastened, is laid on B, the stage of a microscope, and attached by an india-rubber strap, C. D is a small ring of cork covered with a thin circle of glass. E is the inflated frog's lung. F is a tube by which a current of air can be directed on the frog's lung. It is held in position by a piece of wire, G, which can be bent to any position. I is a flask containing ice and water. H, a flask containing hot water. K is a three-way stopcock, by which a current of air may be sent from the spray-producer, L and M, through either I or H at will, and thus cold or hot air may be applied alternately to the lung.

t is evident, however, that such experiments are not free from allacy, because in them the circulation is dependent on the ondition of the heart as well as that of the vessels; and both of hese may be affected by the drug.

A better plan, therefore, is to obviate this fallacy by keeping

up the circulation artificially, either in the body of the frog, or in the ear of the rabbit.

A method of **maintaining artificial circulation** in the rabbit's ear while the calibre of the vessels is being measured was invented by Ludwig, and described by me in the *British Medical Journal*, 1871.

In the frog artificial circulation is kept up by putting a cannula into the aorta, and another into the vena cava or abdominal vein after destruction of the brain and spinal cord. The aortic cannula is connected with two funnels or bottles, such as are used for artificial circulation through the intestine (p. 382). These contain either a saline solution or a mixture of saline solution with defibrinated blood. To one of them the drug is added. The circulation can be rendered quicker or slower at will, by increasing the pressure under which the fluid flows into the aorta. A suitable part of the frog is then put under the microscope, and the vessels measured while unpoisoned blood flows through them. The poisoned blood is then allowed to circulate under exactly the same conditions of pressure and the vessels are measured again. By this method of observation Gaskell ascertained that very dilute alkalies cause great contraction of the vessels, so as sometimes almost entirely to occlude them and arrest any flow of blood through them. Dilute acids counteract this effect and cause the vessels again to dilate.

Cash and I have observed that, in addition to this action, dilute **acids** have a tendency to increase the exudation of fluid from the vessels and produce **œdema** of surrounding tissues.

In many experiments which have been made on the action of drugs on the blood-vessels by direct microscopic measurement of their size, before and after the application of the drug, no account has been taken of the effect which the application of the drug may produce by its local irritating action on the nerves or tissues of the part to which it is applied, and by its reflex action through the nerves, quite independently of any special action which it may have on the vessels. Thus, irritation by the application of alcohol, either alone or as a solvent in tinctures, or by a strong saline solution, has an effect similar to that of simple irritation by pressure or scratching, and usually causes temporary contraction, followed by dilatation of the capillaries. This contraction may be more or less prolonged, according to the strength of the irritant which is applied. Unless these conditions are taken into account, observations on the effect of drugs applied locally to the web, mesentery, or tongue, are very unsatisfactory and generally worthless.

Perhaps a somewhat better result may be obtained by injecting the drug into the lymph-sac of a frog, and then observing the web. But here also we have the same difficulty, because the sensory nerves of the lymph-sac being irritated, reflex stimulation

f the vaso-motor centre and consequent contraction of the vessels ay be induced.

Method of Measurement by Rate of Flow.—Another ethod of ascertaining the effect of drugs on the vessels is to easure the amount which flows out of them in a given time. his method may be employed either in the frog or in the higher nimals. The method of employing it in the frog is to destroy he brain and spinal cord, and tie one cannula into the heart or ortic bulb, and another into the inferior vena cava. The aortic annula is connected with a reservoir containing saline solution, or efibrinated blood, which can be made to pass into the aorta and irculate through the vessels at any desired pressure by simply aising or lowering the reservoir; the fluid flows out through the annula in the vena cava, and the quantity is registered upon a evolving cylinder.

By this method Cash and I have found that potassium hloride, contrary to our expectation, causes great contraction f the vessels; that barium and calcium and strontium do so lso, but to a less extent. The instrument used for this purpose onsists of a light lever, one end of which is depressed each time hat a drop falls upon it. An electric circuit is thus broken, and he fall of each drop is readily recorded by means of an electro-agnetic marker; at the same time the pressure under which the irculation is going on is also recorded by means of a manometer. llowing of the flow indicates of course contraction of the vessels, nd acceleration indicates dilatation of the vessels.

The general results of our experiments with several metallic alts are shown in the accompanying table. Most of the drugs xperimented on cause contraction of the blood-vessels, but we re unable at present to arrange them in the exact order of their trength of action.

ithium causes slight contraction.
otassium (very dilute solutions) causes dilatation.
Ditto (solutions of $\frac{1}{4000}$) causes contraction.
arium causes rapid contraction.
alcium ,, gradual ,,
trontium ,, gradual ,,
agnesium ,, slight ,,
luminium (much diluted) has no effect.
1 per cent. needed to produce any effect.

Iron causes slow contraction.
Copper ,, powerful ,,
Zinc ,, ,, ,,
Tin ,, ,, ,,
Cadmium ,, slight ,,
Nickel ,, ,, ,,
Cobalt ,, ,, ,,
Platinum ,, powerful ,, but none is produced by solutions weaker than $\frac{1}{5000}$.

In experiments made by such methods as that just described e reduce the **problem** of the action of drugs on the blood-vessels o a very **simple form**, although we have still to distinguish hether the drug acts directly on the contractile walls of the lood-vessel or on the nervous elements contained in them. here is at present no means of absolutely separating those two ctors, but it is probable that the nerves die sooner than the

muscular fibres, and that if the experiments are carried on for some time the effect of the drug is chiefly, if not entirely, exerted upon the muscular fibres. This is probably the explanation of the different effects of chloral on the vessels of the kidney observed by Ludwig and Mosso (p. 283).

In experiments on the flow of blood through the vessels of warm-blooded animals, the circulation is kept up in much the same way as in the frog. The blood may be used cold, or may be kept at the temperature of the body. The cannula is usually inserted either into the artery supplying an organ such as the kidney, or supplying a single muscle, or it may be put into the descending aorta, so that the blood passes through the whole of both lower extremities. The flow is measured by the rate at which the blood issues from the corresponding vein.

This method we owe to Ludwig, who, along with his pupil Mosso, made a number of experiments on the circulation through the kidney. The conclusions arrived at were:—that venous blood causes contraction, and oxygenated blood, dilatation of the vessels; but the dilatation which richly oxygenated blood, circulating after venous blood, causes in the vessels is only temporary, and they soon return to their normal calibre. Mosso's experiments have been repeated by Severini, who used the lung instead of the kidneys. He finds that the alternate circulation of oxygenated and of venous blood acts in the manner described by Mosso, but that when oxygenated blood is passed through steadily the vessels contract and the flow through them is diminished; venous blood, on the contrary, when circulated for a length of time causes the vessels to dilate and the flow through them to increase. The action of venous blood upon the arterioles appears indeed to be similar to its action upon other tissues. A small or moderate quantity of carbonic acid acts as a stimulus and causes contraction, but great interference with the natural process of oxidation produces paralysis.

Nicotine, in the proportion of 1 in 10,000, causes contraction of the vessels; but this is also temporary. One per cent., on the contrary, immediately causes dilatation.

Atropine has a very powerful action; but this differs completely according to the dose. One part in 100,000 causes temporary contraction of the vessels, which soon passes off. One in 10,000 causes contraction, which, instead of returning simply to the normal, passes into dilatation, and then returns to the normal. One in 5,000 has a similar action, but instead of the dilatation passing away, and the vessels returning to their normal size, the dilatation persists, and the kidney soon dies.

Chloral causes the vessels to contract and then to dilate; but besides this it has a peculiar action, either increasing rhythmic contraction and dilatation of the vessels, when such movements are already present, or inducing them when they are absent.

nly acts upon the vessels when the blood contains oxygen; and hen the blood is saturated with carbonic acid, it has no action n them at all. Its action is also altered by the condition of the idney. When this organ has been kept for twenty-four hours a cool place, its vessels still retain their irritability; but small oses of chloral, instead of causing contraction followed by dila- tion, only produce contraction, and a much larger dose is equired to produce dilatation. This alteration is due to a hange in the vessels—either in their muscular walls, or more robably in the ends of the vaso-motor nerves—and not to any hange in the blood; for it occurs when serum instead of blood passed through the kidneys. When the kidney is dead, chloral ixed with the blood, instead of increasing the rapidity of the urrent as in the living organ, or leaving it unaltered, as one ould expect, greatly diminishes it. Chloral also alters the effect artificial stimulation of the kidney. Faradaic currents or in- uction-shocks do not seem to affect the normal vessels, but onstant currents cause dilatation, which continues while the urrents are passing and diminishes after they cease. When hloral is added to the circulating blood, however, the vessels ontract during the passage of the current instead of dilating, nd dilate slightly after the current has ceased. When the hloral has acted so far upon the vessels as to dilate them greatly, he constant current causes no alteration while it is passing, but, fter it ceases, dilatation increases still further.

Action of Drugs on Vaso-motor and Vaso-dilating Nerves.

The effect which irritation of the vascular nerves produces the living body is also altered by the action of drugs. This ffect is of two kinds—vaso-motor or vaso-contracting, and vaso- lating. Fibres, having these two different actions on the vessels a part, appear frequently to run together in the same nerve- unk, so that sometimes we get dilatation, at other times con- action of the vessels on irritation of a nerve, and not unfre- uently we get contraction followed by dilatation. Such fibres, owever, are not contained in equal proportions in different erve-trunks. The splanchnics, for example, chiefly contain aso-motor fibres, so that irritation of these nerves causes great ontraction of the vessels in the intestine, and a rise of blood- ressure. The motor nerves of the muscles, on the contrary, ppear to contain chiefly vaso-inhibitory fibres, so that stimulation the nerve causes dilatation of the vessels in the muscle to hich it is distributed. Similarly, irritation of nerves distri- uted to glands usually causes dilatation of the vessels in them. he chorda tympani affords a marked example of this, though he same thing is noticed also in the case of the sweat-glands in he foot on irritation of the sciatic nerve.

Most of these vaso-motor or vaso-inhibitory nerves can be stimulated reflexly by irritation of a sensory nerve, as well as directly by irritants applied to the nerves themselves.

We are not acquainted with many drugs which have the power of paralysing the ends of the vaso-motor nerves in the vessels apart from an action upon the contractile walls of the vessels, or the central nervous system. Arsenic, however, appears to be a drug of this kind, and in acute poisoning by arsenic Böhm has observed that neither irritation of the splanchnic nerves nor of the medulla raises the pressure in the way it usually does. From this effect Böhm concludes that the motor nerves contained in the splanchnics are paralysed, but some other observers have not obtained similar results. Hay has found that potash has a similar action. The method is not free from fallacy, for it is obvious that if the vessels in the intestine should happen to be already contracted either from the effect of a drug upon them or from any other cause, neither stimulation of the splanchnics nor of the medulla can have any further effect upon them or on the blood-pressure through them. For when the vessels of the intestine are contracted the blood pours into the veins from the aortic system, through the arterioles and capillaries of the voluntary muscles, and these are only to a very slight extent under the control of the vaso-motor centre in the medulla. Irritation of it will therefore have little effect on the general blood-pressure when the arterioles of the intestine are already contracted, and irritation of the splanchnics is also prevented from having much effect.

It seems probable that curare and poisons which, like it, not only paralyse the ends of the motor nerves, but also the ends of the vagus in the heart, also paralyse vaso-motor nerves, though larger doses are required for this purpose.

Vaso-dilating fibres appear also to be paralysed by curare, for irritation of the motor nerve of a muscle does not cause dilatation [1] of the vessels in a muscle of an animal deeply poisoned by curare. Stimulation of the spinal cord produces contraction of the vessels of the penis instead of erection in an animal poisoned by curare,[2] and stimulation of the chorda tympani does not cause the same amount of dilatation in a poisoned as in a non-poisoned animal, even when the dose of curare is small.[3] Small doses of curare, however, and even large doses of opium, do not appear to paralyse the vaso-dilating nerves of muscles.

In some experiments which I made on the chorda tympani, I got a different result from the usual one in an animal thoroughly under the influence of opium. The vessels appeared to contract

[1] Gaskell, *Journ. of Physiol.* 1878–9, vol. i. p. 273.
[2] Eckhard, *Beiträge*, vol. vii. p. 67.
[3] V. Frey, Ludwig's *Arbeiten*, 1876, p. 98.

nstead of dilating on irritation of the chorda tympani, so that nstead of the blood gushing out of the vein, it flowed slowly, rop by drop.

Action of other parts on the Blood-pressure.—It has lready been mentioned that the blood-pressure rises during nuscular exertion, as, for example, during the struggles of an nimal. The cause of this has not been definitely ascertained, ut it is probably, to a great extent, due to the flow of blood hrough the muscles being mechanically obstructed by the con- raction of the muscular fibres and to a more rapid action of the eart.

The flow of blood through those organs which consist of in- oluntary muscles, e.g. the intestine, may be also obstructed.

When physostigmine is given to an animal, the blood-pressure s sometimes noticed to rise considerably, and this rise of pres- ure was at first attributed to contraction of the arterioles. According to Von Bezold and Götz, however, this is due, to a reat extent, not to the contraction of the arterioles themselves, ut to mechanical obstruction of the intestinal vessels by the etanic contraction of the muscular walls of the intestine.[1]

Reflex Contraction of Vessels.—Experiments on the out- low of blood from divided vessels, while the nervous system is ntact, are sometimes made on frogs for the purpose of ascer- aining the direct effect of drugs on the arterioles themselves; ut this method is faulty, for the alterations consequent on the njection of the drug may be simply due to its local irritant ction producing reflex contraction.

Such experiments are usually made by snipping off the toe f a frog, then injecting the drug into the lymph-sac and observ- ng how many drops of blood exude in a given time from the toe efore and after the injection.

It is obvious that if no change occur in the heart, and the penings of the divided vessels do not become obstructed by clots r otherwise, these experiments may give some indication re- arding the contraction of the vessels; but the results are not rustworthy unless we can ascertain the condition of the heart. A modification of this experiment enables us to some extent to lo this. The end of a toe on *each* foot having been snipped off, he nerve in *one* leg is divided and then the drug is injected into he lymph-sac. If it be then found that the flow of blood from he foot, whose vaso-motor supply has been destroyed by division f the nerve, continues unchanged or is even increased after the njection of the drug, while that from the other foot is diminished, ve may conclude that the diminution is due to contraction of he vessels caused by the injection of the drug.

But it is incorrect to assume, as has sometimes been done,

[1] *Centralblatt f. d. med. Wiss.*, April 6, 1867, p. 234.

that this contraction is due to any specific action of the drug, either upon the muscular walls of the blood-vessels or upon the vaso-motor centre. There is here a fallacy similar to that already mentioned in respect to direct observation of the size of blood-vessels. Any irritation of a sensory nerve by pinching, scratching, heat, &c., may cause reflex stimulation of the vaso-motor centre and produce contraction of the vessels, and injection of strong saline solutions into the lymph-sac, having a local irritant action, will produce a similar effect.

As an example of this fallacy we may mention certain experiments with bromide of potassium. In such experiments it was found that injections into the lymph-sac were followed by contraction of the vessels of the toes, so that much less blood flowed after the injection. When the sciatic nerve was divided on one side the flow was not lessened but rather increased in the corresponding foot, at the same time that it was much diminished on the other side where the nerve was intact. This result clearly shows that after the injection the vessels in one foot contracted, and that this contraction was due to the effect of the injection on the vaso-motor centre, inasmuch as it did not occur in the foot whose vessels had been withdrawn from the influence of this centre by division of the nerves. From this fact the conclusion has been drawn that bromide of potassium has a special power of contracting blood-vessels generally, and on this conclusion theories of its action upon the nervous system have been based. Such theories, however, rest on a very untrustworthy foundation; for though contraction of the vessels no doubt followed the injection of a strong solution of bromide into the lymph-sac, this contraction was probably not at all due to any specific action of the bromide, but only to the reflex stimulation of the vaso-motor centre caused by its local irritant action at the place of application. If introduced in a dilute solution into the mouth instead of in a concentrated form into the lymph-sac, this local irritant action would be absent and probably no contraction of the blood-vessels would be produced.

Action of Drugs on Reflex Contraction of Vessels.—Irritation of a sensory nerve usually produces reflex stimulation of the vaso-motor centre and consequent contraction of the vessels and rise in the blood-pressure both in the frog and higher animals. The chief vaso-motor centre is situated in the medulla oblongata, but it is probable that there are many subsidiary centres throughout the body. It is probable also that these vary in strength and in the amount of independent action they possess in different animals. When the influence of the chief vaso-motor centre upon the body is destroyed by section of the spinal cord just below the medulla, the vessels dilate and the blood-pressure falls greatly. This is, however, not always the case, for in some dogs I have noticed that after section of the

edulla, the blood-pressure remained so high that I was under he impression that the cord had been imperfectly divided, yet fter death examination of the cord showed that section was mplete.

The vaso-motor centre is paralysed by numerous drugs, pecially in the final stages of their action, so that its ordinary nic action is destroyed and the blood-pressure falls greatly. s action of responding to a reflex stimulation is also abolished, nd irritation of a sensory nerve no longer raises the pressure. he tonic and reflex action of the centre do not always appear be effected *pari passu*,—chloral, for example, appearing to ave a greater power to diminish its reflex action than its tone, that stimulation of a sensory nerve has little or no effect even hen the blood-pressure has not as yet fallen very low. Some-mes, indeed, an opposite effect to the usual one may be pro-uced and the blood-pressure be lowered still further instead of ised by the stimulation. Alcohol also paralyses very markedly th the reflex power and the direct excitability of the vaso-otor centre, so that neither stimulation of a sensory nerve, nor en stimulation of the centre of suffocation, will raise the blood-essure.[1] Both the normal tone and the reflex excitability of e vaso-motor centre are greatly increased by strychnine. The neral blood-pressure greatly rises after the injection of this ug, and the effect of irritation of a sensory nerve upon it is creased. It has already been mentioned that in ordinary rcumstances the subsidiary vaso-motor centres in the cord hen separated from the medulla cannot of themselves maintain e blood-pressure. After the injection of strychnine, however, eir action is so much increased that they may keep the blood-essure at a high average and may also cause it to rise on ritation of a sensory nerve.

Comparative Effect of the Heart and Vessels on Blood-ressure in different Animals.—The influence of these two ctors—the heart and the vessels—on the blood-pressure varies different animals, and under different conditions; and a mber of the discrepancies observed by various investigators e probably due to this circumstance. Thus, in dogs the effect of e heart is very considerable, and when its beats are quickened division of the vagi the pressure rises; in rabbits, on the other nd, the heart, instead of working well under its power as in the g, beats very rapidly in the normal condition, and when the gi are divided the pressure does not rise much, although when ey are stimulated the pressure falls both in the dog and in the bbit. This different action of the vagus in the dog and rabbit well seen when these animals are poisoned by atropine. This ug completely destroys the inhibitory action of the vagus on

[1] Dogiel, *Pflüger's Archiv*, 1874, Bd. viii.

the heart; and when the inhibitory power is completely removed we find that only a slight increase in the number of beats takes place in the rabbit, the pulse-rate rising one quarter: for example, perhaps from 100 to 125. In the dog, on the contrary, the pulse-rate will rise to three times, or even four times, what it was before.

In man the effect of the vagus on the heart is intermediate between that of the rabbit and dog: so that if the normal pulse is between 70 and 80 in the minute, it rises to between 140 and 180 when the vagus is paralysed by atropine (Von Bezold).

This difference between the effect of the vagus on the heart alters the effect of drugs on the blood-pressure in different animals.

The difference in the action of drugs on the dog and rabbit is well shown in the case of nitrite of amyl. If this be given by inhalation to a rabbit, the blood-pressure falls immediately and rapidly. If given to a dog the fall may be very slight, at least if a small quantity only is used. On counting the pulse in the dog we discover at once the cause of the apparent difference in the action of the drug on the two animals. Before inhalation the pulse of the dog was slow, but after inhalation its pulse became almost as quick as that of the rabbit. In both animals the nitrite causes dilatation of the vessels, but in the dog the heart begins to beat so much more rapidly than usual that it maintains the blood-pressure nearly at the normal, notwithstanding this dilatation; while the heart of the rabbit beats so quickly, normally, that it cannot maintain the pressure by increased rate of pulsation. If the vagi be cut in the dog, so that the heart beats rapidly like that of the rabbit before inhalation, the nitrite causes as sudden a fall as in the rabbit.[1]

The numerous factors which have to be taken into consideration in regard to the blood-pressure, the action and the interaction of different parts of the body upon one another, render it by no means easy to understand the effect of drugs on the circulation. The differences which we find in the action of drugs on different animals seem at first to make matters still worse; but it is through these differences of action that we learn the exact mode in which the various factors of the circulation are affected by the drug.

There are at least two other factors which must be borne in mind in relation to the difference between rabbits and dogs: these are (1) the much greater sensitiveness of the inhibitory nerves of the heart to reflex stimulation from the nose as well as to stimulation by venous blood, in the rabbit than in the dog; and (2) the proportionately much greater length of the intestinal tube in the rabbit, which causes the vessels of the intestines, or

[1] Lauder Brunton, *Journ. of Anat. and Physiol.*, Nov. 1870, p. 95.

ccount of their number, to exercise a greater action on the lood-pressure in it than in the dog. Thus, in the rabbit, a ightly irritating vapour will cause the animal to close its nos- ils; and almost immediately the vagus will be excited and the eart will stop. This stoppage is probably chiefly due to reflex tion on the heart through the nasal nerves, though it may be rtly due to accumulation of carbonic acid in the blood. When e spinal cord is divided in the rabbit just below the medulla, e pressure sinks enormously: in the dog it also sinks, but t to the same extent; and in some cases it sinks so little at it is almost impossible to believe that the cord has been vided, until examination after death shows that the section s really been completed. This effect may be partially due the less power which the dilatation of the intestinal vessels, nsequent upon the section, has in the dog. It may also, wever, be partly due to greater development of extra-cranial so-motor centres in the spinal cord and elsewhere, than in the bbit.

Influence of Nerves on Blood-pressure.—Both the quick- ss of the heart's beat and the contraction of the arteries are gulated by the **nervous system**; and it is generally by their tion on it that drugs alter the blood-pressure, though it must constantly borne in mind that they may also do so by acting rectly on the **muscular walls** of the heart and arteries them- ves. The parts of the nervous system chiefly concerned in gulating the circulation are:

I. The **motor cardiac ganglia** which lie in the walls of the art, and are under ordinary circumstances the cause of its ythmical action.

II. **Inhibitory nerves,** which render the heart's action slow, d, if irritated very strongly, may stop its beating altogether, d produce quiescence in **diastole.** The inhibitory fibres have ir origin or roots in the medulla, and proceed in the vagi to heart. In probably all the higher animals they are normally more or less constant action. In men and dogs they main- n a well-marked action; and, after they are cut or paralysed, heart beats in the dog three or four times as quickly, and in n twice as quickly, as before. In rabbits and cats they act s, and their division only makes the heart go one-half or one- rth faster. In frogs they are not in constant action, so that ir section does not usually quicken the beats of the heart in se animals.

A drug may **irritate** them, and render the heart's action w—

1. By acting **directly** on (*a*) their roots in the medulla, (*b*) ir ends in the heart;

2. **Indirectly,** through its action on other parts, producing increased blood-pressure, or (*b*) accumulation of carbonic

acid in the blood, both of which act as irritants to the vagus roots;

3. **Reflexly**, through irritation of sensory nerves, e.g. irritation of the intestines; of the sympathetic nerve; of the depressor; or of certain afferent fibres in the vagus. Reflex irritation is only likely to be caused by drugs having a powerful local action.

Drugs may also paralyse the inhibitory, or the ends of inhibitory, nerves in the heart, and thus quicken the heart.

Inhibitory ganglia have been supposed to exist in the heart, and certain drugs, such as muscarine, are supposed to slow its pulsations by their action on these ganglia. They have been supposed to be distinct from the ends of the vagus (p. 313), although generally when the ends of inhibitory nerves in the heart are spoken of, the inhibitory ganglia are included in the term.

III. **Quickening Nerves.**—These belong to the sympathetic system. They have their origin in the brain or medulla, pass down through the cervical part of the spinal cord to the last cervical and first dorsal ganglion (which in many animals are united), and thence through the third branch of the ganglion to the heart. Quickening fibres are said by some to run also in the cervical part of the sympathetic cord. In the frog the accelerating fibres pass from the spinal cord in the anterior root of the third nerve into the ganglion on the trunks of the glossopharyngeal and vagus and thence in the vagus trunk to the heart (Gaskell). Unlike the inhibitory nerves, the quickening nerves are not normally in constant action in mammals.

The accelerating centres may be stimulated—

1. By the **direct** action of drugs upon them.

2. **Indirectly** by the drugs producing a diminution in the blood-pressure. Such a diminution acts as a stimulus to them.




FIG. 93.—Diagram to show the supposed relation of motor ganglia in the heart to accelerating fibres. A, accelerating fibres proceeding from the cerebro-spinal or sympathetic nervous systems to the motor ganglia of the heart. G, motor ganglion. *a*, accelerating fibres passing from the endocardium to the motor ganglion. *m*, motor fibres to the cardiac muscle. H, the cardiac muscle. [For the sake of simplicity in this diagram all hypotheses regarding separate motor and accelerating ganglia have been disregarded.]

It is probable that accelerating fibres also pass to the cardiac ganglia from the endocardium, for irritation of the interior of the heart, either mechanically or by the injection of irritating drugs

into it, causes acceleration. The supposed relationship of the various accelerating fibres to the cardiac ganglia is shown in the accompanying figure (Fig. 93).

IV. **Vaso-motor Nerves**, which cause the smaller arteries, and probably also the capillaries, to contract. These belong to the sympathetic system; and the most important of them are contained in the splanchnics, which when stimulated produce contraction of the intestinal vessels. As these vessels can, under certain circumstances, hold all the blood in the body, the influence of the splanchnics over the blood-pressure is very great; and division of them can lower it, or stimulation of them increase it, very much. The intestine being much longer in herbivora than carnivora, the splanchnics have a greater influence over the blood-pressure in the former. The chief centre of the whole vaso-motor system seems to be in the medulla oblongata; and it is generally in constant action, keeping up a certain amount of contraction or tone in the vessels. There are also, however, subsidiary centres in the spinal cord, and possibly also in the ganglia of the sympathetic system.

The activity of the **vaso-motor centres** may be increased (cf. p. 276), and the vessels made to contract—

1. By **direct** irritation of these centres.

2. By **reflex** irritation through (*a*) the cervical sympathetic, (*b*) the vagus, when the brain is intact, and the animal not narcotised, (*c*) sensory nerves, including the splanchnics themselves. When the medulla is separated from the rest of the body by dividing the spinal cord at the atlas, it can, of course, no longer exert any influence over the vessels; they consequently become dilated throughout the whole body, and the blood-pressure usually sinks very low. If the lower end of the divided cord be then irritated, the vaso-motor nerves which pass through it from the medulla to the body are stimulated, and the blood-pressure rises.

It is probable that the **peripheral ends** of the vaso-motor nerves in the vessels themselves may be either stimulated or paralysed by the action of drugs conveyed to them by the general circulation.

V. **Depressor nerves.**—Irritation of these nerves is conducted to the vaso-motor centres, and acts on them in such a way as to cause a reflex dilatation of the small vessels, either (1) **generally** throughout the whole body, or (2) **locally** in one particular part of it.

1. The chief nerve which causes dilatation, especially affecting the intestinal vessels, is one which runs from the heart to the medulla, and is called, from its power of diminishing blood-pressure, the depressor nerve. Its fibres seem to be included in the vagus in the dog; but in the rabbit it generally runs separate from the heart to the level of the thyroid cartilage; here it

divides into two so-called roots, one root going to the superior laryngeal, and the other to the vagus nerve. These are generally called roots, though, as the nerve conveys impressions from the heart to the brain, they are, physiologically, really branches. There seem to be also depressor fibres in the vagus itself; but the vagus contains fibres of many kinds, and, among others, some which cause reflex contraction of the vessels and rise of blood-pressure—hence called pressor-fibres. The depressor-fibres of the vagus seem to act on the vaso-motor system through the medulla itself, while the pressor-fibres affect it through a centre in the brain, so that, when the brain is perfect, irritation of the central end of the vagus causes increased contraction of the vessels and raised blood-pressure; but, when the brain is removed or its functions abolished by opium, it causes dilatation of vessels and diminished pressure.

2. When a sensory nerve is irritated, the action of the vaso-motor centre is suspended in the part supplied by the nerve, and in those which immediately adjoin it, so that their vessels become dilated, while at the same time contraction of the vessels in other parts of the body is produced. The blood-pressure is thus increased generally, and produces in the locally dilated vessels a very rapid stream of blood. This fact was first discovered, and its therapeutics indicated, by Ludwig and Lovèn.

The causes of alteration in blood-pressure as well as in the pulse-rate, will perhaps be more easily seen from the table on the next page.

Action of the Heart on Blood-pressure.—I have already mentioned that we can to a certain extent ascertain whether a rise or fall in blood-pressure is due to the heart or arterioles, by comparing the pressure-curve with the pulse-curve (p. 271 *et seq.*). If they run parallel the effect may be attributed in great measure to the heart.

But the effect of the heart on the blood-pressure is not so simple as that of the arterioles. In the case of the arterioles we have to consider only the rate at which the blood will flow through them when they are more or less contracted; but in the case of the heart we have to consider not only the rapidity of its pulsations, but the amount of blood which is sent into the arterial system at each beat. We judge of the amount of blood chiefly by the extent to which the blood-pressure oscillates with each pulsation. A large quantity of blood will, as a rule, cause an extensive, and a small quantity only a slight oscillation. When the heart is beating slowly, so that it has time to fill completely during each diastole, the oscillations are large, and when it is beating quickly the oscillations are small.

It is evident that although quick pulsations tend to raise the blood-pressure, they only do so up to a certain point, as beyond that, the heart does not get properly filled, and so sends but little blood into the aorta at each

Causes of Alterations in Blood-pressure and Pulse-rate.

Blood-pressure may be diminished

- **By slow action of the heart**
  - Irritation, or increased excitability of vagus roots
    - Directly, by the action of the drug on them.
    - Indirectly, by increased blood-pressure.
    - „ by accumulation of CO_2 in the blood.
  - Irritation, or increased excitability of vagus ends in the heart — Reflexly, by irritation of some afferent nerve.
  - Paralysis of sympathetic ends in the heart (?)
  - Weakness of the heart
    - Paralysis of the cardiac ganglia.
    - Paralysis of the cardiac muscular fibres.
- **By smallness in the amount of blood sent into the heart at each systole**
  - Imperfect systole of the heart.
  - Imperfect diastole of heart.
  - Contraction of the pulmonary vessels.
  - Great dilatation of the venous system.
- **By dilatation of the small arteries**
  - Paralysis of the vaso-motor centre
    - Directly, by the action of the drug.
    - Reflexly, through the depressor.
    - Reflexly, through vagus and sensory nerves, when brain is removed or animal poisoned by opium.
  - „ „ „ peripheral ends
  - „ „ „ fibres — In operations by division of the cord or of the splanchnics.
  - Paralysis of the muscular coat of the arterial walls.

Blood-pressure may be increased

- **By quick action of the heart**
  - Paralysis of vagus roots.
  - Paralysis of vagus ends in heart.
  - Stimulation of sympathetic roots
    - Directly, by action of drug.
    - Indirectly, by lowered blood-pressure.
  - Stimulation of sympathetic ends in heart (?) — Directly.
  - Stimulation of the cardiac ganglia
    - Reflexly, by stimulation of the sensory nerves of the endocardium.
    - Indirectly, by causing increased temperature of body.
- **By larger amount of blood at each beat** — More perfect diastole and systole.
- **By contraction of the small arteries**
  - Irritation of vaso-motor centre
    - Directly, by action of drug on it.
    - Indirectly, by accumulation of CO_2 in the blood.
    - Reflexly, through the cervical sympathetic.
    - Reflexly, through the vagus, when the brain is present, and the animal is not narcotised.
    - Reflexly, through sensory nerves.
  - „ „ peripheral terminations.
  - Direct irritation of muscular coat of vessels.
  - „ „ „ vaso-motor fibres — In operations by irritation of the peripheral ends of the divided spinal cord or splanchnics.

Stimulation of nerve-fibres of course frequently occurs in experiments from the application of a faradaic current to the trunk of a nerve, but it probably never occurs from the action of drugs introduced into the general circulation.

beat. But the heart may sometimes be imperfectly filled even when it is beating slowly; this has been shown to occur in the case of the frog by Goltz. When a blow or two is struck on the intestines the veins dilate and the blood accumulates in them, so that the heart, which is also stopped at first, receives no blood when it does begin to beat again. It can therefore send none into the aorta, and the circulation remains completely arrested, although the heart is beating.

If the pulmonary capillaries also are contracted the left ventricle will receive little blood, and so will send little blood into the arteries, although the right ventricle may be much distended. This appears to occur during poisoning with muscarine, which causes the lungs to become blanched,[1] the right ventricle distended, and the left ventricle and the arterial system empty: so that little blood flows from a wound.[2]




FIG. 94.—For description *vide* p. 263.

It is difficult, however, to estimate precisely the quantity of blood sent into the arteries at each beat, and its relation to the rapidity of the pulse, so as to ascertain directly how much the rise or fall of blood-pressure is due to the heart; and therefore this is sometimes estimated indirectly by ascertaining first how much of the effect of the drug on the blood-pressure is due to the arterioles, and then attributing to the heart what is not accounted for by their action.

Sometimes also we may get useful information by compressing the abdominal aorta as near the diaphragm as possible before and after injection. We thus diminish so greatly the number of capillary outlets by which the blood may flow from the arteries into the veins that we greatly lessen, though we do not quite destroy, the effect of the arterioles on the blood-pressure. We can thus estimate more precisely the action of the heart upon it.

Section of the spinal cord below the medulla oblongata, by destroying the effect of the vaso-motor centre upon the vessels, also aids us in estimating the action of the heart.

Another method of ascertaining what share in alterations of the circulation locally is due to the heart and arterioles respectively, consists in the combined use of the manometer and Ludwig's stromuhr or Marey's hæmodromometer. The manometer shows the general blood-pressure while the hæmodromometer shows the rate of circulation in the particular artery experimented upon. If the rate of flow increases while the blood-pressure remains constant or sinks, it is evident that the arterioles of the particular vascular district to which the artery is distributed have become dilated. If on the other hand, the rate of circulation diminishes while the pressure remains constant or rises, it is clear that the arterioles have become contracted.

This method is only capable of being applied to large arteries such as the carotid or femoral. By placing the stromuhr in the femoral artery, Dogiel and Kowalewsky found that during suffocation the rapidity of the blood-flow diminished while the pressure rose, showing that the peripheral vessels were contracted.[3]

---

[1] Lauder Brunton, *Brit. Med. Journ.*, Nov. 14, 1874.
[2] Schmiedeberg and Koppe, *Das Muscarin*, p. 57.
[3] *Pflüger's Archiv*, 1870, p. 489.

By the use of the stromuhr, Dogiel[1] has found that the rapidity of the flow of blood in the carotid is first increased and then diminished by alcohol, the greatest diminution occurring during complete narcosis.

Effect of Drugs on the Pulse-rate.—The pulse-rate, i.e. the rapidity of the heart's beats, is chiefly regulated by the inhibitory fibres of the vagus, although it is affected also by accelerating fibres. In the frog the latter, excepting those which pass to the motor ganglia of the heart from the endocardium, also run mainly in the vagus, which is really the vago-sympathetic (Gaskell). In the higher animals they run chiefly through sympathetic channels, though to a slight extent also in the vagus.

If we find that the administration of a drug quickens the pulse, we next try to discover the mode in which it has done so. A glance at the table (p. 293) will show that there are several ways in which acceleration may occur, though the most important is either paralysis of the vagus or, at least, cessation of its action. The usual stimulus to the vagus-roots in the medulla which calls the nerve into action is the pressure of blood within the medulla; when this is high the vagus-roots are stimulated, and the pulse becomes slow; when the pressure is low, the stimulus is removed, and the pulse again becomes quick. Alterations in the blood-pressure will therefore alter the pulse, and drugs which affect the arterioles may quicken or slow the pulse-rate without any marked action of their own on the heart or vagus. This has already been mentioned when speaking of nitrite of amyl, which, by lowering the blood-pressure, and thus lessening the normal stimulus to the vagus-roots, greatly quickens the heart in the dog (p. 288).

In order to ascertain whether irritation of the vagus has been caused reflexly or not, we may divide the nerves through which we may expect the reflex to have occurred, or we may abolish their action on the medulla to a great extent by the use of large doses of chloral.

Action of Drugs on the Cardio-inhibitory Functions of the Vagus.

When speaking in the following pages of the inhibitory action of the vagus on the heart I mean its power to affect the rhythm of the heart so as to render its pulsations slow or stop them entirely, and I do not include under the term inhibition, the power which the vagus also possesses of enfeebling the cardiac contractions, unless when this is expressly stated.

We distinguish between (*a*) stimulation of the vagus-roots by any cause whatever, and (*b*) stimulation of its ends in the heart[2]

[1] *Pflüger's Archiv*, 1874, vol. viii., p. 606.

[2] We use the term vagus-ends here for the sake of convenient distinction between the central cardio-inhibitory systems in the medulla oblongata and the peripheral one in the heart. A fuller explanation of the peripheral cardio-inhibitory apparatus will be given further on.

by dividing both vagi. Sometimes we inject the drug first, and see whether any slowing of the heart which it has produced disappears on section, or we may divide them before injecting the drug, and see whether any change, either in the way of slowing or acceleration, occurs after the injection. If the effect of a drug in slowing the heart is removed by dividing the vagi, we conclude that its action has been exerted on the vagus-roots: if it should still persist after their division, we conclude that it has acted on the vagus-ends in the heart or on the heart itself.

Thus aconitine,[1] veratrine,[2] erythrophlœum,[3] and probably all members of the digitalis [4] group stimulate the vagus-roots, so that the slowing of the pulse they produce is much lessened or completely abolished by section of the vagi, and takes place to a much less extent when the vagi are divided before the injection. That the slowing does not always completely disappear after section of the vagi, or is not always completely prevented by their previous section, is due to the fact that most of these drugs have also an action either on the ends of the vagus in the heart, or on the nervous mechanism or muscular fibre of the heart itself. Nicotine resembles the substances already mentioned in so far that the slowing which it would otherwise produce is somewhat lessened by section of the vagi, but only to a slight extent, its action being chiefly exerted on the peripheral cardio-inhibitory system.[5] Physostigmine chiefly affects the heart itself, and so the slowing of the pulse it causes is not abolished by section of the vagi.[6]

Reflex Stimulation of the Vagus.—The vagus-centre may be also stimulated reflexly, and slowing or stoppage of the heart produced by irritation of sensory nerves. This stimulation occurs most readily through the nasal, dental, or other branches of the fifth nerve, the nucleus of which is closely connected with that of the vagus, or through the sensory branches of the vagus itself, but it may also be induced through almost any sensory, and some sympathetic nerves, if the stimulus be strong.

The vagus-centre in rabbits appears to be very readily stimulated through the nasal nerves, for the application of any strong vapour such as ammonia or chloroform to the nose not only induces closure of the nostrils and stoppage of respiration, but also complete arrest of the heart's pulsations. It appears also to be very sensitive to venous blood. Stoppage of the heart may occur in man from irritation of a sensory nerve, even under

---

[1] Vide *Dissertation on Aconitine under Böhm's direction*, by C. Ewers, Dorpat, 1873.

[2] Von Bezold and Hirt, *Würzburger physiol. Untersuch.* i. p. 103.

[3] Brunton and Pye, *Phil. Trans.*, 1877, p. 627.

[4] Traube and others.

[5] Traube, *Med. Centralztg.* 1862 and 1863, No. 9; *Centralblatt f. d. med. Wiss.* 1863, pp. 111 and 159; Rosenthal, *Centralblatt f. d. med. Wiss.*, 1863, p. 737.

[6] Fraser, *Trans. of Roy. Soc. of Edinburgh*, 1867, reprint, p. 39; for other literature *vide* Harnack, *Arch. f. exp. Path. u. Pharm.*, Bd. v. p. 446.

chloroform anæsthesia, and indeed I believe that in excision of the eyeball the heart usually misses one beat at the moment the nerves are divided.

In dogs, stoppage of the heart and death may occur from irritation of the stomach, even when complete anæsthesia has been produced by chloroform. Some years ago, when making a gastric fistula in a dog, the animal, which was in a state of profound anæsthesia from chloroform, suddenly died when the stomach was laid hold of with forceps. This occurred in a second case just as the cannula was being introduced. On mentioning the subject to Professor Schiff, he informed me that he had had several cases of a similar sort when using chloroform as an anæsthetic, but had none after he began to use ether instead. I found also on using ether that no further death occurred.

Causes of Quickened Pulse.—If, instead of causing a slowness of the pulse, the drug produces **quickening**, it may be due to paralysis of the vagi, to stimulation of the accelerating nerves, or to direct action on the heart itself. We ascertain whether the drug has paralysed the ends of the vagus in the heart by injecting it, and then irritating the vagi in the neck by a faradaic current. If we find that we are no longer able to slow or stop the heart by stimulation of the vagi, we conclude that the drug has paralysed these nerves. This action is well-marked in the case of atropine.

Action of Drugs on Vagus-roots.—We may wish to know, however, what the action of the drug has been on the vagus-roots, and it is evident that if the ends in the heart are paralysed, no action on the vagus-centre could alter the pulsations of the heart any more than nervous stimuli proceeding from the cord could move the legs of an animal poisoned by curare. Nor can we separate the vagus-centre from the heart by ligature of the vessels so readily as one isolates the frog's leg. It can be done no doubt by tying the carotid and vertebral arteries and keeping up an artificial stream of blood through the head. Instead of this, however, the simpler method is generally adopted of injecting the drug to be tested into the carotid artery, so that it will reach the vagus-centre before it gets to the heart, instead of injecting it as usual into the subcutaneous tissue or veins, whence it will be carried to the heart before it can reach the vagus-centre.

By experimenting in this way it is shown that atropine stimulates the vagus-roots so that when injected into the carotid it causes slowing of the heart's action. When it has passed through the cerebral vessels, and returns with the blood to the heart it paralyses the ends of the vagus in the heart, and therefore the pulse again becomes very rapid, notwithstanding the continued stimulation of the vagus-roots.

We cannot always conclude with certainty that a drug has excited the vagus-roots merely because it has caused the pulse to become slower and has had no action after the vagi have been divided, for it is possible that the terminations of the vagus in the heart may be rendered more sensitive than usual by a drug, so that they may respond to a slighter stimulus than usual or with greater energy to a normal stimulus. Such an action appears to be exerted by physostigmine, which in a certain stage of poisoning renders the vagus more excitable, so that when irritated in the neck by a faradaic current a slighter stimulus suffices to stop the heart after the administration of the drug than before.

Action on Accelerating Nerves.—We ascertain whether a drug has a stimulating action on the accelerating nerves of the heart by cutting both vagi and then injecting the drug. If it quickens the heart still further, we assume that it does so by stimulation of the accelerating nerves. This experiment, however, does not enable us to decide whether the stimulation has affected the accelerating nerves passing to the cardiac ganglia from the central nervous system or those passing from the endocardium.

Stimulating Effect of Asphyxial Blood on the Medulla.—In order to prevent fallacies arising from stimulation of the vagus-roots by an asphyxial condition of the blood due to the action of the drug upon respiration, it is usual to maintain artificial respiration through a cannula placed in the trachea. This acts perfectly well in some cases, but if the drug should cause violent convulsive actions it may prevent the movements of the thorax occurring regularly, and therefore it is sometimes necessary to paralyse them by means of curare.

Moreover, it must be remembered that prolonged stoppage of the heart itself will allow the blood in the medulla to become venous and will thus irritate the vagus-roots. Prolonged arrest of the heart, therefore, tends by this action to prolong it still further, and functional inactivity tends to pass into death. This mechanism would render every intermission of the pulse very dangerous were it not that the same venous condition of the blood which stimulates the vagus-roots stimulates also the vaso-motor centre and the respiratory centre. The vaso-motor centre by contracting the arterioles maintains the blood-pressure during the prolonged diastole, and excitation of the respiratory centre tends to restore the arterial character of the blood. The venous condition of the blood also stimulates accelerating centres in the medulla (Dastre and Morat).

Stimulation of the Heart by increased Blood-pressure.—It has already been mentioned that increased blood-pressure usually renders the beats of the heart slower by the stimulating action it exerts on the vagus-roots. When the vagi are divided, however, its effect is usually quite different, and a rise in blood-pressure after division of the vagi renders the pulse quicker instead of slower, at least generally. An opposite result has been found by Marey in the heart of the tortoise, where increased pressure rendered the beats slower. The reason of the difference observed between the mammalian heart and that of the tortoise is probably due to the different development of the nervous and muscular structures. The tortoise heart acts more like a single simple muscle, and the more resistance it has to overcome the more slowly does it work.

In the mammalian heart the increased pressure appears to stimulate the nerves, so that the more resistance it has to overcome the more quickly does it work—that is, if the vagi have been cut. The sensibility of the nervous system in the heart to increased pressure appears to be diminished by atropine, for Schiff[1] has found that a quantity of this poison slightly larger than will dilate the pupil lessens the sensibility of the heart to changes in blood-pressure so much that the pressure may be first increased to three times the normal and then diminished to one-half, or even one-third, without any change in the pulse-rate being produced.

[1] *La Nazione*, 1872, No. 235.

Such an observation suggests that atropine would be useful in lessening pain or palpitation of the heart in persons with high blood-pressure or suffering from the effects of cardiac strain consequent on violent muscular exertion. I have tried it in such cases sometimes with apparently great benefit, at other times with little result. The cases of failure may, however, have been due to the remedy not being pushed far enough, as in them the pupil was not markedly dilated.

Palpitation.—In what I have just said regarding the effect of blood-pressure on the heart I have spoken of the total work, including in it both the rapidity of pulsation and the amount of work done by each beat. This is, perhaps, fair enough; but at the same time we must not forget that there is a distinction between the total amount of work done and the nature of the individual contraction, either in the heart of tortoises or mammals, or in voluntary muscles. Both voluntary muscles and the heart tend to contract rapidly if they have little resistance to overcome. In patients suffering from anæmia and debility, where the blood-pressure is low and the resistance to the ventricular contractions is consequently small, they are apt to take place with great quickness, giving rise to a short flapping first sound and a short but unsustained apex-beat, while the patient complains of much palpitation. In such cases increased blood-pressure will tend to lessen the palpitation, and digitalis, which contracts the vessels, will be useful; iron also is serviceable by increasing the nutrition of the circulatory apparatus of the body generally. The low blood-pressure, however, while it increases the tendency to palpitation, is not the only factor, and is usually accompanied by a tendency to disturbance of the cardiac innervation, which is to be met by sedatives such as the bromides, or by remedies directed to the stomach or other organs from which the disturbing stimulus may proceed.

The Heart of the Frog.

This is a very convenient object on which to study the action of drugs. Their effects upon it are somewhat, though not absolutely, the same as their effects on the mammalian heart; and the frog's heart being simpler in its construction it is easier to analyse the exact mode in which drugs act upon it. The frog's heart consists of three chambers, one ventricle and two auricles. But in addition to these, there is what might almost be called a fourth chamber, the venous sinus or sac into which the venæ cavæ open.

There are three venæ cavæ, two superior and one inferior, which open into the venous sinus.

The venous sinus itself opens into the right auricle, the opening being covered during the auricular systole by a small fold which acts as a valve.

The left auricle receives the pulmonary veins and discharges into the single ventricle the arterial blood which enters it from them, while the right auricle does the same with the venous blood it receives from the sinus.

The septum between the auricles ends inferiorly in two triangular flaps, which act as valves between the auricles and ventricle.

From the ventricle issues the common aorta, or aortic bulb, which has at its origin from the ventricle a spiral valve to prevent the return of the blood. The two auricles beat together, and the aortic bulb and ventricle usually beat together, though the bulb is capable of independent pulsation.




FIG. 95.—Diagram of the frog's heart.

The usual rhythm is the following: first the venous sinus, next the auricles, then the ventricle and bulb.

The pulsations of the venous sinus and ventricle alternate with those of the auricle. The heart continues to pulsate rhythmically after it has been completely removed from the body, so that the motor power of rhythmical contraction is evidently contained within itself. Its rhythm is, however, regulated by the vagi nerves. These pass along behind the two superior cavæ to the junction of the venous sinus with the auricle. At this spot, or




FIG. 96.—View of the auricular septum in the frog (seen from the left side). The nerves are stained with osmic acid. *n* is the posterior, and *n'* the anterior cardiac nerve; *t* is a horizontal portion of thel atter nerve; *b* is the posterior, and *b'* the anterior auriculo-ventricular ganglion; *m* is a projecting muscular fold. [This figure is taken by the kind permission of my friend, M. Ranvier, from his *Leçons d'Anatomie générale*, Année 1877–78, 'Appareils nerveux terminaux,' t. 6, p. 79.]

just over the auricles, between the superior cavæ and the pulmonary veins, they anastomose to form a single or double ganglion, or a plexus containing ganglionic cells, sometimes known as Remak's ganglion. From hence two nerves pass down in the auricular septum, to the base of the ventricle, where they end in two ganglia, known as Bidder's ganglia (Fig. 95). These are situated at the junction of the wall of the ventricle with the two valvular flaps in which the septum ends. They are connected with one another by fibres which run transversely, nearly in a line with the auriculo-ventricular groove.

The posterior or dorsal nerve comes chiefly from the left vagus; and the anterior or ventral from the right vagus.

Both of these nerves grow thicker as they pass down towards Bidder's

ganglia from the presence in them of numerous ganglionic cells; they also send off several branches to the auricle.

The ventricle itself has not been shown to contain either nerve-fibres or ganglionic cells, excepting just at its base, where Bidder's ganglia already mentioned are situated, and where branches from them proceed to the ventricle.

Action of Drugs on the Heart of the Frog.

The effect of drugs may be observed by simply destroying the brain, exposing the heart, and either injecting the drug subcutaneously, or into the dorsal lymph-sac, or even laying it upon the heart itself. Changes in the rate of the pulse and in the mode of contraction of the different cavities of the heart are thus readily observed. By exposure and irritation of the vagi the effect of drugs upon their action can also be observed. Even when completely excised, the heart of the frog continues to pulsate for a length of time, and the action of heat, cold, and poisons upon it can be readily demonstrated. A simple apparatus for this purpose is shown in Fig. 97.




FIG. 97.—Instrument for showing the action of heat and cold and of poisons on the frog's heart. It consists of a piece of tin plate or glass three or four inches long and two or three wide, at one end of which an ordinary cork cut square is fastened with sealing-wax in such a manner that it projects half an inch or more beyond the edge of the plate. This serves as a support to a little wooden lever about three inches long, a quarter of an inch broad, and one-eighth of an inch thick. A pin is passed through a hole in the centre of this lever, and runs into the cork, so that the lever swings freely about upon it as on a pivot. The easiest way of making a hole of the proper size is simply to heat the pin red hot, and then to burn a hole in the lever with it. To prevent the lever from sliding along the pin, a minute piece of cardboard is put at each side of it, and oiled to prevent friction. A long, fine bonnet-straw, or section of one, is then fastened by sealing-wax to one end of the lever, and to the other end of the straw a round piece of white paper, cut to the size of a shilling or half-crown, according to convenience, is also fixed by a drop of sealing-wax. The pin, which acts as a pivot, should be just sufficiently beyond the edge of the plate to allow the lever to move freely, and the lever itself should lie flat upon the plate. Its weight, too, increased as it is by the straw and paper flag, would now be too great for the heart to lift, and so it must be counterpoised. This is readily done by clasping a pair of bulldog forceps on the other end. By altering the position of the forceps the weight of the lever can be regulated with great nicety. If the forceps are drawn back as at *c*, the flag is more than counterbalanced, and does not rest on the heart at all, while the position *a* brings the centre of gravity of the forceps in front of the pivot, and increases the pressure of the lever on the heart. The isolated frog's heart is laid under the lever near the pivot, and as it beats the lever oscillates upwards and downwards. When used for demonstrating the action of poisons the wooden lever should be covered with sealing-wax, so as to allow every particle of the poison to be washed off it, and thus prevent any portion from being left behind and interfering with a future experiment. By attaching a small point to the end of the straw in place of the paper flag, tracings may be taken upon smoked paper fixed on a revolving cylinder.

The fact that heat accelerates and cold retards the pulsations of the heart is one of fundamental importance, both in regard to a right understanding of the quick pulse, which is one of the most prominent symptoms of **fever**, and to a correct knowledge of the proper treatment to apply when the heart's action is failing.

It may be shown with the apparatus just described by placing a piece of ice under the tin plate. The pulsations will become slower and slower, and if the room be not too warm the heart may stand completely still in diastole. On removing the ice from the plate the pulsations of the heart become quicker. If a spirit-lamp

be now held at some distance below it the heart beats quicker and quicker as the heat increases, until at last it stands still in heat-tetanus. On again cooling it by the ice, its pulsations recommence.




FIG. 98.—Ludwig and Coats' frog-heart apparatus. A is a reservoir for serum. B, a stopcock to regulate the supply to the heart. C, a piece of caoutchouc tubing connecting A and D. D, a glass cannula in the vena cava inferior. D', another in the aorta. E, a manometer. F, a piece of tubing closed by a clip, to allow of the escape of serum. G, a fine pen, floating on the mercury in E. H, the frog's heart. J, a sealed glass tube passed through the œsophagus, K, and firmly held by a holder, L. N, a second holder to support A. P, a stand with upright rod. S, a flap of skin to cover the heart and prevent drying. The vagus nerve is seen passing to the heart.

At first they are quick, but they gradually become slower and slower. On again applying the spirit-lamp they become quicker, and by raising the temperature sufficiently the heat-tetanus is converted into heat-rigor. In this condition no application of cold has the slightest effect in restoring pulsation.

Not only the effects of heat and cold, but the effect of separating the venous sinus or the auricles from the ventricle can readily be shown with this apparatus, as well as the action of various poisons. The best for the purpose of class demonstration is muscarine. A drop of saline solution containing a little of the alkaloid being placed on the heart, it ceases to beat entirely. If a drop of atropine solution be now added the beats recommence. I have seen them do so on one occasion after they had entirely ceased for four hours.

For the purpose of observing alterations in the strength of the cardiac pulsations as well as their rhythm, a convenient piece of apparatus is the one devised by Ludwig and used under his directions by Coats (Fig. 98).

One objection to this apparatus as shown in the engraving is, that the blood does not circulate freely through the heart, but this can be overcome by closing the tube at F only partially instead of completely, and according to the amount of closure the pressure under which the heart works may be regulated. Or the tube F may be lengthened and made to empty itself into the reservoir A. The pressure under which the heart works may be regulated by the height at which the tube is allowed to discharge.

Another apparatus is that used by Williams in his researches on digitalin (Fig. 99).[1] It consists of a Y-shaped cannula whose stem is divided by a




FIG. 99.—Diagram of Williams's apparatus for investigating the action of drugs on the heart of the frog.

longitudinal septum into two halves, each of which is continuous with the fork on its own side. The stem is inserted through the aorta into the ventricle of the heart, which is kept moist by being dipped in a vessel containing serum or a dilute saline solution. One fork of the Y is connected with a flask containing blood-serum or other nutritive fluid, and the other with a manometer. By means of valves these fluids are made to flow only in one direction. These valves consist of a piece of glass tubing with a slit on one side; over this slit is loosely tied a piece of thin membrane (gold-beater's skin) which covers about three-quarters of the circumference of the tube. This membrane allows fluid to pass readily out of the tube from within outwards, but not from without inwards, any external pressure causing the membrane to become tightly applied to the slit and to close it.

[1] *Arch. f. exp. Path. u. Pharm.*, Bd. xiii. p. 1.

A very useful form of apparatus for investigating the action of drugs on the frog's heart and on the effect of the vagus upon it is made by combining the valves in Williams's apparatus with the apparatus of Ludwig and Coats.[1]

The **apex** (as the lower two-thirds of the ventricle is commonly called) contains, as has been mentioned, **no nerves**, and when separated from the rest, either by cutting or by tight ligature, usually lies perfectly quiet without contracting. When irritated by a single induced shock, it answers by a single contraction, just like any other muscular fibre.

But though the muscular fibres contained in the apex cease to contract rhythmically, when the nervous stimulus usually supplied by Bidder's ganglia is removed, they still retain a tendency to rhythmical contraction; and when subjected to a constant stimulus of another kind they again commence to pulsate. This is seen when the apex is stimulated by supplying it with oxygenated blood through a cannula under pressure (the pressure supplying the necessary stimulus), or by passing through it a constant or interrupted current, or by adding a trace of delphinine to the nutritive fluid with which it is supplied. This phenomenon is similar to that which occurs in the bells of medusæ already described (p. 110), which cease to contract rhythmically when their marginal ganglia are removed, but recommence when an additional stimulus is applied to the bell itself, by putting it into acidulated water.

A curious point has been made out by Bowditch regarding the excitability of the heart-apex. It has already been mentioned that the amount of contraction of voluntary muscle varies with the intensity of the stimulus, and that this is also the case with the reflex contraction produced by irritation of sensory nerves. The apex when fed with serum usually stands still for a long time before it begins to beat, but when in this condition may be made to contract by the application of an induction shock. The difference between the reaction of an ordinary striated muscle and of the apex to such a shock is, that the heart, instead of responding by a strong or weak contraction to a strong or weak stimulus, either does not contract at all or contracts with as much force as it can exert. The weakest stimulus which will act at all and the strongest have thus exactly the same action, or, in other words, a minimum is also a maximum stimulus. This condition does not correspond to that which obtains in the normal striated muscle when stimulated either directly or reflexly. We find, however, a corresponding condition in the reflex contraction of the muscle produced by stimulation of sensory nerves in an animal poisoned by strychnine (p. 181). We noted, however, in discussing the action of strychnine on the

[1] Harnack and Hoffmann, *Arch. f. exp. Path. u. Pharm.*, Bd. xvii. p. 159.

spinal cord, that, just after exhaustion had occurred from a spasm, strong and weak stimuli produced strong and weak contractions in the muscle. A somewhat similar condition appears to occur in the heart, for Mays has noticed that, when the apex is supplied with blood which has stood three or four days instead of with fresh blood, strong and weak stimuli produce strong and weak contractions.[1]

It is obvious that, although the contractions of voluntary muscle on reflex stimulation may be analogous to the contractions of the apex, yet, in the former case, the alterations occur in the nervous centres, while in the apex the changes occur in the muscular substance.

Action of Drugs on the Muscular Substance of the Heart.

Since the lower two-thirds of the ventricle or **apex**, as it is usually termed, contains no nerves, it forms a convenient object for ascertaining the action of drugs upon the muscular substance of the heart itself, and has been much used for this purpose.




FIG. 100.—Perfusion cannula, with the anterior part removed so as to show the septum.

The apparatus usually employed (Fig. 100) consists of a small cannula introduced into the ventricle, which is attached to it by a ligature tightly tied round it at the junction of its upper third with its lower two-thirds. The interior of the cannula is divided into two by a septum which runs longitudinally, and the one half is connected with a flask containing the nutritive fluid with which it is to be supplied, and the other with a small mercurial manometer provided with a float to register its oscillations upon a revolving cylinder.

At first the nutritive fluid is supplied pure to the apex, and after a normal tracing has been obtained the substance to be investigated is added to it.

When **saline solution**, a ·65 per cent. solution of NaCl, is employed, the apex usually stops in diastole for a period varying from a few minutes to an hour and a half. It then begins to pulsate (Fig. 101, *a*), getting gradually weaker and weaker (Fig. 101, *b* and *c*), and finally stops in diastole. When the heart is in this condition its pulsations may be restored by the addition

[1] *Separat-Abdk. a. d. Verhandl. d. physiol. Gesellsch. zu Berlin*, Jan. 12, 1883.

to the chloride of sodium solution of 1 to 10 per cent. of blood, or of serum, or of a solution of the ashes of serum.

Minute quantities of several poisons such as delphinine or quinine, or a mixture of atropine and muscarine, also restore the




FIG. 101.—After Ringer. Tracings showing the effect of simple NaCl solution in weakening the pulsations of the apex of the frog's heart. The tracing *a* was taken soon after the blood was replaced by NaCl solution; *b*, after a longer period; and *c* after a still longer time.

rhythmical pulsations after they have ceased in a heart-apex supplied with NaCl solution. A minute quantity of Na_2CO_3 or ·005 per cent. of NaHO restores or increases the beats for a time [1] afterwards the pulsations become again weaker and the heart stops a second time, but it stops in systole and not in diastole.

Ringer has made the remarkable discovery that when the saline solution is made with ordinary tap-water the beats become prolonged, but the addition of a trace of potash causes them at once to assume their normal character, and a frog's heart may be kept beating for hours together with saline solution made in this way and containing a trace of potash, although the saline solution never does this when made with distilled water. The



FIG. 102.—After Ringer. Shows the effect produced upon the beat of the frog's heart fed with Na solution by the addition of a trace of calcium chloride. The beats in this case are induced by induction shock.

addition of a minute trace of calcium salt to distilled water pro duces the same effect as tap-water—the contractions become larger and longer (Fig. 102). When potash is then added, the length of the contractions becomes diminished to the normal without their strength becoming affected, and thus a pure saline solution made with distilled water and with the addition of minute traces of calcium and potassium will keep the heart beating perfectly for hours together.

Dilute **alkalies** added to the saline solution have been shown by Gaskell to cause a tonic contraction of the muscular fibre of the apex, so that it may gradually cease to beat. This contraction may occur whether the apex is pulsating or not. If

[1] Gaule, *Archiv f. Anat. u. Phys.*, 1878, p. 295.

remains at rest, a manometer connected with it simply shows a gradual rise in the mercury until the contraction of the apex is complete. If it is beating, the duration of full contraction at each systole becomes longer, and relaxation during diastole less complete, until no diastolic relaxation occurs and the ventricle remains perfectly still in a condition of complete contraction.

Dilute **acids** have an opposite action to dilute alkalies, and when very dilute acid, e.g. lactic acid, is mixed with the saline solution, it produces a condition of complete relaxation.

Instead of increasing the duration of the systole like alkalies, acids first shorten it and then render it less and less powerful, until contractions cease altogether and the ventricle remains at rest in diastole.

Dilute acids and alkalies counteract each other's effects on the heart, so that after the beats have been very much lowered in force by acids, an alkali will first restore it to its original condition, and then produce its own characteristic effect. The subsequent application of an acid will undo the effect of the alkali, again weakening the beats and again producing dilatation instead of contraction.[1]

The three alkalies, potash, soda, and ammonia, have all a somewhat similar tendency to increase the tonic contraction of the ventricle. When large doses are given they tend to paralyse the muscle, so that it again dilates after a period of tonic contraction. The paralysing action of potash is much more powerful, and manifests itself much sooner than that of the other two.

The excitability of the muscular fibre is also altered by alkalies. Soda and ammonia increase it, so that a faradaic stimulus applied to the ventricle has much more effect after the application of soda and ammonia than before. Potash has a different effect and diminishes the excitability of the ventricle, although sometimes the diminution may be preceded by a stage of increased excitability.[2]

A number of poisons act on the muscular fibre of the ventricle like alkalies, others act like acids.

Antiarine, digitalin, helleborin, veratrine, physostigmine, barium, and probably all the substances belonging to the digitalin group, act like alkalies.

Muscarine [3] acts like an acid, and so apparently do also pilocarpine,[4] saponine,[5] and apomorphine.

Neutral double salts of copper, chloral, iodal, and other members of the chloral group,[6] are probably to be classed along

[1] Gaskell, *Journ. of Physiol.*, vol. iii. p. 48.
[2] Ringer, *Ibid.*, vol. iii. p. 193.
[3] Gaskell, *Journ. of Physiol.*, vol. iii. p. 61.
[4] *Ibid., op. cit.*
[5] Schmiedeberg, *Ludwig's Festgabe*, p. 127.
[6] Harnack, *Archiv f. exp. Path. u. Pharm.*, Bd. xvii. p. 185.

with salts of potassium, first exciting and then paralysing the cardiac muscle.

In classifying cardiac poisons, when we say that some act like acids and others like alkalies, it must be borne in mind that the action though similar is not identical. Although the actions may be generally like one another, they may vary very considerably even in kind, and they certainly vary enormously in degree. Thus the action of barium and veratrine may be very similar, but veratrine is much the more powerful. We find a similar condition in other structures. Thus iodide of ammonium and curarine both paralyse the ends of motor nerves, but an enormously larger amount of the former is required to produce the effect.

That there is considerable similarity in kind, however, between the action of the vegetable alkaloids and inorganic salts is shown by the fact that the action of veratrine may be neutralised by potassium chloride.[1]

The irritability of the heart is preserved for very different lengths of time in different **gases**. Thus Castell[2] found that the frog's heart continued to beat in oxygen for 12 hours, in nitrogen for 1 hour, in hydrogen for $1\frac{1}{4}$ hour, in carbonic acid for 10 minutes, in nitrous oxide for 5 or 6 minutes, in carbonic oxide for 40 minutes, and in chlorine for 2 minutes.

Differences between the Heart-Apex and the Heart.

When the heart is tied on to a cannula in the same way as the apex, by a ligature round the auricles or even the sinus, so that, instead of containing no ganglia at all, it contains either Bidder's or Bidder's and Remak's ganglia, it also remains motionless in the same way as the apex when supplied with chloride of sodium solution, but its rhythmical power is restored by the addition of defibrinated blood, of serum, of solution of the ash of serum, by a trace of Na_2CO_3, or still better by the addition of ·005 per cent. of NaHO and a trace of peptone or serum-albumin.




FIG. 103.—Diagram to show the difference in the mode of experimenting with the heart and with the apex alone. In *a* the apex alone is attached to the cannula. In *b* the heart, consisting of ventricle and auricles, or of the venous sinus also, is attached to the cannula.

When supplied with pure serum, it does not beat regularly, but its pulsations occur in groups separated by long intervals (Fig. 104).[3] When a little hæmoglobin or blood is added to the

[1] Ringer, *Practitioner*, vol. xxx. p. 17.
[2] Hermann's *Handb. d. Phys.*, iv. 1, p. 357.
[3] Luciani, *Ludwig's Arbeiten*, 1872, p. 120.

serum, this grouping disappears, and the pulsations become regular.[1]

When the heart has been supplied with hæmoglobin or blood and is beating regularly, the addition of a little veratrine causes




FIG. 104.—Periodic rhythm of the heart, the pulsations occurring in groups separated by intervals of complete quiescence.

the groups to appear, and a similar effect is produced if the blood is not renewed, but allowed to remain in the heart till it becomes venous.[2]

This periodic stage does not occur immediately after the heart has been tied on the cannula and supplied with serum. It is preceded by an initial stage, in which the beats are at first very quick, then slow, and these are separated by long pauses. Next comes the periodic stage in which the groups occur. It is succeeded by the stage of crisis in which the groups are replaced by single pulsations slower and smaller than the normal.

Atropine and nicotine do not prevent the occurrence of groups. Both of them make the groups longer and the pauses shorter. Atropine, however, even in small doses, soon kills the heart before it even enters on the stage of crisis. Nicotine, on the other hand, shortens the pauses, and rapidly induces the stage of crisis without destroying the energy of the heart, which is quite as great after poisoning by nicotine as in the normal condition.

Moderate doses of muscarine make the pulsations smaller and slower, the groups shorter, and the pauses longer. Sometimes the heart becomes exhausted before the stage of crisis appears, at other times it does not. Large doses of muscarine arrest the movements of the heart.

The activity of the heart which has been stopped by muscarine is again restored by atropine, but muscarine can render the beats smaller and slower, even after the previous application of atropine.

The occurrence of groups appears to be most probably due to interference of rhythms—of the ganglionic rhythm with that of muscular fibre.

We find an indication of alternate interference and coincidence of two rhythms in the alterations which sometimes occur in the beats of a ventricle containing its ganglia, but separated from the auricles. At first all the beats are of equal strength, but soon each alternate beat gets longer and shorter, till some disappear and others get much stronger than before (Fig. 105 ; cf. Fig. 64, p. 168).

---

[1] Rossbach, *Ludwig's Arbeiten*, 1874, p. 92.
[2] *Ibid.*, p. 93.

Action of Drugs on the Vagus in the Frog.—When the vagi are stimulated by an induced current, the heart usually stops in diastole.




FIG. 105.—Tracing of the pulsations of a ventricle separated from the auricles by section at the auriculo-ventricular groove. After Ranvier, *Leçons*, 1877–78.

The effect of stimulation may be observed either on the heart simply exposed or by means of Ludwig and Coats' apparatus. The action of both vagi is not always alike. The right vagus has usually a greater power to arrest the heart than the left. The action of the vagus varies also according to the condition of the heart, and may produce different effects. It may cause, 1st, stoppage of the heart's beats, followed after an interval by slow pulsations or by small rapid pulsations, gradually becoming larger and stronger; 2nd, it may cause them to become small and slow without actual stoppage—this is the usual effect of irritation of the vagus in the living body; 3rd, it may cause the pulsations to become simply small and rapid without any stoppage; 4th, it may cause them to become rapid; 5th, it may cause them to become more powerful (Figs. 112 to 115, p. 324).

It may also act differently on the auricles and ventricle, producing still-stand of the ventricle and rapid pulsation of the auricles. These differences are probably due to a great extent to the vagus of the frog being really the combined vagus and sympathetic. At present the chief point upon which I wish to insist is that irritation of the **vagus** usually causes **still-stand** of the heart.

When the **venous sinus** is stimulated, still-stand of the heart is produced, which is even more complete and permanent than that which follows irritation of the vagus.

Action of Drugs on Inhibition of the Heart.—The effect of certain drugs upon the still-stand produced by irritation of the vagus or of the venous sinus is very remarkable. A large number of drugs, more especially atropine, curare, coniïne, and nicotine, when injected into the circulation have the power of completely destroying the inhibitory power of the vagi as far as the rate of rhythm is concerned, so that when their fibres are stimulated the heart is not arrested, nor are its beats rendered slower, but they are, on the contrary, quickened.

These poisons again may be divided into two classes:

Class I. containing atropine and its congeners.

Class II. containing curare, coniïne, nicotine, &c.

These two classes agree in destroying the inhibitory power of the **vagus** nerve, so that irritation of its trunk will no longer produce still-stand or slowing of the heart. They differ in their action on the still-stand produced by irritation of the **venous sinus**. Atropine and its allies prevent any inhibition occurring when the venous sinus is stimulated, or when muscarine is applied to the heart directly. This action affects chiefly the rhythm of the heart, for muscarine can still reduce the force of the cardiac contractions after the application of atropine.

Poisons of the second class do not prevent the still-stand of the heart occurring on irritation of the sinus, nor do they prevent muscarine from arresting the beats of the heart. This antagonism of atropine and muscarine has hitherto been explained on the supposition that muscarine greatly stimulates inhibitory centres in the sinus or auricle, while atropine paralyses them.

These two classes also agree in leaving unaffected the **accelerating** nerves of the heart.[1]

These complicated effects are very hard to explain on the ordinary hypothesis.

It is still more strange that although atropine and muscarine have such apparently opposite effects, they both agree in ultimately paralysing the inhibitory function of the vagus.

Muscarine, as I have already mentioned, arrests the movements of the heart; but, if the circulation be carried on, this arrest is only temporary, and is succeeded by a period, first of slowness, then of irregularity, and then of return to the normal; the stage of irritation of the inhibitory centre by the muscarine gradually passing into that of complete paralysis. During the time when the pulse is still slow in consequence of the action of muscarine, irritation of the vagus itself has no power to arrest it, or even to increase the slowness, while at that very time irritation of the accelerating nerves quickens its pulsations just as it would those of a normal heart.[2] When the accelerating nerves are thus irritated, there is often not only an increase in the number but also in the size of the pulsations, very much as Gaskell has observed under other conditions from irritation of the vagus in the frog. This action is only to be observed in moderate conditions of poisoning. When the poisoning is very profound, irritation of the accelerating nerves has a very peculiar

---

[1] In the frog the accelerating nerves appear to run along with the inhibitory fibres in the vagus trunk. In warm-blooded animals these fibres run in separate nerves which pass out from the spinal cord along the vertebral artery and reach the heart through the sympathetic system. Although the chief accelerating fibres pass in these nerves, some are also contained in the vagus trunk, both in warm-blooded animals and in frogs. In animals poisoned by atropine, irritation of the vagus usually produces acceleration of the pulse.

[2] Weinzweig. From experiments in Von Basch's laboratory. *Archiv f. Anat. u. Phys.*, Phys. Abt., 1882, p. 527.

effect, sometimes producing so-called staircases, and sometimes a prolonged condition of still-stand, half in systole and half in diastole.

A marked **difference** is seen **between** the action of the **accelerating** nerves **and** the **inhibitory fibres** of the vagus, as the inhibitory action follows very shortly after the irritation of the vagus, and usually ceases very shortly after the irritation is removed, whereas that of the accelerating nerves does not occur until some time after the irritation has been applied, and often lasts a good while after the irritation has been removed. The two sets of fibres also appear to influence a different period of the heart's action, the inhibitory affecting the pause or relaxation, while the accelerating affect the systole or contraction. This condition renders it not improbable that we may have to do here with an action of these nerves on two different parts of the heart —the ganglia and the cardiac muscle.

It is quite clear that, in order to get any satisfactory explanation of these phenomena, we must take into consideration not only the rhythmical actions going on in the cardiac ganglia and those in the cardiac muscle separately, but also the relation to one another of these rhythms both as regards their energy and rate.

Theories regarding the Mode of Action of Drugs upon the Heart.

In order to explain the effects of various poisons upon the heart, a hypothetical view of its nervous system has been proposed by Professor Schmiedeberg,[1] and I have endeavoured to represent this in the accompanying diagram (Fig. 106).[2] It consists of a ganglion, M, which keeps up a rhythmical contraction of those muscular fibres of the heart to which it is connected by the fine nervous filaments, E. This ganglion is connected by an intermediate apparatus with an inhibitory ganglion, I, which can retard or stop the muscular contractions which M produces; and by another apparatus, C, with another ganglion, Q, which quickens the contractions. I is connected by an intermediate apparatus, A with the retarding fibres, V, of the vagus, and D with the quickening nerve, S, of the heart.

This schema has been adopted by Professor Harnack.[3]

It has been supposed that **motor ganglia** are present because the apex of the heart of the frog, which contains no ganglia, will

---

[1] Schmiedeberg, *Ludwig's Arbeiten*, 1870, p. 41.

[2] 'Experimental Investigations of the Action of Medicines,' Lauder Brunton, *British Medical Journal*, December 16, 1871.

[3] *Pharmakologische Thatsachen für die Physiologie des Froschherzens*, Halle, 1881.

not contract rhythmically if left entirely to itself, whereas the ventricle containing ganglia will do so.[1]

It has been supposed that **inhibitory ganglia** are present, because when a little muscarine is applied to the heart it causes




FIG. 106.—Diagram of the hypothetical nervous apparatus in the heart. M, motor ganglion. I, inhibitory ganglion. Q, quickening ganglion. V, inhibitory fibres; and S, quickening fibres from the head. A, A', B, and C, intermediate apparatus. E, fibres passing from the motor ganglia, M, to the muscular substance, F. [For simplicity's sake only one set of motor ganglia has been represented, but other similar ones are supposed to be present in other parts of the heart, and so connected with this set that they all work in unison. It must be remembered that this diagram is purely hypothetical: but if this be carefully borne in mind, the sketch will be found of service in remembering and comparing the action of different poisons on the heart.]

it to stop in diastole. This effect is not developed all at once, but goes on gradually increasing, and its action in this respect seems rather to point to its effect upon ganglia than upon nerve fibres.

It has been supposed that the vagus acts through this inhibitory ganglion or ganglia because irritation of the vagus arrests the heart in diastole, just as muscarine does; but it has been supposed to be connected by some **intermediate apparatus** with the inhibitory ganglia, because we find that when nicotine is applied to the heart irritation of the vagus will no longer arrest its beats, but that irritation of the venous sinus, in which the inhibitory ganglia have been supposed to be situated, will do so at once.

It has been supposed that the inhibitory apparatus, I, was connected by an intermediate structure with the motor ganglia, M, because physostigmine does not produce the extraordinary still-stand which muscarine does, but it counteracts to a certain extent the effects of atropine which muscarine does not. Physostigmine in small doses increases the excitability of the vagus, so that a slight stimulus applied to that nerve, so slight that it would under ordinary circumstances be insufficient to affect the heart, will stop it.[2] In large doses it appears to paralyse the vagus. The difference of action between muscarine and physostigmine seemed to show that they acted on different nerve structures; while the mutual power of atropine and physostigmine

[1] The recent researches of Gaskell have shown that the muscular fibre of the heart of the tortoise will contract, although it contains no ganglia. The question of muscular rhythm independent of ganglia will be considered further on.

[2] Arnstein and Sustschinsky, *Würzburger physiol. Untersuch.* iii.

to neutralise each other's effects within certain limits indicated that atropine acted on the same nerve structure as physostigmine and consequently on a different one from muscarine.[1]

When atropine is applied to the heart it completely removes the effect of muscarine and totally prevents any arrest being produced either by irritation of the vagus or the venous sinus. It has therefore been supposed that nicotine acts upon the intermediate apparatus, A, but that atropine acts either upon I or upon B.

The reason why it has been supposed that **quickening ganglia** exist is, that when irritation is applied to the vagus after its inhibitory power has been destroyed by the administration of nicotine or atropine it no longer produces slowness or still-stand of the heart, but, on the contrary, quickens its pulsations. But the **quickening** does **not** take place **immediately**, it only occurs some time after the application of the stimulus. If it is applied only for a short time, no quickening may take place until after its removal, but the quickening once induced remains for a considerable time. This seems to indicate that the stimulus does not act through nerve-fibres, as these would conduct the stimulus directly to the muscle, but rather through some ganglionic apparatus. It has been supposed that this apparatus is not identical with the motor ganglia themselves, because if the heart is irritated directly, its pulsations at once become quickened, and the quickening does not last long after the irritation is removed.

It is evident, however, that though this hypothetical schema allows us to explain in a fairly satisfactory manner the action of many drugs, yet it can only be looked upon in the same light as the hypothesis of cycles and epicycles in astronomy, which was useful for a time, and enabled astronomers not only to recollect but to predict facts. Its use was only temporary, and the hypothesis just at the time of its greatest complication gave place to one of the greatest simplicity.

It is probable, indeed almost certain, that the same thing will occur in regard to the action of drugs upon the heart, and that the whole complication of motor ganglia, inhibitory ganglia, accelerating ganglia, vagus endings, and intermediate fibres may resolve themselves simply into a question of the mutual relationships between the rate of rhythm and rapidity of conduction in the muscular fibres, nervous ganglia, and nerve-fibres respectively. Schmiedeberg's hypothetical schema has been most useful for several years, but facts which it will not explain are beginning to accumulate, and we must look in another direction for their explanation. The whole question of the action of drugs upon the heart is far from being completely solved

[1] Lauder Brunton, *op. cit.*

but I shall try, if possible, to indicate the direction in which pharmacology is at present looking for an explanation.

For this purpose it will be necessary to go still more fully into the physiology of the heart than we have already done.

Before doing so, however, it may be advantageous to put in




FIG. 107.—Diagram of the heart and vessels to illustrate the action of drugs on the various parts of the circulatory apparatus as given in the following tables. A, indicates accelerating ganglia.

a tabular form the action of the most important drugs on the various parts of the circulatory apparatus, according to the prevalent opinions at present.[1]

[1] In drawing up this table [see pp. 316–319] I have been greatly aided by the admirable paper of Professor Boehm, read before the International Congress in London in 1881.

Cardiac Muscle.

STIMULATED BY.

[Stimulation is shown by increased energy of contraction, the rate of pulsation remaining the same or becoming slower.]

So-called cardiac poisons. With a larger dose the stage of stimulation is followed by one of peristaltic action, and final arrest in systole.[1]

- Digitalin.
- Digitaleïn.
- Digitoxin.
- Erythrophlœum.
- Helleboreïn.
- Nereïn (Oleander).
- Scillaïn.
- Antiarin.
- Strophanthus.
- Thevetine.
- Theveresine.
- Veratrine.
- Barium salts.
- Caffeine (produces rigor).
- Potassium salts. (In small doses.)
- Copper double salts. (In small doses.)
- Zinc double salts. (In small doses.)

These do not cause peristalsis, nor arrest in systole. They excite the heart to pulsate rhythmically, after it has been made to stand completely still in diastole by the application of muscarine.

- Guanidine.
- Physostigmine.
- Camphor.
- Monobromocamphor.
- Borneol.
- Arnica-camphor.
- Anilin sulphate.
- Cumarine.

DEPRESSED OR PARALYSED BY.

[Depression is shown by diminished energy of contraction with final stoppage in diastole. The cardiac muscle is shown to be paralysed by no longer contracting on stimulation, either mechanical or electrical.]

- Salicylic acid.
- Potassium salts. (In large doses.)
- Copper double salts. (In large doses.)
- Zinc double salts. (In large doses.)
- Quinine (?).
- Saponin (removes the systolic still-stand produced by digitalin).
- Apomorphine.
- Emetine.
- Muscarine.
- Pilocarpine.
- Veratrum viride (veratroidine and jervine).

Motor Ganglia.

[Stimulation is shown by increased rapidity and energy of contraction, which is observed, not only when the drug is given to an animal, but when it is applied directly to the heart.]

Alcohol group.

- Alcohol.
- Ether.
- Chloroform.
- Chloral.
- Anæsthetics generally.

- Cyanogen.
- Arsenic.
- Quinine.
- Guanidine.

[Depression is evidenced by slower and less powerful pulsations, with final stoppage in diastole. This stoppage is shown to be due to the action of the drug on the ganglia, and not on the cardiac muscle, by the heart contracting on stimulation, either mechanical or electrical, after spontaneous pulsation has ceased.]

- Ergot.
- Antimony (?). The stoppage in diastole caused by antimony is converted into stoppage in systole by helleboreïn.
- Hydrocyanic acid.

The same drugs that stimulate in small doses depress when used in larger quantity, or at a later stage of their action.

[1] This stoppage of the heart in systole occurs in frogs, but in higher animals the heart may stop in diastole.

Inhibitory Ganglia.

STIMULATED BY.

[Stimulation is shown by the direct application of the drug to the heart, stopping its spontaneous pulsations completely, while it still contracts on the application of a stimulus either mechanical or electrical.]

Muscarine.
Pilocarpine.

DEPRESSED OR PARALYSED BY.

[Depression or paralysis is shown by stimulation, not only of the vagus trunk, but of the venous sinus itself, having lost all power to slow or stop the heart; and by the direct application of muscarine also having no action.]

Atropine.
Hyoscyamine.
Daturine.
Duboisine.
Cocaine.
Sparteine.
Saponin.

Vagus-ends in the Heart.

[Stimulation either of the ends of the vagus in the heart or of the inhibitory ganglia is shown by the injection of a drug rendering the pulse slow after previous division of the trunks of the vagi.]

Physostigmine (?).
It is said to render the peripheral ends of the vagus more sensitive, so that a slighter stimulus will stop the heart applied to the trunk.

[Depression or paralysis is shown by irritation of the vagus trunk no longer producing slowness or stoppage of the pulsations of the heart, while the application of muscarine, or irritation of the venous sinus, will still cause stoppage.]

Nicotine.
Saponin.
Lobeline.
Curare, methyl-strychnine, and probably large doses of all drugs which have the power of paralysing the ends of motor nerves.

Vagus Centre.

[Stimulation is evidenced by slowing of the pulse, disappearing on section of the vagi.]

Increased blood-pressure.
Venous blood.
Ammonia (in frogs).
Carbonic oxide.
Chloroform.
Chloral hydrate.
Butyl-chloral.
Belladonna (atropine).
Hyoscyamus (hyoscyamine).
Stramonium (daturine).
Aconite (aconitine).
Veratrum viride (veratroidine).
Tobacco (nicotine).
Digitalis (digitalin).
Hydrocyanic acid.

[Depression is evidenced by a quick pulse, which is not rendered slow by irritation of sensory nerves which usually produce slowing of the pulse, e.g. the central end of one vagus.]

Diminished blood-pressure and substances which produce it, e.g. nitrite of amyl and other nitrites.
Large doses of such substances as stimulate it in small doses, *vide* adjoining list.

Accelerating Centre.

STIMULATED BY.

[Stimulation is evidenced by the injection of the drug after previous section of the vagi rendering the pulse still more rapid than before.]

Irritants of motor centres.
- Venous blood.
- Ammonia.
- Cicutoxine.
- Caffeine.
- Delphinin.
- Picrotoxin.

DEPRESSED OR PARALYSED BY.

[Little or nothing is known about the depression of the accelerating centres.]

Saponin paralyses accelerating nerves.

Capillaries.

[Stimulation is shown by a rise in blood-pressure which remains after section of the spinal cord at the occiput, and is produced by the injection of the drug after previous division of the cord. It is also ascertained by the rate of flow through the vessels being diminished by the drug when circulation is kept up artificially in a frog whose nerve-centres have been destroyed, or in a single limb of a warm-blooded animal.]

Alkalies.
Digitalis and its allies.
Barium salts.
Potassium salts.
Copper.
Zinc, &c.

[Depression is shown by a fall of blood-pressure to a slight extent, even after the spinal cord has been divided, and by increased rapidity of flow when artificial circulation is kept up.]

Acids.
Nitrites.
Quinine (?)

Vaso-motor Nerves.

[It is very doubtful whether they are stimulated by drugs, and at any rate it is very difficult to ascertain whether any stimulation which may occur in the arterioles or capillaries is in the terminations of the vaso-motor nerves or in the muscular walls.]

[Paralysis is shown by the vessels not contracting on stimulation of the vaso-motor nerves, while they still contract on direct stimulation. This has been chiefly observed in the vessels of the intestines after irritation of the splanchnic nerves. The effect of irritation is ascertained by the alterations in colour of the intestines, and also by the alterations in the general blood-pressure which occur after irritation.]

Potassium salts.
Arsenic.
Antimony.
Mercury.
Iron.


Vaso-motor Centre.

STIMULATED BY.	DEPRESSED OR PARALYSED BY.
[Stimulation is evidenced by a rise of blood-pressure, which disappears on section of the spinal cord below the medulla, and does not occur if the cord has been divided before the injection of the drug. This rule is only partially true, because subsidiary vaso-motor centres occur in the spinal cord itself.]	[Depression is evidenced by fall in the blood-pressure not depending on failure of the heart's action. It is also shown by the absence of rise in blood-pressure on irritation of a sensory nerve.]
Irritants of motor centres, p. 176. Salts of ammonium. Potassium (?) Caffeine (?) Cicutoxine. Delphinin. Picrotoxin. Strychnine. Sanguinaria. Ergot (cornutine). Thebaine. — Convulsants.	Carbolic acid.
Irritants of motor centres, p. 176. Veratrine. Belladonna (atropine). Hyoscyamus (hyoscyamine). Stramonium (daturine). Carbolic acid (?) Salicylic acid. Turpentine. Camphor (rhythmically). Oil of rosemary, and other ethereal oils.	Lobelia.
Digitalin (?)	Large doses of most drugs, such as those in the adjoining column, which stimulate in small doses.
Ether (?) Chloroform (?) Chloral (?) Butyl-chloral (?) — Stimulant action doubtful; slight, and transient.	Depression usually occurs in the later stages of the action of such drugs even in moderate doses.

Stannius's Experiments.

Some of the most important experiments relating to the action of the various cavities of the frog's heart were first performed by Stannius, and bear his name.

When the venous sinus is separated from the rest of the heart by cutting it off with a sharp razor, or by a ligature tightly drawn round it at its junction



a *b* *c*

FIG. 108.—*a*, diagram of frog's heart ligatured at the junction of the venous sinus with the auricles. The venæ cavæ and sinus are represented with a crenated outline resembling the tracing which their beats might give if recorded on a revolving cylinder. The auricle and ventricle being motionless would only trace a straight line if connected with a recording apparatus. Their outline is therefore represented by a straight line. *b*, diagram of a frog's heart in which sections have been made at the junction of the sinus with the auricles, and at the auriculo-ventricular groove. The sinus and ventricles pulsate, whilst the auricles remain motionless. The beats of the ventricle should have been represented as slower than those of the auricle, as in *f*, Fig. 109. *c*, the same as *b*, but with the parts of the heart separated by ligature instead of section.

with the auricle, it continues to pulsate, but the auricle and ventricle stand perfectly still (*a*, Fig. 108). If now the auricle is separated from the ventricle

by another cut (*b*, Fig. 108), or another ligature be applied (*c*, Fig. 108), at the auriculo-ventricular groove, the auricles remain motionless, but the ventricle begins to beat, so that the venous sinus and ventricle are both pulsating, while the auricles are at rest. The venous sinus and the ventricle, however, no longer beat with the same rhythm, and the rate of the ventricular beats is usually much slower (*f*, Fig. 109). In this remarkable experiment the complete stoppage of the auricles and ventricle which follows the removal of the venous sinus has been supposed to show that the motor centres for the entire heart reside in the sinus, and that from them the motor impulses originate which keep up the rhythmical pulsations of the organ. But the fact that the ventricles begin to pulsate on their own account when separated by another cut from the auricle seems to show that they also contain motor centres. The hypothesis has therefore been advanced that both venous sinus and ventricles contain motor centres, while the auricles contain inhibitory centres.

So long as the auricles are in connection both with the venous sinus and the ventricle, the motor centres in the latter two cavities are supposed to be sufficiently powerful to overcome the resistance offered by the inhibitory centres, and thus the cardiac rhythm is maintained. When the motor centres of the sinus are removed, the inhibitory centres of the auricle are supposed to be so powerful as to keep both it and the ventricle in a state of rest.

When the ventricle is separated from the auricles and their inhibitory influence removed, it again begins to pulsate rhythmically. In order to obtain a clearer idea of the mechanism of the heart, many variations of the above fundamental experiments have been made.

The chief results of these are the following :—

First, section or ligature of the venæ cavæ or of the venous sinus at any point before its junction with the ventricle does not affect the action of the heart (*d*, Fig. 109).

Second, section or ligature of the auricles at any point above the auriculo-ventricular groove arrests the movements of the part below them, while that connected with the venous sinus still continues to pulsate (*e*, Fig. 109).




FIG. 109.—*d*, diagram of heart with ligature round the venous sinus. *e*, diagram of heart with ligature round middle of auricles. *f*, diagram of heart with ligature in the auriculo-ventricular groove. The pulsations of the ventricle are much slower than those of the auricle and venous sinus. This is indicated by the larger dentation of the outline of the ventricle.

Third, irritation of the vagus nerves usually produces stoppage of the heart-beats.

Fourth, ligature or section of the vagi before their entrance into the heart prevents their having any action upon it when they are stimulated.

Fifth, ligature or section of the venous sinus or auricles prevents any action of the vagi upon the part of the heart below the ligature or section.

It is evident that section or ligature of the heart at any point between the junction of the sinus and auricles and the auriculo-ventricular groove has the same action on the movements of the part below it as irritation of the vagus.

But more than this; although, as we have seen, the motor ganglia of the heart appear to be situated chiefly in the venous sinus, yet **irritation of the sinus** produces **complete still-stand** of the heart, even more perfect and prolonged than irritation of the vagus. Strong stimulation of the venous sinus has therefore the same effect as its removal. The parts whose motion have been arrested by section or by irritation, in the experiment just de

scribed, are not paralysed: this is shown by the effect of stimulation upon them.

When the auricles and ventricle are standing still after section or ligature of the venous sinus, **irritation** of the outside of the ventricle with a needle has




FIG. 110.—*g*, diagram of heart stopped by a ligature at the junction of the sinus and auricles. The *outside* of the ventricle is irritated by a needle, and the even outline indicates that no contraction occurs. *h*, diagram similar to *g*, but with the *inside* of the ventricle irritated by a needle. The projections on the outline of the heart indicate that one contraction of the ventricle and three or four of the auricles occur. *k*, diagram similar to *g* and *h*, but with the outside of the auricle stimulated by a needle. The projections indicate that one contraction of the auricle and one of the ventricle occur.

no action (*g*, Fig. 110); but if its interior be irritated by a needle (*h*, Fig. 110) the auricle contracts first, then the ventricle, then the auricle again two or three times, but the ventricle does not respond. When the auricle is irritated by a needle applied to its outside, contraction both of the auricle and ventricle ensues (*k*, Fig. 110). When the auriculo-ventricular groove is irritated by a needle there are usually eight or ten contractions in response. When the outside of the auricle is irritated by an interrupted current, numerous and rhythmical contractions both of auricle and ventricle ensue.

To sum up these results shortly, we find that either **removal of** the normal **stimuli** which pass in the direction of the circulation from the venous sinus to the auricle and then to the ventricle, or abnormally **strong stimulation,** produces arrest of the rhythmical movements of the heart, or, as it is usually termed, **inhibition.**

Some exceedingly instructive experiments have been made by Gaskell, who, instead of separating the cavities of the frog's heart from each other by sections or by a ligature, compresses more or less completely the point of junction, so as to impede or block (as it is termed) to a certain extent the transmission of stimuli from one cavity to another (Fig. 111).




FIG. 111.—Diagram to illustrate Gaskell's experiment. At *a* the jaws of the clamp hold the heart without compressing it, and each beat of the auricle is succeeded by one of the ventricle as shown by the figure $\frac{I}{I}$. At *b* the heart is compressed, and its rhythm disturbed, so that one beat of the ventricle only occurs for several of the auricles.

He does this by a clamp the two limbs of which are placed one on each side of the heart. By means of a micrometer screw their edges can be approximated so as either simply to hold the heart without pressure or to compress it to any desired extent. When the clamp is placed in the auriculo-ventricular groove, the beats of the auricles and ventricle are registered separately by levers above and below the clamp with which the auricles and ventricle are connected by threads.

When the heart is simply held by the clamp without compression, each beat of the auricle is followed by one of the ventricle; but when the auriculo-ventricular groove is compressed the transmission of stimuli from the auricle

to the ventricle appears to be blocked in somewhat the same way as it is b compression in the contractile tissue of medusæ, and one beat of the ventricl then occurs with every second, third, fourth, or more auricular beats, accord ing to the degree of pressure, and if this be very great the ventricle will ceas beating altogether.

The beats of the ventricle are shown in this experiment to be diminishe or arrested by hindering or blocking the transmission of stimuli to it fro the venous sinus and auricle. But, as one might expect, a diminution the stimuli themselves has a similar effect as a block to their passag Thus, if the auricle and sinus are heated, but not the ventricle, their rhythm is markedly quickened, but the ventricle now beats only once for every tw or even more pulsations of the auricle, the heat appearing to render th impulses proceeding from the auricle and sinus more rapid but more wea If the ventricle be heated as well, it will respond to each beat of the auricl so that the whole heart beats more quickly, but if the ventricle alone heated its rhythm remains unchanged.

Experiments which are likely to give useful information in regard to th action of various drugs on the cardiac muscle and nerves have been made b Gaskell by the aid of the clamp already described.

General Considerations regarding the Heart.

In ascidians the heart is a mere contractile sac open at both ends, an drives the fluid alternately in opposite directions. In snails it is a simp sac of protoplasm without differentiated nerves, but it drives the nutriti fluid in one direction. In the amphioxus there is no special heart, but on numerous contractile dilatations in the chief blood-vessels. In fishes th heart may be said to consist of three parts—the auricle, ventricle, an arterial bulb. The heart of the frog has already been described, and that mammals requires no description.

Even the complicated mammalian heart may be regarded as a speci development of the simple contractile tube endowed with the power peristaltic contraction. The direction in which the contraction occurs probably determined at first by slight differences in the stimuli to which t two ends of the tube are subjected, and the direction may be altered altering the stimulus. Thus in the heart of a fish the contraction usual proceeds from the auricle to the ventricle and bulb, but by irritating the bu the direction may be reversed so that the bulb contracts first and the auric last, and this reversal of rhythm may persist for some time.[1] In the mam malian heart it is not perhaps so easy to reverse the rhythm by simp irritation, and probably some interference with the cardiac nervous system also requisite, but by introducing tincture of opium into the mammali ventricle the rhythm may be reversed so that the beats of the auricle foll instead of preceding those of the ventricle.[2]

The **cause of rhythmical pulsation** in the heart is usually supposed be the motor ganglia which it contains. Of late years numerous research have shown that, although these are very important indeed, yet they are n to be looked upon as the exclusive originators of the rhythm. The heart the snail, although it consists of simple protoplasm without nerves, be rhythmically, and when a ligature is tied across the venous sinus in the fr the venæ cavæ and upper part of the sinus continue to beat although th possess no special ganglia, while the rest of the heart remains motionl although it contains both Bidder's and Remak's ganglia. From this expe ment one would be inclined at first to say that the **initiation of rhyth** in the heart is due to the **muscular tissue** of the venæ cavæ and sinu

[1] Gaskell, *Journ. of Physiol.*, vol. iv. p. 78.
[2] Ludwig, *Physiologie*, 1861, vol. ii. p. 88.

and might be inclined to regard the **nervous system** of the heart as an apparatus for **merely conducting** stimuli from the sinus to the auricles and ventricle.

Other experiments would seem to deprive the nerves even of this function, for Engelmann [1] and Gaskell have shown that when Bidder's ganglia are excised, or the nerves cut through as they traverse the auricles, contractions still pass from the venous sinus to the ventricle, and continue to do so when the nerves have not only been divided but most of the muscular tissue of the auricle has been cut through and only a narrow bridge remains behind. This may seem to prove that the muscular tissue of the heart conducts the motor stimuli from the venous sinus to the auricle and ventricle, which cause them to contract, and may appear to show that the cardiac nerves are entirely superfluous. A similar mode of reasoning, however, would lead us to say that the ganglia in medusæ are also superfluous because the contractile tissue will pulsate rhythmically after they have been cut off, if it be placed in acidulated water.

In regard to the **conduction of stimuli**, the fact probably is that under favourable conditions they may be conveyed by the muscular tissue alone from the sinus to the ventricle, but under ordinary circumstances they are conveyed in part, at least, by the nerves.

Ganglionic tissue is more sensitive than contractile tissue, and the stimuli which act on the ganglia of the medusa, under the conditions in which it lives, are insufficient to excite contractile tissue. When the ganglia are paralysed by a poison, the effect is the same as if they were cut off, and pulsation is arrested. A similar condition appears to occur in the ventricle. The muscular tissue forming the apex of the frog's heart under ordinary circumstances will not beat when separated from the rest unless an extra stimulus be applied to it. The ventricle containing Bidder's ganglia will usually pulsate rhythmically, and if its apex be dipped in a solution of chloral no effect is produced, but if its base be dipped in the solution so that the drug acts upon the ganglia, the pulsations are arrested apparently by paralysis of the ganglia (Harnack).

We may consider, then, that ganglia are more susceptible to stimuli than muscular fibre, and have the function of making it pulsate rhythmically when it otherwise would not.

It is probable also that they serve to prevent the occurrence of blocks at the junction between the different cavities of the heart which might occur if the stimuli were transmitted from each cavity by muscular tissue alone.

When the **heart** is **dying**, and when we may fairly assume that its nerves are losing their functional activity, such blocks actually take place, and the ventricle may beat only once for every two or three or more beats of the auricle.

The cardiac muscle is also without doubt losing its functional activity, yet it still retains it to such an extent that each cavity can contract powerfully. The same thing occurs when the heart is poisoned with chloral, iodal, or other members of the same group, which, as already mentioned, paralyse the cardiac ganglia.[2]

In the present state of our knowledge it is difficult to make any absolute statement regarding the function of the **cardiac ganglia**, but I think we may fairly assume them to have two **functions**, (1) to originate rhythmical pulsations in the heart when the muscular fibre alone, although capable of independent rhythmical pulsation, would not pulsate under the conditions which may be present; (2) to transmit and receive stimuli from one cavity of the heart to the other, and thus prevent the occurrence of blocks at the junction of the cavities and consequent irregular action which might occur if the stimuli were transmitted only by the muscular fibre.

---

[1] Pflüger's *Archiv*, xi. p. 465.

[2] Harnack and Witkowski, *Arch. f. exp. Path. und Pharm.*, vol. xi. p. 15.

Regulating Action of the Nervous System.

The necessity of some means for regulating the action of the heart in accordance with the wants of the body is obvious, and in the heart we find that such an arrangement exists in relation both to the strength and rate of pulsation.

The **action of the vagus** upon the heart has long been a matter of great dispute, some physiologists holding it to be the motor nerve of the heart, while the majority regard it as inhibitory. The reason of this disagreement probably is that the right and left vagi have frequently different effects upon the heart, and that the effects even of the same vagus may vary according to the state of nutrition of the heart, and other circumstances. We find for example in rabbits that both the right and left vagi can usually slow or stop the heart; but sometimes the right has much greater power in this respect than the left, and in some species of tortoise the left vagus has no inhibitory action upon the heart at all, and in the frog during the breeding season the action of the vagi is very uncertain. The cause of these different results appears to be that the vagus is a very complex nerve, and contains accelerating and strengthening fibres which are derived from the sympathetic, as well as inhibitory fibres which are derived from the spinal accessory, and sensory fibres which belong to the vagus proper. The results of stimulating the vagus trunk will vary according to the proportion of these different fibres which it contains, and on the activity of each kind at the time of stimulation.

A number of experiments made by Gaskell on the heart *in situ* and with the clamping apparatus already mentioned, by which the beats of the auricle and ventricle may be simultaneously recorded, have led him to divide the effects produced on the heart by irritation of the vagi into two types: (*a*) affections of the **rate** of rhythm; and (*b*) affections of the **strength** of the contractions.

The effect of vagus stimulation on the heart of the frog may be divided into five classes.

The 1st class is that which occurs with the heart of the tortoise or frog *in situ* or just after removal from the body. The vagus here causes arrest by **slowing** the rate of **rhythm**; and, in consequence, the first beats which occur after the heart again begins to beat are slower than those preceding the stimulation.

In the next classes the vagus produces its effect by **weakening** the **strength** of the contractions so that they may become invisible and the heart remain still, but after it begins to beat their rate is as quick or quicker than before.




FIG. 112.—After Gaskell. Tracing showing the action of the vagus on the heart. *Aur.* indicates the auricular, and *Vent.* the ventricular tracing. The part included between the upright lines indicates the time during which the vagus was stimulated. *C.* 8 indicates that the secondary coil used for stimulation was eight centimètres distant from the primary. The part of the tracing to the left hand shows the regular contractions of moderate height before stimulation. During stimulation, and for some time after, the movements of both auricle and ventricle are entirely arrested. After they again commence they are small at first, but soon acquire a much greater amplitude than before the application of the stimulus.

The 2nd class is an example of this. In it irritation of the nerve produces complete stoppage of both auricles and ventricles. This is followed by con

tractions, which are at first so small as to be hardly visible, but quickly grow larger until they are much greater than the normal; from this they gradually decrease to the normal size (Fig. 112).

The two types of action may occur together, the rhythm becoming slower and the contractions smaller. This is seen in Fig. 113.




FIG. 113.—After Gaskell. Tracing showing diminished amplitude and slowing of the pulsations without complete stoppage, during irritation of the vagus.

The 3rd class is where irritation produces no still-stand of either auricles or ventricles, but only great diminution in the size of the beats, followed by a gradual increase and subsequent fall similar to that just described. This curve is like the first, but differs from it in the absence of the complete arrest (Fig. 114).




FIG. 114.—After Gaskell. Tracing showing diminished amplitude of contraction without slowing or stoppage during irritation of vagus.

The 4th is that where there is no primary diminution, but gradual increase in the size of the beats, which again sink to the normal (Fig. 115).

The 5th is where irritation of the vagus does not stop the beats of the venous sinus but causes both auricles and ventricle to stop.

The ordinary inhibitory effect of the vagus is the one which is noticed best in well-nourished hearts, and as the heart becomes more exhausted, and is dying, the motor power of the vagus becomes more and more pronounced. We find a similar occurrence in the case of the splanchnics, which lose their inhibitory power as the intestine dies. Nervous structures as a rule die sooner than muscle, and the conclusion is not unwarranted that the disappearance of the inhibitory action of the vagus is due to a gradual death of the nervous structures upon which it acts in the healthy heart, while its action on the muscular tissue, which has a more prolonged vitality, still remains. The actual increase, indeed, in its motor action we may attribute to the removal of nervous interference.

Hypothesis regarding the Action of the Vagus.—Nervous interference as a cause of inhibition was clearly pointed out by Bernard, and in the case of the heart has been discussed by Ranvier with his usual clearness.

In the grey matter of the spinal cord there is ample room for the slowing

of nervous stimuli by transmission along paths of different lengths (p. 169), more especially as a small length of grey matter is equivalent to a great length of ordinary nerve-fibre (p. 162).

In the heart we might suppose there was no such provision, but, as Ranvier points out, the ganglion cells in the auricle have one of their fibres wound




FIG. 115.—After Gaskell. Tracing showing increased cardiac contractions from irritation of the vagus. [In this figure the upper tracing shows the ventricular and the lower the auricular contractions.]

spirally, so as to give a great length in small space, and thus provide for retardation and interference of stimuli (Figs. 116, 117). If we suppose that some of the nerve-fibres contained in the vagus trunk pass through these spiral ganglia while others pass on directly to the heart, we can understand that the different rates of transmission may lead to interference and stoppage of pulsation. Alterations in the rate of transmission along the spiral fibre may again convert interference into coincidence of waves and cause acceleration and increased action. If these spiral fibres are affected by drugs so that the rate of transmission of stimuli along them is altered, we can understand that the interference may in some cases be increased, in others diminished, and that an increase of interference may readily pass into the opposite condition, so that the irritation of the vagus no longer produces stoppage but acceleration of the heart, such as actually occurs on irritation of the vagus after its inhibitory power has been paralysed by atropine.

We can understand also how curare and the large class of drugs which paralyse the motor nerves may destroy the inhibitory power of the vagus.

Inhibition in the Heart.—But it is probable that interference between the nervous structures is not the sole cause of inhibition in the heart; we must look also to the relationship between nervous and muscular rhythms. Thus distension of the ventricle frequently diminishes or abolishes the action of the vagus, the stimulus which the pressure within the heart exerts on the muscular fibre appearing to more than counteract the inhibitory action of the nerve. The condition of the muscular fibre too is probably very important. Thus, feeding the frog's heart with a solution containing soda appears to paralyse the power of the vagus, which is again restored by potash.[1] (Compare their action on the cardiac muscle, p. 307.)

It is indeed to an action on the muscle rather than on the nerve that we must probably look for the explanation of the action of atropine. For the heart in snails, though apparently destitute of both ganglia and nerves, is arrested by an interrupted current. This effect is prevented by atropine.

[1] Lowit, *Pflüger's Archiv*, xxv. p. 466.




FIG. 116.—Part of the posterior cardiac nerve, highly magnified, showing the ganglia.[1]




FIG. 117.—Spiral ganglion cell from the pneumogastric of the frog. This figure is not taken from the cells in the cardiac nerves, as in them the connection between the spiral and straight fibres has not been clearly made out, but it is probable that these cells have a structure similar to the one figured (Ranvier, *op. cit.* pp. 114-120). *a* is the cell-body, *n* the nucleus, *r* the nucleolus, *d* nucleus of the capsule, *f* the straight fibre, *g* Henle's sheath, *sp* spiral fibre, *g'* its *gaine*, *n'* nucleus of Henle's sheath.[2]

[1] Ranvier, *Leçons d'Anatomie Générale*, année 1877-78, p. 106.
[2] *Ibid.*, p. 114.

It is exceedingly difficult, or perhaps impossible, with the physiological data which we at present possess, to give a complete and satisfactory explanation of the action of drugs on the heart, but it is evident that while all new discoveries tended for a while to render our ideas regarding the cardiac mechanism more and more complicated, our increasing knowledge now tends to render them more simple. Before long we may hope that systematic investigations into the action of drugs on the excitability, rhythm, and power to conduct stimuli of the cardiac muscle itself, on the action of drugs upon the rhythm of the ganglia, and on the rate of transmission by the nerves, as well as on the mutual relations of these various factors, will at last give us a clear understanding of this very difficult and complicated subject.

Therapeutic Uses of Drugs acting on the Circulation.

The drugs which act on the circulation have been divided according to their action into stimulants, tonics, and sedatives. Each of these classes has been further subdivided into cardiac and vascular, according as its members act on the heart and vessels. There are thus six subdivisions in all: cardiac stimulants, vascular stimulants, cardiac tonics, vascular tonics, cardiac sedatives, and vascular sedatives.

Cardiac Stimulants.

These are substances which rapidly increase the force and frequency of the pulse in conditions of depression. The most important are ammonia, and alcohol in its various forms, but there are also other substances which are sometimes useful.

Heat.

Liquor ammoniæ. B.P. Aqua ammoniæ. U.S.P.
Ammonium carbonate.
Sal volatile (spiritus ammoniæ aromaticus).
Alcohol.
Brandy.
Whisky.
Eau de Cologne.
Gin.
Liqueurs.
Strong wines.
Atropine.
Ether.
Chloroform.
Spirit of chloroform.
Spirit of ether.
Camphor.
Aromatic volatile oils.
Oil of turpentine.
Heat and counter-irritants to the præcordium.

Cardiac stimulants are used to prevent or counteract sudden failure of the heart's action in syncope or shock due to menta

emotion, physical injury, or poisoning by cardiac depressants, or by the bite of snakes, or when the action of the heart becomes much depressed in the course of fevers or other diseases.

Although alcohol after its absorption stimulates the heart, yet its effect on the heart is probably, to a considerable extent, due to a reflex action on it through the nerves of the mouth, gullet, and stomach. Its action is consequently very rapid, and begins before there has been time for much of it to be absorbed. On this account, however, it must be given in a somewhat concentrated form, and if much diluted, as in the form of weak wine or beer, which has little or no local action and can exert no reflex action, it has little or no power as an immediate stimulant. When given in disease it is best to administer it in small quantities frequently, and the rule by which to ascertain whether it is doing good or not is: Does it bring the circulation more nearly to the normal or not? If it does so, it is beneficial; if it does not, it is harmful. Thus, if the pulse be too quick, alcohol should render it slower; if already abnormally slow, alcohol should make it quicker. If too small, soft, and compressible, alcohol should render it larger, fuller, and more resistant. There are other rules connected with the effect of alcohol on other organs which also regulate its use in disease, but these will be given further on.

Ether alone or mixed with alcohol has a stimulant action almost more rapid than alcohol itself; and chloroform in small doses, and especially when mixed with alcohol, is also a powerful stimulant.

Ammonia has not only a reflex action on the heart like that of alcohol, but has powerful stimulating action on the vaso-motor centre. Its action when applied to the nose in syncope has already been discussed. In cases of snake-bite thirty minims of liquor ammoniæ have been injected directly into the veins. The immediate stimulating effect appears to be beneficial, although it is doubtful whether life can really be saved by this means.

Camphor is useful as a cardiac stimulant in febrile conditions with a tendency to failure of the circulation, as in typhus and typhoid fevers; in exanthemata, when the rash does not appear; in asthenic pneumonia, and in the typhoid condition depending on other diseases.

Aromatic volatile oils and substances containing them have also been used in similar but less severe conditions.

One of the most powerful of all cardiac stimulants is heat, and when the heart's action threatens to fail it may be frequently restored by warm fluid taken into the stomach, or by the application of an indiarubber bag[1] or bottle filled with hot water, or

[1] An indiarubber bag for holding hot water is one of the most useful things an invalid can carry about with him. It should have a flannel case fastened by buttons

of a bag filled with hot sand or salt, or of a hot poultice to the cardiac region.

It must be remembered that the high temperature of the body in febrile conditions acts as a cardiac stimulant; and if this stimulus be removed by the temperature falling, either in the natural course of the disease or in consequence of the administration of antipyretics, the heart may fail and collapse, and death ensue, unless it be stimulated either by medicines or by the application of heat to the cardiac region.

Vascular Stimulants.

These are substances which cause dilatation of the peripheral vessels,[1] and thus render the flow of blood through them more rapid. The most important are:

Heat.

Alcohol in its various forms.	Dover's powder.
Ether.	Acetate of ammonium.
Nitrous ether.	

Alcohol and ether, by stimulating the heart at the same time that they dilate the vessels, render the peripheral circulation very vigorous. From its stimulant action on the vaso-motor centre, ammonia is less useful than alcohol.

Vascular stimulants are useful in equalising the circulation and preventing congestion of internal organs. Thus, from exposure to cold generally so that the whole surface of the body is chilled, or from a local chill due to a draught, or to the combined action of cold and moisture, as in wet feet, congestion of the respiratory tract, or of the stomach, intestines, or pelvic organs may occur. This frequently evidences itself immediately either by rigors or by localised pain. If the congestion be not relieved inflammation may occur, but if alcohol be taken either in a concentrated form or diluted with boiling water, the vessels of the surface dilate, a warm glow is felt throughout the body, the shivering and pains disappear, and frequently all injurious results of the chill are averted. If the external cold, however, is very excessive, and the exposure is to be prolonged, alcohol must be

---

so that it can easily be removed. This allows the heat to come gradually through without burning the skin. For a small gratuity the engine-driver or stoker is usually willing to fill the bag with hot water, and the bag can be refilled if necessary at each station where there is a sufficiently long stoppage. This is sometimes a very great boon to invalids on long railway journeys such as they are often compelled to make on their way to winter health resorts.

[1] From this definition it will be observed that while cardiac stimulants increase the functional activity of the heart, vascular stimulants do not increase the contractile power of the vessels, nor the activity of the vaso-motor centre, but, on the contrary, diminish the contraction of the vessels.

used with great care, as the blood becomes much more rapidly cooled when the cutaneous vessels are dilated than when they are contracted; and in arctic temperatures a person is much more readily frozen to death after the free use of alcohol. Dover's powder is also a useful vascular stimulant, though less powerful and rapid than alcohol. It is of use in similar cases to those just described, and may be given after the alcohol to supplement and continue its action.

Slighter cases of chill may be treated by Dover's powder alone, and ten grains of it taken at night will often cut short commencing coryza, and will frequently prevent slight increase of consolidation occurring round a cavity after a chill in persons suffering from phthisis. Patients suffering from this disease should not omit to take a Dover's powder or some other vascular stimulant at night whenever they feel as if they had caught cold, and before any local mischief can be detected.

All nitrites dilate the blood-vessels and thus act as vascular stimulants. The one most commonly employed is nitrite of ethyl in the form of spirits of nitrous ether. This remedy, taken in hot water or along with acetate of ammonium, is a useful vascular stimulant, and is often used for the same purposes as Dover's powder.

Camphor is frequently used as a popular remedy instead of alcohol or Dover's powder in order to cut short coryza or catarrh, about ten drops of the tincture being taken on a piece of sugar. Local vascular stimulation is useful in removing chronic inflammation or consolidation. For a more detailed account of its action and uses, *vide* Irritants and Counter-irritants (p. 343).

Cardiac Tonics.

These are drugs which have no perceptible immediate action on the heart, but when given for a little while render its beats much more powerful, although usually much slower. The most important of them are :—

Digitalis.
- Digitalin.
- Digitalein.
- Digitoxin.

Erythrophlœum (Casca)
- Erythrophlœin.

Strophanthus hispidus.
- Strophanthin.

Convallaria majalis.
- Convallamarin.

Adonis vernalis.
- Adonidin.

Squills.
- Scillaïn.

Helleboreïn.

Antiarin.

Caffeine.

Nux vomica.
- Strychnine.

All these drugs, as already mentioned, stimulate the cardiac muscle and render its contractions slower and stronger. Although in large doses they tend themselves to produce irregular and peristaltic contraction of the heart, yet in moderate doses they tend to remove irregularity already present. The cases in which they are most useful are those in which the left ventricle is unable to drive the blood with sufficient force into the aorta. It is evident that this inability may depend on simple weakness of the ventricle without any valvular lesion, or upon irregular action of the various cavities, or upon valvular lesions, or on a combination of two or more of these conditions.

Weakness of the heart may occur in cases of general malnutrition, as anæmia and chlorosis, or in consequence of acute disease such as fevers. It is not necessarily accompanied by dilatation, but if it continues for some time the cavities are apt to dilate. A considerable amount of dilatation may sometimes occur without leading to valvular incompetence, but if it proceeds beyond a certain point the cusps of the tricuspid and mitral valves become insufficient to close the dilated orifices, and mitral or tricuspid regurgitation is the result. For it must be remembered that in the healthy heart the tricuspid and mitral orifices are much diminished in size by the contraction of the muscular tissue of the heart at the moment of systole.

In cases where the mitral valve is thus affected, a systolic murmur may be heard at the apex during life, but, should death occur, the valves may be found perfectly competent to close the mitral orifice in the heart, which is then in a state of more or less complete rigor. In all such cases of weakness of the heart, either with or without dilatation and functional incompetence of the valves, digitalis is of the greatest possible service. I have also found erythrophlœum give most satisfactory results in simple dilatation without incompetence.

The form of valvular disease in which cardiac tonics are especially useful is mitral regurgitation. In all forms of valvular disease there is a tendency to the occurrence of compensatory hypertrophy, which will enable the heart to do its work in spite of the hindrance caused by the disease. Wherever this is sufficient, so that the circulation is well carried on, notwithstanding the valvular defect, cardiac tonics are useless and likely to be injurious. Nor should they be given when the compensatory hypertrophy is just beginning to take place. But when compensation is insufficient, cardiac tonics are of the very highest value. In mitral regurgitation the blood, instead of being driven entirely onwards by the left ventricle into the aorta, is partially driven backwards into the left auricle at the very moment that the right ventricle is driving the blood into the pulmonary artery and lungs. Hence there is a tendency to pulmonary congestion, which may lead to hæmoptysis. The right ventricle having to work

against greatly increased pressure tends to dilate, the blood accumulates in the venous system generally, and venous congestion of the stomach leads to loss of appetite, of the kidneys to albuminuria, and of the limbs to anasarca. While the venous system is gorged, the arterial is correspondingly empty, and it is not only the stomach, kidneys, and limbs which suffer by the stagnation of the circulation, for a similar condition exists in the heart itself. In consequence of this its action may become not only weak but irregular, and matters go on from bad to worse.

In such a condition cardiac tonics are of the greatest possible service. By increasing the strength of the cardiac muscle they not only enable the left ventricle to drive a larger proportion of blood into the aorta, but they actually tend to lessen the opening of the mitral orifice in the same way as in functional incompetence. By rendering the pulse less frequent they allow the ventricle to become more completely filled during each diastole. The pressure on the lungs, right side of the heart, and venous system is diminished, the arterial system becomes correspondingly filled, the congestion of the various organs is diminished and their function correspondingly improved.

The consequence of this is, that in the stomach we have increased appetite, in the kidneys diminished albumen, and in the limbs removal of anasarca. The heart also benefits by the improved circulation in it, its pulsations are more regular and powerful, and it will often continue to act well and carry on the circulation satisfactorily even after the tonics which first enabled it to do so have been discontinued.

In mitral stenosis cardiac tonics probably are beneficial both by lengthening the diastole, and thus allowing more time for the blood to run out of the auricle into the ventricle, and by strengthening the auricle itself. Besides this, mitral stenosis is usually accompanied by mitral regurgitation, which will be benefited by cardiac tonics in the way just described.

In aortic stenosis digitalis is of little or no use when there is sufficient compensatory hypertrophy, but may be useful if the heart is becoming feeble.

There has been considerable difference of opinion regarding the use of digitalis in aortic regurgitation, some holding it to be useful and unattended with any risk, while others regard its administration as attended with considerable danger. In considering this question we must bear in mind that the risks which a patient runs from aortic regurgitation are not the same in all stages of the disease. While the aortic regurgitation is uncomplicated, and the ventricle strong enough to carry on the circulation, the risk to the patient is that of sudden death by syncope.

It is easy to understand how this should be the case. When

the aortic valves are healthy the arterial system may be regarde as a large-branched tube open only at one end—the capillaries— and through these the blood flows so slowly that there is no ris of syncope from the blood-pressure falling too low (Fig. 118, *a*).

In a case of aortic regurgitation, on the contrary, the arteria system is open at both ends, and during the cardiac diastole th blood is not only running through the capillaries, but is runnin backwards into the left ventricle, so that the conditions are favour able for the blood-pressure falling so low as to induce syncope (Fig 118, *b*). It is evident that anything which prolongs the diastol and thus allows more time for the arterial system to empty itsel through the capillaries at one end and into the ventricle at th other, will increase the risk of syncope, and for this reason digi talis cannot be regarded as free from danger in aortic regurgita tion. The danger may, however, be very considerably diminishe




FIG. 118.—Diagram to illustrate the tendency to syncope in aortic regurgitation. In *a* the aort valves are healthy and prevent regurgitation. The carotid and its branches are shown as fu In *b* there is aortic regurgitation, the blood flows out of the arterial system through the cap laries and into the heart. The carotid and its branches are shown as empty. In *c* the conditi is the same as in *b*, but the patient is supposed to be in the recumbent posture, and the carot and its branches remain full.

by keeping the patient in a recumbent posture with the hea low. The column of blood above the aortic valves being lowe there will be somewhat less tendency to regurgitation; and eve should the arterial pressure fall much, the brain may still receiv sufficient blood supply to prevent syncope.

In cases of aortic disease, where compensatory hypertrophy insufficient, or where the hypertrophied heart is becoming e feebled and dilated so that the mitral valves no longer close th orifice, the most urgent risk to the patient is no longer that sudden syncope, but of pulmonary embarrassment, dropsy, an all the other consequences of mitral regurgitation. In such case as well as in those where organic disease of both mitral an aortic valves exist simultaneously, we must treat the urge symptoms and give digitalis or other cardiac tonics.

In dilatation of the right heart due to bronchitis or emphysema, digitalis is frequently useful, though its benefit is less marked than in mitral disease.

Risks attending the Administration of Digitalis and other Cardiac Tonics.—The great risk attending the use of these drugs is sudden death from syncope. Whenever it is necessary to push them to any extent, the patient should be kept strictly in the recumbent posture, and not allowed to raise himself quickly even into a sitting position on any pretence whatever, even when there is no aortic complication. The effects of sudden change from the lying to the standing position in producing syncope have already been mentioned (p. 205), and when the patient is allowed to sit up he should be helped up slowly and with care. A change from the lying to the standing position by the patient getting out of bed is, of course, still more dangerous than simply sitting up in bed, and the most dangerous thing of all is for him to get up for the purpose of micturition. The reason of this has been already explained (p. 264).

Such strict precautions are, of course, not required excepting when the cardiac tonics have to be given in full doses. But when it is necessary to do this they should on no account be neglected.

As digitalis is cumulative in its action, it is often advisable after continuing it for several days to leave it off for a day or two, and then recommence; and this is a useful precaution when giving digitalis to out-patients who are seen at an interval of a week or more, even when the dose is comparatively small. Another difficulty in the administration of cardiac tonics is the gastric disturbance, loss of appetite, and vomiting which they are apt to produce.

In cases where the arterial tension is already abnormally high—e.g. in cases of contracting kidney—and the heart seems unable to drive the blood into the aorta, the proper treatment, of course, is to reduce the abnormally high blood-pressure by purgatives, diuretics, and diaphoretics, and not to attempt to strengthen the heart by the use of cardiac tonics. If this be done the pressure may be raised still further and burst the vessels, giving rise to apoplexy.

Vascular Tonics.

Vascular tonics are substances which cause increased contraction of the arterioles or capillaries. They not only raise the blood-pressure, but influence to a considerable extent the quantity of lymph poured out into the tissues or absorbed from them, and thus modify tissue change. They are of special importance in the treatment of dropsy.

The most important vascular tonics are:—

Digitalis.
Iron.
Strychnine.

Pathology of Dropsy.—Dropsy consists in the accumulation of lymph, either in small lymph spaces in the tissues (œdema anasarca) or large serous cavities (ascites, pleural or pericardia effusions). The accumulation is caused by more lymph being poured out from the capillaries than can be removed by the lymphatics and veins.

The chief causes of dropsy are—(1) Diminished removal o lymph from the lymph spaces or serous cavities. This may b




FIG. 119.—Diagram of Ranvier's experiment on dropsy. The vena cava is ligatured, and in the le leg the trunk of the sciatic has been divided so that both the motor and vaso-motor nerves co tained in it are paralysed. On the right side the motor roots of the sciatic alone are divided a the vaso-motor left uninjured. There is thus motor paralysis on both sides, but vaso-mot paralysis and dropsy only on the left side.

due to (*a*) obstruction of the veins, or (*b*) of the lymphatics. (2 Increased exudation of lymph from the capillaries. This increase exudation may be due to (*a*) changes in the walls of the capillarie themselves rendering them more permeable. This appears to b the only condition which by itself can produce œdema. Ther are two others, however, which, although by themselves incapabl of producing œdema, yet, along with others, are of the utmos

importance; these are (*b*) a watery condition of the blood, and (*c*) vaso-motor paralysis. In many, indeed in most cases of dropsy, two or three of these factors are combined.

Obstruction to the veins, or lymphatics alone, will rarely cause dropsy, unless at the same time there is increased transudation from the capillaries. Thus Ranvier found that ligaturing the vena cava of a dog did not produce dropsy in the legs, the lymph being removed either by the collateral venous circulation or by the lymphatics. On dividing the sciatic nerve on one side, however, after ligature of the vena cava, dropsy appeared in the corresponding leg, while it remained absent from the other. He showed that the dropsy was caused by paralysis of the vaso-motor, and not of the motor fibres contained in the sciatic, by dividing the motor roots of the sciatic on the other side, leaving the vaso-motor roots uninjured. When this was done motor paralysis occurred equally in both legs, but dropsy only appeared in the one where the vaso-motor nerves had been divided (Fig. 119). This experiment shows what an important factor the loss of vascular tone is in the production of œdema, and we may legitimately infer from it that vascular tonics, by increasing the contractility of the vessels, will tend to prevent œdema, or remove it when it is already present.

A watery condition of the blood does not of itself increase the exudation of lymph, nor does it produce œdema, yet in cases of anæmia or chlorosis we very frequently find a tendency to œdema of the ankles, and experiments in Cohnheim's laboratory have shown that, although a watery condition of the blood alone causes no increased exudation of lymph so long as the vaso-motor nerves are intact, yet it does so to a very great extent when the vaso-motor nerves are paralysed.[1]

Alteration of the capillaries by inflammation causes increased exudation of lymph, and tends to produce a local œdema. This œdema is greatly increased if the vaso-motor nerves are paralysed, not only attaining a much greater extent, but appearing more quickly and lasting longer. I have already mentioned that, in experiments on artificial circulation, acids added to the circulating fluid not only caused dilatation of the vessels, but increased transudation through them, and tended to render the tissues œdematous. It is not improbable that some alterations of the blood-vessels of the living body which tend to render them more permeable may be connected with imperfect oxidation and the formation of sarco-lactic instead of carbonic acid.

Arsenic has this power of lessening oxidation,[2] and it seems not improbable that the tendency to produce œdema of the eyelids which it possesses may be due to this peculiar action.

---

[1] Jankowski, *Virchow's Archiv*, xciii. p. 259.
[2] Feitelberg, *Inaug. Diss.* Dorpat, 1883.

It is evident that whatever tends to increase oxidation will have an opposite effect, and will tend to prevent any excessive exudation from the capillaries. In cases of anæmia iron is therefore serviceable, and as the condition of the blood improves the tendency to œdema disappears.

What has just been said regarding the action of acids may seem to be in contradiction to the usually received opinion that the mineral acids act as vascular tonics. It is quite true that small doses of dilute acids, especially when given, as they usually are, along with bitters, frequently impart a feeling of strength and tone, whereas alkalies are frequently felt to be depressing, but in the case of both these classes of remedies this effect is probably not due to any direct action on the vessels themselves (*vide* Acids).

Cardiac Sedatives.

Cardiac sedatives are substances which lessen the force and frequency of the heart's action.

They are chiefly used, either for the purpose of lessening violent action or palpitation of the heart, or of rendering the pulse slower in febrile conditions, especially those consequent on local inflammation. It has already been mentioned that belladonna diminishes the sensibility of the heart to changes of pressure, and that sometimes it is useful in palpitation consequent on cardiac strain. Simple pressure over the cardiac region appears to have the power of lessening palpitation, so that when this occurs in consequence of any sudden emotion, there is a natural tendency to press the hand over the region of the heart. It is impossible to say whether the relief which such pressure certainly affords is simply mechanical, or is due to reflex action on the heart through the cutaneous nerves. Plasters applied to the cardiac region have a beneficial action upon palpitation similar to that of the hand, and one of the most commonly used and beneficial is belladonna plaster. In irritable-heart of soldiers Dr. Da Costa found digitalis better than any other remedy.[1]

In palpitation depending on indigestion, hydrocyanic acid is useful. In palpitation due to aortic disease, senega has been recommended. It is probable that its efficacy depends upon the diminished action of the cardiac ganglia and muscle which its active principle, saponine, produces.

An active circulation of blood is usually advantageous both for functional activity and for the repair of damage to an organ, but sometimes it may become excessive, and relief may be afforded by diminishing it (*vide* p. 342).

[1] *Amer. Journ. Med. Sci.*, Jan. 1871.

The chief cardiac sedatives employed for this purpose are:—

Aconite.
Veratrum viride.
Antimonial preparations.

It is questionable whether in extensive inflammation of internal organs cardiac sedatives are of much service or not. They seem, however, to give relief in the feverish condition which accompanies more limited inflammation, such as tonsillitis, otitis, &c. In such cases the tincture of aconite is best employed in very small doses (one drop) frequently repeated. The introduction of this method of using the drug in divided doses is due in great measure to Ringer, and it has the very great advantage that the desired effect can be produced with greater certainty and with less risk of an overdose being given.

Vascular Sedatives.

Vascular sedatives are substances which, by increasing the contraction of the vessels, lessen the flow of blood through them. They are chiefly used to lessen local inflammation or prevent hæmorrhage. One of the most powerful of all vascular sedatives is cold. For its use in local inflammation *vide* p. 343. It is not only a vascular but a cardiac sedative, and ice swallowed in considerable quantity will tend to lessen the action of the heart. It is therefore one of the means to which we chiefly trust in cases of hæmoptysis. In hæmatemesis it has the double action of lessening the activity of the heart, and of contracting the vessels in the stomach.

The remedies which are chiefly employed in addition to cold are:—

Digitalis.
Ergot.
Hamamelis.
Lead acetate.
Opium.

CHAPTER XII.

REMEDIES ACTING ON THE SURFACE OF THE BODY.

Irritants and Counter-irritants.

Irritants are substances which, when applied to the skin cause a greater or less degree of vascular excitement or inflammation. They are employed for the sake of their **local action** to produce increased circulation in the part to which they are applied, and thus to remove abnormal conditions already present in it.

When irritants are employed for the purpose of affecting reflexly a part **remote** from the seat of application they are named **Counter-irritants.**

Irritants are subdivided, according to the amount of effect produced, into rubefacients, vesicants, pustulants, and escharotics.

Rubefacients produce simply congestion and redness, which may be merely temporary, passing off in a few minutes, or may be more permanent, remaining for several days.

When more powerful, so as to cause exudation between the true skin and epidermis, giving rise to vesicles, they are called **vesicants,** or **epispastics.**

When they do not affect the whole skin alike, but do so unequally, and irritate isolated parts in it, such as the orifices of the sudoriferous glands, so powerfully as to give rise to pustules they are called **pustulants.**

When they destroy the tissues altogether, forming a slough they are called **caustics** or **escharotics.**

The difference between these sub-classes is chiefly one of degree, and not of kind. The weaker ones produce the higher degrees of action when applied for a long time, and the stronger ones produce the slighter kinds of action when applied for a short time.

It must be remembered that, although inflammation is usually associated with increased circulation, the two things are essentially different.

Inflammation is the injury to the tissue; the increased circulation is the attempt to repair it.

Increased circulation occurs wherever we have increas

functional activity, whether this be for the purpose of performing a normal function, as in glands during the process of secreting, and in muscles during contraction, or for the purpose of **repair.** When repair is going on slowly, the process may be frequently quickened by increasing the supply of blood to the part, and this is the reason for using friction, and liniments and blisters of various kinds, in cases of **chronic inflammation** in joints or in ulcers.

Sometimes irritation fails to cause absorption, from being too weak. In a case of rheumatic gout which I saw some years ago, irritating liniments had been applied for some time in vain, until, by mistake on the patient's part, so much iodine liniment was put on at once as to cause vesication over the whole back of the hand, when recovery began immediately.

In **acute inflammation,** however, the greatly increased circulation, along with the heightened sensibility of the sensory nerves in the inflamed part, causes much pain, and this is relieved when the tension of the blood in the inflamed part is lessened. We notice this very clearly when the finger is inflamed in consequence of a prick from a thorn, a bruise, or other injury. When it is allowed to hang by the side, the throbs of pain, coincident with every pulse-beat, become excruciating, while, if raised above the




FIG. 120.—Tracings from the radial artery at the wrist : *A* before and *B* after the application of a cloth dipped in cold water round the arm. (After Winternitz.)

head, so that the pressure of blood in the vessels is less, the pain becomes greatly diminished. The tension in the vessels may be relieved likewise by causing contraction of the arteries leading to the part by a cold compress around the arm (Fig. 120), or by dipping the finger in cold water; but relief is also afforded by a warm poultice applied to the finger. At first sight it seems strange that **heat** and **cold** should both relieve the pain, but a little consideration will show that they both relieve the tension in the vessels of the inflamed part. Cold does so by causing a reflex contraction of the afferent arteries, and thus diminishing the quantity of blood going to the inflamed part. Warmth, on the other hand, dilates the capillaries of the collateral circulation, and thus diverts the current away from the inflamed vessels.

The use of **counter-irritation** as a remedial measure depends on the fact that similar alterations to those produced by heat and cold on the finger may be produced on the circulation in internal organs reflexly through the nervous system.

When an **irritant** is applied to any part of the skin, it causes

a local dilatation of the vessels and redness of that part, but contraction of the vessels in other parts of the body. Probably this contraction takes place with the greatest force in certain organs having a definite nervous relation to that part of the surface




FIG. 121.—Diagram to show the effects of heat and cold in lessening the pain of inflammation. The diagram is supposed to represent the end of the finger. The small star indicates the point of irritation, e.g. a prick by a thorn. The line in the centre of each figure is intended to represent the nerve going to the injured part; and at the side of each figure is an artery and vein connected by a capillary network. In *a* the capillary network around the seat of irritation is seen to be much congested; the nerve-filaments are thus pressed upon and pain is occasioned. *b* represents the condition of the finger after the application of cold to the arm or hand. In consequence of the contraction of the afferent arteries the finger becomes anæmic; no pressure is exerted on the nervous filaments, and pain is alleviated. *c* represents the finger after it has been encased in a warm poultice; the capillary network at the surface of the finger is dilated and the blood is thus drawn away from the seat of irritation and the pain therefore relieved.

which is irritated. Zülzer found that when cantharides-collodion was painted repeatedly over the back of a rabbit for fourteen days the vessels underneath the skin, and the superficial layers of




FIG. 122.—Diagram to show congestion of the lung. The pulmonary vessels are shown dilated, and those of the thoracic wall contracted.

muscles, were congested. The deeper layers of the muscles, the thoracic wall, and even the lung itself, were much paler and more anæmic than those of the other side.

It is probable that a similar condition occurs in man, and that when we apply a blister to the side we, sometimes at least, cause contraction of the vessels in the pleura and lung below, and thus relieve pain in the chest in much the same way as when we apply cold to an inflamed finger. It has been supposed that the action of a poultice or blister was simply to draw away blood from the

inflamed part. We have seen that the poultice does this in the case of an inflamed finger, but in an inflamed lung or pleura the quantity which comes to the skin is insufficient to explain the relief. It is quite possible, however, that the vessels in the lung and pleura adjoining the inflamed district may be dilated by the application of a poultice or blister to the side, and thus relief is afforded in the same way as by the application of a poultice to the finger. It is not easy to say in which of these ways a poultice or




FIG. 123.—Diagram to explain the action of counter-irritation. A blister or other counter-irritant is shown applied to the chest-wall. The stimulus which it causes is transmitted up the afferent nerves to the vaso-motor centre; it is thence reflected down the vaso-motor nerves to the pulmonary vessels, causing them to contract, while it is reflected down vaso-dilating fibres to the vessels of the thoracic wall and probably of other parts of the body also, causing them to dilate, and thus lessening the pulmonary congestion by withdrawing blood from the lungs. (Compare with Fig. 122.)

blister acts in any particular case. Clinical experience seems to show that sometimes the blisters relieve acute inflammation by causing contraction of the afferent vessels (as represented in the accompanying diagram, Fig. 123) and thus lessening the tension in the vessels of the inflamed part. If the blister is **too near** to the inflamed part, it may increase instead of diminishing the congestion, and thus do **harm** instead of good.

As a matter of practice, the rule is usually insisted upon, that in a case of pericarditis, for instance, the blister should not be put immediately over the pericardium, but at some little distance from it.

Counter-irritation is not only used, however, as a means of lessening congestion and pain in acute inflammation, it is also employed with much advantage to cause the re-absorption of inflammatory products. The use of the increased circulation which a blister causes in a chronic ulcer is unquestionable, and the rapid absorption of the thickened margins of the ulcer is perceptible to the eye. A similar absorption appears to occur in deeper-seated organs, such as the lung, on the application of counter-irritation to the chest, and painting with iodine liniment is useful in promoting absorption of liquid effused into the pleural cavity or of the product of chronic inflammation of the lung. The mode in which the irritation acts is probably the same both in the chronic

ulcer and in the lung, i.e. by increasing the circulation through the part affected. Where the blister is applied, as in acute pericarditis, to lessen congestion, it is usually placed at a little distance from the inflamed part, but where we wish to increase absorption, as in consolidation of a part of the lung, we apply the counter-irritant directly over the consolidated part.

Rubefacients.

Mechanical, as friction.
Ammonia.—Solution of ammonia, compound camphor liniment.
Alcohol (prevented from evaporating by oil-silk or a watch-glass).
Arnica.
Cajeput oil.
Camphor.
Capsicum.
Chloroform (prevented from evaporating, like alcohol); chloroform liniment.
Ether (like chloroform).
Iodine and its preparations.—Iodide of cadmium, iodide of lead.
Menthol.
Mustard.
Oil of turpentine, of nutmeg, and many other volatile oils.

Vesicants.

Acetic acid (glacial).
Heat of:
Boiling water.
Corrigan's hammer.
Cantharides.—Solutions, plaster, cantharidin.
Euphorbium.
Mezereon.
Volatile oil of mustard.
Rhus toxicodendron.

Pustulants.

Croton oil.
Tartarated antimony.

Caustics.

Actual cautery.
Acids:—Acetic (glacial).
Carbolic.
Chromic.
Hydrochloric.
Lactic.
Nitric.
Osmic.
Sulphuric.
Alkalies:—
Lime.
London paste (p. 346).
Vienna paste (p. 346).
Potash.
Soda.
Ethylate of sodium.
Alum (burnt).
Antimony (chloride).
Arsenic.
Bromine.
Soluble compounds of the heavier metals; as:
Copper sulphate.
Mercuric chloride.
,, nitrate.
Silver nitrate.
Zinc chloride.
Zinc sulphate.

Rubefacients.— One of the simplest rubefacients is mere **friction.** This may be made either with the hand, or more effectually still, with a rough cloth or a flesh-brush. Friction also greatly aids the action of many of the slighter rubefacients.

Rubefacients may be used for their action upon the skin itself

o relieve itching. They may also be used for their effect on leeper-seated structures.

Friction, with firm pressure, is used in shampooing. Upward riction in the limbs will diminish the tension in dropsy, by emoving part of the fluid from them. It also aids the circulaion of the lymph, and by accelerating the passage of the prolucts of muscular waste from the muscles themselves into the eneral circulation, it removes to a great extent the sense of atigue after over-exertion (p. 131). When applied along the back t soothes conditions of nervous excitement, and tends to produce leep. Friction, along with stimulating liniments, applied to the oints after active inflammation has subsided in them, tends to emove the swelling and to restore their function.

Neuralgic pains are frequently relieved by the application of ubefacients such as ammonia, chloroform applied by a watchlass, or a mustard-plaster to the painful spot.

Conditions of nervous debility are sometimes benefited by mustard liniment applied over the spine, and a mustard-plaster o the nape of the neck is sometimes useful in nervous irritability vith sleeplessness. In addition to the action which the mustard as on the vessels, it produces a sharp pain, so that it is employed lso to rouse persons suffering from narcotic poisoning, or from oma.

Mustard-leaves or iodine liniment applied over consolidated arts of the lung tend to cause absorption of inflammatory roducts, and are used for this purpose in cases of effusion into he pleura or pericardium, of chronic consolidation remaining after n attack of pleurisy or pneumonia, or in commencing phthisis.

Vesicants.—Vesicants are employed locally in **chronic ulcers** nd to cause absorption of effusions into **joints,** or chronic hickening about them. When applied around the inflamed oints in acute rheumatism, they not only relieve the local affection, but appear to have a curative action on the general febrile condition.

In neuralgia, blisters over the painful point are useful, and sometimes, when neuralgia is in the side, or in the breast, it may e relieved by applying the blister over the corresponding part f the spine where there is usually a spot which is tender on pressure. In sciatica, the relief is often greater when the blister is applied to the heel, than over the nerve itself.

In neuralgia also it not unfrequently happens that a slight application of the actual cautery is more efficacious than a blister. The most convenient form of this is Paquelin's thermocautery.

In inflammation of the pericardium or pleura, a blister frequently relieves the pain, and it sometimes lessens or cuts short the inflammation. Applied over the epigastrium, blisters relieve vomiting arising from various causes.

In cerebral affections, such as obstinate headache, in menin-

gitis and hydrocephalus, blisters to the nape of the neck or under the mastoid process are useful.

Hysterical paralysis of the limbs sometimes yields to blisters locally applied; and hysterical aphonia is sometimes removed by a blister over the larynx.

Pustulants.—Pustulants are employed for the purpose of keeping up a continuous moderate irritation in chronic inflammations: tartar emetic ointment, and croton-oil liniment, seem sometimes to be of considerable advantage in chronic inflammation of joints or synovial membranes, in chronic bronchitis and in pleurisy; perhaps sometimes in phthisis. They have been used also as an application to the spine in paralysis and hysteria, and to the head in tubercular meningitis, and to the nape of the neck in chronic headache or giddiness. They were much employed formerly, but of late years iodine liniment or small blisters have to a great extent taken their place.

Caustics.—Caustics are used to destroy excrescences on the surface of the skin and mucous membranes: warts, condylomata or polypi; to destroy exuberant and unhealthy granulations in ulcers and fungating sores: thus, a slight touch with nitrate of silver, sulphate of copper, or with nitric acid, will sometimes cause the tissues in an unhealthy wound after an operation to become less exuberant, and take on a healthy healing action.

Caustics may be used to destroy malignant growths. Generally a surgical operation is preferable for this purpose, but sometimes patients have such a horror of the knife that they will not submit to an operation, and in such cases caustics are occasionally employed. For this purpose one of the following may be applied: Vienna paste consisting of caustic potash and caustic lime moistened with water, or London paste, which consists of caustic soda and lime moistened with alcohol. Sulphuric acid mixed with sawdust has sometimes also been used, but it is exceedingly painful. Arsenious acid made with various inert substances into a paste is not unfrequently employed with considerable success by charlatans, who sometimes succeed in removing cancerous growths by its application in apparently hopeless cases, but the risk attending its use is considerable.

Caustics are sometimes employed also to open abscesses, especially abscesses of the liver, if it is thought advisable to cause adhesions between the viscus and the abdominal wall before the abscess is opened, so as to avoid any risk of pus finding its way into the abdominal cavity. The substance usually employed for this purpose is caustic potash.

Caustics are also used to keep up chronic irritation, as in chronic headache or epilepsy, a wound being first made by the use of the caustic, and prevented from healing by the introduction of a foreign body into it, or by the continued application of some irritating ointment, such as savine ointment.

Caustics are also used as an application to the bites of venomous serpents, or of rabid dogs, in order to destroy the virus and prevent its general action on the organism. The weaker caustics are of no use for this purpose. I have seen a boy die of hydrophobia six weeks after he was bitten by a mad dog, although the wound had been thoroughly cauterised by nitrate of silver five minutes after the bite. In all cases the parts around the bite should be, if possible, excised and then cauterised with a red-hot iron, a ligature being, if possible, placed between the bitten part and the heart until the operation has been effected, so as to prevent any absorption of the virus.

Emollients and Demulcents.

Emollients are substances which soften and relax, while **Demulcents** are substances which protect and soothe the parts to which they are applied.

Many substances exercise both of these actions, and so no very sharp line of distinction is drawn between them. Emollients, however, are more generally spoken of in relation to their application to the skin, and demulcents to the mucous membranes.

Demulcents.	Emollients.
Bread.	Moist warmth—bathing with warm water, hot sponge, hot fomentations, steam.
Collodion.	Poultices made of substances which retain heat and moisture—bran, bread, figs, flour, linseed-meal, oatmeal, &c.
Cotton-wool (for external use only).	Gelatinous substances.
Figs.	Fats—almond-oil, glycerin, lard, linseed-oil, neat's-foot oil, olive-oil, spermaceti, suet, lanolin.
Fuller's earth.	Paraffin—petrolatum, vaseline, and unguentum petrolei.
Gelatine.	Soap and other liniments.
Iceland moss.	
Isinglass.	
Glycerin.	
Gum.	
Honey.	
Linseed.	
Linseed-tea.	
Marsh-mallows.	
Almond-oil.	
Olive-oil.	
Starch.	
White of egg.	

The Action of Demulcents is chiefly mechanical. They form a smooth, soft coating to an inflamed mucous membrane, or to a skin deprived of its epidermis, and they thus protect the surface from external irritation, and allow the process of repair

to go on. They are used externally in cases of irritating skin diseases, where the epidermis from one cause or another has been broken or removed, as by friction, exposure to cold, &c. Internally they are employed when the mucous membranes have been irritated, as, for example, in the after-treatment of cases of irritant poisoning.

Mucilaginous substances are also used to relieve pain and irritation in the throat, and to lessen the irritable cough which frequently depends on congestion of the pharynx and upper parts of the respiratory passages.

Such substances as figs, prunes, and even cabbage, are employed to protect the intestines from injury by hard and pointed substances which have been accidentally swallowed. They do this by leaving a bulky indigestible residue in which the pointed article becomes embedded, and thus passes along the intestine without lacerating it.

The Action of Emollients is to relieve the tension and pain in inflamed parts; **warmth** and **moisture** do this by dilating the collateral blood-vessels in the manner already described (p. 342). They also relax the tissues themselves and lessen the pressure upon the nerves of the part.

Fatty emollients soften the skin and thus render it softer and more flexible. These emollients also aid the immediate effect of friction upon the skin, enabling it to be applied with greater advantage, and to act on the more deeply-seated tissues, as, for example, in cases of stiffness in joints.

Therapeutic Uses.—Warmth and moisture are almost invariably used to relieve spasm and the pain attending it, as well as to relieve pain in all cases of inflammation, whether superficial or deep-seated, and they relieve so much that, with many people, the connection between pain and poultice has come to be a household word. When poultices are intended to act directly on the part to which they are applied, the linseed, bran, or bread should be applied to the skin with nothing between, or almost with only a thin piece of muslin, but when intended to act on deep-seated organs, a considerable thickness of flannel should be interposed, so that the heat may come gradually through, and allow an excessively hot poultice to be applied without burning the skin.

In cases of disease of the respiratory passages the warmth is usually applied by means of **inhalation.**

Fatty emollients, by softening the skin or mucous membranes, such as those of the lips, prevent them from cracking and are used by persons with a delicate skin to prevent cracks forming on exposure to cold.

They are also used to prevent friction between surfaces of skin constantly in contact, as between the nates and inner joints in children, and to prevent bed-sores.

Astringents.

These are substances which cause contraction of the tissues to which they are applied and lessen secretion from mucous membranes.

- Acids.
- Alcohol.
- Alum.
- Chalk and Lime.
- Salts of the heavier metals, e.g.—
  - Bismuth subnitrate, &c.
  - Cadmium sulphate.
  - Copper sulphate.
  - Ferric chloride.
  - Lead acetate.
  - Silver nitrate.
  - Zinc sulphate.
- Gallic acid.
- Tannic acid.
- Vegetable substances containing these acids, e.g.—
  - Catechu.
  - Galls.
  - Kino.
  - Oak-bark.
  - Uva-Ursi.
  - Arbutin.

Astringents are usually divided into local and remote.

Local astringents are those which affect the part to which they are applied. **Remote** are those which act on internal organs after their absorption into the blood.

With the exception of gallic acid and ergot they all **coagulate** or precipitate **albumen.** Dilute mineral acids do not coagulate albumen, but precipitate albuminous substances from the alkaline fluids in which they are naturally dissolved in the body.

When applied to a surface from which the epidermis has been removed, the other astringents combine with the albuminous juices which moisten this surface, as well as with the tissues themselves, and form a pellicle more or less thick and dense, which in some measure protects the structures beneath it from external irritation, at the same time that they cause the structures themselves to become smaller and more dense. On a mucous membrane they have a similar action, and they lessen its secretion. It was formerly supposed that their action was partly due to their causing the blood-vessels going to a part of the body to contract, thus lessening the supply of fluid to it, as well as to their effect on the tissues themselves. But experiment has shown that, while nitrate of silver and acetate of lead possess this power, perchloride of iron and alum do not, and that tannic and gallic acids actually dilate the vessels. The astringent action of these latter drugs must therefore be exerted upon the tissues. (Rossbach.)

Uses.—Astringents may be employed **locally** in various forms. In the solid form, as a powder, or in various prepara-

tions, such as lotions, ointments, plasters, glycerines, &c., they are applied, especially the metallic astringents, to wounds and ulcers for the purpose of reducing the size and increasing the firmness of exuberant granulations, as well as of protecting the surface by forming a pellicle over it. They are used to lessen congestion and diminish the secretion of the various mucous membranes—as a lotion to the eye and mouth ; as a gargle or a spray to the throat; in the form of an injection to the nose, urethra, and vagina; and of suppositories to the rectum. Administered internally, several astringents have a powerful effect in checking diarrhœa, and certain of them may have a local action upon the stomach and intestines.

The **remote** action of such astringents as acetate of lead and gallic acid, when absorbed into the blood, in lessening **hæmorrhage,** is made available in the treatment of hæmoptysis, hæmatemesis, hæmaturia, and loss of blood from other parts of the body.

Styptics.

Styptics are substances which arrest the flow of blood from broken or wounded surfaces or vessels. They may do this either by aiding the rapid formation of a coagulum which will plug up the wounded vessels, or by causing the vessels themselves to contract so much as to check the flow of blood out of them. They are closely connected with astringents, which, as we have already mentioned, nearly all coagulate albuminous substances.

Acids.
Actual cautery.
Alum.
Ferric chloride.
Tannin.
Lead acetate.

Collodion, Matico, Spider's-web, } acting mechanically.

Substances acting on the blood-vessels :—

Cold (Ice).
Digitalis.
Ergot.

Action.—Matico and cobwebs act **mechanically** in aiding the formation of a clot around the fibres. Collodion also acts mechanically by exerting pressure over the surface, and thus preventing the blood from issuing.

Alum, lead acetate, and ferric chloride cause **coagulation** of the blood.

Pressure to the surface, cold sponges or ice, cause the vessels to **contract,** and thus prevent the blood from running out of them in superficial hæmorrhage.

Lead acetate and gallic acid, when absorbed into the blood

ot only tend to lessen secretion from the mucous membranes, ut arrest hæmorrhage from internal organs. This is probably artly due to their effect in increasing the coagulability of the lood, and possibly partly also to their power of causing contraction of the arterioles. Ergot and digitalis also lessen or arrest æmorrhage, although they have little or no action on coagulation, and their action probably depends on their power to cause ontraction of the arterioles.

A dependent position increases the pressure of blood locally n the part, and thus tends to increase hæmorrhage. It is herefore advisable to keep the bleeding part as much raised as ossible.

Powerful action of the heart tends to increase the blood-ressure generally. In cases of severe hæmorrhage it is therefore of the greatest importance that the patient should keep **absolutely quiet**, and that all the food should be taken cold.

Cold to the surface is a powerful agent in checking internal as well as superficial hæmorrhage. It probably acts by causing eflex contraction of the vessels (compare Rossbach's experiments, p. 252). A cold key to the back of the neck and cold water to the nose are frequently useful in epistaxis, and ice-bags o the chest or epigastrium are useful in hæmoptysis and hæmaemesis. It is probable that other stimuli to the surface act on he vessels in a similar way, and probably this is the explanation f the fact that menorrhagia and metrorrhagia are sometimes successfully treated by placing a plug of cotton wool soaked in a mixture of vinegar and brandy in the vagina, or applying the same mixture either on cotton wool or on a napkin to the vulva.

The powerful action of hot water injected into the vagina and uterus in arresting *post partum* hæmorrhage (p. 455) is probably due partly to its causing a reflex contraction of the vessels and of the uterus itself, and probably also to its direct stimulating action on the muscular walls of the uterus.

CHAPTER XIII.

ACTION OF DRUGS ON THE DIGESTIVE SYSTEM.

ACTION OF DRUGS ON THE TEETH.

ALTHOUGH the hurry and bustle of modern life is apt to mak people forget it, mastication is a most important part of th digestive process. During early life the stomach and intestine may be able to digest imperfectly-masticated food, but as year advance they cease to do so, and imperfect mastication become a fruitful source of dyspepsia.

If the teeth are entirely or almost entirely gone, the perso may chew with his gums, but if they are only partially gone i frequently happens that those which remain oppose one anothe only sufficiently to prevent the gums from closing, while they d not help mastication.

The decay of teeth is chiefly due to the dentine being attacke by the acid products of the decomposition of food in the mouth This decomposition is to a great extent due to bacteria, an antiseptics are therefore useful in preventing decay.

By cleaning the teeth with a soft brush at night before goin to bed, particles of food sticking between them may be removed and thus its decomposition and consequent injurious action o the teeth may be avoided. Chalk is employed as a basis of mos dentifrices, as its mechanical action is sufficient to clean the teet without injuring their polish, and at the same time it neutralise any acid which may be present. Charcoal has also a usefu mechanical action greater than that of chalk, but it is more liabl to scratch the enamel.

The antiseptics which are usually employed to cleanse th teeth are borax, quinine, and carbolic acid. Dilute solutions permanganate of potassium are also very useful, but have a ver disagreeable taste. Where the gums are soft and spongy and ar apt to leave the fang of the tooth more or less exposed, vegetabl astringents, such as areca nut, catechu, kino, and rhatany ar useful. Mineral acids when given medicinally cause an unplea sant feeling of the teeth being on edge, and are also injurious t the teeth; they are therefore usually sucked up by means of glass tube or quill, instead of being simply swallowed. Whe used as gargles for the throat, their injurious action on the teet

ıay be to a considerable extent prevented by previously rubbing he teeth with oil, butter, or lard, and washing out the mouth or rushing the teeth with a weak solution of alkaline bicarbonate r soap. Soluble preparations of iron, especially persalts, are pt to stain the teeth, and they are therefore also given by means f a tube; alum appears also to have a very injurious action on he teeth; alum gargles should therefore not be employed for a ength of time together, and the same precautions should be used s with acid gargles.

When the gums have receded somewhat from the crown of he teeth, pain or a soreness is not unfrequently felt in the teeth, lthough no definite caries is present. This soreness appears to e due to the irritant action of acid secretions in the mouth upon he exposed fang, and it may be often to a great extent removed y washing the mouth out with a weak solution of bicarbonate of odium, or rubbing finely-powdered chalk or magnesia along the ums. When toothache occurs in consequence of caries, it may ometimes also be relieved by holding some brandy in the mouth, or y placing a small pledget of cotton-wool dipped in tincture or quid extract of opium with a little bicarbonate of sodium in the avity of the tooth. A pledget of cotton-wool dipped in creasote r oil of cloves is often used for a similar purpose, and one of the ıost effectual remedies is to dip a small pledget of cotton-wool ı pure carbolic acid liquefied by heat, and place it in the cavity f the tooth, taking care to cover it well with clean cotton-wool o as to prevent the carbolic acid coming in contact with the ongue or cheeks. Chlorate of potassium often lessens toothache due to inflammation of a large open carious cavity. Phosphate f calcium frequently relieves toothache occurring during pregancy or lactation and is sometimes useful also in toothache nconnected with either of these conditions.

ACTION OF DRUGS ON THE SALIVARY GLANDS.

Sialagogues.

These are remedies which **increase** the secretion of **saliva.**

Anything which is chewed, or even turned about in the mouth, uch as a pebble, will increase the secretion of saliva; but the hief sialagogues have a stimulating action of their own.

Action.—In the secretion of saliva there are **two factors**—rst, the activity of the **secreting cells**; secondly, the supply of ew material to them, from which they may manufacture the ecretion. This depends on the **circulation.**

Secreting cells do not derive the new material from which hey form the secretion directly from the blood. They obtain from the lymph which fills the adjacent lymph-spaces. Hence hey may continue to secrete for a short while after the circula-

tion has ceased, as in the sweat-glands of an amputated limb, or in the salivary glands after the head of the animal has been separated from the body. But the supply of lymph soon becomes exhausted unless a supply of fresh lymph in the spaces is kept up by exudation from the blood-vessels. We therefore find that abundant secretion is usually, though not invariably, associated with an abundant blood-supply. If the flow of blood is not rapid the secretion must soon diminish or come to a stop, for, although it may occur rapidly at first, the lymph which has accumulated in the lymph-spaces supplying the cells soon becomes exhausted.




FIG. 124.—Diagram representing the general relation of nerves to the secreting cells and vessels of a gland. For the sake of simplicity only one afferent nerve and one nerve-centre and one set of secreting and vascular nerves are here represented.

In the salivary gland, when the secretion is going on, the arteries usually dilate, and the blood flows rapidly through them. The submaxillary gland, in which secretion has been best studied, appears to receive four kinds of nerves—two sets being contained in the chorda tympani and two in the sympathetic.

The chorda contains some fibres which act on the blood-vessels, causing them to dilate and allow the blood to flow freely through the gland, and others which stimulate the cells of the gland to secrete a thin, watery saliva. These two kinds are spoken of as vaso-dilating and secreting, or secretory, fibres (Fig. 124).

At present the usually accepted theory is that the secretory nerves have a direct influence upon the tissue-change in the cells of the gland. During secretion the granules in the cell decrease in number and generally in size, the hyaline substance increases and the network within the cell grows.[1] It is not at all improbable, however, that in addition to their action upon secreting nerves some drugs influence the amount of fluid poured out from the vessels. For if we inject a solution of quinine into the duct of the gland and thus destroy its secreting power, and afterward irritate the chorda tympani, the lymph poured out from the blood-vessels will accumulate in the gland and render it œdema-

[1] Langley, *Proc. Camb. Phil. Soc.*, Nov. 12, 1883.

ous; but if an animal be poisoned with atropine the gland does not become œdematous when the chorda tympani is stimulated—although the blood-vessels going to it are dilated and its power of secretion is completely destroyed. We might suppose that the gland did not become œdematous because the lymph, although not used up by the gland, had been carried away by the cervical lymphatics. But this is not the case, for Heidenhain has found that the flow of cervical lymph is not increased under these circumstances.

It appears to me that the circumstance can hardly be explained otherwise than by supposing that atropine not only paralyses the secreting fibres of the chorda, but acts upon the vessels in such a manner as to greatly diminish or prevent the exudation which would usually take place from them into the lymph-spaces on irritation of the chorda.

The sympathetic contains some fibres which cause the vessels of the gland to contract and the blood to flow slowly through it, and others which stimulate the cells to secrete a thick and viscid saliva.

Besides the ordinary secretion of saliva regulated by the action of the nerves, there is a secretion which is usually termed paralytic, because it occurs, not after irritation, but after paralysis of the nerves going to the salivary gland. It occurs in the sub-




FIG. 125.—Diagram to show the afferent nerves by which the secretion of saliva may be reflexly excited.

maxillary gland, when its nerves have either been paralysed by the injection of small doses of curare into the artery going to the gland, or by a section of the combined lingual nerve and chorda tympani, or extirpation of the submaxillary ganglion. It is not improbable that morphine also, like curare, produces it, because

in moderate doses it causes dryness of the mouth, but in enormous doses causes excessive salivation.

The secretion of saliva may be stimulated by the **direct** action of drugs upon secreting nerves in the gland itself, or **reflexly** through the sensory nerves of the mouth, stomach, eye, or nose (Fig. 125). The mere smell, or sight, of appetising food, causes secretion of saliva, which is probably due to the nerves of smell and taste acting through the brain upon the medulla. The **brain**, when excited by mere recollection, may also stimulate the secretion of saliva.

Increased salivation is a common accompaniment of sickness or nausea. The afferent nerve here appears to be the gastric branches of the vagus.

The **nerve-centre** which regulates the secretion of the thin chorda-saliva is probably the nucleus of the seventh nerve situated in the medulla oblongata.

Efferent fibres pass out along the chorda tympani and reach the gland, some directly, and some after passing through the submaxillary ganglion.

The **afferent** fibres, which convey stimuli from the mouth to the medulla are contained in the lingual branch of the fifth, and the glosso-pharyngeal nerves. Those which convey stimuli from the stomach, and excite the salivation which accompanies nausea, are contained in the vagus. The salivary centre may also be stimulated by impulses sent down from the brain, and the nerves of sight and smell may act as afferent nerves to the salivary centre indirectly through the brain (Fig. 125).[1]

Besides the nerve-centre in the medulla oblongata there are **subsidiary** nerve-centres. These are the submaxillary ganglion and small ganglionic masses in the submaxillary gland itself.

Sialagogues have been divided into two **classes**: 1st, **topical**, or direct; and 2nd, specific, **remote**, or indirect. The names *direct* and *indirect* are complete misnomers, and ought not to be used; inasmuch as the so-called *direct* sialagogues are those which act *directly* on the *mouth*, but do *not* act *directly* on the substance of the *gland*, or on the nervous structures contained within it or immediately connected with it.

Sialagogues are better divided according to their mode of action into **reflex** sialagogues, **specific** sialagogues, and those which act both reflexly and specifically, and may be called **mixed** sialagogues.

---

[1] The nasal branches of the fifth nerve probably also act as afferent nerves for the salivary secretion, for I have noticed that on dipping the tip of the nose into hot water containing a little compound tincture of benzoin, salivation occurred, ceased when the nose was withdrawn, and again occurred regularly whenever the nose was again introduced into the mixture. The mere inhalation of the vapour had no effect.

Reflex Sialagogues.	Specific Sialagogues.
Acids, mineral and vegetable.	Jaborandi. (Pilocarpine.)
Acid salts.	Muscarine.
Alkalies.	Physostigma. (Physostigmine.)
Ethereal bodies—	Tobacco.
Ether.	Compounds of Iodine.
Chloroform, &c.	Mercury and its compounds.
Pungent substances—	
Mustard.	
Horseradish.	
Ginger.	
Pyrethrum.	
Mezereon.	
Tobacco, &c.	
Rhubarb.	
Cubebs.	
Nauseants.	
Tartar emetic, &c.	

Reflex Sialagogues.—Acids, ether, ginger, horseradish, mezereon, mustard, pyrethrum and rhubarb, all produce salivation by stimulating the salivary glands reflexly through the nerves of the mouth.

The effect produced by reflex or topical sialagogues is not the same for each. Ether and dilute acids produce a thin, watery saliva, but alkalies cause the secretion of a thicker and more viscid saliva: the former appearing to affect chiefly the chorda tympani, and the latter the sympathetic.

Nauseants, such as tartar emetic, stimulate the glands reflexly through the vagus.

Mixed Sialagogues.—Mercury probably acts partly upon the gland structures and partly reflexly through the nerves of the mouth. Tobacco, when smoked or chewed, probably acts both reflexly and specifically. Iodide of potassium may act partially as a reflex sialagogue, for it is secreted in the saliva, and it therefore comes to be present in the mouth more or less persistently. It is probable, however, that it acts also upon the gland-structures, though it has not been determined whether the secreting cells or the nerves are chiefly affected.

Specific Sialagogues.—The **peripheral ends** of the secreting nerves in the gland itself are stimulated by pilocarpine or jaborandi, muscarine, nicotine and physostigmine, so that secretion is induced by the injection of these substances into the blood even after all the nerves going to the gland have been cut.

In large doses these substances paralyse the ends of the secreting nerves, so that irritation of the chorda tympani will no longer cause secretion. Physostigmine and nicotine, besides acting on the peripheral terminations of the secretory nerves,

stimulate the **central ends** of those nerves so that section of the chorda tympani greatly lessens the secretion which these substances cause, although it may still persist from the effect of the drug upon the peripheral terminations.

The peripheral action of physostigmine and nicotine is, however, much less marked than that of muscarine and pilocarpine, so that the secretion caused by the two former after the nerves have been divided is very much less than that produced by the latter.

Physostigmine acts also on the **sympathetic nerves**, producing contraction of the vessels at the same time that it is stimulating the secreting centre in the medulla. In consequence of this double action, secretion is rapid at first; it, however, diminishes very quickly or ceases entirely, the circulation being so much lessened by the contraction of the vessels that the glands do not get sufficient supply of new material to go on secreting.

Excretion by the Saliva.

Iodide of potassium is very quickly excreted by the kidneys so that the great bulk of it passes out of the body in a short time after it has been taken. But a little of it is retained very persistently for a length of time. There may be more than one reason for this. It is possible that it becomes combined with albuminous matters of the blood and tissues, and this combination being only slowly broken up, the elimination of the drug continues for a length of time. Another reason appears to be that it is excreted even more readily by the salivary glands than by the urine. The saliva in which it is contained is swallowed, the iodide is again absorbed from the stomach and carried by the circulation to the salivary glands. It thus goes on in a continual round from mouth to stomach and from stomach to mouth (Fig. 126). Iodide of iron, and probably other iodides, are eliminated by the saliva in the same way. Iodide of iron occurs in the saliva either when injected into the artery of the gland or when absorbed from the stomach. When lactate of iron and iodide of potassium are introduced simultaneously, or at a short interval after each other, into the stomach, so that iodide of iron is formed there by their combination, iodide of iron is found in the saliva.[1] But if they are injected separately into the blood iodide of potassium alone without any iron appears in the saliva. Iodine probably causes other substances besides potassium and iron to appear in the saliva when they are combined with it. It probably does so to quinine, for when iodide of potassium and quinine are given together in a mixture, patients frequently

[1] Bernard, *Physiologie Expérimentale*, tom. ii. p. 99.

complain of a very persistent bitter taste in the mouth much more marked than when the quinine is given in simple solution with acid.




FIG. 126.—Diagram of the gastro-salivary circulation.

Uses.— Saliva is useful in keeping the mouth moist, and thus facilitating mastication, solution, deglutition, and the movement of the tongue in speaking. By moistening the fauces, it also prevents or lessens thirst. A pebble placed under the tongue, or masticated, will keep up a slight flow of saliva, and may be useful for these purposes. Where this is insufficient, dilute acids are employed. As the flow of blood to the glands is greatly increased through secretion, sialagogues have been used as derivatives to lessen inflammation, congestion, and pain, in other parts of the head, as in toothache, earache, and inflammation of the ear, nose, or scalp.

Saliva has also a digestive action on starch, and increase of the flow may be advantageous in imperfect digestion of this substance. When swallowed, the saliva stimulates the secretion of gastric juice, and increased salivary secretion therefore tends to aid the gastric digestion of proteids. To obtain this object it is best to chew a piece of ginger, pellitory, or rhubarb.

Refrigerants.

Refrigerants are remedies which allay thirst, and give a feeling of coolness.

There appear to be two kinds of thirst: one of which is general, the other of which is local. **Local thirst** is occasioned by dryness of the mouth and fauces. It may be quenched by washing the mouth and gargling the throat with water, although none of it be swallowed, or by anything which will increase the flow of saliva, and thus keep the mouth and fauces moist. Thus, a pebble under the tongue, or chewed, will lessen thirst by increasing the secretion of saliva; and acids, both mineral and vegetable, as well as effervescing drinks containing carbonic acid and the juices of fruits, which contain either free vegetable acid or acid salts, acetates and tartrates, have a similar effect. When the secretion from the mouth and throat is very scanty, it is dried up by the passage of air to and fro in the process of respiration. The evaporation thus occasioned may be lessened, and the feeling of thirst diminished by the use of mucilaginous substances, which will form a thin coating over the mucous membrane of the mouth and pharynx. Thus, the addition of oatmeal to water will increase its power to quench thirst, and a very little milk added to water has a similar effect.

General thirst depends upon the condition of the organism generally, which appears to be due either to deficiency of water or excess of soluble and especially saline substances in the circulation.

General thirst is very often accompanied by local thirst, and may be partially alleviated by the means already described, but cannot be removed excepting by the introduction of water into the organism, or removal from it of the saline or other substances which are present in excess, or by lessening the excitability of that part of the nervous system by which the sensation of thirst is perceived.

This part of the nervous system, or thirst centre as Nothnagel calls it, is probably situated, according to him, in the occipital lobes of the brain, and it is possible that it may be irritated directly by mechanical injury, or by the condition of the blood circulating in it, as well as reflexly from mucous membranes, such as that of the mouth and throat, and possibly also from the kidneys. Its excitability is lessened by opium, and this may be used to diminish thirst in cases where other remedies fail to relieve.

Anti-sialics.

Anti-sialics are substances which **lessen the salivary secretion.** They may do this:

First, by removing the stimulus to secretion.

Second, by lessening the excitability of the efferent nerves or reflex centres.

Third, by paralysing the efferent nerves, such as the chorda tympani.

Fourth, by acting on the circulation through the gland.

Fifth, by acting on the gland-structures themselves.

Borax and chlorate of potassium are useful in the first of these ways by inducing a healthy condition of the mucous membrane of the mouth, and thus lessening the irritation which gives rise to salivation; opium and morphine diminish the reflex excitability of the nerve-centre, and are thus powerful anti-sialics.

Physostigma in large doses greatly lessens the supply of blood to the gland, and thus diminishes its secretion, and quinine, hydrochloric acid, and alkalies injected directly into the duct of the gland arrest secretion by affecting the secretory cells themselves. These latter drugs, however, cannot be used as anti-sialics.

The most powerful of all anti-sialics is, however, atropine, which paralyses the peripheral terminations of secreting nerves. It does not affect the vaso-dilating nerves, so that in an animal poisoned by atropine electrical stimulation of the chorda tympani will cause dilatation of the vessels and a free flow of blood through the gland as usual, but not a drop of saliva will be secreted. That this absence of secretion is due to paralysis of secretory nerves and not of the secreting cells appears to be shown by the fact that at the time when the power of the chorda to induce secretion is completely paralysed, stimulation of the sympathetic will still induce secretion.

Very large doses of atropine, however, paralyse the secreting power of the sympathetic in the cat, although this has not been noticed in the dog.

The paralysing action of atropine can be counteracted by physostigmine. This is shown by poisoning an animal with atropine, and then injecting physostigmine into the gland of one side through the submental artery. It is then found that irritation of the chorda causes salivation in the gland which has received physostigmine, while it causes no secretion in the other.

Iodide of ethyl-strychnine and cicutine have an action like that of atropine on the secreting and not on the vaso-dilating fibres of the chorda tympani.[1]

ACTION OF DRUGS ON THE STOMACH.

Gastric Tonics.

These are substances which increase the appetite and aid gastric digestion.

From observations made on the stomach in persons or animals

[1] Jolyet, *Gaz. Méd. de Paris*, 1877.

where a gastric fistula has been present, it has been found that in the normal condition, when the stomach is empty and quiet, the mucous membrane is of a pale rose colour. When stimulated mechanically, by rubbing it gently with a feather or glass rod, the mucous membrane becomes redder, and such abundant secretion of gastric juice occurs that it runs down in drops along the walls of the stomach.

When the irritation is greater—as, for example, when the mucous membrane is rubbed roughly instead of gently—an opposite effect is produced. The vessels then contract, the mucous membrane becomes pale, and the secretion of gastric juice stops, secretion of mucus commences, and if the irritation be carried still further, vomiting occurs.

Almost all substances which, when applied to the skin, act as irritants, as arsenic and salts of copper, silver, or zinc, and those also which, without irritating the skin, irritate the nerves of taste




FIG. 127.—Diagram to illustrate the supposed nervous connections of the stomach. A gentle stimul applied to the walls of the stomach is transmitted by the afferent nerves, A, to a nerve-cent B, and thence along the vaso-dilating nerves, C, and the secreting nerves, D, to the vessels of t mucous membrane and the cells of the gastric follicles. A stronger stimulus is transmitted to the nerve-centre, E, and thence along the vaso-constricting fibres, F, and the secreting fibr D, of the mucous follicles. A still stronger stimulus is transmitted to H, and thence along t motor nerves to the abdominal walls, K K, causing them to contract and produce retching vomiting.

as bitters, produce a feeling of appetite in the stomach, but the only do this in certain conditions of the stomach, and in certai quantities. The appetite appears to be associated with gent stimulation of the gastric walls; stronger stimulation destro

he appetite, still greater irritation causes nausea and, lastly, omiting.

In cases of atonic dyspepsia, where the stomach is below par, s, for instance, in anæmia and debility, slight stimulants or irri- ants produce appetite.

In such cases, where the tongue is usually smooth and flabby, itters and metallic salts are useful. But when the stomach is lready too irritable, and the tongue is red with enlarged papillæ, uch substances are likely to irritate still more, and thus, instead f increasing the appetite, to diminish it, and produce nausea. he increased irritability of the stomach which precedes a bilious ttack is often signalised by an unusually good appetite, which ontinues during the meal, so that food is eaten with relish. A till greater irritability is characterised by a great appetite before meals, which disappears, giving place to anorexia as soon as a ew mouthfuls have been swallowed, and the gastric irritation eightened by the increased circulation consequent on the intro- luction of the food. In such cases, bitters are likely to do harm, nd gastric sedatives, such as bismuth, are required.

The stomach has not merely to receive food, it has to digest t, and in the process of digestion there are **three factors**: 1st, **secretion** of the gastric juice which is to render the food capable f absorption and of assimilation; 2ndly, **movements** of the tomach to break up the food and mix it thoroughly with the olvent juice; and 3rdly, **absorption** of the products of digestion.

Action of Drugs on Secretion in the Stomach.

The **secretion** of the gastric juice is stimulated by gentle mechanical and chemical irritation, as by dilute alkalies and alcohol.

The name of peptogens is given to substances which increase the gastric secretions. Schiff has examined these, and states the most important of them to be dextrine (toasted bread), soups, peptones, &c.[1]

In order to obtain gentle mechanical stimulation, it is often advisable to make patients who are suffering from atonic dyspepsia commence their meals, and especially their breakfast, with solids, instead of commencing with a large draught of liquid.

Dilute alkalies given before meals increase the secretion of gastric juice; so much so, that the alkali is not only rapidly neutralised, but a large amount of acid gastric juice remains over.

The alkaline saliva has a powerful stimulant action on the

[1] Roberts, *Digestive Ferments*.

secretion of gastric juice, and as its quantity is much increased both by savoury food and by the movements of mastication, it is important that the food should not only be well cooked, but slowly and perfectly masticated. Alcohol is one of the most powerful stimulants that we know, and is probably surpassed only by ether. In persons suffering from weak digestion, therefore, a little dilute alcohol with meals is sometimes very beneficial.

Thorough **mastication** is also of the greatest importance in ensuring perfect digestion, inasmuch as the gastric juice penetrates with difficulty, and only slowly dissolves the masses of albuminous matter, while it would digest them very quickly if they were thoroughly broken up.

In children and young people, the stomach may be able to do more than its fair share of work, but it cannot do this in persons above middle age, and in them, imperfect mastication, either from deficient or decayed teeth, or from the habit of eating quickly, is one of the most common causes of dyspepsia.

When the stomach is too much debilitated to secrete a sufficiency of gastric juice, even when stimulated, as in the weakness consequent upon acute disease, general debility, or old age, we may supply **artificially** the **digestive substances** in the form of acids and of pepsin. Acids should be given for this purpose immediately after meals, or two hours after meals. Pepsin should be given either with, or immediately after, those meals which contain albuminous substances. As pepsin has no action on farinaceous food or salts, it is of no use to give it after meals containing these only.

Pancreatin, given two hours after meals, along with a little bicarbonate of sodium, appears, in some cases, to complete digestion, and to give great relief and comfort. When given before meals it is not of much service, since it is rendered inactive by the gastric juice.

Action of Bitters.—There can be no doubt whatever that infusions of vegetable bitter substances are exceedingly useful in dyspepsia. They not only increase the appetite so that more food is taken by the patient, but they really appear to assist digestion and prevent discomfort and flatulence. Their beneficial action is usually supposed to be due to their causing an increased secretion of digestive juices and having an antiseptic action on the contents of the stomach and intestine, thus preventing decomposition and flatulence. This explanation has recently been contradicted and experiments with a number of bitter substances appear to show that they tend rather to assist than to prevent fermentation and putrefaction, and to lessen the digestive power of the gastric and pancreatic juices. When given in small quantities to animals they cause a slight increase of the gastric juice. They have no action on the secretion of the pancreas; some of them increase slightly the secretion of bile, but not more than could be accounted

or by the water in which they are dissolved. Extract of absinthe ppears to increase tissue-change, so that more nitrogen is exreted both in the urine and fæces, while extract of quassia lessens issue-change by diminishing the amount of food absorbed from he intestine. These experiments would appear to show that itters instead of being useful are injurious, but the evidence of linical experience in regard to their utility is so strong that it s evident either that the experiments have been imperfectly onducted, or that we must look to some other organ than the tomach for an explanation of the beneficial action of bitters in yspepsia. I have just mentioned that the condition of the liver s one of the most important factors in digestion, and this organ ppears to be specially acted upon by a number of bodies belongng to the aromatic series (p. 403). As a great number of the egetable bitters belong to this series, it is possible that their eneficial action in dyspepsia may be due to changes which they nduce in the liver (p. 368) rather than in the stomach.

Action of Drugs on the Movements of the Stomach.

Digestion is greatly aided by the **movements** of the stomach, hich assist it by breaking up the food and mixing it thoroughly ith the gastric juice. When these are deficient, it is probable hat they are stimulated by nux vomica, or strychnine, and also y bitters.

A number of experiments have lately been made by Schütz[1] n the influence of drugs upon the movements of the stomach. These experiments are interesting as showing an analogy between he action of drugs on the stomach and other organs, such as the eart; but the doses applied were so large that the effects are ot to be considered the same as those arising from medicinal oses. These experiments were made by observing the movements of the viscus, after removing it from the body and placing t in a moist chamber. Various drugs were administered to ogs; and after the symptoms of poisoning became well-marked, he animals were killed, and the movements of their stomachs n the moist chamber were compared with those of normal animals.

The movements of the isolated stomach depend upon:

(*a*) The muscular fibres contained in its walls.

(*b*) The motor nerve-endings by which the muscular fibres are excited to action.

(*c*) The ganglionic cells of Auerbach's plexus, by which the rhythmical movements of the organ are maintained.

---

[1] *Arch. f. exp. Path. u. Pharm.*, xxi., p. 341.

(*d*) The sensory nerves, by which those ganglia may be reflexly excited.

The occurrence of spontaneous movements in the stomach shows that both the ganglia and muscular fibres retain their functional power. This is shown also by the occurrence of reflex contractions, when the stomach is distended by inflation and by the production of extensive undulating contractions on local irritation by a weak electrical stimulus. As the stomach dies, the nervous apparatus loses its irritability before the muscles, so that spontaneous movements cease, reflex contraction no longer occurs on inflation, and the strength of electrical stimuli requires to be greatly increased in order to produce undulatory movements extending beyond the part actually stimulated.

When the excitability of the nervous apparatus is quite gone, that of the muscular fibres still remains. Electrical stimuli cause localised contractions corresponding to the bundles of muscular fibres directly excited by the current.

It is evident that this result will be nearly the same if the ganglia themselves are paralysed, or if the motor nerve-fibres through which they act on the muscular fibres, are paralysed. At present, these actions have not been distinguished experimentally in the stomach, and therefore conclusions regarding the mode of action of some drugs are based to some extent upon analogy. Thus, ether and atropine both produce the effect mentioned above; but we know that ether tends to act on nerve-centres, such as those of the brain and spinal cord, while atropine tends to paralyse peripheral nerves ending in involuntary muscular fibre. The conclusion is that in the stomach also the effects of ether are due to its action on the ganglionic cells, while those of atropine are due to its action on motor nerves.

When the muscular fibres are paralysed as well as the nerves, electrical stimuli cause no contractions at all, or local contractions, which are more or less feeble according to the completeness of the paralysis.

The results of Schütz's experiments are as follows :—

Muscular irritability is increased, so that finally general persistent contraction of the stomach occurs, by :—

Physostigmine.	Scillain.
Digitalin.	Helleborein.

Motor nerve-endings in the stomach are

Excited by	Paralysed by
Muscarine.	Atropine.

The excitation by muscarine is shown by general contraction of the stomach. The symptoms of paralysis by atropine have been already discussed.

Automatic nerve-centres in the stomach are **excited**, so that he spontaneous movements become brisker and assume a character differing from the normal—

Strongly by—	Less marked by—
Emetine.	Strychnine.
Tartar emetic.	Caffeine.
Apomorphine.	Veratrine.
	Barium chloride.
	Nicotine, Pilocarpine } in small doses.
	Cocaine (?) [1]

utomatic nerve-centres are partially **paralysed**, so that the ovements are weakened, though not completely abolished, by—

Chloral.	Arsenic.
Urethane.	Nicotine, Pilocarpine } in large doses.
Morphine.	
Pyrophosphate of zinc.	

The whole nervous mechanism of the stomach is paralysed by xposure to the vapour of

Chloroform. Ether.

This paralysis is transient, and only lasts during exposure. The dministration of chloroform or ether to animals so as to pro-




FIG. 128.—Action of tartar emetic on the stomach in producing active contraction of an antiperistaltic character. The dotted line shows the shape of the stomach at rest.

duce ordinary anæsthesia seems to have no action on the movements of the stomach. It must be borne in mind that while exposure to the vapour of ether or chloroform may paralyse the stomach, and that while this action is unimportant, as it may occur from an overdose of these substances, smaller doses probably increase the movements of the stomach and act as carminatives.


[1] Cocaine at first causes greatly increased movement of the stomach, but its subsequent efforts are similar to those of atropine.

Absorption from the Stomach.

We know at present very little regarding the effect of drugs in stimulating **absorption** from the stomach, but it is probable that this is very greatly influenced by the condition of other organs.

All the processes which go on in the stomach—secretion, peristaltic action and absorption—are much influenced by the condition of the circulation.

All the blood which circulates in the stomach has to pass through the liver before it gets into the general circulation



RECTUM AND HÆMORRHOIDAL PLEXUS.

FIG. 129.—Diagram of the veins forming part of the portal circulation. The pancreatic and splenic veins, although most important, have been omitted for the sake of clearness.

(Fig. 129), and thus the condition of the stomach is necessarily much modified by the condition of the liver. If there is any obstruction to the free flow of blood through the liver, the circulation in the stomach will necessarily be impeded, and absorption probably diminished.

Not only the blood from the stomach, but that from the ntestines also, passes through the liver, and we may naturally xpect that the liver itself will be influenced by the condition of he blood which passes to it from the intestinal canal.

In Dr. Beaumont's observations on Alexis St. Martin, in whom gastric fistula existed, he found that after the stomach had een deranged by various articles of food, including fat pork, there as distress in the stomach, headache, costiveness, and a coated ongue. In the stomach there were numerous white and pustular-ooking spots. Half a dozen calomel pills produced catharsis, emoved the symptoms, and restored the mucous membrane of he stomach to its normal condition. Whether this effect was ue to the action of the pills on the liver, or on the intestines, e cannot perhaps positively say, but at all events the improve-ent was readily evident to the observer's eye.

Purgatives and **Cholagogues** may thus act as **indirect astric tonics**,[1] and the effect of bitters (p. 364) may be due to heir action on the liver.

Absorption from the stomach is probably also much influenced y the condition of the nervous system. Bouley found that when he vagi were divided in a horse, strychnine no longer produced oisoning, the reason being that the absorption took place so lowly after a division of the nerves that the poison was excreted s fast as it was absorbed. The retarded absorption, however, e considers to be due, not to any alteration in the absorptive ower of the stomach itself, but to diminished movement in its alls, so that its contents are not so quickly poured out into the ntestine. Absorption normally goes on more slowly from the tomach than from the intestine, and so while the poison re-ains in the stomach it is not absorbed quickly enough to cause oisoning.

Antacids.

Antacids are remedies employed to lessen or counteract cidity. The excessive acidity for which antacids are given may e present in the stomach, intestines, or urine.

Antacids are divided into **direct** and **indirect** or remote. Direct antacids lessen the acidity in the stomach, to which they re directly applied. Remote antacids lessen the acidity of the rine. Some substances have both actions, such as potash and oda, or the carbonates and bi-carbonates. Other substances, uch as the citrates, tartrates, and acetates of these bases, have o power to lessen acidity in the stomach, but, after absorption nto the blood, they appear to undergo combustion, and become onverted into carbonates. In this form they are excreted in the rine, and lessen its acidity.

[1] Beaumont, *Physiology of Digestion*, Burlington, 1847, p. 118.

Ammonia and its carbonate are direct antacids, but not r mote antacids. They lessen acidity in the stomach or intestine but after absorption they undergo change, and are eliminated i the form of urea, and, according to some, of nitric acid, so th they do not lessen the acidity of the urine.

Direct Antacids.—Liquor potassæ, potassium carbonat potassium bi-carbonate, liquor sodæ, sodium carbonate, sodium l carbonate, liquor lithiæ, lithium carbonate, lithium bi-carbonat magnesia, magnesium carbonate, magnesium bi-carbonate, lim water, saccharine solution of lime, chalk.

Direct but not Remote Antacids.—Ammonium carbonat aromatic spirit of ammonia.

Remote Antacids.—Potassium acetate, potassium citra potassium tartrate, potassium bi-tartrate, sodium acetate, sodiu citrate, tartarated soda, lithium citrate.

Emetics.

These are remedies which **produce vomiting.**

Action.—The act of vomiting consists in compression of t stomach by the simultaneous spasmodic contraction of the d phragm and abdominal muscles, while at the same time rela tion of its cardiac orifice is produced by contraction of the fib which radiate out from the lower end of the œsophagus along gastric walls. By their contraction these fibres draw the stoma up towards the diaphragm and pull the walls of the œsopha apart at its lower end so as to open the cardia. When the card orifice dilates at the same moment that the stomach is compres between the diaphragm and the abdominal muscles, its conte are expelled and **vomiting** occurs; but when the compress of the stomach and dilatation of the cardiac orifice do not t place simultaneously, the contents of the stomach are retai and the efforts are then termed **retching.**

The **nerve-centre** which regulates the movements of vomit is situated in the medulla oblongata. The movements of vo ing are modified respiratory actions, and the respiratory ce appears to be closely connected with the vomiting centre. deed some groups of ganglion cells probably take part both respiration and vomiting, or in other words form part of both respiratory and vomiting centres (Fig. 80, p. 235).

The reason for this supposition is not merely that the m ments of vomiting consist of modified respiratory moveme but that drugs which cause vomiting also increase the respira activity. Emetics usually quicken the respiration consider before they produce vomiting, and if injected into the veins not only quicken the respiration, but prevent the conditio apnœa being produced by vigorous artificial respiration.

On the other hand, the desire to vomit may be lessene

ome extent by taking frequent and deep inspirations, and nar-otics which diminish the excitability of the respiratory centre lso lessen the tendency to vomit.

The **motor** impulses from the vomiting centre are sent to the bdominal muscles, diaphragm, stomach and œsophagus by the ntercostal, phrenic, and vagus nerves respectively. Section of he vagi generally, though not always, destroys the power to omit, because it disturbs the co-ordination of the cardia and the bdominal muscles and diaphragm, so that they no longer act imultaneously, and vomiting does not occur, although retching nay continue.

The vomiting centre is usually excited by stimulation of **afferent** nerves passing upwards to it from the body, or by im-pulses sent down to it from the brain.

The **brain** may be stimulated so as to act on the vomiting entre in the medulla through impressions on the nerves of pecial sense, such as a disgusting sight, stench, or taste, or by he recollection of such subjects. Irritation of the brain itself r of its membranes by inflammation, tubercle, hæmorrhage, oftening, or cancer may also excite vomiting. The **afferent nerves** are shown in the accompanying diagram (Fig. 130). Those chiefly concerned with the action of emetics are :—

1. Branches of the glosso-pharyngeal nerve to the soft palate, he root of the tongue, and the pharynx. Tickling these parts with the finger or with a feather is one of the readiest means of nducing vomiting. Vomiting also occurs when the soft palate, onsils, or pharynx are inflamed, especially in children.

2. The nerves of the stomach. These are chiefly branches of the pneumogastric, but they are contained also in the sym-pathetic system.

3. Mesenteric nerves causing vomiting in hernia.

4. Nerves of the liver and gall-duct.

5. Nerves of the kidney and ureter.

6. Vesical nerves.

7. Uterine nerves.

8. Pulmonary branches of the vagus causing vomiting in phthisis.

There are also a number of other nerves which produce vomit-ing, but are more important in connection with pathological vomiting than with the action of emetics.

When less was known regarding the action of the nervous system in vomiting, **Emetics** were divided, according to their relation to the stomach, into direct and indirect. **Direct** emetics were those which acted only when introduced into the stomach. **Indirect** were those which acted when injected into the blood.

Their relation to the vomiting centre is of course the reverse. Drugs which are applied directly to the stomach act reflexly or indirectly on the vomiting centre, while those injected into the

blood may be carried by the circulation to the medulla and ac directly upon it.

It is to be noted, however, that drugs injected into the circula tion are carried not only to the nerve-centres but to the stomach




FIG. 130.—Diagram showing the afferent nerves by which the vomiting centre may be excited to action.

and may be **excreted** by the gastric mucous membrane. The may thus irritate the afferent nerves of the stomach and stimu late the vomiting centre reflexly just as they do when given by th mouth. Thus it has been shown by Brinton that tartar emet injected into the veins of a dog is excreted in a few minut into the stomach, and may be found on testing its contents.

It is therefore evident that the action of drugs in causin vomiting may be complex, and that drugs injected into the bloc or under the skin may cause vomiting, both by (1) **irritating** th vomiting **centre** in the medulla **directly** when conveyed to it l the circulation; and (2) by irritating it **reflexly** from the stomac whither they have also been conveyed by the blood.

It is frequently very difficult to determine in which of the two ways a drug has acted, and sometimes almost impossible decide with certainty.

The reasons for believing that any drug injected into th circulation has caused vomiting by irritating the medulla reflex through the stomach, and not by acting directly upon it, are:

(*a*) When the vomiting does not take place immediately on njection, but only after sufficient time has elapsed to allow of xcretion of the drug into the stomach.

(*b*) When the quantity of a drug required to produce vomitng by injection into the veins is greater than that which is ufficient to produce a similar effect if introduced into the tomach. It is probable that some drugs, as tartar emetic, act n both ways, because, as has already been mentioned, it is exreted into the stomach and will there act as an irritant.

But it will also produce vomiting when the stomach has been xcised and replaced by a bladder, as in Magendie's celebrated xperiment. Even this experiment, however, does not prove that artar emetic acts directly on the vomiting centre, inasmuch as t is possible that it may be excreted by the œsophagus or intesines and irritate the vomiting centre reflexly through them. As artar emetic, however, appears to act as an irritant chiefly in hose parts of the body where there is an acid secretion, it seems loubtful whether it would produce irritation in the œsophagus nd intestines such as it does in the stomach. It therefore seems ot improbable that the vomiting which it occasions after exision of the stomach is due to its direct action on the medulla blongata, but this cannot be regarded as quite proved. In rder to avoid the confusion which the terms **direct** and **indirect** metics are likely to produce with regard to their relations to the tomach and vomiting, it is better to describe them as, and to mploy the terms, **topical** or **local** and **general** emetics.

Topical, or local, are such as produce vomiting by acting ocally on the pharynx, œsophagus, or stomach; and **general**, uch as act through the medium of the circulation. The line etween the two is not distinct, inasmuch as tartar emetic will roduce vomiting in either way, and so will sulphate of zinc, or sulphate of copper. The *local* action of sulphate of zinc and sulphate of copper, however, on the stomach is so much greater han their general action that they may be classed among the *ocal* emetics.

Local Emetics.	General Emetics.
Alum.	Tartar emetic.
Ammonium carbonate.	Ipecacuanha and Emetine.
Copper sulphate.	Apomorphine.
Mustard.	Senega.
Salt.	Squill.
Subsulphate of Mercury.	Muscarine, Urechitine, Digitalis and its congeners, — not used medicinally as emetics.
Water (lukewarm and in copious draughts).	
Zinc sulphate.	
Strong infusions of vegetable bitters, as camomile, quassia, &c.	

The action of **local** emetics is confined to that of producing vomiting, which is generally not long continued, ceasing after the emetic has been evacuated, and is not accompanied by much general depression.

The vomiting occasioned by **general** emetics, on the other hand, is much longer continued, and is accompanied by great general depression, nausea, languor, muscular weakness, enfeeblement of the circulation, and increase of the secretions, especially those of saliva, sweat, and mucus in the œsophagus, stomach, and bronchial tubes.

Uses.—Emetics may be used for the purpose of simply **emptying the stomach**, or the violent expulsive efforts which they occasion may be utilised in order to remove foreign bodies or secretions from the œsophagus or from the biliary or respiratory passages.

1. Emetics may be used to cause the **expulsion of foreign bodies**, such as pieces of gristle or meat which have become impacted in the upper part of the œsophagus, and, by pressing on the larynx, are giving rise to suffocation. In such cases apomorphine given subcutaneously, or injected into a vein in the dose of $\frac{1}{12}$th or $\frac{1}{10}$th of a grain, will be found of service.

2. They may be used to **remove** the **contents** of the **stomach** when these, instead of undergoing digestion and absorption in the normal manner, have undergone fermentative changes and become acid, acrid, and irritating, giving rise to pain, either in the stomach itself, or in some other organ, as in the head. In gastralgia, or in headache either depending upon indigestion, or associated, like sick-headache, with a tendency to vomiting, large draughts of warm water often give relief. Their emetic action may be aided if necessary by tickling the fauces with the finger, or by using strong camomile tea, or mustard and water in place of water alone. Simple draughts of warm water, however, may relieve the gastralgia or headache without causing vomiting. They appear to do so by simply diluting the acrid contents of the stomach so much that they no longer irritate the mucous membrane.

3. Emetics **remove** the **poison** from the stomach in cases where it has been swallowed. Here mustard and water is very useful, as it is the emetic which is most likely to be at hand; but sulphate of copper and sulphate of zinc if readily procured are to be preferred, as they empty the stomach most quickly and effectually. In cases of poisoning by laudanum, the nerve-centres are so much deadened by the narcotic that they may not respond to the stimulus even of large doses of these emetics, and then it may be necessary to employ the stomach-pump or gastric syphon.

4. To **expel bile** from the gall-bladder, to drive small **gall-stones** through the gall-duct. The bile is secreted under a very

ow pressure, and a very slight obstruction in front may prevent s flow through the gall-duct and occasion its accumulation in he gall-bladder and biliary capillaries. The compression of he liver between the diaphragm and abdomen muscles, even n ordinary respiration, tends greatly to dispel the bile from the ver, and this expulsive action is of course greatly increased uring the violent efforts of vomiting. During these efforts the ile may be forced through the gall-duct, driving before it the bstruction which has been occasioned by the accumulation of nucus within it due to catarrh, or by the impaction of a small iliary calculus. In this manner emetics may remove jaundice ue to obstruction.

5. To **remove bile** from the body in cases of **biliousness, evers**, and **ague**. In biliousness the emetics have got the ouble action of expelling the bile from the liver in the way just nentioned, and of removing it from the body through the stomach. When bile passes along the intestines, not only is it re-absorbed, ut poisonous matters from the intestine are absorbed with it. When it is ejected from the stomach by the efforts of vomiting, no time is allowed for its re-absorption, and so both the bile tself, and any poisonous matter which it contains, are more apidly and certainly removed from the body. It is probable that he malarious poison circulates in the bile, and possibly also other oisons which give rise to fevers. There can be no doubt of the dvantages to be derived from the use of emetics in ague before he administration of quinine; and indeed cases of ague may be sometimes cured by the use of emetics alone without quinine, while quinine without emetics is not unfrequently of very little se in bad cases. Emetics have also been recommended in the arly stages of continued fevers, in order to remove the poison on which they are supposed to depend. For such purposes ipecacuanha or tartar emetic is best.

6. To **remove obstructions** from the **air-passages**, such as false membranes from the trachea and bronchia in croup or diphtheria, or the over-abundant secretion which is clogging the bronchi and interfering with respiration in bronchitis, and more rarely in phthisis. Ipecacuanha is the emetic most readily chosen in such cases, as it tends to increase the secretion from the air-passages, as well as to produce vomiting. When it does not act rapidly, sulphate of zinc or sulphate of copper may be used, and a teaspoonful of alum is a very efficient remedy in croup. When there is much depression of the circulation, carbonate of ammonium is to be preferred as an emetic, inasmuch as it stimulates the circulation, as well as causes vomiting.

Contra-indications.—Emetics must be avoided in persons suffering from **aneurism**, and used with care in persons suffering from **atheroma** or a tendency to **hæmorrhage** from the lungs or uterus, lest the high blood-pressure which occurs during the

efforts of vomiting should lead to the rupture of a blood-vessel. They should be used with caution also in persons suffering from **hernia**, or who have a tendency to it, or from **prolapsus** of the uterus. In pregnancy we often find obstinate vomiting lasting for a length of time, and yet producing no abortion; but where a tendency to **abortion** exists, emetics should be avoided if possible.

Anti-emetics and Gastric Sedatives.

Gastric sedatives are substances which lessen the irritability of the stomach and thus diminish pain, nausea, and vomiting.

Their action may be either **local** on the stomach, or **general** on the nervous system, and especially on the vomiting centre in the medulla oblongata.

Local Sedatives.

Alcohol.
Alum.
Arsenious acid in minute doses.
Atropine.
Belladonna.
Bismuth salts.
Carbolic acid.
Cerium oxalate.
Chloroform.
Cocaine.
Creasote.
Ether.
Hydrocyanic acid.
Ice.
Morphine.
Opium.
Resorcin.
Silver nitrate.
Sulpho-carbolates.

General Sedatives.

Hydrocyanic acid.
Morphine.
Opium.

Anti-emetic Measures.

Recumbent posture.
Injection of large quantities of aërated water into the rectum.

The most powerful of all **local** sedatives is ice, and when vomiting is persistent, everything should be iced, and ice swallowed in small lumps. Hydrocyanic acid and morphine probably act by lessening the irritability of both the nerves in the stomach itself and of the vomiting centre as well. The mode of action of creasote and carbolic acid is rather uncertain, because although they have a local anæsthetic action, yet they are found useful also in cases of reflex vomiting, such as the vomiting of pregnancy.

As **adjuvants** to gastric sedatives, we may mention such substances as diminish or remove the irritation, although not

ssening the sensibility, of the stomach itself. Thus, where the ritant consists of very acrid fluid in the stomach, a large draught f water, by diluting it, may lessen pain, or nausea, and alkalies ave a similar action. When the irritation is due to congestion f the mucous membrane, **astringents** will also have a sedative ction. Probably this is the explanation of the use of alum in ne vomiting of phthisis, and possibly, also, of the use of nitrate f silver in the vomiting of chronic alcoholism.

Uses.—Gastric sedatives are employed (1) to **relieve pain** in ne stomach, as in gastrodynia. The most useful are small doses f morphine, hydrocyanic acid, belladonna, arsenic, and bismuth; 2) to **relieve vomiting.** This depends upon the cause of the omiting. When it is due to acrid substances in the stomach, the est sedative is often a large draught of warm water, which either ilutes or renders them less irritating, or causes their removal y vomiting.

Where it is due to acute irritation of the walls of the stomach self, ice, hydrocyanic acid and morphine, and bismuth are est.

When due to the acrid products of fermentation in the omach, sulphurous acid, creasote, resorcin, and the sulpho-arbolates are very useful.

When due to chronic irritation and congestion, alum, nitrate f silver, creasote, carbolic acid, and the sulpho-carbolates are erviceable.

When the vomiting is due to strangulated hernia, the hernia ust be reduced, and in cases of intussusception or obstruction ese conditions must be removed. In the vomiting of pregnancy, ne irritability of the vomiting centre must be reduced by bromide f potassium or morphine. It is only in extreme cases that the ource of irritation, viz. the pregnant condition, is to be removed, ut certain local means are sometimes useful; such are separation f the membranes around the neck of the uterus, which may pos-bly act by lessening the irritation in the organ, and painting the s uteri with stimulating applications which probably rather act y a kind of counter-irritation or inhibition.

The vomiting of pregnancy has sometimes been arrested by ne injection of effervescing water, and especially of natural ffervescing chalybeate water like that of Pyrmont, into the rectum n quantities of two litres at a time. It is difficult to say whether his is due to a local or general sedative action of the carbonic cid or to reflex inhibition of vomiting (cf. inhibition of sneez-ng, p. 246).[1]

[1] Schücking, *Deutsch. Med. Ztg.*, ii. 1885.

Carminatives.

Carminatives are substances which aid the expulsion of gas from the stomach and intestines. They appear to do this by increasing the peristaltic movements of these organs, and in the case of the stomach by causing the lower end of the œsophagus or cardiac sphincter, and perhaps sometimes the pyloric sphincter to dilate so as to allow of the exit of gas. The stomach naturally contains a certain amount of gas, chiefly nitrogen and carbonic acid. The nitrogen is derived from air which has been swallowed the oxygen with which it was mixed being absorbed by the walls of the stomach.

For respiration goes on in the stomach, as well as in the lungs though only to a slight extent in mammals, and oxygen is absorbed and carbonic acid excreted. The stomach, therefore, generally contains carbonic acid in addition to nitrogen; some of the carbonic acid also is derived from the food. In addition to these gases there is frequently hydrogen present: hydrogen and a quantity of carbonic acid being formed by processes of fermentation going on in the food. Sometimes instead of pure hydrogen marsh-gas is formed, which takes fire when expelled from the stomach, and not unfrequently the hydrogen unites with sulphur forming sulphuretted hydrogen, causing to the patient an unpleasant taste of rotten eggs in the mouth, or giving their smell to the breath. It is probable that this last occurrence is due in many cases to the presence and decomposition in the stomach of bile, which contains sulphur as one of its constituents.

When digestion is rapid and complete, little or no fermentation occurs, very much less gas is formed, and therefore there is no uncomfortable distension.

There are several drugs which tend to prevent fermentation while they hardly interfere at all with the action of the gastric juice. Among these may be mentioned creasote, sulphurous acid and bitters, though the anti-fermentative action of the last has been denied. These substances may all be regarded as **adjuvants** to carminatives, and so indeed may pepsin, dilute alkalies, and all other remedies which stimulate the secretion of gastric juice and thus aid digestion.

Where there is any tendency to venous congestion in the stomach, there will be interference with the respiration in the stomach, and thus a greater tendency to the accumulation of gas. Any conditions interfering with the circulation, such as mitral disease or hepatic congestion, will thus tend to cause flatulence, and in such cases digitalis and cholagogues will prove useful adjuvants to carminatives.

It is possible that much mucus covering the surface of the stomach may interfere both with absorption and with gastric respiration. Charcoal has been given to remove flatulence, on the

pposition that it absorbs the gases in the stomach. But it ly absorbs gas when it is dry, and the beneficial action which certainly possesses is probably a mechanical one in removing ucus and stimulating circulation. Possibly bismuth, nitrate and rbonate, and magnesium, oxide and carbonate, act similarly, ough less powerfully.

The chief **Carminatives** belong to the classes of aromatic ls, alcohols, or ethers. They are:—

lspice and oil.
nise and oil.
safœtida.
ajeput oil.
apsicum.
araway and oil.
ardamoms.
nilies.
nloroform.
Cinnamon and oil.
Cloves and oil.
Coriander and oil.
Dill and oil.
Ether and acetic ether.
Fennel.
Ginger.
Horseradish.
Mace.
Mustard.
Nutmeg and oil.
Pepper.
Peppermint and oil.
Spearmint and oil.
Spirits.
Valerian and oil.

Uses.—Carminatives are employed (1) to remove pain and stension of stomach and intestines caused by **flatulence**; (2) to nder peristaltic action regular, and diminish local **spasm** and ain depending upon it. They are useful both in cases where e spasm is due to irritation of the stomach and intestines by ritant articles of food, irritant secretions, or irritant medicines. hey are therefore commonly used not only in griping and colic ains due to indigestion, worms, or exposure to cold, but as djuvants to purgatives in order to lessen the griping pain, which ney often cause when given alone. In addition to this, by ren- ering the peristaltic action of the bowel more regular, they ssist the action of the purgatives.

ACTION OF DRUGS ON THE INTESTINES.

Intestinal Movements and Secretion. — The peristaltic novements of the intestine occur even when it is separated ntirely from the body. Their rhythmical occurrence appears to e due to the action of the ganglia contained in Auerbach's plexus, which lies between the outer longitudinal and internal circular ayer of the muscular coat. The **secretion** is probably influenced y Meissner's plexus, which lies in the sub-mucous coat.

Both the movements and the secretion of the intestine require o be regulated in accordance with the wants of the body, and this s done by the **nerves** which connect these plexuses with the erebro-spinal centres. The chief of these nerves are the splanch- ics and the vagi. Irritation of the vagi frequently causes move- nents of the intestine; irritation of the splanchnics, on the other and, arrests them, so that the splanchnics have been regarded s the inhibitory nerves of the intestine, just as the vagi are the nhibitory nerves of the heart. But this arrest is by no means

constant; sometimes the movements instead of being arrested are distinctly increased; so that it is evident that the splanchnics contain a mixture of stimulating and inhibitory fibres, or else that the same fibres are capable of exercising either function under different conditions.

Paralytic Secretion.—When all nervous connection between the intestine and the higher nerve-centres is cut off by completely dividing the intestinal nerves, a copious secretion, exactly resembling the rice-water stools of cholera, occurs in the intestine. This is best shown by isolating three loops of intestine, by means of ligatures, after they have been previously carefully emptied, as shown in Fig. 131. The nerve-fibres going to the middle loop are then divided, and the intestine is returned to the abdominal cavity. After four or five hours the animal is killed, and the intestine examined; it is then found that the loop, the nerves of which have been divided, is filled with fluid, while the other loops, which have been under precisely the same circumstances, but the nerves of which have not been cut, remain empty.

It is evident, then, that certain **nerve-centres** possess the power of **restraining** the **secretion** from the intestine. These nerve-centres have been shown by Pye-Smith and myself to be the smaller or inferior ganglia of the solar plexus, with the superior mesenteric off-set from them. When these ganglia are destroyed, the same abundant secretion occurs in the intestine




FIG. 131.—Diagram showing the effect of section of nerves on secretion from the intestine. The nerves going to the middle loop have been divided, and it is distended with the fluid secreted.

as when all the nerves are cut, but if these ganglia be left intact the spinal cord may be removed, the vagi and splanchnics cut and the semilunar ganglia excised without any excessive secretion occurring in the intestine.

The **vascular supply** of the intestines is regulated to a considerable extent by the splanchnics, irritation of which causes contraction of the vessels. There appears also, however, to be an important relation between the intestinal vessels and the lumbar portion of the spinal cord, because when this part of the cord is

estroyed with extirpation of the solar plexus, **hæmorrhage** or yperæmia of the intestinal mucous membrane occurs, so that he internal surface of the intestine has a somewhat dysenteric ppearance. This does not occur when the solar plexus and emilunar ganglia are destroyed, the splanchnics divided, or the esenteric nerves cut.[1]

The nervous arrangements for regulating intestinal movement and secretion are evidently exceedingly complex, and until ur knowledge of their physiological relations is more perfect, we annot expect to understand completely the effect which drugs roduce upon them. These are occasionally very complicated, nd vary considerably according to the quantity of the drug sed. **Drugs** may affect the intestine by their **local** action on he intestine itself, by their **direct** action on the **central nervous** ystem, or by their **indirect** action through the alterations in the uality or supply of the blood. The quality of the blood which irculates in the intestine alters its movements very considerably.

When the aorta is clamped, so that the blood which circuates in the intestine and in the lower part of the spinal cord ecomes venous, the peristaltic movements are usually much increased; when the compression is removed and arterial blood is llowed to circulate again, the peristalsis, instead of diminishing, s one might expect, becomes still more intense. Compression f the vena cava inferior, or of the portal vein, sometimes causes slight increase in the peristaltic movements, but it is inconiderable as compared with those produced by clamping the orta. During **suffocation,** when the blood becomes venous hroughout the whole body and exercises an irritating action, not nly on the nerve-centres present in the intestine and in the umbar portion of the spinal cord, but also on the brain and pper part of the cord, the effect on the movements of the intestine is variable. They are sometimes increased, but sometimes an inhibitory effect appears to be produced through the igher centres and their movements are arrested.

It is evident therefore that when an animal has been poisoned y any drug, and the intestines are examined after death, two **different conditions** may be found, which do not depend upon ny peculiar action of the drug on the intestine, but only upon ts effects on the higher nerve-centres; thus, if the higher centres ave been in such a condition as to cause inhibition, the intesines may be found in a state of perfect rest, whereas, if they appen not to be in this condition, brisk peristalsis may be observed. It very often occurs that when the intestines are first xposed after an animal's death, they are found to be at rest, but s the higher centres die from a stoppage of the circulation, the peristaltic movements become much accelerated.

[1] T. Lauder Brunton and Pye-Smith on 'Intestinal Secretion and Movement,' *British Association Reports*, 1874, 1875, 1876.

In order to simplify the problem presented by the compli cated nervous arrangement in the intestine, Ludwig and Salviol have used the plan of keeping up the **circulation artificially** i a small piece of intestine, and then investigating its movement under various conditions. The intestine was laid on a piece o




FIG. 132.—Diagrammatic representation of apparatus for testing the action of drugs on the intestin by artificial circulation through it. For the sake of simplicity the means employed to keep u the temperature of the intestine and apparatus have been omitted. A, a board on which th intestine, B, is laid. C, a cannula tied into a branch of the mesenteric artery. D, D, two stop cocks, by means of which pure blood or poisoned blood may be passed at will through the can nula. E and F, two flasks containing pure and poisoned blood. G, a block on which they stan and by which they can be raised to a greater or less height, so as to alter the pressure und which the blood flows. When the apparatus is kept warm the pressure is more easily regulate by passing air into the flasks from a pressure bottle. H, the lever for registering the movemen of the intestine. One end is weighted and rests on the intestine. I is the axis on which th lever works. K is a revolving cylinder on which the movements are recorded.




FIG. 133.—Shows the effect of anæmia. The upper tracing shows the movements of the intestine supplied with normal blood; the lower shows the movements of an intestine rendered more vigorous by anæmia.




FIG. 134.—Shows the effect of peptones. Th first half of the tracing shows the mov ments of an intestine supplied with bloo thoroughly oxygenated; the second ha shows the effect of blood containing pe tones.




FIG. 135.—Shows the effect of nicotine. The part of the tracing marked *A B* shows the intestinal movements during the circulation of blood saturated with oxygen (apnœic blood); the part *N B* of blood containing nicotine.



FIG. 136.—Shows the effect of opium. In t first part of the tracing the intestine w supplied with apnœic blood; in the latt with blood containing opium.

cork, in a warm chamber. It was supplied with blood by means a cannula placed in the artery, and allowed to flow out throug a cannula in the veins (Fig. 132). Its movements were registere by a small lever placed upon it. When blood fully oxygenate passed through it, the lever traced only a straight line or gent oscillating curve (Fig. 134), but when the flow of blood wa stopped, so that the blood stagnated and became **venous**, contra tions began which were indicated as a series of curves. A trac of **peptone** caused first strong contraction and then a number irregular contractions, at the same time that the vessels becam

fuller of blood (Fig. 134). **Nicotine** causes brisker movements of the intestine, and lessens the rapidity of the flow of blood (Fig. 135). In large doses it causes tetanic contraction of the circular fibres.

Atropine causes irritation of the vessels, while the muscular fibres remain at rest. The action of **opium** is very remarkable; when the tincture is added in the proportion of ·04 to ·01 per cent. to the blood which is circulating through the intestine, the circulation becomes at once lessened, but almost immediately afterwards the diminution passes abruptly into great increase, so that five or seven times as much blood flows through in a given time as formerly; at the same time all the movements of the intestine are abolished, but the intestinal wall instead of being relaxed, as one would expect, is in a condition of considerable contraction (Fig. 136). When the opium is washed out of the vessels by pure blood, the after-effects vary according to the quantity which is used. If it is small, the movements and circulation in the intestine soon become normal, but if a large dose has been used, the circulation returns to the normal condition, but the movements remain abolished for a length of time. The peristaltic action induced by nicotine is arrested by opium. The local action of this drug therefore seems to be that it converts the peristaltic movement into a steady contraction.

A remarkable difference between the action of salts of **sodium** and **potassium** on the intestine has been detected by Nothnagel,[1] and his results have been confirmed by Flöel. When the intestine is exposed, and a potassium salt is applied to its external or peritoneal surface, it produces a contraction of the muscular



FIG. 137.—Represents a piece of duodenum, *a*, after irritation by potassium chloride; *b*, after irritation by sodium chloride. *o* indicates the point of irritation, and the arrows the direction in which the intestinal contents normally move from the pylorus towards the anus. (After Flöel.)

walls, which remains localised to the point of contact, or simply causes a ring of contraction opposite the point (Fig. 137*a*). When a sodium salt is used instead, it produces a contraction which is not limited to the point of contact, but always spreads some little distance from it, and sometimes does so in the direction towards the pylorus, and not towards the anus (Fig. 137*b*), but at other times spreads equally in an upward and downward direction[2] (Fig. 138 *a*). This peculiar action appears to be due to the potassium salts acting as stronger muscular irritants than the sodium salts, while the progressive contraction caused by the sodium is due to the intestinal nerves in their case being to a greater extent involved.

[1] Nothnagel, *Virchow's Archiv*, Bd. 88, p. 1.
[2] Flöel, *Pflüger's Archiv*, vol. xxxv. p. 160.

The effect of **morphine** is very remarkable. When the animal, in addition to being anæsthetised by ether only, as in the previous experiment, has a small dose of morphine injected also into the veins, it has a sedative effect, so that **sodium** salts applied to the intestine produce only a local contraction like potassium salts. But this is only when a certain dose of morphine is employed, about 0·01 to 0·03 gramme of morphine for a rabbit of average size. When the dose was increased from 0·05 to 0·1




FIG. 138.—Represents a piece of intestine, *a*, at the commencement of contraction, after irritation by sodium chloride ; *b* at the end of contraction. *o* indicates the point of irritation. (After Flöel.)

gramme of morphine, an exactly **contrary effect** was produced, and the application of sodium salts, instead of being followed only by local contraction, caused a peristaltic contraction, which was usually very much more energetic than in the normal condition, and not only spread upwards from the point of contact, but downwards towards the large intestine, which it never did under other circumstances.[1] The quieting or inhibitory effect of moderate doses of morphine upon the intestine, irritated by sodium salts, appears to be exercised through the splanchnic nerves, inasmuch as when the mesentery, going to one part of the intestine, is divided in an animal that has received a moderate dose of morphine, the application of sodium salts to this part is followed by a peristaltic wave ; while, in the other parts of the intestine where the nerves are uninjured, the sodium salt still produces only local contractions.

From these experiments it is evident that moderate doses of morphine produce a very different effect upon the intestine from large ones : and this effect has indeed been long recognised in practice.

Moderate doses of opium have a constipating action and are constantly used to check diarrhœa, but large doses, such as those taken by opium-eaters, really have no constipating effect. Indeed, large doses of opium injected directly into the jugular vein of a dog act as most energetic purgatives, being much more prompt in their action than almost any other drug that we know. Immediately after their injection the whole intestinal tract is thrown into violent action and its contents expelled, after which it again becomes quiet.

Very minute doses also seem to have a purgative action, as well as very large ones, and I have used them with considerable success in many cases of constipation.

Constipation may be due to diminished peristaltic action, or

[1] Nothnagel, *Virchow's Archiv*, Bd. 89, p. 1.

iminished secretion, or to both, and in some cases is associated ith accelerated absorption. In all probability it is generally ue to a diminution in the peristaltic action. In the normal ondition this ought to go on regularly, so that the bowels hould be evacuated, on an average, once a day, though in some ersons evacuations normally occur two or three times a day, nd in others only once in three or four days. In some appaently healthy persons I have observed an interval of as much s two or three weeks. In some persons the normal stimulus of rdinary easily digestible food does not seem to be sufficient to eep the bowels acting, but food which leaves much indigestible esidue, such as brown or bran bread, salad, figs, prunes, or amarinds, will do so. These latter fruits owe their laxative roperties partly to the insoluble residue they leave and which cts as a mechanical irritant to the intestine, and partly to the alts and sugar and mild laxative principles they contain. reacle and gingerbread also have a useful aperient action, and heir pleasant taste makes them specially suitable for children. he effect of a somewhat stimulant article of food is greater hen taken on an empty stomach, and thus a fig before breakast will have a much greater laxative effect than one taken after inner. A glass of cold water also, by stimulating peristalsis, ill have a laxative action when taken on an empty stomach at ed-time or on rising in the morning. When these means are nsufficient a slightly irritating substance, such as an aloetic pill aken on an empty stomach just before dinner, will aid the timulating effect of the food which is taken afterwards, and will e sufficient to ensure perfectly regular and normal evacuations hich do not in any way incommode the person. In consequence f this many people continue to take such **dinner pills** regularly or many years together. Others, again, suffer from constipaion, but with them small doses of purgative medicine, if they ct at all, act violently, and leave the person weak and uncomfortable, while the bowels again become constipated. This ondition is found not unfrequently among women, and is accompanied, sometimes at least, with pain or tenderness in one r both ovaries. In such persons, also, contrary to the general ule, walking exercise increases instead of diminishing constipation.

My friend Dr. Litteljohn noticed that in a case of ovarian enderness, half a grain of opium given to relieve the pain acted s a purgative. On thinking over this, it occurred to me that he constipation in such cases might be due to reflex irritation f the inhibitory intestinal nerves by the tender ovary. It eemed therefore probable that by using graduated doses of pium, one might be able to lessen the action of the inhibitory erves, or even to divert the stimulus from them on to the stimuating fibres, and thus produce purgation instead of consti-

pation. Not knowing what dose would be sufficient to produce this effect, I began with one drop of tincture of opium given in a teaspoonful of water every night. To my astonishment this




FIG. 139.—Diagram to show the way in which ovarian irritation probably causes constipation.

dose was not only in most cases sufficient, but in one case it proved excessive, doing no good, while half a drop acted as a brisk purgative. It is evident that opium used in this way will not act as a purgative in cases of constipation depending upon general insensibility of the intestinal nerves. The cases in which it is most useful are those of delicate women of a nervous temperament, suffering from ovarian pain, and in whom, ordinarily, purgatives produce excessive action followed by constipation. Small doses of belladonna have also been recommended in constipation, and it is probable that they act in a similar manner when given alone, and that belladonna, hyoscyamus, and essential oils assist the action of purgatives by tending to divert the stimulus, which the irritating constituent of a purgative produces, from the inhibitory to the accelerating intestinal nerves. We know at present but little regarding diminished secretion as a cause of constipation.

Action of Drugs on Absorption from the Intestines.—Ether introduced into the intestine greatly increases its vascularity. It also quickens absorption very much, as is shown by the fact that poison acts more quickly, and such substances as ferro-cyanide of potassium appear sooner in the urine, when they are administered along with ether than when given alone. Carbonic acid has a somewhat similar though weaker action.

Coto bark has been used in diarrhœa, and as it has no proper astringent action, its utility has been ascribed to an antiseptic action by which it diminished the formation of irritant products in the intestines. Albertoni has investigated the action of the coto alkaloids, and finds that although cotoine somewhat lessens putrefaction and the development of bacteria, it does not stop them either in the organism or outside it. It has, however, a very peculiar action on the vessels of the intestine. By keeping up artificial circulation in a loop of intestine (*vide* p. 382), it

finds that cotoine dilates the arteries, causes the blood to flow more readily into the veins, and preserves the vitality of the intestine. It also dilates the vessels of the kidney, and causes the blood to flow more rapidly through them, but does not alter the circulation in the submaxillary gland.

Albertoni thinks that the benefit which cotoine produces in diarrhœa is due to dilatation of the intestinal vessels, and the increased power of absorption which it causes. He considers that in many cases of diarrhœa diminished absorption is a most important factor.[1]

Paracotoine acts like cotoine, but less strongly.

Opium and chloral also dilate the vessels of the intestine, but their action is a paralysing one, while that of cotoine is not.

It is possible that the beneficial action of bael fruit in dysentery may depend on some similar property, as this substance has the peculiarity of acting as a laxative in health, while it lessens the evacuations in dysentery.

Cholagogues probably influence absorption from the intestine powerfully (p. 406).

Intestinal Astringents.—Diarrhœa may depend (1) upon excessive peristaltic action, whereby the contents of the intestine are hurried along before time has been allowed for their absorption, (2) upon diminished absorption, (3) upon excessive secretion. In one form of diarrhœa, where the introduction of food into the stomach seems to excite peristaltic action throughout the intestine so that the person is frequently forced to rise from the table in order to evacuate the bowels, small doses of one half to two minims of liquor arsenicalis given immediately before meals, as recommended by Ringer, frequently act like a charm. In ordinary cases of diarrhœa, opium, by lessening the irritability of the intestine, is most serviceable. Some medicines lessen peristaltic action, not by affecting the bowel, but simply by removing the stimuli which were exciting it. Thus small doses of soda are useful in the diarrhœa of children by neutralising the acid which was acting as an irritant. Creasote has a similar action by lessening putrefaction or fermentation, and thus preventing the formation of irritant products. It is probable that lime acts also to a certain extent by its antacid properties, but there is little doubt that there are other factors in its astringent action which we do not yet understand. The effect of cotoine on intestinal absorption has just been mentioned. With the view of ascertaining whether we could find any drug which would arrest the copious secretion from the intestine which takes place in cholera, Pye-Smith and I made a large number of experiments. For this purpose we isolated loops of intestine, and into one injected sulphate of magnesium mixed

[1] *Archiv für exper. Path. und Pharm.*, vol. xvii. p. 291.

with the drug to be tested. In some experiments we injected the sulphate of magnesium into the intestine, and the drug which we wished to test into the veins.

Sulphate of atropine, iodide of methyl-atropine, chloral-hydrate, emetine, morphine, sulphate of quinine, tannin, and sulphate of zinc, were all tried locally with negative results. Chloral and morphine injected subcutaneously also gave negative results.[1]




FIG. 140.—Diagram illustrating diarrhœa depending on the presence of scybala in the intestine. *a* is a scybalous mass; *b* is the fluid which it causes the intestine to secrete.

In many cases the best way of checking diarrhœa at its commencement is to give a purgative such as castor-oil, either alone or with a few drops of tincture of opium in it. The irritant substances which cause the diarrhœa are swept out of the intestine by the action of the purgative, and any irritation which remains is soothed by the opium. Chronic watery diarrhœa, alternating with constipation, is often best treated in the same way. We may suppose that here the presence of scybalous masses in the intestine gives rise to a watery discharge, which does not, however, wash away the scybala themselves (Fig. 140). When a purgative is given which causes secretion from the intestine above the scybala, the fluid in its downward flow, assisted also by the increased peristalsis, washes away the scybala, and thus removes the source of irritation.

Purgatives.

Purgatives are substances which **cause intestinal evacuations.** They are divided according to their nature into **laxatives, simple, drastic,** and **saline purgatives, hydragogues,** and **cholagogues.**

Laxatives are those which increase only **slightly** the action of the bowels and render the motions slightly more frequent and softer, without causing any irritation. Most articles of food which leave a large indigestible residue in the stomach act as

[1] *Report to Brit. Assoc.*, 1874.

laxatives: such are oatmeal, brown bread, and bran biscuits. Articles of food which contain salts of vegetable acids and sugar in considerable quantity also act as laxatives. The chief laxatives are:—

Honey.	Tamarinds.	Sulphur.
Treacle.	Figs.	Magnesia.
Gingerbread.	Prunes.	Castor-oil (in small doses).
Manna.	Stewed apples.	
Cassia.		

Figs, raspberries, and strawberries, in addition to containing sugar and vegetable acids, have a number of small seeds which are absolutely indigestible, and these have probably a mechanical action in stimulating the bowel.

Simple purgatives also, when given in small doses, act as laxatives: such are carbonate of magnesium, magnesia, olive-oil, and sulphur.

Simple purgatives are more active than laxatives, and their administration is usually followed by one or more copious and somewhat liquid stools. Their action is sometimes accompanied by some irritation and griping. These are:—

Aloes.	Senna.
Rhubarb.	Castor-oil.
Rhamnus (various species), e.g. Frangula and Cascara Sagrada.	

Drastic purgatives are those which cause violent action of the bowels, usually accompanied by evidences of greatly increased peristaltic action, such as borborygmi. They cause irritation of the intestine, and when taken in large doses produce inflammation and symptoms of poisoning. These are:—

Elaterium.	Gamboge.
Colocynth.	Podophyllin.
Jalap.	Croton-oil.
Scammony.	

Saline purgatives consist of neutral salts of metals of the alkalies or alkaline earths. The more commonly employed are:—

Sulphate of potassium.	Bi-tartrate of potassium.
,, sodium.	Tartrate of potassium and sodium.
,, magnesium.	Citrate of magnesium.
Phosphate of sodium.	Sulpho-vinate of sodium.
Tartrate of potassium.	

Hydragogues are purgatives which excite a copious secretion from the intestinal mucous membrane and thus remove much

water from the body; some of them belong also to the drastic group and others to the saline.

Bi-tartrate of potassium.
Elaterium.
Gamboge.

Cholagogue purgatives are those which remove bile from the body. Some drugs aid the removal of bile by stimulating the secretion of the liver, but these, when they have no purgative action, are classed as hepatic stimulants. Cholagogue purgatives probably act by quickening peristaltic action of the duodenum and small intestine, thus preventing the absorption of the secreted bile.

Aloes.
Rhubarb.
Mercurial preparations (blue pill, calomel, grey-powder).
Euonymin.
Iridin.
Podophyllin.

Action of Purgatives.—Purgatives may act in three ways: 1st, by quickening the peristaltic action of the bowels; 2nd, by increasing secretion of the intestinal membrane, and thus to some extent washing out its interior; 3rd, by hindering absorption of the fluids of the intestines.

Simple purgatives act chiefly by stimulating **peristaltic** movements, and have little effect on the secretion.

Hydragogue and **cholagogue** purgatives increase the secretion more than the peristaltic action, and **drastics** increase both. It has been held by several eminent German pharmacologists that the more watery stools produced by many purgatives are due only to more rapid peristaltic action, which hurries along the intestinal contents before there has been time for the absorption of their fluid constituents.

This opinion is chiefly based on the observations of Thiry and Radziejewski.

Thiry isolated a small piece of intestine, one end of which he attached to the abdomen and the other he sewed up. The part of the intestine from which this piece had been removed was again united by sutures, so that the intestine was perfect as before, though rather shorter. The small bag of intestine retained its vascular and nerve supply uninjured and secreted readily when tickled with a feather; but purgative medicines, such as croton-oil, senna, sulphate of magnesium, aloes, jalap, and sulphate of sodium, when applied to it, produced no increased secretion. These experiments led pharmacologists to believe that the ordinary idea that purgatives produced increased secretion from the intestine was erroneous; and the necessity for any such supposition seemed to be removed by an

experiment of Radziejewski, who made an intestinal fistula in the ascending colon of a dog, and found that the intestinal contents as poured into the large from the small intestine exactly resembled the stools which ordinarily follow the administration of a purgative.

The ordinary phenomena produced by purgative medicines would therefore seem to be readily explained by increased peristalsis alone, but some other experiments by Colin and by Moreau have shown that the method employed by Thiry did not afford trustworthy results as to the action of purgatives on the intestines. Moreau isolated three loops of intestine by means of ligatures, carefully emptying the loops beforehand. He then injected a purgative medicine into the middle loop and returned the intestine to the abdomen. On examination some hours afterwards, it was found that, although all three loops had been under similar conditions, the one into which the purgative had been injected was distended with fluid while the others remained perfectly empty. These experiments were repeated by Vulpian, and afterwards by myself, with similar results. There can be no doubt whatever, then, that purgatives act both by increasing peristaltic action and intestinal secretion. Some purgatives act chiefly by the one, and some chiefly by the other.

In the case of some of the salines, the secretion is greatly increased, while the peristaltic movement is so little affected that the secretion may lie so long in the intestine as to be reabsorbed, and the drug therefore fails to produce purgation at all. For this reason it is usual to **combine** such salines with simple purgatives, which will accelerate the peristalsis.

Laxatives have little action on the system beyond that which is due to the removal of waste and irritating substances from the bowels; but simple **purgatives,** and still more drastic purgatives, in addition to the direct action upon the bowels, exert an indirect effect upon the blood, removing from it a not inconsiderable portion of its fluid, and therefore causing a form of partial depletion.

The action of cholagogues will be more particularly considered in another paragraph (p. 404).

The action of purgatives generally, and especially of saline cathartics, has been a subject of very great dispute, and it is a matter of extreme difficulty to determine exactly. The question seems to be, however, settled by the masterly researches of Dr. Matthew Hay, and I cannot, I think, do better than give his conclusions in his own words.

1. A saline purgative always excites more or less secretion from the alimentary canal, depending on the amount of the salt and the strength of its solution, and varying with the nature of the salt.

2. The excito-secretory action of the salt is probably due to

the bitterness as well as to the irritant and specific properties of the salt, and not to osmosis.

3. The low diffusibility of the salt impedes the absorption of the secreted fluid.

4. Between stimulated secretion on the one hand, and impeded absorption on the other, there is an accumulation of fluid in the canal.

5. The accumulated fluid, partly from ordinary dynamical laws, partly from a gentle stimulation of the peristaltic movements excited by distension, reaches the rectum and produces purgation.

6. Purgation will not ensue if water be withheld from the diet for one or two days previous to the administration of the salt in a concentrated form.

7. The absence of purgation is not due to the want of water in the alimentary canal, but to its deficiency in the blood.

8. Under ordinary conditions, with an unrestricted supply of water, the maximal amount of fluid accumulated within the canal corresponds very nearly to the quantity of water required to form a 5 or 6 per cent. solution of the amount of salt administered.

9. If, therefore, a solution of this strength be given, it does not increase in bulk.

10. If a solution of greater strength be administered, it rapidly increases in volume until the maximum is attained. This it accomplishes in the case of a 20 per cent. solution in from one hour to one hour and a half.

11. After the maximum has been reached, the fluid begins gradually and slowly to diminish in quantity.

12. *Cæteris paribus*, the weaker, or in other words, the more voluminous the solution of the salt administered is, the more quickly is the maximum within the canal reached; and accordingly purgation follows with greater rapidity.

13. Unless the solution of the salt is more concentrated than 10 per cent. it excites little or no secretion in the stomach.

14. The salt is absorbed with extreme slowness by the stomach of the cat.

15. The salt excites an active secretion in the intestines, and probably for the most part in the small intestine, all portions of this viscus being capable of yielding the secretion in almost equal quantities.

16. The bile and pancreatic juice participate but very little in the secretion.

17. The secretion is probably a true *succus entericus*, resembling the secretion obtained by Moreau after division of the mesenteric nerves.

18. The secretion is promoted by local irritation of the intestine, as by ligatures, but only in the immediate vicinity of the irritation.

19. Absorption by the intestine generally is reflexly stimu-
ted by such irritation (the effect of numerous ligatures applied
t points remote from the seat of the injected salt being to dimin-
h the amount of purgative fluid by accelerated absorption).

20. If the salt solution be injected directly into the small
ntestine, the stronger within certain limits the solution is, the
reater will be the accumulation of fluid within the intestine.

21. This difference is not observed when the salt is adminis-
ered *per os*, as the strong solution becomes diluted in the stomach
nd duodenum before passing into the intestine generally.

22. The difference is due to the local action of the salt on the
ucous membrane, and probably more to an impeded absorption
han to a stimulated secretion.

23. When the salt is administered in the usual manner, it
ppears, in the case of the sulphate of magnesium and sulphate
f sodium, to become split up in the small intestine, the acid
eing more rapidly absorbed than the base.

24. A portion of the absorbed acid shortly afterwards returns
o the intestines.

25. After the maximum of excretion of the acid has been
eached, the salt begins very slowly and gradually to disappear
y absorption, which is checked only by the occurrence of
urgation.

26. During the alternations of absorption and secretion of
he acid, it is the salt left within the intestine which excites
ecretion, the absorbed and excreted acid exerting no such action
hilst in the blood, or during the process of its excretion, as
Ieadland believed.

27. The salt does not purge when injected into the blood,
nd excites no intestinal secretion.

28. Nor does it purge when injected subcutaneously, unless
n virtue of its causing local irritation of the abdominal subcuta-
eous tissue, which acts reflexly on the intestines, dilating their
lood-vessels, and perhaps stimulating their muscular movements.

29. The sulphate of sodium exhibits no poisonous action
hen injected into the circulation.

30. The sulphate of magnesium is, on the other hand, power-
ully toxic when so injected, paralysing first the respiration and
fterwards the heart, and abolishing sensation or paralysing the
ensory-motor reflex centres.

31. Both salts, when administered in the usual manner,
roduce a gradual but well-marked increase in the tension of
he pulse.

32. According as the salt-solution within the intestine in-
reases in amount there occurs a corresponding diminution of
he fluids of the blood.

33. The blood recoups itself in a short time by absorbing
rom the tissues a nearly equal quantity of their fluids.

34. The salt, after some hours, causes diuresis, and with it a second concentration of the blood, which continues so long as the diuresis is active.

35. As the intestinal secretion excited by the salt contains a very small proportion of organic matter as compared with the inorganic matter, the purgative removes more of the latter than the former from the blood. In certain cases a large quantity of the salts of the blood is thus evacuated.

36. The amount of the normal constituents of the urine is not affected by the salt.

37. After the administration of sulphate of magnesium much more of the acid than of the base is excreted in the urine.

38. The salt has no specific action in lowering the internal temperature of the body, or has it only to a very small extent.

39. It reduces, however, the absolute amount of heat in the body.

Uses.—Purgatives are used, firstly, to **remove** from the intestinal tube **fæcal** matters. They thus not only prevent the accumulation of such matters, but remove the irritation which their presence produces, and which may evidence itself in disturbances of other organs, producing, for example, headache and malaise. These disagreeable symptoms produced by constipation are perhaps partly due to the irritation of the intestinal nerves producing reflex disturbance of the circulation, but it is probable also that they may be due in part to the toxic action of poisonous gases, liquids, or solids, generated in the intestine by imperfect digestion or decomposition of the food. For such purposes as this we may employ, as we find them necessary, laxatives or simple purgatives.

The second use of purgatives is to **remove liquid** from the body in cases of dropsy, due either to heart or kidney disease. For such purposes we use saline hydragogue cathartics.

From his researches on the action of saline cathartics Dr. Hay had found that if a salt be given in a concentrated solution when the alimentary canal contains little or no fluid, it produces an almost immediate and very decided concentration of the blood by the removal of a large quantity of its water in the form of intestinal secretion. But if the salt be given in sufficient water or if the alimentary canal contain sufficient fluid at the time of administration, no such concentration occurs. The concentration reaches its maximum in half an hour, but does not last more than half an hour or an hour, when it begins to decline and continues to do so until it reaches the normal at the end of about four hours. This return of the blood to its normal concentration is not due to re-absorption from the intestine, but to the absorption of lymph and fluids from the tissues. Some hours after the administration, either of a concentrated or dilute saline solution, the blood undergoes another concentration, but

an the first but continuing longer. Saline cathartics, as often ed in **dilute** saline solution, owe their use in dropsy, to a great tent, to their **diuretic** action. When given in **concentrated** ution under proper conditions, the benefit they produce by **rgation** is exceedingly great. These conditions are that the mentary canal should be freed from food and especially from uids by previous abstinence for some hours, and that the salt ould be given along with the smallest possible quantity of ter. Sulphate of magnesium being soluble in less than its n weight of water is most suitable. Alkaline tartrates, and chelle salt may also be useful; sulphate of sodium is more soluble, and therefore less suitable; phosphate of sodium and phate of potassium are too insoluble to be of any service.[1]

The third use is to **lower** the **temperature** in fever, and for is we chiefly use salines. The *modus operandi* here is not yet ll understood, as they have no such action in health (p. 394).

The fourth use is to **lower** the **blood-pressure**, and thus to event the rupture of a blood-vessel, and consequent apoplexy, to prevent further extravasation in a case where the vessel s already burst.

The regular use of aperients is especially necessary in gouty rsons with contracted kidney and high blood-pressure. How their utility is to be ascribed to their direct effect in lowering e blood-pressure, and how far to the removal of waste products ich might raise the pressure it is impossible at present to say. e utility of purgatives after apoplexy has occurred may be ubtful, and though usually administered, they probably do no od. But, even if they do no good, they do no harm. A drop of oton-oil or a few grains of calomel on the tongue is the usual m of administration.

A fifth use is to prevent straining at stool where violent orts are dangerous, as in aneurism, hernia, &c.

Action of Irritant Poisons.

A great number of drugs which are employed in medicine, d are most useful when given in small doses, act as irritant isons in large ones. Their action is then not restricted to the omach, nor even to the whole of the intestinal canal, but they ercise, in addition, a marked effect upon other functions of the dy, such as respiration and circulation.

In considering the physiological action of many drugs it is cessary to describe the effect they will produce when given in rge quantities, as, for example, in an overdose, as well as in oderate or small ones.

It will save both time and space to consider here the action

[1] *Lancet*, April 21, 1883.

of irritant poisons generally, and to refer to this descriptio when discussing the effect of individual drugs.

The symptoms of irritant poisoning are to a great extent th same, whatever be the irritants swallowed; it is therefore con venient to give an account of these symptoms, and then to men tion the special peculiarities which occur in the case of differen poisons.

A poison is most usually swallowed, and it then comes suc cessively in contact with the lips, **mouth** and tongue, **gullet** an **stomach.** It may sometimes reach no farther, being eithe evacuated by vomiting or absorbed. It frequently, however, als passes into the **intestine.** On all those parts which it reache it exerts a local action; besides this, however, it exerts a refle action on the respiration and circulation. Corrosive poison produce a feeling of burning in the lips, mouth, gullet, an stomach; the **pain** in the stomach, extending more or less ov the abdomen, is accompanied by tenderness, and is increased l pressure. It is thus distinguished from the pain of colic, whic is usually relieved by pressure.

The irritation of the stomach gives rise to **vomiting**; th vomited matters usually consisting, first of the contents of th stomach, next of bile or mucus, and lastly of mucus staine




FIG. 141.—Diagram to show the nervous mechanism by which the action of the heart may depressed by irritation of the stomach. The reflex irritation of the vagus may render heart's action simply weak, or slow and weak (*vide* p. 310).

with blood. These matters may sometimes be more or less act upon by the poison, where this is a strong acid or alkali. T intense irritation in the stomach produces effects on the respi tion and circulation very much like those caused by a sev blow in the epigastrium. The heart's action is greatly weaken at first, and it may be rendered slow from reflex irritation of vagus, but in the later stages it is generally rapid, very sm weak, or almost imperceptible; sometimes it may be intern

nt (see Fig. 141). On account of the weakness of the circula- n the face and the general **surface** of the body are pale, the eeks sunken, and the extremities cold. The frequency of the **spiration** may vary, may be either slower or quicker than rmal, but it is almost always laboured and shallow, as the ense irritation in the stomach renders the descent of the aphragm in deep inspiration painful, and the sufferer there- re tries to avoid it.

Although the **pulse** at the beginning of the poisoning may be w, when advanced it is usually, as already mentioned, very pid. Exceptions to this rule may occur, chiefly in the case of isons which, after their absorption, have an action on the art itself; these are potassium nitrate and salts of barium. consequence of the weakness of the circulation the face is ually very pale, but an exception to this may occur in poison- g by corrosive sublimate, where the face may be flushed. In senical poisoning the face is not only pale, but assumes a lish hue, and the pinching may be extreme, so that the ndition resembles that of a person suffering from Asiatic olera.

Where the poison is exceedingly corrosive, as in the case of ids and caustic alkalies, its local action on the stomach in causing elling of the mucous membrane may tend partially to occlude e pylorus, and the greater part of the poison may either main in the stomach itself or be ejected by vomiting without ssing into the intestine. In such cases vomiting will occur ne without being accompanied by purging, and the pain in e abdomen may be less diffused. Most irritant poisons, how- er, pass from the stomach into the **intestines**, and thus violent rging is induced in addition to the vomiting. The inflamma- n of the intestines also causes the pain to be diffused over the ole abdomen.

Peculiarities in the Action of different Irritant Poisons. -Acids throw down albumen as a white precipitate, and in con- quence, when brought in contact with the lips or tongue in a ncentrated condition, they cause white stains. The white stain most marked in the case of carbolic acid; it occurs also from drochloric acid; it may occur from sulphuric, but as the rther action of the sulphuric is to char albumen or other rganic substances, the stain may acquire a brown or black lour. Nitric acid produces a yellow stain, rendered brighter the application of ammonia. Perchloride of iron produces a llowish-brown stain; the caustic alkalies remove the epidermis nd give a soapy feeling to the surface, but do not leave any stain. fter a short time the mucous membrane becomes injected and vollen from the irritation.

In the mouth the taste peculiar to the poison often leads to s detection, so that very little of it may be swallowed in cases

where a person was about to take it unwittingly. Arsenic although a powerful irritant in the stomach, is almost tasteless.

As the poison passes down the gullet, it may have an important influence on the respiratory tract; this is especially the case where it gives off fumes like nitric acid, hydrochloric acid and ammonia; the fumes, passing into the larynx and trachea excite irritation, spasm, and inflammation, and may cause death by suffocation. Death by suffocation may, however, sometimes occur from the action of poisons which do not fume, e.g. sulphuric acid; the local irritation producing such great œdema and reflex spasm about the epiglottis as to cause obstruction to the respiratory passages. Sometimes, also, such poisons as sulphuric acid may pass directly into the trachea instead of the œsophagus, and thus cause very rapid death from suffocation.

Purging is usually absent and the bowels constipated in poisoning by strong alkalies or acids, and by salts of lead; the former probably act by corroding the stomach, and partially occluding the pylorus; the latter by lessening the peristaltic movements of the intestine. In the case of lead salts the abdominal pain differs from that of ordinary irritant poisons, being of a colicky nature, and to a certain extent relieved by pressure.

Secondary Effects of Irritant Poisoning.—After the immediate condition of collapse caused by the powerful action of the irritant has passed off, the local inflammation which it has produced may give rise to a general febrile condition, with hot skin, flushed face, and quick bounding pulse. This condition may be accompanied by other symptoms due to the physiological action of the poison after its absorption; thus in the case of corrosive sublimate, there may be the metallic taste, sore gums, and profuse salivation characteristic of mercurial poisoning.

One of the most important instances of the secondary effects of irritant poisons is phosphorus; after the primary symptoms of gastric irritation have passed off the patient may appear perfectly well, and then vomiting and purging may set in a second time. These are due, not to the local action of the phosphorus which has been swallowed on the stomach and intestines, but to the changes in the liver, blood, and other organs, which the phosphorus has produced after its absorption. A similar condition has been observed in poisoning by arsenic, but usually the symptoms of arsenical poisoning are continuous, and do not exhibit a distinct intermission of this kind.

Death may occur from the secondary action of some poisons a good while after the primary symptoms have disappeared; thus strong acids and alkalies may produce death, weeks or even months after they have been swallowed, from the effects of their local action on the œsophagus or the stomach. During the passage down the œsophagus they may destroy the muco-

embrane to such an extent that when it heals and the cicatrix egins to contract, the lumen of the tube may be completely bstructed, so that no food can reach the stomach, and the atient dies of starvation; or the mucous membrane of the omach may be destroyed to such an extent that what remains insufficient to digest the food, and the patient dies from non-ssimilation.

ACTION OF DRUGS ON THE LIVER.

The liver is by far the largest organ in the body, and it is aced in a very peculiar situation. It acts as a porter or door-eeper to the circulation, all the substances which are absorbed om the intestinal canal having to pass through the portal vein nd the capillaries of the liver before they can enter the general rculation.

Since the discovery by Ludwig and Schmidt-Mülheim that eptones are poisonous when injected directly into the circulation, he liver has acquired a new importance. Schiff and Lautenbach ndeed had previously made some experiments which they thought howed that a subtle poison existed in the blood even of healthy nimals, but was destroyed by the liver. They based this idea on he observation that ligature of the portal vein causes death in nimals with very much the same symptoms as when they are led to death. Ludwig had formerly explained this phenomenon y supposing that the ligature caused the blood to accumulate n the large and dilatable portal radicles and prevented it from etting into the general circulation again. The animal was thus, s Ludwig expressed it, bled to death into its own veins. Schiff nd Lautenbach, however, thought the symptoms were due ather to poison than to this mechanical alteration in the circu-tion, because they found that when the blood of an animal hose portal vein had been ligatured was injected into a frog, produced death within three hours, whereas blood from a milar animal whose portal vein had not been ligatured produced o effect.

The liver therefore seems to have a most important function n destroying the poisonous properties of peptones, and per-aps other substances produced during digestion, and possibly lso of poisonous products of tissue-waste. The peptones are onverted by it into sugar and glycogenic substance.[1]

Drugs which act on the liver are usually divided into hepatic timulants and cholagogues, and into hepatic depressants.

It has been for a very long time a matter of clinical experience hat the administration of mercurial purgatives was frequently ollowed by the discharge of greenish bilious-looking evacuations

[1] Seegen, *Pflüger's Archiv*, xxviii. p. 990.

and a great improvement in the general condition of the patient. These two results were classed together as cause and effect, and the improvement was considered to be due to the removal of bile. It was then supposed that the bile was formed in the blood and




FIG. 142.—Diagram to show the effect of artificial circulation of blood through the liver, under different pressures. The continuous lines indicate the size of the liver, and the arrangement of the apparatus during circulation, under a low pressure. The dotted lines indicate the increased size of the liver, and the arrangement of the apparatus, under a high pressure.

simply excreted by the liver, and, therefore, the bilious-looking stools were ascribed to stimulation of the secreting function of the liver by the mercurials. Hepatic stimulants and cholagogues were therefore considered to be identical. We now know that the bile is formed in the liver and not simply excreted by it from the blood, and that bile formed in the liver may again be absorbed into the blood. Increased functional activity of the liver might thus lead to the presence of a greater instead of a less quantity of bile in the blood. Recent experiments have also shown that one of the most marked cholagogues which we know, viz. calomel, appears rather to diminish than to increase the actual secretion of bile, so that we are now obliged to distinguish between hepatic stimulants and cholagogues. **Hepatic stimulants** are drugs which increase the functional activity of the liver, and the amount of bile which it forms. **Cholagogues** are substances which remove bile from the body, possibly by acting rather on the intestines; they do not necessarily increase the secretion of bile, they may only prevent its re-absorption and thus diminish the quantity in the circulation. **Hepatic depressants** are drugs which lessen the quantity of bile secreted by the liver.

In relation to tissue-waste it is not to be forgotten that the products of the functional activity of one organ are not only poisonous to itself, but may be poisonous to other organs. Thus the waste products of muscular activity gradually poison the muscle and prevent its contraction, although as soon as they are washed out with salt solution the muscle recovers its power.

Lactic acid also, which is a product of muscular waste, is poisonous not only to muscle but to some extent to nerves, and

ssens the functional activity of the brain and produces sleep. t the same time it is possible that these waste products, poisonous themselves, may through slight changes be rendered available r nutrition, just as peptones which are themselves poisonous re most important foods.

Besides acting on peptones, the liver seems to have the power f destroying the poisonous properties of some **vegetable lkaloids.** For example, $\frac{1}{20}$th of a drop of nicotine given to a og does not produce death, but $\frac{1}{40}$th is sufficient, when the ver has been previously removed. Coniine, cobra poison and yoscyamine, all exert much less poisonous action after they ass through the liver, before they reach the general circulation, an they do when injected directly into the blood. Curare, russic acid, and atropine, on the other hand, do not have their ction modified.[1]

The result of these experiments may be partly explained on he supposition that a good deal of the **poison** has been **ex-reted** along with the bile, and has thus been prevented from eaching the general circulation. But it is probable that in ldition to the function of excreting poisons, the liver has also ot the power of destroying poisons, and, it may be, the power f removing poisons from the circulation by merely storing them or a time.

In relation to this subject it is interesting to bear in mind hat alkaloids to which the name of ptomaïnes has been given p. 99), are formed in dead bodies during the process of decom-osition, and that when a solution of peptone is treated with otash and ether it yields a body which appears to be a volatile lkaloid. If putrid peptone is treated in the same way, a solid on-volatile alkaloid is obtained.[2]

Ptomaïnes are not only formed in dead bodies, they are also ormed in the intestine by the decomposition of parts of its con-ents. They have been found in large quantities by Bouchard oth in the stools of persons suffering from diarrhœa or typhoid ever, and in normal fæces. They appear to be absorbed from he intestine into the blood and excreted by the urine. They ave been found by Bouchard in the urine both in health and isease, and Bocci has shown that the human urine has a para-ysing action on frogs like that of curare, or of the ptomaïnes hich Mosso and Guareschi have obtained from putrefied fibrin r brain.

Some time ago I pointed out[3] the resemblance between the anguor and weakness which occur in many cases of indigestion nd the symptoms of poisoning by curare, and drew attention to

[1] Lautenbach, *Philadelphia Medical Times*, May 26, 1877.
[2] Tanret, *Comptes Rendus*, xcii. 1163.
[3] Lauder Brunton, 'Indigestion as a Cause of Nervous Depression,' *Practitioner*, ol. xxv. October and November 1880.

the probability that the languor was due to the effect of poisonous substances absorbed from the intestine. These I considered to be probably peptones, but it is possible that they may be ptomaïnes. But whether the poisonous substances be peptones or ptomaïnes, the function of the liver is equally important in preventing them from reaching the general circulation.

Bearing in mind, then, the office of the liver as a porter to prevent the passage of injurious substances from the intestinal canal into the blood, and the great effect that any alteration in the circulation through it may produce upon the circulation, and consequently on the functions of all the intestinal organs, we shall much more readily understand the importance of this gland, the largest in the body, than if we look upon it simply as an instrument for secreting the bile which plays a useful, but still subordinate part in the process of digestion.

We are still but imperfectly acquainted with its functions, but we may say that they are at least five:—

1st, to **form** and **store up glycogen**, a material which will afterwards be used in evolving heat and muscular energy; it will thus, as it were, perform the office of a kind of coal-bunker to the body;

2ndly, to **secrete bile** for use in digestion;

3rdly, to **excrete bile**;

4thly, to **destroy peptones** which are poisonous when they are directly introduced into the general circulation, and to convert them into glycogen, &c.;

5thly, to **destroy** or store up and **excrete** other organic **poisons** which may have been formed in the alimentary canal during the process of digestion, or may have been introduced into it from without.

The **glycogenic function** of the liver is influenced by a number of drugs, especially phosphorus, and substances belonging to the same chemical group. Phosphorus, arsenic, and antimony, all destroy the glycogenic function, and at the same time tend to cause fatty degeneration of the organ. It is possible that these effects of the poisons are closely connected, but the exact connection between them has not yet been ascertained.

In consequence of the disappearance of glycogen from the liver which is caused by these drugs, puncture of the fourth ventricle will no longer cause glycosuria in animals which have been poisoned by them. Attempts have been made to utilise this fact in the treatment of diabetes, but as yet the results have not been very satisfactory.

Hepatic Stimulants.—The action of drugs on the **secretion** of the liver has been very carefully studied by some observers, especially by Röhrig, Rutherford, and Vignal. The mode of experimenting was to curarise a dog, ligature the common bile-

duct and insert a cannula into it. The bile was thus entirely prevented from reaching the intestine, and the whole of it flowed through the cannula into a vessel in which it was collected, so that the amount secreted in a given time was readily estimated. The drug was then administered, usually by injection into the duodenum, and the increase or diminution which this caused in the bile was noticed.

The ingestion of food greatly increases the secretion of bile, and in order to get rid of this disturbing factor, the experiments were all made on fasting animals.

A great number of drugs were experimented upon, some of which were found to stimulate the liver, and increase the quantity of bile without altering its quality, so that their action upon the liver would be nearly analogous to that of laxatives upon the intestine; others increased the quantity of bile, and rendered it more watery; others again had little effect upon the liver, but stimulated the intestinal secretion and movements.

The following are hepatic stimulants :—

Acid, dilute nitro-hydro-chloric.[1]	Ammonium benzoate.[2]	Podophyllin.[1]
Aloes.[1]	Baptisin.[2]	Sanguinarin.[1]
Rochelle salt.[3]	Euonymin.[1]	Colchicin.[1]
Sodium sulphate.[2]	Hydrastin.[2]	Colocynth.[1]
Sodium phosphate.[1]	Juglandin.[2]	Jalap.[2]
Potassium sulphate.[2]	Iridin.[1]	Rhubarb.[2]
Mercuric chloride.[1]	Leptandrin.[2]	Ipecacuanha.[1]
Sodium salicylate.[1]	Phytolaccin.[1]	Physostigma [3] (extract).
Sodium benzoate.[1]		

Those drugs which stimulate the intestine much, as a rule increase only slightly the secretion of bile by the liver, and podophyllin, which in certain doses acts as a powerful hepatic stimulant, ceases to have this effect when it produces marked purgation. These effects occur independently of the action of the drugs on the re-absorption and re-secretion of bile, inasmuch as in the experiments quoted the whole of the bile was collected directly from the liver and not allowed to pass at all into the intestine. A large number of substances belonging to the aromatic series act powerfully on the liver. Some of them, like salicylate of sodium, greatly increase the watery constituents of the bile, so that it is not only more abundant, but much more dilute than normal. Others of them, e.g. toluylendiamine, increase the solids to such an extent that the bile becomes so viscid that it cannot flow through the bile-ducts, and being absorbed gives rise to jaundice. A number of bitters belong to the aromatic series (p. 364).

[1] The most powerful stimulants in the preceding list are indicated by (1), the less powerful by (2) and (3).

It seems not improbable that by further observations many aromatic compounds may be arranged in a regular series, according to their action on the solid and liquid constituents of the bile.

Cholagogues.—In making experiments, similar to those of Rutherford and Vignal, Schiff observed that the secretion of bile was very much greater for a short time immediately after the bile-duct was tied, than it was later on; and on further investigation he found that this was due to the fact that the liver




FIG. 143.—ENTERO-HEPATIC CIRCULATION.

has a double function; it not only **forms new bile**, but **re-excretes** the **old bile** which has been re-absorbed from the intestine. A certain quantity of bile is lost in the fæces, but a considerable portion of it seems to be utilised again and again; being formed by the liver, poured out into the intestine, re-absorbed and again excreted. This circulation of bile between the intestine and the liver has been called by Lussana the entero-hepatic circulation (Fig. 143). It has been shown that the bile which is absorbed from the duodenum does not merely act as a stimulus to the liver to cause a greater formation of new bile, but is actually re-excreted, by injecting ox-bile, which gives Pettenkofer's reaction, into the duodenum of a guinea-pig, and finding that shortly afterwards the bile which issued from the gall-duct gave this reaction while the bile normally secreted by the guinea-pig does not.

Not only is bile re-excreted in this manner by the liver, but other substances also, such as **medicines** and **poisons**, are likewise **excreted**. The absorption and re-excretion take place with great rapidity, for Laffter, in some experiments made under Heidenhain's direction, found that rhubarb injected into the duodenum appeared in the bile in less than five minutes. Sub-

tances injected into the blood were also excreted by the bile vith great rapidity, so that sulphindigotate of sodium, introduced lirectly into the circulation in some experiments, began to colour he bile blue one minute after its injection. Other substances re also absorbed from the intestine and excreted by the liver nd passed round in the entero-hepatic circulation, just like the ile. Curare is one of these, and to this probably is due in a reat measure the absence of fatal effect from its introduction nto the stomach. **Iron** also circulates with the bile, and it is robable that the beneficial effect of large doses may be due in art to the action of the iron upon the liver. The objection has een raised to the employment of large doses that they are useless, nasmuch as the whole of the iron which is taken into the mouth s again expelled in the fæces, but there can be no doubt that linically large doses of iron are sometimes beneficial. Copper nd manganese also appear in the bile, and it is probable that ead and all the heavy metals pass chiefly out of the body y this channel. For the action of the liver on **alkaloids** see . 401.

It has been suggested by Lussana that the **malarial poison** lso circulates in the entero-hepatic circulation.

From the fact that bile is re-absorbed from the intestine, it s obvious that an **hepatic stimulant** which simply increases he secretion of the bile by the liver, **will not of itself act as a cholagogue** and remove the bile from the body. In order to lo this, this action must be combined with increased peristaltic ction of the bowels, which will hurry the bile out and prevent its re-absorption. If, in addition to increased peristalsis, we have increased secretion from the intestinal mucous membrane, so as to wash out the intestine, we shall get the bile still more effectually removed from the body. The necessity for such a combination has indeed been long ago shown by clinical experience, and the advantages of following a mercurial pill by a saline purgative in order to clear it away have long been recognised. Some hepatic stimulants increase also the peristaltic movements and secretions from the intestine—for example, those substances which have been already enumerated as cholagogue purgatives.

Aloes.	Colocynth.	Sulphate of potassium.
Baptisin.	Jalap.	Sulphate of sodium.
Colchicum in large doses.	Podophyllin.	Phosphate of sodium.
	Rhubarb.	Mercury salts.

In most cases, however, it is advisable to **combine hepatic and intestinal stimulants** in order to ensure a more complete **cholagogue effect.** Thus calomel as employed in Rutherford's experiments has no stimulant action on the liver, but stimulates the intestinal glands; corrosive sublimate, on the contrary,

stimulates the liver powerfully but has a very feeble stimulant action on the intestine; a combination of the two stimulates both the liver and the intestinal glands. When used in medicine, calomel is recognised to be a powerful cholagogue, one of the most powerful indeed that we possess, and it is by no means impossible that a small portion of it may be converted into corrosive sublimate in the intestine, so that we thus get from the calomel, when given alone, the combined effects of both the mercurial preparations just mentioned. It is more probable, however, that the cholagogue action of calomel is due to its having a peculiar stimulant action on the duodenum and ileum, so as to hurry the bile along the intestine and prevent its re-absorption. The reason for supposing that this is the case rather than that part of it is converted into corrosive sublimate and stimulates the liver, is that when given to dogs with a permanent fistula it does not increase the flow of bile, which it would probably do if any corrosive sublimate were formed. Another is that after the administration of calomel, leucin and tyrosin, which are products of pancreatic digestion, are found in the stools, and it seems not improbable that their appearance under such circumstances is due to their having been hurried along the intestine from the duodenum to the anus, and evacuated without time being allowed for their absorption or decomposition in the intestine.

Adjuncts to Cholagogues.—The pressure under which bile is secreted is very low, so that a very slight obstruction to its flow through the common bile-duct is sufficient to cause its accumulation in the gall-bladder and gall-ducts, and thus to lead to its re-absorption. This is readily observed in cases of catarrh either of the duodenum or of the gall-ducts. In such cases the use of ipecacuanha is indicated. This drug has been found clinically to be of great service, and it probably acts by lessening the tenacity of the mucus in the gall-duct, and thus tends to remove the obstruction in front, while at the same time it increases the pressure behind, by stimulating the hepatic secretion. The movements of the **diaphragm** have a powerful action in aiding the **expulsion** of **bile** from the liver; they do this to a certain extent in ordinary respiration, but their effect is much greater in forced inspiration. Exercise therefore tends to expel bile from the liver, and prevent its accumulation in the biliary capillaries; but a little **brisk exercise** as in riding, rowing, climbing, tennis, &c., will have in a few minutes a more beneficial action than a lazy constitutional walk of a couple of hours.

The secretion of bile is not only increased, but the **pressure** under which it is secreted is **raised** by **sipping fluids**. This is in all probability, due to nervous influence, for it has been shown by Kronecker that taking a liquid in numerous small sips will for the time completely abolish the inhibitory action of the vagus

n the heart. It is probably in consequence of this fact, that arlsbad water, when taken in numerous sips for an hour or nore, as at Carlsbad itself, is so exceedingly efficacious in hepatic iseases, while sodium sulphate, which is the main constituent of he water, was found by Rutherford to have only a very slight ction as a stimulant to the liver.

Uses of Hepatic Stimulants and Cholagogues. — The ressure under which the bile is secreted is very small, but the lood-pressure also in the portal vein is very low. In consequence f this a very slight increase in the tension of the bile within the all-ducts, or diminution of the pressure of blood in the vein, auses the bile to be absorbed. It is then carried by the circu- ation to various parts of the body and disturbs their functions. t lessens the power of the heart and appears to diminish the ctivity of the brain, so that persons suffering from biliousness nd presenting a slight icteric tinge of the conjunctiva, are apt to eel irritable, stupid, and out of sorts generally. Cholagogues re useful by removing bile from the body, and thus relieving he symptoms above mentioned. It is probable, however, that hey also in some way improve the portal circulation, and thus essen congestion of the stomach and intestines, as in Beaumont's xperiments on Alexis St. Martin (p. 369).

Hepatic Depressants.

Purgatives will act as hepatic depressants and lessen the secretion of the liver by removing from the intestine the bile which would otherwise be re-absorbed, and by hurrying out also the food which might yield materials for the secretion of new bile; but some substances, such as calomel, castor-oil, gamboge, and magnesium sulphate, were found by Rutherford to depress the secretion in cases where the bile-duct was ligatured and the animals fasting, so that in all probability the effect of the drugs in diminishing the secretion was due to their lowering the blood-pressure in the liver.

Action of Drugs on the Pancreas.

The pancreatic juice is important in the process of digestion, as it has the threefold power of converting starch into sugar, of digesting proteids with the formation of peptones, and of splitting up and emulsifying fats.

The process of secretion in the pancreas is associated with increased blood-supply as in other glands. Its nerves arise from the hepatic, splenic, and superior mesentery plexuses, with branches from the vagi and splanchnics. Electrical stimulation of the gland itself will cause secretion, and so will stimulation of

the medulla oblongata. It is arrested by powerful irritation of sensory nerves, such as the central end of the vagus, the crural, or sciatic, and by the production of nausea or vomiting.

The secretion is stimulated by the injection of ether into the stomach, and appears to be paralysed by atropine in the same way as the secretion of the salivary gland.

When fibrin is digested with pancreatic juice the solution soon begins to swarm with bacteria, and products of decomposition occur, among which is indol with a peculiarly disagreeable odour.

When calomel is added to pancreatic juice, it does not impair its digestive action upon starch, proteids, or fats, but it arrests decomposition, and thus prevents the formation of indol and scatol, although leucin and tyrosin, which are normal products of pancreatic digestion, are still formed. Salicylic acid has a similar action.[1]

After the administration of calomel the stools are often of a green colour, and this is due to unaltered bile. From the experiments on biliary fistulæ already mentioned it is probable that this bile in the motions is not due to increased secretion by the liver, but to the occurrence of diminished absorption, caused by its more rapid passage through the intestine, and possibly also to lessened transformation from the effect of the calomel in preventing its decomposition.

Anthelmintics.

These are remedies which kill or expel intestinal worms.

They have been divided into **vermicides**, which kill the worm, and **vermifuges**, which expel the worm without necessarily killing it, e.g. purgatives.

The chief worms which infest the intestine are tape-worms, round-worms, and thread-worms.

The chief Vermicides are :—

For Thread-Worms.—Local injections of alum, iron, lime-water, quassia, eucalyptol, sodium chloride, and tannin or substances containing it, as catechu, hæmatoxylon, kino, rhatany.

For Round-Worms.—Santonin, santonica.

For Tape-Worms.—Areca nut, filix mas, kamala, kousso, pomegranate, pelletierine, turpentine, chloroform.

As Vermifuges.—Castor-oil, scammony, rhubarb.

Adjuncts.—Ammonium chloride, common salt and iron, and bitter tonics, are useful internally in preventing excessive secretion of intestinal mucus, which affords a **nidus** for intestinal worms.

---

[1] *Zeitschr. f. physiol. Chem.*, vi. 2.

Uses.—They are used to destroy and remove worms present the intestine. In order that the remedies should come into more timate contact with the worms, and thus destroy them more sily, it is usual to clear out the intestine by a purgative some ours before the administration of the remedy, which is usually ven on an empty stomach, or with a small quantity of milk. fter some hours another purgative is given, in order to bring e worms away. As much mucus in the intestine forms a nidus r the worms, remedies which diminish it tend to prevent their currence. For this purpose preparations of iron and bitter nics are useful.

CHAPTER XIV.

DRUGS ACTING ON TISSUE-CHANGE.

Tonics.

THESE are remedies which impart permanent strength to the body, or its parts. When an individual is loose and limp, and feels unfit for work, like a relaxed bowstring, tonics **restore** his **energy** and strength, and again fit him for work. As their action in this respect resembles the effect of tightening a bowstring, they have received the name of **tonics**, which is derived from τόνος, tension. The feeling of **debility** may depend on many different causes. It may be due to weakness of the muscles, or weakness of the nervous system. Again, the nerves and muscles may suffer because the circulation is languid and feeble, or because the blood which supplies them is deficient in oxygen, or in nutritive matter. These deficiencies again may depend on **deficient nutrition**, due to want of appetite, so that too little food is consumed, or to an improper or insufficient diet, or to imperfect digestion, so that the food is not assimilated. But weakness may be also induced by the **accumulation** of **waste-products** in the body, which interfere with the functional activity of the muscular and nervous systems; and these products may accumulate because they are formed in excess in the tissues themselves by overwork, or in the intestinal canal from imperfect digestion or because they may be allowed to pass too readily from the intestinal canal into the blood by deficient action of the liver.

Or their excretion may be defective from the kidneys being insufficiently active, or the bowels constipated.

The mode of action of tonics is so manifold that they have been divided into blood tonics or hæmatinics, vascular tonics, gastric tonics, intestinal tonics, and nervine tonics.

Uses.—In order to ascertain what form of tonic is required it is necessary to determine carefully what part of the organism is in fault. In very many cases the imperfect functional activity in the body generally, which exhibits itself in languor and weakness, is due to accumulation of waste-products, and not to deficient nutriment. In such cases the plan of loading the stomach with food, and giving iron, wine, and beef-tea, simply

creases the mischief. If it is found, on examination of the ine, that the kidneys are not excreting a sufficient quantity solids, and especially of urea, it is necessary to diminish the antity of food, and especially of animal food, as all, or nearly l, the nitrogen taken into the body must be excreted by the dneys.

In order that no unnecessary work be thrown on the kidneys, e must, as far as possible, prevent products of imperfect diges- on from being absorbed from the intestinal canal, and therefore e state of the liver must be carefully attended to, and the owels themselves carefully regulated.

In cases where the debility does not depend upon excessive aste-products in the blood and tissues, but upon defective oxida- on due to deficiency of hæmoglobin, the patient must be treated **hæmatinics** such as iron, cod-liver oil, and phosphate of lime. hen the digestion is imperfect, gastric or **intestinal** tonics ust be used as the case requires.

Where enfeeblement of the stomach appears to be present, as own by loss of appetite, and such signs of imperfect digestion as atulence or weight and pain after eating, **gastric** tonics are used. hould the muscular coat of the stomach be feeble or inactive, as own by tendency to dilatation and splashing of the contents on ovement, strychnine is especially indicated, and galvanism or ystematic kneading may be also employed. Where the stomach too debilitated to respond sufficiently to this form of treatment, s after long-continued gastric catarrh, or in old age, its work ust be partly done for it, and then such **digestives** as hydro- hloric acid and pepsin are useful. When the muscular move- ents of the intestine are sluggish, as indicated by constipa- ion and by a tendency to distension of the bowel with gas, nux omica and belladonna may be given; and when its mucous embrane appears to be relaxed and flabby, and secreting too rofusely, the mineral acids, astringents, and metallic salts may e of much service. When the pulse is soft and feeble, and there s a tendency to vascular dilatation, either general or local, as hown by local congestion and œdema of the dependent parts, r by drowsiness in the upright position and sleeplessness in the ecumbent posture, **vascular** tonics are serviceable. **Nerve** onics are used where the nervous functions are imperfectly per- ormed, as shown by dulness, loss of memory, incapacity for work, languor, paralysis, or tendency to spasm, as in chorea. As the functions of the nervous system depend very greatly upon he quality of the blood with which it is supplied, and on the apidity of the circulation, the other tonics frequently require to e given in addition to nervine tonics.

Hæmatinics.

Blood-tonics, blood-restoratives, analeptic tonics.—These are generally remedies which improve the quality of the blood; but the name blood-tonics or hæmatinics is generally applied specially to such remedies as **increase** the quantity of red blood-corpuscles and **hæmoglobin** in the blood. The quality of the blood depends upon a number of conditions: upon the amount and nature of the food ingested, on the digestion, on the formation and excretion of the various products of tissue-change, and more especially on the formation and destruction of the red blood-corpuscles themselves.

The red **blood-corpuscles** are probably **formed** in the spleen, the medulla of bones, the liver, and possibly other parts of the body, from leucocytes which lose their nucleus, take up hæmaglobin, and alter their form to that of the red corpuscles.

The red corpuscles are probably **destroyed**, at least to a great extent, in the liver, and probably also in the spleen. The colouring matter of bile contains a quantity of iron, and appears to be formed from hæmoglobin.

An abnormal condition of the liver, by leading to excessive destruction of blood-corpuscles, may therefore be an important cause of anæmia. The corpuscles contain albuminous matters as well as hæmoglobin, and deficiency of albumen in the blood will lead to anæmia. Thus, in cases of Bright's disease, the loss of albumen through the kidneys tends to produce anæmia, and this must be combated by lessening the loss, if possible, as well as by supplying albumen.

The blood-corpuscles also contain fat, and deficiency of fatty food will tend to produce anæmia. Cod-liver oil, on the other hand, which is an easily assimilated form of fat, is a powerful hæmatinic. In anæmia there is a deficiency of iron in the blood, and chalybeate preparations are among the most powerful of all hæmatinics.

One well-marked disease due to imperfect nutrition is scurvy. In it there is not only a deficiency of red blood-corpuscles, but a tendency to extravasation. Its pathology is not definitely made out, and it has been supposed to be due to a deficiency of salts of potassium in the blood, but it is much more likely that it is due to increase in the chlorides, and especially chloride of sodium, either absolutely or relatively to the carbonates.

Excess of chloride of sodium causes the blood-corpuscles to pass out of the vessels (p. 63), and potassium salts alone, or beef-tea, which contains them, do not cure scurvy; but it is removed by fresh vegetables or by lime-juice.

Alteratives.

These are remedies which **improve** the **nutrition** of the body thout exerting any very **perceptible action** on individual gans. The chief alteratives are :—

Arsenic.	Colchicum.
Mercury.	Guaiacum.
Iodine. Iodides.	Stillingia.
Cod-liver oil.	Sanguinaria.
Sarsaparilla.	Xanthoxylum.
Sulphur.	Mezereum.
Gold.	

Action.—Healthy nutrition depends (1) upon a proper supply oxygen and nutriment to each tissue and organ in the body,) on the proper amount and kind of tissue-change in the vari- is cells ; (3) on the proper removal of waste.

The proper supply of oxygen and of nutriment to the body enerally will depend upon the state of the respiratory and gestive organs ; their proper supply to the tissues, as well as e removal of waste from them, will depend upon the circu- tion ; and the removal of waste from the body generally will epend upon the bowels, skin, and kidneys.

The drugs which act upon the different organs just men- oned are considered under other headings, but the changes hich take place in the tissues themselves appear to be effected y drugs which produce no marked corresponding changes in ssimilation, circulation, or excretion. It is uncertain how they ct : it is possible that they may alter in some way the action of nzymes in the body, but it is also possible that they act by re- lacing the normal constituents of the tissues and forming ompounds which tend to break up in a different way from those hich are ordinarily present.

Thus chloride of sodium and nitrogenous bodies such as albu- nen are amongst the most important constituents of the body ; nd we find that among the chief alteratives are substances hich will replace chlorine, sodium, or nitrogen in many com- ounds. Thus we have iodine and iodides, and nitric or nitro- ydrochloric acids, which will displace or replace chlorine. We ave chlorine itself, and chlorides which may alter the proportion f chlorides to other salts in the blood and tissues, and thus modify the solubility of various constituents of the tissues. We ave salts of potassium and calcium, which may replace those of sodium ; sulphur, and sulphides which may replace oxygen ; phos- phorus, hypophosphites, antimony and arsenic, which may replace nitrogen ; mercury and its salts, which may replace calcium.

Besides these we have organic alteratives, regarding the action of which we can at present form no hypothesis unless

they influence the processes of digestion. Nitro-hydrochloric acids, taraxacum, and small doses of mercurials, probably act either by modifying the digestion of food in the duodenum and jejunum, or by modifying the changes which it undergoes in the liver after absorption.

The action of drugs upon tissue-change has usually been investigated by ascertaining the amount of urea excreted before, during, and after the administration of a drug. Most of the older experiments on this subject are of little or no value, as sufficient care was not taken to ensure that the amount of nitrogenous food consumed each day during the experiment was exactly the same. As all the nitrogen taken in the food reappears in the urine, any irregularity in the quantity introduced into the body will cause a corresponding irregularity in the quantity excreted. After this fact was ascertained the plan adopted by some experimenters was to deprive an animal of food for several days, until the excretion of urea due to the gradual destruction of its nitrogenous tissues became nearly constant. The plan now adopted is to give to a dog or a man a quantity of food of a uniform quality and the amount of nitrogen in which is exactly known. The quantity given each day is exactly weighed. The same amount of nitrogen is thus introduced into the organism every day, and therefore any variations in the amount of nitrogen excreted must be due to changes in the organism itself.

Observations on the excretion of urea only give us a very partial and imperfect knowledge of the process of tissue-change, and they ought to be combined, as in the experiments of Pettenkofer and Voit, with observations on the amount of oxygen absorbed and of carbonic acid given off. Such experiments as these, although very valuable, are very laborious, and comparatively few have hitherto been made.[1]

From experiments made with those necessary precautions just described it has been found that free consumption of water increases tissue-change very considerably, as is shown by the increased excretion of urea.

Common salt, sulphate of sodium, phosphate of sodium, acetate of sodium, borax, nitrate of potassium, chloride of ammonium, carbonate of ammonium, and probably all salts which pass out in the urine carrying water with them, somewhat increase tissue-change and the amount of urea excreted. Fats and fatty acids apparently lessen the decomposition of albuminous tissues and the excretion of urea, but glycerine has no action of this sort. Alcohol in small or moderate doses lessens, in large doses increases, tissue-change. Benzoic acid, salicylic acid, and benzamide, all increase tissue-change. Contrary to what perhaps might have been expected, tea, coffee, and cocoa have no action whatever on the excretion of urea.[2] The experiments which seemed to show that they diminished it, appear to have been made without the necessary precautions. Morphine slightly diminishes the excretion of urea, but its action is much more marked on the consumption of oxygen and excretion of carbonic acid. These ar

[1] A complete account of the whole subject is given by Voit in Hermann's *Handb. d. physiol.*, Band VI. Theil i. This contains also complete references to the literature.

[2] Voit, *op. cit.*

eatly increased in the stage of excitement, and greatly diminished the stage of quiescence. It would appear that these changes e not due to the direct action of the morphine, but only to the erations of muscular activity which follow its administration.

Quinine lessens tissue-change, iron appears to increase it, ercury also slightly increases it,[1] while iodine appears to have le influence upon the quantity of urea excreted. This fact is itself, I think, sufficient to show that the mere estimation of the antity of urea excreted before and after the administration of drug is quite insufficient to give us any precise information garding its action on tissue-metamorphosis.

Antimony, arsenic, and phosphorus have a special action on sue-change, and powerfully affect the glandular, nervous, respitory, and cutaneous systems. In large quantities they affect e liver very markedly, producing fatty degeneration; and this so occurs in other tissues.

This **fatty degeneration** is due to a twofold action:—1st, creased tissue-metamorphosis; and 2nd, diminished oxidation. the normal condition albuminous tissues split up as indicated low:—

Albuminous tissues	split up into	Non-nitrogenous substances. e.g. Fat, &c.	converted in health into	Carbonic acid, excreted by lungs.
		Nitrogenous substances e.g. Leucin, Tyrosin, &c.		Urea, excreted by kidneys.

In poisoning by antimony, arsenic, and phosphorus, the nitronous products of tissue-waste appear in much larger quantity the urine than normally, owing to the increased decomposition hich is going on. They may appear in the urine in the form of excessive quantity of urea, as in cases of phosphorus-poisoning the dog, but in man they may appear in the form of leucin d tyrosin. Owing to the diminished oxidation the non-nitronous substances remain in the body as fat, instead of being idised and passing out of the body as carbonic acid.

The exact nature of their effect on the nervous system has t been made out. Their action on the skin and epithelial cells the lungs seems to be that of causing fatty degeneration.

Fatty degeneration of the liver occurs also in poisoning by lts of silver.

Mercury has a peculiar power of breaking up newly deposited rin and of causing disorganisation of syphilitic deposits. Iodine, dides, and probably also chlorides, appear to act on the lymphic system and promote absorption: their action is specially ell-marked in cases of glandular enlargement.

Uses.—In general malnutrition without definite symptoms, ercurials, taraxacum, and nitro-hydrochloric acid are used and

[1] Boeck, quoted by Voit, *op. cit.*

are especially indicated where the liver is suspected to be in fault, as where there are symptoms of biliousness, and also where oxalates and urates are found abundantly in the urine.

In gout, salts of potassium and colchicum are used. Phosphorus and arsenic are employed in nervous debility: and they, as well as antimony, are serviceable in neuralgia, chorea, and other nervous diseases.

In diseases of the skin, arsenic is chiefly employed.

In diseases of the respiratory organs, antimony is very serviceable when the attack is acute; and arsenic is most valuable in some chronic conditions, especially in chronic consolidation, where it probably acts by producing fatty degeneration and softening of the effusion, so that it is either absorbed or expectorated.

Mercury is employed specially to break up deposits of lymph and to prevent adhesions, as in iritis and pericarditis; and is also used and is most serviceable in the treatment of syphilis. It is most generally employed in the secondary stage of this disease: in the third stage it is either given along with, or entirely replaced by the use of, iodides.

Antipyretics, Febrifuges.

These are remedies which reduce the temperature of the body in fever. They act much more powerfully when the temperature is abnormally high than when it is normal.


The constant temperature of warm-blooded animals depends upon the maintenance of a proper balance between the amount of heat generated in the body, chiefly by oxidation, and the amount given off to the surrounding medium—air or water. The heat is chiefly generated in the muscles and glands. It is chiefly given off by the skin, although some is also lost by the lungs, etc.

A little heat, but not much, may be given off by radiation alone. The power of dry air to take up heat is very slight, and so the skin is not much cooled, and very little sensation of cold is felt at temperatures much below 0° if the air is both still and dry. If the air be moist its capacity for heat is much greater, and the loss of heat from the skin being much more rapid, a person may actually feel the weather colder at 4° F. than at −40° F. the air being still in both cases. If air, either dry or moist, is in motion, so that fresh portions of it come successively into contact with the skin, the loss of heat is much more rapid, and a little wind will render even dry air unbearably cold at a temperature which would be quite supportable if the air were still.

Loss of heat occurs more readily in small animals than in large. This is represented diagrammatically in Fig. 144.


It is to be observed that during sleep the action of the vasomotor centre is less, the vessels of the surface dilate, and loss o

eat, with danger of consequent chill, takes place more rapidly. or the effects of local chill to the surface, the results of Rossach's experiments may be consulted (p. 251).



G. 144.—Diagram to show that loss of heat occurs more readily in small animals than in large. The unshaded part in *a* and *b* represents the surface through which heat is lost; the black part shows the heat-producing part of the body. These are shown separately in *a'* and *b'*, from which it is evident that in the small animal the heat-producing area is about the same size as, while in the large animal it is double the size, of the heat-dispersing area.

But heat may be generated in muscles and glands apart from he circulation in them, and Sachs and Aronsohn have shown hat a centre regulating the production of heat is situated in the



IG. 145.—Diagram to illustrate the action of alterations in the circulation of the surface of the body and the internal organs and muscles upon temperature. In this figure the superficial vessels are represented as contracted, and there is therefore not only less loss of heat, but the blood being driven to the internal organs and muscles, the circulation in them is increased and the production of heat augmented. The parts where heat is produced are the dark, the darkness being in proportion to the greater production. The parts where heat is retained without much being formed, e.g. the blood, are moderately shaded. Those where heat is lost are left white. In the intestine heat is both formed and lost (p. 418), and so the intestines are partly dark and partly light.

neighbourhood of the corpora striata.[1] It is probable that the emperature may be affected by drugs acting on the nervous

[1] *Deutsche med. Wochenschr.*, December 1884.

system apart from the circulation and also by drugs which affect the tissues themselves (p. 58 *et seq.*).[1]

The circulation exercises a very important influence upon (1) the amount of **heat lost** from the surface and (2) the amount of **heat produced** in the internal organs and muscles. This is represented diagrammatically in Figs. 145 and 146.





FIG. 146.—Diagram to illustrate the action of alterations in the circulation of the surface of th body and the internal organs and muscles upon the temperature. In the diagram the cutaneou vessels are represented as dilated, and thus not only is more heat lost from the surface, but blood being withdrawn from the internal organs and muscles, the circulation in them is lessene and less heat produced.

The vessels of the skin form a cooling apparatus (p. 440) while heat is generated in the muscles, voluntary and involuntary and in glands, e.g. the intestine and liver. The intestine is however, only protected by the thin abdominal walls from th cooling action of the external air, and so it may act either i cooling or warming the body, according to circumstances.

When the vessels of the surface are dilated, the blood no only courses freely through them and becomes cooled, but, bein withdrawn from the muscles and glands, there is less heat pro duced. The reverse is the case when the cutaneous vessels ar contracted. The condition of the vessels depends on the actio of the vaso-motor centre, and drugs acting upon it may greatl modify the temperature.

Antipyretics may be divided into two great classes: thos which **lessen** the **production** of heat, and those which **increas** the **loss** of heat; and these again may be subdivided as show in the following table:—

[1] Umbach, *Archiv f. exp. Path. u. Pharm.* 1886, xxi.



The mode of action of those which affect the blood and sues themselves has already been considered tolerably fully der the head of 'Oxidation of Protoplasm' (p. 67). They pear simply to diminish the temperature by lessening oxi- tion. The mode of action of antipyretics which produce eir effect through the circulation, has not been investigated detail with satisfactory exactitude, but it is supposed that by ssening the rapidity of the circulation through those parts of e body in which the increased tissue-change is taking place, e temperature is reduced.

Blisters will have this effect locally by causing contraction of e vessels in the inflamed part, as already described under the ad of Counter-Irritants (p. 343).

Antipyretics, which increase the **loss** of **heat**, may do so (1) causing greater dilatation of the vessels of the skin, and thus

[1] Bettelheim, 'Ueber das Antipyrin,' *Wien. med. Jahrbücher*, 1885.

allowing a quicker radiation of heat from the body; (2) by augmenting the secretion of **sweat**: and thus carrying off heat by means of evaporation (see Diaphoretics, p. 440); or (3) they may actually **remove warmth** from the body, as cold baths, cold affusion, cold sponging, wet packing, cold enemata, or ice to the surface.

Uses.—Antipyretics are used to **lower** the **temperature** when it has risen above the normal, whatever be the cause. A high temperature may be produced simply by prolonged exposure to heat. This exposure and the rise in temperature it occasions, seems to induce increased tissue-change, and this increase of the tissue-change will keep up a febrile temperature, even after the external temperature has fallen. Such thermal fever is found in warm climates, and in it quinine injected subcutaneously seems to be very efficient.

A high temperature may also occur from specific fevers, as typhus, typhoid, scarlet fever, measles, and acute rheumatism. The most rapid and powerful antipyretic in such cases is the application of cold by bathing, or sponging; and probably next in efficiency come large doses of quinine or salicylate of sodium. In typhoid fever, salicylate of sodium does not seem to act so rapidly as it does in acute rheumatism.

Venesection, though formerly the antipyretic which was chiefly relied upon, has now fallen to a great extent out of use—probably from its having been very much abused.

In persons suffering from acute inflammation of the lungs or bronchi, where the amount of lung-tissue which remains sound is insufficient to aërate the whole mass of blood, and the patient is becoming livid, small bleedings are serviceable; they not only relieve the breathing, but lessen delirium which may be present.

Venesection lowers the temperature for a short time, but it soon rises again in many cases, so that bleeding alone is by no means a powerful antipyretic,[1] unless the quantity of blood abstracted be so great as probably to injure the patient seriously; yet in combination with other antipyretics it may sometimes be of very great service.

Local bleeding by **leeches** or by **wet cupping** sometimes gives very great relief, lessening both local inflammation and the general symptomatic fever consequent upon it, in pneumonia, pleurisy, pericarditis, peritonitis, &c. In such cases blisters may be used to diminish the local inflammation, and thus aid the action of other antipyretics.

Vascular antipyretics, such as aconite and digitalis, also seem to be of more service in symptomatic fever than they are in specific fevers.

---

[1] Wunderlich's *Medical Thermometry*, pp. 118, 134, 378, New Sydenham Society's edition.

Purgatives take an intermediate place between antipyretics which lessen the production of heat by acting on the tissues, and those which act on the circulation. They diminish the force of the circulation, and may in this way lessen the production of heat. But it is not impossible also, although this is a point on which we have not sufficient information, that they may do so by removing from the body substances whose effect when present in the circulation or tissues would be to maintain the high temperature.

Amongst antipyretics which increase the loss of heat we have: first, alcohol, which is included also in the former list of those which lessen the production of heat, for it appears to act in both ways, both diminishing oxidation and also increasing the loss of heat. It does this by dilating the vessels of the skin and allowing free radiation from the surface, and also by the cooling effect of evaporation of the sweat, although its action as a sudorific is not very marked. Antipyrin seems to act in a similar manner.

We have also the whole class of **sudorifics** (p. 440). One of the most useful of these in checking a febrile condition just at its outset is a dose of compound ipecacuanha powder, or Dover's powder, which has now, to a great extent, taken the place of the older remedy having a somewhat similar action, viz. antimonial powder, or James's powder.

Another mixture in great favour is acetate of ammonium and spirit of nitrous ether. The most powerful, however, of all remedies which increase the loss of heat is the application of **cold** water or ice. The mode of applying these is discussed at page 464.

CHAPTER XV.


ACTION OF DRUGS ON EXCRETION.

ACTION OF DRUGS ON THE KIDNEYS.

THE kidney has a twofold office. It has (1) to regulate the amount of water in the body under various conditions; (2) to remove the products of tissue-waste. These products must be removed in a state of solution from the part of the kidney where they are excreted, and yet sometimes provision must be made for the water, by which they are washed out, being retained in the body. The urine in mammals and amphibia is liquid; in birds and reptiles it is semi-fluid or solid, yet the solid constituents are removed in solution from the urinary tubules, and the water in which they are dissolved is afterwards absorbed. We may say then that the kidney has not only a twofold, but a **threefold action**:—1st, the **excretion** of **waste**-products; 2ndly, a provision for the **removal** of excessive **water**; and 3rdly, an arrangement for the **retention** of **water** in the body by its re-absorption after it has washed out the waste-products. On looking at the kidney we find three structures which seem to be connected with these three functions, viz.: (1) **convoluted tubules** with epithelial cells, which in all probability are the chief structures for excreting waste-products; (2) the **Malpighian corpuscles** for excreting water along with some solids, and (3) usually one or more **constrictions** in the tubule which may serve the purpose of preventing too rapid exit of the water, and thus allow time for its re-absorption in cases where its retention is desirable, as for example on a hot day and when the supply of drinking-water is very limited.

The process of **secretion** in the kidney was regarded by Bowman as consisting of the filtration of water from the vessels of the glomeruli into the tubules, and the excretion of waste-products by the epithelium lining the tubules. Ludwig, however, came to look upon it rather as a process of filtration and re-absorption; a dilute solution of urea and salt being, according to him, poured out from the Malpighian corpuscles and gradually concentrated by the absorption of water in its passage along the tubules. This theory had so many facts in its favour that it was

r a good while exclusively adopted, but latterly Heidenhain, in admirable series of experiments, has shown that such sub-ances as indigo are certainly excreted by the epithelium of e tubules. At the same time Hüfner has shown, by a com-rison of the structure of the kidney in fishes, frogs, tortoises, rds, and mammals, that the form of the tubules closely rees with that required for the re-absorption of water in each se. Fishes have a low blood-pressure, and so the resistance the kidney requires to be small in order to allow of the secre-on of urine. Living as they do in water, they do not require y apparatus for its retention in the body. In them therefore



G. 147.—Diagram showing the form of the urinary tubules in different classes of animals, after Hüfner. 1. Fish. 2. Frog. 3. Tortoise. 4. Bird. 5. Mammal. The letters have the same signification in each. *a*. Capsule of the glomerulus. *b*. Convoluted tubule. *c*. Loop. *d*. Collecting tubule. *u* in 2 indicates the transverse section of the ureter.

ne tubule is short and wide, and destitute of any constriction hich would retard the outflow of the fluid. In frogs there must e ample provision for the retention of water in the body, as vaporation takes place freely from their skin. In them we find, s we might expect, that the tubule, and especially the contracted art of it, is very long. In tortoises no evaporation from the kin can take place, and in them the contracted part of the ubule is short. This renders it probable that, while the ideas dvanced by Bowman and supported by Heidenhain are in the nain true, the **re-absorption** of water on which Ludwig lays so nuch stress is also an important factor in the secretion of urine nder different circumstances.

But it is not only rendered probable by the facts of compara-

tive anatomy; it appears to be proved by direct experiment. Ribbert[1] has extirpated the medullary substance of the kidney in the rabbit while leaving the cortical substance. He has thus succeeded in collecting the urine as it is excreted by the Malpighian corpuscles before it has passed through Henle's loops, and has found that the urine secreted by the cortical substance alone is much more watery than that which is secreted by the entire kidney—a fact which appears conclusively to prove that water is actually re-absorbed, and the urine rendered more concentrated, during its passage through the tubules of the medullary substance.

In the frog and triton the arrangement of the kidney is such as to allow of a much more complete investigation of the different factors in secretion, than in mammals, because in amphibia, the glomeruli which separate the water and the tubules which excrete the solids, receive their blood-supply to a great extent independently. The glomeruli are supplied by branches of the renal artery. The tubules are supplied by a vein which proceeds from the posterior extremities and, entering the kidney, breaks up into a capillary plexus bearing a somewhat similar relation to the renal tubules as that which the portal vein does to the lobules of the liver. It is therefore called the portal vein of the kidney.

The arterial circulation in the glomeruli and the venous portal circulation round the tubules are not entirely distinct, for the efferent arteries of the glomeruli unite with the portal capillaries, and, moreover, arterial twigs also pass directly from the renal artery into the capillary venous plexus (*vide* Fig. 148). The two systems are so far distinct that Nussbaum has been able to ascertain with considerable exactitude the part played by each in secretion, although Adami[2] has shown that the communication is freer than Nussbaum supposed. By ligaturing the renal artery Nussbaum destroyed the functional activity of the glomeruli, and by ligaturing the portal vein of the kidney he destroyed that of the tubules. By injecting a substance into the circulation after ligature either of the artery or the vein, and observing whether it is excreted or not, he determines whether it is excreted by the glomeruli or by the tubules. In this way he finds that sugar, peptones, and albumen pass out through the glomeruli exclusively, for they are not excreted when the renal arteries are tied. Albumen, however, only passes out through the glomeruli when an abnormal change has already occurred in the vascular wall; as, for example, after the circulation has been arrested for a while by ligature of the renal artery. Indigo-carmine, when injected after ligature of the renal arteries, passes into the epithelium of the tubules, but it does not give rise to any secretion of water, so that the bladder is found empty.

[1] Ribbert, *Virchow's Archiv*, July 1883, p. 189.
[2] Adami, *Journ. of Phys.*, vol. vi. 1885.

rea, on the contrary, is not only excreted by the tubules after gature of the renal artery, but carries with it, in the process of cretion, from the venous plexus, a considerable quantity of ater, so that the bladder becomes partially filled.





FIG. 148.—Diagram of the circulation in the kidney of the newt. Modified from Nussbaum.

The **excretion** of **water**, therefore, takes place in a **double** anner: it passes out through the glomeruli when the renal teries are free, and it passes out from the venous plexus along ith urea, even although the renal arteries are tied.



IG. 149.—Diagrammatic sketch of the blood-vessels in a mammalian kidney. *O* is an artery ascending into the cortical substance of the kidney; *p* is a branch from it which divides into two branches, *q* and *P*. *q* breaks up at once into a number of twigs. *P* is the afferent artery to a glomerulus, *S*, of the lowest row. *t* is the efferent vessel of the glomerulus. It divides into two branches, one of which, *u*, ascends towards the cortex, whilst the other, *v*, descends towards the medulla. (From Schweigger-Seidel, *Die Nieren*, Halle, 1865.)

In the kidneys of the higher animals (Fig. 149) and of man the glomeruli and the tubules do not receive blood from two entirely different sources; but there is an arrangement somewhat similar, for the plexus surrounding the tubules does not receive blood only from the efferent vessels of the Malpighian corpuscles, but gets it also directly from the renal arteries. There are three channels by which the blood may pass from the renal arteries into the venous plexus without going through the glomeruli. The first is the inosculation which takes place between the terminal twigs of the renal artery and the venous plexus on the

surface of the kidney directly under the capsule.[1] The second channel is formed by small branches given off directly by the interlobular arteries or by the afferent arteries before they reach the glomeruli. The former of these may be regarded as corre-




FIG. 150.—Diagram of the tubules and vascular supply of the kidney. On the left is a tubule alone in the middle is a tubule along with the blood-vessels; on the right are blood-vessels only.

sponding to the artery which passes directly to the plexus in th newt, and the latter to the branch connecting it with the afferen artery (Fig. 148). These arterial twigs are found not only nea the surface of the kidney, but also in the deeper layers of th cortical substance.[2] The third and most important channel afforded by the arteriæ rectæ, which spring from the branche of the renal artery at the boundary between the cortical an medullary substance and pass into the medulla, where the form a plexus with elongated meshes surrounding Henle's loo and the collecting tubules. Near their origin the arteriæ rect

[1] Ludwig, *Handwörterbuch d. Physiol.*, v. R. Wagner, Bd. 2.

[2] Schweigger-Seidel, *Die Nieren*, p. 67; Heidenhain, Hermann's *Handbuch Physiologie*, vol. v., Th. 1, p. 293.

inosculate with the venous plexus surrounding the convoluted tubules (Fig. 150).

Through these three channels it is possible for blood to reach the secreting structures of the kidney and there get rid of urea, salts, &c., without losing water by its passage through the glomeruli. On the other hand, if these vessels contract, while the size of the renal artery and the pressure of the blood within it remain unaltered, more blood will be forced into the Malpighian corpuscles, and thus the quantity of water excreted will be increased. At the same time the contraction of the arteriæ rectæ will probably diminish absorption from the tubules, and thus the quantity of water excreted will be increased in a twofold manner.

Circumstances Modifying the Secretion of Urine.—The experiments of Ludwig and his pupils have shown that the amount of urine secreted depends very closely upon the pressure of blood in the Malpighian corpuscles, or, to put it more exactly, on the **difference of pressure** between the blood in these corpuscles and the pressure within the tubules. For if the ureter be tied so that the pressure of urine in the tubules is increased, the secretion is greatly diminished, and even arrested, even though the pressure of blood in the renal artery be high.

A somewhat similar effect to that of ligature of the ureter is produced by ligature of the renal vein, for the blood accumulating in the venous plexus surrounding the tubules compresses them so as to prevent the flow of urine through them. A similar condition may occur from cardiac or pulmonary disease obstructing the venous circulation.

But unless under exceptional circumstances which alter the pressure within the tubules, such as compression of the tubules by congestion of the venous plexus, as in cardiac disease, impaction of a calculus in the ureter, or pressure on the ureters by dropsical accumulations or tumours, the rapidity of the **secretion** of urine depends on two factors: (1) **arterial pressure** in the glomeruli; and (2) the **composition** of the **blood.**

The **pressure** of blood in the glomeruli may be **raised**:

(1) By increase of the arterial tension generally.

(2) By increased tension locally.

Such a **general** increase may be brought about by greater action of the heart, or by contraction of the blood-vessels in other vascular areas, such as the intestines, muscles or skin, by nervous stimulation, exposure to cold, or the action of drugs.

The pressure may be increased **locally** by dilatation of the renal arteries, e.g. from section of the vaso-motor nerves, or possibly stimulation of vaso-dilating nerves.

In addition to such increase of pressure in the glomeruli by increase of blood-supply to them, we must not, however, forget the possibility of increased pressure in them by contraction of the efferent vessels leading from them, as well as of those

arterial twigs (arteriæ rectæ) which pass directly to the venous plexus surrounding the tubules, and which form no inconsiderable part of the vascular supply of the kidney.

Alterations in the size of the renal vessels were formerly ascertained simply by exposing the kidney and observing its colour, contraction of the arteries being associated with paleness, and dilatation with redness of the organ. A much more exact method has been introduced by Roy, who encloses the kidney in a capsule filled with oil and connected with a registering apparatus. When the vessels dilate, the kidney increases in size, and diminishes when they contract, so that the alterations can be readily recorded on the same revolving cylinder on which the general blood-pressure is registered by the manometer.

The **pressure** of blood in the glomeruli may be **diminished** generally:

(1) By failure of the heart's action; or

(2) By dilatation of the vessels of large areas, as the intestines, muscles, or skin.

The pressure of blood in the glomeruli may be **diminished locally** by contraction of the renal arteries, or of the afferent branches to the glomeruli.

The heart's action may fail from many causes, which have already been discussed more particularly.

Dilatation of the vessels in the skin, intestines, &c., may be caused by exposure to warmth, by the action of drugs, or by paralysis due to nervous injury.

Section of the splanchnics or of the spinal cord causes paralysis of the renal arteries, and ought, therefore, to increase the secretion of urine. This does occur, though not invariably, when the splanchnics are divided; but section of the spinal cord, by paralysing the intestinal and other vessels, lowers the blood-pressure so much that the supply of blood to the kidney is not only much below the normal, but is so small that the secretion of urine is generally almost completely arrested.

The **nerves** of the kidney consist of a number of small branches running along the renal artery and containing a number of ganglia. When these nerves are **cut** the vessels of the kidney dilate; when they are stimulated the vessels contract. A number of those fibres pass to the kidney from the spinal cord through the **splanchnics**, so that when the splanchnics are cut the vessels of the kidney usually dilate, and when they are irritated they contract.

The whole of the nerves, however, do not pass through the splanchnics, for stimulation of a sensory nerve, of the medulla oblongata, or of the spinal cord in the neck, will cause contraction of the renal vessels after both splanchnics have been cut and section of the splanchnics does not always cause the renal vessels to dilate.

The **nervous centre** for the renal arteries is probably, like the chief vaso-motor centre for the body generally, in the medulla oblongata; but in all probability there are also subsidiary centres in the spinal cord and in the solar and mesenteric plexuses.

The reason for supposing these latter centres to exist is, that stimulation of the peripheral end of the splanchnic, divided at its passage through the diaphragm, causes contraction of both kidneys, and the vessels of the kidney of the side opposite to the stimulated nerve commence to contract later than those on the same side. A delay like this in the action of the stimulus indicates that it has not acted directly, but through the medium of ganglia.

When the splanchnics are divided the vessels of the kidney sometimes dilate and the kidney increases in size; a profuse secretion of urine may take place, which quickly increases to a maximum and remains for a considerable time. This, however, is not a constant effect, and not unfrequently the vessels do not dilate, and the kidney, instead of increasing, diminishes in size. This is what to a certain extent might be expected, inasmuch as a section of the splanchnics causes dilatation of the intestinal vessels and lowers the blood-pressure, and thus diminishes the supply of blood to the kidney.

When a puncture is made in the medulla oblongata in the floor of the fourth ventricle, profuse secretion also occurs, but this differs from that caused by section of the splanchnics, in being preceded by a slight diminution, by rising rapidly to a maximum and then rapidly falling. These characters seem to show that it is due to irritation of some vaso-dilating mechanism,[1] rather than to any paralysis.

Stimulation of the vaso-motor centre in the medulla oblongata by venous blood, or by drugs such as strychnine or digitalis, has a twofold action on the kidney, for it tends to cause contraction not only in the vessels of the kidney, but in those of other parts of the body. The effect upon the kidney is thus a complicated one, for the contraction of the intestinal and other vessels by raising the blood-pressure tends to drive blood into the kidneys, at the same time that the contraction of the renal arteries tends to keep it out. When the renal nerves are cut, the renal vessels no longer oppose the entrance of blood, and therefore the renal vessels dilate very greatly when the vaso-motor centre is stimulated; but when the renal nerves are intact the result is a varying one, for sometimes contraction of the renal vessels may be so great as to prevent the entrance of blood into the kidney, however high the general blood-pressure may rise; at other times the general high blood-pressure may be able to dilate the renal arteries in spite of any resistance they may offer. These different conditions may occur subsequently to one another; and this stimulation of the vaso-motor centre may cause contrac-

[1] Heidenhain, Hermann's *Handbuch der Physiologie*, vol. v. Th. 1, p. 366.

tion of the renal vessels, succeeded by dilatation, or *vice versâ*. Thus Mr. Power and I found that on injecting digitalis into the circulation of a dog, the blood-pressure rose, but the secretion of urine was either greatly diminished or ceased altogether. Here it is evident that the renal vessels had contracted so much as to prevent the circulation through the kidney, notwithstanding the




FIG. 151.—Curves showing the effect of erythrophlœum upon the blood-pressure and secretion of urine. From *Phil. Trans.*, vol. clxvii.

rise which had taken place in the blood-pressure. After a while the blood-pressure began to fall, and then the secretion of urine rose much above its normal, showing that the general blood-pressure was then able again to drive the blood into the kidneys.[1]

Similar observations were made by Mr. Pye and myself with regard to erythrophlœum; and the accompanying curves (Fig. 151) show well the result upon the urine of the mutual action of the rise in blood-pressure and the contraction of the renal arteries upon the secretion of urine. It will be noticed that at first the blood-pressure rises more quickly than the secretion of urine, the circulation through the kidney appearing to be opposed by the renal arteries. This opposition is then overcome, and the secretion of the urine rises more quickly than the general blood-pressure. The renal vessels again appear to contract, so that the urine diminishes while the blood-pressure rises still further. We have then oscillations due first to one factor and then to the other being predominant; and then, when the blood-pressure rises to its maximum, we find that the urine is at its minimum, the secretion of urine again rising as the blood-pressure falls.

A good deal of discussion has arisen regarding the mode of action of digitalis, and it has been stated by many to act as a diuretic only in cases of heart disease, and to have no diuretic


[1] *Royal Society's Proceedings*, No. 153, 1874.

ction in health. In my own experiments, however, I found hat it acted as a very marked diureticeven in health, and the xplanation of this discrepancy may possibly be that in my own ase the blood-pressure was low, whereas in the others it was robably much higher; but I am uncertain regarding the true xplanation, though I am certain of the fact.

By causing increased secretion of water through the kidneys iuretics may increase the concentration of the blood and thus roduce thirst, or cause absorption of water from the intercellular issue or serous cavities in dropsies. In my own experiments on igitalis I weighed all my food and measured all my drink for nearly six months, taking exactly the same quantity every day. After producing profuse diuresis by a large dose of digitaline sixty milligrammes in two days), such thirst ensued that I was orced to take a quantity of water to allay it.[1]

Mode of Action of Diuretics.—From what has already been aid, it is evident that diuretics may act in several ways. They may act:

A, on the **circulation** in the kidney, raising the pressure



IG. 152.—Diagram to show the parts of the secreting apparatus of the kidney which are probably affected by different diuretics.

n the glomeruli—(1) locally, (*a*) by contracting the efferent vessels, or the arterial twigs which pass directly to the capillary plexus; (*b*) by causing dilatation of the renal arteries, and thus increasing the supply of blood to the kidney. This they may do also in more ways than one, for they may either paralyse the vaso-motor nerves of the kidney, or act on vaso-dilating mechanisms. (2) they may raise the blood-pressure generally by causing the contraction of vessels in other parts of the body.

B. Other diuretics may act on the **secreting cells** of the tubules, and may increase both the amount of water and the amount of solids excreted by them.

[1] The experiments were made in 1855, and published in part in my thesis on *Digitalis, with some Observations on Urine*. London: Churchill & Co., 1868.

[2] Munk, *Central. f. d. med. Wiss.*, No. 27, 1886.

Calomel in continued doses acts as a powerful diuretic,[1] po sibly by increasing the amount of urea in the blood, and thu increasing the amount of urine.[2]

Diuretics have already been classified as stimulating an sedative; and the sedative class agrees very closely with the or which we have just indicated as acting on the kidney throug the circulation.

From what has been said of the action of diuretics it evident that we may hope to do much more by combining the than by using them singly. Thus we see that digitalis instea of acting as a diuretic may completely arrest the renal circul tion and stop the secretion altogether. If, however, we ca combine it with something which will produce dilatation of th renal vessels, while the general blood-pressure remains high, v shall greatly increase the circulation through the kidney, an obtain the desired result. Experiments in regard to this we made by Grützner with nitrite of sodium. He found that th substance increased the secretion of urine when the blood-pre sure was reduced to a minimum by curare; and he found tha it also had this effect when the blood-pressure was raised l imperfect respiration. When the vaso-motor centre was great stimulated, however, by allowing the blood to become very venou the nitrite of sodium no longer produced any increase of secretio

Caffeine, again, has an action on the kidney similar to th of physostigmine on the salivary glands (p. 358). Thus, l affecting the vaso-motor centre, it not only produces contracti of the vessels generally, including those of the kidney,[3] but st mulates the secreting cells.[4] The contraction of the vessels ma counteract this stimulating action, so that no urine is secreted in the case of digitalis (p. 430), but when the renal nerves a divided a copious secretion of urine takes place.

Diuretics.

Refrigerant Diuretics.

Water in large quantities.
Carbonic acid (aërated waters).
Sodium salts, e.g. common salt.
Potassium salts, especially the
Acetate.
Bitartrate.
Chlorate.
Citrate.
Nitrate.

Hydragogue Diuretics.

Adonis Vernalis.
Broom.
Caffeine.
Colchicum.
Digitalis.
Erythrophlœum.
Nitrous ether.
Squill.
Strophanthus.

[1] Jendrássik, *Deutsch Archiv f. klin. Med.*, xxxviii. p. 499.
[2] Locke, *Practitioner*, xxxvii. p. 170.
[3] Riegel, *Verhandl. d. III. Congress f. inner. Med.*, 1884.
[4] Von Schroeder, *Central. f. d. med. Wiss.*, 1886, p. 465; Langgard, *ibid.* p. 5

Stimulant Diuretics.

lcohol.
Gin.
Hock.
antharides.
latta Orientalis.
leo-resins, resins and volatile oils—
Turpentine.
Juniper.
Savin.
Copaiba.
Cubebs.
Black pepper.
Matico.
Kawa.
Guaiac.
Umbelliferous plants chiefly containing volatile oils—
Parsley.
Carrot.
Dill.
Fennel.
Cruciferous plants—
Mustard.
Horseradish.
Asparagus.
Uva ursi.
Sarsaparilla.
Buchu.
Pareira.
Chimaphila.
Taraxacum.
Ononis spinosum.
Santonica.

The following tabular view of the probable mode of action of ne various diuretics may help to show it more distinctly :—

- Raise arterial pressure....
  - Generally
    - Increased action of the heart
      - digitalis.
      - alcohol.
    - Contraction of vessels in intestine and throughout the body.
      - Digitalis.
      - Erythrophlœum.
      - Strophanthus.
      - Squill.
      - Convallaria.
      - Strychnine.
      - Caffeine (p. 432).
      - Cold to surface.
  - Locally in kidney.
    - Contract efferent vessels or arteriæ rectæ so as to raise pressure in glomerulus and lessen absorption in tubules, or both.
      - By action on vaso-motor centres.
        - ? The same as in preceding list.
      - By local action on vessels or nervous structures in the kidney itself.
        - ? Broom.
        - ? Turpentine.
        - ? Juniper.
        - ? Copaiba.
        - ? Cantharides.
    - Dilate afferent vessels.
      - Paralyse vaso-motor nerves or involuntary muscular fibre, or stimulate vaso-dilating nerves.
        - Nitrites.
        - Alcohol.
        - ? Urea.[1]
- Act on the secreting nerves, or secreting cells of the kidney itself.
  - Increase water excreted.
    - Urea.
    - Caffeine.
    - Calomel.
  - Increase solids excreted.
    - Liquor potassæ.
    - Potassium acetate, &c., and other saline diuretics.

Uses.—Diuretics may be employed for the purpose of removing either **water** or **solids** from the body. They are used :—

1st, to remove the excess of fluid met with in the tissues and erous cavities in cases of dropsy.

2nd, to hasten the removal of injurious waste-products and oisonous substances from the blood.

3rd, to dilute the urine.

[1] When a current of blood is passed artificially through an excised kidney, the eam is much accelerated by the addition of urea. Abeles, *Sitz.-Ber. d. k. k. iener Akad.*, Bd. 87, Abt. 3, April 1883.

In cases where the accumulation of fluid depends on veno congestion, as for example in **cardiac** dropsy, those diuret which act on the general vascular system, like digitalis, strop anthus, squill, or erythrophlœum, are most efficient becau they tend to remove the cause of the dropsy (p. 333), as well to assist the absorption and excretion of the fluid already effus

When the dropsy depends on the disease of the **kidneys liver,** other diuretics should either be given instead of, or alo with, digitalis or squill. Even in cases of cardiac disease wh digitalis or squill are not proving efficacious, the addition o little blue pill greatly assists their action, though it would hard to say in what way it does so.

In dropsy depending on kidney disease, decoction of broo oil of juniper, and nitrous ether are amongst the most relia diuretics, and in hepatic dropsy, copaiba.

Diuretics are used to increase the secretion of **solids** febrile conditions, and in cases of kidney disease where excretion of waste-products is deficient, and their retent threatens to prove injurious. In such cases nitrate and tartrate of potassium, turpentine, juniper, and caffeine useful.

Diuretics are also used to **increase** the proportion of **wa** in the urine, and thus to prevent the solids being deposited fr it and forming calculi in the kidney or bladder, or even to solve again such concretions as have been already formed.

Adjuvants to Diuretics.—As the amount of urine secre depends upon the difference in pressure between the blood in glomeruli and the urine in the tubules, it is evident that pressure on the tubules, whether caused by obstruction of ureter by a calculus, by the mechanical pressure of drops accumulations in the abdomen, or by distension of the ver plexus in the kidney itself, will tend to lessen the secretion urine. Consequently we sometimes find that in such c diuretics fail to act until the pressure has been relieved by **pa centesis** in cases of dropsy, or the venous congestion lesse by the use of a brisk **purgative,** or by **cupping** over the loin

If the venous congestion is very great, as in cases of mi disease or of chronic bronchitis with emphysema and dil heart, bleeding from the arm may be advantageous or imperatively necessary. In dilated heart and in mitral inc petence, the action of digitalis on the heart itself, strengthe its action and enabling it more effectually to pump the b out of the venous into the arterial system and thus re venous congestion, will aid its action upon the kidneys.

Action of Drugs on Albuminuria.—In the normal kid no albumen passes from the vessels or lymphatics into the nary tubules, but under abnormal conditions it may do so the urine become albuminous.

Albuminuria may be produced by ligature or compression of the renal artery; by ligature of the renal vein; and, though to a less extent, by ligature of the ureter. A similar effect to that of ligature of the renal artery may be produced by causing it to contract temporarily by means of drugs such as digitalis. In the experiments made by Mr. Power and myself we noticed that the urine which was secreted after the secretion had been completely stopped by digitalis was albuminous.

Albuminuria is also noticed after poisoning by strychnine, which, as Grützner has shown, has a similar action to digitalis, and in cases of suffocation or of epilepsy, where the vaso-motor centre is stimulated by venous blood.

Other drugs appear to cause albuminuria by a direct action on the kidney itself. A marked example of this is cantharides, which produces both albuminuria and hæmaturia. Shortly after its injection the kidney appears congested and swollen, and on microscopic examination it is found that the alterations begin first in the glomeruli and convoluted tubules, and gradually extend to the straight tubules. These changes consist in intense congestion, especially in the glomeruli, with increased tension of blood in the vessels. Then the liquid constituents of the blood pass through the vascular walls, carrying along with them granules, red corpuscles, and white corpuscles. This exudation then passes from the glomerulus along the whole length of the tubules, the epithelium of which next becomes changed, the cells which line them swelling up, multiplying, and becoming modified in form, migration of leucocytes also occurring. In short, we have the signs of inflammation beginning in the glomeruli and passing along the tubules.

Lead produces also disease of the kidney, but of a different kind. The kidney in animals poisoned by it is pale and granular with an adherent capsule and with atrophy of the cortical substance, in which crystals are often present. These appearances are due to chronic interstitial nephritis caused by calcareous deposits in Henle's loops. These block up the tubuli, produce subacute inflammation of the glomeruli and tubules, with atrophy and cirrhosis. A similar result is produced also by mercury. Chlorate of potassium has a very peculiar action on the kidney. In large doses it produces a peculiar kind of hæmaturia, the urine being dark brown and containing large quantities of broken-up blood-corpuscles. The drug arrests the secretion of the urine by blocking up the tubules with plugs of broken-up blood-corpuscles.

Tannin and tannate of sodium appear to have a certain power to lessen the exudation of albumen through the Malpighian tufts, as Ribbert found that when albuminuria was produced artificially in rabbits by temporary ligature of the renal artery, both tannin and tannate of sodium either lessened or

prevented the exudation of albumen. Arbutin, the active pri ciple of uva ursi, appears to be still more efficacious, but requires be given in somewhat large doses. Fuchsin has a similar actic

Lithontriptics.

These are remedies employed for the purpose of preventi the solids of the urine from being deposited, or of causing solution.

One of the most important is the abundant use of water, a sometimes it is advisable to use distilled water in place of dinary water, as distilled water is free from salts of any kir Distilled water has a disagreeable, flat taste, but it may be ma quite agreeable by charging it with carbonic acid in a gasogen

The substances which most generally are deposited from t urine are uric acid, acid urates, oxalate of calcium, and ph phates; the two former are liable to be deposited when the uri is too acid, and the two latter when it is alkaline or neutr Oxalate of lime also may be deposited from faintly acid uri These substances may be deposited either in the kidney bladder, and thus give rise to renal or vesical calculi.

The lithontriptics generally employed when uric acid, or a urates are present, are salts of lithium and potassium, as urate of potassium is more soluble than the urate of sodiu and the urate of lithium more soluble than even that of pot isum. On account of the low atomic weight of lithium salts have the further advantage of combining with a mu larger relative proportion of uric acid than the salts of potassi or sodium. When phosphates are present, mineral acids, such phosphoric, are sometimes employed, but it is difficult to ren the urine acid by the internal administration of mineral aci although it is easy to render it alkaline by the administration alkalies. Benzoic and cinnamic acids, however, in passing throu the body, are converted into hippuric acid, and they render urine acid. They may either be given alone, or in combinat with ammonia, as benzoate of ammonium, because, althou ammonium is alkaline, yet it appears to undergo convers into urea in the body, and does not render the urine alkaline

The deposition of oxalate of calcium is usually connec with disturbances in the digestive system, and I have observ in a hospital ward, that a deposit of it is very commonly fou in the urine after the patients have had cabbage for dinn The administration of nitro-hydrochloric acid frequently tend prevent the deposition of oxalates, and this is, perhaps, on whole, the best remedy for the form of dyspepsia to which name of oxalic diathesis is sometimes given. Sometimes, h ever, carbonate of sodium, by aiding the digestion, seems to more beneficial.

ACTION OF DRUGS ON THE SKIN.

Diaphoretics and Sudorifics.

The difference between these classes of remedies is simply ne of degree. When a drug **increases** the secretion of sweat nly slightly, so that it can still evaporate from the skin without nning down in drops, it is called a **diaphoretic**; but when increases it so greatly that it can no longer evaporate, and reams down the skin, it is called a **sudorific.**

The **secretion** of sweat, like that of saliva, consists in the rmation of the secretion by the cells of the gland from the aterial which is yielded by the fluid in the lymph-spaces around ne gland.

New material is constantly supplied to this fluid by the blood hich circulates in the vessels. We therefore find that **increased irculation** of blood through the cutaneous vessels and increased ecretion of sweat usually accompany one another, but this is ot always the case. In the sweat-glands, as in the salivary lands, the **secreting nerves** which regulate the activity of the ells are independent of the vascular nerves which regulate the apacity of the vessels. In fever or in poisoning by atropine he vessels may be widely dilated and the current of blood hrough them **rapid**, while the **secretion** of sweat is arrested. On the other hand, in dying persons we see a copious secretion f sweat occur, while the circulation through the skin has become ery feeble or almost stagnant. A certain amount of sweat, ndeed, may even be secreted by amputated limbs, the material or it being afforded by the lymph around the glands. But profuse secretion of sweat cannot go on long unless the gland s freely supplied with blood, for otherwise the supply of new material would cease. Dilatation of the vessels therefore aids the secretion of sweat. Dilatation may be induced by section of vaso-motor nerves or stimulation of vaso-dilating nerves. Thus, when the sympathetic is cut in the neck of a horse, dilatation of the vessels is produced by the section, and sweating occurs on that side.

The vaso-dilating and secreting nerves of the sweat-glands usually run together, and by irritation of a nerve-trunk, such as that of the sciatic, the vessels of the foot may be dilated, and sweating excited.

Warmth usually increases both the circulation of blood in the skin and the secretion of sweat; while **cold** has the contrary effect.

The **nerve-centres** which excite the secretion of sweat appear to be situated in the **spinal cord**; the centre for the posterior

extremities being situated in the upper lumbar and lower thoraci part of the cord in the cat; while that for the upper extremitie in the same animal is situated in the lower part of the cervica region of the cord.

The sweat-glands may be excited to secrete:

(1) By the action of drugs upon the terminations of nerve in the glands.
(2) By the action of drugs on the sweat-centres themselves
(3) Reflexly by stimulation of sensory nerves.
(4) By mental stimuli.

An example of the stimulation of sweating by the action c drugs on the **nervous terminations** in the glands themselve is afforded by pilocarpine, which will cause secretion even whe the nerves which connect the centres with the glands hav been cut.

Secretion may be also arrested by the paralysing action c drugs upon the terminal fibres; thus, atropine, locally injected prevents the secretion of sweat, however much the nerve goin to the gland or the nerve-centres be stimulated; and atropin also antagonises the effect of pilocarpine on the nervous termina tions, and arrests the secretion which the latter causes.

The **nerve-centres** may be stimulated directly by the con dition of the blood which is passing through them, or reflexly b irritation of sensory nerves. Stimulants of these nerve-centre are: (1) a venous condition of the blood; (2) high temperatur of the blood; and (3) poisons, especially nicotine.

A venous condition of the blood is one of the most powerfu stimulants, and it is to this that the sweats which precede deat are in all probability due; for while watching a patient dying I have observed that drops of sweat appeared on the brow just a the time that the blood became venous, as was evidenced by th commencing lividity of the finger-nails and lobes of the ears Under such conditions, while the secreting cells are strongl stimulated, the circulation is very feeble.

A high temperature is also a powerful stimulant. In con sidering its action we must take into account the effect of th warm blood upon the sweat-centres in the cord, as it circulate through them, and its local action also on the sweat-gland themselves. Up to a certain point it appears to have the effec of dilating vessels and of increasing the activity of the gland by acting both on the sweat-centres and on the periphery.

Local warmth to one foot increases the secretion of sweat and local cold diminishes it in that foot, when the glands in al four feet of an animal are stimulated equally either by excite ment of the sweat-centres or by the action of pilocarpine on th peripheral ends of the sweat-nerves.[1]

[1] Luchsinger, *Pflüger's Archiv*, 1876, vol. xviii. p. 480.

The sweat-centres appear to be directly stimulated by nico-
ne, but the action of this drug may be partly due also to a
flex effect on those centres through the nerves of the stomach.
The sweat-centres appear to be **reflexly** excited by severe
·itation of any sensory nerve passing from the surface of the
dy, and the point at which the irritation is applied does not
em to be of much importance. They are probably stimulated
flexly from the stomach, as in the sweating which accompanies
usea.

The power of the **brain** to stimulate the sweat-centres is
own in the effect of mental emotion, and direct irritation of
e medulla oblongata will cause sweating in cats even some
me after death.

Excretion by the Sweat-glands.—A number of substances
ken into the body pass out in small quantities through the
in. Aromatic and volatile substances appear to pass readily,
also benzoic acid, hippuric and cinnamic acid, tartaric acid,
ccinic acid, iodide of potassium, quinine, corrosive sublimate,
rseniates of sodium and potassium. When arseniate of iron
as been taken, curiously enough, arsenious acid has been found
the sweat, and iron in the urine. Some **colouring matters**
re excreted especially by the skin of the armpits, and the under-
othing may sometimes be found stained of a brick-red colour
these parts. I have observed this in some cases after drinking
aret or port, but it only occurs exceptionally after the employ-
ent of these wines, and it is possible that it is due to adultera-
on with foreign colouring matters, for I have also noticed it
n cases where no wine has been drunk, but where pickled red
abbage or beetroot has been eaten.

Relations between Sweat-glands and Kidneys. — The
weat-glands and the kidneys both remove **water** and small
uantities of salts from the blood, and thus tend to keep it at
s normal concentration. Their functions are complementary, so
hat when much water is excreted by the skin, less is excreted by
he kidneys, and *vice versâ*.

This complementary action is to a great extent due to the
ifferent distribution of blood under varying conditions, because
when both organs are stimulated—as, for example, by salts of
mmonium—diuresis will occur, if the blood be driven towards
he kidneys by external cold ; and diaphoresis if it be attracted
o the skin by external warmth.

The quantity of solids contained in the sweat is very small—
only a little over one per cent.—three-fourths of these being
organic, and one-fourth inorganic. The organic solids are chiefly
fats, fatty acids, and small quantities of urea—about one-tenth
per cent. When the kidneys are insufficient, however, to excrete
urea, the quantity in the sweat becomes greatly increased, and
it has even been found crystallised upon the skin.

Action of the Skin in Regulating Temperature.—As have already mentioned, the skin has an excreting function com plementary to that of the kidneys, and it may to some exte relieve them when they are doing their work imperfectly. B its chief function is that of regulating the bodily temperatur The quantity of heat which is changed into potential energy, converting liquid water into gaseous steam, is very great. Fi and a half times as much heat is required to convert boilin water into steam as to raise the same amount of water from th freezing to the boiling point. The immense loss of heat thu occasioned converts the healthy skin under the influence of gre heat into an actual cooling apparatus. In negroes on the We Coast of Africa it has been noticed that while the skin is perspi ing profusely, it is as cold as marble, and Sir Charles Blagdc observed that in a room with a temperature of 198° Fahr. h side felt quite cold to the touch.

The chief **diaphoretics** are:—

- Stimulating sweat-centres (?)
  - Ammonium acetate.
  - ,, citrate.
  - Dover's Powder.
  - Ipecacuanha.
  - Opium.
  - Camphor.
  - Nicotine. (Also reflexly through stomach (?) (p. 439).)
  - Antimony. (Also reflexly through stomach (?) (p. 439).)
- Stimulating secreting nerves (?)
  - Pilocarpine.
  - Warmth to surface, in baths.
  - Warm drinks.
  - Alcohol.
- Doubtful action
  - Serpentaria.
  - Sassafras.
  - Guaiac.
  - Mezereum.
  - Senega.

Uses.—Diaphoretics are used in cases of threatened catarr or inflammation of mucous or serous surfaces, or internal organ after exposure to cold. Their beneficial action in such cases ma be partly due to the withdrawal of blood from internal organ to the surface of the body, but it is not improbable that in add tion to this the condition of the skin which they induce exercis a favourable action reflexly on internal parts. There seems t be a sort of complementary action between the skin and th internal mucous membranes, as well as between the skin an kidneys. This is sometimes well marked in gouty patient where the disappearance of an eruption from the skin is followe by asthma, and *vice versâ*. It is also shown by the experimen of Rossbach (p. 252); and the effect of irritation of the stomac and nausea on the secretion of the skin has already been notice (p. 439).

One of the best diaphoretics to cut short commencing catarr is compound ipecacuanha powder. In fevers, with the exceptio of rheumatic fever, the skin is generally dry although the ten

erature is high, and diaphoretics are employed to increase the ntaneous secretion, and thus to lower the temperature.

In exanthemata, after the eruption disappears from the skin, here is a tendency to inflammation of internal organs, and in rder to prevent this, diaphoretics are used, those which act arkedly on the vessels, or stimulating diaphoretics, being specially indicated.

The advantage of a free supply of blood in chronic morbid nditions, such as chronic ulcers, has already been mentioned hen speaking of irritants (p. 343); and in chronic morbid nditions of the skin diaphoretics are sometimes employed to romote the cutaneous circulation. In diseases of the kidneys, hen it is advantageous to lessen their functional activity, dia- horetics are employed in order to make the skin act vigorously; nd they are used also to assist the kidneys in removing the uid which has already accumulated in the body in cases of ropsy. When the kidneys, though not diseased, are called upon o do excessive work—as in diabetes mellitus, and polyuria—iaphoretics are employed to aid them. Where an unnatural ecretion of fluid is taking place from the intestine, as in cases of hronic diarrhœa, diaphoretics are also employed to divert secre- on from the intestine to the skin, and thus lessen the diarrhœa.

Antihidrotics or Anhidrotics.

These are substances which **lessen** the secretion of **sweat**:—

- Acids.
- Belladonna and Atropine.
- Hyoscyamus.
- Amanita muscaria and muscarine.
- Agaricus albus.
- Jaborandi and Pilocarpine.
- Nux vomica and Strychnine.
- Quinine.
- Picrotoxine.
- Ipecacuanha (compound powder).
- Zinc salts.

These remedies may act (1) on the **sweat-glands** themselves y lessening the excitability either of the secreting **cells** or of the ecreting **nerves**; (2) on the **sweat-centres**, by lessening their xcitability or removing the excitant; and (3) on the **circulation.** Belladonna in large doses paralyses the ends of the secreting nerves, just as it does in the salivary glands, so that the sweat- glands will not secrete even when a strong stimulation is applied o their nerves. As belladonna acts thus when locally applied, t may be used for local sweating in the form of extract or of olution of atropine painted on, or rubbed over, the surface. It s thus useful in cases of local sweating of the palms of the hands nd soles of the feet. It may also be given internally to paralyse he ends of the secreting nerves, and thus to arrest the night- sweats in phthisis. But in all probability its beneficial effect in

the night-sweats of phthisis is not dependent on its paralysing action on the secreting nerves, for it is useful in doses which appear too small to produce this effect, and which also do not act immediately, but rather after some time. Its utility in such cases therefore, is probably due to an effect on the nerve-centres, and especially to a stimulating action on the respiratory centre.

The **night-sweats** of **phthisis** are usually followed by great weakness and prostration, which has sometimes been attributed to the loss of salts and organic matter contained in the sweat. But the quantity of these is very small, and the same depression is not noticed when there is an increase of two or three ounces




FIG. 153.—Diagram to illustrate the action of antihidrotics. The secretory nerves passing to the sweat-glands from the sweat-centres in the spinal cord have been represented as a single nerve for the sake of simplicity.

in the daily secretion of urine, although it will carry off quite as large a quantity of both salts and organic matter. Nor is the same depression produced by the profuse sweating due to active exertion, nor even by the sweating in ague. The depression is not the consequence of the profuse sweat; both are probably the consequence of one common cause. This cause I believe to be partial failure of the respiration and consequent accumulation of carbonic acid in the system, which leads at the same time to stimulation of the sweat-centres and impairment of tissue-change throughout the body generally.

In healthy persons the respiratory centre is more sensitive to the stimulus of carbonic acid than other parts of the nervous system. Thus any increase in the venosity of the blood at once stimulates this centre, and through it the diaphragm and respiratory muscles of the thoracic wall, rendering the respiratio

re active, and increasing arterialisation. Consequently, the od does not become venous enough to stimulate the sweat-ntres. But when the respiratory centre is depressed by excess-e reflex stimulation during the day in the process of coughing, d by the natural depression which occurs during sleep, it may spond less readily to the stimulus of venous blood. The amount carbonic acid in the blood may thus accumulate to such an tent that the sweat-centres are stimulated before the respira-y centre responds, and thus the profuse sweats which are so pressing to the patient may occur.

It is probable that this is only part of the truth, and that ere are other factors in the production of abnormally profuse eats; for in children suffering from rickets, the head per-ires profusely during sleep, yet the mucous membranes are of bright rosy colour. Nevertheless, acting on this idea, I have ven at night such substances as are powerful stimulants to the spiratory centre, like nux vomica and strychnine, and I have nd that the sweating is usually arrested by them. A small se is sometimes sufficient, but occasionally it must be steadily creased until as much as half a drachm of the tincture of nux mica is given at once. The only disadvantage that I have ticed from this treatment is that the excitability of the respi-tory centre sometimes persists during the day, and renders the ugh more troublesome. I have tried to remedy this by mbining strychnine with opium, and partially succeeded. If we w review the **remedies** used in the **night-sweating** of phthisis, shall see that almost every one of them has a **stimulant** tion on the **respiratory centre**. This is possessed in a marked gree by atropine and hyoscyamus. Ipecacuanha has this tion also, and its combination with opium, in the form of over's powder, although it causes sweating in healthy persons, nds to restrain it in phthisical patients. Picrotoxine, salts of nc, and pilocarpine, all stimulate the respiratory centre also, d we find that the last is useful in the night-sweats of phthisis, though we should expect from its physiological action that it ould be injurious, stimulating, as it does, the terminations of e secreting nerves in the sweat-glands themselves. It is pos-ble, however, that in addition to the stimulation of the sweat-ntres by venous blood, the night-sweats of phthisis may be metimes increased by the **high temperature** of the patient, d in such cases quinine, as Murrell has pointed out, is likely be most serviceable.

ACTION OF DRUGS ON THE BLADDER.

The walls of the bladder consist of involuntary muscular re which expels the urine by its contraction. Around the ck of the bladder is a band of involuntary muscular fibre, the

sphincter vesicæ, which by its contraction closes the orifice ar prevents the escape of urine. The sphincter vesicæ receives i motor supply through the third, fourth, and fifth sacral nerves

The **nerve-centre** for the movements of the bladder situated in the **spinal** cord opposite the fifth lumbar vertebra dogs, and the seventh in rabbits. This centre is able to regula the retention and discharge of the urine by the bladder eve when the spinal cord is divided between it and the brain, but th activity of the centre under normal conditions is modified by th brain, so that we may consider that there is a cerebral as we as a spinal centre for the bladder. The spinal centre may b set in action either reflexly, or by stimuli passing down from to the brain. The cerebral centre may be set in action eith reflexly or voluntarily.

Usually when the pressure of the urine within the bladder increased beyond a certain limit depending not only on th quantity of the water, but on the state of the contraction of th bladder itself, the neck of the bladder becomes slightly dilate and a drop of urine exuding acts as a stimulus to the senso nerves of the urethra, and thus calls reflexly into action th centre in the spinal cord by which at the same time th sphincter vesicæ is inhibited, and the detrusor urinæ stimulate Reflex action may also be induced by stimulation of oth nerves, as for example by the application of a wet sponge to th anus or perinæum. The **cerebral centre** is usually called in action by the sensation of the bladder being full. It may called into action voluntarily, although there is little urine the bladder ; and also may be excited by emotion, such as fea

It may be also excited reflexly through the sense of hearin Boerhaave was accustomed, when patients found difficulty passing water, to make an attendant pour water from a heig into a basin in the patient's hearing. The splashing thus occ sioned induced the patient to pass water, and a similar effe as is well known, is produced on horses by whistling. Nervo agitation has often the contrary effect of producing retention water. When it is desirable for a person to pass water—e when a specimen of urine is wanted for examination—it advisable to put him in a room by himself and turn on a t within his hearing. The removal of the restraint exercised the presence of another person, along with the stimulant acti of the sound of falling water, rarely fails to produce the desi effect. Even the recollection of the sound of falling water v tend to cause evacuation of the bladder, and when there is di culty in passing water the patient may sometimes obtain rel by thinking of a waterfall. Washing the hands in cold wa also tends reflexly to cause evacuation of urine, and the effect a wet sponge to the perinæum has already been mentioned.

Vesical sedatives are substances which lessen the irritabil

the bladder, and thus remove pain, and lessen the desire to inate. This desire may be excited not only by the presence urine in the bladder, but by the irritation of calculi, or in- mmation of the mucous membrane of the bladder itself. hen calculi are a source of irritation, carbonate of calcium taken ternally seems to lessen the irritability. In cystitis the irrita- on is diminished by the use of very hot water externally, in a det or hip-bath. The irritability of the nerves may be dimin- hed by opium, belladonna, and hyoscyamus, and by drinking eely of warm water, either alone or in the form of an infusion decoction of some mucilaginous substance, e.g. linseed-tea or arley-water.

In chronic inflammation the irritation may be diminished by stringents such as buchu, uva ursi, pareira brava, and alche- illa. **Vesical tonics** are substances which increase the con- actile power of the muscular fibres in the bladder. They are herefore useful in two different conditions, for by strengthen- g the detrusor urinæ they prevent retention, and by strength- ning the sphincter vesicæ they prevent incontinence.

Some of these remedies appear to act by increasing the imulating power of the urine, so that the sphincter vesicæ is onsequently more firmly contracted; of this class is cantharides. thers appear to alter the direction of reflex action; such are he passing of a bougie through the urethra once or twice a day, r the application of an injection of nitrate of silver, ten to hirty grains to the ounce, to the neck of the bladder. Others ct on the nerve-centres and apparently are useful sometimes y lessening the reflex susceptibility from the bladder, so that he detrusor urinæ is less called into action; at other times by ncreasing the susceptibility of the nerve-centre, so that the phincter vesicæ is more firmly contracted—of the latter class is trychnine; to the former belongs bromide of potassium, which nust be given at night. Belladonna, which is one of the most seful remedies in incontinence of urine, acts upon the nerve- entres, but whether it acts in the same way as strychnine or as romide of potassium, it is difficult to say. It is quite possible hat it lessens the sensibility of the bladder to changes of pressure within it in somewhat the same way as it lessens the sensibility f the heart to changes in blood-pressure (p. 298).

Urinary Sedatives and Astringents.

When the urinary passages are healthy, the secretion of mucus from them is very slight, and the presence of urine in he bladder or its passage along the urethra usually gives rise to no pain. Pain and scalding are sometimes caused by an ab- normally acid urine, or by the presence of crystals of uric acid

in it, even though the mucous membrane itself be healthy. such cases the use of potash or lithia is indicated to restore t healthy character of the urine.

When the bladder itself is irritable or inflamed, the secreti of mucus is increased and there is constant desire to mictura There are here two indications to be fulfilled: one is to less the irritability, and the other is to remove the inflammatic In lessening the irritability, belladonna seems to be especia useful, and to diminish the inflammation, astringents are e ployed.

In inflammation of the urethra the same indications exi and here also cubebs, copaiba, and sandal-wood oil are employe It is, however, easier to apply astringents locally to the ureth than to the bladder, and consequently astringent injections a more frequently used: these are usually solutions of alum, su phate or acetate of zinc, and acetate of lead.

Finely-divided powders act also beneficially by keeping t inflamed walls of the urethra apart, and on this account a m ture of sulphate of zinc and acetate of lead, which gives a fi white, insoluble precipitate of sulphate of lead, is more efficacio than either of the solutions employed alone. Kaolin or chi clay, which is a completely inert powder, as well as bismuth a calomel, have also been used for a similar purpose. As it found that the secretion in gonorrhœa frequently, if not alwa contains microscopic organisms, the injection of antiseptics h been used: among these may be mentioned permanganate potassium and zinc, boric acid, carbolic acid, sulpho-carbolat sulphurous acid, as well as drugs having both an astringent a antiseptic action, like chloralum, perchloride and pernitrate mercury, and chloride of zinc.

The beneficial effects of copaiba in inflammation of t bladder and urethra are probably due to its antiseptic actic It is excreted in considerable quantities by the kidneys a renders the urine antiseptic, so that its decomposition and t appearance of bacteria in it are greatly retarded or complet prevented. The whole urinary passages from the glomeruli the kidney to the orifice of the urethra are thus washed out antiseptic urine, which does not decompose, and which ten to destroy or remove any germs that may be present. Cube terpenes,[1] and naphthalin[2] have probably a similar action.

[1] Schmiedeberg, *Arzneimittellehre*, p. 121.
[2] Rossbach, *Berlin. klin. Wochenschr.*, 1884, No. 46, p. 279.

CHAPTER XVI.

ACTION OF DRUGS ON THE GENERATIVE SYSTEM.

Aphrodisiacs and Anaphrodisiacs.

The sexual function is regulated by two nerve-centres, one of which is cerebral and the other spinal. The **cerebral centre** is the seat of the feelings and appetite which prompt the individual to seek sexual congress.

The **spinal centre** regulates the condition of erection in the sexual organs which is necessary for coitus. These two centres may act independently of each other, e.g. when the spinal cord is cut, but in the normal condition they naturally influence each other, excitement of the spinal centre re-acting on the cerebral centre so as to awaken sexual feelings, and excitement of the cerebral centre re-acting on the spinal so as to produce erection of the genital organs.

Erection is due partly to dilatation of the arteries in the erectile tissues of the genital organs, and partly to compression of the efferent veins. The blood being thus allowed to flow freely into the organs, and prevented from flowing out, distends them so as to render them turgid and more or less rigid. During the orgasm the turgidity is increased by partial stoppage of respiration, which, by rendering the blood venous and thus stimulating the vaso-motor centre, tends to raise the blood-pressure in the body generally, and in the erectile tissues particularly.

Dilatation of the arteries in the genital organs and consequent erection occurs on stimulation, either of the genital centre in the lumbar spinal cord or of the vaso-dilating nerves (nervi erigentes) which pass from it to the genital organs and end in a ganglionic plexus surrounding the arteries.

The **lumbar** genital centre may be excited either reflexly by stimulation of the sensory nerves of the genital organs and adjoining parts, or by psychical stimuli transmitted to it from the brain.

The exact seat of the cerebral genital centre has not been determined, but Eckhard has found that irritation of the crura

cerebri can produce similar effects to stimulation of the nerv erigentes.

The **cerebral** genital centre may be stimulated and sexu feelings aroused by impressions made on the nerves of speci




FIG. 154.—Diagram to illustrate the action of aphrodisiacs and anaphrodisiacs. The darkly-shad spot indicates the genital centre in the brain, and the lighter spot the spinal centre in t lumbar portion of the cord. The direction in which impulses are conveyed along the nerv are indicated by the arrows. The nerves from the general surface have been represented going to the cerebral centre, and acting through it on the spinal centre. It is probable, ho ever, that several of them pass directly to the spinal centre, as represented in the case of t nerves of the nates.


or general sense, e.g. on the eye, ear, nose, on the mammæ, an general surface of the body, the genital organs and parts adjoi ing, as the bladder, prostate, and nates. Thus, sexual excitemer may occur in consequence of the sight of persons or picture the reading or hearing of licentious stories, or of irritation of th surface of the body either by gentle friction or by pruriginou irritation due to irritating articles of clothing, parasites, or ski diseases. Distension of the bladder has a somewhat simil effect, and the irritation consequent on an enlarged prostate probably, in part at least, the cause of the great sexual excit ment which sometimes occurs in elderly men. A very acid co dition of the urine, such as is found in some gouty patients, ma possibly have a similar action. Chlorate and nitrate of potassiu administered internally are said by Jacobi[1] to render the uri so irritating and to produce such sexual excitement as to lead t onanism. Ascarides in the rectum may cause excitement of th cerebral genital centre and give rise to nocturnal emissions a well as possibly to diurnal excitement, and in females they ma cause even greater irritation by passing into the vagina. Irrit tion of the rectum from the presence of piles or fissure may al give rise to such great sexual excitement as to induce onanis or nymphomania. Fæces in the rectum, and perhaps in th

[1] *Medical Times and Gazette*, 1876, vol. i. p. 177.

lon, may also cause sexual excitement in some persons or crease it when present.

Such sources of local irritation may sometimes be insufficient affect the cerebral centre during waking hours, when the tention is otherwise engaged, but may do so powerfully during ep, or when the cerebral functions are disturbed by cannabis dica, and they may then produce erotic dreams or seminal issions.

The lumbar centre is most readily excited by mechanical mulation of the genital organs, but it may be also powerfully mulated from the mucous membranes of the urinary passages, is seen in the painful priapism which occurs in poisoning by ntharides.



G. 155.—Diagram to illustrate the effects on the genital centres of irritation of the stomach or intestine by flatulence, acrid matters, or fæcal accumulations.

Stimulation of the lumbar centre without stimulation of the rebral centre may occur from the presence of fæces in the ctum and perhaps in the colon, so as to give rise to seminal issions during sleep unaccompanied by any dreams of a sexual aracter. Distension of the stomach or intestines by flatus ay have a similar effect (Fig. 155).

Aphrodisiacs.

These are medicines which increase the sexual appetite.

Irritation of the nates, either mechanically alone, by flogging, mechanically and chemically combined, by urtication or gging with nettles, has been used as an aphrodisiac.[1]

[1] Trousseau et Pidoux, *Traité de Thérapeutique*.

The sexual function requires, however, for its proper pe formance a healthy state of the body, and good, or at least fai nutrition; without these mere reflex excitement of the genit centres is likely to prove inefficient for the propagation of th race. Tonics generally, such as iron, are therefore to be regarde as **indirect aphrodisiacs.**

Strychnine has probably a double action, both increasing th general nutrition and rendering the genital nervous centres, bo lumbar and cerebral, more susceptible to the action of stimu Its aphrodisiac action is sometimes an objection to its use as tonic, for both it and nux vomica may cause seminal emissio which more than counterbalance its tonic action and weak the patient.

Cannabis indica has been regarded as an aphrodisiac, b the trials of it made in this country seem to show that it do not itself at least have any such action, and merely induces condition of partial delirium in which Easterns may possib have visions of a sexual nature, and indeed, they try to give sexual direction to the mental disturbance which the cannal produces, by mixing with it musk, ambergris, or cantharides.

Catharides act as an aphrodisiac, but their action is probab due to an irritating effect on the mucous membrane of t urethra, and their use in such doses as to have any aphrodisi action is attended with danger. Blatta orientalis when used a diuretic may have an aphrodisiac action like cantharides.[1]

Alcohol appears to excite the cerebral centre and increase t sexual appetite, while it interferes with the proper performan of the generative act.[2] This interference may be due to part paralysis of the lumbar centre or the nervi erigentes; but pa lysis of the vaso-motor centre is probably a potent factor, or m indeed be the only cause of the impotency produced by alcoh for alcohol paralyses the vaso-motor centre to such an ext that it will not react to the stimulus of venous blood, and ev suffocation will not raise the blood-pressure.[3] Consequently, rise in blood-pressure which holding the breath will norma produce during coition (p. 447) will not occur when much alco has been taken, and the penis, although it may be turgid fr dilatation of the vessels, will not acquire the rigidity necess for the generative act.

---

[1] Buttenwieser, *Der practische Arzt*, Feb. 1882.
[2] Shakespeare, *Macbeth*, act ii. scene 3.
[3] Dogiel, *Pflüger's Archiv.* vol. viii.

Anaphrodisiacs.

These are medicines which diminish the sexual passion.

The agents employed as anaphrodisiacs are :—

Ice.	Conium.
Cold baths, local and general.	Camphor.
	Digitalis.
Bromides of potassium and ammonium.	Purgatives.
	Nauseants.
Iodide of potassium.	Bleeding.

Anaphrodisiacs may act locally on the genital organs, or may upon the genital nerve-centres.

The effect on the nervous system may be directly exerted on nervous structures themselves, on the circulation, nutrition, general surroundings. Amongst the most powerful **local** aphrodisiacs is the continuous application of cold by means of Bromide of potassium possibly has also a local as well as eneral action.

When the lumbar portion of the cord is abnormally stimu-ed reflexly, the **stimulus** ought to be removed : thus, in warm ntries, where smegma may accumulate around and irritate glans penis, very careful washing is requisite and circum-on is an advantage. Both in warm and cold countries cir-ncision, either general or partial, is useful if the prepuce be y long and its orifice much contracted.

When the irritation appears to arise from the presence of y acid urine, or of crystals of uric acid, irritating the bladder urethra, as in gouty persons, potash or lithia should be em-yed to lessen the acidity of the urine, or to render it neutral. here abnormal irritation of the genitals is present the urine ould be examined for sugar as well as for uric acid, as the gar may cause local irritation of the prepuce or vulva.

Distension of the bladder ought also to be avoided, and in rsons who suffer from seminal emissions, occurring in the rning, it is occasionally advisable that they should be akened and empty the bladder an hour or more before their ual time of rising.

If stone in the bladder is acting as an irritant, surgical treat-nt should be employed, but in cases where this is inadvisable, where the irritation is dependent on enlarged prostate, general aphrodisiacs must be used, such as bromide of potassium large doses, care also being taken that the condition of the ne is not abnormally acid or alkaline. Ascarides in the tum must be treated with anthelmintics. When irritation ses from piles the use of sulphur internally is often beneficial, ough surgical interference may be necessary both for them and fissure.

When irritation arises from fæcal accumulations in t rectum or colon, they should be removed and their return pr vented by the careful use of aperients.

Flatulent distension of the stomach or intestines may be r moved by alkalis and cholagogues, bitters (p. 378), and especial by strychnine, which gives tone to the intestine. It thus happe that, notwithstanding the tendency of strychnine to cause sexu excitement and produce emissions by its action on the nerv centres, it may sometimes effectually relieve these conditions its action on the intestine.

As anything which tends to increase the flow of blood to t genital organs or the lumbar portion of the spinal cord heighte their excitability, care should be taken not only to avoid this, b also to direct as much as possible the current of blood to oth parts of the body. Thus, warm and heavy clothing or pa about the hips or loins should be avoided, and a hard mattr should be used in the place of a feather bed. Sometimes patie suffer from emissions in consequence of lying on their ba This is probably due to the effect of warmth on the spinal co and in order to avoid it, a towel or girdle should be put arou the loins with a knot tied in it, or some hard substance faste on it opposite the spine, so that the person would, even dur sleep, be prevented from lying on his back. Walking exercis not so useful as exercise of the arms, as in rowing, gymnast or mechanical occupations, such as those of a carpenter or bla smith, because, in walking, the current of blood passes towa the lower extremities and part of it may become directed to pelvis. In the other occupations just mentioned, the curr of blood is, on the contrary, directed to the upper extremit Working a treadle, as in turning a lathe or sewing-machine objectionable, both because the blood is directed towards lower extremities generally and because it may become speci directed to the genitals by occasional friction of the clothes.

Hard mental work has also a similar effect to that of bo exercise. In addition to these measures, a meagre diet, especially a vegetable diet, with the avoidance of stimulant of considerable service.

Emmenagogues and Ecbolics.

Emmenagogues are remedies which **restore** and regu the normal **menstrual flow** when it is absent or deficien irregular.

Ecbolics are remedies which cause the **expulsion of contents** of the **uterus.**

In menstruation both ovaries and uterus become conges An ovum is discharged, and a flow of blood occurs from

erus. Diminution or absence of the menstrual flow may be casioned either by general or local conditions: thus great bility or anæmia may cause it, and it is very frequent indeed the anæmia and debility which are consequent on the occurnce of slight consolidation in the lungs.

A local cause may be deficient determination of blood to the aries and uterus, although no general anæmia exists.

The remedies employed for these two conditions are termed **direct emmenagogues.** To correct anæmia, iron, manganese, d cod-liver oil may be employed.

In order to determine more blood to the uterus, warm fooths, warm hip-baths, mustard hip-baths, mustard stupes or ultices to the thighs and lower part of the abdomen, and ches to the inside of the thighs or to the genitals, and aloetic rgatives, may be employed.

It might at first seem from theoretical considerations that t-baths could hardly have any action on the uterus, but warm t-baths cause great dilatation of the arteries in the legs, and s probable that this dilatation extends up the iliacs, so that re blood may be sent to the genitals as well. But in addition this, it is not at all improbable that a close nervous connection sts between the vascular supply of the uterus and of the feet, not only does the warm foot-bath tend greatly to restore, but d and wet feet are amongst the most powerful agents in ecking, menstruation.

Other substances, which seem to have a direct stimulating ion upon the womb itself, are called **direct emmenagogues.** is not easy to see at present how they act; we know, however, t when given in large doses they cause contraction of the mb, and thus act as ecbolics. The chief emmenagogues e:—

Indirect Emmenagogues.		Direct Emmenagogues.
Baths	Hot foot.	Ergot.
	Hot hip.	Digitalis.
	Mustard.	Savin.
Leeches	To genitals.	Quinine.
	To thighs.	Asafœtida.
Mustard	Baths.	Myrrh.
	Poultices.	Guaiacum.
	Stupes.	Cantharides.
Purgatives, as aloes.		Borax.
Iron.		Rue.
Manganese.		Hydrastis.[1]
Cod-liver oil.		
Strychnine.		

[1] Fellner, 'Die physiolog. Wirkung einiger Präparate des Hydrastis Canadensis. *en. med. Jahrbücher*, 1885.

Ecbolics.

The involuntary muscular fibres of the uterus appear, li
those of the ureter or of the frog's heart, to possess the power
rhythmical contraction, and may contract when entirely separat
from the general nervous system. They are, however, controll
by the higher **nerve-centres.** There appears to be one centr
situated in the **lumbar** portion of the spinal cord, which is
itself sufficient to regulate all the movements, for they go
normally, even when the spinal cord has been completely divid
above it. This **centre** may be reflexly stimulated and contra
tions of the uterus induced by irritation of the ovarian, crur
or sciatic nerves. It may be also stimulated by the action up
it of drugs circulating in the blood, as ergotin, picrotoxine,
strychnine, or by great venosity of the blood, due to asphyxia.

There appears, however, also to be a second centre for t
uterus, as for the male genital organs, in the **brain** (*vide* p. 44
by which the lumbar centre may be excited, and in consequen
of this, stimulation of the cerebellum, crura cerebri, corpo
striata, and optic thalami, also gives rise to uterine contractio

Von Basch and Hofmann consider that the impulses pass
the uterus from the central nervous system, along two sets
nerves. One is composed of nerves passing from the inferi
mesenteric ganglion to the hypogastric plexus. Stimulation
these causes circular contraction of the uterus, descent of t
cervix and dilatation of the os. The other consists of branch
passing from the sacral nerves across the pelvis to the hypogast
plexus, and representing the nervi erigentes. On stimulation
these the uterus contracts longitudinally; the cervix ascends a
the os closes.

The mode of action of ecbolics has not been satisfactor
ascertained. Ammonia injected into the circulation appears
cause contraction of the muscular fibres, for it causes contracti
of the uterus even when all nervous connections have be
divided. Ergot possibly acts in the same way, but it is possil
also that it acts on the spinal centre.

The chief ecbolics are:—

Ergot.
Hydrastis.
Quinine.
Savin.
Thuja.

Uses.—Ecbolics are used to **accelerate** the **expulsion** of t
child when the passages are free but expulsive power is deficie
and to cause firm contraction of the uterus and so preve
hæmorrhage after delivery.

Adjuncts.—Compression of the uterus by kneading, pressure
er it by a pad, the hand dipped in cold water laid over the
erus, or a cold pad. Sternutatories have been used to supple-
ent the expulsive power of the uterus, and when necessary,
erative interference must be had recourse to.

The injection of hot water into the vagina, as hot as can be
rne, is a great aid in causing firm contraction of the uterus,
d thus stopping *post partem* hæmorrhage. Some of the liquid
obably enters the cervix through the flaccid os (*vide* p. 351).

Action of Drugs upon the Mammary Glands.

The milk-glands somewhat resemble the salivary glands in
e way in which they are affected by the central nervous system,
d by the action of drugs upon them. The action of the central
rvous system on the milk-glands, however, has not been made
t with anything like the same clearness as in the case of the
livary glands, experiments on animals not having given very
finite results. It is chiefly inferred from the effect of mental
notions in checking or altering the secretion of the milk; and
om the effect of belladonna locally applied in checking the
cretion. The amount of secretion appears to depend on the
nount of blood-pressure in the gland, and gentle stimulation of
e nipple increases both the flow of blood to the gland and the
cretion of milk. It is uncertain whether there are definite
creting nerves affecting the gland-cells apart from the vaso-
otor nerves.

The character of the milk depends to a great extent upon the
eding and exercise of the mother, and diet is the most important
gent in regulating both the quality and the quantity of the milk.
s Dolan points out, it not unfrequently happens that a wet
urse, when first she arrives, yields such milk that the child she
nursing thrives well, but the quality soon falls off. In place
much outdoor exercise and plain, nutritious diet, she is fed
xuriously and gets little exercise. In order to restore the
uality of the milk in such a case, the woman must be restored
s far as possible to her previous conditions of diet and exercise.

Many substances are excreted in the milk, such as ammonia
nd the aromatic oils to which vegetable substances belonging
o Umbelliferæ and Cruciferæ owe their flavour, probably also
l volatile oils are thus excreted. Amongst those which have
tually been found to pass into the milk are the oils of anise,
mmin, dill, wormwood, and garlic, as well as turpentine and
opaiba. The purgative principles of rhubarb, senna, scammony,
nd castor-oil, pass into the milk. Opium, iodine, and indigo do
o also, and metals, such as antimony, arsenic, bismuth, iron,
ad, mercury, and zinc. Volatile oils, having an agreeable taste,

do not appear to affect the secretion of milk directly, but appe
to render it pleasant to children, so that they take the brea
eagerly. When lactation is defective they may increase th
reflex stimulus to the nipple by making the child suck mo
vigorously and thus increase the quantity of milk. For th
reason such volatile oils as anise and dill may be useful as gala
tagogues. Garlic, on the contrary, renders the milk disagreeab
to children, so that they will not take it. Copaiba also rende
the milk disagreeable. The nearest approach to a true **galact**
gogue is jaborandi, but it affects the gland only temporaril
Beer and porter stimulate the secretion for a short time, b
they produce no proportionate benefit in the child, and nursi
mothers are, as a rule, much better without alcohol, and shou
rather take milk instead. When the milk of the mother is de
cient in saline constituents they may be supplied by giving th
appropriate salts to the mother.

Various physiological actions may be produced in the chi
by administering drugs to the mother. The administration of aci
to nursing mothers is generally to be avoided, as they are apt
cause griping in the child. Neutral salts as a rule pass into th
milk and cause looseness of the bowels in the child. Senn
castor-oil, rhubarb, scammony, sulphur, and probably jalap, a
as purgatives to the child. Salts of potassium administered
the mother will act as diuretics to the child. Turpentine a
ministered to the mother also can be detected in the urine of th
child; and this is also the case with copaiba and iodide of pota
sium. Opium administered to the mother may act as a narcot
to the child, and mercury, arsenic, and iodide of potassium ma
all be given to nursing children by administration to the mothe

CHAPTER XVII.

METHODS OF ADMINISTERING DRUGS.

Drugs may be used either for their local or general action, and sometimes for a combination of the two. Thus a solution of opium may be applied to the eye for its local effect in relieving irritation of the conjunctiva. It may be given by the mouth or injected under the skin to relieve pain and induce sleep, though the seat of the pain may be far removed, both from the point of injection and from the alimentary canal; or the opium may be applied in the form of a pessary in uterine disease to relieve pain, both by its local action on the part, and its general action on the system after absorption.

In order to produce their general action drugs may be introduced into the system through the skin, subcutaneous cellular tissue, lungs, mucous membranes, especially that of the alimentary canal, serous membranes and veins. The same drug applied in the same quantity through different channels may have different effects; for not only may slower absorption give rise to difference in the amount present at any time in the blood, as already explained (p. 38), but a reflex effect upon the organism may be produced by the local action of the drug at the place of introduction.

Application of Drugs by the Skin.

There are three different methods of applying drugs by the skin which are well recognised, these are :—

1. Epidermic, to the skin covered by epidermis.
2. Endermic, to the skin denuded of epidermis.
3. Hypodermic, to the subcutaneous cellular tissue.

Epidermic Application.—Remedies are applied to the unbroken skin chiefly for their local action on the part to which they are applied, or their reflex action through the nervous system on more distant parts. The epidermic applications are comparatively rarely used as a means of introducing drugs into the system, for the epidermis opposes such an obstacle to absorption, that it takes place slowly and with great difficulty.

In some of the lower animals, such as frogs, respiration takes place to such an extent through the skin, that the animal will live for a long time after respiratory movements have ceased. Respiration also takes place through the skin in man, but to a

very slight extent, the absorption of oxygen and the excretion of carbonic acid being only about $\frac{1}{200}$th part of that in the lungs.

The skin is able to absorb other gases as well as oxygen, such as sulphuretted hydrogen, carbonic acid, carbonic oxide, and the vapours of hydrocyanic acid, ether, and chloroform.

From the relief which persons who have been shipwrecked and have suffered from extreme thirst have received by bathing in sea-water, or putting on shirts wet with sea-water, it seems probable that the skin is able to absorb water, but this fact also shows that solids dissolved in the water are not absorbed by the skin. A good deal of discussion has taken place regarding the absorption by the skin of substances applied to it in a state of solution. Experiments on this point have usually been made with iodide of potassium, on account of the ease with which this salt can be detected in the urine. The results have generally been negative, but sometimes they have been positive. The general result is that the salt is never absorbed by the skin from the solution, and that in the cases where absorption has taken place, it has been due to the skin not having been washed after the bath, so that the iodide has crystallised on the surface, and has afterwards by friction of the clothes been rubbed into the sebaceous glands. It would appear that the fat in the skin as well as the epidermis presents an obstacle to the absorption of substances in solution, but when they are applied in such a form that they can readily mix with the sebaceous matter of the skin, they are tolerably readily absorbed, as for example when they are used in the form of ointment and well rubbed into the skin, so as to penetrate into the sebaceous follicles and also the sweat-glands. They are also absorbed when dissolved in ether, and especially in chloroform, even when simply painted over the surface. Alcoholic solutions are not absorbed when painted on in this way, although they may be absorbed if rubbed well in. It has been supposed that the absorption of chloroform solution is due to the chloroform mixing with the sebaceous matter. But, if true at all, this is certainly not the complete explanation of the fact, for as has just been mentioned, alcoholic solutions are not absorbed, although alcohol as well as chloroform will dissolve sebaceous matter. Waller has also shown that chloroform passes rapidly through the dead skin, carrying with it alkaloids dissolved in it. Its action is therefore to a great extent due to its peculiar endosmotic power.

The vascularity of the skin greatly alters its absorptive power. In the frog, absorption usually occurs rapidly through the skin, so that if the hind legs be immersed for a few minutes in a solution of cyanide of potassium, the salt is rapidly absorbed and can be detected in the mouth of the animal in a few minutes. But if the circulation be depressed by the previous administration of ether, curare, or any cardiac depressant, this absorption is

e system does not take place; for although the cyanide of tassium passes through the skin, yet, the subcutaneous circu- tion being feeble, it is not conveyed away from the point of cal application into the system generally.

The absorption of drugs may therefore be diminished by de- ession of the circulation either locally at the point of application in the system generally. It may be rendered more rapid by creased circulation at the point of application. A general in- ease in the circulation usually accelerates the circulation in the fferent parts of the body, but does not necessarily do so, for the ssels of a part may remain contracted while the general circu- tion is more rapid than usual.

A local increase in the circulation occurs from inflammation a part, or from temporary irritation such as that produced by bbing, or by the application of irritant substances. The use of ction, therefore, increases absorption not only by pressing the bstances employed into the sweat-glands and hair-follicles but so by increasing the circulation, and this effect will take place a still greater extent if the substances used have a tendency to use dilatation of the vessels.

The most common methods of applying drugs epidermically e baths, poultices, inunction, and friction.

Baths.

These may be either **local** or **general.** In **general** baths, e whole of the body excepting the head is exposed to the action various agents. According to the nature of the agent, baths ay be divided as follows:—

- I. Water.
  - A. Simple.
    - Cold.
      - (1) Ordinary full bath.
      - (2) Affusions.
      - (3) Spray.
      - (4) Sitz-bath.
      - (5) Foot-bath.
      - (6) Cold pack.
      - (7) Compresses.
      - (8) Douches.
    - Hot.
      - (1) Tepid bath.
      - (2) Warm bath.
      - (3) Hot bath.
      - (4) Hot foot-bath.
      - (5) Hot sitz-bath.
  - B. Medicated.
    - (1) Sea-bathing.
    - (2) Common saline bath. Artificial sea-water made by dissolving bay-salt in water (1 lb. of salt in 30 gals. of water).
    - (3) Carbonic acid and saline.
    - (4) Acid bath.
    - (5) Alkaline bath.
    - (6) Sulphurated bath.
    - (7) Mustard bath.
    - (8) Pine bath (Fichtennadelbad).

II. Vapour.	A. Aqueous.	(1) Simple.	Russian. Simple vapour.
		(2) Medicated.	Vinegar.
	B. Volatilised drugs, e.g. Calomel.		
III. Air.	Turkish bath.		

Cold Bath.—The effect of a bath depends very much upo its temperature.

In a cold bath, the temperature of the water is at or belo 70° F.

The **first** effect of immersion in a cold bath is contraction the vessels of the skin, accompanied by a feeling of chilliness an perhaps even of shivering. When the water reaches the level the chest, the respiratory centre becomes reflexly affected, and th respiration becomes gasping.

After a few minutes the cutaneous vessels begin to rela and the blood returning to the surface warms it. If the perso now comes out of the bath, dries quickly and rubs vigorousl the brisk circulation in the skin gives rise to a pleasant feeling warmth.

The feeling of warmth, or at least of lessened coldness, wi occur even if the bath be continued, but the increased circul tion in the skin allows the blood to be much more rapidly coole and thus the temperature of the body is much more quick reduced. When the blood which has been thus cooled in the sk returns to the nerve-centres, it appears to stimulate the vas motor centre and produce a second contraction of the cutaneo vessels, accompanied by a greater and more persistent chilline than before.

The **object** of cold baths is usually:—1st, either to have **tonic** and bracing influence on the body; or 2ndly, to **abstra heat** from the body in cases of fever.

As a **tonic** the cold bath is often very efficacious, and not on gives a feeling of strength and comfort, but tends to prevent tho who take it from catching cold so readily as they might otherwi do. The vessels of the skin are, as has already been mentione the regulators of temperature, and contract when they are expos to cold: thus protecting the internal organs from its chilli influence. But Rosenthal has found that when animals are ke for a long time in a warm chamber, their vessels lose to a gre extent their contractile power, and thus the animal becomes mu more readily chilled when exposed to cold. Cold baths, by trai ing, as it were, the cutaneous vessels to contract, tend to prot the organism from the injurious effects of accidental exposu Besides this, however, the stimulation to the circulation whi comes as an after-effect, tends to increase both the tissu change in the body, and the excretion of waste-substances from In consequence of this, cold bathing is usually followed by

creased appetite, so that the most favourable conditions for the trition of the body are supplied by cold baths, viz. increased pply of food, increased tissue-change, increased excretion of ste.

Cold baths may therefore be looked upon as a most **powerful** nic.

But while cold baths are of great use to those with whom ey agree, they **may be productive of great harm** when ey are indiscreetly used. As a general rule it may be said at when they cause much discomfort during the bath, and pecially if they cause chilliness afterwards, not removed by isk friction, they do harm rather than good. This is more pecially the case with children and with persons of feeble rculation.

Rosenthal's experiments, already quoted, show us that there a scientific basis for the popular notion of '**hardening**' by posure. But this process may be carried much too far, and stead of getting excitement of the circulation with all its atten- nt advantages, the effect of the bath may be to lower the mperature, depress the circulation, and greatly injure the utrition. The **risk** of such injury may be much **diminished** proper attention to the mode of giving the bath. In children delicate persons it is better, as a rule, to avoid immersing e whole body, and especially to avoid putting the feet in cold ater at the same time as the body. The best way is to let the erson sit down in a sitz-bath with the feet out and quickly to ash the water over the face, chest, back, and arms. Then a rge bath sheet is to be thrown around the body so as completely envelope it, and to prevent its being chilled during the process drying. For during the exposure of the body while the sur- ce is still wet, the chilling process is going on by evaporation uring summer, and by conduction by the cold air in winter. his may be seen markedly in persons of a feeble circulation ho rise from the bath with a feeling of slight glow, but lose completely and begin to feel chilly, if the process of drying delayed. Instead of a bath sheet, a dressing-gown made of owelling may be used. For very delicate persons the water of e bath should be rendered tepid by the addition of a little hot ater, and the face may not be sponged until after the rest of e body has been dried and the clothes put on. In winter the mperature of the room must not be too low; it is best, there- re, for delicate persons to take a slightly tepid bath before a re. Tolerance to cold is moreover often established by gradu- lly reducing the temperature of the water in successive baths, are being taken that no feeling of chilliness supervenes.

Sometimes the vigorous use of a flesh-brush over the chest ends to assist the reaction, and, if practicable, a short though risk walk is advisable just after the bath. It must not, however,

be long, as otherwise exhaustion might set in, and the appetite instead of being increased would be diminished.

Besides the tonic action which cold baths exert on the circulation and on the body generally, they appear to have a beneficial action in certain disturbances of the respiration.

The respiratory centre (p. 241) may be strongly affected reflexly by cold applied to the surface of the chest, as is shown by the gasping breathing, or inspiratory tetanus, observed when the cold water reaches the chest on walking slowly into it. In children suffering from broncho-pneumonia the severe attacks of dyspnœa which sometimes occur are relieved by a momentary immersion in water at a temperature of 60° F.

Cold sponging, as recommended by Ringer in his excellent work on Therapeutics, is exceedingly useful in laryngismus stridulus. It should be used two or three times a day whatever be the weather. If the child be hoarse, it should not be allowed to go out, but if there is no hoarseness, the fresh air, even if cold, will be advantageous. To arrest a paroxysm cold water should be dashed over the child.

Ringer also recommends it for a catch in the breath occurring in young children during the night, awaking them from sleep.

By abstracting heat, cold baths are useful in **fever** in several ways. By reducing the temperature they tend to lessen the amount of **tissue-change** which is already excessive, and they thus tend to husband the patient's strength, as well as to reduce the alterations of the tissues, such as fatty degeneration of the heart, which occur in consequence of a high temperature. By lessening the temperature also, they diminish the rapidity of the pulse, and by thus prolonging the cardiac diastole give more opportunity for the nutrition of the muscular walls of the heart.

A high temperature, if it is remittent, is better supported than a lower temperature which is continuous, and therefore Liebermeister, to whom we in a great measure owe the recent introduction of cold baths as a therapeutic measure, uses them with the object of increasing and prolonging the remissions in temperature which usually occur spontaneously in febrile diseases—producing a condition of 'relative apyrexia.'

There are several ways of employing cold baths to reduce temperature. One is that of **cold affusion,** in which the patient is put into a tub and four or five gallons of cold water thrown over him. Another is to place the patient in a **bath** at about 90° F. and **gradually reduce** the **temperature,** by the addition of cold water, to 80°, 70°, or even 60° F. The patient is kept in this from ten to twenty minutes, according to his strength and the height of the temperature. As the temperature continues to fall for some time after the removal of the patient from the water, the bath should not be continued so long as to lower it to

e full extent required while he is in the bath, lest collapse cur afterwards.

Instead of the bath being gradually cooled down, it may be ed at once at a temperature between 60° and 90° according the condition of the patient, and if the temperature be very gh, the water must be cooled still more by means of ice, and action aided by ice given by the mouth and rubbed or laid on the surface of the body. This treatment may be adopted en although pneumonia be present, if the patient's life is reatened by an excessive rise in temperature. When the temrature rises again the bath should be repeated.

Cold Pack.—The pack is a less efficient means of abstractg heat from the body, but it is useful in causing a different stribution of blood in the body. It is therefore sometimes ry useful in lessening delirium and producing quietness and eep. In employing it, a wet sheet is wrung well out of cold ater and wrapped tightly around the patient; over this are rapped one to three blankets. A little heat is abstracted at rst by the cold of the sheet, but this is very little, and indeed is asserted by some that cold packs, instead of abstracting heat, revent its escape. The skin soon becomes warm, and frequently rofuse perspiration is produced. A certain amount of heat is st, though perhaps not very much, by the evaporation through e blankets. It is probable, however, that the production of eat is to a certain extent lessened, at least in restless patients, their movements being mechanically restrained by the sheet, nd also by the blood being withdrawn from the internal organs nd muscles to the skin. As the pack restrains the movements a most complete way and with a force against which it is in ain to struggle, while at the same time it is comfortable and othing, it frequently induces sleep when narcotics have been seless.

Cold sponging is sometimes a very useful means of abstractg heat in cases of fever, where the patient is weak and the mperature, though perhaps not going above 104° or 105° F., nds rapidly to regain its former height after cooling, and where seems inadvisable to subject the patient to the frequent movement in and out of bed required in cold baths. The loss of eat consequent on cold sponging is due partly to the applicaon of the cold water, but it is due chiefly to the evaporation hich takes place from the surface of the body. Consequently ponging with tepid or even with hot water will also reduce mperature.

Cold Douches.[1]—In this form of bath a stream of water aving considerable force is directed against a part of the body.

[1] For a short and concise account of the various appliances used in hydrotherapeutics, *vide* Paper on 'Rational Hydro-therapeutics,' by G. L. Pardington, M.D., *Practitioner*, Jan. 1884.

The stream may either be unbroken, and to this the name douc is usually restricted, or it may be broken up by delivery throu a rose into a number of minute streams, so as to form a show or rain bath. If the douche is large (one or two inches in di meter) it causes a great amount of shock and sometimes do much harm. Usually a stream of a quarter of an inch diameter is quite sufficient for all purposes. Douches are chie applied to the spine, spleen, liver, joints, anus, and vagi The **spinal douche** usually consists of a single stream, and m either be allowed to fall vertically upon the spine, the body bei more or less inclined, or it may be delivered from a horizont pipe with the body in an upright position. It is useful as stimulant in melancholia, cerebral anæmia, and general debili To avoid too great depression it is better to apply hot and c water alternately, unless it is used immediately after a h application such as a spinal pack. Douches to the head a useful in alcoholic coma. Douches to the **liver and spleen** ha been found useful in chronic congestion and enlargement of th organs. The douche applied to stiffened **joints** appears sometim to be of considerable service.

The **ascending douche** is usually delivered through a ro so as to form a shower, and it is directed against the perinæu while the patient is in a sitting position. It is useful in hæm rhoids and pruritus ani, and when used at a regular hour dai first tepid and then cold, it is useful in constipation.

The vaginal douche is used by the patient lying on her ba with her knees drawn up and with the pipe in the vagina. I useful in vaginal leucorrhœa and cervical catarrh, and in chro subinvolution and hyperplasia the hot douche at 105°, F. to 110° twice a day for several minutes is of much service.

Local Application of Cold.

Sitz-bath.—When a person sits down in a cold sitz-bath, when he sits down in an empty bath and cold water is pou into it, until it covers the hips, the vessels of the parts expo to the cold contract, and the blood is consequently driven i other parts of the body. It would appear, however, that not o do the vessels of the skin contract, but also that contraction the intestinal vessels occurs reflexly through the splanch nerves: so that in consequence there is a feeling of warmth a fulness in the head, an increase in the volume of the arm measured by the plethysmograph, and a rise of temperature the axilla.

A cold sitz-bath, when applied only from one to minutes and followed by a brisk rubbing, tends to increase amount of blood in the abdominal organs, to quicken the ci

[1] Pardington, *op. cit.*

ion in the liver and spleen, and to augment the activity of the vements of the intestine and bladder. It may therefore be d with advantage in constipation and in disorders of the dder depending on weakness, such as either difficulty in expel- g the urine or difficulty in retaining it.

In pregnancy, cold sitz-baths are sometimes useful, giving a ling of comfort and strength, and lessening the sensations of gging in the abdomen.

Where any tendency to premature expulsion of the fœtus sts they should be avoided, as the increased circulation which y cause in the pelvic organs might lead to abortion.

When cold sitz-baths are continued for a long time, as from to thirty minutes, at a temperature from 8° to 15° C., the traction of the abdominal vessels appears to be more perma- t, and thus they may be employed for the purpose of lessen- congestion in the intestine, and may be used with advantage cases of obstinate diarrhœa and congestive enlargement of the r and spleen.

The effect of a prolonged sitz-bath in lessening congestion of abdominal organs is greatly increased if it be preceded by a sh-down, with brisk friction, so that the blood may be attracted the other parts of the surface as well as driven out of the omen by contraction of the intestinal vessels.

Cold Foot-bath.—Coldness of the feet not only causes dis- nfort to the person, but if it occurs at night, it may prevent p. Putting them in hot water may warm them temporarily, will not do so permanently, and a much better way is to put m in cold water, rub them briskly while in it, and then dry m thoroughly with a soft towel, giving them a rub afterwards h a rough bath-towel.

Cold foot-baths are to be avoided during the menstrual period, they have a very great power indeed to check menstruation frequently bring on amenorrhœa. Their power to check menstrual flow is popularly known, and sometimes great m is occasioned by young women using them to check men- nation, in order that they may be able to attend some party pleasure.

Cold Compresses.—By the application of cold over the rse of an artery, it can be made to contract, and the amount blood to the district which it supplies may consequently be inished. This is shown by the accompanying curve taken by nternitz from the radial artery (Fig. 156).

The first half of the curve (*A*) was taken before anything been applied to the arm. The instrument being allowed to ain, ice was next applied to the arm, and the second half the curve (*B*) shows the contraction which it had produced he artery.

When the cold application is allowed to remain for a while,

it gradually acquires the temperature of the body, and if evap
ration be prevented, it comes to have the same effect as warmt




FIG. 156.—Tracings from the radial artery at the wrist: *A* before and *B* after the application o cloth dipped in cold water round the arm. (After Winternitz.)

but if constantly renewed, the contraction of the artery may kept up. A similar contraction to that just noticed in the ve sels of the arm may be produced in the vessels of the head cold applications around the neck. This is shown by the fall temperature in the auditory meatus. Cold may be applied the neck either by a bag containing ice, or by an india-rubb bag, or coils of tubing, through which cold water may be ke constantly flowing.

As a very large proportion of the whole blood in the bo flows through the carotids, the application of cold to the ne may act as a general antipyretic. The accurate application ice-bags to the neck so as to cover the supra-clavicular regio also, and thus to cool the blood in the subclavians, has be recommended in fever, to reduce the temperature generally. tonsillitis cold to the neck is useful, for its local action.[1]

Cold to the head is frequently applied in delirium, men gitis, and severe cephalalgia. It may be applied either by a b containing cold water or ice, or still more conveniently by a c consisting of india-rubber tubing through which water constan flows.

A continuous stream of water through an ordinary water-l reduces the temperature slightly and thus relieves the sympto in prolonged fever.

Warm Baths.

Tepid Baths.—These baths range from 85° F. to 65° F. 29·4° C. to 18·3° C. They are chiefly used for cleansing p poses, and at the lower margin of about 65° F. they may be u for a somewhat tonic action in persons of feeble circulat (p. 461).

Warm Baths.—These range from 97° F. to 85° F., 36·1° C. to 29·4° C. When the water is above these tempe tures it forms a hot bath. The warm water softens the dermis, and is thus of much use in chronic skin-diseases. dilates the vessels of the surface of the body, and thus tend

[1] Stephan, *Allg. med. Central-Ztg.*, No. 87, 1884.

sen any internal congestion. At the same time it tends to uce perspiration. On this account the warm bath is useful lessening pain depending on congestion of internal organs l in preventing congestion from going on to inflammation. is therefore very serviceable when there is a threatening of nchitis, or gastro-intestinal catarrh, colic, &c. It tends to uce the temperature both by dilating the peripheral vessels l inducing perspiration, and is therefore useful in febrile ditions. By withdrawing blood from the brain it tends to uce sleep.

Hot Baths.—These range from 97° F., or 36·1° C., upwards. much higher temperature than can be endured at first can be ne if the temperature be gradually raised by the gradual lition of hot water to the bath while the body is immersed, l the bath may thus be raised as high as 110° F. Hot baths only prevent loss of heat from the surface, but if above the nperature of the blood, actually impart heat to the body. e consequence of this is that the temperature of the body rises y rapidly, and therefore the respiration and pulse both become y quick. The peripheral vessels become still more dilated n in the warm bath, and the blood pours so rapidly through m that, in spite of the quick and powerful action of the heart, re may be a tendency to syncope when the head is raised. er remaining in such a bath from ten to twenty minutes, the ient must be carefully lifted out so as to avoid any risk of ncope, and should be wrapped in warm, dry blankets. The bath is a still more powerful agent than the warm bath in ducing sweating, and is employed in cases of dropsy.

Hot Foot-bath.—A hot foot-bath has a general effect that hardly be explained by the simple dilatation of the vessels in feet and consequent derivation of blood to them. It seems, leed, to exert some reflex action on other parts of the body l causes a general feeling of warmth. It is very useful as an unct to vascular stimulants in relieving congestion and pre- nting inflammation, as in threatened catarrh, bronchitis, &c. nen the feet are put into a hot bath, we find that the femoral eries become much dilated and pulsate much more vigor- sly than they did before. It is not improbable that this atation extends beyond the femoral to the iliac arteries, and t the supply of blood is increased in the pelvic organs as well in the feet. In cases of amenorrhœa, especially where it has en brought on by exposure to cold, hot foot-baths tend to store the menstrual flow. They should be begun four or five hts before the period is expected, and continued during the ne it ought to last. Their efficacy may be increased by the lition of a little mustard.

Hot Sitz-baths.—These have a still greater tendency than t foot-baths to increase the circulation in the pelvic organs,

and they may be used either alone or with mustard in t manner just described in cases of amenorrhœa.

Poultices.—Poultices are simply a means of applying he and moisture to a limited portion of the surface of the boc Their mode of action has already been discussed (p. 342). Th consist essentially of some farinaceous substance made into paste with hot water, and the most common substances used bases are linseed meal, bread, bran, oatmeal or starch. In cases, not only should the water with which the poultice is ma be **perfectly boiling**, but the bowl in which it is to be mixed, t spoon with which it is to be stirred, and the tow or flannel which it is to be laid, should all be as hot as possible. By addi the linseed meal to the water and constantly stirring, there less chance of the poultice being knotty than if the water w added to the meal. If the poultice is intended to be applied a wound, sore, boil, or carbuncle, it should be spread upor piece of flannel or tow and applied directly to the skin, beca the softening action of the water and oil it contains on t dermal tissues is required as well as the warmth. But wh




FIG. 157.—The upper figure represents the bag empty; the lower one the bag filled and sewn

the poultice is used to relieve pain, congestion, or inflamma of the internal organs, as in pleurisy, pneumonia, or colic—in tinal, biliary, or renal, it ought not to be applied directly to skin, but should be separated from it by something which ducts heat badly, such as flannel. The reason for this is t it is impossible to apply a very hot poultice directly to the s on account of the pain it causes, whereas if a substance wh conducts heat badly be interposed, the poultice can be app boiling hot, the heat gradually passes through without becon inconveniently great, and is retained for a much longer time

In order to accomplish this, a flannel bag should be prepared, onvenient size being twelve inches by eight; this should be ed at three edges and open at the fourth; one side of it uld be about one inch or one inch and a half longer than the er, as represented in the diagram (Fig. 157), and it is con- ient also to have four tapes attached at the points which form corners when the bag is closed, in order to keep the poultice position. Besides this, another strip of flannel should be pared of the same breadth as the length of the bag, and long ugh to wrap round it once or oftener. Crushed linseed, l, and spoon should then be got together, and the spoon and l thoroughly heated by means of boiling water; the poultice uld then be made with perfectly boiling water, and rather . As soon as it is ready it should be poured into the bag, viously warmed by holding it before the fire; the flap which rmed by the longest side of the bag should now be turned n and fastened in its place by a few long stitches with a dle and thread; it should then be quickly wrapped in the p of flannel (also previously warmed), and fastened *in situ*, if essary, by means of the tapes. It may be covered outside n a sheet of cotton wool.

Medicated Baths.

The addition of stimulating substances, such as **salt**, to the er, increases the stimulation to the skin, and the amount of r-reaction.

In **sea-bathing** the stimulating effect of the salt is further reased by the mechanical shock of the waves, and sometimes by the friction of the fine sand of the beach. Sea-bathing differs from baths in the fact that muscular exertion is bined with it, either in simply moving about and retaining 's footing, or still more in swimming.

Carbonic Acid Bath.—This is a saline bath, containing two three per cent. of chloride of sodium, and not more than one cent. of chloride of calcium, with varying proportions of carbonic acid up to 3 grammes in the litre. It has been ommended for chronic heart-disease, both functional and anic, and is said to act as a cardiac tonic.[1]

Acid Bath.—This bath is made by mixing eight ounces of ro-hydrochloric acid with a gallon of water at blood heat ° F.) This is sometimes used as a foot-bath, but it is better plied as a compress. A flannel roller about a foot wide, and g enough to go twice round the body, should be soaked in the dulated water, wrung thoroughly out, and rolled round the ion of the liver; a piece of oil-silk, large enough to cover it

[1] Aug. Schott, *Berl. klin. Wochensch.*, No. 33, 1885.

completely and leave a little margin over, should then be pu over it. It may be worn for several days, being renewed ever night, and it is chiefly useful in chronic disease of the liver.[1]

Alkaline Bath.—This is made by adding crystallised ca bonate of sodium to water in the proportion of about one drachr to each gallon. It is chiefly used in chronic skin-diseases.

Sulphurated Bath.—This may be made by dissolving su phurated potash in water, about half a drachm to the gallon, o in imitation of Barège waters, may be made by mixing sodiur sulphide, sodium carbonate, and sodium chloride in the propo tion of twenty grains of each to the gallon. These are chiefl useful in chronic scaly skin-diseases, and in rheumatism. Muc more benefit is usually obtained by a visit to sulphur spring such as those of Aix-les-Bains, Aix-la-Chapelle, Barège, Ha rogate, or Strathpeffer, than from the use of sulphur baths a home.

Mustard Bath.—This is made by adding mustard to wat in the proportion of about half a drachm to a drachm and quarter per gallon. It is a powerful stimulant, but must not b applied too long. It must be remembered that, while sligh stimuli to the skin increase the frequency and energy of th cardiac contractions and the rapidity of the circulation, an raise the temperature, severe irritation of the skin lessens th frequency of the pulse and the rapidity of the circulation, dilat the vessels and lowers the temperature.[2] The patient shou never be allowed to remain more than ten minutes in the bat and should be at once removed as soon as he feels eith burning of the skin or icy coldness. Mustard baths are general used in order to quicken the appearance of the eruption in th exanthemata.

Pine Bath.—This is made by adding a decoction of the shoo of pines to water, but it is more convenient to use the oleu pini sylvestris in the proportion of one minim to the gallo These baths are used in rheumatism, gout, paralysis, scrofu and skin-diseases.

Vapour Baths.

In these the body is exposed to steam instead of being i mersed in hot water. The effect is much the same as that the hot bath. The so-called Russian bath consists of a roo filled with steam and provided with benches at various level The higher the level the greater is the heat, and usually, excep ing on the lower benches, it is only possible to breathe with a

[1] Squire's *Companion to the British Pharmacopœia*, 13th ed.

[2] Naumann, *Prager med. Jahrschr.*, 1863, i. p. 1, and 1867, i. p. 133; Heid hain, *Pflüger's Archiv*, Bd. iii. p. 504, and Bd. v. p. 77; Riegel, *Pflüger's Arch* Bd. iv. p. 350.

nfort by holding a sponge dipped in cold water before the nose. om this room the bather goes to another where he is drenched h cold water by a douche, and is then quickly dried, and owed to rest for some time before dressing. These baths are efly used in chronic rheumatism. They are liable to the same ections as the hot bath, and to a still greater extent, for the alation of the hot steam produces greater difficulty of breath-, greater acceleration of the pulse, and greater tendency to ncope. Vapour baths, in which the body only is exposed to action of the steam, and the head is left out are much better. ey are usually applied either by means of a kind of box in ich the body of the bather is enclosed while the head remains side, or else by introducing steam under the bedclothes, which supported by a kind of cradle, while the bedclothes are tucked htly round the patient's neck to prevent the escape of the pour. The latter plan is very useful in cases of dropsy and emia, as it induces a copious perspiration and does not ex-ust the patient nearly so much as a hot bath. In cases of nte rheumatism a vapour bath of vinegar has been recom-nded.

Calomel Fumigation.—This is used as a means of inducing e general action of mercury. The patient is seated naked on vickerwork chair, underneath which is put a stand holding a allow cup containing 20 to 30 grains of calomel. The calomel volatilised by means of a spirit lamp, and a blanket or water-of sheet being thrown round the patient so as completely to velope himself, his chair, and the fumigating apparatus, the lomel fumes become condensed upon his skin in a fine state of vision. It is absorbed with considerable rapidity, probably from coming mixed with the sebaceous secretion from the skin, and e general action of mercury is quickly induced.

Air Baths.

Turkish Bath.—The Turkish bath usually consists of three oms, although frequently there are more. The temperature of e first, or dressing-room, is moderate, that of the second is gher, and that of the third is higher still. In the first room, e bather, after undressing, winds one towel round his loins, d a second round his head in the form of a turban. If he has y tendency to cerebral congestion, the second one may be wet. e then passes into the second room, where he usually waits a ort time before passing into the third room. Some people, owever, go directly into the third room. In both the second d third rooms the bathers partake freely of cold water. A few inutes' stay in the warmest room is usually sufficient to make e bather perspire freely, and he then returns to the second or


cooler room, where he may remain half an hour or more, accord ing to circumstances. He may then be shampooed, the surfac of the body being rubbed, the muscles kneaded, and the smalle joints extended. He is next washed with a lather of soap, an sluiced with basins of tepid or warm water. For some people is most agreeable after this to be simply wrapped in warm towe and allowed to repose in the dressing-room. Others prefer t finish up with a cold douche before proceeding to the dressing room. Here they remain resting for a considerable time before the again dress. Turkish baths are exceedingly useful in chroni rheumatism and gout, and in persons suffering from the effect of malaria. The chief objection to the Turkish bath is th length of time that it takes. In some persons it has a weakenin effect, but in many others it has none. The chief precaution are not to stay too long in the hot room, and to leave it at onc if giddiness or a feeling of tightness in the head comes on. the skin perspires with difficulty, the necessity for caution i entering the hot room becomes still greater, and it is advisabl rather to spend a longer time in the second room, and drin freely of water before entering the hotter room, if, indeed, th be entered at all on the first few times of taking the bath. Pe sons who suffer from a feeling of exhaustion after a Turkish bat should not take a cold douche nor a plunge into water after pe spiring, but should simply allow themselves to cool very gradually and should take some stimulant, such as coffee or beef-tea, whi doing so. Persons who suffer from malaria also should spend good while in the second room before attempting to enter th third, as the sudden application of heat to the skin and lung seems to irritate the vaso-motor centres and cause chilliness, even shivering.

Friction and Inunction.

Friction of the skin causes first a temporary contraction the vessels, followed by a more or less permanent dilatation, s that the skin continues red for a length of time after the irrita tion has ceased. This redness is accompanied by a warm glo from the **increased circulation** in the skin, and friction is there fore useful as an adjunct to cold baths. Besides this, frictio along the extremities in an upward direction tends to aid th flow of lymph, and thus to **remove** the products of **waste** fro the muscles.

The fascia covering a muscle forms a pumping apparatus fo removing waste-products from the muscles (Fig. 158). It consist of two layers, *a b* and *e f*, and between these are lymph spaces, som of which, *x*, are seen in transverse, and others, which appear blac from the injection with which they are filled, are seen in lon gitudinal section. Each time the muscle contracts, it become

cker, presses the two layers of fascia together, and drives the nph from the spaces onwards into the lymphatics. Each time muscle relaxes, the layers of fascia tend to separate, and



G. 158.—Injected lymph-spaces from the fascia lata of a dog. The injected lymph-spaces are black in the figure. (After Ludwig and Schweigger-Seidel.)

nph from the muscle, carrying with it the waste-products, s the spaces between the layers. The action of the muscle lf thus tends to remove the waste-products which give rise to igue (*vide* Massage, p. 131), but after over-exertion their noval may be greatly aided by gentle but firm upward friction, ich will have a similar action on the fascia to the alternate mpression and separation of its two layers, caused by the action the muscle itself.

Gentle firm friction thus lessens or may even remove en- ly the feeling of **fatigue** and weight in the extremities after rtion. When applied to the nape of the neck, or along the ne, it is sometimes useful in headache, in nervous irritability, d in sleeplessness.

When applied between the shoulders in persons suffering m flatulence, it appears to aid the expulsion of gas from the mach.

The effect of friction as a **counter-irritant** is greatly in- ased by the use of stimulating liniments. These are applied pouring a little into the hollow of the hand and then rubbing over the surface of the body, or else by soaking a piece of nnel in the liniment and rubbing the skin with it. Linimen- m ammoniæ applied thus to the chest is useful in the bron- itis of children ; and linimentum camphoræ compositum, B.P., linimentum terebinthinæ may be used in a similar way for ults.

In chronic inflammation of joints, liniments may be applied a similar way. Sometimes it may be advisable also in such es to swathe the joint in a piece of flannel or lint, soaked in liniment so as to procure more continuous application.

Inunction.—Metallic salts are very slightly, if at all, ab- bed from the skin when applied to it in watery solution, and ped off without being allowed to dry. But when applied in

the form of ointments a considerable absorption takes plac especially if lanolin be used as a basis. Advantage is taken this, in order to obtain the *general* action of mercury without i *local* effect on the intestinal canal. For this purpose mercuri ointment is rubbed on the skin, and especially on those par where the epidermis is thin, as under the axillæ and on th inside of the thighs.

Absorption also takes place, however, through the skin of th hands, and if the ointment is not rubbed on by the patient hin self, but by another person, in whom the action of mercury undesirable, it has been recommended that the latter shoul cover his hands with a piece of bladder thoroughly well oiled i order to prevent absorption.

In children, instead of applying the mercurial ointment b inunction, it is customary to smear the ointment on a piece flannel, and to keep it applied to the abdomen of the child b means of a bandage.

Endermic Application of Drugs.

This method consists in applying the drug to the skin pr viously denuded of its epidermis or epithelial layer by blisterin The drug may be applied in the form of powder, solution, oin ment, liniment, or plaster, but most frequently in the form powder. The drug is more readily absorbed when applied i this manner than when applied over the epidermis. Canthari may be used for the purpose of raising a blister, but a mo convenient method is to fill a thimble with cotton-wool or li soaked in the strongest liquor ammoniæ, apply it to the sp and keep it on for five minutes. If the cuticle has not the risen in a blister apply a poultice until it rises. Cut off th cuticle, place the powder on the denuded surface, and cover with a piece of oil-silk fixed in position by two pieces of strappi crossed over it. This method was chiefly employed for the loc application of morphine. It has now been almost entirely supe seded by the hypodermic method, but may still be occasional employed in cases where it is advisable to combine the counte irritant action of the blister with the local sedative effect of th morphine.

Hypodermic Administration of Drugs.

This method, the introduction of which we owe to Dr. Ale ander Wood of Edinburgh, possesses great advantages.

It consists in the injection of a solution of a remedy und the skin. Absorption takes place from the subcutaneous cellul tissue rapidly, and it is much less likely to be modified by alter conditions of the organism than absorption from the stoma

l intestine. For in the intestinal canal there is not only the dition of the circulation to be taken into consideration, but fulness or emptiness of the stomach and intestine, the con- on of their epithelial covering and of their nervous supply, l the state of the liver. These conditions may not only delay entirely prevent absorption.

The advantages of the hypodermic method, therefore, are 1st, tainty of effect, and 2nd, **rapidity** of action.

As absorption of a drug takes place so much more rapidly n the subcutaneous cellular tissue than from the stomach, a s quantity is excreted during the process of absorption, and con- uently a smaller quantity of the drug is required (p. 38 *et seq.*).

But absorption does not take place with equal rapidity from parts of the intercellular tissue. The vascularity of this sue, and the rate of absorption from it, are greater on the nples and breast than on the back, and greater on the inner n on the outer surface of the arms and legs.

As the liquids used for hypodermic injection are usually ncentrated solutions of powerful poisons, it is important that ther more nor less than the quantity previously determined on should be administered. The syringe consists of two parts




FIG. 159.—Syringe for hypodermic injection.

ig. 159), a glass barrel in which a piston plays airtight, and a llow needle which fits tightly on to the end of the syringe either th or without a screw. The bore of the needle being very fine is apt to get choked by rust, or by crystals of the substance last nployed for injection forming within it, and rendering it im- rmeable and useless. In order to avoid this it should be care- lly washed with water each time it is used, and a small piece thin wire kept constantly in it during the intervals of use, or, tter still, a little oil drawn into the bore of the needle. When e syringe has not been used for some time, the packing of the ston is apt to shrink, so that it will no longer either suck in uid or drive it out of the barrel efficiently. This may often be medied to a great extent by soaking the syringe for a short me in warm water and driving the piston up and down in it. this is insufficient the piston may be taken out, and sufficient read wound round it to make it work. Care must be taken so that the needle fits tightly on the syringe, and that no akage takes place at the junction. The liquid to be injected ould contain no solid particles which may obstruct the needle, nd if any such should be present, the fluid may be filtered rough clean blotting-paper.

The exact quantity required, and no more, should then b drawn up into the syringe and injected. Some syringes have small screw upon the piston, so as to stop its movement at an required point. With such a syringe the barrel may be fille quite full of the solution, and the required quantity injected b forcing the piston down until it is stopped by the screw. Th advantage of this arrangement is that if any leakage shoul occur, the screw may be moved further up, and an additiona quantity of solution injected without the necessity of withdraw ing and reintroducing the needle under the skin. If all prope precautions be taken, however, the necessity for such a proce dure will rarely arise.

Convenient places for injection are the outside of the arm near the deltoid, the fore-arms, or the thighs. In order to avoi the risk of introducing the needle into a vein, the injectio should not be made over a vein visible through the skin. Th skin should be pinched up between the finger and thumb, th needle pushed directly through it, and then passed onwards little way obliquely in the subcutaneous cellular tissue.

Objections to Hypodermic Injections.—The chief objec tions are, (1) the pain caused at the time by the introduction o the needle, or by the drug itself after its injection, (2) the in flammation which either the needle or the drug may give rise t subsequently, (3) the scars which may be left by the frequen repetition of the injection, (4) the danger of communicating specific or contagious disease, (5) the danger of injecting th drug directly into a vein, and thus producing a dangerous o fatal effect from the too rapid entrance of the drug into th circulation. With a little care these untoward results may b almost entirely avoided. If the needle is well sharpened th pain of introducing it is very slight, and may be still furthe lessened by making the patient take several deep breaths i rapid succession before the injection is made. If the patient i excessively sensitive, partial or complete anæsthesia of the par may be produced by cold or by carbolic acid (p. 204).

The solutions should always be perfectly free from solid par ticles and should be as neutral and bland as possible. Metalli salts have their irritating properties diminished or removed whe combined with albumen or with an alkaline citrate or tartrate s as to form double salts.

By washing the syringe and needle thoroughly out wit carbolic acid, the danger of conveying any specific or contagiou disease is rendered very slight, and it may be completely avoide by heating all parts of the syringe in a spirit-lamp before usin them. The syringe employed by Koch in his experiments o the effects of micro-organisms in producing disease (Fig. 159) admirably adapted for this purpose, as all parts of it can b readily heated, and the padding upon the piston, which is mo

kely to retain infective matter than any other part of the ringe, can be renewed each time that the instrument is em-oyed. In order to prevent pain or inflammation being caused the solution injected, care should be taken that its reaction is nearly as possible neutral, and that the quantity should not great. The smart which follows the injection is lessened by bbing the finger gently over the part so as to distribute the uid in the subcutaneous tissue. If it is necessary to employ ch large quantities as half a drachm or a drachm, as may be e case with ergot, it is better not to inject the solution under e skin but into the substance of a muscle, such as the gluteus aximus.

Cicatrices are not apt to follow injection if the precautions ready mentioned have been taken, and if the injections are not ade too frequently at the same point.

Application of Drugs to the Eye.

For inflammation of the lids, ointment is smeared between e edges.

Cold water is applied to the conjunctiva for its tonic action, keeping the eyes open and then dipping the face into a basin water.

Strong solutions like that of atropine are applied to the con-nctiva by dropping them into the outer canthus of the eye and lowing them to flow over the surface. If such a solution is to applied frequently, it may be dropped into the inner canthus, d the head held so as to allow it to drop out of the outer nthus; for when the reverse procedure is employed the atro-ne may pass down the lacrimal duct, and being absorbed may oduce its general effect upon the system and cause symptoms poisoning.

Application of Drugs to the Ear.

Astringent solutions are usually applied to the auditory eatus, by injecting them in a gentle stream by means of a nall syringe (Fig. 160).




FIG. 160.—Vulcanite syringe for injecting solutions into the ear.

For the mode of injecting into the middle ear, special eatises on aural surgery must be consulted.

Application of Drugs to the Nose.

Drugs are applied to the nose in the form of powder, whi may be taken in the same way as **snuff** by putting a little on t top of the thumb, holding it in front of the nose and strong inspiring; or the powder may be put on a small piece of car board in which a pinhole has been made just under the powd or with a small perforated spoon like that used in Scotland f snuff. Sternutatories may be used in this way, and so m Ferrier's powder for soothing the mucous membrane in cases commencing catarrh.

Fluids may be applied by **insufflation**, the nose being simp immersed in them and strong inspiration being made.

They may also be applied by the **nasal douche**. This co sists simply of a long india-rubber tube to act as a syphon (F 161). The upper end of it is placed in a vessel filled with t




FIG. 161.—Nasal douche.

solution to be applied, and it is prevented from falling out b hollow lead weight attached to its upper end. At the lower e is a conical nozzle, which completely plugs the nostril. T tube being filled with the fluid by suction so that it commen to act as a syphon, the nozzle is placed in one nostril, and t head is held with the mouth open over a basin. In this positi the posterior nares are cut off by the soft palate from the p rynx, and the solution passes up one nostril and not throu the other, so that the nasal cavity is washed out and its muc

membrane acted upon by the solution which is employed. By altering the position of the head, both in insufflation and in washing with the douche, the part of the nose reached by the fluid will be changed. Thus when the head is held much forward, the anterior and upper part of the nose will be chiefly cleansed, when the head is held upright, the posterior and lower, and when the position is intermediate, the middle part of the nose will be most affected.

The nose may also be washed out by using a large syringe (pear) with a piece of india-rubber tubing fitted on to the nozzle. If at the moment of injection the patient be directed to say 'anemone' (or some such word) and expectorate, the injection will come out of the mouth.

Pure water is irritating to sensitive mucous membranes like that of the nose, and so instead of employing pure water it is much better to use a ·5 to 1 per cent. solution of common salt, which is a bland, non-irritating fluid. Such a solution may be made by adding a drachm of common salt to a pint of water.

Fluids may also be applied to the nose in the form of spray, either directed simply into the nostrils, or by means of a catheter perforated with a number of minute holes, and introduced along the floor of the nasal fossæ. The former may be used for applying astringent and deodorising solutions, and the latter for the purpose of washing out the nose and removing hardened secretions.

Application of Drugs to the Larynx.

Solid powders may be applied to the larynx by **insufflation.** The insufflator (Fig. 162) used for this purpose consists of a tube curved at one end, and having at the other a piece of india-rubber tubing or an india-rubber ball, by which a powder may be blown through the tube near this end of the tube. There is a small opening in its side through which the powder may be introduced, and this is afterwards covered by a sliding ring or a piece of india-rubber tubing so as to prevent the powder from escaping. The bent part of the tube is carefully introduced into the mouth so as not to cause retching by touching the tongue or soft palate, and, when the end of it points down over the larynx, the patient is told to take a deep breath. At the moment of inspiration the operator forces the powder out of the tube into the larynx, either by blowing through the india-rubber mouthpiece, or by compressing the india-rubber ball. Morphine applied by this method gives more relief than almost anything else in laryngeal phthisis. About one-sixth of a grain is sufficient, and in order to give it sufficient bulk it may be mixed with either starch or bismuth.

Solutions may be simply applied by means of a sponge firmly tied to a piece of whalebone having the proper curve; as the

patient inspires this is pushed down the larynx. Doubts ha
been expressed as to whether the sponge does get through t
larynx, but I have seen the crico-thyroid membrane project
forwards by the sponge applied in this manner.




FIG. 162.—Insufflator for applying powders to the larynx. A, piece of india-rubber coverin
opening in the insufflator, by which the powder is placed in it. B, india-rubber tube by w
the powder is blown out of the insufflator into the larynx. C, curved end of insufflato
introduction into the pharynx.

Nitrate of silver applied in this way gives relief in cases
phthisis, but it is a very rough method, and the application
the solution by means of a brush, with the aid of the laryngosco
is much to be preferred. When the sponge has not been firr
fixed it has been known to come off and fall into the trachea.

Fluids may be applied by a brush to the larynx, the opera
using the brush with one hand and holding the laryngosco
mirror with the other, while the patient holds his tongue
himself. If the patient is made to take several deep brea
in succession, a slight anæsthetic condition is produced, wh
renders the operation much more easy.

Caustics are best applied to the larynx by means of a caus
holder in which the caustic is concealed until it reaches the po
of application, when it can be projected by a touch of the fin
and again withdrawn at the wish of the operator.

Solid nitrate of silver may also be applied by heating the
of a partially curved metal rod, then touching the stick of caus
In this way a uniformly-diffused and minute quantity of
caustic is melted on to the end of the instrument, which is t
applied by aid of the mirror.

Liquid may be applied to the larynx in the form of spr
produced either by means of Richardson's apparatus or b
current of steam. The nozzle of the spray-producer may
simply directed towards the pharynx, or the tongue and
cheeks may be protected from the spray by a cylindrical g
speculum.

Application of Drugs to the Lungs.

Inhalations.—**Vapours** employed as inhalations act not y on the bronchial tubes but upon the larynx, pharynx, and trils. One of the commonest is that of simple hot water. A is filled about half-full of boiling water and the head held r it, the steam being kept in by means of a napkin or towel own over the head and around the mouth of the jug. This plication often gives great, though temporary, relief in nasal, yngeal, and bronchial catarrh.

Vapour may be **medicated** by the addition of various sub- nces to it, such as carbolic acid, tincture of benzoin, creasote, pine oil. But in order to gain the full advantage of the mixture of these substances it is better that the inspired air uld not merely play over the surface of the hot water, but be wn through it, and for this purpose **inhalers** are employed. these the air is inspired by means of a mouthpiece fitted h a valve. This valve prevents the air from passing into mouthpiece, so that during inhalation it is sucked through ube which dips under the water and passes into the mouth en with the vapour. During expiration it passes readily ough the valve just mentioned.

In cases of bronchitis the patient breathes much more easily en the air of the room is kept warm and moist, and this is ected by means of a **bronchitis kettle.** This is simply a tin tle with a spout about three feet long which projects into the m, so that when the kettle is kept boiling briskly a constant rrent of steam is driven well out into the room. When this not be obtained a substitute may be extemporised by rolling a ce of brown paper into a tube, tying a piece of string around t intervals so as to keep it in shape, and putting it over the ut of an ordinary kettle. In cases of tracheotomy it is usual keep the air still warmer and moister by hanging sheets und the bed so as to convert it into a kind of tent, and then nveying the steam from a bronchitis kettle into it by means an india-rubber tube, or keeping up a constant spray by one of ster's steam spray producers.

The vapour of the drug itself, without admixture with steam, ay in some cases be inhaled (see Vapores, p. 533). Oil of calyptus or a solution of thymol in alcohol is thus useful as an tiseptic inhalation in gangrene of the lung and bronchiectasis. rebene is also used in this way in cases of emphysema and ronic bronchitis. The vapour of pyridine in a room is used in thma.

Smoke.—The attacks of difficulty of breathing which come on cases of pure spasmodic asthma, in advanced kidney disease, in emphysema, are frequently much relieved by inhaling the noke which issues from burning touch-paper or from powdered

stramonium (*vide* also p. 260). The touch-paper or stramoniu may be simply laid on a plate, or may be placed at the bottom a cup or jug, and the fumes inhaled. Datura is often used in t form of cigarettes made either from the leaves of the datu stramonium or datura tatula.

Application of Drugs to the Digestive Tract.

Mouth and Pharynx.—Weak solutions are applied to t mouth in the form of **washes** with which the mouth is rins out. Stronger ones may be **painted** with a camel's-hair bru inside the cheek, lips, gums, tongue or pharynx. Solutions m be applied to the pharynx by painting with a brush; solid su stances, as caustics, by **rubbing**. In using caustic, care must taken that it is firmly attached to the caustic-holder, and, the case of nitrate of silver, that only a short point is used, otherwise the caustic may fall off, or the stick of nitrate of silv may break and be swallowed. This is especially necessary touching the throat in children. In cases of post-nasal pharyngeal catarrh, solutions such as glycerin of tannin, & may be applied to the back of the soft palate and the **posteri** part of the **nares** by means of a camel's-hair brush fixed on wire which may be bent to any desired angle.

Masticatories.—We sometimes give the patients solid pie of a drug to chew. These are called masticatories. We u them for their action upon the mouth itself, e.g. pellitory, wh we wish to increase the secretion of saliva; or where we not o wish to produce the effect upon the mouth, but the effect of drug mixed with the saliva upon the stomach and intestines, in the case of rhubarb.

Gargles.—In gargling, a full breath is taken, the mouth filled with the liquid which is to be applied to the pharynx, the head being then thrown back the fluid runs against pharynx and is partly thrown up against the soft palate by air which gradually escapes from the lungs. In cases where i advisable for the fluid to reach the posterior nares, the pati should lie down flat, take a mouthful of the liquid, draw out tongue as far as possible with a handkerchief, and gargle wh in that position. By throwing the head suddenly forward liquid may be brought through the nose. This is useful both a method of applying the liquid more thoroughly to the phar and as a training preparatory to rhinoscopic examination.[1]

Stomach.—Drugs are applied to the stomach in the form solutions or draughts, pills, powders, or boluses, &c., which swallowed.

Powders may be very conveniently given in wafers. A t wafer is moistened with water, and the powder being introdu

[1] Rumbold, *Chicago Med. Journ.*, August 1877, p. 113.

folded up in it and swallowed. Another most convenient hicle is oatmeal porridge, a little of which is put upon a spoon, nd, a depression being made in it with the finger, the powder is t into it and covered over with porridge. The porridge should l the front half of the spoon, and the back part should be filled th milk, which helps the child to swallow more easily. owders are sometimes given to children in jelly, but this is too ft, and so also is the paste made of bread and milk, although is may be used when porridge cannot be readily obtained. lls may be simply swallowed with water, or taken in jelly, but me people are unable to take them without choking, and ildren especially have much difficulty in swallowing them. is difficulty is readily got over by dividing the pill into four more parts, and taking each part in a little oatmeal porridge. stard puddings, or puddings made of corn-flour or arrowroot, ay be used instead of porridge, but are hardly so good.

Stomach-pump.—In cases where the patient is unable to allow from paralysis of the pharynx, constriction of the sophagus, or narcotic poisoning, the stomach-pump may be ed. This consists of a large, double-acting syringe with a xible tube attached. In using it care must be taken [1] (1) to ve the tube well softened in hot water; (2) to keep its end rected towards the pharynx, and not bent too much forward, st it enter the larynx; (3) not to use violence in introducing e tube, lest it should be driven into the mediastinum, or even rough the walls of the stomach itself, into the peritoneal vity; (4) not to use violence in working the syringe, lest the ucous membrane of the stomach should be drawn into the lower ifice of the tube and injured.

In place of the stomach-pump the **gastric syphon** may metimes be advantageously employed, especially for feeding. consists of a piece of thick-walled, soft, and flexible india-bber tubing. It is so soft and flexible that it can hardly by y possibility injure the œsophagus or stomach, and yet it is fficiently firm to pass down without much difficulty. After it in, an ordinary funnel is attached to the projecting end, and ater, beef-tea, or whatever substance one wishes to introduce to the stomach, is simply poured in, the funnel being kept at, above, the level of the patient's mouth. When it is desired to npty the stomach water is poured in, in the manner just scribed, the tube being pinched, and then the outer end of the nnel is held down as low as possible—the syphon action is thus versed, and the fluid which has just been poured into the omach again flows out of it.

[1] In cases of poisoning it may be absolutely necessary to use the stomach-pump, t in ordinary cases a tube should never be passed down the œsophagus until the sence of aortic aneurism has been ascertained by a careful examination of the tient's chest.

Intestine.—Drugs are applied to the intestine by means of enemata or suppositories. **Enemata** are liquid injections into the rectum for the purpose of emptying the lower parts of the bowels when we do not wish to excite the whole bowel, or when we wish to cause as little movement as possible to the patient. They are also used for the purpose of administering nutriment when the patient is unable to swallow or to retain food given by the mouth. In using enemata for the purpose of inducing action of the bowels the quantity should be considerable—sixteen fluid ounces, or even more. When they are intended to be retained the quantity is usually small—not more than two to four fluid ounces at most. In using the enema syringe care should be taken that it is first emptied of air and that it is not pushed forcibly into the bowel. The nozzle should not be directed too much backward, as, if this be done, and especially if force be employed, ulceration of the posterior wall of the rectum may be induced. Where enemata are given for the purpose of nutrition a much larger quantity than four ounces may be retained by using the proper method. A flexible, soft rubber tube should be passed for eight or ten inches up the intestine and the nutrient enema may then be slowly and gently introduced either by using a syringe or by simply pouring it into the tube by a funnel. By this method the fluid is introduced into the sigmoid flexure or descending colon, and if the patient can be propped somewhat so as to lie on his left side, none of it may descend into the rectum. In this case there will be little or no tendency to evacuate it and the whole may be readily absorbed.

The retention of a nutritive enema may be aided by folding a soft napkin so as to form a pad, and pressing it firmly against the anus for a few minutes after the enema has been given, and until the desire to evacuate the bowel has passed away.

Suppositories are drugs made up into a conical shape by means of cacao-butter. When introduced into the rectum the cacao-butter melts, the drugs become spread over the surface of the mucous membrane of the rectum and gradually absorbed. They are employed when we wish to get the local action of a drug upon the rectum, or the parts surrounding it, or when we wish to get the general action of a drug after its absorption without producing any local effect upon the stomach.

Application of Drugs to the Urethra.—They are usually employed as lotions. The syringe used to inject them should




FIG. 163.—Vulcanite syringe for injecting solutions into the urethra.

not have a small thin nozzle, but should have a conical point such as that shown in Fig. 163, which fills up the opening of

ethra and allows the injection to be forced up to the neck of e bladder without any escaping.

Application of Drugs to the Vagina and Uterus.—Lotions e usually either injected into the vagina with a syringe, or lowed to flow into it from a reservoir at some height above the tient. In either case, if it is desirable that the lotion should main in contact with the vaginal walls or cervix uteri, the tient should lie on her back with the hips raised by a pillow. he syringe employed for the vagina is usually furnished with a ield to prevent it from being introduced too far, and it ought have no central opening, but only openings at the side, as casionally, when astringent and irritating fluids have been used ith syringes having a central aperture, they have been forced to the cavity of the uterus, and have there produced uterine ntraction and consequent pain. Sedative and astringent sub-ances are often introduced in the form of **pessaries** or vaginal ppositories, in which the active substance is mixed with either acao-butter or with gelatine and glycerin. Solids such as **austics** are applied either to the vaginal walls or cervix directly rough a speculum, and powders are applied on pledgets of tton-wool. **Tents,** consisting of thin sticks of a porous sub-ance, are introduced into the cervix itself for the purpose of ilating it, and solutions may be injected into the uterine cavity self by means of a syringe provided with a long nozzle.

CHAPTER XVIII.

ANTIDOTES.

ANTIDOTES are remedies which **counteract** the effect of **poisons.**

Action.—Antidotes may act in two ways; they may either **prevent** the action of the poison on the body, or they may **counteract** its effects. Many of them, especially those which are employed in the case of mineral poisons, form chemical compounds with the poisons which are almost insoluble and therefore inert.

Some of these compounds though nearly insoluble will nevertheless be gradually dissolved and absorbed if left too long in the stomach, and therefore it is advisable to remove them by means of **emetics** or by the **stomach-pump** or stomach-syphon as soon as possible. Indeed, it is advisable **in all cases of poisoning,** when the substance has been taken into the stomach, to **empty the stomach** at once before proceeding to administer the antidote. The only possible **exception** is when a highly corrosive substance has been taken which may have partially dissolved the wall of the stomach and rendered it extremely liable to rupture during emesis, or on the introduction of the stomach-tube. If the poison has been absorbed, we must try to counteract its poisonous action on the respiration, circulation, or temperature, by giving substances which will tend to produce a opposite effect.

The more common poisons with their antidotes are given in the following table:—

Poisonous Gases.

Sulphuretted hydrogen.	Chlorine cautiously inhaled.
Chlorine	Steam inhalations.
Bromide	
Iodine vapour . . .	
Vapour of ammonia .	Vapour of vinegar.
Carbon monoxide . .	Fresh air and artificial respiration.
	Transfusion.

Poisonous Gases—*continued.*

trous oxide . . .	Artificial respiration, with the tongue drawn forward, and with intermittent pressure over the cardiac region if the heart is failing.
oal gas	Artificial respiration.
harcoal fumes . . .	Alternate warm and cold douche to the head and chest.
rbonic acid (choke damp)	Friction.
arsh gas	Mustard plasters over surface.
re damp	

Acids.

cids—	Alkalies—
Sulphuric	Bicarbonate of sodium or potassium.
Hydrochloric . . .	Magnesia.
Nitric	Chalk or whiting.
Phosphoric . . .	Plaster from the wall.
	Soap.
	Milk.
	Eggs beaten up.
	Olive or almond oil.
xalic acid	Chalk or whiting, or plaster from the wall, with water.
in-oxalate of potassium (salts of lemon or salts of sorrel) .	
artaric acid . . .	
cetic acid	
Hydrocyanic acid . .	Alternate cold and warm affusions.
	Artificial respiration.
	Injection of atropine (2 to 4 minims of liquor atropinæ) repeated every half-hour.
	Per- and proto- salts of iron, with magnesia, are recommended to render the acid insoluble, but it acts so quickly that there is usually no time for their application.

Alkalies.

Caustic potash or soda	Vinegar.
Caustic lime	Lemon juice.
Caustic ammonia . .	Other dilute acids.
Carbonate of sodium or potassium	Milk.
	Oil.

Alkaloids, &c.

Aconite	Spirits. Ammonia. Warmth. Digitalis. Atropine.
Alcohol	Coffee. Cold douche to head.
Anæsthetics Chloroform, ether, &c.	Artificial respiration, inversion, &c.
Antimony	If vomiting does not occur wash out th stomach with water first; then wit tannic or gallic acid; then give mil and white of egg as demulcent t stomach.
Arsenic	Wash out the stomach with lar draughts of warm water, either by th stomach-pump, or if the arsenic itse does not cause vomiting, by usi sulphate of zinc. Give magnesia, or still better, fresh precipitated oxide of iron made l precipitating a solution of perchlori of iron with carbonate of sodium with ammonia. Dialysed iron is al very useful.
Atropine	Give stimulants and coffee; inject ca feine subcutaneously; arouse fro stupor, as in opium-poisoning, an if necessary, artificial respiratio Give cautiously physostigma.
Barium salts	Give Epsom or Glauber's salts or dilu sulphuric acid.

Belladonna. *Vide* Atropine.

Burnett's Disinfecting Fluid. *Vide* Metallic Salts.

Calabar bean	Stimulants. Atropine. Artificial respiration if necessary.

Cannabis Indica. *Vide* Morphine.

Cantharides	Large quantity of demulcent drinks. Barley water. Gruel. Linseed tea. Avoid oils and fats.

Alkaloids, &c.

rbolic acid . . .	Saccharated lime. Stimulants.
erry laurel water.	*Vide* Hydrocyanic Acid.
loral	Keep patient warm. Arouse him. Give him coffee per rectum. Liquor strychninæ, 4 minims, subcutaneously, repeated every 10 to 20 minutes, if necessary.
chromate of potassium.	Same as Acids.
lchicum	Tannic or Gallic acid. Stimulants.
nium	Tannic acid. Stimulants. Coffee.
inine	Tannic or Gallic acid. Strong tea or coffee. Stimulants warmed. Artificial respiration.
pper.	*Vide* Metallic Salts.
rrosive sublimate.	*Vide* Metallic Salts.
easote.	*Vide* Carbolic Acid.
roton oil	Demulcents. Stimulants.
urare	Artificial respiration. If there is a wound, ligature above it if possible, and incise and suck strongly. The ligature should be loosened from time to time, and again tightened, so as not to let too much poison into the blood at once.
yanide of potassium.	*Vide* Hydrocyanic Acid.
igitalis	Strong tea. Tannin. Stimulants. Aconite, 5 minims of the tincture subcutaneously. Keep perfectly quiet, lying in bed.
rgot	Tannin. Stimulants.

Alkaloids, &c.

Gelsemium	Atropine. Stimulants. Artificial respiration.
Hyoscyamus. *Vide* Atropine.	
Insect powder. *Vide* Arsenic.	
Laburnum	Stimulants. Coffee. Alternate hot and cold douches to chest.
Lead. *Vide* Metallic Salts.	
Lobelia	Tannin. Stimulants. Strychnine hypodermically (5 minims of liq. strychninæ).
Metallic salts	White of egg freely to form insoluble compound: then wash out stomach to remove it: afterwards demulcents. Poultices to surface, and morphine if necessary.
Morphine	Warm coffee after the stomach is emptied. Ammonia. Arouse by flicking with a towel, or by galvanic battery, and keep awake by walking about and renewal of stimulation if necessary. 2 to 4 minims of liq. atropinæ subcutaneously. Artificial respiration, if necessary.
Mushrooms	2 to 4 minims liq. atropinæ, subcutaneously: repeat if necessary. Castor oil. Stimulants.
Nitro-benzol Nitrite of Amyl	Stimulants. Alternate hot and cold douche. Artificial respiration.
Nitro-glycerin	Cold to head. Ergotin. Atropine, subcutaneously.
Oil of Bitter Almonds. *Vide* Hydrocyanic acid.	
Opium. *Vide* Morphine.	
Phosphorus	Sulphate of copper. Oil of turpentine, old and oxidised. Avoid oils and fats.

Alkaloids, &c.

rsostigma	Stimulants. Atropine. Chloral. Strychnine. Artificial respiration.
rotoxine	Chloral. Bromide of potassium.
carpine	Atropine.
-paste. *Vide* Phosphorus.	
in	Epsom salts. Demulcents.
ake-bite	Ligature limb, cut out part with penknife and sear with hot iron. Alcoholic stimulants. Ammonia. Artificial respiration.
amonium. *Vide* Atropine.	
rychnine	Chloroform. Tannin. Bromide of potassium. Chloral.
bacco	Tannin. Stimulants, warm. Strychnine.
rpentine (oil of)	Demulcents. Sulphate of magnesium.
ratrine	Stimulants. Coffee, warm. Recumbent posture.
rmin-killer. *Vide* Strychnine.	

CHAPTER XIX.

ANTAGONISTIC ACTION OF DRUGS.

THE idea that one drug might be made to counteract the deadl effects of another is a very old one, and in the middle age alexipharmics and mithridates were used as antidotes. Of lat years, however, the subject has been investigated experimentally and a more accurate knowledge of it obtained. Amongst the firs of these experimental researches were those of Preyer, on th antagonism of atropine and hydrocyanic acid; of Schmiedeber and Koppe on the antagonism of muscarine and atropine; an of Fraser on the antagonism between physostigma and atropine

Although the fact is undisputed that we are occasionally abl by the administration of one drug, to prevent the appearance c certain symptoms which would otherwise have certainly bee produced by another previously administered, it is by no mean certain that the one simply counteracts the effect of the other.

Some regard the effect of one drug in counteracting anothe as a case of chemical combination or substitution, the secon drug either becoming added on to a compound of the first wit some of the tissues, or else displacing it from such a compoun with the tissues. Others, again, think that no chemical actio of this sort takes place, but that each drug acts upon the tissu or tissues by itself—one, for example, exciting, and the oth paralysing.

In favour of the first view may be mentioned the analog between the action of poisons and the formation of acid-albumi and alkali-albumin, either of which can be changed into th other by excess of alkali or of acid respectively.

The objection is a very natural one that the doses of alkaloi required to produce marked physiological action are so extreme small that one can hardly fancy any chemical action being th cause of their physiological action. I have, however, on o occasion, by the addition of a single drop of liquor potassæ, co verted a milky-looking fluid, consisting of the nuclei of fow blood-corpuscles suspended in water and measuring 90 cc., in a solid jelly-like mass—a result more striking than if a simil quantity injected into a frog had induced rigor in every musc Even such a result is infinitely less delicate than the colour r actions by which alkaloids are detected.

Some of the best-marked examples of antagonism in regard involuntary muscular fibre are those observed by Ringer in frog's heart, and they strongly support the view which he cates of chemical substitution. As already mentioned, cal- salts and veratrine greatly prolong the cardiac systole; but prolongation is at once removed, and the systole rendered mal by a small quantity of a potassium salt. The salts of ssium alone render the systole short and weaker, and then mal, but this action again is neutralised by calcium.

A similar condition has been observed by Cash and myself in voluntary muscles of the frog. The contraction of the gas- nemius is prolonged to a slight extent by calcium, and to a t extent by veratrine, and also by barium salts. This con- tion is quickly reduced to the normal by the addition of a ll quantity of potash.

There is no very well-marked case of antagonism, in which drug is able to restore power to motor nerves which have n paralysed by another drug; such antagonism, however, has n observed in regard to the vagus. By small doses of atro- this may be paralysed; by a dose of physostigma adminis- d afterwards the inhibitory power may again be restored; by a further dose of atropine it may be again paralysed. s action has been denied by Rossbach, but in experiments on subject by myself, I have obtained this effect in such a rked degree that I have no doubt regarding it. It is possible the different results obtained may be due partly to the mal employed, partly to the dose, partly to the preparations he drug, and partly to the temperature at which the experi- nts are made.[1] In my experiments the vagus was irritated, I ascertained that the stimulation was strong enough to stop heart. A very small quantity of atropine was then injected, the same stimulus was repeated. After enough atropine been gradually injected to abolish the inhibitory action of vagus completely, some physostigma was injected into the ular vein, and the irritation again repeated with the effect of pping the heart as at first.

The antagonism of certain drugs upon the frog's heart has eived much attention. In considering this subject care must taken to distinguish between experiments made with the tricle alone, containing involuntary muscular fibres but no nglia, and the whole heart, in which both muscle and ganglia contained. The experiments on veratrine, calcium, and assium, already alluded to, were made with the ventricle ne; those which are now to be considered have reference to

[1] My experiments were made on rabbits during the summer. The preparation physostigma employed was a glycerin extract of the bean, and the preparation tropine used was the Liquor Atropinæ, B.P. (1875).

the whole heart. Atropine appears to have the power not on of destroying the inhibitory action of the vagus upon the hea but of antagonising those drugs which inhibit the heart a render its beats slower, or stop them altogether, such as mu carine, physostigma, pilocarpine, and phytolacca. Digitalin a saponin have a mutually antagonistic power, so that when t frog's heart has been stopped by either of them, the other w restore its pulsations. A limited antagonism also exists betwe muscarine, aconitine, and digitalin; when the heart has be stopped by digitalis, muscarine and aconite will restore its mov ments. Digitalin will also restore the pulsations in a hea which has been arrested by aconite. Physostigmine, campho and other drugs which stimulate the muscular fibre of the hea will remove the still-stand caused by muscarine.

Another very important antagonism is that between dru acting on the respiratory centre and spinal cord. The mode action of these drugs is difficult to explain on account of o imperfect knowledge of the physiology of the structures on whi they act. Chloral lessens the excitability of these structur strychnine increases it. These drugs have to a certain exte an antagonistic action, so that a fatal dose of strychnine may so antagonised by chloral as to prevent death; and a sm quantity of strychnine may prevent death from chloral. At pine has an exciting action on the respiratory centre, somewh like strychnine though very much less marked; and atropi also will antagonise chloral. It has also an antagonistic acti to aconite, which has a peculiar depressing influence on t respiratory centre.

The sedative action of chloral enables it to antagonise pic toxine which has a stimulant action on the brain causing c vulsions. Opium and belladonna have to a certain extent antagonistic action to one another. The first point wh appeared to indicate an antagonistic action was their differ effect on the pupil; but probably the point on which they chie antagonise one another is their action on respiration, atrop acting as a stimulant and morphine as a depressant to respiratory centre.

The alkaloids of tea, coffee, and allied substances, viz. the or caffeine, cocaine and guaranine, are antagonistic to morphi These alkaloids in small and moderate doses increase the irr bility of the brain, spinal cord, heart, and vaso-motor syst and in large doses paralyse them. Morphine and these alkal to a certain extent counteract one another, so that a lethal d of one may be prevented from causing death by administer the other.

The antagonism of drugs is also marked in regard to t action on the glandular system; thus the excessive salivat produced by physostigma, pilocarpine, and bromal may

rrested by atropine, which also arrests the excessive secretion om the skin caused by pilocarpine, and the secretion from the ucous membrane of the lungs produced by bromal.

The following table shows the most important examples of ntagonism. The lethal and antagonistic doses have only been certained for a few. When the remark 'not antagonistic' curs in the table, it means that the second drug mentioned ill not prevent death from a lethal dose of the first, although e first will prevent death from a lethal dose of the second.

TABLE SHOWING THE ANTAGONISM OF DRUGS.

		Lethal dose.—I.	Lethal dose.—II.	Antidotal doses
conitine . .	Atropine	$\frac{1}{500}$th	7	$\frac{1}{750}$th
,, . .	Digitalin	$\frac{1}{900}$th	1	$\frac{1}{600}$th
,, . .	Strychnine . . .	$\frac{1}{900}$th	$\frac{1}{288}$th	$\frac{1}{750}$th
lcohol . .	Strychnine . . .	—	$\frac{1}{288}$th	
mmonium chloride }	Chloral	—		
tropine . .	Aconitine . . .	7	$\frac{1}{900}$th {	not antagonistic
,, . .	Bromal-hydrate . .	7	$1\frac{1}{4}$ {	not antagonistic
,, . .	Chloral-hydrate . .	7	7	
,, . .	Hydrocyanic acid . .	7		
,, . .	Jaborandi . . .	7		
,, . .	Muscarine . . .	7		
,, . .	Morphine . . .	7	3 {	not antagonistic
,, . .	Physostigmine . .	7	$\frac{1}{25}$th	
,, . .	Phytolacca . . .	7		
,, . .	Pilocarpine . . .	7		
,, . .	Quinine	7		
arium . .	Sodium sulphate . .			
,, . .	Potassium salts . .			
romal-hydrate	Atropine	$1\frac{1}{4}$	7	
rucine . .	Chloral			
alabarine .	,, ...			
arbolic acid .	,, ...			
hloral . .	Ammonium chloride .			
,, . .	Atropine			
,, . .	Brucine			
,, . .	Calabarine . . .			
,, . .	Carbolic acid . . .			
,, . .	Codeine			
,, . .	Physostigma . . .			
,, . .	Picrotoxine . . .			
,, . .	Strychnine . . .			
,, . .	Thebaine . . .			
hloroform .	Amyl nitrite . . .			
ocaine . .	Morphine . . .			
odeine . .	Chloral			
igitalin . .	Aconitine . . .			
,, . .	Muscarine . . .			
,, . .	Saponin			
elsemium .	Opium			
,, . .	Atropine			

TABLE SHOWING THE ANTAGONISM OF DRUGS—*continued.*

		Lethal dose.—I.	Lethal dose.—II.	Antidotal doses
Morphine . .	Atropine			
,, . .	Caffeine			
,, . .	Chloroform . . .			
,, . .	Cocaine			
,, . .	Daturine . . .			
,, . .	Hyoscyamine . . .			
,, . .	Nicotine . . .			
,, . .	Physostigma . . .			
Muscarine .	Atropine			
Opium . .	,, ...			
,, . .	Gelsemium . . .			
,, . .	Veratrum viride . .			
Physostigma .	Atropine			
,, . .	Chloral			
,, . .	Morphine . . .			
Saponin . .	Digitalin			
Strychnine .	Alcohol			
,, . .	Chloral			
,, . .	Hydrocyanic acid . .			
,, . .	Nicotine			
,, . .	Nitrite of amyl . .			
Thebaine . .	Chloral			

CHAPTER XX.

DOSAGE.

HE circumstances which affect dosage have already been dis-ssed (p. 37). In practice we reckon the dose according to age, aking allowances, however, for the size and sex of the patient. arious tables have been drawn up for this purpose. One in mmon use is Dr. Young's. It is to convert the age into a action by adding twelve to it and using the number thus tained as the denominator, the age itself being the enumerator. hus, if a child's age be three years, the denominator will be + 12 = 15, and the enumerator will be 3. The dose for the ild will therefore be $\frac{3}{3+12} = \frac{3}{15} = \frac{1}{5}$ of that for an adult. For a ild five years old it will be $\frac{5}{5+12} = \frac{5}{17}$, which is between one-ird and one-fourth of that for an adult. If the child is large r its years, we would give one-third; if small, we would rather ve one-fourth.

Another rule, proposed by Dr. Cowling, is to divide the mber of the patient's *next* birthday by twenty-four. Thus, r a child three years old, the fraction representing the dose ould be $\frac{4}{24} = \frac{1}{6}$; for a child five years old, $\frac{6}{24} = \frac{1}{4}$.

The rule which I should propose as being more convenient r the metric system is a modification of Dr. Cowling's. If we sume that the body has attained its full growth at twenty-five ars of age instead of twenty-four, we get the proportion by viding the number of the next birthday by twenty-five. Thus, r a child three years of age, the proportion would be $\frac{4}{25} =$ early $\frac{1}{6}$; for a child five years of age, $\frac{6}{25} =$ between $\frac{1}{5}$ and $\frac{1}{4}$. his number does not lend itself readily to fractions such as the eceding, but it is very easy to divide by twenty-five by simply ultiplying by four and dividing by 100. When the metrical stem is used, all that is necessary is to multiply the full dose the number of the child's next birthday, then by four, and move the decimal point two places to the left. Thus, if the full se for an adult be 1 gramme, the dose for a child of three will $\frac{1 \times 4 \times 4}{100} = \cdot 160$ gramme or 16 centigrammes. If the full dose r an adult be ·3 gramme, the dose for a child of three will be $\frac{\times 4 \times 4}{100} = \cdot 048$, or 48 milligrammes. If the full dose be 1 gramme,

the dose for a child of five will be $\frac{1 \times 6 \times 4}{100} = \cdot 240$ gramme or centigrammes. If the full dose be ·3 gramme, the dose for child of five will be $\frac{\cdot 3 \times 6 \times 4}{100} = \cdot 072$ gramme or 72 milligramm

To put this rule shortly, the number of grammes in the f dose multiplied by the child's next birthday and by four, giv the result in centigrammes. The number of decigrammes m tiplied in the same way gives the result in milligrammes.

SECTION II.

GENERAL PHARMACY.

CHAPTER XXI.

PHARMACEUTICAL PREPARATIONS.

HARMACY includes both the general preparation of drugs from rude natural products and their combinations with other substances, so as to render them either more effectual or more easily dministered.

The great rule for the administration of medicines is (1) **curare** 2) **cito,** (3) **tute, et** (4) **jucunde**—that they shall not only (1) cure, ut that they shall do so (2) quickly, (3) safely, and (4) pleasantly. ccording to this rule many prescriptions contain four ingredients, iz.: (1) the substance which is to cure, or the *basis*; (2) the *djuvant* to help it; (3) the *corrective* to prevent any bad effects; nd (4) the *vehicle* to make it pleasant to take. This rule, however, is carried out not only in written prescriptions, but in those lso which have been adopted by the profession at large, as a eans of saving labour and time in the routine of practice, and mbodied in the Pharmacopœia as useful preparations.

Formerly we were dependent for our medicines chiefly on the rude products of the animal, vegetable, and mineral kingdoms. s chemistry advanced various inorganic compounds were discovered and added to the Materia Medica, and as our knowledge f this science becomes greater and our power of preparing various rganic bodies increases, we find that such bodies are becoming nore and more introduced into medicine. As examples of these, e may take carbolic acid, chloral, chloroform, ether, hydrocyanic cid, iodoform, nitrite of amyl, salicylic acid, and kairin.

We seem now on the verge of discovering the mode of preparation of many organic alkaloids, and when this has been done, he vegetable Materia Medica will be less important than it is ow, inasmuch as it is probable that, by using artificial alkaloids, prepared always under similar conditions, we may obtain purer products and greater constancy of action than we can at present rom the natural active principles.

Recent discoveries have shown that plants generally contain ctive principles so closely associated, that the mixture was regarded as a pure alkaloid, and yet these drugs have very different

and sometimes opposite physiological actions. Thus ordinar coniïne usually contains pure coniïne and methyl-coniïne, th former of which paralyses the motor nerves, while the latt paralyses the spinal cord. Extract of physostigma, and suppos pure physostigmine, or eserine, have been found to contain tw active principles, viz. physostigmine having a paralysing actio and calabarine having a tetanising action on the spinal cord.

The power which chemistry now gives us also of modifyin the chemical constitution of organic bodies and therewith the physiological action, will almost certainly enable us to treat disea much more perfectly than we can at present. For such modifi drugs, however, we must be indebted to the chemist. He w prefer to operate on substances which have been already prepar by himself rather than on crude drugs obtained from plants. B at present we are still dependent on the vegetable kingdom f a large number of our most useful remedies. In plants they a associated, as a rule, with quantities of woody tissue which is qui inert and indigestible, and which would interfere very much bo with their easy administration and with their action.

Sometimes the crude drug is given in the form of a simp **powder,** without any admixture, as in the case of guaiac giv in tonsillitis, where it is advisable to have the local action of t drug on the throat, as well as its general action on the syste Sometimes the powder may be readily given by enveloping it a **wafer,** and swallowing it with a little water, and at other tim it is made up with saccharine, and more or less adhesive su stances, into the form of a **confection** or **bolus** ; or suspended water by means of mucilage in the form of a **mixture.** Usua however the active parts of the drug are extracted by means solvents, and either given in solution, or in the solid form, aft the solvents have been evaporated. There are a number of p parations according to the solvents used, and the mode in whi they are applied. Probably the most convenient arrangeme is not to take the groups of preparations according to the s vents or mode of preparation, but alphabetically for the sake reference.

Groups of Officinal Preparations.

The letters B.P. stand for the British Pharmacopœia of 18 and U.S.P. for the United States Pharmacopœia of 1883. Wh the letters B.P. or U.S.P. *precede* the name of a class or o substance, they indicate that it is contained in the correspondi pharmacopœia only, and not in the other. They succeed name or are omitted when the class or substance occurs in b pharmacopœias. When there are differences between thi bearing the same name in the British and United States Ph macopœias, the letters B.P. are placed after the descriptions

at contained in the British, and U.S.P. after that of the United tates Pharmacopœia.

U.S.P. Abstracta. ABSTRACTS.—These are very dry, powdered tracts. They are twice the strength of the crude drug, and out twice the strength of the corresponding fluid extracts. They e prepared by extracting the active principles from 200 parts of e crude drug by percolation with the strong or diluted alcohol, ixing the percolate with some sugar of milk, letting it dry, and en adding sufficient sugar of milk to make up the product to 00 parts. They are eleven in number.

	DOSE.		DOSE.
stractum Aconiti	¼–1 gr.	Abstractum Ignatiæ	½–1½ gr.
„ Belladonnæ	½–1 gr.	„ Jalapæ	5–15 gr.
„ Conii	1–3 gr.	„ Nucis Vomicæ .	½–2 gr.
„ Digitalis	½–1 gr.	„ Podophylli	5–10 gr.
„ Hyoscyami	2–3 gr.	„ Senegæ	1–3 gr.
		„ Valerianæ	10–20 gr.

Aceta. VINEGARS.—These are solutions of medicines in vinegar or acetic acid. In the B.P. there are three, in the U.S.P. there re four.

B.P.	DOSE.	U.S.P.	DOSE.
cetum.		Acetum Lobeliæ.....	30–60 min.
„ Cantharidis		„ Opii	10–15 min.
„ Scillæ.....	15–60 min.	„ Sanguinariæ	3–4 fluid dr.
		„ Scillæ.....	15–60 min.

Alkaloidea. ALKALOIDS.—These are organic bases which ay be regarded as compound ammonias.

Like ammonia they all contain nitrogen, and form salts with cids. Most of them contain oxygen in addition to nitrogen, arbon, and hydrogen, and occur as crystalline solids. Some, e.g. oniïne, nicotine, sparteine, piperidin, contain no oxygen, and occur s oily liquids. They generally have a powerful physiological action. hey occur in many exogenous plants, but only veratrine and ubstances nearly allied to it have been obtained from the class f endogens and muscarine from thallogens. They occur in the lants in combination with acids. The alkaloids themselves are enerally soluble in alcohol, but sparingly soluble in water. Their alts are more soluble in water. The general plan of obtaining hem is to prepare an aqueous solution either of the salt originlly present in the plant, or of one formed by treatment with an cid, and to precipitate them by an alkali, generally ammonia, rom it. As the alkaloids are soluble in alcohol they would be ery imperfectly precipitated, or not at all, if the ammonia were dded to an alcoholic solution of their salts.

In the B.P. of 1867 the names of alkaloids all terminated in ia,' like ammonia, e.g. quinia, strychnia. Chemists have now enerally returned to the older nomenclature, and assign the ermination 'ine' to alkaloids, e.g. strychnine, quinine. To eutral principles they give the termination 'in,' e.g. santonin,

salicin. This terminology has been followed in the B.P. of 188 and the U.S.P. of 1883.

General Properties and Reactions of Alkaloids.—Alkaloids are basic in nature, like ammonia, forming salts with acid radicals, easily decomposed by the action of alkalies and alkaline carbonates.

Alkaloids are, for the most part, insoluble in water, with the exception of brucine and codeine, which are readily soluble; they are all soluble in alcohol, benzene, and chloroform. The salts are soluble in water, and have the property of turning the plane of polarised light to the left: cinchonine, conchinine, coniïne, laudanosine, however, turn the plane to the right. Some alkaloids have no effect on polarised light, e.g. berberine, cryptopine, emetine, hydrocotarnine, narceïne, veratrine, caffeine, and piperine.

In solution, alkaloids are precipitated by a solution of iodine in iodide of potassium, by potassio-mercuric iodide, and a similar double iodide of cadmium and bismuth, also by picric acid and by phospho-molybdic and phospho-tungstic acids.

B.P.

Aconitina (Aconitine).
Apomorphinæ Hydrochloras (Hydrochlorate of Apomorphine).
Atropina (Atropine).
Atropinæ Sulphas.
Beberinæ Sulphas (Sulphate of Beberine).
Caffeina (Caffeine).
Caffeinæ Citras (Citrate of Caffeine).
Cinchonidinæ Sulphas (Sulphate of Cinchonidine).
Cinchoninæ Sulphas (Sulphate of Cinchonine).
Cocainæ Hydrochloras (Hydrochlorate of Cocaine).
Codeina (Codeine).
Morphinæ Acetas (Acetate of Morphine).
,, Bimeconatis Liquor (Solution of Bimeconate of Morphine).
,, Hydrochloras (Hydrochlorate of Morphine).
,, Sulphas (Sulphate of Morphine).
Physostigmina (Physostigmine).
Pilocarpinæ Nitras (Nitrate of Pilocarpine).
Quininæ Hydrochloras (Hydrochlorate of Quinine).
Quininæ Sulphas (Sulphate of Quinine).
Strychnina (Strychnine).
Strychninæ Hydrochloras (Hydrochlorate of Strychnine).
Veratrina (Veratrine).

U.S.P.

Apomorphina (Apomorphine).
Atropina (Atropine).
Atropinæ Sulphas (Sulphate of Atropine).
Caffeina (Caffeine).
Cinchonidinæ Sulphas (Sulphate of Cinchonidine).
Cinchonina (Cinchonine).
Cinchoninæ Sulphas (Sulphate of Cinchonine).
Codeina (Codeine).
Hyoscyaminæ Sulphas (Sulphas of Hyoscyamine).
Morphina (Morphine).
Morphinæ Acetas (Acetate of Morphine).
Morphinæ Hydrochloras (Hydrochlorate of Morphine).
,, Sulphas (Sulphate of Morphine).
Physostigminæ Salicylas (Salicylate of Physostigmine).
Pilocarpinæ Hydrochloras (Hydrochlorate of Pilocarpine).
Piperina (Piperine).
Quinidinæ Sulphas (Sulphate of Quinidine).
Quinina (Quinine).
Quininæ Bisulphas (Bisulphate of Quinine).
Quininæ Hydrobromas (Hydrobromate of Quinine).
,, Hydrochloras (Hydrochlorate of Quinine).
,, Sulphas (Sulphate of Quinine).

U.S.P.

Quininæ Valerianas (Valerianate of Quinine).
Strychnina (Strychnine).
Strychninæ Sulphas (Sulphate of Strychnine).
Veratrina (Veratrine).

Chinoidinum (Chinoidin or Quinoidin), U.S.P., is a mixture of bases.

Along with the alkaloids may be mentioned several **neutral principles** which resemble alkaloids in having a powerful physiological action.

B.P.

Aloin.
Chrysarobinum (*Chrysarobin*).
Elaterinum (Elaterin).
Ergotinum (*Ergotin*).
Salicinum (Salicin).
Santoninum (Santonin).

U.S.P.

Chrysarobinum (*Chrysarobin*).
Picrotoxinum (Picrotoxin).
Salicinum (Salicin).
Santoninum (Santonin).

The substances whose names are printed in italics in the above list are not pure principles. The chrysarobinum of the pharmacopœias is a mixture of substances containing chrysarobin and chrysophanic acid, and ergotin is only a purified extract of ergot. Lupulinum (B.P.) is only a glandular powder derived from hops, although from the sound of its name it might be supposed to be an active principle.

Aquæ. Waters. (16 in B.P.; 15 U.S.P.)—One is simply water, another distilled water. The others in the B.P. are water containing small quantities of volatile oils in solution, with the exception of two, aqua chloroformi and aqua laurocerasi, which contain chloroform and hydrocyanic acid respectively instead of volatile oil. Two waters are prepared by simply dissolving the substances in them in the cold; these are aqua camphoræ and aqua chloroformi. All the rest are prepared by distillation. Two are prepared by distilling the volatile oils with water; these are peppermint and spearmint waters. All the rest are prepared by distilling the plant in a retort with water and continuing the process until a certain quantity is distilled over.

In the U.S.P. aqua ammoniæ, aqua ammoniæ fortior, and aqua chlori consist of solutions of ammoniacal and chlorine gases in water. One, the aqua creasoti, consists of a solution of one part of creasote in 100 of water.

The others consist of volatile oils in water. Only two, aqua aurantii florum and aqua rosæ, are prepared by distilling the flowers with water. The others are prepared by thoroughly distributing the requisite quantity of volatile oil through a quantity of cotton, and dissolving it in water, by allowing the latter to percolate through. Camphor is dissolved in alcohol before adding it to the cotton.

Waters are chiefly **used** as vehicles.

The dose of all those in the B.P. with one exception is fro half an ounce to two ounces. This exception is aqua lauroceras which is not used as a vehicle, but is, on the contrary, a powerf drug containing hydrocyanic acid, and the dose of it is ve small, 5–30 minims.

Aqua anethi is a favourite remedy for flatulence in childre and in them it is given in a dose of a teaspoonful or more.

B.P. (16).	DOSE.	U.S.P. (15).	DOSE.
Aqua		Aqua	
,, Destillata.		,, Destillata.	
,, Anethi	½–2 oz.	,, Ammoniæ	10-30 minir
,, Anisi	,,	,, Ammoniæ Fortior..	
,, Aurantii Floris	,,	,, Amygdalæ Amaræ.	2 drachms
,, Camphoræ	,,	,, Anisi	½–2 oz.
,, Carui	,,	,, Aurantii Florum	,,
,, Chloroformi	,,	,, Camphoræ	,,
,, Cinnamomi	,,	,, Chlori	,,
,, Fœniculi	,,	,, Cinnamonii	½–2 fluid o:
,, Laurocerasi	5-30 minims.	,, Creasoti	1–4 drachm
,, Menthæ Piperitæ	½–2 oz.	,, Fœniculi	1–2 fluid o:
,, Menthæ Viridis	,,	,, Menthæ Piperitæ	,,
,, Pimentæ	,,	,, Menthæ Viridis	,,
,, Rosæ	,,	,, Rosæ	,,
,, Sambuci	,,		

B.P. Cataplasmata. CATAPLASMS OR POULTICES. (6.) These are used as a means of applying externally moisture a warmth, and in certain cases medicaments, to parts of the bo They consist of linseed meal or of bread crumb, made into a pa with hot water. In one, cataplasma conii, hemlock leaf is add to relieve pain; in another, cataplasma sinapis, mustard is us to stimulate the skin; and in the cataplasma carbonis, cataplas fermenti, and cataplasma sodæ chlorinatæ, wood charcoal, yea and chlorinated soda respectively, are added for the purpose removing fœtor or acting as disinfectants.

B.P. (6).

Cataplasma Carbonis.	Cataplasma Lini.
,, Conii.	,, Sinapis.
,, Fermenti.	,, Sodæ Chlorinatæ

U.S.P. Cerata. CERATES.—These are ointments contain wax. The admixture of wax with oil or lard in cerates rend them harder than ointments, though they are softer th plasters. They can be spread on linen or leather, at ordin temperatures, without requiring heat like plasters, and th can be applied to the skin without melting and running ointments.

U.S.P. (8).

Ceratum.	Ceratum Extracti Cantharidis.
,, Camphoræ.	,, Plumbi Subacetatis.
,, Cantharidis.	,, Resinæ.
,, Cetacei.	,, Sabinæ.

Chartæ. PAPERS.—Charta epispastica or cantharidis, charta sinapis, consist of irritating substances spread upon pa

d used for the purpose of producing rubefaction or vesication. harta potassii nitratis consists of bibulous paper soaked in a lution of nitrate of potassium and dried, and is used for burning give relief in asthma by inhalation of the fumes.

B.P. (2).	U.S.P. (3).
Charta Epispastica.	Charta Cantharidis.
,, Sinapis.	,, Potassii Nitratis.
	,, Sinapis.

Collodia. COLLODIONS.—In these collodion is used as a solvent d means of application.

B.P. (3).	U.S.P. (3).
Collodium.	Collodium.
,, Flexile.	,, cum Cantharide.
,, Vesicans.	,, Flexile.
	,, Stypticum.

Confectiones. CONFECTIONS, ELECTUARIES OR CONSERVES.—ese are soft pastes which contain the drug mixed with sugar honey, and are convenient forms of administering drugs, ich would be unpleasant to take alone, and would be too lky for pills. In two of them, the confection of dog roses, and red roses, the drug is of itself inert, and the confection is ed only as a vehicle; in the others, the drug is active, and the nfection is used as a mode of administering it. The dose of is 1 to 2 drachms, with the exception of the confection of ium (B.P.) and of scammony (B.P.).

B.P. (8).	DOSE.	U.S.P. (2).	DOSE.
nfectio Opii	5–20 grs.	Confectio Rosæ.....	
,, Piperis.....		,, Sennæ	1–2 dr.
,, Rosæ Caninæ.....			
,, Rosæ Gallicæ.....			
,, Scammonii.....	10–30 grs.		
,, Sennæ.....			
,, Sulphuris			
,, Terebinthinæ			

Decocta. DECOCTIONS.—These are made by boiling the drug th water, and then straining while hot. Usually the boiling continued from ten to twenty minutes, in order to dissolve out e active part of the drug; prolonged boiling frequently alters and may render it inert.

B.P. (13).	DOSE.	U.S.P. (2).	DOSE.
coctum Aloes Compositum	½–1 fl. oz.	Decoctum Cetrariæ	ad lib.
,, Cetrariæ	ad lib.	,, Sarsaparillæ Com-	
,, Cinchonæ [Rubræ]	1–2 fl. oz.	positum	4–6 fl. oz.
,, Granati Radicis ...	,,		
,, Hæmatoxyli.....	,,		
,, Hordei	ad lib.		
,, Papaveris	for external use.		
,, Pareiræ.....	1–2 fl. oz		
,, Quercus	,,		

B.P.	DOSE.
Decoctum Sarsæ	2–10 fl. oz.
,, Sarsæ Compositum	,,
,, Scoparii	2–4 fl. oz.
,, Taraxaci	,,

U.S.P. Elixiria. ELIXIRS. — These are diluted tinctu rendered agreeable by aromatics and sugar. The only one the U.S.P. is used as a vehicle.

U.S.P. (1).
Elixir Aurantii (Simple Elixir).

Emplastra. PLASTERS.—These consist of adhesive substan spread upon leather or cloth, so as to stick to the part of t body to which they are applied.

Lead plaster is one of the most important, as it forms a ba for other plasters. It is also used for covering slight woun and excoriations. Resin plaster is more adhesive, and is used hold the edges of wounds together and to apply pressure. T others, emplastrum belladonnæ and emplastrum opii, cont narcotic substances with the intention of lessening pain local The others are used for the purpose of affording mechani support or gentle stimulation, and emplastrum cantharidis (B. is used as a vesicant.

B.P. (14).	U.S.P. (17).
Emplastrum Ammoniaci cum Hydrargyro.	Emplastrum Ammoniaci (Ammonia
,, Belladonnæ.	,, ,, c. Hydrar (ammoniac with merc
,, Calefaciens (warming).	,, Arnicæ (Arnica).
,, Cantharidis.	,, Asafœtidæ (Asafœtida
,, Ferri.	,, Belladonnæ (Belladon
,, Galbani.	,, Capsici (Capsicum).
,, Hydrargyri.	,, Ferri (Iron).
,, Opii.	,, Galbani (Galbanum).
,, Picis.	,, Hydrargyri (Mercuria
,, Plumbi.	,, Icthyocollæ (Court).
,, ,, Iodidi.	,, Opii (Opium).
,, Resinæ.	,, Picis Burgundicæ (gundy pitch).
,, Saponis.	,, Picis Canadensis (E
,, ,, Fuscum.	lock pitch).
	,, Picis cum Cantha (warming).
	,, Plumbi (Diachylon).
	,, Resinæ (adhesive).
	,, Saponis (Soap).

B.P. Enemata. INJECTIONS, ENEMAS, OR CLYSTERS.—Th are preparations for injection into the rectum. When the qu tity injected is large, and especially if cold, it is usually retur almost immediately; therefore, when we wish to get it retai a small quantity only, and warm, must be employed. vehicle in most injections is starch mucilage. In the enem aloes 10 ounces, and in those of Epsom salts and of turpent 15 ounces of the vehicle are used, and these enemata are

oyed for the purpose of evacuating the bowel. In the case of e enema opii which we wish to be retained the quantity is only ounces. This is used both as a local and general sedative, in der to relieve pain in or about the pelvis, or to produce the neral action of opium after its absorption, in cases where edicines cannot be retained by the stomach, or when it is un-visable to administer them by the mouth. The enema asafœ-læ is perhaps the most powerful remedy we possess in cases tympanitic distension of the bowels. As it is used for the rpose of exciting the contraction of the bowels and the expul-on of flatulence, but not of simply evacuating the rectum, an termediate quantity is used, viz. 4 ounces. Asafœtida con-ins a gum as well as a resin, and therefore no mucilage is re-ired to suspend it, and water only is required in preparing it.

The enema of tobacco is now so rarely used, on account of e danger from collapse, that it has been omitted from the B.P. 1885; but formerly, before the introduction of chloroform, it as frequently employed in order to cause muscular relaxation voluntary and involuntary muscles in hernia, tetanus, ob-ruction of the bowels, &c.

B.P. (5).	NONE IN U.S.P.
Enema Aloes (aloes 40 grains, potassium carbonate 15 grains).	
„ Asafœtidæ (asafœtida 30 gr., water 4 fl. oz.).	
„ Magnesii Sulphatis (sulphate of magnesium 1 oz., olive oil 1 fl. oz.).	
„ Opii (tincture of opium ½ fl. dr.).	
„ Terebinthinæ (oil of turpentine 1 fl. oz.).	

B.P. Essentiæ. ESSENCES.—These are strong solutions 1 part volatile oil in 4 of rectified spirit. They are used as rminatives, and are usually given in the form of a few drops a piece of lump sugar, or with a little hot sugar and water, order to remove flatulence.

B.P. (2).	DOSE.
Essentia Anisi	10–20 m.
„ Menthæ Piperitæ	10–20 m.

Extracta. EXTRACTS.—Extracts consist of the soluble parts plants reduced to the consistence of a thick paste by extrac-on and evaporation. The plan of treatment adopted in order extract the soluble parts, and leave behind the woody fibre nd other inert constituents varies, according as the plant is esh or dry.

From fresh plants, green extracts (B.P.) are obtained by vaporation of the fresh juice after removal of the coagulable bumin. From dried plants the active principles are removed y treatment with cold or boiling water, with spirit, ether, or cetic acid, and the solutions thus obtained are evaporated to a nsistence suitable for making pills, or else to dryness.

Where the active principles are of a resinous or alkaloidal ature, and are more soluble in pure than in dilute spirit,

alcohol or rectified spirit is used; in other cases dilute alcoh or proof spirit is employed. Where the drug contains mo than one active substance and one is more soluble in spirit, a the other in water, both spirit and water are used. In order prevent extracts which, when freshly prepared, are of a pro consistence for making pills, from becoming too dry and hard keeping, the U.S.P. in several instances directs them to be mi with 5 per cent. of glycerine.

B.P. (34).	DOSE.	U.S.P. (31).	DOS
Extractum Aconiti	1–2 gr.	Extractum Aconiti	⅙–
„ Aloes Barbadensis	2–6 gr.	„ Aloes Aquosum	2–10
„ „ Socotrinæ	„	„ Arnicæ Radicis	3–
„ Anthemidis	2–10 gr.	„ Belladonnæ Alcoholicum	¼
„ Belladonnæ	¼–1 gr.	„ Cannabis Indicæ	
„ „ Alcoholicum	1/16–¼ gr.	„ Cinchonæ	10–30
„ Calumbæ	2–10 gr.	„ Colchici Radicis	1–
„ Cannabis Indicæ	¼–1 gr.	„ Colocynthidis	½–1
„ Cascaræ Sagradæ	2–8 gr.	„ „ Compositum	5–30
„ Colchici	½–2 gr.	„ Conii Alcoholicum	½–1
„ „ Aceticum	½–2 gr.	„ Digitalis	¼
„ Colcynthidis Compositum	3–10 gr.	„ Ergotæ	5–15
„ Conii	2–6 gr.	„ Euonymi	1–
„ Gelsemii Alcoholicum	½–2 gr.	„ Gentianæ	10–30
„ Gentianæ	2–10 gr.	„ Glycyrrhizæ	ad
„ Glycyrrhizæ	10–30 gr.	„ „ Purum	ad
„ Hæmatoxyli	„	„ Hæmatoxyli	10–30
„ Hyoscyami	5–10 gr.	„ Hyoscyami Alcoholicum	1–
„ Jaborandi	2–10 gr.	„ Iridis	1–
„ Jalapæ	5–15 gr.	„ Juglandis	5–10
„ Krameriæ	5–20 gr.	„ Krameriæ	10–20
„ Lactucæ	5–15 gr.	„ Leptandræ	20–30
„ Lupuli	„	„ Malti	1–
„ MezereiÆthereum		„ Mezerei	
„ Nucis Vomicæ	½–2 gr.	„ Nucis Vomicæ	½–
„ Opii	½–2 gr.	„ Opii	½–
„ Papaveris	2–5 gr.	„ Podophylli	1–
„ Pareiræ	10–30 gr.	„ Physostigmatis	1/16–
„ Physostigmatis	1/16–¼ gr.	„ Quassiæ	1–
„ Quassiæ	3–5 gr.	„ Rhei	5–10
„ Rhamni Frangulæ	15–20 gr.	„ Stramonii	¼–
„ Rhei	5–15 gr.	„ Taraxaci	20–60
„ Stramonii	¼–½ gr.		
„ Taraxaci	5–30 gr.		

Fluid U.S.P. or Liquid B.P. Extracts.—These are m like watery extracts, excepting that instead of evaporating infusion, decoction, or alcoholic solution (U.S.P.) to a s paste, it is only reduced to a small bulk, and in the B.P. sc spirit is added to it in order to prevent decomposition.

B.P. (13).	DOSE.
Extractum Belæ Liquidum	1–2 fluid drachms.
„ Cascaræ Sagradæ Liquidum	½–2 fluid drachms.
„ Cimicifugæ Liquidum	3–30 minims.
„ Cinchonæ „	10–30 minims.
„ Cocæ „	½–2 fluid drachms.
„ Ergotæ „	10–30 minims.

B.P.	DOSE.
Extractum Filicis Liquidum	15–60 minims.
„ Glycyrrhizæ „	60–120 minims.
„ Opii „	10–40 minims.
„ Pareiræ „	½–2 fluid drachms.
„ Rhamni Frangulæ Liquidum	1–4 fluid drachms.
„ Sarsæ Liquidum	2–4 fluid drachms.
„ Taraxaci Liquidum	¼–2 fluid drachms.

U.S.P. (79).	DOSE.
Extractum Aconiti Fluidum	½–1 m. (0·03–0·06 c.c.).
„ Arnicæ Radicis Fluidum	5–10 m. (0·3–0·6 c.c.).
„ Aromaticum „	10–20 m. (0·6–1·25 c.c.).
„ Aurantii Amari „	15–30 m. (0·9–1·9 c.c.).
„ Belladonnæ „	1–2 m. (0·06–0·12 c.c.).
„ Brayeræ „	½–1 fl. oz. (15–30 c.c.).
„ Buchu „	30–60 m. (1·9–3·8 c.c.).
„ Calami „	5–15 m. (0·3–0·9 c.c.).
„ Calumbæ „	15–30 m. (0·9–1·9 c.c.).
„ Cannabis Indicæ „	½–1 m. (0·03–0·06 c.c.).
„ Capsici „	½–1 m. (0·03–0·06 c.c.).
„ Castaneæ „	1–2 fl. dr. (3·75–7·5 c.c.)
„ Chimaphilæ „	1 fl. dr. (3·75 c.c.).
„ Chiratæ „	½ fl. dr. (1·9 c.c.).
„ Cimicifugæ „	½–1 fl. dr. (1·9–3·75 c.c.).
„ Cinchonæ „	¼–2 fl. oz. (7·5–60 c.c.).
„ Colchici Radicis „	2–8 m. (0·12–0·5 c.c.).
„ „ Seminis „	2–8 m. (0·12–0·5 c.c.).
„ Conii „	5 m. (0·3 c.c.).
„ Cornus „	30 m. (1·9 c.c.).
„ Cubebæ „	10–40 m. (0·6–2·5 c.c.).
„ Cypripedii „	15 m. (0·9 c.c.).
„ Digitalis „	1–2 m. (0·06–0·12 c.c.).
„ Dulcamaræ „	30–60 m. (1·9–3·75 c.c.).
„ Ergotæ „	½–4 fl. dr. (1·9–15 c.c.).
„ Erythroxyli „	20–60 m. (1·25–3·75 c.c.).
„ Eucalypti „	5–10 m. (0·3–0·6 c.c.).
„ Eupatorii „	20–60 m. (1·25–3·75 c.c.).
„ Frangulæ „	10–20 m. (0·6–1·25 c.c.).
„ Gelsemii „	2–3 m. (0·12–0·18 c.c.).
„ Gentianæ „	10–30 m. (0·6–1·9 c.c.).
„ Geranii „	30–60 m. (1·9–3·75 c.c.).
„ Glycyrrhizæ „	30–120 m. (1·9–7·5 c.c.).
„ Gossypii Radicis „	30–60 m. (1·9–3·75 c.c.).
„ Grindeliæ „	30–60 m. (1·9–3·75 c.c.).
„ Guaranæ „	1–2 fl. dr. (3·75–7·5 c.c.).
„ Hamamelidis „	30 m. (1·9 c.c.).
„ Hydrastis „	1–2 fl. dr. (3·75–7·5 c.c.).
„ Hyoscyami „	5 m. (0·3 c.c.).
„ Ipecacuanhæ „	15–30 m. (0·9–1·9 c.c.).
„ Iridis „	5–10 m. (0·3–0·6 c.c.).
„ Krameriæ „	10–60 m. (0·6–3·75 c.c.).
„ Lactucarii „	5–30 m. (0·3–1·9 c.c.).
„ Leptandræ „	20–60 m. (1·25–3·75 c.c.).
„ Lobeliæ „	10–20 m. (0·6–1·25 c.c.).
„ Lupulini „	10–15 m. (0·6–0·9 c.c.).
„ Maticæ „	30–60 m. (1·9–3·75 c.c.).
„ Mezerei „	for external use.
„ Nucis Vomicæ „	3–5 m. (0·18–0·3 c.c.).
„ Pareiræ „	1–2 fl. dr. (3·75–7·5 c.c.).
„ Pilocarpi „	15–30 m. (0·9–1·9 c.c.).
„ Podophylli „	5–15 m. (0·3–0·9 c.c.)
„ Pruni Virginianæ „	30–60 m. (1·9–3·75 c.c.).

U.S.P.		DOSE.
Extractum	Quassiæ Fluidum	.....5–10 m. (0·3–0·6 c.c.).
,,	Rhei ,,	.....5–30 m. (0·3–1·9 c.c.).
,,	Rhois Glabræ ,,	.....for external use.
,,	Rosæ ,,	.....1–2 fl. dr. (3·75–7·5 c.c.).
,,	Rubi ,,	.....½–1 fl. dr. (1·9–3·75 c.c.).
,,	Rumicis ,,	....1 fl. dr. (3·75 c.c.).
,,	Sabinæ ,,	.....3–8 m. (0·18–0·5 c.c.).
,,	Sanguinariæ ,,	... .3–5 m. (0·18–0·3 c.c.).
,,	Sarsaparillæ ,,	.....2–4 fl. dr. (7·5–15 c.c.).
,,	Sarsaparillæ Compositum ,,	.....30–60 m. (1·9–3·75 c.c.).
,,	Scillæ ,,	.....1–3 m. (0·12–0·18 c.c.).
,,	Scutellariæ ,,	.....30–60 m. (1·9–3·75 c.c.).
,,	Senegæ ,,	.....1–5 m. (0·06–0·3 c.c.).
,,	Sennæ ,,	.....1–4 fl. dr. (3·75–15 c.c.).
,,	Serpentariæ ,,	.....20–30 m. (1·25–1·9 c.c.).
,,	Spigeliæ ,,	.....1–2 fl. dr. (3·75–7·5 c.c.).
,,	Stillingiæ ,,	.....15–45 m. (0·9–2·8 c.c.).
,,	Stramonii ,,	.....1–2 m. (0·06–0·12 c.c.).
,,	Taraxaci ,,	.....1–3 fl. dr. (3·75–11·25 c.c.
,,	Tritici ,,	.....3–6 fl. dr. (11·25–22·5 c.c.
,,	Uvæ Ursi ,,	.....30–60 m. (1·9–3·75 c.c.).
,,	Valerianæ ,,	.....1 fl. dr. (3·75 c.c.).
,,	Veratri Viridis ,,	.....1–2 m. (0·06–0·12 c.c.).
,,	Viburni ,,	.....30–60 m. (1·9–3·75 c.c.).
,,	Xanthoxyli ,,	.....30–60 m. (1·9–3·75 c.c.).
,,	Zingiberis ,,	.....10–20 m. (0·6–1·25 c.c.).

B.P. Fresh or Green Extracts. — These extracts h already been enumerated among the others. In preparing th the juice obtained from the fresh leaves, flowering tops or fru of the plant, by pressure, is heated to 130° F. to coagulate green colouring matter. This is then filtered off and laid as The filtrate is next heated to 200° F. so as to coagulate the al min; this is filtered off and thrown away. The filtrate is t evaporated at a temperature not exceeding 140° to a thin syr The colouring matter is then added to it, and the wh evaporated to a proper consistence. In the case of extract colchicum and taraxacum there is no chlorophyll to separate the juices are obtained by expression from the colchicum co and the taraxacum root, and not from flowering tops. Con quently the juice is at once heated to the boiling point to coa late the albumin, and after this has been filtered out the filt is evaporated at a temperature of 160° F. In the case of gr extracts, the preservation of the green colour is usually regar as a sign that they are good. It certainly indicates that first and the last parts of the process have been conducted v care, as too high a temperature destroys the green colour.] therefore probable that the whole process may have been c fully done; but this is not certain, for the juice may have b exposed to a high temperature, and thus injured during evaporation after the chlorophyll has been removed and be it has again been added.

The green extracts of the B.P. are (8) :—

tractum Aconiti.	Extractum Colchici Aceticum.	Extractum Lactucæ.
„ Belladonnæ.	„ Conii.	„ Taraxaci.
„ Colchici.	„ Hyoscyami.	

Glycerina, B.P.; Glycerita, U.S.P. GLYCERINES.—These e solutions of soothing, astringent, or antiseptic substances in ycerine. Glycerine being thick and adhesive, they form most eful local applications, either to the skin or mucous membranes.

Those in the B.P. containing carbolic, tannic, and gallic acids ve one part of the drug by weight to four of glycerine by easure; starch, being very light and bulky, is used in only lf this proportion, i.e. one ounce of starch to eight ounces of cerine. In the U.S.P. the starch is in the proportion of 1 to i.e. 10 per cent. The glyceritum vitelli contains 45 parts fresh lk of egg to 55 of glycerine.

B.P. (9).	U.S.P. (3).
cerinum.	Glycerinum.
„ Acidi Carbolici (1 to 4).	Glyceritum Amyli (1 in 10).
„ „ Gallici (1 to 4).	„ Vitelli ($4\frac{1}{2}$ in 10).
„ „ Tannici (1 to 4).	
„ Aluminis (1 to 5).	
„ Amyli (1 to 8).	
„ Boracis (1 to 6).	
„ Plumbi Subacetatis.	
„ Tragacanthæ (3 to 14).	

Infusa. INFUSIONS.—These are prepared by simply pouring ling water on the drug, allowing it to stand for some time, d then straining.

There are four exceptions to this rule of using boiling water, . calumba, quassia, chiretta, and cusparia. Infusions of umba and quassia are prepared with cold water. The reason using cold water in the case of calumba is that the root ntains a quantity of starch, which is extracted if hot water be d, and renders the infusion liable to decompose, especially in weather.

I have been unable to find any definite reason assigned for ng cold water in the preparation of infusion of quassia, exting that cold water is sufficient to dissolve the active nciple.

In the only instance in which I have seen an infusion made h hot water used, it caused vomiting, so that perhaps an usion made with hot water has a more irritating action than t made with cold.

Infusions of chiretta and cusparia are made with water at 0° F. instead of boiling water, as they are more agreeable when pared in this way.

The infusions of substances not specified in the U.S.P. are ected by it to be prepared by taking ten parts of the substance

in coarse powder and 100 of boiling water. These are to be
into a vessel with a tight cover, and allowed to stand for
hours. The infusion is then strained, and enough water pas
through the strainer to make the product weigh 100 parts.

All the infusions both of the B.P. and U.S.P. are strain
with the exception of the infusion of cusso or brayera.

B.P. (28).	DOSE. (Of all not specified 1–2 fl. oz.)	U.S.P. (5).	DO
Infusum Anthemidis	1–4 fl. oz.	Infusum Brayeræ (Cusso)	1(
,, Aurantii		,, Cinchonæ	
,, ,, Compositum		,, Digitalis [1]	
,, Buchu	1–4 fl. oz.	,, Pruni Virginianæ	2–
,, Calumbæ		,, Sennæ Compositum	4 f
,, Caryophylli			
,, Cascarillæ			
,, Catechu			
,, Chiratæ			
,, Cinchonæ Acidum			
,, Cuspariæ			
,, Cusso (Brayera anthelmintica)	4–8 fl. oz.		
,, Digitalis	1–4 fl. dr.		
,, Ergotæ			
,, Gentianæ Compositum			
,, Jaborandi			
,, Krameriæ			
,, Lini			
,, Lupuli			
,, Maticæ			
,, Quassiæ			
,, Rhei			
,, Rosæ Acidum			
,, Senegæ			
,, Sennæ			
,, Serpentariæ			
,, Uvæ Ursi			
,, Valerianæ			

B.P. Injectiones Hypodermicæ. HYPODERMIC INJECTION
These are strong solutions for subcutaneous injection (p.
As the solutions may become decomposed by keeping, they sh
be freshly prepared; and even the injection of morphine sh
not be kept long. Any solid particles should be remove
filtration (p. 476). The injections of apomorphine and of er
are simply made by dissolving these substances in cam
water and filtering if necessary. The injection of morphi
prepared by dissolving freshly-precipitated morphine in a
acid and water. It is ten times as strong as the liquor a
rather stronger than the corresponding preparation in the
of 1867, containing 1 grain in 10 minims, instead of 1 gra
12 minims.

[1] This infusion is about twice the strength of the B.P. The dose is
stated at ½ oz. twice a day, but in many cases this dose would probably pro
large, and it is safer to begin with a smaller dose, and gradually push it
patient will stand it.

B.P.			DOSE.
Injectio Apomorphinæ	Hypodermica	(2 in 100)	2–8 min.
,, Ergotini	,,	(1 to 2)	3–10 min.
,, Morphinæ	,,	(1 in 10)	1–5 min.

B.P. Lamellæ. GELATINE DISCS.—These are thin discs of latine with some glycerine, each weighing about $\frac{1}{50}$th grain d containing a small quantity of an alkaloid. They are chiefly ed for local application to the eye. They may sometimes be nvenient for preparing solutions for hypodermic injection by solving them in a few drops of water.

Lamellæ Atropinæ ($\frac{1}{5000}$th grain in each).
,, Cocainæ ($\frac{1}{200}$th grain in each).
,, Physostigminæ ($\frac{1}{1000}$th grain in each).

Linimenta. LINIMENTS OR EMBROCATIONS.—These are preations for rubbing or painting on a part of the body in order produce local stimulation or relieve pain. The basis of most those in the British Pharmacopœia is olive oil, and of those in United States Pharmacopœia cotton-seed oil.[1] Camphor is ded to most of the liniments in the B.P. for its local stimulant ion, and also that its strong smell may lessen the risk of the iment being used internally. There are four exceptions in the P.—the liniments of ammonia, lime, croton oil, and iodide of assium with soap. With the exception of the liniment of e all these contain very strong smelling substances, namely, monia in the corresponding liniment, cajuput oil in the croton liniment, and oil of lemon in the iodide of potassium and p liniment.

Camphor is not contained in the liniments of the U.S.P., h the exception of the liniments of belladonna, camphor, oroform and soap.

Soap is used to give a lubricating quality to four liniments in B.P., viz. opium, iodide of potassium with soap, soap and pentine; and to two in the U.S.P., viz. chloroform and soap. the compound mustard liniment, whose composition is nearly same in the B.P. and the U.S.P., castor oil is used as a ricant along with alcohol. In one, the turpentine liniment he U.S.P., the lubricating substances are lard and yellow wax.

Three liniments in the B.P., aconite, belladonna, and iodine, l one in the U.S.P., belladonna, are really exceedingly strong tions of active principles in spirit with camphor added for purposes already mentioned.

The liniments last mentioned contain no fatty substances as ricants, nor does the croton oil liniment of the B.P., comnd camphor liniment (B.P.), nor the linimentum cantharidis S.P.). Croton oil liniment (B.P.) is a solution of croton oil

[1] I have been told that a great deal of what is sold as olive oil in Great Britain ally cotton-seed oil.

with cajuput oil in spirit. The compound camphor liniment a mixture of strong solution of ammonia with rectified spir camphor, and oil of lavender.

The linimentum cantharidis (U.S.P.) is a solution of th active principles of cantharides in turpentine. The difference composition between the ordinary camphor liniment (B.P.), whic is simply a mixture of camphor and olive oil, and the compou camphor liniment should be carefully borne in mind. The lin mentum terebinthinæ aceticum (B.P.) consists of oil of turpe tine and acetic acid mixed with ordinary camphor liniment. B if anyone, thinking to increase its efficacy, should add to it co pound camphor liniment, the acetic acid and ammonia wou neutralise one another more or less completely, and the activi of both liniments would be to a great extent destroyed.

B.P. (16).

The proportion of ingredients is put after each constituent.

Linimentum	Basis	Solvent	Adjuvant	Vehicle
Aconiti . .	Aconite root (20)	Rectified spirit (30)	Camphor (1)	
Ammoniæ .	Liquor Ammoniæ (1)			Olive oil (3)
Belladonnæ .	Belladonna root (20)	Rectified spirit (30)	Camphor (1)	
Calcis . .	Liquor Calcis (1)			Olive oil (1)
Camphoræ .	Camphor (1) .			Olive oil (4)
Camphoræ Compositum	Camphor (1) .	Rectified spirit (6)	Liquor ammoniæ fortior (2)	
Chloroformi .	Chloroform (1)			Liniment Camphor (
Crotonis . .	Croton oil (2) .	Rectified spirit (7)	Cajuput oil (7)	
Hydrargyri .	Mercury ointment (1)		Liquor ammoniæ (1)	Liniment Camphor (
Iodi . .	Iodine (5) .	Iodide of Potassium (2)		Glycerine (1 Rectified spi (40)
Opii . .	Tincture of Opium (1)			Liniment Soap (1)
Potassii Iodidi cum Sapone	Iodide of Potassium (12)	Glycerine (8) .	Curd Soap (16) Oil of Lemon (1)	Water (80)
Saponis . .	Hard Soap (16)	Water (32) . Rectified spirit (128)	Camphor (8) Oil of Rosemary (3)	
Sinapis Compositum	Oil of Mustard (1·4)	Castor oil (7) .	Ethereal extract of Mezereon (1) Camphor (3) . Camphor (1)	Rectified sp (44)
Terebinthinæ .	Oil of turpentine (16)		Soft Soap .	Water (2)
Terebinthinæ Aceticum	Oil of turpentine (4)		Glacial Acetic Acid (1)	Liniment Camphor

U.S.P. (10).

Linimentum	Basis	Solvent	Adjuvant	Vehicle
Ammoniæ .	Liquor Ammoniæ (3)			Cotton-seed oil (7)
Belladonnæ .	Fluid Extract of Belladonna (95)		Camphor (5)	
Calcis . .	Lime water (1)			Cotton-seed oil (1)
Camphoræ .	Camphor (1) .			Cotton-seed oil (4)
Cantharidis .	Cantharides (15)	Oil of Turpentine (85)		
Chloroformi .	Chloroform (4)			Soap liniment (6)
Plumbi Subacetatis	Solution of Subacetate of Lead (4)			Cotton-seed oil (6)
Saponis .	Soap (10)	Water (20) .	Camphor (5) . Oil of Rosemary	Alcohol (70)
Sinapis Compositum	Volatile Oil of Mustard (3)	Castor oil (15)	Extract of Mezereon (2) Camphor (6)	Alcohol (74)
Terebinthinæ.	Oil of Turpentine (35)		Resin Cerate (65)	

Liquores. SOLUTIONS.—These are solutions of active substances in water, either alone or with the aid of other solvents.

B.P. (48).	DOSE.
Liquor Acidi Chromici.....	
„ Ammoniæ	10–30 m.
„ „ Fortior.....	3–10 m.
„ Ammonii Acetatis	2–6 fl. dr.
„ „ „ Fortior	25–75 m.
„ „ Citratis.....	2–6 fl. dr.
„ „ „ Fortior	½–1½ fl. dr.
„ Antimonii Chloridi ...	
„ Arsenicalis.....	2–8 m.*
„ Arsenici Hydrochlorici	2–8 m.*
Arsenii et Hydrargyri Iodidi	
„ Atropinæ Sulphatis...	1–4 m.*
„ Bismuthi et Ammonii Citratis	½–1 fl. dr.
„ Calcii Chloridi.....	
„ Calcis.....	1–4 fl. oz.
„ Calcis Chlorinatæ.....	
„ „ Saccharatus	15–60 m.
„ Chlori.....	10–20 m.
„ Epispasticus.....	
„ Ferri Acetatis.....	
„ „ „ Fortior	
„ „ Dialysatus	
„ „ Perchloridi	10–30 m.
„ „ „ Fortior	

U.S.P. (27)	DOSE.
Liquor Acidi Arseniosi.....	2–8 m.
„ Ammonii Acetatis.....	½–1½ oz.
„ Arsenici et Hydrargyri Iodidi	5–10 m.
„ Calcis	2–4 fl. oz.
„ Ferri Acetatis	2–10 m.
„ „ Chloridi	„
„ „ Citratis.....	10 m.
„ „ et Quininæ Citratis.....	10–20 m.
„ „ Nitratis	5–20 m.
„ „ Subsulphatis	3–6 m.
„ „ Tersulphatis	
„ Gutta-perchæ	
„ Hydrargyri Nitratis....	
„ Iodi Compositus	5 m.
„ Magnesii Citratis .....6–12 fl. oz.	
„ Pepsini.....	½–2 fl. oz.
„ Plumbi Subacetatis ...	
„ „ Subacetatis Dilutus.....	
„ Potassii	10–60 m.
„ „ Arsenitis.....	5 m.
„ „ Citratis	½–2 fl. oz.
„ Sodæ	10–60 m.
„ „ Chloratæ	30–60 m.
„ Sodii Arseniatis.....	3–8 m.

B.P.	DOSE.	U.S.P.	DOSE.
Liquor Ferri Pernitratis	10–30 m.	Liquor Sodii Silicatis	
,, ,, Persulphatis		,, Zinci Chloridi	
,, Gutta Percha			
,, Hydrargyri Nitratis Acidus			
,, Hydrargyri Perchloridi	½–2 fl. dr.		
,, Iodi	**		
,, Lithiæ Effervescens	5–10 fl. oz.		
,, Magnesii Carbonatis	1–2 fl. oz.		
,, ,, Citratis	5–10 fl. oz.		
,, Morphinæ Acetatis	10–60 m.*		
,, ,, Bimeconatis			
,, ,, Hydrochloratis	,,		
,, Plumbi Subacetatis			
,, ,, ,, Dilutus			
,, Potassæ	,,		
,, ,, Effervescens	5–10 fl. oz.		
,, Potassii Permanganatis	1–4 fl. dr.*		
,, Sodæ	10–60 m.		
,, ,, Effervescens	5–10 fl. oz.		
,, ,, Chloratæ	10–20 m.		
,, Sodii Arseniatis	5–10 m.*		
,, ,, Ethylatis			
,, Strychninæ Hydrochloratis	5–10 m.*		
,, Zinci Chloridi			

The strength of the liquors marked with an * in the preceding list has b changed from 4 grains to 1 fluid oz., or 1 in 109 (B.P. 1867) to 4½ grains in 1 fl oz., or 1 in 100 in the B.P. 1885. The strength of the one marked ** has b increased from 5 in 109 to 5 in 100.

B.P. Lotiones. LOTIONS.—Mixtures of active substanc in water for external application.

Lotio Hydrargyri Flava (1 part Perchloride of Mercury to 243 of Lime-water)
,, ,, Nigra (,, Subchloride ,, 146 ,,)

U.S.P. Massæ. MASSES.—These simply consist of su stances mixed together to a consistence suitable for maki pills.

Massa Copaibæ.
,, Ferri Carbonatis.
,, Hydrargyri.

Mellita. HONEYS.—In these preparations honey is used a vehicle. Oxymel and oxymel scillæ of the B.P., which conta acetic acid, may be regarded as belonging to this class.

B.P. (4).	U.S.P. (2).
Mel Boracis.	Mel Despumatum.
,, Depuratum.	,, Rosæ.
Oxymel.	
,, Scillæ.	

Misturæ. MIXTURES.—These usually consist of insolu substances simply mixed with water or suspended in it by t aid of gum or other viscid substances. In almond (B.P. a

.S.P.), chalk (B.P. and U.S.P.), guaiac (B.P.), and compound ycyrrhiza (U.S.P.) mixtures, gum is added. In the ammonia- m (B.P. and U.S.P.), asafœtida (U.S.P.) and compound iron .P. and U.S.P.) mixtures, gum is contained in the ammonia- m, asafœtida, and myrrh used in their preparation respec- vely.

In scammony mixture (B.P.) the scammony resin is simply spended in milk. In egg flip or brandy mixture (mistura iritus vini gallici) (B.P.) and chloroform mixture (U.S.P.) yolk egg forms the basis of the mixture.

The magnesia and asafœtida,[1] and rhubarb and soda mix- res of the U.S.P. contain insoluble substances mixed with ater without the addition of any viscid substance; in the easote mixture (B.P.) the syrup may be looked upon as viscid d tending to keep the ingredients mixed, but the aromatic n and compound senna mixtures of the B.P. and the acetate iron and ammonium (U.S.P.) mixture are simply solutions and t mixtures in the usual sense.

B.P. (10).	DOSE.	U.S.P. (11).	DOSE.
stura Ammoniaci	½–1 fl. oz.	Mistura Ammoniaci	½–1 fl. oz.
„ Amygdalæ	1–2 fl. oz.	„ Amygdalæ	1–2 fl. oz.
„ Creasoti	„	„ Asafœtidæ	½–1 fl. oz.
„ Cretæ	„	„ Chloroformi	„
„ Ferri Aromatica	„	„ Cretæ	1–2 fl. oz.
„ „ Composita	„	„ Ferri Composita	„
„ Guaiaci	„	„ „ et Ammonii Acetatis	½–1 fl. oz.
„ Scammonii	„	„ Glycyrrhizæ Composita	½ oz.
„ Sennæ Composita	„	„ Magnesiæ et Asafœtidæ	20 m.
„ Spiritus Vini Gallici	„	„ Potassii Citratis	½ fl. oz.
		„ Rhei et Sodæ	½–1 dr.

Mucilagines. MUCILAGES. — These are thick solutions, rtial or complete, of gum or starch, which are convenient for spending heavy powders in mixtures.

B.P. (3).	U.S.P. (5).
Mucilago Acaciæ.	Mucilago Acaciæ.
„ Amyli.	„ Cydonii.
„ Tragacanthæ.	„ Sassafras Medullæ.
	„ Tragacanthæ.
	„ Ulmi.

Olea. OILS.—These are divided into fixed and volatile. The xed are obtained by simple expression; the volatile by distilla- on excepting in the case of oil of lemon, which being con- ined in distinct vittæ in the rind, may be expressed instead of eing distilled.

[1] In this mixture there is no gum, for although it is contained in crude afœtida, it is not contained in the tincture of asafœtida used in this preparation.

Fixed Oils.

B.P. (9).	DOSE.	U.S.P. (11).	DOSE.
Oleum Amygdalæ	1–4 fl. dr.	Oleum Adipis	
„ Crotonis (croton oil)	$\frac{1}{3}$–1 min.	„ Amygdalæ Expressum	1–8 fl.
„ Lini		„ Gossypii Seminis	
„ Morrhuæ	1–8 fl. dr.	„ Lini	
„ Myristicæ Expressum		„ Morrhuæ	$\frac{1}{2}$–4 fl.
„ Olivæ	„	„ Olivæ	
„ Phosphoratum	5–10 min.	„ Phosphoratum	1–5 mi
„ Ricini	1–8 fl. dr.	„ Ricini	1–8 fl.
„ Theobromatis		„ Sesami	
		„ Theobromæ	
		„ Tiglii (croton oil)	$\frac{1}{4}$–1 m

Volatile Oils.

B.P. (25).	DOSE OF EACH.
	1–4 m. unless otherwise mentioned.
Oleum Anethi	
„ Anisi	
„ Anthemidis	
„ Cajuputi	
„ Carui	
„ Caryophylli	
„ Cinnamomi	
„ Copaibæ	5–20 min.
„ Coriandri	
„ Cubebæ	5–20 min.
„ Eucalypti	
„ Juniperi	1–10 min.
„ Lavandulæ	
„ Limonis	
„ Menthæ Piperitæ	
„ „ Viridis	
„ Myristicæ	
„ Pimentæ	
„ Pini Sylvestris	for use as vapour.
„ Rosmarini	
„ Rutæ	
„ Sabinæ	
„ Santali	10–30 min.
„ Sinapis	For external use only.
„ Terebinthinæ	10–20 m. as diuretic, 2–6 fl. dr. as anthelmintic.

U.S.P. (40).	DOSE.
Oleum Æthereum	
„ Amygdalæ Amaræ	$\frac{1}{4}$–1 min (0·016–0·06 c.c.).
„ Anisi	5–15 min. (0·3–0·9 c.c.).
„ Aurantii Corticis	
„ „ Florum	
„ Bergamii	
„ Cajuputi	5–20 min. (0·3–1·25 c.c.).
„ Cari	1–10 min. (0·06–0·6 c.c.).
„ Caryophylli	2–6 min. (0·12–0·36 c.c.).
„ Chenopodii	4–8 min. for a child (0·25–0·5 c.c.).
„ Cinnamomi	1–3 min. (0·06–0·18 c.c.).
„ Copaibæ	10–15 min. (0·6–0·9 c.c.).
„ Coriandri	
„ Cubebæ	10–12 min. at first (0·6 or 0·72 c.c.), gradually increased.

Volatile Oils—*continued.*

U.S.P.	DOSE.
Oleum Erigerontis	10 min. to ½ fluid drachm (0·6–1·9 c.c.).
„ Eucalypti	10–15 min. (0·6–0·9 c.c.).
„ Fœniculi	5–15 min. (0·3–0·9 c.c.).
„ Gaultheriæ	
„ Hedeomæ (pennyroyal)	2–10 min. (0·12–0·6 c.c.).
„ Juniperi	5–15 min. (0·3–0·9 c.c.).
„ Lavandulæ	1–5 min. (0·06–0·3 c.c.).
„ „ Florum	
„ Limonis	
„ Menthæ Piperitæ	2–6 min. (0·12–0·36 c.c.).
„ „ Viridis	2–6 min. (0·06–0·36 c.c.).
„ Myrciæ	
„ Myristicæ	2–3 min. (0·12–0·18 c.c.).
„ Picis Liquidæ	
„ Pimentæ	3–6 min. (0·18–0·36 c.c.).
„ Rosæ	
„ Rosmarini	3–6 min. (0·18–0·36 c.c.).
„ Rutæ	2–5 min. (0·12–0·3 c.c.).
„ Sabinæ	2–5 min. (0·12–0·3 c.c.).
„ Santali	20–30 min. (1·25–1·9 c.c.).
„ Sassafras	3–5 min. (0·18–0·3 c.c.).
„ Sinapis Volatile	
„ Succini	5–15 min. (0·3–0·9 c.c.).
„ Terebinthinæ	5–30 min. (0·3–1·9 c.c.).
„ Thymi	
„ Valerianæ	4–5 min. (0·24–0·3 c.c.).

Oleata. OLEATES.—Solutions of bases in oleic acid. They are more readily absorbed by the skin than ointments.

B.P.	U.S.P.
Oleatum Hydrargyri.	Oleatum Hydrargyri.
„ Zinci.	„ Veratrinæ.

Oleoresinæ. OLEORESINS.—These are, as the name implies, mixtures of volatile oil and resin. They are extracted by treating the crude substance with stronger ether, and removing the ether partly by distillation and partly by evaporation. Their advantage is that they remain in a liquid or semi-liquid state, and are stable, not requiring alcohol to prevent decomposition.

B.P.	DOSE.
Oleoresina Cubebæ	5–30 min.

U.S.P.	DOSE.
Oleoresina Aspidii	½–1 fl. dr. (1·9–3·75 c.c.).
„ Capsici	¼–1 min. (0·015–0·06 c.c.).
„ Cubebæ	5–30 min. (0·3–1·9 c.c.).
„ Lupulini	2–5 gr. (0·13–0·33 gm.).
„ Piperis	¼–1 min. (0·015–0·06 c.c.).
„ Zingiberis	⅒–1 min. (0·006–0·06 c.c.).

Oxymel.—*Vide* MELLITA.

Pilulæ. PILLS.—Pills are small round masses which can conveniently swallowed. They are rarely made of a greater

B.P. (21).

DOSE: 5–10 grains, with the exception of those mentioned.

Pilula	**Curare.**—Basis	Proportion of Basis	**Cito.**—Adjuvant	Proportion of Adjuvant	**Tute.**—Corrective	**Jucunde.**—Vehicle.	Dose
Aloes Barbadensis	Barbadoes Aloes	1 in 2	Hard Soap	1 in 4	Oil of Carraway	Confection of Roses	
Aloes et Asafœtidæ	Socotrine Aloes	1 in 4	,, ,,	1 in 4	Asafœtida	,, ,,	
Aloes et Ferri	Barbadoes Aloes	1 in 5¼	Sulphate of Iron	1 in 7	Compound Powder of Cinnamon	,, ,,	
Aloes et Myrrhæ	Socotrine Aloes	1 in 2¼	Myrrh	1 in 4½	Saffron	,, ,,	
Aloes Socotrinæ	,, ,,	1 in 2	Hard Soap	1 in 4	Volatile Oil of Nutmeg	,, ,,	
Asafœtidæ Composita (*syn.* Galbani Composita)	Asafœtida	1 in 3⅓	Galbanum	1 in 3½	Myrrh	Treacle	
Cambogiæ Composita	Gamboge	1 in 5	Barbadoes Aloes	1 in 5	Compound Powder of Cinnamon	Syrup	
			Hard Soap	1 in 5			
Colocynthidis Composita	Colocynth pulp	1 in 5	Barbadoes Aloes	1 in 2½	Oil of Cloves	Water	
			Scammony	1 in 2½			
			Sulphate of Potassium	1 in 20			
Colocynthidis et Hyoscyami	Compound pill of Colocynth	2 in 3	—	—	Extract of Henbane		
Conii Composita	Extract of Hemlock	5 in 6	Ipecacuanha	1 in 6	—	Treacle	
Ferri Carbonatis	Saccharated Carbonate of Iron	4 in 5	—	—	—	Confection of Roses	5–20 grs.
Ferri Iodidi	Iron Wine	—	—	—	Refined Sugar	Liquorice Root and Water	3–8 grs.
	Iodine						
Hydrargyri	Mercury	1 in 3	—	—	Confection of Roses	Liquorice Root	3–8 grs.
Hydrargyri Subchloridi Composita	Subchloride of Mercury	1 in 5	Sulphurated Antimony	1 in 5	Guaiacum Resin (1 in 2½)	Castor Oil	
Ipecacuanhæ cum Scillâ	Compound Powder of Ipecacuanha	3 in 5	Squill	1 in 5	Ammoniacum (1 in 5)	Treacle	

Rhei Compositus	Rhubarb Root	1 in 32	Socotrine Aloes	1 in 5	Myrrh	Treacle	
Saponis Composita (*syn.* Opii)	Opium	1 in 5	—	—	Hard Soap . .	Glycerine . .	3–5 grs.
Scammonii Composita .	Resin of Scammony .	1 in 6	Resin of Jalap .	1 in 6	Strong Tincture of Ginger	Rectified Spirit .	5–15 grs.
			Curd Soap . .	1 in 6			
Scillæ Composita . .	Squill	1 in $6\frac{1}{4}$	Ammoniacum .	1 in $6\frac{1}{4}$	Ginger . . .	Hard Soap Treacle	

U.S.P. (15). *Vide* also Massæ.

Aloes	Purified Aloes . .	1 in 2	Soap . . .	1 in 2	—	—	1–5 pills
Aloes et Asafœtidæ .	,, ,, . .	1 in 3	,, . . .	1 in 3	Asafœtida . .	—	2–5 pills
Aloes et Ferri . .	,, ,, . .	1 in 3	Sulphate of Iron .	1 in 3	Aromatic Powder .	Confection of Rose	1–3 pills
Aloes et Mastiches .	,, ,, . .	2 in 3	—	—	Mastic . . .	Red Rose . .	1 pill
Aloes et Myrrhæ . .	,, ,, . .	1 in $1\frac{3}{4}$	Myrrh . . .	1 in $3\frac{1}{2}$	Aromatic Powder .	Syrup . . .	3–6 pills
Antimonii Compositæ (Plummer's Pills)	Sulphurated Antimony.	1 in 4	Mild Chloride of Mercury	1 in 4	Guaiac . . .	Mucilage of Tragacanth	1–2 pills
Asafœtidæ . . .	Asafœtida . . .	3 in 4	—	—	—	Soap . . .	1 pill
Catharticæ Compositæ.	Compound Extract of Colocynth	1 in 3 (nearly)	Abstract of Jalap .	1 in $3\frac{1}{2}$	—	Water . . .	1–3 pills
			Mild Chloride of Mercury . .	1 in $3\frac{1}{2}$			
			Gamboge . .	1 in 14			
Ferri Compositæ . .	Sulphate of Iron . .	1 in 4	Carbonate of Sodium	1 in 4	Myrrh . . .	Syrup . . .	2–6 pills
					Glycyrrhiza, Extract of Glycyrrhiza	Sugar Balsam of Tolu	
						Stronger Ether .	1 pill
Ferri Iodidi . .	Reduced Iron, Iodine .	—	—	—	Acacia		
Galbani Compositæ .	Galbanum . . .	1 in $2\frac{1}{3}$	Myrrh . . .	1 in $2\frac{1}{3}$	Asafœtida . .	Syrup . . .	2–4 pills
Opii	Opium	1 in $1\frac{1}{4}$	—	—	—	Soap . . .	1 pill
Phosphori . . .	Phosphorus . . .	1 in 100	Althæa . . .	1 in $2\frac{1}{2}$	Acacia . . .	Balsam of Tolu .	1–2 pills
					Glycerin		
					Chloroform . .	Stronger Ether	
Rhei	Rhubarb . . .	1 in $1\frac{1}{3}$	—	—	—	Soap . . .	1–6 pills
Rhei Compositæ . .	,, ...	1 in $2\frac{1}{3}$	Aloes . . .	1 in 3	Myrrh . . .	—	2–4 pills
					Oil of Peppermint		

weight than five grains, as they then become too bulky to swallowed easily. Those of the U.S.P. are four grains each. their composition the old rule of **curare cito, tute, et jucun** has been pretty strictly followed, and most of them in addition the basis contain an adjuvant, corrective, and vehicle (see Tab pp. 522, 523). To prevent them sticking together they generally shaken with some dry powder, such as lycopodiu carbonate of magnesium, flour, starch, or liquorice powd Sometimes they are gilt or silvered by shaking them wi freshly prepared, and without the addition of any dust powder, along with gold or silver leaf in a hollow spherical wood box. Sometimes pills are coated with sugar. Recently a coat of firm gelatine has been used, and perhaps the best coating all in certain cases is keratin (*q. v.*).

Pulveres. Powders.—The fineness of powders is ascertai by the size of the meshes of the sieve through which they pa and is represented by numbers ranging from No. 20 to No. these numbers indicating the numbers of parallel wires of ordin thickness within a linear inch forming the meshes of the sie used. The officinal powders contain two or more substan triturated and mixed together.

B.P. (15).	DOSE.
Pulvis Amygdalæ Compositus	60–120 grs.
,, Antimonialis	3–10 grs.
,, Catechu Compositus	20–40 grs.
,, Cinnamomi Compositus	3–10 grs.
,, Cretæ Aromaticus	10–60 grs.
,, ,, ,, cum Opio	10–40 grs.
,, Elaterini Compositus	½–5 grs.
,, Glycyrrhizæ Compositus	30–60 grs.
,, Ipecacuanhæ Compositus	5–15 grs.
,, Jalapæ Compositus	20–60 grs.
,, Kino Compositus	5–20 grs.
,, Opii Compositus	2–5 grs.
,, Rhei Compositus	20–60 grs.
,, Scammonii Compositus	10–20 grs.
,, Tragacanthæ Compositus	20–60 grs.

U.S.P. (9).	DOSE.
Pulvis Antimonialis	3–8 grs. (0·2–0·52 gm.).
,, Aromaticus	10–30 grs. (0·65–1·95 gm.).
,, Cretæ Compositus	10–30 grs. (0·65–1·95 gm.).
,, Effervescens Compositus	One powder.
,, Glycyrrhizæ Compositus	30–60 grs. (1·95–3·9 gm.).
,, Ipecacuanhæ et Opii	5–15 grs. (0·33–1 gm.).
,, Jalapæ Compositus	30–60 grs. (1·95–3·9 gm.).
,, Morphinæ Compositus	10 grs. (0·65 gm.).
,, Rhei Compositus	30–60 grs. (1·95–3·9 gm.).

Resinæ. Resins.—These are brittle, amorphous solids, sisting of an acid or mixtures of acids formed by the oxida of terpenes which are volatile hydrocarbons having the form $C_{10}H_{16}$. Resins are insoluble in water, but soluble in sp They melt when heated, and solidify again on cooling.

solve in alkalies, forming a kind of soap. They frequently ur in plants along with unoxidised volatile oils as oleo-resins. sins may be obtained from oleo-resins, e.g. turpentine, by nple distillation, when the volatile oil distils over and the resin mains. They may be got by heating the part of the plant in ich they are contained, e.g. guaiac resin. They may be pre- red by dissolving them out of the plants by means of alcohol d removing the alcohol by distillation, or precipitating them throwing the strong tincture into water. Resins are of an d nature, and the addition of a little mineral acid to water ses them to be precipitated more readily.

B.P. (5).	U.S.P. (5).
Resina.	Resina Copaibæ.
„ Guaiaci.	„ Jalapæ.
„ Jalapæ.	„ Podophylli.
„ Podophylli.	„ Scammonii.
„ Scammoniæ.	Guaiaci Resina.

Spiritus. SPIRITS.—With the exception of rectified and proof rit, these are alcoholic solutions of volatile oils or ethers. The se is ½ to 1 fluid drachm, except where otherwise mentioned, d except in the case of brandy, rum, and whisky, the doses of ich vary very much, according to the purpose for which they e used.

B.P. (18).	DOSE.
Spiritus Ætheris	30–90 min.
„ „ Compositus	½–2 fluid drachms.
„ „ Nitrosi	„
„ Ammoniæ Aromaticus	
„ „ Fœtidus	
„ Armoraciæ Compositus	1–2 fluid drachms.
„ Cajuputi	
„ Camphoræ	10–30 min.
„ Chloroformi	10–60 min.
„ Cinnamomi	
„ Juniperi	½–1½ fluid drachms.
„ Lavandulæ	
„ Menthæ Piperitæ	
„ Myristicæ	
„ Rectificatus	
„ Rosmarini	10–60 min.
„ Tenuior	
„ Vini Gallici	

U.S.P. (22).	DOSE.
Spiritus Ætheris	1–3 fluid drachms (3·75–11·25 c.c.).
„ „ Compositus	½–2 fluid drachms (1·0–7·5 c.c.).
„ „ Nitrosi	30–60 min. (1·9–3·75 c.c.).
„ Ammoniæ	10–30 min. (0·6–1·9 c.c.).
„ „ Aromaticus	30–60 min. (1·9–3·75 c.c.).
„ Anisi	1–2 fluid drachms (3·75–7·5 c.c.).
„ Aurantii	1–2 fluid drachms (3·75–7·5 c.c.).
„ Camphoræ	5–60 min. (0·3–3·75 c.c.).
„ Chloroformi	10–60 min. (0·6–3·75 c.c.).
„ Cinnamomi	10–20 min. (0·6–1·25 c.c.).
„ Frumenti (Whisky)	

U.S.P.	DOSE.
Spiritus Gaultheriæ	10–20 min. (0·6–1·25 c.c.).
„ Juniperi	30–60 min. (1·9–3·75 c.c.).
„ „ Compositus	2–4 fluid drachms (7·5–15 c.c.).
„ Lavandulæ	30–60 min. (1·9–3·75 c.c.).
„ Limonis	
„ Menthæ Piperitæ	10–20 min. (0·6–1·25 c.c.).
„ „ Viridis	30–40 min. (1·9–2·5 c.c.).
„ Myrciæ (Bay Rum)	
„ Myristicæ	1 fluid drachm (3·75 c.c.).
„ Odoratus (Cologne Water)	
„ Vini Gallici	

Suppositoria. SUPPOSITORIES. — These are small coni masses for introducing drugs into the rectum (p. 484). They used either to produce a local action on the rectum itself, or the adjoining pelvic organs, such as the uterus or the bladd or to introduce certain drugs into the body when we wish avoid any local action on the stomach.

Thus the morphine suppositories may be used for their gene action in inducing sleep, or for their local action in soothing p or irritation in the rectum or pelvic organs, or to check diarrh The compound lead suppository may be used in diarrhœa for local action on the rectum, and likewise for its general action checking bleeding from the lungs, etc. The same may be s of the mercurial suppository. The others are more intended local action.

The basis of the suppositories is cacao-butter (oil of th broma), excepting in those where, as their name indicates, c soap is used along with glycerine of starch.

B.P. (8).

Suppositoria Acidi Carbolici cum Sapone.
„ „ Tannici.
„ „ „ cum Sapone.
„ Hydrargyri.
„ Iodoformi.
„ Morphinæ.
„ „ cum Sapone.
„ Plumbi Composita.

In the U.S.P. no special suppositories are named, but formula is given for their preparation. The quantity of medicine required, brought to a proper consistency if necessa is to be mixed with a small quantity of oil of theobroma rubbing together, and then sufficient oil of theobroma previou melted and cooled to the temperature of 35° C. (95° F.) is to mixed thoroughly with it, and immediately poured into suita moulds cooled by ice. In the absence of moulds the mass is be divided into parts of a definite weight, which are to be m into a convenient form for a suppository. Unless otherw specified, they should weigh fifteen grains or one gramme.

Succi. JUICES.—These consist of the fresh juices of plant, which are mixed with a sufficient quantity of spirit

vent them from decomposing, except in the case of lemon, lberry, and buckthorn juice, to which no alcohol is added.

B.P. (7).

Succus Belladonnæ.
„ Conii.
„ Hyoscyami.
„ Scoparii.
Succus Taraxaci.
„ Limonis.
„ Mori.

U.S.P.

Succus Limonis.

Syrupi. SYRUPS.—These are strong solutions of sugar; many them contain flavouring or colouring matters, and are used to ke medicines more agreeable to the eye or palate.

In the case of the syrups containing ferrous salts the sugar vents oxidation, and thus preserves the preparation from de- nposition.

B.P. (17).	DOSE.
	All 1 fluid drachm except those specially marked.
Syrupus.	
„ Aurantii	
„ „ Floris	
„ Chloral	½–2 fluid drachms.
„ Ferri Iodidi	½–1 fluid drachm.
„ „ Phosphatis	
„ Hemidesmi	
„ Limonis	
„ Mori	
„ Papaveris	
„ Rhei	1–4 fluid drachms.
„ Rhœados	
„ Rosæ Gallicæ	
„ Scillæ	½–1 fluid drachm.
„ Sennæ	1–4 fluid drachms.
„ Tolutanus	
„ Zingiberis	½–1 fluid drachm.

U.S.P. (33).	DOSE.
Syrupus Acaciæ	
„ Acidi Citrici	
„ „ Hydriodici	1–4 fl. dr. (3·75–15 c.c.).
„ Allii	1 fl. dr. (3·75 c.c.).
„ Altheæ.	1–4 fl. dr. (3·75–15 c.c.).
„ Amygdalæ	
„ Aurantii	
„ „ Florum	1 fl. dr. (3·75 c.c.).
„ Calcii Lactophosphatis	2–4 fl. dr. (7·5–15 c.c.).
„ Calcis	1 fl. dr. (3·75 c.c.).
„ Ferri Bromidi	½–1 fl. dr. (1·9–3·15 c.c.).
„ „ Iodidi	15–30 m. (0·9–1·9 c.c.).
„ „ Quininæ et Strychninæ Phosphatum	1 fl. dr. (3·75 c.c.).
„ Hypophosphatum	1–2 fl. dr. (3·75–7·5 c.c.).
„ „ cum Ferro	1–2 fl. dr. (3·75–7·5 c.c.).
„ Ipecacuanhæ	(Emetic) ½–1 oz. (15–30 c.c.). (Expectorant) 30–60 m. (1·9–3·75 c.c.).
„ Krameriæ	½ fl. oz. (15 c.c.).
„ Lactucarii	2–3 fl. dr. (7·5–11·25 c.c.).
„ Limonis	
„ Picis Liquidæ	1–2 fl. dr. (3·75–7·5 c.c.).
„ Pruni Virginianæ	½ fl. oz. (15 c.c.).

U.S.P.	DOSE.
Syrupus Rhei	1 fl. dr. (3·75 c.c.).
„ „ Aromaticus	1 fl. dr. (3·75 c.c.).
„ Rosæ ..	1 fl. dr. (3·75 c.c.).
„ Rubi	1–2 fl. dr. (3·75–7·5 c.c.).
„ „ Idæi	
„ Sarsaparillæ Compositus	½ fl. oz. (15 c.c.).
„ Scillæ	1 fl. dr. (3·75 c.c.).
„ „ Compositus	(Expectorant) 20–30 m. (1·25–1·9 c
„ Senegæ	1–2 fl. dr. (3·75–7·5 c.c.).
„ Sennæ	1–4 fl. dr. (3·75–15 c.c.).
„ Tolutanus	
„ Zingiberis	1 fl. dr. (3·75 c.c.).

B.P. Tabellæ. Tablets of chocolate each weighing 2½ grai containing an active substance. The only officinal ones are tabl of nitroglycerine, containing $\frac{1}{100}$th grain of pure nitroglycer in each.

B.P.	DOSE.
Tabellæ Nitroglycerini	1 or two tablets.

Tincturæ. TINCTURES.—These are solutions of active pr ciples in spirit. Rectified spirit, or alcohol, is used whene the active principle is more soluble in strong than in dil alcohol, as in the case of alkaloids, such as of veratrum viri resins, such as asafœtida, benzoin, and Indian hemp; oils, su as those of cubebs, lavender, tolu, orange peel, larch bark, a ginger; and other substances, such as chloroform, acetate of ir perchloride of iron, iodine, kino.

Aromatic spirit of ammonia is used in the ammoniated ti ture of guaiac, of valerian, and of opium (B.P. and U.S.P.). the case of guaiac and valerian the active principles have an a character, and so ammonia tends to dissolve them more co pletely. In both of them, however, as well as in ammonia tincture of opium, the ammonia has got a stimulating action its own, which tends to aid the effect of the other substances.

Tinctures of fresh herbs (Tincturæ Herbarum recentiu when not otherwise directed, are, according to the U.S.P., to prepared by macerating fifty parts of the fresh herb bruised crushed in a hundred parts of alcohol for fourteen days, t expressing the liquid, and filtering.

B.P. (72).	DOSE.
	The usual dose is ½–2 fl. dr. unless otherwise mentio
Tinctura Aconiti	1–10 min.
„ Aloes	
„ Arnicæ	
„ Asafœtidæ	½–1 fluid drachm.
„ Aurantii	
„ „ Recentis	
„ Belladonnæ	5–20 min.
„ Benzoini Composita	½–1 fluid drachm.
„ Buchu	
„ Calumbæ	
„ Camphoræ Composita	15 min.–1 fluid drachm.
„ Cannabis Indicæ	5–20 min.

B.P.	DOSE.
Tinctura Cantharidis	5–20 min.
„ Capsici	5–20 min.
„ Cardamomi Composita	
„ Cascarillæ	
„ Catechu	
„ Chiratæ	
„ Chloroformi Composita	10–60 min.
„ „ et Morphinæ	5–10 min.
„ Cimicifugæ	15–60 min.
„ Cinchonæ	
„ „ Composita	
„ Cinnamomi	
„ Cocci	
„ Colchici Seminum	10–30 min.
„ Conii	10–60 min.
„ Croci	
„ Cubebæ	
„ Digitalis	5–30 min.
„ Ergotæ	10–60 min.
„ Ferri Acetatis	5–30 min.
„ „ Perchloridi	5–30 min.
„ Gallæ	
„ Gelsemii	5–20 min.
„ Gentianæ Composita	
„ Guaiaci Ammoniata	½–1 fluid drachm.
„ Hyoscyami	½–1 fluid drachm.
„ Iodi	5–20 min.
„ Jaborandi	½–1 fluid drachm.
„ Jalapæ	
„ Kino	
„ Krameriæ	
„ Laricis	15–30 min.
„ Lavandulæ Composita	
„ Limonis	
„ Lobeliæ	10–30 min.
„ „ Ætherea	10–30 min.
„ Lupuli	
„ Myrrhæ	30–60 min.
„ Nucis Vomicæ	10–30 min.
„ Opii	5–40 min.
„ „ Ammoniata	30–60 min.
„ Podophylli	15–60 min.
„ Pyrethri	
„ Quassiæ	
„ Quininæ	
„ „ Ammoniata	
„ Rhei	(Stomachic) ½–2 fluid drachms.
„ „	(Purgative) 4–8 fluid drachms.
„ Sabinæ	10–60 min.
„ Scillæ	10–30 min.
„ Senegæ	
„ Sennæ	1 fluid drachm to 4 fluid oz.
„ Serpentariæ	
„ Stramonii	10–30 min.
„ Sumbul	10–30 min.
„ Tolutana	10–30 min. or more.
„ Valerianæ	
„ „ Ammoniata	½–1 drachm.
„ Veratri Viridis	5–20 min.
„ Zingiberis	10–60 min.
„ „ Fortior	5–20 min.

Tincture of Litmus, in Appendix, used as a test.

	U.S.P. (73)	DOSE.
Tinctura	Aconiti	1–3 m. (0·06–0·18 c.c.).
,,	Aloes	(As laxative) ½–1 fl. dr.
,,	,,	(As purgative) 2–4 fl. dr.
,,	,, et Myrrhæ	1–2 fl. dr. (3·75–7·5 c.c.).
,,	Arnicæ Florum	10–30 m. (0·6–1·9 c.c.).
,,	,, Radicis	20–30 m. (1·25–1·9 c.c.).
,,	Asafœtidæ	30–60 m. (1·9–3·75 c.c.).
,,	Aurantii Amari	1–2 fl. dr. (3·75–7·5 c.c.).
,,	,, Dulcis	
,,	Belladonnæ	15–30 m. (0·9–1·9 c.c.).
,,	Benzoini	20–30 m. (1·25–1·9 c.c.).
,,	,, Composita	½–2 fl. dr. (1·9–7·5 c.c.).
,,	Bryoniæ	1–2 fl. dr. (3·75–7·5 c.c.).
,,	Calendulæ	
,,	Calumbæ	1–4 fl. dr. (3·75–15 c.c.).
,,	Cannabis Indicæ	30 m. (1·9 c.c.).
,,	Cantharidis	3–10 m. (0·07–0·30 c.c.).
,,	Capsici	30–60 m. (1·9–3·7 c.c.).
,,	Cardamomi	1 fl. dr. (3·75 c.c.).
,,	,, Composita	1–2 fl. dr. (3·75–7·5 c.c.).
,,	Catechu Composita	½–3 fl. dr. (1·9–11·25 c.c.).
,,	Chiratæ	1–2 fl. dr. (3·75–7·5 c.c.).
,,	Cimicifugæ	1–4 fl. dr. (3·75–15 c.c.).
,,	Cinchonæ	1–4 fl. dr. (3·75–15 c.c.).
,,	,, Composita	1–4 fl. dr. (3·75–15 c.c.).
,,	Cinnamomi	1–4 fl. dr. (3·75–15 c.c.).
,,	Colchici	½–2 fl. dr. (1·9–7·5 c.c.).
,,	Conii	30 m. (1·9 c.c.) to be increased.
,,	Croci	1–3 fl. dr. (3·75–11·25 c.c.).
,,	Cubebæ	1–2 fl. dr. (3·75–7·5 c.c.).
,,	Digitalis	10–20 m. (0·6–1·25 c.c.).
,,	Ferri Acetatis	20–60 m. (1·25–3·75 c.c.).
,,	,, Chloridi	10–30 m. (0·6–1·9 c.c.).
,,	Gallæ	1–3 fl. dr. (3·75–11·25 c.c.).
,,	Gelsemii	10–20 m. (0·6–1·25 c.c.).
,,	Gentianæ Composita	1–2 fl. dr. (3·75–7·5 c.c.).
,,	Guaiaci	1 fl. dr. (3·75 c.c.).
,,	,, Ammoniata	1–2 fl. dr. (3·75–7·5 c.c.).
,,	Herbarum Recentium	
,,	Humuli	1–3 fl. dr. (3·75–11·25 c.c.).
,,	Hydrastis	30–60 m. (1·9–3·75 c.c.).
,,	Hyoscyami	60 m. (3·75 c.c.).
,,	Ignatiæ	15–20 m. (0·9–1·25 c.c.).
,,	Iodi	5–15 m. (0·3–0·9 c.c.).
,,	Ipecacuanhæ et Opii	10 m. (0·6 c.c.).
,,	Kino	1–2 fl. dr. (3·75–7·5 c.c.).
,,	Krameriæ	1–2 fl. dr. (3·75–7·5 c.c.).
,,	Lavandulæ Composita	30–60 m. (1·9–3·75 c.c.).
,,	Lobeliæ	30–60 m. (1·9–3·75 c.c.).
,,	Maticæ	1 fl. dr. (3·75 c.c.).
,,	Moschi	½–2 fl. dr. (1·9–7·5 c.c.).
,,	Myrrhæ	15–30 m. (0·9–1·9 c.c.).
,,	Nucis Vomicæ	20 m. (1·25 c.c.).
,,	Opii	11 m. (0·65 c.c.) or 22 drops.
,,	,, Camphorata	1–4 fl. dr. (3·75–15 c.c.).
,,	,, Deodorata	11 m. (0·65 c.c.).
,,	Physostigmatis	20–40 m. (1·25–2·5 c.c.).
,,	Pyrethri	
,,	Quassiæ	1 fl. dr. (3·75 c.c.).
,,	Rhei	1–2 fl. dr. (3·75–7·5 c.c.).
,,	,, Aromatica	½–1 fl. dr. (1·9–3·75 c.c.).
,,	,, Dulcis	2–3 fl. dr. (7·5–11·25 c.c.).
,,	Sanguinariæ	30–60 m. (1·9–3·75 c.c.).

U.S.P.	DOSE.
Tinctura Saponis Viridis	
„ Scillæ	10–20 m. (0·6–1·25 c.c.).
„ Serpentariæ	1–4 fl. dr. (3·75–15 c.c.).
„ Stramonii	20–30 m. (1·25–1·9 c.c.).
„ Sumbul	20–60 m. (1·2–3·7 c.c.).
„ Tolutana	1–2 fl. dr. (3·75–7·5 c.c.).
„ Valerianæ	1–4 fl. dr. (3·75–15 c.c.).
„ „ Ammoniata	30–60 m. (1·9–3·75 c.c.).
„ Vanillæ	
„ Veratri Viridis	3–8 m. (0·18–0·5 c.c.).
„ Zingiberis	8–40 m. (0·5–2·5 c.c.).

U.S.P. Triturationes. TRITURATIONS.—These are intimate xtures of substances with sugar of milk. Each contains 10 cent. of the active substance. A general formula for their paration is given in the U.S.P., although only one is named. ording to this formula 10 parts of the substance and 90 ts of sugar of milk are to be weighed out separately. The stance, reduced to a moderately fine powder if necessary, is ed in a mortar with about its own bulk of sugar of milk, and y are triturated together. Fresh portions of the sugar of k are added from time to time until the whole has been added, l the trituration is continued until the substance is intimately ed with the sugar of milk and finely comminuted.

U.S.P. Trituratio Elaterini.

Trochisci. LOZENGES.—These are small, flat, and hard, so t they can be readily carried about and melt slowly in the uth. They are thus convenient for giving drugs which are nded to act upon the mouth or throat locally, or to be readily ried about and taken at times and in places where more bulky parations would be inconvenient. Thus we have lozenges of orate of potassium, which are useful for soreness of the mouth l tongue; tannic acid and catechu, which are useful in relaxed e-throat and hoarseness; ipecacuanha with morphine, and h opium, which are useful in coughs; bicarbonate of sodium ful before meals in dyspepsia or after meals in acidity; bismuth irritability of the stomach; and reduced iron for debility. muth, morphine, and opium are also useful in diarrhœa. In ny cases it happens that although patients can take potions ore, after, or with their morning and evening meals, they are ble to do so in the middle of the day when they are absent m home and engaged in various avocations. For such cases nges form a useful means of administering medicine.

B.P. (11).	U.S.P. (16)
Trochisci Acidi Tannici.	Trochisci Acidi Tannici.
„ Bismuthi.	„ Ammonii Chloridi.
„ Catechu.	„ Catechu.
„ Ferri Redacti.	„ Cretæ.
„ Ipecacuanhæ.	„ Cubebæ.
„ Morphinæ.	„ Ferri.
„ Morphinæ et Ipecacuanhæ.	„ Glycyrrhizæ et Opii.

B.P.

Trochisci Opii.
" Potassii Chloratis.
" Santonini.
" Sodii Bicarbonatis.

U.S.P.

Trochisci Ipecacuanhæ.
" Krameriæ.
" Magnesiæ.
" Menthæ Piperitæ.
" Morphinæ et Ipecacuan
" Potassii Chloratis.
" Sodii Bicarbonatis.
" " Santoninatis.
" Zingiberis.

Unguenta. OINTMENTS.—These are soft admixtures of me cines with fatty substances for external application. The ba of many of them is lard, either alone or mixed with benzoin order to preserve it from rancidity, or mixed with white wax the form of ointment (unguentum U.S.P.). In the B.P., sim ointment, which consists of white wax and almond oil, forms basis of several ointments.

The semi-solid substances, obtained from American pet leum, form a useful basis for ointments, as they do not beco rancid. They consist of hydrocarbons, mostly of the marsh- series. There are two chief varieties, one softer, having melting point about 40° C. (104° F.), the other 51° C. (or 121° They are obtained by distilling off the lighter and more vola portions from American petroleum. They are known un different names, paraffin (B.P.), petrolatum (U.S.P.), unguent petrolei, and vaseline.

B.P. (43).

Unguentum Acidi Borici.
" " Carbolici.
" " Salicylici.
" Aconitinæ.
" Antimonii Tartarati.
" Atropinæ.
" Belladonnæ.
" Calaminæ.
" Cantharidis.
" Cetacei.
" Chrysarobini.
" Creasoti.
" Elemi.
" Eucalypti.
" Gallæ.
" " cum Opio.
" Glycerini Plumbi Subacetatis.
" Hydrargyri (blue ointment).
" " Ammoniati.
" " Compositum.
" " Iodidi Rubri.
" " Nitratis.
" " " Dilutum.
" " Oxidi Rubri.
" " Subchloridi.
" Iodi.
" Iodoformi.
" Picis Liquidæ.

U.S.P. (25).

Unguentum Acidi Carbolici.
" Acidi Gallici.
" " Tannici.
" Aquæ Rosæ (cold cre
" Belladonnæ.
" Chrysarobini.
" Diachylon.
" Gallæ.
" Hydrargyri.
" " Ammon
" " Nitratis
" " Oxidi F
" " " R
" Iodi.
" Iodoformi.
" Mezerei.
" Picis Liquidæ.
" Plumbi Carbonatis.
" " Iodidi.
" Potassii Iodidi.
" Stramonii.
" Sulphuris.
" " Alkalinu
" Veratrinæ.
" Zinci Oxidi.

B.P.	U.S.P.
guentum Plumbi Acetatis.	
,, ,, Carbonatis.	
,, ,, Iodidi.	
,, Potassæ Sulphuratæ.	
,, Potassii Iodidi.	
,, Resinæ.	
,, Sabinæ.	
,, Simplex.	
,, Staphisagriæ.	
,, Sulphuris.	
,, ,, Iodidi.	
,, Terebinthinæ.	
,, Veratrinæ.	
,, Zinci.	
,, ,, Oleati.	

B.P. Vapores. VAPOURS, INHALATIONS.—These are preparations for applying volatile drugs to the air-passages for the purpose of deodorising, disinfecting, stimulating or soothing. The drug is mixed with water and the vapour inhaled. If the drug be not readily volatile, warm water is used, as in the vapor creasoti, or the water is warmed during inhalation, as in the vapor iodi. In the vapor olei pini sylvestris, light carbonate of magnesium is added, to aid the suspension of the drug in the water.

B.P. (6).	
Vapor Acidi Hydrocyanici	10 to 15 min. of the dilute acid to one drachm of cold water.
,, Chlori	2 oz. in cold water.
,, Coninæ	½ fluid oz. of succus to 1 oz. water and 1 drm. of liq. potassæ.
,, Creasoti	12 min. to 8 oz. of boiling water.
,, Iodi	1 drm. of tincture to the oz. of water.
,, Olei Pini Sylvestris	40 min. of fir-wool oil, 20 grs. magnes. carb.; water to 1 oz : 1 dr. in warm water, 1 pint as inhalation.

The vapours of chlorine, creasote, and iodine may be used for deodorising in cases of ozæna or in cases of chronic bronchitis with offensive sputa.

Antiseptic inhalations, such as those of creasote and iodine, as well as non-officinal inhalations of iodoform and oil of pine, have been recently used in the treatment of phthisis, with the object of destroying the tubercle bacillus. For this purpose a special form of inhaler is used, which fits over the mouth and nose. It contains a sponge which is soaked with the drug to be inhaled either pure or dissolved in spirit or water.

They are probably also useful even in simple catarrh, by destroying organisms which may have found their way into the air-passages and occasion or keep up inflammation. The vapours of hydrocyanic acid and conium are useful for the purpose of allaying irritability, as in spasm of the glottis, violent coughing, or spasmodic asthma.

Vina. WINES.—These are made in the same way as tinctures, sherry or orange wine (B.P.) or stronger white wine (U.S.P.) being employed instead of spirit.

B.P. (11)	DOSE.
Vinum Aloes	1–2 fluid drachms.
„ Antimoniale	5–30 min. as expectorant.
„ „	½–1 fluid oz. as emetic.
„ Aurantii	
„ Colchici	10–30 min.
„ Ferri	1–4 fluid drachms.
„ „ Citratis	1–4 fluid drachms.
„ Ipecacuanhæ	5–40 min. as expectorant.
„ „	1–8 drachms as emetic.
„ Opii	10–40 min.
„ Quininæ	½–1 fluid oz.
„ Rhei	1–2 drachms.
„ Xericum	

U.S.P. (14).	
Vinum Album	
„ Album Fortius	
„ Aloes	Stomachic, 1–2 drachms. / Purgative, ½–1 fluid oz.
„ Antimonii	Expectorant, 10–30 min.
„ Aromaticum	
„ Colchici Radicis	10 min.–1 fluid drachm.
„ „ Seminis	30 min.–2 fluid drachms.
„ Ergotæ	1–4 fluid drachms.
„ Ferri Amarum	2–4 fluid drachms.
„ „ Citratis	1–4 fluid drachms.
„ Ipecacuanhæ	Expectorant, 10–30 min. / Emetic, 1–8 drachms.
„ Opii	15–20 min.
„ Rhei	1–4 fluid drachms.
„ Rubrum	

SECTION III.

INORGANIC MATERIA MEDICA.

CHAPTER XXII.

HYDROGEN, OXYGEN, OZONE, CARBON, SULPHUR, AND THE HALOGENS.

ALTHOUGH the officinal substances included in this chapter differ widely from each other in many respects, yet their relations to oxygen form a connecting link between them. Sulphur belongs to the same chemical group as oxygen. The chief action of charcoal is its power of oxidising organic substances by means of oxygen which it has condensed in its pores. The halogens probably owe their disinfecting properties in great measure to their power of liberating oxygen from water in the presence of organic matter which they thus oxidise and destroy.

HYDROGEN (H; 1). Not officinal.

PREPARATION.—By adding diluted hydrochloric or sulphuric acid to granulated zinc—

$$Zn + 2HCl = ZnCl_2 + H_2.$$

USES.—It is of little or no use as a remedy, and is only used as a test.

It is very frequently employed in testing for arsenic, antimony, and sulphur. When in its nascent condition it has active chemical affinities, and readily unites with these substances, forming sulphuretted, arseniuretted, or antimoniuretted hydrogen.

OXYGEN (O; 16). Not officinal.

PROPERTIES.—Oxygen is a colourless gas without smell, slightly heavier than common air. It forms rather more than a fifth by volume of the atmosphere.

PREPARATION.—By heating chlorate of potassium with peroxide of manganese—

$$2KClO_3 = 2KCl + 3O_2.$$

Peroxide of manganese merely aids the decomposition of the chlorate of potassium, and takes no part in the reaction.

PHYSIOLOGICAL ACTION.—Oxygen applied to the unbroken skin has but little action, but when applied to a wound it increases

the circulation in it, and acts as a stimulant. When inhaled
healthy persons it causes a slight feeling of warmth in the mout
extending downwards over the front of the body. In some peop
it appears to cause nervous symptoms somewhat like those pr
duced by nitrous oxide.

In animals, excess of oxygen produces tetanic symptoms almo
like those of strychnine, and death. This effect is produced
a pressure of three atmospheres, and it is evident that it is d
to the oxygen and not to the simple increase in atmosphe
pressure only, because when ordinary air is used, a pressure
three atmospheres has no such action, and a pressure of twent
five atmospheres is requisite to produce this effect (Bert).

It has been thought by some that when oxygen has been on
breathed it loses something which enables it to support li
The reason of this belief is that animals soon die which are ke
in a confined space, from which the carbonic acid formed duri
respiration is absorbed by lime or baryta, and its place suppli
by fresh oxygen. Professor Seegen, however, has found that t
death in such cases is not due to the removal of anything from t
oxygen, but to actual poisoning by the products of tissue-was
In some experiments he noticed that the air in which the anim
had been confined for a while, although its chemical compositi
was correct, had a disagreeable smell, and the animal after
removal soon died of pneumonia. When the air which the anim
was breathing was extracted from one end of the compartme
made to pass through a red-hot tube, and introduced at the oth
end so that any organic matter formed during respiration w
consumed, the animal could be kept for almost any length
time without injury to its health.

USES.—Oxygen has been applied to the surface in aton
scrofulous, and syphilitic ulcers, and in cases of senile or oth
gangrene. It has more especially been employed in cases of res
ratory disease, such as emphysema, bronchial dilatation, phthi
and gangrene of the lung, in asphyxia from noxious vapours
anæsthetics, and in spasmodic asthma. It seems to be chie
of use in the latter disease. It has been employed also in ca
of difficulty of breathing, of cardiac disease, and of anæmia fr
loss of blood or suppuration. It has been employed also in c
ditions where oxidation seems to be deficient, as in gout and d
betes, where sometimes the sugar disappears from the urine dur
its inhalation. Oxygen has also been used in the treatment
epilepsy and spasm.


It has been strongly recommended by Bert in paralysis occ
ring in divers, due to their sudden ascension from a great de
to the surface. When submerged at a considerable depth
pressure of the air causes both nitrogen and oxygen to be absor
by the blood; when they return to the surface the oxygen ent
into combination, but the nitrogen is set free in the blood-vess

rming minute bubbles, which act as emboli, obstructing the rculation in the nerve-centres and in the lungs, thus producing aralysis and dyspnœa. The nitrogen diffuses as readily into a atmosphere of oxygen as into an absolute vacuum; and therefore when animals, in which such a state has been artificially duced, have been made to breathe pure oxygen, bubbles of trogen disappear from the blood, the circulation is speedily stored to its normal condition, and the paralysis and dyspnœa sappear.

Its inhalation has been recommended in cases of cholera.

OZONE. Not officinal.

When an electric spark is passed through air a peculiar smell noticed; this is due to the formation of ozone. The electricity passing through the air appears to break up the molecules of dinary oxygen (Fig. 164), and the atoms which are thus dis-



a *b*

. 164.—Diagram to illustrate the formation of ozone by electricity. *a* represents oxygen, through which a spark is passing; *b* after it has passed. The double rings are intended to represent molecules of oxygen, each containing two atoms. As the electric spark passes through the oxygen it breaks up the first molecule, carrying one atom on to join the second molecule of oxygen, and form one of ozone. The atom which is left joins another molecule of oxygen, and also forms ozone. (After Lockyer.)

ciated join together so as to form ozone. It is also formed by e slow oxidation of phosphorus, and is formed also by protoasm (p. 69). Two atoms are present in a molecule of oxygen d three in that of ozone. When electricity is passed through quantity of oxygen, contained in a tube over mercury, so as to nvert a portion of it into ozone, it becomes condensed in bulk d acquires much greater chemical activity. On warming it gain to about 300° C. the molecules of ozone become again disciated, ordinary oxygen is formed, the gas then returns to its iginal bulk, and it loses its active properties. Ozone has a ost powerful oxidising property, attacking metals and forming ides, and destroying organic substances, such as paper and outchouc. It has a curious action upon albumen, already scribed (p. 58), and decomposes blood. As might be expected,

it is exceedingly poisonous to low organisms, and is fatal also the higher animals.

Its effect appears to be due in a great measure to its havi such a powerful irritant and even destructive effect on the alb minous tissues of the respiratory passages, that it causes refl depression of the heart and interferes with the ordinary respi tion in the lungs. It thus diminishes instead of increasing o dation. In animals it causes sometimes quickness, and som times slowness of the respiration (*vide* p. 241), and produces citement followed by exhaustion and sometimes convulsions.

When it is present only in small quantity in air, it may inhaled without any disagreeable effects, and is, according Binz, a decided soporific.

USES.—It has been recommended in cases similar to tho already mentioned under oxygen ; and also in infectious diseas and in diphtheria, where it is likely to be useful by destroyi low organisms, which produce the disease.

PEROXIDE OF HYDROGEN (H_2O_2; 34). Not officina

PROPERTIES.—When the watery solution thus obtained evaporated it forms a transparent oily liquid ; but it is genera employed in the form of a 3 per cent. solution (10 to 15 volum in water or in ether. The ethereal solution is commonly kno by the name of ozonic ether ; it is generally more stable th the aqueous solution, which, especially if kept in a badly st pered bottle, soon decomposes into water and oxygen.

PREPARATION.—It is generally prepared by treating barium di-oxide w dilute sulphuric acid ($BaO_2 + H_2SO_4 = H_2O_2 + BaSO_4$) and filtering off aqueous solution from the sulphate of barium which is precipitated.

ACTION AND USES.—Peroxide of hydrogen has a power oxidising effect upon organic substances, readily giving off atom of oxygen in much the same way as ozone. It has the fore been used for similar purposes to ozone. It destroys bacte and is a powerful antiseptic.[1] When mixed with the secret from a chancre it destroys its infective power ; and it has b employed as a local dressing for chancres, and also as an ap cation for diphtheritic sore-throat. Curiously enough, althou when mixed with blood or with albumen it becomes decompo almost immediately, it appears to be tolerably stable in the bo and is said to have been found in the urine after it has been ta by the mouth. By long-continued action upon egg-albumin is said to produce hemi-albumose and peptone.[2] Its inter administration has been recommended in rheumatism, scrof diabetes, and cardiac disease.

[1] Professor Dewar, Cambridge, unpublished experiments.

[2] Chandelon, Beitrag zum Studium der Peptonisation, *Ber. d. Deutsch. Ch Ges.* XVII. p. 2143 (1885).

CARBON (C; 12).

This element is employed in medicine in the form of animal d vegetable charcoal.

Carbo Ligni, B.P. and U.S.P. WOOD CHARCOAL.—Wood rred by exposure to a red heat without access of air, B.P. arcoal prepared from soft wood, U.S.P.

CHARACTERS.—In black, brittle, porous masses, without taste smell, very light, and retaining the shape and texture of the od from which it was obtained. When pulverised it forms a e black powder.

PREPARATION.—It is prepared either by burning the wood under turf, or retorts, so that the hydrogen and oxygen are driven off and charcoal alone ains. If too much air be allowed to have access, the charcoal itself be- es burnt, and too large a proportion of ash comes to be present.

IMPURITIES.—Too much ash.

TESTS.—When burned at a high temperature with free access of air it es not more than two per cent. of ash.

DOSE.—20–60 grains.

OFFICINAL PREPARATION.

B.P.	U.S.P.
Cataplasma Carbonis.	None.

B.P. Cataplasma Carbonis. CHARCOAL POULTICE.—Powdered charcoal 1; ad 4; linseed-meal 3; boiling water 20. Mix the water, bread, and linseed- al, then add half the charcoal and sprinkle the remainder on the surface. By ply sprinkling a part of the charcoal on the surface of the poultice it is not ted, and its disinfectant power not destroyed.

ACTION.—Charcoal has the power of absorbing gases and of ndensing them within its pores. Amongst others it absorbs ygen readily. The oxygen thus condensed has an oxidising ion akin to that of ozone, and the charcoal parts with it dily when brought into contact with oxidisable substances, ether these substances be in solution or in the form of gas, t especially the latter. Thus it oxidises and decomposes lphuretted hydrogen very readily, and also quickly oxidises d destroys decomposing organic substances. It thus acts as eodoriser and disinfectant. It only possesses this power, how- er, when it is dry, and loses it when it is wet. For this reason e whole of it is not mixed with the poultice in the cataplasma rbonis, a part of it being merely sprinkled on the surface. Its idising power is destroyed completely only when the charcoal thoroughly saturated with water, and this occurs with diffi- lty even when it is thrown into water. Consequently its idising power may still be exerted in fluids to which it has been shly added.

USES.—It is employed as a deodoriser and disinfectant in aps through which sewer gases may pass, and in a respirator

for persons exposed to sewer gas or other noxious emanation
As a poultice it is employed for fœtid and phagedænic ulcers a
gangrene. It forms a useful tooth-powder, cleaning the tee
rapidly, but it is much more apt to scratch the enamel than
tooth-powder of chalk. When taken into the stomach it reliev
flatulent distension and acidity in the stomach and intestine
It has thus been used in acute and chronic dyspepsia, gastrodyn
and even cancer of the stomach; in constipation, flatulent d
tension of the colon, diarrhœa, dysentery, cancer of the rectu
it is recommended in drachm-doses by Sir William Jenner
correct flatulence and fœtid stools in typhoid fever. It has be
supposed to relieve flatulence by absorbing the gases in t
stomach and intestines, but as it will become wet by the juic
of the intestinal canal after it is swallowed, it is much mo
probable that it acts mechanically, by removing mucus, or
stimulating the circulation and peristaltic movements in t
walls of the stomach and intestine. This is rendered all t
more probable by the fact that in some cases where it is use
the patient is likewise benefited by beginning each meal wi
solid food, and abstaining from liquids until the meal is w
over, so that the stomach may receive a mechanical stimul
from the food, which would be prevented by the ingestion of mu
liquid at the beginning of the meal. In large doses it acts as
mild purgative. It has also been used in diabetes and in int
mittent fevers.

ADMINISTRATION.—It is either used in the form of powder,
made up into biscuits or lozenges.

Carbo Animalis, B.P. and U.S.P. ANIMAL CHARCOAL.
Bone black. Animal charcoal prepared from bone, U.S.P. T
residue of bones which have been exposed to a red heat witho
the access of air. Consists principally of carbon and phospha
and carbonate of calcium, B.P.

Carbo Animalis Purificatus, B.P. and U.S.P. PURIFI
ANIMAL CHARCOAL.

CHARACTERS.—It is a black powder without taste or sme
It absorbs colouring matters, and tincture of litmus diluted wi
20 times its bulk of water agitated with it and thrown upon
filter passes through colourless. It is insoluble in all reagent

PREPARATION.—By dissolving out the earthy matter by hydrochloric a
washing and drying.

IMPURITIES.—Too much ash.

TEST.—When burnt at a high temperature with a little red oxide
mercury and free access of air, it leaves only a slight residue.

DOSE.—20–60 grains.

USES.—From its power of absorbing colouring matte
animal charcoal is used in the preparation of organic alkaloi
for the purpose of decolorising them. It not only carries do

louring matters with it, but alkaloids as well, and therefore a nsiderable loss is occasioned in the process of bleaching. Ad- ntage has been taken of this power to use animal charcoal as antidote in poisoning by opium, aconite, nux vomica, &c. The kaloid is removed from solution by the animal charcoal and ained by it with considerable pertinacity. It would, however, gradually dissolved out if allowed to remain too long in the mach, and therefore the stomach-pump, or emetics, must be d in addition. As an antidote it is used in doses of a table- onful frequently repeated.

SULPHUR (S; 32).

Sulphur is found native in volcanic districts, and occurs in mbination with metals as sulphites in various ores, especially iron and copper pyrites.

Sulphur Sublimatum, B.P. and U.S.P. SUBLIMED SULPHUR, OWERS OF SULPHUR.

CHARACTERS.—A fine, slightly gritty, citron-yellow or greenish- low powder, without taste or smell unless heated. It may metimes have a slight characteristic odour, a faintly acid taste d an acid reaction from slight oxidation occurring with the mation of small quantities of sulphurous acid.

SOLUBILITY.—It is insoluble in water or alcohol, slightly soluble in oils fats, and completely soluble in carbon disulphide.

REACTION.—When ignited it burns with a blue flame, forming sulphurous gas, and leaving no residue, or only a trace.

PREPARATION.—By sublimation from crude or rough sulphur. Native hur is usually mixed with earthy impurities. When heated the sulphur tilises. If the vapour is condensed in a large room it falls in a fine der. If condensed in water it forms masses, which, when melted and into moulds form roll sulphur, but this is not officinal. Ores containing hur are decomposed by heat, and part of the sulphur they contain sub- es, and may be condensed in the same way as native sulphur.

IMPURITIES.—Ores are apt to contain arsenic, and when this is the case hide of arsenic, being volatile, sublimes along with the sulphur and lers it impure. During sublimation the sulphur may undergo oxidation, thus sulphurous or sulphuric acid may be present in it as impurities.

TESTS.—*Vide* SULPHUR LOTUM.

OFFICINAL PREPARATIONS.

B.P.	DOSE.	U.S.P.
onfectio Sulphuris, as laxative	60–120 gr.	Sulphur Lotum.
„ „ as alterative	5–20 gr.	„ Præcipitatum.
mplastrum Ammoniaci cum Hydrargyro.		
„ **Hydrargyri.**		
ulvis Glycyrrhizæ Compositus (1 in 12)	30 to 60 gr.	
nguentum Sulphuris.		Unguentum Sulphuris.

l in preparing:
ntimonium Sulphuratum.
otassa Sulphurata.
lphuris Iodidum.
lphur Præcipitatum.

B.P. Confectio Sulphuris. CONFECTION OF SULPHUR.—Sulphur 4; acid tartrate of potassium 1; syrup of orange-peel 4; tragacanth in powder $\frac{1}{24}$ part. The acid tartrate of potassium is added for the purpose of increasing the secretion from the intestine, while the sulphur stimulates peristaltic action.

Unguentum Sulphuris. SULPHUR OINTMENT.—Sulphur mixed with benzoated lard, 1 part to 4, B.P.; 30 to 70, U.S.P. The U.S.P. ointment is nearly twice as strong as the B.P.

USES.—See pp. 546, 547.

In **skin diseases** sulphur is used both as an **antiparasitic** and as a **stimulant** in chronic and passive congestion. It is used as an ointment in scabies, and in tinea tonsurans, in several cases of which an ointment of sulphur and tar with soap may be used, four drachms of sulphur and oil of cade to one ounce each of green soap and lard. In the true prurigo of Hebra it may be employed in Vleminckx's solution, which is made according to the following formula :—

℞ Calcis .....ʒss.
Sulphuris Sublimati.....ʒj.
Aquæ .....ʒx.
Evaporate to ʒvj., then filter.

The solution must be rubbed into the skin while the patient is in a bath at the temperature of the body (98° F.). Obstinate cases of psoriasis may be similarly treated. Unguentum sulphuris is useful in acne, sycosis, seborrhœa, and chronic indurated eczema. In lupus erythematosus and lupus attended with congested condition of the scalp, a paste of alcohol and sulphur is recommended.

U.S.P. Sulphur Lotum. WASHED SULPHUR.

CHARACTERS AND IMPURITIES.—Those of sulphur sublimatum.

PREPARATION.—By digesting sulphur with dilute ammonia, thorough washing, drying at a gentle heat, and passing through a No. 30 sieve. this process the ammonia not only neutralises any sulphurous or sulphuric acid, but dissolves out and removes sulphide of arsenic which may be present in the sulphur, and which is soluble in ammonia.

TESTS.—Water agitated with it should not redden blue litmus paper (absence of free acid). If washed sulphur be digested with two parts of water of ammonia, and the mixture filtered, the filtrate, on being supersaturated with hydrochloric acid, should remain unaltered (absence of arsenic sulphide), nor should a precipitate make its appearance on passing hydrosulphuric acid through the filtrate (absence of arsenious acid).

OFFICINAL PREPARATIONS.

U.S.P.

Pulvis Glycyrrhizæ Compositus. (1 in 12½.)
Sulphuris Iodidum.
Unguentum Sulphuris Alkalinum.

U.S.P. Unguentum Sulphuris Alkalinum. ALKALINE SULPHUR OINTMENT. Sulphur 20; carbonate of potassium 10; water 5; benzoated lard 65.

Sulphur Præcipitatum, B.P. and U.S.P. PRECIPITATED SULPHUR, LAC SULPHURIS, MILK OF SULPHUR.

CHARACTERS.—Being in a finer state of division than sublimed lphur, it looks almost white, with only a slight tinge of yellow. herwise its characters are the same.

PREPARATION.—By boiling sulphur with slaked lime and water. Calcium lphide and calcium hyposulphite are thus formed.

$$3CaO + 6S_2 = 2CaS_3 + CaS_2O_3.$$

ese dissolve in water, and are separated from any residual lime by filtra- n. To the filtrate, in an open space or under a chimney, hydrochloric id is then added, which decomposes these substances with the evolution of lphuretted hydrogen and sulphurous acid gases, and throws down sulphur the form of an exceedingly fine powder, which is washed until the washings e tasteless (U.S.P.) and have no acid reaction and cease to give a preci- ate with oxalic acid (B.P.), showing that both acid and lime have been moved.

IMPURITIES.—There is a great temptation to fraudulent manufacturers to e sulphuric acid instead of hydrochloric acid. It is not only cheaper but it lds a large product, consisting to a great extent of sulphate of calcium, ich is precipitated along with the sulphur instead of remaining in solution e the calcium chloride which is formed when hydrochloric acid is em- yed.

With Hydrochloric acid, $2CaS_3 + 2CaS_2O_3 + 6HCl = 3S_2 + 2H_2O + H_2S + 2SO_2 + 3CaCl_2$.

With Sulphuric acid, $2CaS_3 + 2CaS_2O_3 + 3H_2SO_4 = 3S_2 + 2H_2O + H_2S + 2SO_2 + 3CaSO_4$.

sides this there are the other impurities which may be present in the sub- ed sulphur employed in the process.

TESTS.—It should be completely volatilised by heat and leave no residue sulphate behind. Under the microscope it should exhibit only minute bules of sulphur and no crystals of sulphate. The absence of the im- rities contained in sublimed sulphur is ascertained by the tests already en.

DOSE.—Of precipitated sulphur, as alterative 10 grs., as xative 30–60 grs.

Sulphuretted Hydrogen. HYDROGEN SULPHIDE. (H_2S; 34.) colourless gas, with a smell of rotten eggs. Used only as a st.

PROPERTIES.—It precipitates most metals as sulphides from id solutions, the precipitate with arsenic being yellow; anti- ony, orange; cadmium, yellow; copper, lead, mercury, and ver, black; bismuth, brown; gold and platinum, brownish ack.

PREPARATION.—By pouring diluted sulphuric acid on sulphide of iron. passing the gas into cold water a solution is obtained.

General Action of Sulphuretted Hydrogen.—As sulphu- tted hydrogen is formed in small quantities from sulphur when e latter is used in various ways, it may be more convenient to ke its action before that of sulphur. It is very destructive to ant life even in very minute quantities. There is a curious

difference between the action of sulphuretted hydrogen and th of sulphurous acid on plants. The latter seems to act as i irritant, causing the leaves to crumple up and fall off, but ev when the leaves are destroyed by sulphurous acid the plant m again recover. Sulphuretted hydrogen causes the leaves simp to become flaccid and droop, but when this has once taken pla the plant does not recover.

In animals it destroys the functions of all tissues, and consequence has two actions which are well marked, (1) deco posing the **blood** and thus producing symptoms of asphyxia, a (2) paralysing the **nervous system** and **muscles**. It is a **sorbed** by the skin, by the lungs, mucous membrane of t alimentary canal, and subcutaneous cellular tissue, and m produce symptoms of poisoning through any of these channe In **frogs**, which are less affected than mammals by interferer with the respiration, the symptoms produced by sulphuret hydrogen are those of paralysis of voluntary motion and ref action, preceded by a stage of restlessness. In **mammals** t symptoms are those of asphyxia; muscular tremors occur, a are succeeded by asphyxial convulsions and death. Most ca of poisoning by sulphuretted hydrogen in man occur from halation of the gas which is often found in large quantities cesspools.

One case has been recorded where symptoms of poisoni occurred from the excessive formation of the gas in the int tinal canal, and subsequent absorption into the blood. Cases poisoning are best treated by artificial respiration.

Special Action.—Even in minute quantities it destroys catalytic action of many substances on peroxide of hydrog In this respect, as well as in many of the symptoms it produc it resembles hydrocyanic acid.

On the **blood.** It first reduces and then decomposes hæ globin. Both the blood and the muscles of frogs poisoned b exhibit a greenish colour. As death occurs in mammals be the blood has become so extensively changed, it simply exhi the characters of asphyxial blood. It induces rigor mortis rap in the **muscular substance** both of the voluntary muscles of the frog's heart.

Action of Sulphur.—Sulphur, when brought into con with living **protoplasm**, enters into combination and fo sulphuretted hydrogen or sulphurous acid. When sulphu sprinkled over actively-growing fungi, like those which cause vine-disease, these gases are formed and the fungi destroyed.

Sulphur has little or no action on the **skin**, exceptin mechanical one. It is a **laxative** (p. 394). When taken into **intestinal canal**, a considerable part of it again passes out changed; a little of it, however, appears to be converted sulphides and into sulphuretted hydrogen. The latter is excre

the breath, and may give to it the peculiar disagreeable smell rotten eggs. It is also excreted by the skin, so as to blacken silver articles which may be worn about the person. The phides give rise to increased peristaltic action of the bowels, hat the motions become more frequent and softer; colicky ns are sometimes produced. The sulphides, after absorpn into the blood, are excreted in the urine, chiefly as sultes.

USES.—For its use in skin disease, *vide* p. 544. It has been lied by insufflation to the throat in diphtheria, in order to troy the organisms present in the pharynx, in the same way in the vine-disease. I have seen one case do very well under treatment; but its general efficacy is by no means certain. rnally it is employed as a mild laxative in cases of constipa- where active purgatives are inadmissible, as in pregnancy, æmorrhoids, fissure of the anus, and stricture or prolapsus he rectum. It has been used also in cases of lead-poisoning, revent the reabsorption of the lead from the intestine.

It has been found useful in cases of sexual irritation arising n hæmorrhoidal congestion (p. 451), and also in the nervous tement and other disturbances accompanying the menose.

It exerts a beneficial action on the tissues in chronic rheuism and gout, and is especially useful in the form of sulrous waters. During its elimination by the lungs it is posed to have a beneficial action on them, and it is consently used in chronic bronchitis.

HALOGEN ELEMENTS.

Fluorine (Fl; 19 or 19·1). **Chlorine** (Cl; 35·5 or 35·4). **Bromine** (Br; 80 or 79·75). **Iodine** (I; 127 or 126·53).

These substances form a series in which the atomic weights nearly in the relation of 1, 2, 4, and 7 (*vide* also p. 16). They distinguished by the activity of their chemical affinities and number of compounds they form.

GENERAL SOURCE.—The name halogen (from ἅλς, the sea) has n given to the group, because its most important members, rine, bromine, and iodine, are derived from the sea; chlorine g obtained from sea-salt, bromine from sea-water, iodine n sea-weed.

GENERAL CHARACTERS.—They are all very volatile. At nary temperatures, chlorine is a gas, bromine a liquid, and ne a solid, but both bromine and iodine give off vapour freely. account of their active chemical affinities they unite directly metals, as is seen in the officinal processes for the prepara- of iodide of iron and green iodide of mercury. They have

all a great affinity for hydrogen, and are therefore powerful c composers of organic matter, destroying organic colours a disagreeable emanations of organic origin, as well as decomp ing sulphuretted hydrogen ($H_2S + Cl_2 = 2HCl + S_2$) and ammo which occur amongst the products of decomposition of orga matter. They are therefore used as deodorisers and disinfectan Chlorine is used for bleaching, but bromine and iodine fo coloured compounds with many organic substances, and so not used for this purpose.

Probably the bleaching power of chlorine is not due to decomposing organic colours by removing hydrogen from the but rather to its decomposing water by removing the hydro from it, and thus setting free nascent oxygen, which is the dir destroyer of organic matters. The reason for this supposition that chlorine does not act upon colouring matters when they dry, but only when moist.

Mode of Preparation.—Chlorine, bromine, and iodine all prepared by expelling them from their compounds with alkaline metals by means of sulphuric acid and mangan dioxide.

Chlorine is prepared by putting sodium chloride, sulphu acid and manganese dioxide into a retort, applying heat and c lecting the chlorine gas in a receiver, by displacement or o warm water, or passing it into cold water which dissolves freely, forming liquor chlori (B.P.) or aqua chlori (U.S.P.).

Bromine is prepared in a similar manner from the bromi of sodium and magnesium contained in the bittern or moth liquor left after the salt has crystallised out of sea-water or of the brine obtained in salt mines. In order to obtain the b mine pure, the bittern is often not treated directly with sulphu acid and manganese dioxide. Instead of this the bromine is f separated by passing chlorine through the liquid, which is t shaken up with ether. The chlorine decomposes the magnesi bromide and the ether dissolves the bromine thus set free. bromine is then converted again by potash into bromide, fr which bromine is obtained by means of manganese dioxide acid.

Iodine is prepared in a similar manner to chlorine from iodides of sodium and magnesium contained in sea-weed. iodides are obtained from the weed by calcining it in a retort by burning it, when the ashes in which they are contained f a hard mass called kelp. This is treated with successive port of water until the soluble salts are all dissolved out (lixiviati The solution is filtered, and evaporated to a small bulk, w the less soluble salts, as the sulphates, &c., crystallise out. mother-liquor containing the iodides of sodium and magnes is then treated with manganese dioxide and sulphuric acid, the iodine distils over.

The reactions which occur in the preparations just described —

Chlorine $2NaCl + 2H_2SO_4 + MnO_2 = Cl_2 + Na_2SO_4 + MnSO_4 + 2H_2O.$

Bromine $2NaBr + 2H_2SO_4 + MnO_2 = Br_2 + Na_2SO_4 + MnSO_4 + 2H_2O.$
$MgBr_2 + 2H_2SO_4 + MnO_2 = Br_2 + MgSO_4 + MnSO_4 + 2H_2O.$

Iodine $2NaI + 2H_2SO_4 + MnO_2 = I_2 + Na_2SO_4 + MnSO_4 + 2H_2O.$
$MgI_2 + 2H_2SO_4 + MnO_2 = I_2 + MgSO_4 + MnSO_4 + 2H_2O.$

General Action.—As chlorine, bromine, and iodine decom- e organic compounds having a disagreeable odour, they have n supposed to have a similar action upon the germs of infec- ns diseases. Chlorine, and sometimes iodine, are therefore d as **deodorisers** and **disinfectants** in sick rooms. Bromine not well be used on account of its abominable smell.

The objections to chlorine or the vapour of iodine as disinfec- ts are that we do not at all know that they have any disin- ting power in the dilute state, in which only they can be used a sick room. When applied to the **skin** or mucous membranes y cause a greater or less amount of irritation or inflamma- n, according to the length of time during which they act, and greater or less degree of concentration in which they are lied. They probably do not enter the blood in the free state, combine with bases or with albuminous substances at the ce of application, and are **absorbed** as chlorides, bromides, or ides, or else as albuminous compounds. According to Binz, e chlorine, bromine, and iodine, and all their readily decom- able compounds, have a narcotic action, and paralyse nervous tres in the brain by a direct action on the nervous structures mselves. He considers that they cause death by paralysis of respiratory centre, and not by paralysis of the heart.

CHLORINE. Cl; 35·5.

A greenish-yellow gas with a suffocating odour. Its prepara- n and general action have already been described (p. 548).

Action.—When applied for a long time to the **skin**, as in rsons who have to work in an atmosphere containing it, it ses itching, reddening, and inflammation. When applied to the re sensitive **mucous membranes** of the respiratory passages, cts as a stimulant or irritant. In a concentrated form it may se death from spasm of the glottis, or intense bronchitis. In more dilute form it is used as a stimulant, deodoriser, and infectant. The manner of employing it is to put a saucer taining salt, binoxide of manganese, and sulphuric acid on a lf or high piece of furniture in the sick room, and thus allow chlorine vapour, which is heavier than air, to diffuse itself ough the apartment. When placed on the floor it is of little e.

Liquor Chlori, B.P.; Aqua Chlori, U.S.P. CHLORI WATER.—An aqueous solution of chlorine containing at least (per cent. of the gas U.S.P., or 2·66 grains in 1 fluid ounce about 0·6 per cent. B.P.

CHARACTERS.—A greenish-yellow clear liquid with a stro smell and taste of chlorine. It instantly decolorises dilute so tions of litmus and indigo.

PREPARATION.—By passing washed chlorine into water (p. 548). T chlorine is directed by the B. and U.S.P. to be prepared from hydrochlo acid and manganese dioxide, instead of from sodium chloride. $4HCl + Mn$ $= Cl_2 + MnCl_2 + 2H_2O$.

IMPURITIES.—The chief is too little chlorine. When exposed to light i apt to be decomposed, the chlorine combining with the hydrogen of the wa and forming hydrochloric acid. The chlorine water thus loses strength, an also becomes weaker by the chlorine escaping when the bottle is imperfec stoppered or frequently opened. A solution of chlorinated soda or lime may sometimes substituted for chlorine water.

TESTS.—The amount of chlorine is not tested directly but indirectly, estimating the amount of iodine which a definite quantity of chlorine wa liberates from iodide of potassium. In this process, chlorine water (grains or 1 fluid ounce B.P., or 35·4 gm. U.S.P.) is mixed with iodide of pot sium (20 grains B.P., 0·9 gm. U.S.P.) and water (1 fluid ounce B.P., 20 g U.S.P.). The amount of iodine which is set free by the chlorine ($2KI +$ $= 2KCl + I_2$) gives a red colour to the solution, and corresponds in quantity the chlorine contained in the water. The red solution requires for its colorisation 750 grain-measures B.P., or 40 cc. U.S.P. of the volumetric s tion of hyposulphite of sodium. The reaction which occurs is :—

Iodine.		Sodium Hyposulphite.		Sodium Iodide.		Sodium Tetrathionate.		Water.
I_2	+	$2Na_2H_2S_2O_4$	=	$2NaI$	+	$Na_2S_4O_6$	+	$2H_2O$.

USES.—Chlorine is used in solution as a lotion to foul-smell ulcers or cancer; as an application to relieve itching in chro skin diseases; and as a gargle or wash to the mouth in affecti of the mouth, throat, and tonsils, especially where they accompanied by fœtor, as in mercurial ptyalism and ulcerat of the tonsils. It is sometimes given internally in cases of blo poisoning. As an inhalation it has been used in cases of phthi it is said with good effect. It is also employed as a stimul and deodoriser in cases of chronic bronchitis with fœtid spu (*Vide* Vapor Chlori, p. 551.)

The aqueous solution is so unstable and liable to lose strength, that compounds of chlorine from which it can be ea evolved are more convenient for general use. The chief of th are the following compounds with lime and with soda.

Calx Chlorinata, B.P.; Calx Chlorata, U.S.P. CHLORIN LIME.—A product obtained by exposing slaked lime to the act of chlorine gas so long as the latter is absorbed. It posses bleaching and disinfecting properties. It may be regarded consisting, chiefly, of a compound of hypochlorite and chlorid calcium ($CaCl_2O_2, CaCl_2$) or as a direct compound of chlorine

ne, B.P. A compound resulting from the action of chlorine on hydrate of calcium, and containing at least 25 per cent. of ailable chlorine, U.S.P.

Characters.—A greyish-white powder having the odour of lorine and an acrid taste; it absorbs carbonic acid and water nen exposed to the air, and at the same time gives off lorine; it is only partly soluble in water. The solution is kaline, and possesses bleaching properties (e.g. it bleaches lphate of indigo).

It is readily decomposed by acids, even by carbonic acid, and us when exposed to the air chlorine is given off slowly. The ldition of a stronger acid causes it to be evolved rapidly. Its robable constitution is $Ca\begin{cases} Cl. \\ OCl. \end{cases}$ This is decomposed by water to a mixture of calcium chloride and hypochlorite, and as is usually moist it may be regarded as usually consisting of mixture of these substances. On the addition of sulphuric id, hypochlorous and hydrochloric acids are set free, which acting on one another yield free chlorine. $HClO + HCl = {}_2 + H_2O$.

Reaction.—The addition of oxalic acid causes the rapid and copious olution of chlorine and the deposition of oxalate of calcium.

Impurities.—Imperfect saturation with chlorine. It is tested volumetrilly in a similar way to liquor chlori, the chlorine being set free from it by e addition of hydrochloric acid. The chlorine thus liberated should amount 30 per cent. B.P., 25 per cent. U.S.P.

Officinal Preparations.

B.P.	U.S.P.
Liquor Calcis Chlorinatæ.	Liquor Calcis Chloratæ.
Vapor Chlori (p. 551).	

Chlorinated lime is used in the preparation of Chloroform.

Liquor Calcis Chlorinatæ. Solution of Chlorinated Lime.—It is a solun of 1 lb. to the gallon of water, and when tested volumetrically it should conin 13 grains of available chlorine in 1 fluid oz.

Liquor Sodæ Chlorinatæ, B.P.; Liquor Sodæ Chloratæ, U.S.P. Solution of Chlorinated Soda.—(Labarraque's disnfecting fluid.)

Characters.—A colourless alkaline liquid, with astringent aste and feeble odour of chlorine.

Preparation.—By passing chlorine into a solution of sodium carbonate .P., or by decomposing chlorinated lime by sodium carbonate U.S.P.

Tests.—It behaves like a solution of chlorinated lime, but is not prepitated by oxalic acid nor oxalate of ammonium. (Distinction from and bsence of solution of chlorinated lime.)

Dose.—10 to 20 minims.

Officinal Preparation, B.P.

Cataplasma Sodæ Chlorinatæ.

Cataplasma Sodæ Chlorinatæ.—Linseed meal 2; solution of chlorinated oda 1; boiling water 4.

Uses.—Chlorinated lime is chiefly employed as a disinfectan and a deodoriser. In sick rooms some of it is put in saucer and, according to the rapidity with which the evolution chlorine is desired, either acid is added to it, or it is simpl moistened and exposed to the air, when it is slowly decompose by the carbonic acid. It is employed also for disinfectin typhoid stools, water-closets, and sewers. For this purpose is used either in powder or solution. A solution is used t disinfect the sheets and bedding of patients suffering fro infectious diseases.

Solutions of chlorinated lime or of chlorinated soda may b employed instead of chlorine water or permanganate of potassiu for washing the hands after dissecting or performing *post-morte* examinations. They are applied externally to wounds and ulce of all sorts which have a fœtid discharge and a tendency t slough. Not only do they remove the fœtor, but they often in duce a healthy action in the tissues themselves; and instead the ulceration or sloughing extending farther and farther, th slough is thrown off and leaves behind it a healthy, healin surface. As the removal of sloughs is aided by heat, we have i the B.P. the poultice of chlorinated soda.

Like chlorine they are destructive to plant life, and they ar therefore useful in skin-diseases depending on the presence parasitic fungi, such as ringworm of the scalp, and in scabie which is due to the presence of a parasitic acarus. As they hav a stimulant action on the skin, they are sometimes useful i eczema and prurigo.

They are employed as gargles, or washes to the mouth whe fœtid ulcers occur in these parts, as in ptyalism or in scarlatina as an injection into the nose they have been used to lessen th discharge and to remove the fœtor in ozæna, a disease in whic the discharge from the nostrils is sometimes so disgusting as t be almost unendurable to the patient himself as well as to thos around him. They are likewise useful in fœtid discharges fro the vagina, such as occur when the uterus is the seat of malig nant disease.

Internally they have been employed in so-called putrid fever when it was imagined there was a special tendency to decom position in the blood, such as typhus and malignant scarlatin They have been given more especially in these diseases whe there was great prostration of strength, with fœtid evacuatio and a dry and furred tongue.

BROMUM. Br; 80.

Bromine, B. and U.S.P. A liquid non-metallic eleme obtained from sea-water and from some saline springs.

Characters.—A dark brownish-red, very volatile liquid, wit

strong, disagreeable odour. The solution renders cold starch-ter yellow.

PREPARATION.—*Vide* p. 548.

IMPURITY.—Iodine.

TEST.—When agitated with sufficient soda to render the fluid very ghtly alkaline, it forms a colourless liquid, which, if coloured by a further lition of a little bromine, does not become blue on the subsequent addition a cold solution of starch. B.P. (absence of iodine).

If an aqueous solution of bromine be poured upon reduced iron and ken with the latter until it has become nearly colourless, then filtered, xed with gelatinised starch, and a few drops of bromine solution be now efully poured on the top, not more than a very faint blue zone should pear at the line of contact of the two liquids (limit of iodine), U.S.P.

USES.—Bromine, although a powerful **disinfectant**, is not ch used, on account of its exceedingly fœtid and disagreeable ell. It is a powerful irritant, and when inhaled without fficient dilution with air will produce pneumonia. Taken in all doses, for a length of time, it has produced mental de-ession, drowsiness, and stupidity. It is sometimes used as a ustic to the os uteri, and from its deodorising and antiseptic tion it is especially useful where there is a fœtid discharge. It used internally in the form of its potassium, sodium, ammo-m, calcium, and zinc salts, and of hydrobromic acid, which not possess its powerfully irritant local action.

Potassii Bromidum, B. and U.S.P. BROMIDE OF POTAS-M. (KBr ; 118·75.)

CHARACTERS.—In colourless cubical crystals, with no odour, t a pungent saline taste.

PREPARATION.—*Vide* p. 605.

SOLUBILITY.—It is readily soluble in water, less soluble in spirit.

REACTIONS.—Its aqueous solution gives the reactions of potassium (p. 603) l a bromide (p. 594).

IMPURITIES.—Iodide and bromate.

TEST.—For the iodide, *vide* p. 560. Bromate is detected by adding dilute phuric acid to the crushed crystals. They should not at once assume a low colour. The acid liberates hydrobromic acid from the bromide, and bromate be present the reaction between it and the hydrobromic acid erates free bromine. $5HBr + HBrO_3 = 3H_2O + 3Br_2$.

ACTION.—Bromide of potassium does not seem to have, like e iodide, any marked influence on the lymphatic system, and hough it has been occasionally used instead of the iodide in mphatic swellings and enlargements of organs, this use of it is t general. When swallowed in small doses it produces no ect, but when taken in **large doses** for a considerable time causes an eruption like acne upon the face, the complexion at e same time becoming muddy or bronzed. The chief symptoms e, however, impairment of the functions of the **spinal cord** and e **brain**. There is a great diminution of reflex action, so that uching the pharynx no longer produces any tendency to vomit,

even though the touch itself be felt. There is drowsiness an heaviness, a great inclination to sleep and insensibility to ou ward impressions, the memory is impaired, the speech becom hesitating and articulation imperfect, the intellect is less clea the genital functions are much diminished, the gait becom tottering and unsteady, and the muscles weak. To these symp toms the name of **bromism** is given.

USES.—Its chief use is in **nervous diseases** for the purpo of producing sleep, allaying excitement, and diminishing spasm

Bromide of potassium is most useful as a **hypnotic** in cas of sleeplessness due to mental excitement and worry. Som persons, after hard study or close attention to business, instea of sleeping at night are no sooner in bed than the brain seem to become doubly active, the carotids throb and they toss abo from side to side trying in vain to get rid of the ideas whic come in a constant train before them. In such cases whe bromide of potassium is taken, the throbbing of the carotids ar temporals and the fulness in the head disappear and sleep induced. A dose of 10–15 grains given before bed-time may sufficient in mild cases, but when the agitation is great 30 or grains must be given, and should be assisted by cold ablution the head and a prolonged warm foot-bath. The dose may repeated, if necessary, every hour or two hours, until the desir effect has been obtained. One great advantage that bromide potassium possesses over other hypnotics is that it can be push without fear, and the same is true of other bromides. They a not dangerous to life, and even when they are pushed so far to cause bromism, the symptoms usually pass off rapidly wh the drug is discontinued.

It is very useful in lessening the excitability, susceptibili to worry, and **irritability** of temper from which gouty perso often suffer. It should be given with a considerable proporti of water.

In delirium tremens where there is sleeplessness with fear visions it may be given in doses from 20–30 grains or ev more every two hours till sleep is induced. It is of most bene in the earlier stages before the delirium has become furious, a is useful also at the end of the attack in dispelling delusio which may still remain.

During the latter months of pregnancy, women are som times troubled at night with the imagination that they ha committed or are about to commit some great crime, such murdering their husbands or children; and these delusio according to Ringer, are removed by potassium bromide.

It is also useful, he says, in the treatment of night screa ing in children, apparently allied to nightmare. They awake of sleep screaming, seem very much frightened, and do appear to recognise their mother or other friends who try

ain to soothe them. In the sleeplessness of mania it is frequently though not always successful. It may be used in vers and inflammation when sleep is absent, and whenever pium and belladonna or hyoscyamus fail to produce sleep or ause sickness.

In **convulsive nervous affections**, such as whooping cough, ryngismus stridulus and spasmodic asthma, it is very useful, nd also to some extent in St. Vitus's dance and hysteria.

It is especially beneficial in **epilepsy**, and by its use the convulsions can almost always be lessened if not entirely stopped. similar result has been obtained in experiments on animals . 187). It is not so useful when the convulsions are violent, nd it is not so beneficial when there is only a transitory loss of onsciousness, as in *petit mal*. It is, perhaps, however, not so uch a curative as an alleviative remedy, and the fits are apt to eturn when its administration is discontinued.

It is useful in relieving **sickness**, especially in pregnancy. n sea-sickness it is perhaps more useful than any other remedy. should be taken in thirty-grain doses twice or thrice a day, r a day or two before the voyage begins, and should be kept up hile it continues. In severe cases it may be necessary to push e bromide so far as to keep up a state of more or less somnoncy and stupidity during the whole voyage.

From its power of lessening the sexual passion it is used as an **naphrodisiac** in priapism and nymphomania.

It is also useful in menorrhagia, especially when this occurs n young women, according to Ringer, while Garrod says it is ore useful in old women.

It is useful in neuralgia occurring in debilitated subjects, and metimes accompanied by flushed face with cold hands and feet. has been used in diabetes.

Sodii Bromidum, B. and U.S.P. BROMIDE OF SODIUM. NaBr; 102·8.)

CHARACTERS.—Small, colourless, or white monoclinic crystals, r a crystalline powder permanent in dry air, odourless, having saline, slightly bitter taste, and a neutral or faintly alkaline eaction.

PREPARATION.—*Vide* p. 618.

SOLUBILITY.—Soluble in 1·2 parts of water and in 13 parts of alcohol at 5° C. (59° F.)

REACTIONS.—It gives the reactions of sodium (p. 617), and if disulphide of arbon be poured into a solution of the salt, then chlorine water added drop by rop, and the whole agitated, the disulphide will acquire a yellow or yellowish-rown colour (bromide) without a violet tint (absence of iodide).

DOSE.—10 to 60 grains.

ACTION.—Its actions are the same as those of bromide of otassium, but it is said to be less irritating to the stomach, and ess apt to cause depression when used for a length of time.

Ammonii Bromidum, B. and U.S.P. BROMIDE OF AMMONIUM. (NH_4Br; 97·8.)

CHARACTERS.—In colourless crystals which become slightly yellow by exposure to the air, and have a pungent saline taste.

PREPARATION.—*Vide* p. 635.

REACTIONS.—Its solution gives the reactions of ammonia (p. 634), and bromide (p. 594).

DOSE.—2 to 20 grains.

USES.—The bromide of ammonium has been employed for the same purposes as the bromide of potassium. It may be used in cases where the bromide of potassium appears to cause depression, either instead of the potassium salt, or mixed with it, and the mixture of bromide of potassium with bromide of ammonium has been supposed to have a better action than either salt alone. The best proportion is said to be that of 1 part of bromide of potassium, 1 of bromide of sodium, and ½ of bromide of ammonium.[1]

U.S.P. Lithii Bromidum. BROMIDE OF LITHIUM. (LiBr 86·8.)

CHARACTERS.—A white granular salt, very deliquescent, odourless, having a very sharp, somewhat bitter taste, and a neutral reaction.

PREPARATION.—*Vide* p. 631.

SOLUBILITY.—Very soluble in water and in alcohol.

REACTIONS.—Those of lithium (p. 630) and of a bromide (p. 594).

DOSE.—15–30 grs.

ACTION.—The same as that of bromide of potassium. It is said by some to have a stronger hypnotic action than the other bromides, but by others to be less effective than the potassium salt.

USES.—The same as those of potassium bromide. It may be preferable to the potassium salt in the irritability of gouty subjects.

U.S.P. Calcii Bromidum. BROMIDE OF CALCIUM. (CaBr 199·6.)

CHARACTERS.—A white granular salt, very deliquescent, odourless, having a pungent saline and bitter taste, and a neutral reaction.

PREPARATION.—By adding milk of lime to a boiling solution of ammonium bromide.

REACTIONS.—An aqueous solution of the salt yields the reactions of calcium (p. 646) and a bromide.

USES.—15 to 30 grains (1 to 2 gm.).

DOSE.—The same as those of potassium bromide (p. 553). It is said not to depress like the potassium bromide.

U.S.P. Zinci Bromidum.—*Vide* p. 672.

[1] Erlenmeyer, *Centbl. f. Nervenhk.* 1884. No. 4.

IODUM. I; 127 or 126·6, U.S.P.

Iodine.—A non-metallic element obtained from the ashes of a-weeds and from mineral iodides and iodates.

CHARACTERS.—Heavy, bluish-black, rhombic plates of a peculiar our and metallic lustre, which, when heated, yield a beautiful olet-coloured vapour.

PREPARATION.—*Vide* p. 548.

SOLUBILITY.—It is very sparingly soluble in water, but freely dissolved alcohol, by ether, and by a solution of iodide of potassium.

REACTION.—The aqueous solution strikes a deep blue colour with starch.

IMPURITIES.—Moisture, metallic impurities fraudulently added, cyanide iodine (the nitrogen in this is yielded by marine animals amongst the sea-ed), chloride of iodine, chlorine and bromine.

TESTS.—It should not adhere to the sides of the bottle, and its solution in oroform should be clear and limpid (absence of moisture). It sublimes as urple vapour without leaving any residue (absence of fixed impurities), l the portion that first comes over does not include any slender colourless sms emitting a pungent odour (absence of cyanide of iodine); 12·7 grains solved in an ounce of water containing fifteen grains of iodide of potassium uire for complete discoloration 1,000 grain-measures of the volumetric ution of hyposulphite of sodium.

PREPARATIONS, B.P.

rsenii Iodidum.
mplastrum Plumbi Iodidi.
ydrargyri Iodidum Rubrum.
doformum.
inimentum Iodi (p. 516).
inimentum Potassii Iodidi cum Sa-pone (p. 516).
iquor Iodi, aqueous solution (1 in 20).
ilula Ferri Iodidi (p. 522).
lumbi Iodidum.
otassii Iodidum.
odii Iodidum.
Sulphuris Iodidum.
Syrupus Ferri Iodidi.
***Tinctura Iodi,** alcoholic solution (1 in 40).
Unguentum Hydrargyri Iodidi Rubri.
* „ **Iodi** (1 in 31).
„ Plumbi Iodidi.
„ Potassii Iodidi.
„ Sulphuris Iodidi.
***Vapor Iodi** (Tincture of Iodine, 1 fl. dr. mixed with 1 fl. oz. of water, gently warmed, and the vapour inhaled).

U.S.P.

mmonii Iodidum.
rgenti Iodidum.
rsenici Iodidum.
iquor Iodi Compositus (5 in 100).
lumbi Iodidum.
otassii Iodidum.
odii Iodidum.
Sulphuris Iodidum.
Tinctura Iodi (8 in 100).
*Unguentum Iodi (4 in 100).
„ Plumbi Iodidi.
„ Potassii Iodi.
Zinci Iodidum.

The preparations marked with * in the preceding list contain iodine in a free te dissolved by the aid of iodide of potassium (p. 556). Tinctura Iodi U.S.P. ntains free iodine dissolved in alcohol. The others contain it in a state of com-nation.

U.S.P. Liquor Iodi Compositus. Iodine 5, iodide of potassium 10, distilled ter 85. This solution differs from Liquor Iodi P.B., only in containing 10 per nt. of iodide of potassium, while the B.P. preparation contains 7½ per cent.

Sulphuris Iodidum. B.P. and U.S.P. IODIDE OF SULPHUR.

CHARACTERS.—Greyish-black, crystalline lumps. It smells ke iodine and stains the skin. When boiled with water it is ecomposed, iodine passing off and sulphur remaining.

PREPARATION.—By fusing iodine and sublimed sulphur together.

OFFICINAL PREPARATION, B.P.

Unguentum Sulphuris Iodidi.—Ointment of iodide of sulphur (30 grains to an ounce of prepared lard).

Iodine is rendered much more soluble either in water or spirit by the addition of iodide of potassium, hence this substance is used in the liniment, liquor, tincture, and ointment of the B.P. and in the compound solution and ointment of the U.S.P. It is not contained in the tincture of the U.S.P., which is a simple solution of iodine in alcohol.

DOSE.—The only preparations of iodine used for internal administration are the tincture B.P. and U.S.P., the liquor B.P. and compound solution U.S.P., of all of which the dose is 5 to 20 minims.

PHYSIOLOGICAL ACTION.—Like chlorine and bromine, iodine is a powerful antiseptic and oxidising agent. When applied to the unbroken **skin**, iodine stains it of a dark yellowish-brown colour, causes slight warmth, and afterwards a little itching. In stronger solutions it will cause a painful burning sensation, and desquamation of the epidermis. In still stronger solution it may produce vesication. When taken internally, in small doses, it acts as an irritant to the **intestinal canal**, causing catarrh of the mucous membrane. When absorbed into the blood it somewhat increases the rapidity of the **pulse**. It has little action upon blood-pressure. Its influence upon the **temperature** is very slight, but it seems rather to raise it. Iodine appears to have a tendency to cause **absorption** of enlarged glands and thickenings caused by chronic inflammation. It seems to combine with such metals as lead and mercury, which have become deposited in the tissues in cases of chronic poisoning, forming with these soluble iodides which are eliminated in the same way as iodine itself. It is **eliminated** by the urine, nasal mucous membrane, saliva, intestinal mucus and milk, in all of which it may be readily detected. It appears to be eliminated even more readily by the saliva than by the urine (p. 358), and on this account it may remain a considerable time in the body. During the process of elimination it may irritate those parts where it is set free from its compounds as the nose or skin. Even in small doses it may cause symptoms of **iodism**. These consist in irritation, either of the nose or intestinal tract; the most prominent are great running at the nose, lacrimation, and sometimes frontal headache. Similar symptoms are produced by exposure to the fumes of iodine for a length of time. The nasal symptoms may be accompanied or replaced by symptoms of gastric irritation, loss of appetite, slight nausea, and tendency to looseness of the bowels. The **symptoms of poisoning**, such as have occurred from the injection of large quantities of iodine solution into an ovarian cyst, were, first, collapse, followed after a little while by an appearance of fever

th rapid pulse and flushed face, but without any rise of temrature. This condition passed off in several days, but during parent convalescence the patient suddenly died. Small doses iodine, by improving the health of patients, may increase the enstrual flow, and may act as aphrodisiacs. Larger doses nerally have a very marked **anaphrodisiac** action, and it has en stated that long-continued use has produced atrophy of the mmæ, ovaries, and testes. It has been stated that very large ses affect the **nervous system**, causing delirium, and twitchg or paralysis of the muscles (p. 549).

Uses.—Iodine applied to the epidermis acts as a **parasiticide**, d may be used in cases of tinea to destroy the fungus, either ne or combined with tar in the proportion of two drachms of line to one ounce of light oil of wood tar. Its solution, painted the surface, is useful in removing muscular pains, and in using absorption of thickening around joints, or of enlarged umous glands. When painted on the surface it sometimes uses absorption of the enlarged thyroid gland in goître, and, en outward application is insufficient, success is sometimes tained by injecting from ten to thirty minims of tincture of line into the substance of the tumour by means of a hypormic syringe, care being taken to avoid injection into a vein. solution, painted on the surface, is also useful in causing sorption of fluid from serous cavities, as in pleurisy. Sometimes, er the fluid has been evacuated from a serous sac, such as the ura, or the tunica vaginalis in hydrocele, or from ovarian sts, a dilute tincture of iodine is injected into the sac to prent the fluid from again accumulating.

In removing slight consolidation of the lung, remaining after eumonia or pleurisy, or in cases of commencing phthisis, the ternal application of liniment of iodine is very useful. It ould be painted on the surface, every second or third day, so always to keep one part a little tender. By mixing the linient with the tincture in varying proportions any degree of rength can be obtained. Cases of ozæna are sometimes much nefited by washing out the nose with a solution of common salt which a few drops of tincture of iodine have been added. The pour of iodine is employed in chronic bronchitis and phthisis.

On account of its irritating action on the intestinal mucous embrane, iodine is rarely given internally, its place being supied by iodide of potassium, but some consider that iodine is metimes more effectual, and it has been given in scrofula, skin seases, and glanders.

The liquor iodi B.P., or compound solution of iodine U.S.P., useful in arresting vomiting when administered internally in ses of 3 to 5 minims.

Potassi Iodidum, B. and U.S.P. Iodide of Potassium. I; 165·6.)

CHARACTERS.— In colourless, generally opaque, cubic crystal

PREPARATION.—By mixing iodine and solution of potassa, when iodic and iodate of potassium are formed, $6KHO + 6I = KIO_3 + 5KI + 3H_2O$. T iodate is then reduced to iodide by roasting with charcoal, $5KI + KIO_3 + 3$ $= 6KI + 3CO$.

SOLUBILITY.—It is readily soluble in water, and in a less degree in spir

REACTIONS.—It commonly has a feeble alkaline reaction; its solution giv the reactions of potassium (p. 603) and an iodide (p. 594).

IMPURITIES.—Iodate from imperfect reduction, chlorides, sulphates, c bonates. Iodate is the most important impurity, since the dilute acid of t gastric juice will form hydriodic acid from the iodide, and this will libera free iodine from the iodate in the stomach, and thus give rise to such gast irritation that the iodide cannot be borne in doses where pure iodide would readily tolerated.

TESTS.—The addition of tartaric acid, B.P., or dilute sulphuric ac U.S.P., and mucilage of starch, B.P., or gelatinised starch, U.S.P., to watery solution does not develop a blue colour (absence of iodate). iodate be present the acid liberates hydriodic acid, and this re-acting on t iodate forms free iodine, $6HI + KIO_3 = 3H_2O + KI + I_6$. Solution of nitr of silver added in excess forms a yellowish-white precipitate, which, wh agitated with ammonia, yields on standing a clear liquid in which excess nitric acid causes no turbidity, B.P. (absence of chloride). Iodide of silve insoluble in ammonia, but chloride is readily soluble, so the chlorides present, would be taken up by the ammonia and re-precipitated on the ad tion of acid. Its aqueous solution is only faintly precipitated by the addit of saccharated solution of lime.

DOSE.—2 to 10 grains.

PREPARATIONS CONTAINING IODIDE OF POTASSIUM.

B.P.	STRENGTH.
Linimentum Iodi (p. 516)	22 grs. in 1 fl. oz. nearl
,, **Potassii Iodidi cum Sapone** (p. 516)	54½ grs. in 1 fl. oz. nea
Liquor Iodi	33 grs. in 1 fl. oz.
Tinctura Iodi (Dose, 1–5 min.)	11 grs. in 1 fl oz. nearl
Unguentum Iodi	16 grs. in 1 oz. nearly.
,, **Potassii Iodidi**	1 part in $8\frac{3}{4}$, nearly.

U.S.P.	DOSE.
Unguentum Potassii Iodidi	
Liquor Iodi Compositus	2–6 min. (0·10–0·40 c.c

Unguentum Potassii Iodidi, B. and U.S.P. OINTMENT OF IODIDE POTASSIUM.—Iodide of potassium 64 grains, carbonate of potassium 4 gra distilled water 1 fluid drachm, prepared lard 1 ounce. Dissolve the iodid potassium and carbonate of potassium in the water, and mix thoroughly with lard. B.P.

Iodide of potassium 12, hyposulphite of sodium 1, boiling water 6, benzo lard, 81. U.S.P.

The ointment is apt to become discoloured by the liberation of free io when iodide of potassium and lard only are used. The carbonate of potass B.P., is added in order that it may combine with any iodine set free, and the h sulphite, U.S.P., is also used to prevent this discoloration.

ACTION.—The action of iodide of potassium appears to dep partly on the iodine and partly on the potassium it contains. differs from that of free iodine (p. 558) in being much irritant. On this account it is of little use as a local stimul

t it can be given in much larger doses. It has been supposed at iodine is set free from iodides in the stomach; but probably s is not the case, at least to any great extent, unless the ides are contaminated with iodates. Iodide of potassium and er alkaline iodides are readily **absorbed**. It is conveyed by blood to the various tissues of the body. It has been sup-ed by Binz to be partially **decomposed** by some of them, h the evolution of free iodine both in the blood and in the sues, and he attributes its most important actions to this composition. The iodine set free from the iodide is taken up **albuminous substances**, and the entrance of the iodine lecule into their composition causes them to undergo more id metamorphosis. Gummatous deposits appear to be espe-lly affected in this way.

Lead and **mercury** also appear to be set free by it, from their nbinations with the tissues, and entering once more into the culation are eliminated. Iodides are **eliminated** very rapidly the kidneys, salivary glands, probably by all mucous mem-nes, and by the skin. During the process of elimination ine is occasionally set free and causes local irritation. This especially marked in the mucous membrane of the **nose**, and he skin, but it may occur also in the conjunctivæ, bronchi, stomach. The irritation of the nasal mucous membrane s produced gives rise to the symptoms generally known as **ism**. They are exactly the same as those produced by pro-ged exposure to the fumes of iodine. They consist of running he nose, and frontal headache, which probably depends upon lling of the mucous membrane lining the frontal sinuses. ere is also frequently running of the **eyes**. Not unfrequently **bronchial** mucous membrane becoming congested there is gh and pain in the chest. These symptoms are most readily duced by small doses of 2–5 grains, and they may usually be sted either by discontinuing the medicine or increasing the e. When the dose is raised to 10 grains the symptoms ally disappear, and I have only seen one case in which they sisted after the dose had been raised to 30 grains. In some sons the congestion is not confined to the nose, but extends to back of the throat and to the **larynx**, so that serious symptoms suffocation may follow the laryngeal congestion produced in m by iodide. As the iodine is eliminated in the tears, severe junctivitis may follow the application of calomel to the eyes of sons who are taking iodide at the same time. Affections of **skin** usually occur with large doses of iodide. The most mon form of eruption is acne, but tubercular eruptions are met with. They appear to be caused by decomposition of iodide with elimination of free iodine in the sweat and aceous matter. They are said to be lessened by the simul-eous use of arsenic, and to be prevented by perfect cleanliness

and daily baths. Occasionally the iodide causes **gastric** irrit tion with diminished appetite. It is readily excreted by th **salivary** glands, and may give rise to salivation (p. 358). sometimes gives rise not only to congestion of the bronchi mucous membrane and cough, but to hæmoptysis, exudatio into the pleural cavity, and even pneumonic consolidation.

In some persons it greatly depresses the **genital** functions.

During its excretion by the **kidneys** it acts as a diureti though not a very powerful one.

USES.—Although iodide of potassium is probably absorb in very small quantity by the unbroken skin, even when mix with oil or fat, yet the iodide of potassium and soap linimer especially when mixed with its own bulk of opium linimer sometimes gives considerable relief when applied to inflam and rheumatic joints by means of flannel or lint. When us with lanolin, it is said to be more readily absorbed and to gi still greater relief in chronic joint disease. Iodide of potassiu is chiefly used, however, internally in syphilis, rheumatis scrofula, and chronic poisoning by lead or mercury. the primary and secondary stages of syphilis, mercury generally used either alone or in combination with iodine. the tertiary stage, iodide of potassium is more generally giv alone, although it is said by some to have but little eff unless mercury has been administered at some previous tim If this opinion be correct, the beneficial action of iodide potassium may be due, in part at least, to its again liberati part of the mercury which has been in a state of more or l dormant combination with some of the tissues. The power action of iodide of potassium in removing syphilitic deposits readily seen when these deposits are superficial, as nodes on t shin or on the sternum, or when they can be readily seen, li deposits in the larynx. Sometimes such deposits are unaffect by small doses, such as five grains of iodide, but disappe rapidly when the dose is increased to ten grains or more. Fr its beneficial action on visible deposits we may infer that it h a similar action on those which are deeply situated, and inde sometimes we may observe enlargement and induration of t liver, probably dependent on a syphilitic condition, rapidly d appear under the use of the iodide. In chronic rheumatis especially when the pain is worse at night, it is sometim useful.

It apparently increases the activity of the lymphatic syste and is used in enlargement of glands connected with this syste e.g. enlarged thyroid, enlarged spleen, and the enlarged ly phatic glands which occur in scrofula, as well as in scrofulo conditions generally.

It is given wherever absorption is deficient and organs beco hypertrophied, e.g. the breasts, testicles, prostate, uterus, ovari

. In cancer and tubercle it is of little benefit; it is some-
nes given, and possibly with benefit, in order to aid the
sorption of pneumonic consolidation.

In bronchitis with much congestion and deficient secretion it
a useful expectorant, rendering the mucus more abundant and
s tenacious, so that it is more readily expectorated.

As syphilitic skin-diseases often disappear under its use, it
s been applied to other skin-diseases not dependent on syphilis,
ch as psoriasis, lepra, herpes, impetigo, lichen, prurigo, sycosis,
ne, lupus, &c., especially in scrofulous patients.

In frogs it destroys sensibility and voluntary motion by act-
g on the spinal cord. It is useful in large doses to diminish
e pain in cases of aneurism, and is also used in neuralgia,
ralysis, convulsions, &c.

The relief which it affords to the pain of aneurism is very
rked, but it must be given in large doses, e.g. thirty grains.
e benefit which it affords may be partly due to weakening of
e circulation, partly to diminished sensibility by the action of
e drug on the nervous system, and partly to beneficial altera-
ns in the morbid condition of the walls of the affected vessels,
ich are often syphilitic in character.

It is exceedingly useful, as already mentioned, in chronic
tallic poisoning, e.g. by mercury or lead.

It is used in dropsies as a diuretic, and is also employed as
emmenagogue.

Sodii Iodidum, B. and U.S.P. IODIDE OF SODIUM. NaI;
0·6.

CHARACTERS.—Minute, colourless, or white monoclinic crystals,
a crystalline powder, deliquescent on exposure to air, odour-
s, having a saline and slightly bitter taste and a neutral or
ntly alkaline reaction.

SOLUBILITY.—Soluble in 0·6 part of water and in 1·8 parts of alcohol at
C. (59° F.).

REACTION.—If disulphide of carbon be poured into a solution of the salt,
n chlorine water added drop by drop, and the whole agitated, the disulphide
arbon will acquire a violet colour.

DOSE.—3 to 30 grains.

USES.—It is employed in place of iodide of potassium. Its
ysiological actions are almost exactly the same, but it appears
be less depressing and to irritate the stomach less. It may
us be given in larger doses.

U.S.P. Ammonii Iodidum. IODIDE OF AMMONIUM. NH_4I;
1·6.

CHARACTERS.—A white granular salt, or minute crystalline
bes, very deliquescent and soon becoming yellow or yellowish-
wn on exposure to air; odourless when white, but emitting a

slight odour of iodine when coloured, having a sharp saline ta and a neutral reaction.

USES.—A solution of ½-drm. in an ounce of glycerine has be used as an application to enlarged tonsils. An ointment co taining 20 to 60 grs. of the iodide to 1 oz. of lard has been us in cases of lepra and psoriasis. It is chiefly used internally syphilis, scrofula, and glandular enlargements, either instead or along with iodide of potassium. A mixture of the two iodi has been thought by some to be more efficacious than eith used singly, and the iodide of ammonium prevents the depre ing action often exerted by the iodide of potassium alone.

U.S.P. Zinci Iodidum.—*Vide* p. 673.

U.S.P. Argenti Iodidum.—*Vide* p. 680.

Hydrargyri Iodidum Rubrum, B. and U.S.P. — *V* p. 696.

U.S.P. Hydrargyri Iodidum Viride.—*Vide* p. 696.

Plumbi Iodidum, B. and U.S.P.—*Vide* p. 705.

The action of the iodides of zinc, silver, mercury, and l is modified to such an extent by the special action of the me that the compounds are better considered under the headings their respective metals (*q.v.*) than side by side with the compou with the alkalis.

CHAPTER XXIII.

ACIDS.

NERAL CHARACTERS.—It is somewhat difficult to get a correct inition of an acid. Most of them have a sour taste and den blue litmus: they combine with alkalis and destroy the wer which these have of turning red litmus-paper blue.

They may be regarded as compounds of hydrogen with certain icals, hydrogen being readily displaced by other bases. Some ds, as boric and carbolic, have no sour taste. Carbolic acid s not redden litmus-paper, but it is in reality an alcohol, nough in chemical combinations it behaves like an acid.

GENERAL PREPARATION OF ACIDS.—Most acids are prepared by rating them from their alkaline salts by means of sulphuric d. When they are volatile they are separated by distillation, d when non-volatile by crystallisation.

Sulphuric acid, which is of such importance in the preparation ther acids, is itself prepared by oxidising the fumes of sulphur means of nitric acid. Sulphur is burnt, and the sulphurous de thus produced is conducted along with the vapour of nitric d into a large leaden chamber, where it is mixed with steam. phurous oxide is oxidised by the nitric acid and sulphuric de is formed, which uniting with the watery vapour forms phuric acid. The nitric acid is deoxidised in this process into ric oxide; this unites with the oxygen of the air to form nitric oxide, and this again supplies fresh oxygen to the sulphurous d, $NO_2 + SO_2 + H_2O = NO + H_2SO_4$. In this way a small quan- of nitric acid is sufficient to oxidise a large quantity of phuric acid; reduction and reoxidation going on alternately he nitrous fumes. The sulphuric acid formed in the leaden mber is drawn off and evaporated to the proper strength.

The acids which are prepared by liberation from their sa by sulphuric acid are given in the following tables:—

Volatile Acid	Prepared from	By addition of Sulphuric Acid and
Carbonic Acid . .	Any carbonate, generally Carbonate of Calcium	Conducting into water or alk line solution, according to th purpose required.
Hydrochloric Acid, B. and U.S.P.	Sodium chloride .	Distilling into water, which di solves the acid.
Nitric Acid, B. and U.S.P.	Sodium Nitrate, or Potassium Nitrate	Distilling.
Acetic Acid, B. and U.S.P.	Crystallised Sodium Acetate	Ditto.
Glacial Acetic Acid, B. and U.S.P.	Dried Sodium Acetate	Ditto.
Dilute Hydrocyanic Acid, B. and U.S.P.	Potassium Ferrocyanide	Distilling into water.

Sodium chloride and sodium nitrate are found native: sodium acetate is prepared from gas liquor by saturating w sodium carbonate.

In preparing hydrocyanic acid the cyanide is not employ but the ferrocyanide which is prepared by heating toget animal refuse and iron filings and potassium carbonate.

Non-Volatile Acid	Prepared from	By addition of Sulphuric Acid and
Chromic Acid . .	Potassium Bichromate	Collection of crystals, drainin and drying.
Tartaric Acid, B. and U.S.P.	Tartrate of Calcium, made from acid tartrate of potassium	Subsequent decantation fr calcium sulphate, evaporati and crystallisation.
Citric Acid, B. and U.S.P.	Citrate of Calcium, made from lemon-juice	Subsequent decantation, &c., for tartaric acid.
Lactic Acid, B. and U.S.P.	Lactate of Calcium, obtained by peculiar fermentation of sugar	Decantation and evaporation.
Boric Acid, B. and U.S.P.	Sodium borate . .	Precipitation; the boric ac sparingly soluble in water, f as a precipitate, and the sodi sulphate is removed by dec tation or filtration.

If sulphuric acid were added to citrate or tartrate of potass or sodium, it would be difficult to separate the acid from sulphate. To avoid this, the citrates and tartrates of calcium first prepared, and to these sulphuric acid is added. Th results an insoluble calcium sulphate which falls as a precipit and the solution of citric or tartaric acid is readily separate decantation or filtration, and evaporated to crystallisation.

Citrate of calcium is prepared by adding chalk to boiling len juice, and washing the colouring matter from the precipitat

t water. Hot is employed in preference to cold water because rate of calcium is less soluble in it. Tartrate of calcium is pre-red from the crude acid tartrate of potassium or argol, which deposited from wine during the process of fermentation. alk is first added to a solution of it, whereby a neutral tartrate ormed, $2(KHC_4H_4O_6) + CaCO_3 = CaC_4H_4O_6 + K_2C_4H_4O_6 + CO_2 + O$. This is then decomposed by the addition of calcium oride or sulphate, $K_2C_4H_4O_6 + CaCl_2 = CaC_4H_4O_6 + 2KCl$.

Exceptions to the rule that acids are prepared from salts the addition of sulphuric acid :—

Acid	Prepared by
ulphuric Acid . .	Combustion of sulphur and the oxidation and hydration of the resulting sulphurous acid gas by means of nitrous and aqueous vapours.
hosphoric Acid .	Oxidising phosphorus by heating it with diluted nitric acid until nitrous fumes have ceased to form, and then diluting it to the proper strength.
xalic Acid . .	Oxidising sugar by heating with nitric acid.
ulphurous Acid .	Deoxodising sulphuric acid by means of charcoal and passing the fumes into water.
ydrobromic Acid .	By passing sulphuretted hydrogen into bromine and water $2Br_2 + 2H_2S = 4HBr + S_2$.
rsenious Acid . .	Roasting arsenical ores, collecting the acid which sublimes, and purifying it by resublimation.
enzoic Acid . .	Heating gum benzoin when the acid sublimes.
rbolic Acid . .	Fractional distillation of coal-tar oil and subsequent purification.
eic Acid . .	Decomposing lead oleate by hydrochloric acid or by decomposing fats by superheated steam and separation from solid fats by pressure.
licylic Acid . .	By passing carbonic acid gas over sodium carbolate which is made by evaporating a mixture of caustic soda and carbolic acid to dryness.
nnic Acid . .	Dissolving out from the fresh nut-galls in which it is contained by ether and water.
llic Acid . .	Dissolving it out from fermented nut-galls by hot water.

Hydrobromic acid, although volatile, is not unfrequently epared without distillation. McLean Hamilton and Milner thergill's plan is to dissolve 84¼ grs. of potassium bromide in fluid ounce of water, and add 99 grs. of tartaric acid to it. ter standing at a low temperature for twelve hours, acid rtrate of potassium crystallises out, and leaves a solution con-ning about 10 per cent. of real hydrobromic acid.

General Action of Acids.—They have an affinity for electro-sitive or basic substances, and combine with them when they me in contact. Stronger acids drive out weaker ones from eir combination with bases, setting them free; but are them-ves sometimes driven out by weaker ones if these form an soluble combination.

When they come in contact with the tissues they produce anges in a twofold manner; (1) by forming new compounds,

(2) by destroying others previously existing. The different acids possess different affinities, and the actions they exert vary with the acid and with the degree of its concentration, weak acids having their affinities easily satisfied. All the **tissues** of the body are alkaline, and the first effect of acids will be to neutralise the alkali, and if albumin be dissolved in it to precipitate it. If sufficient acid be present, they all, with the exception of nitric acid, again redissolve it. Acids unite with **albumin** in different proportions, forming acid-albumin. When mixed with **blood** they not only precipitate albuminous substances, but decompose hæmoglobin, forming a substance which holds oxygen with more tenacity than hæmoglobin. They coagulate myosin and produce instantaneous rigidity in **muscles**. Sulphuric and phosphoric acids have, besides their chemical affinities, a strong attraction for water, and completely decompose the tissues to which they are applied, so that they are most powerful **escharotics**. Nitric acid does not readily redissolve the albumin precipitated by it, and thus forms a barrier to its own action, so that it does not penetrate so deeply as sulphuric acid.

Round the tissue killed by acids inflammation ensues, and an eschar is separated. When their action is less intense they cause inflammation of the surface of the dermis, and produce **vesication**. Still less concentrated, they precipitate albumin from its solutions in the tissues, act as irritants, and cause contraction of the blood-vessels. This effect is removed by the alkalinity of the blood, and the irritation may be only sufficient to cause a temporary congestion subsequent to the contraction. Then the acids act only as **rubefacients**. As such they are used in the form of baths.

In the **mouth** they cause a peculiar taste, and a feeling of roughness in the teeth. They cause an increased flow of saliva from the parotid, and of the thin saliva which the submaxillary secretes when the chorda tympani is irritated, but have no effect on the sympathetic saliva. They are therefore given to allay thirst in fever, the increased secretion of saliva which they provoke keeping the fauces moist (p. 357).

Acids stimulate the secretion of the alkaline saliva and intestinal juice, and excite the expulsion of bile from the gall-bladder. They are supposed generally to stimulate those glands whose secretions are alkaline. On the other hand alkalis stimulate the secretion of gastric juice, which is acid; and they are supposed to stimulate in general those glands whose secretion is acid. Professor Ringer supposes that the converse is also the case, and that acids and alkalis severally hinder the secretion of a like character. This supposition may be correct, and no doubt when an acid is present—e.g. in the stomach—it will neutralise any alkali which may be taken, and either retard its stimulant action on the gland or prevent it altogether, according

the relative quantities of acid present and of alkali employed. e presence of much alkali will also hinder the action of an d stimulus in the same manner, but whether acids and alkalis ve any further effect in hindering secretion than that just ntioned is uncertain.

Acids are partly neutralised by the saliva, and partly act as ringents on the mouth and fauces. They are thus used in gestion of the throat. As they corrode the teeth, they are erally given through a glass tube or quill, and the teeth uld be rubbed with chalk afterwards.

Digestion in the **stomach** is accomplished by the action of sin along with dilute hydrochloric acid (·2 per cent. in man). s ferment only acts in presence of free acid; but the amount acid necessary is different in different animals, being greatest he carnivora (·3 per cent. HCl in the dog) and least in the bivora. Pepsin seems able to go on dissolving fibrin almost hout a limit, but fresh acid must always be added. If the retion is deficient, digestion goes on slowly and fermentation he food takes place, causing the formation of other acids and ration of gases.

The secretion of gastric juice may be stimulated by alkalis n just before meals; but if the stomach is so much out of r as not to respond to the stimulus, hydrochloric or phosric acid may be given after meals, alone, or with pepsin. In ile conditions there is a deficiency of free acid in the stomach, ough pepsin is present in plenty. In chronic gastric catarrh, cially when accompanied by dilatation, the free acid is greatly inished, and in carcinoma of the stomach it would seem to anting in the great majority of cases. In such conditions, refore, the administration of diluted hydrochloric acid is cated.

For acid eructations and heartburn depending on excessive ity of the gastric juice, acids should be given before meals ger).

Some persons are troubled by eructations of sulphuretted rogen with a taste of rotten eggs. These persons have gene- oxalic acid in the urine, and frequently suffer from depres- of spirits. Such patients are benefited by acids, especially o-hydrochloric acid. Persons who suffer from dyspepsia and ression of spirits with oxaluria are also benefited by mineral s, even when no sulphuretted hydrogen is present in the stines.

When the use of acids is long continued they lessen the tion of gastric juice, and produce a catarrhal condition of mucous membrane of the stomach. They should therefore be given for more than a week or two at a time. They ld then be left off for a short time, or alternated with alkalis. stant use of acid wines has a similar tendency to produce

catarrh. Vinegar is sometimes drunk in order to lessen obes or even plumpness. It has this effect by inducing gastro-int tinal catarrh, but sometimes the derangement of the digest occasioned by it has been so great as to cause death.

Acids stimulate the expulsion of bile from the gall-bladd and the secretion of **intestinal** juice. As they will be rapi neutralised by the bile and pancreatic juice, and absorbed in duodenum, they can hardly reach the lower and middle parts the alimentary canal as acids. Their action in relieving diarrh is difficult to explain.

When absorbed from the intestine they must pass throu the **liver** before they can reach the general circulation (p. 39 *seq.*). It is probable that during their passage through the po system they alter the processes of tissue-change which go on the liver, and check the formation of urea. The reason for t supposition is that acids are excreted in the urine chiefly in form of ammoniacal salts. In the normal condition ammoni readily converted into urea in the organism, and when gi internally it appears in the urine in the form of urea, and no ammoniacal salts. The appearance of these salts in the u after the administration of acids shows that the normal proc of conversion into urea has been diminished. Possibly it is such alterations in the **tissue-change** in the liver that the called tonic action of acids is due (p. 410), as well as the mar benefit obtained in hepatic disorders from the administratio nitric and nitro-hydrochloric acids. Although acids app in the **urine** in combination with ammonia and other ba yet their free administration increases the acidity of the ur They are therefore used to prevent the deposits of phosph calculi which are apt to occur in alkaline urine.

POISONING BY ACIDS.—The symptoms of poisoning by ac and the antidotes to be employed, have already been descr (pp. 395, 397, and 486). In cases of acute poisoning wh death has not occurred too quickly, much albumen, hæma and indican have appeared in the urine, and fatty degen tion of the liver, muscles, and kidneys has been found. In kidneys the cloudy swelling and fatty degeneration of the were accompanied by evidences of inflammation in the connec tissue also, as it exhibited proliferation of nuclei, especially a the course of the vessels.

Acidum Sulphuricum, B. and U.S.P. SULPHURIC ACI It contains 96·8 per cent. of H_2SO_4 (98) and corresponds t per cent. of anhydrous sulphuric acid, SO_3 (80).

PROPERTIES.—A colourless, oily-looking, heavy liquid. Sp 1·843; no smell, but intensely acid taste. It blackens and rodes most organic substances. It has a great affinity for w and when mixed with it evolves much heat. When dilut

es a copious white precipitate of barium sulphate ($BaSO_4$) h chloride of barium, insoluble in nitric or in hydrochloric l.

REPARATION.—*Vide* p. 565.

MPURITIES.—Lead derived from the leaden chambers in which it is pre- d; nitric acid from the nitrous fumes; arsenic from impure sulphur g used and the arsenious fumes passing over with the sulphurous acid; water from imperfect concentration or fraudulent addition.

ESTS.—Not unfrequently it contains so much lead in the form of sulphate when diluted with water it deposits a white precipitate, the sulphate g soluble in the strong but not in the weak acid. It should not do this, when evaporated in a platinum dish it should leave little or no residue lead, arsenic, or saline impurities). When a solution of sulphate of iron refully poured over its surface there is no purple colour developed where two liquids unite (no nitric acid). Diluted with six times its volume of lled water it gives no precipitate with sulphuretted hydrogen (no arsenic ad). The absence of water is ascertained by the sp. gr. not being be- 1·840, and by the volumetric estimation of its neutralising power with tion of soda.

OFFICINAL PREPARATIONS.

B.P.	U.S.P.
idum Sulphuricum Aromaticum.	Acidum Sulphuricum Aromaticum.
„ „ Dilutum.	„ „ Dilutum.
usum Rosæ Acidum.	

Acidum Sulphuricum Aromaticum, B. and U.S.P. AROMATIC SULPHURIC . Is sulphuric acid diluted with alcohol and flavoured with cinnamon and r. About 1 in 13 B.P., and 1 in 10 U.S.P. by measure.

nfusum Cinchonæ Acidum contains aromatic sulphuric acid 1 part in 80.

Acidum Sulphuricum Dilutum, B. and U.S.P. DILUTE SULPHURIC ACID. e strong acid diluted with 11 parts B.P., 16½ parts U.S.P., of water by measure; 10 by weight U.S.P.

DOSES.—Of either aromatic or dilute sulphuric acid 5–30 min. ly diluted.

INCOMPATIBLES.—Preparations of lead.

ACTION.—It is a most powerful **caustic**, and quickly chars destroys the parts it touches. When mixed with charcoal te it is used as a caustic in cancer, and with lard in obstinate n-diseases. When swallowed, as it not unfrequently is in nufacturing districts, it produces symptoms of irritant poison- (p. 395). The antidotes are alkalis, soap, oil, whiting, milk, ster from the wall, or magnesia.

USES.—Internally it is used, after free dilution, to quench rst in fever, to prevent absorption of lead from the stomach painters and colour-grinders, to check diarrhœa, especially in hisis, to arrest hæmoptysis and other hæmorrhages, and to en night-sweats and mucous discharges.

Acidum Sulphurosum, B. and U.S.P. SULPHUROUS ACID.— phurous acid gas (SO_2; 64) dissolved in water and consti- ng 9·2 per cent. of the solution.

PROPERTIES.—A colourless liquid with a strong sulphurous ur.

REPARATION.—*Vide* p. 567, $2H_2SO_4 + C = CO_2 + 2SO_2 + 2H_2O$.

REACTIONS.—Unlike sulphuric acid, it gives no precipitate with chlor of barium, but if chlorine be added to it, it becomes converted into sulph acid, and then gives a precipitate, $SO_2 + 2H_2O + Cl_2 = H_2SO_4 + 2HCl$.

IMPURITIES.—Sulphuric acid, solid impurities, too little sulphurous aci

TEST.—It should give no precipitate, or only a slight one, with chlorid barium (little or no sulphuric acid); but very few specimens answer eit to this test or to the officinal volumetric test, on account of the liability of acid to decompose. It should leave no residue on evaporation. Its stren is determined by its sp. gr. 1·04, and the volumetric test.

DOSE.—½–1 fluid drachm diluted with water.

ACTION.—It is a powerful deoxidising agent. It is extrem destructive to plant life, and so may destroy disease-germs.

USES.—Gaseous sulphurous acid is used to **disinfect** roo The room should be closely shut up, and a brazier with charc placed in it. On this sulphur is thrown, and the fumes allowed to permeate the room for several hours. Care must taken that the brazier is so placed that there is no danger anything in the room catching fire. A solution mixed w glycerine may be applied in skin-diseases depending on paras fungi. It is very useful in cases of vomiting, especially wh the vomited matters have a frothy or yeasty appearance due the presence of sarcinæ and to the occurrence of fermentat in the stomach. Applied as spray it sometimes gives relief laryngeal phthisis.

Acidum Hydrochloricum, B. and U.S.P. HYDROCHLO or MURIATIC ACID.—Hydrochloric acid gas (HCl; 36·4) dissol in water, and forming 31·8 B.P., 31·9 U.S.P., per cent. by wei of the solution.

PROPERTIES.—A nearly colourless liquid, sp. gr. 1·16. emits white vapours having a pungent odour, and has a stron acid taste.

PREPARATION.—By warming chloride of sodium with sulphuric washing the evolved HCl, and conducting it into cold water by whic is absorbed. Excess of sulphuric acid is employed if glass vessels are in the preparation either of this or of nitric acid, as the bisulphate of po sium left behind is more soluble than the neutral sulphate, and thus vessels are more easily cleaned. $NaCl + H_2SO_4 = NaHSO_4 + HCl$.

REACTION.—It gives with nitrate of silver a curdy white precipitate sol in excess of ammonia, insoluble in nitric acid.

IMPURITIES.—Salts; sulphuric acid, with its impurities lead and arse chloride of sodium or chlorine; sulphurous acid formed from sulphuric organic substances; iron from the apparatus in which it is made comm cially.

Arsenic is of importance as an impurity because hydrochloric aci sometimes used in testing for arsenic by the formation of arseniur hydrogen. When testing for arsenic in cases of suspected poisoning both acid and the zinc must be tested first, in order to ascertain their purity b the suspected substance is added.

TESTS.—When diluted with four times its volume of distilled wat gives no precipitate with solution of chloride of barium (absence of sulph acid), or with sulphuretted hydrogen (absence of lead or arsenic), and not tarnish or alter the colour of bright copper foil when boiled wi

ence of arsenic). When diluted with five volumes of water it should not ate iodine from iodide of potassium (absence of chlorine); and when . is diluted to 10 c.c. with water and supersaturated with ammonia, the tion of two drops of ammonium sulphide causes no black colour (absence on). If a fluid drachm of it mixed with half an ounce of distilled water ut into a small flask with a few pieces of granulated zinc, and while the vescence continues a slip of bibulous paper wetted with solution of sub- te of lead, B.P., or nitrate of silver, U.S.P., be suspended in the upper of the flask above the liquid for about five minutes, the paper will not me discoloured (absence of sulphurous or arsenious acid, $SO_2 + 6H = + 2H_2O$). When evaporated it leaves no residue (no sodium chloride or fixed impurity).

PREPARATIONS CONTAINING FREE HYDROCHLORIC ACID.

B.P.	DOSE.
Acidum Hydrochloricum Dilutum (acid 8, diluted with water up to 26⅔ by measure)	10–30 m.
Acidum Nitro-hydrochloricum Dilutum	10–30 m.
Liquor Antimonii Chloridi	
,, Arsenici Hydrochloricus	
,, Morphinæ Hydrochloratis	
U.S.P.	
Acidum Hydrochloricum Dilutum (acid 6, water 13 by weight; 5½ and 14 by measure)	10–30 m.
Acidum Nitro-hydrochloricum	
,, ,, ,, Dilutum	10–30 m.

ACTION AND USES.—It produces symptoms of poisoning like e of sulphuric acid. The stains which it leaves upon the ous membrane are white. It is rarely used externally. It be employed to quench thirst in fevers, and to lessen phos- ic deposits in the urine; it is sometimes useful in cases of -throat. As it is the acid of the gastric juice, it may be n after meals in cases of indigestion, where we suspect iency of acid (p. 568), and to aid the digestion of food, as well relieve thirst in febrile conditions (pp. 360 and 569).

Acidum Hydrobromicum Dilutum, B. and U.S.P. DILUTED ROBROMIC ACID.—A liquid composed of 10 per cent. of real aseous hydrobromic acid (HBr; 80·8) and 90 of water.

CHARACTERS.—A clear, colourless liquid, odourless, having a ngly acid taste and an acid reaction. Sp. gr. 1·077. By it is completely volatilised.

EACTIONS.—On adding chlorine or nitric acid to diluted hydrobromic acid, ine is liberated, which is soluble in chloroform or in disulphide of carbon, rting to these liquids a yellow colour. Test solution of nitrate of silver s a white precipitate, insoluble in nitric acid and in water of ammonia, sparingly soluble in stronger water of ammonia.

ESTS.—On being kept for some time, the acid should not become coloured. solution of chloride of barium should not produce a turbidity or precipitate huric acid).

DOSE.—15 to 50 min. B.P. Two fluid drachms contain 12 ns of bromine, which are equal to about 18 grains of bromide

of potassium (United States Dispensatory). It may be given
syrup.

ACTION AND USES.—It appears to act as a **sedative** to t
nervous system, diminishing reflex action and lessening tenden
to spasm, in the same way as bromide of potassium, but diff
ing from it in not producing the feeling of depression frequen
caused by potassium bromide.

It has been employed in epilepsy, and to relieve nervousne

It is useful in headache and singing in the ears, either id
pathic or due to the administration of quinine or of iron. It
used also to remove the bad effects of excess in tea or alcoh
and to quiet palpitation.

Syrupus Acidi Hydriodici, U.S.P. SYRUP OF HYDRIO
ACID.—A liquid containing 1 per cent. of pure hydriodic a
(HI; 127·6), sugar, and spirit of orange.

CHARACTERS.—A transparent, colourless, or not more th
straw-coloured, liquid, odourless, and having a sweet acidul
taste. Sp. gr. 1·300.

TESTS.—If bisulphide of carbon be poured into a small portion of the sy
and a little chlorine water added, the disulphide will separate with a vi
colour in shaking. Gelatinised starch should not give to the syrup m
than a faint bluish tinge; and the precipitate by silver nitrate ought to
insoluble in ammonia. 31·9 grammes of the syrup require, for complete p
cipitation, 25 cubic centimetres of the standard solution of nitrate of silve

DOSE.—1 to 4 fluid drachms.

ACTION AND USES.—Hydriodic acid may be given in asth
and bronchitis instead of iodide of potassium, to which its acti
is similar (p. 560).

Acidum Nitricum, B. and U.S.P. NITRIC ACID. HN
63.—An acid prepared from nitrate of potassium or nitrate
sodium by distillation with sulphuric acid and water, and c
taining 70 per cent. B.P., or 69·4 U.S.P., by weight of nit
acid, HNO_3, corresponding to 60 per cent. of anhydrous nit
acid, N_2O_5.

CHARACTERS.—A colourless liquid, having a specific grav
of 1·42. Boiling-point, 250° F. When exposed to the air
emits an acrid, corrosive vapour.

REACTIONS.—If it be poured over copper-filings, dense, red vapours
immediately formed; but if the acid be mixed with an equal volume of wa
and then added to the copper, it gives off a colourless gas, which acquires
orange-red colour as it mixes with the air, and which, if it be introduced i
a solution of sulphate of iron, communicates to it a dark purple or bro
colour, due either to solution of N_2O_2 in the sulphate or combination with
If submitted to distillation the product continues uniform throughout
process.

IMPURITIES.—Weaker or stronger acid, sulphuric or hydrochloric ac
fixed impurities.

ESTS.—It leaves no residue when evaporated to dryness (no fixed im-ties, as iron, lead, &c.). Diluted with six times its volume of distilled r it gives no precipitate with chloride of barium or nitrate of silver (ab-e of sulphuric or hydrochloric acids).

PREPARATIONS CONTAINING FREE NITRIC ACIDS.

B.P.	DOSE.	U.S.P.
dum Nitricum Dilutum (acid 1, with about 4 of water measure)	10–30 m.	Acidum Nitricum Dilutum (acid 1, water 6 by weight; 1½, and 12½ by measure).
um Nitro-hydrochloricum lutum		Acidum Nitrohydrochloricum.
or Ferri Pernitratis		„ „ „ Dilutum.
Hydrargyri Nitratis Acidus		
entum Hydrargyri Nitratis		

ACTION.—It is an exceedingly powerful **caustic**, and destroys tissues, but, unlike sulphuric acid, it forms, to some extent, arrier to its own action by coagulating the albumin with ch it meets. When swallowed, it may not only produce the ptoms of irritant poisoning already described (p. 395), but vapour, getting into the larynx, may cause spasm of the glottis, death from suffocation, or may produce intense bronchitis.

USES.—Nitric acid is applied externally to destroy chancres, ty growths, and hæmorrhoids; to the surface of phagedænic rs; and to bites of snakes or rabid dogs, in order to destroy virus and prevent its absorption. Internally the dilute acid sed to quench thirst in febrile conditions, like other dilute ls, and it is useful in cases of dyspepsia. It is supposed have an action upon the liver, and certainly appears to be of in cases of so-called biliousness. When absorbed it has an **ringent** action, and is exceedingly serviceable in diminishing secretion from the lungs in bronchitis and in the sub-acute cerbations of phthisis. It is also employed in cases of syphilis urring in debilitated subjects, where mercurials are not well ne. It diminishes the phosphatic deposits in the urine, and, dilute condition, has been injected into the bladder in order issolve calculi already formed.

U.S.P. Acidum Nitrohydrochloricum. NITROHYDROCHLORIC D.

CHARACTERS.—A golden yellow, fuming, and very corrosive id, having a strong odour of chlorine and a strongly acid re-ion. By heat it is wholly volatilised. It readily dissolves gold , and a drop added to a test solution of iodide of potassium rates iodine abundantly.

PREPARATION.—By mixing nitric acid (4) with hydrochloric acid (15 parts), when effervescence has ceased, preserving it in glass-stoppered bottles, ch should not be more than half-filled and kept in a cool place.

Acidum Nitrohydrochloricum Dilutum, B. and U.S.P. UTE NITROHYDROCHLORIC ACID.—It contains free chlorine,

hydrochloric, nitric, and nitrous acids and other compound dissolved in water.

PREPARATION.—By mixing nitric acid 3, hydrochloric 4, water 25, measure, and allowing it to stand for 14 days before it is used, B.P. By dil ing nitrohydrochloric acid (1) with water (26 parts by weight, U.S.P.). T proportions of the components U.S.P. are, by measure, nitric acid 3, hyd chloric acid 13½, water 80.

DOSE.—5 to 20 minims.

USE.—This, like nitric acid, is supposed to have a spec action upon the liver. It is sometimes used, in the form of bat or compresses, in hepatic disorders, and is frequently given



FIG. 165.—Showing the position of the frontal headaches relieved by acids and alkalis in the abs of constipation. The lower is relieved by acids, the upper by alkalis before meals. The l one also indicates the occasional position of headache caused by straining the eyes.

cases of dyspepsia, biliousness, and jaundice. When given bef meals it seems to check acidity in the stomach, and it is v useful in removing headache situated in the forehead, just ab the eyebrows, and unaccompanied by constipation (Fig. 165). the ordinary diluted acid fails, a few drops of the strong a diluted with water at the time it is taken may succeed, and this fails a mixture evolving oxides of nitrogen and oxides chlorine may prove successful.[1]

Acidum Aceticum, B. and U.S.P. ACETIC ACID. HC_2H_3 60.—An acid liquid prepared from wood by destructive disti tion and subsequent purification. 100 parts by weight cont 33 B.P., 36 U.S.P., parts of acetic acid $HC_2H_3O_2$; 60 co sponding to 28 parts of anhydrous acetic acid, $C_4H_6O_3$.

CHARACTERS.—A colourless liquid having a strong acid react

[1] Such a mixture is :

℞ Solutionis Sodii Nitritis (1 in 4).
Sol. Potassii Chloratis (1 in 4), aa ℥ij.
Misce.
℞ Acidi Hydrochlorici Diluti.
Aquæ, aa ℥ij.

One teaspoonful of each mixture to be added to a wineglassful of water and t after meals.—Cook, *Practitioner*, vol. xxvii. p. 328.

a pungent odour. Specific gravity 1·044 B.P., 1·048 U.S.P., 5° C.

MPURITIES.—Lime, lead, copper, tin, sulphuric and hydrochloric acids, sulphurous acid due to the action of organic matter on the sulphuric

ESTS.—It leaves no residue when evaporated (no lime, &c.), and gives recipitate with sulphuretted hydrogen (no metals), chloride of barium nce of sulphuric acid), or nitrate of silver (absence of hydrochloric . If a fluid drachm of it mixed with half an ounce of distilled water alf a drachm of pure hydrochloric acid be put into a small flask with a ieces of granulated zinc, and while the effervescence continues a slip of ous paper wetted with solution of subacetate of lead be suspended in the r part of the flask above the liquid for about five minutes, the paper will ecome discoloured (absence of sulphuric acid, $SO_2 + 6H = H_2S + 2H_2O$).

PREPARATIONS CONTAINING FREE ACETIC ACID.

B.P.	STRENGTH.	DOSE.
um	4·6 per cent. anhydrous acetic acid	1 fl. dr. to 1 fl. oz.
Cantharidis		
Scillæ		15 to 40 min.
um Aceticum Glaciale	84 per cent. anhydrous acid.	
Aceticum	28 „ „ „ „	
„ **Dilutum**	3·6 „ „ „ „	1 fl. dr. to 1 fl. oz.
ctum Colchici Acetum		
entum Terebinthinæ Aceti- m (p. 516)	1 volume acetic acid in 3.	
r Epispasticus	1 volume acetic acid in 5.	
ra Creasoti		
el		1 to 2 fl. dr.
Scillæ		½ to 1 fl. dr.
us „		½ to 1 fl. dr.
ura Ferri Acetatis		5 to 30 min.

U.S.P.	DOSE.
cetum Lobeliæ	30 min. to 1 fl. dr. (2 to 4 gm.)
„ Opii	4 to 15 min. (0·25 to 1 c.c.)
„ Sanguinariæ	15 to 30 min. (1 to 2 gm.) as emetic, 3 to 4 fl. dr. (12 to 16 gm.)
„ Scillæ	15 min. to 1 fl. dr. (1 to 4 gm.)
cidum Aceticum	
„ „ dilutum	
„ „ glaciale	
xtractum Colchici Radicis	⅛ to 2 gr. (0·03 to 0·12 gm.)
yrupus Scillæ	15 min. to 1 dr. (1 to 4 c.c.)
incture Ferri Acetatis	15 min. to 1 dr. (1 to 4 c.c.)

idum Aceticum Dilutum, B. and U.S.P. DILUTED ACETIC ACID.—acid, 1 part diluted with water 7 parts, B.P., or acid 17, water 83, U.S.P.
OPERTIES, IMPURITIES.—The same as of acetic acid, except so far as they are d by its dilution.
SE.—1 to 2 fluid drachms.

PREPARATIONS IN WHICH DILUTED ACETIC ACID IS USED.

B.P.

Acetum Scillæ. Liquor Morphinæ Acetatis.

cidum Aceticum Glaciale, B. and U.S.P.—GLACIAL ACETIC $HC_2H_3O_2$; 60. Concentrated acetic acid, corresponding to st 84 per cent. of anhydrous acid, $C_4H_6O_3$, B.P. Nearly or absolute acetic acid, U.S.P.

HARACTERS AND REACTIONS.—It crystallises when cooled to

34° F., and remains crystalline until the temperature rises above 48° F. Specific gravity 1·065 to 1·066, and this is increas by adding ten per cent. of water. At the mean temperature of t air it is a colourless liquid, with a pungent acetous odour, B.P

At or below 15° C. (59° F.) a crystalline solid; at a high temperature, a colourless liquid. When liquefied and as near possible to 15° C. (59° F.) it has the sp. gr. 1·056–1·058. properties are similar to those of acetic acid, and it is similar affected by reagents. U.S.P.

PREPARATIONS IN WHICH GLACIAL ACETIC ACID IS USED.

B.P.

Acetum Cantharidis. Mistura Creasoti.
Linimentum Terebinthinæ Aceticum (p. 516).

B.P. Acetum. VINEGAR.—An acid liquid, prepared fr malt and unmalted grain by the acetous fermentation.

CHARACTERS.—A liquid of a brown colour and peculiar odo

IMPURITIES.—A little sulphuric acid added to it is said to make it k better. Too much may be fraudulently added in order to increase its acid Lead from the vessels in which it is kept.

TESTS.—If ten minims of solution of chloride of barium be added t fluid ounce of the vinegar, and the precipitate, if any, be separated by filt tion, a further addition of the test will give no precipitate (limit of sulph acid). Sulphuretted hydrogen causes no change of colour (absence of lea

DOSE.—1 to 2 fluid drachms.

PREPARATION IN WHICH VINEGAR IS USED.

Emplastrum Saponis Fuscum.

ACTION AND USES.—When applied externally to the sk glacial acetic acid causes the formation of a large bleb. It is u to destroy warts and corns, and is sometimes employed a **vesicant** in cases of kidney-disease, where danger is apprehen from the use of cantharides. When the vapour of it is snif up the nose, it causes reflex contraction of the blood-vessels, raises the blood-pressure. It is therefore useful in lessen drowsiness and preventing syncope, or arousing patients fro (pp. 194 and 265).

Dilute acetic acid is applied to the skin in cases of headac and is used to sponge the surface and check perspiration w too profuse. It checks bleeding, and may be used to stop oo from leech-bites, or to wash out the mouth after the extrac of a tooth, and, when sniffed up the nose, sometimes arr epistaxis. It is occasionally employed in the form of an en to destroy ascarides.

When applied either alone or mixed with proof spirit o napkin to the vulva it is sometimes very useful in chec menorrhagia (*vide* p. 351).

Acidum Phosphoricum Concentratum, B.P., Acid

sphoricum, U.S.P. PHOSPHORIC ACID.—Phosphoric acid, HPO_4, with 33·7 per cent. of water, B.P. A liquid composed of per cent. of ortho-phosphoric acid (H_3PO_4; 98) and 50 per . of water, U.S.P.

CHARACTERS.—A colourless syrupy liquid, without odour, and strongly acid taste and reaction, sp. gr. 1·347. When heated ses water, and when a temperature of about 200° C. (392° F.) been reached, the acid is gradually converted into pyro- phoric and metaphosphoric acids, which may be volatilised red heat.

REPARATION.—Oxidising phosphorus by nitric acid. *Vide* p. 567.

EACTIONS.—When diluted, and supersaturated with ammonia, the test- on of magnesium gives a white precipitate. *Vide* also the reactions and of acidum phosphoricum dilutum.

PREPARATIONS CONTAINING FREE PHOSPHORIC ACID.

B.P.	U.S.P.
Acidum Phosphoricum Dilutum.	Acidum Phosphoricum Dilutum.
Syrupus Ferri Phosphatis.	

Acidum Phosphoricum Dilutum, B. and U.S.P. DILUTED SPHORIC ACID.—Concentrated phosphoric acid, 3 parts mixed water up to 20 parts; forming a solution corresponding to er cent. by weight of phosphoric anhydride, P_2O_5, B.P. Phosphoric acid 20 parts with 80 of water, U.S.P.

CHARACTERS.—A colourless liquid, with a sour taste and ngly acid reaction. Specific gravity, 1·08.

EACTIONS.—With ammonio-nitrate of silver it gives a canary-yellow pitate, soluble in ammonia and in diluted nitric acid. Evaporated, it s a residue which melts at a low red heat, and upon cooling exhibits a y appearance.

IPURITIES.—Phosphorous acid, meta- and pyro-phosphoric acids, nitric, uric, and hydrochloric acids, arsenic.

ESTS.—It is not precipitated by sulphuretted hydrogen (no metals), ide of barium (no sulphuric acid), nitrate of silver acidulated with nitric (no hydrochloric acid), nor by the solution of albumin (absence of meta- phoric acid which coagulates albumin). When mixed with an equal ne of pure sulphuric acid, and then introduced into solution of sulphate n, it does not communicate to it a dark colour (absence of nitric acid). d with an equal volume of solution of perchloride of mercury and heated, recipitate is formed (no pyro-phosphates). Its strength is estimated metrically by ascertaining the increase in weight which occurs in oxide d when phosphoric acid is poured on it, evaporated and ignited.

OSE.—10–30 minims.

SES.—Phosphoric acid may be used to allay thirst, like r dilute acids, in febrile states, and in diabetes. It may be n in larger doses than other mineral acids without deranging stion, and is therefore to be preferred to them in cases where quires to be given for a length of time, as in diabetes and linity of the urine. It is said to be useful in scrofula, and minish the growth of bony tumours.

Acidum Tartaricum, B. and U.S.P. TARTARIC ACI $H_2C_4H_4O_6$; 150.—A crystalline acid prepared from the ac tartrate of potassium.

CHARACTERS.—In colourless crystals, the primary form which is the oblique rhombic prism. It has a strongly acid tast and is readily soluble in water and in rectified spirit. When either solution, not too much diluted, a little acetate of potassiu is added, a white crystalline precipitate is formed.

20 grains neutralise { 27 grains bicarbonate of potassium. / 22 ,, ,, sodium. / 15½ ,, carbonate of ammonium.

PREPARATION.—*Vide* p. 566.

IMPURITIES.—Lead, copper, and iron from the vessels in which it is pr pared; calcium, or acid tartrate of potassium, from the substances used in preparation; racemic and oxalic acids.

TESTS.—An aqueous solution of the acid is not affected by sulphurett hydrogen (absence of metals), and gives no precipitate with the solution sulphate of calcium (no racemic or oxalic acids), or of oxalate of ammoni (no calcium). It leaves no residue, or only a mere trace, when burned w free access of air (no acid tartrate of potassium).

DOSE.—10 to 30 grains.

ACTION AND USES.—Used for cooling drinks.

Acidum Citricum, B. and U.S.P. CITRIC AC $H_3C_6H_5O_7.H_2O$; 210.—A crystalline acid prepared from lemo juice, or from the juice of the fruit of the lime, *Citrus Bergam*

CHARACTERS.—In colourless crystals, of which the right rho bic prism is the primary form; very soluble in water, less solul in rectified spirit, and insoluble in pure ether. The cryst dissolve in three-fourths of their weight of cold, and in half th weight of boiling water. The diluted aqueous solution has agreeable acid taste. When the solution is made by dissolvi thirty-four grains of the acid in one ounce of water, it resemb lemon-juice in strength and in the nature of its acid properti and, like lemon-juice, it undergoes decomposition and becon mouldy by keeping.

The quantity contained in ½ fl. oz. of this solution, viz.:—

17 grains neutralises { 25 grains bicarbonate of potassium. / 20 ,, ,, sodium. / 15 ,, carbonate of ammonium.

PREPARATION.—*Vide* p. 566.

IMPURITIES.—Lead and copper from the vessels in which it is prepa calcium used in its preparation, tartaric acid, which is cheaper, and is ap be mixed with or substituted for it, sulphuric acid or sulphates, oxalic aci

TESTS.—The aqueous solution is not darkened by sulphuretted hydro (absence of metals), gives no precipitate when added in excess to solution acetate of potassium (no tartaric acid), or of chloride of barium (no sulphat and if sparingly added to cold lime-water it does not render it turbid oxalic acid). The crystals leave no ash when burned with free acces air (no calcium).

DOSE.—10 to 30 grains.

PREPARATIONS CONTAINING FREE CITRIC ACID.

B.P.	U.S.P.
Succus Limonis.	Syrupus Acidi Citrici.
Syrupus Limonis.	,, Limonis.
Vinum Quininæ.	

U.S.P. Syrupus Acidi Citrici. SYRUP OF CITRIC ACID.—Citric d 8, water 8, spirit of lemon 4, syrup 980.

ACTION AND USES.—Citric acid, from the agreeable taste of its ution in water, is used for drinking in fever to allay thirst, her alone or with alkaline bicarbonates as effervescing drinks. is also used in scurvy, as it is supposed by some to be the in- dient to which lemon-juice owes its curative properties in that ease.

B.P. Oxalic Acid, Purified. $H_2C_2O_4 . 2H_2O$; 126.

Dissolve 1 pound of commercial oxalic acid in 30 fluid ounces boiling distilled water, filter the solution, and set it aside to stallise. Pour off the liquor, and dry the crystals by exposure the air on filtering paper placed on porous bricks.

TEST.—It is entirely dissipated by a heat below 350° F.

USES.—As a test.

Standard Solution of Oxalic Acid, B.P. and U.S.P.—63 grammes solved in water to 1000 c.c.

Acidum Boricum, B. and U.S.P. BORIC OR BORACIC ACID. BO_3; 62.

CHARACTERS. — Transparent, colourless, six-sided plates, ghtly unctuous to the touch, permanent in the air, odourless, ving a cooling, bitterish taste and a feebly acid reaction; in ution turning blue litmus-paper red and turmeric paper wn, the tint in the latter case remaining unaltered in presence free hydrochloric acid. The alcoholic solution burns with a me tinged with green.

PREPARATION.—*Vide* p. 566.

IMPURITIES.—Sulphates, chlorides, lead, copper, iron, &c., calcium and ium salts.

TESTS.—An aqueous solution of boric acid should not be precipitated by solutions of chloride of barium, nitrate of silver with nitric acid, sulphide mmonium, or oxalate of ammonium. A fragment heated on a clean inum wire in a non-luminous flame should not impart to the latter a sistent yellow colour.

DOSE.—5–30 grains.

OFFICINAL PREPARATION.

B.P.

Unguentum Acidi Borici.—Boric acid 1, soft paraffin 4, hard paraffin 2.

ACTION AND USES.—From its power of turning turmeric wn it is used as a test for this substance in rhubarb. It has power of destroying low organisms, and has therefore been d as an **antiseptic** application to wounds either in the form a solution (1 part in 20 of hot water) or of an ointment. The iseptic ointment originally recommended by Lister consisted

of a mixture of the acid (1) with white wax (1), paraffin (almond oil (2). This is rather hard, and a better ointm consists of the powdered acid (3), paraffin (5) and vaseline (1 The relative proportions of these may be varied according to temperature, more or less paraffin being added according as temperature is high or low. Boric acid lint is a useful antise dressing for small wounds and ulcers; and as an antiseptic fomentation in small abscesses, whitlows, &c. The powdered a mixed with starch, forms a useful dusting powder for infants, lessens the fœtor of perspiration. When given internally it is s to be occasionally useful in cases of vomiting in somewhat the sa way as sulphurous acid, and it has also been given along w ether in septic diseases. **Boro-glyceride**, discovered and paten by Barff, is made by heating 92 parts of glycerine with 6 boric acid. A solution of 1 in 40 of water is recommended a powerful antiseptic. It is used to preserve food, and as a lot for the treatment of wounds and in purulent ophthalmia.[1]

Acidum Chromicum, B. and U.S.P. CHROMIC ACID, Cr 100·4. It is an anhydride (not a true acid).

CHARACTERS.—Small, crimson, needle-shaped or colum crystals, deliquescent, odourless, having a caustic effect upon skin and other animal tissues, and an acid reaction. Very sol in water, forming an orange-red solution. Brought in con with alcohol, mutual decomposition takes place. When hea to about 190° C. (374° F.) chromic acid melts and at 250 (482° F.) it is mostly decomposed, with the formation of d green chromic oxide and the evolution of oxygen. On cont trituration, or warming with strong alcohol, glycerine, spiri nitrous ether, or other easily oxidisable substances, it is liab cause sudden combustion or explosion.

TESTS.—If 1 grain of chromic acid be dissolved in 100 c.c. of cold w and mixed with 10 c.c. of hydrochloric acid, the further addition of 1 c. test solution of chloride of barium should cause not more than a v turbidity (limit of sulphuric acid).

OFFICINAL PREPARATION.

B.P.

Liquor Acidi Chromici (acid 1, water 3 parts).

ACTION.—It has a great power of coagulating albumin, destroying low organisms, and as it parts very readily with oxy it oxidises organic matter and decomposes ammonia and sul retted hydrogen. It is thus a powerful deodoriser and di **fectant.** It is chiefly used as a **caustic** to destroy condylom and morbid growths in the mouth, larynx, or uterus, an phagedænic ulcers, poisoned wounds, &c. As a solution of 40, it has been especially recommended in syphilitic affectio

[1] *Extra Pharmacopœia*, Martindale and Westcott.

e tongue, mouth, and throat. As a lotion, it has been employed lessen fœtid discharges, and as an injection in ozæna, leucorœa and gonorrhœa. Care must be taken not to prescribe it th any substance to which it readily yields oxygen, such as ohol, glycerine, &c., as the mixture may explode spontaneously.

Acidum Carbonicum. CARBONIC ACID, CO_2; 44. Not offihal. It is very extensively used dissolved in water, as aërated ter, effervescing soda, potash, or lithia waters, or in wine, as ampagne.

PROPERTIES.—Colourless gas, heavier than air, causing a punnt feeling in the nostrils. Soluble in its own volume of water. solubility is increased by the presence of carbonates, or by essure, and when this is removed the gas escapes and causes e fluid to effervesce. The solution has an acid reaction. Carnates of magnesium, calcium, iron, &c., which are only sparly soluble in water, are dissolved with comparative ease by ter holding the gas in solution.

ACTION AND USES.—Like other acids, when applied to the **skin** acts as an irritant, but only slightly. After a prolonged apcation it causes a slight reddening of the skin and a feeling of rmth, which changes on the continuance of the application o burning or prickling, felt most where the skin is thin and hly supplied with nerves, as the external genitals, and this is t unfrequently accompanied by sweating. Carbonic acid baths . 469) are therefore sometimes used in catarrh and rheumatism a slight rubefacient to the whole skin, and to cause sweating, pecially where they can be obtained with ease, as in places where ere are springs containing much carbonic acid. These baths e.g. the ferruginous carbonic acid baths of various continental as—have an aphrodisiac action and may be useful in sterility.

Carbonic acid has been used as a stimulant to ulcers, either directing a stream of gas directly upon them or by applying poultice of yeast (Cataplasma Fermenti, B.P.), which in the ocess of fermentation causes a constant production of this gas.

Streams of carbonic acid have been applied to the eyes, ears, se, vagina, and rectum in catarrhal inflammation or ulceration these parts, in order to cause a slight hyperæmia of the parts d healing of the inflammation and to diminish pain, as it is pposed to act locally by diminishing the sensibility of the nerves the part.

In the **mouth** carbonic acid, like other acids, acts as a stiulant to the secretion of saliva, and so water containing it enches thirst better than pure water, and it is therefore often ed in feverish states (p. 360).

In the **stomach** it causes that slight pain which we confound th hunger, and a pleasant feeling of warmth just as on the in. Here too it most probably causes a slight hyperæmia, and

increased secretion. The greatest part leaves the stomach gaseous eructations, but a portion is absorbed and enters t blood. Its action is thus transient, and it produces no materi change in the chemical composition either of the contents or wa of the stomach. It increases the rapidity of the absorption water in the intestinal canal, as is shown by the fact that wat containing carbonic acid is excreted by the kidneys much soon after it has been drunk, than water without it. It relieves ir tation in the stomach, and allays or stops vomiting or naus and slight derangements of digestion. Carbonic acid is natura present in the intestines, in greater quantities in the large th the small. The carbonic acid is partly that which passes fr the blood into the intestine in interchange for the oxygen c tained in the air we swallow, and is partly formed by proces of fermentation which take place in the chyme.

That part of the carbonic acid which, after introduction i the stomach, passes into the blood is excreted by the lun Injected into the blood through a vein, it is likewise excreted the same way without causing an injury, unless it is injected such a quantity that some remains as gas undissolved in blood, and then it causes death mechanically, just like air, hindering the passage of blood through the lungs.

Poisoning by Carbonic Acid.—When it is inhaled, the or nary interchange between the carbonic acid in the blood and oxygen of the air is prevented, the gas in the blood accumula and the processes of oxidation in tissues being interfered w their functions are lessened or destroyed (p. 262).

The nervous system is first affected, and there is headac beating or singing in the ears, giddiness, flushing of the f Then there is a feeling of want of breath, tightness of the bre palpitation of the heart and great anxiety. If the CO_2 be inhaled, the pulse becomes slower, consciousness is lost, deliri or coma ensues, and death occurs with convulsions.

In poisoning by carbonic acid three stages may be dis guished, (1) dyspnœa; (2) convulsions; (3) paralysis.

During the first stage the carbonic acid appears to act a stimulus to the nerve-centres in the medulla, and especiall the respiratory and vaso-motor centres. In the second stag stimulates other motor centres (p. 237). In the third it paral them. In the first stage, that of dyspnœa, the respirations both rapid and deep, the inspiratory as well as the expira movements being increased. Both the inhibitory and the a lerating centres for the heart are stimulated, but the irrita of the vagus-roots preponderates, and the heart is generally s The vaso-motor centre in the medulla is also stimulated, and blood-pressure rises. Besides this the carbonic acid also stimul either subsidiary centres in the spinal cord (pp. 285 and 286 acts directly on the walls of the vessels themselves, causing t

ontract (p. 282), for the blood-pressure rises during inhalation arbonic acid even when the spinal cord has been divided below medulla. The vessels of the surface become dilated. This is ribed by Frankel to stimulation of a dilating centre. During second stage, that of **convulsions**, the respiration becomes e and more laboured, and the expiratory movements greater, il general convulsions occur. The blood-pressure rises still e, the heart becomes still slower, and the right ventricle more ended. In the third stage, that of **paralysis**, the inspiratory vements become more and more feeble, the intervals between m longer and longer, and finally they cease. The vaso-motor tre becoming exhausted the blood-pressure falls, and this fall robably aided by the action of the carbonic acid on the mus- r walls of the blood-vessels themselves (p. 282), as well as by kness of the heart. The heart generally continues to beat some minutes after respiration has completely ceased, and if ficial respiration be commenced before pulsation is entirely sted, life may generally be saved. Indeed, this is the case n when the cardiac pulsations are quite imperceptible, and refore in cases of death from asphyxia it is well to keep up ficial respiration if possible for an hour or even longer, not- nstanding the apparent hopelessness of the case. It should y be discontinued when a ligature tied moderately tightly ses no trace of congestion in the finger-tip after being on for minutes, and it ought to be supplemented by intermittent ssure on the cardiac region in order to stimulate the heart. se observations apply not only to poisoning by carbonic acid, to poisoning by all drugs which produce death by asphyxia, to death by drowning.

Post-mortem examination shows great venous congestion rywhere, the right side of the heart being distended with od, the brain much congested, with exudation and even ex- asation, and the blood extraordinarily dark.

TREATMENT.—In cases of poisoning by carbonic acid, as in ers or men who have been suffocated in wells or brewers' s, the great object is to get the blood oxygenated as quickly as sible. Get the person into the fresh air, and if the respiratory vements have ceased, dash cold water on the face and chest waken them reflexly. If this does not do, have recourse to ficial respiration. The next thing is to see that the heart is ting. When the right ventricle is distended with blood it omes paralysed, and if it does not begin to beat shortly after ficial respiration has been begun the jugular vein should be ned in order to relieve the dilatation. There are no valves ween the heart and the jugular vein (at least of any import- e), so the blood flows directly out and the distended ventricle lieved. One must, of course, be careful to prevent the access ir into the vein.

Acidum Hydrocyanicum Dilutum, B. and U.S.P.

LUTED HYDROCYANIC ACID. PRUSSIC ACID.—Hydrocyanic ac HCN, dissolved in water, and constituting 2 per cent. by weigh the solution, B.P. A liquid consisting of 2 per cent. of absol hydrocyanic acid (HCN ; 27) and 98 per cent. of water, U.S.

CHARACTERS.—A colourless liquid with a peculiar odo Specific gravity, 0·997. It only slightly and transiently redd litmus-paper.

REACTION.—Treated with a minute quantity of a mixed solution of phate and persulphate of iron, afterwards with potash, and finally acidul with hydrochloric acid, it forms Prussian blue.

PREPARATION.—By distilling yellow prussiate of potash with H_2SO_4.

Potassium Ferrocyanide — Everett's Yellow Salt

$$2K_4FeCy_6 + 6H_2SO_4 = 6HCy + K_2Fe_2Cy_6 + 6KHSO_4.$$

Half the cyanogen of the ferrocyanide passes over as hydrocyanic while a ferrocyanide of potassium and iron, often called Everett's yellow remains behind along with potassium sulphate.

IMPURITIES.—The most important is want of strength, so that when scribed it has not the desired effect. It loses strength when kept, and th fore the volumetric test is more important than in the case of other acid

TESTS.—A fluid drachm of it evaporated in a platinum dish leave fixed residue (no fixed impurities). It gives no precipitate with chlori barium (no sulphuric acid), but with nitrate of silver it gives a white cipitate entirely soluble in boiling concentrated nitric acid (no hydroch acid). 270 grains of it rendered alkaline by the addition of solutio soda, require 1,000 grain-measures of the volumetric solution of ni of silver to be added before a permanent precipitate begins to which corresponds to 2 per cent. of the real acid. Silver nitrate for soluble double cyanide of silver and sodium, and till all the hydrocyanic is used up no silver oxide is precipitated. $AgNo_3 + 2NaCy = NaN$ $NaAgCy_2$. The silver oxide reacts on the soluble compound, and decom it, so that a permanent precipitate of silver cyanide is formed. $2NaAgC$ $Ag_2O + H_2O = 2NaHO + 4AgCy$.

Standard silver test solution contains $\frac{1}{10}$ of an equivalent of $AgNO_3$, 1,000 grains therefore combine with $\frac{1}{10}$ of 2NaCy.

DOSE.—2 to 8 minims. As a lotion, 5–10 min. to 1 fl. o water, rose water, elderflower water, or almond mixture. addition of 1 fl. dr. of glycerine tends to prevent evaporation

PREPARATIONS. **B.P.**

Vapor Acidi Hydrocyanici.

Tinctura Chloroformi et Morphinæ (contains 1 vol. in 16).

B.P. Vapor Acidi Hydrocyanici. VAPOUR OF HYDROCYANIC ACID. 10 to 15 minims of diluted hydrocyanic acid with 1 fluid drachm of cold wat suitable apparatus, and let the vapour that arises be inhaled.

ACTION.—Hydrocyanic acid differs from all the other in having upon the organism an action peculiarly its own. one of the most powerful and most rapid poisons known destroys protoplasmic movement, kills infusoria, checks o tion, and arrests fermentation. When applied to the sk passes through the epidermis and paralyses the ends of sensory nerves below, so that the part becomes numb, and t

sation is diminished or destroyed. It is rapidly absorbed m the mucous membranes, and its action is the same when plied to any of them. A single drop of pure hydrocyanic acid ected into the eye, nose, or mouth of a small animal causes it fall down dead as if struck by lightning, and the same dose is ficient to cause the death even of a large animal. In these es the pupils are usually widely dilated, and the animal nerally utters a characteristic cry. When a smaller, but still al dose is given, the **poisoning** may be divided into three ges. In the **first** stage the **brain** is chiefly affected. There giddiness, uncertain gait, a few slow breaths, and then rapid piration and irregular action of the heart. These are suc- ded in the **second** stage by violent **convulsions**, tonic and nic. The head is bent backwards, the limbs are stiffly ex- ded, and sensibility is generally lost, although reflex action y still persist. In the **third** stage there is **coma**, complete s of sensibility, paralysis of the voluntary muscles, almost perceptible pulse, slow and weak respiration—the expiratory vements predominating, and death.

It is evident that these are the symptoms of rapid **asphyxia**. ey are very like those produced by carbonic acid, but much re rapid, and resemble those of poisoning by sulphuretted drogen. The convulsions occur only in warm-blooded animals, d not in frogs. In this point they resemble those of simple phyxia (p. 237). They differ from those of ordinary asphyxia, wever, in the fact that whereas the blood is venous when phyxial convulsions occur, the blood is arterial in colour when hydrocyanic acid convulsions occur. They differ also in not ng arrested by artificial respiration.

Death, in animals poisoned by hydrocyanic acid, is due sudden arrest of the **heart** in the more rapid cases, and to ralysis of the **respiration** in those which occur more slowly. consequence of this, the blood in the left side of the heart is nd to be arterial in cases of instantaneous death, but venous those instances where some minutes have been required. It stated that in the first stage of poisoning the blood is more erial than usual, though it afterwards becomes more venous. is has been said to depend upon diminution of the oxidising wer of the **blood** by the action of the acid. Hydrocyanic acid said to form a compound with hæmoglobin (cyan-hæmoglobin) ich does not readily give up its oxygen (p. 70). But this com- und is often not to be found in the blood of animals poisoned the acid, and the arterial appearance is more probably due to atation of the peripheral vessels allowing the blood to pass rough them rapidly, without undergoing the usual changes, st as it does in the sub-maxillary gland on irritation of the orda tympani nerve. This is rendered all the more probable the fact, that at the exact moment in which the blood becomes

of an arterial colour in the veins, the blood-pressure sudden falls in the arteries (Rossbach).

The **respiratory changes**, however, do seem to be also inte fered with, for in the first stage of poisoning the exhalation carbonic acid is diminished. As the diminution in the power the blood to give oxygen off is hardly sufficient to explain th and as the convulsions, apparently asphyxial in character, con on while the blood is still arterial, we may, with some probabilit suppose that the respiratory changes are due to the effect of t hydrocyanic acid in lessening internal respiration in the nervo tissues themselves (p. 239).


The stoppage of the **heart** in mammals is partly due to irrit tion of the vagus-roots in the medulla, and partly to paralysis the motor ganglia in the heart.

When placed upon the heart of a frog it arrests its beats, t the heart, at first, still contracts when irritated, though after short time its muscular irritability is also lost.

That its action in stopping the mammalian heart is par due to irritation of the vagus-roots is shown by the fact that, some animals, section of the vagi prevents the stoppage. T effect of hydrocyanic acid is, first to raise, and afterwards grea to depress the **arterial pressure**, and at the same time to sl the **pulse**. The slowing and paralysis of respiratory moveme which this acid produces are chiefly due to its action on t **respiratory centre** in the medulla oblongata. When direc applied to the medulla in the alligator it causes continuo powerful expiration and death, whereas when given in other wa considerable time is required for its action to be produced. appears to paralyse the **brain**, peripheral **afferent nerves**, th **spinal cord, motor nerves**, and **muscles**. That the affer nerves are paralysed before the cord is proved by the fact th when frogs are poisoned with prussic acid, and afterwards w strychnine, slight irritation of the sensory nerve-roots will ca tetanus, after irritation of the periphery has ceased to prod any effect.

This fact was observed by Von Kiedrowski, working un Reichert's direction. The same author observed the effect of local application of hydrocyanic acid in paralysing muscle a nerve, by removing the soft parts and bones from the lower p of the thigh of a frog, leaving the leg attached to the body only nerves (Fig. 166). The grastrocnemius and crural muscles w then separated, and the gastrocnemius with its nerve was immer in aqueous humour diluted with water, and the crural mus with their nerves in a similar liquid to which hydrocyanic a had been added. After four hours the crural muscles did not c tract on direct irritation, but the gastrocnemius did so read This showed that the acid had paralysed the **muscles**. Irritat of the gastrocnemius, of its nerve *f g*, or of the sciatic nerv

sed reflex movements in the body of the frog, but irritation he crural muscles caused no such reflex movements, showing t the ends of the sensory nerves within them had been para- d. When the sciatic *a* was irritated the crural muscles did contract, but the gastrocnemius did. The poison probably alyses motor nerves as well as muscles, for it is found that muscles contract, though feebly, on direct irritation, after y have ceased to respond to the strongest irritation of the or nerves.



66.—After Kiedrowski. Diagram to show the effect of hydrocyanic acid when applied locally. the sciatic nerve; *b*, thigh of a frog; *d* and *e*, branches of sciatic going to the crural muscles; *g*, branch going to the gastrocnemius.

Uses.—Hydrocyanic acid is used externally in order to lessen ing in skin-diseases, and is best applied in combination with erine. It is chiefly employed internally to diminish irrita- y of the stomach, and to relieve vomiting, also pain in the nach or intestines, and functional palpitation of the heart ndent on dyspepsia. It is also used to relieve cough in cases ronchitis, phthisis, asthma, and whooping cough. It has etimes been employed, though with doubtful effect, in chorea, epsy, and hysteria. Its vapour is sometimes used to lessen ability of the respiratory passages and cough.

Acidum Lacticum, B. and U.S.P. Lactic Acid. $HC_3H_5O_3$; —A liquor composed of 75 per cent. of absolute lactic acid 25 per cent. of water.

Characters.—A nearly colourless syrupy liquid, odourless, ng a very acid taste, and an acid reaction. Sp. gr., 1·212. s freely miscible with water, alcohol and ether, but nearly luble in chloroform. It is not vaporised by a heat below C. (320° F.); at higher temperatures it emits inflammable urs, then chars, and is finally entirely volatilised, or leaves a trace of residue.

Preparation.—By adding chalk to sour milk and decomposing the lactate lcium with sulphuric acid (*vide* p. 566).

IMPURITIES.—Hydrochloric acid, sulphuric acid, sarcolactic acid, lead iron, sugars, glycerin, organic impurities.

TESTS.—When diluted with water, lactic acid should afford no precipitat with test solutions of nitrate of silver, chloride of barium, sulphate of copper nor with sulphide of ammonium after the addition of excess of water of am monia. It should not reduce warm test-solution of potassio-cupric tartrate When mixed and heated with excess of hydrated zinc oxide and extracted wit absolute alcohol, the latter should not leave a sweet residue on evaporation Cold concentrated sulphuric acid shaken with an equal volume of lactic aci should assume at most only a pale yellow colour.

DOSE.—1 to 3 fl. dr. per diem, diluted or sweetened, lik lemonade.

When used as a **caustic** it may either be applied on lin covered with gutta percha or as a paste of silica saturated wit the acid. After being left on for 12 hours it should be washe off, and the application renewed as necessary.

PREPARATION.

B.P.	DOSE.
Acidum Lacticum Dilutum (acid 3, water up to 20).....	½–2 fl. dr.

ACTION.—It has been employed in a solution of 1 part to 5, t dissolve the false membrane in croup and diphtheria. In case of dyspepsia it is used to aid digestion in somewhat the sam way as hydrochloric acid, and it has been given also to lesse the alkalinity of the urine and prevent phosphatic deposits. I diabetes it has been employed with considerable success alon with an exclusively meat diet in doses of ½ oz. in 1 pint of wat daily, though it is said to have given rise to rheumatism in diabetic patient. Buttermilk has been recommended in place it, but the difficulty of obtaining this in towns is very great.

Acidum Oleicum, B. and U.S.P. OLEIC ACID.—$HC_{18}H_{33}O$ 282.

CHARACTERS.—A yellowish, oily liquid, gradually becomi brown, rancid and acid, when exposed to the air; odourless, nearly so, tasteless, and, when pure, of a neutral reactio Sp. gr., 0·800 to 0·810.

PREPARATION.—It is obtained by adding lead oxide to almond oil, whi forms an oleate of lead or lead soap, and decomposing this by hydrochlo acid. Or by decomposing palm oil by superheated steam, and separati from any solid fats by pressure (*vide* p. 566).

SOLUBILITY.—Oleic acid is insoluble in water, but completely soluble alcohol, chloroform, benzin, benzene, oil of turpentine, and the fixed oils.

At 14° C. (57·2° F.) it becomes semi-solid, and remains so until cooled 4° C. (39·2° F.), at which temperature it becomes a whitish mass of crysta

TESTS.—At a gentle heat the acid is completely saponified by carbon of potassium. If the resulting soap be dissolved in water and exac neutralised with acetic acid, the liquid will form a white precipitate with te solution of acetate of lead. This precipitate, after being twice washed w boiling water, should be almost entirely soluble in ether (absence of m than traces of palmitic and stearic acids). Equal volumes of the acid and alcohol, heated to 25° C. (77° F.) should give a clear solution, without se rating oily drops upon the surface (fixed oils).

Uses.—Oleic acid is employed only for the preparation of tes, which are not only elegant preparations, but appear to more readily absorbed than other ointments.

Preparations.

B.P.

leatum Hydrargyri (yellow oxide of mercury 1, oleic acid 9). This oleate be prepared with half the above proportion of oleic acid, the remainder being d just before, or not long before, the oleate is dispensed.
leatum Zinci (oxide of zinc 1, oleic acid 9).
nguentum Zinci Oleati (oleate of zinc 1, soft paraffin 1).

U.S.P.	AMOUNT USED.
leum Hydrargyri. Oleate of Mercury (Hydrargyri Oxidum Flavum, 1 part; Acidum Oleicum, 9 parts)	10 min., externally.
leatum Veratrinæ. (Veratrinum, 2 parts; Acidum Oleicum, 98 parts)	6–25 gr., externally.

Acidum Arseniosum.—*Vide* p. 719.
Acidum Benzoicum.—*Vide* p. 964.
Acidum Carbolicum.—*Vide* p. 813.
Acidum Chrysophanicum.—*Vide* p. 909.
Acidum Gallicum.—*Vide* p. 1033.
Acidum Meconicum.—*Vide* p. 846.
Acidum Pyrogallicum.—*Vide* p. 819.
Acidum Salicylicum.—*Vide* p. 819.
Acidum Tannicum.—*Vide* p. 1031.

CHAPTER XXIV.

METALS.

GENERAL CLASSIFICATION OF THE METALS.

It has already been mentioned (p. 20) that Mendelejeff's classi- cation of the elements, although it gives us the outlines of a tr natural classification, is not at present perfect, inasmuch as separates members of natural groups, such as those of the earth metals. In regard to this classification it must be borne in mi that by it the elements are arranged in groups according to the atomicity, and this is not in all cases determined. A glance the table (p. 19) will show this, for copper, silver, and gold a there included both in Group I., containing monad metals, a in Group VIII. But the commonest and most stable compoun of copper, such as cupric oxide or cupric sulphide, appear to sh that it is a dyad rather than a monad. Silver, also, though appears like copper in Groups I. and VIII., may also be a dya while gold forms two series of compounds, in one of which it monad, and in the other triad. In the classification which have adopted, I have followed Mendelejeff's tables as modifi by Watts, but I have modified them somewhat, in order not separate metals having a similar physiological action.

Class I.—MONAD METALS.[2]

Group I.—Alkalis—Potassium, Sodium, Lithium, *Cæsiu* *Rubidium*.

II.—Ammonium.

---

[1] The formula of argentous oxide is Ag_2O, and if this formula be correct, silver be a monad, oxygen must be a tetrad; but if silver be a dyad, argent oxide may be represented as $\begin{matrix} Ag-Ag \\ Ag-O-Ag \end{matrix}$. (Fownes' *Chemistry*, by Watts, 1 ed. vol. i. p. 369.)

[2] The metals whose names are printed in italics are not officinal.

Class II.—DYAD METALS.

Group I.—Metals of the alkaline earths—Calcium, *Strontium*, Barium.

(Appendix.) Metals of the earths—Aluminium, Cerium, *Beryllium*, *Zirconium*, *Thorium*, *Lanthanum*, *Didymium*, *Yttrium*, *Erbium*.

II.—Magnesium.

III.—Copper, Zinc, Silver, *Cadmium*.

IV.—Mercury.

Class III.—TRIAD METALS.

Thallium, *Iridium*, *Gallium*.

Class IV.—TETRAD METALS.

Tin, Lead, *Titanium*.

Class V.—PENTAD ELEMENTS.

Nitrogen, Phosphorus, Arsenic, Antimony, Bismuth, *Vanadium*, *Tantalum*, *Niobium or Columbium*.

Class VI.—HEXAD METALS.

Chromium, *Uranium*, *Tungsten*, *Molybdenum*.

Class VII.—HEPTAD METALS.

Manganese.—*Vide* next group.

Class VIII.

Group I.—Iron metals. Iron, Nickel, Cobalt, Manganese.

II.—Platinum, Gold.

General Tests for the Acid Radicals in Metallic Salts.—The same acids occur in the salts of different metals, the tests for their presence are described again and again in the Pharmacopœias. In order to save repetition, it may be advisable to give here in a tabular form the tests for the different acids. It is to be remembered that the same tests apply to the simple ignition of a metallic salt, and to its detection as an impurity in other substances. The tests are generally applied to solutions of the salt in water.

Salt	Reagent	Reaction
Acetate * . .	Sulphuric acid . .	Vapour of acetic acid given off and recognised by its smell.
,,	Ferric chloride .	Deep red colour.
Borate . .	Sulphuric acid . .	The saturated solution causes deposition of shining scales, which give a green colour to the flame of alcohol.
Benzoate * .	Dilute solution of ferric sulphate	Flesh-coloured precipitate.
Bromide . .	Disulphide of carbon and chlorine water	If disulphide of carbon be poured into a solution of the salt, the chlorine water added drop by drop, and the whole agitated, the disulphide will acquire a yellow or yellowish-brown colour. (If iodine be present there will be a violet tint.)
Carbonate .	Acid . . .	Causes effervescence.
Bicarbonate .	,, . . .	Causes effervescence more abundant than in the case of the carbonate. With solution of mercuric chloride bicarbonates give a white, and carbonates a yellow precipitate.
Citrate * .	Calcium chloride .	The solution remains clear, but deposits white precipitate on boiling (calcium citrate being less soluble in hot than in cold water).
,, . .	Sulphuric acid and heat	Is charred and evolves the odour of acetic acid.
Chloride . .	Nitrate of silver .	White precipitate, soluble in ammonia, insoluble in hydrochloric or nitric acids.
Hypophosphite .	Heat . . .	Heated in a dry test-tube it evolves phosphoretted hydrogen, which takes fire spontaneously, and burns with a bright flame.
,, .	Nitrate of silver .	White precipitate, which rapidly turns brown and black.
,, .	Hydrochloric acid and mercuric chloride	White precipitate of calomel, and on further addition separation of metallic mercury.
Hyposulphite .	Sulphuric acid .	Gives rise to the smell of burning sulphur, and causes white precipitate of sulphur (bisulphite and sulphite give no precipitate).
Iodide . .	Disulphide of carbon and chlorine water	If disulphide of carbon be poured into a solution of the salt, then chlorine water added drop by drop, and the whole agitated, the disulphide of carbon will acquire a violet colour.
,, . .	Starch water, starch paste, or gelatinised starch, with chlorine water	Blue colour in the cold, discharged by boiling.
Nitrate . .	Sulphuric acid and copper	Nitrous fumes.
,, . .	Sulphuric acid and solution of ferrous sulphate	When sulphuric acid is added to a solution containing a nitrate, and a solution of ferrous sulphate is carefully poured over it, a dark colour appears at the junction of the two liquids.

Salt	Reagent	Reaction
xalate* . .	Calcium chloride .	White precipitate. In applying the test to cerium and iron, their salts must be decomposed by boiling with potash or soda. The oxide of cerium or iron is removed by filtration, and the reagent applied to the filtrate, which contains oxalate of potassium or sodium.
hosphate .	Chloride of ammonium, ammonia, and sulphate of magnesium	White precipitate.
hosphide .	Sulphuric or hydrochloric acid	Evolves phosphoretted hydrogen.
alicylate * .	Ferric salts . .	Intense violet colour.
ulpho-carbolate	Ferric chloride .	Violet colour. This salt can be distinguished from the salicylate by heat, when it gives off inflammable vapours having the odour of carbolic acid.
ulphate . .	Barium chloride .	White precipitate, almost insoluble in nitric acid.
ulphide . .	Mineral acids, e.g. sulphuric or hydrochloric	Gives off sulphuretted hydrogen.
ulphite . .	Ditto . .	Gives off sulphurous acid (has neutral or feebly alkaline reaction).
isulphite .	Ditto . .	Ditto (has acid reaction).
artrate* . .	Acetic acid in presence of potash	White crystalline precipitate of bitartrate.
„ . .	Sulphuric acid and heat	Is charred and evolves the odour of burnt sugar.
„ . .	Nitrate of silver .	White precipitate, becoming black on boiling.
itartrate* .	Nitrate of silver .	Solution rendered neutral by potash, gives with the reagent a white precipitate becoming black on boiling (very sparingly soluble in water : is thus distinguished from neutral tartrate, which is readily soluble).
„ . .	Sulphuric acid and heat	Same reaction as tartrate.

* In the preceding table the salts of organic acids marked * when ignited in rucible or on a piece of platinum foil, become charred and oxidised, leaving a idue which consists of carbonate. This is black from the presence of carbon, ignition has not been carried sufficiently far to convert all the carbon into carnic acid. This residue gives the reaction of a carbonate, effervescing with acids, l it is frequently convenient to convert the carbonate into chloride, before plying tests for the base.

Class I.—MONAD METALS.

Group I.—METALS OF THE ALKALIS.

Lithium, Sodium, Potassium, *Rubidium*, *Cæsium*.

Group II.—AMMONIUM.

I have omitted silver and gold from this class, because bot their physiological actions and physical properties appear t show that they do not belong to it. I have put ammonium int a group by itself and separated it from the other members of thi class, because it differs from them in being a compound and n an element; in being volatile; and in having an entirely differer physiological action.

General Characters.—They are all powerful bases and hav a great affinity for oxygen. The oxides of the first group a non-volatile, and are sometimes termed fixed alkalis, whi ammonia is volatile. They all have a strong alkaline reactio neutralising acids readily, turning red litmus-paper blue, ar turmeric paper brown.

General Reactions.—They are not precipitated from sol tions by the successive addition of (1) hydrochloric acid, (hydrogen sulphide, (3) ammonium sulphide, (4) ammoniu carbonate, and (5) sodium phosphate.

General Physiological Action.—The alkalis are of gre physiological importance, and salts of **potassium** and **sodium** for a large proportion of the saline constituents of the body. The two elements are differently distributed, potassium being chie found in solid tissues, while sodium is more abundant in the fluic They are found as carbonates, bicarbonates, chlorides, phosphat and sulphates. The proportion of these salts in the body is, ho ever, very different, as are also their uses in the economy. T chlorides are by far the most abundant, and sodium chlori may be looked upon as the most important constituent of t nutritive fluids in which all the tissues of the body are bath But while sodium chloride forms the saline basis of these fluic the other constituents are indispensable for the continued life the tissues. All the fluids of the body are alkaline, and dea occurs whenever the alkalinity is diminished below a cert point, even though the fluids and tissues are far from having acid reaction. Such a reaction is only observed in the tiss after death. The importance of the different saline constitue in nutrition has been most fully worked out in the case of t frog's heart (p. 305 *et seq.*).

In the case of the **heavy metals**, which are not normal c stituents of the body, the action of their **salts** depends alm

tirely on the **base** and only slightly on the **acid** with which it combined. In the case of the **alkalis**, however, this is not so, action of their salts depending much on the **acid**.

In consequence of this it is necessary in considering the ysiological action of salts of the alkaline metals to divide them o at least three groups :—

1. Alkaline salts, hydrates, carbonates, and bicarbonates.
   (Sub-groups—Salts of organic acids, acetates, citrates, tartrates).
2. Chlorides.
3. Sulphates and other salts which are slowly absorbed.

General Action of the Alkaline Group.—Alkaline salts e their activity diminished by combination with carbonic or anic acids. The hydrates have an intense **local action** on the sues ; and the carbonates have an action, the same in kind, much less in degree. In the case of the bicarbonates it still further diminished, and in the acetates, citrates, and trates it is absent. The hydrates of potassium and sodium solve **horny tissues** such as the epidermis. They combine h **albumen** and form a soluble alkali-albuminate.

When applied to the **skin** the hydrated alkalis, which have a at affinity for water, withdraw it from the tissues and form a ution which softens and partly dissolves the epidermis and n acts on the softer textures below, combining with and dis- ving them. Round the part thus killed inflammation sets in, l a slough separates. The rapidity with which they absorb ter and form a solution which flows readily over adjacent rts, where its action is injurious, is an objection to their appli- ion, and the part actually cauterised by them should always less than the part we wish to destroy. From this very perty of widely destroying the tissues over which they flow, through which they soak, they are admirably adapted for plication in cases where we desire this effect, as in cauterising soned wounds.

When applied as **caustics** to unhealthy sores, cancer, &c., ir action is sometimes limited by adding lime and forming the called Vienna paste (p. 346). The water which they withdraw m the tissues is sucked up by the lime, forming a solid drate and preventing the caustic from becoming too fluid and nning over other parts. When less concentrated they may ly irritate the surface sufficiently to produce exudation, but y generally soften or dissolve the epidermis so much that sicles do not form well. When still more diluted they may use only congestion or redness of the skin. They are then d to act as **rubefacients**. This rubefacient action may be ed for the purpose of relieving troublesome itching in skin- eases, or to produce derivation from other parts.

Ammonia does not dissolve the epidermis, and so, unlike potash or soda, it does not act as an immediate caustic, but only passes through the epidermis and irritates the skin below causing lymph to be effused between it and the epidermis, and thus acting as a **vesicant**. It may, however, act as a caustic if its evaporation is prevented and it is applied too long, the irritation then becoming so great as to lead to suppuration, or even to sloughing of the part.

From their great solvent power, and especially their power of dissolving greasy substances, alkalis are used for **cleansing** the skin, but when used alone they very frequently produce irritation and we therefore generally employ them in the form of soap, or in the form of those salts which have only a very slight alkaline character, such as borax.

In the **mouth** they neutralise any acid present. They may thus relieve toothache due to irritation of the exposed nerve in a carious tooth or of the roots of the teeth close to the gums by acid secretions. A dilute solution of sodium bi-carbonate as a wash to the mouth frequently relieves soreness of the teeth, or headache depending on dental irritation, and prevents injury from acid tonics. Alkalis are used in the shape of borax to heal aphthæ in the mouth and as soap for cleaning the teeth.

In the **stomach** they increase the amount of gastric juice secreted; and where this is deficient and the food lies heavy and is digested slowly and with difficulty, they should be given before a meal or just at its commencement, either in the form of a medicinal mixture or as aërated potash or soda water. The amount of acid secreted by the stomach after their introduction is sufficient to neutralise them pretty rapidly, and probably only the caustic alkalies which act very rapidly have time to produce any local action before they are neutralised, unless large quantities have been ingested. Where there is a large amount of mucus on the surface of the stomach it will both hinder the exit of the gastric juice from the follicles and the entrance of the peptone from the stomach into the blood. Caustic alkalies have a great power of dissolving mucus. They probably do this to some extent before they are neutralised, and this may be the reason why we occasionally find that they are of great service when a corresponding amount of their carbonates does little or no good. From the effect they produce on the secretion of gastric juice, alkalis in small doses are said to act as **gastric stimulants** (p. 363).

When the amount of acid in the stomach is too great, either because too great a proportion of it has been present in the gastric juice, or because it has been generated by the decomposition of food, digestion goes on slowly, and burning acid eructations take place after meals. In such cases we give alkalis to neutralise the excess and to restore the proportion of acid in the stomach to its normal. They are then said to act as **antacids** (p. 369).

Alkalis are serviceable as **antidotes** in poisoning by acids, tals, and alkaloids. They neutralise the acids, they precipi- e the metals as insoluble oxides, and they render alkaloids less ible by taking away the acid with which they are generally bined. They thus retard their absorption and afford time the use of other means.

The chyme from the stomach is normally acid, and will there- act as a stimulus to the expulsion of bile from the gall-bladder. s partly neutralised by the bile and pancreatic juice, but erally remains acid throughout the small **intestines** and act as a stimulus to the secretion of intestinal juice. If it neutralised by alkalis in the stomach, this stimulus will be oved and digestion consequently impaired. Many substances thus pass through the intestinal canal undigested, which unts to the same thing as if less food had been taken.

Through this derangement of the digestion the blood will be- e poorer in solids, the person will become emaciated, the fat naturally be first absorbed, and, along with this, perhaps hological formations may also disappear.

The excessive use of alkalis or their carbonates is thus inju- s, and their employment to reduce obesity may, unless care- y watched, be followed by serious consequences, like the use of ls for a similar purpose (p. 569).

Caustic alkalis injected directly into the blood cause death in w minutes, probably from formation of alkali-albuminate he blood and its consequent coagulation. Shortly after death blood is found coagulated. Smaller amounts taken in from stomach will to some extent increase the alkalinity of the od, but are rapidly separated by the **kidneys**. They cause st, and probably the larger amount of water drunk in conse- nce is one cause of the diuresis they produce. From their er of dissolving fibrin outside the body, they have been given cute rheumatism to prevent fibrinous deposits on the heart. s not certain that the amount we can introduce into the blood hout injury to the patient has this effect.

After small doses of liquor potassæ the urea and sulphuric d in the urine are increased, and Parkes therefore thinks that tissue-change of the albuminous substances is increased. alis are therefore classed as **alteratives** (p. 414).

They are used both to increase the amount of water passed d to diminish its acidity if this be excessive. They are there- e classed amongst **diuretics** (p. 432), and **remote antacids** 370).

General Action of the Group of Chlorides.—Chloride of ium is not only one of the most abundant saline constituents he animal body, but it is one of the most important **solvents** albuminous substances. Water will dissolve albumins proper, globulins are insoluble in it, and are precipitated by it from

solutions. Dilute solutions of chloride of sodium on the contra dissolve both albumins and globulins. From this action of wat on albuminous substances it is very irritating when applied a cut surface, or to the delicate mucous membrane of the no while muscles dipped in it swell up, and pass into a state of rig Weak solutions of chloride of sodium, on the other hand, have irritating action, and may be applied to cut surfaces or muco membranes without causing pain, and to muscle and nerve withc producing any injurious effect. A solution of the strength of 0· per cent. is the one usually employed in physiological experime as a basis for the nutritive fluid in artificial circulation throu the frog's heart or vessels, and as a solvent for alkaloids whi are to be injected into the lymph-sac of the frog, in order to av the local irritation which the injection of a watery solution wo produce. A solution of this strength is often called 'normal s solution' in physiological treatises.

While dilute solutions of chloride of sodium are ready solve of albuminous substances and are non-irritating, sodium chlori in substance or in concentrated solutions, precipitates globuli withdraws water from the tissues, and acts as an exceedin powerful irritant to cut surfaces, mucous membranes, musc and nerve. Common salt taken in a large quantity at once v irritate the **stomach** and cause vomiting. It is **absorbed** w great rapidity, but it is also excreted so rapidly that it produ no definite symptoms of irritation in any part of the bo excepting that part of the **nervous system** by which the sen tion of thirst is perceived. This sensation becomes so urg when much salt has been taken that any risk will be encounte in order to gratify it. Should it be impossible to obtain fr water, other parts of the nervous system become involved, a travellers whose supply of water has failed in the desert, shipwrecked sailors who have drunk sea-water, have beco delirious. It is difficult to say, however, how far the delirium due to the direct irritant action of sodium chloride on the bra as many other factors may concur in its production. Un ordinary circumstances, the thirst occasioned by sodium chlor after its absorption, causes as much water to be drunk as allow the salt to be excreted by the **kidneys**, leaving the prop tion both of salt and water in the body nearly the same as bef During its stay in the body the salt does not appear to alter composition of the **tissues**, and the chief alterations produ by it are probably due to its action on the solubility of al minous substances and on the processes of osmosis between intercellular fluid and blood, and the circulation of lymph in tissues. In consequence of this, sodium chloride increases tiss change, as is shown by an increase in the amount of u excreted. A similar increase, however, occurs when the quant usually taken is diminished, the amount of water daily consu

aining the same. The alteration here is probably also due to eased rapidity of the circulation of fluid through the tissues t), but it may also be due in part to the different solubilities lbuminous substances in solutions of sodium chloride of dif- nt strengths. Certain albuminous tissues may thus be ted by one proportion of salt in the blood, others by another, hat increase and diminution of the normal proportion of um chloride may increase tissue-change in the body as a le, though not in the same tissues. The **proportion** of ride of sodium in the body is not always the same. It nds on the quantity taken daily, and may be increased or inished within certain limits. If a definite quantity be taken y for some time, the same quantity will be found in the urine, hat the amount present in the body is constant. If the ntity consumed be now increased, no increase takes place in excretion for about three days, a **storage** of salt taking place ne body. After about three days the quantity excreted daily ne urine will again be found equal to the quantity daily taken, amount present in the body remaining constantly at the er level. If the quantity daily taken be now diminished, liminution takes place in the quantity excreted for about e days, and then the quantities daily taken and excreted n correspond. The amount stored up at first is now gone, the proportion of salt in the body is now again reduced to wer level.[1]

ncreased consumption of sodium chloride not only increases quantity of it and of urea in the urine but increases also the **retion** of **potassium** salts.

On the other hand, potassium salts also increase the excre- of sodium. Between salts containing no chlorine, such as onate or phosphate, and the sodium chloride in the blood, a le decomposition takes place, potassium chloride, and sodium onate or phosphate, being formed. These newly-formed are unnecessary for the organism, and are excreted in the e along with the unaltered remainder of the phosphate or onate administered. Considerable quantities both of chlorine sodium may thus be removed from the organism. In con- ence of this, herbivorous animals and people living chiefly vegetable diet, and who thus consume considerable quanti- of potassium salts, feel the need of sodium chloride greatly, on the American prairies the herds of buffaloes travel lreds of miles to visit the salt licks. Beyond a certain point, ever, the excretion of sodium chloride is not increased by ssium salts, and when the quantity of sodium salts in the body w, excretion is not increased at all.

When an abnormal quantity of fluid is present in the tissues,

[1] Ludwig, *Manuscript Notes of Lectures*, 1869–1870.

as in dropsies, an increase in the saline constituents of the blo may cause its absorption, especially if the quantity of wat drunk by the patient be limited. It is probable that in additi to their diuretic action the alkaline salts affect the nutrition the tissues themselves, and that salts of potassium are bet than those of sodium in cases of dropsy, because of their acti on the tissues.

General Action of the Sub-Group of Sulphates, &c. This group contains salts which are sparingly absorbed, such sulphates, phosphates, and bitartrates. That they are sparing absorbed is shown by the fact that when administered interna they only appear to a small extent in the urine. They usua act as **purgatives**, but if from any cause their purgative acti should be prevented, and they remain long in the intesti absorption will occur, though slowly. In herbivorous anima which have a much longer intestinal canal than carnivora, lar doses of these salts are required to produce a purgative acti The mode of action has already been discussed (p. 390 *et seq.*)

Comparative Action of the Alkaline Metals.—As the act of the base appears to be less modified by the acid radical in case of the chlorides than of other salts of the alkaline met they are better adapted for experiments on the comparat action of the members of this class.

Group I.—The chlorides of lithium, sodium, potassiu rubidium, and cæsium produce in **frogs** gradually increas torpor, paralysis, and death. The chief action appears to be the **spinal cord**, which is **paralysed**, a slight primary excitem occurring in the case of potassium and rubidium. Lithium potassium paralyse also the ends of the **motor nerves**. Sodi does so also, though to a much less extent. Cæsium and rubidi do not do so, excepting when given in very large doses.

The contractile power of **muscle** is almost always diminis by lithium, unaffected by sodium, and increased by the ot members of this group in small or moderate doses. La quantities of potassium diminish both the irritability and tractile power of muscle voluntary and involuntary.

In frogs the **heart** becomes weaker and finally stops diastole.

Group II.—Ammonium differs entirely from the member the first group in the symptoms it produces. While they p lyse the spinal cord with little or no previous excitement, cau torpor and death, ammonia at first **stimulates** the cord, ducing tetanic convulsions. The action of ammonium is co derably modified by the acid radical with which it is combi All the ammonium salts have an action on the **spinal c motor nerves**, and **muscles**, and, in advanced poisoning, p **lyse** these structures.

They do not, however, affect all these structures with e

ness. The organ first affected, and consequently (p. 26) ymptoms of poisoning, vary with the salt employed. Some affect the spinal cord first, others the motor nerves. Am- a and ammonium chloride produce tetanus. The bromide ices hyperæsthesia with some clonic spasm, passing into us, which, however, comes on very late.

he sulphate also produces hyperæsthesia and clonic spasms, rarely tetanus. The phosphate produces paralysis without ulsions, either clonic or tonic, the only indication of any con- nt action being slight twitches accompanying movements e hind limbs before reflex action has ceased. The iodide ices progressive paralysis and no tetanus. The brain ap- s to be affected before the spinal cord. This is shown by rog croaking when stroked, as it does after removal of the ral hemispheres, and by the reflex from the conjunctiva g before that from the limbs.

mmonium salts appear to form a **series**, at one end of n the members **stimulate** the spinal **cord** and have no ed paralysing action on the motor nerves, while those at ther end have no marked stimulating action on the cord, on the contrary, have a marked **paralysing** action both on ord and on **motor nerves.** At the stimulating end of this s are ammonia and ammonium chloride, and at the para- g end ammonium iodide; whilst the bromide, phosphate, sulphate lie between.

Group I.—METALS OF THE ALKALIS.

POTASSIUM. K; 39.

ENERAL SOURCES OF POTASSIUM SALTS.—The chief source tassium salts is the ash left by the combustion of plants or ; but there are two subsidiary sources, viz. nitrate of potas- , which is found native, and bitartrate of potassium, which posited from wine in the process of fermentation.

ENERAL REACTIONS OF POTASSIUM SALTS.—In analysis, ssium is distinguished from all other bases, excepting mag- um, sodium, and ammonium, by not being precipitated by onium sulphide nor carbonate of ammonium. The positive ions by which its presence is ascertained are—(1) its preci- ion when converted into an acid tartrate; (2) its precipita- by perchloride of platinum; (3) the violet colour it imparts me.

he sparing solubility of the **acid tartrate** is the test which ed in the U.S.P. to distinguish all salts of potassium. The nt employed is tartaric acid in the case of potassium ate, carbonate, and bicarbonate; in the case of the tartrate otassium and sodium, acetic acid is used. In the case of

most other salts a saturated solution of bitartrate of sodiu added to their aqueous solution. Potassium chlorate is calc and the reagent added to a solution of the residue. Pot sulphurata is decomposed by boiling with hydrochloric acid, sulphur removed by filtration, and the filtrate neutralise soda before the reagent is applied. No test for potassiu given in the case of potassium bitartrate or permanganate.

This test is only employed in the British Pharmacopœi four instances—viz. neutral tartrate, acetate, bromide, iodide. In the case of the neutral tartrate the test is applie adding a small quantity of acetic acid, and thus producing tartrate. In the case of the acetate, bromide, and iodide, i applied by adding tartaric acid. On the addition of **perchlo of platinum** to chloride of potassium a double chloride of po sium and platinum is formed, and falls as a sparingly sol pale-yellow precipitate. If the potassium salt be other tha chloride, part of the chlorine in the platinum salt is used u convert the potassium into a chloride, and thus loss of expensive reagent takes place. To avoid this loss hydroch acid is always to be added before the addition of the plati salt. This reaction is not used for the bromides and iod because bromide and iodide of platinum would be formed an loss of the reagent would occur. In testing some potass salts, **modifications** are observed in the mode of applying test. Before applying it to the chlorate the salt is calci oxygen is thus driven off, and the residue, consisting of chl of potassium, does not require the addition of hydrochloric a The permanganate is also calcined, but the potash containe the residue, after being dissolved out by water from its admix with manganese dioxide requires to be treated with acid as u In the case of the sulphide the hydrochloric acid causes evolution of hydrogen sulphide, which must be removed by ing, and causes also the precipitation of sulphur, which mu removed by filtration before the addition of platinum chlori

Preparation of Potassium Salts.

	Prepared from	By
Potassium carbonate, B. and U.S.P.	Wood ashes . .	Lixiviating, evaporating, crystallising.
Liquor potassæ, B.P.	Potassium carbonate	Treating solution with sl
,, potassii, U.S.P.		lime and partially evapora
Caustic potash, B. and U.S.P.	Do. .	Ditto, and evaporating to ness.
Potassium bicarbonate, B. and U.S.P.	Do. .	Passing carbonic acid gas solution.
Potassium sulphite, U.S.P.	Do. .	Passing sulphurous acid ga strong solution until acid, ing equal weight of potas carbonate and crystallisin

PREPARATION OF POTASSIUM SALTS—(*continued*).

	Prepared from	By
ssium acetate, and U.S.P.	Potassium carbonate	Dissolving in acetic acid.
ssium citrate, B. d U.S.P.	Do. .	Neutralising with citric acid.
ssium hypophos- ite, U.S.P.	Do. .	Decomposing by hypophosphite of calcium.
ssium chlorate, and U.S.P.	Do. .	Treating with lime and chlorine.
ssa sulphurata, and U.S.P.	Potassium carbonate and sulphur	Heating together.
ssium ferrocyan- e, B. and U.S.P.	Potassium carbonate	Fusing with animal matter and iron; lixiviating and crystallising.
ssium cyanide, and U.S.P.	Potassium ferrocyanide	Igniting either alone, or with carbonate of potassium. The former process is official B.P. and gives a purer, the latter a more abundant product.
ssium acid tar- ate, B. and U.S.P.	Crude tartar or argol	Treating with charcoal or clay.
ssium tartrate, and U.S.P.	Acid tartrate of potassium	Neutralising with potassium carbonate.
ssium nitrate, and U.S.P.	Native . . .	—
ssium sulphate, and U.S.P.	Acid sulphate left from admixture of sulphuric acid and potassium nitrate in the preparation of nitric acid	Neutralising with carbonate of potassium or calcium.
ssium perman- nate, B. and S.P.	Chlorate of potassium, caustic potash, and oxide of manganese	Ignition together, boiling and neutralising.
ssium bichrom- e, B. and U.S.P.	Chromate of potassium	Treating with sulphuric acid.
ssium iodide, and U.S.P.	Potash and iodine .	Mixing and heating with charcoal.
ssium bromide, and U.S.P.	Potash and bromine .	As in the iodide.

GENERAL ACTION OF POTASSIUM SALTS.—According to Ringer, ssium is a **protoplasmic poison** destroying muscle, nerves, nerve-centres when applied to them sufficiently long and in a ciently concentrated form. But this action is not peculiar to ssium, for sodium, ammonium, hydrocyanic acid, and pro- y many other substances possess it. Potassium salts differ sodium salts in **diffusing** more readily through membranes. y are more easily absorbed and more easily excreted than um salts. In the living organism they **occur** chiefly in the l structures, such as blood-corpuscles and muscles, while um salts occur chiefly in the fluids of the body.

When applied to **muscle**, potassium salts in minute doses may ease its contractile power (p. 135); but in larger doses, or when

continued for a longer time, they diminish its power and fi paralyse it altogether. They remove the excessive prolong of muscular contraction produced by veratrine, barium, cal strontium, and by large doses of sodium or lithium (p. 135).

They have a somewhat paralysing action on **motor ne** They paralyse also the **nerve-centres**, generally after a pri transitory, excitement.

A peculiar difference in the action of sodium and potas salts locally applied to the intestine has been already no (p. 383). Large doses paralyse the muscular fibre of the tines, and it is possible that this paralysing action is the ca the digestive disturbances which the prolonged use of potas salts causes (Rossbach).

When administered by the mouth they may produce, like salts in large doses, irritation of the **gastro-intestinal** They are, however, so quickly **excreted** that they can h produce poisoning by their action on the heart while circul in the blood; they probably modify the nutrition of the ti and act as alteratives. It is probable that potassium salts accumulate to a certain extent in the body in the same w sodium chloride (p. 601). By feeding animals with potas salts the poisonous action of barium may be lessened. Casl I have now found that when injected simultaneously with of barium (cf. p. 137), they will antagonise the action o latter, and prevent death from an otherwise lethal dose of ba Similar experiments with potassium and veratrine have negative results. The prolonged use of potassium salts i to cause some depression, and larger doses continued for time may diminish the force of the circulation. They d paralyse the **heart** when given by the mouth, but when in directly into the veins they produce transitory excitement, spasms, paralysis, and death.

Death is preceded by convulsions, and is caused by sto of the heart while respiration still continues. Even after heart and respiration have ceased and the animal is appar dead, life may be restored by the patient use of artificial re tion, and mechanical irritation of the heart by compressin cardiac region. After the heart has thus been induced to spontaneously, respiration still remains in abeyance for some The **nerve-centres** are also paralysed, and neither volu movement nor reflex action occur for some time. When r **excitability** returns it is often much exaggerated, so that a shake or gentle touch on the surface may cause spasms. I respect potassium somewhat resembles atropine, and the po explanation of this action has already been discussed (p. 171 *et*

The effect of potassium salts on the **circulation** some resembles that of digitalis. In large doses they cause a fall of the blood-pressure and pulse-rate. Smaller doses ca

t fall of both pulse-rate and pressure, followed by a rise of . During the rise of pressure, however, the pulse becomes n slow, and continues so even when the pressure again begins ll to the normal. The rise of pressure occurs even when spinal cord is divided, and probably depends on contraction e arterioles (p. 281).

Potassii Carbonas, B. and U.S.P. Carbonate of Potassium, O_3, with about 16 per cent. of water of crystallisation, B.P. $CO_3)\ 3H_2O$; 330, U.S.P.

Characters.—A white crystalline powder, alkaline, and tic to the taste, very deliquescent.

olubility.—It is readily soluble in water, but insoluble in spirit.

eaction.—It gives the reactions of a carbonate (p. 594) and of potas- (p. 603).

0 grains Carbonate of Potassium } neutralise { 17 grains Citric Acid, or 18 grains Tartaric Acid.

Dose.—10 to 30 grains.

Action.—When taken internally it acts as an **irritant** poison. rarely used internally, but may be given instead of liquor ssæ, or of bicarbonate, or in an effervescent form with citric or aric acid. It is chiefly employed in the preparation of other ssium salts. A dilute solution of it may be used as an ication to the skin to relieve itching, and for this purpose be alternated with dilute acid. Carbonate of potassium is used as an ingredient in sulphur ointments (Ung. Sulph. U.S.P. p. 544) in cases of indurated acne: the strength be half a drachm to a drachm in the ounce of ointment.

Liquor Potassæ, B. and U.S.P. Solution of Potash, B.P.; Potassa, U.S.P.—An aqueous solution of hydrate of potassium O; 56) containing 5·84 per cent. of the hydrate, B.P.; about r cent., U.S.P.

Dose.—15 to 60 minims.

Uses.—Dilute liquor potassæ is used **externally** as a lotion eckles, and when diluted with water in the proportion of 1 , is employed in order to soften ingrowing toe-nails. **Inter-** y it acts both as a direct and remote **antacid** and as an rative. It is given in scaly skin-diseases, in eczema and , especially when these occur in gouty subjects, or are ac- panied by acidity of the stomach. In cases of dyspepsia, irritability, it is said to have a **sedative** action upon the nach, and thus to be preferable to the bicarbonate. It is eved to be useful in jaundice, and in enlargement or cancer he liver. For its action upon the system it has been adminis- d in rheumatism, both acute and chronic. It is given to se the **absorption** of fat in obese persons, but may destroy general health (cf. p. 599). It has been used to cause the

absorption of scrofulous glands and of bronchocele. It increa the bronchial secretion, and renders it more liquid and easier cough up. It is therefore useful in bronchitis where the secret is scanty and difficult to expectorate, and is equally servicea in the intercurrent bronchitic attacks to which phthisical patie are liable (p. 252).

Potassa Caustica, B.P.; Potassa, U.S.P. KHO; Caustic Potash.—Hydrate of potassium, KHO, containing sc impurities.

Characters.—In hard white pencils, very deliquescent, pow fully alkaline and corrosive.

Reactions and Tests.—A watery solution gives the reactions of potass (p. 603) and those showing the absence of impurities.

Preparation containing Caustic Potash.

Liquor Potassæ.....27 grains in 1 fluid ounce.

Preparation in which Caustic Potash is used.

Potassii Permanganas.

Uses.—It is used as a **caustic** where we wish to burn dee and widely, as in snake-bites, the bites of rabid animals, or poisoned wounds. It is occasionally employed to open absces more especially abscess of the liver, in which it is sometimes ; ferred to the knife, as by its use we secure adhesion of the live the abdominal wall before the abscess is opened, and thus prev any pus from finding its way into the peritoneal cavity. Rin says that the best way to apply it is to cut a hole in a th piece of plaster, smaller than the size of the slough which wish to make, and rub on the caustic potash, slightly we until the tissues assume a greyish colour, then to wash the with vinegar, and apply a poultice. Solutions of caustic pot of the strength of 10 to 30 grains to the ounce of distilled w are useful in dissolving the thickened patches of old eczem acetic acid must be applied to neutralise the potash, and treatment renewed once or twice a week.

U.S.P. Potassa cum Calce. Potassa with Lime; Vie Paste.

Characters.—It is a greyish-white, deliquescent powder a strongly alkaline reaction.

Reaction.—It gives the tests of potassium (p. 603) and calcium (p. Preparation.—Equal parts of caustic potash and lime made into a with alcohol.

Uses.—It is used for the same purposes and in the s manner as caustic potash, but being less deliquescent its ac is slower and more limited; it is thus more easily restricte the part which it is wished to destroy, and is less liable to spr

Potassii Bicarbonas, B. and U.S.P. Bicarbonate Potassium. $KHCO_3$; 100.

CHARACTERS.—Colourless right rhombic prisms, not deliques-, of a saline feebly alkaline taste, not corrosive.

REACTIONS AND TESTS.—It gives the reactions of a bicarbonate (p. 594 of potassium (p. 603) and those showing the absence of impurities.

) grains Bicarbonate of Potassium } neutralise { 14 grains Citric Acid, or 15 grains Tartaric Acid.

DOSE.—10 to 40 grains.

PREPARATION.

B.P.

Liquor Potassæ Effervescens (Potash water).....30 grs. in 1 pint.

USES.—Solutions of bicarbonate of potassium may be used rnally to relieve itching. **Internally** it is given in dyspepsia, matism, gout, and scalding depending upon excessive acidity e urine with presence of uric acid, or in cases of deposit of acid in the urinary passages.

Potassii Acetas, B. and U.S.P. ACETATE OF POTASSIUM K(CO·OH); 98.

HARACTERS.—White foliaceous satiny masses, very deliques-

ACTIONS.—With a watery solution, tartaric acid causes a crystalline itate (potassium), sulphuric acid the disengagement of acetic acid, and te solution of perchloride of iron strikes a deep red colour (acetate).

PURITIES.—Acid, carbonate, lead.

STS.—Neutral to test paper (no acid); almost entirely soluble in rectified (no carbonate). Its solution is unaffected by sulphide of ammonium etals).

OSE.—10 to 60 grains.

PREPARATION IN WHICH ACETATE OF POTASSIUM IS USED.

Tinctura Ferri Acetatis.

SES.—From its slight local action and its great solubility oduces little effect directly on the stomach and is easily bed into the blood. Here it is converted into carbonate enders the blood and the secretions which come from it **alkaline.** This salt of potassium is one which is very ently used for the purpose of rendering the urine alkaline. one of the most powerful saline **diuretics** we possess, and ch used in dropsies, alone or combined with other diuretics, th tonics and stimulants, e.g. acetate of iron and acetic

hen given in large doses (120 grains and upwards) and in centrated form it acts as a **purgative.**

is employed, like other potassium salts, as an **alterative** in rheumatism, skin diseases, and enlarged glands.

otassii Citras, B. and U.S.P. CITRATE OF POTASSIUM. H_5O_7. B.P. $K_3C_6H_5O_7.H_2O$; 324. U.S.P. LIQUOR POTASSII TIS, U.S.P.

CHARACTERS.—A white powder, of saline feebly acid tas deliquescent, and very soluble in water.

REACTIONS AND TESTS.—Heated with sulphuric acid it forms a brown fl gives off an inflammable gas and evolves the odour of acetic acid (citra Its solution gives the reactions of potassium (p. 603) and, mixed wit solution of chloride of calcium, remains clear till it is boiled, when a wh precipitate separates which is readily soluble in acetic acid. This precipit is citrate of calcium, which is less soluble in hot than in cold water.

DOSE.—20 to 60 grains.

USES.—Is very pleasant to the taste, produces no local acti and is very soluble. It is thus easily absorbed into the blo and there becomes carbonate. It is less liable to purge th other potassium salts, and can thus be given in larger dos After absorption it acts like the carbonate, causes **diuresis** a **lessened acidity** or even alkalinity of the urine, and proba influences tissue-change as well. It is **antiscorbutic.**

Potassii Tartras Acida, B.P.; Potassii Bitartras, U.S

ACID TARTRATE OF POTASSIUM, B.P.; BITARTRATE OF POTASSI U.S.P. CREAM OF TARTAR. $KHC_4H_4O_6$; 188.

An acid salt obtained from the crude tartar which is posited during the fermentation of grape-juice, B.P.

CHARACTERS.—A gritty white powder, or fragments of ca crystallised on one surface; of a pleasant acid taste.

SOLUBILITY.—Sparingly soluble in water, insoluble in spirit.

REACTIONS AND TESTS.—Heated in a crucible it evolves inflamm gas and the odour of burnt sugar, and leaves a black residue (tartrate). calcined residue consists of potassium carbonate and gives its reactions.

DOSE.—20 to 60 grains as a diuretic; $\frac{1}{4}$–$\frac{1}{2}$ oz. as purgati

PREPARATIONS IN WHICH ACID TARTRATE OF POTASSIUM IS USED.

B.P.	U.S.P.
Acidum Tartaricum.	Pulvis Jalapæ Compositus.
Antimonium Tartaratum.	
Confectio Sulphuris.	
Ferrum Tartaratum.	
Potassii Tartras.	
Pulvis Jalapæ Compositus.	
Soda Tartarata.	

USES.—From there being two equivalents of tartaric aci one of potassium it has a somewhat acid taste, and is instead of tartaric or other acids for making **cooling** dr in fevers, &c. A refreshing drink called Potus Imperialis Imperial, is made by dissolving 1 to $1\frac{1}{2}$ drachm of acid tart and a little sugar in a pint of boiling water and infusing half the fresh peel of a lemon.

In small doses it is absorbed, oxidised in the blood to bonate, and acts like the acetate as a **diuretic.**

In larger doses it retains water with great avidity, and

ts its absorption into the blood for a long time. It therefore ses the stools to be very watery, by detaining water in the estine, but it has no irritating action on the intestine, and duces no increased peristalsis. If no other medicine be given ause peristalsis, the salt and the water it has been retaining be absorbed. Its action is thus very much like that of a ple enema of water going along the whole intestine, and like mple enema it produces no depressing effect.

It is much used in dropsies as a **purgative**, generally in com- ation with jalap or scammony to produce peristalsis, whether dropsy be due to affections of the heart or kidneys, and also Bright's disease, even when unaccompanied by dropsy. It also been employed as a laxative in dysentery, piles, and apsus ani.

Potassii Tartras, B. and U.S.P. TARTRATE OF POTASSIUM, $_4H_4O_6.H_2O$ (B.P.), or $(K_2C_4H_4O_6)_2H_2O$; 470 (U.S.P.).

CHARACTERS.—In small, colourless, four or six-sided prisms.

EACTIONS.—It gives the reactions showing the presence of tartaric acid potassium like the bitartrate, but it is readily distinguishable by its er solubility in water.

MPURITY.—Bitartrate.

EST.—Entirely dissolved by its own weight of water.

OSE.—As a diuretic, 20–60 grains. As a purgative, $\frac{1}{4}$–$\frac{1}{2}$ ce.

SES.—In small doses it is absorbed, converted into carbon- n the blood and acts as a **diuretic, antilithic**, &c., like the ate and citrate. In larger doses it acts as a **purgative**, like r saline cathartics.

Potassii Sulphas, B. and U.S.P. SULPHATE OF POTASSIUM. O_4; 174.

HARACTERS.—Colourless hard six-sided prisms terminated x-sided pyramids.

LUBILITY.—Sparingly soluble in water, insoluble in alcohol.

ACTIONS.—It decrepitates strongly when heated. Its solution in water the reactions showing the presence of potassium and a sulphate (*v.* p.

PURITIES.—Calcium, chlorides, iron and lead.

ST.—The solution should give no precipitate with oxalate of ammo- (no calcium), nitrate of silver (no chloride), nor ammonium sulphide (no s).

OSE.—15 to 60 grains.

PREPARATIONS.

B.P.

Pilula Colocynthidis Composita (p. 522)	1 part in	24.
„ „ **et Hyoscyami** (p. 522)	1 „	36.
„ **Ipecacuanhæ cum Scilla** (p. 522)	1 „	3.
Pulvis Ipecacuanhæ Compositus	4 „	5.

USES.—Sulphate of potassium is employed as a saline purg tive in cases of dyspepsia, biliousness, and albuminuria. It generally combined with some other aperient, such as rhubar From its hardness it is used to aid in pulverising tough vegetal substances, like ipecacuanha in the preparation of Pulv. Ipec cuanhæ Co., B.P. It was once supposed to have the power arresting the secretion of milk, and was therefore given to wom who wished to stop suckling.

Potassii Nitras, B. and U.S.P. NITRATE OF POTASSIU KNO_3; 101.

Nitrate of potassium of commerce, purified, if necessary, crystallisation from solution in distilled water.

CHARACTERS.—In white crystalline masses or fragments striated six-sided prisms, colourless, of a peculiar cool sal taste.

REACTIONS.—Thrown on the fire it deflagrates; warmed in a test-t with sulphuric acid and copper wire it evolves ruddy fumes (nitrate). solution gives the reactions of potassium (p. 603).

IMPURITIES.—Sulphates and chlorides, which are detected by the u tests (*v.* p. 594).

DOSE.—10 to 30 grains.

PREPARATIONS.

B.P. Argenti et Potassii Nitras. U.S.P. Argenti Nitras Dilutus U.S.P. Charta Potassii Nitratis. Nitrate of Potassium Paper. Unsized p dipped in a 20 per cent. solution of nitrate of potassium and dried.

ACTION.—In large doses, nitrate of potassium will prod death by gastro-enteritis, with vomiting, weakness, and ar of the circulation, due partly to the reflex action of the drug, partly to its direct action on the heart after absorption. W injected into the blood, it slows the pulse by lessening the i tability of the cardiac ganglia, lowers the temperature, causes dyspnœa and death with convulsions. The convuls are due to arrest of the heart, and consequent irritation of brain by venous blood.

USES.—Nitrate of potassium gives up its oxygen readily, paper dipped in a strong solution of it (Charta potassii nitr U.S.P.) and then dried, may be burnt in a plate, and the fu inhaled, in asthma. It has been suggested that among the ducts of combustion the nitrite of potassium is the most cacious. A ball of nitre, kept in the mouth and allowed to slowly away, gives relief in cases of relaxed sore-throat. has been used internally in acute bronchitis, spasmodic ast (either internally or by inhaling its fumes), and in dyspepsia congestion of the mucous membranes. Generally it is avo in inflammation of the stomach, intestine, kidneys, and blad on account of its local irritant action. On account of its a on the heart it has been given in hæmoptysis and other hæ

ages. On account of its supposed action on the blood it was, d is, used in inflammation, fevers, and exanthemata. As an erative it is used in scurvy, purpura, rheumatism, and gout. enty grains of nitre with thirty of potassium bicarbonate en in the morning in a large soda-water tumbler full of water l sometimes prevent the onset of a gouty paroxysm, and will o remove the headache consequent upon a debauch. Nitrate potassium is also used as a **diuretic** in cases of dropsy and norrhœa, and as a stimulant to the bladder in cases of in-tinence of urine.

Potassii Chloras, B. and U.S.P. CHLORATE OF POTASSIUM, $KClO_3$; 122·4.

CHARACTERS.—In colourless rhomboidal crystalline plates, with ool saline taste.

PREPARATION.—By passing chlorine through a mixture of potassium car-ate and slaked lime. If potassium carbonate alone were used part of it ld be converted into KCl and lost. $3K_2CO_3 + 3Cl_2 = 5KCl + KClO_3 + 3CO_2$. save this, lime is used, which is much cheaper. After the mixture has n saturated with chlorine it is boiled, filtered, evaporated, and the rate crystallised out. $K_2CO_3 + 6CaH_2O_2 + 6Cl_2 = 2KClO_3 + 5CaCl_2 + CaCO_3 + H_2O$.

SOLUBILITY AND REACTIONS.—Sparingly soluble in cold water. It ex-les when triturated with sulphur. When heated it fuses, gives off gen gas, and leaves a white residue, which dissolves in water and gives reactions of potassium and of a chloride.

IMPURITIES.—Chloride and calcium.

TEST.—Its solution is not affected by nitrate of silver (no chloride) nor late of ammonium (no calcium).

DOSE.—10 to 30 grains.

OFFICINAL PREPARATIONS.

B.P. and U.S.P.	DOSE.
Trochisci Potassii Chloratis.....5 grains in each lozenge.	—1 to 6.

Used also in preparing Potassii Permanganas.

ACTION.—Chlorate of potassium, when injected into the cir-ation, has not the same action as other salts of potassium. all doses generally at first depress, and afterwards raise the **od-pressure** and accelerate the **pulse**. Large doses cause den stoppage of respiration, and sinking of the blood-pressure vn to zero, while the exposed heart continues to beat at nearly normal rate, or a little over it, for half or three-quarters of hour.

Large doses administered medicinally have caused poisoning, ecially in children. The symptoms are due to the hæmoglobin he **blood** being converted into methæmoglobin by the action he chlorate. They consist in hæmaturia with blood-casts and inished secretion of urine, many of the renal tubules being d with plugs of blood. The skin becomes discoloured or ndiced, and death occurs with coma or convulsions.

USES.—Chlorate of potassium is chiefly used as a **local** appli-

cation to the mouth, to bring about a more healthy condition the mucous membrane, and to cause ulceration present there heal up. It is used in stomatitis occurring during nursing, wha ever it may depend upon; in aphthæ, in cancrum oris. As gargle it is used in follicular pharyngitis; and has been employ internally and as a local application in cases of croup, diphtheri and spasm of the larynx. It may be used internally as a loti to relieve the dryness of the throat after diphtheria and scarl tina. When taken early, it is said to lessen or arrest catarrh conditions of the nose, throat, and larynx. It has been reco mended in chronic mucous diarrhœa with whitish or mucilagi ous-looking stools. It has also been used as an enema in cas of dysentery. After absorption into the blood it has been su posed to give off its oxygen, and thus to have a disinfecta action in cases of blood-poisoning and malignant fevers. A gre part of it is excreted unchanged by the kidneys, but in lar doses it decomposes the blood and converts it into methæm globin. It has been employed in acute and chronic bronchit in order to thin the secretion and promote expectoration, and a diuretic in cases of dropsy. It was recommended by the la Sir James Simpson in 20-grain doses three times a day, pregnant women where abortion was liable to occur from fat degeneration of the placenta.

Potassii Permanganas, B. and U.S.P. PERMANGANATE POTASSIUM. $KMnO_4$, B.P. $K_2Mn_2O_8$; 314, U.S.P.

CHARACTERS.—Dark purple, slender, prismatic crystals, i odorous, with a sweet astringent taste.

PREPARATION.—By heating caustic potash and manganese diox together in a crucible with chlorate of potassium which yields up its oxy to the manganese and forms manganate of potassium, $3MnO_2 + 6KHO$ $KClO_3 = 3K_2MnO_4 + KCl + 3H_2O$. On boiling this with water it is deco posed, permanganate being formed, and manganese dioxide being deposit $3K_2MnO_4 + 2H_2O = K_2Mn_2O_8 + MnO_2 + 4KHO$. On decanting from the m ganese dioxide, neutralising with sulphuric acid, evaporating, filter through asbestos, and evaporating further, the salt crystallises out.

SOLUBILITY.—It is entirely soluble in cold water. A single small cry suffices to form with an ounce of water a rich purple solution.

REACTIONS.—It gives off oxygen readily to organic substances and is composed, manganese dioxide being precipitated, so that the solution wh mixed with a little rectified spirit and heated, becomes yellowish-bro The crystals heated to redness decrepitate, evolve oxygen gas, and le a black residue from which water extracts potash, recognised by its alkal reaction and by the appropriate tests.

PREPARATION.

B.P. Liquor Potassii Permanganatis (Permanganate of Potass 4·4 grs. in 1 fl. oz. of water or 1 per cent. solution).

Condy's fluid is a solution of 2 grains to the ounce.

ADMINISTRATION.—The solution has a disagreeable taste, a the solid permanganate of potassium gives off oxygen so read that, if mixed with easily oxidisable substances, such as sug

ıp, or glycerine, the mixture may explode or take fire spon-
eously. Martindale recommends that the necessary quantity
ermanganate should be made into a pill with kaolin ointment
sisting of equal parts of vaseline, paraffin, and kaolin.

Action.—Permanganate of potassium very readily parts with
oxygen, and thus **destroys organic matter**; when mixed
cobra poison it completely destroys the deadly power of
latter, and the mixture may be injected subcutaneously with-
any bad effects. When injected after the poison, however,
oes not appear to come into such immediate contact with it
he tissues as to destroy it, and it therefore does not act as
ntidote.

Uses.—It is used to **disinfect** the stools in typhoid fever, and
isinfect the hands after making *post-mortem* examination, or
r coming in contact with matters likely to convey contagion
nfection (p. 105). It is applied as a lotion to wounds and
s, especially those having a foul-smelling discharge, and may
njected into the cavity of abscesses after evacuation of pus,
sed to wash out the cavity of the pleura after the fluid has
removed in cases of pleurisy. In cases of ozæna it is em-
ed to wash the nose, and as a lotion or gargle to the mouth
lceration with fœtor, such as mercurial stomatitis, and also
iphtheria. It has been recommended internally in cases of
etes. It is said by Ringer and Murrell to be of very great
in **amenorrhœa**, two or three grains being given in pill three
our times a day for some days before the period.

Potassa Sulphurata, B. and U.S.P. Sulphurated Potash,
.; Sulphurated Potassa, U.S.P.

Characters.—Solid, greenish fragments, liver-brown when
ntly broken, alkaline, and acrid to the taste.

olubility and Reactions.—It readily forms with water a yellow solu-
which has the odour of sulphuretted hydrogen, and evolves it freely
excess of hydrochloric acid is dropped into it, sulphur being at the
time deposited. The acid fluid when boiled and filtered is precipitated
w by perchloride of platinum, and white by chloride of barium.

mpurity.—Carbonate left in the preparation, or sulphate formed by
mposition.

est.—About three-fourths of its weight are dissolved by rectified spirit,
hich both carbonate and sulphate are insoluble.

Dose.—2 to 10 grains.

Preparation.

B.P.

uentum Potassæ Sulphuratæ (5 parts, hard paraffin 18, soft paraffin 55).

Action.—When applied to the skin, the ointment may be
l instead of simple sulphur ointment. In the intestine sul-
rated potash seems to stimulate peristaltic action, and to act
laxative. Apparently also, like sulphur, it has a somewhat

stimulating action upon the **respiratory** mucous membrane, a upon the **sweat**-glands.

USES.—The ointment is used externally in cases of scab and acne. Sulphurated potash is used as a bath in chro rheumatism (p. 470), rheumatoid arthritis, and chronic orga nerve-disease, and as a diaphoretic in albuminuria. It has be given internally in chronic bronchitis, croup, and whoopi cough, and used as an injection into the rectum to destr ascarides, in solutions of half a grain to a grain in the ounce water.

Potassii Bichromas, B. and U.S.P. BICHROMATE POTASSIUM, $K_2CrO_4.CrO_3$, B.P. : $K_2Cr_2O_7$; 294·8, U.S.P.

CHARACTERS.—In large red, transparent, four-sided tabl anhydrous.

REACTIONS AND SOLUBILITY.—It fuses below redness; at a higher te perature is decomposed, yielding green oxide of chromium and yellow ch mate of potassium, which may be separated by dissolving the latter in wat The bichromate dissolved in water gives a yellowish-white precipitate w chloride of barium, and a purplish red precipitate with nitrate of silver, a both these precipitates are soluble in diluted nitric acid. The solution a when digested with sulphuric acid and rectified spirit acquires an emer green colour.

PREPARATIONS IN WHICH BICHROMATE OF POTASSIUM IS USED.

Acidum Chromicum. Sodæ Valerianas.

Test solution of Bichromate of Potassium, U.S.P. 1 in 10 of water.

ACTION.—In **frogs** it causes general feebleness of moti respiration, and circulation, and sometimes convulsions. T nerve-centres are first excited and then depressed. The ner centres are affected before the nerves or muscles. The he stops in diastole. In **mammals** it causes vomiting, diarrho and bloody stools, great feebleness, and general clonic movemen In rabbits and guinea-pigs **convulsions** and **paralysis** occ chiefly affecting the posterior limbs. *Post mortem* a red colo tion of the muscles is observed, and the gastric and intesti mucous membranes are congested.

USES.—It has been used by Vulpian alternately with iodi of potassium and nitrate of silver in tabes dorsalis; and in do of ½–1½ grain it is said to be useful in cases of dyspepsia simul ing cancer of the stomach.

Potassii Ferrocyanidum, B. and U.S.P. FERROCYAN OF POTASSIUM. $K_4Fe(CN)_6.3H_2O$; 421·9.

CHARACTERS.—In large yellow four-sided tablets or pris permanent in the air.

SOLUBILITY.—Soluble in water, insoluble in alcohol.

REACTIONS.—The aqueous solution precipitates deep blue with persulph of iron, brick-red with sulphate of copper, and white with acetate of le Heated with diluted sulphuric acid, hydrocyanic acid vapours are evolved

PREPARATIONS FOR WHICH FERROCYANIDE OF POTASSIUM IS USED.

Acidum Hydrocyanicum Dilutum, Potassii Cyanidum.

'est solution of Ferrocyanide of Potassium. Dissolve ¼ ounce of ferrocyanide otassium (yellow prussiate of potash) in crystals in 5 fluid ounces of distilled r and filter, B.P.; 1 in 10 of water, U.S.P.

'est solution of Ferricyanide of Potassium. Dissolve ¼ ounce of ferricyanide otassium (red prussiate of potash) in crystals in 5 fluid ounces of distilled r and filter, B.P.; 1 in 10 of water, U.S.P.

Potassium Cyanidum, B. and U.S.P. CYANIDE OF POTAS-I. KCN; 65.

CHARACTERS.—White, opaque, deliquescent, crystalline masses ing the odour of hydrocyanic acid, like which it is intensely onous (p. 586).

B.P. PREPARATION FOR WHICH IT IS USED.
Bismuthum Purificatum.

Potassii Bromidum, B. and U.S.P.—*Vide* p. 553.

Potassii Iodidum, B. and U.S.P.—*Vide* p. 559.

SODIUM. Na; 23.

SOURCES OF SODIUM SALTS.—The chief source of sodium is mon salt obtained by the evaporation of sea-water, or from mines. Two subsidiary sources are the nitrate of sodium borax, both of which are found native.

GENERAL REACTIONS OF SODIUM SALTS.—They are not preci-ted by any of the ordinary reagents. The special test for n is the yellow colour which they give to flame. The mere arance of the yellow colour is the test adopted by the British rmacopœia, but it is improved upon in the American Pharma-eia, which directs that the flame should not appear more transiently red when observed through a blue glass. In way sodium salts are both more readily distinguished from e of potassium, and the presence of the slightest impurity is y observed; for sodium salts are so widely distributed in re, and the yellow colour which they give to the flame is so ht, that minute quantities of sodium mixed with potassium disguise the violet colour which the potassium gives, although ould be present in much greater quantity than the sodium. istinguish between potassium salts and sodium salts, it is efore necessary to look at the flame through a blue glass, h cuts off the yellow rays emitted by the sodium of the flame, thus allows the violet ones of the potassium to be seen.

PREPARATION OF SODIUM SALTS.

	Prepared from	By
Sodium chloride	Sea-water	Evaporation. Or found native.
Sodium sulphate	Sodium chloride	Heating with sulphuric acid in th preparation of hydrochloric aci
Sodium carbonate	Sodium sulphate	Roasting with calcium carbona and coal.
Sodium	Sodium carbonate	Igniting with charcoal.
Sodium ethylate (Liquor)	Sodium	Dissolving in ethylic alcohol.
Dried sodium carbonate	Sodium carbonate	Heating.
Sodium bicarbonate	Ditto	Mixing with dry carbonate a saturating with carbonic acid.
Caustic soda	Ditto	Decomposing by lime.
Sodium acetate	Ditto	Neutralising with acetic acid.
Effervescent citro-tartrate	Ditto	Heating dry carbonate with t taric and citric acids.
Tartrate of soda and potash (soda tartarata)	Ditto	Neutralising solution with a tartrate of potassium, evapor ing and crystallising.
Sodium benzoate, U.S.P.	Ditto	Neutralising a hot solution w benzoic acid and crystallising
Sodium phosphate	Ditto	Decomposing bone-ash with s phuric acid, and saturating acid phosphate of calcium th obtained with sodium carbon
Sodium hypophosphite	Ditto	Decomposing hypophosphite lime with sodium carbonate.
Liquor sodæ chlorinatæ	Ditto	Passing chlorine through its so tion.
Sodium valerianate	Ditto	Neutralising by valerianic acid
Sodium salicylate, B. and U.S.P.	Ditto	Neutralising solution by salic acid with slight excess of s and evaporating.
Sodium sulphocarbolate, B. and U.S.P.	Ditto	Decomposing by barium sulp carbolate. The barium sulp carbolate is prepared by mix equal parts of carbolic and str sulphuric acid, allowing th to stand for some days, dilut and neutralising with bar carbonate.
Sodium bisulphite, U.S.P.	Sodium carbonate	Saturating its solution with phurous acid.
Sulphite, B. and U.S.P.	Sodium bisulphite	Adding an equal weight of sod carbonate to the bisulphite pared as above.
Hyposulphite, U.S.P. and B.P., App.	Sulphite	Heating with sulphur.
Borax	—	Found native.
Nitrate	—	Found native.
Arseniate	Carbonate and nitrate	Fusing with arsenious acid.

GENERAL IMPURITIES OF SODIUM SALTS.—As sodium carbo is prepared from sodium sulphate, and the latter from soc chloride, sulphates and chlorides may be present as impu in it. As the other sodium salts are chiefly obtained from carbonate, chlorides and sulphates also come to be preser

urities in them. They also occur even in the nitrate of um found native.

ENERAL TESTS FOR IMPURITIES IN SODIUM SALTS.—In order stinguish between salts of potassium and sodium, as well as rove the absence of potassium as an impurity, the B.P. ts that the solutions of sodium salts, when acidulated, ld not give a precipitate with perchloride of platinum. The P. directs that the yellow colour which sodium salts give to lame should not appear more than transiently red when seen ugh a blue glass. The absence of chlorides and sulphates is tained by the usual tests (pp. 594, 595), and the absence of ls by the want of any colour or precipitate on the addition drosulphuric acid or ammonium sulphide.

ENERAL ACTION OF SODIUM SALTS.—Salts of sodium diffuse slowly than those of potassium. They are neither absorbed excreted so readily, and have not a marked diuretic action. n locally applied to **muscle** and **nerve** in large doses they lyse both, but not so powerfully as salts of potassium, nor they such a paralysing action upon the involuntary muscle, r of the **heart** or the **intestine**. In large doses they lengthen nuscular curve, and increase the length of the curves pro- d by calcium and strontium instead of shortening them, like ssium (p. 142).

rate of sodium is less soluble than urate of potassium or um. It is therefore less readily excreted, and forms the les known by the name of chalk-stones in gouty patients.

.P. Sodium. SODIUM. Na; 23. The metallic element m as met with in commerce. It should be preserved in stoppered bottles under mineral naphtha.

HARACTERS.—A soft metal, rapidly oxidising in the air, but ing a bright metallic surface when freshly cut.

EACTIONS.—It attacks water or alcohol, with evolution of hydrogen gas, or no insoluble matter remaining. Twenty-three grains, cautiously ved in water, require for neutralisation at least 975 grain-measures of olumetric solution of oxalic acid.

PREPARATION.

Liquor Sodii Ethylatis.

.P. Liquor Sodii Ethylatis. SOLUTION OF ETHYLATE OF UM.—It contains 19 per cent. of the solid salt, NaC_2H_5O.

HARACTERS.—A colourless liquid of syrupy consistence, be- ng brown by keeping. Specific gravity 0·867.

EPARATION.—By dissolving metallic sodium (1) in ethylic alcohol (20) con- in a flask which is kept cool in a stream of cold water. The solution l be recently prepared.

EACTIONS.—When heated it boils and gives off alcoholic vapours, leaving te salt which, on being strongly heated, chars. If the white salt be

mixed with water and heated, it yields alcohol, and the solution, on evap tion, leaves a white residue consisting almost wholly of caustic soda.

ACTION.—It is a powerful **caustic.**

USE.—To destroy nævi. It should be applied by means a glass rod to the nævus for two or three days successively, then discontinued until the scab which forms has become tached, after which the treatment should be resumed.

Sodii Chloridum, B. and U.S.P. CHLORIDE OF SODI COMMON SALT. NaCl; 58·4.

CHARACTERS.—In small white crystalline grains, or tra parent cubic crystals, free from moisture. It has a purely sal taste, and imparts a yellow colour to flame.

SOLUBILITY AND REACTIONS.—Is soluble in water. The solution g the reaction of a chloride (p. 594), and does not give that of potassium bu sodium (p. 617).

PREPARATIONS IN WHICH CHLORIDE OF SODIUM IS USED.

Acidum Hydrochloricum. Hydrargyri Perchloridum.
Hydrargyri Subchloridum.

ACTIONS.—Although chloride of sodium is not much used a remedy, it is most important as a **food.** It forms a large p portion of the salts of the body, and no doubt plays a v important part in tissue-change. When persons are deprive it for a length of time the longing for it becomes intense, animals will go very great distances to obtain it. When mi with water, in the proportion of **0·65 to 100, the solution d not destroy animal tissues** like water alone, and may be mi with blood without destroying the corpuscles (*vide* p. 600). Str solutions, however, are intensely irritating. When injected i the lymph-sac of a frog it causes increased **diapedesis** of the corpuscles, which then pass out through the vessels in consi able numbers. It is possible that an increase in the propor of sodium chloride may have something to do with the proc tion of scurvy, as this disease appears to be relieved by s containing another base than sodium and another acid rad than chlorine.

USES.—Externally it is used as a **stimulant** to the ski the form of baths (pp. 459 and 469). A solution of salt of 1 per cent. has been recommended by Kühne to wash wou and raw surfaces in place of water, as it does not destroy vitality of the tissues, and a similar solution may be used ins of water to wash out the nasal cavities, either alone or m with other medicaments. When taken in considerable qu tities it produces vomiting, and may be used as an **eme** either alone or to aid the action of other emetics. Half a spoonful of dry salt, repeated until nausea is produced, is sometimes to arrest hæmoptysis. It appears to diminish secretion of mucus, and may be given to children suffering f

ns, where the intestinal mucus is excessive and affords a s for the parasites.

A solution (ʒss in ℥j water) flavoured with liquorice, in table-nful doses every two hours, sometimes proves very useful in ing absorption of pleuritic serous exudation. It is contra-cated when the exudation is purulent.

After hæmorrhage there is generally excessive thirst, and the tion of chloride of sodium to the water drunk by the patient been recommended in order to prevent destruction of the d-corpuscles which might arise from the absorption of small unts of pure water. During convalescence patients some-s exhibit a desire for salt and indigestible food, which, if n, would probably derange the digestion, but the craving be allayed by giving salt alone. It has been used in bilious rhœa, in doses of 10 to 60 grains, three or four times a day. As an **enema** to destroy ascarides it is frequently used. The portion generally is 1 or 2 tablespoonfuls to the pint of water.

Sodii Carbonas, B. and U.S.P. CARBONATE OF SODIUM. $CO_3.10H_2O$; 286.

Obtained from the ashes of marine plants, or produced by nical decomposition with chloride of sodium.

CHARACTERS.—In transparent, colourless, laminar crystals, of mbic shape, efflorescent, with a harsh alkaline taste and ng alkaline reaction.

REACTIONS.—By heat it undergoes aqueous fusion, and then dries up, g 63 per cent. of its weight.

20 grains Carbonate of Sodium } neutralise { 9·7 grains Citric Acid. / 10½ grains Tartaric Acid.

DOSE.—5 to 30 grains.

PREPARATIONS.

B.P.		DOSE.
Sodæ Carbonas Exsiccata.	Dried carbonate of sodium (used for pills)	3–10 grs.

USES.—It is not much used as a remedy. Its chief use is the preparation of other sodium salts. A dilute solution of it be used as a wash to the skin to remove itching. In cases mæmia it may be combined with ferri sulphas exsiccata, ains of each, in pill.

Soda Caustica, B.P.; Soda, U.S.P. CAUSTIC SODA, B.P.; A, U.S.P.—Hydrate of sodium, NaHO, 40, with some im-ties.

CHARACTERS.—Hard, greyish-white pencils or fibrous pieces, quescent in moist air, dry and efflorescent in dry air, very line and corrosive.

REACTIONS AND TESTS.—It gives the tests of sodium (p. 617), and not of ssium. Its solution in water, acidulated by nitric acid, effervesces only

slightly (limit of carbonate) and gives only scanty white precipitates v nitrate of silver and chloride of barium (limit of chlorides and sulphates).

IMPURITIES.—Carbonate, chlorides, sulphates.

PREPARATION CONTAINING CAUSTIC SODA.

Liquor Sodæ .....18·8 grains in 1 fluid ounce.

USE.—It is used as caustic like potash, but has less affin for water, and so does not take it from the tissues and dest them so powerfully. At the same time it has less tendency run over adjacent parts.

Liquor Sodæ, B. and U.S.P. SOLUTION OF SODA.— aqueous solution of hydrate of sodium (NaHO ; 40) containi about 3 per cent. of the hydrate, U.S.P. (4·1 per cent. B.P.).

CHARACTERS.—Like those of liquor potassæ (p. 607), but it not precipitated by tartaric acid nor by perchloride of platinu

USES.—Is used in preparing ferric oxide and in other ph maceutical processes, as it is cheaper than solution of pota Internally it may act on the blood, rendering it and the secretio more alkaline, but it will not alter nutrition in the way th potassium salts do.

Sodii Bicarbonas, B. and U.S.P. BICARBONATE OF SODIU $NaHCO_3$; 84.

CHARACTERS.—In powder, or small opaque irregular scal white, of a saline and not unpleasant taste.

REACTIONS.—It gives the reactions showing the presence of sodium, a of carbonic acid. It is distinguished from carbonate by its solution in c water giving a white and not a coloured precipitate with solution of p chloride of mercury.

20 grains of Bicarbonate of Sodium } neutralise { 16·7 grains of Citric Acid, o 17·8 grains of Tartaric Acid.

DOSE.—10 to 60 grains.

PREPARATIONS CONTAINING BICARBONATE OF SODIUM.

B.P.	DOSE.
Liquor Sodæ Effervescens (soda-water)...30 grains in 1 pint	$\frac{1}{6}$–1 pint.
Sodii Citro-tartras Effervescens.....17 parts in 31	6 grs. to $\frac{1}{2}$
Trochisci Sodii Bicarbonatis .....5 grs. in each lozenge	1 to 6.

U.S.P.

Sodii Bicarbonas Venalis (for external use).
Mistura Rhei et Sodæ .....2 dr. to 3 oz.
Pulvis Effervescens Compositus .....one or two powders.

U.S.P. Sodii Bicarbonas Venalis. COMMERCIAL BICARBONATE OF SODIUM.—Sho contain 95 per cent. of pure bicarbonate, which it resembles in appearance and te

U.S.P. Mistura Rhei et Sodæ. MIXTURE OF RHUBARB AND SODA.—Bicarbonat sodium 3, fluid extract of rhubarb 3, spirit of peppermint 3, water q.s. to make 1

U.S.P. Pulvis Effervescens Compositus. COMPOUND EFFERVESCING POWDE Bicarbonate of sodium 8, tartrate of potassium and sodium 24, mixed to mak powder of 160 grains; tartaric acid, in separate powder, 35 grains.

USES.—Bicarbonate of sodium has a slight local irrita

on. It may be used as a wash in cases of itching skin-
ases, e.g. prurigo, and as a lotion to eczema. The strength
grains to the ounce, and it is applied like water-dressing.
A solution of this strength when used to rinse the mouth
etimes relieves the pain of toothache, and also relieves
lache, either temporal or occipital, depending on decayed
h, even though no pain should be felt in the tooth itself.
It may also be used to prevent injury to the teeth from acid
cs.
Mixed with tincture of opium, and introduced into the cavity
decayed tooth by means of a pledget of cotton-wool, it will
n arrest the pain of toothache. When swallowed it stimu-
s the secretion of gastric juice, and is a most efficient remedy
n given from ten minutes to half an hour before meals, in
s of atonic **dyspepsia**, where the patient complains of weight
ain at the pit of the stomach, pain between the scapulæ, and
h flatulence unaccompanied by constipation. In such cases
often advantageous to combine it with a bitter tonic and
e carminative. As dyspepsia often occurs in persons engaged
usiness who cannot carry mixtures about with them, the
nges (B.P.) are very useful, for they can be easily carried
t and taken when necessary.
It also relieves frontal **headache**, unaccompanied by constipa-
, where the headache is situated just at the junction of the
head with the hairy scalp. Frontal headache, lower down,
above the eyebrows, is better treated by nitro-hydrochloric
(p. 576). In persons who suffer from great acidity after meals,
ay be used as an **antacid**. A solution of $\frac{1}{2}$ or 1 grain to the
e of water or milk is exceedingly useful in the diarrhœa and
asmus of infants.
It is also serviceable in cases of diabetes, to lessen the amount
gar. It renders the bronchial secretion less tenacious, but
t so useful as bicarbonate of potassium. The lozenges are
convenient in such cases.
It seems to have less tendency than potash to produce
rrh of the stomach, and may be used for a longer time
506).
As sodium naturally exists in large quantity in the blood, the
unt we can add is but a small fraction of that quantity, and
lterative action is very slight. It will increase the alkalinity
he blood, and has been given instead of bicarbonate of potas-
n in acute rheumatism, but it is perhaps not so good. The
e of sodium is not so soluble as that of potassium, so sodium
t so good in the uric acid diathesis (Garrod), and its diuretic
er is also less.

B.P. **Sodii Citro-Tartras Effervescens.** EFFERVESCENT
O-TARTRATE OF SODIUM.

CHARACTERS.—A granular powder which effervesces on the addition of water.

DOSE.—60 grains to ¼-ounce.

USE.—If absorbed there may be some slight difference between the effect of this salt and of tartarated soda, which contains some potash, but this is very slight, and of no importance. It is used only for its **laxative** effect. It is both pleasanter to take than tartarated soda, and it is less likely to cause unpleasant feelings in the stomach.

Soda Tartarata, B.P.; Potassii et Sodii Tartras, U.S.P. TARTARATED SODA, B.P.; TARTRATE OF POTASSIUM AND SODIUM, U.S.P. ROCHELLE SALT. $NaKC_4H_4O_6.4H_2O$; 282.

CHARACTERS.—In colourless, transparent prisms or halves of prisms, of the right rhombic order, generally eight-sided; tasting like common salt.

IMPURITY.—Bitartrate of potassium.

TEST.—Entirely soluble in cold water.

REACTIONS.—Heated with sulphuric acid it blackens, evolving inflammable gases and the odour of burnt sugar (tartrate). It imparts a yellow colour to flame (sodium). A strong solution gives a crystalline precipitate with a small quantity of acetic acid (potassium).

DOSE.—As a purgative, ¼ to ½ ounce; as a diuretic, 30 to 60 grains.

USES.—In large doses it retains water, quickens peristalsis, acts as a **purgative**, and is chiefly used as such. In small doses it is absorbed from the intestines, is converted in the blood into carbonate of potassium and sodium, causes **diuresis** and renders the urine alkaline. It may be used as a remote antacid.

Sodii Acetas, B.P. Appendix, and U.S.P. ACETATE OF SODIUM, U.S.P. $NaC_2H_3O_2.3H_2O$; 136.

USES.—In testing and in preparing acetic ether.

Borax, B.P.; Sodii Boras, U.S.P. BORAX, B.P.; BORATE OF SODIUM, U.S.P. BIBORATE OF SODIUM. $Na_2B_4O_7.10H_2O$; 38

A native salt. It is also made artificially by boiling together in proper proportions, boric acid and carbonate of sodium.

CHARACTERS.—In transparent, colourless crystals, sometimes slightly effloresced, with a weak alkaline reaction.

SOLUBILITY.—Insoluble in rectified spirit, soluble in water.

REACTIONS.—A hot saturated solution, when acidulated with any of the mineral acids, lets fall, as it cools, a scaly crystalline deposit (boric acid), the solution of which in spirit burns with a green flame.

DOSE.—5 to 40 grains.

PREPARATIONS.

B.P.

Glycerinum Boracis.....1 part in 6 by weight (= 1 oz. in 4 fluid oz. glycerin)

Mel Boracis.....56 grains in 1 oz.

Used also to prepare boric acid.

USES.—Borax destroys low vegetable organisms and prevents r germination. It thus acts as a **disinfectant.** Applied to the it removes the epidermis, and may be used for this purpose ead of soap. It is used as a lotion in acne. It forms a useful n to remove scurf from the head, chloasma or liver spots, to allay itching in urticaria, psoriasis, impetigo, and pruritus ndi, scroti, and ani; it is also used in acute eczema in a tion of 1 per cent. with 1 per cent. of acetate of alum. In trigo it may be dusted on in a mixture with 5 per cent. of e of bismuth and starch. It is much employed in aphthous litions of the mouth and throat, either alone or combined chlorate of potassium. It may be given simply in solution, n the form of the honey or glycerine. As an injection it is ul in leucorrhœa and gonorrhœa.

t has been supposed to have a special action upon the **uterus,** has been employed in amenorrhœa, dysmenorrhœa, and puer- l fever and convulsions. On account of its asserted power crease the uterine contraction, it ought either to be avoided nployed with care during pregnancy. Borax is useful in some s of epilepsy in doses of 10 to 15 grains three times a day. ts as a solvent to benzoic acid.

Sodii Sulphas, B. and U.S.P. SULPHATE OF SODIUM. BER'S SALT. $Na_2SO_4.10H_2O$; 322.

HARACTERS.—In transparent, oblique prisms. It has a salt bitter taste and effloresces on exposure to the air.

LUBILITY.—It is soluble in water, insoluble in spirit.

EACTIONS.—It gives the reactions of sodium (p. 617) and of a sulphate 5).

EPARATION, B.P.—May be obtained from the residue left in the manu- e of hydrochloric acid, by neutralising it with carbonate of sodium, and llising from solution in water.

OSE.—$\frac{1}{4}$ to 1 ounce.

SES.—Sulphate of sodium, when introduced into the ach, is supposed to excite peristaltic movements in it, and ve a similar action upon the intestine. It produces in the tine a secretion of watery fluid, and acts as a **purgative.** It ed either alone, or mixed with bicarbonate of sodium, in of the stomach, chronic gastritis, and dilatation of the ach. A mixture of sulphate and bicarbonate of sodium has used in imitation of the Carlsbad salts obtained by evapora- f the natural mineral water of Carlsbad. The mixture, or natural salts, ought to be taken dissolved in warm water diately after rising, and it is better to sip the solution at vals, while dressing, than to drink the whole off at a draught 06). One-third of a teaspoonful of the crystallised salts in ge tumblerful of warm water, taken immediately on rising, quently sufficient to produce one free action of the bowels breakfast, and no more. This quantity of salts, with a

smaller quantity of water, may have no action; and if a sma quantity of water be used along with a larger quantity of s it not unfrequently happens that several scanty motions oc during the day, with considerable discomfort in the abdomen

Carlsbad water, natural or artificial, is also useful in bili disorders, and in persons of a gouty diathesis. A gentle cou will often remove the dulness, irritability, and other sympto which accompany biliary derangements or precede a gouty atta It may be used, also, with advantage in chronic constipation tendency to congestion of the brain or of the abdominal and pe organs. A continued course of the water is exceedingly be ficial in cases of excessive obesity, and also in diabetes mellitu

The Carlsbad waters contain a number of other salts wh are not crystallised out, and they often prove much more effic when drunk at the springs than when the solution of the salt taken by patients at their own homes. The great benefit wh is often obtained from a course of the waters at Carlsbad is doubt due in great measure to the diet and regimen wh patients will follow there in company with others, but wh nothing would induce them to conform to while at home.

Sodii Sulpho-carbolas, B. and U.S.P. SULPHO-CARBOL OF SODIUM. $NaC_6H_5SO_4.2H_2O$.

CHARACTERS.—Colourless, transparent, rhombic prisms, odorous, or nearly so, with a cooling, saline, and somewhat b taste.

SOLUBILITY.—Readily soluble in water, less so in spirit.

REACTIONS.—On ignition it gives off vapours of carbolic acid, and the due dissolved in water gives a precipitate with chloride of barium (sulph It gives a yellow colour to flame. The watery solution is neutral to paper, and gives a violet colour with perchloride of iron. It is not at rendered turbid by chloride of barium.

DOSE.—10–15 grains.

ACTION.—**Antiseptic** and mildly astringent.

USES.—It arrests fermentation in the stomach, and given before meals is useful in flatulence and acidity occurrin phthisical patients. It may be combined with bitters. It is in septic conditions.

Sodii Phosphas, B. and U.S.P. PHOSPHATE OF SOD $Na_2HPO_4.12H_2O$; 358.

CHARACTERS.—In transparent, colourless, rhombic pri terminated by four converging planes, efflorescent, tastin common salt. It imparts a yellow colour to flame.

REACTIONS.—Its solution has a faintly alkaline reaction; it gives a precipitate with nitrate of silver, the resulting fluid acquiring an acid re (phosphate).

DOSE.—As a purgative, $\frac{1}{4}$ to 1 ounce. As an alterative, 40 grains.

USES.—It is used as a **purgative** in children and in delicate ons, both because it acts gently and has little or no taste. It be easily given to children in a little soup without their ving it.

It has been used in fevers as a purgative, and in rickets in r to supply phosphoric acid to the bones. It has been found cially useful in children with hepatic derangement, as shown er by white or green stools, or by jaundice. The dose for n is 3 to 10 grains given in food or milk.

U.S.P. Sodii Chloras. CHLORATE OF SODIUM. $NaClO_3$; 106·4.

CHARACTERS.—Colourless, transparent tetrahedrons of the lar system; permanent in dry air, odourless, having a ng saline taste and a neutral reaction.

OLUBILITY.—Soluble in 1·1 parts of water, and in 40 parts alcohol at C. (59° F.); in 0·5 parts of boiling water, and in 43 parts of boiling ol.

EACTIONS.—When heated the salt melts, and afterwards gives off a por- of its oxygen, finally leaving a residue of sodium chloride which gives eactions peculiar to it (p. 620).

USES.—Similar to those of chlorate of potassium (*vide* p. 613). t is more soluble, stronger solutions can be employed.

Sodii Hypophosphis, B. and U.S.P. HYPOPHOSPHITE OF UM. $NaH_2PO_2.H_2O$; 106.

CHARACTERS.—Small, colourless or white rectangular plates, white granular powder, deliquescent on exposure to air, rless, having a sweetish saline taste and a neutral reaction.

OLUBILITY.—Soluble in 1 part of water and in 30 parts of alcohol at 15° C. F.); in 0·12 parts of boiling water, and in 1 part of boiling alcohol.

EACTIONS.—When heated in a dry test-tube the salt loses water, and then es a spontaneously inflammable gas (phosphoretted hydrogen), burning a bright yellow flame. A fragment of the salt imparts to a non-luminous an intense yellow colour, not appearing more than transiently red when ved through a blue glass. On triturating or heating the salt with an ing agent the mixture will explode.

OSE.—1 to 10 grains (5 to 10 grs. B.P.).

PREPARATION.

U.S.P.

Syrupus Hypophosphitum.

USES.—It is said to have a stimulating action upon the **ous system**, and to increase digestion and **nutrition**. It is ly given in the earlier stages of phthisis (*vide* p. 717), and æmia and nervous debility.

U.S.P. Liquor Sodii Silicatis.

CHARACTERS.—An almost colourless, slightly yellow, viscid d, with a sharp saline taste and an alkaline reaction.

REACTIONS.—It imparts an intense yellow colour to a non-luminous fl
A small quantity should not produce any caustic effect on the skin (sho
the absence of excess of alkali).

USE.—It is used for making bandages, which are thus
dered lighter than plaster-of-paris, and stronger than sta
bandages.

U.S.P. Sodii Benzoas. BENZOATE OF SODIUM. NaC_7H
H_2O; 162.

CHARACTERS.—A white, semi-crystalline, or amorphous pow
efflorescent on exposure to air, odourless, or having a faint oc
of benzoin, of a sweetly astringent taste, free from bittern
and having a neutral reaction.

TESTS.—When heated the salt melts, emits vapours having the odou
benzoic acid, then chars, and finally leaves a blackened residue of an alk
reaction and exhibiting the reactions of sodium (p. 617). On mixin
aqueous solution of the salt with a dilute solution of ferric sulphate a f
coloured precipitate is produced.

DOSE.—10 to 20 grains.

USES.—It has been strongly recommended as a remed
phthisis, and has also been used in puerperal fever and to el
nate uric acid in gout.

Sodii Iodidum.—*Vide* p. 563.

Sodii Bromidum.—*Vide* p. 555.

U.S.P. Sodii Pyrophosphas. PYROPHOSPHATE OF SOD
$Na_4P_2O_7.10H_2O$; 446.

CHARACTERS.—Colourless, translucent, monoclinic prisms,
manent in the air, odourless, having a cooling, saline, and fe
alkaline taste, and a slightly alkaline reaction.

SOLUBILITY.—Soluble in 12 parts of water at 15° C. (59° F.) and i
parts boiling water; insoluble in alcohol.

REACTIONS.—Its aqueous solution with excess of test-solution of nitra
silver gives a white precipitate and a neutral filtrate.

ACTION.—Its actions in medicinal doses appear to be ne
the same as those of the phosphate, but probably it would l
a greater influence on the nervous system.

USES.—To prepare the pyrophosphate of iron.

Sodii Salicylas, B. and U.S.P. SALICYLATE OF SOD
$2NaC_7H_5O_3.H_2O$; 338.

CHARACTERS.—Small, white, crystalline plates, or a cry
line powder, permanent in the air, odourless, having a swe
saline and mildly alkaline taste and a feebly acid reaction.

SOLUBILITY.—Soluble in 1·5 parts of water and in 6 parts of alcoh
15° C. (59° F.); very soluble in boiling water and in boiling alcohol.

REACTIONS.—When heated the salt gives off inflammable vapour
leaves an alkaline residue amounting to between 30 and 31 per cent. o
original weight, and which gives the reactions of sodium carbonate.

DOSE.—In rheumatism with high temperature 10 to 20 grains ery two to four hours. The addition of some aromatic spirit ammonia, or alcohol in some form, tends to lessen the cardiac pression which the salicylate alone may cause.

ACTION AND USES.—It agrees in its action with salicylic acid, cepting that it has no power to destroy low organisms. In rile conditions, and especially in acute rheumatism, it greatly ers the **temperature** and lessens the pain. Its use should be ntinued for some time after apparent convalescence, as the nperature is apt to rise again when the administration of the nedy ceases. It often gives relief in tonsillitis. In small doses s useful in chronic rheumatism. In doses of ½ to 2½ grains ry quarter or half hour it will often cut short headaches. The nptoms of its physiological action are the same as those of icylic acid (see p. 819)—ringing in the ears, &c. (pp. 228 and). These symptoms may be lessened by ergot, hydrobromic d, or bromides. It renders the **bile** more watery, and so may used to prevent gall-stones; it is sometimes very useful in betes.

U.S.P. Sodii Santoninas. SANTONINATE OF SODIUM. $2NaC_{15}O_4.7H_2O$; 698.

PREPARATION.	DOSE.
Trochisci Sodii Santoninatis	1 grain in each, 1–5 lozenges.

CHARACTERS.—Colourless, transparent, tabular, rhombic crys-, slowly coloured yellow by exposure to light, slightly efflo-cent in dry air, odourless, having a mildly saline and somewhat er taste, and a slightly alkaline reaction.

REACTIONS.—The aqueous solution, on the addition of hydrochloric acid, osits a crystalline precipitate, which is soluble in chloroform, and which ds, with alcoholic solution of potassa, a scarlet-red liquid gradually ming colourless.

DOSE.—8 to 10 grains.

USES.—This substance has been introduced into the U.S.P. an **anthelmintic.**

Sodii Sulphis, B. and U.S.P. SULPHITE OF SODIUM. $SO_3.7H_2O$; 252.

CHARACTERS.—Colourless, transparent, monoclinic prisms, prescent in dry air, odourless, having a cooling saline and phurous taste.

REACTIONS OF SODIUM SULPHITE, BISULPHITE, AND HYPOSULPHITE.—They evolve sulphurous acid vapours, recognised by their giving the smell of ning sulphur on the addition of hydrochloric acid to an aqueous solution. hyposulphite is distinguished from the sulphites by the acid causing hur to be deposited from the solution, and thus rendering it turbid, whilst tions of the sulphites remain clear. The sulphites are distinguished n each other by the bisulphite having an acid and the sulphite a neutral ebly alkaline reaction.

DOSE.—5 to 20 grains, or even up to 1 drachm (3·9 gm.).

USES.—A solution of 1 part in 8 of water is used in case aphthæ in the mouth; it has been given also to destroy sarc and torulæ in cases of yeasty vomiting (*vide* Sulphurous A p. 572). In some cases of boils the sulphite and hyposulphit 15 to 20 grain doses every 2 or 3 hours are said to have effe a cure.

U.S.P. Sodii Bisulphis. BISULPHITE OF SODIUM. $NaHS$ 104.

CHARACTERS.—Opaque, prismatic crystals, or a crystallin granular powder, slowly oxidised, and losing sulphurous aci exposure to air, having a faint sulphurous odour, and a disag able sulphurous taste.

DOSE.—15 to 60 grains.

USES.—The same as those of the sulphite.

U.S.P. and Appendix B.P. Sodii Hyposulphis. HYPO PHITE OF SODIUM. $Na_2S_2O_3.5H_2O$; 248.

CHARACTERS.—Large, colourless transparent prisms or pla no smell; cooling, rather bitter taste.

USE.—It is an antiseptic and deodoriser like the sulph Chiefly used as a reagent to estimate iodine (*vide* p. 556).

B.P. Sodii Valerianas. VALERIANATE OF SODIUM. NaC_5H

CHARACTERS.—In dry white masses, without alkaline reac entirely soluble in rectified spirit, and giving out a powe odour of valerian on the addition of dilute sulphuric acid.

PREPARATION.—By distilling amylic alcohol with a mixture of d sulphuric acid and an aqueous solution of bichromate of potass $2K_2Cr_2O_7 + 8H_2SO_4 = 2(Cr_2(SO_4)_3) + 2K_2SO_4 + 8H_2O + 3O_2$; and $C_5H_{11}HC$ $= HC_5H_9O_2 + H_2O$. The valerianic acid thus obtained is saturated w solution of soda and dried: $HC_5H_9O_2 + NaHO = NaC_5H_9O_2 + H_2O$.

DOSE.—$\frac{1}{2}$ to 5 grains.

PREPARATION IN WHICH VALERIANATE OF SODIUM IS USED.

Zinci Valerianas.

USE.—As an **antispasmodic** in hysteria. It is chiefly for making the zinc salt.

LITHIUM. Li; 7.

SOURCES OF LITHIUM.—Native silicates and phosphate lithium and other metals.

REACTION.—It is recognised by the *red* colour which it giv flame. This appears to be more brilliant when the salt is converted into chloride by addition of hydrochloric acid.

GENERAL IMPURITIES OF LITHIUM.—Alkalis, alkaline salts, metals.

PREPARATION OF LITHIUM SALTS.

Lithium Salt	Is prepared from	By
arbonate, B. and U.S.P.	Lithium chloride obtained from minerals	Precipitating with carbonate of ammonium.
itrate, B. and U.S.P.	Lithium carbonate .	Dissolving in citric acid.
enzoate, U.S.P. .	Ditto .	Neutralising in hot solution with benzoic acid, filtering, and evaporating to dryness, or crystallising.
alicylate, U.S.P. .	Ditto .	Neutralising hot solution with salicylic acid, filtering, and evaporating.
romide, U.S.P. .	Ditto .	Neutralising with sulphuric acid, and decomposing the sulphate thus obtained by bromide of potassium.

TESTS.—The alkalis are detected by igniting the lithium salt and converting the carbonates which remain (when the acid has been an organic one, as ic or salicylic) into chloride by the addition of hydrochloric acid. On porating the filtered solution to dryness, 1 part of the residue should be pletely soluble in 3 parts of alcohol, and should give no precipitate on the ition of an equal volume of stronger ether, U.S.P. (Alkaline salts, if sent, would give a precipitate.) A solution in water of another portion of residue should give no precipitate with a solution of oxalate of ammonium sence of alkaline earths), and no precipitate or colour with hydrosulphuric l or ammonium sulphide (absence of metals, U.S.P.).

GENERAL ACTION OF LITHIUM SALTS.—The action of lithium on muscle, nerves, and nerve-centres is very much like that of tassium (*vide* p. 605), but is more powerful.

Lithii Carbonas, B. and U.S.P. CARBONATE OF LITHIUM. CO_3; 74.

CHARACTERS.—In white powder or in minute crystalline grains, aline in reaction.

SOLUBILITY.—It is soluble in 100 parts of cold water, insoluble in alcohol.
REACTIONS.—It dissolves with effervescence in hydrochloric acid; and the tion evaporated to dryness leaves a residue of chloride of lithium, which municates a red colour to the flame of a spirit-lamp, and redissolved in er yields a precipitate with phosphate of sodium.

DOSE.—3 to 6 grains.

PREPARATION.

B.P.

Liquor Lithiæ Effervescens. LITHIA WATER (10 grains in 1 pint of water rated with carbonic acid), given in quantities of 5 to 10 fluid ounces.

USES.—The urates of lithium being much more soluble than se of either potassium or sodium, lithia is often employed in

preference to these other alkalis in gout. It is given intern in order to aid in the elimination of uric acid by the kidneys prevent the gouty paroxysm, and to lessen the acidity of urine, to prevent the deposit of uric acid gravel or calculi in kidneys or bladder, and also to aid in their solution when alre formed. It is applied locally to parts affected with gouty infl mation, in order to aid in the solution and absorption of urate of sodium in the tissues. For this purpose it may be app to stiff joints and chalk-stones, whether covered by the skin already laid bare by ulceration. A solution of lithia, five gra to the ounce, is kept constantly applied to the part for sev weeks together.

Lithii Citras, B. and U.S.P. CITRATE OF LITH $Li_3C_6H_5O_7$; 210.

CHARACTERS AND TESTS.—A white amorphous powder, d quescent, and soluble in water without leaving any residue.

REACTIONS.—Heated to redness it blackens, evolving inflammable ga and leaving a residue of lithium carbonate which gives the usual reactio

DOSE.—5-10 grains.

USE.—It has a similar action to the carbonate, and may used in its stead where we wish to avoid any local action u the stomach itself.

U.S.P. Lithii Benzoas. BENZOATE OF LITHIUM. LiC_7H_5 128.

CHARACTERS.—A white powder, or small shining scales p manent in the air, odourless or having a faint benzoin-l odour; of a cooling sweetish taste, and a faintly acid reaction

REACTIONS.—When heated, the salt fuses; at a higher temperatur chars, emits inflammable vapours having a benzoin-like odour, and fin leaves a black residue of an alkaline reaction, and imparting a crim colour to a non-luminous flame. On mixing the aqueous solution wit dilute solution of ferric sulphate, a flesh-coloured precipitate is produced.

DOSE.—8-30 grains (0·5-2 gm.).

USES.—It has been used as a remedy for gout and uric ac

U.S.P. Lithii Bromidum.—*Vide* p. 556.

U.S.P. Lithii Salicylas. SALICYLATE OF LITHI $2LiC_7H_5O_3.H_2O$; 306.

CHARACTERS.—A white powder, deliquescent on exposure air, odourless, or nearly so, having a sweetish taste and a fain acid reaction.

SOLUBILITY.—Very soluble in water and in alcohol.

REACTIONS.—When strongly heated the salt chars, emits inflamma vapours, and finally leaves a black residue having an alkaline reaction imparting a crimson colour to a non-luminous flame. On supersaturat the dilute aqueous solution with hydrochloric acid a bulky white precipit

btained, which is soluble in boiling water, from which it crystallises on ling; also soluble in ether; and producing an intense violet colour with ric salts.

USES.—It is used as a remedy in gout and rheumatism, and intended to unite the properties of salicylic acid and lithium. is less irritant to the stomach than salicylic acid.


DOSE.—20–40 grs. (1·3–2·6 gm.).

MONAD METALS.—GROUP II.


AMMONIUM SALTS. AMMONIA. NH_3; 17.

Ammonium salts are well-defined, like those of potassium and lium, but the base, instead of being a so-called element, is own to be a compound of nitrogen and hydrogen. They are med by the direct union of ammonia, NH_3, with acids. Thus monia and hydrochloric acid unite directly to form ammonium oride, $NH_3 + HCl = NH_4Cl$. In the case of other members of metallic group this direct union with the components of the d does not occur, the metal replacing hydrogen, e.g. $Zn + 2HCl$ $ZnCl_2 + H_2$. This exception to the general rule may be avoided regarding the compounds of ammonia with acids as not being med by the direct union of ammonia with the acids, but by replacement of hydrogen in a basylous radical ammonium, I_4.


In gaseous **ammonia** the nitrogen may be posed to be **triad** with its three affinities urated by hydrogen, thus,




In the radical **ammonium** the nitrogen is posed to be **pentad**, four of its affinities being urated by hydrogen, the other being free to te with an atom of some other element, thus,



In ammonium oride this free nity is saturated chlorine



In liquor ammoniæ this free affinity is saturated by hydroxyl,



The atoms of hydrogen in ammonia or in ammonium can be laced by organic radicals, and **compound ammonias** are med. When the organic radical which replaces the hydrogen f a positive nature, the compounds are termed **amines**, but t is of a negative nature they are termed **amides**.

Ammonium, NH_4, does not exist in the free state, a whether the double molecule, N_2H_8 or $\begin{matrix}NH_4\\|\\NH_4\end{matrix}$, exists separat is uncertain.

It has been supposed to form an amalgam with mercu When mercury, potassium, and sal-ammoniac are mixed, mercury swells up enormously and forms a pasty amalg This may consist of ammonium and mercury, but it soon dec poses into mercury, ammonia, and hydrogen, so that some h supposed it to be nothing more than mercury which has absor a certain quantity of gas, as the mercury in this condition yi to pressure in the same way as froth does in other liquids. all events the salts of ammonium correspond very closely w those of potassium and sodium. In their general reactions t differ, however, in the fact that ammonia is volatile, whe potassium and sodium are not.

SOURCES OF AMMONIUM SALTS.—Ammonia is formed chi by the union of the nitrogen and hydrogen contained in ani or vegetable tissues during the processes of decomposition destructive distillation. The principal commercial source ammonium salts is the ammoniacal liquor from gas-works, tho some of it is also obtained by the dry distillation of bones making animal charcoal.

GENERAL REACTIONS OF AMMONIUM SALTS.—Like potash soda, ammonia is not precipitated by most reagents. It is cognised by its volatile alkaline character. It is given off f any of its salts on the addition of caustic potash or soda to th and is then distinguished by its peculiar smell, and by its v tile alkaline character—turning a piece of red litmus-paper and turmeric paper brown, when they are held above the t glass in which the ammonium salt has been mixed with pot or soda. It also forms white fumes of ammonium chloride w brought near to strong hydrochloric acid.

GENERAL IMPURITIES OF AMMONIUM SALTS.—As all the s are obtained from the chloride or sulphate, chlorides or sulph may be present. Iron may be present, as the chloride is usu sublimed in an iron pot, and, if the heat employed be too gr some ferric chloride sublimes along with the ammonium chlo and gives it a reddish colour. Some lead may also be pre from the leaden domes into which the ammonium chlorid sublimed.

GENERAL TESTS.—Lead and iron are detected by hydro phuric acid, or ammonium sulphide, and iron also by ferrocya of potassium. As the gas liquor contains many empyreum substances, these may sublime, and they are tested for in bonate of ammonium (U.S.P.) by solution of permanganat potassium. The colour of this ought not to alter after stan for five minutes.

PREPARATION OF AMMONIUM SALTS.

Is prepared	From	By
mmonium Chloride, B. and U.S.P.	Gas liquor . .	Adding hydrochloric acid and subliming in iron pots covered with leaden domes; or by adding sulphuric acid, and subliming the ammonium sulphate with sodium chloride in the same way.
mmonium Sulphate, U.S.P.	Ditto . .	Adding sulphuric acid and subliming.
iquor Ammoniæ fortior, B.P.; Aqua Ammoniæ fortior, U.S.P.	Ammonium chloride, or sulphate	Heating with lime, and saturating a quantity of water with the gaseous ammonia (NH_3) given off:— $2NH_4Cl + Ca(OH)_2 = CaCl_2 + 2NH_3 + 2H_2O$.
iquor Ammoniæ, B.P.; Aqua Ammoniæ, U.S.P.	Ditto . .	Is simply liquor ammoniæ fortior diluted with 2 parts of water.
mmonium Carbonate, B. and U.S.P.	Ditto . .	Subliming with calcium carbonate.
mmonium Valerianate, U.S.P.	Ditto . .	Mixing with lime and neutralising valerianic acid with the ammonia given off.
mmonium Iodide, U.S.P.	Ammonium sulphate	Decomposing by potassium iodide, precipitating potassium sulphate by alcohol, filtering, and evaporating.
mmonium Bromide, B. and U.S.P.	Ditto .	Same process as for iodide, substituting bromide for iodide of potassium. Or by neutralising hydrobromic acid with ammonia.
quor Ammonii Acetatis, B. and U.S.P.[1]	Ammonium carbonate .	Neutralising with acetic acid.
piritus Ammoniæ Aromaticus, B. and U.S.P.	Ammonium carbonate and liquor ammoniæ	Distilling with volatile oil of nutmeg, oil of lemon, rectified spirit, and water, B.P. Oil of lemon, of lavender flowers, and of pimenta are the flavouring agents, U.S.P.
quor Ammonii Citratis Fortior, B.P.	Liquor ammoniæ fortior	Neutralising with citric acid. It would be better prepared by neutralising ammonium carbonate with citric acid.
quor Ammoniæ Citratis, B.P.	Liquor ammonii citratis	By diluting with water five times.
mmonium Phosphate, B. and U.S.P.	Liquor ammoniæ .	Neutralising with phosphoric acid.
mmonium Sulphide	Ditto .	Saturating with hydrogen sulphide.
mmonium Nitrate, B. and U.S.P.	Liquor ammoniæ or carbonate	Neutralising with dilute nitric acid, evaporating and fusing.

GENERAL ACTION OF AMMONIUM SALTS. — This has already n described, as well as the modifications induced in it by erent acid radicals (p. 602). The tetanus produced by ammia and ammonium chloride is due to their action on the

[1] Liquor ammonii acetatis fortior, B.P., is made from the carbonate, and liquor monii acetatis is prepared by diluting the strong solution with water.

spinal cord, and not on cerebral centres, for it persists, like th of strychnine, after section of the cord. The paralysing acti of ammonium chloride on the **muscles** modifies the tetanus, so far that after the first spasm, irritation applied to the sk does not cause tetanic convulsions, but only a single refl twitch. This effect is usually ascribed to the paralysing acti on the **motor nerves**, but it seems really to be due to an affecti of the muscles (Fig. 167), as well as to a disturbance of the relati between the muscle and motor nerve. Amylamine, which is compound ammonia, has a paralysing action on muscle simil to ammonia, as shown in Fig. 168. When a muscle has be poisoned by some ammonium salt, a single stimulation applied




FIG. 167.—Tetanus-tracing to show the paralysing action of ammonium sulphate on muscle. first contraction of the poisoned muscle is nearly as great as that of the unpoisoned one, bu soon becomes exhausted, and the curve rapidly falls during the continuance of the stimulat while that of the normal muscle rather rises.

the nerve causes a strong contraction like that of an unpoison muscle; but a second stimulus has sometimes little or no tion, and when the muscle is stimulated directly it soon becom exhausted. Ammonia is a powerful muscular irritant, causi contraction and subsequent rigor mortis when applied directly voluntary muscle.




FIG. 168.—Tetanus-tracing to show the paralysing action of amylamine on muscle. Cf. Fig. 1(

Ammonium salts are said to increase the secretion of **mucous glands** of the **bronchi** and of the **intestine**, as well that of the **sweat-glands** and of the **kidneys**. Ammonia appe to be converted almost entirely into **urea** in the blood of ma mals, but in birds it is converted into uric acid.[1]

[1] Schröder, quoted by Kmerin, *Ztschr. f. Biol.*, xxi. p. 76.

It increases the formation of **glycogen** in the **liver.**[1]

Neither ammonia, nor its carbonate, nor its salts with organic ids diminish, but rather increase the acidity of the urine, and this ammonia differs from potash, soda, and lithia.

Ammonii Chloridum, B. and U.S.P. CHLORIDE OF AMONIUM. NH_4Cl; 53·4.

CHARACTERS.—In colourless, inodorous, translucent, fibrous asses, tough, and difficult to powder.

SOLUBILITY.—It is soluble in water and in rectified spirit.

REACTIONS.—When heated it volatilises without decomposition, and ves no residue. Its solution in water gives the reactions of ammonia 634) and a chloride (p. 594).

PREPARATION. U.S.P.

	DOSE.
Trochisci Ammonii Chloridi. 2 grains in each	.....1 every hour or two.

DOSE.—5 to 20 grains.

ACTION AND USES.—Cold is produced during the process of lution in water of ammonium chloride, and so its solution has en used **locally** in headache, inflammation of the brain, mania, d apoplexy. It has been employed as a lotion to remove ecchyoses, to prevent discoloration in bruises and sprains, and to allay hing in prurigo. It has been applied locally as a dressing in scess of the mamma, and to remove glandular enlargements. As gargle, it has been used to cause contraction of the enlarged bby uvula, and to relieve the cough which the tickling of the arynx by the uvula often causes.

A **small dose** of 5 to 7 grs. of ammonium chloride has effect, but if taken frequently it causes discomfort and heat the stomach, slight headache, diuresis, and an increased secreon of mucus from the intestine, although the stools are not more merous.

Large doses given to animals often cause pain and excitent, then collapse (no diarrhœa), convulsions, and death. The omach is congested, the mucous membrane swollen, and the ithelial cells easily separated.

The same symptoms are produced when ammonium chloride applied to a wound, and the same *post-mortem* appearances are en in the stomach.

It thus seems to have a special action on the **gastric mucous embrane.** It is used in Germany in cases which are usually pposed to be due to a catarrhal state of the stomach—viz. hen there is loss of appetite, sickness, bad taste in the mouth, lness in the stomach, and flatulence, with a coated tongue, and ong with these bronchial catarrh without fever. Ammonium

[1] Rohmann, *Centralblatt f. klin. Med.*, No. 36, 1884.

carbonate is preferred when there is much cough or the per is weak.

It is also used alone in **bronchial catarrh**, when this either come on without fever, or the feverish symptoms h passed off. It is supposed to have the power of increasing secretion of mucus in the bronchi as well as in the intestine, a it is therefore not given when the expectoration is profuse, only when it is scanty and difficult to bring up.

It has been given to relieve the vomiting and heartbu occurring in cancer of the stomach. It is said to have powerful action on the **liver** (p. 636), and has been stron recommended in chronic congestion and hepatic abscess, as v as in dropsy depending upon hepatic disease. For its alterat action it has been given in muscular rheumatism, rheuma pains, and neuralgia. In neuralgia it should be given in h drachm doses several times a day; but if the pain is not relie after four or five doses have been given, it may be discontinu It is also useful in neuralgic headaches.

Liquor Ammoniæ Fortior, B.P.; Aqua Ammoniæ F tior, U.S.P. Strong Solution of Ammonia, B.P.; Strong Water of Ammonia, U.S.P.

Characters.—A colourless liquid, with a characteristic a very pungent odour, and strong alkaline reaction. Speci gravity 0·891.

Preparations in which Strong Solution of Ammonia is used.

B.P.	U.S.P.
Ammonii Phosphas.	Spiritus Ammoniæ
Linimentum Camphoræ Compositum (p. 516).	
Liquor Ammoniæ.	
„ Ammonii Citratis Fortior.	
Spiritus Ammoniæ Aromaticus.	
„ „ **Fœtidus.**	
Tinctura Opii Ammoniata.	

Action and Uses.—When applied to the nose, the vapour strong ammonia acts as a powerful irritant. It **stimulates** t nasal branches of the fifth nerve, and thus reflexly excites t vaso-motor centre and raises the blood-pressure. It thus ten to prevent or to remove conditions of shock and syncope. Wh applied for too long a time, or in too concentrated a form, may produce inflammation of the mucous membrane and res ratory passages. Applied to the skin it quickly evaporates, a has but a slight **rubefacient** effect, but when its evaporation prevented it passes through the epidermis and acts as a power **vesicant**. When swallowed in large quantities, and undilut it may produce gastro-enteritis, but on account of the vapo gaining access to the air-passages and causing immediate suf cation, it may cause death in a few minutes. Along with t gastro-enteritis there may be comatose symptoms due to t

ction of the drug itself on the **brain** after absorption, and h this it differs from poisoning by caustic potash or soda. It timulates the **circulation** reflexly through the nerves of the omach, and after its absorption stimulates both the **respiration** nd circulation by its direct action upon the circulatory and espiratory nerve-centres.

Uses.—**Inhalation** of its fumes is used to prevent drowsiness r fainting, or to recover persons from a faint, or from shock, or om the narcosis produced by opium, syncope, or the depression aused by vascular sedatives. It should not be applied for too ng a time, lest bronchitis be induced. It is sometimes employed a milder form to cut short nasal catarrh, to lessen pain in the ose and forehead, and diminish the expectoration in chronic ronchitis. It is used as a **counter-irritant** to the skin in heumatic pains, stiffened rheumatic joints, and bronchitis. As **vesicant** it may be employed where the use of cantharides is bjectionable. A pledget of lint, somewhat larger than the blister esired, is moistened with ammonia, covered with a watch-glass, nd applied to the skin until a red ring forms round the glass. he pledget is then removed and a poultice applied. The poison f nettles and insects is frequently of an acid character, and mmonia rubbed over the part stung will lessen the pain and welling. The injection of ten drops of strong liquor ammoniæ, iluted with three parts of water, into the veins, has been recom- ended in cases of **snake-bite.** It may be useful possibly in ites of less poisonous snakes, but is of no utility in bites by he cobra or daboia. It may be given internally, diluted, as a timulant in cases of syncope, and in the depression, weakness, nd faintness to which some women are subject. In these cases he liquor ammoniæ may be employed as a **substitute for lcohol,** and thus the tendency to contract habits of drinking ay be counteracted. It may be used, like other alkalis, to timulate the secretion of gastric juice, and especially where we o not wish to diminish the acidity of the urine or render it lkaline, and also where we wish to stimulate the **nervous ystem,** as in cases of anæmia and debility, and more especially here the stomach is relaxed and distended with gas. It also timulates the **intestines,** and aids the expulsion of gas from hem. It is therefore very useful in the flatulence and colic of hildren. It may be employed to lessen the watery discharge om the bowels where this persists after the removal of the irri- nt which has caused it.

U.S.P. Spiritus Ammoniæ. Spirit of Ammonia.—An alco- olic solution of ammonia containing 10 per cent. by weight of he gas.

Preparation.—By warming strong water of ammonia so as to expel the mmoniacal gas, passing this into cold alcohol, and diluting with alcohol to he necessary strength.

Liquor Ammoniæ, B.P.; Aqua Ammoniæ, U.S.P. Solution of Ammonia, B.P.; Water of Ammonia, U.S.P.—Ammonia Gas, NH_3; 17; dissolved in water.

Preparation.—By mixing 1 part of strong solution of ammonia with water.

Preparations.

B.P.	U.S.P.
Linimentum Ammoniæ (p. 516).	Spiritus Ammoniæ Aromaticus Linimentum Ammoniæ (p. 51

Dose.—10 to 30 minims well diluted.

Uses.—This may be used as a local application in a simi manner to the liquor ammoniæ fortior, except that it has not same powerful vesicant action. It may be given internally similar purposes. When mixed in the proportion of two oun of liquor ammoniæ with two ounces of common salt and th drachms of camphorated spirit of wine to thirty-two ounces water, it forms Raspail's sedative solution, for the treatment headaches occurring at the menopause, or due to uterine rangement.

Ammonii Carbonas, B. and U.S.P. Carbonate of Ammonium, $N_3H_{11}C_2O_5$, B.P. $NH_4HCO_3NH_4NH_2CO_2$; 157, U.S.P.

A volatile and pungent ammoniacal salt, produced by submitting a mixture of sulphate or chloride of ammonium a carbonate of calcium to sublimation. It consists of a mixture acid carbonate of ammonium (NH_4HCO_3), and carbamate ammonium ($NH_4NH_2CO_2$).

Characters.—In translucent crystalline masses, with strong ammoniacal odour, and alkaline reaction.

Solubility.—Soluble in cold water, more sparingly in spirit.

Reactions.—It volatilises entirely when heated, and is readily dissol by acids with effervescence.

20 grains of Carbonate of Ammonium } neutralise { 23½ grains Citric Acid. / 25½ grains Tartaric Acid

Dose.—3 to 10 grains as stimulant and expectorant, 30 grai as emetic.

Preparations in which Carbonate of Ammonium is used.

B.P.	U.S.P.
Liquor Ammonii Acetatis.	Spiritus Ammoniæ Aromaticus.
Spiritus Ammoniæ Aromaticus.	

Uses.—Carbonate of ammonium may be used as an inha tion, and may be given internally, for similar purposes to liqu ammoniæ.

It is an **emetic**, and may be employed in cases of bronchit where the bronchial tubes are choked with mucus, and t patient's circulation is weak. In smaller doses it stimulates t secretion of gastric juice, and may be used in atonic dyspeps

tulence, and colic to relieve sinking and depression, and as substitute for alcoholic stimulants. When employed for this ter purpose, five to ten grains may be given along with ten nims of tincture of capsicum in an ounce of bitter infusion, to taken whenever the feeling of sinking comes on, or the craving alcoholic stimulants is experienced.

From its power of stimulating the respiratory centre, it is ployed as a stimulating **expectorant** in chronic bronchitis, in broncho-pneumonia of children, and in asthma depending on diac disease. It is also given in measles, and has been re-mmended as almost a specific in scarlet fever, in doses of three five grains, every one, two, or three hours, according to the erity of the case, no acid drinks or fruits being allowed to the ient at the time.

Carbonate of ammonium has been supposed to have the ver of preventing iodism, when given along with iodide of assium.

Spiritus Ammoniæ Aromaticus, B. and U.S.P. AROMATIC RIT OF AMMONIA (SAL VOLATILE).—It consists of carbonate of monium, and strong solution of ammonia diluted with alcohol l water. It is flavoured with volatile oil of nutmeg and oil of on in the B.P., and with oil of lemon, oil of lavender flowers, l oil of pimenta, in the U.S.P.

DOSE.—20 to 60 minims in water.

PREPARATIONS.

Tinctura Guaiaci Ammoniata. B. and U.S.P.
„ Valerianæ Ammoniata. „ „

USES.—It is very commonly taken to relieve feelings of faint-s and depression, and is much safer than alcohol, which might erwise be employed. It may be used also for other purposes ead of carbonate of ammonium, to which it has a similar on.

B.P. Liquor Ammonii Acetatis Fortior. STRONG SOLUTION CETATE OF AMMONIUM. Sp. gr. 1·073.

DOSE.—25 to 75 minims.

Liquor Ammonii Acetatis, B. and U.S.P. SOLUTION OF TATE OF AMMONIUM.—Acetate of Ammonium, $NH_4C_2H_3O_2$, olved in water.

DOSE.—2 to 6 fluid drachms.

USES.—It is used as an eyewash, and as a lotion to inflamed s. When given internally it acts as a **diaphoretic**, if the y be kept warm, or as a **diuretic** if it be cool. As a dia-retic it is given when the skin is hot and dry, and is very uently used, especially combined with spirit of nitrous ether, never a feverish condition is present, whether its cause be

known or not. It is especially used in the exanthemata influenza and catarrh.

B.P. Liquor Ammonii Citratis Fortior. STRONG SOLU OF CITRATE OF AMMONIUM. Neutral. Sp. gr. 1·209.

DOSE.—½ to 1½ fl. dr.

B.P. Liquor Ammonii Citratis. SOLUTION OF CITRAT AMMONIUM.—Citrate of Ammonium, or $(NH_4)_3.C_6H_5O_7$, disso in water.

DOSE.—2 to 6 fluid drachms.

USES.—Like the solution of the acetate, but more agreea

B.P., Appendix, Oxalate of Ammonium $(NH_4)_2C_2O_4.H$

PROPERTIES.—Colourless prismatic crystals, no smell.

USES.—Used to test for calcium, and to separate it magnesium.

Ammonii Phosphas, B. and U.S.P. PHOSPHATE OF MONIUM. $(NH_4)_2HPO_4$; 132.

CHARACTERS.—In transparent colourless prisms.

SOLUBILITY.—Soluble in water, insoluble in rectified spirit.

REACTIONS.—The aqueous solution gives the reactions of ammoni of a phosphate (p. 595).

DOSE.—5 to 20 grs. freely diluted.

USES.—It has been used as a remedy in cases of gou order to eliminate urate of sodium from the system, the th of its action being that it decomposes the insoluble ura sodium, converting it into soluble urate of ammonium phosphate of sodium.

Ammonii Bromidum.—*Vide* p. 556.

Ammonii Iodidum.—*Vide* p. 664.

Ammonii Nitras, B. and U.S.P. NITRATE OF AMMO NH_4NO_3; 80.

CHARACTERS.—Colourless crystals, generally in the for long thin rhombic prisms, or in fused masses somewhat quescent, odourless, having a sharp bitter taste and a ne reaction.

REACTIONS.—When gradually heated, the salt melts at 165° to 1 (329° to 331° F.), and at about 185° C. (365° F.) it is decomposed into r oxide gas and water, leaving no residue. The aqueous solution of th when heated with potassa, evolves vapour of ammonia. On heating tl with sulphuric acid, it emits nitrous vapours.

USE.—It is only used for the preparation of nitrous oxi

U.S.P. Ammonii Sulphas. SULPHATE OF AMMO $(NH_4)_2SO_4$; 132.

CHARACTERS.—Colourless transparent rhombic prisms, pe nent in the air, odourless, having a sharp saline taste, a neutral reaction.

USES.—It is not used internally, but is only employed for the eparation of other salts of ammonium, of ammonium alum .P.) and sulphate of iron and ammonium (U.S.P.).

U.S.P. Ammonii Valerianas. VALERIANATE OF AMMONIUM. $H_4C_5H_9O_2$; 119.

CHARACTERS.—Colourless or white quadrangular plates, deliescent in moist air, having the odour of valerianic acid, a arp and sweetish taste, and a neutral reaction.

SOLUBILITY.—Very soluble in water and in alcohol.

REACTIONS.—When heated the salt fuses, gives off vapour of ammonia, l of valerianic acid, and is finally dissipated without leaving a residue.

DOSE.—2 to 8 grs. (0·13 to 0·52 gm.).

USE.—It is chiefly used, like valerian, in cases of hysteria.

Ammonii Benzoas, B. and U.S.P. BENZOATE OF AMMOM, $NH_4C_7H_5O_2$; 139.

CHARACTERS.—Thin white four-sided laminar crystals, permanent in the air, having a slight odour of benzoic acid, a ine, bitter, afterwards slightly acrid taste, and a neutral ction.

REACTIONS.—When strongly heated the salt melts, emits vapours having odour of ammonia and of benzoic acid, and is finally wholly dissipated.

USES.—It is used as a diuretic, and to render the urine acid ere there is a tendency to phosphatic deposits.

B.P. Sulphide of Ammonium.—$(NH_4)_2S$. TEST SOLUTION.

PROPERTIES.—Greenish-yellow transparent liquid, with a greeable pungent odour. S.G. 0·999.

PREPARATION.—Saturate a solution of ammonia by sulphuretted hydrogen.

DOSE.—3 minims, cautiously increased.

ACTIONS.—In small doses it increases secretion, especially of nchi and skin, and is thus used as a sudorific and expectorant hronic skin-diseases, rheumatism, and bronchitis; in large es it causes giddiness, drowsiness, faintness, and nausea. le given.

It is chiefly used as a test.

CHAPTER XXV.

METALS—(*continued*).

Class II.—DYAD METALS.

Group I.—METALS OF THE ALKALINE EARTHS.

Calcium, *Strontium*, Barium,

Appendix.—METALS OF THE EARTHS.

Aluminium, (? triad) *Beryllium* (dyad), *Zirconium* (tetrad), *N*
bium (tetrad), Cerium, *Lanthanum*, *Didymium*, *Yttri*
Erbium (triads).

Group II.—MAGNESIUM.

Group III.—COPPER, ZINC, SILVER, *Cadmium*.

Group IV.—MERCURY.

This large class contains a number of metals which l
widely different characters and reactions. Yet it will be
from the following table that the successive addition of
reagents divides the metals tolerably nearly into those gr
which agree in their physiological action. In some resp
Groups I. and II. of Class 2 are perhaps more closely conne
with the alkaline metals than with the heavy metals.

REACTIONS OF THE METALS IN CLASS II.

	Hydrochloric Acid	Sulphuretted Hydrogen	Ammonium Sulphide	Ammonium Carbonate	Ammonia and Sodium Phosphate
UP I.					
cium	No precipitate.	No precipitate.	No precipitate.	White precipitate.	
ontium	Do.	Do.	Do.	Do.	
rium	Do.	Do.	Do.	Do.	
NDIX.)					
minium	Do.	Do.	White (Hydrate)		
ther earthy etals	Do.	Do.	Do.		
UP II.					
gnesium...	Do.	Do.	No precipitate.	No precipitate.	White ppt. (phosphate).
UP III.					
c.....	Do.	Do.	White (sulphide)		
pper	Do.	Black ppt.			
dmium	Do.	Yellow ppt.			
ver.....	White curdy ppt. soluble in ammonia.	Black ppt.			
UP IV.					
cury as sub- lt	White ppt.	Black ppt.			
as persalt..	No precipitate	Do.			

It must be borne in mind that the above reagents are used ccessively, and each remains in the solution. Thus when monium sulphide is added, part of it is decomposed by the drochloric acid and ammonium chloride is formed. It is on ount of the presence of the ammonium chloride in the liquid t magnesium is not precipitated by the ammonium sulphide, ile aluminium is.

Class II. GROUP I.

GENERAL ACTION.—In regard to the action on the **nervous** stem of the chlorides of calcium, strontium, barium, beryllium, ymium, erbium, and lanthanum, these substances fall into groups—

(*a*) Containing beryllium, calcium, strontium, and barium;
(*b*) Containing yttrium, didymium, erbium, and lanthanum.

Group (a) has a tendency to **increase reflex** action, as evi- ced by spasm or tremor in the frog.

With **group (b)** reflex action in the cord appears to be little ected, but its members appear to have a tendency to **paralyse** tor centres of the **brain** in the frog.

Group (*a*) all paralyse **motor nerves** to some extent. Lan- num has also a slight paralysing action, but the other mem- s of the group (*b*) have not, agreeing in this respect with ium and rubidium, and differing from all the others.

In regard to their action on muscle these substances can be divided into sub-groups. Their action on muscle has been already described (p. 135).

The lethal activity, on frogs, of the chlorides of the alkalis and earths is not in proportion to their atomic weight. It is as follows, potassium being most powerful, and calcium least powerful:—potassium, beryllium, rubidium, barium, ammonium, cæsium, lithium, lanthanum, didymium, erbium, strontium, yttrium, sodium, calcium (*vide* p. 29).

Barium causes contraction of the ventricle of the frog's heart in much the same way as veratrine, and by its local action on the walls of the vessels causes them to contract. When injected into the circulation it causes enormous rise of blood-pressure at first, followed by stoppage of the heart and consequent fall of pressure. It causes contraction also of the involuntary fibres of the bladder and intestine, so that the lumen of the latter may be almost completely obliterated. The symptoms of poisoning in mammals are probably due to its action on the involuntary muscles of the intestines, heart, and vessels, on the voluntary muscles, and on the nervous system. They are vomiting, colic, diarrhœa, muscular weakness and cramp, ringing in the ears, tightness over the heart, and general convulsions. Injection of sulphate of sodium into the veins appears to counteract the effect of barium,[1] and the simultaneous injection of potassium salts will prevent death from an otherwise lethal dose of barium. The action of barium on muscles and on the heart is abolished by heat in the same way as that of veratrine (p. 128), and the inhabitants of southern climates tolerate much larger doses of barium than those of northern.[3]

Metals of the Alkaline Earths.

Calcium, *Strontium*, Barium.

The only one of these whose preparations are used internally is calcium. At present barium is only used as a test, though possibly it may yet prove useful in muscular tremor (p. 134).

CALCIUM. Ca; 40, or 39·9.

Sources of Calcium-salts.—The chief source is the carbonate, found native as chalk or limestone.

General Test of Calcium-salts.—The addition of ammonium oxalate to calcium salts causes a white precipitate of calcium oxalate, which is very sparingly soluble in water. It is soluble in hydrochloric, but insoluble in acetic acid.

---

[1] Hermann, *Lehrbuch d. experimentel. Toxicologie*, p. 191.

[2] Brunton and Cash, *Centralblatt für d. med. Wissenschaften*, 1884, p. 545.

[3] Lisfranc, quoted by Lewin, *Nebenwirkungen d. Arzneimittel*, p. 74.

General Preparation of Salts of Calcium.

Is prepared	From	By
eta præparata, B. and U.S.P.	Chalk . . .	The process of elutriation, which consists in stirring with water, pouring off the liquid containing fine particles in suspension, and allowing them to subside.
lx (quicklime), B. and U.S.P.	Chalk or limestone .	Calcining; $CaCO_3 = CaO + CO_2$.
lcii hydras (slaked lime), B.P.	Quicklime . .	Slaking with water.
lcii chloridum, B. and U.S.P.	Limestone or chalk (Carbonate) . .	Neutralising with hydrochloric acid; $CaCO_3 + 2HCl = CaCl_2 + H_2O + CO_2$.
lcii carbonas præcipitata, B. and U.S.P.	Calcium chloride .	Precipitating with excess of carbonate of sodium; $CaCl_2 + Na_2CO_3 = CaCO_3 + 2NaCl$.
lx chlorata (chlorinated lime), B. and U.S.P.	Slaked lime . .	Exposing lime to chlorine gas until saturated: thus is formed chlorinated lime, consisting of a mixture of calcium chloride and calcium hypochlorite.
lcii hypophosphis, B. and U.S.P.	Lime and phosphorus	Heating together with water; removing excess of lime by CO_2, and evaporating.
lcii phosphas, B. and U.S.P.	Bone ash . .	Dissolving in diluted hydrochloric acid, precipitating with ammonia, and drying.

General Impurities.—The chief impurities are aluminium and magnesium.

Tests.—These are usually detected by converting the calcium-salt into oride by hydrochloric acid, and evaporating to dryness so as to drive off excess of acid. The residue is re-dissolved in water and the tests applied he solution. On the addition of saccharated solution of lime, aluminium l magnesium will be precipitated. The B.P. states that only a very scanty cipitate should occur, showing that only traces of magnesium and aluminum are present. The test used in the U.S.P. to detect aluminium is water ammonia; and to detect magnesium, water of ammonia and phosphate of ium. These reagents should not give more than a faint turbidity with te solutions of calcium salts.

B.P. Marmor Album. White Marble. $CaCO_3$.
Hard white crystalline native carbonate of calcium, in masses. ed in producing carbonic acid gas.

B.P. Creta. Chalk. $CaCO_3$. Native friable carbonate of lcium. Used in producing carbonic acid gas.

Preparation.

Creta Præparata.

Calx, B. and U.S.P. Lime. CaO; 56.
An alkaline earth, oxide of calcium, CaO, with some impurities, obtained by calcining chalk or limestone so as to expel rbonic acid.

CHARACTERS.—In compact masses of a whitish colour, wh readily absorb water, and which, when rather less than th weight of water is added, crack and fall into powder with development of much heat.

TESTS.—The powder obtained by the process of slaking, when agit with distilled water, gives, after filtration, a clear solution which ha alkaline reaction, and is shown by the appropriate tests to contain calc and only traces of aluminium and magnesium.

PREPARATIONS.

B.P.	U.S.P.
Calcii hydras.	Liquor Calcis. Potassa cum Calce (p. 608). Syrupus Calcis.

B.P. Calcii Hydras. SLAKED LIME.

Hydrate of lime, $Ca(HO)_2$; 74; with some impurities, rece prepared by pouring 1 pint of water over 2 lbs. of lime metal pot.

SOLUBILITY.—It dissolves in water, but only sparingly, 11 grs. b dissolved by a pint of water at 60° F.; and, contrary to the usual rul solubility is increased by cooling the water, and diminished by heating i

Its solubility is greatly increased by the addition of sugar, as in Liquor Calcis Saccharatus, B.P., or Syrupus Calcis, U.S.P.

PREPARATIONS.

	DOSE.
Liquor Calcis.	1–4 fl. oz.
Liquor Calcis Saccharatus.	15–60 min.

Liquor Calcis Saccharatus, B.P.; Syrupus Calcis, U.S.P. SACCHAR SOLUTION OF LIME, B.P.; SYRUP OF LIME, U.S.P.

PREPARATION.—B.P. Like lime-water, mixing 1 ounce of lime with 2 of s and using them instead of 2 of lime. This mixture contains 7·11 grains of in 1 fluid ounce. U.S.P. Mixing lime (5) and sugar (30) with boiling (50); diluting with an equal volume of water, filtering, and evaporating to parts.

DOSE.—15 to 60 minims.

Liquor Calcis, B. and U.S.P. SOLUTION OF LIME. LIME WATER.

PREPARATION.—B.P. By shaking 2 ounces of slaked lime with 1 gallon of tilled water in a stoppered bottle well for two or three minutes. After t hours the excess of lime will have subsided, and the clear solution may be d off with a syphon as it is required for use, or transferred to a green glass b furnished with a well-ground stopper. In the U.S.P. the lime is first washed ordinary water and afterwards stirred well with distilled water.

It is a saturated solution, and contains a little over half a grain to an oun

DOSE.—1–4 fl. oz.

PREPARATIONS.

B.P.	U.S.P.
Linimentum Calcis (p. 516). Argenti Oxidum. Lotio Hydrargyri Flava. „ „ Nigra.	Linimentum Calcis (p. 517)

USES.—When applied to the surface either of the skin c a mucous membrane from which a watery discharge is issu lime seems to act as a slight **astringent**, possibly becaus combines with the albumen.

Lime-water is therefore sometimes used as a lotion for cracked pples and as a dressing to eczematous surfaces, where it eases e smarting and tingling. It is often mixed with oil, as in lini- ntum calcis, or glycerine for this purpose. The efficacy of e liniment is much increased by the addition of minute quan- ies of carbolic acid.

Linimentum Calcis—better known, perhaps, under the name Carron oil—is used as an application to burns and scalds. It rives its name of Carron oil from its being so extensively used the workmen in the foundries at Carron.

It was formerly made with linseed oil, and this preparation is s fluid, and is often preferable to that made with olive or cotton- d oil. It is useful not only in burns and scalds, but as a ssing to the face in small-pox, and in some cases of eczema ecting a large extent of skin.

Lime-water is also used as an injection to lessen discharges m the ears, urethra, vagina or vulva, in otorrhœa, gleet, and corrhœa, while active inflammation is still present, and as enema to destroy ascarides in the rectum. It may also be d as a wash to the mouth in ulceration. In croup it has n recommended as a solvent for the false membrane. It either applied as spray or by a camel's-hair pencil. When en into the stomach it will act as an **antacid**. It is especially ful in preventing vomiting, and a mixture of milk and lime- ter will often be retained by the stomach and digested when other food can be borne. In children suffering from chronic niting and diarrhœa, where the milk is vomited in hard ps instead of small flakes, lime-water proves very useful.

In typhoid fever it tends to prevent milk from forming hard digested lumps which may irritate the intestine, while it has he same time an astringent action.

It is very useful as an **astringent** in diarrhœa, more especially slight cases of diarrhœa in children. When the child is at breast about one teaspoonful of lime-water mixed with an al quantity of milk should be given to it every three hours, when it is brought up by hand the lime-water is just mixed h the milk which the child ordinarily takes. It has been used liarrhœa in adults depending on ulceration of the intestine, n the view of healing the ulcers by combining with the umen on their surface and thus forming a coating over them, it is not so efficient as other remedies for this purpose.

Only a small quantity is absorbed by the intestine and passes the blood; yet, after it has been used for a little while, urine becomes alkaline from the lime being excreted by the neys. Lime-water has been used in cases of stone, and with siderable benefit. It has been supposed to dissolve stones in bladder; but the good effects which result from its use are bably not due to this cause, which is still problematical.

They are most probably produced by the lime lessening t irritating qualities of the urine, and at the same time acting an astringent on the walls of the bladder and rendering it le irritable.

Liquor Calcis Saccharatus, B.P., or Syrupus Calcis, U.S.I may be given in milk instead of liquor calcis, when it is desir simply to get the effect of the lime and it is unadvisable to dilu the milk, as admixture with liquor calcis would necessarily c It has been used also in acute rheumatism.

Creta Præparata, B. and U.S.P. Prepared Chalk.

Properties.—It is a white powder, or in small lumps whi break into powder readily on pressure. It has no taste or sme

Preparation.—Prepared chalk is simply chalk freed from sand and ot impurities by elutriation (p. 647).

Solubility.—It is insoluble in water, but it dissolves in acids such acetic acid.

Reactions.—While doing so it effervesces strongly, showing that it i carbonate, and the solution gives the reactions of calcium (p. 646).

Impurities.—Silica, barium, strontium, magnesium, iron.

Test.—It should dissolve without leaving any residue in hydrochl acid (absence of silica), B.P. The solution in acetic acid should give no p cipitate with test solution of sulphate of calcium (absence of strontium barium), and the tests for magnesium and iron should not indicate more t traces of these substances, U.S.P.

Dose.—10 to 60 gr.

Officinal Preparations.

B.P.	Dose.
Mistura Cretæ. Chalk mixture. Chalk (1) suspended in cinnamon water (30) by means of gum (1) and sweetened with syrup (2)	1–2 fl. oz.
Pulvis Cretæ Aromaticus. Aromatic powder of chalk. Cinnamon (8), cardamoms (2), cloves (3), nutmeg (6), saffron (6), sugar (50), chalk (22)	10–60 gr.
Pulvis Cretæ Aromaticus cum Opio. Aromatic powder of chalk thoroughly mixed with powdered opium. 1 part of opium in 40	10–40 gr.
U.S.P.	
Mistura Cretæ. Chalk mixture. Compound chalk powder (20), cinnamon water (40), water (40)	½–2 fl. oz.
Pulvis Cretæ Compositus. Compound chalk powder. Prepared chalk (30), powdered acacia (20), sugar (50)	8-60 gr. (½–4 g
Trochisci Cretæ. Chalk lozenges. 4 grains in each	*Ad lib.*

Chalk is also contained in Hydrargyrum cum Creta, B. and U.S.P.

Action.—Carbonate of calcium or chalk possesses the astr gent and antacid powers of lime itself, and is without its irri ing qualities. It can therefore be given in much larger do and so chalk is used, instead of liquor calcis, in the diarrhœ adults accompanied by acidity.

Uses.—Chalk may be used as a dusting powder to the ski excoriations, burns, and ulcers. It forms a useful tooth-pow Internally it serves to arrest diarrhœa, and is often given, what be the cause of the diarrhœa; but when the disease depends u

ne irritating substance in the intestine, the irritant should be noved by a dose of castor oil previous to the administration of chalk. In the form of whiting, chalk forms a useful antidote cases of poisoning by acids, and especially by oxalic acid.

Calcii Chloridum, B. and U.S.P. CHLORIDE OF CALCIUM. $CaCl_2$; 110·8.

CHARACTERS.—Colourless, slightly translucent, hard and fri- e masses, very deliquescent, odourless, having a hot, sharp, ne taste, and a neutral or faintly alkaline reaction.

SOLUBILITY.—Soluble in 1·5 parts of water, and in 8 parts of alcohol at C. (59° F.).

REACTIONS.—The aqueous solution yields the reactions of calcium (p. 646) of a chloride (p. 594).

DOSE.—1 to 3 grains for children, and 10 to 20 for adults in up. May be given in milk after meals.

OFFICINAL PREPARATION.

B.P.

Liquor Calcii Chloridi. SOLUTION OF CHLORIDE OF CALCIUM. Calcium ride 1, water 5 parts. DOSE.—15–50 minims. It is used as a test for tartrates, tes, and oxalates.

USES.—Chloride of calcium was in much greater use formerly n at present. It was strongly recommended by Dr. Warbur- Begbie for cases of strumous enlargement of the cervical nds, for strumous children with hectic, diarrhœa, and loss of etite, and for the chronic diarrhœa of children. It reduced glandular swelling and improved the general health, increas- the appetite: to do good, however, the drug must be taken months and even as long as two years.[1] It has, however, en almost into disuse, and is now practically replaced by cod- r oil and other tonics.

It has a great affinity for water, and is used to remove water m other substances in pharmacy, e.g. in the preparation of olute alcohol or ether.

Calcii Carbonas Præcipitata, B.P.; Calcii Carbonas ecipitatus, U.S.P. PRECIPITATED CARBONATE OF CALCIUM. $CaCO_3$; 100.

CHARACTERS.—A very fine white impalpable powder, perma- t in the air, odourless and tasteless.

SOLUBILITY.—It is insoluble in water or alcohol.

REACTIONS.—Wholly soluble in hydrochloric, nitric, or acetic acid, with ous effervescence. A neutral solution of the salt in acetic acid yields the tions of calcium.

USE.—It may be used as an **astringent** in the same way as lk.

Calcii Bromidum, U.S.P.—*Vide* p. 556.

[1] Warburton Begbie's Works; *New Syden. Soc.*

Calcii Phosphas, B.P.; Calcii Phosphas Præcipita U.S.P. PHOSPHATE OF CALCIUM, B.P.; PRECIPITATED PHOSPH OF CALCIUM, U.S.P. $Ca_3(PO_4)_2$; 310 (*Synonym*, PHOSPHATE LIME).

CHARACTERS.—A light, white, amorphous powder, perma in the air, odourless, tasteless.

SOLUBILITY.—It is insoluble in water or alcohol.

IMPURITIES AND TESTS.—Wholly soluble in nitric or hydrochloric without effervescence (absence of carbonate). A solution of the salt in dil nitric acid, after being mixed with an excess of acetate of sodium, yiel white precipitate with test solution of oxalate of ammonium (calcium), a lemon-yellow precipitate with test solution of ammonio-nitrate of s (phosphate).

DOSE.—1–20 grains. A simple way of giving it is to it with the salt used at meals.

OFFICINAL PREPARATIONS.

B.P.	U.S.P.	DOSE.
It is contained in **Pulvis Antimonialis.**	Syrupus Calcii Lactophosphatis.	1–4 fl. dr. (7·5–15 c

U.S.P. Syrupus Calcii Lactophosphatis. SYRUP OF LACTOPHOSPHATE OF Made by dissolving freshly-precipitated phosphate in lactic acid, and mixing orange-flower water and sugar (22 parts phosphate in 1,000).

ACTION.—Phosphate of calcium is an important constitu of the body, and occurs in considerable quantity wherever ac cell-growth, either normal or pathological, is going on. It fo a large proportion of bones, and Chossat found that when ani were fed on food containing no lime-salts, the bones were During pregnancy, fractures unite slowly, and Milne-Edw found that when animals were supplied with abundance of p phate of calcium fractures united more quickly.

It has been supposed that the constant use of fine flour t to cause premature decay of the teeth, owing to the want of s cient proportion of lime-salts. The decay of the teeth amo Americans has been attributed to the perfection of their machin which completely separates the external parts of the grain makes the flour exceedingly fine and white.

USES.—It frequently lessens or removes toothache, especi that occurring in pregnancy or lactation (p. 353). It is us in cases of chronic diarrhœa in children. It has been rec mended in cases of rapid growth or deficient repair, as in gr ing children, anæmia, and debility from over-work, child-bear suckling, or diseases such as chronic abscess, diarrhœa, leu rhœa, bronchitis, and phthisis. It is frequently given in ric with considerable benefit, although it is well to combine it cod-liver oil. It is often advantageously given, along with i in the form of Parrish's Chemical Food, containing two a half grains of phosphate of calcium and one grain of phosp of iron in every drachm.

Calcii Hypophosphis, B.P. and U.S.P. HYPOPHOSPHITE OF CIUM, $Ca(PH_2O_2)_2$, B.P. $CaH_4(PO_2)_2$; 170, U.S.P.

CHARACTERS.—Colourless or white six-sided prisms, or thin ble scales, of a pearly lustre; permanent in dry air, odourless, ng a nauseous, bitter taste and a neutral reaction.

EACTIONS.—The aqueous solution yields the reactions of calcium (p. 646).

DOSE.—1–10 grains.

OFFICINAL PREPARATION.

B.P.	U.S.P.	DOSE.
None	Syrupus Hypophosphitum	1–2 fl. dr. (3·75 to 7·5 cc.).

U.S.P. Syrupus Hypophosphitum. SYRUP OF HYPOPHOSPHITES. Consists hypophosphites of calcium (35), of sodium (12), and of potassium (12); citric 1), spirit of lemon (2), sugar (500), water q.s. to make 1,000.

USES.—Hypophosphite of lime is useful in the early stages of isis (p. 717), and in nervous debility consequent upon over- or worry. It may be given between two thin slices of bread butter, if no irritability of the stomach be present. It is well egin with a dose of two grains and gradually increase it, as rwise it is apt to cause derangement of the digestion.

Calx Chlorinata, B.P.; Calx Chlorata, U.S.P. CHLORIDE LIME.—*Vide* CHLORINE (p. 549).

Calx Sulphurata, B. and U.S.P. SULPHURATED LIME.—A ure (commonly misnamed sulphide of calcium) consisting ly of sulphide of calcium [CaS; 72] and sulphate of calcium SO_4; 136], in varying proportions, but containing not less 50 per cent. of absolute sulphide of calcium, B.P. (36 per U.S.P.).

CHARACTERS.—A nearly white powder with a smell somewhat mbling that of sulphuretted hydrogen.

REPARATION.—B.P. By calcining sulphate of calcium (7) with wood oal (1) when part of the sulphate is reduced to sulphide.
.S.P. By calcining finely-powdered lime (100) with precipitated sulphur

DOSE.—$\frac{1}{10}$–1 gr.

ACTION.—In large doses it is an irritant to the stomach, but cinal doses usually cause no trouble, or at most slight dis- fort, sometimes giving rise to eructations of sulphuretted ogen, and perhaps to some looseness of the bowels.

USES.—It is used chiefly for its effect on the process of suppura- hastening the discharge of pus if already formed, and check- ts formation if the inflammation be still in its early stage. ulphite of calcium in doses of $\frac{1}{10}$–1 gr. four or five times is said to do good in acne.

Class II.

Group I.—Appendix.

Aluminium. Cerium.

ALUMINIUM. Al; 27·5.

General Sources of Alum Salts.—Aluminium is widely distributed in nature, clays being silicates of alum Two kinds of clay, **kaolin** and **fuller's earth**, being i powders, are used as demulcents (pp. 347 and 446), and ka also as a pill-basis.

General Preparation.—It is prepared on a large scale from a kin clay-slate called alum-schist. This contains a quantity of ferric sulp It is first roasted and moistened and exposed to air. The sulphur is converted into sulphuric acid, and ferrous sulphate and aluminium sulp are formed. These are separated by lixiviation with water, and ammo chloride is added. This forms ammonium sulphate, which combines aluminium sulphate to form alum, ferrous chloride remaining in solutio

General Reactions of Alum Salts.—Salts of aluminium give a v gelatinous precipitate of hydrate with caustic potash or soda, solub excess; with ammonia a similar precipitate, insoluble in excess. Th solubility of the precipitate with ammonia in excess of the reagent re distinguishes aluminium from zinc, which also gives a white precipitate ammonium sulphide. Carbonates of potassium, sodium, and ammo also precipitate the hydrate, which is insoluble in excess; ammonium phide also gives a white precipitate of hydrate.

General Impurities of Aluminium Salts.—The chief is sulphat iron coming from the schist.

General Tests.—Alum should give no blue with either ferro- or f cyanide of potassium.

Alumen, B. and U.S.P. Alum.—A sulphate of alumin and potassium (potassium alum or potash alum), or of minium and ammonium (ammonium alum or ammonia alu crystallised from solution in water, B.P.; a sulphate of minium and potassium, U.S.P. $K_2Al_2(SO_4)_4.24H_2O$; 948.

Characters.—B.P. In colourless transparent crystal masses, exhibiting the faces of the regular octahedron, having an acid sweetish astringent taste.

Reactions.—Its aqueous solution gives with caustic potash or so white precipitate soluble in an excess of the reagent (aluminium); an immediate precipitate with chloride of barium (sulphate).

U.S.P. Large colourless octahedral crystals, acquirin whitish coating on exposure to air; no smell, sweet astring taste, and acid reaction.

Impurity.—Iron.

Test.—The solution in water does not acquire a blue colour from addition of yellow or red prussiate of potash.

Dose.—10 to 20 grains.

PREPARATIONS.

B.P.	U.S.P.
Alumen exsiccatum.	Alumen exsiccatum.
Glycerinum Aluminis (1 in 5).	

Alumen Exsiccatum, B. and U.S.P. DRIED ALUM.
$O_4Al_2(SO_4)_3$; 516.

PROPERTIES.—Dry white powder with the taste and other perties of alum.

PREPARATION.—By heating potassium alum until the water of crystallisa- is driven off.

DOSE.—As an astringent, 10 to 40 grs.; as an emetic, 30 to grs. For a lotion or gargle, 4 to 20 grs. to an ounce of water, n the glycerinum aluminis, B.P.

ACTION.—Alum precipitates **albumen** and **gelatin**. It has action on the unbroken **skin**, but when applied to parts n which the epidermis has been removed, it causes a film of gulated albumen to form on the surface, and produces con- tion of the tissues and vessels below. It thus lessens the ply of blood to the part, relieves congestion, diminishes swelling, lessens the discharge from inflamed surfaces, and refore acts as an **astringent**. By causing contraction of els and aiding the formation of coagula, it arrests hæmor- ge, and is therefore used either as a strong solution, or, if prove insufficient, in the form of powder mixed with starch **styptic**. Dried alum abstracts water from the tissues and as a slight **caustic**. When swallowed in large quantities n produces gastro-enteritis. In smaller doses it acts as an etic. It is not so powerful as a caustic, astringent, styptic, metic as the salts of zinc or copper.

USES.—Dried alum is sometimes used to check exuberant nulation in ulcers. Bleeding from the nose may be stopped niffing up or injecting a solution of alum into the nostrils, if the solution be ineffectual, powdered alum may be blown by means of a paper funnel; it is also employed locally in ding from the mouth, throat, gums, hæmorrhoids, and the us. As an astringent, alum is used in both purulent and ple ophthalmia, but on account of its solvent action on cornea it may lead to perforation, and should therefore voided (p. 216). A 1 per cent. solution, with 1 per cent. x, is useful in acute eczema. It is used as a lotion in rhœa; as a wash to the mouth in ptyalism, aphthæ, and ration of the mouth and gums; as a gargle for sore-throat, gestion of the pharynx, and elongation of the uvula, as well or the tickling, violent coughs which depend upon them, and often accompanied by retching (p. 248). Dried alum has applied in powder to remove the false membrane from the at in croup and diphtheria.

Alum may be employed as a spray to the larynx in cou and hoarseness depending upon chronic laryngeal catarrh. a wash it may be used in inflammation of the vulva in childr to relieve itching in pruritis vulvæ, and to prevent the rec rence of prolapsus ani. It is useful as an injection in gonorrh and leucorrhœa.

When swallowed it will act on the stomach as an astringe and is useful in **preventing** the **vomiting** of phthisis. It is p improbable that the vomiting which occurs usually after paroxys of coughing is due to the congestion produced in the stomach the cough, and that the alum prevents the vomiting by lessen this congestion (p. 377). When given in larger quantities al is an **emetic**, acting promptly, and producing little depressi A teaspoonful of powdered alum proves a very useful emetic cases of croup, and may be given to children mixed with hon In the intestines alum acts as an **astringent** also, and is use in diarrhœa; but, curiously enough, in lead colic it will act a purgative, relieving the pain and opening the bowels. Its util in lead-poisoning probably depends, to a considerable extent, its being a sulphate, and thus precipitating any lead salts it m meet in the intestine in the form of insoluble lead sulphate, a preventing absorption from the intestinal canal. In typh fever, and in chronic dysentery and diarrhœa, it is said to useful in checking the discharges from the bowels.

After its absorption into the blood it is supposed to exerc an astringent action, and is given to check sweating.

Internally, as a styptic, it is employed to check bleedi from the stomach, intestines, lungs, uterus, or kidneys.

ANTIDOTE.—Give tepid water with small doses of carbon of sodium to decompose the alum, and empty the stomach the stomach-pump or emetics.

U.S.P. Aluminii Hydras. HYDRATE OF ALUMINI $Al_2(HO)_6$; 156.

CHARACTERS.—A white, light, amorphous powder, permane in dry air, odourless, and tasteless.

SOLUBILITY.—It is insoluble in water or alcohol.

REACTIONS.—Soluble without residue in hydrochloric or in sulphuric ac also in solution of potassa or of soda.

USES.—It is feebly astringent and desiccant. Is used ternally as a powder in inflammatory diseases of the skin.

U.S.P. Aluminii Sulphas. SULPHATE OF ALUMINI $Al_2(SO_4)_3.18H_2O$; 666.

CHARACTERS.—A white, crystalline powder, permanent in t air, odourless, has a sweet, and afterwards an astringent tas and an acid reaction.

OLUBILITY.—Soluble, without leaving more than a trifling residue, in 1·2 of water at 15° C. (59° F.), and very soluble in boiling water; almost uble in alcohol.

EACTIONS.—The aqueous solution of the salt yields the reactions of inium (p. 654) and of a sulphate (p. 595).

USES.—It is a powerful **antiseptic**. A saturated solution been used as a mild caustic in enlarged tonsils, nasal polypi, i, scrofulous and cancerous ulcers, diseases of the os uteri, various chronic enlargements. Weaker solutions are used otions to ulcers, and as injections in gonorrhœa, leucorrhœa, fœtid discharges from the vagina.

A solution of the sulphate dissolves recently precipitated tinous alumina, and thus a benzoated solution of alumina be prepared by saturating with gelatinous alumina 8 oz. of sulphate in 1 pint of water, adding 6 drms. of powdered oin, keeping it at a temperature of 150° F. for six hours, putting in a cool place for several days to allow the deposi- of crystals. This solution is remarkable for its sweet odour astringent balsamic taste.[1]

CERIUM. Ce; 92.

t is a rare metal.

ts salts are supposed to resemble those of bismuth and silver eir action.

Cerii Oxalas. OXALATE OF CERIUM, B. and U.S.P. $_2O_4.3H_2O$, B.P.; $Ce(C_2O_4)_3.9H_2O$, U.S.P.

HARACTERS.—It is a white granular powder, insoluble in r.

REPARATION.—Is prepared by precipitating a soluble salt of cerium with te of ammonium.

EACTIONS.—At a red heat it is decomposed into a reddish-brown powder, dissolves completely in boiling hydrochloric acid without effervescence). The resulting solution gives a white crystalline precipitate of double ate of potassium and cerium when a saturated solution of sulphate of ium is added to it.

IPURITIES.—Aluminium, carbonates, and metals.

ST.—When the salt is boiled with caustic potash and filtered, the filtrate t affected by chloride of ammonium, showing that no aluminium is nt: but when supersaturated with acetic acid it gives with calcium de a white precipitate of oxalate of calcium. The absence of car- es and metals is ascertained by the usual tests.

OSE.—1 to 10 grains. Large doses may succeed when l ones fail.

SES.—It was introduced by the late Sir James Simpson as nedy to check the vomiting of pregnancy, and for this pur- is sometimes useful. It has also been employed in cases ronic bronchitis and dyspnœa, and has been used also in ous cough and nervous palpitation. It has been given, but doubtful utility, in chorea and epilepsy.

[1] *United States Dispensatory*, 15th ed. p. 167.

Class II.

Group II.—Magnesium.

MAGNESIUM. Mg; 24.

Sources.—The chief source is dolomite, or mountain li stone, which consists of carbonates of magnesium and calci Magnesium is also found native as carbonate and silicate.

General Reactions of Magnesium Salts.—They giv gelatinous white precipitate with potash, soda, or ammo insoluble in excess, but soluble in a solution of ammon chloride. They likewise give a white precipitate with potass and sodium carbonates, but none with ammonium carbonate

The characteristic test of magnesium is the formation precipitate of triple phosphate on the addition of ammonia a soluble phosphate to a solution of a magnesium salt. Cau ammonia itself throws down a precipitate of magnesium hyd insoluble in excess, but soluble in ammonium chloride. As easier to prevent the precipitation of hydrate than to re-diss it when down, it is usual to add ammonium chloride first, t the ammonia, and lastly the phosphate of sodium.

General Preparation of Salts of Magnesium.

Is prepared	From	By
Magnesium sulphate, B. and U.S.P.	Dolomite . .	Dissolving in sulphuric ac when soluble magnesium phate and insoluble calci sulphate are formed.
Magnesium carbonate (heavy), B.P.	Magnesium sulphate	Precipitating with sodium bonate, using hot concentra solutions.
Ditto (light), B. and U.S.P.	Ditto . . .	Ditto, using dilute solutions the cold.
Magnesia (heavy), B. and U.S.P.	Magnesium carbonate (heavy) . .	Calcining until all the carb acid is driven off, as shown some taken from the centr the crucible no longer ef vescing on the addition of a
Ditto (light), B. and U.S.P.	Ditto (light). .	Calcining like the heavy m nesia.
Granulated citrate of magnesium, U.S.P.	Ditto . . .	Mixing with citric acid and wa drying and powdering. powder is mixed with su sodium bicarbonate, and ci acid, damped with alco passed through a sieve, s to form a coarse powder, dried.
Magnesium sulphite, U.S.P.	Magnesia. . .	Suspending in water and ad excess of sulphurous acid.

ENERAL IMPURITIES.—The chief impurities in the sulphate are the cal- and iron from dolomite. Other alkaline earths and alkalis may also be nt. The sulphuric acid employed may be impure, or the sulphate may been prepared by a process in which hydrochloric acid is used, and thus des may occur. In the carbonate prepared from the sulphate the same ities may occur, as well as unchanged sulphate. In magnesia these ll occur, and carbonate as well.

STS.—The absence of iron and other metals is ascertained by the s solution giving no colour or precipitate with ferrocyanide of potas- hydrogen sulphide, or ammonium sulphide. Chloride of ammonium ts the precipitation of magnesium by ammonia and ammonium carbon- t it does not prevent the precipitation of other alkaline earths, and bsence is ascertained by the solution remaining clear after the addition e three reagents.

ENERAL ACTION OF MAGNESIUM.—When administered by the h the difference between absorption and excretion (p. 39) is reat enough to allow magnesium salts to accumulate in the sufficiently to produce any toxic effects. When injected he blood, sulphate of magnesium, in doses of about 5 grs. ound of body weight, abolishes reflex action, and paralyses espiration and heart in cats (Hay), and has a similar effect ner animals also.

agnesii Sulphas, B. and U.S.P. SULPHATE OF MAGNE- EPSOM SALTS. $MgSO_4.7H_2O$; 246.

ROPERTIES.—In minute, colourless, transparent, acicular ls, whose form is a rhombic prism. They look exactly like ate of zinc. Its taste is bitter, and it is called in Germany *salz*. This distinguishes it from zinc sulphate, which has a g metallic taste.

LUBILITY.—It readily dissolves in water.

ACTIONS.—The solution gives the reactions of magnesium (p. 658) and ate (p. 595).

URITIES.—Calcium and iron.

TS.—Its aqueous solution is not precipitated at ordinary temperatures late of ammonium (no calcium), nor does it give a brown precipitate lorinated lime or soda (no iron).

SE.—As a purgative, half an ounce to an ounce and a half single dose. In repeated doses, especially if taken fasting, 120 grains. As a diuretic, 20 to 60 grs.

OFFICINAL PREPARATIONS.

B.P.	U.S.P.
ema Magnesii Sulphatis.	Infusum Sennæ Compositum.
stura Sennæ Composita.	

Enema Magnesii Sulphatis. ENEMA OF SULPHATE OF MAGNESIUM Catharticum).—Sulphate of magnesium 1, olive oil 1, starch mucilage 15.

TION.—Sulphate of magnesium to saturation precipitates ins.

moderate doses it causes a copious secretion from the nal mucous membrane, and acts as a **purgative**. It does mulate the muscular coat of the bowels much; it thus

causes little griping. As it does not accelerate peristaltic acti a part of the fluid poured out into the intestine may be reabsor as it passes slowly along. It is therefore usual when we wish produce free purgation to combine the salt with some purgat which will stimulate the muscular coat of the bowel, such senna or cascara sagrada. When given alone it is apt to prod much flatulent distension of the abdomen and rumbling, an carminative is therefore often given along with it. Its objecti able bitter taste may be covered by dissolving it in acid infus of roses and adding spirit of chloroform. It may be emplo as a purgative enema. When absorbed into the blood it act a **diuretic** if the skin be kept cool, and as a **diaphoretic** if skin be kept warm or moderate exercise be taken. It is absor more readily when given in small quantities, but a little is a taken up when purgative doses are employed, and it is theref a useful purgative in febrile states.

Uses.—Sulphate of magnesium is one of the most comm and useful saline purgatives. For its mode of action and u *vide* pp. 391–394. On account of its great solubility it may used in very concentrated solution to remove dropsy (p. 3 when less soluble salts cannot. Repeated small doses are v serviceable in biliousness.

U.S.P. Magnesii Carbonas. Carbonate of Magnesi $(MgCO_3)_4Mg(HO)_2.4H_2O$; 484. This corresponds to the kinds mentioned in the B.P.

B.P. Magnesii Carbonas. Carbonate of Magnesi $(MgCO_3)_3Mg(HO)_2.4H_2O$.

B.P. Magnesii Carbonas Levis. Light Carbonate Magnesium. $(MgCO_3)_3Mg(HO)_2.4H_2O$.

Both the light and heavy carbonates of magnesium have same chemical composition, and differ only in their weight.

Properties.—A white granular powder almost tasteless.

Preparation.—Both are prepared by precipitating a solution of sulp of magnesium by a solution of carbonate of sodium; removing the resul sulphate of sodium, washing the carbonate, and drying it at a tempera not exceeding that of boiling water so as not to decompose it.

In preparing the heavy carbonate, concentrated boiling solutions are u the mixture evaporated to dryness, and the sulphate of sodium remove subsequent digestion with water. In preparing the light carbonate, di solutions are employed: they are mixed cold; boiled for fifteen minu and the sulphate of sodium separated by filtration.

Reactions.—It is recognised as a carbonate by dissolving with effer cence in hydrochloric acid, and the magnesium is detected by the ap priate tests in the resulting solution (p. 658). The two carbonates are di guished by their weight.

Action.—When swallowed, carbonate of magnesium will h a less stimulating effect upon the mucous membrane than pot or soda, as it is nearly insoluble; but on this very account i

e preferred to them for neutralising acid in the stomach after ls, inasmuch as it will only neutralise the excess of acid with- rendering the fluids alkaline. In the intestine it acts as a tive, and is partly excreted in the fæces and partly converted magnesium salts which are absorbed and pass out in the e.

USES.—As an **antacid** and **laxative**, especially in children; eartburn, in dyspepsia, and vomiting during pregnancy; and ases where it is desirable to render the urine alkaline, as in y persons, where potash and soda disagree.

DOSE.—As an antacid, 5 to 20 grains; as a laxative, 10 to 60 ns. It may be conveniently given in milk.

OFFICINAL PREPARATIONS.

B.P.	DOSE.
quor Magnesii Carbonatis, as antacid, 1–4 fl. dr.; as laxative, 1–2 fl. oz.	
„ „ **Citratis,** as laxative,.....5–10 fl. oz.	

U.S.P.

istura Magnesii et Asafœtidæ.....½ fl. oz.

.P. Liquor Magnesii Carbonatis. SOLUTION OF CARBONATE OF MAG- M.—It is a solution of carbonate of magnesium in water containing carbonic It contains about 13½ grains in the fluid ounce. It is a pleasant laxative hildren; and laxative and antacid for women, especially useful during ancy.

.P. and U.S.P. Liquor Magnesii Citratis. SOLUTION OF CITRATE OF ESIUM.—Dissolve citric acid, 200 grains, in 2 ounces of water, add carbonate agnesium 100 grains, and stir until it is dissolved. Filter the solution into a half-pint bottle, add syrup of lemons ½ fl. oz. and enough water nearly to ll the bottle; then introduce bicarbonate of potassium in crystals 40 grains, mmediately close the bottle with a cork, which should be secured with string re. Afterwards shake the bottle until the bicarbonate of potassium has lved.

S.P. Mistura Magnesii et Asafœtidæ (Dewees' Carminative).—Carbonate agnesium 5, tincture of asafœtida 7, tincture of opium 1, sugar 10, distilled up to 100. DOSE.—½ fl. oz. in hysterical flatulence.

Magnesia Levis, B.P.; Magnesia, U.S.P. MAGNESIA. IT MAGNESIA, MgO; 40.

PREPARATION.

U.S.P.

Trochisci Magnesiæ (3 grs. in each).

Magnesia Ponderosa, B. and U.S.P. HEAVY MAGNESIA.

CHARACTERS.—Both are white powders differing from each r only in their weight, which is 3½ to 1.

OLUBILITY.—They are insoluble in water, but dissolve in acids without escence.

EACTIONS.—The solution in acids exhibits the reactions of magnesium.

DOSE.—10 to 60 grains of either heavy or light.

ACTION AND USES.—Like those of the carbonate.

OFFICINAL PREPARATION.

Pulvis Rhei Compositus, 2 parts of heavy magnesia in 3.

CHAPTER XXVI.

METALS—(*continued*).

Class II.—DYAD METALS—(*continued*).

General Actions of Heavy Metals.—The heavy metals fo compounds with albumen, known as **albuminates.** These sparingly soluble, and in consequence of this, white of egg i useful antidote in poisoning with heavy metals. Albuminate copper have been obtained by Harnack in which the proportio copper is definite, and is either 1·35 or 2·64 per cent. On acco of their affinity for albumen the heavy metals combine with albuminous constituents of the **tissues,** and act as powe **astringents** (p. 349), **irritants** (pp. 341 and 395), or **caust** (pp. 344 and 346), according to the strength of the applicati Their action is comparatively slight when they are applied to unbroken skin, as the epidermis forms an obstacle to their acti but it is strongly marked where the epidermis is absent, as wounds or ulcers, and on mucous surfaces where the epitheli is soft. In addition to their astringent action on the fluids tissues, two metals—lead and silver—cause contraction of **blood-vessels** (p. 349). In considering the action of the he metals belonging to this group and those belonging to Clas III.–VIII., on the organism, it is necessary to distinguish ca fully between—

(1) The **local action** upon the surface of the body or u the alimentary canal, with the **reflex effects** upon the nervo respiratory and circulatory systems consequent on this l action, and—

(2) The effects produced on the various organs of the body the metal **after its absorption.** Thus, a large dose of corro sublimate when swallowed may produce the ordinary sympt of irritant poisoning, causing vomiting and purging by its l action on the stomach and intestine, and producing reflexly gen collapse with feeble circulation and respiration. Yet if the tr ment be prompt, none of the metal may be absorbed, and thus symptoms which would be produced by its action on the vari organs when carried to them by the circulation may be absen

In considering the effects produced by a metal after its abs tion, we must remember that the nature of its **action diff**

ording to the **quantity** present in the blood at any one time, l that this quantity depends on the relation between the rapidity **absorption** and **excretion** (p. 39).

The proportion between absorption and excretion depends atly on the **channel of introduction**, and therefore the same g may produce quite different effects according to the mode its administration. Thus solution of perchloride of iron, when ected directly into the veins, will cause almost immediate th from coagulation of the blood. Other salts of iron which ve no coagulating action, if injected into the **circulation**, pro- e paralysis of the central nervous system and of the vaso- tor nerves, causing loss of voluntary motion, an enormous fall the blood-pressure, and death. When injected **subcutaneously** n is absorbed, but it enters the blood less rapidly than when ected into the veins, the quantity present in the blood at any e time is less, and these symptoms are not produced. Never- eless absorption takes place from the subcutaneous tissue so idly that enough iron enters the blood to produce a toxic action. t this action, instead of affecting the nerves, is chiefly exerted the excreting system, and inflammation of the kidneys occurs. hen taken into the **intestinal canal** iron is absorbed very wly, and only a very small quantity appears in the urine. It hard to say whether the slight headache which is apt to come from the administration of iron is due to the direct action of e metal on the nerve-centres after its absorption, or is merely flex and due to the action of the metal on the intestine. No jury is done to the kidneys of healthy persons, though the effect the iron upon these organs may be manifested by the diminu- on of albumen in cases of renal disease.

The **form** in which metals are **absorbed** from the intestinal nal is probably that of albuminates, or, perhaps, more properly, peptonates.

The only heavy metals which are rapidly absorbed from the ealthy intestinal canal are lead, mercury, and arsenic. Copper, nc, silver, tin, iron, manganese, nickel, and cobalt are absorbed ry slowly indeed. This is shown by the fact that when given ternally only mere traces of them appear in the urine. That eir absence from this secretion is due to non-absorption, and ot to their retention in the blood or tissues, is proved by the ct that when they are injected subcutaneously they pass readily rough the kidneys.

Contrary to one's expectation, it has been found that metals re much more readily absorbed by the gastro-intestinal mucous embrane when it is in a catarrhal condition than when it is in healthy state. When large doses of metallic salts are given at nce they are very apt to produce acute catarrh of the intestinal anal, and they are then readily absorbed, and appear in large uantity in the urine. If small doses are given at first, instead

of large ones, they may be gradually increased without produc any catarrh, and then absorption into the blood and excretion the urine does not occur, or only to a slight extent, although dose finally reached may be large.

The therapeutic bearing of this fact is that if we wish to af the kidneys by metallic remedies, e.g. by iron in cases of al minuria, the best method of administering the remedy is to be with large doses at once.

After absorption into the **blood** the metals probably rem to a great extent, if not entirely, in the plasma, and do become combined with the corpuscles, or only to a very sli extent.[1]

They are carried to all parts of the body, and probably u with certain **tissues.** They remain in combination with tissues for a greater or less length of time, modifying their nu tion and functional activity, and then, being again set free, t become excreted.

The heavy metals have all a powerful poisonous action **muscles, nerves, nerve-centres, and glands.** The slight of the action which they exert on these structures when adm istered by the alimentary canal is due to their slow and spa absorption by it. But their poisonous power at once beco evident, as in the case of iron, when they are injected either cutaneously or directly into the circulation in the form of do salts or organic compounds, which produce no local irritatio the point of injection, nor coagulation of the blood when are introduced directly into the vessels. The alterations in spinal cord in acute poisoning by some of them—e.g. lead mercury, and also by arsenic—have the characters of acute cer myelitis, the grey substance being chiefly affected. In chronic poisoning the white substance is affected as well, so the alterations resemble those of diffuse myelitis. The ner symptoms produced by heavy metals are probably due to alterations in the nerve-centres, and sometimes to periph alterations in the nerves also.

Metals are **excreted** chiefly by the bile (p. 405), by the kidn by the mucous membranes of the stomach and intestine; probably to a slight extent by the skin. Elimination by t channels may commence very soon after the metal has ent the blood.

During the process of elimination the metals may irritate eliminating organs (Fig. 5, p. 39), and may cause vomiting by t action on the stomach (p. 372), diarrhœa by their action on intestine, and albuminuria by their action on the kidneys, altho

[1] This is best shown by separating the corpuscles and plasma in a centri machine and analysing them separately, so as to ascertain the amount of in each.

ey have been injected into the veins, or subcutaneously, and ly reach these organs through the blood.

On account of the quantity of metal which is eliminated by e bile and intestinal mucous membrane, purgatives are useful ents in the treatment of chronic metallic poisoning (cf. pp. 4 and 561).

When metals have entered the blood in considerable quantities, e **kidneys** become inflamed during the process of their excre- n, and undergo changes which affect both the tubules and the omeruli. The tubules are affected first, and the epithelial cells, th of the convoluted and straight tubules, take up the metal d become gradually disintegrated. They are partly thrown t as casts, and partly block up the tubules, causing secondary generation of the glomeruli. Both tubules and glomeruli be- me atrophied. These effects appear to be produced by all the avy metals.

The possible effect of mercury on the kidneys should be rne in mind when prescribing a very prolonged mercurial urse, and it would be interesting to inquire how far albumi- uria in apparently healthy persons is caused by mercurials (cf. 20).

Group III.—Zinc, Copper, *Cadmium*, and Silver.

General Actions.—They combine with **albumen** and form soluble albuminates, and have thus an astringent action.

With the exception of salts of silver, which form a compound ith the epidermis, they have no action on the epidermis, but ey may pass through the pores, especially chloride of zinc. his salt produces inflammation, or even mortification, acting y its affinity both for water and for albumen. It is used as a austic for destroying the surface of unhealthy sores and produc- g a more healthy action. The other preparations of the metals this group act in the same way, but are less powerful, and are pplied to ulcers and to chronic skin-diseases.

They are applied for their astringent action to the **eye** in onorrhœal ophthalmia, ulcerations or opacity of the cornea, and o the **mucous membranes** of the urethra and vagina in gonor- hœa and leucorrhœa.

Insoluble preparations such as oxide of zinc have little action n the skin, but are applied as powder or ointment to raw and xcoriated surfaces, where protection from external influences ith very slight stimulation is wished, as in intertrigo.

In the **mouth** they combine with the albumen of the tongue nd cheeks, and produce a very disagreeable metallic taste. Notwithstanding this they are employed, especially sulphate of opper, for ulcers of the mouth or fauces.

Zinc chloride has been recommended for carious teeth.

In the **stomach** they unite with the albumen in its wall producing irritation and consequent nausea, accompanied muscular relaxation. They have been used as nauseants spasmodic affections, as epilepsy, chorea, hysteria, &c.

In a somewhat larger dose they produce vomiting, which speedy and complete, especially in the case of zinc and copp which are consequently much used in cases of poisoning whe we wish the stomach emptied with all possible speed. They a preferred in such cases to tartar emetic, as they do not produ so much depression, nor are they so liable to cause diarrhœa; a to ipecacuanha, because their action is more rapid and certain

The compounds of zinc or copper with albumen or pepton will produce vomiting, either when given by the mouth or wh injected into the veins, but they are classed as **local emeti** (p. 373).

Their emetic action when injected into the veins may be d to a direct action on the vomiting centre in the medulla (p. 37 but it may also be that they are carried to the stomach by t blood and act reflexly from it (*vide* Fig. 5, p. 39, and cf. p. 37

The albuminates of copper and zinc, and probably those the other metals, undergo changes both in the stomach and i testine before absorption which we do not perfectly understan Albumen is not simply dissolved and absorbed in the intestin canal, but is converted into peptone. Albuminate of copper h been introduced into a gastric fistula in a dog, and the bl colour was seen to disappear at the edges, and finally all copp was removed from it before the albumen was itself complet digested. Whether or not the copper was removed in combin tion as a peptone or not we cannot as yet say. Copper sa unite with peptone, forming an easily soluble compound.

In the **intestine** small doses lessen the frequency of t stools, and have been thus used in chronic diarrhœa and dyse tery, but larger doses have an irritant effect and cause diarrho The insoluble salts, as oxide and carbonate of zinc, have much weaker action than the soluble ones, and thus a lar quantity of them has the same action as a small one of t soluble salts.

Chronic poisoning by copper is said to have occurred consequence of the use of copper salts to give a bright gre colour to tinned peas or other vegetables, as well as from the e ployment of imperfectly cleansed copper pans. Some doubt l been thrown on the possibility of producing chronic poisoning the internal administration of copper in small doses, as in so experiments it was given to animals for a length of time with injury. More recent experiments show, however, that at le in ruminants chronic poisoning may be produced. The syn toms are loss of appetite, imperfect rumination, periodi constipation, imperfect nutrition, muscular weakness, langu

ndice, albuminuria, and towards the end hæmoglobinuria or maturia. On *post-mortem* examination granular degeneration the muscles and heart, enlarged spleen, fatty degeneration the liver, dark brown colour of the blood, and granular posits of methæmoglobin in the renal tubules, along with morrhagic parenchymatous nephritis, are found.

Chronic poisoning by copper may occur among coppersmiths, in families where copper pans have been used. The symptoms are a metallic taste, a feverish state, with symptoms of bacute gastro-enteritis, not unfrequently jaundice, trembling of nbs, and cramps. A purple line is said to form on the gums.

ZINC. Zn; 64·9.

Sources of Zinc.—The chief are native carbonate or calamine ($ZnCO_3$) and zinc blende (ZnS).

General Reactions of Zinc Salts.—The most characteristic test is that it forms a white sulphide, which is precipitated the addition of ammonium sulphide to a solution, and which insoluble in caustic alkalies. Caustic potash, soda, or ammonia give a white precipitate of hydrate, soluble in excess; ammonium carbonate gives a similar precipitate, soluble in excess; t sodium and potassium carbonate give a white precipitate, soluble in excess.

General Preparation of Zinc Salts.

Prepared	From	By
inc, B. and U.S.P. .	Zinc blende or calamine	Roasting, to drive off sulphur or carbonic acid, and then distilling the oxide with charcoal.
ranulated zinc, B.P.	Zinc	Melting and throwing into water.
inc chloride, B. and U.S.P.	Zinc	Dissolving in hydrochloric acid ($Zn_2 + 4HCl = 2ZnCl_2 + 2H_2$): it is then purified from lead or iron by passing chlorine through it, and adding carbonate of zinc, $2FeCl_2$ (Ferrous chloride) + Cl_2 (Chlorine) = Fe_2Cl_6 (Ferric chloride). Fe_2Cl_6 (Ferric chloride) + $3ZnCO_3$ (Carbonate of zinc) + O = $Fe_2(HO)_6$ (Ferric hydrate) + $3ZnCl_2$ (Chloride of zinc) + $3CO_2$ (Carbonic acid gas). $PbCl_2$ (Chloride of lead) + Cl_2 (Chlorine) + $2ZnCO_3$ (Carbonate of zinc.) = PbO_2 (Peroxide of lead) + $2ZnCl_2$ (Chloride of zinc) + $2CO_2$ (Carbonic acid gas).
inc sulphate, B. and U.S.P.	Zinc	Dissolving in sulphuric acid, and purifying in the same way as chloride.
inc carbonate, B. and U.S.P.	Zinc sulphate . .	Precipitating with carbonate of sodium.

GENERAL PREPARATION OF ZINC SALTS—*continued.*

Prepared	From	By
Zinc acetate, B. and U.S.P.	Zinc carbonate . .	Dissolving in acetic acid.
Zinc oxide, B. and U.S.P.	Ditto . .	Calcining.
Zinc oleate, B.P. .	Zinc oxide . .	By dissolving in oleic acid.
Zinc valerianate, B. and U.S.P.	Zinc sulphate . .	Mixing with sodium valerianat
Zinc bromide, U.S.P.	Ditto . .	Mixing with hot solution of pot sium bromide, precipitati potassium sulphate by alcoh filtering and evaporating. Or acting on zinc with bromine.
Zinc iodide, U.S.P. .	Zinc	Digesting with iodine in wa and evaporating.
Zinc phosphide. U.S.P.	—	Passing phosphorus vapour in c hydrogen over melted zinc.
Zinc sulphocarbolate, B.P.	Zinc oxide . .	Heating a mixture of carbolic a and sulphuric acid, saturati the product with zinc oxi evaporating and crystallising.

GENERAL IMPURITIES OF ZINC SALTS.—Iron, lead, copper, and arseni

GENERAL TESTS.—A solution of zinc salt acidulated with hydrochl acid gives no precipitate with sulphuretted hydrogen (absence of lead, cop or arsenic). The absence of copper is further ascertained by ammonia gi with a solution of zinc salts a white precipitate, soluble in excess with colour. If copper be present the solution would be blue. Solutions sh give no blue with ferro- or ferri-cyanide of potassium, nor any black co with tincture of galls (absence of iron).

GENERAL ACTION OF SALTS OF ZINC.—They combine w albumen and coagulate it. The chloride of zinc thus acts as **escharotic** after the epidermis has been previously removed caustic potash. Neither it, nor the sulphate, nor acetate of z has any action on the unbroken skin, but when applied mucous membranes, they will act as **irritants** in large, and **astringents** in small doses.

Sulphate and acetate of zinc are prompt **emetics**, caus rapid evacuation of the contents of the stomach with little nau or depression.

The mode of action of zinc salts as emetics has not b perfectly determined. It is probably partly due to the lo effect upon the stomach, and partly to the stimulant action u the vomiting centre in the medulla oblongata after absorpt into the circulation.

Vomiting is produced by the injection of zinc salts into circulation, but this may be partly due to irritation of the stom by the zinc salts during the process of excretion by its muc membrane, as well as to the action upon the medulla.

In small doses zinc salts act also as **nervine tonics**, lessen sweating.

Zincum. B. and U.S.P. Zinc. 64·9. Zinc of commerce, P. Metallic zinc in the form of thin sheets or irregular granuled pieces, U.S.P.

Characters.—A bluish-white metal having the sp. gr. 6·9.

Reactions.—When treated with warm diluted sulphuric acid it is almost completely dissolved, forming a colourless liquid which yields a white precipitate with test solution of ferro-cyanide of potassium, or of sulphide of ammonium. U.S.P.

Preparations containing Zinc.

B.P.	U.S.P.
Liquor Zinci Chloridi.	Liquor Zinci Chloridi.
Oleatum Zinci.	Unguentum Zinci Oxidi.
Unguentum Zinci.	Zinci Acetas.
,, ,, Oleati.	,, Bromidum.
Zinci Acetas.	,, Carbonas Præcipitatus.
,, Carbonas.	,, Chloridum.
,, Chloridum.	,, Iodidum.
,, Oxidum.	,, Oxidum.
,, Sulphas.	,, Phosphidum.
,, Sulphocarbolas.	,, Sulphas.
,, Valerianas.	,, Valerianas.

Zincum Granulatum.

B.P. Zincum Granulatum. Granulated Zinc—(Zinc fused and poured into water).

Impurities.—Very frequently it contains sulphur or arsenic.

Tests.—Zinc is chiefly used for preparing hydrogen, and these impurities may be tested by adding pure dilute hydrochloric or sulphuric acid to it and holding over it a piece of paper dipped in acetate of lead. If sulphur be present the paper is blackened. If the piece of paper be wetted with solution of nitrate of silver, a brown or black stain is produced if arsenic is present. On lighting the hydrogen and depressing a piece of porcelain on it, a black stain is produced if arsenic is present.

Zinci Oxidum, B. and U.S.P. Oxide of Zinc. ZnO. 80·9.

Characters.—A soft, nearly white, tasteless and inodorous powder, becoming pale-yellow when heated.

Impurities.—Undecomposed carbonate, chloride, sulphates, iron and copper.

Tests.—Dissolves without effervescence in diluted nitric acid, forming a solution, which is not affected by chloride of barium or nitrate of silver, and gives with carbonate of ammonium a white precipitate which dissolves entirely (no iron) without colour (no copper) in an excess of the reagent, forming a solution which is precipitated white by sulphide of ammonium.

Dose.—2 to 10 grains.

Officinal Preparations.

B.P.	U.S.P.
Unguentum Zinci.	Unguentum Oxidi Zinci.

B.P. Unguentum Zinci. Zinc Ointment.—Oxide of zinc 80 grs., benzoated lard 1 oz., or 1 in 6½ nearly.

U.S.P. Unguentum Oxidi Zinci. Ointment of Oxide of Zinc.—Oxide of zinc 20, benzoated lard 80, or 1 in 5.

Uses.—Oxide of zinc is sparingly soluble in the stomach. It dissolves to a slight extent, too little to act as an emetic, but sufficient to produce the action of small doses of soluble zinc salts as a nervine tonic and astringent.

It may be used as a dusting powder in intertrigo, and t zinc ointment is one of the most efficacious remedies we poss for application to excoriated surfaces. In acute eczema, zi ointment can sometimes be borne, when other forms of bla ointment only increase the inflammation, and in acute vesicul eczema, dabbing the part for about fifteen minutes with bla wash and then rubbing in zinc ointment gently is sometimes very successful treatment. It has been given in whooping-coug epilepsy, hysteria, nervous headache, and to check profu sweating in phthisis, and profuse secretion from the bronchi bronchitis. In the sweating of phthisis it is frequently co bined with hyoscyamus, and it is somewhat difficult to say h much of the beneficial action is due to the hyoscyamus.

B.P. Oleatum Zinci. Oleate of Zinc (p. 591).

B.P. Officinal Preparation.

Unguentum Zinci Oleati (oleate of zinc 2, benzoated lard 11).

Uses.—Ointment of oleate of zinc alone, or along with olea of morphine, is an excellent preparation in many cases of acu eczema and of intertrigo.

B.P. Calamina Præparata. Prepared Calamine.—Nati

carbonate of zinc calcined in a covered earthen crucible at moderate temperature, powdered and freed from gritty particl by elutriation.

Characters.—A pale pinkish-brown powder, without grit ness.

Solubility.—It is almost entirely soluble, with effervescence, in acids.

Officinal Preparation.

Unguentum Calaminæ (prepared calamine 1, benzoated lard 5).

Uses.—Used sometimes instead of oxide. In skin diseas preferred to the oxide by some, especially in weeping eczema; is still better applied in the form of a lotion, e.g. calamine grs., oxide of zinc 20 grs., glycerine 20 min., water to 1 oz., prepared calamine 12 grs., prepared chalk 24 grs., lime water 1 c

Zinci Carbonas, B.P.; Zinci Carbonas Præcipitatu U.S.P. Carbonate of Zinc. B.P. Precipitated Carbonate Zinc. $ZnCO_3(ZnO)_2.3H_2O$. B.P.; $(ZnCO_3)_2.3Zn(HO)_2$; 546 U.S.P.

Characters.—White, tasteless, inodorous.

Solubility.—It is insoluble in water; soluble, with effervescence a without residue, in dilute nitric acid.

Reactions.—The solution in nitric acid gives the reactions of zinc (p. 66

Dose.—1 to 10 grains.

Uses.—Like those of calamine.

Zinci Chloridum, B. and U.S.P. CHLORIDE OF ZINC, $ZnCl_2$; 135·7.

CHARACTERS.—Colourless opaque rods or tablets, very deliescent and caustic.

SOLUBILITY.—It is soluble almost entirely in water, alcohol, and ether.

REACTIONS.—The watery solution gives the reactions of zinc and of a oride (p. 594).

PREPARATION CONTAINING CHLORIDE OF ZINC.

Liquor Zinci Chloridi .....366 grains in one fluid ounce.

Liquor Zinci Chloridi, B. and U.S.P. SOLUTION OF CHLORIDE OF ZINC, $ZnCl_2$; 135·7, U.S.P. Prepared like the solid, but not so much evaporated.

USES.—It is a powerful **caustic** distinguished by its property burning **deeply** and not spreading sidewise like many others. is applied, in substance, or made into a paste with starch or psum, to cancers, sloughing or unhealthy sores, and nævi. luted it is applied to ulcers.

It has been used to destroy the exposed pulp in decayed eth, warty growths, condylomata, syphilitic sores, and lupus. the proportion of one to two grains in a pint of water it has en recommended by Ringer as an injection in gonorrhœa.

Burnett's (Sir W.) disinfectant and deodorising solution is lution of chloride of zinc (of sp. gr. 2), and it is by the accintal use of this, that most cases of zinc-poisoning occur.

Zinci Sulphas, B. and U.S.P. SULPHATE OF ZINC. $ZnSO_4.7H_2O$; 286·9.

CHARACTERS.—In colourless transparent prismatic crystals ith a strong metallic styptic taste.

REACTIONS.—Its solution in water gives the reactions of zinc and of a lphate (p. 595).

DOSE.—1 to 3 grains as a tonic; 10 to 30 grains as an metic.

USES.—Sulphate of zinc is used as an **astringent** to lessen scharges from mucous membranes; it is employed as a lotion gonorrhœa and leucorrhœa; as a wash to the eye in ophthalia; and, mixed with honey, in gangrene of the mouth in chilren. It is used as a gargle to the throat in relaxed sore-throat, endent uvula, and enlarged tonsils.

As an **emetic** it is chiefly employed in narcotic poisoning, here the rapidity of its action, unaccompanied by any depressng influence on the circulation, is very serviceable. It is sometmes used, also, to cause vomiting in croup. It is employed as n **astringent** in chronic diarrhœa and dysentery. It has also een used as a **tonic** in flatulence and flatulent distension of the olon. After absorption into the blood it has a tonic action on ome parts of the nervous system, and is used in the treatment f convulsive diseases, such as chorea, epilepsy, hysteria, as well

as in spasmodic affections of involuntary muscular fibre, such angina pectoris and spasmodic asthma.

Zinci Sulphocarbolas, B.P. SULPHOCARBOLATE OF ZI $Zn(C_6H_5SO_4)_2.H_2O$.

CHARACTERS.—Colourless, transparent, tabular, efflores crystals, with an astringent taste.

SOLUBILITY.—Soluble in about twice the weight of rectified spirit an water.

REACTIONS.—The watery solution is coloured violet by perchloride of i and gives a white precipitate with sulphydrate of ammonium; it is m faintly turbid by chloride of barium, and it is not precipitated by oxalat ammonium.

ACTION.—Sulphocarbolate of zinc is **antiseptic** and **astr gent.**

USES.—It is used as an injection in otorrhœa, gonorrhœa, a other cases of purulent discharges, in the strength of 2 to 4 gra to the ounce of water. It is not given internally.

Zinci Acetas, B. and U.S.P. ACETATE OF ZINC. $Zn(C_2H_3O_2)_2.2H_2O$; 218·9, B.P.; $Zn(C_2H_3O_2)_2.3H_2O$; 23 U.S.P.

CHARACTERS.—Thin, translucent and colourless crystall plates, of a pearly lustre, with a sharp unpleasant taste.

SOLUBILITY.—Soluble in water.

REACTIONS.—The solution gives the reactions of zinc, and evolves ac acid when decomposed by sulphuric acid.

DOSE.—1 to 2 grains as a tonic; 10 to 20 grains as emetic.

USES.—It is used for much the same purposes, and in same doses, as the sulphate. An unchemical but useful inject for gonorrhœa, gleet, and leucorrhœa, consists of six grains sulphate of zinc, with four ounces of the dilute solution of s acetate of lead. In this mixture the sulphate of lead which precipitated has probably a beneficial action in keeping ap the surfaces of the mucous canal into which it is injec (p. 446).

U.S.P. Zinci Bromidum. BROMIDE OF ZINC. ZnB 224·5.

CHARACTERS.—A white, or nearly white, granular pow very deliquescent, odourless, having a sharp saline metallic ta and a neutral reaction.

SOLUBILITY.—Very soluble in water and in alcohol.

REACTIONS.—The aqueous solution of the salt yields the reactions of and of a bromide (p. 594).

DOSE.—2 to 8 grains given in syrup.

USES.—In large doses it is irritant and emetic like ot salts of zinc. It has been recommended in epilepsy with idea of combining the actions of bromine and zinc.

U.S.P. Zinci Iodidum. IODIDE OF ZINC. ZnI_2; 318·1.

CHARACTERS.—A white, or nearly white, granular powder, y deliquescent, odourless, having a sharp saline and metallic te, and an acid reaction.

SOLUBILITY.—Very soluble in water and in alcohol.

REACTIONS.—The aqueous solution yields a white precipitate with test tion of ferrocyanide of potassium or of sulphide of ammonium, a yellow ipitate with test solution of acetate of lead, and a red one with test tion of mercuric chloride (iodide).

DOSE.—½ to 2 grains.

USES.—Locally it has been used in solution as an application nlarged tonsils. An ointment, 1 part to 8 of lard, has been d in place of the ointment of iodide of potassium or of cad- um to reduce swellings. A solution of 2 grains to 1 oz. has n used in gonorrhœa. Internally it has been used in scrofula, rea, and hysteria. It is best administered in the form of syrup.

Zinci Valerianas, B. and U.S.P. VALERIANATE OF ZINC. $(C_5H_9O_2)_2.H_2O$; 284·9.

CHARACTERS.—In brilliant, white, pearly, tabular crystals, h a feeble odour of valerianic acid, and a metallic taste.

SOLUBILITY.—It is scarcely soluble in cold water or in ether, but is soluble ot water and alcohol.

REACTIONS.—Heated to redness in an open crucible, it leaves a residue ch, when dissolved in diluted sulphuric acid, yields with ammonia a pre- tate which entirely dissolves in an excess of the reagent, and the result- solution gives a white precipitate with sulphide of ammonium (zinc).

PREPARATION.—Mixing hot aqueous solutions of sulphate of zinc and erianate of sodium, evaporating at a gentle heat and crystallising. The stals are washed with water until free from sulphate.

IMPURITIES.—Sulphate and butyrate of zinc from imperfect preparation.

TESTS.—Its solution in hot water is not precipitated by chloride of ium (no sulphate). It gives when heated with diluted sulphuric acid a illate, which when mixed with the solution of acetate of copper, does not mediately affect the transparency of the fluid, but forms after a little time drops, which gradually pass into a bluish-white crystalline deposit (no yrate).

DOSE.—½ to 4 gr.; the dose may be increased until some usea is produced.

USES.—Valerianate of zinc has been supposed to combine the rvine tonic action of zinc with the antispasmodic effect of lerian; but it is much better to use valerian itself or its oil ng with a salt of zinc, as the acid has no important physio- ical action. It is used in chorea, especially when occurring hysterical persons, and should not be discontinued until mptoms of nausea begin to make their appearance. It is also ployed in epilepsy and neuralgia.

U.S.P. Zinci Phosphidum. PHOSPHIDE OF ZINC. Zn_3P_2; 6·7.

CHARACTERS.—Minutely crystalline friable fragments, having metallic lustre on the fractured surfaces, or a greyish black

powder permanent in the air having a faint odour and tast phosphorus.

SOLUBILITY AND REACTIONS.—Insoluble in water or alcohol, but pletely soluble in hydrochloric or sulphuric acids with evolution of phos retted hydrogen.

DOSE.—Not more than $\frac{1}{20}$ grain at first.

USES.—Its action is similar to that of phosphorus, an is used in place of it. Each grain contains nearly $\frac{1}{4}$ grai phosphorus.

COPPER. Cu; 63·4.

SOURCES.—Its chief source is copper pyrites, which is a do sulphide of copper and iron.

GENERAL REACTIONS.—Ammonia throws down a pale precipitate of hydrate, which is soluble in excess, forming a blue solution. Potassium ferrocyanide gives a maroon precipitate.

	Prepared from	By
Copper, B.P. . .	Copper pyrites .	Roasting with sand and coal.
Copper sulphate, B. and U.S.P.	Copper . . .	Heating copper or its oxide v sulphuric acid, dissolving water and crystallising.
Copper nitrate, B.P.	Ditto . . .	Dissolving in nitric acid, eva rating and crystallising.
Copper acetate, B. and U.S.P.	Copper sulphate .	Precipitating with acetate of l

GENERAL IMPURITY.—Iron.

GENERAL TEST.—If an aqueous solution of a copper salt be mixed twice its volume of chlorine water, any iron present is converted into a salt. If solution of ammonia be now added, cupric hydrate will fall precipitate of a pale blue colour, but is redissolved by excess, forming a blue solution. If iron be present, it will be precipitated by the ammoni not redissolved.

Cuprum, Cu = 63·4. B.P. COPPER.—Fine copper wire, a No. 25 wire gauge, or 0·02 inch.

USE.—To detect the presence of metals, as silver, merc and arsenic, by their being precipitated on its surface and f ing a stain. It is employed in the preparation of sulphate nitrate of copper and of spirit of nitrous ether.

B.P. Cupri Nitras. NITRATE OF COPPER, $Cu(NO_3)_2.6H$

CHARACTERS.—Deep blue prismatic crystals, very deliques highly corrosive. With one-third of its weight of water it f at a temperature below 70° F. (21·1° C.), tabular crys $Cu(NO_3)_2.6H_2O$. With a very little more water, added direct absorbed from the air, it yields a styptic, caustic, corrosive l

REACTIONS.—The diluted aqueous solution is only faintly acid to lit it gives the reactions of copper and a nitrate (p. 594).

Cupri Sulphas,[1] **B. and U.S.P.** SULPHATE OF COPPER. $O_4.5H_2O$; 249·2.

CHARACTERS.—A blue crystalline salt, in oblique prisms.

REPARATION.—*Vide* p. 674.

OLUBILITY.—It is soluble in water, forming a pale blue solution which gly reddens litmus.

EACTIONS.—The aqueous solution gives the reactions of copper and a hate.

DOSE.—As an astringent, $\frac{1}{4}$ to 2 grains; as an emetic, 5 to grains.

.P. Sulphate of Copper, Anhydrous. $CuSO_4$. Sulphate of copper ved of its water by a heat of 400° F.

HARACTERS.—A yellowish-white powder, which becomes blue when moistened water.

ACTION.—Sulphate of copper has little or no action on the covered by epidermis, but when applied to the denuded it combines with the albuminous constituents of the tissues, ming an albuminate of copper. It thus acts as a mild **caustic**, is an **astringent**. It has a similar astringent action on ous membranes, and when swallowed in large doses it acts a powerful **emetic**, like the sulphate of zinc, and in smaller es as an astringent. Like sulphate of zinc, it probably exerts action partly on the stomach itself and partly on the vomit- centre. Small doses absorbed into the blood appear to have onic action on some parts of the nervous system, and to exert astringent action on mucous membranes. The copper is reted by the mucous membrane of the intestine, by the bile, at, and kidneys. It is probable that its effect as an emetic n injected into the blood is partially due to the action it duces upon the stomach or intestines in the process of elimi- ion (p. 39). Its action as an astringent upon other mucous mbranes is probably due to a similar cause.

USES.—Sulphate of copper in substance is used as a mild stic to the edges of sores, to repress exuberant granulations, h of ulcers and of trachoma, and as a styptic to arrest the od from leech-bites. When mixed with honey it may be ap- d to the mouth in cancrum oris. In solution it may be ap- d to indolent ulcers, and to remove warts and parasitic skin- eases, and as an injection into the nose to stop epistaxis. It used as a wash to the eyes in ophthalmia, as an injection in orrhœa and leucorrhœa, and as a gargle in sore-throat. It is efficient and rapid emetic in cases of narcotic poisoning, in sphorus-poisoning, and in croup. It is a powerful astringent

[1] Oleate of copper is a useful application in cases of ringworm, applied night morning. It is first prepared by drying a mixture of sulphate of copper (3 in water) and a solution of Castile soap (8 in 32), and may be applied in the of ointment, 1 in 4 of petroleum cerate. It has also been used for indolent rs, warts, and corns.

in chronic diarrhœa, dysentery, and colliquative diarrhœ phthisical patients. It is employed, like zinc, in chorea, epil and hysteria, but seems less useful than zinc. The nitrate a similar action to the sulphate, but is more powerful caustic and styptic. It is a useful application to syphilitic on the tongue.

B.P. Test Solution of Ammonio-Sulphate of Copp A test for arsenious acid, forming with it Scheele's gree

B.P. Subacetate of Copper of Commerce. Cu $(C_2H_3O_2)_2$. VERDIGRIS, AERUGO.—Used in solution as a test

B.P. Test Solution of Acetate of Copper.
USE.—In testing for butyric acid in valerianates.

U.S.P. Cupri Acetas. ACETATE OF COPPER. Cu(C $(CO{\cdot}OH)_2.H_2O$; 199·2.
CHARACTERS.—Deep green, prismatic crystals, yieldi bright green powder, efflorescent on exposure to air, odou having a nauseating metallic taste and an acid reaction.

TESTS.—If the aqueous solution of the salt be treated with hydrosul acid until all the copper is precipitated, the filtrate should leave no r on evaporation (alkalis, alkaline earths, or iron). If the aqueous so be heated to boiling with solution of soda in excess, it will yield a f which should not be clouded by hydrosulphuric acid (absence of lea zinc).
USES.—Like sulphate of copper. Not used internally.

ARGENTUM. Ag; 108 B.P. (107·7 U.S.P.) Silv

Argentum Purificatum. B.P. REFINED SILVER.
Pure metallic silver.

IMPURITIES.—Gold, copper, and lead.
TEST.—If ammonia be added in excess to a solution of the metal in acid, the resulting fluid exhibits neither colour nor turbidity.

PREPARATION.
Argenti Nitras.

Argenti Nitras, B. and U.S.P. NITRATE OF SILVER. I CAUSTIC.—$AgNO_3$; 169·7.
CHARACTERS.—In colourless tabular crystals, the pr form of which is the right rhombic prism; or in white cylin rods.

SOLUBILITY.—It is soluble in distilled water, and in rectified spirit.
REACTIONS.—The solution gives with hydrochloric acid a curdy precipitate, which darkens by exposure to light, and is soluble in solu ammonia. A small fragment heated on charcoal with the blowpip melts, and then deflagrates, leaving behind a dull white metallic coat
PREPARATION.—By dissolving silver in nitric acid, evaporating a stallising.
It is obtained in rods by fusing the crystals in a capsule of platin

orcelain, and pouring the melted salt into proper moulds. Nitrate of must be preserved in bottles carefully stoppered.

ughened nitrate of silver or '**toughened caustic**' is formed by adding ts of nitrate of potassium to 95 parts of the nitrate of silver before .

PREPARATIONS FOR WHICH NITRATE OF SILVER IS USED.

Argenti et Potassii Nitras.

Argenti Oxidum.

PURITIES.—Nitrate of potassium, metallic impurities.

STS.—Ten grains dissolved in two fluid drachms of distilled water give hydrochloric acid a precipitate, which, when washed and thoroughly weighs 8·44 grains. The filtrate, when evaporated by a water-bath, s no residue.

OSE.—$\frac{1}{6}$ to $\frac{1}{2}$ grain.

DMINISTRATION.—As an application to the eyes or injection used in solutions of various strengths, but an ordinary safe is 2 grains to the ounce. When made into pill it must not ixed with tannin, which reduces the silver to the metallic ition and becomes converted into gallic acid with evolution rbonic acid gas. It is best made up into pill with kaolin a very little tragacanth. As a draught it may be made up dilute nitric acid, syrup, and mucilage.

U.S.P. Argenti Nitras Fusus. MOULDED NITRATE OF ER.

HARACTERS.—A white, hard solid, generally in form of pen- or cones of a fibrous fracture, becoming grey or greyish- k on exposure to light in presence of organic matter.

REPARATION.—Prepared by fusing together nitrate of silver 100 parts, ochloric acid 4 parts, and pouring into suitable moulds.

Argenti et Potassii Nitras, B.P.; Argenti Nitras Dilutus, U.P. NITRATE OF SILVER AND POTASSIUM, B.P.; DILUTED RATE OF SILVER, U.S.P. Mitigated Caustic.

HARACTERS.—White or greyish-white cylindrical rods or s.

REPARATION.—Prepared by fusing together nitrate of silver 1 part, with te of potassium 2 parts, B.P.; 1 part, U.S.P.

OLUBILITY.—It is freely soluble in distilled water, but only sparingly in fied spirit.

EACTIONS.—The aqueous solution gives with hydrochloric acid a curdy e precipitate which darkens by exposure to light (silver); the filtrate this mixture giving a yellow precipitate with perchloride of platinum ssium), and evolving ruddy fumes when warmed with sulphuric acid and er (nitrate).

GENERAL ACTION OF SILVER SALTS.—Soluble silver salts, as the nitrate of silver, have a strong affinity for the cement which epithelial or endothelial cells are united, and are, refore, much used in staining microscopic preparations. y also unite with albumen, forming **albuminates** of silver. en applied to the **skin**, nitrate of silver produces a white

mark which rapidly becomes blackened by exposure to light, a
the epidermis, either alone or with a slough varying in de
according to the strength of the application, is thrown
Locally, it causes greater contraction of the **vessels** than ot
metals. In the **mouth** it has an unpleasant astringent ta
corrugates the mucous membrane, and acts as an irritant
caustic. In the **stomach**, in small doses, it acts as an astr
gent, and occasionally lessens vomiting, but in larger doses
acts as an irritant, and causes vomiting and symptoms of irrit
poisoning (p. 396). In the **intestine** small doses are astringe
and, when absorbed from the blood, appear, like zinc or copp
to have a tonic action on some parts of the **nervous syste**
When taken for a length of time it is apt to cause a livid disc
ration of the skin. This discoloration appears to depend u
the amount of silver taken independently of the time dur
which its administration has been continued, so that it is
visable, when administering nitrate of silver to a patient
inquire whether he has previously taken it or not, as the sil
remaining in the system, together with that administered in
second instance, might cause a darkening of the skin which
quantity employed in the second course alone would not h
produced. When taken for a long time, silver salts appear
produce fatty degeneration of the **tissues**. They are proba
very slowly **eliminated** by means of albuminous secretions s
as bile.

USES.—Nitrate of silver may be applied to destroy paras
fungi and remove tinea; to destroy the epidermis itself or
dermic structures such as warts, and to check the bleeding fi
leech-bites. In solution it relieves the itching of pruritus an
lichen. When sponged over the skin it hardens the epider
and may prevent the formation of bed-sores. It is said to ar
vesication in herpes if painted over the surface as soon as
vesicles begin to form. It is also said that the pitting of sm
pox is prevented by opening the vesicle and touching the sur
beneath with a solution of the salt, or even by painting the s
tion over the skin. It has been recommended as a remedy
erysipelas, and is applied either by painting the strong solu
over and beyond the inflamed surface, or by drawing a line
solid nitrate of silver upon the skin a little way beyond
margin of the inflammation. The alteration produced in
tissues underneath this line is said to prevent the extensio
the inflammation beyond the limit thus formed. It is of l
use in poisoned wounds, such as the bite of a mad dog (p. 3
Dilute solutions may be applied to the eye in tinea tarsi
conjunctivitis. In the mouth it may be used as an applica
to ulceration of the tongue, soft palate, or tonsils, and is o
employed for this purpose on account of the readiness with w
it can be applied; it is especially useful in follicular tonsil

pharyngitis. In thus applying it care should be taken that well fixed in the holder, as otherwise a quick motion of the ent may break off the portable stick of nitrate of silver, which probably fall into the pharynx, be swallowed, and may luce symptoms of irritant poisoning. The treatment of oning is to give common salt in order to form insoluble, and efore inert, chloride of silver. Where the stick of nitrate of r has been swallowed in substance this treatment has not ys proved efficacious, and salt should therefore then be ad- istered in combination with mucilaginous substances such orridge and gruel, along with an emetic, so that the stick of r may be at once evacuated from the stomach, while the ilaginous envelope prevents it from doing any harm to the phagus on its way. It has been used to destroy the false brane in croup, and as a useful application to the larynx in ngeal phthisis. It may be applied either in solution of the ngth of 30 grains to the ounce in laryngeal phthisis, by ns of a brush, or in the form of lycopodium, which, after g dipped in the solution and then dried, may be blown by a ed tube into the larynx (cf. p. 480). It is sometimes used as injection in gonorrhœa. Internally, it may be employed in able stomach, and also as an astringent in chronic diarrhœa dysentery, and as a nervine tonic in chorea and epilepsy.

Argenti Oxidum, B. and U.S.P. Oxide of Silver. O ; 231·4.

Characters.—An olive-brown powder, which at a low red t gives off oxygen and is reduced to the metallic state.

olubility and Reactions.—It dissolves completely in nitric acid with- he evolution of any gas, forming a solution which has the characters of te of silver. 29 grains heated to redness leave 27 grains of metallic r.

Dose.—½ to 2 grains.

Uses.—It has been used internally in neuralgic pain in the nach, irritable dyspepsia, and pyrosis. Another drug not requently given in similar affections is creasote ; but creasote oxide of silver are incompatible, as the former becomes lised at the expense of the silver oxide, and the mixture may ergo spontaneous combustion. It has been used in hæmor- ge from the stomach and lungs, and has been highly recom- ded in menorrhagia.

U.S.P. Argenti Cyanidum. Cyanide of Silver. AgCN ; ·7.

Characters.—A white powder permanent in dry air, but dually turning brown on exposure to light, odourless and eless.

Solubility.—It is insoluble in water or alcohol; insoluble in cold soluble in boiling nitric acid, with evolution of hydrocyanic acid; also sol in water of ammonia and in solution of hyposulphite of sodium.

Reactions.—When heated the salt fuses, gives off cyanogen gas, and ignition metallic silver is left.

Officinal Preparation.

U.S.P.

Acidum Hydrocyanicum Dilutum.

U.S.P. Argenti Iodidum. Iodide of Silver. AgI; 23

Characters.—A heavy, amorphous, light-yellowish pow unaltered by light if pure, but generally becoming somew greenish-yellow, without odour and taste.

Solubility.—It is insoluble in water, alcohol, diluted acids or in solu of carbonate of ammonium. Soluble in about 2,500 parts of stronger w of ammonia.

Reactions.—It is dissolved by an aqueous solution of cyanide of po sium and the resulting solution yields a black precipitate with hydrosulph acid or sulphide of ammonium (silver). If a small quantity of chlo water be agitated with an excess of the salt, the filtrate acquires a dark colour on the addition of gelatinised starch (iodide).

Dose.—1 to 2 grains.

Use.—It has been used instead of nitrate of silver in irr bility of the stomach, dysmenorrhœa, and epilepsy.

Class II. Group IV.

MERCURY. Hg; 200.

Mercury is a liquid metal. It forms two series of compou viz. mercurous, in which it is univalent, e.g. Hg_2Cl_2; and m curic, in which it is bivalent, e.g. $HgCl_2$. In constitution th salts are analogous to the cuprous and cupric salts.

General Sources.—The chief source is native sulphide cinnabar.

Metallic mercury is prepared from this by roasting it eit alone or with lime or iron.

General Reactions of Salts of Mercury.—They are either volatile, or decomposed by heat with the liberation of mercury. The soluble salts are decomposed by stannous chlori the mercuric salts giving first a white precipitate changing i black, and the mercurous salts a black one of finely divided m cury at once. Mercurous salts are most readily distinguis from mercuric salts by their reactions with alkaline carbona with ammonia, or with potassium iodide. The differences be readily seen from the following table. The difference betw the reactions of potash and ammonia with mercuric salts is n worthy.

General Reactions of Salts of Mercury.

Reagent	Mercurous Salts	Mercuric Salts
nnous chloride .	Black ppt. (finely divided mercury)	White ppt., turning black (calomel changing into mercury).
ustic soda or potash	Black ppt. . .	Yellow ppt. (oxide).
rbonates of sodium or potassium	White ppt. turning black	Red-brown ppt.
mmonia . .	Black ppt. . .	White ppt. (double salt of mercury and ammon a).
mmonium carbonate	White ppt. turning black	White ppt.
tassium iodide .	Greenish-yellow ppt.	Bright scarlet ppt., soluble in excess either of mercuric chloride or of potassium iodide.

General Impurities.—Other metals, especially lead, arsenic, and antiny, may be present. But there is such an enormous difference between activity of the mercurous and the mercuric salts, that the latter form the st important impurities of the former. Corrosive sublimate, for example, o active that a slight trace of it as an impurity in calomel might cause a dicinal dose of the latter to produce poisonous effects.

General Test.—Mercuric salts are readily soluble in alcohol, and espelly in ether, and also in a solution of sodium chloride, while mercurous s are not. The presence of mercuric compounds as an impurity in merous preparations can be ascertained by shaking them with ether (B.P.), with a solution of common salt (U.S.P.), filtering, and testing the filtrate mercury. If no mercuric salt has been present, neither the ether nor t solution will dissolve anything, and so the test will show the absence mercury. When ether or alcohol is used, the absence of mercury may be ertained by evaporating it and finding that no residue remains.

General Action.—Metallic mercury, mercurous salts, and ercuric salts all have actions differing from each other as far their local effect is concerned, but agreeing together in their neral result after absorption into the system. When applied ally to the skin, **mercury**, either in a state of vapour or when ely subdivided in the form of ointment, will pass through the idermis without exciting any local irritation, and be absorbed to the circulation, where it will produce the general effects of e drug. Taken in the form of vapour into the lungs, it will ve a similar action. The **mercurous salts** are also absorbed the same way as metallic mercury. They have a slightly ore stimulating effect than it, but do not produce the same tense irritation that the mercuric salts cause. The **mercuric lts** unite with albumen, forming **albuminates**. They have tle action on the epidermis, but when applied to the denuded in, or to a mucous membrane, they precipitate the albumen, nd, when used in a concentrated form, produce a slough. When vallowed, they cause the symptoms of gastro-enteritis produced y other irritant poisons, but these may be quickly succeeded by

the symptoms of special mercuric poisoning from the absorpti of the substance into the circulation (cf. p. 398).

The general effects on the body which are produced alike mercury and its salts are termed **mercurialism.**

The first symptoms produced by mercury, however it is a plied, are almost always connected with the alimentary can and more especially the **mouth.** A metallic unpleasant taste observed in the mouth, along with a feeling of heat; the saliva somewhat increased and the breath has a most unpleasant sm The teeth feel sticky, as if their edges were glued together wi some adhesive substance, when the patient tries to separa them; they feel as if they were longer than usual. The gu are red and swollen and tender, and chewing is painful. T tongue is covered with a thick coating, and the appetite is sma The **medicinal administration** of mercury is generally stopp when the gums become sore and salivation begins. In childr salivation occurs with difficulty, and mercury may be disco tinued when the breath becomes fœtid or the previously healt stools become green and offensive. When the administration mercury is continued the symptoms increase; the gums beco still more inflamed, their edges are covered with a white sticky su stance, and they bleed on the slightest touch; the teeth beco loosened in their sockets, and the **salivation** becomes still great

In still worse cases ulcers form on the gums and inside t cheeks, the tongue itself becomes swollen so that articulation b comes difficult, mastication is so painful as to be nearly i possible, the fœtor of the breath is insupportable, and the sali pours from the mouth in great quantities.

Along with these symptoms there is a certain amount **fever,** which, indeed, sometimes is present before any lo symptoms have appeared. There is general depression, chilline and even rigors, followed by a rise of temperature, a feeling heat, thirst, loss of appetite, quick pulse, weight or pain in t epigastrium, nausea, belching, vomiting, and purging, sometim bloody motions, or more rarely constipation. These symptor last several days and then decrease, sweating occurring at t same time, or salivation if the fever has preceded it. Mercuri fever occurs most readily after a lengthened application of bl ointment.

When the administration of mercury is stopped the symptor decrease, though in the case of broken-down individuals necro of the jaw, and even death, has occurred.

Occasionally it has happened that even healthy individua instead of recovering after profuse salivation, have become pe manently dyspeptic.

These symptoms appear in adults, generally with great reg larity, when a similar quantity of mercury has been taken in similar time, though the effect is modified by various condition as age, sex, the presence of disease, &c.

When persons are exposed for a long time to the fumes of ercury, and the metal is thus taken in in very small quantities a lengthened period, a different effect is sometimes produced. is is called **mercurial cachexia**. In this condition the appe- e is lost, the gums become livid and bleed easily, the breath is tid, the tonsils and fauces become congested or even ulcerated, d a tendency to diarrhœa is often present. In bad cases vomit- g and purging generally occur.

The lips become pale, the complexion earthy, the person comes emaciated, the hair sometimes falls out, the muscles come weak and small. The person is easily affected by changes weather; there is a tendency to fainting, uneasiness, and xiety; the pulse and respiration become quick; the pulse is so small and intermittent; and palpitation becomes very oublesome. The intellect is dull, and rheumatic pains are felt in e muscles of the extremities, more rarely in those of the trunk.

These symptoms go on increasing, and new ones also appear. **Iercurial tremors** occur in the muscles, beginning generally the upper extremities, and gradually extending till the patient nnot execute any movement, and the speech itself becomes ammering.

Mercurial paralysis of muscles or groups of muscles occa- onally occurs. Generally this is confined to the muscles of the pper extremities, but sometimes affects other muscles, such as ose of the larynx, causing mercurial aphonia. These paralyses enerally occur in the later stages of mercurial erethism, and rely occur before the other symptoms.

The **mental qualities** become also affected. Ill-humour, ritability, melancholy, and fear of death occur in some persons, nd in others, though very rarely, idiocy, and still more rarely, rious mania. In some instances epilepsy has been observed.

Mercury in the form of organic compounds appears to have special action on the **brain**. The symptoms are those of im- airment of the special senses, sight, taste, hearing, of motor ower, and of the cerebral functions. Two chemists who were ngaged in the preparation of mercuric methide during three nonths, suffered from weakness and dimness of vision, and one of nem from some soreness of the gums, nausea, and vomiting. At he end of this time the symptoms became much worse, deafness nd numbness came on, and were succeeded by a semi-comatose ondition with great restlessness. In the one who had not pre- iously suffered from soreness of the gums, this now appeared, long with fœtor of the breath; the urine was albuminous, heyne-Stokes' breathing was observed, the evacuations were assed involuntarily, and he died comatose a fortnight after the ymptoms became severe. Sensibility was retained nearly to he last. In the other patient, impaired sensation, loss of power o direct movement, and muscular feebleness were succeeded by

involuntary passage of evacuations, an idiotic condition of re lessness, and violent muscular movements, especially when was touched. After remaining in an idiotic state for a year died of pneumonia.

The action of mercury may be **modified** by sex, age, or id syncrasy. Women, as a rule, are more easily affected than m whilst children may take mercury in considerable quantit without showing any symptom of salivation. In certain perso large quantities of mercury may be administered for a length time without producing much more effect than in children, l in others exceedingly injurious results may follow very min doses. A case of salivation from as little as a grain and a h of calomel has been recorded, and from one-eighthieth of a gr of corrosive sublimate. In typhus it is very hard to produ salivation, but in persons suffering from Bright's disease, althou mercury may be useful as a purgative, it requires to be giv with caution, on account of the violent effects which may foll even small doses.

Mercury combines with **albumen**, and forms albuminate mercury, which is insoluble in water, but is easily soluble in cess of albumen or in chloride of sodium. This compound m be formed in the stomach or intestines, and a compound of m curic oxide with albumen is probably the form under wh mercury, however administered, circulates in the blood. Wh taken into the **stomach**, mercuric salts are powerful irritan and, when given in large quantities, cause gastro-enteri vomiting, and purging, with bloody stools. Finely divid metallic mercury and mercurous salts are less irritating, and simply as purgatives.

A good deal of discussion has arisen regarding the action mercury on the **liver**. It has long been ranked as a cholagogu and there can be no question whatever that mercury and compounds are very beneficial in cases of so-called bilious d order characterised by feelings of laziness and apathy, inabil to think, dislike of exertion, not unfrequently combined w irritability of temper, deranged digestion, and slight yellowi tinge of the eyes. When bile was supposed to be formed in t blood, and to be only excreted by the liver, the beneficial eff of mercury was attributed to a stimulating action on the liv whereby it increased the rapidity of the secretion, and thus moved the bile more quickly from the blood. But it was fou on experiment by Dr. Scott that mercury does not increase t rapidity of the biliary secretion, and this result was confirmed a committee of the British Medical Association, the chief me bers of which were Hughes Bennett, Rutherford, and Gamg and also by later experiments made by Rutherford, Vignal, a Dodds. As we now know that bile is formed by the liver, a not merely separated from it by the blood, we can understa

that the real action of mercury as a cholagogue consists, not in its stimulating the liver to form more bile, but in removing more readily from the body the bile which is already present in excess. It appears to perform this function by stimulating the upper part of the small intestine, and thus causing the evacuation of the bile before time has been allowed for its reabsorption. For the liver does not merely form bile, it also excretes bile which has been previously formed and reabsorbed from the intestine. The bile may thus serve several times over. It is formed, passes from the liver into the duodenum, is reabsorbed, and carried by the portal blood to the liver, where it is again excreted and poured out through the bile-duct a second time (p. 404). Part of it, however, is carried down the intestine, decomposed, and evacuated, and to supply the place of this a certain amount of new bile is constantly being formed, which is poured into the intestine along with the old. It is evident that any drug which acts upon the lower part of the intestine will have little power to remove the bile, as this will have undergone absorption already in the upper part of the digestive tract. But any drug acting upon the duodenum will cause the bile to be rapidly moved on and its absorption to be prevented. More especially will this be the case if the cholagogue be combined with a saline purgative, which, by causing a profuse secretion of watery fluid, will wash the bile out. This action on the upper part of the small intestine is probably possessed by mercury, and the reasons for this supposition are: (1) that it is so beneficial in bilious disorders; (2) that it does cause the appearance of bile in the stools, for Buchheim has found by analysis that the green stools which occur after purgation by calomel actually owe their colour to bile; and (3) that in the stools passed after mercurial purgatives, leucin and tyrosin, the products of pancreatic digestion, have been found, showing the rapid peristalsis produced. Mercury acts as a **disinfectant of the intestinal contents.**

After the absorption of mercury into the **blood**, it is said, in small doses, to increase the number of blood-corpuscles; in larger doses, however, it produces anæmia, but how far these results are dependent upon the improvement or disturbance of the digestion, and how far upon the action of the mercury itself upon the blood, has not been ascertained. Albuminate of mercury, when added to blood out of the body, gradually destroys the corpuscles.

Mercury appears to have the power of causing absorption of **fibrinous exudations**, for the fibrinous adhesions observed in syphilitic iritis have been seen to disappear as the patient was brought under the influence of mercury. When mercury is used for a long time, it appears to lessen greatly the force of the pulse, and large doses of mercuric preparations, when brought into contact with a frog's **heart**, will arrest its pulsations immediately.

The **respiration** is affected in persons who have been taking much mercury, and becomes laboured and accompanied feeling of constriction. The **temperature** is rarely affec excepting secondarily, in consequence of local inflammat which the mercury may excite, although sometimes mercu fever (p. 682) precedes any marked local change.

Mercury is **excreted** by the saliva, bile, urine, sweat, milk. The **salivation** which it produces is probably due in to reflex excitement of the salivary glands by the irritatio the tongue, but it is no doubt also in part due to irritatio the nerves of the gland, or of the gland-structure itself, by mercury. The **urine** is said to be somewhat increased, and stated that the addition of a little mercury to digitalis and s greatly increases the diuretic action of these drugs. Calomel an undoubted diuretic action, and it has been suggested th owes this action to the increase of urea in the blood, prod by part of the salt being changed into mercuric chloride, w acts as an hepatic stimulant (cf. p. 432).

Hydrargyrum. B. and U.S.P. MERCURY. Hg; 200 199·7 U.S.P.

CHARACTERS.—A metal, fluid at common temperatu brilliantly lustrous, and easily divisible into spherical globul

REACTION.—Volatilises at a heat below that of visible redness, leavi residue.

PREPARATIONS CONTAINING MERCURY.[1]

I. **In the metallic state.**

B.P. (9)	U.S.P. (7)
Hydrargyrum.	Hydrargyrum.
Emplastrum Ammoniaci cum Hydrargyro (1 in 5).	Emplastrum Ammoniaci cum drargyro.
Emplastrum Hydrargyri (1 in 3).	Emplastrum Hydrargyri.
Hydrargyrum cum Creta (1 in 3).	Hydrargyrum cum Creta.
Linimentum Hydrargyri (*v.* p. 516) (1 in 6).	
Pilula Hydrargyri (*v.* p. 522) (1 in 3).	Massa Hydrargyri.
Suppositoria Hydrargyri (1 in 6).	
Unguentum „ (1 in 2).	Unguentum Hydrargyri.
„ „ **Compositum** (1 in 4½).	„ „ Compos

II. **Oxidised.**

(5)	(4)
Hydrargyri Oxidum Flavum.	Hydrargyri Oxidum Flavum.
„ „ **Rubrum.**	„ „ Rubrum.
Lotio Hydrargyri Flava.	
„ „ **Nigra.**	
	Unguentum Hydrargyri Oxidi
Unguentum Hydrargyri Oxidi Rubri.	„ „ „

III. **Sulphuretted.**

	(1)
None.	Hydrargyri Sulphidum Rubrum

IV. **As Mercurous Chloride.**

(3)	(3)
Hydrargyri Subchloridi.	Hydrargyrum Chloridum Mite.
Pilula Hydrargyri Subchloridi Composita (*vide* p. 522).	Pilulæ Antimonii Compositæ p. 523).
	Pilulæ Catharticæ Compositæ
Unguentum Hydrargyri Subchloridi.	p. 523).

[1] Altered from the *United States Dispensatory*, p. 773.

PREPARATIONS CONTAINING MERCURY—*continued*.

V. **As Mercuric Chloride.**

B.P. (4)	U.S.P. (3)
Hydrargyri Perchloridum.	Hydrargyri Chloridum Corrosivum.
Hydrargyrum Ammoniatum.	Hydrargyrum Ammoniatum.
Liquor Hydrargyri Perchloridi.	
Unguentum Hydrargyri Ammoniatum.	Unguentum Hydrargyri Ammoniati.

VI. **Combined with Iodine.**

(3)	(3)
Hydrargyri Iodidum Rubrum.	Hydrargyri Iodidum Rubrum.
	,, ,, Viride.
Liquor Arsenii et Hydrargyri Iodidi.	Liquor Arsenii et Hydrargyri Iodidi.
Unguentum Hydrargyri Iodidi Rubri.	

VII. **Combined with Cyanogen.**

	(1)
None.	Hydrargyri Cyanidum.

VIII. **Oxidised and combined with Acids.**

(5)	(4)
Hydrargyri Persulphas.	
	Hydrargyri Sulphas Flava.
Liquor Hydrargyri Nitratis Acidus.	Liquor Hydrargyri Nitratis.
Oleatum Hydrargyri.	Oleatum Hydrargyri.
Unguentum Hydrargyri Nitratis.	Unguentum Hydrargyri Nitratis.
,, ,, ,, Dilutum.	

IMPURITIES.—Other metals.

TESTS.—The presence of other metals is ascertained by their being left behind as a residue when the mercury is volatilised. It is indicated by the formation of a grey scum or dust on the surface of the metal after exposure to air, and by the mercury forming globules which are not spherical but elongate to a tail when allowed to run over a piece of paper. They are also recognised by shaking the mercury in a perfectly dry bottle, when a grey powder will be formed if they are present.

On boiling 5 grms. of distilled water with 5 grms. of mercury and 4·5 grms. of hyposulphite of sodium in a test-tube for a minute, the mercury should not lose its lustre nor acquire more than a slightly yellowish shade (absence of more than a trace of other metals, U.S.P.).

PURIFICATION.—Other metals may be separated by distillation, or by mixing the mercury with strong sulphuric acid and letting it stand in the cold for twenty-four hours. The other metals will be converted into sulphates, but mercury is only attacked by sulphuric acid when it is aided by heat. The mercury is then washed with water to remove the sulphates, and dried with blotting-paper. Mercury is freed from dust and mechanical impurities by pressing it through chamois leather or filtering it through a paper filter in the apex of which several small holes have been made with a needle or pin.

USES.—Metallic mercury in mass has no action whatever on the body. As much as a pound has been taken without producing any physiological effect. Such a dose as this is sometimes given in cases of intestinal obstruction in the hope that the weight of the mercury may carry the obstruction before it. The theory of its action formerly held was purely mechanical: that the mercury passed from the stomach to the intestines and meeting with the obstruction drove it on; but latterly Traube

has supposed that the mercury remains chiefly in the stomac and by pulling on it excites the intestines reflexly to peristal action. Whatever the correct theory may be, however, it certain that the mercury does not always stay in the stomac but does get down into the intestine, and consequently so precautions must be observed in its administration, and it never given except when all other measures fail. The p cautions are not to give it in cases of intussusception, as it m very probably render this worse; nor in cases where the intesti is considerably inflamed, as the tissues being weak are then eas torn; nor in hernia, as better means, viz. external means, c be employed.

Hydrargyrum cum Creta, B. and U.S.P. MERCURY WITH CHALK.

PREPARATIONS.—By rubbing up chalk (2) and mercury (1) together, B.P. rubbing up mercury (38), chalk (50), and sugar of milk (12) together, moisten them with a mixture of equal parts of ether and alcohol, U.S.P.

CHARACTERS.—A powder of light-grey colour; free from grittiness; insolu in water; partly dissolved by diluted hydrochloric acid, leaving the mercury ir finely-divided state.

IMPURITY.—Mercuric oxide.

TEST.—The solution formed with hydrochloric acid is not precipitated by addition of chloride of tin.

DOSE.—3 to 8 grains.

USES.—It has been much recommended by Ringer as remedy in many diseases both of adults and of children. simple tonsillitis, or the inflamed throat of scarlatina, or mumps, he recommends a third of a grain every hour, and t same dose three or four times a day will, he says, clean t tongue, remove the disagreeable taste from the mouth, a improve appetite and digestion in the dyspepsia occurri in chronic disease or commencing convalescence. A simi dose will cut short an attack of jaundice, with vomiting a pale stools, occurring in nervous persons after exposure to co fatigue, or excitement; and half a grain thrice a day will rest the colour to the stools and remove the dyspepsia in patie suffering from acidity, flatulence, and vomiting in the mornir Diarrhœa in children, accompanied by pale, offensive motio or by muddy, or green-coloured, or curdy stools, whet accompanied by sickness or not, is successfully treated similar doses of this remedy. It may also be used to produ the general action of mercury combined with opium or Dove powder.

B.P. Pilula Hydrargyri. MERCURIAL PILL; BLUE PILL (p. 522). 3 contain 1 of mercury.

DOSE.—3 to 8 grains.

U.S.P. Massa Hydrargyri. BLUE MASS; BLUE PILL.—Mercury (33), powde liquorice (5), althæa (25), glycerin (3), honey of rose (34). 3 grs. contain 1 of mercu

USES.—Blue pill may be given either for its local action up the intestines or to produce the action of mercury upon the syste This pill is one of the most effectual remedies for the conditi usually termed biliousness. The patient complains of feeli

l, heavy, and often sleepy, suffers from occasional headache, s little appetite, and occasionally feels sick. The complexion is en of a dirty-yellow, muddy colour, and the white of the eyes ewise. The use of blue pill in such conditions was recommended by Mr. Abernethy. Five grains of blue pill are given rnight and a draught of salts and senna in the morning. This very effective, but the disadvantage of it is said to be that the ous state is more apt to return, and that when a patient has e become habituated to the use of mercurials no other medicine l do instead.

It is one of the best preparations for producing **mercurialism**: grains with ½ grain of opium are given in the morning, and r 10 also with ½ grain of opium in the evening.

The addition of a small quantity of blue pill to digitalis and ill sometimes increases their efficacy in cases of cardiac disease.

Unguentum Hydrargyri, B. and U.S.P. Ointment of Mercury, B.P.; curial Ointment, U.S.P.—Contains 1 lb. each of mercury and prepared lard. his would be too soft, 1 oz. of prepared suet is added.

Preparations.

Linimentum Hydrargyri (p. 516).
Suppositoria Hydrargyri.
Unguentum Hydrargyri Compositum.

Uses.—It may be used either for its general or its local ion. When employed to produce the **general action** of mery in the system, it is rubbed into some part of the body where skin is thin, as the armpits or the sides of the thighs. If it rubbed in by another person, and not by the patient himself, s advisable to protect the operator's hand by a piece of bladder ked in oil, in order to prevent absorption through the palm. cases of congenital syphilis, a piece of mercurial ointment, the e of the thumb-nail (half a drachm to one drachm), may be upon a flannel roller, and bound round the child's belly.

It has been applied **locally** in inflammation of the skin, as sipelas; of the veins in phlegmasia dolens; or of the genital ans, as in ovaritis, orchitis, and indurated testicles.

B.P. Suppositoria Hydrargyri. Mercurial Suppositories.—Each con- s 60 grs. of ointment of mercury, benzoated lard and white wax each 20 grs., f theobroma 80 grs.

Uses.—They are employed where we wish to produce mercurial ion without the risk of interfering with the digestion.

B.P. Unguentum Hydrargyri Compositum. Compound Ointment of curv.—Contains mercurial ointment (6), yellow wax (3), olive oil (3), and phor (1½).

The compound ointment is used to cause absorption of effusion thickening around joints in cases of disease or injury after the ammation has subsided. It ought to be combined with pres- e and rest.

B.P. Linimentum Hydrargyri. Liniment of Mercury.—*Vide* p. 516.

Used for similar purposes as the plaster or ointment. I more irritating than either, on account of the ammonia it conta

It is said to cause salivation more readily than mercu ointment, as the camphor and ammonia with which it is mi assist its absorption.

Emplastrum Hydrargyri, B. and U.S.P. MERCURIAL PLASTER.

PREPARATION.—Rub mercury with olive-oil, and sulphur B.P. or resin U. and add lead plaster to give it consistency. Sulphur and resin are used tc tinguish the globules of mercury, i.e. make them so small as to be invisible.

Emplastrum Ammoniaci cum Hydrargyro, B. and U.S.P. AMM CUM AND MERCURY PLASTER, B.P.; AMMONIAC PLASTER WITH MERCURY, U.S.P.

PREPARATION.—B.P. By rubbing mercury 3 oz. with warm olive-oil 1 fl. dr., sulphur 8 grs. until the globules of mercury are no longer visible, then ad melted ammoniacum 12 oz. and mixing. U.S.P. Mercury 180 is extinguished sulphur 1 and olive oil 8 as in the B.P. process. Ammoniacum 720 is digested diluted acetic acid 1,000, strained, evaporated until it hardens on cooling. then added while hot to the mercury, and mixed. Then enough lead plaster viously melted is added to make up to 1,000 parts.

Both plasters are used to promote the absorption of gland enlargements, buboes, nodes, and are applied over the live chronic enlargement and induration. Emplastrum hydrar is useful also in sycosis, lupus, and other deep-seated infiltrat of the skin.

B.P. Hydrargyri Persulphas. PERSULPHATE OF MERC $HgSO_4$.

CHARACTERS.—A white crystalline heavy powder.

PREPARATION.—Heat mercury 20 oz. with sulphuric acid 12 fl. oz. porcelain vessel, stirring constantly until the metal disappears, then con the heat until a dry white salt remains.

REACTIONS.—It is rendered yellow by affusion with water, the subsul being formed. Entirely volatilised by heat.

PREPARATIONS IN WHICH SULPHATE OF MERCURY IS USED.

Hydrargyri Perchloridum. Hydrargyri Subchloridum.

U.S.P. Hydrargyri Subsulphas Flavus. YELLOW SUE PHATE OF MERCURY. $Hg(HgO)_2SO_4$; 727·1.

CHARACTERS.—A heavy lemon-yellow powder, permaner the air, odourless and almost tasteless.

SOLUBILITY.—It is insoluble in water or in alcohol, but soluble in nit hydrochloric acid.

REACTIONS.—When heated the salt turns red, becoming yellow aga cooling. At a red heat it is volatilised without residue, evolving vapo mercury and of sulphurous acid.

TESTS.—As it is a mercuric oxysulphate, it should be soluble in 20 of hydrochloric acid without residue (no mercurous salt).

USES.—The yellow oxysulphate has been used under the n of Turpeth mineral as an errhine in chronic ophthalmia. a prompt emetic, and is sometimes preferred to other emeti croup, as it is quick and certain, and does not produce depre nor purging. The dose for a child two years old is 2–5 g (0·13–0·33 gm.), repeated in fifteen minutes if necessary may also be used as an alterative.

Hydrargyri Subchloridum, B.P.; Hydrargyri Chloridum te, U.S.P. SUBCHLORIDE OF MERCURY, HgCl, B.P.; MILD LORIDE OF MERCURY, Hg_2Cl_2; 470·2, U.S.P. CALOMEL.

CHARACTERS.—A dull-white, heavy and nearly tasteless powder, dered yellowish by trituration in a mortar.

SOLUBILITY.—It is insoluble in water, spirit, or ether.

REACTIONS.—It is very heavy, and can be distinguished by its weight from ost every other white powder. Its weight is noticed more distinctly by ng the bottle an up-and-down shake. Digested with solution of potash it mes black (mercurous oxide); and the clear solution, acidulated with ic acid, gives a copious white precipitate with nitrate of silver (chloride). tact with hydrocyanic acid also darkens its colour.

PREPARATION.—Calomel is prepared by rubbing up mercury with sulphate nercury moistened with water till globules are no longer visible, adding um chloride, mixing the whole by trituration, and subliming the mixture a large chamber.

The mercury and mercuric sulphate form mercurous sulphate, and this, sodium chloride, forms calomel and sulphate of sodium, $HgSO_4 + Hg + Cl = Hg_2Cl_2 + Na_2SO_4$.

When the calomel is sublimed into a small receiver it forms a thin crystal- crust which adheres to the sides, but when sublimed into a large cham- as directed in the B.P., it falls as a powder on the floor. As some corro- sublimate is often formed, the powdered calomel is washed with water all the sublimate is removed, as shown by the water no longer giving a ipitate with ammonium sulphide.

It is then dried under 212° F., and kept in a well-stoppered and dark bottle.

ADULTERATIONS.—Chalk, sulphate of calcium, sulphate of barium, car- ate of lead, corrosive sublimate.

TESTS.—It is entirely volatilised by a sufficient heat (no earthy impurities). rm ether which has been shaken with it in a bottle leaves, on evaporation, esidue (no corrosive sublimate).

DOSE.—½ grain to 5 grains.

PREPARATIONS IN WHICH SUBCHLORIDE OF MERCURY IS USED.

B.P.	DOSE.
io Hydrargyri Nigra (3 grains to 1 fluid ounce)	
ula Hydrargyri Subchloridi Composita (1 part in 5, v. p. 522).	5–10 grs.
uentum Hydrargyri Subchloridi, Calomel Ointment (with prepared lard) (1 part in 6½, nearly)..	

U.S.P.

Pilulæ Antimonii Compositæ (p. 523).
Pilulæ Cathartice Compositæ (p. 523).

Pilula Hydrargyri Subchloridi Composita, B.P. PILULÆ ANTIMONII POSITÆ, U.S.P.; COMPOUND PILL OF SUBCHLORIDE OF MERCURY, B.P.; COMPOUND LS OF ANTIMONY, U.S.P. COMPOUND CALOMEL PILL. PLUMMER'S PILL (p. 522).

B.P. Lotio Hydrargyri Nigra. BLACK MERCURIAL LOTION. BLACK WASH. sists of half a drachm of calomel mixed with half a pint of lime-water. It ains suboxide of mercury.

USES.—Calomel may be employed as a dusting powder to re- ve condylomata from the skin, and condylomatous patches m the tongue, throat, and larynx; it is also recommended in following powder—calomel, six parts, boric acid, three parts, icylic acid one part.[1] As an ointment it may be applied to

[1] *Philadelphia Medical Reporter*, June 14, 1884.

relieve the itching in pruritus ani and pruritus scroti, and pi
riasis of the scalp, and to heal strumous sores and lupus
children. In pruritus pudendi it is also of service, though
quite so much as in the other cases (Ringer). It should not
applied in large quantities, lest so much of it be absorbed as
cause its physiological action. Calomel ointment ($\frac{1}{2}$ to 1 drac
to the ounce) is useful in the treatment of small patches of v
cular eczema; and in psoriasis Rochard's ointment, which c
tains one part of iodine and one and a half part of calome
seventy parts of simple ointment, is beneficial in some ca
Black wash is a good application to varicose ulcers, and is u
as an application to syphilitic ulcerations, as a wash to
mouth in syphilitic sore-throat and in cancrum oris.

Internally calomel may be given in cases of biliousness,
followed by a saline purgative in the same manner as is rec
mended under 'Blue Pill.' In some cases of diarrhœa it is v
useful in combination with opium (p. 106).

It may also be used to produce the general action of merc
in syphilitic patients, and for this purpose may either be gi
internally, in combination with opium, or applied to the skin
the form of calomel fumigations (p. 471).[1]

The compound pill of subchloride of mercury may be u
in cases of biliousness, gout or rheumatism.

Calomel is a useful diuretic in some cases of dropsy (pp.
and 686), especially when due to heart-disease. It must be gi
in doses of 4 or 5 grains, repeated when necessary, salivat
being prevented by a chlorate of potassium gargle, and diarrh
by small doses of opium.[2]

**Hydrargyri Perchloridum, B.P.; Hydrargyri Chlorid
Corrosivum, U.S.P.** PERCHLORIDE OF MERCURY, B.P.; COR
SIVE CHLORIDE OF MERCURY, U.S.P. $HgCl_2$; 270·5.

CHARACTERS.—In heavy colourless masses of prismatic cryst
possessing a highly acrid metallic taste.

PREPARATION.—By mixing mercuric sulphate with sodium chloride
subliming into a small chamber. To prevent the formation of any calo
some peroxide of manganese is added.

SOLUBILITY.—It is more soluble in alcohol, and still more so in ether, t
in water.

REACTIONS.—Its aqueous solution gives the reactions of mercuric s
(p. 681) and of a chloride (p. 594).

DOSE.—$\frac{1}{16}$ to $\frac{1}{8}$ grain. In cholera and summer diarrhœa t
dose may be given every quarter of an hour, half-hour, or ho

A solution of 1 in 500 or 1 in 1,000 (about $\frac{1}{2}$ grain in 1
or the liquor of the B.P.) may be used as an antiseptic lotion
for a spray in diphtheria.

---

[1] Mercurous tannate has been used in doses of one grain and a half twic
thrice a day in syphilis. It is said to be efficient, and yet neither to interfere
the digestion, nor to cause any stomatitis. *Zeitsch. f. Therapie*, 2, 1884.

[2] Jendrássik, *Deutsch. Archiv f. klin. Med.*, vol. xxxviii. p. 499.

Officinal Preparations.

B.P.	dose.	U.S.P.
Liquor Hydrargyri Perchloridi	½–2 fl. drm.	None.

Lotio Hydrargyri Flava (18 grs. in 10 fl. oz.).

Used in preparing.—Hydrargyri Iodidum Rubrum; Hydrargyrum Ammoniatum.

B.P. Liquor Hydrargyri Perchloridi. Solution of Perchloride of Mercury. Contains ½ grain of perchloride of mercury in 1 oz. of water, with ½ grain of ammonium chloride to keep it in solution and prevent precipitation.

Uses.—When mixed with **albumen**, corrosive sublimate precipitates it, forming a mercuric albuminate. It is one of the most powerful **antiseptics** known (p. 95). It may be applied (in the strength of 2 grains to the ounce of water) to the skin to destroy vegetable and animal parasites present upon it, such as the fungus in pityriasis versicolor, in sycosis and favus, the acarus of scabies and the pediculus pubis. It is the most powerful remedy for the removal of the pigment in chloasma, and may be applied in a lotion of bichloride of mercury 2 grains, tincture of benzoin half a drachm, and 1 ounce of almond emulsion. For the rapid removal of pigment Hebra used a solution of 5 grains to the ounce of alcohol and water, and applied it by means of compresses for 4 hours, so as to raise a blister; the relief, however, is not permanent, since pigmentation returns. The danger of absorption must be considered, so that it is unwise to apply the treatment to large surfaces. It is useful in allaying the itching of pruritis scroti and pudendi, prurigo, and urticaria. It may be employed as a wash in ophthalmia (p. 216), as a gargle in syphilitic sore-throat, as a spray in diphtheria (p. 692), and as an injection in gonorrhœa, gleet, and leucorrhœa, or for the uterus and vagina in puerperal conditions. When swallowed in strong solution it sometimes causes an **irritant poisoning** (p. 395 *et seq.*); and if this should pass off, it may be succeeded by intense salivation due to the absorption of the drug. The treatment in such cases is to give albuminous substances, such as white of egg or milk, in order to form mercuric albuminate in the stomach, and thus prevent its irritant action on the mucous membrane. If the irritation which the drug itself produces is not sufficient to cause vomiting, the stomach should be emptied by an emetic or the stomach-pump, in order to prevent digestion and absorption of the mercuric albuminate and the poisoning which might occur from its absorption. In small and frequently-repeated doses it is useful in the dysenteric diarrhœa of adults or children and in cholera, its utility probably depending, to a great extent at least, on its antiseptic power, which is not destroyed, like that of other antiseptics, by considerable admixture with organic matter, such as the fæcal contents of the intestine (p. 106). After its absorption it has the same effect as the other salts of mercury, and may be used for this purpose in syphilitic cases.

B.P. Lotio Hydrargyri Flava. Yellow Wash.

Preparation.—By mixing 18 grs. of corrosive sublimate with half a pint of lime-water.

USES.—It is used as a stimulating application to syphil sores in cases where the black wash is not sufficiently powerf

Hydrargyri Oxidum Flavum, B. and U.S.P. YELL OXIDE OF MERCURY. HgO; 215·7.

CHARACTERS.—A yellow powder readily dissolved by hyd chloric acid, yielding a solution which, with solution of ammo gives a white precipitate. It is entirely volatilised when hea to incipient redness, being resolved into oxygen gas and vapour of mercury.

PREPARATIONS.

U.S.P.

Unguentum Hydrargyri Oxidi Flavi (1 in 10 of Unguentum).

B. AND U.S.P.

Oleatum Hydrargyri (yellow oxide 10, oleic acid 90, parts).

USES.—The oleate of mercury acts beneficially in ringwo and may be used for inunction in cases of syphilis in doses o to 30 drops.

Hydrargyri Oxidum Rubrum, B. and U.S.P. RED OX OF MERCURY. HgO; 215·7.

CHARACTER.—An orange-red powder.

SOLUBILITY AND REACTIONS.—It is readily dissolved by hydrochloric yielding a solution which, with caustic potash added in excess, gives a ye precipitate, and with solution of ammonia a white precipitate.

PREPARATION.—Triturate nitrate of mercury and metallic mercury toge and heat until nitrous fumes cease to be given off. $Hg(NO_3)_2 + Hg = 2Hg$ N_2O_4.

IMPURITY.—Undecomposed nitrate.

TEST.—Entirely volatilised by a heat under redness, being at the time decomposed into mercury and oxygen. If this be done in a test- no orange vapours are perceived.

PREPARATIONS.

B. AND U.S.P.

Unguentum Hydrargyri Oxidi Rubri (Ointment of Red Oxide of Mercury) } 1 part in 8, B.P.; 1 in 10, U.S

With soft and hard paraffin, B.P.; with ointment, U.S.P.

USES.—The red oxide is rarely given internally. The ment may be used in ophthalmia and conjunctivitis in the s way as the nitrate of mercury ointment, and as an applica to the auditory meatus in otorrhœa occurring after scarlet fe It is also useful in scaly skin-diseases, syphilitic sores on skin, and in ulcers within the margin of the anus.

Hydrargyrum Ammoniatum, B. and U.S.P. AMMONI MERCURY. WHITE PRECIPITATE. NH_2HgCl; 251·1.

CHARACTER.—An opaque white powder.

SOLUBILITY.—It is insoluble in cold water, alcohol, and ether.

REACTIONS.—Digested with caustic potash, it evolves ammonia, acqu a pale yellow colour, and the fluid, filtered and acidulated with nitric gives a white precipitate with nitrate of silver. Boiled with a solutio chloride of tin it becomes grey, and affords globules of metallic mercury.

PREPARATION.—By dissolving corrosive sublimate in water, and precipitating by ammonia.

IMPURITIES.—Chalk, sulphate of calcium, baryta, lead, carbonates, mercurous salts.

TESTS.—Entirely volatilised at a heat under redness (no chalk, etc.). It should dissolve in hydrochloric acid without residue (no mercurous salt) and without effervescence (no carbonate).

PREPARATION.

B. AND U.S.P.

Unguentum Hydrargyri Ammoniati...1 part in 10, B. and U.S.P. (was about 15 per cent. B.P. 1867.) With simple ointment, B.P.; with benzoated lard, U.S.P.

USES.—Not used internally. The ointment is used in order to destroy parasitic fungi, but more especially to kill pediculi in the hair or on the body. It is also useful in impetigo contagiosa, lichen, pityriasis, herpes, subacute eczema, and other skin-diseases.

Liquor Hydrargyri Nitratis Acidus, B. and U.S.P. ACID SOLUTION OF NITRATE OF MERCURY. $Hg(NO_3)_2$; 323·7.

CHARACTERS AND REACTIONS.—A colourless and strongly acid solution, which gives a yellow precipitate with solution of potash added in excess (mercuric oxide). If a crystal of sulphate of iron is dropped into it, in a little time the salt of iron, and the liquid in its vicinity, acquire a dark colour (nitrate).

USES.—It is a powerful **caustic**, and is used as such in lupus. It is to be applied with a camel's-hair brush to the extent of a brown piece over the ulcers, tubercles, and scars which are soft and ready to break. The part is then covered with lint moistened in the solution. It soon becomes white, a kind of erysipelatous inflammation sets in around it, and it falls off as a yellow scab. The solution is also applied to the os uteri when there are large ulcers with flabby unhealthy granulations upon it. It has been used in cancer and in chancres, condylomata, syphilitic and scrofulous ulcers, favus, and obstinate psoriasis. If applied often it may cause mercurialism, and indeed salivation has occurred after one application to the os uteri. To prevent this it should be washed off immediately after being applied.

Unguentum Hydrargyri Nitratis, B. and U.S.P. OINTMENT OF NITRATE OF MERCURY. CITRINE OINTMENT.

CHARACTERS.—It has a fine lemon-yellow colour and a consistence like butter. It is apt to become decolourised when mixed with metals or deoxidising powders, and hence an excess of acid is used in order that it may reoxidise them as necessary. It should be spread with a wooden or ivory spatula.

PREPARATION.—By mixing a hot solution of mercury in nitric acid with lard and olive oil, B.P.; or with lard oil, U.S.P.

USES.—This ointment was made in imitation of Singleton's

golden eye-ointment, and it is of remarkable service in ophthal
tarsi. It should be mixed with its own weight of almond
and applied to the lids.

It is also applied to phagedænic ulcers and syphilitic so
and soon destroys the parasitic fungi on which ringworm,
depend.

PREPARATION.

B.P.

Unguentum Hydrargyri Nitratis Dilutum (Nitrate of Mercury Ointm
1, Soft Paraffin 2).

U.S.P. Hydrargyri Iodidum Viride. GREEN IODIDE
MERCURY. Hg_2I_2; 652·6.

CHARACTERS.—A dull green powder, which darkens in col
upon exposure to light.

SOLUBILITY.—It is insoluble in water. When it is shaken in a tube
ether nothing is dissolved.

REACTIONS.—Gradually heated in a test-tube, it yields a yellow sublim
which, upon friction, or after cooling, becomes red, while globules of met
mercury are left in the bottom of the tube.

PREPARATION.—By rubbing iodine and mercury together in a porce
mortar, occasionally moistening with a few drops of spirit.

DOSE.—1 to 3 grains.

USES.—It is employed for the purpose of combining
action of iodine with that of mercury, as in cases of second
and tertiary syphilis occurring in persons of a scrofulous con
tution, and especially in the syphilis of children.

Hydrargyri Iodidum Rubrum, B. and U.S.P. RED IOD
OF MERCURY. HgI_2; 452·8.

CHARACTERS.—A crystalline powder of vermilion colour,
coming yellow from an alteration in its crystalline form w
gently heated over a lamp on a sheet of paper, and again
coming red when placed on a sheet of paper and rubbed wit
smooth substance.

SOLUBILITY.—It is almost insoluble in water, dissolves sparingly
alcohol, but freely in ether, or in an aqueous solution of iodide of potass

REACTIONS.—When digested with solution of soda it assumes a redd
brown colour (mercuric oxide); and the fluid, cleared by filtration and m
with solution of starch, gives a blue precipitate on being acidulated
nitric acid (iodide). Entirely volatilised by a heat under redness.

PREPARATION.—By mixing solutions of corrosive sublimate with potass
iodide in the proper proportions.

DOSE.—$\frac{1}{16}$ to $\frac{1}{4}$ grain.

PREPARATIONS.

B.P.

Unguentum Hydrargyri Iodidi Rubri (Ointment of Red Iodide of Mercury) ... } 1 part in 28.

With yellow wax and almond oil.

B. AND U.S.P.	DOSE.
Liquor Arsenici et Hydrargyri Iodidi	10–30 min.

USES.—It may be used for the same purposes as the green ide, but, like all the mercuric salts, it is much more powerful n the corresponding mercurous one. It is a powerful local tant, and is used in the form of ointment in cases of goître. e mode of employing it is to rub the ointment upon the nour, and afterwards to expose the patient either to the heat he sun or of a fire as long as he can bear it. This treatment s first used in India. In this country, where the sun's rays not so powerful, the heat of a fire may be employed, and I ve found it efficacious when used in this way. Red iodide tment is useful in obstinate skin-diseases, especially lupus thematosus.

It is frequently given in syphilis, one of the most common ys of prescribing it being to give one-half to one drachm of solution of the perchloride with several grains of potas- m iodide. The periodide is thus formed, and is dissolved in ess of the potassium iodide.

U.S.P. Hydrargyri Cyanidum. CYANIDE OF MERCURY. $Hg(CN)_2$; 251·7.

CHARACTERS.—Colourless or white prismatic crystals, be- ming dark-coloured on exposure to light; odourless, having a ter metallic taste, and a neutral reaction.

REACTIONS.—When slowly heated the salt decomposes into metallic rcury and cyanogen gas, which is inflammable, burning with a purplish ne. On further heating, the blackish residue containing globules of tallic mercury is wholly dissipated. On adding hydrochloric acid to the eous solution, hydrocyanic acid vapour is evolved.

TESTS.—A 5 per cent. aqueous solution of the salt, when mixed with a te aqueous solution of iodide of potassium, should not yield a red or dish precipitate soluble in excess of either liquid (absence of mercuric oride).

DOSE.—$\frac{1}{16}$ to $\frac{1}{8}$ grain.

USES.—It may be given in syphilis. A solution of 5–10 grains an ounce of water, painted on with a camel's-hair brush, is useful application to syphilitic sores of the tongue or mouth.

U.S.P. Hydrargyri Sulphidum Rubrum. RED SULPHIDE MERCURY. HgS; 231·7.

CHARACTERS.—Brilliant dark-red crystalline masses, or a fine ght scarlet powder, permanent in the air, odourless and steless.

SOLUBILITY.—It is insoluble in water, alcohol, nitric or hydrochloric acid, in dilute solutions of alkalis.

REACTIONS.—It is dissolved by nitrohydrochloric acid, and on adding an cess of stannous chloride, metallic mercury is precipitated.

USES.—It is used for mercurial fumigation. Thirty grains ay be used instead of calomel, in the way already described . 471).

Class IV.

Tetrad Metals.

LEAD. *Titanium.* TIN.

General Actions.—Lead and tin resemble one another t considerable extent in their physiological action. After abso tion into the circulation lead affects the **muscles**, involunt and voluntary, and the central nervous system. Its action muscle appears to be first irritant then paralysing. The irrit action on the muscle of the intestine leads to colic, and on voluntary muscle to cramps in man. In animals, when quantity administered in experiments at one time is much lar paralysing action is more marked, and in frogs and rabb muscular weakness and rapid loss of irritability both in voluntary muscles and heart are marked symptoms. In the paralysis of voluntary muscle is less marked, and in d it is absent.

The **motor area** of the central nervous system appears t much more affected by lead than the sensory; and in dogs, c and pigeons choreic movements and even convulsions oc without impairment of sensation or consciousness. The irr tion of the motor centres is succeeded by paralysis and death

Tin has an action resembling lead in increasing the cont tions of the intestinal canal and causing paralysis of the sp cord. In rabbits it produces weakness and apparent recov and then paresis and death.[1]

LEAD. Pb; 207.

General Source of Lead Salts.—Lead is obtained enti from the native sulphide called galena, by roasting.

General Reactions.—The chief reactions of lead salts shown in the following table:—

Reagent	Reaction
Hydrogen sulphide . . . } Ammonium sulphide . . }	Black precipitate.
Caustic potash or soda . . .	White ,, soluble in excess.
Ammonia	,, ,, insoluble ,,
Carbonates of potassium, sodium, or ammonium . . . }	,, ,, ,, ,,
Sulphuric acid or sulphates . .	,, ,, ,, in nitric a
Potassium iodide	Yellow ,, ,,

[1] T. P. White, *Archiv f. exp. Path. u. Pharm.* 1880, viii. p. 33.

GENERAL IMPURITIES.—Alkaline earths, zinc or copper.

GENERAL TESTS.—As alkaline earths and zinc are not precipitated by hsuretted hydrogen, they can be detected by passing this gas through the tion of a lead salt until all the lead has been precipitated as sulphide. removing the sulphide by filtration, and evaporating the filtrate to dry- s, no residue should remain if the lead be pure, U.S.P.

Copper may be detected by precipitating the lead from a solution by huric acid, filtering, and super-saturating with ammonia. If copper be sent, the solution will exhibit a blue colour, U.S.P. Insoluble salts, as the de, may be dissolved in dilute nitric acid super-saturated with ammonia. e filtrate should show no blue colour.

ACTION.—Soluble lead-salts unite with **albumen**, and form uminate of lead. They have little or no irritating action en applied directly to the denuded **skin** or to a mucous mbrane. In the mouth they have an astringent action, but sweet instead of a corrosive taste. In large doses in the **mach** they may excite vomiting, and may produce symptoms irritant poisoning. In the **intestine** they act as powerful ringents. After absorption into the blood lead is carried by blood to all parts of the body, and there becomes deposited. appears to be eliminated very slowly, so that when even very nute quantities are taken continuously chronic lead-poisoning y be produced.

One of the most important **sources of lead-poisoning** of s sort is drinking water. Soft water attacks the leaden pipes which it may be conveyed, or the cisterns in which it may stored, and dissolves enough lead to cause lead-poisoning, small quantity of one grain per gallon appearing to be suffi- nt.

Hard waters are not injurious, as they cause a coating of osphate or sulphate of lead to form on the surface of the pipe cistern, and thus protect it from further attacks. Other urces of lead-poisoning are beer or cider which has stood in pipes leading to the tap, and snuff, from the decomposition the lead-foil which surrounds it. There are certain trades workers in which are very liable to lead-poisoning, such as our-grinding, painting, plumbing, type-founding and printing mpositors), or persons making stereotype plates. The chief urce of poisoning in these trades is the lead which adheres to hands and is swallowed along with the food, and the pre- utions to be adopted are cleanliness, washing the hands care- lly before taking meals, taking the food in a different room m that in which the work is carried on, changing the clothes en the work is over, and, if necessary, drinking water acidu- ed with sulphuric acid.

Treatment of chronic lead-poisoning consists in eliminating e poison, first from the tissues and then from the body. rious means have been employed, such as sulphur baths, the ternal administration of sulphur, frequent doses of castor oil. the lead is eliminated by the skin and mucous membrane, sul-

phur, applied either to the skin or taken internally, will conv
it into an insoluble sulphide and prevent its re-absorpti
Castor oil will remove from the intestinal canal the lead excre
into it. But the treatment which I employ, and which I f
very satisfactory, is to combine the use of iodide of potassi
with that of sulphate of magnesium, giving from five to ten gra
of the iodide three times a day, and a drachm of the sulph
also three times a day, with an interval of about two ho
between the medicines. The object of this treatment is (1)
dissolve the lead deposited in the tissues by means of the iod
(p. 561), and to cause its elimination by the mucus of the
mentary canal, and (2) to render the lead insoluble after it
passed into the intestine by means of the sulphate, and to
move it thence as quickly as possible.

The **symptoms of chronic lead-poisoning** are a blue l
on the gums, lead colic, lead cramps, and lead paralysis. T
blue line on the gums may appear when neither the co
cramps, nor paralysis are present. It appears to be produ
by sulphuretted hydrogen in the mouth precipitating the lead
black sulphide in the gums just at the margin of the teeth, a
this, shining through the tissue above it, appears of a blu
colour. It is absent when the teeth have been lost, and sligh
they are kept clean.

The **lead colic** may either be preceded by symptoms
digestive derangement, such as loss of appetite, or may app
at once. It is characterised by a tearing pain referred chie
to the region of the umbilicus, and generally accompanied
obstinate constipation. It is usually, though not alwa
relieved by pressure, but may sometimes be somewhat increa
by it.

Lead cramps are almost entirely confined to the flexor s
faces, specially marked in the calves of the legs, and are usua
worse at a change of weather. They may either accompany
succeed the colic.

Lead paralyses are usually confined to the extensor surfac
and more particularly affect the extensors of the wrist, so th
this form of paralysis is sometimes known as **wrist-drop.** T
affected muscles become atrophied, and, as the extensor tend
also act as ligaments of the wrist, the bones of the carpus m
become displaced. The paralysis probably depends on
affection of the spinal cord rather than of the muscles the
selves; for degeneration of the muscles does not occur until af
the paralysis has set in for some time, and the muscles
affected in physiological groups which act together, althou
supplied by different nerves. Thus the supinator longus, wh
is rather a flexor than a supinator, escapes in lead-poisoni
while the supinator brevis and extensor muscles in the forea
are paralysed. In peripheral paralysis of the musculo-spi

ve from cold or pressure the supinator longus is paralysed as as the others.[1]

Cerebral symptoms, consisting of headache, delirium, epiiform convulsions, or stupor and coma, have been described as urring in lead poisoning, and have been termed *encephalohia saturnina*. These have been ascribed to cerebritis caused the action of lead upon the brain, but it seems not impossible t they are really due to uræmia. If this be so they may be arded as the direct consequences of the action of lead which, causing the degeneration of the kidneys to be presently cribed, leads to imperfect elimination of tissue-waste.

Affections of the eye are sometimes associated with the ebral symptoms just mentioned, and are noticed in cases ere there is no kidney disease. Sudden onset of amblyopia hout organic changes may occur, but is then usually transient. e amblyopia consists in a general dimness of vision, or in a inution of the field of vision of one or both eyes. Optic ritis (papillitis) also occurs in some cases, and may proceed trophy.

Chronic lead-poisoning has a tendency to induce cirrhotic nges in the **kidneys** with albuminuria, the tubules becoming cked by plugs of lead-carbonate and atrophy ensuing.

Lead appears to cause contraction of the muscular walls of arteries, and to raise the arterial tension and to slow the rt. This action has been supposed to depend on a local ringent effect upon muscular fibre itself, but as in cases of onic poisoning the proportion of lead in the nervous system much greater than in muscular fibre, it is more probable that se effects are of nervous origin. The contraction of the estine which gives rise to the colic is probably due rather to action of the lead upon the nerves of the intestine than upon muscular coats.

Lead is **eliminated**, to a slight extent, in the urine, and bably largely by the mucus of the intestinal canal. It apars to check the elimination of uric acid, and, in London, gout urs very frequently among patients who work in lead.

Lead-salts may be administered in medicinal doses for a conerable time without bringing on any sign of lead-poisoning; Garrod has observed, and I can confirm the statement, that administration of medicinal doses of lead-salts will bring on t of gout in persons predisposed to it. Lead-poisoning appears ccur readily in gouty subjects.

Uses.—Lead lotions are sometimes applied externally to ains and bruises. They are useful in relieving the itching l the discomfort of pruritus, and in lessening the discharge of ema. As injections they may be applied in otorrhœa, vulvitis

[1] Duchenne's Works, selected by Poore, *New Syd. Soc.*

in children, gonorrhœa, and leucorrhœa. They are not used ulceration of the cornea, lest lead should be deposited in ulcer and leave a permanent opacity (p. 216). Internally, l is used for its local action on the stomach in pyrosis, and the intestine in diarrhœa and dysentery, and for its astring action on the vessels in hæmatemesis, hæmoptysis, and bleed from the kidneys and uterus. It has also been employed in pitation from hypertrophied heart, and in aortic aneurism.

Plumbi Oxidum, B. and U.S.P. Oxide of Lead. P 223.

Character.—In heavy scales of a pale brick-red colour.

Solubility and Reactions.—Completely soluble without effervescenc diluted nitric and acetic acids, either solution, when neutral, giving the actions of lead (p. 698). It should contain no copper.

Preparation.—By roasting lead in a current of air.

Preparations in which Oxide of Lead is Used.

Emplastrum Plumbi.	Liquor Plumbi Subacetatis.
„ **Saponis Fuscum.**	Plumbi Acetas.

Emplastrum Plumbi, B. and U.S.P. Lead Plaster.

Preparation.—By heating oxide of lead with olive oil and water. oleic acid of the oil combines with the lead, forming oleate of lead, and leav glycerine. This plaster is a lead soap.

Preparations.

B.P.	U.S.P.
Emplastrum Ferri.	Emplastrum Ammoniaci cum Hydrarg
„ Galbani.	„ Asafœtidæ.
„ Hydrargyri.	„ Ferri.
„ Resinæ.	„ Galbani.
„ Saponis.	„ Hydrargyri.
	„ Opii.
	„ Resinæ.
	„ Saponis.
	Unguentum Diachylon (1 in 4, nearly).
	And several other plasters into whic enters, as resin plaster.

Uses.—Lead plaster is used to hold together the edges wounds, to protect irritable surfaces, either alone or by keepi other dressings in contact with them by means of its adhes power. It is also used as a means of applying pressure.

Unguentum Diachylon (U.S.P.) is very useful in chro eczema, and in the acute form after severe inflammatory sy ptoms have subsided. It must be applied thickly spread on cloth, which is kept in place by a bandage. It is also useful hyperidrosis, especially of the feet, the treatment being c tinued, without washing, and with a daily change of dressing, ten to fourteen days. In sycosis, after shaving, the applicati of soft soap twice a day, and diachylon ointment in the interva has a very beneficial effect.

Plumbi Carbonas, B. and U.S.P. Carbonate of Lead. $(CO_3)_2Pb(HO)_2$; 773·5.

Characters.—A soft, heavy, white powder, blackened by phuretted hydrogen.

Solubility and Reactions.—Insoluble in water, soluble with effervesce in diluted acetic acid without leaving any residue, and forming a solu- which gives the reactions of lead.

Preparation.—By exposing lead to the fumes of vinegar and to CO_2.

Impurity.—Calcium.

Test.—The acetic solution when treated with excess of sulphuretted rogen, boiled and filtered, gives no precipitate with oxalate of ammonium.

Preparation.

B. and U.S.P.

Unguentum Plumbi Carbonatis.....1 part in 8, B.P.; 1 in 10, U.S.P.
With simple ointment, B.P.; with benzoated lard, U.S.P.

Uses.—Carbonate of lead is used as an application to exiated surfaces, piles, boils, and ulcers.

The ointment is used in the same way.

Plumbi Acetas, B. and U.S.P. Acetate of Lead. $(CH_3)_2(CO.OH)_2$. $3H_2O$; 378·5. Sugar of Lead.

Characters.—In white crystalline masses, slightly efflorest, having an acetous odour, and a sweet, astringent taste.

Solubility and Reactions.—Its solution in water slightly reddens nus, and gives the reactions of lead (p. 698) and of an acetate (p. 594).

Preparation.—By dissolving oxide of lead in acetic acid.

Impurity.—Slight amount of carbonate.

Test.—Its solution in distilled water is clear, or has only a slight milkis, which disappears on the addition of acetic acid.

Dose.—1 to 4 grains.

Preparations in which Acetate of Lead is Used.

B.P.	U.S.P.
rcerinum Plumbi Subacetatis.	
uor „ „ .....5 ounces to 1 pint.	Liquor Plumbi Subacetatis.

ula Plumbi cum Opio (*v.* p. 522), 3 parts in 4.
ppositoria Plumbi Composita...1 part in 5.
guentum Plumbi Acetatis.....1 part in 38.

Uses.—The acetate is the preparation of lead most frequently ed as a local application in inflammations, ulcers, ophthalmia, d gonorrhœa, or for its general actions on the system.

B.P. Pilula Plumbi cum Opio. Pill of Lead and Opium.

Dose.—3 to 5 grains.

Uses.—It is a powerful astringent, used either for the purpose obtaining the local astringent action of lead upon the bowels diarrhœa, or for its general effect upon the system, after abrption, as in hæmoptysis.

B.P. Suppositoria Plumbi Composita. Compound Lead Suppositories.
ch suppository contains 1 grain of opium and 3 grains of acetate of lead.

Uses.—Used in piles and dysentery accompanied by m tenesmus, or in phthisis, where we wish to stop hæmopt without putting lead or opium into the stomach and t running the risk of interfering with digestion.

B.P. Unguentum Plumbi Acetatis. Ointment of Acetate of Lea Acetate of lead (12 grains), benzoated lard (1 ounce).

Uses.—It is used as a sedative and astringent applicat to ulcers, excoriations, painful piles, irritable and itching sk diseases, erysipelas, burns, bruises, &c.

Liquor Plumbi Subacetatis, B. and U.S.P. Solution Subacetate of Lead.

Subacetate of lead, $Pb(C_2H_3O_2)_2.PbO$, dissolved in wa B.P. An aqueous liquid containing in solution about 24 cent. B.P., 25 per cent. U.S.P., of subacetate of lead.

Characters.—A dense clear colourless liquid, with alkal reaction and sweet astringent taste, becoming turbid by expos to the air and forming with mucilage of gum-arabic an opa white jelly.

Reactions.—It gives the reactions of lead and of an acetate.

Preparation.—By boiling acetate of lead, oxide of lead in powder, distilled water together.

Preparations.

B.P.	U.S.P.
Glycerinum Plumbi Subacetatis.	Ceratum Plumbi Subacetatis.
Liquor „ „ Dilutus.	Linimentum „ „ (v. p. 5
	Liquor „ „ Dilu

Uses.—It is recommended by Ringer as an application pityriasis and eczema, and in combination with one or two pa of glycerine to the milder forms of lupus after the crusts h been removed. Diluted, and mixed with liquor morphinæ acetat it is a useful application to hæmorrhoids.

B.P. Glycerinum Plumbi Subacetatis. Glycerine of Subacetate Lead.

Preparation.—By boiling acetate of lead, oxide of lead, glycerine and w together and evaporating off the water.

Preparation.

B.P. Unguentum Glycerini Plumbi Subacetatis. Glycerine of S acetate of lead 1, soft paraffin 4, hard paraffin $1\frac{1}{3}$ parts.

Liquor Plumbi Subacetatis Dilutus, B. and U.S.P. Diluted Solut of Subacetate of Lead.—Consists of 2 fl. dr. of solution of lead and 2 fl. dr rectified spirit diluted with water up to a pint, B.P. Solution of acetate of lea distilled water 97 parts, U.S.P.

Uses.—Used as a mild astringent and sedative to irrita and itching skin-diseases and superficial inflammation; as eye-wash unless ulceration of the cornea be present; as an inj tion in leucorrhœa and pruritus pudendi.

U.S.P. Ceratum Plumbi Subacetatis. Cerate of Subacetate of Lead.—S tion of subacetate of lead (20 parts), camphor cerate (80 parts), U.S.P.

Uses.—Chiefly as an application to chapped hands and ulce

U.S.P. Linimentum Plumbi Subacetatis. Liniment of Subacetate of Lead.—
e p. 517.

Uses.—To allay itching in chilblains and skin-diseases.

Plumbi Nitras, B. and U.S.P. Nitrate of Lead. $Pb(NO_3)_2$;
)·5.

Characters.—In colourless octahedral crystals which are
rly opaque, permanent in the air, of a sweetish astringent
te.

Solubility.—Soluble in water and alcohol.

Reactions.—The aqueous solution gives the reactions of lead (p. 698).
led to sulphate of indigo it discharges the colour.

Preparation.—By dissolving lead in nitric acid with the aid of heat and
tallising.

Preparation in which Nitrate of Lead is used.

Plumbi Iodidum.

Uses.—It is sometimes applied as a disinfectant, and occa-
nally to cracked hands or lips and fissured nipples, and in
rchia maligna. It has been given in order to check hæmor-
ge from the lungs.

Plumbi Iodidum, B. and U.S.P. Iodide of Lead. PbI
PbI_2; 459·7.

Characters.—A heavy, bright, citron-yellow powder, neutral,
h no taste or smell.

Solubility.—Sparingly soluble in water, readily soluble in chloride of
monium.

Reaction.—When strongly heated it first fuses and then is decomposed,
tting violet vapours of iodine, and leaving a citron-yellow residue.

Preparation.—By mixing solutions of nitrate of lead and potassium
ide.

Impurities.—Chromate, zinc, alkalis, and alkaline earths.

Tests.—On triturating 1 part of the salt with 2 parts of chloride of
monium in a porcelain mortar, and adding 2 parts of water, a colour-
liquid should result (absence of, and difference from, chromate). This
id, diluted with water, affords a white precipitate with diluted sulphuric
l, and a black one with hydrosulphuric acid. If all the lead has been
cipitated from a portion of the solution by the last-named reagent, the
rate should leave no residue on evaporation and gentle ignition (absence
inc, alkalis, or alkaline earths).

Preparations.

B.P. Emplastrum Plumbi Iodidi. Iodide of Lead Plaster, 1 part in 9
h soap and resin plaster).

Unguentum Plumbi Iodidi, B. and U.S.P. Ointment of Iodide of Lead;
n simple ointment, 1 part in 8, B.P.; with benzoated lard, 1 part in 10, U.S.P.

Uses.—It has been used externally as an application to ring-
rm, and as a counter-irritant in scrofulous enlargement of the
nds. It has been given internally in enlarged glands, and in
ronic enlargement of the spleen. In the latter case the iodine
y be supposed to have a beneficial effect upon the corpuscles
the spleen, and the lead to cause contraction by acting upon
e involuntary muscular fibre of the organ.

The ointment is used for enlarged glands.

TIN. Sn; 118.

B.P. Tin, granulated.

Grain tin, reduced to small fragments by fusing and pour into cold water.

USE.—Used formerly in powder as an anthelmintic in ½ ou doses.

Solution of Chloride of Tin. $SnCl_2$.

PREPARATION.—By dissolving granulated tin in dilute hydrochloric ac

USES.—It has a powerful affinity for oxygen and for chlori When added to trichloride of gold it gives a precipitate cal purple of Cassius whose composition is not known. It is u as a test for mercury. When added to calomel it abstra chlorine and precipitates metallic mercury. When added corrosive sublimate it precipitates calomel, which it afterwa reduces to mercury.

Salts of tin are not commonly used in practice, but have b given in nervous diseases in somewhat the same way as zinc.

Chloride of tin is a caustic of considerable power. poisoning by it the treatment would be to give milk and alkal carbonates.

CHAPTER XXVII.

METALS—(*continued*).

Class V.—PENTAD ELEMENTS.

NITROGEN, PHOSPHORUS, *Vanadium*, ARSENIC, *Niobium*, ANTIMONY, *Tantalum*, BISMUTH.

In the heading to this class I have substituted the word ments for metals, for nitrogen and phosphorus belong to it, hough they are non-metallic elements.

They form analogous compounds with oxygen and hydrogen.

		1	2	3	4	5	
Nitrogen.....	N	N_2O	N_2O_2	N_2O_3	N_2O_4	N_2O_5	NH_3
Phosphorus	P			P_2O_3		P_2O_5	PH_3
Vanadium	V	V_2O	V_2O_2	V_2O_3	V_2O_4	V_2O_5	
Arsenic	As			As_2O_3		As_2O_5	AsH_3
Antimony	Sb			Sb_2O_3		Sb_2O_5	SbH_3
Bismuth.....	Bi			Bi_2O_3		Bi_2O_5	

Nitrogen. N; 14. Non-officinal.

Nitrogen when free is chemically inactive, and does not adily unite with other elements. It is also physiologically in- tive, but has been used as an anæsthetic. The anæsthesia is e to asphyxia, from absence of oxygen; but as the carbonic id is constantly removed by the inhalation of nitrogen, the mptoms of irritation produced by it in ordinary asphyxia are sent.

Combined with **hydrogen**, as in ammonia and salts of mmonium, nitrogen stimulates and then paralyses nerve-centres, otor nerves and muscles (p. 144); and the action varies in the lts, for while the chloride affects the spinal cord, the iodide pa- lyses motor nerves and muscles. When nitrogen is combined ith **carbon**, the activity of the substance depends on whether e nitrogen is pentad or triad, as in $-N\equiv\equiv C$, and $-C\equiv\equiv N$, in the rst of which, with one free affinity belonging to the nitrogen, e compounds are very poisonous, while in the second, where e free affinity belongs to the carbon, the compounds are com- aratively harmless.

The 1st, 3rd, and 5th of its **oxygen** compounds in the above ble can take up the elements of water and of metallic oxides to rm salts.

Hydrogen Salt.		Metallic Salt, e.g. of Potassiu	
Hyponitrous acid	H_2ON_2O or HNO.	Potassium hyponitrite	K_2ON_2O or K
Nitrous acid	$H_2ON_2O_3$ or HNO_2.	,, nitrite	$K_2ON_2O_3$ or K
Nitric acid	$H_2ON_2O_5$ or HNO_3.	,, nitrate	$K_2ON_2O_5$ or K

The acid compounds of nitrogen with oxygen resemble th of phosphorus and arsenic in this, that the nitrites are c siderably more active than the nitrates, just as the phosphi and arsenites are more active than the phosphates and arsenia The action of nitrites on the organism was first investigated the case of nitrite of amyl, but by some unpublished experime made in Professor Ludwig's laboratory in 1869–70, I satisf myself of the correctness of Dr. B. W. Richardson's observatic that other nitrites, such as those of ethyl and sodium, had action on the blood-pressure similar in kind though less degree. In other experiments Dr. Gresswell and I found th the nitrites of propyl and butyl had also this action, and th all nitrites were muscular poisons.[2] Mr. Tait and I found th nitroglycerine had an action resembling the nitrites both its effect on blood-pressure and the change it caused in colour of the blood, but the headache it produced deterred from employing it in the treatment of patients.[3]

Nitrous Oxide. Nitrogen Monoxide. Laughing gas. N Not officinal.

Preparation.—By heating nitrate of ammonium.

Action.—When a mixture of nitrous oxide and air is inha it causes excitement, generally characterised by fits of involunta laughter, dancing, singing, and shouting, although it sometin appears to arouse pugnacity. When inhaled pure, it produc first of all, a feeling of increased circulation through the bo generally, accompanied by warmth and a little singing in t ears. If the inhalation be now stopped, the effect may pass o but occasionally, after a few breaths of pure air have be taken, the same excitement may ensue which is usually produc by the inhalation of mixed air and gas. On one occasion, havi inhaled pure gas for a short time, I felt a little warmth of t skin and a humming in the head, and, thinking it was time desist, laid down the mask of the inhaler. After a few breat of fresh air, I noticed that on attempting to speak, the spee was slow and hesitating. An electric shock then seemed shoot through the spine, and I was seized with an uncontrolla desire to laugh, jump, and throw the arms about, while the p ceptive faculties appeared quite unaffected. Although unable control my movements, I was perfectly conscious of their lu crous nature, and was astonished that two men who were sitti by, and who afterwards informed me that they thought the wh

[1] B. W. Richardson, *Brit. and For. Med. Chir. Rev.*, July, 1867.
[2] *St. Bartholomew's Hospital Reports*, 1876, p. 143. [3] *Ibid.* p. 14

ng a bad joke, were able to preserve their gravity. After ting for one or two minutes, the effect of the gas suddenly d completely passed off.

When inhalation is continued for a longer time, the feelings warmth and buzzing in the ears are succeeded by gradually reasing dimness of perception; sight, sounds, and tactile im-ssions become much dimmer than usual: and then the per-n becomes unconscious. At this time the face usually assumes ivid aspect, and during the period of insensibility small opera-ns may be performed without the patient being the least aware them. When the administration of the gas is stopped, re-very quickly and completely occurs, often passing off without ving any after-effects, though occasionally more or less head-e is experienced for some hours. No stage of exhilaration h as that which has already been described as occurring after administration of a small quantity of nitrous oxide is noticed ring recovery from complete narcosis.

Nitrous oxide appears to act as an anæsthetic chiefly by de-ving the nerve-centres of oxygen. As the inhalation of pure rogen has a similar anæsthetic power, the exhilarating effect small doses of nitrous oxide seems to show besides that it has pecial relation to the nerve-centres.

Uses.—It is useful as an anæsthetic for extraction of teeth, lsion of the toe-nail, and other minor operations. The in-se venosity of the blood which occurs during its use renders unsuitable for continued administration, and therefore in-missible in the case of lengthy operations. It is sometimes d to commence anæsthesia, ether being given after the patient nconscious.

Mode of Administration.—The most convenient mode of ministering it is to have it condensed in a large iron bottle, m which the gas may be readily conveyed to the patient by ans of a flexible tube attached to a mask. The mask ought be provided with a margin of inflated india-rubber, so that it l fit perfectly tight to the face, and thus prevent the escape gas. After the operation it is well to make the patient form some act, such as taking hold of the glass of water after tooth has been extracted, in order to hasten the return of nsciousness.

PHOSPHORUS. P; 31. B. and U.S.P.

A non-metallic element obtained from bones.

Characters.—A semi-transparent, yellowish, waxy-looking id. When exposed to air it emits white fumes which are minous in the dark and have a garlicky odour.

Preparation.—By treating bones with sulphuric acid, when sulphate of cium is precipitated and acid phosphate of calcium remains in solution.

This is evaporated and distilled with charcoal, which removes the oxyg
The phosphorus distils over and is condensed under water.

Officinal Preparations.

B.P.	DOSE
Pilula Phosphori ($\frac{1}{30}$ gr. in 3 grs.) (p. 522)	2–4 p
Oleum Phosphoratum (phosphorus in almond oil, about 1 per cent.)	1–10

U.S.P.	
Pilulæ Phosphori ($\frac{1}{100}$ gr. in each) (p. 523)	1–5 pi
Oleum Phosphoratum (with stronger ether and almond oil 1 per cent.)	1–5

Action of Phosphorus.—Living protoplasm has the power oxidising all the members of this group, and also of reducing t products of their oxidation (Binz). It is probable that this acti goes on more easily with phosphorus than with nitrogen. Her if phosphorus replaces nitrogen in a living cell it will quick metabolism. It is absorbed unchanged into the blood, and excreted by the kidneys either as phosphorus or phosphoric ac In **small doses** it appears to cause development of the fibro tissue in the **liver**, and in doses too small to affect the liver stomach it acts upon the osseous tissues. Its action upon t **bones** is somewhat peculiar, and has been fully investigated Wegner. When phosphorus is given to growing animals t bone as it develops is denser than usual, the cancellous tiss being like the denser tissue in the long bones. Cancellous tiss formed before the administration of phosphorus remains u changed. If the administration be still continued, the cancell tissue formed previously to the use of the drug is absorbed, a serves to form the cavity of the bone, and after a while t normal cancellated tissue at the end of the epiphysis is a replaced by solid bone. Afterwards even the dense bone th formed becomes absorbed, and forms the cavity of the long bo In adult animals phosphorus also causes the bones to beco denser, and this is especially noticeable in chickens, in which t cavity of the bone may be completely filled up, so that long bo form a solid rod instead of a tube. The influence of phospho upon osseous tissues is not due to excess of phosphates produc by it in the blood, but to stimulation of tissue-growth itself the phosphorus, for Wegner found that in animals fed w phosphorus but almost entirely deprived of phosphates, the sa dense, bony substance was formed, except that instead of t bone being hard, it was like that which occurs in rickets. men and women exposed to the fumes of phosphorus, e.g. th employed in the manufacture of lucifer-matches, caries of t **lower jaw** is a frequent occurrence. This is not due to t action of the phosphorus after absorption into the circulati but to the direct effect of the fumes upon the bone itself. F it has been found that when a bone of an animal fed by ph phorus was exposed, no carious change took place; but if c were exposed to the fumes, caries was produced, and amon

Lucifer-match makers it has been noticed that only those who have carious teeth suffer from necrosis of the jaw. When doses larger than those which induce induration of the bones are given, the phosphorus appears to act upon the **connective tissue** of the stomach and **liver**, causing chronic inflammation of these organs, and atrophy of the secreting cells, so that cirrhosis of the liver appears. In **poisonous doses** phosphorus first produces the symptoms of gastro-enteritis, with a garlicky taste in the mouth, the vomited matters having a similar odour, containing bile, and, but rarely, blood. They sometimes shine in the dark. At the end of twenty-four to thirty-six hours, the symptoms of gastro-intestinal irritation cease, and the patient is apparently well with the exception of vague pains in the limbs and loins. During this period, however, fatty degeneration of the liver, stomach, and **kidneys** is going on, and the effect of the changes in these organs soon manifests itself. Sometimes, after two or three days, the patient may die suddenly, without exhibiting any fresh symptoms, but usually, on the second or third day, jaundice appears, while the urine contains bile, and often albumen, leucin, and tyrosin. There is occasionally vomiting and purging, head-ache, sleeplessness, delirium, and coma, and death with or without convulsions. In some cases, when the poisoning runs a less acute course, the effect of fatty degeneration of the **vessels** is most prominent, discharges of blood occurring from the stomach, intestines, nose, lungs, bladder, uterus, and ears, and ecchymoses appearing on the surface. Increasing anæmia and debility finally kill the patient.

The **treatment** in cases of poisoning by phosphorus is to wash out the stomach freely by means of the stomach-pump, or to employ it by an emetic of sulphate of copper, and to give oxidised oil of turpentine in 40-minim doses in mucilage every fifteen minutes for an hour. Fats and oils should be withheld, as they dissolve any phosphorus which may be present in the stomach, and assist its absorption.

The **fatty degeneration** produced by phosphorus appears to depend on a more rapid splitting up of albuminous tissues, along with deficient oxidation. This was shown by Voit and Bauer, who produced fatty degeneration of the organs by the administration of phosphorus in dogs absolutely deprived of food, where the fat found after death could neither have come from food nor from fat deposited in other parts of the body, as this had all been absorbed before the administration of the drug had been commenced. It must therefore have been formed *in situ* from the decomposition of albuminous substances, and these were shown to have split up more quickly than usual by the amount of urea in the urine being increased by the phosphorus, while oxidation in the body was shown to have diminished by the amount of oxygen absorbed and carbonic acid given off being lessened. In

man, the products of albuminous waste are often not conver into urea, but appear in the urine as leucin and tyrosin.

The action of **compounds** containing phosphorus appear depend considerably on the more or less complete saturatio its affinities, and the readiness with which the phospho may attach itself to the organic constituents of the tissues. Th phosphoric acid, in which the affinities of the phosphorus fully saturated by oxygen, appears simply to act as an acid wi out exerting any specific action, and when combined with sodiu its effects are simply those of a neutral alkaline salt.

Metaphosphoric and pyrophosphoric acids appear to hav specific poisonous action more nearly resembling that of ph phorus. Pyrophosphate of sodium paralyses the nerve-cent in the spinal cord and medulla oblongata, producing drowsin loss of reflex action, paralysis, and death, which is sometim preceded by convulsions. It lowers the blood-pressure mammals, slows the beats of the frog's heart, renders th powerful and finally arrests them in systole. When death d not occur rapidly, marked fatty degeneration of the heart a kidneys is found, and a similar change takes place, though a less extent, in the liver. Although it acts as a poison wh injected subcutaneously or into the circulation, pyrophosph of sodium has no poisonous action when taken into the intesti canal.

Metaphosphate of sodium has a similar but less power action.

USES.—Phosphorus forms an important constituent of n vous tissue, and has been employed in cases of nervous debil neuralgia, wakefulness, paralysis, locomotor ataxia, and im tence. In some cases of leucocythæmia it is useful. It has b used in osteomalacia, and instead of arsenic in skin-disea (*vide* also p. 719). Even in small doses it may cause naus with unpleasant eructations. It is well, therefore, to comme with a very small dose, such as $\frac{1}{100}$ of a grain.

ARSENIUM (ARSENIC). As; 75.

Metallic arsenic is not used in medicine. It is steel-colou crystalline, and brittle, and when heated gives off garlicky fum Very light (sp. gr. 5·8), very volatile. It forms two classes salts. In one—the arsenious salts—it is tri-, in the other— senic salts—pent-atomic. Arsenious oxide, As_2O_3, usually ca arsenious acid, forms arsenites. Arsenic oxide, As_2O_5, or arse acid, forms arsenates, or, as they are termed in the B. and U.S. arseniates.

GENERAL SOURCES OF ARSENIC.—It occurs in many ores combined v metals, oxygen, and sulphur. Its presence as a frequent impurity in sulp

s already been mentioned (p. 543). It is chiefly obtained by roasting the senides of iron, nickel, and cobalt, and condensing the arsenious oxide in a ng, nearly horizontal, chimney.

General Tests for Arsenious Acid.—With hydrosulphuric acid it gives yellow precipitate, which is brightest in acid solutions. Silver nitrate gives anary-yellow and copper sulphate a brilliant green precipitate (Scheele's een). These are very soluble in acid, and neither of them is thrown down m simple aqueous solutions of arsenious acid (a little acid being freed in e reaction); a little alkali must be present. Both are very soluble in excess ammonia, so that to avoid adding excess ammonio-nitrate of silver and mmonio-sulphate of copper are used as reagents, in preference to adding mmonia, along with simple solutions of nitrate of silver or of sulphate of pper. Arseniates throw down a brick-red precipitate with ammonio-nitrate silver, and are thus distinguished from arsenites.

General Reactions of Arsenic, Antimony, and Bismuth.

	Arsenic	Antimony	Bismuth
ydrosulphuric acid	Yellow precipitate (soluble in ammonium sulphide and re-precipitated by acids).	Orange or brick-red precipitate (soluble in ammonium sulphide, and precipitated by acids).	Black precipitate (insoluble in ammonium sulphide).
Water		Strong solution thrown into much water gives a white precipitate, which becomes **orange** on the addition of hydrosulphuric acid.	Strong solution thrown into water gives a white precipitate, which becomes **black** on the addition of hydrogen sulphide.

General Action of Arsenic.—Although arsenic, like antiony, has no great affinity for albumen, and does not produce ith it a coagulum, yet when applied to the **skin** denuded of its idermis, it acts as a caustic and produces a slough. If used a dilute form, and over a large surface, it may be absorbed, nd may produce the general effects of the drug upon the system. hen applied in a concentrated form it appears to produce a ough more rapidly, and the dead tissue forms a barrier to its rther absorption. In the **mouth** it has a somewhat sweetish ste, and in small doses excites in the **stomach** a feeling of ppetite. In larger doses it produces irritation, colicky pains, iarrhœa, and mucous evacuations, sometimes tinged with blood. n still larger doses it causes symptoms of gastro-enteritis, vomitng, and purging, the stools being finally of a rice-watery appearnce, closely resembling those of Asiatic cholera. These are also ccasionally accompanied by collapse, with pale, pinched, and mewhat livid surface, and violent cramps of the extremities, o that cases of arsenical poisoning may be readily mistaken for holera, and *vice versâ*. There is sometimes strangury, priapism, uppression of urine or bloody urine; the consciousness is etained to the last. In some cases there are no symptoms at ll of gastro-intestinal irritation, the **nervous system** being

affected, and the patient presents the symptoms of coma, v
much resembling those of opium-poisoning.

The **treatment** in cases of arsenical poisoning is to wash
the stomach freely by means of the stomach-pump, and
copious administration of diluents, taking care to ensure th
evacuation by the subsequent speedy administration of s
emetics as mustard or sulphate of zinc if they are not at o
rejected by the vomiting caused by the arsenic itself. Fresh
prepared peroxide of iron may be administered in doses o
tablespoonful every ten minutes, and alcohol has been gi
when the moist peroxide could not be obtained. Demulce
should afterwards be given to allay the irritation.

Chronic poisoning by arsenic may occur from the inhalat
of arsenical vapour or dust, arising from wall-papers, dresses
other substances containing arsenic. The proportion of arse
necessary to produce poisoning when taken into the lungs
this way appears to be very small. The symptoms are at f
increased appetite, then colicky pains and mucous or dysent
stools, with great prostration, irritation of the eyes, running
the nose, a short cough, which is dry or accompanied by sli
expectoration, and a white silvery appearance of the tong
These symptoms may sometimes continue for months, or e
years, without the cause being suspected, until the recovery wh
ensues upon the removal of the offending wall-paper gives
clue to their cause.


When taken internally for a length of time a condition
tolerance may be induced in the case of arsenic, as well as in t
of antimony. This is seen in the arsenic-eaters of Styria, w
beginning with small quantities, are gradually capable of tak
larger and larger doses, until they can swallow at once, with saf
as much as five grains. In taking such doses as these they
careful not to take water with the arsenic, so that it is proba
slowly absorbed from the stomach, and is, very possibly, rapi
evacuated. Dr. Craig Maclagan watched a noted arsenic-ea
swallow his dose, and obtained from the urine which he af
wards passed a considerable quantity of the poison. By us
the arsenic in this way, these people are said to undergo m
greater exertion than usual without exhaustion, and to be abl
ascend the steep Styrian hills without being affected with brea
lessness. Some, no doubt, die in the attempt to acquire the ha
but those who have once become accustomed to the d
appear to continue its use without deriving any harm f
it, and, moreover, seem sturdy and vigorous, and live to an
age.

After absorption into the blood, arsenic appears to some ex
to modify **tissue-change**. When a solution of arsenious aci
added to **blood** outside the body, it retards coagulation, preve
putrefaction, and conserves the form of the red blood-corpusc

very dilute arsenical solution also conserves the irritability of e excised nerve and muscle of the frog.

Considerable doses of arsenic given for a length of time pro-ce fatty degeneration of the liver and other organs, and cause e **glycogen** to disappear from the liver, so that puncture of the urth ventricle no longer produces glycosuria.

Minute doses of arsenic appear to increase the rapidity of the lse. Larger doses diminish the pulse and blood-pressure. In gs the heart is slowed, and finally stands still in diastole. This ppage of the **heart** appears to be due to paralysis of the motor nglia, as the muscular substance will still continue to contract on direct irritation. In warm-blooded animals it appears to olong the irritability of the heart, so that it will still continue beat for many hours after the death of the animal. According Küntzer, this is due to retardation of the vital processes in the ammalian heart, so that it comes to resemble that of a cold-ooded animal. In animals, arsenic has been found to diminish e **blood-pressure** from the beginning. This appears to be due rtly to diminished activity of the heart, but chiefly to para-sis of the splanchnics allowing the abdominal vessels to dilate . 284). In frogs it produces apparent paralysis, but this appears



. 169.—Vertical section of the healthy epi-dermis of a frog. *a*, Columnar layer of cells. , Malpighian layer. *c*, Intermediate layer. , Corneous layer. *f*, Sheet of connective tissue forming boundary between dermis and epi-dermis. (After Nunn.)




FIG. 170.—Vertical section of epidermis from a frog poisoned by arsenic. *b*, vacuole in the softened protoplasm of the columnar layer of cells. At *a* the protoplasm is more softened and the vacuoles enlarged so that the cells are attached to the dermis only by threads of protoplasm. (After Nunn.)

ther due to diminished sensibility of the grey matter in the pos-rior cornua of the spinal cord than to real paralysis; for the erves and muscles in this state are found to be still quite irrit-ble, and although the animal is insensible to pinching it can and oes move when laid on its back. As, according to Schiff, the uscular sensations are conveyed in the white substance of the osterior columns, this would appear to be unaffected, while the rey substance which conveys sensations of pain is completely aralysed (p. 160).

In some cases of poisoning by arsenic, **paralysis** of one or nore limbs occurs after the acute symptoms have passed off. It sually affects the extensors more than the flexors, and is gene-ally temporary, though it may be permanent.

The action of arsenic on the **skin** is peculiar. Ringer Murrell noticed that in frogs poisoned by it the cuticle could stripped off the whole body with the greatest readiness withi few hours after its administration. This condition was found Nunn to depend upon softening of the protoplasm of the col nar layer of cells in the epidermis, so that the cuticle rema attached to the dermis only by a few protoplasmic threads (F 169 and 170).

Other epithelial structures are also affected, and Cornil found fatty degeneration of the epithelium lining the alveo the **lungs** in animals poisoned by arsenic (Fig. 171).

Arsenic is **eliminated** chiefly by the urine, and to a less tent by the bile, and slightly by the skin. Its elimination by urine is very rapid.

Uses.—Arsenic has been used externally as a **caustic** ap cation to cancers, and forms the basis of most of the secret 'cu




Fig. 171.—Section of lung, hardened in osmic acid, from guinea-pig poisoned by arsenious The capillaries, *v*, project into the cavities of the alveoli, and are full of red blood-corpu The protoplasm, *a*, of the cells is filled with fatty granules. The nuclei are well pres (After Cornil.)

for this disease. The old recipe for this purpose consists of following ingredients: Arsenious acid, 2 drachms; cinnab 2 drachms; ashes of old leather, 8 grains; dragon's blo 12 grains, made into a paste with water or saliva.

In applying a paste of this sort it is advisable that it sho consist of at least one-fifth of arsenic, and that it should not applied to too large an extent of surface at a time. The arsen paste used by Hebra consisted of arsenious acid 1 gramme, c nabar 3 grains, and emollient ointment 24 grains.

Internally, arsenic is used for its local action on the intesti canal as a **tonic** and **astringent**, for its action on tissue-char and as a tonic and **anti-spasmodic** in cases of nervous disea In the stomach, small doses stimulate the appetite, and are use in allaying pain and checking vomiting. It may be given irritative dyspepsia, in gastralgia, heartburn, in the vomiting drunkards, and in gastric ulcer or cancer. It is also recommen by Ringer in cases of regurgitation of food unaccompanied nausea. It is very useful in cases of diarrhœa where the t

ncy comes on during or immediately after the ingestion of food, ether in adults or children; it is then best given in small doses fore meals (p. 387).

Arsenic is a powerful **antiperiodic**, nearly rivalling quinine; it ems less serviceable than quinine in well-marked cases of ague, t is sometimes as good, or even better, than it in the irregular alarious manifestations such as headache, neuralgia, &c., which e known under the head of masked malaria. It is sometimes eful in chronic rheumatism and rheumatic gout, and in neuralgia various sorts its effects are occasionally almost magical.

It has been used, not only in tic and hemicrania, but in asmodic nervous diseases such as angina pectoris, chorea, and ilepsy, whooping-cough and asthma. It is often very service- le in hay fever, and in cases of spasmodic sneezing coming on er exposure to dust or even without any apparent cause. It s been employed in chronic bronchitis with copious expectora- n, and in ordinary catarrh without febrile disturbance. It ap- ars to be very useful in the commencement of phthisis. Under influence the author has seen consolidation of the lung, con- quent on catarrhal pneumonia, clear up completely, even in a bject having a very bad family history.

Probable mode of action of Arsenic in Phthisis.

The treatment of phthisis is so important that it may be ad- sable to discuss in a few words the probable mode of action of senic and hypophosphites in its early stages. It is now probable at this disease depends on the presence of a **bacillus** (*B. tuber- losis*, p. 83). In order that it should grow within the body, wever, it is necessary that a suitable **nidus** should be present, d the different susceptibility to the disease of different indi- duals, or of the same individual at different times, probably pends on their liability to present a suitable nidus. The cillus *tuberculosis* differs from such bacilli as the *B. anthracis* being of a very slow growth, so that when it is cultivated tificially on a solid medium it takes about ten days before it cceeds in establishing itself and begins to grow. Consequently, nen applied to an open wound, or when inhaled into the lungs a healthy person, it does not, like the *Bacillus anthracis*, at ce begin to multiply and produce disease in the organism, but is usually removed by washing in the case of a wound, or by pectoration in healthy persons. But if its removal be inter- red with it will produce disease. Thus, if instead of being plied to an open wound it be injected under the skin so that cannot be removed by washing, it will after a time begin to ow, and produce tuberculosis, first local and then general. It probable that the case is similar in the lungs. In the healthy ng it finds no nidus, and is removed by expectoration, but if a

portion of the lung be consolidated by catarrhal pneumonia, consolidated part probably affords a nidus to the bacillus, the longer the consolidation lasts the greater the risk of ba finding entrance. In croupous pneumonia the exudation the alveoli, consisting chiefly of fibrin with a few leucocy quickly breaks up and is absorbed, so that it is comparati rarely followed by phthisis. But the proliferated epithelial which fill the alveoli of the lung in catarrhal pneumonia much more resistant; they break down and are absorbed m more slowly, and hence a much longer time is given du which bacilli may find a nidus. The marked hereditary na of phthisis is a curious point in a disease which we suppos depend on the presence of a bacillus, and is a character in w it differs from such diseases as anthrax, ague, or relapsing fe which are also due to foreign organisms. But the differ probably depends on the slow growth of the tubercle baci which renders a prolonged undisturbed rest at the point w it enters the body necessary for its further growth. **disease is not** hereditary, **but the predisposition** to such mo changes in the lungs as affords a nidus to the bacilli **is h ditary.**

The more rapidly the effused products in pneumonia ca removed from the lung, the less chance have the bacilli of fin a nidus. It is probable that arsenic, which causes fatty deg ration of the normal epithelial cells lining the alveoli, also ca a similar degeneration of such cells when filling the alv cavities. By thus breaking them up and quickening thei sorption, arsenic will lessen the risk of bacilli finding a m in them and converting catarrhal consolidation into phth Probably the hypophosphites act in a similar way. If patient should be in places where there are no tubercle ba the consolidation may persist for a long time without pht occurring, and hence one advantage of sea-voyages in cas recent consolidation.

Mode of Administration.—In those cases where the action of arsenic on the stomach and intestine is desired, best to give it in small doses before meals, but where the a of the drug on other organs of the body is desired, it shou administered immediately after meals.

The symptoms which show that arsenic is beginning to duce its physiological effect, and that it is time to diminis dose or cease its administration, are irritation of the eyes, a pricking sensation in them, the conjunctivæ being some injected, and the patient showing a tendency to rub the e or the digestive canal may be the first to show the effect of drug, the tongue being covered with a thin white silvery fu red, with enlarged fungiform papillæ; the appetite may fail, colicky pains with a tendency to diarrhœa may appear befor

es are affected. Either of these symptoms indicates that the ug should be discontinued, or the dose diminished.

In skin diseases arsenic is used more frequently than any ner internal remedy. As it increases metabolism in the cells the epidermis (p. 716) it is contraindicated in acute cases, or en there is any active cutaneous inflammation in a chronic se. It is sometimes useful in chronic eczema when associated th chlorosis, and in lupus, chronic urticaria, and the neuralgia llowing herpes zoster. According to Mr. Hutchinson it cures mphigus. The skin-diseases, however, in which arsenic is most eful are psoriasis and lichen ruber; beginning with two minims Fowler's solution three times daily, the dose should be adually increased to 12 minims or even 30 minims daily, and should be given until either the amendment begins, or the ns of conjunctivitis or gastric irritation appear. When these e noticed, the dose should be diminished until they become st perceptible, and the administration of the drug should be ntinued for some time after the eruption has disappeared, in der to prevent its recurrence.

Acidum Arseniosum, B. and U.S.P. ARSENIOUS ACID. As_2O_3; 197·8.

An anhydride (not a true acid), obtained by roasting arsenical es, and purified by sublimation.

CHARACTERS.—Occurs in sublimed masses which usually esent a stratified appearance caused by the existence of separate layers differing from each other in degrees of opacity, or as heavy white powder. When slowly sublimed in a glass tube it rms minute brilliant and transparent octahedral crystals.

SOLUBILITY.—It is sparingly soluble in water.

REACTIONS.—Its solution gives with ammonio-nitrate of silver a canary-llow precipitate insoluble in water, but readily dissolved by ammonia and nitric acid. Sprinkled on a red-hot coal it emits a garlicky odour.

IMPURITIES.—Gypsum and chalk.

TEST.—It is entirely volatilised at a temperature not exceeding 400° F. ur grains of it dissolved in boiling water with eight grains of bicarbonate sodium discharge the colour of 808 grain-measures of the volumetric lution of iodine. $As_2O_3 + 2H_2O + 4I = As_2O_5 + 4HI$.

DOSE.—$\frac{1}{60}$ to $\frac{1}{12}$ of a grain, in solution. It may also be ven in the so-called 'Asiatic pills,' which are used in some arts of the Continent. These consist of arsenious acid, 0·75 grm., owdered black pepper, 6 grm., gum arabic, 1·5 grm., powdered arsh-mallow root, 2 grammes, to make 100 pills, of which three re to be taken daily.

PREPARATIONS OF ARSENIOUS ACID.

B.P.	DOSE.
Liquor Arsenicalis	2–8 min.
„ **Arsenici Hydrochloricus**	2–8 min.
U.S.P.	
Liquor Potassii Arsenitis	2–8 min.
Liquor Acidi Arseniosi	5 min.

PREPARATIONS OF ARSENIC ACID.

B. AND U.S.P.

Ferri Arsenias. Sodii Arsenias. Liquor Sodii Arseniatis.

Liquor Arsenicalis, B.P.; Liquor Potassii Arsenitis, U.S.P. ARSEN SOLUTION, B.P.; SOLUTION OF ARSENITE OF POTASSIUM, U.S.P. FOWLER'S S TION.—Is a mixed solution of arsenite and carbonate of potassium flavoured compound tincture of lavender. Contains 1 part arsenious acid in 100 of w or about 4½ grains in 1 fl. oz., B. and U.S.P. In the B.P. 1867, it contained 4 in 1 fl. oz., or 1 in 109.

CHARACTERS.—A reddish liquid, alkaline to test-paper, and having the o of lavender.

REACTION.—After being acidulated with hydrochloric acid, it gives, with sul retted hydrogen, a yellow precipitate, which is brightest when the arsenical s tion has been previously diluted.

DOSE.—2 to 8 minims.

USE.—This is the preparation of arsenic most commo employed. It may be given along with alkalis.

Liquor Arsenici Hydrochloricus, B.P.; Liquor Acidi Arseni U.S.P. HYDROCHLORIC SOLUTION OF ARSENIC, B.P.; SOLUTION OF ARSENIOUS A U.S.P.—A solution of arsenious acid, 87 grs. with 2 fl. dr. of hydrochloric aci 20 fl. oz. of water, B.P.; 1 part arsenious acid and 2 of hydrochloric in 10 water, U.S.P. It is a 1 per cent. solution in both Pharmacopœias.

CHARACTERS AND REACTION.—A colourless liquid, having an acid reaction. phuretted hydrogen gives at once a bright yellow precipitate.

DOSE.—2 to 8 minims.

USE.—Some think it milder than the ordinary liquor. Gar thinks not. It can be given along with perchloride of iron solution, or with acids.

Sodii Arsenias, B. and U.S.P. ARSENIATE OF SODI $Na_2HAsO_4.7H_2O$; 311·9.

CHARACTERS.—In colourless transparent prisms.

PREPARATION.—By fusing arsenious acid with nitrate and carbonate sodium. The As_2O_3 is oxidised by the nitrate to As_2O_5, which combi with the sodium to form arseniate.

SOLUBILITY.—It is soluble in water.

REACTIONS.—The solution in water is alkaline, giving white precipit with chloride of barium, chloride of calcium, and sulphate of zinc, a brick-red precipitate with nitrate of silver (arseniate), all of which are sol in nitric acid.

DOSE.—$\frac{1}{16}$ to $\frac{1}{8}$ gr.; of the dried salt, $\frac{1}{24}$ to $\frac{1}{12}$ gr.

PREPARATIONS.

B. and U.S.P.

Liquor Sodii Arseniatis. 4½ grains dried in 1 fl. oz. of water, or 1 in B. and U.S.P.

DOSE.—5 to 10 minims.

ACTION.—It acts like other preparations of arsenic, but d not irritate the stomach so much, and may be given in lar doses. In frogs it produces, like arsenious acid, paralysis of

ain and spinal cord, but is much less powerful (Ringer and urrell).

USES.—It may be used in the same diseases as arsenious id. It is perhaps one of the best remedies for neuralgia hich we have.

Arsenii Iodidum, B. and U.S.P. IODIDE OF ARSENIUM, B.P.; ARSENIC, U.S.P. AsI_3; 454·7.

CHARACTERS.—Small orange-coloured crystals.

SOLUBILITY.—Readily and almost entirely soluble in water and in rectified irit.

REACTIONS.—Its aqueous solution has a neutral reaction, and gives a llow precipitate with sulphuretted hydrogen. Heated in a test-tube it most entirely volatilises, violet vapours of iodine being set free.

PREPARATION.—By the direct combination of iodine and metallic arsenic, by evaporating to dryness an aqueous mixture of arsenious and hydriodic ids.

DOSE.—$\frac{1}{30}$ gr.

USE.—In skin diseases.

Liquor Arsenii et Hydrargyri Iodidi, B. and U.S.P. OLUTION OF IODIDE OF ARSENIC AND MERCURY. DONOVAN'S OLUTION.[1] Iodide of arsenium, AsI_3, and red iodide of mercury, HgI_2, of each 45 grains (1 per cent. of each by weight), water up 10 fl. oz., B.P. Iodide of arsenic, 1; red iodide of mercury, 1; ater up to 100, U.S.P.

CHARACTERS.—A pale yellow liquid, with a metallic taste.

INCOMPATIBLES.—Solutions of opium or morphine.

DOSE.—5 to 30 minims (0·3–1·8 c.c.).

USES.—In skin diseases, syphilis, rheumatism, and nocturnal ains.

ANTIMONY. Sb; 122.

Antimony forms two classes of salts, antimonious and anti- nonic. In the former it is tri- and in the latter pent-atomic.

GENERAL SOURCES.—It is chiefly found native in the form of ne black antimonious sulphide, Sb_2S_3.

GENERAL REACTIONS.—It is recognised by the orange-coloured recipitate which it gives with sulphuretted hydrogen in acid olutions. A characteristic reaction is the white precipitate hich falls on throwing a strong solution of a salt of antimony, uch as the chloride, into water, and the change of the white nto an orange colour on the addition of sulphuretted hydrogen. A similar reaction occurs with salts of bismuth, but the white precipitate becomes black on the addition of sulphuretted ydrogen (p. 713).

A solution of chloride of antimony gives with potash or soda

[1] It contained 1 in 109 in B.P. 1867. The original Donovan's Solution con- ained nearly 42 grains of each iodide in 10 fluid ounces.

a white precipitate which only dissolves in large excess, a with ammonia a white precipitate insoluble in excess. Bu tartaric acid be present the precipitate dissolves in a slight cess of potash or soda, and with ammonia only a slight precipit is formed.

General Actions of Antimony.—Salts of antimony proba combine with **albumen**, but in alkaline solutions they form precipitate. They only form precipitates in acid solutions, a they consequently appear to exert an irritant action only those parts of the animal body where they meet with an acid se tion, such as the orifices of the sweat-glands and of the stoma When applied to the **skin** the chloride of antimony destr the cuticle, and acts as a powerful escharotic, producing a d slough and a slowly healing sore.

The other preparations, however, instead of affecting whole surface to which they are applied, produce inflammat in isolated spots, which, beginning with papules, proceeds pustules resembling those of small-pox. A similar pustular i tation is sometimes noticed upon the fauces of persons who h been taking antimony for some time, or have been poisoned it. When taken **internally, small doses** produce little m than a feeling of warmth in the stomach and slightly increa diaphoresis, but larger doses cause loss of appetite, nau accompanied by enfeeblement of the circulation, and a fee of great depression and weakness. Not only the secretion sweat, but those of the mucous membranes, stomach, intest and respiratory passages, seem at the same time to be consic ably increased. In still **larger doses** antimony produces vor ing, with great depression of the circulation, and relaxation b of the voluntary and involuntary muscles. In large and **pois ous doses** it causes gastro-enteritis, with profuse diarrhœa extreme collapse. The pulse is small and quick, the sur cold, and covered with clammy perspiration. There is g weakness and severe cramps of the extremities, and the sy toms somewhat resemble those of Asiatic cholera. **Death** i occur in this condition. It is sometimes preceded by deliri and convulsions, and tonic or clonic convulsive spasms.

The **treatment** of antimonial poisoning consists in the ministration of tannin, and in some readily accessible form. most easily obtained is a strong infusion of tea, and the tan is more readily extracted from this by the addition of a sr quantity of bicarbonate of sodium. Infusions of oak bark o cinchona may also be used if obtainable. Milk and mucilagi drinks may also be used. A diffusible stimulant should be gi to counteract the collapse.

The mode in which tartar emetic causes **vomiting** has gi rise to considerable dispute. It acts as an emetic even when jected into the veins, as well as when given by the stomach,

was found by Magendie that when the stomach of an animal as excised, and a pig's bladder filled with liquid attached to the wer end of the œsophagus, the injection of tartar emetic into e circulation caused movements of vomiting, and the contents the bladder were expelled just as if the stomach had been *in tu*. This experiment seemed to prove not only that the act of miting was independent of the movements of the stomach self, but also that tartar emetic caused vomiting by acting upon e vomiting centre, and not upon the stomach. The objection, wever, has been raised that the action of the drug upon the miting centre is not direct, but reflex; and it has been urged at, although the stomach was removed, the antimony might ill be carried by the circulation to the œsophagus and intes- nes, and by there causing irritation might produce reflex miting. This seems improbable, especially as the antimonial lts have a comparatively slight action on organs having, like e œsophagus and intestines, an alkaline reaction, instead of an id one, as the stomach has.

It is probable, then, that tartar emetic does produce vomit- g by its direct action on the vomiting centre in the medulla longata, but this direct action is not the only way in which it imulates the vomiting centre—it also produces a reflex action pon it through the stomach. For it has been found that even hen tartar emetic is injected into the veins, it is eliminated by e mucous membrane of the stomach (p. 38 *et seq.*), and may thus t upon that organ in the same way as when introduced directly to it. If its emetic action be due in any great measure to irri- tion of the stomach, one would expect that a smaller dose ould be found sufficient to produce vomiting, when introduced irectly into the stomach, than when injected into the veins, for the former case the whole of it will come in contact with the omach and will do so at once; in the latter case only a fraction f the quantity injected into the veins will reach the stomach, nd some time will be required before it accumulates in the astric mucous membrane sufficiently to cause irritation. This exactly what is found by experiment, and vomiting is produced ore quickly, and by a smaller dose, when the drug is introduced to the stomach, than when injected into the veins, just as we hould expect to be the case if its emetic action were due in con- iderable measure to its action upon the stomach itself. This iew is also supported by another experiment, for after the ervous channel by which impressions are conducted from the tomach to the vomiting centre is destroyed by section of the agi, double the dose of the drug is required in order to produce omiting. It may then be concluded that antimony acts chiefly s an emetic by irritating the stomach, and thus exciting the omiting centre reflexly, but that it also acts directly on this entre when conveyed to it by the blood (p. 373).

When applied directly to the **heart** of a frog, it first increas then slows, and finally arrests its pulsations in diastole. Th action appears to be chiefly due to paralysis of the cardi muscle itself, and possibly also to the effect upon motor gangl

The effect of antimony upon the **circulation** appears to d pend partly upon the direct action of the drug upon the hea and vessels, and partly on its reflex action upon them throu the nerves of the stomach. In warm-blooded animals the pu becomes quicker as the feeling of nausea increases, and, after t vomiting, again falls nearly to the normal. Its volume is at t same time diminished. After the nausea has ceased, the pu again becomes quicker, and after this secondary acceleration h reached a greater or less height, according to the dose, it aga sinks to the normal.

As the primary acceleration during the stage of naus ceases with vomiting, it is probably to be attributed to refl irritation of the accelerating centres, or reflex depression of t vagus through the gastric nerves, whereas the cause of t secondary acceleration is more probably to be sought in dimi ished power of the vagus nerve itself. The **blood-pressu** sinks constantly from the very beginning, and this sinking probably due to diminished power of the cardiac pulsations. T **temperature** in the extremities appears to be diminished duri the stage of nausea, owing to the smaller amount of blood goi to them. As less blood reaches the surface in this conditio there is less opportunity afforded for its being cooled by conta with the atmosphere, and the temperature in the body gradua rises, even above the normal. When the spasm of the vessels the extremities relaxes, they also become warmer than norm As the effects pass off, the temperature sinks to the normal below it.


The **respiration** is first increased, and then diminished.

Large doses of antimony affect the **spinal cord** both in co and warm-blooded animals. It appears to paralyse, aft perhaps, slightly exciting, both the sensory and motor tracts the spinal cord, and as this paralysis appears in frogs while t heart still continues to beat, it must be due to the direct acti of the drug upon the nervous system itself, and not to its i direct action through the circulation. The **motor** and **senso nerves** appear also to be paralysed. The **muscles** are weaken (p. 127).

When given for a length of time, antimony seems to produ **fatty degeneration** of various organs.

The action of antimony upon the **skin** in frogs is even mo rapid than that of arsenic (p. 716), and differs from it in this r spect, that the softening does not affect the cells of the columna layer only, but extends to those of the intermediate layer (F 172). In consequence of this, the cuticle does not merely becor

tached from the dermis and peel off in strips as in poisoning arsenic, but the cells of the epidermis becoming detached



172.—Vertical section of epidermis from a frog poisoned by antimony. *a*, Columnar layer in which large cavities are formed. *b*, Columnar cells in which the reduced protoplasm is drawn into processes. *c*, Spaces in the intermediate layer. *d*, Light lines between cells indicating a softening and separation of cells. (After Nunn.)

om each other, the cuticle becomes converted into a soft jelly-ke mass which can be scraped or brushed off.

Tartar emetic appears to be **eliminated** by the mucus of the omach and alimentary canal, by the bile, and by the kidneys. s action upon the renal secretion is somewhat uncertain. It ppears to increase urea, uric acid, and pigment, and to diminish ne water and the chloride of sodium, probably by increasing the erspiration.

Uses.—The local uses of antimony will be considered under ne special preparations.

When antimony is given **internally** for its action on the sys-m generally, tartar emetic is the preparation usually employed, ut the other preparations of antimony have a similar action hen given in appropriate doses. It can be used for its emetic ction, nauseant and depressant action, or diaphoretic action. s an **emetic** it has been employed in cases of croup, in order o cause expulsion of the false membrane; but for this purpose ther emetics, such as ipecacuanha, alum, or sulphate of zinc, re now more generally employed, as they do not cause so much epression. It has also been used with considerable success to ut short an attack of intermittent fever, either alone or com-ined with a purgative. Indeed, in cases where malarial poison-ng has been intense, quinine sometimes proves ineffectual unless receded by the administration of an emetic and purgative. It as sometimes been injected into the veins to produce vomiting, n cases of obstruction of the œsophagus, as, for example, by a iece of meat firmly lodged in it, and to cause expulsion of a iliary calculus lodged in the gall-duct, by the pressure from ehind which the movements of vomiting produce, along with he relaxation of the muscular fibres of the gall-duct itself.

When large doses are administered several times, what is ermed **tolerance** of the drug sets in, and it no longer produces omiting. It has been used in this way in pneumonia, but the lan is now rarely followed. How this tolerance is produced is

not at present understood. It is not improbable that it may caused by the irritant action of the first few doses upon stomach arresting the secretion of the acid juice, and produci a condition similar to that which occurs in fever. In this c dition subsequent doses of the tartar emetic, meeting with acid, will have but a feeble action upon the stomach.

In cases of obstinate constipation it has been used alc with sulphate of magnesium. As a **nauseant** it has been giv to relax the cervix uteri in labour; in acute inflammations, e in acute orchitis, where the emetic is first given, and nau is kept up by a continued administration of smaller doses; a also in pericarditis, pneumonia, pleurisy, peritonitis, meningi bronchitis, and hepatitis, as well as in acute rheumatism. an **expectorant** it is used in bronchitis. The cases in whicl is especially serviceable are those in which there is great cong tion and much dyspnœa, with little or no secretion, as shown loud, sibilant *râles* over the chest, the pulse being full, and face flushed, with a tendency to lividity. It has also been giv to check hæmoptysis when there is much excitement of circulation. As a **sedative** it is of use in nervous diseas attended with much excitement, such as certain cases of insani delirium tremens, and puerperal convulsions. In the deliri of fever, it has been highly recommended by Dr. Graves, combination with opium, as a means of producing sleep. Wh the delirium is furious the tartar emetic must be given in f and the opium in small doses; while if the delirium is mil and the sleeplessness great, the opium dose must be increa and that of the tartar emetic diminished. The same treatm may be adopted in the delirium and sleeplessness of deliri tremens.

For its **diaphoretic** action, antimony has been used to arr commencing inflammations, such as catarrh, and to check feb conditions. For this purpose it is not unfrequently given tartar emetic in doses of $\frac{1}{16}$ grain frequently repeated, or James's powder. In acute dropsy it appears to be occasiona useful, especially as a diaphoretic, in combination with bitartr of potassium and squills.

PREPARATIONS CONTAINING ANTIMONY.

B.P.	U.S.P.
Antimonii Oxidum.	Antimonii et Potassii Tartras.
Antimonium Nigrum Purificatum.	„ Oxidum.
„ **Sulphuratum.**	Antimonii Sulphidum.
„ **Tartaratum.**	„ „ Purificatum.
Liquor Antimonii Chloridi.	„ Sulphuratum.
Pilula Hydrargyri Subchloridi Composita (*v.* p. 522).	Pilulæ Antimonii Compositæ (p. 52
Pulvis Antimonialis.	Pulvis Antimonialis.
Unguentum Antimonii Tartarati.	Syrupus Scillæ Compositus.
Vinum Antimoniale.	Vinum Antimonii.

U.S.P. Antimonii Sulphidum. SULPHIDE OF ANTIMONY.—ative sulphide of antimony, Sb_2S_3; 340; purified from sili-ous matter by fusion, and as nearly free from arsenic as ssible.

CHARACTERS.—Steel-grey masses of a metallic lustre, and a riated crystalline fracture without taste or smell.

U.S.P. PREPARATION.

Antimonium Sulphidum Purificatum.

This is the ore from which the other compounds are pre-ared.

It seems to be inert, and is not used internally.

Antimonium Nigrum Purificatum, B.P.; Antimonii Sul-hidum Purificatum, U.S.P. BLACK ANTIMONY, B.P.; PURIFIED ULPHIDE OF ANTIMONY, U.S.P. Sb_2S_3; 340.

CHARACTERS.—A greyish-black crystalline powder, without nell or taste.

SOLUBILITY.—It is insoluble in water or alcohol.

REACTIONS.—It dissolves almost entirely in boiling hydrochloric acid, olving sulphuretted hydrogen, and the solution affords a white precipitate hen poured into water.

PREPARATION.—The crude sulphide, purified by fusion, is obtained in very ne powder by elutriation, then digested with ammonia to remove arsenic, ashed and dried.

IMPURITIES.—Other sulphides and arsenic.

TESTS.—If one grain be dissolved in hydrochloric acid, and the solution, ightly diluted, be gently warmed with a piece of bright copper foil, the opper being washed, dried, and heated in a dry narrow test-tube, no crystal-ne sublimate (of arsenious anhydride) should form on the upper cool part f the tube.

PREPARATIONS.

B.P.	U.S.P.
Antimonium Sulphuratum.	Antimonium Sulphuratum.
Liquor Antimonii Chloridi.	

Antimonium Sulphuratum, B. and U.S.P. SULPHURATED NTIMONY.

B.P. Sulphide of antimony, Sb_2S_3; 336; with a small and ariable amount of oxide of antimony, Sb_2O_3.

U.S.P. Chiefly antimonious sulphide, Sb_2S_3; 340; with a ery small amount of antimonious oxide.

CHARACTERS.—B.P. An orange-red powder. U.S.P. A reddish-rown, amorphous powder, odourless and tasteless.

SOLUBILITY.—It is insoluble in water and in alcohol.

REACTIONS.—B.P. It is readily dissolved by caustic soda, also by hydro-hloric acid with the evolution of sulphuretted hydrogen and the separation f sulphur. Sixty grains, moistened and warmed with successive portions of itric acid until red fumes cease to be evolved, and then dried and heated to edness, give a white residue weighing about 40 grains.

U.S.P. When heated with twelve parts of hydrochloric acid, it is nearly all issolved, with evolution of sulphuric acid. The residue, after having been ashed and dried, burns, on the application of a flame, with the characteristic

odour of sulphur, and should leave not more than a scanty ash. On dropp a solution of sulphurated antimony in hydrochloric acid into water, a w precipitate is produced, which, after washing and drying, should weigh less than 85 per cent. of the sulphide. The liquid filtered from this pr pitate yields an orange-red precipitate with hydrosulphuric acid.

Distilled water boiled with sulphurated antimony, filtered and acidula with hydrochloric acid, should be rendered not more than slightly opales by test solution of chloride of barium (limit of sulphate).

PREPARATION.—By boiling black antimony with caustic soda and sulph the sulphide is partly converted into oxide and partly unites with sodi forming sulphantimonite and antimonite of sodium.

Sulphide of Antimony		Soda		Sulphantimonite of Sodium		Antimonious Oxide	
$2Sb_2S_3$	+	$6NaHO$	=	$2Na_3SbS_3$	+	Sb_2O_3	+ $3H_2O$,

and

Antimonious Oxide		Soda		Antimonite of Sodium	
Sb_2O_3	+	$6NaHO$	=	$2Na_3SbO_3$	+ $3H_2O$.

Owing to the presence of free sulphur, sulphantimoniate, and antimon of sodium are also formed.

Sulphide of Antimony			Soda		Sulphantimoniate of Sodium		Antimonic Oxide	
$2Sb_2S_3$	+	$2S_2$ +	$6NaHO$	=	$2Na_3SbS_4$	+	Sb_2O_5	+ $3H_2O$,

and

Antimonic Oxide		Soda		Antimoniate of Sodium	
Sb_2O_5	+	$6NaHO$	=	$2Na_3SbO_4$	+ $3H_2O$.

The sulphides and oxides of antimony are soluble in the solutions of salts of antimony just mentioned. The addition of sulphuric acid decompo the salts, with the formation and precipitation of the oxides and sulphi In order to ensure uniformity of the product the acid is added while solution is hot.

These antimony compounds are soluble in caustic soda, but when thi neutralised they are precipitated, the greater part of them being decompo and the Sb_2O_3 reconverted into Sb_2S_3.

Sulphantimonite of Sodium		Sulphuric Acid		Sodium Sulphate		Antimonious Sulphide		Sulphuretted Hydrogen
$2Na_3SbS_3$	+	$3H_2SO_4$	=	$3Na_2SO_4$	+	Sb_2S_3	+	$3H_2S$.

Antimonite of Sodium				Antimonious Oxide		Water
$2Na_3SbS_3$	+	$3H_2SO_4$	=	$3Na_2SO_4$	+ Sb_2O_3	+ $3H_2O$.

Sulphantimoniate of Sodium				Antimonic Sulphide		
$2Na_3SbS_4$	+	$3H_2SO_4$	=	$3Na_2SO_4$	+ Sb_2S_5	+ $3H_2S$.

Antimoniate of Sodium				Antimonic Oxide		
$3Na_3SbO_4$	+	$3H_2SO_4$	=	$3NaSO_4$	+ Sb_2O_5	+ $3H_2O$.

DOSE.—1 to 5 grains.

PREPARATIONS.

B.P.	DOSE
Pilula Hydrargyri Subchloridi Composita (Plummer's pill) (p. 522).....1 part in 5.....	5–10

U.S.P.

Pilulæ Antimonii Compositæ (Plummer's pill) (p. 523)....1 part in 4.....1 or 2 p

The oxide it contains is probably the active part, and as t is variable the action is rather uncertain.

Liquor Antimonii Chloridi, B.P. Solution of Chloride Antimony.

Characters.—A heavy liquid, usually of a yellowish-red lour.

Reactions.—A little of it dropped into water gives a white precipitate, d the filtered solution lets fall a copious deposit on the addition of nitrate silver. If the white precipitate formed by water be treated with sulphur- ed hydrogen it becomes orange-coloured. The specific gravity of the ution is 1·47. One fluid drachm of it mixed with a solution of a quarter an ounce of tartaric acid in four fluid ounces of water, forms a clear solu- n, which, if treated with sulphuretted hydrogen, gives an orange precipi- e, weighing, when washed and dried at 212° F., at least 22 grains.

Preparation.—By boiling black antimony with hydrochloric acid, Sb_2S_3 $6HCl = 2SbCl_3 + 3H_2S$.

Preparation in which Solution of Chloride of Antimony is used.

Antimonii Oxidum.

Uses.—Is a powerful **caustic**—sometimes applied to cancers d to poisoned wounds.

Antimonii Oxidum, B. and U.S.P. Oxide of Antimony. $_2O_3$; 288.

Characters.—A greyish-white powder, fusible at a low red- at.

Solubility.—It is insoluble in water, but readily dissolved by hydrochloric id.

Reactions.—The solution, dropped into distilled water, gives a white posit, at once changed to orange by sulphuretted hydrogen. It dissolves tirely when boiled with an excess of the acid tartrate of potassium.

Preparation.—By pouring solution of chloride of antimony into water d treating the precipitate of oxychloride with sodium carbonate.

Chloride of Antimony			Oxychloride of Antimony		Hydrochloric Acid
$12SbCl_3$	+ $15H_2O$	=	$2SbCl_3, 5Sb_2O_3$	+	$30HCl$.

Oxychloride of Antimony		Carbonate of Sodium		Oxide of Antimony		Sodium Chloride		
$2SbCl_3,5Sb_2O_3$	+	$3Na_2CO_3$	=	$6Sb_2O_3$	+	$6NaCl$	+	$3CO_2$.

Dose.—1 to 4 grains.

Preparations.

B. and U.S.P.	Dose.
ulvis Antimonialis. Antimonial powder or James's powder (one part of oxide of antimony with two of phosphate of calcium)	3–10 grs.

Uses.—Oxide of antimony may be used for the same purposes tartar emetic, but it is not soluble in water, and it depends ry much on the state of the stomach how much of it will be ssolved. It is therefore less certain in its action than tartar metic and the latter is consequently to be preferred. In conse- uence of its insolubility it is said to be slower and milder than rtar emetic, but this advantage is more than counterbalanced its uncertainty.

James's powder is given as an antipyretic in fever and rheu- atism. It is also given in chronic skin-diseases along with ercury.

Antimonium Tartaratum, B.P.; Antimonii et Potas Tartras, U.S.P. TARTARATED ANTIMONY, TARTAR EMETIC, B. TARTRATE OF ANTIMONY AND POTASSIUM, U.S.P.

$KSbC_4H_4O_7.H_2O$, B.P.; $2KSbOC_4H_4O_6.H_2O$; 664, U.S.P. A tartrate of potassium and antimony.

CHARACTERS.—In colourless transparent crystals exhibiti triangular facets.

SOLUBILITY.—It is soluble in water, and less so in proof spirit.

REACTIONS.—It decrepitates and blackens upon the application of h (tartrate). Its solution in water gives with hydrochloric acid a white p cipitate, soluble in excess, and which is not formed if tartaric acid be p viously added.

PREPARATION.—By boiling acid tartrate of potassium and oxide of a mony together, $2KHC_4H_4O_6 + Sb_2O_3 = 2K(SbO)C_4H_4O_6 + H_2O$.

DOSE.—As a diaphoretic $\frac{1}{10}$ to $\frac{1}{6}$th of a grain; as an eme 1 to 2 grains. Of the wine as a diaphoretic, 10 to 40 min.; an emetic for children, $\frac{1}{2}$ to 1 fl. dr. repeated frequently.

PREPARATIONS.

B.P.	STRENGTH.	DOSE.
Unguentum Antimonii Tartarati (with simple ointment.)	1 part in 5	
Vinum Antimoniale. Antimonial Wine	2 gr. in 1 fl. oz. of sherry	5 min.–1 fl

U.S.P.	STRENGTH.	DOSE.
Syrupus Scillæ Compositus		5 min.–1 fl
Vinus Antimonii. Wine of Antimony	4 parts in 60 of water and stronger white wine up to 1,000.	

USE.—This preparation of antimony is readily soluble, as the proportion of the dose administered which actually ta effect is more constant than that of the other preparations antimony, it has gradually displaced them. For its uses p. 725.

Tartar emetic ointment has been used as a **counter-irrit** in cases of neuralgia, paralysis of children, enlarged joints, ac meningitis, laryngitis, acute bronchitis, whooping-cough, phth asthma, angina pectoris, and subacute ovaritis. For man these purposes the application of iodine preparations is preferred.

BISMUTH. Bi; 210.

Bismuth forms three classes of compounds in which it is tri-, and quinqui-valent respectively.

GENERAL SOURCES.—It is found native in the metallic sta

GENERAL REACTIONS.—It is distinguished by the white p cipitate which falls on throwing a solution of the nitrate chloride into water, and the blackening of this by sulphure hydrogen (*vide* p. 713).

General Preparation of Salts of Bismuth.

Salt	Prepared from	By
bnitrate, B. and .S.P.	Bismuth . . .	Dissolving in nitric acid, throwing the solution into a large quantity of water, collecting and drying the precipitate.
rbonate, B.P.; ubcarbonate, .S.P.	Ditto . . .	Dissolving in nitric acid, evaporating to a small bulk and adding to solution of ammonium carbonate.
ide, B.P. . .	Subnitrate . .	Boiling with solution of soda.
rate, B. and U.S.P.	Ditto . .	B.P. Dissolving in nitric acid, and adding freshly-made citrate of sodium. U.S.P. Boiling with citric acid and washing with a large quantity of water, when insoluble citrate is formed.
trate of bismuth nd ammonium, B. nd U.S.P.	Citrate of bismuth .	Mixing the citrate to a smooth paste with water and adding ammonia until it is dissolved and the liquid is neutral or faintly alkaline; filtering, evaporating, and drying.
lution of citrate of ismuth and ammonium, B.P.	Ditto .	Do., and diluting instead of evaporating.

General Action.—The soluble salts of bismuth, such as the rate of bismuth and ammonium, when given in large doses ve an action like that of antimony or arsenic and cause gas--enteritis with fatty degeneration of the liver. Small doses of uble preparations, or larger doses of sparingly soluble preparans, have a sedative effect on the stomach like that of minute ses of arsenic. The subnitrate is so sparingly soluble that its lity in gastric catarrh is probably due to its mechanical action, e charcoal (p. 542) or binoxide of manganese.

Uses.—Subnitrate of bismuth is used under the name of anish or pearl white to whiten the complexion, and as a dust- powder, lotion, or ointment to chapped nipples and hands, raded surfaces and chronic oozing from the skin, as eczema, order to take up moisture and allay smarting and itching.

It has also been employed externally as an application in aly diseases, and in intertrigo in combination with starch and ric or salicylic acid. From its power of diminishing the itability of mucous membranes it was applied by Ferrier, ng with morphine in the form of a snuff,[1] to arrest nasal tarrh, and has been used as an injection in ozæna, leucorrhœa, d gonorrhœa, to diminish the irritability. In powder with morine and starch it is a useful insufflation in laryngeal phthisis d other painful laryngeal affections. It is applied as a local

[1] Bismuth subnitrate 6 drachms; hydrochlorate of morphine 2 grains; powdered acia 2 drachms.

sedative to diminish the pain, nausea, or vomiting in irrit dyspepsia, and to lessen the irritability of the intestine in c rhœa and dysentery. It is very serviceable, either alone or c bined with lime or alkalis in the gastro-intestinal catarrh ca by cold, which is commonly known as cold in the stomach well as in the same affection occurring in children at the pe of dentition.

It is useful in pyrosis, gastralgia, and vomiting, whether vomiting be from ulcer of the stomach or other causes. It remarkably well in the indigestion and pain in the stom caused by the use of alcohol. In such cases it is best g with a little magnesia, about ten grains of the subnitrate an equal quantity of magnesia or its carbonate.

The carbonate of bismuth is more soluble in the gastric j than the subnitrate, and is supposed to be more powerful, and same advantage, if advantage it be, is possessed by the citrat bismuth and ammonium. My own experience leads me to pr the less soluble subnitrate to either of the other preparations

B.P. Bismuthum. BISMUTH.—A crystalline metal. In crude state it is impure.

PREPARATION.

Bismuthum Purificatum.

B.P. Bismuthum Purificatum. PURIFIED BISMUTH.

CHARACTERS.—A crystalline metal of a greyish-white col with a distinct roseate tinge. Specific gravity 9·83.

SOLUBILITY AND REACTIONS.—Dissolved in a mixture of equal volu of nitric acid and distilled water, it forms a solution which by evapora yields colourless crystals, that are decomposed on the addition of w giving a white precipitate.

PREPARATION.—By fusing with cyanide and carbonate of potassium, bonate of sodium and sulphur.

IMPURITIES.—Arsenic, iron, copper, cadmium, lead, antimony.

TEST.—If the mother liquor from which the crystals have been separ be evaporated with hydrochloric acid until all the nitric acid is dissipate little of the product yields no evidence of arsenium on being examine the hydrogen test commonly known as Marsh's Test; no blue coloratio adding water and excess of ammonia (no copper), and no precipitate or tering and saturating the ammoniacal filtrate with nitric acid (no ti cadmium); no white precipitate with diluted sulphuric acid (no lead); no or black precipitate with sulphite of sodium (no selenium nor tellurium) blue precipitate with ferrocyanide of potassium (no iron).

PREPARATIONS CONTAINING BISMUTH.

B.P.	U.S.P.
Bismuthi Carbonas.	Bismuthi Carbonas.
„ Subnitras.	„ Citras.
Liquor Bismuthi et Ammonii Citratis.	„ Subnitras.
Trochisci Bismuthi.	

Bismuthi Subnitras, B. and U.S.P. SUBNITRATE OF BISMUTH. $BiONO_3.H_2O$; 306, U.S.P.

CHARACTERS.—A heavy white powder in minute crystalline les, blackened by sulphuretted hydrogen.

SOLUBILITY.—Insoluble in water, but soluble in nitric acid mixed with its volume of distilled water.

REACTIONS.—The solution in nitric acid when poured into water gives a te precipitate. It forms with sulphuric acid diluted with an equal bulk vater a solution which is blackened by sulphate of iron (nitrate). The ic acid solution gives no precipitate with diluted sulphuric acid (no lead) with solution of nitrate of silver (no chloride).

IMPURITIES.—Lead, nitrates, chlorides.

DOSE.—5 to 20 grains.

PREPARATION.

B.P.	DOSE.
Trochisci Bismuthi, 2 grs. in each lozenge	.....1 to 6 lozenges.

Bismuthi Carbonas, B.P.; Bismuthi Subcarbonas, U.S.P. RBONATE OF BISMUTH, B.P.; SUBCARBONATE OF BISMUTH, U.S.P. $Bi_2CO_3).H_2O$, B.P.; $(BiO)_2CO_3.H_2O$; 530, U.S.P.

CHARACTERS.—A white powder, blackened by sulphuretted drogen.

SOLUBILITY.—It is insoluble in water, but soluble with effervescence in ic acid.

REACTIONS.—The solution gives the reactions of bismuth (pp. 713, 731).

IMPURITIES.—Nitrate.

TEST.—When added to sulphuric acid coloured with sulphate of indigo colour of the latter is not discharged.

DOSE.—5 to 20 grains.

Bismuthi Citras, B. and U.S.P. CITRATE OF BISMUTH. $C_6H_5O_7$; 399.

CHARACTERS.—A white amorphous powder, permanent in the , odourless and tasteless.

SOLUBILITY.—It is insoluble in water or alcohol, but soluble in water of monia.

DOSE.—2 to 5 grains.

USES.—Used to prepare the solution of bismuth and ammo- um.

PREPARATIONS.

B.P.	U.S.P.
Liquor Bismuthi et Ammonii Citratis.	Bismuthi et Ammonii Citras. Liquor „ Citratis.

B.P. Liquor Bismuthi et Ammonii Citratis. SOLUTION OF TRATE OF BISMUTH AND AMMONIUM.

CHARACTERS.—A colourless solution with a saline and slightly etallic taste. Neutral or slightly alkaline to test-paper; mixing th water without change. One fluid drachm contains 3 grains oxide of bismuth.

REACTIONS.—It gives the reactions of ammonia and bismuth.

DOSE.—½ to 1 fluid drachm.

B. and U.S.P. Bismuthi et Ammonii Citras. CITRATE OF BISMUTH AND AMMONIUM.

CHARACTERS.—Small, shining, pearly or translucent sca becoming opaque on exposure to air, odourless, having a slig acidulous and metallic taste, and a neutral or faintly alka reaction.

REACTIONS.—The aqueous solution of the salt gives the reaction of muth, of ammonia (p. 634) and of a citrate (p. 594).

DOSE.—2 to 4 grains.

USES.—The solution of bismuth and ammonium, B.P., and soluble salt, U.S.P., are more astringent and irritant in t action than the insoluble subnitrate, oxide, or carbonate. T may be used as astringents, but are inferior to the insol preparations as a means of allaying irritation.

CHAPTER XXVIII.

METALS—(*continued*).

Class VIII

Group I.

Iron—*Nickel*—*Cobalt*—Manganese.

FERRUM; IRON. Fe; 55·9.

ETALLIC iron in the form of fine, bright, and non-elastic ire.

Iron forms ferrous salts in which it is bivalent, e.g. $FeCl_2$ or $FeSO_4$, and ferric, in which it is either trivalent or quadrivalent. Ferric chloride may be regarded as $FeCl_3$ or as Fe_2Cl_6, in which ach of two atoms of quadrivalent iron have one affinity satu-ated by union with each other, and the other three by chlorine, $Cl_3{\equiv}Fe—Fe{\equiv}Cl_3$.

General Sources.—It is found native in the metallic state, nd also as oxide, sulphide, chloride, carbonate, phosphate, sul-hate, and arseniate. It is obtained from its ores by smelting with coke and clay or limestone.

General Reactions.—These are shown in the accompanying able. The reactions most generally mentioned in the pharma-opœias are those with ferrocyanide and ferricyanide of potassium. t is to be remembered that a preparation of iron containing it n both the ferrous and ferric condition, or which, by its decom-position, yields iron in these two states, gives a precipitate with both of these reagents. The arseniate of iron, B.P., phosphate f iron, and the citrate of iron and quinine are examples of his.

General Reactions of Iron Salts.

Reagent	Ferrous Salts	Ferric Salts
Hydrogen sulphide .	No precipitate .	White precipitate of sulphur (ferric are reduced to ferrous)
Ammonium sulphide	Black precipitate .	Black precipitate.
Caustic alkalis and ammonia	Nearly white precipitates of ferrous hydrate rapidly becoming green and then brown	Foxy-red precipitates of fe hydrate.
Carbonates of ditto .	Whitish precipitate of ferrous carbonate which changes like the hydrate	Foxy-red precipitates. Carbo acid escapes.
Potassium ferrocyanide	Nearly white precipitate becoming blue on exposure	Deep blue precipitate (Pruss blue).[1]
Potassium ferricyanide	Deep blue precipitate	No precipitate. Dark colorati
Tincture of galls .		Intense black.

General Impurities.—Zinc, copper, and fixed alkalis may be presen its salts. Ferrous salts may be present as impurities in ferric and *vice ve*

Tests.—The test used for the chloride in the U.S.P. is as follows :—If iron be completely precipitated from a solution of the salt by an exces water of ammonia the filtrate should not yield either a white precipi (absence of zinc) or a dark-coloured precipitate with hydrosulphuric (absence of copper), nor should it leave a fixed residue on evaporation gentle ignition.

The absence of ferrous salts as impurities in ferric is ascertained by solution giving no precipitate with *ferri*cyanide of potassium.

The absence of ferric salts as an impurity in ferrous is ascertained by precipitate with *ferro*cyanide of potassium not being blue at first, but ne white, and only becoming blue on exposure.

General Preparation of Salts of Iron.

	Prepared from	By
Ferrous Sulphate (p. 741)	Iron . . .	Dissolving in sulphuric acid.
Dried Sulphate (p. 741)	Ferrous sulphate .	Heating to drive off water crystallisation.
Granulated Sulphate, B.P., Precipitated, U.S.P. (p. 741)	Ditto . . .	Pouring an aqueous solution i spirit.
Carbonate (Saccharated) (p. 742)	Ditto . . .	Decomposing (by ammonium c bonate, B.P.), (by sodium bi-c bonate, U.S.P.), and mixing w sugar.
Do. (Mistura Ferri Composita) (p. 742)	Ditto . . .	Decomposing by potassium car nate and mixing with myrrh,

[1] With the tartrate of iron and ammonium (U.S.P.) no colour or precipita produced unless the solution is acidulated with hydrochloric acid.

GENERAL PREPARATION OF SALTS OF IRON—*continued.*

	Prepared from	By
rric Sulphate, B.P. p. 742) rric Tersulphate, .S.P. (p. 742) rric Subsulphate, .S.P. (p. 743)	Ferrous sulphate	Adding sulphuric acid and oxidising by heating with nitric acid. ($6FeSO_4 + 3H_2SO_4 + 2HNO_3 = 3Fe_2(SO_4)_3 + 4H_2O + N_2O_2$.) Ditto, using too little sulphuric acid to form tersulphate.
rric Oxide (p. 743)	Ferric sulphate .	Mixing with magnesia and water, U.S.P. Mixing with water and solution of soda, B.P.
rric Oxide (Hyrated, U.S.P.) (p. 43)	Ditto . . .	By precipitating with ammonia, washing and making into a paste with water, U.S.P.
rric Oxide (Hyrated, B.P.) (p. 744)	Ditto . . .	Pouring the diluted solution into solution of soda, B.P.; and drying below 212°.
duced Iron (p. 744)	Ferric oxide . .	Passing hydrogen over it while heated ($Fe_2O_3 + 6H = Fe_2 + 3H_2O$).
rric Chloride (p. 45)	Iron . . .	Dissolving in hydrochloric acid and oxidising by nitric acid. ($3Fe_2 + 12HCl = 6FeCl_2 + 12H$ $6FeCl_2 + 6HCl + 2HNO_3 = 3Fe_2Cl_6 + 4H_2O + N_2O_2$.)
rric Nitrate (p. 747)	Iron . . .	Dissolving in nitric acid ($Fe_2 + 8HNO_3 = Fe_2(NO_3)_6 + 4H_2O + N_2O_2$).
rric Oxychloride Dialysed Iron) B.P. p. 746)	Ferric chloride .	Precipitating ferric oxide by ammonia, dissolving it in solution of perchloride, and dialysing the solution until it is tasteless.
rric Acetate (Solution of), B. and .S.P. (p. 744)	Ferric sulphate .	Precipitating ferric oxide by ammonia, washing, and dissolving in glacial acetic acid, and diluting to the necessary strength.
rric Citrate, U.S.P. p. 748)	Ditto (Tersulphate)	Precipitating oxide by ammonia, washing and dissolving in citric acid. This forms the Liquor Ferri Citratis, U.S.P. Ferri Citras is prepared by evaporation of the Liquor under 60° C.
rtrate of iron and otassium, U.S.P. errumTartaratum, .P.) (p. 747)	Persulphate . .	Precipitating ferric oxide by ammonia, washing and mixing with acid tartrate of potassium.
rtrate of iron and mmonium, U.S.P. p. 747)	Ditto . . .	Ditto, using tartaric acid and tartrate of ammonium in place of acid tartrate of potassium.
trate of iron and mmonium, B. and .S.P. (p. 748)	Ditto . . .	Ditto, using citric acid and ammonia.
trate of iron and uinine, B. and .S.P. (p. 749)	Ditto and sulphate of quinine	Precipitating ferric oxide and quinine by ammonia and dissolving it in citric acid.
trate of iron and trychnine, U.S.P. p. 749)	Ferric sulphate and strychnine	Precipitating ferric oxide by ammonia and dissolving it along with strychnine in citric acid.
lphate of iron and mmonium, U.S.P. p. 749)	Ferric sulphate and ammonium sulphate	Heating them together.

General Preparation of Salts of Iron—*continued.*

	Prepared from	By
Ferrous Lactate, U.S.P. (p. 750)	Iron. . . .	Dissolving in lactid acid.
Ferrous Oxalate, U.S.P. (p. 750)	Ferrous sulphate .	Precipitating a solution with alic acid (ferrous oxalate is slightly soluble).
Ferrous Iodide, B.P. (Syrup of) (p. 750)	Iron. . . .	Heating with iodine and w (the completion of the pro is recognised by the brown co of the iodine disappearing the froth becoming white) then adding syrup.
Ferrous Iodide (Pill of), B.P. (p. 750)	Ditto . . .	Same as syrup, but mixing sugar and powdered liquc root instead of with syrup.
Ferrous Bromide (Syrup of) U.S.P. (p. 751)	Ditto . . .	Same as syrup of iodide, u bromine instead of iodine.
Arseniate of Iron, B.P. (p. 751)	Ferrous sulphate, arseniate of sodium, and acetate of sodium	Mixing a solution of arseniate acetate of sodium with on ferrous sulphate. If arsenia sodium alone were used, free phuric acid would be for which would react on the ar iate. $3FeSO_4 + 2Na_2HAsO$ $Fe_3As_2O_8 + 2Na_2SO_4 + H_2$ To avoid this acetate of sodiu added. The sulphuric acid bines with the sodium and set acetic acid, which has no ac on the arseniate of iron. $3F$ $+ 2Na_2HAsO_4 + 2NaC_2H_3O$ $Fe_3As_2O_8 + 3Na_2SO_4 + 2HC_2H$
Phosphate of Iron, B. and U.S.P. (p. 751)	Ferrous sulphate, phosphate of sodium, and acetate of sodium	The same process as in the paration of arseniate. The tions are similar. $3FeSO$ $2Na_2HPO_4 + 2NaC_2H_3O_2 =$ $P_2O_8 + 3Na_2SO_4 + 2HC_2H_3O_2$
Pyrophosphate of Iron, U.S.P. (p. 752)	Citrate of iron . .	Decomposing solution by sol of sodium pyrophosphate.
Hypophosphite of Iron, U.S.P. (p. 752)	Ferrous sulphate .	Decomposing by hypophos of calcium when ferrous h phosphite is precipitated, on evaporation becomes fer
Valerianate of Iron, U.S.P. (p. 752)	Ferric sulphate .	Decomposing by valerianat sodium.

General Action of Iron Salts.—Iron differs from most other heavy metals in forming a normal constituent of the a body, so that it may be regarded as a food as well as a medi It forms an important constituent of the hæmoglobin in the b This acts as the oxygen-carrier to the tissues, and, therefore tissue-oxidation and the functional activity of the organs de more or less upon the amount of iron present in the body. cording to Preyer, in a healthy woman the minimum amou

n in 100 grammes of blood is ·048 gramme, of hæmoglobin 57 grammes; the maximum, ·057 gramme and 13·69 grammes iron and hæmoglobin respectively. In a healthy man, in 100 mmes the proportion is ·0508 gramme of iron (minimum), ·063 aximum), 12·09 grammes hæmoglobin (minimum), and 15·07 mmes (maximum).[1] Both per- and proto-salts of iron form mpounds with **albumen**, but they differ in their properties. The rous salts give a yellow colour with albuminous solutions, but not precipitate them, the albuminous compound being, apently, usually soluble. Diluted ferric salts, on the contrary, cipitate albumen slowly, and concentrated solutions precipitate apidly. The precipitate is soluble in dilute acids and in gastric ce.

When applied to the **skin** neither ferrous nor ferric salts have y action, as they do not dissolve the epidermis nor pass through in any appreciable quantity. When applied to a denuded face, or to a mucous membrane they combine with albumen. e ferrous salts have but a slight astringent action, whereas the ric salts coagulate the albumen on the surface and also blood. ey are thus powerful astringents and styptics. In the **mouth** y all have an inky taste, and as they are liable to form black phides with sulphuretted hydrogen, which is not unfrequently sent in the breath, they are apt to discolour the teeth or tongue. the **stomach** they have an astringent and irritant action, that the ferric being more powerful than that of the ferrous salts. the **intestine** they have a somewhat similar action; meeting re, as they often do, with sulphuretted hydrogen they become nverted, in great part, into sulphides, and, passing out in the ols, give to them an inky black colour which sometimes alarms tients. In small doses they usually have an astringent action, d tend to cause constipation. Larger doses, on the other hand, m to stimulate peristalsis, and increase the number of stools, d sometimes even small doses will cause diarrhœa in some lividuals. After absorption into the **blood** they are found to rease, not only the number of the blood-corpuscles, but the rcentage of hæmoglobin contained in them, and may also cause ittle free iron to be present in the serum. By thus increasing idation in the **tissues** they increase the functional activity of various organs. The effect of ferrous and ferric salts added the blood is very different, ferric salts producing a firm coagum, whereas the ferrous salts tend rather to diminish the coagulity of the blood.

Iron has an action on the **nervous system** which varies acding to the dose and mode of administration. When injected bcutaneously in **frogs**, iron salts cause slight excitement and n paralysis of the central nervous system. In the later stages poisoning the irritability of the voluntary muscles is diminished,

[1] Preyer, *Die Blutcrystalle*. Jena, 1871.

but the heart is not affected. In mammals they cause cong tion of the stomach and intestine, and **diarrhœa**. They prod **paralysis** both of sensation and motion. The **blood-pressu** falls. This is due to paralysis of the **vaso-motor nerves**, pecially of the intestine, resembling that produced by arse antimony, emetin, and colchicin.

Iron is **eliminated** to a considerable extent by the bile (p. 40 by the mucous membrane of the intestine, and by the kidneys

Uses of Iron.—The ferrous salts are rarely employed for th local action. The ferric salts are used as **styptics**. The str solution of perchloride may be employed to arrest bleeding fr the cavity of a tooth after extraction, or to stop the oozing fro wound where it is impossible to ligature all the bleeding poi When diluted it may be used as an injection to arrest hæmorrh from the nose, or may be injected into the cavity of the ute to arrest bleeding from that organ. Mixed with laudanum it been used as an injection in gonorrhœa and gleet. Both ferr and ferric salts are administered internally in order to prod the general action of iron in increasing the blood-corpusc They differ to some extent, however, the ferrous salts havin less astringent action on the intestines than the ferric. In ca where the mucous membrane of the alimentary canal is irrita this is advantageous, as in such instances the ferric salts mi cause digestive disturbances and headache. In other instanc however, especially those where the tongue is pale and flab the more astringent preparations are to be preferred. The ch use of iron is as a **hæmatinic**, and the condition in which i most beneficial is where we have anæmia and chlorosis, whet these be due to loss of blood, imperfect nutrition, chronic charges, scrofula, syphilis, malarial poisoning, amenorrhœa albuminuria, or be consequent upon acute febrile disease; bu is also serviceable in a number of disturbances of the nutritive nervous systems. It has been recommended in large doses in ca of blood-poisoning, such as diphtheria and erysipelas, and in r vous diseases like chorea, epilepsy, giddiness, formication, twit ing of the fingers, and subjective sensations of light and heat cold to which some patients are liable, especially about the clim teric period. It is also used internally in order to diminish charges from the mucous membranes of the intestines, as chronic diarrhœa and dysentery, and from the vagina in leuc rhœa. It acts as an astringent on the kidney, lessening amount of blood in hæmaturia, and sometimes the amoun albumen in albuminuria. It is also a useful adjunct to diure in cardiac and renal dropsy (p. 338).

B.P. Vinum Ferri.—This is prepared by macerating i wire in sherry for a month. Some of it is converted into tart and dissolved by the bitartrate of potassium in the wine.

Dose.—1 to 2 fl. dr. or more.

Use.—It is useful in anæmia both in children and adults, and ay be given with cod-liver oil.

B.P. Mistura Ferri Aromatica.—This is a curious prepara- on containing tannate of iron in very small quantities. It is metimes called Heberden's ink. It is usually said that iron nd tannin are incompatible, and so they are in so far that they roduce ink, but this preparation is said to be a very useful one. Iron cannot be taken up in very large quantities, and its bsorption is often prevented by the condition of the patient's omach. This preparation has been put together evidently with he view of combining all the drugs which were likely to do good y themselves, and in total disregard of the chemical action which ould take place among themselves.

Preparation.—By macerating pale cinchona bark (1 oz.), calumba root -oz.), cloves (¼-oz.), and fine iron wire (½-oz.), in peppermint water (12 oz.) r three days, agitating occasionally; then filtering and adding as much eppermint water to the filtrate as will make the product measure 12½ fl. oz.; this add compound tincture of cardamoms (3 fl. oz.) and tincture of orange eel (½ fl. oz.), and preserve the mixture in a well-stopped bottle. The pale inchona bark contains tannin, which combines with the iron. Both it and alumba are gastric tonics, and the carminatives relieve flatulence.

Dose.—1 to 2 fl. oz.

Ferri Sulphas, B. and U.S.P. Sulphate of Iron. $FeSO_4.7H_2O$; 277·9.

Characters.—In oblique rhombic prisms, of a pale greenish lue colour and styptic taste.

Solubility.—It is insoluble in rectified spirit, soluble in water.

Reactions.—The aqueous solution gives the reaction of a sulphate (p. 594) nd of a ferrous salt (p. 736).

Dose.—1 to 5 grains.

Preparations.

B.P.	U.S.P.
Ferri Sulphas Exsiccata.....	Ferri Sulphas Exsiccata.
Pilula Aloes et Ferri (*vide* p. 522) 1 part in 7.	

Ferri Sulphas Exsiccata, B.P.; Ferri Sulphas Exsic- catus, U.S.P. Dried Sulphate of Iron. $FeSO_4.H_2O$; 169·9.

Prepared by heating sulphate. It is less apt to oxidise, and is well fitted for pills.

Dose.—½ to 3 grains.

Preparation.

U.S.P.

Pilulæ Aloes et Ferri (*vide* p. 523).

Ferri Sulphas Granulata, B.P.; Ferri Sulphas Præcipi- tatus, U.S.P. Granulated Sulphate of Iron, B.P. Pre- cipitated Sulphate of Iron, U.S.P. $FeSO_4.7H_2O$; 277·9.

Characters and Tests.—In small granular crystals of a pale

greenish-blue colour. In other respects it corresponds to characters and tests for sulphate of iron.

DOSE.—1 to 5 grains.

USES.—It is very **astringent**. It has been used externa as ointment or lotion to the skin in erysipelas, as a lotion ophthalmia, and as a lotion or injection in prolapsus ani, a bleeding piles. It has also been used as an injection in gon rhœa and leucorrhœa.

Internally it is used in cases of anæmia, especially where t is accompanied by a tendency to profuse sweating, pass hæmorrhages, or mucous discharges, such as chronic catarrh leucorrhœa. Its astringent action on the stomach has been s to render it serviceable in gastrodynia and gastric ulcer.

Ferri Carbonas Saccharata, B.P.; Saccharatus, U.S SACCHARATED CARBONATE OF IRON, B.P.; SACCHARATED FERR CARBONATE, U.S.P.

Carbonate of iron, FeO,CO_2 or $FeCO_3$, mixed with perox of iron and sugar, the carbonate forming at least 37 per cent. the mixture B.P., 15 per cent. U.S.P.

CHARACTERS.—Small coherent lumps, or powder, of a g colour, with a sweet, very feeble chalybeate taste.

SOLUBILITY.—It dissolves with effervescence (carbonate) in warm hy chloric acid diluted with half its volume of water.

REACTIONS.—The solution gives only traces of sulphate (p. 595) exhibits the reactions of a ferrous salt.

DOSE.—5 to 20 grains.

PREPARATIONS.

B.P.	DOSE.
Pilula Ferri Carbonatis (*vide* p. 522) .....1 part in 1¼	.....5–20 grs.

U.S.P.	
Massa Ferri Carbonatis	.....3–5 grs.

U.S.P. Massa Ferri Carbonatis. MASS OF CARBONATE OF IRON.—Sulphat iron, 100 parts; carbonate of sodium, 110 parts; honey, 38 parts; sugar, 25 pa syrup and water, q.s.

Mistura Ferri Composita, B. and U.S.P. COMPOU MIXTURE OF IRON. GRIFFITH'S MIXTURE.

COMPOSITION.—Sulphate of iron, 25 grs.; carbonate of pot sium, 30 grs.; myrrh and refined sugar, of each 60 grs.; sp of nutmeg, 4 fl. drs.; rose water, 9½ fl. oz., B.P. Sulphate iron, 6; myrrh, 18; sugar, 18; carbonate of potassium, spirit of lavender, 50; rose water, 900, U.S.P.

DOSE.—1 to 2 fluid ounces.

USES.—Carbonate of iron in its various preparations is of the most useful forms of iron for administration as a **her tinic** and **emmenagogue**.

Liquor Ferri Persulphatis, B.P.; Tersulphatis, U.S SOLUTION OF PERSULPHATE OF IRON, B.P.; OF TERSULPHA U.S.P. $Fe_2(SO_4)_3$; 399·8.

CHARACTERS.—A dense solution of a dark-red colour, inodorous d very astringent, miscible in all proportions with alcohol and ter.

REACTIONS.—Diluted with ten volumes of water, it gives the reactions of ulphate and of a ferric salt only.

PREPARATIONS IN WHICH SOLUTION OF PERSULPHATE OF IRON IS USED.

B.P.	U.S.P.
Ferri et Ammonii Citras.	Ferri et Ammonii Citras.
Ferri et Quininæ Citras.	„ „ „ Tartras.
Ferri Peroxidum Hydratum.	„ „ Potassii „
Ferrum Tartaratum.	„ Oxidum Hydratum.
	„ „ „ cum Magnesiâ.
	Liquor Ferri Nitratis.
	„ „ Citratis.

USES.—Not used as a remedy, but to prepare peroxide, &c.

U.S.P. Liquor Ferri Subsulphatis. SOLUTION OF SUB-LPHATE OF IRON. SOLUTION OF BASIC FERRIC SULPHATE. IONSEL'S SOLUTION.)

CHARACTERS. — Like the tersulphate; but on mixing two lumes of the solution with one of concentrated sulphuric acid solid white mass separates on standing.

DOSE.—3 to 10 minims (·18–·64 c.c.).

ACTION.—**Astringent, styptic, hæmatinic.** Less irritating an the tersulphate.

USES.—Like the chloride. It is a useful astringent in relaxed re-throat and tonsillitis.

U.S.P. Ferri Oxidum Hydratum. HYDRATED OXIDE OF ON. $Fe_2(HO)_6$; 213·8.

CHARACTERS.—A soft, moist, pasty mass, of a reddish-brown lour.

SOLUBILITY.—Dissolves readily in diluted hydrochloric acid.

REACTIONS.—The solution gives the reaction of a ferric salt only.

DOSE.—$\frac{1}{4}$ to $\frac{1}{2}$ ounce.

USE.—As an **antidote** for arsenic, it should be given in doses f a tablespoonful every five or ten minutes. It may be used in næmia and amenorrhœa.

PREPARATIONS.

U.S.P. Emplastrum Ferri (hydrated oxide dried, with Canada turpentine, urgundy pitch, and lead plaster).

U.S.P. Trochisci Ferri (troches of iron). Iron lozenges, 5 grs. in each lozenge.

U.S.P. Ferri Oxidum Hydratum cum Magnesiâ. HY-RATED OXIDE OF IRON WITH MAGNESIA.—Antidote to arsenious acid.

PREPARATION.—Mix the solution of tersulphate of iron 1,000 grs. (65·00 gm.) ith twice its weight of water. Rub the magnesia, 150 grains (10·00 gm.) ith water to a smooth and thin mixture; transfer this to a bottle capable of olding 32 fl. oz., or about 1 litre, and fill it up with water. When the pre-aration is wanted for use, mix the two liquids by adding the magnesia ixture gradually to the iron solution, and shake them together until a omogeneous mass results.

NOTE.—The diluted solution of tersulphate of iron and the mixture of magnesia with water should always be kept on hand, ready for immediate use.

USE.—As an **antidote** in poisoning by arsenic.

B.P. Ferri Peroxidum Hydratum. HYDRATED PEROXI OF IRON. $Fe_2O_3H_2O$ or $Fe_2O_2(HO)_2$.

CHARACTERS.—A reddish-brown powder, destitute of taste a not magnetic.

SOLUBILITY.—It dissolves completely, though slowly, with the aid of he in hydrochloric acid, diluted with half its volume of water.

REACTIONS.—The solution gives the reactions of a ferric salt only.

DOSE.—5 to 30 grains.

B.P. PREPARATION.

Emplastrum Ferri. IRON PLASTER.—Hydrated peroxide of iron in powder, Burgundy pitch, and lead plaster (1 part in 11).

USES.—Not astringent. Given in powder or electuary chie in cases of tic and neuralgia.

Iron plaster is often called 'strengthening plaster.' It for a mechanical support to weak parts and keeps them war Used in pains or weakness across the loins in females, in rhe matic pains, as lumbago, weak joints, &c.

Ferrum Redactum, B. and U.S.P. REDUCED IRON. Metallic iron, with a variable amount of magnetic oxide of iro

CHARACTERS.—A fine greyish-black powder, strongly attract by the magnet, and exhibiting metallic streaks when rubbed w firm pressure in a mortar.

SOLUBILITY.—It dissolves in hydrochloric acid with the evolution hydrogen. ($Fe + 2HCl = FeCl_2 + H_2$.)

REACTIONS.—The solution gives a light blue precipitate with the yel prussiate of potash.

IMPURITY.—Magnetic oxide.

TEST.—When ten grains are added to an aqueous solution of fifty gra of iodine and fifty grains of iodide of potassium ($Fe + I_2 = FeI_2$ which solves in KI), and digested in a small flask at a gentle heat, the redu iron is converted into iodide and dissolved, and not more than five gra should be left undissolved, which should be entirely soluble in hydrochl acid (oxide).

DOSE.—1 to 5 grains.

Trochisci Ferri Redacti, B.P. REDUCED IRON LOZENGES, B.P.—E lozenge contains one grain of reduced iron.

DOSE.—1 to 6 lozenges.

USES.—This preparation is generally well borne even if t stomach be somewhat irritable. It has no astringent acti When dissolved by the gastric juice it evolves hydrogen, and sulphur be present as an impurity eructations of sulphureti hydrogen are produced.

U.S.P. Liquor Ferri Acetatis. SOLUTION OF ACETA OF IRON.—An aqueous solution of ferric acetate [$Fe_2(C_2H_3O_2$ 465·8]—containing 33 per cent. of the anhydrous salt. Sp. 1·160.

PREPARATION.

Tinctura Ferri Acetatis (Solution of Acetate 50, Alcohol 30, Acetic Ether 2)

DOSE.—15 min. to 1 fl. dr.

B.P. Liquor Ferri Acetatis Fortior. STRONG SOLUTION ACETATE OF IRON.

CHARACTERS.—A deep-red fluid with a sour, styptic taste and etous odour, miscible with water or rectified spirit in all proortions. Sp. gr. 1·127.

REACTIONS.—Diluted with water it gives the reactions of a ferric salt.

DOSE.—1 to 8 minims.

PREPARATIONS.

B.P.	DOSE.
quor Ferri Acetatis (strong solution 1, diluted with water to 4)	5 to 30 min.
nctura Ferri Acetatis („ „ 1, „ „ spirit to 4)	5 to 30 min.

USE.—May be given along with acetate of potassium in opsy.

U.S.P. Mistura Ferri et Ammonii Acetatis. MIXTURE ACETATE OF IRON AND AMMONIUM (BASHAM'S MIXTURE) comises tincture of chloride of iron (2 parts), diluted acetic acid (3), lution of acetate of ammonium (20), elixir of orange (10), syrup 5), water (50).

DOSE.—½–1 fluid ounce.

USE.—As a hæmatinic generally, and in cases of renal disease pecially.

U.S.P. Ferri Chloridum. CHLORIDE OF IRON. Fe_2Cl_6. $2H_2O$; 540·2.

CHARACTERS.—Orange-yellow crystalline masses, very deliquesnt, odourless or having a faint odour of hydrochloric acid, a yptic taste, and an acid reaction.

SOLUBILITY.—Freely and wholly soluble in water, alcohol, or ether.

REACTIONS.—The dilute aqueous solution gives a brown-red precipitate ith water of ammonia, a blue one with test solution of ferrocyanide of tassium, and a white one, insoluble in nitric acid, with test solution of trate of silver.

USES.—In the solid state it keeps indefinitely, whereas in lution it is apt to deposit ferric oxide leaving excess of acid in ne solution which renders it irritating. When required it may e dissolved in water in the proportion of 1½–6 drachms to the unce of water. When semi-deliquesced it is an efficient styptic.

Liquor Ferri Perchloridi Fortior, B.P. Liquor Ferri Chloridi, U.S.P. STRONG SOLUTION OF PERCHLORIDE OF IRON, B.P. SOLUTION OF CHLORIDE OF IRON, U.S.P.

CHARACTERS.—An orange-brown solution with a strong styptic aste, miscible with water and rectified spirit in all proportions.

REACTIONS.—Diluted with water it gives the reactions of a chloride p. 594) and of a ferric salt only.

PREPARATIONS.

B.P.	DOSE.
Liquor Ferri Perchloridi (with water).....1 volume in 4	10–30 min.
Tinctura Ferri Perchloridi (with spirit)...1 volume in 4	10–30 min.

U.S.P. Tinctura Ferri Chloridi. TINCTURE OF CHLORIDE OF IRON. Dose, to 30 minims.

PREPARATION.

Mistura Ferri et Ammonii Acetatis, U.S.P.

USES.—The strong solution is one of the most power **styptics** we possess. It forms, almost immediately, a hard bl coagulum with blood, and by blocking up the mouths of vessels arrests further hæmorrhage. Cotton wool steeped in t may be used to arrest the hæmorrhage from the cavity o tooth after its extraction, and to stop the bleeding from lee bites. It has been applied as a caustic in hospital gangrene, bleeding from the uterus, and, diluted with three volumes water, it may be injected into the uterine cavity, but is bet applied by swabbing it over the interior of the uterus wit sponge. It has been injected into aneurisms, in order to p duce coagulation within them. There is, however, great dan that part of the clot may become detached and carried onwar producing embolism, or that inflammation and ulceration m take place within the aneurismal sac itself.

It has also been injected into varicose veins and nævi fo similar purpose, but in nævi on the face it may cause sloughi and leave scars. It has been used as a spray for the purpose arresting hæmorrhage from the lungs.

The liquor and tincture are perhaps more often employ than any other preparation of iron. They are **astringe** generally causing constipation, but sometimes they irritate t intestine, increasing the number of stools. They are amon the most efficient preparations of iron as **hæmatinics.** They contraindicated by a red irritable tongue, and succeed b when the tongue is pale, flabby, and marked with the teeth the edges.

I have found that when patients bear iron badly and co plain of headache even after small doses, they can take wi benefit a single drop of the tincture or solution of the perchlori in a full tumbler of water. In its great dilution the mixtu somewhat resembles chalybeate waters, which often succe much better than pharmaceutical preparations. The tinctu has been given in erysipelas in very large doses, 20–30 minim repeated every hour or two.

The tincture is useful in purpura with extensive extravasatio In skin-diseases generally, such as eczema, lupus, seborrhœa, a psoriasis, it is only useful when they are associated with anæm

B.P. Liquor Ferri Dialysatus. SOLUTION OF DIALYS IRON.—This solution of dialysed iron, so-called, is a solution highly basic ferric oxychloride, or chloroxide of iron, from whi most of the acidulous matter has been removed by dialysis.

CHARACTERS.—A clear dark reddish-brown liquid, free fr

y marked ferruginous taste. Neutral to test-papers. Specific vity about 1·407.

REACTIONS.—The solution gives no precipitate with ferrocyanide of potas- n or with nitrate of silver, but after being heated with hydrochloric acid ields with ferrocyanide of potassium a blue precipitate.

DOSE.—10 to 30 minims.

Liquor Ferri Pernitratis, B.P.; Liquor Ferri Nitratis, S.P. SOLUTION OF PERNITRATE OF IRON, B.P.; NITRATE OF ON, U.S.P. $Fe_2(NO_3)_6$; 483·8.

CHARACTERS.—A clear solution of a reddish-brown colour, ghtly acid and astringent to the taste.

REACTIONS.—When to a little of it placed in a test-tube half its volume of e sulphuric acid is added, and then a solution of sulphate of iron is poured the whole assumes a dark-brown colour (nitrate). It gives the reactions a ferric salt only.

DOSE.—10 to 40 minims.

USES.—It has been used as an **astringent** in the diarrhœa children, and, also as an astringent, to diminish discharges m mucous surfaces, also to arrest hæmorrhage from internal gans. It can be given along with spirit of nitrous ether or trate of potassium in cases of anæmia with albuminuria and opsy.

Ferrum Tartaratum, B.P.; Ferri et Potassii Tartras, .S.P. TARTARATED IRON, B.P.; TARTRATE OF IRON AND POTAS- UM, U.S.P.

CHARACTERS.—Thin, transparent scales of a deep garnet colour, ghtly sweetish and astringent in taste.

SOLUBILITY.—It is soluble in water and sparingly soluble in spirit.

REACTIONS.—The aqueous solution, when acidulated with hydrochloric id, gives the reactions of a ferric salt only. When the salt is boiled th solution of soda, peroxide of iron separates, but no ammonia is evolved ot the ammonia-citrate), and the filtered solution when slightly acidulated acetic acid gives, as it cools, a crystalline deposit (potassium).

DOSE.—5 to 10 grains.

The double salts of iron with potassium, ammonium, quinine, c., are usually called the **scale preparations of iron** from their ppearance. These are less astringent than, and do not confine e bowels so much as, either the proto-sulphate or the per-salts. nother advantage is that they may be given along with alkaline rbonates without being precipitated. They are employed in ses where the other preparations cause headache, or derange e digestion, on account of the stomach being irritable.

U.S.P. Ferri et Ammonii Tartras. TARTRATE OF IRON AND MMONIUM.

CHARACTERS.—Transparent scales, varying in colour from arnet-red to yellowish-brown, only slightly deliquescent, without

odour, having a sweetish and slightly ferruginous taste and neutral reaction.

SOLUBILITY.—It is readily soluble in water.

REACTIONS.—It is not precipitated by ammonia, but gives a brown precipitate of ferric oxide with potash and evolves the vapour of ammonia. adding test solution of ferrocyanide of potassium to the salt, no blue col or precipitate is produced unless the solution is acidulated with hydrochl acid.

Ferri et Ammonii Citras, B. and U.S.P. CITRATE OF IR AND AMMONIUM.

CHARACTERS.—In thin, transparent scales of a deep red colo slightly sweetish and astringent in taste. It feebly reddens litm paper.

SOLUBILITY.—It is soluble in water, but almost insoluble in recti spirit.

REACTIONS.—Heated with solution of potash it evolves ammonia deposits peroxide of iron. The alkaline solution from which the iron separated does not, when slightly supersaturated with acetic acid, give crystalline deposit (distinction from and absence of tartrate).

DOSE.—5 to 10 grains.

PREPARATIONS.

B.P.	DOSE.
Vinum Ferri Citratis. 8 grains in 1 fl. oz. of orange wine	1–4 fl. drs.

U.S.P.

Ferri et Strychninæ Citras	
Liquor Ferri et Quininæ Citratis	
Vinum Ferri Citratis	1–2 fl. drs.

U.S.P. Vinum Ferri Citratis. (Citrate of iron and ammonium, 4; tinctur sweet orange-peel, 12; syrup, 36; stronger white wine, 44.)

U.S.P. Liquor Ferri Citratis. AN AQUEOUS SOLUTION FERRIC CITRATE, $Fe_2(C_6H_5O_7)_2$; 489·8, containing about 35 cent. of the anhydrous salt.

CHARACTERS.—A dark brown liquid, odourless, having slightly ferruginous taste and acid reaction.

REACTIONS.—It gives the reactions of a citrate (p. 594) and a bluish gr precipitate with ferrocyanide of potassium, which is increased and rende dark blue by the subsequent addition of hydrochloric acid.

DOSE.—Ten minims (0·6 c.c.), equal to 5 grains of the sal

U.S.P. Ferri Citras. CITRATE OF IRON. $Fe_2(C_6H_5O_7)_2.6H$ 597·8.

CHARACTERS.—Transparent garnet-red scales, permanent the air, odourless, having a very faint ferruginous taste and acid reaction.

SOLUBILITY.—Slowly but completely soluble in cold water and readil in boiling water; insoluble in alcohol.

REACTIONS.—*Vide* supra.

PREPARATION.

Ferri Quininæ Citras.

USE.—Is pleasant. A solution of 240 grains in 1 fl. oz

ater keeps perfectly, and may be given in doses of 10 minims, qual to 5 grains, as a tonic.

Ferri et Quininæ Citras, B. and U.S.P. CITRATE OF IRON ND QUININE.

CHARACTERS.—Thin scales of a greenish golden-yellow colour, mewhat deliquescent.

SOLUBILITY.—It is entirely soluble in cold water.

REACTIONS.—The solution is very slightly acid, and is precipitated eddish-brown (iron) by solution of soda, white (quinine) by solution of mmonia, blue by the yellow (ferric) and red prussiates (ferrous) of potash, nd greyish-black by tannic acid. The taste is bitter (quinine) as well as halybeate.

DOSE.—5 to 10 grains.

U.S.P. Liquor Ferri et Quininæ Citratis. SOLUTION OF ITRATE OF IRON AND QUININE. (Citrate of iron and ammonium, 5; quinine, 12; citric acid, 28; alcohol, 30; distilled water p to 200.)

DOSE.—8 to 15 minims ($\frac{1}{2}$–1 c.c.).

PREPARATION.

U.S.P.

Vinum Ferri Amarum. BITTER WINE OF IRON. (Solution of citrate of iron nd quinine, 8; tincture of sweet orange peel, 12; syrup, 36; stronger white wine, 4.) Dose 1–2 fl. drs. (4–16 c.c.).

U.S.P. Ferri et Strychninæ Citras. CITRATE OF IRON AND TRYCHNINE.

CHARACTERS.—Transparent garnet-red scales, deliquescent on xposure to air; odourless, having a bitter and slightly ferruginous taste and a slightly acid reaction.

SOLUBILITY.—Soluble in water.

REACTIONS.—If one gm. of the salt be dissolved in 4 c.c. of water in a mall test-tube, then 1 c.c. of solution of potassa added and the mixture haken with 2 c.c. of chloroform, the residue left on evaporating the chloroorm will answer to the reaction of strychnine. (See 'Strychnina.')

DOSE.—3 to 5 grains (0·20—0·33 gm.).

USES.—As **tonic** and chalybeate to combine the uses of trychnine and iron.

U.S.P. Ferri et Ammonii Sulphas. SULPHATE OF IRON AND AMMONIUM. AMMONIO-FERRIC SULPHATE OR AMMONIO-FERRIC ALUM. $Fe_2(NH_4)_2(SO_4)_4.24H_2O$; 963·8.

This is an ammonia iron-alum in which the place of the aluminium oxide is occupied by the ferric oxide.

CHARACTERS.—Pale violet octahedral crystals efflorescent on exposure to air, odourless, having an acid styptic taste and a slightly acid reaction.

DOSE.—5 to 10 grains.

USES.—It is more **astringent** than common alum, and has not the stimulating properties of other iron salts. It is useful in

leucorrhœa. Internally it is sometimes very useful in lessen albumen in cases of intermittent albuminuria.

U.S.P. Ferri Lactas. LACTATE OF IRON. $Fe(C_3H_5O_3)_2.3H_2$ 287·9.

CHARACTERS.—Pale greenish-white, crystalline crusts grains, permanent in the air; odourless, having a mild sweeti ferruginous taste and a slightly acid reaction.

SOLUBILITY.—Soluble in water.

REACTIONS.—When heated on platinum foil the salt froths up, gives thick white acrid fumes, and chars, a brown-red residue being finally left. the salt be boiled for fifteen minutes with nitric acid of the sp. gr. 1·2 white granular mucic acid will be deposited on cooling the liquid.

PREPARATION.

U.S.P. Syrupus Hypophosphitum cum Ferro. (Lactate of iron, 1; syrup hypophosphites, 99.)

DOSE.—12–20 grains per diem; of syrup, ½ to 1 fl. dr.

USE.—In chlorosis and anæmia.

U.S.P. Ferri Oxalas. OXALATE OF IRON. $FeC_2O_4.H_2$ 161·9.

CHARACTERS.—A pale yellow, or lemon-yellow crystalli powder, permanent in the air, odourless and nearly tasteless.

SOLUBILITY.—It is very slightly soluble in cold or hot water, but solu in cold concentrated hydrochloric acid and in hot diluted sulphuric acid.

DOSE.—2 to 3 grains (0·13 to 0·20 gm.).

B. and U.S.P. Syrupus Ferri Iodidi. SYRUP OF IODIDE IRON. FeI_2; 309·1.—It contains 4·3 grains of iodide of iron 1 fluid drachm.

CHARACTERS.—Yellowish or greenish-yellow liquid with a sw inky taste.

DOSE.—½ to 1 fl. dr.

B. and U.S.P. Pilula Ferri Iodidi (*vide* pp. 522, 523). P OF IODIDE OF IRON. Pill with sweet inky taste.

DOSE.—3 to 8 grains.

U.S.P. Ferri Iodidum Saccharatum. SACCHARATED IODI OF IRON.

CHARACTERS.—A yellowish-white or greyish powder ve hygroscopic, odourless, having a sweetish ferruginous taste, a a slightly acid reaction.

DOSE.—2 to 5 grains (0·13–0·33 gm.).

USES.—Iodide of iron is given when a combination of t effect of iodine on the lymphatic system is desired along with t hæmatinic action of iron. It is thus very useful in the form of t syrup in dispensary practice in large towns, where pale, anæm flabby, and scrofulous children abound, and come in lar numbers to be treated. It is generally advantageous to combi

with cod-liver oil, a few drops of the syrup being dropped into e oil and taken along with it. It has been given in phthisis in e same way, and has been found useful in rheumatic arthritis d syphilis.

U.S.P. Syrupus Ferri Bromidi. SYRUP OF BROMIDE OF ON.—A syrupy liquid containing 10 per cent. of ferrous bro-de. $FeBr_2$; 215·5.

DOSE.—½ to 1 fluid drachm (1·9 to 3·75 c.c.).

USE.—In nervous diseases accompanied by anæmia. It is ubtful, however, whether it is not better to give the iron and omine separately, as sufficient bromine cannot be given in this rm. It may, however, be advantageously combined with other omides.

B.P. Ferri Arsenias. ARSENIATE OF IRON.—Arseniate of on, $Fe_3As_2O_8$, partially oxidised.

CHARACTERS.—A tasteless amorphous powder of a green lour.

SOLUBILITY.—It is insoluble in water, but readily dissolved by hydro-loric acid.

REACTIONS.—The solution in hydrochloric acid gives a copious light-blue ecipitate with the yellow prussiate of potash (ferric), and a still more undant one of a deeper colour with the red prussiate of potash (ferrous). small quantity boiled with an excess of caustic soda and filtered gives, en exactly neutralised by nitric acid, a brick-red precipitate on the dition of solution of nitrate of silver (arseniate).

DOSE.—$\frac{1}{16}$ to ½ grain.

USES.—Used when we wish to employ arsenic and iron gether, as in skin-diseases in anæmic subjects.

Ferri Phosphas, B. and U.S.P. PHOSPHATE OF IRON.—hosphate of iron, $Fe_3P_2O_8$, partially oxidated.

CHARACTERS.—A slate-blue amorphous powder.

SOLUBILITY.—It is insoluble in water, soluble in hydrochloric acid.

REACTIONS.—The solution yields a precipitate with both the yellow (ferric) d red prussiates of potash, that afforded by the latter being the more undant (ferrous); and when treated with tartaric acid and an excess of mmonia, and subsequently with the solution of ammonio-sulphate of mag-sium, lets fall a crystalline precipitate (phosphate). When the salt is gested in hydrochloric acid with a lamina of pure copper, a dark deposit es not form on the metal (distinction from and absence of arseniate).

DOSE.—5 to 10 grains.

PREPARATIONS CONTAINING PHOSPHATE OF IRON.

B.P.	DOSE.
yrupus Ferri Phosphatis (freshly-precipitated phosphate (p. 738) is dissolved in dilute phosphoric acid and sugar added) 1 gr. in 1 fl. dr.	...1 fl. dr.

U.S.P.

Syrupus Ferri, Quininæ, et Strychninæ Phosphatum. (Phosphate of iron, 133; inine, 133; strychnine, 4; phosphoric acid, 800; sugar, 6,000; distilled water to 10,000.) This preparation resembles Easton's Syrup.

Uses.—It is used in diabetes, in rickets, and in nervous
pression. It is frequently given along with the phosphate
calcium, potassium, and sodium, as the preparation usu
called Parrish's Chemical Food, or with the phosphates
quinine and strychnine, as in Easton's Syrup.

U.S.P. Ferri Pyrophosphas. Pyrophosphate of Iron.

Characters.—Thin, apple-green, transparent scales, per
nent in dry air when excluded from light, but turning dark
exposure to light. Odourless, having an acidulous, slightly sa
taste, and a slightly acid reaction.

Solubility.—Very soluble in water.

Reactions.—When heated with solution of potassa in excess a brown
precipitate is thrown down, and the filtrate, after being supersaturated
acetic acid, yields a white precipitate with test solution of nitrate of si
(difference from phosphates).

Dose.—2 to 5 gr. (0·13 to 0·33 gm.).

Uses.—Has no disagreeable taste, and is very soluble, so t
it can be given in any form.

U.S.P. Ferri Hypophosphis. Hypophosphite of Iron
$Fe_2(H_2PO_2)_6$; 501·8.

Characters.—A white or greyish-white powder, perman
in the air, odourless and nearly tasteless.

Solubility.—It is only slightly soluble in water, more readily so in
sence of hypophosphorous acid, freely soluble in hydrochloric acid, or
solution of citrate of sodium, forming with the latter a green solution.

Reactions.—When strongly heated in a dry test-tube, the salt evolv
spontaneously inflammable gas (phosphoretted hydrogen), and on ignit
leaves behind ferric pyrophosphate. The salt is readily oxidised by ni
acid or other oxidising agents. It should be completely soluble in ac
acid (absence of ferric phosphate). This solution, when mixed with t
solution of oxalate of ammonium, should not afford a white precipit
soluble in hydrochloric acid (absence of calcium).

Dose.—5 to 10 grains in pill, more generally given in syr

Uses.—In nervous debility with anæmia, and also in phthis

U.S.P. Ferri Valerianas. Valerianate of Iron.—
$(C_5H_9O_2)_3$; 717·8.

Characters.—A dark tile-red amorphous powder, permane
in dry air, having a faint odour of valerianic acid, and a mil
styptic taste.

Solubility.—Insoluble in cold water, but readily soluble in alcohol.

Reactions.—Boiling water decomposes it, setting free the valerianic a
and leaving ferric hydrate. When slowly heated the salt parts with its a
without fusing, but when rapidly heated it fuses and gives off inflamma
vapours having the odour of butyric acid.

Dose.—1 grain or more.

Uses.—In hysteria with anæmia.

MANGANESE. Mn ; 55.

Manganesii Oxidum Nigrum, B.P. ; Mangani Oxidum Nigrum, U.S.P. Black Oxide of Manganese.—Native crude oxide of manganese containing at least 66 of the pure oxide. MnO_2; 86, U.S.P.

Characters.—A heavy black powder.

Solubility and Reactions.—Dissolves almost entirely in hydrochloric acid with evolution of chlorine, and gives off oxygen when heated to redness.

Uses.—Used for producing chlorine, and for making oxygen. It has been used instead of bismuth in pyrosis and irritable conditions of the stomach, with pain after eating; and instead of iron in debilitating diseases, anæmia, syphilis, scurvy, and in skin-diseases.

U.S.P. Mangani Sulphas. Sulphate of Manganese.—$MnSO_4.4H_2O$; 222.

Characters.—Colourless or pale rose-coloured, transparent slight rhombic prisms, odourless, having a slightly bitter and astringent taste, and a faintly acid reaction.

Solubility.—Soluble in water.

Reactions.—The aqueous solution of the salt yields, with sulphide of ammonium, a flesh-coloured precipitate completely soluble in moderately diluted acetic acid (absence of zinc); with test-solution of ferro-cyanide of potassium it affords a reddish-white precipitate, and a brown one with test-solution of ferricyanide of potassium.

Action of Manganese Salts.—When injected into the blood, or subcutaneously, manganese salts **paralyse** voluntary movement and reflex action, and stop the **heart** in diastole. The paralysis of reflex action is due to destruction of the transverse conduction of the **spinal cord** (p. 161), longitudinal conduction remaining intact until death (Kobert). Proto-sulphate produces purging in doses of 1 to 2 drms., and, in consequence of Gmelin's experiments, has been thought to increase the secretion of bile.

Uses.—Has been used in place of iron in anæmia, but without good results. Possibly it may be serviceable in amenorrhœa.

Potassii Permanganas, B.P. and U.S.P.—*Vide* p. 614.

Class VIII.

Group II.—Gold, Platinum.

AURUM ; GOLD. Au ; 196·2.

B.P. Gold, Fine. Gold, free from Metallic Impurities.

Gold foil is used for stopping teeth and to make the test solution.

B.P. Solution of Chloride of Gold.

PREPARATION.—By dissolving gold foil in a mixture of nitric and hy chloric acids and diluting.

U.S.P. Auri et Sodii Chloridum. CHLORIDE OF GOLD SODIUM.

A mixture composed of equal parts of dry chloride of g $AuCl_3$; 302·4; and chloride of sodium, NaCl; 58·4.

CHARACTERS.—An orange-yellow powder, slightly deliques in damp air, odourless, having a saline and metallic taste an slightly acid reaction.

SOLUBILITY.—The compound is very soluble in water; at least one of it should be soluble in cold alcohol.

REACTIONS.—When exposed to a red heat it is decomposed and met gold is separated. A fragment of the compound imparts an intense sistent colour to a non-luminous flame.

PREPARATION.—By dissolving gold in nitro-hydrochloric acid and evapo ing to dryness, chloride of gold is obtained. This is dissolved in water, mixed with its own weight of pure decrepitated common salt also dissol in water. The mixed solution is then evaporated to dryness.

DOSE.—$\frac{1}{10}$ to $\frac{1}{5}$ grain (·006–·012 gm.), once or twice a da

ACTION.—Salts of gold cause rapid **paralysis** of the cen nervous system in frogs, which appears to affect first the o lobes and cerebellum, then the cord, and lastly the cerebral lo (*vide* p. 183 *et seq.*). In mammals small doses appear to incre the appetite; larger ones cause symptoms of irritation in **stomach** and **intestines**, viz. loss of appetite, diarrhœa, emaciation, followed by paralysis of the limbs, a catarrhal co tion of the **respiratory** passages, and death by asphyxia. La doses injected into the veins cause œdema of the **lungs**, rapid death, with convulsions, from asphyxia. In man they said to increase the **secretions**, and to produce salivation mercury, but without stomatitis. They are **eliminated** in urine.

USES.—Salts of gold have been supposed to act like thos mercury and silver. They have been given like mercurial s in syphilis, scrofula, and cancer; and, like silver salts, h been used in myelitis. Gold has been supposed to act specific on the genital organs, and has been used in chronic uterine flammation and irritation, and inflammation and neuralgia the ovaries.

PLATINUM. Pt; 197.

B.P. Platinum Foil.

A heavy whitish metal Sp. gr. 8·921. Withstands considera heat. The foil is convenient for holding salts of organic ac which it is wished to char.

B.P. Solution of Perchloride of Platinum. $PtCl_4$; 33

PREPARATION.—By dissolving thin platinum foil in a mixture of ni acid and hydrochloric acid and diluting.

USES.—Used to distinguish potassium from sodium and to ecipitate salts of ammonium, and of compound ammonias, . organic alkaloids.

ACTION.—Soluble salts of platinum are as poisonous as enic. In frogs they appear to paralyse the centres for volun- y motion in the cerebral lobes, and irritate the motor centres ween them and the cord, so that voluntary motion is dimi- hed, but reflex convulsions occur. The excitability of voluntary iscle is much lessened, that of the heart is not apparently ered. In **mammals** the most prominent symptom is paralysis the peripheral ends of the **vaso-motor nerves.** In conse- ence of this, diarrhœa, blood in the motions, hyperæmia of the dominal viscera, and ecchymoses of the mucous membrane of stomach and intestine and bladder occur.

B.P. Platinum Black.

PREPARATION.—Platinum in a state of minute division, obtained by adding ss of carbonate of sodium and some sugar to solution of perchloride of inum, and boiling until a black precipitate is formed, which is washed dried.

ACTION.—Platinum-black appears to have a greater power n even charcoal to condense gases, and especially oxygen, in pores. By giving the oxygen off again it acts as an oxidising nt.

USE.—To test amylic alcohol by oxidising it into valerianic l.

SECTION IV.

ORGANIC MATERIA MEDICA.


This Section contains Organic Compounds artificially prepared, nd not merely extracted from Vegetable Substances containing em. Although it is small, it contains some of the most important emedies we possess, and in the future will probably replace to a reat extent, and perhaps entirely, the Vegetable Materia Medica.

CHAPTER XXIX.

CARBON COMPOUNDS—FATTY SERIES.

RBON is a tetrad element. It is sometimes represented graphi-

lly thus: —C—. It combines with four atoms of a monad, or



o of a dyad element, e.g. H—C—H or , or it combines


th one atom of a triad and one of a monad, H—C—N. It

so unites with itself, and the complex molecules thus formed mbine with other elements or radicals. Thus the number of s compounds is almost endless.


These compounds are divided into two great series, according the mode in which the atoms are linked.

We have thus in Inorganic Chemistry two great series, the etalloids and metals, and in Organic Chemistry two great series, e fatty and the aromatic.

Series of Carbon Compounds.—In the first, or **fatty** series, e carbon atoms are supposed to be linked so as to form an pen chain, e.g.:



In the second, or **aromatic** series, the carbon atoms are sup- osed to be linked so as to form a **closed** chain.



Some of the simpler compounds of carbon have already be considered—carbonic acid, CO_2 (p. 583), hydrocyanic acid, HC (p. 585), acetic acid, $C_2H_4O_2$ (p. 577).

GENERAL ACTION.—It will be noticed that compounds carbon with hydrogen alone, as in the hydrocarbons of t marsh-gas series; with oxygen alone, as in carbonic acid, CO with sulphur alone, as in bisulphide of carbon, CS_2; or wi chlorine alone, as in tetrachloride of carbon, CCl_4, all tend **paralyse** the **nervous system**, and to destroy the function activity of its various parts in a definite order. Thought fa first, next sensation, and next reflex action (p. 206).

The compounds with hydrogen have a comparatively slig action on **muscle**, but those containing chlorine are mo powerful muscular poisons, and destroy the contractility of mu cular fibre, both voluntary and involuntary.

Many compounds containing oxygen in addition to carb and hydrogen have an **anæsthetic** action, e.g. alcohol and ethe others, like acetic acid, have a strongly irritant action. Co pounds of carbon with nitrogen, hydrogen, and oxygen may ha a very complicated chemical constitution, and, as in the organ alkaloids, have physiological actions which are too varied a specialised to allow of their being classed at present under general law.

U.S.P. Carbonei Bisulphidum.—BISULPHIDE OF CARBO CS_2; 76.—Bisulphide of carbon should be kept in well-stopp bottles, in a cool place, remote from lights or fire.

CHARACTERS.—A clear, colourless, highly refractive liqui very diffusive, having a strong, characteristic odour, a shar aromatic taste, and a neutral reaction.

SOLUBILITY.—It is insoluble in water; soluble in alcohol, ether, chlor form, and fixed or volatile oils.

REACTIONS.—Specific gravity 1·272. It vaporises abundantly at ordina temperatures, is highly inflammable, boils at 46° C. (114·8° F.), and, wh ignited, burns with a blue flame, producing carbonic and sulphurous acids.

It should not affect the colour of blue litmus-paper moistened with wat (absence of sulphurous acid). A portion evaporated spontaneously in a gla vessel should leave no residue (sulphur). Test-solution of acetate of le agitated with it should not be blackened (absence of hydrosulphuric acid).

ACTION.—When inhaled it is a rapid, powerful, but transie anæsthetic.

USES.—It can be used to produce local **anæsthesia** by atom sation. It has been employed as a local **irritant** in enlarg lymphatic glands, neuralgia, and deafness accompanied by i sufficiency of wax; and has been given as an internal **antisept** in enteric fever, in the form of a mixture with water and peppe mint oil.[1]

[1] Dujardin-Beaumetz, *Bull. Gén. de Thérap.*, Août, 1885, p. 97.

FATTY SERIES.

HYDROCARBONS.

The chemical nature of a carbon compound depends on the rangement of its constituent atoms, but in its physical cha- cters on the number of the atoms.

The **physical character** of a compound greatly influences its ysiological action, a gaseous body being more easily absorbed d excreted than a liquid, and a liquid more easily than a solid. here will also be differences amongst the gaseous, liquid, and lid bodies themselves, for if a liquid, for example, has a low iling-point so as to volatilise readily at ordinary temperatures, will more resemble a gas in its action, while a liquid which has high boiling-point will act more like a solid.

Thus in the group of hydrocarbons belonging to the paraffin ries the lowest members are gaseous at ordinary temperatures, e highest members form solid wax-like bodies, while those hich are intermediate are liquid. Obviously we cannot expect gas which can be inhaled in large quantities, and which will quickly excreted when pure air is inhaled instead, to have e same action as a solid wax-like substance which can only be owly absorbed, and slowly excreted or broken up in the ganism.

The **boiling-point** of substances belonging to a series differs mewhat according to the chemical nature of the substance, but nongst the members of the series having the same chemical ture it rises with the number of atoms. It will be seen from e accompanying table that the boiling-point differs according the series, e.g. that of chlorides is lower than that of bromides; is, again, is lower than that of iodides. In each series also chlorides, bromides, or iodides, the boiling-point rises with e number of carbon atoms which the member of the series ntains.

As the action of substances depends so much on their vola- lity, it may be convenient to give here the boiling-points of the rious members of the paraffin series (p. 762).

Physiological Action of Hydrocarbons belonging to the arsh-Gas Series.—These hydrocarbons may be regarded as ydrides of the radicals, methyl, &c. Those low in the series— ethane, ethane, propane, and butane—are permanent gases at dinary temperatures, and when inhaled pure produce anæs- esia much like that of nitrous oxide. The intermediate fluid embers of the series, e.g. pentane, and substances containing em, as benzin, petroleum oil, &c., give off vapour having an næsthetic action somewhat like that of chloroform.

Radical	Chloride, $C_nH_{2n+1}Cl$.	Bromide, $C_nH_{2n+1}Br$.	Iodide, $C_nH_{2n+1}I$.	Hydride, $C_nH_{2n+1}H$.	Alcohol, $C_nH_{2n+1}OH$.	Aldehyde, $C_nH_{2n}O$.	Ether
Methyl, CH_3 . .	...	...	40°	Gas.	66·0°	...	Gas.
Ethyl, C_2H_5 . .	12·5°	39°	72°	Gas.	78·4°	20·8°	35°
Propyl, C_3H_7 . .	46·4°	71°	102°	Gas.	97·4°	48·8°	85°
Butyl, C_4H_9 . .	77·6°	100·4°	129·6°	1°	116·9°	58°	140°
Amyl, C_5H_{11} . .	105·6°	128·7°	153·4°	38°	138°	92·5°	163°
Hexyl, C_6H_{13} . .	...	...	179·4°	70°	158°	127·9°	205°
Heptyl, C_7H_{15} . .	...	...	...	99°	176°	150°	...
Octyl, C_8H_{17} . .	108°	199°	221°	124°	192°	...	281°
Dodecyl, $C_{12}H_{25}$.	...	...	...	202°	...	...	...
Hexdecyl, or Cetyl, $C_{16}H_{33}$ . .	...	...	...	278°	...	...	300° Melting point 55°

The higher members of the series are solid at ordinary temperatures, and are used as a basis for ointments under the name of petrolatum, vaseline, cosmoline, &c.

U.S.P. Benzinum. Benzin. Petroleum Benzin. Petroleum Ether.—A purified distillate from American petroleum consisting of hydrocarbons, chiefly of the marsh-gas series [C_5H_{12}; C_6H_{14}, and homologous compounds], having a specific gravity from 0·670 to 0·675, and boiling at 50° to 69° C. (122° to 140° F.).

Benzin should be carefully kept in well-stoppered bottles or cans, in a cool place, remote from lights or fire.

Characters.—A transparent, colourless, diffusive liquid, of strong, characteristic odour, slightly resembling that of petroleum, but much less disagreeable; neutral in reaction. It is highly inflammable, and its vapour, when mixed with air and ignited, explodes violently.

Solubility.—It is insoluble in water, soluble in about 6 parts of alcohol and readily so in ether, chloroform, benzene, and fixed and volatile oils.

Reactions.—Benzin, when evaporated upon the hand, should leave no odour, and when evaporated in a warmed dish should leave no residue (absence of heavy hydrocarbons). When boiled a few minutes with one-fourth its volume of spirit of ammonia and a few drops of test-solution of nitrate of silver, the ammoniacal liquid should not turn brown (absence of pyrogenous products, and sulphur compounds); and it should require 6 parts of officinal alcohol to dissolve it (difference from benzene). If five drops are added to a mixture of 40 drops of sulphuric acid with 10 drops of nitric acid, in a test-tube, the liquid warmed and set aside for half an hour, and then diluted, in a shallow dish, with twice its volume of water, it should not have the bitter almond-like odour of nitro-benzene (absence of benzene).

Dose.—As a vermifuge, 30 minims.

Uses.—It is a good **solvent** for fats, resins, caoutchouc, and some of the alkaloids. It has been used externally as a **sedative**

prurigo and other cutaneous diseases, and to relieve the itching in urticaria, and internally as a **vermifuge** for tape-worm.

U.S.P. Petrolatum. PETROLATUM. [PETROLEUM OINTMENT, ASELINE.]—A semi-solid substance, consisting of hydrocarbons, hiefly of the marsh-gas series, $C_{16}H_{34}$, &c., obtained by distilling f the lighter and more volatile portions from American petroum, and purifying the residue. Melting-point about 40° C. to 1° C. (104° F. to 125° F.), the first constituting the softer, and e second the firmer variety.

When petrolatum is prescribed or ordered, without specifying s melting-point, the low-melting variety, which liquefies at bout 40° C. (104° F.), is to be dispensed.

CHARACTERS.—A yellowish or yellow, fat-like mass, transarent in thin layers, more or less fluorescent, especially when elted, completely amorphous, tasteless and odourless, or giving f, at most, only a faint petroleum odour when heated, and aving a neutral reaction. When gently heated, until the mass almost entirely melted, the liquid portion has a specific ravity varying from 0·835 to 0·860.

SOLUBILITY.—It is insoluble in water, scarcely soluble in alcohol, or in old absolute alcohol, but soluble in 64 parts of boiling absolute alcohol, and adily soluble in ether, chloroform, bisulphide of carbon, oil of turpentine, enzin, benzene, and in fixed or volatile oils.

REACTIONS.—When heated on platinum foil, it is completely volatilised ithout emitting the acrid vapours of burning fat or resin. If 5 gm. of etroleum ointment be digested, for half an hour, with 5 gm. of soda and 25 m. of water, the aqueous layer separated, and supersaturated with dilute lphuric acid, no oily substance should separate (absence of fixed oils or fats vegetable or animal origin, or of resin). Liquefied petroleum ointment gitated with sulphuric acid of specific gravity 1·540 should not acquire a dark olour within two hours (absence of readily carbonised organic impurities).

B.P. Paraffinum Durum. HARD PARAFFIN. *Synonyms:* ARAFFIN; PARAFFIN WAX; SOLID PARAFFIN.

A mixture of several of the harder members of the paraffin eries of hydrocarbons; usually obtained by distillation from hale, separation of the liquid oils by refrigeration, and purification of the solid product.

CHARACTERS.—Colourless, semi-transparent, crystalline, inodorous and tasteless, slightly greasy to the touch. Specific ravity, 0·82 to 0·94.

SOLUBILITY.—Insoluble in water, slightly soluble in absolute alcohol, reely soluble in ether.

REACTIONS.—It melts at 110° to 145° F. (43·3° to 62·8° C.), and burns ith a bright flame, leaving no residue.

PREPARATIONS.

Unguentum Acidi Borici.
" " Carbolici.
" " Salicylici.
" Eucalypti.
" Glycerini Plumbi Subacetatis.
Unguentum Hydrargyri Oxidi Rubri.
" Potassæ Sulphuratæ.
" Sulphuris Iodidi.
" Veratrinæ.

B.P. Paraffinum Molle. Soft Paraffin. *Synonyms:* Petrolatum; Pétroleine; Unguentum Paraffinum.

A semi-solid mixture containing some of the softer or mo fluid members of the paraffin series of hydrocarbons; usual obtained by purifying the less volatile portions of petroleum. is known in commerce by various fanciful names.

Characters.—White or yellowish, translucent, soft, greas free from acidity, alkalinity, or any unpleasant odour or flavo even when warmed to 120° F. (48·9° C.). Specific gravity at t melting-point, from about 0·840 to 0·870. Melts at 95° to 10 F. (35° to 40°·5 C.), or even somewhat higher, volatilises witho giving acrid vapours, and burns with a bright flame, leaving residue.

Solubility.—Insoluble in water, slightly soluble in absolute alcoh freely soluble in ether, chloroform, benzene, &c.

Reactions.—It is not saponified by solutions of alkalis.

Preparations.

Unguentum Acidi Borici.
" " Carbolici.
" " Salicylici.
" Eucalypti.
" Glycerini Plumbi Subacetatis.
Unguentum Hydrargyri Oxidi Rubri.
" " Nitratis Dilutu
" Potassæ Sulphuratæ.
" Sulphuris Iodidi.
" Veratrinæ.
" Zinci Oleati.

Uses.—These hydrocarbons, which are not liable to becor rancid, have been found very useful as a bland protection, and a substitute for animal and vegetable fats in the preparation ointments.

ALCOHOLS.

Alcohols of the Series $C_2H_{2n+1}OH$.—These may be garded as hydrates of the radicals. They differ from the hydri by the radical being united in them to hydroxyl, HO, instead to hydrogen. The most important of them are:—

Methyl alcohol, CH_4O. Wood spirit.
Ethyl alcohol, C_2H_6O. Spirit of wine.
Propyl alcohol. C_3H_8O.
Amyl alcohol, $C_5H_{12}O$. Fusel oil or potato spirit.

General Action.—These alcohols have all a toxic acti when given in sufficiently large doses. The general effect th produce on the organism appears to be much the same in a viz. **paralysis** affecting the **nerve-centres** in the inverse ord of their development. Their lethal power and the symptor they produce are modified by their physical characters, su as their solubility in water, and their volatility; for if they a not readily soluble in water they cannot be readily absorbe and probably will not be readily excreted. Their **toxic pow** increases with their atomic weight, so that a less quantity of t higher alcohols will produce death. This is shown in the f lowing table by Dujardin-Beaumetz. It will be noticed, ho

ver, that the lowest term and also the higher terms of the series rm exceptions. This may possibly be due to rapid absorption compared with excretion (p. 39) in the case of methylic alcohol, and to slow absorption in the case of œnanthic and caprylic cohols :—

	Kind of Alcohol	Mean toxic dose in grammes per kilogramme weight of the animal	
		Pure	Diluted
Non-fermented	Methylic Alcohol, CH_4O	...	7·0
Fermented	Ethylic ,, C_2H_6O	8·0	7·75
	Propylic ,, C_3H_8O	3·9	3·75
	(Isopropylic) ,, (C_3H_8O)	...	(3·7 to 3·8)
	Butylic ,, $C_4H_{10}O$	2·0	1·85
	Amylic ,, $C_5H_{12}O$	1·7	1·50
Non-fermented	Œnanthic ,, $C_7H_{16}O$	8·0	...
	Caprylic ,, $C_8H_{18}O$	7· to 7·5	...

All the alcohols produce **symptoms** which are divided by ujardin-Beaumetz into three stages, the first of which corresponds to the first and second stages of action I have given at . 206, and his second and third corresponding to the third and urth of mine respectively. These stages are **modified by** (*a*) he kind of alcohol used, (*b*) its quantity, and (*c*) the resistance f the subjects.

Ethylic alcohol has the most typical action, and in poisoning y it all the stages succeed one another in regular order. In the ase of the other alcohols obtained by fermentation the stages re also regular, but the farther the alcohol is from ethylic, the ss regular do the stages become. They succeed one another ore rapidly, their character is less marked, and convulsive henomena appear.

In the case of **methylic** alcohol, the excitement is greater, the ubsequent stages succeed one another more quickly, and reach eir acme sooner ; but if the dose be insufficient to cause death, he effects pass off more quickly.

In the case of **œnanthic** and **caprylic** alcohol, the stages do ot present the same regularity, and convulsions occur.

All the alcohols now mentioned **lower** the **temperature.**

On *post-mortem* examination after acute poisoning by alcools, the blood, stomach, intestines, liver, lungs, and kidneys are ound to be affected. It is possible, however, that some of these **esions** are not to be regarded as specific consequences of the ction of alcohol, but rather as due to the **death by asphyxia** hich ensues from the respiratory paralysis. The blood is of a ark colour, and forms clots in the heart. When the alcohol is iven **by the mouth**, the **stomach** and **intestine** are much ongested and softened, the congestion being greater when

the alcohol is undiluted. When the alcohol is injected sub**cutaneously**, the stomach is little altered, but the **intestin** is congested, the congestion being probably due, according t Dujardin-Beaumetz, to elimination of the alcohol by the intes tinal mucous membrane. The **liver** is the gland most affecte It is congested, soft, and friable. The **spleen** is also gorge with blood, and soft. The lungs are congested with sma extravasations, which are most abundant when the alcohol ha been given by the mouth. Hæmorrhages are observed in th **kidneys**, especially in the case of the non-fermented alcohols.

Methyl Alcohol. CH_3OH; Wood Spirit. *Synonyms:* Car binol, Hydroxymethane, Methol. Not officinal.

Characters.—A colourless, mobile liquid. When pure it ha a taste and smell somewhat like ethyl alcohol; but ordinar wood spirit contains many impurities which give it a disagreeabl odour and burning taste.

Preparations.—By destructive distillation of wood, and neutralisatio and repeated distillation of the product.

Uses.—The admixture of wood spirit with alcohol render the latter so disagreeable as to unfit it for drinking, so that i can be sold under the name of methylated spirit as a solven and for other uses in the arts, without interfering with the dutie on potable alcoholic drinks.

Alcohol Ethylicum, B.P. $C_2H_5.OH$. Ethyl Alcohol Absolute Alcohol.

Characters.—Colourless and free from empyreumatic odour Sp. gr. 0·797 to 0·800. Containing 1 to 2 per cent. of water, B.P

General Source and Preparation.—Alcohol is prepared from solution of maltose by adding to them a ferment, which causes the sugar to split u into alcohol and carbonic acid.

The solutions of maltose which yield alcohol are generally prepared fro malt. This is made by steeping barley for a while in water till it begins to ger minate. The barley when fresh contains starch and a ferment termed diastase which converts the starch into maltose during the process of germination.

When this has gone far enough, as is ascertained by the radicle attainin a certain length, the process is stopped by roasting the malt, as the suga would all be used up again by the plant if it were allowed to continue it growth. The malt is then infused in warm water, and the solution of maltos which it yields is fermented by yeast, a small fungus which causes the suga to split up and yield alcohol. The alcohol thus obtained is very muc diluted with water, and in order to separate them the liquor is distilled, whe the alcohol passes over first, and the greater part of the water is left behind.

Reactions.—Entirely volatilised by heat. Not rendered turbid by mixin with water, and does not cause anhydrous sulphate of copper to becom decidedly blue on shaking.

General Impurities.—Water, fusel oil, and aldehyde. The water ma have come to be present either as an accidental impurity or as an intentiona adulteration. One of the most important impurities of alcohol is the presenc of organic alkaloids. A good deal of spirit is made from spoiled grain maize, &c., which cannot be used for food. In diseased grain alkaloids ar formed, and these appear to pass over with the alcohol during distillation

TESTS.—Water is detected by the use of the hydrometer, as any admixture water with alcohol raises the specific gravity of the latter.

The presence of oily, fatty, or resinous substances in alcohol is recognised diluting it with water, when these substances, being insoluble in weak irit, are precipitated and render the solution turbid.

Traces of fusel oil and aldehyde are almost always present, and they are ckoned as impurities by the B.P. only when they rise above a certain nount. The quantity of them present in alcohol is determined by adding 4 oz. of it 30 grain-measures of standard solution of nitrate of silver and posing it to the sunlight for twenty-four hours. The nitrate of silver is oxidised by these substances and a black precipitate consisting of oxide of some organic compound is deposited.

GENERAL ACTION OF ALCOHOL.—When alcohol is added in fficient quantity to **albuminous** solutions it precipitates them, parently simply by withdrawing the water from them, because hen water is added to the freshly-precipitated albumin it redis-lves easily. When, however, the precipitate is kept for some me in alcohol it loses its solubility, and is no longer redissolved water. Peptones are, however, uncoagulated by long standing nder alcohol. When applied to the **skin**, alcohol evaporates adily, and gives rise to a sensation of cold. It renders the epider-is drier and harder, and if kept in contact with the skin, evapora-on being prevented, it passes through the epidermis, and, acting on the tissue below, stimulates it, causing an increased supply blood to the part, and producing a feeling of warmth or burn-g. A similar action takes place when it is applied to a mucous embrane, e.g. when taken into the **mouth**. It here produces slight precipitate of albumin on the surface and acts as an tringent, drawing the parts slightly together, and forming on e surface a whitish pellicle, which, however, rapidly disappears. causes considerable reflex secretion of saliva. When taken to the **stomach** in small quantities, it has a similar action on at organ, causing increased vascularity and increased secretion, companied by a feeling of warmth, and it excites a feeling of petite, for which purpose it is taken by some persons before eals. It aids the expulsion of flatulence from the stomach and testines. In cases of diarrhœa it has a somewhat astringent tion in the **intestine**, but in persons accustomed to take cohol to excess the bowels are always rather loose, constipation curring very rarely, if at all.

After absorption into the **blood**, it appears to form a com-und with hæmoglobin, which takes up and gives off oxygen ss readily than hæmoglobin itself (Schmiedeberg). It thus ssens the oxidising power of the blood, and will, consequently, minish oxidation in the **tissues**.

Considerable dispute has arisen as to whether alcohol is a od or not. The chief argument in favour of its not being a od is that it is eliminated in the urine unchanged, but this ems to occur only when it is given in considerable quantities. small doses it is partly **eliminated** by the breath, but most of

it appears to undergo combustion in the body, and very little it passes out in the urine. In this respect it agrees with oth foods, such as cane-sugar. Hammond found that when insufficient diet he was losing weight, the addition of a lit alcohol not only enabled him to reach his former weight, but add to it.

The argument in favour of alcohol being a food is that it retained in the body, and supplies the place of other foods, that the quantity of food which would without it be insufficie with its aid becomes sufficient.

The conclusion to which all the evidence points is th alcohol is a food, and in certain circumstances, such as feb conditions, it may be a very useful food; but in health, wh other kinds of food are abundant, it is unnecessary, and, as interferes with oxidation, it is an inconvenient kind of food.

After its absorption into the **circulation** it causes dilatat of the vessels on the surface of the body, and increases t rapidity of the pulse. From the freer circulation which th takes place in the capillaries of the surface, the skin of the fa and hands becomes more flushed. The blood flows so fre from the arteries into the veins that there is no longer time it to become completely venous in its passage. In consequen of the capillaries being dilated, the skin is no longer mottl but of a uniformly pink colour. The veins are distended; th fill more rapidly when emptied, and are of a lighter blue th usual, owing to the blood they contain being more arterial.

The action of alcohol upon the **temperature** seems to depe upon two factors. One of these is its power of lessening oxidati but this only comes into consideration with large doses, wh this factor may aid considerably in reducing the temperatu The other factor is the dilatation of the vessels on the surfa (p. 419), which occurs even after moderate doses. This dilatat allows the warm blood from the interior of the body to circul more readily near the surface, and thus subjects it to the cooli influence of the surrounding air, and also to the cooling effect evaporation from the skin. By increasing the sweat it m lessen the temperature of the body, even when that of the s rounding air is as high or higher than it, and it will also c the blood by freer radiation when the temperature of the atm sphere is below that of the body. It is evident that the cooli effects of alcohol will thus depend to a great extent on t atmospheric conditions of temperature and moisture to wh the person taking it is subjected, as well as on the quantity alcohol. Normally, when a person is subjected to cold, t vessels of the skin contract and prevent the warm blood in t interior of the body from approaching the surface and thus coming cooled; but when large quantities of alcohol are take this mechanism becomes paralysed, the blood from the inter

culates over the surface, and is cooled down more and more til its temperature becomes so much reduced as to be incompatible with life, and the patient is frozen to death. The dangerous ects of alcohol under such circumstances are well known to the mberers in Canada, and to Arctic voyagers, who dread alcohol, d generally avoid it altogether. The utility of this selfsame tion of alcohol is very evident when a person comes from the ld atmosphere into a warm room; for here the individual may ll remain cold, although in front of a fire, as the contraction the surface vessels now continues, and the blood is no longer le to convey warmth to the interior, just as it was formerly able to convey the cold. If alcohol be now taken, and the ssels dilated, the blood is allowed to circulate in the surface, n becomes warm, and thus diffuses the warmth equally rough the body.

In considering the action of alcohol upon the **nervous system**, one must distinguish between the effect it produces upon various nerve-centres by increasing the circulation through m, and the effect of the alcohol on the nervous structures mselves. By increasing the circulation it may stimulate the nctions of all the nerve-centres, and render them, for the time ng, capable of greater activity. It may thus enable its consumer to think more clearly, to express himself more fluently, or perform feats of greater bodily activity than usual, but its ion on the nerve-centres themselves is a paralysing one.

The mode of action of alcohol on the circulation has not been l ascertained; but it seems probable that in considering it we st take into account both its direct action upon the circulatory apparatus itself and its reflex action upon that through er organs. Thus it is not improbable that even from the uth it exercises an influence over the **cranial circulation** 193). Although we have no experiments on the effect of tation of the branches of the fifth nerve on the cranial circulation, yet individuals of all nations, when desiring to think re accurately, are accustomed to irritate some branch of this ve, either by scratching the head, rubbing the forehead or n, striking the nose or taking snuff. Chewing sweet or pungent substances has a similar effect in enabling some persons to nk more clearly, while, under similar circumstances, alcohol sipped by others. From the stomach it probably stimulates heart and vascular system reflexly, and thus increases both cranial and the general circulation. When given in very ge doses, as when a bottle of whiskey has been drunk at a ught, the reflex action on the heart has been so great that th has occurred immediately from shock.

Its action upon the **nervous tissues** themselves seems to be of progressive paralysis, affecting them in the inverse order their development, the highest centres being affected first,

and the lowest last. Thus the power of **judgment** usually g first, while the imagination may be lively, and the **emoti** even more than usually active, so that, after a man beco incapable of discussion, he is combative, affectionate, or lach mose. The **motor centres** may be next affected, either afte before the perceptive centres, so that the **speech** may be unc tain and thick while the power of judgment is little affected the speech may remain tolerably distinct after the power clear conception is entirely gone. The **cerebellum** appear be affected sometimes before and sometimes after the cerebr This depends partly upon the constitution of the individual, partly upon the quality of the alcoholic liquor. The affectio the cerebellum gives rise to double vision and inability to w from the relations of surrounding objects being no longer rectly perceived. After both cerebrum and cerebellum paralysed, the **cord** may still retain its functional activity that the man who cannot walk may be able to ride, owing to reflex contraction of the adductors produced by the impres of the saddle. The **respiratory centre** is next paralysed, if quantity taken be sufficiently large. The **heart** continues beat although the respiration may be paralysed; but if a su cient dose of alcohol be administered, and respiration be k up artificially in an animal, so as to allow the drug to act u the heart, the cardiac ganglia may also become paralysed.

The sensibility of the **vaso-motor centre** to reflex imp sions appears to be early destroyed, and the consequence of is that injuries which in a sober man would produce death shock, have comparatively little effect on a man who is drunk

The **diagnosis** of drunkenness from opium-poisoning from apoplexy is of great practical importance, for it occasion happens that cases brought into hospital by the police have b dismissed as cases of drunkenness, and have proved afterwa to be cases of apoplexy. The difficulty of diagnosis is increase the fact that the patient may have had alcoholic drinks pou down his throat by sympathetic bystanders, so that the indication of drunkenness, viz. the smell of alcohol in breath, may occur equally in apoplexy. The other chief po of diagnosis are given under ' Opium ' (p. 848).

Effect of Impurities on the Action of Alcohol.—It be seen by the annexed table from Dujardin-Beaumetz that toxic action of alcohol is greatly increased by impurities, so inferior brandy from a public-house has a lethal action ne one-half greater (as 5·30 to 7·75) than pure ethylic alcohol.

Chronic Alcoholic Poisoning.—In persons who are ac tomed to take an excessive quantity of alcoholic stimulants f length of time, although perhaps never sufficient to produce symptoms of acute intoxication, alterations are produced in digestive and nervous systems. One of the commonest evide

Toxic Action of Alcohol.

Kind of Spirit	Mean toxic doses per kilogramme of body-weight of dog, to cause death in 24–36 hours		
	Spirits and Brandies	Crude	Rectified
	grammes	grammes	grammes
Ethylic alcohol	7·75	...	...
Spirit of wine of Montpellier	7·50	...	...
„ „ from pears	7·35	...	...
„ „ from cider and from the marc of grapes	7·30	...	...
Spirit from grain	...	6·96	7·25
„ from molasses and beetroot	...	6·90	7·15
Brandy from a public-house (ordinary quality)	7·0	...	...
„ „ „ (inferior quality)	5·30	...	...
Spirit from potatoes	...	6·85	7·10
„ „ „ (said to have been ten times rectified)	...	...	7·35

this condition is **vomiting** of watery fluid in the morning mediately after rising. The **bowels** are rarely, if ever, con-pated, being generally open three or four times daily. There a tendency to fatty degeneration of various organs, the **skin** quires a satiny feeling, and the capillaries on the surface of e face often become prominently dilated, giving a character-ic hue to the complexion, which is often especially marked on the nose. The **liver** is apt to undergo fatty degeneration, d, at first, to be congested. Afterwards, the connective tissue comes increased, the organ contracts, interfering with the culation in the abdominal viscera, and producing ascites. is may be complicated by cirrhosis of the **kidney** also. The **rvous system** may also be affected, the mental powers be-ming impaired, the temper, at the same time, frequently being itable, while a tremulousness appears in the tongue, lips, and nds.

When those accustomed to indulge freely in stimulants are acked by acute disease, or when they receive injuries, or when, consequence of a drinking bout, their stomachs are so deranged to bring on loss of appetite and vomiting, and to lower their trition, they are liable to **delirium tremens**. So long as the nkard is able to eat and digest his food, he is little liable to s disease. As a rule delirium comes on in from two to four ys after he has lost his appetite and begun to vomit. This irium is marked by a peculiar tremor of the tongue, as well of the limbs, and by delusions which are especially connected h the sense of sight, the unfortunate patient imagining that sees noxious animals crawling around him, or that he is gued by demons, which are sometimes of a blue colour, from

which the disease is popularly known as 'blue devils.' T
tongue is moist, and covered with a thick white fur. There
loss of appetite and vomiting, which is often obstinate. T
delirium is constant and active. It may become violent, a
there is great restlessness and sleeplessness. It may gradua
subside, and the patient recover his health, or a condition
mania may ensue. Patients sometimes die suddenly, with
any warning symptoms.

The **treatment** of delirium tremens consists in keeping
the strength of the patient by a nutritive diet, and preserv
him from exhaustion by combating the sleeplessness which wo
cause it. The vomiting, which is the chief obstacle to nutriti
is often well combated by a combination of bismuth, magne
and hydrocyanic acid, to which small quantities of morph
may be added. Until the patient is able to retain food, he ou
to be fed by nutritive enemata, while chloral may be administe
for the sleeplessness. A combination of chloral with bromide
potassium is often very useful. Large doses of digitalis h
been given in order to quiet the delirium, and sometimes w
benefit; but this is a very dangerous treatment, and it see
not improbable that the reason why the enormous doses of s
a powerful drug have produced so little effect has simply b
that they have not been absorbed from the stomach, fo
have seen a case in which food lay undigested and unabsor
in the stomach for a period of four days, after which it
vomited.

CAUSES OF CHRONIC ALCOHOLISM.—The craving for stimula
which leads to chronic alcoholic poisoning may be acquired
the habit of drinking in society; but it is not seldom due to
practice of taking alcohol in order to relieve depression of spi
bodily or mental weakness, or inability to work as long or as
as might be desired. In men, the depression of spirits
feeling of weakness may be due to unfavourable physical
roundings, close atmosphere, over-work, exhausting dischar
or mental worry. In women, it may not only be connected v
any of these, but also with uterine derangement. The crav
appears to be partly gastric and partly systemic, and it is t
combated by the substitution for alcohol of other stimul
which will not have the same deleterious action. As a stimul
to the stomach, producing a sensation of warmth, tincture
capsicum is very useful, and aromatic spirit of ammonia sti
lates both the stomach itself and the circulation and nerv
system generally. A useful formula consists of 20 or 30 min
of aromatic spirit of ammonia, with 5 to 10 minims of tinc
of capsicum, in two ounces of infusion of gentian or cascar
This draught, which amounts to an ordinary wineglass-
should be taken when the craving is felt. In place of
draught a lemon may be sucked, or a glass of iced or cold wa

effervescing water, may be slowly sipped so as to get its mulating action on the cerebral circulation (p. 193) and heart 194). At the same time chalybeate tonics and strychnine y be given in order to increase the nutrition of the tissues nerally. The liquid extract of red cinchona bark has been ommended in such cases, and no doubt this medicine, along h easily digested food, beef-tea, and warm nutritive drinks, h as hot cocoa, may prove a useful adjunct in the treatment chronic alcoholism.

In some patients the tendency to drink appears to be epileptic character. The person affected by it will remain sober for eks or even months, and then be suddenly seized with the fit, gin to drink, and remain drunk for several days together, and, er the conclusion of the bout, will again remain sober for a g time. I have seen a case in which this species of inter- ttent drunkenness was brought on by a fall from a horse, and s associated with epilepsy. The fit began with an intense ving for drink, and after one or two days' drunkenness epilepsy me on. If the desire for drink was not gratified, the fit came sooner after the craving began than it would otherwise have ne, but it was not so violent. The treatment in these cases is omide of potassium combined with tonics.

Uses.—The cold produced by the evaporation of alcohol when is applied to the skin and rapidly dissipated by fanning or wing upon it is useful in preventing syncope, in relieving adache, or in rousing from fainting or coma. For these pur- ses one of the most convenient forms of application is eau-de- logne, and in cases of headache this may be used, diluted with ual parts of water, and applied by means of a thin handkerchief. e power of alcohol to harden the epidermis renders it a useful plication in cases where we desire to hinder the formation of d-sores or prevent the nipples from cracking. Brandy is the m most frequently employed for this purpose, as it stimulates e circulation when its evaporation is prevented, and especially en aided by friction. Alcohol, diluted simply, or in conjunction th one half per cent. carbolic or salicylic acid, is useful in ieving pruritus in erythema and other diseases; a similar ion is also useful in alopecia furfuracea. In urticaria it is best mbined with petroleum (*v.* p. 762). It has been used as a lini- nt in the form of brandy or spirit to sprained joints. A little andy held in the mouth increases the secretion of saliva, and en relieves toothache. Alcohol is also a useful gargle in relaxed re-throat, port wine being a form in which it is frequently plied for this purpose. It is also a useful astringent wash to e mouth in cases of profuse salivation. As in small doses it creases the secretion of gastric juice, it forms a useful addition the meals of persons whose digestive powers are weak either consequence of temporary exhaustion or from permanent

debility, occurring in convalescence from acute disease, gener malnutrition, or from old age. Some men, after being busi engaged all day, go home exhausted, and dine immediately their arrival. The consequence of this is that their food remai undigested, and they suffer from weight of the stomach a drowsiness. This condition may generally be prevented in perso below middle age, by simply making them rest for a while, that the stomach, as well as the body generally, may recover fro fatigue before the meal is taken; but in elderly individuals t addition of a little alcoholic stimulant may be necessary to ensu digestion. This use of alcohol was noticed in the Ashantee cam paign, in which the effect of alcohol as a stimulant, compare with beef-tea, was carefully tested. It was found that when ration of rum was served out the soldier at first marched mo briskly, but after about three miles had been traversed the effe of it seemed to be worn off, and he then lagged more than befor If a second ration were then given its effect was less marked, a wore off sooner than that of the first. A ration of beef-tea, ho ever, seemed to have as great a stimulating power as one of rum and not to be followed by any secondary depression. At the e of the march a short rest during the cooking of the evening me seemed sufficient to enable the younger men to eat and digest without the aid of rum, which they did not desire; but the m who had passed middle age not only wanted their own sha of the alcohol, but were glad to get that of their younger comrad also.

In the intestine alcohol is used as a carminative to relie flatulent distension, as an antispasmodic in colic, and as astringent in diarrhœa.

Alcohol as a Stimulant.—As a stimulant alcohol see serviceable in acute diseases running a limited course, where wish to sustain the patient's strength until the crisis is past, well as to prevent it sinking from debility afterwards. T various rules which have been given for the administration alcohol (in fever) may be condensed into one. If the alcoh tends to bring the patient nearer to his normal condition it doing good; if it takes him further away from a healthy conditi it is doing harm. The points which are usually specially attend to are the condition of the tongue, pulse, respiration, skin, a nervous system.

If it is found that the alcohol (*a*) renders the dry tong moist, (*b*) slows and strengthens the pulse when it is too qui or quickens it when it has been abnormally slow, (*c*) slows t hurried respiration, (*d*) renders the skin cooler or moister wh too hot and dry, and (*e*) lessens delirium and brings on sleep, then its action is beneficial. If it have an opposite effect it harmful. Useful indications regarding the advantage of alcoh and the amount to be given in any particular case may

tained by the practitioner remaining beside the patient, counting the pulse, and watching the tongue, respiration, skin, and neral condition for a quarter of an hour after the dose has en given. He will thus be able to give more definite directions an he otherwise could as to its continuance when he is absent. rticular care should be taken in the administration of alcoholic mulants to patients in the small hours of the morning. It is out this time that attendants are most apt to become sleepy, d therefore careless, and just at this time, also, the external mperature is lowest, the fire is apt to get low, and the vital wers of the patient are most likely to sink. In giving alcoholic mulants to support the strength in disease, care must be taken at they are not given so frequently and in such large quantities to disorder the stomach and produce subacute gastritis. metimes, when given very freely to support the failing circulan, they have this effect; the result of which is that both food d stimulants are vomited, and the patient may be brought to ath's door. The treatment here consists in the free administation of ice, along with two or three minims of solution of orphine and of hydrocyanic acid, frequently repeated until the miting is arrested.

During its **elimination** by the urine, alcohol may act as an itant to the urinary passages when these are already inflamed. is, consequently, injurious in gonorrhœa; and some sorts of er, especially Bavarian beer, will even bring on gonorrhœa in rsons who have previously had it, but who have been free from at the time of taking the beer.

U.S.P. Alcohol. ALCOHOL.—A liquid composed of 91 per nt. by weight (94 per cent. by volume) of ethyl alcohol $_2H_5HO$; 46), and 9 per cent. by weight (6 per cent. by volume) water.

CHARACTERS.—A transparent, colourless, mobile, and volatile uid, of a characteristic, pungent and agreeable odour, and a rning taste. It boils at 78° C. (172°·4 F.), and is readily inmmable, giving a blue flame without smoke. Specific gravity 820 at 15°·6 C. (60° F.), and 0·812 at 25° C. (77° F.). It should t change the colour of blue or red litmus-paper previously oistened with water.

IMPURITIES.—Fusel oil, amyl alcohol, methyl alcohol, aldehyde, oak-tannin, eign organic matters.

TESTS.—If a portion of at least 50 cc. be evaporated to dryness in a glass ssel, no residue or colour should appear. If mixed with its own volume of ter and one-fifth its volume of glycerin, a piece of blotting-paper on being ade wet with the mixture, after the vapour of alcohol has wholly disappeared, ould give no irritating or foreign odour (no fusel oil). And if a portion be aporated to one-fifth its volume, the residue should not turn reddish upon e addition of an equal volume of sulphuric acid (no amyl alcohol). When ated in a test-tube with an equal volume of solution of potassa, there should t be an immediate darkening of the liquid (no methyl alcohol, aldehyde,

and oak-tannin). If a portion of about 150 cc. be digested for an hour wi 20 grs. of carbonate of lead and filtered, the filtrate then distilled from water-bath, and the first 20 cc. of the distillate treated with 1 cc. of te solution of permanganate of potassium, the colour should not disappe within one or two minutes (absence of methyl alcohol). If 20 cc. are shak in a glass-stoppered vial, previously well rinsed with the same alcohol, wi 2 cc. of test-solution of nitrate of silver, the mixture should not be render more than faintly opalescent during one day's exposure to direct sunlig (absence of more than traces of foreign organic matters, fusel oil, &c.).

B.P. Spiritus Rectificatus. RECTIFIED SPIRIT. Alcoh C_2H_6O, with 16 per cent. of water; obtained by the distillatic of fermented saccharine fluids.

CHARACTERS.—Colourless, transparent, very mobile and i flammable, of a peculiar pleasant odour, and a strong spirituo burning taste. Burns with a blue flame without smoke. Specif gravity 0·838. Remains clear when diluted with distilled wate Odour and taste purely alcoholic.

TESTS.—Four fluid ounces with thirty grain-measures of the volumet solution of nitrate of silver exposed for twenty-four hours to bright light, a then decanted from the black powder which has formed, undergoes no furth change when again exposed to light with more of the test solution (no fu oil).

IMPURITIES.—Water, fusel oil.

Spiritus Tenuior, B.P.; Alcohol Dilutum, U.S.P. PRO SPIRIT, B.P.; DILUTED ALCOHOL, U.S.P.

Rectified spirit, 5 pints, mixed with distilled water, 3 pint specific gravity 0·920, B.P. Alcohol, 45·5 per cent. by weig (53 per cent. by volume), and distilled water, 54·5 per cer by weight (47 per cent. by volume); specific gravity 0·928 15·6° C. (60° F.), and 0·920 at 25° C. (77° F.), U.S.P.

Spiritus Vini Gallici, B. and U.S.P. SPIRIT OF FRENCH WIN BRANDY.

Spirit distilled from French wine. It has a peculiar flavou and a light sherry colour derived from the cask in which it h been kept, B.P. An alcoholic liquid obtained by the distillatic of fermented grapes and at least four years old, U.S.P. It shou contain from 39 to 47 per cent. by weight (46 to 55 per cer by volume) of alcohol.

PREPARATION.

B.P.	DOSE.
Mistura Spiritus Vini Gallici	1–2 fl. oz.

B.P. Mistura Spiritus Vini Gallici. MIXTURE OF SPIRIT OF FREN WINE. EGG FLIP (*vide* also Eggs). Beat up the yolks of two eggs, and sugar ½ o then add brandy and cinnamon-water, of each 4 fl. oz.

B.P. Vinum Xericum. SHERRY. A Spanish wine.

CHARACTERS.—Pale yellowish-brown, containing about 17 p cent. of alcohol.

USES.—As a stimulant, and in preparing all the wines of t B.P. except Vinum Ferri Citratis, Vinum Aurantii, and Vinu Quininæ.

U.S.P. Vinum Album. WHITE WINE.

CHARACTERS.—A pale, amber-coloured or straw-coloured alcoolic liquid, made by fermenting the unmodified juice of the rape freed from seeds, stems, and skins. White wine should ave a full, fruity, agreeable taste without excessive sweetness or idity; and it should have a pleasant odour free from yeastiess. Its sp. gr. at 15·6° C. (60° F.) should not be less than 0·990 or more than 1·010.

IMPURITY.—Tannic acid.

TESTS.—If 10 cc. of white wine be diluted with an equal volume of disilled water, and treated with 5 drops of test-solution of ferric chloride, only faint greenish-brown colour should make its appearance (absence of tannic id). Upon evaporation and twelve hours of drying on the water-bath, it ould leave a residue of not less than 1·5 per cent. nor more than 3·0 per nt. Using litmus-paper as an indicator 250 cc. of white wine should reire for complete neutralisation not less than 15 nor more than 26 cc. of e volumetric solution of soda.

U.S.P. Vinum Album Fortius. STRONGER WHITE WINE.

COMPOSITION.—White wine 7 parts, alcohol 1 part. When sted for alcohol it should not contain less than 20 nor more than per cent. of absolute alcohol by weight.

USE.—In preparing all the medicated wines in the U.S.P.

U.S.P. Vinum Rubrum. RED WINE.

A deep red alcoholic liquid, made by fermenting the juice of loured grapes with their skins.

CHARACTERS.—Red wine should have a full, fruity, moderately tringent, pleasant taste without decided sweetness or excessive idity. It should have a pleasant odour free from yeastiness. s sp. gr. at 15°·6 C. (60° F.) should not be less than 0·989 nor ore than 1·010.

TESTS.—If 10 cc. of red wine be diluted with an equal volume of distilled ater, and treated with 5 drops of test-solution of ferric chloride, the liquid ould acquire a brownish-green colour due to tannic acid. Upon evaporan and twelve hours drying on the water-bath, it should leave a residue of t less than 1·6 per cent. nor more than 3·5 per cent.

Using litmus-paper as an indicator, 250 cc. of red wine should require for mplete neutralisation not less than 15 nor more than 26 cc. of the voluetric solution of soda. If 50 cc. of red wine be treated with a slight excess water of ammonia, the liquid should acquire a green or brownish-green lour; if it be then well shaken with 25 cc. of ether, the greater portion of the hereal layer removed, and evaporated in a porcelain capsule with excess of etic acid and a few fibres of uncoloured silk, the latter should not acquire crimson or violet colour (absence of anilin colours). With test-solution of etate of lead, red wine should form a heavy precipitate, which may vary colour from bluish-green to green.

B.P. Alcohol Amylicum. AMYLIC ALCOHOL. *Synonym:* OUSEL OIL.

Amylic alcohol, $C_5H_{11}HO$, with a small proportion of other pirituous substances. An oily liquid, contained in the crude pirit produced by the fermentation of saccharine solutions with

yeast, and separated in the rectification or distillation of suc crude spirit.

CHARACTERS.—A colourless liquid with a penetrating ar oppressive odour, and a burning taste. When pure its specif gravity is 0·818, and its boiling-point 270° F.

SOLUBILITY.—Sparingly soluble in water, but soluble in all proportions alcohol, ether, and essential oils.

REACTIONS.—Exposed to the air in contact with platinum-black it slowly oxidised, yielding valerianic acid.


PREPARATIONS IN WHICH AMYLIC ALCOHOL IS USED.

Sodii Valerianas. Amyl Nitris.

USES.—It is oxidised into valerianic acid.

ALDEHYDES.

These substances in their chemical constitution lie betwee alcohols and acids. They are obtained from alcohols by th removal of two atoms of hydrogen, hence the name aldehyd (*al*cohol *dehyd*rogenatum).

They contain the group  (p. 22). They reduce silv

salts in darkness. Living protoplasm has a similar powe whereas dead protoplasm has not, and from this circumstance has been supposed that active albumin contains the aldehyd group in its constitution.

This supposition is supported by the fact that substanc which act energetically upon aldehydes are also protoplasm poisons.[1]

Acetic Aldehyde.—*Synonyms:* Aldehyde, ethyl aldehyde, ethylidene oxide. C_2H_4O. Not officinal.

CHARACTERS.—A colourless, mobile liquid, with an etheres acrid, and suffocating odour. Specific gravity 0·79. Boilin point, 22° C. (71°·6 F.).

PREPARATION.—It may be prepared in several ways, as the hydrogen c be removed from alcohol either by oxidising agents or chlorine. $C_2H_6O + = C_2H_4O + H_2O$, or $C_2H_6O + Cl_2 = C_2H_4O + 2HCl$.

ACTION.—It is **antiseptic.** It has a strong local irrita action. When inhaled it causes excitement followed by **anæ thesia.** It has a powerfully depressant action on respiratio and rapidly produces asphyxia, so that it is not used as anæsthetic.

Paraldehyde. $C_6H_{12}O_3$.—It appears to be a polymeric mod fication of aldehyde. Not officinal.

[1] O. Loew, Pflüger's *Archiv*, xxxv. p. 516.

CHARACTERS.—A colourless fluid.

DOSE.—3 to 6 gm., or more; ½ to 1 fl. drachm.

ADMINISTRATION.—It is soluble in about 8 parts of water, and y be given with glycerin, syrup of tolu, or syrup of oranges.

ACTION AND USES.—It is a pure **narcotic**, causing sleep like oral. It is about half the strength of chloral, and is said to without any depressing action on the heart and respiration. may thus be used instead of chloral in cases of weak heart. local action renders its use unadvisable in severe gastric dis- ers and laryngeal phthisis.

INCONVENIENCE.—It causes an unpleasant smell in the breath, ich is very disagreeable to some patients.

KETONES.

These are aldehydes in which the distinctively aldehyde drogen has been replaced by a radical. They thus bear a re- on to aldehydes similar to that of ethers to alcohols.

Alcohol, R—O—H Aldehyde, R—C(=O)—H

Ether, R—O—R Ketone, R—C(=O)—R

ey may also be regarded as compounds of carbonyl with two icals, instead of with one radical and H as in aldehydes, or radical and hydroxyl (H—O—) like the acids of this series.

Hypnone.[1]—Phenyl-methyl-acetone, or acetophenone, C_6H_5 O)(CH_3).

CHARACTERS.—Below 60° or 70° it forms white needles, but ve these temperatures it occurs as a liquid with a powerful ell of bitter almonds and orange.

PREPARATION.—By oxiding ethyl-benzene by chromic acid in presence of ic acid, or by distilling a mixture of acetate and benzoate of calcium.

DOSE.—·05–·015 gm.

ADMINISTRATION.—It is mixed with gelatine and enclosed in atine capsules.

ACTION.—It is a powerful **hypnotic**, and may be used instead chloral or paraldehyde. It appears to be free from danger.

USES.—To produce sleep. It is said to be especially useful alcoholism.

INCONVENIENCE.—It causes an unpleasant smell of acetone in breath which annoys patients.

---

[1] This name has been given by its introducers, Dujardin-Beaumetz and Bardet.

SIMPLE ETHERS.

These correspond in structure to oxides in which the pla of a metal is taken by an alcohol radical, thus potash, $\left.\begin{matrix}K\\K\end{matrix}\right\}O$ K_2O, corresponds to $\left.\begin{matrix}C_2H_5\\C_2H_5\end{matrix}\right\}O$ or $(C_2H_5)_2O$, ethylic ether.

Æther, B. and U.S.P. $(C_2H_5)_2O$; 74. ETHER.

A volatile liquid prepared from alcohol, and containing n less than 92 per cent. by volume of pure ether $(C_2H_5)_2O$, B.P. liquid composed of about 74 per cent. of ethyl oxide $(C_2H_5)_2($ and about 26 per cent. of alcohol containing a little water. Speci gravity about 0·750 at 15° C. (59° F.), U.S.P.

CHARACTERS.—A colourless, very volatile and inflammab liquid, emitting a strong and characteristic odour, and boili below 105° F. Specific gravity 0·735, B.P.

REACTIONS.—Fifty measures agitated with an equal volume of water reduced to 45, by an absorption of 10 per cent. It evaporates witho residue.

PREPARATION.—By distilling rectified spirit with sulphuric acid, and fr ing the ether thus obtained from water by redistillation with calcium chlor and lime.

In this process ethylsulphuric or sulphovinic acid and water are fi formed, ethyl replacing one atom of hydrogen in the sulphuric acid.

$$\underset{\text{Sulphuric Acid.}}{\left.\begin{matrix}H\\H\end{matrix}\right\}SO_4} + \underset{\text{Alcohol.}}{\left.\begin{matrix}C_2H_5\\H\end{matrix}\right\}O} = \underset{\text{Ethylsulphuric Acid.}}{\left.\begin{matrix}C_2H_5\\H\end{matrix}\right\}SO_4} + \underset{\text{Water.}}{\left.\begin{matrix}H\\H\end{matrix}\right\}O.}$$

By the action of fresh alcohol on the ethylsulphuric acid it is decompos ether being formed and sulphuric acid being reproduced.

$$\underset{\text{Ethylsulphuric Acid.}}{\left.\begin{matrix}C_2H_5\\H\end{matrix}\right\}SO_4} + \underset{\text{Alcohol.}}{\left.\begin{matrix}H\\C_2H_5\end{matrix}\right\}O} = \underset{\text{Sulphuric Acid.}}{\left.\begin{matrix}H\\H\end{matrix}\right\}SO_4} + \underset{\text{Ether.}}{\left.\begin{matrix}C_2H_5\\C_2H_5\end{matrix}\right\}O.}$$

Theoretically this process might go on *ad infinitum* if fresh alcohol w continually supplied; but practically the acid volatilises partly in the form oil of wine, so that the process cannot go on indefinitely.

IMPURITIES.—Water, alcohol, and fixed impurities.

TESTS.—Water is detected by the greater sp. gr., and so is alcohol; fixed impurities by their remaining on evaporation.

DOSE.—20 to 60 min.

PREPARATIONS.

B.P.	
Æther Purus	
Collodium	6 volumes in 8 nearly.
„ Flexile	6 „ 8 „
Spiritus Ætheris	1 volume in 3 „
„ „ **Compositus**	1 „ 3 „
Tinctura Chloroformi et Morphinæ	1 „ 32 „

B.P. Æther Purus. PURE ETHER.—Ether, $C_4H_{10}O$, f from alcohol and water.

PREPARATION.—By washing ether with distilled water, and then distilling
m calcium chloride and recently calcined lime.
TEST.—Specific gravity not exceeding 0·720.

USES.—Used as an **anæsthetic**; to prepare some alkaloids, aconitine; to test the amount of quinine in bark. Ether is metimes used locally in ringworm, and to dissolve sebaceous atter from the surface of the skin. In conjunction with alcohol forms a cooling lotion in urticaria and pruritus.

U.S.P. Æther Fortior. STRONGER ETHER, $(C_2H_5)_2O$; 74.

PREPARATIONS.

Spiritus Ætheris. Spiritus Ætheris Compositus.

CHARACTERS.—A liquid composed of about 94 per cent. of hyl oxide and about 6 per cent. of alcohol, containing a little ater. Specific gravity not higher than 0·725 at 15° C. (59° F.) 0·716 at 25° C. (77° F.).

Ether is highly inflammable, and its vapour when mixed with r and ignited explodes violently.

TEST.—It should boil actively in a test-tube half filled with it and held a ort time in the hand on the addition of small pieces of broken glass.

USES.—Used for inhalation as an **anæsthetic**.

Spiritus Ætheris, B. and U.S.P. SPIRIT OF ETHER.—It is mixture of ether (1), rectified spirit (2).

TEST.—Specific gravity, 0·809.

DOSE.—30 to 90 min.

PREPARATION.

B.P.

Tinctura Lobelia Ætherea.

USES.—Spirit of ether is used as a carminative and stimulant. is useful in lessening the pain in the passage of biliary or inary calculi.

ACTION OF ETHER.—When applied to the **skin** ether evapotes very readily, and causes intense cold. The application of her to the surface will freeze it completely, and render it rfectly insensitive to pain. If the freezing be continued for o long a time, the frozen part may be killed, and separate as a ough. In the **mouth**, ether acts as a powerful stimulant to e salivary secretion. In the **stomach** it increases the secretion gastric juice, stimulates the movements of the organ, expels atulence, and probably tends to increase the co-ordination of e movements of the stomach and **intestine**, so that it diminishes pasm and relieves pain. When absorbed into the circulation om the intestine, or, still more markedly, when absorbed from e lungs after an inhalation, it first stimulates the **circulation**, nd, after a very brief, and perhaps hardly perceptible, period of imulation of the nerve-centres, it depresses their powers in

succession. First of all, it affects the **cerebral hemispher** causing delirium and unconsciousness; next, the grey matter the **spinal cord**; next the white matter of the spinal cord, a lastly, the cardiac and vaso-motor centres in the **medu oblongata**. It does not appear to destroy the irritability of **muscles** in animals poisoned by it; but muscles exposed to vapour soon lose their contractility, and fall into a condition *rigor mortis*. **Nerves**, also, which are exposed to its vapo lose their irritability, so that when attempted to be irritated th no longer respond, the irritability of the sensory fibres apparen disappearing before that of the motor fibres. When the vapo is applied only for a short time, they may regain their irritabili but if its application be continued too long, the irritability permanently destroyed. There is no marked alteration in t blood of animals poisoned by ether, but when mixed in sm quantity with **blood** outside the body, it appears to form compound with the hæmoglobin, and to lessen its oxidisi power. If mixed with the blood in large quantity, it destro the blood-corpuscles, probably by dissolving the protagon whi forms an essential constituent of them.

The **heart** is very much less easily paralysed by ether th by chloroform. If two rabbits are thoroughly narcotised by eth and chloroform vapour respectively, and the thorax opened, a artificial respiration kept up with air containing these vapou the heart of one can be readily stopped by increasing the pr portion of chloroform vapour in the air blown in, whereas t heart of the other is only arrested when the proportion of eth vapour becomes exceedingly large. It is this peculiarity of eth which gives it the advantage over chloroform, and renders dea from syncope during operations less probable when ether employed as an anæsthetic.

Another **difference between ether and chloroform**, whi renders the former much safer as an anæsthetic, is that the vas motor centre appears, like the heart, to be very much less readi affected by ether than by chloroform, so that irritation of sensory nerve continues for a longer time to raise the bloo pressure when ether is employed as an anæsthetic. The di **advantages of ether** are that it is less agreeable to take, a that its odour hangs unpleasantly about the patient for a muc longer time than is the case with chloroform. It causes great irritation of the air-passages, and may produce a catarrh condition. It has to be administered in a more concentrat form than chloroform, and thus is not so convenient as th latter when operations on the face and mouth are necessary. is frequently administered along with nitrous oxide, the nitro oxide being first given alone until the patient is sufficient under its influence not to notice the taste or smell of the ethe Nitrous oxide loaded with ether vapour is then given, and

on as complete insensibility is induced air is mixed with ether apour, the anæsthesia being maintained by regulating the roportion of vapour according to the condition of the patient. he administration of ether is inadmissible in operations on the outh and face if the thermo-cautery has to be used.

SALINE ETHERS.

These correspond to metallic salts, in which the metal is placed by an organic radical, e.g.:

Potassium Sulphate.	Ethyl Sulphate.
$\left.\begin{matrix}K\\K\end{matrix}\right\}SO_4$ or K_2SO_4	$\left.\begin{matrix}C_2H_5\\C_2H_5\end{matrix}\right\}SO_4$ or $(C_2H_5)_2SO_4$.

U.S.P. Oleum Æthereum. Ethereal Oil.—A volatile quid, consisting of equal volumes of heavy oil of wine and of ronger ether.

The heavy oil of wine is either a mixture of ethyl sulphate $_2H_5)_2SO_4$, and a polymeric form of ethylene (C_2H_4), or else a lphovinate of a hydrocarbon radical.

Characters.—A transparent, nearly colourless, volatile liquid, a peculiar aromatic ethereal odour, a pungent, refreshing, tterish taste, and a neutral reaction to dry litmus-paper. pecific gravity, 0·910.

Preparation.—By mixing alcohol with sulphuric acid, allowing it to nd for some hours (24 B.P.; 12 U.S.P.), and then distilling. The dis- late consists of three layers—ether, water, and yellow ethereal oil of wine me water is added to it to neutralise any acid, B.P.). The yellow oil of ne is separated and exposed to the air for twenty-four hours in a shallow psule, so that any ether evaporates. It is then used, B.P., but according U.S.P. it is then put in a wet filter, washed with distilled water, and xed with an equal volume of stronger ether.

Preparation.
Spiritus Ætheris Compositus.

Spiritus Ætheris Compositus, B. and U.S.P. Compound pirit of Ether. Hoffmann's Anodyne.

Composition.—B.P., oil of wine 3, ether 64, rectified spirit 8; U.S.P., ethereal oil 3 parts, stronger ether 30, alcohol 67. ne strength of the two preparations is nearly the same, as the l of wine is diluted to make the ethereal oil of the U.S.P.

Use.—Like that of spirit of ether, but more powerful. It is ven in similar doses.

Æther Aceticus, B. and U.S.P. Acetic Æther. $C_2H_5C_2H_3O_2$; . Acetate of Ethyl.

Characters.—A transparent and colourless liquid, of a strong agrant ethereal and somewhat acetous odour, a refreshing taste d a neutral reaction.

PREPARATION.—By distilling rectified spirit with acetate of sodium sulphuric acid, $NaC_2H_3O_2 + H_2SO_4 + C_2H_6O = C_2H_5C_2H_3O_2 + NaHSO_4 + H$ The acetic ether and water distil over together, and they are separated means of calcium chloride.

DOSE.—20 to 60 min.

USES.—It has an action much like ether, but is inconveni as an anæsthetic. It has a pleasanter taste than ether, and used as a stimulant, carminative, and **antispasmodic**. It m be given along with the acetates of iron and potassium in al minuria.

PREPARATION.

B.P.

Liquor Epispasticus.

Spiritus Ætheris Nitrosi, B. and U.S.P. SPIRIT OF NITR ETHER.

A spirituous solution containing nitrous compounds, aldeh and other substances, B.P. An alcoholic solution of ethyl niti ($C_2H_5NO_2$; 75), containing 5 per cent. of the crude ether, U.S

CHARACTERS.—Transparent and nearly colourless, with a v slight tinge of yellow, mobile, inflammable, of a peculiar pe trating apple-like odour, and sweetish cooling sharp ta Specific gravity, 0·845.

REACTIONS.—It effervesces feebly or not at all when shaken with a li bicarbonate of sodium (no acid). When agitated with solution of sulphat iron and a few drops of sulphuric acid it becomes deep olive-brown or bl When freshly prepared it should yield 7 times its volume of nitric acid or 5 times even after it has been kept.

PREPARATION.—By distilling rectified spirit with nitric and sulph acids and copper wire, and diluting the distillate with spirit. In this pro the copper reduces the nitric to the nitrous radical.

$$C_2H_5HO + HNO_3 + H_2SO_4 + Cu = C_2H_5NO_2 + 2H_2O + CuSO_4.$$

IMPURITIES.—Water, free acid.

DOSE.—$\frac{1}{2}$ to 2 fluid drachms.

USE.—Is used as a **diaphoretic** and **diuretic**.

PREPARATION.

U.S.P.

Mistura Glycyrrhizæ Composita.

Amyl Nitris, B. and U.S.P. NITRITE OF AMYL, $C_5H_{11}N$ 117.

CHARACTERS.—A yellowish liquid with a strong ether fruity smell. When freely exposed to air it decomposes, leav a large residue of amyl alcohol.

SOLUBILITY.—Insoluble in water, but soluble in all proportions in alc ether, and chloroform.

PREPARATION.—By distilling dilute amyl alcohol with nitric acid, phuric acid and copper wire. The distillate is washed with caustic sod remove hydrocyanic and other acids; the moisture removed by potass carbonate, and the nitrite purified by fractional distillation between 262° 270° F. (128°—132° C.).

IMPURITIES.—It is apt to contain free acid, nitrate of amyl, nitro-pentane.
TESTS.—The physiological test is the most certain. One or two sniffs
m a bottle containing the nitrite are usually sufficient to produce flushing
the face and fulness in the head. If the preparation is impure or has
t its strength, this effect does not occur. Some specimens are entirely
rt.

PHYSIOLOGICAL ACTION.—When mixed with **blood** it forms
thæmoglobin, which is not so readily de-oxidised as hæmo-
bin itself. The blood, under the influence of the nitrite,
comes of a dark chocolate colour, both in the arteries and
ns, and oxidation in the body is interfered with; so much so
at in rabbits convulsions almost exactly resembling those of
linary asphyxia are very rapidly produced by the inhalation
the drug. The methæmoglobin may be broken up by reducing
nts, and the blood will then take up oxygen again. It is
refore probable that, when the venosity of the blood becomes
at, the unoxidised products of tissue-waste will act as re-
cing agents, and again restore the internal respiration. When
haled, nitrite of amyl causes at first a short dry tickling cough,
lowed in about half a minute by flushing of the face, throbbing
the carotids and their branches, a quicker and fuller pulse, a
ling of tension in the head, sometimes lacrimation, quickened
piration, and giddiness. The giddiness is more especially felt
he patient is sitting up. If the dose of nitrite be large the
piration becomes very quick, laboured, and dyspnœic. The
od-pressure is very greatly lessened by nitrite of amyl, the
minution being chiefly due to dilatation of the arterioles. The
lse in man and in dogs is very much quickened by it. In
bits the acceleration is not so great. This appears to show
t the quickening is in a great measure due to diminution in
tone of the vagus-roots in the medulla caused by the fall of
od-pressure. The dilatation of the arterioles appears to be
to weakening or paralysis, either of the muscular walls of
arterioles themselves, or of the vaso-motor ganglia in or
r them. This is shown by the fact that the nitrite of amyl
ers the blood-pressure in animals, even after the cord has
n divided just below the medulla. It has been objected to
s that Bernheim has found that when the capillaries are
ted by nitrite of amyl they may still be made to contract by
tation of the vaso-motor nerves; and he concludes from this
t the dilatation is due rather to paralysis of vaso-motor
tres than to vaso-motor nerves, or to the arterioles. It is
sible that the dilatation may be partly due to weakening
the vaso-motor centres also; but Bernheim's objection is
gether without force, because in animals killed by curare,
muscles will still contract on the application of an electric
rent to the motor nerves. In this case the nerves are so far
alysed that they will no longer respond to the stimuli sent
n from the nerve-centres, although they will do so to strong

currents, and probably the same thing occurs with the muscula walls of the arterioles when paralysed by nitrite of amyl.

Action on Muscles.—The voluntary muscles are not para lysed in animals poisoned by nitrite of amyl, but when th muscles of a frog are exposed to the vapour they soon lose the contractility. It was stated by Dr. Richardson that nitrite amyl, like curare, paralysed the ends of the **motor nerves**, an that it acted in consequence as an antidote to strychnine. O repeating his experiments other observers have failed to dete any paralysis of motor nerves. I have found that nitrite of amy alone does not paralyse them, nor does strychnine alone; but a frog be poisoned with strychnine after one leg has been protecte by a ligature from the influence of the poison, and is then expose to the vapour of nitrite of amyl, the joint action of the strych nine and nitrite paralyses the ends of the motor nerves, whi the nerves of the limb protected from the strychnine retai their irritability, although both were equally exposed to th nitrite of amyl.[1]

Action on the Nervous System.—It lessens reflex actio apparently by its action on the spinal cord.

On the Urine.—When nitrite of amyl is given to anima either by inhalation or hypodermically, sugar appears in th urine.

Uses.—The action of nitrite of amyl in causing flushing wa first observed by Guthrie, and Dr. B. W. Richardson recom mended it as a remedy in spasmodic conditions, from the powe he thought it to possess of paralysing motor nerves. In th spring of 1867 I had opportunities of constantly observing patient who suffered from angina pectoris, and of obtaining fro him numerous sphygmographic tracings, both during the attac and during the interval. These showed that during the attac the pulse became quick, the blood-pressure rose, and the art




Fig. 173.—Normal pulse-tracing of a patient suffering from aortic regurgitation and angina pecto

rioles contracted; for the form of the pulse-curve was such could only be caused by contraction of the arterioles (Fig. 173 The pain, which came on every night, lasted for one and a ha or two hours. All other remedies were nearly useless, thoug

[1] These experiments were made with *Rana temporaria*.


leeding always removed the pain for one night. It seemed robable that the great rise in tension was the cause of the pain, nd it occurred to me that if it was possible to diminish the nsion by drugs, instead of by bleeding, the pain would be moved.

I knew from unpublished experiments by Dr. A. Gamgee, at nitrite of amyl had this power, and therefore tried it on e patient. My expectations were perfectly answered. The pain sually disappeared in three quarters of a minute after the in- alation began, and at the same time the pulse became slower nd much fuller, and the tension diminished. Occasionally the ain would disappear, though the pulse regained its normal lness, and on these occasions the pain always reappeared after e lapse of a few minutes (Fig. 174). Whenever the pulse



FIG. 174.—Tracing of the same pulse during severe anginal pain.

ain regained its normal character completely (Fig.175), I knew at the pain would not again return.



. 175.—Tracing of the same pulse during temporary relief of pain by nitrite of amyl. The pain returned after a few minutes.

In some cases of angina pectoris nitrite of amyl has failed. e reason of this may be either that the drug has not been re, or that it has undergone changes from age. In one case entioned to me by Dr. Balfour, the patient was only relieved nitrite of amyl newly made, the drug appearing to lose its wer in a few days. As migraine is generally connected with scular spasm, I employed the nitrite of amyl in headache, and nd that frequently, though not invariably, it relieved the pain. was also useful in neuralgia of the scalp. As epilepsy has been pposed to depend upon spasmodic contraction of the cerebral ssels, I employed it in this disease, during the fit, without suc- ss, but Sir Crichton Browne found that when administered mediately after the appearance of the aura it prevented the fit ich would otherwise have come on. On the commencement of e cold stage in ague nitrite of amyl cuts short the attack. sea-sickness, a disease probably of cerebral, rather than stric, origin, it appears to give relief. It has been employed

to aid circulation in cases of syncope, and in chloroform po soning, its administration in the latter case being combined wi the depression of the patient's head below the level of his bod and the use of artificial respiration. In spasmodic asthma sometimes affords some relief, but this is not very marked. It useful in the case of persons who are subject to sudden flushes heat and profuse perspiration.

The administration of nitrite of amyl is not attended wi much danger. I have pushed it in many cases, and have se no bad effects from its use. In cases of chronic bronchitis a emphysema, however, it is advisable not to give it even for t relief of asthmatic attacks which come on in this disease, as t difficulty of breathing already present may be seriously increas by the action of the drug upon the blood. It has been thoug that its administration would be especially dangerous in aort disease; and no doubt it is well both in this disease and in oth cases to give the drug in the recumbent posture and thus avo the faintness which might otherwise occur. Although it caus a feeling of fulness in the head, little danger of apoplexy is to apprehended from it, because the blood-pressure, instead of bei higher, is much lower than usual, and therefore the tendency the vessel to burst must be reduced to its minimum.

Nitro-glycerinum. NITRO-GLYCERINE, GLONOINE. $C_3H_5(NO_3)$ Not officinal.

PROPERTIES. — A colourless transparent liquid; aromat taste.

SOLUBILITY.—It is slightly soluble in water, readily soluble in absol alcohol and ether, soluble also in oils and fats.

PREPARATION.—By dropping pure glycerine into a mixture of sulphu and nitric acid kept cool by ice; pouring the mixture into water; washing well; and carefully drying in a warm room.

DOSE.—$\frac{1}{200}$ to $\frac{1}{50}$ gr. increased to $\frac{1}{10}$ grain; of Liquor Nitr glycerini (non-officinal) [1] (1 gr. in 100 min. rectified spirit), $\frac{1}{2}$–. minims.

B.P. Tabellæ Nitro-glycerini. TABLETS OF NITRO-GLYCERIN Tablets of chocolate, each weighing $2\frac{1}{2}$ grains, and containi $\frac{1}{100}$th of a grain of pure nitro-glycerine.

DOSE.—1 or two tablets.

Liquor Nitro-glycerini (non-officinal) [1] (1 gr. in 100 rectified spirit), $\frac{1}{2}$–10 mi

ACTION.—Its action is much like that of nitrite of amyl a other nitrites,[2] but is more persistent. In frogs it causes first great restlessness, then lethargy, to which convulsions a paralysis succeed. In mammals it causes depression, with ve rapid pulse and respiration, paralysis of reflex action and volu tary motion, loss of sensation, and death by stoppage of t

[1] Martindale and Westcott, *The Extra Pharmacopœia.*

[2] Lauder Brunton and Tait, *St. Bartholomew's Hospital Reports*, 1876, p. 14

spiration. It agrees with nitrites in acting as a poison to uscle. The **spinal cord** appears to be paralysed before the rebral ganglia, and the convulsions in frogs are of cerebral ther than spinal origin. It paralyses the **heart** of the frog hen directly applied. It diminishes the oxidising power of the lood and communicates to it a chocolate colour, like nitrites, nd like them also it lessens the **blood-pressure.** In some ersons it produces intense **headache**, even in exceedingly minute oses. It is curious that its action upon the blood and organs hould so exactly resemble that of nitrites, because nitro-glycerine a nitrate and not a nitrite of glyceryl. Hay has shown, how-er, that nitro-glycerine is decomposed by alkalis, two-thirds its nitric acid being reduced to nitrous acid and uniting with he alkali to form a nitrite, whilst the remaining third is set free ithout reduction and forms a nitrate.

The reasons why nitro-glycerine acts more powerfully than itrites probably are that the whole of it is absorbed without ecomposition, and that nitrous acid being set free in the blood n a nascent condition is more active than it would otherwise be.

USES.—Like nitrite of amyl, it is useful in angina pectoris, eadache, neuralgia, epileptic vertigo, and epilepsy. Its action eing more persistent than that of nitrite of amyl, it is some-mes more efficacious. It is sometimes of service in spasmodic sthma, uræmic asthma, and in puerperal convulsions. It fre-uently relieves sea-sickness, and may lessen pain in gastralgia nd hepatic colic. By dilating the vessels it may cut short or revent the cold stage of ague. By lessening the arterial ten-ion and diminishing the resistance the heart has to overcome, is useful when the heart is weak in old persons, or from fatty egeneration, or where the tension is abnormally high, as in Bright's disease. In conjunction with elaterium it is said to ave proved useful in myxœdema.

B.P. Liquor Sodii Ethylatis.—*Vide* p. 619.

HALOID COMPOUNDS.

These correspond to haloid salts of metals, e.g. :

Potassium Bromide.	Ethyl Bromide.
KBr.	$(C_2H_5)Br$.

Æthyl Bromidum. BROMIDE OF ETHYL. C_2H_5Br. Hydro-romic Ether. Not officinal.

CHARACTERS.—A colourless volatile liquid; of peculiar odour nd sweetish taste. Specific gravity, 1·419.

PREPARATION.—By distilling alcohol with bromide and phosphorus.

ACTION AND USES.—When applied as spray it produces **local anæsthesia**, which seems to depend on the action of the drug on

the nerves as well as on the cold produced. It is used as a loca anæsthetic in neuralgia. When inhaled it produces **anæsthesia** and has been recommended as an anæsthetic either alone or a a mixture of one part of it with 3 of chloroform and 4 of alcoho Its advantages are that it is not inflammable like ether, that does not irritate the respiratory passages, and that it causes les excitement and struggling than ether or chloroform, and is les depressing than chloroform. Its disadvantages are that it i not absolutely safe, as one death at least has occurred from it use. Its odour remains longer in the breath than either chloro form or ether, and some patients dislike its smell extremely.

Æthyl Iodidum. Iodide of Ethyl. C_2H_5I. (Hydriodi Ether.) Not officinal.

Characters.—A colourless liquid, with a penetrating odour It is apt to become decomposed by keeping, and acquire a brow colour from free iodine.

Preparation.—Like bromide of ethyl, using iodine instead of bromine.

Action and Uses.—It has an **anæsthetic** action when in haled, which is more slowly produced but is more persistent tha that of ethyl bromide. It is decomposed in the body, and th iodine is excreted in the urine as iodide of potassium. It ha been given internally as an **alterative** in doses of 0·2 to 0·5 gm in scrofula and rheumatism, and as a **diuretic** in cases of cardia dropsy. Its chief use, however, is as an **antispasmodic** i asthmatic paroxysms, either of the purely spasmodic kind, o occurring in chronic bronchitis and emphysema, or in cardia or laryngeal disease. In some of these cases it gives very grea relief, and not only cuts short the paroxysm, but benefits th bronchitic condition where this is present (cf. p. 562).

Administration.—It is best given in small glass capsule containing 5 minims, and encased in cotton-wool and silk These can be readily carried about, and when the paroxysm comes on one is crushed between the finger and thumb, and the vapour inhaled from the cotton-wool, which becomes soaked by the iodide.

Chloral Hydras, B.P.; Chloral, U.S.P. $C_2HCl_3O.H_2O$ 165·2. Hydrate of Chloral (Hydrous Chloral), B.P. Chloral U.S.P.

Characters.—Whitish crystals with a peculiar very pungen odour, a bitterish caustic taste, and a neutral reaction. It melts when heated, forming a colourless liquid, and volatilises if the temperature be further raised.

Preparation.—By saturating absolute alcohol with dry chlorine ga much hydrochloric acid gas is formed, and the alcohol is first reduced t aldehyd, which is then attacked by the chlorine, forming tri*chloral*dehyd a word which has been shortened to chloral. Chloral is an oily liquid, whic is purified with sulphuric acid, and then with lime, and finally converte into hydrous chloral by the addition of water.

SOLUBILITY.—It is soluble in less than its own weight of water, alcohol, ether, and in four parts of chloroform.

REACTIONS.—When mixed with carbolic acid or camphor it liquefies. hen mixed with alkalis it is decomposed into chloroform and a formiate of e base.

IMPURITIES.—Hydrochloric acid and oily impurities.

TEST.—The aqueous solution should be neutral or only slightly acid. A lution in chloroform when shaken with sulphuric acid should not impart lour to the acid (absence of oily impurities).

PREPARATION.

B.P.		DOSE.
Syrupus Chloral.	SYRUP OF CHLORAL. Chloral in syrup and water, 10 grs. in each fl. dr.	1 fl. dr.

ACTION OF ANHYDROUS CHLORAL.—Anhydrous chloral applied the skin is absorbed and converted in the organism into hloral hydrate. When thus applied it sometimes occasions æmoglobinuria and nephritis. Anhydrous chloral being little sed, the name 'chloral' is applied in ordinary conversation chloral hydrate, and in the following account of the action of hloral hydrate the name chloral is intended to apply to the ydrate.

ACTION OF CHLORAL HYDRATE.—It destroys low organisms, nd prevents the decomposition which they occasion. It is there-re sometimes used as an **antiseptic**. In the **mouth** chloral as a hot, burning taste, and when applied to a raw surface, or the mucous membrane of the eye, it is a powerful irritant. hen injected under the skin in a strong solution it is apt to use inflammation and suppuration. It was introduced into edicine by Oscar Liebreich with the object of attaining by it he same effects as those of chloroform slowly administered for a ngth of time. When chloral is mixed with an alkali it is split p, yielding formic acid which combines with the alkali and hloroform. Liebreich thought that if chloral were administered nternally the alkalis of the blood would slowly split it up, and hat chloroform would thus be slowly generated from it in the rculating blood for a considerable length of time. His expec-tations regarding the utility of chloral as a means of producing leep and relieving pain have been fully answered; but the theory hich led him to employ chloral appears to be erroneous, and it robably acts as a hypnotic and analgesic without undergoing ny decomposition in the body. The experiments which have d to the conclusion that chloral is not decomposed in the body re chiefly those of Hammersten, who found that when a stream f carbonic acid was passed through the blood taken from hloralised animals, and then passed through a red-hot tube into mixture of starch paste and iodine or a solution of nitrate of ilver, no reaction occurred, and that the slightest addition of hloroform to the blood or the administration of chloroform o the animal beforehand always causes a reaction to take lace. The expired air of chloralised animals is also free from

chloroform. The chloral is excreted in the urine as such so lo as the urine is acid, and it is only when the urine is alkaline th chloroform is found in it, this being formed by the decompositi of the chloral by the alkali in the urine itself. In **frogs**, sm doses slow the respiration, and abolish reflex action, but t animal recovers perfectly after several hours. When the dose increased, the stoppage of the heart follows the cessation of refl movements and the animal dies. In **mammals**, the respirati also becomes slow, the pupil contracted, and sleep occurs. Fro this the animal may first be awakened with ease, but it gradual becomes deeper, and the reflex movements disappear. Insen bility occurs first to painful impressions, so that the animal m be cut or burned without showing the slightest symptoms sensation, whereas it will still withdraw its limb quickly when slight pressure is made upon the toes. When larger doses a given, the **temperature** gradually falls until it can no longer measured by an ordinary clinical thermometer. The **respirati** gets slower and weaker, and finally ceases altogether. Wh chloral is added to the **blood**, it causes the red corpuscles swell up and become paler, but does not dissolve them.

Action on the Circulation.—It diminishes the blood-pressu in two ways—first by weakening and finally paralysing the **vas motor centre**, and thus dilating the vessels; and secondly weakening the heart. The **pulse** may at first be quickene possibly, in consequence of the lessened blood-pressure, but afterwards becomes slow. The slowing of the pulse is not due any action of the drug upon the vagus, for it occurs after secti of the vagi, or after the previous administration of nicoti atropine, or curare. The weakening and final stoppage of t heart appears to be due to paralysis of the cardiac **ganglia**, the heart still continues to contract when its muscular substan is irritated directly.

Action on Muscles and Motor Nerves.—The muscles a motor nerves are not paralysed by chloral. The paralysis a loss of sensibility are of spinal origin.

Action on the Spinal Cord.—Chloral first increases a then diminishes the excitability of the spinal cord, and final abolishes it altogether. It probably acts first upon the gr matter, as impressions which are usually painful are not felt a time when tactile impressions still produce reflex.

Action on the Brain.—At first it may cause a little excit ment of the brain, followed by sleep, and then by coma. The actions are probably due partly to the influence of the drug the circulation, and partly to its direct action on the cerebr tissue itself. In the first stage of excitement the circulati in the brain is somewhat increased, but as sleep comes on t vessels contract and the brain becomes anæmic.

The **pupil** is almost invariably contracted; the temperatur

has already been mentioned, falls steadily and rapidly, and is fall appears to be due partly, though not entirely, to lessened oduction of heat, for it still occurs, though to a less extent, ien the animal is wrapped up in cotton-wool, or is put in a rm place.

THE TREATMENT OF CHLORAL-POISONING.—In conjunction th Professor Stricker, I found that animals which had received dose of chloral which would certainly kill them if they were t exposed, would recover from the effects of such a dose if they re wrapped up in cotton-wool. If the dose be still further creased, so as to kill the animal even when carefully so wrapped , it may still be kept alive by being put in a warm place, so at its temperature is kept up artificially. If, however, the dose still further increased, the animal will die, notwithstanding ese precautions. The treatment of cases of poisoning in man the same as in animals, viz. to keep up the temperature of e patient by putting him in a warm room, covering him with ankets, applying hot bottles, and giving stimulants, coffee, &c.

CHRONIC CHLORALISM.—Despite its nauseous taste, chloral metimes excites a craving, just like morphine, in those who ve begun its use to allay nervous excitement, or to procure ep. Taken habitually in this manner, it is apt to excite gastro-testinal disturbance, and to produce skin-eruptions (chiefly ythematous), which sometimes occur only on taking alcohol so, to lower the nutrition, and to cause pains, nervous irritability d depression, which may lead to disturbance of the mental equi-rium. After a time, the dose has to be increased to produce e desired effect, but tolerance is not so readily established as in e taking of opium or morphine, so that patients have died from slight increase of the dose they have been accustomed to take.

USES.—If equal parts of chloral and powdered camphor are bbed together, they dissolve, and form a syrup. This is use-l in neuralgia, when painted over or gently rubbed into the inful part. In the proportion of chloral 1 part, camphor 1 rt, and simple ointment 8, it is a useful remedy in the itching skin-diseases.

The chief use of chloral is to produce sleep. It is useful as a **ypnotic** in the sleeplessness due to overwork or worry, and the akefulness depending on constitutional peculiarity, old age, or sease, such as fever, delirium tremens, insanity, and puerperal ania. In the latter stage of Bright's disease, where there is reat sleeplessness accompanied by high blood-tension, chloral is ry useful. The sleep which it causes is generally quiet and freshing, and as a rule it is not followed next day by sickness, adache, and depression, like the sleep caused by opium. sually, also, the sleep is not too deep to prevent the patient ing readily awakened for the purpose of taking food.

Chloral may be used to lessen reflex excitability and diminish

convulsions, as well as to produce sleep. For this purpose it given in puerperal convulsions, in the convulsions of childr and in chorea and tetanus. In these two latter diseases it m be given in large doses. It alleviates the dyspnœa in spasmo asthma, and the asthmatic attacks which occur in perso labouring under chronic bronchitis with emphysema. In ca of this sort, however, it is well to give it with care, for Rin states that in them it often produces increased lividity and m tering delirium, lasting for several days.

The action of chloral as an **anæsthetic** or analgesic is mu slighter than that of chloroform, but nevertheless it sometim relieves pain, and for this purpose it has been used in gastralg intestinal and renal colic, neuralgia, and chronic rheumatis It has been recommended by Dr. Playfair in doses of 15 grai repeated if necessary in twenty minutes, before the os ut has become completely dilated, to lessen pain in labour.

Chloral is an **antidote** to strychnine, physostigma, and pici toxine. Liebreich states that strychnine is an antidote chloral; and while some observers have confirmed his stateme others have denied it, so that strychnine has certainly not t same power of antagonising the action of chloral as chloral h of antagonising strychnine.

Chloral is a useful remedy in sea-sickness, and in the inco tinence of urine in children.

B.P. Butyl-Chloral Hydras. HYDRATE OF BUT CHLORAL. $C_4H_5Cl_3O.H_2O$.—(*Synonym*: Croton-chloral hydra wrongly so called.)

CHARACTERS.—It forms white pearly crystalline scales, with pungent smell, and acrid, disagreeable taste.

SOLUBILITY.—It is sparingly soluble in water (1 in 100), but is rea soluble in glycerine (1 in 4).

PREPARATION.—By acting on cold dry aldehyd at 14° F., with chlori separating the butyl-chloral by fractional distillation, and converting it i solid hydrous butyl-chloral by the addition of water.

DOSE.—To lessen pain, 1½–5 gr. (0·1–0·3 gm.); as hypnot 5–15 gr. (0·3–1·0 gm.).

ACTION.—It acts much like chloral, though less powerful and has a less depressing effect on the heart, and is much l poisonous than chloral. It is said by Liebreich to affect the fi **nerve** especially, and cause **anæsthesia** in the parts supplied it before general anæsthesia is produced.

USES.—It has been used especially in facial neuralgia a migraine and paroxysmal toothache. It has been used also a hypnotic instead of chloral in cases of weak heart.

ADMINISTRATION.—The disagreeable taste is best covered syrup of tolu, and it may be suspended in almond mixture mucilage.

Bromal Hydrate. C_2Br_3OH. Not officinal.

CHARACTERS.—An oily colourless substance, with a strong ll and burning taste.

PREPARATION.—It is prepared in the same way as chloral hydrate, bromine ur being employed in place of chlorine.

ACTION.—It irritates the eyes and produces running at the e. It has a **narcotic** action like chloral, but causes more itement and less profound sleep. It has a more powerful para- ng action on the **heart**, and is poisonous in smaller doses n chloral. It generally causes salivation, and **profuse secre-** n from the bronchial mucous membrane accompanied by gestion. In toxic doses it produces cyanosis, dyspnœa, and th with convulsions, which are probably due, in great measure east, to clogging of the respiratory passages.

USE.—It is said to have been of use in epilepsy.

Bichloride of Methylene. CH_2Cl_2. Not officinal.

CHARACTERS.—A colourless volatile liquid, with a smell like roform. Sp. gr. 1·344. Boiling point, 40° C. (104° F.).

PREPARATION. — By acting on chloroform with nascent hydrogen, $Cl_3 + H_2 = CH_2Cl_2 + HCl$.

ACTION.—Like that of chloroform but more rapid, though a ger quantity is required. It is said to depress the action of heart more than chloroform, but it has been found a very sfactory anæsthetic in ovariotomy.

It is very doubtful whether the substance sold as bichloride methylene is anything but a mixture of chloroform and alco- as the pure substance is expensive.

Chloroformum, B.P.; Chloroformum Venale, U.S.P.

LOROFORM. $CHCl_3$; 119·2.

CHARACTERS.—A limpid colourless liquid, of an agreeable ereal odour, and sweet taste. Specific gravity 1·497.

SOLUBILITY.—Dissolves in alcohol and ether in all proportions; and in er to the extent of 1 volume in 200, communicating to it a sweetish taste.

REACTIONS.—It is not coloured by agitation with sulphuric acid, leaves no lue and no unpleasant odour after evaporation.

PREPARATION.—By distilling alcohol with chlorinated lime and slaked , washing the distillate with sulphuric acid, and redistilling from slaked and calcium chloride.

In this process the alcohol probably first becomes reduced to aldehyd. m the aldehyd, chloral is formed, and this is broken up by the caustic into formate of calcium and chloroform.

Aldehyd. Chloral.

$$C_2H_4O + 3Cl_2 = C_2HCl_3O + 3HCl.$$

Formate of Calcium. Chloroform.

$$2C_2HCl_3O + Ca(HO)_2 = Ca(CO.OH)_2 + 2CHCl_3.$$

disregarding the intermediate steps, the reaction may be represented :—

Calcium
Alcohol. hypochlorite.

$$4C_2H_6O + 8CaCl_2O_2 = 2CHCl_3 + 3Ca(CO.OH)_2 + 5CaCl_2 + 8H_2O.$$

IMPURITIES.—Hydrochloric acid, chlorine, hydrocarbons, alcohol.
TESTS.—The same as those of purified chloroform.

DOSE.—3 to 10 min.

U.S.P. Chloroformum Purificatum. PURIFIED CHLOROFORM. $CHCl_3$; 119·2.

PREPARATION.—By mixing chloroform (200) with sulphuric acid (60) allowing them to stand, with occasional shaking, for twenty-four hours; t separating the lighter liquid and adding to it carbonate of sodium (10) viously dissolved in water (20). The mixture is then agitated thoroughly half an hour and set aside. The chloroform is then separated from supernatant layer, mixed with alcohol (2), transferred to a dry retort, lime (1) is added, and the liquid distilled, taking care that the tempera does not rise above 67·2° C. (153° F.), into a well-cooled receiver, until residue in the retort is reduced to 2 parts.

TESTS.—If 5 c.c. of purified chloroform be thoroughly agitated with 10 of distilled water, the latter when separated should not affect blue litm paper (absence of acids), nor test-solution of nitrate of silver (chloride), test-solution of iodide of potassium (free chlorine). If a portion be dige warm with a solution of potassa, the latter should not become dark-colo (absence of aldehyd). On shaking 10 c.c. of the chloroform with 5 c. sulphuric acid, in a glass-stoppered bottle, and allowing them to remai contact for twenty-four hours, no colour should be imparted to either liq If a few c.c. be permitted to evaporate from blotting-paper, no foreign o should be perceptible after the odour of chloroform ceases to be recognise

PREPARATIONS.

B.P.		DOSE.
Aqua Chloroformi	1 volume in 200	½–2 fl. oz.
Linimentum Chloroformi (*vide* p. 516)	1 „ 2.	
Spiritus Chloroformi	1 „ 20	20–60 min.
Tinctura Chloroformi Composita	1 „ 10	20–60 min.
„ „ **et Morphinæ**	1 „ 8	5–10 min.

U.S.P.	
Linimentum Chloroformi (*vide* p. 517)	40 per cent.
Mistura Chloroformi	8 „ „
Spiritus Chloroformi	10 „ „

U.S.P. Mistura Chloroformi. CHLOROFORM MIXTURE. Purified chlorofor camphor 2, fresh yolk of egg 10, water 80.

DOSE.—1 to 2 tablespoonfuls.

Spiritus Chloroformi, B. and U.S.P. SPIRIT OF CHLOROFORM.

Chloroform 1 fl. oz., rectified spirit 19 fl. oz., B.P.; purified chloroform alcohol 90, U.S.P.

DOSE.—20 to 60 min.

B.P. Tinctura Chloroformi Composita. COMPOUND TINCTURE OF CHI FORM.

Chloroform 2 fl. oz., rectified spirit 8 fl. oz., compound tincture of cardam 10 fl. oz.

DOSE.—20 to 60 minims.

USES.—The liniment is used as a stimulant and local an thetic. Spirit of chloroform, chloroform mixture, and compo tincture are used as carminatives and sedatives. Chloro water as a vehicle and carminative.

ACTION OF CHLOROFORM.—When mixed with **album** chloroform produces a precipitate, but renders the supernat albumen more easily filtered than before. It is a powerful vent of **protagon**, which forms the essential ingredient bot

nerve-centres, of the nerves themselves, and of the red blood-
uscles, and some authors have considered that to this sol-
t property the action of chloroform as an anæsthetic was, in
e measure at least, due. This, however, is at present hypo-
tical. It appears to lessen the oxidising power of the **blood**,
ough not to a very great extent, for the diminution of this
er is hardly perceptible in the blood of animals poisoned by
roform, although distinct in blood which has been mixed with
When applied to the **skin**, it evaporates rapidly, and produces
eling of cold. When its evaporation is prevented, it passes
ough the epidermis, and acts as an irritant on the skin, produc-
rubefaction, and leaving behind a painful burning spot, or
n vesication. It greatly assists the absorption of organic alka-
ls by the skin, so that a number of them will pass through the
dermis and be absorbed with considerable ease when mixed
h chloroform, although they would not pass through at all if
lied as an alcoholic solution. In the **mouth** it has an exceed-
ly sweet taste, and stimulates the secretion of saliva. When
llowed in large quantities, it acts first as an irritant, produc-
gastro-enteritis, and afterwards, from its absorption, will
se anæsthesia and coma, so that the vomiting, pain at the
gastrium, and purging, which are first observed, gradually
s off, and are succeeded by stupor, coma, and abolition of
ex sensibility, which may either end in death, or may pass
while the irritation of the intestines and stomach may con-
ue for some time afterwards. In small doses it probably
mulates the secretion of gastric juice and the movements of
stomach (cf. p. 367), and both increases and co-ordinates
re perfectly the movements of the stomach and **intestines**, so
t it causes expulsion of flatulence and relieves griping.

After absorption into the blood, either from the stomach or
m the lungs, it acts on the **nervous system** in somewhat the
ne way as alcohol, paralysing the nerve-centres in much the
ne order. Its action, however, is more rapid than that of
ohol, and it does not appear to produce the stimulation with-
derangement of the mental faculties which marks the first
ge of the action of alcohol. Chloroform appears to derange
mental faculties from the very first. The effect of chloroform
y generally be divided into **three stages**: (1) of imperfect
nsciousness, (2) of excitement, and (3) of anæsthesia; or per-
ps one might divide it more exactly into four stages (p. 206),
d add a fourth stage, that of paralysis. Its **first effect** is to
oduce a feeling of warmth over the surface, with affection of
optic and auditory nerves, noises being heard in the ears,
d a sensation of light experienced in the eyes. There is also a
ling of oppression at the chest, and sometimes a choking sen-
ion, occasionally accompanied by cough. The choking and
ugh are more especially felt if the vapour is administered in

too concentrated a form, and not unfrequently the patient put up his hand to try and take away the cloth containing chloroform. External impressions are now slightly felt, sou are faintly heard, questions are slowly and imperfectly answe and any sensation of pain which may be present becomes gre diminished or entirely disappears. In children and weak pers this stage may pass into that of complete anæsthesia, bu most cases it is succeeded by the stage of **excitement.** patient is no longer conscious of what is going on around h but he may, according to his temperament, sing, shout, struggle violently. The violent struggles are more especi noticed in men of irritable temperament, who have been acc tomed to the use of alcoholic stimulants. In them the excitem is greater, and more chloroform is required in order to produce stage of complete anæsthesia. During the violent struggles, efforts of the patient may induce him to hold his breath until su cation seems impending; the face becomes livid, the eyes pro nent, and the jugulars distended. The struggling is usually l in women than in men, and is less in patients exhausted by p vious illness. In women, hysterical sobbing or crying may occ occasionally indications of venereal excitement have been served, and even a complete venereal orgasm. When the chlo form is pushed, this stage soon subsides, and the patient pas into the state of complete **anæsthesia.** The limbs beco flaccid; when the hand is taken up it falls like that of a corps painful stimuli produce neither reflex action nor any indicati of sensation. The last reflex actions to disappear are those fr the conjunctiva, the anus, and the vagina. When touching t conjunctiva no longer causes reflex contraction of the eyel anæsthesia may be regarded as complete, and surgical operatic may be commenced. During the administration of chlorofo the **respiration** is generally first rendered somewhat slow, th quicker, and lastly steady, unless the anæsthetic be pushed t far, when it again becomes slower and weaker, and finally cea altogether. The **pulse** is usually affected in a similar mann The reason of this appears to be that the chloroform vapour, it descends the respiratory passages, successively irritates th parts with which it comes immediately in contact: (1) the na mucous membrane, (2) the larynx, and (3) the lungs. It caus through the nerves of the nose and larynx (p. 242), refl slowing of the respiration and reflex slowing of the pulse. these nerves gradually become paralysed by the action of t drug, its stimulating effect on the branches of the vagus d tributed to the lung becomes manifest in accelerated respiratic usually accompanied by a quickened pulse. Next, as the dr continues to act, it paralyses those nerves also, and the respir tory centre, being now no longer affected by any reflex irritatio continues to keep up the respiratory movements with a som

t slow and steady rhythm. If the drug be now pushed still her, the respiratory centre itself becomes **paralysed,** the irations become still slower and feebler, and finally cease gether. These alterations in the respiratory rhythm during administration of chloroform may sometimes be more or less rfered with by the effect upon the respiratory centre of blood h has become venous in consequence of the altered respira- movements. The action of the **heart** is also modified by roform, the pulse usually becoming somewhat slower just at ; then accelerated during the whole period of excitement; afterwards steady, at or below its normal rate. The **blood-**ssure is usually lowered, and if the chloroform vapour be ng the pressure may fall very considerably, and may even be ced to zero. The fall of blood-pressure is probably due reat measure to the dilatation of the vessels, but it may also partly owing to enfeebled action of the heart, even at the nning of the anæsthesia. When the chloroform has been hed so far as greatly to lower the blood-pressure, the fall is ed, to a great extent, by the weakening of the heart. The tation of the vessels is not due to paralysis of the vaso-motor es, for these, when irritated directly, will still cause the ry to contract during chloroform-narcosis. It appears to be to paralysis of the vaso-motor centre. The reflex power of centre is first diminished, and then abolished, by chloroform, hat irritation of a sensory nerve during imperfect chloroform-osis, causes only a slight rise of blood-pressure, and in per- narcosis no rise at all.

The tension of the **intercellular fluid** and the lymph in the appear to be diminished, so that the **mammæ** become flaccid, intra-ocular tension is diminished, and irregular astigmatism occur.

The **nervous system** appears to be paralysed in the following r: first, the cerebral hemispheres; next, the grey matter of cord; next, the white matter; next, the reflex power of the ulla oblongata; next, the automatic power of the respiratory re, and lastly, the cardiac ganglia.

The order in which the nerve-centres are paralysed may etimes be changed, and the heart may be affected before the iration.

Dangers of Chloroform.—Cases may arise where it is im- ible to obtain assistance, but whenever it is possible to obtain , anæsthetics should never be given without the presence of ird person, both for the sake of the administrator and of patient. In consequence of neglecting this rule, a number of lical men have suffered severely from false charges of assault rape brought against them by female patients. These rges, though perfectly false, have frequently been brought by ents in all good faith, and under the belief that they were

true. The action of alcohol on the sexual centres in the br (pp. 448 and 450) is surpassed by that of chloroform, and sex excitement caused by the latter (p. 798) may be accompanied delusions, which are afterwards remembered and believed by t patients to have been real events. By having an assistant in t room false charges arising from such delusions may be disprov

For the patient's sake also no one should attempt, if it c possibly be avoided, both to administer anæsthetics and operate, for this is more than a single man can do, and t attempt to do both is likely to lead to failure in either one both.

The dangers resulting from the employment of chlorofo are: (1) death by **stoppage of respiration**; (2) death **stoppage of the heart.** Usually the respiration stops bef the heart. This order, however, may be somewhat vari because occasionally the heart will fail before the respiratio This may sometimes be due to the employment of too **stro chloroform vapour,** because this very quickly paralyses t heart; but sometimes the stoppage of the heart before the res ration may be due to the **shock** of the operation, and not to t chloroform.

The **respiration** may **stop** from (1) **obstruction** to the e trance of air into the glottis by the tongue, by vomited matte or by blood, (2) by **mechanical interference** with the respirato movements, (3) by **paralysis** of the respiratory centre. If t heart is naturally feeble it is more apt to become paralyse Aortic or mitral regurgitation do not by themselves contra-indica the use of chloroform; but in all cases the heart should be pr viously examined, and if it is found to be weak and dilated, as emphysema, and especially if there should be reason to susp fatty degeneration, it is safer to employ ether. This is especia the case in persons who have been addicted to the use of alcoh

Precautions.—(1) If the patient should partially wake fr chloroform-narcosis during an operation, sickness is very lik to occur. In order to prevent this, it is well that the patie should take no solid food for four or five hours before the oper tion; but, at the same time, his strength should be kept fr sinking by the administration of beef-tea, along with so alcoholic stimulant three hours before. When vomiting d occur, the head of the patient should be turned on one side, as to allow an easy exit to the vomited matters, which shou if necessary, be removed from the mouth. Mr. Mills tells u that the most common causes of obstruction to the respirati are either falling back of the tongue or depression of the ch Both of these may be remedied by changing the position of t head by turning it on one side, or forcibly drawing the chin aw from the sternum at each inspiration. Very seldom it may necessary to draw the tongue forwards with dressing force

Mechanical interference with the respiratory movements may ur from unwary pressure upon the chest, interfering with the racic movements. The most common cause of this is the ght of the patient's own body, when any operation upon the k requires him to be laid upon his face. In such cases, cial watch should be kept upon the respiratory movements. hanical interference with respiration may occur in old people o have lost their teeth. The flaccid lips and the alæ nasi are hem drawn inwards at each inspiration, and acting as valves vent the entrance of air into the trachea. In such cases the uth should be opened by the fingers (Esmarch).

Stoppage of the respiration may occur from the patient spas- lically holding his breath during the stage of excitement, but usually soon passes off if the anæsthetic be pushed. The ggling is less if the anæsthetic be given gradually. (3) Para- s of the respiratory centre takes place when the drug is hed too far. It may sometimes occur suddenly, after a fresh ntity of chloroform has been poured upon the cloth used in inistration. If the respiration ceases the administration of roform should be discontinued, and the patient roused by king the cheeks and breast with a wet towel. The tongue uld be drawn forwards with forceps and artificial respiration un if necessary. As a rule the patient can be restored with parative ease by means of artificial respiration, provided the rt continues to beat, but on rare occasions even the prolonged of this means does not induce any further voluntary respira- movement. The easiest way of performing artificial respira- is to press the sternum forcibly inwards, and allow it to urn to its normal position by its own elasticity. The pressure uld be exercised synchronously with the operator's own re- ration. Each time the sternum is depressed the ends of the gers may be pressed under the cartilages of the ribs on the side, so as to stimulate the heart mechanically also.

Stoppage of the heart may occur suddenly, and may take e while respiration is still going on. It is usually ascribed he chloroform, and no doubt concentrated chloroform vapour aled into the lungs may arrest the heart. Very commonly, vever, it is reflex, and when death occurs in such a case it is be attributed to the want of chloroform rather than to its ess. It is worthy of note that in the greater number of the es recorded as deaths from chloroform, the statement is made t the quantity administered was very small, and that anæs- sia was incomplete. Before anæsthetics were used at all, th from shock during operation was by no means uncommon, no doubt it still occurs during imperfect anæsthesia, although plete anæsthesia tends to prevent it. The operations in which th during chloroform chiefly occurs are short and compara- ly slight, though painful, such as extraction of teeth, and

evulsion of the toe-nail—operations in which the introduction deep chloroform anæsthesia might be regarded as superfluo and involving a waste of time. These operations appear to dangerous during imperfect narcosis, and not so when either anæsthetic at all has been given, or complete anæsthesia l been produced. The reason of this probably is that when anæsthetic is given, irritation of the sensory nerves during operation causes two effects—slowing or stoppage of the hea and reflex contraction of the vessels. This contraction neutrali the result of cardiac weakness or stoppage, maintains the blo pressure, and thus prevents syncope. During imperfect an thesia, the reflex contraction of the vessels is destroyed, wher the effect on the heart may still persist, so that irritation o sensory nerve may produce syncope by stopping the supply arterial blood from the heart, while the blood still flows rapi from the arterial system through the capillaries into the vei When the anæsthesia is complete, both reflexes are paralysed, a the circulation remains unaffected by any impression made up the sensory nerves. Even when chloroform anæsthesia appe perfectly complete, death from shock may still occur, at any r in the case of animals. I have noticed this on two occasio when engaged in making a gastric fistula in a dog. The anir was completely anæsthetised, but in both instances, when draw upon the stomach in the process of inserting a cannula, animal died suddenly. On mentioning this to Professor Sch he informed me that he had had many similar experiences, that he had entirely abandoned the use of chloroform in su operations, and substituted ether.

When the heart stops, the treatment to be adopted is to the patient's head lower than his body (p. 264), to keep up a ficial respiration, and to administer nitrite of amyl by inhalati

Instead of the plan of artificial respiration already m tioned, Sylvester's may be used. Howard's plan may be u for very strong patients, but is not suitable for delicate on Respiration may be assisted by stimulating the diaphragm the application of a faradaic current to the phrenic nerve. C pole is applied to the epigastrium and the other to the side the neck, and the current is made and broken during the ti that the inspiratory movement is being made artificially.

USES.—The vapour of chloroform may be applied to the in photophobia, to the os uteri in pruritus pudendi, neuralg ulceration, or cancer of the uterus, in order to relieve pain. A f drops held in the hand of the nurse and inhaled by a child wh a paroxysm of whooping-cough comes on, will lessen its violen

The power of chloroform to aid the absorption of vegeta alkaloids may be employed in order to assist their action wh applied externally, but care must be taken not to apply th over too large a surface when using such drugs as aconite

trine in combination with chloroform or chloroform liniment. edget of cotton-wool dipped in chloroform is frequently em- ed as a remedy in toothache; but as the chloroform irritates pulp, and may increase pain afterwards, Ringer recommends ece of linen moistened with chloroform to be folded over the h, so that the vapour may act upon the pulp without irritating It relieves vomiting from gastric catarrh or sea-sickness, ns flatulent distension of the stomach and intestines, and be used in dyspepsia and diarrhœa after the irritant has removed. In cases of dyspepsia and chronic gastritis with ation, washing out the stomach with chloroform water has ed useful, by lessening pain and irritability of the stomach, nishing the dilatation, by preventing decomposition and the ation of gas, as well as by exciting movement and secretion e stomach.

Chloroform, in combination with small doses of morphine, with some adhesive vehicle such as glycerin, is a useful dy in coughs, more especially the coughs of phthisis. When led to an extent quite insufficient to produce even the earlier es of anæsthesia it may relieve the paroxysms of asthma. The stage of chloroform action, viz. partial anæsthesia and par- loss of consciousness, is useful in biliary and renal colic, and her cases of very severe pain, such as intestinal colic, severe algia, aneurism, and during labour. A most ingenious plan dministering chloroform in such cases has been devised by Image, of Bury St. Edmunds. A piece of blotting-paper or is put in the bottom of a tumbler, and moistened with chlo- m. The patient then takes the tumbler in the hand and les the vapour. The shape of the tumbler prevents it from g brought too close to the face, so that the vapour is always led with a free admixture of air. As soon as it begins to effect, the patient's hand and the tumbler drop, so that the lation ceases. When the effect begins to pass off, the patient n raises the tumbler and inhales anew, and so the process go on for a long time, without any further care on the part e attendant than to keep the lint or blotting-paper in the bler moist with chloroform.

n severe cases of chorea with cerebral symptoms, the in- tion of chloroform may be necessary; care is, however, ssary if there be any cardiac disease. In the administra- of chloroform for surgical operations, the towel or napkin be folded so as to form an imperfect cone, into the con- y of which a little chloroform is poured. The towel is then over the patient's face, a few inches from his nose, the apex e cone touching the bridge of the nose, its base being ted downwards, and its margin a couple of inches from the Care should be taken that no part of the towel which is with chloroform touches the face, on account of the burning

sensation which it produces, and that a free admixture of air be lowed and the vapour not administered in too concentrated a st

Another way of giving it is to spread a single fold of napkin over the patient's face, and allow the chloroform to a drop at a time, upon the napkin a little in front of the n The drug may be administered in a similar way upon a v mask covered with a single layer of flannel. In order to av the possibility of the patient inhaling too concentrated a vap an apparatus has been devised by Mr. Clover, consisting o bag of 10,000 cubic inches capacity, which is filled with containing 4 per cent. of chloroform vapour, and from this patient is allowed to inhale by means of a flexible tube an mask. The apparatus is filled by pumping successive quanti of air from a bellows holding 1,000 cubic inches through a heated by hot water, into which 32½ minims of chloroform h been injected, a quantity just sufficient to charge the air w the proper amount of chloroform.

A mixture of 1 part of alcohol with 2 of chloroform and ether, known under the name of the 'A, C, E Mixture,' is so times used instead of chloroform. It is supposed to have advantage of being more stimulant and less depressing to heart than chloroform. One disadvantage of it is that the th constituents evaporate with unequal rapidity, so that at the of an operation a patient may get a much larger proportio chloroform than of the other two.

Iodoformum, B. and U.S.P. Iodoform, CHI_3; 392·8 Iodoform should be kept in well-stoppered bottles, in a cool pl

Characters.—Shining, lemon-yellow, crystalline scales, so what greasy to the touch; having a persistent and disagree odour and flavour.

Solubility.—Very slightly soluble in cold water, more soluble in rect spirit, soluble in chloroform or ether, readily and entirely soluble in w ether; the solutions being neutral to litmus paper.

Reactions.—When heated it first melts to a brown liquid, then give brown and violet vapours, leaving a black residue which entirely disap on continued ignition. Warmed with an alcoholic solution of potash the resulting fluid acidified by nitric acid, iodine is liberated, the mix acquiring a brown colour, or, when cold, a blue colour on the additio mucilage of starch.

Preparation.—By mixing alcoholic solution of potash with tinctu iodine, and evaporating; or by the action of iodine on a mixture of alc and solution of carbonate of potassium or sodium.

Dose.—½–3 grains.

Preparations.

B.P.

Suppositoria Iodoformi.....3 grains in each supposi

B. and U.S.P.

Unguentum Iodoformi (with benzoated lard)...1 part in 10.

Administration.—It may be given in the form of pill, u up with sugar of milk, tragacanth and glycerin, or as a s pository made up with cacao-butter.

s an inhalation in phthisis, a solution may be used con-
ng 20 grains of iodoform, 20 minims of oil of eucalyptus,
) of creasote, ½ fl. oz. rectified spirit, and ½ fl. oz. of ether.
is used with an inhaler of horsehair matting lined with
n-wool, on the interior of which the solution is dropped
schfeld).

he disagreeable smell of iodoform may be covered by Tonquin
(50 per cent.), Coumarin, or to some extent by ground coffee.
s an external application it may simply be dusted over the
and covered with cotton-wool, or cotton-wool may be soaked
ethereal solution of it and then dried. The quantity of
orm in the cotton-wool should be at least 10 per cent. It
be applied to the nose or throat as snuff, or mixed with half
eight of starch as insufflation, or an ethereal solution may
pplied as spray. The nozzle of the spray-producer is apt
come choked and must be washed out frequently with pure
. It may also be applied to the nose in the form of a bougie
aining $\frac{1}{6}$–$\frac{1}{2}$ a grain made up with gelatin and glycerin. In
rrhœa, bougies composed of iodoform 5 grains, oil of euca-
s 10 minims, and cacao-butter 35 grains, are useful in the
stage.

CTION.—Iodoform destroys bacilli, and is an **antiseptic deodorizer** of very considerable power. It also destroys cytes. When applied in substance or strong solution it uces no local irritation, but acts as a **local anæsthetic.** Its r in this respect is so great that a suppository containing it introduced into the rectum may so diminish sensibility defæcation may occur without the knowledge of the person imal (Wood).

s absorption from the intestine is probably aided by fat.

weakens the circulation when taken for some time, and applied to the frog's **heart** it has a powerful paralysing n on the cardiac ganglia in the same way as chloral and (p. 323).

has a marked action on the **nervous system.** In cats dogs it produces narcosis, but not in rabbits. In man it be absorbed from wounds and affect the nervous system, but ad of producing sleep or anæsthesia, as in dogs, it usually s, in slight cases of poisoning, sleeplessness, headache, irrita-, and loss of memory. In severe cases it produces maniacal ks, hallucinations, or melancholia.

hese disagreeable effects appear to be diminished by bicar-e of potassium or sodium in doses of 10 grains hourly.[1] It rs to have an extraordinary power to prevent the develop- of giant-cells, and may thus prevent morbid tissue-growth.

SES.—Its **local anæsthetic** and **antiseptic** actions render

[1] Behring, *Wien. med. Blätt.*, 1884, No. 9.

it useful as a dressing after operations instead of carbolic a and it is especially useful where a regular antiseptic dres cannot be applied, as in operations on the bladder or rectum wounds or ulcers of these parts. It is a most useful applica to poisoned wounds, chancres, phagedænic or syphilitic sc and to fungating growths generally. It induces healthy ac in indolent sores. In deep-seated infiltrations of lupus it is u after the epidermis has been macerated and removed by action of a strong solution of potash. It lessens the disch and disagreeable smell of ozæna. It has been used as a vap in cases of phthisis, and also given internally, but with doul result: an ointment, 1 in 5, has been found useful rubbed the scalp in tubercular meningitis.

Methylal. *Vide* Appendix.


Urethane. *Vide* Appendix.

Iodol. *Vide* Appendix.

CHAPTER XXX.

CARBON COMPOUNDS—AROMATIC SERIES.


RBON NUCLEUS.—In this series the carbon atoms are supposed be linked so as to form a closed chain or chains. The lowest mber of the series contains six atoms of carbon, which are so ked that the group has six free affinities, thus:



For convenience' sake, this carbon ring, or nucleus, is often aphically represented simply thus:



RADICAL.—When five of the free affinities are saturated by drogen, the group forms an organic radical with one free inity, termed **phenyl**:



HYDRIDE. — When this free affinity is also saturated by drogen, the group  forms phenyl hydride, or ben-

ne, or benzol, which must be carefully distinguished from the nzin already mentioned (p. 762).


Bodies belonging to the aromatic group differ from those of e fatty series in the fact that they do not readily link on other bstances to themselves, and so form compounds by addition. hey form them rather by substitution.

ALCOHOL.—When one atom of hydrogen in benzene is placed by hydroxyl (OH), phenyl-alcohol or carbolic acid formed:




The name of **phenol** has been given to this body as it more convenient than the names phenyl-alcohol or carbolic ac and its termination, "**ol**," indicates that it resembles alcohol its constitution.

The relations of some of the other members of the aroma group to each other may be more easily seen if they are put in tabular form:

Benzene, 

Phenol, 

in which 1 atom of hydroxyl (OH) replaces 1 of H in benzene.

Nitrobenzene, 

in which 1 atom of nitroxyl (NO_2) replaces 1 of H in benzene.

Amidobenzene, or Anilin 

in which 1 atom of amidogen (NH_2) replaces 1 of H in benzen


Benzoic acid, or Phenylformic acid, 

in which 1 atom of carboxyl (CO·OH) replaces 1 of H in benzer


Benzoic acid may also be regarded as formic acid in whi one atom of hydrogen is replaced by phenyl, and so it may called phenyl-formic acid.

As the carbon atoms in the benzene ring or nucleus are su posed to be arranged symmetrically, it does not matter whi atom of hydrogen is replaced by another radical if the substit tion takes place only in one atom, e.g. in phenol.

If we number the carbon atoms so as to distinguish the from one another, thus:




is evident that phenol is always the same, whether the hy-
xyl is attached to the carbon atom, 1, 2, or 3, &c. &c. :





t this is not the case when **substitution** occurs **at two or re points** in the benzene ring.

Thus when substitution in the benzene ring occurs at two nts these may take three different positions.





1 and 2 The substitution-products 1 and 6 are the same as 1 and 2, and are usually termed **ortho**-compounds.





1 and 3 1 and 5 are the same as 1 and 3, and are usually termed **meta**-compounds.







1 and 4 1 and 4 are usually termed **para**-compounds.

s three isomeric forms may occur.

When two atoms of hydrogen are replaced by two of hydroxyl, ead of by one, as in phenol, we have three isomeric substances, ering from one another only in the relative position of the stituted atoms. These three bodies are pyrocatechin, in which position is 1 and 2, resorcin, 1 and 3, and hydroquinone, d 4. The relative position of the hydroxyl groups in these e bodies is indicated in their formulæ by the figures (1 : 2), 3), and (1 : 4), or by the terms **ortho, meta,** or **para**, re-tively.



Pyrocatechin.
-di-hydroxy-benzene.
$C_6H_4.(OH)_2(1:2)$




Resorcin.
Meta-di-hydroxy-benzene.
$C_6H_4.(OH)_2(1:3)$




Hydroquinone.
Para-di-hydroxy-benzene.
$C_6H_4.(OH)_2(1:4)$

When three atoms of hydrogen in benzene are replaced by h
droxyl we get tri-hydroxy-benzene—pyrogallol or pyrogallic ac




$C_6H_3.(OH)_3$.
Tri-hydroxy-benzene.
Pyrogallol.

When two atoms of hydrogen in benzene are replaced, t
one by hydroxyl (OH) and the other by carboxyl (CO.OH),
get three isomers, salicylic acid, oxybenzoic acid, and pa
oxybenzoic acid.




Salicylic Acid. Oxybenzoic Acid. Para-oxybenzoic Acid.


Pyridine (C_5H_5N) is probably formed by one atom of tetra
in the benzene ring being replaced by triad N:



Naphthaline ($C_{10}H_8$) is formed by the union of two benz
groups, thus:



Chinoline (C_9H_7N) is formed by the union of benzene and yridine groups:



Chinoline is closely connected with quinine, from which it ay be produced, and it is probable that many of the **organic kaloids** are closely related to the aromatic series.

That morphine, for example, is related to phenol is shown y the fact that when morphine is treated with nitric acid and eated with water under pressure, it yields tri-nitrophenol, or icric acid.[1]

General Action.—The distinctive action of the lower members of the **fatty series** is their **stimulant** and **anæsthetic** action n the nerve-centres (p. 760). The most marked action of the wer members of the **aromatic series** is their **antiseptic** and **ntipyretic** power. The antiseptic action appears to be very asily modified by slight changes in some substances of this roup. Thus salicylic acid is antiseptic, but its sodium salt is ot; and meta- and para-oxybenzoic acids, which are isomeric ith salicylic acid, have no antiseptic power. The members of he aromatic series also affect the **nervous system**, but they ppear to affect the motor centres more than the sensory, so that stead of producing anæsthesia, like the members of the fatty eries, they tend rather to produce tremor, convulsions, and aralysis. Benzene, chlorobenzene, bromobenzene, and iodobenzene are all somewhat similar in their action upon frogs; the alogen radicals not modifying the action of the benzene to such n extent as they do in the case of ammonium salts. The voluntary muscles are weakened by them and there is a slight tendency to paralysis of the motor nerves; but the action is chiefly xerted on the brain and spinal cord. The brain is first affected, s shown by general lethargy and disinclination to move. Next he cord is affected; motions are imperfectly performed, and there a tendency to general tremor on movement resembling that observed in disseminated sclerosis; sometimes, however, the tremor observed independently of movement (Brunton and Cash).

The addition of hydroxyl into the benzene nucleus intensifies he convulsant action, so that oxybenzene (carbolic acid) and

[1] Chastaing, *Compt. Rend.*, xciv. 44.

dioxybenzene cause convulsions in frogs, and trioxybenzene cause jerkings, though of a slighter character.

All the members of the pyridine and chinoline series destro life, either by exhaustive convulsions or by gradual paralysis o the respiratory centres.[1] The members of the pyridine series– pyridine, picoline, lutidine, etc.—have an action similar in kinc but differing in degree, the lethal power increasing as one ascend in the series. The higher members of the pyridine series hav an action like that of the lower members of the chinoline series but are more liable to cause death by asphyxia than the chinc lines, and have more than twice their lethal power.

In ascending the chinoline series, a change occurs in th physiological action of its members, the lower ones acting chiefl on the sensory centres of the brain and reflex centres of th cord, destroying voluntary and reflex movement; while th higher act chiefly on the motor centres, first as irritants causin violent convulsions, and afterwards producing paralysis.

'On comparing the action of such compounds as chinolin (C_9H_7N) with parvoline, etc. ($C_9H_{13}N$), or collidine ($C_8H_{11}N$) wit coniine ($C_8H_{15}N$), or dipyridine ($C_{10}H_{10}N_2$) with nicotine ($C_{10}H_{14}N_2$) it is observed that the physiological activity of the substanc is, apart from chemical structure, greatest in those bases con taining the larger amount of hydrogen. Further, when the base of the pyridine series are doubled by condensation, as in dipyri dine, parapicoline, etc., they become not only more active physio logically, but have a different action from that of the simple bases.'[2]

As alterations in the physiological action of the carbon com pounds of this group can be effected by slightly changing thei chemical composition, several attempts have been recently mad to obtain artificial alkaloids which should possess a strong anti pyretic action without depressing the heart or causing sickness Antipyrin, one of the most recent introductions, appears to b the best as yet, but further attempts in this direction may b still more successful.

U.S.P. Acidum Carbolicum Crudum. CRUDE CARBOLIC ACID.

CHARACTERS.—A nearly colourless or reddish-brown liqui of a strongly empyreumatic and disagreeable odour, having benumbing, blanching, and caustic effect on the skin or mucou membrane, and a neutral reaction.

REACTIONS AND TESTS.—Bromine water produces in an aqueous solutio of carbolic or cresylic acid a white flocculent precipitate. Crude carboli acid should not dissolve in less than 15 parts of water at 15° C. (59° F.), no should the solution have an alkaline reaction (absence of alkalis). If 5 volumes of crude carbolic acid be diluted with warm water to measure 1,00 volumes, the mixture well shaken, cooled, and allowed to separate, th amount of undissolved impurities should not exceed 5 volumes or 10 pe cent. by volume of the crude acid.

[1] McKendrick and Dewar, 'On the Physiological Action of the Chinoline an Pyridine Bases,' *Proc. Roy. Soc.*, 1874, p. 432. [2] McKendrick and Dewar, *op. cit*

Acidum Carbolicum. B. and U.S.P. CARBOLIC ACID. HENOL. PHENYL-ALCOHOL. C_6H_5HO; 94.

A substance obtained from coal-tar oil by fractional distillation d subsequent purification.

CHARACTERS.—In colourless acicular crystals, which at a temrature of 95° F. become an oily liquid, having a strong odour d taste resembling those of creasote, which it also resembles many of its characters and properties. Its specific gravity is 065; boiling-point, 370° F.

SOLUBILITY.—The crystals readily absorb moisture on exposure to the , and they are thus liquefied; the acid, however, is soluble in water to the ent of only 5 per cent., but it is freely soluble in alcohol, ether, and rcerin.

REACTIONS.—It does not redden blue litmus-paper. A slip of deal dipped o it, and afterwards into hydrochloric acid, and then allowed to dry in the , acquires a greenish-blue colour. It coagulates albumen. It does not ect the plane of polarisation of a ray of polarised light.

DOSE.—1 to 3 grains.

PREPARATIONS.

B.P.

idum Carbolicum Liquefactum .....about 90 per cent.
ycerinum Acidi Carbolici. Glycerine of Carbolic acid (Carbolic acid 1, Glycerine 4 by measure) .....1 part in 6 by weight.
ppositoria Acidi Carbolici cum Sapone. Carbolic Acid Suppositories. Carbolic acid, 1 gr.; curd soap, 15 gr.; starch, q.s. to give consistence.
nguentum Acidi Carbolici (Carbolic Acid, 1; soft paraffin, 12; hard paraffin, 6).

U.S.P.

Unguentum Acidi Carbolici (with ointment 1 in 10).

B.P. Acidum Carbolicum Liquefactum. LIQUEFIED RBOLIC ACID.—Carbolic acid liquefied by the addition of 10 r cent. of water.

CHARACTERS.—A colourless or very slightly reddish or brown- liquid having the taste, odour, &c., of carbolic acid.

SOLUBILITY.—It dissolves in 18 to 26 per cent. of water at 60° F. (15·5° C.), lding a clear or nearly clear solution, from which any slight coloured purity contained previously in the acid separates as dark oily drops.

DOSE.—1 to 4 minims.

ACTION.—Carbolic acid is a powerful **deodoriser** and **disfectant** (p. 106). It precipitates **albumen**, and destroys low ganisms. It prevents the decomposition of albuminous fluids **bacteria**, and the fermentation of sugar by **yeast**. Quantities naller than those which are sufficient to kill these organisms ffice to prevent their development. It does not appear to stroy the action of all **organic ferments** so readily, although does so when applied for a long time, or in concentrated lution; it prevents the conversion of starch into sugar, the nversion of albumen into peptones, and the decomposition of nygdalin with formation of hydrocyanic acid. When applied

to the **skin** it produces a white stain, and greatly diminishes th sensibility of the part. The stain afterwards becomes brownish and of a parchment-like consistence, and the epidermis by-and by peels off. Carbolic acid does not act as a vesicant, but ap pears to cause anæsthesia of the part to which it is applied extending to some distance below the surface. If applied over large surface of skin it may be absorbed to such a degree as t cause poisoning, and even death. The symptoms are weakness delirium, and collapse. When applied to **mucous membrane** it has a similar action. In the mouth it causes a burning pain and when swallowed produces symptoms of gastro-enteritis, pai in the stomach, and sometimes vomiting and purging. Alon with this there is great collapse, delirium, and death, sometimes though not always, preceded by convulsions, the pupils bein contracted. After death the **blood** is found to be very dark and its **coagulability** greatly diminished. Carbolic acid appear to be a powerful poison to all the tissues, paralysing both **muscle** and **nerve** when applied directly to them without previously stimulating them. After absorption it acts especially on th **medulla oblongata**, but acts also on the **spinal cord**, firs stimulating and then paralysing these centres. From its actio on the cord it produces in frogs **convulsions** resembling thos of strychnine, these being followed by paralysis. It first stimu lates the **respiratory** and **vaso-motor centres**, and afterward paralyses them. It thus produces at first quickened respiratio with rise of **blood-pressure**, and it also quickens the **pulse**. A the centres become paralysed the blood-pressure falls greatly the respiration becomes slower, and the pulse also becomes slower When it is injected directly into the blood, so that it can act i large quantity on the nerve-centres, it paralyses the vaso-moto centre at once, and causes the blood-pressure to fall very greatly without much alteration being observed in the action of the hear itself. That the vaso-motor centre is completely paralysed by carbolic acid is shown by the fact that after its injection th blood-pressure is not raised either by stimulation of sensory nerves or by asphyxia. Although carbolic acid acts first an most markedly on the nerve-centres in the medulla oblongata i affects the **cerebral centres** also. This effect is evidenced i man by headache, giddiness, and lassitude, followed by uncon sciousness. In animals it also affects the cerebrum, as show by alterations in sensibility and motor power. It stimulates th **sweat** centre and **salivary** centres, producing perspiration an salivation. Medium doses appear to cause death by paralysis o the respiration, so that artificial respiration may be of some us in preventing it; but large doses paralyse the heart also, so tha death occurs in spite of artificial respiration. It diminishes th **temperature** in cases of poisoning, and also when given t animals in a febrile condition, though when the fever is very

h it does not seem to have much effect. It is excreted by kidneys, and can be readily detected in the urine by bromine er. It sometimes gives rise to a very dark colouration of the ne, due to some oxidation-product of the carbolic acid, probably droquinone (p. 809).

Part of the carbolic acid appears in the urine, in combination h sulphuric acid, as sulpho-carbolates, and if the quantity ministered has been large the ordinary sulphates may com- tely disappear. The hydroquinone occurs also to a great ent in the urine in combination with sulphuric acid. The npound is colourless, and thus the urine, when freshly passed, a normal appearance; on standing, the hydroquinone be- nes free, undergoes further oxidation, and causes the urine to ume a brown colour.

Treatment of Poisoning.—The stomach should be emptied emetics, or best by the stomach-pump. Demulcents, such as e oil, should then be administered. For the treatment of the neral symptoms following carbolic acid poisoning, and to aid elimination in the urine, the administration of sulphates .g. sodium sulphate in 10-grain doses—is advisable.

Uses.—It has sometimes been applied externally to produce al anæsthesia for slight operations, such as opening abscesses. When mixed with oil, in the proportion of ten minims to an nce of oil, it relieves the pain of burns. One of the best means removing the pain of toothache is to dip a little cotton-wool carbolic acid melted by the aid of heat, and insert the dget into the cavity of the tooth, covering it over with dry ton-wool, to prevent the tongue being burned by contact with acid. It is used as a stimulant to indolent ulcers and nds, and to destroy condylomata, and has been applied to throat in cases of diphtheria, ulceration, and aphthæ. It has n employed as an injection in deep-seated inflammations h as chronic synovitis, inflamed glands, boils, hydrocele, ery- elas, and poisoned wounds. Carbolic acid, 2 per cent. in ple ointment, is useful in relieving itching in chronic eczema l urticaria, and in papular eczema it gives relief when applied a lotion of one part of the acid to one part of boric acid and parts of alcohol. It is used locally as an antiparasitic in favus, ea versicolor, and ringworm. Its chief application, however, o destroy the minute organisms which cause putrefaction in uminous fluids, and to prevent the untoward results which uld arise from the absorption of putrid discharges.

According to Sir Joseph Lister, the untoward consequences of rations are frequently due, not to the operation itself, but to poisoning of the wound by the products of decomposing dis- rges, and poisoning of the system generally by absorption these products. The decomposition is due to low organ- s, such as bacteria, introduced from without, and it may be

prevented by the use of such substances as will prevent th development or destroy them when present. In performing ope tions, therefore, he advises that the skin should first be wash with a watery solution of carbolic acid (1 in 40), that the inst ments also should be treated with a similar solution, and that t incision should be made under a spray of carbolic acid (1 in 6C After the operation is concluded under a constant use of t spray, the wound is covered with a protective consisting of va nished linen dipped in a solution of carbolic acid (1 in 40), abo which are laid eight layers of gauze, steeped in a mixture carbolic acid (1), resin (4), and paraffin (4). Between the six and seventh layers is put a piece of waterproof tissue, in order distribute the discharge and prevent it from oozing out at o spot. If the discharge be great the dressings ought to be chang once in twenty-four hours, under the spray; but as the wou heals, the intervals between the dressings may be lengthened.

A solution of carbolic acid in oil is frequently used to lub cate, and at the same time disinfect, catheters (p. 105); but, Koch's experiments show, such a solution has no antisep power, and they ought to be first disinfected with an aque solution and afterwards oiled.

Carbolic acid is very useful in what is sometimes known an influenza cold, beginning with coryza, spreading down t throat to the air-passages, leading to severe bronchitis with mu depression, and occasionally also to gastro-intestinal catar This form of cold appears, like true influenza, to be extrem infectious, and to be easily communicated, not only by o member of a family to another, but even by casual visitors. may sometimes be arrested, and may frequently be rendered l severe, by carbolic acid spray applied to the nostrils and by t use of a gargle containing carbolic acid. Other forms of so throat are also relieved by gargles containing about 1 per ce of carbolic acid. Considerable care must be taken in using t gargle not to swallow it, on account of the poisonous properties the acid. When the cold begins in the nose the solution of c bolic acid for spray may contain 1 per cent., but perhaps a s better method of applying it is by a small ear-syringe, as a $\frac{1}{4}$ $\frac{1}{2}$ per cent. solution. A mixture of 1 part of carbolic acid w 3 of creasote has been used for continuous inhalation in phthi by means of the oro-nasal respirator.

Carbolic acid is also used as an injection to wash out serc cavities, after the evacuation of fluids; for example, the cav of the pleura after the evacuation of the fluid in pleurisy, a the cavity of an abscess after the removal of the pus. Internal the acid has been given in cases of flatulent dyspepsia. It i

[1] The strength of solution placed in the bottle of the spray-producer is 1 in but when mixed with the steam it is reduced to 1 in 60.

ful application to the uterus in chronic inflammation, excoria-
, catarrh, and cancer, and as an injection in leucorrhœa.

Sodii Sulpho-carbolas, B. and U.S.P. *Vide* p. 626.

B.P. Zinci Sulpho-carbolas. *Vide* p. 671.

Creasotum, B. and U.S.P. CREASOTE.

A product of the distillation of wood-tar.

CHARACTERS.—A liquid, colourless or with a yellowish tinge, a strong empyreumatic odour. Specific gravity, 1·071.

OLUBILITY.—It is sparingly dissolved by water, but freely by alcohol r, and glacial acetic acid.

EACTIONS.—It coagulates albumin. A slip of deal dipped into it, and wards into hydrochloric acid, acquires on exposure for a short time to ir a greenish-blue colour. Dropped on white filtering paper and exposed heat of 212° F., it leaves no translucent stain. It turns the plane of isation of a ray of polarised light to the right. It is not solidified by the produced by a mixture of hydrochloric acid and sulphate of sodium.

DOSE.—1 to 3 drops.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
ura Creasoti (1 min. in 1 fl. . nearly)	1–2 fl. oz.	Aqua Creasoti	1–4 fl. dr.
entum Creasoti (with simple ntment, 1 part in 9)			
or Creasoti			

S.P. Aqua Creasoti. CREASOTE WATER. Creasote, 1; distilled water, 99; e and filter.

.P. Mistura Creasoti. CREASOTE MIXTURE.

ke of creasote 1 part, glacial acetic acid 1 part, spirit of juniper 2 parts, 32 parts, distilled water 480 parts.

.P. Vapor Creasoti. INHALATION OF CREASOTE.

ix creasote (12 min.) and water (8 fl. oz.) in an apparatus so arranged that air e made to pass through the solution, and may afterwards be inhaled.

ACTION.—Creasote destroys low vegetable organisms, and pre- s the fermentation which they cause. When administered mall animals, it causes great dyspnœa, weakening of the t's action, paralysis, and often sudden death. Its action rs from that of carbolic acid in the absence of convul- s and in causing increased coagulability of the blood.

reasote is a powerful muscular poison. It coagulates albu- and blood. When applied to the skin it destroys the elium, and has a similar action upon mucous membranes. e mouth it produces a burning sensation and much sali- n. Large doses taken internally cause nausea, vomiting, y pains, and diarrhœa. The pulse is quickened, there is ness and headache, the respiration is slow and laboured, he secretion of urine is increased.

SES.—It is often employed as a remedy in toothache, a l pledget of cotton wool being dipped into it and placed in avity of the decayed tooth. Care should be taken to cover

this with fresh cotton wool, to prevent the tongue from bei burned. Internally, it is given in cases of vomiting dependi upon abnormal processes of fermentation in the stomach, and is said to relieve vomiting due to other causes, such as ulce tion of the stomach, cancer, Bright's disease, sea-sickness, a pregnancy. It is useful in diarrhœa, especially that of childr where the diarrhœa depends upon irritation due to abnorn fermentation-processes in the intestinal contents. The vap is used in phthisis and fœtid bronchitis.

Resorcin. $C_6H_4(OH)_2(1:3)$. META-DI-HYDROXY-BENZE (*vide* p. 809). Not officinal.

CHARACTERS.—White crystalline plates somewhat like benz acid, melting at 99° C. It has a sweetish harsh taste.

SOLUBILITY.—It is soluble in less than 2 parts of water and 20 of olive

REACTION.—The aqueous solution gives a dark violet colour with fe salts.

DOSE.—5–30 grs. (0·3–2 gm.). It is best given with syr of oranges and freely diluted.

ACTION.—It is a powerful **antiseptic**. It coagulates all min. A saturated solution has a caustic action on the skin, l a weak solution—e.g. 5 per cent.—is not irritating to the sl or mucous membranes. In **frogs** it produces stupor, collap clonic spasms, and dyspnœa like carbolic acid. In **war blooded animals** it also causes clonic convulsions, dyspn dilatation of the vessels and increased secretion of saliva a tears. Death occurs through paralysis. Large doses in **man** 30 grs. or more—cause giddiness, singing in the ears, sympto of intoxication, like those of alcohol, convulsive tremors a collapse. In febrile conditions it greatly lowers the temperatu

USES.—It is a powerful **antiseptic** and has been employ locally in diphtheria. A 5 per cent. solution has been used an application to syphilitic sores and skin diseases, and as injection into the bladder in cystitis. It appears to shorten t duration of facial erysipelas when applied every four hours, the form of a 25 per cent. ointment made with vaseline. A per cent. solution has been used as a collyrium. In infant cholera it has proved very useful in doses of $1\frac{1}{2}$–5 gra (0·1–0·3 gm.), given in infusion of chamomile. Doses o grains three times a day before meals are useful in prevent fermentation in the stomach. As an **antipyretic** it lessens t temperature in phthisis and in typhoid, to a less extent in pn monia and erysipelas. It has also been used in ague.

Its disadvantages are the profuse perspiration which it p duces, the short duration of its antipyretic action, and the rapid with which the temperature again rises.

Hydroquinone. $C_6H_4(OH)_2(1:4)$. PARA-DI-HYDROXY-BENZE (p. 809). Not officinal.

CHARACTERS.—In crystals or plates with a slight sweetish taste.
ACTION.—Like that of resorcin, but about four times stronger.
USES.—Similar to those of resorcin.

Pyrocatechin. $C_6H_4(OH)_2(1 : 2)$. ORTHO-DI-HYDROXY-BENZENE 809). Not officinal.
CHARACTERS.—It forms crystals or plates.
SOLUBILITY.—It is readily soluble in water, alcohol, and ether.
REACTION.—It reduces cupric sulphate.
ACTION.—Like that of resorcin, but it is about three times onger.
USES.—Like those of resorcin.

Pyrogallic Acid. PYROGALLOL, TRI-HYDROXY-BENZENE, $H_3(OH)_3$ (*vide* p. 810). Not officinal.
CHARACTERS.—Light, glistening crystals.
PREPARATION.—By heating gallic acid.
SOLUBILITY.—Readily soluble in water and alcohol.
REACTION.—It rapidly combines with oxygen, becoming dark in colour.
DOSE.—$\frac{1}{2}$ to $1\frac{1}{2}$ gr.
ACTION.—It has a doubtful **antiseptic** action. In mammals decomposes the red blood-corpuscles, causing brownish dis-oration of the skin and mucous membranes, thrombosis in veins, **hæmorrhagic** infarcts in the kidneys and methæmo-bin or blood in the urine. In man the symptoms of poisoning ne on rapidly, with headache, vomiting, purging, and collapse.
USES.—Pyrogallol is chiefly used **externally** in skin diseases. 20 per cent. ointment has been used as a caustic in lupus, cer, and chancres. It appears to destroy the diseased part hout affecting the surrounding healthy tissue. In place of the tment, a 20 per cent. powder with starch may be used. As n as the wound granulates it is dressed with iodoform: the n is short and moderate, and no danger is to be apprehended m absorption.[1] In lupus erythematosus, a 10 per cent. oint-nt may be applied twice daily for three or four days, anti-tics being afterwards used. An ointment of similar strength l similarly applied is of great service in patches of psoriasis, ecially of the face and hands. It does not, like chrysarobin, in linen; but the risk of absorption must be considered, as moglobinuria has followed its application to large surfaces of body. It is useful in tylosis of the palms and soles, and a 2 cent. alcoholic solution may be painted with beneficial result r large tubercles in acne rosacea, after poulticing.
Internally it has been given in hæmorrhage.

Acidum Salicylicum, B. and U.S.P. SALICYLIC ACID. $C_7H_5O_3$; 138 (p. 810).

[1] *Bull. de Thérap.*, Jan. 30, 1883; *Centralblt. f. d. med. Wissenschaft*, No. 42, 3.

A crystalline acid obtained by the combination of the elemen of carbolic acid with those of carbonic acid gas and subseque purification, or from natural salicylates such as the oils of winte green (*Gaultheria procumbens*, Linn.) and sweet birch (*Betu lenta*, Linn.).

CHARACTERS.—In white acicular crystals, inodorous but lig and easily diffused and then irritating to the nostrils; taste first sweetish, then acid.

The crystals melt at about 311° F. (155° C.), and bel 392° F. (200° C.) volatilise without decomposition.

SOLUBILITY.—It is soluble in 500 to 700 parts of water at ordinary tem ratures; readily soluble in alcohol, ether, and hot water; soluble also solutions of citrate or acetate of ammonium, phosphate of sodium, or bora

REACTIONS.—The aqueous solution gives with solution of perchloride iron a reddish-violet colour. An alcoholic solution allowed to evapor spontaneously should leave a perfectly white residue.

DOSE.—5 to 30 grains.

B.P. PREPARATION.

Unguentum Acidi Salicylici (salicylic acid, 1; soft paraffin, 18; h paraffin 9).

OFFICINAL SALICYLATE.

Sodii Salicylas.

ACTION.—When mixed in a proportion of 1 to 10 per ce with fluids containing the germs of **bacteria** it will preve their development, and in the proportion of 1 in 60 will destr bacteria when swarming in a fluid (p. 91). Salicylic acid lik wise destroys the life of the torula, and prevents alcoholic f mentation, as well as the fermentation caused by the orga ferments, &c. (p. 78).

It has little power to reduce the **temperature** in health, l is a most powerful agent in lowering the temperature of fev When injected into the blood, or administered by the stomach large quantities, it lowers the pulse-rate, blood-pressure, a respiration. When taken in medicinal doses for some time produces noises in the **ears**, deafness, giddiness, and headac in this respect resembling quinine. Occasionally it has cau sudden depression of the circulation and collapse.

In large doses salicylic acid causes feeble **circulation**, low the blood-pressure, and produces death through paralysis of **respiration.** It is excreted in the perspiration, saliva, a urine. During its **excretion** it frequently irritates the kidn and produces albuminuria. It appears in the urine partly salts of salicylic acid, and partly in combination with glycol salicyluric acid. After its use the urine is not unfrequer brown by reflected and green by transmitted light, and conta a substance which reduces copper solution.

USES.—Externally it has been employed as an antise instead of carbolic acid, and has been used by insufflation

htheria successfully. A mixture of 2 parts with 100 of tallow plied directly to the feet, not to the stockings, has been found st useful in preventing sweating and soreness of the feet in liers after a long march. In intertrigo 1 to 2 per cent. in rch soothes the irritation and prevents decomposition of the at. A lotion (4 per cent.) is useful in pruritus and chronic icaria, and one of half per cent. in alopecia furfuracea. It s been recommended for soft sores, which should be kept ered with the pure acid for two days, and then treated with ollient ointment. Salicylic acid dissolved in collodion flexile . XXX. to 3j.) is very useful for corns and warts, and in a ster with gutta-percha in corns, tylosis, and in the thickened ches of chronic eczema; also to hasten the peeling of the ms and soles after scarlet fever.

In doses of 3 to 5 grains taken during meals it is very useful arresting fermentative changes in the stomach and prevent- acidity and flatulence. It is usually employed internally in form of salicylate of sodium (p. 628). As already mentioned s useful both in acute and chronic rheumatism. It is of much s use in typhoid fever than in rheumatism, and, although it s some antiperiodic action, it is not such a powerful remedy malarious affections as quinine. Salicylate of sodium is useful phlegmasia alba. As already mentioned, it relieves headache. seems to have a peculiar power of increasing the secretion of e and rendering it more watery. In this it differs from most er cholagogues, which increase the proportion of solids in the e. It is therefore indicated in cases where there is a tendency the formation of gall-stones.

Naphthalin, $C_{10}H_8$ (*vide* p. 810). Not officinal.

SOURCE.—It is prepared from tar.

CHARACTERS.—Colourless micaceous crystals with a peculiar ell.

SOLUBILITY.—Insoluble in water, dilute acids or alkalis. Sparingly ible in cold alcohol, more readily in hot alcohol.

PURIFICATION.—As the commercial naphthalin is often impure it should purified by washing it with alcohol on a filter until the alcohol is colour-, then drying and subliming.

DOSE.—For adults 1½–8 grains as a single dose. As much 80 grains may be given during the day. For children, 1½–3 ins every three hours.

ADMINISTRATION.—In the form of powder mixed with sugar l scented with oil of bergamot it may be taken in wafers or psules. It may be used as enema, but as it is quite insoluble water it must be suspended in a mucilaginous vehicle such as coction of marsh mallow. The best way of doing this is by xing the quantity of naphthalin required (15–75 grains) with r 3 fluid ounces of boiling distilled water, and stirring until

it is diffused in very fine drops throughout the liquid. It shou then be poured into 15 or 30 fluid ounces of boiling mars mallow tea and vigorously stirred. The liquid is then allowed cool, and introduced into the rectum by a soft tube and funn (p. 484).

Action.—It destroys low organisms and prevents the ge mination of their spores. It is a powerful **antiseptic**, but must be intimately mixed with the substances on which it is have this action. It has little or no poisonous action on th higher animals when given either by inhalation or internall the reason probably being that it is so sparingly soluble that is not absorbed in sufficient quantity from the intestinal can to be injurious to the organism. When given internally it di infects the whole contents of the intestinal canal, so that the fæc have either no smell at all or a faint smell of naphthalin. It so sparingly soluble that most of it remains in the intestine an acts on the contents of the intestinal tube along its whole lengt from the stomach to the rectum. It is excreted in the urin partially unchanged and partially as naphthol and perhaps phenc

Uses.—It may be used wherever it is desirable to destro germs and stop processes of putrefaction or fermentation in th intestine. It has proved useful in typhoid fever, diarrhœa acute and chronic, vomiting and diarrhœa in children, and tu bercular diarrhœa. During its excretion by the kidneys th urine is rendered aseptic by it or by the products of its decom position, and it is therefore useful in vesical catarrh.[1] It i possible that it may be useful in cholera.

Naphthol. $C_{10}H_7OH$.—There are several kinds of naphtho The only one hitherto used is the beta- or iso-naphthol. No officinal.

Characters.—In white crystals with a somewhat agreeabl smell.

Solubility.—Sparingly soluble even in hot water. Soluble in alcoho ether, and chloroform, in olive oil and vaseline.

Action and Uses.—It has a therapeutic action on the ski like tar, and may be applied as ointment in the strength of 1 t 5 per cent., for children not over 2 per cent. It is useful i hyperidrosis (Kaposi). It is used in scabies, eczema, and loca sweating. It may be applied in ½ to 5 per cent. alcoholic solutio or as an ointment (10 per cent.). When absorbed it cause vomiting, loss of consciousness, convulsions, and hæmaturia.

Hydrochlorate of Rosaniline. *Synonyms:* Fuchsin, M genta, Roséine, Aniline Red. $C_{20}H_{19}N_3HCl$. Not officinal.

Characters.—Elongated crystals with a brilliant green lustr

[1] Rossbach, *Berlin. klin. Wochenschr.*, 1884, Nos. 24, 42, 46.

SOLUBILITY.—It is readily soluble in water, giving a bright red solution.
PREPARATION.—Rosaniline is a colourless substance, prepared by acting aniline with oxidising agents, such as arsenic acid. The compounds of aniline with monobasic acids have brilliant colours.

DOSE.—$\frac{1}{2}$–4 grs.
ACTIONS.—Rosaniline hydrochlorate, when perfectly pure, is d to have no marked physiological action. Fabrics dyed with have acted as local irritants, producing eczema; but it is bable that this effect may be due, at least in great part, to presence of arsenic. When given internally it has produced ivation, vomiting, diarrhœa, and when injected into the veins has caused trembling, staggering, albuminuria, and fatty generation of the kidneys. These symptoms may possibly be e to the presence of aniline or of arsenic as impurities. It is reted by the kidneys, saliva, and bile, and probably also by intestinal mucous membrane. It gives a magenta colour to urine.
USE.—To lessen or remove albumin from the urine in albuuria.

Pyridine. C_5H_5N (p. 810). Not officinal.
CHARACTERS.—A colourless liquid with a powerful odour. It porates when exposed to the air, and mixes with water in all portions. Like chinoline it forms salts.
DOSE.—4–5 gm., allowed to evaporate in an open dish in a m of 25 cubic metres capacity. The patient must be exposed the vapour for twenty to thirty minutes three times a day.[1]
ACTION.—(See also p. 811.) According to Sée it has been nd by experiments on animals to diminish the reflex activity the spinal cord and respiratory centre.
USES.—On account of its sedative action upon the respiratory tre, pyridine has been used in the manner described with benefial effect in cases of asthma; the emphysematous and cardiac ms as well as the purely nervous seem to be benefited.

Chinoline. C_9H_7N (p. 811). Not officinal.
CHARACTERS.—A colourless liquid with an aromatic odour. It ms crystalline salts.
DOSE.—Of the tartrate 7–15 grs. (0·5–1 gm.).
ACTION.—It is a powerful **antiseptic** and **antipyretic**. In derate doses it lowers the temperature and pulse-rate. In ge doses it produces languor, diminished reflex excitability, spnœa, paralysis and collapse (*vide* p. 811).
USES.—It has been used in typhoid fever, rheumatism, and rsipelas, apparently with benefit. It is little used in pneunia; and in phthisis it is apt to irritate the stomach and proce collapse.

[1] Germain Sée, *Comptes Rend. Ac. Scien.*, 1886.

Kairin. Hydrochlorate of oxy-ethyl-chinoline Hydrid Not officinal.


Dose.—3–30 grs. Best given in wafer-paper or a capsule.

Action.—It is a powerful **antipyretic.**


Uses.—Used in febrile conditions to lower the temperatur Filehne recommends that doses of 8 grains should be given eve hour at first for four times or until the temperature has fallen t 100° F. If the temperature falls after four doses, 4 grains shou be given hourly until the temperature again begins to rise, whe the dose should be increased. If the temperature has not falle to 100° after four doses of 8 grains, 12 or 16 grains should l given hourly, until the temperature of 100° F. is reached, whe the dose should be lowered as before. Like resorcin, it pr duces profuse sweating.

Antipyrin. Not officinal. A synthetically prepared alkaloi There are two substances bearing this name, viz. methy oxy-chinicine and dimethyl-oxy-chinicine. The latter is th commercial drug.

Chinicine or quinicine is a hypothetical base. The suppose constitution of chinicine and methyl-oxy-chinicine may be thu graphically represented :—



Chinicine or Quinicine.



Methyl-oxy-chinicine.

Solubility.—It is very readily soluble in water, with a sweetish bitt and rather pleasant taste.

Reactions.—Its solutions give with ferric chloride a deep red, and wi nitrous acid a greenish blue colour.

Dose.—Thirty grains hourly for three hours. For childre a grain and a half for every year of the child's age may be give hourly for three hours. If it causes vomiting it may be di solved in half its weight of hot water and injected subcut neously.

Action.—It reduces the febrile temperature for several (1–2 hours when given as above in two or three doses (*vide* p. 419 and when its effect has passed off, the rise of temperature whic then occurs is less frequently accompanied by rigor than is th case with kairin. It causes profuse **perspiration.** It slightl increases the **blood-pressure.** It has no action on the respir

n. It is **excreted** in the urine. It sometimes, though rarely, ses vomiting, and very seldom causes collapse.

USES.—In febrile diseases generally. It seems specially ful in typhoid fever and phthisis, but is also useful in erylas, surgical fever, pleurisy, and pneumonia.

Thallin. Not officinal. A synthetically prepared alkaloid. is chemically tetrahydro-paramethyl-oxy-chinolin.

CHARACTERS.—A colourless powder, with a taste and smell minding one of meadow-sweet.

SOLUBILITY and REACTION.—It is soluble in water and gives an emerald en colour with perchloride of iron, whence its name.

DOSE.—5 grains or more.

ACTION.—It is a powerful **antipyretic** (p. 419), but does not pear to be quite so good as antipyrin.

Antifebrin. PHENYLACETAMIDE. $C_6H_5.C_2H_3O.NH$. Not offiial.

CHARACTERS.—A pure white crystalline powder; odourless, l producing a slight burning sensation on the tongue; neutral reaction. It melts at 113° C. and distils at 292° C.

PREPARATION.—By the action of glacial acetic acid upon anilin.

SOLUBILITY.—It is soluble in 189 parts of water at 6° C., more soluble in ing water, freely soluble in alcohol, in wine, and in ether.

DOSE.—$\frac{1}{4}$–1 gm., not exceeding 2 gms. in the twenty-four hours.

ACTION AND USES.—Antifebrin seems not to be poisonous dogs and guinea-pigs when given in relatively large doses. It s been introduced as an **antipyretic** in man, and has been en in typhoid fever, erysipelas,[1] rheumatic fever, and other rile conditions. It reduces the temperature rapidly, the effect ting from three to seven hours, according to the size of the se; the pulse is slowed, and the patient often falls into a iet sleep.[2] No vomiting or diarrhœa has been noticed, but ere is some tendency to collapse. A quarter of a gramme of tifebrin is said to have the same effect as one gramme of ipyrin.

Saccharine. BENZOYL-SULPHONIC-IMIDE. $C_6H_4(CO)(SO_2)NH$. t officinal.

CHARACTERS.—A white amorphous powder, crystallisable from t aqueous solutions, with a very sweet taste and faint flavour bitter almonds. It melts at 200° C., with partial decomsition.

SOLUBILITY.—With difficulty soluble in cold, more soluble in hot, water. adily soluble in alcohol and ether. As sugar is not soluble in ether, this gent may be employed to separate a mixture of saccharine and sugar.

[1] In one case of erysipelas I found two doses of 7 grains each with an interval wo hours reduce the temperature below normal and cause some tendency to colse; in another case, 2 grs. every 2 hours reduced the temperature slowly and adily without collapse.

[2] Cahn and Hepp, *Central. f. klin. Med.*, Aug. 14, 1886.

PREPARATION.—Acting on toluene, $C_6H_5CH_3$, by sulphuric acid at 100° C by which toluene sulphonic acids (ortho and para) are formed; the sodium salts of these are next prepared and converted into sulphonic chlorides. Th ortho-chloride is changed into the amide by ammonium carbonate and th amide oxidised, and then treated with a dilute mineral acid; saccharine precipitated.[1]

ACTION AND USES.—Saccharine is **antiseptic**. It is said t be quite innocuous to dogs, even in large doses, but it is no a food, like sugar. From its sweet taste, 220 times stronge than that of sugar, it may prove a useful substitute for sugar i cases of diabetes. It has no injurious action in man, nor, lik salicylate of sodium, has it any curative action in diabetes.

---

[1] For full details of this process, see Roscoe, 'Recent Progress in Coal-ta Industry,' *Roy. Inst. Proc.*, 1886.

SECTION V.

VEGETABLE MATERIA MEDICA.

VEGETABLE KINGDOM.

INTRODUCTION.

HOUGH it is probable that, at some future time, we may be to make artificially drugs which will be able to produce on organism any effect which we desire, yet many years must se before this can be done, and in the meantime we may ibly find our purpose served, at least to a certain extent, by use of new remedies of vegetable origin. In our search for remedies we may be aided by the knowledge that plants ch resemble each other in some of their botanical characters, le differing in others, frequently contain principles which t upon the body actions similar in their general features, but ring in details.

Thus, we find that various species of the genus *Rhamnus* con- principles which have a general similarity in action, but at same time present such differences that the action of one ies may be uncertain and painful, while that of another is ain and free from discomfort.

In plants which are so much less closely connected as no ger to belong to the same genus, but yet belong to the same ural order, we find differences varying considerably in amount. example, we sometimes find the action of different genera ne natural order, e.g. *Gentianaceæ*, is as much alike as the on of different species in a genus belonging to another order. other times we find, as in the *Cucurbitaceæ* and *Atropeæ*, plants belonging to all the genera in an order have a ten- cy to produce somewhat similar actions, but these actions y very considerably in regard both to their intensity and lity. In other cases we find plants which are so closely d as to belong to the same genus contain active principles ch have apparently an entirely opposite action. Thus one ies of strychnos will yield strychnine, which causes death by vulsions, while another will yield curara, which kills by para- ng the motor nerves.

But more than this, we find that principles having a very rent, or even an antagonistic, action are frequently contained he same plant; thus from the poppy and from Indian hemp an obtain morphine and cannabin, which are almost pure cotics, and thebaine and tetanocannabin, which are almost e convulsants. From Calabar bean we obtain physostig- e, which paralyses the spinal cord, and calabarine, which nulates it so as to produce convulsions. From jaborandi we

get pilocarpine, which stimulates the ends of secreting nerv and jaborine, which paralyses them.

It is thus evident that the action of many drugs will depe upon the proportion in which their active principles are prese in them, and it is possible that the proportions may be such th the drug may entirely fail to produce its usual action, as wou be the case, for example, if the proportion of jaborine in jal randi leaves should be sufficient to neutralise the action of t pilocarpine.

It is just possible, also, that the proportion may occasiona be such as to reverse the usual action of the drug, and the effe of a mixture of alkaloids may sometimes be considerably infl enced by the greater susceptibility of the patient to the action one or other of them.

A great deal of light has been thrown on the relationship each other of the alkaloids in individual plants or in alli species by Crum-Brown and Fraser's discovery that the additi of alcohol-radicals to alkaloids sometimes completely alters th action; so that methyl-strychnine, e.g., has an action like curar

It is probable that the active principles in plants are form by the decomposition of the albuminous matter in their tissu (p. 99), and that the quantity, the quality, and the proportion different principles present in the plant may vary with the peri of growth, and with the conditions under which the plant grown. Thus hyoscyamus is comparatively inert in the first ye of its growth, but it becomes active in the second year; and t common hemp has little or no narcotic power when grown moderate temperatures, but acquires it when cultivated in warm climate, as that of India or the Southern States of Americ

It is not at all improbable that the active principles of pla may vary even with the time of day, for Sachs has found that great variation certainly takes place in the amount of star present in leaves, so much so, indeed, that leaves gathered evening contain starch in considerable quantities, while it m be almost absent from others gathered before sunrise. T old herbalists were very particular regarding the times at whi plants were to be gathered, and it is quite probable that by mo attention to such minutiæ, we might obtain remedies mo certain in their effect.

At the same time, by investigating the physiological acti of various plants, we may possibly be able to obtain a series which the actions vary regularly from one another, so that can select the one which will best suit our purpose.

A **mere knowledge of the names** of species, genera, natural orders is **perfectly useless**, for the names are liable to changed at the will of botanists, but a knowledge of the botani relationships of plants may be a useful indication in our sear after new remedies.

CHAPTER XXXI.

PHANEROGAMÆ.

Division I.—ANGIOSPERMÆ.

Class I.—DICOTYLEDONES POLYPETALÆ.

Sub-Class I.—THALAMIFLORÆ.

RANUNCULACEÆ.

B.P. Aconiti Folia. Aconite Leaves.—The fresh leaves and flowering tops of *Aconitum Napellus*, gathered when about one-third of the flowers are expanded, from plants cultivated in Britain.

Characters.—Leaves have deeply-cut, wedge-shaped segments, by which even a fragment of the leaf can be recognised; exciting slowly, when chewed, a sensation of tingling. Flowers deep-blue, helmet-shaped.

Officinal Preparation.

B.P.	Dose.
Extractum Aconiti (green extract)	1–2 gr.

B.P. Aconiti Radix. Aconite Root.—The dried root of *Aconitum Napellus*, collected in winter or early spring before the leaves have appeared. From Britain or Germany.

U.S.P. Aconitum. The tuberous root of *Aconitum Napellus*.

Characters.—Conical and tapering, usually from one to three inches long, not thicker than the finger at the crown, blackish-brown, internally whitish. A minute portion, cautiously chewed, causes prolonged tingling and numbness.



Fig. 176. Aconite, half the natural size.

Properties and Composition.—The chief active principle in both leaves and roots is an alkaloid **aconitine** or aconitia, which is combined with aconitic acid. It is only present in small quantity in the leaves. In the root resinous and fatty matters and several other active principles are also present. Nepal aconite, or Bikh, the root of *A. ferox*, contains an alkaloid, pseudaconitine, which is much more active than aconitine. Japanese aconite is said to contain an alkaloid which is much more powerful even than pseudaconitine. It is therefore very important that officinal preparations should be made only from the root of *A. Napellus*.

OFFICINAL PREPARATIONS.

B.P.	DOSE.
Tinctura Aconiti	1–15 minims.
Linimentum Aconiti (p. 516)	

U.S.P.

Abstractum Aconiti	$\frac{1}{3}$–1 gr. (·03–·36 gm.)
Extractum Aconiti	$\frac{1}{6}$–$\frac{1}{3}$ gr. (·01–·02 gm.)
Extractum Aconiti fluidum	$\frac{1}{2}$–2 min. (·03–·12 c.c.)

U.S.P. Abstractum Aconiti.—Exhaust powdered aconite, 200 parts, with alc hol containing 2 parts of tartaric acid. Retain the first 170 parts of the percolat evaporate the remainder to 30, at a temperature not exceeding 50° C. (122° F.), a mix with the reserve portion. Place the mixture in an evaporating dish, and havi added 50 parts of sugar of milk, cover it with a piece of thin muslin gauze and s aside in a warm place, where the temperature will not rise above 50° C. (122° F until the mixture is dry. Lastly, having added enough sugar of milk to make t mixture weigh 100 parts, reduce it to a fine uniform powder.

B.P. Aconitina. ACONITINE.—A white, usually amorphou solid alkaloid.

When rubbed on the skin it causes a tingling sensatio followed by prolonged numbness. It is a very active poison.

PREPARATION.—The aconitate of aconitine is dissolved out of the pounde root by macerating in spirit. If ammonia were now added, the aconiti would be set free, but being soluble in spirit would not be precipitated. Th spirit is therefore recovered by distillation, and the residual extract dissolve in water, in which the aconitate of aconitine is soluble, although the alkalo is very sparingly so. By adding ammonia, aconitine is precipitated mixe with colouring matter and other principles. It is then dissolved in ethe which leaves the colouring matter behind. The ether is recovered by di tillation, and the aconitine further purified by dissolving in water acidulate with sulphuric acid and reprecipitating by ammonia.

CHARACTERS AND REACTIONS.—A white, usually amorphous, solid; strong alkaline to reddened litmus, neutralising acids, and precipitated from the by the caustic alkalis, but not by carbonate of ammonium or the bicarbonat of sodium or potassium. It melts with heat, and burns with a smoky flam leaving no residue when burned with free access of air.

SOLUBILITY.—Soluble in 150 parts of cold and 50 of hot water, and muc more soluble in alcohol, ether, and chloroform.

OFFICINAL PREPARATIONS.

B.P. Unguentum Aconitinæ.—Aconitine, 8 gr., dissolved in rectified spir $\frac{1}{2}$ fl. dr., and mixed with prepared lard, 1 oz. For external application only.

PHYSIOLOGICAL ACTION.—**General Action.**—The action aconite is exerted most markedly on the peripheral ends of sen sory nerves, on the heart, and on the respiration.

In **frogs** it produces steady loss of motion, both voluntar and reflex, with gradually increasing weakness of respiratio and of the heart, which finally stops in diastole, usually abou the same time as the respiration.

In **man** one of the most marked symptoms is the loc **tingling** and numbness produced in the mouth by aconite aconitine if they come into actual contact with it. This irrit tion is not limited to the mouth, but occurs also in the gulle and stomach, where it produces belching, nausea, and vomiting

aconite preparations, or aconitine, are taken in capsules so at they do not touch the mouth or tongue, this local tingling d numbness are hardly felt at all.

After absorption, however, the poison is carried by the cir- lation throughout the body, and then causes a tingling in all rts of the body in the order of their sensitiveness as de- mined by Weber. The most sensitive parts are affected first, z. the tongue and lips, the finger-tips, face, perineum, breast, lly, and last the back.

The **heart** is quickly affected even by very small doses, and single drop of the tincture (B.P.) given in water twice or thrice intervals of a quarter of an hour will in many cases greatly luce the rate of the pulse. This slowness of the pulse is due an action of the aconite upon the vagus-roots, and does not cur after the administration of atropine. In some cases of sease also the pulse seems little affected by aconite. In larger ses the vaso-motor centre becomes gradually paralysed, while e heart remains slow, the blood-pressure falls greatly, and the lse is not only slow but exceedingly weak and irregular.

Great muscular weakness and **dyspnœa** occur, the respira- ns being slow, shallow, and feeble. The dyspnœa, and pro- bly the weakness also, depend to a considerable extent upon e feebleness of the circulation and consequent imperfect trition of the nerve-centres, for the administration of atropine sens the dyspnœa.

In addition to this, however, there must be a direct paralys- ; action on the respiratory centre, and **death** usually occurs m stoppage of the respiration.

When the heart is examined immediately after death, it is nerally found to be still pulsating, although sometimes it is nd to have stopped and even lost its irritability. In the latter ge of aconite poisoning the effects of imperfect respiration y become manifest in the livid colour and anxious appearance he face, the cold sweat on the skin, and sometimes protrusion he eyes with dilatation of the pupil.

Death is sometimes preceded by convulsions, which do not pear to be entirely due to asphyxia.

Action on Individual Organs.—The **muscles** are little if at affected by aconite. The terminations of the **motor nerves** pear to be first irritated, so that fibrillary twitchings of the scles occur in a frog; afterwards they are paralysed. The ipheral ends of **sensory nerves** in the skin and mucous mbranes are first irritated, so that the peculiar tingling and nbness is felt, and sometimes also intense neuralgia, affecting nches of the fifth nerve; afterwards they are paralysed. The tor centres of the **spinal cord**, and the respiratory and vaso- tor centres in the **medulla**, appear to be first slightly stimu- d, so that clonic convulsions may occur. The reflex power of

the cord is diminished, the sensory ganglia being affected befc the motor ganglia. The paralysis of the cord is probably tc great extent, however, due to its imperfect nutrition from failu of circulation. The **brain** remains unaffected, the mental fac ties being usually clear up till death. Sometimes drowsine occurs, which may, however, be due to the circulation; a headache is also observed, which seems to involve the interior the head, and is distinct from the facial neuralgia observed earlier stages of the poisoning. Like the motor centres in t cord, the **vaso-motor** centre in the medulla oblongata appea to be first stimulated and then paralysed, so that the bloc pressure rises at first in rabbits, though it falls in dogs and ca apparently from the slowing of the pulse produced by stimu tion of the vagus-roots (p. 288). Later on, the vaso-mot centre becomes paralysed to a considerable extent, though r entirely, so that the blood-pressure falls greatly. Although r completely paralysed, it becomes insensible to reflex stimulatic so that irritation of a sensory nerve will no longer raise t blood-pressure.

The **heart** in the frog is first quickened and then slowed. man or mammals there is first slowness of the pulse, but shor before death it may become more rapid. This effect appears depend chiefly upon primary stimulation succeeded by paraly of the motor ganglia in the heart, the effect in mammals bei altered by the simultaneous action of the drug upon the vag roots in the medulla.

The **respiration** is at first slow and deep with marked piratory effort; afterwards slow, shallow, and laboured.

This effect appears to be due to the direct action of the pois on the respiratory centre, together with its indirect action throu weakening of the circulation (pp. 238 and 239). Before dea convulsions occasionally occur, and these are, to a great exte due to the indirect effect of the drug through the circulation, l possibly also to a direct irritating effect on a convulsive cen in the medulla.

The **temperature** falls constantly throughout. The **stoma** is irritated immediately by the poison taken directly into it, that violent vomiting may occur; but it may also be irritated the poison being eliminated by the gastric mucous membra after injection subcutaneously or into the blood, so that t effects are similar to those produced by the direct introducti of the drug into the stomach (p. 39). The **secretion** of salivary glands is increased, and usually the sweat also, possi other secretions. The intestines are irritated like the stoma and diarrhœa occurs in consequence.

The **pupil** at the commencement of poisoning alternat contracts and dilates, the tendency to contraction being m marked; and a similar result occurs from the local applicat

aconitine to the eye. Later on there is extreme dilatation. his dilatation may be due to reflex irritation from the gastro-testinal mucous membrane (p. 218). Aconite quickly passes om the blood into the tissues, for if the greater part of the blood of poisoned dog is transfused into the veins of a healthy one within few minutes after poisoning has begun, it produces no effect.

THERAPEUTIC USES OF ACONITE.—Aconitine is applied **locally** the form of ointment in cases of severe neuralgia, a small ece about the size of a pea being rubbed into the painful part. the neuralgia affects the temple, great care must be taken that e ointment does not get into the eye, as rapid absorption curs from the conjunctiva, and general poisoning may result.

Aconite liniment is frequently employed in muscular rheu-atism; in various forms of neuralgia, such as sciatica; and er swollen and painful joints. Admixture with chloroform cilitates the absorption of alkaloids through the skin, so that mixture of aconite liniment with chloroform liniment may be ore efficacious than either the one or the other separately; but e mixture should be employed with care, and not over too large surface, to prevent any risk of too rapid absorption.

As a local sedative to the **stomach** it has been employed in ll doses to check the vomiting of pregnancy. Its chief use, owever, is in the **febrile condition** depending upon local in-mmations, such as tonsillitis, sore-throat, pleurisy, pneumonia, thisis, peritonitis, pericarditis, acute rheumatism, gout, ery-pelas, otitis, gonorrhœa, and in urethral fever. In many of ose conditions small doses of aconite slow the pulse, lower the mperature, and give much relief to the patient. In **cardiac sease** its action is somewhat uncertain. In nervous palpita-on it is sometimes useful, and it may give relief in palpitation pending upon hypertrophy, but frequently it is of no use in is condition. In diseases of the **nervous system** its internal plication alone, or combined with its external use, sometimes ves relief in headache, toothache, noises in the ear, neuralgia, pecially in the face, in intercostal neuralgia, and neuralgia ac-mpanying herpes zoster. It has been found useful, also, in me cases of amenorrhœa depending on a sudden check to the enstrual flow, and also in severe menorrhagia.

MODE OF APPLICATION.—Externally it may be applied in the rm of ointment or liniment, internally in the form of tincture extract. The extract is uncertain in its strength, and death has curred from the two grains laid down as a maximum dose by e British Pharmacopœia. The tincture should also be adminis-red in very small doses, as it is difficult to counteract its effect hen too much has been given. Instead of giving a large dose, erefore, all at once, it is much better to give it in divided ses, such as one drop in a little water, every quarter or half hour until the pulse has begun to be affected, and then every

hour or two afterwards, according to the necessities of the cas so as to maintain the action (Ringer).

Staphisagriæ Semina, B.P.; Staphisagria, U.S. STAVESACRE SEEDS, B.P. STAPHISAGRIA. STAVESACRE, U.S. —The seeds dried ripe of *Delphinium staphisagria*.

CHARACTERS.—Irregularly triangular or obscurely quadrangular, arche blackish-brown when fresh, but becoming dull greyish-brown by keepin Testa wrinkled and deeply pitted; nucleus soft, whitish, oily. No mark odour; taste nauseously bitter and acrid.

COMPOSITION.—They contain several alkaloids, the most in portant being **delphinine** and **staphisagrine**.

B.P. PREPARATION.

Unguentum Staphisagriæ. (Crushed seeds, 1; macerated in benzoat lard, 2, for two hours, and strained.)

ACTION.—**Staphisagrine** paralyses the **motor nerves** i frogs, like curare, and kills mammals without convulsions b paralysing the respiration. **Delphinine** resembles aconitine i many respects, and like it causes slowness of the **pulse** and r **spiration**, paralysis of the **spinal cord**, and **death** by asphyxi It stimulates the vagus centre in the **medulla**, and also th accelerating centre for the heart (p. 318). It slows the respir tion, apparently by an action on the slowing fibres of the **vagu** for when the vagi are cut, it quickens respiration, probably b stimulating the respiratory centre in the medulla. In advance stages of poisoning it paralyses the ends of the vagus in th **heart** and also the cardiac muscle. It removes the still-star caused by muscarine and digitalin (Boehm). By depressing th action of the spinal cord it arrests the convulsions caused b strychnine.

USES.—Stavesacre ointment is used to destroy pediculi.

U.S.P. Pulsatilla. PULSATILLA.—The herb of *Anemo pulsatilla* and *Anemone pratensis*, and of *Anemone patens*, va *Nuttalliana*, collected soon after flowering.

It should be carefully preserved and not be kept longer tha one year.

CHARACTERS. — Leaves radical, petiolate, silky-villous, twice or thri deeply three-parted or pinnately cleft, with linear, acute lobes, appearing aft the large, purple (or, in the last-named species, sometimes whitish) flower inodorous, very acrid.

DOSE.—1½–6 grains.

COMPOSITION.—The fresh plant yields by distillation wit water, an acrid, **oily principle**, with a burning, peppery tast A similar oil is got from *Ranunculus bulbosus*, *R. flammula*, ar *R. sceleratus*. Its therapeutic value is not great. When ke for some time, this oily substance becomes decomposed in anemonic acid and anemonin.

ACTION.—The **oil** acts as a vesicant when applied to the ski **Anemonic acid** appears to be inert. **Anemonin** sometim

uses local inflammation and gangrene when subcutaneously jected; vomiting and purging when given internally. It is certain whether these symptoms are due to anemonin itself or some impurity in it. The chief action of pure anemonin is a pressant one on the **circulation, respiration,** and **spinal cord,** a certain extent resembling that of aconite. The symptoms e slow and feeble **pulse,** slow respiration, coldness, **paralysis** fecting first the hind and then the fore-legs, **dyspnœa,** and **ath** without convulsions. In poisoning by extract of pulsatilla nvulsions are always present. Their absence in poisoning by emonin appears to be due to its paralysing action on motor ntres in the brain (p. 184); it does not paralyse the muscles d motor nerves in frogs.

USES.—It is supposed to be **diaphoretic** and **emmenagogue.** has been used in amenorrhœa, dysmenorrhœa, catarrh of rious mucous membranes, bronchitis, and asthma.

Adonis Vernalis. Not officinal.—This plant is considered some to be a species of Anemone.

COMPOSITION.—It contains a glucoside **adonidin.**

ACTION.—Adonidin has an action almost exactly like that of italin, but is much stronger, and is said not to be cumulative. appears to be about ten times as powerful as digitoxin.

USE.—It may be used instead of digitalis, and sometimes ceeds when digitalis fails. It is, however, less certainly bene- al in valvular disease than digitalis, and should be used only en digitalis fails (Nothnagel). It appears to produce vomiting l diarrhœa more readily than digitalis (Bubnoff).

ADMINISTRATION.—It may be given in the form of infusion 2 dr. of the root to 6 fl. oz. of water) in doses of ½ fl. oz. every to four hours.

Cimicifugæ Rhizoma, B.P.; Cimicifuga, U.S.P. CIMI- UGA. BLACK SNAKEROOT.—The dried rhizome and rootlets of *micifuga racemosa.* Synonym: *Actæa racemosa.*

CHARACTERS.—The rhizome is hard, 2–6 inches long, about ½ to 1 inch k, somewhat flattened-cylindrical in form, having on its upper surface remains of several aërial stems, and below numerous small wiry brittle nched rootlets, which in commercial specimens are more or less broken Both rhizome and rootlets are brownish-black, almost odourless, and of itter, slightly acrid, taste. Their fracture is close, that of the rootlets pre- ting a thick bark, and a central axis with from three to five, usually four, verging woody wedges, so as to assume a triangular, cross-like, or stellate earance. An infusion is blackened by a persalt of iron.

COMPOSITION.—It contains, when fresh, a **volatile oil,** a **resin,** l a **bitter** neutral **substance,** but it is not known to which of se its activity is due.

B. AND U.S.P. OFFICINAL PREPARATIONS.	DOSE.
Extractum Cimicifugæ Liquidum, B.P. (Fluidum, U.S.P.) ...	3–30 min.
Tinctura Cimicifugæ	15–60 min.

ACTION.—In large doses this drug produces nausea, vomiting,

depression, headache, and giddiness. Its action on the heart is said to be like that of digitalis, but is less powerful.

USES.—It is used as a **stomachic** and **cardiac tonic** in various conditions of weakened heart. It has been used in chore rheumatic affections, headache, and neuralgia, and is useful as an **expectorant** in bronchitis or acute catarrh, and in phthis Under the name of *Actæa racemosa* it obtained a great reputati as a cure for acute rheumatism, but this was not confirmed on more extensive trial.

Podophylli Rhizoma, B.P.; Podophyllum, U.S.P. POD PHYLLUM ROOT.—The dried rhizome and rootlets of *Podophyll peltatum*, North America.



FIG. 177.—Podophyllum, half the natural size.

CHARACTERS.—In pieces of variable length, about $\frac{1}{5}$ of an inch thick, da reddish-brown externally, whitish within, breaking with a short fracture. intervals of about two inches the rhizome is thickened, and from ea swollen part or joint a number of pale brown rootlets spring. These brittle, and many of them break short off close to the rhizome, leaving lit round white spots which help to distinguish podophyllum easily from oth roots. Powder yellowish-grey, sweetish in odour, bitterish, subacrid a nauseous in taste.

COMPOSITION.—Its most important constituents are **poo phyllin**, which is a resinous substance, and **berberine**, whi is a yellow alkaloid (p. 839).

OFFICINAL PREPARATIONS OF PODOPHYLLUM.

B.P.	DOSE.
Podophylli Resina	$\frac{1}{8}$–1 gr.
U.S.P.	**DOSE.**
Resina Podophylli	$\frac{1}{8}$–$\frac{1}{2}$ gr. (0·008–0·03 gm.)
Abstractum „	5–10 gr. (0·33–0·67 gm.)
Extractum „	1–3 gr. (0·06–0·2 gm.)
„ „ Fluidum	5–15 min. (0·3–0·9 c.c.)

Podophylli Resina, B.P.; Resina Podophylli, U.S. RESIN OF PODOPHYLLUM. *Synonym*: Podophyllin.

PREPARATION.—The resin is dissolved out of the powdered root by hausting with spirit, the greater part of which is recovered by distillati and the remainder holding the resin in solution is poured into water sligh acidulated with hydrochloric acid, when the resin is precipitated as a powder, as it is insoluble in water. The resin itself consists to a great ext of a fatty and resinous acid, and subsides more quickly in acidulated thar pure water. It is afterwards washed and dried.

CHARACTERS AND SOLUBILITY.—A pale greenish-brown amorphous pow soluble in rectified spirit and in ammonia; precipitated from the for solution by water, from the latter by acids. Almost entirely soluble in ether.

COMPOSITION.—It consists chiefly of a fatty and resinous a having little physiological action, and two active substanc

odophyllotoxin and **picropodophyllin**, the former being much e more powerful.

DOSE.—$\frac{1}{8}$ to $\frac{1}{2}$ grain.

B.P. PREPARATION.

	DOSE.
Tinctura Podophylli (1 gr. of resin in 1 fl. dr.)	15 min. to 1 fl. dr.

PHYSIOLOGICAL ACTION.—The resin is the part chiefly em-oyed. It acts as a drastic **purgative**, increasing the secretions the intestinal mucous membrane, and of the liver (p. 403). acts on the bowels, when injected subcutaneously as well as nen introduced into the intestinal canal. Like many other epatic stimulants, it does not increase the secretion of bile so uch when it acts as a purgative (p. 403).

USES.—It is used in cases of biliousness associated with dark ools (Ringer). When the stools are pale, mercurial pill is ually employed. It is often employed in combination with her purgatives, such as colocynth, aloes, or rhubarb. It is eful in congestion of the liver, and of the portal circulation, in ue with congested liver, and in sick headache with biliousness. s action is uncertain and it frequently causes griping.

Externally it acts as an irritant; if incautiously handled, it ten produces conjunctivitis.

U.S.P. Hydrastis. HYDRASTIS. GOLDEN SEAL.—The rhi-me and rootlets of *Hydrastis canadensis*.

CHARACTERS.—Rhizome about 1½ inch long and ¼ inch thick; oblique, th short branches, somewhat annulate and longitudinally wrinkled; ex-rnally yellowish-grey; fracture short, waxy, bright reddish-yellow, with a ickish bark, about ten narrow wood-wedges, broad medullary rays and ge pith. Rootlets thin, brittle, with a thick, yellow bark, and subquadran-lar, woody centre. Odour slight; taste bitter.

COMPOSITION.—It contains the yellow, bitter alkaloid **ber-erine** (p. 838), and the colourless, also bitter, hydrastia, or **ydrastine**, besides a third alkaloid and a volatile principle not et isolated.

U.S.P. PREPARATIONS.

	DOSE.
Extractum Hydrastis Fluidum	1–2 fl. dr.
Tinctura Hydrastis	2–5 fl. dr.

USES.—Its uses are similar to those of the simple **bitters** p. 364). Professor Rutherford found the resinous substance ob-ained from the root to be an **hepatic stimulant** of moderate power p. 403). This substance, which is also called hydrastin, must ot be confounded with the alkaloid. It consists of a mixture f hydrastine, berberine, and resin in varying proportions. The ure alkaloid hydrastine is said to be **antiperiodic**, and causes nging in the ears like quinine. The mixture of the alkaloids cts as an **emmenagogue** (*vide* p. 453).

MAGNOLIACEÆ.

B.P. Anisi Stellati Fructus; U.S.P. Illicium. STAR-ANI FRUIT.—The dried fruit of *Illicium anisatum*. China.

CHARACTERS.—The fruit consists of 8 brown, boat-shaped carpels, join at their inner ends so as to form a star. Each contains one seed with oily taste. The taste of the fruit is sweet and aromatic.

COMPOSITION.—It contains a volatile oil which so close resembles that of true anise as to be officinal.

Oleum Anisi, B.P. and U.S.P.—A volatile oil distilled Europe from anise fruit; or in China from star-anise fruit. F Preparations and Action *vide* Anise (p. 935).

MENISPERMACEÆ.

U.S.P. Menispermum. MENISPERMUM. CANADIAN MOONSEE —The rhizome and rootlets of *Menispermum canadense*.

CHARACTERS.—Rhizome several feet long, about a quarter of an in (6 millimetres) thick, yellowish-brown or brown, finely wrinkled longitudina and beset with numerous thin, rather brittle rootlets; fracture tough, wood internally yellowish, with a thickish bark, a circle of porous, short, nea square wood-wedges, and a large central pith; nearly inodorous; taste bitt

DOSE.—5–20 gr. in infusion.

COMPOSITION.—It contains a small quantity of **berberine** a a colourless alkaloid.

USES.—It acts as a **bitter tonic**, and is sometimes used al as a substitute for sarsaparilla.

Calumbæ Radix, B.P.; Calumba, U.S.P. CALUMBA ROO —The root, cut transversely and dried, of *Jateorrhiza Calum*




FIG. 178.—Calumba, half the natural size.

(*Cocculus palmatus, DC.*) From the forests of Eastern Afric between Ibo and Zambezi.

CHARACTERS.—Slices flat, circular, or oval, about 2 inches in diamet from $\frac{1}{6}$ to $\frac{1}{3}$ of an inch thick, softer and thinner towards the centre, so as present the appearance of bi-concave discs, greyish-yellow, bitter.

COMPOSITION.—It contains a neutral principle, **calumbin**, yellow alkaloid **berberine**, to which it owes its colour, a **calumbic acid**. All these are bitter. It contains much **starc** which is dissolved by hot water, so that a decoction is blacken

iodine. The infusion is consequently made with cold water leave the starch behind, as it renders the infusion liable to decompose, especially in hot weather. It contains no tannin, and e infusion can therefore be prescribed along with salts of iron.

PREPARATIONS.

B.P.	DOSE.
Extractum Calumbæ	2–10 gr. or more.
Infusum Calumbæ (1 oz. to 1 pint)	1–2 fl. oz.
Tinctura Calumbæ	½–2 fl. dr.

Also contained in Mistura Ferri Aromatica.

U.S.P.	
Extractum Calumbæ Fluidum	15–30 min. (0·9–1·9 c.c.)
Tinctura Calumbæ	1–4 fl. dr. (3·75–15 c.c.)

ACTION.—**Calumba** is a pure bitter stomachic tonic.

Neither the berberine nor calumbin which it contains has any werful physiological action. **Berberine** in doses of 1½ grain ven subcutaneously kills rabbits, with symptoms of prostration d fall of temperature; but a dose eight times as great given them by the mouth has no action, and 15 grains only produce man slight colicky pains and diarrhœa. It is said to cause ntraction of the intestines and of the spleen, and to lessen oxiion in the blood. **Calumbin** seems to have still less action. small doses it seems, like other bitters, to raise the bloodessure slightly, and in large doses to lower it.

USES.—Calumba is used as a **bitter tonic** in atonic dyspepsia d debility of the digestive organs. It is said to have a soothg effect, and is therefore given in irritable conditions of the mach. It is frequently employed in combination with iron, iefly in the form of infusion; the advantage it possesses over her bitter infusions, except quassia, for this purpose, being at it contains **no tannin**, and consequently does not form an ky-looking mixture. It may be used as a general tonic during nvalescence from various acute diseases, and may be prescribed combination with either acids or alkalis.

Pareiræ Radix, B.P.; Pareira, U.S.P. PAREIRA ROOT.—e dried root of *Chondrodendron tomentosum*, Brazil.

CHARACTERS.—Generally seen in more or less cylindrical pieces, about nch to 2 inches in diameter and 4 inches or more in length. The bark is yish-brown, and the wood greyish-yellow. It is recognised by the wellrked rings and medullary rays on the wood. The rings are irregularly ncentric.

COMPOSITION.—It contains an alkaloid **pelosine** or **buxine**, ich appears to be identical with beberine.

PREPARATIONS.

B.P.			DOSE.
Decoctum Pareiræ		1½ ounce to pint	1½–2 fl. oz.
Extractum	„		10–20 gr.
„	„	**Liquidum** 1 oz. to 1 fl. oz.	½–2 fl. dr.

U.S.P.	
Extractum Pareiræ Fluidum	1–2 fl. dr. (3·75–7·50 c.c.)

PHYSIOLOGICAL ACTION AND USES.—Pareira is a bitter toni but is chiefly employed as a **stimulant** to the mucous membra of the genito-urinary tract, in chronic catarrh of the **bladde** It is usually given in the form of decoction or liquid extra frequently combined with an acid or an alkali, according to t condition of the urine.

U.S.P. Picrotoxinum. PICROTOXIN. $C_9H_{10}O_4$; 182.— neutral principle prepared from the seeds of *Anamirta paniculat*

CHARACTERS.—Colourless, flexible, shining, prismatic crystals, permane in the air, odourless, having a very bitter taste, and a neutral reaction.

SOLUBILITY.—It is soluble in 50 parts of boiling water, and in 150 water at 14° C.; soluble in alkalis and in alcohol.

REACTIONS.—When heated to about 200° C. (392° F.), the crystals me forming a yellow liquid; when heated on platinum foil, they char and finally completely dissipated. Concentrated sulphuric acid dissolves picroto with a golden-yellow colour, which turns violet-red on the addition of a tr of bichromate of potassium. When mixed with three times its weight nitrate of potassium, moistened with sulphuric acid, and then treated w strong solution of soda in excess, picrotoxin assumes a brick-red colour short duration. The aqueous solution should remain unaffected by solutio of salts of mercury or platinum, tannic acid, iodide of mercury and potassiu or other reagents for alkaloids (absence of, and difference from, alkaloids).

DOSE.— $\frac{1}{120}$ to $\frac{1}{60}$ gr. in pill, or in the acetic solution scribed under Uses.

ACTION.—It stimulates all the motor and inhibitory cent in the **medulla,** especially the respiratory and vagus centres. also irritates **motor centres,** either in the cerebrum or in medulla and **cord,** producing in all vertebrates alternating e leptiform spasms, with periodic stoppage of the motions of diaphragm and slowness of the pulse. The spasms often t the form of swimming, running backwards or round in a ci (*manège* movements), or rolling of the body on its axis (pp. and 215). The **temperature** is somewhat raised.

USES.—It is employed as an ointment (10 gr. to 1 oz. of la in tinea capitis, and to destroy pediculi. It should be used w care, as its application to the head has been followed by conv sions and death. It has been used, though unsuccessfully epilepsy in doses of $\frac{1}{25}$-grain hypodermically, and has been fo useful in the night sweats of phthisis (p. 443), in doses of $\frac{1}{12}$ $\frac{1}{60}$ grain in pill, or 2 to 4 minims of a solution containing 8 gr of picrotoxin, 4 fluid drachms of glacial acetic acid, and water to 4 ounces.

BERBERIDACEÆ.

U.S.P. Caulophyllum. CAULOPHYLLUM. BLUE COHOS The rhizome and rootlets of *Caulophyllum thalictroides.*

CHARACTERS.—Rhizome about four inches (10 centimetres) long, about one-fourth to two-fifths of an inch (6 to 10 millimetres) thick, b on the upper side, with broad, concave stem-scars and short, knotty branc externally grey-brown, internally whitish, tough and woody. Roo

merous, matted, about four inches (10 centimetres) long, and one twenty-h of an inch (1 millimetre) thick, rather tough; nearly inodorous; taste etish, slightly bitter, and somewhat acrid.

DOSE.—1–5 gr. in infusion.

COMPOSITION.—It contains the glucoside **saponin** (p. 918) and sins.

USES.—It has little medicinal virtue, though it has been re-mmended as a **diuretic, antispasmodic,** and **emmenagogue.**

PAPAVERACEÆ.

B.P. Papaveris Capsulæ. POPPY CAPSULES.—The nearly e dried capsules of the white poppy, *Papaver somniferum.* ltivated in Britain.




FIG. 179.—Poppy capsule, half the natural size.

CHARACTERS.—Globular, two or three inches in diameter, crowned by a sile stellate stigma, which distinguishes them from colocynth and bael its.

PREPARATIONS.

B.P.	DOSE.
Decoctum Papaveris (2 oz. boiled for ten minutes in 1½ pint of water, strained, and made up to 1 pint)	For fomentations.
Extractum Papaveris	2–5 gr.
Syrupus Papaveris	1 fl. dr.–½ fl. oz.

COMPOSITION.—The capsules contain a small amount of **mor-ine** (more being found when they are unripe than when ripe), gether with **meconic acid,** and very minute quantities of **paverine** and **papaverosine.** The seeds are devoid of these inciples, but contain much bland oil.

ACTION AND USES.—Poppy capsules act in a similar manner opium, but are much weaker, and not so certain in their action. ey are employed in the form of syrup of poppies, and given iefly to children as an opiate. Considering the uncertainty of action, and in view of the fact that children are very readily fected by any preparation of opium, the drug should be used th caution. Externally the decoction is used for sedative mentations to **allay pain.**

Opium, B. and U.S.P. OPIUM.—The inspissated juice ob tained from the poppy, *Papaver somniferum*. Grown in Asia Mino

PREPARATION.—The unripe capsules are incised, or rather deeply scratche The milky juice which exudes becomes inspissated by spontaneous evapor tion, and is scraped off and made into lumps. As these ought to consist on of the tears of thickened juice from the incisions, the lumps should tear wi an irregular surface, and when drawn across a piece of paper should leave light-brown interrupted streak. Sometimes vegetable extracts are used adulterate opium, and then it has a more even fracture, and makes a mo or less even streak on a piece of paper.

CHARACTERS.—Irregular lumps, weighing from four ounces to two pound enveloped in the remains of poppy-leaves, and generally covered with th chaffy fruits of a species of rumex; when fresh, plastic, tearing with an irr gular, slightly moist, chestnut-brown surface, shining when rubbed smoot with the finger, having a peculiar odour and bitter taste.

TEST.—Opium should yield, when assayed, about 10 per cen of morphine, B.P., 9 per cent. according to the U.S.P.

PREPARATIONS.

B.P.		DOSE.
Codeina		¼–2 gr.
Confectio Opii (Pulv. Opii Co. 192 gr.; Syrup 1 oz.)	1 part in 40, nearly	5–20 gr.
Emplastrum Opii (with resin plaster)	1 part in 10	for external us
Enema Opii	½ fl. dr. tincture to 2 fl. oz. starch mucilage.	
Extractum Opii	About 1 part from 2	¼–3 gr. or mor
Extractum Opii Liquidum	22 grs. extract in 1 fl. oz. nearly	4–40 m. „ „
Injectio Morphinæ Hypodermica	1 gr. acetate of morphine in 10 m.	
Linimentum Opii (*vide* p. 516)	1 of tincture in 2.	
Morphinæ Acetas	About 1 part from 8 or 10 of opium	⅛–½ gr.
Morphinæ Acetatis Liquor	4⅓ gr. acetate in 1 fl. oz.	10–60 m.
Morphinæ Bimeconatis Liquor	5⅓ grs. bimeconate in 1 fl. oz.	5–40 m.
Morphinæ Hydrochloras	About 1 part from 8 or 10 of opium	⅛–½ gr.
Morphinæ Hydrochloratis Liquor	4½ gr. hydrochlorate in 1 fl. oz.	10–60 m.
Morphinæ Sulphas	1 part from 7½	⅛–½ gr.
Pilula Ipecacuanhæ cum Scillâ (*vide* p. 522)	1 part in 23, nearly	5–10 gr.
Pilula Plumbi cum Opio (*vide* p. 522)	1 part in 8	4–8 gr.
[1] **Pilula Saponis Composita** (*vide* p. 523)	1 part in 6, nearly	3–5 gr.
Pulvis Cretæ Aromaticus cum Opio	1 part in 40	10–60 gr.
Pulvis Ipecacuanhæ Compositus	1 part in 10	5–15 gr.
Pulvis Kino Compositus	1 part in 20	5–20 gr.
Suppositoria Plumbi Composita	1 grain in each suppository.	
Pulvis Opii Compositus	1 part in 10	2–5 gr.
Tinctura Camphoræ Composita	2 gr. to 1 fl. oz.	15 m.–1 fl. dr.
Tinctura Opii (Laudanum)	33 grains to 1 fl. oz., nearly	4–40 m. or mor

[1] Pilula Saponis Composita is purely a preparation of opium. It is sometime convenient to give opium to patients without their knowledge. If the pill wer called Pilula Opii the patients would see from the prescription what they wer taking, while they learn nothing about the nature of the medicine from the nam Pil. Saponis Co. The name of this pill was changed from Pil. Saponis Co. to Pilul Opii in the B.P. of 1864, but the inconveniences which arose from this were so grea that the name was altered again.

PREPARATIONS—*continued.* DOSE.

ctura Opii Ammoniata.....5 grains to 1 fl. oz. .....½–1 fl. dr.
ochisci Opii .....$\frac{1}{10}$th grain of extract in each.....1–4.
guentum Gallæ cum Opio.....32 grains to 1 oz. galls ointment..for external use.
num Opii .....22 gr. extract in 1 fl. oz., nearly..4–40 m. or more.

B.P. Pulvis Kino Compositus. COMPOUND POWDER OF KINO.—Kino, $3\frac{3}{4}$; um, ¼; cinnamon bark, 1.

B.P. Pulvis Opii Compositus. COMPOUND POWDER OF OPIUM.—Opium, $1\frac{1}{2}$; k pepper, 2; ginger, 5; caraway fruit, 6; tragacanth, ½.

B.P. Tinctura Camphoræ Composita. COMPOUND TINCTURE OF CAMPHOR GLISH PAREGORIC).—Opium, 40 gr.; benzoic acid, 40 gr.; camphor, 30 gr.; oil nise, ½ fl. dr.; proof spirit, 1 pint.

B.P. Tinctura Opii Ammoniata. AMMONIATED TINCTURE OF OPIUM (SCOTCH EGORIC).—Opium, in coarse powder, 100 gr.; saffron, 180 gr.; benzoic acid, gr.; oil of anise, 1 fl. dr.; strong solution of ammonia, 4 fl. oz.; rectified it, 16 fl. oz.

B.P. Vinum Opii. WINE OF OPIUM.—Extract of opium, 1 oz.; cinnamon k, 75 gr.; cloves, 75 gr.; sherry, 1 pint.

PREPARATIONS.

U.S.P. DOSE.

xtractum Opii.....½–1 gr. (0·031–0·065 gm.)
mplastrum Opii (6 parts in 100) } prepared from
rochisci Glycyrrhizæ et Opii (1/20 gr. in each lozenge)..... } Extractum Opii.

U.S.P. Opii Pulvis. POWDERED OPIUM.—Opium dried at a nperature not exceeding 85° C. (185° F.), and reduced to a derately fine powder. It ought not to contain less than 12 more than 16 per cent. of morphine.

PREPARATIONS.

U.S.P. DOSE.

Acetum Opii (Black Drop).....10–15 min. (0·60–1 c.c.)
Opium Denarcotisatum .....¼–2 gr. (0·016–0·13 gm.)
Pilulæ Opii (Opium 1 gr.; Soap, ¼ gr., vide p. 523) One pill.
Pulvis Ipecacuanhæ et Opii (1 in 10) .....5–15 gr. (0·32–1 gm.)
Tinctura Ipecacuanhæ et Opii .....4–15 min. (0·25–1 c.c.)
Tinctura Opii.....6 min.
Tinctura Opii Camphorata .....4–15 min. (0·25–1 c.c.)
Tinctura Opii Deodorata .....6 min.
Vinum Opii ....6 min. (0·37 c.c.)

U.S.P. ACETUM OPII. VINEGAR OF OPIUM.—Opium, 10; nutmeg, 3; extracted diluted acetic acid by maceration and percolation up to 80 parts of liquid; sugar, 20, is added.

U.S.P. OPIUM DENARCOTISATUM. DENARCOTISED OPIUM.—Prepared by removing otine and odorous principles by extraction with stronger ether, and adding cient sugar of milk to make up the weight to that of opium containing 14 per . of morphine.

U.S.P. TINCTURA OPII DEODORATA. DEODORISED TINCTURE OF OPIUM.—Macerate m, 10, with water, 40, evaporate down to 10, shake with ether, 20, pour off the r, and evaporate until the whole of the ether is gone. Mix with water, 50, r, adding water up to 80, then add alcohol, 20.

U.S.P. TINCTURA IPECACUANHÆ ET OPII. TINCTURE OF IPECAC AND OPIUM.—dorised tincture of opium, 100, evaporated to 85, then fluid extract of ipecac, s added, the mixture filtered, and diluted alcohol added up to 100.

U.S.P. TINCTURA OPII CAMPHORATA. CAMPHORATED TINCTURE OF OPIUM.—dered opium, 4; benzoic acid, 4; camphor, 4; oil of anise, 4; glycerine, 40; ted alcohol up to 1,000.

U.S.P. VINUM OPII. WINE OF OPIUM.—Powdered opium, 10; cinnamon, 1; es, 1; stronger white wine up to 100.

COMPOSITION OF OPIUM.—Besides the usual constituents vegetable products, such as mucilage, albumin, pectinous su stances, caoutchouc-like substances, fat, volatile substances, son sugar, salts of ammonium, calcium, and magnesium, opium co tains seventeen or eighteen alkaloids and two neutral substances, well as a peculiar acid—**meconic acid.** The **alkaloids** are chief combined with meconic acid or sulphuric acid, but may be part free. The three most important alkaloids are morphine, codein and thebaine. The others are papaverine, pseudomorphine oxymorphine, gnoscopine, codamine, laudanine, laudanosin meconidine, lanthopine, protopine, cryptopine, narcotine, ox narcotine, hydroctarnine, narceine, rhœadine. The **neutr substances** are meconin and meconiasin. Some at least of th alkaloids in opium may be regarded as **derivatives** from mo phine. Thus codeine and pseudomorphine or oxymorphine ca be produced from morphine artificially.

Besides the derivatives of morphine found naturally in opium various series of **alkaloids** can be **artificially prepared** fro morphine by (*a*) the addition of alcohol radicals, or by (*b*) oxid tion, or (*c*) by dehydration. To the series of alkaloids produce from morphine by the addition of alcohol radicals, the name **codeines** has been given. An example of these is codethylin obtained from morphine by the introduction of ether. Amon the alkaloids produced by oxidation are oxymorphine and oxyd morphine. **Apomorphine** is produced by dehydration.

B.P. Acidum Meconicum. MECONIC ACID. $H_3C_7HO_7$. A acid obtained from opium.

CHARACTERS.—In micaceous crystals, nearly colourless, th solution in water having a strongly acid taste and reaction.

SOLUBILITY.—It is sparingly soluble in water, readily soluble in alcohol.

REACTIONS.—The solution is coloured red by neutral solution of perchlori of iron, the colour being discharged by strong but not by diluted hydrochlor acid. The aqueous solution gives no precipitate with solution of iodine a iodide of potassium.

OFFICIAL MECONATE.

B.P.	DOSE.
Liquor Morphinæ Bimeconatis	5–40 min.

ACTION.—It has very **little** physiological **action.** It has bee stated to have a narcotic action, but this is very feeble.

U.S.P. Morphina. MORPHINE. $C_{17}H_{19}NO_3.H_2O$; 303.—A alkaloid prepared from opium.

CHARACTERS.—Colourless or white shining prismatic crystal or a crystalline powder. Permanent in air, having a bitter tas and alkaline reaction. Heated on platinum foil, the crystals fus char, and disappear.

SOLUBILITY.—Slight in cold water; complete in 500 parts boiling wate in 100 alcohol at 15° C. (59° F.); in 36 boiling alcohol; in 13 boilin absolute alcohol; almost insoluble in ether; slightly soluble in chloroform

REACTIONS.—Morphine is first reddened and then rendered yellow by tric acid. With ferric chloride it gives a blue colour, changed to green by cess of the reagent, and destroyed by free acids or alcohol, but not by kalis. A solution of morphine, acidified by acetic or sulphuric acid, is t precipitated by tannic acid.

IMPURITIES.—Other alkaloids.

TESTS.—On adding 20 parts of colourless solution of soda or potassa to part of morphine, a clear, colourless solution should result without a residue bsence of other alkaloids). Morphine yields a colourless solution with d concentrated sulphuric acid, which should not acquire more than a ldish tint by standing for some time, and which should not assume a rple or violet, but merely a greenish colour, on the addition of a small stal of bichromate of potassium (absence of and difference from strych-ne, brucine, &c.).

Morphinæ Hydrochloras, B. and U.S.P. HYDROCHLORATE MORPHINE, U.S.P. $C_{17}H_{19}NO_3HCl.3H_2O$.

CHARACTERS.—White, feathery, acicular prisms of a silky stre, permanent in air.

SOLUBILITY.—It is soluble in water (24 parts at 15° C.) and spirit.

REACTIONS.—The aqueous solution gives a white curdy precipitate with rate of silver (HCl), and a white one with potash, soluble in excess orphine). It exhibits the reactions of morphine. Heated on platinum l, it leaves no residue (no inorganic salts).

PREPARATION.—Mix concentrated infusion of opium with chloride of cium, decolorise by animal charcoal, precipitate the morphine by ammonia, l neutralise with hydrochloric acid.

PREPARATIONS.

U.S.P. None.

B.P.		DOSE.
quor Morphinæ Hydrochloratis	$4\frac{1}{2}$ grs. in 1 fl. oz., or 1 per cent.	10–60 min.
ppositoria Morphinæ	$\frac{1}{2}$ gr. in each suppository...	
„ „ **cum Sapone**	$\frac{1}{2}$ gr. „ „ ...	
nctura Chloroformi et Morphinæ	1 gr. in 1 fl. oz.	5–10 min.
ochisci Morphinæ	$\frac{1}{36}$ gr. in each lozenge	1–4.
„ „ **et Ipecacuanhæ**	$\frac{1}{36}$ gr. „ „	1–4.

Liquor Morphinæ Hydrochloratis. SOLUTION OF HYDROCHLORATE OF RPHINE.—Add diluted hydrochloric acid (9 min.), rectified spirit (2 fl. dr.) to tilled water (6 fl. dr.), and dissolve hydrochlorate of morphine ($4\frac{1}{2}$ gr.) in the xture.

Tinctura Chloroformi et Morphinæ. TINCTURE OF CHLOROFORM AND RPHINE.—It contains in a 10-minim dose chloroform, $1\frac{1}{4}$ min.; ether, $\frac{1}{3}$ min.; tified spirit, $1\frac{1}{4}$ min.; hydrochlorate of morphine, $\frac{1}{48}$ gr.; diluted hydrocyanic d, $\frac{5}{8}$ min.; oil of peppermint, $\frac{1}{80}$ min.; liquid extract of liquorice, $1\frac{1}{4}$ min.; treacle, l syrup. It resembles chlorodyne.

Morphinæ Acetas, B. and U.S.P. ACETATE OF MORPHINE. $_7H_{19}NO_3.C_2H_4O_2$.

CHARACTERS.—A white powder, with a faintly acetous odour.

SOLUBILITY.—Soluble in water and in spirit.

REACTIONS.—Potash or soda gives a precipitate soluble in excess, and ibiting the reactions of morphine, U.S.P. When sulphuric acid is added he salt, acetous vapours are evolved. When freshly prepared it is soluble 12 parts of water at 15° C.

PREPARATION.—Obtain morphine by precipitating it from the hydro-orate by ammonia, dissolve it in acetic acid and crystallise, B.P. In the S.P. morphine is officinal, and requires only to be dissolved in acetic acid.

PREPARATIONS.

U.S.P. None.

B.P.	DOSE.
Liquor Morphinæ Acetatis.....4 gr. in 1 fl. oz., or 1 per cent....	60 min.
Injectio Morphinæ Hypodermica, 1 gr. in 10 min.	1–5 min or mor

Liquor Morphinæ Acetatis. SOLUTION OF ACETATE OF MORPHINE.—It prepared like the solution of the hydrochlorate, using the acetate of morphine a acetic acid.

Injectio Morphinæ Hypodermica. HYPODERMIC INJECTION OF MORPHI —A solution of acetate of morphine, containing 1 grain of the acetate in 10 mini of the injection. Acetate of morphine is freshly prepared by precipitating morph from a solution of 92 grains of hydrochlorate of morphine in 2 ounces of wa distilled water, with sufficient ammonia to render the solution alkaline. T morphine is washed on a filter, dissolved in about an ounce of distilled water w the addition of acetic acid, and the use of gentle heat, until the whole of the m phine is dissolved and a slightly acid solution formed. Enough distilled wate now added to make up the solution to 2 fluid ounces exactly. It is then filter and kept from the light in a stoppered bottle.[1]

Morphinæ Sulphas, B. and U.S.P. SULPHATE OF MO PHINE. $(C_{17}H_{19}NO_3)_2.H_2SO_4.5H_2O$; 758.

CHARACTERS.—White feathery silk crystals, permanent in a with no smell, but a bitter taste.

SOLUBILITY.—Soluble in 24 parts of water at 15° C.

REACTIONS.—In its reactions it corresponds to the hydrochlorate, but known to be a sulphate by giving with chloride of barium a white precipit insoluble in hydrochloric acid.

U.S.P. PREPARATIONS. NONE IN B.P.

	DOSE.
Pulvis Morphinæ Compositus	10 gr. (0·65 gm.)
Trochisci Morphinæ et Ipecacuanhæ.....	1 or 2.

U.S.P. PULVIS MORPHINÆ COMPOSITUS. COMPOUND POWDER OF MORPHI (Tully's Powder).—Sulphate of morphine, 1; camphor, 20; glycyrrhiza, 20; p cipitated carbonate of calcium, 20; alcohol, q.s. to mix the camphor intimat with the other ingredients. It is intended as a substitute for Dover's powder.

Apomorphinæ Hydrochloras, B. and U.S.P. HYDROCHL RATE OF APOMORPHINE. $C_{17}H_{17}NO_2HCl$; 303·4.—The hydrochl rate of an artificial alkaloid prepared from morphine. It shou be kept in small, well-stoppered vials, in a dark place.

PREPARATION.—By heating morphine or codeine in sealed tubes w concentrated hydrochloric acid.

CHARACTERS.—Small, greyish-white, shining, acicular crysta turning green on exposure to light and air, inodorous, with very faint acid reaction on moistened litmus-paper.

SOLUBILITY.—Soluble in thirty-five parts of alcohol, the solutions be decomposed with production of a green colour when they are boiled.

REACTIONS.—From solutions, bicarbonate of sodium throws down a p cipitate which becomes green on standing and then forms a purple soluti

[1] The possibility of morphine being transformed into apomorphine by l keeping in solution should be remembered. A 3 per cent. solution of hydrochlor of morphine, which was hypnotic when freshly prepared, became partly convert into apomorphine after being kept for eleven months, and then produced viol vomiting.—*Brit. Med. Journ.*, June 26, 1886, p. 1222.

with ether, violet with chloroform, and bluish-green with alcohol. With dilute solution of perchloride of iron it gives a deep red and with nitric acid a blood-red coloration.

B.P. PREPARATION.

Injectio Apomorphinæ Hypodermica.—(2 grains dissolved in 100 minims of camphor-water and filtered. It should be made as required for use.)

DOSE.—$\frac{1}{10}$–$\frac{1}{5}$ grain (·006–·012 gm.), or 2–8 minims of the B.P. injection, hypodermically as emetic.

ACTION.—When given internally or injected hypodermically apomorphine acts as an **emetic**, producing nausea and vomiting in from five to twenty minutes. After vomiting has occurred the nausea usually disappears quickly. It usually produces less depression than tartar emetic, but collapse has occurred from its use in children. It probably causes vomiting, partly reflexly and partly directly, in the same way as tartar emetic (p. 373). It stimulates the **motor centres** in the **brain** and the respiratory and vomiting centres in the **medulla**, and afterwards paralyses them.

In rabbits, which cannot vomit, apomorphine causes constant movement, rapid breathing, convulsions, paralysis, and death. In cats and dogs small doses cause vomiting, while large doses do not, but produce *manège* movements and paralysis; some degree of inco-ordination of gait may be observed in man after a large dose.

It paralyses **muscular fibre**, voluntary and involuntary, but does not affect motor or sensory nerves. The **pulse** is at first quickened, while the blood-pressure is unaltered; but large doses paralyse the heart. The **secretion** of bronchial mucus is increased (p. 253).

USES.—It is used as an emetic for the purposes already mentioned (p. 374). Its special advantages are the readiness with which it can be administered by hypodermic injection without causing any local irritation and the short duration of the nausea it occasions. It is useful also as an expectorant, alone or along with morphine (p. 250).

Codeina, B. and U.S.P. CODEINE. $C_{18}H_{21}NO_3.H_2O$; 317.—An alkaloid contained in opium. It is probably methyl-morphine. Morphine $= C_{17}H_{18}NO_2(OH)$; codeine $= C_{17}H_{18}NO_2(OCH_3)$.

CHARACTERS.—In colourless or nearly colourless octahedral crystals. The aqueous solution has a bitter taste and an alkaline reaction.

PREPARATION.—It is separated from the ammoniacal liquors from which morphine has been obtained, by evaporating, treating the residue with water, precipitating with caustic potash, and purifying the precipitated alkaloid by recrystallisation from ether.

SOLUBILITY.—It is soluble in eighty parts of water and of solution of ammonia, readily soluble in spirit and in diluted acids.

REACTIONS.—The alkaloid dissolves in sulphuric acid, forming a colourless solution, which, when gently warmed with molybdate of ammonium or a

trace of perchloride of iron, assumes a deep blue colour, Moistened w strong nitric acid it becomes yellow but not red (difference from and abse of morphine). Ignited in air it yields no ash.

DOSE.—For diabetes ¼ grain gradually increased to 5 gra or more three times a day, unless it produces great drowsin or the sugar disappears. For cough ⅙ of a grain every three four hours.

ACTION.—Codeine has only a slight hypnotic action, and m sometimes be given in doses of 15 grains daily without produci any marked drowsiness in diabetic patients. Others again rendered drowsy by 5 or 6 grains daily. Its most marked act appears to be on the **nerves** of the abdominal **viscera** and motor centres in the brain. When given for several days lessens the irritability of the digestive tract so that irrita poisons, like arsenic, produce neither vomiting nor purging.

It increases the irritability of the **spinal cord**, and produ in frogs languor succeeded by convulsions and paralysis. mammals it appears rather to stimulate **motor centres** in brain (p. 190). It causes some drowsiness, but the motor p nomena are most marked. These are twitchings, *manège* swimming movements, paralysis of the hind-legs, and weaker circulation, followed by a sudden shriek and convulsions. De may occur at once or recovery take place.

I have observed symptoms very like these in poisoning pure brucine, and in some points they resemble those of pic toxin (p. 838).

USES.—Although it is not a powerful hypnotic, like morphi codeine has been strongly recommended in nervous insomn and also in cases where sleep is prevented by the pain of rh matism or cancer, or by distressing cough. Its power to less the irritability of the intestinal nerves has been already m tioned, and possibly it exerts a similar action on the nerves other viscera, such as those of the respiratory organs, &c. S an action would explain its beneficial effects in **cough** w morphine cannot be borne. Its chief use is in **diabetes.**[1] certainly lessens, and sometimes entirely removes, the su from the urine. As Claude Bernard found that irritation of central end of the cut vagus caused dilatation of the hepa vessels and the appearance of sugar in the urine, it seems improbable that the utility of codeine in diabetes is due to power of lessening the irritability of the afferent fibres in nerves of the abdominal viscera. This is rendered all the m likely by the fact that codeine does not prevent the occurrenc sugar in the urine in carbonic oxide poisoning,[2] where alterati in tissue change, leading to glycosuria, are probably of a m general nature, and less dependent on local alterations in hepatic circulation.

[1] Pavy, *Guy's Hospital Reports.* [2] The late Otto Schultzen.

Physiological Action of Opium.

General Action.—Opium, and all its alkaloids hitherto examined, act almost exclusively on the **central nervous system,** and in mammals especially on the brain, the brain-symptoms preponderating in proportion as the organ is developed relatively to the other nerve-centres. This conclusion holds good only for mammals, and must be qualified in regard to the frog, for in it narcotine, codeine, papaverine, and thebaine have also a paralysing action on the motor ganglia of the **heart.** Opium and its alkaloids agree not only in the organ they affect but in the nature of their action. The symptoms may be divided into two stages :—

(1) **Narcosis,** due to a paralytic action on the brain, followed by

(2) **Tetanus,** due to increased irritability of the spinal cord.

Action on Frogs.—If the drug be introduced by injection under the skin of a frog, the **functions of the nerve-centres** are **abolished** in the order of their development, the highest centres being first affected (*vide* p. 183).

The first symptom to appear after the injection of the drug is a diminution of the power of voluntary movement; the frog remains quiet, making no effort at voluntary movement; but when irritated responds to the stimulation by springing in the usual way. Next, the power of co-ordination is lost; the frog springs as before when irritated, but has no control over the direction of its leaps. It then gradually loses the power of springing in response to stimulation, and finally reflex action cannot be excited. The heart is unaffected.

After a time increased excitability of the spinal cord comes on, so that the slightest irritation causes muscular spasms like those of strychnine-poisoning. During this condition the spinal cord of the frog does not react to stimuli in the ordinary way, but responds as it were by one violent explosion, after which it seems to become exhausted for a time, but after an interval another violent spasm can be induced, so that there are alternating periods of spasm and exhaustion. If the action of the drug be not pushed beyond this point, the phenomena will pass off in the reverse order of their appearance. If pushed further, there succeeds a deepening paralysis, and respiration becomes first slower and then stops.

Action on Birds.—Birds are peculiarly insusceptible to the action of opium or morphine. But morphine produces in them a marked lowering of body temperature, sometimes to the extent of 5° or 6° C.[1]

[1] Brunton and Cash, *Central. f. die med. Wissensch.*, 1886, p. 241.

Action on Mammals.—Opium causes partial abolition voluntary movement, sometimes preceded by a certain amou of increased excitability, followed by sleep. Sometimes th spinal cord shows signs of increased excitability with diminishe conducting power, evidenced by convulsions with a tendency paralysis of the hinder limbs.

Action on Man.—In man the action of opium is chief upon the **brain**, producing sleep. When taken in **small dose** of ¼ gr. to 1 gr. there is, first, a stage of **excitement** of the ci culation, as evidenced by the pulse being fuller and quicker, ar by the surface of the skin being warm and flushed. During th stage the individual has the power of directing his energies any particular object, and the action of the drug causes him do well whatever he wishes to do. Thus, if he wishes to slee and surrounding circumstances be favourable, an agreeab languor followed by quiet sleep comes on. He can be easi aroused from this sleep; and after a few hours the effect pass off, leaving, however, slight headache and languor, with dryne of mouth and slight nausea. If, on the other hand, he wish to work, he can do this with increased energy; or, if he desir to exert the mind, he will find his imagination more vivid, h thoughts more brilliant, and his power of expression greate (Christison). The after-effects are the same as after sleep.

With **moderate doses** of 1 gr. to 2 grs. the stage of **excite ment** is **short** and is followed by **deep sleep**, from which th person can still be aroused. The after-effects are severe hea ache, with nausea, furred tongue, and loss of appetite. Duri the stage of sleep the brain is anæmic, both the arteries ar veins being empty (*vide* p. 197).

With **large doses**, of 3 grs. or more, the **first stage** is ver **short**. **Sleep** rapidly follows, becomes deeper and deeper, an passes into **coma**, from which the patient can no longer l aroused. The arms and limbs are limp; the face is general pale, with a bluish tinge at times; the eyes are sunken, th pupils very much contracted, almost to the size of a pin's point respiration slow and stertorous. The pulse during sleep an coma is slow and full; as coma proceeds it becomes feeble Finally **death** by asphyxia occurs, the respiration ceasing befo the heart. It may occasionally be preceded by convulsion though this is rare.

Post mortem the ordinary appearances of death by asphyx are found, viz. congestion of the brain and lungs, &c.; the ve tricles of the brain contain serous fluid, the veins of the brai and spinal cord are distended with dark blood, and there ma be slight extravasation of blood in some of the tissues.

Diagnosis between Opium-poisoning, Intoxication, an Apoplexy.—One should obtain the history of the case where is possible, as this may enable one to diagnose not only betwee

opium-poisoning, intoxication, and apoplexy, but between these and other forms of coma, e.g. post-epileptic and uræmic coma. The former is recognised by the history of convulsions, and the latter by the presence of albumen in the urine, with sometimes œdema of the legs. When the history cannot be obtained—for instance, in cases where the patient is found lying unconscious—the diagnosis is sometimes extremely difficult.

Notice first the odour of breath; the **smell** guides one in opium-poisoning. The smell of alcohol does not assist one much, as it may be taken with opium; and in apoplexy brandy is frequently given by the person who first finds the unconscious patient.

Secondly, the **pupil**, which is very much contracted in opium, but dilated in alcoholic, poisoning, and often unequally contracted in apoplexy. It must be borne in mind that in apoplexy of the pons varolii, the pupils may be equally and extremely contracted, just as in opium-poisoning. In apoplexy the arms on being raised and then relaxed fall unequally on the two sides, one being more rigid or flaccid than the other. The **rectal temperature** is often an important sign, as in apoplexy there is an initial fall with a subsequent rise in the majority of cases. In no case should the individual be treated roughly or exposed to the slightest chance of a chill, but, on the contrary, he must be kept warm; and if it appears to be a case of poisoning by alcohol or opium, and not apoplexy, the stomach should be washed out and strong coffee injected.

Treatment in Opium Poisoning.—Evacuate the stomach as soon as possible by administering 20 grs. of zinc sulphate in a little water; if this acts, then give some strong coffee. Sometimes the zinc will not produce vomiting on account of the insensibility of the stomach and vomiting centre, due to the action of the opium. If such be the case, employ the stomach-pump, wash out the stomach with warm water, and inject coffee. Keep the patient awake by walking him about the room, tapping on the forehead with the finger-nails, or flicking him with a wet towel. Apply mustard-leaves to various parts of the body, or use a galvanic battery. Cold affusion is a good adjunct; but the alternate use of hot and cold water is better both as a stimulant and as preventing the risk of chilling the patient. Lastly, give a subcutaneous injection of 4 minims of liquor atropinæ sulphatis, B.P. every ten minutes, until symptoms of recovery show themselves or the pulse is quickened or the pupil dilated.

Precautions.—Do not allow the patient to become cold while trying to rouse him, and take care not to chill him when applying cold affusions, as death may result from syncope after recovery from the comatose condition. The average length of insensibility is twelve hours, and if this period be passed, recovery is nearly certain, but sometimes the symptoms may reappear, and death from asphyxia or syncope occur.

Treatment of the Symptoms after an Ordinary Dose.—Strong coffee with or without brandy, or lemon-juice and wate should be administered. The patient should be kept in bed.

Action on Special Organs.—Opium has little action c **muscular contractility.** The action of opium on the moto **nerves** is doubtful. According to some observers, it first in creases and then diminishes their excitability, the action com mencing at the centres and proceeding towards the peripher Others, however, have found that opium has little or no actio on them, except towards the end of poisoning, when all th functions are paralysed.

The **sensory nerves** are first excited and then paralyse Opium applied locally is said by some observers to have n action on the sensory nerves, but it has been found to have paralysing action by Baxt. The results of his experiments a confirmed by clinical experience, for when the drug is injecte subcutaneously it lessens sensibility, diminishes the power distinguishing tactile impressions, and relieves pain whe present.

When applied externally to the eye, or to the skin denude of its epidermis, opium also relieves pain.

Opium lessens first the conducting power of the **spinal cor** then the reflex functions, producing first inco-ordination of th movements of the hind limbs and then paralysis of reflex actio

Opium acts on the centres of the **brain** in the order of the importance; thus in the frog, there is, first, loss of voluntar motion, such as may be produced by extirpation of the cerebr hemispheres; next, loss of co-ordination, such as is produced b extirpation of the optic lobes; and lastly, effects like those pr duced by destruction of the medulla (p. 183).

The **pupil** is markedly contracted by opium, the action of th drug being probably central and not peripheral; but the exa mode of action has not been definitely made out. Stimulatio of sensory nerves causes reflex dilatation of the pupil, and it not improbable that the contraction which opium produces due to its paralysing this reflex action more or less completel (p. 219).

The pupil sometimes dilates just before death. This dilata tion is probably due to the excessively venous condition of th blood, as in the later stages of chloroform-poisoning.

The first effect which opium has on the **circulation** is t cause a dilatation of the vessels of the skin, sometimes givin rise to a cutaneous eruption of a roseolous character accon panied by itching, and coming on either before or after sleep.

The **vaso-motor** centre in the medulla is slightly, if at al affected by small doses of opium. Large doses paralyse it.

The drug appears to have a peculiar action on the **peripher vaso-motor apparatus.** It is well known that stimulation

the chorda tympani causes dilatation of the vessels of the submaxillary gland; but I found that after the exhibition of opium the vessels of the gland no longer dilated, but on the contrary contracted, on stimulation of the chorda tympani, so that the blood which issued from the gland was not of a bright arterial hue, but was very dark, and flowed drop by drop. This observation requires confirmation; but if it be confirmed, this result might serve to explain the effect of opium in cutting short inflammations, e.g. of the peritoneum.

In peritonitis as in other inflammations the blood-vessels are greatly dilated. Opium by its action on the vaso-motor centre, and (if these experiments be correct) by its action also on the peripheral terminations of vaso-motor nerves, will prevent or diminish the reflex dilatation of the vessels which the local irritation would otherwise produce. Congestion will thus be diminished and inflammation be relieved. The action of opium in peritonitis is therefore probably twofold. First, it lessens peristaltic movements of the intestines, and thus diminishes local irritation. Secondly, it lessens the reflex activity of the centres through which local irritation causes dilatation of the vessels, and thus diminishes peritoneal congestion. The late Sir Robert Christison used to say that not only coryza, but probably all inflammations, could be nipped in the bud by opium if it were only given sufficiently early and sufficiently freely.

The blood-pressure appears to be but little affected by opium. It varies after the injection of the drug, but this variation is probably due to an alteration in the general functions of the body, for example, great quiet, &c.

Opium has little direct action on the **heart,** which continues to beat after the nervous centres have been experimentally destroyed in animals.

On Secretion.—The secretions of the body, except those of urine and of sweat, are lessened by opium.

If the lingual nerve of an animal be stimulated, a reflex flow of **saliva** takes place; but when opium has been given in sufficient quantity this reflex action is paralysed, and stimulation of the nerve no longer excites a flow. Very large doses, however, may cause salivation (p. 355). Opium also diminishes the other secretions of the alimentary canal, causing impairment of digestion, and this action serves partially to explain the constipation produced by opium.

The quantity of **sweat** secreted is increased by opium, and especially so when it is combined with ipecacuanha. Just before death by opium the secretion of sweat is greatly increased, so that the surface is bathed in it; but this is due to stimulation of the sweat-centres in the spinal cord by the increasing venosity of the blood (p. 438).

The quantity of **urine** is frequently lessened. Sometimes may be really increased, but appear diminished in consequen of paralysis of the bladder preventing its being evacuate Sometimes there is a constant desire to pass water.

On the Intestines.—The action of opium on the intestin varies with the dose. On isolating a piece of intestine a supplying it artificially with blood, the action of opium may observed by mixing it with the blood (p. 383). When used large quantity all peristaltic action ceases, and the intesti becomes tetanically contracted. Hence in large doses, inject directly into the jugular vein, it acts as a most powerful pu gative, causing one very copious evacuation. It acts chiefly the small intestines. In moderate doses it lessens peristal action and causes constipation. In very small doses it genera increases peristalsis and acts as a purgative, but not invariabl so. This property is made use of in cases of constipation d to reflex irritation starting from the ovary. The mode of acti has already been discussed (p. 385).

Elimination.—Morphine is eliminated by the gastric muco membrane (p. 39), and may be found in the stomach after su cutaneous injection. It is excreted also in the bile, but m remain a long time in the liver. It is found unchanged in t urine. In cases where its use has been continued for some tim some of it probably becomes changed in the body, as a substan with the chemical reactions of oxydimorphine has been found the liver and kidneys in such cases (p. 35).

Circumstances Modifying the Action of Opium.

Age.—In childhood the brain is proportionately larger th in adult life and absorption much more rapid, hence the effe of opium is greater than in adults, and children bear it ve badly; consequently smaller doses must be given than are pr portionate to their ages. Care is necessary from the age of s months to one year, as 1 minim has produced fatal results. old age the dose must be diminished according to the advance years.

Sex.—Women are more readily affected than men, and m more liable to nausea and headache after its administration.

Idiosyncrasy.—Small doses easily affect some subjects, a on the other hand large doses are nearly inert in others. E citement and delirium, instead of quietness and sleep, are n unfrequently produced. In such cases it is best to give a fe whiffs of chloroform to quiet the patient and induce sleep, if t excitement has already come on.[1] If it is necessary to gi opium or morphine to a patient having this idiosyncrasy, ought to be combined with chloral or a bromide, or with bot

[1] Morrant Baker, *St. Bartholomew's Hospital Reports.*

In some persons excitement and wakefulness occur on the night immediately succeeding the dose, and sleep only occurs on the second night.

Habit.—The effect of habit is perceived in two ways—in some cases large quantities are required to produce a result; in others a long interval is necessary for the drug to take effect. As much as two pints of the tincture have been taken in the course of a day; and as much as 12 grains of morphine have been subcutaneously injected. Both slowness and weakness of action may result from its continued use, so that it may be necessary not only to give a larger dose but to give it a considerable time beforehand. In one case with which I am acquainted, after a few months during which the time gradually increased, it became necessary to give the dose twenty-four hours before its effect was desired.

The explanation of this tardy action probably is that the absorptive power of the intestines is diminished by the continual use of the drug, for it is well known that opium-eaters can take large doses of corrosive sublimate without experiencing any ill-effects, the drug being but slowly absorbed.

But it is quite possible, indeed probable, that there is, besides delayed absorption, another factor in the tolerance of opium induced by repeated doses. It is possible that part of the morphine introduced is converted in the organism into oxydimorphine, which appears, to a certain extent, to counteract the soporific action of morphine,[1] or into other substances which may have this action (see p. 35). Each dose of morphine will thus leave in the body substances having an action antagonistic to the next dose, unless a sufficient interval should elapse between them to allow them to be completely eliminated.

Opium-eating—Morphinism.—When opium is first taken, its action is to stimulate and afterwards depress; to remove this depression the individual takes another dose; the habit of taking the drug thus becomes established. The nervous system suffers, the mental powers become enfeebled, the moral faculties perverted, and there is inability to distinguish between truth and falsehood. Then the motor powers are attacked, the gait becomes shuffling and uncertain, and digestion is impaired. The bowels may be constipated, but are generally loose.

When morphine is taken for some time in medicinal doses, obstinate vomiting sometimes sets in and will not yield to ordinary remedies. It is usually checked by discontinuing the administration of the drug. This vomiting may possibly be due to the morphine being converted into oxydimorphine[2] or apomorphine in the system.[3]

[1] Diedrich, *Ueber Oxydimorphin*, Inaug. Diss., Göttingen, 1883.
[2] Diedrich, *op. cit.*
[3] The view expressed in the text received a curious confirmation shortly after

If the patient has been accustomed to the use of hypoderm injections of morphine, hypodermic injections of water shou be substituted in such cases and the strength supported by ca ful frequent administration of nourishment.

Disease.—When a patient is suffering intense pain, opiu is well borne, and must be given in large quantities; as, example, to a person suffering from peritonitis. In cases Bright's disease small doses may produce disproportionately gr effects (p. 41). Hence in these cases the drug must not be giv in large quantities, and the effect of each dose must be carefu watched.

Combination with other Drugs. — Chloroform sometim modifies the action of opium, the chloroform narcosis passi into opium sleep, or the opium sleep may more resemble chlo form anæsthesia; hence the use of the two drugs together may of advantage in certain operations, such as excision of the ja where it is difficult to continue administering an anæsthetic (p. 20

In some cases opium will not produce sleep even in la doses, and it is then advisable to combine it with a small dose hydrate of chloral. Sometimes when opium has been given produce sleep, and has only caused excitement, a few whiffs chloroform will quiet the excitement, and the patient sinks i a quiet sleep.

Action of the Alkaloids of Opium.—The action of t opium alkaloids has not been fully made out, and various resu have been obtained by different observers. It is certain, ho ever, that morphine is in mammals almost entirely narcot whilst thebaine is purely convulsive. Between these extrem the other alkaloids probably range themselves in such an or that they may be divided into two sub-groups, the first of whi may be called the morphine group, characterised by the p minence of the narcotic stage; while in the other, which may called the codeine group, the tetanic stage is more promine and the narcotic less so. The members of these groups may arranged as follows, so that each subsequent member has weaker narcotic, and in the codeine group has at the same ti a stronger convulsive, action :—

Morphine Group.	Codeine Group.
Morphine.	Papaverine.
Oxydimorphine.	Codeine.
	Narcotine.
	Thebaine.

---

the appearance of the first edition of this book by the following annotation in *Lancet*, which seems to show that emetic substances (? alkaloids) are excreted the saliva of opium-eaters :—An envelope received from a person who habitu took large quantities of morphine hypodermically was reclosed by the person v opened it, by licking the adhesive surface, with the result of making him violer sick.—*Lancet*, May 23, 1885, p. 959.

The codeine group contains also hydrocotarnine, laudanosine, and cryptopine; but at present we know too little about them to assign a place in the group to them with certainty. The same may be said of codethyline. The codeine group becomes closely allied by its last members with the strychnine group.

By the addition of **alcohol-radicals** to morphine, substances to which the name of **codeines** has been given are produced. In some of these, such as codethyline, $C_{17}H_{18}NO_2(OC_2H_5)$, obtained from morphine by the introduction of ethyl, the narcotic action is diminished, whilst, according to Von Schroeder, the convulsive action is increased, in proportion to the number of atoms of hydrogen substituted by alcohol-radicals. If such be the case it is remarkable that by the addition of alcohol-radicals to codeine or thebaine, their tetanising action should be altered into a paralysing action, methyl-thebaine producing paralysis like methyl-strychnine.[1]

In the alkaloids produced from morphine by **oxidation** (oxydimorphine and oxymorphine) the narcotic action is diminished, without the convulsant action being increased. Narceine has no apparent physiological action.[2]

Apomorphine has no narcotic action, but is an emetic acting on the vomiting centre in the medulla. In large doses it does not produce vomiting, but causes peculiar *manège* movements.

Morphine is said to be less constipating, less diaphoretic, and less nauseating than opium. Others affirm that opium is less nauseating. It is also said that opium quickens the pulse and raises the temperature at first, and then depresses both, while morphine depresses them both from the first.

The activity of morphine appears to depend on the presence of **hydroxyl** (HO) in it. When this is replaced by SO_4 its activity is greatly diminished.[3]

THERAPEUTICS.—**General Uses.**—The general uses of opium in disease are (1) to lessen pain; (2) to produce sleep; (3) to lessen irritation in various organs.

Local Uses.—Opium is a local sedative, and is applied to the skin and irritable surfaces to relieve pain, thus:—

Fomentations or liniments containing it are used for inflamed joints, myalgia, lumbago, pleurisy, peritonitis, herpes zoster, etc.

Morphine dissolved in glycerine and spread on lint is used to allay pain in cancer; and, applied either by the endermic or hypodermic method, is useful in neuralgia. In many cases, however, the injection of pure water will relieve the pain, and hence part of the relief is probably due to the local irritation caused by the injection.

---

[1] Crum-Brown and Fraser, *Trans. Roy. Soc. of Edinburgh*, vol. xxv.
[2] Von Schroeder, *Archiv f. exper. Path. und Pharm.*, vol. xvii. p. 96.
[3] Stolnikow, *Ztschr. f. Physiol. Chemie*, viii. p. 236.

Opium lessens pain in conjunctivitis, earache, and tootha
In conjunctivitis it may be used in the form of liquid ext
dropped into the eye; and in toothache applied to the cavit
the tooth as laudanum on a pledget of cotton wool. In the la
malady it is well to add a little sodium bicarbonate, to neutra
the acid secretions in the mouth.

Opium, used in the form of ointment of galls and opium
of opium or morphine suppositories, relieves pain in the rec
caused either by ulcers, fissure, or hæmorrhoids.

Morphine subcutaneously injected has been used to proc
local anæsthesia, as in evulsion of the toe-nail.

Digestive System.—Opium often relieves salivation w
due to reflex irritation in the mouth; if this fails, bellado
may succeed (p. 361).

It relieves the pain and vomiting due to irritability of
stomach, as in cancer and ulcer of the stomach, but if they
due to simple neuralgia of the stomach, small doses of ars
are preferable.

In biliary colic opium or morphine is given either by
stomach or hypodermically. It may be used either with
instead of, the inhalation of chloroform (pp. 208 and 209).

In diarrhœa opium is often useful when ordinary astring
fail.

In dysentery it is generally combined with ipecacuanha.

In cholera opium is frequently given, but during the
stage absorption is so slow that it has very little action.
these cases patients have been known to die from opium-pois
ing, as soon as partial recovery had taken place and absorp
was re-established.

In peritonitis it is used both internally and externally.
should be given freely in doses of 1–2 gr. every four hours
oftener, and fomentations to the abdomen should be used
ternally. The action of the opium in this disease is twof
and possibly threefold:—(i.) It stops the peristalsis of the bo
(ii.) It relieves pain. (iii.) It has possibly an action on the bl
vessels, lessening congestion in the manner already discus
(p. 855).

Very small doses (1 or even ½ drop of tinctura opii in sy
or peppermint water) relieve certain forms of constipation,
that caused reflexly by ovarian irritation. The opium prob
acts on some reflex centre in the lumbar portion of the cord,
the minute dose probably just turns the reflex impulse from
inhibitory to the motor fibres of the splanchnic (p. 385).
these small doses are insufficient, the opium may be gradu
increased until it is clear that it is increasing instead of lesse
the constipation.

Respiratory Tract.—Opium will cut short catarrhal co
tions of the respiratory tract, and 10 grains of Dover's pow

t night are very useful when a 'cold' is coming on. It is also sed in phthisis to cut short an acute exacerbation due to taking old (p. 331).

It relieves cough, and is best given in the form of linctus, so as o act locally as well as generally (p. 249 *et seq.*). Applied locally t is used to relieve cough and pain on swallowing in tubercular lisease of larynx, and a very good method is to mix $\frac{1}{6}$ to $\frac{1}{3}$ gr. of norphine with 1 gr. of starch or 3 grs. of subnitrate of bismuth, nd blow the mixture well down into the larynx, the patient aking a deep inspiration at the same time (*vide* p. 497). Opium s used in asthma and bronchitis, but one should be careful of ts use when the secretion from the bronchial mucous membrane s profuse; for during sleep, when the respiratory and other entres are dulled by the opium, the fluid may increase to such n extent as to suffocate the patient, who is unable to expectorate t on awaking.

Circulatory System.—It is useful in cardiac dyspnœa with leeplessness, and in angina pectoris it sometimes gives relief.

It is useful in hæmorrhages, especially those from the uterus. t may be combined with digitalis (tincturæ opii ♏xxx., tincturæ igitalis, ♏xxx.).

Genito-Urinary Tract.—Opium is used in diabetes to lessen he amount of urine and of sugar, but codeine ($\frac{1}{2}$–5 grs. ter die) s often used instead, the advantage it possesses being that it oes not render the patient so drowsy. Opium allays irritability nd pain, as in renal colic or irritable bladder.

Skin.—If the skin is too dry, Dover's powder will cause iaphoresis, and yet it will check the night-sweats of phthisis.

For the probable cause of this peculiar action *vide* p. 443.

The two most important uses of opium and morphine are to **elieve pain** and **produce sleep.** In their power to relieve pain pium and morphine stand unrivalled, for they can be more enerally applied than anæsthetics, such as chloroform. They requently relieve pain even in doses too small to produce any ther marked effect. When the pain is great large doses may e required, but even then the other effects they would usually roduce seem frequently to be counteracted by the pain, so that hey relieve it without causing drowsiness or stupor. Opium nd morphine are employed in neuralgias of various kinds, such s tic, sciatica, or intercostal neuralgia, in dysmenorrhœa and n cancer. They are used to lessen both pain and inflammation n rheumatism and inflammatory conditions, such as pleurisy, neumonia, peritonitis, cystitis. They are used to lessen pain nd spasm in ordinary colic, lead colic, and in hepatic and renal olic.

Nervous System.—Opium or morphine is used to relieve leeplessness due to almost any cause, but in cases of worry or orn-out conditions of the nervous system it is better to use

bromide of potassium or chloral, as opium-taking becom habit. If these will not act, it may be necessary to use opiu

In fever and delirium 10 min. of tincture of opium ma given with ¼ gr. of tartar emetic, and the effect watched.

In mania, delirium tremens, and chorea, morphine ma given subcutaneously, but bromide of potassium and chlora often preferable.

In intense melancholia subcutaneous injection of morp may be used, but care must be taken not to establish the op habit. Small doses of tincture of opium (5–10 min.) by mouth are also very useful. Care should be taken to disg the drug so that the patient may not know what he is tak and thus to prevent the risk of his taking opium afterward his own pleasure. Morphine is sometimes employed to prolong anæsthesia of chloroform, as in excision of the upper jaw, w it is inconvenient to continue the administration of chlorofor

In malarial poisoning there appears to be a hyper-sensib of the vaso-motor centre, so that a draught of cold air blow on the surface, slight gastric irritation, or even slight disten of the bladder, will cause contraction of the cutaneous ves and shivering, in one suffering from such poisoning. Op appears to be useful in such conditions, probably by lesser the excitability of the vaso-motor centre.

Opium-eaters are frequently found in the fen districts, an some forms of ague in the tropics opium has been of ser when quinine has failed, and the two drugs combined have b still more serviceable than either alone.

Contra-indications :—

(1) Childhood, till the age of 5 years. Either abstain tota or be most cautious in the use of opium and its preparations small doses act with disproportionate power.

(2) Blocking of the bronchial tubes by excessive secretion

(3) Congestion of the brain, with suffused eyes and contrac pupils.

B.P. Rhœados Petala. Red Poppy Petals.—The fr petals of *Papaver Rhœas*. From indigenous plants.

Characters.—Of a scarlet colour and heavy poppy odour. On dry they become dull in colour and lose their odour.

Composition.—They contain a red colouring matter solu in water and spirit, but none of the alkaloids of opium. alkaloid, **rhœadine**, which they do contain has no poison action.

Preparation.

B.P.	dose.
Syrupus Rhœados	1 fl. dr. or more.

Use.—They have little or no physiological action, and only used for colouring.

U.S.P. Sanguinaria. SANGUINARIA. BLOODROOT. — The rhizome of *Sanguinaria canadensis*, collected in autumn.

CHARACTERS.—About two inches (5 centimetres) long, and two-fifths of an inch (10 millimetres) thick, horizontal, cylindrical, somewhat branched, faintly annulate, wrinkled, reddish-brown; fracture short, somewhat waxy, whitish, with numerous small red resin-cells, or of a nearly uniform brownish-red colour; bark thin; odour slight; taste persistently bitter and acrid.

COMPOSITION.—It contains an alkaloid—**sanguinarine.**

OFFICINAL PREPARATIONS.

U.S.P.	DOSE.
Acetum Sanguinariæ	15–30 min.
Extractum Sanguinariæ Fluidum	1–5 min.
Tinctura Sanguinariæ	1–3 fl. dr.

ACTION.—Sanguinarine appears to irritate the **intestinal canal**, producing vomiting and diarrhœa. Small doses after absorption **stimulate** the **medullary centres** for respiration and circulation, and motor centres in the **brain** and spinal **cord.** They thus cause increased respiration, rapid pulse, and increased blood-pressure. Larger doses produce convulsions which are clonic in mammals and tetanic in frogs. In the latter they still persist after section of the cord. Large doses paralyse all these centres, and cause death by paralysis of respiration.

USES.—Except as a stimulant **expectorant** in chronic bronchitis it is rarely employed.

U.S.P. Chelidonium. CHELIDONIUM. CELANDINE.—*Chelidonium majus.*

CHARACTERS.—Root several-headed, branching, red-brown; stem about twenty inches (50 centimetres) long, light green, hairy; leaves about six inches (15 centimetres) long, petiolate, the upper ones smaller and sessile, light green, on the lower side glaucous, lyrate-pinnatifid, the pinnæ ovate-oblong, obtuse, coarsely crenate or incised, and the terminal one often three-lobed; flowers in small, long-peduncled umbels with two sepals and four yellow petals; capsule linear, two-valved and many-seeded. The fresh plant contains a saffron-coloured milk-juice and has an unpleasant odour and acrid taste.

DOSE.—10 to 30 gr.

COMPOSITION.—It contains two alkaloids—**chelidonine** and **chelerythrine**—the latter being supposed to be identical with sanguinarine.

ACTION. –Chelerythrine, however, as obtained from chelidonium, has no tetanising action, but produces **paralysis** and loss of reflex action (Schroff, jun.). Chelidonine has a bitter, acrid taste, but appears to have little physiological action.

USES.—Externally the fresh juice acts as a local irritant, and is used to destroy corns or warts, and to lessen itching in skin diseases. When given internally in large doses it excites violent purging. It was formerly much used in jaundice. It appears to act as a bitter tonic and alterative, and is employed in phthisis and scrofula.

CRUCIFERÆ.

B.P. Sinapis. MUSTARD.—Black mustard seeds and w
mustard seeds powdered and mixed.

Sinapis Albæ Semina, B.P.; Sinapis Alba, U.S.P. Wi
MUSTARD SEEDS.—The dried ripe seeds of *Brassica alba* (*Sin
alba, U.S.P.) Britain.

Sinapis Nigræ Semina, B.P.; Sinapis Nigra, U.S
BLACK MUSTARD SEEDS.—The dried ripe seeds of *Brassica n*
(*Sinapis nigra*, U.S.P.)

The seeds of black mustard are very small, round,
brownish-black outside; those of the white are larger and yell
Both are yellow inside.

CHARACTERS OF THE POWDER.—Greenish-yellow, of an acrid, pun
taste, scentless when dry, but exhaling when moist a pungent, penetra
peculiar odour.

ADULTERATION.—Starch.

TEST.—A decoction cooled is not made blue by tincture of iodine.

DOSE.—As an **emetic**, from one teaspoonful to a tablespoo
of mustard flour, mixed with a little water.

COMPOSITION.—The pungency of the moist powder is due
oil of mustard, but this does not exist in the seeds or fr
powder. Both black and white mustard contain a crystallisa
substance, called in the black **sinigrin**, and in the white **sinall**
and an albuminous body **myrosine**. When moistened, b
sinigrin and sinalbin are split up by the myrosine, which a
as a ferment, and yield a volatile oil. This is not quite
same in the two mustards, that from the black being m
pungent; but the oil from both possesses powerful vesicat
properties. The action of myrosine as a ferment is destroyed
a heat of 60° C.; so mustard poultices should not be made w
boiling water. Black mustard contains less myrosine than wh
—too little, indeed, to decompose the sinigrin completely, so t
its pungency may be increased by admixture with white
directed by the B.P., and as found in ordinary table mustar
Both mustards also contain a **fixed oil**.

PREPARATIONS.

B.P. (of Mustard).	U.S.P. (of Black Mustard).
Cataplasma Sinapis.	Charta Sinapis.
Charta Sinapis.	Oleum Sinapis Volatile.
Oleum Sinapis.	

Charta Sinapis, B. and U.S.P. MUSTARD PAPER.—Consists in the B.
mustard in powder, mixed with solution of gutta-percha, so as to make it stic
the paper upon which it is spread, and then dried. In the U.S.P. the fixed o
removed from the mustard by percolation with benzin before it is spread on
paper. It is used as a substitute for a mustard poultice by immersing it for a
seconds in tepid water and then applying it to the skin. Rigollot's mustard-le
are more frequently used than those of the Pharmacopœia. They cause, as a r

harper pain than the ordinary mustard poultice, and can rarely be borne as long. They are, however, more convenient and readily applied, and in cases of narcotic poisoning the sharp pain they cause renders them preferable to the ordinary poultice.

B.P. Cataplasma Sinapis. MUSTARD POULTICE.—Mix mustard ($2\frac{1}{2}$ ounces) with 2 or 3 ounces of lukewarm water; mix the linseed meal with 6 to 8 ounces of boiling water; add the former to the latter and stir them together.

Oleum Sinapis, B.P.; Oleum Sinapis Volatile, U.S.P.

OIL OF MUSTARD, B.P.—The oil distilled with water from the seeds of black mustard, *Brassica nigra*, after the expression of the fixed oil, B.P. A volatile oil obtained from black mustard by maceration with water, and subsequent distillation, U.S.P. It is sulphocyanide of allyl (C_3H_5CNS).

CHARACTERS.—Colourless or pale yellow. Has an intensely pungent, acrid odour, and burning taste.

SOLUBILITY.—Soluble in alcohol and ether, slightly in water.

ACTION.—Applied to the skin, it produces almost instant vesication.

PREPARATIONS.

B.P.	U.S.P.
Linimentum Sinapis Compositum (*vide* p. 516).	Linimentum Sinapis Compositum (*vide* p. 517). 3 parts of the oil by weight in 100.

ACTION.—Locally applied to the **skin** or mucous membranes, mustard acts as a stimulant, causing warmth, redness, pain passing off if the application is short, but if the action is prolonged vesication is produced. Externally applied for a short time in the form of flying sinapisms, it is also a general stimulant, increasing the force of the circulation. **Internally**, it is a prompt direct emetic (a tablespoonful of mustard in a tumbler of hot water).

USES.—Externally it is used as a **counter-irritant** in myalgia, lumbago, headache, in the form of poultice or paper to the back of the neck; in congestion of the brain, apoplexy, and opium-poisoning, in the form of poultices or leaves to the calves of the legs and other parts of the body. It is applied to the chest in catarrh, bronchitis, congestion of the lung, and catarrhal pneumonia. In phthisis, mustard-leaves applied to the chest are useful to check the spread of consolidation when the patient has taken cold. It is applied to the spine for the relief of pains in the loins, and loss of power in walking accompanying spinal irritation. For this purpose a very useful application is the linimentum sinapis compositum sprinkled on some spongio-piline. Mustard baths to the feet are used in amenorrhœa (p. 453) and sleeplessness (p. 198).

When Rigollot's leaves are used, the pain they cause in persons with delicate skins renders them almost unbearable, and in such cases two or three layers of damped muslin should be placed next to the skin, to modify their action.

With the leaves of the B.P. it is advisable to use one laye muslin to prevent the mustard coming off the leaf and stic to the skin.

Internally, mustard is used as a condiment, to increase appetite by stimulating the mucous membrane. One impor use is that of an **emetic** in indigestion or narcotic poiso (p. 864). In irritant poisoning—e.g. by croton oil—it is given in linseed tea or thin gruel.

B.P. Armoraciæ Radix. Not in U.S.P. HORSE-RA ROOT.—The fresh root of *Cochlearia Armoracia*, cultivate Britain, and most active in the autumn or early spring be the leaves have appeared.



FIG. 180.—Horse-radish root, reduced to ¼ the size.

CHARACTERS.—A long, cylindrical fleshy root, internally white. It pungent taste and smell. Aconite root, which has been mistaken for short and conical, and has a numbing instead of a pungent taste.

COMPOSITION.—A **volatile oil** identical with that of b mustard is developed in it after it has been cut.

PREPARATION.

B.P.	DOSE.
Spiritus Armoraciæ Compositus	1–2 fl. dr.

B.P. Spiritus Armoraciæ Compositus. COMPOUND SPIRIT OF H RADISH.—Sliced horse-radish, dried orange-peel, and bruised nutmeg are mixe diluted proof-spirit and distilled.

ACTION AND USES.—Horse-radish is chiefly used as a co ment in cases of deficient digestion; also as a masticator hoarseness. It is sometimes used in atonic dyspepsia, and diuretic in dropsies. The spirit is used as a pleasant vehicl

VIOLARIEÆ.

U.S.P. Viola Tricolor. VIOLA TRICOLOR. PANSY.— wild-grown, flowering herb of *Viola tricolor*.

CHARACTERS.—Stem angular and nearly smooth; leaves alternate, late, ovate or oblong, crenate, with leaf-like, pinnatifid stipules; flowers an obtuse spur, and the variegated petals shorter or longer than the c inodorous; taste somewhat bitter and acrid.

DOSE.—15 to 75 gr. (1-5 gm.) in decoction.

COMPOSITION AND ACTION.—It contains a little **violine**, a stance similar to emetine, and having an emeto-cathartic ac

USES.—It is used externally in the form of an ointment poultice in eczema and impetigo. It is sometimes given inter in bronchitis.

CANELLACEÆ.

B.P. Canellæ Albæ Cortex. CANELLA ALBA BARK.—The ark of the *Canella alba* deprived of its corky layer and dried. outh Florida and the West Indies.

CHARACTERS.—Large quills or flattish pieces about 1 inch broad; buff-oloured externally; whitish internally. Taste bitter, pungent, acrid; odour ke a mixture of cloves and cinnamon.

COMPOSITION.—A **volatile oil** (about 1 per cent.) consisting of veral oils, of which one is identical with **eugenic acid**, from oil f cloves; a bitter principle, **canellin**, together with resin, starch, nd mannite. There is **no tannin**.

DOSE.—Of the powdered bark, 15–30 grs.

PREPARATION.

B.P.

It is used in Vinum Rhei (60 grs. to 1 pint).

ACTION AND USE.—It is an **aromatic bitter** and **tonic**. Given metimes in atonic dyspepsia. It has been employed in rheu-atism and gout.

POLYGALACEÆ.

Senegæ Radix, B.P.; Senega, U.S.P. SENEGA ROOT.—he dried root of *Polygala Senega*. North America.




FIG. 181.—Senega, half the natural size.

CHARACTERS.—A knobby rootstock with spreading, tortuous rootlets, isted and *keeled*.

ADULTERATIONS.—Ginseng and other roots, detected by absence of keel.

COMPOSITION.—The active principle which is contained in the rtex is called **senegin** or polygalic acid. It appears to be iden-al with saponin obtained from *Saponaria officinalis* and *Quillaia ponaria* (p. 918), which is a glucoside splitting up when boiled to grape-sugar and sapogenin. It is a white powder, easily luble in hot water and alcohol, forming a soapy emulsion when ixed with boiling water even in small quantities.

PREPARATIONS.

B.P.	DOSE.
Infusum Senegæ (1 in 20 for half-an-hour)	1–2 fl. oz.
Tinctura Senegæ	½–2 fl. dr.

PREPARATIONS—*continued.*

U.S.P.	DOSE.
Abstractum Senegæ	5–10 gr. (0·3–0·6 gm.)
Abstractum Senegæ Fluidum	10–20 min. (0·6–1·25 c.c.)
Syrupus Senegæ	1–2 fl. dr. (3·75–7·5 c.c.)
Syrupus Scillæ Compositus	For children 10 min. to 1 fl. dr. (0·6–3·75 c
	Expectorant for adults 20–30 min. (1·25–1·9

ACTION AND USE.—It is employed as a **stimulating expec rant**, diuretic, and diaphoretic. The indications for its admi tration as an expectorant are when the power to expectorat small, but the quantity of expectoration is abnormally large, it is more or less purulent in character, as in the second stag acute bronchial catarrh, or pneumonia in the stage of resolut When the expectoration is tough and scanty, senega is of l use.

It is also used in chronic pneumonia, and chronic bronch and in dropsy dependent on renal disease. It is usually combi with other expectorants and diuretics. Its taste is to many disagreeable, but spirit of chloroform both makes it more ag able and tends to lessen cough. It has been recommende palpitation due to **aortic disease** (pp. 316 and 317), and als amenorrhœa. (*Vide* also p. 919.)

SUB-ORDER.—**KRAMERIÆ.**

Krameriæ Radix, B.P.; Krameria, U.S.P. RHATANY R The dried root of (1) Peruvian Rhatany, *Krameria triandr* of (2) Savanilla Rhatany, *Krameria Ixina* (*Krameria tomento*

CHARACTERS.—Peruvian rhatany is about an inch thick, knotty above branched or branched below; the branches are long, often broken or reddish-brown and rough externally, reddish-yellow internally, with a re separated bark.

The root of *Krameria tomentosa* (Savanilla Rhatany) is less knotty more slender, and has dark purplish-brown, firmly adherent bark.

The bark of both kinds is strongly astringent, and when chewed t the saliva red, but has no marked odour.

COMPOSITION.—The bark contains about 20 per cent. of a of tannin called **ratanhia-tannic acid**, a red matter, **ratan red**, and a neutral substance, **ratanhin.**

PREPARATIONS.

B.P.	DOSE.
Extractum Krameriæ	5–20 gr.
Infusum „ (1 oz. to 1 pint)	1–2 fl. oz.
Pulvis Catechu Compositus	20-40 gr.
Tinctura Krameriæ	½–2 fl. dr.

U.S.P.			
Extractum Krameriæ			5–20 grs. (0·3–1·3 gm.)
„	„	Fluidum	5 min.–1 fl. dr. (0·3–3·75 c.
Syrupus	„		1 fl. oz. (30 c.c.)
Tinctura	„		½–2 fl. dr. (1·9–7·5 c.c.)
Trochisci	„		ad lib.

ACTION.—It is strongly **astringent.**

USES.—The powder is used as a dentifrice when the gums are spongy and bleed easily. The infusion or tincture is employed in bleeding from the nose, mercurial affections of the mouth, relaxed sore-throat, leucorrhœa, prolapsus ani. Internally it is given in diarrhœa, and hæmorrhage from the kidneys or genito-urinary passages.

GUTTIFERÆ.

Cambogia, B. and U.S.P. GAMBOGE.—A gum resin obtained from *Garcinia Hanburii* (*Garcinia Morella*, var. *pedicellata*). Imported from Siam.

CHARACTERS.—In cylindrical pieces, sometimes hollow in the centre, 1 or 2 inches in diameter, breaking easily with a smooth conchoidal glistening fracture; colour tawny, changing to yellow when it is rubbed with water; taste acrid; powder, bright yellow.

PROPERTIES AND COMPOSITION.—Contains a resin, **gambogic acid**, and a **soluble gum**, so that it forms an emulsion with water.

ADULTERATION.—Starch fraudulently added.

TEST.—An emulsion made with boiling water, and cooled, does not become green with the solution of iodine.

DOSE.—1–4 grs.

PREPARATION.

B.P.	DOSE.
Pilula Cambogiæ Composita (*vide* p. 522)	5–10 gr.
U.S.P.	
Pilulæ Catharticæ Compositæ (*vide* p. 523)	1–3 pills.

ACTION AND USE.—It is a **drastic hydragogue purgative**, and in large doses causes violent irritation of the alimentary canal, with vomiting and griping. It is used in combination with other purgatives as a derivative in cerebral affections, also with cream of tartar in dropsies. It has been used as an **anthelmintic.**

TERNSTRŒMIACEÆ.

Thea. TEA. Not officinal.—The dried leaves of *Thea sinensis*. China, Assam, Ceylon, &c.

CHARACTERS.—Both green and black tea are prepared from the same species of thea. Green teas are obtained by drying the freshly-gathered leaves on a hot iron plate until they shrivel. Black teas are obtained by allowing the leaves to lie in heaps and undergo a kind of fermentation before drying them.

COMPOSITION.—They contain **theine**, a **volatile oil**, and **tannin.**

ACTION.—The action probably depends partly on the theine and partly on the volatile oil they contain. Both green and

black teas are powerful **cerebral stimulants.** They render mental faculties more active and tend to prevent sleep. Gr tea is much more powerful than black, and its admixture w black is sometimes the cause of **sleeplessness** in persons v have thus taken it unconsciously. In some persons it produ giddiness, restlessness, and such severe muscular trembling t the hand shakes violently. A quantity of tea eaten by a ho caused great excitement, and probably anæsthesia, as the anir killed itself by dashing its head against a stone. Both green a black teas are apt to cause **indigestion.** This is probably d in some measure at least, to the tannin they contain. Tea mi with gastric juice lessens its power of digesting fresh meat, not of digesting smoked meat. This is probably due to tannin hardening the soft fibre of fresh meat, but leaving comparatively hard fibre of dried meat, ham, &c. unchang To avoid getting much tannin it is advisable not to let the stand long on the leaves, but pour it off quickly, so that volatile oil which gives the aroma only is extracted.

USE.—As a cerebral stimulant to relieve drowsiness a headache.

Caffeina, B. and U.S.P. CAFFEINE (THEINE (?), GUARANIN $C_8H_{10}N_4O_2.H_2O$; 112.

An alkaloid (B.P.), or proximate principle of feeble alkaloi power (U.S.P.), generally prepared from the dried leaves *Camellia Thea*, or from the dried seeds of *Coffea arabica* (N Ord., *Rubiaceæ*); or from the Guarana, and occurring also other plants.

CHARACTERS.—Colourless, silky, inodorous, acicular crystals.

PREPARATION.—By evaporating aqueous infusions from which astring and colouring matters have been removed.

SOLUBILITY.—Soluble in 80 parts of cold water, the solution havin faintly bitter taste and being neutral to litmus. More soluble in boil water and in rectified spirit, and very soluble in chloroform; sparin soluble in ether.

REACTIONS.—Above 212° F. they melt and volatilise without decompositi Treated with a crystal of chlorate of potassium and a few drops of hyd chloric acid, and the mixture evaporated to dryness in a porcelain dis reddish residue results, which becomes purple when moistened with ammo In an aqueous solution of the alkaloid, tannic acid gives a white precipit soluble in excess of the reagent.

DOSE.—1 to 5 grains.

	PREPARATION.
B.P.	DOSE.
Caffeinæ Citras	2–10 grains.

B.P. Caffeinæ Citras. CITRATE OF CAFFEINE.—$C_8H_{10}N_4$ $H_3C_6H_5O_7$. A weak compound of caffeine and citric acid.

CHARACTERS.—A white inodorous powder with an acid and faintly bit taste and an acid reaction on litmus.

PREPARATION.—Dissolve citric acid (1) in hot water (2), add caffeine evaporate to dryness, and reduce to a fine powder.

SOLUBILITY.—It is soluble in a mixture of two parts of chloroform and one part of rectified spirit.

REACTIONS.—With a little water it forms a clear syrupy solution, which on dilution yields a white precipitate of caffeine that redissolves when ten parts of water have been added.

DOSE.—1 to 5 grains. Caffeine is very soluble in solutions of benzoate, cinnamate, or salicylate of sodium. By using these as solvents concentrated solutions of caffeine can be made for hypodermic injection. Caffeine 20 gr., salicylate of sodium 17½ gr., water 1 fl. dr. makes a non-irritating solution containing 1 gr. of caffeine in 3 min., but stronger solutions may be made if required.

ACTION.—Caffeine causes at first stimulation and subsequently paralysis of **nerve-centres** in the cerebrum, cord, and medulla. It has also a marked action on **muscular fibre**, both voluntary and involuntary. In large doses it acts as a gastro-intestinal irritant. Its action on **frogs** varies according to the species. In *rana temporaria* it produces a rigid condition of the muscles resembling rigor mortis, especially when locally applied to them. In *rana esculenta* this action on the muscles is slight, and the chief symptom is tetanus, which, like that of strychnine, depends on the action of the drug on the spinal cord. This is followed by paralysis (of voluntary movement) and then of reflex action. The action of theine is said by Mays to differ from that of caffeine; it affects in the frog chiefly sensation, which it paralyses, and causes tetanus, while caffeine does not.[1] In **warm-blooded animals** also caffeine (? theine) produces tetanic convulsions, which may be arrested by artificial respiration, and death frequently prevented even from a very large dose. Morphine lessens the convulsions but does not prevent death.

From its stimulant action on the **brain**, doses of 2–8 grains sometimes cause heaviness of the head, flashes of light before the eyes, singing in the ears, loss of sleep, great restlessness, and delirium.

Its stimulant action on the **medulla** and cardiac centres increases the **respiration** and pulse-rate and raises the **blood-pressure** in moderate doses. Large doses depress the respiration and pulse, and lower the blood-pressure. In man the **pulse**, after somewhat large doses, becomes very frequent, irregular, and intermittent. This effect occurs in some persons even after a single cup of coffee, but it is prevented in such cases by adding a little brandy to the coffee, as is usually done when coffee is taken without milk.

It appears sometimes to increase the **salivary** secretion. It has little action on the peristaltic movements of the **intestine**,

[1] Mays, *Therapeutic Gazette*, 1886, p. 587. Mays states that, commercially, theine and caffeine are considered identical, so that a specimen of so-called 'caffeine' may really be theine, or a mixture of the two alkaloids (*op. cit.*).

but it causes the intestinal veins to become much dilated, a appears to cause hæmorrhoids.

The **temperature** is not altered by small doses of caffei but is increased by large doses.

Caffeine acts as a **diuretic**, though not invariably so. diuretic action may partly depend upon its stimulant action the heart and vaso-motor centre, and consequent rise of blo pressure, but the contraction of vessels may be so great that diuresis takes place till the renal nerves are divided (p. 43 This diuretic action is also due in part to a stimulant action the cells of the urinary tubules, as Brackenridge, Schröder, a others have shown that it increases the excretion of urinary sol as well as the amount of water.

Uses.—It is used in headache, especially migraine and cases where the headache seems to be inside the head witho any external tenderness. As a diuretic it is especially useful cardiac dropsy, though it may be given also in cases of hepa dropsy. It acts as a diuretic even when the kidneys are diseas and is useful even in very advanced cardiac cases. It is b given alternately with digitalis or along with it.

MALVACEÆ.

U.S.P. Gossypii Radicis Cortex. Cotton Root Bark. The bark of the root *Gossypium herbaceum* and of other spec of gossypium.

Characters.—Thin flexible bands or quills, brownish-yellow outsi whitish and silky inside, no smell, taste faintly acrid and astringent.

Composition.—It contains a colourless **acid resin** becomi red on exposure.

Preparation.	dose.
Extractum Gossypii Radicis Fluidum	½–1 fl. dr. (1·9–3·75 c.c.)

Action and Uses.—It is said to cause contraction of t **uterus**, and is used instead of ergot. It may be given either the officinal fluid extract or as a decoction made by boiling 4 o of the bark in a quart of water down to a pint. Of this a win glassful (60 c.c.) is given every 20 or 30 minutes.

U.S.P. Oleum Gossypii Seminis. Cotton Seed Oil.— fixed oil, expressed from the seed of *Gossypium herbaceum* and other species of gossypium, and subsequently purified.

Characters.—A bright, pale yellow, oily liquid, odourless, having a bla nut-like taste and a neutral reaction. Sp. gr. 0·920 to 0·930.

Solubility.—It is only slightly soluble in alcohol, but readily so ether.

Reactions.—When cooled to near 2° C. (35·6° F.) it begins to conge Concentrated sulphuric acid instantly renders it dark reddish-brown.

Uses.—It is a bland oil very much like olive oil, and answe perfectly well most purposes for which olive oil is generally use

except for making lead plaster. A great deal of the oil exported from France and Italy under the name of olive oil is really cotton-seed oil, either alone or mixed with a proportion of olive oil. Eighty-eight per cent. of the cotton-seed oil exported from New Orleans in 1880 was sent to the Mediterranean.

OFFICINAL PREPARATIONS.

U.S.P.

Linimentum Ammoniæ (p. 517).
„ Calcis (p. 517).
„ Camphoræ (p. 517).
„ Plumbi Subacetatis (p. 517).

Gossypium, B. and U.S.P. COTTON. COTTON-WOOL. (Purified Cotton. Absorbent Cotton.)—The hairs of the seed of *Gossypium barbadense* (*G. herbaceum*, U.S.P.) and other species, freed from adhering impurities and deprived of fatty matter.

PREPARATION.—It is made by boiling the raw cotton in a dilute alkaline solution, such as a 5 per cent. solution of caustic potash or soda. The alkali unites with the fatty matter of the cotton to form a soap, which is removed by repeated washings, in the course of which chlorinated lime and dilute hydrochloric acid are used as well as water.

CHARACTERS.—In white soft filaments, each consisting of an elongated tubular cell, and when examined under the microscope appearing as a flattened twisted band with slightly thickened rounded edges; inodorous and tasteless.

TEST.—When thrown upon water it should immediately absorb the latter and sink, and the water should not acquire either an acid (no hydrochloric acid) or alkaline reaction.

PREPARATIONS.

B.P.	U.S.P.
Pyroxylin (Gun Cotton).	Pyroxylinum (Gun Cotton).

USES.—Cotton wool is employed as a local application to the skin in cases of burns and erysipelas, to exclude external irritation and protect the part from cold. Cotton wool is also used to surround gouty or rheumatic joints.

A pledget of cotton wool placed in the ears tends to prevent sore-throat. The explanation of this seems to be that catarrh may result reflexly from irritation of the auricular branch of the vagus. (Cf. Rossbach's experiments, p. 252.)

When subjected to heat, so as to destroy any adherent germs, it is used in cultivation experiments on bacteria (p. 90) to plug the orifice of the test-tubes and prevent the accidental entrance of germs. With a somewhat similar object it has been used as a dressing to wounds, from which it excludes the germs which might cause pyæmia, erysipelas, &c. It may be impregnated with various antiseptics and deodorising substances, such as iodine, picric acid, salicylic acid, iodoform, or benzoic acid. Some of these form useful applications to the os uteri, to destroy fœtor and induce healthy action. The dressing of wounds after operation by salicylic acid or iodoform wool has almost completely superseded the Listerian gauze dressing (p. 816).

Pyroxylin, B.P.; Pyroxylinum, U.S.P. GUN COTTON. Prepared by the action of sulphuric and nitric acids on cotton.

TEST.—Readily soluble in a mixture of ether and rectified spirit: leaves no residue when exploded by heat.

USE.—To prepare collodium (collodion), B. and U.S.P.

Collodium. B. and U.S.P. COLLODION. A solution of pyroxylin in ether and alcohol.

CHARACTERS. — A colourless, highly inflammable liquid with ethereal odour, which dries rapidly on exposure to the air, and leaves a thin transparent film, insoluble in water or rectified spirit. The great inflammability of its vapour must be carefully remembered. After successfully completing the operation of ovariotomy, a surgeon covered the wound with a layer of collodion. In order to inspect it more closely he brought a light near, when the ethereal vapour caught fire, and the patient died from the effects of the burns which she received (Binz).

PREPARATIONS.

B.P.	U.S.P.
Collodium Flexile	Collodium cum Cantharide.
„ Vesicans.	„ Flexile.
	„ Stypticum.

B. and U.S.P. Collodium Flexile. FLEXIBLE COLLODION. Collodion mixed with Canada balsam and castor oil.

USES.—Collodion applied to the skin acts both as a protective and also, through its contraction, exerts a gentle pressure on the part, and is hence applied to cut surfaces, chapped nipples, and to check hæmorrhage from leech-bites. The flexible collodion does not crack, and therefore is more useful as a protective, but it exerts less pressure than ordinary collodion.

B.P. Collodium Vesicans. CANTHARIDAL COLLODION (blistering liquid 20, pyroxylin 1).

U.S.P. Collodium cum Cantharide. CANTHARIDAL COLLODION.

PREPARATION.—By dissolving a chloroform extract of cantharides in flexible collodion.

ACTION.—When painted on the skin it acts as a rapid and powerful vesicant. If covered immediately with oiled silk, so as to prevent the evaporation of the ether, it is said to act more rapidly.

USES.—*Vide* Cantharides.

U.S.P. Collodium Stypticum. STYPTIC COLLODION.

PREPARATION.—By dissolving tannin in a mixture of alcohol, ether, and collodion (20 parts tannin in 100).

USES.—To stop bleeding from leech-bites, abrasions, and wounds. When painted over the bleeding surface the tannin coagulates the blood and lymph; and this, with the collodion, forms a film over the surface which prevents further bleeding and

protects the raw surface from exposure to air or from accidental irritation.

U.S.P. Althæa. ALTHÆA. [MARSHMALLOW.]—The root of *Althæa officinalis*.

CHARACTERS.—In cylindrical or somewhat conical pieces, from three to six inches (7 to 15 centimetres) long, about half an inch (12 millimetres) in diameter, deeply wrinkled; deprived of the brown, corky layer and small radicles; externally white, marked with a number of circular spots, and of a somewhat hairy appearance from the loosened bast-fibres; internally whitish and fleshy. It breaks with a short, granular and mealy fracture, has a faint aromatic odour, and a sweetish, mucilaginous taste.

PREPARATION.

	DOSE.
Syrupus Althææ	1–4 fl. dr.

COMPOSITION.—It contains some 35 per cent. each of **vegetable mucin** and **starch.**

USES.—It is bland and unirritating, and a useful **demulcent** in sore-throat, coughs, or intestinal irritation. An ointment made by boiling the cut fresh leaves with lard for half an hour, and then straining, has proved successful in palmar psoriasis after other means failed.[1]

STERCULIACEÆ, or BYTTNERIACEÆ.

Oleum Theobromatis, B.P.; Oleum Theobromæ, U.S.P.

OIL OF THEOBROMA; CACAO BUTTER.—A concrete oil obtained by expression and heat from the ground seeds of *Theobroma Cacao*.

COMPOSITION.—Consists chiefly of **stearin** and **olein.**

CHARACTERS.—Of the consistency of tallow; colour yellowish-white; odour like chocolate; taste bland and agreeable; reaction neutral. Does not become rancid from exposure to the air. Melts at 30°–35° C. (86°–95° F.).

ADULTERATIONS.—Paraffin, wax, tallow, stearin, &c.

TESTS.—If 2 parts of it be dissolved in 4 parts of ether in a test-tube, by immersing the tube in water at 17° C. (63° F.), and if this be afterwards plunged into water at 0° C. (32° F.), the mixture should not become turbid, nor separate a granular deposit in less than 3 minutes; and if the mixture, after congealing, be exposed to a temperature of 15° C. (59° F.), it should gradually become entirely clear. (Absence of impurities mentioned above.)

PREPARATIONS.

B.P.	U.S.P.
Suppositoria Acidi Tannici.	For suppositories of various kinds, each weighing 15 gr. or 1 gm.
„ Hydrargyri.	
„ Iodoformi.	
„ Morphinæ.	
„ Plumbi Composita.	

USES.—As a basis for suppositories. Also as a non-irritant application to the skin.

[1] Berry, *Practitioner*, vol. xxxi., p. 346.

CHAPTER XXXII.

PHANEROGAMÆ—(*continued*).

Class I.—DICOTYLEDONES POLYPETALÆ.

Sub-Class II.—DISCIFLORÆ.

LINEÆ.

Lini Semina, B.P.; Linum, U.S.P. Linseed, B. and U.S. **Flax Seed, U.S.P.**—The dried ripe seeds of *Linum usitatissimu* It is grown in Britain.

Characters.—About one-sixth of an inch long, oval, pointed, flatten smooth, shining, brown externally, yellowish-white within.

Composition. — The covering of the seeds contains mu mucilage, and the seed itself contains nearly one-third of weight of **oil**. The oil is obtained by expression, and the r maining cake when powdered forms linseed-meal.

Preparations.

B.P.	dose.	U.S.P.
Farina Lini		Oleum Lini.
Infusum „	ad lib.	
Oleum „		

B.P. Infusum Lini. Linseed Tea.—Infuse 150 grains of linseed, with grains of dried liquorice-root in No. 20 powder, in 10 ounces of boiling water i covered vessel for 2 hours and strain.

Action and Uses.—Linseed tea is a most useful **demulcent** coughs depending in whole or in part on irritation of the phary and upper part of the respiratory passages. It may be kept war all night in a baby's food-warmer, and a sip taken whenever t patient awakes. This often prevents troublesome paroxysms coughing, and enables the patient to obtain a fair night's re Internally it is used as a demulcent drink in enteritis, diarrhœ dysentery, catarrh, and irritation of the urinary organs, also phosphorus-poisoning.

B.P. Lini Farina. Linseed Meal.—Linseed reduced powder. It is used not only in the cataplasma lini but also the cataplasma carbonis, conii, sinapis, and sodæ chlorinatæ.

B.P. Cataplasma Lini. LINSEED POULTICE.—Mix a quarter of a pound (about 4 tablespoonfuls) of linseed-meal gradually with half a pint of boiling water with constant stirring.

USES.—Linseed meal forms an excellent vehicle for applying warmth and moisture, and is used in the form of poultices in inflammation of both superficial and deep-seated parts (p. 468).

Oleum Lini, B. and U.S.P. LINSEED OIL. OIL OF FLAX SEED, U.S.P.—A fixed oil expressed without heat from linseed.

CHARACTERS.—Viscid, yellow, with a faint odour, and oleaginous taste. It thickens, and finally solidifies on exposure to air.

USES.—It is sometimes applied as a soothing application to burns, scalds, and eczematous eruptions, either alone or with lime-water (p. 649). It is sometimes added to purgative enemata, and has been recommended as a cure for piles in the dose of two ounces of the fresh oil morning and evening.[1]

SUB-ORDER.—ERYTHROXYLEÆ.

Coca, B.P.; Erythroxylon, U.S.P. COCA ERYTHROXYLON. [CUCA.]—The dried leaves of *Erythroxylon Coca*.

CHARACTERS.—Shortly stalked, oval or lanceolate, of varying thickness, one to two inches or more in length, entire, usually blunt and emarginate, quite smooth; midrib prominent, with numerous faint freely anastomosing lateral veins, and on each side of the midrib a curved line extends from base to apex; green above, somewhat paler beneath. In commercial specimens the leaves are more or less broken, and frequently yellowish-green, yellowish-brown, or brown, and in rare cases the curved lines are indistinguishable. Odour faintly tea-like, especially when bruised; taste somewhat bitter and aromatic.

DOSE.—½ to 2 drachms.

PREPARATIONS.

B.P.	DOSE.
Cocainæ Hydrochloras	$\frac{1}{5}$–1 gr.
Extractum Cocæ Liquidum (1 in 1)	½–2 fl. dr.

U.S.P.	
Extractum Erythroxyli Fluidum	1–4 fl. dr.

COMPOSITION.—This drug contains the alkaloids **cocaine, ecgonine**, and **hygrine**, and a volatile constituent which gives a pleasant fragrance to the fresh leaves. Different specimens of the leaves vary greatly in their strength. Leaves which have been long kept contain less of the active alkaloid than the fresh leaves.

B.P. Cocainæ Hydrochloras. HYDROCHLORATE OF COCAINE. $C_{17}H_{21}NO_4.HCl$.

The hydrochlorate of an alkaloid obtained from the leaves of *Erythroxylon Coca*.

[1] *United States Dispensatory*, p. 1017.

PREPARATION.—It may be obtained by agitating with ether an aque solution of an acidulated alcoholic extract, made alkaline with carbonate sodium; separating and evaporating the ethereal liquid, purifying the prod by repeating the treatment with acidulated water, carbonate of sodium, a ether; decolourising; neutralising with hydrochloric acid, and recrystallisi

CHARACTERS.—In almost colourless acicular crystals crystalline powder. The solution in water has a bitter tas and produces on the tongue a tingling sensation followed numbness.

SOLUBILITY.—It is readily soluble in water, alcohol, and ether.

REACTIONS.—Its solution gives a yellow precipitate with chloride of gol and a white precipitate with carbonate of ammonium, soluble in excess of t reagent. It dissolves without colour in cold concentrated acids, but ch with hot sulphuric acid. The solution yields little or no cloudiness w chloride of barium or oxalate of ammonium. Ignited in the air it bur without residue.

DOSE.—$\frac{1}{5}$ to 1 grain.

PREPARATION. **B.P.**

Lamellæ Cocainæ. Discs of cocaine (each contains $\frac{1}{200}$th grain of hyd chlorate of cocaine, p. 515).

ACTION.—Cocaine is a powerful **local anæsthetic.** Wh applied to the tongue it destroys both taste and tactile sen bility, so that salt and sugar cannot be distinguished, nor t prick of a pin felt. In the eye it causes local anæsthesia alo with dilatation of the pupil, paralysis of accommodation, slig lacrimation, and enlargement of the palpebral fissure.[1] Wh injected into the back of the orbit it causes protrusion of the ey ball. Its effects appear to be due to stimulation of the periphe ends of the sympathetic (*vide* p. 226). Subcutaneous injection al produces local anæsthesia at the point of application, so that su sequent irritation at that spot produces no sensation in man a no reflex action in animals. When taken **internally** it appears have, in small doses, a stimulant, and, in large doses, a paralysi action on the **nerve-centres** somewhat like that of caffeine. affects first the cerebral hemispheres, next the medulla, and aft wards the spinal cord. In small doses it is said to **lessen fatigu** and enable the Indians in Peru to make long marches; and similar result has been obtained in trials upon soldiers Germany. **Larger doses** cause fulness in the head, wearine slight deafness, loss of memory, and inability to control ide It appears sometimes to cause restlessness, singing in the ea giddiness, headache, and delirium.

In animals large doses appear to affect specially the **sem circular canals**, possibly by an anæsthetic action upon t nerves connected with them. This is shown by constant mov ment of the head in mammals, disturbances of equilibrium, lo

[1] Jessop, *Practitioner*, January 1885.

of co-ordination, and rotatory convulsions and opisthotonos. The **convulsions** are of cerebral origin (p. 188), and cease when the spinal cord is divided. The motor columns of the **spinal cord** appear to be unaffected, but the sensory columns are paralysed. In its action on respiration and circulation cocaine, to a certain extent, resembles atropine, and it does so also in its action on the pupils, intestinal movements, and salivary and sweat glands. The **respiration** is greatly increased at first, afterwards diminished, and death occurs from respiratory paralysis. Small doses quicken the **pulse** and raise the **blood-pressure**. Large doses slow the pulse and lower the blood-pressure. The quickness of the pulse appears to be due to paralysis of the vagus, and the action of cocaine on both pulse and blood-pressure is very like that of atropine. Small doses increase, large ones paralyse, the intestinal movements. The secretion of **saliva** and **sweat** is diminished. The **urine** does not appear to be affected. The **temperature** is generally raised.

USES.—The expectations of the practical utility of cocaine, founded on a knowledge of its physiological action, which Rossbach[1] expressed have been completely fulfilled, and it now bids fair to replace as a local anæsthetic the use of chloroform in many minor operations. Its local anæsthetic action was first observed by Niemann. Its actual introduction into practice we owe to Koller. A 4 per cent. solution dropped into the eye is sufficient to produce local anæsthesia, so that operations for cataract or squint can be readily performed, and foreign bodies extracted from the eye under its influence.[2] A 20 per cent. solution applied once or twice to the nasal mucous membrane at intervals of three or four minutes causes such complete anæsthesia that the application of the galvano-cautery is not felt. A similar effect is produced on the soft palate and larynx, and the solution may be applied to facilitate the use of the laryngoscope and lessen pain and spasm in operations on the larynx. It has been applied with benefit to the interior of the nose in acute coryza, nasal polypus, and hay fever. It is useful in producing local anæsthesia of the uterus and rectum in operations on these parts; in vaginismus and in pruritus of the anus and vulva. Internally cocaine or coca is useful as a tonic, especially in debility with nervousness, and in mental diseases accompanied by depression. It may be given in the form of the fluid extract either alone or with a glass of wine. A non-officinal wine made from the leaves is also a useful tonic.

---

[1] Nothnagel and Rossbach, *Arzneimittellehre*, 5th edition.

[2] In consequence of the readiness with which solutions of cocaine undergo decomposition, it is best to add a trace of boric acid ($\frac{1}{2}$ per cent.) to them.

ZYGOPHYLLEÆ.

Guaiaci Lignum, B. and U.S.P. GUAIACUM WOOD.—Th heart-wood of *Guaiacum officinale* and *G. sanctum*. St. Doming and Jamaica. It should be deprived of the sapwood and re duced to chips, raspings, or shavings.

CHARACTERS.—The wood is known as *Lignum vitæ*, occurs in logs, and very hard and heavy. The alburnum, or sapwood, is yellow in colour, th duramen, or heart-wood, is dark greenish-brown, which should become dar blue-green on the addition of nitric acid.

COMPOSITION.—Contains **resin**, chiefly in the heart-wood.

PREPARATION.

B.P.

	DOSE.
Decoctum Sarsæ Compositum (p. 1052)	2–10 fl. oz.

U.S.P.

Decoctum Sarsaparillæ Compositum	4–6 fl. oz. (200–300 gm.)

Guaiaci Resina, B. and U.S.P. GUAIACUM RESIN.—Th resin of *Guaiacum officinale* or *G. sanctum*.

PREPARATION.—Obtained from the stem by natural exudation, by in cisions, or by heat.

CHARACTERS.—In masses of a greenish-brown or reddish-brown colour fractured surface resinous, translucent at the edges, where the greenish colou is usually well-marked, and serves to distinguish this from other resins. solution in rectified spirit strikes a clear blue colour when applied to th inner surface of a paring of raw potato (p. 68), or on the addition of tinctu of perchloride of iron. Powder greyish, turning green on exposure to air.

COMPOSITION.—It contains several resinous acids, **guaiaconic guaiaretic**, and **guaiacic acids**; these are soluble in alkalis an are precipitated on neutralisation.

DOSE.—10 to 30 gr.

PREPARATIONS.

B.P.

	DOSE.
Mistura Guaiaci	1–1½ fl. oz.
Tinctura Guaiaci Ammoniata	½–1 fl. dr.
Pilula Hydrargyri Subchloridi Composita (*v.* p. 522)	5–10 gr.

U.S.P.

Tinctura Guaiaci	1–3 fl. dr. (4–12 c.c.)
,, ,, Ammoniata	1–2 fl. dr. (4–8 c.c.)
Pilulæ Antimonii Compositæ (*v.* p. 523)	1–2 pills.

B.P. Mistura Guaiaci. GUAIACUM MIXTURE.—Guaiacum, ½ oz.; refine sugar, ½ oz.; gum acacia, ¼ oz.; cinnamon water, 1 pint.

Tinctura Guaiaci Ammoniata, B. and U.S.P. AMMONIATED TINCTURE O GUAIACUM.—Guaiacum resin, 4 oz.; aromatic spirit of ammonia, to 1 pint (B.P. Guaiacum, 20; aromatic spirit of ammonia, 100 (U.S.P.).

ACTION.—It causes a burning sensation in the mouth an throat when given in small doses. Large doses cause vomitin and purging. When absorbed it acts as a stimulant, an altera tive, and a diuretic.

USES.—It is employed in the treatment of tonsillitis, Mistur

Guaiaci being in my experience more efficacious than the ammoniated tincture. Others prefer the simple powder, as it remains longer applied to the tonsils and pharynx, and it may be given in lozenges containing 2 grains each, and flavoured with red currant. It is also used in chronic rheumatism. It has been used in the treatment of gout and syphilitic periosteal diseases.

GERANIACEÆ.

U.S.P. Geranium. GERANIUM [CRANESBILL]. The rhizome of *Geranium maculatum*.

CHARACTERS.—Horizontal, cylindrical, two to three inches (5 to 7 centimetres) long; half an inch (12 millimetres) or less thick; tuberculated, longitudinally wrinkled, dark brown; fracture short pale red-brown; bark thin; wood-wedges yellowish, small, forming a circle near the cambium line; medullary rays broad; central pith large; rootlets thin, fragile; inodorous; taste astringent.

OFFICINAL PREPARATION.

	DOSE.
Extractum Geranii Fluidum	½ fl. dr. to 1 fl. dr.

COMPOSITION.—It contains a considerable amount of **tannic** and **gallic** acids.

USES.—It is a mild and not disagreeable **astringent**, especially useful for children. It is used internally for diarrhœa, and is employed also as an astringent gargle in sore-throat and as an injection in gonorrhœa and gleet.

RUTACEÆ.

SUB-ORDER I.—RUTEÆ.

Oleum Rutæ, B. and U.S.P. OIL OF RUE.—A volatile oil distilled from the fresh herb of *Ruta graveolens*.

CHARACTERS.—Pale yellow when recent; odour strong and disagreeable; taste, bitter, acrid.

COMPOSITION.—Consists of a **hydrocarbon** and an oil containing **oxygen**.

DOSE.—1 to 4 min. (0·06–0·3 c.c.)

USES.—Externally it is **rubefacient**, internally it is stimulant, **antispasmodic, emmenagogue,** and carminative; used in amenorrhœa, hysteria, convulsions, and flatulence.



FIG. 182.—Cusparia, half the natural size.

B.P. Cuspariæ Cortex. CUSPARIA, OR ANGOSTURA BARK.—The dried bark of *Galipea Cusparia*, the Angostura bark tree. Tropical America.

CHARACTERS.—Consists of flattish pieces or quills, grey outside, li brown inside; several inches long, about an inch in breadth, and one-eigh of an inch thick. Generally readily recognised by one edge being obliquely or feathered, from the oblique introduction of the knife by wh the bark has been detached. Odour, peculiar; taste, bitter.

COMPOSITION.—A bitter substance, **cusparine**, and so **volatile oil.**

ADULTERATION.—The bark of *Strychnos nux vomica.*

TESTS.—Nitric acid gives a blood-red colour when applied to the in surface of the false bark from the brucine present in it, but gives a blui black colour with the true bark.

B.P.	DOSE.
Infusum Cuspariæ (1 in 20 at 120° F. for 1 hour)	1–2 fl. oz.

ACTION AND USE.—Cusparia is an **aromatic bitter ton** and is used in cases of atonic dyspepsia and in cases of we digestion, especially during convalescence from acute diseases.

SUB-ORDER II.—DIOSMEÆ.

Buchu Folia, B.P.; Buchu, U.S.P. BUCHU LEAV B.P.; BUCHU, U.S.P.—The dried leaves of (1) *Barosma betuli* (2) *Barosma crenulata*, (3) *Barosma serratifolia*. Cape of Go Hope.



FIG. 183.—Barosma betulina.



FIG. 184.—Barosma crenulata.



FIG. 185.—Barosma serrati

CHARACTERS.—Smooth, marked with pellucid dots at the indentati and apex; having a powerful, somewhat mint-like odour, and a warm c phoraceous taste. *B. betulina.*—Obovate, with a recurved, truncated a and sharp cartilaginous spreading teeth. *B. crenulata.*—Oval-lanceol obtuse, minutely crenated. *B. serratifolia.*—Narrow linear-lanceolate, ta ing at each end, sharply and finely serrated.

COMPOSITION.—The leaves contain a **volatile oil** in the vi which appear as dots on the leaves, and a bitter substance.

PREPARATIONS.

B.P.	DOSE.
Infusum Buchu (1 in 20 for ½-hour)	1–4 fl. oz.
Tinctura „	1–2 fl. dr.
U.S.P.	
Extractum Buchu Fluidum	20–45 min.

ACTION AND USE.—Buchu is slightly **tonic.** It is also diur and diaphoretic. Its chief use is as a **stimulant** to the muc membrane of the **bladder** in cases of vesical catarrh and irr tion. It is also used with other drugs as an **expectorant**

hronic bronchitis. It is used in South Africa, in doses of 20 rains of the powdered leaves, in the treatment of diarrhœa and ysentery.

Sub-Order III.—XANTHOXYLINÆ.

U.S.P. Xanthoxylum. Xanthoxylum. Prickly Ash.—The bark of *Xanthoxylum fraxineum*, and of *Xanthoxylum carolinianum*.

Characters.—*Xanthoxylum fraxineum* is in curved or quilled fragments, about $\frac{1}{25}$th inch thick; outer surface brownish-grey, with whitish patches and minute, black dots; inner surface whitish, smooth, inodorous; bitterish, very pungent.

Xanthoxylum carolinianum resembles the preceding, but is about $\frac{1}{12}$th inch thick, and is marked by many conical, corky projections, and stout, brown spines.

Preparation.

	Dose.
Extractum Xanthoxyli Fluidum	30–60 min.

Composition.—It contains a **volatile oil, resins,** and possibly berberine.

Action and Uses.—Its action seems to be that of an **aromatic** and somewhat irritant **bitter,** somewhat resembling mezereum and guaiac. Like these drugs it is used in rheumatism. The bark is chewed to relieve toothache, and to aid recovery in palsy affecting the tongue.

Jaborandi, B.P.; Pilocarpus, U.S.P. Pilocarpus. Jaborandi.—The dried leaflets of *Pilocarpus pennatifolius*.

Characters.—About four inches (ten centimetres) long, short-stalked, oval or ovate-oblong, entire and slightly revolute at the margin, obtuse and emarginate, unequal at the base; coriaceous pellucid-punctate, mostly smooth; smell, when bruised, slightly aromatic; taste, somewhat bitter and aromatic at first, but subsequently pungent and increasing the flow of saliva.

Composition.—The leaves contain a **volatile oil** and two alkaloids, **pilocarpine** and **jaborine.**

Preparation.

B.P.	Dose.
Extractum Jaborandi	2–10 grs.
Infusum „ (1 in 20 for $\frac{1}{2}$-hour)	1–2 fl. oz.
Pilocarpinæ Nitras	$\frac{1}{20}$–$\frac{1}{2}$ gr.
Tinctura Jaborandi	$\frac{1}{2}$–1 fl. dr.

U.S.P.

Extractum Pilocarpi Fluidum	5–60 min.

B.P. Pilocarpinæ Nitras. Nitrate of Pilocarpine. $C_{11}H_{16}N_2O_2.HNO_3$.—The nitrate of an alkaloid obtained from extract of jaborandi.

Preparation.—By shaking the extract with chloroform and a little alkali, evaporating the chloroformic solution, neutralising the product with nitric acid and purifying by recrystallisation.

CHARACTERS.—In white crystalline powder, or in acicular crystals.
SOLUBILITY.—Soluble in eight or nine parts of water at common tempe tures, slightly soluble in cold, freely soluble in hot rectified spirit.
REACTIONS.—Strong sulphuric acid forms with it a yellowish solution whi on the addition of bichromate of potassium, gradually acquires an emera green colour. It leaves no ash when burned with free access of air. causes contraction of the pupil of the eye.

U.S.P. Pilocarpinæ Hydrochloras. HYDROCHLORATE PILOCARPINE.—The hydrochlorate of an alkaloid prepared fr Pilocarpus. It should be kept in small, well-stoppered vials.

CHARACTERS.—Minute, white crystals, deliquescent, odourless, havin faintly bitter taste, and a neutral reaction.
SOLUBILITY.—Very soluble in water and in alcohol, but almost insolu in ether or chloroform.

DOSE.— $\frac{1}{20}$ to $\frac{1}{2}$ gr. internally or by subcutaneous injectio
USES.—Its action and uses are similar to those of Pilocarp

ACTION.—**Jaborine** has an action like that of atropine a antagonistic to that of pilocarpine. The amount of jaborine the leaves is insufficient to antagonise the pilocarpine, so th the leaves have an action like that of pilocarpine. It is probal that some discrepancies between the statements of differe observers regarding the action of pilocarpine may be due to t presence of more or less jaborine in the pilocarpine which th supposed to be pure.

Pilocarpine stimulates the peripheral terminations **efferent nerves** going to **glands,** and first stimulates and th paralyses the efferent nerves going to structures composed **involuntary muscular fibre.** In large doses it lessens but d not quite destroy the irritability of voluntary **muscle** and **mot nerves.**

It appears to have a certain action on the **nerve-centr** It produces in *Rana esculenta* convulsions like those of pic toxin. In *Rana temporaria* it only produces paralysis. Fr poisoned by it croak, when stroked, in the same way as wh the cerebrum is removed. In mammals it causes dyspn convulsive twitching and shivering, and movements of rotati (p. 215; cf. also Apomorphine). These may, however, be par due to the action of the drug upon the heart. It seems, ho ever, to stimulate the **centres** of the salivary and sweat glan as well as the peripheral terminations of the secreting nerves.

From its stimulating action on secreting nerves it produc enormous secretion of **saliva** from the submaxillary, sublingu and parotid glands, and enormous secretion of **sweat** from t sweat-glands, beginning either in the face or at the point subcutaneous injection, and extending over the whole surf of the body. It produces, though to a less extent, secretion **tears** from the lacrimal gland; of wax from the **ears**; of muc from the **nose** and from the **bronchial** mucous membrane;

astric juice from the glands of the **stomach**; probably of ntestinal juice from the **intestinal glands**, and of urine from ne **kidney**. The secretion of **milk** is sometimes but not lways increased. It does not appear to increase the secretion f **bile**.

Its stimulating action on nerves supplying **involuntary nuscular fibre** is observed in the eye, intestine, heart and essels, bladder, **uterus**, and spleen. By stimulating the ter- inations of the third nerve in the **eye** it causes contraction of ne pupil and spasm of accommodation, and indistinct vision. fter this passes off there may be dilatation of the pupil. By timulating the **intestinal ganglia** it causes increased peristalsis. y stimulating the vagus ends in the **heart** like nicotine, **large oses** of it cause the pulse to become slow in frogs and in ammals, and the blood-pressure to fall. In small doses its ffect is more complicated, as will be afterwards noticed. In **rger doses** it paralyses the **vagus** ends (A, Fig. 106, p. 313), ut not the inhibitory ganglia. By acting on the **bladder** it auses contraction, and may produce strangury and sometimes re- ntion. It causes contractions of the **uterus**, which, in rabbits, egin at the openings of the Fallopian tubes and proceed to the s uteri. This depends also on a peripheral action of the drug, nd is not arrested by destruction of the spinal cord. It causes ontraction of the **spleen** in man both in its normal condition nd when abnormally enlarged.

As **vomiting** is a complex movement demanding the co- peration of the abdominal muscles and diaphragm, it is evident hat it would not ensue merely from increased contraction of he gastric walls. Jaborandi appears, however, to irritate the tomach, and often causes nausea and vomiting; and so does ilocarpine, though to a less extent, even when subcutaneously jected.

It is probable that even when injected subcutaneously it is iminated by the mucous membrane of the stomach in the same ay as tartar emetic, morphine, atropine, quinine, and strych- ine, and that it thus acts as a local irritant to the gastric erves (Fig. 5, p. 39).

Its action on the **circulation** is a complicated one, as the irect effect of the drug on the heart and vessels is probably uch modified by the reflex action from the stomach, intestines, c., which have been stimulated by it. The **vessels** usually ecome much dilated at first, the carotids pulsating violently, he pulse becoming rapid, and a feeling of heat being perceived ver the body. When perspiration sets in there is sometimes feeling of cold and shivering. The blood-pressure usually falls little at first, with quicker pulse, then rises with slower pulse p. 272), and finally falls greatly from vaso-motor paralysis.

Respiration.—There is sometimes a feeling of slight dyspnœa

just after the dose has been given, but this only lasts for a fe moments. Poisonous doses cause in animals dyspnœa and con vulsions, which, as already mentioned, probably depend in som measure on cardiac failure. In animals the abundant secretio into the bronchi and pulmonary œdema produced by large dose also lead to dyspnœa.

The **temperature** rises when the patient is shivering an falls during sweating (p. 440). The secretion of sweat usuall lasts for two or three hours, and is so copious that the bod loses one or two pounds and sometimes as much as eight pound from it and the salivation together. Sweating does not occur i every patient who takes pilocarpine, and even salivation is not constant symptom.

After the sweating is over there is usually a feeling of debilit languor, and thirst.

Pilocarpine is **excreted** unchanged by the urine. It does no appear in the saliva.

The **injurious effects** sometimes produced by it are, in add tion to the dimness of vision and vomiting already mentione sudden collapse, swelling of the salivary glands and tonsil hiccough, diminished secretion of urine, albuminuria, strangur bleeding from the vagina, and anticipation of the menstrual flu

Atropine **antagonises** pilocarpine very completely, preven ing its action if administered before it, and removing its effec if given after it. Sudden collapse ought therefore to be treate by the subcutaneous injection of atropine.

The nausea and vomiting generally yield easily to morphin

Uses.—As its action is a peripheral rather than a centra one, it affects the **eye** more powerfully when applied locally tha when taken internally. It has been employed in chronic catarrh in iridocyclitis, intraocular hæmorrhage, turbidity of the vitreou humour, in separation of the retina, in albuminuric retinitis, an instead of physostigmine in glaucoma, &c. (*vide* Myotics, p. 225 It has been used with a certain amount of success in deafne depending on disease of the labyrinth, especially when it syphilitic.[1] In some **skin** diseases it is very useful, especially i prurigo and chronic urticaria and in baldness; also in cases Hebra's prurigo and psoriasis. In small doses it relieves thir in chronic renal disease, and has been used for a similar purpo in fever (*vide* Refrigerants, p. 360).

It has been used in diseases of the **throat**, especially tonsillit and diphtheria, but its utility in the latter disease is uncertai In bronchitis, asthma, and whooping-cough it sometimes giv relief, though it is not so useful as might be expected (p. 254 From its action on the **uterus** it has been used as an oxytoc to induce premature labour. As a **diaphoretic** it may be use

[1] Politzer, *Med.-Chir. Rundschau*, viii. 1885.

in small doses to induce diaphoresis and prevent or relieve coryza, bronchial catarrh, or rheumatism consequent on a chill (p. 330).

It has been employed to remove pleural and peritoneal effusions, and has been used in cardiac dropsy when digitalis failed, but great care is then requisite in its use.

Its chief use, however, is in dropsy, and especially in uræmia depending on disease of the **kidneys**; it may be given subcutaneously as the nitrate in $\frac{1}{6}$–$\frac{1}{3}$ grain doses. In renal dropsy it not only removes water from the body but it removes urea and possibly other products of tissue-waste. Some of the urea is excreted in the sweat, and a considerable amount appears in the saliva. Probably the removal of these products from the body is the reason why pilocarpine cuts short uræmic convulsions. In puerperal eclampsia it is not so successful as in convulsions depending on kidney disease. Pilocarpine has also been used to eliminate other poisons from the body, and has been used in syphilis and chronic poisoning by lead, mercury, and arsenic.

CONTRA-INDICATIONS.—Fatty heart, and impeded pulmonary circulation from valvular disease, emphysema, or pleurisy. These conditions do not absolutely prohibit the use of the remedy, but it must then be given with care and the patient watched. It may be combined with alcoholic stimulants, and atropine should be ready for subcutaneous injection if necessary.

AURANTIÆ.

U.S.P. Aurantii Flores. ORANGE FLOWERS.—The partially expanded fresh flowers of *Citrus vulgaris* and *Citrus Aurantium*. They may be preserved by mixing them well with half their weight of chloride of sodium, pressing them into a jar, and keeping in a cool place.

CHARACTERS.—Fragrant and somewhat bitter.

PREPARATION.

Aqua Aurantii Florum.

U. S. P. Oleum Aurantii Florum. OIL OF ORANGE FLOWERS, OIL OF NEROLI.—A volatile oil distilled from fresh orange flowers.

CHARACTERS.—Yellowish or brownish; it has a fragrant odour of orange flowers, and an aromatic, somewhat bitter taste.

COMPOSITION.—It consists chiefly of a **hydrocarbon** and a little **neroli camphor**.

PREPARATION.

Spiritus Odoratus.

USE.—As a **flavouring** matter.

Aqua Aurantii Floris, B.P.; Aqua Aurantii Florum U.S.P. ORANGE FLOWER WATER.—The distilled water of the flowers of the bitter orange tree, *Citrus vulgaris* (*Citrus bigaradia*) and of the sweet orange tree, *Citrus aurantium*. Prepared mostly in France.

The orange flower water of commerce is usually three times the strength of that employed in former years.

CHARACTERS.—Colourless, or with a slight greenish-yellow tint; it has the fragrant odour of the flowers.

IMPURITY.—Lead from the vessels in which it has been kept.

TEST.—It should not be coloured by sulphuretted hydrogen.

COMPOSITION.—It contains a **volatile oil** (Oil of Neroli).

PREPARATION.

B.P.	DOSE.
Syrupus Aurantii Floris	1–2 fl. dr.
U.S.P.	
Syrupus Aurantii Florum	1–2 fl. dr. (4–8 c.c.)

B.P. Aurantii Fructus. BITTER ORANGE.—The ripe fruit of the *Citrus vulgaris* (*Citrus Bigaradia*). Imported from the South of Europe.

CHARACTERS.—It is like the sweet orange, but darker in colour and very bitter.

Aurantii Cortex, B.P.; Aurantii Amari Cortex, U.S.P. BITTER ORANGE PEEL.—The dried outer part of the rind of the ripe bitter orange.

CHARACTERS.—Thin strips of dark orange colour, with a fragrant odour and an aromatic bitter taste. It should be nearly free from the white part of the rind.

COMPOSITION.—The inner part of the rind is white, spongy and useless; the outer part is yellow when fresh, but brownish-green when dried, and contains a fragrant **volatile oil**, a bitter neutral principle **hesperidin**, and a small quantity of some sort of **tannin**.

PREPARATIONS.

B.P.	DOSE.
Of the fresh peel—	
Tinctura Aurantii Recentis	1–2 fl. dr.
Vinum Aurantii	
Of the dried peel—	
Infusum Aurantii (½ oz. in ½ pint)	1–2 fl. oz.
„ „ **Compositum**	1–2 fl. oz.
„ Gentianæ Compositum	1–2 fl. oz.
Spiritus Armoraciæ Compositus	
Syrupus Aurantii (Tinct. 1, Syrup 7)	1 fl. dr.
Tinctura Aurantii	1–2 fl. dr.
„ Cinchonæ Composita	½–2 fl. dr.
„ Gentianæ „	½–2 fl. dr.
U.S.P.	
Extractum Aurantii Amari Fluidum	2–4 fl. dr. (8–15 c.c.)
Tinctura „ „	1–2 fl. dr. (4–8 c.c.)

B.P. Infusum Aurantii Compositum. COMPOUND INFUSION OF ORANGE PEEL.—Bitter orange peel, ¼ oz.; fresh lemon peel, 56 gr.; cloves, bruised, 28 gr. boiling distilled water, 10 fl. oz.

U.S.P. Aurantii Dulcis Cortex. SWEET ORANGE PEEL.—The rind of the fruit of *Citrus Aurantium*.

CHARACTERS.—Closely resembling bitter orange peel, but having an orange yellow colour. It has a sweetish fragrant odour and an aromatic slightly bitter taste.

PREPARATIONS.	DOSE.
Syrupus Aurantii	1–2 fl. dr.
Tinctura Aurantii Dulcis	20 min.–1 fl. dr.

USES.—The preparations of oranges are used almost entirely as **flavouring** vehicles. The rind is an aromatic stomachic, and is used with other bitters in the treatment of dyspepsia.

U.S.P. Oleum Aurantii Corticis. OIL OF ORANGE PEEL.—A volatile oil extracted by mechanical means from fresh orange peel.

PREPARATION.—It is prepared from the outer part of the rind by expression; by putting it in hot water and skimming off the oil; or by rubbing it in a kind of bowl lined with short spikes in the same way as oil of lemons.

CHARACTERS.—Pale yellow, has the smell of oranges, and an aromatic somewhat bitter taste. By keeping it becomes thicker, and gets a turpentine-like taste. This may be prevented by mixing the fresh oil with 5 per cent. of alcohol and decanting from the sediment.

COMPOSITION.—Contains two **camphenes** and a glucoside, **hesperidin**.

OFFICINAL PREPARATIONS.	DOSE.
Elixir Aurantii	2–8 fl. dr. (4–30 c.c.)
Spiritus Aurantii	2–4 fl. dr. (4–15 c.c.)
Spiritus Myrciæ	Used as perfume.

ACTION AND USE.—Externally it is **rubefacient**. Internally, in large doses, it is an irritant poison. It is used as a **flavouring** matter.

U.S.P. Elixir Aurantii. ELIXIR OF ORANGE (Simple Elixir).—Oil of orange, 1; cotton, 2; sugar, in coarse powder, 100; alcohol and water, of each a sufficient quantity to make 300 parts. Mix alcohol and water in the proportion of 1 part of alcohol to 3 parts of water. Add the oil of orange to the cotton in small portions at a time, distributing it thoroughly by picking the cotton apart after each addition; then pack tightly in a conical percolator and gradually pour on the mixture of alcohol and water until 200 parts of filtered liquid are obtained. In this liquid dissolve the sugar by agitation, without heat, and strain.

USE.—To **cover the taste of drugs** and render them agreeable to the palate. By mixing tinctures and liquid extracts with simple elixir, preparations are obtained which are both palatable and efficient.

U.S.P. Oleum Bergamii. OIL OF BERGAMOT.—A volatile oil extracted by mechanical means from the rind of the fresh fruit of *Citrus Bergamia*, var. *vulgaris*.

CHARACTERS.—A greenish or greenish-yellow, thin liquid, of a peculi very fragrant, odour, an aromatic, bitter taste and a slightly acid reactic Sp. gr. 0·860 to 0·890. It is soluble in all proportions in alcohol and in glac acetic acid.

USE.—In flavouring.

PREPARATION.

SPIRITUS ODORATUS. PERFUMED SPIRIT (Cologne Water).—Oil of bergamot, 1 oil of lemon, 8 ; oil of rosemary, 8 ; oil of lavender flowers, 4 ; oil of orange flowe 4 ; acetic ether, 2 ; water, 158 ; alcohol, 800.

USES.—For perfuming lotions. When bathed on the templ or forehead and evaporated quickly by fanning the face, it useful in headaches or tendency to faintness. Eau de Cologi is not unfrequently taken as a stimulant by ladies, who have idea that it contains alcohol.

Limonis Cortex, B. and U.S.P. LEMON PEEL.—Tl outer part of the rind of the fresh fruit of *Citrus Limonu* Southern Europe and West Indies.

CHARACTERS.—Like those of orange peel, but the colour is a deep lem yellow.

COMPOSITION.—Similar to orange peel.

PREPARATIONS.

B.P.	DOSE.
Infusum Aurantii Compositum	1–2 fl. oz.
,, Gentianæ ,,	1–2 fl. oz.
Oleum Limonis	1–5 min.
Syrupus ,,	1–2 fl. dr. or more.
Tinctura ,,	1–2 fl. dr.

U.S.P.	
Oleum Limonis	1–5 min.
Spiritus ,,	For flavouring.
Syrupus ,,	1–2 fl. dr. or more.
Mistura Potassii Citratis	4–8 fl. dr. (15–30 c.c.)

Oleum Limonis, B. and U.S.P. OIL OF LEMONS.— volatile oil expressed or distilled (B.P.) or extracted by mechan cal means (U.S.P.) from fresh lemons.

CHARACTERS.—A pale yellow liquid, having the fragrant odour of lemo an aromatic, somewhat bitterish taste, and a neutral reaction. By keepi it becomes thicker, and acquires a disagreeable terebinthinate taste. Tl may be prevented by mixing it while fresh with 5 per cent. of alcohol, a decanting the oil after it has become clear from the sediment. When want for use a quantity of water equal to the alcohol may be added, when th unite and subside, leaving the oil on the top.

PREPARATION.—It is sometimes obtained by rasping the outside of t rind and expressing the oil it contains, sometimes by distillation, but the b is got by rubbing the lemons over the interior of a sort of cup lined wi short points, when the oil flows into a reservoir at the bottom of the cup.

COMPOSITION.—It is said to consist of two isomeric oils and kind of camphor formed from them by exposure to air.

ACTION.—Externally it is a strong rubefacient; internall

n small doses, it is stimulating and carminative. It is chiefly sed as a **flavouring** matter.

Officinal Preparations.

B.P.	U.S.P.
Linimentum Potassii Iodidi cum Sapone (p. 516).	Spiritus Limonis.
Spiritus Ammoniæ Aromaticus (1 in 185).	Spiritus Odoratus.

Limonis Succus, B. and U.S.P. Lemon Juice.—The reshly expressed juice of the ripe fruit of *Citrus Limonum*.

Characters.—Slightly turbid, yellowish liquor, with an acid taste, and sually a slight odour of lemon from a little of the oil contained in the rind.

Preparation.—By squeezing the fresh fruit.

Composition.—It contains some acid salts, especially those of otassium, and 7 per cent. of **citric acid** (U.S.P.); 36 to 40 rains in the fluid ounce (B.P.).

Officinal Preparations.

B.P.	Dose.	U.S.P.	Dose.
yrupus Limonis.....	½–2 fl. dr.	Mistura Potassii Citratis...	4 fl. dr. (15 c.c.)
		Syrupus Limonis.....	ad lib.

U.S.P. Mistura Potassæ Citratis. Mixture of Citrate of Potassium (Neutral ixture).—Fresh lemon juice strained, 100; bicarbonate of potassium about 10 arts, or enough to neutralise.

Syrupus Limonis. Syrup of Lemons, B. and U.S.P.—Boiling lemon juice, trained, 1 pint, with fresh lemon peel, 2 oz.; refined sugar, 2¼ pounds (B.P.). oiling lemon juice, 40; fresh lemon peel, 2; sugar, 60; water up to 100 (U.S.P.).

Not officinal. **Decoction of Lemon.**—Cut a *fresh* unpeeled lemon (best when ulled immediately from the tree) into thin slices, put it into three teacupfuls of ater, and boil it down to one teacupful in a clean earthenware jar. Allow it to tand over night in the open air, and give it the first thing in the morning. Free , by compression and filtration, from rind, pulp, and seeds just before it is drunk.

Uses.—It is used locally as a gargle in sore-throat; to elieve itching in pruritus of the scrotum, in uterine hæmorrhage fter delivery, and mixed with equal parts of glycerine as an ap-lication to the face in sunburn. Internally it is **refrigerant,** nd forms a pleasant drink, allaying the thirst in fevers. It is sed, in place of citric acid, to make effervescent mixtures and drinks. It is **antiscorbutic,** and is employed to prevent scurvy n long voyages.

The decoction of lemon is said to be a powerful **antiperiodic,** nd to be exceedingly useful as a substitute for large doses of quinine in cases of ague, typho-malarial fevers, and malarious conditions generally. It appears to be useful in reducing the temperature in typhoid fever even when no malarial complica-tion exists.

B.P. Belæ Fructus. Bael Fruit.—The dried half-ripe fruit of *Ægle Marmelos*, from Malabar and Coromandel.

Characters.—Fruit roundish, about the size of a large orange, with a hard woody rind. Usually seen in fragments consisting of portions of the hard grey rind and dry adherent red pulp and seeds. The moistened pulp is mucilaginous.

COMPOSITION.—Not well ascertained. It contains no appreciable amount of tannin.

PREPARATION. **B.P.**

	DOSE.
Extractum Belæ Liquidum	1 fl. dr. to ½ fl. oz.

USES.—Although it contains no tannin it is used in diarrhœa and dysentery. The fresh pulp is sometimes used as a laxative.



FIG. 186.—Bael, half the natural size.

Possibly bael fruit may owe its utility in dysentery to its possessing some action similar to that of cotoine (p. 387).

SIMARUBACEÆ.

Quassiæ Lignum, B.P.; Quassia, U.S.P. QUASSIA WOOD, B.P.; QUASSIA, U.S.P.—The wood of *Picræna excelsa*. Jamaica.

CHARACTERS.—Billets varying in size, seldom thicker than the thigh. Wood dense, tough, yellowish-white, intensely and purely bitter. Also chips and raspings of the same.

COMPOSITION.—The wood contains a small quantity of a bitter neutral principle, **quassiin**. The wood contains **no tannin**, so that an infusion does not become black on the addition of a persalt of iron.

PREPARATIONS.

B.P.			DOSE.
Extractum Quassiæ			2–5 gr.
Infusum	„	(1 in 80, cold water, for ½ hour)	1–2 fl. oz.
Tinctura	„		½–2 fl. drm.

U.S.P.			
Extractum Quassiæ			3–5 gr. (0·18–0·32 gm.)
„	„	Fluidum	½–1 fl. drm. (2–4 c.c.)
Tinctura	„		½–2 fl. drm. (2–8 c.c.)

ACTION AND USES.—Quassia is a pure bitter **stomachic tonic**, having no other action on man. On insects it exerts a narcotic influence and, in the form of an infusion sweetened with sugar, it is often employed to destroy flies.

In small doses it increases the appetite. In large doses it acts as an irritant and causes vomiting. The infusion is made with cold water. As it contains **no tannin**, it does not form a black inky mixture with iron, like most vegetable bitters, and so can

e conveniently prescribed with it. It is used in atonic dys-epsia.

Its action is not thoroughly understood, but it is not improable that it lessens putrefaction in the stomach and prevents to ome extent the formation of acid substances during digestion.

It is often administered by using a cup made of the wood; his when filled with water, imparts its active principle to that uid. An infusion is used in the form of enema to destroy hread-worms.

BURSERACEÆ.

(AMYRIDACEÆ).

Myrrha, B. and U.S.P. MYRRH.—A gum-resinous exudation from the stem of *Balsamodendron Myrrha*. Arabia Felix nd Abyssinia.

CHARACTERS.—In irregular-shaped tears or masses varying much in size, omewhat translucent, of a brownish-yellow or reddish-brown colour, fractured surface irregular and somewhat oily; odour agreeable and aromatic, aste acrid and bitter.

COMPOSITION.—**Gum** (50–60 per cent.) soluble in water, and f which arabin constitutes a portion. The remainder, insoluble n water, is made up principally of a resinous acid, **myrrhic** cid, and a **volatile oil.**

DOSE.—10–30 gr.

PREPARATIONS.

B.P.	DOSE.
Decoctum Aloes Compositum	½–2 fl. oz.
Mistura Ferri Composita	1–2 fl. oz.
Pilula Aloes et Myrrhæ (*vide* p. 522)	5–10 gr.
„ Asafœtidæ Composita (*vide* p. 522)	5–10 gr.
„ Rhei Composita (*vide* p. 523)	5–10 gr.
Tinctura Myrrhæ	½–1 fl. dr.

U.S.P.	
Mistura Ferri Composita	1–2 fl. oz. (30–60 c.c.)
Pilulæ Aloes et Myrrhæ (*vide* p. 523)	1 pill.
„ Ferri Compositæ (*vide* p. 523)	2–6 pills.
„ Galbani Compositæ (*vide* p. 523)	2–4 pills.
Tinctura Aloes et Myrrhæ	1–2 fl. dr. (4–8 c.c.)
Tinctura Myrrhæ	1–2 fl. dr. (4–8 c.c.)

ACTION AND USES.—Myrrh is a very useful **astringent** in the orm of wash or gargle for spongy gums, aphthous stomatitis, nd ulcerated throats. Internally it is used as an **expectorant** n chronic bronchitis; and combined with iron and aloes is used n the treatment of amenorrhœa. It is also useful in bronchorhœa and leucorrhœa.

B.P. Elemi. ELEMI.—A concrete resinous exudation, the otanical source of which is undetermined, but is sometimes referred to *Canarium commune* (or to *Icica Abilo*). Manilla.

CHARACTERS.—A soft sticky mass, yellowish-white, with fennel-like odour; almost entirely soluble in rectified spirit.

COMPOSITION.—Two resins and a volatile oil.

PREPARATION.

B.P. Unguentum Elemi (with simple ointment).....1 part in 5.

USES.—Not given internally; is used as a local stimulant ulceration.

MELIACEÆ.

U.S.P. Azedarach. AZEDARACH.—The bark of the root *Melia Azedarach.*

CHARACTERS.—In curved pieces or quills varying in size and thickne outer surface red-brown, with irregular, blackish, longitudinal ridges; inn surface whitish or brownish, longitudinally striate; fracture more or l fibrous; upon transverse section tangentially striate, with yellowish ba fibres; almost inodorous, sweetish, afterward bitter and nauseous.

If collected from old roots, the bark should be freed from the thick, ru brown, nearly tasteless, corky layer.

ACTION.—It produces vomiting and purging and symptoms narcotic poisoning.

USE.—It is used as an anthelmintic, to destroy the asca lumbricoides, in the form of a decoction (2 oz. of the herb to pint of water, boiled down to ½ a pint). This is given in dos of a tablespoonful every two or three hours until the bowels a freely opened.

ILICINEÆ.

(AQUIFOLIACEÆ.)

U.S.P. Prinos. PRINOS. BLACK ALDER.—The bark *Prinos verticillatus,* Linné (*Ilex verticillata,* Gray).

CHARACTERS.—Thin, slender fragments, about one-twenty-fifth of an in (1 millimetre) thick, fragile; outer surface brownish ash-coloured with whiti patches and blackish dots and lines, the corky layer easily separating fr the green tissue; inner surface pale greenish or yellowish; fracture sho tangentially striate; nearly inodorous, bitter, slightly astringent.

DOSE.—30 grains.

ACTION.—It is an astringent bitter. It is employed in t form of a decoction, prepared by boiling two ounces of the ba in three pints of water down to two pints. This decoction given internally, in doses of two or three fluid ounces, in dia rhœa and malarial disorders, and is used externally in indole sores and chronic skin-diseases.

CELASTRINÆ.

U.S.P. Euonymus. EUONYMUS. WAHOO.—The bark *Euonymus atropurpureus.*

CHARACTERS.—In quilled or curved pieces, about one-twelfth of an in (2 millimetres) thick; outer surface ash-grey, with blackish patches, detach in thin and small scales; inner surface whitish or slightly tawny, smoot fracture smooth, whitish, the inner layers tangentially striate; nea inodorous; taste sweetish, somewhat bitter and acrid.

Preparation.	Dose.
Extractum Euonymi	2–5 gr.

Composition.—It contains a bitter principle called **euonymin**, which is precipitated, together with a resin and a fixed oil, when the strong tincture is poured into water.

Action.—It acts as an **hepatic stimulant** (p. 403), hydragogue **cathartic**, and diuretic. In large doses it causes intestinal and hæmorrhoidal irritation.

Use.—In constipation accompanied by biliousness, and in chronic malarial conditions.

RHAMNEÆ.

B.P. Rhamni Purshiani Cortex. Sacred Bark. (*Synonym:* Cascara Sagrada.)—The dried bark of *Rhamnus Purshianus*. North Pacific Coast.

Characters.—In quills or incurved pieces of varying lengths and sizes, the bark itself being from about $\frac{1}{25}$ to $\frac{1}{8}$ of an inch thick, smooth or nearly so externally, covered with a greyish-white layer, which is usually easily removed, and frequently marked with spots or patches of adherent lichens. Beneath the surface it is violet-brown, reddish-brown, or brownish; and internally reddish-brown or yellowish-brown, and nearly smooth, although somewhat striated longitudinally. Fracture short, except internally, where it is slightly fibrous, more especially in the larger pieces. No marked odour; taste bitter. It is frequently imported in flattened packets, consisting of small pieces of the bark compressed into a more or less compact mass.

Composition.—Cascara bark contains several resinoid bodies, which are supposed to be derived from **chrysophanic acid**. It also contains much **tannin**.

Preparations.		Dose.
B.P.		
Extractum Cascaræ Sagradæ		2–8 gr.
" " "	**Liquidum**	$\frac{1}{2}$–2 fl. dr.

Action and Uses.—All the species of buckthorn appear to possess cathartic properties. Cascara Sagrada is usually given in the form of liquid extract in doses of $\frac{1}{2}$ to 1 fl. dr., but $\frac{1}{2}$ fl. dr. or less given immediately after rising in the morning or at bedtime is often sufficient. It may also be given with advantage in chronic constipation in doses of 10–15 min. thrice a day before meals. It acts as a stomachic tonic and bitter in these small doses.

Rhamni Frangulæ Cortex, B.P.; Frangula, U.S.P. Frangula Bark, B.P.; Buckthorn, U.S.P.—The dried bark of *Rhamnus Frangula*, collected from the young trunk and moderate-sized branches and kept at least one year before being used. Holland.

CHARACTERS.—In quills about $\frac{1}{25}$ of an inch thick; greyish or blackis brown outside with whitish corky warts; brownish-yellow internall Nearly inodorous, taste sweetish and bitter.

COMPOSITION.—The most important constituent is a cathart substance, **frangulin**.

PREPARATIONS.

B.P.

Extractum Rhamni Frangulæ	15–60 gr.
" " " **Liquidum**	1–4 fl. dr.

U.S.P.

	DOSE.
Extractum Frangulæ Fluidum	1 fl. dr. (4 c.c.)

ACTION AND USES.—When fresh it acts as an **irritant** poiso on the gastro-intestinal canal, but when dried its action becom less violent, and more like that of rhubarb. It is used as **purgative** in constipation, and may be given in the form of th fluid extract or of a decoction ($\frac{1}{2}$ oz. to $\frac{1}{2}$ pint) in tablespoonf doses, or as an elixir, 1 fl. dr. of the fluid extract to 3 of elixir orange.

AMPELIDÆ.

(VITACEÆ.)

B.P. Uvæ. RAISINS.—The ripe fruit of the *Vitis vinifer* dried either wholly or partly by the sun. Spain.

COMPOSITION.—They contain **grape-sugar** and **acid tartrat of potassium**.

PREPARATIONS.

Tinctura Cardamomi Composita.
" Sennæ.

USES.—They are used to sweeten preparations. They are useful stimulant in weariness from mental work (p. 193); and i active physical exertion, such as alpine climbing, they not onl tend to maintain the strength and prevent exhaustion, but the somewhat relieve thirst when water cannot be had (p. 360).

Vinum Xericum, B.P. SHERRY WINE. **Vinum Album U.S.P.** WHITE WINE.—A pale amber or straw-coloured alcoholi liquid, made by fermenting the unmodified juice of the grap freed from seeds, stems, and skins. It should contain not les than 10 per cent. nor more than 12 per cent. by weight o absolute alcohol.

PREPARATION.

U.S.P.

Vinum Album Fortius, prepared by mixing 7 parts white wine with 1 of alcoho This should contain not less than 20 per cent. nor more than 25 per cent. by weigh of absolute alcohol.

U.S.P. Vinum Rubrum. RED WINE.—A deep red alcoholi liquid made by fermenting the juice of coloured grapes in pre sence of their skins.

It should not contain less than 10 per cent. nor more than 12 per cent. by weight of absolute alcohol.

ACTION AND USES.—*Vide* Alcohol (p. 766).

SAPINDACEÆ.

U.S.P. Guarana. GUARANA.—A dried paste prepared from the crushed or ground seeds of *Paullinia sorbilis*.

CHARACTERS.—Sub-globular, or elliptic cakes, or cylindrical sticks, hard, dark reddish-brown; fracture uneven, somewhat glossy, showing fragments of seeds invested with a black testa; odour slight, peculiar, resembling chocolate; taste astringent, bitter; it is partly soluble in water, and in alcohol.

PREPARATION.

	DOSE.
Extractum Guaranæ Fluidum	15 min. to 1 fl. oz.

COMPOSITION.—It contains four or five per cent. of **caffeine** (p. 870) and a considerable amount of **tannic acid**, and it is upon these that its medicinal value depends.

USES.—It is chiefly used to cut short attacks of sick headache. It may be given in doses of one or two drachms of the powder, mixed with hot water, or as fluid extract, when the headache is coming on.

ANACARDIACEÆ.

(TEREBINTHACEÆ.)

Mastiche, B. and U.S.P.—MASTICH.—A concrete resinous exudation obtained by making incisions in the bark of the stem and large branches of *Pistacia Lentiscus*. Scio.

CHARACTERS.—Globular or elongated tears about the size of a pea, pale yellow, glass-like, brittle, becoming soft and plastic when chewed; faint agreeable odour and slight terebinthinate taste.

COMPOSITION.—Consists of about 90 per cent. of an acid resin (**masticic acid**), soluble in alcohol; the remaining 10 per cent. is **masticin**, a tenacious resin soluble in ether, with traces of an ethereal oil.

PREPARATION.

U.S.P.

Pilulæ Aloes et Mastiches (*vide* p. 523).

DOSE.—20 to 40 gr. if administered internally.

USES.—It is sometimes chewed in order to give a pleasant odour to the breath. It is chiefly employed for temporarily stopping decayed teeth, and for arresting hæmorrhage from leech-bites. When used to stop teeth the cavity ought to be well cleaned and dried, and a piece of cotton saturated with a solution of four parts of mastiche should be gently pressed into it so as not to cause pain, but to fill the cavity exactly. Another method

is to dissolve one part of mastiche with two of collodion, and f the cavity with this. Either of these methods may also be em ployed to stop bleeding from leech-bites. It has been suppos to have a **stimulating** action on the **bronchial** mucous mem brane, and has been used in bronchorrhœa, and also in infantile cholera. It is used to cover mercurial pills and prevent th formation of amalgam when they are silvered. When mixed with aloes it renders the pill less readily soluble, and so to exer an action more on the lower than upper part of the intestine.

U.S.P. Rhus Glabra. RHUS GLABRA. SUMACH.—The fruit of *Rhus glabra*.

CHARACTERS.—Sub-globular, about one-eighth of an inch (3 millimetres) in diameter, drupaceous, crimson, densely hairy, containing a roundish oblong, smooth putamen. It is inodorous, and its taste acidulous.

PREPARATION.	DOSE.
Extractum Rhois Glabræ Fluidum.	.....1–2 fl. dr.

COMPOSITION.—It contains much **tannin.**

USES.—It may be used as an **astringent** in the form of de coction, or of the fluid extract diluted, for an effective gargle in inflammation of the throat or mouth.

U.S.P. Rhus Toxicodendron. RHUS TOXICODENDRON. POISON IVY.—The fresh leaves of *Rhus Toxicodendron*, Michaux, *Rhus Toxicodendron* and *Rhus radicans*, Linné.

CHARACTERS.—Long-petiolate, trifoliate; the lateral leaflets sessile, about four inches (10 centimetres) long, obliquely ovate, pointed; the terminal leaflets stalked, ovate or oval, pointed, with a wedge-shaped base; the leaflets entire and glabrous (in *Rhus radicans*, Linné), or variously notched, coarsely toothed or lobed, downy beneath (in *Rhus Toxicodendron*, Linné); when dry, papery and brittle; inodorous; somewhat astringent and acrid.

The fresh leaves abound with an acrid juice which darkens when exposed to the air, and, when applied to the skin, produces inflammation and swelling. The leaves should, therefore, not be touched with bare hands.

Rhus Toxicodendron should not be confounded with the leaves of *Pteris trifoliata*, Linné, which are similar in appearance, but have all the leaflets sessile.

COMPOSITION.—It contains a **volatile acid** which appears to be the active principle.

ACTION.—In many persons, contact with this plant causes an eczematous eruption of a very distressing character, which is best treated by solutions of lead, permanganate of potassium, and ammonia. Internally it causes gastro-intestinal irritation, drowsiness, stupor, and delirium.

USES.—It has been recommended in **incontinence of urine** paralysis, and cutaneous diseases.

A fluid extract of a non-officinal plant, *Rhus aromatica*, has been used successfully in incontinence of urine in doses of 5 to 30 min.

CHAPTER XXXIII.

Class I.—DICOTYLEDONES POLYPETALÆ.

Sub-Class III.—CALYCIFLORÆ.

LEGUMINOSÆ.

Sub-Order I.—PAPILIONACEÆ.

Glycyrrhizæ Radix, B.P.; Glycyrrhiza, U.S.P. Liquorice Root.—The root or underground stem, fresh and dried, of *Glycyrrhiza glabra.*

Characters.—In long cylindrical branched pieces, tough and pliable; yellowish-brown outside, yellow inside; taste sweet and slightly acrid. Digested with water it yields a solution which gives a precipitate with diluted sulphuric acid.

Composition.—Contains **starch, sugar,** and a sweet principle **glycyrrhizin**—which is the substance precipitated by sulphuric acid.

Preparations.

B.P.	STRENGTH.	DOSE.
Confectio Terebinthinæ	1 in 4	60–120 gr.
Decoctum Sarsæ Compositum	¼ oz. in 1½ pint	2–10 fl. oz.
Extractum Glycyrrhizæ		10–30 gr.
„ „ **Liquidum**		1 fl. dr.
Infusum Lini	1 in 87½ fl. parts	1–2 fl. oz.
Pilula Hydrargyri (*vide* p. 522)		3–8 gr.
„ Ferri Iodidi (*vide* p. 522)		3–8 gr.
Pulvis Glycyrrhizæ Compositus (*vide* p. 910)		30–60 gr.

OF EXTRACT OF LIQUORICE—

Confectio Sennæ	1 part in 94, nearly.
Decoctum Aloes Compositum	1 oz. in 30 fl. oz.
Tinctura Aloes	1½ oz. to 1 pint.
Trochisci Opii	

OF LIQUID EXTRACT OF LIQUORICE—

Mistura Sennæ Composita	1 fl. oz. in 1 pint.
Tinctura Chloroformi et Morphinæ	

U.S.P.	DOSE.
Extractum Glycyrrhizæ Fluidum	1 fl. dr. (4 c.c.)
„ „ Purum	1 fl. dr. (4 c.c.)
Glycyrrhizinum Ammoniatum	5–15 gr. (0·32–1 gm.)
Pulvis Glycyrrhizæ Compositus (*vide* p. 906)	30–60 gr. (2–4 gm.)

U.S.P. Glycyrrhizinum Ammoniatum. Ammoniated Glycyrrhizin.—Prepared by exhausting powdered liquorice with ammonia, precipitating by sulphuric acid, redissolving in ammonia, and drying. It forms dark brown or reddish scales, very sweet. It is used for flavouring.

ACTION AND USES.—Taken into the mouth, liquorice has sweet taste; it increases the flow of saliva, and being mucilaginous acts as a **demulcent**. It is used to allay cough by lessening the irritation of the mucous membrane. It is particularly useful when there is violent cough due to irritation of the pharynx and upper part of the respiratory passages (p. 249). is used as a vehicle to cover the taste of other medicines, and has been used instead of sugar in diabetes. The Pulv. Glycyrrhizæ Co., which is really a preparation of senna (*q.v.*, p. 909) is a gentle laxative.

Scopari Cacumina, B.P.; Scoparius, U.S.P. BROOM TOPS, B.P.; BROOM, U.S.P.—The fresh and dried tops of *Cytisus Scoparius* (*Sarothamnus Scoparius*). From indigenous plants.

CHARACTERS.—Thin flexible tough twigs, dark green, angular, of a bitter nauseous taste, and of a peculiar odour when bruised.

COMPOSITION.—It was found by Stenhouse to contain two principles: a neutral body, **scoparin**, and a volatile poisonous alkaloid, **sparteine**.

PREPARATIONS.

B.P.	DOSE.
Decoctum Scoparii (1 oz. in 1 pint for 10 minutes and strain)	1–3 fl. oz.
Succus Scoparii	1–2 fl. dr. or more

None in U.S.P.

PHYSIOLOGICAL ACTION.—Broom-tops have a **diuretic** action. The action of **sparteine** is identical with that of coniine. It **paralyses** the endings of the motor nerves and vagi, diminishes reflex excitability of the cord, and causes death by paralysis of the respiratory centre in the medulla oblongata. According to J. Fick it has a diuretic action.

Scoparin has been supposed to be the diuretic principle. It has **little** physiological **action**, and in a number of unpublished experiments which I made in 1865 with a specimen given to me by my friend Dr. Stenhouse, I found that in the healthy subject it does not produce diuresis. Similar results have been obtained by Paton. It is quite possible, however, that it may act as a diuretic in cases of dropsy.

THERAPEUTICAL USES.—Broom-tops are most useful in dropsy dependent on chronic renal disease. They are also useful in cardiac dropsy, but digitalis is generally more certain. In comparative experiments I have found the decoction of the dried broom-tops quite as efficacious as the juice expressed from the fresh tops.

Tragacantha, B. and U.S.P. TRAGACANTH.—A gummy exudation obtained by making incisions in the stems of *Astragalus gummifer* and some other species of Astragalus. Asia Minor.

Characters.—Shell-like bands, slightly curved, white or yellowish, tough nd elastic; very sparingly soluble in cold water, but swelling into a gelati- ous mass, which is tinged violet by tincture of iodine.



Fig. 187.—Tragacanth, half the natural size.

Composition.—Consists of a mixture of **arabin**, or common gum-arabic; and **bassorin**, a gum which does not dissolve in water, but swells up in it.

Preparations.

B.P.	Dose.	U.S.P.
Confectio Opii	5–20 gr.	Mucilago Tragacanthæ
„ Sulphuris	60–120 gr.	
Glycerinum Tragacanthæ	6 grs. to 1 fl. oz.	
Mucilago „	1 fl oz. or more.	
Pulvis Opii Compositus	2–5 gr.	
„ Tragacanthæ Compositus	20 gr. upwards.	

Mucilago Tragacanthæ. Mucilage of Tragacanth.—Tragacanth, 60 gr.; water, 10 fl. oz. (B.P.). Tragacanth, 6; glycerine, 18; water up to 100 (U.S.P.).

B.P. Pulvis Tragacanthæ Compositus. Compound Powder of Tragacanth.—Tragacanth, 1; gum acacia, 1; starch, 1; refined sugar, 3.

Uses.—It is used to **suspend heavy powders**, such as subnitrate of bismuth, and is more efficacious than gum-arabic owing to the insoluble gum bassorin, which swells up when water is added. Also used in making lozenges, and emulsions of cod-liver oil.

Pterocarpi Lignum, B.P. Red Sandal-Wood.—The sliced or rasped heart-wood of *Pterocarpus santalinus*. Ceylon.

Santalum Rubrum, U.S.P. Red Saunders.—The wood of *Pterocarpus santalinus*.

Characters.—The wood is in billets, chips, or powder. It resembles logwood in appearance, but is denser, and the cut surface is more glistening and of a deeper red colour.

Composition.—It contains a fine ruby colouring matter named **santalin**, which may be dissolved out by spirit, ether, acetic acid, &c.; it is insoluble in water.

Preparation.

B.P.	Dose.	U.S.P.
Tinctura Lavandulæ Composita	½–2 fl. dr.	Not given.

Use.—It is used to give colour to the compound tincture of lavender, and through this to *Liquor arsenicalis*.

Kino, B. and U.S.P. KINO.—The juice obtained from i cisions made in the trunk of *Pterocarpus marsupium* inspissat without artificial heat. Malabar.

CHARACTERS.—Small angular, brittle, glistening, reddish-black fragmen translucent and ruby-red on the edges, inodorous, very astringent. Wh chewed it tinges the saliva blood-red.

COMPOSITION.—**Kino-tannic acid** and **pyrocatechin**, whi differs very slightly from catechin, obtained from catech Through the action of kino-tannic acid, kino strikes a vio colour with ferrous salts, turning to green by exposure.

DOSE.—Of powdered kino, 10–30 gr.

PREPARATIONS.

B.P.	DOSE.
Pulvis Catechu Compositus (p. 951)	20–40 gr.
„ **Kino** „ (p. 845)	5–20 gr.
Tinctura Kino	½–2 fl. dr.
U.S.P.	
Tinctura Kino	½–2 fl. dr. (2–8 c

ACTION AND USES.—Kino has an **astringent** action both e ternally and internally. It is useful in relaxed sore-throat as gargle. It is given internally in diarrhœa and in pyrosis. Fro its insolubility it is most useful when we desire an astringe action on the lower part of the intestinal canal, but when t astringency is required in the upper part it is not so useful the more soluble astringents.

Balsamum Peruvianum, B. and U.S.P. BALSAM OF PE A balsam obtained from *Myroxylon Pereiræ*. It exudes fr the trunk of the tree after the bark has been beaten and scorch and removed. Salvador in Central America.

CHARACTERS.—A treacle-like liquid, nearly black in bulk, reddish-bro and translucent in thin films; of syrupy consistence, balsamic odour, and acrid, slightly bitter taste.

COMPOSITION.—Contains **resin**, **volatile oil**, and both **benzo** and **cinnamic acids**.

DOSE.—10 min. to ½ fl. dr., and upwards, made into emulsion with mucilage or yolk of egg.

ACTION AND USES.—It is employed locally as a **parasitici** in scabies and in cases of skin-diseases depending on vegeta fungi. It destroys both the itch-acarus and its eggs. It is mu more agreeable than sulphur ointment. Before applying it, i advantageous to take a warm bath, and wash the affected pa thoroughly with soft soap, and then to rub it well in all over body, especially into the armpits, between the fingers, and on inside of the thighs. The treatment should be repeated every t or three days, during which time the same linen should be wo this when cast off should be well disinfected, or the disease n return. It may be used either alone or in combination w petroleum to destroy pediculi; a useful formula is—balsam Peru, 20 parts; olive oil, 50; petroleum, 100 parts. It is a

useful in prurigo, in pruritus, and in the later stages of an acute eczema. It is a useful **stimulant** to bed-sores and ulcers. It is given internally to lessen discharge from mucous membranes, as in bronchorrhœa, gleet, and leucorrhœa; also as a stimulating **expectorant** in chronic bronchitis.

Balsamum Tolutanum, B. and U.S.P. BALSAM OF TOLU. A balsam obtained from *Myroxylon toluifera*. It exudes from the trunk of the tree after incisions have been made into the bark. New Granada.

CHARACTERS.—A soft and tenacious solid when fresh, but hard, brittle, and resinous-looking when kept, with a fragrant balsamic odour; soluble in rectified spirit. The solution shows an acid reaction with test-paper.

COMPOSITION. — Contains a **resin, volatile oil,** and **free cinnamic** and **benzoic acids.**

DOSE.—10 to 20 grains.

PREPARATIONS.

B.P.	DOSE.
Pilula Phosphori (4 parts in 9)	
Syrupus Tolutanus	1–3 fl. dr.
Tinctura Benzoini Composita	½–1 fl. dr.
„ **Tolutana**	½–1 fl. dr.

U.S.P.	
Syrupus Tolutanus	1–3 fl. dr. (4–12 c.c.)
Tinctura Tolutana	1–2 fl. dr. (4–8 c.c.)

USES.—As a stimulating **expectorant** in chronic coughs. It should not be used while acute inflammation is present. The syrup covers well the taste of chloral or butyl-chloral.

Abrus. JEQUIRITY SEEDS, PRAYER BEADS, JUMBLE BEADS, GUMCHI, INDIAN LIQUORICE.—The seeds of *Abrus precatorius*. Not officinal.

CHARACTERS.—Small hard seeds of a brilliant scarlet colour, with a black spot round the hilum.

COMPOSITION.—They contain a ferment closely associated with a proteid to which the name of **abrin** has been given. The activity of the ferment is destroyed by a temperature over 60° C.[1] The infusion when left for a short time swarms with bacteria.

ACTION.—When applied to the eye the infusion causes **inflammation** of the conjunctiva. The seeds are sometimes used to kill cattle illegitimately. The seeds are moistened with water and rolled into small cylinders or needles with which the animal is stabbed, the point being left in the wound. The animal dies in a few hours. The seeds contain no alkaloid, and possibly death may be due to the **ferment** of the seeds causing micrococci and bacilli to develop in the blood in the same way as papain (p. 85).

[1] Warden and Waddell, *The Non-bacillar Nature of Abrus-Poison*. Calcutta, 1884.

USE.—An infusion is used to produce purulent ophthalm in order to cure granular lids. The infusion is made by mixi the powdered seeds (3) with cold water (500), and adding b water (500). This is filtered when cold. It is applied thr times the first day, and repeated on the second or third day necessary. An emulsion made by triturating the seeds wi water and painted on with a brush is useful in unhealthy ulce and lupus.

Physostigmatis Semen, B.P.; Physostigma, U.S. CALABAR BEAN.—The dried seed of *Physostigma venenosu* Western Africa.



FIG. 188.—Calabar Bean, half the natural size.

CHARACTERS.—A kidney-shaped bean about an inch long, chocola coloured, shining, and with a broad black groove along the whole length of t convex edge. Internally the bean is white, and tastes like an edible bean.

COMPOSITION.—Contains two alkaloids—**physostigmine** eserine, and **calabarine.**

DOSE.—Of the powdered bean 1 gr. gradually increased.

PREPARATIONS.

B.P.	DOSE.
Extractum Physostigmatis	$\frac{1}{15}$–$\frac{1}{4}$ gr.

U.S.P.

Extractum Physostigmatis	$\frac{1}{15}$–$\frac{1}{4}$ gr. (0·004–0·01 gm.)
Tinctura Physostigmatis	12 min.

B.P. Physostigmina. PHYSOSTIGMINE.—*Synonym:* Eserin $C_{15}H_{21}N_3O_2$.—An alkaloid obtained from the alcoholic extract Calabar bean, by dissolving the extract in water, adding bica bonate of sodium, shaking the mixture with ether, and evap rating the ethereal liquid.

CHARACTERS.—In colourless or pinkish crystals.

SOLUBILITY.—It is slightly soluble in water, but readily soluble in alcob and in dilute acids.

REACTIONS.—The aqueous solution has an alkaline reaction; when warm with or when shaken with dilute solution of potash it becomes red, and wh evaporated to dryness over a water-bath it leaves a bluish residue, the acidifi solution of which is beautifully dichroic, being blue and red. Physostigmi causes contraction of the pupil of the eye.

PREPARATION.

B.P.	STRENGTH.
Lamellæ Physostigminæ	$\frac{1}{1000}$th gr. in each.

U.S.P. Physostigminæ Salicylas. SALICYLATE OF PHYS STIGMINE. $C_{15}H_{21}N_3O_2C_7H_6O_3$; 413.—The salicylate of an alk loid prepared from physostigma.

CHARACTERS.—Colourless, shining, acicular, or short, columnar crystals, radually turning reddish when long exposed to air and light, odourless, aving a bitter taste, and a neutral reaction.

DOSE.— $\frac{1}{16}$ to $\frac{1}{12}$ gr.

PHYSIOLOGICAL ACTION.—Physostigma stimulates **muscular bre**, both voluntary and involuntary, throughout the body, and aralyses the **nerve-centres.**

The alkaloids of Calabar bean have different actions, and ifferent or even contradictory results may be obtained according o the amount of each present in the preparation of the bean mployed. **Physostigmine** or eserine **paralyses** the nervous entres and stimulates muscular fibre, but **calabarine** causes **onvulsions** like strychnine.

General Action.—A small dose of physostigma, from its ction on the muscular fibres of the intestine, causes pain in the bdomen, with nausea and vomiting. From its action on the agus and motor centres it causes a sense of oppression in the hest, and weakness. With larger doses these symptoms become orse; and, in addition, contraction of the pupil, salivation, lowness of the pulse, and spasmodic respiration occur. Death s due to paralysis of respiration.

The excitability of the **muscles** is increased, so that they ontract on the application of a slighter stimulus than usual, but heir actual working power is not increased. In the first stage f poisoning in frogs muscular tremors are often apparent, and re also seen on the local application of the drug to the muscle f frogs. They are due to the local action of the drug on the intra-nuscular end-plates, for they occur when the sciatic nerve has been ivided before poisoning, but cease after the injection of curare.

The **spinal cord** is paralysed; the posterior columns first and hen the anterior columns. This action on the cord is the cause f the general paralysis induced by the drug. Convulsions like hose of strychnine-poisoning may occur. They are due to alabarine.

The **medulla** is paralysed, and respiratory movements cease efore the reflex action of the spinal cord is destroyed.

The **motor nerves** in warm-blooded animals are not usually ffected until very late, but in frogs they are paralysed gradually.

The **sensory nerves** are partially paralysed by the local pplication of physostigma in a concentrated form, but not when t is injected into the blood.

The **brain** in man seems not to be paralysed, for in a number f cases of poisoning which occurred among children in conse-uence of eating the beans, consciousness was not impaired at ll, and neither convulsions nor anæsthesia occurred. Not-withstanding the absence of convulsions in these cases, however, hysostigma appears to have an irritant action upon the brain, or when it is administered to epileptic patients, or to animals

rendered epileptic by section of the sciatic nerve, it increases t number of fits (p. 188). Cats and guinea-pigs poisoned by also show symptoms of great cerebral excitement, becoming v timid and running wildly about. This may be partly due interference with the respiration, but can hardly be the o cause, as this condition is not observed in the case of other dr which paralyse the respiration. In frogs the brain appears to paralysed before the spinal cord, so that voluntary motion cea before reflex action.

Action on the Eye. — When locally applied, physostig causes contraction of the pupil, diminishes intra-ocular tensi and causes spasm of accommodation, preceded by increa power of accommodation for near objects ; often twitching of eyelids and slight supra-orbital pain are observed. These effe are due either to stimulation of the fibres of the third nerve of the circular muscular fibres of the iris ; but are certainly due to paralysis of the sympathetic, since stimulation of sympathetic will, during the influence of the poison, cause di tation of the pupil (p. 222).

Respiration is first quickened and then retarded. T acceleration is due to spasm of the bronchial tubes according some observers ; but others consider it to be caused by stimu tion of the ends of the vagi in the lungs (p. 245) ; and it is cert that if the vagi are first divided, physostigma no longer cau acceleration of respiration, but slows it from the first. T slowing of respiration is due to paralysis of the respirat centre in the medulla. Death is the result of this failure respiration.

Action on the Circulation.—Small doses sometimes ca a slight fall in blood-pressure, larger ones always cause a r This rise is chiefly due to the increased contractile power of heart, but it is not improbable that it is aided by a contract of the arterioles, the muscular fibres of which, like all ot involuntary muscles in the body, are stimulated by the act of physostigma upon them. According to Von Bezold Goetz the rise is also partly due to tetanic contraction of intestinal walls, which drives the blood out of them. The irr bility of the **vagus** appears to be increased, as a slighter stimu applied to its trunk will stop the heart after its administrati We should therefore expect the normal stimuli passing to vagus centre along sensory nerves from various parts of the b to have a greater effect upon the heart than usual, and t render its beats slower. This seems to be the case, for phy stigma causes slowness of the pulse, which does not appear depend upon direct stimulation of the vagus roots, as it is abs in animals which have been deeply chloralised before the adm istration of physostigma. In such animals physostigma, on contrary, quickens the pulse and raises the blood-pressure.

Muscle.—When applied to the frog's heart it renders the pulsations slower and more powerful. Its stimulant action on the **cardiac muscular fibre** is so great that neither irritation of the vagus nor of the venous sinus can stop the heart. That the vagus is not paralysed is shown by the fact, that when the stimulant action of the physostigma on the muscular fibre is counteracted by a poison having a paralysing action on the muscle, such as a double salt of copper, stimulation of the vagus will again produce the stillstand in diastole.[1] In larger doses physostigma produces the staircase phenomenon (p. 312, and Fig. 30, p. 110), and finally imperfect stillstand in systole. The contracted ventricle still continues to pulsate slightly, and when it is distended by increasing the pressure of the fluid within it the pulsations become vigorous, and there is no tendency, as in the case of digitalis, to rapid paralysis of the cardiac muscle.

The action of physostigma on the heart is counteracted by atropine, and, though to a less extent, the action of atropine is counteracted by physostigma (p. 493).

From its action on **involuntary muscle** it causes contraction of the **stomach**, retching and vomiting. It causes also diarrhœa and increased peristaltic movements of the **intestines**, which finally end in tetanic contraction, so that the lumen of the intestine is almost obliterated, and it appears like a hard cord. It causes contraction of the **spleen, bladder**, and **uterus**: these contractions are not prevented by a dose of atropine sufficient to paralyse the nerves. The difference between the action of muscarine, which causes tetanic contraction of the intestine by acting on the nerves, and of physostigma, which produces a similar effect by acting on the muscular fibre, is seen when muscarine, atropine, and physostigma are administered successively to an animal.[2] The muscarine first causes tetanic contraction. Atropine causes this to disappear, and produces complete relaxation, which is succeeded by a second tetanic contraction after the administration of physostigma. In consequence of its action on the bladder it causes **urination.**

Secretion is increased by physostigma not only in the salivary, but in the sweat, lacrimal, and mucous glands. It seems probable that the secretion is not due, like that produced by muscarine, nicotine, or pilocarpine, to an action on the ends of the secreting nerves, but rather to the action of physostigma on the secreting **cells** themselves, because, unlike the secretion produced by the three drugs already mentioned, it still persists after the administration of atropine. Physostigma restores its excitability to the chorda tympani after its secretory fibres have been paralysed by atropine. When the dose of physostigma is large, the secretion of saliva which it occasions lasts only for a

[1] Harnack, *Buchheim's Arzneimittellehre*, 3te Aufl., p. 712.
[2] Schmiedeberg, *Arzneimittellehre*, p. 70.

short time, because the vessels of the gland become so muc contracted through the action of the drug that the circulation insufficient to maintain the secretion (p. 358).

Uses.—It is used in certain diseases of the eye, e.g. wound and ulcers of the cornea, and from its lessening intra-ocular tension it is used in glaucoma and staphyloma (p. 224). It removes dilatation of the pupil and paralysis of accommodation after the use of atropine, and, used alternately with atropine breaks down adhesions after iritis (p. 226).

It is used in tetanus, strychnine-poisoning, general paralysis of the insane, and mania, in paraplegia and in locomotor ataxy.

It is also useful in constipation due to atony of the intestinal walls.

It has been recommended in bronchitis, catarrh, and dyspnœa when due to weakness of the bronchial muscles (Ringer).

It is used as an **antidote** to atropine and also to strychnine.

Treatment in Poisoning by Physostigma.—Evacuate the stomach by an emetic, and inject atropine (4 minims of the liquor every ½ hour) until the pulse quickens or the symptoms pass off. If the dose of atropine be too great, it seems to intensify the lethal action of the physostigma.

Hæmatoxyli Lignum, B.P.; Hæmatoxylon, U.S.P. Logwood.—The heart-wood of *Hæmatoxylum campechianum*. Imported from Campeachy, Honduras, and Jamaica.

Characters.—The logs are heavy, hard, purplish-black externally, reddish-brown internally. The chips (which are the officinal form) are reddish-brown, and have often a greenish lustre; they have a feeble, agreeable odour and sweetish taste; a small portion chewed imparts to the saliva a dark pink colour.

Composition.—The colouring principle of logwood is a crystalline substance, **hæmatoxylin.** It is soluble in hot water or alcohol. Logwood also contains **tannic acid,** which imparts to it its astringent properties.

Preparations.

B.P.	Dose.
Decoctum Hæmatoxyli (1 in 20)	1–2 fl. oz.
Extractum „	10–30 gr.
U.S.P.	
Extractum Hæmatoxyli	10–30 gr. (0·65–1·95 gm.)

B.P. Decoctum Hæmatoxyli. Decoction of Logwood.—Logwood, in chips, 1 oz.; cinnamon bark, bruised, 55 gr.; distilled water, 1 pint.

Boil the logwood in the water for ten minutes in a covered vessel, adding the cinnamon towards the end. Strain the decoction, and pour as much distilled water over the contents of the strainer as will make the strained product measure a pint.

Uses.—It is a useful **astringent** in diarrhœa, especially in children. Its great disadvantage is the stain which it imparts to clothing. For the diarrhœa of phthisis, decoctum hæmatoxyli with acidum sulphuricum aromaticum is a good prescription. It is also used in dysentery and in atonic dyspepsia.

Chrysarobinum, Chrysarobin, B. and U.S.P.—*Synonyms*

ARAROBA POWDER; GOA POWDER.—The medullary matter of the tem and branches of *Andira Araroba*, dried and powdered.

CHARACTERS.—A light brownish-yellow, minutely crystalline powder, asteless and inodorous.

SOLUBILITY.—Very sparingly soluble in water, but almost entirely soluble n 150 parts of hot rectified spirit.

REACTIONS.—On heating it melts and partially sublimes in yellow vapours, eaving a charred residue, which entirely disappears on ignition in air. It lissolves in sulphuric acid to form a yellow to orange-red solution, and in olution of caustic potash to form a yellow to reddish fluorescent solution, which becomes carmine by absorption of oxygen from the air.

COMPOSITION.—It contains more or less **chrysophanic acid** according to age and condition, and yielding much chrysophanic acid by oxidation.

DOSE.—$\frac{1}{5}$ to 2 grains.

PREPARATION, B. AND U.S.P.

Unguentum Chrysarobini. Chrysarobin Ointment (Chrysarobin 1, benzoated lard 24, B.P.; Chrysarobin 10, benzoated lard 90, U.S.P.).

USES.—It is used in psoriasis and parasitic affections of the skin. It may be simply applied to the skin moistened with vinegar or saliva, or used in the form of ointment (of the strength of 1 in 50 to 1 in 10). It should never be applied to the head, as it may cause extensive erythema and œdema of the face. It colours both the skin and clothing, and it is better not to use it over too large a surface at a time, as it may cause much irritation. In 2 per cent. ointment it is useful in eczema after exudation has ceased, especially in that of the genitals and anus. It is an excellent application in fissured nipple, and is useful in tylosis of the palms and soles after the epidermis has been removed by salicylic acid plaster (*vide* p. 821). It may also be given internally in eczema, impetigo, acne, psoriasis, urticaria, and other skin diseases.

SUB-ORDER II.—CÆSALPINIÆ.

Senna, U.S.P. SENNA.—The leaflets of *Cassia acutifolia* (Alexandrian senna), and of *Cassia elongata* (Indian senna).

Senna Alexandrina, B.P. ALEXANDRIAN SENNA.—The dried leaflets of *Cassia acutifolia* (*Cassia lanceolata*). Imported from Alexandria, and sometimes in a more or less contaminated condition, in which case the true senna leaflets should be carefully separated from all extraneous matters.

CHARACTERS.—Lanceolate or oval-lanceolate leaflets, about an inch long, *unequally oblique at the base*, brittle, greyish-green, of a faint peculiar odour, and mucilaginous sweetish taste.

Senna Indica, B.P. TINNEVELLY SENNA.—The dried leaflets of *Cassia angustifolia* (*Cassia elongata*). Southern India.

CHARACTERS.—About two inches long, lanceolate, acute, unequally oblique at the base, flexible, entire, green, without any admixture; odour and taste those of Alexandrian senna, in place of which it may be used.

COMPOSITION.—The properties of senna are due principally t a glucoside, **cathartic acid**, which, when isolated, is powerfull purgative.

ADULTERATION.—Of Alexandrian senna, *Solenostemma Argel*; none Tinnevelly senna.



FIG. 189.—Alexandrian Senna, half natural size.



FIG. 190.—Indian Senna, half natural size.

TEST.—Senna-leaves have always an unequally oblique base, and are fre from bitterness. Other leaves are equally oblique at the base.

PREPARATIONS.

B.P.	DOSE.
Confectio Sennæ	60–120 gr.
Infusum „	1–2 fl. oz.
Mistura „ **Composita**	1–1½ fl. oz.
Syrupus „	1 fl. dr. upwards.
Tinctura „	1 fl. dr. to ½ fl. oz.
Pulvis Glycyrrhizæ Compositus	30–60 gr.

U.S.P.	
Confectio Sennæ	60–120 gr.
Extractum Sennæ Fluidum	1 fl. dr. (4 c.c.)
Infusum Sennæ Compositum	2½ fl. oz. (75 c.c.)
Pulvis Glycyrrhizæ Compositus	30–60 gr. (2–4 gm.)
Syrupus Sarsaparillæ Compositus	1–4 fl. dr. (4–16 c.c.)
Syrupus Sennæ	1–4 fl. dr. (4–16 c.c.)

Confectio Sennæ. CONFECTION OF SENNA.—Senna, in fine powder, 7; cori ander, 3; figs, 12; tamarind, 9; cassia pulp, 9; prunes, 6; extract of liquorice, 1 refined sugar, 30; distilled water, up to 75 (B.P.) Senna, 10; coriander, 6; cassi fistula, 16; tamarind, 10; prunes, 7; figs, 12; sugar, 50; water, 60 (U.S.P.).

B.P. Infusum Sennæ. INFUSION OF SENNA.—Senna, 2; ginger, sliced, 1 boiled distilled water, 20.

U.S.P. Infusum Sennæ Compositum. COMPOUND INFUSION OF SENNA. BLACI DRAUGHT.—Senna, 6; manna, 12; sulphate of magnesium, 12; fennel, 2; boilin water, 100. Macerate, strain and make up to 100 with water.

B.P. Mistura Sennæ Composita. COMPOUND MIXTURE OF SENNA.—Sul phate of magnesium, 4; liquid extract of liquorice, 1; tincture of senna, 2½; com pound tincture of cardamoms, 1½; infusion of senna, 15.

Pulvis Glycyrrhizæ Compositus. COMPOUND LIQUORICE POWDER, B. AN U.S.P.—Senna, 2; liquorice root, 2; fennel fruit, 1; sublimed sulphur, 1; sugar 6 (B.P.). Senna, 18; liquorice, 16; fennel, 8; washed sulphur, 8; sugar, 5 (U.S.P.).

Syrupus Sennæ, B. and U.S.P. SYRUP OF SENNA.—Senna, 16 oz.; oil o coriander, 3 min.; refined sugar, 24 oz.; distilled water, 5 pints, or a sufficiency rectified spirit, 3 fl. oz.; distilled water, up to 2 lb. 10 oz. (B.P.). Senna, 33; sugar 60; alcohol, 4; oil of coriander, 1; water up to 100 (U.S.P.).

B.P. Tinctura Sennæ. TINCTURE OF SENNA.—Senna, 2½ oz.; raisins, 2 oz. caraway fruit, ½ oz.; coriander fruit, ½ oz.; proof spirit, 1 pint.

ACTION AND USES.—Senna acts as a **laxative** or brisk pur gative, according to the dose. It acts chiefly on the small intestines, and increases both peristalsis and the secretion. It is frequently combined with other purgatives. A useful remedy in constipation is Mistura Sennæ Co., where we have senna com-

ined with sulphate of magnesium. In habitual constipation, he most convenient preparation, perhaps, is Pulvis Glycyrhizæ Co., which contains sulphur and fennel-seeds as well as enna and liquorice root. One drachm taken every day at bedime will generally keep the bowels regularly open without cting too violently. The sulphur in this preparation is in such mall quantity that it might seem useless; but in a number of xperiments which I made on small quantities (about $\frac{1}{4}$ grain) of ulphur many years ago, I found that they caused an increase of atus in the intestine which appeared to facilitate the expulsion f its contents.

Cassia Fistula. PURGING CASSIA, U.S.P.—The fruit of *Cassia fistula*.

Cassiæ Pulpa, B.P. CASSIA PULP.—The pulp obtained rom the recently imported pods of *Cassia fistula* (the purging assia).

CHARACTERS.—Blackish-brown, viscid, sweet in taste, and somewhat ickly in odour; usually containing the seeds and dissepiments, which should e removed before it is used.

COMPOSITION.—**Sugar**, with **albuminoid matter.**

DOSE.—120 gr. or more.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Confectio Sennæ	60–120 gr.	Confectio Sennæ	1–2 dr. (4–8 gm.)

USE.—A simple **laxative** in doses of 120 gr. upwards. Seldom given alone.

Tamarindus, B. and U.S.P. TAMARIND.—The preserved pulp of the fruit of *Tamarindus indica*. West Indies.

CHARACTERS.—A reddish-brown, sweetish, subacid pulp, preserved in sugar, containing strong fibres, and brown shining seeds, each enclosed in a membranous coat.

COMPOSITION.—The pulp contains **citric, tartaric,** and **acetic acids,** chiefly in combination with **potassium.** Grape-sugar is also present.

IMPURITY.—Traces of copper.

TEST.—A piece of bright iron left in contact with the pulp for an hour does not exhibit any deposit of copper.

DOSE.—$\frac{1}{4}$ oz. and upwards.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Confectio Sennæ	60–120 gr.	Confectio Sennæ	1–2 dr. (4–8 gm.)

USES.—Tamarind, in doses of $\frac{1}{4}$ oz. upwards, is both a **laxative** and **refrigerant.** The pulp is said to weaken the action of resinous cathartics in general, but it is frequently prescribed with them, and is used in the form of compressed tablets, called 'Tamar Indien,' as a vehicle for the administration of some

purgative, probably jalap. A cooling and agreeable drink (tam rind whey) may be made by adding 4 parts of the pulp to 1(of boiling milk, straining and filtering.

Copaiba, B. and U.S.P. COPAIVA, OR COPAIBA, B.P.; BALSA OF COPAIBA, U.S.P.—The oleo-resin obtained by cutting deeply boring into the trunk of *Copaifera Langsdorfii*, and other speci of Copaifera. Valley of the Amazon.

CHARACTERS.—A more or less viscid liquid, about the consistence of oli oil, light yellow, transparent, with a peculiar odour and a persistently bitt and acrid taste.

COMPOSITION.—Copaiva consists of a solution of several **resin** in a **volatile oil.** The resins consist chiefly of crystallisab **copaivic acid.**

IMPURITIES.—Wood oil, or gurjun balsam, and fixed oils, especially cast oil, fraudulently added.

TESTS.—Perfectly soluble in an equal volume of benzene. Does not becon gelatinous after having been heated to 270° F. Is not fluorescent (wood oi After heating on paper it does not leave a greasy ring round the stain (fixed oi

The absence of turpentine is shown by the smell of it not being given on heating, and after distilling off the volatile oil the residue, when coo should be hard and friable (absence of fixed oils). The essential oil distill off from the oleo-resin, when rectified, should not begin to boil below 200° ((392° F.). On adding 1 drop of copaiba to 19 drops of disulphide of carbo and shaking the mixture with 1 drop of a cold mixture of equal parts of su phuric and nitric acids, it should not acquire a purplish red or violet colou (absence of gurjun balsam).

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Oleum Copaibæ	5–20 min.	Massa Copaibæ	10–30 gr.

U.S.P. Massa Copaibæ. MASS OF COPAIBA.—Copaiba, 94; magnesia recent prepared, 6; mix and set aside till it concretes into a pilular mass. If it does n concrete in eight or ten hours, there is deficiency of water in the copaiba. Th may be remedied in subsequent operations by shaking the copaiba with on twentieth of its weight of water and decanting after the uncombined water h subsided. The mass is divided while fresh into pills weighing 5 gr. (0·33 gm each.

Oleum Copaibæ, B. and U.S.P. OIL OF COPAIVA.—A vola tile oil distilled from copaiva.

CHARACTERS.—Colourless or pale yellow, with the odour and taste copaiva.

DOSE.—Of copaiva, 15 min. to 1 fl. dr.; of oil of copaiva 5 min. to 20 min.; of the resin (as a diuretic), 15 to 20 gr. i almond emulsion.

Copaiva may be taken mixed with yolk of egg or floating upo water or some other liquid, or made into pills with burnt mag nesia; or lastly, dissolved in water by the aid of liquor potassæ with which it forms a soap. Sometimes, to hide its disagreeabl taste, it is put into membranous or gelatinous capsules.

ACTION.—Copaiva has a stimulating action on **mucous mem branes**, especially those of the lungs and genito-urinary tract. I is diuretic. Large doses have an **irritant** action, causing vomit

ng and purging. It is **excreted** by the kidneys and lungs, and may be recognised by its characteristic odour. It is very apt to produce an **eruption** of the skin, generally in the form of rose-oloured spots resembling a syphilitic eruption, but distinguished rom it by its affecting chiefly the backs of the arms and legs, by oming on suddenly, and by the intense itching with which it is ccompanied. Sometimes it resembles urticaria more in its ppearance, but rarely it is eczematous. Copaiba forms a con-ugate glycuronic acid in the system, and is eliminated in the rine, which, with nitric acid, gives a precipitate of copaibic cid easily mistaken for albumen, but distinguished by disappear-ng on the application of heat. The conjugate acid renders the rine antiseptic as it is secreted by the kidneys, so that it does not readily decompose, and bacteria either do not appear in it at ll or only in very small numbers, even after the surface has become covered with mould. It is probable that the utility of he drug in diseases of the bladder and urethra is due to the washing out of the urinary passages by the antiseptic urine (p. 446).

Uses.—Copaiba is employed in diseases of the mucous mem-branes, and especially of the genito-urinary passages, the lungs, and, along with digitalis, in cardiac dropsy. It is also useful in chronic bronchitis and bronchorrhœa. Its great disadvantage is its nauseous smell and taste. It is chiefly used in gonorrhœa. It is not advisable to use it when the inflammation is acute and severe, but it is exceedingly useful after the acuteness of the inflammation has subsided. It is not so useful in gleet. It ap-pears to be of service in chronic cystitis. The resin is a good diuretic, especially in cases of dropsy depending on disease of the liver, where the kidneys are healthy.

Piscidia Erythrina. Jamaica Dogwood.—The part used is the bark. Not officinal.

Preparation.

	Dose.
Extractum Piscidiæ Erythrinæ Fluidum	20 min.–2 fl. dr.

Action.—It has been employed for stupefying and catching fish. It is a **narcotic** not only to fish but to frogs, rabbits, and man. It lessens reflex action at first, by stimulation of Setsche-now's centres (p. 165), and afterwards produces tetanus by stimulation of the **spinal cord**. It stimulates the vaso-motor centre, raises **blood-pressure**, and slows the **pulse**. It dilates the **pupil**. It increases the secretion of the **skin** and **saliva**.

Use.—It is employed as a narcotic instead of opium.

Sub-Order III.—MIMOSEÆ.

Acaciæ Gummi, B.P.; Acacia, U.S.P. Gum Acacia, B.P.; Gum Arabic, U.S.P.—A gummy exudation from the stem and

branches of *Acacia Senegal* (*Acacia Verek*), and from other speci of Acacia.

CHARACTERS.—In roundish tears usually from half an inch to an inch length, nearly colourless, brittle, and opaque from numerous minute crac or in angular fragments with shining surfaces. Bland and mucilaginous taste; insoluble in alcohol, but soluble in water. The aqueous solution for with subacetate of lead an opaque white jelly.

COMPOSITION.—Arabin or **arabic acid** (gummic acid) combin with calcium, and, in smaller quantities, with potassium a magnesium.

IMPURITY.—Starch fraudulently added.

TEST.—Should not give a blue colour with iodine.

PREPARATIONS CONTAINING GUM ACACIA.

B.P.	DOSE.	U.S.P.	DOS
Mistura Cretæ	1–2 fl. oz.	Mucilago Acaciæ	ad l
,, Guaiaci	½–2 fl. oz.	Syrupus Acaciæ	,,
Mucilago Acaciæ	ad lib.		
Pulvis Amygdalæ Compositus	60–120 gr.		
,, Tragacanthæ ,,	20–60 gr.		
Trochisci, in all.			

USES.—It is a useful **demulcent** in coughs or sore-throat, al in irritation of the stomach and intestines due to catarrhal i flammation. It is also serviceable in cases of irritant poisonin and it has been employed as a masticatory. The mucilage used to **suspend powders.**

U.S.P. Catechu. CATECHU.—An extract prepared from t wood of *Acacia Catechu*. Pegu.

CHARACTERS.—In dark brown, irregular masses, containing fragments leaves, brittle, somewhat porous and glossy when freshly broken; solu in alcohol and partly soluble in water. It is nearly inodorous, and has strongly astringent and sweetish taste.

It was formerly officinal in the B.P. It is sometimes called black catec to distinguish it from the pale catechu got from *Uncaria Gambier*.

COMPOSITION AND REACTIONS.—It contains a form of tan acid called **catechu-tannic acid.** This differs from other for of tannic acid in not being a glucoside. It gives a greenish-bla colour with iron, and precipitates gelatine but not tartar emet

PREPARATIONS.

U.S.P.	DOSE.
Tinctura Catechu Composita	15 min.–2 fl. dr. (1–8 c.c.)
Trochisci Catechu (1 grain in each)	ad lib.

Tinctura Catechu Composita. COMPOUND TINCTURE OF CATECHU.—Catechu, 1 cinnamon, 8; diluted alcohol to 100.

USES.—It is a powerful **astringent.** It may be employed an injection in gonorrhœa and gleet. The lozenges are useful sore-throat, hoarseness, relaxed uvula, and the tickling cou consequent on it (p. 248). Internally it is useful in diarrhœ and in internal hæmorrhages, especially from the uterus (*vi* also p. 951).

Erythrophlœum. Casca Bark, Sassy Bark. Not officinal.—he bark of *Erythrophlœum gũinense*, a large tree growing on he coast of Africa.

Composition.—It contains an alkaloid, **erythrophlœine.**

Preparation.

	DOSE.
Tinctura Erythrophlœi (1 in 10)	5–10 min.

Action.—The powder when inhaled causes violent sneezing. nternally the infusion or tincture causes vomiting and purging. rythrophlœum has an action on the circulation (p. 273) and dneys like that of **digitalis** (p. 430). The alkaloid appears to mbine the actions of digitalin and picrotoxin, producing con-ılsions like the latter. (Harnack.)

Uses.—I have found it useful in dilated heart without val-ılar disease. It is also useful in mitral disease and dropsy. It as the disadvantage of disturbing the digestion still more readily han digitalis.

Indigo, B.P. C_8H_5NO.—A blue pigment prepared from arious species of Indigofera.

Composition.—Solution of sulphate of indigo.

Use.—As a test for chlorine.

ROSACEÆ.

Sub-Order I.—PRUNEÆ.

Amygdala Dulcis, B. and U.S.P. Sweet Almond.—The ipe seed of the sweet almond tree, *Prunus Amygdalus* (*Amygdalus ommunis*), var. *dulcis*. Imported from Malaga, and known as he Jordan almond.

Characters.—Above an inch in length, lanceolate, acute, with a clear nnamon-brown seed-coat, with a bland sweetish kernel. Does not evolve he odour of bitter almonds when bruised with water.

Composition.—Contains upwards of 50 per cent. of a **fixed** il which consists principally of oleic acid. It contains also an lbuminous substance—**emulsin**, which is supposed to be pro-uced from a vegetable casein and asparagin.

Preparations.

B.P.	DOSE.
leum Amygdalæ	1 fl. dr. to ½ fl. oz.
ulvis Amygdalæ Compositus (almonds 8, sugar 4, gum acacia 1)	60 gr. to 120 gr.
Mistura Amygdalæ (1 of Pulv. Amygd. Co. to 8 of water)	1–2 fl. oz.

U.S.P.	
Mistura Amygdalæ	2 fl. dr.–1 fl. oz. (4–16 c.c.)
yrupus ,,	2 fl. dr.–1 fl. oz. (4–16 c.c.)

Amygdala Amara, B. and U.S.P. Bitter Almond.—The ipe seed of the bitter almond tree, *Prunus Amygdalus* (*Amygdalus ommunis*), var. *amara*. Mogadore.

CHARACTERS.—Resembles the sweet almond in appearance, but is rath broader and shorter; has a bitter taste, and when rubbed with a little wat emits the odour of hydrocyanic acid.

COMPOSITION.—Bitter almonds contain all the constituents sweet almonds, the **fixed oil**, however, being in less proportio and in addition a glucoside **amygdalin** upon which **emuls** (either of sweet or bitter almonds) acts as a ferment produci hydrocyanic acid and volatile oil of bitter almonds, thus:—

Amygdalin. Bitter almond oil. Glucose.

$$C_{20}H_{27}NO_{11} + 2H_2O = HCN + C_7H_6O + C_{12}H_{24}O_{12}$$

Ammonia and formic acid are also produced in the deco position. Amygdalin may be extracted by alcohol, and is n poisonous. Emulsin by boiling loses its property of decompo ing amygdalin.

PREPARATIONS.

B.P.	DOSE.
Oleum Amygdalæ.....	1 fl. dr.–½ fl. oz.

U.S.P.	
Syrupus Amygdalæ.....	2 fl. dr.–2 fl. oz. (7–60 c.c.)

Oleum Amygdalæ, B.P.; Oleum Amygdalæ Expressu U.S.P. ALMOND OIL, B.P.; EXPRESSED OIL OF ALMOND, U.S. A fixed oil expressed from bitter and sweet almonds.

CHARACTERS.—Pale yellow, nearly inodorous or having a nutty odo with a bland oleaginous taste.

PREPARATION.

B.P.	U.S.P.
Oleum Phosphoratum.	Unguentum Aquæ Rosæ
Unguentum Cetacei.	
,, Resinæ.	
,, Simplex, and the preparations containing it.	

U.S.P. Oleum Amygdalæ Amaræ. OIL OF BITTER ALMON A volatile oil obtained from bitter almonds by maceration wi water, and subsequent distillation.

CHARACTERS.—A colourless or yellowish thin liquid of a peculiar aroma odour, a bitter and burning taste and a neutral reaction.

PREPARATION.

	DOSE.
Aqua Amygdalæ Amaræ (oil of bitter almond 1, water 999).....	...Indefinite.

USES.—The fixed oil is **demulcent.** It is applied external to chapped hands and slight excoriations, also to the ear in ea ache. Internally, in doses of 1 drachm to 2 drachms, it is a mi **laxative.** The cake left after the expression of the bland from sweet almonds contains no starch, and is therefore e ployed instead of bread in diabetes. The oil of bitter almonds used as a flavouring agent. The **crude oil** of the U.S.P. co **tains hydrocyanic acid,** and may be used instead of it as a loc application in pruritus, and also for internal administratio

t retains its strength better than pure hydrocyanic acid, but s disadvantage is that the proportion of the acid is not con- tant. It may be given in doses of $\frac{1}{4}$ to 1 minim cautiously ncreased.

Prunum, B. and U.S.P. PRUNE.—The dried drupe of the lum, *Prunus domestica*. Southern Europe.

CHARACTERS.—Oblong, shrivelled, blackish-blue.

COMPOSITION.—**Malic acid**, with **saccharine** and albuminoid natter.

DOSE.—2 oz. or more.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
onfectio Sennæ	1–2 dr.	Confectio Sennæ	1–2 dr.

USE.—Stewed prunes form a useful and pleasant **laxative** for hildren or adults. If they do not move the bowels when simply tewed, they may be stewed along with senna, which does not mpart to the prunes any unpleasant taste, and children will still ake them readily.

U.S.P. Prunus Virginiana. WILD CHERRY.—The bark of *Prunus serotina* (*Cerasus serotina*) collected in autumn.

CHARACTERS.—In curved pieces or irregular fragments, one twelfth of an nch (two millimetres) or more thick, outer surface greenish-brown, or yellowish- rown, smooth and somewhat glossy, marked with transverse scars; if col- ected from old wood and deprived of the corky layer, the outer surface is nut- rown and uneven; the inner surface somewhat striate or fissured. Upon naceration in water it develops a distinct bitter-almond odour; its taste is stringent, aromatic and bitter.

The bark of the small branches is to be rejected.

PREPARATIONS.

	DOSE.
Extractum Pruni Virginianæ Fluidum	30–60 min. (2–4 c.c.)
Infusum ,, ,, ,,	2–3 fl. oz. (60–90 c.c.)
Syrupus ,, ,, ,,	1–4 fl. dr. (4–16 c.c.)

USES.—A nervine **sedative** and **tonic**, used in atonic dys- epsia and general debility, associated with general or local rritation. In large doses it renders the action of the heart low. It has been employed in hectic fever and consumption, nd in functional and organic cardiac disease.

B.P. Laurocerasi Folia. CHERRY-LAUREL LEAVES.—The resh leaves of *Prunus Laurocerasus*.

CHARACTERS.—Ovate-lanceolate or elliptical, distinctly toothed, furnished ith glands at the base, smooth and shining, deep green, on strong short otstalks; emitting a ratafia odour when bruised.

COMPOSITION.—By distillation the leaves yield **bitter-almond** il and **hydrocyanic acid**.

PREPARATION.

DOS

Aqua Laurocerasi (prepared by mixing the leaves, 1 lb., with water 2½ pints, distilling off one pint, and bringing the distillate to the strength of 0·1 per cent. of real hydrocyanic acid by diluting with water, or by adding hydrocyanic acid as required)..... ½–2 fl.

ACTION.—Cherry-laurel water has an action similar to **hydrocyanic acid**, but is only $\frac{1}{20}$th of the strength of the B.P. acid.

USE.—Cherry-laurel water is supposed to be an elegant method of giving prussic acid.

SUB-ORDER II.—**QUILLAJEÆ.**

U.S.P. Quillaia. QUILLAIA. SOAP BARK.—The bark of *Quillaia Saponaria*. Chili.

CHARACTERS.—Flat, large pieces, about one-fifth of an inch (5 millimet thick; outer surface brownish-white, often with small patches of brown c attached, otherwise smooth; inner surface whitish, smooth; fracture sp tery, checkered with pale brownish bast-fibres embedded with white tiss inodorous, very acrid and sternutatory.

COMPOSITION.—It contains a glucoside, **saponin.** Saponin also contained in senega and sarsaparilla. It appears to identical with cyclamin from *Cyclamen europæum* and with mulin from *Primula officinalis*. Digitonin from digitalis appe to be a kind of saponin differing somewhat from the others.

ACTION AND USES.—The bark has little or no application medicine. The powder when snuffed provokes sneezing. infusion and extract are used for cleaning cloth and taking stains. On account of the saponin it contains, the infus froths easily and the froth remains long. A little of it is son times added to syrups, lemonade, or other drinks, to give th a head. It also retains fine powders in suspension and for **emulsions.** It is used to form an emulsion with coal-tar.

Saponin when applied locally acts as a powerful irritant, lo anæsthetic, and muscular poison. On account of its **local ir tant** action, it produces most intense pain when injected su cutaneously; sneezing when applied to the nose; vomiti diarrhœa, and gastro-enteritis when taken internally in la doses. Locally applied it paralyses nerves both sensory a motor, and muscular fibre both voluntary and involuntary. therefore produces **local paralysis** and **local anæsthesia** wh injected under the skin in a frog's leg. The muscles and mo nerves being paralysed, no irritation to either will cause co traction; and the sensory nerves being also paralysed, lo irritation does not produce reflex action. In the volunt **muscles** it produces a condition of *rigor mortis*, and the muscu substance becomes brittle and structureless, as after myositis.

When locally applied to the **intestine,** either by internal ministration or injection into the peritoneal cavity, it paraly the involuntary muscular fibre of the intestinal wall. Wh

pplied to the **heart** it causes rapid stoppage in diastole. It **ounteracts** the effect of **digitalis** on the heart, and *vice versâ* igitalis counteracts the effect of saponin on the heart, so that hen the ventricle of the frog's heart has been brought to a andstill by one of these drugs, its pulsations may be restored y the other.

When absorbed into the circulation, saponin paralyses the **erve-centres** in addition to the nerves and muscular structures. he symptoms it produces depend on the mode in which it is troduced into the body and the structures which it first reaches n consequence. If injected into the jugular vein so as to reach ne heart first, it usually kills by producing cardiac paralysis, ith slow pulse, and rapid fall of blood-pressure, and convulsions hich are probably asphyxial and due to the failure of circulation p. 239), respiratory movements still continuing. Saponin also aralyses the respiratory and vaso-motor centres, so that the lood-pressure falls much and the respirations become feeble and low. In large doses saponin may paralyse the respiratory entre before the heart, so that death ensues from failure of the espiration while the heart continues to beat.

It is possible that quillaia might be used instead of sarsa- arilla, and it might perhaps be useful in cases of aortic disease ith hypertrophy (p. 338).

Sub-Order III.—RUBEÆ.

U.S.P. Rubus. Rubus. Blackberry.—The bark of the oot of *Rubus villosus*, *Rubus canadensis*, and *Rubus trivialis*.

Characters.—In thin, tough, flexible bands, outer surface blackish or lackish-grey, inner surface pale brownish, sometimes with strips of whitish, asteless wood adhering; inodorous; strongly astringent, somewhat bitter.

Preparation.

U.S.P.	Dose.
Extractum Rubi Fluidum	30–60 gr. (2–4 c.c.)

Uses.—It is a pleasant **astringent**, its efficacy being due to annin. It is useful in the diarrhœa of children, and also in dults.

U.S.P. Rubus Idæus. Raspberry.—The fruit of *Rubus dæus*.

Characters.—Deprived of the conical receptacle and therefore hollow at he base; hemispherical, red, finely hairy, composed of from twenty to thirty coalesced small drupes, each one crowned with the withered style; juice red; of an agreeable odour and pleasant acidulous taste.

The closely allied, light red fruit of *Rubus strigosus*, and the purplish- black fruit of *Rubus occidentalis*, may be employed in place of the above.

Preparation.

	Dose.
Syrupus Rubi Idæi	ad lib.

Use.—To give mixtures an agreeable colour and **flavour**.

Sub-Order IV.—ROSEÆ.

Oleum Rosæ, U.S.P. Oil of Rose.—A volatile oil distilled from the fresh flowers of *Rosa damascena*.

Characters.—Pale yellowish, with a strong odour of rose, and a sweetish taste.

Adulterations.—Sandal-wood oil, geranium oil, and other volatile oils; fixed oils; spermaceti.

Test.—When slowly cooled to near 10° C. (50° F.) the oil becomes a transparent solid, interspersed with numerous slender shining iridescent scale-like crystals. When rapidly cooled to 12·5° C. (54·5° F.) it congeals to a solid mass of light feathery shining scales or plates.

Rosæ Centifoliæ Petala, B.P.; Rosa Centifolia, U.S.P. Cabbage-Rose Petals, B.P.; Pale Rose, U.S.P.—The fresh petals, fully expanded, of *Rosa centifolia*. Britain.

Characters.—Pink, fragrant roseate odour; taste sweetish-bitter, and faintly astringent; both readily imparted to water.

Composition.—A minute quantity of **volatile oil**, a red colouring matter, a little **gallo-tannic acid**, fat, sugar, acids, &c.

Preparation.

B.P.	dose.
Aqua Rosæ	ad lib.

U.S.P.	
Aqua Rosæ	ad lib.
Syrupus Sarsaparillæ Compositus	1–4 fl. dr. (3·75–15 c.c.)

U.S.P. Unguentum Aquæ Rosæ. Ointment of Rose Water (Cold Cream).—Expressed oil of almond, 50; spermaceti, 10; white wax, 10; rose water, 30.

Uses.—Rose-water is much used as a **vehicle** for gargles and lotions, and sometimes it is used for internal administration.

Rosæ Gallicæ Petala, B.P.; Rosa Gallica, U.S.P. Red Rose Petals, B.P.; Red Rose, U.S.P.—The fresh and dried petals of *Rosa gallica*, collected before expanding. Britain.

Characters.—Small cones consisting of numerous imbricated deep purple petals, with a roseate odour, and a bitterish, astringent taste.

Composition.—Similar to cabbage-rose petals.

Preparations.

B.P.	dose.	U.S.P.	dose.
Confectio Rosæ Gallicæ	60 gr. or more.	Pilulæ Aloes et Mastiches (p. 523)	1 pil.
Infusum Rosæ Acidum	1–2 fl. oz.	Confectio Rosæ	ad lib.
Syrupus Rosæ Gallicæ	1 fl. dr. or more.	Extractum Rosæ Fluidum	„
		Mel Rosæ	„
		Syrupus Rosæ	„

B.P. Infusum Rosæ Acidum. Acid Infusion of Roses.—Dried red-rose petals, broken up, ¼ oz.; diluted sulphuric acid, 1 fl. dr.; boiling distilled water 10 fl. oz.

B.P. Rosæ Canninæ Fructus. Fruit of the Dog-Rose: Hips.—The ripe fruit of the dog-rose, *Rosa canina*, and other indigenous allied species.

CHARACTERS.—An inch or more in length, ovate, scarlet, smooth, shining; taste sweet, subacid.

COMPOSITION.—Crystallisable **sugar, gum, citric** and **malic acids** free and combined.

PREPARATION.

B.P.	DOSE.
Confectio Rosæ Caninæ	60 gr. or more.

USES.—The preparations of roses are used chiefly as **vehicles.** The Confectio Rosæ Gallicæ and Confectio Rosæ Caninæ are used as bases for pills, and also for linctus. The acid infusion of roses is used as a gargle, and is slightly astringent. Aquæ Rosæ is used as a vehicle.

Cusso, B.P.; Brayera, U.S.P. Kousso, B.P.; Kooso, U.S.P.—The dried panicles (chiefly of the female flowers) of *Hagenia abyssinica* (*Brayera anthelmintica*). Abyssinia.

CHARACTERS.—In bundles, rolls, or compressed clusters consisting of panicles about 10 inches (25 centimetres) long. Flowers small, reddish-brown, on hairy stalks. Odour slight, tea-like, taste bitter and nauseous.

COMPOSITION.—**Tannic acid**; a bitter acrid resin and some **volatile oil** and **kosin** or kousseïn. Kosin is the active principle of the drug. It is a crystalline substance with an acid reaction. Kousseïn is a resinoid substance, and consists of impure kosin.

PREPARATIONS.

B.P.	DOSE.
Infusum Cusso	4–8 fl. oz.

U.S.P.	
Infusum Brayeræ	8 fl. oz. (236 c.c.)
Extractum „ Fluidum	20–40 min. (1·25–2·50 c.c.)

B.P. Infusum Cusso. INFUSION OF KOUSSO.—Kousso, in coarse powder, ½ oz.; boiling distilled water, 4 fl. oz. Infuse in a covered vessel for fifteen minutes without straining.

U.S.P. Infusum Brayeræ. INFUSION OF BRAYERA.—Brayera in No. 20 powder, 6; boiling water, 100. Pour the boiling water on the brayera and let it macerate in a covered vessel until cool. This infusion should be dispensed without straining.

ACTION AND USE.—Cusso is used as an **anthelmintic** for tapeworm. Kosin or coussine, which is the active principle, administered in 20-gr. doses acts quite as well as the infusion, and has not the disadvantage of producing nausea and vomiting, which are sometimes caused by the infusion of the pharmacopœias.

SUB-ORDER V.—POMEÆ.

U.S.P. Cydonium. CYDONIUM. QUINCE SEED.—The seed of *Cydonia vulgaris*.

CHARACTERS.—About a quarter of an inch (6 millimetres) long, oval, or oblong, triangularly compressed, brown, covered with a whitish mucilaginous epithelium, causing the seeds of each cell to adhere. With water the seeds swell up, and form a mucilaginous mass. The unbroken seeds have an insipid taste.

COMPOSITION.—It contains a large amount of **mucilage.**

PREPARATION.

	DOSE.
Mucilago Cydonii (cydonium 2, water 100, macerate for half an hour, and strain through muslin)	ad lib.

USE.—It is useful as a bland **demulcent** preparation t relieve irritation of mucous surfaces.

MYRTACEÆ.

Caryophyllum, B.P.; Caryophyllus, U.S.P. CLOVES.—The dried unexpanded flower-buds of *Eugenia caryophyllat* (*Caryophyllus aromaticus*). East Indies.

CHARACTERS.—About ½ an inch long, dark reddish-brown, plump an heavy, consisting of a nearly cylindrical body surmounted by four teeth an a globular head, with a strong fragrant odour, and a bitter spicy pungen taste. It emits oil when indented with the nail.

COMPOSITION.—Cloves contain a large quantity of **volatile oi resin, gum,** and **tannin.**

PREPARATIONS.

B.P.	DOSE.
Infusum Aurantii Compositum	1–2 fl. oz.
„ **Caryophylli**	1–2 fl. oz.
Mistura Ferri Aromatica	1–2 fl. oz.
Oleum Caryophylli	1–5 min. or more.
Vinum Opii	10–40 min.

U.S.P.	
Oleum Caryophylli	
Tinctura Lavandulæ Compositum	½–2 fl. dr. (2–8 c.c.)
„ Rhei Aromatica	2–4 fl. dr. (8–15 c.c.)
Syrupus „ Aromaticus	1 fl. dr. (4 c.c.)
Vinum Opii	6 min. (0·4 c.c.)

ACTION AND USE.—Stimulant **carminative,** used in flatulenc nausea, and atonic dyspepsia, chiefly given along with othe medicines to afford an agreeable flavour and prevent griping.

Oleum Caryophylli, B. and U.S.P. OIL OF CLOVES.—A volatile oil distilled from cloves.

CHARACTERS.—Colourless when recent, but gradually becoming red-brow having the odour of cloves and a pungent spicy taste.

COMPOSITION.—It consists chiefly of a phenol-like substanc eugenol or **eugenic acid,** which forms permanent salts wit alkalis. With its own bulk of strong solution of potash, the o forms a semi-solid mass.

DOSE.—Of the oil, 2 to 6 drops.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Confectio Scammonii	10–30 gr. or more.	
Pilula Colocynthidis Composita (*v.* 522)		Not given
„ „ et Hyoscyami (*v.* p. 522)	5–10 gr.	

ACTION AND USE.—Same as those of cloves. It has a local **analgesic** action, and is frequently used to relieve toothache by putting a drop on a piece of cotton-wool, and introducing it into the cavity of the tooth.

Pimenta, B. and U.S.P. PIMENTA, B.P.; PIMENTA, U.S.P. ALLSPICE.—The dried unripe full-grown fruit of the allspice tree, *Pimenta officinalis* (*Eugenia Pimenta*). West Indies.



FIG. 191.—Pimenta.

CHARACTERS.—Of the size of a small pea, brown, rough-looking, somewhat like black pepper, but distinguished from it by being crowned with the teeth of the calyx. Odour and taste aromatic, hot, and peculiar.

COMPOSITION.—From 3 to 4 per cent. of a **volatile oil** having the same composition as oil of cloves, also a considerable quantity of **tannin** and some starch.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Aqua Pimentæ	1–2 fl. oz.	Oleum Pimentæ	A few drops.
Oleum „	1–5 min.		

Oleum Pimentæ, B. and U.S.P. OIL OF PIMENTA, B.P.; OIL OF PIMENTA, OIL OF ALLSPICE, U.S.P.—A volatile oil distilled from pimenta.

CHARACTERS.—Colourless or slightly reddish when recent, but becoming brown by age, having the odour and taste of pimenta.

COMPOSITION.—Nearly the same as oil of cloves.

USE.—Same as cloves. The oil may be given in a dose of 2 or 3 drops on a piece of sugar in flatulence.

PREPARATIONS.

B.P.	U.S.P.
None.	Spiritus Myrciæ.

Chekan. CHEKEN. Not officinal.—The leaves and shoots of *Myrtus Chekan* (*Eugenia Chekan*). Chili.

CHARACTERS.—They resemble some buchu leaves (*Barosma betulina*), but have the margin entire and a different smell.

COMPOSITION.—They contain a **volatile oil** resembling that of eucalyptus, a volatile alkaloid—**chekanine**—and **tannin**.

ACTION AND USES.—It is **antiseptic, tonic, expectorant,** and diuretic. The expressed juice diluted with water has been used as a lotion in inflammation of the eye, and a decoction of the bark as an astringent in dysentery. It is chiefly used in catarrh of the mucous membranes, especially those of the bronchi and bladder. It appears to be very useful in cases of bronchitis with thick purulent expectoration, also in cases of phthisis. The oil of myrtle appears to have a similar action.

PREPARATIONS, NOT OFFICINAL.

	DOSE.
Infusum Chekan (1 part leaves to 10 of boiling water)	
Extractum ,, Fluidum (prepared like Ext. Cinchonæ Fluid., U.S.P.)	1–3 fl. dr.
Syrupus ,, (1 part leaves to 2 of syrup)	

Oleum Myrti. OIL OF MYRTLE. Not officinal.—A volatile oil obtained from the leaves of *Myrtus communis*.

DOSE.—0·15 gm. in capsules.

ACTION AND USES.—It has an **antiseptic** action, and may be used in cases of foul ulcers and fœtid discharges from mucous passages, as in otorrhœa. It is not a sufficiently powerful irritant to affect the unbroken skin, but does so when the epidermis is removed. It has been used externally as a **rubefacient** in rheumatism. It causes warmth and increased flow of saliva in the mouth; and in small doses (0·06–0·09 gm.) appears to aid digestion. In larger doses it acts as an **irritant**, causing nausea, flatulent distension, headache, and languor. It is **excreted** in the urine, to which it gives a smell like violets, and like copaiba gives a precipitate when nitric acid is added to the urine. Like copaiba it may be used as an expectorant in chronic bronchitis with profuse expectoration, in phthisis, and in chronic inflammation of the bladder or urethra. (Cf. p. 446.)

Oleum Cajuputi, B. and U.S.P. OIL OF CAJUPUT.—A volatile oil distilled from the leaves of *Melaleuca minor*, B.P. (*M. Cajuputi*, U.S.P.; *M. Leucodendron*). East Indies.

CHARACTERS.—Pale bluish-green, transparent. Odour strong and agreeable; taste, warm and aromatic, leaving a sensation of coldness in the mouth.

IMPURITY.—Copper, added to preserve the fine green colour which the oil possesses when newly distilled or accidentally present.

TEST.—See Copper (p. 674).

DOSE.—1 to 5 min. or more.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Linimentum Crotonis (p. 516)		
Spiritus Cajuputi	½-1 fl. dr.	None.

USES.—It is a powerful **stimulant** and **antispasmodic**. Locally it acts as a stimulant and rubefacient. It is used externally in skin diseases—pityriasis, psoriasis, and acne rosacea. In this last disease it is said to be particularly useful and also in eczema.[1] It has also been used externally, alone, or with olive oil, in cases of muscular and articular rheumatism, and gout. Applied to a carious tooth, it relieves pain in the same way as oil of cloves. Internally it is used to relieve flatulence. A few drops on a piece of sugar are useful in neuralgia and hysteria, and its internal use is said to be also useful in chronic rheumatism.

[1] Claiborne, *Gaillard's Med. Journ.*, Virginia, U.S.A.

U.S.P. Eucalyptus. EUCALYPTUS.—The leaves of *Eucalyptus globulus*, collected from rather old trees.

CHARACTERS.—Petiolate, lanceolately scythe-shaped, from six to twelve inches (fifteen to thirty centimetres) long, rounded below, tapering above, entire, leathery, grey green, glandular, feather-veined between the midrib and marginal veins; odour strongly camphoraceous, taste pungently aromatic, somewhat bitter and astringent.

COMPOSITION.—**Eucalyptol**, resin, tannin, &c.

PREPARATIONS.

	DOSE.
Extractum Eucalypti Fluidum	5–15 min.
Oleum Eucalypti	2–5 drops.

Oleum Eucalypti, B. and U.S.P. OIL OF EUCALYPTUS.—A volatile oil distilled from the fresh leaves of *Eucalyptus globulus*, or *Eucalyptus amygdalina*, and some other species of Eucalyptus.

CHARACTERS.—A colourless or very pale yellowish liquid, having a characteristic aromatic odour, a pungent, spicy, and cooling taste, and a neutral reaction. It is soluble in an equal weight of alcohol.

DOSE.—1 to 4 minims. B.P.

B.P. PREPARATION.

Unguentum Eucalypti (Oil of Eucalyptus, 1; hard paraffin, 2; soft paraffin, 2).

ACTION.—Eucalyptus oil, or eucalyptol, as it is often termed, is a powerful **antiseptic**, even more powerful than quinine (p. 95). The antiseptic action of the oil is greater when it is old and charged with oxygen than when it is freshly distilled. Like quinine (p. 62) it arrests the movements of **white blood-corpuscles**, and its vapour prevents inflammation in the exposed mesentery of the frog. The **red corpuscles** of frog's blood have their nucleus rendered more distinct, and their surface wrinkled by it. Like quinine it causes contraction of the **spleen**. It is a local irritant. When applied to the **skin** and its evaporation prevented, it acts as a rubefacient, vesicant, or pustulant. When applied to a mucous membrane or injected hypodermically it causes pain. When **swallowed** it causes burning in the throat, stomach, and intestine. It may produce nausea, loss of appetite and slight looseness of the bowels, but it is not an active emetic, nor purgative. In large doses after absorption it appears to act chiefly on the **nerve-centres**, producing paralysis and death. In invertebrata killed by exposure to its vapour the paralysis is preceded by excitement, but in vertebrate animals the paralysis is not preceded by excitement. Its depressing action on the **spinal cord** is so great as to abolish reflex action even when it has been previously increased by brucine; and from depression of the **brain, medulla, and heart**, there is drowsiness, feeble respiration, lowered blood-pressure and fall of **temperature**. Death occurs from paralysis

of the respiration. It is **excreted** by the lungs and kidneys. Like turpentine it imparts a smell of violets to the urine of persons taking it.

USES.—It has been employed as an **antiseptic** in surgical dressing in the form of eucalyptus gauze, but is apt to cause local irritation. It has proved useful as a lotion to wash out suppurating cavities. As an inhalation it has been employed to check secretion, and remove fœtor in ozæna, in bronchitis with profuse or fœtid expectoration, in phthisis and in diphtheria. It has been used in the form of injections or pessaries in uterine catarrh, and after parturition. It has been recommended as a hypodermic injection in pyæmia.

In three cases of septicæmia I treated by it recovery occurred during its use, and in one of these quinine had proved useless. It has been used as an **antiperiodic** in ague and an antipyretic in fever, but it has not proved so useful as one would have expected from the resemblance between its action and that of quinine.

Eucalyptus trees when freely planted in malarious districts appear to render them more healthy.

Granati Radicis Cortex, B.P.; Granatum, U.S.P. POMEGRANATE ROOT BARK, B.P.; POMEGRANATE, U.S.P.—The dried bark of the root of *Punica Granatum*. South of Europe.



FIG. 192.—Pomegranate, half the natural size.

CHARACTERS.—In quills or fragments of a greyish-yellow colour externally, yellow internally, having a short fracture, little odour, and an astringent slightly bitter taste.

COMPOSITION.—The most important constituents on which its anthelmintic action depends are two liquid alkaloids, **pelletierine** and **iso-pelletierine**. It contains two other alkaloids which are inactive, **tannin**, mannite, &c.

PREPARATION.

B.P.	DOSE.	U.S.P.
Decoctum Granati Radicis...(2 ounces to 1 pint)...	1–3 fl. oz.	None.

USES.—Pomegranate is chiefly used as an **anthelmintic** for tapeworm. As it is not purgative, but rather astringent, its use must be followed by that of a cathartic. Often, several doses are required. The dose of the tannate of pelletierine is $\frac{1}{2}$–$\frac{3}{4}$ gr. (0·03–0·05 gm.), taken fasting and followed in fifteen minutes by a brisk purgative.

PAPAYACEÆ.

Papayotin. Not officinal. The dried juice of the papaw tree, *Carica papaya*.—**Papain.** A ferment obtained from the juice of *Carica papaya*. The term papain is frequently applied to the dried juice.

PREPARATION.—When scratches are made on the half-ripe fruit of the Carica papaya a milky juice exudes in abundance. When dried it forms a powder somewhat like gum-arabic, and to this the name of papayotin is sometimes given. Papain is the pure ferment associated with a proteid and obtained by precipitation with alcohol and removal of the chief albuminous matters by basic acetate of lead.

DOSE.—5 to 10 grains.

ACTION.—The fruit of the papaw tree has long been used in the West Indies to render beef tender. The unripe fruit is split open and rubbed over the surface of the meat previous to cooking. Its action probably depends upon the fact that papain has a **digestive** action not only upon muscular fibre, but also upon connective tissue. It digests fibrin and albumin in neutral and slightly alkaline solutions. It also rapidly dissolves the false membrane of croup. When injected into the circulation in large doses it paralyses the heart. In smaller quantities it appears to favour the multiplication of micrococci in the blood (p. 85).

USES.—It has been recommended to dissolve the fibrinous membrane in croup and diphtheria, a solution being painted over the pharynx every five minutes. It has also been recommended to destroy epithelioma and warts. Internally it appears to be useful in dyspepsia and catarrhal conditions of the stomach.

CUCURBITACEÆ.

Colocynthidis Pulpa, B.P.; Colocynthis, U.S.P. COLOCYNTH PULP, B.P. COLOCYNTH, U.S.P.—The dried peeled fruit,



FIG. 193.—Colocynth (peeled), half the natural size

freed from seeds, of *Citrullus Colocynthis*. Imported chiefly from Smyrna, Trieste, France, and Spain.

CHARACTERS.—Light, spongy, white or yellowish-white balls, intensely bitter in taste. The pulp from which the seeds have been removed only is officinal.

Composition.—The active principle is a glucoside, **colocynthin** which is soluble in water and alcohol, not in ether. The remaining part of the pulp consists principally of resinous matter.

Dose.—Of the pulp, 2–8 gr.

Preparations.

B.P.	dose.
Extractum Colocynthidis Compositum	3–10 gr.
Pilula Colocynthidis Composita (*vide* p. 522)	5–10 gr.
" " **et Hyoscyami** (*vide* p. 522)	5–10 gr.

U.S.P.	
Extractum Colocynthidis	Seldom used alone.
" " Compositum	5–20 gr.
Pilulæ Catharticæ Compositæ (*vide* p. 523)	1–3 pills.

Extractum Colocynthidis Compositum. Compound Extract of Colocynth, B.P.—Colocynth pulp, 6 oz.; extract of Socotrine aloes, 12 oz.; resin of scammony, 4 oz.; curd soap, in powder, 3 oz.; cardamom seeds, in finest powder, 1 oz.; proof spirit, 1 gallon. An extract of the colocynth is first made, and the mixed with the other ingredients.

In the U.S.P. a simple extract is already officinal, and the proportions are—extract of colocynth, 16 parts; aloes, 50; cardamom, 6; resin of scammony, 14; soap, 14; alcohol, 10.

Physiological Action.—The active principle colocynthin acts as a powerful **cathartic** on the intestines whether swallowed or administered hypodermically, or injected into the circulation. In small doses it increases peristalsis, and the secretions from the intestines and liver. It thus produces watery and mucous motions, frequently accompanied by griping. In large doses it causes gastro-enteritis with mucous and bloody stools. It appears to act also on the urinary system, as Tidy found inflammation of the kidneys and bladder, as well as of the rectum, in dogs poisoned by it; it is said to act as a **diuretic.**

Uses.—It is used in obstinate chronic constipation, especially if there is a tendency to congestion of the brain, as in plethoric people. It is also used in amenorrhœa. It is apt to gripe if given alone; hence it is well to combine it with other purgatives and with sedatives such as hyoscyamus. It may sometimes be advantageously combined with mercurial pill.

B.P. Ecballii Fructus. Squirting Cucumber Fruit.—The fruit, very nearly ripe, of the squirting cucumber, *Ecballium Elaterium*. Britain.

Preparation.

B.P.	dose.
Elaterium	$\frac{1}{16}$–$\frac{1}{2}$ gr.

Characters.—Oval, about 1½ in. long, covered with soft prickles terminating in white points. When ripe the fruits are suddenly detached from the stalk and the juice and seeds expelled.

Composition.—The juice deposits **elaterium.**

B.P. Elaterium. ELATERIUM. (*Synonym*: Extractum Elaerii).—A sediment from the juice of the squirting cucumber ruit.

PREPARATION.—Expressing the juice, separating the deposit by straining, nd drying by a gentle heat on porous tiles.




FIG. 194.—Elaterium.

CHARACTERS.—In cakes, about $\frac{1}{10}$th inch thick, light, friable, slightly inurved, greenish-grey, tea-like smell, acrid and bitter.

COMPOSITION. — Elaterium is composed of **elaterin**, with tarch and fibrous and colouring matters.

IMPURITIES.—Chalk and earthy matter fraudulently added.

TESTS.—Does not effervesce with acids (absence of chalk), yields half its eight to boiling rectified spirit. It should yield 25 per cent. or not less than 0 per cent. of elaterin.

DOSE.—$\frac{1}{16}$th to $\frac{1}{2}$ gr.

PREPARATION, B. AND U.S.P.

Elaterinum.

Elaterinum, B. and U.S.P. ELATERIN. $C_{20}H_{28}O_5$.—The ctive principle of elaterium. It may be obtained by exhausting elaterium with chloroform, adding ether to the chloroform olution, collecting the precipitate, washing the latter with ether, nd purifying by recrystallisation from chloroform.

CHARACTERS.—A chemically neutral substance with a bitter taste. In mall colourless crystals.

SOLUBILITY.—It is insoluble in water, sparingly soluble in rectified spirit.

REACTIONS.—When heated it melts and burns without residue. With nelted carbolic acid it yields a solution which, on the addition of sulphuric cid, acquires a crimson colour rapidly changing to scarlet. It is not preipitated from solution by tannic acid, nor by the salts of mercury or of latinum.

DOSE.—$\frac{1}{40}$ to $\frac{1}{10}$ gr.

PREPARATIONS.

B.P.	DOSE.
Pulvis Elaterini Compositus (elaterin, 1; sugar of milk, 39).....	$\frac{1}{2}$–5 gr.
U.S.P.	
Trituratio Elaterini (1 gr. elaterin, 9 gr. sugar of milk)	$\frac{1}{2}$–$\frac{3}{4}$ gr.

ACTION AND USES.—Elaterin is the most **powerful hydragogue cathartic** we possess, increasing the peristaltic action and low of fluid from the intestines. It only acts as a purgative when taken internally, and appears to require bile in order to act. When injected subcutaneously it acts on the **nervous system**, causing salivation, insensibility, tetanus, and dyspnœa. It is used in dropsies, especially those affecting the abdominal cavity and due to cirrhosis of the liver. It is also used as a

depletory in cerebral affections. It is usually combined wit henbane and volatile oils, as it is apt to gripe. In large doses may cause gastro-enteritis and fatal collapse, and should given with care to old or feeble persons.

U.S.P. Pepo. PUMPKIN SEED.—The seed of *Cucurbita Pep*

CHARACTERS.—About ¾ inch long, broadly ovate, flat, whitish, near smooth, with a shallow groove parallel to the edge; inodorous, bland, a oily.

COMPOSITION.—It is probable that the active principle is **resin** contained in the endopleuron or greenish envelope imm diately surrounding the embryo. This resin is dissolved an rendered more active by castor oil, which should be given befo and after the anthelmintic. The decorticated seeds, as well the oil derived from them, are bland and unirritating.

DOSE.—An ounce or an ounce and a half. The seeds may crushed, and flavoured with some aromatic oil.

USES.—It is an excellent **anthelmintic** for the removal tapeworm. It should be given the first thing in the mornin after a very light supper, and should be followed in two or thr hours by an active purgative. No solid food should be take until two hours after the purgative.

U.S.P. Bryonia. BRYONIA. BRYONY.—The root of *Bryon alba*, and of *Bryonia dioica*.

CHARACTERS.—In transverse sections about two inches (5 centimetre in diameter, the bark grey-brown, rough, thin, the central portion whitish greyish, with numerous small wood-bundles arranged in circles and proje ing, radiating lines; inodorous, taste disagreeably bitter.

PREPARATION.

	DOSE.
Tinctura Bryoniæ	2–10 fl. dr.

COMPOSITION.—It contains a bitter principle, **bryonin**.

USE.—Its chief use was that of a **hydragogue cathartic**, b it is now superseded by jalap.

UMBELLIFERÆ.

SUB-ORDER I.—CAMPYLOSPERMÆ.

B.P. Conii Folia. HEMLOCK LEAVES.—The fresh leaves an young branches of *Conium maculatum*; gathered from wild Britis plants when the fruit begins to form.

CHARACTERS.—Fresh leaves, smooth, arising from a smooth stem wit dark purple spots; dried leaves of a full green colour and characteris mousy odour. The leaf rubbed with solution of potash gives out strongl the odour of coniine.

COMPOSITION.—The fresh leaves and branches contain th same alkaloids as the fruits, **coniine** and **methyl-coniine** (*q.v.*)

although in smaller proportion, while the coniine is sometimes accompanied by a third alkaloid, **conhydrine**. These principles are lost when the leaves are dried or heated, both being highly volatile.

DOSE.—Of the powdered leaf, 2–8 gr.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Cataplasma Conii (from succus)	For external use.	None.
Extractum Conii (green extract)	2–6 gr. or more.	
Succus Conii (juice of hemlock)	30 min. to 2 fl. dr. or more.	
Vapor Coninæ	*vide infra.*	
Pilula Conii Composita (*vide* p. 522)	5–10 gr.	

B.P. Cataplasma Conii. HEMLOCK POULTICE.—Juice of hemlock, 1; linseed meal, 4; boiling water, 10.

B.P. Vapor Coninæ. INHALATION OF CONINE.—Juice of hemlock, ½ fl. oz.; solution of potash, 1 fl. dr.; distilled water, 1 fl. oz. Put 20 min. of the mixture on a sponge in an inhaler containing hot water.

Conii Fructus, B.P. HEMLOCK FRUIT.—The fruit of *Conium maculatum* (spotted hemlock), gathered when fully developed, but while still green, and carefully dried.



FIG. 195.—Conium.

CHARACTERS.—About one-eighth of an inch long, broadly ovate compressed laterally; half-fruit with five waved or crenated ridges. Reduced to powder and rubbed with solution of potash, they give out strongly the odour of coniine.

Conium, U.S.P. HEMLOCK.—The full-grown fruit of *Conium maculatum*, gathered while yet green.

CHARACTERS.—Similar to those of hemlock fruit, B.P.

COMPOSITION.—**Coniine**, a poisonous alkaloid, occurs in hemlock as a yellow, oily liquid, and is separated by distilling the fruit with slightly alkaline water. The fruit contains **methyl-coniine** in varying proportion, and a small quantity of **volatile oil**, which does not appear to be poisonous.

PREPARATIONS.

B.P.	DOSE.
Tinctura Conii	20–60 min.

U.S.P.	
Abstractum Conii	7–8 gr.
Extractum Conii Alcoholicum	2 gr.
Extractum Conii Fluidum	15 min.
Tinctura Conii	60 min.

PHYSIOLOGICAL ACTION.—The action of conium depends on the alkaloids, coniine and methyl-coniine, which it contains; and as

their action differs considerably and the relative quantity of eac varies, contradictory results have been obtained by differer observers. The symptoms of conium-poisoning are weakness the legs and staggering gait, passing on to paralysis, whic gradually progresses upwards and finally causes death by failu of respiration. The mind remains clear to the last. **Coniïn** paralyses the ends of the motor nerves and of the vagus, lik curare, and afterwards paralyses the motor centres in the brai and spinal cord. It causes death by paralysing the respirator muscles. Death is usually accompanied by convulsions i warm- but not in cold-blooded animals. There is dilatation the pupil, and ptosis from paralysis of the endings of the thir nerve. Locally applied, it appears to paralyse the ends sensory nerves.

Methyl-coniïne acts on the spinal cord, causing paralysis reflex action.

Dimethyl-coniïne and conhydrine have an action similar t that of coniïne, but less powerful.

Uses.—It is used locally as a poultice to soothe pain i cancer and ulcers, and as a vapour to relieve cough in bron chitis and pertussis. It is used to allay muscular spasm i chorea, mercurial tremor, and paralysis agitans, but is useless i tetanus and strychnine-poisoning. The best preparation to us is the succus in doses of one drachm, gradually increased as th patient becomes tolerant of the drug.

Sub-Order II.—ORTHOSPERMÆ.

Asafœtida, B. and U.S.P. Asafœtida, B.P.; Asafetid U.S.P.—A gum-resin obtained from the root of *Ferula Narthe* (*Narthex Asafœtida*) and *F. Scorodosma* and probably othe species. Afghanistan and the Punjaub.

Characters.—In irregular masses, composed of whitish tears, which a embedded in a yellowish-grey or brownish-grey sticky mass. The tears, whe hard, break with a conchoidal fracture, showing a milk-white colour whic changes gradually, on exposure, to pink, and finally to brown. Taste bitte acrid; odour fœtid, alliaceous. The fresh fracture touched with nitric aci becomes green temporarily.

Composition.—**Volatile oil,** resin, and gum. The oil contai a very large proportion of **sulphur.**

Test.—It dissolves almost entirely in rectified spirit, B.P.; 60 per cen soluble in alcohol, U.S.P.

Dose.—Of the gum-resin, 5-30 gr. or more.

Preparations.

B.P.	dose.
Enema Asafœtidæ	*vide infra.*
Pilula Aloes et Asafœtidæ (*vide* p. 522)	4–10 gr.
Pilula Asafœtidæ Composita (*vide* p. 522)	5–15 gr.
Spiritus Ammoniæ Fœtidus	½–1 fl. dr.
Tinctura Asafœtidæ	½–1 fl. dr. or more.

U.S.P.	DOSE.
Emplastrum Asafœtidæ	for external use.
Mistura Asafœtidæ	4–8 fl. dr.
„ Magnesiæ et Asafœtidæ	4 fl. dr.
Pilulæ Asafœtidæ (3, soap 1, *vide* p. 523)	1–3 pills.
„ Aloes et Asafœtidæ (*vide* p. 523)	2–5 pills.
„ Galbani Compositæ (*vide* p. 523)	2–4 pills.
Tinctura Asafœtidæ	30 min. to 1 fl. dr.

B.P. Enema Asafœtidæ. Enema of Asafœtida (Enema Fœtidum).—safœtida, 30 gr.; distilled water, 4 fl. oz. Rub the asafœtida in a mortar with ne water added gradually, so as to form an emulsion.

U.S.P. Mistura Asafœtidæ. Asafœtida Mixture.—Rub asafœtida, 4, with ater, 100.

U.S.P. Mistura Magnesiæ et Asafœtidæ. Mixture of Magnesia and Asafœ-ida (Dewee's Carminative). Carbonate of magnesium, 5; tincture of asafœtida, 7; ncture of opium, 1; sugar, 10; distilled water up to 100.

B.P. Spiritus Ammoniæ Fœtidus. Fœtid Spirit of Ammonia.—Asafœ-ida, 1½ oz.; strong solution of ammonia, 2 fl. oz.; rectified spirit up to 1 pint.

Uses.—It is used as a stimulant, **anti-spasmodic,** and **car-minative.** It is useful in hysteria, especially that occurring bout the menopause.

It is an exceedingly useful remedy in the form of enema for ympanites, but on account of its disagreeable odour is not much sed for flatulent distension of the stomach. It is given as a **timulating expectorant** in cases of chronic bronchitis and ertussis.

Galbanum, B. and U.S.P. Galbanum.—A gum-resin, de-ived from *Ferula galbaniflua*, *Ferula rubricaulis*, and probably ther species. India and the Levant.

Characters.—In tears about the size of a pea, or more commonly in masses formed by their agglutination; greenish-yellow or pale brown ex-ernally, milky-white internally, translucent, having a strong disagreeable dour, and an acrid, bitter taste.

Composition.—**Gum resin** and **volatile oil.**

Dose.—10–30 gr. or more.

Preparations.

B.P.	DOSE.
Emplastrum Galbani	for external use.
Pilula Asafœtidæ Composita (*vide* p. 522)	5–15 gr.

U.S.P.	
Emplastrum Asafœtidæ, „ Galbani	for external use.
Pilulæ Galbani Compositæ (*vide* p. 523)	2–4 pills.

U.S.P.—Pilulæ Galbani Compositæ. Compound Pills of Galbanum (*vide* p. 523). This pill is much like the compound asafœtida pill, B.P., but contains less asafœ-tida.

Uses.—It has little antispasmodic power, but is a **stimulant expectorant,** used in chronic bronchitis with much wheezing and abundant discharge, as it lessens secretion. It is also used locally as a stimulant to inflamed joints.

Ammoniacum, B. and U.S.P. Ammoniacum, B.P.; Ammo-

NIAC, U.S.P.—A gum-resinous exudation from the stem, aft being punctured by beetles, of *Dorema Ammoniacum*. Persia an the Punjaub.

CHARACTERS.—In roundish tears or irregular masses formed by their a glomeration without any intervening dark-coloured substance. The tears a roundish, pale yellowish-brown externally, milk-white internally, brittl Peculiar odour, bitter, acrid, nauseous taste. It is coloured yellow by caust potash, and a solution of chlorinated soda gives it a bright orange hue.

COMPOSITION.—**Gum resin** and **volatile oil.**

DOSE.—10 to 30 grains.

PREPARATIONS.

B.P.	DOSE.
Emplastrum Ammoniaci cum Hydrargyro	for external use.
,, Galbani	
Mistura Ammoniaci (¼ oz., water 8 fl. oz.)	½–1 fl. oz.
Pilula Scillæ Composita (*vide* p. 523)	
,, Ipecacuanhæ cum Scilla (*vide* p. 522)	

U.S.P.	
Emplastrum Ammoniaci	for external use.
,, ,, cum Hydrargyro	for external use.
Mistura Ammoniaci (4, water 100)	2 fl. dr. or more.

USE.—It is used for the **same** purposes as **galbanum,** chiefl as a stimulant to the mucous membrane in bronchorrhœa.

Fœniculi Fructus, B.P.; Fœniculum, U.S.P. FENNE FRUIT, B.P.; FENNEL, U.S.P.—The fruit of *Fœniculum capilla ceum*, B.P. (*F. vulgare*, U.S.P.) Malta.



FIG. 196.—Fennel.

CHARACTERS.—Longer than conium fruit, being about one-quarter of a inch long. Slightly curved, elliptical, longitudinal ribs, the two lateral bein double; taste and odour aromatic. The footstalk is often attached.

COMPOSITION.—A **volatile oil,** having the same composition a oil of anise.

PREPARATIONS.

B.P.	DOSE.	U.S.P.
Aqua Fœniculi (1 lb. to 1 gallon)	1–2 fl. oz.	None.
Pulvis Glycyrrhizæ Compositus (*vide* p. 910)		

USE.—It is stimulant and **carminative,** used to relieve flatu lence, and lessen the griping of purgatives.[1]

[1] I am informed that the wild fennel growing in South Africa will completel drive away fleas from kennels and stables, and powdered fennel has a similar effec in this country.

Oleum Fœniculi, U.S.P. Oil of Fennel.—A volatile oil, distilled from fennel.

Characters.—Colourless or yellowish, with the odour of fennel, and a sweetish, warm taste. Sp. gr. not less than 0·960. Concretes between 5° and 10° C. (41° and 50° F.).

Solubility.—Soluble in an equal weight of alcohol.

Composition.—Oil of fennel consists chiefly of **anethol** (anise-camphor), $C_{10}H_{12}O$, which exists both in a solid and liquid form. There is also a smaller proportion of an oil isomeric with oil of turpentine.

Preparations.

	dose.
Aqua Fœniculi	Indefinite.
Spiritus Juniperi Compositus	2–4 fl. dr. (8–16 c.c.)

Use.—The same as that of oil of anise.

Anisi Fructus, B.P.; Anisum, U.S.P. Anise Fruit, B.P.; Anise, U.S.P.—The fruit of *Pimpinella Anisum*.

Characters.—About $\frac{1}{8}$ of an inch (4 millimetres) long, ovate. It has an agreeable aromatic odour, and a sweet, spicy taste. It may be distinguished from conium fruit, which it somewhat resembles, and which has been mistaken for it, by the conium fruit consisting usually of single mericarps, which are smooth-grooved upon the face and have crenate ridges and no oil-tubes.

Preparations.

B.P.	dose.
Aqua Anisi	
Oleum „	1–4 min.
U.S.P.	
Oleum Anisi	2–5 min.

Oleum Anisi, B. and U.S.P. Oil of Anise.—A volatile oil distilled in Europe from anise fruit or in China from the star anise fruit (p. 840).

Characters.—Colourless or pale yellow; with the odour of anise, and a warm, sweetish taste. Concretes at 10° to 15° C. (50°–59° F.). Oil of illicium has nearly the same properties, except that it congeals at 2° C. (35·6° F.).

Composition.—The same as that of oil of fennel.

Dose.—2–5 min.

Preparations.

B.P.	dose.
Essentia Anisi	10–20 min.
Tinctura Camphoræ Composita	15 min.–1 fl. dr.
Tinctura Opii Ammoniata	$\frac{1}{2}$–1 fl. dr.
U.S.P.	
Aqua Anisi	Indefinite.
Spiritus Anisi	1–2 fl. dr.
Tinctura Opii Camphorata	1–2 fl. dr.
Trochisci Glycyrrhizæ et Opii	1–3 troches.

Use.—It is an aromatic stimulant **carminative**, and is used as an adjunct to purgatives to lessen griping.

B.P. Anethi Fructus. Dill Fruit.—The dried fruit of *Peucedanum graveolens* (*Anethum graveolens*). England, or middle and Southern Europe.



Fig. 197.—Dill.

Characters.—Oval, flat, about a line and a half in length, and easily distinguished by its membranous wings. Aromatic taste and odour.

Composition.—Contains a **volatile oil.**

Preparations.

B.P.	Dose.	U.S.P.
Aqua Anethi	1–2 fl. oz. (for infants, 1–2 fl. dr.)	None.
Oleum Anethi	1–4 min.	

B.P. Oleum Anethi. Oil of Dill.—A volatile oil distilled from the fruit.

Characters.—Pale yellow colour, aromatic odour, sweetish taste.

Use.—The chief use of dill water is in the flatulence of children in one-drachm doses. It is stimulant and **carminative.**

Carui Fructus, B.P.; Carum, U.S.P. Caraway Fruit, B.P.; Caraway, U.S.P.—The dried fruit of *Carum Carui*, B.P. (*Carum Carvi*, U.S.P.).



Fig. 198.—Caraway.

Characters.—Fruit usually separating into two mericarps about one sixth inch long, curved, tapering at each end, brown, with five paler longitudinal ridges; having an agreeable aromatic odour and spicy taste.

Composition.—A volatile oil, which consists of a hydrocarbon **carvene,** and an **oxygenated oil** identical with that obtained from oil of dill.

Preparations.

B.P.	Dose.
Aqua Carui	1–2 fl. oz.
Oleum Carui	1–4 min.
Confectio Opii	5–20 gr.
Confectio Piperis	60–120 gr.
Pulvis Opii Compositus	2–5 gr.
Tinctura Cardamomi Composita	½–2 fl. dr.
Tinctura Sennæ	1–4 fl. dr.

U.S.P.	DOSE.
Oleum Cari	2–5 min.
Spiritus Juniperi Compositus	2–4 fl. dr.

Oleum Carui, B.P.; Oleum Cari, U.S.P. OIL OF CARAWAY. The oil distilled in Britain from caraway fruit, B.P. A volatile oil distilled from caraway, U.S.P.

CHARACTERS.—Colourless or pale yellow, odour aromatic, taste spicy, and neutral reaction. It is soluble in an equal weight of alcohol.

PREPARATIONS.

B.P.

Confectio Scammonii, 2 parts in 150 nearly.
Pilula Aloes Barbadensis (*vide* p. 522).

U.S.P.

Spiritus Juniperi Compositus.

USE.—**Carminative** and stimulant. Used with purgatives to lessen griping and to relieve flatulence.

Sumbul Radix, B.P.; Sumbul, U.S.P. SUMBUL ROOT, B.P.; SUMBUL, U.S.P.—The dried transverse sections of the root of *Ferula Sumbul*. Imported from Russia and India.

CHARACTERS.—Cylindrical pieces, varying considerably in diameter and thickness. They are covered on the outer edge with a dusky brown rough bark, frequently beset with short, bristly fibres. The cut surface looks like felt from the interior of the root consisting of easily separated fibres. It has a strong odour, resembling that of musk. The taste is at first sweetish, becoming after a time bitterish.

COMPOSITION.—A **resin** soluble in ether, and a small quantity of an **essential oil.**

PREPARATIONS.

B.P.	DOSE.
Tinctura Sumbul (2½ oz. in 1 pint)	10–60 min.

U.S.P.	
Tinctura Sumbul (10 per cent.)	1–4 fl. dr.

USE.—Sumbul is said by some to be of little service; however, it seems useful in the malady for which it is usually prescribed, viz., **hysteria** and nervous conditions occurring in females in feeble health or recovering from an acute disease.

SUB-ORDER III.—**CŒLOSPERMÆ.**

Coriandri Fructus, B.P.; Coriandrum, U.S.P. CORIANDER FRUIT, B.P.; CORIANDER, U.S.P.—The dried ripe fruit of *Coriandrum sativum*.



FIG. 199.—Coriander.

CHARACTERS.—Globular, nearly as large as white pepper, beaked, finely ribbed, yellowish-brown; has an agreeable aromatic odour and flavour.

COMPOSITION.—Contains **volatile** and **fixed oils.**

PREPARATIONS.

B.P.	DOSE.
Confectio Sennæ	60–120 gr.
Oleum Coriandri	2–5 min.
Syrupus Rhei	1–4 fl. dr.
Tinctura Rhei	1–8 fl. dr.
Tinctura Sennæ	1–4 fl. dr.

U.S.P.	
Oleum Coriandri	2–5 min.

Oleum Coriandri, B. and U.S.P. OIL OF CORIANDER.—A volatile oil distilled from coriander.

CHARACTERS.—A colourless or yellowish liquid, having the characteristic aromatic odour of coriander, a warm spicy taste, and a neutral reaction.

DOSE.—2 to 5 min.

PREPARATION.

B.P.	DOSE.
Syrupus Sennæ	1–4 fl. dr.

USE.—**Carminative** and stimulant. Used as an adjunct to purgatives.

CORNACEÆ.

U.S.P. Cornus. CORNUS. DOGWOOD.—The bark of the root of *Cornus florida.*

CHARACTERS.—In curved pieces of various sizes, about one-eighth of an inch (3 millimetres) thick; deprived of the furrowed, brown-grey, corky layer; outer and inner surface pale-reddish, or light reddish-brown, striate; transverse and longitudinal fracture short, whitish, with brown, yellow striæ; inodorous; astringent and bitter.

DOSE.—20 to 60 gr. (1–4 gm.)

PREPARATION.

	DOSE.
Extractum Cornus Fluidum	1 fl. dr.

COMPOSITION.—It contains a **bitter** neutral **principle.**

ACTION.—It acts as an **astringent tonic** and feeble stimulant to the stomach. It was formerly used in ague and malarious conditions, and a resinoid substance obtained from it by alcohol is popularly called **dogwood-quinine.**

CHAPTER XXXIV.

Class II.—DICOTYLEDONES GAMOPETALÆ.

(COROLLIFLORÆ).

CAPRIFOLIACEÆ.

B.P. Sambuci Flores. Elder Flowers.—The fresh flowers of *Sambucus nigra*. From indigenous plants.

Characters.—Flowers small, white, fragrant, crowded in large cymes.

U.S.P. Sambucus. Elder.—The flowers of *Sambucus canadensis*.

Characters.—In level tipped cymes, cream-coloured, odour peculiar, taste sweetish, aromatic, slightly bitter.

Composition.—A small amount of a light **essential oil.**

	Preparation.	
B.P.	dose.	U.S.P.
Aqua Sambuci	1–2 fl. oz.	None.

Use.—Elder-flower water is used as a **vehicle** in collyria and lotions.

U.S.P. Viburnum. Viburnum. Black Haw.—The bark of *Viburnum prunifolium*.

Characters.—In thin pieces or quills, glossy purplish-brown, with scattered warts, and minute black dots; when collected from old wood, greyish-brown; the thin, corky layer easily removed from the green layer; inner surface whitish, smooth; fracture short; inodorous; somewhat astringent and bitter.

Preparation.	dose.
Extractum Viburni Fluidum	30–60 min.

Uses.—It is said to be useful in preventing threatened abortion, and in **dysmenorrhœa.** Its action is not well understood.

RUBIACEÆ (CINCHONACÆ).

Sub-Order I.—CINCHONEÆ.

B.P. Cinchona Cortex. Cinchona Bark.—The dried bark of *Cinchona Calisaya*, *Cinchona officinalis*, *Cinchona succirubra*, *Cinchona lancifolia*, and other species of cinchona from which the peculiar alkaloids of the bark may be obtained.

B.P. Preparations.

Cinchoninæ Sulphas. **Quininæ Hydrochloras.**
Cinchonidinæ Sulphas. „ **Sulphas.**

(Salts of quinine and cinchonine may also be obtained fro some species of Remijia, DC.)

U.S.P. Cinchona. CINCHONA.—The bark of any species cinchona containing at least 3 per cent. of its peculiar alkaloi

PREPARATION.

U.S.P.	DOSE
Infusum Cinchonæ (cinchona in powder 6, aromatic sulphuric acid 1, water q.s. to make 100 parts by percolation)	1–2 fl. d



FIG. 200.—Bark of *Cinchona officinalis*, half the natural size.

U.S.P. Cinchona Flava. YELLOW CINCHONA (CALISA BARK), U.S.P.—The bark of the trunk of *Cinchona Calisay*



FIG. 201.—Cinchona Calisaya Bark, half the natural size.

containing at least 2 per cent. of quinine. Collected in Boliv and Southern Peru.

CHARACTERS.—In flat pieces, or quills. The flat pieces are recognised their tawny yellow colour, and by the long channelled depressions left on t outer side of the bark by the gouge with which the epidermis has been moved. Transverse fracture shows numerous very rigid glistening fibr short and very fibrous. Powder cinnamon-brown, somewhat aromatic, p sistently bitter.

U.S.P.	PREPARATIONS.	DOSE.
Extractum Cinchonæ		8–15 gr.
,, ,,	Fluidum	30–60 min.
Tinctura Cinchonæ		1–2 fl. dr.

Cinchonæ Rubræ Cortex, B.P.; Cinchona Rubra, U.S. RED CINCHONA BARK. RED CINCHONA.—The dried bark of t stem and branches of cultivated plants of *Cinchona succirubra*.



FIG. 202.—Red Cinchona, half the natural size.

CHARACTERS.—In quills or incurved pieces, coated with the periderm outer surface brown or reddish-brown, rough, fissured or warty; inner surfa redder; fractured surface often approaching to brick-red; transverse fractu finely fibrous; powder red-brown; taste bitter and astringent.

ADULTERATION.—Some of the brown and red inferior barks are occasional substituted.

TEST.—When used for purposes other than that of obtaining the alkaloids their salts, it should yield between five and six per cent. of total alkaloids, which not less than half shall consist of quinine and cinchonidine.

PREPARATIONS.

B.P.	STRENGTH.	DOSE.
Decoctum Cinchonæ	27½ gr. to 1 fl. oz.	1–2 fl. oz.
Extractum Cinchonæ Liquidum	about 1 oz. to 1 fl. oz.	5–10 min.
Infusum Cinchonæ Acidum	22 gr. to 1 fl. oz.	1–2 fl. oz.
Mistura Ferri Aromatica	1 oz. to 16 fl. oz.	1–2 fl. oz.
Tinctura Cinchonæ	88 gr. to 1 fl. oz.	½–2 fl. dr.
" " **Composita**	2 oz. to 1 pint.	½–2 fl. dr.

U.S.P.

Tinctura Cinchonæ Composita ..... 1–4 fl. dr. (4–16 c.c.)

B.P. Tinctura Cinchonæ Composita. COMPOUND TINCTURE OF CINCHONA. ed cinchona bark, 2 oz.; bitter orange peel, 1 oz.; serpentary, ½ oz.; saffron, gr.; cochineal, 30 gr.; proof spirit, 1 pint.

U.S.P. Tinctura Cinchonæ Composita. COMPOUND TINCTURE OF CINCHONA.—ed cinchona, 10; bitter orange peel, 8; serpentaria, 2; glycerin, 10; alcohol d water (in the proportion of 8 of the former to 1 of the latter), q.s. to make 100.

PROPERTIES AND COMPOSITION OF THE CINCHONA BARKS.—he cinchona barks contain varying quantities of the following lkaloids:—**Cinchonine** ($C_{20}H_{22}N_2O$), **cinchonidine** ($C_{19}H_{22}N_2O$), uinine ($C_{20}H_{24}N_2O_2$), **quinidine** ($C_{20}H_{24}N_2O_2$), **quinamine** ($C_{19}H_{24}$ $_2O_2$), **conquinamine** ($C_{19}H_{24}N_2O_2$).

Both the total quantity of alkaloids and the relative proportions of each vary considerably in the barks of the different pecies of cinchona.

By heating solutions of the cinchona alkaloids with excess of mineral acid they may be converted into amorphous isomeric lkaloids. Quinine yields quinicine, and cinchonine is converted nto cinchonicine.

In addition to the alkaloids, the cinchona barks contain certain acid principles. These are:—(1) **Quinic** or **chinic acid**, oluble in water and alcohol, but sparingly so in ether. On oxiation it yields quinone or chinone. (2) **Cincho-tannic acid.** 3) **Quinovic acid.**

Cinchona bark also contains **quinovin**, which by means of ydrochloric acid is resolved into quinovic acid and an uncrytallisable sugar. It also contains **cinchona-red**, which is a olouring matter abundantly found in the red bark.

DISTINGUISHING TESTS FOR CINCHONA ALKALOIDS.

	Solution	Chlorine water and Ammonia	Polarised Light	Solubility in Ether	Solubility in excess of Ammonia
Quinine .	Fluorescent	Green .	Left .	Readily .	Readily
Quinidine .	Fluorescent	Green .	Right .	Readily .	Sparingly
Cinchonine .	Not	Not .	Right .	Almost insoluble .	Almost insoluble
Cinchonidine .	Not	Not .	Left .	Sparingly .	Almost insoluble

U.S.P. Quinina. QUININE. $C_{20}H_{24}N_2O_2.3H_2O$ (crystallised); 378.—An alkaloid prepared from different species of cinchona.

PREPARATION.—By adding to the solution of the sulphate a quantity water of ammonia or solution of soda, just sufficient to precipitate the alkaloi

Although it is not separately mentioned in the B.P., it is used in the preparati of citrate of iron and quinine.

PREPARATIONS.

U.S.P.	DOSE.
Ferri et Quininæ Citras	3–5 gr.
Liquor Ferri et Quininæ Citratis	8–45 min.
Syrupus Ferri Quininæ et Strychninæ Phosphatum	1–2 fl. dr.

Quininæ Sulphas, B. and U.S.P. SULPHATE OF QUININ $(C_{20}H_{24}N_2O_2)_2H_2SO_4.7H_2O$; 872.—The sulphate of an alkaloi prepared from the powder of various kinds of Cinchona an Remijia bark.

PREPARATION.—By extraction with spirit after the addition of lime, or b the action of alkali on an acidulated aqueous infusion with subseque neutralisation of the alkaloid by sulphuric acid and purification of the resul ing salt.

CHARACTERS.—Filiform, silky, snow-white crystals, of a pure intense bitter taste.

SOLUBILITY.—It is sparingly soluble in water, that is 1 part in 700 or 80 parts, at common temperatures, yet imparting to the water a bluish tint fluorescent appearance. Entirely soluble in water acidulated by sulphur acid.

REACTIONS.—Its solutions give with chloride of barium a white precipitat insoluble in nitric acid. When treated first with solution of chlorine an afterwards with ammonia they become of a splendid **emerald-green colou** and solution of ammonia gives with them a white precipitate of quinin soluble in ether, and in excess of the solution of ammonia. It dissolves i pure sulphuric acid with a feeble yellowish tint, and undergoes no furth change of colour when gently warmed. For the mode of testing the purit of the salt, *vide* B.P.

PREPARATIONS.

B.P.	DOSE.
Ferri et Quininæ Citras	5–10 gr.
Tinctura Quininæ Ammoniata	½–2 fl. dr.
Vinum Quininæ	½–1 fl. oz.

U.S.P. Quininæ Bisulphas. BISULPHATE OF QUININ $C_{20}H_{24}N_2O_2H_2SO_4.7H_2O$; 548.

CHARACTERS.—Colourless, clear, orthorhombic crystals or small needle effloresing and becoming opaque on exposure to air, no smell, very bitte taste, strongly acid reaction.

SOLUBILITY AND REACTIONS.—It resembles the sulphate in its reaction but is much more readily soluble. It dissolves with vivid blue fluorescenc in 10 parts, while the sulphate requires 740 parts, of water at 59° F.

U.S.P. Quininæ Hydrobromas. HYDROBROMATE OF QUININ $C_{20}H_{24}N_2O_2HBr.2H_2O$; 440·8.

CHARACTERS.—Colourless, lustrous needles, no smell, very bitter taste, an a neutral or slightly alkaline reaction.

SOLUBILITY.—It is soluble in about 16 parts of water at 59° F.

REACTIONS.—The solution gives the reactions of quinine, and with te solution of nitrate of silver yields a white precipitate insoluble in dilute nitric acid, and in solution of carbonate of ammonium.

ACTION.—Useful for **hypodermic injection.** It is supposed produce fewer unpleasant head symptoms than other preparations of quinine.

Quininæ Hydrochloras, B. and U.S.P. HYDROCHLORATE OF QUININE. $C_{20}H_{24}N_2O_2HCl.2H_2O$; 396·4.

CHARACTERS.—In crystals like those of the sulphate, but generally somewhat larger.

REACTIONS.—It gives the reactions of quinine, and with test solution of nitrate of silver produces a white precipitate insoluble in nitric acid, but soluble in ammonia.

USES.—Like those of the bisulphate.

PREPARATION.

B.P.	DOSE.
Tinctura Quininæ (1 gr. in 1 fl. dr.)	½–2 fl. dr.

U.S.P. Quininæ Valerianas. VALERIANATE OF QUININE. $C_{20}H_{24}N_2O_2C_5H_{10}O_2.H_2O$; 444.

CHARACTERS.—White pearly crystals with a slight odour of valerianic acid, a bitter taste and a neutral reaction.

REACTIONS.—The solution when acidulated with sulphuric acid emits the odour of valerianic acid, and gives the reactions of quinine.

USE.—As a tonic in hysteria and nervous irritability. It is said to be particularly useful in some forms of intermittent and spasmodic nervous affections (*vide* p. 952).

U.S.P. Quinidinæ Sulphas. SULPHATE OF QUINIDINE. $(C_{20}H_{24}N_2O_2)_2H_2SO_4.2H_2O$; 782.—It is chiefly obtained from *Cinchona pitayensis*.

CHARACTERS.—White silky needles, no smell, very bitter taste, with a neutral or faintly alkaline reaction.

SOLUBILITY AND REACTIONS.—It is soluble in 100 parts of water at 59° F. For its reactions, *vide* p. 941.

U.S.P. Cinchonina. CINCHONINE. $C_{20}H_{24}N_2O$; 308.

CHARACTERS.—White, somewhat lustrous, prisms or needles, no smell, at first nearly tasteless, but developing a bitter after-taste and having an alkaline reaction.

SOLUBILITY.—Almost insoluble in hot or cold water, readily soluble in dilute acids.

Cinchoninæ Sulphas. B. and U.S.P. SULPHATE OF CINCHONINE. $(C_{20}H_{24}N_2O_2H_2SO_4)_2H_2O$; 750.

PREPARATION.—From the mother-liquors of the crystallisation of the sulphates of quinine, cinchonidine, and quinidine, by precipitating with caustic soda, washing with spirit until free from other alkaloids, dissolving in sulphuric acid, purifying with animal charcoal, and allowing to crystallise.

CHARACTERS.—Hard, colourless, short, prismatic crystals, with a vitreous lustre. The aqueous solution has a bitter taste; the acidified solution is not fluorescent (p. 941).

SOLUBILITY.—Soluble in water and in chloroform, almost insoluble in ether and in solution of ammonia, readily soluble in rectified spirit and in dilute acids.

Cinchonidinæ Sulphas. B. and U.S.P. SULPHATE OF CINCHONIDINE. $(C_{20}H_{24}N_2O)_2H_2SO_4.3HO$; 768.

PREPARATION.—By concentrating the mother-liquors after the crystallisation of sulphate of quinine, purifying by crystallisation from alcohol and finally from hot water.

CHARACTERS.—In colourless silky crystals, usually acicular.

SOLUBILITY.—Soluble in water, alcohol, or ether; almost insoluble in chloroform or in solution of ammonia; readily soluble in diluted acids.

REACTIONS.—The solution in water has a bitter taste and a neutral or faintly alkaline reaction, twists a ray of polarised light to the left; when acidified is not distinctly fluorescent. For other tests, *vide* p. 941.

U.S.P. Chinoidinum. CHINOIDIN. (QUINOIDIN).—A mixture of alkaloids, mostly amorphous, obtained as a by-product in the manufacture of the crystallisable alkaloids from cinchona.

CHARACTERS.—A brownish-black or almost black solid, breaking when cold with a resinous shining fracture, becoming plastic when warmed, odourless, having a bitter taste and an alkaline reaction.

SOLUBILITY.—Almost insoluble in water, freely soluble in alcohol, chloroform, and diluted acids.

USE.—It is of uncertain composition, and liable to adulteration, and is employed instead of quinine on account of its cheapness.

DOSES OF CINCHONA ALKALOIDS AND THEIR SALTS.

Quinina	½–2 gr. as tonic; 2–5 gr. repeated every 2–4 hours as antipyretic. 15–20 gr. a large dose.
Quininæ Sulphas	The same.
„ Bisulphas	A little larger.
„ Hydrobromas	The same as for quinina.
„ **Hydrochloras**	„
„ Valerianas	1–2 gr.
Quinidinæ Sulphas	Same as quinina.
Chinoidinum	Somewhat larger than of the crystalline alkaloids.
Chinonidinæ Sulphas	1–15 gr.
Cinchonina	About one half more than of quinina.
Cinchoninæ Sulphas	„ „ „ „

The preparations in thick type belong both to the B.P. and U.S.P.; the others to the U.S.P. alone.

Physiological Action.

GENERAL ACTION.—A solution of quinine when added to **albumen** loses its fluorescence and seems to enter into combination with it, for the albumen is rendered less soluble and more coagulable (p. 58).

It lessens **protoplasmic** and amœboid **movements** (pp. 61, 62, 65), and destroys low animal and vegetable organisms, but salt-water amœbæ seem to withstand the action of quinine to a great extent.

Quinine diminishes **oxidation** (p. 72) and diminishes and prevents the development of a blue colour on the addition of a few drops of blood to a solution of tincture of guaiac and ozonic ether (p. 69). A similar but less marked effect is seen if blood be taken from an animal into which quinine has been previously injected, instead of mixing the quinine directly with the blood.

Quinine diminishes and in large doses arrests **fermentation**, pecially when it depends on organised ferments (as alcoholic, ctic, or butyric fermentations), but does not prevent the change starch into sugar by ptyalin or diastase. It has, however, an tion on some enzymes, and diminishes the action of pepsin on bumin, and the change of amygdalin into oil of bitter almonds by nulsin. It is a powerful **antiseptic** (p. 94), and a dilute solution ill preserve meat, milk, butter, or urine for a length of time. is **absorbed** from all mucous membranes, and is better given solution, as some of the powder passes out in the fæces. It rms with the bile a salt which is sparingly soluble, except excess of bile; hence before giving quinine in malaria, ear out the liver by administering an emetic and a cholagogue rgative.

Special Action.—**On the Alimentary Canal.**—When taken to the mouth, quinine causes a persistent bitter taste if the lution be neutral or only slightly acid, for then the alkalinity the saliva precipitates the alkaloid; but if given with an cess of acid, and a little water, the bitter taste soon disappears, aving a sweetish one behind. The bitter taste produces in- eased flow of saliva by reflexly influencing the centre in the edulla. When quinine is injected into the duct of the sub- axillary gland it prevents the secretion of watery saliva by aralysing the ends of the chorda tympani, or by acting directly n the secretory cells themselves (p. 354). The secretion of the ick ropy saliva is not prevented, for the sympathetic is not aralysed except by large doses (p. 355). The vaso-dilator erve fibres are not paralysed, for if they be stimulated the ood-vessels dilate, the lymph-spaces become full and the gland dematous, but no secretion takes place.

When taken into the **stomach** small doses increase the petite, especially in atonic dyspepsia, but if the stomach is ritable quinine in large doses causes loss of appetite and may roduce nausea and vomiting (p. 362 *et seq.*). When it causes miting, the addition of hydrobromic acid will often enable it be borne. If the stomach be congested the flow of mucous cretion will be increased by quinine.

The action of quinine on the secretions and peristalsis of the testines is unknown, as also is its action on the secretion of le, though it is certain that it does not increase it.

When absorbed into the **blood**, quinine causes contraction of e spleen, and in large doses lessens the contractile power and mœboid movements of the white blood-corpuscles. It thus checks e diapedesis of the white blood-corpuscles (p. 62).

The size of the red corpuscles is increased (p. 63), but their wer of giving up oxygen seems to be diminished, as is shown y the guaiacum test (p. 69).

On the Circulation.—Small and moderate doses increase

the strength of the circulation, but how they act has not bee ascertained.

Large doses diminish the blood-pressure, chiefly by weaker ing the heart, but partly by paralysing the vaso-motor centr thus causing dilatation of the vessels. This paralysis occu from very large doses. It is evidenced by the fact that irritatio of a sensory nerve or asphyxia no longer produces contraction the vessels and rise of blood-pressure.

The **heart's** action is weakened by quinine, from its actio on the motor ganglia, and probably also on the muscular fibr of the heart itself.

The **vagus nerve** is little affected by moderate doses, but finally paralysed by very large doses. In poisoning by quinin **death** generally occurs from failure of the respiration, and onl occurs through cardiac paralysis if the drug be injected direct into the circulation in large doses; the animal then dies in co vulsions consequent on stimulation of the nerve-centres by th venous condition of blood thus produced.

On the Respiration.—Small doses have no effect on i Moderate doses quicken the respiratory movements, but lar doses first slow, and then stop them, by paralysing the respir tory centre. The amount of oxygen taken in and of carbo dioxide exhaled is diminished. This is due to the action of th drug on tissue-change and on the red blood-corpuscles (p. 72).

On Tissue-change.—Moderate doses diminish tissue-chan (p. 415) and lessen the relative amount of nitrogen and sulphat in the urine, but increase the total quantity. In fever, especial when due to septic poisoning, the **temperature** of a patient lowered by quinine. It is also lowered in an animal even aft section of the cord and wrapping up in cotton-wool, showing th the fall is due to the lessened tissue-change and oxidation in th body. When given in fever quinine increases the amount nitrogen in the urine.

On the Nervous System.—In man small doses give to to the system generally.

Large doses cause symptoms to which the term **cinchonis** (or quinism) has been applied; these consist in a feeling tightness across the forehead, ringing in the ears, deafnes diminution of the power of sight and of accuracy of feeli (p. 229). These symptoms may generally be relieved by giving minims of solution of hydrobromic acid with each dose. Erg also tends to prevent or remove them.

By **still larger doses** the powers of hearing and sight a more affected, complete deafness being sometimes produce Giddiness, headache, staggering gait, and muscular weakne succeed, and the circulation becomes feeble.

With **very large doses** delirium occurs and occasional death, sometimes in convulsions.

Small doses stimulate, large doses depress, the functions of the **brain**, lessening the powers of thought, but may stimulate the motor centres so as to cause epileptic fits (p. 190), and I have seen one case in which an epileptic fit appeared to be brought on by large doses of quinine.

Spinal Cord.—Reflex action is diminished, especially in the frog. Immediately after the injection of quinine into the lymph-sac of a frog a great depression of reflex action occurs. This was attributed by Chaperon to stimulation of Setschenow's centres by the quinine. It is probably, however, only reflex depression, due to the local irritation of the injection. At a later stage of poisoning considerable depression of the reflex action is also observed, which has been attributed to gradual paralysis of the cord from feebleness of the heart and consequent failure of the circulation. **Sensory and motor nerves** are only affected by the drug when locally applied. The **muscles** retain their irritability till near death, but their capacity for work as well as their irritability is diminished. The muscular curve is somewhat prolonged (p. 128). During its **excretion** quinine stimulates the genito-urinary tract, and occasionally produces irritability of the bladder and urethra. It is said to produce contraction of the gravid **uterus**, and is therefore to be given with care in pregnancy.

Uses.—From its power of destroying germs and preventing putrefaction, quinine is used as a local **antiseptic**. As a lotion it is useful in conjunctivitis, and in the diphtheritic form of this disease quinine destroys the power of the secretion to cause inflammation when inoculated into another eye.

Hay fever, which probably is caused by the presence of the pollen of grasses, is often relieved by washing the nose with a saturated aqueous solution of sulphate of quinine (about ½ grain to 1 fl. oz.), (p. 478). Sometimes it is quite useless.

Sore-throat is often relieved by a gargle of quinine (cf. p. 816).

Whooping-cough is often relieved by quinine, which may be inhaled in the form of spray of the strength of 2 grains to the ounce in Richardson's ball spray or 4 grains to the ounce in Siegel's apparatus.

After the evacuation of an empyema or pleural effusion, a solution of quinine may be injected as an antiseptic into the pleural cavity. It is a useful injection (2 gr. to the ounce) in chronic cystitis and otorrhœa.

As a **tonic** it is useful in general debility; it increases the appetite and muscular strength; it may be advantageously combined with iron.

As an **antiperiodic** it is used in ague, malarial fever, and all malarial remittent affections, with great efficiency, being almost a specific. It should be given in doses of 3 or 4 grains, three times a day, or in a single dose of 10 grains just before a fit comes on; it will often cut short a fit of moderate intensity. An emetic

or cholagogue purgative should be given before it (p. 405).] malarial cachexia without distinct fits, it is much less serviceabl

In neuralgia of the intestine, when due to malaria, 5 grai should be administered in one dose, followed by 5 more in a quart of an hour if no relief is obtained. It will also cure other forn of neuralgia not apparently due to malaria, and even when n of a periodic character. It is especially useful in supra-orbit neuralgia.

Intermittent headache is often greatly relieved by 5 grai of quinine, especially if calomel, grey powder, or podophyllin] also given along with it to act on the liver (cf. pp. 375, 406).

As an **antipyretic** large doses (5–20 gr.) lessen the temper ture in typhus, enteric, and other fevers. It is better to give single large dose once a day, or two doses of 5 grains give within an hour, between five and six in the evening.

In symptomatic fevers quinine has been used to reduce th temperature, as in pneumonia.

In rheumatism and exanthemata it is not much used.

In the treatment of worms quinine is useful to prevent th accumulation of mucus which forms a nidus for the worm.

As a **prophylactic** agent against ague and all intermitte affections quinine is invaluable.

Warburg's tincture, containing quinine and a number r aromatics, is very useful in cases of ague in doses of one to fo drachms, and of collapse from various causes in doses of half a ounce.

The other alkaloids of cinchona seem to have very much th same action as quinine.

Sometimes people who work with cinchona barks are attacke with great irritation of the skin; this is probably due to th mechanical action of minute spicules of the bark.

Sub-Order II.—IXOREÆ.

(COFFEÆ.)

Ipecacuanha. Ipecacuanha, B.P.; Ipecac, U.S.P.—The dri root of *Cephaëlis Ipecacuanha*. Brazil.



Fig. 203.—Ipecacuanha, two-thirds the natural size.

Characters.—In pieces about the size of a small quill, contorted a irregularly annulated. Colour brown, of various shades. It consists of t parts, the cortical or active portion, which is brittle, and a slender, tou white, woody centre. This hard centre and the annulated appearance of t cortex give to the root the appearance of a number of brown beads strung a white thread.

Composition.—The woody centre is inert. The cortical pa contains an alkaloid, **emetine**, and an acid, **ipecacuanhic aci** which is a glucoside allied to tannic acid.

Dose.—Of the powdered root, as emetic, 15–30 gr.; in dysentery, 20–30 gr. in a bolus.

Preparations.

B.P.	dose.
Pilula Conii Composita (*vide* p. 522)	5–10 gr.
Pilula Ipecacuanhæ cum Scillâ (*vide* p. 522)	5–10 gr.
Pulvis Ipecacuanhæ Compositus	5–14 gr.
Trochisci Ipecacuanhæ ($\frac{1}{4}$-gr. in each)	1–3
Trochisci Morphinæ et Ipecacuanhæ ($\frac{1}{30}$-gr. morphine, $\frac{1}{12}$-gr. ipecac.)	1–6
Vinum Ipecacuanhæ (as an emetic)	3–6 fl. dr.
" " (as an expectorant)	5–40 min.

U.S.P	
Extractum Ipecacuanhæ Fluidum (as expectorant)	5 min.
" " " (as emetic)	25 min.
Pulvis Ipecacuanhæ et Opii	5–15 gr.
Trochisci Ipecacuanhæ ($\frac{1}{4}$-gr. in each)	1–4
Trochisci Morphinæ et Ipecacuanhæ ($\frac{1}{40}$-gr. of morphine, $\frac{1}{12}$-gr. ipecac.)	
Tinctura Ipecacuanhæ et Opii	4–15 min.
Syrupus Ipecacuanhæ (as expectorant)	2–30 min.
" " (as emetic)	$\frac{1}{2}$–1 fl. oz.
Vinum " (as expectorant)	3–5 min.
" " (to relieve vomiting)	half a drop

Pulvis Ipecacuanhæ Compositus. Compound Powder of Ipecacuanha, B.P. Pulvis Ipecacuanhæ et Opii. Powder of Ipecac and Opium, U.S.P. (Dover's Powder).—Ipecacuanha, 1; opium, 1; sulphate of potassium, 8, B.P. Ipecac, 10; powdered opium, 10; sugar of milk, 80, U.S.P.

Physiological Action.—In **frogs** small doses of emetine cause irregularity of the heart, with final stoppage in diastole and loss of irritability of the cardiac muscle. Larger doses paralyse the central nervous system and diminish the contractile power of the muscles (p. 128).

Locally applied to the skin or mucous membranes, it acts as an irritant and may produce a pustular eruption. In some persons it has a peculiarly irritating action on the respiratory tract, so that almost infinitesimal quantities of the powder cause running at the nose, and sometimes asthma. When taken internally, it is an irritant to the mucous membrane of the **stomach**, and acts as a prompt emetic. This is partly due to the local action of the drug on the ends of the vagus in the stomach, and, when absorbed into the blood, to its action on the vomiting centre in the medulla.

Emetine produces in dogs, both when injected under the skin and when administered internally, diarrhœa, which is sometimes bloody. The **intestinal** mucous membrane is swollen, red, and ecchymosed as in poisoning by arsenic, antimony, platinum, iron, or sepsine.

When injected either subcutaneously or into the veins it produces death by cardiac paralysis. It paralyses the **vessels** first, and then the **heart**, so that the blood-pressure sinks nearly to

zero while each cardiac pulsation is still powerful and produces a considerable wave in the blood-pressure tracing.

The **lungs** are often congested, œdematous, or in a state of red hepatisation, especially in rabbits.

In medicinal doses it increases the secretion from mucous membranes often very markedly, and is hence used to increase the expectoration and render it more fluid in bronchitis (p. 255). It is slightly diaphoretic, independently of the effect produced by its nauseating qualities.

Uses.—Ipecacuanha is used as an **emetic** in cases of poisoning and in overloaded conditions of the stomach; to clear out the trachea and larynx in croup and diphtheria (1 teaspoonful of vinum ipecacuanhæ every ¼-hour, in a child, till vomiting occurs); to empty the bronchial tubes in chronic bronchitis when choked up with mucus.

In jaundice depending on catarrhal conditions of the bile-ducts, it is useful to lessen the viscidity of the mucus; also in jaundice depending on the presence of a small calculus.

As a **diaphoretic** it is given in suddenly suppressed menstruation, and in rheumatism, muscular or acute, in the form of Dover's Powder; also in catarrhs. In small doses it is often useful in vomiting from various causes, e.g. vomiting of pregnancy.

As an **expectorant** (p. 255) it is very useful when the bronchial secretion is scanty, tough, and difficult to expectorate. Ringer strongly recommends the spray of ipecacuanha wine in winter cough and bronchial asthma.

Ipecacuanha is very useful as an **anti-dysenteric**, especially in the acute dysentery of the tropics; large doses (30 gr.) must be given on an empty stomach, preceded by a dose of laudanum half an hour before, to still the stomach and prevent vomiting. No water must be taken with it, and the patient must lie down with his head low.

Precautions.—Large doses must not be given to pregnant women, or to old people with atheromatous arteries. The wine is apt to lose its power by keeping, and hence it is best to preserve it in small sealed bottles.

Caffea. Coffee. Not officinal.—The seed of *Coffea arabica*.

Composition.—Unroasted coffee contains **caffeine** and a kind of tannin called **caffeotannic acid.** During roasting a part of the caffeine is volatilised and an empyreumatic substance called **caffeon** is developed.

Action.—The action of coffee is somewhat like that of caffein (p. 871), but differs from it in some respects, inasmuch as the caffeon increases the peristaltic movements of the intestine, and causes, indeed, tetanic contraction of it, while caffeine does not alter peristaltic movements. Caffeon quickens the pulse, dilates the vessels and lowers the blood-pressure, and produces a sensation of warmth on the surface. In some persons coffee produces

feeling of weight in the abdomen and a **tendency to hæmorrhoids.** As tea has not this action, or has it only to a comparatively slight extent, it is probably due to the combined action of the caffeine and caffeon.

USE.—Coffee is used chiefly as a remedy in headache and as a **stimulant** in cases of opium-poisoning.

B.P. Catechu. CATECHU. *Synonym:* CATECHU PALLIDUM.—An extract of the leaves and young shoots of *Uncaria Gambier*, Eastern Archipelago.

CHARACTERS.—In cubes about an inch square, or masses formed of coherent cubes, externally brown, internally ochrey-yellow or pale brick-red, breaking easily with a dull earthy fracture. Taste bitter, very astringent and mucilaginous, succeeded by slight sweetness.

The catechu of the U.S.P. is an extract prepared from the wood of *Acacia Catechu*, Leguminosæ (p. 910).

COMPOSITION.—Contains **catechu-tannic acid** and catechuic acid or **catechin**, which is related to catechu-tannic acid in the same way as gallic to tannic acid. There is also a yellow colouring matter, **quercitin.**

ADULTERATION.—Starch.

TEST.—The decoction when cool is not rendered blue by iodine.

PREPARATIONS.

B.P.	DOSE.
Infusum Catechu (catechu, 160 gr.; cinnamon, 30 gr.; water, ½-pint)	1–1½ fl. oz.
Pulvis Catechu Compositus (pale catechu, 4 oz.; kino and rhatany, of each 2 oz.; cinnamon and nutmeg, of each 1 oz.)	20–40 gr.
Tinctura Catechu	1–2 fl. dr.
Trochisci Catechu (1 gr. in each)	1–3 or more.

USES.—Catechu is employed as a local remedy in relaxed sore-throat. It may sometimes be chewed with advantage before taking food by persons suffering from pyrosis. Its use in such cases is probably to diminish the coating of mucus on the gastric mucous membrane. It is also employed in diarrhœa as an **astringent** (*vide* also p. 914).

VALERIANACEÆ.

B.P. Valerianæ Rhizoma. VALERIAN RHIZOME.—The dried rhizome and rootlets of *Valeriana officinalis*. Collected in autumn from plants growing wild or cultivated in Britain.




FIG. 204.—Valerian, half the natural size.

U.S.P. Valeriana. VALERIAN.—The rhizome and rootlets of *Valeriana officinalis*.

CHARACTERS.—A short, yellowish-white rhizome, with numerous fibrous roots about two or three inches long; of a bitter taste and penetrating odour agreeable in the recent root, becoming fetid by keeping; yielding volatile oil and valerianic acid when distilled with water.

COMPOSITION.—Contains a **volatile oil** and **valerianic acid.**

PREPARATIONS.

B.P.		DOSE.
Infusum Valerianæ	(2 dr. in ½ pint)	1–2 fl. oz.
Tinctura „	(2½ oz. in 1 pint spirit)	1–2 fl. dr.
„ „	**Ammoniata** (2½ oz. in 1 pint aromatic spirit of ammonia)	½–1½ fl. dr.

U.S.P.		
Abstractum Valerianæ		15–45 gr.
Extractum „	Fluidum	15–30 min.
Tinctura „	(20 per cent.)	1–2 fl. dr.
„ „	Ammoniata (20, in aromatic spirit of ammonia up to 100)	1–2 fl. dr.
Oleum Valerianæ		One or more drops
Quininæ Valerianas		1–2 gr.

U.S.P. Oleum Valerianæ. OIL OF VALERIAN.—A volatile oil distilled from Valerian.

CHARACTERS.—A greenish or yellowish, thin liquid, becoming darker and thicker by age and exposure to air, having the characteristic odour of valerian, an aromatic, somewhat camphoraceous taste, and a slightly acid reaction; sp. gr. about 0·950. It is readily soluble in alcohol.

ACTION AND USES.—The activity of valerian is chiefly due to the volatile oil it contains, and not to the valerianic acid. The **oil** in large doses **paralyses** both the **brain** and **spinal cord** and lessens the convulsions due to strychnine-poisoning, lowers the **blood-pressure** and slows the **pulse.** It is employed as an **antispasmodic** and stimulant in cases of hysteria, and is most useful in those occurring in delicate and young women.

Valerianate of zinc has been supposed to combine the nervine tonic action of zinc with the antispasmodic effect of valerian, but it is much better to use valerian itself or its oil along with a salt of zinc, as the acid has no important physiological action. It is used in chorea, especially when occurring in hysterical persons, and should not be discontinued until symptoms of nausea begin to make their appearance. It is also employed in epilepsy and neuralgia.

Valerianate of iron and valerianate of ammonium have also been used in medicine, and may be given in the same doses as the corresponding salt of zinc. For the action of valerianate of quinine, *vide* p. 943.

COMPOSITÆ.

Pyrethri Radix, B.P.; Pyrethrum, U.S.P. PELLITORY ROOT, B.P.; PYRETHRUM, U.S.P.—The dried root of *Anacyclus Pyrethrum.* The Levant.

CHARACTERS.—In pieces about the length and thickness of the little finger, overed with a thick brown bark studded with black shining points. It reaks with a resinous fracture, and presents internally a radiated structure. When chewed it excites a prickling sensation in the lips and tongue, and a lowing heat.

COMPOSITION.—A **resin**, the properties of which are not yet ully known; also a **volatile oil** and sugar.

PREPARATION.

B.P. and U.S.P.	DOSE.
Tinctura Pyrethri	10–20 m.

ACTION AND USES.—Pellitory is a local irritant, increasing he flow of **saliva** when taken into the mouth. It is used as a masticatory in dryness of the mouth, relaxed conditions of the throat, aphonia, and paralysis of the tongue or throat. It is also employed as a masticatory in headache and neuralgia of the head or face. The tincture diluted with water may be used as a gargle in similar conditions. The tincture may be applied on cotton wool to carious teeth to lessen the pain, but that of the pharmacopœia is hardly strong enough. It has been given internally with success in globus hystericus in doses of 10 to 20 drops four times a day.

U.S.P. Absinthium. WORMWOOD.—The leaves and tops of *Artemisia Absinthium*.

CHARACTERS.—Leaves about two inches (5 centimetres) long, hoary, silky-pubescent, petiolate, roundish-triangular in outline, pinnately two or three-cleft, with the segments lanceolate, the terminal one spatulate, bracts three-cleft or entire; heads numerous, subglobose, with numerous small pale yellow florets, all tubular and without pappus; odour aromatic; taste persistently bitter.

PREPARATION.

Vinum Aromaticum.

DOSE.—Of the powder 20–40 gr. It may be given with advantage as infusion (1 oz. to 2 fl. oz.), of which 1–2 fl. oz. may be given. It strikes blue with iron salts.

ACTION.—It contains a **volatile oil** and a bitter principle, **absinthin**. To the bitter principle it owes its action in stimulating the digestive organs. The volatile oil is a narcotic poison. In dogs and rabbits it causes trembling, stupor, **epileptiform convulsions** with involuntary evacuations, and stertorous breathing, which may or may not end in death. Similar symptoms may be produced in man.

USE.—It is a bitter **stomachic tonic**, and is used for atonic dyspepsia. It is said to be **anthelmintic**.

U.S.P. Tanacetum. TANSY.—The leaves and tops of *Tanacetum vulgare*.

CHARACTERS.—Leaves about six inches (15 centimetres) long; bipinnatifid, the segments oblong, obtuse, serrate or incised, smooth, dark green, and glandular; flower-heads corymbose, with an imbricated involucre, a convex,

naked receptacle, and numerous yellow, tubular florets; odour strongly aromatic; taste pungent and bitter.

COMPOSITION.—Tansy contains a powerful and irritating **volatile oil.**

USES.—It is seldom used in regular practice. Fatal cases of poisoning from this drug have been reported, the symptoms being epileptiform convulsions and coma, feeble pulse and death. Its action thus resembles that of absinthe. It has been used as a **diuretic** and **stimulant** in rheumatism, ague, and hysteria, as an **emmenagogue** in amenorrhœa, and sometimes as an **anthelmintic.** It is generally given as an infusion.

Santonica, B. and U.S.P. SANTONICA.—The dried unexpanded flower-heads of *Artemisia maritima*, var. *Stechmanniana*. Imported from Russia.

CHARACTERS.—Flower-heads resembling seeds in appearance, fusiform, blunt at each end, pale greenish-brown, smooth; odour strong, taste bitter, camphoraceous. Flower-heads not round or hairy.

COMPOSITION.—**Santonin** about 2 per cent., also essential oil and fatty acids.

PREPARATION.

B.P. and U.S.P.	DOSE.
Santoninum	2–6 gr.

B. and U.S.P. Santoninum. SANTONIN. $C_{30}H_{18}O_6$ or $C_{15}H_{18}O_3$.—A crystalline neutral principle prepared from *Santonica*.

CHARACTERS.—Colourless, flat, rhombic prisms, feebly bitter, fusible and subliming at a moderate heat.

SOLUBILITY.—Scarcely soluble in cold water, sparingly in boiling water, but abundantly in chloroform and in boiling rectified spirit; not dissolved by diluted mineral acids.

REACTIONS.—Sunlight renders it yellow; added to warm alcoholic potash it yields a violet-red colour.

PREPARATION.—The santonica is boiled with milk of lime, strained and partially evaporated. Hydrochloric acid is added to the hot solution, which is set aside to allow the santonin to subside and to separate from oily matter which is removed by skimming. The precipitate is washed with water and ammonia and purified by boiling in spirit with a little animal charcoal, which is separated by filtering. On the liquid cooling, crystals of santonin are deposited. It is to be protected from light.

DOSE.—1–3 gr. for a child; 2–6 gr. or more for an adult.

B.P. PREPARATIONS.	DOSE.
Trochisci Santonini (one grain in each)	1–6 lozenges.

U.S.P.	
Sodii Santoninas (p. 629)	8–10 gr.
Trochisci Sodii Santoninatis	1–8 troches.

PHYSIOLOGICAL ACTION.—Large doses of santonin given to a frog cause paralysis of the **cerebrum** with abolition of voluntary movement, followed by stimulation of the **medulla** causing

onvulsions, which cease on section of the cord. In man, large oses cause headache, giddiness, vomiting, and sometimes death y **convulsions**, with a tendency to paralysis of the respiration etween the convulsions; hence in a case of poisoning treat with hloroform to lessen the convulsions, and keep up artificial re- piration.

It produces a peculiar disturbance of **vision**, so that at first verything appears of bluish and afterwards yellowish or greenish- ellow. The blue appearance lasts only a short time, the yellow ision lasts much longer. This condition is usually regarded as ue to stimulation, and subsequent paralysis, of those fibres of he retina by which blue light is perceived. It is eliminated as a odium salt in the **urine** and colours it bright yellow; if the urine s rendered alkaline it becomes blood red; these colours are pro- ably due to some product of the oxidation of santonin. The uantity of urine is increased and the patient has a constant esire to micturate; in children it may give rise to incontinence f urine.

Uses.—It is used almost entirely as a **vermicide** for round- orms in doses of 2–5 gr. every other night, followed by a purga- ive. It should be given three or four times. It is useless gainst tape-worms. It has been frequently used as an injection gainst thread-worms (2–5 gr. in 1 oz. of castor oil).

The best method of administration probably is to give it in astor oil, although not unfrequently it is given in powder for wo or three nights running, the last powder being followed by a ose of castor oil next morning. It is best given at bedtime, as he effect on the sight passes off to a great extent during the night.

Anthemidis Flores, B.P.; Anthemis, U.S.P. Chamomile Flowers, B.P.; Anthemis, U.S.P.—The dried single and double flower-heads of the common chamomile, *Anthemis nobilis*, col- ected from cultivated plants.

Characters.—Subglobular heads, about three-quarters of an inch (2 centi- metres) broad. The single variety consists of both yellow tubular and white trap-shaped florets; the double of white strap-shaped florets only; all aris- ng from a conical scaly receptacle; both varieties, but especially the single, are bitter and very aromatic.

Composition.—**Essential oil**, removed by distillation, also a **bitter acid** in small quantity.

Preparations.

B.P.		Dose.	U.S.P.
Extractum Anthemidis		2–10 gr.	None.
Infusum	„	1–4 fl. oz.	
Oleum	„	1–4 min.	

B.P. Infusum Anthemidis. Infusion of Chamomile.—Chamomile flowers, ½ oz.; boiling water, 10 fl. oz.; infuse for quarter of an hour and strain.

B.P. Oleum Anthemidis. Oil of Chamomile.—The oil distilled in Britain from chamomile flowers.

CHARACTERS.—Pale-blue or greenish-blue, but gradually becoming yellow with the peculiar odour and aromatic taste of the flowers.

PREPARATION.

B.P.	DOSE.
Extractum Anthemidis	2–10 gr.

USES.—Like other ethereal oils, it has an action on bacteria (p. 103) and on the vaso-motor centre (p. 319). It is an aromatic **tonic, stomachic,** and **carminative.** It is used in atonic dyspepsia, accompanied by flatulence; also in summer diarrhœa in children and in sick headache.

U.S.P. Matricaria. GERMAN CHAMOMILE.—The flower-heads of *Matricaria Chamomilla.*

CHARACTERS.—About three-fourths of an inch (18 millimetres) broad composed of a flattish, imbricate involucre, a conical, hollow, naked receptacle, about fifteen white, ligulate, reflexed ray-flowers, and numerous yellow tubular, perfect flowers without pappus.

ACTION AND USES.—Strongly aromatic, **bitter, carminative** and **anthelmintic.** It is generally used as an infusion or decoction like chamomile.

U.S.P. Eupatorium. EUPATORIUM. THOROUGHWORT.—The leaves and flowering tops of *Eupatorium perfoliatum.*

CHARACTERS.—Leaves opposite, united at base, lanceolate, from four to six inches (10 to 15 centimetres) long, tapering, crenately serrate, rugosely veined, rough above, downy and resinous, dotted beneath; flower-heads corymbed, numerous, with an oblong involucre of lance-linear scales, and with from ten to fifteen white florets, having a bristly pappus in a single row; odour weak and aromatic; taste astringent and bitter.

COMPOSITION.—It contains a **volatile oil** and a bitter glucoside **eupatorin.**

PREPARATION.

	DOSE.
Extractum Eupatorii Fluidum.....	15–30 min.

USE.—It is used as a **tonic** and **diaphoretic.** In large doses it causes catharsis and emesis. As a tonic it is employed in dyspepsia and general debility. As a diaphoretic it is used to prevent any bad consequences from exposure to cold, and to cut short an attack of catarrh or muscular rheumatism at its commencement. It may then be given as infusion or as fluid extract mixed with hot water. When given in large doses as an emetic and **cathartic,** it is useful in causing the expulsion of tape-worm.

Taraxaci Radix, B.P.; Taraxacum, U.S.P. DANDELION ROOT, TARAXACUM.—The fresh and dried roots of *Taraxacum officinale* (*T. Dens-leonis*).

CHARACTERS.—Tap-shaped roots, smooth and dark-brown externally white within, easily broken, and giving out an inodorous, bitter, milky juice which becomes pale-brown by exposure.

COMPOSITION.—They contain a bitter principle—**taraxacin**—sugar, inulin, and a considerable quantity of **potassium** and **calcium salts.**

IMPURITY.—Common hawkbit fraudulently mixed.
TESTS.—Not wrinkled or pale-coloured externally; juice not watery; any adherent leaves runicate and quite smooth.

PREPARATIONS.

B.P.			DOSE.
Decoctum Taraxaci	(dried root, 1 oz.; water, 1 pint)		2–4 fl. oz.
Extractum „	(fresh)		5–30 gr.
Succus „	(fresh)		1–2 fl. dr. or more.

U.S.P.		
Extractum Taraxaci		30–60 gr.
„ „	Fluidum	½–2 fl. dr.

ACTION AND USES.—It is supposed to have a stimulant action on the liver, increasing its secretion, and is used in biliary disorders and dyspepsia. It has also a diuretic action.

B.P. Lactuca. LETTUCE.—The flowering herb of *Lactuca virosa*.

COMPOSITION.—It contains **lactucarium.**

PREPARATION.

B.P.	DOSE.	U.S.P.
Extractum Lactucæ	5–30 gr.	None.

U.S.P. Lactucarium. LACTUCARIUM.—The concrete milk-juice of *Lactuca virosa*.

CHARACTERS.—In sections of plano-convex, circular cakes, or in irregular, angular pieces, externally grey brown or dull reddish-brown, internally whitish or yellowish, of a waxy lustre; odour heavy, somewhat narcotic; taste bitter. It is partly soluble in alcohol and ether, and when triturated with water it yields a turbid mixture.

COMPOSITION.—Its chief ingredient is a bitter substance—**lactucin.**

PREPARATIONS.

	DOSE.
Extractum Lactucarii Fluidum	3–60 min.
Syrupus Lactucarii	2 fl. dr.

DOSE.—Of lactucarium, 5–30 gr.

ACTION AND USE.—Lettuce has a somewhat **soporific** action, and the extract has been used for sleeplessness. Lactucarium is used instead of opium to **allay cough**, quiet nervousness, and induce sleep in cases where, from idiosyncrasy, opium is not borne.

Arnicæ Rhizoma, B.P.; Arnicæ Radix, U.S.P. ARNICA RHIZOME, B.P.; (ROOT, U.S.P.)—The dried rhizome and rootlets of *Arnica montana*. Middle and Southern Europe and North-west of the United States.

CHARACTERS.—Rhizome, cylindrical, contorted, rough from the scars of the coriaceous leaves, of which some usually remain attached, and furnished with numerous long, slender fibres; has a peppery taste and peculiar odour.

COMPOSITION.—**Arnicin**, a substance having some of the properties of a glucoside. Arnica also contains about one per cent of an **essential oil**, with a considerable quantity of **inulin**.




FIG. 205.—Arnica, half the natural size.

ADULTERATION.—Sometimes adulterated with other and similar roots. These may be distinguished on close inspection.

PREPARATIONS.

B.P.	DOSE.
Tinctura Arnicæ (1 oz. to 1 pint)	30 min. to 1 fl. dr.

U.S.P.	
Extractum Arnicæ Radicis	5–10 gr.
,, ,, ,, Fluidum	10–30 min.
Tinctura ,, ,,	2–5 fl. dr.
Emplastrum Arnicæ	

U.S.P. Arnicæ Flores. ARNICA FLOWERS.—The flower-heads of *Arnica montana*.

CHARACTERS.—About one and one-fifth inch (30 centimetres) broad, depressed-roundish, consisting of a scaly involucre in two rows, and a small flat, hairy receptacle, bearing about sixteen yellow, strap-shaped ray-florets and numerous yellow, five-toothed, tubular disk-florets having slender spindle-shaped achenes, crowned by a hairy pappus. It has a feeble, aromatic odour, and a bitter, acrid taste.

PREPARATION.

U.S.P.	DOSE.
Tinctura Arnicæ Florum	½–2 fl. dr.

ACTION.—Arnica, externally, has a **stimulant** effect on the skin, and if evaporation be prevented it will produce redness and sometimes an erysipelatous inflammation, spreading some distance.

Internally it gives rise to a feeling of warmth in the mouth, stomach, and intestines, also increasing their peristaltic movements. In large doses it produces partial insensibility, convulsions, and sometimes syncope.

USES.—It is very generally used in bruises and sprains, but it has been shown by Dr. Garrod to be no more serviceable than spirit of the same strength, and it has the disadvantage of sometimes producing erysipelatous inflammation. It has been used

nternally in dysentery, chronic bronchitis, rheumatism, nervous liseases, and malarious conditions. Its value is doubtful.

U.S.P. Calendula. CALENDULA. MARIGOLD.—The fresh, lowering herb of *Calendula officinalis*.

CHARACTERS.—Stem somewhat angular, rough; leaves alternate, thickish, nairy, spatulate or oblanceolate, slightly toothed, the upper ones sessile; lower-heads nearly two inches (5 centimetres) broad, the yellow strap-shaped ray-florets in one or several rows, fertile, the achenes incurved and muricate; odour slightly narcotic; taste bitter and saline.

COMPOSITION.—It contains a **bitter principle** and **calendulin**. Its physiological action is not well understood.

PREPARATION.

Tinctura Calendulæ (used externally).

USES.—It is used as an application to sprains and bruises, in somewhat the same way as **arnica**.

U.S.P. Grindelia. GRINDELIA.—The leaves and flowering tops of *Grindelia robusta*.

CHARACTERS.—Leaves about two inches (5 centimetres) or less long, varying from broadly spatulate or oblong to lanceolate, sessile or clasping, obtuse, more or less sharply serrate, pale green, smooth, finely dotted, brittle; heads many-flowered; the involucre hemispherical, about half an inch (12 millimetres) broad, composed of numerous, imbricated, squarrosely-tipped scales; ray-florets yellow ligulate, pistillate; disk-florets yellow, tubular, perfect; pappus consisting of about three awns of the length of the disk-florets; odour balsamic; taste pungently aromatic and bitter.

COMPOSITION.—It probably owes its medicinal properties to a **resin** and **volatile oil**.

PREPARATION.

	DOSE.
Extractum Grindeliæ Fluidum	15 min.–1 fl. dr.

USES.—It has been found useful in spasmodic **asthma**, hay asthma, asthmatic attacks in bronchitis and emphysema, whooping cough, and in chronic bronchitis or bronchorrhœa, especially in old persons. It has also been found to give relief in **dyspnœa** depending on cardiac disease. The oleo-resin appears to be **excreted** by the kidneys, and is useful in catarrh of the urinary passages. As a **local application** it has been recommended to relieve the eruption caused by *Rhus Toxicodendron*, and to relieve itching and pain in vaginitis and in priapism.

The fluid extract of another non-officinal species, *Grindelia squarrosa*, growing in California, has been recommended as a remedy for enlarged spleen, ague, and **malarious conditions** generally, in doses of 1 fl. dr.

U.S.P. Inula. INULA. ELECAMPANE.—The root of *Inula Helenium*.

CHARACTERS.—In transverse concave slices or longitudinal sections, with overlapping bark, externally wrinkled and brown; flexible in damp weather;

when dry, breaking with a short fracture; internally greyish, fleshy, slightly radiate and dotted with numerous shining, yellowish-brown resin-cells; odour peculiar, aromatic; taste bitter and pungent.

COMPOSITION.—It contains a substance closely allied to starch—**inulin**—a bitter neutral principle—**helenin**—and a little **volatile oil.**

ADMINISTRATION.—The powder may be given in doses of 20–60 gr. It may be given as a decoction made by boiling ½ oz. of the root in a pint of water. The dose of this is 1–2 fl. oz.

USES.—It is used chiefly as a domestic remedy in **amenorrhœa,** chronic **bronchitis,** and skin diseases. Helenin has been said to be peculiarly destructive to the **tubercle bacillus.** If this statement be substantiated, inula may be useful in phthisis.

U.S.P. Lappa. LAPPA. BURDOCK.—The root of *Lappa officinalis.*

CHARACTERS.—About twelve inches (30 centimetres) or more long, and about one inch (25 millimetres) thick; nearly simple, fusiform, fleshy, longitudinally wrinkled, crowned with a tuft of whitish, soft, hairy leafy stalks; grey-brown, internally paler; bark rather thick, the inner part and the soft wood radially striate, the parenchyma often with cavities lined with snow-white remains of tissue; odour feeble and unpleasant; taste mucilaginous, sweetish, and somewhat bitter.

USES.—It has no marked therapeutic properties, but is said to be **alterative,** diaphoretic, diuretic, and purgative. It is chiefly used as a domestic remedy as a decoction prepared by boiling 2 oz. of the recent bruised root in three pints of water to two. One pint is taken daily. Burdock is employed in obstinate **skin diseases,** both internally and in the form of poultices of the leaves. It is given also in syphilis, scrofula, rheumatism, gout and renal disease.

CAMPANULACEÆ.

(LOBELIACEÆ.)

Lobelia, B. and U.S.P. LOBELIA.—The dried flowering herb of *Lobelia inflata.* North America, B.P. The leaves and tops of *Lobelia inflata* collected after a portion of the capsules have become inflated, U.S.P.

CHARACTERS.—Usually in compressed oblong rectangular packages weighing from half a pound to a pound each, and wrapped in sealed and labelled papers. The separate pieces are of varying lengths, yellowish-green, angular, and bearing sessile or stalked hairy oval irregularly toothed leaves together with some flowers and fruits. Odour somewhat irritating; taste at first mild, but, after chewing, burning and acrid.

COMPOSITION.—**Lobelina,** a yellowish liquid with alkaline reaction, soluble in water, spirit, and ether, and possessing the poisonous properties of the drug; also an acrid principle, **lobelacrin,** yielding lobelic acid; resins and a volatile oil are obtained in minute quantities.

PREPARATIONS.

B.P.	DOSE.
Tinctura Lobeliæ ($2\frac{1}{2}$ oz. in 1 pint spirit)	10 min. to $\frac{1}{2}$ fl. dr.
" " **Ætherea** ($2\frac{1}{2}$ oz. in 1 pint spirit of ether)	10 min. to $\frac{1}{2}$ fl. dr. or more.

U.S.P.	
Acetum Lobeliæ (in dilute acetic acid 10 per cent.)	$\frac{1}{2}$–1 fl. dr.
Extractum Lobeliæ Fluidum	1–5 gr.
Tinctura Lobeliæ (20 per cent.)	$\frac{1}{2}$–2 fl. dr.

PHYSIOLOGICAL ACTION.—Taken internally it causes a feeling of burning in the œsophagus, stomach, and intestines; vomiting, headache, giddiness, and great prostration; sometimes followed by convulsions and coma. Hence its action is very like that of tobacco, only differing in the greater intensity of the local burning sensations. It is often used to excess by the Coffinites, whose theory is 'Heat is life,' and most cases of poisoning by it are due to its employment by such herbalists. It produces death by paralysis of the **respiratory centre**. Small doses first raise and then depress the **blood-pressure**; large doses paralyse the **vaso-motor centre** and the peripheral ends of the **vagi** (Attwood).

USES.—It is chiefly used as a remedy in **spasmodic asthma** and other affections of air-passages accompanied by dyspnœa —e.g. chronic bronchitis with a tendency to spasm of the bronchial muscles. Ringer states that larger doses must be used than those given in most text-books; he recommends 10 min. every ten minutes while the fit is on. In a case of poisoning, evacuate the stomach; give demulcents and stimulants.

ERICACEÆ.

Uvæ Ursi Folia, B.P. BEARBERRY LEAVES.—The dried leaves of *Arctostaphylos Uva-ursi*. From indigenous plants.

Uva Ursi, U.S.P. UVA URSI. [BEARBERRY.]—The leaves of *Arctostaphylos Uva-ursi*.



FIG. 206.—Uva Ursi.

CHARACTERS.—Obovate, entire, coriaceous, shining leaves, about three-fourths of an inch in length, reticulated beneath; with a strong astringent taste, and a feeble hay-like odour when powdered.

COMPOSITION.—**Tannic and gallic acids**, and a bitter neutral extractive—**arbutin**—which is soluble in warm water.

ADULTERATION.—Red whortleberry leaves.

TESTS.—Leaves not dotted beneath nor toothed on the margin.

PREPARATIONS.

B.P.	DOSE.
Infusum Uvæ Ursi (1 oz. to 1 pint)	1–2 fl. oz.

U.S.P.	
Extractum Uvæ Ursi Fluidum	30–60 min.

USES.—Bearberry is an **astringent** and **diuretic**. It is chiefly used in catarrh of the bladder and of other parts of the genito-urinary passages.

The utility of the leaves is probably due not to the tannic and gallic acids which they contain, but to the arbutin. This substance is partially excreted unchanged, and part of it is decomposed in the body, yielding hydroquinone (p. 809). The hydroquinone is excreted by the kidneys in combination with sulphuric acid. Hydroquinone-sulphuric acid is colourless and is not poisonous. It may become decomposed in the bladder and the hydroquinone becoming oxidised will give a brown colour to the urine and impart to it antiseptic and stimulant properties which are useful in catarrh of the bladder. The quantity of arbutin, in the infusion, is too small to be very useful, and yet if the infusion be made stronger it may disagree with the stomach. Pure arbutin is therefore to be preferred, and may be given in doses of 4 gr. or more, three or four times a day, either in powder or in solution.

U.S.P. Chimaphila. CHIMAPHILA. [PIPSISSEWA.]—The leaves of *Chimaphila umbellata*.

CHARACTERS.—About two inches (5 centimetres) long, oblanceolate, sharply serrate above, wedge-shaped and nearly entire toward the base, coriaceous, smooth, and dark green on the upper surface. It is nearly inodorous, and has an astringent and bitterish taste.

DOSE.—30 to 60 gr.

OFFICINAL PREPARATION.

U.S.P.	DOSE.
Extractum Chimaphilæ Fluidum	1 fl. dr. (4 gm.)

COMPOSITION.—It contains **tannin** and several neutral principles found in other Ericaceæ.

ACTION.—It is **astringent** and has a **diuretic** action.

USE.—It is employed in disorders of the urinary passages and in the treatment of rheumatic pains.

U.S.P. Oleum Gaultheriæ. OIL OF GAULTHERIA.—Oil of wintergreen, a volatile oil distilled from *Gaultheria procumbens*.

CHARACTERS.—A colourless, yellow, or reddish liquid, of a peculiar, strong and aromatic odour, a sweetish, warm, and aromatic taste, and a slightly acid reaction.

SOLUBILITY AND REACTIONS.—It is readily soluble in alcohol. When heated to about 80° C. (176° F.) the oil should not yield a colourless distillate, having the characteristics of chloroform or of alcohol. On mixing five

drops of the oil with five drops of nitric acid, the mixture should not acquire a deep red colour, and should not solidify to a dark red resinous mass (absence of oil of sassafras).

COMPOSITION.—Oil of wintergreen consists chiefly of **salicylate of methyl**, which forms about $\frac{9}{10}$ths of it, the remaining $\frac{1}{10}$th being a hydrocarbon called **gaultherilene**.

PREPARATIONS.

	DOSE.
Spiritus Gaultheriæ (oil, 3; spirit, 97)	10–20 min.
Syrupus Sarsaparillæ Compositus	
Trochisci Morphinæ et Ipecacuanhæ	

ACTION AND USE.—It is used on account of its agreeable smell and taste to **flavour** medicines. It is also given as an **antipyretic** to reduce the temperature in rheumatism, its antipyretic action being somewhat the same as that of salicylate of sodium or salicin.

SAPOTACEÆ.

Gutta-percha, B. and U.S.P. GUTTA-PERCHA.—The concrete juice of *Dichopsis Gutta* (*Isonandra Gutta*) and of several other trees of the natural order Sapotaceæ.

CHARACTERS.—In tough, flexible pieces, of a light brown or chocolate colour.

SOLUBILITY.—Soluble, or nearly soluble, in chloroform, yielding a more or less turbid solution.

PREPARATION.

B.P.	U.S.P.
Liquor Gutta-percha.	Liquor Gutta-perchæ.

USE.—Chiefly employed on account of its physical properties for making splints, &c.; also as a temporary stopping for decayed teeth. Gutta-percha tissue and similar articles are used to prevent the evaporation of lotions, and to cover poultices and fomentations.

STYRACACÆ.

Benzoinum, B. and U.S.P. BENZOIN.—A balsamic resin obtained from *Styrax Benzoin*, and probably from one or more other species of Styrax. It is generally procured by making deep incisions in the bark of the trees, and allowing the liquid that exudes to concrete by exposure to the air. Siam and Sumatra.

CHARACTERS.—In lumps, consisting of agglutinated tears, or of a brownish mottled mass with or without white tears embedded in it; has little taste, but an agreeable odour; gives off, when heated, fumes of benzoic acid; is soluble in rectified spirit and in solution of potash.

COMPOSITION.—Contains about 14 per cent. of **benzoic acid** in combination with several **amorphous resins.**

DOSE.—10–30 gr.

Preparations.

B.P.	DOSE.
Acidum Benzoicum	10–15 gr.
Adeps Benzoatus	
Tinctura Benzoini Composita	½–1 fl. dr.
Unguentum Cetacei	

U.S.P.

Adeps Benzoinatus	
Tinctura Benzoini	½–1 fl. dr.
Tinctura Benzoini Composita	½–1 fl. dr.

Tinctura Benzoini Composita. Compound Tincture of Benzoin (Friar's Balsam).—Benzoin, 2 oz.; prepared storax, 1½ oz.; balsam of tolu, ½ oz.; Socotrine aloes, 160 gr.; rectified spirit, 1 pint, B.P.

Benzoin, 12; purified aloes, 2; storax, 8; balsam of tolu, 4; alcohol up to 100 U.S.P.

Acidum Benzoicum, B. and U.S.P. Benzoic Acid $HC_7H_5O_2$. (Not chemically pure.)

Preparation.—By heating benzoin, when benzoic acid sublimes.

Properties.—In light, feathery, crystalline plates and needles, which are flexible, nearly colourless, and have an agreeable aromatic odour, resembling that of benzoin.

Solubility.—It is sparingly soluble in water, but is readily dissolved by rectified spirit; soluble also in solutions of the caustic alkalis and of lime.

Reactions.—When dissolved in solutions of caustic alkalis or of lime it is precipitated from them on the addition of hydrochloric acid unless the solution be very dilute. When heated to 462° F. it passes off in vapour leaving only a slight residue.

Preparations.

B.P.	DOSE.
Ammonii Benzoas	10–20 gr.
Tinctura Camphoræ Composita	15 min to 1 fl. dr.
Tinctura Opii Ammoniata	½–1 fl. dr.
Trochisci Acidi Benzoici.	1–5 lozenges.

U.S.P.

Ammonii Benzoas.
Tinctura Opii Camphorata.

Ammonii Benzoas, B. and U.S.P. Benzoate of Ammonium. $NH_4C_7H_5O_2$ 139 (cf. p. 643).

Preparation.—By dissolving benzoic acid in a slight excess of ammonia evaporating and crystallising.

$$HC_7H_5O_2 + NH_4HO = NH_4C_7H_5O_2 + H_2O.$$

Properties.—In colourless, laminar crystals; soluble in water and in alcohol.

Reactions.—It gives a bulky yellowish precipitate with persalts of iron (benzoate). Its aqueous solution when heated with caustic potash evolves ammonia, and, if it be not too dilute, when acidulated with hydrochloric acid it gives a deposit of benzoic acid.

Impurities.—Fixed salts.

Tests.—When heated it sublimes without any residue.

Physiological Action.—Benzoic acid is a **stimulant** and irritant to raw surfaces. It has an **antiseptic** action, destroying low organisms, and is used in the form of the tincture for ulcers

wounds, blisters, and chapped hands. It was owing to its antiseptic action that Friar's balsam was successfully used for the treatment of wounds in the Middle Ages, although at that time its mode of action was unknown (p. 104).

It acts as a stimulating **expectorant**, diminishing the secretion of the mucous membrane.

Benzoic acid when absorbed into the blood is excreted by the kidneys, and acts as a **diuretic**. It does not diminish the uric acid. In the kidneys it unites with glycocoll, and is excreted as hippuric acid, rendering the urine acid and somewhat irritating. This is proved by the following experiments:—

(1) If you give benzoic acid it is found in the urine as hippuric acid, but in the blood still remains as benzoic acid.

(2) If you give to a rabbit hippuric acid, it is excreted as such, but is found in the blood as benzoic acid.

(3) If you tie the renal arteries and give benzoic acid no conversion into hippuric acid takes place, but if you ligature the ureters the change takes place, and hippuric acid is found in the blood. This localises the seat of the change to the kidneys.

Uses.—Compound tincture of benzoin (5 per cent.) and glycerine (5 per cent.), in rose water is a useful application or a stimulant to the skin after the cure of acne. Friar's balsam is also useful in urticaria. As an inhalation (one drachm to one ounce in a pint of boiling water) it has a sedative effect in relieving the irritation and cough of sub-acute laryngitis and of tracheitis. It is also useful in bronchitis. Benzoic acid is used in chronic bronchitis and phthisis, both internally and as an inhalation, and extraordinary results have been ascribed to its uses; many, however, deny its beneficial effect. It is used in catarrh of the bladder to acidify the urine. Ammonium benzoate has a similar action to benzoic acid.

OLEACEÆ.

Oleum Olivæ, B. and U.S.P. Olive Oil.—The fixed oil expressed from the ripe fruit of *Olea europæa*. South of Europe.

Characters.—Pale-yellow, with scarcely any odour, and a bland, oleaginous taste; congeals partially at about 36° F. Specific gravity about 0·916 at 63° F.

Composition.—**Olein**, the liquid principle of the oil, and the quantity of which determines its excellence. It also contains **palmitin** and other fatty compounds.

Adulteration.—Other, and usually heavier, oils fraudulently added.

Tests.—Specific gravity. Olive oil when treated with sulphuric acid evolves a small amount of heat compared with other similar oils.

Dose.—Of olive oil, 1 fl. dr. to 1 fl. oz. or more, as a demulcent or laxative.

PREPARATIONS.

B.P.

Charta Epispastica.
Emplastrum Ammoniaci cum Hydrargyro.
,, Hydrargyri.
,, Picis.
,, Plumbi.
,, Saponis Fuscum.
Enema Magnesii Sulphatis.
Linimentum Ammoniæ (p. 516).
,, Calcis (p. 516).
,, Camphoræ (p. 516).
Unguentum Cantharidis.
,, Hydrargyri Compositum.
,, Hydrargyri Nitratis.
,, Veratrinæ.

U.S.P.

Emplastrum Plumbi.
,, Resinæ.
,, Ammoniaci cum Hydrargyro.
,, Arnicæ.
,, Asafœtidæ.
,, Belladonnæ.
,, Capsici.
Emplastrum Ferri.
,, Galbani.
,, Hydrargyri.
,, Opii.
,, Saponis.
Unguentum Diachylon.

Sapo Durus, B.P. HARD SOAP. **Sapo, U.S.P.** SOAP.—Soap made with olive oil and soda.

CHARACTERS.—Greyish-white, dry, inodorous; horny and pulverisable when kept in dry, warm air; easily moulded when heated; soluble in rectified spirit; not imparting an oily stain to paper. Incinerated it yields an ash which does not deliquesce.

DOSE.—As an antacid, &c., 5–20 gr.

PREPARATIONS.

B.P.

Linimentum Saponis (p. 516).
Pilula Aloës Barbadensis (p. 522).
,, ,, et Asafœtidæ.
,, ,, Socotrinæ.
Pilula Cambogiæ Composita.
,, Rhei Composita.
,, **Saponis Composita** (p. 523).
,, Scillæ Composita.

U.S.P.

Emplastrum Saponis.
Linimentum ,, (p. 517).
,, Chloroformi.
Pilulæ Aloës (p. 523).
Pilulæ Aloës et Asafœtidæ.
,, Asafœtidæ.
,, Opii.
,, Rhei.

Sapo Mollis, B.P. SOFT SOAP. **Sapo Viridis, U.S.P.** GREEN SOAP.—Soap made with olive oil and potash, B.P. Soap prepared from potassa and fixed oils, U.S.P.

CHARACTERS.—Yellowish-green, inodorous, of a gelatinous consistence. Soluble in rectified spirit; not imparting an oily stain to paper. Incinerated it yields an ash which is very deliquescent.

DOSE.—As an antacid, &c., 5-20 gr.

PREPARATIONS.

B.P.

Linimentum Terebinthinæ (p. 516).

U.S.P.

Tinctura Saponis Viridis (green soap, 65; oil of lavender, 2; alcohol up to 100).

Glycerinum, B. and U.S.P. GLYCERINE, B.P.; GLYCERIN, U.S.P.; GLYCEROL.—A sweet principle (B.P.). It is a trihydric alcohol, $C_3H_5(HO)_3$; 92, obtained by reaction of fats and fixed oils with aqueous fluids, and containing a small percentage of water (not less than 95 per cent. of absolute glycerin, U.S.P.)

CHARACTERS.—A clear, colourless fluid, oily to the touch, without odour, of a sweet taste.

SOLUBILITY.—Freely soluble in water and in alcohol.

REACTIONS.—When decomposed by heat it evolves intensely irritating vapours due in part to acrolein. Specific gravity 1·25.

DOSE.—One half to 2 fl. dr.

PREPARATIONS (*vide* p. 513).

B.P.

Extractum Cinchonæ Liquidum.	Lamellæ, in all.
Glycerinum Acidi Carbolici.	Linimentum Iodi (p. 516).
„ „ **Gallici.**	„ Potassii Iodidi cum Sapone.
„ „ **Tannici.**	Mel Boracis.
„ **Aluminis.**	Pilula Aloes et Myrrhæ (p. 522).
„ **Amyli.**	„ Rhei Composita.
„ **Boracis.**	„ Saponis Composita.
„ **Plumbi Subacetatis.**	Tinctura Kino.
„ **Tragacanthæ.**	Unguentum Iodi.

U.S.P.

Glyceritum Amyli. Glyceritum Vitelli.
Mucilago Tragacanthæ.

ACTION AND USES.—**Olive oil** is used externally in the form of liniments as a **lubricating** substance, and in seborrhœa it may be applied 4 or 5 times daily till the crusts are removed. It is useful alone in acute attacks of psoriasis and in acute eczema capitis. Internally it acts as a demulcent in cases of irritant poisoning, except by phosphorus. In large doses it is slightly **laxative,** as in oily salads.

Soft soap is more alkaline than the hard, and from the free potash it contains, it may produce a caustic effect on the skin if too long applied. Rubbed in for 5 or 10 minutes once or twice daily, it is very useful in chronic and subacute eczema, a soothing ointment being applied after its use. A tincture of soft soap (2 in 1 of rectified spirit) is a convenient form of applying it to the hairy scalp: after rubbing in, it must be washed off and an oily preparation used. This treatment does good in seborrhœa, in scaly forms of eczema capitis, and in lupus furfuracea. Soft soap is also useful in sycosis and ichthyosis and in some cases of lupus erythematosus.

Hard soap is used chiefly as a **detergent,** and for its mechanical effect, in pills and as an adjunct in suppositories. A small piece of soap cut into a conical form and used as a suppository is very useful in constipation occurring in infants. Soap and water forms a useful enema for constipation in adults.

Glycerin is used as an ingredient in ointments and lotions in various skin-diseases. With two per cent. carbolic acid added, if rubbed on in the bath, it relieves the itching in chronic eczema. Five per cent. glycerin with an equal part of Friar's balsam in rose-water is useful in acne (*vide* p. 965); glycerin soaps are used in seborrhœa and acne.

Glycerin acts as a laxative, and when used along with castor oil increases its power. It is largely destroyed in the system, has an influence on nutrition, and has been proposed as a substitute for cod-liver oil, but without much benefit. Very large doses cause a red coloration in the urine, due to the colouring matter of the blood, without any free corpuscles.

It is used as a **laxative** in hæmorrhoids; as a **solvent** of other drugs, as borax, tannic acid; as an **emollient** to soften the hands, and applied to sore nipples, fissure of the tongue, in advanced phthisis, croup, laryngitis, &c. It has been painted on in eczema, psoriasis, pruritus; also as a preventive of bed-sores. It must be diluted with water, or it will irritate the part. It has been proposed as a substitute for sugar in diabetes.

Manna, B. and U.S.P. MANNA.—A concrete saccharine exudation obtained by making transverse incisions in the stems of the trees of *Fraxinus Ornus*, cultivated in Calabria and Sicily.

CHARACTERS.—In stalactiform pieces from one to six inches in length, and one or two inches in width, uneven, porous, and friable, curved on one side, of a yellowish-white colour. Odour faint, resembling honey; taste sweet and honey-like, combined with a slight acridity and bitterness.

DOSE.—60 grains to 1 ounce.

PREPARATION.

U.S.P.	DOSE.	B.P.
Infusum Sennæ Compositum	2½ fl. oz.	None.

COMPOSITION.—It consists principally of **mannite** or mannitol, a hexahydric alcohol, $C_6H_8(OH)_6$, together with common **sugar** and extractive matter. The mannite, which forms from 60 to 80 per cent. of the manna, may be extracted by means of boiling rectified spirit, from which it will afterwards separate on cooling in colourless, shining crystals. It requires five parts of cold water for its solution, and this does not undergo vinous fermentation in contact with yeast, being thus distinguished from grape-sugar.

USE.—Manna is used as a simple **laxative.**

APOCYNACEÆ.

U.S.P. Apocynum. APOCYNUM. CANADIAN HEMP.—The root of *Apocynum cannabinum.*

CHARACTERS.—Long, cylindrical, somewhat branched, one-fourth to one-third of an inch (6 to 8 millimetres) thick, pale brown, longitudinally wrinkled and transversely fissured; brittle; fracture short, white; the bark rather thick; the wood porous, spongy, with delicate, medullary rays and a thin pith; inodorous; taste bitter, disagreeable.

COMPOSITION.—It contains an amorphous substance—**apocynin**—easily soluble in alcohol, but insoluble in water, and a glucoside—**apocyneïn**—easily soluble in water.

Dose.—15–30 gr. (1–1·95 gm.) of powdered root. A decoction is more convenient. It is made by boiling ½ oz. in 1½ pint water to 1 pint. Of this 1–2 fl. oz. (30–60 c.c.) may be given twice or thrice a day.

Action.—In small doses it is **laxative**, in large doses emetic and cathartic. Apocynin and apocyneïn act on the heart as **cardiac tonics** like digitalis, and are also **diuretic**.

Use.—It is chiefly used in dropsy.

Quebracho Cortex. White Quebracho Bark. Not official.—The bark of *Aspidosperma Quebracho*, imported from the Argentine Republic.

Characters.—In large pieces, about three-quarters of an inch thick, greyish-brown outside, yellowish inside, intensely bitter.

Composition.—It contains six alkaloids, the most important of which are **quebrachine, aspidosamine,** and **aspidospermine**; others are called quebrachamine, hypoquebrachin, aspidospermatin. There is also a peculiar kind of tannic acid.

Preparations.

Tinctura Quebracho (1 in 5 of proof spirit)	½–1 fl. dr.
Aspidospermine	0·5–1 gm.
Quebrachine	

Action.—Quebrachine is the most active of the alkaloids; aspidosamine ranks second, and aspidospermine third. These three have a similar action. **Respiration** is first affected, in warm-blooded animals the fulness and frequency of breathing being increased, and finally respiration is paralysed. In frogs respiratory paralysis, from an affection of the respiratory centre, rapidly follows the introduction of the poison. The **central nervous system** is paralysed, the brain being first affected so that there is at first a loss of voluntary movement, with increase of reflex excitability; finally the spinal cord also is paralysed. **Voluntary muscle** is paralysed by the local action of all these alkaloids, and aspidosamine and hypoquebrachin paralyse also the motor nerve endings.[1] The **heart** is paralysed in cold-blooded animals after the respiration; it is at first slowed, and the peripheral ends of the vagus are paralysed; in warm-blooded animals the cardiac paralysis is said to be primary.[2]

Uses.—It has been used to lessen dyspnœa in **asthma**, emphysema, and phthisis.

[1] E. Harnack and K. Hofmann, *Zeits. f. klin. Med.*, Bd. viii. Hft. 6, 1884.
[2] G. Gutmann, *Archiv f. exper. Patholog. u. Pharmakol.*, xiv. p. 451.

ASCLEPIADACEÆ.

U.S.P. Asclepias. Asclepias. Pleurisy Root.—The root o *Asclepias tuberosa*.

Characters.—Root large and fusiform, dried in longitudinal or transvers sections; from one to six inches (25 to 150 millimetres) long, and about thre quarters of an inch (two centimetres) or more in thickness; the head knotty and slightly but distinctly annulate, the remainder longitudinally wrinkled externally orange-brown, internally whitish; tough and having an unever fracture; bark thin, and in two distinct layers, the inner one whitish; wood yellowish, with large, white medullary rays; it is inodorous, and has a bitterish, somewhat acrid taste; when long kept it acquires a grey colour.

Composition.—It contains **resins** and an odorous **fatty matter.**

Dose.—20–60 gr.

Use.—It may be used as a **diaphoretic** or **expectorant.** In large doses it acts as an emetic and purgative.

Asclepias Incarnata. White Indian Hemp. Not officinal America.—The root appears to act **like digitalis,** strengthening the beats of the heart, and producing diuresis. A fluid extract has been used in doses of ½–1 fl. dr. every three hours.

B.P. Hemidesmi Radix. Hemidesmus Root.—The dried root of *Hemidesmus indicus*, Indian sarsaparilla. India.



Fig. 207.—Hemidesmus.

Characters.—Yellowish-brown, cylindrical, tortuous, furrowed, and with annular cracks; having a fragrant odour and a very agreeable flavour.

Composition.—The chemical constituents of the root have not yet been fully investigated. A substance supposed to be a **volatile acid** has been separated by distillation with water.

Preparation.

B.P.	Dose.
Syrupus Hemidesmi (1 to 10½ oz.)	1–2 fl. dr.

Use.—Hemidesmus is supposed to have the same action as **sarsaparilla** (*q.v.*) and is used in rheumatism and syphilis. The syrup is of little use except for flavouring.

Condurango. Not officinal.—The bark of *Gonolobus Condurango* from Ecuador. It is said, however, that there are several species of plants yielding a bark known by the name 'Condurango.'

Characters.—Condurango is a climbing plant; the bark is generally of a greyish colour outside with a few adherent lichens, and occurs in thin, curled pieces.

ACTION.—It does not seem to have any definite physiological tion. It has been stated by Gianuzzi to produce tetanus like rychnine. I found that an infusion injected into the jugular in caused convulsions and death, but this appeared to be really ue to embolism of the pulmonary vessels by fine particles sus- nded in fluid, for when injected into the peritoneal cavity the lution had no action.

USES.—It has been recommended as a remedy in cancer, but useless in this disease. It has been found beneficial, however, cases of **dyspepsia**, and has been given also as an alterative syphilis.

LOGANIACEÆ.

Nux Vomica. NUX VOMICA.—The seeds of *Strychnos Nux-mica*. East Indies.

CHARACTERS.—Nearly circular and flat, about an inch in diameter, um- icated and slightly convex on one side, externally of an ash-grey colour, ickly covered with short satiny hairs, internally translucent, tough, and rny; taste intensely bitter, inodorous. The seeds to be pulverised must heated by steam and dried.

COMPOSITION.—Two alkaloids, **strychnine** and **brucine**. The rmer is much less soluble in boiling water than the latter, and ffers, further, in not being coloured by nitric acid, with which rucine gives a brilliant red. Both alkaloids are found combined ith strychnic or igasuric acid—similar to malic acid.

DOSE.—Of the powdered seed, 2–5 gr.

PREPARATIONS.

B.P.	DOSE.
Extractum Nucis Vomicæ	$\frac{1}{4}$–2 gr.
Strychnina	$\frac{1}{30}$–$\frac{1}{12}$ gr.
Tinctura Nucis Vomicæ	10–20 min.

U.S.P.	
Abstractum Nucis Vomicæ	$\frac{1}{2}$ gr.
Extractum „ „	$\frac{1}{3}$–1 gr.
„ „ „ Fluidum	1–5 m.
Strychnina	$\frac{1}{30}$–$\frac{1}{12}$ gr.
Tinctura Nucis Vomicæ	10–20 min.

U.S.P. Ignatia. IGNATIA. BEAN OF ST. IGNATIUS.—The eed of *Strychnos Ignatii*.

CHARACTERS.—About an inch and a fifth (3 centimetres) long, oblong, or vate, irregularly angular, dull brownish or blackish, very hard, horny; frac- re granular, irregular; the albumen somewhat translucent, enclosing an regular cavity with an oblong embryo; inodorous; very bitter.

OFFICINAL PREPARATIONS.

	DOSE.
Abstractum Ignatiæ	1 gr.
Tinctura Ignatiæ	15 min.–1 fl. dr.

COMPOSITION.—Its activity depends on the contained **brucine** nd **strychnine**.

Strychnina, B. and U.S.P. STRYCHNINE. $C_{21}H_{22}N_2O_2$; 33
An alkaloid prepared from Nux Vomica (B.P.) or Ignatia, and al
occurring in other plants of the Nat. Ord. Loganiaceæ (U.S.P.)

PREPARATION.—Softening the tough seeds by steam, chopping, dryin
and grinding them. Exhausting the powdered seeds with rectified spirit whi
is recovered by distillation. Precipitating colouring matter and acids
acetate of lead. Precipitating strychnine and brucine from concentrat
solution by ammonia. Dissolving the precipitate in rectified spirit and crysta
lising out strychnine from concentrated solution. The brucine being mo
soluble remains in the mother liquor. The strychnine is purified by washi
and boiling with rectified spirit.

CHARACTERS.—In right square octahedrons or prisms, colourless, and i
odorous.

SOLUBILITY.—Sparingly soluble in water, but communicating to it i
intensely bitter taste; soluble in boiling rectified spirit and in chloroform
but not in absolute alcohol or in ether.

REACTION.—Pure sulphuric acid forms with it a colourless solution, whi
on the addition of bichromate of potassium acquires an intensely violet hu
speedily passing through red to yellow. A very active poison.

IMPURITY.—Brucine from imperfect preparation, and mineral matter.

TESTS.—Not coloured by nitric acid (no brucine), leaves no ash whe
burned with free access of air (no mineral matter).

PREPARATIONS.

B.P.	DOSE.
Liquor Strychninæ Hydrochloratis.—(Strychnine, 1 part, with 2 of dilute hydrochloric acid, and 24 of spirit to keep it in solution, and water 73)	5–10 min.

U.S.P.	
Ferri et Strychninæ Citras	1–3 gr.
Syrupus Ferri, Quininæ et Strychninæ Phosphatum (p. 751)	1–2 fl. dr.

U.S.P. Strychninæ Sulphas. SULPHATE OF STRYCHNINE.

PHYSIOLOGICAL ACTION.—Strychnine added to water contain
ing low **organisms** in small doses increases their activity; i
large doses it lessens it. The drug lessens **oxidation** of proto
plasm and oxidation taking place in the blood; it also lessen
fermentation, but its action on it is not nearly so great as migh
be expected from its powerful action on higher organisms (p
61, 65, 69, 72, 89).

GENERAL ACTION.—The most marked feature in the gener
action of strychnine is the great increase which it produces i
the **reflex excitability** of the spinal cord and other reflex nerve
centres, such as the vaso-motor and respiratory centres. Whe
the dose is large this increase is so great as to cause **convulsion**
and **death.**

Taken in small doses strychnine gives rise to a bitter tast
and increases the appetite; sometimes also it increases th
peristaltic movements of the **intestines,** and lessens constipatio
When taken in small doses for a long time the drug produce
increased sensibility of the **sensory nerves,** so that impression
are felt more acutely and are of longer duration, and the sens
of touch is rendered more acute; the field of vision is increase

nd distant objects are rendered more distinct; the sense of earing is also sharpened (pp. 226, 229). Taken in larger doses e drug produces increased sensibility more markedly, and cites sexual desire. If pushed still further the drug causes alaise, anxiety, restlessness, twitchings of the muscles, stiffness the neck and convulsions.

After a dose of half a grain of strychnine symptoms of **poisoning** appear in a period varying from five minutes to five ours, coming on without vomiting or any other warning, the rst symptom being general convulsions; the teeth are clenched, e pupils dilated, and the body forced into the opisthotonic osition, resting on the head and feet, with the hands clenched nd the arms drawn tightly towards the body; the spasms last om half to one minute, and are followed by a period of relaxaon, during which sensibility to reflex stimuli is enormously inreased, the slightest stimulus, such as a draught of cold air, inging on a fresh attack of spasms. Death results either from sphyxia occurring during a spasm, or from paralysis and colpse coming on during a period of relaxation. The **diagnosis** etween convulsions occasioned by strychnine and ordinary etanus depends (1) on the history of the case, and (2) on the ct that the spasms of tetanus are tonic whilst those of strychine-poisoning are clonic. In tetanus too the muscles of the w are first affected, hence the term 'lock-jaw'; whilst in rychnine convulsions these muscles are not affected before thers.

The **treatment** of strychnine poisoning consists in evacuating he stomach, if possible before the convulsions begin; but, if this annot be done, chloroform must be given and the stomach ashed out whilst the patient is under the influence of the anesthetic, and, lastly, chloral should be given by subcutaneous njection (10 gr.) or in enema (1 dr. repeated).

Special Action. **On the Alimentary Canal.**—Strychnine roduces, by its bitter taste, an increased flow of saliva; it also ncreases the peristaltic action of the bowels.

On the Blood.—When mixed with the blood it lessens oxiation to a slight extent, but probably it has little action on xidation in the living body, from the small doses which can lone be used.

On the Circulation.—It increases the **blood-pressure.** his is due to several causes: (1) It stimulates the **vaso-motor entre** directly, or else greatly increases its excitability to the rdinary stimuli it receives, even when the dose is too small to roduce convulsions. When these occur, other factors help to ncrease the pressure. (2) The vaso-motor centre during the onvulsions is stimulated indirectly by the action of the carbon ioxide of the venous blood, which accumulates during the asphyxia caused by the convulsions. (3) The violent muscular

contractions during the convulsions increase the resistance t the flow of blood through the arteries and capillaries.

After section of the cord in a normal animal, stimulation a sensory nerve no longer produces vaso-motor spasm; but i an animal poisoned with strychnine it does. The explanatio of this is that strychnine increases the excitability of the vaso motor centre to such an extent that that portion of it which i in the cord becomes able to take on to a great extent the norma functions of the whole centre (p. 287).

The medicinal use of strychnine is said to cause in som cases fits resembling those of tertian ague.[1] It is not probabl that these are true ague fits, due to malaria, the action of whic has been aided by that of strychnine on the vaso-motor centr (cf. p. 287, and action of opium, p. 862).

The **heart** is stimulated, but during the convulsions it i slowed in the frog. In mammals it is quickened during th spasms, but if curare be previously given it is slowed.

Strychnine stimulates the motor ganglia of the heart, fo Dr. Cash and I found that when a frog is under the action o strychnine a ligature placed between the sinus venosus an auricle did not stop the auricle and ventricle as in Stannius experiment (p. 319), and if this experiment has already bee performed, strychnine injected into the interior of the ventricl causes the auricle and ventricle to recommence beating.[2] Th action of strychnine on the motor centre in the heart is probabl similar to its action on the vaso-motor and respiratory centres.

Respiration is quickened and rendered more deep, owing t stimulation of the respiratory centre, just as in the case of th vaso-motor centre the spinal part of the respiratory centre i rendered so active; if strychnine be given to an animal and th cord be divided below the medulla, respiration is not entirel arrested, as it usually is; and if strychnine be given to an anima after division of the cord, respiration will recommence (p. 236).

On the Muscles.—These are but little affected directly, bu indirectly they become greatly exhausted by the wear and tea due to the convulsions. After death they quickly enter int *rigor mortis*.

Nervous System.—The **sensory** nerves are so stimulate that the slightest impression is most distinctly felt; the actio of the drug has not been shown to be on the nerves themselves but probably is due to stimulation of the nerve-centres (pp. 226 229, and 230). Small doses do not affect the **motor nerves** large doses paralyse them. This paralysis is partly due to ex haustion from the convulsions, but not entirely, since if on sciatic nerve of the frog be divided before poisoning, so as to pre

[1] Lewin, *Nebenwirkungen der Arzneimittel*, p. 50.
[2] Brunton and Cash, *St. Bartholomew's Hospital Reports*, vol. xvi.

ent any convulsions in the corresponding limb, it still loses its ritability, though not so soon as the undivided nerve.

On the Brain.—Small doses increase the **mental powers** nd sharpen the **senses**. Large doses cause anxiety and malaise, ut the functions of the cerebrum continue until death, the mind emaining clear to the last. The convulsions are not cerebral pp. 179, 180).

On the Spinal Cord.—The spinal cord is greatly stimulated, o that a slight stimulus through a sensory nerve produces not nerely increased reflex action but, by increasing the diffusion or radiation ' of impulses, causes general convulsions. This action f strychnine has been supposed to be due to increased excitability f the nerve-cells in the spinal cord, but is more probably caused y an alteration in the comparative rate of transmission of timuli from one cell to another (pp. 161, 173). The con-ulsant action of strychnine was first localised to the spinal cord y the experiments of Magendie, as already described (p. 180).

Strychnine acts more powerfully when injected into the rec-um than when swallowed, contrary to the general rule.

Brucine, thebaine, and some other **opium alkaloids** act in he same way as strychnine.

The effect of brucine in producing convulsions has been said o depend on admixture with strychnine. Mr. Shenstone pre-ared some pure brucine, and in experiments with this I have ound it cause convulsions and death in rabbits when injected ubcutaneously. It appears to be both less powerful than strych-ine, and to be eliminated more rapidly, for when given to rats s a paste with butter it caused no symptoms whatever.

Methyl-strychnine and **methyl-brucine,** like **methyl-the-aine,** do not affect the cord, but paralyse the ends of the motor erves, like curare.

Uses.—Strychnine is one of the best gastric tonics in yspepsia when there is a tendency to catarrh and congestion. t probably acts by perfecting co-ordination between the various unctions of the parts concerned in the processes of digestion nd assimilation. It probably also increases the movements of he stomach and gives tone to the gastric vessels, and thus re-ieves congestion of the stomach due to bronchitis, cirrhosis, nd cardiac disease (p. 367). As a **tonic** it is very useful during onvalescence from acute diseases, in anæmia, in dyspepsia due o indigestible articles of diet or excess of alcoholic stimulants; lso in ' sick headache ' in doses of one minim of tincture of nux omica in a teaspoonful of water every ten minutes (Ringer).

In doses of 10 min. before meals I have found it prevent rontal headache in persons liable to it.

It also gives contractile power to the intestines and is used s an adjunct to purgative pills. A very good dinner pill is il. rhei co. gr. iv., pulv. ipecac. ½ gr., ext. nucis vom. ½ gr.; given

before dinner. A few drops of tincture of nux vomica just before dinner both increase the appetite and tend to lessen habitual constipation. In dilated heart it is useful as a cardiac tonic. It is useful as a respiratory stimulant in bronchitis, especially when there is a tendency to failure of respiration.

The night-sweats of phthisis are usually checked by taking 10 min. of tincture of nux vomica at bed-time. The probable mode of action has already been discussed (p. 443). It may also increase the cough during the day.

In depression due to mental overwork it is very valuable, as it increases the mental powers, but we must be cautious not to give it for too long a time. One of the chief dangers of giving it to overworked men is that it increases their powers temporarily and they are tempted to overwork themselves still more.

In some forms of paralysis (hemiplegia, paraplegia, wrist-drop), except where there still exist symptoms of irritation, it is serviceable; it is also useful in some forms of local paralysis, as atony of the bladder. It is useful in infantile paralysis after the acute symptoms have passed away.

In sexual debility it is often serviceable. Its marked aphrodisiac action is sometimes inconvenient and interferes with its use as a tonic (p. 450). In some cases where debility is associated with sexual excess, strychnine increases instead of diminishes the weakness, and in such cases bromide of potassium should be employed. It has been used in hysteria and chorea with low spirits. It is a cumulative poison, as it contracts the renal arteries and thus prevents its own excretion (p. 40).

Curare. Not officinal.—*Synonyms*: CURARA, WOORARI, WOURALI, URARI, TICUNAS.

This substance appears to be an extract from a species of Strychnos mixed with some mucilaginous juice.

CHARACTERS.—A black extractiform body some specimens of which are readily soluble in water, but others leave an insoluble residue.

COMPOSITION.—It contains an alkaloid, **curarine.**

ACTION.—It paralyses the peripheral ends of **motor nerves** even when given in very minute doses (p. 147). Larger doses paralyse the **vagus** and the ends of **sensory nerves.** As poisoning progresses the **spinal cord** is paralysed, and finally the heart. Voluntary **muscles** appear to be little affected, yet their contractility is somewhat diminished, and this diminution begins even before the motor nerves themselves are paralysed. The **vessels** of the surface become dilated, and sometimes a peculiar erythematous rash appears on the skin in dogs. The **blood-pressure** is little affected by small doses, but is much lowered by large ones. When injected into the salivary gland it causes intense **salivation,** which appears to be paralytic (p. 355). In **men** who have been slightly poisoned by it, it has produced in-

reased secretion of the sweat, tears, nasal mucus, saliva, and rine, with a feeling of weariness and disinclination to move. arge doses produce **death** by paralysis of the muscles of re- piration, but, the motor nerves of the extremities being para- sed, no convulsions occur. Although the motor nerves are aralysed to such an extent that they will not excite muscular ntractions, even when the nerve-centres are powerfully stimu- ted by asphyxial blood, they still cause muscular contractions hen irritated by an interrupted current in a warm-blooded nimal poisoned by curare. In frogs the poisoning may be so mplete that no irritation of the trunk of a nerve will excite ntraction in the muscles supplied by it. Curare is rapidly **liminated** by the kidneys, and if artificial respiration be kept p complete recovery occurs. I have succeeded in restoring an nimal completely by this means, after it had been apparently ead for four hours. When given internally, curare is so rapidly iminated that it usually produces no symptoms. When given a a very large dose on an empty stomach, symptoms of poison- g may occur. If elimination be prevented, by excision of the dneys or ligature of the renal vessels, poisoning occurs, and in is case death is usually preceded by convulsions. So rapidly es elimination occur, that the urine of a frog poisoned by curare ill paralyse a second frog injected subcutaneously, and the urine f the second will even paralyse a third.

Uses.—It has been employed, but without much benefit, in ilepsy and chorea, and has been used with success in traumatic tanus. In poisoning by strychnine it is not so useful as nloral. A case of hydrophobia has been described by Offenburg which the subcutaneous injection of curare, to such an extent s to keep the patient almost, though not quite, paralysed for me time, effected a cure. If this were really so it would be ost important, but from a comparison of the symptoms de- ribed by Offenburg with those of three fatal cases I have myself en, I am inclined to think that his case was one of hysteria imicking hydrophobia.

Gelsemium, B. and U.S.P. Gelsemium. Yellow Jasmine. he dried rhizome and rootlets of *Gelsemium nitidum* (*G. sempervirens*).

Characters.—Nearly cylindrical, from ½ to 6 inches or more in length, d commonly from ¼ to ¾ inch in diameter, with small rootlets attached to, mixed with, the larger pieces; light yellowish-brown externally, and arked longitudinally by dark purplish lines; fracture splintery; bark thin, esenting silky fibres in its liber, and closely attached to a pale yellow rous woody axis, with evident medullary rays, and with or without pith. dour somewhat narcotic and aromatic; taste bitter.

Composition.—It contains an alkaloid, **gelsemine**.

Dose.—5 to 30 grains.

PREPARATIONS.

B.P.	DOSE.
Extractum Gelsemii Alcoholicum	½–2 gr.
Tinctura Gelsemii	5–20 min.

U.S.P.	
Extractum Gelsemii Fluidum	5–20 min.
Tinctura Gelsemii	½–2½ fl. dr.

ACTION.—When applied to the **eye** it produces dilatation of the pupil and paralysis of accommodation. It appears to paralyse the sensory columns of the **spinal cord**, while it excites the **motor centres** both in the brain and cord. The motor centres themselves become paralysed subsequently. This action causes in frogs paralysis, which is at first accompanied by increased reflex excitability, so that irritation gives rise to tremor or tetanus. Afterwards the reflex excitability completely disappears. In mammals a peculiar affection of the **head** is noticed, consisting in spasmodic attacks of tremor. The tremor affects the fore feet also and sometimes the hind legs. A kind of ataxia is also observed in the fore legs, which sometimes slip about and sometimes make abnormal running movements. This is succeeded by paralysis of the voluntary muscles and of respiration. The **vagus** is paralysed, the **blood-pressure** is diminished, the **pulse** rapid, and the **heart** weak. **Death** occurs from paralysis of the respiration. In **man** large doses have caused giddiness, double vision, numbness of the fingers, tremor of the head, difficult respiration, nausea, vomiting, and partial paralysis of the tongue and eyes, so that ptosis occurs, and difficulty is felt in moving the eyes or tongue.

USE.—It is chiefly used in cases of **neuralgia** of the fifth nerve, in toothache, sick headache, and in rheumatism.

U.S.P. Spigelia. SPIGELIA. PINKROOT. MARYLAND PINK. CAROLINA PINK.—The rhizome and rootlets of *Spigelia marylandica*.

CHARACTERS.—Rhizome two inches (5 centimetres) or more long, about one-eighth of an inch (3 millimetres) thick, horizontal, bent, somewhat branched, on the upper side with cup-shaped scars; on the lower side with numerous, thin, brittle rootlets about four inches (10 centimetres) long; dark purplish brown; somewhat aromatic, sweetish and bitter.

It should not be confounded with the underground portion of *Phlox carolina*, the rootlets of which are brownish-yellow, rather coarse, straight, and contain a straw-coloured wood underneath a readily removable bark.

PREPARATION.

	DOSE.
Extractum Spigeliæ Fluidum	10–20 min.

USE.—It is very generally used as an **anthelmintic**, and is best given with a cathartic, as senna.

GENTIANACEÆ.

Gentianæ Radix, B.P.; Gentiana, U.S.P. GENTIAN ROOT, B.P.; GENTIAN, U.S.P.—The dried root of *Gentiana lutea*. Mountainous districts of Central and South Europe.



FIG. 208.—Gentian, half the natural size.

CHARACTERS.—From half an inch to one inch in thickness, several inches in length, often twisted, much wrinkled, or marked with close transverse rings; brown externally, yellow within; tough and spongy; taste at first sweetish, afterwards very bitter.

COMPOSITION.—**Gentio-picrin,** from which the root derives its bitter taste; it is soluble in water. Also **gentianin,** which is tasteless and only slightly soluble in water.

PREPARATIONS.

B.P.	DOSE.
Extractum Gentianæ	2–10 gr.
Infusum Gentianæ Compositum	1–2 fl. oz.
Tinctura Gentianæ Composita	½–1 fl. dr.

U.S.P.			
Extractum Gentianæ			2–10 gr.
,,	,,	Fluidum	8–30 min.
Tinctura	,,	Composita	1–4 fl. dr.

B.P. Infusum Gentianæ Compositum.—Root, 1 part; bitter orange peel, 1 part; fresh lemon peel, 2 parts; and boiling water, 80 parts.

Tinctura Gentianæ Compositum.—Root, 1½ oz.; bitter orange peel, ¾ oz.; cardamoms, ¼ oz.; proof spirit, 20 fl. oz., B.P. Gentian, 8; bitter orange peel, 4; cardamom, 2; diluted alcohol up to 100, U.S.P.

USE.—Gentian is a simple, bitter **stomachic tonic.** It is used in atonic dyspepsia, to give tone to the stomach and increase the appetite. Also used as a general tonic.

Chirata, B. and U.S.P. CHIRETTA.—The dried plant *Ophelia Chirata*; collected when the fruit begins to form. Northern India.

CHARACTERS.—Stems about three feet long, of the thickness of a goose-quill, round, smooth, pale-brown, branched; branches opposite; flowers small, numerous, panicled; the whole plant intensely bitter.

COMPOSITION.—**Ophelic acid,** soluble in water and forming a soluble compound with tannic acid; and **chiratin,** soluble in warm water and forming an insoluble compound with tannic acid. Both substances are intensely bitter.

PREPARATIONS.

B.P.	DOSE.
Infusum Chiratæ (1 in 40 of water at 120° F.)	1–2 fl. oz.
Tinctura Chiratæ	½–2 fl. dr.
U.S.P.	
Extractum Chiratæ Fluidum	15–30 min.
Tinctura Chiratæ	½–2 fl. dr.




FIG. 209.—Chiretta, half the natural size.

USES.—As a **bitter tonic** like gentian. It has been supposed by some to be specially useful in disorders of the liver.

CONVOLVULACEÆ.

B.P. Scammoniæ Radix. SCAMMONY ROOT.—The dried root of *Convolvulus Scammonia*. Syria and Asia Minor.

CHARACTERS.—Tap-shaped roots, often twisted, sometimes three inches in diameter at the top, brown without, white within, slightly odorous but tasteless. Ether agitated with the powder and evaporated leaves a residue having the properties of scammony resin.

COMPOSITION.—Resina Scammoniæ (*q.v.*).

PREPARATIONS.

B.P.	DOSE.
Resina Scammoniæ	3–8 gr.
U.S.P.	
Resina Scammonii	4–8 gr.

Scammonium, B. and U.S.P. SCAMMONY.—A gum-resinous exudation obtained by incision from the living root of *Convolvulus Scammonia*, hardened in the air. Chiefly in Asia Minor. B.P. A resinous exudation from the root of *Convolvulus Scammonia*, U.S.P.

CHARACTERS.—In irregular, angular pieces or circular cakes, ash-grey and rough externally; fresh fracture, resinous, splintery, shining, black when dry; odour and flavour cheesy; causes, when chewed, a slight prickly sensation in the back of the throat; easily triturated into a dirty-grey powder, and converted with water into a smooth emulsion.

COMPOSITION.—**Gum and resin.**

ADULTERATIONS.—Chalk, starch, wood-ashes, and gum.

TESTS.—It does not effervesce with hydrochloric acid (no chalk). Boiling water agitated with the powder, cooled and filtered, does not strike a blue colour with tincture of iodine (no starch). Ether removes from 80 to 90 per cent. of resin; and what remains is chiefly soluble gum, with a little moisture (no wood ashes).

PREPARATIONS.

B.P.	DOSE.
Mistura Scammonii	½–2 fl. oz.
Resina Scammoniæ	3–8 gr.
U.S.P.	
Resina Scammonii	4–8 gr.

B.P. Mistura Scammonii. SCAMMONY MIXTURE.—Scammony (3 gr.) triturated with milk (1 fl. oz.).

Scammoniæ Resina, B.P. Resina Scammonii, U.S.P. RESIN OF SCAMMONY.

CHARACTERS.—In brownish, translucent pieces; brittle; resinous in fracture; of a sweet fragrant odour if prepared from the root. It cannot form singly an emulsion with water. Ether dissolves it entirely.

PREPARATION.—Extracted from the root by percolating with alcohol.

COMPOSITION.—Principally **jalapin** soluble in ether, in this respect differing from the convolvulin of jalap. The resin also contains other substances the properties of which are imperfectly known. Contains no gum.

IMPURITY.—Guaiacum fraudulently added.

TEST.—The tincture does not render the fresh cut surface of a potato blue.

PREPARATIONS.

B.P.	DOSE.
Confectio Scammonii	10–30 gr. or more.
Extractum Colocynthidis Compositum	5–15 gr.
Pilula Colocynthidis Composita (*vide* p. 522)	5–10 gr.
„ „ et Hyoscyami (*vide* p. 522)	5–10 gr.
Pilula Scammonii Composita (*vide* p. 523)	5 gr.
Pulvis Scammonii Compositus	10–20 gr.
U.S.P.	
Extractum Colocynthidis Compositum	5–20 gr.

B.P. Confectio Scammonii. CONFECTION OF SCAMMONY.—Resin of scammony,

3 oz.; ginger, 1½ oz.; oil of caraway, 1 fl. dr.; oil of cloves, ½ fl. dr.; syrup, 3 fl. oz.; clarified honey, 1½ oz.

B.P. Pulvis Scammonii Compositus. COMPOUND POWDER OF SCAMMONY.—Scammony resin, 4; jalap, 3; ginger, 1.

ACTION AND USES.—It increases the secretion of the intestines and acts as a **drastic purgative.** It is used as a derivative in dropsy and cerebral affections. It is also used, in combination with other drugs, as a **vermifuge** for tape-worm in children. It combines with the sodium in the bile, and its solution in bile is necessary to its action (Buchheim).

Jalapa, B. and U.S.P. JALAP.—The dried tubercles of *Ipomœa Purga* (*Exogonium Purga*), B.P. The tuberous root of *Exogonium Purga*, U.S.P. Mexico.



FIG. 210.—Jalap, reduced to ½ in size.

CHARACTERS.—Varying from the size of a nut to that of an orange, ovoid, the larger tubercles frequently incised, covered with a thin, brown, wrinkled cuticle; presenting, when cut, a yellowish-grey colour, with dark brown concentric circles.

PREPARATIONS.

B.P.	DOSE.
Extractum Jalapæ	5–15 gr.
Pulvis Jalapæ Compositus	20–60 gr.
Pulvis Scammonii Compositus	10–20 gr.
Resina Jalapæ	2–5 gr.
Tinctura Jalapæ	½–2 fl. dr.

U.S.P.	
Abstractum Jalapæ	7–10 gr.
Pulvis Jalapæ Compositus	30–60 gr.
Resina Jalapæ	2–5 gr.
Pilulæ Catharticæ Compositæ (*vide* p. 523)	1–3 pills.

Pulvis Jalapæ Compositus. COMPOUND JALAP POWDER.—B.P. Jalap, 5; acid tartrate of potassium, 9; ginger, 1 part. U.S.P. Jalap, 35; acid tartrate of potassium, 65.

Jalapæ Resina, B. and U.S.P. RESIN OF JALAP.—Extracted from jalap by rectified spirit.

CHARACTERS AND SOLUBILITY.—In dark-brown opaque fragments, translucent at the edges, brittle, breaking with a resinous fracture, readily reduced to a pale brown powder, sweetish in odour, acrid in the throat, easily soluble in rectified spirit, but only partially so in ether, and insoluble in oil of turpentine.

PREPARATION.—Digesting and gently heating the jalap with rectified spirit, precipitating the resin with water, evaporating by a water bath, and drying.

COMPOSITION.—The resin consists of **convolvulin** in combination with another resinous substance (**gammaresin**), which

is the part dissolved by ether. The convolvulin of jalap differs from the jalapin of scammony in being insoluble in ether.

PREPARATION.

B.P.

Pilula Scammonii Composita (*vide* p. 523).

ACTION AND USES.—Jalap is a **hydragogue purgative**, used for constipation, dropsy due to renal disease, and cerebral affections. It is best given with acid tartrate of potassium, as in Pulv. Jalapæ Co. Like scammony, it is dissolved by the bile, and appears to require it in order to act. It has no action when injected subcutaneously, nor when injected into the veins. It has no irritant action when locally applied to the skin or mucous membranes of the eye or nose, nor has it any diuretic action, or any action on the nervous system.

SOLANACEÆ.

U.S.P. Dulcamara. DULCAMARA. BITTERSWEET.—The dried young branches of *Solanum Dulcamara*. From indigenous plants which have shed their leaves.

CHARACTERS.—Light, hollow, cylindrical, about the thickness of a goose-quill; bitter and subsequently sweetish to the taste.



a *b*

FIG. 211.—Dulcamara. *a*, reduced ½. *b*, natural thickness.

COMPOSITION.—It contains **solanine**, and less **dulcamarine**, both alkaloids, amorphous, and of a bitter taste. It yields also sugar.

PREPARATION.

U.S.P.	DOSE.
Extractum Dulcamaræ Fluidum	1 fl. dr.

ACTION.—The action of dulcamarine has not been investigated.

Solanine, both in warm and cold-blooded animals, paralyses the central **nervous system** without affecting the peripheral nerves or voluntary muscles. It slows the **heart** and **respiration**, lessens sensibility, and causes death with convulsions. In warm-blooded animals there is constant fall of **temperature**, and there is entire absence of any action on the pupil. In man it produces weakness, laboured breathing, nausea, vomiting, and drowsiness, but no true sleep. The pupil is unaffected and

there is no increased movement of the bowels, diuresis, or diaphoresis.

USES.—Dulcamara is chiefly used as an **alterative** in scaly skin diseases, in which it is often combined with antimony. It has been recommended by Husemann in chronic bronchial catarrh, asthma, and whooping cough.

Capsici Fructus, B.P.; Capsicum, U.S.P. CAPSICUM FRUIT, B.P.; CAPSICUM, U.S.P.—The dried ripe fruit of *Capsicum fastigiatum*. Zanzibar.

CHARACTERS.—Pod membranous, from five to eight lines long, two lines broad, straight, conical, pointed, smooth, shining, but somewhat corrugated, orange-red; intensely hot in taste.

COMPOSITION. — An exceedingly acrid, volatile substance, **capsaïcin**, and an alkaloid resembling coniïne in odour.

ADULTERATION.—The powder is occasionally found adulterated with red lead.

TEST.—Digest in nitric acid and add sulphate of sodium. There should be no precipitate of sulphate of lead. It should burn away without residue of lead.

PREPARATIONS.

B.P.	DOSE.
Tinctura Capsici	5–20 min. (as a gargle, ½–2 fl. dr. in 5 oz. of fluid).

U.S.P.	
Extractum Capsici Fluidum	2–10 min.
Oleoresina Capsici	⅛–1 min.
Tinctura Capsici	8 min. to 2 fl. dr.
Emplastrum Capsici	

ACTION AND USES.—Externally capsicum is an **irritant**, producing warmth, redness, and vesication. Internally it is an irritant, and in large doses will produce gastro-enteritis.

It has been used for unbroken chilblains, neuralgia, and rheumatic pains. The Emplastrum Capsici of the U.S.P. is a useful application in cases of myalgia and sciatica. Internally it may be used as a gargle for tonsillitis, pharyngitis, and relaxed sore-throat. It is used as a condiment, and to relieve flatulence. It is also recommended to relieve the sinking in the epigastrium felt by dipsomaniacs. It promotes appetite and stimulates the stomach.

SUB-ORDER.—ATROPEÆ.

Belladonnæ Folia, B. and U.S.P. BELLADONNA LEAVES. The leaves of *Atropa Belladonna*, U.S.P. The fresh leaves, with the branches to which they are attached, of the deadly nightshade, *Atropa Belladonna*; also the leaves separated from the branches and carefully dried; gathered from wild or cultivated British plants when the fruit has begun to form, B.P.

CHARACTERS.—Leaves alternate, three to six inches long, ovate, acute, entire, smooth, the uppermost in pairs and unequal. The expressed juice, or an infusion, dropped into the eye, dilates the pupil.

COMPOSITION.—Less than one per cent. of **atropine**, and a small proportion of asparagin. More atropine is obtained from the leaves of mature plants than from those gathered before inflorescence.

PREPARATIONS.

B.P.			DOSE.
Extractum Belladonnæ		(green)	$\frac{1}{4}$–1 gr.
Tinctura	„	(from dried leaves)	5–30 min.
Succus	„	(from fresh leaves)	5–15 min.

U.S.P.

Extractum Belladonnæ Alcoholicum		$\frac{1}{4}$ gr.
Tinctura Belladonnæ		8–30 min.
Unguentum	„	

Belladonnæ Radix, B. and U.S.P. BELLADONNA ROOT. The dried root of *Atropa Belladonna*. Britain or Germany.

CHARACTERS.—From one to two feet long, and from half an inch to two inches thick, branched and wrinkled, brownish-white. An infusion dropped into the eye dilates the pupil. Roots which are tough and woody, breaking with a splintery fracture, should be rejected.

COMPOSITION.—Two alkaloids, **atropine** and **belladonnine**, the former under one per cent. Also a red colouring matter, atrosin.

PREPARATIONS.

B.P.			DOSE.
Atropina			$\frac{1}{200}$–$\frac{1}{20}$ gr.
Linimentum Belladonnæ (1 oz. to 1 fl. oz., *vide* p. 516)			
Extractum Belladonnæ Alcoholicum			$\frac{1}{16}$–$\frac{1}{4}$ gr.
Unguentum Belladonnæ		from alcoholic extract	
Emplastrum	„		

U.S.P.

Atropina			$\frac{1}{200}$–$\frac{1}{20}$ gr.
Abstractum Belladonnæ			$\frac{1}{2}$ gr.
Emplastrum	„		
Extractum	„		1–2 min.
Linimentum	„	(*vide* p. 517)	

Atropina, B. and U.S.P. ATROPINE. $C_{17}H_{23}NO_3$; 289.—An alkaloid obtained from belladonna.

PREPARATION.—It cannot be profitably prepared on a small scale. The chief parts of the process are the precipitation of acid colouring matters from a strong tincture by means of lime, removal of the alcohol, addition of water and carbonate of potassium, taking up the alkaloid from the alkaline solution by chloroform, and subsequent purification.

CHARACTERS.—In colourless, acicular crystals.

SOLUBILITY.—Sparingly soluble in water, more readily in alcohol and in ether.

REACTIONS.—Its solution in water has an alkaline reaction, gives a citron-yellow precipitate with terchloride of gold, has a bitter taste, and powerfully dilates the pupil. It leaves no ash when burned with free access of air. It is an active poison.

The following test has been proposed for the members of the group o mydriatic alkaloids—atropine, hyoscyamine, daturine, duboisine, and homa tropine. To a small portion of atropine in a test-tube add about 2 c.c. of 5 per cent. solution of mercuric chloride in 50 per cent. of alcohol, and warm gently. A precipitate will at once appear, and become brick-red in colour This test does not answer in dilute solutions, neither does it turn out well i atropine be added to the mercury. Other alkaloids give for the most part a white precipitate (Gerrard).

PREPARATIONS.

B.P.	DOSE.
Atropinæ Sulphas	$\frac{1}{200}$–$\frac{1}{20}$ gr.
Liquor Atropinæ Sulphatis.....4 gr. in 1 fl. oz.	$\frac{1}{2}$–6 min.
Unguentum Atropinæ (with rectified spirit $\frac{1}{2}$ fl. dr. and prepared lard 1 oz.) .....8 gr. in 1 oz.	

Atropinæ Sulphas, B. and U.S.P. SULPHATE OF ATROPINE.

PREPARATION.—By dissolving atropine in dilute sulphuric acid and evaporating.

CHARACTERS.—A colourless powder.

SOLUBILITY AND REACTIONS.—Soluble in water, forming a solution which is neutral to test paper, and when applied to the eye dilates the pupil as the solution of atropine does. It leaves no ash when burned with free access of air.

USES.—Intended for external application. It is a powerful poison.

PREPARATION.

B.P.	U.S.P.
Liquor Atropinæ Sulphatis (1 in 100 of camphor water).	None.
Lamellæ Atropinæ ($\frac{1}{5000}$ gr. in each).	

GENERAL ACTION OF BELLADONNA OR ATROPINE. — The first toxic symptoms to appear after a **small dose** are dryness of the mouth and headache. After **full doses** the pupils become dilated, a red rash appears on the skin like that of scarlatina, and a delirium of a peculiar and often of a pleasant character ensues, in which there is a great desire for movement and activity, with a feeling of great lassitude (p. 200). The pulse becomes rapid. This is generally followed by sleep.

With large doses, the mouth becomes so dry that swallowing is almost impossible, and the attempt to swallow may bring on general convulsions like hydrophobia; these convulsions are followed by paralysis, stupor, often alternating with delirium, coma and death, preceded by marked failure of the heart's action and of respiration. Death is due to asphyxia.

SPECIAL ACTION.—**Locally applied** it diminishes the sensibility of the sensory nerves (whether applied as liniment or injected subcutaneously). It can be absorbed from the skin and produce its general symptoms.

It stimulates the centres in the **brain,** but tends to paralyse the ends of the motor nerves, hence causing that peculiar form of delirium in which a constant desire for action is associated

with lassitude. The **spinal cord** is first stimulated, then paralysed.

In a frog the primary stimulation quickly passes off, and there follows gradually increasing weakness both of respiratory and voluntary movements, until these become entirely abolished. If the frog be kept in this condition for four or five days, this state of absolute paralysis passes off and is succeeded by a condition of excitement with violent tetanic convulsions which may be brought on by the slightest afferent stimulus. Various explanations of this action have been given (*vide* p. 171).

The endings of **motor nerves** in voluntary muscles are paralysed by large doses, but small doses will paralyse the efferent nerve-endings which terminate in peripheral ganglia (e.g. vagus), and in involuntary muscle (p. 139). The converse is the case with curare.

Atropine has no action on voluntary **muscles.** Involuntary muscle is paralysed by large doses (p. 139).

On the Eye.—The pupil is dilated and the eye becomes bright, dry, and injected. The power of accommodation is paralysed, and by large doses intraocular tension is increased. For the mode of action, *vide* pp. 220–225.

On the Circulation.—The action of atropine on the excised heart of the frog affords an illustration of the statement I have made (p. 45), that in all probability contradictory observations frequently depend on differences in the temperature at which the observations were made. Thus Bowditch and Luciani found the contractions, both of the frog's heart containing ganglia and of the apex alone (p. 308), were rendered more powerful by atropine, while Gnauck, on the contrary, found that the contractions of the ventricle were diminished both by atropine and hyoscyamine. Kronecker and Schapiro have found that these contradictory observations are both correct, but at different temperatures. When the temperature is low (7° to 8° C.) the ventricular contractions are enlarged by atropine, but diminished by it when the temperature rises over 15° C. Large doses of atropine completely paralyse the intracardiac inhibitory apparatus, while at the same time they stimulate the vagus centres in the medulla.

Atropine is supposed to act upon inhibitory ganglia in the heart itself, not upon the vagus endings, in which respect it differs from nicotine (*vide* p. 314).

Sometimes there is a primary slowing of the pulse rate, followed by quickening; but it is uncertain whether this is due to stimulation of the vagus centre, or of the inhibitory apparatus in the heart.

Small doses raise the blood-pressure by stimulating the vaso-motor centre in the medulla, but large doses diminish it by paralysing the vaso-motor centre and partly by paralysing the

peripheral vaso-motor ganglia or muscular fibres of the walls
the arteries themselves (p. 282). Atropine also diminishes th
sensibility of the heart to changes of pressure within it (p. 299

On Respiration.—Atropine first quickens, and then slow
respiration. This is due to stimulation and subsequent paralys
of the respiratory centre in the medulla. When injected int
the jugular vein it appears to paralyse the ends of the sensor
fibres of the vagus in the lungs, and thus tends to slow respira
tion at first (p. 245). It arrests secretion from the bronchia
mucous membrane (p. 250).

On Secretion.—Atropine paralyses the secreting fibres
the chorda tympani without affecting the vaso-dilator fibres, s
that when the chorda tympani is stimulated, either directly c
reflexly, the flow of blood to the gland is increased, but no flui
exudes from the duct (p. 361).

It probably has a similar action on many, if not all, glands
including the sweat-glands, milk-glands, mucous glands, pan
creas, and liver. When locally applied it stops the secretion c
milk and sweat. In the case of the sweat it probably paralyse
the efferent sweat-fibres which accompany the vaso-motor fibre
and start from centres in the lumbar and lower dorsal parts c
the cord (Luchsinger). It does not, however, prevent secretio
in the intestine after division of the intestinal nerves (Brunto
and Pye-Smith).

The secretion of **urine** is sometimes increased, but large dose
may cause retention from paralysis of the bladder.

On the Intestines.—**Small doses** increase the movement
of the intestines. This action is probably due to paralysis of th
inhibitory fibres of the splanchnic, since stimulation of the peri
pheral end of the cut splanchnic will cause arrest of movemen
in the unpoisoned, but not in the poisoned, animal. Moderat
doses completely arrest peristaltic movements, but the muscula
fibres of the intestine retain their irritability. Local irritatio
causes a local contraction but no peristalsis. This is probabl
due to paralysis of the intestinal ganglia.

Large doses stop the movements and paralyse the involun
tary muscular fibres of the intestine, so that they only contrac
feebly, or not at all, when directly irritated.

The Temperature is increased by small doses, lessened b
large ones.

Certain animals, especially pigeons and rodents, such a
rabbits, guinea-pigs, and rats, are peculiarly insusceptible to th
action of atropine. It is not improbable that the **insuscepti
bility** of rodents to the action of atropine depends on the ver
slight tonic action which the vagus exerts on the heart in then
in their normal condition. When it is paralysed there is littl
change in the circulation, while in dogs the case is very differen
(p. 287).

Methyl- and ethyl-atropine paralyse the ends of the motor nerves, but do not tetanise; they, however, retain the action of atropine on the eye, heart, &c.

USES.—**Locally applied**, belladonna lessens irritability and pain, and is hence used as a lotion in photophobia.

Solution of atropine is employed to dilate the pupil and paralyse accommodation in many conditions which have already been mentioned (p. 225). Migrainous attacks frequently depend upon astigmatism, hypermetropia, or other visual disturbances, and an attack may sometimes be cut short by the local application of atropine to the eye.

In the form of a plaster or liniment over the tender spots, it is useful in myalgia, neuralgia—especially supraorbital and intercostal neuralgia—pleurodynia, hypersensitiveness of skin, and irritability of the chest muscles seen in phthisical patients. The pain arising from old adhesions due to pleurisy is relieved by a belladonna plaster.

In the form of ointment it lessens pain and spasm in fissure of the anus and the pain and itching of hæmorrhoids.

It is useful in checking local sweating on the head, hands, or feet, in the form of the liniment two or three times a day.

Atropine is used internally to check the sweating of phthisis and other exhausting diseases, in doses of $\frac{1}{200}$ gr., gradually increased. It may be given in pill, or mixture, or hypodermically. The beneficial effect may here be due to paralysis of nerves of sweat-glands, but is probably due also to the stimulating effect on the respiratory centre (p. 443).

Belladonna stops the secretion of milk, and is hence used locally, in plaster or with glycerine (1 in 4), when the mother from any cause is unable to suckle her child, and the breast becomes swollen and inflamed.

In leucorrhœa with ulceration of the os uteri, a pessary made up of 2 gr. of ext. belladonnæ, with 7 gr. of tannin, and cacao butter q.s., is very useful (Trousseau).

Given **internally** atropine is useful in extreme salivation, as in mercurial ptyalism. In chronic constipation, relief is often afforded by small doses of $\frac{1}{4}$-gr. of the extract of belladonna; in children the tincture in a proportionate dose is more suitable than the extract. Its action here may be due to diversion of a stimulus from the inhibitory to the motor fibres of the splanchnic, or to paralysis of the inhibitory fibres of the splanchnics (p. 386). It lessens griping, hence it is a useful adjunct to purgatives. It is useful in cases of spasm of involuntary muscles, as in lead colic, simple colic, asthma, and in the spasm set up by renal and biliary calculi (cf. p. 171).

Internally it is useful in palpitation due to cardiac strain (p. 299), and sometimes gives relief in angina pectoris. One of the most useful applications in all cases of palpitation, whether

accompanied by pain or not, is a belladonna plaster to the cardiac region. As atropine, while it appears to lessen the excitability of the ends of the vagus in the lung, excites the respiratory centre, its action in preventing cough is slight and uncertain. As it has the power of completely arresting secretion from the bronchial tubes it is useful in cases where there is excessive secretion, but where the bronchial mucous membrane is already too dry, it is injurious (p. 250). In incontinence of urine in children belladonna is a most useful remedy. It probably acts by lessening the irritability of the bladder. It is also very serviceable in irritability of the bladder with frequent micturition in adults (p. 445).

In epilepsy and chorea it is not of much use, but in frontal headaches it is useful in doses of 3 min. of tincture every three hours.

Atropine has been given internally for urticaria; it sometimes produces striking, though temporary, effects in hyperidrosis.

As an antidote to opium, 4 min. of liquor atropinæ, B.P. may be injected subcutaneously, and repeated every quarter of an hour until the pupil dilates.

It has also been used in poisoning by Calabar-bean, and has been found useful in chloroform-poisoning, when death is impending from stoppage of the heart. Doses sufficiently large to paralyse the inhibitory apparatus must be used.

Hyoscyami Folia, B.P.; Hyoscyamus, U.S.P. HYOSCYAMUS LEAVES, B.P.; HYOSCYAMUS, U.S.P.—The fresh leaves, with the branches to which they are attached, of *Hyoscyamus niger*, also the leaves separated from the branches and carefully dried, collected from plants of the second year's growth.

CHARACTERS.—Leaves sinuated, clammy, and hairy. The fresh herb has a strong, unpleasant odour, and a slightly acrid taste, which nearly disappears on drying. The fresh juice, dropped into the eye, dilates the pupil.

COMPOSITION. — A volatile alkaloid, **hyoscyamine**, soluble in water and spirit. It is decomposed, and its physiological action neutralised by caustic alkalis. It is isomeric with, but not identical with, atropine. Nitrate of potassium and other inorganic salts are present in the leaves.

PREPARATIONS.

B.P.		DOSE.
Extractum Hyoscyami		5–10 gr. or more.
Succus	„	30 min. to 1 fl. dr. or more.
Tinctura	„	30 min. to 1 fl. dr.

U.S.P.			
Abstractum Hyoscyami			3–5 gr.
Extractum	„	Alcoholicum	2 gr.
„	„	Fluidum	5–10 min.
Tinctura	„		1 fl. dr.

U.S.P. Hyoscyaminæ Sulphas. SULPHATE OF HYOSCYAMINE, $(C_{17}H_{23}NO_3)_2.H_2SO_4$; 676.—The neutral sulphate of an alkaloid prepared from hyoscyamus.

It is found also in the seeds of *Belladonna Stramonium*, and in *Duboisia myoporoides*, the alkaloid of which (duboisine) is identical with hyoscyamine. Hyoscyamine is isomeric with atropine.

CHARACTERS.—Small golden-yellow, or yellowish-white scales or crystals, or a yellowish-white, amorphous powder, deliquescent on exposure to air, odourless, having a bitter and acrid taste and a neutral reaction.

SOLUBILITY.—Very soluble in water and in alcohol.

REACTIONS.—When heated on platinum foil, the salt chars and is finally completely dissipated. An aqueous solution of the salt is not precipitated by test-solution of platinic chloride. With chloride of gold it yields a precipitate, which, when recrystallised from boiling water acidulated with hydrochloric acid, is deposited on cooling (without rendering the liquid turbid) in brilliant, lustrous, golden-yellow scales (difference from atropine). The aqueous solution yields, with test-solution of chloride of barium, a white precipitate insoluble in hydrochloric acid.

DOSE.—$\frac{1}{60}$ gr. to 1 gr.

ACTION AND USES.—The physiological action of hyoscyamine is like that of atropine and daturine. Hyoscyamus is used chiefly as an adjunct to purgatives to lessen griping. It is also used to lessen spasm, and to allay pain and irritation of the bladder. It has also been employed as a sedative to the nervous system.

U.S.P. Stramonii Folia. STRAMONIUM LEAVES.—The dried leaves of *Datura Stramonium*. Thorn Apple.

CHARACTERS.—Large, ovate, sinuous, deeply cut; of a heavy odour, which is strongest while they are drying, and of a mawkish, faintly bitter, nauseous taste.

COMPOSITION.—A very small proportion of **daturine**. The other constituents are chiefly saline and mineral matters.

Stramonii Semina, B.P.; Stramonii Semen, U.S.P. STRAMONIUM SEEDS, B.P.; STRAMONIUM SEED, U.S.P.—The dried ripe seeds of *Datura Stramonium*.



FIG. 212.—Stramonium seeds.

CHARACTERS.—Brownish-black, reniform, flat, rough; inodorous unless bruised, when they emit a peculiar, heavy smell.

COMPOSITION.—Contains an alkaloid, **daturine**, identical with atropine, and also some **hyoscyamine**.

PREPARATIONS.

B.P.	DOSE.
Extractum Stramonii	¼–½ gr.
Tinctura „	10–30 min.

	U.S.P.	DOSE.
Extractum Stramonii		½-gr.
,, ,,	Fluidum	1 min.
Tinctura ,,		10–30 min.
Unguentum ,,		

ACTION AND USE.—The impure alkaloid daturine, consisting of atropine and hyoscyamine, has exactly the same physiological action as atropine, though less powerful.

The chief use of stramonium is as an **antispasmodic** in cases of asthma. It is often employed in the form of cigarettes during the attack, or the fumes of the ignited powder are inhaled. A mixture of potassii nitras, potassii chloras, stramonium, and ipecacuanha has been employed with good effect in asthma by inhaling the fumes of the ignited mixture. The leaves of *Datura Tatula* have been substituted for *Datura Stramonium*.

Tabaci Folia, B.P.; Tabacum, U.S.P. LEAF TOBACCO B.P.; TOBACCO, U.S.P.—The dried leaves of Virginian Tobacco, *Nicotiana Tabacum*. Cultivated in America.

CHARACTERS.—Large, mottled-brown, ovate or lanceolate, acuminate leaves, up to twenty inches (50 centimetres) long, bearing numerous short glandular hairs; having a peculiar, heavy odour and nauseous bitter, acrid taste; yielding, when distilled with solution of potash, an alkaline fluid which has the peculiar odour of nicotine, and precipitates with perchloride of platinum and tincture of galls. Not manufactured.

COMPOSITION.—A volatile liquid alkaloid, **nicotine**, is contained in tobacco as a malate, and is obtained by distillation with an alkali. The leaves contain also **nicotianin**, or tobacco camphor, which crystallises out from an aqueous distillate. Resin, gum, and several inorganic compounds are also present.

GENERAL ACTION.—Tobacco stimulates and then paralyses the motor nerves of involuntary muscles and the **secreting nerves** of glands. In consequence of this action on the **gastro-intestinal tract**, there is in poisoning by tobacco nausea and vomiting, with intense prostration and wretchedness. In consequence of the action of the drug on the **heart** and **vaso-motor system**, there is paleness of the face, cold sweats, feebleness of circulation, and tendency to faint. The action of tobacco is the same as that of its alkaloid, nicotine, though less powerful. In **frogs, nicotine**, after a period of temporary excitement, causes a tetanic condition in a peculiar attitude, the head being drawn down, the fore legs back, and the hind legs forward; there may be convulsions. This is followed by muscular relaxation. In **warm-blooded animals** there is excitement, difficulty of breathing, followed by trembling, with expulsion of urine and fæces, stupor, staggering gait, convulsions, and death. When the dose is very large, the animal may fall with a loud cry and the convulsions begin at once, deepening into muscular paralysis; and death ensues from failure of respiration, the heart continuing to beat after respiration ceases.

SPECIAL ACTION.—The **spinal cord** is first stimulated (p. 181),

giving rise to convulsions, and is afterwards paralysed. The convulsions are of spinal origin in the frog, as is shown by such experiments as have been already mentioned (p. 180), but those which occur before death in mammals are probably asphyxial.

Circulation.—Nicotine causes a great diminution of pulse-rate and a fall, followed by a rise, of blood-pressure, the pulse-rate still remaining slow; but if a large dose be given, the pulse-rate rises very quickly. The drug first stimulates both the **vagus** roots and its ends in the heart (causing slow pulse-rate), and then paralyses the latter (causing high pulse-rate). It does not, however, paralyse the inhibitory ganglia of the heart, like atropine, since stimulation of the sinus will slow the heart in frogs after nicotine-poisoning. The primary fall of **blood-pressure** is due to the slowing of the **heart**, and the subsequent rise to contraction of the peripheral **vessels**.

Alimentary canal.—Nicotine stimulates peristalsis markedly (p. 383).

The methyl and ethyl derivatives of nicotine have no tetanising influence on the cord, neither, curiously enough, do they paralyse the ends of the motor nerves.

Uses.—Tobacco is used as an enema in supposed intussusception, and was formerly used in the reduction of strangulated hernia, but as death has occurred from this treatment it must be employed with care.

Owing to its influence on the cord, nicotine has been used in tetanus and strychnine-poisoning, but is not of much use.

Tobacco-smoking.—The effects produced on the system by tobacco-smoking may be partly due to nicotine, but are probably rather due to products of its decomposition such as pyridine and collidine. In pipe-smoking pyridine (p. 810) preponderates, but when tobacco is smoked in cigars, where there is free access of air, the chief product of the dry distillation undergone by the tobacco is collidine, which is far less active than pyridine (Vohl and Eulenburg, *vide* p. 812).

In those accustomed to smoke tobacco, it has a soothing effect on the nervous system, but it often acts as a nervous stimulant to mental work, as in reading. In these cases the effect is probably not due to the nicotine itself, but to the stimulus of the smoke on the sensory nerves of the mouth, which reflexly stimulates the vaso-motor centre, and dilates the vessels of the brain; since some people produce the same effect by sucking sweets, or sipping whisky and water (p. 193).

There is no doubt that smoking in excess is injurious. It produces a furred tongue, irritation of the throat, hoarseness, often dyspepsia and irritability of the heart, with a characteristic rhythm and palpitation (smoker's heart). This effect on the heart is like that produced by partial paralysis of the vagus, and disappears when the habit is given up for a time.

Sudden faintness is also apt to occur, so that a previously strong and healthy man will suddenly fall down in a state of syncope without apparent cause, or the faint may be brought on by some mental emotion.

The sight is impaired by habitual excess in tobacco-smoking (p. 228).

Tobacco-smoking is often very useful in asthma, and a pipe after breakfast will often relieve constipation.

Tobacco-snuff is used as an errhine.

SCROPHULARIACEÆ.

Digitalis Folia, B.P.; Digitalis, U.S.P. DIGITALIS LEAF, B.P.; DIGITALIS, FOXGLOVE, U.S.P.—The dried leaf of *Digitalis purpurea*, purple foxglove. Collected from wild indigenous plants when about two-thirds of the flowers are expanded, B.P. The leaves of Digitalis, U.S.P.

CHARACTERS.—Ovate-lanceolate, shortly petiolate, rugose, downy, paler on the under surface, crenate.

COMPOSITION.—Contains a number of active principles formerly included under the name of **digitalin** (*vide* p. 995).

PREPARATIONS.

B.P.		DOSE.
Infusum Digitalis	(3 gr. to 1 fl. oz.)	2–4 fl. dr. or more.
Tinctura „	(54½ gr. to 1 fl. oz.)	5–30 min.

U.S.P.		
Abstractum Digitalis		⅓–1 gr.
Extractum „		¼–⅓ gr.
„ „	Fluidum	1–2 min.
Infusum „		1–2 fl. dr.
Tinctura „		5–10 min.

Infusum Digitalis. INFUSION OF DIGITALIS.—Digitalis leaves, dried, 30 grs. boiling distilled water, 10 fl. oz. Infuse in a covered vessel, for one hour, and strain, B.P. Digitalis in No. 20 powder, 3; cinnamon in No. 20 powder, 3; boiling water, 185; alcohol, 15; water, q.s. Pour the boiling water on the mixed powders and macerate for two hours in a covered vessel. Then strain, add the alcohol and pass enough water through the strainer to make the infusion weigh 200 parts, U.S.

Digitalinum. DIGITALIN. Not officinal.

PREPARATION.—Dissolving out digitalin from an alcoholic extract of the leaves by acetic acid and water, decolorising by animal charcoal. Neutralising by ammonia and precipitating the digitalin by tannic acid. Rubbing with oxide of lead and spirit, to remove the tannic acid. Dissolving out the digitalin with spirit, again decolorising by animal charcoal, evaporating, and purifying by washing with ether.

CHARACTERS.—In porous, mammillated masses or small scales, white, inodorous, and intensely bitter.

SOLUBILITY.—It is readily soluble in spirit, but almost insoluble in water and in pure ether; dissolves in acids, but does not form with them neutral compounds.

REACTIONS.—Its solution in hydrochloric acid is of a faint yellow colour, but rapidly becomes green. It leaves no residue when burned with free access of air. It powerfully irritates the nostrils, and is an active poison.

Dose. — $\frac{1}{60}$–$\frac{1}{30}$ of a grain.

Chemistry of Digitalis.—Formerly the active principle of digitalis was said to be digitalin, but the substances prepared and sold by different manufacturers under this name varied much in their solubility and in the intensity of their physiological action. The most important varieties were Homolle's amorphous digitaline, Nativelle's crystallised digitaline, and soluble or German digitalin.

An examination of the chemistry of digitalis by Schmiedeberg has shown that there are at least **five principles** present in it, and possibly there are present also some products of their decomposition. They are all non-nitrogenous and, with the exception of one, digitoxin, are glucosides. They are : **digitoxin, digitalin, digitaleïn, digitonin,** and **digitin.** The first three of these are cardiac poisons. Digitonin has an action like that of saponin, and digitin appears to be inert.

Digitoxin is quite insoluble in water, and forms the chief constituent in Nativelle's digitaline. By boiling with dilute acids digitoxin yields toxiresin and digitalin yields digitaliresin.

Digitalin is also insoluble in water and is the active principle of Homolle's digitaline. Digitaleïn differs from the two former in being readily soluble in water, and forms a large proportion of the soluble digitalin.

The digitalin of the B.P. 1867, being almost insoluble in water, probably consisted chiefly of digitoxin or digitalin.

General Action.—In large doses digitalis causes sickness, vomiting, muscular weakness, diuresis, subjective affections of vision, laboured respiration, and death ; the heart usually failing before the respiration. The condition of the heart after death varies. Sometimes I have found it in diastole and sometimes in systole in dogs poisoned by digitalis.

Special Action.—On the **muscles.** In a number of unpublished experiments on this subject made in 1867–68 in the laboratories of Professors Brücke and J. Rosenthal, I found that soluble digitalin did not lessen the excitability of the unweighted muscle but diminished its power to lift a weight. According to Schmiedeberg and Koppe digitalis paralyses all voluntary muscles. Digitalin causes elongation of the muscle with increased elasticity in the frog.

On the **nervous system.** It has no marked action on sensory or motor nerves. It has little action on the spinal **cord.** It has been stated to lessen reflex action in the frog by stimulation of Setchenow's centre, but this may be due to reflex irritation from the point of injection (p. 171). The **brain** is unaffected, and in cases of poisoning remains clear to the last. (Two of the products of the decomposition of digitalin, toxiresin and digitaliresin, however, produce convulsions like those of picrotoxin.) Large doses cause subjective affections of vision, consisting in dimness,

occasional flashes of light, or in the constant appearance of rainbow or bright light before the eyes. Locally applied to th eye it produces irritation at first, and afterwards causes a ha to surround bright objects.

The **respiration** is generally somewhat slowed, and occa sionally before death may become excessively slow.

The effects produced on the circulation by the active principl of digitalis and by substances having a similar action, such a oleandrin, scillain, adonidin, neriin, convalamarin, antiarin, an helleborein, may be divided according to Schmiedeberg into fou stages:—

1. Rise of blood-pressure, usually though not invariabl accompanied by slowing of the pulse.

2. Continued rise of blood-pressure, with a quick pulse.

3. Continued high pressure, with irregularity of the heart action and pulse-rate.

4. Rapid fall of the blood-pressure, sudden stoppage of th heart, and death.

The rise in **blood-pressure** is regarded by Schmiedeber Boehm, and others as entirely due to increased action of th **heart** and not at all to contraction of the vessels. With th view I cannot agree, and I still hold to the opinion which I ex pressed many years ago that the rise in pressure is due in grea measure to contraction of the **arterioles.** Not only is it mor difficult to raise the pressure in the arterial system by alteration in the heart's action than by contraction of the arterioles, as w find from experiments on a schema (p. 266), but the form of th pulse-curve under the action of digitalis conclusively demon strates that the arterioles are contracted (*vide* p. 276). This ha also been demonstrated by Donaldson and Stevens,[1] who foun that the addition of digitalis to blood lessens the flow throug vessels in which circulation was artificially maintained. similar result has been obtained by Ringer.

The slow pulse in the first stage of digitalis-poisoning partly due to stimulation of the **vagus-roots** of the medulla, ar partly to increased sensibility or actual stimulation of the end of the nerves in the heart. This increased sensibility has bee shown to exist by Boehm, who found that after the admini tration of digitalis, a faradaic current which previously had n action on the heart would not only slow the pulse but produc prolonged diastolic arrest.

The rapid pulse in the second stage of digitalis-poisonin is due to paralysis of the **vagus-ends.** The irregularities in th third stage depend on the action of the drug on the heart itself

The action of digitalis on the **frog's heart** is very peculia At first it causes the pulsations to become slower and mor

[1] *Journal of Physiology*, vol. iv. p. 165.

powerful, then the contraction during systole becomes peristaltic, and the dilatation during diastole less and less complete, until





FIG. 213.—Pulse-wave, *b* before and *a* after injection of digitalis in a dog.

finally the ventricle stands quite still, in such complete systolic contraction that its cavity is entirely obliterated. The auricles are sometimes distended with blood, sometimes only moderately dilated. According to Schmiedeberg this contraction is not tetanic, but is rather due to increased elasticity of the cardiac muscle which prevents its normal relaxation during diastole. When it is overcome by driving a nutrient fluid into the ventricle under pressure, or by partially paralysing the cardiac muscle by saponin, apomorphine, or hydrocyanic acid, the systolic stillstand is removed, and pulsation again commences.

Digestive Organs.—Small doses of digitalin have a pleasant bitter taste but exercise no marked effect upon the digestive organs. Larger doses produce loss of appetite, nausea, and vomiting, with rumbling and pain in the abdomen, and sometimes diarrhœa. This occurs even when the drug is injected subcutaneously.

Urine.—All observers are agreed regarding the diuretic power of digitalis in cardiac disease, but most of them state that it has no such power in health. In my own experiments, however, in which I took the same quantity of food by weight and of fluid by measure during more than a hundred days, I found that, while small doses had little or no action, marked diuresis occurred when the drug was pushed so as to produce symptoms of poisoning. In these experiments also I found that while the diuresis continued the absolute quantity of solids excreted daily in the urine was increased, although their proportion to the urinary water was diminished. In cases of poisoning by digitalis, a marked diminution in the flow of urine frequently precedes a fatal issue; and on injecting digitalis into the veins of a dog, Mr. Power and I found that the secretion of urine became entirely arrested when the blood-pressure reached its maximum, and again commenced when the blood-pressure began to fall (p. 430). It is probably to the power of digitalis to arrest the action of the kidneys and thus stop its own excretion that its cumulative action is due (p. 42).

Effect of Temperature on the Action of Digitalis.—I has already been mentioned (p. 47) that digitalis has sometime no action on the pulse in pneumonia. The inhibitory action o



The unbroken line shows the pulse-rate, the dotted line shows the temperature in the axilla in all the figures.

FIG. 214.—Shows the effect of rise of temperature alone. At the 195th minute both vagi were cut the section was not followed immediately by any apparent effect. After eight minutes mor the pulse-rate rose slightly and then fell.

the vagi on the heart is lessened by heat, but their peripher terminations, although weakened, are not completely paralysed Dr. Cash and I have made some experiments which appear t show that a very high temperature has an action on the vagu centre in the medulla similar to its action on the ends of th nerve in the heart. It does not completely paralyse either th centre or the peripheral ends of the nerve, but it greatly weaken




FIG. 215.—Shows the effect of rise of temperature after injection of digitalis. At the 45th minu ·75 c.c. (12 minims) tincture of digitalis were injected, and another similar injection was ma at the 55th minute. At the 65th minute the heating was begun. After section of the vagi t pulse continued to rise, but not more rapidly than before.

them. This weakening action is so great that it practicall amounts to paralysis, for when the temperature rises above

certain point the pulse-rate suddenly rises just as it would do if both vagi were cut. This is shown in Fig. 214. When the pulse-rate has been thus quickened by heat, section of the vagi does not render it any quicker (Figs. 215 and 216).

Although the vagus centre is so much weakened by the action of the heat that it ceases to exercise any inhibitory action upon the heart, yet its functional activity is not completely de-




FIG. 216.—Shows the action of digitalis when given after the temperature has already risen. At the 30th minute the warming was begun; at the 100th minute ·75 c.c. of tincture of digitalis was injected.

stroyed even by very high temperatures, and irritation of an afferent nerve will still cause reflex slowing (p. 290) of the pulse, until immediately before the death of the animal from hyperpyrexia.

These experiments render it probable that the rapid rise in the pulse-rate, which a high temperature occasions, is chiefly of central origin, and is due to partial paralysis of the vagus centre, although diminished action of the peripheral ends of the vagus and increased action of the cardiac ganglia also aid in quickening the pulse.

Although neither the vagus centre nor the vagus ends in the heart are completely paralysed by very high temperatures they are yet weakened so much that digitalis, and probably all drugs which act like it, such as adonidin (p. 331), no longer slow the pulse as they do at normal temperatures. This is shown in Fig. 216, where the pulse remained slow until the temperature rose to nearly 41° C. and then suddenly became very quick. Moderately high temperatures do not prevent digitalis from slowing the heart (Fig. 214).

Action of Different Preparations of Digitalis.—The two most marked effects of digitalis in disease are a reduction in the rate of the pulse, and an increase in the amount of urine. These effects are not coincident, and, according to Christison, the diuretic action is less when the heart is much affected. The preparation generally employed to act on the heart is the tincture, while the infusion is regarded as the best diuretic.[1] The

[1] *The National Dispensatory.*

differences between the action of the infusion and tincture o digitalis are probably due, in part at least, to the different pro portions in which the active principles of the plant are dissolve by alcohol and water.

In digitalis, as in physostigma (p. 904) and many othe plants, there is a mixture of principles having antagonisti actions. Digitonin, which has an action very like saponin (pp 307, 915), will to a greater or less extent antagonise the actio of digitoxin, digitalin, and digitaleïn. Digitonin is readil soluble in water, forming, like saponin, a solution which froth easily. Digitaleïn is soluble in water, but digitalin is only spar ingly so, and digitoxin is hardly soluble in water at all.

The solubility of these substances in alcohol is almost th converse of their solubility in water. Digitonin is sparingl soluble in alcohol, while digitalin and digitaleïn are readil soluble. Digitoxin is only sparingly soluble in cold alcohol.

From the ready solubility of digitonin in water, infusion o digitalis will contain it in much larger proportion than digitali or digitaleïn. This, indeed, is readily seen by putting some in fusion of digitalis into one bottle and a corresponding dose o the tincture diluted with water until both solutions have th same bulk. On shaking the bottles, the infusion will be foun to froth much more strongly and to retain the froth muc longer than the diluted tincture, although the latter also froth strongly.

Tincture of digitalis will, on the other hand, contain a large proportion of digitalin and digitaleïn, with probably a sma quantity of digitoxin.

It is quite possible, however, that in addition to differenc in the preparations due to the menstruum, there may be diffe ences in the same preparation due to the plants used. Thus i Edinburgh the usual dose of the infusion is half an ounce, an this is usually readily tolerated, while in London I have fr quently seen doses of one or two drachms produce considerab gastric disturbance. The infusion of the U.S.P. is nearly twic as strong as that of the B.P., and yet the recognised dose is co siderably larger.

Whether these differences are or are not due to the amou and relative proportions of the active ingredients in digital plants grown in Scotland, England, and America, is a poi which requires investigation, more especially when we have oth examples, e.g. cannabis indica, where there is a notable differen between the action of plants of the same species growing in di ferent climates.

Uses.—It is chiefly used as a tonic to the heart, when i action is irregular and feeble, and in dropsy, especially cardi dropsy (pp. 332, 336).

It is used in functional palpitation, and in the irritable hea

often seen in young soldiers, but its chief use is in mitral disease.

In pure aortic disease, with hypertrophy, it is not only injurious but dangerous, since by slowing the pulse-rate it lengthens the time during which blood can regurgitate (pp. 333, 334).

When the aortic disease is accompanied by mitral incompetence and the immediate danger is that from the mitral affection, it may be given with advantage (p. 334). In these cases, whilst taking the drug the patient must be kept perfectly quiet, as there is a great danger of sudden syncope (p. 335).

Digitalis is of great use as a soporific in sleeplessness at night, accompanied by drowsiness during the day, for both these symptoms depend on want of tone in the vessels, the blood gravitating to the feet when the patient is erect and to the head when in a lying posture (p. 194).

It is very useful in hæmorrhages, especially when occurring in the lungs, and it has been added to cough mixtures to lessen congestion of the mucous membrane.

It was formerly used in fever and pneumonia, but is now discarded as being of very little use.

In delirium tremens it has been given in very large doses, but its use is dangerous.

In dropsy depending on mitral disease, also in renal dropsy and ascites, it has been used with good effect.

It is very serviceable in some cases of menorrhagia. Its action in this case is due not to contraction of the vessels of the uterus, but of the walls of the uterus itself, since digitalis did not affect hæmorrhage from a fungoid growth in the cervix (Dickinson).

It is also useful in spermatorrhœa.

PRECAUTIONS.—(1) Stop the administration of digitalis on the appearance of sickness or a tendency to faint, or change the preparation of digitalis and lower the dose.

(2) Do not give digitalis in large doses unless you see the patient frequently, and it is necessary to push the drug. Keep the patient in bed, and do not allow him even to sit up in bed, much less to rise, and above all not to rise up and make water, as otherwise fatal syncope may occur (p. 265).

TREATMENT ON POISONING.—Keep the patient recumbent and give stimulants, e.g. alcohol. Tannin has been recommended in order to precipitate digitalin in the stomach.

U.S.P. Leptandra. LEPTANDRA. CULVER'S ROOT.—The rhizome and rootlets of *Leptandra virginica* (*Veronica virginica*).

CHARACTERS.—Horizontal, from four to six inches (10 to 15 centimetres) long, and about a quarter of an inch (6 millimetres) thick, somewhat flattened, bent and branched, deep blackish-brown, with cup-shaped scars on the upper side, hard, of a woody fracture, with a thin, blackish bark, a hard,

yellowish wood, and a large, purplish-brown, about six-rayed pith; rootlets thin, wrinkled, very fragile; inodorous; taste bitter and feebly acrid.

DOSE.—Of the root, 20–60 gr. (1·5–4 gm.).

PREPARATIONS.

	DOSE.
Extractum Leptandræ	2–4 gr.
,, ,, Fluidum	30–60 min.

COMPOSITION.—It contains a resinous principle, **leptandrin**.

ACTION.—It is an irritant to the gastro-intestinal mucous membrane, and **stimulates** the secretion of **bile** (p. 403). It may be used as a **cathartic** in biliousness or constipation.

PEDALINEÆ.

U.S.P. Oleum Sesami. OIL OF SESAMUM. (Benné Oil.)—A fixed oil expressed from the seed of *Sesamum indicum*.

CHARACTERS.—A yellowish or yellow, oily liquid, inodorous or nearly so, having a bland, nut-like taste, and a neutral reaction.

ACTION.—Similar to olive oil (*q.v.* p. 967).

VERBENACEÆ.

Lippia Mexicana. Not officinal.—An evergreen creeping shrub growing in Mexico. The parts used are the leaves and flowers.

COMPOSITION.—It contains a volatile oil—**lippiol**—a camphor-like body, and a substance allied to quercitin.

ACTION.—Lippiol in doses of 3 gr. (0·2 gm.) caused in a cat within half an hour slight dilatation of the pupil and nictitation (probably due to gastro-enteric irritation, p. 218). A repetition of the dose caused vomiting, restlessness, and sleep lasting for two hours. In doses of 4½ gr. (0·3 gm.) it causes warmth, flushing, diaphoresis, and drowsiness (Podwissotzki).

USES.—As a **respiratory sedative** in cough. Given as tincture in doses of ½–1 fl. dr.

LABIATÆ.

Rosmarinus, U.S.P. ROSEMARY.—The leaves of *Rosmarinus officinalis*.

CHARACTERS.—About one inch (25 millimetres) long, rigid, linear, entire, revolute, dark green above, woolly and glandular beneath; pungently aromatic; somewhat camphoraceous.

PREPARATION.

Vinum Aromaticum.

Oleum Rosmarini, B. and U.S.P. OIL OF ROSEMARY.—The oil distilled from the flowering tops of *Rosmarinus officinalis*, B.P. A volatile oil distilled from rosemary, U.S.P.

CHARACTERS.—Colourless, with the odour of rosemary, and a warm aromatic taste.

DOSE.—1–5 min.

PREPARATIONS.

B.P.	DOSE.
Linimentum Saponis (p. 516)	for external use.
Spiritus Rosmarini	10–50 min. or more.
Tinctura Lavandulæ Composita	½–2 fl. dr.

U.S.P.

Linimentum Saponis (p. 517)	for external use.
Spiritus Odoratus	do.
Tinctura Lavandulæ Composita	½–2 fl. dr.

ACTION AND USE.—It is a stimulant and **carminative**, and is used to lessen flatulence, and to allay pain and spasm of the intestines. It is a useful adjunct to purgatives, and is used in hysteria.

U.S.P. Lavandulæ. LAVENDER.—The flowers of *Lavandula vera*.

CHARACTERS.—Calyx tubular, blue-grey, hairy, five-toothed, the upper tooth largest and roundish-rhomboid; corolla violet-blue, hairy and glandular on the outside, tubular and two-lipped, the upper lip two-lobed, the lower lip three-lobed; stamens four, short, on the corolla tube; odour fragrant; taste bitterish, aromatic, somewhat camphoraceous.

PREPARATION.

Vinum Aromaticum.

Oleum Lavandulæ, B. and U.S.P. OIL OF LAVENDER.—The oil distilled in Britain from the flowers of *Lavandula vera*, B.P. A volatile oil distilled from the flowering tops or whole herb of *Lavandula vera*, U.S.P.

CHARACTERS.—Colourless or pale yellow, with the odour of lavender, and a hot, bitter, aromatic taste.

DOSE.—1–4 min.

PREPARATIONS.

B.P.	DOSE.
Linimentum Camphoræ Compositum (p. 516)	
Spiritus Lavandulæ	½–1 fl. dr.
Tinctura „ Composita	½–2 fl. dr.

U.S.P.

Tinctura Lavandulæ Composita	½–2 fl. dr.

Tinctura Lavandulæ Composita, B. and U.S.P. COMPOUND TINCTURE OF LAVENDER.—Oil of lavender 1½ fl. dr., oil of rosemary 10 min., cinnamon bark, bruised, 150 gr., nutmeg, bruised, 150 gr., red sandal-wood 300 gr., rectified spirit 2 pints, B.P. Oil of lavender 8 parts, oil of rosemary 2, cloves 4, nutmeg 10, red saunders 8, alcohol 680, water 270, and diluted alcohol up to 1,000 parts, U.S.P.

U.S.P. Oleum Lavandulæ Florum. Oil of Lavender Flowers.—A volatile oil distilled from fresh lavender.

Characters.—A colourless or yellowish liquid, having the fragrant odour of lavender flowers, a pungent and bitterish taste, and a neutral reaction while fresh. Sp. gr. about 0·890. It is readily soluble in alcohol, and in acetic acid of 90 or more per cent. When heated to about 80° C. (176° F.) it should not yield a colourless distillate having the characteristics of alcohol.

Dose.—1–5 min.

Preparations.

U.S.P.	DOSE.
Spiritus Lavandulæ (3 parts of the oil with 97 of alcohol)	½–2 fl. dr.
Spiritus Odoratus	

Action and Uses.—Lavender is a **stimulant** and **carminative**, and is used to lessen flatulence, to relieve colic, and in hysteria. Tinctura Lavandulæ Composita is contained in Liquor Arsenicalis.

Oleum Menthæ Piperitæ, B. and U.S.P. Oil of Peppermint.—The oil distilled in Britain from fresh flowering peppermint, *Mentha piperita*, B.P.

A volatile oil distilled from peppermint, U.S.P.

Characters.—Colourless or pale yellow, with the odour of peppermint, taste warm, aromatic, succeeded by a sensation of coldness in the mouth.

Preparations.

B.P.	DOSE.
Aqua Menthæ Piperitæ (1½ fl. dr. to 1 gallon)	1–2 fl. oz.
Essentia Menthæ Piperitæ (1 volume in 5)	10–20 min.
Pilula Rhei Composita (*vide* p. 523) (1 min. in 1 dr.)	nearly 5–10 gr.
Spiritus Menthæ Piperitæ (1 volume in 50)	½ fl. dr.
Tinctura Chloroformi et Morphinæ (1 min. in 2 fl. oz.)	5–10 min.

Dose.—1–5 min.

U.S.P.	
Aqua Menthæ Piperitæ	1–2 fl. oz.
Spiritus Menthæ Piperitæ	10–15 min.
Trochisci Menthæ Piperitæ (Peppermint Lozenges)	ad lib.

Action and Use.—**Carminative** and stimulant, used to relieve flatulence and colic; and as an adjunct to purgatives, to lessen griping. Mosquito-bites may be prevented by rubbing the skin of the face and hands, the lips and the margins of the nostrils with soap strongly scented with peppermint or lavender. A sprig of peppermint or pennyroyal, or a small bottle containing their volatile oils, hung near the head during sleep is said to have a similar effect. Peppermint lozenges are useful in relieving flatulence and the tendency to faintness due to it.

B.P. Menthol. $C_{10}H_{20}O$. Peppermint Camphor.—A stearoptene obtained by cooling the oil distilled from the fresh herb of *Mentha arvensis*, vars. *piperascens et glabrata*; and of *Mentha piperita*.

CHARACTERS.—Colourless crystals or masses, with a taste and smell of peppermint oil, sparingly soluble in water, readily soluble in alcohol, ether, and ethereal oils. When rubbed up with an equal quantity of thymol it forms a colourless oily liquid. The same is the case when it is rubbed with an equal quantity of pure carbolic acid or of chloral hydrate, or with butyl-chloral hydrate in the proportion of 1 part to 2 of menthol, or with camphor 2 parts to 3 of menthol. When boiled with sulphuric acid diluted with half its volume of water it becomes blue, the acid becoming brown.

ACTION.—It is a powerful **antiseptic.** When applied to mucous membranes or the skin it causes a feeling of warmth or burning, replaced by a feeling of coldness when the part is blown upon.

USES.—It is chiefly used as an **anti-neuralgic.** It is either applied in the form of a solid pencil rubbed lightly over the part where the pain is felt, or an alcoholic solution, or the oily liquids prepared by trituration with camphor, carbolic acid, &c., may be painted over the painful spots. These oily liquids are also applied on cotton wool in order to relieve toothache.

Oleum Menthæ Viridis, B. and U.S.P. OIL OF SPEARMINT. The oil distilled in Britain from fresh flowering spearmint, *Mentha viridis*, B.P.

CHARACTERS.—Colourless or pale yellow, with the odour and taste of spearmint.

DOSE.—1–5 min.

PREPARATIONS.

B.P.	DOSE.
Aquæ Menthæ Viridis (1½ fl. dr. to 1 gallon)	1–2 fl. oz.

U.S.P.	
Aqua Menthæ Viridis	1–2 fl. oz.
Spiritus Menthæ Viridis	5–20 min.

ACTION AND USES.—Like other **carminatives** and stimulants, to relieve colic, flatulence, and with purgatives to prevent griping.

Thymol, B. and U.S.P. THYMOL. $C_{10}H_{13}HO$, or $C_6H_3.C_3H_7.CH_3.OH$.—A stearoptene obtained from the volatile oils of *Thymus vulgaris* (Labiatæ), *Monarda punctata* (Labiatæ), and *Carum Ajowan* (*Ptychotis Ajowan*) (Umbelliferæ).

These oils contain **thymol** and **thymene**, $C_{10}H_{16}$, which is fluid. The thymol is separated by saponifying with caustic soda and treating the separated soap with hydrochloric acid, or from a distilled fraction of the oil by exposure at a low temperature. It may be purified by recrystallisation from alcohol.

CHARACTERS.—Large oblique prismatic crystals having the odour of thyme and a pungent aromatic flavour. They sink in cold water, but on heating the mixture to a temperature of 110° to 125° F. (43·3° to 51·7° C.) they melt and rise to the surface. The crystals volatilise completely at the temperature of a water-bath.

SOLUBILITY.—Slightly soluble in cold water, freely soluble in alcohol, ether, and solutions of alkalis.

REACTIONS.—A solution of thymol in half its bulk of glacial acetic acid, warmed with an equal volume of sulphuric acid, assumes a reddish-violet colour.

IMPURITY.—Carbolic acid.

TEST.—Water saturated with thymol when treated with a few drops of test solution of ferric chloride should not give a blue colour (absence of carbolic acid).

DOSE.—Internally, ½–10 gr. For spray, 1 in 800 of hot water. As ointment, 5–30 gr. to 1 oz. of petrolatum. As inhalation, 6 gr. to an ounce of warm water.

ACTION.—In respect of its physiological action, thymol appears to stand between carbolic acid and oil of turpentine. Like carbolic acid, it destroys low organisms, and is a powerful **antiseptic**. In higher animals it acts as a local irritant and anæsthetic to the skin and mucous membranes. When absorbed it **paralyses** the **nerve-centres** in the **cord** and **medulla**, like carbolic acid, lessening reflex action, slowing **respiration**, and lowering the **blood-pressure** and **temperature**. In poisonous doses it causes weakness, drowsiness, coma, and death. It differs from carbolic acid in being less volatile and less easily oxidised. Its action as a disinfectant is more permanent, and at the same time more powerful than that of carbolic acid. It is less irritating to the skin or mucous membrane, and does not act as a caustic like carbolic acid, and is a less powerful poison to mammals. Its action on the nerve-centres is a paralysing one from the first, and is not preceded by excitement as in the case of carbolic acid. While in the body it appears to effect tissue-metabolism, for in animals poisoned by it the liver is found quite fatty, as in phosphorus-poisoning. It appears to be **eliminated** by the respiratory and urinary organs, and to cause irritation of these organs during the process of excretion. In poisoning by it the bronchial mucous membrane is extremely congested, the secretion of mucus increased; the lungs congested, and sometimes consolidated; the kidneys inflamed, and the urine albuminous or bloody.

USES.—It has been used as an **antiseptic** instead of carbolic acid for dressing wounds; as an application to skin diseases, ringworm, eczema, psoriasis; as a gargle, spray, or inhalation in sore-throat, bronchiectasis, and phthisis, or as an injection in ozæna. Internally it has been used in diabetes and vesical catarrh.

U.S.P. Hedeoma. HEDEOMA. PENNYROYAL.—The leaves and tops of *Hedeoma pulegioides*.

CHARACTERS.—Leaves opposite, short-petioled, about half an inch (12 millimetres) long, oblong-ovate, obscurely serrate, glandular beneath; branches roundish-quadrangular; flowers in small, axillary cymules, with a tubular-ovoid, two-lipped and five-toothed calyx, and a pale-blue, spotted, two-lipped corolla, containing two sterile and two fertile exserted stamens; odour strong, mint-like; taste warm and pungent.

PREPARATION.

U.S.P.	DOSE.
Oleum Hedeomæ	1–5 min.

COMPOSITION.—It contains a **volatile oil.**

ACTION AND USES.—It is stimulant, **carminative,** diaphoretic, and **emmenagogue.** It is used in flatulence and in amenorrhœa. It is frequently given in the form of hot infusion, to promote the menstrual flow when delay or recent suppression has occurred.

U.S.P. Marrubium. MARRUBIUM. HOREHOUND.—The leaves and tops of *Marrubium vulgare.*

CHARACTERS.—Leaves about one inch (25 millimetres) long, opposite, petiolate, roundish-ovate, obtuse, coarsely crenate, strongly rugose, downy above, white-hairy beneath; branches quadrangular, white tomentose; flowers in dense, axillary, woolly whorls, with a stiffly ten-toothed calx, a whitish bi-labiate corolla, and four included stamens; aromatic and bitter.

COMPOSITION.—It contains a **volatile oil** and a bitter principle, **marrubiin.**

DOSE.—30–60 gr. (2–4 gm.).

USES.—It is **expectorant,** tonic, diaphoretic, and diuretic. In large doses it is laxative. It is employed in laryngeal and bronchial catarrh, and in chronic affections of the lungs attended with cough and copious expectoration.

U.S.P. Melissa. MELISSA. BALM.—The leaves and tops of *Melissa officinalis.*

CHARACTERS.—Leaves about 2 inches (5 centimetres) long, petiolate, ovate, obtuse, crenate, somewhat hairy, glandular; branches quadrangular; flowers in about four-flowered cymules, with a tubular, bell-shaped, five-toothed calyx, a whitish or purplish two-lipped corolla, and four stamens; fragrant, aromatic, and bitterish.

COMPOSITION.—It contains a small quantity of a **volatile oil.**

USES.—It has scarcely any remedial action, but is used in the form of warm infusion or tea as a **diaphoretic** in slight febrile conditions.

U.S.P. Origanum. ORIGANUM. WILD MARJORAM.—*Origanum vulgare.*

CHARACTERS.—Stem branched above, often purplish, leaves opposite, petiolate, about an inch (25 millimetres) long, roundish-ovate, obtuse, nearly entire, pellucid-punctate, hairy beneath; flowers in corymbs, with reddish bracts, a five-toothed calyx, a somewhat two-lipped, pale purple corolla, and four exserted stamens; aromatic, pungent, and bitterish.

PREPARATION.

Vinum Aromaticum. Used externally.

COMPOSITION.—It contains a **volatile oil,** which has been largely superseded by the oil of thyme.

ACTION AND USES.—The infusion is tonic, **diaphoretic,** and **emmenagogue.** It is also used externally as a fomentation.

U.S.P. Salvia. SALVIA. SAGE.—The leaves of *Salvia officinalis*.

CHARACTERS.—About two inches (5 centimetres) long, petiolate, ovate-oblong, obtuse, finely crenulate, thickish, wrinkled, greyish-green, soft-hairy and glandular beneath; aromatic, bitterish, somewhat astringent.

PREPARATION.

Vinum Aromaticum. Used externally only.

COMPOSITION.—The leaves contain a **volatile oil**.

USES.—They are chiefly used as a condiment. The infusion is **tonic**, carminative, and slightly **astringent**. It is used in atonic dyspepsia, and to check hectic sweating.

U.S.P. Scutellaria. SCUTELLARIA. SKULL-CAP.—*Scutellaria lateriflora* (whole plant).

CHARACTERS.—About twenty inches (50 centimetres) long, smooth; stem quadrangular, branched; leaves opposite, petiolate, about two inches (5 centimetres) long, ovate-lanceolate or ovate-oblong, serrate; flowers in axillary one-sided racemes, with a pale blue corolla and a two-lipped calyx, closed in fruit, the upper lip helmet-shaped; odour slight; taste bitterish.

PREPARATION.

U.S.P.	DOSE.
Extractum Scutellariæ Fluidum	1–2 fl. dr.

USES.—As a remedy it has little value. It has been used as a nervine **tonic** in neuralgia, chorea, delirium tremens, and nervous exhaustion.

CHAPTER XXXV.

Class III.—DICOTYLEDONES MONOCHLAMYDEÆ.

(APETALÆ.)

CHENOPODIACEÆ.

U.S.P. Chenopodium. CHENOPODIUM. AMERICAN WORMSEED. The fruit of *Chenopodium ambrosioides*, var. *anthelminticum*.

CHARACTERS.—Nearly one-twelfth of an inch (2 millimetres) in diameter, depressed-globular, glandular, dull greenish or brownish, the integuments friable, containing a lenticular, obtusely-edged, glossy, black seed. It has a peculiar, somewhat terebinthinate odour, and a bitterish, pungent taste.

DOSE.—10–40 grains.

U.S.P. Oleum Chenopodii.—A volatile oil distilled from wormseed.

USE.—It is used as a **vermifuge** to expel lumbricoid worms. The powdered seeds, which possess the active medicinal virtues, may be combined with some agreeable elixir, or the essential oil may be given on a lump of sugar, or in emulsion in doses of 3–5 minims.

PHYTOLACCACEÆ.

U.S.P. Phytolaccæ Bacca. PHYTOLACCA BERRY. POKE BERRY. The fruit of *Phytolacca decandra*.

CHARACTERS.—A depressed-globular, dark purple, compound berry, about one-third of an inch (8 millimetres) in diameter, composed of ten carpels, each containing one lenticular, black seed; juice purplish-red; inodorous; sweet, slightly acrid.

U.S.P. Phytolaccæ Radix. PHYTOLACCA ROOT. POKE ROOT. The root of *Phytolacca decandra*.

CHARACTERS.—Branched, wrinkled, yellowish-brown externally, yellowish-white internally. Transverse sections exhibit numerous concentric rings. No smell; taste sweetish, and afterwards acrid.

ACTION.—Poke is **emetic**, cathartic, and somewhat **narcotic**, producing in large doses vomiting, purging, drowsiness, dimness of vision, giddiness, and sometimes convulsions. It has been proposed as an emetic instead of ipecacuan, but its action is too slow. As an **alterative** it has been recommended in rheumatism. Externally a strong infusion or decoction of the root has been used in piles, skin diseases, and cancer.

POLYGONACEÆ.

Rhei Radix, B.P.; Rheum, U.S.P. Rhubarb Root, B.P.; Rhubarb, U.S.P.—The root more or less deprived of its bark, sliced and dried, of *Rheum palmatum*, *Rheum officinale*, and probably other species. Collected and prepared in China and Thibet.

Characters.—Trapezoidal, roundish, cylindrical, or flattish pieces, frequently bored with one hole, yellow externally, internally marbled with fine waving greyish and reddish lines, finely gritty under the teeth; taste bitter, faintly astringent and aromatic; odour peculiar.

Composition.—The chief constituent is **chrysophanic acid**, so-named from its forming briliant yellow crystals. It is extracted by ether or alcohol, not by water. Besides this there is also a glucoside **chrysophan**, which splits up into chrysophanic acid and sugar. There are also several resinous matters, one of which, **phaoretin**, is purgative, and mineral compounds are also present, especially oxalate of calcium. The astringency of rhubarb is due to a peculiar tannic acid (**rheo-tannic**), which is soluble in water and alcohol, but not in ether.

Impurities.—English rhubarb and turmeric fraudulently added.

Tests.—Odour and taste (English rhubarb). Boracic acid does not turn the yellow exterior brown (turmeric).

Dose.—Of the powdered root, 1–5 gr. as a stomachic; 10–30 gr. as a purgative.

Preparations.

B.P.	dose.
Extractum Rhei	5–15 gr.
Infusum Rhei (¼-oz. in ½-pint for 1 hour)	1–2 fl. oz.
Pilula Rhei Composita (*vide* p. 523)	5–10 gr.
Pulvis Rhei Compositus	5–10 gr. (child).
,, ,, ,,	20–60 gr. (adult).
Syrupus Rhei	1–4 fl. dr.
Tinctura Rhei	1–2 fl. dr. (stomachic).
,, ,,	½–1 fl. oz. (purgative).
Vinum Rhei	1–2 fl. dr.

U.S.P.

Rheum.	
Extractum Rhei	3–10 gr.
Extractum Rhei Fluidum	1–10 min.
Pilulæ Rhei (*vide* p. 523)	1–3 pills (3 gr. each).
Pilulæ Rhei Compositæ (*vide* p. 523)	1–4 pills.
Pulvis Rhei Compositus	30–60 gr.
Syrupus Rhei	1–4 fl. dr. } for children.
Syrupus Rhei Aromaticus	1–4 fl. dr. }
Tinctura Rhei	1–6 fl. dr.
Tinctura Rhei Aromatica	1–4 fl. dr.
Tinctura Rhei Dulcis	1–4 fl. dr. for children.
Vinum Rhei	1–4 fl. dr.
Mistura Rhei et Sodæ	2 dr.–3 oz.

B.P. Pulvis Rhei Compositus. Compound Powder of Rhubarb (Gregory's

Powder).—Rhubarb root, 2 oz.; light magnesia, 6 oz.; ginger, 1 oz. Mix the powdered ingredients and pass through a fine sieve.

B.P. Syrupus Rhei. Syrup of Rhubarb.—Rhubarb root and coriander fruit, both in coarse powder, each 2 oz.; refined sugar, 24 oz.; rectified spirit, 8 fl. oz.; distilled water, 24 fl. oz. Percolate the rhubarb and coriander with the spirit and water; evaporate the filtrate to 13 fl. oz.; filter; dissolve the sugar in the filtrate.

B.P. Tinctura Rhei. Tincture of Rhubarb.—Rhubarb, 2 oz.; bruised cardamom seeds, ¼ oz.; coriander fruit, ¼ oz.; saffron, ¼ oz.; proof spirit, 1 pint.

B.P. Vinum Rhei. Wine of Rhubarb.—Rhubarb root, 1½ oz.; Canella alba bark, 60 gr.; sherry, 1 pint.

U.S.P. Pulvis Rhei Compositus. Compound Powder of Rhubarb.—Rhubarb, 25; magnesia, 65; ginger, 10 parts.

U.S.P. Syrupus Rhei. Syrup of Rhubarb.—Rhubarb, 90; cinnamon, 18; carbonate of potassium, 6; sugar, 600; water q.s. to make 1,000.

U.S.P. Syrupus Rhei Aromaticus. Aromatic Syrup of Rhubarb.—Aromatic tincture of rhubarb, 10; syrup, 90 parts.

U.S.P. Tinctura Rhei. Tincture of Rhubarb.—Rhubarb, 12; cardamom, 2; diluted alcohol up to 100 parts.

U.S.P. Tinctura Rhei Aromatica. Aromatic Tincture of Rhubarb.—Rhubarb, 20; cinnamon, 4; cloves, 4; nutmeg, 2; diluted alcohol up to 100.

U.S.P. Tinctura Rhei Dulcis. Sweet Tincture of Rhubarb.—Rhubarb, 8; glycyrrhiza, 4; anise, 4; cardamom, 4; diluted alcohol up to 100.

U.S.P. Vinum Rhei. Wine of Rhubarb.—Rhubarb, 10; calamus, 1; stronger white wine up to 100.

Action and Uses.—Rhubarb when chewed increases the flow of saliva. **Small doses** have a **tonic** and **astringent** action and are employed in atonic dyspepsia, especially when there is an accumulation of mucus in the intestinal tube. **Large doses** are **purgative** in their action, increasing peristalsis. This is followed by an astringent effect. It is especially useful in cases of diarrhœa associated with worms, or when there is some irritating body in the intestines: the cause of irritation is removed, and then the after-astringent action checks the diarrhœa.

U.S.P. Rumex. Rumex. Yellow Dock.—The root of *Rumex crispus* and of other species of Rumex.

Characters.—From eight to twelve inches (20 to 30 centimetres) long, about half an inch (12 millimetres) thick, somewhat fusiform, fleshy, nearly simple, annulate above, deeply wrinkled below; externally rusty-brown, internally whitish, with fine, straight, interrupted, reddish medullary rays, and a rather thick bark; fracture short; odour slight, peculiar; taste bitter and astringent.

Composition.—It contains **tannic acid** and **rumicine**, which is identical with chrysophanic acid.

Preparation.

	Dose.
Extractum Rumicis Fluidum	30–60 min.

Action.—It is **astringent** and bitter, and is supposed to possess **alterative** properties, which render it useful in scorbutic diseases.

ARISTOLOCHIACEÆ.

Serpentariæ Rhizoma, B.P.; Serpentaria, U.S.P. SERPENTARY RHIZOME, B.P.; SERPENTARIA, U.S.P.—The dried rhizome and rootlets of *Aristolochia Serpentaria* or *Aristolochia reticulata*. From the southern parts of North America.




FIG. 217.—Serpentary, half the natural size.

CHARACTERS.—A small roundish rhizome, with a tuft of numerous slender rootlets, about three inches long, yellowish, of an agreeable camphoraceous odour, and a warm bitter camphoraceous taste.

COMPOSITION. — An **essential oil**, and resin, **tannin**, and sugar.

ADULTERATION.—Other roots fraudulently or inadvertently added, distinguished by appearance and smell.

PREPARATIONS.

B.P.	DOSE.
Infusum Serpentariæ	1–2 fl. oz.
Tinctura Cinchonæ Composita	½–2 fl. dr.
Tinctura Serpentariæ	½–2 fl. dr.

U.S.P.	
Extractum Serpentariæ Fluidum	10–30 min.
Tinctura Cinchonæ Composita	1–4 fl. dr.
Tinctura Serpentariæ	1–3 fl. dr.

ACTION AND USES.—Serpentary is a stimulant **tonic**, and is used in atonic dyspepsia with nervous depression. Owing to it having some **diaphoretic** and **diuretic** properties, it is used in chronic rheumatism.

ASARUM EUROPÆUM or ASARABACCA belongs to this order; its leaves were formerly used as an errhine. They cause powerful vomiting and purging when administered internally.

PIPERACEÆ.

Piper Nigrum, B.P.; Piper, U.S.P. BLACK PEPPER.—The dried unripe fruit of *Piper nigrum*, B.P. The unripe fruit of *Piper nigrum*, U.S.P East Indies.

CHARACTERS.—Small, roundish, wrinkled; tegument brownish-black, containing a greyish-yellow globular seed; odour aromatic; taste pungent and bitterish.

DOSE.—5 to 20 grains.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Confectio Opii	5–20 gr.	Oleoresina Piperis	1–2 min.
Confectio Piperis	60–120 gr. or more.		
Pulvis Opii Compositus	2–5 gr.		

B.P. Confectio Piperis. CONFECTION OF PEPPER.—Black pepper, 2; caraway fruit, 3; clarified honey, 15.

U.S.P. Oleoresina Piperis. OLEORESIN OF PEPPER.—Exhaust pepper with stronger ether, remove the ether by distillation and evaporation, and separate the oleoresin from the piperine in the residue by expression through a muslin strainer.

COMPOSITION.—**Piperine, resin,** and **volatile oil.** Piperine is a crystalline principle, almost neutral, tasteless, inodorous, and insoluble in water, and is isomeric with morphine. The resin possesses the pungent taste of the drug, and gives the oil its aromatic smell.

U.S.P. Piperina. PIPERINE. $C_{17}H_{19}NO_3$; 285.—A proximate principle of feebly alkaloidal power, prepared from pepper, and occurring also in other plants of the Nat. Ord. *Piperaceæ*.

CHARACTERS.—Colourless, or pale yellowish, shining, four-sided prisms, permanent in the air, odourless, and almost tasteless when first put in the mouth, but on prolonged contact producing a sharp and biting sensation. When heated to about 128° C. (about 262° F.), piperine melts, yielding a clear, yellowish liquid, which, on cooling, congeals to a resinous mass. It has a neutral reaction.

SOLUBILITY.—It is almost insoluble in water, but soluble in 30 parts of alcohol at 15° C. (59° F.), in 1 part of boiling alcohol, and but slightly soluble in ether.

REACTIONS.—When heated on platinum foil, it takes fire and is consumed without residue. Concentrated sulphuric acid dissolves piperine with a dark, blood-red colour, which disappears on dilution with water. When treated with cold nitric acid, piperine turns rapidly greenish-yellow, orange, and red, and gradually dissolves with a reddish colour. On adding to this solution an excess of solution of potassa, the colour is at first pale yellow, but on boiling it deepens to blood-red, while, at the same time, vapours of an alkaline reaction and of a peculiar odour (piperidine) are given off.

DOSE.—1 to 10 grains.

ACTION AND USES.—Pepper is a stimulant **stomachic.** It is used chiefly as a condiment, but has been employed in the treatment of hæmorrhoids, and, on account of its stimulating action on mucous membranes, as a substitute for cubebs in the treatment of **gonorrhœa.** The action and uses of piperine are similar to those of pepper.

Cubeba, B. and U.S.P. CUBEBS.—The dried unripe fruit of *Piper Cubeba* (*Cubeba officinalis*). Java.




FIG. 218.—Cubebs.

CHARACTERS.—Is like black pepper, but is distinguished from it by the adherent stalk of rather more than its own length, from which it gets its

ordinary name of tailed pepper. It has a warm camphoraceous taste and characteristic odour.

COMPOSITION.—A **volatile oil**, a **resin**, and **cubebin**. Cubebin is neutral and crystalline. It does not seem to have any important physiological action. The resin yields cubebic acid, and a volatile oil consisting of a hydrocarbon holding a camphor in solution.

DOSE.—Of the powder 30 to 120 gr.

PREPARATIONS.

B.P.		DOSE.	U.S.P.	DOSE.
Oleoresina Cubebæ		5–30 min.	Cubeba	15 gr.
Oleum	„	5–20 min.	Extractum Cubebæ Fluidum	8–30 min.
Tinctura	„	½–2 fl. dr.	Oleoresina Cubebæ	5–30 min.
			Tinctura Cubebæ	8 min.–3 fl. dr.
			Trochisci Cubebæ (each contains ½-gr. oleoresin).	

Oleum Cubebæ, B. and U.S.P. OIL OF CUBEBS.—A volatile oil distilled from cubebs.

CHARACTERS.—Colourless or pale greenish-yellow, having the peculiar odour and taste of cubebs.

COMPOSITION.—A **hydrocarbon** holding a camphor in solution.

Oleoresina Cubebæ, B. and U.S.P. OLEORESIN OF CUBEBS.

PREPARATION.—By extracting cubebs with stronger ether, distilling off most of the ether; letting the rest evaporate; transferring the residue to a closed vessel till waxy and crystalline matter has ceased to deposit, and then pouring off the oleoresin.

DOSE.—5 to 30 min. (0·3 to 2 gm.) given in capsules.

ACTION AND USES.—Cubebs owes its action to the oil and resin. It is carminative and **stimulant** to mucous membranes. It is used chiefly for its action on the mucous membrane of the bladder and urethra, as in gonorrhœa (p. 446). It is used in the form of lozenges for relaxed sore-throat, and as an errhine for coryza when free secretion has become established. It is slightly **diuretic**, and has been used as an adjunct to other diuretics. Large doses may produce gastro-enteritis, and it sometimes gives rise to a rash resembling urticaria. The oil has an action somewhat like oil of turpentine or oil of copaiba. The resin is said to be a more active diuretic than the oil, and the oleoresin is therefore introduced into the U.S.P.

Maticæ Folia, MATICO LEAVES, **B.P. Matico**, MATICO, **U.S.P.**—The dried leaves of *Piper angustifolium* (*Artanthe elongata*). Peru.

CHARACTERS.—From two to eight inches long, veined and tesselated on the upper surface, downy beneath. They may be confounded with digitalis leaves, but are distinguished by their marked reticulation in squares.

COMPOSITION.—**Essential oil, artanthic acid, tannin,** and resin.

DOSE.—Of the powder, 30–60 gr.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Infusum Maticæ (½-oz. in ½-pint for ½-hour)	1–4 fl. oz.	Extractum Matico Fluidum	½–3 fl. dr.
		Tinctura Matico	½–3 fl. oz.

ACTION AND USES.—Matico is employed locally as a **styptic** to arrest hæmorrhage from small wounds, such as leech-bites. It acts mechanically, much in the same way as a spider's web. It has been administered in cases of vesical catarrh and gonorrhœa, but is now not much used.

MYRISTICEÆ.

Myristica, B. and U.S.P. NUTMEG.—The kernel of the seed of *Myristica fragrans* deprived of its hard coat or shell. Malayan Archipelago.

CHARACTERS.—Oval or nearly round, about an inch in length, marked externally with reticulated furrows, internally greyish-red with dark brownish veins. It has a strong peculiar odour, and a bitter aromatic taste. Nutmeg resembles areca nut, especially in its internal structure, but the latter is devoid of the strong odour.

COMPOSITION.—**Fixed oil** (oil of mace) and **volatile oil,** the latter imparting the aromatic smell and taste.

DOSE.—Of powdered nutmeg, 5–15 gr.

PREPARATIONS.

B.P.	DOSE.
Oleum Myristicæ	1–5 min.
„ „ **Expressum**	1–5 min.
Pulvis Catechu Compositus	20–40 gr.
Pulvis Cretæ Aromaticus	10–60 gr.
Spiritus Armoraciæ Compositus	1–2 fl. dr.
Tinctura Lavandulæ Composita	½–2 fl. dr.

U.S.P.	
Tinctura Lavandulæ Composita	½–2 fl. dr.
Pulvis Aromaticus	10–30 gr.

Oleum Myristicæ, B. and U.S.P. VOLATILE OIL OF NUTMEG. The oil distilled in Britain from nutmeg, B.P. A volatile oil distilled from nutmeg, U.S.P.

CHARACTERS.—Colourless or straw-yellow, having the odour and taste of nutmegs.

PREPARATIONS.

B.P.	DOSE.
Pilula Aloes Socotrinæ (*vide* p. 522)	5–10 gr.
Spiritus Ammoniæ Aromaticus	30 min.–1 fl. dr.
Spiritus Myristicæ (Mistura Ferri Composita)	30–60 min.

U.S.P.	
Spiritus Myristicæ	1–2 fl. dr.

B.P. Oleum Myristicæ Expressum. EXPRESSED OIL OF NUTMEG.—A concrete oil obtained by means of expression and heat from nutmegs.

CHARACTERS.—Of an orange colour, firm consistence, and fragrant odour like that of nutmeg.

PREPARATIONS.

B.P.

Emplastrum Calefaciens. Emplastrum Picis.

ACTION AND USES.—Nutmeg is aromatic, **stimulant**, and **carminative.** The expressed oil is used externally as a stimulant, and with other stimulants is contained in emplastrum picis and emplastrum calefaciens. It is very little used in medicine, but chiefly to flavour articles of food.

U.S.P. Macis. MACE.—The arillus of the fruit of *Myristica fragrans*.

CHARACTERS.—In narrow bands, one inch (25 millimetres) or more long, somewhat branched and lobed above, united to broader bands below; brownish-orange; fatty when scratched or pressed; odour fragrant; taste warm and aromatic.

USES.—It contains the **same** volatile oil **as nutmeg**, and has the same uses.

LAURINEÆ.

Cinnamomi Cortex, B.P.; Cinnamomum, U.S.P. CINNAMON BARK, B.P.; CINNAMON, U.S.P.—The inner bark of shoots from the truncated stocks of *Cinnamomum zeylanicum*. Imported from Ceylon.

CHARACTERS.—In closely rolled quills, containing several small quills within them, light yellowish-brown, with a fragrant odour and warm sweet aromatic taste; breaks with a splintery fracture.

COMPOSITION.—A **volatile oil** to the extent of 1 per cent. with mannite, sugar, mucilage, and **tannic acid.**

ADULTERATION.—*Cassia lignea.*

TEST.—Decoction of *cassia lignea* is coloured blue-black by tincture of iodine.

PREPARATIONS.

B.P.	DOSE.
Aqua Cinnamomi	1–2 fl. oz.
Decoctum Hæmatoxyli	1–2 fl. oz.
Infusum Catechu	1–2 fl. oz.
Oleum Cinnamomi	1–5 min.
Pulvis Catechu Compositus	20–40 gr.
Pulvis Cinnamomi Compositus	10–30 gr.
Pulvis Cretæ Aromaticus	10–60 gr.
Pulvis Kino Compositus	5–20 gr.
Tinctura Cardamomi Composita	½–2 fl. dr.
Tinctura Catechu	½–2 fl. dr.
Tinctura Cinnamomi	½–2 fl. dr.
Tinctura Lavandulæ Composita	½–2 fl. dr.
Vinum Opii	10–40 min.

U.S.P.	DOSE.
Pulvis Aromaticus	10–30 gr.
Tinctura Cinnamomi	½–2 fl. dr.
Oleum „	1–5 min.
Tinctura Lavandulæ Composita	½–2 fl. dr.
Vinum Opii	6 min.

Pulvis Cinnamomi Compositus, B.P.; Pulvis Aromaticus, U.S.P. COMPOUND CINNAMON POWDER, B.P.; AROMATIC POWDER, U.S.P.—Equal parts of cinnamon, cardamoms, and ginger, B.P. Cinnamon 35, ginger 35, cardamoms 15, nutmeg 15, U.S.P.

Oleum Cinnamomi, B. and U.S.P. OIL OF CINNAMON.—The oil distilled from cinnamon bark.

CHARACTERS.—Yellowish when recent, gradually becoming red, having the odour and taste of cinnamon.

COMPOSITION.—Consists principally of **cinnamic aldehyde**, or hydride of cinnamyl, with other hydrocarbons, one of which, a camphor, is deposited at low temperatures, thus causing the change in colour. The oil has a specific gravity of from 1·025 to 1·050, so that it sinks in water. It is slightly lævulose.

DOSE.—1–5 min.

PREPARATIONS.

B.P.	DOSE.
Spiritus Cinnamomi (oil 1, spirit 49)	½–1 fl. dr.
Acidum Sulphuricum Aromaticum (contains spirit of cinnamon)	5–30 min.

U.S.P.	
Aqua Cinnamomi	indefinite.
Spiritus Cinnamomi	5–15 min.
Acidum Sulphuricum Aromaticum	5–15 min.

ACTION AND USES.—Cinnamon is an aromatic **carminative**, and since it contains tannic acid slightly **astringent**. It is chiefly used in conjunction with other astringents, and from its agreeable taste is very frequently employed.

Coto Bark. Not officinal.—The bark of a tree imported from Bolivia.

COMPOSITION.—It contains an alkaloid, **cotoin**. Cotoin forms a pale yellow powder or minute crystals sparingly soluble in water, soluble in alcohol, ether, and chloroform.

DOSE.—½ to 2 gr. every two or three hours in mucilage or syrup. A solution of 1 part in 4 of acetic ether is recommended for hypodermic injection. Tincture of coto bark (1 in 10) may be used in doses of 10 min.

ACTION.—It appears greatly to **increase intestinal absorption** (p. 387).

USES.—It is useful in gastric and intestinal catarrh, in infantile diarrhœa, and in the diarrhœa of phthisis. It is said also to check salivation and the night sweats of phthisis.

Paracoto Bark. Not officinal.—Contains an alkaloid, **paracotoin**, similar in its actions and uses to cotoin, but less powerful.

Camphora, B. and U.S.P. CAMPHOR.—A stearoptene (concrete volatile oil), obtained from the wood of *Cinnamomum Camphora* (*Camphora officinarum*). Imported in the crude state from China and Japan, and purified by sublimation.

CHARACTERS.—White, translucent, tough, crystalline lumps; has a powerful penetrating odour, and a pungent taste followed by a sensation of cold; floats on water; volatilises slowly at ordinary temperatures.

SOLUBILITY.—Is slightly soluble in water, but readily soluble in rectified spirit and in ether.

COMPOSITION.—A **stearoptene** having the formula $C_{10}H_{16}O$, and yielding camphoric acid on oxidation.

IMPURITIES.—Fixed salts.

TEST.—Sublimes entirely when heated.

DOSE.—1 to 10 grains.

PREPARATIONS CONTAINING CAMPHOR.

B.P.	DOSE.
Aqua Camphoræ (saturated aqueous solution)	1–2 fl. oz.
Linimentum Aconiti (*vide* p. 516)	
,, Belladonnæ (*vide* p. 516)	
Linimentum Camphoræ (*vide* p. 516)	
,, ,, **Compositum** (*vide* p. 516)	
Linimentum Chloroformi (*vide* p. 516)	
,, Hydrargyri (*vide* p. 516)	
,, Opii (*vide* p. 516)	
Linimentum Saponis (*vide* p. 516)	
Linimentum Sinapis Compositum (*vide* p. 516)	
Linimentum Terebinthinæ (*vide* p. 516)	
,, ,, Aceticum (*vide* p. 516)	
Spiritus Camphoræ (camphor 1, rectified spirit 10)	10–30 min.
Tinctura Camphoræ Composita (*vide* Opium)	15 min.–1 fl. dr.
Unguentum Hydrargyri Compositum	

The hypodermic injections of apomorphine and ergot contain camphor water.

U.S.P.	DOSE.
Aqua Camphoræ	1 fl. dr.
Linimentum Belladonnæ (*vide* p. 517)	
,, Camphoræ (*vide* p. 517)	
,, Chloroformi (*vide* p. 517)	
,, Saponis (*vide* p. 517)	
Spiritus Camphoræ	5–10 min.
Tinctura Opii Camphorata	1–2 fl. dr.
Ceratum Camphoræ	

Aqua Camphoræ. CAMPHOR WATER, B. and U.S.P.—It is prepared according to the B.P. by tying crushed camphor, ½-oz., in a muslin bag, which is kept immersed in 1 gallon of water in a bottle for at least two days. The U.S.P. directs camphor (8) to be dissolved in alcohol (16), and then added to cotton (16). After the alcohol has nearly evaporated the cotton is packed in a percolator, and distilled water poured on till 1,000 parts are obtained.

U.S.P. Ceratum Camphoræ. CAMPHOR CERATE.—Camphor liniment, 3; olive oil, 12; cerate, 85.

PHYSIOLOGICAL ACTION.—**Externally** camphor is **stimulant** and rubefacient.

Internally in small doses it acts as a carminative, in large

doses as an **irritant**, causing nausea and vomiting. It is **diaphoretic** and **anaphrodisiac**, and **stimulates** the **heart** (pp. 316, 319). It stimulates the circulation, but may slow the pulse; and stimulates the **nerve-centres**, causing exhilaration, but finally paralyses them, causing lassitude. It produces, in large doses, a form of **delirium**, and sometimes death, occasionally preceded by **epileptiform convulsions** and maniacal excitement. In small doses it is said to be aphrodisiac, and in large doses anaphrodisiac (p. 451). It lowers the **temperature**.

USES.—**Externally**, in the form of liniment, it is applied to sprains, enlarged joints, &c. An ointment of 1 part of camphor to 8 of lard is useful in relieving itching in chronic eczema and urticaria.

Inhalation of its vapour ($\frac{1}{2}$–1 dr. in $\frac{1}{2}$-pint hot water) has been recommended for coryza.

Internally it is used in catarrh and coryza. It is very useful in summer diarrhœa, and may be given in the form of Rubini's solution (1 gr. in 2 min. of absolute alcohol), two to five minims every fifteen minutes. It is also useful in cholera, tympanitic distension of the abdomen, and hysterical vomiting.

It is also used as a nervine stimulant, especially in debility of the respiratory organs; as a nervine and cardiac stimulant in fever, and as an antispasmodic in epilepsy, chorea, pertussis, hysteria, and other nervous affections, especially those connected with the sexual organs.

U.S.P. Camphora Monobromata. MONOBROMATED CAMPHOR. $C_{10}H_{15}BrO$; 230·8.

PREPARATION.—By heating camphor with bromine and crystallising from petroleum benzin.

CHARACTERS.—Colourless, prismatic needles or scales, permanent in air, unaffected by light, having a mild camphoraceous odour and taste, and a neutral reaction.

SOLUBILITY.—Almost insoluble in water, freely soluble in alcohol, ether, chloroform, hot benzin, and fixed oils; slightly soluble in glycerine.

DOSE.—2 to 10 grains. It may be given in pills, made by rubbing 5 grains with 1 grain of Canada balsam in a warm mortar.

ACTION.—Like other bromides it produces weakness and paralysis, stupor and sleep. It slows the pulse (p. 316) and respiration and reduces the temperature. In the rabbit the vessels of the eye and ear are contracted. When given for a length of time it produces marked emaciation.

USES.—Monobromated camphor has been used as a **sedative** instead of the bromides, but it is less efficient. It has been recommended in insomnia, chorea, hysteria, and delirium tremens. In large doses it has caused epileptiform convulsions, like camphor.

B.P. Sassafras Radix. SASSAFRAS ROOT.—The dried root of *Sassafras officinalis*. From North America.

CHARACTERS.—In branched pieces; bark externally greyish-brown, internally rusty-brown, of an agreeable odour, and a peculiar aromatic warm taste; wood light, porous, greyish-yellow. The chips or shavings, which are the officinal form, resemble quassia, but are browner, and distinguished by their smell.

COMPOSITION.—Contains 1 to 2 per cent. of a **volatile oil**. The bark contains **tannic acid** to a small extent.

PREPARATION.

B.P.	DOSE.
Decoctum Sarsæ Compositum (¼-oz. to 1 pint)	2–10 fl. oz.

U.S.P. Sassafras. SASSAFRAS.—The bark of the root of *Sassafras officinalis*.

CHARACTERS.—In irregular fragments, deprived of the grey, corky layer, bright rust-brown, soft, fragile, with a short, corky fracture; strongly fragrant; sweetish, aromatic, and somewhat astringent.

U.S.P. Oleum Sassafras. OIL OF SASSAFRAS.—A volatile oil distilled from sassafras.

CHARACTERS.—A colourless or yellowish liquid becoming darker and thicker by age and exposure to air, having the characteristic odour of sassafras, a warm, aromatic taste, and a neutral reaction; sp. gr. about 1·090.

SOLUBILITY.—It is readily soluble in alcohol.

REACTIONS.—When treated with cold nitric acid it becomes dark red, and is finally converted into a red resin.

DOSE.—1–5 min.

PREPARATIONS.

U.S.P.			DOSE.
Decoctum Sarsaparillæ		Compositum	4–6 fl. oz.
Extractum	„	„ Fluidum	30–60 min.
Syrupus	„	Compositus	1–4 fl. dr.

ACTION AND USE.—Sassafras has a destructive action on infusoria (cf. p. 63). It is a stimulant **diaphoretic**, and is used in rheumatism and syphilis, generally in combination with other drugs.

U.S.P. Sassafras Medulla. SASSAFRAS PITH.—The pith of *Sassafras officinalis*.

CHARACTERS.—In slender cylindrical pieces, often curved or coiled, light, spongy, white, inodorous, insipid. Macerated in water it forms a mucilaginous liquid, which is not precipitated on the addition of alcohol.

PREPARATION.

	DOSE.
Mucilago Sassafras Medullæ (sassafras pith, 2 parts; water, 100 parts)	Ad libitum

USES.—As a **demulcent** either internally or externally.

B.P. Nectandræ Cortex. BEBEERU BARK.—The dried bark of *Nectandra Rodiæi*, the green-heart tree. Imported from British Guiana.

CHARACTERS.—In large flat heavy pieces; external colour greyish-brown, internal, dark cinnamon-brown; taste strongly and persistently bitter, with considerable astringency.

COMPOSITION.—Contains **beberine**, a peculiar alkaloid. Beberine is a colourless, amorphous substance, soluble in alcohol, but sparingly soluble in boiling water.

PREPARATION.

B.P.	DOSE.	U.S.P.
Beberinæ Sulphas	1–10 gr.	None.

B.P. Beberinæ Sulphas. SULPHATE OF BEBERINE. $C_{36}H_{42}N_2O_6.H_2SO_4$.—Prepared from Nectandra or Bebeeru bark. It is probably a mixture of sulphates of beberine, $C_{36}H_{42}N_2O_6$, nectandrine, $C_{40}H_{46}N_2O_6$, and other alkaloids.

PREPARATION.—By exhausting the bark with diluted sulphuric acid, removing most of the acid by lime, precipitating the alkaloid with ammonia, and neutralising with sulphuric acid.

PROPERTIES.—In dark-brown, thin, translucent scales, yellow when in powder, with a strong bitter taste.

SOLUBILITY.—Soluble in water and in alcohol.

REACTIONS.—Its watery solution gives a white precipitate with chloride of barium (sulphate); and with caustic soda a yellowish-white precipitate, which is dissolved by agitating the mixture with twice its volume of ether (beberine).

IMPURITIES.—Mineral matter.

TESTS.—The ethereal solution, separated by a pipette and evaporated, leaves a yellow translucent residue, entirely soluble in dilute acids. It is entirely destructible by heat. Water forms with it a clear brown solution.

ACTION AND USES.—Bebeeru bark is seldom used in medicine; both it and the sulphate of beberine are said to have a similar action to quinine (cf. p. 61), and have been used as **tonics** and **antiperiodics**, but sulphate of beberine is but a poor substitute for the cinchona alkaloids.

SANTALACEÆ.

Oleum Santali, B. and U.S.P. OIL OF SANTAL (Oil of sandal wood).—A volatile oil distilled from the wood of *Santalum album*.

CHARACTERS.—A pale yellowish or yellow liquid of a peculiar strongly aromatic odour, a pungent and spicy taste, and a slightly acid reaction.

SOLUBILITY.—It is readily soluble in alcohol.

DOSE.—10 to 30 min. in capsules or mixture.

ACTION AND USES.—Its action and uses are **similar** to those of **copaiba**, than which its smell is less disagreeable.

THYMELACEÆ.

Mezerei Cortex, B.P.; Mezereum, U.S.P. Mezereon Bark, B.P.; Mezereum, U.S.P.—The dried bark of *Daphne Mezereum*, or of *Daphne Laureola*.

Characters.—In long thin more or less flattened strips, which are commonly folded or rolled into disks; or in small quills of various lengths. Inner surface whitish, silky, very tough, and covered externally by an olive-brown, or somewhat reddish-brown, readily separable corky layer. No marked odour; taste burning and acrid.

Preparations.

B.P.	U.S.P.
Decoctum Sarsæ Compositum.	Decoctum Sarsaparillæ Compositum.
Extractum Mezerei Æthereum.	Extractum Sarsaparillæ Compositum Fluidum.
Linimentum Sinapis Compositum (p. 516). (Contains Extract.)	Extractum Mezerei.
	„ „ Fluidum.

Action.—Externally it is **irritant**. Internally it is supposed to be **diuretic** and **alterative**.

EUPHORBIACEÆ.

Cascarillæ Cortex, B.P.; Cascarilla, U.S.P. Cascarilla Bark, B.P.; Cascarilla, U.S.P.—The dried bark of *Croton Eluteria*. Bahama Islands.



Fig. 219.—Cascarilla.

Characters.—In quills, two or three inches in length and about $\frac{1}{8}$ to $\frac{1}{2}$ inch in diameter, dull brown, but more or less coated with white crustaceous lichens; breaks with a short resinous fracture; is warm and bitter to the taste; and emits a fragrant odour when burned.

Composition.—The active principle is **cascarillin**, a bitter substance, soluble in hot spirit or ether. Resin, gum, and a small quantity of volatile oil are also present.

Preparations.

B.P.	Dose.	U.S.P.	Dose.
Infusum Cascarillæ (1 oz. to ½-pint)	1–2 fl. oz.	Cascarilla	30 gr.
Tinctura „	½–2 fl. dr.		

Action and Uses.—Cascarilla is aromatic, **stimulant**, and **tonic**. It is also a stimulant to the mucous membranes, and is used as an **expectorant** in chronic bronchitis. It is useful in atonic dyspepsia and as a general tonic to the system.

U.S.P. Stillingia. Stillingia. Queen's Root.—The root of *Stillingia sylvatica*.

CHARACTERS.—About twelve inches (30 centimetres) long, and nearly two inches (5 centimetres) thick, sub-cylindrical, slightly branched, compact, wrinkled, tough, greyish-brown, breaking with a fibrous fracture, showing a thick bark and porous wood, the inner bark and medullary rays with numerous yellowish-brown resin cells; odour peculiar, unpleasant; taste bitter, acrid, pungent.

COMPOSITION.—It contains a **resinous substance.**

PREPARATION.

	DOSE.
Extractum Stillingiæ Fluidum	15–30 min.

USES.—In large doses it causes vomiting and purging. It has been used as an **alterative** in secondary syphilis and cutaneous diseases.

Oleum Crotonis, B.P.; Oleum Tiglii, U.S.P. CROTON OIL.—A fixed oil expressed (in Britain) from the seeds of *Croton Tiglium*. East Indies.



FIG. 220.—Croton Oil Seeds.

CHARACTERS.—Slightly viscid; colour brownish-yellow, taste acrid, odour faintly nauseous.

COMPOSITION.—Very complex. It contains **several fatty acids.** Its active principles have not yet been separated. An oily substance named **crotonal** is said to possess the irritant properties of croton oil.

DOSE.—Of the oil $\frac{1}{3}$–1 min. placed on the tongue, or formed into a pill with crumb of bread. As an adjunct $\frac{1}{12}$ min. upwards.

B.P. PREPARATION.

Linimentum Crotonis (*vide* p. 516) (1 volume in 8).

ACTION.—**Externally** it is an irritant and gives rise to a pustular eruption. This effect is increased by the addition of an alkali.

Internally it is a violent purgative, causing great congestion of the intestinal canal, and may cause death from gastro-enteritis with collapse.

USES.—**Externally** it is used as a counter-irritant in phthisis, bronchitis, inflammation of the brain and its membranes, and inflammation of the ovary, in the form of the liniment.

Internally it is given as a **purgative** in obstinate constipation ($\frac{1}{2}$–1 min. in pill). It is especially useful in paralysis, mania, and apoplexy, when there is a difficulty in swallowing and a purgative of small bulk is required. It can be mixed with a little bread-crumb and placed on the back of the tongue, and

PREPARATION.

U.S.P.	DOSE.
Mucilago Ulmi (slippery elm 6, boiling water 100; macerate for two hours and strain)	Ad libitum.

USES.—Elm bark is used as a **demulcent**, slight **astringent** and **tonic**, and in the treatment of skin diseases.

SUB-ORDER II.—CANNABINEÆ.

Cannabis Indica, B. and U.S.P. INDIAN HEMP.—The dried flowering tops of the female plants of *Cannabis sativa*, the common hemp. (For medicinal use that which is grown in India, and from which the resin has not been removed, is alone to be employed. It is known in India as Gunjah or Ganga.)

CHARACTERS.—Tops consisting of one or more alternate branches, bearing the remains of the flowers and smaller leaves and a few ripe fruits, pressed together in masses of a dusky green colour with almost no taste, but a characteristic odour.

PREPARATIONS.

B.P.	DOSE.
Extractum Cannabis Indicæ	¼–1 gr. or more.
Tinctura ,, ,,	5–20 min.

U.S.P.	
Extractum Cannabis Indicæ Fluidum	5–10 min.
Tinctura ,, ,,	10–20 min.
Extractum ,, ,,	⅓-gr.

U.S.P. Cannabis Americana. AMERICAN CANNABIS.—*Cannabis sativa*, grown in the Southern United States and collected while flowering.

CHARACTERS.—Stem about six feet (2 metres) long, rough; leaves opposite below, alternate above, petiolate, digitate; the leaflets linear-lanceolate, serrate; diœcious, the staminate flowers in pedunculate clusters forming compound racemes; the pistillate flowers axillary, sessile, and bracteate; odour heavy; taste bitter, slightly acrid.

COMPOSITION.—The active constituent is a resinoid substance, **cannabin**. The tops also contain a small quantity of **volatile oil**.

ACTION.—Its chief effect is on the brain, and is of a twofold nature; it excites a form of delirium and hallucinations, usually followed by deep sleep.

Small doses give rise to delirium with hallucinations, generally of a gay character, causing much merriment; accompanied by a great inclination to muscular movement.

The nature of the hallucinations depends greatly on the character of the individual, and people seem to be able to determine their nature, as in the case of opium.

Haschish is an Arabian preparation of Indian hemp, and is the origin of the word assassin. An Eastern chief used to dose his fanatic followers with Indian hemp, and they became imbued with the idea that they would be taken to heaven if killed, and hence were not afraid to encounter death.

The dreams produced by Indian hemp in inhabitants of Eastern countries are usually of a sexual character (p. 450), but when taken by the more civilised people of Western nations they are not sexual, and are often of a disagreeable nature.

During this stage of hallucination, the person may conduct himself rationally and answer clearly any question put to him (Wood). The drug produces in some persons a curious loss of sense of time and of space. This stage is generally followed by deep sleep. The **sensory nerves** are benumbed, and there is frequently tingling and partial anæsthesia. The **pupil** is dilated.

Respiration may be either quickened or slowed. The action on the **pulse** is very uncertain. Usually it is first quickened, then slowed, sometimes *vice versâ*. The **temperature** rises or sinks according as the drug produces muscular movement or sleep. The **urine** is increased. The processes of **digestion** are less altered by cannabis indica than by opium, and the after-effects of opium (nausea, headache, &c.) are not produced.

USES.—**As a soporific** it is used instead of opium when the latter does not agree, or in old opium-eaters; also in cases of mental derangement; in acute and chronic mania it is very useful, especially when combined with potassium bromide.

It has been used in neuralgia to lessen pain; also in spasmodic coughs, asthma, &c. In certain cases of menorrhagia it is useful, but its mode of action is unknown. Ringer recommends it in migraine, and S. Mackenzie in constant headache.

B.P. Lupulus. HOP. The dried strobiles of *Humulus Lupulus*. Cultivated in England.

CHARACTERS.—Strobiles of a greenish-yellow colour, with minute yellow grains (lupulin) adherent to the base of the scales. Odour aromatic, taste bitter.

U.S.P. Humulus. HOP.—The strobiles of *Humulus Lupulus*.

CHARACTERS.—Ovate, about an inch and a quarter (3 centimetres) long, consisting of a thin, hairy, undulated axis, and many obliquely ovate, membranous, greenish scales, in the upper part reticulately veined, and toward the base parallel-veined, glandular, and surrounding a subglobular achene; odour aromatic; taste bitter, aromatic, and slightly astringent.

Lupulinum, B. and U.S.P. LUPULIN.—The glandular powder, separated from the strobiles of *Humulus Lupulus*.

CHARACTERS.—Bright brownish-yellow, becoming yellowish-brown, resinous, consisting of minute granules which, as seen under the microscope, are subglobular, or rather hood-shaped, and reticulate; aromatic and bitter.

When agitated with water and allowed to stand, no considerable sediment (sand, &c.) should be deposited. When ignited, lupulin should not leave more than 15 B.P., 8 U.S.P., per cent. of ash.

COMPOSITION.—The lupulin of hops consists of a bitter principle, **lupulite, volatile oil,** to which the odour of hops is due, and **resin.** Hops apart from the grains contain a kind of **tannin.**

DOSE.—2 to 5 grains or more.

PREPARATIONS.

B.P.	DOSE.
Extractum Lupuli	5–10 gr.
Infusum „	1–2 fl. oz.
Tinctura „	½–2 fl. dr.

U.S.P.

Of HUMULUS—

Tinctura Humuli	1–3 fl. dr.

Of LUPULINUM—

Extractum Lupulini Fluidum	10–30 min.
Oleoresina „	2–20 gr.

ACTION AND USE.—Hops act as a bitter **tonic** and **stomachic**, also slightly as a **soporific**. In the form of bitter beer they are used in some cases of atonic dyspepsia; and a supper of beer and lettuce, with bread and butter, is markedly soporific, from the combined effect of the hops and lettuce.

A hop-pillow is sometimes used in sleeplessness of fevers, but its use is probably due, not to the action of the volatile principle of the hops, but to the mechanical elasticity and softness of the pillow. The crackling of the leaves in this pillow may be stopped by sprinkling a little alcohol on them.

SUB-ORDER III.—MOREÆ.

B.P. Mori Succus. MULBERRY JUICE.—The juice of the ripe fruit of *Morus nigra*.

CHARACTERS.—Of a dark violet colour, with a faint odour, and an acidulous sweet taste.

COMPOSITION.—Colouring matter, **sugar**, and **acid**, supposed to be malic.

PREPARATION.

B.P.	DOSE.
Syrupus Mori	1 fl. dr. or more.

USE.—To flavour and colour mixtures.

SUB-ORDER IV.—ARTOCARPEÆ.

Ficus, B.P. FIG.—The dried fruit of *Ficus Carica*, Smyrna.

Ficus, U.S.P. FIG.—The fleshy receptacle of *Ficus Carica*, bearing fruit upon its inner surface.

CHARACTERS.—Compressed, of irregular shape, fleshy, covered with an efflorescence of sugar; of a sweet, fruity odour, and a very sweet, mucilaginous taste. When softened in water, figs are pear-shaped, with a scar or short stalk at the base, and a small scaly orifice at the apex; hollow internally; the inner surface covered with numerous, yellowish, hard achenes.

COMPOSITION.—**Grape sugar** (about 70 per cent.), a little gum, and fatty matter.

PREPARATIONS.

B.P.	DOSE.	U.S.P.	DOSE.
Confectio Sennæ	60–120 gr.	Confectio Sennæ	60–120 gr.

USE.—Figs are used locally as poultices, by splitting them and applying them to the inflamed part, as in gum-boils, dental abscesses, inflamed tonsils, &c.

Figs are chiefly employed as a domestic **laxative**. They are useful, given in large quantities, when a person has swallowed a hard sharp substance, by forming a bulky mass which will sheath the substance and protect the intestines from injury. In such cases purgatives are to be avoided.

JUGLANDACEÆ.

U.S.P. Juglans. JUGLANS. BUTTERNUT.—The inner bark of the root of *Juglans cinerea*, collected in autumn.

CHARACTERS.—In flat or curved pieces, from an eighth to a quarter of an inch (3 to 6 millimetres) thick; the outer surface nearly free from soft cork; deep brown; the inner surface smooth and striate; transverse fracture short, delicately checkered, whitish and brown; odour feeble; taste bitter and somewhat acrid.

PREPARATION.	DOSE.
Extractum Juglandis	20–30 gr.

USES.—It is a mild **cathartic**, especially useful in the treatment of chronic constipation, dysentery and congestion of the abdominal viscera. It has a slight action as a **hepatic stimulant** (p. 403), and is useful in malarial conditions (pp. 375 and 407).

HAMAMELACEÆ.

U.S.P. Hamamelis. HAMAMELIS. WITCH-HAZEL.—The leaves of *Hamamelis virginica*, collected in autumn.

CHARACTERS.—Short-petiolate, about four inches (10 centimetres) long, obovate or oval, slightly heart-shaped and oblique at the base, sinuate-toothed, nearly smooth; inodorous; taste astringent and bitter.

COMPOSITION.—It contains **tannic acid** and a **bitter principle**.

OFFICINAL PREPARATION.

	DOSE.
Extractum Hamamelidis Fluidum	15 min.–2 fl. dr.

USES.—It is used as an external application to piles, bruises, and inflammatory swellings. Hazeline, or the fluid extract of hamamelis, arrests the bleeding from piles in some cases almost like magic. Just before a motion a pledget of cotton about the size of a hazel nut, and soaked in the liquid, should be inserted into the rectum, and after the motion, when the anus has been cleansed by washing, a similar pledget should be again introduced and allowed to remain. Internally it is a very efficient **hæmostatic** in bleeding from the lungs and other internal organs. In some cases of hæmoptysis I have found it in the form of the non-officinal preparation of it called hazeline more efficient than digitalis and ergot, although in other cases digitalis

and ergot have succeeded better. It checks the flow in menorrhagia when given during the period, and it lessens pain in dysmenorrhœa. In one case a patient informed me that it invariably caused seminal emissions, which ceased when it was discontinued. In this action it resembles strychnine (p. 450). It has been supposed by Dujardin-Beaumetz to owe its utility to an action on the muscular fibre of veins.

BALSAMIFLORÆ.

Styrax Præparatus, B.P.; Styrax, U.S.P. PREPARED STORAX, B.P.; STORAX, U.S.P.—A balsam obtained from the inner bark of *Liquidambar orientalis*. Purified by solution in spirit, filtration and evaporation.

CHARACTERS.—A semi-transparent, brownish-yellow semi-fluid resin, of the consistence of thick honey, with a strong agreeable fragrance and aromatic bland taste. Heated in a test-tube on the vapour-bath, it becomes more liquid but gives off no moisture; boiled with solution of bichromate of potassium and sulphuric acid, it evolves the odour of oil of bitter almonds.

COMPOSITION.—**Styrol, cinnamic acid, styracin**, and resin. Cinnamic acid yields, when oxidised, hydride of benzoyl (oil of bitter almonds).

DOSE.—Of the prepared resin, 5–20 gr.

PREPARATIONS.

B.P.	DOSE.
Tinctura Benzoini Composita	½–1 fl. dr.
U.S.P.	
Tinctura Benzoini Composita	½–1 fl. dr.

USE.—Its action and use are **similar** to those of the **balsam of Peru** (p. 902). A styrax ointment very useful in scabies is of the strength of one ounce of liquid styrax to two ounces of lard.

CUPULIFERÆ.

B.P. Quercûs Cortex. OAK BARK.—The dried bark of the smaller branches and young stems of *Quercus robur*. Collected in spring, from trees growing in Britain.

CHARACTERS.—Covered with a greyish shining epidermis, cinnamon-coloured on the inner surface, fibrous, brittle, and strongly astringent.

U.S.P. Quercus Alba.—The bark of *Quercus alba*.

CHARACTERS.—In nearly flat pieces, deprived of the corky layer, about a quarter of an inch thick, pale brown, inner surface with short sharp longitudinal ridges, tough, of a coarse, fibrous fracture, a faint, tan-like odour, and a strongly astringent taste.

COMPOSITION.—**Querci-tannic acid** and **quercin**, a bitter crystalline substance.

PREPARATION.

B.P.	U.S.P.
Decoctum Quercûs (1¼ oz. to 1 pint).	None.

Action and Use.—Chiefly used externally as a local **astringent**, e.g. as a gargle in relaxed sore-throat or as an injection in gonorrhœa and leucorrhœa.

Galla, B. and U.S.P. Galls, B.P.; Nutgalls, U.S.P.—Excrescences on *Quercus lusitanica*, var. *infectoria*, caused by the punctures and deposit of an egg or eggs of *Cynips Gallæ tinctoriæ*. Asia Minor.

Characters.—Hard, heavy, globular bodies, tuberculated on the surface, the tubercles and intervening spaces smooth; of a bluish-green colour on the surface, yellowish-white within, with a small central cavity; intensely astringent.

Composition.—**Gallo-tannic acid** (14 to nearly 70 per cent. according to the quality of the galls), **gallic acid** (3 per cent.), free sugar and resin in minute quantities.

Preparations.

B.P.	dose.
Acidum Gallicum	2–20 gr.
„ **Tannicum**	2–30 gr.
Tinctura Gallæ	½–2 fl. dr.
Unguentum Gallæ (80 gr. to 1 oz.)	
„ „ **cum Opio** (80 gr. to 1 oz. nearly)	
U.S.P.	
Tinctura Gallæ	½–3 fl. dr.
Unguentum Gallæ (1 part in 10)	

Action and Uses.—Galls are used in the form of galls and opium ointment as a local **astringent** in the treatment of hæmorrhoids. The action of galls depends on the contained tannic and gallic acids (*q.v.*).

Acidum Tannicum, B. and U.S.P. Tannic Acid. [Tannin.] $C_{27}H_{22}O_{17}$.—A glucoside extracted from galls.

Preparation.—By dissolving out the tannic acid from powdered galls with ether mixed with a very little water, gently evaporating the solution, and drying the acid. Although tannic acid is very sparingly soluble in pure ether, yet it appears to dissolve readily in ether containing a very little water.

Properties.—In pale yellow vesicular masses, or thin glistening scales, with a strongly astringent taste, and an acid reaction. On exposure to air or by the action of dilute acids, it splits up into glucose and gallic acid (*q.v.*). Tannin in its natural state appears to be a mixture of digallic acid ($C_{14}H_{10}O_9$) with a glucoside of digallic acid. Schiff proposes to give the name tannic acid to the digallic acid, and that of tannin to the glucoside.

Solubility.—It is readily soluble in water and rectified spirit; very sparingly soluble in ether.

Reactions.—The aqueous solution precipitates solution of gelatine yellowish-white, and the persalts of iron of a bluish-black colour.

Impurities.—Mineral matter.

Tests.—It leaves no residue when burned with free access of air on platinum foil.

Dose.—2 to 10 grains.

Preparations.

B.P.	
Glycerinum Acidi Tannici	1 part in 6 by weight.
Suppositoria „ „	3 grains in each.
„ „ „ **cum Sapone**	3 grains in each.
Trochisci „ „	½-grain in each.

PREPARATIONS—(*continued*).

U.S.P.

Collodium Stypticum (tannic acid 20, alcohol 5, stronger ether 20, collodion 55 parts).....1 part in 5.
Trochisci Acidi Tannici .....1 grain in each.
Unguentum ,, ,, (with benzoated lard).....1 part in 10.

ACTION.—When applied externally to the unbroken skin tannic acid has little or no action; but applied to **skin deprived of its epidermis**, it coagulates the albumin and causes contraction of the cells of the skin. It **coagulates blood** and consequently acts as a local styptic.

It acts locally on **mucous membranes**, coagulating the mucus. On account of the dryness in the mouth produced by the drug, it was concluded that the vessels are contracted, and that the astringent action is due to this; but Rossbach found, from direct observation, that the vessels are dilated; in this particular tannin differs from other astringents, such as nitrate of silver. This dilatation is not due to paralysis of the coats of the arteries, since they contract on stimulation or subsequent application of silver nitrate.

Its astringent action on the skin and mucous membranes is probably due to coagulation of albumin and a 'tanning' of all the tissues to which it is applied.

When taken into the **mouth** it causes dryness, coagulation of mucus, and a partial paralysis of the ends of the sensory nerves (both the nerves of ordinary sensation and the special nerves of taste), so that it destroys to a great extent the sense of taste, and also lessens irritation in the throat.

When taken into the **stomach** in large doses it is irritant and causes vomiting. When given to animals it does not lessen either secretion or peristaltic action of the intestines, and yet in man, even from small doses, there is a dryness of the fæces and lessened peristalsis; probably these different results are due to some imperfection in the experiments or to a difference of dose.

Large doses cause diarrhœa, with subsequent constipation.

It is absorbed into the **blood**, and passes out as gallic acid or some product of the oxidation of gallic acid.

It restrains hæmorrhage in distant organs, as the uterus, lungs, or **kidneys**, but the *modus operandi* is not known, and some authorities deny this action altogether.

USES.—**Externally** applied to the skin **tannic acid** is used in intertrigo, impetigo, and eczema, especially when occurring behind the ears in children: in desquamating chronic eczema, a ten per cent. tannic acid ointment is useful, also in sycosis, applied after shaving. In hyperidrosis of the axillæ, genitals, palms, and hands, and in sweating of the feet, frequent washing with a solution of tannin in diluted alcohol (1 in 250) is recommended.

It is also applied to mucous membranes, such as the external auditory meatus in otorrhœa (fill the meatus with glycerine of tannic acid and keep it there by a pledget of cotton wool). Also to the nasal mucous membrane, when there is ulceration and offensive discharge. In this case it is applied either in aqueous solution by means of the nasal douche or as glycerine of tannic acid with a brush. It is thus of use in ozæna after measles or scarlet fever, and in that form occurring in syphilitic children. In hæmorrhages from the nose dry tannin may be snuffed up.

It is used in stomatitis and ulceration of gums; and as a gargle in relaxed sore-throat or applied locally as glycerine of tannic acid. It is very useful in the hacking cough often met with in children, and also in adults, which is due to an irritation at the back of the pharynx, often accompanied by inflamed throat, covered with mucus; in inflamed tonsils and deafness; also in whooping-cough and other throat affections, either in the form of the glycerine or as lozenges.

It has been used, dissolved in water, or mixed with olive oil, as an injection in leucorrhœa, gonorrhœa, and chronic discharges from the os uteri.

Internally tannin is used in hæmatemesis and intestinal hæmorrhage; also as an **antidote** to poisoning by alkaloids, but when used for this purpose it must be followed by a purgative, as the tannates are all more or less soluble in the juices of the alimentary canal. It is also used in poisoning by tartar emetic, as tannic acid forms with antimony an insoluble tannate. It is used in diarrhœa, but usually the more sparingly soluble forms of tannin, such as kino, are preferred. Tannic acid lessens the amount of albumin in albuminuria.

Acidum Gallicum, B. and U.S.P. GALLIC ACID. $C_6H_2(OH)_3(CO.OH)$. H_2O; 188.—A crystalline acid prepared from galls; it may be considered as salicylic acid in which two atoms of hydrogen are replaced by two of hydroxyl (cf. p. 810).

PREPARATION.—From galls, by pulverising, moistening with water, and allowing them to ferment for six weeks in a temperature of 60° to 70° F. The tannin present in the galls is split up by the fermentation into gallic acid and glucose, the tannic acid, or digallic acid (p. 1,031) splitting up into gallic acid, $C_{14}H_{10}O_9 + H_2O = 2C_7H_6O_5$. It is purified by solution, and re-solution in boiling water, filtering and crystallising.

PROPERTIES.—Crystalline, in acicular prisms or silky needles, nearly white or of a pale fawn-colour. Its taste is acidulous and astringent.

SOLUBILITY.—It requires about 100 parts of cold water for its solution, but dissolves in 3 parts of boiling water. Soluble also in rectified spirit.

REACTIONS.—It gives a bluish-black precipitate with a persalt of iron. It leaves no residue when burned with free access of air. Its aqueous solution gives no precipitate with solution of isinglass, and is thus distinguished from tannic acid.

IMPURITY.—Tannic acid from imperfect fermentation.

TESTS.—No precipitate with solution of isinglass (no tannic acid).

DOSE.—2 to 10 grains.

PREPARATIONS.

B.P.	DOSE.
Glycerinum Acidi Gallici (1 in 6)	12–60 min.

U.S.P.

Unguentum Acidi Gallici (with benzoated lard, 1 part in 10).

USES.—**Gallic acid** resembles tannic acid in its action, but does not coagulate albumin, and is used chiefly in cases of hæmorrhages from the lungs, or kidneys, or where the affected part can only be reached through the circulation.

In hæmoptysis it is useful in ten-grain doses every two hours. Like tannin it is said to lessen the amount of albumin in the urine in albuminuria.

U.S.P. Castanea. CASTANEA. [CHESTNUT.]—The leaves of *Castanea vesca*, collected in September or October, while still green.

CHARACTERS.—From six to ten inches (15 to 25 centimetres) long, about two inches (5 centimetres) wide, petiolate, oblong-lanceolate, acuminate, mucronate, feather-veined, sinuate-serrate, smooth; having a slight odour, and a somewhat astringent taste.

PREPARATION.

	DOSE.
Extractum Castaneæ Fluidum	½–1 fl. dr.

USES.—It has been used in whooping-cough. Its taste is not disagreeable, but it has no extraordinary physiological power.

SALICINEÆ.

U.S.P. Salix. SALIX. WILLOW.—The bark of *Salix alba* and of other species of *Salix*.

CHARACTERS.—In fragments or quills, from one-twenty-fifth to one-twelfth of an inch (1 to 2 millimetres) thick, smooth; outer surface somewhat glossy, brownish or yellowish, more or less finely warty; under the corky layer green; inner surface brownish-white, smooth, the liber separating in thin layers; inodorous; bitter and astringent.

COMPOSITION.—It contains **tannin** and **salicin**.

USE.—The infusion may be used as a bitter tonic.

Salicinum, B. and U.S.P. SALICIN. $C_{13}H_{18}O_7$; 286.—A crystalline glucoside obtained by treating the bark of *Salix alba* and other species of *Salix*, and the bark of various species of *Populus*, with hot water, removing tannin and colouring matter from the decoction, evaporating, purifying, and recrystallising.

CHARACTERS.—Colourless shining crystals with a very bitter taste.

SOLUBILITY.—Soluble in about twenty-eight parts of water or a similar quantity of spirit at common temperatures; insoluble in ether. It is much less readily dissolved by putting it into cold water than by dissolving it in hot water and allowing the solution to cool.

Reactions.—Sulphuric acid colours it red. A small quantity heated with a little red chromate of potassium, a few drops of sulphuric acid and some water, yields vapours of salicylic aldehyde, $C_6H_4.OH\ (CHO)$, having the odour of meadow-sweet. The crystals melt when heated, and emit vapours having the odour of meadow-sweet. On ignition in air it leaves no residue.

The aqueous solution of salicin should not be precipitated by tannic or picric acids, nor by iodide of mercury and potassium (absence of and difference from alkaloids).

Dose.—3 to 20 grains.

Action.—Its action is similar to that of salicylic acid (p. 820). Salicin is one of the sources of salicylic acid, which may be prepared from it by heating with caustic potash and treating the mass with hydrochloric acid. The salicylic acid prepared from salicin, or from oil of wintergreen, is generally purer than that made artificially (p. 820), and may frequently be tolerated by patients when the artificial salicylic acid disagrees. Salicin appears to be decomposed in the body, and is eliminated in the urine partly as salicin and partly as salicylic acid, as salicyluric acid, and as saligenin. Its action is less powerful than that of salicylic acid, and its depressing effect on the circulation less marked.

Uses.—It is used as an **antipyretic**, and has been given with success instead of salicylic acid in the treatment of acute rheumatism. It is useful also in headaches.

CHAPTER XXXVI.

SUB-KINGDOM I.—PHANEROGAMÆ.

Class IV.—MONOCOTYLEDONES.

ORCHIDACEÆ.

U.S.P. Vanilla. VANILLA.—The fruit of *Vanilla planifolia*.

CHARACTERS.—From six to ten inches (15 to 25 centimetres) long, linear, narrowed and bent or hooked at the base, rather oblique at the apex, wrinkled, somewhat warty, dark brown, glossy-leathery, one-celled, and containing a blackish-brown pulp, with numerous minute seeds, and more or less acicular crystals; odour and taste peculiar, fragrant.

PREPARATION.

	DOSE.
Tinctura Vanillæ	A few drops as a flavouring.

USES.—It is used chiefly as a **flavouring** and a perfume. It is also an **aromatic stimulant** in hysteria and low fevers.

U.S.P. Cypripedium. CYPRIPEDIUM. LADIES' SLIPPER.—The rhizome and rootlets of *Cypripedium pubescens*, and of *Cypripedium parviflorum*.

CHARACTERS.—Horizontal, bent, four inches (10 centimetres), or less, long; about one-eighth of an inch (3 millimetres) thick; on the upper side beset with numerous circular cup-shaped scars; closely covered below with simple, wiry rootlets varying from four to twenty inches (10 to 50 centimetres) in length; brittle, dark brown or orange-brown; fracture short, white; odour faint but heavy; taste sweetish, bitter and somewhat pungent.

PREPARATION.

	DOSE.
Extractum Cypripedii Fluidum	15 min.

USE.—It has an **antispasmodic** action similar to that of valerian, but it is less powerful.

SCITAMNACEÆ.

(ZINGIBERACEÆ.)

Zingiber, B. and U.S.P. GINGER.—The (scraped and dried, B.P.) rhizome of *Zingiber officinale*. West Indies, India, and other countries.

CHARACTERS.—Irregular lobed decorticated pieces, three or four inches long, yellowish-white but not chalky on the surface, with a short mealy fracture, hot taste, and agreeable aroma. Powder yellowish-white.

PREPARATIONS.

B.P.	DOSE.
Confectio Opii	5–20 gr.
„ Scammonii	10–30 gr.
Infusum Sennæ	1–2 fl. oz.
Pilula Scillæ Composita (*vide* p. 523)	5–10 gr.
Pulvis Cinnamomi Compositus	30–60 gr.
„ Jalapæ „	20–60 gr.
„ Opii „	2–5 gr.
„ Rhei „	20–60 gr.
„ Scammonii „	10–20 gr.
Syrupus Zingiberis	½–1 fl. dr.
Tinctura „	15 min.–1 fl. dr.
„ „ **Fortior**	5–20 min.
Vinum Aloes	1–2 fl. dr.

U.S.P.

Extractum Zingiberis Fluidum	10–30 min.
Oleoresina „	1–2 min.
Pulvis Aromaticus	10–30 gr.
„ Rhei Compositus	30–60 gr.
Syrupus Zingiberis	1 fl. dr.
Tinctura „	15–75 min.
Vinum Aloes	1–2 fl. dr.

COMPOSITION.—A yellow **volatile oil** and a **resin**, the former having the odour, and the latter the taste, of the drug.

ACTION.—Ginger causes a feeling of warmth in the mouth, and reflexly stimulates the secretion of saliva. It has a stimulant action on the stomach, producing warmth at the epigastrium. It promotes the expulsion of flatus.

USES.—It is used in atonic dyspepsia, also to relieve flatulence, and as an adjunct to purgatives to lessen griping. It is also used as a masticatory to increase secretion of saliva, and in relaxed conditions of the throat. Also used as a **carminative** in colic.


B.P. Turmeric.—The rhizome of *Curcuma longa*.

Turmeric Tincture, B.P.; Solution of Turmeric, U.S.P. A solution prepared by macerating 1 part bruised turmeric in 6 parts rectified spirit, B.P., or diluted alcohol, U.S.P., in a closed vessel for 7 days, and filtering.

Turmeric Paper, B. and U.S.P.—Unsized white paper coloured by steeping in tincture of turmeric and drying by exposure to the air without heat.

ACTION AND USES.—Turmeric acts similarly to ginger. Chiefly used as a **condiment**. Turmeric paper is used as a **test for alkalis**, which turn it brown.

Cardamomi Semina, B.P.; Cardamomum, U.S.P. CARDAMOMS.—The fruit U.S.P. (dried capsules, B.P.), of *Elettaria Cardamomum*. Malabar. The seeds are best kept in their pericarps, from which they should be separated when required for use, the pericarpal coats being rejected.



a *b*

FIG. 222.—Cardamoms. *a*. Cross section. *b*. Side view.

CHARACTERS.—Seeds obtusely angular, corrugated, reddish-brown, internally white, with a warm, aromatic, agreeable taste, contained in ovate-oblong, triangular, pale-brown, coriaceous pericarps.

PREPARATIONS.

B.P.	DOSE.
Tinctura Cardamomi Composita	½–2 fl. dr.
Tinctura Chloroformi Composita	20–60 min.

CONTAINED ALSO IN

Extractum Colocynthidis Compositum.	Tinctura Gentianæ Composita..
Pulvis Cinnamomi Compositus.	Tinctura Rhei.
Pulvis Cretæ Aromaticus.	Vinum Aloes.

U.S.P.	DOSE.
Pulvis Aromaticus	10–30 gr.
Tinctura Cardamomi	1–2 fl. dr.
„ „ Composita	1–2 fl. dr.

CONTAINED ALSO IN

Tinctura Rhei.	Vinum Aloes.
Tinctura Gentianæ Composita.	Extractum Colocynthidis Compositum.

Tinctura Cardamomi Composita. COMPOUND TINCTURE OF CARDAMOMS. B. and U.S.P.—Cardamom seeds and caraway fruit bruised each ¼ oz., raisins freed from seeds 2 oz., cinnamon bark ½ oz., cochineal 55 gr., proof spirit 1 pint. B.P. Cardamom and cinnamon, each 20 parts, caraway 10, cochineal 5, glycerin 60, diluted alcohol to 1,000 parts. U.S.P.

COMPOSITION.—**Fixed oil** and aromatic **volatile oil**, containing a camphor in solution.

ACTION AND USES.—Cardamoms act similarly to ginger. They are **stimulant**, aromatic, and **carminative**, and are less pungent than ginger. Used chiefly as a carminative in flatulence, and as an adjunct to other medicines to lessen griping.

IRIDEÆ.

Crocus, B. and U.S.P. SAFFRON.—The dried stigmas and top of the style of *Crocus sativus*, B.P. The stigmas of *Crocus sativus*, U.S.P. Spain, France, and Italy.

CHARACTERS.—Thread-like styles, each terminated by three long orange-brown stigmas, broadest at the summit. Has a powerful aromatic odour.

DOSE.—Of dried saffron, 20 gr. and upwards.

PREPARATIONS.

B.P.	DOSE.
Decoctum Aloes Compositum	½–2 fl. oz.
Pilula Aloes et Myrrhæ (*vide* p. 522)	5–10 gr.
Pulvis Cretæ Aromaticus	10–60 gr.
Tinctura Cinchonæ Composita	½–2 fl. dr.
Tinctura Croci	½–2 fl. dr.
Tinctura Opii Ammoniata	½–1 fl. dr.
„ Rhei	1–2 fl. dr. (stomachic).
„ „	4–8 fl. dr. (purgative).

U.S.P.	
Tinctura Croci	½–2 fl. dr.

COMPOSITION.—The colouring matter of saffron is a glucoside—**crocin**—soluble in water and easily decomposed by dilute acids. A **volatile oil** is obtainable both directly from the drug and by the decomposition of crocin. It possesses the odour of saffron.

IMPURITIES.—Saffron is often adulterated with parts of other plants dyed, and with coloured chalk.

TESTS.—By throwing saffron on the surface of warm water, the peculiar form of the stigma is at once seen, and admixture of other plants discovered. The chalk is detected by its immediately rendering the water turbid.

ACTION AND USES.—Saffron has but little action. It is used chiefly as a **colouring agent**, and as a slight **carminative**.

U.S.P. Iris. IRIS. BLUE FLAG.—The rhizome and rootlets of *Iris versicolor*.

CHARACTERS.—Rhizome horizontal, consisting of joints, two to four inches (5 to 10 centimetres) long, cylindrical in the lower half, flattish near the upper extremity, and terminated by a circular scar, annulated from the leaf-sheaths, grey-brown; rootlets long, simple, crowded near the broad end; odour slight; taste acrid, nauseous.

PREPARATIONS.

	DOSE.
Extractum Iridis	2–4 gr.
„ „ Fluidum	5–10 min.

COMPOSITION.—It owes its medicinal virtues to an **oleoresin**.

ACTION.—It is **emetic** and **cathartic**, and has been proved by Professor Rutherford to act as a **stimulant to the liver** and the intestinal glands (p. 403).

USES.—In constipation and biliousness.

LILIACEÆ.

U.S.P. Allium. GARLIC.—The bulb of *Allium sativum*.

CHARACTERS.—Bulb subglobular, compound, consisting of about eight compressed, wedge-shaped bulblets, which are arranged in a circle around the base of the stem, and covered by several dry, membranaceous scales. It has a pungent, disagreeable odour, and a warm, acrid taste. It should be preserved in a dry place, and used only in the fresh state.

COMPOSITION.—The bulblets, or cloves as they are commonly termed, owe their strong taste and smell to a **volatile oil** which is sulphide of allyl $(C_3H_5)_2S$.

OFFICINAL PREPARATION.

	DOSE.
Syrupus Allii	1–4 fl. dr.

ACTION.—Allyl alcohol is a powerful **antiseptic** (pp. 95 and 102), and it is probable that oil of garlic will have a similar action. Like oil of mustard, to which it is allied in chemical composition (p. 864), oil of garlic is a powerful **irritant**, or even vesicant, when applied to the skin. In the intestine it acts in small doses as a gastric tonic and **carminative**; in large doses as an emetic and irritant, causing vomiting, purging, headache, and fever. After absorption, it quickens the pulse and acts as a nervine **stimulant**. It is partly eliminated by the lungs, imparting its peculiar odour to the breath, and acting as an **expectorant**. It is diaphoretic or **diuretic** according as the patient is kept warm or cool. It is said to be an emmenagogue.

USES.—A mixture of garlic juice and oil, or bruised garlic steeped in spirit, is used as a counter-irritant in convulsions or nervous diseases in children, and also in skin-eruptions. The syrup may be used as a gastric tonic in atonic dyspepsia, and to check nervous vomiting. It is chiefly employed in nervous coughs of children, and as an expectorant in bronchitis after the acute stage has passed. It is used as an anthelmintic in cases of ascarides, and is given by the mouth and also as an enema.

Convallaria Majalis. LILY OF THE VALLEY. Not officinal.—The flowers and stem are used, though the whole plant contains the active principle.

COMPOSITION.—The flowers and stem contain two glucosides, **convallarin**, soluble in alcohol but insoluble in water, and **convallamarin**, soluble in both alcohol and water.

PREPARATIONS.

	DOSE.
Extractum Convallariæ	2–8 gr.
„ „ Liquidum	2–10 min.
Tinctura „	5–30 min.
Convallamarin	½–2 gr.

ACTION.—**Convallamarin** acts like digitalis (p. 996), though not so well, on the **heart**, and in producing diuresis in cardiac disease. **Convallarin** has only a purgative effect.

USES.—An infusion of the whole plant is a common remedy in Russia for cardiac dropsy. Convallamarin has been used in mitral disease with dropsy, but it has not superseded digitalis, though it is said to have no harmful effects.

Scilla, B. and U.S.P. SQUILL.—The sliced (and dried

B.P.) bulb of *Urginea Scilla* (*U. maritima*). Mediterranean coasts.

CHARACTERS.—Bulb pear-shaped, weighing from half a pound to ten pounds; outer scales membranous, brownish red or white; inner scales thick, whitish, fleshy, juicy; taste mucilaginous, intensely and disagreeably bitter, somewhat acrid. The dried slices are white or yellowish-white, slightly translucent, scentless, disagreeably bitter, brittle and easily pulverisable if very dry.



FIG. 223.—Cut piece of Squill, half the natural size.

COMPOSITION.—The active principle is a glucoside, **scillitoxin**, or scillaïn. The scillitin of some authors is probably slightly impure scillitoxin.

DOSE.—Of powdered squills, 1–3 gr.

PREPARATIONS.

B.P.	DOSE.
Acetum Scillæ	15–40 min.
Oxymel „	½–1 fl. dr.
Pilula Ipecacuanhæ cum Scillâ (*vide* p. 522)	5–10 gr.
„ **Scillæ Composita** (*vide* p. 523)	5–10 gr.
Syrupus Scillæ	½–1 fl. dr.
Tinctura „	10–20 min.

U.S.P.	
Acetum Scillæ	15 min.–1 fl. dr.
Extractum Scillæ Fluidum	1–2 min.
Syrupus „ Compositus	10–30 min.
Tinctura „	8–30 min.
Syrupus „	½–1 fl. dr.

U.S.P. Syrupus Scillæ Compositus. Squill, 120; senega, 120; tartrate of antimony and potassium, 3; sugar, 1,200; precipitated phosphate of calcium, 9; diluted alcohol and water, of each, q.s. to make 2,000.

ACTION AND USES.—Squill and its active principle, scillitoxin, act like digitalis.

Internally, in **large doses**, it causes vomiting and purging. When absorbed into the blood, it slows the **pulse** and raises the blood-pressure. Like digitalis it acts as a **diuretic**, and also acts like it on voluntary muscle fibre. It is chiefly used as an adjunct to digitalis to produce diuresis in cases of cardiac dropsy; also as an **expectorant**, when, although the secretion is profuse, it is difficult to expel. It is of no use when the expectoration is dry and deficient; in such cases ipecacuanha should first be given and followed by squill.

Pilula ipecacuanhæ cum scillâ, 10 grains night and morning, is a most useful remedy in chronic bronchitis.

Aloe Socotrina, B.P.; Aloe, U.S.P. SOCOTRINE ALOES, B.P.; ALOES, U.S.P.—The inspissated juice of the leaf of *Aloe*

Perryi and probably other species. Imported principally by way of Bombay and Zanzibar.

CHARACTERS.—In hard, opaque, reddish-brown or yellowish-brown, not greenish, masses, translucent at the edges; breaks with an irregular or smooth and resinous fracture; has a bitter taste, and when breathed on has a saffron-like odour; dissolves entirely in proof spirit, and during solution exhibits under the microscope numerous minute crystals.

PREPARATIONS.

B.P.		DOSE.
Aloin		⅛–2 gr.
Decoctum Aloes Compositum (Extract)	4 gr. in 1 fl. oz.	½–2 fl. oz.
Enema Aloes	4 gr. in 1 fl. oz.	10 fl. oz.
Extractum Aloes Socotrinæ	1 part from 2, nearly	2–6 gr.
Extractum Colocynthidis Compositum (Extract)	1 part in 2, nearly	3–10 gr.
Pilula Aloes et Asafœtidæ (*vide* p. 522)	1 part in 4	5–10 gr.
„ „ **Myrrhæ** (*vide* p. 522)	1 part in 3	5–10 gr.
„ „ **Socotrinæ** (*vide* p. 522)	1 part in 2, nearly	5–10 gr.
Pilula Rhei Composita (*vide* p. 523)	1 part in 6	5–10 gr.
Tinctura Aloes	11 gr. to 1 fl. oz.	1–3 fl. dr.
Tinctura Benzoini Composita	8 gr. to 1 fl. oz.	½–2 fl. dr.
Vinum Aloes	16½ gr. to 1 fl. oz.	1–2 fl. dr.

U.S.P.		
Aloes Purificata		½–6 gr.
Extractum Aloes Aquosum		½–6 gr.

B.P. Decoctum Aloes Compositum. COMPOUND DECOCTION OF ALOES.—Extract of Socotrine aloes, 120 gr.; myrrh, 90 gr.; saffron, 90 gr.; carbonate of potassium, 60 gr.; extract of liquorice, 1 oz.; compound tincture of cardamoms 8 fl. oz.; distilled water up to 30 fl. oz.

B.P. Enema Aloes. Aloes (Socotrine or Barbadoes), 40 gr.; carbonate of potassium, 15 gr.; mucilage of starch, 10 fl. oz.

B.P. Extractum Aloes Socotrinæ. Treating with boiling water, separating insoluble matter by subsidence and filtration, and evaporating the clear solution.

B.P. Tinctura Aloes. TINCTURE OF ALOES.—Socotrine aloes, ½ oz.; extract of liquorice, 1½ oz.; proof spirit, to 20 fl. oz.

B.P. Vinum Aloes. WINE OF ALOES.—Socotrine aloes, 1½ oz.; cardamom seeds and ginger, of each, 80 gr.; sherry, up to 2 pints.

U.S.P. Extractum Aloes Aquosum. AQUEOUS EXTRACT OF ALOES.—Aloes, 100; boiling distilled water, 1,000. Separate the insoluble matter by subsidence and filtration, and evaporate.

COMPOSITION.—All kinds of aloes contain a bitter substance **aloïn**, to which their activity is due. It has in each kind of aloes a slightly different composition, and has received a name showing its source—socaloïn from Socotrine aloes, barbaloïn from Barbadoes aloes, and nataloïn from Natal aloes. According to some authors these substances are isomeric; according to others they form a homologous series. Besides aloïn, aloes contains resinous substances and traces of an ethereal oil.

Barbaloïn and nataloïn are distinguished from socaloïn by giving with a drop of nitric acid, on a porcelain slab, a bright crimson colour. With barbaloïn this gradually fades, but it is permanent with nataloïn. Socaloïn does not give this reaction. Barbaloïn is distinguished from nataloïn by the latter giving

fine blue colour, while the former remains unchanged, on adding a minute quantity of each to one or two drops of strong sulphuric acid and then bringing a glass rod dipped in nitric acid so near that the vapour shall pass over the surface.

B.P. Aloin. ALOIN. $C_{16}H_{18}O_7$.—A crystalline substance extracted from aloes by solvents and purified by recrystallisation. As obtained from the different varieties of aloes, the products differ slightly, but their medicinal properties are similar.

CHARACTERS.—Usually in tufts of acicular crystals, yellow, inodorous, and having the taste of aloes.

SOLUBILITY AND REACTIONS.—Sparingly soluble in cold water, more so in cold rectified spirit, freely soluble in the hot fluids. Insoluble in ether. Not readily altered in acidified or neutral solutions; rapidly altered in alkaline fluids.

U.S.P. Aloe Purificata. PURIFIED ALOES.

PREPARATION.—By melting aloes 100, adding alcohol 15, straining and evaporating.

CHARACTERS.—Purified aloes is in irregular brittle pieces of a dull-brown or reddish-brown colour, and having the peculiar aromatic odour of Socotrine aloes.

SOLUBILITY.—It is almost entirely soluble in alcohol.

PREPARATIONS.

U.S.P.	DOSE.
Pilulæ Aloes (*vide* p. 523)	1 pill.
Pilulæ Aloes et Asafœtidæ (*vide* p. 523)	2–5 pills.
Pilulæ Aloes et Ferri (*vide* p. 523)	1 pill.
Pilulæ Aloes et Mastiches (*vide* p. 523)	1 pill.
Pilulæ Aloes et Myrrhæ (*vide* p. 523)	1 pill.
Tinctura Aloes	1–4 fl. dr.
Tinctura Aloes et Myrrhæ	1–2 fl. dr.
Vinum Aloes	as stomachic, 1–2 fl. dr.; as purgative, ½–1 fl. oz.

It is contained also in Pilulæ Rhei Compositæ (p. 523), Extractum Colocynthidis Compositum, Pilulæ Catharticæ Compositæ (p. 523), and Tinctura Benzoini Composita.

U.S.P. Tinctura Aloes. TINCTURE OF ALOES.—Aloes, 10; extract of glycyrrhiza, 10; diluted alcohol up to 100.

U.S.P. Tinctura Aloes et Myrrhæ. TINCTURE OF ALOES AND MYRRH.—Aloes 10; myrrh, 10; alcohol, to 100.

U.S.P. Vinum Aloes. WINE OF ALOES.—Aloes, 6; cardamom, 1; ginger, 1; stronger white wine, up to 100.

B.P. Aloe Barbadensis. BARBADOES ALOES.—The inspissated juice of the leaf of *Aloe vulgaris*. Barbadoes and Dutch West Indian Islands.

CHARACTERS.—In yellowish-brown or dark-brown opaque masses; breaks with a dull conchoidal fracture; has a bitter, nauseous taste, and a strong, disagreeable odour.

COMPOSITION.—Contains **barbaloïn**, resin, and volatile oil.

DOSE.—In powder, 2–6 grains.

PREPARATIONS.

B.P.		DOSE.
Aloin		½–2 gr.
Enema Aloes (*vide supra*)	4 gr. in 1 fl. oz.	
Extractum Aloes Barbadensis	8 parts from 10, nearly	2–6 gr.
Pilula „ „	(*vide* p. 522) 1 part in 2, nearly	5–10 gr.
„ „ **et Ferri**	(*vide* p. 522) 1 part in 5¼	5–10 gr.
Pilula Cambogiæ Composita	(*vide* p. 522) 1 part in 6, nearly	5–10 gr.
„ Colocynthidis Composita	(*vide* p. 522) 1 part in 3, nearly	5–10 gr.
„ „ et Hyoscyami	(*vide* p. 522) 1 part in 4½, nearly	5–10 gr.

B.P. Extractum Aloes Barbadensis.—Prepared like extract of Socotrine aloes.

ACTION AND USES.—It causes a bitter taste in the **mouth**, and reflex salivation. In small doses it seems to have a tonic action like simple bitters. It increases peristalsis of the **intestines** and also intestinal secretion. Its action is particularly exerted on the large intestines, and especially in the **rectum**. This is shown by the great length of time which usually elapses between its administration and its action (ten or twelve, sometimes as much as twenty-four, hours), and by the rectal irritation which it produces, and which is evidenced by tenesmus, hæmorrhoidal swelling, and hæmorrhage. It increases the secretion of **bile** by stimulating the liver (Röhrig and Rutherford). It only acts when mixed with bile, and is consequently useless in jaundice, where the bile does not enter the intestine, as is shown by the whiteness of the stools. It may, however, be rendered active by giving it along with ox-gall. Aloes has little or no purgative action when given alone as an enema, but is active if mixed with ox-bile. In the enema aloes, B.P., it is mixed with carbonate of potassium. Aloes appears to cause hyperæmia of the **uterus** and other pelvic organs, as well as of the rectum. In acute and chronic poisoning by aloïn, the **kidneys** are affected, the tubules losing their epithelium, while the glomeruli remain intact, but become surrounded by an increase of fibrous tissue. In both forms of poisoning there is **albuminuria**.[1] Aloes sometimes has an **aphrodisiac** action, but this is not constant, and probably is due to irritation caused by hæmorrhoids (p. 448). Aloes differs from other purgatives in not causing subsequent constipation, but on the contrary rendering the intestine more sensitive, so that the dose can be gradually reduced. As it **does not cause subsequent constipation**, it is a favourite purgative, and is contained in most vegetable purgative pills (except pil. scammon. co.). As it **acts slowly**, it should be given a good while before a motion is desired, and a favourite plan is to give it as a **dinner pill** just before the last meal of the day, when it usually acts next morning after breakfast. I have known people who have taken dinner pills regularly every day for thirty years without

[1] A. Mürset, 'Untersuch. über Intoxicationsnephritis,' *Archiv f. exp. Path. und Pharmak.*, Bd. xix., p. 310.

injury and with apparent benefit. As it tends to cause congestion of the rectum, some authorities prohibit its use in piles, but in small doses, and if the piles are not inflamed, it is often beneficial in these cases, although large doses are injurious. From its action in causing congestion of the uterus, it is used in amenorrhœa (at the time when the catamenia are expected), but must be avoided in pregnancy and rectal inflammation. In these cases it is usually combined with iron or myrrh.

Veratri Viridis Rhizoma, B.P.; Veratrum Viride, U.S.P.
GREEN HELLEBORE RHIZOME, B.P.; AMERICAN HELLEBORE, U.S.P.
The rhizome and rootlets of *Veratrum viride*. United States and Canada.

CHARACTERS.—Rhizome two or three inches long, one to two inches thick, with numerous shrivelled, light yellowish-brown rootlets.



FIG. 224.—*Veratrum viride* root, half the natural size.

COMPOSITION.—It contains several alkaloids—**jervine, pseudojervine, cevadine,** very little **rubijervine,** and traces of **veratrine** and **veratralbine.** Veratroidine, which was formerly regarded as one of its constituents, is probably rubijervine and resin.

DOSE.—Of the powdered rhizome, 1–3 gr. or more.

PREPARATIONS.

B.P.	DOSE.
Tinctura Veratri Viridis	5–20 min. or more.

U.S.P.	
Extractum Veratri Viridis Fluidum	1–4 min.
Tinctura „ „	5–10 min.

ACTION.—In small doses veratrum viride lessens the strength of the **pulse** in man without at first affecting its rate, but afterwards it renders it very slow, soft, and compressible, although sometimes moderately full. At this stage any exertion at once renders the slow pulse rapid, feeble, small, and even imperceptible. The depression of the circulation is accompanied by muscular weakness, and frequently, though not always by nausea and vomiting. When the dose is large these symptoms

become increased, and a state of **collapse** comes on with an exceedingly rapid, almost imperceptible pulse, cold clammy skin, constant nausea and retching, intense muscular weakness, giddiness, loss of vision, and partial unconsciousness.

The action of veratrum viride is due to the jervine and other alkaloids which it contains. It has been mentioned already that veratroidine is not a pure alkaloid, but as no further investigations have been made on the alkaloids of veratrum since those of Professor H. C. Wood, I give his results.

Jervine lessens the functions of the **spinal cord**, both in frogs and mammals, and of the **medulla** (especially the vaso-motor centre), and of the **cardiac ganglia**, and at the same time irritates the motor centres in the **brain**, producing convulsions. Thus the symptoms produced are muscular weakness, loss of reflex action, followed by tremors, lowered blood-pressure, and slow pulse.

Respiration ceases before the heart, and **death** ensues from asphyxia. There is invariably salivation, but no vomiting nor purging. It has no action on the vagus, and the slow pulse is due to an action on the cardiac muscle or its ganglia. Voluntary **muscles** and **motor nerves** are little, if at all, affected by it.

Veratroidine differs from jervine in always causing **vomiting** and purging, and in producing less violent convulsions. It stimulates the **vagus centre** and paralyses the **vagus ends**. It depresses the **spinal cord** and paralyses the **respiratory centre**, but increases the excitability of the **vaso-motor centre**. At first it slows the pulse and lowers the **blood-pressure**. Next the pulsations become very powerful, though still slow, and the blood-pressure rises to normal. Then the **pulse** becomes very rapid, and the pressure rises greatly. This rise is, however, not due to the direct action of the drug, but to stimulation of the vaso-motor centre by asphyxial blood from paralysis of the respiration. If artificial respiration be kept up veratroidine steadily lessens both pulse-rate and blood-pressure.

USES.—Veratrum viride has been used as a cardiac depressant in inflammations, but has not come into general use.

B.P. Sabadilla. CEVADILLA.—The dried ripe seeds of *Schœnocaulon officinale* (*Asagræa officinalis*). Mexico.

CHARACTERS.—Fruit about half an inch long, consisting of three light-brown papyraceous follicles, each containing from one to three seeds, which are about a quarter of an inch long, blackish-brown, shining, slightly winged, possessing an intensely acrid bitter taste. The seeds only are officinal.

B.P. PREPARATION.

Veratrina.

COMPOSITION.—Three alkaloids, the first—**veratrine**—being the active principle. The remaining alkaloids—**sabadillina** and

sabatrina—occur in very small quantities, and are of little importance in pharmacy.

Veratrina, B. and U.S.P. VERATRINE.—An alkaloid or mixture of alkaloids obtained from cevadilla; not quite pure, B.P. An alkaloid or mixture of alkaloids prepared from the seeds of *Asagræa officinalis*, U.S.P.

PREPARATION.—A concentrated tincture of the seeds is poured into cold water in order to precipitate the albumin. From the filtered solution veratrine is precipitated by ammonia, and purified by re-solution in dilute hydrochloric acid, decolorisation by animal charcoal, and reprecipitation by ammonia.

CHARACTERS.—Pale grey, amorphous, without smell, but, even in the most minute quantity, powerfully irritating the nostrils; strongly and persistently bitter, and highly acrid. An active poison.

SOLUBILITY.—Insoluble in water; soluble in spirit, in ether, and in diluted acids, leaving traces of an insoluble brown resinoid matter.

IMPURITIES.—Mineral matter, and sometimes traces of the other alkaloids of cevadilla.

TEST.—Heated with access of air it melts into a yellow liquid, and at length burns away, leaving no residue.

DOSE.—$\frac{1}{12}$–$\frac{1}{8}$ gr.

PREPARATIONS.

B.P.

Unguentum Veratrinæ (8 gr. to 1 oz.) for external use.

U.S.P.

Oleatum Veratrinæ (1 part in 50).
Unguentum „ (1 part in 25).

ACTION.—**Large doses** of veratrine cause violent sneezing, and great gastro-intestinal irritation, vomiting, purging, and symptoms of collapse, the pulse being rapid, small, and irregular; and often involuntary muscular tremors come on. A peculiar creeping and prickling sensation in the skin generally accompanies these symptoms.

Externally, applied to the unbroken skin, it has no marked action, but if rubbed in with some fat it passes through the epidermis and acts on the true skin, and causes first irritation and then paralysis of the ends of the sensory nerves, producing a prickling and creeping sensation, succeeded by numbness. It is somewhat like aconitine in this respect. This effect is produced whether applied locally or taken internally.

Its irritating action on the sensory nerves is also observed if it be inhaled into the nose, when it causes violent sneezing, which also occurs after absorption from the stomach.

Internally.—It has no marked action on the **brain**. It has probably no action on the **spinal cord**. By some experimenters it is stated that convulsions are produced in frogs, but, from numerous experiments which I performed, I doubt the accuracy of this statement.

Muscles.—The contractile power is increased, but the elas-

ticity very much diminished. The period of contraction is very much prolonged, but neither the latent period nor the ascent of the curve is affected in character; the height of the curve is slightly increased, and the descent of the curve very much prolonged, so that it does not reach the abscissa for several revolutions of the cylinder. This contraction is not a state of partial rigor, since during its continuance the development of heat is increased to a marked degree; neither is it a true tetanus, since the rheoscopic frog only gives a single contraction when its nerve is laid on the poisoned muscle. It is a **prolonged contraction.** To this alteration in the muscles is due the peculiar behaviour of frogs when poisoned by veratrine. The frog jumps readily on stimulation, but after its spring it lies on the table with legs extended for a long time; then it draws the limbs up slowly, for both the flexors and extensors are contracted, and the contraction has to pass off from the extensors before the flexors can act. When it has drawn its limbs up, it remains still for a time, to allow the contraction to pass off from the flexors, after which it springs again. Thus the frog performs the normal movements with very long intervals between them. These movements have probably been mistaken for convulsions. Temperature affects the veratrine curve in a remarkable manner. As the muscle is cooled down, the curve becomes more and more like the normal, and if the temperature be much raised (keeping below the heat of *rigor caloris*), the effect also disappears; thus extremes of heat and cold remove the veratrine effect on the muscle-curve. The effect of veratrine on the muscle is also removed by potash (p. 130).

Muscles previously exhausted by over-exertion have their powers restored by veratrine.

Motor nerves have their excitability increased at first; afterwards their peripheral ends are paralysed. **Sensory nerves** have their peripheral ends first stimulated (causing pricking, &c.), and then paralysed (cf. Aconite, p. 832).

Circulation.—The effect of veratrine on the **heart-muscle** of the frog is very similar to that on voluntary muscle; hence the contractions of the heart become slower, and each systole lasts a long time, till finally the heart stops in complete systole. The effect of veratrine on the heart is also removed by heat and by potash (Ringer). In mammals, small doses injected into the circulation quicken the **pulse** and raise the blood-pressure; moderate and large doses slow the heart and lower the **blood-pressure.** Small doses quicken the **respiration**; large ones slow it, producing long pauses like those which occur after section of the vagi, and finally paralyse it. These effects are probably due to stimulation at first, and afterwards to paralysis of the ends of the vagus in the lung, and to paralysis of the respiratory centre. The **temperature** is lowered.

USES.—**Locally,** it is used like aconitine for neuralgia, in the form of the ointment rubbed over the affected part.

Internally, it is sometimes used in rheumatic arthritis, and in sthenic febrile affections, as pneumonia; but its action is uncertain, and its use dangerous; hence it is seldom employed. Possibly one cause of the uncertainty of its action is the high temperature accompanying febrile affections, by which its action is altered. A similar reason may hold good for aconite, which varies considerably in its action on febrile disorders (cf. Digitalis, p. 998).

Colchici Cormus, B.P.; Colchici Radix, U.S.P. COLCHICUM CORM, B.P.; COLCHICUM ROOT, U.S.P.—The (fresh, B.P.) corm of *Colchicum autumnale*, collected about the end of June, and the same stripped of its coats, sliced transversely, and dried at a temperature not exceeding 150° F., B.P.




FIG. 225.—Slice of Colchicum.

CHARACTERS.—Fresh corm about the size of a chestnut; furnished with an outer brown and an inner yellow coat; internally white, solid and fleshy. Dried slices about a line thick, moderately indented on one, rarely on both sides, firm, flat, whitish, amylaceous.

COMPOSITION.—**Colchicine,** and traces of **veratrine**; also starch, tannin, and fatty oil. They lose their odour by drying

PREPARATIONS.

B.P.			DOSE.
Extractum Colchici			½–2 gr.
„	„	**Aceticum**	½–2 gr.
Vinum	„	88 gr. to 1 fl. oz	10–30 min.

U.S.P.

COLCHICI RADIX.

Extractum Colchici Radicis				½–2 gr.
„	„	„	Fluidum	2–5 min.
Vinum	„	„		8 min.

Colchici Semina, B.P.; Colchici Semen, U.S.P. COLCHICUM SEEDS, B.P.; COLCHICUM SEED, U.S.P.—The seeds of *Colchicum autumnale*, collected when fully ripe, usually about the end of July or beginning of August, and carefully dried, B.P. The seed of *Colchicum autumnale*, U.S.P.

CHARACTERS.—About the size of white mustard seed, very hard, of a reddish-brown colour, and pitted.



FIG. 226.—Colchicum Seeds.

COMPOSITION.—**Colchicine,** generally regarded as an alkaloid, soluble in water and alcohol. Traces of **veratrine**—in combination with gallic acid—and a fixed oil are found.

PREPARATIONS.

B.P.		DOSE.
Tinctura Colchici Seminum	54½ gr. to 1 fl. oz.	10–30 min.

U.S.P.		
Extractum Colchici Seminis Fluidum		2–10 min.
Tinctura	,, ,,	15–30 min.
Vinum	,, ,,	15–30 min.

GENERAL ACTION.—The action of colchicum does not vary in proportion to the dose, since, when a certain (fairly large) dose is given, an increased dose does not seem to produce a more marked effect. It acts as a poison both to cold- and warm-blooded animals, but its effect is least marked on cold-blooded animals, and more marked on Carnivora than Herbivora. It has the same effect on the alimentary canal whether swallowed or subcutaneously injected.

When given in continued non-poisonous doses it causes an acrid taste, with reflex flow of saliva, and symptoms of **gastro-intestinal** disturbance, viz. **irritation** of the fauces, loaded tongue, loss of appetite, flatulence, uneasiness, or pain in the stomach and intestines, and diarrhœa. The **pulse** is slowed, and there is a tendency to muscular weakness.

A single large dose, or moderate **doses long continued** may produce symptoms of acute gastro-intestinal inflammation, viz. violent **vomiting** (vomited matter being first bilious and then bloody) and **purging** (the stools being first serous, then mucous, then bloody). Marked symptoms of **collapse** supervene, the pulse becomes small, rapid, and thready, the skin cold and bedewed with sweat, respiration slow and painful. Death ensues from collapse, the brain remaining clear to the last.

Sometimes **nervous symptoms** occur, such as flying pains over the body, numbness, and occasionally, though rarely, convulsions.

SPECIAL ACTION.—When applied to the **skin** it is an irritant, causing redness, prickling, and smarting, and if taken into the nose causes sneezing and running at the eyes.

Internally.—Its action on the brain, if any, is not well marked.

In frogs the **spinal cord** is paralysed, the paralysis being preceded by excitement, sometimes giving rise to convulsions.

In the higher animals there is no excitement, the cord being paralysed from the first. The **sensory nerves** are more or less paralysed. The **motor nerves** and **muscles** are unaffected. The **circulation** is affected, but the action is to a great extent reflex, since, if injected directly into the circulation, both the heart and the blood-pressure are only slightly altered. Very large doses are required to paralyse the inhibitory fibres of the vagus, but ultimately they are paralysed.

The Secretion of Urine.—Some authorities affirm that the total solids (both inorganic and organic) are increased, and also the quantity of water. Some say that only the urea is increased, others that the uric acid is increased, while others, again, contradict both these statements.

The probable explanation of these conflicting statements is that the observers have conducted experiments with different diets.

Treatment in Poisoning.—Evacuate the stomach by an emetic, if vomiting is not induced by the drug itself; give tannic acid in large quantities (which acts as a chemical antidote); white of egg diluted with water may be given freely; or, if the pulse is very depressed, give stimulants and keep the patient warm.

USES.—Its chief use is in gout, in the form of vinum or tincture, either in large doses during the fit, or in small ones continued for a length of time. It seems to act best when the bowels are previously freely acted on, hence a very old and useful mixture is colchicum, magnesia, and sulphate of magnesium.

In rheumatic arthritis 10 min. of tincture with 10 gr. of potassium iodide often prove useful.

In subacute rheumatism it is of very much less service.

In acute rheumatism it is hardly ever used, salicylate of sodium being more frequently employed.

LILIACEÆ.

(SMILACEÆ.)

Sarsæ Radix, B.P.; Sarsaparilla, U.S.P. (JAMAICA, B.P.) SARSAPARILLA.—The (dried B.P.) root of *Smilax officinalis* (*Smilax medica*, and other undetermined species of *Smilax*, U.S.P.). It is commonly known as Jamaica Sarsaparilla, from having been formerly obtained from central America, by way of that island.

CHARACTERS.—Roots not thicker than a goose-quill, generally many feet in length, reddish-brown, covered with rootlets, and folded in bundles about eighteen inches long, scentless.

COMPOSITION.—The active principle is a crystalline body, parillin or **smilacin**.

PREPARATIONS.

B.P.	DOSE.
Decoctum Sarsæ ($2\frac{1}{2}$ oz., water 1 pint)	2–10 fl. oz.
„ „ **Compositum**	2–10 fl. oz.
Extractum „ **Liquidum**	$\frac{1}{2}$–4 fl. dr.

U.S.P.			
Decoctum Sarsaparillæ Compositum			4–6 fl. oz.
Extractum	„	„ Fluidum	30–60 min.
„	„	Fluidum	30–60 min.
Syrupus	„	Compositus	1–4 fl. dr.

Decoctum Sarsæ Compositum, B.P.; Decoctum Sarsaparillæ Compositum, U.S.P. COMPOUND DECOCTION OF SARSAPARILLA.—Sarsaparilla, cut and bruised, 10 parts, or $2\frac{1}{2}$ oz.; sassafras, guaiacum wood and liquorice root, of each 2 parts, or $\frac{1}{4}$ oz.; mezereon, 1 part, or 1 dr.; boiling water up to 100 parts, or up to 1 pint after straining.

U.S.P. EXTRACTUM SARSAPARILLÆ COMPOSITUM FLUIDUM.—Sarsaparilla, 75; glycyrrhiza, 12; sassafras bark, 10; mezereum, 3; glycerin, 10; alcohol and water, of each, q.s. to make 100 parts.

U.S.P. SYRUPUS SARSAPARILLÆ COMPOSITUS.—Sarsaparilla, 150; guaiacum wood, 20; pale rose, 12; glycyrrhiza, 12; senna, 12; sassafras, 6; anise, 6; gualtheria, 6; sugar, 600; diluted alcohol and water, of each, q.s. to make 1,000 parts.

ACTION AND USES.—The action of sarsaparilla is very much disputed. Some believe it to be **diuretic, tonic,** and **alterative.** Others deny its beneficial action. It has been used a good deal in syphilis, scrofula, chronic rheumatism, gout, and skin diseases, but probably the good effects are due to the drugs with which it is used.

Syrupus sarsaparillæ compositus, U.S.P., is a convenient vehicle for iodide of potassium.

PALMACEÆ.

Areca. ARECA NUT. Not officinal. — The seed of *Areca Catechu*, the betel-nut tree.

COMPOSITION.—Oil, containing an acid in solution, and red **tannic matter** resembling rhatany-red.

DOSE.—As an astringent, 15 to 30 gr. As an anthelmintic, $\frac{1}{2}$ to $\frac{3}{4}$ oz.

USE.—It is much used in veterinary practice, and occasionally in ordinary practice, as an **anthelmintic** for tapeworm. It is also astringent, and is used as a masticatory (p. 193).

AROIDEÆ.

U.S.P. Calamus. CALAMUS. SWEET FLAG.—The rhizome of *Acorus Calamus*.

CHARACTERS. — In sections of various lengths, unpeeled, about three-quarters of an inch (2 centimetres) broad, subcylindrical, longitudinally wrinkled; on the lower surface marked with the circular scars of the rootlets in wavy lines; externally reddish-brown, somewhat annulate from remnants of leaf-sheaths; internally whitish, of a spongy texture, breaking with a short,

corky fracture, showing numerous oil-cells and scattered wood-bundles, the latter crowded within the subcircular nucleus-sheath. It has an aromatic odour, and a strongly pungent taste.

PREPARATION.

U.S.P.	DOSE.
Extractum Calami Fluidum	15–60 min.

COMPOSITION.—It contains a **volatile oil** and a **bitter principle.**

USES.—It is used as a feeble aromatic, **stomachic,** and **stimulant.**

GRAMINEÆ.

B.P. Farina Tritici. WHEATEN FLOUR.—The grain of wheat, *Triticum sativum*, ground and sifted.

PREPARATION.

Cataplasma Fermenti.

COMPOSITION.—**Starch** and **gluten.**

USE.—Chiefly as an article of **food.**

B.P. Mica Panis. CRUMB OF BREAD.—The soft part of bread made with wheat-flour.

PREPARATION.

Cataplasma Carbonis (p. 541).

USE.—It is used as a cataplasm, both alone and in cataplasma carbonis. It is also used as a basis for pills, and especially for making up croton oil into pill. Occasionally pills made of it alone are given as a placebo.

Amylum, B. and U.S.P. STARCH.—The starch procured from the grains of common wheat, *Triticum sativum* (*T. vulgare*); maize, *Zea Mays*; and rice, *Oryza sativa.*

CHARACTERS.—In white columnar or irregular angular masses, white, inodorous, and tasteless; easily powdered.

SOLUBILITY.—Insoluble in alcohol, ether, or cold water.

REACTIONS.—When rubbed in a Wedgwood mortar with a little cold distilled water it is neither acid nor alkaline to test-paper, and the filtered liquid does not become blue on the addition of solution of iodine. Mixed with boiling water and cooled, it gives a deep blue colour with iodine.

PREPARATIONS.

B.P.	DOSE.
Glycerinum Amyli	1 part in 10 by weight
Mucilago „	12 gr. to 1 fl. oz.
Pulvis Tragacanthæ Compositus	1 part in 6 — 20–60 gr.
Suppositoria Acidi Tannici cum Sapone.	
„ Morphinæ cum Sapone.	

U.S.P.

Amylum Iodatum (starch, 95 parts; iodine, 5 parts).
Glyceritum Amyli (starch, 10 parts; glycerine, 90 parts).

Uses.—The glycerine of starch forms a soothing application for chilblains and chapped hands. Amylum iodatum is really a preparation of iodine (*q.v.*). Starch is also used as a vehicle for enemata. Bandages saturated with it are used in surgery.

U.S.P. Triticum. Triticum. Couch-Grass.—The rhizome of *Triticum repens*, gathered in the spring and deprived of the rootlets.

Characters.—Very long, but, as met with in the shops, cut into sections about two-fifths of an inch (1 centimetre) long, and about one-twelfth of an inch (2 millimetres) thick; creeping, smooth, hollow in the centre, straw-yellow, inodorous, and of a sweet taste.

Preparation.

	Dose.
Extractum Tritici Fluidum	1 fl. dr. to 1 oz.

Uses.—It is used as a **demulcent** and diluent, more particularly in cystitis and irritation of the urinary passages.

It probably owes its diuretic effect to its sugar, and is best given in the form of an infusion or decoction, which may be freely used.

B.P. Hordeum Decorticatum. Pearl Barley.—The husked seeds of *Hordeum distichon*. Britain.

Characters.—White, rounded, retaining a trace of the longitudinal furrow.

Composition.—**Starch, albuminous matter, cellulose,** and a small quantity of **fixed oil.**

Preparation.

Decoctum Hordei. Barley Water.—Pearl barley, 2 oz.; boiling water, 30 fl. oz. The barley is first washed well in cold water, which is thrown away, and then the barley is boiled for twenty minutes and strained.

Use.—The decoction is used as a demulcent drink.

U.S.P. Maltum. Malt.—The seed of *Hordeum distichon*, caused to enter the incipient stage of germination by artificial means and dried.

Characters.—Malt should be fresh, of a colour not darker than pale amber, and should have an agreeable odour and a sweet taste.

Preparation.

	Dose.
Extractum Malti	4 fl. dr.

U.S.P. Extractum Malti. Extract of Malt.

Preparation.—Upon malt in coarse powder, not finer than No. 12, 100 parts, contained in a suitable vessel, pour 100 parts of water, and macerate for six hours. Then add 400 parts of water, heated to about 30° C. (86° F.), and digest for an hour at a temperature not exceeding 55° C. (131° F.). Strain the mixture with strong expression. Finally, by means of a water-bath or vacuum apparatus, at a temperature not exceeding 55° C. (131° F.) evaporate the strained liquid rapidly to the consistence of thick honey. Keep the product in well-closed vessels, in a cool place.

DOSE.—4 fl. dr.

ACTION.—This officinal extract of malt is similar to various other extracts and foods prepared from malt. It is not only **nutritious**, but, on account of the diastase contained in it, acts as a **digestive ferment.**

In large doses it relaxes the bowels.

USES.—In cases of imperfect digestion and in phthisis, and in general imperfect nutrition in children or adults.

Saccharum Purificatum, B.P.; Saccharum, U.S.P. REFINED SUGAR, B.P.; SUGAR, U.S.P. $C_{12}H_{22}O_{11}$, or $C_{24}H_{22}O_{11}$; 342. The refined sugar of *Saccharum officinarum.* West Indies and other tropical countries.

CHARACTERS.—Compact crystalline conical loaves, known in commerce as lump sugar.

IMPURITIES.—Salts, foreign matters.

TESTS.—U.S.P. White, dry, hard, distinctly crystalline granules, permanent in the air, odourless, having a purely sweet taste, and a neutral reaction. Soluble in 0·5 part of water, and in 175 parts of alcohol at 15° C. (59° F.); in 0·2 part of boiling water, and in 28 parts of boiling alcohol; also in 80 parts of boiling, absolute alcohol, but insoluble in ether. The aqueous solution, saturated at 15° C. (59° F.), has the specific gravity 1·345, and is miscible with alcohol in all proportions.

Neither an aqueous nor an alcoholic solution of sugar, kept in large, well-closed, and completely filled bottles, should deposit a sediment on prolonged standing (absence of insoluble salts, foreign matters, ultramarine, Prussian blue, &c.). If a portion of about 1 gm. of sugar be dissolved in 10 c.c. of boiling water, then mixed with 4 or 5 drops of test-solution of nitrate of silver and about 2 c.c. of water of ammonia, and quickly heated until the liquid begins to boil, not more than a slight coloration, but no black precipitate, should appear in the liquid after standing at rest for five minutes (absence of grape-sugar and of more than a slight amount of invert sugar).

USE.—To mask the taste of disagreeable remedies. It is used as a **vehicle,** corrigent, **preservative,** and antiseptic. Syrups have the advantage of protecting the active ingredients against fermentation, and certain ferruginous preparations against oxidation.

PREPARATIONS.

B.P.

Confectio Rosæ Caninæ.
„ „ Gallicæ.
„ Sennæ.
Ferri Carbonas Saccharata.
Liquor Calcis Saccharatus.
Mistura Ferri Composita.
„ Guaiaci.
Mistura Spiritus Vini Gallici.
Pilula Ferri Iodidi (p. 522).
Pulvis Cretæ Aromaticus.
„ Amygdalæ Compositus.
„ Tragacanthæ „
Sodii Citro-tartras Effervescens.
All the Syrups and Lozenges.

U.S.P.

Pilulæ Ferri Carbonatis (p. 523).
„ „ Iodidi.
Ferri Carbonas Saccharatus.
Mistura Ferri Composita.
Pulvis Cretæ Compositus.
„ Glycyrrhizæ Compositus.
Troches, Syrups, Compound Syrups, &c.

B.P. Theriaca. TREACLE.—The uncrystallised residue of the refining of sugar.

CHARACTERS.—A thick brown fermentable syrup, very sweet; not crystallising by rest or evaporation. Specific gravity about 1·40.

TEST.—Nearly free from empyreumatic odour or flavour.

PREPARATIONS.

B.P.

Pilula Aloes et Myrrhæ (p. 522).
" Asafœtidæ Composita.
" Conii Composita.
" Ipecacuanhæ et Scillæ.
Pilula Rhei Composita.
" Scillæ Composita.
Tinctura Chloroformi et Morphinæ.

USE.—To make up some of the pills of the Pharmacopœia. With sulphur it is used as a domestic **laxative**.

Avenæ Farina. OATMEAL. Not officinal.—The meal prepared from the seeds of *Avena sativa*, the common oat.

COMPOSITION.—The seeds contain **starch, gluten,** and **gum.** The pericarp contains an amorphous **alkaloid**. This alkaloid is soluble in alcohol. It is more abundant in dark than in light oats. It probably gives to them their bitterish taste.

ACTION.—The alkaloid appears to act chiefly as a stimulant of the **motor ganglia**. It increases the excitability of the **muscles**, and in horses causes excitement.

USES.—Oatmeal is chiefly used for making gruel or porridge, which, in addition to being nutritious, acts as a **demulcent** in coughs, and as a slight **laxative**. Warm oatmeal porridge at bed-time may have a **soporific** action (p. 198), though the exciting action of the alkaloid may render panada, indian corn, or lentils preferable. An infusion, decoction, or tincture has been recommended as a **stimulant** to replace opium in persons addicted to opium-eating, in order to help them to break off that habit.

CHAPTER XXXVII.

Sub-Kingdom I.—PHANEROGAMÆ.

Division II.—GYMNOSPERMÆ.

CONIFERÆ.

Terebinthina Canadensis, B. and U.S.P. Canada Balsam, B.P.; Canada Turpentine (Balsam of Fir), U.S.P.—The turpentine obtained by incision from the stem of *Pinus balsamea* (*Abies balsamea*), B.P. A liquid oleoresin, obtained from *Abies balsamea*, U.S.P. Canada.

Characters.—A pale-yellow ductile oleoresin of the consistence of thin honey, with a peculiar agreeable odour, and a slightly, bitter, feebly acrid taste.

Composition.—An **essential oil** resembling oil of turpentine, and a **resin.**

Dose.—10 to 30 grains.

Preparations.

B.P.	U.S.P.
Charta Epispastica.	Collodium Flexile.
Collodium Flexile.	

Uses.—Used in the preparation of collodion flexile and of charta epispastica; also to mount microscopic objects. It may be given internally as a stimulant to mucous membranes.

B.P. Thus Americanum. Common Frankincense.—The concrete turpentine which is scraped off the trunks of *Pinus australis* and *Pinus Tæda*. Southern States of North America.

Characters.—A softish bright yellow opaque solid, resinous but tough, having the odour of American turpentine.

Preparation.

B.P.	U.S.P.
Emplastrum Picis.	None.

Use.—Applied externally is a slight stimulant. Contained in pitch-plaster.

U.S.P. Terebinthina. Turpentine.—A concrete oleoresin, obtained from *Pinus australis* and from other species of *Pinus*.

CHARACTERS.—In tough, yellowish masses, brittle in the cold, crummy-crystalline in the interior, of a terebinthinate odour and taste.

DOSE.—As a stimulant, antispasmodic, or diuretic, 5–30 min. As an anthelmintic, 2–4 fl. dr.

Oleum Terebinthinæ, B. and U.S.P. OIL OF TURPENTINE. The volatile oil distilled usually by the aid of steam from the oleoresin (turpentine) obtained from *Pinus australis* (*P. palustris*), *Pinus Tæda*, and sometimes *Pinus Pinaster* and *Pinus sylvestris*, rectified if necessary.

CHARACTERS.—Limpid, colourless, with a strong peculiar odour, and pungent and bitter taste.

COMPOSITION.—A mixture of **several hydrocarbons** having the composition $C_{10}H_{16}$.

PREPARATIONS.

B.P.			DOSE.
Confectio Terebinthinæ			60–120 gr.
Enema	„		
Linimentum	„	(*vide* p. 516)	
„	„	**Aceticum** (*vide* p. 516)	
Unguentum	„		

U.S.P.

Linimentum Cantharidis (*vide* p. 517) ...1 part in 7.
„ Terebinthinæ (*vide* p. 517)...1 part in 3.

Confectio Terebinthinæ. CONFECTION OF TURPENTINE.—Oil of turpentine, 1 fl. oz.; liquorice root, 1 oz.; honey, 2 oz.

Enema Terebinthinæ.—Oil of turpentine, 1 fl. oz.; mucilage of starch, 15 fl. oz.

ACTION.—Oil of turpentine when **applied to** the **skin** acts as an irritant and rubefacient, causing a sensation of burning, and if applied for any length of time, especially if evaporation be prevented, it causes vesication.

When inhaled it produces sneezing, tightness across the eyes, and difficulty of breathing, caused reflexly by the local irritant action of the drug on the nasal mucous membrane.

Internally it causes burning in the mouth, and reflexly a profuse flow of saliva, and in the **stomach** it gives rise to a sensation either of heat or of cold. In large doses it produces gastro-enteritis with vomiting and diarrhœa. Ulceration of the intestine has been found after death from poisoning with turpentine.

After absorption it causes a rise and then a fall of blood-pressure, due to its first stimulating and afterwards paralysing the vaso-motor centres. Its effect on the pulse is uncertain: sometimes it is slowed and sometimes quickened.

Respiration becomes quickened and spasmodic. The drug is partly excreted by the lungs, and acts on the mucous membrane, lessening its secretion.

The **temperature** sometimes rises and sometimes falls.

It acts on the **nerve-centres**, lessening first the functions of he brain, causing a diminution of voluntary movement; then the nctions of the cord, lowering reflex action; and lastly those f the medulla, causing dilatation of the vessels, lowered blood-ressure, and slowed respiration.

It is excreted by the **kidneys**. In small doses it increases he quantity of urine, to which it gives a sweetish odour re-embling that of violets. In large doses it diminishes the quan-ty of urine and gives rise to pain in the lumbar region, burning n the urethra, painful micturition, and even hæmaturia. Large oses of turpentine have a **purgative** action.

USES.—**Externally** it is used as a rubefacient and counter-ritant to relieve pain or inflammation, as in chronic rheu-natism affecting either the joints or muscles, also in inflam-nations of internal organs, as chronic bronchitis (liniment over he chest), pleuritis, and peritonitis with tympanites (by means f hot turpentine stupes). It is also very useful as a local appli-ation in sciatica and other neuralgias. It is used as an inhala-on (as well as internally) in chronic bronchitis with profuse xpectoration (p. 253), and is supposed to be useful in phthisis. t has been used as a curative agent in psoriasis, after the re-noval of the scales by alkaline baths. Two drachms to one ounce f olive oil is a good strength to begin with; the proportion must e increased till pure oil is used, if the patient can bear the ap-lication. The treatment has, however, been almost completely uperseded by chrysophanic acid and other preparations.

Internally, in hæmorrhage and ulceration of the intestine, as n typhoid fever, it is very serviceable in doses of 10–60 minims very hour or two hours, the action being watched; also in æmorrhage from other organs, as the lungs, nose, uterus, idneys; but in hæmaturia it must be given in very small doses 5 minims), as large ones produce harm.

As a **vermifuge**, to destroy tape-worm, it must be given in rge doses, which are best combined with castor oil, as it then asses through the alimentary canal rapidly, and consequently not absorbed and produces no disagreeable renal symptoms. f moderate doses are given, insufficient to produce purgation, he drug may be absorbed, and hæmaturia, nausea, and vomiting ay ensue.

It is sometimes employed in biliary colic (1 part of oil of rpentine with three of ether).

The French oil of turpentine (old and containing ozone) is sed in phosphorus-poisoning, and has been given in acute ellow atrophy of the liver. New oil of turpentine, free from zone, is useless. Turpentine is sometimes used as an anti-pasmodic in hysterical affections.

B.P. Oleum Pini Sylvestris. OIL OF SCOTCH FIR. FIR

Wool Oil.—It is a colourless liquid obtained by distilling the fresh leaves of the Scotch fir, *Pinus sylvestris*.

B.P. Preparation.

Vapor Olei Pini Sylvestris.—Rub fir-wool oil, 40 minims, with light carbonate of magnesium, 20 grains, and gradually add sufficient water to produce one fluid ounce.

Put one fluid drachm of this mixture with half a pint of cold water and half a pint of boiling water into an apparatus so arranged that air may be made to pass through the solution and may afterwards be inhaled.

Action.—Somewhat similar to that of oil of turpentine.

Uses.—It is used as a liniment to rheumatic joints or muscles, and is used as an addition to baths in rheumatism (p. 470). As an inhalation (at 140° F.) it is useful in sore-throat and laryngeal catarrh. The use of water which is too hot may cause loss of voice. It is a stronger stimulant than benzoin (p. 964) and is more useful in subacute or chronic cases. In acute cases the inhalation of benzoin (1 fl. dr. of compound tincture in 10 fl. oz. of warm water) is usually preferable. It is of use in chronic bronchitis, in bronchiectasis, and in phthisis with a tendency to hæmorrhage.

Terebene. $C_{10}H_{16}$. Not officinal.—Isomeric with oil of turpentine, and prepared from it by oxidation with sulphuric acid.

Characters.—A colourless liquid, with the odour of pine wood, and a hot taste.

Solubility.—Insoluble in water; soluble in alcohol.

Dose.—10 to 20 minims.

Administration.—It may be given internally in sugar, or as an inhalation like the vapor olei pini sylvestris, B.P.; 40 minims suspended in one ounce of water by the aid of 20 grains of light carbonate of magnesium; one drachm to be inhaled in one pint of hot water. It is sometimes inhaled on a respirator (10–20 min.).

Action.—Terebene acts like oil of turpentine (*q.v.* p. 1059), as a **stimulant** to the bronchial mucous membrane. It is, however, more agreeable to take, and is said not to have the same tendency to cause renal mischief. It is **antiseptic** and **deodorant**.

Uses.—Both internally and by inhalation, terebene has been extensively used for the dyspnœa of emphysema and chronic bronchitis, where there is no acute inflammation.

It is sometimes useful in flatulence due to fermentative changes in the stomach.

Sanitas. Not officinal.—A **disinfecting** solution obtained by acting on oxidised turpentine with water. Its active principle is peroxide of hydrogen (p. 540). Its advantages are that it is not poisonous and does not stain linen.

U.S.P. Oleum Succini. Oil of Amber.—A volatile

obtained by the destructive distillation of amber and purified by subsequent rectification.

CHARACTERS.—A colourless pale yellow thin liquid, having an empyreumatic balsamic odour, a warm acrid taste, and a neutral or faintly acid reaction. Readily soluble in alcohol.

DOSE.—5 to 10 minims in capsule.

ACTION AND USES.—Externally it is **stimulant** and may be used like oil of turpentine. Internally it is said to be **antispasmodic.**

Resina, B. and U.S.P. RESIN. COLOPHONY.—The residue left after distilling off the volatile oil from turpentine, U.S.P.

CHARACTERS.—Translucent, yellowish, brittle, pulverisable; fracture shining.

COMPOSITION.—Resin is the portion of turpentine fixed by oxidation. The greater part of it consists of **abietic anhydride** ($C_{44}H_{62}O_4$), this being formed by the dehydrating of abietic acid ($C_{44}H_{64}O_5$), during the distillation of the oil. It is again transformed into abietic acid by treating it with alcohol. A small proportion of **pimaric acid** is obtained from resin.

PREPARATIONS.

B.P.	U.S.P.
Charta Epispastica.	Ceratum Resinæ.
Emplastrum Calefaciens.	Emplastrum Resinæ.
,, Cantharidis.	
,, Opii.	
,, Picis.	
,, **Resinæ.**	
,, Saponis.	
Unguentum Resinæ.	
,, Terebinthinæ.	

USE.—Resin is only used externally as a **stimulant** application, in the form of ointment or plaster.

B.P. Laricis Cortex. LARCH BARK.—The bark, deprived of its outer layer, of *Pinus Larix* (*Abies Larix*), the common larch.

CHARACTERS.—In flat pieces or sometimes large quills, with the inner surface yellow and fibrous, and the outer surface reddish-brown under a greyish epidermis. Odour faint, resembling turpentine, taste astringent.

COMPOSITION.—A peculiar **tannin** striking olive-green with salts of iron, and larixinic acid or **larixin.**

PREPARATION.

B.P.	DOSE.	U.S.P.
Tinctura Laricis	20–30 min.	Not given.

ACTION AND USE.—It has the same action as oil of turpentine. It is seldom used except as a **stimulant expectorant** in chronic bronchitis with abundant secretion.

Pix Burgundica B. and U.S.P. BURGUNDY PITCH.—A resinous exudation from the stem of the spruce fir, *Pinus picea* (*Pinus Abies* or *Abies excelsa*). Melted and strained. Switzerland.

CHARACTERS.—Hard and brittle, yet gradually taking the form of the vessel in which it is kept; opaque, varying in colour, but generally dull reddish-brown; of a peculiar odour and aromatic taste, without bitterness. Readily soluble in glacial acetic acid.

COMPOSITION.—An amorphous **resin**, mixed with **oil of turpentine** and other oils isomeric with it, and **abietic acid**.

PREPARATIONS.

B.P.	U.S.P.
Emplastrum Ferri.	Emplastrum Picis Burgundicæ.
„ **Picis.**	„ „ cum Cantharide.

USE.—It is used as a **stimulant** in chronic rheumatism and bronchitis, in the form of plasters.

U.S.P. Pix Canadensis. CANADA PITCH. HEMLOCK PITCH.—The prepared resinous exudation of *Abies canadensis*.

CHARACTERS.—It is somewhat softer than the Burgundy pitch.

PREPARATION.

Emplastrum Picis Canadensis.

Pix Liquida, B. and U.S.P. TAR.—A bituminous liquid obtained from the wood of *Pinus sylvestris* and other pines by destructive distillation, B.P. An empyreumatic oleoresin obtained by the destructive distillation of the wood of *Pinus palustris* and of other species of *Pinus*, U.S.P.

CHARACTERS.—Thick, viscid, brownish-black, of a well-known peculiar aromatic odour. Slightly soluble in water, soluble in alcohol, fixed or volatile oils, and in solution of potassa or of soda. Water agitated with it acquires a pale brown colour, sharp empyreumatic taste, and acid reaction.

COMPOSITION.—**Pyroligneous acid**, methyl alcohol, acetic acid and oily bodies, **creasote**, with toluene, xylene, and other **hydrocarbons**.

DOSE.—Of tar, 20 minims to 1 drachm, and upwards, made into pills with flour, or given as tar-water in doses of 1–4 fluid ounces.

PREPARATION.

B.P.

Unguentum Picis Liquidæ (tar 5 oz., yellow wax 2 oz.).

U.S.P.	DOSE.
Syrupus Picis Liquidæ	½ fl. oz.
Unguentum Picis Liquidæ (equal parts of tar and suet).	

U.S.P. Syrupus Picis Liquidæ. SYRUP OF TAR.—Pour cold water (12) on tar (6), stir frequently for twenty-four hours, and then throw the water away. Pour on boiling distilled water (50), stir for fifteen minutes, and then set aside for thirty-six hours, stirring occasionally. Decant, filter, and add sugar, 40 parts.

ACTION AND USE.—Tar acts as a **stimulant** both to the skin and to mucous membranes. It is used in chronic scaly skin-diseases, such as psoriasis, and the scaly stages of eczema. It is an efficient agent in relieving the itching of chronic skin-affections. The best way of applying tar is in the form of distilled wood-tar, beech, birch, or juniper tar. These should be applied carefully with a stiff brush, and are found useful in chronic eczema, psoriasis, the prurigo of Hebra, lupus erythematosus, lichen ruber, and ringworm. They may be made into ointment with vaseline or lard. In the form of tar-water or of vapour, it is useful in chronic bronchitis and phthisis.

U.S.P. Oleum Picis Liquidæ. OIL OF TAR.—A volatile oil distilled from tar.

An almost colourless liquid when freshly distilled, but soon acquiring a dark, reddish-brown colour, having a strong tarry odour and taste, and an acid reaction. Specific gravity about 0·970. It is readily soluble in alcohol.

USE.—It is used, dissolved in water or in alcohol, as an external application in skin diseases.

U.S.P. Thuja. THUJA. ARBOR VITÆ.—The fresh tops of *Thuja occidentalis*.

CHARACTERS.—Twigs flattish, two-edged, the scale-like leaves appressed and closely imbricate in four rows, rhombic-ovate, obtusely pointed, with a roundish gland upon the back; of a balsamic, somewhat terebinthinate odour, and a pungently aromatic, camphoraceous, and bitter taste.

DOSE.—Of a saturated tincture or fluid extract 1 fluid drachm.

ACTION.—The twigs of thuja, like those of savin, may produce **abortion**. They probably have no direct specific action on the uterus itself, but cause great gastro-intestinal irritation, and thus act on the uterus reflexly. The oil of thuja has an action somewhat like camphor, and like it produces epileptiform **convulsions** in warm-blooded, and **paralysis** in cold-blooded animals. Both camphor and oil of thuja have only a slight action on the heart. They both produce rhythmical contraction and dilatation of the **vessels** (as seen in the rabbit's ear). Both lessen the **temperature** (Köhne) (cf. p. 1019).

USES.—It is **diuretic**, astringent, and **aromatic**, and its volatile oil has been used as a **vermifuge**. It has been employed in the form of a decoction in coughs, rheumatism, dropsy and amenorrhœa.

U.S.P. Juniperus. JUNIPER.—The fruit of *Juniperus communis*.

CHARACTERS.—Nearly globular, about one-third of an inch (8 millimetres) in diameter, dark purplish, with a bluish-grey bloom, a three-rayed furrow at the apex, internally pulpy, greenish-brown, containing three ovate, somewhat triangular, bony seeds, with several large oil-glands on the surface; odour aromatic; taste sweet terebinthinate, bitterish and slightly acrid.

Oleum Juniperi, B. and U.S.P. OIL OF JUNIPER.—A volatile oil distilled from the unripe fruit of *Juniperus communis*.

CHARACTERS.—Colourless or pale greenish-yellow, of a sweetish odour, and warm aromatic taste.

DOSE.—1–4 min.

PREPARATIONS.

B.P.	DOSE.
Spiritus Juniperi (with spirit 1 volume in 50) (Is contained in Mistura Creasoti.)	30 min.–1 fl. dr.

U.S.P.	
Spiritus Juniperi (3 per cent. in alcohol)	30–60 min.
„ „ Compositus	2–4 fl. dr.

U.S.P. Spiritus Juniperi Compositus. COMPOUND SPIRIT OF JUNIPER.—Oil of juniper, 10; oil of caraway, 1; oil of fennel, 1; alcohol, 1,000; water up to 5,000.

ACTION AND USES.—Oil of juniper is a local **stimulant**. It is contained in gin and hollands. It resembles oil of turpentine in its action, but has a more powerful effect on the kidneys. It is used chiefly as a **diuretic** in dropsy depending on cardiac, liver, or kidney disease. In the last case it must be employed with caution. In a healthy man it does not seem to increase the flow of urine. Gin is flavoured with juniper, and is frequently employed as a diuretic. The compound spirit of juniper, U.S.P., approximates to gin in strength and may be used in place of it.

Sabinæ Cacumina, B.P.; Sabina, U.S.P. SAVIN-TOPS, B.P.; SAVINE, U.S.P.—The (fresh and dried, B.P.) tops of *Juniperus Sabina*. Collected in spring.

CHARACTERS.—Twigs densely covered with minute imbricated appressed leaves in four rows; odour strong, peculiar, and unpleasant; taste acrid, bitter, resinous, and disagreeable.

COMPOSITION.—The active principle is a **volatile oil**.

DOSE.—Of dried tops, 4–10 gr. or more.

PREPARATIONS.

B.P.	DOSE.
Oleum Sabinæ (from fresh plant)	1–5 min.
Tinctura „	20 min.–1 fl. dr.
Unguentum Sabinæ (8 oz. fresh savin-tops, bruised, are digested with melted wax, 3 oz., and benzoated lard, 16 oz., for 20 minutes, and strained).	

U.S.P.	
Extractum Sabinæ Fluidum	5–15 min.

Oleum Sabinæ, B. and U.S.P.—A volatile oil distilled from the fresh tops of *Juniperus Sabina*.

CHARACTERS.—Colourless or yellowish, becoming darker and thicker by age and exposure to air, peculiar odour, pungent, bitterish, and camphoraceous taste.

DOSE.—1 to 4 minims.

ACTION AND USES.—Savine owes its properties to its oil.

Externally it is used as an **irritant** to keep open issues or blisters.

Internally it produces symptoms of violent gastro-intestinal irritation, with either stoppage of the urine or hæmaturia and difficulty in micturition. In women it causes congestion of the pelvic organs, and has been used criminally to procure **abortion**; in these cases gastro-enteritis and death have occurred. Small doses may be used as an **emmenagogue** when menstruation is deficient and the patient is not pregnant.

CHAPTER XXXVIII.

SUB-KINGDOM II.—CRYPTOGAMÆ.

FILICES.

Filix Mas, B.P.; Aspidium, U.S.P. MALE FERN.—The rhizome with the persistent bases of the petioles of *Aspidium Filix mas*. Collected late in the autumn, divested of its scales, roots, and all dead portions, and carefully dried with a gentle heat. Should not be used if more than a year old, B.P. The rhizome of *Aspidium Filix-mas* and of *Aspidium marginale*, U.S.

CHARACTERS.—Tufted, scaly, greenish-brown; powder greenish-yellow, with a disagreeable odour, and a nauseous, bitter, somewhat astringent taste.

COMPOSITION.—A dark green oil which deposits crystals of **filicic acid**, also traces of **volatile oil**. The filicic acid is regarded as the chief, though not the only, active principle; tannin, resin, and sugar have been found in the rhizome.

DOSE.—Of the powder, 60–180 gr.

PREPARATIONS.

B.P.	DOSE.
Extractum Filicis Liquidum	15 min.–1 fl. dr.
U.S.P.	
Oleoresina Aspidii	30–60 min.

ACTION AND USES.—The liquid extract is one of the best **anthelmintics** against tape-worm, killing the *Bothriocephalus latus*, *Tænia solium*, and *Tænia mediocanellata*. Pomegranate root bark is said to kill the latter with greater certainty. The dose often given is too small, and hence failure is attributed to the drug when it really depends on the smallness of the dose. Single doses of ʒj.–ʒjss. of the liquid extract will often cure at once.

METHOD OF ADMINISTRATION.—Allow the patient to take no food after five or six in the evening except a little bread-and-milk. Just before bed-time give ʒj. of the liquid extract in ʒj. of mucilage, and let the patient lie down immediately and go to sleep. This often prevents the vomiting which sometimes occurs. Next morning administer a purgative, and repeat the treatment until the worm comes away.

Another method is to give a dose of castor oil at night (with

the same conditions of feeding) and early next morning give a dose of liquid extract (ʒss.–ʒj.), and abstain from food till after the bowels have acted.

LICHENES.

Cetraria, B. and U.S.P. Iceland Moss.—The entire lichen, *Cetraria islandica*. North of Europe.

Characters.—Foliaceous, lobed, crisp, cartilaginous, brownish-white, paler beneath; taste bitter and mucilaginous. A strong decoction gelatinises on cooling.

Composition.—**Lichenin** and **cetrarin** or cetraric acid. The former constitutes 70 per cent. of the moss. It swells in cold, and dissolves in hot water, gelatinising on cooling. The latter, which is the bitter principle, is obtained in white acicular crystals, and forms soluble salts with alkalis.

Preparations.

B.P.		Dose.
Decoctum Cetrariæ	(1 oz. to 1 pint)	1–2 fl. oz.

U.S.P.		
Decoctum Cetrariæ		2–4 fl. oz.

Action and Uses.—It is **demulcent, nutritious,** and slightly **tonic.**

B.P. Litmus.—A blue pigment prepared from various species of Roccella.

Litmus Paper, Blue, B. and U.S.P.—Unsized white paper steeped in tincture of litmus, and dried by exposure to the air.

Litmus Paper, Red, B. and U.S.P.—Unsized white paper steeped in tincture of litmus which has been previously reddened by the addition of a very minute quantity of sulphuric acid, and dried by exposure to the air.

Litmus Tincture, B.P.; Solution of Litmus, U.S.P.—A solution prepared by macerating 1 part of litmus, in powder, in 10 parts of proof spirit, B.P., or diluted alcohol, U.S.P., in a closed vessel for two days, and filtering.

Use.—Red litmus paper is used as a test for alkalis, and blue litmus as a test for acids.

FUNGI.

Muscarinæ Nitras. Not officinal.—An alkaloid, $C_5H_{15}NO_3$, prepared from the Fly Agaric, *Amanita muscaria*, a fungus growing in all parts of the world.

Muscarine can be prepared artificially from cholin, $C_5H_{15}NO_2$, by oxidation with nitric acid: it differs from cholin by having one atom of oxygen more, and may be represented in a constitu-

tional formula as $N\begin{cases}(CH_3)_3\\CH_2.\\OH\end{cases}CH(OH)_2$. Betain (trimethylglycin), $C_5H_{13}NO_3$, is also related to muscarine and cholin, and is said to have been produced by oxidation of the latter. Cholin and artificial muscarine have a similar action, which differs from that of natural muscarine, in paralysing the ends of motor nerves like curare. Artificial muscarine is 500 times as strong as cholin, and 50 times more lethal in its action.[1] It is not completely antagonised by atropine as natural muscarine is.

CHARACTERS.—A viscid, yellowish-brown liquid, soluble in water, and giving the reactions of an alkaloid (p. 504).

DOSE.—$\frac{1}{2}$ to $\frac{3}{4}$ grain, hypodermically.

ACTION.—Muscarine is a **myotic** (p. 219), and an **antihidrotic** (p. 441) and sialagogue (p. 357). It has a powerful action on the **heart**, paralysing the cardiac muscle (p. 316) and stimulating the inhibitory ganglia (p. 317). It is a general **emetic** (p. 373), and diminishes the activity of the respiratory centre (p. 241). Its action is completely neutralised by atropine (p. 495).

USES.—Hypodermically, muscarine has been used in checking night-sweats.

Agaricus albus. Not officinal.

CHARACTERS.—It occurs in white irregular pieces, light and friable, with a sweetish and afterwards bitter taste.

DOSE.—2 to 30 gr.

COMPOSITION.—A white, crystalline body, **agaricin**, and various other ill-defined principles.

PREPARATIONS.

	DOSE.
Extractum Agarici	3–6 gr.
Tinctura ,, (1 in 10)	20–60 min.
Agaricin	$\frac{1}{12}$–$\frac{1}{6}$ gr.

ACTION.—In large doses, agaric is **purgative** and sometimes **emetic**. It acts in smaller doses as an **antihidrotic** (p. 441).

USES.—In the form of extract or of agaricin, it has been found useful in checking night-sweating in phthisis.

Ergot, B. and U.S.P. ERGOT. ERGOT OF RYE.—The sclerotium (compact mycelium or spawn) of *Claviceps purpurea*, produced between the paleæ and replacing the grain of *Secale cereale*, the common rye, Nat. Ord. *Graminaceæ*.

CHARACTERS.—Somewhat fusiform, subtriangular, curved, with a longitudinal furrow on the concave side, obtuse at the ends, about an inch long, purplish black outside, pinkish within, solid, breaking with a short fracture, odour peculiar, but strong if the powder be triturated with solution of potash, taste oily and disagreeable.

[1] Boehm, *Arch. f. exp. Path. u. Pharm.*, Bd. 19, p. 87.

PREPARATIONS.

B.P.	STRENGTH.	DOSE.
Extractum Ergotæ Liquidum	1 oz. to 1 fl. oz.	10–30 min.
Infusum „	11 gr. to 1 fl. oz.	1–2 fl. oz.
Tinctura „	109 gr. to 1 fl. oz.	10 min.–1 fl. dr.

U.S.P.		
Extractum Ergotæ Fluidum	100 gm. in 100c.c.	30–60 min.
Vinum „	15 parts in 100	2–4 fl. dr.
Extractum „	5 times strength of fluid extract	3–12 gr.

B.P. Ergotinum. ERGOTIN.—Purified extract of ergot, commonly called ergotin or ergotine, or Bonjean's ergotine.

PREPARATION.—By evaporating the fluid extract of ergot, 4 fl. oz., by a water-bath to a syrupy consistence, and when cold mixing with 4 fl. oz. of spirit. Let it stand for half an hour, then filter, and evaporate the filtered liquid to the consistence of a soft extract.

COMPOSITION.—The chemical composition of ergot is still very imperfectly known, and the active principle (or principles) to which its most important action, that of causing contraction of the uterus, is due, has not been satisfactorily isolated. The active principles were formerly said to be **ergotin** and ecbolin, but these do not seem to be pure substances. The term ergotin has been applied to several substances. According to Schmiedeberg, two pure principles have been isolated—**ergotinic acid** and an alkaloid, **ergotinine.** According to Dragendorff and Podwyssotzki, the active principles are **sclerotinic acid** and a colloid substance, **scleromucin.** Sclerotinic acid is impure ergotinic acid. In addition to ergotinic acid, ergotinin, and probably several other principles, ergot contains about 35 per cent. of oil, a peculiar sugar (mykose), and two colouring matters, scleroxanthin and sclero-erythrin.

The most recent researches are those of Kobert, who states that ergot contains three active principles : ergotinic acid, **sphacelinic acid,** and an alkaloid, **cornutine.**

DOSE.—2 to 5 grains.

PREPARATION.

Injectio Ergotini Hypodermica (ergotin 1, camphor water 2 parts ; mix by stirring together just before using).

DOSE (by subcutaneous injection), 3–10 min.

GENERAL ACTION.—There is a great difference of opinion as to the action of ergot, due to its preparations undergoing change so rapidly, and hence not being of the same strength. They become quite inactive if kept for any length of time. In certain parts of Germany, where rye-bread is much used, epidemics of **ergotism** have occurred. These epidemics depend both upon the continued large doses of ergot and upon the deficiency of food, the nutritive part of the rye being replaced by the fungus. The deficiency of food is probably an important factor, since continued therapeutic doses of ergot rarely produce ergotism, though occasionally they do so.

There are two varieties of symptoms seen in ergotism: (1) the **gangrenous**; (2) the **anæsthetic** or **convulsive**. Both begin with gastro-intestinal disturbance, causing loss of appetite, nausea, vomiting, and diarrhœa.

The **gangrenous** symptoms are redness of the skin followed by well-marked gangrene in the part. The cause of this gangrene is probably stasis due to the great contraction of the small blood-vessels.

The **nervous symptoms** are giddiness, with symptoms of irritation and paralysis of sensory nerves, or more probably of sensory centres, e.g. the posterior columns of the spinal cord. The irritation is indicated by a sensation as of insects crawling over the skin, flying pains, &c., the paralysis by loss of sensation in the hands and feet. Sclerosis has been found in the postero-lateral columns of the cord in such cases. Spasms may occur, and even convulsions of an epileptic nature.

SPECIAL ACTION.—**Ergotinic acid** causes ascending paralysis of the spinal cord and brain, both in frogs and mammals, with loss of voluntary motion, paralysis of the vaso-motor centre, and fall of blood-pressure, while respiration and reflex irritability continue. It does not appear to have the power of increasing the uterine contractions, and so cannot be regarded as the most important constituent of ergot. **Ergotinine** is also not the active principle, as it is present in very small quantity in ergot, and is to some extent removed by ether without the ergot losing its power.

Sphacelinic acid causes at first great spasmodic contraction of the blood-vessels, with rise of blood-pressure and subsequently symptoms of gangrene. The heart is unaffected. The gangrene in fowls appears to be due to permanent occlusion of the smaller arteries by a hyaline substance, which is formed during the time they are spasmodically contracted. In rabbits, guinea-pigs, and cats the substance is not formed, and no gangrene appears, but their walls degenerate, and blood is effused into various organs. When brought into contact with the intestine, sphacelinic acid, or its sodium salt, causes an inflammatory condition resembling that of typhoid fever, and ergot should therefore be avoided in this disease. Sphacelinic acid causes tetanus of the uterus (Kobert). **Cornutine** causes spastic rigidity in frogs, lasting many days, even when given in very minute doses ($\frac{1}{3\frac{1}{2}}$ of a milligramme). In warm-blooded animals half a milligramme causes salivation, vomiting, diarrhœa, and active movements of the uterus, which are clonic and not tonic. The vessels are contracted and the blood-pressure raised. Sphacelinic acid and cornutine are therefore the principles which cause uterine contraction (Kobert). As these active principles have not yet found their way into common use, it will be better for practical purposes at present to take the results of experiments, not with

pure principles isolated from ergot, but only of an extract such as Bonjean's ergotin, although it is evident that the effects of different preparations may vary according to the proportions of ergotinic acid, sphacelinic acid, and cornutine which they contain. Thus if there be much ergotinic acid, the blood-pressure may be reduced, while if much sphacelinic acid and cornutine be present the blood-pressure will be raised.

Action of Extract of Ergot.—A solution of Bonjean's ergotin injected into animals causes an affection of the **nervous system** indicated by inco-ordination, anæsthesia, and paralysis; and death is due to paralysis of respiration.

The **muscles** are unaffected; the motor nerves are not paralysed, but on the contrary have their power somewhat increased.

The **sensory nerves** are paralysed, but it is uncertain whether the action is central or peripheral. The **spinal cord** is paralysed.

Circulation. Heart.—Its action on the frog's heart is not well marked; sometimes the injection of ergot produces slowing of the pulse-rate with stoppage in diastole, and in these cases direct mechanical irritation immediately after the poisoning does not cause the heart to contract.

Slowing and diastolic arrest occur after section of the vagi, but not after administration of atropine; hence they are due to the action of the ergot on the inhibitory apparatus in the heart itself.

Vaso-motor System.—The blood-pressure is considerably raised. When injected into the jugular vein, the blood-pressure, according to Holmes, is first lowered and then raised considerably, which he explains by supposing that the ergot passing to the right side of the heart causes contraction of the vessels of the lungs (by acting on their muscular walls), and hence lessens the supply to the aortic system and produces a fall of blood-pressure; but when it reaches the medulla it stimulates the vaso-motor centre, and causes contraction of the vessels throughout the body and consequent rise of blood-pressure. This explanation is confirmed by the fact that if ergot is injected into the femoral artery, instead of a fall occurring at first there is a rise due to contraction of vessels in the limb, then a fall as soon as the blood reaches the lungs, and lastly a final rise.

This explanation is not accepted by Wood, who considers that the primary fall is due to the sudden introduction of a large quantity of ergot into the heart causing temporary paralysis, which will pass off as the drug is removed by the circulation.

The final rise of blood-pressure no doubt is due to the action on the medulla, for, if the cord be divided, very little rise follows the injection of ergot.

One other factor, which usually receives very little attention, must be taken into account (as well in this drug as in many others), viz. the effect on the blood-pressure of contraction of the internal viscera, as the intestines or uterus, for by contraction

their blood will be driven out, and a rise of blood-pressure produced without any action on the vessels.

Respiration is usually slowed from the beginning, but in some animals (dogs) it is first quickened and then slowed. Death is due to paralysis of the respiratory centre.

Secretion.—The urine is increased in quantity, and the bladder tends to contract, due to the effect of the drug on its unstriped fibres.

Alimentary Canal.—Ergot markedly increases the peristaltic movements of the intestine.

Uterus.—Ergot causes contraction of the uterus, especially of the pregnant uterus. This contraction is not usually so much rhythmical as **tetanic** in nature, with occasional increases in violence. There is no complete relaxation between the spasms, as in the ordinary labour-pains. This is probably due to an action on the unstriped fibres of the uterus, since ergot causes contraction of involuntary fibres throughout the body, but it may be due wholly or in part to an action on the uterine centre in the spinal cord.

USES.—Ergot is chiefly used in medicine for two purposes: (1) to cause contraction of the uterus; (2) to check hæmorrhage by causing contraction of the vessels.

It is sometimes used to hasten delivery when the power of the uterine contractions is not sufficient to expel the fœtus. But the tetanic nature of the contraction produced by ergot must be borne in mind. It does not increase the power of the labour-pains, but only the tonic contraction of the uterus. It should be carefully avoided if there be any mechanical obstruction to delivery, such as a rigid and undilated os uteri, a contracted pelvis, or an abnormal presentation, for in such cases it may so far interfere with the circulation in the uterus and placenta as to asphyxiate the fœtus, or cause such contraction of the uterus as to produce rupture of its walls. After the child is expelled, the tetanic nature of the contraction produced by ergot is useful, and hence it is used to prevent post-partum hæmorrhage. In these cases, it is administered either in the form of powdered ergot in warm water, or of the liquid extract, or by subcutaneous injection of ergotin. The last method gives the most rapid results, but if the ergotin is injected just beneath the skin it causes irritation and may lead to an abscess, hence it should be injected deep into a muscle, such as the gluteus maximus.

Ergot is also used very largely in the practice of gynæcology, for example, in chronic metritis, in sub-involution of the uterus, after abortions, to promote the expulsion of retained membranes, and in all atonic conditions of the uterus.

It is also used in certain cases of leucorrhœa, also in atony of the bladder and enlarged prostate.

It is used to check hæmorrhage in fibroid tumours of the

uterus; in hæmoptysis (either internally ʒss. of liquid extract every two, three, or four hours, or subcutaneously injected). In hæmatemesis also it is sometimes useful.

In some cases of chronic constipation it is useful, and appears to give tone to the bowel.

Subcutaneous injections of ergotin have been used in purpura, erythema, and in the prurigo of Hebra. Temporary improvement sometimes follows the internal administration of ergotin in urticaria.

U.S.P. Ustilago. USTILAGO. CORN-SMUT.—*Ustilago Maydis* (Nat. Ord., *Fungi*), grown upon *Zea Mays* (Nat. Ord., *Graminaceæ*).

Ustilago should be preserved in a dry place, and should not be kept longer than a year. This fungus is a form of smut growing upon maize.

CHARACTERS.—Irregular, globose masses, sometimes six inches (15 centimetres) thick, consisting of a blackish membrane, enclosing innumerable brownish-black, globular and nodular spores; odour and taste unpleasant.

DOSE.—$\frac{1}{4}$–1 dr. (1–4 gm.).

ACTION.—It **resembles ergot** in its action, and probably also contains the same active principles.

B.P. Cerevisiæ Fermentum. BEER YEAST.—The ferment obtained in brewing beer, and produced by *Saccharomyces* (*Torula*) *cerevisiæ*.

CHARACTERS.—Viscid, semi-fluid, frothy, exhibiting under the microscope numerous round or oval confervoid cells (p. 83).

DOSE.—$\frac{1}{2}$–1 oz.

PREPARATION.

Cataplasma Fermenti. YEAST POULTICE.—Mix beer yeast, 6 fl. oz., with water at 100° F., 6 fl. oz., stir in wheaten flour, 14 oz., and place the mass near the fire till it rises.

USE.—It has been given internally along with camphor and nitrous ether, in typhoid fever and dysentery, and to persons suffering from boils. The poultice is applied to sloughing sores. It is apt to cause much pain.

ALGÆ.

U.S.P. Chondrus. CHONDRUS. IRISH MOSS.—*Chondrus crispus* and *Chondrus mammillosus*.

CHARACTERS.—Yellowish or white, horny, translucent; many-forked; when softened in water, cartilaginous; segments flat, wedge-shaped, or linear; at the apex emarginate or two-lobed; it has a slight seaweed odour, and a mucilaginous, somewhat saline taste. One part of it boiled for ten minutes with thirty parts of water, yields a solution which gelatinises on cooling.

DOSE.—2–4 dr.

USE.—It is a **demulcent**, which is useful in bronchial and catarrhal affections.

SECTION VI.

ANIMAL KINGDOM.

CHAPTER XXXIX.

CLASS MAMMALIA.

Order RODENTIA.

Castoreum. CASTOR. Not officinal.—The dried preputial follicles and their secretion, obtained from the beaver, *Castor Fiber*, and separated from the somewhat shorter and smaller oil-sacs which are frequently attached to them. Hudson's Bay Territory.

CHARACTERS.—Follicles in pairs, about three inches long, fig-shaped, firm, and heavy, brown or greyish-black; containing a dry resinous reddish-brown or brown highly odorous secretion, in great part soluble in rectified spirit, and in ether.

COMPOSITION.—Several **fats, salicin,** a bitter resin, and **bitter volatile oil.**

DOSE.—5-10 gr.

PREPARATION.

	DOSE.
Tinctura Castorei.....22 gr. to 1 fl. oz.....	½–1 fl. dr.

ACTION AND USES.—Castor is used chiefly as an **antispasmodic** and stimulant. It may be given in hysteria and epilepsy. Its action is very like that of musk.

Order RUMINANTIA.

Moschus, B. and U.S.P. MUSK.—The inspissated and dried secretion from the preputial follicles of *Moschus moschiferus*. Central Asia.

CHARACTERS.—In irregular reddish-black rather unctuous grains; having a strong, peculiar, very diffusible odour, and a bitter aromatic taste; contained in a round or slightly oval membranous sac, about two inches in diameter, covered on the outer side with stiff, greyish hairs arranged in a concentric manner around its central orifice.

COMPOSITION.—An **odoriferous substance** not yet isolated, **fats,** resins, and salts.

DOSE.—5–10 gr. and upwards.

U.S.P. PREPARATION.

	DOSE.
Tinctura Moschi.....	20–50 min.

USES.—Musk is often employed in hysteria, although its physiological action has not been investigated. It is more powerful in its action than castor. It is used as an **antispasmodic** and **stimulant.** It is a powerful stimulant, and excellent results have been obtained in cases of collapse, when due to paralysis of the respiration. It has also been given in asthenic pneumonia, bronchitis, fever, and gangrene of the lungs, on account of its power of **stimulating** the **respiratory centre** and covering the disagreeable odour of the sputa. There is a temptation to give it in small doses on account of its high price, and probably many failures are due to this. In cases where it is prescribed at all it should be given freely, and in many instances it seems to be of great service.

Sevum Præparatum, B.P.; Sevum, U.S.P. PREPARED SUET, B.P.; SUET, U.S.P.—The internal fat of the abdomen of the sheep, *Ovis Aries*, purified by melting and straining.

CHARACTERS.—White, smooth, almost scentless; fusible at 103° F.

COMPOSITION.—Consists principally of **stearin.**

B.P. PREPARATIONS.

Emplastrum Cantharidis. Unguentum Hydrargyri.

USE.—Used in the preparation of certain unguenta and emplastra.

Lanolin. Not officinal.—The purified fat of sheep's wool. It is also found in other tissues containing keratin.

CHARACTERS.—Pure lanolin is of a consistence between resin and fat, but it rapidly takes up 100 per cent. of water. It is yellowish-brown, becoming darker on exposure, and has a faint smell.

REACTIONS.—It is a very stable compound, remaining unchanged after boiling with alkalis. When dissolved in anhydrous acetic acid and a small quantity of strong sulphuric acid added, a rose colour is developed, rapidly becoming dark blue and then green.[1]

IMPURITIES.—It ought not to contain more than 0·1 to 0·5 per cent. of free fatty acid, since the presence of a greater amount, especially of the lower fatty acids, is likely to produce irritation of the skin.

COMPOSITION.—Lanolin is a **cholesterin-fat,** having cholesterin, instead of glycerin, combined with the fatty acid.

USES.—Lanolin is recommended by O. Liebreich as a basis for ointments, and as more valuable than glycerin- or petroleum-fats (vaselin), because of its unirritating qualities when pure, but chiefly from its great absorbability when rubbed into the skin. This property is perhaps connected with the fact that lanolin, in the animal kingdom, is closely associated with keratin-

[1] Oscar Liebreich, 'Ueber das Lanolin, eine neue Salbengrundlage,' *Berlin. klin. Wochens.*, 1885, No. 47.

forming cells. Ointments containing carbolic acid and corrosive sublimate rapidly produce the physiological effects of the drug, when rubbed into the skin.

Lanolin has been found useful in the pruritus of old people and in seborrhœa sicca and other skin diseases, but its chief use is in the application of drugs to the skin by means of ointments.[1] An ointment with iodide of potassium is useful in relieving the swelling and pain of chronic joint-affections.

B.P. Sapo Animalis. CURD SOAP.—A soap made with soda and a purified animal fat, consisting principally of stearin.

CHARACTERS.—White or with a very light greyish tint; dry; nearly inodorous; horny and pulverisable when kept in dry, warm air. Easily moulded when heated. It does not impart a greasy stain to paper.

SOLUBILITY.—Soluble in rectified spirit; soluble also in hot water, the solution being neutral or only slightly alkaline to test-paper.

PREPARATIONS IN WHICH CURD SOAP IS USED.

Emplastrum Resinæ.
„ Saponis.
„ „ Fuscum.
Extractum Colocynthidis Compositum.
Linimentum Potassii Iodidi cum Sapone (*vide* p. 516).
Pilula Phosphori (*vide* p. 522).
„ Scammonii Composita (*vide* p. 523).
Suppositoria Acidi Carbolici cum Sapone.
„ Morphinæ cum Sapone.
„ Acidi Tannici cum Sapone.

B.P. Lac. MILK.—The fresh milk of the cow, *Bos Taurus*.
COMPOSITION.—Fat (butter), casein, milk, sugar, and water.

PREPARATION IN WHICH MILK IS USED.

Mistura Scammonii.

USES.—Milk is not, strictly speaking, a medicine, but rather an article of **diet**: it, however, plays an important part in medicine, as we rely on it to a great extent in cases of fever and dyspepsia.

Great attention ought to be paid to the milk given to infants if they are fed from the bottle, for the milk may begin to ferment before it reaches the stomach, and, if it does, it is likely to cause vomiting and diarrhœa, and may even act as a nervous poison, paralysing the nerve-centres. The best way to prevent this is not to have any tubes to the bottles, but to have the teat fixed directly to the bottle, and to scald the bottle well after every meal. The teats should also be soaked in some antiseptic, such as permanganate of potassium and water, when not in use. When milk is drunk in any quantity, the rennet-ferment in the

[1] Liebreich, 'Ueber den med. Gebrauch des Lanolin,' *Deutsch. med. Wochenschrift*, 1886, No. 28.

stomach produces large curds, which are sometimes hard like felt, and are very indigestible and irritating to the stomach; hence, in typhoid fever, the possibility of these curds should be borne in mind. The milk will not readily curdle if mixed with its own bulk of water or soda-water, or (if diarrhœa be present) with lime-water. One may often with advantage use **koumiss**, which is made in the steppes of Tartary by fermenting mares' milk. Phthisis is so rare in Tartary, that Russians suffering from it go to the steppes, and numbers have been cured. No doubt other factors aid the cure, such as climate and change of air; but even in the same conditions of life koumiss often helps to keep the disease in check. It can be made artificially from grape-sugar and cows' milk which is allowed to ferment. It is a good stimulant. It contains lactic acid, alcohol, casein, and fat thrown down in small flakes. **Kephir** is made by fermenting the milk of cows, sheep, or goats; it is very much like koumiss, and may be used for the same purposes. It contains alcohol.

Milk may be used with ferments such as pepsin or pancreatin. The mixture is allowed to stand for a time, and then boiled to stop the fermentation.

Cows' milk diluted with one or more parts of water and a little milk-sugar added, forms a good substitute for human milk as food for infants.

Saccharum Lactis, B. and U.S.P. SUGAR OF MILK.—$C_{12}H_{24}O_{12}$ or $C_{24}H_{24}O_{24}$; 360.—A peculiar crystalline sugar, obtained from the whey of cows' milk by evaporation and purified by re-crystallisation.

CHARACTERS.—Usually in cylindrical masses, two inches in diameter, with a cord or stick in the axis, or in fragments of cakes; greyish-white, crystalline on the surface and in its texture, translucent, hard, scentless, faintly sweet, gritty when chewed.

SOLUBILITY.—Soluble in 7 parts of water at 15° C. (59° F.), and in 1 part of boiling water; insoluble in alcohol, ether, or chloroform.

REACTIONS.—On adding to a solution of sugar of milk in an equal weight of boiling water some solution of soda, the liquid turns brownish, and, on further addition of test-solution of sulphate of copper, a brick-red precipitate separates.

IMPURITY.—Cane-sugar.

TEST.—If 1 part of sugar of milk be sprinkled upon 5 parts of sulphuric acid contained in a flat-bottomed capsule, the acid should acquire not more than a greenish or reddish, but no brownish or brownish-black colour within one hour (absence of cane-sugar).

PREPARATION.

B.P.

Pulvis Elaterini Compositus.

USES.—Sugar of milk is used as a **diluent** in the abstracts, denarcotised opium, &c., of the U.S.P. It is harder, less sweet, and less soluble than cane-sugar, and hence is a better **excipient** and diluent for powders that require trituration.

B.P. Pepsin. PEPSIN.—A preparation of the mucous lining of a fresh and healthy stomach of the pig, sheep, or calf.

PREPARATION.—The stomach of one of these animals recently killed having been cut open, and laid on a board with the inner surface upwards, any adhering portions of food, dirt, or other impurity, are to be removed and the exposed surface slightly washed with cold water; the cleansed mucous membrane is then to be scraped with a blunt knife or other suitable instrument; and the viscid pulp thus obtained is to be immediately spread over the surface of glass or glazed earthenware, and quickly dried at a temperature not exceeding 100° F.

DOSE.—2–10 gr. given with a meal.

U.S.P. Pepsinum Saccharatum. — Pepsin, the digestive principle of the gastric juice, obtained from the mucous membrane of the stomach of the hog, and mixed with powdered sugar of milk.

CHARACTERS.—Saccharated pepsin is a white powder of a slight but not disagreeable odour and taste, and a slightly acid reaction.

SOLUBILITY.—It is not completely soluble in water, leaving floccules of pepsin floating in the solution, which, however, dissolve on the addition of a small quantity of hydrochloric acid.

IMPURITIES.—Strong turbidity of the acidulated solution indicates the presence of mucus, which also imparts to the saccharated pepsin a disagreeable odour and taste, and will eventually impart to it an ammoniacal odour.

U.S.P. PREPARATION.

	DOSE.
Liquor Pepsini	2–4 fl. dr.

USES.—Pepsin is given as an **aid to digestion,** when the ordinary stimuli do not excite sufficient secretion, and the digestive ferment is insufficient. Such cases occur during a long illness or during recovery from an acute disease, in old people, and in people with atrophy of the mucous membrane and glands of the stomach, due to alcoholic excesses or long-continued dyspepsia. It may be given either with or just after meals. It has no influence on farinaceous foods or fat, but only acts on gelatinous and albuminous matter; hence it is no use giving it after farinaceous or fatty food.

In these cases the secretion of acid is usually defective, and a little dilute hydrochloric acid given along with pepsin, and again about two hours after meals, is very useful.

In some cases of asthma, dependent on insufficient digestion, pepsin is very useful. Pepsin wines and essences usually contain little or no pepsin, and have little digestive power, but they contain rennet, and are frequently of use in indigestion in children; they also appear serviceable in adults.

U.S.P. Fel Bovis. OX-GALL. — The fresh gall of *Bos Taurus*.

CHARACTERS.—A brownish-green, or dark green, somewhat viscid liquid, having a peculiar odour, a disagreeable bitter taste, and a neutral or faintly alkaline reaction. Specific gravity 1·018 to 1·028.

REACTIONS.—A mixture of 2 drops of ox-gall and 10 c.c. of water, when treated first with a drop of freshly prepared solution of 1 part of sugar in 4 parts of water, and afterwards with sulphuric acid until the precipitate first formed is redissolved, gradually acquires a cherry-red colour, changing successively to carmine, purple, and violet.

PREPARATIONS.

U.S.P.	DOSE.
Fel Bovis Inspissatum	
„ „ Purificatum	8–15 gr.

U.S.P. Fel Bovis Inspissatum. INSPISSATED OX-GALL.

PREPARATION.—Heat the ox-gall to a temperature not exceeding 80° C. (176° F.), strain it through muslin, and evaporate the strained liquid, on a water-bath, in a porcelain capsule, from 100 parts to 15 parts.

Fel Bovinum Purificatum, B.P.; Fel Bovis Purificatum, U.S.P. PURIFIED OX-BILE.—The purified gall of the ox, *Bos Taurus*.

PREPARATION.—Mix fresh ox-bile (1 pint) and rectified spirit (2 pints) by agitation in a bottle, and set aside for twelve hours until the sediment subsides. Decant the clear solution, and evaporate it in a porcelain dish by the heat of a water-bath, until it acquires a suitable consistence for forming pills, B.P. Evaporate ox-gall 3 parts in a water-bath to 1 part. Add alcohol 1 part. After twenty-four hours decant, filter, distil off the alcohol, and evaporate to a pilular consistence, U.S.P.

CHARACTERS.—A yellowish-green substance, having a taste partly sweet and partly bitter.

SOLUBILITY.—It is soluble in water and in spirit.

REACTIONS.—A solution of one or two grains of it, in about a fluid drachm of water, when treated, first with a drop of freshly made syrup consisting of one part of sugar and four of water, and then with sulphuric acid cautiously added until the precipitate at first formed is redissolved, gradually acquires a cherry-red colour, which changes in succession to carmine, purple, and violet. Its watery solution gives no precipitate on the addition of rectified spirit.

COMPOSITION.—**Taurocholic** and **glycocholic acids**, mucus, **cholesterin**, fats, and salts.

DOSE.—Of purified bile, 5–10 gr. or more, formed into pills or given in small gelatin capsules. When the object is to affect the intestines rather than the stomach, the latter mode is preferable.

ACTION AND USES.—Bile precipitates pepsin and interferes with the digestion of albuminous substances in the stomach. It seems also to irritate the mucous membrane and gives rise to headache and vomiting. It does not aid the digestion of farinaceous food. It quickens the absorption of fats, it prevents to some extent putrefactive changes in the intestinal contents, and it quickens peristaltic action. Some purgatives, such as aloes and jalap, only act when mixed with bile. It is therefore a useful adjunct to them in cases of jaundice with deficiency of bile in the intestine. It is sometimes used in dyspepsia with constipation, and is given by some along with opium in order to prevent

the constipating effect of the latter. Its action in preventing putrefactive changes in the intestine may sometimes be useful in cases of indigestion where these occur (pp. 101, 378), and where the flatus has consequently a very disagreeable odour. In order to prevent its local action on the stomach, it may be given as pills coated with keratin.

Keratin. Not officinal.

PREPARATION.—Horn-turnings are digested with artificial gastric juice until all the matter soluble in them has been removed. They are then allowed to lie for some weeks in ammonia or glacial acetic acid, which gradually dissolves them. The solvent is then allowed gradually to evaporate until a mucilaginous solution is obtained.

CHARACTERS.—The solution resembles gum in appearance, and when dry forms yellow or yellowish-brown scales. When dried, keratin is absolutely insoluble in gastric juice, but dissolves readily in the juices of the intestine.

USES.—To coat pills containing any substance which we wish to act upon the intestine without acting on the stomach. These are:—

1. Such substances as irritate the gastric mucous membrane when long used, e.g. arsenic, all anthelmintics, salicylic acid, creasote, chrysarobin, copaiba, cubebs, digitalis, preparations of iron (and especially the iodide and chloride), preparations of mercury (especially the perchloride and periodide), opium, phosphorus, quinine, tartarated antimony.

2. Such substances as impair digestion in the stomach by forming insoluble precipitates with pepsin and peptones, e.g. tannic acid, alum, acetate of lead, subnitrate of bismuth, nitrate of silver, corrosive sublimate.

3. Such substances as are partly rendered inert by the gastric juice, and partly decomposed in an undesired manner, e.g. alkalis, soap, bile, calcium sulphide, ferric sulphide, charcoal, nitrate of silver, iodide of iron, green and red iodides of mercury, &c.

4. Medicines which we wish to introduce into the duodenum in as concentrated a form as possible, e.g. kousso, extract of male fern, santonin, nitrate of silver, acetate of lead or tannin in ulceration of the bowels, bile, charcoal, soaps, and alkalis, &c.

5. Medicines of which we desire the remote without the local action, e.g. iron, quinine, arsenic in gastric catarrh, in anæmia, in cardialgia and gastric ulcer.

MODE OF APPLICATION.—The medicine is thoroughly mixed with marsh-mallow powder, liquorice powder, or charcoal, and a few drops of almond oil. It is then made into a pill-mass with cacao-butter. After the pills have been made of the proper size they are covered with a thin coating of cacao-butter, and then with one, or better still with two or three coats of keratin.

Usually the solution of keratin in ammonia is employed, but

the solvent least likely to decompose the medicine may be employed, and thus the acetic acid solution may be used for the chloride of iron or mercury, or salicylic acid.

Order PACHYDERMATA.

Adeps Præparatus, B.P.; Adeps, U.S.P. PREPARED LARD, B.P.; LARD, U.S.P.—The purified fat of the hog, *Sus Scrofa*, B.P.; the prepared internal fat of the abdomen of *Sus Scrofa* purified by washing with water, melting, and straining, U.S.P.

CHARACTERS.—A soft white fatty substance, melting at about 100° F. Has no rancid odour.

SOLUBILITY.—It dissolves entirely in ether.

REACTIONS.—Distilled water in which it has been boiled should not acquire an alkaline reaction (absence of alkalis). A portion of the water when cooled and filtered, and another portion acidulated with nitric acid, should give no precipitate with nitrate of silver (absence of salt), and is not rendered blue by the addition of solution of iodine (no starch). When heated for several hours on the water-bath, under frequent stirring, lard should not diminish sensibly in weight (absence of water).

IMPURITIES.—Rancidity due to acrid fatty acids, alkalis, common salt, starch, water.

PREPARATIONS.

B.P.

Adeps Benzoatus.
Emplastrum Cantharidis.
Unguentum Hydrargyri.
Unguentum Hydrargyri Nitratis.
,, Iodi.
,, Terebinthinæ.

U.S.P.

Adeps Benzoinatus.
Ceratum Resinæ.
Unguentum.
Ceratum.
,, Camphoræ.
,, Cantharidis.
,, Extracti Cantharidis.
,, Plumbi Subacetatis.
,, Sabinæ.
Unguentum Acidi Carbolici.
,, Hydrargyri.
,, ,, Oxidi Flavi.
,, ,, ,, Rubri.
,, Mezerei.
,, Acidi Gallici.
Unguentum Acidi Tannici.
,, Belladonnæ.
,, Chrysarobini.
,, Gallæ.
,, Hydrargyri Ammoniatæ.
,, Iodi.
,, Iodoformi.
,, Plumbi Carbonatis.
,, ,, Iodidi.
,, Potassii ,,
,, Stramonii.
,, Sulphuris.
,, ,, Alkalinum.
,, Veratrinæ.
,, Zinci Oxidi.

Adeps Benzoatus, B.P.; Adeps Benzoinatus, U.S.P. BENZOATED LARD.

PREPARATION.—By mixing powdered benzoin (2 parts, U.S.P.; 2 drachms, B.P.) with melted lard (100 parts, U.S.P.; 1 lb. B.P.) and straining. The benzoin prevents the lard from becoming rancid.

PREPARATIONS.

B.P.

Unguentum Aconitinæ.
„ Atropinæ.
„ Belladonnæ.
„ Calaminæ.
„ Chrysarobini.
„ Gallæ.
„ Hydrargyri Subchloridi.
„ Iodoformi.
Unguentum Plumbi Acetatis.
„ Potassii Iodidi.
„ Sabinæ.
„ Simplex.
„ Staphysagriæ.
„ Sulphuris.
„ Zinci.

USES.—Lard is **emollient.** It is used in the preparation of ointments, and spread upon poultices to prevent them from getting dry or sticking to the surface of the body.

Order CETACEÆ.

Cetaceum, B. and U.S.P. SPERMACETI.—A peculiar concrete, fatty substance obtained from *Physeter macrocephalus*, U.S.P. Nearly pure cetine, obtained, mixed with oil, from the head of the sperm whale, *Physeter macrocephalus*, inhabiting the Pacific and Indian Oceans. It is separated from the oil by filtration and pressure, and afterwards purified, B.P.

CHARACTERS. — Crystalline, pearly-white, glistening, translucent, with little taste or odour, reducible to powder by the addition of a little rectified spirit. Scarcely unctuous to the touch; does not melt under 100° F.

PREPARATIONS.

B.P.

Unguentum Cetacei.
Charta Epispastica.

U.S.P.

Ceratum Cetacei.
Unguentum Aquæ Rosæ.

USE.—It is used as an **emollient** external application.

CLASS AVES.

Order GALLINÆ.

B.P. Ovi Albumen. EGG ALBUMEN.—The liquid white of the egg of *Gallus Banckiva*, var. *domesticus*.

CHARACTERS.—Transparent, viscid, soluble in water, coagulable on heating to 160° F. When coagulated it is opaque and insoluble in water. It is coagulated by ether.

U.S.P. TEST-SOLUTION OF ALBUMEN.—A solution, recently prepared by triturating the white of one egg with 100 cubic centimetres of distilled water, and filtering through cotton moistened with distilled water.

Ovi Vitellus, B.P.; Vitellus, U.S.P. YOLK OF EGG.—The yolk of the egg of *Gallus Banckiva*, var. *domesticus*.

PREPARATIONS.

B.P.	U.S.P.
Mistura Spiritus Vini Gallici.	Glyceritum Vitelli.

PROPERTIES. — Yellow, coagulated on heating, contains **vitellin**, also **cholesterin**, and **fats**, together with salts of calcium, &c.

B.P. Mistura Spiritus Vini Gallici.

PREPARATION.—By rubbing up the yolk of the egg with ½ oz. of fine sugar, then adding one wineglassful (2 fl. oz.) of brandy and another of cinnamon-water, and beating them all up together.

USES.—White of egg forms insoluble albuminates with a number of metals, and hence is employed as an **antidote** in cases of poisoning (especially in the cases of corrosive sublimate and sulphate of copper); in these cases the albuminates generally dissolve readily enough in the gastric juice, and therefore you must give an emetic at once.

The white and yolk of egg are useful as **nutritious** articles of diet, and in the form of egg-flip (mistura spiritus vini gallici) is much used in exhausted conditions of the system (p. 773). One case in which eggs are very useful is cancer of the rectum, since, being entirely absorbed in the alimentary canal, disturbance in the rectum is avoided. A good mixture is the white of three eggs, the yolk of two, and a quarter of a pint of beef-tea, beat up separately and then together, put in hot water until set, and given in two or three portions.

Eggs are often mixed with a little pancreatin, and administered as enemata.

CLASS PISCES.

Order STURIONES.

Isinglass, B.P.; Ichthyocolla, U.S.P. — The swimming-bladder or sound of *Acipenser Huso*, and other species of *Acipenser*.

PROPERTIES.—In fine shreds, B.P.; in separate sheets, &c., U.S.P.

COMPOSITION.—It consists of **gelatine**, which is precipitated by tannic acid.

PREPARATIONS.

B.P.	U.S.P.
Solution of Gelatine.	Emplastrum Ichthyocollæ (Court Plaster).

USES.—Gelatine baths are useful in soothing the irritation of the skin in urticaria. Gelatine is, however, chiefly used as a food in soups and in jellies for convalescents and those suffering from chronic diseases. It will not, however, supply the place of ordinary albumen as a food.

Order TELEOSTEÆ. Fam. GADIDÆ.

Oleum Morrhuæ, B. and U.S.P. Cod-Liver Oil.—A fixed oil extracted from the fresh livers of the cod, *Gadus Morrhua*, B.P. (or of other species of Gadus, U.S.P.), by the application of a heat not exceeding 180° F.

Characters.—Pale yellow, with a slight fishy odour, and bland fishy taste.

Test.—A drop of sulphuric acid added to a few drops of the oil on a porcelain slab develops a violet colour, which soon passes into a yellowish or brownish red.

Composition.—Contains **olein** (7 per cent.), **palmitin** (25 per cent.), and some **stearin**, also minute traces of **iodides**, and a peculiar substance probably allied to biliary acids.

Dose.—From 1 to 8 fl. dr.

Action.—Cod-liver oil is rather a **food** than a medicine, and its therapeutical use depends on two properties, viz. its ready absorption and its ready assimilation.

Its **ready absorption** is probably partly due to the presence of biliary matters in the oil, since oil passes more readily through a membrane when it is moistened with bile. If you take two loops of intestine and fill one with ordinary oil and the other with cod-liver oil, and replace them, the one with cod-liver oil will lose more in the same time than that containing ordinary oil.

It is **readily assimilated**, and hence it is used in all diseases where nutrition is slow, as in enlarged glands, catarrhal pneumonia, bronchitis, &c. By means of its property of stimulating nutrition, cod-liver oil improves all the functions of the body, but has no specific action on any of the organs themselves. When large quantities of the oil are taken into the stomach they cause vomiting, but if the oil be finely divided previously, it can be taken without discomfort. Hence it is advisable, when giving it in any quantity, to make it into an emulsion. Potash is sometimes used, but in the stomach the potash is probably neutralised, the emulsion decomposed, and the oil liberated. A better method is to mix it with an equal volume of mucilage of acacia and a few drops of oil of lemon ; this emulsion is not decomposed by the acid of the stomach. The oil can also be mixed with isinglass and taken as jelly. Some people take it best by putting a little salt on the tongue before, and eating a piece of bread after the oil. It is often digested if taken with a little ether, for the ether stimulates the pancreatic secretion.

The oil must not be pressed if it causes nausea or diarrhœa —for it is a food and not a medicine, and must not be given if detrimental to the appetite.

It can sometimes be taken in a single dose at bed-time, when it cannot be retained during the day. It is rarely well borne

when taken on an empty stomach, but is best retained when given not immediately after, but from half an hour to two hours after a meal. Probably the partially digested food then forms it into an emulsion.

USES.—**Externally**, cod-liver oil is a good application for the removal of scales in seborrhœa, eczema, and psoriasis. In wasting diseases of children, when it cannot be borne by the mouth, it may be rubbed into the skin twice daily.

Internally, cod-liver oil is used in all diseases arising from defective nutrition and in all scrofulous conditions (of the skin, bones, &c.), and as a food during chronic illnesses and in convalescence from acute diseases.

In children emaciated with diarrhœa, a useful mixture is vinum ferri and cod-liver oil; it must not be given in such quantities as to increase the diarrhœa. Often it will also relieve constipation in children.

Its nutritive properties are especially directed to glandular tissues; hence it is used in all cases of enlarged glands, as in tabes mesenterica.

In malnutrition of the heart, and defective circulation, it improves the condition of the heart, increases the red corpuscles, and to some extent also the white corpuscles; hence it is useful in old people with giddiness and a tendency to syncope.

It is also used in chronic rheumatism and tertiary syphilis.

It is also a tonic to the nervous system, and is of great service in cases of nervous debility consequent on hard work, worry, or acute disease. It is used in neuralgia with iron and port wine. In hysteria in middle-aged persons it is often serviceable.

In rickets it may be given alone or in combination with phosphate of calcium.

In inflammations, as bronchitis, newly developed cells are present in great abundance, but nutrition is so defective that they cannot take on the character and functions of mucous cells, and hence, in order to allow them to form a new mucous membrane, they must be supplied with a readily assimilable nutritive material; this is probably the explanation of the benefit obtained by the use of cod-liver oil in bronchitis and other diseases dependent on malnutrition.

In chronic bronchitis, with violent cough and abundant sweetish expectoration, it gives great relief.

In phthisis it is of great service, and is used in all stages of the disease except when the temperature is very high; especially is it useful in the first stage, where there is little consolidation. Under its use the patient gains flesh, keeps the disease in check, and even sometimes becomes cured.

In catarrhal conditions of other mucous membranes besides those of respiration it is very useful, as in ozæna in children recovering from measles, and in otitis after scarlet fever.

CLASS INSECTA.

Order HYMENOPTERA.

Mel, B. and U.S.P. HONEY.—A saccharine secretion deposited in the honeycomb by *Apis mellifica*, the hive-bee.

CHARACTERS.—When recently separated from the honeycomb, it is a viscid translucent liquid, of a brownish-yellow colour, which gradually becomes partially crystalline and opaque. It has a peculiar heavy odour, and a very sweet taste.

COMPOSITION.—Chiefly **glucose** and **levulose.**

IMPURITIES.—Starch, common salt, sulphates, grape sugar, and other foreign substances.

TEST.—Water boiled with it for five minutes and allowed to cool does not become blue or green with the solution of iodine (absence of starch).

If 1 part of honey be dissolved in 4 parts of water, a clear solution should result, which should not be rendered more than faintly opalescent by a few drops of test-solution of nitrate of silver (chloride), or of nitrate of barium (sulphate). If a small portion of honey be diluted with 1 volume of water and then gradually mixed with 5 volumes of absolute alcohol, it should not become more than faintly opalescent and should neither become opaque, nor deposit a slimy substance at the bottom and along the sides of the test-tube. When incinerated in small portions at a time, in a platinum crucible, it should not leave more than 0·2 per cent. of ash (any larger percentage of ash and failure to respond to the preceding tests indicating the presence of glucose or other foreign admixtures).

OFFICINAL PREPARATIONS.

B.P.	DOSE.
Mel Depuratum (melted and strained)	Ad lib.
Of Mel Depuratum—	
Mel Boracis	
Oxymel (honey 40, acetic acid 5, water 5)	1 fl. dr.–1 fl. oz.
,, Scillæ	
Confectio Piperis	
,, Scammonii	
,, Terebinthinæ	
U.S.P.	
Mel Despumatum (warmed and strained)	
Confectio Rosæ	
Mel Rosæ	

USE.—It is slightly **laxative**—chiefly used as a **vehicle.** Oxymel is the old-fashioned household remedy of honey and vinegar, and is used for colds and sore-throats.

Cera Flava, B. and U.S.P. YELLOW WAX.—The prepared honeycomb of the hive-bee, *Apis mellifica*, B.P.; a peculiar concrete substance prepared by *Apis mellifica*, U.S.P.

CHARACTERS.—Yellowish or yellowish-brown, solid, firm, breaking with a granular fracture, having an agreeable honey-like odour.

COMPOSITION.—**Cerin** and **myricin.**

IMPURITIES.—Fats, fatty acids, Japan wax, resin, soap, and paraffin.

TESTS.—B.P. Not unctuous to the touch; does not melt under 140° F. (absence of fats); yields nothing to cold rectified spirit (absence of resin), but

is entirely soluble in oil of turpentine. Boiling water in which it has been agitated, when cooled, is not rendered blue by iodine (absence of starch).

U.S.P. If 1 gm. of wax be boiled, for half an hour, with 40 gm. of solution of soda (specific gravity 1·180), the volume being preserved by the occasional addition of water, the wax should separate, on cooling, without rendering the liquid opaque, and no precipitate should be produced in the filtered liquid by hydrochloric acid (absence of fats or fatty acids, Japan wax, resin); nor should the same reagent produce a precipitate in water which has been boiled with a portion of the wax (absence of soap). If 5 gm. of wax be heated in a flask, for fifteen minutes, with 25 gm. of sulphuric acid to 160° C. (320° F.), and the mixture diluted with water, no solid, wax-like body should separate (absence of paraffin).

OFFICINAL PREPARATIONS.

B.P.	U.S.P.
Cera Alba.	Ceratum Resinæ.
Emplastrum Calefaciens.	,, Cantharidis.
,, Cantharidis.	,, Extracti Cantharidis.
,, Galbani.	,, Sabinæ.
,, Picis.	Unguentum
,, Saponis Fuscum.	,, Acidi Carbolici.
Pilula Phosphori (p. 522).	,, Mezerei.
Unguentum Cantharidis.	
,, Hydrargyri Compositum.	
,, Picis Liquidæ.	
,, Resinæ.	
,, Sabinæ.	
,, Terebinthinæ.	

USE.—To give proper consistence to **ointments.**

Cera Alba, B. and U.S.P. WHITE WAX.—Yellow wax bleached by exposure to moisture, air, and light.

CHARACTERS.—Hard, nearly white, translucent. Not unctuous to the touch; does not melt under 150° F.

OFFICINAL PREPARATIONS.

B.P.	U.S.P.
Charta Epispastica.	Ceratum.
Unguentum Cetacei.	Compound Cerates—
,, **Simplex.**	Ceratum Camphoræ.
	,, Cetacei.
	,, Plumbi Subacetatis.
	Unguentum Aquæ Rosæ.

USE.—In the preparation of the above **ointments** and **suppositories.**

Order HEMIPTERA.

Coccus, Cochineal, B. and U.S.P. The dried female of *Coccus cacti*, reared on *Opuntia cochinillifera*, and on other species of *Opuntia*. Mexico and Teneriffe.

CHARACTERS.—Ovate, plano-convex, about one-fifth of an inch (5 millimetres) long; wrinkled, of a purplish-grey or purplish-black colour; easily pulverisable, yielding a dark-red powder. Odour faint; taste slightly bitter.

COMPOSITION.—It contains a **red colouring matter** soluble in water, alcohol, or water of ammonia, slightly soluble in ether, insoluble in fixed and volatile oils.

REACTIONS.—On macerating cochineal in water, the insect swells up, but no insoluble powder should be separated. The greyish-white insect quickly becomes black when warmed before the fire.

PREPARATIONS.

B.P.	DOSE.
Tinctura Cocci (2½ oz. in 1 pint).	Ad lib.
,, Cardamomi Composita.	
,, Cinchonæ ,,	

USES.—It has little medicinal value; it is used to give an attractive colour to various liquid preparations.

Order COLEOPTERA.

Cantharis, B. and U.S.P. CANTHARIDES. SPANISH FLIES.—The beetle, *Cantharis vesicatoria*, dried. Hungary.

CHARACTERS.—From eight to ten lines long, furnished with two wing-covers of a shining metallic-green colour, under which are two membranous transparent wings; odour strong and disagreeable; powder greyish-brown, containing shining green particles. Free from mites.

COMPOSITION.—**Cantharidin**, a tasteless, inodorous substance, which may be crystallised from an alcoholic extract. It is insoluble in water and cold alcohol, although it may be extracted from the cantharides by both when in conjunction with the yellow colouring-matter. The other ingredients are unimportant.

PREPARATIONS.

B.P.	STRENGTH.	DOSE.
Acetum Cantharidis	2 oz. to 1 pint	
Charta Epispastica		
Emplastrum Calefaciens	1 part in 24, nearly	
,, **Cantharidis**	1 part in 3	
Liquor Epispasticus	1 oz. to 2½ fl. oz.	
Tinctura Cantharidis	5½ gr. to 1 fl. oz.	5–20 min.
Unguentum ,,	1 part to 7, nearly	

U.S.P.

Ceratum Cantharidis.
,, Extracti Cantharidis.
Charta Cantharidis.
Collodion cum Cantharide.
Linimentum Cantharidis (p. 517).
Tinctura Cantharidis.

ACTION.—**Externally** the preparations of cantharides produce, when applied to the skin, tingling, redness, and vesication; if the action is prolonged, the vesicles coalesce into a large bleb filled with serum, and if left on too long the true skin becomes irritated, and suppuration, ulceration, and even sloughing occur.

Internally the drug causes irritation of the alimentary canal, with a feeling of warmth in the mouth, œsophagus, and stomach, loss of appetite, and (if its use be prolonged, or if a single large dose be given) burning and pain in the stomach (increased by

pressure), nausea, vomiting, and diarrhœa (the vomited and ejected matters often being mixed with blood).

It affects the trachea and larger bronchi, causing congestion and irritation.

It affects the kidneys and urinary passages, causing pain in the loins, burning in the bladder and along the urethra, irritation of the glans penis, and sometimes increased sexual appetite. If continued for a long time, it causes great pain in the kidneys, painful erections of the penis, difficulty of micturition or suppression of urine, the latter often containing albumen or blood.

The nervous system is usually not affected by small doses, but large doses cause headache and quickened pulse and respiration.

Very large doses produce insensibility, paralysis of respiration, and death with asphyxial convulsions.

The salivary glands and the back of the throat become so much swollen that swallowing is difficult, and the attempt to swallow may give rise to convulsions, like hydrophobia.

Urinary Organs.—The inflammation caused by cantharides begins in the glomeruli, and not in the straight tubes as is often stated.

The first condition of the kidneys noticed after the administration of cantharides is extravasation of leucocytes into the glomeruli and an exudation of a fibrinous matrix; next, following in order, we notice:—

(1) The glomeruli and the proximate tubules are filled with a granular fluid.

(2) The cells of the capsule become swollen.

(3) The cells of the collecting tubes are affected, and become swollen.

(4) The cells of the whole urinary tubule become swollen.

(5) In the straight collecting tubes the cells become multiplied, and are thrown off so that the lumen becomes full of exuded cells.

Treatment in Poisoning.—Evacuate the stomach, give mucilaginous drinks to lessen the gastro-intestinal irritation, but avoid oils or fats, which increase the solubility of cantharidin and the dangers arising from its absorption. Use opium and sitz-baths to relieve the strangury.

USES.—It is used externally as an irritant and counter-irritant, and internally for its effect on the genito-urinary tract.

Externally as irritant—

(1) To increase the supply of blood to a part, and hence improve its nutrition, as in chronic ulcers in the leg.

(2) To cause disappearance of inflammatory products in chronic inflamed joints and swellings; also in acutely inflamed

joints, as in acute rheumatism, in the form of a blister above and below the joint. In chronic rheumatism a large and strong blister should be used.

As **counter-irritant** it is used in pleurisy and pneumonia, and often relieves the pain almost immediately.

It is also used in acute inflammation of the heart and pericardium. It is better not to apply the blister directly over the affected part, but a little to one side, since there is a risk of getting the vessels just underneath it congested instead of anæmic.

In affections of other serous membranes, as in meningitis, and often in inflammation of the brain itself, the application of a blister is very useful.




FIG. 226.—Diagram of the body showing some of the points where blisters or sinapisms are usually applied. Front view.

When applied to the nape of the neck, it often relieves giddiness and disturbed cerebral functions dependent on tertiary syphilis, diseases of the ear, or of the semicircular canals.

It is occasionally useful to keep up the irritation by means of savine ointment applied to the blistered surface.

It is also locally applied to the perineum in inflammation of

the prostate, and over the tender region in inflammation of the ovary.

A blister sometimes relieves the pain of sciatica and the tenderness of nerves in peripheral paralysis; and a blister the size of a shilling may be applied over each tender spot in these diseases. In sciatica a row of such small blisters, or a long narrow blister along the course of the nerve, is sometimes better than single small blisters. A blister is a useful application applied under the ear in paralysis of the facial nerve due to cold.

Internally, in small doses of 1 or 2 min. of tincture, it checks hæmaturia; in larger doses it increases the disease.

In Bright's disease, after the acute stage has passed, but a little albumen and blood still remain in the urine, it is very useful in doses of 1–3 min. every three hours.




FIG. 227.—Diagram, like Fig. 226. Back view.

In cystitis, especially where there is inability to retain the urine, and also in ordinary incontinence of urine, it is useful; though in both cases atropine generally acts better.

A drop of tincture three times a day will often relieve chordee.

Precautions. — (1) Do not use the blisters on debilitated persons, and children; or do not keep them on long, but just sufficient to start the blister, and then, after two or three hours, put on a poultice to make the blister rise.

(2) Be careful of its use both externally and internally in Bright's disease.

Class ANNELIDA.

B.P. Hirudo. The Leech.—(1) *Sanguisuga medicinalis*, the speckled leech; (2) *S. officinalis*, the green leech. Collected in Spain, France, Italy, and Hungary.

Characters.—Body elongated, two or three inches long, tapering at each end, plano-convex, wrinkled transversely; back olive-green with six rusty-red longitudinal stripes. (1) Belly greenish-yellow, spotted with black; (2) belly olive-green, not spotted.

Action.—At the anterior extremity the leech has a sucking disc, in the middle of which is a triradiate mouth furnished with sharp teeth. Fixing itself to the surface by its disc, it saws through the skin and sucks the blood. This process is facilitated by the power of destroying the coagulability of the blood which the secretion from the pharynx of the leech possesses (Haycraft). This secretion is probably the cause of the ecchymoses which frequently occur at the bites as well as of the persistent hæmorrhage they sometimes occasion.

Uses.—Leeches may be employed as a substitute for general blood-letting in women and children. They are more generally employed for the purpose of local depletion in inflammation. The irritation occasioned by the bites has probably a certain counter-irritant action (p. 341), but the relief they afford is chiefly due to the depletion. They are useful in bruises, fractures, inflamed joints, meningitis, otitis, ophthalmia, persistent headache, laryngitis, pleurisy, pneumonia, pericarditis, hepatitis, orchitis, and hæmorrhoids.

Application.—Each leech draws on an average about one and a half fluid drachm of blood. By applying fomentations afterwards, as much again, or even more, may be withdrawn. Care should be taken that leeches which have been applied to anyone suffering from an infective disease should not be used again, lest they convey the virus. When they are to be applied to a mucous membrane, such as the tonsil, they should be put in a leech-glass. This is a small syringe large enough to hold a leech. The head of the animal is introduced first, and the body gently pushed down with a piston. The nozzle of the leech-glass is large enough to allow the head of the animal to protrude, but not to allow the body to follow.

Leeches may be applied to the skin by simply confining them to the spot with a pill-box; or a piece of blotting-paper, with

holes in it at the points where we wish the leeches to fix, may be laid on the skin, and the leeches kept over this by a wine-glass or tumbler. It is sometimes difficult to make leeches bite. The skin should be carefully washed, and thoroughly dried and warmed, and, if necessary, shaved. The room should be well ventilated and free from tobacco-smoke, and from the fumes of vinegar or disinfectants. Leeches should be dried in a soft warm cloth and then applied. If a single one is to be used, the body may simply be held in the cloth, and the head allowed to reach the skin. A slight movement of withdrawal being now made, the leech will probably fix. Care should be taken not to withdraw it so strongly as to tear it from its hold. When difficulty is still experienced in making the leeches bite, a little warm milk, sweetened with sugar, may be rubbed over the skin, or a drop of blood extracted from the finger by a needle may be used for the same purpose. Usually leeches fall off when they are full, but if they do not they can be detached by sprinkling salt over them. If it is desirable to encourage the bleeding, warm fomentations, poultices, or cupping-glasses may be employed. The bleeding may be stopped by applying a small piece of absorbent cotton-wool, or of lint rolled into a hard cone and fixed over the bite with a compress and bandage. Cobwebs used in the same manner are very efficacious. If these are insufficient, a piece of absorbent cotton-wool dipped in strong solution of perchloride of iron and dried, or the styptic collodion of the U.S.P., may be applied. When other means fail a pointed stick of nitrate of silver may be pushed into the bite, or the bite may be transfixed with a needle and a silk thread passed in a figure-of-8 around it. If possible, leeches should not be applied at night, especially to feeble individuals or children, unless the patients are carefully watched, as, if hæmorrhage from the bite should occur, it might not be noticed until much blood had been lost. Leeches should not be applied over loose cellular tissues where pressure cannot be applied. In inflammation of the eyes they should be applied to the temples, and not to the eyelids; and in inflammation of the testicles to the perineum, and not to the scrotum. As the marks of the bites are permanent, care should be taken to apply leeches, if possible, where the marks will not appear. Thus, in applying them to the temples the hair may be shaved off a spot and the leeches applied. When the hair grows the marks will be hidden. In applying them to the chest in girls they should, if possible, be placed so low down that the marks will not be seen when evening dress is worn.

If leeches should get into any mucous cavity—nose, stomach, or rectum—they may be dislodged by the injection of strong brine.

APPENDIX.

Methylal. Methylenedimethyl Ether. $CH_2(OCH_3)_2$. Not officinal.

Characters.—A mobile, colourless, volatile liquid, boiling at 42° C.; sp. gr. 0·8551. Odour like chloroform and acetic ether, with a burning aromatic taste.

Preparation.—By distilling methyl alcohol with an oxidising mixture of dioxide of manganese and sulphuric acid, and adding potash to the distillate to separate methyl formate.



Dose.—1 gramme (15 gr.).

Action and Use.—It is a local **anæsthetic.** It produces in dogs anæsthesia, followed by deep sleep. It is rapidly eliminated, and is said not to produce any bad after-effects. It is recommended as a local anæsthetic to the skin, and as an analgesic to the stomach; but as yet it has not been much employed.

Urethane. Ethyl Carbamate. Not officinal.

Urethane is a general term for the ethereal salts of carbamic acid; but ethyl carbamate is the most important of them, so it is usually called *par excellence* urethane, just as ethylic ether is usually called simply ether.

Carbamic acid, $CO.NH_2.OH$, or $\begin{matrix} O- \\ | \\ -C-O-H \\ | \\ NH_2 \end{matrix}$, is not known in the free state. Its ammonium salt forms an important constituent of the officinal ammonium carbonate. The general formula for the salts of carbamic acid is $\begin{matrix} O- \\ | \\ -C-O-(R') \\ | \\ NH_2 \end{matrix}$ and of ethyl carbamate, (urethane) $\begin{matrix} O- \\ | \\ -C-O-(C_2H_5) \\ | \\ NH_2 \end{matrix}$. Ammonium

carbamate is , and its relationship, as well as that of urethanes, to urea is seen by referring to its rational formula,  (see p. 636).

PREPARATION.—From commercial ethyl chlorocarbonate, by adding solution of ammonia, which converts it into ethyl carbamate (urethane). This is removed by ether, which, with the water, is then distilled off. The urethane which remains is purified by distilling, and then dried over sulphuric acid.

DOSE.—4–8 gr., repeated; or 15–30 gr., or more, in one dose.

ACTION.—The value of this drug and, though to a less extent, of other urethanes as a hypnotic was discovered by Schmiedeberg, from the consideration that the alcohol radical in it ought to exert a sedative or paralysing action on the cerebrum (p. 764); while the amidogen in it ought to have a somewhat stimulating action on the medulla and cord (p. 602). It ought, therefore, to have a soporific action, like chloral, and yet be free from the danger of paralysing the respiratory centre or heart.

In **frogs**, doses of 20 to 30 milligrammes cause a condition in which the animals are very readily hypnotised without affecting the respiration or co-ordination of movement. Larger doses diminish voluntary motion without affecting reflex excitability, which is, however, paralysed by still larger doses.

In **warm-blooded animals**, the same symptoms are produced; and may be ascribed to a blunting of the functions of the cerebral hemispheres, diminution of voluntary motion, and of the perception of sensory stimuli, ending in deep narcosis. In dogs, urethane causes a staggering gait, and, in large doses, vomiting. Urethane stimulates the respiration and, unlike chloral, does not diminish the blood-pressure or affect the heart.[1]


USES.—Urethane is a pure **hypnotic**, and may be used instead of bromide of potassium and chloral in those cases in which, from overwork, worry or other cause, there is an inability to sleep (p. 199). Urethane produces the necessary tranquillity conducive to normal sleep. It is best given in small doses frequently repeated (4 gr.), as vomiting may occur from large doses. It has the advantage over chloral of not affecting the circulation and stimulating, instead of depressing, the respiration. It may be given in cases of heart-disease and of Bright's

[1] Schmiedeberg, *Pract.*, vol. xxxv., p. 275.


disease. When the tension is high, however, it may be less active than chloral, as it does not lessen the tension like chloral, and thus does not reduce the flow of blood through the brain. It is an **antidote** to strychnine.

Iodol. TETRAIODPYRROL. C_4I_4NH. Not officinal.

Pyrrol.



Iodol.



CHARACTERS.—Light brown tasteless crystalline powder, with a faint smell somewhat like thymol.

SOLUBILITY.—Insoluble in water, soluble in 3 parts of alcohol, readily soluble in ether and chloroform, sparingly soluble in oils by means of warmth. Glycerine may be added to the alcoholic solution without causing a precipitate.

ACTION.—Like iodoform (p. 805). It may be given internally, in doses of 3 grains daily, without causing any irritation of the intestinal canal.

USE.—It is useful as a dressing in venereal sores, adenitis and periadenitis. It may be applied as a powder, sprinkled over the surface of the sore, or suspended in glycerine, dissolved in spirit, or as an ointment.

Strophanthus hispidus. [*Kombé, Inée.*] Not officinal. A plant belonging to the natural order *Apocynaceæ*, and the seeds of which are used in Africa as an arrow-poison.

DESCRIPTION.—The ripe follicles are 9 to 12 inches long and enclose 100 to 200 seeds, which contain the greatest proportion of the active principle. The seeds are oval, and are readily recognised by their comose appendages.

COMPOSITION.—The active principle is **strophanthin**, of which the seeds contain from 8 to 10 per cent. It is a crystalline glucoside, with a strongly bitter taste and a slightly acid reaction; readily soluble in water and rectified spirit, practically insoluble in ether, chloroform, benzene, and petroleum spirit. It yields, on heating with sulphuric acid, glucose and an insoluble body, strophanthidin.

PREPARATIONS.

	DOSE.
Tinctura Strophanthi (1 in 20 [1])	5–10 min. or ½ to 2 min. frequently repeated.
Strophanthin	$\frac{1}{120}$–$\frac{1}{60}$ gr. hypodermically.

[1] A stronger tincture, 1 in 8, corresponding to the tincture of digitalis, has been chiefly used hitherto; but a tincture 1 in 20 is recommended by Fraser, and a formula for preparing it is given by him in the *British Medical Journal*, Jan. 22, 1887, p. 151.

Action and Uses.—Strophanthin, according to Fraser, is a **muscle-poison**, increasing primarily the contractile power of all striated muscles; the contraction becoming more complete and prolonged. It is a **cardiac tonic** (p. 331), increasing the length of the systole, and slowing the rhythm, acting like digitalis and producing a similar standstill in systole. Its action on the heart is much more powerful than that of digitalis. Strophanthus causes a rise of blood-pressure, due chiefly to the heart, since it does not produce so marked a contraction of arterioles as digitalis. In the normal animal it is sometimes **diuretic** (p. 432) and **antipyretic**. Strophanthus has been used as a tincture in cases of cardiac disease similar to those in which digitalis is serviceable. It is most beneficial in cases of mitral disease with great anasarca, in which it reduces the frequency of the pulse and makes it regular, while producing great diuresis. Strophanthin, hypodermically, acts in a similar manner. Strophanthus is said not to cause great sickness or gastro-intestinal irritation, and to have no cumulative effect. The exact utility of the drug has, however, not yet been determined, as it has not been sufficiently tried in cases of heart-disease.

Dead Space.—This name has been given by O. Liebreich to the part of a fluid in which no reaction occurs between substances dissolved in it. Chloral hydrate and sodium carbonate in solution decompose each other, chloroform and sodium formate




Fig. 228.—Diagram showing the dead space and space of reaction in a mixture of solutions of chloral hydrate and sodium carbonate.

being produced, but this reaction does not occur equally throughout the whole solution. If the solution be mixed in a test-tube the fluid will be seen to become milky, from the formation of minute globules of chloroform; but just below the surface of the fluid this reaction does not occur, and a clear space is observed, a section of which has a bi-concave formation, as it is bounded above by the concave level of the fluid and below by the convex surface of that part of the liquid in which no action occurs.

If the mixture is placed in horizontal capillary tubes, the

dead space in which no reaction occurs is at each end of the liquid; if the entire length of the column of liquid in the tube is shorter than the combined length of the two dead spaces no reaction occurs at all. This absence of reaction renders it probable that the chemical processes which occur in the confined space of a living cell may be very different from those in an ordinary test-tube, on account of the difference in physical conditions as well as from the complex phenomena which we are




FIG. 229.—Diagram showing the two dead spaces in a capillary tube.

accustomed to class as vital. The same absence of reaction in certain parts of a liquid can be observed with other mixtures, and a convenient one for demonstration is a mixture of iodic acid, sulphurous acid, and starch. When these substances are mixed, iodine is set free, and an intense blue colour produced. If they are mixed in a large beaker the reaction occurs more quickly than if they are contained in a narrow glass tube. In a tube also it can be seen that the reaction begins in the centre, so



FIG. 230.—Diagram showing the absence of reaction in a capillary tube where the column of liquid is shorter than the length of the two dead spaces in a tube of that size.

that occasionally one may notice a blue thread occupying the centre of the liquid, while that part of it which lies adjacent to the walls of the tube is still colourless. When a series of vesicles made of membranes such as calves' peritoneum are filled with the mixture just mentioned, it can be seen that the reaction occurs quicker in the larger spheres, and that it generally begins in the centre of the fluid. When one vesicle is contracted in the centre by a ligature, so as to form two smaller vesicles connected with each other, two centres of reaction may be frequently observed instead of one. Although this discovery has not yet been fully worked out, it promises to have a most important bearing on our ideas regarding the action of drugs in living tissues.

GENERAL INDEX.

A.

ABDOMEN, mustard stupes or poultices applied to the lower part of the, act as indirect emmenagogues, 453
Abernethy, Mr., reference to, 689
Abney and Festing, reference to, 28
Abortion, emetics to be avoided where a tendency to, exists, 376; the twigs of thuja may produce, 1063
Abscesses, especially of the liver, caustics employed to open, 346
Absinthe, as a spinal stimulant, 181; action of, on the brain of dogs, 188
Absorption and excretion of drugs, diagrams illustrative of, 39 and 40; effects of rapid or delayed, 39
Abstracts, 503
Abstractum Aconiti, 503, 832
  Belladonnæ, 503
  Conii, 503, 931
  Digitalis, 503, 994
  Hyoscyami, 503, 990
  Ignatiæ, 503, 971
  Jalapæ, 503, 982
  Nucis Vomicæ, 503, 971
  Podophylli, 503, 838
  Senegæ, 503, 868
  Valerianæ, 503, 952
Acetate of aluminium, action of, on enzymes, 78; on bacteria, 91
  Ammonium, as a vascular stimulant, 330
  Copper, 674
  Ethyl, 783
  Lead, 703
  Morphine, 847
  Potassium, 609
  Sodium, 624
  Zinc, 672
Acetates, test for, 594
Acetic acid, action of, on bacteria, 94; of the vapour of, on the general circulation, 194; action of, on the respiratory mucous membrane, 253; as a vesicant, 344; as a caustic, 344; as a poison with its antidotes, 487; properties and uses of, &c., 576; preparations containing, 577; glacial ditto, 577
Acetone, action of, on bacteria, 93, 95
Acetum, 503, 578
  Cantharidis, 503, 577, 1091
  Lobeliæ, 503, 961
  Opii, 503, 845
  Sanguinariæ, 503, 863
  Scillæ, 503, 577, 1041
Acid Bath, the, 469
  Dilute nitro-hydrochloric, as a hepatic stimulant, 403
  Ergotinic, 1070
  Hæmatin, 72
  Radicals in metallic salts, general tests for, 593; list of tests for the different acids, 594, 595
  Solution of nitrate of mercury, 695
  Sphacelinic, 1070
  Tartrate of potassium, 610
Acidity, corrected by antacids, 369
Acids, action of, on the secretion of the respiratory mucous membrane, 253; as stimulating expectorants, 255; action of dilute, on the frog's heart, 307; on the capillaries, 280, 318, 337; as caustics, 344; as astringents, 349; as styptics, 350; as sialagogues, 357; as artificial digestive substances, 364; action of, as irritant poisons, 395; strong, may produce death weeks after they have been swallowed, 398; as antihidrotics, 441; as poisons, with their antidotes, 487; general characters and properties of, 565; general action of, on the tissues, 567; on the skin, 568; in the mouth, 568; in the stomach, 569; on the bile and liver, 570; morbid anatomy of poisoning by, 570
Acids, mineral, action of, on albumen, 58; on protoplasm, 60; on infusoria, 65; as sialagogues, 356
Acids, physiological action of—
  Arsenic, 27
  Bromic, 27
  Hydriodic, 27
  Hydrochloric, 27
  Iodic, 27
  Phosphoric, 27

Acids, physiological action of—
Selenic, 27
Sulphuric, 27
Acids, preparation, properties, action, and uses of—
Acetic, 566, 576
Glacial, 566, 577
Arsenious, 567
Benzoic, 567
Boracic or boric, 566, 581
Carbolic, 567
Carbonic, 566, 583
Chromic, 582
Citric, 566, 580
Dilute hydrobromic, 567
Hydrocyanic, 566, 586
Phosphoric, 567, 579
Gallic, 567, 1033
Hydrochloric, or muriatic, 566, 572
Lactic, 589
Nitric, 566, 574
Nitro-hydrochloric, 575
Dilute, 575
Oleic, 567, 590
Oxalic, 567, 581
Phosphoric, 516, 579
Salicylic, 567, 819
Sulphuric, 567, 570
Aromatic, 571
Dilute, 571
Sulphurous, 567, 571
Tannic, 567, 1031
Tartaric, 566, 580
Vinegar, 578
Acidum Aceticum, 576
Dilutum, 577
Glaciale, 577
Arseniosum, 719
Benzoicum, 964
Carbolicum, 813
Crudum, 812
Liquefactum, 813
Chrysophanicum, 895, 909
Gallicum, 1031
Hydriodicum (syrupus), 574
Hydrobromicum Dilutum, 573
Hydrochloricum, 572
Dilutum, 573
Hydrocyanicum Dilutum, 586
Meconicum, 846
Nitricum Dilutum, 575
Nitro-hydrochloricum, 575
Dilutum, 573, 575
Phosphoricum, 579
Pyrogallicum, 819
Salicylicum, 819
Sulphuricum aromaticum, 571, 1017
Dilutum, 571
Tannicum, 1031
Tartaricum, 580, 610
Aconite leaves, 831; root, 831
Aconitine or Aconitia, action of, on oxidation, 70; effects of, on muscle, 158; as a sedative, 157; as an anodyne, 201, 203; action of, on the respiratory centre, 233, 241; on the vagus-roots, 296; on the vagus-centre, 317; on the heart, 339; Ringer's mode of using, 339; as a poison, with its antidote, 488; antagonism of, to other drugs, 495; preparation, characters, and tests of, 832; general action of, in frogs, 832; in man, 833; on the heart, 833; action of, on individual organs, 833; on the muscles, motor and sensory nerves, 833, 834; on the spinal cord, brain, and vaso-motor centre, 833, 834; on the heart and respiration, 834; on the temperature, the stomach, and the secretion of the salivary gland, 834; on the pupil of the eye and the tissues, 834, 835; therapeutic use of, locally, 835; for the stomach, in febrile conditions, in cardiac disease, and on the nervous system, 835; mode of application, 835
Aconitum, properties, composition, and preparation of, 831
Actual cautery, as a styptic, 350
Adami, reference to, 424
Adeps benzoatus, 964, 1084
Benzoinatus, 964, 1084
Adonidin, as a cardiac tonic, 331
Adonis vernalis, as a cardiac tonic, 331; as a refrigerant diuretic, 432, composition, action, and use of, 837
Aeby, reference to, 131
Æther purus, 780
Agaricus albus, as an antihidrotic, 441, action and uses, 1068
Ague, utility of quinine in, 1; produced by the *bacillus malariæ*, 99; importance of emetics and purgatives in aiding the action of antiperiodics in the cure of, 108; value of emetics in, before the administration of quinine, 375; sometimes cured by emetics alone, without quinine, 375; action of opium in, 862; brought on by strychnine, 974
Air-baths, 471
Air-passages, value of emetics in removing obstructions from the, 375
Albertoni, reference to, 187
Albumen, nature of, and action of drugs on, 57; effects of acids and organic alkaloids on, 58; action of quinine on, 944; test solution of, 1085; albumen of eggs, 1085
Albuminous solutions, action of alcohol on, 767
Albuminuria, action of drugs on, 434; how far caused in apparently healthy persons by mercurials, 665
Alchemilla, action of, on the bladder, 445
Alcohol, effects of, on the blood, 72; change undergone by, when boiled with sulphuric acid, 73; action of, on

enzymes, 79; on bacteria, 91, 93, 95; appears to arrest the action of zymotic diseases, 103; and preserves animal matter, 103; action of, on medusæ, 111; on annulosa, 115; on muscles, 128; general nervous system, 146; as a spinal depressant, 165; on the brain of the lower animals, 187; on psychical processes, 192; a typical stimulant on the action of the brain, 195; different action of, in different doses, on the brain, 195; has both stimulant and narcotic action on the brain, 200; as an antispasmodic, 213; action of, on frogs, 215; on the respiratory centre, 241; on the vaso-motor centre, 287; on the motor ganglia, 316; as a cardiac stimulant, 328; as a vascular stimulant, 330; as a rubefacient, 344; as an astringent, 349; as a local sedative, 376; as an antipyretic, 421; as a stimulant diuretic, 433; as an aphrodisiac, 450; as a poison with its antidote, 488; antagonism of, to strychnine, 495

Alcohol, 775
- Absolute, 775
- Amylic, 777
- Diluted, 776
- Ethylicum, 766, 775
- Proof spirit, 776
- Rectified spirit, 776
- Red wine, 777
- Sherry, 776
- Spirit of French wine, 776
- White wine, 777; stronger, 777

Alcohol, ethyl, general source and preparation of, 766; impurities and tests of, 766, 767; general action of, 767; on albuminous solutions, 767; on the skin, mouth, stomach, intestine, and blood, 767; and tissues, 767; dispute as to whether it can be regarded as a food, 767; its action on the circulation and temperature, 768; on the nervous system, 769; and cranial circulation, 769; on the nervous tissues, on the judgment and emotions, 769, 770; on the motor centres, the speech, and the cerebellum, 770; on the spinal cord, the respiratory centre, the vaso-motor centre, and the heart, 770; the importance of a proper diagnosis of drunkenness from effects of opium and apoplexy, 770; effect of impurities on the action of, 770; effects of chronic poisoning by, 770; on the bowels, skin, liver, kidneys, and nervous system, 771; nature and effects of delirium tremens, 771; and treatment of, 772; causes of chronic alcoholism, 772; uses of, 773; its weakness as a stimulant compared with beef-tea, 774; action of, as a stimulant, 774; and on the urine, 775

Alcohol, methyl, preparation, characters, and uses of, 766

Alcoholism, causes of chronic, 772

Alcohols, list of the principal, with their respective toxic powers, 764, 765; action of, on the general system, 764 *et seq.*

Aldehydes, properties, action, uses of—acetic aldehyde, 778: and paraldehyde, 778

Alder, black, 894

Ale, intoxicating effects of a single glass of, when sucked through a straw, 194

Algæ, 1073

Alimentary canal, action of quinine on the, 945; of sulphate of strychnine on the, 973; of tobacco, 992; of extract of ergot, 1071

Alkalies, action of, on protoplasm, 60; on infusoria, 65; on muscle, 135 *et seq.*; on the secretions of mucus from the trachea, 252; on the amount and nature of moist *râles* in the lungs, 252; as a depressant expectorant, 255; dilute, on the frog's heart, 306; on the capillaries, 318; as caustics, 344; as sialagogues, 357; arrest secretion of saliva, 361; dilute, increase the action of the gastric juice, 363; strong, may produce death weeks after it has been swallowed, 398; as poisons with their antidotes, 487

Alkalis, metals of the, 596; (1) alkaline salts, general characters and reactions of the, 597; their physiological action, 597; and general action, 597; on the skin, as caustics, rubefacients, and vesicants, 597, 598; in the mouth, 598; in the stomach, 598; on the gastric juice, 598; as antidotes in poisoning by acids, metals, and alkaloids, 599; their action on the blood, 599; as alteratives, diuretics, and antacids, 599; (2) general action of the group of chlorides, 599; on the stomach and other parts of the body, 600, 601; (3) general action of the sub-group of sulphates, 602; comparative action of the alkaline metals, 602

Alkaline bath, 470
- Bromides, as antispasmodics, 214
- Hæmatin, 72
- Sulphur ointment, constituents of, 544

Alkaloids, action of, on the general system, 32; on albumen, 58; on protoplasm, 61; on bacteria, 89; formed by putrefaction, 99; Albertoni's investigations as to the action of the coto, 386; antidotes to, 488; objection to the extremely small doses of, required to produce marked physiological action, 492; antagonistic action of certain, to

morphine, 494, 495; nature of, 503; properties and reactions, 504; of opium, 858
Alkaloids, cinchona, and their salts, 944
of opium, action of the, 858
Allspice and oil, as carminatives, 379
Oil of, 923
Allyl alcohol, action of, on bacteria, 95; extraordinary effect of, 102; *vide* also 1040
Almond, bitter, 915
Oil of, 916
Oil, as a demulcent, 347; nature of, 916
Oil of, expressed, 916
Aloes, as a purgative, 389; as a cholagogue, 390; as a hepatic stimulant, 403; characters, preparations containing, and composition of, 1041–1044
Barbadoes, 1043; action of, in the mouth, the intestines, and the rectum, 1044; on the bile and the uterus, 1044; as an aphrodisiac and a purgative, 1044
Purified (Purificata), 1043
Socotrine, 1041
Aloin, 505; nature and action of, 1043, 1044
Alteratives, nature of, 413; list of the principal, 413; action of, 413–415; uses of, 415; alkalies as, 599; lappa as, 960; solanine as, 984; rumex as, 1011; phytolacca root as, 1009; stillingia as, 1023; sarsaparilla as, 1052
Althæa (marsh-mallow), characters, composition, and uses of, 875; a useful demulcent, 347, 875
Alum, action of, on bacteria, 94; on the mucous membranes, 288; as a caustic, 344; as an astringent, 349; as a styptic, 350; as a local emetic, 373; as a local sedative, 376; as a vermicide, 408; action of, on the skin, 655; as an astringent, 655; as a styptic, 655; a caustic, and an emetic, 655; properties, action, and uses of, 654–656; of dried ditto, 655
Aluminium, symbol and atomic weight of, 9; physiological action of, 27; action of, on the mouth and stomach, 568, 569; general sources, reactions, &c., of the salts of, 654; hydrate of, 656; sulphate of, 656
Amanita muscaria, as an antihidrotic, 441
Amber, oil of, action and uses of, 1060
American cannabis, 1026
Wormseed. *See* Chenopodium
Ammonia, nature of, and changes it undergoes, 15; physiological action of, 27; action of, on bacteria, 93; on the muscles, 126 *et seq.*; as a spinal stimulant, 181; stimulating effects of the vapour of strong, and of carbonate of, on the general circulation, 194; action of, on the ear, 229; on the respiratory centre, 240; and movements, 244; of strong liquor of, on the secretion of the mucous membranes, 253; as a stimulating expectorant, 255; carbonate of, as an emetic in chronic bronchitis, 255; action of, on the vagus-centre, 317; on the accelerating centre, 318; action of salts of, on the vasomotor centre, 319; as a cardiac stimulant, 328; as a rubefacient, 344; aromatic spirit of, as a direct antacid, 370; action of, on the uterus, 454; vapour of, as a poison, with its antidote, 486
Ammonia, character, action, and uses of—
Aromatic spirit of, 641
Spirit of, 639
Water of, 640; stronger, 638
Ammonium, Acetate of, 641
Benzoate of, 643
Bromide of, 556
Carbonate of, 640
Chloride of, 637
Citrate of, 712
Iodide of, 664
Solution of acetate of, 641
Solution of citrate of, 642
Sulphate of, 642
Sulphide of, 643
Valerianate of, 643
Ammoniac, 933
Ammoniacum, as an antispasmodic, 214; characters and uses of, 934
Ammonias, compound, action on general nervous system, 144; action on muscle, 636
Ammoniated mercury, 694
Ammonii benzoas, 563, 964
Iodidum, 557
Phosphas, 642
Ammonio-ferric sulphate, or ammonio-ferric alum, 749
Ammonium, sulphate of iron and, 749
Benzoate, as a hepatic stimulant, 403
Bromide, action of, on the spinal cord, 173
Carbonate, as a cardiac stimulant, 328; as a direct antacid, 370; as a local emetic, 373
Chloride, action of, on bacteria, 93; on muscle, 127 *et seq.*; on the ear, 229; as a stimulating expectorant, 255; antagonism of, to chloral, 495; character, action, and uses of, 637; on the liver, 638
Nitrate of, 642
Phosphate of, 642
Salts, characteristics of, 633; sources, reactions, and preparations of, 634; impurities, tests of, 634; action of,

636; figure showing the paralysing action of ammonium sulphate on muscle, 636
Sulphide, action of, on bacteria, 94
Amœbæ, nature of, action of drugs on, and method of experimenting on, 59 *et seq.*; an amœba, figured at two different periods during movement, 74; struggle for life between the, and bacilli, 84; the protoplasm of, contracts in any direction, 117; anæsthetics act as poisons to, 206
Amphioxus, mechanism of respiration in the, 232; diagram of an, 233
Amygdala, 915
Amylamine, action on muscle, 636
Amyl nitris, 784
Amyl, nitrite of, use of, in diminishing tension and removing pain in angina pectoris, 4; difference of action of, in different animals, 54; action of, on blood, 71; action of, on medusæ, 111; on psychical processes, 191; on the dog and rabbit, 288; as a poison, with its antidote, 490; antagonism of, to strychnine, 492; preparation, characters, and tests of, 784, 785; physiological action of, 785; on the blood, blood-pressure, respiration, and pulse, 785; on the muscles and motor nerves, 786; on the nervous system and urine, 786; uses of, 786; as a remedy in spasmodic conditions, 786; in angina pectoris, headache, &c., 786; pulse-tracings illustrative of the action of, in angina pectoris, 787; in epilepsy and ague, considerations regarding the administration of, 788
Amylum iodatum, 1053
Amyridaceæ, 893
Anacardiæ, 897
Anæmia, causes functional inactivity of the cerebro-spinal system, 197; loss of albumen through the kidneys, and deficiency of fatty food cause of, 412; a deficiency of iron in the blood in, 412
Anæsthesia, various modes of inducing, 204, 205; may be caused by the direct action of drugs on the nerve-cells, 205; dangers arising from the efforts to induce, 207; action of, and mode of using in animals, 210; history of the discovery of, 211
Anæsthetics, nature and uses of, 157, 203, action of, on the motor centres of the brain, 187; difference between anodynes and, 203; divided into local and general, 204; chief local and general, 204-205; usual action of general anæsthetics, 205; the action of, divided into four stages—the stimulant, 206; the narcotic, 206; the anæsthetic, 207; and the paralytic stage, 207; uses of, 207; dangers of, 207, 208; mode of administering, 209; action of on, and mode of using in, animals, 210; history of the discovery of the uses of, 211; action of, on the eye, 219; may obstruct respiration, 238; fallacies from, in ascertaining the action of drugs on the circulation, 269; action of, on the motor ganglia, 316; as poisons, with their antidotes, 488; iodide of ethyl as an anæsthetic, 790; iodoform as, 805; erythroxylon and hydrochlorate of cocaine as, 878
Analgesics. *See* Anodynes
Anaphrodisiacs, nature and action of, 447–452; diagrams illustrating the action of, 448, 449; general considerations regarding, 451–452; camphor as an, 1019
Anemonin, 836
Aneurism, emetics to be avoided in persons suffering from, 375
Angina pectoris, 4; nitrite of amyl diminishes tension and removes pain in, 4
Aniline red, 822
Sulphate, action of, on the cardiac muscle, 316
Animal charcoal, 542; purified, 542
Animal kingdom, 1077–1096; class mammalia, order rodentia, 1077; order ruminantia, 1077; order pachydermata, 1084; order cetacea, 1085; class aves, order gallinæ, 1085; class pisces, order sturiones, 1086; order teleosteæ, family gadidæ, 1087; class insecta, order hymenoptera, 1089; order hemiptera, 1090; order coleoptera, 1091; class annelida, 1095
Animals, utility of, for experiments in medicine, 51–56
Anise, character of, 935; oil of, 840, 935; as a carminative, 379, 935
Anise fruit, character of, and preparations, 935
Annelida, 1095
Annulosa, action of drugs on, 114
Anodynes, two classes of, local and general, 201; nature, action, and uses of, 201–202; adjuncts to, 203
Antacids, nature and action of, 369; divided into direct and indirect, or remote, 369; action of alkalies as, 598; slaked lime as an antacid, 649
Antagonistic action of drugs, 492–496
Anthelmintics, nature of, 408; divided into two kinds, 408; list of the chief, 408; adjuncts to, 408; uses of, 409; benzin as an, 762; azedarach as, 894; kousso as a, 921; pomegranate root bark as, 926; pumpkin seed as, 930; wormwood as, 953; tansy as, 954; santonin as, 955; spigelia as an, 978; oleum chenopodii as, 1009; kamala as, 1025; oil of turpentine as, 1059; thuja as,

1063 ; areca nut as, 1052 ; male fern as, 1066
Anthrax, produced by the bacillus anthracis, 99
Anthrax bacilli. *See* Bacilli
Antiarine, action of, on mollusca, 114 ; on the frog's heart, 307 ; on the cardiac muscle, 316 ; as a cardiac tonic, 331
Antidotes, alkalies serviceable as, in poisoning by acids, metals, and alkaloids, 599
Antidotes, nature and action of, 486 ; list of the more common poisons with their antidotes, 486–491 ; to poisonous gases, 486 ; to acids and alkalies, 487 ; to alkaloids, &c., 488
Antidysenteric, ipecacuanha as an, 950
Antifebrin, action and uses, 825
Antihidrotics, or anhidrotics, nature, action, and uses of, 441–443 ; on the sweat-glands, 441 ; on the secreting cells and nerves, 441 ; on the sweat-centres and on the circulation, 441 ; diagram illustrating the action of, 442
Antimonial preparations are depressant expectorants, 255
Antimonii et potassii tartras, 726, 730
Oxidum, 726, 729
Sulphidum, 726, 727
Purificatum, 726, 727
Antimonium nigrum, 726
Sulphuratum, 726, 727
Tartaratum, 610, 726
Antimony, symbol and atomic weight of, 9 ; its relations to other members of a group, 16 ; action of, on muscle, 127 *et seq.* ; of large doses of, on the lungs, 238 ; on the motor ganglia, 316 ; on the vaso-motor nerves, 318 ; tartarated, as a pustulant, 344 ; as a caustic, 344 ; destroys the glycogenic function of the liver, 402 ; has a special action on tissue-change, 415 ; in poisoning by, action of, on the urine, 415 ; employed in diseases of the respiratory organs, 416 ; as a poison with its antidote, 488 ; general sources and reactions of, 721 ; action of, on the skin and stomach, 722 ; effects of poisoning from, 722 ; and mode of treatment, 722 ; account of the dispute that has arisen regarding the mode in which tartar emetic causes vomiting, 723 ; action of, on the heart of a frog, 724 ; on the circulation, blood-pressure, and temperature, 724 ; on the respiration, spinal cord, motor and sensory nerves and muscles, 724 ; produces fatty degeneration of various organs, 724 ; rapidity of its action on the skin of frogs, 724 ; diagram of vertical section of the epidermis of a frog poisoned by, 725 ; how eliminated, 725 ; uses of, 725 ; as an emetic, 725 ; how tolerance of the drug is produced, 44, 725 ; as a nauseant, 726 ; as an expectorant, 726 ; as sedative, 726 ; as a diaphoretic, 726 ; preparations containing, 726
Antimony, properties, action, and uses of—
Oxide of, 729
Purified sulphide of, 727
Solution of chloride of, 729
Sulphurated, 727
Tartarated, 730
Tartrate of, and potassium, 730
Antineuralgic, peppermint camphor as an, 1005
Antiperiodics, list of the chief, 107 ; their action, uses, and adjuncts, 107 ; emetics and purgatives aid the action of, 108 ; they rarely succeed without them if the functions of the liver are disturbed, 108 ; lemon-juice as a powerful 891 ; quinine as, 947 ; sulphate of beberine as, 1021
Antipyretics, or febrifuges, divided into two great classes, 418 ; their nature 416 ; action, 419 ; and uses, 420 aromatic series as antipyretics, 811 resorcin as, 818 ; chinoline as, 823 kairin as, 824 ; antipyrin as, 824 thallin as, 825 ; antifebrin as, 825 quinine as, 948 ; oil of gaultheria as 963 ; salicin as, 1035
Antipyrin, characters, 824 ; action of in reducing temperature, causing profuse perspiration, and slightly increasing the blood-pressure, 824 ; uses of in febrile diseases generally, 825
Antiscorbutic, lemon-juice as an, 891
Antiseptic, what is required in an, 89
Antiseptics, nature and action of, 103 list of, 91 ; uses of, 104, 106 ; externally 104 ; internally, 105 ; calomel as an antiseptic, 106 ; corrosive sublimate as 693 ; chloral hydrate as, 791 ; iodoform as, 805 ; iodol as, 1099 ; the aromatic series of the carbon compounds as, 811 naphthalin as, 446, 822 ; chinoline as 823 ; cubebs as, 446 ; terpenes as, 446 cheken as, 923 ; oil of myrtle as, 924 oil of eucalyptus as, 925 ; quinine as 945 ; arbutin as, 962 ; benzoic acid as 964 ; peppermint-camphor as, 1005 thymol as, 1006 ; garlic as, 1040
Antisialics, nature and action of, 360, 36
Antispasmodics, nature, action, and use of, 212, 214 ; action of, and list of generally, 214 ; adjuvants to, 214 acetic ether as an antispasmodic, 784 iodide of ethyl as, 790 ; caulophyllum as, 843 ; oil of rue as, 881 ; oil of cajeput as, 924 ; asafœtida as, 933 ; valerian as, 952 ; stramonium leaves as, 992 cypripedium as, 1036

ntizymotics, nature and action of, 103
ortic regurgitation. *See* Regurgitation, aortic
ortic stenosis. *See* Stenosis, aortic
phrodisiacs, nature and action of, 447, 450; diagrams illustrating the action of, 448, 449
pnœa, nature and cause of, 237, 240
pocynaceæ, 968
pocynum, characters and action of, 968; as a laxative, a cardiac tonic, and a diuretic, 969
pomorphina, 504
pomorphine, action of, on muscle, 127; on the cerebellum, 215; may lead to obstruction of the bronchi, 238; action of, on the respiratory centre, 240; on the mucous membranes, 253; caution required in the administration of, in catarrhal conditions, 254; as a depressant expectorant, 255; effect of, on the frog's heart, 307; on the cardiac muscle, 316; as a general emetic, 373
Apomorphine, hydrochlorate of, characters of, 848; action of, as an emetic, on the motor centres in the brain and the respiratory and vomiting centres in the medulla, 849; on muscular fibre, the pulse, 849; and the secretion of bronchial mucus, 849; opium *versus*, 859
Apoplexy, diagnosis between opium-poisoning, intoxication, and, 853
Apples, stewed, as a laxative, 389
Aqua Ammoniæ, 506, 640
fortior, 506, 638
Amygdalæ amaræ, 506, 916
Anethi, 506, 936
Anisi, 506, 935
Aurantii floris, 506, 888
Aurantii florum, 506, 888
Camphoræ, 506, 1018
Carui, 506, 936
Chlori, 506, 550
Chloroformi, 506, 796
Cinnamomi, 506, 1017
Creasoti, 506, 817
Distillata, 506
Fœniculi, 506, 934
Laurocerasi, 506, 918
Menthæ piperitæ, 506, 1004
Menthæ viridis, 506, 1005
Pimentæ, 506, 923
Rosæ, 506, 920
Sambuci, 506, 939
Aqueous solution of ferric nitrate, 747
Aquifoliaceæ, 894
Araroba powder, 909
Arbutin, as an astringent, 349; action of, on the kidneys, 436; as an antiseptic, 962
Areca nut, as a vermicide, 408; nature of, 1052
Argenti et potassii nitras, 677
Oxidum, 648, 679
Iodidum, 557
Argentum. *See* Silver
Aristolochiaceæ, 1012
Arnica, as a rubefacient, 344
Camphor, action of, on the cardiac muscle, 316
Flowers, characters, action, and uses of, 958
Rhizome (root), 957
Arnstein, reference to, 313
Aroideæ, 1052
Arseniate of iron, 751
Arseniate of sodium—properties, action, and uses of, 720
Arsenic, symbol and atomic weight of, 9; effect of habit in eating, 44; use of a small dose of, for gastric neuralgia, 43; action of, on bacteria, 93; as an antiperiodic is sometimes more powerful than quinine, 107; action of, on muscle, 127 *et seq.*; on the ends of the vaso-motor nerves, 284; on the motor ganglia, 316; on the vaso-motor nerves, 318; almost tasteless as a poison, 398; secondary effects of, as a poison, 398; destroys the glycogenic function of the liver, 402; as an alterative, 413; has a special action on tissue-changes, 415; in poisoning by, action of, on the urine, 415; used in nervous debility, 416; in diseases of the skin, 416; in some chronic conditions of the respiratory organs, 416; as a poison, with its antidote, 488; character and general sources, 712; action of, on the skin, mouth, stomach, and nervous system, 713; treatment in cases of poisoning by, 714; how chronic poisoning by, may occur, 714; how the system may become habituated to it, as seen in the arsenic-eaters of Styria, 714; action of, on the blood, pulse, and heart, 715; on the blood-pressure in animals, 715; causes paralysis, 715; peculiarity of its action on the skin, 716; diagrams illustrating the epidermis of a frog before and after poisoning by, 715; uses of, in various diseases, 716, 717; diagram of section of lung of a guinea-pig poisoned by arsenious acid, 716; probable mode of action of, in phthisis, 717, 718; mode of administration of, 718
Arsenic acid, physiological action of, 27
Arsenic, iodide of, nature and use of, 720; solution of, and mercury, 721
Arsenici iodidum, 557
Arsenii iodidum, 557
Arsenious acid, effects of, on the blood, 73; as a local sedative (in minute doses), 376; properties, preparations, and uses of, 719, 720
Arsenium, 712
Arteries, nature and functions of, 262; blood only available for the nutrition

of cells while in the, 262; action of the pressure of the, on the circulation of the blood, 263; action of the heart on the, 263; effect of an upright and of a horizontal position on the circulation of the blood in the, 263; arrest of circulation in the, the cause of fainting and shock, 264–265; schema of the circulation from the heart to the veins and the, 265–267; action of blood-pressure on the, 267; method of ascertaining the blood-pressure in the, 268–270; causes of alterations in blood-pressure of the, 270; how it may be raised and lowered, 271; relation of blood-pressure to pulse-rate and the, 271–275; effect of the, on pulse-curves, 275–277; investigation of the action of drugs on the, 277–279; another method of ascertaining this, 281–283

Arterioles, action of the, on the blood-pressure, 263; effects of rapid dilatation of the, 264; schema of the circulation in the, 265–267; circulation in the, in the living body, 267; blood-pressure in the, and method of ascertaining it, 268–270; diagram of the apparatus employed in this, 269; alterations in blood-pressure in the, 270; relation of pulse-rate and the, to blood-pressure, 271–275; diagrams illustrative of this, 272–273; effect of the, on pulse-curves, 275–277; investigation of the action of drugs on the, 277–283; two modes of estimating the contraction of the, 278; the method of direct observation, 278; the method of measurement by rate of flow, 281; mode of ascertaining whether a rise or fall in blood-pressure is due to the heart or to the, 292; action of digitalin on the, 996

Artocarpeæ, 1,028

Asafœtida, as an antispasmodic, 213, 214; as a carminative, 379; characters and uses of, 932, 933; as an antispasmodic, carminative, and expectorant, 933

Asarum Europæum or asarabacca, action of, internally, 1,012

Ascidians, action of drugs on, 114; diagram of an ascidian, 233

Asclepiadaceæ, 970

Asclepias, characters and use of, 970; as a diaphoretic, or expectorant, 970

Asclepias incarnata, as cardiac tonic and diuretic, 970

Asparagus, as a stimulant diuretic, 433

Asphxyial blood, stimulating effects of, on the medulla, 298; on sweat centres, 438

Astringents, action of, on the mucous membranes, 253; sulphate of copper as an astringent, 344, 675; nature, action, and uses of, 349, 377; slaked lime as an astringent, 648; alum as, 655; salts of zinc as, 668; geranium as, 881; rhatany root as, 869; prinos as, 894; rhus glabra (sumach) as, 898; myrrh as, 893; kino as, 902; logwood as, 908; catechu as, 914; rubus or blackberry as, 919; pale catechu as, 951; bearberry as, 962; chimaphila as, 962; salvia as, 1,008; rhubarb as, 1,011; rumex as, 1,011; oil of cinnamon as, 1,017; the bark of quercus alba as, 1,031; galls or nutgalls as, 1,031; elm bark as, 1,026

Atheroma, emetics to be avoided in persons suffering from, 375

Atomic weight of the elements, 9, 10; arrangement according to, 16

— — and physiological action, relation between, 281

— — and smell, relation of, 29

— — and taste, 30

Atonic dyspepsia, slight stimulants produce appetite in, 363

Atropeæ, 984

Atropinæ Sulphas, 986

Sulphatis, Liquor, 986

Unguentum, 986

Atropina, 504, 985, 986

Atropine, physiological action of, on the motor or efferent nerves, 26; effect of large and small quantities of, on the pulse, 36; action of, on oxidation, 69; on medusæ, 111; on annulosa, 116; on muscles, 139, 141, 155, 157; as a sedative, 157; action of, on the spinal cord, 163, 172; on the brain of the lower animals, 188; as a local and general anodyne, 201; as a mydriatic, 216, 219 *et seq.*; action of, on the respiratory centre, 240; on the vagus, 244; when injected into the jugular vein, 245; has a slight and uncertain action on the respiratory centre, 250; but a powerful effect in completely arresting the secretion from the bronchial tubes, 250; cases in which it is useful as a pulmonary sedative when combined with apomorphine, 250; diagram of pulse and blood-pressure curve caused by the actions of, on the heart, 272; action on the vessels, 282; destroys the inhibitory action of the vagus on the heart in dogs and rabbits, 287; acts on the heart through the vagus-roots, 297; might be useful in lessening pain or palpitation of the heart in persons with high blood-pressure, 299; with muscarine, restores the pulsations in the heart-apex of the frog, 306; rapid action of, on the heart of the frog, 309; on the inhibitory power of the vagi, 310, 311; neutralises the action of muscarine on the heart, 314; action of, on the vagus centre, 317; on the

vaso-motor centre, 319; as a cardiac stimulant, 328; effect of, on the secreting cells of a gland, 355; the most powerful of all antisialics, 361; paralysing action of, counteracted by physostigmine, 361; as a local sedative, 376; action of, on the intestines, 383; as an antihidrotic, 441; strong solutions of, applied to the conjunctiva, 477; as a poison, with its antidote, 488; antagonistic action of, to other drugs, 492–495; general action of belladonna or, in large and small doses, 986; special action of, locally applied, 986; on the brain, the spinal cord, and the motor nerves, 986, 987; on the muscles, the eye, and the circulation, 987; on the urine, 988; on the intestines in large and small doses, 988; and on the temperature, 988; certain animals insusceptible to the action of, 988; uses of, 989; as an antidote to opium, 990
Aurantiæ, 887
Auricular septum, view of the, in the frog, 300
Aves, 1085
Azedarach, nature and use of, 894; chiefly as an anthelmintic, 894

B.

Bacilli, action of drugs on particular species of, 92; mode of experimenting on the action of drugs on reproduction of, 92; power of the spores of *Bacillus anthracis* to resist certain substances usually fatal to life, 94, 95; action of drugs on the development and growth of, 95. *See* also Bacteria
Bacillus, the lactic ferment a, 79; treatment for destroying the tubercle bacillus, 533, 717
Bacillus Anthracis, nature and action of, 717
Bacillus tuberculosis, difference between the action of, and that of *Bacillus anthracis*, 717
Bacteria, killed by creasote, 79; origin and nature of, 80; diagram of the different kinds of, 83; diseases caused by, 82; importance of a knowledge of, in relation to disease, 82; divided by Pasteur into two classes, 82; life-history of, 82, 84; struggle for existence between the different species of, 84, 85; between the organism and, 85; diagrams illustrating this struggle, 86, 87; action of phagocytes on, 85; action of drugs on the movements of, 88; and on the reproduction of, in general, 89; the most destructive substances to, 89; mode of experimenting to test the effects of drugs in destroying the germs of, 89, 90; comparative action of different drugs on, 91; action of drugs on particular species of, 92; mode of experimenting on the action of drugs on the reproduction of, 92; results of Koch's experiments on, with three groups of disinfectants, 93, 94; action of drugs on the development and growth of, 95; table showing the strength of various disinfectants required to prevent the development of, 95; influence of temperature on the action of antiseptics on, 96; alterations in by heat and soil, 96; possible identity of different forms of, 97; may be modified by cultivation. 98; action of, and their products on the animal body, 98; list of diseases caused by, 99; alkaloids formed by, 99; absorption of elimination of these alkaloids, 101; effect of drugs on the action of, in the animal body, 102; decomposition of food in the mouth due to, 352; action of salicylic acid on, 820. *See* also Antiseptics
Bael fruit, beneficial action of, in dysentery, 387; characters, composition, and uses of, 891, 892
Baker, Morrant, reference to, 856
Balm. *See* Melissa
Balsam, Canada, 1057
Of Copaiba, 912
Fir, 1057
Peru, as a stimulant expectorant, 255; nature, action, and uses of, 902, 903
Tolu, as an expectorant, 255, 903
Balsamifloræ, 1030
Baptisin, as a hepatic stimulant, 403, 405
Barbaloïn, nature and reaction of, 1042
Barium, symbol and atomic weight of, 9; its relation to other members of a group, 16; physiological action of, 27; salts of, action of, on muscles, 129, 135, 136, 142; causes contraction of the vessels, 281; action of, on the heart of the frog, 307; salts of, action of, on the cardiac muscle, 316; and on the capillaries, 318; antagonism of, to other drugs, 492–495
Barium chloride, action of, on bacteria, 93
Bark, Angostura, 881
Bebeeru, 1021
Calisaya, 940
Canella alba, 867
Casca, 915
Cascarilla, 1022
Cinchona, 939
Cinchona, Red, 940
Yellow, 940
Cinnamon, 1016
Coto, 1017
Cotton root, 872
Larch, 1061

Bark—
Mezereon, 1022
Oak, 1030
Paracoto, 1017
Pomegranate root, 926
Quebracho, White, 969
Sacred, 895
Sassy, 915
Soap, 918
Barley, pearl, 1054
Baryta salts, as poisons, with antidote, 488
Basham's mixture, 745
Baths, cold, as anaphrodisiacs, 451; hot foot, hip, and mustard, as indirect emmenagogues, 453; may be either local or general, 459; three chief kinds, 459, 460; the cold bath, 460-462; the cold pack, 463; cold sponging, 463; cold douche, 463; the spinal douche, 464; the ascending douche, 464; sitz bath, 464, 465; cold foot-bath, 465; cold compresses, 465; tepid baths, 466; warm baths, 466; hot baths, 467; hot foot-bath, 467; hot sitz baths, 467; poultices, 468; medicated baths, 469; sea-bathing, 469; carbonic acid bath, 469, 583; acid bath, 469; alkaline bath, 470; sulphurated bath, 470; mustard bath, 470; pine bath, 470; vapour baths, 470; calomel fumigation, 471; air baths, 471; the Turkish bath, 471; friction and inunction, 472-474
Bat's wing, Luchsinger's experiment with a, 138
Baxt, reference to, 854
Baxter, B., reference to, 61
Beads, jumble, 903
Prayer, 903
Bean of St. Ignatius, 971
Bearberry, and bearberry leaves, 961
Beaumont, Dr., references to his observations on the case of Alexis St. Martin, 369, 407
Bebeerine, action of, on bacteria, 89; as an antiperiodic, 107
Bebeeru bark, as an antiperiodic, 107; characters and composition of, 1021
Beberinæ sulphas, 1021
Beberine, sulphate of, properties, action, and uses of, 1021
Beef-tea *versus* alcohol, as a stimulant, 774
Beer yeast, 1073
Belladonna, difference of action of, in men, rabbits, and dogs, 54; as a sedative, 157; action of, on frogs, 171; as a spinal stimulant, 182; as a narcotic, 200; as a local and general anodyne, 201, 202; as a mydriatic, 219; action of, on the respiratory centre, 250; on palpitation of the heart, 338; as a local sedative, 376; as a purgative, 386; as an antihidrotic, 441; its action in incontinence of urine, 445; as a poison, with its antidote, 488; antagonism of, to opium, 494; preparations, 985; action, 986; uses, 989
Belladonna leaves, 984
Root, 985. For general action of belladonna, *see* Atropine
Belladonnine, as a mydriatic, 219
Bennett, Hughes, reference to, 160
Benzin, properties and uses of, 762
Benzoates, test for, 594
Benzoate of ammonium, 643, 964
of lithium, 632
of sodium, action of, on enzymes, 78; on bacteria, 94, 95; uses of, 628
Benzoated lard, 1084
Benzoic acid, action of, on enzymes, 78; on bacteria, 91, 94, 95; as a stimulating expectorant, 255; action of, on the kidneys, 436; preparation and properties of, 964; action of, as an antiseptic, 964; as diaphoretic, 965; uses of, 965
Benzoin, as a stimulating expectorant, 255; characters of, 963; and preparations of, 964; compound tincture of, 964
Benzol, action of, on bacteria, 93
Benzoyltropine, as a mydriatic, 219, 223
Berberidaceæ, 842
Berberine, character and action of, 837, 838, 841, 883
Bergamot, oil of, characters and uses of, 890
Bergmann, reference to, 100
Bernard, Claude, references to, 38, and *n.*, 56, 147, 150, 358, 850
Bernstein, references to, 174, 235, 237
Bert, Paul, reference to, 94
Beryllium, symbol and atomic weight of, 9; physiological action of, 27
Bezold, Von, references to, 285, 288, 296
Bicarbonates, test for, 594
Bicarbonate of potassium, 608
of sodium, action of, on the gastric juice, 364; nature of, 622
Bichloride of ethidene, as a general anæsthetic, 205; of methylene, as a general anæsthetic, 205; nature of, 795
Bichromate of potassium, as a poison, with its antidotes, 489; nature and uses of, 616
Biedermann, reference to, 133
Bigelow, Dr., reference to his use of ether, 212
Bile, utility of emetics to expel, from the gall-bladder, 374; and to remove it from the body in cases of biliousness, fevers, and agues, 375; nature and functions of the, 399-406; use of cholagogues in removing the, from the body, 407; action of acids on the, 570; of pilocarpine, 885; of leptandra, 1002; of aloes, 1044; purified ox-bile, 1082; its composition, action, and uses, 1082
Bin-oxalate of potassium (salts of lemon or sorrel), as a poison, with its antidote, 487

Binz, Prof., references to, 62, 72, 166, 549, 874
Birds, action of opium on, 851
Bismuth, properties, preparation, action, and uses of—
Carbonate of, 731, 733
Citrate of, 733
and ammonium, 734
Common, 730-732
Oxide of, 731
Purified, 732
Solution of citrate of, and ammonium, 733
Subcarbonate of, 733
Sub-nitrate of, 731, 732
Bismuth, symbol and atomic weight of, 9; a mild irritant to the stomach, 363; salts of, as a local sedative, 376
Bismuth subnitrate, as an astringent, 349
Bismuthi et ammonii citras, 734
Citratis liquor, 733
Carbonas, 732
Citras, 732
Subnitras, 732
Bisulphide of carbon, action of, on bacteria, 93; action and uses, 760
Bisulphite, test for, 595
Bisulphite of sodium, 630
Bitartrate, test for, 595
Bites of venomous serpents or of rabid dogs, utility of caustics in, 347; necessity for care in cauterising for dog-bites, 347
Bitters, action of, 364
Bittersweet. *See* Dulcamara
Blackberry, 919
Black Haw, 939
Pepper, 1012
Wash, 691
Bladder, diagram to show the effects on the cerebral circulation of rapidly emptying the, 264; action of drugs on the, 443–445; situation of the nerve-centre of the, 444; and of the cerebral, 444; action of vesical sedatives on, 444; and vesical tonics, 445; urinary sedatives and astringents, 445; treatment of inflammation of the, 446; result of distension of the, and of stone in the, 451; utility of pareira root in chronic catarrh of the, 842; action of buchu leaves on the mucous membrane of the, 882; of pilocarpine, 884, 885; of physostigmine, 907
Blagdon, Sir Charles, reference to, 440
Blake, reference to, 26
Blastomycetes, 83
Blatta orientalis, as a stimulant diuretic, 433; as an aphrodisiac, 450
Bleeding, local, or by leeches or by wet cupping, usefulness of, in inflammation and fever, 420; as an anaphrodisiac, 451
Blisters, probable action of, in inflammation, 342, 343; various diseases in which they are useful, 345; as antipyretics, 418
Blood, red corpuscles of the, effect of heat and cold on, 63; action of drugs on the, 70; effects of oxygen and other gases on the, 69–71; various constituents of the,—hæmoglobin, 70–72; oxy-hæmoglobin, 70–72; hæmatin, 70–71; methæmoglobin, 71–72; effects of carbonic acid on the, 70; of hydrocyanic acid, 70; of nitrites, 71; alterations effected in the interchange between the air and the, 72; poisoning of the, produced by the bacillus septicæmiæ, 99–100; action of, on the brain, 192–200; state of the, in respiratory complications, 237–240; effect of excessive venosity of the, on the respiratory centres, 237–238; condition of the, in suffocation, and in nitrite and carbonic oxide poisoning, 239, 240; difference in the quality of, in the arteries and in the veins, 262; importance of the pressure of the arteries and veins on the circulation of the, 263; action of the heart in reference to the, 263; fainting and shock caused by the sudden arrest of the supply of, to the brain, 264, 265; schema of the circulation of the, 265–267; diagram illustrating this, 266; circulation of the, in the living body, 267; nature of arterial tension, or blood-pressure, 267; method of ascertaining the blood-pressure, 268; alterations in blood-pressure and their causes, 270; how this pressure may be raised and lowered, 271; relation of pulse-rate and arterioles to blood-pressure, 271–275; diagrams illustrative of blood-pressure, 272 *et seq.*; effect of the arterioles on blood-pressure and pulse-rate, 275–277; investigation of the action of drugs on the blood-vessels, 277–280; another method of ascertaining this, 281–283; venous, causes contraction, and oxygenated, dilatation of the vessels, 282; action of other parts on blood-pressure, 285; reflex contraction of blood-vessels, 285; action of drugs on this reflex contraction, 286; comparative effect of heart and vessels on blood-pressure in different animals, 287–288; influence of nerves on blood-pressure, 289–292; causes of alteration in blood-pressure and pulse-rate, 293; action of the heart on blood-pressure, 292; action of styptics on the, 350; coagulation of the, caused by alum, lead acetate, and ferric chloride, 350; action of hæmatinics in improving the quality of the, 412; nature and action of the red corpuscles of the, 412; the various constituents of, 412; pressure

of the, in the glomeruli, and the composition of the, two factors in the rapidity of the secretion of urine, 427, 430; experiment with digitalis on blood-pressure, 430, 431; action of hydrocyanic acid on the, 587; of caustic alkalies injected into the, 599; action of the metals on the, 665; of mercury, 685; of salts of iron, 740; of alcohol, 767; of spirit of ether, 782; of nitrite of amyl, 785; of nitro-glycerine, 789; of choral hydrate, 792; of purified chloroform, 797, 799; of carbolic acid, 814; of creasote, 817; of antipyrin, 824; of erythroxylon, 879; of caffeine, 871; of Jamaica dogwood, 913; of oil of eucalyptus, 925; of quinine, 945; of oil of valerian, 952; of sulphate of strychnine, 974; of curare, 976; of gelsemium, 978; of tobacco, 993; of digitalin, 996; of thymol, 1006; of tannic acid, 1032
Blood-letting, as a local anodyne, 201
Bloodroot. *See* Sanguinaria
Blue cohosh, 842
Bocci, reference to, 401
Body, Remedies Acting on the Surface of the, 340–351. *See* Remedies, &c.
Boehm, references to, 124, 245, 284, 315, 836, 996
Boerhaave, reference to, 444
Boisbaudran, L. de, on molecules, 27
Bon, M. Gustave le, reference to, 103
Bones, action of phosphorus on the, 710
Boracic acid, action on bacteria, 94, 95; nature and properties of, 581
Borates, test for, 594
Borax, action of, on enzymes, 78; on bacteria, 91, 94, 95; as an antiseptic for cleansing the teeth, 352; as an antisialic, 361; as a direct emmenagogue, 453; nature and uses of, 624; its derivatives, glycerinum boracis and mel boracis, 624
Boric or boracic acid, properties of, &c., 581
Borneol, action of, on the brain and spinal cord, 213; on the cardiac muscle, 316
Boron, symbol and atomic weight of, 9
Borosalicylate of sodium, 91
Botkin, Jnr., reference to, 29
Bouchard, reference to, 101, 401
Bouley, reference to, 369
Bowditch, reference to, 304
Bowels. *See* Intestines.
Bowman, reference to, 422–423
Brain, Action of Drugs on the, 183–215; in the frog, 183; in mammals, 184; of frogs, rabbits, guinea-pigs, monkeys, dogs, and cats, 183–186; diagram of the brain of a frog, 184; diagram of the brain of a monkey, 185; arrangement of the motor and sensory centres of the, in the lower animals, 186; depressant action of drugs on the motor centres of the, 187; method of investigating the action of drugs on the excitability of the, 187; irritant action of drugs on the motor centres of the, 188–190; action of drugs on the sensory and psychical centres of the, 191–212; effect of drugs upon the time required for mental processes, 191; drugs which increase the functional activity of the, 192; nerve stimulants, 192; cerebral stimulants, 192; effects of posture and mastication on the action of the, 192; stimulating effects of smoking, sips of alcohol, and tea and coffee on the, 193–194; suction causes an increased supply of blood to the, 194; diagrams illustrating action on circulation of, by posture, mastication, and sucking, 193; exercise causes increased activity in the, 194; sipping a powerful stimulant to the, 194; alcohol one of the typical stimulants of the, 195; direct action of strychnine and caffeine on the, 195; drugs which lessen the functional activity of the, 195–211; hypnotics or soporifics induce sleep, 196; effects of different degrees of sleep on the, 196–197; action of hypnotics on the, 196–200; of narcotics, 200; peculiar action of alcohol on the, 200; peculiar physiological conditions of the, 200; action of anodynes or analgesics, 201–203; causes and transmission of pain, 202; adjuncts to anodynes, 203; action of anæsthetics on the, 203–210; of antispasmodics, 212; of drugs on the cerebellum, 215; different kinds of spirits appear to affect different parts of the, 215; fainting and shock caused by arrest of the supply of blood to the, 264, 265; action of the, on vomiting, 371; action of bromide of potassium on the, 554; of strong solution of ammonia, 639; of alcohol, 769; of spirit of ether, 782; of chloral hydrate, 792; of hydrochlorate of apomorphine, 849; of codeine, 850; of opium, 854; of sanguinaria, 863; of citrate of caffeine, 871; of oil of eucalyptus, 925; of coniïne, 932; of oil of valerian, 952; of strychnine, 975; of belladonna or atropine, 986
Brandy as a cardiac stimulant, 328; nature, &c., of, 773, 776
Bread, as a demulcent, 347; crumb of, 1053
Brefeld, his classification of organised ferments, 81
Brieger, references to, 99, 101
Bromal-hydrate, antagonism of, to atropine, 495; nature, action, and use of, 795

Bromic acid, physiological action of, 27
Bromides, test for, 594
Bromide of Ammonium as a hypnotic, 199; as an anaphrodisiac, 451; nature of, 556
Calcium, as a hypnotic, 199, 556
Ethyl, 205, 789
Lithium, 556
Potassium, 553
Sodium, 555
Zinc, as a hypnotic, 199, 672
Bromide of potassium, action of, on the motor centres of the brain, 187; lessens the functional activity of the brain, 196; as a hypnotic, 199; as an anodyne, 202; as an antispasmodic, 213; action of, as an antispasmodic, 214; on the vessels of circulation, 286; as an anaphrodisiac, 451; action of, 553; action of, on the spinal cord and the brain, 553; uses in nervous diseases and as a hypnotic, 554; allays excitability and irritability, 554; in epilepsy and sickness, especially in pregnancy and sea-sickness, 555; as an anaphrodisiac, 555
Bromide of sodium, as a hypnotic, 199
Bromides, mixed, 556
Bromine, symbol and atomic weight of, 9; action of, on infusoria, 65; on enzymes, 78; on bacteria, 89, 91, 93, 95; as a caustic, 344; as a poison, with its antidote, 486; characters, test, and uses of, 552
Bromo-camphor, antispasmodic powers of, 213
Bromoform, as a general anæsthetic, 205
Bronchial asthma, pathology of, 259; treatment, 260
Bronchial tubes, atropine completely arrests the secretion from the, 250; action of drugs on, 259
Bronchitis, chronic, cod-liver oil affords more relief in, than any of the ordinary expectorants, 254; importance of an emetic in, 255; ipecacuanha, either alone or combined with squills, as expectorant in, 255; with great depression and feeble circulation, carbonate of ammonium to be preferred, 255; importance of warmth and moisture in, 255; of respirators, warm clothing, &c., in, 256; value of certain plasters in, 256; tartar emetic ointment and croton-oil liniment sometimes of use in, 346
Bronchitis kettle, nature and use of, 481
Broom, as a refrigerant diuretic, 432; broom and broom-tops, characters and composition of, 900; physiological action and therapeutical uses of, 900
Brown-Séquard, reference to, 244
Brucine, effects of, on the blood, 72; as a spinal stimulant, 181; action of, on the respiratory centre, 240; antagonism of, to chloral, 495; acts like strychnine, 975
Brücke, Professor, reference to, 995
Brunton, Dr. L., references to, 29, 37, 42, 47, 55, 124, 129, 150, 176, 186, 228, 273, 276, 288, 294, 296, 312, 381, 401, 430, 431, 493, 497, 606, 900
Bryonia, or bryony, characters and use of, as a hydragogue cathartic, 930
Bubnoff, reference to, 837
Buchheim, references to, 37, 150
Buchner, reference to, 98
Buchu, as a stimulant diuretic, 433; action of, on the bladder, 445; buchu leaves, nature, action, and use of, 882
Buckthorn, nature, action, and use of, 895
Burdock, 960
Burgundy pitch, 1062
Burnett, Sir W., reference to, 671; his disinfecting fluid, as a poison, with its antidote, 488
Burseraceæ, 893
Butternut. *See* Juglans
Butyl-chloral, as a general anodyne, 201, 202; characters, action, and uses of, 794
Butyric acid, action of, on bacteria, 93
Buxine, as a spinal stimulant, 181
Byttneriaceæ, 875

C.

Cabbage-rose petals, 920
Cacao-butter, 875
Cadaverine, 100
Cadmium, symbol and atomic weight of, 9; its relation to other members of a group, 16; physiological action of, 27; effect of, on muscle, 127 *et seq.*; causes slight contraction of the vessels, 281; cadmium sulphate, as an astringent, 349
Cæsalpiniæ, 909
Cæsium, symbol and atomic weight of, 9; its relation to other members of a group, 16; physiological action of, 27
Caffeina, 504
Caffeinæ citras, 504, 870
Caffeine, action of, on oxidation, 70; on medusæ, 111; on annulosa, 116; on muscles, 130, 136 *et seq.*; on the spinal cord, 160; as spinal stimulant, 181; on the brain, 195; on the accelerating centre, 318; on the vaso-motor centre, 319; on the cardiac muscle, 316; as a cardiac tonic, 331; as a hydragogue diuretic, 432; antagonism of, to morphine, 494, 496; (theine, guaranine) characters of, 870; action of, on the nerve-centres, and on muscular fibre, 871; on frogs and warm-blooded animals, 871; on the brain, medulla, respiration, blood-pressure, and pulse, 871; on the salivary secretion and the

intestines, 871; on the temperature, 872; as a diuretic, 872
Cahours, reference to, 150
Cajuput oil, as a rubefacient, 344; and carminative, 379; oil of, characters and uses of, 924; as a powerful stimulant, antispasmodic, and rubefacient, 924
Calabar bean as a myotic, 219; as a poison, with its antidote, 488; character, composition, and preparations of, 904. *See* also Physostigma
Calabarine, as a spinal stimulant, 181; antagonism of, to chloral, 495
Calamine, prepared, 670
Calamus, 1052
Calcii hydras, 647, 648
Calcium, symbol and atomic weight of, 9; its relation to other members of a group, 16; and specially to lithium, 17; physiological action of, 27; action of, on the muscles, 134, 142; causes great contraction of the vessels, 281; salts of, and distilled water prolong the beating of the frog's heart, 306
Calcium salts, sources and reactions of, 646; general preparation of, 647; impurities and tests of, 647; characters and uses of, 646 *et seq.*
Bromide of, 556
Chloride of, action on bacteria, 93, 651
Hypophosphite of, 653
Precipitated Carbonate of, 651
Phosphate of, 652
See also under Lime
Calendula (marigold), 959
Calomel, antiseptic power of, 106; action of, on the stomach, 369; on the pancreatic juice, 408; as a diuretic, 432, 686; its action and uses, 691
Calomel fumigation, 471
Calumba and Calumba root, characters, composition, and preparations of, 840; actions and uses of, 841
Calycifloræ (sub-class III.), 899
Camphor, action of, on bacteria, 95; on ascidians, 114; and on annulosa, 116; curious exciting action of, on the brain and the medulla, 190; action of, as an antispasmodic, 213; on the ear, 229; on the vaso-motor centre, 319; on the cardiac muscle, 316; as a cardiac stimulant, 326, 329; as a popular remedy to cut short coryza or catarrh, 331; compound liniment of, and camphor, as a rubefacient, 344; as an anaphrodisiac, 451; use of, in liniments, 515; characters, composition, and preparations of, 1018; action of, as a stimulant and rubefacient, 1018; as a diaphoretic and anaphrodisiac, 1019; action of, on the heart, nerve-centres, and the temperature, 1019; uses of, externally and internally, 1019
Camphor, monobromated, characters of, 1019; action and uses of, 1019; as a sedative, 1019
Campylospermæ, 930
Canada Balsam, 1057
Pitch, 1062
Turpentine, 1057
Canadian hemp. *See* Apocynum
Canellaceæ, 867
Canella bark, an aromatic bitter and tonic, 867
Cannabin, action of, on brain of dogs, 188
Cannabineæ, 1026
Cannabis, American, 1026
Cannabis indica, as a hypnotic, 199; as an anodyne, 202; action of, in producing visions, 228; doubtful value of, as an aphrodisiac, 450; as a poison, with its antidote, 488; character, action, and uses of, 1026
Cantharides, as a vesicant, 344; as a stimulant diuretic, 433; action of, on the kidneys, 435; produces both albuminuria and hæmaturia, 435; its action on the urine, 445; as an aphrodisiac, 450; as a direct emmenagogue, 453; as a poison, with their antidotes, 488; character and composition of, 1091; action of, externally and internally, 1091; on the salivary glands and on the urinary organs, 1092; uses of, externally as an irritant and a counter-irritant, 1092; with diagrams, 1093, 1094; and internally, 1094; precautions, 1094
Capillaries, list of drugs by which they are stimulated, depressed, or paralysed, 318; a certain abnormal condition of the, one of the chief causes of dropsy, 337
Caprifoliaceæ, 939
Capsicum, as a rubefacient, 344
Fruit, characters and composition of, 984; action and uses of, 984
Caraway, as a carminative, 937
Fruit, 936
Oil of, 937
Caraway and oil, as a carminative, 379
Carbolic acid, action of, on enzymes, 78; on bacteria, 91–92; as a deodorizer, 104; its superiority for removing smell from the hands, 106; as a sedative and an anæsthetic, 157; one of the chief local anæsthetics, 204; action of, on the vaso-motor centre, 319; as a caustic, 344; as an astringent for the teeth, 352; liquefied as a remedy for tooth-ache, 353; as a local gastric sedative, 376; as a poison, with its antidote, 489; antagonism of, to chloral, 495; characters, tests, and preparations of, 813; action of, as a deodorizer and disinfectant, 813; on the skin and mucous membranes, 814; on the blood,

muscle, nerve, and medulla oblongata, 814; on the spinal cord, respiratory and vaso-motor centres, 814; on the cerebral, sweat and salivary centres, 814; on the temperature, 814; how excreted, 815; poisoning of, treatment, 815; uses of, 815–816
Carbon, symbol and atomic weight of, 9; found in three forms, and in various compounds, 14; its relation to other members of a group, 16; its forms, 541–543
Carbon, bisulphide of, character, action, and uses of, 760
Carbon compounds, fatty series, 759 *et seq.*; properties and general action of, 759, 760; aromatic series, 807–826; general characters of, 807 *et seq.*; action of, 811; their antiseptic and antipyretic power, 811. *See* Hydrocarbons
Carbon monoxide. *See* Carbonic oxide
Carbonates, test for, 594
Carbonate of Ammonium, 640
Bismuth, 733
Lead, 703
Lithium, 631
Magnesium, 658, 660
Potassium, 604, 607
Sodium, 618, 621
Zinc, 667, 670
Carbonate of sodium, action of, on the ear, 229; on the mucus from the trachea, 252; as a poison, with its antidote, 487
Carbonic acid, action of, on protoplasm, 61; as a local anodyne, 201; action of, on the blood, 283; as a refrigerant diuretic, 432; as a poison, with its antidote, 487; as choke-damp, with its antidotes, 487; properties of carbonic acid, 583; action and uses of, 583; effects of, in the mouth, the stomach, and the intestinal canal, 583; poisoning by, 584; has three stages—dyspnœa, convulsions, and paralysis, 584; its treatment, 585
Carbonic oxide, compound with hæmoglobin, 72; action of, on muscles, 127 *et seq.*; on the vagus-centre, 317; effects of poisoning by, on the colour of the blood, 240; as a poison, with its antidote, 486
Cardamoms, as carminatives, 379; as stimulants and carminatives, 1038
Cardiac muscle, drugs which stimulate or depress, 316
Cardiac poisons, action of different kinds of, 308, 316
Cardiac sedatives, nature and action of, 338, 339
Cardiac stimulants, nature and action of and list of the principal, 328
Cardiac tonics, 249; nature of, and list of the principal, 331; conditions and diseases of the heart in which they are most useful, 332–334; the question as to the use of digitalis in aortic regurgitation considered, 333-334; risks attending the administration of digitalis and other cardiac tonics, 335; cimicifuga (black snakeroot) as a cardiac tonic, 837; apocynin and apocynein as, 969
Carlsbad water, probable cause of its efficacy in hepatic diseases, 407; nature and uses of, 625
Carminatives, nature of the action they exert on the stomach, 378, 379; list of the chief, 379; their principal uses, 379; cloves as, 922; asafœtida as, 933; fennel fruit as a, 934; oil of anise as, 935; oil of dill as, 936; oil of caraway as, 937; oil of coriander as, 938; oil of chamomile as, 956; oil of rosemary as, 1003; oil of lavender flowers as, 1004; oil of peppermint as, 1004; oil of spearmint as, 1005; hedeoma or pennyroyal, 1007; expressed oil of nutmeg as, 1016; oil of cinnamon as, 1017; garlic as, 1040; cardamons as, 1038; saffron as, 1039
Carolina pink. *See* Spigelia
Carron oil, origin, composition, and uses of, 649
Carrot as a stimulant diuretic, 433
Casca bark (sassy bark), composition, action, and uses of, 915
Cascara Sagrada as a purgative, 389, 895
Cascarilla, 1022; cascarilla bark as a stimulant, tonic, and expectorant, 1022
Cash, Dr., references to, 45, 124, 129, 135, 137, 142, 150, 280, 281, 493, 606, 974
Cassia, as a laxative, 389; cassia pulp, characters and use, 911; purging cassia, 911
Cassia fistula, 911
Castanea, characters and uses of, 1034
Castor, antispasmodic action of, 214; its characters and therapeutics, 1077
Castor oil, nauseous taste of, owing almost entirely to its odour, 230; as a purgative, 389, 1024; as a vermifuge, 408; characters and preparations of, 1024; composition, action, and uses of, 1024; mode of administration, 1025
Cat, easiest mode of anæsthetising, 210; diagram of curve of the pulse and blood-pressure in a, after division of the spinal cord and injection of erythrophlœum, 273
Catalysis, effects of, on different substances, 73
Cataplasma carbonis, 506, 541, 1053
Conii, 506, 931
Fermenti, 506, 1053, 1073
Lini, 506, 877

Cataplasma—
Sinapis, 506, 864
Sodæ chlorinatæ, 506, 551
Cataplasms, or poultices, 506
Catarrh, with copious secretion of mucus, a combination of morphine and atropine useful in, 250; camphor a popular remedy in common, 331
Catechu, as an astringent, 349; for the teeth and gums, 352, characters, composition and uses of, 914, 951
Cathartics. *See* Purgatives
Catheter, importance of cleansing and disinfecting, 105
Caulophyllum (blue cohosh), character, composition, and uses of, 842
Caustic Ammonia, as a poison, with its antidote, 487; caustic lime, as ditto, 487; caustic potash, or soda, as ditto, 487
Lunar, 676
Mitigated, 677
Potash, 608
Soda, 621
Caustics, nature and uses of, 346; general action of the alkaline group of metals as, 597; alum as a caustic, 654
Celandine. *See* Chelidonium
Celastrineæ, 894
Cells how kept alive, and cause of death of, 262
Cera alba, 1090
Cerates, or ointments, 506
Ceratum, 506, 1084, 1090
Camphoræ, 506, 1018, 1090
Cantharidis, 506, 1084, 1090, 1091
Cetacei, 506, 1085, 1090
Extracti cantharidis, 506, 1084, 1090, 1091
Plumbi subacetatis, 506, 704, 1084, 1090
Resinæ, 506, 1061, 1018, 1090
Sabinæ, 506, 1084, 1090
Cerebellum, action of drugs on the, 215; different kinds of spirits appear to affect different parts of the, 215; action of alcohol on the, 770
Cerebral affections, blisters useful in, 346; circulation, diagram to show the effects on, of rapidly emptying the bladder, 264; stimulants, nature and action of, 192–195; action of carbolic acid on the cerebral centres, 814; tea as a powerful stimulant, 870
Cerium oxalate, as a local sedative, 376; characters, uses, &c. of, 657
Symbol and atomic weight of, 9; physiological action of, 27
Cetaceæ, 1085
Cevadilla, 1046
Chalk, as an astringent, 349; as a dentifrice, 352; as a direct antacid, 370
Chalk, prepared, 647–650; officinal preparations of, 650; mixture of, 650; aromatic powder of, 650; compound powder of, 650; lozenges of, 650; hydrargyrum cum cretâ contains, 650
Chamomile, characters and uses of, 955
German, 956; a bitter, carminative, and anthelmintic, 956; infusion of, 956
Oil of, 955; a tonic, stomachic, and carminative, 956
Chaperon's experiments on inhibitory paralysis, 166
Charcoal, reputed power of, for attracting oxygen, 73; as a deodorizer, or antiseptic, 106; as a dentifrice, 352; action of, on the stomach, 378; chief action of, 541
Charcoal, animal, preparation and constituents of, 542
Purified animal, preparation, characters, and uses of, 542
Wood, its preparation, characters, action, and uses, 541; poultice of, how to make, 541
Charcoal fumes, as a poison, with its antidote, 487
Charta Cantharidis, 506, 1091
Epispastica, 506, 966, 1057, 1061, 1085, 1090, 1091
Potassii nitratis, 507
Sinapis, 507, 864
Cheken, composition, action, and uses of, 923
Chelidonium (celandine), characters, composition, and uses of, 863
Chemical constitution and physiological action, connection between, 30; the most important subject in pharmacology, 32
Chemical reactions, number and nature of, 24; of the metallic elements divided into two groups, 24; which only occur between two bodies when a third is present, 73
Chenopodiaceæ, 1009
Chenopodii, oleum, as a vermifuge, 1009
Chenopodium, characters of, 1009
Cherry-laurel water, as a poison, with its antidote, 489; cherry-laurel leaves, nature, action, and use of, 917
Cherry, wild, as a nervous sedative and tonic, 917
Chestnut. *See* Castanea
Chilies, as carminatives, 379
Chill, or cold, utility of vascular stimulants in, 330; action of, on bronchi, 252
Chimaphila (pipsissewa), as a stimulant diuretic, 433; as an astringent and diuretic, 962
Chinicine, constitution of, 824
Chinoidin (quinoidin), 944
Chinoidinum, 505, 944
Chinoidinæ sulphas, 944
Chinoline, 823
Chiretta, as a bitter tonic, 980

Chloral, action of, on muscle, 128 *et seq.*; as a sedative, 157; diagram to show the action of, on the spinal cord, 160; a useful hypnotic, 199; as a general anodyne, 201, 202; action of, on the respiratory centre, 241; on the brain, 244; on the vessels and circulation, 282; on the vaso-motor centre, 287, 319; on the motor ganglia, 316; on the intestines, 387; as a poison, with its antidotes, 489; antagonistic action of, and strychnine and picrotoxine, 494–495; antagonism of, to other drugs, 492–496
Chloral hydrate, action of, on the nervous system, 204; on the vagus centre, 317; antagonism of, to atropine, 495; preparation and characters of, 790; action of, 791, 792; as an antiseptic, in the mouth, and when injected under the skin, 791; first introduced into medicine by Oscar Liebreich, 791; his speculations regarding its action, 791; its action in the body, 791; in frogs and mammals, 792; on the temperature, respiration, and blood, 792; on the circulation, 792; on muscles and motor nerves, 792; on the spinal cord, 792; on the brain, 792; treatment of poisoning by, 793; chronic chloralism, 793; uses of, 793
Chlorate of potassium, action of, on bacteria, 91, 95; as a remedy for toothache, 353; as an antisialic, 361; action of, on the kidneys, 435; characters, action, and uses of, 613–614
Chlorate of sodium, 627
Chlorides, test for, 594
Chloride of Ammonium, 637
Calcium, 651
Gold, 754
Gold and Sodium, 754
Iron, 745
Sodium, 599–601, 620
Tin, 706
Zinc, 667
Chloride of lime, action of, on enzymes, 78, 79; on bacteria, 93
Chloride of sodium, action of, on bacteria, 95; action of, as compared with bromide of potassium, 214; on the pulsations of the frog's heart, 306; effects of excess of, in the blood, 412; one of the most important constituents of the body, 413
Chlorides, general action of the group of, 599–601
Chlorinated lime, action on bacteria, 91; characters of, &c., 550; solution of, 550; inhalation of, 551
Chlorinated soda, solution of, 551; as a cataplasm of, 551
Chlorine, symbol and atomic weight of, 9; its relation to other members of a group, 16; action of, on infusoria, 65; on enzymes, 77–79; on bacteria, 91, 95; as a poison, with its antidote, 486; general source, characters, and mode of preparation of, 547–552; action of, 549; chlorine water, tests and uses of, 550; chlorinated lime, its characters and uses, 550; solution of chlorinated lime, 551; inhalation of chlorine, 550; solution of chlorinated soda, 551; poultice of ditto, 552; uses of ditto, 552
Chlorine water, action of, on bacteria, 93; nature, action, and uses of, 550
Chloroform, effects of, on the blood, 72; on enzymes, 78; on bacteria, 91, 93; on medusæ, 111; on mammals and leeches, 115; on muscle, 128 *et seq.*; as a sedative, 157; diagram to show the action of, on the spinal cord, 160; action of, on psychical processes, 191; action of, as an anæsthetic, 204 *et seq.*; acts directly on the nerve-cells, 205; dangers arising from the use of, 207–208; mode of administering, 209; action of, on the respiratory centre, 241; on the brain, 244; on the vagus centre, 317; on the vaso-motor centre, 319; on the motor ganglia, 316; as a cardiac stimulant, 328; as a rubefacient, 344; as a sialagogue, 357; as a local sedative, 376; as a carminative, 379; as a poison, with its antidotes, 488; antagonism of, to amyl nitrite, 495; chlorinated lime used in the preparation of, 550; purified, preparation, 795; tests, 796; preparations of, 796; action of, 796; when mixed with albumen, 796; a powerful solvent of protogon, 796; on the blood and skin, 797; on the mouth, stomach, and intestines, 797; the nervous system, 797; its action divided into three stages, 797; its action on the respiration, pulse, heart, and blood-pressure, 798; on the nervous system, 799; dangers in the administration of, 799; precautions to be taken, 800–802; uses of, and various plans for administering, 802, 803. *See* also Anæsthetics
Chloropicrin, action of, on bacteria, 94
Cholagogues, may act as indirect gastric tonics, 365, 369; nature and action of, 390, 400; experiments with, 404–407; adjuncts to, 406; uses of, 407; remove bile from the body, 407
Cholera, corrosive sublimate in, 692; possible use of napthalin in, 822
Chondrus, 1073
Christison, Sir Robert, references to, 42, 852, 855, 999
Chrome alum, action of, on bacteria, 94
Chromic acid, action of, on bacteria, 94, 95; as a caustic, 344; how prepared, 566; characters and action of, as a disinfectant and caustic, 582
Chromium, symbols and atomic weight of, 9

Chrysarobin, 505; characters and uses of, 909
Chrysarobinum, 505, 909
Cicutine, as an antisialic, 361
Cicutoxine, action of, on the accelerating centre, 319; on the vaso-motor centre, 319
Cimicifuga (black snakeroot), characters and composition of, 837; action and uses of, 838; as a stomachic, a cardiac tonic, and an expectorant, 838
Cinchona bark and its alkaloids the chief antiperiodics, 107; the former almost a specific in intermittent fevers, periodic headaches, neuralgias, &c., 107; cinchona alkaloids and their salts, 944; action and uses of, 944–948
Cinchona, characters, &c., of, 939
  Bark, red, 940
  Calisaya bark, yellow, 940
Cinchona, properties and composition of the cinchona barks, 940; physiological action of, 944–948; uses of, 947, 948
Cinchonaceæ, 939
Cinchoneæ, 939
Cinchonidinæ sulphas, 505, 939, 944
Cinchonidine, an antiperiodic, 107; sulphate of, 944
Cinchoninæ sulphas, 505, 939, 943
Cinchonine, 943
  Action of, on oxidation, 92; on the blood, 72; as an antiperiodic, 107; action of, on muscle, 128
  Sulphate of, 943
Cinnamic acid, action of, on bacteria, 94; on the kidneys, 436
Cinnamon and oil, as a carminative, 379
Cinnamon, characters and composition of, 1016
  Aromatic powder of, 1017
  Bark, 1016
  Powder, compound, 1017
  Oil of, 1017; as a carminative and an astringent, 1017
Circulation, action of drugs on the, 262–339; nature of the, in the arteries and veins, 262; effect of blood-pressure on the, 263; arrest of the, causes fainting and shock, 264; schema of the, 265–267; diagram illustrative of this, 266; nature of the, in the living body, 267; effects of variation in blood-pressure on the, 267, 268; method of ascertaining this, 268; alterations in blood-pressure in the, 270; relation of pulse-rate and arterioles to blood-pressure in the, 271–277; diagram of the, 275; method for maintaining artificial, in the rabbit's ear, 280; in the frog, 280; method of measurement of the, by the rate of flow, 281–283; action of potassium salts on the, 606; of strong solution of ammonia, 638; of the heavy metals, 663; of the salts of iron, 663; of antimony, 724; of alcohol, 768; and on the cranial, 769; of the spirit of ether, 781; of chloral hydrate, 792; of salicylic acid, 820; of anemonin, 837; of opium, 855, 861; of pilocarpine, 885; of quinine, 945; of strychnine, 973; of belladonna or atropine, 992; of tobacco, 993; of veratrine, 1048; of colchicum, 1051; of extract of ergot, 1071
Citrate of bismuth, 733; and ammonia, 734
  Caffeine, 870
  Iron, 748
    and ammonium, 748
  Lithium, 632
  Magnesium, 389, 661
  Potassium, 609
  Quinine, 749
  Strychnine, 749
Citrates, test for, 594
Citric acid, properties of, &c., 580; syrup of ditto, 581
Citrine ointment, 695
Citro-tartrate of sodium (effervescent), 623
Clover, Mr., his plan of administering chloroform, 804
Cloves, characters, action, and use of, 922; as a carminative, 922; oil of, 922
Cloves and oil, as a carminative, 379
Clysters, injections, or enemas, 508
Coal gas, as a poison, with its antidotes, 487
Coats, reference to, 278
Cobalt, symbol and atomic weight of, 9; physiological action of, 27; causes slight contraction of the vessels, 281
Cobra poison, action of, on the infusoria, 65; convulsions caused by, 189
Coca. *See* Erythroxylon
Cocainæ Hydrochloras, 504, 877
Cocaine, action of, on muscle, 128; on the eye, 226; antagonism of, to morphine, 494, 495; characters, action, and uses of, 877, 878; as a local anæsthetic, 157, 878; action of, on the nerve-centres in man, 878; is said to lessen fatigue, 878; on animals, on the spinal cord, the respiration, the pulse, blood-pressure, and temperature, 879; uses of, 879
Cocaine hydrochlorate, characters, action, and uses, 877. *See* also Cocaine
Coccus, 1090
Cochineal, 1090; its characters and uses, 1090
Codeina, 504, 844
Codeine, action of, on oxidation, 69; antagonism of, to chloral, 495; characters of, 849; action of, on the nerves and abdominal viscera, 850; on the

spinal cord and motor centre in the brain, 850; uses of, 850; action and use of, in diabetes, 850
Codeïnes, artificial, 859
Cod-liver oil, one of the most efficient expectorants, 254; great virtue of, in chronic bronchitis, 254; a powerful hæmatinic, 411; as an alterative, 413; as an indirect emmenagogue, 453; character, composition, physiological and therapeutic action of, 1087
Cœlospermæ, 937
Coffeæ, 948
Coffee, composition, action, and use of, 950
Cohn's solution for experimenting with bacteria, 90
Colchici radix, 1049
Colchicine, action of, on the respiratory centre, 241; as a hepatic stimulant 403, 405; as an alterative, 413; used in gout, 416; as a refrigerant diuretic, 432; as a poison, with its antidote, 489
Colchicum corm, 1049
Root, 1049
Seeds, 1049; general action of, 1050; special action of, on the skin, brain, and spinal cord, 1050; on the sensory and motor nerves and the muscles, 1051; on the circulation and the secretion of urine, 1051, uses of, 1051; treatment in poisoning by, 1051
Cold, effects of, on the action of drugs, 44–46; on protoplasmic movements, 60; on the action of infusoria, 64; on muscle, 119, 123, 138; extreme, as an anæsthetic, 157; on the action of strychnine, 175; in preventing and inducing sleep, 199; as a local anodyne, 201; applied to the surface of a painful part, relieves the pain, 203; one of the chief local anæsthetics, 204; action of, on the respiratory centres, 241; in causing congestion, 252; apparatus for ascertaining the effect of, on the vessels of the frog's lung, 280; instrument for showing the action of, on the frog's heart, 301; one of the most powerful of vascular and cardiac sedatives, 339; action of, on inflammation, 341; diagram to show the effects of, in lessening the pain of inflammation, 342; as an antipyretic, 418, 420; local application of, 464
Cold bath, as an anaphrodisiac, 451; various uses of, and risks attending, 460–463
Compresses, 465
Douche, ascending, 464
Spinal, 464
Douches, 463
Foot bath, 465
Cold Pack, 463
Colds, arrest of, 256
Coleoptera, 1091
Collidine, in treatment of asthma, 261
Collodion, as a demulcent, 347; and a styptic, 350
Collodion, characters, action, and uses of, 874
Blistering, 874
Cantharidal, 874
Flexible, 874
Styptic, 874
Collodions, 507
Collodium, 507, 780
Flexile, 507, 780, 874, 1024, 1057
Cum cantharide, 507, 874, 1091
Stypticum, 507, 874, 1032
Vesicans, 874
Colocynth, 927
Colocynth as a drastic purgative, 389; as a hepatic stimulant, 403, 405; colocynth pulp, composition, action, and therapeutics of, 927, 928; a powerful cathartic and diuretic, 927, 928
Cologne water, for perfuming, 890
Colophony, 1061
Coma, condition of the veins and brain during, 197
Compositæ, 952
Compound radicals, nature of, 24; most of them possess a paralysing action on the motor nerves, 32
Condurango, characters, action, and uses of, 970
Confectio opii, 507, 844, 901, 936, 1013, 1037
Piperis, 507, 936, 1013, 1089
Rosæ, 507, 920, 1089
Caninæ, 507, 920, 1055
Gallicæ, 507, 920, 1055
Scammonii, 507, 922, 936, 981, 1037, 1089
Sennæ, 507, 899, 910, 911, 917, 938, 1028, 1055
Sulphuris, 507, 544, 610, 901
Terebinthinæ, 507, 899, 1058, 1089
Confections, electuaries, or conserves, 507
Congestion of the internal organs arising from cold, 252; utility of vascular stimulants in, 330
Coniferæ, 1057
Coniïne, effects of, on oxidation, 69; action of, on the spinal cord, 163; as a general anodyne, 201; on the inhibitory powers of the vagi, 310. *See* Hemlock
Conium, as a local and general anodyne, 201; the vapour of, has a local sedative action on the lung, 249; as an anaphrodisiac, 451; as a poison, with its antidotes, 489; nature, actions, and uses of, 931
Conjunctiva of the eye, action of drugs on the, 216
Constipation, cause of, and remedies for,

384; diagram to show how ovarian irritation probably causes, 386; action of opium in, 386; and of small doses of belladonna, 386
Contraction of the pupil of the eye, origin and nature of, 222
Convallamarin, as a cardiac tonic, 331
Convallaria majalis, as a cardiac tonic, 331; composition, action, and uses, 1040
Convolvulaceæ, 980
Convulsions produced by poisoning, 34; and by strychnine and other drugs acting on the spinal cord, 171–181; by the absence or excess of oxygen, 176; whether convulsions are caused by the action of poison on the brain or the spinal cord, 179; certain drugs, when taken, are the cause of, 187; they are usually of spinal or cerebral origin, 188; asphyxial convulsions, 189; experiments to ascertain whether they are asphyxial or not, 189; excitement of the respiratory centre causes, 237; asphyxial, only occur in warm-blooded animals, 237; carbolic acid produces convulsions in frogs, 814
Copaiba, as a stimulant diuretic, 433; value of, in inflammation of the bladder, 446
Copaiva, or copaiba, characters, &c., of, 912; balsam of, 912; oil of, characters, action, and uses of, 912
Copper, sources, reactions, uses, &c., of, 674
  Acetate of, 676
    Test solution of, 676
  Nitrate, 674
  Sub-acetate of, 676
  Sulphate of, 675
    Anhydrous, 675
    Test solution of ammonio-, 676
Copper sulphate, action of, on enzymes, 78; on bacteria, 93; on annulosa, 116; as a caustic, 344, 675; as an astringent, 349; as a local emetic, 373; character, action, and uses of, 674–76
Copper, symbol and atomic weight of, 9; physiological action of, 27; action of, on muscle, 127 *et seq.*; causes powerful contraction of the vessels, 281; double salts of, action of, on the cardiac muscle, 316; on the capillaries, 318; as a poison, with its antidote, 489; nature, action, and uses of, 674–76
Coriander, characters of, 937
  Fruit, 937
  Oil of, a carminative and stimulant, 379, 938
Cornaceæ, 938
Cornea, chief drugs employed in disease of the, 216; action of alum on, 216, 655
Corn-smut, 1073
Cornus, characters and action of, 938
Cornutine, 1069
Corollifloræ, 939
Corrosive chloride of mercury, 692
Corrosive sublimate, action of, on infusoria, 65; on enzymes, 78, 79; on bacteria, 89, 91, 93, 95; extraordinary destructive power of, might be useful in destroying bacilli, 102; owes its curative power in cases of infantile dysentery to its antiseptic action, 106; the only trustworthy disinfectant for destroying septic organisms, 106; as a poison, with its antidotes, 489; nature and uses of, 692, 693; one of the most powerful antiseptics known, 693; use of, in cholera, 692; poisoning by, and treatment for, 693
Coto alkaloids, action of, on the intestines, 386; Albertoni's investigations regarding the action of the, 386
Coto bark, composition, action, and uses of, 1017; paracoto bark, 1017
Cotoine, action of, on the intestines, 387
Cotton, gun, preparation and uses of, 873
  Root bark, characters, action, and uses of, 872
  Seed oil, characters and uses of, 872
  Wool, what derived from, 873
Couch-grass, as a demulcent, 1054
Cough, chest and stomach, pathology of, remedies for, and general treatment of, 246–261; diagram of the afferent nerves by which it may be excited, 247; action and use of expectorants in, 250, 255; of emetics, 255; of warmth and moisture, 255; of respirators, 256; of warm clothing, friction, liniments, poultices, and plasters, 256; selection of remedies in treatment of, 257; action of lactucarium in allaying, 957
Cowling, Dr., his rule for dosage, 497
Cramps of the muscles, cause and general treatment of, 212, 213
Cranesbill, 881
Cranial circulation, 192; action of alcohol on the, 769
Cream of tartar, nature and uses of, 610
Creasote, action of, on infusoria, 65; no effect on ptyalin, 77; on enzymes, 78, 79; on yeast and bacteria, 79; as a local anodyne, 201; as a remedy for toothache, 353; as a local sedative, 376; as a poison, with its antidote, 489; characters, tests, and preparations of, 817; action of, as a muscular poison, 817; on the blood, skin, and mouth, 817; on the pulse, respiration, and urine, 817; uses of, 817
Creta, 647. *See* also Chalk
Croix, N. de la, results of his experiments with different drugs on bacteria, 90, 91

Croton oil, as a pustulant, 344; as a drastic purgative, 389; as a poison, with its antidote, 489; action of, externally and internally, 1023; use of, ditto, 1023; treatment of poisoning by, 1024
Cruciferæ, 864
Crum-Brown, reference to, 150, 859
Crumb of bread, 1053
Cryptogams (sub-kingdom II.), 1066–1073; filices, 1066; lichens, 1067; fungi, 1067; algæ, 1073
Cubeba, 1013
Cubebs, as a sialagogue, 357; as a stimulant diuretic, 433; characters and composition of, 1013
Oleoresin of, preparation, action, and uses of, 1014; as a stimulant diuretic, 1014
Oil of, 1014
Cucumber fruit, squirting, 928
Cucurbitaceæ, 927
Culver's root. *See* Leptandra
Cumarin, action of, on the cardiac muscle, as an antipyretic, 316
Cupping, wet, 420
Cupuliferæ, 1030
Curare, physiological action of, on the endings of efferent nerves, 26; when applied externally and internally, 33, 34; opposite effect of, when differently administered, 38; effects of, on the blood, 73; on mollusca, 114; on muscle, 122, 128, 146, 147; list of drugs which have a similar action to, on the motor nerves, 150, 151; exact localisation of action, 151; on the muscles of respiration, 238; on the vaso-motor nerves, 284; on the inhibitory power of the vagi, 310; on the vagus ends in the heart, 317; on the nerves of the salivary gland, 355; action of the liver on, 405; as a poison, with its antidote, 489; characters, composition, and action of, 976; on the motor nerves, vagus, and sensory nerves, 976; on the spinal cord, muscles and vessels, 976; on the blood-pressure and on salivation, 976; effects of, on the general system, 977; uses of, 977
Curd soap, 1079
Cusparia or Angostura bark, character, 881; composition, tests, action, and use, 882
Cyanide of potassium, action of, on medusæ, 112; as a poison, with its antidote, 489
Cyanide of silver, 679; of mercury, 697;
Cyanogen, action of, on the motor ganglia, 316
Cydonium, characters and use of, 921
Cypripedium, characters and use of, as an antispasmodic, 1036

D.

Da Costa, Dr., reference to, 338
Dandelion, protoplasm of, experiment with, on oxygen, 69
Dandelion root, characters and action of, 956; on the liver, and as a diuretic, 957
Dastre, reference to, 277, 298
Daturine, as a mydriatic, 219; action of, on the vagus centre, 317; on the vaso-motor centre, 319; on the inhibitory ganglia, 317; antagonism of, to morphine, 496; nature, action, and use of, 991
Davy, Sir H., split up some supposed elements into oxygen and a metal, 11; his observation on the properties of nitrous oxide, 211
Dead space, 1100 (Appendix)
Decoction of lemon, as an antiperiodic, 891
Decoctions, 507
Decoctum, Aloes compositum, 507, 893, 899, 1039, 1042
Cetrariæ, 507, 1067
Cinchonæ, 507, 941
Granati radicis, 507, 926
Hæmatoxyli, 507, 908, 1016
Hordei, 507, 1054
Papaveris, 507, 843
Pareiræ, 507, 841
Quercus, 507, 1030
Sarsæ, 508, 1052
Sarsæ compositum, 508, 880, 899, 1020, 1022, 1052
Sarsaparillæ compositum, 508, 880, 1020, 1022, 1052
Scoparii, 508, 900
Taraxaci, 508, 957
Delirium tremens, cause, symptoms, and treatment of, 771, 772
Delphinine, action of, on the frog's heart, 306; on the accelerating centre, 318; on the vaso-motor centre, 319; nature, action, and use of, 836
Demulcents, nature, action, and therapeutic uses of, 347, 348; althæa as a, 875; linseed as a demulcent, 876; liquorice root as a demulcent, 900; gum acacia, or arabica, as a, 914; quince seed as a, 922; sassafras pith as a, 1020; elm as, 1026, triticum as, 1054; Iceland moss as, 1067; chondrus as, 1073
Deodorisers or deodorants, nature and action of, 103, 106; iodoform as a, 805; carbolic acid as a, 813
Desmobacteria, 83
Dew-Smith, reference to, 114
Diabetes, action of codeine in, 850
Diaphoretics, action of, on the secretion of sweat, 437; antimony as a diaphoretic, 726; eupatorium as a, 956; ipecacuanha as, 950; asclepias as a, 970; melissa or balm as, 1007; origanum

as, 1007; camphor as, 1019; oil of sassafras as, 1020; serpentary root as, 1012
Diarrhœa, astringents have a powerful effect in checking, 350
Diastase, 75
Dickenson, reference to, 1001
Didymium, symbol and atomic weight of, 10
Diedrich, references to, 857
Diedülin, reference to, 150
Digestive System, Action of Drugs on the, 352–409; on the teeth, 352; on the saliva, as sialagogues, 353–359; on thirst, as refrigerants, 360; on the salivary secretion, as antisialics, 360; on the appetite, as gastric tonics, 361–369; on acidity, as antacids, 369; on vomiting, as emetics, 370–376; on the stomach, as gastric sedatives, 376; on the gases of the stomach, as carminatives, 378, 379; on the intestines, 379–388; as purgatives, 388–395; as irritant poisons, 395–399; on the liver, 399–407; on the pancreas, 407; on the intestines, as anthelmintics, 408
Digestive tract, application of drugs to the, 482–485; by the mouth and pharynx, 482; as masticatories, 482; as gargles, 482; by the stomach, 482; by the stomach-pump, 483; by the gastric syphon, 483; to the intestine, 484; as enemata, 484; as suppositories, 484; action of opium on the, 860; action of digitalin on the, 997
Digestives, when necessary, 411
Digitalin, effects of, on medusæ, 111; action of, on the vision, 228; on the frog's heart, 307; on the vagus centre, 317; on the cardiac muscle, 316; as a cardiac tonic, 331; antagonistic action of, 494, 495; preparation and characters, 994; chemistry of, 995; general action of, 995; special action of, on the muscles, nervous system, and spinal cord, 995; on the brain, respiration, and blood-pressure, 996; on the heart and arterioles, 996; diagram of a pulse-wave before and after injection of, in a dog, 997; on the vagus-roots and ends, 996; peculiar action of, on the frog's heart, 996; on the digestive organs and the urine, 997; effect of temperature on the action of, 998; diagram showing effects of rise of temperature alone, 998; ditto, showing effects of rise, after injection of, 998; ditto, showing action of, after temperature, 999; action of different preparations of, 999; uses of, 1000; precautions, 1001; treatment of poisoning by, 1001
Digitalinum, 994
Digitalis, effect of varied quantities of, on the pulse, 37; cumulative action of, 42; has sometimes no action on the pulse in pneumonia, 47; acts differently on the heart of a frog from that of mammals, 54; action of, on oxidation, 70; on mollusca, 114; action of, on the brain, 198; as a cardiac tonic, 249; as a vascular tonic, 254; diagram showing the blood-pressure and form of the pulse-wave before and after the injection of, in the dog, 276; on the vagus centre, 317; on the cardiac muscle, 316; on the capillaries, 318; on the heart, as a cardiac tonic, 331, 333; the question of the use of, in aortic regurgitation considered, 333; caution to be observed in the use of, as a cardiac tonic, 335; as a vascular tonic, 336; as a sedative, 339; as a styptic acting on the blood-vessels, 350; has the power of lessening or arresting hæmorrhage, 351; as a general emetic, 373; experiment with, on blood-pressure, 430; as a hydragogue diuretic, 432; as an anaphrodisiac, 451; as a direct emmenagogue, 453; as a poison, with its antidotes, 489; antagonism of, to other drugs, 494, 495
Digitalis (foxglove), characters, &c., of, 994
Leaf, 994
Digitin, composition of, 995
Digitonin, composition of, 995
Digitoxin, composition of, 995; action of, on the cardiac muscle, 316; as a cardiac tonic, 331. *See* Digitalis
Dilatation of the pupil of the eye, origin and nature of, 219–222
Dilator muscle of the iris, nature and functions of, 217
Dill, as a stimulant diuretic, 433
Dill and oil, as a carminative, 379
Dill, fruit, characters and use of, as a carminative, 936
Oil of, 936
Dimethylamine, 100
Dimethyl-coniïne, 932
Diosmeæ, 882
Diseases caused by mould-fungi, 82; by bacteria, 82
Disinfectants, Koch's experiments on bacteria with, 92–96; nature and action of, 103, 106; superheated steam the best disinfectant under ordinary circumstances, 106; borax as a disinfectant, 625; carbolic acid as a, 813; thymol as, 1006
Distilled water, action of, on bacteria, 93; and calcium salts, on the frog's heart, 306; as a lithontriptic, 436
Diuretics nature and mode of action of, 431; list of refrigerant, hydragogue and stimulant, 432, 433; saline, action of, 433; uses of, 433; adjuvants to, 434; alkalies as, 599; iodide of ethyl as a diuretic, 790; caulophyllum as, 843

caffeine as a, 872; tansy as, 954; dandelion root as, 957; uva ursa as, 962; chimaphila as, 962; benzoic acid as, 965; serpentary root as, 1012; thuja as, 1063; oil of juniper as, 1064; sarsaparilla as, 1052; garlic as, 1040; squill as, 1041
Di-toluyl-diethyl ammonium iodide, action on motor nerves, 150
Dogiel, references to, 287, 295
Dog-rose, fruit of the, 920
Dogs, experiments with drugs on, 54–56; Majendie's series of experiments on the action of strychnine on the reflex powers of the spinal cord of, 177 *et seq.*; easiest way of anæsthetising, 210; diagram of a stopcock by which air or vapour, or two kinds of gas, may be given to, 211; diagram showing the blood-pressure and form of the pulse-wave before and after the injection of digitalis in, 276; action of the heart in, 287; difference between rabbits and, in this respect, 287; cause of the stoppage of the heart in, 297; effects of large doses of opium injected into, 384; diagram of a pulse-wave before and after injection of digitalis in, 997; action of, on, 997
Dogwood, 938; dogwood quinine, 938
Jamaica, action and use of, 913
Donaldson, reference to, 996
Donovan's solution, 721
Dosage, the rules which affect correct, 497
Dose, nature, size, and effects of a, on the system, 37; rules which regulate the amount of a, for children and adults, 497; Dr. Young's rule, 497; Dr. Cowling's, 497; the author's proposed modification of Dr. Cowling's, 497
Douche, nasal, diagram of a, 478
Douches, cold, nature and uses of, 463; the spinal, 464; the ascending, 464
Dover's powder, as a vascular stimulant, 330, 331; as a sudorific, 421; in combination with mercury, 688; ten grains of, useful when a cold is coming on, 860; will cause diaphoresis, 861
Dropsy, the pathology of, 336, 337; diagram of Ranvier's experiment on, 336; the principal causes of, 336; and drugs that are useful in, 336, 337; usefulness of upward friction in, 345
Drugs, reaction between, and the various parts of the body, 5; changes undergone by, in the body, 5; physiological action of, depends chiefly upon their power of acting on one tissue or organ first, 26; the effects produced by large and moderate doses of veratrine on the frog an example of this, 26; effect of artificially modifying the chemical constitution of, 32; CIRCUMSTANCES WHICH AFFECT THE ACTION OF, ON THE ORGANISM, 33–56; direct and indirect action of, 34; local and remote action of, 33; relation of effect to quantity employed, 36; the doctrine of homœopathy in, 36; the dose, 37; size, 37; and mode of administration of, 38; difference betwixt venous and subcutaneous injection and absorption by the stomach, 38–40; action of the liver on, 39; absorption and excretion of, 39–40; cumulative action of, 41; effect of different preparations of, 42; of fasting on the action of, 43; of habit, 43; of temperature, 44; effect of temperature on the action of, on the spinal cord, 46; the proper definition of the action of, is the reaction between them and the various parts of the body at a certain temperature, 47; effects of climate on, 48; time of day, 48; season, 48; and disease, 49; use of experiments in the administration of, 49; effects of idiosyncrasies on the power of, 51; objections to experiments, 53; difference in the effect of, on men and animals, and on different animals, 53–55; erroneous deductions from, 55, 56; ACTION OF, ON PROTOPLASM, BLOOD, AND LOW ORGANISMS, 57–108; on albumen, 57; on protoplasmic movements, 59–63; on infusoria, 63–65; relations of motion and oxidation to, 65–70; action of, on oxidation, 69; on the blood, 70–73; on enzymes, 75–79; on the movements of bacteria, 88; on the reproduction of bacteria in general, 89; and on the destruction of the germs, 89; table of the comparative action of different, on bacteria, 90, 91; action of, on particular species of, 92; mode of experimenting on the action of, on the reproduction of bacteria, 92; Koch's experiments with three groups of disinfectants on bacteria, 93; action of, on the development and growth of bacilli, 95; strength of various disinfectants required to prevent the development of anthrax bacilli, 95; effect of, on the action of bacteria in the animal body, 102; ACTION OF, ON INVERTEBRATA, 109–116; on the medusæ, 109–113; on mollusca, 114; on ascidians, 114; on annulosa, 114; ON MUSCLE, 117–143; on voluntary muscle, 117; as poisons to the muscles, 126–131; the action of, on muscle is relative, not absolute, 136; on involuntary muscular fibre, 137; hypothetical considerations regarding the action on muscles, 141; ON NERVES, 144–158; on motor nerves, 146; on motor nerve-endings, 147; on the trunks of motor nerves, 154; on sen-

sory nerves, 155; on the peripheral ends of the sensory nerves, 157; ON THE SPINAL CORD, 159–182; on the conducting power of the cord, 159; on the reflex action of the cord, 160, 163; direct, indirect, and inhibitory paralysis of the cord by, 164–171; explanation of the action of certain drugs on a given hypothesis, 171–177; stimulating action of, on the reflex powers of the cord, 177–181; ON THE BRAIN, 183–215; depressant action of, on the motor centres, 187; irritant action of, on the motor centres in the brain, 188; action of, on the sensory and psychical centres in the brain, 191–215; drugs which increase the functional activity of the brain, 192; nerve stimulants, 192; cerebral stimulants, 192; which lessen the functional activity of the brain, 195; hypnotics, or soporifics, 196; narcotics, 200; anodynes, or analgesics, 201; anæsthetics, 203–211; antispasmodics, 212; action of drugs on the cerebellum, 215; ON THE ORGANS OF SPECIAL SENSE, 216–231; on the eye, 216; on the conjunctiva, 216; on the lacrimal secretion, 217; on the pupil, 217–223; on accommodation, 225; on intra-ocular pressure, 226; on the sensibility of the eye, 227; in producing visions, 228; on hearing, 228; on smell, 230; on taste, 230; ON RESPIRATION, 232–261; action of, when injected into the jugular veins, 239; on the respiratory centre, 240–244; on the respiratory nerves, 244–257; ON THE CIRCULATION, 262–339; method of ascertaining the action of, on the circulation, 268–270; diagrams illustrative of this, 272–276; investigation of the action of, on the arterioles, 277–280; another method of ascertaining the action of, on the blood-vessels, 280–283; action of, on the vaso-motor and vaso-dilating nerves, 283; on reflex contraction of vessels, 286; as the cause of alteration in blood-pressure and pulse-rate, 293; on the pulse-rate, 295; on the cardio-inhibitory functions of the vagus, 295; on the reflex stimulation of the vagus, 296; on vagus-roots, 297; on the heart of the frog, 299–305; on the muscular substance of the heart, 305–310; on the vagus in the frog, 310; on inhibition of the heart, 310–312; theories regarding the mode of action of, upon the heart, 312–315; diagram to illustrate the action of, on the various parts of the circulatory apparatus, 315; on the vagus-centre, 317; on the accelerating and vaso-motor centres, 318, 319; on the vagus-ends in the heart, 317; on the inhibitory and motor ganglia, 316, 317; on the cardiac muscle, 316; on the vaso-motor nerves, 318; on the capillaries, 318; various experiments with, on the heart of a frog, 319–328; therapeutic use of, acting on the circulation, 328–339; as cardiac stimulants, 328; as vascular stimulants, 330; as cardiac tonics, 331–335; as vascular tonics, 335; as cardiac sedatives, 338; as vascular sedatives, 339; ACTION OF, ACTING ON THE SURFACE OF THE BODY, 340–351; as irritants and counter-irritants, 340–347; as rubefacients, 344, 345; as vesicants; 344, 345; as pustulants and caustics, 344, 346; as emollients and demulcents, 347–348; as astringents, 349–350; as styptics, 350, 351; ACTION OF, ON THE DIGESTIVE SYSTEM, 352–409; on the teeth, 352; as sialagogues, 353–359; as refrigerants, 360; as antisialics, 360; as gastric tonics, 361; on the secretion of the stomach, 363; on the movements of the stomach, 365; as antacids, 369; as emetics, 370–376; as gastric sedatives and anti-emetics, 376; as carminatives, 378, 379; action of, on the intestines, 379–409; on absorption from the intestines, 386; as intestinal astringents, 387; as purgatives, 388–395; as irritant poisons, 395–399; action of, on the liver, 399; as hepatic stimulants, 402; as cholagogues, 404–407; as hepatic depressants, 407; action of, on the pancreas, 407; as anthelmintics, 408; ON TISSUE-CHANGE, 410–421; as tonics, 410; ON EXCRETION, 422–445, on the kidneys, 422 *et seq.*; as diuretics, 431–434; in albuminuria, 434; as lithontriptics, 436; on the skin as diaphoretics and sudorifics, 437–441; as antihidrotics or anhidrotics, 441–443; on the bladder, 443–446; ON THE GENERATIVE SYSTEM, 447–456; as aphrodisiacs and anaphrodisiacs, 447–453; as emmenagogues and ecbolics, 452–455; upon milk, 455, 456; METHODS OF ADMINISTERING, 457–485; by the skin, 457 *et seq.*; as baths, 459; cold baths, 460–466; warm baths, 466; medicated baths, 469; vapour baths, 470; air baths, 471; friction and inunction, 472; endermic application of, 474; hypodermic administration of, 474; application of, to the eye, 477; to the ear, 477; to the nose, 478; to the larynx, 479; to the lungs, 481; to the digestive tract, 482; to the urethra, 484; to the vagina and uterus, 485; as antidotes, 486–491; antagonistic action of, 492–496; table showing the antagonism of, 495–496

Drunkenness, general effects of, 767 *et seq.*; causes and treatment of, 772
Duboisine, action of, as a mydriatic, 219; on the respiratory centre, 240; on the inhibitory ganglia, 317
Dujardin-Beaumetz, reference to, 1030
Dulcamara, characters, action, and uses of, 983; action of, on the nervous system, heart, respiration, and temperature, 983; as an alterative, 984
Dumas, M., points out a curious relationship between the potassium and the lithium group of elements, 17
Dyad metals, 644 *et seq.*
Dyspepsia, atonic, slight stimulants produce appetite in, 363
Dyspnœa, nature and cause of, 237–240; action of aconitine on, 833

E.

Ear, various diseases of the, and their treatment, 228, 229; action of salicylic acid on the, 820; application of drugs to the, 477; diagram of a vulcanite syringe for injecting solutions into the, 477; action of pilocarpine on the, 884
Eau de Cologne, as a cardiac stimulant, 328; as a general stimulant, 890; uses of, in headache, fainting, &c., 773
Ecbolics, nature and action of, 452; list of the chief, 454; uses of, 454; adjuncts to, 455
Eckhard, references to, 174, 175, 284
Egg-albumin, 1085
Yolk of, 1085
Elaterin, characters and action of, 929; a powerful hydragogue cathartic, 929; action of, on the nervous system, 929
Elaterinum, 505
Elaterium, as a drastic purgative, 389; and a hydragogue, 390; characters and composition of, 929
Elder, characters and uses of, 939
Flowers, 939
Elecampane, 959
Electricity, effects of, on the protoplasmic movements, 60, 61; on the action of infusoria, 64
Elements composing the earth, list of the, with their symbols and atomic weights, 9, 10; nature of the, 11; recent spectroscopic researches prove them to be compounds, 13; dissociation of the, 12; spectrum analysis of the, 11–15; evolution of the, 15; classification of the, 15; according to their atomic weight, 16; in groups, 17; in series, 17; Mendelejeff's classification, 19; differences between the even and the uneven series, 18; the classification in series not yet perfect, 20; general relations of the, 20–32; organic radicals, 20; chemical reactions of the, 24; physiological reactions of the, 24; the latter divided into groups, 25; relation between atomic weight and physiological action, 28; between spectroscopic characters and physiological action, 27; connection between chemical constitution and physiological action, 32; relation between isomorphism and physiological action, 26; Blake's division of the, into nine groups, according to their physiological action, 27; his classification and conclusions cannot be accepted as final, 27
Elemi, nature and use of, 893
Elixir aurantii, 508, 889
Elixirs, 508
Elm, characters and uses of, 1025; as a demulcent, astringent, and tonic, 1026
Slippery, 1025; characters of, 1025
Embrocations or liniments, 515
Emetics, aid the action of antiperiodics, and sometimes cure ague without their aid, 108; powerful adjuncts to expectorants, 255; nature and action of 370; divided into two classes, local and general, 373; the various uses of, 374–376; in simply emptying the stomach, 374; in expelling foreign bodies from it, 374; in removing the contents of it, 374; in removing poison from it, 374; and bile, 374; and obstructions from the air-passages, 375; contra-indications of, 375; anti-, 376; salt as an emetic, 620; alum as, 655; sulphate and acetate of zinc as, 668; sulphate of copper as, 344, 675; subsulphate of mercury as, 690; antimony as, 725; hydrochlorate of apomorphine as, 849; mustard as a prompt and direct, 865; ipecacuanha as an, 950; phytolacca root as, 1009; iris as, 1039
Emetine, action of, on muscle, 128; as a depressant expectorant, 255; action of, on the cardiac muscle, 316; as a general emetic, 373
Emmenagogues, nature and action of, 452; list of indirect and direct, 453; caulophyllum as an emmenagogue, 843; oil of rue as an, 881; tansy as, 954; hedeoma or pennyroyal as, 1007; origanum as, 1007
Emollients, nature, action, and therapeutic uses of, 347, 348
Emphysema, with copious secretion of mucus, a combination of morphine and atropine useful in, 250
Empirical therapeutics, explanation and example of, 3
Emplastrum ammoniaci, 508, 934
cum Hydrargyro, 508, 686, 702, 934, 966

Emplastrum Arnicæ, 508, 958, 966
Asafœtidæ, 508, 702, 933, 966
Belladonnæ, 508, 966, 985
Calefaciens, 508, 1016, 1061, 1090, 1091
Cantharidis, 508, 1061, 1078, 1084
Capsici, 508, 966, 984
Ferri, 508, 702, 743, 966
Galbani, 508, 702, 933, 966, 1090
Hydrargyri, 508, 686, 966
Ichthyocollæ, 508, 1086
Opii, 508, 702, 844, 845, 966, 1061
Picis, 508, 966, 1016, 1057, 1061, 1062, 1090
Burgundicæ, 508, 1062
Canadensis, 508, 1062
cum Cantharide, 508, 1062
Plumbi, 508, 702, 966
Iodidi, 508, 705
Resinæ, 508, 702, 966, 1061, 1079
Saponis, 508, 578, 702, 966, 1061, 1079
Fuscum, 966, 1079, 1090
Endermic application of drugs, 474
Endocarditis, ulcerative, micrococci present in, 99
Enema Aloes, 509, 1042, 1044
Asafœtidæ, 509, 932
Magnesii sulphatis, 509, 966
Opii, 509, 844
Tabaci, 509
Terebinthinæ, 509, 1058
Enemas, injections, or clysters, 508; nature and uses of, 484
Engelmann, reference to, 138
Enzymes, nature of, 75; action of drugs on, 76; functions of, 76; list of the chief, in the animal body, 76; method of ascertaining the action of drugs on, 76; table and diagram showing the different action of drugs on different, 78, 79; methods of liberating from zymogens, 80; alteratives supposed to alter in some way the action of, 413
Epidermic application of drugs, 457
Epsom salts, 659
Erbium, symbol and atomic weight of, 10
Ergot, action of, on the vaso-motor centre, 319; on the motor ganglia, 316; as a vascular sedative, 339; as a styptic acting on the blood-vessels, 350; has the power of lessening or arresting hæmorrhage, 351; as a direct emmenagogue, 453; one of the chief ecbolics, 454; as a poison, with its antidotes, 489; its characters, composition, and general action, 1068, 1069; special action, 1070
Ergot, characters and preparations, 1068, 1069
Ergotin, extract of, its action on the nervous system, muscles, and sensory nerves, 1071; on the circulation and heart, 1071; on the vaso-motor system, respiration, and secretion, 1071; on the alimentary canal and uterus, 1072; therapeutics, 1072
Ergot of rye, 1068
Ergotinic acid, 1069
Ergotinin, 1069
Ergotinum, 505
Ergotism, symptoms of, 1069, 1070
Ericaceæ, 961
Erysipelas, caused by micrococci, 99
Erythrophlœin, as a cardiac tonic, 331
Erythrophlœum, state of the pulse and blood-pressure in a cat after division of the spinal cord and injection of, 273; action of, on the vagus-roots, 296; on the cardiac muscle, 316; as a cardiac tonic, 331; diagram showing the effect of, upon the blood-pressure and secretion of urine, 430; as a hydragogue diuretic, 432
Erythroxylaceæ, 877
Erythroxylon (coca), characters and composition of, 877; action of, as a powerful local anæsthetic, 878; on the nerve-centres, respiration, pulse, and blood-pressure, 878, 879; on mammals, 878; on the secretion of saliva and sweat, 879; on the urine and temperature, 879; uses of, 879
Escharotics, acids as, 568
Esmarch, reference to, 801
Essences, 509
Essentia Anisi, 509, 935
Menthæ piperitæ, 509, 1004
Ether, action of, on bacteria, 93; on annulosa, 115; on muscle, 128 *et seq.*; on psychical processes, 191; nature of narcosis by, 204; first used as an anæsthetic in dentistry, 212: as an antispasmodic, 213; action of, on the respiratory centre, 241; on the brain, 244; on the vaso-motor centre, 319; on the motor ganglia, 316; as a cardiac stimulant, 328, 329; as a vascular stimulant, 330; as a rubefacient, 344: as a sialagogue, 357; as a local sedative, 376; and acetic acid, as a carminative, 379; action of, on the vascularity of and absorption in the intestines, 386; as a poison, with its antidotes, 488; its preparation, character, and uses, 780; action of, on the skin, 781; mouth, stomach, and intestine, 781; cerebral hemispheres, spinal cord, and medulla oblongata, 782; muscles, nerves, and blood, 782; and heart, 782; difference between chloroform and, 782
Ether, simple and saline—
Acetic, 780, 783
Amyl, nitrite of, 784
Compound spirit of, 783
Nitro-glycerine (glonoine), 788

Ether, oil of, 783
Pure, 780
Spirit of, 781
Nitrous, 784
Stronger, 781
Ether spray as an anæsthetic, 157
Ethereal oils, action of, on bacteria, 103
Ethyl, iodide of, preparation and characters of, 790; action and uses of, as an anæsthetic, alterative, diuretic, antispasmodic, 790; mode of administration, 790
Ethyl-atropine, action of, on the motor nerves, &c., 989
Ethyl-carbamate. *See* Urethane
Eucalyptol, action of, on bacteria, 95; as a disinfectant, 106; and antiperiodic, 107; as a vermicide, 408
Eucalyptus, character, action, and uses of, 925; oil of, 925; action of, as an antiseptic, 925; on the blood, spleen, and skin, 925; effects of, when swallowed, 925; action of, on the nerve-centres, spinal cord, 925; brain, medulla, and heart, 925; on the temperature, 925; how excreted, and uses of, 926
Eucalyptus oil, action of, on enzymes, 78; on bacteria, 91; use in blood-poisoning, 106, 926
Eulenberg, references to, 40, 204
Euonymin, as a cholagogue, 390; as a hepatic stimulant, 403
Euonymus (wahoo), nature and action of, 894; acts as a hepatic stimulant, &c., 895
Eupatorium, characters and use of, 956; as a tonic, diaphoretic, emetic, and cathartic, 956
Euphorbiaceæ, 1022
Euphorbium, action of, on the nose, 245; as a vesicant, 344
Eustachian tube, the, some diseases of, and their treatment, 229
Evolution of species and of elements, 15
Ewald, A., reference to, 176
Ewers, references to, 245, 296
EXCRETION, ACTION OF DRUGS ON, 422–446
Expectorants, nature and action of, 250–255; action of, on the secretions of the air-passages and the mucous membranes, 250, 251; on the expulsive mechanism, 254; list of depressant, 255; of stimulating, 255; adjuncts to, 255; antimony as an expectorant, 726; cimicifuga (black snakeroot) as an, 838; senega root as a stimulating, 868; myrrh as, 893; balsam of Peru as, 903; balsam of Tolu as, 903; cheken as, 923; galbanum and ammoniacum as, 933; ipecacuanha as, 950; benzoic acid as, 965; marrubium as, 1007; cascarilla bark as, 1022; garlic as, 1040; squill as, 1041
Experiments, use of, 49; upon healthy man, 51; fallacies, 52; in disease, 52; objections to, answered, 53–55; erroneous deductions from, 55, 56; mode of conducting, for examining the action of drugs on infusoria, 63; for testing the oxidising power of protoplasm, 68; the action of drugs on oxidation, 69; the action of drugs on alcoholic fermentation, 81; on the movements of bacteria, 88; on the destruction of germs, 89; on the action of drugs on the reproduction of bacilli, 92; and on the development and growth of bacilli, 95; for testing the action of drugs on the motor nerves, 147–149; on the reflex action of the spinal cord, 163, 164; on the respiratory centre, 240; on the action of drugs on the circulation, 262–268; on blood-pressure, 268–270; on the action of heat and cold on the frog's lung, 278–280; on the action of the heart on blood-pressure, 292; on the heart of the frog, 299–303; Stannius's, on the action of the various cavities on the frog's heart, 319; Ranvier's, on dropsy, 336
Expressed oil of nutmeg, 1016
Extract of ergot, 1069
Extract of malt, 1054
Extracts, 509; fluid or liquid extracts, 510; fresh or green extract, 512
Extractum, Aconiti, 510, 513, 831, 832
Fluidum, 511, 832
Alcoholicum, 985
Aloes aquosum, 510, 1042
Barbadensis, 510, 1044
Socotrinæ, 510, 1042
Anthemidis, 510, 955
Arnicæ Radicis, 510, 958
Fluidum, 511, 958
Aromaticum fluidum, 511
Aurantii amari, 511
Fluidum, 888
Belæ liquidum, 510, 892
Belladonnæ, 985
Belladonnæ fluidum, 510, 511, 513
Alcoholicum, 510, 985
Brayeræ fluidum, 511, 921
Buchu fluidum, 511, 882
Calami fluidum, 511, 1053
Calumbæ, 841
Fluidum, 841
Cannabis Indicæ, 1026
Fluidum, 510, 511, 1026
Capsici fluidum, 511, 984
Castaneæ fluidum, 511, 1034
Cheken fluidum, 924
Chimaphila, 962
Fluidum, 511, 962
Chiratæ fluidum, 511, 980
Cimicifugæ fluidum, 511, 837
Cinchonæ, 940
Liquidum, 941, 967

Extractum Cinchonæ Flavæ liquidum, 510
Fluidum, 510, 511, 940
Cocæ liquidum, 877
Colchici, 510, 513, 1049
Aceticum, 510, 513, 577, 1049
Radicis, 1049
Radicis fluidum, 510, 511, 1049
Seminis fluidum, 511, 1050
Colocynthidis, 510, 928
Compositum, 510, 928, 981, 1042, 1043, 1038, 1079
Conii, 931
Alcoholicum, 510, 931
Fluidum, 510, 511, 513, 931
Cornus fluidum, 511, 938
Cubebæ fluidum, 511, 1014
Cypripedii fluidum, 511, 1036
Digitalis, 994
Fluidum, 511, 994
Dulcamaræ fluidum, 511, 983
Ergotæ, 1069
Ergotæ fluidum, 510, 511, 1069
Liquidum, 510, 1069
Erythroxyli fluidum, 511, 877
Eucalypti fluidum, 511, 925
Euonymi, 510, 895
Eupatorii fluidum, 511, 956
Filicis liquidum, 511, 1066
Frangulæ fluidum, 511, 896
Gelsemii alcoholicum, 978
Fluidum, 511, 978
Gentianæ, 979
Fluidum, 510, 511, 979
Geranii fluidum, 511, 881
Glycyrrhizæ, 899
Fluidum, 510, 511, 899
Glycyrrhizæ Liquidum, 511, 899
Purum, 510, 899
Gossypii radicis fluidum, 511, 872
Grindeliæ fluidum, 511, 959
Guaranæ fluidum, 511, 897
Hæmatoxyli, 510, 908
Hamamelidis fluidum, 511, 1029
Hydrastis fluidum, 511, 839
Hyoscyami, 990
Alcoholicum, 510, 990
Fluidum, 510, 511, 513, 990
Ipecacuanhæ fluidum, 511, 949
Iridis, 1039
Iridis fluidum, 510, 511, 1039
Jaborandi, 883
Jalapæ, 510, 982
Juglandis, 510, 1029
Krameriæ, 868
Fluidum, 511, 868
Lactucæ, 510, 513, 957
Lactucarii fluidum, 511, 957
Leptandræ, 1002
Fluidum, 510, 511, 1002
Extractum Lobeliæ fluidum, 511, 961
Lupuli, 510, 1028
Lupulini fluidum, 511, 1028
Malti, 510, 1054
Maticæ fluidum, 511, 1015
Matico fluidum, 1015
Mezerei, 1022
Mezerei Æthereum, 510, 1022
Fluidum, 510, 511, 1022
Nucis Vomicæ, 971
Fluidum, 510, 511, 971
Opii, 510, 844
Liquidum, 511, 844
Papaveris, 510, 843
Pareiræ, 841
Fluidum, 510, 511, 841
Liquidum, 511, 841
Physostigmatis, 510, 904
Pilocarpi fluidum, 511, 883
Piscidiæ erythrinæ fluidum, 913
Podophylli, 838
Fluidum, 510, 511, 838
Pruni virginianæ fluidum, 511, 917
Quassiæ, 892
Fluidum, 510, 512, 892
Rhamni frangulæ, 896
Liquidum, 896
Rhei, 1010
Fluidum, 510, 512, 1010
Rhois glabræ fluidum, 512, 898
Rosæ fluidum, 512, 920
Rubi fluidum, 512, 919
Rumicis fluidum, 512, 1011
Sabinæ fluidum, 512, 1064
Sanguinariæ fluidum, 512, 863
Sarsæ liquidum, 511, 1052
Sarsaparillæ fluidum, 512, 1052
Sarsaparillæ compositum fluidum, 512, 1020, 1022, 1052
Scillæ fluidum, 512, 1041
Scutellariæ fluidum, 512, 1008
Senegæ fluidum, 512, 868
Sennæ fluidum, 512, 910
Serpentariæ fluidum, 512, 1012
Spigeliæ fluidum, 512, 978
Stillingiæ fluidum, 512, 1023
Stramonii, 992
Fluidum, 510, 512, 992
Taraxaci, 957
Fluidum, 510, 512, 513, 957
Tritici fluidum, 512, 1054
Uvæ ursi fluidum, 512, 962
Valerianæ fluidum, 512, 952
Veratri viridis fluidum, 512, 1045
Viburni fluidum, 512, 939
Xanthoxyli fluidum, 512, 883
Zingiberis fluidum, 512, 1037
Eye, action of drugs on the, 216–228
chief drugs employed in the treatment of disease of the cornea, 216; on the conjunctiva, 216; on the lacrimal secretion, 217; projection of the eye-ball, 217; on the pupil, 217; diagram to show the nervous supply of the, 218

the iris of the, and the two muscles of which it consists—the sphincter and the dilator, 217, 218; drugs which act on the iris—mydriatics and myotics, 219; causes and consequences of the dilatation of the pupil of the, 219–221; and of the contraction of the, 221; action of drugs on accommodation, 223; on intra-ocular pressure, 223; uses of mydriatics and myotics, 225; action of drugs on the sensibility of the, 227; in producing visions, 228; application of drugs to the, 477; action of purified chloroform on the eye, 799; of aconitine, 834; of opium on the pupil of the, 854; of cocaine, 878; of pilocarpine, 885; of Jamaica dogwood on the pupil of the, 913; of gelsemium, 978; of belladonna or atropine, 987; of Indian hemp or American cannabis, on the pupil of the, 1027

F.

FAINTING, cause of, 264; effect of emptying the bladder on, 264; treatment of, 265
Farina lini, 876
Fasting, rapid effect of drugs when taken, 43
Fats, as emollients, 347
Fatty degeneration, due to a twofold action, 415; of the liver, stomach, and kidneys produced by phosphorus, 711; what this chiefly depends on, 711; of the vessels, and its result, 711; of the liver and other organs produced by arsenic, 715
Febrifuges. *See* Antipyretics
Feet, cold, remedy for, 199
Feitelberg, reference to, 337
Fel bovis inspissatum, 1082
Purificatum, 1082
Fennel as a carminative, 379; as a stimulant diuretic, 433; characters, composition, and uses of, 934
Fruit, characters and use of, as a stimulant and carminative, 934
Ferments, inorganic, 74; organic and organised, 74; nature of, 75; the process of fermentation divided into two kinds, 75; diastatic amylotic, 76; inversive, 76; proteolytic, 76; action of drugs on, 75–79; yeast and bacteria, 80 *et seq.*; description of the chief organised, 80 *et seq.*; Brefeld's classification of, 81; diagram illustrating the principal organised, 83. *See* also Yeasts, Mound-fungi, Bacteria, Bacillus, &c.
Fern, male, its characters, physiological action, and therapeutics, 1066; method of administration, 1066
Ferri arsenias, 720
Carbonas Saccharata, 1055
et Ammonii citras, 743
et Quininæ citras, 748, 942
et Strychninæ citras, 748, 972
Sulphas Exsiccata, 741
Ferric chloride, action of, on bacteria, 93; as an astringent, 349; as a styptic, 350
Ferrier, Dr., references to, 173, 186, 201, 215, 228, 230; composition and use of his snuff, 731
Ferrocyanide of potassium, 616
Ferrous salts, physiological action of, 27
Ferrous sulphate, action of, on bacteria, 93
Ferrum tartaratum, 610, 743
Fever, remittent, depends on the presence of a spirillum in the blood, 107
Fibres, efferent and afferent, position and functions of the, 356
Fibrin, condition of, when digested with pancreatic juice, 408
Fibrin, effects of heating, 75; and of pepsin on, 75
Fick, A., his kymograph, 269
Fick, J., reference to, 124
Figs, as demulcents, 347; as laxatives, 389; characters, composition, and uses of, 1029
Filices, 1066
Filix mas, as a vermicide, 408
Fir-wool oil, action and use of, 1059
Fire-damp, as a poison, with its antidote, 487
Fish, mechanism of respiration in the, 232; diagram of a, 233
Flag, blue, 1039; as an emetic or cathartic, and a stimulant, 1039
Flag, sweet, as a stomachic stimulant, 1053
Flaxseed, 876; oil of, 877
Flea-powders, fennel, 934; pyrethrum, 952
Flies, Spanish, 1091; external and internal action of, 1091; in very large doses, 1092; on the salivary glands, 1092; on the urinary organs, 1092; external and internal use of, 1092; as an irritant and counter-irritant, 1092; precautions, 1094
Floël, reference to, 383
Flour, wheaten, 1053
Flourens, reference to, 236
Flowers of sulphur, its preparation, characters, &c., 543
Fluorine, symbol and atomic weight of, 10; its relation to other members of a group, 16
Fodor, reference to, 85
Fokker, reference to, 102
Food, discussion as to whether alcohol can be deemed a, 767
Foot-baths, warm, utility of, as direct emmenagogues, 453
Formad, reference to, 98

Formic acid, action of, on bacteria, 94
Foster, M., references to, 114, 175, 177
Fothergill, Dr. Milner, his plan of preparing hydrobromic acid, 567
Franck, F., reference to, 186, 187
François-Franck and Brissaud, reference to, 193
Frankincense, common, characters and use of, 1057
Fraser, references to, 150, 171–173, 296, 492, 1100
Freusberg, reference to, 181
Friars' balsam, 965
Friction, one of the simplest rubefacients, 344; value of friction of the skin, as an adjunct to cold baths, 461
Fritsch, reference to, 186
Frogs, effects of large and small doses of veratrine on, 26; and of various poisons, when modified by heat or cold, 45, 46; various experiments on, 54–56; action of quinine on the mesentery of, 62; action of veratrine on, 128; experiment on the sartorius of, 132; rhythmical action of the ventricle of the heart of, 138; experiment on the leg of, 147; explanation and diagram of the mode of experimenting on the sensory nerves in, 148; experiment on the gastrocnemius of, 161–163; mode of experimenting on the action of drugs on the reflex action of the spinal cord of, 163; on the heart of, 164; diagram, showing the nervous system of, 166; experiments with quinine on the spinal cord of, 166; experiments with, 167–174; on the sartorius of, 176; experiments on the nervous system of the, 183; diagram of the higher nerve-centres of, 184; Prevost's experiment with chloroform on the brain of, 206; the easiest way of anæsthetising, 209–211; action of alcohol on, 215; on convulsions in, 237; diagram to illustrate the effects of the horizontal and vertical position of the, in shock, 263; experiments on the arterioles of, 278; as to the effects of drugs on the vessels of, 278; and as to the effect of heat and cold on the lung of, 279; diagram illustrative of this, 279; method of maintaining artificial circulation in, 280; method of measurement by the rate of flow, 281; experiments on the outflow of blood from divided vessels in, while the nervous system is intact, 285; heart beats in the, when imperfectly filled, 292; the heart of, 299; diagram of the heart of, 299; diagram of the auricular septum in, 300; action of drugs on the heart of, 301; instrument for showing the action of heat and cold, and of poisons on the heart of, 301; effect of heat and cold on the action of the heart of, 301; Ludwig and Coats's apparatus for observing alterations in the pulsations and rhythm of the heart of, 302; Williams's, 303; tracings showing changes in the pulsations of the apex of the heart of, 306; irritation of the vagus of, causes stillstand of the heart of, 310; actions of two classes of poisons on the vagus of, 311; difference between the action of the accelerating nerves and the inhibitory fibres of the vagus of, 312; Stannius's experiments on the heart of, 319–322; diagrams illustrative of these, 319–321; Gaskell's experiments on, 321; with illustrative diagram, 321; general considerations regarding the heart of, 322, 323; vagus stimulation on the heart of, divided into five classes, 324, 325; diagrams illustrative of this, 324, 325; hypothesis regarding the action of the vagus on the heart of, 325; with illustrative diagrams, 326, 327; inhibition in the heart of, 326; experiments with, as to the antagonism of drugs, 493; action of chlorides on the nervous system of, 602, 645; of soda on, 620; action of barium on, 645; of mercury, 685; of phosphorus, 712; of arsenic on the skin of, 715; diagrams of the epidermis of, before and after poisoning by arsenic, 715; action of antimony on the heart and skin of, 724; diagram of the vertical section of the epidermis of a, poisoned by antimony, 725; of solution of perchloride of platinum on, 755; of salts of iron on, when injected subcutaneously, 739; of nitrite of amyl, 788; of chloral hydrate, 792; of iodoform, on the heart of, 805; carbolic acid produces convulsions in, 814; action of resorcin on, 818; of aconitia, 832; of staphisagrine, 836; of opium, 851; of caffeine, 871; of quinine, 949; of belladonna or atropine, 987; of nicotine, 993; of digitalis on the heart of, 996; of veratrine on the heart muscle of the, 1048; of colchicum on the spinal cord of the, 1050; and of ergotinic acid, 1070; of cornutine, 1070
Fruit, Anise, 935
Bael, 891
Capsicum, 984
Caraway, 936
Coriander, 937
Dill, 936
of the Dog-rose, 920
Fennel, 934
Hemlock, 931
Squirting cucumber, 928
Fuchsin, 822
Fuller's earth, as a demulcent, 347; nature and uses of, 654
Fungi, 1067

G.

GADIDÆ, 1087
Gadinine, 100
Galactagogues, 456
Galbanum, as an antispasmodic, 214; characters and use of, as a stimulant expectorant, 933
Gall, ox, inspissated, 1082
Gallic acid, 1033; properties and uses of, 1033
Gallici, mistura spiritus vini, 1086; its therapeutics, 1086
Gallinæ, 1085
Gallium, symbol and atomic weight of, 10; properties of, 20
Galls, as an astringent, 349; characters, action, and uses of, 1031
Gamboge, as a drastic purgative, 389; and a hydragogue, 390; characters, action, and uses of, 869
Gamgee, A., reference to his *Physiological Chemistry*, 67
Ganglia, motor cardiac, 289; inhibitory, 289; diagram to show the supposed relation of motor, in the heart to accelerating fibres, 290; Remak's and Bidder's, 300, 304, 308; motor, inhibitory, and quickening, supposed to be present in the nervous system of the frog, 312–314; inhibitory and motor, of the heart, 316, 317; functions of the cardiac, 323
Gargles, method of using, 482
Garlic, as a stimulating expectorant, 255; action of, 1040; as an antiseptic, irritant, and carminative, 1040; as a stimulant, expectorant, and diuretic, 1040
Gärtner, reference to, 42
Gases, action of different, on the frog's heart, 308; poisonous gases, with their antidotes, 486, 487
Gaskell, references to, 111, 276, 280, 284, 295, 307, 311, 313, 321, 322–326
Gastric juice, action of acids on the, 569
Sedatives, and anti-emetics, nature, number, and uses of, 376, 377; divided into local and general, 376; adjuvants to, 376
Stimulants, alkalies as, 598
Syphon, nature and uses of, 483
Tonics, nature and action of, 361 *et seq.*; purgatives and cholagogues may act as indirect, 369; states in which they are indicated, 411
Gastro-salivary circulation, diagram of, 359
Gaultheria, oil of, characters, 962; action, and use of, as an antipyretic, 963
Gelatine, as a demulcent, 347; solution of, 1086
Gelatine discs, 515
Gelsemine, as a spinal stimulant, 181; as a local and general anodyne, 201; as a mydriatic and myotic, 219; action of, on the respiratory centre, 233, 241. *See* Gelsemium
Gelsemium, as a poison, with its antidote, 490; antagonism of, to opium and atropine, 495; characters and action of, 977; on the eye, the spinal cord, and the motor centres, 978; on the head, the vagus, the blood, pulse, and heart, 978; uses of, 978
Geltowsky, references to, 61
GENERATIVE SYSTEM, ACTION OF DRUGS ON THE, 447–456; action of the cerebral and spinal centres on the, 447; action of drugs on the, as aphrodisiacs, 449; as anaphrodisiacs, 451; as emmenagogues, 452; and as ecbolics, 454; action of drugs upon milk, 455
Genito-urinary tract, action of opium on, 861
Gentian, 979
Root, characters and composition of, 979; preparation and use of, 979
Gentianaceæ, 979
Geraniaceæ, 881
Geranium (cranesbill), characters, composition, and action of, as an astringent, 881
Gianuzzi, references to, 239, 971
Giant cells, action of iodoform on, 805
Gilbert, reference to, 136
Gin, as a cardiac stimulant, 328; and as a stimulant diuretic, 433
Ginger, as a carminative, 379; as a sialagogue, 357; characters, action, and uses of, 1037; as a carminative, 1037
Gingerbread, as a laxative, 389
Glanders, caused by a species of bacillus, 99
Glands, poisonous action of the heavy metals on the, 664
Glandular system, antagonistic action of drugs on the, 494
Glauber's salt, 625
Glaucoma, nature of, and mode of treatment, 226
Glomeruli, the result of arterial pressure on the, 427, 428; poisonous action of the heavy metals on the, 665
Glycerine, action of, on enzymes, 78; on bacteria, 93; as a demulcent, 347; characters and uses of, 966, 967
Glycerines, 513
Glycerinum, 513, 966
Acidi Carbolici, 513, 813, 967
Gallici, 513, 967, 1034
Tannici, 513, 967, 1031
Aluminis, 513, 967
Amyli, 513, 967, 1053
Boracis, 513, 624, 967
Plumbi Subacetatis, 513, 967
Tragacanthæ, 513, 967

Glyceritum vitelli, 513, 967, 1086
Glycogen, formed and stored up by the liver, 402; glycogenic function of the liver destroyed by phosphorus, arsenic, and antimony, 402
Glycyrrhizinum ammoniatum, 899
Goa powder, 909
Gold, symbol and atomic weight of, 10; as an alterative, 413; properties, action, and uses of, free from metallic impurities, 753; solution of chloride of, 754; chloride of, and sodium, 754
Goltz, reference to, 183, 285
Gonorrhœa, caused by micrococci, 99
Gout, rheumatic. *See* Rheumatic Gout
Granville, Mortimer, his proposed mode of relieving pain, 203
Grass, couch, 1054
Graves, Dr., reference to, 726
Grawitz, reference to, 81
Griffith's mixture, 742
Grindelia, characters and uses of, 959; in asthma, dyspnœa, and as a local application, 959
Groups, arrangement of the elements in, 16
Grützner, reference to, 42
Guaiac resin, and tincture of guaiac, experiments with, on oxygen, 68, 69; as a stimulant diuretic, 433
Guaiaci resina, 525
Guaiacum, as an alterative, 413; as a direct emmenagogue, 453; guaiacum resin, characters, composition, action, and uses of, chiefly in the treatment of tonsillitis, 880; guaiacum wood, nature and composition of, 880
Guanidine, action of, destroyed by extremes of heat or cold, 45; effect of temperature on, extraordinary, 175; action of, on the motor ganglia, 316; on the cardiac muscle, 316
Guarana, characters, composition, and uses of, 897
Guareschi, references to, 101, 401
Guinea-pigs, the cerebral hemispheres of, more developed than in the frog, 184
Gum, as a demulcent, 347
Gum acacia, characters, &c., and use of, 913; gum arabic, 913
Gumchi, 903
Gun-cotton, preparation and use of, 873
Gutta-percha, characters and use of, 963
Guttiferæ, 869
Gymnosperms, 1057

H.

Habit, effect of, on the action of drugs, 43
Hæmatemesis, value of astringents and styptics in, 350
Hæmatin, nature and spectrum of, 71
Hæmatinics, or blood-tonics, nature, action and uses of, 411
Hæmaturia, value of astringents and styptics in, 350
Hæmodromometer, Marey's, 294
Hæmoglobin, solution of, 60; power of, 70; spectroscopic examination of, 70, 72; action of, on the frog's heart, 308; treatment to be adopted when there is a deficiency of in the blood, 411; the quantity of, increased by hæmatinics, 412
Hæmoptysis, value of astringents and styptics in, 350
Hæmorrhage, action of astringents and styptics in lessening or arresting, 350, 351; importance of absolute quiet in severe, 351; emetics to be avoided in persons suffering from, 375
Hall, Marshall, reference to, 246
Halogen elements, the general source, characters, and mode of preparation of, 547–564
Haloid Compounds—
Bichloride of methylene, 795
Bromal hydrate, 794
Bromide of ethyl, 789
Chloral, 790
,, hydrous, 790
Chloroform, 795
,, Purified, 796
Hydrate of butyl-chloral, 794
Hydrate of chloral, 790
Iodide of ethyl, 790
Hamamelaceæ, 1029
Hamamelis, as a vascular sedative, 339; characters and use of, 1029
Hamilton, Dr. McLean, his plan of preparing hydrobromic acid, 567
Harley, reference to, 72
Harnack, references to, 119, 127, 150, 296, 304, 307, 312
Haycraft, reference to, 30
Haywood, Dr., reference to his use of ether, 212
Head, action of gelsemium on the, 978
Hearing, action of drugs on, 228
Heart and vessels, comparative effect of, on blood-pressure in different animals, 287, 288; in dogs and rabbits, 287, 288; action of the, on blood-pressure, 292; various modes of estimating the action of the, on the circulation, 292–294; cause of the stoppage of the, in rabbits, dogs, and men, 296; stimulation of the, by increased blood-pressure, 298; difference betwixt the tortoise and the mammalian heart, 298; palpitation of the, 299; the, of the frog, 299; diagram of the heart of the frog, 300; action of drugs on the, of the frog, 301; instrument for showing the action of heat and cold, and of poisons on the frog's heart, 301; diagram of Ludwig

and Coats's frog-heart apparatus, 302; diagram of Williams's apparatus for investigating the action of drugs on the heart of the frog, 303; action of drugs on the muscular substance of the, 305; apparatus for ascertaining the action of drugs on the muscular substance of the, 305; tracings showing changes in the action of the frog's heart, 306; difference between the heart-apex and the, 308; diagram to show the difference in the mode of experimenting with the heart and with the apex alone, 308; diagram showing the periodic rhythm of the, 309; tracings of the pulsations of a ventricle of the, 310; action of drugs on inhibition of the, 310; theories regarding the mode of action of drugs upon the, 312; hypothetical view of the nervous system of the, 312, 314; diagram of the hypothetical nervous apparatus in the, 313; detailed description of the physiology of the, 316–328; diagram of the heart and vessels to illustrate the action of drugs on the circulatory apparatus of the, 315; drugs which stimulate, or depress, or paralyse the vagus-centre of the, 317; the accelerating-centre, 318; the vaso-motor centre, 319; the vagus-ends in the, 317; the inhibitory and motor ganglia, 316; the cardiac muscle, 316; the vaso-motor nerves, 318; the capillaries, 318; Stannius's experiments regarding the action of the various cavities of the frog's, 319–322; diagrams illustrative of this, 319–321; Gaskell's experiments on the same subject, 321; diagram to illustrate this, 321; general considerations regarding the, 322, 323; regulating action of the nervous system of the, 324, 325; diagrams illustrating this, 324, 325; hypothesis regarding the action of the vagus of the, 325; illustrative diagrams, 327; inhibition of the, 326; no satisfactory explanation can as yet be given of the action of drugs on the, 328; knowledge in this respect at present in a progressive state, 328; drugs which act on the circulation of the, their divisions and subdivisions, 328; cardiac stimulants, 328; vascular, 330; cardiac tonics, 331; various conditions and diseases of the, in which tonics are most useful, 332–335; the question of the use of digitalis in aortic regurgitation considered, 333; precautions as to position of the, during the administration of cardiac tonics, 334; action of sedatives on the, 338; diagram to show the nervous mechanism by which the action of the, may be depressed by irritation of the stomach, 396; action of manganese salts on the, 753; of alcohol, 769; of spirit of ether, 782; of bromal hydrate, 795; of purified chloroform, 799–803; of iodoform, 805; of aconitine, 833, 834; of staphisagrine, 836; of quillaia (saponin), 919; of quinine, 946; of ipecacuanha, 949; of strychnine, 974; of gelsemium, 978; of solanine, 983; of tobacco, 992; of digitalin, 996; of camphor, 1019; of extract of ergot, 1071

Heat, effect of, on the power of poisons, 44, 48; power of, to preserve life in narcotic poisoning, 47; effects of, in accelerating death from muscular and metallic poisoning, 47; effect of, on protoplasmic movement, 60; on the action of infusoria, 64; on mould-fungi, 82; on bacteria, 88; as a disinfectant, 106; effects of, on muscle, 118, 123, 131, 138; on the action of strychnine, 175; in inducing sleep, 198; as a local anodyne, 201; dry, in the form of a poultice, relieves pain, 203; action of, on the respiratory centre, 240; apparatus for ascertaining the effect of, on the vessels of the frog's lung, 279; instruments for showing the action of, on the frog's heart, 301; the most powerful of all cardiac stimulants, 329; as a vascular stimulant, 330; action of, on inflammation, 341; diagram to show the effect of, in lessening the pain of inflammation, 342; as a vesicant, 344; as an emollient, 347

Hedeoma, or pennyroyal, characters of, 1006; action and uses of, 1007; as a carminative, diaphoretic, and emmenagogue, 1007

Heidenhain, originates the name of zymogens, 80; references to, 404, 423, 426

Hellebore, American, 1045; hellebore rhizome, green, 1045; action of, on the pulse, 1045

Helleborin, action of, on ascidians, 114; on the frog's heart, 307; on the cardiac muscle 316; as a cardiac tonic, 331

Hemiptera, 1090

Hemidesmus root, characters, composition, and use of, 970

Hemlock (conium), composition, action, and therapeutics of, 931; paralysing power of, 932
  Fruit, 931
  Leaves, 930
  Pitch, 1062

Hemp, Indian, as a hypnotic, 199; as a narcotic, 200; character, action, and uses of, 1026; on the sensory nerves, the pupil, and respiration, 1027; on the pulse, temperature, urine, and digestion, 1027; uses of, as a soporific, 1027

Henle's loop, 424, 426, 435

Hepatic stimulants, nature of, 400; action of, 402; importance of combining in-

testinal and, 405; cholagogues and, 407; depressants, 407; resin of podophyllum as a, 838; euonymus (wahoo) as a, 895; juglans as a, 1029
Hermann, references to, 34, 39, 41, 74, 308
Hernia, emetics to be used with caution in persons suffering from, 376
Hip-baths, and mustard hip-baths, utility of, as indirect emmenagogues, 453
Hips (fruit of the dog-rose), 920
Hirt, reference to, 296
Histozyme, a recently discovered ferment, 76
Hitzig, reference to, 186
Hock, as a stimulant diuretic, 433
Hoffmann, reference to, 304
Hoffman's anodyne, 783
Holmgren, reference to, 278
Holmium, symbol and atomic weight of, 10
Homatropine, as a mydriatic, 219
Homœopathy, the principle of, 36
Homolle's digitaline, 995
Honey, as a demulcent, 347; as a laxative, 389; its characters, composition, &c., 1089
Honeys, 518
Hoppe-Seyler, references to, 74, 75
Hops, as a hypnotic, 199; characters of, 1027
Horehound. *See* Marrubium
Horseradish, as a sialagogue; 357; as a carminative, 379; as a stimulant diuretic, 433; horseradish root, characters, composition, and uses of, 866
Hot baths, 467; hot foot-baths, 467; hot sitz baths, 467
Howard's plan of artificial respiration, 802
Hüfner, reference to, 423
Hughlings Jackson, reference to, 145
Humboldt, Alexander von, reference to, 45
Humulus, or hop, 1027
Hunter, John, reference to, 277
Husemann on lithium, 28
Hydragogues. *See* Purgatives
Hydrargyri Chloridum mite, 686
Cyanidum, 687
Iodidum rubrum, 557, 687
Viride, 687
Oxidum flavum, 686
Rubrum, 686
Perchloridum, 620, 687, 690
Persulphas, 687, 690
Flava, 687
Subchloridum, 620, 686, 690
Sulphidum rubrum, 686
Hydrargyrum, 686
Ammoniatum, 637
Corrosivum, 687
Cum cretâ, 686
Hydrastin, as a hepatic stimulant, 403
Hydrastis (golden seal), as a direct emmenagogue, 453; as an ecbolic, 454; characters, composition, and uses of, 839; as a hepatic stimulant and as an antiperiodic, 839
Hydrate, bromal, preparations and characters, 794; action of, 795; irritates the eyes and causes running at the nose, 795; has a narcotic action like chloral, and a powerful paralysing action on the heart, 795; causes salivation and profuse secretion from bronchial mucous membrane, 795; uses of, 795
Hydrate, of aluminium, 656
Butyl chloral, action of, on the vagus-centre, 317; character, action, uses, and administration of, 794
Of chloral, action of, on bacteria, 95
Hydriodic acid, physiological action of, 27
Hydrobromic acid, action of, on the ear, 229; how prepared, 567
Hydrocarbons, fatty series, 761; chemical nature and physical character of the, 761; boiling-point of the, 761; physiological action of those belonging to the marsh gas series, 761. *See* under the different names of the series.
Hydrochlorate of apomorphine. *See* Apomorphine, hydrochlorate of
Hydrochlorate of morphine. *See* Morphine, hydrochlorate of
Hydrochlorate of cocaine. *See* Cocaine and Cocaine hydrochlorate
Hydrochlorate of pilocarpine, characters of, 884. *See also* Pilocarpine
Hydrochlorate of rosaniline, preparation, characters, actions, and uses of, 822
Hydrochloric acid, physiological action of, 27; action of, on the protoplasmic movements, 60; on enzymes, 78; on bacteria, 93, 95; as a caustic, 344; arrests secretion of saliva, 361; as a poison, with its antidote, 487; properties and uses of, 572; preparations containing free, 573
Hydrocyanic acid, forms a compound with hæmoglobin, 70; nature and spectrum of this compound, 71; effects of, on the blood, 72; on bacteria, 95; as a local anodyne, 201; action of, on the respiratory centre, 234; on the muscles of respiration, 238; effects of poisoning by, on the colour of the blood, 240; the vapour of, has a local sedative action on the lung, 249; action of, on the vagus-centre, 317; on the motor ganglia, 316; on palpitation of the heart, 338; as a local and general sedative, 376; as a poison, with its antidote, 487; antagonism of, to atropine, 492, 495; preparation, properties, action, and uses of, 566 *et seq.*; action of, on the skin, 586; on the blood, 587; on respiration, 587; on the heart, 587; on the arteries and nerves, 588; diagram

to show the effect of, when applied locally, 589; uses of, 589
Hydrogen, symbol and atomic weight of, 10; its preparation and uses, 537
Hydrogen, peroxide of, rapidly decomposed by finely-divided platinum, 73; power of certain metals to absorb, 73; its preparation, properties, action, and uses, 540
Hydroquinone, characters, action, and uses of, 818
Hymenoptera, 1089
Hyoscyaminæ sulphas, 504
Hyoscyamine, as a general anodyne, 199; action of, on the vagus-centre, 317; on the vaso-motor centre, 319; and inhibitory ganglia, 317; as an antihidrotic, 441; as a vesical sedative, 445; as a poison, with its antidotes, 490; antagonism of, to morphine, 496
Hyoscyamine, sulphate of, characters, action, and uses of, 991
Hyoscyamus, a hypnotic, 199; as a narcotic, 200; as a general anodyne, 201; action of, on the vagus-centre, 317; on the vaso-motor centre, 319; on the inhibitory ganglia, 317; characters, composition, and preparation of, 990
Hyoscyamus leaves, 990
Hyphomycetes, 82
Hypnone, characters, action, and uses, 779
Hypnotics, or soporifics, nature and action of, on the brain, 196–200; list of the chief, 199; bromide of potassium as a hypnotic, 554
Hypodermic administration of drugs, 474; advantages of this method, 475; nature and method of the injections, 475; diagram of a syringe for hypodermic injection, 475; objections to hypodermic injections, 476; method of obviating these, 476; account of the syringe employed by Koch, 476; injections of apomorphine, ergotin, and morphine, 514
Hypophosphite of sodium, 627; of calcium, 653; of iron, 752
Hyposulphite, test for, 594; of sodium, 630
Hysterical paralysis of the limbs and hysterical aphonia, usefulness of blisters in, 346

I.

Ice, as an anæsthetic, 157; action of, externally, on the mucous membrane, 252; the most powerful of local sedatives, 376; as a cardiac sedative, 339; as a styptic, 350; as an anaphrodisiac, 451
Iceland moss, as a demulcent, 347; composition of, 1067
Ichthyocolla, 1086
Idiosyncrasy, effects of, on the action of drugs, 51
Ignatia, characters and composition of, 971
Image, Mr., of Bury St. Edmunds, his plan of administering chloroform, 803
Indian hemp, 1026
White, 970; acts like digitalis, 970
Liquorice, 903
Indiarubber bag for holding hot water, utility of, to invalid travellers, 329 and *n.*
Indigo, preparation and use of, 915
Indol, action of, on bacteria, 94
Inflammation, chronic and acute, action of irritants and counter-irritants in, 340–347; diagrams illustrative of the action of irritants in, 342, 343; of the joints, utility of friction in, 345
Infusions, 513
Infusoria, nature of, and action of drugs on, 63 *et seq.*; mode of experimenting on, 63; effects of heat, cold, and saline solutions on, 64; of acids, alkalies, and other drugs on, 65; oxidation of, 65–68
Infusum Anthemidis, 514, 955
Aurantii, 514, 888
Compositum, 514, 888, 890, 922
Brayeræ (Cusso), 514, 921
Buchu, 514, 882
Calumbæ, 514, 841
Caryophilli, 514
Cascarillæ, 514, 1022
Catechu, 514, 951, 1016
Cheken, 924
Chiratæ, 514, 980
Cinchonæ, 514, 940
Acidum, 514, 571, 941
Cuspariæ, 514, 882
Cusso, 514, 921
Digitalis, 514, 994
Dulcamaræ, 983
Ergotæ, 514, 1069
Gentianæ compositum, 514, 888, 890, 979
Jaborandi, 514, 883
Krameriæ, 514, 868
Lini, 514, 876, 899
Lupuli, 514, 1028
Maticæ, 514, 1015
Pruni Virginianæ, 514
Fluidum, 917
Quassiæ, 514, 892
Rhei, 514, 1010
Rosæ Acidum, 514, 571, 920
Senegæ, 514, 867
Sennæ, 514, 910, 1037
Compositum, 514, 659, 910, 968
Serpentariæ, 514, 1012
Uvæ ursi, 514, 962
Valerianæ, 514, 952

Inhalations, 533; of chlorine, 550
of vapours for the lungs, 481, 533
Inhalers for the lungs, 481
Inhibition, and the action of drugs on inhibitory centres, nature of, 167–171
Injectio apomorphinæ, 849
Ergotini hypodermica, 1069
Morphinæ hypodermica, 515, 844, 848
Injections, enemas, or clysters, 508
INORGANIC MATERIA MEDICA, 537
Insect powder, as a poison, with its antidotes, 490
Insecta, 1089
Insufflator, for applying powders to the larynx, diagram of an, 480
Intestines, difference between the vessels of the, and those of the muscles, 276; action of drugs on the, 379; movements and secretion of the, 379; cause of these, 379; paralytic secretion of the, 380; diagram illustrative of the effect of section of the nerves on secretion from the, 380; certain nerve-centres possess the power of restraining the secretion from the, 380; nervous arrangements and nerve-centres of the, 381; natural and artificial circulation in the, 382; diagrams illustrating the effects of artificial circulation in the, 382; action of peptones, nicotine, and atropine, 382, 383; of opium, 383; difference between the action of soda and potash on the, with diagrams, 383; effects of morphine on the, 384; and of sodium salts, 384; cause of constipation of the, and remedies for, 384, 385; diagram to show how ovarian irritation probably causes constipation, 386; action of opium as a purgative on the, 386; small doses of belladonna also act as purgatives on the, 386; action of drugs on absorption from the, 386; action of astringents on the, in diarrhœa, 387; diagram illustrating diarrhœa depending on the presence of scybala in the, 388; nature and action of various kinds of purgatives on the, 388–395; of irritant poisons, 395; diagram of the liver, stomach, and, 404; application of drugs to the, 484; as enemata, 484; as suppositories, 484; action of strong solution of ammonia on the, 639; action of iron on the, 663; of copper, 666; of alcohols, 765, 766, 770; of salts of iron, 739; of gold, 754; of spirit of ether, 781; of purified chloroform, 797; of opium, 856; of sanguinaria, 863; of caffeine, 871; of pilocarpine on the glands of the, 885; of physostigmine, 907; of quillaia (saponin), 918; of ipecacuanha, 949; of sulphate of strychnine, 972; of belladonna or atropine, 988; of aloes, 1044
Intoxication, diagnosis between opium-poisoning, apoplexy, and, 852
Inula (elecampane), characters and uses of, 959
Inunction of drugs, method of employing, 473
of the skin, advantage to be derived from, 474
Invertebrata, action of drugs on, 109–116
Iodic acid, physiological action of, 27
Iodide, test for, 594
Iodide of ammonium, action of, on the ear, 229; preparation, character, and uses of, 563
Ethyl-strychnine, 361
Lead, 705
Mercury, green, 696
Red, 696
Potassium, 559
Silver, 680
Sodium, 563
Sulphur, 557
Zinc, 673
Iodide of potassium, action of, on the ear, 229; on the sense of smell, 230; on taste, 231; difference between large and small doses of, on the secretion of mucus, 253; as an anaphrodisiac, 451; nature, action, and uses of, 559–563
Iodides, the, as alteratives, 413
Iodine, symbol and atomic weight of, 10; its relation to other members of a group, 16; action of, on infusoria, 65; on enzymes, 78, 79; on bacteria, 89, 91, 94, 95; on taste, 231; on quinine, 231; and its preparations, as rubefacients, 344; and its compounds, as sialagogues, 357; as an alterative, 413; has little influence on the excretion of urea, 415; vapour of, as a poison, with its antidote, 486; characters, tests, and preparations of, 557; iodide of sulphur, characters and uses of, 557; ointment of, 558; physiological action of iodine, 558; uses of, 559; as an aphrodisiac, 559; as an anaphrodisiac, 559
Iodine water, action of, on bacteria, 93
Iodism, symptoms of, 558, 561
Iodoform, a local anæsthetic, 204; preparation and characters of, 804; mode of administration, 804; action of, as an antiseptic, a deodoriser, and a local anæsthetic, 805; action of, on the heart and nervous system, 805; on giant cells, 805; uses of, 805
Iodoformum, 557
Iodol, action and uses (Appendix), 1099
Ipecac, 948
Ipecacuanha, causes vomiting in man, but not in rabbits, 54; action of, on the nose, 245; one of the most useful expectorants in sufficient doses, 254; as a depressant expectorant, 255; as a local

emetic, 373, 375; as a hepatic stimulant, 403; as an antihidrotic, 441; characters, composition, and preparations of, 948; physiological action of, on frogs, 949; locally, 949; on the stomach and intestine, 949; on the vessels, heart, and lungs, 949; uses of, —as an emetic and diaphoretic, 950; as an expectorant and anti-dysenteric, 950; precautions, 950
Ipecacuanha powder, as a sudorific, 421
Iridaceæ, 1038
Iridin, as a cholagogue, 390; as a hepatic stimulant, 403
ridium, symbol and atomic weight of, 10; physiological action of, 27
Iris of the eye, structure and action of the, 217
Iris, the, or blue flag, 1039
Irish moss, 1073
Iron, symbol and atomic weight of, 10; effects of large and small doses of, on the muscles, 127; causes slow contraction of the vessels, 281; action of, on the vaso-motor nerves, 318; as a vascular tonic, 336; action of, on the liver, 405; as a vermicide, 408; action of, on the general system, 663; properties, sources, and reactions of, 735, 736; general preparations of, 736–738; action of, 738; on the skin, mouth, stomach, and intestines, 739; on the blood and tissues, 739; on the nervous system, 739; on frogs and mammals, 739; how eliminated, 740; the strong solution of the perchloride of, one of the most powerful styptics, 746; the liquor and tincture of, more often employed than any other preparation of, 746
Iron, properties, preparations, action, and uses of—
Ammonio-ferric, sulphate of, or alum, 749
Aqueous solution of citrate of, 748
Arseniate of, 751
Citrate of, 748
and Ammonium, 748
Quinine, 749
Strychnine, 749
Chloride of, 745
Compound mixture of, 742
Hydrated oxide of, 743
with magnesia, 743
Peroxide of, 744
Hypophosphite of, 752
Lactate of, 750
Mixture of acetate of, and ammonium, 745
Nitrate of, 747
Oxalate of, 750
Phosphate of, 751
Pyrophosphate of, 752
Reduced, 744
Iron, saccharated carbonate of, 742
Iodide of, 750
Solution acetate of, 744; of basic sulphate of, 743
Chloride of, 745
Citrate of, and quinine, 749
Solution of Pernitrate of, 747
Persulphate of, 742
Subsulphate of, 743
Tersulphate of, 742
Strong solution of acetate of, 745
Perchloride of, 745
Sulphate of, 741
and ammonium, 749
Dried, 741
Granulated, 741
Precipitated, 741
Syrup of bromide of, 751
Syrup of iodide of, 750
Tartrate of, and ammonium, 747
Potassium, 747
Tartarated, 747
Valerianate of, 752
Irritants and counter-irritants, 340–347; divided into four classes, 340; diagrams illustrating the action of, 342, 343; rubefacients, and their action on chronic and acute inflammation, 340–345; list of the principal, 344; vesicants and their action, 344; pustulants, 344; and caustics, 344; oil of copaiva as an irritant, 912; quillaia (saponin) as an, 918; oil of myrtle as, 924; camphor as, 1019; garlic as, 1040
Isinglass, as a demulcent, 347; nature and properties of, 1086
Isomorphism and physiological action, relation between, 26
Ivy, poison, 898

J.

JABORANDI, as a myotic, 219; as a depressant expectorant, 255; as a sialagogue, 357; as an antihidrotic, 441; antagonism of, to atropine, 495; extract, 510; characters, action, and uses of, 883, 884
Jackson, Dr., advises the use of sulphuric ether as an anæsthetic, 212
Jalap, as a drastic purgative, 389; as a hepatic stimulant, 403; as a cholagogue, 405; characters of, 982
Resin of, characters, action, and uses of, 982
Jamaica dogwood, action and use of, 913
Sarsaparilla, 1051
James's powder, 726, 729
Jankowski, reference to, 337
Jaw, lower, action of phosphorus on the, 710

Jequirity seeds, character, action, and uses of, 903
Jervine, action of, on the spinal cord and the medulla, 1046; the cardiac ganglia and the brain, 1046
Joints, inflammation of the, utility of friction in, 345; and of vesicants, 345; tartar emetic ointment and croton-oil liniment sometimes useful in, 346
Jolyet, references to, 150, 361
Juglandaceæ, 1029
Juglandin, as a hepatic stimulant, 403
Juglans, characters and uses of, 1029; as a cathartic and hepatic stimulant, 1029
Jugular veins, action of poisons when injected into the, 178, 239, 244
Juices, 526
Jumble beads, 903
Juniper, as a stimulant diuretic, 433; composition of, 1063; oil of, 1064; as a stimulant and diuretic, 1064

K.

Kairin, action of, as an antipyretic, and uses of, 824
Kamala, as a vermicide, 408; characters, action, and uses of, 1025; as an anthelmintic, 1025
Kaolin, or China clay, action of, in inflammation of the urethra, 446; nature and uses of, 654
Kava, as a local anæsthetic, 157; as a stimulant diuretic, 433
Képhir, 1080
Keratin, its preparation, characters, and uses, 1083; its mode of application, 1083
Ketones, nature, 779; hypnone, 779
Kidneys, precautions to be taken regarding the state of the, 411; action of drugs on the, 422–436; the threefold functions of the, 422; three structures connected with these functions, 422; nature and process of secretion in the, 422–436; diagram of the urinary tubules in different classes of animals, 423; diagram of the circulation in the kidney of the newt, 425; diagrammatic sketch of the blood-vessels in a mammalian kidney, 425; diagram of the tubules and vascular supply of the, 426; circumstances modifying the secretion of urine by the, 427; relation between sweat-glands and the, 439; action of the heavy metals on the, 664; the possible effect of mercury on the, 665; action of phosphorus on the, 711; of alcohol, 765, 771; of pilocarpine, 885, 887; of tannic acid, 1032; of oil of turpentine, 1059
Kiedrowski, reference to, 588
Kino, as an astringent, 349; nature, action, and uses of, 902
Klein, on bacteria, 81; reference to, 98
Knoll, reference to, 244
Kobert, references to, 126, 127
Koch, on bacteria, 81; reference to, 90; his experiments on bacteria with disinfectants, 92–95; references to, 102, 105; account of a syringe employed by, 476
Köhler, F., reference to, 98
Kölliker, references to, 146, 150
Koppe, references to, 294, 492
Koumiss, 1080; nature and use of, 1080
Kousso, as a vermicide, 408; nature, action, and use of, 921
Kowalewsky, reference to, 294
Kraepelin, reference to, 191
Krameria, 868
Krameriæ, 868
Kratchmer, reference to, 244
Kronecker, references to, 46, 124, 125, 406
Krukenberg, references to his researches on the medusæ, 109, 112, 114, 115
Kühne, Professor, references to, 45, 61; his discovery of ferment-yielding bodies, 80; references to, 132, 153, 176
Kunde, reference to, 175
Küntzer, reference to, 715
Kymograph, the, for ascertaining blood-pressure, description and diagram of, 268–269

L.

Labiatæ, 1002
Laburnum, as a poison, with its antidote, 490
Lac sulphuris, 544
Lacrimal secretion, action of drugs on the, 217
Lactate of iron, 750
Lactic acid, action of, on bacteria, 94; a hypnotic, 199; properties of, &c., 589
Lactucarium, character, action, and use of, 957; has a soporific action and allays cough, 957
Lamellæ, 515
    Atropinæ, 515, 986
    Cocainæ, 515, 878
    Physostigminæ, 515, 904
Langendorf, reference to, 242
Langley, reference to, 354
Lanolin, composition and uses, 1078
Lanthanum, symbol and atomic weight of, 10
Lappa, characters and uses of, 960; as an alterative, and in skin diseases, 960
Larch bark, 1061
Lard, prepared, 1084
    Benzoated, 1084; as an emollient, 1085

Larynx, irritation of the, a cause of cough, 247–249; application of drugs to the, 479; diagram of insufflator for applying powders to the, 480; various modes of applying different drugs to, 480
Laudanum, use of, in maintaining anæsthesia, 211
Laurineæ, 1016
Lautenbach, references to, 399, 401
Lavender, characters of, 1003
Oil of, characters of, 1003
Flowers, 1004; characters, action, and uses of, 1004; as a stimulant and carminative, 1004
Laxatives. *See* Purgatives
Lead, symbol and atomic weight of, 10; action of, on the kidneys, 435; sources and reactions of, 698; action of, 699; in the mouth, stomach, and intestine, 699; general sources of lead-poisoning, 699; treatment for, 699; symptoms of chronic poisoning by, 700; lead colic and cramps, 700; paralysis, 700; known as wrist-drop, 700; action on brain and eye, 701; action of, on the general system, 701; how eliminated, 701; uses, 701
Lead, acetate of, action of, on bacteria, 94; as a vascular sedative, 339; as an astringent, 349; as a styptic, 350; as a poison, with its antidote, 490
Lead, acetate of, 703
Carbonate of, 703
Iodide of, 705
Nitrate of, 705
Oxide of, 702
Plaster of, 702
Solution of subacetate of, 704
Leaf, digitalis, 994
Tobacco, 992
Leaves, Aconite, 831
Bearberry, 961
Belladonna, 984
Buchu, 882
Cherry-laurel, 917
Hemlock, 930
Hyoscyamus, 990
Matico, 1014
Stramonium, 991
Leech, the, 1095; action of chloroform on, 115; to genitals and thighs, as indirect emmenagogue, 453; its action and uses, 1095
Leguminosæ, 899
Lemon, decoction of, 891
Juice, characters, preparations, and uses of, 891; it is refrigerant, antiscorbutic, and a powerful antiperiodic, 891
Peel, characters, composition, and preparations of, 890
Lemons, oil of, characters, preparation, and action of, 890
Leprosy, produced by the bacillus lepræ, 99
Leptrandra, characters, and action of, 1001; on the bile and as a cathartic, 1002
Leptandrin, as a hepatic stimulant, 403
Lettuce, experiments with the protoplasm of, and water on oxygen, 69; as a hypnotic, 199; composition of, 957
Leucin, action of, on bacteria, 94
Leucocytes, nature of, action of drugs on, and method of experimenting on, 60 *et seq.*; diagram to illustrate the action of quinine on, 62; the protoplasm of, contracts in any direction, 117; anæsthetics act as poisons to, 206
Leucomaïnes, 101; absorption and elimination, 101
Lewin, reference to, 974
Lichens, 1067
Liebreich, references to, 791, 1078
Liliaceæ, 1039
Lime, as a caustic, 344; as an astringent, 349; composition of, 648; character, tests and preparations of, 647; as an astringent and as an antacid, 649
Lime, chlorinated, 550, 551, 653
Liniment of, 649
Phosphate of, 652
Saccharated solution of, 648
Slaked, 648
Sulphurated, 653
Syrup of, 648
Lime salts. *See* Calcium salts
Lime water, action of, on bacteria, 93; as a direct antacid, 370; as a vermicide, 408; composition of, 648
Limonis succus, 527
Lineæ, 876
Liniments, or embrocations, 515; list of, with ingredients, 516, 517
Linimentum Aconiti, 516, 832, 1018
Ammoniæ, 516, 873, 966
Belladonnæ, 516, 985, 1018
Fluidum, 985
Calcis, 516, 648, 873, 966
Camphoræ, 516, 873, 1018
Camphoræ compositum, 516, 638, 1003, 1018
Cantharidis, 517, 1058, 1091
Chloroformi, 516, 796, 966, 1018
Crotonis, 516, 924, 1023
Hydrargyri, 516, 686, 1018
Iodi, 516, 557, 967
Opii, 516, 844, 1018
Plumbi subacetatis, 517, 704, 873
Potassii iodidi cum sapone, 516, 557, 891, 967, 1079
Saponis, 516, 966, 1003, 1018
Sinapis compositum, 516, 865, 1018, 1022, 1024
Terebinthinæ, 516, 966, 1018, 1058
Terebinthinæ aceticum, 516, 577, 1018, 1058

Linseed, and linseed tea, as demulcents, 347; composition, action, and use of, 876; chief use is as a demulcent, 876
Meal, 876
Oil, 877
Poultice, 877
Lippia Mexicana, composition, action, and uses of, 1002
Liqueurs, as cardiac stimulants, 328
Liquor Acidi Arseniosi, 517, 720
Chromici, 517
Ammoniæ, 328, 638
Fortior, 517
Ammonii acetatis, 517, 635
Fortior, 517
Citratis Fortior, 517, 638
Antimonii chloridi, 517, 573, 726, 727
Arsenicalis, 517, 719
Arsenici hydrochlorici, 517, 719
Arsenici et hydrargyri iodidi, 517, 687
Atropinæ sulphatis, 517, 986
Bismuthi et ammonii citratis, 517, 732
Calcii chloridi, 517, 651
Calcis, 517, 648
Calcis chlorinatæ, 517, 551
Saccharati, 517, 648, 1055
Chlori, 517
Epispasticus, 517, 577, 784, 1091
Ferri acetatis, 745
Fortior, 517, 745
Chloridi, 517
Citratis, 517
Dialysati, 517
et Quininæ citratis, 517, 748, 942
Nitratis, 517
Perchloridi, 517, 745
Fortioris, 517
Pernitratis, 518, 575
Persulphatis, 518
Subsulphatis, 517
Tersulphatis, 517
Gutta-percha, 517, 963
Hydrargyri nitratis, 687
Acidi, 518, 575, 687, 695
Perchloridi, 518, 687, 693
Iodi, 518, 560
Iodi compositus, 517, 557, 560
Lithiæ, 370
Lithiæ effervescens, 518, 631
Magnesii carbonatis, 518, 661
Citratis, 518, 661
Morphinæ acetatis, 518, 577, 848
Bimeconatis, 518, 846
Hydrochloratis, 518, 573, 847
Nitro-glycerini, 788
Pepsini, 517, 1081
Plumbi subacetatis, 517, 702, 703
Dilutus, 517, 704
Liquor—
Potassæ, 370, 518, 607, 608
Effervescens, 518, 609
Potassæ permanganatis, 518
Potassii, 517
Arsenitis, 517, 720
Citratis, 517
Sodæ, 370, 517, 622
Sodii Arseniatis, 517, 518, 720
Chlorinatæ, 517
Effervescens, 518, 622
Ethylatis, 518, 619
Silicatis, 518, 627
Strychninæ hydrochloratis, 518
Zinci chloridi, 518, 669, 671
Liquorice, as a stimulating expectorant, 255
Liquorice root, characters and composition of, 899; preparation, action, and uses of, 899
Lister, Sir Joseph, originates the antiseptic mode of treatment, 104; on the untoward consequences of operations, 815
Lithium, benzoate of, 632
Bromide of, 556
Carbonate of, 631
Citrate of, 632
Salicylate of, 632
Lithium, symbol and atomic weight of, 10; more poisonous than sodium or potassium, 28; its relation to other members of a group, 16; physiological action of, 27; causes contraction of the vessels, 281; sources, reaction, impurities, and tests of, 630, 631; general action of, 631
Lithium, bicarbonate, as a remote antacid, 370
Carbonate, as a direct antacid, 370
Citrate, as a remote antacid, 370
Lithontriptics, nature and uses of, 436
Litmus, 1067
Paper, blue, 1067
Red, 1067
Solution of, 1067
Tincture, 1067
Littlejohn, Dr., reference to, 385
Liver, effect of the, on the action of drugs, 39, 44; caustics employed to open abscesses of the, 346; action of drugs on the, 399; important function of the, in the general system, 399; action of hepatic stimulants and cholagogues on, 400; power of the, in destroying the poisonous properties of some vegetable alkaloids, 401; five principal functions of the, 402; experiments on the action of hepatic stimulants, 402; list of these stimulants, 403; diagram of the stomach, intestines, and, 404; experiments on the action of cholagogues, 404–406; im-

portance of combining hepatic and intestinal stimulants to ensure complete cholagogue effect, 405; adjuncts to cholagogues, 406; uses of hepatic stimulants and cholagogues on the, 407; action of hepatic depressants on the, 407; action of acids on the, 570; of chloride of ammonium, 638; of mercury, 684; of phosphorus, 710; of alcohol, 765, 771; of dandelion, 957
Liversedge, reference to, 80
Lobelia, as a depressant expectorant, 255; as a poison, with its antidote, 490; characters and composition of, 960; action of, on the respiratory centre, the blood-pressure, the vaso-motor centre, and the vagi, 961; uses of, 961
Lobeliaceæ, 960
Lobeline, as a myotic, 219; as a depressant expectorant, 255; action of, on the vagus-ends of the heart, 317
Lockyer, J. N., propounds the hypothesis that all the elements are compounds, 11; reference to, 28
Loganiaceæ, 971
Logwood, characters, composition, and uses of, 908
Long, Dr. C. W., first uses ether as an anæsthetic, 211
Loos, reference to, 150
Lotiones, 518
Lotio Hydrargyri flava, 518, 648, 686
Nigra, 518, 648, 686, 691
Lovèn, reference to, 292
Lozenges, 531
Luchsinger, references to, 45, 46, 115, 138, 139, 438, 988
Luciani, reference to, 308
Ludwig, references to, 177, 181, 268, 278, 280, 282, 292, 294, 322, 399, 422, 423, 426, 427
Ludwig and Coats's apparatus for experimenting on the frog's heart, 302, 303, 304, 310
Lumbar genital centre, connection of the, with the generative organs, 447
Lunar caustic, 676
Lungs, application of drugs to the, 481, by inhalation of vapours, 481; by the bronchitis kettle, 481; and by smoke, 481; action of gold on the, 754; of ipecacuanha, 950
Lupuline, as a general anodyne, 201, 202; characters, composition, action, and uses of, 1027; as a tonic, stomachic, and soporific, 1028
Lupulinum, 1027
Lupulus, as a general anodyne, 201
Lussana, reference to, 405
Lymph, an abnormal condition of, one of the chief causes of dropsy, 336

M.

Mace, as a carminative, 379; characters and uses of, 1016
McKendrick, reference to, 278
Mackenzie, J. N., reference to, 248
Maclagan, Dr. Craig, reference to, 714
Magenta, 822
Magnesia, as a direct antacid, 370; as a laxative and purgative, 389; carbonate of, as a purgative, 389; characters and action of, 659, 660; sulphate of, 659; enema of sulphate of, 659; carbonate of, 660; light ditto, 660; solution of carbonate of, 661; solution of citrate of, 661; light and heavy magnesia, 661
Magnesium, symbol and atomic weight of, 10; its relation to other members of a group, 16; physiological action of, 27; causes contraction of the vessels, 281; sources, reactions, and preparations of, 658; impurities, tests, and action of, 659; sulphate of, 659; carbonate of, 660
Magnesium, carbonate and bi-carbonate as a direct antacid, 370
Magnoliaceæ, 840
Majendie's experiments on the spinal cord, 174; references to, 373, 975
Malaria, and all diseases of malarious origin, quinine and cinchona bark are almost specifics in, 107; condition of vaso-motor centre in, 862
Malpighian corpuscles, the, 422, 424, 425, 427
Malt, extract of, 1054; as a digestive ferment, 1055
Malvaceæ, 872
Mammalia, 1077
Mammals, action of nitro-glycerine on, 788; of chloral hydrate, 792; of opium, 852; of erythroxylon, 878
Mammary glands, action of drugs on, 455. (*Vide* also Milk.)
Manganese, symbol and atomic weight of, 10; as an indirect emmenagogue, 453; properties, action, and uses of black oxide of, 753; of sulphate of, 753
Manna, as a laxative, 389; characters, composition, and use of, 968; as a laxative, 968
Manometers, fallacies of mercurial, 269
Mansell's solution of iron, 743
Marble, white, 647
Marey, references to, 128, 298
Marey's levers, 243; pneumograph, 243; and hæmodromometer, 294
Marigold, 959
Marjoram, wild. *See* Origanum
Marrubium, characters and use of, 1007; as an expectorant, 1007; and in large doses as a laxative, 1007

Marsh damp, as a poison, with its antidote, 487
Marshmallow. *See* Althæa
Marx, reference to, 41
Maryland pink. *See* Spigelia
Massa copaibæ, 518, 912
Ferri carbonatis, 518
Hydrargyri, 518, 686, 688
Massage, action of, on muscles, 131
Masses, 518
Mastication, arteries of the brain dilated in animals by the movements of, 193
Masticatories, nature and use of, 482
Mastich, characters, composition, and uses of, 897
Materia medica, definition of, 3
Inorganic, 537 *et seq.*
Organic, 759 *et seq.*
Proper, 3
Vegetable, 827 *et seq.*
Matico, as a styptic, 350, 1015; and stimulant diuretic, 433; characters, action, and uses of, 1014; leaves, 1014
Maynard, reference to, 217
Mays, reference to, 305
Meconic acid, 846
Medicated baths, 469
Medicine, materia medica gives an account of the various remedies used in, 3; preventive medicine, or prophylaxis, growing importance of, 5; cause of the rapid advance of, 5
Medulla oblongata, nature and functions of, 232 *et seq.*; diagram representative of various groups of ganglion cells or 'centres,' in the, 235; experiments on the, 244; blood-vessels relax after section of the, 262; stimulating effect of asphyxial blood on the, 298; the nerve-centre which regulates the secretion of the saliva situated in the, 356; the nerve-centre which regulates the movements of vomiting is situated in the, 370; the nervous centre for the renal arteries in the, 429; action of spirit of ether on the, 782; of carbolic acid, 814; of aconitine, 834; of delphinine, 836; of hydrochlorate of apomorphine, 849; of caffeine, 871; of physostigmine, 905; of oil of eucalyptus, 925; of thymol, 1006
Medusæ, action of drugs on, 109–112; effect of stimuli on the rhythmical movements of, 109–111; and of various poisons on, 111, 112; general results of various experiments on, 112, 113
Mel boracis, 518, 624, 967, 1089
Depuratum, 518, 1089
Despumatum, 518, 1089
Rosæ, 518, 920, 1089
Meliaceæ, 894
Melissa, character, composition, and uses as a diaphoretic, 1007
Mendelejeff, perfects the classification of the elements in series, 17–20; table of his arrangement, 19; his predictions regarding gallium, 18; reference to his classification, 592
Menispermaceæ, 840
Menispermum (Canadian moonseed), characters, composition, and uses of, 840
Menstruation, action of emmenagogues on, 452
Menthol, action of, on the brain and spinal cord, 213; as a rubefacient, 344
Mercurial cachexia, 683; tremors, 683; and paralysis, 683
Mercurial preparations, as cholagogues, 390
Mercurialism, nature and cause of, 682; one of the best preparations for producing, 689
Mercuric chloride, effects of, on the blood, 73; on annulosa, 116; as a caustic, 344; as a hepatic stimulant, 403
Mercuric nitrate, as a caustic, 344
Mercury, symbol and atomic weight of, 10; physiological connection between calcium and, 20; action of, on muscle, 127; on the vaso-motor nerves, 318; and its compounds as a sialagogue, 357; as a cholagogue, 405; as an alterative, 413; its power in fibrinous and syphilitic deposits, 415; used to break up deposits of lymph, and to prevent adhesions in iritis and pericarditis, 416; and in the treatment of the secondary stage of syphilis, 416; action of, on the kidneys, 435; sources and reactions of, 680; general impurities and tests, 681; general action of, 681–686; on the skin, 681; effects of, on the body, termed 'mercurialism,' 682; action of, on the mouth, 682; salivation, 682; causes fever, 682; the fumes of, produce a state called mercurial cachexia, 683; which results in mercurial tremors in the muscles, 683; and paralysis, 683; mental powers also affected, 683; special action of, on the brain, 683; action of, modified by sex, age, and idiosyncrasy, 684; action of, on the stomach, 684; the liver, 684, 685; and blood, 685; has the power of causing the absorption of fibrinous exudations, 685; action of, on the pulse, 685; on respiration, 686; and the temperature, 686; cause of the salivation produced by, 686; action of, on the urine, 686
Mercury, nature, preparations, action, and uses of, 686–690
Acid solution of nitrate of, 695
Ammoniated, 694
Black lotion of, 691

Mercury—
Corrosive chloride of, 692
Cyanide of, 697
Green iodide of, 696
Mild chloride of, 691
Ointment of nitrate of, 695
Perchloride of, 692
Persulphate of, 690
Red iodide of, 696
Red oxide of, 694
Red sulphide of, 697
Subchloride of, 691
Yellow oxide of, 694
Yellow subsulphate of, 690
Metallic salts, as poisons, with their antidotes, 490; general tests for the acid radicals in, 593; list of tests for the different acids, 594
Metals, general classification of the, 592; I., monad metals, 592; 1, metals of the alkalis, 596; 2, ammonia, 596; general characters and reactions, 596; physiological action, 596; general action of the alkaline group, 597–599; and of the group of chlorides, 599–602; general action of the sub-group of sulphates, 602; comparative action of the alkaline metals, 602; 1, metals of the alkalis—potassium, 603–617; sodium, 617–630; lithium, 630–633; monad metals, group 2, ammonium salts, 633–643; II., dyad metals, 644; reactions of the metals in class II., 645; group 1, metals of the alkaline earths, 646; general action, 645; calcium, 646–653; appendix to group 2, aluminium, 654–657; and cerium, 657; group 2, magnesium, 658–661; general action of heavy metals on the circulation, intestinal canal, blood, tissue, muscles, nerves, nerve-centres, and glands, 662–665; group 3, 665; general action of, on the system, 665; zinc, 667–674; copper, 674–676; cadmium, 676; argentum, 676–680; mercury, 680–697; lead and tin, 698–706
Methæmoglobin, origin, nature, and changes of, 71, 72
Methyl, effect of the introduction of, into the molecule of strychnine, brucine, and thebaine, 32
Methyl-atropine, -codeine, -morphine, -nicotine, -quinine, and -veratrine, paralysing action of, 32
Methyl-atropine, action of, on the motor nerves, &c., 989
Methyl-coniïne, action of, on the spinal cord, 932
Methylal, action and uses (Appendix), 1097
Methylene, bichloride of, preparation, character, and action of, 795
Methyloxychinicine, constitution of, 824
Methyl-strychnine, action of, on muscle, 144; on the vagus-ends in the heart, 317; characters of, 975
Methyl-tri-ethyl stibonium iodide, action on motor nerves, 150
Methyl-tri-ethyl stibonium hydrate, action on motor nerves, 150
Metschnikoff, reference to, 85
Meyer, reference to, 276
Meyer, Hermann, reference to, 77
Meyer, Lothar, his labour in completing the classification of the elements in series, 17
Meyer, R., reference to, 248
Meyer, Sigmund, reference to, 139
Mezereon, as a vesicant, 344; as a sialagogue, 357
Mezereon bark, character, preparations, and action, 1022
Mezereum, as an alterative, 413; character, preparations, and action, 1022
Microbacteria, 83
Microbes, recent increase in knowledge of, 5; destruction or prevention of, diminishes disease, 5; references to, 99, 104
Micrococci, references to, 83, 84, 85, 90, 98; list of diseases caused by, 99
Microzymes, references to, 92, 93, 106
Milk, action of drugs upon, 455; what the character of the, depends upon, 455; substances excreted by the, 455; various drugs administered to the mother react upon the child through the, 456; action of pilocarpine on the secretion of, 884; its composition, therapeutics, and use, 1079
Milk, sugar of, its characters, 1080; and uses, 1080
Milk of sulphur, 544
Mills, Mr., reference to, 800
Mimoseæ, 913
Mistura ammoniaci, 519, 934
Amygdalæ, 519, 915
Asafœtidæ, 519, 933
Chloroformi, 519, 796
Creasoti, 519, 578, 817
Cretæ, 519, 914
Ferri aromatica, 519, 841, 922, 941
Composita, 519, 893, 1015, 1055
et ammonii acetatis, 519, 746
Glycyrrhizæ composita, 519, 784
Guaiaci, 519, 880, 914, 1055
Magnesiæ et asafœtidæ, 519, 661, 933
Potassii citratis, 519, 890, 891
Rhei et sodæ, 519, 622, 1010
Scammonii, 519, 981, 1079
Sennæ composita, 519, 899, 910
Spiritus vini gallici, 519, 776, 1055, 1086
Mixtures, 518
Molecules, origin and nature of, 11; simple and complex, 11, 12; condition of, in a solid and gaseous state, 12; the

vibrations of, determined by their weight, 27
Mollusca, action of drugs on, 114; effects of various poisons on, 114
Molybdenum, symbol and atomic weight of, 10; its relation to other members of a group, 16
Mommsen, reference to, 155
Monobromo-camphor, as a hypnotic, 199; action of, on the cardiac muscle, 316
Morat, references to, 277, 298
Moreæ, 1028
Mori succus, 527, 1038
Morphine, acetate of, character and preparations of, 847
Hydrochlorate of, ditto, ditto, 847
Morphina, 504
Morphinæ acetas, 504, 844
Acetatis, liquor, 844
Bimeconatis, liquor, 504, 844
Hydrochloras, 504, 844
Hydrochloratis, liquor, 844
Sulphatis, 504, 844
Morphine, effect of habit on the quantity that can be taken, 44; action of, on oxidation, 69; on the blood, 72; as a sedative, 157; action of, on the spinal cord, 163, 172, 173; as a spinal stimulant, 182; as a powerful hypnotic, 199; induces sleep and lessens pain, 199; as a local and general anodyne, 201; as a myotic, 219; action of, in diminishing the excitability of the respiratory centre, 250; and when combined with atropine, 250; as an antisialic, 361; as a local and general sedative, 376; action of, on the intestines, 384; action of, on urea, 414; value of, in laryngeal phthisis, 479; as a poison, with its antidote, 490; antagonistic action of, to certain alkaloids, 494, 496; as an injection, 514; characters, reactions of, &c., 846; opium *versus*, 859
Morphine, Acetate of, character and preparations of, 847
Hydrochlorate of, characters of, &c., 847
Apo-, characters, action, and uses of, 848, 849
Sulphate of, preparations of, 848
Morshead, reference to, 220
Morton, Mr., his use of ether in dentistry, 212
Moseley, reference to, 115
Moss, Iceland, its characters, composition, and therapeutics, 1067
Moss, Irish, characters and use of, 1073
Mosso, references to, 101, 128, 151, 282, 401
Motion and oxidation, relations of, in the animal economy, 65
Motor ganglia, action of oatmeal on the, 1056
Motor Nerves. *See* Nerves
Mould-fungi, origin, nature, and effects of, 82; diseases caused by, 82
Mouth, application of drugs to the, 482; as washes, 482; as caustics, by rubbing, 482; as masticatories, 482; as gargles, 482; action of acids in the, 568; action of alkalies in the, 598; of the metals, zinc, copper, cadmium, and silver, 665; of silver, 678; of alcohol, 765; of spirit of ether, 781; of chloral hydrate, 791; of purified chloroform, 797; of creosote, 817; of tannic acid, 1032; of aloes, 1044
Mucilages, 519
Mucilaginous remedies, useful in cases of irritating cough, 249
Mucilago Acaciæ, 519, 914
Amyli, 519, 1053
Cydonii, 519, 922
Sassafras medullæ, 519, 1020
Tragacanthæ, 519, 901, 967
Ulmi, 519, 1026
Mucous membranes, action of morphine and atropine on the secretions of the, 250; character and action of the secretion of the, 251; of heat and cold on the circulation and secretion of the, 252; of drugs on the secretion of the, 252–254; drugs which increase the ciliary motion in the tracheal, 254; action of chloride of ammonium on the gastric, 637; of tannic acid, 1032
Mulberry juice, characters and use of, 1028
Murrell, references to, 716, 721
Muscarine, formed by putrefaction, 100; action of, on mollusca, 114; as a myotic, 219; action of, on the respiratory centre, 241, 245; on the frog's heart, 307; on the inhibitory power of the vagi, 311; on the ganglia, 313; action of, neutralised by atropine, 314; action of, on inhibitory ganglia, 317; on the cardiac muscle, 316; as a sialagogue, 357; as a general emetic, 373; as an antihidrotic, 441; antagonism of, to atropine, 492–496; artificial and natural muscarine, 1067; action and uses, 1068
Muscarine nitrate, 1067
Muscle, action of drugs on, 117–143; on voluntary, 117; elasticity, extensibility, and retractility of, 117, 118; irritability of, 119; contraction of, 119; latent period of, 120; muscle-dynamite, nature and action of, 120; summation of stimuli, 122; contraction, 122; fatigue, 123; contracture of, 124; tetanus, 125; poisons, 126–131; massage of, 131; propagation of the contraction wave in, 131; rhythmical contraction of, 131; connection between chemical constitution and physiological action on, 134;

action of drugs on, relative, not absolute, 136; action of drugs on involuntary muscular fibre, 137; contraction, 137; effect of stimuli on the, 138; of cold and heat, 138; relation of the contractile tissue to the nerves, 139; propagation of contraction waves, 139; effects of stimulation of the vagus and a weak interrupted current, 140; artificial rhythm, 140; hypothetical considerations regarding the action of drugs on muscle, 141
Muscles, spasms and cramps of the, nature, cause, and general treatment of, 212–214; of the eye, 216 *et seq.*; of respiration, 235; difference between the vessels of the intestines and those of the, 276; the vaso-motor centre has no power over the vessels of the, 276; action of chlorides on the, 602; of ammonium salts, 602; of potassium salts, 605; of ammonium chloride, 636; poisonous action of the heavy metals on the, 664; of platinum, 755; of spirit of ether, 782; of nitrite of amyl, 786; of nitro-glycerine, 789; of chloral hydrate, 792; hydrochlorate of apomorphine on the fibres of the, 849; of caffeine on ditto, 871; of pilocarpine on muscles and muscular fibre, 884, 885; of physostigmine on ditto, 905; of quinine, 947; of strychnine, 974; of curare, 976; of belladonna or atropine, 987; of digitalin, 995; of veratrine, 1047; of oatmeal, 1056
Muscular contraction, apparatus for registering, 120; muscular poisons, number and action of, 126–131; muscular fibre, importance of the action of chloroform and ether on, 206; nerves die sooner than the, 281
Mushrooms, as poisons, with their antidotes, 490
Musk, antispasmodic action of, 213, 214, 1077; as an antispasmodic and stimulant, 1078; its action on the respiratory centre, 1078
Mustard leaves and liniment of, as rubefacients, 344, 345; as a sialagogue, 357; as a local emetic, 373; as a carminative, 379; as a stimulant diuretic, 433; baths, poultices, and stupes, as indirect emmenagogues, 453; bath, 470; powdered, 864; white, 864; black, 864; characters and compositions of the powdered, 864; preparations of, 864
Mustard, oil of, action of, on enzymes, 78; on bacteria, 91, 94, 95; as a vesicant, 344, 865; characters and preparations of, 865; action of, on the skin, and internally as a prompt emetic, 865; it is also used externally as a counter-irritant, in the form of a poultice, &c., 865
Mycoderma vini, nature and action of, 81
Mydaleïne, 100
Mydriatics, and their action in dilating the pupil of the eye, 219–222
Myositis, infective, micrococci present in, 99
Myotics, and their action in contracting the pupil of the eye, 219–223
Myristicaceæ, 1015
Myrrh, as a direct emmenagogue, 453; characters and composition of, 893; action and uses of, as an astringent and expectorant, 893
Myrtaceæ, 1015
Myrtle, oil of, action and uses of, 924; is an antiseptic, rubefacient, internal irritant, and expectorant, 924

N.

Naegeli, references to, 81, 98
Naphthalin, action as a urinary sedative, 446; source and characters of, 821; mode of administration, 821; action of, in destroying low organisms and preventing the germination of their spores, 822; as an antiseptic, and when used internally, 822; uses of, 822
Naphthol, characters, action, and uses of, 822
Narcotics, nature and action of, 200
Nasal douche, diagram of a, 478
Nataloïn, nature and action of, 1042
Nativelle's digitalin, 995
Nauseant, antimony as a, 726
Nerein, action of, on the cardiac muscle, 316
Neroli, oil of, 888
Nerve-centre, the, which regulates the movements of vomiting, 370
Nerve-centres, in respiration, nature and functions of the, 234–245; for the secretion of sweat situated in the spinal cord, 437; how they may be stimulated, 438; situation of the, for the movements of the bladder, 444; action of potassium salts on the, 606; poisonous action of the heavy metals on the, 664; action of gold on the, 754; of alcohol, 769; of erythroxylon, 878; of caffeine, 871; of hydrochlorate of pilocarpine, 884, 885; of physostigmine, 905; of quillaia (saponin), 919; of oil of eucalyptus, 925; of thymol on the, of the cord and medulla, 1006; of camphor, 1019; of oil of turpentine, 1059
Nerve-stimulants divided into two kinds, 192; tonics, when necessary, 411
Nerves, relation of the contractile tissue to the, 139; action of drugs on, 144–158; on motor, 146–155; paralysis of the motor endings of the, 143, 147;

paralysis may be due to disturbance of rhythm between muscle and, 143; experiments illustrative of paralysis, 147–149; list of drugs which have the same paralysing action on the, as curare, 150, 151; irritation of the motor endings of the, by drugs, 154; action of drugs on the trunks of the motor, 154; on sensory, 155; the general action, 155; the local action, 156; action and uses of local sedatives and anæsthetics on, 157; and of drugs on the peripheral ends of the sensory, 157; pain ascribed to vibration of, or of the sheaths, 203; action of anæsthetics on the, 203 *et seq.*; the chief afferent, expiratory, and inspiratory, 241–244; of drugs on the respiratory, 244; the, die sooner than the muscular fibres, 281; action of drugs on the vaso-motor and vaso-dilating, 283; action of the, on the vessels of circulation, 286; influence of, on blood-pressure, 289–292; inhibitory nerves, 289; quickening nerves, 290; vaso-motor nerves, 291; depressor nerves, 291; action of drugs on the accelerating, 298; action of the, on the secretion of saliva, 353–359; diagrams illustrating this action, 354, 355, 359; action of the afferent on vomiting, 371; diagram showing the afferent, by which the vomiting centre may be excited, 372; of the kidney, 428, 429; action of ammonium salts on motor, 602; of potassium salts on ditto, 606; of strong solution of ammonia, 639; poisonous action of the heavy metals on the, 664; action of silver on the, 678; of salts of iron, 739; of manganese salts, 753; of alcohol, 769–770; of spirit of ether, 782; of nitrite of amyl, 786; of chloral hydrate, 792; of purified chloroform, 797; of carbolic acid, 814; of codeine, 850; of opium on the sensory, 854; of pilocarpine on the efferent and other, 884, 885; of physostigmine on the motor and sensory, 905; of sulphate of strychnine on the sensory, 972; of belladonna or atropine on the motor, 987; of tobacco on the motor and secreting, 992; of Indian hemp on the sensory, 1027; of veratrine, 1048; of colchicum, 1051; of extract of ergot, 1071

Nervine tonics, zinc salts as, 668; sulphate of copper as, 675

Nervous debility and irritability, relieved by mustard applications, 345

Nervous ganglion in some lower organisms, nature and functions of the, 232 *et seq.*

Nervous system, general action of drugs on, 144; general irritability of the, generally precedes an attack of gout, 214; regulating action of the, 324–326; action of silver on the, 678; of purified chloroform on the, 799; of iodoform, 805; of aconitine, 835; of opium on the central, 851, 854, 861; of pilocarpine, 884; of elaterin, 929; of quinine, 946; of strychnine, 974; of solanine, 983; of tobacco, 992; of digitalin, 995; of extract of ergot, 1071

Neuralgia, blisters and cautery of great use in, 345

Neuralgic pains, relieved by rubefacients, 345

Neuridine, 100

Neurine, 100

Newlands, Mr., makes the first natural classification of the elements, 17; points out a curious relationship between the lithium and calcium group of elements, 17; and notes that the eighth element is a kind of repetition of the first, 17

Newman, reference to, 278

Newt, diagram of the circulation in the kidney of the, 425

Nicati and Rietsch, reference to, 100

Nickel, symbol and atomic weight of, 10; physiological action of, 27; causes slight contraction of the vessels, 281

Nicotine, action of, on oxidation, 70, 72; on medusæ, 111; on mollusca, 114; on ascidians, 114; on the spinal cord, 163; as a spinal stimulant, 181; as a myotic, 219; on the respiratory centre, 241; on the vessels of circulation, 282; on the vagus-roots, 296; on the heart of the frog, 309; on the inhibitory power of the vagi, 310; on the vagus-centre, 317; on vagus-ends in the heart, 317; action of, on the intestines, 383; on the sweat centres, 439; antagonism of, to morphine, 496. *See* also Tobacco

Niobium, symbol and atomic weight of, 10

Nitrates, test for, 594

Nitrate of Ammonium, 642
- Copper, 674
- Iron, 747
- Lead, 705
- Potassium, 612
- Potassium paper, 612
- Silver, 676
  - And potassium, 677
  - Diluted, 677
  - Moulded, 677

Nitrate of pilocarpine, preparation, characters, and tests, 883. *See* also Pilocarpine

Nitrate of silver, action of, on the mucous membrane, 253; difference of the action of, on the mucous membrane and on the trachea, 253; value of, in laryngeal phthisis, 480

Nitric acid, as a caustic, 344; as a poison,

with its antidote, 487; properties and uses of, 574
Nitrite of amyl, ethyl, &c. *See* Amyl, Ethyl, &c., nitrite of
Nitrites, effects of mixing, with freshly-drawn blood, 71; of poisoning by, on the colour of the blood, 240; on the capillaries, 318; all nitrites act as vascular stimulants, 331
Nitro-benzol, as a poison, with its antidote, 490
Nitrogen, 707; symbol and atomic weight of, 10; its relation to other members of a group, 16; experiments as to the excretion of, in the body, 414; compounds, with hydrogen, carbon and oxygen, 707; and compounds, 708
Nitrogen monoxide, nature, action, uses, and mode of administration of, 708
Nitro-glycerin, as a poison, with its antidote, 490
Nitro-glycerin (glonoine), preparation and properties of, 788; action of, similar to that of nitrite of amyl and other nitrites, 789; in frogs and mammals, 788; on the blood and blood-pressure, 789; why it acts more powerfully than other nitrites, 789; uses of, 789
Nitrohydrochloric acid, properties and uses of, &c., 575; dilute ditto, 575; action of, on the urine, 436
Nitrous ether, as a vascular stimulant, 330; as a refrigerant diuretic, 432
Nitrous oxide, as an anæsthetic, 205 *et seq.*; nature and action of, 708
Nose, application of drugs to the, 478; as snuff, 478; by insufflation, 478; by the nasal douche, 478; diagram of nasal douche, 478; action of pilocarpine on the, 884
Nothnagel, references to, 360, 384, 837
Nowak, reference to, 136
Nussbaum, reference to, 424
Nut, areca, 1052; as an anthelmintic, 1052
Nutgalls, action and uses of, 1031
Nutmeg, characters and composition of, 1015; volatile oil of, 1015; expressed oil of, as a stimulant and carminative, 1016
Nutmeg and oil, as carminatives, 379
Nutrition, remedies which improve, 413; what healthy nutrition depends on, 413
Nux vomica, as a stimulating expectorant, 255; as a cardiac tonic, 331; as an antihidrotic, 441; characters, composition, and preparations of, 971

O.

Oak-bark, as an astringent, 349; action and use of, 1030
Oatmeal, 1056; action and uses of, 1056
Œsophagus, the, of various animals, muscular structure of, 139
Offenburg, reference to, 977
Officinal preparations. *See* the different drugs
Oil, castor. *See* Castor oil
Oil, cod-liver, 1087: its characters and composition, 1087; its physiological action, 1087; powers of absorption and assimilation, 1087; uses, 1088
Oil, ethereal, 783
Oil of allspice, 923
Almonds, 916
Bitter, 490, 916
Amber, 1060
Anise, 935
Bergamot, characters and use of, 889
Cajuput, 924
Caraway, 937
Castor, 1024
Chamomile, 955
Cinnamon, 1017
Cloves, 95, 922
Copaiva, 912
Coriander, 938
Croton, 1023
Cubebs, 1014
Dill, 936
Eucalyptus, 925
Firwool, 1060
Flaxseed, 877
Gaultheria, 962
Juniper, 1064
Lavender, 1003
Flowers, 1004
Lemons, 890
Mace, 128
Mustard. *See* Mustard oil
Myrtle, 924
Neroli, 887
Nutmeg, expressed, 1016
Volatile, 1015
Olive, 965
Orange flowers, 887
Peel, 889
Peppermint, 1004
Pimenta, 923
Rose, 920
Rosemary, 319, 1002
Rue, 881
Santal, 1021
Sassafras, 1020
Scotch fir, 1059
Sesamum, 1002
Spearmint, 1005
Tar, 1063
Theobroma, 875
Turpentine, 93, 253, 328, 344, 1058
Valerian, 952
Oil of turpentine, action of, on bacteria, 95; of the vapour of, on the mucous membrane, 253; great therapeutical value of the vapour of, in bronchitis,

253; as a cardiac stimulant, 328; as a rubefacient, 344; as an antidote to phosphorus, 491
Oils, ethereal, action of, on bacteria, 103; on the vaso-motor centre, 319; aromatic volatile, as cardiac stimulants, 328; volatile, as rubefacients, 344; as an antidote to phosphorus, 490
Oils, fixed and volatile, 519, 521
Ointment, sulphur, 544; alkaline sulphur, 544; various kinds of iodine, 557; iodide of sulphur, 557. *See* Unguentum
Ointments, their nature, number, and uses, 532
Oleaceæ, 965
Oleate of mercury, 591
of Veratrine, 591
of Zinc, 670
Oleates, 521
Oleatum hydrargyri, 521, 591, 687, 694
Veratrinæ, 521, 591, 1047
Zinci, 521, 670
Oleic acid, action of, on bacteria, 94; properties and uses of, 590
Oleoresina Aspidii, 521, 1066
Capsici, 521, 984
Cubebæ, 521, 1014
Lupulini, 521, 1028
Piperis, 521, 1013
Zingiberis, 521, 1037
Oleoresins, 521
Oleum Adipis, 520
Æthereum, 520, 783
Amygdalæ, 520, 916
Amaræ, 520
Expressum, 520
Anethi, 520, 936
Anisi, 520, 840, 935
Anthemidis, 520, 955
Aurantii corticis, 520, 889
Florum, 520
Bergamii, 520, 889
Cajuputi, 520, 924
Cari, 520, 937
Carui, 520, 936
Caryophylli, 520, 922
Chenopodii, 520, 1009
Cinnamomi, 520, 1016
Copaibæ, 520, 912
Coriandri, 520, 938
Crotonis, 1023
Cubebæ, 520, 1014
Erigerontis, 521
Eucalypti, 521, 925
Fœniculi, 521
Gaultheriæ, 521, 962
Gossypii seminis, 520, 872
Hedeomæ, 521, 1007
Juniperi, 520, 521
Lavandulæ, 520, 521
Florum, 521
Limonis, 520, 521, 890
Lini, 876
Oleum—
Menthæ piperitæ, 520, 521
Viridis, 520, 521
Morrhuæ, 520
Myrciæ, 521
Myristicæ, 520, 521, 1015
Expressum, 520, 1015, 1016
Myrti, 924
Olivæ, 520, 965
Phosphoratum, 520, 710, 916
Picis liquidæ, 521
Pimentæ, 520, 521, 923
Pini Sylvestris, 520
Ricini, 520
Rosæ, 521, 920
Rosmarini, 520, 521
Rutæ, 520, 521, 881
Sabinæ, 520, 521, 1064
Santali, 520, 521, 1021
Sassafras, 521, 1020
Sesami, 520, 1002
Sinapis, 520, 865
Volatile, 521, 865
Succini, 521
Terebinthinæ, 520, 521
Theobromæ, 520
Theobromatis, 875
Thymi, 521
Tiglii, 520, 1023
Valerianæ, 521, 952
Oleum animale, action of, on bacteria, 94
Oleum menthæ piperitæ, action of, on bacteria, 94
Oleum pini pumilionis, as a stimulating expectorant, 255
Oleum pini sylvestris, as a stimulating expectorant, 255
Olive oil, as a demulcent, 347; characters, 965; composition, and preparations of, 965; action and uses of, 967
Onion, as a stimulating expectorant, 255
Ononis spinosum, as a stimulant diuretic, 433
Operations, surgical, Sir Joseph Lister on the best mode of performing, 815
Ophthalmia, gonorrhœal, contagious, and neonatorum, caused by micrococci, 99
Opium, effect of habit on the quantity that can be taken, 44; abnormal effects of, in some cases of fever, 47; some persons very slightly affected by, 51; as a sedative, 157; as a spinal stimulant, 182; different actions of, in different doses, on the brain, 195; one of the most powerful hypnotics, 199; induces sleep and lessens pain, 199; as a local and general anodyne, 201, 211; as a myotic, 219; action of, on the respiratory centre, 241; on the brain, 244; in diminishing the excitability of the respiratory centre, 250; action of, on the vessels of circulation, 284; as a vascular sedative, 339; as an antisialic,

361; as a local and general sedative, 376; action of, on the intestines, 383, 384, 387; as a purgative, 386; as a vesical sedative, 445; as a poison with its antidotes, 490; antagonistic action of, and belladonna, 494; antagonism of, to other drugs, 494, 497; characters and preparations of, 844; alkaloids of, 846; physiological action of, 851; general action of, exclusively on the central nervous system, 851; and in mammals especially on the brain, 851; in the frog it acts on the motor ganglia of the heart, 851; action of, on frogs, 851; on birds, 851; on mammals, 852; on man, it acts chiefly on the brain, 852; in producing sleep, and in large doses, death, 852; diagnosis between poisoning by, and intoxication and apoplexy, 852; treatment in poisoning by, 853; precautions, 853; treatment of the symptoms after an ordinary dose, 854; action of, on special organs, 854; on the sensory nerves, the spinal cord, and the brain, 854; on the pupil, 854; the circulation, and the vaso-motor centre in the medulla, 854; has a peculiar action on the peripheral vaso-motor apparatus, 854; on secretion, 855; on sweat and the urine, 855; on the intestines, 856; elimination, 856; circumstances modifying the action of, 856; sex and idiosyncrasy, 856; habit, 857; opium-eating, 857; action of, in disease, 858; and in combination with other drugs, 858; action of the alkaloids of, 858; the morphine group and the codeine group, 858; how codeines are produced, 859; action of apomorphine and morphine, 859; therapeutics—general uses and local uses, 859; on the digestive system, 860; the respiratory tract, 860; the circulatory system, 861; the genito-urinary tract, 861; the skin, 861; two most important uses of opium and morphine to relieve pain and produce sleep, 861; action of, on the nervous system, 861; contra-indications, 862

Opium denarcotisatum, 845

Opium-eating, the effects of, 284

Opium, powdered, preparations and composition of, 845

Orange, bitter, 888
- Flower water, 888
- Flowers, character, composition, and uses of, 887
- Oil of, 887
- Peel, bitter, 888
- Oil of, 889
- Sweet, Oil of, 889

Orchidaceæ, 1036

Organism, the animal, general relations between, and substances affecting it 9–32; circumstances which affect the action of drugs on the, 33–56; effects of oxidation on, 65 *et seq.*; relations of motion and oxidation in, 65; excess of temperature injurious to, 102

Origanum, characters, action, and uses of, 1007; as a diaphoretic and emmenagogue, 1007

Orthospermæ, 932

Osmic acid, action of, on bacteria, 94, 95; as a caustic, 344

Osmium, symbol and atomic weight of, 10; physiological action of, 27

Ovarian irritation, diagram showing how, probably causes constipation, 386

Oxalates, test for, 595

Oxalate of cerium, 657; of iron, 750

Oxalic acid, as a poison, with its antidote, 487; nature and use of, 581

Ox-bile, purified, 1082

Ox-gall, 1081; inspissated, 1082

Oxidation, relations of motion and, 65; of protoplasm, 67; action of drugs on, 69; methods of ascertaining the effects of drugs on, 72

Oxide of Lead, 702
- Manganese, black, 753
- Mercury, red, 694
- Yellow, 694
- Silver, 679
- Zinc, 669

Oxygen, symbol and atomic weight of, 10; broken up by electricity, and forms a new element, ozone, 13; its relation to other members of a group, 16; necessary for protoplasmic life, 61; power of protoplasm over, 68; action of hæmoglobin on, 70; effects of other gases on, 70; of carbonic oxide on, 70; of charcoal, 73; effects of, on mould-fungi, 82; on bacteria, 82; excess or absence of, causes tetanus, 176; effects of the presence or absence of, on the blood, 235–240; its preparation, 537; properties, physiological action, and uses, 537, 538

Oxyhæmoglobin, 70, 72

Oxymel, 518, 577, 1089
- Scillæ, 518, 577, 1041, 1089

Ozone, origin and nature of, 13; action of, on albumen, 58; power of protoplasm in forming, 69; action of phosphorus in forming, 69; nature and uses of, 539, 540; diagram illustrating the formation of, by electricity, 539

P.

Pachydermata, 1084

Paget, Sir James, reference to his lecture on 'Elemental Pathology,' 50

Pain, origin and nature of, 201; where seated, 201; how caused, and how re-

lieved, 202; action and uses of anodynes in, 202, 203; relieved by an effort of the attention, 203; action of anæsthetics in relieving, 203 *et seq.*; and of electricity and cold, 203; Mortimer Granville's treatment of, 203; action of anæsthetics in alleviating or destroying, 203 *et seq.*
Pale rose, composition and uses of, 920
Palladium, symbol and atomic weight of, 10; physiological action of, 27
Palmaceæ, 1052
Palmitic acid, action of, on bacteria, 94
Palpitation, of the heart, effect of blood-pressure on, 299; the principal drugs which diminish it, 339
Pancreas, action of drugs on the, 407
Pancreatic juice, importance of the, in the process of digestion, 407; effects of the secretion of the, 408; and of different drugs on the, 408
Pancreatin, utility of, in aiding digestion, 364
Papain, 927
Papaveraceæ, 843
Papayaceæ, 927
Papayotin, preparation, action, and uses of, 927; digestive power of, on muslar fibre and connective tissue, 927
Paper, litmus, blue, 1067
Red, 1067
Paper, turmeric, 1037; as a test for alkalies, 1037
Papers, 506
Papilionaceæ, 899
Papillon, M., reference to, 28
Paracoto bark, 1017
Paracotoine, action on intestinal secretion, 387
Paraffin, as an emollient, 347
Paraffin, hard, 763; soft, 764
Paraldehyde, a hypnotic, 199; a general anæsthetic, 205
Paralysis, of the respiration and heart, danger from anæsthetics, 207; treatment necessary when this occurs, 207; of the sphincter muscle of the iris of the eye, 220; and of the dilator muscle of the same, 221
Parasiticide, balsam of Peru as a, 902
Pardington, Dr., reference to, 167
Paré, Ambrose, reference to, 104
Pareira brava, as a stimulant diuretic, 433; action of, on the bladder, 445
Pareira root, characters and composition of, 841; action and uses of, 842
Parsley, as a stimulant diuretic, 433
Pasteur, divides bacteria into two classes, 82
Paton, reference to, 900
Pavy, reference to, 850
Pearl barley, 1054
Pedalineæ, 1002
Pellitory root, characters, action, and uses of, 952
Pennyroyal, 1006
Pentad elements, 707–734
Pepper, as a carminative, 379
Pepper, black, as a stimulant diuretic, 433; characters, composition, and preparations of, 1012; action and uses of, 1013; as a stomachic, &c., 1013
Peppermint-camphor, characters, action, and uses of, 1004; as an antiseptic and antineuralgic, 1005
Peppermint and oil, as a carminative, 379
Peppermint oil, action of, on bacteria, 95; characters, action, and use of, 1004; as a carminative and stimulant, 1004
Pepsin, action of, on fibrin, 75, 76; action of, as an artificially digestive substance, 364; nature of, 1081
Pepsinum saccharatum, 1081; its therapeutics, 1081
Peptogens, their action in increasing the gastric juice, 363
Peptones, action of on the intestines, 382; action of the liver on, 399
Perchloride of mercury, 692
Perinæum, a wet sponge applied to the, causes the evacuation of urine, 444
Peristalsis, and mode of increasing, 212; some hepatic stimulants which increase, 405
Permanganate of potassium, action of, on bacteria, 95; as a powerful antiseptic, may be used to wash out abscesses, and as a lotion for ulcers or wounds, 105; action of, on muscle, 121; characters, action, and uses of, 614, 615
Peroxide of hydrogen, preparation properties, action, and uses of, 540
Perspiration, antipyrin causes profuse, 824. *See* also SKIN, ACTION OF DRUGS ON THE
Peru, balsam of, as a parasiticide, 902
Pessaries, nature and uses of, 485
Petals, cabbage-rose, 920
Red poppy, 862
Red rose, 920
Petrolatum, 532; properties and uses of, 763
Petroleum benzin, or ether, properties and uses of, 762; petroleum ointment, 763
Petroleum ether, action of, on bacteria, 93
Pettenkofer, reference to, 404, 414
Phagocytes, 85
Pharmaceutical preparations, 501–534; general principles which govern, 501, 502; the following are the principal abstracts, 503; vinegars, 503; alkaloids, 503; waters, 505; cataplasms or poultices, 506; cerates, 506; papers, 506; collodions, 507; confections, electuaries, or conserves, 507; decoctions, 507; elixirs, 508; plasters, 508;

injections, enemas, or clysters, 508; essences, 509; extracts, 509–513; fluid or liquid extracts, 510; fresh or green extracts, 512; glycerines, 513; infusions, 513; hypodermic injections, 514; liniments or embrocations, 515; solutions, 517; masses, 518; honeys, 518; mixtures, 518; mucilages, 519; oils, fixed and volatile, 519; oleates, 521; oleoresins, 521; pills, 521; powders, 524; resins, 524; spirits, 525; suppositories, 526; juices, 526; syrups, 527; tinctures, 528–531; triturations, 531; ointments, 532; vapours, inhalations, 533; wines, 534

Pharmacology, definition of, 3; one of the most important subdivisions of materia medica, 3; rapid advances of, of late years, 5; difficulty students find in dealing with, 5; the great object of, 20; the connection between chemical constitution and physiological action the most important one in, 32; importance of comparative, 50; inhibition, and the action of drugs on inhibitory centres play a very important part in, 167–171

Pharmacy, definition of, 3, 501

Pharyngeal irritation the probable origin of the so-called stomach cough, 248

Pharynx, structure and functions of, 248; cough caused by irritation of the, 248; application of drugs to the, 481; as washes, 482; as caustics, 482

Phenol. *See* Carbolic acid

Phenyl-alcohol. *See* Carbolic acid

Phenyl-methyl-amyl ammonium hydrate, action on motor nerves, 150

Phenyl-dimethyl-ethyl ammonium iodide, action on motor nerves, 150

Phenyl-tri-ethyl ammonium iodide, action on motor nerves, 150

Phosphates, test for, 595

Phosphate of sodium, as a cholagogue purgative, 405; nature of, 626; as a saline purgative, 389; of ammonium, 642; of calcium, 652; of iron, 751

Phosphides, test for, 595

Phosphide of zinc, 673

Phosphoric acid, physiological action of, 27; as a poison, with its antidotes, 487; properties, &c., 579; dilute ditto, 579

Phosphorus, symbol and atomic weight of, 10; occurs in two forms, red and yellow, 14; in combination sometimes pentad and sometimes triad, 14; its relation to other members of a group, 16; secondary effects of, as an irritant poison, on the system, 398; destroys the glycogenic function of the liver, 402; has a special action on tissue-change, 415; in poisoning by, action of, on the urine, 415; used in nervous debility, 416; as a poison, with its antidotes, 490; preparation and characters of, 709; action of, 710; on the liver and bones, 710; on the lower jaw, 710; in poisonous doses, 711; produces fatty degeneration of the liver, stomach, and kidneys, 711; treatment in cases of poisoning by, 711; cause of the fatty degeneration, 711; action of compounds containing, 712; uses of, 712

Phthisis, caused by the *bacillus tuberculosis*, 99; when accompanied by a copious secretion of mucus, a combination of morphine and atropine useful in, 250; the atropine beneficial also in lessening sweating in, 250; alkalies useful in diminishing the moist *râles* heard in the lungs in, 252; tartar emetic ointment and croton-oil liniment sometimes useful in, 346; on the night-sweats of, 442; diagram illustrating the action of antihidrotics in diminishing sweating in, 442; probable mode of action of arsenic in, 717; how the disease originates and increases, 717

Physiological action, relation between atomic weight and, 28; between spectroscopic characters and, 27; between isomorphism and, 26; Blake's division of the elements into nine groups, according to their, 27

Physiological reactions, 24; divided into groups, 25

Physostigma, lethal dose of, 38; action of, on muscle, 130 *et seq.*; effects of a solution of, applied locally to the nerve-trunk, 155; action of, on the motor centres of the brain, 188; as a myotic, 219; on the respiratory centre, 241, 245; on the blood-pressure, 285; chiefly affects the heart, 296; action of, on the vagus, 297; on the frog's heart, 307; on the ganglia, 313, 314; on the vagus-ends in the heart, 317; on the cardiac muscle, 316; action of, on the secretory and sympathetic nerves, 357, 358; as a sialagogue, 357; as an antisialic, 361; the paralysing action of atropine counteracted by, 361; as a hepatic stimulant, 403; as a poison, with its antidotes, 491; antagonism of, to atropine, 492–496; antagonistic action of, 493–496; nature, physiological action, and therapeutics of, 904–908. *See* also Physostigmine

Physostigminæ, 504

Physostigminæ salicylas, 504

Physostigmine, character, tests, and preparation of, 904, 905; action of, on the muscular fibre and nerve-centres, 905; general action on the muscles, spinal cord, medulla, and motor and sensory nerves, 905; on the brain, eye,

respiration, and circulation, 905, 906; on muscle, stomach, and intestines, 907; on the spleen, bladder, and uterus, 907; on the secretions and secreting cells, 907; uses of, 908; treatment of poisoning by, 908
Physostigmine, salicylate of, characters of, 904
Phytolacca berry, 1009
Root, 1009; characters, and action of, 1009; as an emetic, narcotic, and alterative, 1009
Phytolaccaceæ, 1009
Phytolaccin, as a hepatic stimulant, 403
Picric acid, action of, on bacteria, 91, 95
Picrotoxin, effect of temperature on the action of, 46; action of, on oxidation, 70; powerful convulsant action of, 190; action of, on the accelerating centre, 318; as an antihidrotic, 441; as a poison, with its antidotes, 491; antagonism of, to chloral, 495; characters of, 842; action of, on the medulla, motor centres, spinal cord, and temperature, 842; uses of, 842
Picrotoxinum, 505
Pills, 521; list of, with ingredients, 522, 523
Pilocarpine, effects of cold on the action of, 46; as a myotic, 219; action of, on the mucous membrane, 253; as a depressant expectorant, 255; effect of, on the frog's heart, 307; on the cardiac muscle, 316; as a sialagogue, 357; action of, on the peripheral ends of the sweat nerves, 438; as an antihidrotic, 441; as a poison, with its antidote, 491; antagonism of, to atropine, 494, 495; action of, on the nerves, nerve-centres, and muscular fibre, 884, 885; and on all the secretions of the body, 884; on the bladder, uterus, and spleen, 885; on the circulation and vessels, 885; on the respiration and temperature, 886; on the eye, skin, and throat, 886; its chief use in dropsy, 887; contra-indications, 887
Pilocarpinæ hydrochloras, 504, 884
nitras, 883
Pilocarpus (jaborandi), characters of, 883
Pilula Aloes, 523, 966, 1043
Aloes Barbadensis, 522, 937, 966, 1044
et Asafœtidæ, 522, 932, 966, 1042, 1043
et Ferri, 522, 741, 1043, 1044
et Mastiches, 523, 897, 920, 1043
et Myrrhæ, 523, 893, 967, 1042, 1043, 1039, 1056
Socotrinæ, 522, 966, 1042
Antimonii compositæ, 523, 686, 691, 726, 728, 880
Asafœtidæ, 523, 933, 966
Pilula Asafœtidæ—
Composita, 522, 893, 932, 933, 1056
Cambogiæ composita, 522, 869, 966, 1044
Catharticæ compositæ, 523, 686, 691, 869, 928, 982, 1043
Colocynthidis composita, 522, 611, 922, 928, 981, 1044
et hyoscyami, 522, 611, 922, 928, 981, 1044
Conii composita, 522, 931, 949, 1056
Ferri carbonatis, 522, 742, 1055
Iodidi, 522, 557, 750, 899, 1055
Compositæ, 523, 893
Galbani compositæ, 523, 893, 933
Hydrargyri, 522, 686, 899
Subchloridi composita, 522, 686, 691, 726, 728, 880, 1024
Ipecacuanhæ cum scillâ, 522, 611, 844, 934, 949, 1041, 1056
Opii, 523, 845, 966
Phosphori, 522, 710, 903, 1079, 1090
Plumbi cum opio, 522, 703, 844
Rhei, 523, 966, 1010
Composita, 523, 893, 966, 1004, 1010, 1042, 1043, 1056
Saponis composita, 523, 844, 966
Scammonii composita, 523, 981, 983, 1079
Scillæ composita, 523, 934, 966, 1041, 1037, 1056
Pimenta, 923
Oil of, 923
Pimento, characters and composition of, 923
Oil of, 923
Pine bath, 470
Pinkroot. *See* Spigelia
Piperaceæ, 1012
Piperine, 504; character, action, and uses of, 1013
Pisces, 1086
Pitch, Burgundy, 1062
Canada, 1062
Hemlock, 1062
Pitres, references to, 186, 187
Piturine, as a mydriatic, 219
Plasters, 508; utility of, in chest complaints and in bronchitis, 256
Platinum, symbol and atomic weight of, 10; physiological action of, 27; action of, on muscle, 127; causes powerful contraction of the vessels, 281; properties, action, and uses of foil, 754; of solution of perchloride of, 754; of platinum black, 755
Pleurisy, tartar emetic ointment and croton-oil liniment sometimes useful in, 346
Pleurisy root. *See* Asclepias

Plumbi acetas, 703
Iodidum, 557, 705
Pneumonia, contagious, micrococci present in, 99
Podophylli resina, 838
Podophyllin, as a drastic purgative, 390; and as a cholagogue, 390; as a hepatic stimulant, 405. *See* also Podophyllum root, and resin of podophyllum
Podophyllum root, characters, properties, and composition of, 838; resin of, nature, properties, and uses of, 838
Poisoning, what is necessary to be done in all cases of, before administering the antidote, 486; by acids, 570; chronic, by copper, 666; by phosphorus, and its treatment, 710, 711; by arsenic, and its treatment, 713, 714; chronic, by arsenic, 714; by antimony, 722; chronic alcoholic, 770; treatment of, by chloral, 793; by opium, 853; by physostigmine, 908; by strychnine, and its treatment, 973; by belladonna or atropine, 990; by digitalis, and its treatment, 1001; by croton oil, and its treatment, 1023; by colchicum, 1051; treatment of, by cantharides, 1092
Poisonous gases, with their antidotes, 486
Poisons, effect of heat on the power of, 44–48; different effects of, on different animals, 43–49; effects of various, on medusæ, 111, 112; list of muscular, 126–131; effects of certain, on the colour of the blood, 240; on the muscular fibre of the ventricle of the heart, 307; on the heart itself, 308; of two classes of, on the vagus, 310–314; list of cardiac, 316; most suitable emetics for removing, from the stomach, 374; action of various irritant, on the general system, 395–397; peculiarities in the action of different irritant, 397; secondary effects of irritant poisoning, 398; list of the more common, with their antidotes, 486–491; carbonic acid as a, 584; has three stages—dyspnœa, convulsions, paralysis, 584; copper as a, 666
Poke berry. *See* Phytolacca berry
Root. *See* Phytolacca root
Politzer, reference to, 153
Polygalaceæ, 867
Polygonaceæ, 1010
Pomeæ, 921
Pomegranate, as a vermicide, 408; characters, composition, and use as an anthelmintic, 926
Root bark, 926
Poppy capsules, character of, 843; composition, action, and uses of, 843
Poppy petals, red, characters, composition, and use of, 862
Potash, physiological action of, 27; action of, on protoplasm, 61; permanganate of, effect of, on infusoria, 65; on bacteria, 91; on muscle, 121; salts of, effects of, on muscular contraction, 129; action of, on the ends of the vaso-motor nerves, 284; action of, combined with other ingredients, on the frog's heart, 307; as a caustic, 344; difference between the action of, and soda, on the intestines, 383; used in gout, 416
Potassæ liquor, singular effect of a single drop of, 492
Potassium salts, preparation, nature, and uses of the following—
Potassium acetate, 605, 609
Acid tartrate, 605, 610
Bicarbonate, 604, 608
Bichromate of, 605, 616
Bitartrate of, 610
Bromide, 553–555, 605
Carbonate, 604, 607
Caustic potash, 604, 608
Chlorate, 605, 613
Citrate, 605, 609
Cyanide, 605
Ferrocyanide, 605, 616
Hypophosphite, 605
Iodide, 559, 605
Liquor potassæ, 604, 607
Potassii, 604
Nitrate, 605, 612
Permanganate, 605, 614
Potassa cum calce, 608, 648
Sulphate, 605, 611
Sulphite, 604
Sulphurata, 543, 605, 615
Tartrate, 605, 611
Tartrate (acid), 610
Potassium salts, action of, on the cardiac muscle, 316; on the vaso-motor nerves, 318; on the capillaries, 318; as refrigerant diuretics, 432; antagonism of, to barium, 493, 495; general sources and reactions of, 603, 604; action of, on the general system, 605, 607
Potassium, symbol and atomic weight of, 10; its relation to other members of a group, 16; and specially to lithium, 17; action of, on muscles, 127, 129, 135, 142, 143; on the vaso-motor centre, 319
Potassium acetate, action of, on bacteria, 94; as a remote antacid, 370; as a refrigerant diuretic, 432
Potassium bicarbonate, as a direct antacid, 370
Potassium bichromate, action of, on bacteria, 94
Potassium bitartrate, as a remote antacid, 370; as a saline purgative, 389; a hydragogue, 390; and a refrigerant diuretic, 432
Potassium bromide, action of, on bacteria, 93; on the nervous system, 204

Potassium carbonate, as a direct antacid, 370
Chlorate, action of, on bacteria, 94; as a refrigerant diuretic, 432
Potassium chloride, causes great contraction of the vessels, 281; neutralises the action of veratrine in certain cases, 308
Potassium chromate, action of, on bacteria, 94
Potassium citrate, as a remote antacid, 370; and refrigerant diuretic, 432
Potassium iodide, action of, on bacteria, 93; as a depressant expectorant, 255
Potassium nitrate, as a refrigerant diuretic, 432
Potassium permanganate, action of, on bacteria, 94
Potassium picrate, effects of, in destroying bacteria, 89
Potassium sulphate, as a hepatic stimulant, 403
Potassium tartrate, as a remote antacid, 370; as a saline purgative, 389; and sodium, as ditto, 389
Potato and potato water, experiments with, on oxygen, 69
Poultice, action of a warm, on the mucous membrane, 252; and on the chest, 256; use of a warm, in inflammation, 341, 342; as an emollient, 347; uses of, and how to apply different kinds of, with diagram, 468; a linseed, 877
Poultices, or cataplasms, 506
Powders, 524
Power, Mr., references to, 430, 997
Prayer-beads, 903
Precipitated sulphur, its preparation, &c., 544
Pregnancy, best mode of treating the vomiting of, 377
Preventive medicine, growing importance of, 5; chiefly owing to recent increase in knowledge of microbes and their action in causing disease, 5
Prevost on poisoning by mercury, 20
Preyer, references to, 150, 492
Prickly ash, 883
Prinus, (black alder), characters and action of, as an astringent, 894
Prolapsus of the uterus, emetics to be used with caution in persons suffering from, 376
Prophylactic, quinine as a, 948
Prophylaxis. *See* Preventive medicine
Protoplasm, action of drugs on, 59–63; method of experimenting on amœbæ and leucocytes, 59, 60; relation of motion and oxidation to, 65; oxidation of, 67; oxygen-carrying power of, 68; potassium salts poison or destroy, 605
Protoplasmic poison, anæsthetics act as a, 206; and potassium salts, 605
Prune, composition and use of, 917
Virginian prune, or wild cherry, 917
Prunes, as a laxative, 389
Prussic acid, 586
Ptomaïnes, alkaloids formed by putrefaction, 99; absorption and elimination, 101; action of, on muscle, 128; how formed, 401
Ptyalin, 75
Puerperal fever, micrococci present in, 99; singular cause of an epidemic, 104
Pulmonary sedatives, nature, number, and uses of, 246–250; divided into three classes, 246
Pulsatilla, characters and composition of, 836; action of the oil of, as a vesicant, 836; pure anemonin has a depressant action on the circulation, respiration, and spinal cord, 836; causing feeble pulse, slow respiration, paralysis, dyspnœa, and death, 837; uses of, as a diaphoretic and emmenagogue, 837
Pulse-rate, relation of, and arterioles, to blood-pressure, 271; diagrams of a pulse-curve, 272; effect of the arterioles on pulse-curves, 275; effect of drugs on the, 295; of irritant poisons on, 397; of arsenic, 715; of nitrite of amyl, 785; of chloral hydrate, 791; of purified chloroform, 798; of carbolic acid, 814; of creosote, 817; of staphisagria, 836; of anemonin, 837; of hydrochlorate of apomorphine, 849; of erythroxylon, 879; of caffeine, 871; of Jamaica dogwood, 913; of oil of valerian, 952; of gelsemium, 978; of tobacco, 993; of camphor, 1019; of Indian hemp or American cannabis, 1027; of squill, 1041; of hellebore, 1045; of veratrine, 1047
Pulvis amygdalæ compositus, 524, 914, 915, 1055
Antimonialis, 524, 652, 726, 729
Aromaticus, 524, 1015, 1016, 1037, 1038
Catechu compositus, 524, 868, 902, 951, 1015, 1016
Cinnamomi compositus, 524, 1016, 1037, 1038
Cretæ aromaticus, 524, 650, 1015, 1016, 1038, 1039, 1055
Aromaticus cum opio, 524, 650, 844
Compositus, 524, 650, 1055
Effervescens compositus, 524
Elaterini compositus, 524, 929, 1080
Glycyrrhizæ compositus, 524, 543, 899, 910, 934, 1055
Ipecacuanhæ compositus, 524, 611, 844, 949
Et opii, 524, 845, 949
Jalapæ compositus, 524, 610, 982, 1037
Kino compositus, 524, 844, 902, 1016

Pulvis—
Morphinæ compositus, 524, 848
Opii compositus, 524, 844, 901, 936, 1037
Rhei compositus, 524, 661, 1010, 1037
Scammonii compositus, 524, 982, 1037
Tragacanthæ compositus, 524, 901, 914, 1053, 1055
Pumpkin seed, composition and uses of, as an anthelmintic, 930
Pupil of the eye, structure of, and action of drugs on the, 216–227
Purgatives, aid the action of antiperiodics, and sometimes cure ague without them, 108; nature of, 388; divided into laxatives (list of the chief), 389; simple, 389; drastic, 389; saline, 389; hydragogues, 389; and cholagogues 390; action of, 390; Dr. Hay's researches into the action of, 391–394; the various uses of, 394, 395; to remove fæcal matters from the intestinal tube, 394; to remove liquid from the body, 394; to lower the temperature in fever, 395; to lower the blood-pressure, 395; they act as hepatic depressants, 407; as antipyretics, 421; as anaphrodisiacs, 451; as indirect emmenagogues, 453; resin of podophyllum as a, 839; gamboge as a, 869; buckthorn as a, 896; senna as a, 910; tamarind as a, 911; olive oil as, 967; manna as, 968; rhubarb as, 1011; castor oil as, 1024; oil of turpentine as, 1059; aloes as, 1044; treacle as, 1056; oatmeal as, 1056
Putrefaction, alkaloids formed by, 100, 101; antiseptics arrest the, 104, 105
Putrescine, 100
Pyæmia, micrococci present in, 99
Pye, Mr., references to, 296, 430
Pye-Smith, Dr., references to, 381, 988
Pyrethrum, 952
Pyrethrum, as a sialagogue, 357
Pyridine, in treatment of asthma (as tobacco-smoke), 261; action and uses, 823
Pyrocatechin, characters, action and uses of, 819
Pyrophosphate of iron, 752
Pyrophosphate of sodium, 628; action of, on the nerve-centres of the spinal cord, &c., 712
Pyroxylin, 873
Pyroxylinum, 873

Q.

Quassia, as a vermicide, 408
Quassia and quassia wood, properties and composition of, 892; action and uses of, 892; is simply a pure bitter stomachic, 892
Quebracho, as a depressant expectorant, 255
Quebracho bark, white, characters, action, and uses of, 969
Queen's root. *See* Stillingia
Quercus alba, the bark of, 1030; characters, action and use of, as a local astringent, 1031
Quillaia (saponin), characters, composition, action, and uses of, 918; action of, as a local irritant, 918; produces local paralysis and anæsthesia, 918; action of, on the voluntary muscles, the intestine, and the heart, 918; on digitalis, and on the nerve-centres, 919
Quince seed, characters and use of, 921
Quinicine, constitution of, 824
Quinidinæ sulphas, 504, 944
Quinidine, sulphate of, 943
Quinina, 504, 944
Quininæ sulphas, 504, 939, 944
Bisulphas, 944
Hydrobromas, 944
Hydrochloras, 943
Valerianas, 944, 952
Quinine, example of the empirical use of, 3; utility of, in ague, 3; action of, on protoplasmic movements, 61–63; on the mesentery of a frog, 62; on infusoria, 65; effects of, on oxidation, 69, 72; on bacteria, 89, 94, 95; as a disinfectant, 106; as an antiperiodic almost a specific in intermittent fevers, periodic headaches, neuralgias, &c., 107; action of, on ascidians, 114; on annulosa, 114; on muscle, 128 *et seq.*; on the spinal cord of a frog, 166; on the ear, 229; on taste, 230; on the respiratory centre, 241; on the frog's heart, 306; on the motor ganglia, 316; on the capillaries, 318; on the secreting cells of a gland, 354; arrests secretion of saliva, 361; lessens tissue-change, 415; as an antihidrotic, 441; value of, in the high temperature of the night sweats of phthisis, 443; as a direct emmenagogue, 453; one of the chief ecbolics, 454; as a poison, with its antidotes, 489; antagonism of, to atropine, 495
Quinine, characters and action of, 942
Bisulphate of, 942
Hydrobromate of, 942
Hydrochlorate of, 943
Sulphate of, 942
Valerianate of, 943
Physiological action of—general action, 944–948; special action—on the alimentary canal, 945; on the stomach, 945; on the blood, 945; on the circulation, 945; on the heart and respiration, 946; on tissue-change, and on the nervous system, 946; on the spinal cord, 947; on the muscles and uterus,

947; uses—as an antiseptic, a tonic, and an antiperiodic, 947; as an antipyretic and a prophylactic, 948; Warburg's tincture, 948

R.

Rabbits, experiments with drugs on, 54–56; two kinds of muscles in, red and white, 119; number of stimuli necessary to cause tetanus in the latter, 125; Stenson's experiment on the abdominal aorta of, 164; the cerebral hemispheres of, more developed than those of the frog, 184; effect of the removal of the cerebrum on, 184; easiest way of anæsthetising, 210, 211; effect of injecting drugs into the jugular vein of, 239; effect of the inhalation of tobacco-smoke on, 244; experiment on the ear of, 279; method of maintaining artificial circulation in the ear of, 280; action of the heart in, 287–289; difference between dogs and, in this respect, 287; the vagus centre in, stimulated through the nasal nerves, 296; Zülzer's experiments with, 342; experiments with, as to the antagonism of drugs, 493
Rabuteau, reference to, 28
Radicals, compound, nature of, 20; of carbon, 22, 23; of nitrogen, 23; of phosphorus, arsenic, antimony, and sulphur, 24; most of them possess a paralysing power over the motor nerves, 32
Raisins, composition and uses of, 896
Râles, moist, nature and treatment of, 252
Ranke, reference to, 175
Ranunculaceæ, 831 *et seq.*
Ranvier, L., references to, 50, 176, 336, 337
Raspberry, characters and use of, 919
Rat paste, as a poison, with its antidote, 491
Rational therapeutics, explanation and example of, 3
Rattle-snake poison, action of, on the red corpuscles of the blood, 63
Rectum, action of aloes on the, 1044
Red cinchona, 940
  Bark, 940
Red poppy petals, characters, composition, and use of, 862
Red rose, and red rose petals, 920
Red sandal-wood, 901
Red saunders, nature and use of, 901
Refined silver, 676
Refrigerants, nature and uses of, 360; tamarind as a, 911
Regnard, reference to, 94
Regurgitation, mitral and tricuspid, nature and cause of, 332; value of digitalis and other cardiac tonics in, 332, 333; the question of the use of digitalis in aortic regurgitation considered, 333; diagram to illustrate the tendency to syncope in aortic, 334
Reichert, reference to, 588
Remedies acting on the surface of the body, 340–351; irritants and counter-irritants, 340–347; subdivided into four classes, 340; rubefacients and their uses in chronic and acute inflammation, 340–345; diagrams illustrative of the action of, 341–343; list of the principal rubefacients, 344; friction one of the simplest, 344; vesicants and their uses, 345; pustulants, 346; and caustics, 346; general uses of caustics, 346; emollients and demulcents, 347; list of the principal demulcents, 347; and emollients, 347; action of demulcents and emollients, 347, 348; their therapeutic uses, 348; astringents, local and remote, and their uses, 349, 350; styptics and their action, 350, 351
Resin, composition and use of, 1061
Resin of podophyllum, preparation, characters, and composition of, 838; action of, as a drastic purgative, and a hepatic stimulant, 839; uses of, 839
Resin of scammony, 981
  Jalap, 982
Resina Copaibæ, 525, 912
  Guaiaci, 525
  Jalapæ, 525, 982
  Podophylli, 525, 838
  Scammoniæ, 525, 980, 981
  Scammonii, 525, 980, 981
Resins, 524
Resorcin, characters of, 818; action of, as an antiseptic, 818; on frogs, warm-blooded animals, and man, 818; uses of, 818; utility of, as an antipyretic, 818
Respiration, action of drugs on, 232–261; respiratory stimulants and depressants, 232; mechanism of, in some of the lower organisms, 232, 233; diagrams illustrative of this, 233; in the higher organisms, 234; muscles of, 235; centres of, 234–237; certain conditions of, called apnœa, dyspnœa, and convulsions, 237; action of certain conditions of the blood on, 237, 238; result of the presence or absence of air on external and internal, 238–240; action of drugs on the centre of, 240–244; diagram showing position of the centre of, and the afferent nerves which influence it, 242; method of testing the movements of, 243; action of drugs on the nerves of, 244; of irritant poisons on, 397; action of hydrocyanic acid on, 588; of strong solution of ammonia, 639; of mercury, 686; of gold, 754; purified

chloroform, 798–800; of creasote, 817; of salicylic acid, 820; of antipyrin, 824; of aconitine, 834; of staphisagrine, or stavesacre, 836; of anemonin, 837; of erythroxylon, 879; of caffeine, 871; of pilocarpine, 885; of physostigmine, 906; of quinine, 946; of strychnine, 974; of solanine, 983; of belladonna or atropine, 988; of digitalin, 996; of thymol, 1006; of monobromated camphor, 1019; of Indian hemp or American cannabis, 1027; of oil of turpentine, 1058; of veratrine, 1048; of extract of ergot, 1072
Respiratory centre, nature and functions of, 233–237; action of drugs on the, 240, 241; diagram showing the position of the, and the afferent nerves which influence it, 242; action of drugs on the respiratory nerves, 244; of sternutatories, 245; of pulmonary sedatives, 246–250; drugs which increase the activity of the, 254; connection of the, with the sweat-glands, 443; action of gold on the, 754; of alcohol, 770; of carbolic acid, 814; of quillaia (saponin), 919; of musk, 1078
Respiratory passages, in disease of the, warmth usually applied by means of inhalation, 348; action of gold on the, 754
Respiratory sedatives, 246
Respiratory tract, remedies which lessen irritation of, 249; action of opium on the, 860
Retina, action of drugs on, 226, 227
Rhamneæ, 895
Rhamnus Frangula, 895
Purshiana, 895
Rhamnus, as a purgative, 389
Rhatany root, composition, action, and use of, chiefly as an astringent, 868
Rheochord, Du Bois-Reymond's, 119
Rheum, 1010
Rheumatic gout, remarkable instance of accidental cure in, 341
Rhodium, symbol and atomic weight of, 10
Rhubarb, as a sialagogue, 357; as a purgative, 389; and as a cholagogue, 390; as a hepatic stimulant, 403; as a cholagogue purgative, 405
Rhubarb, 1011
Root, characters and composition of, 1010; action and uses of, 1011; as a tonic, astringent, and purgative, 1011
Rhus aromatica, in incontinence of urine, 898
Rhus glabra (sumach), nature and uses of, as an astringent, 898
Rhus toxicodendron (poison ivy), as a vesicant, 344; characters, action, and uses of, 898
Ribbert, reference to, 424 and *n*.
Richardson, B. W., reference to, 708
Richet, reference to, 125
Rigollot's mustard leaves, usefulness of, 864, 865
Ringer, Dr. S., references to, 46, 219, 306, 308, 339, 493, 568, 671, 688, 716, 975, 996
Roberts, Sir W., reference to, 363
Rochelle salt, as a hepatic stimulant, 403; nature and uses of, 624
Rodentia, 1077
Röhrig, reference to, 402
Romanes, references to his researches on the medusæ, 109, 110, 112
Root, Aconite, 831
Arnica, 957
Bark, cotton, 872
Bark, pomegranate, 926
Belladonna, 985
Black snake-, 837
Blood, 863
Calumba, 840
Colchicum, 1049
Culver's, 1001
Dandelion, 956
Gentian, 979
Hemidesmus, 970
Horse-radish, 866
Liquorice, 899
Pareira, 841
Pellitory, 952
Phytolacca, 1009
Pink-, 978
Pleurisy, 970
Podophyllum, 838
Poke, 1009
Queen's, 1022
Rhatany, 868
Rhubarb, 1010
Sassafras, 1020
Scammony, 980
Senega, 867
Sumbul, 937
Rosaceæ, 915
Rosaniline, 920
Rose, dog-, fruit of the, 920
Oil of, characters, &c., of, 920
Pale, 920
Red, 920
Petals, 920
Roseæ, 920
Roseine, 822
Rosemary, characters of, 1002
Oil of, characters, actions and use of, 1002; as a stimulant and carminative, 1003
Rosenberger, on bacteria, 85
Rosenthal, Professor J., references to, 127, 174, 242, 995
Rossbach, references to, 59, 64; on bacteria, 85, 248, 252, 253, 417, 440, 493, 606, 873, 1032
Rovighi, reference to, 190
Roy's tonometer, 269

Rubefacients, and their action in chronic and acute inflammation, 340–344; list of the principal, 344; friction one of the simplest, 344; acids as, 568; oil of rue as a, 881; oil of myrtle as a, 924; oil of cajeput, 924; camphor as, 1018
Rubiaceæ, 939
Rubidium, symbol and atomic weight of, 10; physiological action of, 27; action of, on the muscles, 135, 142
Rubus, characters and uses of, 919
Rue, as a direct emmenagogue, 453
Rue, oil of, nature and use of, 881; is a rubefacient, antispasmodic, and an emmenagogue, 881
Rumex, characters of, 1011; action of as an astringent, 1011
Ruminantia, 1077
Russell and Lapraik, reference to, 28
Russian bath, account of the so-called, 470
Rutaceæ, 881
Ruteæ, 881
Ruthenium, symbol and atomic weight of, 10
Rutherford, reference to, 402, 407, 839
Rye, ergot of, 1068

S.

SACCHARATED carbonate of iron, 742
Ferrous carbonate, 742
Iodide of iron, 750
Saccharine, properties and uses, 825
Saccharine substances are stimulating expectorants, 255
Saccharine solution of lime, as a direct antacid, 370
Sachs, reference to, 151
Saffron, 1038; as a colouring agent and carminative, 1039
Sage. *See* Salvia
St. Bartholomew's Hospital Reports, reference to, 167, *n.*
Sal volatile, as a cardiac stimulant, 328; composition and uses, 641
Salad oil (French), action of, on bacteria, 93
Salicaceæ, 1034
Salicin, character, action, and uses of, 1034; as an antipyretic, 1035
Salicinum, 505
Salicylates, test for, 595
Salicylate of lithium, 632
Salicylate of sodium, action of, in producing visions, 228; on the ear, 229; nature of, 628
Salicylates, antiperiodics, 107
Salicylic acid, action of, on enzymes, 78; bacteria, 91, 94, 95; an antiperiodic, 107; on the vaso-motor centre, 319; on the cardiac muscle, 316; on the pancreatic juice, 408; characters and tests of, 820; action of, in preventing the development of bacteria, 820; on the temperature, pulse rate, blood-pressure and respiration, and the ears, 820; on the circulation, 820; how excreted, 820; uses of, 820; natural *versus* artificial, 1035
Saline solutions, effects of, on infusoria, 64
Saliva, cause of, and mode of secretion, 353–357; diagram representing the general relation of nerves to the secreting cells and vessels of a gland, 354; diagram to show the nerves by which the secretion may be excited, 355; various causes which stimulate the secretion of, 356; action of sialagogues on the secretion of, 357; excretion by the, 358; diagram of the gastro-salivary circulation, 359; uses of, 359; action of erythroxylon on the secretion of, 879; of caffeine on ditto, 871; of Jamaica dog-wood, 913; of pellitory root, 953
Salivary centres, action of carbolic acid on the, 814
Salivary glands, action of drugs on, 353; of cantharides on the, 1092
Salivation, produced by mercury, 682; what it is in part due to, 686; action of gold in producing, 754; of curare, 976
Salix, characters, composition, and use of, 1034
Salt, effects of common, on protoplasmic movement, 60; on bacteria, 93; as a local emetic, 373; as a refrigerant diuretic, 432; effects of, in large quantities, on the general system, 600
Salts, inorganic, isomorphic, ferrous, manganous, ferric, physiological action of, 27; of barium, action of, on muscles, 130; of zinc and copper, action of, on the respiratory centre, 241; results of experiments with several metallic, 281; of calcium and distilled water, prolong the beating of the frog's heart, 306
Salts of the cinchona alkaloids, 944
Salts of the heavier metals as astringents, 349
Salvia, characters, action, and uses of, 1008; as a tonic, carminative, and an astringent, 1008
Samarium, symbol and atomic weight of, 10
Sandal wood, red, 901
Sanguinaria (bloodroot), action of, on the vaso-motor centre, 319; as an alterative, 413; characters and composition of, 863; action of, on the intestinal canal, and the medullary centres, 863; on the brain and spinal cord, 863; chiefly used as a stimulant expectorant, 863

Sanitas, nature and use of, 1060
Santal, oil of, characters, action, and use of, 1021
Santalaceæ, 1021
Santini, reference to, 190
Santonica, as a vermicide, 408; as a stimulant diuretic, 433; characters and composition of, 954
Santonin, as a vermicide, 408; characters and preparation of, 954; action of, on the cerebrum and medulla of the frog, 954; effects of large doses on man, 955; action of, on the vision and on the urine, 955; used only as a vermicide, 955
Santoninate of sodium, 629
Santoninum, 505, 954
Sapindaceæ, 897
Saponin, action of, on the respiratory centre, 241; on the nose, 245; as a stimulating expectorant, 255; action of, on the vagus-ends of the heart, 317; on the inhibitory ganglia, 317; on the cardiac muscle, 316; on the heart, 338; antagonistic action of, 494–496; nature, action, and uses of, 918. *Vide* also Quillaia
Sapotaceæ, 963
Saprine, 100
Sarsaparilla, as an alterative, 413; as a stimulant diuretic, 433; nature and action of, 1051; as a diuretic, tonic, and alterative, 1052
Sassafras, characters of, 1020
  Oil of, 1020; action and use of, as a diaphoretic, 1020
  Pith, characters and uses of, 1020; as a demulcent, 1020
  Root, characters and composition of, 1020
Sassy bark, action of, on the nose, 245; composition, action, and use of, 915
Savin, as a stimulant diuretic, 433; as a direct emmenagogue, 453; as a chief ecbolic, 454; as a poison, with its antidotes, 491
Savine, 1064
  Tops, 1064
Saunders, red, nature and use of, 901
Scammony, as a drastic purgative, 389; as a vermifuge, 408
Scammony, characters, &c., of, 980
  Resin of, 981; action and use of, as a drastic purgative and a vermifuge, 982
  Root, 980
Scandium, symbol and atomic weight of, 10
Scharrenbroich, reference to, 72
Schiff, Professor, references to, 236, 297, 363, 399, 715
Schizomycetes, 82. *See* Bacteria
Schlesinger, reference to, 102
Schmidt-Mülheim, reference to, 399
Schmiedeberg, Professor, references to, 56, 100, 142, 294, 312, 492, 995, 997, 1098
Schönlein, reference to, 133
Schroeder, Von, reference to, 859
Schroff, Von, references to, 151, 158, 228
Schroff (junr.), reference to, 863
Schulte, reference to, 72
Schultzen, Otto, reference to, 850
Schweigger-Seidel, reference to, 426
Scillain, action of, on the cardiac muscle, 316; as a cardiac tonic, 331
Scoparin, 900
Scurvy, due to imperfect nutrition, 412; is supposed to be due to a deficiency of potassium salts in the blood, 412; is removed by fresh vegetables or lime-juice, 412
Scutellaria, 1008; characters and uses of, 1008; has been used as a nervine tonic, 1008
Scybala, diagram illustrating diarrhœa depending on the presence of, in the intestine, 388
Sea-bathing, 469
Secretion, from the bronchial tubes, 250; from the air-passages, 251; nature of the, from the mucous membrane, 251; action of drugs on the, 252; action of belladonna or atropine on, 250, 988
Secretion, in the stomach, action of drugs on, 363
Secretions, action of opium on the, 853; physostigmine, 907
Sedatives, nature and uses of, 157; pulmonary, 246–250; cardiac, 338, 339; vascular, 339; gastric, 376; vesical, 444; urinary, 445
Seed, American worm-, 1009
  Oil, cotton, 872
  Oil of flax, 877
  Pumpkin, 930
  Quince, 921
Seeds, Colchicum, 1049
  Jequirity, 903
  Stramonium, 991
Seegen, Professor, references to, 399, 538
Selective action of drugs, 34
Selenic acid, physiological action of, 27
Selenium, symbol and atomic weight of, 10
Senega root, composition, preparation, action, and use of, 867, 868; as a stimulating expectorant, diuretic, and diaphoretic, 868; as a general emetic, 373. *See* also Saponin
Senna, characters, composition, action, and uses of, 909
  Alexandrian, 909
  Tinnevelly, 909
Sensation, anæsthetics destroy, 203
Septic poisoning, and bacteria, 88; effects of, and modes in which it may be produced, 104, 105

Series, arrangement of the animal kingdom and of the elements in, 17; Mendelejeff and Meyer the perfecters of this system of classification, 17; Mendelejeff's classification in, 19; difference in the even and uneven series, 18; irregularities in the system, 18, 20
Serpentaria, 1012
Serpentary Rhizome, characters, action, and uses of, 1012; as a tonic, diaphoretic, and diuretic, 1012
Serum, and blood, action of, on the frog's heart, 308, 309
Sesamum, oil of, characters and action of, 1002
Setschnow's centres, 165; experiment on a frog, 166
Severini, reference to, 282
Shenstone, Mr., reference to, 975
Sherry, characters and uses of, 776; wine, 896
Shorthouse, Dr., reference to, 215
Sialagogues, nature and action of, 353–356; diagrams illustrative of the nerves and glands acted on by, 354, 355; divided into three classes, reflex, specific, and mixed, 356, 357
Sialics, and anti-, nature and action of, 360
Silicon, symbol and atomic weight of, 10; its relation to other members of a group, 16
Silver, symbol and atomic weight of, 10; physiological action of, 27
Silver, characters, action, and uses of—
Cyanide of, 679
Iodide of, 680
Nitrate of, 676
Diluted, 677
Moulded, 677
Oxide of, 679
Refined, 676
Silver nitrate, as a caustic, 344; as an astringent, 349; as a local sedative, 376
Simarubaceæ, 892
Simpson, Sir J. Y., his mode of administering chloroform, 209; and discovery of the use of, as an anæsthetic, 212
Sipping, the action of, a powerful stimulant to the brain, 194; increases the secretion of the bile, 406; and abolishes the inhibitory action of the vagus on the heart, 406; the value of Carlsbad water in hepatic disease is probably owing to its being taken in sips, 407
Sitz bath, cold, 464; hot, 467
Skatol, action of, on bacteria, 94
Skin, Action of Drugs on the, 437–443; as diaphoretics and sudorifics, 437; effects of warmth on the, 437; excretion by the sweat-glands, 439; relation between sweat-glands and kidneys, 439; action of the, in regulating temperature, 440; antihidrotics, or anhidrotics, 441; diagram to illustrate the action of anhidrotics, 442; the night-sweats of phthisis, 442; cause of profuse sweating, 443; application of drugs by the, 457; three methods of applying drugs to the—(1) by epidermic application, 457–459; power of absorption of the, 458, 459; by baths, 459; the cold bath, 460; objects of the cold bath, 460–463; the cold pack, 463; cold sponging, 463; cold douches, 463; the sitz bath, 464; cold foot-bath, 465; cold compresses, 465; tepid baths, 466; warm baths, 466; hot baths, 467; hot foot-bath, 467; hot sitz bath, 467; poultices, 468; medicated baths, 469; acid bath, 469; alkaline baths, 470; sulphurous baths, 470; the mustard bath, 470; the pine bath, 470; vapour baths, 470; calomel fumigation, 471; air baths, 471; the Turkish bath, 471; by friction, 472; by inunction, 473: (2) by endermic application, 474; (3) by hypodermic application, 474; diagram of syringe for hypodermic injection, 475; objections to hypodermic injections, 476; action of hydrocyanic acid on the, 586; of alkalies, 597; soda as a stimulant to the, 620; of dried alum, 655; of nitrate of silver, 677; of arsenic, 713; of antimony, 722; of iron salts, 739; of alcohol, 767, 772; of spirit of ether, 781; of purified chloroform, 797; of opium, 861; of mustard, 865; of pilocarpine, 886; of chrysarobin, 909; of oil of copaiva, 913; of Jamaica dogwood, 913; of oil of eucalyptus, 925; of ipecacuanha, 949; of tannic acid, 1032; of colchicum, 1050
Skull-cap. *See* Scutellaria
Sleep, remedies which induce, 196; the cerebro-spinal system functionally inactive in, 196; certain parts of the nervous system may still remain active, 196; the inactivity caused by anæmia, 197; state of the arteries of the brain during, 197; and in normal, 197; the brain anæmic during, 197; two things necessary to produce, 197; to lessen circulation in the brain, and to lessen its functional activity, 197; position may sometimes induce, 197; cold to the abdomen prevents, and warmth procures, 198; warmth to the stomach in the shape of warm food and drinks, causes, 198; efficacy of the wet pack in inducing, 198; cold feet prevent, 199; and cooling the surface of the body sometimes induces, 199; opium and morphine the chief hypnotics or inducers of, 199; list of the principal hypnotics, 199; nature of the reflexes in ordinary and mesmeric, 204

Slippery elm, 1025
Smell, action of drugs on, 230
Smelling salts, stimulating action of, on the brain, 194
Smells, remedies for destroying disagreeable, 103–107
Smilaceæ, 1051
Smoke, utility of inhaling certain kinds of, in asthma, 481
Smut, corn, characters and action of, 1073
Snail, structure of the heart of the, 322
Snake-bite, as a poison, with its antidote, 491; action of strong solution of ammonia in, 639
Snake-poison, effects of, on the blood, 72; action of ammonia in, 329
Sneezing, drugs which cause, their number, nature, and uses, 245, 246
Snuff, Ferrier's, composition and uses of, 731 and *n*.
Soap, as an emollient, 347
Soap, curd, 1079
Soap, hard, characters, &c., of, 966
Soft, 966, 967
Soap, soft, action of, on bacteria, 94, 95
Socaloïn, nature and action of, 1042
Soda, as a caustic, 344; difference between the action of, and potash on the intestines, 383
Sodium Salts, nature, action, and uses of—
Arseniate of, 720
Biborate of, 624
Bisulphite of, 630
Borate of (borax), 624
Bromide of, 555
Caustic, 621
Chlorate of, 627
Chloride of, 618
Hyposulphite, 630
Iodide of, 563
Nitrate of, 618
Pyrophosphate of, 628
Salicylate of, 628
Santoninate of, 629
Solution of soda, 622
Sulphite of, 629
Sulphocarbolate of, 626
Tartarated, 624
Valerianate of, 630
Sodium salts, sources of, 617; reactions of, 617; preparations of, 618; impurities of, 618; tests for impurities in, 619; general action of, 619; their action, in large doses, on muscle and nerve, 619; action of, on the intestines, 383; as refrigerant diuretics, 432
Soda tartarata, 610
Sodium hyposulphite, action of, on bacteria, 89
Sodium sulphate, action of, on bacteria, 89
Sodii arsenias, 720
Arseniatis, liquor, 720
Citro-tartras effervescens, 622, 1055
Iodidum, 557
Salicylas, 820
Santoninas, 954
Valerianas, 778
Sodium, symbol and atomic weight of, 10; its relation to other members of a group, 16; physiological action of, 27; character and preparation of, 617
Sodium Acetate, as a remote antacid, 370, 624
Benzoate, as a hepatic stimulant, 403, 628
Bicarbonate, action of, on the ear, 229; as a direct antacid, 370, 623; preparation, characters, and uses of, 622
Carbonate, as a direct antacid, 370; preparation, characters, and uses of, 621
Chloride, as a vermicide, 408; how prepared, 618
Citrate, as a remote antacid, 370
Ethylate (liquor), 618
Hypophosphite, 627
Phosphate, as a hepatic stimulant, 403, 626
Salicylate, as a hepatic stimulant, 403
Santoninate, as an anthelmintic, 629
Sulphate, as a hepatic stimulant, 403; antagonism of, to barium, 495
Valerianate, 618
Sokoloff, reference to, 138
Solanaceæ, 983
Solution of—
Acetate of ammonium, 641
Iron, 744
Ammonia, 640
Basic ferric sulphate of iron, 743
Bichromate of potassium, 616
Carbonate of magnesium, 661
Chloride of calcium, 651
Chloride of iron, 745
Chloride of tin, 706
Chloride of zinc, 671
Chlorinated lime, 551
Citrate of ammonium, 642
Citrate of bismuth, 733
Citrate of iron and quinine, 749
Citrate of magnesium, 661
Gelatine, 1086
Iodide of arsenic and mercury, 721
Litmus, 1067
Perchloride of iron (strong), 745
Permanganate of potassium, 614
Pernitrate of iron, 747
Persulphate of iron, 742
Potash, 607
Red prussiate of potash, 617
Soda, 622

Solution of—
Subacetate of lead, 704
Subsulphate of iron, 743
Tersulphate of iron, 742
Turmeric, 1037
Yellow prussiate of potash, 617
Solution, test-, of albumen, 1085
Solutions, 517
Sonnenschein, reference to, 101
Soporific, Indian hemp or American cannabis as a, 1027; lupulin as, 1028
Soporifics, 196. *See* Hypnotics
Space, dead, 1100 (Appendix)
Spanish flies, 1091
Sparteine, action of, on inhibitory ganglia, 317
Spasm, nature and cause of, 212; general mode of treatment, 212–214; list of antispasmodics and adjuvants, 213–214
Spearmint and oil, as a carminative, 379
Spearmint, oil of, characters, action, and use of, 1005; as a carminative and stimulant, 1005
Spectrum of simple and compound bodies, 12; of calcium chloride, 12; of lithium, 13; of calcium, 13; hæmoglobin and its derivatives, 72
Spence, Dr. A. J., reference to, 181
Spermaceti, 1085; as an emollient, 1085
Sphacelinic acid, 1070
Sphærobacteria, 83
Sphincter muscles of the iris, nature and functions of, 217
Spider's-web, as a styptic, 350
Spigelia, characters and use of, 978; as an anthelmintic, 978
Spinal centre for respiration, 236; vasomotor, 287; for secretion of sweat, 437; for the generative organs, 447
Spinal cord, action of drugs on the, 159–182; the three functions of the, 159; action of drugs on the conducting power of the, 159; mode of testing this, 159; mode of ascertaining the power of the, to conduct sensory impressions, 159; and reflex stimuli, 160; and of the time required for transverse and longitudinal conduction, 161; diagrams illustrative of this, 161, 162; mode of experimenting on the action of drugs on the reflex action of the, 163; direct, indirect, and inhibitory paralysis of the, by drugs, 164; list of, and uses of, depressants for the, 165; inhibitory paralysis of the, 165; experiments illustrative of this, 166; diagram to illustrate inhibition in the, 169; explanation of the actions of certain drugs on the, on the author's hypothesis, 171–177; stimulating action of drugs on the reflex powers of the, 177; Magendie's series of experiments on the action of poison on, 177–181; diagram illustrating Magendie's method of investigating the mode of action of strychnine on, 179; stimulants for the, and their uses, 181; antagonism between drugs acting on the respiratory centre and the, 494; action of ammonium salts on the, 603; of bromide of potassium, 553; of ammonium chloride, 636; of manganese salts, 753; of spirits of ether, 782; of nitroglycerin, 789; of chloral hydrate, 792; of carbolic acid, 814; of aconitine, 833; of delphinine, 836; of codeine, 850; of opium, 854; of sanguinaria, 863; of erythroxylon, 879; of physostigmine, 905; of Jamaica dogwood, 913; of oil of eucalyptus, 925; of coniïne, 932; of quinine, 947; of oil of valerian, 952; of strychnine, 975; of curare, 976; of gelsemium, 978; of belladonna or atropine, 987; of tobacco, 992; of digitalin, 995; of thymol, 1006; of colchicum, 1050
Spinal depressants, number, nature, and uses of, 165; stimulants, 181
Spirit, proof, 776; rectified, 776; of French wine, 776
Spirit of chloroform, as a cardiac stimulant, 328
Spirit of ether, as a cardiac stimulant, 328
Spirits, 525
Spirits, as a carminative, 379
Spiritus ætheris, 525, 780
Compositus, 525, 780, 783
Nitrosi, 525
Ammoniæ, 525, 638
Aromaticus, 525, 638, 640, 641, 891, 1015
Fœtidus, 525, 638, 932
Anisi, 525, 935
Armoraciæ, compositus, 525, 866, 888, 1015
Aurantii, 525, 889
Cajuputi, 525, 924
Camphoræ, 525, 1018
Chloroformi, 525, 796
Cinnamomi, 1017
Cinnamonii, 525
Frumenti, 525
Gaultheriæ, 526, 963
Juniperi, 526, 1064
Compositus, 526, 937, 1064
Lavandulæ, 526, 1003
Limonis, 526, 890
Menthæ piperitæ, 525, 526, 1004
Viridis, 526, 1005
Myrciæ, 526, 889, 923
Myristicæ, 525, 526, 1015
Odoratus, 526, 887, 890, 891, 1003, 1004
Rectificatus, 525
Rosmarini, 525, 1003

Spiritus—
Tenuior, 525
Vini gallici, 526
Spiritus vini gallici, mistura, 1086
Spirobacteria, 83
Splanchnics, the, and the kidneys, 428, 429
Spleen, action of alcohol on the, 766; action of physostigmine, 907; of oil of eucalyptus, 925
Squills, action of, on the blood-vessels, 249; as a stimulating expectorant, 255; as a cardiac tonic, 331; as a general emetic, 373; as a hydragogue diuretic, 432; action and use of, 1040; in large doses, 1041; on the pulse, and as a diuretic and expectorant, 1041
Squirting cucumber fruit, 928
Stannius, reference to, 974
Stannius's experiments as to the actions of the various cavities of the frog's heart, 319–322
Staphisagria, or stavesacre, characters and composition of, 836; action of, in frogs, 836; delphinine acts like aconitine on the pulse and respiration, 836; on the spinal cord and medulla, 836; on the vagus and the heart, 836; uses of, 836
Star-anise, characters and composition of, 840
Starch, 1053; characters and uses, 1053
Starch, is converted into dextrin and sugar by boiling with acids, 73; as a demulcent, 347
Stavesacre, 836
Stearic acid, action of, on bacteria, 94
Stenhouse, Dr., reference to, 900
Stenosis, mitral, cardiac tonics useful in, 333; aortic, digitalis of doubtful use in, 333
Stenson's experiment on the abdominal aorta of a rabbit, 164
Stercoræmia, 101
Sterculiaceæ, 875
Sternutatories or errhines, number, nature, and uses of, 245, 246; contra-indications of, 246; must be used with caution in certain cases, 246
Stevens, reference to, 996
Stewed apples, as a laxative, 389
Stillingia, as an alterative, 413; characters and uses of, 1023; as an alterative, 1023
Stimulant, beef-tea *versus* alcohol as a, 774
Stimulants, spinal, 181; nerve, 192; cerebral, 192; cardiac, 328; vascular, 330; hepatic, 403; diuretic, 433
Stirling, reference to, 125
Stolnikow, reference to, 859
Stomach, impaired power of the, in the aged, 352; action of drugs on, 361; normal and abnormal condition of, 362; irritability of the, 363; diagram to illustrate the supposed nervous connections of the, 362; three factors in the process of digestion in the, 363; action of drugs on secretion in the, 363; drugs which stimulate the secretion of the gastric juice, 363; importance of thorough mastication, 364; supply of artificially digestive substances to the, 364; action of drugs on the movements of the, with classes of drugs, 365; absorption from the, 368; action of calomel on the, 369; use of gastric sedatives in relieving pain in the, 376; and vomiting from the, 376; list of sedatives which have the most powerful action on the, in certain circumstances, 377; action of, in expelling gases from the, 378; drugs which tend to prevent fermentation in the, 378; they remove pain and distension of, and diminish local spasm, 379; action of irritant poisons on the, 395–397; diagram to show the nervous mechanism by which the action of the heart may be depressed by irritation of the, 396; diagram of the liver, intestines, and, 404; application of drugs to the 482; the stomach-pump, 483; the gastric syphon, and its use, 483; action of acids in the, 569; of alkalies, 598; of the metals zinc, copper, cadmium, and silver, 666; of nitrate of silver, 678; of mercury, 684; of phosphorus, 711; of arsenic, 713; of antimony, 722; of iron salts, 739; of gold, 754; of alcohol, 765, 766; of spirit of ether, 781; of chloral hydrate, 791; of purified chloroform, 797; of creasote, 818; of aconitine, 835; of pilocarpine, 885; of physostigmine, 907; of quinine, 945; of tannic acid, 1032; of oil of turpentine, 1058
Stomach cough, probable origin of the so-called, 248; rationale of the, 248
Stomachic, black pepper as a, 1013; lupulin as, 1028
Storax, characters, composition, and use of, 1030; prepared, 1030
Stramonium, as a narcotic, 200; as a general anodyne, 201; action of, on the lungs, on the respiratory centre, and on the ends of the vagi, 249, 250; on the vagus-centre, 317; on the vaso-motor centre, 319; as a poison, with its antidote, 491
Stramonium leaves, characters of, 991
Seed, 991
Seeds, characters, action, and use of, 991; as an antispasmodic, 992
Stricker's stage, uses of a, 60
Stromuhr, Ludwig's, 294
Strontium, symbol and atomic weight of, 10; physiological action of, 27; action

of, on the muscles, 135, 142; causes contraction of the vessels, 281
Strophanthin, as a cardiac tonic, 331; as a refrigerant diuretic, 432
Strophanthus hispidus, action of, on the cardiac muscle, 316; as a cardiac tonic, 331; composition, action, and uses, 1099 (Appendix)
Strychnina, 505, 972
Strychnine, cumulative action of, 42; effect of, on protoplasm, 61; has little power on infusoria, 65; effects of, on oxidation, 69, 72; action of, on medusæ, 111; on mollusca, 114; on ascidians, 114; and on annulosa, 115; on muscle, 122, 144; effect of, on the spinal cord, 162, 172; effect of, in causing tetanus, 173, 174, 175; Magendie's series of experiments on the action of, 177–181; as a spinal stimulant, 182; action of, on the brain of dogs, 188; and of men 195; on the retina, 227; on the ear, 229; on taste and the sense of smell, 230; on the respiratory centre, 240; as a stimulating expectorant, 255; action of, on the vaso-motor centre, 287, 319; as a cardiac tonic, 331; as a vascular tonic, 336; fails to poison when the vagi are divided, 369; as an antihidrotic, 441; action of, in lessening the night-sweats in phthisis, 443; as an aphrodisiac, 450; as an indirect emmenagogue, 453; as a poison, with its antidote, 491; antagonism of, to other drugs, 494–496; antagonistic action of, to chloral, 494–496
Strychnine, preparation and characters of, 972
Sulphate of, action of, on low organisms, oxidation, and fermentation, 972; on the reflex nerve-centres, on the intestines and sensory nerves, 972; poisoning by, and treatment for, 973; action of on the alimentary canal, on the blood and circulation, on the heart, 973; on the respiration and muscles, 974; on the nervous system and brain, 974; on the spinal cord, 975; uses of, 975
Stuart, Anderson, references to, 127, 142
Sturiones, 1086
Styptics, action of, 350; action of cold to surface of body, 351; of hot water as a, 351; dried alum as a, 655; strong solution of perchloride of iron one of the most powerful styptics, 746; matico as a, 1015
Styracaceæ, 963
Styria, arsenic-eaters of, account of the, 714
Subchloride of mercury, 691
Sublimed sulphur, its preparation, characters, &c., 543
Subnitrate of bismuth, 732
Subsulphate of mercury, as a local emetic, 373
Succus belladonnæ, 527, 985
Conii, 527, 931
Hyoscyami, 527, 990
Limonis, 527
Mori, 527
Scoparii, 527, 900
Taraxaci, 527, 957
Sudorifics, action of, on the secretion of sweat, 437
Suet, 1078; prepared, 1078
Suffocation, cause of, 239; produced by the action of certain poisons on the respiratory tract, 398
Sugar, 1055; as a vehicle and corrigent, 1055; preservative and antiseptic, 1055; sugar, refined, 1055
Sugar of milk, 1080
Sulphæmoglobin, 72
Sulphate of Aluminium, 656
Ammonium, 642
Atropine, 986
Beberine, 1021
Copper, 675
Hyoscyamine, 991
Iron, 741
and Ammonium, 749
Dried, 741
Granulated, 741
Precipitated, 741
Magnesium, 659
Morphine, 848
Quinidine, 943
Quinine, 942
Potassium, 611
Sodium, 625
Strychnine, 972
Zinc, 671
Sulphate of aluminium, action of, on bacteria, 93
Sulphate of beberine, action of, on protoplasm, 61
Sulphate of potassium, as a cholagogue purgative, 405
Sulphate of potassium, sodium, and magnesium, as saline purgatives, 389
Sulphate of sodium, as a cholagogue purgative, 405
Sulphates, general action of, 602
Sulphide of mercury, red, 697
Sulphites, test for, 595
Sulphite of sodium, 629
Sulphocarbolate of sodium, 626
of zinc, 672
Sulphocyanide of potassium, action of, on mollusca, 114
Sulpho-vinate of sodium, as a saline purgative, 389
Sulphur, symbol and atomic weight of, 10; its relation to other members of a group, 16; as a stimulating expectorant, 255; as a laxative and purgative, 389

Sulphur and its elements, 543–547; sublimed sulphur, flowers of sulphur, 543; confection of sulphur, 544; sulphur ointment, 544; washed sulphur, 544; alkaline sulphur ointment, 544; precipitated sulphur, lac sulphuris, or milk of sulphur, 544; use of sulphur in skin diseases, 544; sulphuretted hydrogen, or hydrogen sulphide, 545; general action of sulphuretted hydrogen, 545; special action, 546; action and uses of sulphur, 546; iodide of, 557
Sulphur lotum, 544
Precipitatum, 544
Sulphurated potash, 615
Sulphuretted hydrogen, action of water of, on bacteria, 94; as a poison, with its antidote, 486; its preparation and properties, 545, 546
Sulphuric acid, physiological action of, 27; direct and local action of, 34; effects of, on alcohol, 73; on bacteria, 91, 93; as a caustic, 344; as a poison, with its antidote, 487; properties and uses of, 570
Sulphuris iodidum, 544, 557
Sulphurous acid, action of, on enzymes, 78; on bacteria, 91; properties and uses of, 570
Sulphurous bath, uses of a, 470
Sumach as an astringent, 898. *See* also Rhus glabra
Sumbul, as an antispasmodic, 214; characters and use of, chiefly in hysteria, 937
Root, 937
Suppositoria acidi carbolici cum sapone, 526, 813, 1079
Acidi tannici, 526, 875, 1031, 1053
cum Sapone, 526, 1079
Hydrargyri, 526, 686, 875
Iodoformi, 526, 804, 875
Morphinæ, 526, 847, 875
cum Sapone, 526, 847, 1053, 1079
Plumbi composita, 526, 703, 875
Suppositories, nature and uses of, 484; list of, and composition, 526
Surgical operations, use of antiseptics in, 104; Sir Joseph Lister on the best mode of performing, 815
Sustschinsky, reference to, 313
Sweat, mode of secretion of, 437; various causes which arrest or increase the secretion of, 437; excretion by the sweat-glands, 439; relation between the sweat-glands and the kidneys, 439; uses of diaphoretics and sudorifics in increasing the secretion of, 437; action of antihidrotics on the secretion of the, 441; the night-sweats of phthisis, 442; diagram to illustrate the action of antihidrotics, 442; connection of the respiratory centre with the sweat-glands, 443; various drugs which act on the secretion of, 443; action of carbolic acid on the sweat centres, 814; action of opium on the secretion of, 855; and of erythroxylon, 879
Sylvester's plan of artificial respiration, 802
Syncope, caused by sudden change of posture, 205; by the use of anæsthetics, 207–210; by fainting and shock, 264, 265; by the incautious use of cardiac tonics, 335; by the lowness of the blood-pressure, 334; by the administration of digitalis, 335
Syphon, gastric, nature and uses of, 483
Syringe, diagram of a, for hypodermic injection, 475; of a vulcanite, for injecting solutions into the ear, 477; of a vulcanite, for injecting solutions into the urethra, 484
Syrupus Acaciæ, 527, 914
Acidi citrici, 527, 581
Hydriodici, 527
Allii, 527, 1040
Althææ, 527, 875
Amygdalæ, 527, 915
Aurantii, 527, 888
Floris, 527, 888
Florum, 888
Calcii lactophosphatis, 527, 652
Calcis, 527, 648
Cheken, 924
Chloral, 527, 791
Ferri Bromidi, 527
Iodidi, 527, 557, 750
Phosphatis, 527, 579, 751
Quininæ et Strychninæ Phosphatum, 527, 751, 942, 972
Hemidesmi, 527, 970
Hypophosphitum, 527, 627, 653
cum ferro, 527, 750
Ipecacuanhæ, 527, 949
Krameriæ, 527, 868
Lactucarii, 527, 957
Limonis, 527, 581, 890, 891
Mori, 527, 1028
Papaveris, 527, 843
Picis Liquidæ, 527, 1062
Pruni Virginianæ, 527
Fluidum, 917
Rhei, 527, 528, 938, 1010, 1011
Aromaticus, 528, 922, 1010
Rhœados, 528, 862
Rosæ, 528, 920
Gallicæ, 527, 920
Rubi, 528
Idæi, 528, 919
Sarsaparillæ compositus, 528, 910, 920, 963, 1020, 1052
Scillæ, 527, 528, 1041
Compositus, 528, 726, 730, 868, 1041
Senegæ, 528, 868
Sennæ, 527, 528, 910, 938

Syrupus—
Tolutanus, 527, 528, 903
Zingiberis, 527, 528, 1037
Syrups, 527
Szpilman, reference to, 139

T.

Tablets, 528
Tamarind, character, composition, and use of, 911
Tannate of sodium, action of, on the kidneys, 435
Tannic acid, as an astringent, 349; preparation and properties of, 1031; action of, on the skin, mucous membranes, mouth, and stomach, 1032; on the blood and kidneys, 1032; uses of, externally and internally, 1032
Tannin, action of, on bacteria, 94; on the mucous membranes, 253; as a styptic, 350; as a vermicide, 408; action of, on the kidneys, 435; indigestibleness of tea partly due to the tannin it contains, 870
Tansy, characters and uses of, 953; as a diuretic, stimulant, emmenagogue, and anthelmintic, 954
Tantalum, symbol and atomic weight of, 10
Tar, as a stimulating expectorant, 255; action and use of, 1063; as a stimulant, 1063
Tar, oil of, 1063
Taraxacum, 956
Taraxacum, as a stimulant diuretic, 433
Tartar emetic, effects of, on the blood, 73; as a depressant expectorant, 255; action of, on the system, in causing vomiting, 373; as a general emetic, 373; nature and use of, 725, 726; ointment, 730
Tartarated soda, as a remote antacid, 370
Tartaric acid, as a poison, with its antidote, 487; properties of, &c., 580
Tartrates, test for, 595
Tartrate of iron and ammonium, 747
Potassium, 747
Potassium, 611, 624
Sodium, 624
Taste, action of drugs on the sense of, 230
Tea, characters, action, and uses of, 869; a powerful cerebral stimulant, 870; indigestibleness of, partly due to the tannin it contains, 870
Teeth, danger of extracting the, with chloroform, in certain cases, 208; action of drugs on the, 352; importance of the, for mastication, 352; what the decay of the, is chiefly due to, 352, 652; the best substances for cleansing the, 352; and for protecting and preserving the gums, 353, 598; remedies for toothache, 353, 652, 815, 817, 860
Teleosteæ, 1087
Tellurium, symbol and atomic weight of, 10; its relation to other members of a group, 16
Temperature, effect of, on the action of drugs, 44–48; on the secreting nerves, 46; of the body half a degree higher in India, 48; effects of, on ferments, 75; on mould-fungi, 82; on bacteria, 88; excess of, injurious to the human organism, but destructive of bacteria, 102; effects of, on the rhythmical action of medusæ, 110; on mollusca, 114; on muscles, 128 *et seq.*; effects of, on the poisonous action of guanidine, 175; the, of warm-blooded animals; 416; action of antipyretics on, 416; action of the skin in regulating the, 440; action of salicylate of sodium on the, 629; of mercury on the, 686; of alcohol, 768; of chloral hydrate, 792; of carbolic acid, 814; of salicylic acid, 820; of aconitine, 834; of erythroxylon, 879; of caffeine, 872; of pilocarpine, 886; of oil of eucalyptus, 925; of solanine, 983; of belladonna or atropine, 988; effects of, on the action of digitalin, 998; on thymol, 1006; of camphor, 1019; of Indian hemp or American cannabis, 1027; of oil of turpentine, 1058; of thuja, 1063; of veratrine, 1048
Tents, nature and uses of, 485
Tepid baths, 466
Terbium, symbol and atomic weight of, 10
Terebene, action and uses, 1060
Terebinthaceæ, 897
Ternströmiaceæ, 869
Tetrachloride of carbon, as an anæsthetic, 205
Tetra-amyl-ammonium iodide, action on motor nerves, 150
Tetra-ethyl-ammonium iodide, action on motor nerves, 150
Tetra-ethyl-arsonium iodide, action on motor nerves, 150
Tetra-ethyl-arsonium and zinc double iodide, action on motor nerves, 150
Tetra-ethyl-arsonium and cadmium double iodide, action on motor nerves, 150
Tetra-methyl-ammonium iodide, action on motor nerves, 150
Thalamifloræ, 831 *et seq.*
Thallin, character and action of, 825
Thallium, symbol and atomic weight of, 10; physiological action of, 27
Thebaine, as a spinal stimulant, 181; action of, on the respiratory centre,

240; on the vaso-motor centre, 319; antagonism of, to chloral, 495, 496 acts like strychnine, 975
Theine, action on sensory nerves, 155; local anæsthetic action of, 870; different from caffeine, 871 and *n*.
Theobroma, oil of (cacao-butter), characters, uses, &c., of, 875
Theobromine, action of, on muscles, 130
Therapeutics, definition of, (1) may be either empirical or rational, 3; explanation and example of empirical therapeutics, 3; and also of rational, 3, 4, first stage of rational, 4; what should follow this, 4
Thermometer, importance of cleansing and disinfecting, 105
Theveresine, action of, on the cardiac muscle, 316
Thevetin, action of, on the cardiac muscle, 316
Thighs, utility of mustard stupes, poultices, and leeches, to the, as indirect emmenagogues, 453
Thirst, two kinds of, local and general, 360; nature of local, and how it is lessened or quenched, 360; general, and the means of alleviating, 360
Thomas, reference to, 47
Thorium, symbol and atomic weight of, 10
Thoroughwort, 956
Throat, action of pilocarpine on the, 886
Thuja, characters and action of, 1063; in producing abortion, convulsions, and paralysis, 1063; on the vessels and temperature, 1063; uses of, as a diuretic, astringent, aromatic and vermifuge, 1063
Thulium, symbol and atomic weight of, 10
Thymelaceæ, 1022
Thymol, action of, on enzymes, 78; on bacteria, 91, 94, 95; preparation and characters of, 1005; action of, as a disinfectant, and on the nerve-centres of the medulla and cord, 1006; on the respiration, blood-pressure, and temperature, 1006; how eliminated, 1006; uses of, as an antiseptic, 1006
Tiçunas. *See* Curare
Tin, symbol and atomic weight of, 11; causes powerful contraction of the vessels, 281; general action of, 698; nature and uses of granulated, 706; of solution of chloride of, 706
Tinctura Aconiti, 528, 529, 832
Aloes, 528, 529, 899, 1042, 1043
et Myrrhæ, 529, 893, 1043
Arnicæ, 528, 958
Florum, 529, 958
Radicis, 529, 958
Asafœtidæ, 528, 932
Aurantii, 528, 888
Recentis, 528, 888
Amari, 529, 888
Tinctura—
Aurantii, dulcis, 529, 889
Belladonnæ, 528, 530, 985
Benzoini, 530, 964
Composita, 528, 530, 903, 964, 1030, 1043
Bryoniæ, 530, 930
Buchu, 528, 882
Calendulæ, 959
Calumbæ, 528, 530, 841
Camphoræ composita, 528, 844, 935, 964, 1018
Cannabis indicæ, 528, 530, 1026
Cantharidis, 529, 530, 1091
Capsici, 529, 530, 984
Cardamomi, 530, 1038
Composita, 529, 530, 896 936, 1016, 1038, 1091
Cascarillæ, 529, 1022
Castorei, 1077
Catechu, 529, 1016
Composita, 530, 914
Chiratæ, 529, 530, 980
Chloroformi composita, 529, 796, 1038
et Morphinæ, 529, 586, 780, 847, 1004, 1056
Cimicifugæ, 529, 530, 837
Cinchonæ, 529, 530, 940
Composita, 529, 530, 888, 941, 1012, 1039, 1091
Cinnamomi, 529, 530, 1016
Cocci, 529, 1091
Colchici, 530
Seminum, 529, 1050
Seminis, 1050
Conii, 529, 530, 931
Convallariæ, 1040
Croci, 529, 530, 1039
Cubebæ, 529, 530, 1014
Digitalis, 529, 530, 994
Ergotæ, 529, 1069
Erythrophlœi, 915
Ferri Acetatis, 529, 530, 577, 745
Chloridi, 530, 746
Perchloridi, 529, 745
Gallæ, 529, 530, 1031
Gelsemii, 529, 530, 978
Gentianæ composita, 529, 530, 888, 979, 1038
Guaiaci, 530, 880
Ammoniata, 529, 530, 641, 880
Herbarum recentium, 530
Humuli, 530, 1028
Hydrastis, 530, 839
Hyoscyami, 529, 530, 990
Ignatiæ, 530, 971
Iodi, 529, 530, 557, 560
Ipecacuanhæ et Opii, 530, 845, 949
Jaborandi, 529, 883
Jalapæ, 529, 982
Kino, 529, 530, 902, 967
Krameriæ, 529, 530, 868

Tinctura—
Laricis, 529, 1061
Lavandulæ composita, 529, 530, 901, 922, 1003, 1015, 1016
Limonis, 529, 890
Litmus, 1067
Lobeliæ, 529, 530, 961
Ætherea, 529, 781, 961
Lupuli, 529, 1028
Maticæ, 530, 1015
Moschi, 530, 1077
Myrrhæ, 529, 530, 893
Nucis vomicæ, 529, 530, 971
Opii, 529, 530, 844
Ammoniata, 529, 638, 845, 935 964, 1039
Camphorata, 530, 845, 935, 964, 1018
Deodorata, 530, 845
Physostigmatis, 530, 904
Podophylli, 529, 839
Pyrethri, 529, 530, 953
Quassiæ, 529, 530, 892
Quebracho, 969
Quininæ, 529, 943
Ammoniata, 529, 942
Rhei, 529, 530, 938, 1010, 1038, 1039
Aromatica, 530, 922, 1010
Dulcis, 530, 1010
Sabinæ, 529, 1064
Sanguinariæ, 530, 863
Saponis viridis, 530, 966
Scillæ, 529, 530, 1041
Senegæ, 529, 867
Sennæ, 529, 910, 936, 938
Serpentariæ, 529, 530, 1012
Stramonii, 529, 530, 991
Sumbul, 529, 530, 937
Tolutana, 529, 530, 903
Turmeric, 1037
Valerianæ, 529, 530, 952
Ammoniata, 529, 530, 641, 952
Vanillæ, 530, 1036
Veratri viridis, 529, 530, 1045
Zingiberis, 529, 530, 1037
Fortior, 529, 1037
Tinctures, 528–531
Tissue-change, action of drugs on, 410–421 ; of tonics, 410; of hæmatinics or blood tonics, 412 ; of alteratives and their action on the tissues, 413–416; of antipyretics, or febrifuges, 416; list of the chief, their action, 419; and their uses, 420 ; experiments as to the action of drugs on, 414; action of the heavy metals on, 664 ; of silver, 678 ; of salts of iron, 739; of alcohol, 767 ; of quinine, 946
Titanium, symbol and atomic weight of, 11
Tobacco, effect of the inhalation of the smoke of, on a rabbit, 244 ; snuff, action of, on the nose, 246; the vapour of tobacco has a local sedative action on the lung, 249 ; tobacco as a sialagogue, 357 ; as a poison, with its antidote, 491
Tobacco, 992 ; tobacco leaf, character of, 992 ; general action of, 992 ; on the motor and secreting nerves, the intestine, the heart and vaso-motor system, 992 ; in frogs and warm-blooded animals, 992 ; special action of, on the spinal cord, circulation, and vagus, 993 ; on the blood-pressure, heart, and alimentary canal, 993 ; uses of, 993 ; on the effects of tobacco-smoking, 993
Toldt, reference to, 136
Tolu, balsam of, characters and uses of, as an expectorant, 903
Toluyl-di-ethyl-amyl ammonium iodide, action, on motor nerves, 150
Toluyl-tri-ethyl ammonium hydrate and iodide, action on motor nerves, 150
Tonics, as adjuvants to antispasmodics, 214; list of cardiac, 331–335 ; of vascular, 336 ; of gastric, 361 ; nature and action of, 410 ; subdivisions of, 410 ; states in which gastric, digestive, vascular, and nerve tonics are indicated, 411 ; hæmatinics, or blood tonics, 412 ; their mode of action on the blood, 412 ; alteratives and their action, 413–416 ; nature, action, and uses of antipyretics, or febrifuges, 416–421 ; quassia as a tonic, 892; cheken as, 923 ; quinine as a, 947 ; wormwood as, 953 ; oil of chamomile as, 956 ; eupatorium as, 956 ; rhubarb as, 1011 ; sulphate of beberine as, 1021; serpentary root as, 1012 ; cascarilla bark as, 1022 ; elm as, 1026 ; lupulin as, 1028 ; sarsaparilla as, 1052 ; Iceland moss as, 1067
Tonometer, Roy's, 269
Toothache, may frequently be removed by means of a brisk purgative, 203 ; various remedies for alleviating, 353, 815, 817, 860
Tortoise, experiments on the muscular structure of the, 125, 140; difference betwixt the mammalian heart and that of the, 298
Tragacanth, characters, composition, and uses of, 900
Traube, references to, 37, 296
Traube's curves, nature of, 268
Treacle, as a laxative, 1056
Tremor, pathology of, 133 ; treatment of, 134
Trephining, utility of, in investigating the functions of the brain, 187, 197
Trichlorhydrin, as an anæsthetic, 205
Triethylamine, from putrefaction, 100
Trimethylamine, action of, on bacteria, 94 ; formed from putrefaction, 100
Triticum, 1054
Trituratio Elaterini, 531, 929
Triturations, 531

Trochisci, 914
Acidi tannici, 531, 1031
Ammonii chloridi, 531, 537
Benzoici, 964
Bismuthi, 531, 732, 733
Catechu, 531, 914, 951
Cretæ, 531, 650
Cubebæ, 531, 1014
Ferri, 531, 743, 744
Redacti, 531
Glycerrhizæ et opii, 531, 845, 935
Ipecacuanhæ, 531, 949
Krameriæ, 532, 868
Magnesiæ, 532
Menthæ piperitæ, 532, 1004
Morphinæ, 532, 847
et Ipecacuanhæ, 532, 949, 847, 848
Morphinæ et Ipecacuanhæ, 532, 847
Opii, 532, 845, 899
Potassii chloratis, 532, 613
Santonini, 532
Sodii bicarbonatis, 532, 622
Santoninatis, 532, 629, 954
Zingiberis, 532
Trypsin, action of, on fibrine, 75, 76
Tungsten, symbol and atomic weight of, 11; its relation to other members of a group, 16
Türck's method of experimenting on reflex action, 163
Turmeric, 1037; as a condiment, 1037
Paper, 1037
Solution of, 1037
Tincture, 1037
Turpentine, as a stimulating expectorant, 255; action of, on the vaso-motor centre, 319; as a vermicide, 408; as a stimulant diuretic, 433
Turpentine, oil of, action of, on the mucous membranes, 253; importance of, in bronchitis, 253; as a poison, with its antidote, 491
Turpentine, characters of, 1057
Canada, 1057
Oil of, characters and action of, 1058; when inhaled and internally, 1058; on the stomach, respiration, and temperature, 1058; on the nerve-centres and the kidneys, 1059; use of, externally and internally, and as a vermifuge, 1059
Turpentine water, action of, on enzymes, 78
Tweedy, Mr. J., references to, 216, 224

U.

Ulcers, chronic, use of vesicants in, 345; of astringents, 350
Ulmeæ, 1025
Umbelliferæ, 1025
Unguentum, 1084, 1090
Acidi Borici, 532
Carbolici, 532, 763, 764, 813, 1084, 1090
Gallici, 532, 1034, 1084
Salicylici, 532, 763, 764, 820
Tannici, 532, 1031, 1084
Aconitinæ, 532, 832, 1085
Antimonii tartarati, 532, 726, 730
Aquæ rosæ, 532, 920, 916, 1085, 1090
Atropinæ, 532, 1085
Belladonnæ, 532, 985, 1084
Calaminæ, 532, 1085
Cantharidis, 532, 966, 1090, 1091
Chrysarobini, 532, 909, 1084
Cetacei, 532, 916, 964, 1085, 1090
Creasoti, 532, 817
Diachylon, 532, 702, 966
Elemi, 532, 894
Eucalypti, 532, 763, 764, 925
Gallæ, 532, 1031, 1084
cum Opio, 532, 845, 1031
Glycerini plumbi subacetatis, 532, 763, 764
Hydrargyri, 532, 686, 1078
Ammoniati, 532, 687, 695, 1084
Compositum, 532, 686, 966, 1018, 1090
Dilutum, 532
Iodidi rubri, 532, 687, 696
Nitratis, 532, 575, 687, 966, 1084
Nitratis, dilutum, 687, 764
Oxidi flavi, 532, 686, 694, 1084
Rubri, 532, 686, 694, 763, 1084
Subchloridi, 532, 686, 691, 1085
Iodi, 532, 557, 560, 967, 1084
Iodoformi, 532, 804, 1084
Mezerei, 532, 1084, 1090
Paraffinum, 764
Picis Liquidæ, 532, 1062, 1090
Plumbi Acetatis, 533, 703, 1085
Carbonatis, 532, 533, 703, 1084
Iodidi, 533, 557, 705, 1084
Potassæ sulphuratæ, 533, 615, 763, 764
Potassii iodidi, 533, 557, 1084
Resinæ, 533, 916, 1061, 1090
Sabinæ, 533, 1064, 1085, 1090
Simplex, 533, 916, 1090
Staphisagriæ, 533, 836, 1085
Stramonii, 532, 992, 1084
Sulphuris, 532, 533, 544, 1084
Alkalinum, 532, 544, 1084
Iodidi, 533, 557, 763, 764, 1084
Terebinthinæ, 533, 1058, 1061, 1084, 1090

Unguentum—
Veratrinæ, 532, 533, 763, 764, 966, 1084
Zinci, 533, 669
Oleati, 533, 669, 764
Oxidi, 532, 669, 1084
Uranium, symbol and atomic weight of, 11
Urari. *See* Curare
Urea, drugs which act on the excretion of, 414; excreted by the tubules, 424
Urechitine, as a general emetic, 373
Ureter, rhythmical contraction of the, 138
Urethane, composition (Appendix), 1097; action and uses of, 1098
Urethra, drugs employed in inflammation of the, 446; application of drugs to the, 484; diagram of a vulcanite syringe for injecting solutions into the, 484
Uric acid, effects of, on the blood, 72; action of lithontriptics on, 436
Urinary sedatives and astringents, 445; urinary organs, action of cantharides on the, 1092
Urine, circumstances modifying the secretion of, 427–436; the rapidity of the secretion of, depends on two factors, 427; arterial pressure in the glomeruli and the composition of the blood, 427–429; curves showing the effect of erythrophlœum on blood-pressure and secretion of the, 430; action of lithontriptics on the, 436; how evacuation of the, is promoted, 444; action of the bladder on the, 443–445; action of mercury on the, 686; of nitrite of amyl, 786; of belladonna or atropine, 988; of Indian hemp or America cannabis, 1027; of colchicum, 1051; of extract of ergot, 1072
Urticaceæ, ulmeæ (ulmaceæ), 1025
Ustilago, 1073
Uterus, action of ecbolics on, 454; the involuntary muscular fibres of the, controlled by two nerve-centres, 454; nature of the nerves which stimulate the, 454; mode of aiding the expulsive power of the, 454; application of drugs to the, 485; as pessaries, 485; as caustics, 485; utility of tents inserted in, 485; action of borax on the, 625; of pilocarpine, 885; of physostigmine, 907; of quinine, 947; of aloes, 1045; of extract of ergot, 1072
Uva ursa (bearberry), action of, on the bladder, 445; as an astringent, 349; as a stimulant diuretic, 433; characters and uses of, 961, 962; as an astringent and diuretic, 962

V.

Vagina, application of drugs to the, 485; as pessaries, 485; as caustics, 485
Vagus, effects of stimulation of the, 140; contains both expiratory and inspiratory fibres, 241; diagram illustrating this, 242; reference to the, 243; experiments on the, 244; cough chiefly excited by branches of the, 247; heart's beats chiefly regulated by the inhibitory fibres of the, 295; action of drugs on the cardo-inhibitory functions of the, 295; reflex stimulation of the, 296; quickened pulse may be caused by paralysis of the, 297; action of drugs on roots of the, 297; irritation of the, causes still-stand of the heart, 310; action of two classes of poisons on the, 311; position of the accelerating nerves of the, in frogs and warm-blooded animals, 311 and *n.*; vagus-centre in the heart, 317; and ends, 317; nature of the action of the, upon the heart, 324; antagonistic action of certain drugs on the, 493; of delphinine, 836; of cocaine, 879; of pilocarpine, 885; of tobacco, 993; of digitalin on the roots and ends of the, 996
Valerianic acid, action of, on bacteria, 94
Valerian, antispasmodic action of, 213, 214
Valerian, characters, &c., 951
Oil of, 952; action of, on the brain and spinal cord, 952; on the blood-pressure and the pulse, 952; as an antispasmodic, 952
Rhizome, 951
Valerian and oil, as a carminative, 379
Valerianaceæ, 951
Valerianate of sodium, 630; of zinc, 630, 673, 952; of iron, 752; of quinine, 943, 944, 952
Vanadium, symbol and atomic weight of, 11
Vanilla, characters and action of, 1036; as an aromatic stimulant, 1036
Vapor Acidi Hydrocyanici, 533, 586
Chlori, 533, 551
Coninæ, 533, 931
Creasoti, 533, 817
Iodi, 533, 557
Olei Pini Sylvestris, 533, 1060
Vapour baths, 470
Vapours, inhalations, 533
Vascular stimulants, nature and uses of, 330; tonics, 336; and sedatives, 339; when vascular tonics are serviceable, 411; antipyretics, more useful in symptomatic fevers than in specific ones, 420
Vaseline, properties and uses of, 763
Vaso-motor and vaso-dilating nerves, action of drugs on, 283; the vaso-motor centre paralysed by various drugs, 287; action of, on the smaller arteries and capillaries, 291; how the

activity of the vaso-motor centre may be increased, 291; vaso-motor centre of the heart, 319; and nerves, 318; action of the salts of iron on the, 740; of platinum on the, of mammals, 755; of alcohol, 769; of carbolic acid, 814; of aconitine, 835; of opium on the peripheral, 854; of quillaia (saponin), 919; of tobacco, 992; of extract of ergot, 1071
Vegetable alkaloids, poisonous properties of some, destroyed by the liver, 401
Vegetable bitters, strong infusions of, as local emetics, 373
VEGETABLE KINGDOM, Introduction, 830
Veins, nature and functions of, 262; blood in the, useless for nutrition, 262; action of the nervous system on the, 262; of the heart, 263; effect of an upright and of a horizontal position on the circulation of the blood in the, 263, 264; arrest of circulation in the, the cause of fainting and shock, 264, 265; schema of the circulation from the heart to the arterial system and the, 265–267; action of blood-pressure on the, 267; method of ascertaining the blood-pressure on the, 268–270; causes of alterations in blood-pressure in the, 270; how blood-pressure may be raised and lowered in the, 271
Venesection, as an antipyretic, 420
Veratrina, 504, 505, 1045
Veratrine, effects produced by different doses of, on frogs, 26; effects of heat or cold on the action of, 45; action of, on oxidation, 70; on medusæ, 111; on mollusca, 114; on ascidians, 114; on annulosa, 116; power of, for restoring muscle after fatigue, 121; as a muscular poison, 128, 158; as a sedative, 157; action of, on the spinal cord, 163; as an anodyne, 201; on the respiratory centre, 241, 245; action of, on the vagus-roots, 296; on the heart of the frog, 308; on the vaso-motor centre, 319; on the cardiac muscle, 316; as a poison, with its antidote, 491; antagonism of, to opium, 491; physiological action of, in large doses and externally, 1046, 1047; internally, action of, on the brain, spinal cord, and muscles, 1047; on the motor and sensory nerves, the circulation, and the pulse, 1048; on blood-pressure, respiration, and temperature, 1048; uses of, locally and internally, 1049
Veratroidine, 1046; action of, on the vagus-centre and -ends, 1046; on the spinal cord and respiratory centre, 1046; on the vaso-motor centre, blood-pressure, and the pulse, 1046
Veratrum album, action of, on the nose, 245
Veratrum, viride, action of, on the vagus-centre, 317; on the cardiac muscle, 316; on palpitation of the heart, 339; nature and action of, 1045
Verbenaceæ, 1002
Vermicides. *See* Anthelmintics
Vermifuges. *See* Anthelmintics
Vesical sedatives and tonics, action of, on the bladder, 444, 445
Vesicants, 345; strong solution of ammonia as a, 638
Vesication, produced by acids, 568
Vessels, blood, 262; reflex contraction of the, 285; experiments with bromide of potassium on the, 286; action of drugs on this reflex contraction, 286; comparative effect of heart and, on blood-pressure in different animals, 287; influence of nerves on blood-pressure in the, 289–292; action of pilocarpine on, 885; of thuja on, 1063. *See* Arteries and Arterioles
Viburnum (black haw), characters and uses of, 939
Vienna paste, as a caustic to extirpate malignant growths, 346
Vignal, reference to, 402
Vinegar, properties and uses of, &c., 578
Vinegar, aromatic, stimulating action of, on the brain, 194; action of the, on the heart in man, 287; in dogs and rabbits, 287, 288
Vinegars, 503
Vini gallici, mistura spiritus, 1086
Vinum aloes, 534, 1042, 1043, 1037, 1038
Album, 534, 896
Fortius, 534, 896
Antimoniale, 534, 726, 730
Antimonii, 534, 726, 730
Aromaticum, 534, 953, 1002, 1007
Aurantii, 888
Colchici, 534, 1049
Radicis, 534, 1049
Seminis, 534, 1050
Ergotæ, 534, 1069
Ferri, 534, 740
Ferri Amarum, 534, 749
Citratis, 534, 748
Ipecacuanhæ, 543, 949
Opii, 534, 845, 922, 1017
Quininæ, 534, 581, 942
Rhei, 534, 867, 1010
Rubrum, 534, 896
Xericum, 534, 896
Viola tricolor (pansy), characters, composition, and uses of, 866
Violarieæ, 866
Virchow, reference to, 175
Visions, action of drugs in producing, 228
Vitaceæ, 896
Voit, reference to, 414
Volatile oils, 520
Vomiting, relieved by blisters, 345; description of the act of, 370; and of

the nerve-centre which regulates the act of, 370; action of the brain and afferent nerves on, 371; diagram showing the afferent nerves by which the vomiting centre may be excited, 372; the action of drugs in causing, 372–374; the various uses of emetics in causing, 373-376; action of the most powerful sedative in persistent, is ice, 376; gastric sedatives in relieving, 376; list of sedatives useful in vomiting arising from different causes, 377; the action of irritant poisons on the stomach gives rise to, 396; action of pilocarpine on, 885

W.

WARBURG'S tincture, 948
Warm, foot, and hip baths, utility of, as indirect emmenagogues, 453; warm baths, 466
Warm-blooded animals, action of tobacco on, 992; of thuja on, 1063
Warm clothing, importance of, to delicate people, 256
Warmth. *See* Heat
Warmth and moisture, importance of, in rooms occupied by patients having bronchial or chest complaints, 256; as an emollient, 347; poultices made of substances which retain, 348; action of, on the circulation of the blood and the secretion of sweat, 437
Warren, Dr., reference to his use of ether, 212
Washed sulphur, its preparation, &c., 544
Wassilieff, reference to, 106
Water, lukewarm, as a local emetic, 373; in large quantities, as refrigerant diuretics, 432
Water of ammonia, 640
Waters, nature of, uses, and doses, 505
Watts's modification of Mendelejeff's tables, reference to, 592
Wax, white, 1090
  Yellow, 1089; its characters, composition, tests, and uses, 1089
Weber, E. H., reference to, 219
Wedenskii, reference to, 132
Wells, Mr. H., his use of nitrous oxide as an anæsthetic, 211
Wegner, reference to, 710
Wernitz, reference to, 77
Wheaten flour, 1053
White, reference to, 142
  Indian hemp, 970
  Precipitate, 694
  Quebracho bark, 969
  Wax, 1090
Wild marjoram. *See* Origanum
Wilhite, Dr., reference to his use of ether, 211
Williams's apparatus used in researches on digitalin, 303, 304
Willow. *See* Salix
Wine, spirit of French, 776; red wine, 777, 896; white wine, 777, 896; stronger ditto, 777; sherry, 776, 896
Wines, 534
Wines, strong, as cardiac stimulants, 328
Witchhazel. *See* Hamamelis
Witkowski, reference to, 119
Wood, Dog-, 913
  Guaiacum, 880
  Log-, 908
  Quassia, 892
  Red sandal-, 901
  Worm-, 953
Wood, H. C., reference to, 98
Wood charcoal, its preparation and characters, 541; its action, uses, and administration, 541, 542
Wood tar, as a stimulating expectorant, 255
Woorari. *See* Curare
Worms, the three chief kinds which infest the intestines, 408; list of the principal vermicides, 408; and vermifuges, 408; and their adjuncts, 408
Wormseed, American. *See* Chenopodium
Wormwood, nature, action, and use of, 953; as a stomachic tonic and anthelmintic, 953
Wounds, value of astringents in, 350; of styptics, 350
Wourali. *See* Curare
Wundt, references to, 160, 162, 174, 176
Wurrus. *See* Kamala

X.

Xanthine, action of, on muscles, 130
Xanthoxylinæ, 883
Xanthoxylum (prickly ash), as an alterative, 413; characters and use of, 883
Xylol, action of, on bacteria, 94

Y.

YEAST, beer, character and uses of, 1073
Yeasts, origin and nature of, 81
Yellow cinchona bark, 940
  Calisaya bark, 940
  Dock. *See* Rumex
  Jasmine, 977
Yellow wax, 1089
Yolk of egg, 1085
Young, Dr., his table for dosage, 497
Ytterbium, symbol and atomic weight of, 11
Yttrium, symbol and atomic weight of, 11; physiological action of, 27

Z.

ZABLUDOWSKI, reference to, 131

Ziegler's *Pathological Anatomy*, reference to, as translated and edited by MacAlister, 84
Zinc, symbol and atomic weight of, 11; physiological action of, 27; double salts of, action of, on the cardiac muscle, 316; on the capillaries, 318
Zinc, nature, characters, and uses of—
Acetate of, 672
Bromide of, 672
Carbonate of, 670
Precipitated, 671
Chloride of, 671
Iodide of, 673
Oleate of, 670
Oxide of, 669
Of commerce, 669
Phosphide of, 673
Sulphate of, 671
Valerianate of, 673
Zinc chloride, as a caustic, 344
Zinc salts, as antihidrotic, 441; sources of, 667; general reactions and preparation of, 667; impurities, tests, and general action of, 668
Zinc sulphate, as a caustic, 344; as an astringent, 349; as a local emetic, 373
Zinci Acetas, 669
Bromidum, 669
Carbonas, 669
Precipitatus, 669
Chloridum, 669
Iodidum, 557, 669, 673
Oxidum, 669
Phosphidum, 669, 673
Sulphas, 669
Sulphocarbolas, 669
Valerianas, 669, 952
Zincum granulatum, 669
Zingiberaceæ, 1036
Zirconium, symbol and atomic weight of, 11
Zuelzer, references to, 101, 342
Zuntz, reference to, 72
Zygophylleæ, 880
Zymogens, ferment-forming substances, 80

INDEX OF DISEASES AND REMEDIES.

NOTE.—The numbers after the drugs refer to the works quoted as authorities for the treatment :—Neale's *Medical Digest*, 1 ; Ringer's *Therapeutics*, 2 ; Bartholow's *Therapeutics*, 3 ; Wood's *Therapeutics*, 4.

ABSCESS.

ALCOHOL, 4. As a pure stimulant where a large quantity of pus is being poured out, draining the system

BELLADONNA, 2, 3. Internally, and locally as liniment or plaster, to abort the preliminary inflammation—e.g. of breast—afterwards to ease the pain in addition

BORIC ACID, 2. A powerful non-irritating antiseptic dressing

CALCIUM PHOSPHATE. Where abscess is large or chronic, as a tonic

CALCIUM SULPHIDE, 3. Small doses frequently repeated, to hasten maturation or healing, especially in deep-seated suppuration

CARBOLIC ACID, 1, 2, 4. As dressing, and as injection after evacuation

CAUSTIC POTASH, 3. For opening abscess in liver, also in chronic abscess where the skin is much undermined, also used to prevent scarring if otherwise opened

COD-LIVER OIL, 3. In scrofulous cases and in hectic

COUNTER-IRRITATION. To surrounding parts, to check formation or hasten irritation

CREASOTE. Same as carbolic acid

EMPLASTRUM AMMONIACI c. HYDRARGYRO, 2. As a stimulant to indolent inflammatory swellings

ETHER, 3. To produce local anæsthesia, used as a spray for opening an abscess.

ICE, 1. After opening

IODINE, 2. As injection into the sac, and internally to cause absorption of products of inflammation

OAKUM, 1. As a stimulating and antiseptic dressing

OLEATE OF MORPHINE AND MERCURY, 3. Relieves the pain, allays the inflammation, and causes the absorption of the products

PERMANGANATE OF POTASSIUM, 2, 3, 4. As antiseptic

POULTICES, 3. Advantageously medicated, e.g. with belladonna or opium, to allay pain and inflammation

RESORCIN, 2. In syphilitic and other unhealthy sores as an antiseptic

SALICYLIC ACID, 2. As antiseptic dressing

SHEET LEAD. Is useful in the chronic abscess of the leg as a dressing

SILVER NITRATE, 2. A strong solution in nitrous ether, painted around the area of inflammation, will check it in superficial parts

SODIUM AURO-TERCHLORIDE, 1. In scrofulous abscesses as a tonic

SULPHIDES, 3. Of potassium, sodium, ammonium, and calcium. They must be used in low doses, and are indicated in scrofulous abscess and in the chronic boils of children. To hasten suppuration

ACIDITY.

ACIDS, 2, 3. Before meals, or as an acid wine during meals. For acid eructations, especially of sulphuretted hydrogen

ALKALIES, 3. After meals, best as bicarbonates ; with flatulence give magnesia, if there is constipation ; lime water, if there is diarrhœa

AMMONIA, 4. In headache from acidity

BISMUTH, 2, 3. In gastritis due to chronic abscess or chronic alcoholism. Very well combined with arsenic in very chronic cases, with hydrocyanic acid in more acute cases

CARBOLIC ACID, 2. To stop fermentation, or to relieve an irritable condition of the stomach

CHARCOAL. As biscuits

CREASOTE. Same as carbolic acid

IPECACUANHA, 3. In minim doses in pregnancy where flatulence and acidity are both present

KINO, 2. Useful along with opium

LEAD ACETATE, 2. In gastric catarrh and pyrosis

MANGANESE OXIDE, 2. Sometimes relieves, probably acting like charcoal

MERCURY, 3. When liver deranged and stools pale

NUX VOMICA. In small doses before meals, especially in pregnancy, or in chronic alcoholism

PULSATILLA. ℥v. every four hours in water

SILVER NITRATE, 2. Same as silver oxide

SILVER OXIDE, 2. Especially useful when acidity is accompanied by neuralgic pains in stomach

SULPHUROUS ACID, 2. If associated with the vomiting of a pasty material, presence of sarcinæ

TANNIC ACID, 2. In acidity associated with chronic catarrh and flatulence. Glycerine ℥j, tannic acid gr. iv, as pill

ACNE.

ALKALINE LOTIONS, 2. When skin is greasy and follicles are black and prominent

ARSENIC. In chronic acne ; generally, though not always, prevents the acne from bromide or iodide of potassium

BELLADONNA, 3. As local application to check a too abundant secretion

BISMUTH, 2. As ointment or powder. In acne rosacea if acute

BORAX. Solution very useful

CAJEPUT OIL, 4. As stimulant in acne rosacea

CALCIUM SULPHIDE, 3. Same as sulphur. For internal use

COD-LIVER OIL

GLYCERINE. Both locally and internally

IODIDE OF SULPHUR, 3. In all stages of the disease

Acne.

Iodine, 4. Is of doubtful value
Liquor Hydrargyri Perchloridi, 2. In very early stages as a wash
Liquor Hydrargyri Pernitratis, 4. A single drop on an indurated pustule will destroy without scar
Phosphorus, 2. In chronic cases in place of arsenic. The phosphates and hypophosphites are safer and more valuable. The latter in acne indurata
Potassium Bromide, 3. Sometimes useful in moderate doses in obstinate cases. This salt and the iodide very often cause acne when taken continuously
Sand, 1. Friction with, useful
Sulphur. Internally, and externally as a lotion or ointment, the most valuable agent
Water. Hot sponging several times a-day

Addison's Disease.

Glycerine, 1. In full doses
Iron. Anti-emetics and tonics
Skimmed Milk, 1. As diet

After-pains.

Actæa Racemosa, 3. It restores the lochia in cases of sudden suppression and removes the symptoms
Belladonna. As ointment
Camphor, 2. Useful when combined with morphine, 10 gr. with ½ gr. of morphine
Chloral, 2. In large doses arrests the pains; contra-indicated in feeble action of the heart
Chloroform. Liniment to abdomen along with soap liniment
Cimicifuga, 2. Same as ergot
Ergot. To keep the uterus constantly contracted and prevent accumulation of clots in its cavity, and consequently the pains which they would occasion
Gelsemium, 2. Stops pains in doses sufficient to produce its physiological effect
Morphine and Atropine. Hypodermically very useful, ⅛–¼ gr. morphine with $\frac{1}{100}$ gr. of atropine
Opium. The same as morphine
Poultices. Warm, to the hypogastrium relieve
Quinine. 5–10 gr. night and morning, with neuralgic after-pains which do not yield to opiates

Albuminuria.

Aconite, 1, 2. To lower a high temperature; and in the onset of acute nephritis in scarlet fever
Alcohol, 1. Hurtful in acute stage; useful when a slight trace of albumen is persistent
Alkaline Diuretics, 1. To prevent formation of fibrinous plugs in the renal tubules
Aqua Calcis, 1. In large doses has been found to increase the urine, and decrease the albumen
Arsenic, 1, 2. Beneficial in very chronic cases. Albumen will return if the use of the drug be stopped
Baths, 1, 3. Warm water and hot air and Turkish, to increase action of skin after dropsy or uræmic symptoms have appeared
Belladonna, 1. Has been used to diminish the chronic inflammatory condition left by an acute attack
Broom. As diuretic in chronic renal disease
Caffeine, 4. To increase secretion of solids, especially in cases dependent on cardiac disease. Should be combined with digitalis.

Albuminuria.

Very useful in chronic Bright's disease; should be used with great caution in the acute stage
Cannabis Indica. As diuretic in hæmaturia
Cantharis, 1, 3. ♏j. of tincture every 3 hours, when acute stage has passed off, to stop hæmaturia
Chimaphila. As a diuretic
Cod-Liver Oil. As a tonic
Copaiba, 3. To remove ascites and albuminuria dependent on cardiac or chronic Bright's disease, and in some cases of hæmaturia
Counter-irritation. Dry cupping most useful when tendency to uræmia
Croton Oil, 1. As liniment to the loins in chronic cases is sometimes useful
Digitalis, 2, 3. The infusion is the most valuable in acute tubal nephritis, and in renal disease attended with dropsy due to cardiac disease. Must be given with caution in granular kidney
Elaterium, 1, 3. As hydragogue cathartic for dropsy; and when uræmic symptoms have come on
Eucalyptus, 2. Cautiously for a short time in chronic disease
Fuchsin, 1. In gr. j. to gr. iij. doses in the day, in albuminuria of children of renal origin
Gallic Acid, 2, 4. Lessens albumen and hæmaturia
Gold, Chloride of, 2, in contracted kidney, in the chronic disease in doses of $\frac{1}{10}$ gr.
Hydrastis. Lessens albumen
Incisions, 3. Over the malleoli, to relieve the anasarca of the lower extremities
Iron, 1, 2, 3. To diminish anæmia with a flabby tongue, give the persalts. In dropsy, associated with high tension, iron must be cautiously given, and withheld unless improvement is quickly shown. It always does harm if allowed to constipate
Jaborandi. In uræmia and dropsy due either to renal disease or occurring in pregnancy
Juniper, Oil of. Diuretic
Lead, 3. Lessens albumen and increases the urine
Milk Cure. Pure skim-milk diet sometimes very useful when tendency to uræmia; it also lessens the albumen
Nitroglycerin, 1, 2. In acute and chronic albuminuria
Nitrous Ether, 2. As diuretic
Oxygen. Condensed, will, on inhalation, temporarily diminish albumen
Potassium Salts. Especially the iodide and vegetable salts in syphilitic or amyloid disease
Potassium Bitartrate, 1, 3, 4. As hydragogue cathartic and diuretic
Potassium Bromide. In uræmic convulsions
Tartrates. As diuretics
Turpentine. As diuretic, ♏ ss.–j. dose every 2 to 4 hours
Water. In large draughts as diuretic when excretion of solids is deficient; and in dropsy.

Alcoholism.

Actæa Racemosa, 2, 3. In irritative dyspepsia
Ammonia. Aromatic spirits of, as substitute for alcohol, to be taken when the craving comes on.
Arsenic, 3. To lessen vomiting in drunkards, in the morning before food is taken; and also in the irritable stomach of drunkards
Bismuth, 2, 3. With hydrocyanic acid, to relieve acidity and heartburn
Bromides, 2, 3. Useful during delirium tremens, or to lessen irritability, in ʒj. doses, in the wakeful condition which immediately precedes it

Alcoholism.

Capsicum, 2, 3. As substitute for alcohol, and also to relieve the restlessness and insomnia
Chloral, 2. To quiet nervous system and induce sleep in an acute attack. Must be used with caution in old drunkards
Cocaine, 3. To remove the craving
Faradization, 1
Gelsemium, 2. Same as bromides
Lupuline, 2. Along with capsicum as substitute for alcohol, also to quiet nervous system in delirium tremens
Milk, 1. At night
Nux Vomica. As tonic and stimulant, both to nervous system and generally to aid digestion
Opium, 2, 3. May be necessary to produce sleep; to relieve the pain of the chronic gastritis and the want of appetite
Orange. Slowly sucked, a substitute for alcohol
Phosphorus, 3. In chronic cases as nervine tonic
Picrotoxine, 2. For tremors
Quinine. In the 'horrors' stage it acts as a sedative to the brain and restores the digestive functions
Sumbul. In the headache of old drinkers
Water, Cold. A glass taken in small sips at a time, as substitute for alcohol
Water, Hot. 1 pt. drunk as hot as possible an hour before meals will remove craving
Zinc Oxide. In chronic alcoholic dyspepsia, and nervous debility. It also allays the craving.

Alopecia.

Ammonia. Very useful—℞ Ol. amygd. dul., Liq. ammoniæ āā f. ʒj. Spt. rosmarini, Aquæ, Mellis āā f. ʒiij. mm. fl. lotio (E. Wilson).
Antimonium Tartaratum, 1. As lotion, gr. j., aquæ ʒj.
Arsenic. Internally
Cantharides Tincture, 1. One part to eight of castor oil rubbed in roots of hair morning and night
Carbolic Acid, 1. In Alopecia areata
Glycerine, 883. Very useful; either alone or in combination appears greatly to assist
Nitric Acid. With olive oil, in sufficient quantity just to make it pungent
Pilocarpine, 1, 4. Subcutaneous injection has been useful
Sabinæ Oleum, 1. Prevents loss of hair in Alopecia pityrodes
Sapo Viridis, 1. Very useful as a shampoo night and morning—℞ Saponis virid. (German), Alcoholis āā ij., Ol. lavandulæ, guttæ xxx.
Shaving. Sometimes useful after illness
Sodium Bicarbonate, 1. As a lotion in Alopecia pityrodes
Sulphur Iodide. Useful both internally and externally
Tannin, 1. Watery solution or made up into ointment

Amaurosis and Amblyopia.

Amyl Nitrite, 1. Useful in many cases of disease of the optic nerve
Arnica. Sometimes useful
Electricity, 1.
Myotomy, 1. In asthenopia and hysterical amblyopia
Pilocarpine, 2. In tobacco and alcoholic abuse
Rue. In minute doses in functional dimness of vision, *e.g.* hysterical amblyopia
Santonin, 4. Sometimes useful in later stages of iritis and choroiditis, and in loss of power of optic nerve

Amaurosis and Amblyopia.

Seton. In temple, or blisters, along with iodide of potassium, in amaurosis coming on suddenly, and associated with tenderness of the eyeball on pressure; the disc is sometimes congested
Strychnine, 1, 2, 3, 4. Very useful in cases of tobacco amaurosis, alcoholic excess, nerve-atrophy (without cranial disease), and in traumatic amaurosis
Veratrine. To eyelids and temples. Care must be taken to keep out of the eye

Amenorrhœa.

Aconite, 3. When menses are suddenly checked, as by cold, &c.
Actæa Racemosa, 2, 3. To restore the secretion, and remove the headache, ovarian neuralgia, &c. produced by its sudden stoppage
Alcohol, 4. In sudden suppression after exposure
Aloes, 2, 3. Alone or with iron. In torpor and anæmia; best administered a few days before the expected period
Ammonium Chloride, 3. In headache
Apiol (oil of parsley), 2, 4. Gr. iij. twice a day for some days before the expected period; if there is a molimen gr. xv. in a few hours. Useful in anæmia and torpor only
Arsenic, 2, 4. Along with iron in anæmia and functional inactivity of the ovaries and uterus
Asafœtida, 2. Along with aloes in anæmia and torpor of the intestines
Cantharides, 2, 4. Along with iron in torpor of the uterus
Cold Sponging, 3. To brace the patient up
Colocynth. In anæmia with constipation
Electricity, 2. Locally applied, sometimes useful
Ergot, 2. In plethoric subjects
Gold Salts, 2. Like Asafœtida
Guaiacum, 4. Mild stimulant to the uterus
Hydropiper, 2. In torpor; with iron in anæmia, aloes in a constipated subject. Contra-indicated in a plethoric condition. Should be given a few days before menses are expected
Iron, 2, 3, 4. In anæmia, *q. v.*
Manganese, 3. Useful in the amenorrhœa of young women; in delayed menstruation, or when a period has been missed through a chill. Perseverance is required, especially in the last case
Myrrh. A tonic emmenagogue
Nux Vomica, 2. In combination with iron in anæmia
Potassium Permanganate. Like Manganese
Pulsatilla, 2. Like Aconite
Rue, 2, 4. In atonic condition of ovaries or of uterus. Plethora contra-indicates
Saffron Wine, 1. Emmenagogue
Salines, 4. In constipation in plethoric cases
Sanguinaria. Like Rue
Santonin, 3. In two doses of 10 gr. one or two days before the expected period
Savin. Like Rue
Senega, 4. A saturated decoction in large doses of a pint daily about two weeks before period
Serpentaria. In anæmia
Silver Nitrate. Locally, to os uteri at period
Sitz Baths. Hot, alone, or with mustard, for some days before the period; with mustard, if suddenly arrested
Spinal Ice-bag. To lumbar vertebræ

Anæmia.

Acids. For a tonic action on the mucous membranes in the anæmia of young women

Anæmia.

Acidum Gallicum, 1. In anæmia due to a chronic mucous or other discharge
Alkalies, 1. Potash and Soda as gastric and hepatic tonics
Aloes, 1. As tonic and slight purgative
Arsenic, 1, 2. In the cases where iron fails of its effect or does not agree with the patient. Also in Pernicious Anæmia
Cold Sponging.
Galvanisation.
Hypophosphites of Calcium or Sodium. In cases of nervous debility care must be taken that they do not derange the digestion
Iron, 1, 2, 3, 4. Very useful. When stomach is at all irritable the carbonate is often best. Weak anæmic girls with vomiting after food are best treated with the Perchloride. In coated tongue the ammonio-citrate is often the best to begin with. The malate has been useful in pernicious anæmia. In gastric disturbance and constipation a combination with Rhubarb is often very effectual. Where mucous membrane very flabby large doses of the perchloride. Chalybeate waters more often succeed than pharmaceutical preparations; one drop of the solution of perchloride in a tumbler of water is a good substitute for them
Lactophosphate of Calcium. During nursing, or after exhausting purulent discharge
Manganese. May be given along with iron—not much use alone
Nux Vomica. Useful sometimes along with iron
Oxygen, 2, 3. In anæmia from loss of blood or suppuration
Pancreatin. In feeble digestion
Pepsin. In feeble digestion
Phosphate of Calcium. During growth, or where system is enfeebled by drain of any kind
Quinine. In malnutrition
Sea-Bathing, 1. Good, but not in chlorosis
Wines. Along with food to aid digestion

Aneurism.

Aconite, 1, 2. To relieve pain and slow the circulation
Aliment. Low diet; absolute rest
Barium Chloride, 1, 2. In doses of $\frac{1}{6}$ gr. Perhaps raises the arterial tension. It has been successfully used
Chloroform. Inhaled to relieve dyspnœa
Electrolysis. Sometimes useful in causing coagulation within the sac
Ergotin, 1. A local hypodermic injection has been successful
Eucalyptus, 1.
Ferri Perchloridi Liquor. 1. To cause coagulation on injection into sac
Lead Acetate. Useful, combined with rest
Potassium Iodide. Very useful in doses of gr. xxx. Should be combined with the recumbent position
Veratrum Viride. Along with opium in quieting circulation

Angina Pectoris.

Aconite.
Arsenic, 1. To prevent paroxysms
Chamomile. In hysterical symptoms
Chloral. In full doses
Chloroform, 1. Cautiously inhaled to ease the pain
Cold, 1. Applied to forehead gives relief
Ether. To diminish pain, combined with opium in $\frac{1}{4}$ gr. doses
Morphine. Hypodermically

Angina Pectoris.

Nitrite of Amyl. Gives great relief during paroxysms; in atheromatous arteries must be used with care
Nitrites of Sodium and Potassium. Less rapid than nitrite of amyl, but have more power to prevent return of symptoms
Nitroglycerin. Like nitrite of sodium
Phosphorus. During intervals to lessen tendency
Potassium Bromide. In full doses will relieve the spasm
Quinine. When any malarious taint is present
Strychnine. Sometimes useful in mild cases, in very small doses
Turpentine. Locally to the chest during paroxysms

Anus, Fissure of.

Belladonna. Locally relieves spasms
Benzoic Acid. As a local application
Bismuth, 1. With glycerine, as a local application
Calomel. As ointment
Carron Oil, 1. As a dressing
Castor Oil. To keep motions soft
Chloral. Useful in dilute solution (2 per cent.) as a dressing
Chloroform, 1. Diluted with half its bulk of alcohol, will aid healing
Cocaine. In ointment
Collodion. Locally, to protect
Dilatation, Forcible. Relieves spasm
Hydrastis. Local application
Ice, 3. To relieve pain after operation
Iodoform. Locally, to heal and relieve pain
Iodo-tannin (solution of iodine in tannin). Useful locally
Opium and Gall Ointment. Relieves pain
Potassium Bromide. With five parts of glycerine locally
Rhatany, 1. Injected after the bowels have been opened by enema
Sulphur. To keep motions soft
Tannin. Useful as a local application

Aphonia.

Aconite, 1. In the painful contraction of the throat of singers
Alum. As spray in chronic congestion of throat and larynx, with hoarseness
Ammonium Chloride. As vapour in laryngeal catarrh
Argenti Nitras, 1. As local astringent
Atropine. In hysterical aphonia; must be pushed to produce physiological symptoms
Benzoin, Tincture of. Inhaled in laryngeal catarrh
Borax. A piece the size of a pea slowly sucked in sudden hoarseness
Chloroform, 1. In hysterical and nervous cases
Electricity. Locally applied
Ether. Like chloroform
Glycerine of Tannin. Locally, to pharynx
Ignatia. Like atropine
Ipecacuanha. Wine as spray in laryngeal catarrh
Nitric Acid. In hoarseness from fatigue or indigestion
Nux Vomica, 1. Locally applied in impaired nervous power
Potassium Nitrate. Like Borax
Rue, Oil of. As inhalation in chronic catarrh
Sulphurous Acid. As spray or inhalation, in clergyman's sore-throat
Turkish Bath. In acute laryngeal catarrh
Uranium, Nitrate of. As spray in very chronic catarrh
Zinc Sulphate, 1. Local astringent

APHTHÆ.

ALUMEN EXSICCATUM, 3. To aphthous ulcers which do not readily heal
ARGENTI NITRAS, 1. Local application
BISMUTH. As local application
BORAX. As honey or as glycerine, either alone or with chlorate of potassium
CHLORINE WATER. Locally applied
COPPER SULPHATE. Weak solution painted over the aphthæ
COPTIS TRIFOLIA. Infusion is employed in New England
GLYCERINE.
HYDROCHLORIC ACID, 2. In small doses and as a local application
MERCURY. In the form of hydrarg. cum cretâ in children, to remove the indigestion on which aphthæ frequently depends
MINERAL ACIDS. Dilute solution as paint
NITRIC ACID. In small doses
POTASSIUM CHLORATE. Exceedingly useful as wash, 10 grs. to the oz., alone or with borax, also given internally
POTASSIUM IODIDE. As local application, solution of 1–5 grs. to the oz.
QUININE. 1 gr. every two or three hours, in aphthæ in infants consequent on diarrhœa
RHUBARB. To remove indigestion, as compound rhubarb powder
SALICYLIC ACID. As local application
SULPHUROUS ACID. As solution or spray, well diluted

APOPLEXY.

ACONITE. To lower blood-pressure and prevent further hæmorrhage, where pulse is strong and arterial tension high
ARSENIC, 1. In cerebral congestion preceding apoplexy
COLD WATER. To the head when face congested
COLOCYNTH. As purgative
CROTON OIL. As purgative, one drop on back of tongue, or part of a drop every hour
DIET AND HYGIENE, PROPHYLACTIC. Butcher's meat and stimulants to be taken very sparingly, exposure to heat, over-exertion, and especially anger, to be avoided
ELATERIUM. In suppository, or as enema, during attack
ELECTRICITY. To promote absorption, after partial recovery has taken place
ICE. To head
NITROGLYCERIN. To lessen cerebral congestion
POTASSIUM BROMIDE. In combination with aconite
POTASSIUM IODIDE. To cause absorption of effused blood
STIMULANTS. Cautiously exhibited when collapse is present
VENESECTION OR LEECHES, 1. To relieve arterial pressure when apoplexy is threatening

APPETITE, IMPAIRED.

CANNABIS INDICA, 1. Produces an enormous appetite
FOOD. Savoury, well-cooked
GLYCERINE.
IGNATIA. Corrects diseased appetite and hysteria
LOW DIET.
NITRIC ACID. In low doses with a bitter
PEPTONES.
STRYCHNINE. Especially in Phthisis

ASCARIS LUMBRICOIDES (Round-worm).

CAMPHOR.
CARBOLIC ACID. As an enema; unsafe
MUCUNA, 2. As an electuary
QUASSIA. As an enema
SANTONIN.
SPIGELIA. Like Santonin; to be preceded by a purgative
TURPENTINE.
VALERIAN. In convulsions

ASCITES.

ACIDUM NITRICUM, 1. In cirrhosis of the liver
ACONITE. In scarlatinal nephritis at the onset of the attack
APOCYNUM CANNABINUM. As diuretic
ARSENIC. In old persons with feeble heart
ASCLEPIAS. In dropsy of cardiac origin
CAFFEINE, 1. In cardiac dropsy
CALOMEL. As diuretic in cardiac dropsy
CANNABIS INDICA, 1, 3. As diuretic in acute and chronic Bright's disease with hæmaturia
COPAIBA. Especially useful in hepatic and cardiac dropsy
CROTON OIL. In dropsy, in ½ of a drop doses every morning
CYTISUS SCOPARIUS, 2. In cardiac dropsy and dropsy with chronic Bright's disease
DIGITALIS. Best in cardiac dropsy; its action is increased by combination with squill and blue pill
ELATERIUM. As hydragogue cathartic
GAMBOGE. Like Elaterium. Large doses tolerated
JABORANDI. In anasarca and uræmia
JALAP. In compound powder as hydragogue cathartic
MILK DIET. Sometimes very useful when kidneys are inadequate
PODOPHYLLIN, 1. In hepatic cirrhosis
POTASSII TARTRAS ACIDA. In combination with Jalap in hepatic cirrhosis
SQUILLS, 1. As diuretic in cardiac dropsy.
STILLINGIA. In hepatic dropsy

ASTHENOPIA.

ATROPINE. To prevent spasms
HYDROCYANIC ACID, 1. In irritable ophthalmia
HYSTERIA, 1. A cause
MASTURBATION, 1. Often a cause
MYOTOMY, INTRAOCULAR, 1. To relieve spasm
PHYSOSTIGMA, 1. In the paralysis produced by diphtheria, and in senile asthenopia

ASTHMA.

ACONITE. In spasmodic cases, also in asthma consequent on nasal catarrh in children
ALCOHOL, 1. In combination with amyl nitrite in spasmodic asthma
ALKALIES, 1. In chronic bronchial catarrh
ALUM, 3. 10 grs. of dry powdered alum put on the tongue will arrest a spasm
AMMONIA VAPOUR, 1.
AMMONIACUM. Like Asafœtida
AMYL NITRITE. Sometimes checks paroxysm in spasmodic asthma and dyspnœa due to cardiac hypertrophy. Must not be given in chronic bronchitis and emphysema
ANÆSTHETICS, 4. As a temporary remedy in severe cases
ANTIMONY, 3. In asthmatic conditions in children, $\frac{1}{60}$ gr. of tartar emetic every quarter of an hour
APOMORPHINE, 1. Emetic, where it is due to a peripheral blocking of the air-tubes
ARSENIC, 3. In small doses in cases associated

Asthma.

with bronchitis or simulating hay fever, or in the bronchitis of children, or in dyspeptic asthma. Inhaled as cigarettes with caution
Asafœtida. As an expectorant where there is profuse discharge
Belladonna. Internally in large doses to relieve paroxysm. It should only be administered during a paroxysm and then pushed
Bromides. Only available in true spasmodic asthma; soon lose their efficacy
Caffeine Citrate, 1. In low dose, 1–5 grs., which varies with the case
Camphor, 1. Gr. ij. combined with gr. j. of opium in spasmodic asthma
Cannabis Indica. Sometimes useful in chronic cases
Chamois-Leather Waistcoat, 3. Reaching low down the body and arms; in bronchial asthma
Chloral. During paroxysm
Chloroform. Relieves when inhaled from tumbler or with warm water
Coffee. Very strong during paroxysm
Colchicum. In gouty cases
Conium, 1. Palliative in a chronic case
Counter-irritation, 1. Applied for a short time only at frequent intervals
Creasote. Vapour in bronchitic asthma
Datura. *See* Stramonium.
Ether. In full doses at commencement of attack, or administered by inhalation
Ethyl Iodide, 1. 15 to 20 drops inhaled will relieve spasm
Eucalyptus. Sometimes along with stramonium, belladonna, and tobacco
Galvanism of Pneumogastric Region. Positive pole beneath mastoid process, negative pole to epigastrium
Gelsemium, 2. Useful in some cases, but after a time may fail
Grindelia. To prevent or cut short attack; used as cigarette
Hyoscine, 2. In spasmodic asthma
Iodine, 1. Painting the line of the pneumogastric nerves with liniment or tincture in pure spasmodic asthma
Ipecacuanha. As a spray in bronchial asthma, especially in children; useless in true asthma
Lobelia. To prevent and cut short paroxysm. Cautiously used in cardiac weakness
Mercury, 1. In spasmodic and bronchitic asthma combined
Morphine. Combined with Belladonna very useful
Nitroglycerin, 1, 2, 3. In bronchitic, nephritic, and spasmodic asthma
Nux Vomica. In dyspeptic asthma
Opium. Hypodermically, during paroxysm
Oxygen. As inhalation during paroxysm
Pepsin. Exceedingly useful in preventing attacks in dyspeptic subjects
Pilocarpine, 2. In spasmodic asthma, subcutaneously; also in humid asthma if there is no cardiac dilatation
Potassium Bromide.
Potassium Iodide. In large doses, when asthma due to acute bronchial catarrh
Potassium Nitrate. Inhalation of fumes of touch-paper relieves paroxysm. Sometimes advisable to mix a little chlorate with it
Pyridine. In bronchial asthma vapour to be inhaled
Quebracho, 2. Good in nephritic and spasmodic asthma
Quinine. During intervals when attacks are periodical
Resorcin, 1. Relieves dyspnœa
Silver Nitrate. Has been injected into trachea
Sodium Arseniate, 1. Tonic, acts probably on respiratory centre

Asthma.

Sodium Nitrite. Like Nitroglycerin
Sodium Phosphate, 1. Sometimes efficacious
Stramonium. Sometimes very useful. May be made into cigarettes, or 20 grs. of dried leaves may be mixed with nitrate of potassium, and the fumes inhaled. A little powdered ipecacuanha may often be added
Strychnine, 2. In weakness of the respiratory centre
Sulphur Fumes, 1. In bronchitic asthma
Tobacco. Smoking is sometimes beneficial
Turkish Baths. In bronchial asthma

Astigmatism.

Suitable Glasses.

Atheroma.

Ammonium Iodide. To promote absorption
Arsenic, 2. Often useful, especially where there are cerebral symptoms
Cod-Liver Oil, 2.
Digitalis, 4. Requires caution; useful in general capillary atheroma
Phosphorus. In minute doses, along with cod-liver oil, in cases with cerebral symptoms
Quinine. Like Arsenic

Atrophy.

Arsenic. In muscular atrophy
Electricity.
Massage.
Olive Oil. Inunction to atrophied parts
Strychnine.

Balanitis.

Astringent Lotions. Alum; sulphate of zinc
Lime Water. As lotion
Mercury. Yellow wash, as lotion
Oil.

Bed-sores.

Alcohol. As wash to prevent; afterwards dust with powdered starch
Alum. With white of egg, as local application
Balsam of Peru and Unguentum Resinæ, 1. Equal parts spread on cotton wool
Charcoal. As poultices, to stop bed-sores
Galvanic Couplet. Of zinc and silver; one element on sore, the other on adjacent part
Glycerine. Prophylactic local application
Hydrargyri Perchloridum, 1. A solution mixed with diluted spirits of wine
Iodoform.
Medicated Poultices, 1. Patient to lie with poultices under the parts likely to be affected; if fœtor, cataplasma carbonis; if sloughing, addition of Balsam of Peru
Quinine, 1. Local dressing.
Silver Nitrate. Dusted over open bed-sores
Styptic Colloid.
Tannate of Lead, 1. At an early stage

Biliousness.

Aconite. As adjunct to podophyllum
Alkalies. In indigestion due to obstruction to the flow of bile
Alkaline Mineral Waters, 2. In catarrh of the bile-duct, early stage of cirrhosis, and obstruction to the hepatic circulation
Aloes. In constipation, and in deficient secretion of bile
Ammonium Chloride, 2. In jaundice due to

Biliousness.

catarrh of the bile-ducts; early stage of cirrhosis; deficient intestinal secretion
Ammonium Iodide, 2. In catarrh of duodenum and biliary ducts, in the early stage of cirrhosis, in the malarial cachexia; efficacy increased by the addition of arsenic
Angostura. In bilious fevers
Argenti Oxidum.
Bryonia. In bilious headache
Calomel. 1. In excessive production with deficient secretion; Calomel or Blue Pill at night and in the morning a Black Draught
Calumba. As stomachic tonic
Carlsbad Water. A tumbler sipped warm during dressing very useful
Euonymin, 1. At night, followed in the morning by a saline purge
Friedrichshall Waters, 3. A wineglassful in a tumbler of hot water slowly sipped while dressing in the morning
Horse Exercise.
Hydrastis, 2. When chronic gastric catarrh is present, in chronic catarrh of the duodenum and bile-ducts, with inspissation of the bile and gall-stones
Manganese. In malarial jaundice
Mercurial Cathartics. In moderate doses night and morning, or in small doses more frequently repeated. Especially useful, when stools are pale, is the bichloride
Milk Cure. In obstinate cases
Mineral Acids. Nitrohydrochloric acid especially useful in chronic hepatic affections, dysentery and dropsy of hepatic origin
Podophyllum. In place of mercury when stools dark
Rhubarb. As hepatic stimulant
Sodium Phosphate, 2. In bilious sick headache; also in the catarrh of the gall-duct in children, dose, 10 gr.
Stillingia, 2. In cirrhosis; torpidity and jaundice following intermittent fever; ascites due to hepatic changes; in deficient secretion to be combined with Nux Vomica

Bladder, Irritable.

Alkalies, 2. Vegetable salts, especially of potassium when the urine is acid
Aquapuncture, 2.
Belladonna. In the irritable bladder of children more especially causing nocturnal incontinence of urine
Benzoate of Ammonium. Like Benzoic Acid
Benzoic Acid. In large prostate, and alkaline conditions of urine
Buchu, 4. In combination with the vegetable salts of potassium in a very acid condition of the urine
Cantharides. In women without acute inflammation or uterine displacement; also in the irritable bladder produced by chronic enlargement of the prostate
Copaiba. In chronic irritability
Cubebs. Like Copaiba
Hops, 4. Useful in a few cases in large doses
Indian Corn Silk (Zea Mays), 4. A mild stimulant diuretic; infusion *ad lib.*
Pareira. In chronic irritable bladder

Bladder, Paralysis of.

Cannabis Indica. In retention, from spinal disease
Cantharides. In atonic bladder, painting around the umbilicus with the Acetum
Ergot. In paralysis, either of bladder or sphincter, when bladder so that urine is retained, and incontinence in sphincter
Galvanism. In lumbar region

Bladder, Paralysis of.

Nicotine, 1. 3j. of a 4 per cent. solution of nicotine injected by catheter and then withdrawn in a few minutes
Strychnine.

Blepharitis.

Alkaline Lotions. Warm, to remove the secretion
Cupri Sulphas. Dropping in a very dilute solution
Iron. To remove the anæmia usually present
Mercury (Unguentum Hydrargyri Nitratis). Most useful application. If too strong, dilute with vaseline or simple ointment
Pulsatilla. Internally and locally
Silver Nitrate. Pencilling the border of the lid with the solid

Boils.

Acid Nitrate of Mercury, 1. To abort at an early stage
Arnica, 1. Locally as an ointment, and also internally
Arsenic. To lessen tendency to recurrence
Belladonna. Internally, or as local application
Boric Acid, 1. As a dressing
Calcium Sulphide, 2, 3. Occurring in strumous subjects or otherwise; to hasten maturation or abort
Camphorated Alcohol. As local application in early stage
Carbolic Acid. Injection
Caustic, 1.
Cocaine, 1. To allay the pain
Collodion. Painted over whole surface to abort in papular stage; and over base, leaving centre free, in pustular stage
Counter-irritation. By plasters surrounding the boil
Opium. Locally to remove pain
Phosphates, 2. 4. Especially of sodium as a constitutional agent
Potassium Chlorate, 1. As an alterative
Poultices. To relieve pain and hasten maturation
Silver Nitrate. Strong solution painted over the skin round boil
Strapping. Properly applied gives great relief
Subcutaneous Incisions, 1.
Sulphides. In small doses to abort or hasten maturation
Sulphites, 1.
Sulphur Waters, 2.
Unguentum Hydrargyri, 1. Early applied around will prevent sloughing
Yeast, 1. ʒss. ter die for an adult very useful

Bone, Diseases of.

Calcium Salts, 2, 4. The phosphate in rickets, in delay of union of fractures; the chloride in strumous subjects
Cod-Liver Oil. In scrofulous conditions
Iodine. Alone, or with cod-liver oil
Iodoform. As a dressing to exposed bone

Breath, Fetid.

Benzoic Acid. In spray
Camphor.
Carbolic Acid. Dilute solution as wash to mouth
Chlorine. Liq. chlori and chloride of lime as lotion
Permanganate of Potassium. As wash to mouth

Bright's Disease.

Vide Albuminuria.

Bronchiectasis.

Chlorine. As inhalation to lessen fœtor
Creasote. As inhalation
Iodine. As inhalation
Phosphates and Hypophosphites
Quinine
Terebene. As inhalation

Bronchitis, Acute.

Aconite, 2. ½–1 min. every hour at commencement of an acute catarrhal attack
Actæa Racemosa, 2. In acute catarrh and bronchitis when the more active symptoms have subsided
Alkalies, 4. To render mucus less viscid
Amber Oil, 4. Counter-irritant over spine in children
Ammoniacum. Very useful in old people
Ammonium Carbonate, 2. Where much expectoration and much depression; or where the mucus is very viscid and adherent
Apomorphine, 4. Causes a copious expectoration in the early stage
Asafœtida. Like Ammoniacum
Belladonna, 1. In acute bronchitis of children, to stimulate respiratory centre
Benzoin and Benzoic Acid, 3. 3j. inhaled from hot water eases cough and lessens expectoration
Bleeding, 1. From the superficial jugular veins in severe pulmonary engorgement
Chloral Hydrate, 1, 4. To be used with caution to allay pain
Cod-Liver Oil, 1. Relieves
Colchicum. In gouty cases
Copaiba, 4. In advanced stage of disease
Counter-irritants, 3. Dry-cupping most efficient in acute cases; mustard leaves; mustard poultices
Croton Oil, 3. As liniment; vesication must not be produced
Cubebs. When secretion copious
Demulcents, 4. Liquorice, linseed
Eucalyptus, 1, 4. As liniment combined with Belladonna in the early stage. Internally in the late stage
Garlic, Oil of, 4. In the acute bronchitis of children
Ipecacuanha, 1, 2, 3, 4. When expectoration scanty, dryness in chest, ipecacuanha in large doses; also when expectoration has become more abundant, but difficult to expel
Jalap, 3. With Bitartrate of Potassium instead of bleeding in engorgement of the right side of the heart
Lead, 3. In profuse discharge
Lobelia, 2, 3. 4. When cough is paroxysmal and there is much expectoration slightly nauseant expectorants are good, combined with opium
Mercury, 1. In some cases useful where there is much congestion and litt'e secretion
Morphine, 2. ½-gr. combined with quinine (gr. x.) will abort the attack if given early enough
Muscarine, 2. In doses of $\frac{1}{8}$ gr. at the commencement of the attack; well combined with digitalis
Mustard, 3. Poultice in acute bronchitis of children and adults
Nitric Acid. When expectoration free and too copious
Opium. As Dover's powder to cut short attack, and along with expectorants to lessen cough
Pilocarpine, 2. With abundant exudation
Potassium Chlorate. 1. First increases the fluidity of the expectoration, then diminishes it in quantity, increasing the feeling of relief

Bronchitis, Acute.

Poultices, 3. In children to encircle the whole chest
Quinine, 3. To reduce temperature
Sanguinaria, 2, 4. After acute symptoms have subsided
Senega, 4. In the advanced stage of acute disorder
Squills, Sypup of, 2, 4. Combined with Tinct. Camphoræ Co. after acute stage is over
Tartar Emetic, 2, 3, 4. In dry stage to promote secretion; most useful in the first stage
Turpentine, 3, 4. When expectoration very profuse; also as inhalation or stupes

Bronchitis, Capillary.

Alum, 2. As a nauseating expectorant and emetic
Ammonium Carbonate. Much fluid or viscid expectoration and lividity commencing. Also as an emetic
Ammonium Chloride, 2, 3. To promote secretion
Ammonium Iodide. In small rapid doses relieves much
Apomorphine, 2. To produce a plentiful fluid secretion; also as nauseant expectorant
Camphor, 2. As expectorant and stimulant
Cupping. Four to six dry cups over the back often give very great relief, and if the pulmonary congestion appears very great wet cups should be placed instead, and 8–10 oz. of blood withdrawn from adult
Ethyl Iodide, 2. As an inhalation
Iodides, 2. Are very serviceable to diminish viscidity of expectoration if given in very low doses
Ipecacuanha. As expectorant and emetic
Mustard. As poultices
Pilocarpine, 2. In abundant non-purulent exudation; not to be used in dilatation of veins and right side of the heart
Poultices. Over whole chest
Serpentaria. In children as a stimulant expectorant
Subsulphate of Mercury, 2. As nauseant expectorant and emetic
Turpentine, 2. In languid circulation in the capillaries

Bronchitis, Chronic.

Acids, 3. To diminish a chronic copious expectoration
Actæa Racemosa, 1. Sometimes relieves the hacking cough
Alum, 1. In children with copious expectoration in doses of gr. iij.
Ammonia. When there is difficulty in bringing up expectoration
Ammoniacum. Very useful, especially in elderly people
Ammonium Chloride, 2, 3, 4. To render the secretion less viscid
Antimony. When secretion scanty
Arsenic, 3, 4. In emphysema and asthmatic attack as cigarettes, where there is much wheezing and little bronchitis following the sudden disappearance of eczematous rash
Asafœtida. Like Ammoniacum
Balsam of Peru, 3. When expectoration copious
Balsam of Tolu, 3. The same
Belladonna, 1. To children choked with secretion give ♏j. of tincture every hour to stimulate respiratory centre. It also lessens the secretion
Benzoin, 3. As inhalation or as spray
Burgundy Pitch, 4. Emplastrum in chronic bronchitis

Bronchitis, Chronic.

Camphor
Cannabis Indica, 1. In very chronic cases
Carbolic Acid. As inhalation or as spray
Carbonic Acid Gas, 1. Inhaled
Chamois-Leather Waistcoat, 3.
Cheken, 1. The fluid extract renders expectoration easier, and paroxysms less frequent
Chloral Hydrate, 1. A solution of gr. x. to ʒj. used as a spray to allay cough
Codeine. In place of opium when the latter disagrees
Cod-Liver Oil. One of the most useful of all remedies
Colchicum. In acute cases
Conium, 1. The vapour to relieve cough
Copaiba. Like Balsam of Peru
Creasote, 1. Inhaled to allay cough
Crude Petroleum, 1. In capsules or pills in chronic bronchitis
Cubebs, 2, 4. Like Copaiba
Digitalis. Where heart is feeble, especially in the aged
Emetics
Eucalyptus. Stimulant expectorant
Galbanum, 3. Like Ammoniacum
Gallic Acid. With profuse discharge
Grindelia, 2. Expectorant when the cough is troublesome
Hydrastis. In chronic coryza
Iodides 2, and Iodine, 3. As inhalation or liniment to chest, to lessen expectoration in chronic bronchitis; in the hoarse hollow cough of infants after measles
Ipecacuanha, 1, 3. Wine as spray, with much expectoration; in emetic doses in children where the bronchioles are blocked up with mucus
Iron. When expectoration is profuse
Koumiss-Cure, 2. Sometimes very useful
Lobelia, 3. When there is spasmodic dyspnœa
Mercury, 1. To diminish congestion
Morphine, 1, 2. To quiet cough, in small doses
Nitric Acid, 1. In mixtures to remedy the effect on digestion produced by sedatives like opium
Opium. To lessen secretion and cough
Phosphates, 3. In very chronic cases
Physostigma, 4. In chronic cases with great dyspnœa
Plumbic Acetate, 1. In profuse secretion
Potassium Iodide, 1. In combination with Antim. Tart. in cases of great dyspnœa. The carbonate in viscid secretion
Sanguinaria, 2. With other expectorants
Senega, 3. When expulsive efforts are feeble
Serpentaria. Like Senega
Spinal Ice-bag, 3. In excessive secretion
Squill. Where expectoration is thick
Stramonium, 1. In dry cough
Strychnine, 2. As respiratory stimulant
Sulphur, 3. Where expectoration copious, bronchitis severe, and constitutional debility
Sulphurous Acid Gas, 1, 2, 3. As inhalation or spray
Sumbul
Tar. To lessen secretion and allay chronic winter cough; may be given in pill or as spray
Terebene. Internally, or as inhalation
Turkish Bath, 3. To clear up a slight attack and to render the patient less susceptible to taking cold
Turpentine, 1. Liniment to chest in children
Zinc Oxide, 3. To control too profuse a secretion

Bronchorrhœa.

Alcohol, 2. Accordingly as it agrees or disagrees with the patient
Alum, 4. A remote astringent

Bronchorrhœa.

Ammoniacum, 3. In old people
Ammonium Carbonate, 2. Stimulant expectorant
Ammonium Chloride, 2. Stimulant expectorant
Ammonium Iodide, 3. Small doses frequently repeated; value increased by the addition of arsenic
Asafœtida, 3. Like Ammoniacum
Astringents, 4.
Carbolic Acid, 2. As spray
Cod-Liver Oil
Copaiba, 2. Stimulant expectorant; to be given in capsules
Cubebs, 2. Like Copaiba
Eucalyptus. Sometimes very useful
Gallic Acid, 4. Remote astringent
Grindelia, 2. Respiratory stimulant
Iodine. As counter-irritant to chest, and as inhalation
Lead Acetate, 3. To lessen secretion
Myrtol, 2. In profuse fœtid expectoration
Oleum Pini Sylvestris. As inhalation
Quinine, 2. Tonic.
Phosphates, 2. Tonic.
Spinal Ice-bag, 3. To lessen secretion
Sulphurous Acid Gas. As inhalation or spray
Terebene
Turpentine, 2. Stimulant expectorant, and also as inhalation

Bruises.

Aconite. Liniment locally, to relieve pain
Arnica. As local application, no more use than alcohol, and sometimes gives rise to much inflammation; this it will do if the skin is abraded
Capsicum. To remove discolouration of bruise
Compressed Sponge, 1.
Convallaria (Solomon's Seal), 1. The juice from the fresh root will take away a 'black eye'
Hamamelis, 3. Locally
Ice, 1
Lead Lotions. To allay pain
Oil of Bay. Same as Capsicum
Opium. Local application to relieve pain
Spirit Lotion, 1.
Sulphurous Acid. As local application constantly applied

Bubo.

Argentic Nitrate, 1. A saturated solution, applied over, will often effect absorption
Blisters, 1. Followed up by application of Tinct. Iodi, will cause absorption
Chloral Hydrate, 4. 25 per cent. solution, antiseptic and stimulant application
Copper Sulphate, 1. Gr. iv. to ʒj.
Hydrargyri Perchloridum, 1. Epidermis is first removed by a blister and then a saturated solution applied; a poultice is then applied to separate the eschar, leaving a healthy ulcer
Ice. To relieve pain and lessen inflammation
Iodine, 1, 3. As counter-irritant applied round the bubo
Iodoform, 1, 4. As local application
Lead Lotions, 1. Compresses soaked in these will abort, or assist in the healing process
Mercury. As local application after opening bubo, when syphilitic affection is great
Nitric Acid, 1. As local application to indolent bubo
Peroxide of Hydrogen, 3. Washed and dressed with lint soaked in it
Potassa Fusa, 1. To open, instead of the knife
Potassio-Tartrate of Iron. Local and general

Bubo.

Potassium Chlorate, 1. Powdered finely and then applied
Silver Nitrate. Lightly applied to surface in indolent bubo
Sulphides, 3. To check suppuration; not so useful as in an ordinary abscess
Tartar Emetic, 1. When inflammation acute and fever considerable

Bunion.

Iodine. Painted on in indolent forms
Rest. When thickened and painful. Pressure is removed by thick plasters, with a hole in the centre

Burns and Scalds.

Alkalies, 1. Soon remove the pain if exposed to the air after application
Alum, 1. Finely powdered over foul, bleeding granulations
Anhydrous Dressings, 1.
Argenti Nitras, 1. Wash with a solution of gr. iv. to gr. viij. to 3j. and wrap in cotton wool
Bismuth and Glycerine, 1. A thick paste of the subnitrate protective
Boric Acid, 1, 2, 3. Useful as ointment or lint dressings, or as Boric Oil
Carbolic Acid. One to six of olive oil, locally; 1 per cent. solution relieves pain and prevents suppuration
Carron Oil, 1, 4. In recent burns
Chalk, Oil, and Vinegar, 1. Applied as a paste of a creamy consistence relieves pain at once
Chlorinated Soda. In dilute solution
Chloroform, Olive Oil, and Lime-Water, 1. Soon relieves the pain
Cocaine, 3. As lotion to allay the pain
Cod-Liver Oil
Cold, 1. Instant application
Collodion, 2, 3. Flexile, to protect from air
Cotton Wool. To protect from irritation and so lessen pain
Creasote, 1. Like Carbolic Acid
Gallæ, Unguentum, 1. To prevent cicatrix. Formula: Ung. gallæ, 3j. Adipis 3j.
Ice to Spine, 1.
Iodoform, 1. Local anæsthetic and antiseptic
Lead Carbonate. As white paint for small burns; should be applied instantly
Lime, 3. As Lin. Calcis, or lime-water with linseed oil
Linimentum Terebinthinæ, (Kentish Ointment, U.S.P.), 2, 4. To be applied at once to the injury
Oakum, 1.
Oil and Litharge, 1. Applied as a varnish containing 5 per cent Salicylic Acid
Ol. Menthæ Piperitæ, 1. Painted on
Phytolacca. To relieve pain.
Potassium Chlorate, 1. Solution of gr. v. to 3j. locally
Rhubarb Ointment, 1. One part of root to two of lard
Salicylic Acid, 2. One to sixty, olive oil
Soap Suds, 1. Instead of alkali, if it is not at hand
Sodium Bicarbonate, 1. Immediate application of a saturated solution
Stimulants, Local, 1. Such as Ung. Resinæ afterwards followed by astringents
Thymol, 1. 1 per cent. in Olive Oil, local anæsthetic
Treacle, 1. A useful handy remedy for dressing
Warm Bath. Keep whole body, with exception of head, totally immersed for some days in very extensive burns or scalds. It relieves pain, although it may not save life
Whiting and Water, 1. Mixed to the thickness of cream and smeared over, excluding the air, gives instant relief
Zinc Ointment and Vaseline. In equal parts for dressing

Bursitis.

Blisters. Most useful
Carbolic Acid, 4. As injection
Fomentations. To relieve pain
Iodine. When chronic, Lin. Iodi may be used as a blister, or the liquor, after blistering or aspiration

Cachexiæ.

Air. Fresh
Aliment. Nutritious
Ammonium Carbonate. With bark; after acute illness
Arnica. Internally, in bad cases
Arsenic, 1, 2. In malarial, also in cancerous, cachexia; in chronic malaria, combined with iron
Baths. Turkish bath useful
Chalybeate Waters, 2
Cholagogues. Most useful before, or along with, other remedies, and especially in malarial cachexia before the administration of quinine
Electricity, 1
Eucalyptus, 2. In general cachectic conditions
Euonymin. As cholagogue
Ferri Succinas, 1, 2. In malarial cachexia; iron generally in all anæmic conditions
Glycerine, 4. As a food
Grape Cure
Hydrastis. In malaria
Manganese, 2. Along with iron and as syrup of double iodide
Massage, 2. Exceedingly useful
Mercury. In syphilitic cases; *see* Cholagogues
Nitric Acid. In debility after acute disease; in combination with the fresh decoction of bark
Oil and Fats, 2. Cod-liver oil very useful. Cream as an addition to food; oil as inunction
Phosphates. In cachexiæ attended with much discharge
Phosphate of Calcium, 1. In scrofulous phthisis and malnutrition
Podophyllin. As cholagogue; in children of a few months old improperly fed; in alcoholic excess; chronic morning diarrhœa
Potassium Iodide. In syphilitic and resulting conditions
Purgatives, Saline. As adjuncts to cholagogues
Quinine, 2. In various forms of cachexia
Sarsaparilla. In syphilis

Calculi, Biliary.

Aliment, 2. Absence of starch and fat recommended
Anæsthetics, 4. During the passage of the calculus
Belladonna, 4. Relief during spasm
Carlsbad Waters, 1. Prophylactic
Chloral Hydrate, 1. To relieve pain during paroxysm; good in combination with morphine
Chloroform. Inhalation from tumbler, most useful to relieve paroxysm
Counter-Irritation, 3. To relieve pain during passage

Calculi, Biliary.

Creasote, 1. Where the mischief arises from the intestinal canal
Emetics, 4. Of doubtful value in aiding the expulsion of the calculus
Ferri Succinas, 1. As a solvent for existing stones, and prophylactic
Ferri Perchlor. Tinctura, 1, Like Creasote, as an astringent. Useful if renal changes complicate
Iridin, 1. In doses of gr. j. for its cholagogue properties
Mercury, 1. The green iodide, with manna and soap as a pill
Morphine. ¼ gr. (repeated if necessary) with $\frac{1}{100}$ gr. atropine, subcutaneously, to relieve pain and vomiting in paroxysm
Nitric Acid, 1. Hepatic stimulant and alterative
Nitro-Hydrochloric Acid, 1. Same as Nitric Acid
Nitro-Hydrochloric Bath. To cause expulsion of calculus, and to relieve pain
Oil, 1. In large doses has been followed by the expulsion of gall-stones
Purton Spa, 1
Salicylate of Sodium. As prophylactic
Sodium Carbonate, 1. In large quantity of hot water during passage of stone. At first there is usually vomiting, but this soon ceases
Sodium Phosphate, 1, 2. In 20 or 30 gr. doses before each meal as prophylactic. Should be given in plenty of water
Sprudel Spa, 1
Turpentine and Ether, 1, 2. Durande's remedy. Equal parts to relieve pain during paroxysm ; also occasionally as prophylactic along with a course of Carlsbad or Vichy water

Calculi, Renal and Vesical.

Alkalies, 2, 3. To resolve calculi, potash and soda to be used
Alkaline Mineral Waters. Especially Vichy and Bethesda
Ammonium Benzoate, 2. To resolve phosphatic calculi
Anæsthetics. To relieve pain during passage of calculus
Belladonna, 4. Sometimes relieves the pain of the passage of calculus
Borocitrate of Magnesium, 1, 2. To dissolve uric acid calculus. Formula : Magnesii carb. 3j.; Acid. citric., 3ij.; Sodii biborat. 3ij.; Aquæ, ℥viij. m. sig. ; 3ij. ter die
Calumba. To relieve vomiting
Castor Oil. As purgative
Chloroform. As in biliary calculi
Cotton Root. As decoction to relieve gravel and strangury
Counter-Irritants, 3. To lessen pain during passage of calculus
Cows' Urine (Hippuric Acid), 1
Mineral Waters, especially Wildungen
Morphine. Hypodermically, as in biliary calculi
Nitric Acid. Dilute, as injection into the bladder to dissolve phosphatic calculi
Potassium Boro-Tartrate, 2. More efficient than the magnesium salt ; prepared by heating together four parts of cream of tartar, one of boric acid, and ten of water. 20 gr. three times a day well diluted
Potassium Citrate. In hæmaturia with uric acid crystals
Water, Distilled. As drink

Cancer.

Acetic Acid. As injection into tumours
Acid Nitrate of Mercury
Acids. Internally in cancer of stomach
Aluminium Sulphate, 1. A caustic and disinfectant application
Argenti Nitras, 1. A saturated solution injected in several places ; to be followed by an injection of common salt of a strength of 1 in 1,000
Arsenic, 1, 2, 3, 4. As local application, causes cancer to slough out. Sometimes successful when the knife fails, but is dangerous. Internally, in cancer in stomach lessens vomiting. Supposed to retard growth of cancer in stomach and other parts
Belladonna. Locally relieves pain. Used internally also
Bismuth, 2. To relieve pain and vomiting in cancer of stomach
Bromine Chlorides, 1. Alone or combined with other caustics. To be followed by a poultice
Bromine, Pure, 2. As caustic to use round cancer
Carbolic Acid, 1, 2, 3. As application or injection into tumour to lessen pain, retard growth, and diminish fœtor
Carbonic Acid, 1, 3. To relieve pain in uterine cancer
Caustic Alkalies, 1. In strong solution dissolve the cells.
Charcoal Poultices. To relieve pain and fœtor
Chian Turpentine, 1. Benefits cases according to the experience of some—of others, it is useless
Chloral Hydrate, 3, 4. To lessen pain
Chloroform. Vapour as local application to ulcerated cancer
Chromic Acid, 2. As caustic
Citric Acid. As lotion to allay pain, 1 in 60
Codeine, 1. As a sedative in cases of abdominal tumour
Cod-Liver Oil, 1. In cachexia
Coffee, 1. Disinfectant, applied as fine powder
Conium, 2, 3, 4. As poultices to relieve pain. Used internally also
Gas Cautery, 1. A form of actual cautery
Glycerine of Carbolic Acid, 3. Same as Carbolic Acid
Glycerine of Tannin, 3. Mixed with iodine, to check discharge and remove smell in uterine cancer
Hæmatoxylin Extract, 1. To a fungating growth
Hydrastis, 1, 2. Palliative application
Hyoscyamus. Bruised leaves locally applied
Iodoform, 1, 2, 3. Locally, to lessen pain and fœtor
Iron and Manganese. Internally as tonics
Lime, 1. As caustic
Opium, 3. Locally and generally, to relieve pain
Papain. As local application or injection
Pepsin. As injection into tumour
Potassium Chlorate, 2. Allays the pain and removes the fœtor
Potassa Fusa, 2. As escharotic
Poultices. To relieve pain
Salicylic Acid. Locally applied as powder or saturated solution
Sodium Ethylate, 1. A powerful caustic
Stramonium, 1. Ointment to relieve pain
Terebene, 1. Disinfectant dressing
Vienna Paste
Warm Enemata, 3. To lessen pain in cancer of rectum
Zinc Chloride, 2. As caustic
Zinc Sulphate, 2. As caustic

Cancrum Oris.

Arsenic. Internally
Nitric Acid. Undiluted as local caustic
Potassium Chlorate, 1. Internally in stomatitis; useless in noma
Quinine. As syrup or enema

Carbuncle.

Alcohol. As needed
Ammonium Carbonate. Combined with bark, after a free purge
Arnica, 3. Fresh extract spread on adhesive plaster and strapped; internal administration is also beneficial
Belladonna Extract. With glycerine, as local anodyne
Blister, 1. To cover area, with a hole in the centre to allow discharge
Boric Acid, 1. As dressing
Butyl-Chloral Hydrate, 1. To lessen the pain of facial carbuncle
Calcium Sulphide. $\frac{1}{10}$ gr. hourly useful
Carbolic Acid. As wash and injection after spontaneous discharge, or on lint after opening
Collodion. Round base, leaving opening in centre
Ether, 1. Sprayed on for a little time will cause an eschar to separate
Hydrargyri, Unguentum, 1. Early application will abort sometimes
Iodine. Locally, to lessen pain and inflammation, should be applied around the base
Iodoform. Useful local antiseptic dressing
Opium. Locally, mixed with glycerine
Potassium Chlorate and Mineral Acids, 1. Internally administered
Potassium Permanganate, 1. Antiseptic lotion
Poultices. To relieve pain
Strapping. Concentrically, leaving centre free, lessens pain
Terebene, or Turpentine. Antiseptic application

Caries.

Calcium Carbonate
Calcium Chloride
Carbolic Acid, 1. As a disinfectant lotion; often heals under this treatment
Cod-Liver Oil
Gold. In syphiloma of bone
Iodine, 1. Locally and internally
Phosphates of Calcium and Iron. Useful
Phosphoric Acid. Diluted, 1 in 8 of water, locally
Phosphorus
Potassium Carbonate, 1. Concentrated solution locally applied
Potassa Fusa, 1. To carious bone to remove disorganised portion
Potassium Iodide. In syphilitic cases
Sarsaparilla
Sulphuric Acid, 1. Injection (one of strong acid to two of water) into carious joints, and locally to carious or necrosed bone. To be useful the disease must be superficial.
Villate's Solution—Cupri sulph., Zinc. sulph. ää partes xv., Liq. plumb. subacetat. part. xxx., Acid acet. part. cc., as injection into a sinus

Catalepsy.

Chloroform, 1. Inhaled
Sternutatories
Turpentine. As enemata and embrocations to spine during paroxysms

Cataract.

Codeine. In diabetic cases
Diet and Regimen. Nutritious in senile cases. Sugar and starch to be avoided in diabetic cases
Galvanism. In early stage
Mydriatics. To dilate pupil as a means of diagnosis
Phosphorated Oil, 1. Instilled into the eye will lead to absorption if borne

Catarrh, Acute Nasal.

Aconite, 3. Internally at commencement, especially in children
Aconite and Belladonna, 2. In sore-throat and cold with profuse watery secretion, one drop of tinct. of aconite to two of belladonna every hour
Aconite Liniment. To outside of nose in paroxysmal sneezing and coryza
Ammonia, 2. As inhalation in early stage, while discharge is serous
Ammonium Chloride, 4. In the catarrh of young children
Ammonium Iodide, 2. 1 gr. every two hours
Argenti Nitras, 1. Injection of a solution of gr. x. to ℥j.
Arsenic. Internally, or as cigarettes in paroxysm and chronic cases; valuable in cases which exactly simulate hay fever
Baths. Hot foot-bath. Turkish, at commencement; cold bath is prophylactic
Belladonna, 2. 5 m. of tinct., and afterwards one or two doses every hour until the throat is dry in acute nasal catarrh, with profuse watery secretion, and in ordinary sore-throat
Benzoic Acid, 1. In ordinary catarrh, for its stimulant effects
Bismuth, as Ferrier's Snuff—Bismuth subnit. ij., Acaciæ pulv. ℥ij., Morph. hydrochlor. gr. ij.
Camphor. As inhalation
Carbolic Acid. As inhalation, or much diluted as spray. As gargle, 1 in 100, when catarrh tends to spread from nose into throat and chest, or to ascend from throat into nose
Cimicifuga, 2. In coryza accompanied by rheumatic or neuralgic pains in head and face
Cold Powder—Camph. partes v, dissolved in ether to consistence of cream, add Ammon. carbonat. partes iv. and Pulv. opii pars j. Dose, grs. iij-x. To break up or modify cold
Cubebs. Powder as insufflation; also smoked; also the tincture in ℥ss. doses with infusion of linseed
Ferrier's Snuff, *vide* Bismuth
Hot Sponging, 3. To relieve the headache
Iodine and Iodides. As inhalation; like ammonium iodide
Iodoform and Tannin, 2. As insufflation
Ipecacuanha, 2, 3. In moderate doses (gr. x.) Dover's powder at night will cut short an attack. The wine as spray to the fauces
Jaborandi, 1. As tincture or hypodermic injection of half a grain of pilocarpine
Nux Vomica. In dry cold in the head
Oil. Inunction to whole body to lessen susceptibility. Locally to nose. Sometimes ointment may be used instead
Opium, 3. As Dover's powder at commencement; but not with obstruction to respiration
Potassium Bichromate. Solution locally, 1 to 10 gr. in 4 oz.
Potassium Chlorate. Eight or ten lozenges a day to check
Potassium Iodide. 10 gr. at bedtime to avert acute coryza
Pulsatilla, 2. Warm lotion applied to interior of nares; or internally, but not with symptoms of intestinal irritation

Catarrh, Acute Nasal.

Quinine. 10 gr. of quinine with ½ gr. morphine at commencement may abort it
Salicylate of Sodium. 2½ gr. every half-hour to relieve headache and neuralgia associated with coryza
Sanguinaria. Internally, and powder locally
Sea-water Gargle
Spray. Useful means of applying solutions such as ipecacuanha wine, already mentioned
Sugar, 1. Finely powdered and snuffed up the nose in catarrh due to potassium iodide
Sulphurous Acid. As inhalation, spray, or fumigation
Tannic Acid, 1. Injection of a solution in rectified spirit
Tartar Emetic, 2, 3. $\frac{1}{20}$ to $\frac{1}{12}$ gr. at commencement, especially in children with thick and abundant secretion
Turkish Bath, 3
Veratrum Viride. If arsenic fails
Warm Foot-Bath, 3. Before going to bed
Zinc Sulphate, 1. As injection to nose, gr. j. to 3j.

Catarrh, Chronic Nasal.

Alum. In powder by insufflation, or in solution by douche
Ammonia. Inhalation
Ammonium Chloride, 3. In thick and abundant secretion
Asafœtida, 4. Stimulant expectorant
Balsam of Peru, 4. Stimulant expectorant
Benzoic Acid, 4. Inhaled as vapour
Bromine. As vapour, inhaled with great caution
Carbolic Acid. 1 to 100 as spray, or 1 to 200 as douche. 1 part with 4 of iodine tincture as inhalation or by spray
Cod-Liver Oil, 2
Cubebs, 2. In powder, by insufflation or trochees
Ethyl Iodide, 2. As inhalation
Eucalyptol, 3. In chronic catarrh with profuse secretion
Hamamelis, 3. In chronic catarrh, snuffed up nose
Hydrastis, 2. In chronic catarrh
Iodine, 2. Vapour inhaled
Iodoform and Tannin, 2. Insufflated
Sanguinaria, 2. In very chronic cases
Turpentine. As liniment to chest

Cerebral Anæmia.

Ammonia, 2. Inhaled is useful in sudden attacks
Amyl Nitrite. To act on vessels
Arsenic, 2. In hypochondriasis of aged people; best combined with a minute dose of opium
Aurum, 2. Melancholic state
Caffeine. In hypochondriasis
Camphor
Chalybeate Mineral Waters, 2
Chloral Hydrate. In small doses, with stimulants
Digitalis
Electricity
Glycerine
Guarana, 2. Restorative after acute disease
Iron
Nitro-Glycerine. To dilate cerebral vessels. Like Nitrite of Amyl
Nux Vomica
Phosphorus and Phosphates, 2. To supply nutriment
Quinine, 2
Strychnine, 2

Cerebral Concussion.

Rest. Absolute to be enjoined
Stimulants. To be avoided
Warmth. To extremities

Cerebral Congestion.

Aconite, 2. In acute cases before effusion has taken place
Arsenic, 2. In commencing atheroma of cerebral vessels and tendency to drowsiness and torpor
Belladonna. Very useful
Bromides. Very useful
Cathartics. To lessen blood-pressure
Chloral Hydrate. When temperature high
Colchicum. In plethoric cases
Colocynth. As purgative
Diet. Moderate, animal food sparingly, and stimulants to be avoided
Digitalis, 2. In alcoholic congestion; and simple congestive hemicrania
Ergot, 2. In want of arterial tone, or miliary aneurisms causing vertigo, &c.
Galvanism of head and cervical sympathetic
Gelsemium, 2. In great motor excitement, wakefulness, horrors after alcoholic excess
Hydrocyanic Acid
Venesection, 2. A suitable remedy in cases of threatening rupture of a vessel
Veratrum Viride, 2. In acute congestion, the good ceases with exudation
Water. Cold douche to head, and warm to feet, alternately hot and cold to nape of neck

Cerebritis.

Ammonium Chloride. Locally
Ice

Chancre.

Calomel, 1. Applied locally
Camphor, 1. Finely powdered
Canquoin's Paste, 4. Zinc chloride, 1 in 6, made into paste and applied
Carbolic Acid. Locally
Caustics. Chromic acid, bromine, acid nitrate of mercury, zinc chloride, nitric acid, caustic alkalies
Eucalyptol, 3. Mixed with iodoform and locally applied
Hydrogen Peroxide. Constantly applied to destroy specific character
Iodoform. One of the best remedies
Mercury. Internally. Black wash locally; or yellow wash, or corrosive sublimate in solution

Chancroid.

Camphor, 1. Finely powdered
Carbolic Acid. As injection and local application
Caustics. Sometimes necessary
Eucalyptol, 3. With iodine
Ferric Iodide, 2, 3. Internally in phagedænic cases, or debility
Ferrum Tartaratum. Like Ferric Iodide
Iodoform. Very useful
Mercury. Acid nitrate as local application
Nitric Acid. Locally as caustic
Potassium Chlorate, 1. In fine powder

Chapped Hands and Lips.

Benzoin, 4. Compound tincture, 1 part to 4 of glycerine
Collodion
Glycerine. Saturated with half the quantity of eau de cologne; or as glycerinum amyli

Chapped Hands and Lips.

Hydrastis. As lotion
Lotio Plumbi, 1
Solution of Gutta Percha, 1. Protective
Sulphurous Acid. As lotion or as fumigation

Chest Pains.

Belladonna, 3. In pleurodynia, as plaster or ointment
Iodine, 3. In myalgia as ointment

Chicken Pox.

Aconite
Ammonium Acetate
Bath. Cold in hyperpyrexia. Warm as diaphoretic
Compress, Cold. If sore-throat.
Laxatives

Chilblains.

Aconite, 1
Arnica. Useful
Balsam of Peru, 3. As ointment when broken
Basilicon. Ointment.
Cajeput Oil
Capsicum, Tincture. Locally, when unbroken, a strong tincture and solution of gum arabic in equal parts on silk
Carbolic Acid, 2. With tincture of iodine and tannic acid as ointment
Cod-Liver Oil. Internally
Collodion
Copper Sulphate, 1. Solution of, gr. iv. to ℥j.
Electricity
Iodine, 1, 2, 3. Ointment or tincture to unbroken chilblains
Sulphurous Acid, 1, 2, 3. Diluted with equal part of glycerine, as spray, or as fumes of burning sulphur
Tincture of Opium, 1. Locally to ease itching
Turpentine, 2

Chlorosis.

Arsenic. In place of, or along with, iron
Benzoin
Berberine Sulphate, 1. Inferior to quinine
Cocculus Indicus. In amenorrhœa and leucorrhœa
Ergot. In chlorotic amenorrhœa
Ferri Iodidum, 1.
Ferro-Manganates, 1
Gallic Acid, 1
Hypophosphite of Calcium, or Sodium, 3
Iron. 3. Carbonate, useful form. Sometimes best as chalybeate waters. In irritable stomach the non-astringent preparations; in weak anæmic girls, with pain and vomiting after food, the persalts are best
Manganese. In amenorrhœa
Massage. Useful, combined with electricity and forced feeding
Nux Vomica, 2. Useful, combined with iron
Oils and Fats. As inunction
Pancreatin, 2. To improve digestion
Pepsin. When digestion imperfect
Potassium Iodide
Purgatives. Useful; often indispensable
Sea-Bathing
Zinc Phosphide

Choking.

Potassium Bromide, 3. In children who choke over drinking, but who swallow solids readily

Cholera Asiatica.

Alcohol, 2. Iced brandy, to stop vomiting, and stimulate the heart
Ammonia, 1, 4. Intravenous injection
Amyl Nitrite
Antimony, 1
Arsenic. In small doses, has been used to stop vomiting.
Atropine, 2. Hypodermically in collapse
Boric Acid, 1
Cajeput Oil
Calomel, 2. In minute doses to allay vomiting
Camphor, 2, 3, 4. ℥v. of strong tincture, along with tincture of opium, every ten minutes, while the symptoms are violent, and then every hour
Cannabis Indica, 1
Cantharides
Capsicum, 1
Carbolic Acid, 2. Gr. ss. along with ℥ij. of iodine every hour
Chloral Hydrate. Subcutaneously, alone, or with morphine in the stage of collapse
Chloroform, 2 or 3 min., either alone or with opium, every few minutes to allay the vomiting
Cinnamon
Copper Salts. Sometimes used to stop vomiting
Corrosive Sublimate
Counter-irritation over Epigastrium
Creasote, 1. Alone or with opium to allay vomiting
Dry Packing, 1
Guaco, 1
Hydrocyanic Acid
Ice to Spine, 3. For cramps
Ipecacuanha, 1
Jaborandi, 1
Lead Acetate. Has been used as an astringent in early stages along with camphor and opium
Morphine, 3. One-eighth to one-fourth of a grain subcutaneously to relieve cramps
Naphthalin. May be useful
Nitric Acid
Opium, 2. In subcutaneous injection $\frac{1}{10}$-$\frac{1}{2}$ gr. to check the preliminary diarrhœa, and arrest the collapse
Permanganates
Phosphoric Acid, 1
Physostigma, 1
Podophyllin, 1
Potassium Bromide, 1
Quinine, 1
Ricini, Oleum
Saline Injections, 2. Into the veins have a marvellous effect during collapse, in apparently restoring the patient, but their benefit is generally merely temporary
Strychnine. Has been used during the preliminary diarrhœa, and also as a stimulant to prevent collapse
Sulpho-carbolates, 1
Sulphuric Acid. Alone, or with opium, is very effective in checking the preliminary diarrhœa
Transfusion of Milk. Has been used in collapse
Turpentine. Has sometimes appeared serviceable in doses of 10-20 m. every two hours

Cholera Infantum.

Aliment. Milk
Arsenic. For vomiting in collapse
Bismuth Sub-Nitrate, 1, 2. In emulsion
Brandy, 2. In full doses
Caffeine
Calomel, 2. In minute doses to arrest the vomiting
Camphor, 2. Where there is very great depression

Cholera Infantum.

Carbolic Acid, 2. With bismuth or alone very effective
Cold, 4. Bath at 75° F. every three or four hours, or cold affusions
Creasote, 1
Cupri Sulphas, 2. In very minute doses up to the one thirty-secondth of a grain
Ferri et Ammonii Citras, 1
Ice to Spine, 1
Ipecacuanha. When stools greenish or dysenteric
Lead Acetate. Very useful
Liquor Calcis, 1
Mercury, 2, 3. ⅓ gr. of grey powder, hourly. In urgent cases a starch enema should be given, containing a minute quantity of laudanum
Nux Vomica, 1
Oleum Ricini
Peptonized Milk, 1
Potassium Bromide, 2. In nervous irritability and feverishness
Potassium Chlorate, 4. In enemata
Resorcin
Rhubarb, 1
Silver Nitrate. After acute symptoms are past
Sodium Phosphate
Tannin and Glycerin
Zinc Oxide, 2. With bismuth and pepsin

Cholera Simplex.

Alcohol. Dilute and iced.
Arsenic. To stop vomiting
Atropine, 2. Hypodermically, an efficient remedy
Cajeput Oil. Used in India
Calumba. As anti-emetic
Camphor. Very useful
Carbolic Acid, 2. With bismuth
Chloral Hydrate. Subcutaneously, very useful
Copper Salts. As astringent
Ipecacuanha. Very useful
Lead Acetate, 2. At commencement and before administering opium, in order to deplete the vessels
Mustard. Internally, as emetic; poultice over chest
Opium. Hypodermically
Salines, 2. To precede the use of Lead Acetate
Sumbul
Veratrum Album

Chordee.

Aconite. 1 m. every hour
Amyl Nitrite, 1
Atropine, 2. Subcutaneously along with morphine
Belladonna. With camphor and opium, internally, very useful
Bromides. Especially of Potassium
Brominated Camphor, 4
Camphor, 2, 3, 4. Internally, useful in full doses
Cannabis Indica
Cantharis, 2, 3. One drop of tincture three times a day as prophylactic
Colchicum, 2. 3ss. of tincture at night
Cubebs
Digitalis, 1
Lupulin, 2, 4. As prophylactic
Morphine. Hypodermically, in perinæum at night, most useful
Tartar Emetic, 2. If carried to the extent of producing nausea
Strychnine
Tobacco Wine, 2. Just short of nauseating at bedtime

Chorea.

Anilin, 1
Amyl Nitrite, 1
Antimony, 1, 3. In gradually increasing doses twice a day, to maintain nauseating effect
Apomorphine, 3
Arsenic. Useful sometimes; must be pushed till eyes red or sickness induced, then discontinued, and then used again
Belladonna, 1
Bromide of Iron, 4
Bromide of Sodium, 4
Calcium Chloride, 1, 2. In strumous subjects
Cannabis Indica, 2. May do good; often increases the choreic movements
Chloral Hydrate, 2, 3, 4. Sometimes very useful in large doses, carefully watched, also where sleep is prevented by the violence of the movements
Chloroform, 3. As inhalation in severe cases
Cimicifuga, 3. Often useful, especially when menstrual derangement, and in rheumatic history
Cocculus, Picrotoxine, 2. In large doses
Cod-Liver Oil
Cold, 1, 3. To spine or sponging, but not with rheumatism, pain in joints, fever; best to begin with tepid water
Conium, 2, 3, 4. The succus is sometimes useful, must be given in large doses
Copper. The ammonio-sulphate in increasing doses till sickness produced
Curare, 1
Electricity, 1, 2. Static electricity
Ether Spray, 1. Instead of cold to spine
Hyoscyamus, 1
Iron, 1, 2, 3. Chalybeate waters in anæmia and amenorrhœa
Lobelia, 4. Only in nauseating doses
Mineral Water Baths, 1
Morphine, 2, 3. Subcutaneously in severe cases, until effect is manifested; by mouth in combination with chloral best
Musk, 3
Physostigma, 3. Three to six grains of powder a day for children, ten to twenty for adult
Potassium Bromide
Quinine, 1
Silver, 3. The oxide and nitrate sometimes do good
Strychnine, 2. Useful at puberty, or in chorea from fright
Valerian, 3. To control the movements
Veratrum Viride, 3. Has been employed
Water. Cold affusion to spine useful
Zinc Sulphate, 1, 3. In small but very frequent doses, and when the nausea produced is unbearable another emetic to be used

Choroiditis.

Mercury
Opiates

Climacteric Disorders.

Aconite. ♏j hourly for nervous palpitations and fidgets
Ammonia, 2, 3. As inhalation. Raspail's Eau sédative locally with headache. ℞ Sodii chloridum, ʒij.; Liq. ammoniæ, ʒij.; Spiritus camphoræ, 3iij.; Aquam ad ʒxxxij.
Ammonium Chloride. Locally in headache
Calabar Bean, 2. In flatulence, vertigo, &c.
Camphor, 3. For drowsiness and headache
Change of air and scene useful adjunct
Cimicifuga. For headache
Eucalyptol, 3. Flushings, flatulence, &c.
Hot Sponging, 3
Iron. For vertical headache, giddiness, and feeling of heat, fluttering of the heart

Climacteric Disorders.

Nitrite of Amyl. Where much flushed
Nux Vomica, 3. Useful where symptoms are limited to the head
Potassium Bromide. Very useful
Warm Bath
Zinc Vialerianate

Coccygodynia.

Belladonna. Plaster useful
Chloroform. Locally injected
Counter-irritation
Electricity
Surgical Treatment. In obstinate cases

Coldness.

Cold Water, 3. As prophylactic with friction and wrapping up
Spinal Ice-bag, 3. For cold feet
Strychnine

Colic, Intestinal.

Ammonia, 3. In intestinal colic, and in colic of children
Antacids, 4. In acidity
Arsenic. When pain is neuralgic in character
Asafœtida, 2, 4. To remove flatulence, especially in children and hysterical patients
Atropine, 4. In simple spasmodic colic
Belladonna, 3, 4. Especially in children and intestinal spasm
Chamomile Oil. In hysterical women
Chloral Hydrate, 3. Sometimes relieves
Chloroform. By inhalation, to remove pain and flatulence
Cocculus. During pregnancy
Essential Oils. Aniseed, 2, 3, 4. Cajeput, Camphor, Cardamoms, Cinnamon, Cloves, Peppermint, Rue, Spearmint. All useful
Ether, 2, 4. Internally and by inhalation
Fomentations
Ginger, 4. Stimulant carminative
Lime Water. In children, where due to curdling of milk
Milk Cure. In enteralgia
Morphine. Very useful
Nux Vomica. Useful
Opium, 3. In intestinal colic; if constipated, a purgative. With spirits of chloroform in renal and hepatic colic
Phosphate of Sodium. In hepatic colic, to prevent gall-stones forming
Potassium Bromide, 3. In local spasm in children, which can be felt through hard abdominal walls
Poultices. Large and warm, of great service
Tobacco. Dangerous

Colic, Lead.

Alum, 2, 4. Relieves the pain and constipation
Belladonna, 1
Bromides, 2. As solvents alone or with iodides
Castor Oil. Given twice a day to eliminate
Chloroform, 1. Internally and externally as liniment
Eggs, 1.
Electro-chemical Baths, 1
Iodide of Potassium, 2. Most useful in eliminating lead from the system, and combined with magnesium sulphate to evacuate it
Magnesium Sulphate. Most useful along with iodide of potassium
Milk, 1
Morphine, 2. Subcutaneously to relieve pain
Opium
Sodium Chloride, 1

Colic, Lead.

Sulphur, 1. To aid elimination
Sulphur Baths
Sulphuric Acid, 1, 2. Dilute in lemonade as a prophylactic and curative

Colic, Renal and Hepatic, *vide* also Calculi.

Aliment. Abstain from starches and fats
Alkalies. Alkaline waters very useful
Baths. Warm, to remove pain
Chloroform. Inhalation from tumbler during fit
Counter-irritation. *See* Irritants, &c.
Ether. Like chloroform
Opium. In small doses frequently repeated, or hypodermically as morphine
Turpentine

Coma.

Blisters, 3. On various parts of the body in succession in the critical condition, especially at the end of a long illness
Cold Douche. In the drunkenness of opium, care must be taken not to chill, and it is best to alternate the cold with warm water
Croton Oil. As a purgative in cerebral concussion, &c.
Mustard. To stimulate
Potassium Bitartrate, 3. Purgative where the blood is poisoned
Turpentine. Enema as stimulant

Condylomata.

Argentic Nitrate, 1. As caustic
Arsenic, 3. As caustic
Carbolic Acid, 2, 4. Locally
Chromic Acid, 1, 2, 4. 1–4 of water, locally, as caustic
Iodoform, 2. Locally applied
Mercury. Wash with chlorine water, or chlorinated soda, and dust with calomel and oxide of zinc in equal quantities
Nitric Acid. As caustic, or dilute solution as a wash
Thuja. Strong tincture, locally, small doses internally, useful
Zinc Chloride or Nitrate, 3. Locally, as a caustic or astringent

Conjunctivitis.

Alum. After acute symptoms have subsided, but not if the epithelium is denuded, since perforation may then take place
Argenti Nitras, 1. Solution of gr. iv.–ʒj. in purulent ophthalmia. The solid in gonorrhœal ophthalmia, to be afterwards washed with sodium chloride solution, gr. iv.–ʒj.
Belladonna. Locally and internally
Bismuth, 1, 2. Locally, in chronic cases
Blisters. Behind ear
Cadmium. As a wash instead of copper or zinc; the sulphate, gr. j.–ʒj.
Castor Oil. A drop in eye to lessen irritation from foreign body
Copper Sulphate. As collyrium
Ergot, 1, 2. The fluid extract, undiluted, locally applied in engorgement of the conjunctival vessels
Euphrasia. As a mild astringent
Mercury, 3. As citrine ointment, very useful outside the lids in palpebral conjunctivitis
Opium. Liquid extract in eye relieves pain
Pulsatilla. As wash and internally
Tannin. As Collyrium
Zinc Sulphate, 3. As Collyrium

Constipation.

Aloes, *vide* Dinner Pill
Alum
Ammonium Chloride. In bilious disorders
Apples. Stewed or roast
Arsenic. In small doses
Belladonna Extract, 2, 3, 4. $\frac{1}{10}$-$\frac{1}{2}$ gr. in spasmodic contraction of the intestine leading to habitual constipation; best administered along with nux vomica as a pill at bedtime
Bismuth, 3. Formula: ℞ Aluminii Sulphas, gr. jss.; Bismuthi Subnitratis, gr. j.; Extracti Gentianæ, q.s.; fiat pilula
Carlsbad Waters. Tumblerful sipped hot while dressing
Cascara Sagrada, 4. In habitual constipation, ♏x.–xx. of fluid extract an hour or two after meals
Castor Oil. ♏x.–xx. in a teaspoonful of brandy and peppermint water before breakfast
Cocculus. When motions hard and lumpy, and much flatus
Cod-Liver Oil, 3. In obstinate cases in children
Coffee, 3. Sometimes purges
Colocynth, 3. Compound pill. Colocynth pill at night, or a few drops of Prussian tincture
Croton Oil. When no inflammation is present, very active
Dinner Pills. Aloes and myrrh; aloes and iron; with nux vomica and belladonna or hyoscyamus, taken just before dinner
Enemata, 2, 3, 4. Soap and water, or castor oil; habitual use tends to increase intestinal torpor; should only be used to unload
Ergot. To give tone
Euonymin, 4. Cholagogue purgative in hepatic torpor
Fig. One before breakfast
Gamboge, 4. In habitual constipation
Guaiacum, 3. Especially when powerful purgatives fail
Honey. With breakfast
Hydrastis. Useful in biliousness
Ipecacuanha, 3. One grain in the morning before breakfast
Jalap, 3. Along with scammony
Lime, 3. Saccharated solution after meals
Liquorice Powder, Compound. A teaspoonful at night or in the morning
Magnesia, 3. Solution of bicarbonate, useful for children and pregnant women
Mercury, 3. In bilious disorders, stools light
Muscarine, 2. To increase peristalsis
Nux Vomica. ♏v.–x. in a glass of cold water before breakfast or before dinner
Opium, 1. When rectum is irritable
Physostigma. ♏x. of tincture along with belladonna and nux vomica in atony of the walls
Podophyllum. Very useful, especially in biliousness; ten drops of the tincture at night alone, or the resin along with other purgatives in pill, especially when stools are dark
Prunes, 3. Stewed, often efficient. If stewed in infusion of senna they are still more active
Rhubarb Compound Pill, 3. At night; also for children, mixed with bicarbonate of sodium
Saline Waters. In morning, before breakfast; Friedrichshall, Hunyadi Janos, or Pullna
Senna. As confection, &c.
Soap, 3. Suppository in children
Stillingia. ♏x. of fluid extract
Strychnine, 4. In atony of the walls
Sulphates, 3. In purgative natural waters, in small doses; sulphate of potassium has been used in poisonous doses
Sulphur, 3. Sometimes very useful as a good addition to compound liquorice powder, as in that of the Prussian Pharmacopœia
Tobacco, 2. ♏v. of wine at bed-time, or cigarette after breakfast

Constipation.

Treacle. With porridge useful for children
Turpentine. In atonic constipation with much gaseous distension of colon
Water. Draught in the morning before breakfast
Whole-Meal Bread

Convalescence.

Alcohol, 2. With meals
Bitters. The simple
Coca, 2. Either extract, or as coca wine for a nervine tonic
Cod-Liver Oil
Cream
Eucalyptus. A tonic after malarial disease
Guarana, 2. Same as coca
Hydrastis, 2. As a substitute for quinine
Iron, 2. As chalybeate waters
Koumiss
Lime. As lime-water or carbonate of calcium
Opium. As enema for insomnia
Pancreatin, 2. To aid digestion
Pepsin, 2. The same
Phosphates, 2
Phosphites, 2
Sea-Bathing, 3
Sumbul. Where great nervous excitability

Convulsions, Infantile.

Aconite
Alcohol. A small dose of wine or brandy arrests convulsions from teething
Asafœtida. A small dose in an enema arrests convulsions from teething
Baths. Warm, with cold affusions to the head
Belladonna. Very useful
Bromide of Potassium, 2, 3, 4. Exceedingly useful; children bear it in large doses; gr. v. three times a day or oftener for a child a year old in convulsions from teething
Chloral Hydrate. In large doses—gr. v. by mouth or rectum
Chloroform. To arrest fit
Garlic Poultices, 4. To spine and lower extremities in infantile convulsions
Ignatia. When intestinal irritation
Spinal Ice-bag
Valerian. When due to worms
Veratrum

Corneal Opacities.

Cadmium
Hydrargyri Bichloridum, 1. $\frac{1}{8}$ gr. to ʒj.
Iodine. Internally and locally
Mercury. Internally and locally
Silver Nitrate. Locally
Sodium Chloride. Injected under conjunctiva

Corns.

Acetic Acid
Chromic Acid
Iodine
Poultices. And plaster with hole in centre to relieve pressure
Salicylic Acid, 3. Saturated solution in collodion with extract of cannabis indica, ʒss–ʒj.
Silver Nitrate

Cough.

Aconite. In throat-cough and emphysema
Alcohol, 3. Relieved by brandy or wine; aggravated by beer or stout
Alum, 3. As spray or gargle

Cough.

Argenti Nitras, 1. In throat-cough, a solution of gr. viij.–ʒj. applied to fauces
Apomorphine. In bronchitis, with deficient secretion; and as emetic in children where there is excess of bronchial secretion
Asafœtida, 2. In the after-cough from habit, and in the sympathetic whooping-cough of mothers
Belladonna, 3, 4. In nervous cough and uncomplicated whooping-cough
Blue Pill. In gouty or bilious pharyngeal irritation
Butyl-Chloral Hydrate, 3. In night coughs of phthisis
Camphor. Internally, or locally, painted over the larynx with equal parts of alcohol
Carbonic Acid Gas, 3. Inhalation in nervous cough
Cerium, 2. In cough associated with vomiting
Chloral Hydrate, 2. In respiratory neurosis
Chloroform, 3. With a low dose of opium and glycerine in violent paroxysmal cough; if very violent to be painted over the throat
Cod-Liver Oil. One of the most useful of all remedies in cough
Conium, 3. In whooping-cough
Creasote, 3. In winter cough
Cubebs, 2, 3. Along with linseed in acute catarrh
Gelsemium, 2, 3. In convulsive and spasmodic cough, with irritation of the respiratory centre
Grindelia, 2. In habitual or spasmodic cough
Glycerine, 3. Along with lemon-juice, as an emollient
Hydrocyanic Acid, 2, 4. For irritable cough, and in phthisis, and in reflex cough arising from gastric irritation
Hyoscyamus. In tickling night-coughs
Iodine, 3. As inhalation in cough after measles, or exposure to cold, associated with much hoarseness and wheezing of the chest
Iodoform, 3. In the cough of phthisis
Ipecacuanha. Internally, and as spray locally; in obstinate winter cough and bronchial asthma
Ipecacuanha and Squill Pill. In chronic bronchitis at night
Lactucarium. To relieve
Laurocerasus. Substitute for hydrocyanic acid
Linseed. In throat-cough
Liquorice. In throat-cough
Lobelia, 2. In whooping-cough and dry bronchitic cough
Nasal Douche. In nasal cough
Opium, 2, 3. Morphine locally to the throat and larynx, and generally
Plasters. Calefaciens and picis to the chest
Potassium Bromide. In reflex coughs
Potassium Carbonate, 1. In dry cough with little expectoration
Prunus Virginiana
Pulsatilla. Anemonine, gr. ss–j. dose, in asthma and whooping-cough
Sanguinaria. In nervous cough
Tannin. As glycerine to the fauces in chronic inflammation, especially in children
Tar Water. In winter-cough, especially paroxysmal, bronchitis and phthisis
Valerian. In hysterical cough
Zinc Sulphate, 1. In nervous hysterical cough

Croup.

Aconite, 3. In catarrhal croup
Alum, 2, 3, 4. Teaspoonful, with honey or syrup, every ¼ or ½ hour until vomiting is induced; most useful emetic
Apomorphine, 2. As an emetic; may cause severe depression
Calomel, 2. Large doses, to allay spasm and check formation of false membrane

Croup.

Carbolic Acid, 2. Spray
Copper Sulphate, 2, 3. gr. j–v., according to age of child, until vomiting is induced
Ipecacuanha, 2, 4. Must be fresh; if it does not succeed, other emetics must be taken
Jaborandi, 4. Beneficial in a few cases
Lactic Acid. To dissolve membrane (1 in 20); applied as spray or painted over
Lime Water, 4. Spray, most useful in adults
Lobelia, 3. Has been used
Mercury Subsulphate. One of the best emetics; gr. iij–v. given early
Quinine, 2. In spasmodic croup, in large doses
Sanguinaria. A good emetic. ℞ Syr. ipecac. ʒij.; Pulv. sanguin. gr. xx.; Pulv. ipecac. gr. v.; give a teaspoonful every quarter-hour till emesis, then half a teaspoonful every hour
Senega. As an auxiliary
Sulphurous Acid, 3. As spray
Tannin, 3. As spray, or glycerin of tannin
Tartar Emetic, 2. Too depressant in young children
Zinc Sulphate, 2, 3. Sometimes used as an emetic

Cystitis.

Aconite. When fever present
Alkalies. When urine is acid and the bladder irritable and inflamed
Ammonium Citrate, 1. In chronic cystitis
Arbutin, 4. Diuretic in chronic cystitis
Belladonna. Most useful to allay irritability
Benzoic Acid, 1. In catarrh with an alkaline state of the urine
Boric Acid, 4. As Boroglyceride as injection in cystitis, with an alkaline urine due to fermentation
Buchu. Especially useful in chronic cases
Cantharides, 3. In small doses long continued, where there is a constant desire to micturate associated with much straining and pain in the act.
Carbolic Acid, 3. And sulpho-carbolates as antiseptics
Chimaphila. In chronic cases
Copaiba. Useful
Cubebs
Eucalyptus. Extremely useful in chronic cases
Hot Enemata, 3. To relieve the pain
Hot Sitz-Bath, 3
Hyoscyamus. To relieve pain and irritability
Iodine and Iodides, 4
Iodoform. As suppository
Milk Diet, 1
Opium. As enema, or suppository, to relieve pain
Pareira. In chronic cases
Potassium Bromide. To relieve the pain
Potassium Chlorate
Quinine. In acute cases
Salicylic Acid, 4. In chronic cystitis with ammoniacal urine
Sulphites. To prevent putrefaction of urine
Triticum Repens, 1
Turpentine, 3, 4. In chronic cases
Uva Ursi, 4. In chronic cases
Zea Mays, 4. A mild stimulant diuretic

Cysts.

Acupuncture, 2
Chloride of Gold, 2. In ovarian dropsy
Galvano-puncture
Iodine, 2. As an injection after tapping
Silver Nitrate, 2. As an injection

Deafness.

Ammonium Chloride
Cantharides. As ointment behind the ear
Colchicum. In gouty persons
Gargles. In throat-deafness
Glycerin, 3. Locally
Quinine. In Menière's disease
Tannin, 3. In throat-deafness

Debility.

Alcohol, 3. Along with food often very useful. Liable to abuse—not to be continued too long; effect watched in aged people with dry tongue
Arsenic, 3. In young anæmic persons, alone or with iron, and in elderly with feeble circulation.
Bitters. Useful as tonic
Calcium Salts, 3. Phosphates if from overwork or town life; hypophosphites in nervous debility
Cholagogue Purgatives. When debility is due to defective elimination of waste
Cinchona. A fresh infusion along with carbonate of ammonium
Cod-Liver Oil
Digitalis. When circulation is feeble
Eucalyptus. In place of quinine
Hydrastis. The same
Iron. In anæmic subjects
Manganese, 2. Alone or with iron
Morphine, 3. Subcutaneously, if due to onanism or hysteria
Nux Vomica. Most powerful general tonic
Quinine, 3. General tonic
Sanguinaria. When gastric digestion is feeble
Sarsaparilla. If syphilitic taint is present
Sea-Bathing, 3. In chronic illnesses with debility
Turkish Baths, 3. If due to tropical climate, with caution; in townspeople, when they become stout and flabby

Delirium.

Alcohol. When delirium is due to exhaustion
Antimony. Along with opium in fever, such as typhus
Baths, Cold. In fever
Belladonna. In the delirium of typhus
Blisters, 4. In delirium due to an irritant poison, and not to exhaustion
Bromide of Potassium. In fevers
Camphor. In 20-gr. doses every two or three hours in low-muttering delirium
Cannabis Indica. In nocturnal delirium occurring in softening of the brain
Chloral Hydrate, 3, 4. In violent delirium of fevers
Cold Douche, 3. Place patient in warm bath while administered
Hyoscyamus, 1
Morphine. Hypodermically
Musk, 4. In the delirium of low fever, and in ataxic pneumonia of drunkards with severe nervous symptoms
Opium. With tartar emetic
Quinine, 1
Valerian, 4. In the delirium of adynamic fevers

Delirium Tremens.

Alcohol, 2. Necessary when the attack is due to a failure of digestion; not when it is the result of a sudden large excess
Ammonium Carbonate. In debility
Antimony, 4. Along with opium, to quiet maniacal excitement and give sleep

Delirium Tremens.

Arnica, 2. The tincture where there is great depression
Beef-tea. Most useful
Belladonna. In insomnia when coma-vigil
Bromide of Potassium. In large doses, especially when an attack is threatening
Brominated Camphor, 4. Nervine, sedative, and antispasmodic
Butyl-Chloral Hydrate, 1
Cannabis Indica. Useful, and not dangerous
Capsicum, 2. 20–30-gr. doses, repeated after three hours, to induce sleep
Chloral Hydrate, 2. If the delirium follow a debauch; with caution in old topers and cases of weak heart; instead of sleep, sometimes produces violent delirium
Chloroform, 2. Internally by stomach
Cimicifuga. As a tonic
Coffee
Cold Douche or Pack, 1, 3. For insomnia
Conium. As an adjunct to opium
Croton Oil, 4. Purgative
Digitalis, 2, 3, 4. In large doses has had some success
Enemata. Nutritive, when stomach does not retain food
Food, nutritious, more to be depended upon than anything else
Gamboge, 4
Hyoscyamus. Useful, like belladonna, probably, in very violent delirium
Ice to Head, 3. To check vomiting
Lupulin, 4. As an adjunct to more powerful remedies
Opium. To be given with caution
Potassium Bromide
Quinine. To aid digestion
Stramonium. More powerful than belladonna
Sumbul. In insomnia and nervous depression preceding an attack
Veratrum Viride, 4. Very dangerous

Dentition.

Belladonna. In convulsions
Bromide of Potassium. To lessen irritability and to stop convulsions
Calumba. In vomiting and diarrhœa
Hypophosphites. As tonic
Phosphate of Calcium. When delayed or defective

Diabetes Insipidus.

Alum
Atropine
Creasote
Dry Diet, 2
Ergot, 2. Carried to its full extent
Gallic Acid. Combined with opium
Gold Chloride, 2. In a few cases
Jaborandi, 2. In some cases
Krameria. To lessen the quantity of urine
Muscarine, 2. In some cases
Nitric Acid
Opium. Most useful; large doses, if necessary
Potassium Iodide, 2. In syphilitic taint
Valerian. In large doses

Diabetes Mellitus.

CAUTION.—The urine of patients taking salicylic acid gives Trommer's test for sugar.

Alkalies, 2. Alkaline waters are useful, when of hepatic origin, in obese subjects; and in delirium
Almond Bread
Ammonium Carbonate
Ammonium Citrate

Diabetes Mellitus.

Ammonium Phosphate
Arsenic, 3. In thin subjects
Belladonna. Full doses
Calcium Sulphide
Codeine. A most efficient remedy. Sometimes requires to be pushed to the extent of 18 grs. or more per diem
Creasote
Glycerin. As remedy, and as food in place of sugar
Gold Chloride, 2
Hydrogen Peroxide
Iron. Most useful along with morphine
Jaborandi
Krameria
Lactic Acid
Opium, 3, 4. Most useful
Phosphoric Acid. To lessen thirst
Potassium Bromide
Quinine
Quinine Bromide, with morphine
Quinine Sulphate
Rhubarb
Salicylate of Sodium
Skim-Milk Diet
Sodium Citrate
Sodium Phosphate. As purgative

Diarrhœa.

Aconite. In high fever and cutting abdominal pains
Alkalies, 3, 4. In small doses in diarrhœa of children, if due to excess of acid in the intestine, causing colic and a green stool
Alum, 4
Ammonium Carbonate, 3. In the after-stage if there is a continuous watery secretion
Ammonium Chloride, 3. In intestinal catarrh
Argentic Nitrate, 3. In acute and chronic diarrhœa as astringent
Arnica
Aromatics, 4. In nervous irritability or relaxation without inflammation
Arsenic, 2, 3. A few drops of Fowler's solution in diarrhœa excited by taking food; in diarrhœa with passage of membranous shreds associated with uterine derangement; and along with opium in chronic diarrhœa of malarial origin.
Bael. Infusion to children
Belladonna, 4. In colliquative diarrhœa
Bismuth, 2, 3, 4. In large doses in chronic diarrhœa; with grey powder in the diarrhœa of children
Cajeput Oil, 4. Along with camphor, chloroform and opium in serous diarrhœa
Calcium Carbonate, 2. The aromatic chalk mixture in the diarrhœa of children, and in the diarrhœa of phthisis and typhus
Calcium Carbolate
Calcium Chloride. In the colliquative diarrhœa of strumous children, and in chronic diarrhœa with weak digestion
Calcium Phosphate, 3. In chronic diarrhœa, especially of children
Calomel, 2. In minute doses in chronic diarrhœa of children, with pasty white stools
Calx Saccharata, 1, 3. In the chronic diarrhœa and vomiting of young children
Camphor, 2, 3, 4. In the early stage of Asiatic cholera, at the commencement of summer diarrhœa, acute diarrhœa of children, and diarrhœa brought on by effluvia
Cannabis Indica, 1
Capsicum, 3. From eating fish; and in summer diarrhœa, and diarrhœa after expulsion of irritant
Carbolic Acid
Cascarilla
Castor Oil and Opium, 3, 4. To carry away any irritant; also alone in the diarrhœa of children
Catechu, 4. Astringent
Charcoal, 4. In foul evacuations
Chloral Hydrate, 1
Chloroform, 3. As spirits with opium after a purgative
Cocaine, 4. In serous diarrhœa
Cod-Liver Oil, 3. To children with pale stinking stools
Cold or Tepid Pack, 3. In summer diarrhœa of children
Copaiba, 4. From its local action in chronic cases
Copper Sulphate, 2, 3. $\frac{1}{10}$ gr. along with opium in acute and chronic diarrhœa, associated with colicky pains and catarrh
Corrosive Sublimate, 3. In small doses in acute and chronic watery diarrhœa, marked by slimy or bloody stools, of children and adults; and diarrhœa of phthisis and typhoid
Coto Bark. In catarrhal diarrhœa
Creasote
Dulcamara. In diarrhœa of children from teething and exposure
Ergot, 2, 4. In a very chronic diarrhœa succeeding to an acute attack
Erigeron Canadense
Eucalyptus, 4. In catarrh
Flannel Binder. Adjunct in children
Galls. In chronic diarrhœa
Guarana. In convalescence
Hæmatoxylon. Mild astringent, suitable to children from its sweetish taste
Ice to Spine, 3
Injection, 3. Of starch water, at 100° F., with tinct. opii and acetate of lead, or sulphate of copper in the choleraic diarrhœa of children
Ipecacuanha, 3. Drop doses of the wine every hour in the dysenteric diarrhœa of children, marked by green slimy stools
Iron Pernitrate, 3. Simple astringent
Kino. Astringent
Krameria. Astringent
Lead Acetate, 2, 3, 4. In suppository or by mouth; in the summer diarrhœa of children; with morphine of adults: with opium in purging due to typhoid or tubercular disease, in profuse serous discharge, and in purging attended with inflammation
Magnesia. Antacid in children
Mercury, 3. The grey powder in diarrhœa of children, marked by derangement of intestinal secretion and stinking stools; to be withheld where masses of undigested milk are passed; in adults, *vide* Corrosive Sublimate
Mineral Acids, 2, 4. In profuse serous discharges, and in cholera infantum
Nitric Acid. With nux vomica, to assist mercury, when due to hepatic derangement; combined with pepsin when this is the case with children
Nitro-hydrochloric Acid, 4. When it is an intestinal dyspepsia
Nitrous Acid, 4. In profuse serous diarrhœa, and the sudden diarrhœa of hot climates
Nux Vomica. In chronic cases
Oak Bark. Infusion astringent
Opium, 3, 4. In tubercular and typhoid diarrhœa; in acute, after expulsion of offending matter; as an enema, with starch, in the acute fatal diarrhœa of children
Pepsin. Along with nitro-hydrochloric acid in infantile diarrhœa
Podophyllum, 3. In chronic diarrhœa, with high-coloured, pale or frothy stools
Potassium Chlorate. In chronic cases with mucilaginous stools
Pulsatilla. In catarrhal
Quinine
Rhubarb, 3, 4. To evacuate intestine

Diarrhœa.

Rumex Crispus, 3. In morning diarrhœa
Salicin, 2. In catarrh and chronic diarrhœa of children
Salicylic Acid, 3. In summer diarrhœa and diarrhœa of phthisis
Sulphuric Acid. Diarrhœa of phthisis
Tannin with Opium, 2, 3, 4. In acute and chronic internally, or as enema
Veratrum Album, 3. In summer diarrhœa
Zinc Sulphate and Oxide, 3, 4. A stimulant astringent; of the oxide gr. iij. or gr. iv. for children

Diphtheria.

Alcohol. Freely given, very useful
Ammonium Chloride
Apomorphine. As an emetic
Argentic Nitrate, 2, 3. Of doubtful value
Arsenic. Internally
Belladonna, 2. At commencement, especially useful when tonsils much swollen and there is little exudation; later on, to support the heart
Benzoic Acid, 4. In large doses
Boric Acid or Borax, 3, 4. Glycerine solution locally
Bromine, 1. As inhalation
Carbolic Acid, 2, 4. As spray or painted on throat, internally with iron
Chloral Hydrate
Chlorinated Lime. Locally, as gargle or wash
Chlorine Water. Internally, locally in sloughing of the throat
Cold, 3, 4. Externally
Copper Sulphate. As emetic
Glycerine of Carbolic Acid, 3. Painted over twice a day
Guaiacum, 2, 3, 4. Internally.
Hydrochloric Acid, 2. Dilute as gargle, or strong as caustic
Iodine, 3. As inhalation
Iron, 2, 3, 4. The perchloride in full doses by the mouth, and locally painted over the throat
Lactic Acid, 2, 3. A spray or local application of a solution of 3j.–3j. of water, to dissolve the false membrane
Lemon Juice, 1. Gargle
Lime Water, 4. Most serviceable in adults, as a spray
Mercury. Internally as calomel or cyanide, $\frac{1}{20}$–$\frac{1}{40}$ of a grain
Papain. As solvent of false membrane
Pilocarpine, 2, 3, 4. Sometimes aids in loosening the false membrane
Potassæ, Liquor. Internally.
Potassium Bichromate. As emetic
Potassium Chlorate, 2, 4. Internally in large doses frequently repeated, and locally as a gargle
Potassium Permanganate, 3. As gargle
Quinine, 3. Strong solution or spray
Resorcin, 2. Spray to the throat
Salicylic Acid. Locally as gargle, or internally
Sanguinaria. As emetic. *Vide* Croup
Sassafras, Oil of. As local application
Soda Chlorinata, 3. In a solution as gargle
Sodium Hyposulphite and Sulphites. Internally and locally
Sodium Benzoate, 2. In large doses and powder unsufflated
Strychnine, 3. Subcutaneously for paralysis
Sulpho-carbolates, 2
Sulphurous Acid
Tannin, 3. 5 per cent. solution as a spray
Tolu, Balsam of

Dropsy.

Aconite, 1, 3. At once in scarlet fever if temperature should rise
Acupuncture, 3. In œdema about the ankles, to be followed up by hot bathing; not much use in tricuspid disease
Ammonium Benzoate. In hepatic dropsy
Ammonium Chloride. In hepatic dropsy
Antihydropin, 1, 4. A crystalline principle extracted from cockroaches; is a powerful diuretic in scarlatinal dropsy; gr. xv. as a dose for an adult; the insect used in Russia
Arsenic, 3. In dropsy of feet from fatty heart, debility, and old age
Asclepias Syriaca
Asclepias Syriaca and Apocynum
Broom. One of the most useful diuretics, especially in scarlatinal, renal, and hepatic dropsy
Bryonia. As drastic, purgative, and diuretic
Caffeine, 4. In cardiac and chronic renal dropsy
Cannabis Indica. As diuretic
Chenopodium Anthelminticum. In scarlatinal dropsy
Chimaphila, 2. In renal dropsy
Colchicum. In hepatic, cardiac, and scarlatinal dropsy
Convallaria, 3, 4. Used by the Russian peasantry
Copaiba, 2, 3, 4. Especially in hepatic dropsy and cardiac dropsies, not certain in renal
Digitalis, 2, 3, 4. In all dropsies, but especially in cardiac dropsy; infusion is the best form
Dry Diet, 2
Elaterium, 3, 4. Useful hydragogue cathartic, especially in chronic renal disease; should not be given in exhaustion
Erythrophlœum. In cardiac dropsy instead of digitalis
Gamboge, 4. Never to be used
Hellebore. In post-scarlatinal dropsy
Iron, 2. To correct anæmia; along with saline purgatives
Jaborandi, 2, 4. In renal dropsy with suppression of the renal function
Jalap, 3, 4. In some cases
Juniper, 2, 3. Exceedingly useful in cardiac, and chronic, not acute renal mischief
Milk Diet, 2
Nitrous Ether. Useful alone, or with other diuretics
Parsley, 2. A stimulant diuretic
Potassium Bitartrate and Acetate, 2, 3, 4. With compound jalap powder, most useful of the hydragogue cathartics
Potassium Iodide, 3. In large doses, sometimes a diuretic in renal dropsy
Potassium Nitrate. As diuretic
Saline Purgatives, 2
Senega, 4. In renal dropsy
Squill, 2, 3, 4. In cardiac dropsy
Strophanthus. In cardiac dropsy.
Sulphate of Magnesium, 3. A concentrated solution before food is taken
Taraxacum
Turpentine. In albuminuria

Duodenal Catarrh.

Arsenic, 2. In catarrh of the bile-ducts as a sequela
Bismuth
Gold, 2. The chloride
Hydrastis, 2. In catarrh associated with gallstones
Ipecacuanha
Nitro-Hydrochloric Acid
Podophyllum
Rhubarb

Dysentery.

Aconite. With much fever
Alum, 3. To control the diarrhœa
Ammonium Chloride, 1
Argentic Nitrate, 1. As injection
Arnica. With much depression
Arsenic, 2, 3. Fowler's solution, along with opium, if due to malarial infection
Belladonna
Benzoin. In chronic cases
Bismuth, 1
Calomel, 4. In acute sthenic type
Carbolic Acid
Castor Oil. In small doses, with opium
Cathartics, 4. To cause local depletion
Cold, 4. Enemata of ice-cold water to relieve pain and tenesmus
Copaiba, 4. In some cases
Corrosive Sublimate, 1, 3. In small doses in acute or chronic cases when stools are slimy and bloody
Creasote
Cupric Sulphate, 2. In acute, with sulphate of magnesium, and in later stage with opium; with opium in chronic
Ergotin, 2, 4. In very chronic type
Glycerine, 4. With linseed tea to lessen tenesmus
Grape Diet, 2
Hamamelis. Where much blood in motions
Injections, 3. In early stages, emollient; in later, astringent
Iodine
Ipecacuanha, 2, 3, 4. In 30-gr. doses on empty stomach, with complete rest; or as enema, with small quantity of fluid; milk is a good vehicle
Iron, 2. Internally, or as enemata
Lead Acetate, 2, 3, 4. By mouth, or as enema or suppository, along with opium
Lemon Juice
Magnesium Sulphate, 2. In acute cases, in early stage
Nitrous Acid, 4. In the chronic dysentery of hot climates
Nux Vomica, 2. In epidemic cases; and where prune juice stools and much depression
Opium, 2, 3, 4. To check the diarrhœa, given after the action of a saline purge
Potassium Bitartrate. In advanced stages where much mucus
Potassium Chlorate, 4. As enema
Quinine Sulphate. In large doses in malarious cases, followed by ipecacuanha
Soda Chlorinata. As enema
Sulphur. In chronic cases
Tannin, 2. Conjoined with milk diet in chronic disease
Turpentine, 2. Along with opium when the acute symptoms have passed off; also in epidemic of a low type
Zinc Oxide
Zinc Sulphate, 2. By mouth or enema

Dysmenorrhœa.

Aconite, 2. In congestive form in plethorics; or sequent to sudden arrest
Ammonium Acetate, 4
Amyl Nitrite, 2, 3, 4. In neuralgic form
Apiol (Oil of Parsley), 4. As emmenagogue in neuralgic form; to be given just before the expected period
Arsenic, 3. When membranous discharge from uterus
Belladonna, 4. In neuralgic form; along with synergists
Borax. In membranous form
Butyl-Chloral Hydrate, 3. In neuralgic form
Cajeput Oil, 3
Camphor, 2, 4. Frequently repeated in nervous subjects

Dysmenorrhœa.

Cannabis Indica, 2. Very useful
Chloral Hydrate, 2
Chloroform, 2. Vapour locally
Cimicifuga, 2. In congestive cases at commencement
Electricity. The galvanic current in neuralgic; an inverse current in congestive
Ergot, 2. In congestive cases at commencement, especially if following sudden arrest
Gelsemium, 2, 3
Ginger, 4. If menses are suddenly suppressed
Guaiacum, 4. In rheumatic cases
Hamamelis, 3. Often relieves
Hot Sitz Bath, 3
Ipecacuanha. As an emetic
Iron, 2. In anæmia
Morphine, 2. Like opium
Nux Vomica. In neuralgic form
Opium. Exceedingly useful in small doses of 3 to 5 ms. of tincture alone, or along with 3 or 4 gr. of chloral
Pulsatilla, 2. Like aconite
Rue
Sumbul

Dyspepsia.

Acids. Before or after meals, especially nitro-hydrochloric acid
Alcohol, 2, 4. Along with food when digestion is impaired by fatigue, &c.
Alkalies, 1, 2, 3, 4. Very useful before meals in atonic dyspepsia or two hours after
Alkaline Mineral Waters
Aloes. As dinner pill, along with nux vomica, in habitual constipation
Arsenic, 2, 3. ♏j. of liquor before meals in neuralgia of the stomach, or diarrhœa excited by food
Asafœtida
Belladonna, 3. To lessen pain and constipation
Berberine
Bismuth, 3. When stomach irritable; and in flatulence
Bitters, 2. Given with acids or alkalies to stimulate digestion
Bryonia. In bilious headache
Calabar Bean, 4. In the phantom tumour sometimes accompanying
Calumba. Very useful
Capsicum. In atonic dyspepsia
Cardamoms
Castor Oil
Cerium Oxalate
Chamomile
Charcoal. For flatulence
Cholagogues. Often very useful
Cinchona
Cocaine, 3. In nervous dyspepsia, ¼ gr. twice or three times a day
Cod-Liver Oil, 3. In the sinking at the epigastrium in the aged without intestinal irritation
Colchicum, 3. In gouty subjects
Cold Water, 3. Half a tumbler half an hour before breakfast
Creasote, 3. If due to fermentative changes
Eucalyptus, 2, 3. In atonic dyspepsia due to the presence of sarcinæ
Gallic Acid. In pyrosis
Gentian, 1. In atony and flatulence
Ginger, 4. An adjunct
Glycerine
Gold, 2. The chloride in nervous indigestion
Hops, 2. A substitute for alcohol
Hot Water, 3. A tumbler twice or three times between meals, in acid dyspepsia, flatulence, and to repress the craving for alcohol
Hydrastis. In chronic dyspepsia or chronic alcoholism

Dyspepsia.

Hydrochloric Acid, 3, 4. Dilute after a meal, especially if there is diarrhœa
Hydrocyanic Acid. In irritable cases
Ipecacuanha, 3. Useful adjunct to dinner-pill, in chronic irritable dyspepsia
Kino. In pyrosis
Lactic Acid. In imperfect digestion
Lime Water
Magnesia, 4. In acid dyspepsia
Magnesium Sulphate
Manganese. In gastrodynia and pyrosis
Mercury. As cholagogue
Morphine, 3. Subcutaneously in irritable dyspepsia of irritable subjects
Nux Vomica. Exceedingly useful in most forms along with mineral acids
Opium, 3. In sinking at the stomach partially relieved by food which, at the same time, produces diarrhœa, a few drops of tincture before meals; with nux vomica in palpitation, &c.
Pancreatin. 1½ or 2 hours after meals, very useful
Pepper, 4. In atonic indigestion
Pepsin, 2. Sometimes very useful with meals; and in apepsia of infants
Podophyllin, 3. A cholagogue, used instead of mercury; useful along with nux vomica and mineral acids
Potassium Iodide
Potassium Permanganate, 4. Like manganese
Potassium Sulphide
Quassia
Quinine, 3. In elderly people, and to check flatulence
Rhubarb
Sanguinaria. In atonic dyspepsia
Silver Nitrate, 4. In neuralgic cases
Silver Oxide
Sulpho-carbolate of Sodium, 3. In flatulence and spasm after a meal; in the latter, phosphorus is better
Sulphurous Acid. In acid pyrosis and vomiting
Tannic Acid. 3. In irritable dyspepsia
Taraxacum
Turkish Bath, 3. In malaise after dining out
Wahoo (Euonymin), 4. As a cholagogue
Xanthoxylum. As stomachic tonic

Dysphagia.

Bromide of Potassium. In hysterical dysphagia; or dysphagia of liquids in children
Cajeput Oil. In nervous dysphagia
Cocaine, 3. In tonsillitis, &c. as cause, 4 per cent. solution painted over
Hydrocyanic Acid, 1. As gargle
Iced Fluids. Slowly swallowed in spasmodic dysphagia

Dyspnœa.

Vide Asthma, Bronchitis, Croup, Emphysema, Phthisis

Dysuria.

Alkalies. When urine very acid
Belladonna
Camphor. In strangury
Cannabis Indica. In hæmaturia
Cantharides Tincture
Chimaphila
Ergot. In paralysis, when bladder feels imperfectly emptied
Gelsemium
Nitrous Ether
Opium

Ear-ache.

Almond Oil
Atropine, 2. Along with opium
Blisters, 3. Behind the ear
Cocaine, 3. As spray
Ether Vapour, 1. To tympanum
Glycerine, 3
Hop Poultice, 2
Lead Acetate, and Opium. As wash
Opium
Pulsatilla

Ecchymoses.

Alcohol. Externally
Arnica. Internally and externally
Compressed Sponge, 1. Bound over
Ice, 1
Solomon's Seal (Convallaria), 1. The juice of the root, especially in a 'black eye'

Ecthyma.

Cod-Liver Oil, 2. Internally and locally
Grape Cure. Useful
Lead. Locally
Quinine, 2, 3. For the malnutrition
Zinc Oxide. Locally

Ectropium and Entropium.

Collodion
Silver Nitrate

Eczema.

Alkalies. Weak solutions as a constant dressing
Alum, 3. To check a profuse discharge, not curative
Ammonium Carbonate, 1. Along with fresh infusion of cinchona
Anacardium Orientale
Argentic Nitrate, 2, 3. Simple solution, or solution in nitric ether painted over in chronic form
Arsenic, 2. Applicable only in squamous and chronic form, not in acute
Belladonna, 2. Internally, or atropine subcutaneously, in acute stage
Benzoin, 3. Compound tincture painted on to relieve itching
Bismuth, 2, 3. Where there is much exudation, the powder, or ointment either of subnitrate or carbonate
Blisters, 3. In chronic cases, especially of hand
Borax, 3. The glycerine in eczema of the scalp and ears
Boric Acid Ointment, 2, 3. Topically, especially in eczema of the vulva
Camphor, 3. Powder to ally heat and itching
Carbolic Acid, 2, 3. Internally and locally
Cashew Nut Oil. Ointment in chronic cases
Chloral, 1. As ointment 3ss.-ʒj. of petroleum; or as lotion
Cinchona, 3. Powdered bark locally as an astringent
Citrine Ointment, 2, 3. Locally, alone or with tar ointment in eczema of the eyelids
Cocaine, 3. To allay itching in scrotal eczema
Cocoa Nut Oil, 1. In eczema narium
Cod-Liver Oil, 3. In eczema of children due to malnutrition, and locally to skin to prevent cracking
Collodion, 1
Conium, 1
Copper Sulphate, 2. Astringent
Croton Seeds. Tincture of, as ointment

Eczema.

Electricity, 2. Central galvanisation in very obstinate cases
Eucalyptol, 3. With iodoform and vaseline in dry eczema
Glycerin, 3, 4. As local emollient after an attack
Glycerole of Aloes, 1. In eczema aurium
Hamamelis. Locally to allay itching
Iris Versicolor. In chronic gouty cases
Jaborandi, 1
Lead Salts, 2, 3. Where there is much inflammation and weeping, a lotion containing a glycerine preparation; if dry and itching, a strong solution or an ointment
Lime Water, 3. A sedative and astringent, in later stages with glycerine
Lithia, 1. In gouty subjects
Mercury
Oil of Cade, 3. With vaseline
Phytolacca. In obstinate cases
Plumbago, 1. Ointment in eczema aurium
Potassium Salts, 1. Internally
Potassium Cyanide, 3. To allay itching
Potato Poultice, 3. Cold, sprinkled with zinc oxide, to allay itching
Rhus Toxicodendron. Internally and externally; with much burning and itching, and in chronic eczema of rheumatism worse at night time
Salicylic Acid, 2, 3. Locally, if there is much weeping
Soap, 3. A glycerine soap to wash with night and morning will allay itching
Sulphides, Sulphur } 3. Internally, and as baths; but not in acute stage
Tannin, 2, 3. After removal of the scales the glycerine of tannin, tar, or other ointment may be required to complete the cure
Tar, 3. Ointment; and internally as pill or capsule in very chronic form
Turkish Bath
Viola Tricolor. Infusion along with senna; externally as ointment
Warm Baths, 3. In acute stages
Yolk of Egg, 2. With water locally
Zinc, 1, 3. The oxide and carbonate as dusting powders; the oxide as ointment, if the raw surface is indolent after inflammation has subsided

Elephantiasis.

Anacardium Orientale
Arsenic. Along with five or six times as much black pepper
Cashew Nut Oil
Gurjun Oil
Iodine, 1. Internally and externally
Sarsaparilla

Emaciation.

Arsenic
Calcium Chloride, 1. In scrofulous diathesis
Cinchona
Cod-Liver Oil
Iodine
Iron
Pancreatin
Pepsin
Phosphate of Calcium
Potassium Chlorate, 1
Potassium Iodide, 1. In syphilitic taint

Emphysema.

Apomorphine. When secretion is scanty
Arsenic, 2, 3. In subjects who are affected with dyspnœa on catching a very slight cold.

Emphysema.

Especially valuable if following on retrocession of a rash
Belladonna, 3. If bronchitis and dyspnœa are severe
Bleeding. When right side of heart engorged
Chloral, 3. In acute if sudden, a single large dose; if long continued, small doses
Cod-Liver Oil. One of the best remedies
Compressed Air, 2. Inhaled
Cubebs, 3. The tincture sometimes relieves like a charm
Ether. Internally, as inhalation
Grindelia, 2. In most respiratory neuroses
Hypophosphites
Iodide of Ethyl. As inhalation
Iron
Lobelia, 3. Where there is severe dyspnœa, or capillary bronchitis
Oxygen. In paroxysmal dyspnœa
Purging, 3. Instead of bleeding
Senega
Stramonium
Strychnine, 2, 4. As a respiratory stimulant
Turpentine, Oil of

Empyæma.

Aspiration, or free incisions
Carbolate of Iodine, 2.
Carbolic Acid, 2, 3.
Chlorine Water, 3.
Iodine, 2, 3, 4.
Quinine, 3.
Salicylic Acid.
} All used as injections to wash out cavity

Endocarditis.

Aconite. In small doses frequently at commencement
Blisters
Bryonia
Chloral Hydrate, 2. In moderate doses
Mercury, 4. To prevent fibrinous deposits; conjointly with alkalies; if of rheumatic origin
Opium. In full doses
Potassium Salts. To liquefy exudation
Quinine, 2. In full doses at the commencement
Salicylic Acid, 2. In the rheumatic form

Endometritis.

Carbolic Acid, 2. Locally applied, undiluted, on cotton wool probe in chronic form
Chromic Acid, 2. Strong solution, 15 gr.–3j. of hot water in catarrh
Ergot. Subcutaneously
Glycerin. Locally
Hot Water Injections
Hydrargyri Bichloridum, 1. Antiseptic injection
Iodine
Iodoform
Iodo-tannin. Solution of iodine in tannic acid applied on cotton wool
Nitric Acid
Ustilago Maydis

Enteritis.

Aconite. In acute cases
Argentic Nitrate, 1, 4. In chronic form
Arsenic, 3. In small doses along with opium
Calomel, 4. In obstructive enteritis with constipation, pushed to salivate
Castor Oil. Especially in the chronic enteritis of children. Very useful along with opium
Copper Sulphate, 2. In minute doses
Iron

Enteritis.

Lead Acetate, 2. Sedative astringent
Linseed, 4. Infusion as drink
Magnesium Sulphate, 4. The most valuable purgative
Opium
Podophyllum
Poultice Hot
Skim Milk. As diet, alone or with lime-water
Ulmus. Infusion as drink, or leaves as poultice

Enuresis.

Atropine
Belladonna. Very useful for children, but the dose must be large
Buchu. In chronic cases
Cantharides, 3. Internally very useful in middle-aged women or the aged
Chloral Hydrate. In children
Collodion. To form a cap over prepuce
Ergot. In paralytic cases
Iodide of Iron. In some cases
Lupuline
Potassium Nitrate, 3. In children
Rhus Toxicodendron
Rhus Aromatica
Santonin. When worms present
Strychnine, 3. Very useful in the paralysis of the aged, and incontinence of children
Turpentine

Epididymitis. *Vide* Testicle, Diseases of.

Aconite. In small doses frequently repeated
Mercury and Morphine. Locally as oleate if persistent
Pulsatilla. In very small doses along with aconite
Silver Nitrate. Strong solution locally applied to abort

Epilepsy.

Apomorphine. To prevent; in emetic doses
Argentic Nitrate, 1, 2, 3, 4. Sometimes useful, but objectionable from risk of staining
Arsenic. In epileptiform vertigo
Asafœtida
Anæsthetics, 4. Rarely called for
Belladonna. In *petit mal*, in nocturnal epilepsy and in anæmic subjects; perseverance in its use is required
Blisters. Over seat of aura.
Bromides of Potassium, Sodium, Lithium, and Iron. Most generally useful; dose should be large; in cases occurring in the day-time, in *grand mal*, reflex epilepsy, and cerebral hyperæmia
Brominated Camphor, 4
Bryonia
Calabar Bean, 4. Doubtful value; may produce a succession of fits
Camphor, 4. Has been, but is not now, much used
Cannabis Indica, 2
Cautery, 3. Frequently and lightly repeated
Cerium Oxalate, 1
Chloral Hydrate, 2. Full dose at bed-time in nocturnal attacks
Chloroform. Inhalation in hystero-epilepsy
Cod-Liver Oil
Conium
Copper Salts, 2, 3, 4. The ammonio-sulphate is sometimes useful
Electricity, 1
Hydrargyri Biniodidum, 1. In syphilitic history
Hydrobromic Acid
Ignatia

Epilepsy.

Iron, 2, 3. In uterine obstruction, in cerebral and general anæmia; alone, or the bromide along with the bromide of potassium
Lobelia, 4. Has been used as a nauseant to relieve the spasms
Musk, 3. Has been tried
Nitrite of Amyl, 2, 3, 4. Inhaled will cut short a fit; if there is appreciable time between aura and fit will prevent it, and cut short status epilepticus
Nitrite of Sodium, 3. In *petit mal* in gr. j. dose thrice daily
Nitro-glycerin, 2, 3. Like nitrite of amyl, but slightly longer in acting
Paraldehyde. Instead of bromides
Phosphorus
Picrotoxin, 1, 2. Weak and anæmic type; or nocturnal attacks; must be persisted in
Potassium Iodide. With bromide; alone in syphilitic history
Quinine
Rue. When seminal emissions also are present
Santonin, 4. Has been tried
Seton. In the back of the neck
Strychnine, 2. In idiopathic epilepsy and especially in pale anæmic subjects; not if there is any organic lesion
Sumbul, 1
Turpentine. If due to worms
Valerian, 3. Sometimes does good, especially if due to worms
Zinc Salts, 2, 3, 4. The oxide, or sulphate; epileptiform vertigo due to gastric disturbance is often relieved by the oxide

Epistaxis.

Aconite, 3. In small and frequent doses to children, and in plethora
Alum, 2. Powder snuffed or blown up the nostrils
Arnica. In traumatic cases
Barium Chloride, 2. To lower arterial tension
Belladonna
Blister over Liver, 1
Cocaine, 3. Locally in hæmorrhage from the nasal mucous membrane
Compression of Facial Artery, 3
Digitalis, 2, 3. The infusion is the best
Ergot, 2, 3, 4. Subcutaneously, or by stomach
Gallic Acid. Along with ergot and digitalis
Hamamelis
Ice. Over nose and head
Ipecacuanha, 2, 3. Until it nauseates or produces actual vomiting
Iron, 2. As spray the subsulphate or perchloride
Plugging anterior and posterior nares necessary, if epistaxis obstinate
Tannin, 2. Locally applied
Transfusion, 2. If death threatens from loss
Turpentine, 2. Internally in passive hæmorrhage
Warm Bath, 3. To feet and hands, with or without mustard
Warm Water Bag. To spine

Erysipelas.

Aconite, 3. At commencement may cut it short; valuable when skin is hot and pungent and pulse firm; also in erysipelatous inflammation following vaccination
Ammonium Carbonate, 2, 3. When tendency to collapse, and in typhoid condition; internally and locally; more adapted to idiopathic, especially facial erysipelas than to traumatic with fever, digitalis or aconite
Belladonna, 2, 3, 4

Erysipelas.

Benzoic Acid, 4. The soda salt 3ij.–3iij. in the twenty-four hours
Boric Acid, 4. Lotion in phlegmonous erysipelas
Carbolic Acid, 2, 3. Lint soaked in 2 per cent. solution relieves pain; subcutaneously 3ss., alcohol 3ss., water ℥ij.
Collodion, 3. Locally in superficial erysipelas, useless when cracked
Digitalis. Infusion locally
Hot Fomentations, 3
Iodine, 3, 4. Solution not too strong painted over
Iron. Large doses frequently, and local application
Potassium Permanganate, 3. Solution, locally and internally
Quinine, 2. In large doses
Resorcin, 2. Antipyretic and antiseptic
Rhus Toxicodendron
Silver Nitrate. Strong solution locally applied for an inch or two beyond inflamed area
Sodium Salicylate, 2. Antipyretic
Sulphurous Acid, 3. Equal parts with glycerine locally
Tartar Emetic, 1. Small doses frequently

Erythema.

Acids. In cases of indigestion
Alum, 2. Lotion
Belladonna, 2. In simple erythema
Bismuth. Locally
Hydrochloric Acid, 2. If reflex from gastro-intestinal disturbance
Lead, 2. The glycerine of the carbonate
Nitric Acid, 2. Like hydrochloric acid
Quinine. In erythema nodosum
Rhus Toxicodendron
Zinc, 2. Locally, as ointments or lotions

Exophthalmos.

Barium Chloride, 2. To raise arterial tension
Belladonna, 2, 3
Chalybeate Waters, 2. For the anæmia
Digitalis, 2. If functional in young subjects; often relieves in other cases
Galvanism of the cervical sympathetic, and pneumogastric nerves
Iron. For the anæmia

Favus.

Boric Acid, 2. Locally in ethereal solution
Carbolic Acid, 2. As a local parasiticide
Cod-Liver Oil, 2. In a debilitated subject
Mercury, Oleate, 3. Parasiticide; also lotion of bichloride gr. ij.–3j. of water
Myrtol, 2. Parasiticide
Oils, 3. To get rid of scabs, and prevent spread
Resorcin, 2.
Salicylic Acid, 2.
Sulphurous Acid, 3.
} Like myrtol

Fever.

Acids or Acid Drinks, 3. To allay thirst and aid digestion
Aconite, 2, 3, 4. Small doses frequently in all sympathetic fevers
Alcohol, 2, 3. Often useful, but effect watched carefully and quickly discontinued if it does not relieve symptoms
Alkalies, 3. Febrifuges, and increase urinary solids
Ammonia, 4. In a sudden collapse
Ammonium Acetate, 2, 3. Very useful as diaphoretic, more so in milder forms

Fever.

Ammonium Carbonate, 3. In scarlet fever and measles, and in any typhoid condition
Antipyrin, 3, 4. To reduce temperature; has caused collapse and death
Arnica, 2. Full doses of the infusion in sthenic reaction; low doses of the tincture in asthenia
Arsenic, 3. In malarious fevers; and in prostrating acute fevers to raise the patient's tone
Belladonna, 3. In eruptive fevers and delirium
Benzoate of Sodium, 4. In infectious and eruptive fevers, antiseptic and antipyretic
Bitters, 3. With acid drinks to quell thirst, e.g. cascarilla, orange peel, &c.
Blisters, 3. Flying blisters in various parts of the body in the semi-comatose state
Bromide of Potassium, 3
Calomel, 2. In the early stages of typhoid
Camphor, 3. In adynamic fevers, and in delirium, in gr. xx. doses every two or three hours, and effects watched
Carbolate of Iodine, 2. In the later stages of typhoid; and in chronic malarial poisoning
Carbolic Acid, 2, 3. An antiperiodic and antipyretic
Castor Oil, 3. As purgative
Chloral, 3. In the violent delirium and wakefulness of typhus, &c., and to reduce fever
Cimicifuga, 2. When cardiac action is quick and tension low
Cocculus. In typhoid, to lessen tympanitis
Coffee. In place of alcohol
Cold Bath and Affusion, 1, 2, 3, 4. To lessen hyperpyrexia, and a first-class stimulant, tonic, and sedative
Cold Packing, 3. In acute fevers, especially on retrocession of a rash
Digitalis, 1, 2, 3, 4. In inflammatory eruptive fevers, especially scarlet fever, as an antipyretic; much used in typhoid on the Continent
Elaterium, 1. Hydragogue cathartic
Eucalyptus, 3. In intermittent fevers
Gelsemium, 2, 4. In malarial and sthenic fevers, especially in pneumonia and pleurisy
Glycerine, 3. Demulcent drink
Hot Affusions, 3. For headache sometimes better than cold
Hydrastis, 2. Inferior to quinine in intermittent fever
Ice. To suck; bag to forehead
Kairin, 4. Not a safe antipyretic
Lemon Juice, 4. An agreeable refrigerant drink
Mercury. Small doses at the commencement of typhoid or scarlet fever
Musk, 3. A stimulant in collapse; along with opium in an acute specific fever
Opium, 3. In typhoid delirium; with tartar emetic if furious; at the crisis aids action of alcohol
Phosphate of Calcium, 3. In hectic
Quinine, 2, 3, 4. In malarial, typhoid, and septic fevers; the most generally applicable antipyretic
Resorcin, 2. Antipyretic and antiseptic
Rhus Toxicodendron. In rheumatic fever, and scarlet fever with typhoid symptoms
Salicin.
Salicylate of Sodium, 3.
Salicylic Acid, 2, 3.
} In rheumatic fevers, or in hyperpyrexia
Strychnine, 3. Subcutaneously for muscular paralysis as a sequela
Sulphate of Magnesium, 3. As a depletive and purgative
Tartar Emetic, 3, 4. In small doses, with opium, if delirium is not greater than wakefulness; if greater, in full doses, with small doses of opium: diaphoretic; in ague aids quinine, also in acute

Fever.

Turpentine, 2. As stimulant in typhoid, puerperal, and yellow, and to stop hæmorrhage in typhoid
Veratrum Viride. In delirium ferox
Warm Sponging, 3. In the simple fevers of children

Fistula.

Capsicum. As weak infusion locally
Pepper. The confection as laxative
Sanguinaria. As injection]

Flatulence.

Abstention from sugar, starchy food, tea, 3
Alkalies. Before meals
Ammonia, 3. In alkaline mixture a palliative
Asafœtida, 2, 3. In children; simple hysterical, or hypochondriacal
Belladonna, 2. If due to paresis of intestinal walls
Bismuth, 3. With charcoal, in flatulent dyspepsia
Calumba, 2. With aromatics
Camphor, 2. In hysterical flatulence, especially at climacteric
Carbolic Acid, 3. If without acidity, &c.
Carlsbad Waters. If due to hepatic derangement
Carminatives
Charcoal
Chloroform, 3. Pure, in drop doses in gastric flatulence
Creasote
Essential Oils, 3
Ether, 2. In nervousness and hypochondriasis
Eucalyptol, 3. At climacteric, if associated with heat flushings, &c.
Galvanism, 1
Hot Water, 3. Between meals
Ipecacuanha, 3. In constipation, oppression at epigastrium, and in pregnancy
Mercury, 3. When liver sluggish
Muscarine, 2. In intestinal paresis
Nux Vomica, 2, 3. In constipation, pain at top of head
Physostigma, 2. In women at change of life
Potassium Permanganate. In fat people
Rue, 1. Most efficient
Sulpho-Carbolates, 3. When no acidity, and simple spasms
Sulphurous Acid, 3. If due to fermentation
Turpentine. Few drops internally, or as enema in fevers, peritonitis, &c.

Flushing and Heat.

Eucalyptol, 3. At climacteric
Iron. Most useful
Nitrite of Amyl, 3. If associated with menstrual irregularity; accompanying symptoms, cold in the extremities, giddiness, fluttering of the heart; inhalation, or internally in one-third of a drop doses; effects sometimes disagreeable
Nux Vomica, 3. With tinct. opii in the hysteria of middle-aged women
Potassium Bromide, 3. If at climacteric
Valerian
Valerianate of Zinc, 3. At climacteric

Fractures and Dislocations.

Aconite. If febrile symptoms are present
Arnica. Internally and locally
Iodine. Antiseptic dressing
Opium
Phosphate of Calcium. Quickens union

Freckles.

Alkaline Lotions, 2
Benzoin
Borax
Iodine
Lime-Water
Mercuric Chloride, 1. Locally, with glycerine, alcohol, and rose water. ¾ of gr. to the oz.
Olive Oil
Potassium Carbonate

Gangrene.

Ammonium Chloride, 1
Balsam of Peru
Bromine, 2. Escharotic in hospital gangrene
Carbolic Acid, 2, 3, 4. Locally in strong solution to act as a caustic; as a dressing to promote healthy action
Charcoal. As poultice
Chlorine Water. To destroy fetor
Chromic Acid, 2. Local escharotic
Cinchona
Creasote
Eucalyptol, 2. Along with camphor in gangrene of lungs to prevent spread and lessen the fetor
Lime Juice and Chlorine Water in hospital gangrene
Myrtol, 2. To destroy fetor and promote healthy action
Nitric Acid, 2, 4. Next to bromine the most useful escharotic
Oakum, 1. Dressing
Opium
Oxygen. As a bath
Potassium Chlorate
Potassa Fusa, 2. Wide caustic
Resorcin, 2. Antiseptic, antipyretic
Salicylic Acid, 2. Locally
Sanguinaria
Turpentine, 2. Internally, and inhalation of vapour

Gastralgia.

Acupuncture. Sometimes gives great relief
Alum, 2. If pyrosis
Arsenic, 2, 3, 4. In small doses
Atropine, 2. In gastric ulcer
Bismuth, 2, 3, 4. In irritable gastralgia
Charcoal, 3. In neuralgia
Chloral, 3. To relieve pain
Chloroform. Two or three drops on sugar
Creasote, 3
Ergot
Ether, 2. A few drops
Galvanism. Of pneumogastric and sympathetic
Hydrocyanic Acid, 2, 4. If purely nervous
Manganese, 2, 3, 4. The black oxide purified
Milk Cure
Morphine. Subcutaneously, in epigastrium, very useful, or with bismuth and milk before each meal
Nitro-glycerin, 2. Quickly eases
Nux Vomica, 3. To remove morbid condition on which it depends
Pancreatin
Pepsin
Quinine, 2. If periodic in character
Resorcin, 2
Salicylic Acid, 2. Like quinine
Silver Nitrate, 2, 3, 4. Nervine tonic
Silver Oxide, 2
Zinc Oxide, 2

Gastric Ulcer.

Arsenic, 2. In chronic ulcer it eases pain and vomiting, and improves the appetite

Gastric Ulcer.

Atropine, 2. Arrests pain and vomiting
Bismuth, 2. Like arsenic
Cannabis Indica
Carlsbad Salts. Before meals
Castor Oil
Charcoal, 3. In chronic ulcer to allay pain
Ice-bag, 3. To epigastrium
Lead Acetate, 2. To check hæmatemesis
Lime Water with Milk, 3. Diet
Mercuric Chloride. Small dose before meals
Milk
Morphine, 2. Like atropine
Nutritive Enemata, 2, 3, 4
Opium
Pepsin
Peptonised Milk, 1
Potassium Iodide. With bicarbonate, to lessen flatulent dyspepsia
Silver Nitrate, 2, 3, 4. To relieve pain and vomiting
Silver Oxide, 2
Tannin
Turpentine, 3, 4. Frequently repeated to check hæmorrhage

Gastritis.

Alum. When vomiting of glairy mucus
Ammonium Chloride, 4. In gastric catarrh
Arsenic, 3. In drunkards
Atropine, 2. In chronic cases
Bismuth, 4. In catarrh
Caffeine, 3. Especially when associated with migraine
Calumba
Cinchona
Eucalyptus, 3. In chronic catarrh
Hydrastis, 2
Hydrocyanic Acid, 2, 3. To allay pain
Ice, 2, 3. To suck; and to epigastrium
Ipecacuanha, 2. In catarrh
Lead Acetate, 3. Along with opium
Nutrient Enemata
Nux Vomica
Opium
Silver Nitrate, 4. In chronic gastritis
Silver Oxide
Tannic Acid
Veratrum Viride, 4. Should never be used

Glanders.

Ammonium Carbonate. Every hour in concentrated solution, followed by opiate
Arseniate of Strychnine
Carbolic Acid. Locally
Chlorinated Soda. Locally
Creasote
Iodide of Sulphur
Iodine
Potassium Bichromate
Sulphites

Glandular Enlargements.

Ammoniacum, 4. Plaster counter-irritant on scrofulous glands
Ammonium Chloride
Arsenic
Barium Chloride
Belladonna
Blisters, 3. To scrofulous glands
Cadmium Chloride
Calcium Chloride. In enlarged and breaking down scrofulous glands
Calcium Sulphide, 3. For glands behind jaw with deep-seated suppuration
Carbolic Acid, 4. Injections of a 2 per cent. solution
Cod-Liver Oil, 3

Glandular Enlargements

Conium, 2, 4. In chronic enlargements
Gold Chloride. In scrofula
Guaiacum
Iodine. Internally; and painted around, not over the gland
Iodoform. As a dressing to breaking down glands
Lead Iodide, 2. Ointment
Mercury, 2, 4. Internally, and locally the oleate of mercury and morphine
Pilocarpine, 2. In acute affections of parotid and submaxillary
Potassium Iodide. Ointment over enlarged thyroid, and chronically inflamed glands
Sulphides, 2
Valerian

Glaucoma.

Atropine. Has caused this disease
Dubosine. Like Atropine
Eserine. Lowers intraocular tension
Iridectomy. The only cure

Gleet.

Aloes
Bismuth, 3. Along with glycerine or mucilage
Blisters, 2, 3. To perinæum useful in obstinate gleet
Cantharides, 2, 3, 4. Minim doses of tincture frequently repeated
Copaiba. Internally, and locally smeared on a bougie and introduced; best used in chronic form
Copper Sulphate. As injection
Eucalyptol, 3. In very chronic gleet
Iron, 2, 3, 4. Along with opium, either perchloride or sulphate as injection
Juniper Oil. Like Copaiba
Kino
Lead Acetate, 3. Injection is sometimes used
Lime Water, 3
Mercury, 3. Half a grain of bichloride in six ounces of water
Peru, Balsam of
Piper Methysticum
Sandal Wood Oil. Useful both locally and generally
Tannin, Glycerine of, 3. As injection
Tolu, Balsam of
Turpentine, 2, 3, 4. In a condition of relaxation
Zinc Sulphate, 3. As injection

Glossitis.

Bismuth. Locally
Electrolysis, 2. In simple hypertrophy, and cystic
Leeches, 1
Purgatives

Glottis, Œdema of.

Ammonium Carbonate. As emetic
Inhalations
Scarification. Especially useful
Tracheotomy

Goître.

Iodine, 2, 3, 4. Internally, and locally as ointment or tincture, and as injection
Mercuric Biniodide, 2, 3. As ointment, to be used in front of hot fire or hot sun
Potassium Iodide, 3

Gonorrhœa.

Aconite, 2, 3. In acute stage
Alcohol, 3. Not to be touched
Alkaline, 3. Salts or waters, as citrates or bicarbonates to make urine alkaline
Alum, 2. As an injection
Antimony, 4. If acute stage is severe
Benzoic Acid, 4. Internally
Bismuth, 2, 3, 4. Alone, or with hydrastis injected
Buchu, 2. More useful after acute stage
Cadmium Sulphate, 2. Astringent injection
Cannabis Indica. To relieve pain and lessen discharge
Cantharides, 3. In small doses where there is pain along urethra and constant desire to micturate. The tincture in min. doses three times daily in chordee
Cocaine, 3. Injection to relieve the pain
Colchicum, 2. In acute stage
Copaiba. After acute stage
Cubebs. Either alone or mixed with copaiba
Erigeron, Oil of, 4
Eucalyptus, Oil of, 4
Glycerin of Tannin, 2, 3. In later stage injection
Hydrastis, 2. As injection
Iron, 2, 3. Astringent injection in later stage
Kaolin
Lead Salts. As injection
Mercuric Chloride. Weak solution, locally
Pulsatilla
Quinine, 4. Stimulant in later stage
Sandal Wood Oil. Internally and locally
Silver Nitrate. As injection, said to cut short at commencement
Turpentine
Veratrum Viride, 2. In early stage of acute fever
Zinc Salts. As injection, sulpho-carbolate, acetate, &c.

Gout.

Aconite, 3
Alkalies, 2
Alkaline Mineral Waters, 2
Alkaline Poultice, 3
Ammonium Phosphate, 1
Ammonium Tartrate, 1
Argentic Nitrate, 1
Arnica, 2
Arsenic, 2, 4
Belladonna, 1
Blisters, 3
Carbonate of Lithium, 3, 4
Carbonic Acid, 1
Carlsbad Waters, 3
Chicory, 1
Chloral, 1
Citrate of Lithium, 3, 4
Cod-Liver Oil, 3, 4
Colchicum, 1, 2, 3, 4
Cold Water, 1
Collodion, 3
Ether, 4
Fraxinus, 1
Guaco, 1, 2
Horse Chestnut Oil, 1
Iodide of Potassium, 4
Iodine, 1, 3
Iodoform, 3
Lithium, 1, 4
Magnesia, 4
Manganese, 2
Morphine, 1
Oil of Peppermint, 3
Pine Leaves Bath, 1
Piper Methysticum, 1
Potassæ Liquor, 4
Prunus Virginiana, 1
Quinine, 1

Gout.

Rubefacients, 4
Salicylic Acid, 2
Sodium Chloride, 1
Sodium Salicylate, 1
Strawberries, 1
Strychnine, 3
Sulphides, 3. In chronic cases
Sulphur Baths, 2, 3
Trimethylamine, 1
Turkish Baths, 3
Veratrine, 1, 3. As ointment
Vichy Waters, 1

Gums, Spongy.

Alum, 2
Areca
Iodine Tincture. Locally
Krameria, 1
Myrrh
Pomegranate Bark
Potassium Chlorate, 1
Tannin, 2

Hæmatemesis.

Alum, 2, 3
Ammonium Chloride, 2, 3
Ergot, 2, 3. Hypodermically
Gallic Acid, 3, 4
Hamamelis, 2, 3
Ice, 3. Exceedingly useful
Ipecacuanha
Iron Perchloride, or Pernitrate, 3
Iron Subsulphate, 4
Lead Acetate, 2, 3
Logwood, 2
Magnesium Sulphate
Rhatany, 2
Sulphuric Acid, 3
Tannin, 2, 3, 4
Turpentine, 2, 3, 4

Hæmaturia.

Alum, 1. Internally, or as injection into the bladder
Bitartrate of Potassium
Camphor, 3
Cannabis Indica, 3
Chimaphila
Copaiba
Creasote
Digitalis
Ergot, 2
Gallic Acid, 2, 3, 4
Hamamelis, 3
Ipecacuanha
Iron Perchloride, or Pernitrate, 1
Krameria. Extract in large dose
Lead Acetate
Matico
Quinine, 2, 3
Rhatany, 2
Tannic Acid, 3
Turpentine Oil, 1, 2, 3, 4

Hæmoptysis.

Acetic Acid
Aconite
Alum, 4
Ammonium Chloride
Arnica
Astringent Inhalations, 4
Barium Chloride, 2
Chlorodyne, 1
Chloroform. To outside of chest
Copaiba

Hæmoptysis.

Copper Sulphate, 1
Digitalis, 1, 2, 3
Dry Cups. To chest
Ergot and Ergotinin, 2, 3, 4
Ferric Acetate. Added to water, so as to take away the taste; a little constantly sipped
Ferri Persulphas, 1
Gallic Acid, 1, 2, 3, 4. Very useful
Hamamelis, 3. Very useful
Hot Water Bag, 3. To spine
Ice, 3
Ipecacuanha, 1, 2, 3, 4
Iron, 2, 3. And absolute rest
Lead Acetate, 1, 2, 4. Very useful
Matico
Morphine, 3
Opium, 4
Phosphoric Acid
Potassium Bromide, 1
Potassium Chlorate, 1
Potassium Nitrate. When fever present, along with digitalis or antimony
Pyrogallic Acid, 1
Silver Oxide
Sodium Chloride. In drachm doses
Subsulphate of Iron, 4
Sulphuric Acid, 3
Tannin, 1, 3
Tr. Laricis, 1
Turpentine, 1, 3, 4
Veratrum Viride, 1, 2

Hæmorrhage, Intestinal.

Belladonna. For rectal ulcers
Castor Oil
Ergotin, 2, 3
Ferric Chloride, 1
Hamamelis. Very useful
Ice, 2, 3
Iodine
Iron, 2, 3
Lead Acetate, 2
Opium, 2, 3
Potassium Bitartrate, 1
Sulphuric Acid, 2, 3
Tannic Acid, 2, 3, 4
Turpentine, 1, 2, 3, 4. Very useful

Hæmorrhage, Postpartum.

Acetic Acid
Achillea
Capsicum
Cimicifuga
Compression of Aorta, 3
Digitalis
Enemata, Hot
Ergot, 4. Most efficient
Ether Spray
Gallic Acid
Hamamelis. For persistent oozing
Hot Water. Injection into uterus
Hydrastis
Ice, 3. To abdomen, uterus, or rectum
Iodine
Ipecacuanha, 3, 4. An emetic dose; good
Iron, Perchloride Diluted, 3. 1–4 injected into uterus
Mechanical Excitation of Vomiting, 3
Nux Vomica. Along with ergot
Opium, 2. 3j. dose of tincture, with brandy, in profuse bleeding
Pressure over Uterus
Quinine, 4

Hæmorrhoids.

Alkaline Mineral Waters useful
Aloes, 1, 2, 3, 4. As purgative

Hæmorrhoids.

Alum, 2. In bleeding piles, powder crystal or ointment
Argentic Nitrate, 1
Belladonna, 1
Bismuth, 1
Bromide of Potassium, 3
Calomel, 1, 3
Carbolic Acid, 1, 2. Injection into piles
Castor Oil, 3
Chalybeate Waters, 2
Chlorate of Potassium, 3
Chromic Acid, 1
Cocaine, 4
Cold Injection, 3
Cubebs, 4
Ergot, 1, 2, 4
Ferri Perchloridum, 1
Ferri Protosulphas. As lotion
Galls Ointment, 2, 3. With opium very useful
Grapes, 2
Glycerine, 1, 4
Hamamelis, 1, 3. Internally, and locally as lotion, injection, enema, or suppository
Hydrastis. As lotion and internally
Hyoscyamus. Bruised leaves or ointment locally
Ice, 3
Iodoform, 1, 4. As ointment or suppository
Leeches, 2
Lead, 3
Liq. Potassæ, 1
Magnesia, 1
Malt, 1
Nitric Acid, 1, 2, 3. As caustic; dilute as lotion
Nux Vomica, 1. Very useful
Ol. Lini, 1
Ol. Terebinthæ, 1
Opium, 3
Pitch Ointment, 1
Potassium Bitartrate, 1
Rheum, 1, 3
Saline Purgatives, 2
Senna, 2. As confection, or, better compound liquorice powder of Prussian Pharmacopœia
Stillingia. In constipation and hepatic disease
Stramonium, 4
Sulphur, 1, 2, 3, 4. As confection
Sulphurous Waters, 2
Tannic Acid, 4
Tobacco, 4

Hay Fever.

Aconite, 3
Ammonia, 3
Argentic Nitrate, 1
Arsenic, 1, 2, 3. As cigarette
Atropine, 2
Boric Acid, 1
Brandy Vapour
Bromine, 2
Camphor, 3
Carbolic Acid, 1, 2
Chlorate of Potassium, 3
Cocaine, 3, 4
Coffee, Strong, 1
Grindelia, 2
Hamamelis, 3
Iodide of Potassium, 1, 3. Internally and locally
Iodides, 2
Ipecacuanha, 3
Lobelia, 1
Morphine, 1, 2
Muscarine, 2
Opium, 3
Pilocarpine, 2

Hay Fever.

Quinine, 1, 2, 3, 4. Locally, as injection or douche
Salicylic Acid, 1
Strychnine, 1
Sugar Snuff, 1
Sulphurous Acid, 3
Sulphurous Spray, 1
Tetrachloride of Carbon, 1
Tobacco, 1
Tr. Cantharides, 1
Turkish Bath, 1, 3
Veratrum Viride, 3

Headache.

Aconite, 1. When circulation excited.
Actæa Racemosa, 3
Ammonia, 1, 2, 3, 4. Aromatic spirits in ½–2 dr. doses. Raspail's lotion very useful; often relieves nervous headache
Ammonium Chloride, 3. 10–15 gr. doses in hemicrania
Antacids, 4
Arsenic. In brow ague
Atropine, 2, 3. Locally to eye in migraine
Belladonna, 3. Frequently given in frontal headache, especially at menstrual period, or from fatigue
Bicarbonate of Sodium. With bitters before meals in frontal headache at the junction of hairy scalp and forehead, or pain in upper part of forehead without constipation. As wash to the mouth when headache depends on decayed teeth
Bleeding, 1
Bromides, 2
Bromide of Potassium, 3. In large doses
Bryonia. In bilious headache
Butyl-Chloral Hydrate, 1
Caffeine, 4
Caffeine Citrate, 1
Cajeput Oil. Locally
Camphor, 3. Internally, and saturated solution externally
Cannabis Indica. In neuralgic headache
Carbon Disulphide, 1
Chamomile
Chloroform, Spirits of. In nervous headache
Cimicifuga. In nervous and rheumatic headache, especially at menstrual period
Coffee and Morphine, 1
Cold Affusion, 3
Croton Oil
Digitalin, 2. $\frac{1}{60}$ of a grain twice a day for congestive hemicrania
Electricity, 1
Ergot, 2, 4
Ether Spray, 3. Locally, for frontal headache after illness or fatigue
Friedrichshall Water, 3
Galvanism, 2
Guarana
Heat. As hot water-bag or poultice to nape of neck
Hot Sponging, 3
Hot Water, 3
Hydrastis. In congestive headache with constipation
Ice-bag, 3
Ignatia. In hysterical headache
Iodide of Potassium, 1. In rheumatic headache, with tenderness of scalp
Iris. In supra-orbital headache, with nausea
Magnesium Sulphate, 4. For frontal headache, with constipation
Menthol. As local application
Mercury, 3. In bilious headache
Morphine, 1
Mustard, 3. As foot-bath, or poultice to nape of neck

Headache.

Nitrite of Amyl, 1, 2. As inhalation when face pale
Nitro-glycerin, 2
Nitro-Hydrochloric Acid. For pain just above eyeballs without constipation, also for pain at back of neck
Nux Vomica. Frequently repeated in nervous or bilious headache
Paraldehyde, 3
Phosphoric Acid, 1
Picrotoxine, 2. In periodical headache
Podophyllum, 3. When constipation
Potassium Cyanide, 2. As local application
Pulsatilla, 1
Quinine
Salicylate of Sodium. 3-gr. dose every half hour exceedingly useful
Sanguinaria. In gastric derangement
Sitz-bath, 3
Skull-cap as prophylactic
Sodium Chloride, 1
Sodium Phosphate, 2. As laxative in bilious headache
Spectacles. Where the headache depends on inequality of focal length or astigmatism
Strychnine, 1, 2
Tea, 3. Strong black or green, often relieves nervous headache quickly
Valerian. In nervous and hysterical cases
Veratrum Viride, 3
Zinc Oxide, 3

Heartburn.

Acids, 3
Alkalies, 3
Almonds. Six or eight blanched
Ammonia, 3
Antacids, 4
Bismuth, 3
Capsicum
Cod-Liver Oil, 1
Morphine, 3
Nux Vomica, 3. Very useful
Opium, 3
Podophyllum
Pulsatilla

Heart, Dilated.

Cocaine, 3
Digitalis, 1, 2, 3
Ergot, 2
Iron, 2
Morphine, 2, 3
Nitrite of Amyl, 2, 3
Nitrite of Sodium
Nitro-glycerin, 2

Heart, Fatty.

Arsenic, 1, 3
Belladonna
Cimicifuga
Cod-Liver Oil, 1, 3
Ergot
Iron
Nitrite of Amyl, 4
Strychnine, 3

Heart, Hypertrophied.

Aconite, 2, 3, 4. To be used with care when valvular disease is present
Bromides, 2
Camphor. In palpitation and dyspnœa
Cimicifuga, 2
Digitalis, 2, 3, 4. In small doses
Ergot, 2

Heart, Hypertrophied.

Galvanism, 1
Lead Acetate, 1. In palpitation
Nitrite of Amyl, 2, 3
Veratrum Viride, 2, 3

Heart, Palpitation of.

Aconite, 1, 2, 3. Internally
Amyl Nitrite
Belladonna, 1, 4. Internally useful in cardiac strain
Bromide of Potassium, 1, 2. In fluttering heart
Camphor
Cimicifuga, 2
Cocaine, 3
Digitalis, 2, 3
Eucalyptus
Hot Bath
Hyoscyamus. In nervous palpitation
Lead, 1
Milk Cure. In gouty persons
Posture, 1. Head hung forward, body bent, arms by the sides, and breath held for a few seconds
Potassium Iodide, 1
Senega
Valerian. In nervous cases with dyspnœa
Veratrine, 2, 3. As ointment to chest

Heart, Valvular Disease of.

Aconite, 3, 4. To quiet action. To be used with caution
Arsenic, 1, 3
Cimicifuga, 2
Comp. Sp. of Ether, 4
Digitalis, 1, 2, 3, 4. In mitral disease, to be avoided in purely aortic disease, but useful when this is complicated with mitral
Iron, 1
Morphine, 2, 3. To relieve pain and dyspnœa
Nitrites. To lessen vascular tension
Purgatives, 3. To lessen tension and remove fluid
Salicin, 1
Strychnine, 3. As cardiac tonic
Veratrum Viride, 4

Hectic.

Antipyrin
Calcium Phosphate
Calumba
Cold, 4
Digitalis, 1
Gelsemium
Ipecacuanha
Iron. Especially Mistura ferri composita
Prunus Virginiana, 4. To lessen cough
Salicin. To lessen perspiration
Salicylate of Sodium, 1
Strychnine. To lessen night sweats

Hemeralopia.

Amyl Nitrite, 1
Blisters. Small, to external canthus of the eye
Electricity
Mercury. Locally
Quinine. In large doses internally
Strychnine, 1

Hepatitis.

Aconite, 2
Alkaline Mineral Waters, 2
Ammonium Chloride, 1, 4

Hepatitis.

Bryonia
Chelidonium
Colchicum, 2
Iodine, 1. As enema
Leeches
Mercury, 4
Nitre and Antimony, 1
Nitro-Hydrochloric Acid, 2, 4
Rhubarb, 2
Sulphurous Waters, 2
Tartar Emetic. With opium

Hernia.

Chloral, 1. As enema
Chloroform, 1, 3
Ether and Belladonna, 1
Ether Spray, 1
Forced Enemata, 4
Oil, 1
Opium, 1

Herpes Zoster.

Aconite and Opium. Locally
Alcohol. Locally
Atropine, 2
Belladonna, 2
Calomel, 2
Carbolic Acid, 1
Celandine
Chloroform, 1
Collodion, 1
Copper Acetate, 2
Dulcamara
Ferri Perchlor., 1
Galvanism, 1, 2
Morphine, 3
Myrtol, 2
Phosphorus, 1
Rhus Toxicodendron
Silver Nitrate, 3. Strong solution locally
Spirits of Wine, 1
Tar, 1
Veratrine, 3. As ointment
Zinc Ointment, 2

Hiccough.

Amber, Oil of, 4
Apomorphine, 3
Belladonna, 4
Bismuth, 1
Camphor, 3
Cannabis Indica, 1
Chloral, 1, 4
Chloroform, 3
Ether, 4
Iodoform, 1
Jaborandi, 1
Laurel Water
Morphine, 1, 3. Hypodermically
Musk, 4
Mustard and Hot Water, 3
Nitro-glycerin, 3
Nux Vomica
Pepper
Potassium Bromide
Pressure over Phrenic, Hyoid, or Epigastrium, 1
Quinine. In full doses
Sugar and Vinegar, 1
Tobacco-smoking, 1

Hydrocephalus, Acute.

Blisters. To the nape of the neck useful
Bromide of Potassium
Croton Oil, 3. Liniment

Hydrocephalus, Acute.

Elaterium, 1
Ergot
Iodide of Potassium, 1, 4
Iodoform, 1, 4. Dissolved in collodion, or as ointment to neck and head; along with small doses of calomel, as enemata
Leeches
Mercuric Chloride. Small doses internally
Tartar Emetic. Ointment
Turpentine. By mouth or as enema, at commencement

Hydrocephalus, Chronic.

Blisters
Cod-Liver Oil
Iodide of Iron
Iodide of Potassium, 1
Iodine
Mercury
Potassium Bromide, 1

Hydrophobia.

Acid, Acetic and Hydrochloric, 1
Actual Cautery
Acupuncture. To wound immediately
Alisma, 1
Amyl Nitrite, 2
Arsenic, 1
Asparagus, 1
Atropine, 1
Belladonna
Bromide of Potassium, 1
Calabar Bean, 1
Cannabis Indica, 1
Carbolic Acid, 1
Chloral, 1
Chloride of Potassium, 4
Chloroform, 1, 2. To control spasms
Curare, 1, 2
Escharotics, 4
Ether, 2
Euphorbia, 1
Excision of Bitten Part, 1
Hoang-nan, 1
Hyoscyamine, 1
Iodine, 1
Jaborandi, 1
Mercury, 1
Morphine, 1, 2
Nitro-glycerin, 2
Permanganate of Potassium. As lotion to wound
Potassium Iodide, 1
Quinine
Sabadilla, 1
Silver Nitrate. To wound, no use, even though applied immediately
Stramonium, 1

Hydrothorax.

Blisters, 1
Broom
Digitalis. As diuretic
Dry Diet, 2
Elaterium
Iodine, 2. Injections after tapping
Jaborandi, 1
Mercury, 1
Morphine, 1
Pilocarpine, 1, 2, 3
Resin of Copaiba, 2
Sanguinaria
Tr. Ferri, 1
Veratrum Viride, 1

Hypochondriasis.

Alcohol, 4. As temporary stimulant
Arsenic, 2. In the aged
Asafœtida, 2
Bromide of Potassium, 3
Caffeine, 2
Cimicifuga. In puerperal, and spermatorrhœa
Colchicum, 2
Creasote
Electricity, 4
Gold Chloride, 2. When giddiness and cerebral anæmia
Hyoscyamus. In syphiliphobia
Ignatia
Musk, 1
Opium, 2. In small doses
Ox-Gall
Sumbul

Hysteria.

Aconite, 3
Actæa Racemosa, 3
Alcohol, 3
Aloes. In constipation
Ammonia, Aromatic Spirits of, 2
Amyl Nitrite, 1
Anæsthetics, 4
Antispasmodics, 4
Apomorphine, 1, 3
Arsenic
Asafœtida, 2, 3, 4
Atropine. In hysterical aphonia
Belladonna, 1
Bromide of Camphor, 1, 4
Bromide of Potassium, 3, 4
Bromide of Sodium, 4
Camphor, 2, 4. In hysterical excitement
Cannabis Indica, 3
Chloroform, 1, 3
Cimicifuga. In hysterical chorea
Cocaine, 2, 4
Cod-Liver Oil, 2, 3
Cold Water poured over mouth to cut short attack
Conium, 4
Electricity, 4. To cut short attack
Ether, 2, 4
Eucalyptus, 2
Faradism, 2
Galbanum. Internally, and as plaster to sacrum
Galvanism, 1
Garlic. To smell during the paroxysm
Hyoscyamus, 1
Ignatia
Ipecacuanha, 1. As emetic
Iron, 2, 3
Lupulin. When sleepless
Massage, 1, 2
Morphine, 3
Musk, 3, 4
Nux Vomica, 3
Oil of Amber, 4
Oil of Wormseed, 4
Opium, 1, 3. In small doses
Paraldehyde, 3
Pellitory. For Globus
Phosphates, 2
Phosphorus, 1, 3. In hysterical paralysis
Santonin. If worms present
Spiritus Etheris Nitrosi. To relieve spasm
Tartar Emetic
Valerian, 2, 4
Valerianate of Ammonium, 4
Valerianic Acid, 4
Volatile Oils, 3
Zinc Oxide, 1
Zinc Sulphate, 1
Zinc Valerianate, 3

Ichthyosis.

Baths, 3
Cod-Liver Oil, 1
Elm Bark Decoction. Useful
Glycerine, 1
Zinc Oxide

Impetigo.

Acetate of Lead, 2
Arsenic
Boric Acid, 1
Calcium Chloride
Chrysophanic Acid. Locally
Cod-Liver Oil, 1
Glycerine of Tannin, 2, 3
Grape Cure
Gutta-percha
Hydrocyanic Acid. To relieve itching
Laurel Water. To relieve itching
Mercury. Locally
Mineral Acids, 2
Nitric Acid, 1. Internally
Oil of Cade, 1
Oils, 3
Potassium Chloride, 1
Poultices, 3
Quinine, 2, 3
Sulphate of Copper, 3
Sulphur, 3. Internally
Tannin. Locally
Tar, 1
Zinc Ointment
Zinc Oxide, 2, 3

Impotence.

Arseniate of Iron, 2
Cannabis Indica, 2
Cantharides, 3
Cubebs
Ergotin, 2. Hypodermically about dorsal vein of penis, when it empties too rapidly
Gold Chloride, 2. To prevent decline of sexual power
Nux Vomica, 2. Very useful
Phosphoric Acid
Phosphorus, 2
Sanguinaria, 2
Serpentaria
Strychnine, 3
Turpentine, 4
Zinc Phosphate, 3. Very useful

Inflammation.

Aconite, 1, 2, 3. At the commencement of all inflammations, superficial or deep-seated; best given in small doses frequently repeated until pulse and temperature are reduced
Alcohol, 2. As antipyretic and stimulant, especially useful in blood-poisoning
Alkalies, 2
Ammonium Chloride, 1
Antimonium Tart., 1, 2, 4
Antimony, 3. 10–15 m. of vinum antimonii frequently repeated at commencement
Arnica, 2
Arsenic, 1
Atropine, 3
Barium Chloride, 2
Belladonna, 1, 2, 3. In gouty and rheumatic inflammation and cystitis
Blisters, 4
Borax, 4
Bryonia. In serous inflammations after heart or pulse lowered by aconite
Chloral. When temperature is high and much delirium
Cod-Liver Oil, 3. In chronic inflammations

Inflammation.

Cold, 4
Copaiba, 4
Digitalis, 2, 3
Electricity, 1
Ergot, 2
Fomentations, 3
Gelsemium, 2
Ice, 3. Locally applied
Iodine, 3. Locally
Lead, 4
Leeches, 2
Mercury, 1, 3, 4. In deep-seated inflammations, especially those of serous membranes and iritis, and syphilitic cases
Mercury Frictions, 1
Nitrates, 3
Opium, 1, 2, 3. Exceedingly useful to check it at commencement, and relieve pain afterwards
Phosphorus, 1
Pilocarpin, 2
Poultices, 3
Pulsatilla. In inflammation, when purulent discharge from eyes, ears, and nose; and in epididymitis
Purgatives
Quinine, 1, 2. In peritonitis and in acute inflammations along with morphine
Salicin
Salicylate of Sodium. Most useful, especially in rheumatic affections
Salicylic Acid. Most valuable
Saline Cathartics, 2
Stramonium, 4
Sulphides, 3. To abort or to hasten maturation
Veratrum Viride, 1, 2
Water, 2

Influenza.

Aconite, 1
Actæa Racemosa, 3
Ammonium Acetate, with Nitrous or Chloric Ether
Carbolic Acid. As spray and gargle
Cimicifuga
Cubebs, 3
Hot Sponging, 3
Opium. With Ipecacuanha, useful for cough
Potassium Nitrate. Freely diluted, as lemonade
Quinine. Useful, especially in later stages
Sanguinaria. Sometimes very useful
Spiritus Etheris Nitrosi
Sulphurous Acid, 3. By fumigation or inhalation
Turkish Baths. Useful

Insomnia.

Aconite, 1. 1 m. every quarter of an hour when skin dry and harsh
Alcohol, 2, 3. Sometimes very useful
Atropine. With opium, $\frac{1}{120}$–$\frac{1}{100}$ gr. atropine, to $\frac{1}{4}$ or $\frac{1}{2}$ gr. morphine
Belladonna, 2
Bleeding, 1
Butyl-Chloral, 1, 3. If heart weak
Camphor, 1
Cannabis Indica, 3. Alone or with hyoscyamus
Chloral, 1, 2, 3. Most useful, alone or with bromide of potassium: the addition of a small quantity of opium to the chloral and bromide assists their action
Chloroform
Codeine, 1, 3
Coffee. Causes insomnia, but has been recommended in insomnia from deficient nervous power, or chronic alcoholism
Cold Douche, 3

Insomnia.

Digitalis, 1. When deficient tone of vaso-motor system
Duboisine, 2
Ether, 3. In full dose
Galvanisation, 2
Gelsemium, 3. In simple wakefulness
Humulus, 2. A hop-pillow sometimes useful in the aged
Hyoscine, 2
Hyoscyamus, 2, 3, 4. Alone, or with cannabis indica, useful to combine with quinine
Hypnone
Ignatia. In nervous irritability
Morphine, 2, 3
Musk. In irritable and nervous cases
Opium, 1, 3, 4. Most powerful hypnotic, given alone or in combination
Paraldehyde, 2, 3
Phosphorus, 1, 2, 3. In the aged
Potassium Bromide, 1, 2, 3, 4. In full doses, alone or with other hypnotics
Removal Inland, 3
Sitz Bath, 3
Sodium Lactate, 1
Sumbul, 1. In nervous irritability and chronic alcoholism
Tannate of Cannabin, 3
Tartar Emetic, 3. Along with opium when there is a tendency to congestion of brain, which opium alone would increase
Urethane
Warm Bath, 3
Warmth. Internally and externally
Water, 2
Wet Compress
Wet Pack, 1

Intercostal Neuralgia

Is very commonly connected with
Leucorrhœa, *q. v.* (*Vide* also Neuralgia.)

Intermittent Fever

Aconite, 1
Alcohol, 1
Ammonium Carbazotate. ½–1 gr. in pill
Ammonium Chloride, 4
Apiol, 2, 4. In mild cases, 15 gr. during an hour, in divided doses four hours before the paroxysm
Arsenic, 3, 4. Exceedingly useful, especially in irregular malaria
Atropine, 1. Subcutaneously, to arrest or cut short cold stage
Berberine. In chronic cases
Bleeding, 1
Brucine
Camphor, 1. Taken before the fit to prevent it
Capsicum, 2. Along with quinine as adjuvant
Carbolic Acid, 1, 2
Chamomile, 3
Chinolin, 2
Chloral Hydrate, 1. As antipyretic when fever high; and to check vomiting or convulsions in adults and children during malarious fever
Chloroform, 1, 2, 4. To prevent or cut short cold stage
Cimicifuga. In brow ague
Cinchonidine, 2. Like Cinchonine
Cinchonine, 2. Useful and cheap
Coffee, 1
Cold Compress, 1
Cornus Florida. A substitute for quinine
Digitalis, 1
Elaterium, 1
Emetics, 3
Eucalyptus Globulus, 2, 3, 4. During convalescence

Intermittent Fever.

Ferric Sulphate
Ferrous Iodide
Gelsemium, 4. Pushed until it produces dilated pupils or double vision
Grindelia Squarrosa. In hypertrophied spleen
Hot Bath, 4
Hydrargyrum Sublimatum, 1
Hydrastis, 2. In obstinate cases
Hydroquinone, 2
Hyoscyamine, 1
Iodine Tincture. To prevent recurrence of ague
Ipecacuanha, 2, 4. Most useful as emetic
Kairin, 2
Leptandra Virginica. After disease is lessened by quinine
Morphine. Along with quinine as an adjuvant
Mustard to Soles of Feet, 1
Narcotin, 3. 2–5 gr. three times a day sometimes very useful
Nitric Acid, 2. In obstinate cases
Nitrite of Amyl, 2, 4. By inhalation to relieve or shorten cold stage
Nitrite of Sodium, 3
Nitro-glycerin, 2, 3
Nux Vomica, 2
Ol. Terebinthinæ, 1
Opium, 1. In full doses, to prevent chill
Pepper. Along with quinine
Phosphorus, 1
Pilocarpin, 2
Piperine, 4
Potassium Bromide, 1
Potassium Chloride, 1
Potassium Nitrate. 10 gr. in brandy and water, or dry on the tongue to prevent fit
Quassia, 3
Quinetum, 1
Quinine, 1, 3, 4. As prophylactic to abort fit and to prevent recurrence; its action is aided by purgatives, emetics, and aromatics
Quinine Bromohydrate. Like quinine, and less liable to produce cinchonism
Resorcin, 2
Saccharated Lime, 1
Salicin, 1, 2
Salicylic Acid, 1, 2, 3, 4
Sodium Chloride. Tablespoonful in glass of hot water at a draught on empty stomach
Sodium Hyposulphate, 3. In mild cases
Spider Web. As pill
Stramonium, 1
Strychnine

Intertrigo.

Bismuth, 2, 3. Locally.
Camphor, 3. Added to dusting powders to allay heat and itching
Carbolic Acid, 1
Carbonate of Calcium, 3, 4
Fullers' Earth
Glycerine of Tannin, 2, 3
Lead Lotion, 1
Lime Water, 3
Soap, 3
Tannin, 1
Zinc Ointment, 2

Iritis.

Acidum Hydrocyanicum, 1
Atropine, 2, 3, 4
Belladonna, 1, 3. Internally and locally
Bleeding, 1
Copaiba, 1
Duboisine, 2. Substitute for atropia
Eserine, 2
Homatropine, 2

Iritis.

Iodide of Potassium, 1
Mercury, 1, 2, 3, 4. Most serviceable
Morphine, 1, 3
Opium. To lessen pain
Pilocarpin, 2
Salicylic Acid, 1
Santonin, 1
Sodium Salicylate, 1
Turpentine, 1. In rheumatic iritis

Irritability.

Alkaline Waters
Bromide of Potassium
Chloral, 3
Colchicum. With potash in large quantity of water when gouty
Ignatia. In small doses
Laxatives. In constipation
Sitz-Bath, 3
Strychnine. In small doses

Jaundice.

Alkaline mineral waters in catarrh of duodenum or bile-ducts, 2
Aloes, 2
Ammonium Chloride, 2. In scruple doses in jaundice from mental emotion
Ammonium Iodide, 2. When catarrh of bile-ducts
Arsenic. In malarious cases
Benzoic Acid, 1
Calomel Purgative, 4. Followed by saline, often very useful
Carlsbad Salts. Very useful
Carlsbad Waters, 1
Celandine
Chloroform, 1
Colchicum
Dulcamara
Eggs, 1
Emetics, 4
Enemata, 4. Cold water, one or two litres once a day
Ether. When due to gall-stones
Euonymin, 1, 2, 3
Fel Bovinum, 1
Hydrastis. In cases of catarrh of ducts
Ipecacuanha, 1, 4
Iridin
Iris, 2
Lemon Juice, 4
Magnesia, 1
Magnesium Sulphate
Manganese, 2. In malarious or catarrhal cases
Mercurials, 2, 3
Mineral Acids, 1
Nitro-hydrochloric Acid, 2, 4. Internally, and as local application over liver, or as bath in catarrhal cases
Podophyllum, 2. In catarrhal conditions very useful
Potassium Chloride, 1
Potassium Salts, 4
Potassium Sulphate. As laxative
Quinine, 1. In malarious cases
Rhubarb, 2. Jaundice in children
Sanguinaria
Sodium Phosphate, 2, 3. Very useful in catarrh of bile-ducts
Stillingia. After ague
Turpentine, 1

Lactation, Defective.

Calabar Bean
Castor Oil Leaves
Jaborandi, 2

Lactation, Defective.

Mustard Poultice
Vanilla

Lactation, Excessive.

Alcohol, 3
Belladonna, 1, 2, 3. Internally and locally
Camphor and Glycerine, 1
Chloral, 1
Coffee, 1
Electricity, 1
Hempseed Oil, 1
Iodide of Potassium, 1
Mercury, 1
Parsley, 1
Quinine, 3
Ricinus Leaves, 1. As poultice
Tobacco, 3

Laryngismus Stridulus.

Aconite
Belladonna
Bromides. Very useful in large doses
Chloral Hydrate
Chloroform. As inhalation to stop spasm
Cod-Liver Oil, 3
Cold Sponging
Cold Water dashed in Face, 3
Coniine. Pushed until physiological action observed
Emetics
Ether, 2
Ipecacuanha. As emetic
Lancing Gums, 3
Lobelia, 3
Morphine. Hypodermically
Nitro-glycerin, 2
Potassium Bromide, 1, 3
Quinine
Spinal Ice-bag, 3
Sub-sulphate of Mercury, 2
Tartar Emetic, 2
Worms, Removal of, 3

Laryngitis, Acute.

Acetic Acid, 1. As inhalation
Aconite, 1, 2
Antimon. Pot. Tart., 1
Benzoin, 1. As inhalation
Gelsemium, 4
Glycerine, 4
Inhalations, 4
Iodine. As inhalation and counter-irritant over neck
Leeches. To larynx, or nape of neck
Mercury, 4
Morphine
Quinine, 1
Scarification of Larynx
Silver Nitrate, 1, 4. As spray
Sulphurous Acid. As inhalation or spray
Tracheotomy, 1
Veratrum Viride, 1
Zinc Chloride, 1
Zinc Sulphate. As emetic

Laryngitis, Chronic.

Alum. As garle
Ammonium Chloride. As spray
Bismuth. Locally by insufflation.
Carbolic Acid. As spray.
Ferric Chloride. As spray, or brushed on interior of larynx
Gelsemium, 4
Glycerine, 4
Guaiacum. As lozenges or mixture

Laryngitis, Chronic.

Inhalation, 4
Iodine. As counter-irritant
Mercury, 4
Morphine. Mixed with bismuth or starch as insufflation, most useful when much irritation, as in laryngeal phthisis
Silver Nitrate, 1, 4. As solution to interior of larynx
Sulphurous Acid. As fumigation, inhalation, or spray
Tannin. As gargle or spray
Uranium Nitrate. As spray

Leucorrhœa.

Acid Nitric and Cinchona, 1
Alkalies, 3
Aloes, 1
Alum, 2, 3. As injection
Ammonio-Ferric Alum, 4
Argenti Oxidum, 1
Arsenic, 1
Bael Fruit, 1
Balsam of Peru. Internally
Balsam of Tolu. Internally
Belladonna, 3. As pessary, for over-secretion and pain
Bismuth, 1, 2, 4. As injection or pessary
Borax. As injection
Boric Acid, 3
Carbolic Acid, 1, 2, 3. As injection
Cimicifuga
Cocculus Indicus
Cold Sponging, 3
Common Red Wine, 2
Copaiba
Copper Sulphate, 3. As injection
Creasote, 1
Ergot, 1, 3
Glycerine
Hydrastis, 2. Locally
Iodine, 4
Iodoform, 2. As local application, alone or mixed with tannic acid
Iodo-Tannin, 2
Iron, 3. Internally
Lead, 2, 3
Lime Water, 3
Monsel's Solution, 2
Myrrh. Internally
Phosphate of Calcium, 3. Internally
Potassium Bicarbonate, 3. Dilute solution as injection
Potassium Bromide, 1
Potassium Chloride, 1
Potassium, Permanganate of, 1, 4
Saffron, 1
Spinal Ice-Bag, 3
Sumbul
Tannin, 1, 2, 3, 4. As injection or suppository
Zinc Sulphate, 3

Lichen.

Alkalies, 3
Arsenic, 1, 3, 4
Cantharides, 3
Chloroform, 3
Cod-Liver Oil, 1
Glycerole of Aloes, 1
Mercury, 3. Locally
Potassium Cyanide, 3
Silver Nitrate, 3. Solution locally
Sulphides, 3
Sulphur, 1
Tar Ointment
Thymol, 1
Warm Baths, 3

Locomotor Ataxy.

Amyl Nitrite, 1
Argentic Phosphate, 1
Belladonna
Calabar Bean, 3
Cannabis Indica
Chloride of Gold, 2
Damiana, 1
Electricity, 1, 2
Ergot
Hyoscyamus, 2
Morphine, 1
Nitro-Hydrochloric Acid
Phosphorus, 2
Physostigma, 1
Potassium Iodide, 1. For syphilitic taint
Silver Nitrate, 1, 2, 4
Sodium Salicylate, 1
Strychnine, 1

Lumbago.

Aconite. Small doses internally, and liniment locally
Actæa Racemosa, 1, 3
Acupuncture, 2, 3
Aquapuncture, 2. Sometimes very useful
Atropine, 1
Belladonna, 3
Capsicum, 3. Locally
Carbolic Acid, 1. Hypodermically
Cautery
Chloroform, 2. Liniment
Cimicifuga, 2. Sometimes very useful internally
Cod-Liver Oil, 4
Electricity, 1
Emplastra, 2
Ether Spray, 1, 3
Eucalyptus Oil, 1. As liniment
Faradization, 3
Galvanism, 2
Guaco, 1
Guarana. In large doses
Hot Douche, 2. Or hot poultice
Hot Flat Iron, 3
Ice, rubbed over back, 1, 3
Iodide of Potassium, 3, 4
Iodides, 2
Lead Plaster, 3
Massage, 2
Morphine, 1, 2, 3. Hypodermically
Nitrate of Potassium, 3
Pitch Plaster, 3
Poultices, 3
Quinine, 1
Rhus Toxicodendron
Salicylic Acid, 2
Sulphur, 4
Thermic Hammer, 3
Turkish Bath, 3
Turpentine, 3. Internally and locally
Veratrum Viride, 3

Lupus.

Arsenic
Blisters, 3
Carbolic Acid
Cautery
Chaulmugra Oil
Chromic Acid
Cod-Liver Oil, 1, 2
Creasote
Galvano-Cautery, 2
Hydrargyri Biniodidum, 1
Hydrargyri Nitratis Acidum, 1
Iodide of Potassium
Iodide of Starch
Iodide of Sulphur. Externally
Iodine. In glycerine

Lupus.

Iodoform
Lead Lotion
Mercury. Internally and locally
Phosphorus
Plumbic Nitrate, 1
Potassium Chlorate, 2
Pyrogallic Acid
Salicylate of Sodium
Salicylic Acid, 1
Silver Nitrate
Sodium Acetate
Sodium Ethylate
Zinc Chloride
Zinc Sulphate, 2

Mania.

Actæa Racemosa, 3
Alcohol, 1
Anæsthetics, 2
Atropine, 2
Belladonna. Useful
Blisters, 4
Bromide of Potassium, 3,
Bromides, 2
Camphor
Cannabis Indica, 1, 3
Chloral Hydrate, 1, 2, 3, 4. As narcotic and carminative
Chloral and Camphor, 4
Cold Douche, 3
Coniine, 1, 2, 2, 4. Alone, or with morphine
Croton Oil, 3, 4. As purgative
Daturine
Digitalis, 1, 2. In acute and chronic mania, especially when complicated with general paralysis and epilepsy
Duboisine, 2. As calmative
Ergot, 2. In recurrent mania
Ether. In maniacal paroxysms
Galvanism, to head and cervical sympathetic
Gamboge, 4
Gelsemium, 1, 2, 3, 4. With much motor excitement and wakefulness
Hyoscyamine, 2
Hyoscyamus, 1, 2, 3. In hallucinations and hypochondriasis
Iron, 2
Morphine, 2, 3
Opium, 3. Alone or with tartar emetic
Paraldehyde, 2, 3
Physostigma, 2
Stramonium
Veratrum Viride, 2
Wet Pack, 1, 2

Mastitis.

Aconite, 1
Ammonium Chloride, 1. As lotion, locally
Arnica, 1
Belladonna, 1, 2, 4. Locally as liniment or ointment
Calcium Sulphide. Internally, if abscess is forming
Chloral Poultice, 1
Conium, 1
Digitalis Infusion. Locally as fomentation
Friction, with oil
Galvanism, 1
Hyoscyamus. As plaster to relieve painful distension from milk
Ice, 1
Iodine, 1
Jaborandi, 1, 2
Mercury and Morphine Oleate, 1. Locally, in mammary abscess
Phytolacca, 1, 2. To arrest inflammation, local application
Plaster, 1. To support and compress mammæ

Mastitis.

Potassium Bromide, 1
Stramonium. Fresh leaves as poultice
Tartar Emetic. In small doses frequently repeated at commencement
Tobacco Leaves. As poultice

Measles.

Aconite, 3
Ammonium Acetate
Ammonium Carbonate, 1, 3
Antimony
Camphor
Carbolic Acid. Internally, at commencement
Cold Affusion, 3
Digitalis, 1
Fat, 3
Iodine, 3
Ipecacuanha
Mustard Bath, 3. When retrocession of rash
Packing, 3
Potassium Bromide. When sleeplessness
Potassium Chlorate. In adynamic cases
Pulsatilla
Purgatives, 3
Quinine
Veratrum Viride, 3
Zinc Sulphate, 1

Melancholia.

Alcohol, 4
Arsenic, 2. In aged persons, along with opium
Belladonna, 1
Bromide of Potassium, 1, 3. Often very useful
Bromides, 2
Caffeine, 2
Camphor, 3
Cannabis Indica, 2
Chloral Hydrate, 1. As hypnotic
Cimicifuga. In puerperal or uterine despondency
Cocaine, 4
Colchicum, 2
Colocynth, 2
Galvanism
Gold, 2
Ignatia
Iron
Morphine, 1, 3
Musk, 3
Nitrous Oxide, 1
Opium, 2. In small doses especially useful
Phosphorus, 3
Turkish Bath, 1
Valerian. In hysterical and suicidal cases

Menière's Disease.

Gelsemium, 3
Quinine, 1

Meningitis, Cerebral.

Aconite
Ammonium Carbonate, 2
Belladonna
Blisters. To nape of neck
Bromide of Potassium, 1, 3. In convulsions consequent on meningitis
Bryonia. When effusion
Cold, 4. To head
Cold Baths, 2
Digitalis, 2
Ergot, 2
Gelsemium, 2
Hyoscyamus
Iodide of Potassium, 1
Mercury. As ointment, or internally

Meningitis, Cerebral.

Opium, 2. In small doses, alone or with tartar emetic
Pilocarpine, 2
Pulsatilla, 2. In acute cases
Purgatives. At commencement; calomel and jalap most useful
Quinine, 2
Turpentine, 2
Venesection. When much excitement

Meningitis, Cerebro-Spinal.

Aconite, 1, 2. Along with opium
Antimony, 3. Alone, or with opium
Atropine, 1
Belladonna, 1
Bromide of Potassium, 1, 3
Cautery, 1. Freely to back
Cold, to spine, 4
Cold Baths, 2
Digitalis. In early stage
Ergot, 2. Useful
Gelsemium, 2. Useful
Opium, 2. Very useful in large doses
Quinine, 2. At commencement, large doses
Turpentine. As enema
Venesection

Menorrhagia.

Actæa Racemosa, 3
Aloes, 2, 4. As adjuvant to iron
Ammonium Acetate, 4
Ammonium Chloride, 3. For headaches
Argentic Oxide, 1
Arsenic, 1. With iron
Berberine, 1
Bromide of Potassium, 1, 2, 3
Calcium Phosphate, 3. In anæmia
Cannabis Indica, 2, 3. Sometimes very useful
Cimicifuga
Cinnamon, Oil of, 1, 3
Coniine, 1
Creasote, 1
Digitalis, 1, 2, 3. Sometimes useful
Ergot, 1, 2, 3, 4. Most useful
Ferri Perchloridum, 1
Gallic Acid, 1, 2, 3. Very useful
Guaiacum, 1
Hamamelis, 3. Useful
Hot Water Bag to dorsal and lumbar vertebræ, 1, 3
Hydrargyri Perchloridum, 1
Hydrastis, 1
Ice, 1. To spine
Iodine, 1
Iodoform, 1
Ipecacuanha, 2. In emetic doses in evening, followed by acidulated draught in morning
Iron
Lemons, 3
Magnesium Sulphate. Sometimes useful
Phosphates, 4
Potassium Chlorate, 1
Pyrogallic Acid, 1
Quinine, 1, 3
Rue, 4
Savine, 3, 4
Senega
Sulphuric Acid, 1. When due to fibroid or polypus
Tannin, 1, 3
Urtica Urens, 1
Vinca Major, 1

Mentagra.

Arsenic
Canada Balsam, 1
Carbolic Acid, 1

Mentagra.

Cod-Liver Oil,
Copper. Locally, as lotion
Epilation, 1
Goa Powder, 1
Iodide of Sulphur, 1
Mercury
Oil of Turpentine, 1
Oleate, Bichloride, or Nitrate of Mercury. As ointment or lotion
Petroleum
Silver Nitrate, 2
Sulphurous Acid. With glycerine
Tr. Iodine (compound)
Zinc and Copper Sulphate
Zinc Chloride

Metritis, Acute.

Aconite
Aloes, 1. Enema
Aurum, 2
Carbolic Acid, 2
Ergotin, 2, 4
Hydrargyri Bichloridum, 1
Iodine, 2
Iodoform, 2
Nitrate of Silver, 2
Nitric Acid, 2
Opium. As suppository or enema
Potassa Fusa, 2
Poultices
Saline Laxatives, 2
Saline Mineral Waters, 2
Turpentine Stupes

Milk Deficiency.

Gossypium. Decoction or seeds, two or three times every hour
Ricinus. Poultices or infusion of leaves to the mammæ

Muscæ Volitantes.

Blue Pill. In biliousness
Iodide of Potassium
Iron. Perchloride in anæmia and climacteric
Valerian

Myalgia.

Acupuncture, 1, 2
Aquapuncture, 2
Ammonium Chloride, 1, 2, 3
Arnica. Internally and locally
Belladonna Liniment, 1, 3. Locally
Belladonna Plaster
Chloroform Liniment, 1. With friction
Cimicifuga, 2
Electricity, 1
Ether, 3
Friction
Gelsemium. Large doses
Iodide of Potassium. In rheumatic cases
Iodides, 2
Iodine
Massage, 2
Opium
Packing
Poultices, 3
Salicylate of Sodium
Salicylates, 2
Veratrine. Externally
Xanthoxylum. Internally and externally

Myelitis.

Barium Chloride, 2
Belladonna

Myelitis.

Electricity, 1, 4. In chronic cases
Ergot, 1, 2
Galvanism, 2
Hydrotherapy, 2
Iodides, 2
Iodide of Potassium, 1
Massage, 2
Mercury, 2
Phosphorus, 4. In paraplegia from excessive venery
Picrotoxin, 2
Silver Nitrate, 4. Useful
Strychnine, 1, 2

Nævus.

Antimonium Tartaratum, 1
Carbolic Acid, 1
Chloral, 1
Chromic Acid, 2
Collodion, 1, 2
Creasote, 1
Croton Oil, 1
Electrolysis, 1
Ferric Chloride, 1
Galvano-Cautery, 2
Hydrargyri Bichloridum, 1
Liquor Plumbi, 1
Nitrate of Mercury (Acid), 1
Nitric Acid, 1, 2
Potassium Nitrate, 1
Sodium Ethylate, 1
Tannin, 1
Vaccination, 1
Zinc Chloride, 3

Nails, Ingrowing.

Alum, 1
Ferri Perchloridum, 1
Ferri Persulphas, 1
Glycerine
Iodoform, 1
Lead Carbonate. Locally
Liquor Potassæ
Plumbi Nitras, 1
Silver Nitrate
Tannin, 1

Nausea.

Aconite, 1
Ammonio-Citrate of Iron, 1
Belladonna, 1
Bismuth, 1
Calomel, 1
Calumba, 1
Carbolic Acid, 1
Cerium Oxalate, 1
Chloral, 1
Cinnamon
Cloves
Cocculus Indicus. In violent retching without vomiting
Coffee, 1
Creasote, 1
Electricity, 1
Hydrocyanic Acid, 1
Ice
Ingluvin, 1
Iodine, 1
Ipecacuanha. In sickness of pregnancy and chronic alcoholism; very small dose, 1 ♏ of wine
Koumiss, 1
Lead Acetate, 1
Leeches, 1
Liquor Potassæ, 1
Morphine
Nutmeg

Nausea.

Pepper
Peppermint
Pepsin, 1
Pimento
Pulsatilla. In gastric catarrh
Salicin
Spt. Nucis Juglandis, 1
Strychnine, 1
Sulphuric Acid, 1

Nephritis Acute. *vide* Bright's Disease.

Aconite, 1, 3. At commencement
Alkalies, 3
Aqua Calcis, 1
Arsenic, 1
Belladonna, 1, 4
Bromide of Potassium, 3
Camphor, 1
Cannabis Indica, 3. As diuretic, especially in hæmaturia
Cantharides, 3. 1 ♏ of tincture every three hours to stop hæmaturia after acute symptoms have subsided
Cod-Liver Oil, 3
Copaiba, 3
Croton Liniment, 1
Cytisus Scoparius, 1
Digitalis, 3. As diuretic
Elaterium, 1, 3
Eucalyptus. Given cautiously
Fuchsin, 1
Gallic Acid, 1
Glonoine, 1
Hyoscyamus
Incisions, 3
Iron, 3
Jaborandi, 1, 3, 4
Juniper
Lead, 3
Liquor Ammonii Acetatis, 1
Liq. Potassæ, 1
Pilocarpin, 1
Potassium Bitartrate, 3, 4
Potassium Iodide, 1, 3
Potassium Sulphate, 1
Poultices. Over loins, very useful
Senega, 3
Tannin, 1, 3
Tartrate, 3
Tincture Ferri Perchloridi, 1
Turkish Baths, 3
Turpentine. 1 ♏ doses, every two to four hours
Warm Baths, 3

Nervousness.

Aconite. 1 ♏ of tincture at bed-time for restlessness and fidgets
Ammonium Chloride, 1
Argenti Phosphas, 1
Bromide of Potassium, 3, 4. Over-work and worry
Caffeine, 4. Where much debility
Camphor, 4
Chamomile
Chloral Hydrate, 1, 3
Chloroform, 3
Cod-Liver Oil
Cold Sponging, 3
Electricity, 1
Ergot, 1
Ether, 4
Hops. Internally, and as pillow
Hydrargyri Perchloridum, 1
Ignatia
Massage, 1

Nervousness.

Musk. In uterine derangement
Opium, 1
Phosphorus, 1
Strychnine, 1
Sumbul. In pregnancy, and after acute illness
Zinc Phosphate, 1

Neuralgia.

Aconite, 2
Aconitine, 1, 2, 3, 4 As ointment
Acupuncture, 1, 3
Alcohol, 2, 3, 4
Ammonium Chloride, 1, 3, 4. ½ dr. doses
Ammonium Valerianate, 1, 4
Amyl Nitrite, 1, 2, 3
Anæsthetics, 2
Antiseptic Oils, 2
Aquapuncture, 2
Arsenic, 1, 2, 3, 4
Atropine, 1, 3. As liniment, or hypodermically near the nerve
Auro-Terchlor. Iod., 1
Belladonna, 1, 2, 3, 4
Bebeeru Bark
Blisters, 1, 4
Bromide of Potassium, 1, 3, 4
Bromides, 2
Butyl-Chloral, 2, 3, 4. For neuralgia of fifth nerve
Caffeine
Cannabis Indica, 1, 3, 4
Capsicum, 3. Locally
Carbonic Acid. 3. Locally for uterine neuralgia
Cautery, 1
Chamomile, 3
Chaulmoogra Oil, 1
Chelidonium
Chloral and Camphor, 2, 3, 4. Equal parts locally applied
Chloral and Morphine, 1
Chlorate of Potassium, 3. In facial neuralgia
Chloroform, 1, 2, 3, 4. Locally, and by inhalation, when pain very severe
Cimicifuga, 2. In neuralgia of fifth nerve, and ovarian neuralgia
Cocaine, 3
Codeine, 1
Cod-Liver Oil, 2, 4
Colchicum, 1
Conium, 1, 3, 4
Counter-irritation, 3
Creasote, 1
Cupri-Ammonii-Sulphas, 1, 2
Digitalis, 1
Dogwood, Jamaica, 1
Electricity, 1, 4
Epispastics, 4
Ergot, 3, 4. In visceral neuralgia
Ether, 1, 3, 4
Ferric Perchloride, 1
Ferro-Manganates, 1
Galvanism, 2
Gelsemium, 2, 3, 4
Glonoine, 1
Hydrocyanic Acid, 3
Hyoscyamus, 3
Ignatia. In hysterical cases and in intercostal neuralgia
Iodides, 1. Especially when nocturnal
Iodide of Potassium, 4
Iodoform, 1, 3, 4
Iron, 2, 3
Massage, 2
Menthol, 1
Morphine, 1, 2, 3. Hypodermically
Mustard Poultice
Narceine, 1
Nickel, 1

Neuralgia.

Nitro-glycerin, 2, 4
Nux Vomica. In visceral neuralgia
Oil of Cloves. Locally
Opium, 3
Peppermint, 3. Locally
Phosphorus, 1, 2, 3, 4
Potassium Bichromate, 1
Pulsatilla
Pyrethrum. As masticatory
Quinine, 3, 4. In periodical cases
Quinine Salicylate, 1
Salicin, 1
Salicylic Acid
Sodium Salicylate, 1, 3
Spinal Ice-bag, 3
Stavesacre
Stramonium, 1, 3
Strychnine, 1, 2
Sumbul. Sometimes very useful
Thermo-cautery
Tonga, 1
Turkish Bath, 1
Turpentine, 1, 2
Valerian
Valerianated Zinc, 3
Valerianic Acid, 4
Veratrine, 2, 3, 4
Vibration
Wet Pack, 2

Neuralgic Pains.

Cold Sponging
Friction. Along back or on limbs
Rubefacients. Useful
Valerian
Warm Sponging

Nightmare.

Bromide of Potassium, 3
Camphor Water

Nipples, Sore.

Alcohol. Locally
Arnica, 3
Balsam of Peru
Balsam of Tolu
Benzoin, 1
Borax. Saturated solution locally
Brandy and Water, 3
Carbolic Acid, 1
Catechu, 1
Chloral Poultice, 1
Collodion, 1, 3
Ferrous Subsulphate. Locally
India Rubber, 1
Lead Nitrate, 1
Lead Salts
Lime Water, 3
Potassium Chlorate, 1
Rhatany, 1. 1 part extract to 15 of cacao butter
Shield, 1
Silver Nitrate
Sulphurous Acid, 3
Tannic Acid, 4
Tannin, Glycerine of, 1
Zinc Shield, 3

Nodes.

Mercury Oleate, 3. With morphine, locally
Potassium Iodide, 3. Internally and externally
Stramonium Leaves. As poultice

Nyctalopia.

Amyl Nitrite, 1
Blisters. Small to external canthus
Quinine
Strychnine, 1

Nymphomania.

Anaphrodisiacs, 1
Bromide of Potassium, 1, 2, 3, 4. In large doses
Camphor, 2, 3. In large doses
Camphor Monobromate, 2
Digitalis, 1
Lupuline
Opium, 1
Stramonium, 1
Sulphur. When due to hæmorrhoids
Sulphuric Acid. Internally
Tobacco, 2. So as to cause nausea, effectual but depressing

Obesity.

Alkalies, 2, 3
Alkaline Waters, 2. Especially those of Marienbad, 2
Ammonium Bromide, 1, 2
Banting's System—living on meat and green vegetables, and avoiding starch, sugars, and fats, 1, 2
Fucus Vesiculosus, 1
Liq. Potassæ, 1
Potassium Permanganate, 2
Salines, 1
Sodium Chloride, 1
Sulphurous Waters
Vegetable Acids, 2
Vinegar, 3. Very injurious

Onychia.

Alum, 1
Aluminium Sulphate, 1
Arsenic, 1
Carbolic Acid. As local anæsthetic
Chloral, 2. Locally
Corrosive Sublimate, 4
Ferri Perchloridum, 1
Ferri Persulphas, 1
Iodoform, 1, 2. Locally
Lead Nitrate, 1, 2, 3, 4
Mercury, 3. As ointment, alternately with poultices
Silver Nitrate, 1. At commencement
Tannin, 1
Tar Ointment
Tartar Emetic

Ophthalmia, *vide* Conjunctivitis.

Orchitis, *vide* Epididymitis.

Otitis, *vide* Earache.

Otorrhœa.

Aconite, 3
Alcohol
Alum, 1, 3. Insufflation
Arsenic, 1
Boric Acid, 1
Cadmium, 2. Locally
Carbolic Acid, 1
Caustic, 1

Otorrhœa.

Chloral, 1
Cod-Liver Oil, 3
Cotton Wool, 1
Iodide. 2 grs. to an ounce locally
Iodoform, 1
Lead Acetate, 3
Lead Lotions, 2
Lime Water, 3
Liquor Sodæ. Locally, when discharge is fetid
Mercury, Brown Citrine Ointment, 2
Permanganate of Potassium, 4. As injection or spray
Quinine
Silver Nitrate, 2. Locally
Spt. Vini Rect., 1
Sulpho-Carbolates, 2
Tannin, Glycerine of, 2, 3. Very useful
Zinc Sulphate, 2

Ovaritis and Neuralgia.

Gold

Oxaluria.

Mineral Acids, 3
Nitric Acid, 2
Nitro-Hydrochloric Acid, 2

Ozæna.

Acetate of Ammonium, 3
Acid, Sulphurous, 1
Alum, 3. As powder or wash
Bichromate of Potassium, 2
Bismuth, 3
Boro-glyceride, 3
Bromine, 2. As inhalation
Calcium Chloride, 1
Calomel Snuff, 1
Carbolate of Iodine, 2
Carbolic Acid, 2, 3
Chlorinated Lime. Injections of the solutions of
Ethyl Iodide, 2
Glycerine and Iodine, 1
Gold Salts
Hydrastis. Internally and locally
Insufflation, 2
Iodine, 2, 3, 4. As inhalation. Much benefit derived from washing out the nose with a solution of common salt, to which a few drops of the tincture of iodine have been added
Iodoform, 1, 2
Iron, 3
Medicated Cotton, 1
Mercuric Oxide, or Ammoniated Mercury, 3
Potassium Chlorate, 1
Potassium Iodide, 1
Potassium Permanganate, 4
Sodium Arseniate, 1
Sodium Chloride, 1
Sodium Ethylate, 1
Spray, 1
Tannin, Glycerine of, 3
Tinct. Thujæ, 1

Parotitis.

Aconite
Emetics, 1
Jaborandi, 1
Mercury. ½ gr. of grey powder three or four times a day
Poultice

PEDICULI.

ANISE
BAKE CLOTHES to destroy ova
CHLOROFORM, 1
COCCULUS INDICUS
DALMATIAN FLOWERS, 1
ESSENTIAL OILS, 3
LAUREL LEAVES, DECOCT. 1
MERCURY, 3. As ointment or wash
PETROLEUM, 1
PYRETHRUM, 1
QUASSIA, 1
STAVESACRE, 3

PEMPHIGUS.

ARSENIC, 1, 2, 3, 4
BELLADONNA, 2
CHLORATE OF POTASSIUM, 1
COD-LIVER OIL
HOT BATH, 1
IODIDE OF POTASSIUM, 1
MERCURY
PHOSPHORUS, 1
SILVER NITRATE
SULPHIDES, 1
TAR, 1

PERICARDITIS.

ACONITE, 3
ALCOHOL, 3. Sometimes very useful
BLEEDING, 1
BLISTERS, 1, 3. Near heart very useful
BRYONIA. Useful in exudation
CALOMEL AND OPIUM. Formerly much used
DIGITALIS, 1, 3. When heart is rapid and feeble with cyanosis and dropsy
IODIDE OF POTASSIUM, 4
IODINE, 1
IODOFORM, 4
MERCURY, 1, 4
OPIUM, 1. In grain doses every three to six hours, very useful
POULTICE, 3
QUININE, 1
VERATRUM VIRIDE, 3

PERIOSTITIS.

IODIDE OF POTASSIUM, OR AMMONIUM, 3
IODINE. Locally
MERCURY, 1. Internally
MERCURY AND MORPHINE OLEATE, 3. Externally
MEZEREON. In rheumatic and scrofulous cases
PHOSPHATES, 4
POULTICES
STAVESACRE. When long bones affected

PERITONITIS.

ACONITE, 2, 4. At commencement
AMMONIA, 1
ANTIMONY, 3
BLISTERS, 4
BRYONIA. When exudation
CHLORAL, 2
CHLORINE SOLUTION, 3
COCCULUS INDICUS. For tympanites
COLD, 4
ICE, 1
IODINE, 1
IPECACUANHA, 4
LEECHES, 2
MERCURY, 1, 4. When there is a tendency to fibrous exudation
OPIUM, 1, 2, 3, 4. Freely, most useful
PLUMBIC ACETATE, 1
POTASSIUM SALTS, 2
POULTICES, 2, 3, 4

PERITONITIS.

QUININE, 1, 2
RUBEFACIENTS, 2
STEAM, 2. Applied to the abdomen under a cloth when poultices cannot be borne
TURPENTINE, 2. For tympanites
VERATRUM VIRIDE, 4

PERSPIRATION.

AGARIC. In phthisis
AROMATIC SULPHURIC ACID, 2. In phthisis
ATROPINE, 2, 3. In sweating of phthisis, internally
BELLADONNA, 3. As liniment for local sweats
BETULA, 1
CARBOLIC ACID. With glycerine locally for fetid sweat
ERGOT, 3
GALLIC ACID, 2, 3. In phthisis
GLYCERINE, 1
IODOFORM, 3
JABORANDI, 1
LEAD, 2
MUSCARINE, 2
NEAT'S FOOT OIL rubbed over the surface
OILS, 3
OPIUM, 3. As Dover's powder in phthisis
PERMANGANATE OF POTASSIUM, 2. Locally for fetid perspiration
PICROTOXIN, 2, 3
PILOCARPINE, 3
QUININE, 3
SALICIN. In phthisis
SALICYLIC ACID, 2. With borax in fetid perspiration
SPINAL ICE-BAG, 3
SPONGING, 3. Very hot
STRYCHNINE. In phthisis
TANNIN, 3
VINEGAR. Locally
ZINC OXIDE, 2, 3. In phthisis

PERTUSSIS.

ACONITE, 1
ALUM, 1
AMMONIUM CHLORIDE, 1
AMYL NITRITE, 1
ARGENTI OXIDUM, 1
ARNICA, 1
ARSENIC, 1
ATROPINE, 1
BELLADONNA, 1
BENZIN, 1
BLISTER, 1. To nape of neck
BROMIDE OF AMMONIUM, 1
BROMIDE OF POTASSIUM, 1
BUTYL-CHLORAL, 1
CANTHARIDES, 1
CARBOLIC ACID, 1. As spray
CASTANEA VESCA, 1
CERIUM OXALATE, 1
CHEKEN, 1
CHLORAL, 1. In spasmodic stage
CHLOROFORM, 1. As inhalation during paroxysm
CLOVER TEA, 1
COCHINEAL, 1
COD-LIVER OIL, 1
COFFEE, 1
DECOCTION OF CHESTNUT LEAVES, *ad lib.* Sometimes useful
DROSERA, 1
ERGOT, 1
ETHER SPRAY, 1
GAS LIME, 1. Exhalation
GELSEMIUM, 1. In spasmodic stage
HYDROBROMIC ACID, 1
HYDROCYANIC ACID, 1. In habitual cough when the true whooping cough has ceased
HYDROGEN, PEROXIDE OF, 1

Pertussis.

Inhalation of Atomised Fluids, 1
Ipecacuanha, 1. Sometimes very useful alone, or combined with bromide of ammonium
Leeches, 1. To nape of neck
Lobelia, 1. In spasmodic stage
Milk Diet, 1
Monobromate of Camphor
Morphine, 1
Nitric Acid, 1
Opium. In convulsive conditions
Potassa Sulphurata, 1
Quinine, 1
Salicylic Acid, 1. As spray
Silver Nitrate
Sodium Carbolatum, 1
Sodium Salicylate, 1
Tannin, 1
Tar, 1. For inhalation
Tartar Emetic
Terebinthinæ Oleum, 1
Urtica, 1
Vaccination, 1
Valerian
Valerianate of Atropine, 1
Wild Thyme, 1
Zinc Sulphate, 1

Pharyngitis.

Aconite, 1, 2, 3
Acid, Sulphurous, 1, 3
Actæa Racemosa, 3
Alcohol, 3. Dilute as gargle
Alum, 2, 3. As gargle
Ammonii Acetatis, Liq., 1
Belladonna, 1, 2, 3
Capsicum, 3. As gargle
Cimicifuga. Internally when pharynx dry
Copper Sulphate. Locally
Cubebs Powder, 2. Locally applied
Electric Cautery, 1
Ferric Chloride. Locally as astringent, internally as tonic
Glycerine, 3. Locally, alone or as glycerine and tannin
Guaiacum, 1
Hydrastis, 2. Internally and locally
Ice, 1, 3
Iodine, 1, 3
Iodoform, 2
Ipecacuanha, 3. As spray
Nitric Acid, 1, 3
Pomegranate Bark. As gargle
Potassium Chlorate, 1. Locally
Quinine. As tonic
Silver Nitrate, 2, 3. In solution locally
Sodium Borate, 1
Strychnine. As tonic
Tannin, 2, 3. As powder or glycerine locally
Zinc Sulphate, 1, 3. As gargle

Phimosis.

Belladonna. Locally
Elastic Ligament, 1
Lupulin. After operation
Warm Baths, 1

Phlebitis.

Blisters, 3
Hamamelis
Hot Fomentations
Opium. To allay pain
Rest, absolute

Phlegmasia Alba Dolens.

Ammonium Carbonate. In full doses when much prostration

Phlegmasia Alba Dolens.

Belladonna Extract. With mercurial ointment locally
Blisters. In early stage
Creasote. As enemata
Hamamelis
Hydrochloric Acid. With potassium chlorate, in barley water
Leeches. During active inflammation
Opium. Internally and locally to allay pain

Photophobia.

Ammonium Chloride, 1
Atropine, 1, 3
Belladonna, 3. To eye
Bromide of Potassium, 1
Butyl-Chloral, 1
Calabar Bean, 1
Chloroform Vapour, 1, 3
Cold, 1
Coniine. In scrofulous photophobia locally
Galvanism, 1
Iodine Tr., 1
Mercuric Chloride. By insufflation
Nitrate of Silver, 1
Opium, 1, 3
Potassium Chlorate, 1. In large doses
Seton, 1
Tonga, 1

Phthisis.

Actæa Racemosa, 3
Alcohol. Along with food or cod-liver oil
Ammonium Carbonate, 1
Ammonium Chloride, 1
Ammonium Urate, 1
Antimonium Tartaratum, 1
Antipyrin. To reduce temperature
Arsenic. To remove commencing consolidation, and also when tongue is red and irritable
Atropine. To check perspiration
Belladonna. Locally for pain in muscles
Benzoic Acid, 3
Benzoin. As inhalation to lessen cough and expectoration
Blisters
Bromides, 2
Butyl-Chloral, 3. To check cough
Calcium Chloride, 1, 2, 3
Camphor, 1
Cannabis Indica, 4
Carbo Ligni, 1
Carbolic Acid, 1, 2
Chaulmoogra Oil, 1
Chloral, 3. As hypnotic
Chlorine, 1
Chlorodyne, 1
Chloroform, 3. As linctus to check cough
Cocaine, 2. A solution locally to throat and mouth tends to relieve irritable condition and aphthæ, especially in later stages
Cod-Liver Oil, 2, 3, 4. Most useful as nutrient
Conium, 1, 4
Coto Bark, 3
Counter-irritation, 3
Creasote, 1, 2, 3. As inhalation
Croton Oil, 3. To chest as counter-irritant
Digitalis, 1
Enemata, 3. Of starch and opium to control diarrhœa
Ether, 1
Eucalyptus Ol., 1, 4
Ferri Iodidum, 1
Ferri Sulphas, 1
Fluoric Acid, 1
Gallic Acid, 4
Gelsemium, 3
Glycerine, 3. As nutrient in place of cod-liver oil, locally to mouth in the last stages to relieve dryness and pain

Phthisis.

Guaiacum, 1
Hypophosphites, 1, 2, 3. Very useful in early stage
Inulin. Possibly useful
Iodine Liniment, 1, 3, 4. As a counter-irritant to remove consolidation in early stage, and to remove pain and cough later; as inhalation to lessen cough and expectoration
Iodoform, 3. As inhalation
Ipecacuanha, 3. As spray to the throat to relieve bronchial asthma and emphysema, combined with fibroid phthisis
Koumiss, 1
Linseed, 1
Mercuric Chloride, 3. In minute doses for diarrhœa
Mineral Acids, 1
Mineral Waters, 1
Morphine, with Starch or Bismuth. Locally to larynx, and in laryngeal phthisis most useful
Mustard Leaves. Most useful to lessen pain and prevent spread of subacute intercurrent inflammation
Ol. Pini Sylvestris, 1
Ol. Lini and Whisky, 1
Opium, 3. To relieve cough, and, with ipecacuanha and Dover's powder, to check sweating
Oxalic Acid, 1
Oxygen, 2, 3
Ozone, 1
Pancreatic Emulsion, 1
Peroxide of Hydrogen, 1
Phallandrium, 1
Phosphates, 2, 4
Phosphate of Calcium, 3. As nutrient, and to check diarrhœa
Phosphoric Acid, 1
Picrotoxin, 2, 3. To check perspiration
Pilocarpine, 2, 3. To check sweats
Plumbi Acetas, 1
Plumbi Carbonas, 1
Podophyllum, 1
Potassæ, Liquor, 1
Potassium Chloride, 1
Potassium Iodide, 1
Prunus Virginiana, 2, 4
Prunus, Tincture, 1
Quinine, 1, 3. As tonic to lessen temperature, to check sweat
Raw Meat and Phosphates, 1
Salicylic Acid, 3. When breath foul and expectoration offensive
Sanguinaria, 1
Sea Bathing, 3
Sea Voyage, 1
Secale, 1
Silver Nitrate, 1, 3
Snuff, 1
Sodium Benzoate, 1, 2
Sodium Chloride, 1
Sodium Phosphate, 1
Sponging, very hot, 3
Strychnine, 2, 4
Sugar, 1
Sulphur, 1
Sulphuric Acid, 3
Sulphurous Acid, 1, 3. As fumigation
Terebene, 1
Thymol, 1, 4
Tr. Iodi, 1
Transfusion, 1
Turkish Bath, 1, 3
Turpentine, 1
Vinegar, 3

Pityriasis.

Acetic Acid, 2
Arsenic and Mercury. Internally
Bichloride of Mercury, 2

Pityriasis.

Borax, 2, 3. Saturated solution or glycerine locally
Cajeput Oil, 4
Carbolic Acid, 2. With glycerine and water locally
Chrysarobinum,
Citrine Ointment, 1
Glycerine, 1
Lead, 3. Locally
Mercuric Ointment, 3. Locally
Myrtol, 2
Oleate of Mercury, 2
Sapo Laricis, 1
Sulphides, 2. Locally
Sulphurous Acid, 3

Pleurisy.

Aconite, 2, 3. In early stage
Antimony, 3
Belladonna Plaster. Most useful to relieve pain in old adhesions
Blisters, 2, 3, 4
Blood-letting, 2
Bryonia. After aconite
Chloral, 2
Cod-Liver Oil, 3
Digitalis, 2. When much effusion
Gelsemium, 4
Iodide of Potassium, 2, 3, 4. To aid absorption
Iodine, 3, 4. As a liniment externally to assist absorption, or as a wash or injection to cavity after tapping
Jaborandi, 1, 4
Leeches
Local Wet Pack. To chest
Mercury, 1, 4
Morphine, 1, 2, 3
Packing, 3
Pilocarpine, 1, 2
Poultices, 3, 4
Purgative Salts, 3
Quinine, 2
Sinapisms, 3
Sodium Chloride
Veratrum Viride, 1, 3

Pleurodynia.

Actæa Racemosa, 3
Acupuncture, 3
Belladonna, 3. Plaster or liniment very useful
Blistering, 3
Chloral, 3. With camphor, locally
Croton Oil, 3. Locally in obstinate cases
Ether, 3. As spray, locally
Iodine, 3. Locally
Iron. When pleurodynia associated with leucorrhœa
Morphine, 1
Mustard Leaves, 3
Nerve-stretching, 1
Opium, 3. Liniment rubbed in after warm fomentations or hypodermic injections. Internally, most useful to cut short attack and relieve pain
Plasters. To relieve pain and give support
Poultices, 3
Quinine
Strapping, 1
Veratrum Viride
Wet-cupping. When pain severe and fever high

Pleuro-Pneumonia.

Bryonia
Carbolic Acid. 2 per cent. solution injected locally

Pleuro-Pneumonia.

Sanguinaria
Turpentine. Locally

Pneumonia.

Acid, Phosphoric, 1
Aconite. Very useful, especially at commencement
Alcohol, 4
Ammonia, 4
Ammonium Carbonate, 2. As stimulant
Arnica, 1
Belladonna. At commencement
Bleeding, 1
Blisters. At beginning to lessen pain
Bryonia. When pleurisy present
Carbonate of Sodium, 1
Chloral, 1, 4
Chloroform, 1
Cold, 4
Cold Bath, 1
Cold Compress to Chest, 1
Copper Acetate
Copper Sulphate, 2
Digitalis, 1, 2, 4. To reduce temperature
Ether, 2
Expectorants, 4
Gelsemium, 4
Iodide of Ammonium, 2
Mercury, 4
Morphine, 2, 3
Muscarine, 2
Packing, 3
Phosphorus, 3, 4
Pilocarpine, 1
Plumbi Acetas, 1
Potassium Chlorate, 1
Potassium Nitrate, 1
Poultices, 1, 3, 4. To lessen pain
Quinine, 1, 2, 3, 4. To lower temperature
Salicylate of Sodium. As antipyretic
Secale, 1
Senega. As expectorant
Serpentaria, 2. With carbonate of ammonia as stimulant
Sinapisms, 3
Stimulants, 1
Strychnine, 1
Tartar Emetic, 1, 3, 4
Turpentine, 2, 4. As stimulant at crisis
Veratrine, 1
Veratrum Viride, 1, 2, 3, 4
Wet Pack, 2

Polypus.

Alcoholic Spray, 1
Alum. As insufflation
Carbolic Acid and Glycerine, 1
Sesquichloride of Iron, 1
Sodium Ethylate, 1
Tannin, 1. As insufflation
Tr. Opii cum Croco, 1
Zinc Sulphate, 1

Prolapsus Ani.

Aloes, 1
Alum, 3. In solution locally
Bismuth, 1
Electricity, 1
Ergotin, 1
Hydrastis. As enema or lotion
Ice. When prolapsed parts inflamed
Nitric Acid, 1
Opium, 1
Pepper. Confection
Podophyllum. In small doses
Silver Nitrate, 1

Prolapsus Ani.

Strychnine, 1, 3. As adjunct to laxatives
Tannin, 3. As enema

Prolapsus Uteri.

Alum, 3. As hip-bath and vaginal douche
Bromide of Potassium, 1
Cimicifuga. To prevent miscarriage and prolapsus
Electricity, 1
Galls. Decoction of, as injection
Glycerine Tampon, 1
Ice, 3. Locally when part inflamed, and to spine
Oak Bark. As injection
Secale, 1
Tannin, 3

Prostate, Enlarged.

Alkalies, 2. When irritation of the bladder with acid urine
Ammonium Benzoate, 2. For cystitis with alkaline urine
Ammonium Chloride, 1
Conium, 1
Ergot, 1, 2
Iodine, 1, 2. Apply to rectum
Iodoform, 2. As suppository very useful
Sulphides, 2

Prostatitis.

Blisters. To perineum in chronic cases
Buchu
Cantharides, 3. Small doses of tincture
Cubebs
Hot Injections, 3
Hydrastis. Internally and locally
Iron
Silver Nitrate. Locally
Turpentine

Prurigo and Pruritus.

Aconite, 1. Externally
Alkaline Lotions, 1
Alkaline Warm Baths, 2
Alum. A strong solution for pruritus vulvæ
Aluminium Nitrate, 1
Arsenic, 1. Internally
Atropine, 1
Balsam of Peru, 1
Belladonna, 2
Boric Acid, 1
Borax, 1, 3. Saturated solution
Bromide of Potassium, 1
Calomel. Ointment very useful in pruritus ani
Cantharides, 3
Carbolic Acid, 1, 2, 3. Internally and locally, especially in prurigo senilis
Chloral and Camphor, 1
Chloroform Ointment, 3
Cod-Liver Oil. As inunction
Corrosive Sublimate. For pruritus vulvæ
Cyanide of Potassium, 2, 3. As lotion or ointment, to be used with care
Electricity, 1
Gelsemium
Glycerine
Glycerole of Tar
Hot Water, 1
Hydrargyrum Bichloridum, 1
Hydrargyrum Oleatum cum Morphina, 1, 2
Hydrocyanic Acid, 2. Locally
Ice, 3
Iodoform. As ointment

Prurigo and Pruritus.

Liquor Carbonis Detergens
Marine Lint, 1
Mercury. Locally
Opium, 1
Oil of Cade, 1
Petroleum Oil, 1
Pilocarpine, 1
Potassium Carbonate
Salicylic Acid, 1
Sapo Viridis, 1
Silver Nitrate, 1, 2
Sodium Carbonate
Stavesacre, 1
Strychnine, 1
Sulphate of Zinc, 1
Sulphides
Sulphites, 1, 2
Sulphur and Compounds, 1, 3
Tar Ointment
Tobacco, 1. Useful but dangerous
Turkish Baths, 1, 3
Warm Baths, 3

Psoriasis.

Aconite
Alkaline Baths, 1
Ammonium Carbonate, 1
Ammonium Chloride
Arsenic, 1, 2, 3, 4
Baths. Alkaline, to remove scales
Berberine
Bleeding, 1
Cajeput Oil, 4
Calomel, 1, 3. Locally as ointment
Cantharides, 3
Carbolic Acid, 1, 3
Carbonic Acid
Chloride of Lime, 1
Chromic Acid. 10 grs. to the ounce in psoriasis of tongue
Chrysophanic Acid, 1, 4
Cod-Liver Oil, 1, 2
Copaiba, 1
Copper Sulphate, 3
Corrosive Sublimate Bath, 1
Creasote Baths, 1
Electricity, 1. Constant current rapidly applied
Fats and Oils, 3
Galium, 1
Glycerine, 4
Glycerole of Lead, 1
Guano, Urate of Ammonium Baths, 1
Hepar Sulphuris
Hydrochloric Acid, 1
India-rubber Solution, 1
Iodine, 4
Iris
Lead Iodide, 1. Locally
Liq. Potassæ, 1
Mercury, 1, 3. Locally as ointment
Mezereon
Nitric and Nitro-Hydrochloric Acids. When eruption is symptomatic of indigestion
Phosphorus, 1, 2, 4. As substitute for arsenic
Pitch, 1
Potassium Acetate, 1
Potassium Iodide, 1
Pyrogallic Acid, 1
Salicylic Acid, 1
Sapo Laricis, 1
Silver Nitrate, 1, 2, 3. In psoriasis of tongue
Soap, 3
Sodium Arseniate, 1
Sulphides, 3
Sulphur, 1, 3. Internally
Sulphur Baths, 2
Sulphur Iodide. Internally and externally
Tar, 3. As ointment
Terebinthinæ Ol., 1

Psoriasis.

Thymol, 1
Turkish Baths, 3
Ulmus, 1
Vaseline
Warm Baths, 3

Ptosis.

Arseniate of Sodium
Ergot
Salicylic Acid
Tr. Iodi, 1
Veratrine. Locally to the eyelids and temples
Zinc Chloride

Ptyalism.

Acids. In small doses internally and as gargles
Alcohol. Dilute as gargle
Atropine. Hypodermically
Belladonna, 1, 2, 4. Very useful
Brandy, 2
Calabar Bean, 1
Chlorate of Potassium, 1. As gargle
Chloride of Zinc, 1
Iodide of Potassium
Iodine. As gargle, 1 of tincture to 30 of water
Opium, 4
Purgatives, 1
Sulphur, 1
Tannin, 2
Vegetable Astringents, 2

Puerperal Convulsions.

Aconite. In small doses frequently
Anæsthetics, 4
Belladonna. Useful
Benzoic Acid, 1
Bleeding, 2
Bromide of Potassium, 1, 3
Bromides, 2
Camphor, 4
Chloral, 1, 2, 3, 4. In full doses
Chloroform, 1, 2, 3, 4. By inhalation
Cold to Abdomen, 1
Dry Cupping over Loins
Ether, 1
Ice. To head
Morphine, 2, 3. Hypodermically very useful
Mustard. To feet
Nitrite of Amyl, 2, 4. Of doubtful utility
Nitro-glycerin, 4
Ol. Crotonis, 1
Pilocarpine, 1
Veratrum Viride, 1. Pushed to nausea very useful

Puerperal Fever.

Acid, Salicylic, 2
Aconite, 1. Useful at commencement
Alkaline Sulphates. In early stages
Ammoniæ Liq., 1
Amyl Sol. of Iodine, 1
Blisters, 1
Borax, 4
Calumba. As tincture
Camphor, 1
Carbolic Acid, 1, 2
Chloroform, 1
Creasote Oil, 1
Digitalis, 4
Emetics, 1
Ergot, 1
Hydrargyrum, 1. The subchloride or bichloride
Ice, 1
Iodine, 1
Ipecacuanha, 1

Puerperal Fever.

Opium, 1, 2. For wakefulness and delirium very useful
Permanganate of Potassium, 2
Plumbi Acetas, 1
Potassium Oxalate, 1
Purgatives, 1
Quinine, 1, 2. In large doses
Resorcin, 2
Sodium Benzoate, 1
Sodium Sulphite, 1
Stimulants, 1
Stramonium. With cerebral excitement
Tr. Ferri Perchloridi, 1
Turpentine, 1, 2, 3, 4. With much vascular depression and tympanites
Venesection, 1
Veratrum Viride, 1
Warburg's Drops, 1

Puerperal Mania.

Aconite. With much fever
Anæsthetics, 2. During paroxysm
Bromide of Potassium, 2, 3
Bromides, 2
Camphor, 1
Chalybeates, 2
Chloral, 1, 2, 3
Chloroform, 1
Cimicifuga. Useful in hypochondriasis
Duboisine, 2
Hyoscyamus, 2. In mild cases
Iron. In anæmia
Morphine, 2, 3
Opium, 1
Poultices
Quinine, 2. When much sickness
Stramonium. When delirium furious but intermittent, or suicidal, or when impulse to destroy child
Tartar Emetic, 1, 2, 3. Frequently repeated

Puerperal Peritonitis.

Aconite. At commencement
Antimony, 3
Chlorine Solution, 3
Cimicifuga. In rheumatic cases
Heat to Abdomen, 2
Ice to Abdomen, 2
Laxatives. Useful combined with Dover's powder and hyoscyamus
Mercury, 4
Opium, 2. Very useful
Quinine, 2. In large doses
Turpentine, 2. As stimulant, 10 m. frequently repeated

Purpura.

Agrimonia, 1
Alum. Locally with brandy
Arsenic, 3
Digitalis, 2
Electricity, 1
Ergot. Very useful
Gallic Acid
Iron. Internally
Lead Acetate, 2
Lime Juice, 1
Malt, 1
Milk, 1
Molasses, 1
Nitrate of Potassium
Nux Vomica
Phosphates, 1
Potassium Binoxalate, 1
Potassium Chlorate, 1
Potassium Citrate, 1
Quinine

Purpura.

Sulphuric Acid, 2
Tannic Acid
Tr. Laricis, 1
Turpentine, 1, 2, 3, 4

Pyæmia.

Alcohol, 4
Alkalies, 1
Ammonium Carbonate, 3
Bleeding, 1
Boric Acid
Ergotin, 1
Ferri Perchloridum, 1, 4
Iodine, 1
Jaborandi, 1
Malt Liquor, 2
Oil of Cloves. Locally
Permanganate of Potassium, 3. Internally
Quinine, 1, 2, 3, 4. In large doses
Resorcin, 2
Salicin, 3
Salicylic Acid, 2
Tannin, 1
Turpentine. As stimulant

Pyelonephritis.

Cantharides, 2
Erigeron, 2
Eucalyptus, 2
Gallic Acid, 2
Hydrastis
Pipsissewa (Chimaphila), 2
Turpentine, 2

Pyrosis.

Bismuth, 3, 4
Camphor, 1
Carbolic Acid
Creasote
Gallic Acid, 1
Glycerine, 1
Lead, 3
Manganese Oxide, 3, 4
Mineral Acids
Nitrate of Silver, 4
Nitric Acid, 3
Nux Vomica
Oxide of Silver, 4
Pulvis Kino Compositus, 1
Strychnine, 1
Sulphuric Acid, 1, 3

Relapsing Fever.

Laxatives
Leeches. As cupping for headache
Quinine

Remittent Fever.

Aconite
Arsenic, 4
Benzoates, 2
Cold Affusion, 1
Emetics
Gelsemium. In bilious remittents
Hyposulphites, 1
Ipecacuanha, 4
Livingstone's Pills, 1
Morphine. Hypodermically
Myrrh, 1
Nitric Acid, 1
Packing. Useful
Quinine. 20-30 gr. for a dose, once or twice daily
Resorcin, 2

Remittent Fever.

Salicylic Acid, 2
Silver Nitrate, 1
Sodium Chloride, 1
Turpentine, 1
Warburg's Tincture, 4

Renal Calculi, *vide* Calculi.

Rheumatic Arthritis.

Aconite. Locally
Actæa Racemosa, 3
Arnica. Internally and externally
Arsenic, 1, 2, 3, 4
Buckeye, 1
Chaulmoogra Oil, 1
Cimicifuga. When pains are nocturnal
Cod-Liver Oil, 2, 3
Colchicum, 2
Cold Douche, 3
Electricity, 1
Guaiacum
Iodide of Potassium, 3, 4
Iodides, 2
Iodine, 1, 3. Internally as tonic
Iodoform, 1
Lithium, 2. Internally and locally
Morphine, 1
Potassium Bromide, 3. Sometimes relieves pain
Quinine, 1
Quinine Salicylate, 1
Sodium Salicylate, 1
Stimulants, 1
Strychnine, 1
Sulphides, 3
Sulphur
Turkish Bath, 1, 3

Rheumatism, Acute.

Acid Steam Bath, 3
Aconite, 1, 2, 3, 4
Actæa Racemosa, 1, 3
Acupuncture, 3
Alcohol, 4
Alkalies, 1, 2
Amber, Oil of, 4
Ammonium Bromide, 2, 4
Antimony, 1
Aquapuncture, 1
Arnica, 2
Arsenic, 4
Belladonna, 1
Benzoates, 2
Benzoic Acid, 3
Bicarbonate and Citrate of Potassium, 3
Blisters, 1, 2, 3. Very efficient around joints, near to cardiac region
Bryonia
Burgundy Pitch, 4
Cajeput Oil, 4
Carbolic Acid, 1, 4
Chloroform, 4
Cimicifuga, 4
Citric Acid, 1
Cod-Liver Oil, 4
Colchicum, 1, 4
Cold Baths, 1, 2, 3
Conium, 3, 4
Creasote, 1
Digitalis
Donovan's Solution, 4
Dover's Powder, 4
Dulcamara. In persons liable to catarrh
Faradisation, 1
Fraxinus Polygamia, 1
Guaiacum, 4
Horse Chestnut Oil, 1

Rheumatism, Acute.

Hot Pack, 1
Iodine, 4
Iodoform, 4
Iron, 2
Jaborandi, 4
Leeches, 1
Lemon Juice, 1, 2
Lime Juice, 3
Lithium Bromide, 2. Especially when insomnia and delirium present
Magnesia, 4
Manaca, 1
Mercury, 1, 4
Mineral Acids, 1, 2
Mineral Baths, 1
Mustard Plasters, 1
Opium, 1, 3, 4. 1 gr. every 2 or 3 hours, especially when cardiac inflammation
Packing, 3
Pellitory, 4
Permanganate of Potassium, 1
Potassium Acetate, 1
Potassium Iodide and Opium, 1
Potassium Nitrate, 1, 3, 4
Poultices, 3
Propylamine, 1
Quinine, 1, 3, 4. As antipyretic
Rhus Toxicodendron. Exceedingly useful in after-stage and subacute forms
Salicin, 1, 2, 3
Salicylate of Sodium, 1, 3. Relieves pain most quickly
Salicylates, 1, 2
Scudamore's Mixture, 4. Contains colchicum wine, magnesia, and sulphate of magnesium
Sodium Benzoate, 1
Spigelia Anthelmintica. In pericarditis and shifting inflammation of joints
Spiræa Ulmaria, 1
Steam Bath, 1
Stimulants, 1
Sulphur, 4
Sulphurated Potash, 4
Sulphurous Acid, 1, 3. Fumigative
Tr. Ferri, 1
Trimethylamine, 1, 2
Turkish Bath, 3
Veratrine, 1, 3, 4
Veratrum Viride, 1, 3
Zinc Cyanide, 1
Zinc Oxide, 1

Rheumatism, Chronic.

Aconite, 1
Actæa Racemosa, 3
Acupuncture, 1
Alkaline Baths, 1
Alkaline Mineral Waters, 2
Ammonium Chloride, 1
Ammonium Phosphate, 1
Arnica
Arsenic, 1
Atropine, 1
Belladonna
Blistering, 3
Bryonia
Burgundy Pitch. As plaster locally
Cajeput Oil. Internally and externally
Capsicum, 3
Carbonic Acid, 3
Chaulmoogra Oil, 1
Chimaphila
Chloral, 3
Cimicifuga, 2
Cod-Liver Oil, 2, 3. Internally and locally
Colchicine, 1
Colchicum, 2
Cold Douche, 3
Dulcamara
Faradisation, 1

Rheumatism, Chronic.

Galvanism, 3
Guaiacum, 1, 2
Guarana, 1
Ice and Salt, 3
Iodide of Potassium, 1, 3. Especially when pain worst at night
Iodides, 2
Iodine, 1, 3. Locally
Lamp Black, 3
Lithium Bromide, 2. When smaller joints affected
Lupulin
Manganese Sulphate, 2
Massage, 1
Mercury and Morphine, 3. Oleate locally
Mezereon, 3
Packing, 3
Phytolacca
Pine Leaf Baths, 1
Potassio-Tartrate of Iron, 1
Potassium Nitrate, 3
Poultices, 3
Propylamine, 1
Quinine. When much debility and night sweats
Quinine Salicylate, 1
Rhus Toxicodendron. Internally and locally
Salicylic Acid, 2
Sodium Salicylate, 1
Stramonium, 1
Sulphur, 1, 2, 3. Locally, and as sulphides or sulphur waters internally
Thuja Occidentalis,
Turkish Baths, 2, 3
Veratrine, 3
Xanthoxylum, 2

Rickets.

Calcium Phosphate, 3. If child is suckling it may be given to nurse
Cod-Liver Oil, 2, 3, 4
Cold Sponging, 3
Ferric Iodide
Gallic Acid, 1
Iron, 2, 3
Lime, 1, 3
Nitro-Hydrochloric Acid Baths, 1
Phosphates, 2
Phosphorus, 2, 4
Quinine,
Sarsaparilla, 1
Sugar, 1

Sarcinæ.

Calcium Chloride, 1
Carbolic Acid, 1
Creasote, 1
Gastric Syphon. To wash out stomach
Sulphites, 1, 3
Sulphuric Acid
Wood Spirit, 1

Scabies.

Alkalies, 3
Anise. As ointment
Arsenic, 1
Baking of clothes to destroy ova
Balsam of Peru, 1. Locally, agreeable and effective
Benzoic Acid. As ointment or lotion
Cajeput Oil, 2
Carbolic Acid, 1, 2. Dangerous
Chloroform, 1
Chrisma, 1
Coal Tar Naphtha, 1
Cocculus Indicus. As ointment
Copaiba, 1

Scabies.

Copper Sulphate, 2
Corrosive Sublimate, 2
Glycerine, 1, 4
Iodine, 1
Kamala, 1. As ointment
Liq. Potassæ, 1
Manganese, 2
Mercury. White precipitate ointment
Oil. Inunction
Petroleum, 1
Phosphoretted Oil, 1
Potassium Iodide, 3
Soft Soap
Stavesacre, 1. As ointment
Storax, 1, 3. With almond oil, when skin cannot bear sulphur
Sulphide of Calcium
Sulphides, 2
Sulphites, 2
Sulphur, 1, 3. As ointment
Sulphur and Lime, 3
Sulphur Baths, 2
Sulphuric Acid, 3. Internally as adjuvant
Sulphurous Acid, 3
Tar. Ointment
Vaseline

Scarlet Fever.

Acid, Acetic, 1
Acid, Nitric, 1, 3
Aconite, 2, 3, 4
Ammonium Benzoate, 1
Amyl Hydride, 1
Arsenic, 3. If tongue remains red and irritable during convalescence
Belladonna, 1, 2, 3, 4
Benzoate of Sodium, 2
Bromine, 1
Carbolic Acid, 1, 2. As gargle
Carbonate of Ammonium, 1, 2, 3. Greatly recommended in frequent doses given in milk or cinnamon water
Chloral, 1
Chlorine Water, 1, 2, 3. As gargle
Cold Compress, 3. To throat
Cold Affusion, 1, 3, 4
Copaiba, 1
Digitalis, 1, 2
Fat, 2, 3. As inunction to hands and feet during the rash, and over the whole body during desquamation
Ferric Perchloride. In advanced stage with albuminuria and hæmaturia, very useful
Hot Bath, 1
Hot Packing, 1
Hydrochloric Acid, 1, 2
Ice, 3. To suck, especially at commencement
Ice Poultice, 3
Iodine, 1
Juniper Oil, 3. As diuretic when dropsy occurs
Mercury, 1, 3. ⅛ of a gr. of grey powder every hour to lessen inflammation of tonsils
Mineral Acids. Internally, and as gargle
Mustard Bath, 3. When rash recedes
Packing, 3. Useful and comforting
Potassium Chlorate, 1, 4
Potassium Iodide, 1
Potassium Permanganate, 3. As gargle to throat
Purgatives. Most useful to prevent albuminuria
Quinine, 1, 2, 4
Resorcin, 2
Rhus Toxicodendron
Salicylate of Sodium. As antipyretic
Salicylic Acid, 1, 2, 3
Strychnine, 3. Hypodermically in paralysis
Sulphate of Magnesium, 3
Sulphur, 1

Scarlet Fever.

Sulphurous Acid, 1, 3. Inhalation when throat much affected
Tr. Ferri, 1
Veratrum Viride, 3
Water, 2

Sciatica.

Acid, Sulphuric, 1
Aconite, 3. As ointment or liniment
Actæa Racemosa, 3
Acupuncture, 2, 3
Aquapuncture, 1, 2
Atropine, 1, 2, 3
Belladonna, 3
Blisters
Cautery, 1. Exceedingly useful, slight application of Paquelin's thermo-cautery
Chloride of Ammonium, 1, 3
Chloral, 1
Chloroform, 1, 2, 3. Locally as liniment, inhalation when pain excessive
Cod-Liver Oil, 4
Conium, 4
Copaiba Resin, 1
Counter-irritation, 3
Croton Oil, 1, 3. Internally as purgative
Electricity, 4
Ether, 1, 3. As spray
Galvanism
Gelsemium, 1
Guaiacum, 1, 2
Iodide of Potassium, 1, 3, 4
Iodides, 2
Menthol, 1
Morphine, 1, 2, 3. Hypodermically most useful
Phosphorus, 1
Plasters, 1
Poultices, 3
Salicylic Acid, 2
Salicylate of Sodium, 1, 3
Sand Bath
Secale, 1
Silver Nitrate, 1, 2
Stramonium. Internally, pushed until physiological action appears
Sulphur, 1, 3, 4. Tied on with flannel over painful spot
Turkish Bath, 3
Turpentine, 1, 2, 3. In ½ oz. doses internally for three or four nights successively
Veratrine, 3. As ointment

Scrofula.

Acacia Charcoal, 1
Acid, Phosphoric, 4
Alcohol, 4
Arsenic, 1
Barium Chloride, 1
Blisters, 3. To enlarged glands
Calcium Phosphate, 3
Calomel, 3
Chalybeate Waters, 2
Chloride of Calcium, 3
Cod-Liver Oil, 2, 3, 4. Exceedingly serviceable
Fats, 1. Inunction
Galium Aparinum, 1
Gold Salts, 1
Iodides, 2
Iodide of Iron, 3, 4
Iodine, 3, 4. Locally to glands, and internally
Iron, 2, 3
Milk and Lime Water, 1
Peroxide of Hydrogen, 1
Pipsissewa, 4
Phosphates, 2, 4
Potassium Chlorate, 1
Sanguinaria, 2
Sarsaparilla, 2, 4

Scrofula.

Soft Soap, 3
Stillingia, 2
Sulphides, 1, 3
Walnut Leaves, 1

Scurvy.

Acids. As preventive in the absence of lime-juice
Aconite. In acute stomatitis with salivation in scorbutic conditions
Agrimonia, 1. Useful in the absence of other remedies
Alcohol. Diluted as gargle
Alum. Locally with myrrh for ulcerated gums
Ammonium Carbonate. In scorbutic diathesis
Arsenic. In some scorbutic symptoms
Atropine. Hypodermically when salivation
Cinchona. As decoction, alone or diluted with myrrh as gargle
Citric Acid. As substitute for lime-juice
Ergot, 1
Ergotin, Hypodermic Injection of, or Ergot by mouth to restrain the hæmorrhage
Ferri Arsenias, 1. As a tonic where other remedies have failed
Ferri Perchloridi, Tinctura, 1. To restrain hæmorrhage
Laricis, Tinctura, 1. Like Ferri Perchlor., Tinct.
Lemon Juice, 4. Exceedingly useful as preventive and curative
Liberal Diet often sufficient
Liquor Sodæ Chlorinatæ. Locally to gums
Malt, 1. An antiscorbutic
Oranges. Useful
Phosphates, 1. Non-assimilation a cause
Potassium Binoxalate. In doses of 4 grains three times a day; if not obtainable sorrel is useful instead
Potassium Citrate, 1. Substitute for lime-juice
Quinine. With mineral acids internally
Silver Nitrate
Tartar Emetic
Vegetable Charcoal. As tooth-powder to remove fetid odour
Vinegar. Very inferior substitute for lime-juice

Sea-Sickness.

Amyl Nitrite, 1. A few drops on handkerchief inhaled; the handkerchief must be held close to the mouth
Atropine, 3. $\frac{1}{100}$ gr. hypodermically
Belladonna, 1. Like Atropine
Bitters, 2. Calumba, &c.
Caffeine Citrate, 1. For the headache
Cannabis Indica, 1. ½–½ gr. of the extract to relieve headache
Capsicum, 1.
Champagne, Iced, 1. Small doses frequently repeated
Chloral, 2, 3. 15 to 30 grs. every four hours most useful; should be given before nausea sets in; the combination with Potassium Bromide taken with effervescing Citrate of Magnesia is very good
Chloroform, 2, 3. Pure, 2–5 min. on sugar
Chloric Ether. Stomachic tonic
Cocaine, 1. Infusion of Coca leaves quickly relieves
Counter-irritation. Mustard plaster or leaf to epigastrium
Creasote, 1
Hydrocyanic Acid, 1
Hyoscyamine, 1, 3. $\frac{1}{60}$ gr. with the same quantity of strychnine
Ice, 1. To spine

Sea-Sickness.

Magnetic Belt, 1.
Morphine, 2. Hypodermically
Nitro-glycerin, 2. Same action as Nitrite of Amyl
Nitro-Hydrochloric Acid, 1. Formula: Acidi nitro-hydrochlorici, 3iij., Acidi hydrocyanici dil., 3ss., Magnesii sulphatis, 3ij., Aq., ℥viij. 3j. ter die sumenda
Nux Vomica, 2. When indigestion with constipation
Potassium Bromide, 1. Should be given several days before voyage is begun
St. Etienne Arsenical Waters, 1.
Salt and Warm Water, 1.
Sodium Bromide. Like Potassium Salt

Seborrhœa.

Borax, 4. With glycerine and lead acetate, as a local application
Glycerine
Iodine
Lead Acetate. With borax and glycerine, as above
Liquor Potassæ, 2. Locally applied to hardened secretion
Sodium Chloride
Zinc Oxide, 2. In inflammation the following formula is useful: ℞ Zinci oxidi, 3j.; Plumbi carbonat. 3j.; Cetacei, ℥j.; Ol. olivæ, q.s.; ft. ung.

Sexual Excitement.

Camphor, 3, 4. Will often control
Digitalis, 1. Anaphrodisiac; also diminishes quantity of seminal fluid
Lupulus Humulus, 4. In large doses
Opium, 1. Anaphrodisiac
Potassium Bromide, 4. The most generally useful
Stramonium, 1. In nymphomania, or epilepsy due to sexual excitement

Sleeplessness.

Alcohol, 3. With care in febrile disorders
Butyl-Chloral. Like Chloral
Cannabis Indica. Instead of opium, when the latter does not agree
Chloral Hydrate, 3. In the high tension of Bright's disease; in delirium tremens, acute mania, and puerperal convulsions; contra-indicated by weak heart
Codeine, 3. A pure narcotic
Digitalis, 3. In want of arterial tone, marked by blood rushing to the head when the person lies down
Ether, 4. In full dose
Gelsemium, 2. In mania with motor excitement
Cold Sponging either of the whole body or feet only, followed by brisk rubbing
Hyoscyamine, 3. Sleeplessness of acute mania
Hop Pillow
Hypnone
Lettuce. A supper of lettuce and ale
Opium, 3, 4. In acute disease
Potassium Bromide, 3, 4. In over-work of any description; in alcoholic mania
Phosphorus, 2. Well combined with chloral in cerebral anæmia and in the aged
Urethane. Like Chloral
Warm Bath, 3. Or warm sponging
Wet Pack. Like the preceding in fever

Sneezing.

Arsenic, 3. In paroxysmal sneezing, such as usually ushers in hay fever
Belladonna, 1

Sneezing.

Camphor, 3. As powder, or strong tincture inhaled in commencing catarrh
Chamomile Flowers, 1. In nares
Cotton Plug. In nares
Gelsemium. In excessive morning sneezings with discharge
Iodine. Inhalation
Mercury. Heaviness of head and pain in limbs
Potassium Iodide, 3. 10-gr. doses frequently repeated
Pressure beneath Nose, over the termination of the nasal branch of the ophthalmic division of the fifth

Somnambulism.

Opium
Potassium Bromide. In all cases of children and adults

Spasmodic Affections.

Aconite, 3, 4. Externally and internally; it subdues motor spasm, and the spasms of dyspnœa in spasmodic asthma of children
Alcohol. In the dyspnœa of fever with caution, and in flatulent distension
Ammonia, 3. In syncope, and in the intestinal colic of children
Ammoniacum. In hysteria
Amyl Nitrite. In spasm of the arterioles
Anæsthetics. To reduce muscular spasm
Arsenic. Nervine tonic in hysteria, epilepsy, &c.
Asafœtida, 4. Carminative, and to relieve functional spasm
Atropine, 3, 4. Internally, to relieve spasm of involuntary muscular fibre; hypodermically, local spasm
Cajeput, Oil of, 4. In intestinal colic
Camphor. Nervine, vaso-motor, respiratory stimulant
Cardamoms. Carminative
Chamomile, Oil of. Migraine
Chloroform. In small doses to co-ordinate; in large doses it paralyses muscular movements
Cimicifuga. Congestive dysmenorrhœa; and in acute bronchitis
Cocaine, 4. Cerebral stimulant
Conium, 1. To relieve clonic muscular spasm
Copper. Nervine tonic in chorea, &c.
Electricity
Ether. Like alcohol and chloroform
Gelsemium, 2. In hyperæsthesia and motor excitement
Grindelia, 2. In spasm due to respiratory neurosis
Hot Sand, 3. Locally, in painful spasm, such as intestinal colic
Hyoscyamus, 1. In pain about the bladder
Ice, 1. To spine
Ipecacuanha, 2. In laryngismus stridulus, in an emetic dose
Lactucarium, 4. Cerebral sedative
Lead Salts probably have an action on the spinal cord
Leeches. By counter-irritation
Lobelia. In spasm of the respiratory organs
Local Pressure, 1. On a particular point, to be found for each case
Lupuline, 2. Cerebral sedative
Musk, 4. A mild nervine stimulant
Nitro-glycerin, 1. Like Amyl nitrite
Nux Vomica. Nervine tonic
Opium, 2, 3, 4. Central sedative, both for motor and sensory nerves
Oxygen, 1. Heated and mixed with nitrite of amyl in spasmodic asthma
Physostigmine. To paralyse muscular fibre
Potassium Bromide, 1. Sedative to the central nervous system

Spasmodic Affections.

Poultices, Mustard. Counter-irritant
Silver Nitrate. Tonic in epilepsy and chorea, laryngismus stridulus, &c.
Strychnine. Nervine tonic
Sulpho-carbolates, 3. In flatulent 'spasms'
Sumbul. In nervousness and hysterical symptoms, both in men and women
Tobacco, 3. Relieves spasm by its prostrating effect
Valerian, 4, In hysteria
Veratrine. Prolongs the systole of the heart and muscular fibre
Veratrum Viride. Controls and depresses the vaso-motor system
Warmth to abdomen to allay cramp and convert into peristalsis
Zinc Salts. Like copper and silver

Spermatorrhœa.

Arsenic, 2. In functional impotence; best combined with iron as the arseniate, and with ergot
Belladonna, 2, 3. In relaxation of the genital organs where there is no dream nor orgasm; one-fourth grain of extract, and a grain and a half of zinc sulphate
Bladder to be emptied as soon as patient awakes
Bromide of Potassium, 2. When it is physiological in a plethoric patient, not when genitalia are relaxed
Calomel, 1. Ointment applied to urethra
Camphor Bromide, 2, 4. Or camphor alone; diminishes venereal excitement
Cantharides, 2, 3. In cases of deficient tone either from old age, excess, or abuse; should be combined with iron
Chloral, 4. To arrest nocturnal emissions
Cimicifuga, 2. Where emission takes place on the least excitement
Cold Douching and Sponging, 2
Digitalis, 2, 3. In frequent emissions with languid circulation; with bromide in plethoric subjects
Electricity
Ergot, 2. Deficient tone in the genital organs
Gold Chloride, 2. To increase venereal desire
Hydrastis, 2. Local application to urethra
Hypophosphites, 3. Nervine tonic
Iron. Where there is anæmia only
Lupulin, 2. Oleoresin, to diminish nocturnal emissions
Nitrate of Silver, 2. Vesication by it of the perineum; and local application to the prostatic portion of the urethra
Nux Vomica, 2. Nervine tonic and stimulant
Phosphorus, 3. In physical and mental debility
Quinine. As a general tonic
Spinal Ice-bag, 3
Sulphur. As a laxative, especially if sequent to rectal or anal trouble
Turpentine, 4. In spermatorrhœa with impotence
Zinc Oxide, 1

Spina Bifida.

Calcium Phosphate
Collodion. As means of compression
Cotton Wool over tumour
Glycerine. Injection after tapping
Iodine. Injections; formula for injection: Iodine, gr. x.; Potassium Iodide, gr. xxx.; Glycerin, ℥j.
Potassium Iodide
Tapping, followed by compression

Spinal Concussion.

Arnica
Bleeding. To relieve heart
Lead Water and Opium. As lotion
Leeches
Vinegar. To restore consciousness

Spinal Congestion.

Aconite
Antiphlogistic treatment
Cold Affusions. To spine
Ergot, 4. In large doses
Gelsemium
Nux Vomica
Turpentine
Wet Cupping

Spinal Irritation.

Aconite Ointment, 3. Locally
Arsenic
Atropine
Belladonna, 3. Gives way to this more readily than to aconite
Blisters. To spine
Cimicifuga
Cocculus Indicus. Like strychnine
Conium
Counter-irritation
Digitalis
Electricity, 2, 4. Combined with massage and rest
Ergot, 4. In spinal congestion
Ignatia
Leeches
Nux Vomica
Opium. In small doses
Phosphoric Acid
Phosphorus
Picrotoxin
Potassium Bromide, 2. To lessen activity
Sinapis, Linimentum. Counter-irritant
Sodium Hypophosphite
Strychnine. To stimulate the depressed nerve-centres
Veratrum Viride

Spinal Paralysis and Softening.

Argentic Nitrate, 4. In chronic inflammation of the cord or meninges
Belladonna, 3. In chronic inflammatory conditions
Cod-Liver Oil, 2. As a general nutrient
Electricity, 2, 3. Combined with massage and rest
Ergot, 4. In hyperæmia of the cord
Hyoscyamus, 2, 3. In paralysis agitans to control tremors
Iodide of Potassium, 2. In syphilitic history
Mercury. Temporarily cures in chronic inflammation of the cord and meninges
Phosphorus, 2. As a nervine tonic
Physostigma, 2, 3. In a few cases of progressive paralysis of the insane, in old-standing hemiplegia, in paraplegia due to myelitis, and in progressive muscular atrophy it has done good service
Picrotoxin, 2. Spinal stimulant after febrile symptoms have passed off
Strychnine, 2, 3, 4. Like picrotoxin

Spinal Affections.

Arsenic, 2. With quinine in malarial enlargement; alone in simple engorged spleen; in typho-malarial fever; and prophylactic in malaria

Spinal Affections.

Cold Affusion, 2. To reduce the engorged spleen
Ergot, 1. In relapsing intermittent fever associated with permanently enlarged spleen
Gelsemium, 2. Beneficial in cases in which arsenic is, but not specific
Grape Cure
Hydrastis, 2. Less powerful than quinine
Iodine and Iodides, 2. To promote absorption of the enlarged spleen in simple hypertrophy
Manganese, 2. To remedy anæmia if present
Mercuric Biniodide. The ointment applied over the splenic area rapidly produces absorption in simple enlargement
Muscarine, 2. In vascular dilatation
Nitric Acid, 1. Long course in syphilitic and cachexia with enlargement of the spleen
Plumbic Iodide, 2. Like mercuric iodide
Quinine, 2, 3, 4. Almost a specific in the malarial enlargement of the spleen
Resorcin, 2. Like and equal to quinine

Splenic Affections.

Aconite
Ammonium Iodide

Sprains.

Aconite Liniment. Well rubbed in
Alcohol. Methylated spirit in four of water applied to sprain continuously and allowed to evaporate
Ammonium Chloride, 1. Prolonged application of cold saturated lotion
Arnica, 3. Much vaunted, little use
Bandaging, 1. To give rest to the injured ligaments
Calendula. As a lotion
Camphor, 4. A stimulating liniment
Cold Douche, 1, 3.
Collodion, 1. A thick coating to exert a firm even pressure as it dries
Hot Fomentations, 1. Early applied
Inunction of Olive Oil, 1. With free rubbing
Iodine. To a chronic inflammation after a sprain
Lead Lotions. Applied at once to a sprained joint
Oil of Bay
Rest
Rhus Toxicodendron. Lotion
Shampooing. After the inflammation has ceased, to break down adhesions
Strapping, 1. To give rest
Turpentine Liniment. A stimulant application to be well rubbed in
Vinegar, 4. Cooling lotion

Stammering.

Hyoscyamus
Stramonium
Vocal Training the most useful

Sterility.

Alkaline Injections, 1. In excessively acid secretions from the vagina
Aurum, 2. Where due to chronic metritis, ovarian torpor or coldness; also in decline in the sexual power of the male
Borax. Vaginal injection in acid secretion
Cantharides. As a stimulant where there is impotence in either sex
Cimicifuga, 2. In congestive dysmenorrhœa
Dilatation of Cervix in dysmenorrhœa, in pinhole os uteri, and in plugging of the cervix with mucus
Electrical Stimulation of Uterus, 1. In torpor

Sterility.

Gossypii Radix, 4. In dysmenorrhœa with sterility
Guaiacum, 1. In dysmenorrhœa with sterility
Intra-uterine Stems, 1. To stimulate the lining membrane of the uterus
Key-tsi-Ching, 1. A Japanese remedy for female sterility
Phosphorus, 2. Functional debility in the male
Potassium Iodide. An emmenagogue

Stings and Bites.

Aconite
Alum, 1. For scorpion sting
Ammonia and Alkalies, 3. In stings of insects, to neutralise the formic acid; and in snake-bite
Aqua Calcis, 1. In stings of bees and wasps
Arsenic. As a caustic
Camphor
Carbolic Acid. Mosquito-bites and scorpion-stings
Chloroform, 1. On lint
Essence of Pennyroyal, 1. Against mosquitos
Eucalyptus, 1. Plant in room to keep away mosquitos
Ipecacuanha, 1. Leaves as poultice for mosquito and scorpion bites
Mint Leaves
Oil of Cinnamon. 3j. to ℥j. spermaceti ointment spread over hands and face against mosquitos
Oil of Cloves. The same
Potassa Fusa. In dog-bites a most efficient caustic
Removal of Sting
Rosemary
Sage
Silver Nitrate. A caustic, but not sufficiently strong in dog-bites
Soap, 1. To relieve itching of mosquito-bites
Stimulants
Sugar. Pounded, in wasp-stings

Stomatitis.

Acids, Mineral, 3. Nitro-hydrochloric acid as gargle or internally ulcerative stomatitis
Alcohol, 2. Brandy and water, a gargle in mercurial and ulcerative stomatitis
Alum, 3. Burnt alum applied locally in ulcerative stomatitis
Argentic Nitrate, 1. In thrush locally
Bismuth, 2. In aphthæ of nursing children, sore mouth, dyspeptic ulcers, mercurial salivation, locally applied
Borax, 1. In thrush and chronic stomatitis
Boric Acid, 3. Lotion of 1 in 50
Carbolic Acid, 4. Strong solution locally to aphthæ
Copper Sulphate, 3. Locally in ulcerative stomatitis, and to indolent ulcers and sores
Cornus. Astringent
Eucalyptus, 2. In all forms
Glycerine of Tannin, 3. In ulcerative stomatitis
Hydrochloric Acid, 2. Concentrated in gangrenous stomatitis; dilute in mercurial, aphthous, &c.
Hydrastis, 2. Fluid extract locally
Iris. In dyspeptic ulcer
Krameria, 2. Local astringent
Lime Water, 3. In ulcerative stomatitis
Mercury. In dyspeptic ulcers, grey powder
Potassium Chlorate, 1, 2, 3, 4. The chief remedy locally and internally
Potassium Iodide, 1. In syphilitic ulceration
Rubus, 2. Astringent
Salicylic Acid, 3. One part in sufficient alcohol to dissolve, to 50 of water, in catarrhal inflammation to ease the pain

Strabismus.

Atropine. To lessen converging squint when periodic in hypermetropia
Eserine. To stimulate the ciliary muscles in deficient contraction
Electricity
Hyoscyamus
Mercury. Like Iodide of Potassium
Operation
Potassium Iodide. In syphilitic history if one nerve only is paralysed
Shade over One Eye. In children to maintain acuity of vision
Suitable Glasses. To remedy defective vision

Strophulus.

Antimonium Crudum
Borax and Bran Bath. If skin is irritable
Carbonate of Calcium
Chamomile
Glycerine
Lancing the Gums
Lead Lotions. To act as astringents
Mercury. Grey powder if stools are pale
Milk Diet
Pulsatilla
Spiritus Ætheris Nitrosi. In S. confertus where there is deficient secretion of urine

Sunstroke.

Aconite, 1. Not to be used with a weak heart
Alcohol, 1. Is afterwards always a poison
Ammonia, 1. For its diaphoretic action
Apomorphine, 1. $\frac{1}{16}$ grain at once counteracts symptoms
Artificial Respiration
Belladonna
Bleeding, 1. In extreme venous congestion
Brandy. In small doses in collapse
Camphor
Chloroform. In convulsions
Digitalis, 1. To stimulate heart
Ergot, 1. By the mouth or subcutaneously
Gelsemium
Hot Bath. In collapse
Ice, 1. To reduce temperature. Ice drinks as well
Leeches
Nitrite of Amyl
Nitro-glycerin
Potassium Bromide, 1. To relieve the delirium
Quinine. In thermic fever
Scutellaria
Tea. Cold, as beverage instead of alcoholic drinks
Veratrum Viride
Water, Cold. Affusion
Wet Sheet. Where the breathing is steady, otherwise cold douche

Suppuration.

Alcohol, 2. To be watched
Ammonium Carbonate. In combination with bark
Calcium Salts, 2. To repair waste
Carbolic Acid, 2. Lotion and dressing
Cinchona. As tonic, fresh infusion is best
Hypophosphites, 1. Tonic
Iodide of Iron. Tonic
Iodide of Manganese. Tonic
Mercury
Phosphates. Like the hypophosphites
Quinine. Tonic
Sarsaparilla. Tonic
Sulphides, 3. When a thin watery pus is secreted, to abort, or hasten suppuration

Surgical Fever.

Aconite
Chloral
Quinine
Salicylic Acid
Tinctura Ferri Perchloridi, 1. As a prophylactic
Veratrum Viridi. To reduce the circulation and fever

Sycosis.

Arsenici et Hydrargyri Iodidi, Liquor. Where there is much chronic thickening
Canada Balsam and Carbolic Acid, 1. In equal parts, to be applied after epilation in tinea sycosis
Chloride of Zinc, 1. Solution in tinea sycosis
Chrysarobini, Ung. In parasitic sycosis
Cod-Liver Oil. In chronic non-parasitic
Hydrargyri Acidi Nitratis, Ung.
Hydrargyri Ammoniatum, Ung. In parasitic
Hydrargyri Oxidi Rubri, Ung.
Iodide of Sulphur Ointment, 1. In non-parasitic
Oleate of Mercury, 2, 3. In parasitic
Oleum Terebinthinæ, 1. Like the preceding
Shaving
Sulphurous Acid. Like preceding
Thuja
Zinci et Cupri Sulphas, 1

Syncope.

Aconite
Alcohol, 3, 4. Sudden, from fright or weak heart
Ammonia, 3, 4. Inhaled cautiously; the carbonate internally
Arsenic. Nervine tonic, prophylactic
Belladonna, 1. In cardiac syncope
Camphor. Cardiac stimulant
Chloroform, 3. Transient cardiac stimulant. Mostly in hysteria
Cold Douche
Counter-irritation to Epigastrium, 1. In collapse
Digitalis, 4. In sudden collapse after hæmorrhage; the tincture by the mouth, digitalin hypodermically
Ether, 4. In collapse from intestinal colic
Galvanism
Heat to Epigastrium, 1
Lavandula
Musk
Nitrite of Amyl, 1, 4. In sudden emergency, in fatty heart, in syncope during anæsthesia, and in hæmorrhage
Position. Head lowest and feet raised
Stimulants, 1. Undiluted
Veratrum Album. An errhine

Synovitis.

Aconite
Alcohol and Water. Equal parts
Antimony. Combined with saline purgatives
Arnica
Bandage or Strapping. Martin's elastic bandage in chronic
Blisters. Flying blisters at night in chronic synovitis; if not useful, strong counter-irritation
Calcium Sulphide. As a general tonic
Carbolic Acid, 2. Injections of 3j. of a 2 per cent. solution into the joint
Carbonate of Calcium
Cod-Liver Oil. Tonic
Conium, 1. In scrofulous joints
Heat

Synovitis.

Iodine. Injection in hydrarthrosis after tapping, or painted over
Iodoform, 1. Solution in ether, 1 in 5, injected into tuberculous joints; as a dressing after opening
Mercury. Scott's dressing in chronic strumous disease. Internally in syphilitic origin
Oleate of Mercury. To remove induration left behind
Potassium Iodide
Pressure, combined with rest
Shampooing and Aspiration, 1
Silver Nitrate, 2. Ethereal solution painted over
Splints
Sulphur

Syphilis.

Acid, Acetic, 1. Caustic to sore
Acid, Carbolic, 2. To destroy sore, mucous patches, condylomata, &c.; as bath in second stage
Acid, Nitric, 1, 3, 4. In primary syphilis, to destroy the chancre, especially when phagedenic. The nitro-hydrochloric acid in constitutional syphilis
Ammonium Iodide, 1. Prescribed with excess of the carbonate in tertiary symptoms; as ointment to nodes, &c., in nocturnal pains
Aurum, 2. In recurring syphilitic affections where mercury and iodide of potassium fail
Bamberger's Peptone, 1. Mercurialised
Benzoin, 2. Antiseptic dressing for ulcers
Bicyanide of Mercury, 1. To destroy mucous tubercles, condylomata, and to apply to syphilitic ulceration of the tonsils and tongue
Boric Acid. Like Benzoin
Calcium Sulphide
Calomel, 1, 2, 3, 4. For vapour bath in secondary; dusted in a mixture with starch or oxide of zinc over condylomata will quickly remove them
Camphor, 1. Dressing in phagedenic chancres
Cauterisation, 1
Cod-Liver Oil. Tonic in all stages
Creasote. Internally in strumous subjects, and where mercury is not borne
Denutrition, 2. Hunger-cure of Arabia
Guaiacum, 2, 4. Alterative in constitutional syphilis
Iodide of Iron, 3. In sloughing phagedena; in tertiary with anæmia
Iodide of Starch
Iodoform, 1, 2, 4. Dressing for chancre and ulcers
Iron, 1, 2, 3, 4. In anæmia, the stearate perchloride and iodide are useful
Lotio Flava. Dressing for syphilitic ulcers
Lotio Nigra. Dressing for syphilitic ulcers, and gargle in sore throat and stomatitis
Manganese, 2. In cachexia
Mercury, 1, 2, 3, 4. The specific remedy in one or other of its forms in congenital and acquired syphilis in primary or secondary stage
Oil of Mezereon. In constitutional syphilis
Oil of Sassafras. In constitutional syphilis
Phosphates, 4. In syphilic periostitis, &c.
Podophyllum, 1. Has been tried in secondary, with success after a mercurial course
Potassium Chlorate, 1, 2, 4. Local application of powder to all kinds of syphilitic ulcers, gargle in mercurial and specific stomatitis
Potassium Iodide, 1, 2, 3, 4. The specific for all forms of tertiary syphilis where there has been a mercurial course; also in combination with mercury
Salicylic Acid, 2. Antiseptic application
Sarsaparilla, 1, 2, 4. Alterative in tertiary
Soft Soap, 3. To syphilitic glandular swellings

Syphilis.

Stillingia, 2. Most successful in cases broken down by a long mercurial and iodide course which has failed to cure; improves sloughing phagedenic ulcers
Suppositories of Mercury, 1
Turkish and Vapour Baths, 2. To maintain a free action of the skin
Wet Pack
Zinc Chloride, 1, 3. Locally to ulcers as caustic

Tabes Mesenterica.

Alcohol
Arsenic. In commencing consolidation of the lung
Barium Chloride, 1. In scrofula
Calcium Chloride. In enlarged scrofulous glands
Cod-Liver Oil
Diet, plain and nourishing
Fatty Inunction, 1
Ferri Pernitratis, Liquor, 1. Hæmatinic and astringent
Gallic Acid, 1. Astringent in the diarrhœa of
Gelsemium, 2. In the reflex cough of
Iodine
Olive Oil. Inunction
Phosphates, 2. As tonic
Phosphoric Acid
Sarsaparilla

Tape-Worm.

Agrimonia, 1. Caffre remedy
Alanthus Glandulosa, 2. The oleoresin or decoction
Alum, 3. As injection
Areca Nut
Balsam of Copaiba, 1. In half-ounce doses
Carbolic Acid, 2
Chenopodium Oil, 4. 10 drops on sugar
Cocoa Nut, 1. A native remedy
Cod-Liver Oil. Tonic
Creasote, 1
Ether, 1, 4. An ounce and a half at a dose, followed by a dose of castor oil in two hours
Filix Mas, Oil of. Followed by purgative
Iron. Tonic
Kamala
Kousso
Mucuna, 4. Night and morning for three days, then brisk purgative
Myrzina Africana, 1. Used in Upper Egypt, to which it is native
Papaya, 1
Pelletierine, 3. The tannate
Pumpkin Seeds, 4. Pounded into an electuary, ʒij. at dose
Punica Granatum, 1, 4. The same as its chief alkaloid, pelletierine
Quinine. As tonic
Resorcin, 2
Salicylic Acid, 2. This and the preceding to be followed by a purgative
Sulphuric Acid, 1. The aromatic acid
Turpentine, 2
Valerian, 3. In convulsions due to the worms

Testicle, Diseases of.

Aconite. In small doses frequently repeated in acute epididymitis
Ammonium Chloride, 2. Solution in alcohol and water, topical remedy
Antimony, 3. In gonorrhœal epididymitis
Belladonna. In neuralgia of the testis. As an ointment with glycerine in epididymitis or orchitis

Testicle, Diseases of.

Collodion. By its contraction to exert pressure on, in gonorrhœal epididymitis
Compression, 1. At the end of an acute and beginning of a subacute attack, as well as chronic inflammation
Conium. Poultice of leaves in cancer
Copaiba, 1. In orchitis
Digitalis, 1. In epididymitis
Gold Salts. In acute and chronic orchitis
Hamamelis. In some patients gives rise to seminal emissions
Hot Lotions. In acute inflammation
Ice Bag, 2, 3. In acute orchitis
Iodine, 1, 2. Injection into an encysted hydrocele; local application in orchitis after the acute symptoms have passed off
Iodoform, 1, 2. Dressing in ulceration
Magnesium Sulphate. With antimony in epididymitis
Mercury and Morphine Oleate, 1, 2, 3. In syphilitic enlargement and chronic inflammation
Nitrate of Silver, 2, 4. Ethereal solution painted around an enlarged testis better than over
Nux Vomica. In debility
Phosphoric Acid and Phosphates. In the same condition
Potassium Bromide
Potassium Iodide. In syphilitic testicle
Pulsatilla. In very small doses along with aconite
Suspension. In orchitis and epididymitis

Tetanus.

Aconite, 1. In large doses to control muscular spasm
Acupuncture, 1. On each side of the spines of the vertebræ
Alcohol, 1. Will relax muscular action, also support strength
Anæsthetics, 1. To relax muscular spasm
Antimonium Tartaratum, 1. In large doses, along with chlorate of potassium
Apomorphine. As a motor paralyser
Arsenic
Atropine, 1, 2. Local injection into the stiffened muscles to produce mild poisoning. Useful both in traumatic and hysterical tetanus
Bromide of Potassium, 1, 2, 4. In very large doses frequently repeated does good
Cannabis Indica, 1, 4. Serviceable in many cases; best combined with chloral
Chloral, 1, 2, 3, 4. In large doses; best combined with bromide or cannabis indica
Conium, 1, 3. Injection of ℥xv. every two hours of the following formula, increasing the dose, has done good. ℞ Coninæ, ℥ij.; Acidi sulphurici dil. ℥j.; Aquæ, ʒj.
Curare, 2. An uncertain drug
Duboisine, 2. Like atropine
Freezing the Nerve, 1. In traumatic tetanus has been proposed
Gelsemium, 2, 3. In a few cases it has done good
Heat to Spine, 1. Will arrest convulsions
Hyoscyamus. In traumatic
Ice-bag to Spine, 1
Lobelia, 4. A dangerous remedy
Morphine, 2. Injected into the muscles gives relief
Nerve-stretching, 1. Where a nerve is implicated in the cicatrix has done good
Neurotomy, 1. In the same cases
Nicotine, 1, 2. Cautiously administered relieves the spasm; best given by rectum or hypodermically; by the mouth it causes spasm which may suffocate

Tetanus.

Nitrite of Amyl, 1, 2, 3, 4. In some cases it cures
Nitro-glycerin, 2. Like the preceding
Opium, 1. Alone or with chloral
Physostigma, 2, 3, 4. The liquid extract pushed to the full. Given by the mouth, or rectum, or hypodermically
Quinine, 1. In both idiopathic and traumatic tetanus
Strychnine, 1, 2. The evidence, which is doubtful, seems to show that it is beneficial in chronic and idiopathic tetanus; should only be given in a full medicinal dose
Vapour Baths
Warm Baths

Thread-Worm (*Oxyuris Vermicularis*).

Aconite, 2. In the fever produced
Alum, 3. Injections
Asafœtida with Aloes, 1
Carbolic Acid, 1. Solution, gr. ij. to ʒj. in doses of ʒj.; or as enema
Castor Oil
Chloride of Ammonium, 3. To prevent accumulation of intestinal mucus, which serves as nidus
Common Salt, 3. Along with antimony to remove catarrhal state of intestine, or alone as enema
Enema Aloes
Enema Quassiæ, 1, 2, 3. Or infusion by mouth
Ether (Sulphuric), 1. Injection of solution of ℥xv. in water
Eucalyptol, 2, 3. Injection
Ferri Perchloridi, Tinct., 1, 3. Enema
Lime Water. Enema
Mercurial Ointment, 1. Introduced into the rectum relieves itching and is anthelmintic
Oleum Cajuputi, 4
Ol. Olivæ, 1
Ol. Terebinthinæ
Santonica, 3
Santonin, 3
Scammony, 3. For thread-worms in rectum
Tannin. Enema
Tonics
Vinegar. Enema, diluted with twice its bulk of water

Throat, Sore.

Aconite. In acute tonsillitis with high temperature; in the sore-throat of children before running on to capillary bronchitis; best given frequently in small doses
Alcohol, 3. Gargle in relaxed throat
Alum, 3, 4. Gargle in chronic relaxed throat, simple scarlatinal and diphtheritic sore-throat
Arsenic, 3. In coryza and sore-throat simulating hay fever; in sloughing of the throat
Balsam of Peru
Balsam of Tolu
Belladonna, 1, 3, 4. Relieves spasm of the pharyngeal muscles; also when the tonsils are much inflamed and swollen
Capsicum, 3. As gargle in relaxed sore-throat
Carbolic Acid, 4. As a spray in relaxed sore-throat and in coryza
Catechu. Astringent gargle
Chlorine Water, 4. Gargle in malignant sore-throat.
Cimicifuga, 2. In combination with opium and syrup of tolu in acute catarrh
Cold Compresses, 3. In tendency to catarrh
Electric Cautery, 1. In chronic sore-throat, to get rid of thickened patches

Throat, Sore.

Ferri Perchloridum. Gargle in relaxed sore-throat
Glycerine of Tannin, 3. To swab the throat with in the same condition
Guaiacum, 1. Sucking the resin will abort or cut short the commencing quinsy
Hydrastis, 2. Gargle in follicular pharyngitis and chronic sore-throat
Ice, 1, 3. Sucked, gives relief
Iodine, 1, 3. Locally to sores and enlarged tonsil
Ipecacuanha, 3. As spray in congestion of upper pharynx
Liq. Ammonii Acetatis. In full doses
Magnesium Sulphate. To be given freely in acute tonsillitis
Mercury, 3. In very acute tonsillitis grey powder or calomel in small doses
Mercury and Morphine Oleate. In obstinate and painful sore-throat
Myrrh. Gargle in ulcerated sore-throat
Nitric Acid. As alterative with infusion of cinchona
Phytolacca. Internally, and as gargle
Podophyllum. Cholagogue purgative
Potassium Chlorate. Chief gargle
Potassium Nitrate. A ball of nitre slowly sucked
Pulsatilla, 2. In acute coryza without gastric irritation
Sanguinaria, 2. The tincture sprayed in extended chronic nasal catarrh
Silver Nitrate, 3, 4. Solution in sloughing of the throat or chronic relaxation; saturated solution an anæsthetic and cuts short inflammation
Sodium Borate, 1. In clergyman's sore-throat
Sodium Salicylate, 3. In quinsy
Steam. Of boiling water, and vapour of hot vinegar
Sulphurous Acid, 3. Spray
Sumach, 4. The berries infused and addition of potassium chlorate a most efficient gargle
Tracheotomy
Veratrum Viride. To control any febrile change
Zinc Chloride
Zinc Sulphate, 1. A gargle

Tic Douloureux.

Aconitine, 2. Formula: Aconitinæ (Duquesnel's), gr. $\frac{1}{10}$; Glycerini, Alcoholis, aa. ℥j.; Aq. menth. pip., ad ℥ij.; dose ℥j. cautiously increased to ℥ij.
Ammonium Chloride, 3. In large dose
Amyl Nitrite, 1. In pale anæmic patients
Anæsthetics quickly relieve, 2
Arsenic, 3. Occasionally useful
Atropine, 3. Hypodermically, and ointment
Butyl-Chloral Hydrate
Caffeine
Cannabis Indica
Cautery in Dental Canal, 1. Where pain radiated from mental foramen
Chamomile
Chloroform, 3. Inhalation, hypodermically
Counter-irritation
Cupric Ammonio-Sulphate, 1. Relieves the insomnia
Delphinine. Externally
Electricity
Gelsemium, 3, 4. Valuable
Glonoine, 1. In obstinate cases
Heat
Hyoscyamus
Iron, 1. In combination with strychnia; the following formula is good: Ferri potassio-tartratis, ℈iv.; Vin. opii, ℥iss.; Aq. cinnam. ad ℥viij. ℥j. ter die sumenda
Laurocerasi, Aqua

Tic Douloureux.

Ligature of the Carotids, 1. In obstinate cases a last resort. Has done good
Morphine, 3. Hypodermically
Ol. Crotonis, 1. Sometimes cures; will relieve
Phosphorus, 3. In obstinate cases
Physostigma
Potassium Iodide. The following formula relieves: ℞ Chloral, gr. v.; Potassii iodidi, gr. iij.; Sp. ammoniæ co., ℥i.; Infusum gentianæ, ad ℥j. Alone in syphilitic history
Pulsatilla, 1. Relieves
Salicin, 1. Instead of quinine, where pain is periodic
Stramonium
Veratrine, 3. Ointment
Valerian, 1. ℞ Zinci valerianatis, Quininæ valerianatis, aa. gr. xii.; Extracti Hyoscyami, gr. xxiv., fiat pilulæ duodecim., una ter die sumenda

Tinea Circinata.

Boric Acid, 1, 2. In simple or ethereal solution
Carbolic Acid, 2. Solution, or glycerine of carbolic acid
Chromic Acid
Cod-Liver Oil
Copper, Carbonate
Goa Powder. As ointment, or moistened with vinegar
Kamala, 1
Oil of Cade
Sulphites, 2. Or sulphurous acid
Sulphur Baths, 2. Faithfully carried out

Tinea Decalvans, *vide* Alopecia.

Tinea Favosa.

Calcium Sulphide
Carbolic Acid, 1. Lotion
Cleanliness
Epilation, 1. Followed up by using a parasiticide
Hyposulphites
Mercury, 3. A lotion of the bichloride, gr. ij. ad ℥j.; or the oleate of mercury ointment
Nitric Acid, 1. Caustic after the crust has been removed
Oil. To soften and remove scabs
Oleander
Petroleum, 1. One part to two of lard after crusts are gone
Sulphides
Sulphurous Acid, 3. The glycerine of the B.P. preparation assisted by epilation
Turkish Bath, 1. Followed by the use of carbolic soap, instead of ordinary
Viola Tricolor
Zinc Chloride, 1. Dilute watery solution

Tinea Tarsi.

Blisters to Temple, 3
Epilation, 1, 3. Removal of scabs and application of stick of lunar caustic
Mercury, 1, 3. After removal of scabs, Ung. hydrargyri nitratis diluted to half its strength; also ℞ Plumbi acetatis, ℥j.; Ung. hydrargyri oxidi rubri, ℥j.; Zinci oxidi, ℥j.; Calomelanos, ℥ss.; Adepis, ℥ij.; Olei palmat. ℥v.; ft. ung.; also Oleate
Tinct. Iodi, 1. After removal of scabs followed by application of glycerine
Ung. Picis, 1. Touched along edge of tarsi

Tinea Tonsurans.

Acetic Acid, 3. Strong locally
Acetum Cantharidis, 1
Arsenic, 1. Tonic
Boric Acid, 1. Ethereal solution after head is thoroughly cleansed
Carbolic Acid, 1, 3. In early stages
Chrisma, 1. A derivative from petroleum. A parasiticide
Chrysophanic Acid, 1. Gr. xxx. to ʒj. as ointment
Cocculus Indicus
Cod-Liver Oil
Coster's Paste. Iodine ʒij., Oleum cadini, ʒij.
Creasote
Croton Oil, 1, 3. Liniment followed by a poultice
Epilation
Iodine, 1, 3. The tincture in children
Menthol, 1. Parasiticide and analgesic
Mercury, 1, 3. White precipitate lightly smeared over, the oleate, pernitrate and oxide as ointments. The bichloride as a lotion gr. ij. ad ʒj.
Oil of Naphtha
Salicylic Acid, 1. Strong solution in alcohol, gr. xl. ad ʒj., or gr. xl. to vaseline ʒj.
Sodium Ethylate
Sulphurous Acid, 1, 3
Sulpho-cyanide of Potassium
Thymol. Like menthol

Tongue, Diseases of.

Bicyanide of Mercury, 1. In mucous tubercles
Borax. In chronic superficial glossitis; and in fissured tongue
Cinnamon. To flavour
Cloves. As gargle
Cochlearia Armoracia, 1. As gargle
Conium
Frænulum. Should be divided in tongue-tie
Ginger. Masticatory
Hydrastis. In stomatitis
Iodine
Iodoform. To ulcers
Mercury. In syphilitic disease
Mezereon, Oil of. Sialagogue
Nitric Acid. In dyspeptic ulcers; the strong acid as caustic
Nux Vomica
Pepper. Condiment
Phytolacca
Potassium Bromide
Potassium Chlorate. In aphthous ulceration, chronic superficial glossitis, stomatitis
Potassium Iodide. In tertiary specific ulceration, and in macroglossia
Pyrethrum. Masticatory
Rhus Toxicodendron
Silver Nitrate. Caustic to ulcers
Xanthoxylum, 2. In lingual paralysis
Zinc Chloride. Caustic

Tonsillitis, *vide* Throat, Sore.

Tonsils, Enlarged.

Aluminium Sulphate. Locally applied
Ammonium Iodide
Catechu. Astringent gargle
Excision
Fel Bovinum, 1. Inspissated, rubbed up with conium and olive oil as an ointment to be painted over
Ferri Perchloridi, Tinctura. Astringent in chronically enlarged tonsils
Iodine Tincture. To cause absorption

Tonsils, Enlarged.

Massage, 1. Of the tonsils
Silver Nitrate. Caustic
Tannin, 1. Saturated solution of fresh tannin

Tonsils, Ulcerated.

Cantharides. As vesicant
Coptis. Gargle
Iron. Gargle
Lycopodium. To dust over
Magnesium Sulphate. Free purgation with
Mercuric Iodide. In scrofulous and syphilitic ulceration
Potassium Chlorate. Gargle
Potassium Iodide. In tertiary syphilis
Sulphurous Acid. Pure or B.P. mixed with equal quantity of glycerine and painted over

Toothache.

Aconite, 3. Liniment or ointment in facial neuralgia if due to decayed teeth
Alum, 2. A solution in nitrous ether locally applied
Argenti Nitras. The solid applied to the clean cavity and the mouth then gargled
Arsenic, 1, 3. Caustic to destroy the dental nerve
Belladonna
Butyl-Chloral, 1, 3. In neuralgic toothache
Calcium Salts
Camphor. Rubbed on gum, or dropped on cotton wool and placed in tooth
Camphor and Chloral. Liniment to relieve facial neuralgia
Capsicum, 3. A strong infusion on lint
Carbolic Acid, 2. A single drop of strong, on cotton wool placed in cavity of tooth
Chamomile
Chloral, 1. Solution in glycerine one in four, or solid in cotton wool to be applied to the hollow tooth
Chloroform, 1, 3. Into ear or tooth on lint; a good liniment with creasote; or injected into the gum
Cocaine, 3. The hydrochlorate into a painful cavity
Colchicum. Along with opium in rheumatic odontalgia
Collodion, 3. Mixed with melted crystallised carbolic acid, and put into cavity on cotton wool; first increases and then diminishes pain
Coniine, 3. Solution in alcohol on cotton wool and put into tooth
Creasote. Like carbolic acid
Croton Oil
Electricity
Gelsemium, 1, 3. To relieve the pain of a carious tooth unconnected with any local inflammation
Ginger
Glonoine
Iodine, 3. Painted on to remove tartar on teeth, and in exposure of fang due to atrophy of gum
Mercury. As alterative and purgative
Morphine. Subcutaneously injected
Nitric Acid. To destroy exposed nerve
Nux Vomica
Oil of Cloves, 2, 4. Dropped into the cavity of a hollow tooth
Opium, 2. Dropped into cavity
Pellitory, 4. Chewed
Potassium Bromide
Pulsatilla, 1. In rheumatic odontalgia
Quinine. In full dose
Resorcin, 2. Like creasote
Sodium Bicarbonate, 1, 2. Saturated solution to rinse mouth with
Tannin, 1, 2. Ethereal solution dropped into carious tooth
Zinc Chloride, 1, 3. To destroy exposed pulp

Torticollis.

Aconite. Liniment externally; and tincture internally
Arsenic, 1. Controls and finally abolishes spasm
Belladonna. Liniment
Capsicum, 3. Strong infusion applied on lint and covered with oiled silk
Cimicifuga
Conium, 1. Due to spasmodic action of the muscles
Electricity, 2. Galvanism to the muscles in spasm; faradic to their paretic antagonists
Local Pressure, 1
Massage, 1
Nerve-stretching, 1
Nux Vomica
Water, 2. Hot douche

Trismus.

Aconite
Anæsthetics. To allay spasm
Belladonna, 1. Extract in large doses
Cannabis Indica
Chloral, 4. In T. neonatorum, one grain dose by mouth or two by rectum when spasms prevent swallowing
Conium. The Succus is the most reliable preparation
Ether
Gelsemium
Opium
Physostigma

Tumours.

Anæsthetics. To detect the presence of phantom tumours; also to relax abdominal walls to permit deep palpation of abdomen

Tympanites.

Acids, 1. After meals
Alkalies, 1. Before meals with a simple bitter
Arsenic
Asafœtida, 4. As an enema
Aspiration, 1. To relieve an over-distended gut
Bismuth, 1
Capsicum
Carbolic Acid, 1. Or creasote in tympanites due to fermentation
Chamomile, 1. Enema
Chloral, 1. As an antiseptic to fermentation in the intestinal canal
Cocculus Indicus
Colchicum
Cubebs, 1. Powdered in T. after strangulated hernia
Galvanism, 1. In old cases, especially of lax fibre
Ginger
Glycerine. Associated with acidity
Hyoscyamus
Ice Poultice, 1. Prepared by mixing linseed meal and small pieces of ice; in tympanites of typhoid fever
Iris
Nux Vomica
Ol. Terebinthinæ, 1. Very efficient as enema, not for external application
Plumbi Acetas. When due to want of tone of intestinal muscular walls
Rue, 1. Very effectual
Sumbul, 1
Vegetable Charcoal, 1. In gruel, in flatulent distension of the colon associated with catarrh; dry, in flatulent distension of the stomach

Typhlitis.

Arsenic
Belladonna
Ice Bag, 2, 3. Or poultice over the cæcum
Leeches, 2. At once as soon as tenderness is complained of, unless subject is too feeble
Magnesium Sulphate, 2. Only when disease is due to impaction of cæcum
Metallic Mercury
Opium, 2. Better as morphine subcutaneously
Veratrum Viride

Typhoid Fever, *vide* Fevers.

Aconite, 1, 2, 3. To reduce the pyrexia
Alcohol, 2, 4. Valuable, especially in the later stages
Alum, 3. To check the diarrhœa
Antipyrin, 4. To lower the temperature
Argenti Nitras, 1, 2. To check diarrhœa; in obstinate cases along with opium; should not be given until the abdominal pain and diarrhœa have begun
Arnica, 2. Antipyretic
Arsenic, 1, 2. Liquor arsenicalis with opium to restrain the diarrhœa
Baths, 1, 2, 3. Agreeable to patient, and reduce hyperpyrexia
Belladonna, 1. During the pyrexial stage it lowers the temperature, cleans the tongue, and steadies the pulse; afterwards it brings on irritability of heart
Bismuth, 2. To check diarrhœa
Calomel, 2. Gr. x. first day, and eight each day after, the German specific treatment. 3. In small continuous doses without producing stomatitis
Calx Saccharata, 1. With milk when the tongue is black and parched
Carbolate of Iodine, 2. One drop of tincture of iodine and of liquefied carbolic acid, out of infusion of digitalis, every two or three hours
Carbolic Acid, 1, 2. Cuts short the attack
Carbonate of Ammonium, 3
Charcoal, 1. To prevent fetor of stools, accumulation of fetid gas, and to disinfect stools after passage
Conchinin, 1. Synonym, Quinidine; equal to quinine
Creasote, 1. Like carbolic acid
Digitalis, 1, 3. To lower temperature and pulse-rate; death during its use has been known to occur suddenly
Ergot, 1, 3. For intestinal hæmorrhage
Eucalyptus, 1. Thought to shorten disease
Ferri Perchloridi, Tinctura
Hydrochloric Acid, 1, 2. To diminish fever and diarrhœa
Hyoscyamus
Iodine, 1, 2. Specific German treatment; use either liquor or tincture
Lead Acetate, 3. To check diarrhœa
Mercury, 3. The perchloride, ♏x. of the liquor every two or three hours
Opium, 3. To check delirium and wakefulness at night, and to relieve the diarrhœa
Phosphoric Acid. Cooling drink
Potassium Iodide, 1. Alone or with iodine
Quinine, 1, 2, 3, 4. In large doses to reduce the temperature
Resorcin, 2. Antipyretic
Salicylic Acid, 1, 2, 3, 4. Some hold that it is good in the typhoid of children, many that it does great harm
Sodium Benzoate, 2. Antipyretic
Sulpho-carbolates. Proposed as internal antiseptics
Tartar Emetic. In pulmonary congestion
Turpentine, 1, 2, 3, 4. In the bad symptoms at the end of the second week, ♏x. every two hours, and every three hours in the night; specific if the diarrhœa continue during convalescence

Typhus Fever.

Aconite
Alcohol, 4. Where failure of the vital powers threatens
Antimony, 3. Combined with opium, in pulmonary congestion, wakefulness, and delirium
Arnica, 2. Antipyretic
Baths, 1, 2, 3, 4. To reduce temperature; instead of baths, cold compresses, &c., may be used
Belladonna, 3, 4. Cleans the tongue, steadies and improves the pulse; too long usage makes the heart irritable
Calx Saccharata. With milk in the black and coated tongue
Camphor
Chloral, 3, 4. In wild delirium in the earlier stages of the fever, but not in the later
Chlorine Water, 4. Not much used now
Cod-Liver Oil
Counter-irritation
Cuca, 1. Tentative
Diet. Nutritious
Digitalis, 1, 4. To increase the tension of the pulse and prevent delirium; if a sudden fall of pulse and temperature should occur during its administration it must be withheld
Expectant Treatment
Hyoscyamus
Musk
Opium
Phosphoric Acid. Agreeable drink
Potassium Chlorate. In moderate doses
Potassium Nitrate. Mild diuretic and diaphoretic
Quinine. In full doses to pull down temperature
Salicylic Acid, 4. Antipyretic
Strychnine, 1. Where the circulatory system is deeply involved
Turpentine, 1. In the stupor
Yeast, 1, Accelerates the course of the disease

Vomiting.

Acids, 3. In acid eructations, given immediately after food
Alcohol, 2. Iced champagne, in sea-sickness, &c. Hot brandy is also useful
Alkalies, 2. Especially effervescing drinks
Alum, 3. In doses of five to ten grains in phthisis, when vomiting is brought on by cough
Ammonium Carbonate
Ammonio-Citrate of Iron, 1. In the vomiting of anæmia, especially of young women
Apomorphine. To empty the stomach of its contents
Arsenic, 2, 3. In the vomiting of cholera; in chronic gastric catarrh, especially of drunkards; chronic, not acute gastric ulcer, and chronic painless vomiting
Bicarbonate of Sodium, 3. In children 3ss. to 3j. to the pint of milk. If this fails, stop milk. In acute indigestion with acid vomiting
Bismuth, 2, 3, 4. In acute and chronic catarrh of the stomach or intestine
Blisters. In vomiting due to renal and hepatic colic
Bromides, 2, In cerebral vomiting and cholera infantum
Calcium Phosphate
Calomel, 2. In minute doses in cholera infantum and similar intestinal troubles
Calumba. A simple bitter and gastric sedative
Carbolic Acid, 2, 4. In irritable stomach, along with bismuth; alone if due to sarcinæ or other ferments; in Asiatic cholera and cholera infantum
Carbonic Acid Waters, 3. With milk
Cerium Oxalate, 3, 4. In doses of gr. j. in sympathetic vomiting

Vomiting.

Chloral, 2. In sea-sickness and reflex vomiting
Chloroform, 2, 3. In drop doses in sea-sickness, and in reflex vomiting such as passage of calculi
Cocaine
Creasote. Like carbolic acid
Electricity, 1. In nervous vomiting the constant current positive pole on last cervical vertebra, and negative over stomach
Emetics. If due to irritating substances
Ether, 2. Like chloroform
Eucalyptus, 3. In vomiting due to sarcinæ
Gelatin, 3. To the food of babies who suffer from chronic vomiting of lumps of curded milk
Horseradish
Hydrocyanic Acid. In cerebral vomiting, vomiting of phthisis, and of acute disease of stomach
Ice. Sucked
Ice Bag, 1. To spine or epigastrium
Iodine. The liquor in 3–5ℳ doses
Ipecacuanha, 1, 2, 3, 4. In sympathetic nervous vomiting, in minute doses; in the vomiting of children from catarrh, and the vomiting of drunkards
Iris
Koumiss, 1. Diet and food in obstinate cases
Leeches, 1. To epigastrium if tender, especially in malarial vomiting
Lime Water, 3, 4. In chronic vomiting with milk, especially in the case of children. The saccharated is laxative
Magnesia, 3. In sympathetic vomiting
Mercury, 3. In vomiting with clayey stools; *vide* Calomel
Morphine, 1, 3. Hypodermically injected in the epigastrium in persistent sea-sickness
Nitrite of Amyl, 2. In concentrated form in sea-sickness
Nitro-glycerin, 2, 3. Like nitrite of amyl
Nutrient Enemata, 2, 3. In persistent vomiting
Nux Vomica, 2, 3. In atonic dyspepsia
Opium, 4. As a suppository in severe acute vomiting, especially associated with obstinate constipation, which is relieved at the same time
Pepsin, 2. In the vomiting of dyspepsia
Potassium Iodide. In very small doses
Pulsatilla. In catarrh
Quinine, 3. In sympathetic vomiting
Silver Nitrate. In nervous derangement
Spiritus Nucis Juglandis, 1. Relieves or cures in sympathetic vomiting and gastric irritability
Sulphurous Acid, 1. If due to sarcinæ
Tartar Emetic. If due to irritating substances or poisons
Veratrum. In vomiting of summer diarrhœa
Zinc Sulphate. Emetic

Vomiting of Pregnancy.

Aconite, 1, 4. In full doses, so long as physiological effect is maintained
Arsenic, 2. Where the vomit is blood, or streaked with blood, drop doses of Fowler's solution
Belladonna, 1. Either internally, or plaster over the hypogastrium
Bismuth, 1. Along with pepsin
Bromide of Potassium, 1, 4. Controls in some cases in large doses
Calcium Phosphate, 1
Calomel, 1. In small doses to salivate, or one large dose of 10 gr.
Calumba, 1. Occasionally successful
Carbolic Acid, 1, 2. An uncertain remedy
Caustics, 1. To the cervix if abraded
Cerium Oxalate, 1. The chief remedy
Champagne

Vomiting of Pregnancy.

Chloral, 1, 3
Cocaine, 1, 3. 10 m. of a 3 per cent. solution will relieve and cure in a few doses
Coffee, 1. Before rising
Creasote, 3
Dilatation of the Os Uteri
Electricity, 1. Same as in nervous vomiting
Hydrocyanic Acid, 2. Sometimes useful, often fails
Ingluvin
Iodine, 2. A drop of tincture or liquor as a last resort
Ipecacuanha, 3, 4. In minim doses relieves
Koumiss. As diet
Morphine, 1, 3. Suppository introduced into the vagina; no abrasion should be present or there may be symptoms of poisoning
Naphtha, 1. 1 or 2 drops
Nux Vomica, 2. 1 and 1-2 drop doses of tincture
Pepsin, 1, 2. Like ingluvin but not so successful
Plumbic Acetate, 1. In extreme cases
Potassium Iodide, 1. Like iodine
Quinine, 3. Sometimes useful
Salicin
Spinal Ice-bag, 2

Warts.

Acetic Acid, 1. Touched with the glacial acid
Alum, 1. Saturated solution in ether
Antimonic Chloride
Arsenious Acid
Caustic Alkalies
Carbolic Acid
Chloral
Chromic Acid
Corrosive Sublimate
Creasote
Mercuric Nitrate, 3
Nitric Acid
Permanganate of Potassium, 1
Phosphoric Acid
Potassæ, Liquor, 3
Poultice
Salicylic Acid, 3. Saturated solution in collodion, with extract of Indian hemp
Rue
Savin
Silver Nitrate, 1. In venereal warts along with savin
Sodium Ethylate, 1
Staves acre
Sulphur

Wen.

Extirpation

Wounds.

Aconite
Alcohol, 2. In pyrexia; antiseptic and astringent dressing
Aloes, 3. Topical stimulants
Aluminium Acetate
Anhydrous Dressings
Balsam of Peru
Benzoin
Blotting Paper, 1. As lint, saturated with an antiseptic

Wounds.

Boric Acid
Calamine, 1
Calendula
Carbolated Camphor, 1
Carbolic Acid, 2, 3, 4
Charcoal
Chloral, 1. Antiseptic and analgesic
Collodion, 1, 3. To exclude air
Conium
Eucalyptus
Glycerine, 1
Hamamelis, 3. On lint to restrain oozing
Heat
Iodine
Iodoform, 3
Lead Dressings, 1
Nitrate of Silver. To destroy unhealthy granulations
Nitric Acid
Oakum
Opium
Petroleum
Permanganate of Potassium
Potassium Chlorate, 1
Poultices
Salicylic Acid
Sodium Chloride. ½ per cent. solution
Styptic Colloid, 1. To prevent bedsores, &c.
Sugar
Sulphurous Acid, 1, 3
Tannin
Turkish Baths
Turpentine
Yeast in hospital phagedæna
Zinc Sulphate and Chloride

Yellow Fever.

Aconite
Arsenic
Belladonna
Camphor
Cantharides
Capsicum
Carbolic Acid, 1, 2. Subcutaneously and by the stomach
Champagne, 2. Iced
Chlorate of Potassium
Chlorodyne
Cimicifuga
Ergot, 1. To restrain the hæmorrhage
Gelsemium
Iodide of Potassium
Ipecacuanha
Lead Acetate
Liquor Calcis
Mercury
Nitrate of Silver
Nitro-hydrochloric Acid
Nux Vomica
Quinine, 1. In some cases good, in others harmful
Salicylic Acid
Sodium Benzoate, 1. By subcutaneous injection
Sodium Salicylate
Stimulants
Sulphur Baths
Sulphurous Baths
Tannic Acid
Tartar Emetic
Turpentine, 2. For vomiting
Vegetable Charcoal
Veratrum Viride

BIBLIOGRAPHICAL INDEX.

ACIDS.

Bertram, Z. f. Biol., xiv. p. 558
Bobrik, Königsberger Diss., 1863
Brunton and Cash, Phil. Trans., pt. i. 1884, p. 231
Buchheim, Arch. f. physiol. Heilk., 1857, p. 122; Pflüger's Arch., Bd. xii., 1876
Cook, Pract., vol. xxvii.. p. 328
Cyon, Arch. f. Anat. u. Physiol., 1866, p. 416
Edelfsen, Centralbl. f. d. med. Wiss., 1878, p. 513 (Phosphoric acid)
Elsässer, Die Magenerweichung d. Säuglinge, 1846
Feitelberg, Dorpat. Diss., 1883
Gähtgens, Centralbl. f. d. med. Wiss., 1872, vol. x. p. 833
Gamgee, Centralbl. f. d. med. Wiss., 1879, p. 253 (different kinds of Phosphoric acid)
Gaskell, Journ. of Physiol., vol. iv. p. 48
Goltz, Virch. Arch., Bd. xxvi. p. 1
Guttmann, Arch. f. path. Anat., lxix. p. 534
Heiss, Zeitschr. f. Biologie, 1876, Bd. xii. p. 151
Hermann, Toxicolog., 1874, p. 160
Hertwig, Thierheilkunde
Hofbauer, Rossbach's Pharmacol. Unters., Bd. iii.
Hofmann, Zeitschr. f. Biologie, 1871, Bd. vii. p. 338
Höppener, Dorpat. Diss., 1863
Kobert, Schmidt's Jahrb., Bd. clxxix. p. 225
Koch, Zeitschr. f. rat. Medicin, 3. R. Bd. xxiv. p. 264
Kühne, Unters. üb. d. Protoplasma, Leipzig, 1864
Kurtz, Joh., Alkalientzieh. a. d. Thierk., Dorpat. Diss., 1874; u. Centralbl. f. d. medicin. Wiss., 1874, vol. xii. p. 569
Lassar, O., Pflüger's Arch., 1874, vol. ix. p. 44
Leyden u. Munk, Virch. Arch., Bd. xxii. p. 237
Maly, Liebig's Annal., Bd. clxxiii. p. 227, 1874
Meissener, G., Zeitschr. f. rat. Med., 3. R. Bd. xxiv. p. 97
Miquel, Arch. f. physiol. Heilk., 1851, p. 479
Onsum, Arch. f. path. Anat., Bd. xxviii.
Piotrowski, Dorpat. Diss., 1856
Quincke, Corr.-Blatt. f. Schweizer Aerţze, iv. No. 1, 1874
Salkowski, Virch. Arch., Bd. lviii. p. 460
Sieber, N., Journ. f. pract. Chemie, N. F., Bd. xix. 1879, p. 433 (Antiseptic action)
Strassburg, Pflüger's Arch., Bd. iv. p. 454
Strübing, A. f. exp. Path. u. Pharm., Bd. vi. 266 (Phosphoric acid)
Szabó, Z. f. physiol. Chem., i. p. 140 (complete literature of the acids in gastric juice)
Trachtenberg, Dorp. Diss., 1861
Walter, Arch. f. exp. Path. u. Pharm., 1877, p. 148
Zülzer, Virch. Arch., Bd. lxvi. pp. 223 and 282 (Phosphoric acid)

ACONITINE.

Achscharumoff, Reichert u. Du Bois's Archiv, 1866, p. 255; Schmidt's Jahrb., cxxxvi. p. 157, 1867
Anrep, V., Arch. f. Anat. u. Phys., 1880, p. 161
Berthemot, Pharmaz. Centralbl., 1837, p. 733
Böhm u. Ewers, Arch. f. exp. Path. u. Pharm., Bd. iii. p. 385
Böhm und Wartmann, Verh. d. physik. med. Ges. in Würtzburg, N.F., Bd. iii.
Brodie, Phil. Trans. 1811, p. 178
Coulson, Schmidt's Jahrb., xix. 285
Cramoisy, E. P., Paris, J. B. Baillière & fils, p. 30, 1865
Debout & Gubler, Schmidt's Jahrb., cxxv. 19, 1864
Dyce Duckworth, Brit. Med. Journ., vol. i. p. 224, 1861; Schmidt's Jahrb., cxi. p. 23, 1861
Ewers, C., Dissert. über Aconitine, Dorpat, 1873
Ferrand, De l'Aconit., Lyon, Chauvine, 1861
Fleming, An Inquiry into the Phys. & Medicinal Properties of the Aconitum napellus, Edinb. 1845
Fothergill, Digitalis, London, 1871, p. 6
Fristedt, Nord. Med. Ark., iii. 3, No. 18, p. 38, 1871
Geiger, Hesse, Brandes Pharmaz. Centralbl., 1835, p. 85
Gréhant & Duquesnel, Bull. gén. de Thérap., Aug. 1871, p. 492
Gubler, Bull. gén. de Thérap., lxvi. p. 385, May, 1864
Guillaud, Arch. de Phys. norm. et path., 1875, p. 766
Hahn, Essai sur l'Aconit, Strasbourg, 1863
Harley, St. Thomas's Hosp. Reports, v. p. 149
Hottot et Debout, Bull. Thér., lxvi. p. 360, Apr. 1864
Janus, Corn., de Man. Spec. Medic. inaug. de Aconito, Lugd. Batav., 1841, 8vo. p. 68
Lewin, Prüger Vierteljahrs., Bd. cxxxi. p 20; Cent. f. d. med. Wiss., 1875, p. 401
Liégeois & Hottot, Journ. de Physiol., iv. p. 520, Oct 1861; Schmidt's Jahrb., cxiv. p. 291, 1862; Bull. de Thérap., Paris, lxv. p. 208, 1863
Mackenzie & A. Guillaud, Arch. d. Physiol., 1875, p. 766
Mackenzie, G. H., London Practitioner, xx. p. 100
Mammi, Dell'Aconito Napello, Reggio, 1866, p. 30
Nunneley, F. B., Proceed. of the Royal Society, vol. xviii. p. 46, 1870
Orfila on Poisons (translated by Waller), 7th ed. vol. ii. p. 46
Pereira, Elements of Mat. Med., 4th ed. ii. pt. ii. p. 684
Praag, L. von, Virchow's Archiv, Bd. vii. 438-478, 1854
Ringer, S., and W. Murrell, Journ. of Phys., i. p. 232, Nos. 4, 5

ACONITINE.

Rosenthal, J., Sitzungsber. d. phys. med. Ges. zu Erlangen, 1876, 6. Juni
Schroff, Von, sen., Präger Vierteljahrs., xlii. p. 129, 1854 ; Oest. med. Jahrb., xvii. p. 57, 1861; Schm. Jahrb., cxii. 15, 1861
Schulz, Marburger Diss., 1846
Simon u. Sobernheim, Handb. d. Tox., p. 60
Skey, Froriep's Not., ii. 80, 1837, Schmidt's Jahrb., xvii. p. 306
Soubeiran, Schmidt's Jahrb., xix. 285
Turnbull, On the Preparations and Medical Properties of the Natural Order Ranunculaceæ, London, 1835 ; Froriep's Not., i. 302, ii. 252, 1837 ; Schmidt's Jahrbuch, xix. 285
Weyland, Eckhard's Beitr., v. 1, p. 29
Wibmer, Wirkungen, i. p. 33

ALCOHOL.

Anstie, Stimulants and Narcotics, London, 1864 ; Lond. Practitioner, viii. p. 148, Mar. 1872, July, 1874 ; Lond. Med. Review, 1862 ; Reprint, Lancet, ii. Sep. 13, 1865, p. 343
Baudot, E., L'Union Médicale, 1863
Béchamp, London Lancet, 1873, vol. i. p. 846
Bernard, Cl., Leçons sur les Effets des Substances toxiques, Paris, p. 397 ; Gaz. Méd. de Paris, 1856, p. 295
Binz, Virchow's Archiv, 1871, iv. p. 529, Bd. liii.; Berl. klin. Woch., xi. 11, p. 129, 1874–1876, p. 54 ; Archiv. für exp. P. u. Ph., vi. 287
Blair, Glasgow Med. Journ., Feb. 1870, p. 204
Boeck, V., Unters. üb. d. Zersetz. d. Eiweiss. München, 1871
Boeck, V., u. Bauer, Zeitschrift f. Biol., Bd. x. p. 361
Boeker, Beitr. z. Heilkde., i. p. 247, 1849
Bonwetsch, Dorpat Diss., 1869, p. 39
Bouvier, Cuny, Pflüger's Arch., Bd. ii. p. 370 ; Wirk. der Alcohol auf d. Körpertemperatur, Bonn, 1869 ; Centralbl. f. d. med. W., Bd. ix. p. 807, 1871
Brodie, Phil. Trans., Lond., 1811, p. 178
Brunton, Lauder, Book of Health, Cassell & Co., p. 183 ; Practitioner, xvi. p. 56 ; Contemporary Review, xxxiii. p. 691
Carpenter, Alcohol in Health and Disease, Lond., 1851, 2d ed.
Clemens, Theodor, of Frankfort, Deutsche Klinik, 1874, 1875
Daub, P., Centralbl. f. d. med. Wiss., 1873, p. 466
Davies, N. S., Trans. of the American Med. Assoc., 1855 ; Diction. encyclopéd., ii. Alcohol, p. 582
Dogiel, J., Pflüger's Arch., 1874, Bd. viii.
Dujardin-Beaumetz et Audigé, Compt. Rendus, lxxxi. 192–194
Dupré, The Doctor, Feb. 1, 1873 ; Lond. Practitioner, vol. viii. 148, vol. ix. 1872, p. 28, vol. xiii. p. 15
Edes, R. D., Bost. Med. & Surg. Journ., 1872, vol. lxxxvi.
Flourens, Système Nerveux, Paris, 1842, p. 400
Fokker, Nederlandsch Tijdschrift vor Geneeskunde, 1871
Fontana, Berlin, 1787, p. 439
Ford, N.Y. Med. Journ., Jan. 1872
Giacomini, Traité Philos. de Mat. Méd. et Thérap., Paris, 1842
Hammond, Phys. Memoirs, Philadelphia, 1863 ; Amer. Journ. Med. Sci., Oct. 1856, p. 305
Hermann, Archiv f. Anat. u. Phys., 1867, p. 64
Horwath, Gaz. des Hôpitaux, Sep. 1878
Huss, Magnus, Chron. Alkoholkrankh., Stockholm, 1852
Leudet, Arch. Gén. de Méd., Jan. 1867, vol. ix. pp. 5–39
Leuret et Lassaigne, Paris, 1825, p. 200
Lichtenfels u. Fröhlich, Denkschr. d. k. k. Acad. d. W. in Wien, 1852, Math. Nat. Cl., Bd. iii.

ALCOHOL.

Lieben, A., Ann. d. Chemie u. Pharm., 1870, vii., Suppl. Bd. p. 236
Ludger, Lallemand, Perrin, Duroy, Paris, 1860, p. 424, Chameret édit.
Magendie, Précis Elém. de Phys., Paris, 1825
Magnan, De l'Alcoolisme, Paris, 1874 ; Gaz. Méd. de Paris, No. xl. p. 444, 1871
Manassein, Centralbl. f. d. med. Wiss., ix. p. 689, 1871
Marvaud, Paris, Baillière et fils, 1re éd. 1871, pp. 89, 169
Meihuizen, Arch. d. Ges. Phys., vii. 4 u. 5, p. 201, 1873
Obernier, Pflüger's Archiv, Bd. ii. p. 494
Orfila, Tox. Gén., 1818
Parkes and Wollowicz, Proceedings of the Royal Society, 1870
Percy, Exp. Inquiry on Alcohol in Ventricles of Brain, Lond. 1839
Perrin, Arch. Générales, 6th series, tome ix.
Rabow, Berl. klin. Wochenschrift, 1871, p. 257
Rabuteau, l'Union Méd., 1870, pp. 154 and 165 ; Compt. Rend., lxxxi. 631
Rajewsky, Ueber das Vorkommen von Alcohol im Organismus, Pflüger's Archiv, Bd. xi. p. 122
Riegel, F., Deutsch. Arch. für klin. Med., 1873
Ringer and Rickards, London Lancet, 1866, vol. i. p. 208
Ruge, P., Virch. Arch., Bd. xlix., p. 252
Schmidt, A., Cent. f. d. med. Wissen., 1875, 371–4
Schulinus, Unters. über d. Vertheilung des Weingeistes im thier. Organismus, Diss. Dorpat, 1865 ; Arch. Heilk., 1866, p. 97
Smith, E., Brit. Med. Journ., March, 1859, 255
Strauch, Dorpater Diss., 1852
Subbotin, Phys. Bedeutung des Alcohols, Z. f. Biol., vii. 361 ; Schmidt's Jahrb., 1872, Bd. cliv. p. 261
Suessarott, Phila. Med. Times, vol. iv. p. 774
Sulzynski, Dorpat. Disser., 1865
Thudichum and Dupré, Tenth Rep. of Med. Officer of the Privy Council, London, 1868
Voit, Zeitschr. f. Biologie, Bd. vii. p. 341
Wibmer, Wirk. d. Arztn. u. Gifte, i. 90
Complete list of Literature on Alcohol, given in the Index Catalogue of the Surgeon-General's Library, U.S. Army, vol. i.

ALKALIES.

Aubert, Z. f. rat. Med., 1852, p. 225
Aubert u. Dehn, Pflüger's Arch., 1874, Bd. ix. p 115
Bence Jones, Lect. on Application of Chem. & Mechan. to Path., and Therap., Lond., Churchill and Sons, 1867, pp. 41, 70, 107, 125 ; Pflüg. Arch., iv. p. 235, 1871
Bernard, C., Leçons de Physiol. expériment., tom. ii. p. 404
Bernard, Cl., et Grandeau, Journal de l'Anatomie et de Physiol., t. i. p. 378
Bischoff, Zeitschr. f. Biologie, Bd. iii. p. 309
Blake, Edinburgh Med. & Surg. Journal, 1838
Böhm, A. f. exp. P. u. Ph., viii. p. 68
Bouchardat, Du Diabète Sucré, Paris, 1852
Boussingault, Ann. de Ch. et Phys., t. xix. p. 117, xx. p. 113, xxii. p. 116
Brunton, Lauder, The Practitioner, London, 1874, Nos. 71 & 72, pp. 342 and 403, vol. xii.
Brunton and Cash, Phil. Trans., 1884, p. 197
Buchheim, Archiv f. exp. Path. u. Pharmak., iii. 252–259 ; Vierordt's Arch. f. Phys. Heilk., 1853, liv., lv., lvii. ; Archiv f. exp. P. & Pharm., Bd. lii. p. 252
Bunge, Z. f. Biologie, 1873, p. 104, and 1874, p. 111, Bd. ix. & x.
Durand-Fardel, Lettres Méd. sur Vichy, Paris, 1855
Falck, Arch. f. path. Anat., Bd. lvi.

Alkalies.

Flöel, Pflüger's Archiv, Bd. xxxv. p. 160 (on Intestine)
Förster, Z. f. Biologie, Bd. ix. p. 207
Förster, R., Arch. d. Heilk., v. 521, 1864
Grandeau et Bernard, L'Institut, 1863, No. 1555
Guttmann, Berl. klin. Wochenschrift, 1865, Nos. 34–6; Virch. Arch., xxxv.
Heubel, Wirk. wasseranziehender Stoffe auf die Linsd., Pflüger's Archiv, Bd. xx. p. 114
Hirtz, Nou. Dic. de Méd., tom. i. *A*. p. 594
Hoffmann, F., Zeits. f. Biol., vii. p. 338
Hoppe-Seyler, Med. Chem. Unters.; and his pupils, Sertoli, Kaupp; Arch. f. Phys. Heilk., 1855
Jacobi, Med. Times and Gaz., 1876, vol. i. p. 177
Kemmerich, Pflüger's Archiv, 1869, p. 49
Klein u. Verson, Sitzungsber. d. Wien. Akad., Bd. lv. p. 627
Köhler, H., Centralbl. f. d. med. Wiss., 1877; vol. xv. No. 38, p. 673
Liebig, V., Ann. d. Chem. u. Pharm., lxxvii. p. 25
Löffler (Saltpeter), Schmidt's Jahrb., 1848, Bd. lx. p. 18
Lomikowsky, Berl. klin. Woch., 1873, p. 475
Lowit, Pflüger's Archiv, xxv. p. 466
Magendie, Union Méd., 1852, p. 498
Marchand, Virchow's Archiv, Bd. lxxvii. 1879
Mauricet, Schmidt's Jahrb., cxviii. 18, 1863
Mérandon, Act. phys. des Sels de Potasse, Thèse de Paris, 1868
Mialhé, Chimie appliquée, Paris, 1856, p. 58; Bull. Thérap., lxxxiv. p. 154, 28 Feb. 1873
Munk, Cent. f. d. med. Wissen., No. 27, 1886 (Saline Diuretics)
Nasse, H., Wagner's Handwörterbuch der Phys., i. p. 167 (Blut)
Nothnagel, Virchow's Archiv, Bd. lxxxviii, p. 1 (On Intestine)
Podcopäw, Virch. Arch., xxxiii. 505
Rabuteau, Gaz. Hebdom., 1871, 43, 46, 48
Ranke, F., Reichert u. Du Bois-Reymond's Arch., 1864, p. 320
Richet, Ch., Compt. Rend., xciii. p. 649; Arch. d. Phys. norm. et path., 1882, ii. pp. 145 and 366
Rilliet, Arch. Gén. de Méd., iv. 35, 1848
Ringer, Journ. of Phys., vol. iii. p. 193
Röhrig, Arch. f. wissensch. Heilk., vi. 3, 4, p. 396, 1863
Rossbach, Festschr. der Julius-Maximil. Universität zu Würzburg, Leipzig
Salkowski, Archiv f. path. Anat., Bd. liii.; Centralbl. med. Wiss., xi. 1873, p. 774
Schmidt, Al., u. Aronstein, Pflüger's Archiv, Bd. viii. p. 75
Sertürner, Ann. f. d. Universal-System d. Elements, Jahrg. 1826
Setschenow, Centralbl. f. d. med. W., 1873, p. 355
Tilt, Lancet, i. 1861, p. 556, June
Traube, Berl. klin. Wochenschrift, 1864, p. 18
Trousseau, Clin. Méd. de l'Hôtel-Dieu, Paris, 1861
Trousseau et Pidoux, Traité de Thérap., Paris, Asselin, 1868, 8e éd. p. 420
Voit, Unters. üb. d. Einfluss. d. Kochs. auf d. Stoffwechsel, München, 1860; und Ber. d. München. Acad., 1869
Voit, Z. f. Biol., Bd. i. p. 195 (Glaubersalz, Stoffwechsel)
Voit und Bauer, Zeitschrift f. Biol., 1869, Bd. v. p. 536
Zuntz, Pflüg. Arch., i. p. 361

Alkaline Earths.

Bence-Jones, Chem. Soc. Quart. Journ., xv.
Beneke, Pathologie des Stoffwechsels, 1876
Boussingault, Ann. d. Chem. u. Pharm., lix. (Phosphors. alk. Erden)
Chossat, Gaz. Méd. de Paris, 1842 (Phosphates)

Alkaline Earths.

Diakonow, Centralbl. f. d. med. W., 1867, Bd. v. p. 673
Dussart, Beneke et Feissier, Arch. Gén., 6e sér. tome xiv. p. 670, xv. pp. 66 and 198
Neubauer, u. Vogel, On Urine, etc. 1863
Piorry, Journal de Chim. Méd., tome ix. 1863
Roloff, Virchow's Archiv, Bd. xlvi. p. 305
Weiske, Zeitschrift f. Biol., Bd. vii. p. 333
Zalesky in Hoppe-Seyler's Med.-chem. Unters.

Alkaloids.

Heger, Journ. d. Méd. Chir. et Pharm. de Bruxelles, 1879 (sur l'Absorption des Alcaloïdes dans la Foie, les Poumons et les Muscles)
Rossbach, Verh. d. Würzb. physiol. medic. Ges., N.F., Bd. v. 1, vi. 162 u. 190, vii. 20; Pflüger's Archiv, x. 438, xxi. 1 (Antagonism); Verhandlung d. Würzb. physiol. medic. Ges., N.F., Bd. iii. 346, 1872, Bd. vi. p. 162, 1874; Pflüger's Arch., xxi. 213, 1880

Aloes, *see* Purgatives.

Buchheim, Die scharfen Stoffe, p. 27
Barker, Fordyce, American Practitioner, 1872
Gerhard, North American Med. and Surg. Journ.
Groves, Pharm. Journ., xvi.
Husemann, Pflanzenstoffe, p. 1047
Lienau, Oldenb. Corresp.-Blatt, 9, 10, 1861
Mürset, A., Arch. f. exp. Path. u. Pharmak., Bd. xix. p. 310
Smith, T. and H., Chem. Gaz., 1851, 107
Stillé, Therapeutics, vol. ii. p. 444
Trousseau and Pidoux

Althæa.

Bury, Pract., xxxi. p. 346

Alum.

Barthez, Frank's Magazin, iii.
Blanc, L'Union, 117, 120, 1873
Gamgee, Schmidt's Jahrb., cli. p. 23, 1871
Homolle, Paris, Malteste, 1861, p. 125; l'Union, 15, 17, 1861
Mitscherlich, Lehrb. d. Artzneimittellehre, 1847
Paulier, Gaz. Hebd. (2), x. p. 717, 1873
Rosenstirn in Rossbach's Pharmakolog. Unters. 1874, Bd. ii. p. 78
Schreber, Jahrb. f. Kinderheilk., iii. 2, p. 138, 1860
Smith, Curtis, Philad. Med. and Surg. Report, xxiv. p. 409

Ammonia and Ammonium Salts.

Barclay, Med. Times & Gaz., Nov. 1853, p. 553
Bellini, Lo Sperimentale, 1872, Giugno, 561
Bence-Jones, Philos. Trans., London, 1851, p. 399
Bichlmayr, Z. für Biol., 1867, 381
Billroth, Arch. f. klin. Chirurg., Bd. vi. p. 421
Blake, St. George's Hosp. Rep., v. p. 73, 1870
Bohm u. Lange, A. f. exp. P. u. Pharm., ii. p. 364; und Dorpater Diss., 1874
Brunton and Cash, Proc. Roy. Soc., 1883
Cazenave, Bull. gén. de Thérap., xxxi. 70
Cholmeley, St. Andrew's Med. Grad. Assoc. Trans., iii. 102, 1870
Crum-Brown and Fraser, Trans. Roy. Soc. Edinb.
Fayrer, Indian Annals of Med. Science, 1872
Delioux, Bull. de l'Acad., xxxv. No. 23, 15 Dec. 1870, p. 883
Feder, Z. f. Biol., xiii. p. 256

Ammonia and Ammonium Salts—(*continued*).

Feltz, V., et E. Ritter, Journ. d'Anatomie et de la Physiol., 1874, p. 326
Funke u. Deahna, Pflüg. Arch., 1874, ix. p. 416
Gmelin, Apparatus Medicamin., ii. 1, 48
Halford, G. B., Melbourne Argus, 1872
Hallervorden, A. f. exp. P. u. Pharm., x. p. 125
Husemann u. Selige, Arch. f. exp. Path., vi. 552–77
Huxham, On Fevers, p. 299
Knieriem, von, Zeitschr. f. Biol., 1874, Bd. x. p. 263
Knoll, Wien. Acad. Sitzber., 1874, Bd. lxviii.
Kühne u. Strauch, Centralbl. med. Wiss., 1864, No. 36, pp. 561, 577
Lange, F., Arch. f. exp. Path. u. Pharm., Bd. ii p. 368
Maurecet, Schmidt's Jahrb., clxviii. p. 18, 1863
Mitscherlich, Zeits. des Preuss. Vereins f. Heilk., Nos. 43, 44, 45, 46, 1841; Lehrb. der Arztn., ii. 228
Munk, Zeitschr. f. physiol. Chem., ii. p. 29
Priestley, On Air, ii. p. 369, 1790
Rabuteau, Gaz. Hebd., 43, 46, 48, 1871; Comptes Rend., lxx. 25, p. 1356, 1870; Traité élément. de Thérapeut., 4th ed. p. 536
Richet et Montard-Martin, Compt. Rend., xcii. p. 465
Rohmann, Centr. f. klin. Med., No. 36, 1884
Salkowski, Zeitschr. f. phys. Chem., Bd. i. pp. iv., 1, 374
Schiffer, Berl. klin. Wochenschr., 1872
Schmiedeberg, A. f. exp. P. u. Pharm., viii. p. 1
Stevenson, Guy's Hosp. Rep., 3rd ser. xvii. 225, 1872
Thiry, Henle u. Pfeufer's Zeits. (3), xvii. p. 166, 1864
Trousseau et Pidoux, Traité, 9th ed. 1, p. 453
Walter, A. f. exp. P. u. Pharm., vii. p. 148, u. Wibmer, Wirk. d. Arzneim. u. Gifte, Munich, 1831, pp. 123, 127, 139, 144

Amyl Compounds.

Richardson, Brit. Ass. Rep., 1865, p. 280

Amyl Nitrite, *see* Nitrite of Amyl.

Anilin.

Bergmann, Präger Vierteljahrsschr., Bd. lxxxviii. p. 109, 1865
Feltz et Ritter, Compt. Rend., lxxxii. p. 1512, 1876
Jolyet et Cahours, Compt. Rend., lxvi. p. 1181 (Methyl- and other Compounds)
Schuchhardt, Virch. Arch., Bd. xx. p. 446

Antifebrin.

Cahn & Hepp, Centr. f. klin. Med., Aug. 14, 1886

Antimony.

Ackermann, Virch. Arch., Bd. xxv. 1862, p. 531; Rostock, 1856 (Ader), iv. p. 44; Henle u. Pfeufer's Zeits. f. ration. Med., 3. R. ii. Heft, 3, 1858
Balfour, Tartar Emetic in Fever, Inflamm., Asthma, etc., Lond., 1818
Böcker, Beitr. z. Heilk., ii. p. 234, 1849
Brinton, Todd's Cyclop. of Anat. and Physiol., Suppl. p. 319
Buchheim u. Eisenmenger, Eckhardt's Beirt., Bd. v.

Antimony.

Corput, van den, Journ. Méd. de Brux., xxxv. p. 491, Nov. 1863
Denny, Brit. Med. Journ., Jan. 28, 1871, p. 89
Duffin, Edin. Med. & Surg. Journ., xix. 3, p. 354, 1823
Eisenmenger, U. d. Einfl. Gifte a. d. Zuckungscurve d. Froschesmuskels, iv. p. 7, Giessen, 1869
Forget, Bull. gén. de Thérap., lviii., June, 1860, p. 481
Fonssagrives, Bull. gén. de Thérap., lvii., Aug. 1859, p. 145
Gianuzzi, Centralbl. med. Wiss., 1865, p. 129
Grimm, Pflüg. Arch., iv. p. 205
Jankowich, Oesterr. Jahrb., N.F., xxxviii. p. 53, 1842
Jones, Handfield, Med. Times & Gaz., Dec. 1852, p. 362
Koschlakoff u. Bogomoloff, Centralbl. med. Wiss., 1868, p. 628; Pflüger's Arch., v. p. 280, 1872
Kleiman u. Simonowitsch, Arch. f. d. ges. Physiol., Bd., v. p. 280
Lange, D., Klinik, 28, 30, 31, 1863; Schmidt's Jahrb., cxxiii. 283, 1864
Lepelletier, Paris, 1835, p. 171
Long, Bull. gén. de Thérap., lix. Oct. 1860, p. 317
Magendie, Paris, 1813
Mayerhofer, Heller's Arch., iii. 3–5, p. 356, 1846
Mosso, Schmidt's Jahrb., Bd. clxix. p. 236
Nöbiling, Zeits. f. Biol., Bd. iv. p. 40, 1868; Schmidt's Jahrb., cxl. 24
Orfila, Mémoires de l'Acad. roy. de Méd., viii. 1840, p. 509
Papillaud, Schmidt's Jahrb., clvi. p. 267, 1872
Pécholier, Comptes Rend., lvi. 1863, p. 718; Gaz. Hebd., Apr. 17, 1863, p. 275
Radziejewski, Arch. f. Anat. u. Phys., 1871, p. 472
Rasori, Milano, 1830; Arch. gén. de Méd., 1824, iv. pp. 300, 415
Rayer et Bonnet, Dict. de Méd. et de Chir., iii. 69, Paris, 1829
Richardson, Med. Times and Gaz., May, 1856, p. 473
Salkowski, Virch. Arch., xxxiv. p. 73
Solon, Martin, Mémoires de l'Acad. roy. de Méd., viii. 1840, p. 518
Stedmann, Med. Times & Gaz., Dec. 1852, 641
Taylor, Guy's Hosp. Rep., 1860, p. 397
Traube, Centralbl. med. Wiss., 1864, p. 490
Trousseau et Pidoux, Traité de Thérap. et de Mat. Med., 9e éd. 1870, ii. p. 954
Viborg and Hertwig, quoted by Wibmer, Wirk. d. Arzneim. u. Gifte, v. 187, 194
Witt, J. H. D. de, Groningae apud Wilkens, 8, 1847, p. 32
Wood, Philad. Med. Times, vol. iii.

Antipyrin.

Bettelheim, Wien. med. Jahrbücher, 1885

Apiol.

Gallico u. Poggeschi, Bull. Gén. Thérap., 1861, ii. p. 279
Joret, Bull. Thérap., Feb. 1860, lix. p. 97
Joret et Homolle, Journ. de Pharm. et de Chim., 3e sér. xxviii. 212
Marotti, Bull. Thérap., lxv. pp. 295 and 341, 1863; Gaz. Hebd., 45

Apomorphine.

Bourgeois, Thèse de Paris, 1874, No. 19; Bull. gén. de Thérap., lxxxvi. p. 236, 1874
Chouppe, Soc. de Biol., July 18, 1874; Arch. de Physiol., 1875, p. 101
David, G., Gaz. Méd., 1874, p. 465

Apomorphine.

Dujardin-Beaumetz, Bull. Gén. de Thérap., lxxxvii. Oct. 8, 1874, p. 345
Eichberg, Würtemberg. Corr.-Bl., 89, pp. 1819–1873
Fronmüller, Memorabil., xviii. 9, 1873
Ganghofner, Böhm. Corr.-Bl., i. 3, p. 65, 1873
Gee, St. Barth. Hosp. Reports, vol. v. p. 215; Trans. Clin. Soc., ii. p. 166, 1870
Gellhorn, Allgem. Zeitschr. f. Psych., xxx. 46, 1873
Greve, Berl. klin. Wochens., xi. 28, 29, 1874
Harnack, Arch. f. exp. Path. u. Pharm., Bd. ii. p. 291, 1874
Huchard, H., Union Méd., Oct. 1874, p. 493
Juratsz's Centralbl. f. d. med. Wiss., p. 499. 1874
Löb, Berlin. klin. Wochens., 1872, p. 400
Mattheissen, R., & C. R. A. Wright, Proceedings Roy. Soc., xvii. 455
Mayer, E. L., Berichte Deutsch. Chem. Gesell., Berlin, 1871, iv. 121
Meyer, De, Bull. de la Soc. roy. de Pharm. de Bruxelles, 1872
Moerz, A., Präger Vierteljahrs., 1872, Bd. cxv. p. 82
Möller, Bull. de l'Acad. de Méd. de Belgique, viii. 3, 1873, p. 749
Oberlin, Revue Méd. de l'Est, Aug. 1874, ii. p. 98
Onsum, Norsk Mag., 3. R. iii. 155, 1872
Quehl, Hallenser Diss., 1872
Pierce, British Med. Journ., 1870, vol. i. p. 204
Riegel u. Boehm, Deutsch. Arch. f. klin. Medicin, Bd. ix. 211, 239, 1871
Routy, Thèse de Paris, 1874, No. 437
Siebert u. Boehm, Arch. d. Heilk., Bd. xii. 6. Heft, 1871, p. 522
Wertner, M., Wien. med. Presse, 1876, 269
Ziolkowski, Apomorphin, Inaug. Diss. Greifswald, 1872

Araroba or Chrysaroba.

Fayrer, Med. Times, ii. 1874, pp. 470, 547; 1876, ii. p. 711
Thompson, I. Ashburton, Brit. Med. Journ., May, p. 607, 1877

Arnica.

Balding, C. C., Lancet, vol. ii. p. 885, Dec. 1870
Fayrer, Practitioner, xvi. p. 52
White, Boston Med. and Surg. Journ., Jan. 1875, p. 61

Aromatic Compounds.

Baumann u. Herter, Z. f. physiol. Chem., i. 244, ii. 335
Brieger, A. f. Anat. u. Phys., 1879, Physiol. Abth., Suppl. Bd. p. 61 (Pyrocatechin, Hydrochinon, Resorcin)

Arsenic.

Binz u. Schulz, Arch. f. exp. Path. u. Pharm., Bd. xi. p. 200
Bergeron and Lemaitre, Brit. and For. Med.-Chir. Review, vol. xlviii. p. 226, 1871
Blake, Edin. Med. and Surg. Journ., 1839
Boeck, Von, Zeitschr. f. Biol., Bd. vii. p. 418, u. xii. p. 512; u. Centralbl. d. med. Wiss., 1876, üb. d. Zersetzung des Eiweisses, München, G. Himmer, 1871, p. 41
Böhm u. Schäfer, Ueb. den Einfluss des Arsen. auf ungeform. Fermente, Würzburg. Verhandlungen, N.F., Bd. iii. 1872
Brodie, Phil. Trans., 1811, 1812
Cunze, Henle u. Pfeufer's Zeitschr. f. rat. Med., 3, xxviii. p. 33, 1866; Schmidt's Jahrb., cxxxi. 19
Dogiel, Pflüger's Archiv, xxiv. p. 328
Downie, K. M., Indian Medical Journ., 1872
D'Etiolles, Leroy, Gaz. Hebd., 1857, vol. iv.
Feitelberg, Inaug. Dissert., Dorpat, 1883
Filehne, Virchow's Archiv, lxxxiii., p. 1
Flandin u. Danger, Husemann, Toxicologie, p. 823
Fleck, Arch. f. Biologie, Bd. viii. p. 444
Fokker, Schmidt's Jahrb., clviii. 15
Fowler, Med. Rep. on Arsenic in Ague, etc., Lond. 1786
Gaethgens, Arch. f. exp. P. u. Pharm., Bd. v. p. 128, u. Centralbl. f. med. Wiss., 1876
Gies, Arch. f. exp. Path. u. Pharm., Bd. viii. p. 175
Grohe, Fr., u. Fr. Mosler, Virch. Arch., Bd. xxxiv. p. 213
Herapath, Philosophical Mag., 1851, p. 345
Heisch, Chas., Pharmaceutical Journ. and Trans., vol. i. 2nd series, 1859, 1860, p. 556
Hoffman, Virch. Arch., Bd. i. (50), p. 456
Imbert-Gourbeyre, Histoire des Éruptions arsénicales, Monit. des Hôpit., 1857
Jackson, W. C., Amer. Journ. of the Med. Sciences, July 1858, p. 57
Jäger, Wirk. d. Arseniks auf Pflanzen, Stuttgart, Schweizerbart, 1864, p. 113
Johannsohn, Arch. f. exp. P. u. Pharm., Bd. ii. p. 106
Karajau, Tardieu, Sur l'empoisonnement, p. 335
Kendall and Edwards, London Pharmaceutical Journal, ix. 1850
Köhler, H., of Halle, Brit. and Foreign Med.-Chir. Rev., 1870, vol. xlv. p. 538
Kossell u. Gaethgens, Arch. f. exp. Path. u. Pharm., Bd. v. 133, and Centralbl. med. Wiss., 1875, 530; 1876, 833
Lachèse, Ann. d'Hyg. et de Méd. légale, 1837, 1e série, tome xvii. p. 334
Lesser, A., Virch. Arch., Bd. lxxiii. p. 398, and lxxiv. 125, 1878
Leube, Deutsch. Arch. f. klin. Medicin, Bd. v. 372, 1869
Loew, O., Pflüger's Archiv, xxxii. p. 111
Maas, Verhandl. d. Leipziger Naturforsch. Vers., 1872
Mackenzie, Ind. Med. Gazette, 1872
Maclagan, C., Edin. Med. Journal, vol. x. 1864, p. 203
Nunn, Emily A., Journ. of Physiology, i. p. 247
Pinkham, Boston Med. and Surg. Journ., 1878, vol. xcix. 358
Popow, N. (with lead and mercury), Virchow's Archiv, xciii. p. 351
Renner, Würtzburger Diss., 1876
Ringer and Murrell, Journal of Physiol., i. p. 213
Saikovski, Virch. Arch., Bd. xxxiv. p. 77
Saikowsky, Mosler u. Grohé, Virch. Arch., 1865, Sept. u. Oct., p. 208
Salomon, Alex., Wirk. kleiner Dosen Arsenik, Diss. Berl., 1873, p. 35
Sawitsch, Dorpater Dissert., 1854
Schmidt u. Stürzwage, Moleschott's Unters., vi. 3, p. 283, 1859
Schroff (senior), V., Zeitschr. d. Wiener Aerzte, N.F. ii. 44; Schmidt's Jahrb., 1860, cv. 176, 1860
Schulz, Arch. f. exp. P. u. Pharm., Bd. xi. p. 131
Sklarek, W., of Berlin, Reichert's Archiv, 1866, p. 481; Schmidt's Jahrb., cxxxii. 290
Sturtzwage, Dorpater Dissert., 1859
Taylor, Guy's Hosp. Reports, vol. x. 3rd series, 1864, p. 227
Unterberger, S., u. Bohm, Arch. f. exp. Path. u. Pharm., Bd. ii. pp. 89, 99, 1874; ibid. Bd. xi. p. 89
Virchow, Virchow's Archiv, Bd. xlvii. p. 524

Arsenic.

Vogt, Lehrbuch d. Pharmacodynamik, 3te Aufl., Bd. i.
Vulpian, Arch. de Phys., 1868 (Compounds)
Weir-Mitchell, New York Med. Journ., vol. i.
Wyss, Arch. d. Heilkunde, 1873, p. 15

Aspidospermine, *vide* Quebracho.

Atropine.

Anrep, Pflüger's Arch., Bd. xxi. 1880 (chron. Atropinvergiftung)
Arlt, Arch. f. Ophthalmologie, 1869, p. 294
Bennett, Hughes, Brit. Med. Journ., 1874, vol. ii. 547; London Med. Record, 1877, p. 341
Bernard, Cl., Physiol. u. Path. du Système Nerveux, Paris, vol. ii. p. 112
Bezold, V., u. Blöbaum, Unters. a. d. physiol. Labor. in Würtzburg, Bd. i., 1867
Boehm, Studien über Herzgifte, Würzburg, 1871
Borelli, Ed. Med. Journ., Nov. 1871, vol. xvii. p. 480
Botkin, Virchow's Arch., Bd. xxiv. p. 83
Braun, Arch. f. Ophthalmologie, Band v. Abth. ii. p. 112
Buchheim, Arch. f. exp. Path., v. p. 463
Budge, Ueb. d. Bewegung der Iris, 1855
Chambers, Lancet, 1864, vol. i. p. 8
Da Costa, Amer. Journ. Med. Sciences, July, 1865, p. 71; Pennsylvania Hosp. Rep., 1858; Philad. Med. Times, Feb. 15, 1871
Dogiel, J., Max. Schultze's Arch. f. microscop. Anat., Bd. vi. Heft i. 1870, p. 85
Donders, The Accommodation and Refraction of the Eye, Syd. Soc. ed., pp. 584, 588
Eckhard, Eckhard's Beiträge zu Anat. u. Phys., viii. p. 1
Fraser, Transactions of the Royal Society of Edinburgh, May, 1869, vol. xxv. 450, vol. xxvi. 1872, with complete *résumé* of older literature
Fraser, T. R., Bartholow, Oglesby, Nunnely, The Practitioner, iv. pp. 27, 65, and 217
Gnauck, Arch. f. Anat. u. Phys., 1881, p. 466
Graefe, Von, Deutsche Klinik, 1851
Graser, Arch. f. exp. Path. u. Pharmak., Bd. xvii. p. 5
Harley, The Old Veg. Neurotics, London, 1869, p. 220
Hayden, Dublin Quarterly, Aug. 1863, p. 51
Heidenhain, Pflüg. Arch., Bd. v. p. 309
Hirschmann, L., Zur Lehre v. d. durch Arzneim. u.s.w., Reichert's Arch., 1863, p. 309
Iwanoff, Alex., u. Alex. Rollett, Arch. f. Ophthalm., Bd. xv. p. 17
Jones, Wharton, Med. Times and Gazette, p. 28, vol. i. 1857
Ladenburg, Ber. d. deutsch. chem. Ges., Jg. xii. 1879, p. 941; Compt. Rend., xc. p. 874
Langendorff, Archiv f. Anat. u. Phys. (Phys. Abth.), 1886, p. 267
Lautenbach, Phil. Med. Times, May 26, 1877
Lemattre, Arch. Générales, Aug. 1865, p. 173
Lichtenfels u. Fröhlich, Denkschr. d. Wien. Acad. Math., Naturw. Cl., 1852, p. 113
Luchsinger, Arch. f. d. ges. Phys., xv. p. 482
Meuriot, De la Méthode physiol. en Thérapeutique et de ses Applications à l'Étude de la Belladonne, Paris, 1868, p. 73
Norris, Wm. F., Amer. Journ. of Med. Sci., Oct. 1862, p. 395
Putnam, Miss Mary, New York Med. Record, 1873
Rossbach, Pharmakol. Unters., Bd. i. ii. iii., Würtzburg, 1873 (*vide* also Alkaloids)
Rossbach u. Fröhlich, Pharm. Unters. Würzburg, i. p. 6, N.F., v. 1874

Atropine.

Roy and Brown, Journ. of Phys., vol. vi.
Schapiro, Cent. f. d. med. Wiss., 1884, No. 33
Schiff, La Nazione, 1872, No. 235
Schmiedeberg, Arb. des Phys. Instit. z. Leipzig, v. p. 41, 1870
Schroff, Zeitschr. d. Wien. Aertze, 1852
Stellwag v. Carion, Der intraoculare Druck u. d. Innervations-Verhältn. der Iris, Wien, 1868
Szpilman u. Luchsinger, Pflüger's Archiv, Bd. xxvi. p. 459
Valentin, Y., Versuch einer physiol. Pathologie der Nerven, Leipzig, 1864, 2e Abth. p. 368
Weir-Mitchell, Injuries of Nerves, Philadelphia, 1872, p. 258
Wood, Amer. Journ. Med. Sci., Apr. 1873, p. 332; N.S. p. 258, Jan. 1871; Philadelphia Med. Times, vol. i. p. 290
Zeller, Virchow's Archiv, lxvi. p. 384

Barium.

Böhm u. Mickwitz, Arch. f. exp. Path. u. Pharm., 1875, Bd. iii. p. 216
Brunton and Cash, Roy. Soc. Proc., No. 226, 1883; Phil. Trans., 1884; Cent. d. med. Wiss., 1884, p. 545
Hermann, Toxicologie, 1191
Lisfranc, quoted by Lewin, Nebenwirkungen der Arzneien, p. 74
Onsum, Arch. f. path. Anat., Bd. xxviii. p. 233

Bebeeru Bark.

Albers, Virch. Arch., Bd. xxiv. p. 304
Binz, Virchow's Arch., Bd. xlvi. p. 130
Flückiger, N., Jahrb. Pharm., 1869
Gamgee and Maclagan, Edin. Roy. Soc. Trans., 1869, p. 567
Walz, N. Jahrb. Pharm., xii. 1861, p. 302

Benzoic Acid.

Bird, Golding, Urinal Deposits, Philad., 1859, p. 160
Brown, Zur Therapie der Diphtheritis, Arch. f. exp. Path. u. Pharm., Bd. viii. p. 140
Bryant, Lancet, ii. 1876, 747
Bucholtz, Arch. f. exp. Path. u. Pharm., Bd. iv. p. 1
Delcours, Gaz des Hôp., Dec. 1844
Dougall, Med. Times and Gazette, i. p. 495, 1872
Fleck, Benzoesäure, Carbolsäure, Zimmtsäure, München, 8vo. Oldenburg, 1875
Garrod, Memoirs of the Chem. Soc., i. 1842; London Lancet, ii. p. 239, 1844
Grübe W., Centralbl. f. Chem., 1876, pp. 777, 778
Hallwachs u. Kühne, Götting. Nachr., 8, 1857
Jaarsveld, A. f. exp. P. u. Pharm., x. 268
Jaffé, Ber. d. deutsch. chem. Ges., 1877, p. 1925
Keller, Ann. der Chem. und Pharm., xliii. 108; Lancet, ii. Nov. 1844, p. 239
Lamaire, Phil. Med. Times, iv. 638
Meissener u. Shepard, Unters. üb. d. Enstehen des Hippurs. im thier. Organismus, Hannover, 1866
Morri, Trans. Phil. Coll. of Med., March 7, 1855
Rohde, Berl. klin. Woch., 1871, 10
Salkowski, E., Berl. klin. Wochens. 1875, 297
Seligsohn, Chem. Centralbl., 1861
Shepard, U. C., Der Hippursäure im thier. Organismus, Hannover, 1866
Ure, Medico-Chir. Trans., xxiv. p. 30, 1841
Ure and Wood, Phil. Trans., March 7, 1856

Benzol.

Hoffmann, F. A., quoted by Böhm, Ziemssen's Cyclopædia, vol. xvii. p. 513
Perrin, L'Union Méd., 1861, No. 6, p. 92

Bichloride of Methylene.

Richardson, B. W., Med. Times and Gaz., 1867, p. 479; ibid., 1869, ii. 524; Brit. Med. Journ., vol. i. p. 332, 1871; vol. ii. p. 249, 1872; London Lancet, 1877, ii. 26

Bismuth.

Becker u. Jansen, Arch. der Pharm., lv. 31, lxviii. 129, lxxvii. 231, lxxviii. 18
Bergeret et Mayençon, Journ. de l'Anatomie, 1873, p. 242
Feder-Meyer, Würzburg Diss., 1879
Langhans, Zeits. f. Chirurgie, xxii., p. 575
Luchsinger u. Mory, Mitth. d. Bern. Naturf.-Ges., 1883, p. 23
Stefanowitsch-Lebedeff, Virch.'s u. Hirsch's Jahresb., 1869, p. 335
Wiggers, Canstatt's Jahresb. Pharm., 1848, p. 104; 1851, p. 105; 1854, p. 109

Bitters.

Buchheim u. Engel, in Buchheim's Beitr. z. Arzneimittellehre, Leipzig, 1849
Koehler, H., Tageblatt d. 46. Naturforscher-Versamml. zu Wiesbaden, 1873, p. 70

Blatta Orientalis.

Bogomolow, Lond. Record, 1877, p. 502
Buttenwieser, Der practische Arzt, Feb. 1882
Unterberger, Petersburg. med. Wochensch., 1876

Blood Root.

Smith, R. M., Amer. Journ. Med. Sci., Oct. 1876, p. 346

Borax.

Binswanger, Pharm. Würdigung der Borsäure des Borax u.s.w., 1846
Buchholz, Arch. exp. Path. u. Pharm., Bd. iv. p. 1
Copland, Dict. of Pr. Med. (art. Abortion)
Dumas and Schnatzles, Pharmac. Journ., April 1874
Gmelin, App. Medicaminum, i. p. 104
Guibourt, Histoires des Drogues simples, i. p. 191
Homberg, Mém. de l'Acad. des Sci. de Paris, 1702, 33
Richter, Ausführl. Arzneiml., iii. p. 558
Vogt, Pharmakol., ii. 587
Wibmer, Wirk. d. Arzneim. u. Gifte, v. 51

Brayera.

Bedall, Sydenh. Year Book, 1868, p. 476; l'Union, 116, p. 596, 1863
Leidesdorf, Wien. med. Woch., xii. 26, 1871
Viale, Journ. de Chimie méd., 5, ii. p. 207, 1866

Bromal Hydrate.

McKendrick, J. G., Ed. Med. Journ., July 1874, p. 1
Rabuteau, Gaz. Hebdom., xliii. p. 681
Steinauer, E., Virch. Archiv, 1870, Bd. i. p. 235, lix. p. 65

Bromides, Mixed.

Erlenmeyer, Centralbl. f. Nervenheilk., No. 14, 1884

Bromine and Bromide of Potassium.

Anstie, Practitioner, xii. p. 19, 1874
Bartholow, The Bromides, 1871
Binz, Practitioner, xii. p. 6, Jan. 1874
Blake, Journ. of Anat., iv. 1, 1870

Bromine and Bromide of Potassium.

Clark and Amory, Bromide of Potass., Boston, 1872
Clouston, Journ. Mental Sci., Oct. 1868, vol. xiv. p. 305
Complete Literature, see Krosz, Arch. f. exp. P. u. Pharm., 1876, Bd. vi. p. 46
Eulenburg u. Guttmann, Schmidt's Jahrb., cxxxvii. p. 158, 1868
Hammond, Quart. Journ. of Psycholog. Med., vol. iii. p. 46, 1869
Laborde, Paris, B. Delahaye, p. 30, 1870
Marchand, R., Thèse de Paris, 1868, p. 32
Namias, Compt. Rendus, lxx. 16, p. 882, 1870
Ozanam, Gaz. des Hôp., No. 66, 1856
Paul, C., Gaz. des Hôp., 91, 1866
Podcopäw, Virch. Arch., xxxiii. p. 505, 1865
Purser, J. M., Dub. Quart. Journ., xlii, 94, May 1869
Ringer, Sydney, Lancet, i. p. 392, 1869
Teissier, Gaz. Méd. de Lyon, p. 501, Nov. 15, 1868
Williams, Obstet. Trans., xii. 249, 1871

Brominated Camphor.

Besnier, Gaz. des Hôp., 35, 1865
Bourneville, Le Progrès Méd., 1874; The Practitioner, Aug. 1874, p. 119; Comptes Rend., Aug. 1875
Crichton-Browne, Edinb. Med. Journ., June, 1865, p. 1085
Deneffe, Presse Méd. Belge, 1871, p. 405
Hamilton, McLean, N.Y. Med. Journ., July 1872, p. 72
Hammond, Wm., N.Y. Med. Journ., Dec. 1871, p. 594
Lawson, Practitioner, vol. xiii. p. 324, 1874, vol. xiv. p. 262, 1875
Mussy, Guénau de, Union Méd., 83-6, 1866
Pathault, Bromure de Camphor, Paris, 1875
Ricard, Union Méd., cxi. p. 417, 1869
Soulez, Amer. Journ. Med. Sci., July, 1877, p. 237; Lond. Med. Rec., 1877, p. 196.

Broom.

Fick, Arch. f. exp. Path. u. Therap., i. 397, 1873
Husemann, Die Pflanzenstoffe, p. 64

Brucine.

Buchheim u. Loos, Eckhard's Beiträge, Bd. v. (Methylbrucine)

Cacodyl Compounds.

Lebahn, Rostocker Inaug. Diss., 1868
Renz, Deutsch. Arch. f. klin. Med., 1865, i. 2, 235
Schmidt u. Chomse, in Moleschott's Unters., vi. 122

Cadmium.

Marmé, Zeitschr. f. rat. Med., 1867, Bd. xxix. p. 113

Caffeine.

Albers, Deutsche Klinik, 1853, p. 370
Amory, Boston Med. Journ., May 28, 1868, p. 261

Caffeine.

Aubert, Pflüger's Arch., v. p. 589, 1872
Bennett, Alex., Brit. Med. Journal, 1874, vol. ii. p. 510; Edin. Med. Journ., ccxx. p. 328, 1873
Bennett, J. Hughes, Brit. Med. Journ., 1874, vol. ii. p. 697
Binz, Arch. f. exp. Path. u. Ph., 1878, ix. p. 31; Berl. klin. Wochenschr., xlv. p. 545, 1872
Böcker, Beiträge z. Heilk., Bd. i. 1849; Arch. d. Vereins. f. Gemeins. Arb. z. Förd. d. wiss. Heilkunde, Bd. i. p. 213
Brill, Marburger Dissert., Elwert, 1862
Brown-Séquard, Arch. de Phys. Norm. et Path., 1868
Eggerth, Diss. de Coffea, Pesth, 1833, p. 31
Eisenmenger, Ueb. d. Einfluss v. Giften a. d. Zuckungscurve, etc., Giessen, Pietsch, 1869, p. 49
Falck und Stuhlmann, Virchow's Archiv, Bd. xi. p. 325
Garrison, J. B., Phila. Med. and Surg. Reporter, xxx. Feb. 6, p. 111, 1874
Gubler, Bull. Thér., xciii. 523
Hoppe, F., l'Echo Médical, 1858; Deutsche Klinik, 1857, p. 181
Johannsen, O., Dorpater Diss., 1869
Langgard, Centr. f. d. med. Wiss., 1886, p. 513
Leven, Arch. de Phys., 1868, t. i. p. 178
Marvaud, Angel, Effets physiol. et thérap. des Aliments d'Epargne, Paris, 1869–71, p. 118
Meihuizen, Pflüg. Arch., vii. 4–5, p. 201, 1873
Mitscherlich, Der Cacao und Chocolade, Berl. 1859
Payen, Compt. Rend., xxii. p. 724, xxiii. pp. 8 and 244, 1846
Riegel, Verhandl. d. III. Cong. f. inner. Med., 1884
Roques, Schmidt's Jahrb., x. p. 18
Runge, Schweigg. Journ. Chem. Phys., xxxi. 1820
Schmiedeberg, Arch. f. exp. P. u. Ph., Bd. ii. p. 62, 1874
Schroeder, V., Cent. f. d. med. Wissen., 1886, p. 465
Smith, H. M., Journ. of Applied Sciences, Sept. 1874
Stuhlmann u. Falk, Virch. Arch., Bd. xi. p. 481
Thompson, Med. Times and Gaz., Feb. 12, p. 185, 1871
Uspensky, Reichert's Arch., 1868, p. 522; Centralbl., 1868, p. 677
Voit, Ueber d. Wirk. d. Kochsalzes u. Kaffees auf d. Stoffwechsel, München, 1860, p. 135

Calcium Chloride.

Warburton Begbie Works, New Syden. Soc.

Camphor.

Baum, Centralbl. f. d. med. Wiss., 1870, p. 467
Flückiger, Neues Repertor. f. Pharm., xvii. 28, 1868
Grisar, Bonnar Diss., 1873, u. Centralbl. f. d. med. Wiss., 1874, p. 77
Gübler, Bull. de Thérap., Dec. 30, 1871, p. 529
Harley, Practitioner, ix. 210, 1872
Heubner, Arch. f. exp. Path. u. Pharm., v. p. 427
Hoffmann, Beitrag z. Kenntn. d. Physiolog. W. d. Carbolsäure u. d. Camphors, Diss. Dorpat, 1866
Pellacani, Archiv f. exper. Path. u. Pharmak., xvii. p. 369
Schmiedeberg u. Meyer, Z. f. phys. Chem., iii. 422, 1879
Wiedemann, Arch. f. exp. Path. u. Pharm., Bd. vi. p. 216 (with complete list of Literature)

Cannabis Indica.

Christison, Edinb. Monthly Journ. of Med. Sci., July, 1851, p. 26
Fronmüller, Klinische Studien üb. d. schlafmachende Wirkung, etc., Erlangen, bei Enke, 1869
Lawrie, Stillé's Therap., vol. i. p. 772
O'Shaughnessy, On the Preparations of Indian Hemp, Calcutta, 1830
Preobraschensky, Dragendorf's Jahresb., 1877, p. 98
Roemer, St. Louis Med. and Surg. Journ., p. 363, 1873
Schroff, V., Zeitschrift d. Wien. Aerzte, 1857, u. Lehrbuch d. Pharmakologie, Aug. 3, 1868, p. 499
Wood, Proceed. Amer. Philos. Society, 1869, vol. xi. p. 226

Cantharidin.

Cautieri, Schmidt's Jahrb., Bd. clxv. p. 237
Cornil, Practitioner, xxvii. p. 110
Galippe, Gaz. Hebdom., 1874, p. 439
Husemann, Hanb. d. Toxicol., 1862, p. 264
Pallé, Journ. de. Pharm. et de Chimie, June 1871
Radecki, Dorpater Diss., 1866
Schwakowa, Berner Diss., 1876
Stüler, Deutsche Z. f. Chir., 1872, xii. 377

Carbazotic Acid.

Binz, Virch. Arch., Bd. xlvi. p. 130
Erb, W., Die Pikrinsäure, Würzburg, 1865

Carbolated Camphor.

Soulez, Amer. Journ. Med. Sci., July, 1877, p. 237, and London Med. Record, May, 1877

Carbolic Acid.

Almén, Zeitschr. f. Anal. Chimie, Bd. x. p. 125, Heft 7
Aufrecht, Centralbl. med. Wiss., 1874, p. 129
Baumann, Pflüger's Archiv, Bd. xiii. p. 285; Zeits. f. phys. Chimie, v. Hoppe-Seyler, i. p. 244; Du Bois' Arch., physiol. Abth., 1879, iii. 245
Baumann u. Sonnenburg, Med. Times and Gaz., ii. 1878
Bill, J. H., Amer. Journ. Med. Sci., Oct. 1870, p. 573
Brieger, Zeitschr. f. physiol. Chemie, iii. p. 134
Buchholtz-Waldemar, Dorp. Diss., 1866
Buchholtz, Einwirk. a. Gährungs-Processe, Dorpat, 1866, p. 50
Buliginski, Hoppe-Seyler's Med. chem. Unters., Berlin, 1867, p. 234
Dougall, John, Lancet, 1870, vol. ii. p. 176
Eames, J. H., Brit. Med. Journ., May, p. 490, 1873
Erb, E., Schmidt's Jahrb., Bd. clxiv. p. 148
Hagen, Schmidt's Jahrb., Bd. clxiv. p. 147
Hoffmann, W., Dorpat. Diss., 1866
Hoppe-Seyler, Pflüger's Arch., 1872, Bd. v. pp. 470, 475, 476, 479
Hueter, C., Deutsch. Zeits. f. Chir., iv. p. 508, 1874; Schmidt's Jahrb., clxiv. p. 144
Husemann, Schmidt's Jahrb., Bd. clv. p. 274
Husemann u. Ummethun, Deutsch. Klinik, 1870 and 1871
Kempster, W., Amer. Journ. Med. Sci., July, 1868, p. 31
Kunze, Centralbl. med. Wiss., 1874, p. 479
Labée, E., Arch. Gén. de Scien., t. xviii. p. 451, 1871
Lemaire, J., De l'Acide phénique, 2e éd., Paris, 1865

Carbolic Acid.

Lister, J., Lancet, vol. ii. 1867, p. 353
Mader, Centralbl. f. Chir., 1877, p. 376
Neumann, I., Arch. f. Dermat. u. Syphil., Jahrg. i. 1869, p. 425
Oberst, Berl. klin. Woch., 1878, p. 157, No. xii. (Acute Poisoning)
Patrouillard, Journ. de Pharm. et de Chimie, Dec. 1871, p. 459
Plugge, P. C., Pflüger's Arch., 1872, Bd. v. p. 540
Reuder, Journ. de Pharm. et de Chimie, p. 456, Dec. 1871
Rosenbach, Ueb. d. Einfluss Carbolsäure, u.s.w., Göttingen, 1873
Salkowski, Pflüger's Arch., Bd. v. p. 210, 335, 1872; Centralbl. med. Wiss., 1876, p. 818
Schaffer, Journ. f. pract. Chimie, N.F. xviii. p. 282
Schmidt, T., Centralbl. f. Chir., 1876, 552
Senator, Berl. klin. Wochenschr., 1876, p. 69
Sonnenburg, Deut. Zeits. f. Chir., Bd. ix. p. 356
Städeler, Ann. d. Chem. u. Pharm., Bd. lxxxvii. p. 17
Stevenson, Brit. Med. Journ., vol. i. p. 442, 1870; and Guy's Hosp. Rep., 1868, p. 407
Tauber, Z. f. phys. Chem., ii. 366
Ummethun, Göttingen. Diss., 1873
Volkmann, Volkmann's Samml. klin. Vortr., 1875, No. xcvi. in Beit. z. Chir., p. 42
Waldenström, Zeitschr. d. Allgemein. Apothek.-Vereins, Jan. 10, 1872
Wilson, Erasmus, Journ. Cutaneous Med., June, 1870

Carbon.

Liebermann, Sitzber. d. k. k. Acad. d. Wiss. Wien., 1877, p. 331
Stenhouse, Economical Applications of Charcoal, 3rd ed. Lond. 1855

Carbonic Acid.

Basch, Von, u. Dietl, Wien. m. Jahrb., 1870, xxvi. 3
Beddoes, on the Med. Effects of Factitious Airs, pp. iv. p. 42
Bernard, Cl., Subst. toxiques, etc., p. 135
Bert, Comptes Rend., t. lxxxvii. p. 628
Buchheim, A. f. exp. P. u. Ph., Bd. iv. p. 137
Christison, on Poisons, 3rd ed. p. 745
Donders, Pflüger's Arch., Bd. v. p. 20
Friedländer u. Herter, Z. f. physiol. Chem., 1878, ii. 99, and 1879, iii. 19
Heidenhain u. L. Meyer, Stud. d. physiolog. Instit. zu Breslau, Bd. ii.
Hermann, L., Exper. Toxikologie, 1874, p. 118
Hickmann, Séance de l'Acad. Roy., Sept. 24, 1828
Humboldt, Von, U. üb. d. gereizte Nerven u. Muskelfaser, ii. p. 321
Kühne, Protoplasma u. Contractilität, pp. 28, 53
Liebig, G., Arch. f. Anat. u. Physiol., 1850, p. 401
Pflüger, Pflüger's Arch., Bd. i.
Preyer, Wiener Acad. Sitzber. Math.-nat. Cl., Bd. xlix.; Pflüger's Arch., Bd. i. p. 395
Priestley, on Airs, vol. i. p. 302
Quincke, A. f. exp. P. u. Ph., vii. p. 101, 1877
Schott, Aug., Berl. klin. Wochens., No. 33, 1885
Setschenow, Wiener Acad. Sitzungsber. Math.-nat. Cl., Bd. xxxvi.; Z. f. rat. Med., Bd. x. p. 101; Centralbl. f. d. med. Wiss., 1873, p. 355, 1877, 625, u. 1879, p. 369
Zuntz, Centralbl. f. d. med. Wiss., Bonner Diss., 1868; Berl. klin. Wochenschr., 185, 1870

Carbonic Oxide.

Friedberg, Die Vergift. durch Kohlendunst, Berlin. 1866
Hoppe-Seyler, Virch. Arch., 1857, Bd. xii.
Kühne, Centralbl. f. d. med. Wiss., 1864, p. 134
Lothar Meyer, Breslauer Diss., 1858
Pokrowsky, Arch. f. Anat. u. Phys., 1866, p. 59
Senff, Dorpater Diss., 1862
Traube, Gesammelte Beiträge, Berlin, 1878, iii.

Chinoline.

McKendrick and Dewar, Proc. Roy. Soc., 1874, p. 432

Chloral Hydrate.

Adams, Lancet, i. pp. 212 and 567, 1870
Adrian, New York Med. Journ., 1870
Andrews and Da Costa, Amer. Journ. Med. Sci., April 1870, p. 359
Anstie and Andrews, Amer. Journ. of Insan., July 1871
Beck, Jos. R., St. Louis Med. and Surg. Journ., June 1872
Bouchut, N.Y. Med. Gaz., Dec. 1870
Bradbury, J. B., Brit. Med. Journ., vol. i. p. 363, 1871
Brunton, Lauder, Journ. Anat., viii. p. 332, 1874
Clarke, Lancet, May 2, 1874, p. 643
Clemens, Schmidt's Jahrb., Bd. cli. p. 105
Demarquay, Bull. Thérap., t. lxxvii. p. 307
Dieulafoy and Krishaber, Amer. Journ. Med. Sci., Jan. 1870, p. 234
Djurberg, Schm. Jahrb., Bd. cli. p. 84
Dujardin-Beaumetz et Hirne, Bull. Thérap., lxxxvi. p. 224, 1872
Elliott, G. F., Lancet, 1873, i. 754
Fuller, H. W., Lancet, March, 1871, p. 403
Gascoyen, Brit. Med. Journ., vol. i. p. 91, 1872
Giovanni u. Bauzoli, Schmidt's Jahrb., Bd. cli. p. 91
Hammarsten, Deutsche Klinik, 1870; Schmidt's Jahrb., Bd. cli. p. 90
Harnack, Arch. f. exp. Path. u. Pharmak., Bd. xvii. p. 185 (Chloral group)
Harnack u. Witowski, ibid., Bd. xi. p. 1
Keen and Personne, Phil. Med. Times, vol. iv. p. 385
Keen, Schmidt's Jahrbücher, clxxvii. p. 139; Am. Journ. Med. Sci., July 1875, pp. 76 and 150
Kirn, Ludwig, Allgem. Zeits. f. Psychiatrie, xxix. 1872; Practitioner, vol. x. p. 361
Leavitt, Amer. Journ. Med. Sci., Apr. 1871, p. 363
Levinstein, Lancet, i. p. 279, 1874
Lewisson, Reichert's Arb. f. Anat. u. Phys., 1870, p. 348
Liebreich, Chloralhydrat, ein neues Hypnoticum, Berlin, 1869; Wiener med. Wochens., Aug. 1869, p. 1087
Macnamara, Pract., vol. ix. 257
Mering, V., Arch. f. exp. Path., iii. 185–203; Zeits. f. phys. Chemie, vi. p. 480
Morgenstern, Wien. med. Presse, Nov. 1871, p. 1212
Mosso, Schmidt's Jahrb., clxxvii. p. 138
Murchison, Lancet, ii. p. 596, 1870
Owsjannikow, Leipz. Acad. d. W., 1871
Pellogio, Schmidt's Jahrb., Bd. cli. p. 89
Personne, Journ. de Pharm. et de Chimie, 1870, p. 1
Playfair, Lyon, Lancet, 1874, vol. i. p. 263
Rajewski, Centralbl. f. d. med. Wiss., 1870, p. 211; Schmidt's Jahrb., Bd. cli. p. 90
Rehn, Jahrb. f. Kinderkrankh., 1871, p. 430
Reynolds, Practitioner, 1870, iv. p. 188
Richardson, Med. Times and Gaz., vol. ii. p. 374, 1870
Rigden, Practitioner, vol. v. p. 151, 1870

Chloral Hydrate.

Russell, Glasgow Med. Journ., Feb. 1870, p. 209
Schmidt's Jahrb., Bd. cli.; Köhler's Abstracts of papers
Schule, Allgem. Zeits. f. Psych., xxviii. p. 1
Schulz, Arch. f. exp. Path. u. Ph., xvi. p. 305
Smith, N. R., Bost. Med. and Surg. Journ., vol. viii. p. 33, 1871
Tomaszewitz, Pflüger's Arch., Bd. ix. p. 35
Waterhouse, Practitioner, Dec. 1870, vol. v. p. 244
Watson, Med. and Surg. Reporter, Jan. 27, 1871
Widenhofer, Boston Med. and Surg. Journ., 1874

Chloride of Sodium.

Becquerel et Rodier, Gaz. de Paris, xlviii. 1844
Bert, P., Comp. Rend., lxxiii. p. 382
Berzelius, Lehrbuch, ix. p. 98
Guttmann, Klin. Woch., 1865, xxxiv.-xxxvi.
Hoppe, Deutsche Klinik, xxxii. 1863
Klein u. Verson, Centralbl. f. med. Wiss., 1867, p. 788
Lehmann, Physiol. Chem., i. p. 440, ii. 171, 241, iii. 141, 255
Müller, Inaug. Diss., Greifswald (on Pleurisy)
Nasse, H., R. Wagner's Handwörterbuch (art. Blut), p. 167
Panum, Virch. Arch., iv. 1852
Poggiale et Plouviez, Comp. Rend., xxv. p. 110
Prussak, Wien. Acad. Sitzungsber., lvi. 1876, (Abth. ii.), p. 13
Rabuteau, Bull. de Thérap., lxxxi. 1871, p. 562
Robinson, Brit. Med. Journ., 1883 (on Pleurisy)
Voit, Unters. üb. d. Einfluss d. Kochsalzes, u.s.w., München, 1860
Wiscknewsky, Canstatt's Chemie, p. 116, 1867

Chloroform.

Anstie, Stimulants and Narcotics, p. 321
Baudin, Le Progrès Méd., Sept. 1874
Bernard, Cl., Leçons sur les Anésthésiques, Paris, 1875
Bernstein, Centralbl. f. d. med. Wiss., 1867, Bd. v. p. 38; Schmidt's Jahrb., Bd. clxii. p. 218
Bert, Comp. Rend., t. lxiv. 1867; Journ. of Anat. and Phys., May, 1870, p. 312; Compt. Rend., cxiii. p. 768
Bonwetsch, Dorpater Dissert., 1869
Böttcher, Virch. Arch., Bd. xxxii. p. 126
Bowditch, H. P., and C. S. Minot, Boston Med. and Surg. Journ., May 1874
Budin et Coyne, Arch. de Phys. norm. et path., 1875, 61–100
Bufalini, Giorn. di Clin. e Therap., iii. 1884 (Chloroform water in chronic gastritis)
Carter, Brit. Med. Journ., vol. i. p. 208, 1867
Chloroform Committee, Med.-Chir. Trans., vol. xlvii. p. 326
Dogiel, Arch. f. Anat. u. Phys., 1866
English Chloroform Committee, Medico-Chir. Trans., 1864, vol. xlvii.
Eulenburg (Anæsthetics), Cent. f. d. med. Wiss., 1881, No. 6
Glover, Ed. Med. Journ., 1842, pp. 709 and 1009
Gosselin, Arch. Gén., 1848, vol. xviii. p. 385
Harley, Phil. Trans., London, 1865
Hartmann, Giessener Dissert., 1855
Hermann, Arch. f. Anat. u. Phys., 1866, p. 27
Holmes, E. L., Chicago Med. Examiner, Sept. 1868
Husemann's Abstracts in Virchow-Hirsch's Jahresber.; Schmidt's Jahrb., Bd. cli. p. 80
Knoll, Wien. Acad. Sitzber., 1874, 1876, 1877
Krukenberg, Vergleich. phys. Studien, Abth. 1, p. 77
Lallemand, Perrin, Duroy, Du Rôle de l'Alcohol et des Anésthésiques, Paris, 1860
Leute, T. D., Psychol. and Med. Legal Journ., Feb. 1875
Luchsinger, Pflüger's Archiv, xxviii. p. 61

Chloroform.

McKendrick, Coats, and Newman, Brit. Med. Journ., Dec. 18, 1880
Noel, Lond. Med. Record, 1877, p. 457
Nothnagel, Berl. klin. Wochenschr., 1866, Bd. iii.
Prevost, Pract., July, 1881
Ranke, H., Centralbl. f. med. W., 1867, p. 209, u. 1877, No. 34, p. 608
Richardson, Med. Times and Gazette, 1866–70
Sabarth, Das Chloroform, Würzburg, 1866
Sansom, Chloroform, p. 55, Philadelphia, 1866
Scheinesson, Dorpater Diss., 1868, u. Arch. d. Heilk., Bd. x. p. 36
Schenk, Sitz-berichte d. Wien. Acad., M.N. Cl., 1868, Bd. lxviii.
Schmidt's Jahrb., Bd. cxlii. cxlv. cli., H. Köhler's Abstracts
Schmidt, A., u. F. Schweiger-Seidel, Ber. d. König. Sächs. Gesell. d. Wiss. Math. Phys. Klin., 1867, p. 190
Schmiedeberg, Dorpater Diss., 1867
Simpson, Edin. Month. Journ. of Med. Sci., 1847, p. 33, and 1848, p. 315
Simonin, Centralbl. Chir., 1876, p. 234
Snow, On Chloroform and other Anæsthetics, London, 1858
Vulpian, Compt. Rend., lxxxvi. p. 1303
Westphal, Virch. Arch., Bd. xxvii. p. 409
Winslow, W. H., Phil. Med. Times, vi. p. 275

Chrysophanic Acid.

Gehe's Handelsberichte, 1878–79
Squire, Centralbl. f. d. med. Wiss., 1877, p. 384, u. 1878, p. 699

Cimicifuga.

Chapman, N., Elements of Therap., 6th ed. vol. i.
Davies, N. S., Trans. Amer. Med. Assoc., 1848, vol. i. p. 351
Young, Amer. Journ. Med. Sci., vol. ix. 1831, p. 310

Cinchonine.

Buchheim u. Loos, Eckhard's Beiträge, (Methyl compounds.)

Cocaïne.

Anrep, Pflüger's Arch. Bd. xxi. 3, 38 (with complete list of literature)
Bennett, A. Hughes, Edin. Med. Journ., Oct. 1873
Jessop, Practitioner, xxxiv. p. 1; Proc. Roy. Soc., 1885.
Koller, Cent. f. d. med. Wiss., 1874, p. 870

Codeïne, *vide* Opium Alkaloids.

Barbier, Gaz. Méd., ii. p. 147, 1834
Barnay, De la Codéïne, Paris, 1877
Baxt, W., Reichert's Arch., 1869, p. 125
Berthe, Compt. Rend., lix. p. 914, 1865
Crum-Brown and Fraser, Proceed. Roy. Soc. of Edin., xxv. Jan. 6, 1868
Des Brulais, Mon. des Hôp., xcvi. p. 767, 1856
Dumont, Mon. des Hôp., xxviii. p. 221, 1858
Falck, Deutsche Klin., 1870
Guibert, Nouveaux Méd., p. 397
Harley, Old Veg. Neurotics, p. 179
Husemann, Pflanzenstoffe, p. 155
Krebel, Med. Ztg. Russlands, 1856, p. 59
Kunkel, Journ. de Chimie Méd., xi. 223, 1833
Mitchell, Weir, Amer. Journ. Med. Sci., Jan. 1870, p. 26

Codeïne, *vide* Opium Alkaloids.

Myrtle, Brit. Med. Journ., 1874, i. 478
Ott, Opium Alkaloids
Pavy, Guy's Hosp. Reports
Schroff, Von, Pharmakologie, 3. Aufl. p. 483
Wachs, L., Das Codein, Diss. Marburg, 1858

Colchicum.

Albers, Deutsche Klinik, 1856
Bacmeister, Arch. d. Pharmacie, 1857
Bird, Urinary Deposits, Phila., 1859, p. 354
Garrod, A. B., Med.-Chir. Trans., 1858, xli. 348
Geiger, Annal. Chem. Pharm., vii. 274
Hammond, Proc. Phila. Acad. Nat. Sci., Dec. 1858
Hoppe u. Aschoff, Vierteljahrs. f. prakt. Pharm., vi.
Krahmer, Journ. f. Pharmacodynamik, ii. 561
Lewins, R., Ed. Med. and Surg. Journ., 1841, vol. lvi. p. 200
Ludwig and Pfeiffer, Arch. der Pharm., cxi. 3
Maclagan, Ed. Monthly Journ. of Med. Sci., 3rd series, vol. xiv. p. 24
Major, G. W., Canada Med. Surg. Journ., Dec. 1873
Percy, S. R., Amer. Med. Times, Apr. 1862, p. 173
Rossbach, Pharm. Unters., Bd. ii. 1876, pp. 1–58; Arch. f. d. ges. Phys., xii. p. 308
Schroff, V., Zeitschr. d. Ges. d. Aerzte, 1851, u. Oesterr. Zeitschr. f. pract. Heilk., 1856
Scudamore, On Gout, Lond. 1835
Taylor, Med. Juris., 2nd ed. vol. i.
Wood, Geo. B., U.S. Dispensatory, 13th ed. p. 1504

Colocynth, *vide* Purgatives.

Buchheim, Die scharfen Stoffe, etc.
Husemann, Handbuch. d. Toxicol., p. 525
Marmé, W., Zeits. f. rat. Mediz., xxvi. 61
Schroff, Von, Pharmacologie, 4. Aufl., p. 368, 1873

Condurango.

Brunton, Lauder, Journ. of Phys., v. 17
Ernst, Vjhrschr. f. ger. Med., xvi. 2, p. 321, u. Schmidt's Jahrb., clvii. p. 121
Friedreich, Berliner klin. Wochenschr., 1874, No. 1
Gianuzzi, Cent. f. d. med. Wiss., 1873, p. 824
Hulke, Centralbl. f. d. med. Wiss., 1872, p. 111
Obalinski, Centralbl. f. Chir., 1874, No. 12, p. 177
Riegel, Berl. klin. Wochenschr., 1874, No. 35 u. 36
Sanctis, De, Schmidt's Jahrb., clvii. p. 121
Sandahl, Hygiea, 1872, p. 14, and Schmidt's Jahrb., clviii. p. 121
Schroff, Von, Schmidt's Jahrb., clviii. p. 211

Copaiba.

Bernatzik, Prager Vierteljahrs., Bd. c. 1868, p. 239
Blanchard, Gaz. des Hôp., xl. 1852
Gubler, Comment. thérap. du Code, p. 88; Bull. de la Soc. de Thérapeut., 1e série, xvi.
Mitscherlik, Preuss. Vereinsz., xix. 22, 1848
Rees, Guy's Hosp. Rep., vol. xvii.
Schweitzer, Poggend. Ann., Bd. xvii. pp. 487 and 1095
Valentine, Grundriss der Phys.
Weikart, H., Arch. d. Heilk., 1860, p. 176
Wilks, Lancet, i. 12, Mar. 1873, p. 410

Copper.

Bailly, L'Union, 6, 1874; Schmidt's Jahrb., clxiii. 1874, iii. Bd. p. 61
Bergeret u. Mayençon, Journ. de l'Anat. et Phys., 1873
Blake, Frank's Magaz., ii. 405
Blasius, Zeitschr. f. rat. Med., 3. Reihe, Bd. xxvi. p. 240
Buchner, Toxikol., 2. Aufl., p. 525
Burq, Ducom, Schmidt's Jahrb., 1878, Bd. clxxviii. 14; Arch. de Phys. Norm. et Path., 1877, t. iv. 183
Clapton, Med. Times and Gaz., vol. i. p. 658, June, 1868
Clemens, Schmidt's Jahrb., cxxxi. p. 82, 1866
Falck, Deutsche Klinik, xi. 1859
Faulk, Deutsch. Klin., x. 430
Feltz et Ritter, Compt. Rend., lxxxiv. p. 506; *ib.* lxxxv. p. 87
Galippe, Étude toxicol. sur le Cuivre, Paris, 1875; Comptes Rendus, t. lxxxiv. pp. 404 and 718
Harnack, Arch. f. exp. P. u. Pharm., Bd. iii. p. 46, u. Bd. ix. p. 164, 1874
Hönerkopff, Ueb. d. Anwend. d. schwefelsäuren Kupferoxydes gegen Croup, Leipzig, 1852, p. 60
Lieberkühn, Poggendorff's Ann., 1852, Bd. lxxxvi.
London Clinical Soc. Transactions, 1870, p. 13
Mérat et de Lens, Dict. univ. de Mat. Méd., ii. p. 67
Mitscherlich, Müller's Arch., 1837, p. 91
Neebe, Marburger Diss., 1857
Pierre, St., u. Pécholier, Med. Centralbl., 1854 p. 270
Wibmer, Wirk. der Arzneim. u. Gifte, ii. 260, 1838

Coto.

Albertoni, Arch. f. Path. u. Pharm., xvii. 291
Burkhart, Berl. klin. Woch., 1877, p. 276
Jobst, Ber. d. deutsch. chem. Ges., 1876, No. 17

Croton Oil, *vide* Purgatives.

Adams, Husemann, Toxicol., Bd. ii. p. 443
Brunton, Lauder, Practitioner, xii. 346
Buchheim, Virchow's Arch., xii. 1
Giacomini, Stillé's Therapeutics, vol. ii. p. 451
Hertwig, Stillé's Therapeutics, 2nd ed. vol. ii. p. 449
Joret, Bull. de Thérap., lxi. p. 385, 1861
Radziejewsky, Casuistik der Vergift. bei Husemann, Handbuch, p. 442, u. Pflanzenstoffe, p. 1113
Wibmer, Wirkungen, etc., ii. 222

Cubeba.

Adams, Edinb. Med. Surg. Journ., xv. 61
Bernatzik, Prag. Vierteljahrs., 1864, Bd. lxxxi. p. 9
Clarus, Arzneiml, p. 728
Crane, Edin. Med. Surg. Journ., xxi. 302
Crawford, Edin. Med. Surg. Journ., xiv. 32
Gödecke, Preuss. Vereinsz., 34, 35, 1850

Curare.

Buchheim u. Loos, Ueber d. pharmakolog. Gruppe des Curarius, Giessener Dissert., 1870
Bernard, Cl., Leçons sur les Substances toxiques, Paris, 1857, p. 338; Revue des Sciences, 1865
Bezold, Reichert u. du Bois' Arch., 1859
Colasanti, Pflüger's Arch., Bd. xvi. p. 157
Conty et de Lacerda, Compt. Rend., lxxxix., p. 582
Eckhardt, Beitr. z. An. u. Physiol., Bd. vi. p. 19, Giessen, 1871 (Historical); Ibid. Bd. vii. p. 67

Curare.

Frey, Ludwig s Arbeiten, 1876, p. 98
Funke, Ber. d. k. sächs. Acad., 1869
Hermann, Pflüger's Arch., Bd. xviii., p. 458, 1878; Arch. f. Anat. u. Phys., 1867, 64, p. 650
Kölliker, Virch. Arch., Bd. x. p. 1
Kühne, Reichert u. du Bois' Arch., 1860, p. 477
Lautenbach, Phil. Med. Times, May 26, 1877
Preyer, Göttinger Zeitsch. f. Chemie, i. p. 381 (Curarine)
Röhrig u. Zuntz, Pflüger's Arch., Bd. iv. p. 57, 1871
Schulz, Zeitschr. f. klin. Med., iii. p. 10
Steiner, J., Reichert u. Du Bois' Arch., 1875, u. eigene Schrift., Leipzig, 1877
Tarchanoff, J., Arch. de Phys. norm. et path., 1875, 33–60
Zuntz, Pflüger's Arch., Bd. xii. p. 522, 1876

Cyanogen, *vide* Prussic Acid.

Daturia.

Laurent, Ch., Thèse, Paris, 1870, p. 22

Digitalis.

Ackermann, Deutsch. Arch. f. klin. Medicin, Bd. xi. 9, p. 135; Volkmann's Samml. klin. Vorträge, No. 48, Leipzig, 1872
Bert, P., Gaz. Méd. de Paris, xi. 1873
Boldt, Inaug. Diss., Schmidt's Jahrb., March, 1872
Böhm, Pflüger's Arch., Bd. v. 4 u. 5, p. 153, 1872
Bordier, Bull. Thérap., 1868, vol. lxxiv. p. 110
Brunton, Lauder, On Digitalis, London, 1868
Brunton and Meyer, Journ. of Anat. and Phys., vii. 1872, p. 134
Brunton and Power, Proc. Roy. Soc., 1874, No. 153
Christison, Edin. Med. Journ., vii. p. 149
Coblentz, Z. E., Strasburg, Thesis, 1862
Costa, Da, Amer. Journ. Med. Sci., Jan. 1871, p. 1
Dickinson, Med.-Chir. Trans., vol. xxxix. p. 1
Donaldson and Stevens, Journ. of Phys., vol. iv. p. 165
Dybkowsky, W., and E. Pelikan, Zeitschr. f. wiss. Zool., Bd. xi. 1852
Eulenburg u. Ehrenkaus, Med. Central-Z., xxviii. 777, 1859
Fagge and Stevenson, Proceed. of the Royal Soc. London, vol. xiv. p. 270
Fothergill, Digitalis, London, 1871; Brit. Med. Journ., pp. 5, 27, 57, 90, 115, and 146, 1871
Görtz, Schmidt's Jahrb., Bd. clviii.; Unters. üb. Digitalis-Präparationen, Dorpat, 1873
Gourvat, Gaz. Méd. de Paris. 1871
Gaunot, Phila. Med. Times, iv. 30
Hammond, Proc. Biol. Dep. Acad. Nat. Sci. Phila., Dec. 1858; Am. Med. Journ., Jan. 1859, p. 275
Homolle, Arch. Génér. de Méd., July, 1861, p. 5; Journ. de Pharm. et de Chimie (3), vii. p. 57
Köhler, H., Arch. f. exp. Path. u. Pharm., i. 2, p. 138, 1873
Köhnhorn, Lancet, 1876, i. p. 582
Koppe, Arch. f. exp. Path. u. Pharm., Bd. iii. p. 274
Kosmann, Bull. de Thérap., lix. p. 60, July, 1860.
Lorain, Paul, Journ. de l'Anat. et Phys., 1870, p. 128
Meihuizen, Arch. f. Phys., vii. p. 201, 1873
Meusnier, Aug., De l'Action de la Digitale sur la Fonction glycogénique, Paris, Thesis, 1868
Meyer, A. B., Arb. u. d. Phys. Instit. zu Zürich, Centralbl. f. med. Wiss., xvii. p. 270, 1869
Onimus, Journ. de l'Anat. et Phys., ii. 337, July, 1865

Digitalis.

Otto, Deutsch. Archiv f. klin. Med., xvi. 140
Paul, C., Bull. Thérap., 1868, lxxiv. p. 193
Perrier, Arch. f. exp. Path. u. Pharm., Bd. iv. p. 191
Quévenne et Homolle, Arch. de Phys., de Thérap., etc., par Bouchardat, i. 1854
Ranvier, Comptes Rendus, 1869, vol. lxix. p. 1327
Roucher, Practit., ix. p. 304, 1872
Sanders, Edin. Med. Journ., iv. 369
Schmiedeberg, Arch. f. exp. Path. u. Pharm., Bd. iii. p. 16; *ibid.* xvi. p. 149; Ludwig's Festgabe, i. 222
Schroff, V., Wien. W. S., xxiv.; Wochenblatt d. k.k. G. der Aerzte z. Wien, xx. xxii. 1868
Skoda, Wien. m. Presse, xiii. Jahrb., 142, p. 21, 1864
Stadion, Prager Vierteljahrs. f. d. prakt. Heilk., 1862, Bd. lxxiv. p. 97, 1872; Sydenham Soc. Year-book, 1862, p. 451
Stannius, Arch. f. Phys. Heilk., Bd. x. 1851, p. 177
Tardiau, Clinique, p. 685, Obs. viii., Paris, 1867
Thomas, Archiv f. Heilk., Bd. iv. p. 329, 1865
Traube, Annalen d. Charitékrankenh. in Berlin, 1851, Bd. ii. p. 1; Gesammelte Beiträge z. Path. u. Physiol., Bd. i. Berlin, 1871; Med. Central-Z., xxx. 94, 1863; Berl. klin. Woch., vii. 201, 213, 1870, xxxi. xxxiii. 1871
Vulpian, Comptes Rendus de la Soc. de Biol., 1855, p. 70
Weil, A., Reich. Arch. f. Anat., 1871, p. 252
Winkel, Phila. Med. Times, 1874, iv. p. 6, p. 554, 1861
Winogradoff, Virch. Arch. f. Anat., Bd. xxii. p. 457
Wood, Amer. Journ. Med. Sci., July, 1871
Wunderlich, Manual Med. Therm., Sydenham Soc. Transl., p. 325

Ditaine.

Harnack, Archiv f. exp. Path. u. Pharmak., vii. p. 126

Duboisine.

Marmé, Nachr. v. d. k. Ges. d. Wiss. u. d. G. A. Universit. zu Göttingen, 1878, No. xii. p. 413

Elaterium.

Gibson, Brit. Med. Journ., Nov. 1861
Köhler, Virch. Arch., Bd. xlix. p. 408, L. 2, p. 273, 3, p. 375, 1870
Morries, Repertor. f. Pharm., xxxix. p. 134
Schroff, Von, Pharmakologie, 4. Aufl., 371, 1873
Stillé, Therap., vol. ii. p. 459

Emetine.

Ackermann, Rostocker Diss., 1856
Carriger, J. H., New York Med. Journ., 491, 1878
Chouppe, Le Progrès Méd., 1874, p. 425; Bull. de Thérap., June, 1874, 86, p. 481
D'Ornellas, Gaz. Méd., 1873, p. 537
Duckworth, Dyce, Bartholomew Hosp. Reports, vol. v. p. 218, 1869, vol. vii. p. 91, 1871
Foulkrod, Phila. Med. Times, viii. p. 554
Harnack, E., Arch. f. exp. Path. u. Pharm., Bd. ii. p. 299, iii. 44
Magendie et Pelletier, Journ. de Pharmacie, lix. p. 223, 1817
Orfila, Toxicol., i. 551
Pécholier, Comptes Rendus, Bd. lv. 1862, p. 771; Gaz. Méd., 1862
Podwyssotski, A. f. exp. Path. u. Pharm., Bd. xi. p. 231, 1879

EMETINE.

Pollichronie, L'Ipécacuanha, Paris, 1874
Weylandt, Eckhardt's Beiträge z. Anat. u. Physiol., Giessen, 1869, v. i., u. Inaug. Dissert.
Woodhull, A. A., Atlanta Med. and Surg. Journ., 1875

ERGOT, *vide* SECALE CORNUTUM.

Bailly et Sée, Bull. Thérap., t. lxxviii. p. 435
Barlau-Fontayral, Journ. des Sci. méd. pratiques de Montpellier, tomes vi. vii.
Bodin, Journ. des Connaissances Méd., 1842
Boldt, Schmidt's Jahrb., March, 1872
Bonjean, Traité de l'Ergot de Seigle, Paris, 1845
Boreischa, Arbeit. Pharm. Lab. Moskau, i. 55
Brown-Séquard, Arch. de Phys., 1870, t. iii. p. 434
Buchheim, Berl. klin. Wochenschr., 1876, p. 309, No. xxii.; Arch. f. exp. Path. u. Pharm., Bd. iii. p. 1
Christmann, Centralbl. f. d. med. Wiss., p. 800, Nov. 1869
Clemens, Deutsche Klinik, 1865, 267
Costa, Da, Amer. Med. Journ. Sci., Jan. p. 117, 1875
Diez, Stillé's Therapeutics, 2nd ed. vol. ii. p. 585
Dragendorff u. Podwissotzky, Arch. f. exp. Path. u. Pharmak., Bd. vi. pp. 153, 192
Duboué, Recherches sur les Propriétés thérap. de Seigle ergoté, Paris, 1873
Eberty, Hallenser Diss., 1873; Schmidt's Jahrb., Bd. clviii. p. 127
Goodall, Proceed. Med. Soc. Pennsylvania, 1873
Hampel, Practitioner, vol. i. p. 263
Haudelin, Dorp. Diss., 1871; Schmidt's Jahrb., Bd. clv. p. 143
Hensinger, Journ. f. Pharmacodyn., Bd. i. p. 405
Hermann, Büchner's Repertor. f. Pharm., 1871
Hildebrandt, Berl. klin. Woch., p. 297, 1872
Holmes, Ch. L., Arch. de Physiol., t. iii. p. 384, 1870
Kersch, Betz's Memorabilien, vol. xviii.
Kitchen, Amer. Journ. Insan., July 1873
Kobert, Practitioner, xxxiii., 409
Köhler, H., Virch. Arch., Bd. lx. p. 384
Langenbeck, Berl. klin. Woch., p. 117, 1869
Le Gendre, Bull. Thérap., t. lxxvii. p. 282
Levi, Lo Sperimentale, Aug. 1875
Luton, A., Gaz. Hebdom., Oct. 1871, p. 610
Meadows, Practitioner, vol. i. 166
Nicitin, Rossbach's Pharm. Unters., Bd. iii. 1878
Nicoll, P., and Mossop, Brit. and For. Med.-Chir. Rev., vol. i. 1872, p. 252
Oldwright, Canada Med. Journ., 1870, 320, 321, 404
Ostere, Stillé's Therap., 2nd ed. vol. ii.
Poyet et Commarmond, Annal. de la Soc. de Méd. de St. Etienne et de la Loire, 1863
Ramsbotham, Principles and Practice of Obstetric Med. and Surg., Phila. 1860, p. 318
Rossbach, Pharm. Unters., Bd. i.
Salkowski, Berl. klin. Wochenschr., 1876, p. 228
Schilling, Aerztl. Intelligenzbl., 1883
Schüller, Berl. klin. Wochenschr., 1874, p. 305
Tanret, Bull. Thérap., xciii. p. 231
Tulasne, Ann. Scien. Natur. Botan., 3e série, t. xx. 1853
Vogt, P., Berl. klin. Wochenschr., 1869, No. xii. p. 117; March, 1872, p. 115
Wernich, Virch. Arch., Bd. lvi. p. 505, 1872; u. Beitr. z. Geburtsh., Bd. iii. Berlin, 1874
Winckler, Amer. Journ. Pharm., May, 1864
Woakes, Practitioner, vol. i. p. 257
Wood, Phila. Med. Times, vol. iv.
Wright, S. A., Ed. Med. and Surg. Journ., Oct. 1839, vol. lii. p. 293
Zweifel, Arch. f. exp. Path. u. Pharm., Bd. iv. p. 387

ERIGERON.

Starke, Lond. Med. Rec., 1876, p. 267

ERYTHROPHLŒUM.

Brunton and Pye, Phil. Trans., 1877, p. 627
Gallois et Hardy, Arch. de Phys. norm. et path., 1876, p. 197
Harnack u. Zabrocki, Arch. f. exp. Path. u. Ph., xv. p. 403
Sée et Bochefontaine, Compt. Rend., xc. p. 1366
Zabrocki, Inaug. Diss., Halle, 1882

ETHER.

Bowditch and Mimol, Boston Med. and Surg. Journ., May 21, 1874
Kronecker, Arch. f. Anat. u. Phys., 1881, p. 354
McKendrick, Coats, and Newman, Brit. Med. Journ., Dec. 18, 1880

ETHER OIL.

Binz, Arch. f. exp. Path. u. Pharm., Bd. v. p. 109, Bd. viii. p. 50
Böhm u. Kobert, C. f. d. med. Wiss., 1879, p. 689
Grisar, Bonner Dissertation, 1873
Högyes, Centralblatt f. d. med. Wissen., 1879, p. 32
Köhler and his pupils, Schmidt's Jahrb., Bd. clxxiv. pp. 19, 80, 121

EUCALYPTUS OIL.

Aron, Schmidt's Jahrb., Bd. clvii. p. 239
Binz, Brit. Med. Journ., i. 1874, p. 15
Bohn, Berl. klin. Wochens., p. 110, 1872
Brudell, Bull. Thérap., May, 1875, vol. lxxxix. p. 108
Cortau, Montpellier Méd., May, 1872
Gimbert, Arch. Gén., 1873, xxi. p. 141
Haller, Wien. med. Wochens., xxvi.
Keller, Wien. med. Wochens., xxii. p. 227, 1872
Köhler, H., Arch. d. Pharm., 3. Reihe, Bd. iii. Heft 2
Lorrinser, Wien. med. Wochens., xix. xx.
Martin, S., Bull. Thérap., lxxxiii. p. 453
Mosler, Deutsch. Arch. klin. Med., 1872, x. 160
Pappillon, Gaz. Hebdom., 1872, p. 501
Rabuteau, Bull. Thérap., lxxxiii. 549
Schläger, Inaug. Diss. Göttingen, 1874
Seitz, Bayer. Aerztl. Intell.-Blatt, 1870, p. 310
Siegen, Bonner Diss., 1873
Tristany, Buchner's Repertor., xix. 1870

FAT.

Lassar, Berl. klin. Wochenschr., 1879, No. xviii. p. 261
Munk, J., Verh. d. physiol. Ges. in Berlin, Jahrg. 1877–79, No. 13

FUCHSIN.

Paris, Diss., Bern, 1878

GELSEMIUM.

Bartholow, Lond. Practitioner, v. p. 203
Centralbl. f. d. med. Wiss., 1876, pp. 128, 320, 384, 608, 927; 1877, p. 783; 1878, p. 652; 1880, p. 74
Courtwright, Cincinnati Lancet and Obs., 1876, 963
Ott, Phila. Med. Times, v. p. 691, vii. p. 289
Ringer and Murrell, Lancet, ii. 1875, p. 908; i. p. 83, vol. ii. pp. 78 and 569, 1876
Tweedy, J., Lond. Lancet, 1877, i. p. 833
Wormley, Amer. Journ. Pharm., 1870

Glycerine.

Dujardin-Beaumetz et Audigé, Bull. Thérap., xci. p. 62
Eckhard, Centralbl. med. Wiss., 1876, p. 273
Lewin, L., Z. f. Biologie, 1879, Bd. xv. p. 243
Luchsinger, Pflüg. Arch., Bd. xi. p. 502; Centralbl. med. Wiss., 1877
Munk, J., Verh. d. physiol. Ges. zu Berlin, Dec. 13, 1878, u. Virch. Arch., Bd. lxxvi. Heft 1, p. 119
Schultzen, Berliner klin. Wochenschr., 1872, No. xxxv. p. 417
Schwann, Eckhart's Beiträge z. Anat. u. Physiol., viii. p. 159
Ziemssen's Encyclop., vol. xvi. for Literature

Guaiac.

Bell, Lond. Med. Gaz., Oct. 1840, p. 202
Bryden, Brit. Med. Journ., No. 47, 1857, p. 967; No. 97, p. 927, 1858
Husemann, Die Pflanzenstoffe, p. 1106
Sandras, Bull. de Thér., v. 371
Walker, Brit. Med. Journ., vol. i. pp. 528 and 660, 1864
Wood, U.S. Dispensatory, p. 1233

Hellebore.

Helm, Würzburger m. Zeitschr., ii. 5, 6, p. 448, 1861
Marmé, Z. f. rat. Med., 3. Reihe, Bd. xxvi. p. 1098
Scattergood, H., Journ. de Bruxelles, xxxix. p. 550, 1864
Schroff, Von, Prager Vierteljahrss., lxii. 1859, p. 49, 95, 106, lxiii. p. 95

Hydrastis.

Fellner, Wien. med. Jahrbücher, 1885

Hyoscyamine.

Harley, Old Veg. Neurotics
Hellmann, Beitr. d. phys. Wirk. des Hyoscyamins, Diss. Jena, 1873
Hellmann, Beitr. z. Kenntniss d. phys. Wirk. des Hyoscyamins, Jen. 1873.
Höhn, Arch. d. Pharm., 1868, p. 215
Laurent, De l'Hyoscyamine et de la Daturine, p. 15, Paris, 1870
Lemaître, Arch. Gén., 1865, vol. vi.
Oulmont, Bull. Gén. de Thérap., lxxxiii. p. 481, 1872; Practitioner, vol. x. p. 1, 1873
Schroff, V., Woch. d. Zeits. d. Gesellsch. d. Aerzte z. Wien, 1865

Iodine and Iodide of Potassium.

Annuschat, A. f. exp. P. u. Pharm., x. 261 (Action in Lead Poisoning)
Bachrach, Berl. Diss., 1878
Balfour, Ed. Med. Journ., xiii. p. 775, xiv. p. 33, xv. p. 47, xvi. p. 704; Brit. Med. Journ., 1874, i. 112
Béhier, Nerven-Centralorg., Schmidt's Jahrb., cxxvi. 162, 1865
Benedikt, M., Wien. Jahrb., xviii. ii. 94, 1862
Bernard, Cl., Arch. Génér., 1853, Bd. i. p. 5
Binz, Virch. Arch., Bd. lxii. p. 124, u. Arch. f. exp. P. u. Ph., Bd. viii. p. 309; ibid. xiii. p. 113
Böck, V., Z. f. Biol., 1869; Bd. iii. 126; Bd. v. 393; Schmidt's Jahrb., Bd. cxlv. p. 142
Böhm u. Berg, A. f. exp. P. u. Ph., v. 337, 1876
Branne, Diss., Leipzig, 1856
Buchheim, Arch. f. exp. Path. u. Pharm., Bd. iii. 104

Iodine and Iodide of Potassium.

Chuckerbutty, Brit. Med. Journ., vol. ii. pp. 61 and 85, 1862 (In Aneurysm)
Cogswell, Edinburgh, 1837
Coindet, Froriep's Notizen, i. 55, 89, 1822
Devergie, Arch. gén. de Méd., x. 2, p. 255, 1826; Frank's Mag., iii. i. p. 201
Dorpater Diss. v. Arronect, 1852; Strauch, 1852; Heubel, 1865; Sartisson, 1866
Eulenburg, Berlin. klin. Wochenschr., xvi. 1870
Fournier, Centralbl. f. d. med. Wiss., 1878, p. 55
Issersohn, Berl. Diss., 1877
Greenhalgh, Brit. Med. Journ., vol. i. p. 52, 1868
Handfield, Jones, Beale's Arch., i.
Heubel, E., Dorpat. Diss., 1865, p. 70
Kümmerer, Virch. Arch., Bd. lix. p. 459; Bd. lx. p. 527
Keith, Edin. Med. Journ., xviii. p. 1077, 1873
Kochler, Deutsche Zeitschr. f. pract. Med., 1877, No. xi.
Melsens, Schmidt's Jahrb., Bd. cxxxiv. 19, 1867; Mémoire sur l'Emploi de l'Iodure de Potassium pour combattre les Affections Saturnines mercurielles et les allid. consécut. de la Syphilis. Bruxelles, 1868
Pellikan, V., Beiträge zur Pharm. u. Tox., Würzb., 1858, p. 118
Rabuteau, Gaz. Méd. de Paris, xix. p. 190, xxii. p. 302, xxiii. p. 313, 1869
Rilliet, Bull. de l'Acad. Roy., xxv.
Ringer, Practit., March, 1872, vol. viii. p. 129
Rose, Arch. f. path. Anat., 1866; Bd. xxxv.
Rösler, Frank's Mag., ii. p. 120, 136
Sée, Lond. Med. Rec., i. pp. 757, 777
Sharpe, T. S., Amer. Journ. Med. Sci., Jan. 1876, p. 124
Taylor, R. W., Amer. Journ. Syphil. and Derma., April, 1873
Wallace, I., Liverpool Med. and Surg. Rep., 1871

Iodoform.

Behring, Wien. med. Blätter, 1884, No. 9
Binz, Arch. f. exp. P. u. Ph., viii. 309
Elsberg, Phila. Med. Times, Oct. 4, 1873, vol. iv. p. 4
Féréol, Bull. Thérap., t. lxxiv. p. 400, May, 1868
Högyes, Arch. f. exp. P. u. Ph., x. 228
Izard, A. A., New Treat. of Vener. Diseases, Boston, 1872
Kennedy, S., Med. and Surg. Rep., Jan. 1870, p. 50
Lazansky, Centralbl. Chir., 1876, 219
Moleschott, Wien. med. Wochenschr., 1878; Lond. Med. Rec., Nov. 1878, pp. 350 and 464
Oberländer, Centralbl. f. d. med. W., 1879, p. 336
Pelletan, Phila. Med. Times, iv. 695
Völker, G., Bull. Thérap., t. lxxiii. p. 493, Dec. 1867

Ipecacuanha, *vide* Emetine.

Ackermann, Beobachtungen üb. physiol. Wirk. d. Emetica, Rostock, 1856, 4. Diss.
Cunningham, Edin. Med. J., vii. p. 25, July, 1861
Duckworth, Dyce, St. Barth. Hosp. Rep., v. p. 230, 1869, vii. p. 98, 1871
Higginbottom, Brit. Med. Journ., vol. i. p. 143, 1869
Pécholier, Comp. Rend., vol. lvi. p. 718, 1863
Schuchard, Arzneim., p. 586
Wibmer, Wirk. d. Arzneim. u. Gifte, ii. 77

Iron.

Becquerel, Simon's Chemistry, vol. ii. p. 254
Bernard, Cl., L'Union Méd., 1854

Blake, Journ. of Anat. and Phys., p. 280, Nov. 1868
Complete list of Literature (228 Nos.) by Scherpf in Rossbach's Pharmakolog. Unters., 1877, Bd. ii.; later works, Hamburger Z. f. phys. Chem., v. 1; Hoppe-Seyler, ii. p. 191
Cutler & Bradford, Amer. Journ. Med. S. f. 1878, p. 78
Mialhé, Chim. Appliquée, Paris, 1856
Mitscherlich, C. g. Preuss. Vereins-Z., 1846, xxi.
Nasse, Lond. Med. Rec., 1877, p. 498; Wagner's Handwörterb., Bd. i. (art. Blut)
Podrowsky, W., Virch. Arch., Bd. xxii. 5 and 6, p. 476, 1861
Quevenne, Mémoire sur l'Action phys. et thérap. des Ferrugineux, Arch. de Phys., de Thérap. et d'Hygiène, Oct. 1854, p. 93
Quincke, Ueb. Siderosis, Festschr. z. Haller's Jubelf. Bern; Reichert u. Du Bois' Arch., vi. p. 757, 1868
Sasse, A., Vierteljahrs. f. prakt. Heilk., 1866, 2. Bd.
Scherpf, Resorpt. u. Assim. d. Eisens, Würzb. 1878
Simon, Animal Chem., Lond., 1845, Syd. Soc. ed.
Tiedemann u. Gmelin, Heidelberg, 1820.

Irritants, *vide* Oil of Mustard.

Jaborandi, *vide* Pilocarpine.

Carville, Journ. de Thérap., 1875, p. 81
Féréol, Journ. de Thérap., Jan. 1875, p. 45
Galezowski, Med. Times and Gaz., 1877, ii. 558
Greene, Phila, Med. Times, vi. p. 56
Hardy, Journ. d. Thérap., 88, p. 469, 1875
Harnack u. Mayer, Arch. f. exp. Path. u. Phar., xii. p. 366
Langley, J. N., Brit. Med. Journ., 1875, vol. i. p. 241; Journ. d. Phys., 1878, p. 339; Journ. Anat., x. 188, 194
Luchsinger, Pflüger's Arch., xv. 482
Pillicier, Inaug. Diss., Bern., 1875; Med. Centralbl., 1876, p. 430
Purjesz, Deutsch. Arch. klin. Med., xvii. p. 533
Ringer, Lancet, i. 1875, p. 159; Lond. Pract., xvii. p. 401
Schwann, Med. Centralbl., 1874, p. 440
Scotti, Berl. klin. Wochensch., 1877, p. 141
Stumpf, Deutsch. Arch. f. klin. Med., xvi. p. 255
Tweedy, Lancet, i. 1875, p. 159
Weber, Med. Centralbl., 1874, p. 770

Jalap, *vide* Purgatives.

Jequirity.

Warden and Waddell, The Non-bacillar Nature of Abrus-Poison, Calcutta, 1884

Kawa-Kawa.

Lewin, Ueber Piper Methysticum, Berlin, 1886

Lactic Acid.

Auerbach, A., Deutsch. Zeitschr. f. pract. Medicin, 1877, No. xlvii.
Bötticher, Berl. klin. Wochens., 1877, p. 537
Erler, Centralbl. med. Wiss., 1876, p. 658
Fischer, Lond. Med. Rec., 1877, p. 193
Lothar, Meyer, Virch. Arch., Bd. lxvi. p. 120
Mendel, Deutsch. med. Wochens., 1876, No. 17
Preyer, Centralbl. med. Wiss., 1875, p. 577

Lanolin.

Liebreich, O., Berl. klin. Wochens., 1885, No. 47; Deutsch. med. Wochens., 1886, No. 28

Lead.

Annuschat, A. f. exp. Path. u. Pharm., Bd. vii. p. 45, and Bd. x. p. 261
Bardenhewer, E., Berl. klin. Wochensch., 1877, 126
Blake, Edin. Med. and Surg. Journ., lvi. 1, p. 116, 1841
Chatin, Comptes Rendus, Soc. Biolog., t. iv. 1862, p. 84
Cours, A. de, De l'Hémianesthésie saturnine, Paris, 1875
Debove et Renaut, Le Progrès Méd., 1876, 151
Eulenburg, A., Deustch. Arch. für klin. Med., Bd. iii. p. 506
Falck, Virch. Handbuch d. spec. Path. und Ther., ii. 1, 1855
Frank, A., Deutsch. Arch. klin. Med., xvi. 423
Friedländer, Virch. Arch., Bd. lxxv. p. 24, 1879
Gusserow, Arch. f. path. An., Bd. xxi.
Harnack, A. f. exp. P. u. Pharm., Bd. iii. 54, 1874, Bd. ix. 152
Henle, Zeitschrift f. rat. Med., 3. R. Bd. iv., u. Handb. d. rat. Path., 1847, Bd. ii. 179
Hermann, Arch. f. Anat. u. Phys., 1867, 64
Reubel, Pathogen. u. Sympt. d. chron. Bleivergift., 1871; Virch. u. Hirsch's Jahrbücher, 1871, Bd. i. p. 316
Hitzig, Studien ü. Bleivergift., 1868
Kussmaul u. Meyer, Arch. f. klin. Med., Bd. ix. 283
Lancereaux, E., Comptes Rendus de la Soc. Biol., liv. 3rd ser. 1862, p. 84
Lewald, Unters. üb. d. Ausscheid. von Arzneim. aus dem Organismus, Breslau, 1861
Lewy, E., Schmidt's Jahrb., Bd. clii. p. 250
Malassez, Arch. de Phys., 1874, p. 50
Manouvriez, Arch. d. Phys. normale et Pathol., 1870, 411, 1876, 762; Recherches cliniques sur l'Intox. Saturnine locale et directe, Paris, 1874
Mason, New York Med. Journ., 1877
Paul, C., Arch. Gén., 5th series, vol. xv. 1860, p. 513
Remak, Arch. f. Psychiatr. u. Nervenkr., Bd. ix. Heft 3, p. 510
Renaut, Gazette Méd., 1878, No. 32, u. Centralbl. f. d. med. W., 1879, p. 159.
Rosenstein, Arch. f. path. Anat., Bd. xxxiv. 1867, p. 4
Rosenstirn, Rossbach's pharmak. Unters., Würzburg, 1874
Tanquerel des Planches, Die gesammten Bleikrankh., übers. v. Frankenberg, 1842
Trousseau, Froriep's Notiz., xviii. No. 13, p. 207, 1827
Wood, Geo. B., Therapeutics, vol. i. p. 158

Lithium, *vide* Alkalies.

Gibb, Report of Brit. Assoc. for Advancement of Science, 1864
Mitchell, Weir, Amer. Journ. Medical Science, Oct. 1870, p. 443

Lobelia.

Ott, I., Bost. Med. and Surg. Journ., 1875, vol. xcii. p. 124; Phila. Med. Times, vi. p. 121

Magnesium, *vide* Alkaline Earths.

Manganese.

Charvet, Bull. de Thérap., lxxviii. p. 80, 1870, Lungengangrän.
Garrod, Med. Times and Gaz.
Gmelin, U.S. Dispensatory
Laschkewitz, Journ. de Bruxelles, t. xliv. p. 534, June 1867

Manganese.

Leared, Glasgow Med. Journ., Jan. 1865, p. 488
Pétrequin, Nouvelles Recherches du Manganèse, 2e éd. Paris, 1852; Bull. Thérap., Mar. 1852, p. 193
Williams, American Journ., N.S. cxvii. p. 74, Jan. 1870

Massage.

Zabludowski, Cent. f. d. med. Wiss., 14, 1883, p. 241

Mercury.

Baerensprung, Ann. d. Charité, 1856, Bd. vii. p. 2
Bamberger, Wien. med. Wochenschr., 1876, Nos. xi. u. xiv.
Boeck, V., Z. f. Biologie, v. 3, 1869; Schmidt's Jahrb., Bd. cxlv. p. 142
Cash, Proc. Phys. Soc., Dec. 12, 1885; Journ. Phys., vol. vii. (Perchloride)
Foot, A. W., Dub. Journ. Med. Sci., 1873
Fürbringer, Berl. klin. Wochenschr., 1878, No. xxiii. p. 332
Hassenstein, Königsberger Diss., 1879
Heilborn, Arch. f. exp. Path. u. Pharm., Bd. viii. p. 361
Jendrássik, Deutsch. Arch. f. klin. Med., xxxviii. p. 499 (Calomel)
Keyes, E. L., Amer. Journal Med. Sci., Jan. 1876, p. 17
Kölliker, Th., Verh. d. Würzburger phys. med. Ges., N.F., Bd. x. 1877
Kussmaul, Unters. üb. d. constit. Mercurial., 1861, p. 17
Lewin, Charité-Ann., Bd. xiv.
Locke, Pract., xxxvii., p. 170
Mussy, N. G. de, Gaz. des Hôpitaux, 1868
Oetlingen, V., Dorp. Diss., 1848
Overbeck, Mercur. u. Syphil., Berlin, 1861
Rindfleisch, Arch. f. Dermatol., 1870
Saikowski, Virch. Arch., Bd. xxxvii. p. 346
Schlesinger, Arch. f. exp. Path. u. Pharm., xiii. p. 317
Sigmond, Mercury, Blue Pill, and Calomel, Lond., 1840
Sigmund, Wien. med. Wochenschr., 1859
Stern, Berl. klin. Wochenschr., 1878, p. 59
Voit, Ueb. d. Aufnahme des Q. u. seiner Verb. und Körper, in his Phys. chem. Unters., 1857
Wilbouchewitcz, Arch. de Physiol., Sept. 1874, p. 509
Zeitsch. f. Therapie, 2, 1884 (Tannate)

Methylene-Blue.

Ehrlich, Deutsch. med. Woch., 1885, No. 4, 1886; Centralbl. f. d. med. Wiss., No. 8, 1885

Morphine, *vide* Opium Alkaloids.

Muscarine.

Bäuerlein, Zur Accommodat. des menschl. Auges, Würtzburg, 1876
Boehm, Arch. f. exp. Path. u. Ph., xix. p. 87
Bogoslowsky, Centralbl. f. d. med. Wiss., 1870, p. 97
Harnack, Arch. f. exp. Path. u. Pharm., Bd. iv. p. 168, 1875
Högyes, Arch. f. Anat. u. Phys., 1882, p. 37
Jordan, Arch. f. exp. Path., viii. p. 15
Krenchel, Arch. f. Ophthalm., xx. ii. p. 134
Ott and Woodfield, Journ. of Phys., i. p. 193

Muscarine.

Schmiedeberg u. Koppe, Das Muscarin, Leipzig, 1869
Schmiedeberg u. Harnack, Arch. f. exp. Path. u. Pharm., Bd. vi. p. 101, 1876
Weinzweig, Archiv f. Anat. u. Phys. (Phys. Abth.), 1882, p. 527

Musk.

Barbier, Mat. Méd., ii. p. 217
Filehne, Sitzungsber. der Erlanger phys. med. Ges., 1876; u. Centralbl. f. d. med. Wiss., 1876, p. 880
Jörg, Materialien z. e. z. Arzneimittellehre, p. 285, Leipzig, 1825
Tralles, Com. de rebus in Sc. Natur. et Med. gestis, xxvi. p. 434
Trousseau et Pidoux, Traité, etc., 8e éd. ii. p. 187

Naphthalin.

Rossbach, Berl. klin. Wochenschr., 1884, Nos. 24, 42, 46, p. 279

Narceine, *vide* Opium Compounds.

Albers, Virch. Arch., vol. xxvi. p. 225
Baxt, Reichert's Arch., 1869, p. 112
Belner et Debout, Bull. Thérap., t. lxvii. p. 145
Bernard, Cl., Arch. Générales, 1874. 6e sér. t. iv. p. 459
Eulenburg, Schmidt's Jahrb., Aug. and Oct. 1866, cxxxi. p. 22
Fronmüller, Schmidt's Jahrb., Bd. cxli. p. 15
Harley, The Old Veg. Narcotics, p. 143; Pennsyl. Hosp. Reports, 1868
Husemann, Pflanzenstoffe, p. 184
Kersch, S., Schmidt's Jahrb., Bd. cxli. p. 15
Liné, Journ. de Pharm. et de Chimie, 4e sér. t. iii. p. 386
Mitchell, Weir, Amer. Journ. Med. Sci., Jan. 1870, p. 17
Oetlinger, Inaug. Diss., Tübingen, 1866
Schroeder, V., Arch. f. exp. Path. u. Pharmak., Bd. xvii. p. 96

Narcotics, *vide* Opium Alkaloids.

Rumpf, Centralbl. d. med. Wiss., 1884, p. 366

Nicotine.

Albers, Deutsche Klinik, 1851, No. 32
Anrep, V., Du Bois' A. f. An. u. Phys., Phys. Abth., Jg. 1879; Suppl. Bd. p. 167; u. Jg. 1880, p. 209
Basch, V., u. Oser, Wien. med. Jahrb., 1872, p. 367
Benham, W. T., West Riding Lunatic Asylum Rep., vol. iv., p. 307, 1874
Bernard, Cl., Substances Tox., pp. 399, 410
Bernstein u. Dogiel, Verhandl. des nat.-med.-Vereins zu Heidelberg, iv. 28
Bibra, V., Die Narkot. Genussmittel, 1855, p. 297
Blatin, Recherches phys. et clin. sur la Nicotine et le Tabac, Paris, 1870
Bohm, Herzgifte, Würzburg, 1871, p. 12
Bon, Le, Med. Centralzeit., xli. 1, June, 1872
Böttger, Buchner's Neue Repert. der Pharm., xvi. 579
Brodie, Phil. Trans., 1811, p. 178
Buchheim u. Loos, Ueb. d. Gruppe d. Curarins, Diss., Giesen, p. 48
Eulenburg u. Vohl, Vierteljahrsschr. f. Gerichtl. Medicin, Bd. xiv., No. 6, p. 249

NICOTINE.

Grünhagen, Centralbl. für med. Wiss., 1863, p. 577
Hammond, Amer. Journ. Med. Sci., p. 282, 1857
Haughton, p. 55
Hirschmann, L., Reich. Arch., 1863, p. 309
Husemann, Handb. d. Toxicol., vol. ii. 483
Kölliker, Virch. Arch., x. p. 253, 1856
Krocker, Berl. Diss., 1855
Namias, Comp. Rend., lix. p. 90, 1864
Nasse, V., Beitr. z. Darmbewegung, Leipzig, 1866
Orfila, Mémoire sur la Nicotine et sur la Conicine, Bruxelles, Youker frères, 1851
Praag, L. v., Virch. Arch., Bd. viii. p. 56
Reil, Journ. f. Pharmacodyn., Bd. ii. p. 203
Rogow, Zeitschr. f. rat. Med., xxix. p. 1
Rosenthal, Centralbl. f. d. med. Wiss., 1863, p. 737
Roy and Graham Brown, Journ. of Phys., vol. vi.
Savory, The Lancet, 1863, vol. i. p. 549
Schmiedeberg, Sitzber. d. K. Sächs. Acad., 1870
Sée, Nouveau Dict. de Méd. V., art. Asthma, p. 715, 1865; Journ. of Anat., May 1870, p. 315
Surminsky, Zeitschr. f. rat. Med. (3), xxxvi. p. 205
Traube, Allgemeine med. Central-Zeit., 1862; Centralbl. f. d. med. Wissens., 1863, pp. 111, 159
Truhart, Dorpater Diss., 1869
Tscheschichin, Reich. u. Du Bois' Arch., 1868, p. 151
Uspensky, Reich. u. Du Bois' Arch., 1868, p. 522
Vulpian, Comptes Rend. de la Soc. de Biol., 1851 p. 151
Wertheim, Zeitschr. d. k. k. Gesellsch. d. Aerzte z. Wien, 1851, 8.

NITRIC OXIDE.

Podolinsky, Arch. f. ges. Physiol., 1872, Bd. vi. p. 553

NITRITE OF AMYL.

Aldridge, Ch., West Riding Lunatic Reports, vol. i. p. 71
Amez-Droz, Arch. de Phys. Norm. et Path., Sept. 1873, p. 467
Arb, a. d. physiol. Inst. z. Leipzig, 1869; Journ. of Anat. and Phys., vol. v. p. 93; Lond. Clin. Soc. Reports, vol. iii.
Balard, Ann. de Chimie et de Phys., xii. 1844, p. 294
Berger, O., Allgem. med. Central-Zeit., May 1871
Brunton, Lauder, Lancet, vol. ii. p. 97, 1867
Brunton and Gresswell, St. Barth. Hosp. Rep., 1876, p. 143 (other nitrites)
Filehne, Pflüger's Archiv, Bd. ix. p. 470; and Arch. f. Anat. u. Physiol., 1879, p. 385; Berl. klin. Wochensch., Nov. 4, 1875
Fothergill, Brit. Med. Journ., 1874, i. 77
Gamgee, A., Philos. Trans., 1868, p. 589
Giacosa, Z. f. physiol. Chemie, iii. p. 54
Gray, St. Clair, Glasg. Med. Journ., 1871, p. 188
Guthrie, Ann. d. Chem. u. Pharm., Bd. iii.
Hoffmann, F. A., Reichert's Arch., 1872, 747
Jolyet u. Regnard, Centralbl. f. d. med. Wiss., 1876, p. 860; Gaz. Méd. de Paris, 1876, No. 29
Kraepelin (abst.) in Rivista sperim. di Freniatria, anno ix., 1883, p. 124
Ladendorf, Berl. klin. Wochensch., No. 43, 1874, 537
Mayer, S., A. f. exp. P. u. Pharm., v. 55, 63
Mitchell, Weir, Phila. Med. Times, 1872, vol. v. p. 353
Pick, über d. Amylnitrit, 26. Aufl. bei Hirschwald, Berlin, 1877; mit ausführlicher älterer Literaturangabe, Centralbl. med. Wiss., No. 55, p. 865, 1873; Deutsch. Arch. klin. Med., xvii. 143
Putnam, Mary, Jacobi's New York Med. Rec., Jan. 1875, p. 11
Richardson, B. W., Trans. Brit. Med. Assoc. for Adv. of Science, 1864–1872; Brit. and For. Med.-Chir. Rev., July 1867
Schuller, Berl. klin. Wochensch., No. 25, 1874, 294
Sebold, L. Th., Inaug. Diss. Marburg, 1874
Urbantschitsch, Wien. med. Presse, 1877
Wood, Amer. Journ. Med. Sci., July, 1871, p. 39

NITROBENZOL.

Bahrdt, Arch. f. physiol. Heilk., 1871, p. 320
Filehne, A. f. exp. P. u. Ph., ix. p. 339
Guttmann, Arch. f. Anat. u. Phys., 1866
Helbig, Deutsche mil.-ärztl. Zeitschr., Bd. ii. 1873
Letheby, Med.-Chirurg. Review
Lewin, Virchow's Arch., lxxviii. p. 193, 1879
Mering, V., Centr. f. d. med. Wiss., 1875, 945
Poincaré, Centralbl. f. d. med. Wiss., 1879, p. 937

NITROGEN.

Chevreul, Nouv. Bullet. d. l. Soc. Philomet., 1816
Meyer, L., Zeitschr. f. r. Med., N.F., t. viii. p. 256
Regnault et Reiset, Compt. Rend., t. xxvi.

NITROGLYCERIN.

Bruel, Thèse, Paris, 1876
Brunton, Lauder, and Tait, St. Bartholomew's Hosp. Rep., 1876, p. 140
Green, Practitioner, xxviii. 102
Murrell, Lancet, 1879, pp. 80, 113, 225
Pelikan, Beiträge

NITROUS OXIDE.

Amory, N.Y. Med. Journ., Aug. 1870, p. 1
Bert, Gaz. d. Hôp., 1879, Nos. xxxvii. et xli.; Compt. Rend., lxxxvii. p. 728; ibid. lxxxix. p. 245
Cotton, Phys. Action of Nitrous Oxide Gas, Phila. 1871
Goldstein, Pflüger's Arch., 1878, Bd. xvii. 331
Hermann, L., Arch. f. Anat. u. Physiol., 1864, p. 521
Jolyet et Blanche, Arch. de Phys., July 1873, p. 364
Thomson, E., Phil. Med. Times, Nov. 15, 1873, p. 97, vol. iv.
White, T. W., Dental Mat. Med., Phila. 1868
Zuntz, Pflüger's Arch., xvii. 135

OIL OF CAJUPUT.

Claiborne, Gaillard's Med. Journ., Virginia, U.S.A.

OIL OF MUSTARD.

Heidenhain, Pflüger's Arch., Bd. iii. p. 504; Bd. v. p. 309; Bd. vi. p. 20
Köhler, Centralbl. f. d. med. W., 1878, pp. 433, 450
Naumann, Prag. Vierteljahrsschr., Bd. lxxvii. p. 1
Paalzow, Pflüger's Arch., 1871, vol iv. p. 492

OIL OF TURPENTINE.

Crucis, Léon, De la Térébenthine Paris, thesis, 1874
Fleischmann in Rossbach's Pharm. Unters., Bd. ii. Vgl. ätherische Oele
Heppe, Journ. f. Pharmacodyn., Bd. i. p. 105
Kobert, R., Centralbl. f. med. Wiss., 1877, p. 129

OPIUM ALKALOIDS.

Albers, Arch. f. path. Anat., Bd. xxvi. p. 229
Baker, Morrant, St. Barth. Hosp. Rep.
Baxt (Thebaine), Wien. Acad. Sitzber., 2. Abth. Bd. lvi. p. 189; u. Arch. f. Anat. u. Phys. 1869, p. 128, Ludwig's Arbeiten

Opium Alkaloids.

Bernard, Cl., Leçons sur l'Anésth. et s. l'Asphyxie, Paris, 1875; Arch. Gén. p. 455, vol. iv. 6th ser. 1864
Boeck, V., Unters. üb. d. Zersetz. d. Eiweiss. München, 1871
Bouchardat, Schmidt's Jahrb., Bd. cxx. p. 280
Brunton u. Cash, Cent. f. d. med. Wiss., p. 241, 1886 (Morphine)
Buskirk, Washington Post, Jan. 33, 1878
Chalkius, Quart. Journ. Psychol. Med., 1868, vol. ii. 739
Charvet, Pereira's Mat. Med., vol. ii. p. 1035, Phila. 1854
Chastaing, Compt. Rend., xciv. 44 (Morphine)
Dain, Amer. Med. Journ., July 1874
Dietl and Vintschgau, Pflüg. Arch., Bd. xvi. p. 316
Dragendorff, Pharm. Zeitschr. f. Russland, 1866
Eckhard, C. u. F., Eckhard's Beiträge z. An. u. Phys., Bd. viii. p. 79, 138, 1878 (Morphine)
Eulenburg (Narcein), Deutsch. Arch. f. klin. Med., Bd. i. p. 55
Fiset, Morrison, N.Y. Med. Rec., July 1874, p. 342
Gscheidlen (Morphin), Unters. a. d. physiol. Lab. in Würzburg, Bd. ii. 1869
Hall, Marshall, Memoirs on the Nervous System, London, 1837, p. 7
Harley, Old. Veg. Neurotics, 107, London, 1869
Kauzmann, Dorpater Diss., 1868
Kölliker, Arch. f. path. Anat., Bd. x.; Virch. Arch., Bd. x. p. 248
Literature, complete, Arch. f. Path. u. Pharm. vii. 24
Loomis, A., New York. Med. Rec., 1873
Meihuizen, Pflüger's Arch., Bd. vii. 1873, p. 201
Mitchell, Weir, Amer. Journ. Med. Sci., Jan. 1869, p. 37, Jan. 1870, p. 17
Müller (Thebaia), Marburger Dissert., 1868
Nasse, Beitr. z. Physiol. d. Darmbew., Leipzig, 1866
Nothnagel, Handb. d. Arzneim., Berlin, 1870, p. 8; (on Intestine) Virchow's Archiv, lxxxix. p. 1
Oetinger (Narcein), Tübinger Diss., 1866
Paby, Med. Times and Gaz., June 1869, p. 641
Reese, Amer. Journ. Med. Sci., Jan. 1871, pp. 133, 373
Salvioli, Ludwig's Arbeiten
Schröder, V., Arch. f. exp. Path. u. Pharm., xvii. p. 96
Smith, E., Lancet, vol. i. p. 419, 1854
Stolnikow, Zeitsch. f. phys. Chemie, viii. p. 236
Wachs, üb. Codein, Marburger Diss., 1868
Witkowski (Morphine), Arch. f. exp. Pathol. u. Pharm., Bd. vii. p. 247. Complete Literature
Wood, Bost. Med. Surg. Journ., vol. lix. p. 268, 1858

Organic Acids, *vide* Acids.

Oxydimorphin.

Diedrich, Inaug. Diss. Göttingen, 1883

Oxygen.

Afanassiev, Ber. d. k. sächs. Ges. d. Wiss., 1873
Assmuth, Dorp. Diss., 1864
Bert, Leçons sur la Respiration
Binz (Ozone), Berl. klin. Wochensch., 1884, No. 20
Buchheim, Arch. f. exp. P. u. Ph., Bd. iv. p. 137
Donders, Pflüger's Arch., Bd. v. p. 20
Dybkowski in Hoppe-Seyler's Med.-Chem. Unters., Bd. i.
Estor et St. Pierre, Journ. de l'Anatomie et de la Phys., t. ii. 106
Fernet, Ann. d. Sciences nat., vi. t. viii.
Friedlander u. Herter, Z. f. physiol. Chem., iii. 19
Gorup-Besanez, Annal. d. Chem. u. Pharm., Bd. cx. u. cxxv.
Hücker, Dissert. Dorpat, Riga, 1863
Herter, Ueber d. Spannung des O. im arteriellen Blut, Z. f. physiol. Chem., iii. 98, 1879

Oxygen.

Hoppe-Seyler, Med. Chem. Unters., Bd. i., in Arch. f. Physiol., Bd. vii. 9; Physiol. Chimie, i. pp. 7, 39
Hüfner, Zeitsch. f. phys. Chemie, i. pp. 317, 386, u. Centralbl., 1878, p. 710
Liebig, G., Aerztl. Intelligenzbl., 1879, No. xix.
Magnus, Poggendorf's Ann., Bd. xl. p. 583, u. lxvi. p. 177
Manassein, Centralbl. f. m. Wiss., 1871, xliv. p. 688
Meyer, Lothar, Zeitschr. f. rat. Med., No. 1, Bd. viii. p. 256
Müller, W., Wien. Acad. Sitzber., Bd. xxxiii. 99
Pflüger in seinem Arch., Bd. 1, p. 274
Regnault et Reiset, Compt. Rend., t. xxvi. pp. 3, 4, 17
Schmidt, Al., Ozon im Blut, Dorpat, 1872; Hämatol. Studien, Dorpat, 1865; Centralbl. f. d. med. Wiss., 1867; Ber. d. k. sächs. Ges. d. Wiss., M. phys. Cl., Bd. xix.; Arch. f. path. Anat. u. Phys., Bd. xlii.
Schönbein, Roy. Soc. Proc. 1840

Pellitory.

Browne, London Practitioner, xvii. p. 86

Peppermint.

Marcusson, Hallenser Diss., 1877

Pepsin.

Albertoni, Centralbl. f. d. med. Wissensch., 1878, p. 641
Beale, Arch. f. 1850, i. iv.
Davidson, Practit., March 1872, vol. viii. p. 131
Dowdeswell, Pract., Papain, vol. xxx. p. 485
Ewald, Frerichs u. Leyden's Z. f. klin. Med., i. p. 231
Gray, Jas., Edinb. Med. Journ., Jan. 1853, p. 31
Joynes, L. S., Richm. and Louisville Med. Journ., 1869
Leube, W. O., Deutsches Arch. f. klin. Med. ix. 532; x. 1, 1872
Manassein, Virch. Arch., 1872, vol. lv. p. 413
Roberts, Sir W., Digestive Ferments
Tuson, Med. Times and Gaz., vol. ii. 1882
Wayne, Amer. Journ. Pharm., 1868

Pepton.

Chandelon, Ber. d. deutsch. Chem. Gesell., xvii. p. 2143 (1885)
Penzoldt, Deut. med. Wochenschr., Bd. iv. pp. 413, 425
Schmidt-Mühlheim, Ludwig's Arb.
Seegen, Pflüger's Arch., vol. xxv. p. 165; ibid. vol. xxviii. p. 990
Tanret, Comptes Rendus, xcii. 1163

Permanganate of Potassium.

Kronecker, Ludwig's Arbeiten, 1871, p. 183

Peroxide of Hydrogen.

Assmuth, Dorp. Diss., 1864
Guttmann, Virch. Arch., Bd. lxxiii. p. 23, u. lxxv. p. 255
Richardson, Lancet, vol. i. p. 383, 1862
Schwerin, Arch. f. path. Anat., lxxiii. p. 23
Stöhr, Arch. f. klin. Med., 1867, Bd. iii. p. 421

Petroleum.

Lassar, Berl. klin. Wochenschr., 1879, No. xviii. p. 261

Phosphorus.

Abstract of the Literature up to 1867, in Schmidt's Jahrb., Bd. cxxxvi. p. 209
Andant, Journ. de Méd. de Bruxelles, 1868–79
Anstie, Pract., 1873, vol. xi. 103
Aufrecht, Deut. Arch. f. klin. Med. xxiii. 331
Bauer, Zeitschr. f. Biologie, Bd. vii.–xiv.
Bollinger, Deutsch. Arch. klin. Med., Bd. v. p. 149, 1869; Bd. vi. p. 94, 1870
Demarbaix and Wilmart, Presse Méd. belge, xxi. p. 197, xxv. 1869; Schmidt's Jahrb., Bd. cxliv., cxlv. p. 152
Dybkowsky, Hoppe-Seyler's Med.-Chem. Unters., Heft i. p. 54
Eames, H., Dub. Journ. Med. Sci., Jan. 1872, p. 1
Eulenburg u. Guttmann, Aertz. Literaturblatt, 1868, No. 12; Syd. Year Book, 1868, p. 450
Falk, jun., Arch. f. exp. Path. u. Pharm., Bd. vii. 1877
Friese, Berl. klin. Wochens., 1877, p. 437
Gamgee, Priestley, and Larmuth, Journ. Anat. and Phys., xi.
Hartmann, Dorp. Diss., 1866
Hermann u. Brunner, Pflüger's Arch., Bd. iii. p. 1; Deut. Arch. klin. Med., p. 198
Köhler, Berl. klin. Wochens., 1870
Kohts, O., Pflüg. Arch., Bd. xiii. p. 84; Deutsch. Arch. f. klin. Med., Bd. v. p. 168
Lebert and Wyss, Arch. Gén., 1868
Mayer, Canstatt's Jahresb., Bd. v. 1862, p. 123
Meyer, Arch. f. exp. Path. u. Ph., xiv. p. 313
Munk u. Leyden, Die acute Phosphorverg., Berl. 1865
Ossikowsky, Wien. med. Presse, 1872
Percy, S. R., Prize Essay, Trans. Amer. Med. Assoc., 1872, p. 659
Poulet, Gaz. Méd. de Paris, Aug. 1872
Schiff, Arch. f. exp. Path. u. Pharm., Bd. ii. p. 347
Schuchardt, Henle und Pfeufer's Arch., N.F., Bd. viii. p. 235
Schulzen et Riess, Ann. de Charité, t. xv.
Sotnitschewsky, Z. f. physiol. Chemie, iii. p. 391, 1879
Thompson, J. A., Lond. Pract., vol. xi. pp. 13 and 27, July 1873
Vetter, Virch. Arch., Bd. liii. p. 186, p. 21
Vigier, Bull. Thérap., xc. Jan. 1876
Virchow, sein Archiv, Bd. xxxi. p. 399, 1864
Vulpian, Arch. de Phys., 1868 (Compounds)
Wegner, Virch. Arch., Bd. lv. p. 11, June 22, 1872; Wien. med. Presse, Jan. 1872
Weyl, Arch. d. Heilk., 1878, p. 163

Physostigma.

Amagat, Journ. de Thérap., 1876
Arnstein, C., u. Sustschinsky, Unters. Phys. Lab. Würzburg, 2. Th. p. 86
Bezold, V., u. Götz, Central. f. d. med. Wissens., April 6, 1867, p. 234
Complete Literature by Harnack, Arch. f. exp. Path. u. Pharm., Bd. v. p. 401
Edwards, J. B., Med. Times and Gaz., vol. ii. p. 212, 1864
Engelhardt, Unters. a. d. Phys. Lab. Würzburg, 2. Th. 526
Fraser, Ed. Med. Journ., ix., Aug. and Sept., pp. 123 and 235, 1863; Trans. Roy. Soc., Edinb., xxiv. 73, 1867, xxvi. 1872
Frölich, Pharm. Unters., i. 56
Fronmüller, Deutsch. Klinik, 32, 35, 1864
Gräfe, A. von, Deut. Klinik, No. xxiv. 1863
Graser, Arch. f. exp. Path. u. Pharmak., Bd. xvii. Heft 5
Grünhagen, Virch. Arch., Bd. xxv. p. 521

Physostigma.

Harley, Journ. de l'Anat. et de la Phys., 1864, pp. 140–152
Harnack u. Witkowski, Arch. f. exp. Path. u. Pharm., v. 142
Hirschler, Wien. med. Woch., 13, xlii. 1863
Höring, Würtemberg. Corresp.-Blatt, xli. 1863
Jones, W., Pract., 1869, vol. iii. p. 163
Keyworth, Glas. Med. Journ., N.S. 1869, i. p. 54
Kleinwächter, Revue Photogr. des Hôpitaux, 1870
Köhler, Arch. f. exp. Path. u. Pharm., Bd. i. 280, 1873
Laschkewitsch, Virch. Arch., 1866, Bd. xxxv. 294, 1866
Laurence, Ophthal. Hosp. Reports, iv. 1, 129, 1863
Leven u. Laborde, Schmidt's Jahrb., Bd. cxlvi. p. 136
Lewisson, Reich. Arch., 1870, p. 346
Maynard, Virchow's Archiv, vol. lxxxix. p. 258
Merson, Journ. of Mental Sci., Jan. 1875, vol. xx. p. 602
Ogle, Brit. Med. Journ., vol. i. p. 673, 1863
Papi, C. Schmidt's Jahrb., cxlii. 287; Gaz. Lomb., 1858
Röber, Berlin. Diss., 1868
Robertson, Argyll, Edinb. Med. Journ., 1863
Roemer, St. Louis Med. and Surg. Journ., 1873, 367
Rosenthal, Reich. Arch.
Rossbach, Pharmak. Unters., Heft i. 1873
Schiff, Centralbl. f. d. med. Wiss., 1873, p. 37
Subbotin, Arch. f. klin. Med., Bd. vi. 285, 1869
Tachau, Arch. d. Heilk., 1865, p. 70
Tweedy, J., Pract., 1883, vol. xxxi. p. 321
Vée et Leven, Comptes Rend. de la Soc. de Biol., 1865, p. 161
Vintschgau, Moleschott's Unters., ix. 800, 1865
Watson, E., Ed. Med. Surg. Journ., xii. p. 11, May, 1867; Centralbl. f. d. med. Wiss., 1868, p. 143
Weber, Klin. Monatsschr. f. Augenheilk., Aug. 1863
Westermann, Schmidt's Jahrb., Bd. cxxxviii. p. 290

Picrotoxine.

Luchsinger, Physiol. Stud., Leipzig, 1882
Rovighi e Santini, Pubblicaz. del R. Instit. di Stud. sup. in Firenze, 1882, p. 1

Pilocarpine.

Complete List of Literature (117 Authors), by Lewin, Berl. Charité Annal., v. Jahrg. 1878, p. 559

Prussic Acid.

Bernard, Cl., Leçons sur les Subst. toxiques, p. 193, Paris, 1857
Bischoff, Ueb. Vergift., Wien, 1844
Böhm, Arch. f. exp. P. u. Pharm., Bd. ii.
Böhm u. Knie, Arch. f. exp. Path. u. Therap, Bd. ii. pp. 135, 137
Bunge, A. f. exp. P. u. Pharm., xii. 1 (Gangas).
Coze, Gaz. Méd. de Paris, 1849; Comptes Rend., t. xxviii. 1849, p. 780
Fagge, Hilton, Guy's Hosp. Rep., 1868, p. 259
Funke, Ber. d. k. sächs. Gesell. d. Wiss. z. Leipzig, Bd. xl. 1859, p. 28
Gähtgens in Hoppe-Seyler's Med. Chem. Unters., Berl., 1866, pp. 324, 346
Geinitz, E., Pflüger's Arch., Bd. iii. 1870, p. 46
Harley, Lond. Phil. Trans., 1865, p. 706
Hiller, Centralbl. f. d. med. W., 1877, 577
Hiller and Wagner, Lancet, 1877, ii. 933
Hoppe-Seyler, Med. Chem. Unters., Berl. 1867 140; Virch. Arch., Bd. xxxviii. p. 475

Prussic Acid.

Hünefeld, der Chemismus in d. thierischen Organisation, Leipzig, 1840
Jones, J., N.Y. Med. Rec., vol. ii. p. 459
Keen, Proc. Phil. Acad. Nat. Sci., 1869
Kiedrowski, Virch. Jahresb., 1858, vol. i. p. 48
Kölliker, Virch. Arch., Bd. x. p. 272
Lankester, Ray, Pflüger's Arch., vol. ii. 1869, p. 492
Laschkewitsch, Reich. Arch. f. Anat., 1868, p. 653
Lautenbach, Phil. Med. Times, May 26, 1877
Lecorché and Meuriot, Arch. Gén., t. xi. 6e série, pp. 539, 543
Lewisson, Reich. Arch., 1873, p. 352
Preyer, Die Blausäure, physiol. Unters., 2 Thl. Bonn, 1868 u. 1870, contains a full *résumé* of the literature of the subject up to 1870
Preyer, Arch. f. exp. Path. u. Ph., Bd. iii. p. 381
Rossbach u. Papilsky in Rossbach's Pharm. Unters., Bd. iii. 1877
Schönbein, Schmidt's Jahrb., Bd. cxl. 1868, p. 161
Schubarth, Horn's Arch. f. med. Erf., Berl. 1824
Sobernheim, J. F., Handb. d. prakt. Toxicol., Berlin, 1838
Stannius, Arch. f. Anat., 1858, p. 95
Vietz, F. B., Med. Jahrb. d. k. k. österreich. Staates, Bd. ii. 1814
Wahl, De Vi et Effectu Acidi Hydrocyanati, Bonn, 1865
Wallach, Ber. d. deutsch. chem. Ges., x. 2120

Ptomaïnes and Leucomaïnes.

Brieger, Üb. Ptomaïne
Gautier, Sur les Alcaloïdes dérivés de la destruction bactérienne, etc., Paris (Masson), 1886
Guareschi u. Mosso, Les Ptomaïnes, Turin, 1883
Nicati et Rietsch, Compt. Rend., xc. p. 928
Selmi, Sulla Ptomaïne, etc., Bologna, 1878; ibid. 1882

Purgatives.

Asp, Ludwig's Arbeiten, 1868
Brieger, Arch. f. exp. Path., Bd. viii. p. 355
Brunton, Lauder, Med. Press and Circular, Dec. 31, 1873, p. 590; Pract., vol. xii. pp. 342 and 403
Buchheim, Arch. f. physiol. Heilk., Bd. xiii. u. xiv.; Virchow's Archiv, Bd. xii. p. 1
Falck, Virchow's Archiv, Bd. liv. p. 173
Hay, Matthew, Journ. of Anat. and Physiol., vol. xiv.; Lancet, April 21, 1883
Headland, Action of Medicines, London, 1867, p. 443
Köhler, H., Virchow's Archiv, Bd. xlix. p. 408
Moreau, F. A., Mémoires de Physiologie, Paris, 1877; Comp. Rend., t. lxvi. 1868; Arch. Générales, 6e sér. t. xvi. p. 234
Mosler, Berl. klin. Wochensch., No. xlv. 1873, p. 533
Nasse, O., Beitr. z. Physiol. der Darmbewegung, Leipzig, 1866
Radziejewski, Reichert und Du Bois-Reymond's Arch., 1870, p. 37
Röhrig, A., Stricker's Med. Jahrb., 1873, p. 240; Exp. Unters. ü. d. Phys. d. Gallenabsonderung, Wien, 1873
Rutherford, British Med. Journ., vol. i. p. 362, 1877; Schmidt's Jahrb., 1878, Bd. clxxvii. p. 11 ff.
Schiff, Il Morgagni, 1867
Simon, Gus., Arch. d. klin. Chir., xv. p. 99
Thiry, Sitzungsber. d. Wiener Acad., Math. Naturw. Cl., 1864, Bd. i. p. 95; Gaz. Méd., 1871
Vulpian, Gaz. Méd., 1873, p. 300
Wood, Amer. Journ. Med. Sci., vol. lix. p. 395, 1870

Pyridine.

McKendrick and Dewar, Proc. Roy. Soc., 1874, p. 432
Sée, Germain, Comptes Rend. Ac. Scien., 1886

Pyrogallol.

Bullet. de Thérap., Jan. 30, 1883; Cent. f. d. med. Wissensch., No. 42, 1883

Quebracho Bark.

Gutmann, Arch. f. exp. Path. u. Pharm., xiv. p. 451
Harnack u. Hofmann, Zeits. f. klin. Med., Bd. viii. Apr. 6, 1884

Quinine.

Albertoni et Ciotto, Bull. Thérap., xc. p. 403
Appert, Virch. Arch., Bd. lxxi. p. 364
Baldwin, W. O., Amer. Journ. Med. Sci., Apr. 1847, p. 292
Bauer u. Künstle, Deutsch. Arch. f. klin. Med., Bd. xxiv. p. 53
Baxter, Buchanan, Practitioner, vol. viii. pp. 325–330
Binz, Zur Salicylsäure- u. Chininwirkung, Arch. f. exp. Path. u. Pharm., Bd. i. p. 18, 1873, Bd. v. p. 39, Bd. vii. p. 275; Lond. Pract., p. 4, vol. v. 1870; Virch. Arch., Bd. xlvi. 1864, p. 138
Bochefontaine, Recherches exp. à la Contractilité de la Rate, Paris, 1873; Arch. de Physiol., July 1873
Boeck, Von, Unters. ü. d. Zersetzung des Eiweisses im Thierkörper, Munich, 1871
Briquet, Traité Thérap. de Quinquina, Paris, 1855
Brunton, Lauder, and Pardington, St. Bartholomew's Hosp. Rep., 1876, p. 150
Burt, Med. and Surg. Reporter, 1870
Chalvet, Schmidt's Jahrb., Bd. cxli. p. 152; Gaz. Hebdom., 2e sér. t. v. 1868
Chaperon, Pflüg. Arch. f. Phys., 1869, vol. ii. p. 295
Chiara, L'Un. Med., Nov. 20, 1873, p. 795
Clapton, Med. Times and Gaz., vol. i. p. 462, 1864
Complete Collection of Literature up to 1875 (82 Nos.) in Binz, Das Chinin, Berlin, bei Hirschwald, 1875
Cutler, J. R., Psych. and Med. Legal Journ., 1875
Dietl, Wien. med. Wochensch., 1852
Dupuis, L'Action Phys. de Quinine, Paris, 1877
Eulenburg, A., Reich. Arch. f. Anat., 1865, p. 423
Geltowsky, Lond. Pract., vol. viii. p. 321
Hallier, Das Cholera-Contagium, Leipzig, 1867
Hamilton, J. B., Ind. Med. Gaz., 1873
Henbach, Arch. f. exp. Path. u. Pharm., Bd. v. p. 233; Centralbl. med. Wiss. 1874, p. 673
Henke, Deutsch. Arch. f. klin. Med., Bd. xii. p. 630
Hesse, Ber. d. deutsch. Chem. Ges., x. 2152
Jacobowitch, Magnan, Revue des Sci. Méd., 1873
Jerusalimsky, Ueb. d. phys. Wirk. d. Chinin, Berl., bei Hirschwald, 1875; Centralbl. med. Wiss., 1876, p. 476
Jones, Bence, Lectures on Path. and Therap., London, 1867
Kerner, Lond. Pract., vol. x. 169; Pflüg. Arch. f. Phys., 1870, p. 93
Köhler, Zeitschrift f. d. ges. Naturwiss. f. Sachsen in Thüringen, Bd. xlix., u. Sitzber. der Naturforscher-Gesellsch. zu Halle, 1876
Lauderer, Repertorium f. Pharm., Bd. xxv. 1836, 1839, 1842
Liebermeister, Deutsch. Arch. f. klin. Med., Bd. iii. 1867

Quinine.

Magendie, Gaz. Méd., 1847
Martin, A., Inaug. Diss., Giessen, 1868
Melier, Mémoires de l'Acad., t. xii. p. 722, 1843
Monteverdi, Ann. et Bull. de la Société de Méd. de Gand, May 1871
Mosler, Path. d. Leukämie, Berl., 1872, p. 451
Naunyn u. Quincke, Reich. Arch. f. Anat., 1869
Pagès, Gaz. Méd., 1846
Personne, Centralbl. f. d. med. Wiss., 1879, p. 110
Piorry, Arch. Gén. de Méd., 1847
Pringle, Abs. on Diseases of the Army, Lond., 1765
Rabuteau, Bull. Thérap., t. lxxv. p. 475
Rapmund, Deutsch. Klin., 1874, p. 51
Raucillia, L'Union Méd., 1873
Rausoné, Inaug. Diss. Bonn, 1871
Renzi, D., Bull. Thérap., xci. p. 45
Rhoads, E., and W. Pepper, jun., Pennsyl. Hosp. Rep., vol. i. 1868
Rich, Charleston Med. Journ. and Review
Rossbach, Pharm. Unters., Bd. i. Heft iii.
Rovighi e Santini, Pubblicaz. del R. Instit. di Stud. sup. in Firenze, 1882, p. 1
Sayre, Amer. Pract., 1871, p. 260
Scharrenbroich, Inaug. Diss. Bonn, 1867
Schlockow, De Chini sulfurici Vi physi. nonnulla Exp. Vratisl., 1860
Schroff, Stricker's Med. Jahrb., 1875, p. 175
Schulte, A., Centralbl. f. d. med. Wiss., p. 727, Nov. 1871
Walranen, Boston Med. and Surg. Journ., 1873
West, Jos. J., Savannah Journ. Med., vol. i. p. 19, 1858
Wilson, J. S., South. Med. and Surg. Journ., p. 341, 1855, Sept. 1860
Zunst, Beit. z. Phys. des Blutes, Inaug. Diss. Bonn, 1868; Arch. f. exp. Path., Bd. ii. p. 343

Resorcin.

Kaegler, Prakt. Arzt. xxv. p. 260 (cuts short facial erysipelas)

Rhubarb, *vide* Purgatives.

Ricin, *vide* Purgatives.

Rue.

Cahours et Gerhard, Annales de Chim. et de Physique, xxiv. p. 227, 2e sér.; Pharmaz. Jahresb. v. Wiggers, viii. 50
Cooper, G. T., Med. Exam., N.S. ix. 720
Gorup-Besanez, Neues Repert. für Pharmaz., xix. 385
Hélie, Bull. de Thérap., xv. 55; Schmidt's Jahrb., xxi. p. 275

Saccharine.

Roscoe, Recent Progress in Coal-tar Industry, Roy. Inst. Proc., 1886

Salicylates and Salicylic Acid.

Bälz, Arch. d. Heilk., xviii. p. 60
Bochefontaine and Chabret
Bochefontaine, Le Progrès Méd., 1877, p. 630
Buchholtz, Arch. f. exp. Path. u. Pharm., Bd. iv.; Dorpat. Diss., 1866
Byasson, Centralbl. f. Chir., 1877, p. 809
Callender, Trans. Lond. Clin. Soc., ix. p. 9

Salicylates and Salicylic Acid.

Danewsky, Arbeit. im Pharm. Lab. Moskau, i. p. 190
Drasche, Centralbl. f. Chir., 1876, 777
Farsky, Sitzber. d. k. Akad. d. Wiss., Bd. ii. lxxiv. p. 49
Jacoud, Le Progrès Méd., 1877, pp. 528, 745
Laborde, Bull. de Thérap., xciii. p. 276
Marmé, Göttinger Nachricht., 1878, No. vii. p. 229
Martenson, Petersb. med. Zeits., 1875, p. 343
Meyer u. Kolbe, Journ. f. prakt. Chem., Bd. xii. p. 9
Musey, Bull. Thérap., xiii. p. 318
Riess, Berl. klin. Wochens., xii. 1875, pp. 674, 675
Robin, Lond. Med. Rec., 1877, p. 151
Scheffer, Marburger Diss., 1860
Schroeder, Deutsch. Arch. f. klin. Med., xviii. 516
Sée, Bull. de l'Acad. Méd., 1877, p. 697
Senator, Berl. klin. Wochens., 1875, p. 461
Stricker, A. E., Berl. klin. Wochens., xiii. p. 1, 1876
Weber, Bull. de Thérap., xciii. p. 328
Wolffberg, Deutsch. Arch. klin. Med., xv. p. 403
Wolfsohn, Königsberg. Diss., 1876; Centralbl. f. med. Wiss., 1877, p. 30
Zeits. f. phys. Chemie, vi. 2

Salicylic Acid.

Bertagnini, Annal. d. Chemie u. Pharm., Heft xcvii. p. 248, 1856
Binz, Niederrh. Ges. f. Nat. u. Heilk. Sitz., v. 6, Dec. 1875 u. 20. März 1876; u. Berl. klin. Wochenschr., 1876, No. xxvii.; Arch. f. exp. Path., vii. p. 275
Butt, Centralbl. f. d. med. Wiss., 1875, No. xviii. p. 276; u. Zur antipyret. Bedeutung d. Salicylsäure u. d. salicyls. Natrons, Stuttgart, 1876
Ebstein, Berl. klin. Wochenschr., 1873, 1875, 1876
Feser u. Friedberger, Arch. f. wiss. u. pract. Thierheilk., 1875, Heft ii. iii. u. vi.; 1876, Heft ii. u. iii.
Fleck, Benzoësäure, Carbolsäure, Salicylsäure, Zimmetsäure, Vergl. Versuche, München, 1875
Fliescher, Centralbl. f. d. med. Wiss., p. 628, 1876, No. xxxvi.; u. Arch. f. klin. Med. 1877, Bd. xix.
Fürbringer, Centralbl. f. d. med. Wiss., p. 273, 1875, No. xviii.
Gedl, M., Med. Centralbl., 1876, p. 403
Goltdammer, Berl. klin. Wochenschr., 1876, No. iv.
Köhler, H., Centralbl. f. d. med. Wiss., 1876, 161, 195; Deutsch. Zeitschr. f. pract. Med. v. Kunze, 1877
Kolbe, Journ. f. pract. Chem., N.F. Bd. xii. 1875, Bd. xi. p. 9
Möli, Berl. klin. Wochenschr., 1875, No. xxviii.
Salkowski, Berl. klin. Wochenschr., 1875, No. xxii.
Thiersch, Klin. Ergebnisse der Lister'schen Wundbehandl. in Volkmann's Samml. klin. Vorträge, Nos. lxxxiv. and lxxxv.
Wolfsohn, Dissert. Königsberg, 1876

Sanguinaria.

Smith, R. M., Amer. Journ. Med. Sci., Oct. 1876, p. 346

Santonin.

Andaul, Brit. Med. Journ., vol. i. p. 186, 1872
Berg, Württemberg. Medic. Correspond., 1862

Santonin.

Binz, Arch. f. exp. P. u. Ph., Bd. vi. p. 300
Brown, Dyce, Brit. and For. Med.-Chir. Rev., April 1871, p. 472
Falck, Deutsche Klinik, 1860
Frohnstein, Diss., Bern., 1877
Guépin et Martin, Ann. de Thérap., 1862
Krauss, Inaug. Diss., Tübingen, 1869
Manns, Marburger Diss., 1858
Rose, Virch. Arch., Bd. xvi. p. 233, Bd. xviii. p. 15, Bd. xix. p. 522, Bd. xx. p. 245, Bd. xxviii. p. 30, Bd. xxx. p. 442
Walz, Jahresber. f. pract. Pharm., Bd. xv.
Whitehead (in amenorrhœa), Lancet, Sept. 5, 1885

Saponin.

Buchheim u. Eisenmenger, Eckhardt's Beiträge, v. 3, Giessen, 1869
Harnack, Arch. f. exp. Pharm., ii. 1874
Keppler, Berl. klin. Wochenschr., 1878, p. 475
Köhler, H., Die totale Anästh. durch Saponin, Halle, 1873
Lautenbach, Phila. Med. Times
Pelikan, Berl. klin. Wochenschr., xxxvi. 1867, p. 375; u. Bulletin d. k. Acad. zu St. Petersburg, xii. 1867, p. 253
Przybyszewski, Arch. f. exp. Path., v. 137
Schmiedeberg, Ludwig's Festgabe, p. 127

Savin.

Letheby, London Lancet, vol. i. p. 677, 1845

Silver Nitrate, etc.

Bogolowski, Arch. f. path. Anat., Bd. xlvi. p. 413
Charcot et Ball, Gaz. Méd., 1864
Curci, Lond. Med. Rec., 1877, p. 72
Eichmann, Husemann's Toxicologie, 871
Fragstein, Berl. klin. Wochens., 1877, 294
Frommann, Virch. Arch., Bd. xvii. p. 135
Jacobi u. Gissmann, A. f. exp. P. u. Pharm., Bd. viii. p. 217, 1878
Higginbottom, Lond. Pract., vol. ii. p. 34, 1869
Kramer, Das Silber als Arzneim., Halle, 1845
Neumann, Med. Jahrb., 1877, p. 369
Pepper, Trans. Phila. Coll. Phys., 1877
Reimer, Arch. f. Heilk., Bd. xvi. p. 296
Rosenstirn in Rossbach's pharmak. Unters. Bd. i.
Rouget, Arch. de l'Anatom. et de Physiol., July 1873, p. 356, u. Jahresber. d. ges. Med., 1870, Bd. i. p. 363
Roszahegzi, A. f. exp. P. u. Pharm., Bd. ix. p. 289, 1878
Weichselbaum, Centralbl. f. d. med. Wiss., 1878, p. 954
Yandell, Amer. Pract., June 1872

Sodium Salts, *vide* Alkalies.

Barnard, Phys. Exp., t. ii. p. 393; Phila. Med. Times, vol. v.
Bidder and Schmidt, Canstatt's Jahresb., 1852
Gaule, Arch. f. Anat. u. Phys., 1878, p. 295
Grandeau, Robin's Journ. de l'Anat., 1864, p. 378
Guttmann, Virch. Arch., Bd. xxxv. p. 450
Longet, Physiologie, Paris, 1861, t. i. p. 196
Münich, Arch. Vereins Gemeinsch. Arb., Bd. vi. p. 369, 1863
Nothnagel, Virchow's Archiv
Plouviez, Com. Rend., t. xxv. 1847, p. 113
Podkaepow, Virch. Arch., Bd. xxxiii. p. 507
Rabuteau, L'Union Méd., t. xii. p. 186, 1871
Roberts, Urinary and Renal Diseases, Am. ed., 1866, p. 240

Spigelia.

Eberle, Materia Med. and Therap., vol. i.
Spalsbury, Bost. Med. and Surg. Journ., vol. lii. p. 72, 1855

Squill.

Dassen, Groninger Diss., 1834
Husemann, Arch. d. Pharmacie, Bd. vi. Heft iv. 1876; Deutsch. med. Wochens., xiii. p. 149, 1875; Lond. Med. Rec., 1876, p. 120; Toxicologie, Bd. i. 413
Jarmersted, A. f. exp. P. u. Pharm., 1879, Bd. ii. p. 22 (Scillain)
Schroff, Wien. Wochenschr., 1864, 43, p. 673
Wolfring, Bayer. ärztl. Intelligenzbl., 1842

Staphysagria.

Boehm u. Serek, Arch. f. exp. Path., v. p. 311

Strychnine.

Amagat, Journ. d. Thérap., 1875, p. 467
Ambrosoli, Gaz. Méd., 1857, p. 525
Bennett, Brit. Med. Journ., vol. ii. p. 436, 1874
Bernard, Cl., Leçons sur les Substances Toxiques, Paris
Bochefontaine, Arch. de Phys. norm. et path., 1873, p. 664
Brown-Séquard, Comptes Rendus, 1849, 29, p. 672
Buchheim, R., Arch. f. d. ges. Phys., xi. 177–181
Buchheim u. Engel, Beitr. z. Arzneim., Leipzig, 1849, i. p. 92
Cohn, Wien. med. Wochensch., Nos. xlii., xlvii. 1873
Deen, Van, Phys. de la Moelle épinière
Eckhard, Hermann's Handb. d. Phys., Bd. ii. Th. 2, p. 40, etc.
Falck, F. A., jun., Vierteljahrsschr. f. gerichtl. Méd., N.F. Bd. xx. 2, 193, xxi. 12, u. xxiii. 1874
Falck, senior, Virch. Arch., xlix. 1870, p. 458
Freusberg, Arch. f. exp. Path. u. Pharm., Bd. iii. pp. 204 and 348, 1875
Gärtner, Sep.-Abdruck a. d. lxxx. Bd. d. k.k. Acad. d. Wiss., iii. Abt. Dec. Hft. Jahrg. 1879
Grützner, Pflüger's Archiv, 1876, Bd. xi. p. 601
Harley, Lancet, July 1856, p. 40
Heinemann, C., Virch. Arch., Bd. xxxiii. p. 394
Hippel, V., Wirk. des Strych. auf d. Augen, Berlin, 1873, p. 77
Husemann, Arch. d. Pharm., Bd. viii. Heft 3, 1877
Jacoud, Pathol. Interne, i. 441
Jochelsohn, Rossbach's pharm. Unters., Bd. i.
Jolyet, Gaz. Méd. de Paris, 1877 (Iodide of ethyl compound and cicutine).
Klapp, Journ. Mental Diseases, Oct. 1878
Kölliker, Virch. Arch., Bd. x. p. 239, 1856
Lange, F., Königsberger Diss., 1874
Leube, Arch. f. Anat. u. Phys., 1867, p. 629
Ludwig and Walton, Ludwig's Arbeiten, 1882
Magendie, Paris Soc. Philom., N. Bull., i. 368, 1880
Mager, S., Wiener Acad. Sitzungsber., Math. Nat. Wiss. Cl., 3. Abth. 1871
Martin-Magron et Buisson, Brown-Séquard's Journ. de la Phys., 1860, t. iii. pp. 130, 342
Matteucci, Traité des Phénom. électro-physiol., Paris, 1844
Meschede, Berl. klin. W., 1878, No. xxiv.
Möller, Ugeskr. f. Läger, 3. R. Bd. xix. 161
Moreau, Comptes Rend. Soc. de Biol., 1855, p. 173
Nagel, Die Behandl. d. Amaurosen u. Amblyopien m. Strych., Tübingen, 1871
Nasse, O., Centralbl. f. med. Wiss., 1865, p. 787
O'Farrell, L., Phila. Med. Times, vol. iii. p. 311
Orr, Gaz. Méd., July 6, 1872
Pelikan, E., Beitr. z. ger. Med., p. 92, 1858
Ranke, Virch. Arch., lxxv. p. 1, 1878

Strychnine.

Richter, Zeitschr. f. rat. Med., iii. Bd. xviii. p. 76
Rosenthal u. Leube, Arch. für Anat. u. Phys., 1867, p. 629
Rossbach, Centralbl. f. med. Wiss., xxiv. p. 369, 1873
Rossbach u. Jochelsten, Würtzburg. Abhandl., 1873, p. 92
Savory, Lancet, May 1863; Schmidt's Jahrb., cxix. p. 286, 1863
Schiff, Schmidt's Jahrb., Bd. cxli. p. 25
Schlesinger, Wien. med. Jahrb., 1874
Schroff, V., jun., Wien. med. Jahrb., 1872, p. 420; Wochenbl. d. Zeitschr. d. Aerzte zu Wien, No. 14, 1866
Schultzen, Arch. f. Anat. u. Phys. (Dubois), p. 491, 1864
Spence, A. T., Edinb. Med. Journ., July 1866, xii. i. p. 44
Tschepke, Deut. Klinik, xiii. 1861
Uspensky, Arch. f. Anat. u. Phys., 1868, iv. p. 522
Valentin, Path. der Nerven, p. 327, pt. ii. Leipzig, 1864; Arch. de Physiol., Nov. 1870, p. 125, t. iii. p. 120
Wittich, Bericht Fortschritte Anat., 1857, p. 434
Wundt, Unt. d. Med. d. Nerven, Stuttgart, 1871

Sugar.

Mering u. Musculus, Hoppe-Seyler's Z. f. phys. Ch., i. p. 395 and ii. 177

Sulphide of Calcium.

Ringer, Sydney, Lancet, Feb. 1874, vol. i. p. 264

Sulphur and Sulphuretted Hydrogen.

Dorpater Diss. Krause, 1853; Trachtenberg, 1861; Höppener, 1863
Hermann, Toxicologie
Hoppe Seyler, Centralbl. f. d. med. Wiss., 1863, p. 433; Med. chem. Unters., 1867, Bd. ii.
Kunkel, Pflüger's Arch., Bd. xiv. p. 344
Poleck, Die chem. Natur der Minengase, etc., Berl. 1867
Regensburger Centralbl. med. Wiss., 1877, p. 328
Rosenthal u. Kaufmann, Reichert's Arch., 1866, p. 647
Schmiedeberg, Arch. d. Heilk., 1867, Bd. viii. p. 422
Sertoli, Instituto fisiol. di Pavia, 1869

Tannic Acid. Tannin.

Hennig, Arch. d. Pharm., Bd. cxxxiii.
Lewin, Arch. f. exp. Path. u. Ph., xxxi. p. 74
Rosenstirn, Rossbach's pharmak. Unters., Bd. i.
Schroff, Die Pflanzenstoffe, Lehrb. d. Pharm., 1. Auflage

Thuja.

Köhne, Göttingen. Diss., 1883

Thymol.

Husemann, Arch. f. exp. Path. u. Pharm., Bd. iv. 1875, p. 288
Küssner, Habil.-Schr., Halle, 1878
Lewin, Centralbl. f. d. med. Wiss., 1875, p. 324

Tin.

White, Archiv f. exp. Path. u. Pharmak., 1880, viii. p. 33

Tobacco, *vide* Nicotine.

Benham, W. T., West Riding Lun. Reports, vol. iv. p. 305, 1874
Bernard, Cl., Substances Toxiques, p. 410
Copeland, Dict. of Pract. Med., art. Colic
Hirschmann, Reich. Arch., 1863, p. 309
Husemann, Handb. d. Toxicol., vol. ii. 483
Nasse, Beiträge z. Phys. der Darmbewegung, Leipzig, 1866
Reil, Journ. f. Pharmacodyn., Bd. ii. p. 203
Rosenthal, Centralbl. f. med. Wiss., 1863, p. 738
Traube, Allgem. med. Central-Zeit., 1862
Uspensky, Reich. Arch., 1868, p. 525
Vohl u. Eulenburg, Arch. Pharm. (2), 1873, Bd. cxlvii. 130–6
Vulpian, Comptes Rendus de la Soc. de Biol., 1859, p. 151

Trimethylamine (or Propylamin).

Husemann, Selige, Arch. f. exp. Path. u. Pharm., Bd. vi. p. 55

Valerianate of Amyl.

Wade, W. F., Brit. Med. Journ., i. 1874, p. 741

Veratrine.

Bezold, V., u. Hirst, Unters. a. d. Würzburger physiol. Laborator., Bd. i. 1869 (contains the entire older Literature)
Brunton and Cash, Cent. f. d. med. Wiss., 1883, p. 81; Journ. of Physiol. iv. 1
Claus, Journ. of Anat., viii. p. 228
Eisenmenger, Ueb. d. Einfluss d. Gifte u. d. Zuckungscurve des Froschmuskels, Diss. Giessen, 1862, p. 40
Fick u. Böhm, Verhandl. d. phys. med. Ges. in Würzburg., N.F. Bd. iii. pp. 198, 229
Guttmann, Reich. Arch. f. Anat., 1866, p. 498
Jones, Phila. Med. and Surg. Reporter, xvii. p. 361, 1872
Kölliker, Virch. Arch., Bd. x. p. 257, exp. ix.
Ott, Toxicol. Studies, Phila. 1874
Pellikan, V., u. Kölliker, Würzburg. Verh., ix. p. 106
Praag, L. von, Virch. Arch., vii. p. 252, 1854
Ringer, Arch. of Med., vii. Feb. 1882; Pract., vol. xxx. p. 17
Robin's Journ. de l'Anat., 1868, t. v. p. 206; Gaz. Méd. de Paris, No. 5, p. 69, 8, p. 120, 10, p. 148, 11, p. 167, 1857
Rossbach, Clostermeyer, u. Harteneck, in Rossbach's pharm. Unters., Bd. i. ii., and Pflüger's Arch., Bd. xiii. u. xv.
Rossbach u. Anrep, Pflüger's Arch., Bd. xxi. 240, 1880
Taylor, Med. Jurispr., 2nd ed., Lond. 1873
Turnbull, Investigation of Extern. Applic. of Veratria, London, 1829; Schmidt's Jahrb., ii. 379
Weyland, Vergleich. Unters. üb. Veratrin, Sabadillin, Delphinin, etc., Giessen, 1869
Wood, H., Amer. Journ. Sci., Jan. 1870, p. 36

Whey.

May, Bair. ärztl. Intelligenzbl., 1879, No. xii. p. 123

Zinc.

Harnack, Arch. f. exp. Path. u. Pharm., Bd. iii. p. 44
Meihuizen, Arch. f. ges. Physiol., Bd. vii. p. 212
Michaëlis, Arch. f. phys. Heilk., 1851, p. 109
Schlokow, Deutsch. med. Wochenschr., 1879, Nos. xvii. u. xviii. pp. 208 and 221

n@8/6

PRINTED BY
SPOTTISWOODE AND CO., NEW-STREET SQUARE
LONDON