A botanical dictionary: or elements of systematic and philosophical botany / [Colin Milne].

Contributors

Milne, Colin, 1743 or 1744-1815.

Publication/Creation

London : Bye & Law for H.D. Symonds, 1805.

Persistent URL

https://wellcomecollection.org/works/t2cm2mjh

License and attribution


This work has been identified as being free of known restrictions under copyright law, including all related and neighbouring rights and is being made available under the Creative Commons, Public Domain Mark.

You can copy, modify, distribute and perform the work, even for commercial purposes, without asking permission.

wellcome collection

Wellcome Collection
183 Euston Road
London NW1 2BE UK
T +44 (0)20 7611 8722
E library@wellcomecollection.org
https://wellcomecollection.org

36845/B


MILNE'S

BOTANICAL

DICTIONARY

THIRD EDITION,

WITH

Twenty-five New Plates.

Price £1 4 0 Plain.

— £1 15 0 Coloured.

1805.

Digitized by the Internet Archive
in 2016

https://archive.org/details/b22041710

A

BOTANICAL DICTIONARY:

OR,

ELEMENTS

OF

SYSTEMATIC AND PHILOSOPHICAL

BOTANY.

BY COLIN MILNE, LL.D.

AUTHOR OF INSTITUTES OF BOTANY, AND HABITATIONS OF ENGLISH PLANTS.

THE THIRD EDITION,

REVISED, CORRECTED, AND VERY CONSIDERABLY ENLARGED.

Illustrated by Twenty-five New Plates.

——————————————Πλεῖστα φέρει ζείδωρος ἄρουρα
Φάρμακα, πολλὰ μὲν ἐσθλὰ μεμιγμένα, πολλὰ δὲ λυγρά.

HOM. ODYSS. Δ'.

Quid majora ſequar? Salices, humileſque geneſtæ,
Et tiliæ, pecori frondem, aut paſtoribus umbras
Sufficiunt, ſepemque ſatis, et pabula melli.
——————————— Juvat arva videre
Non raſtris, hominum non ulli obnoxia curæ.
Ipſæ Caucaſio steriles in vertice ſilvæ
Dant alios aliæ foetus: dant utile lignum
Navigiis pinos, domibus cedrumque cupreſſos.
Hinc radios trivere rotis, hinc tympana plauſtris
Agricolæ, et pandas ratibus poſuere carinas.

VIRG. GEORG. Lib. II.

LONDON:

PRINTED FOR H. D. SYMONDS, PATERNOSTER-ROW;
By Bye and Law, St. John's-Square, Clerkenwell.

1805.

14420

WELLCOME
HISTORICAL
MEDICAL
LIBRARY

TO HIS GRACE

HUGH PERCY,

DUKE AND EARL OF NORTHUMBERLAND,

EARL PERCY, AND BARON WARKWORTH,

LORD LIEUTENANT AND VICE-ADMIRAL OF NORTHUMBERLAND AND NEWCASTLE-UPON-TYNE, HIGH STEWARD OF LAUNCESTON, AND CONSTABLE OF LAUNCESTON-CASTLE, ONE OF THE COUNCIL OF STATE OF THE PRINCE OF WALES IN CORNWALL, AND KNIGHT OF THE MOST NOBLE ORDER OF THE GARTER;

THE FOLLOWING IMPROVED EDITION OF A WORK,

WHICH ORIGINALLY APPEARED UNDER THE DISTINGUISHED AUSPICES OF

HIS ILLUSTRIOUS FATHER, THE MÆCENAS OF HIS AGE,

ON WHOSE APPROBATION OF THIS HIS FIRST ATTEMPT TO ILLUSTRATE AND PROMOTE A SCIENCE, WHICH HIMSELF NOT ONLY PATRONIZED, BUT EMINENTLY ADORNED, THE AUTHOR WILL EVER REFLECT WITH PECULIAR SATISFACTION,

IS INSCRIBED,

WITH THAT PROFOUND RESPECT AND VENERATION, WHICH THE TRULY

DIGNIFIED CONDUCT

HIS GRACE HAS UNIFORMLY MAINTAINED,

BOTH IN PUBLIC AND DOMESTIC LIFE, MORE EVEN THAN

HIS ELEVATED RANK,

OR

THE SPLENDOR OF HIS ANCESTRY,

IS SO JUSTLY ENTITLED TO COMMAND,

BY HIS GRACE'S VERY FAITHFUL,

AND MOST DEVOTED

HUMBLE SERVANT,

COLIN MILNE.

PREFACE.

THIS corrected and greatly enlarged edition of his Botanical Dictionary, the Author cannot ſubmit to the public without previouſly embracing an opportunity which ſo naturally preſents itſelf, of expreſſing, in the ſtrongeſt terms, his ſincere acknowledgements for the very favourable reception which the work has obtained ſince its firſt publication; and in particular, for the mention ſo honourably made of it in the periodical, and various other writings of the Learned, both in this country and on the Continent.

Had circumſtances permitted, it was fully the Author's intention, among other prefatory matter, to have offered ſome remarks on his Deſcriptions of the Natural Orders of Linnæus—a part of his ſubject, on which he has beſtowed a more than ordinary ſhare of attention, as the Deſcriptions alluded to, he muſt conſider as peculiarly and excluſively his own *. But this he muſt at preſent decline;

* See the article FRAGMENTA METHODI NATURALIS.

partly

partly in conſideration of the ſize which the volume has already attained, but chiefly in juſtice to the Publiſher, who, having incurred a conſiderable expence in adorning it, has a right to expect that he may not be exposed to ſuffer by any unneceſſary delay in the publication.

To his ingenious and excellent friend, Dr. THORNTON, at whoſe earneſt and repeated requeſt this edition was undertaken, the Author ſtands indebted for many uſeful ſuggeſtions towards the improvement of the preſent work, and for ſeveral valuable communications during the progreſs of it. With the literary character of this gentleman the world is ſo well acquainted, that any endeavour of the Author to add to his well-earned fame, would be ſuperfluous. But though it be generally known that his eminence in his favourite ſcience can only be equalled by the generous ardour he manifeſts in its purſuit, and the diſintereſted public-ſpirited ſacrifices which for years he has been making for the advancement of its objects, it belongs to thoſe alone who enjoy the happineſs of his friendſhip, to remark the ſuperior qualities of his mind and heart—that noble independence which, in matters of ſcience, diſdains the fetters of authority, and dares to think for itſelf—that candour, ſo eſtimable, becauſe ſo rare, which, on even the ſhadow of merit,

is eager to beſtow its due portion of applauſe—that mild forbearance, which he never fails to exerciſe towards those who, envious of abilities which they despair to reach, have not the magnanimity to emulate his candour;—above all, that love of virtue (not the inſeparable concomitant of learning) which pervades every page of his writings, prompting him to render every talent and purſuit ſubſervient to the advancement of the eſſential intereſts of morality and religion. In praiſe of ſuch a man, (and the portrait is neither ideal, nor drawn by the flattering hand of partial friendſhip) it were ſcarce poſſible to exceed; nor of his fate with the moſt diſtant poſterity, requires it much prophetical ſagacity to pronounce,

"SEMPER HONOS, NOMENQUE SUUM, LAUDESQUE MANEBUNT."

ERRATA.

ERRATA.

The reader is requeſted to correct the following *inaccuracies*. In the article ACINI, for "*ſtrawberry*," read "*raſpberry*;"—At the end of the article BRACTEATÆ, for "*and* is exemplified, &c." read "*which* is exemplified;"—In the article CAPITATUS *flos*, at the beinning, for "*a fructification*, generally conſiſting of *many flowers*," read, "*a flower* generally conſiſting of *many fructifications*;"—In the article CORCULUM, line 5, for "*the former*," read, "*the latter*;"—and in STRUCTURA VEGETABILIS, page 3, line 23, after *liber*, for, "*from its fine and thin plates*, &c." read, "*the leaves of books, (libri) being originally formed from its fine, thin plates.*"


*** The Binder is deſired to place, immediately after the Preface, Ray's Method—Tournefort's ditto, and Linnæus's Analyſis.—The Plates, Index, and Alphabetical Liſt, conclude the work.

RAY'S METHOD.

This complex but beautiful Mode of Arrangement is founded chiefly on the Fruit, combined with the Habit or Port of Plants, and a Variety of other Circumſtances. Plants, according to this Method, are primarily divided into

	CLASSES.	EXAMPLES.
Such as bear no Buds, termed Herbs;		
Imperfect plants, — — — — — — — —	1 *Submarinae*,	Corallines, ſponge, fuci.
	2 *Fungi*,	Muſhrooms.
	3 *Muſci*,	Moſſes.
Perfect plants,	4 *Capillares*,	All the fern tribe.
riſing with two ſeed-leaves,		
without petals, — — — — — — — —	5 *Apetalae*,	Hop, hemp, nettle, dock, orach, amaranthus, alchemilla, plantain, knawel, mercury.
with petals,		
with a compound flower, — — — — — — — —	6 *Planipetalae*,	Lettuce, dandelion, hawk-weed, goat's-beard, nipple-wort, ſuccory.
	7 *Diſcoideae*,	After, golden-rod, groundſel, colt's-foot, cudweed, leopard's-bane.
	8 *Corymbiferae*,	Sun-flower, marigold, fever-few, daiſy, wormwood, tanſy, milfoil.
	9 *Capitatae*,	Thiſtle, artichoke, blue-bottle, burdock, ſaw-wort, ſcabious, teazel.
with a ſimple flower,		
having naked ſeeds,		
in number one, — — — — — —	10 *Monoſpermae*,	Valerian, thrift, agrimony, marvel of peru, fumatory.
in number two, — the flowers growing in umbels, — — —	11 *Umbelliferae*,	Lafer-wort, ſhepherd's-needle, hemlock, fanicle, angelica, maſter-wort.
in number two, — the leaves ſurrounding the ſtem in rays, — — —	12 *Stellatae*,	Madder, gooſe graſs, wood-roof.
in number four, — the leaves rough and hairy, — — —	13 *Aſperifoliae*,	Comfrey, borage, lang-wort, bugloſs, hound's-tongue, mouſe-ear.
in number four, — the flowers growing in whirls round the ſtem, — —	14 *Verticillatae*,	Roſemary, mint, marjoram, ſage, betony, germander.
in number many, — — — — — —	15 *Poliſpermae*,	Water-plantain, ranunculus, herb-bennet, adonis, anemone.
having the ſeeds covered,		
with a pulpy ſubſtance, — of the apple kind, — — —	16 *Pomiferae*,	Cucumber, melon, pumpkin, gourd, paſſion-flower.
with a pulpy ſubſtance, — of the berry kind, — — —	17 *Bacciferae*,	Herb-chriſtopher, butcher's-broom, deadly night-ſhade, winter-cherry.
with a membranaceous ſubſtance, — that is manifold, — — —	18 *Multiſiliquae*,	Houſe-leek, pæony, hellebore, monk's-hood, columbine, fraxinella.
with a membranaceous ſubſtance, — that is ſingle, — with one petal, — —	19 *Monopetalae*,	Hen-bane, ſpeedwell, looſe-ſtrife, mullein, mallow, fox-glove.
with a membranaceous ſubſtance, — that is ſingle, — with two and three petals, —	20 *Di-Tripetalae*,	Enchanter's night-ſhade, marſh-aloe.
with a membranaceous ſubſtance, — that is ſingle, — with four regular petals, —	21 *Siliquoſae*,	Stock, ſatin-flower, ſcurvy-graſs, poppy, rue, epilobium.
with a membranaceous ſubſtance, — that is ſingle, — with four irregular petals, —	22 *Leguminoſae*,	Pea, vetch, lentils, broom, trefoil.
with a membranaceous ſubſtance, — that is ſingle, — with five petals, — —	23 *Pentapetalae*,	Pink, lychnis, chickweed, violet.
with a membranaceous ſubſtance, — that is ſingle, — with graſſy leaves and one or more petals	24 *Floriferae*,	Hyacinth, narciſſus, tulip, flower-of-a-day, ſow-bread, orchis, ginger.
riſing with one ſeed-leaf, and wanting the petals, — — — — —	25 *Stamineae*,	Ruſh, acorus, and the graſſes.
Herbs of uncertain family, — — — — — —	26 *Anomalae*,	Water-lily, barren-wort, meadow-rue, pine-apple, pepper, vanelloe.
ſuch as bear Buds, termed Trees;		
riſing with one ſeed-leaf, — — — — — —	27 *Arundinaceae*,	The palms.
riſing with two ſeed-leaves, — The flower placed apart from the fruit, — — —	28 *Apetalae*,	Fir, pine, cedar, cypreſs, juniper, walnut, oak, cheſnut, poplar.
riſing with two ſeed-leaves, — The flower joined to the fruit, — which is crowned with the calyx,	29 *Fructu umbilicato*,	Apple, quince, medlar, roſe, honey-ſuckle, hawthorn, elder.
riſing with two ſeed-leaves, — The flower joined to the fruit, — not crowned with the calyx, —	30 *Fructu non umbilicato*,	Plum, almond, cherry, peach, orange, lemon, calabaſh, arbutus, olive, acajou.
riſing with two ſeed-leaves, — The flower joined to the fruit, — of a dry ſkinny ſubſtance,	31 *Fructu ſicco*,	Maple, aſh, lime, tamariſk, elm, lilac, ſumach, tea.
riſing with two ſeed-leaves, — The flower joined to the fruit, — of the pod kind, — —	32 *Fructu ſiliquoſo*,	St. John's bread, oleander, caſſia, tamarind, acacia, broom, laburnum, bladder-ſenna.
Trees of difficult arrangement. — —	33 *Anomalae*,	Fig.

Obſervation.—This method is much to be eſteemed for its approximation to nature. The 1ſt, 3d, 4th, 6th, 11th, 12th, 13th, 14th, 16th, 21ſt, 22d, and 25th claſſes are true natural families.




TOURNEFORT'S METHOD.

This celebrated Method is founded upon the Figure of the Petals, in which Reſpect it is preferable to that of Rivinus and Knaut; Figure being more conſtant than Regularity or Number. According to it, Plants are primarily divided into

	CLASSES.	EXAMPLES.
Herbs and under-ſhrubs;		
Bearing flowers,		
With petals,		
The flowers ſimple,		
Having one petal,		
that is bell-ſhaped,	1 *Campaniformes*, -	Deadly night-ſhade, gentian, convolvulus, navel-wort, mallow, cucumber, bell-flower, ladies bed-ſtraw.
funnel-ſhaped, —	2 *Infundibuliformes*,	Tobacco, thorn-apple, primroſe, valerian, borage, looſeſtrife, mullein, night-ſhade.
of various figures,	3 *Anomali*, - -	Arum, Birth-wort, toad-flax, bear's-breech, ſpurge.
lip-ſhaped, —	4 *Labiati*, - - -	Sage, mint, balm, germander.
Having more petals than one,		
that are croſs-ſhaped, — —	5 *Cruciformes*, -	Scurvy-graſs, ſtock, alyſſum.
diſpoſed circularly, — —	6 *Roſacei*, - - -	Amaranthus, poppy, paſſion-flower, rue, ſaxifrage.
the flowers growing in umbels, —	7 *Umbellati*, - -	Hemlock, chervil, angelica.
emerging from the tube of the calyx,	8 *Caryophyllaei*, -	Pink, lychnis, thrift.
diſpoſed like thoſe of the lily, —	9 *Liliacei*, - - -	Aſphodel, hyacinth, iris, tulip, lily, crown-imperial.
ſhaped like a butterfly, — —	10 *Papilionacei*, -	Vetch, lupine, trefoil, pea.
of various figures, — —	11 *Anomali*, - -	Balſam, violet, fumatory, dyer's-weed, monk's-hood, fraxinella, orchis, columbine.
the flowers compound,		
with hollow florets, — — —	12 *Floſculoſi*, - -	Thiſtle, burdock, tanſy, cud-weed, ſcabious, teazel, globe-amaranth.
with florets flat above and hollow below,	13 *Semifloſculoſi*, -	Dandelion, goat's-beard, hawk-weed.
with hollow and flat florets, — —	14 *Radiati*, - -	After, golden-rod, groundſel, feverfew, marigold, ſun-flower.
without petals, — — — — —	15 *Apetali*, - - -	Aſarabacca, dock, amaranthus, hemp, nettle, and the graſſes.
not bearing flowers,		
with ſeeds, — — — —	16 *Spermatophorae*, -	The ferns.
without ſeeds, — — —	17 *Aſpermae*, - -	Moſſes, muſhrooms, ſea-weed.
Trees and ſhrubs;		
without petals, the flowers not growing in catkins, — —	18 *Apetali*, - - -	Aſh, box, fig.
without petals, the flowers growing in catkins, — —	19 *Amentacei*, - -	Walnut, oak, beech, fir, cypreſs.
with one petal, — — — — — —	20 *Monopetali*, - -	Buckthorn, privet, jeſſamy, olive, lilac, elm, acacia, elder, honey-ſuckle.
with more petals than one,		
diſpoſed circularly like thoſe of the roſe,	21 *Roſacei*, - - -	Sumach, lime, tamariſk, horſe-cheſnut, nettle-tree, ivy, vine, maple, tea, peach, cherry, palms, apple, roſe, myrtle, medlar.
ſhaped like a butterfly, — —	22 *Papilionacei*, -	Broom, St. John's-bread, coral-tree, falſe acacia, coronilla.

Obſervation.—The 4th, 5th, 7th, 9th, 10th, 13th, 14th, and 17th claſſes of this method are true natural families.



ANALYSIS of the celebrated SEXUAL SYSTEM of LINNÆUS.

According to this ingenious Method all Vegetables are furniſhed with FLOWERS, *which are either*

Viſible,
- Stamina and pointal in the ſame flower,
  - Male and female organs diſtinct,
    - Stamina not united either above or below,
      - Generally of equal length,

IN NUMBER.	CLASSES.	EXAMPLES.
One, — — —	1 *Monandria*, - -	Ginger, Indian arrow-root, turmerick, blite.
Two, — — —	2 *Diandria*, - -	Jeſſamine, privet, olive, lilac, ſpeedwell.
Three, — — —	3 *Triandria*, - -	Valerian, tamarind, iris, and the graſſes.
Four, — — —	4 *Tetrandria*, - -	Scabious, teazel, madder, holly, woodroof.
Five, — — —	5 *Pentandria*, - -	Bell-flower, bind-weed, mullein, thorn-apple, periwinkle, and the rough-leaved and umbelliferous plants.
Six, — — —	6 *Hexandria*, - -	Snow-drop, narciſſus, tulip, aloe, hyacinth.
Seven, — — —	7 *Heptandria*, - -	Horſe-cheſnut.
Eight, — — —	8 *Octandria*, - -	Indian-creſs, heath, French-willow.
Nine, — — —	9 *Enneandria*, - -	Bay, rhubarb.
Ten, — — —	10 *Decandria*, - -	Fraxinella, rue, rhododendron, lychnis.
Twelve, — — —	11 *Dodecandria*, -	Purſlane, houſe-leek, aſarabacca.
Many, frequently twenty, attached to the calyx,	12 *Icoſandria*, - -	Peach, medlar, apple, roſe, cinquefoil.
Many, generally upwards of twenty, not attached to the calyx,	13 *Polyandria*, - -	Herb-chriſtopher, poppy, lark-ſpur, columbine.

      - Of unequal length,

Two long, and two ſhort, —	14 *Didynamia*, - -	Savory, hyſſop, ground-ivy, balm, toad-flax, fox-glove, agnus caſtus, bear's-breech.
Four long, and two ſhort, —	15 *Tetradynamia*, -	Scurvy-graſs, candy-tuft, water-creſs, ſtock, woad.


    - Stamina united

by the filaments, into one body,	16 *Monadelphia*, -	Geranium and the mallow tribe.
into two bodies,	17 *Diadelphia*, - -	Fumatory, milk-wort, and the pea-bloom flowers.
into many bodies,	18 *Polyadelphia*, -	Orange, chocolate-nut, St. John's-wort.
by the anthers or tops, into a cylinder,	19 *Syngeneſia*, - -	Violet, balſam, cardinal-flower, and the flowers termed compound, as dandelion, ſuccory, thiſtle, cud-weed, tanſey, blue-bottle.

  - Male organs (ſtamina) attached to, and ſtanding upon the female (piſtillum). — — 20 *Gynandria*, - - Orchis, ladies-ſlipper, arum, vanelloe, birth-wort, paſſion-flower.
- Stamina and pointal in different flowers,

on the ſame plant, — —	21 *Monoecia*, - -	Mulberry, nettle, oak, cypreſs, fir, cucumber.
on different plants, — —	22 *Dioecia*, - - -	Willow, hop, ſpinach, poplar, mercury, juniper.
on the ſame, or different plants along with hermaphrodite flowers,	23 *Polygamia*, - -	White hellebore, pellitory, orach, fig.

Or lie concealed from view, and cannot be diſtinctly deſcribed. — — 24 *Cryptogamia*, - Ferns, moſſes, muſhrooms, flags.



A

BOTANICAL DICTIONARY.

A C U

A in compoſition ſignifies *without*, as *herbæ acalyces*, herbs or plants that want the calyx: *herbæ acaules*, plants that want the *caulis* or ſtem.

ACALYCES *Plantæ*, (from *α* priv. and *calyx*), having no calyx, or flower-cup. *Vide* CALYX.

This is the name of the 15th claſs in Wachendorffius's Natural Method, and conſiſts of ſuch plants as have no flower-cup.

ACANACEÆ, the name of the 19th claſs in Cæſalpinus's Syſtematic Method, conſiſting entirely of compound flowers. It anſwers to part of Linnæus's claſs *Syngeneſia*, and is exemplified in the dandelion, (*leontodon*). *Vide* SYNGENESIA.

ACAULES *Herbæ*, (from *a* priv. and *caulis*); herbs that want the *caulis* or ſtem. The 20th claſs, or family, in Magnolius's Method. *Vide* CAULIS.

ACINI, the ſmall berries which compoſe the fruit of a mulberry, bramble, ſtrawberry, *&c.*

ACOTYLEDONES, (from *a* priv. and *cotyledon*); plants ſo called whoſe ſeeds are not furniſhed with *cotyledons*, or lobes, and conſequently, put forth no ſeminal leaves. All the moſſes are of this kind. *Vide* COTYLEDONES.

ACULEUS, (from *acus*, a needle, of which Priſcian conſiders it, as well as *acicula*, to be a diminutive, all of them, probably, derived from the Greek ἀκη, or ἀκις, *cuſpis*, a point); a prickle, or ſharp point. A ſpecies of armature, or offenſive weapon, with which the ſtems and branches of

ſeveral plants are furniſhed. *Vide* ARMA. It is particularly remarkable in roſe, raſpberry, currant, and berberry buſhes.

The prickle differs from the thorn (*ſpina*), another ſpecies of armature, or defence againſt animals, in being only a prolongation of the *cortex* or outer bark of the plant, and in no ſort connected with, or protruded from the wood. This is apparent from the facility with which ſuch prickles are detached from the ſtem along with the bark: whilſt the other, and more rigid ſpecies of weapon, being an expanſion or proceſs of the lignous body, cannot be detached without rending and tearing the ſubſtance of the wood. *Vide* SPINA.

Duhamel compares prickles on the ſurface of plants, to the nails and claws of animals.

Prickles are either,

Recti, ſtraight; as in *ſolanum indicum*;

Incurvi, bent inwards; as in *mimoſa cineraria*;

Recurvi, bent outwards.

Tomentoſi, downy, or covered with *tomentum*, a ſilver-white woolly appearance, as in the *ſolanum ſanctum*. *Vide* TOMENTUM.

Aceroſi, chaffy; *ſolanum tomentoſum*.

Geminati, growing in pairs; as in *euphorbia canarienſis*, and *euphorbia officinarum*.

ADVERSIFOLIÆ *Plantæ*, (from *adverſus*, oppoſite; and *folium*, a leaf); plants whoſe leaves ſtand oppoſite to each other, on the ſame ſtem or branch. The name of the 5th claſs in Sauvage's *Methodus Foliorum*, exemplified in valerian, teaſel, honey-ſuckle, and the labiated, or lipped flowers. *Vide* LABIATUS *Flos*.

ÆSTIVALES *Plantæ*, (from *æſtas*, ſummer); plants which flower in ſummer. The ſecond diviſion or claſs of Du Pas's Method or arrangement from the four ſeaſons of the year, conſiſting of herbs which flower in ſummer.

AFORA, from *a* priv. and *fores*, a door); having no doors or valves. The name of a claſs in Camellus's Method, conſiſting of plants whoſe pericarpium or ſeed-veſſel

veſſel is not furniſhed with the incloſure or external covering called a valvule. *Vide* VALVULA.

AGGREGATUS *Flos*, (from *aggregare*, to aſſemble, or collect); properly ſignifies a flower conſiſting of a number of ſmaller flowers, or fructifications, collected into a head by means of ſome part common to them all. In this view, aggregate flowers ſtand oppoſed to ſimple flowers, which have a ſingle fructification, compleat in its parts, none of which are common to many flowers.

From the deſcription of aggregate flowers, juſt given, it is evident that each of the ſmaller flowers will not conſtitute a complete fructification of itſelf; as one or two of the eſſential parts of fructification are only common to the whole bundle or heap. It happens, however, ſometimes, that the partial flower will be furniſhed with a part analogous to the common part in the aggregate. Thus in compound flowers, (the *Syngeneſia* of Linnæus), the florets or partial flowers are generally furniſhed with a proper calyx or flower-cup, though the calyx is one of the common parts in ſuch compound flowers. The ſame thing occurs in ſeveral other aggregate flowers, which are not compound. Thus thrift, or ſea-pink, *ſtatice*; ſcabious, *ſcabioſa*; teaſel, *dipſacus*; blue-daiſy, *globularia*; button-wood, *cephalanthus*; hartwort of Crete, *tordylium*; hog's-fennel, *peucedanum*; laſerwort, *laſerpitium*; lovage, *liguſticum*; piſtacia-nut, *piſtacia*; &c. are furniſhed with a common and proper calyx. On the other hand, Leucadendron, ſilver tree, *protea*; carrot, *daucus*; cowparſnep, *heracleum*; carvy, *carum*; dill, *anethum*; parſley, *apium*; &c. though furniſhed with a common calyx, under different appellations, have ſcarce any proper flower-cups for the different florets, of which the aggregate is compoſed.

The common part in aggregate flowers, is either the receptacle, or the calyx. *Vide* RECEPTACULUM, and CALYX.

From the different ſtructure, diſpoſition, and other circumſtances of theſe common parts, ariſes a ſevenfold diviſion of aggregate flowers: the *aggregate*, properly ſo called; the

compound, the *umbellate*, the *cymoſe*, the *amentaceous*, the *glumoſe*, and the *ſpadiceous* flowers. *Vide* COMPOSITUS *Flos*, UMBELLA, AMENTACEUS *Flos*, *&c.*

Theſe all agree in being compoſed of florets, called by Linnæus, *floſculi*, which are connected by means of ſome part or parts common to the whole; but differ in the figure, proportion, and diſpoſition of theſe parts.

The AGGREGATE FLOWER properly ſo called, has its florets erected on peduncles or foot-ſtalks: the receptacle, which is common, being dilated, or extended in breadth for that purpoſe. The calyx is likewiſe common, and univerſally that ſpecies called perianthium. In ſome flowers, each floret has a proper calyx, which is likewiſe a perianthium, and generally monophyllous, or of one piece. In others, there is either no proper calyx at all, as in *leucadendron*; or it is ſo very ſmall, as ſcarcely to be diſcerned: as in teaſel.

Striking Structures.

Scabious, *ſcabioſa*; has a double proper calyx.

The genus *mitchella* has two diſtinct flower-cups, and two florets placed upon a ſingle germen, or fruit-bud.

The genus *morina* has likewiſe a double perianthium, each perfectly diſtinct, the one of the flower, and the other of the fruit.

Valerian, button-wood, and American hog-weed, *boerhavia*, have ſcarce any common calyx.

In the genus *brunia*, the proper calyx or perianthium is pentaphyllous, or conſiſts of five diſtinct leaves.

Theſe are the moſt remarkable exceptions to the general deſcription of aggregate flowers, properly ſo called.

AGGREGATÆ, the ſeventh claſs in Royen's Natural Method; and forty-eighth order in Linnæus's *Fragmenta Methodi Naturalis*, conſiſting of plants whoſe flowers anſwer to the deſcription given above.

It may not be improper here, to obſerve, that theſe Fragments of a Natural Method, have undergone ſeveral alterations ſince their firſt publication in the *Philoſophia Botanica*. The number of orders, then ſixty-eight, is now reduced to fifty-

fifty-eight; and beſides, that the names and places of theſe orders have undergone a total revolution; ſeveral genera, that formerly were ranked under one title, are now diſperſed among a number of different titles or orders. To avoid confuſion, therefore, let the reader keep in mind, that the Fragments I always refer to, are thoſe publiſhed at the end of the ſixth edition of the *Genera Plantarum*, printed Holmiæ, 1764, under the head *Ordines Naturales*.

To illuſtrate the above obſervation, I would remark, that theſe genera, *lonicera*, honey-ſuckle; *mitchella*, *morinda*, and *loranthus*, are removed into the order *aggregatæ*, which we are now conſidering, from an order entitled *cymoſæ*, which is not to be found in the improved editions of the Fragments. In like manner, the genera *ſelago*, *conocarpus*, button-tree; and *viſcum*, miſletoe; which were formerly thrown into the laſt order, as vague, and of difficult arrangement, now make a part of the ſame order of aggregate flowers.

ALA, a wing; ſo the word literally ſignifies. Among former botaniſts, it was uſed to expreſs the angle formed by the ſtem with the branch or leaf.

With Linnæus, and others, *ala* is the name of a membrane, affixed to ſome ſpecies of ſeeds, and which, by its flying, helps to diſperſe them. *Vide* SEMEN.

Examples of the winged ſeed will be found in the fir, birch, and tulip-trees, *liriodendrum*; in the aggregate flower button-wood, *conocarpus*; and the umbelliferous flowers, *artedia*, and dill, *anethum*.

Meadow-rue, *thalictrum*; trumpet-flower, *bignonia*; red jaſmine, *plumeria*; tickſeed, *coriſpermum*; and queen's-july-flower, *heſperis*; are alſo furniſhed with ſeed-membranes of this kind.

ALÆ, the two lateral, or ſide petals of a papilionaceous, or butterfly ſhaped flower. *Vide* COROLLA, and DIADELPHIA.

ALBURNUM, (from *albus*, white); the ſoft white ſubſtance, which, in trees, is found between the *liber* or inner bark and the wood, and, in progreſs of time, acquiring ſolidity, becomes itſelf the wood. From its colour, and com-

parative ſoftneſs, it has been ſtiled by ſome writers, the fat of trees, *adeps arborum*.

The *alburnum* is found in largeſt quantities in trees that are vigorous; though in ſuch as languiſh, or are ſickly, there is a greater number of beds. In an oak ſix inches in diameter, this ſubſtance is nearly equal in bulk to the wood. In a trunk of one foot diameter, it is as one to three and a half; of two and a half feet diameter, as one to four and a half, *&c.* but theſe proportions vary according to the health and conſtitution of the trees.

The *alburnum* is frequently gnawed in pieces by inſects, which lodge in the ſubſtance, and are nouriſhed from it.

ALGÆ, flags; one of the ſeven families, or natural tribes, into which the whole vegetable kingdom is divided by Linnæus, in his *Philoſophia Botanica*. They are defined to be plants, whoſe root, leaf and ſtem, are all in one. Under this deſcription are comprehended all the ſea-weeds, and ſome other aquatic plants.

In the ſexual ſyſtem, they conſtitute the third order of the twenty-fourth claſs *Cryptogamia*; in Tournefort's, the ſecond genus of the ſecond ſection, (*Marinæ, aut fluviatiles,*) of the ſeventeenth claſs, *aſpermæ vulgo habitæ*; and the fifty-ſeventh order in Linnæus's Fragments of a Natural Method.

The diſcoveries made in this part of the vegetable kingdom, are uncertain, and imperfect; and the attempts, in particular, to arrange flags by the parts of the fructification, have not been attended with great ſucceſs. Dillenius has arranged this order of plants, from their general habit and ſtructure; Micheli from the parts of fructification.—— Each has conſiderable merit.

ALOPECUROIDEA, (from *alopecurus*, fox-tail graſs); the name of a claſs, in Ray's, Montis, and Scheuchzerus's Diviſion of the Graſſes.

ALTERNÆ *Plantæ*, the name of the third and fourth claſſes of Sauvage's *Methodus Foliorum*, conſiſting of plants whoſe leaves are alternate: oppoſed to the claſs *Adverſifoliæ* of the ſame author. *Vide* ADVERSIFOLIÆ *Plantæ*.

AMARÆ *Herbæ*, bitter herbs; the name of a diviſion or claſs,

claſs, in Hernandes, and other botaniſts, who have arranged plants according to their ſenſible qualities.

AMENTACEUS *Flos*, (from *amentum*); having that ſpecies of calyx, called *amentum*. *Vide Infra*.

All amentaceous flowers are aggregate. *Vide* AGGREGATUS *Flos*.

An amentaceous aggregate flower has a filiform, or thread-ſhaped receptacle, along which are diſpoſed amentaceous *ſquamæ*, that is, ſcales forming an amentum, thong, or catkin.

The willow-tree, *ſalix*; birch, *betula*; beech, *fagus*; poplar, *populus*; hazel, *corylus*; horn-beam, *carpinus*; fir, *pinus*; walnut, *juglans*; oak, *quercus*; fig-tree, *ficus*; cypreſs, *cupreſſus*; and other trees, are amentaceous.

It does not appear abſolutely neceſſary for a flower of this kind to have an amentum for its calyx. In fact, the leſſer burdock; the genus *ambroſia*; baſtard-feverfew, *parthenium*; Jeſuit's-bark-tree, *iva*; pellitory, *parietaria*; the nettle, *urtica*; &c. which are reckoned by Linnæus among the amentaceous flowers, have either a perianthium or involucrum for their calyx. *Vide* PERIANTHIUM and INVOLUCRUM.

The greateſt part of the amentaceous flowers, belong to one of the claſſes *Monœcia*, or *Diœcia* of Linnæus. *Vide* MONŒCIA, DIŒCIA.

Beſides the common amentum, ſeveral of the amentaceous flowers have a proper calyx or perianthium; as *cynomorium*; burr-reed, *ſparganium*; ſand-box-tree, *hura*; piſtacia nut, *&c.* and many others.

AMENTACEÆ, the thirty-ſecond claſs of Boerhaave's Method, and nineteenth of Tournefort's, comprehending trees only. In Linnæus's *Methodus Calycina*, it is the third claſs; in his Fragments, the fiftieth order; and in Royen's Natural Method, the fourth claſs.

It is not eaſy to give an exact deſcription of the idea Linnæus ſeems to have affixed to amentaceous plants; for, in the *Philoſophia Botanica*, (as we have obſerved in the preceding article,) he calls ſeveral flowers amentaceous, which have not an *amentum* for their calyx; and, in his fragments

of a Natural Method, the order *amentaceæ* does not contain the cypreſs, juniper, arbor vitæ, *thujæ*; ſand-box-tree, and other conebearing-trees, whoſe calyx is an amentum.

In Boerhaave and Tournefort's Method, as we have remarked above, the term *amentaceous* reſpects trees only. In the latter, the claſs *amentacei* conſtitutes the ſecond diviſion of apetalous trees; that is, of trees wanting the petals, or coloured leaves; and conſiſts of flowers, attached in a bundle, or heap, round a common thread, or ſlender receptacle; which thread is deſcribed under the name of

AMENTUM, catkin; (derived by Feſtus from the Greek ἀμμα, *vinculum ſive nexus*, a bond or thong,) a ſpecies of calyx, conſiſting of a great number of chaffy ſcales, diſperſed along a ſlender thread, or receptacle, which, from its reſemblance to a cat's tail, has obtained, in Engliſh, the name of catkin; in French, *chaton*; and by many botaniſts, the ſimilar appellation of *catulus*. The term *amentum* is uſed by Tournefort and Linnæus, and is ſynonimous to *julus*, *nucamentum*, and *catulus*, in other writers. *Vide* CALYX.

An amentum, as defined by Linnæus, is a compoſition of a calyx, and a common receptacle. The *ſquamæ*, or ſcales, that form the amentum, mix alternately with the flowers, and reſemble the chaff in an ear of corn.

This ſpecies of calyx occurs frequently in the claſſes *Monœcia*, and *Diœcia* of Linnæus; that is, it is found to ſupport male and female flowers, that grow either on the ſame root, as in the former claſs, or on two diſtinct roots, as in the latter.

In the horn-beam, *carpinus*; an amentum ſupports both male and female flowers, on the ſame root.

In the willow, *ſalix*; and the poplar, *populus*; an amentum ſupports male and female flowers on diſtinct roots.

Male and female flowers, when produced from the ſame root, are ſometimes mixed together, ſometimes placed at a conſiderable diſtance on the ſame plant. In the latter caſe, it is not uncommon to find an amentum ſupporting the flowers of one ſex, and a perianthium thoſe of the other. This

is

is exactly what happens in the hazel-nut, *corylus*; where the male and female flowers are removed from each other on the ſame plant. The male flowers form an amentum; the female flowers are incloſed by a perianthium. In like manner, the walnut-tree, *juglans*; and the ſand-box tree, *hura*; have on the ſame root their male flowers, with an amentum; their female flowers with a perianthium.

Arbor vitæ, *thuja*; and the cypreſs tree, have, upon the ſame root, the male flowers formed into an amentum, and the female flowers into a cone. *Vide* CONIFERÆ.

In plants that have male and female flowers on diſtinct roots, *Diœcia*; the piſtacia-nut has its male flowers only formed into an amentum; a perianthium ſurrounding the female. The ſame thing happens in the juniper-tree, and ſhrubby-horſe-tail, *ephedra*.

Flowers that are ſupported by an amentum, whether male or female, or both, generally want the petals, or coloured leaves. *Vide* COROLLA. This obſervation is exemplified in the oak, beech, hazel, cypreſs, piſtacia-nut, and ſeveral others.

The following are exceptions to the general rule.

In the genus *carex*, which has male and female flowers produced on the ſame root, the female flowers have a *nectarium*, but no petals: the male flowers have neither petals nor *nectarium*. *Vide* NECTARIUM.

The contrary of this takes place in the willow, *ſalix*; where the male and female flowers are produced on diſtinct roots. The male flowers have a *nectarium*, and want petals; the female want both.

In the poplar-tree, *populus*, both male and female flowers want petals, and are furniſhed with a *nectarium*.

The male flowers of the birch-tree have a proper corolla, conſiſting of one petal, deeply divided into four parts. The female flowers have no corolla that is perceptible.

Both male and female flowers of the walnut-tree, *juglans*, are furniſhed with a corolla; but this corolla is cut into ſix parts in flowers of the former ſex; into four in thoſe of the latter.

Horn-

Horn-beam, *carpinus*; whoſe male flowers want the corolla, has its female flowers furniſhed with one in the form of a calyx, conſiſting of one piece, divided into ſix parts.

The male flowers of the juniper-tree have no corolla. The female have three rigid petals, which continue till the fruit is arrived at maturity.

ANDROGYNA *Planta*, (from ἀνηρ, a man, and γυνή, a woman); a plant is ſaid to be androgynous, which produces both male and female flowers from the ſame root; as the walnut, birch, hornbeam, nettle, oak, cheſnut, fir, box, mulberry, hazel, cypreſs, cat's tail, *typha*; plane tree, and many others.

N. B. The nettle and mulberry, produce male and female flowers, either on the ſame, or diſtinct plants. *Vide* MASCULUS *Flos*, and FEMINEUS *Flos*.

Androgynous plants conſtitute the claſs *Monœcia* in Linnæus; *vide* MONŒCIA; and have frequently an amentum for their calyx. *Vide* AMENTUM.

ANGIOSPERMÆ *Herbæ*, (from ἀγγεῖον, a veſſel, and σπερμα, a ſeed); herbs, whoſe ſeeds are incloſed in a covering, or veſſel; in oppoſition to *gymnoſpermæ*, where the ſeeds are placed naked in the bottom of the flower-cup, without any other external covering whatever. In this view, Hermannus divides all ſuch herbs as are furniſhed with petals, into *gymnoſpermous* and *angioſpermous*.

The firſt ſeven claſſes exhauſt the diviſion ariſing from the number, &c. of naked ſeeds: from the eighth claſs to the eighteenth incluſive, the herbs are *angioſpermous*, or furniſhed with a ſeed veſſel. The different ſtructure of ſuch ſeed-veſſels, their number, and other circumſtances, ſuggeſt very properly the diviſion into claſſes. Thus the ſeed-veſſel in ſome plants is dry, and hard, and denominated a capſule; in others, it is a pod, as in the pea, bean, cabbage; in ſome a berry; in ſome, a fleſhy, or pulpy ſubſtance, containing a capſule; as the apple, pear, &c. in others, a fleſhy or pulpy ſubſtance, containing a ſtone; as the cherry, plumb, peach. Again, ſome plants have only one capſule; others have two, three, or more. It is evident

evident what beautiful diviſions muſt naturally ariſe from a view of the whole vegetable kingdom in this way. In fact, the greateſt number of Hermannus's claſſes are true natural aſſemblages; whilſt the ſo much boaſted ſyſtem of Linnæus, ſeparates things that ought never to be disjoined, and brings together ſuch as agree in nothing but the ſingle circumſtance that is the foundation of his method.

ANGIOSPERMIA, the name of the ſecond order in the claſs *Didynamia* of Linnæus. *Vide* DIDYNAMIA.

Hermannus, we have ſeen, uſed this term in its moſt extenſive ſenſe. Linnæus, the profeſſed reformer of botanical language, has reſtricted it to a few genera of plants, in a claſs, whoſe characteriſtic it is to have four ſtamina, two of which are long, and two ſhort. *Vide* STAMINA.

For the particular claſſical characters of *Didynamia*, ſee the term itſelf.

With reſpect to this order, *Angioſpermia*, the only eſſential character is, that the ſeeds are placed in a *pericarpium*, or veſſel; a character which is conſtant, and diſtinguiſhes this order from the other, *Gymnoſpermia*, under every form.

The genus *ſelago*, indeed, has no proper *pericarpium*; but its ſingle ſeed, inſtead of being lodged in the bottom of the calyx, as in the order *Gymnoſpermia*, is involved, or infolded by the corolla; the tube, or lower part of which is ſmall, and narrowed for that purpoſe.

The ſtigma, in this order, is generally obtuſe. *Vide* STIGMA.

Exceptions.—Fox-glove, *digitalis*; american-viburnum, *lantana*; bear's-breech, *acanthus*; *torenia*, *ſelago*, and *ovieda*, have an acute ſtigma.

The corolla is univerſally monopetalous, both in this and the other order, except in the genus *melianthus*, honey-flower; which has four petals, and a nectarium of one leaf.

The corolla too, is generally ringent, or gapes.

In figwort, *ſcrophularia*; fox-glove, *digitalis*; *ſelago*, and ſome other genera which belong to this order, the corolla ſpreads at the top.

Many plants of this order, have a double ſtigma. Take

the

the following examples: broom-rape, *orabanche*; oily purging-grain, *ſeſamum*; chaſte-tree, *vitex*; *mimulus*, *&c.*

From the reſemblance which the corolla of the plants of this order bears to a maſque, Tournefort has diſtinguiſhed them by the name of *perſonati*, that is maſqued flowers; which conſtitute the third claſs in his ſyſtem. *Vide* PERSONATUS *flos*.

The order *Angioſpermia* is ſynonimous to *Perſonatæ*, the fortieth order of Linnæus's Fragments, and makes part of the twelfth claſs *Ringentes*, in Royen's Natural Method. It is however to be obſerved, that Linnæus's Natural Order, *Perſonatæ*, contains ſeveral genera that do not belong to the ſecond order of the claſs *Didynamia*, in his Sexual Syſtem: as ſpeedwell, *veronica*; malabar-nut, *juſticia*; hedge-hyſſop, *gratiola*; vervain, *verbena*; which belong to the ſecond claſs, *Diandria*.

The term angioſpermous, is equivalent to Rivinus's *Semina tecta Pericarpio*, ſeeds covered with a pericarpium.

ANGULI *Folii*, the prominent parts of an horizontal leaf. *Vide* FOLIUM.

ANOMALÆ, (from α priv. and νομος, a law); irregular: the name of the twenty-ſixth and thirty-third claſſes in Ray's Method; the former, reſpecting herbs; the latter, trees. The eleventh claſs in Tournefort's Method, has alſo obtained this name, and conſiſts of plants whoſe corolla is compoſed of ſeveral irregular and diſſimilar pieces. The aconite, columbine, violet, fumatory, lark-ſpur, orchis, fraxinella, and ſeveral other plants, which have a *nectarium*, are reduced to this claſs of Tournefort. *Vide* NECTARIUM.

Anomalæ is likewiſe the name of the fourth, thirteenth, and twenty-ſecond claſſes of Pontedera's Syſtem, and the ninth of Linnæus's *Methodus Calycina*, or method derived from the form, ſtructure, and ſituation of the calyx.

ANTHEMIDES, the name of the eleventh claſs, in Cæſalpinus's Syſtem: containing a number of plants, which are furniſhed with ſeveral naked ſeeds within a common calyx, each petal or floret having a ſingle ſeed. It anſwers to part of the *ſyngeneſious*, or compound flowers of Linnæus;

næus; and is exemplified in the daiſy, *bellis*. Cæſalpinus's twelfth claſs, *Acanaceæ*, or *Cichoracæ*, contains the remaining part of the compounded flowers. *Vide* ACANACEÆ, *&c.*

ANTHERA, (from ἀνθὸς, a flower); the *Apex* of Ray, Tournefort, and Rivinus; the *Capſula Staminis* of Malpighi. *Vide Philoſophia Botanica*, page 134. The anther, ſummit, or top of the ſtamen, connected with the flower, and elevated by means of the filament, or thread. *Vide* STAMEN, and FILAMENTUM.

From the great utility of the fine coloured duſt contained within this part of the fructification, Linnæus has diſtinguiſhed it by the name of *anthera*, or, *the flower* by way of eminence.

The duſt, which he has denominated *Pollen*, is diſcharged, when ripe, for the impregnation of the plant, by the anther, which ſwells and burſts open for that purpoſe. *Vide* POLLEN.

This is a leading principle in the celebrated Sexual Syſtem of Linnæus.

Natural Structure.

The moſt natural ſtructure of the Anther, by which I always mean the moſt common, or that which is found to obtain in the greateſt number of plants, is, in point of ſituation, to be placed on the top of the filament; in point of number a ſingle anther to each filament.

Different ſtriking Structures.

We obſerved above, that the generality of plants have a ſingle anther to each filament; the following are exceptions to the general rule.

The herb mercury, *mercurialis*; and ranunculus, have two anthers to each filament; this is ſtyled by Linnæus, *anthera didyma*; and is frequently found in the claſs *Monœcia*.

Fumatory, *fumaria*; has three anthers to each filament.

Bryony, *bryonia*; has five anthers to three filaments; a

ſingle

ſingle anther upon one of the filaments, and the remaining four equally divided between the other two.

The chocolate-nut, *theobroma*; has five anthers to each filament.

The bean, pea, vetch, furze, trefoil, liquorice, and all the other butterfly-ſhaped flowers (the *Diadelphia* of Linnæus) have generally ten anthers to two filaments, or, more properly, to two ſets of united ſtamina.

The gourd, *cucurbita*, has one anther, common to three filaments.

Dandelion, feverfew, groundſel, and all the other compound flowers, (the *Syngeneſia* of Linnæus) have one anther, common to five filaments; or, to ſpeak more properly, five anthers united in a cylinder, are placed upon five diſtinct and ſeparate filaments.

The genera *chelone* and *martynia*, which belong to the claſs *Didynamia* of Linnæus, and conſequently have four ſtamina, two of which are long, and two ſhort, are very ſingular in their ſtructure. Within the uppermoſt, or talleſt pair of ſtamina, is placed the rudiment of a fifth filament, ſharp and pointed, without an anther.

Vervain, *verbena*, though of the claſs *Diandria*, has four filaments, two ſhorter than the reſt, and but two anthers. Some ſpecies of vervain have four anthers.

Hedge-hyſſop, *gratiola*, likewiſe of the claſs *Diandria*, has four filaments; two ſhorter than the reſt and barren; that is, without anthers. In ſome ſpecies, three anthers are wanting.

In a ſpecies of the trumpet-flower, *bignonia*, called by Linnæus *catalpa*, there are only two perfect ſtamina, or ſtamina with anthers. The three remaining rudiments of ſtamina, are ſhorter than the other two, and want the anthers.

Turmerick, *curcuma*; of Linnæus's firſt claſs, *Monandria*; has five ſtamina, four of which are imperfect, or, according to Linnæus, caſtrated; that is, want the anthers.

Some ſpecies of *geranium*, particularly that called by Linnæus *Cicutarium*, have the filaments furniſhed alternately

nately only with anthers; that is five anthers to ten filaments.

The anthers, we obſerved, are generally ſeated on the tops of the filaments.

The herb *paris*, and aſarabacca, *aſarum*, have the anthers fixed to the middle or ſides of the filaments.

Birthwort, *ariſtolochia*, has no filaments; the anthers, which are ſix in number, adhere to the ſtigma.

In cuckow-pint, *arum*, there are likewiſe no filaments, unleſs a number of nectaria, thick at the baſe, and terminated with thread-ſhaped tendrils. The anthers are numerous, four-cornered, placed between a double row of tendrils, and adhere to the receptacle, which, in this genus, is a *ſpadix*. *Vide* SPADIX.

The anthers are generally furniſhed with one or more cells, (*loculi*,) for containing the fine duſt, or vivifying powder mentioned above.

Mercury has one cell.

Hellebore, has two cells.

Orchis, three; and

Fritillaria, four.

The powder, when ripe, is diſcharged by the anther, which burſts, either on the ſide, as in moſt flowers; on the top, or apex, as in ſnow-drop; or through the whole length downwards, as in barren-wort, *epimedium*; and lion's leaf, *leontice*.

This burſting of the anthers, is ſtiled by Linnæus, *Dehiſcentia*; and where the opening is very minute, as in ſome ſpecies of anthers, it is termed APERTURA.

Terms expreſſing the mode of connection of the Anthers with the Filament.

ANTHERÆ ERECTÆ, erect, or ſtraight anthers; when they are faſtened by either extremity to the top of the filament; by the baſe, as in moſt plants; or by the top, as in meadow-ſaffron, *colchicum*.

ANTHERÆ INCUMBENTES, anthers which lie upon the filaments, or are faſtened to them by the ſides; oppoſed to *erectæ*.

This

This term is exemplified in the ſea-pink, *ſtatice*; the currant-tree, *ribes*; the pink, *dianthus*; ſea-daffodil, *pancratium*, &c.

ANTHERÆ VERSATILES, veering about like a vane, or weather-cock; when they are placed horizontally on the top of the filament, and conſequently ſo poiſed, as to turn on it like a vane, or the needle of a compaſs. Exemplified in cock's-comb, *celoſia*; *geranium*, *clutia*, *amaranthus*, and *eriocaulon*.

Note, the verſatile anther, is a ſpecies of the incumbent.

Indian flowering-reed, and the genus *coſtus*, have their anthers incumbent, or attached by the ſides, not to a filament, but to a nectarium, the upper-lip of which ſerves in the laſt genus, inſtead of a filament.

Terms of Figure and Reſemblance.

Anthera Linearis, ſmall, and ſlender, like a line; as *heliocarpus*, *ſtapelia*, &c.

Anthera Subulata, awl-ſhaped, or narrowing towards the top; as in the genus *roella*.

Anthera Haſtata, like a ſpear, or javelin, as in the genus *jacquinia*.

Anthera Oblonga, of an oblong figure, or much longer than broad; as in the capſicums, blood-flower, *hæmanthus*; and evolvulus.

Anthera Bicornis, with diviſions like two horns; as in winter-green, *pyrola*; whortle-berries, *vaccinium*.

Anthera Biſida, parted half-way down in two; as in heath, *erica*.

Anthera Biloba, parted more than half-way down in two, with wide and concave diviſions, as in eye-bright.

Anthera Sagittata, arrow-ſhaped; as in crocus, flax, *linum*; and the pine-apple, *bromelia*.

Anthera Cordata, heart-ſhaped; as in ſweet-weed, *capraria*; *tinus*, *bucida*.

Anthera Reniformis, kidney-ſhaped; as in *ginora*, and *tradeſcantia*.

The kidney-ſhaped anther, as well as the kidney-ſhaped ſeeds, is very common in the claſs *Monodelphia* of Linnæus.

Anthera

Anthera Ovata, egg-ſhaped; as in *limeum*.

Anthera Subovata, nearly approaching to the egg ſhape, as in ſparrow-wort, *paſſerina*.

Anthera Rotunda and *Globoſa*, though diſtinguiſhed by Linnæus, ſeem to be of equal import; round, or without any angles: *calamus*, a genus of the *Hexandria* of Linnæus, furniſhes an example of the former term; the herb mercury, *mercurialis*, of the latter.

Anthera Subrotunda, roundiſh, or a little round: as in louſe-wort; ceraſtium; american viburnum, *lantana*; orach, *atriplex*; american night-ſhade, *phytolacca*; baſtard milk-vetch, *phaca*.

Anthera Trigona, three-cornered; as in the roſe.

Anthera Tetragona, four-cornered; as in hemp, *cannabis*; the poplar, *populus*; and fraxinella, *dictamnus*.

Anthera Lunulata, and *Lunularis*, creſcent-ſhaped; as in the ſtrawberry, and marſh cinquefoil, *comarum*.

Theſe are the moſt remarkable terms for expreſſing the ſhape and figure of the anthers; to particularize them all, with the minute exactneſs of Linnæus, in his Genera Plantarum, would be endleſs, and, indeed, is altogether unneceſſary.

The following terms relating to the anther, cannot be diſpoſed under any particular head.

Anthera Acuta, ſharp, or terminating in an acute angle; as in comfrey, *ſymphytum*; and honey-wort, *cerinthe*.

Anthera Acuminata, tapering to a point; as in fox-glove, *digitalis*; and *thlaſpi*.

Anthera Obtuſa, blunt, oppoſed to the two former; as in herb bennet, *geum*; bear's breech, *acanthus*.

Anthera Diſtincta, diſtinct, or unconnected with each other; as in moſt plants.

Anthera diſtans, a term expreſſing the remoteneſs of the anthers from each other; as in the genera *zixiphora* and *morina*.

Anthera Connivens, approaching, or inclining towards each other, oppoſed to the two former; as in lung-wort, *pulmonaria*; borage, *borago*; night-ſhade, *ſolanum*; and ſeveral

genera of the claſs *Didynamia*, of Linnæus; as ſnap-dragon, *antirrhinum*; ground-ivy, *glecoma*; ſavory, *ſatureia*, &c.

Anthera Connata, *Cohærens*, united together; as in water milfoil, *utricularia*.

Anthera Incurva and *Incurvata*, bowed, or crooked; as in vervain, *verbena*; and ſilk cotton-tree, *bombax*.

Anthera Villoſa, covered with ſoft hairs, woolly; as in bear's-breech, *acanthus*.

Anthera Hirſuta, rough with hair, as in the dead nettle, *lamium*; and elephant's-head, *rhinanthus*.

Anthera Membranacea, hard like parchment; as in the genus *triplaris*.

Anthera Pellucida, ſhining, or tranſparent; as in moon-ſeed, *meniſpermum*. This tranſparency is obſerved in the barren anther of the female flower only; for this genus of plants belongs to the claſs *Diœcia* of Linnæus, and conſequently, has its male and female flowers upon diſtinct roots. *Vide* MASCULUS and FEMINEUS *Flos*.

Principles of the Sexual Method.

1. Every vegetable is furniſhed with flower and fruit. *Vide* FLOS, and FRUCTUS.

2. The flower and fruit together conſtitute the fructification. *Vide* FRUCTIFICATIO.

3. The fructification, therefore, is the eſſence of the vegetable.

4. The eſſence of the flower conſiſts in the anther and ſtigma. *Vide* STIGMA.

5. The anther, and ſtigma, therefore, conſtitute a flower, with or without the calyx and corolla. *Vide* CALYX and COROLLA.

6. The anther produces, and, when ripe, diſcharges a powder called *pollen*, which, falling upon the ſtigma, is abſorbed by a tough and viſcid humour, with which the ſurface of that part is covered; and paſſing through the ſtyle which correſponds to the vagina in animals, diſcharges what Linnæus calls the *aura ſeminalis*, for the impregnation of the germen, or ovarium below. *Vide* STYLUS and GERMEN.

7. To

7. To ſpeak, by analogy, therefore, the anthers may be conſidered as the teſtes; the pollen contained within them, as the *ſemen maſculinum*, or male ſeed; and the filament, which elevates the anthers, as the ſpermatic veſſels. *Vide* POLLEN and FILAMENTUM.

8. The ſtigma is to be conſidered in general, as the female organ of generation in plants.

Arguments in ſupport of the opinion that the Anther is the male organ of generation in plants.

1. The flower univerſally precedes the fruit, as generation and conception precede the birth. I ſay univerſally, becauſe the few inſtances which ſeem to contradict this aſſertion, are found, upon examination, to be exceptions in appearance only.

Meadow-ſaffron, *colchicum*; and witch-hazel, *hamamelis*; flower in autumn, and produce fruit the following ſpring: —a ſingular fact in vegetation, and which, to an inattentive obſerver, might ſuggeſt the opinion, that, in theſe plants, the flower is preceded by the fruit.

In the plantain-tree, *muſa*; the germen, or ſeed-bud, which is very large, has attained its full-growth, but not maturity, before the male flowers appear. The fruit, therefore, does not precede the flower, even in this inſtance, where the germen is not impregnated by the male duſt.

2. Another argument for the ſexes of plants, is derived from the ſituation and proportion of the ſuppoſed organs of generation, the anthers, and ſtigma.

In an erect, or upright flower, the anthers and ſtigma are either of equal length, as in moſt plants; or the anthers are conſiderably taller, that the duſt, when diſcharged, may fall upon the top of the ſtigma.

In an inverted flower, (*flos nutans*,) the female organ is longer than the male, for the ſame reaſon. Of this we have familiar inſtances in the ſnow-drops, campanulas, and fritillarias. It is obvious, that if the ſtamina were longer than the piſtillum, or female organ, in ſuch plants, no impregnation could ever, on the hypotheſis of Linnæus, poſſibly enſue:

ſue: as the duſt, when ripe and diſcharged, would fall to the ground, and never approach the ſtigma, which lies in the oppoſite direction.

In flowers that ſlope downwards, or droop, both organs incline towards the under ſide; and the anthers are generally placed immediately above the ſtigma. Wild ſenna, *caſſia*; and all the butter-fly ſhaped flowers, the *Diadelphia* of Linnæus, furniſh examples.

In flowers that ſlope upwards, *(flos adſcendens)*; both organs are placed cloſe under the upper ſide; as in the *Didynamia Gymnoſpermia* of Linnæus.

Thus we have ſeen, that the piſtillum, in every inſtance, follows the direction of the anther; that its length is likewiſe regulated by the male organ; and that the fine duſt diſcharged by the anthers does, in effect, fall upon the ſtigma.

In the pink, *dianthus*, the ſtyle is generally longer than the ſtamina: and the ſtigma is bent backwards, to receive the pollen, which otherwiſe would eſcape. In ſome ſpecies, the ſtyles are exceedingly long, but are ſo rolled back, that the impregnation by the male duſt can eaſily be accompliſhed without the inflection of the flower.

The long ſtyles in the fennel-flower, *nigella*, are likewiſe rolled back for the ſame purpoſe.

Hitherto we have treated of the ſituation of the anthers and ſtigma, when they are placed within the ſame covers, and form together a fructification, which is termed by Linnæus an hermaphrodite flower.

The ſituation of theſe eſſential parts of fructification, is not leſs favourable to the hypotheſis of the ſexes, when they are placed within diſtinct covers, upon the ſame root, as in the claſs *Monœcia* of Linnæus, where the flowers that have the anther only, which he calls male-flowers, are generally placed immediately above the female-flowers, or ſuch as have the piſtillum only; and that, either upon the ſame, or different foot-ſtalks. Thus in the genera *zea*, and *coix*, Job's-tears, the male-flowers, or thoſe furniſhed with the anthers, are placed above the female-flowers, upon different ſpikes in the former, and upon the ſame ſpike in the latter. *Vide* SPICA.

Exception.

Exception.—The genera *olyra*, *zizania*, and *poterium*, garden-burnet, have the male-flowers placed below the female; the two former on the ſame panicle; the latter on the ſame ſpike. *Vide* PANICULA.

In compound flowers, the *Syngeneſia* of Linnæus, there are few barren plants, or that do not ripen ſeed; a circumſtance which Linnæus accounts for from the ſituation of the anthers, which are, in a manner, perforated by the ſtigma. *Vide* SYNGENESIA.

In the order *polygamia fruſtranea*, of the ſame claſs, the florets in the circumference *(radius)* which are female, or furniſhed with the piſtillum only, are never impregnated, though there are hermaphrodite flowers in the center, (*diſcus*); becauſe the ſtigma is wanting. To this order belong the ſun-flowers, centaury, *&c.*

In ſaxifrage, *ſaxifraga*; and ſeveral plants, where the piſtillum is very ſhort; the anthers approach and form a compact body immediately above the ſtigma.

This approaching of the anthers, ſays Linnæus, is very remarkable in the genus *celoſia*, at the time of their burſting and diſcharging the duſt.

3. Among animals, the male and female organs of generation ripen, and are in a capacity of performing their functions much about the ſame time.

In plants, the ſtigma, which is the ſuppoſed female organ, is in its greateſt vigour, when the male duſt is diſcharged by its organ the anther.

This coincidence in point of time is obſerved, not only in hermaphrodite flowers, or ſuch as have the anthers and ſtigma contained within the ſame covers; but likewiſe in the claſſes *Monœcia* and *Diœcia* of Linnæus, where thoſe organs are placed apart within different covers, on the ſame root, as in the former, or on diſtinct roots, as in the latter. In theſe claſſes, the male flowers ripen their anthers, at the very time in which the female flowers ripen their ſtigma. To ſtrengthen the concluſion in favour of the ſexes from the above-mentioned facts, let it be remarked, that in the plantain-tree, *muſa*, where the male flowers are poſterior to the

female, there is no impregnation, the pericarpium being barren, or devoid of ſeeds.

4. In the generality of flowers, the ſtigma withers and falls off, after the diſcharge of the pollen and fall of the anthers.

Such are the principal arguments for the ſexes, ariſing from a general view of the ſtructure, proportion, and ſituation of the ſuppoſed organs.

Experiments on theſe organs, give riſe to a ſecond ſet of arguments; the management and culture of fig and palm-trees, furniſh a third ſort. Theſe, along with the oppoſite ſet of arguments, employed by Dr. Alſton, and other eminent naturaliſts, ſhall be fully enumerated under the article SEXUS PLANTARUM, whither we refer our readers.

ANTHOPHILI, (from ἄνθος, a flower, and φιλέω, to love). Floriſts.

The varieties ariſing chiefly from the colours of the corolla, in the ſame ſpecies of plants, are the principal object of the floriſt. In many ſpecies of flowers, the colour is variable; as in the tulip, hyacinth, ranunculus, pink, blue bottle, violet, columbine, fumatory, &c. Such flowers, therefore, claim, in an eminent manner, the attention of the floriſt. *Vide* VARIETAS.

Double flowers, which are a ſpecies of monſters in the vegetable kingdom, and ariſe from a luxuriancy of nouriſhment, are likewiſe the delight of the floriſt. *Vide* PLENUS *Flos*, MULTIPLICATUS *Flos*, &c. *Phil. Bot.* p. 81, 240.

ANTHUS, (from ἄνθος, a flower); the flower. A term uſed by Columna, ſynonimous to the *corolla* of Linnæus.

We have ſeen that the petals, or coloured leaves, are not eſſential to the exiſtence of a flower, which, according to Linnæus, is conſtituted by the preſence of the anthers and ſtigma. *Vide* Principles of the Sexual Method, under the article ANTHERA.

The ſuppoſed utility of theſe organs in the buſineſs of generation ſuggeſted the definition. When that utility was not ſo much as dreamt of, we need not wonder, that the petals,

the

the moſt conſpicuous and beautiful part of the plant, ſhould have claimed a principal regard, and even have been characteriſed by the name of *the flower*, by way of eminence; eſpecially as ſeveral Syſtems and Methods, particularly thoſe of Rivinus and Tournefort, are founded upon their figure, number, ſituation, and regularity.

APERTURA, (from *aperio*, to open); an aperture or opening; the minute opening in certain ſpecies of anthers ſo called. *Vide* ANTHERA.

APETALUS *Flos*, (from *a* priv. and *petalum*, a petal); having no petals, or corolla. The term was uſed by Tournefort, and adopted by Linnæus, and is equivalent to the *Imperfectus* of Rivinus, Khautius, and Pontedera; the *Stamineus* of Ray; the *Incompletus* of Vaillant, and the *Capillaceus* of other botaniſts. *Vide* COROLLA.

In almoſt every former ſyſtem, the preſence or abſence of ſuch a conſpicuous part as the petals, was a leading point: in the ſexual ſyſtem, however, the corolla is totally diſregarded in the primary diviſions, which are formed ſolely on the number, proportion, ſituation, union and abſence of the ſtamina, or ſuppoſed male organ of generation in plants. Hence we are not to expect in the *Genera Plantarum*, as in other botanical writings, a liſt, exhibiting at one view all the plants which are not furniſhed with petals: theſe are to be found diſperſed among the different claſſes in that accurate and elaborate work.

In general, few of the amentaceous flowers, and fewer of the claſs *Cryptogamia*, containing the moſſes, muſhrooms, ferns, and ſea-weed, are furniſhed with petals. *Vide* AMENTACEUS *Flos*, and CRYPTOGAMIA.

Many of the graſſes likewiſe, want the corolla.

Chriſtian Knaut, a Saxon, who was contemporary with Tournefort, and publiſhed a method founded upon the number and regularity of the petals, among other curious doctrines, denies the exiſtence of apetalous flowers.

APETALÆ, the name of a diviſion or claſs in moſt of the ſyſtematic botaniſts, conſiſting of ſuch herbs and trees as want the corolla. Apetalous herbs are generally ſubdivided

into apetalous properly ſo called, which want petals, but have the ſtamina: apetalous without flowers, which apparently want petals, ſtamina and calyx; as the ferns, which are dorſiferous, that is, bear their fruit on the back of the leaf: and apetalous without flower and fruit, as the moſſes and muſhrooms.

Apetalous trees contain, amongſt others, ſuch whoſe flowers have the ſpecies of calyx called *amentum*. *Vide* AMENTUM.

Theſe are the *amentacei* and *juliferi* of Tournefort, Hermannus, and others. *Vide* AMENTACEOUS *Flos*, &c. They form a conſiderable part of the claſſes *Monœcia* and *Diœcia*, of Linnæus. *Vide* MONOECIA, *&c.*

APEX, the top, or ſummit; a term uſed by Tournefort, Rivinus, and Ray, ſynonimous to the *anthera* of Linnæus. *Vide* ANTHERA.

APEX *Folii*, the tip or upper extremity of the leaf. *Vide* FOLIUM.

APHYLLÆ, (from α priv. and φυλλον, a leaf); devoid of leaves; the name of the firſt claſs in Sauvage's ingenious *Methodus Foliorum*, conſiſting of plants which are entirely deſtitute of leaves.

To this claſs belong muſhrooms, ſeveral of the ſea-weed, ruſh, garlick, &c.

APYRINÆ, (*apȳrĭnus et apȳrēnus*, without ſtone or kernel, or a ſmall one, from the Greek ἀ, privativ. and πυρην, *nucleus*, a kernel), the name of the fifty-third claſs in Lud. Gerard's Arrangement of the Plants that are natives of Provence, in France. It conſiſts of two genera, the myrtle and pomegranate.

AQUATICÆ *Plantæ*, (from *aqua*, water); plants that grow in, or near water. Aquatics. The name of a claſs in Dodoneus's, Porta's, and J. Bauhin's Methods.

When artificial arrangement was yet in its infancy, ſyſtems were conſtructed, not as in modern times, from the ſtructure and ſituation of a particular part, but from a complex view of the whole plant. Neither was this view confined merely to the habit; it included every circumſtance, however

however different; the place of growth, the time of flowering, the medicinal and œconomical uſes, the ſenſible qualities, and ſeveral other particulars, which by modern botaniſts, the only genuine ſyſtematical writers, are neceſſarily diſregarded as primary characters, but deſerve every conſideration as ſecondary marks of diſtinction and uſeful auxiliaries for obtaining a complete knowledge of the plant.

ARBOR, a tree; a perennial plant which riſes to a very great height, with a ſimple, woody, and durable ſtem, or trunk. By theſe characters, are trees, with great accuracy, diſtinguiſhed from herbs, whoſe ſtems are frequently compound, herbaceous, or ſucculent, and die down to the root every year.

All trees too are perennial, as is evident from the characters juſt enumerated: many herbs are either annual, that is, of one year's duration; or biennial, of two; thoſe only are perennial, whoſe roots, not periſhing with the ſtems, continue a long time under the ſurface of the ground, and put forth a new ſtem every year. *Vide* HERBA.

Upon theſe obvious and ſtriking differences was founded the very ancient diviſion of vegetables, into herbs and trees; though, perhaps, that diſtinction was principally ſuggeſted by the difference of ſize and duration of the plants in queſtion. Be that as it may, the diviſion was eſteemed ſo natural and ſpontaneous, that, from the time of Ariſtotle and Theophraſtus to the preſent age, it has obtained a principal place in almoſt every ſyſtem, thoſe of Rivinus and Linnæus excepted, which mix herbs and trees promiſcuouſly together.

Among the celebrated names in botany, which have retained the ancient diſtinction, are numbered Cæſalpinus, the father of ſyſtematic botany; Moriſon, Hermannus, Chriſtopher Knaut, Boerhaave, Ray, Pontedera, and Tournefort. The latter, rather than omit a diviſion, through cuſtom become neceſſary, choſe to hurt the elegance and uniformity of his plan; and, in fact, ſpun out into twenty-two claſſes, what, without ſuch a diviſion, might have been eaſily compriſed in ſeventeen.

On

On the oppoſite ſide are ranged, beſides Rivinus and Linnæus, already mentioned, Chriſtian Knaut, Ludwig, and other names of leſs note.

The diſtinction into trees and ſhrubs, though of equal antiquity, is neither ſo obvious, nor are its limits ſo accurately aſcertained. In fact, of the numerous characteriſtic differences which have been ſuggeſted by botanical writers, not one is perfectly ſatisfactory. To ſay, with Tournefort, that trees are univerſally taller than ſhrubs, is, in effect, ſaying nothing, unleſs a certain fixed, immutable ſtandard were previouſly eſtabliſhed. Beſides, every thing reſpecting dimenſion is ſo variable in its nature, and depends ſo much upon difference of climate, ſoil and management, that were a ſtandard of this kind attempted to be eſtabliſhed, the greateſt confuſion would enſue; and the ſame plant in different countries, and even in oppoſite ſoils in the ſame country, would receive different appellations, according as it exceeded, or came ſhort of the given ſtandard.

Thus the *ricinus*, or palma-chriſti; the dwarf roſebay, *rhododendron*; the ſtrawberry-tree, *arbutus*; and ſeveral others, which grow to the ſize of very large trees in warm climates, are, in this country, equalled and even exceeded in height by many of our ſmalleſt ſhrubs.

The difference of ſoil and culture in the ſame climate, produces a like diverſity in dimenſion. Thus to take an example from herbaceous vegetables, the marigold, which, in a fat and moiſt earth riſes two feet high, ſcarce exceeds the ſame number of inches in a dry and gravelly ſoil.

Nature, ſays Linnæus, has put no limits between trees and ſhrubs. Where then are we to ſearch for the foundation of this diſtinction? Not in the difference of ſize and height, for nothing can be more fallible. Either, he continues, there are no limits at all, or they are to be found in the buds; and the plants are ſtiled trees, when their ſtems come up with buds; ſhrubs when they ariſe without buds: but this diſtinction is ſufficiently confuted by its author, who immediately ſubjoins, that there are ſeldom any buds upon the very large trees in India; which muſt, therefore, notwithſtanding

ing their great height, according to this definition, be reckoned ſhrubs.

The learned Dr. Alſton, in his *Tyrocinium Botanicum*, ſeems to conſider the diſtinction into trees and ſhrubs as a true natural diſtinction, and endeavours to trace its foundation in the internal ſtructure of the plants themſelves. All trees, ſays he, whether they bear buds or not, are covered with the two barks, the outer and inner, called by botaniſts, *cortex* and *liber*. Shrubs differ from herbaceous vegetables in the duration of their ſtems; from trees in the nature of their covering, which is not a bark, but a cuticle, or ſimple ſkin.

This thought is ingenious; but the fact on which it depends is not ſufficiently aſcertained.

The farther diſtinction into ſhrubs and under-ſhrubs, which is exceedingly arbitrary and indeterminate, was firſt ſuggeſted by Cluſius, in a work entitled, *Rariores & Exoticæ Plantæ*, publiſhed in 1576; and afterwards adopted by Cæſalpinus, and others. *Vide* FRUTICES.

ARBUSTIVA, (from *arbuſtum*, a copſe of ſhrubs, or trees; an orchard, or vineyard;) the thirty-ninth order of plants in the former editions of Linnæus's Fragments of a natural Method, containing theſe genera, the myrtle, mock-orange, *philadelphus*; *eugenia*, guayava, or bay-plumb, *pſidium*; and the clove-tree, *caryophyllus*. The firſt four belong to the claſs *Icoſandria* in the ſexual method; the laſt to the claſs *Polyandria*.

In the lateſt editions of theſe fragments, the above-mentioned genera form the nineteenth order, under the title of *Heſperideæ*. *Vide* HESPERIDEÆ.

ARILLUS, (from *arēre*, to be dry or parched,) a term invented by Linnæus, and defined to be the proper exterior coat or covering of the ſeed, which, drying, falls off ſpontaneouſly.

All ſeeds are not furniſhed with an *arillus*; in many, a dry covering, or ſcarf-ſkin, ſupplies its place. In jeſſamine, hound's tongue, *cynogloſſum*; cucumber, fraxinella, *dictamnus*; ſtaff-tree, *celaſtrus*; ſpindle-tree, *euonymus*; African ſpiræa,

ſpiræa, *dioſma*; and the coffee-tree, *coffea*; it is very conſpicuous.

In the genus hound's tongue, four of theſe *arilli*, or proper coats, each infolding a ſingle ſeed, are affixed to the ſtyle, or pointal; and in this circumſtance, ſays Linnæus, does the eſſence of the genus conſiſt.

In fraxinella, the *arillus* is common to two ſeeds.

The ſtaff-tree has its ſeeds only half-involved with this cover.

The *Arillus* is either

Baccatus, ſucculent, and of the nature of a berry, as in the ſpindle tree, *euonymus*.

Cartilagineus, cartilaginous, or griſtly, as in the African ſpiræa, *dioſma*.

Coloratus, coloured, as in the ſtaff-tree.

Elaſticus, endued with elaſticity for diſperſing the ſeeds; as is remarkable in the African ſpiræa, *dioſma*; and fraxinella.

Scaber, rough, and knotty, as in hound's tongue.

Although covered with an *arillus*, or other dry coat, ſeeds are ſaid to be naked, (*ſemina nuda*,) when they are not incloſed in any ſpecies of *pericarpium*, or fruit-veſſel; as in the graſſes, and the *labiati*, or lipped flowers of Tournefort; which correſpond to the *Didynamia Gymnoſpermia* of Linnæus.

Seeds are ſaid to be covered, (*ſemina tecta*,) when they are contained in a fruit-veſſel, whether capſule, pod, or pulpy pericarpium of the apple, berry, or cherry kind. *Vide* SEMEN.

This exterior coat of the ſeed is, by ſome former writers, ſtyled *Calyptra*. *Vide* CALYPTRA. By Scopoli, the ingenious author of the *Flora Carniolica*, it is termed *Theca*, (a ſheath or caſe).

The different ſkins, or coverings of the ſeed, are adapted, ſay naturaliſts, for receiving the nutritive juices, and tranſmitting them within.

ARISTA, (derived, as the preceding term, from *areo*,

to

to be dried), the awn, ſharp beard, or point, iſſuing from the huſk, or ſcaly flower-cup, of the graſſes, called *Gluma*. *Vide* GLUMA.

The greateſt part of the plants that belong to the natural order of graſſes, are *hermaphrodite*, that is, bear flowers, which have the ſtamina and piſtillum within the ſame covers. *Vide* HERMAPHRODITUS *Flos*.

Some, however, are *androgynous*, that is, have both male and female flowers, produced on the ſame root; as the genera *zea*, *coix*, *olyra*, *tripſacum*, *zizania*. *Vide* MASCULLUS *Flos*, and ANDROGYNA *Planta*.

Others are *polygamous*, that is, bear hermaphrodite flowers, and flowers of either, or of both ſexes, on the ſame, or on different roots: as the genera *andropogon*, *holcus*, Indian millet; *apluda*, *ægilops*. *Vide* POLYGAMIA.

The hermaphrodite graſſes are all reduced, except three, (vernal graſs, *anthoxanthum*; *cinna*, and rice, *oryza*;) under Linnæus's third claſs, *triandria*; the androgynous belong to the claſs *Monœcia*; and the polygamous to the claſs *Polygamia*. *Vide* MONŒCIA, POLYGAMIA.

Of hermaphrodite graſſes, ſome want the beard, as the genus *poa*.

A like deficiency is obſerved in the genera *zea*, *coix*, &c. which range under the head of androgynous graſſes.

Both male and female flowers of the genus *olyra*, have one of the valves only of the huſky calyx terminated with a beard.

The male flower of the genus *zizania*, wants the beard; the huſky corolla of the female, (*corolla gluma*,) at the termination of its large outward valve, or petal, is furniſhed with a very long one.

Of polygamous graſſes, *andropogon* and *holcus* want the *ariſta* in the calyx; the huſk of the corolla of the hermaphrodite flower, in the former, has a long, ſharp, and twiſted beard, proceeding from the baſe of the greater valve: in the latter, the outward valve is furniſhed with a very rigid beard of the ſame kind. The inner valve has none.

The valves of the huſky calyx of the hermaphrodite

flower, in the genus *ægilops*, are furniſhed with various beards.

The outer valve of the huſky corolla, in the ſame genus, is terminated with a double or triple beard. The inner valve has none.

Ariſtæ are either

Divaricatæ, ſcattered, or placed at a conſiderable diſtance from each other, oppoſed to *confertæ*, as in *bromus ſquarroſus*.

Dorſales, fixed to the back, or outward part of the huſk, as in oat, and fox-tail graſs, *alopecurus*.

Erectæ and *rectæ*, upright, perpendicular; as in *bromus*, and winged ſpike-graſs, *ſtipa*.

Filiformes, thread-ſhaped, as the *ariſtæ* of a ſpecies of panic-graſs, called by Linnæus, *panicum hirtellum*.

Glutinoſæ, covered with a ſtiff glue; as in *panicum hirtellum*.

Geniculatæ, jointed; as in vernal graſs, *anthoxanthum*.

Læves, ſmooth, or poliſhed, without any roughneſs; as in *avena fatua*.

Lanatæ, woolly, covered with a ſoft ſubſtance like wool; as in *ſtipa pennata*, and *ariſtida plumoſa*. In the laſt genus, there are three *ariſtæ*; the intermediate one only is woolly.

Longiſſimæ, very long; as in the winged ſpike-graſs, *ſtipa*.

Patulæ, ſpreading; as in *ariſtida*, and *bromus ſcoparius*.

Piloſæ, hairy, covered with *pili*; as in *ſtipa tenaciſſima*, where the *ariſtæ* are hairy at the baſe.

Plumoſæ, feathery; as in *geum*.

Recurvæ, bent back; as in *andropogon*, and *agroſtis canina*.

Retortæ and *Reflexo-tortæ*, twiſted backwards; this is exemplified in one of the *ariſtæ* of the genus *lagurus*.

Sanguineæ, of a blood colour; as in *panicum hirtellum*.

Setaceæ, briſtly, covered with *ſetæ*, (*Vide* PUBES); as in the *agroſtis canina*, and *hordeum jubatum*.

Terminales, fixed to the apex of the huſk, as in *olyra*, and *lagurus*.

Tortiles, wreathed or twiſted like a rope; as in *andropogon*, *ſtipa*, and *aira montana*. The beards of oats are twiſted into a ſpiral form.

Villoſæ,

Villoſæ, hairy, almoſt ſynonimous with *piloſæ*; exemplified in *lagurus*.

Uncinatæ, hooked; as in *panicum hirtellum*, and *geum urbanum*.

Note, the ſeeds of herb-bennet, *geum*, are furniſhed with long jointed beards.

ARMA, arms; offenſive weapons. One of the ſeven kinds of *Fulcra*, or props of plants, enumerated by Linnæus in the *Delineatio Plantæ*, at the beginning of his Syſtem of Nature; and by Elmgren, a ſcholar of Linnæus, in his *Termini Botanici*, firſt publiſhed in the *Amænitates Academicæ*.

For the numerous variations theſe *fulcra* have undergone, ſee the article FULCRA.

In the lateſt editions of the *Philoſophia Botanica* that I have ſeen, no mention is made of *arma*, in enumerating the *fulcra*; in its ſtead are retained the antient FULCRA, *aculeus*, and *ſpina*, prickles and thorns; which, in the *Delineatio Plantæ* abovementioned, are regarded only as ſpecies: *armæ* being the genus.

The different ſpecies of armour with which plants are furniſhed, are *aculei*, prickles; *ſpinæ*, thorns; *furcæ*, forks; and *ſtimuli*, ſtings. *Vide* ACULEUS, SPINA, *&c.*

They are intended, ſay Naturaliſts, to keep off animals from hurting the plants.

AROMATA, (Gr. ἀρωματα, all ſweet ſpices, herbs, ſeeds, and roots) the name of a diviſion in Ray's, Monti's, and Sceuchzerus's arrangement of the graſſes; conſiſting of ſuch as have an odoriferous quality.

AROMATICÆ *Plantæ*, odoriferous, of a ſtrong agreeable ſmell and taſte; aromatics; the name of a claſs in Dioſcorides, Cluſius, Hernandes, J. Bauhin, Johnſton, Rumfius, and ſeveral other botaniſts, who have arranged plants according to their virtues and ſenſible qualities.

The plants of the order *Didynamia Gymnoſpermia* of Linnæus, which correſpond to the *labiati*, or lipped flowers of Tournefort, are all aromatics.

ARTICULUS, that part of the *culmus*, or ſtalk in graſſes,

graſſes, which is intercepted, or lies between two joints, or knots. *Vide* CULMUS.

ARUNDINACEÆ *Plantæ*, (from *arundo*, a reed); the twenty-ſeventh claſs in Ray's Method, conſiſting of trees, whoſe ſeeds are *Monocotyledonous*; that is, furniſhed with a ſingle *cotyledon*, or lobe. The *Palms* belong to this claſs. *Vide* COTYLEDONES.

ASCYROIDEÆ, (ASCYRUM, *Plin.* St. John's or St. Peter's wort), the name of the thirteenth claſs in Scopoli's *Flora Carniolica*, conſiſting of *Aſcyrum*, *Hypericum*, and ſuch genera as reſemble them in habit and ſtructure.

ASPERIFOLIÆ *Plantæ*, (from *aſper*, rough; and *folium*, a leaf); rough leaved plants. The name of a claſs in Hermannus, Boerhaave, and Ray's Methods, conſiſting of plants which have four naked ſeeds, and whoſe leaves are rough to the touch.

In Tournefort's ſyſtem theſe plants conſtitute the third ſection or order of the ſecond claſs; and in Linnæus's Sexual Method, they make a part of the *Pentandria Monogynia*. *Vide* PENTANDRIA.

ASPERIFOLIÆ, the forty-firſt order of plants in Linnæus's Fragments of a Natural Method.

Liſt of Genera *contained in this Natural Order.*

SECTION I.

Rough-Leaved Plants, with four naked Seeds. Vide SEMEN.

Linnæan Genera.			*Engliſh Names.*
Anchuſa,	—	—	Bugloſs.
Aſperugo,	—	—	Small wild Bugloſs, or Great Gooſe Graſs.
Borago,	—	—	Borage.
Cynogloſſum,	—	—	Hound's-Tongue, Venus's Navel-Wort, or Lawn.
Echium,	—	—	Viper's Bugloſs.
Heliotropium,	—	—	Turnſole.
Lithoſpermum,		—	Gromwell, or Graymill.
Lycopſis.			
Myoſotis,	—	—	Mouſe-ear Scorpion-Graſs.

Onoſma.

Linnæan Genera.			*Engliſh Names.*
Oneſma.			
Pulmonaria,	—	—	Lungwort, or Sage of Jeruſalem.
Symphytum,	—	—	Comfrey.

SECTION II.

Rough-Leaved Plants with two naked Seeds.

Cerinthe,	—	—	Honey-wort.

SECTION III.

Rough-Leaved Plants with five naked Seeds.

Nolana.

SECTION IV.

Rough-Leaved Plants with covered Seeds; Vide SEMEN. *or a Seed-Veſſel, whether pulpy, or dry.*

1. *With a pulpy Seed-Veſſel, with, or without a Stone*; (*Drupa,* or *Bacca.*)

α With a Stone, (*Drupa.*)

Cordia,	—	—	Sebeſten.
Varronia.			

β Without a Stone, (*Bacca.*)

Tournefortia.

Ehretia.

2. *With a dry Seed-Veſſel, or Capſule.*

Patagonula.

Habit and Structure of the Plants of this Order.

Moſt of the plants of this order are herbaceous and perennial.

The ROOTS are branched and fibrous.

The STEMS and branches rounded.

The BUDS of a conic form, naked, or without ſcales.

The LEAVES ſimple, alternate, commonly very rough to the touch, and in moſt of the herbaceous plants, ſeſſile, that is, attached to the ſtem and branches without any foot-ſtalk. In the few trees, however, of this order, the leaves

have a foot-ſtalk, the lower part of which, after the fall of the leaves, remains on the branches like a ſpine or thorn.

Note, in the genus *Tournefortia*, which is of the tree kind, the foot-ſtalk of the leaves is jointed.

In ſome ſpecies of *Tournefortia*, *varronia*, and turnſole, *heliotropium*; the leaves are placed almoſt oppoſite; and in the ſmall wild bugloſs, *aſperugo*, there are three or four leaves diſperſed in whirls round the ſtem. The leaves at the bottom of borage are oppoſite: thoſe at the top, alternate.

The HAIRS, (*pili*,) are ſimple, and generally very rough to the touch.

The FLOWERS are in ſome genera ſolitary; but commonly collected into a *ſpike*, or *corymbus*, (*Vide* SPICA, CORYMBUS), and do not proceed from the angle formed by the ſtem or branch with the leaf, as in many plants, but from the ſide of the leaf, or from that part of the ſtem which is oppoſite to it.

In the genus *varronia*, the ſpike of flowers proceeds from the *axilla* or angle of the leaves.

The flowers are generally arranged on the ſide of the *ſpike*, or *corymbus*, and unaccompanied with any ſcale.

They are almoſt univerſally hermaphrodite; in a few ſpecies of ſebeſten, *cordia*, male and female flowers are produced upon different roots.

The CALYX, or flower-cup, is monophyllous, that is, compoſed of one leaf, which is divided from three to ten equal or unequal parts. Thoſe of the firſt ſection with four naked ſeeds, have the calyx deeply divided into five ſegments, which, as in the other genera of this order, are permanent, accompanying the germen to its maturity. Indeed, in the greateſt number of rough-leaved plants, the calyx ſerves as a *pericarpium* or ſeed-veſſel, and therefore could not be taken away, without injuring the tender ſeeds which are nouriſhed in its boſom.

The COROLLA, or coloured inner cover of the flower, is monopetallous, that is, compoſed of one petal, which, in different plants, is bell—funnel—ſalver—and wheel-ſhaped. The diviſions of the limb or upper part of the petal, are generally

generally five in number, alternate with thoſe of the calyx, equal, and regular, except in viper's bugloſs, *echium*; where the ſegments are unequal.

The STAMINA are five in number, alternate with the diviſions of the corolla, and oppoſite to thoſe of the calyx. They are equal, attached to the tube of the corolla a little above its origin, and of the ſame height.

The ANTHERS or ſummits, are in ſome genera *connivent*; that is, approach and form a compact body above the filaments. This is particularly exemplified in borage, lungwort, *pulmonaria*; and the genus *tournefortia*.

The PISTILLUM, pointal, or female organ, is generally compoſed of a ſlender ſtyle, of the ſame length with the ſtamina, and crowned with a ſimple ſtigma. It proceeds from a germen, which in ſome plants is undivided, but generally ſplit into four. In hound's-tongue, the ſtyle is permanent.

In all the plants of the three firſt ſections, there is properly no ſeed-veſſel; the calyx, in theſe genera, ſupplies its place, and continues till the ſeeds are arrived at maturity.

In the plants of the fourth ſection, the ſeed-veſſel is either a *capſule*, as in *patagonula*; pulpy with a ſtone, (*drupa*,) as in ſebeſten, *cordia*; or pulpy without a ſtone, (*bacca*,) as in *tournefortia*.

The SEEDS are generally four in number, and lodged in the bottom of the calyx.

In honey-wort, *cerinthe*, there are two ſeeds of a hard bony nature, each of which is furniſhed with two cells; and in the genus *nolana*, the number of ſeeds is five.

Sebeſten, and the genus *varronia*, have a ſtone or nut, which is divided into four cells.

The plants of this natural order are moſtly mucilaginous, with little taſte or ſmell.

Moſt of the rough-leaved plants, particularly thoſe of the firſt ſection, are uſed in medicine. The flowers are eſteemed cordial; the leaves and roots vulnerary and aſtringent; and the hard bony ſeeds, particularly thoſe of Gromwell, *lithoſpermum*, are reckoned powerful promoters of urine.

A decoction of the roots and leaves of comfrey, (*ſymphytum officinale*,) has been ſucceſsfully applied in violent coughs, and diſorders of the lungs and breaſt.

Externally, theſe plants are uſed for burnings, and poiſonous bites; they extirpate warts, and relieve diſorders in the loins.

AUTUMNALES *Plantæ*, (*autumnus*, autumn,) plants that flower in autumn. The third diviſion in Du Pas's arrangement, from the time of flowering.

AXILLA, an arm-pit; the angle formed by the branch and ſtem, or by the leaf with either.

Leaves are ſaid to be *axillary*, which proceed from the angle formed by the ſtem and branch. *Vide* FOLIUM.

B.

BACCA, a berry; defined by Linnæus to be a pulpy *pericarpium* or ſeed-veſſel without a valve, incloſing ſeveral ſeeds which are naked, that is, have no other covering. The ſeeds are ſometimes diſperſed promiſcuouſly through the pulp, as in the water-lily; but generally placed on receptacles or foot-ſtalks within the pulp, as in the currant, gooſeberry, raſpberry, &c.

In the leſſer burdock, *xanthium*, the ſeed-veſſel, which is called by Linnæus, though improperly, a berry, is dry, and contains within it a nut furniſhed with two cells.

The ſeed-veſſel or fruit of the *capſicum*, which the ſame author alſo improperly ſtyles a berry, has no pulp, and is hollow within.

From theſe and other inſtances which might be produced, we may ſafely affirm, either, that the definition of a berry juſt now given is imperfect, or that the ſeed-veſſels of a great number of plants are, in the *Genera Plantarum*, wrongly denominated berries. To ſay truth, it is ſometimes difficult to refer a pericarpium to the head of *bacca*, or *drupa*, as defined by Linnæus. The only difference betwixt theſe ſeed-veſſels conſiſts in the nature of the ſeeds incloſed within

within the pulp. In the latter is incloſed a nut, or ſtone; in the former, a number of naked ſeeds. Theſe definitions being eſtabliſhed, to what head are we to refer the leſſer burdock, which, as we have ſeen, contains a nut within a dry pericarpium? Why, certainly, to the head of *drupa*, as well as the walnut, and many other plants which have a dry ſeed-veſſel incloſing a ſtone, or nut. On the other hand, we may refer the walnut, and other dry pericarpiums, which incloſe a nut, with equal propriety, to the head of *bacca*, as the leſſer burdock, the ſeed-veſſel of which is denominated, by Linnæus, a berry.

The very different fruits, or, to ſpeak more properly, ſeed-veſſels of the ſumach; night-ſhade, *ſolanum*; ſow-bread, *cyclamen*; medlar, *meſpilus*; orange, *citrus*; and pine-apple, *bromelia*; are all denominated berries.

The berry is commonly round, or oval, and frequently furniſhed, like the apple, and other fruits of that kind, with an *umbilicus* or ſmall cavity, at the end oppoſite to the foot ſtalk.

A berry is ſaid to be *proper*, when it is formed of the pericarpium or ſeed-veſſel; *improper*, or *ſingular*, when it is formed of any of the other parts.

The latter ſpecies of formation is frequent, and admits of numerous varieties.

The following are the moſt conſiderable.

In the mulberry, roſe, blite, and myrtle-leaved ſumach, *coriaria*; a large, fleſhy and ſucculent calyx becomes a berry.

In the ſtrawberry and caſhew nut, *anacardium*; a berry is formed of the common receptacle; in the raſpberry and adonis, of a ſeed; in marvel of Peru, *mirabilis*, of the *nectarium*; (*Vide* NECTARIUM) in garden-burnet, *poterium*, of the tube of the corolla, which hardens and ſhuts for that purpoſe; in ſpindle-tree, *euonymus*, of a ſucculent *arillus*, or proper ſeed-covering. *Vide* ARILLUS.

The berry does not naturally gape, or burſt; the diſperſion of the ſeeds within the pulp being deſigned to be performed by means of animals. *Vide Philoſophia Botanica*, p. 75. 87.

BACCIFERÆ *Herbæ*, (from *bacca*, a berry; and *fero*, to bear); herbs that have a berry for their *pericarpium* or ſeed-veſſel.—The ſixteenth claſs in Morriſon, ſeventeenth in Hermannus, firſt in Chriſt. Knaut, twenty-fifth in Boerhaave, and ſeventeenth in Ray's Method; conſiſting in ſome ſyſtems of all ſuch plants as have a pulpy fruit, whether of the apple, berry, or cherry kind; in others, with more propriety, of ſuch only as have that ſpecies of pulpy pericarpium, called *bacca*. *Vide* BACCA.

BARBA, a beard; a ſpecies of *pubes* or down, with which the ſurface of ſome plants is covered. *Vide* PUBES.

The term was invented by Linnæus, and made its appearance in the *Delineatio Plantæ*, without any explanation. Its meaning, therefore, has not been accurately aſcertained: though, by its application in the *ſpecies plantarum*, it ſeems to ſignify a tuft or bunch of ſtrong hairs terminating the leaves. *Meſembryanthemum barbatum*, furniſhes an example.

BARBA *Corollæ ringentis*, the lower-lip of a ringent, or gaping corolla. *Vide* COROLLA.

The term was invented by Rivinus, and ſtands oppoſed to *galea ringentis*, the upper-lip. *Vide* GALEA *corollæ ringentis*.

BARBATUS *Flos*, (from *barba*, a beard); a bearded, gaping, or ringent flower; a term uſed by Rivinus, ſynonimous to the *ringens* of Linnæus, and the *labiatus* and *perſonatus* of Tournefort. *Vide* COROLLA, and LABIATUS *Flos*.

The ringent, or gaping flowers, form the *Didynamia* of the Sexual Method. *Vide* DIDYNAMIA.

BICORNES *Plantæ*, (from *bis*, twice, and *cornu*, a horn); plants whoſe anthers have the appearance of two horns.

The name of the eighteenth order in Linnæus's Fragments of a Natural Method.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Plants with horned Anthers, *and four* Stamina.

Linnæan Genera.	*Engliſh Names.*
Blaeria.	

SECTION

SECTION II.

Plants with horned Anthers, *and five Stamina.*
(Pentandria *of* Linnæus.)

Linnæan Genera.			*Engliſh Names.*
Azalea.			
Myrſine,	—	—	African Box.

SECTION III.

Plants with horned Anthers, *and eight Stamina.*
(Octandria *of* Linnæus.)

Erica,	—	—	Heath.
Vaccinium,	—	—	Whortle, or Bilberries.

SECTION IV.

Plants with horned Anthers, *and ten* Stamina.
(Decandria *of* Linnæus.)

Andromeda.			
Arbutus,	—	—	Strawberry-tree.
Clethra.			
Epigæa,	—	—	Trailing Arbutus.
Gaultheria.			
Kalmia,	—	—	Dwarf-Laurel of America.
Ledum,	—	—	Marſh Ciſtus, or wild Roſemary.
Pyrola,	—	—	Winter-Green.
Rhododendrum,		—	Dwarf Roſe bay.
Rhodora.			
Royena,	—	—	African Bladder-Nut.

SECTION V.

Plants with horned Anthers, *and twelve or more* Stamina.
(Dodecandria *of* Linnæus.)

Garcinia,	—	—	Mangoſtan.
Haleſia.			
Styrax,	—	—	Storax-Tree

SECTION VI.

Plants with horned Anthers, *and many ſets of united* Stamina.

(Polyadelphia *of* Linnæus.)

Linnæan Genera.		*Engliſh Names.*
Citrus,	— —	Citron, Orange, Lemon.

SECTION VII.

Plants with horned Anthers, *and Hermaphrodite Flowers, with Flowers of either or both Sexes, on diſtinct Roots.*

(Polygamia Dicœcia *of* Linnæus.)

Dioſpyros,	— —	Indian Date Plumb.

The appearance of horned *anthers*, which has given name to this order, is not very conſpicuous, unleſs in the following genera: whortle-berries, heath, ſtrawberry-tree, dwarf roſe-bay, and trailing arbutus. The fifth and ſixth ſections ſeem to be improperly annexed to this order.

Habit and Structure of the Plants of this Natural Order.

The plants of this order are all of the ſhrub and tree kind.

The ROOTS are branched and fibrous.

The STEMS and branches cylindric.

The BUDS conic, ſometimes covered with ſcales, as in the ſtrawberry-tree; ſometimes naked or without ſcales, as in ſtorax.

The LEAVES are generally alternate; in heath, *rhododendron*, and ſome ſpecies of *kalmia*, they are oppoſite.

In moſt of the plants of this order, the leaves are either ſeſſile, that is placed upon the branches without a foot-ſtalk, or ſupported by a very ſhort foot-ſtalk, which is ſemi-cylindric, and flat above. In a ſpecies of *rhododendron*, called *dauricum*, the leaves are furniſhed with long foot-ſtalks.

The FLOWERS in this order are univerſally hermaphrodite, except in one genus, Indian date plumb, *dioſpyros*; where hermaphrodite and male flowers are produced in the ſame ſpecies, upon diſtinct roots.

The flowers proceed either ſolitary, or in a *corymbus*, from the angles formed by the leaves and branches; or hang down

down in ſpikes and cluſters, at the end of the branches; each flower having a ſmall ſcale, or floral leaf, placed under it.

In moſt plants of this order, the calyx is placed around or below the germen. In the genera *vaccinium*, *ſtyrax*, *haleſia*, it is ſeated above the germen; a circumſtance which eſſentially diſtinguiſhes thoſe genera from all the plants of the family to which they belong.

The CALYX is univerſally a *perianthium*, and generally monophyllous or of one piece deeply divided into four or five ſegments, which are permanent, that is, accompany the germen to its maturity. The ſegments are often acute, and ſometimes coloured. In heath, *erica*; and mangoſtan, *garcinia*; the flower-cup is compoſed of four diſtinct leaves.

Trailing arbutus, *epigæa*; and the genus *gaultheria*; have the appearance of a double calyx: the external conſiſting of three leaves in the former, of two in the latter; the internal being divided into five ſegments in both.

Some ſpecies of heath, *erica*, have likewiſe a double calyx.

The inner calyx in the genus *gaultheria* becomes pulpy like a berry, and in this form ſurrounds the ſeed-veſſel, which is a *capſule*. *Vide* CAPSULA.

In the orange-tree, *citrus*, the calyx is *marceſcent*, that is, withers without falling off.

The COROLLA, or coloured inner cover, is generally monopetalous, and bell or funnel-ſhaped; the figure, however, is not very conſtant, even in plants of the ſame genus, as is remarkably the caſe in heath *erica*; and the genus *andromeda*; which, in this and other circumſtances, are ſo ſimilar, as ſcarce to be diſtinguiſhed but by the number of ſtamina.

The LIMB or upper part of the petal, is commonly divided into four or five ſegments, which are ſometimes rolled back, as in *vaccinium*; ſometimes bent inwards, as in *blaeria*.

The limb too is ſometimes ſlightly cut, as in the genus *gaultheria*; ſometimes divided almoſt to the bottom, as in trailing arbutus, *epigaea*; and the ſtorax-tree, *ſtyrax*.

The

The TUBE or lower part of the petal, is cylindric, and generally of the ſame length with the calyx. In the dwarf laurel of America, *kalmia*, it is longer than the calyx. The tube in trailing arbutus, *epigaea*, is hairy within.

Dwarf laurel of America, *kalmia*; and the genus *gaultheria*, are furniſhed with a *nectarium* of ten pieces, which, in the former, is horn-ſhaped, prominent, and ſurrounds the limb of the corolla; in the latter, is placed round the *germen* or ſeed-bud, within the ſtamina. *Vide* NECTARIUM.

Marſh-ciſtus, *rhodora*, *clethra*, winter-green, *pyrola*; orange-tree, *citrus*; and *garcinia*; are polypetalous; that is, have a corolla compoſed of more pieces than one.

The number of STAMINA in this order is from four to twenty. Theſe are generally erect, and attached to the lower part of the tube of the corolla. In *blaeria*, American upright honey-ſuckle, *azalea*; *gaultheria*, heath, *erica*; and Indian date plumb, *dioſpyros*, which are monopetalous; the ſtamina are inſerted into the common receptacle.

Dwarf roſe-bay, *rhodora*, and *gaultheria*, have declining ſtamina.

The ANTHERS or ſummits are bifid or forked below, and being ſlightly attached to the filaments, are frequently inverted in ſuch manner as to exhibit an appearance like two horns at top. This appearance, however, as we obſerved above, is conſpicuous in a few genera only.

In winter-green, *pyrola*; and heath, *erica*; the anthers are not inverted, being forked at top.

African bladder-nut, *royena*, according to Linnæus, has two anthers upon each filament: (*Vide* ANTHERA *Didyma*.) though I am apt to imagine he has miſtaken the horns or forked ſummits of this genus, for two diſtinct anthers.

In whortle-berries, *vaccinium*, the back of the anthers is furniſhed with two ſpreading *ariſtæ* or beards.

The GERMEN, or ſeed-bud, in plants of this order, is generally roundiſh, and ſeated above the receptacle. In *rhododendron*, and *blaeria*, it is cornered. *Vaccinium*, *haleſia*, and *ſtyrax*, have the germen below the receptacle.

The

The STYLE is ſingle, thread-ſhaped, of the ſame length with the corolla, and in a few genera permanent.

African bladder-nut, *royena*, has two ſtyles; the genus *garcinia* ſcarce any; in *blaeria*, the ſtyle is much longer than the corolla.

The STIGMA or top of the ſtyle, is obtuſe, and frequently entire.

In heath, the ſtigma is four cornered, and divided in four.

Trailing arbutus, mangoſtan, and the genus *rhodora*, have likewiſe a divided ſtigma.

The SEED-VESSEL is either a *capſule* with five cells, as in *kalmia*; a roundiſh *berry* with diviſions of the ſame kind, as in the ſtrawberry-tree: or an oblong four-cornered *nut* with two cells, as in *haleſia*.

The SEEDS are numerous, frequently hard, or bony, generally roundiſh, ſometimes cornered.

The plants of this order are aſtringent; particularly heath, winter-green, whortle-berries, and uva urſi, (*arbutus*.)

The berries of the Indian date plumb, *arbutus*, and *vaccinium*, are acid and eſculent.

From the ſtorax-tree is drawn, by inciſion, a fragrant, reſinous gum, which is much uſed in medicine, particularly for coughs, catarrhs, and internal ulcers.

The leaves of winter-green, (*pyrola*,) ſays Lemery, are uſed internally, either in infuſion, or powder, for the hæmorrhoids, inflammations of the breaſt, and fluxes of the lower belly: externally in plaiſters and ointment, for ſtopping blood, and drying up wounds.

The flowers of the Azalea tribe bear a ſtriking reſemblance to thoſe of honey-ſuckle, whence the name of American upright honey-ſuckle, by which the Virginian ſpecies are diſtinguiſhed. From the clammineſs of the flowers of one of theſe ſpecies, hence termed *azalea viſcoſa*, and by Cateſby, *Ciſtus Virginiana, flore et odore periclymeni*, it ſeems highly probable, that the plant poſſeſſes balſamic virtues, which, if particularly inveſtigated, might render it of ſovereign uſe in medicine.

From the dried peel of the fruit of the Japaneſe Citron,

the

the *citrus trifoliata* of Linnæus, cut into ſmall pieces, is prepared, with the addition of ſome other ingredients, a celebrated medicine known in Japan by the name of Ki-ko-ke; by which name the fruit itſelf is known among the vulgar. It is a thorny ſhrub, the trunk of which, ſays Kempfer, by age and culture, acquires the thickneſs of a tree. The leaves grow by threes like thoſe of trefoil, upon the extremity of a common foot-ſtalk: and to the white flowers, which reſemble thoſe of medlar, ſucceeds a fruit, which in external beauty differs nothing from a middle-ſized orange, the internal ſtructure of which it likewiſe reſembles, except that the pulp, which is contained in a cavity having ſeven partitions, is glutinous, of an unpleaſant ſmell, and harſh diſagreeable taſte. The ſeeds are exactly like thoſe of the orange, and have the ſame taſte with the pulp. See Kempferi Amœnit. Exoticæ. p. 801.

BICORNES, is likewiſe the name of the forty-fourth claſs or natural order, in Lud. Gerard's Arrangement of the Plants that are natives of Provence in France; conſiſting, like the ſame order in Linnæus, of plants whoſe anthers have the appearance of two horns. The genera deſcribed by Gerard are,—*vaccinium*, *erica*, *azalea*, *rhododendron*, *arbutus*, *ſtyrax*, *pyrola*, and *hedera*, (ivy.) The laſt mentioned genus, though its anthers are bifid at the baſe, does not belong to Linnæus's claſs *Bicornes*; but is placed with the vine, and ſome other genera of plants, in the order *hederaceæ*. *Vide* HEDERACEÆ.

BIFERÆ *Plantæ*, (from *bis*, twice, and *fero*, to bear); plants that flower twice a year, in ſpring and autumn, as is common between the tropics. *Vide Phil. Bot.* p. 277.

BIFORA *Pericarpia*, (from *bis*, twice; and *fores*, a door); the name of a claſs in Camellus's Method, conſiſting of plants whoſe *pericarpium* or ſeed-veſſel, is furniſhed with two incloſures, termed *valvules*. *Vide* VALVULA.

It is exemplified in celandine, *chelidonium*.

BILOCULARES, (from *bis*, twice, and *loculus*, a little cell); the name of the thirtieth class or family, in Lud. Gerard's Arrangement of the Plants that are natives of Provence

vence in France; conſiſting of theſe genera; jeſſamine, *jaſminum*; privet, *liguſtrum*; the olive, *olea*; ſpeedwell, *veronica*; mock-privet, *phillyrea*; and the aſh-tree, *fraxinus*.

The title of this order would ſeem to import, that the ſeveral genera in queſtion were furniſhed with a ſeed-veſſel divided into two *loculi* or cells; yet, in fact, there are but two genera, jeſſamine, and ſpeedwell, that anſwer this deſcription; the reſt having either a ſeed-veſſel furniſhed with one cell only, as the olive, privet, and mock-privet; or no ſeed-veſſel at all, except the cruſt or tough covering of the ſeed, as the aſh-tree. The plants of this natural family make part of the order *Sepiariæ* of Linnæus; and, except the aſh-tree, are all reduced to the claſs *Diandria*, in the Sexual Syſtem. *Vide* SEPIARIÆ, and DIANDRIA.

BIVASCULARES *Herbæ*, (from *bis*, twice, and *vaſculum*, a little veſſel); the name of the 9th claſs in Hermannus's Method, conſiſting of herbaceous vegetables, which have a ſingle *capſule*, (*Vide* CAPSULA,) or hollow ſeed-veſſel, divided into two *loculi* or cells. *Vide* LOCULAMENTA.

To this claſs belong thorn apple, *datura*; mullein, *verbaſcum*; the tobacco plant, *nicotiana*; water-purſlane, *peplis*; *limeum*, *roella*, *galenia*, *weinmannia*, *cunonia*, *hydrangea*, *heliocarpus*, *curatella*, and many others.

Note, the term *bivaſcularis* is ſynonimous to *bilocularis*, in Linnæus.

BRACHIUM, and BRACHIALIS *Menſura*, the arm; a term of meaſure. *Vide* MENSURA.

BRACTEA, (properly a thin leaf or plate of gold, ſilver, or other metal,) a floral leaf; the name of one of the ſeven *fulcra* or *props* of plants, enumerated by Linnæus, in his *Delineatio Plantæ*, and *Philoſophia Botanica*.

The invention of this term, though claimed by Linnæus, is due to Jungius, who uſes it for the *corolla* of modern botaniſts, including under that name both petals and *nectarium*. *Vide* COROLLA, PETALUM, and NECTARIUM.

In fact, of the numerous terms with which the great reformer of botanical language pretends to have enriched the ſcience, there

there are very few that have not been uſed, either in the ſame, or a different ſenſe, by former writers. Thus, *ſpatha* is as old as Theophraſtus; *germen*, which Linnæus applies to the ſeed-bud, is uſed by Pliny for the buds of the leaves: *involucrum*, is a term of Artedi; *legumen*, *cyma*, and *glandula*, are of great antiquity: *drupa* is to be found in Kyber's Lexicon, publiſhed at Straſbourg, in 8vo. 1553. The terms *arillus*, and *bractea*, are very improper: nor can much be ſaid in favour of *ſcapus* and *pedunculus*. In ſhort, of the ſixteen terms enumerated by Linnæus, as new and neceſſary, there are but five in reality ſuch; viz. *corolla*, *anthera*, *pollen*, *ſtigma*, and *ſtipula*. But this by the way.

The BRACTEÆ, or floral leaves, differ in ſize, ſhape, and colour, from the other leaves of the plant. They are ſituated on the flower-ſtalks, and often ſo near the fructification, as to be confounded with the calyx. Examples of the floral-leaf may be ſeen in the lime-tree, *tilia*; cow-wheat, *melampyrum*; ſage, lavender, *bartſia*, ſome ſpecies of fumatory, *muſſaenda*, *hebenſtretia*, *monarda*, hellebore, fennel-flower, *nigella*; paſſion-flower, *paſſiflora*; wild Syrian rue, *peganum*; bird's-foot, *ornithopus*; ſome ſpecies of French honey-ſuckle, *hedyſarum*; African-broom, *aſpalathus*; milk-wort, *polygala*; reſt-harrow, *ononis*; lady's-finger, *anthyllis*; kidney-bean, *phaſeolus*; baſe tree-trefoil, *cytiſus*; Carolina kidney-bean tree, *glycine*; bird's-foot trefoil, *lotus*; indigo, dragon's-head, *dracocephalum*; and many others.

The floral-leaf is commonly of the ſame duration with the ordinary leaves of the plant; a circumſtance by which, in doubtful caſes, it will be diſtinguiſhed, with great accuracy, from the calyx or flower-cup, which always withers when the fruit is ripe, if not before.

Without attending to this obſervation, we might be apt to commit miſtakes, in aſcertaining ſeveral genera of plants; as hellebore, fennel-flower, paſſion-flower, and others, which have *bracteæ*, but want the calyx.

In point of SIZE and HEIGHT, floral leaves are ſhorter than the flower-cup in ſnap-tree, *juſticia hyſſopifolia*, and *ruellia*

ruellia ringens: longer than the flower-cup in common clary, *ſalvia ſclarea*; *ruellia repens*, and *ſtipa ſpinifex:* larger than the flower-cup, and placed under it, in *royena villoſa:* ſhorter than the flower in ſpotted clary with a ſage leaf, *ſalvia ſylveſtris*; *fumaria nobilis*, and *minuartia campeſtris:* of equal length with the flower, in greater bulbous fumatory with a hollow root, *fumaria bulboſa*; *hypoxis erecta*, and *ornithogalum comoſum:* and longer than the flower in ſweet alpine currant, *ribes alpina*; and *minuartia montana*. *Cunila pulegioides*, beſides a number of ſmaller ones, has two floral leaves larger than the flower, placed on each ſide of the foot-ſtalk.

In reſpect to NUMBER, plants have either one floral leaf: as viſcous field gum ſuccory with ruſhy ſtalks, *chondrilla juncea*; *ariſtolochia piſtolochia*, and *andromeda dabœcia:* two, as *campanula alpina*, *commelina zanonia*, wild-briar, *roſa canina*; *royena villoſa*, *ruellia ringens*, *cineraria ſibirica*, and *hypoxis erecta:* three, as *erica calycina*, and diſtaff-thiſtle with a bellied netted involucrum, *atractylis cancellata:* four or five, as *corymbium ſcabrum:* or ſeveral, as *cunila pulegioides*, *ſtipa ſpinifex*, and many others.

The *bracteæ*, in black-berried upright honey-ſuckle, (*lonicera nigra*,) are compoſed of two dry ſcales, and three broad leſſer leaves.

In crown imperial, lavender, ſome ſpecies of ſage, *ſalvia*; and a few other plants, the flower-ſtem is terminated with a number of very large *bracteæ*, which, from their reſemblance to a buſh of hair, are denominated *coma*, and *bracteæ comoſæ*. *Vide* COMA.

Floral-leaves, particularly thoſe of the buſhy kind juſt mentioned, afford excellent marks of diſtinction in determining the ſpecies; on which account they merit the careful attention of every botaniſt.

BRACTEATÆ, (from *bractea*). The twenty-eighth claſs in Boerhaave's Method, conſiſting of herbaceous vegetables, which have petals, and whoſe ſeeds are furniſhed with a ſingle *cotyledon*, or lobe. *Vide* COTYLEDONES.

The term *bractea*, from which the name of this claſs is manifeſtly

manifeſtly derived, is uſed by Boerhaave, after Jungius, for the *corolla* of modern botaniſts. *Vide* BRACTEA.

This claſs ſtands oppoſed to the twenty-ninth claſs, *apetalæ monocotyledones*, of the ſame author, and is exemplified in the graſſes.

BRUMALES *Plantæ*, (from *bruma*, winter); plants which flower in our winter; common about the Cape. *Vide Phil. Bot.* p. 276.

BULBOSÆ, (from *bulbus*); the name of the ninth claſs in Cæſalpinus's Syſtematic Method, conſiſting of herbaceous vegetables, which have a bulbous root, and a *pericarpium* or ſeed-veſſel, divided into three cells. *Vide* BULBUS.

The tulip, onion, and lilly, furniſh examples.

Bulboſæ, and *bulboſis affines*, are likewiſe the names of the twenty-fourth and twenty-fifth claſſes, in Ray's *Methodus Propria*, publiſhed in the *Philoſophia Botanica*, p. 21.

BULBUS, (Gr. Βολβος, *Bulbus*, *radix quævis rotunda*,) a bulb; a kind of large bud, generally produced under the ground, upon or near the root of certain herbaceous plants, hence denominated bulbous.

A bulb is defined by Linnæus to be a ſpecies of *hybernaculum*, produced upon the deſcending *caudex* or root, conſiſting of *ſtipulæ*, *petioli*, the rudiments of the former leaves, and ſcales of the bark. *Vide* HYBERNACULUM, and CAUDEX.

The obſcurity of this definition, and the great confuſion in botanical terms thence ariſing, render it neceſſary for me to give a more accurate and preciſe idea of the term in queſtion.

For this purpoſe, I would previouſly remark that every bud contains in miniature or embryo, a plant, in every reſpect ſimilar to the parent plant upon which it is ſeated. Plants, therefore, are perpetuated in the buds, as well as in the ſeeds; and the ſpecies may be renewed, with equal efficacy, in either way.

The tender rudiments of the future vegetable, of which the bud is compoſed, are incloſed, and, during the ſeverities of winter, defended from cold and other external injuries,

juries, by a hard bark, or rind, which generally conſiſts of a number of ſcales, placed over each other like tiles, and faſtened together, by means of a tenacious, reſinous, and frequently odoriferous ſubſtance. Thus defended, the buds remain upon different parts of the mother-plant, till the enſuing ſpring; and are, therefore, with great propriety, denominated by Linnæus, the *hybernaculum*, or winter-quarters of the future vegetable.

With reſpect to their place, buds are ſeated either upon the ſtem and branches, or upon the roots: the former are ſtiled *gemmæ*, or buds properly ſo called; the latter bulbs, and ſuckers, *bulbi & turiones*; in French, *oignons & cayeux*. *Vide* GEMMA.

Annual plants, which perform the changes of vegetation but once, can have neither buds, nor bulbs; and are only preſerved in the ſeeds.

Herbaceous perennials, which loſe their ſtems during the winter, can have no *gemmæ*, or buds properly ſo called; but as they ſubſiſt ſeveral years by their roots, may be furniſhed with the other ſpecies of *hybernaculum*, called bulbs, which, according to the definition, are ſeated upon the deſcending *caudex* of the root.

Again, trees which are perennial, with a woody and durable ſtem or trunk, have generally *proper* buds, or *gemmæ*, but no bulbs.

In bulbous plants, as the tulip, onion, and lily, what we ignorantly call the root, is, in fact, a bulb, or *hybernaculum*, which encloſes and ſecures the embryo, or future ſhoot.

At the lower part of this bulb, may be obſerved a fleſhy knob, or tubercle, from which proceed a number of fibres, or threads. This knob, with the fibres attached to and hanging from it, is, properly ſpeaking, the true root; the upper part being only the cradle, or nurſery of the future ſtem, which after the bulb has repaired a certain number of times, it periſhes; but not till it has produced, at its ſides, a number of ſmaller bulbs, termed *turiones*, or *ſuckers*, for perpetuating the ſpecies.

One part of Linnæus's Definition ſtill remains obſcure. The bulb, ſays he, is compoſed of the remains or rudiments of the former leaves of the plant, *è rudimento foliorum præteritorum.*

It is eaſy to comprehend, that buds contain the rudiments of the future leaves; but how can bulbs be ſaid to contain the rudiments of leaves, which, to all appearance, are already periſhed?

To explain this, let it be obſerved, that, in the opinion of eminent botaniſts, the root, in a very great number of perennial herbs, is annually renewed, or repaired out of the trunk, or ſtalk itſelf; in which ſenſe only, roots are properly said to descend.

In the perennials alluded to, the baſis of the ſtalk continually, and by inſenſible degrees, deſcends below the ſurface of the earth, and is thus changed into a true root; which root, by the continuance of the ſaid motion of the ſtalk, alſo deſcends; and thus, according to the durableneſs of its ſubſtance, becomes a ſhorter, or longer root: the elder, or lower part rotting off in proportion as the upper is generated out of the ſtalk. Thus in brownwort, the baſis of the ſtalk, ſinking down by degrees, till it is hid under ground, becomes the upper part of the root; and continuing ſtill to ſink the next year, becomes the lower part, and the following year rots away.

This is exactly what obtains in bulbous roots, as well as in the far greater number of other herbaceous perennials: as arum, valerian, tanzy, brownwort, ſamphire, primroſe, wood ſorrel, iris, and others.

The immediate viſible cauſe of this deſcent, is the ſtring-roots, which this kind of trunks frequently puts forth; which deſcending themſelves directly into the ground, ſerve, like ſo many ropes, for pulling the trunk after them. Hence the tuberous roots of iris are ſometimes obſerved to re-aſcend a little, upon the rotting, or fading away of the ſtring-roots which hang at them.

In bulbous roots, where the ſtalk and former leaves of the plant are ſunk below, and formed into what is called the bulb,

bulb, or wintering of the future vegetable, the radicles, or ſmall fibres that hang from the bulb, are to be conſidered as the root, that is, the part which furniſhes nouriſhment to the plant: the ſeveral rinds and ſhells whereof chiefly the bulb conſiſts, ſucceſſively periſh, and ſhrink up into ſo many dry ſkins, betwixt which, and in their center, are formed other leaves and ſhells; and thus the bulb is perpetuated.

What has been ſaid of the deſcent of roots, by the ſinking of the ſtalk, is further confirmed by the appearance of certain roots; as of valerian, *plantago major*, and devil's bit, (*ſcabioſa ſucciſa*,) in which the lower part appears bitten, or chopped off. In theſe, the lower part rotting off, as the upper deſcends, the living remainder becomes ſtumped, or ſeems bitten.

All bulbous roots, ſays the learned Dr. Grew, in his Anatomy of Plants, may be conſidered as hermaphrodite roots, or root and trunk both together; for the radicles, or ſtrings only, are abſolute roots: the bulb actually containing thoſe parts which, ſpringing up, make the leaves, or body of the plant; ſo that it may be regarded as a great bud under ground.

We enlarged above, upon the deſcent of roots, by the ſinking of the ſtalk, or trunk; and gave evidences of the reality of ſuch an appearance. I ſhall only add to what was then obſerved, another demonſtration of the ſame appearance from the root of a ſpecies of *iris*, called by Grew, *iris tuberoſa*; in which, although the leaves fall off, cloſe to the ſurface of the ſtalk, yet after that is ſunk down, and ſwelled into a root, the ſeats of the periſhed leaves, and the ends of the veſſels belonging to them, become viſible: the whole ſurface of the root appears covered with ſeams and pricked lines; the former exhibiting the ſeats of the leaves; the latter, the terminations or broken ends of the veſſels; which ends are ſtill more apparent, upon ſtripping off the bark.

The deſcent, or ſinking of the ſtalk, may alſo be gathered from the ſimilar poſition and ſtructure of the veſſels, in the root and trunk of certain plants. In ſhort, as among animals, there are many which are not bred of eggs immediately, but

transformed, one into another, as in the caſe of many inſects: ſo it is probable, that, among plants, there are not a few inſtances of the like transformation, whereof this is one.

From what has been ſaid, we may clearly underſtand in what particular way ſome roots become perennial. Thoſe of trees, ſhrubs, and divers other woody plants, are wholly perennial; others are only ſo in part, or by means of a new *progenies* of roots, proceeding from the old head, or body, in the room of thoſe that die yearly, or after a certain time; as the roots of the potatoe, Jeruſalem-artichoke, monks-hood, and others. In like manner, ſtring-roots, or fibrous roots, ſucceed one another annually: ſo that, at the end of many years, what is ſtill looked upon as the ſame individual root, is, in reality, another, as to every particle thereof.

Of bulbs, there are generally reckoned five ſpecies, or kinds.

BULBUS SQUAMATUS, or SQUAMOSUS, a ſcaly bulb, conſiſting of thin plates, or ſcales, laid over one another like tiles, (*lamellæ imbricatæ*); as in the lilly.

BULBUS ARTICULATUS, a jointed bulb, compoſed of ſeveral *lamellæ* or plates, that are cloſely linked together; as in *lathræa*, *adoxa*, and *martynia*.

BULBUS DUPLICATUS, conſiſting of two ſolid bulbs connected together; as in *fritillaria*, and ſome ſpecies of *orchis*. This kind of bulbous root is alſo called *teſticulata*, from its fancied reſemblance to a pair of teſticles.

BULBUS SOLIDUS, a ſolid bulb; compoſed of an entire fleſhy ſubſtance; as in the tulip.

BULBUS TUNICATUS, a coated bulb; conſiſting of ſeveral tunics or coats, cloſely embracing, or infolding each other; as in the onion, *cepa*. This ſpecies of bulb ſtands oppoſed to the former, which is of a ſolid ſubſtance, that is, has no diviſions, or coats.

The coats in queſtion are ſometimes very thick, and ſo ſucculent, that they ſuffice to make the plant vegetate, without the aſſiſtance of earth and water. This is what happens in the officinal plant, *ſcilla maritima*, or ſea-onion; the coated bulbs of which put out their ſtems, and produce flowers,

flowers, without being planted in earth, as they lie in the druggiſts ſhops. The veſſels, with which theſe coats are probably furniſhed, abſorb the humidity from the air, and thus perform the office of the ſmall fibres of the root.

To the five ſpecies of bulbs, already enumerated, may be added a ſixth ſort,

BULBUS CAULINUS, a bulb ſeated upon the ſtem or ſtalk, in oppoſition to all the former ſpecies, which are placed immediately upon the root. Of theſe ſtem-bulbs, we ſhall ſpeak more at large below.

It was obſerved in the definition, that bulbs are frequently produced near the root of certain plants. Such are the ſmall bulbs, called ſuckers; the *ſoboles*, and *turiones*, of ſome writers; the *adnata*, and *adnaſcentia bulbi*, of others. Theſe ſuckers, or off-ſets, which frequently come up with ſurprizing rapidity, are produced from the ſides of the old, or parent bulb, to which they are cloſely connected. Examples may be ſeen in the narciſſus, amaryllis, ſea-daffodil, *pancratium*, and ſeveral others.

Suckers ſerve inſtead of buds to bulbous plants; they renew the ſpecies, and, in ſome meaſure, replace the individual, by developing, or unfolding the plant which they contain in miniature.

This plant, although not viſible by the naked eye, in the ſucker, may be diſtinctly perceived, in the month of January, with the aſſiſtance of a good glaſs, in the center of the bulb.

Suckers begin to be formed on the bulbs, when the ſtalk and other adhering parts are ſupplied with little or no juice from the root; that is, when the plant begins to wither and fade. This, in our climate, happens in autumn; at which time, under-ſhrubs, and perennial herbs, collect on their roots new ſtrength, for the vegetation of the enſuing year.

Thus we have ſeen, that ſuckers, as well as buds, contain the rudiments of a præ-exiſting plant; that their nouriſhment is tranſmitted by the parent-bulb, and that this nouriſhment developes and unfolds their parts, by aſſimilating to their ſubſtance the nutritive juices. Thus unfolded,

the ſucker produces an individual; forms news ſuckers, which, in their turn, produce others; and in this manner multiply the ſpecies, as certainly as the ſeed.

The terms *ſcaly*, *jointed*, *ſolid*, and *coated*, are applicable to ſuckers, as well as bulbs. *Vide ſupra.*

Many plants form productions, which may be compared to *ſuckers*, although they are not, like them, placed near the root. Such are the ſtem-bulbs mentioned above, which, in different plants, are diſpoſed in different parts of the ſtalk, or ſtem.

In tooth-wort, *dentaria*; ſaxifrage; biſtort; *dioſcorea*; ſtar of Bethlehem, *ornithogalum*; fiery-lily, *lilium humile*; and ſome other liliaceous plants, the ſtalks put out bulbs from the wings of the leaves; which, if taken off, when the ſtalks decay, and planted, will quickly take root, and vegetate. Productions of the ſame ſort are obſerved in moſt of the *lichens*, with this difference, that in theſe they are ſeated without the wings of the leaves, *e axilla foliorum*. *Vide* AXILLA.

Such productions in imperfect plants of this kind, are not to be aſcribed, ſays a French writer, to any ſpecies of generation; they are detached portions of their own proper ſubſtance, which, by a ſimple extenſion, and without any regular developement, as in the caſe of germinating from a ſeed, or bud, become, as they enlarge, perfectly ſimilar to the mother-plant.

In ſome ſpecies of garlick, hence denominated *bulbiferous*, bulbs are produced at the origin of the umbel of flowers, between the *pedunculi*, or foot-ſtalks. *Vide* UMBELLA and PEDUNCULUS. Theſe ſmall bulbs are ſometimes among gardeners, known by the name of *cloves*.

An appearance of the ſame kind is obſerved in the flowers of two or three ſpecies of *poa*, hence ſtyled *viviparous*; and in the fruit of a plant of Senegal, called by M. Adanſon, *tangekolli*; the ſeeds of which germinate, and form bulbs or ſuckers, *cayeux*, even before the capſule which contains them has arrived at maturity.

To the head of ſtem-bulbs may be likewiſe referred the fleſhy

fleſhy ſucculent leaves of ſeveral liliaceous plants; as the aloe, and ſea-onion, *ſcilla*; and of ſome ſpecies of *arum*; which being planted in the ground, take root, and vegetate.

Bulbs often afford a real ſpecific difference, and are ſometimes the ſole diſtinction; as in the ſea-onion, *ſcilla*; where the ſpecies are ſcarce to be diſtinguiſhed, but by the difference of the bulbs, which are either *coated*, *ſolid*, or *ſcaly*. *Vide ſupra*.

By their ſituation in the wings of the leaves, and on different parts of the ſtalk, ſtem-bulbs furniſh eſſential marks in ſtar of Bethlehem, tooth-wort, ſaxifrage, biſtort, lily, a few ſpecies of garlick, and ſome other plants.

In drying bulbous plants for uſe, it is neceſſary to ſtrip off the leaves, and expoſe the roots to a ſand heat.

C.

CADUCI, (from *cado*, to fall); the name of a claſs in Linnæus's *Methodus Calycina*, conſiſting of plants whoſe calyx is a ſimple *perianthium*, ſupporting a ſingle flower, or fructification, and falling off either before or with the petals. It ſtands oppoſed to the claſſes *perſiſtentes* in the ſame method, and is exemplified in muſtard, *ſinapi*; and ranunculus.

The term caducous in Botany, is expreſſive of the ſhorteſt period of duration, and has different acceptations, according to the different parts of the plant to which it is applied. A calyx is ſaid to be caducous, which drops at the firſt opening of the petals, or even before, as in poppy, *papaver*, and barren-wort, *epimedium*. Petals are caducous, which are ſcarce unfolded before they fall off, as in meadow-rue, (*thalictrum*); and ſuch leaves have obtained this denomination as fall before the end of ſummer.

From this definition of the term *caducus*, it evidently appears that the above-mentioned claſs in Linnæus's *Methodus Calycina*, includes not only ſuch plants as have a caducous

calyx properly ſo called, but thoſe likewiſe in which the calyx is deciduous, that is, falls off either before or with the petals. *Vide* DECIDUUS *and* PERSISTENS.

CALAMARIÆ, (from *calamus*, a reed); the name of the third order in Linnæus's Fragments of a Natural Method. This order will be eaſily diſtinguiſhed from the family of the graſſes, to which it is nearly allied, by attending to the following particulars. *Vide* GRAMINA.

1. The baſe of the leaf, which embraces the ſtalk like a glove, has no longitudinal aperture in plants of this order, but is perfectly entire.

2. The ſtalk is generally triangular, and without knots, or joints.

3. The flowers have no petals.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Hermaphrodite Plants.

Linnæan Genera.	*Engliſh Names.*
Cyperus, —	— Cypreſs Graſs.
Eriophorum, —	— Cotton Graſs.
Schœnus,	— Baſtard Cypreſs.
Scirpus, —	— Ruſh Graſs.

SECTION II.

Androgynous Plants. (Monoecia.)

Carex.	
Sparganium, —	— Burr-Reed.
Typha, —	— Cat's-Tail, or Reed-Mace.

In the former editions of the Fragments, the genera *Bobartia*, *Flagellaria*, and *Juncus*, made part of this order; they are now very improperly removed into the order *Tripetaloideæ*, which ſee.

Habit

Habit and Structure of the Plants of the Order Calamariæ.

In ſome plants of this natural order, the ROOTS are long and knotty; in others they are compoſed of fleſhy fibres, which pierce deep into the ground; and in others of a bulb.

The STALKS are three-cornered, ſtraight, and have no knots, or joints.

The LEAVES are long, graſſy, frequently three-cornered, and have no *petiolus*, or foot-ſtalk, except the baſe of the leaf, which entirely embraces the ſtem, without any longitudinal aperture, as in the graſſes.

The membrane, and two lateral wings likewiſe, which crown the baſe of the leaf in moſt of the graſſes, are generally wanting in the plants of this natural order.

Exception. The genus *carex* is furniſhed with a ſhort membrane of this kind.

The FLOWERS are either hermaphrodite, as in the firſt ſection: or male and female upon the ſame root, as in the ſecond.

Note.—The female flowers, in ſome ſpecies of *carex*, are produced upon diſtinct roots from the male.

The mode of inflorescence in this order, is generally a SPIKE; *Vide* SPICA. ſometimes a CAPITULUM, or head, as in burr-reed. *Vide* CAPITULUM.

The CALYX, in plants of the firſt ſection, is a *gluma*, or ſcaly huſk; in thoſe of the ſecond, an *amentum*, or catkin. *Vide* GLUMA, and AMENTUM.

The former ſpecies of calyx ſupports a ſingle flower in cypreſs-graſs, ruſh-graſs, and *eriophorum:* the latter in *carex*.

In baſtard-cypreſs; burr-reed, *ſparganium*; and cat's-tail, *typha*; the calyx is common to many flowers.

Some ſpecies of cypreſs-graſs, ſays a French writer, have two abortive, or imperfect flowers, at the bottom of each ſpike; the ſcales of which reſemble the common huſk or calyx, which is generally ſeated under the graſſes. By a ſimilar abortion, continues the ſame author, the genus *ſchœnus* appears to have a common calyx, conſiſting of ſeveral ſcales; whereas, in fact, of the ſix flowers which compoſe

each

each ſpike, the four loweſt proving abortive, leave void the ſpaces between their reſpective ſcales: ſo that the calyx of this plant has been erroneouſly ſuppoſed to conſiſt of ſix or more ſcales, formed into a common *gluma*, or huſk.

The COROLLA, in plants of this order, is wanting.

Exception. The female flowers of the genus *carex* are furniſhed with a *nectarium*, of an oblong figure, ſwelled out like a bladder, contracted above, gaping at the top, bifid, and permanent; the male flowers have neither petals nor *nectarium*.

The genus *ſchœnus*, according to Linnæus, has ſix lance-ſhaped, acute, and permanent petals.

The FILAMENTS of the STAMINA are three in number, ſhort, ſlender like a hair, and ſometimes briſtly.

Some ſpecies of cypreſs, and ruſh-graſs, have only two ſtamina; and Mr. Adanſon mentions a ſpecies of the latter, a native of Senegal, which never produces above one ſtamen.

The ANTHERS, or ſummits, are generally long, ſlender, and erect.

In cat's-tail, *typha*, the ſummits are oblong, and hang down, (*antheræ pendulæ*.)

The SEED-BUD is very ſmall, blunt, and ſometimes three-cornered, as in the *carex*, where it is placed within the *nectarium*.

The STYLE is thread-ſhaped, and of the length of the ſcaly calyx. In cypreſs-graſs, the ſtyle is very long: in *carex*, very ſhort.

The ſummits of the ſtyle, *ſtigmata*, are generally three in number, ſlender, hairy, and ſometimes permanent.

Note.—Cat's-tail has but one *ſtigma*; burr-reed, and ſome ſpecies of cypreſs-graſs, but two: in a ſpecies of ruſh-graſs, Sceuchzerus obſerved four.

Each flower, in plants of this order, is furniſhed with a ſingle *ſeed*, which is generally hairy, three cornered, and without any *pericarpium*, or veſſel.

Note.—In ſuch as have only a ſingle or double *ſtigma*, the ſeeds are not cornered, but oval, or flat.

The *nectarium*, in the genus *carex*, by cheriſhing the ſeed within

within its boſom, ſerves inſtead of a *pericarpium*, or fruit-veſſel.

The virtues, uſes, and ſenſible qualities of this order of plants, are the ſame as thoſe of the graſſes to which it has been always joined by former botanical writers. *Vide* GRAMINA.

The roots of the round and long cypreſs-graſs, were formerly much uſed in medicine. The long is of our own growth, though not very common; the round we have from the Eaſt-Indies. The former, which is properly the *cyperus* of the ſhops, and is called by Tournefort, ſweet-ſcented *cyperus* with a long root, grows by rivulets, and other watery places, as ditches, and the like. The root is knotty, wrapped round with fibrous ſtrings, not eaſy to break, of a brown colour without, and grey within; of a pleaſant ſcent, eſpecially when freſh, and well dried; the leaves are green, and reſemble thoſe of the reed and leek. The latter, ſometimes called Engliſh, or Flemiſh cypreſs, grows in the water, and along banks and river ſides. Its root is as thick as an olive, full of little knots, or ſpecks, of an oblong figure, grey colour, ſweet and ſomewhat ſharp taſte, and almoſt without ſmell, when it is newly taken out of the ground.

The roots of both plants are eſteemed cordial, diuretick, and cephalick, reſiſters of poiſons, and expellers of wind. Long cypreſs is much uſed by perfumers, and glovers.

Fragrant ruſh, or camel's hay, which I take to be a ſpecies of *ſchœnus*, is a kind of reed, or graſs, which grows plentifully in Arabia Felix, and at the foot of Mount Libanus, where it ſerves the people for forage and litter for their camels. The plant is about a foot high, with a ſmall, hard, dry, knotty root, from which proceed ſeveral hard ſtalks, of the ſize, figure, and colour of a barley-ſtraw. The leaves are about half a foot long, narrow, rough, pointed, and of a pale green colour. The flowers are ſmall, hairy, of a carnation colour, agreeable to the eye, and of a warm, biting, aromatick taſte. All the plant, but eſpecially the flower, is uſed in medicine. It is reckoned attenuating, deterſive, diuretic,

diuretic, and vulnerary: but its principal uſe, at preſent, is as an ingredient in the Venice treacle.

Long-rooted baſtard cypreſs, the *ſchœnus mariſcus* of Linnæus, ſerves, in Gothland and other parts of Sweden, for thatching, inſtead of ſtraw, and often grows in ſuch quantities in pools, as to form floating iſlands. *Vide* LINNÆI ITER GOTLANDICUM.

It is obſerved by Pennant, in his Tour to the Hebrides, that, in the Iſle of Sky, many-headed cotton-graſs (*eriophorum polystachion*,) is uſed by the inhabitants to ſupport their cattle in the earlier part of the ſpring, before the other graſſes are ſufficiently grown. The poorer ſort, in Sweden, ſtuff their pillows with the down, cotton, or wool, which ſurrounds the ſeeds, and gives name to the genus; of which likewiſe they make wicks of candles: but for this purpoſe it is the leſs proper, as being apt to become brittle when dry.

The Laplanders, ſays Linnæus, in his *Flora Lapponica*, put the dried and carded leaves of the bladder-carex (*carex veſicaria*) into their ſhoes, to repel the cold in winter, and in the heats of ſummer, to prevent exceſſive perſpiration. In Italy and Germany, obſerves Micheli, in his *Novæ Genera Plantarum*, the leaves of the ſame ſpecies of *carex* are uſed by different artificers, as glaſs-makers and ſadlers, for various purpoſes, but eſpecially by coopers, for ſtopping the chinks, and cloſing the joinings of their caſks.

With bull-ruſh *ſcirpus*, the *ſcirpus lacuſtris* of Linnæus, cottages are thatched, pack-ſaddles ſtuffed, and, in want of more ſubſtantial nouriſhment, cattle are ſometimes fed with it. *Lin. Flor. Suec.* p. 16. Mats, and bottoms of chairs too, are very commonly made of this ruſh. If cut at one year old, it makes the fine bottoms; coarſe bottoms are made of it at two years old; and thoſe that are ſtill older, mixed with the leaves of the yellow flag, (*Iris pſeud-acorus*), make the coarſeſt bottoms of all. *Withering*, vol. 1.

CALCAR *Corollæ*, the ſpur of the corolla. The *nectarium* ſo called, which terminates the corolla behind, like a cock's

cock's-ſpur, in calve's-ſnout; valerian; orchis; violet; balſam, *impatiens*; lark-ſpur, *delphinium*; fumatory; butter-wort, *pinguicula*: and water-milfoil, *utricularia*. *Vide* NECTARIUM, and *Phil. Bot.* p. 73.

CALENDARIUM *Floræ*, a calendar; containing an exact regiſter of the reſpective times, in which the plants of any given province, or climate, germinate, expand, and ſhed their leaves and flowers, and ripen and diſperſe their ſeeds. *Vide Phil. Bot.* p. 276.

For particulars, on this curious ſubject, we refer the reader to the articles DEFOLIATIO, EFFLORESCENTIA, FRONDESCENTIA, FRUCTESCENTIA, and GERMINATIO.

CALIDÆ *Plantæ*, (from *calor*, heat); plants that are natives of warm climates. Such are thoſe of the Eaſt-Indies, South-America, Egypt, and the Canary iſlands.

Theſe plants, ſays Linnæus, will bear a degree of heat, which is as 40, on a ſcale, in which 0 is the freezing point, and 100 the heat of boiling-water. In the 10th degree of cold, they ceaſe to grow, loſe their leaves, become barren, are ſuffocated, and periſh. *Vide Phil. Bot.* p. 277.

CALOR, *heat*. In aſſimilating the vegetable with the animal kingdom, Linnæus terms heat the *heart* of Plants, *cor plantarum*. *Vide Phil. Bot.* p. 93.

"*Cor* plantis nullum, ſed calor efficit omne: nec opus eſt corde, ubi nec perpetui mobilis effectus neceſſarius eſt, & ubi propulſio, non circulatio humorum."

CALYCANTHEMÆ, (from calyx, the flower-cup; and ἄνθος, the flower); the name of the ſeventeenth order, in Linnæus's Fragments of a Natural Method, conſiſting of plants, which, among other characters, have the corolla and ſtamina inſerted into the calyx.

Liſt of Genera *contained in this Natural Order.*

SECTION I.

Plants having the Receptacle of the Flower, *placed upon the fruit.*

Linnæan Genera.	*Engliſh Names.*
Epilobium, — —	Willow-Herb, or French Willow.

Gaura,

Linnæan Genera.			*Engliſh Names.*
Gaura,	—	—	Virginian looſe-ſtrife.
Iſnardia.			
Juſſiæa.			
Ludvigia.			
Melaſtoma,	—	—	American Gooſeberry-tree.
Mentzelia.			
Oenothera,	—	—	Tree Primroſe.

SECTION II.

Plants having the fruit (Germen) *placed upon the* Receptacle of the Flower.

Ammannia.			
Frankenia.			
Glaux,	—	—	Sea-chickweed, or Milk-wort, and Black Salt-wort.
Griſlea.			
Lythrum,	—	—	Willow-Herb, or Purple looſe ſtrife.
Oſbeckia.			
Peplis,	—	—	Water Purſlane.
Rhexia.			

Habit and Structure of the Plants of the Order Calycanthemæ.

This order furniſhes trees, ſhrubs, and annual, biennial and perennial herbs. The herbaceous annuals are by much the moſt numerous.

The ROOTS are branched and fibrous.

The STEMS and BRANCHES, cylindric.

In plants of the laſt ſection, the branches are generally oppoſite; in thoſe of the firſt, alternate.

They are ſquare, or four-cornered, when young, in both.

Note.—Such genera of the firſt ſection as have oppoſite leaves, have likewiſe oppoſite branches.

The BUDS are of a conic form, and without ſcales.

The LEAVES, in plants of the firſt ſection, are generally alternate, ſimple, and attached to the branches by a ſhort foot-ſtalk. In American gooſeberry-tree, they are oppoſite: and in French-willow, *epilobium*, oppoſite and alternate upon the ſame branch.

In all the plants of the laſt ſection, the leaves are oppoſite at the bottom of the ſtem; and in ſome, alternate towards the top. They are univerſally ſeſſile; that is, attached to the branches without any foot-ſtalk.

The MARGIN of the leaves in tree-primroſe, *ænothera*; ſea-milkwort, *glaux*; and French-willow, inſtead of indentments, has a number of ſmall grains, or white tubercles, which are not perceptible, without cloſe examination.

At the origin of the foot-ſtalk of the leaves, in *ludvigia*, *juſſiæa*, and ſome other genera of the firſt ſection, are diſcovered two ſmall ſcales in the form of *Stipulæ*, attached to the young branches.

The FLOWERS are univerſally hermaphrodite; growing oppoſite in ſuch as have the leaves oppoſite, from the wings of which they generally proceed.

In French willow, the flowers are attached to the foot-ſtalk of the leaves, as they are likewiſe in *turnera*, and a ſpecies of althæa frutex, *hibiſcus*; which do not belong to this natural family.—The modes of infloreſcence in this order of plants, are a *ſpike*, *corymbus*, and *racemus*. *Vide* SPICA, &c.

The CALYX is univerſally a *perianthium*, and generally monophyllous, that is, compoſed of one leaf.

In French-willow, it conſiſts of four diſtinct leaves; and in *mentzelia*, of five.

The ſegments, *laciniæ*, of the limb, or upper part of the calyx, are different in point of number and diviſion. In *oſbeckia*; tree-primroſe, *ænothera*; Virginian looſe-ſtrife, and *ludvigia*, it is deeply divided; in *rhexia*, *iſnardia*, and *griſlea*, more ſlightly cut, into four: in *frankenia*, and American gooſe-berry tree, it is marked with five indentments, or teeth; in *ammannia*, with eight; in water-purſlane, and purple looſe-ſtrife, with twelve.

The calyx, in plants of the firſt ſection, is placed upon the germen, or ſeed bud; the upper part falls off with the petals; the lower is permanent, and in fact, continuous with the *germen*.

In plants of the ſecond ſection, the calyx is permanent,

and

mouth of a deep black, that the generical name *Melaſtoma*, that is, black mouth, is derived.

CALYCIFLORÆ, (from *calyx*, the flower-cup, and *flos*, the flower); the ſixteenth order in Linnæus's Fragments of a Natural Method, conſiſting of plants which, as the title imports, have the ſtamina (the flower) inſerted into the calyx.

This order differs from the former, which has a title of the ſame import, in the following particulars.

1. The plants of this order want the corolla.

2. With reſpect to their ſex, the flowers are either hermaphrodite and male upon the ſame root, *polygamia*; or male and female upon different roots.

3. The ſeed-veſſel is pulpy, of the berry, or cherry-kind, and contains a ſingle ſeed or ſtone.

The Order Calycifloræ *contains but four Genera:* viz.

Linnæan Genera.			*Engliſh Names.*
Elæagnus,	—	—	Oleaſter, or Wild-olive.
Hippophae,	—	—	Baſtard-Rhamnus, or Sea-Buckthorn.
Oſyris,	—	—	Poet's-Caſia.
Trophis.			

The laſt Genus is only to be found in the improved Editions of the Fragments.

Habit and Structure of the Plants of this Order.

All the plants of this order are of the ſhrub and tree kind. Some of them riſe to the height of twelve or fourteen feet, as the wild olive; others to not above two or three, as poet's caſia.

The ROOTS are branched, fibrous, and woody.

The STEMS are cylindric.

The BRANCHES, when young, are cornered.

The BUDS are of a conic form, and without ſcales.

The LEAVES are ſimple, alternate, and attached to the branches by a very ſhort foot-ſtalk.

The

The FLOWERS are male and female upon diſtinct roots, in the three laſt genera; hermaphrodite and male upon the ſame root, in wild olive, *elæagnus*; where two male flowers are produced by the ſide of an hermaphrodite flower, at each wing, or angle of the leaves.

Note.—Linnæus, not attending to this circumſtance, places *elæagnus*, in the firſt order of his claſs *tetrandria*; which, according to his plan, ſhould conſiſt only of hermaphrodite flowers.

The CALYX, in this order, is a *perianthium*, which is compoſed of one leaf, divided into two ſegments, in ſea buck-thorn; into three in poet's caſia; and into four in wild olive. It is commonly placed upon the *germen*, which it accompanies to maturity.

Note.—The male plants of the genus *trophis*, have no calyx.

The COROLLA, in plants of this order, is univerſally wanting, except in *trophis*, the male plants of which, according to Linnæus, have four obtuſe and ſpreading petals.

The STAMINA are generally four in number, ſlender like a hair, ſhort, placed at a conſiderable diſtance from the ſtyle, and inſerted into the tube of the calyx.

Poet's caſia has only three ſtamina, which are oppoſite to the diviſions of the calyx.

The PISTILLUM is compoſed of a roundiſh *germen*, crowned with the calyx; a ſingle thread-ſhaped *ſtyle*; and a cylindric *ſtigma*, which, in poet's caſia, is deeply divided in three.

The SEED-VESSEL in the firſt genus, *elæagnus*, is an obtuſe, oval fruit, of the cherry kind (*drupa*,) with a puncture at the top, incloſing an oblong, obtuſe nut; in the three other genera, a globular berry, (*bacca*,) with one cell, containing a roundiſh ſeed.

In poet's caſia, the ſeed is hard like a ſtone, and fills the whole cavity of the *pericarpium*.

The plants of this order are aſtringent.

From the odoriferous flowers of the wild-olive is drawn an aromatick and cordial liquor, which has been ſucceſsfully uſed in putrid and peſtilential fevers.

Sea buck-thorn is purgative; poet's caſia, highly aſtringent.

The name *elæagnus* is derived from Ἐλαία, an olive, and Ἄγνος, *vitex*; becauſe the plant hath leaves like thoſe of the chaſte-tree, *vitex agnus caſtus*, and a fruit like an olive.

The yellow flowers of the oleaſter or wild olive of Boemia, *elæagnus anguſtifolia*, emit a ſtrong, agreeable ſcent, when fully expanded; from which circumſtance, ſays Mr. Duhamel, the Portugueze have given the name of *tree of Paradiſe* to this plant.

The genus *elæagnus*, is not to be confounded with the oleaſter or wild olive of Parkinſon, Gerard, and Ray. This laſt is only a particular ſpecies of olive, called by Tournefort and Caſpar Bauhin, *olea ſylveſtris*, and deſcribed to have a hard leaf, which is hoary on its under ſide. It grows naturally in woods, in the ſouth of France, Spain, and Italy, and is never cultivated.

The wild olive, *elæagnus*, is ſaid to poſſeſs the ſame virtues as the olive-tree. *Vide* SEPIARIÆ.

In *elæagnus latifolia*, which grows naturally in the iſland of Ceylon, and ſome other parts of India, the leaves continue green all the year.

The berries of baſtard rhamnus, or common ſallow-thorn, as it is ſometimes called, obſerves Linnæus, in his *Flora Suecica*, dye yellow. They are exceedingly acid, and by the fiſhermen of Aland, one of the Swediſh iſlands, prepared into an embamma, or ſauce, which gives to their fiſh a very agreeable ſavour. The ſhrub flowers in the early part of the ſpring, before it puts forth leaves, and in a ſandy ſituation, that is expoſed to the ſun, is uſed for hedges.

The berries of the genus *trophis* are eſculent.

CALYCIFLORÆ, is likewiſe the name of the eleventh claſs in Royen's Natural Method; and of the forty-eighth order in Lud. Gerard's Arrangement of the Plants that are natives of Provence, in France. In Royen's Method it is a very extenſive claſs, comprehending all plants which have the filaments of the *ſtamina* inſerted into the *perianthium*. It exactly

exactly correſponds to the claſs *Floribundi*, in Linnæus's *Methodus Calycina*; and, beſides the claſs *Icoſandria*, in the ſexual method, includes the orders *Calycanthemæ*, and *Calycifloræ*, which have been analyſed above. *Vide* FLORIBUNDI, and ICOSANDRIA.

In Lud. Gerard's Method, the order *calycifloræ* is the ſame as in Linnæus.

CALYCINI, (from *calyx*, the flower-cup); the name of the ſixteenth claſs in Wachendorffius's Natural Method, conſiſting of plants with viſible flowers, which have a flower-cup, and whoſe ſeeds are furniſhed with a ſingle *cotyledon*, or lobe. *Vide* COTYLEDONES. It is exemplified in ruſh, *eriophorum*, and *cynomorium*.

CALYCISTÆ, (from *calyx*, the flower-cup). Syſtematic botaniſts ſo termed by Linnæus, who have arranged all vegetables from the different ſpecies, ſtructure, and other circumſtances of the calyx, or flower-cup.

The only ſyſtems of this kind are the *Character Plantarum novus*, a poſthumous work of Magnolius, profeſſor of botany at Montpelier, publiſhed in 1720; and Linnæus's *Methodus Calycina*, publiſhed in his claſſes *Plantarum*, at Leyden, in 1738.

By the *internal calyx*, in Magnolius's Method, is meant the *pericarpium*, or ſeed-veſſel.

CALYPTRA, (from καλυπτω, *tego*, to cover); a veil, or covering; one of the ſeven ſpecies of *calyx*, enumerated in the *Philoſophia Botanica*, and defined to be the proper calyx of the moſſes. It is placed over the *anthers* or ſummits, and in figure reſembles an extinguiſher, hood, or monk's cowl. *Vide* MUSCI.

The term was firſt uſed in this ſenſe, by Dillenius, to whom we owe the principal diſcoveries that have been made in the moſs, muſhroom, and *lichen* tribes.

The *Calyptra* is either

Acuminata, pointed, as in *minium*, and *bryum*.

Caduca, falling off early, and before the burſting of the anthers, as in *buxbaumia*.

Conica, of a conic form, as in moſt moſſes.

Glabra, ſmooth and ſhining, as in *hypnum*.

Lævis, poliſhed, without any inequalities, as in *ſplachnum*.

Oblonga, of an oblong figure, as in *minium*.

Villoſa, hairy, or ſhaggy, as in golden maiden-hair, *polytrichum*.

In ſome genera, as *lycopodium*, *porella*, *ſphagnum*, and *phaſcum*, the *calyptra* is wanting.

CALYPTRA, by Tournefort, and former botaniſts, was uſed to ſignify the proper exterior covering or coat of the ſeed, which falls off ſpontaneouſly. *Vide* ARILLUS.

CALYPTRATI, (from *calyptra*) the name of one of the principal diviſions in Dillenius's Arrangement of the Moſſes; containing ſuch of thoſe imperfect plants as are furniſhed with the ſmall membranaceous calyx called *calyptra*. *Vide* CALYPTRA.

This claſs, which is exemplified in water-moſs, *fontinalis*; and golden maiden-hair, *polytrichum*; ſtands oppoſed to the claſs or diviſion *Calyptra Deſtituti*, moſſes wanting the *calyptra*, of the ſame author. *Vide* MUSCI.

CALYX, (Gr. Καλυξ, a Καλυπτω, *tego—calyx, roſa clauſa, theca, vel cui aliquid includitur ut folliculus, putamen*, &c. —properly the bottom of a roſe-bud not fully blown). The outer covering of the flower, commonly called the flower-cup, which, in the greater number of plants, incloſes and ſupports the bottom of the *corolla*. *Vide* COROLLA.

It is defined by Linnæus to be the termination of the *cortical epidermis*, or outer bark of the plant, which, after accompanying the trunk, or ſtem, through all its branches, breaks out with the flower, and is preſent in the fructification, in this new form.

I am not, at preſent, to enquire into the propriety of a definition, which, by the way, contains neither the deſcription nor uſe of the part in queſtion: but only mean to oppoſe to the opinion contained in it, that of a very learned naturaliſt of the laſt century, Dr. Nehemiah Grew, who,

in

in his Anatomy of Plants, a moſt ingenious and elaborate work, thus expreſſes himſelf, with regard to the origin of the flower-cup. "The impalement, (*calyx*), whether of one or more pieces, I call that which is the outmoſt part of the flower, encompaſſing the other two; *viz.* the foliation, (*Corolla* of Linnæus) and the attire, (*Stamina* and *Piſtillum*). It is compounded of the three general parts, the ſkin, the cortical and lignous bodies; as is evident from the artichoke, in which the continuation of all theſe parts is clearly diſcoverable; the empalers being of that amplitude, as fairly to ſhew them all." *Grew's Anatomy of Plants*, p. 35.

By former botaniſts, the term *calyx* is always uſed in its proper and reſtricted ſenſe, as expreſſed above, and correſponds, therefore, to what, in the modern ſyſtems, is denominated *perianthium*.

By Linnæus, the reformer of botanical language, it is employed with much more latitude, as a generical term, comprehending the ſeven following ſpecies.

1. Perianthium, *Calyx* of Tournefort and others.
2. Involucrum.
3. Amentum, *Julus* of Tournefort.
4. Spatha.
5. Gluma, *Locuſta* of Ray.
6. Calyptra.
7. Volva.

Theſe different appellations of the calyx, for they are no other, depend upon circumſtances, which will be explained under each particular term. At preſent we may obſerve, that of the ſeven ſpecies above enumerated, the firſt, *perianthium*, is by much the moſt common; an *involucrum*, is almoſt peculiar to umbelliferous flowers; *gluma*, to the graſſes; *amentum*, to another order of plants; *calyptra*, to moſſes; and *volva*, to muſhrooms. When we ſpeak, therefore, of the proportion, figure, ſituation, or ſingularities of the *calyx*, we would always be underſtood to mean, that ſpecies of calyx called *perianthium*. The other ſpecies, which differ remarkably both in appearance and ſtructure

from the firſt, are always denominated by their own proper names; that no confuſion, amidſt ſuch a diverſity of terms, may ariſe.

CALYX, then, being a general or generical term, and uſed, even when employed as a particular ſpecies, for the *perianthium*, it was thought proper to refer to that head the ſtructure, and ſingularities of this firſt part of the fructification. *Vide* PERIANTHIUM.

General Remarks.

1. Malpighi's, Ray's, Tournefort's, and Ludwig's Definition of the calyx, is applicable only to the *perianthium* of Linnæus.

2. The calyx is of a coarſer ſubſtance, and thicker than the corolla.

3. The leaves of the calyx are generally green; thoſe of the corolla coloured.

4. Notwithſtanding ſuch eſſential differences, nature ſeems to have put no abſolute limits between theſe parts of fructification; for in many plants, as *bartſia*, the calyx, or *perianthium*, is deeply coloured; and there are many flowers,—hellebore, and ſtar of Bethlehem, for inſtance,—which, having a coloured *corolla*, and no calyx, are ſubject to loſe their petals, about the time of flowering: but theſe afterwards hardening, turn green, and remain on the plant like a calyx.

In *daphnis*, the calyx and corolla are joined together, and united in the margin like a leaf of box. *Lin. Phil. Bot.* p. 58.

Burning thorny plant, or ſpurge, *euphorbia*, has been often erroneouſly deſcribed as monopetalous, by thoſe who have miſtaken the *calyx* for the *corolla*.

A more ſure mark of diſtinction betwixt the calyx and corolla, in doubtful caſes, is given under the article COROLLA, which ſee.

5. Both calyx and corolla are ſometimes ſtyled by Linnæus, the covers of the flower, *tegumenta floris*. Ludwig calls them by another name, of the ſame import, *involucra*.

6. In eſtabliſhing the analogy betwixt the animal and vegetable

vegetable kingdoms, Linnæus has diſtinguiſhed the calyx by the name of *thalamus floris*, or the conjugal bed.

7. The calyx, in the language of Tournefort, becomes the fruit, when the *receptacle* of the flower is placed upon the *germen*; which has, for its *receptacle*, the *extremity of the pedunculus* or foot-ſtalk, to which it is attached. This deſcription correſponds to the *germen inferum*, or *flos ſuperus* of Linnæus, and is exemplified in campanula, madder, lady's bed ſtraw, cucumber, marvel of Peru, valerian, and the umbelliferous flowers.

8. For a ſure method of diſtinguiſhing the calyx from a *bractea*, or floral-leaf, with which it is frequently confounded, ſee the article BRACTEA.

9. The following quotation, from Alſton's *Tyrocinium Botanicum*, publiſhed at Edinburgh, in 1753, will give the reader a juſt idea of the proportion that obtains in point of number, betwixt the ſeveral ſpecies of calyx above enumerated. The *Genera Plantarum* at that time contained only 1021 genera. Of theſe, ſays Dr. Alſton, 673 have a *perianthium* for their calyx; 72 a *ſpatha*; 75 an *involucrum*; 29 a *gluma*; 18 an *amentum*; and 3 a *calyptra*. *Volva*, though deſcribed in the *Phil. Bot.* to be the membranaceous calyx of the muſhrooms, yet, in fact, is never once mentioned in the *Genera Plantarum*, among the characters of the 11 genera of that kind of Imperfect plants there enumerated. About 110, he continues, want the calyx altogether; 25 have both a *perianthium* and *involucrum*; and a few plants have both a *perianthium* and *ſpatha*. Beſides, in *eriophorum*, *xyris*, cypreſs-graſs, *cyperus*: and ruſh-graſs, *ſcirpus*; the *ſpike* is a calyx: in *morinda*, and ſea-holly, *eryngium*; the *common receptacle*.

10. The deſign of the empalement, (*calyx*) ſays Grew, is to incloſe, ſecure, and ſupport the other parts of the flower; to be their ſecurity before its opening, by intercepting all extremities of weather; and afterwards to be their ſupport, by containing all the parts in their due, and moſt graceful poſture.

Hence, continues the ſame author, we have the reaſon, why the calyx is frequently various, and ſometimes wanting.

Some

Some flowers have none, as tulips; becauſe, having a fat and firm leaf, (*petalum*;) and each leaf, likewiſe ſtanding on a broad and ſtrong baſis, they are thus ſufficient to themſelves. Carnations, (*dianthus*,) on the contrary, have not only an empalement, but that, for greater ſupport, of one piece: for, otherwiſe, the foot of each leaf, or petal, being very long and ſlender, moſt of them would be apt to break out of compaſs. In the ſame flower, the top of the empalement is indented; that the indentments may protect the petals, by being lapped over them before their expanſion, and afterwards may ſupport and prop them up, by being ſpread under them.

CAMPANACEÆ, (from *campana*, a bell); bell-ſhaped flowers. The name of the twenty-ninth order, in Linnæus's Fragments of a Natural Method.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Bell-ſhaped Flowers, with diſtinct Anthers or Summits.

Linnæan Genera.			*Engliſh Names.*
Campanula,	—	—	Bell-Flower.
Convolvulus,	—	—	Bindweed.
Evolvulus.			
Ipomoea,	—	—	Quamoclit, or Scarlet Convolvulus.
Phyteuma,	—	—	Rampions.
Polemonium,	—	—	Greek Valerian, or Jacob's Ladder.
Röella.			
Trachelium,	—	—	Blue umbelliferous Throatwort.

SECTION II.

Bell-ſhaped Flowers, with Anthers united into a Cylinder.
(Syngeneſia.)

Jaſione,	—	—	Rampions with ſcabious heads, or ſheep-ſcabious.
Lobelia,	—	—	Cardinal Flower.

Linnæan Genera.			*Engliſh Names.*
Viola,	—	—	Violet, or Heart's-eaſe.

Habit and Structure of the Plants of this Natural Order.

The plants of this order are generally herbaceous, and perennial. Some of the bell-flowers and bindweeds are annual; and a few foreign ſpecies of the latter have woody ſtalks.

The ROOTS are either ſpindle-ſhaped, as in bell-flowers and rampions; or branched and fibrous, as in convolvulus.

The STEMS are round, and, in convolvulus, twiſted, in a direction oppoſite to the diurnal motion of the ſun.

The BRANCHES are generally alternate.

The LEAVES are ſimple, alternate, and commonly attached to the branches by a ſemi-cylindric foot-ſtalk, which is furrowed above. The indentments are terminated by a ſmall white tubercle or knob, which renders them conſpicuous.

Note, in ſome ſpecies of *lobelia*, the leaves are oppoſite.

The FLOWERS are hermaphrodite, and proceed either ſolitary from the wings of the leaves, or are collected into a ſpike and head, at the end of the flower-ſtalk. In ſome ſpecies of *campanula*, they grow out of the angle formed by the ſtem and branch.

The CALYX, in this order, is univerſally a perianthium, ſituated upon, or round the *germen*, and generally compoſed of one leaf deeply divided into five ſegments. In *evolvulus*, and violet, it conſiſts of five diſtinct leaves; the common calyx, in ſheep-ſcabious, *jaſione*, is compoſed of a like number.

The COROLLA, is monopetalous, and of the bell, funnel, or wheel ſhape. Umbelliferous throat-wort, *jaſione*, and the violet, have five diſtinct petals, which, in the laſt, are unequal.

The TUBE, in flowers of the bell and wheel ſhape, is very ſhort; in thoſe of the funnel ſhape very long. In Greek valerian, the tube is ſhut with five valves, which are placed on its *apex*.

The LIMB, or upper part of the *corolla*, is deeply divided

into

into five ſegments, which ſpread, and are alternate with the diviſions of the calyx.

In ſome ſpecies of *campanula*, as Venus's looking-glaſs, the *corolla* is very ſmall; and in others, becomes almoſt inſenſible. In convolvulus, it is beautifully plaited.

The *Corolla* in this order, is generally permanent; that is, accompanies the ſeed-bud to its maturity.

Bell-flower, *roella*, and the violet, are furniſhed with a NECTARIUM, which, in the two former, conſiſts of five ſcales placed in the bottom of the petal; in the violet, of a ſubſtance, which, in figure, reſembles a horn, or cock's ſpur, and terminates the upper petal of the *corolla*. *Vide* CALCAR.

The STAMINA are five in number, attached to the baſe of the tube of the corolla, alternate with its diviſions, and oppoſite to thoſe of the calyx. In bell-flower, and *roella*, the ſtamina are inſerted into the nectarium; and in Greek-valerian, into the valves of the tube.

The FILAMENTS, or threads, are diſtinct, very large at their origin, and frequently approach, ſo as to form a ſort of vault, which covers the ſummit of the *germen*. They are ſlender and awl-ſhaped above.

The ANTHERS, or ſummits, are very long, oval, marked with four longitudinal furrows, and either diſtinct, as in the firſt ſection; or united in a cylinder, as in the ſecond.

The POLLEN, or male-duſt, is compoſed of very ſmall, ſpherical, white, ſhining, and tranſparent particles.

The GERMEN, or ſeed-bud, is roundiſh, and ſituated, either wholly, or in part, under the flower.

The STYLE is generally ſingle, and of the length of the *ſtamina*, or *corolla*.

Note, the genus *evolvulus* has four ſtyles.

The STIGMA, or top of the ſtyle, is commonly ſingle, but deeply divided, as in bell-flower, Greek valerian, and rampions, *phyteuma*. Convolvulus, and *roella*, have a double ſtigma.

The SEED VESSEL is a roundiſh capſule, generally divided into three cells, and furniſhed externally with the ſame number of valves.

Note.

Note. The capſule of the violet conſiſts of only one cell: that of *roella*, *jaſione*, and *lobelia*, of two.

The figure of the ſeed-veſſel in the genus *campanula*, is exceedingly diverſified. In nettle leaved bell-flower, *campanula trachelium*, it is hairy, rough with knots, and divided into three cells. In *campanula rapunculus*, ſmooth, and egg-ſhaped; in Canterbury bell-flower, *campanula Medium*, furniſhed with five cells, and the ſame number of valves; and in Venus's looking-glaſs, priſm-ſhaped, with three cells.

The SEEDS are ſmall, numerous, attached to a receptacle in the center of the fruit, generally rounded, and ſometimes cornered.

The plants of this order abound with a white milky juice, which, upon the ſtalk being cut, flows out in great quantities. *Vide* LACTESCENTIA.

The roots and leaves of *campanula rapunculus*, (rampion,) are preſcribed, in decoction, for diſorders of the wind-pipe. They are much cultivated in France for ſallads; as they were in this country ſome years ago, though now almoſt univerſally neglected.

A decoction of the roots of a ſpecies of American *lobelia*, which Moriſon deſcribes under the name of *rapunculus galeatus Virginianus, flore violaceo majore*, is ſaid to cure the moſt inveterate venereal diſorders, in the ſhort ſpace of ten, or fifteen days.

Beſides thoſe already mentioned, and many others, this natural order furniſhes the following excellent medicines: ſcammony, turbeth, and jalap.

SCAMMONY is the inſpiſſated juice of the roots of a ſpecies of bind-weed, called by Tournefort, *Convolvulus Syriacus*, and *Scammonia Syriaca*; by Linnæus and Miller, *Convolvulus Scammonia*, Syrian bind-weed, and Syrian ſcammony.

This plant, which grows naturally in Syria, and the Levant, bears green leaves, almoſt in the ſhape of an heart, or nearly approaching to thoſe of ivy. The flowers are white, and of a bell-figure. The branches extend themſelves

ſelves on every ſide, to the diſtance of four or five feet: they are ſlender, and trail on the ground, if not properly ſupported. The plant is hardy, and will thrive very well in the open air in England, provided it is placed in a dry ſoil.

To procure the drug in queſtion, inciſions are made into the roots of the plant, and ſhells placed under the wounds, to receive the milky juice which flows out. This juice is then thickened by means of fire; and afterwards put up in cods, or lumps, for exportation.

The beſt ſcammony comes from Aleppo, and St. John d'Acre. It is light, grey, tender, brittle, reſinous, grinds to a grey powder, of a bitter taſte, and faint, unpleaſant ſmell. That which is heavy, hard, and black, is to be rejected, and is, in fact, either the juice of the whole plant, or what has been burnt, and otherwiſe damaged in the operation of thickening.

This concreted juice, which, by the way, is frequently ſophiſticated, is reckoned one of the ſtrongeſt purgatives, and is therefore never given without a corrector. In weak habits, it is apt to occaſion irritations, and even inflammations; and therefore ought never to be adminiſtered when there is the leaſt ſuſpicion of inflammation in any part of the *abdomen*. It is likewiſe a very uncertain purge, ſometimes not operating at all; at other times cauſing fatal ſuperpurgations: and, what is very remarkable, it often does not operate at all the firſt day, but brings on afterwards an inſupportable purging, followed by that violent inclination, called by phyſicians, *Teneſmus*.

Scammony admits of various preparations. Theſe are the moſt common: 1. *Diagrydium*, or ſcammony prepared, and corrected with the juice of quinces. This is a very proper ingredient in the *Pulvis Cornachini*, which has all the virtues of ſcammony, without any of its bad effects. 2. Scammony ſulphurated. 3. Scammony vitriolated. 4. Extract of Diagrydium. 5. Extract of Scammony. 6. Syrup of Scammony.

All the preparations of this juice, ſays Pomet, in his Hiſtory

Hiſtory of Drugs, are prevalent againſt old contumacious diſeaſes; ſuch as gout, ſcurvy, dropſy, rheumatiſm, obſtructions, head-achs, apoplexies, and remains of the venereal diſeaſe.

Beſides the Aleppo ſcammony, there are two other ſorts, commonly ſold by the names of Smyrna and Indian ſcammony. The former is black, heavy, full of ſtones, ſhells and other extraneous matter; the latter grey, light, and brittle; and diſcovered, by minute examination, to be a compoſition of ſome very ſtrong purgative powders made up of roſin.

TURBITH is a ſpecies of bind-weed, called by Ray, *Convolvulus Indicus, Alatus, Maximus, foliis Hibiſco nonnihil ſimilibus, angulosis*; and by Linnæus, and Miller, *Convolvulus Turpethum*, turbith of the ſhops; it is deſcribed to have angular heart-ſhaped leaves, a quadrangular membranaceous ſtalk, and foot-ſtalks which ſupport many flowers.

The plant grows naturally in Ceylon and Malabar, in the Eaſt Indies. It is perennial, having thick fleſhy roots, which ſpread far in the earth, and abound with a milky juice, that flows out when the roots are broken or wounded; and ſoon hardens into a gummy ſubſtance, when expoſed to the ſun and air. From the root ſhoot forth many twining branches, which twiſt about each other, or the neighbouring plants, like the common bind-weed; the leaves and flowers reſemble thoſe of the marſh-mallow. The roots of this plant, the only part uſed in medicine, are brought to us from India, by the name of turpethum, and turbith.

Turbith, ſay writers on the *Materia Medica*, is a pretty ſtrong cathartic; purging tough ſerous humours from the remote parts, and thereby affording eaſe in the dropſy, gout, and rheumatiſm. Being given alone, ſays Lemery, it is apt to cauſe loathing and vomiting; and is therefore corrected with ginger, cardamoms, and grains of paradiſe.

The root of the white thapſia is often unſkilfully adminiſtered by apothecaries and druggiſts, for the true turbith.

Both black and white thapſia are exceedingly violent in their operations; and the juice, or milk, in the latter particularly,

cularly, is ſo ſharp, that being rubbed upon the face, it will carry off the ſkin along with it. For this reaſon, the roots ought to be placed among the violent medicines, the uſe of which is very dangerous.

JALAP, the root of which has long obtained a merited place in our Diſpenſatories, is generally ranked with the bind-weeds, and termed by Ray, in his Hiſtory of Plants, *Convolvulus Americanus Jalapium dictus*. It is deſcribed to have foot-ſtalks with ſingle flowers, a tuberous root, and variable leaves, ſome of them being heart-ſhaped, others angular, and ſome oblong and pointed. The plant, which will not thrive in England, unleſs preſerved in a warm ſtove, grows naturally in a territory of the Spaniſh Weſt-Indies, ſituated between La Vera Cruz and Mexico, called Xalapa, or Jalapa, (the X, and J conſonant being in Spaniſh of the ſame ſound, and interchangeable,) from whence the drug in queſtion derives its name. It has been found a matter of great difficulty, notwithſtanding every poſſible reſearch, to aſcertain the genus of the vegetable producing this excellent medicine; nor does the place which it now holds in the Sexual Syſtem meet with univerſal approbation. Caſpar Bauhin's title was, *Bryonia Mechoacana nigricans*. Father Plumier, an eminent French botaniſt of the 17th century, having aſſerted in his *Deſcription des Plantes de l'Amerique*, that Jalap was a ſpecies of Marvel of Peru, (*mirabilis*); Tournefort was induced, upon his authority, to conſtitute a genus from that plant, under the title of *jalapa*. Plumier's opinion, too, was at firſt adopted by Linnæus, who, both in his *Species Plantarum* and *Materia Medica*, has diſtinguiſhed the plant whoſe hiſtory we are tracing, by the name of *Mirabilis Jalappa*. In his 12th edition, however, of the *Syſtema Naturæ*, publiſhed at Stockholm in 1767, he renounces his former idea, transferring the plant in queſtion to the genus convolvulus by the name of *Convolvulus Jalapa*, on the teſtimony of Miller, author of the Gardener's Dictionary, who had received ſome roots from Dr. Houſton, in the Weſt-Indies, which, on due examination, were found to be the true officinal

jalap;

jalap; and, from the doctor's report, pertained to a plant which was manifeſtly a ſpecies of bind-weed. That the botanical characters, however, are not yet ſo ſufficiently aſcertained as to give ſatisfaction to all, we may collect from this circumſtance, that, in the London Pharmacopœia, this medicine is diſtinguiſhed by no ſcientific name. Dr. Lewis, after the Edinburgh Diſpenſatory, terms it *Convolvulus Jalapa Linnæi.*

Dr. Houſton, whom I juſt mentioned, had procured ſome roots of the true jalap, which he planted in Jamaica, as well with a view of fixing the genus as of cultivating the plants in that iſland. During his ſtay there, they throve very well; but ſoon after he left the country, as Miller informs us, the perſon to whoſe care he committed them, ſuffered the hogs to root them out and deſtroy them, ſo that, when ſome time after, he returned thither, there were no remains of them left; nor, as far as I can learn, has the plant been introduced into any of the Britiſh iſlands ſince that time.

Jalap has a large root, of an oval form, full of a milky juice: from it proceed many herbaceous triangular twining ſtalks, riſing to eight or ten feet, and garniſhed with ſmooth leaves, which ſtand upon long foot-ſtalks. The flowers are ſaid to be bell-ſhaped, like thoſe of the common great bind-weed.

The root of this plant is reckoned an excellent cathartic, particularly in expelling ſerous and watery humours; but ſhould be adminiſtered with caution, according to the ſtrength and age of the patient, becauſe it works very vigorouſly.

Diſtillers, and brewers, make great uſe of jalap, for exciting a fermentation.

Sea bind-weed, called likewiſe *ſoldanella*, and *braſſica marina*, has been preſcribed in dropſies, with great ſucceſs. The plant grows naturally on the ſea-beach, in many parts of England, but cannot be long preſerved in gardens. It has many ſmall, white, ſtringy roots, which ſpread wide, and ſend out ſeveral weak, trailing, reddiſh ſtalks, which twine about the neighbouring plants like the common bind-

weed. The leaves are almoſt round, ſmooth, ſhining like thoſe of the leſſer celandine, but thicker. The flowers are of a purple colour, bell-ſhaped, and ſucceeded by a fruit that is almost round, and membranous, and contains a cornered ſeed, black, or white. The whole plant has a bitter taſte, and is a little ſaltiſh.

The roots of Spaniſh potatoe, *convolvulus batatas*, are eſculent. They are annually imported from Spain and Portugal, where they are greatly cultivated for the table: but they are too tender to thrive well in the open air in England. The plants are propagated by the roots, in the ſame way as the common potatoe, but require much more room.

The leaves, flowers, ſeeds, and roots of purple violets, *viola odorata*, are uſed in medicine. The leaves are emollient, and laxative; the flowers anodyne; the ſeeds uſeful in obſtructions of the kidneys and the nephritic cholic; the roots purgative and emetic. From a repeated infuſion of the flowers in the pureſt rain-water, is prepared the ſyrup of violets, which is cordial, corrects every thing acrimonious, and looſens the belly.

The violet is one of the four cordial flowers.

Greek valerian, obtained the name of *polemonium*, according to Pliny, from πολεμεῖν, to wage war, on account of the conteſts which aroſe betwixt two princes, each claiming the honour of diſcovering it.

The plants in the genus *lobelia*, according to Linnæus, are poiſonous. *Vide Phil. Bot.* p. 283.

This deleterious quality is ſaid to be particularly obſervable in two species; *Lobelia Longifolia*, a native of Jamaica, and a Peruvian ſpecies, vulgarly known by the name of *Tupa*, which Father Feuilleé affirms to be ſo exceedingly noxious, that the ſmell of it excites ſtrong and long continued vomiting.

Lobelia Dortmanna, the aquatic bell-flower of Blair, poſſeſſes a more than ordinary ſhare of that lacteſcence which we announced above to be a general attribute of the plants of this natural order; even the leaves which grow under water abounding with milk.

We

We learn from the *Flora Suecica*, that the bloſſoms of *Jaſione montana* are peculiarly acceptable to bees; and that a green paint is procured from the flowers of round-leaved campanula.

CAMPANACEÆ, is likewiſe the forty-ninth claſs in Lud. Gerard's Arrangement of the Plants that are natives of Provence, in France; conſiſting of theſe four genera,—*campanula*, *phyteuma*, *jaſione*, and *ſamolus*.

CAMPANIFORMES *Herbæ*, (from *campana*, a bell; and *forma*, a figure). The name of the firſt claſs in Tournefort's Method, conſiſting of herbs and under-ſhrubs which have a ſimple flower, with a monopetalous corolla in the ſhape of a bell, or baſon. *Vide* COROLLA.

This claſs, in Tournefort, is ſubdivided into ſeven ſections or orders, from the ſituation of the *germen*, and nature of the fruit.

Mandrake; deadly night-ſhade, *atropa*; lily of the valley, *convallaria*; butcher's-broom; honey-wort; gentian; water-leaf; ſoldanella; convolvulus; dodder, *cuſcuta*; burning thorny-plant, *euphorbia*; caſſava, *jatropha*; *glaux*; wood-ſorrel, *oxalis*; rhubarb, *rheum*; navel-wort, *cotyledon*; dog's-bane, *apocynum*; Virginian ſilk, *periploca*; ſwallow wort, *aſclepias*; mallow; marſh-mallow; baſtard-mallow; *lavatera*; Indian-mallow, *ſida*; althæa frutex, *hibiſcus*; cotton, *goſſypium*; bryony, *tamus*; ſingle-ſeeded cucumber, *ſicyos*; male balſam apple, *momordica*; cucumber; gourd; bell-flower; rampions; croſs-wort, *valantia*; madder; and ladies bed-ſtraw, *galium*; are the bell-ſhaped flowers of Tournefort.

CAMPANIFORMES, is likewiſe the name of the ſixth and twenty-third claſſes in Pontedera's Syſtem, conſiſting of herbs and trees with bell-ſhaped flowers.

CANDELARES, the name of an order in the early editions of Linnæus's Fragments of a Natural Method, conſiſting of theſe three genera: *rhizophora*, mangrove; (the candel or kandel of the *Hortus Malabaricus*); *nyſſa* and *mimuſops*. They are removed in the later editions into the order HOLERACEÆ, which ſee.

CANDOR, the whites; a diſeaſe incident to trees. See the article VARIETAS.

CAPILLARES *Herbæ*, (from *capillus*, hair); capillary, or hair-ſhaped plants. The name of a claſs in Moriſon, Ray, and Boerhaave, conſiſting of thoſe imperfect plants called ferns. It correſponds to the ſixteenth claſs in Tournefort's Syſtem, and to the firſt order *Filices*, of the claſs *Cryptogamia*, in the Sexual Method. *Vide* FILICES, and CRYPTOGAMIA.

CAPILLUS, a term of meaſure, or dimenſion. *Vide* MENSURA.

Note. Linnæus calls the calyx of the female flowers of cat's-tail, *typha*; CAPILLI PAPPOSI, downy hairs. *Vide* PAPPUS.

CAPITATUS *Flos*, (from *caput*, a head). A fructification, generally conſiſting of many flowers firmly connected on the ſummits of the foot-ſtalk, ſo as to form a knob, or head. It is exemplified in globe amaranth, *gomphrena*. *Vide* CAPITULUM.

CAPITATÆ, is the name of a claſs in Ray's Method, and of a diviſion, or ſection, in Linnæus's Arrangement of the compound flowers, which conſtitute the forty-ninth order, in his Fragments of a Natural Method. *Vide* COMPOSITÆ.

CAPITULUM, a little head. A mode of inflorescence, in which many flowers are collected into a head, at the extremity or ſummits of the foot-ſtalk; as in globe amaranth, *gomphrena*.

A *Capitulum* is either

Dimidiatum, halved; reſembling half a head, hemiſpherical; as in *lippia hemiſphærica*.

Folioſum, leafy, intermixed with leaves.

Globoſum, round, of a globular form; as in globe amaranth, *gomphrena*.

Hiſpidum, briſtly; as in field baſil, *clinopodium vulgare*.

Nudum, naked, having no leaves, oppoſed to *folioſum*.

Ovatum, egg-ſhaped; as in *lippia ovata*.

Pedunculatum, furniſhed with pedicelli, or little foot-ſtalks; as in *teucrium capitatum*. *Vide* PEDICELLUS.

Pyramidatum, ſhaped like a pyramid; as in *lippia Americana*.

Seſſile,

Seſſile, having no peduncles or flower-ſtalks; as in *teucrium pumilum*.

Subrotundum, roundiſh; as in *ſelago fruticoſa*.

Note. The anthers of the moſſes are ſtiled by Linnæus, CAPITULA, heads, or tops. *Vide Phil. Bot.* p. 223.

CAPREOLUS, (diminutive from *caprea*, uſed by Varro for a branch that putteth forth tendrils,) a tendril. *Vide* CIRRUS.

CAPRIFICATIO, (from *caprificus*, a wild fig); the very ſingular husbandry or management of fig-trees.—Caprification.

Before I enter upon a particular diſcuſſion of this curious ſubject, which furniſhes one of the principal arguments for the doctrine of the ſexes of plants, I would previouſly remark, that the fruit of the fig-tree is not a *pericarpium* or ſeed-veſſel, as other fruits, but a *receptacle*, incloſing and ſupporting the flowers within it.

Theſe flowers, in the cultivated fig-tree, are *female* only; but of the wild figs, ſome have *male* flowers; others have both *male* and *female* flowers diſtinct, though lodged within the ſame receptacle.

This being premiſed, two queſtions naturally occur: 1, In what manner are the flowers of the cultivated fig-tree fecundated? 2, How happens it, that the fruit of our fig-trees ripen, if the flowers are of one ſex only, and have no aſſiſtance from the male? For it is not pretended that there are any male fig-trees in this country.

The difficulty of the firſt queſtion is not immediately perceived. In the iſlands of the Archipelago, and other countries, where the wild, or male figs, grow in the neighbourhood of the female, why may not the fecundation of the flowers of the latter, by the ſprinkling of the male-duſt, be performed with as great facility as that of the palm trees, and even of many plants in our own country, which bear flowers of different ſexes on diſtinct roots? I anſwer, becauſe in fig-trees there is no communication between the male and female flowers. They are incloſed within the fruit, which, as we obſerved above, is not a *pericar-*

pium, but a *receptacle*. How then, the queſtion ſtill recurs, is that fecundation effected? In a manner ſo ſingular, that were not the facts properly authenticated, they would exceed belief. A very ſmall kind of gnat, of a black colour, no where to be ſeen but about theſe trees, makes a puncture into the figs, at the time of their flowering, and there depoſits, along with its eggs, the duſt, or fecundating vapour of the ſtamina of the male, or wild fig, in which it had been formerly incloſed. Theſe inſects, whoſe worms can only ſubſiſt in the kernels of the fig-ſeeds, probably foreſee, by a ſort of wonderful inſtinct, that, if the ſeeds are not fertilized, they can produce no kernels, and conſequently no nouriſhment to their worms. For this reaſon, immediately after their tranſformation, they iſſue out of the fig, which has in ſome meaſure given them birth, copulate, repair to other figs, which are then in flower, prick them, enter by the aperture they have made, ſprinkle the fertilizing duſt of the ſtamina, which remains attached to ſeveral parts of their body, upon the ſtigma, or ſummit of the germen; and making a puncture into the germen, or ſeed-bud itſelf, there depoſit their eggs, one in each *germen*. Here the little worm being hatched, is nouriſhed with the ſubſtance of the kernel, till having attained its full ſize, and totally conſumed its proper nouriſhment, it is transformed, firſt into a *nympha*, and afterwards into a winged gnat, which, with its teeth, opens a paſſage for itſelf through the cavity of the *germen*, iſſues out of the fig, and, like its mother, takes the neceſſary precautions to perpetuate the ſpecies in other figs.

Such is the ſingular huſbandry and culture of fig-trees, as practiſed in Malta, Italy, and the iſlands of the Archipelago; countries where the fig-trees ſuſceptible of caprification naturally grow.

The moſt ample and ſatisfactory accounts of this curious operation in gardening, are thoſe of Tournefort and Pontedera: the former in his Voyage to the Levant, and in a memoir delivered to the Academy of Sciences, at Paris, in 1705: the latter in his *Anthologia*, or Philoſophy of Flowers.

Tournefort's relation is, in ſubſtance, as follows.

Of

Of the thirty ſpecies, or varieties of the domeſtic fig, which are cultivated in France, Spain, and Italy, there are but two cultivated in the Archipelago.

The firſt ſpecies is called *ornos*, from the Greek ὄρνος, which anſwers to *caprificus* in Latin, and ſignifies a wild fig-tree. The ſecond is the domeſtic, or garden fig-tree.

The former bears ſucceſſively, in the ſame year, three ſorts of fruit, called *fornites*, *cratitires*, and *orni*, which, though not good to eat, are found abſolutely neceſſary towards ripening thoſe of the garden fig. Theſe fruits have a ſleek, even ſkin; are of a deep green colour, and contain in their dry and meally inſide, ſeveral male and female flowers, placed upon diſtinct foot-ſtalks; the former above the latter.

The *fornites* appear in Auguſt, and continue to November, without ripening: in theſe breed ſmall worms, which turn to a ſort of gnats, no where to be ſeen but about theſe trees. In October and November, theſe gnats, of themſelves, make a puncture into the ſecond fruit, called *cratitires*. Theſe do not ſhew themſelves till towards the end of September. The *fornites* gradually fall away, after the gnats are gone; the *cratitires*, on the contrary, remain on the tree till May, and incloſe the eggs, depoſited by the gnats of the *fornites* when they pricked them. In May, the third ſort of fruit begins to put forth from the ſame wild fig-trees, which produced the other two: this is much bigger, and is called *orni*: when it grows to a certain ſize, and its bud begins to open, it is pricked in that part by the gnats of the *cratitires*, which are ſtrong enough to go from one fruit to the other to diſcharge their eggs.

It ſometimes happens that the gnats of the *cratitires* are ſlow to come forth in certain parts; while the *orni*, in thoſe very parts, are diſpoſed to receive them: in which caſe, the huſbandman is obliged to look for the *cratitires* in another part, and fix them at the end of the branches of thoſe fig-trees, whoſe *orni* are in fit diſpoſition to be pricked by the gnats. If they miſs the opportunity, the *orni* fall, and the gnats of the *cratitires* fly away. None but thoſe that are well acquainted with this culture, know the critical moment of

doing this; and in order to it, their eye is perpetually fixed on the bud of the fig; for that part not only indicates the time that the prickers are to iſſue forth, but alſo when the fig is to be ſucceſsfully pricked. If the bud be too hard, and too compact, the gnat cannot lay its eggs; and the fig drops when the bud is too open.

Theſe three ſorts of fruit are not good to eat; their office is to help to ripen the fruit of the garden fig-trees, in manner following: during the months of June and July, the peaſants take the *orni*, at a time that their gnats are ready to break out, and carry them to the garden fig-trees; if they do not nick the moment, the *orni* fall, and the fruit of the domeſtic or garden fig not ripening, will, in a very little time, fall in like manner. The peaſants are ſo well acquainted with theſe precious moments, that, every morning, in making their inſpection, they only transfer to their garden fig-trees ſuch *orni* as are well conditioned, otherwiſe they loſe their crop. It is true, they have one remedy, though an indifferent one, which is, to ſtrew over the garden fig-trees, the *aſcolimbros*, a very common plant there, and in whoſe fruit there is a ſort of gnats proper for pricking: perhaps they are the gnats of the *orni*, which are uſed to hover about, and plunder the flowers of this plant.

To ſum up all in one word, the peaſants ſo well order the *orni*, that their gnats cauſe the fruit of the garden fig-tree to ripen, in the compaſs of forty days. Theſe figs are very good green; when they would dry them, they lay them in the ſun for ſome time, then put them in an oven, to keep them the reſt of the year. Barley bread, and dried figs, are the principal ſubſiſtence of the boors and monks of the Archipelago; but theſe figs are very far from being ſo good as thoſe dried in Provence, Italy, and Spain: the heat of the oven deſtroys all their delicacy and good taſte: but then, on the other hand, this heat kills the eggs, that the prickers of the *orni* diſcharged therein, which eggs would infallibly produce ſmall worms that would prejudice the fruits.

What an expence of time and pains is here for a fig, and that but an indifferent one at laſt! I could not, ſays Tournefort,

ſort, (from whom this account is derived) ſufficiently admire the patience of the Greeks, buſied above two months, in carrying theſe prickers from one tree to another. I was ſoon told the reaſon; one of their fig-trees uſually produces between two and three hundred pounds of figs; but thoſe in Provence, ſeldom above twenty-five.

The prickers contribute, perhaps, continues the ſame learned naturaliſt, to the maturity of the fruit of the garden fig-tree, by cauſing them to extravaſate the nutritious juice, the veſſels incloſing which they tear aſunder, in depoſiting their eggs; perhaps, too, beſides their eggs, they leave behind them ſome ſort of liquor, proper to ferment gently with the milk of the figs, and to make their fleſh tender. The figs in Provence, and even at Paris, ripen much ſooner for having their buds pricked with a ſtraw dipped in olive-oil. Plumbs and pears, pricked by ſome inſects, likewiſe ripen much the faſter for it: and the fleſh round ſuch puncture is better taſted than the reſt. It is not to be diſputed, that conſiderable change happens to the contexture of fruits ſo pricked, in like manner as to parts of animals pierced with any ſharp inſtrument.

Pontedera, in his *Anthologia*, ſays, that in Italy, caprification is performed by gnats, which iſſuing from the male figs of the wild fig-tree, *caprificus*, loaded with the duſt of the ſtamina, make a puncture into the female figs, that is, the autumn figs of the domeſtic fig-tree; which they fecundate. This domeſtic fig-tree, he calls ſimply by the name of *ficus*; and remarks, that there is another ſpecies, *erinoſyce*, which, in ſpring, bears figs, that, having many male-flowers, and few female, fall off before they ripen; and, in autumn, figs full of female flowers, and which do not ripen till the following ſpring.

The caprification of the ancient Greeks and Romans, deſcribed by Theophraſtus, Plutarch, Pliny, and other authors of antiquity, correſponds, in every circumſtance, with what is practiſed, at this day, in the Archipelago, and in Italy. Theſe all agree in declaring, that the wild fig-tree, *caprificus*, never ripened its fruit; but was abſolutely neceſ-

ſary

fary for ripening that of the garden, or domeſtic fig, over which the huſbandman ſuſpended its branches.

The ſpecies of wild fig-tree, called *ornos* in the Archipelago, grows likewiſe at Malta, where it obtains the name of *tokar:* the fruit, called by Tournefort, *fornites*, is ſtiled by the Malteſe, *tokar-leouel*; the *cratitires*, *tokar-lanos*; and the *orni*, *tokar-taiept*. Beſides this fig, there are ſeven or eight other domeſtic ſpecies in that iſland, of which they *caprify* but two. The firſt is that deſcribed by Tournefort, which only bears once a year; the ſecond bears twice a year. The figs of the firſt crop, which is in the end of June, are ſweet like honey, thicker, and much better than thoſe of France, and arrive at perfect maturity without any aſſiſtance. Thoſe of the ſecond crop, are much ſmaller, inferior in quality to the former, and do not ripen till Auguſt, nor then, but by the aſſiſtance of caprification, without which, the greateſt part of the fruit will fall off before maturity. The conſequence, however, of this operation, is, that the fruit is greatly impoveriſhed, and the firſt crop of the following year rendered much leſs. The caprified figs too, are generally yellow, and dry within; and not unfrequently incloſe two or three gnats, ſome with, and ſome without wings.

In Provence and Spain, though the ſame ſpecies of figs are cultivated as in the Archipelago, and Malta, the curious huſbandry in queſtion has never yet been attempted. This neglect has certainly ariſen from a prudent foreſight, that the fruit gained not more in quantity by that operation, than it ſuffered in quality; for, although theſe countries do not produce the gnat, which is the principal agent of caprification, there is nothing in the nature of the climate, which would ſeem to oppoſe its introduction.

Pontedera, Linnæus, and others, have attributed the ripening of the ſeeds of the caprified fig-trees, to the fecundation of the *germina*, or ſeed-buds, by the duſt of the ſtamina, conveyed to them, and lodged in their ſubſtance, by means of the gnats. In this view, caprification becomes a principal argument in ſupporting the curious doctrine of the ſexes of plants; a doctrine, to an enlarged view of which we

are

are indebted for one of the moſt ingenious, and uniform, though it muſt be acknowledged, one of the moſt artificial ſyſtems that ever appeared.

Upon the whole, from the various facts that have been collected upon this head, and which the reader will find diſperſed in different authors, we are led to conclude, that the principal object of caprification, thus naturally performed by the gnats, is to fecundate the ſeeds, which, without ſuch aſſiſtance, would not ripen, nor, of conſequence, produce kernels proper to nouriſh the young worms, and perpetuate their race.

We are now prepared to give a ſatisfactory anſwer to the other queſtion propoſed in the beginning of this article. "How it happens, that the fruit of our fig-trees ripen, if the plants are of one ſex only, and have no aſſiſtance from the male?"

The queſtion ſuppoſes, that the fig-trees, in this country, bring fruit to maturity without the aſſiſtance of caprification; and the fact cannot be denied. The ſame thing, we have ſeen, obtains in Spain, Provence, and Malta; but the fruit, or, more properly, the fruit-veſſel, is, in all caſes, to be diſtinguiſhed from the ſeed contained within it. If the male be wanting, the ſeed will not vegetate when ſown; but the fruit may nevertheleſs ſwell, and come to an appearance of perfection: and ſo it is obſerved to do in the inſtance in queſtion, and in many others, eſpecially where the fruit is formed of one of the parts leſs connected with the ſeed, as the calyx, receptacle, *&c.* though it is more common for it to drop off before it ripens, if not impregnated by the male.

Fig-trees, then, in this country, ripen their fruit, but not their ſeed; and can therefore be propagated only by layers, ſuckers, or cuttings. But the ſummer figs of Paris, Provence, Italy, and Malta, ripen not their fruits only, but their ſeed, without the aſſiſtance of caprification; as is evident from the trees being frequently raiſed from ſeed. To account for this ſeeming paradox, I would obſerve, that the cultivated fig-trees have a few male-flowers, placed above

the

the female, within the ſame covering, or receptacle; that in Spain, Italy, and the warm climates, theſe male-flowers are perfect, and perform their proper office in fecundating the female: But that in colder climates, as that of England, and even in late ſeaſons in a warm climate, the ſtamina of the male flowers prove abortive, and no fecundation of the ſeed can enſue.

Mr. de la Hire has demonſtrated, in the Memoirs of the Academy of Sciences, that the ſummer-figs at Paris, in Provence, Italy, and Malta, have all ſtamina of a perfectly proper and regular conformation; and that the ſtamina of the autumn figs, in the ſame places, are abortive. Of this abortion, two cauſes have been aſſigned: 1, that the figs appear at a time, when the leaves, already old, perſpire but little, and receive a very ſmall ſupply of nouriſhment from the root: 2, that being much more numerous than the ſummer-figs, they require a greater ſupply of nouriſhment than the trees are, at that ſeaſon, able to afford them.

CAPSULA, (diminutive from *capſa*, a box, coffer, or caſe) a little cheſt, or caſket; a capſule. A dry, hollow ſeed-veſſel, that cleaves, or ſplits, in ſome determinate manner. *Vide* PERICARPIUM.

This ſpecies of ſeed-veſſel is frequently fleſhy and ſucculent, like a berry, before it has attained maturity; but in ripening, becomes dry, and often ſo elaſtic as to dart the ſeeds from their departments, with conſiderable velocity. This elaſticity is remarkably conſpicuous in wood-ſorrel; balſam, *impatiens*; African ſpiræa, *diaſma*; fraxinella; *juſticia*; *ruellia*; *barleria*; *lathræa*, and many others.

The general aptitude or diſpoſition of this ſpecies of ſeed-veſſel, to cleave or ſeparate, for the purpoſe of diſperſing its ſeeds, diſtinguiſhes it, not leſs remarkably than its texture, from the pulpy, or ſucculent fruits of the apple, berry, and cherry kind.

This opening of the capſule for diſcharging the ſeeds when the fruit is ripe, is either at the top, as in moſt plants; at the bottom, as in *triglochin*; at the ſide, through a pore, or ſmall hole, as in campanula, and orchis; horizontally,

as in plantain, amaranthus, and anagallis; or longitudinally, as in convolvulus.

All fruit that is jointed opens at every one of the joints, each of which contains a ſingle ſeed.

Capſules, in ſplitting, or opening, are divided, externally, into one or more pieces, called by Linnæus *valves*. *Vide* VALVULA.

The internal diviſions of the capſule are called cells, *loculamenta*; theſe, in point of number, are exceedingly diverſified; ſome capſules have only one cell, as the primroſe; others many, as the water-lily. For particulars on this ſubject, the reader is referred to the article LOCULAMENTA.

The number of capſules is generally the ſame as that of the *germina*, or ſeed-buds: for the ſeed-veſſel is nothing elſe than the ſeed-bud arrived at maturity.

We may obſerve, however, that when a flower contains a number of ſeed-buds with an undivided cavity, that is, a ſingle cell, theſe ſeed-buds, in the progreſs of vegetation, unite, and become detached, or ſeparate cells of the ſame membranous capſule.

The ſeed-veſſel conſiſts of one capſule, in lychnis; of two in pæony, and ſwallow-wort; of three in lark-ſpur, and white hellebore, *veratrum*; of four in roſe-root, *rhodiola*; of five in columbine; and of many in globe ranunculus, and marſh marigold.

The partitions which divide the capſule internally into cells are called by Linnæus, *Diſſepimenta*; and the ſubſtance which connects theſe partitions to the ſeeds, *Columella*.

In convolvulus; thorn-apple, *datura*; and chick-weed; the partitions, juſt mentioned, ſeparating, or detaching themſelves from the top of the fruit, before its maturity, open a communication betwixt the cells, and thus render the cavity of the capſule undivided; which, in its ſtate of *germen*, or ſeed-bud, conſiſted of numerous diviſions, or cells. As the ſame thing may happen, from accidental cauſes, in many other plants, it would not be improper previouſly to aſcertain the number of cells, as they exhibit themſelves in a tranverſe ſection of the ſeed-bud, in which

every

every thing reſpecting the future fruit may be viewed in miniature. Without this precaution, numberleſs miſtakes will be committed in fixing and diſcovering the genera of ſeveral plants; as of honey-ſuckle, cardinal flower, and others.

The terms *valvula*, *diſſepimentum*, *loculamentum*, and *columella*, which Linnæus, in the Philoſophia Botanica, conſiders as ſo many members, or diſtinct parts of that ſpecies of ſeed-veſſel called *capſule*, are applied, at leaſt ſome of them, with equal propriety, to any kind of dry ſeed-veſſel.

Note. Pulpy ſeed-veſſels of the apple kind, *pomum*, contain a capſule. *Vide* POMUM.

Capſules conſiſting of three cells, each of which contains a ſingle ſeed, are denominated by Linnæus, *Capſulæ Tricoccæ*. Of this ſort are the ſeed-veſſels of *euphorbia*; mercury; papaw; palma-chriſti; jack in a box, *hernandia*; baſtard-orpine, *andrachne*; and the remaining genera, in the thirty-eighth order of Linnæus's Fragments, entitled *tricoccæ* from that circumſtance. *Vide* TRICOCCÆ.

A capſule is either

Acuminata, pointed, tapering to a point, as in lilac.

Trigona, three-cornered; as in Indian arrow-root, *maranta*.

Scabra, rough with knots; as in Indian flowering-reed, *canna*.

Hiſpida, ſhaggy or briſtly; as in enchanter's night ſhade, *circæa*.

Ovata, egg-ſhaped; as in *pæderota*.

Subrotunda, roundiſh; as in Indian flowering-reed.

Globoſa, round, of a globular form; as in water-milfoil, *utricularia*.

Ventricoſa, big-bellied; as in corn-flag, *gladiolus*.

Oblonga, longer than broad; as in iris.

Triſulcata, having three grooves, or furrows; as in Indian flowering-reed, *canna*; and the genus *moræa*.

Nuda, naked, oppoſed to *hiſpida*; as in *commelina*.

Turbinata, ſhaped like a top; as in *montia*.

Emarginata, deficient in its margin, notched; as in Carolina-flax, *polypremum*.

Biſulca, furniſhed with two furrows; as in *buddleia*.

Teres, ſlender, and cylindrical; as in primroſe, and *ſoldanella*.

Coronata, crowned with the calyx; as in moſt plants which have the ſeed-bud placed below the receptacle of the flower.

Pentacocca, having five cells, each containing a ſingle ſeed; as in *byttneria*.

Colorata, coloured; as in ſtaff-tree, *celaſtrus*.

Muricata, prickly; as in *byttneria*.

Succulenta, ſucculent, pulpy; as in ſpindle-tree, *euonymus*.

Lignoſa, of a woody ſubſtance; as in *cedrela*.

Coriacea, of a ſubſtance like leather; as in *cupania*.

Inflata, blown up, ſwelled; as in bladder-nut, *ſtaphylæa*; and leſſer flowering ruſh, *ſcheuchzeria*.

Compreſſa, flat, preſſed together: as in leſſer orpine, *craſſula*; and water plantain, *aliſma*.

Carnoſa, fleſhy, or pulpy; as in *pontederia*.

Pellucida, thin, and tranſparent; as in ſuperb lily, *glorioſa*.

Flaccida, feeble, flaccid; as in bladder-nut.

Glabra, having a ſmooth even ſurface; as in ſquill, *ſcilla*; and ſpider-wort, *anthericum*.

Cordata, heart-ſhaped; as in water-purſlane, *peplis*.

Obcordata, heart-ſhaped with its tip downwards; as in ſpeedwell.

Conica, of a conic form; as in *pontederia*.

Striata, ſuperficially furrowed; fluted; as in French-willow, *epilobium*.

Lanceolata, ſhaped like a lance; as in log-wood, *hæmatoxylum*.

Semivalvis, and *ſemivalvata*, having only half a valve; as in prickly-poppy, *argemone*.

Echinata, (from Ἐχῖνος, a hedge-hog); beſet with prickles; as in *ſloanea*, and Indian-mallow, *urena*; ſynonimous to *muricata*. *Vide Supra*.

Alata, winged; as in *ſeguieria*.

Tomentoſa,

Tomentoſa, downy; as in pæony. *Vide* TOMENTUM.

Lunulata, creſcent-ſhaped; as in *iſopyrum*.

Bicarinata, having two prominences like the keel or bottom of a ſhip; as in hellebore, and marſh-marigold.

Elaſtica, burſting like a ſpring; as in *lathræa*, and *elaterium*. *Vide Supra*.

Farinacea, having a mealy ſort of pulp; as in Æthiopian ſour-gourd, *adanſonia*.

Tricarinata, having three keels; as in orchis; *ſatyrium*; and ſeveral other genera of the claſs *Gynandria* of Linnæus.

Columnaris, ſhaped like a pillar; as in *limodorum*, and *nepenthes*.

Bicornis, reſembling two horns; as in *ceratocarpus*.

Dicocca, having two cells, each containing a ſingle ſeed; as in *ſolandra*.

Scrotiformis, ſhaped like the *ſcrotum* in animals; as in mercury.

Tricornis, reſembling three horns; as in baſtard-hemp, *datiſca*.

Didyma, twin-capſules; two united in one; as in mercury, and many other plants.

Dr. Grew, in his Anatomy of Plants, diſtinguiſhes all dry ſeed-veſſels, whether capſules or pods, by the name of *ſeed-caſes*, or *membranous uteri*; in oppoſition to the pulpy ſeed-veſſels of the apple, berry, and cherry kind, which he denominates fruits.

From the curious mechaniſm of theſe ſeed-caſes, ſays that learned author, may be eaſily underſtood the reaſon of the violent and ſurprizing ejaculation of the ſeeds, obſerved in many plants. This is not a motion originally in the ſeeds themſelves; but contrived by the ſtructure of the caſe, (*ſeed-veſſel.*) For the ſeeds hanging very looſe, and not on the ſides of the caſe, as ſometimes, but on a *pole*, or column, in the centre, with their thicker end downward, they ſtand ready for a diſcharge: and the ſides of the caſe being lined with a ſtrong and tenſe membrane, they perform the office of ſo many little bows, which remaining faſt at top, and opening, or being let off at the bottom, curl forcibly upward, and ſo drive all the ſeeds before them.

This

This obſervation, which the learned author particularly applies to a ſpecies of *polygonum*, is equally applicable to the elaſtic ſeed-veſſels of other plants.

CAPSULA *Staminis*. The ſummits of the *ſtamina*. Malpighi's term for the *Anthera* of Linnæus, and *Apex* of Ray. *Vide* ANTHERA and APEX.

CARINA, a keel. The name which Linnæus gives to the lower concave petal of a pea-bloom, or butterfly-ſhaped flower, from its fancied reſemblance to the keel of a ſhip. *Vide* COROLLA and DIADELPHIA.

The keel is placed cloſe under the upper petal, called the ſtandard, *vexillum*; and within the two ſide petals, called wings, *alæ*. *Vide* VEXILLUM, and ALÆ.

It incloſes the *ſtamina*, and *piſtillum*; and conſiſts either of one petal, as in *cytiſus*; or of two adhering pretty cloſely together; as in broom, *ſpartium*; and coral-tree, *erythrina*.

The *Carina* is either

Lunulata, ſhaped like a creſcent; as in *piſcidia*, and *borbonia*:

Bifida, ſlightly cut in two; as in African-broom, *aſpalathus*:

Spiralis, ſpirally twiſted; as in kidney-bean, *phaſeolus*:

Incurva, turning back; as in ground nut, *arachis*:

Ventriculoſa, bellying out in the middle; as in baſe tree trefoil, *cytiſus*: or

Compreſſa, flat, that is, preſſed together at the ſides; as in falſe acacia, *robinia*; and milk-wort, *polygala*.

The line that forms the keel in this irregular petal, runs ſtraight as far as the middle, and then riſes in the ſegment of a circle: but the marginal line runs ſtraight to the *apex*, where the two lines meet, and terminate obtuſely.

The lower part of the baſe of the keel extends into a claw, which is inſerted into the common receptacle, and of the length of the calyx.

The ſides are ſimilar to the wings, both in ſhape and ſituation, except that they are lower, and ſtand within them.

CARYOPHYLLÆUS *Flos*, (from *caryophyllus*, Tournefort's name for the clove-gilly flower, or carnation pink,

and the clove-tree.) A flower, whoſe petals, generally five in number, are diſpoſed like thoſe of the clove-gilly flower. Theſe are the flowers *en œillet* of French writers. They have a hollow calyx or empalement of one piece, into the bottom of which are inſerted the claws of the petals. Theſe are of the ſame length with the calyx. The upper part of the petals is broad, plain, and diſpoſed on the margin of the empalement like a wheel.

Under this deſcription are included, cucubalus; lychnis; viſcous campion, *ſilene*; ſtellaria; ceraſtium; and ſeveral other plants, to be afterwards enumerated.

CARYOPHYLLEI, the name of the eighth claſs in Tournefort's, and ſixteenth in Pontedera's method, conſiſting of *herbaceous* vegetables, whoſe flowers anſwer to the deſcription given above.

Carnation; pink; clove-tree; lychnis; ſoapwort; cucubalus; flax, *linum*; and thrift, or ſea-gilly flower, *ſtatice*; are the caryophyllei of Tournefort.

CARYOPHYLLEI, is likewiſe the name of a very numerous family, or order, in Linnæus's Fragments of a Natural Method: containing, beſides the claſs of the ſame name in Tournefort, many other plants, which, from their general appearance, ſeem nearly allied to it.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Carnation-like plants with a hollow calyx of one piece, and five petals. (This ſeems to be Tournefort's idea of a clove-like flower.)

Linnæan Genera.			*Engliſh Names.*
Agroſtemma,	—	—	Campion, or wild Lychnis.
Cucubalus,	—	—	Berry-bearing Chick-weed.
Dianthus,	—	—	Clove-gilly-flower, or Carnation-pink.
Drypis.			
Gypſophila.			
Lychnis,	—	—	Campion.

Saponaria,

Linnæan Genera.			*Engliſh Names.*
Saponaria,	—	—	Soap-wort.
Silene,	—	—	Viſcous Campion.
Velezia.			

SECTION II.

Carnation-like plants with a calyx of more pieces than one, and five petals.

Alſine,	—	—	Chick-weed.
Arenaria,	—	—	Sandwort.
Bufonia.			
Ceraſtium,	—	—	Mouſe-ear chick-weed.
Cherleria.			
Glinus.			
Holoſteum.			
Loeflingia.			
Moehringia,	—	—	Mountain chick-weed.
Polycarpon.			
Sagina,	—	—	Pearl-wort.
Spergula,	—	—	Spurrey.
Stellaria,	—	—	Great chick-weed.

SECTION III.

Carnation-like plants with a calyx of more pieces than one, and no petals.

Minuartia.
Mollugo.
Ortegia.
Pharnaceum.
Queria.

To this order have been annexed, ſomewhat improperly indeed, two other *genera*, which cannot be arranged under any of the foregoing ſections. Theſe are,

Polypremum, Carolina flax.

Scleranthus, German knot-graſs, or knawel.

The former has a calyx of four pieces, and one wheel-

ſhaped petal; the latter a hollow calyx of one piece and no petals.

Habit and Structure of the Plants of this Order.

All the plants of this order are herbaceous, and moſtly annual. Some of the creeping kinds do not riſe an inch; and the talleſt exceed not ſeven or eight feet.

The ROOTS are branched, fibrous, and of a moderate length.

The STEMS are cylindrical.

The BRANCHES proceed from the wings or angles of the leaves, and are generally oppoſite, and, as it were, jointed at each knot. In ſome ſpecies of *Ceraſtium*, the branches are ſquare.

The LEAVES are generally placed oppoſite in pairs, ſo as to reſemble a croſs; and are ſlightly united at the bottom, by their foot-ſtalks, which form a ſort of glove round the ſtem.

In *Glinus*, the leaves ſurround the ſtalk in greater numbers in whirls, or whorls, (*verticilli*); and in a ſpecies of ſoap-wort, mentioned by Mr. Adanſon, they are placed alternate.

The HAIRS, (*Pili*) are ſimple, like ſilk.

The FLOWERS in this order are hermaphrodite; that is, have their ſtamina and pointal, *piſtillum*, within the ſame covers.

Lychnis dioica, *cucubalus otites*, and *gypſophila paniculata*, have male and female flowers upon diſtinct roots, and are, therefore, very improperly placed by Linnæus, in a claſs, which, according to his plan, ſhould conſiſt of hermaphrodite flowers only.

The Flowers either ſtand ſingle on their foot-ſtalks, and proceed from the wings, or angles, of the leaves and branches; or are diſpoſed in a SPIKE, CORYMBUS, UMBEL, or PANICLE. *Vide* SPICA, CORYMBUS, &c.

The CALYX, or flower-cup, is permanent, and compoſed either of one piece with five indentments, as in plants of the firſt ſection; or of four or five diſtinct leaves, as in thoſe of the ſecond and third. In clove-gilly flower, the baſe of the *calyx* is ſurrounded with four ſmall leaves or ſcales, of which the two lower are oppoſite.

The

The COROLLA in this order generally conſiſts of five petals, which, in plants of the firſt ſection particularly, have claws of the length of the *calyx*; and a ſpreading limb, ſometimes entire, but oftener cleft, or divided into two, as in *cucubalus* and viſcous campion.

Several ſpecies of *lychnis*, *ſilene*, and carnation, are rendered double by culture.

Buſonia; *ſagina*; and mountain chick-weed, *moehringia*; have four petals: *polypremum*, but one, which is wheel-ſhaped, and has its limb, or upper part, deeply divided in four.

In *Drypis*, the jaws of the tube of the corolla, (*faux*,) are furniſhed with a ſet of ſmall teeth, (*denticuli*); which ſerve as an eſſential mark in diſtinguiſhing the genus.

In viſcous campion, *ſilene*, the neck of each petal is indented with two ſmall teeth of the ſame kind, which crown the jaws of the tube, and diſtinguiſh that genus from *cucubalus*, to which it is otherwiſe very nearly allied.

Theſe appearances are reduced by Linnæus under his general term NECTARIUM, which, by the way, includes every ſingularity in the flower, whether connected with the petals, as in the preſent inſtances, or not. *Vide* COROLLA and NECTARIUM.

The STAMINA are, in number, from three to fifteen, and of a moderate length. When their number is double the diviſions of the *calyx*, as in *ſilene*, and moſt of the plants of the firſt ſection, they are attached alternately to the claws of the petals; thoſe ſo attached, being ſhorter than the reſt. The remaining ſtamina are inſerted into the common receptacle, and ſtand oppoſite to the ſegments of the *calyx*.

Note. The *filaments* in german knot graſs, *ſcleranthus*, are inſerted into the *calyx*.

Ceraſtium pentandrum, and *ſpergula pentandra*, have only five ſtamina, as the ſpecific name imparts; although the genera *ceraſtium* and *ſpergula*, belong to a claſs in Linnæus's ſyſtem, whoſe characteriſtic it is to have ten ſtamina. Theſe ſpecies ought certainly to have been arranged as diſtinct genera, or as particular ſpecies of other genera in the claſs *pentandria*. But improprieties of this, and even of a worſe

kind, are very common in the ſexual method of arrangement.

In ſome genera of this order, the number of ſtamina is found to vary, even in the different flowers of the ſame plant: thus chick-weed, *alſine*, has ſome flowers with ten ſtamina, though the greater number are furniſhed only with five.

The ANTHERS, or ſummits, are ſhort, hemiſpherical, marked with four longitudinal furrows, frequently divided or cleft below, moſt commonly erect, ſometimes, however, *incumbent*; that is, faſtened to the filaments by the ſides, as in *drypis*, and *lychnis*. *Loeflingia*, *bufonia*, & *glinus*, have twin-anthers, *anthera didyma*; that is, two anthers are placed upon each filament.

Note. The petals and ſtamina in this order, as well as the *calyx*, generally accompany the ſeed-bud to its maturity.

The POINTAL, (*Piſtillum*,) is compoſed of a ſingle SEED-BUD, which is generally roundiſh, ſometimes cornered, ſupporting either one ſtyle, as in *loeflingia*; two, as in *bufonia* and clove-gilly flower; three, as in *mollugo*, *cucubalus*, and viſcous campion; or five, as in *lychnis*, *agroſtemma*, and *glinus*.

Theſe STYLES are thread-ſhaped, of the length of the *ſtamina*, and crowned with a ſimple STIGMA, which is ſleek or ſmooth externally, and ſlightly hollowed or vaulted within.

In ſome ſpecies of pink, *dianthus*, the two ſtyles are much longer than the ſtamina; and the tops, or *ſtigmata*, are rolled back for the purpoſe of impregnation, according to the ſexualiſts.

The SEED-VESSEL is a dry capſule, of an oval form, of the length of the *calyx*, and conſiſts of one cell, as in clove gilly flower, *lychnis*, and ſoap-wort; or of three, as in viſcous campion, and *cucubalus*.

The SEEDS are numerous, ſmall, and generally kidney-ſhaped.

Note. Drypis has only one ſhining kidney-ſhaped ſeed.

The plants of this order are innocent in their quality; they

they abound in a watery ſort of phlegm, and have bitter ſeeds.

With reſpect to their virtues, they are reckoned aſtringent, attenuating, and deterſive.

The ſeeds of *lychnis*, according to Dioſcorides, were formerly applied as a proper remedy againſt the poiſonous bites of ſerpents: and in modern times, phyſicians have uſed them with ſome ſucceſs in preventing that putrefaction of the humours, which is apt to attend a continual uſe of ſpirituous liquors, particularly gin.

Burman relates in his *Theſaurus Zeylanicus*, that a particular ſpecies of Indian Lychnis, termed by the natives of Ceylon, Wiſaduli, that is, pain-alleviating powder, is ſtill uſed with efficacy, in counteracting the poiſon occaſioned by the bites of venomous animals. For this purpoſe, the ſeeds reduced to a very fine powder, are ſprinkled over the part affected, which never fails to remove the inflammation, and produce a ſpeedy cure.

Officinal ſoap-wort is a moſt powerful reſolver of obſtructions formed by fat and viſcid matter collected in the veſſels and bowels. It provokes the *menſes*, and is uſed in the aſthma and venereal diſeaſe. The Leaves are externally applied to hard tumours and whitloes. A decoction of the herb is uſed to cleanſe and ſcour woollen-cloths; and in ſome countries, the poor people uſe it inſtead of ſoap for waſhing, from which it derives its title.

The root of *Gypſophila faſtigiata*, boiled with linen and woollen cloths, poſſeſſes a like cleanſing quality: and hence, by Haller and other Botaniſts, this plant is ranked with the ſoap-worts.

The chick-weed of the ſhops, the *alſine media* of Boerhaave, grows in watery places, by the ſides of hedges and paths. The herb is in uſe: it refrigerates and moiſtens, and has the virtues of pellitory of the wall, but has no aſtringency. It is reckoned nutritive, and therefore a wholeſome food for perſons in an atrophy, or conſumption. The diſtilled water of chick-weed, or the infuſion of it in wine, reſtores thoſe who are emaciated after long diſeaſes. The

root powdered, being laid on the piles, ſtops their immoderate flux, and aſſuages the pain. The juice is vulnerary, and cleanſing, and employed with ſucceſs in inflammations and pains of the eyes.

A ſpecies of *cucubalus*, called by Miller *cucubalus latifolius*, grows naturally in moſt parts of England, where it is generally known by the name of ſpatling poppy. It ſtands in the catalogue of medicinal plants, under the title of *Behen album*; the roots are ſometimes uſed, and accounted cordial, cephalic, and alexipharmic.

Linnæus relates in his *Flora Suecica*, that by the natives of Gothland, the leaves of *Cucubalus Behen*, or Bladder Campion, are applied externally with ſucceſs in the Eryſipelas.

The flowers of ſome ſpecies of *cucubalus*, and viſcous campion, *ſilene*, are cloſed all day; but when the ſun leaves them, they expand, and have a very agreeable ſcent. From this ſingular circumſtance, ſuch plants are termed *noctifloræ*, flowering in the night-time.

Alſine media wakes, that is, expands its flowers from nine in the morning to noon, unleſs rain fall, in which caſe it does not open that day. Next day, it droops, nor does it recover its erect poſition till a conſiderable time afterwards.

The flowers of *Arenaria rubra* open betwixt nine and ten in the morning, and cloſe betwixt two and three in the afternoon.

A ſpecies of *Dianthus* (pink,) which grows naturally in European and Aſiatic Turkey: is termed by Linnæus *pomeridianus*, from the circumſtance of its always opening its flowers at half-paſt twelve at noon. They generally ſhut at ten in the evening. *Vide Vigiliæ* PLANTARIUM.

An inſect of the genus *chermes* of Linnæus, which infeſts the flowers of clammy campion (*Ceraſtium viſcoſum*) often produces ſo remarkable a change, that the leaves of the calyx become thrice as large as in their natural ſtate, and are inflated, with their tips bent inwards; the petals too become green, and are permanent.

In a ſpecies of *cucubalus*, called *gumſepungar* in Sweden, the

the flower-cup is curiouſly veined like net-work. That of our common ſort is plain.

From the joints of the ſtalks of *cucubalus otites*, there oozes a viſcous clammy juice, which ſticks to the fingers when handled, and hinders ſuch inſects as ſettle upon thoſe parts of the ſtalks from getting looſe again. The name of catch-fly has been given to a ſpecies of lychnis, and viſcous campion, which poſſeſs a glutinous quality of the ſame fatal effects to flies and other inſects.

The leaves of a variety of common ſoap-wort, called *ſaponaria hybrida*, and generally eſteemed a *luſus naturæ*, are hollowed like a ladle.

CASTRATIO, a term uſed by modern botaniſts, derived from the fancied analogy betwixt plants and animals. CASTRATION.

The caſtration of plants conſiſts in cutting off the *anthers*, or tops of the ſtamina, before they have attained maturity, and diſperſed the *pollen*, or fine duſt contained within their ſubſtance. This operation has been frequently practiſed by the moderns, with a view to eſtabliſh or confute the doctrine of the ſexes of plants: the *anthers*, or tops, being conſidered by the ſexualiſts as the male organ of generation.

The experiment of caſtration ſucceeds principally on plants, which, like the melon, have their male flowers detached from the female. In ſuch as have both male and female flowers contained within the ſame covers, this operation cannot be eaſily performed without endangering the neighbouring organs.

The reſult of the experiments on this curious ſubject by Linnæus, Miller, Alſton, and other eminent naturaliſts, may be ſeen under the article *Sexes of Plants*, whither we refer our reader. *Vide* SEXUS.

CATULUS, catkin. *Vide* AMENTUM.

CAUDEX, (*vel codex, proprie truncus arboris; ſic dictus*, ſays Voſſius, *videtur a caido ſive cædo, quia in plures ſecaretur tabulas craſſas, quarum etiam contextus caudex propterea dicebatur*); by Malpighi and other botaniſts, is uſed to ſignify the ſtem or trunk of a tree; by Linnæus, the ſtock or body of the

the root, part of which aſcends, part deſcends. The aſcending part raiſes itſelf gradually above ground, ſerving frequently for a trunk, and correſponds, in ſome meaſure, to the *caudex* of former writers: the deſcending part ſtrikes gradually downward into the ground, and puts forth radicles, or ſmall fibres, which are the principal and eſſential part of every root. *Vide* RADICULA.

The deſcending *caudex*, therefore, correſponds to the *radix* of other botaniſts. *Vide* RADIX.

Agreeably to this idea, Linnæus conſiders trees and ſhrubs as roots above ground; an opinion which is confirmed by a well known fact; that trees, when inverted, put forth leaves from the deſcending caudex, and radicles or roots from the aſcending. *Vide Phil. Bot.* p. 38, 39.

For the varieties in the ſtructure of the deſcending *caudex*, ſee the article RADIX.

CAULESCENS *Planta*, (from *caulis*, the ſtem); having a ſtem or trunk, as moſt plants, oppoſed to *acaulis*. *Vide* ACAULIS.

CAULIS, (from Καυλος,) a ſtalk or ſtem; the firſt and moſt common ſpecies of trunk, defined by Linnæus, in his *Philoſophia Botanica* to be the proper trunk of the *herb*, which elevates the leaves, flower, and fruit. *Vide* HERBA.

To this deſcription may be added another circumſtance, that *caulis* is an univerſal trunk; that is, proceeds immediately from the root: whilſt the foot-ſtalks of the flower and leaf, which Linnæus likewiſe denominates trunks, are partial, that is, proceed from an univerſal trunk, or its branches.

The ſtalks of the graſſes, palms, ferns, and muſhrooms, being of a very ſingular nature, are diſtinguiſhed by particular names.

For the different ſpecies of trunks enumerated by Linnæus, ſee the article TRUNCUS.

Note. The term *caulis*, which is now equally applied to herbs and trees, was formerly applied to herbs only: the terms *caudex*, *ſtipes*, and *truncus*, being uſed to denote the ſtem or trunk of trees and ſhrubs. *Vide* CAUDEX, &c.

A ſtem

A ſtem is either ſimple or compound.

SIMPLE ſtems are ſuch as do not divide, but proceed in a continued ſeries towards their ſummits.

COMPOUND ſtems are ſubdivided into *ramuli*, or ſmall branches, and diminiſh as they aſcend, ſo as frequently to loſe the appearance of a ſtem altogether.

Simple Stems.

Theſe are either totally entire, *caules integri*; or ſend out ſmall lateral branches, *caules ramoſi*.

Simple undivided Stems.

In this manner, I have thought proper to tranſlate the *caules integri* of Linnæus, as ſtanding oppoſed to *caules ramoſi*. I cannot, at the ſame time, help remarking, that Linnæus's explanation of this term, affords an inſtance of the great inaccuracy which ſtill prevails in botanical language. In the *Philoſophia Botanica*, he explains it by the word *ſimpliciſſimus*, and adds, *ramis vix ullis*; but in his *Delineatio Plantæ*, he gives us *ſimpliciſſimus* as a ſeparate term; it ſhould ſeem therefore, that *ramis vix ullis* belongs to *ſimpliciſſimus*; and to *integer*, *ramis nullis*, which ſenſe I have given it. In Elmgren's *Termini Botanici*, reviſed by Linnæus, we have a new explanation of *caulis integer*, viz. *ſimpliciſſimus*, *ramis anguſtatis*; the former addition, *ramis vix ullis*, is transferred to the term *ſimpliciſſimus*.

Caulis Nudus, a naked ſtem, that is, devoid of leaves and hair. Linnæus, in his *Philoſophia Botanica*, applies this term to ſuch trunks as want the leaves alone; but as in the *Delineatio Plantæ*, and the *Termini Botanici*, he makes it a diſtinct term from *Aphyllus*, which, from its etymology, is expreſſive of the want of leaves, he muſt intend that it ſhould imply entire nakedneſs, in oppoſition not to *foliatus* only, but alſo to *ſcaber*, *villoſus*, *hiſpidus*, *ſetaceus*, and other terms importing roughneſs and pubeſcence. When applied to leaves, *nudus* is evidently taken in this ſenſe.

Melon-thiſtle, dodder, burning thorny-plant, ſhrubby horſe-tail, and *ſtapelia*, afford inſtances of the naked ſtem alluded to.

Caulis

Caulis Foliatus, a ſtem covered with leaves; as in the corn-flag, and moſt plants; oppoſed to *aphyllus*, and the foregoing term.

Caulis Flexuoſus, a ſtem which takes a different direction at every joint; as in rough bindweed, *ſmilax*; and ſhrub trefoil, *ptelea*.

Caulis Volubilis, a twining or winding ſtem; that is, which aſcends ſpirally round the branch or ſtem of ſome other plant. The courſe of ſuch ſtems is either to the left, according to the apparent diurnal motion of the ſun, as in honey-ſuckle, hop, buck-wheat, and black bryony; or to the right, contrary to that motion, as in convolvulus, burning thorny-plant, Malabar night-ſhade, kidney-bean, and hemp-agrimony.

Caulis Reclinatus, bending in an arch towards the earth, as in the fig-tree.

Caulis Procumbens, lying along the ground, without putting forth roots; ſynonimous to *proſtratus*, and exemplified in the leſſer ſea-bindweed, *convolvulus ſoldanella*.

Caulis Repens, a creeping ſtem, running along the ground, and ſtriking root at certain diſtances; in which reſpect it differs from the foregoing term. It is exemplified in ivy, and the trumpet flower, *bignonia*.

Caulis Sarmentoſus, (from *ſarmentum*, a vine-twig). This ſpecies of ſtem ſtrikes root as the former; but is almoſt naked, that is, without leaves, except immediately above each knot of *radiculæ*, or little roots, where a few leaves are produced in bunches.

Caulis Paraſiticus, a ſtem not growing out of the ground, but ſupporting itſelf like a paraſite on ſome other plant; as in vanilla, dodder, miſletoe, and *tillandſia*.

Caulis teres, ſhaped like a cylinder.

Caulis anceps, two-edged, compreſſed and forming two oppoſite acute angles; as in *ſiſyrinchium*.

Caulis triqueter, having three plain or flat ſides; as in *viola tricolor*.

Caulis triangularis, having three angles.

Caulis trigonus, having three angles, as the former, with the ſides concave or convex.

Caulis Sulcatus, furrowed, marked with deep grooves, or channels, through the whole length.

Caulis Striatus, from *ſtria*, (a ſlight or ſuperficial groove); fluted, marked with ſlight, parallel channels, or grooves, through the whole length.

Caulis Glaber, having a ſmooth or even ſurface; oppoſed to

Caulis Scaber, rough, ſcabby, covered with ſmall rigid projecting points, or tubercles.

Caulis Villoſus, from *villus*, wool; hairy, or ſhaggy; covered with down, or ſoft hairs; woolly; as in ſumach, *tomex*, and common furze, *ulex europæus*.

Caulis Hiſpidus, briſtly, covered with ſtiff fragile briſtles, or prickles, whoſe roots are only ſuperficial, ſo as to be detached with the rind. *Vide* ACULEUS.

Note. The term expreſſes a great degree of roughneſs, and is exemplified in *braſſica erucaſtrum*.

Simple Branching Stems.

Caulis Adſcendens. The ſtem is ſo called when the branches grow firſt in a horizontal direction, and then gradually curve upwards.

Caulis Diffuſus, diffuſed, that is, with ſpreading branches; as in the common water germander.

Caulis Diſtichus, (from δις, twice, and στιχος, a rank, or row); having the branches horizontal, and produced in two rows; in other words, when the branches all proceed from two ſides of the ſtem only.

Caulis brachiatus, from *brachium*, the arm; having arms, branching in pairs, each pair ſtanding at right angles with thoſe above and below.

Caulis Ramoſiſſimus, abounding with branches diſpoſed without any regular order.

Caulis Fulcratus, from *fulcrum*, a prop. The ſtem ſo called, when ſupported by the branches which deſcend to the root; as in the fig-tree, and that curious aquatic, mangrove, the *rhizophora* of Linnæus.

Caulis Prolifer, ſhooting forth branches only from the

center

center of the *apex*; as in the fir, pine, cedar, and larch trees.

Caulis Simpliciſſimus, moſt ſimple, having very few branches, and proceeding in a ſtraight line up to its *apex*; exemplified in the *lathræa ſquamaria*.

The reſt as in entire ſtems.

Compound Stems.

Caulis Dichotomus, (from δις, twice, and τέμνω, to cut); a forked-ſtalk; when the diviſions are made by two and two; as in horned chickweed, *ceraſtium dichotomum*; and eaſtern ſoap-wort.

Caulis Sudiviſus, divided into branches irregularly, or without order.

Caulis Articulatus, jointed; having knots or joints at certain diſtances; as in pepper and glaſs-wort.

The ſtem often furniſhes eſſential marks of diſtinction. Thus many ſpecies of St. John's wort, lily of the valley, and French honey-ſuckle, are diſtinguiſhable only by the angles of the ſtem; and in the genus *lupinus*, the ſpecies are ſcarce to be known, except by the ſame part being ſimple or compound.

Obſervations on the reciprocal relations which ſubſiſt betwixt roots and ſtems are referred to the general head TRUNCUS, which ſee.

CEREALIA, from *Ceres*, the goddeſs of corn. Linnæus's name for the larger eſculent ſeeds of the graſſes; theſe are rice, wheat, rye, barley, oats, millet, panic graſs, Indian millet, *holcus*; *zizania*, and mays. To this head may be likewiſe referred darnel, *lolium*; which by preparation is rendered eſculent. *Vide Phil. Bot.* p. 279.

CESPITITIÆ, from *ceſpes*, a ſod, or turf; the name of a claſs in Sauvage's *Methodus Foliorum*, conſiſting of plants which have only radical leaves, that is, leaves proceeding from the root; ſuch are the primroſe, ſome ſpecies of leopard's-bane, ſea-pink, aloe, garlic, crown imperial, narciſſus, rhubarb, ſow-bread, cuckow-pint, navel-wort, the lichens, and many others.

This claſs in Sauvage's Method includes all thoſe plants which have the ſpecies of trunk or ſtem called by Linnæus *ſcapus*. *Vide* SCAPUS.

CESPITOSA *Planta*, a plant ſo termed, which produces many ſtems from one root, thereby forming a cloſe thick carpet on the ſurface of the earth.

Multitude or quantity, however, is merely an accidental circumſtance in plants, and cannot furniſh a true ſpecific diſtinction, becauſe ſubject to variation. Thus a plant which would naturally be diſpoſed, in a proper ſoil, to produce ſeveral ſtems, with difficulty produces one in a lean and poor earth: on the contrary, there are circumſtances which promote the growth of ſeveral ſtems from a ſingle root, in plants which generally produce but one. *Vide Phil. Bot.* p. 216.

CESPITOSÆ *Paludes*, turf-bogs; a term of ſoil. *Vide* SOLUM.

CHARACTERES, marks or ſigns, characters. The deſcription of the *Genera* of plants ſo termed by Linnæus; hence the *Generical Character* of any plant, and the *Definition of the Genus*, are ſynonimous terms.

The term *Character* is not extended by that author to the *ſpecies* of plants; becauſe he never gives the complete deſcription of any ſpecies; but only enumerates thoſe characters or circumſtances in which it differs from all the other ſpecies of the ſame genus. This obſervation ſufficiently illuſtrates the different methods which are obſerved in the *Genera* and *Species Plantarum*. In the former work, all the parts of the flower and fruit, from which the characters of the genera are derived, are accurately and completely deſcribed; in the latter, ſuch ſtriking circumſtances only of the ſtem, leaves, buds, roots, *&c.* are mentioned, as ſufficiently diſtinguiſh the ſpecies in queſtion from every other of that genus to which it belongs.

The ſame obſervation accounts for the appellations CHARACTERES and DIFFERENTIÆ, prefixed to two chapters or ſections in the *Philoſophia Botanica:* the former of which lays down rules for eſtabliſhing the genera; the latter, the ſpecies.

In general, characters, or characteriſtical marks, according to the idea of ſyſtematic writers, are certain external ſigns obvious in the appearance of natural bodies, by means of which they are diſtinguiſhed from one another. Theſe ſigns being collected and expreſſed by proper words, lay the foundation at once for *definition*, *diſtribution*, and *denomination*, the three grand parts of practical botany.

The characters which are known by the ſenſe of ſight are only to be depended on in diſtinguiſhing bodies: thoſe which are acquired by the other ſenſes, as the taſte and ſmell, being rarely or never to be admitted as marks of diſtinction.

The characteriſtic mark of each genus is to be fixed from the figure, ſituation, connection, number and proportion of all the parts.

Figure is the boundary of extenſion: in deſcribing figure, therefore, let the boundaries be indicated by lines, and expreſſed by proper terms. For although, in aſcertaining this property of bodies, accurate and geometrical dimenſions cannot every where be obtained; yet is figure principally to be attended to in this view. Figures, from reſemblance to other bodies, are fallacious, and ſhould be but ſparingly uſed. Tournefort and Linnæus are faulty in this reſpect. Inſtances of ſuch improper terms, will occur frequently in deſcribing the parts, particularly the trunk and leaf. *Vide* CAULIS and FOLIUM.

Situation, or inſertion, (*ſitus*,) expreſſes an order of co-exiſting things, without any reſpect to their continuity or contiguity to others. Thus leaves are ſaid to be oppoſite or alternate in point of ſituation; by which it is meant to expreſs, not that the leaves are continuous or contiguous, for they are neither; but that they ſtand in a certain relation of oppoſition, or alternation to each other. The parts being accurately defined, excellent characters may be deduced from this property; as from the ſituation of the fins in fiſhes, and the various inſertion of the ſtamina of flowers, into the calyx, petals, or receptacle.

Connection, (*nexus*,) expreſſes an order of co-exiſting bodies, reſpecting continuity and conjunction, by an immediate

diate production of the conſtituent parts. The coaleſcence of the parts is neceſſary in this property of bodies. The union of the claws with the upper ſpreading part of the petals; of the anthers and filaments of the ſtamina; and of the toes in web-footed birds, furniſhes examples.

Number expreſſes unity multiplied, or the relation of ſimilar parts to unity. Examples of characters thence deduced, are found in almoſt every part of natural hiſtory; thus the diviſions of the calyx, petals, *ſtamina*, and *ſtyli* in flowers; the feet, toes, wings, fins, and teeth in various animals; are, with reſpect to number, no deſpicable foundations of generic diſtinctions.

Proportion reſpects the compariſon of quantities; or, to ſpeak more accurately, the quantity of any part compared with another in its neighbourhood. In the vegetable kingdom, examples may be adduced from the proportion of the petals between themſelves; from the ſegments, (*laciniæ*,) of the calyx, compared to thoſe of the petals; from the ſtamina and petals, or ſtamina and ſtyli: in the animal kingdom, from the proportion of the head and tail to the body, or of the wings and fins to one another.

Any part of a body conſidered either in itſelf, or with relation to others, is found to poſſeſs all the properties juſt enumerated. Characters, therefore, may be drawn from all the parts, to define the difference of bodies; thus the leaf, ſtem, flower and its parts in plants; the foot, wing, fin, in animals; all differ in their figure, ſituation, number, and proportion, and exhibit characters proper for diſtinction.

Experience ſhews that one part or property of a part varies more than another; in conſtituting a method, therefore, thoſe parts and properties are to be ſelected, which vary leaſt. Thus the parts of flowers in vegetables, the feet, fins, beaks, in animals, are more fixed with reſpect to the above-mentioned properties. Again, the figure and number of theſe parts are more apt to vary than their ſituation, connection and proportion; the characters, therefore, are, if poſſible, to be taken from theſe laſt.

In arranging natural bodies, nothing creates ſuch confu-

ſion as the great variety which yet is ſo expreſſive of the Creator's omnipotence and wiſdom. The fact is, various bodies, every way limited in their eſſential properties, are ſubject to change from occaſional cauſes, in other properties leſs eſſential. Hence the enquirers into nature ſhould give particular attention to all the properties of bodies, and ſelect from them the moſt conſtant for ſcientific diſtinction.

The great number of bodies to be inveſtigated requires, that, in diſtinguiſhing them, we ſhould collect many characters; that from theſe placed in proper ſubordination, we may lay the foundation of the differences and agreements of bodies.

Before the invention of regular ſyſtematic methods, diſtinctive characters were derived from all the parts of plants indiſcriminately; a circumſtance which ſufficiently explains the confuſion that long obtained in botany, as well as the ſlow advances of the ſcience. It was not till the diſtribution into claſſes, genera and ſpecies became an object of attention, that rules were eſtabliſhed for fixing with preciſion the parts, whence characters could moſt commodiouſly be drawn.

Tournefort, who, in 1694, gave the firſt and moſt perfect model of this diſtribution, has made no diviſion of the characters in queſtion. Dr. Linnæus is the firſt who ſuggeſted four ſorts; the factitious, accidental, or artificial character, *character factitius*; the eſſential; the natural; and the habitual;—which are all equally applicable to the higher and lower diviſions.

Artificial Character.

The artificial character, otherwiſe called accidental, and by Linnæus, factitious, is drawn indiſcriminately from different parts of the plant, and admits of fewer or more characteriſtical marks than are abſolutely neceſſary for diſtinguiſhing the claſſes, genera, and ſpecies.

Linnæus, who particularly applies all the characters juſt enumerated, to the diſtribution of the genera, eſtabliſhes for

for a criterion of the artificial character, that it can never diſtinguiſh the genera in a natural order; being calculated merely for diſcriminating ſuch as arrange themſelves under the ſame artificial order.

To the head of artificial characters is referred, by Linnæus the deſcription of the genera, in the methods of Tournefort, Ray, Rivinus, Boerhaave, and moſt of the other ſyſtematic botaniſts.

The claſſical characters only, in the ſexual method, are deemed artificial: the generical, as exhauſting the deſcription of the parts of fructification, its author conſiders as true natural characters: with what propriety will be ſeen below.

Linnæus's idea of an artificial character is well expreſſed by Ray, when he ſays, That no more characteriſtical marks of the genera are to be collected, than are found abſolutely neceſſary for determining the genus with certainty and preciſion.

Eſſential Character.

The eſſential character diſcriminates one plant from another, by means of a ſingle mark, ſo ſtriking and particular, as to diſtinguiſh the plant in which it is found, from every other at firſt ſight. It ſerves, ſays Linnæus, to diſtinguiſh ſuch genera as arrange themſelves under the ſame natural order.

The eſſential character of the claſſes and genera, by the conſent of all the modern ſyſtematic botaniſts, ought to be drawn from one of the ſeven parts of fructification; that of the ſpecies from any of the other parts, as the ſtem, leaf, root, buds, *&c.* In the following ſpecies of Linnæus, the eſſential ſpecific characters are very improperly taken from the parts of fructification:

Tamarix floribus pentandris, tamariſk with five ſtamina.
Tamarix floribus decandris, tamariſk with ten ſtamina.
Spergula pentandra, ſpurrey with five ſtamina.
Salix floribus diandris, willow with two ſtamina.
Salix triandra, willow with three ſtamina.
Salix pentandra, willow with five ſtamina.

Valeriana floribus monandris, valerian with one ſtamen, or male organ.

Valeriana floribus diandris, valerian with two ſtamina.

Verbena diandra, vervain with two ſtamina.

Dryas pentapetala, dryas with five petals.

Dryas octopetala, dryas with eight petals.

Tilia floribus nectario inſtructis, lime-tree whoſe flowers are furniſhed with a *nectarium*. *Vide* NECTARIUM.

Tilia floribus nectario deſtitutis, lime-tree whoſe flowers want a *nectarium*.

Delphinium nectariis monophyllis, lark-ſpur with a *nectarium* of one leaf.

Delphinium nectariis diphyllis, lark-ſpur with a *nectarium* of two leaves.

Delphinium nectariis tetraphyllis, lark-ſpur with a *nectarium* compoſed of four leaves.

Papaveres capſulis hiſpidis, poppies with briſtly capſules, or ſeed-veſſels.

Papaveres capſulis glabris, poppies with ſmooth capſules.

Delphinium unicapſulare, lark-ſpur with one ſeed-veſſel.

Delphinium tricapſulare, lark-ſpur with three ſeed-veſſels.

Nigella pentagyna, fennel-flower with five ſtyles.

Nigella decagyna, fennel-flower with ten ſtyles.

Hypericum floribus pentagynis, trigynis, & digynis, St. John's-wort with five, three, and two ſtyles.

Beautiful as theſe ſpecific diſtinctions from the parts of the fructification frequently are, they muſt be allowed to be highly improper and immethodical; as, by making the ſame parts characteriſtical of the claſſes, genera and ſpecies, the illuſtrious author confounds the higher with the lower diviſions, and thus falls into the very error, which he himſelf has been at ſuch pains to expoſe.

In apology for ſo remarkable a deviation from his own principles, Linnæus tells us, that, though he once imagined, that, as the flower was of ſhort duration, and its parts commonly very minute, recourſe ſhould not be had to the fructification for ſpecific differences, till all other ways had been tried, and found ineffectual; yet, upon a ſtricter attention

tention to the ſubject, he was inclined to recant that opinion, as the fructification contains more diſtinct parts than all the reſt of the plant taken together; and certainty throughout nature, is found moſt commonly to obtain in her minuter parts. *Vide Phil. Bot.* p. 222.

I ſhall make no further comment upon this obſervation, than by remarking, that ſeveral of the ſpecies above enumerated, as well as many others in the Linnæan method of arrangement, might, with as great propriety, be denominated genera, and removed into different claſſes and orders, as many old genera, which were not eſtabliſhed on the fructification, are rejected by the ſexual ſyſtem, and converted into ſpecies.

The excellence of the eſſential character conſiſts in its brevity.

Natural Character.

This character includes the two former, and collects all the poſſible marks of plants. It is uſeful, ſays Linnæus, in every method; lays the foundation of the ſyſtems; remains unchanged, although new genera be daily diſcovered; and is capable of emendation by the detection of new ſpecies alone, which afford an opportunity of excluding ſuch characteriſtical marks as are totally ſuperfluous. He adds, that the *Genera Plantarum* firſt introduced theſe characters into the ſcience.

Botaniſts, from the time of Geſner, who eſtabliſhed the diſtribution into genera and ſpecies on rational principles, have been greatly puzzled in determining from what parts of the plant, claſſic, generic, and ſpecific characters might moſt commodiouſly be drawn.

Before we examine their opinions on this ſubject, it will not be improper to obſerve, that what they have ſaid of characters in general, may, with ſufficient propriety, be referred to the head of natural characters, which we are now conſidering.

Conrad Geſner, a phyſician of Switzerland, was the firſt, who, in 1560, ſuggeſted the idea of eſtabliſhing generic characters from the parts of the fructification; I mean, from the flower, fruit, and ſeed: a principle ſo much the more

juſt, as theſe parts being deſtined for the reproduction of the plant, muſt neceſſarily be moſt conſtant, and general. And yet, till the time of Geſner, the roots, leaves, or flowers alone had engaged the attention of enquirers into nature. In one of his letters to Zwinger, he thus expreſſes himſelf: "Ex his enim, (fructu, ſemine & flore) potius quam foliis, ſtirpium naturæ et cognationes apparent." And in another letter to Occon: "Meliſſa Conſtantinopolitana ad Lamium vel Urticam mortuam quodammodo videtur accedere; ſeminis tamen, unde ego cognationes ſtirpium indicare ſoleo, figura differt."

In 1694, Tournefort, who introduced into the ſcience order, purity, and preciſion, availed himſelf of Geſner's idea for eſtabliſhing the genera. Generical characters, according to this illuſtrious botaniſt, are to be drawn from all the parts of fructification, if neceſſary; if unneceſſary, from the moſt eſſential. If all the parts of fructification ſhould not ſufficiently diſtinguiſh any particular genus, recourſe is then to be had to auxiliary characters from the other parts of the plant, and even from their virtues and ſenſible qualities. The genera formed from the parts of fructification alone, were called primary genera, or genera of the firſt order; thoſe formed from any of the other parts combined with the fructification, were ſtyled ſubaltern genera, or genera of the ſecond order. See the article GENUS.

In ſhort, Tournefort, as well as Ray, proceeded upon this principle, neither to multiply characteriſtical marks without neceſſity; nor, on the other hand, to be ſo limited to a particular part of the plant, as at any time to incur the danger of ſacrificing accuracy to uniformity, or preciſion to elegance.

Heiſter, in a diſſertation *de Foliorum Utilitate*, printed at Helmſtadt, in 1731, is of opinion, that the leaves furniſh eſſential marks for characteriſing the genera of plants. Tournefort had advanced the ſame thing in the preface to his inſtitutions. His words are, "ſitus numeruſque foliorum plurimum faciunt ad generum diſtinctionem; ut fragariæ folia terna, &c." *Iſagoge*, p. 60.

In 1735, Dr. Linnæus, afterwards profeſſor of botany at Upſal,

Upſal, in Sweden, preferring uniformity to preciſion, proceeded to arrange the genera upon a new principle; and, notwithſtanding the lights which he muſt have received from the ingenious reſearches of Geſner, Ray, Tournefort, and other eminent botaniſts who preceded him, is not aſhamed to arrogate to himſelf the chief, nay, the ſole merit of eſtabliſhing the genera upon a ſure and unſhaken foundation.

The generical characters, according to Linnæus, are to be drawn from all the parts of the fructification, and in no caſe, be it ever ſo neceſſary, from any other. Upon this principle, ſo different from that of every former botaniſt, does the *Genera Plantarum* proceed: a book, which, although executed in a maſterly manner, and with the moſt aſtoniſhing accuracy, has, I think, contributed very little to the progreſs of the ſcience. This aſſertion will not appear extravagant, if it is conſidered that, accurately determined as the Linnæan Genera are, they have caſt a thick cloud over all the labours and ingenious enquiries of the very men to whom the ſcience is moſt indebted. The genera of Ray, Tournefort and Boerhaave, are now no more. Eſtabliſhed upon other principles, they are either ſwallowed up in more extenſive genera, and dwindle into mere ſpecies; or they are ſplit, and become numerous genera inſtead of one. The names too, are frequently changed, without neceſſity: in ſhort, ſuch is the transformation, that there are very few of the Linnæan genera which agree in every thing with correſponding genera in Tournefort, or Ray.

Linnæus calls his generic characters natural; and adds, that he was the firſt who introduced them into botany. "Ego primus, (ſays he) hos characteres compoſui;" again, "*Genera mea Plantarum* promunt characteres naturales." *Phil. Bot.* p. 130. And in the preface to his *Genera*, ſection 18, "Naturales itaque hic trado Characteres qui notas omnes in fructificatione obvias et communes exhibent; tales ante me, quantum novi, dedit nullus."

A character of this kind, continues the ſame author, is applicable to every method that has been, or ſhall be invented; and affords a foundation both to the old and new ſyſtems

that are eſtabliſhed upon the parts of the fructification; viz. the calyx, petals, *ſtamina*, *piſtillum*, or fruit. The diſcovery even of a thouſand genera, does not render it neceſſary to make the ſlighteſt alteration in the next natural genus, by the addition or diminution of a ſingle character.

Theſe and many other properties of the natural character enumerated by Linnæus, are true. But was he the firſt that introduced this character into botany? I readily allow, that the principle of eſtabliſhing the genera from all the parts of the fructification, and none other, was never uniformly adopted by any former ſyſtematic writer. We have ſeen, however, that Ray and Tournefort, occaſionally adopted it; nay, never tranſgreſſed it, but with a view to avoid ſuperfluous characters, or imperfect deſcriptions. In fact, what has Linnæus added to Tournefort's generical characters of the paſſion-flower, burnet, the willow and poplar-trees, and many others, in which the latter has given accurate and full deſcriptions or figures of all the parts of fructification? It is true, he inſiſts leſs than Linnæus on certain parts, as the number of ſtamina in the above mentioned plants; the calyx and ſeeds in others: ſuch parts in his idea, being not only leſs eſſential, but even ſuperfluous for eſtabliſhing the character of the genus.

Nor is Tournefort the only botaniſt prior to Linnæus, whoſe generical characters exhauſt the deſcription of the parts of fructification. Many genera, in Boerhaave, are of the ſame kind.

Again, Linnæus's characters are by no means applicable to a natural method, which, in aſcertaining the genera of plants, is not confined merely to the parts of fructification. Thus in certain tribes or families, as the pea-bloom flowers, the leaves furniſh the moſt eſſential marks; and in others, as the gaping, or maſqued tribe, *ringentes*, the diſpoſition of the flowers. In fact, theſe characters cannot be applied to every artificial method, but to ſuch only as are eſtabliſhed on the parts of the flower and fruit; nor do I think that in theſe they are always ſufficient for aſcertaining the genus, without calling in ſome other characters to their aſſiſtance.

The

The natural character of the ſpecies of plants ought, according to Tournefort, to be drawn from all the parts which are unconnected with the fructification, as the root, ſtem, and leaves; likewiſe from their ſenſible qualities, as colour, taſte and ſmell.

To the former part of this aphoriſm Linnæus cheerfully ſubſcribes, but not to the latter. The duration of plants, their colour, place of growth, time of flowering, and other qualities which are not obvious in their appearance, are rejected by the ſexual ſyſtem as very improper ſpecific diſtinctions, and referred to the head of varieties, to which they more properly belong. If Linnæus has corrected one error in thus refuſing to admit the ſenſible qualities of plants into the number of genuine ſpecific diſtinctions, he has committed another no leſs dangerous, by having recourſe to characters from the parts of the fructification, which he adviſes to adopt, when they do not interfere with thoſe of the claſs and genus. Examples of this impropriety may be ſeen above.

Character drawn from the Habit or Port of Plants.

This character was the invention of the earlier botaniſts, who knew no better rule for the diſtribution of vegetables. It is drawn from the external face or general conformation of plants, conſidered with reſpect to the reſult of all their parts, their manner of growth, the diſpoſition of the branches and leaves; in ſhort, all the relations which approximate plants, or remove them from one another.

The character of the habit, although quickly diſcerned, and eaſily recalled by the memory, has never been employed but in diſtinguiſhing the ſpecies. Linnæus ſeems to think, that it may be uſed, with caution, and in default of other characters, for aſcertaining the genera; and M. Gouan, in his *Hortus Monſpelienſis*, has uſefully adopted it under the name of ſecondary character.

As among quadrupeds, ferocious animals, ſuch as the bear, and lion, are diſtinguiſhed at firſt ſight, from the ſheep, bull, camel, and other *pecora*, without inſpecting their teeth by

by which they are artificially arranged: ſo many natural orders of plants may be diſtinguiſhed from one another by their habit or external face, without having recourſe to any artificial or partial characters whatever.

An expert botaniſt, ſays Linnæus, can eaſily diſtinguiſh the plants of Africa, Aſia, America, and the Alps, from each other, by their habit and external face, without being able to aſſign the cauſes or characteriſtic marks of ſuch diſtinction. Thus the plants of Africa have a certain ſtern, dry, obſcure appearance; thoſe of Aſia are proud and towering; the American plants have a ſmooth agreeable aſpect; thoſe of the Alps appear hardy and vigorous.

From what has been ſaid of claſſic, generic, and ſpecific characters, they appear to be highly arbitrary and variable. So far, indeed, from being fixed on an unſhaken foundation, they are ſubjected to the caprice of every ſyſtematic botaniſt, who may regard as accidental, or arbitrary, what others conſider as true, natural and eſſential characters.

I conclude with laying down Linnæus's arbitrary principles on this head. Theſe eſtabliſh that the characters of the claſs are to be taken from one part of the fructification: thoſe of the genus, which he calls his natural characters, from all the parts of the fructification, and none other: thoſe of the ſpecies, from all the other parts, as the root, trunk, leaf, buds, and habit; nay, even from ſome circumſtances attending the parts of fructification, if they do not enter into the character of the genus or claſs.

CHRONICI, from χρονος, time. By this name Linnæus denominates a claſs of early botaniſts, who arranged all plants from their time of flowering.

CICHORACEUS *Flos*, from *cichorium*, ſuccory; a flower like ſuccory, or endive. The term is uſed by Vaillant, and is ſynonimous to the *planipetalus* of Ray and Boerhaave, the *ſemifloſculoſus* of Tournefort, the *lingulatus* of Pontedera, and the *ligulatus* of Linnæus. *Vide* LIGULATUS, *&c.*

CICHORACEI, the name of a claſs in Cæſalpinus's ſyſtem, and of Vaillant's arrangement of the compound flowers, conſiſting

conſiſting of plants whoſe flowers, like endive, are compoſed of ſeveral leſſer flowers, which are hollow at the baſe only, flat in the middle, and expanded towards the top. Of this ſort are dandelion, hawk-weed, nipple-wort, viper's-graſs, and ſeveral others.

CIRCULATIO *humorum ſeu ſucci.* Circulation of the humours, or ſap in plants.

The curious controverſy in philoſophical botany, reſpecting the deſcent of the ſap, is fully diſcuſſed under the article SUCCUS, which ſee.

CIRRUS, (*capillus quaſi in circum tortus*,—curled or frizzled hair,)—a claſper, or tendril; that fine ſpiral ſtring or fibre, put out from the foot-ſtalks, by which ſome plants, as the ivy and vine, faſten themſelves to walls, pales, or trees for ſupport.

The term is ſynonimous to the *capreolus*, *clavicula*, and *viticulus* of other botaniſts, and is ranked by Linnæus among the *fulcra*, or parts of plants that ſerve for ſupport, protection, and defence. *Vide* FULCRA.

Tendrils are ſometimes placed oppoſite to the leaves, as in the vine; ſometimes at the ſide of the foot-ſtalk of the leaf, as in paſſion-flower; and ſometimes, as in the winged-pea, *piſum ochrus*, they are emitted from the leaves themſelves.

With reſpect to compoſition, they are either ſimple, that is, compoſed of one fibre or chord, as in the vetch; or compound, that is, conſiſt of two, three, or more, as in the everlaſting pea.

Bitter-ſweet, *ſolanum dulcamara*; *bignonia*, and ivy, ſend forth tendrils which plant themſelves like roots in the adjacent walls, or the bark of the neighbouring trees.

Claſpers, ſays the ingenious Dr. Grew, are not like trunk roots, a mean betwixt a root and a trunk, but a compound of both, as may be gathered from their circumvolutions, in which they mutually aſcend and deſcend.—In the mounting of the trunk, continues the ſame author, claſpers ſerve for ſupport. Thus in vines, the branches being very long, fragile and ſlender, would be liable to frequent breaking, unleſs, by means of their claſpers, they were mutually contained

tained together; ſo that the whole care is divided betwixt the gardener and Nature: the former, with his ligaments of leather, ſecures the main branches; and Nature, with thoſe of her own providing, ſecures the leſs. Their aptitude to this end is ſeen in their convolutions, a motion not proper to any other part: and alſo in their toughneſs, which is ſo much the more remarkable, as they are ſlenderer than the branches from which they proceed.—In the trailing of the trunk, tendrils ſerve for ſtabiliment and ſhade. Thus in cucumbers, the trunk and branches being long and fragile, would be driven to and fro by the winds, to the great prejudice both of themſelves and their tender fruits, were they not by theſe ligaments held faſt together, and preſerved in good aſſociation and fellowſhip. The ſame claſpers ſerve likewiſe for ſhade: ſo that a natural arbour is formed by the branches of the cucumber, in the ſame manner as an artificial one is made by tangling together the twigs of trees; for the branches, by the linking of their claſpers, being couched together, the tender fruits lie under the umbrage of a bower made of their own leaves.

Moſt of the pea-bloom flowers have twining claſpers, that is, which wind to the right and back again.

CLASSIS, a claſs; the firſt and higheſt diviſion in every method; defined by Tournefort to be a collection of *Genera* which have ſome ſtriking mark in common; and by Linnæus, the agreement of ſeveral *Genera* in the parts of the fructification, according to the principles of nature, diſtinguiſhed by art. This primary diviſion is very aptly illuſtrated by the manner in which a dictionary is compiled; there all the words, which have the ſame initial letter, arrange themſelves together, as it were, under one claſs: each particular word being a diſtinct genus of that claſs. The claſſic character then is conſtituted from a ſingle circumſtance, as the initial letter in queſtion which is found to be poſſeſſed equally by all the words in that diviſion, how different ſoever they are in other reſpects.

The ancient botaniſts knew neither methods, ſyſtems, nor claſſes; they collected in chapters, or in ſections, thoſe plants,

plants, which appeared to them to reſemble each other in the greateſt number of relations. It is in this manner that Theophraſtus, Dioſcorides, and other authors, who are conſidered as ſyſtematic botaniſts, have arranged vegetables.

The ſingle mark which characterizes the claſs is arbitrary; and therefore different in different ſyſtems. In Tournefort, the petals; in Ray, the fruit; and in Linnæus, the ſtamina, furniſh claſſic artificial characters.

Claſſes are ſubdivided into ſections or orders, and diſtinguiſhed, like ſyſtems, into natural and artificial. The umbelliferous, compound, pea-bloom, and croſs-ſhaped flowers ſeem to prove that there are true natural claſſes. *Vide Phil. Bot.* p. 100.

Some artificial methods retain a few of the natural claſſes; others preſerve none. In general, that method is to be preferred, which collects the greateſt number of ſuch claſſes. Whenever a claſs, or part of a method, is demonſtrated to be falſe, that method cannot be natural; it is artificial.

Modern botaniſts having eſtabliſhed as an axiom, that the characters of the claſs may be drawn from any of the parts of fructification, were determined in their choice by the real, or ſuppoſed conſtancy of a particular part. Thus Tournefort's ſyſtem, as we have ſaid, is founded upon the ſtructure, figure, and other circumſtances of the petals: that of Magnolius, on the calyx; thoſe of Ray and Boerhaave, on the fruit; that of Sigeſbeck, on the ſeeds; and that of Linnæus, upon the ſtamina. The piſtil, although as uniform and conſtant as any of the other parts, has never yet been employed as a claſſic diſtinction: Linnæus chiefly uſes it as the foundation of his ſecondary diviſions or orders, as Tournefort does the fruit, becauſe it generally ſucceeds the petals, which furniſh his claſſic characters.

Tournefort was the firſt who demonſtrated that the parts of the fructification in plants were preferable to all the other parts for eſtabliſhing the claſſes. Theſe laſt, however, he does not abſolutely exclude: on the contrary, he admits them, whenever the other characters are inſufficient. Linnæus has followed Tournefort's principle in all its rigour,

and

and pretends that the claſſic characters ought to be taken from the parts of fructification, and none other.

From this diverſity of opinion, with reſpect to the moſt eſſential parts of the plant, or of the fructification, for eſtabliſhing a ſyſtem, have ariſen the diſſenſions among ſyſtematic writers, who, miſunderſtanding the extent of the principle in queſtion, have framed a multiplicity of methods, each of which is regarded by its founder, as the moſt univerſal, moſt eaſy, and moſt natural that had hitherto appeared. But how can thoſe methods be natural, which contain few or no natural claſſes? Or how can the principles upon which ſuch claſſes proceed, be regarded in any other light than as arbitrary and hypothetic?

The excellence, or defect, of the claſſic character conſiſts, ſays Linnæus, in its greater or leſs approximation to the natural one. Natural claſſes are ſuch as agree in their habit, manner of growth, virtues, uſes and ſenſible qualities. Such are the graſſes, the compound, umbelliferous, pea-bloom, croſs-ſhaped, and verticillated flowers, the ferns, and ſome others.

CLAVICULA, (diminutive from *clavis*, a key; uſed by Cicero for the tendril of a vine, wherewith it takes hold of any ſubſtance, and climbs up by it,)—a claſper, or tendril. The term is employed by Tournefort, Ludwig, and the ancient botaniſts. Linnæus has ſubſtituted CIRRUS, which ſee.

CLAVUS, (properly a nail,—uſed by Celſus for any horny appearance, as a corn in the toe or elſewhere—,) a ſpecies of diſeaſe, to which the grains of many graſſes, particularly thoſe of rye, are incident. *Vide* VARIETAS.

CLIMA, a climate; a part of the ſurface of the earth, bounded by two circles parallel to the equator.

Different climates, as well as different ſoils, rarely produce plants of the ſame ſpecies. This ſubject is curious, and, conſidering its importance to gardening, well deſerves the attention of every botaniſt.

The numerous ſpecies of plants, which grow betwixt the North Pole and the Equator, when viewed in detail, appear

to differ from each other only by inſenſible degrees: yet are the plants of the frozen zones, when viewed *in cumulo*, totally different from thoſe which are produced betwixt the tropics. Thus we often ſee whole families of plants natives of the torrid zone, which are never to be found in any of the others.

In the climate of plants, ſays Linnæus, are to be conſidered latitude, longitude, and the temperature or elevation of the ſoil. Vaillant was among the firſt who viewed the loca natalia of plants in this light; but his obſervations were confined to latitude alone.

Places ſituated under the ſame parallel of latitude, but in oppoſite hemiſpheres, produce plants that are totally different; even thoſe in the ſame hemiſphere are rarely alike. Thus Rome, Pekin, and New York in America, are ſituated almoſt in the ſame degree of north latitude, yet produce very different plants. The ſame may be ſaid of the plants of Florida and Paleſtine, the Cape of Good Hope, and Chili in South-America: places which exactly correſpond in latitude; the two former ſituated in the northern hemiſphere; the latter in the ſouthern.

What has been affirmed of latitude, may likewiſe be aſſerted of places that are ſituated upon the ſame meridian. Thus the North Cape, Rome, Upſal, and the Cape of Good Hope, agree in longitude, yet produce plants that are totally different.

The aptitude, however, of plants to grow in certain climates, and not in others, ſeems to depend not ſo much upon longitude and latitude, as upon the elevation of the ſoil, or difference of temperature in ſuch climates. From this cauſe principally proceeds the difference which is generally found to obtain betwixt the plants of the torrid, and thoſe of the temperate and frigid zones. For when in the torrid zone we find mountains, which, by their elevation, have acquired a temperature ſimilar to that of the temperate or frigid zones, we always diſcover on ſuch mountains the ſame, or, at leaſt, a part of the ſame, plants. Thus the plants on the mountains of Lapland, of Switzerland, Greenland, Siberia, Wales,

the

the Pyreneans, Olympus, Ararat, the Andes, and thoſe of Braſil, though placed at ſuch immenſe diſtances from each other, are nearly the ſame.

Again, as at a certain depth, the temperature of water is found to be nearly the ſame in all climates: the greateſt part of aquatic plants are common to the torrid, temperate and frigid zones. Thus the water-lily, *aldrovanda*, ſun-dew, arrow-head, water-milfoil, and many other aquatics, are equally natives of Europe and the Indies.

As culture, ſo climate, has a mighty tendency to change the texture and external appearance of plants. Thus the ſame plants which, under an inclement, rigorous atmoſphere, are covered, or cruſted over with a thick coriaceous ſkin, ſhall, in more indulgent ſkies, exhibit no ſuch appearance, but be perfectly ſmooth.

COADUNATÆ, (*coadunare*, to join, or gather together). The 52d order of plants, in Linnæus's Fragments of a Natural Method, ſo termed, as I imagine, from the general appearance of the ſeed-veſſels, which are numerous, and being ſlightly attached below, form altogether a ſingle fruit in the ſhape of a ſphere or cone, the parts of which, however, are eaſily ſeparated from one another.

The Genera *contained in this Order are ſix:* viz.

Linnæan Genera.		*Engliſh Names.*
Annona.		
Liriodendron,	—	— The Tulip Tree.
Magnolia,	—	— Laurel-leaved Tulip Tree.
Michelia.		
Uvaria.		
Xylopia.		

Habit and Structure of the Plants of this Order.

This family of exotic plants furniſhes as beautiful and choice a collection of ſhrubs and trees, both evergreen and deciduous, as is to be found in the whole vegetable kingdom. The trees are often ſixty feet high, and garniſhed from the bottom

bottom to the top with ſpreading branches and leaves of a bright green colour, which aſſume a very agreeable conic form.

The ROOTS are branched and fibrous.

The STEMS cylindric.

The WOOD very hard.

The BUDS conic, flat, and generally naked, or without ſcales.

The LEAVES are univerſally ſimple, and alternate. The foot-ſtalk is cylindric, without furrows, frequently ſwelled at its origin, and appears jointed at its inſertion into the branch.

In the magnolias, and tulip-trees, two very large *ſtipulæ*, or ſcales, are attached to the branches near the origin of the foot-ſtalk of the leaves; but theſe fall ſoon after the leaves are expanded. *Vide* STIPULA.

The FLOWERS are hermaphrodite, that is, have both *ſtamina* and piſtil within the ſame covers; and are generally produced either along, or at the end of, the branches.

The CALYX generally conſiſts of three oblong plain leaves like petals, which fall off with the flower. The tulip-tree, beſides a flower-cup of three leaves, has likewiſe an external *involucrum*, or cover, compoſed of two triangular leaves, which fall away in like manner as the others.

In *xylopia*, the calyx conſiſts of one leaf; in *uvaria*, it is permanent, that is, accompanies the ſeed-bud to its maturity.

The PETALS are in number, from ſix to eighteen, oblong, concave, and frequently diſpoſed in two or three ſeries or rows, the outermoſt of which are largeſt.

The STAMINA are numerous, ſhort, and inſerted into the common receptacle in the five firſt genera; into the *germen*, or ſeed-bud, in the ſixth; a circumſtance, which removes that genus to the claſs *Gynandria* in the ſexual method; whilſt the other genera, from the indefinite number of their *ſtamina*, are reduced to the claſs *polyandria* in the ſame method. *Vide* GYNANDRIA, and POLYANDRIA.

The FILAMENTS, or threads of the ſtamina, are very

ſhort and ſlender; *uvaria*, *xylopia*, and the cuſtard-apple, have ſcarce any filaments at all.

The ANTHERS, or tops, are numerous, ſlender, and placed round the ſeed-bud; in *xylopia*, they are ſeated upon it.

The PISTIL, or pointal, generally conſiſts of a number of ſeed-buds, diſpoſed in the form of a cone, and ſeated upon a receptacle, which riſes like a ſmall pillar above the receptacle of the calyx. Cuſtard-apple, and *xylopia*, have only one roundiſh ſeed-bud.

From each ſeed-bud generally ariſes a cylindric ſtyle, which is very ſhort, and in *magnolia* bent backwards.

The tulip-tree, *michelia*, and the cuſtard-apple, have no ſtyle.

In *xylopia* it is of the length of the petals.

The STIGMA, or top of the ſtyle, is commonly blunt, and in *michelia*, bent backwards.

Magnolia has a hairy ſtigma placed along each ſtyle.

The SEED-VESSEL is commonly a berry; in *magnolia* it is an oval cone, conſiſting of a number of roundiſh capſules, laid over one another like tiles. The fruits, or ſeed-veſſels, whether of the berry, capſule, or cherry kind, are equal in number to the ſeed-buds, and generally ſlightly attached below.

In the tulip-tree there is properly no ſeed-veſſel; the ſeed-buds, in the progreſs of vegetation, become ſo many naked ſeeds, which lie over one another like the ſcales of fiſh, and form the appearance of a cone.

The SEEDS, in this order, are generally numerous, hard, roundiſh, and ſometimes cornered. In the *magnolias*, each capſule contains a ſingle kidney-ſhaped ſeed, of the nature of a berry, which, when ripe, is diſcharged from its cell, and hangs by a ſlender filament, or thread.

In *xylopia*, the ſeed is a ſtone, the fruit being of the cherry kind.

The ſeeds of the tulip-tree are winged. *Vide* ALA.

The plants of this order have a ſtrong, agreeable, and aromatic ſmell; the fruits and ſeeds have a pungent taſte, like pepper. The bark and wood are bitter.

The berries are eſculent, particularly thoſe of *annona*, ſome ſpecies of which have an exquiſite and very delicate taſte.

None of theſe plants, as far I can learn, (ſour-ſop, a ſpecies of *annona* excepted,) have ever been uſed in medicine; but for beauty and ornament, they yield to no tribe or family whatever, on which account they have of late years been cultivated with great care in this country.

The talleſt *magnolia* is a native of Florida, and South-Carolina, where it riſes to the height of eighty feet, and upwards, with a ſtrait trunk of two feet diameter, and a regular head; the leaves reſemble thoſe of the common laurel, but are much larger; they are of a ſhining green on their upper ſurface; of a ruſſet, or buff-colour on their under, and continue all the year: ſo that this is one of the moſt beautiful ever-green trees yet known.

The leaves of the *magnolia tripetala* are very large, and produced in horizontal circles ſomewhat reſembling an umbrella; from which circumſtance, the inhabitants of Virginia and Carolina, where it grows naturally, have given it the name of umbrella-tree.

The tulip-tree, termed by Linnæus *liriodendron*, from the fancied reſemblance of its flowers to thoſe of the lily, and by other botaniſts, *Tulipifera*; is a native of North-America, where it grows to be a tree of the firſt magnitude, and is generally known through all the Engliſh ſettlements by the title of poplar. Of late years, a great number of theſe trees have been raiſed from ſeeds in the Engliſh gardens; ſo that they are now become common in the nurſeries about London. The firſt of the kind which flowered in England, was in the gardens of the late earl of Peterborough, at Parſon's-Green, near Fulham. There is a very beautiful tulip-tree which flowered laſt ſummer, (1769) * in the garden of Waltham-Abbey; and at Wilton, the ſeat of the earl of Pembroke, there are ſome trees of great bulk. The flowers, which are produced at the end of the branches, conſiſt of ſix petals, in two rows, which form a ſort of bell-ſhaped

* The firſt edition of the Botanical Dictionary was publiſhed in 1770.

flower, whence the North Americans gave it the name of tulip.

Some of theſe trees, ſays Cateſby, in his Natural Hiſtory of Carolina, are thirty feet in circumference, with unequal and irregular boughs, which diſtinguiſh them at a diſtance, even when they are ſtript of their leaves. Their timber is of great uſe in their native ſoil, particularly for making that kind of boats called periaugues.

The cuſtard-apple, a ſpecies of *annona*, derives its name from the texture of the fruit, which, when ripe, is of an orange colour, with a ſoft, ſweet, yellowiſh pulp, of the conſiſtence of a cuſtard.

North American *annona*, is called by the inhabitants papaw-tree.

The fruit of Soortſak, Zuurſak, or ſour-ſop, the *annona muricata* of Linnæus, is ſhaped like a heart, but ſomewhat longer, and generally bends towards the point. The outſide is of a glaucous green, ſtudded here and there with ſoft-pointed prickles. The inſide is a ſoft pulpy ſubſtance, which is eaten, and looked upon to be a good cooler in fevers.

The leaves of moſt ſpecies of *annona* being rubbed, emit a ſtrong agreeable ſcent.

COLOR, colour; an attribute, or ſenſible quality, which, in plants, is found to vary, not only in different individuals of the ſame ſpecies, but likewiſe in different parts of the ſame individual. Thus marvel of Peru, and ſweet-william, have frequently petals of a different colour, on the ſame plant.

Three or four different colours are frequently found upon the ſame leaf, or flower: as on the leaves of the *amaranthus tricolor*, and the flowers of the tulip, auricula, three coloured violet, and others. To produce the moſt beautiful, and ſtriking variety of colours in ſuch flowers, is the principal delight and buſineſs of the floriſt.

The primitive colours, and their intermediate ſhades or gradations, enumerated by botaniſts, are as follows.

Water-colour, *hyalinus*.

WHITE, *albus*.

Lead-

Lead-colour, *cinereus.*
BLACK, *niger.*
Brown, *fuſcus.*
Pitch-black, *ater.*
YELLOW, *luteus.*
Straw-colour, *flavus.*
Flame-colour, *fulvus.*
Iron-colour, *gilvus.*
RED, *ruber.*
Fleſh-colour, *incarnatus.*
Scarlet, *coccineus.*
PURPLE, *purpureus.*
Violet-colour, *cæruleo-purpureus.*
BLUE, *cæruleus.*
GREEN, *viridis.*

Theſe colours ſeem to be appropriated to particular parts of the plant. Thus white is moſt common in roots, ſweet berries, and the petals of ſpring flowers. Water colour, in the filaments and ſtyles. Black, in the root and ſeeds; rarely in the ſeed-veſſel, and ſcarce ever to be found in the petals. Yellow is frequent in the anthers, or tops of the ſtamina; as likewiſe in the petals of autumnal flowers, and the compound ligulated flowers of Linnæus. *Vide* LIGULATUS *Flos.*

Red is common in the petals of ſummer-flowers, and in the acid fruits. Blue and violet colour, in the petals. Green, in the leaves and calyx, but rarely in the petals.

In the interchanging of colours, which in plants is found to depend upon differences in heat, climate, ſoil and culture, a ſort of elective attraction is obſerved to take place. Thus red is more eaſily changed into white and blue; blue into white and yellow; yellow into white; and white into purple.

A red colour is often changed into a white, in the flowers of heath, mother of thyme, betony, pink, viſcous campion, *cucubalus*, trefoil, orchis, fox-glove, thiſtle, cudweed, ſaw-wort, roſe, poppy, fumatory, and geranium.

Red paſſes into blue in pimpernel.

Blue is changed into white in bell-flower, Greek valerian, bind-weed, columbine, violet, vetch, milk-wort, goat's-rue, viper's-bugloſs, comfrey, borage, hyſſop, dragon's-head, ſcabious, blue-bottle and ſuccory.

Blue is changed into yellow in crocus.

Yellow paſſes eaſily into white in melilot, agrimony, mullein, tulip, *blattaria*, or moth-mullein, and corn marigold.

White is changed into purple in wood ſorrel, thorn-apple, peaſe, and daiſy.

Although plants are ſometimes obſerved to change their colour upon being moiſtened with coloured juices, yet that quality in vegetables ſeems not ſo much owing to the nature of their nouriſhment, as to the action of the internal and external air, heat, light, and the primitive organization of the parts.

In ſupport of this opinion, we may obſerve with Dr. Grew, that there is a far leſs variety in the colours of roots, than of the other parts of the plant; the pulp, within the ſkin, being uſually white, ſometimes yellow, rarely red.

That this effect is produced by their ſmall intercourſe with the external air, appears from this circumſtance, that the upper parts of roots, when they happen to ſtand naked above the ground, are often dyed with ſeveral colours: thus the tops of ſorrel roots turn red; thoſe of turnips, mullein, and radiſhes, purple; and many others green: whilſt thoſe parts of the ſame roots, which lie more under ground, are commonly white.

The green colour is ſo proper to leaves, that many, as thoſe of ſage, the young ſprouts of St. John's-wort, and others which are reddiſh when in the bud, acquire a perfect green, upon being fully expanded.

In like manner, the leaves of the ſea-ſide grape, *polygonum*, which, when young, are entirely red, become, as they advance in growth, perfectly green, except the middle and tranſverſe ribs, which retain their former colour.

As flowers gradually open, and are expoſed to the air, they throw off their old colour, and acquire a new one. In fact, no flower has its proper colour till it is fully expanded. Thus the purple ſtock gilly flowers are white, or pale, in the bud.

bud. In like manner, batchelor's-buttons, blue-bottle, poppy, red-daiſy, and many other flowers, though of divers colours when blown, are all white in the bud. Nay, many flowers change their colours thrice ſucceſſively; thus the very young buds of lady's looking-glaſs, bugloſs, and the like, are all white; the larger buds purple, or murrey; and the open flowers, blue.

With reſpect to the colours of the juices of plants, we may obſerve that moſt reſinous gums are tinctured; ſome, however, are limpid; that which drops from the domeſtic pine, is clear as rock-water. The milk of ſome plants is pale, as in burdock; of others, white, as in dandelion, euphorbium, and ſcorzonera; and of others yellow, as in lovage, and greater celandine. Moſt mucilages have little colour, taſte, or ſmell.

Of all the colours above enumerated, green is the moſt common to plants, black the moſt rare.

Moſt plants, either by decoction, or long infuſion, communicate a green colour to oil. Saffron gives it a light golden tincture.

Several aromatic plants, as mint, marjoram, balm, being dried and infuſed in oil, give it a double tincture, both green and yellow; one drop of the oil ſhewing green; but a good quantity of it held up againſt a candle, looks reddiſh, or of a deep yellow colour.

Alkanet root, the *anchuſa minor purpurea* of Parkinſon, is the only vegetable yet known, which gives a true red tincture to oil; yet will it not colour water in the leaſt.

Red roſes being dried, and infuſed for ſome time in oil of aniſeed, a more potent menſtruum than common oil, loſe their own colour entirely, and turn white, without effecting any change on the oil, which remains limpid as at firſt.

As oil rarely takes a red, there being but one known inſtance of it; ſo there is no plant that I know of, which, by infuſion, will give a perfect green to water.

But although the green leaves will not give their viſible colour, by infuſion in water, yet will they impart moſt other colours, as well as the flowers themſelves. Thus the leaves

of cinquefoil give a tincture reſembling Rheniſh wine; thoſe of hyſſop, Canary; of ſtrawberry, Malaga; of mint, Muſcadine; thoſe of wood-ſorrel produce a tincture reſembling a mixture of Claret and water; of balm, near as red as ordinary Claret alone. All aromatic hot plants give a yellow-red tincture to water, as well as oil. Theſe leaves, however, do not all give their tincture in the ſame ſpace of time; ſome require a fortnight; others a week; others five, three, or two days; and ſome but one, or even half a day.

Spirit of wine is as unſuſceptible of a blue colour, as the two former menſtrua are of a red and a green. In fact, ſeveral blue flowers, as lark-heel, violet, mallows, borage, being infuſed in that ſpirit, produce no ſenſible effect in changing its colour: yet upon dropping a little ſpirit of ſulphur, or ſal-ammoniac, into the infuſion, it immediately becomes a full red in the firſt caſe; a deep green in the other:—the preciſe effects which theſe ſubſtances would have produced, if the liquor had been previouſly of a blue colour.

Balm, the green leaves of which, as we obſerved above, give a Claret colour to water, gives a pure and perfect green to ſpirit of wine.

Yellow and red flowers give a ſtronger and fuller tincture to water than to ſpirit of wine; as may be ſeen by comparing the infuſions of cowſlips, poppies, clove gilly-flowers, and roſes, in either liquor.

Let us now examine what changes are effected in colour, by the mixture of the infuſions of plants with other bodies.

A ſtrong infuſion, or the juice, of the leaves of roſe-tree, raſpberry, ſtrawberry, cinquefoil, gooſeberry, primroſe, Jeruſalem-cowſlip, peony, biſtort, laurel, and goat's-beard, dropped upon ſteel, makes a purple tincture.

Sugar of lead dropped on a tincture of red roſes, turns it to a faint pale green.

Salt of tartar dropped upon the ſame tincture, turns it to a deeper green.

Spirit of ſulphur dropped on the green leaves of Adonis flower, everlaſting-pea, and hollyhock, turns them all yellow.

Salt

Salt of tartar dropped on the white flowers of daiſy, changes them into a light green.

Of all colours, yellow ſeems to be the moſt fixed and unfading. No ſenſible change is effected by dropping the ſpirit of ſulphur, or a ſolution of tartar, on a tincture of the yellow flowers of crowfoot, adonis, and ſaffron.

Of all water-colours, the rareſt and moſt difficult to make clear, bright, and permanent, is blue. There are many flowers of an excellent blue colour, as thoſe of the bugloſs, lark-heel, and others; but they eaſily fade. Among the very few inſtances of flowers that will ſtrike into a blue, may be mentioned lathyrus, or the everlaſting pea, which, upon the affuſion of ſpirit of hartſhorn, is changed from a peach to a pure blue. Other alkalis, and particularly lime-water, will, no doubt, have the ſame effect, and perhaps, render the colour more permanent.

For a full diſcuſſion of this curious ſubject the reader is referred to a very ingenious treatiſe of the learned Dr. Grew on the Colours of Plants, read before the Royal Society, from which many of the above obſervations and experiments are taken.

We proceed to make ſome further remarks on the colours of plants, with reference to method and ſyſtematic arrangement.

Colour being, as we have ſeen, ſo very ſuſceptible of change, ought never to be employed in diſtinguiſhing the different ſpecies of plants, which are to be characterized from circumſtances not liable to alteration by culture, or other accidents.

Hitherto we have treated principally of the inconſtancy of colour in flowers, as the tulip, hyacinth, anemone, ranunculus, primroſe, blue-bottle, bell-flower, columbine, violet, fumatory, and many others.

The ſame inconſtancy is obſerved in other parts of the plant; berries frequently change from green to red, and from red to white. Even in ripe fruits, the colour, whether white, red or blue, is apt to vary; particularly in apple, pear, plumb, and cherry-trees.

Seeds

Seeds are more conſtant in point of colour, than the veſſel which contains them. In the ſeeds, however, of the poppy, oat, pea, bean, and kidney-bean, variations are frequently obſerved.

The root too, although not remarkably ſubject to change, is found to vary in ſome ſpecies of carrot and raddiſh.

Leaves frequently become ſpotted, as in a ſpecies of orchis, hawk-weed, ranunculus, knot-graſs, and lettuce; but ſeldom relinquiſh their green colour altogether. Thoſe of ſome ſpecies of amaranthus, or flower-gentle, are beautifully coloured.

The ſpots that appear on the ſurface of leaves, are of different colours, liable to vary, and not ſeldom diſappear altogether.

The leaves of officinal lungwort, and ſome ſpecies of ſow-bread, ſorrel, trefoil, and ranunculus, are covered with white ſpots. Thoſe of dog's-tooth violet, with purple and white.

Thoſe of ſeveral ſpecies of ranunculus, and orchis, and a kind of knot-graſs, called by Tournefort, *Perſicaria ferrum equinum referens*, with black and purple.

Thoſe of *Amaranthus tricolor*, with green, red, and yellow.

Thoſe of *Ranunculus acris*, and a ſpecies of bog-bean, with red, or purple.

The under ſurface of the leaves of ſome ſpecies of pimpernel, and of ſea plantain, is marked with a number of dots, or points. A white line runs through the leaves of Indian-reed, black-berried heath, and a ſpecies of canary-graſs; and the margin, or brim of the leaf, in ſome ſpecies of box, honey-ſuckle, ground-ivy, and the ever-green oak, is of a ſilver-white colour.

The whole plant is often found to aſſume a colour that is unnatural, or foreign to it. The varieties in ſome ſpecies of eryngo, mugwort, orach, amaranthus, purſlane, and lettuce, furniſh examples.

Such being the inconſtancy of colour in all the parts of the plant, ſpecific names derived from that quality are, very properly, by Linnæus, deemed erroneous; whether they reſpect

reſpect the colour of the flower, fruit, ſeeds, root, leaves; or expreſs in general, the beauty or deformity of the entire plant, with a particular view to that circumſtance. Of this impropriety, ſo generally committed by former botaniſts, Linnæus himſelf is not always guiltleſs. Thus the two ſpecies of *ſarracenia*, or the ſide-ſaddle flower, are diſtinguiſhed by the colour of their petals into the yellow and purple ſarracenia; although the ſhape and figure of the leaves afforded much more conſtant, as well as ſtriking, characters. The ſame may be ſaid of his *lupinus albus, & luteus*; *Reſeda alba, glauca, & lutea*; *Angelica atropurpurea*; *Dictamnus albus*; *Lamium album*; *Selago coccinea*; *Sida alba*; *Paſſiflora rubra, lutea, incarnata, & cærulea*; and of many others, in which the ſpecific name is derived from a character or quality that is ſo liable to vary in the ſame ſpecies. I conclude this article with obſerving, that of all the ſenſible qualities, colour is leaſt uſeful in indicating the virtues and powers of vegetables. The following general poſitions on this ſubject, are laid down by Linnæus, and ſeem ſufficiently confirmed by experiment.

A yellow colour generally indicates a bitter taſte; as in gentian, aloe, celandine, turmeric, and other yellow flowers.

Red indicates an acid, or ſour taſte; as in cranberries, berberries, currants, raſpberries, mulberries, cherries; the fruit of the roſe, ſea-buck-thorn, and ſervice-tree. Herbs that turn red towards autumn, have likewiſe a ſour-taſte, as ſorrel, wood-ſorrel, and bloody dock.

Green indicates a crude alkaline taſte, as in leaves and unripe fruits.

A pale colour denotes an inſipid taſte, as in endive, aſparagus, and lettuce.

White promiſes a ſweet, luſcious taſte; as in white currants, and plumbs, ſweet apples, *&c.*

Laſtly, black indicates a harſh, nauſeous, diſagreeable taſte; as in the berries of deadly night-ſhade, myrtle-leaved ſumach, herb-chriſtopher, and others; many of which are not only unpleaſant to the taſte, but pernicious, and deadly in their effects,

To diſcover the acid, or alkaline quality of any plant, expreſs ſome of the juice, and rub it upon a piece of blue paper, which, if the plant in queſtion is of an acid nature, will turn red; if of an alkaline, green.

COLUMELLA, (*quaſi Columnella*, a little pillar, or column.) The ſubſtance which paſſes through that ſpecies of ſeed-veſſel called a capſule, and connects the ſeveral internal partitions with the ſeed. *Vide* CAPSULA.

COLUMNIFERÆ, from *columna*, a pillar; and *fero*, to bear. The name of the 87th order in Linnæus's Fragments of a Natural Method, conſiſting of plants whoſe ſtamina and piſtil have the appearance of a pillar in the centre of the flower.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Plants with Stamina that are diſtinct, and inſerted into the common Receptacle.

Linnæan Genera.			*Engliſh Names.*
Bixa,	—	—	Arnotta, or Anotta; by the French termed Roucou.
Corchorus,	—	—	Jew's-Mallow.
Heliocarpus,	—	—	Tree Montia.
Kiggelaria.			
Microcos.			
Muntingia.			
Thea,	—	—	Tea-Tree.
Tilia,	—	—	Lime, or Linden-Tree.
Turnera.			
Triumfetta.			

SECTION II.

Plants with Stamina that are diſtinct, and inſerted into the Piſtillum, *or Pointal.* (Gynandria.)

Ayenia.
Grevia.

Heliceres,

Linnæan Genera.			*Engliſh Names.*
Helicteres,	—	—	Screw-Tree.
Kleinhovia.			

SECTION III.

Plants with one or more ſets of united Stamina.

Adanſonia,	—	—	Æthiopian Sourgourd, or African Calabaſh-Tree.
Alcea,	—	—	Hollyhock, or Roſe-Mallow.
Althæa,	—	—	Marſh-mallow.
Bombax,	—	—	Silk Cotton-Tree.
Camellia.			
Goſſypium,	—	—	Cotton.
Hermannia.			
Hibiſcus,	—	—	Althæa Frutex, or Syrian Mallow.
Lavatera,	—	—	Sea Tree-Mallow.
Malope,	—	—	Baſtard Mallow.
Malva,	—	—	Mallow.
Melochia.			
Napæa.			
Pentapetes,	—	—	Indian vervain Mallow.
Sida,	—	—	Indian Mallow.
Stewartia.			
Theobroma,	—	—	Chocolate-nut, or Baſtard Cedar of Jamaica.
Urena.			
Waltheria.			

Habit and Structure of the Plants of this Order.

This order furniſhes a choice and curious collection of herbs both annual and perennial, ſhrubs, and trees. Theſe are very different in point of ſize and height, from the creeping mallows, and low ſhrubby tea-tree, to the lofty limes, and ſtill more lofty ſilk cotton-trees, which, by ſome modern writers, are affirmed to be ſo large, as not to be

fathomed by ſixteen men, and ſo tall, that an arrow cannot reach their top.

The ſize of the African calabaſh-tree, or Æthiopian ſour-gourd, the Baobab of Proſper Alpinus, as deſcribed by M. Adanſon, is truly amazing. The diameter of the trunk, he ſays, frequently exceeds 25 feet; and the breadth of the tree at top, meaſures from 120 to 150 feet. The horizontal branches, he continues, are from 45 to 55 feet long; and ſo large in circumference, that each branch is equal to a monſtrous tree in Europe. The roots too, where the water of a neighbouring river has waſhed away the earth ſo as to leave them bare and open to view, meaſure one hundred and ten feet long, excluſive of thoſe parts which remain covered with earth, or ſand; and yet, amazing as theſe dimenſions are, the height of the talleſt tree, mentioned by that author, does not exceed ſeventy feet. *Vide* Adanſon's *Voyage au Senegal, & Famille des Plantes*, Tom. 1, p. 211. *Preface*.

The ſhrubs and trees of this order are deciduous, pretty thick, of a beautiful appearance, with an erect ſtem, which is formed by its branches and foliage into a round head.

The ROOTS are extremely long, branch but little, and either run perpendicularly downwards, as in plants of the firſt and ſecond ſections; or extend themſelves horizontally below the ſurface, as in thoſe of the third.

The STEMS are cylindric. The young branches, though commonly of the ſame figure, are ſometimes angular.

The BARK is thick, and pliant.

The WOOD, in general, very ſoft and light.

The BUDS are of a conic form, naked, that is, without ſcales, and ſituated either at the extremity of the branches, or in the angle formed by the branch and leaf. Syrian mallow, Ethiopian ſourgourd, and *lavatera*, have no buds.

The LEAVES are alternate, ſimple, divided into ſeveral lobes, and frequently hand or finger-ſhaped. The ribs, or nerves, on the back of the leaf, in ſome genera of this order, are provided near their origin with a number of hollow furrows, or glands, which being filled with a clammy honey-like liquor, have been conſidered as ſo many veſſels of ſecretion.

cretion. Egyptian and Syrian ketmia, *bibiſcus*, have one hollow of this kind, placed on the middle rib. The cotton-tree has three, two of which frequently diſappear in cold climates; *urena* has ſometimes three hollows, but moſt commonly one.

The FOOT-STALK of the leaves is cylindric, ſwelled at its origin, and appears jointed at its junction with the branch. In ſome ſpecies of Syrian mallow, and *turnera*, the flowers and leaves are borne on the ſame foot-ſtalks; or, to ſpeak more properly, the foot-ſtalk of the flower proceeds from the foot-ſtalk of the leaf. At each ſide of the foot-ſtalk are generally faſtened two *ſtipulæ*, or ſcales, which are ſimple, of a moderate ſize, commonly erect, and fall before the other leaves of the plant. The glands, or veſſels of ſecretion at the baſe of the leaves in tree montia, furniſh eſſential marks in diſtinguiſhing the ſpecies.

The ſtems and branches of ſome ſpecies of Syrian mallow, and ſilk cotton-tree, are armed with long conic prickles, which in the latter are ſometimes two inches in diameter, and fall off very early, being only faſtened to the bark. A ſpecies of ſilk cotton-tree, called by Linnæus *Bombax pentandrum* from the number of its ſtamina, has its ſtem, when young and tender only, covered with prickles; that of the full grown tree being very ſmooth, and unarmed. Tree-montia, and triumfetta, when young, bear downy leaves; when full grown, thoſe of the former are ſmooth; thoſe of the latter, prickly.

The FLOWERS are univerſally hermaphrodite, except in *kiggelaria*, and a ſpecies of Virginian marſh-mallow, called by Linnæus, *Napæa dioica*; the former of which bears male and female, the latter male and hermaphrodite, flowers on different roots.

In plants of the third ſection, the flowers generally open about nine in the morning, and remain expanded till one o'clock in the afternoon. Theſe ſame flowers, as they wither, are ſubject to change their colour; the red become violet, or purple; the white contract a fleſh colour; and the yellow

yellow turn white. The flowers of *Triumfetta* are rolled or turned backwards, in the night time.

The flowers either terminate the branches, proceed from the angles of the leaves, or are diſpoſed either ſingly, or in a *corymbus*, along the branches, or ſtem. *Vide* CORYMBUS.

The FLOWER-CUP is ſingle in plants of the firſt and ſecond ſections; but frequently double in thoſe of the third. In theſe laſt, the inner calyx is always of one piece generally divided into five ſegments; the outer conſiſts either of one leaf, as in cotton-tree, and marſh-mallow; of three diſtinct leaves, as in mallow and baſtard-mallow; or of many, as in Syrian mallow. The ſmall ſcales, which frequently accompany the calyx of Indian vervain-mallow, *pentapetes*, are not a ſecond calyx, as Miller fancies, but *ſtipulæ*, which fall off ſoon after their production. *Vide* STIPULA.

The calyx, when ſingle, is ſometimes compoſed of one leaf, which is permanent; as in arnotta, and *hermannia*: or of ſeveral diſtinct leaves, which, in plants of the firſt ſection, are generally coloured, and fall off with the petals; as in *microcos* and Jew's-mallow.

In plants that have a double calyx, both flower-cups are generally permanent.

The PETALS in this order, are in number from four to nine; five is the prevailing number. In ſome ſpecies of ſilk cotton-tree, the flower conſiſts of one petal only, which is ſhaped like a funnel, and divided into five ſegments at top; moſt flowers of the tea-tree have ſix petals; ſome, however, are obſerved to have nine, three of which are external, equal, and of a middling ſize; ſix internal, equal, and very large. Arnotta has a double *corolla*, or rather a double row of petals; each row conſiſting of five oblong and large petals, which are equal. Plants of the third ſection have univerſally five petals, which are heart-ſhaped, terminated below by a claw or ſtalk which attaches them to the receptacle of the calyx, and cloſely embrace or infold each other above, ſo as to form the appearance of a ſingle petal. They are alternate with the diviſions of the calyx, and fall

ſoon

ſoon after their expanſion. The lapping, or embracing of the petals juſt mentioned, is always found to be in a direction contrary to the apparent diurnal motion of the ſun.

In many flowers of this order is found that ſpecies of ſuperfluity to which Linnæus has given the indefinite name of NECTARIUM; this appearance adds greatly to the beauty of the flower; and is particularly conſpicuous in *hermannia*, chocolate-nut, *kigelaria*, and the plants of the ſecond ſection. *Vide Supra.*

The ſpring flowers of a ſpecies of Jew's-mallow, called by Linnæus *corchorus ſiliquoſus*, have no petals, and but four ſtamina; the autumnal flowers of the ſame ſpecies have five petals, and numerous ſtamina. A ſpecies of ſcrew-tree, termed *helicteres apetala*, wants likewiſe the petals, as the name imports.

The STAMINA, which are in number from five to twenty, and upwards, are generally inſerted into the common receptacle of the calyx, in plants of the firſt and third ſections; into the *piſtillum*, or ſeed-bud, in thoſe of the ſecond.

The FILAMENTS, or threads of the ſtamina, are diſtinct in the two firſt ſections; but in the third are united into a cylinder, which proceeding from the receptacle of the calyx, ſurrounds the ſeed-bud, and attaches itſelf to the baſe of the petals, which it ſlightly unites. Silk cotton-tree has the appearance of ſeveral ſets of ſtamina ſo united; and, in the genus *pentapetes*, are interſperſed betwixt the fertile ſtamina, which are fifteen in number, five longer filaments that are coloured, erect, and caſtrated, that is, without anthers.

The ANTHERS, or tops, are frequently roundiſh, and placed erect on the filament; moſt commonly, however, they are oblong, or kidney-ſhaped, and ſlightly attached by the middle, or ſides, to the filaments, on which they turn like a vane, or needle. *Vide* ANTHERÆ *Incumbentes*, & *Verſatiles*.

This laſt is particularly the characteriſtic of all the mallow tribe.

Heliocarpus has twin anthers, or two upon each filament; chocolate nut, five.

In *kiggelaria*, the tops are perforated, and gape in two different places.

The SEED-BUD is generally roundiſh, or conic, and ſometimes, as in tea-tree, angular.

The genus *grevia* has its ſeed-bud furniſhed with a long foot-ſtalk, by which it is attached to a receptacle ſhaped like a pillar, erect, and cut into five angles at its brim.

From the ſummit of the ſeed-bud ariſe the ſtyles, which in this order are from one to five, thread-ſhaped, of the length of the ſtamina, and crowned with a *ſtigma*, which is generally thick, blunt, and ſometimes cornered.

Muntingia has a hairy ſeed-bud, no ſtyle, and a five cornered *ſtigma*, or ſummit.

In plants of the third ſection, which have a true claſſic character, the receptacle of the fructification, or that to which the flower and fruit are attached, is prominent in the centre of the flower. The ſeed-bud is erect, and ſurrounds the top of the receptacle in a jointed ring. The ſtyle forms one body with the receptacle below, but is generally divided above into as many branches, or threads, as there are cells, or partitions in the ſeed-bud. Each of theſe branches is crowned with a thin, ſpreading, and frequently hairy *ſtigma*.

The SEED-VESSEL is generally a capſule; ſometimes a pulpy fruit of the berry, or cherry kind. In plants of the third ſection, it is a woody, or membranous capſule, which is divided into as many cells internally, as there were partitions in the ſeed-bud. The capſule, in theſe ſame plants, is frequently formed by the union of ſo many proper coats, or coverings of the ſeed, called by Linnæus *arilli*. *Vide* ARILLUS.

The capſule of the lime-tree is divided into five cells; yet, as only one ſeed arrives at perfection, the reſt proving abortive, we might be apt, without previouſly viewing them in the ſeed-bud, to commit a miſtake, and conclude that the capſule was furniſhed with only one cavity. A ſimilar abortion ſometimes takes place in the genus *triumfetta*, which has a round

a round capſule, armed on every ſide with ſtrong hooked prickles.

Tree-montia has a hooked ſeed-veſſel of the ſame kind.

The ſeed-veſſel of the genus *hibiſcus*, is generally a capſule; in a particular ſpecies, called by Linnæus *hibiſcus malaviſcus*, it is a roundiſh berry, with five cells containing ten ſeeds. *Stewartia*, according to the ſame author, has a dry ſeed-veſſel, of the apple kind.

In tea-tree, and hermannia, the capſule ſplits at the top; in lime-tree, at the baſe. The woody capſule of Ethiopian ſour gourd does not ſplit, or open at all.

The SEEDS are generally ſolitary; ſometimes angular, and, in plants of the laſt ſection, kidney-ſhaped.

Theſe plants are mucilaginous, and lubricating.

The lime-tree contains a gummy juice, which being repeatedly boiled and clarified, produces a ſubſtance like ſugar. Arnotto is bitter, and aromatic. The freſh, or green leaves of tea, according to Kæmpfer, are diſagreeably bitter, narcotick, and injurious to the brain and nerves; but theſe bad qualities are entirely deſtroyed by the preparation which they undergo before they are expoſed to ſale.

Applied externally, theſe plants, particularly thoſe of the laſt ſection, are highly emollient; taken internally, they correct acrid humours, allay exceſſive heats in the blood, internal inflammations, irritations, and heat of urine; and are of great benefit in the cough, ſtrangury, ſtone, and cholic.

The ſeeds of arnotta, within their capſule, are covered on the ſurface with a reddiſh powder, or duſt, with which the American Indians paint their bodies. This powder, ſaid to be uſed ſometimes as an antidote againſt poiſon, is taken off by ſteeping the ſeeds in hot water, until it has totally ſubſided; the water being then poured off, the ſediment is left to harden, and afterwards made up in balls, which are ſent to Europe, for the uſe of dyers, and painters.

The leaves of common Jew's-mallow, the *olus judaicum* of Avicenna, are uſed in the Eaſt Indies, and by the Jews about Aleppo, as a pot-herb. *Rauwolf's Travels.*

An infuſion of the flowers of the lime-tree has been uſed with ſucceſs in an epilepſy. The timber, which is too ſoft for any ſtrong purpoſes, is principally employed by the carvers, and turners, as likewiſe by architects, for framing the models of their buildings. The flowers of the Carolina lime-tree emit a very fragrant odour, and are conſtantly haunted by bees during their continuance.

The Negroes of Senegal, in Africa, put a very high value on a decoction of the bark of a ſpecies of *Grevia*, which they call *Kell*, and conſider as a never failing ſpecific in venereal complaints.

The ſcrew-tree derives its name from the figure and appearance of the fruit or ſeed-veſſel, which is compoſed of five capſules that are cloſely and ſpirally twiſted over one another like a ſcrew; they are hairy, and conſiſt each of one cell incloſing ſeveral kidney-ſhaped ſeeds.

Proſper Alpinus, in his Hiſtory of Egyptian Plants, deſcribing Ethiopian ſourgourd, by the name of *Baobab*, affirms that the much celebrated Lemnian Earth, was nothing elſe than a preparation of the powder of the fungous and ſour pulp, ſurrounding the ſeeds of that tree, which M. Adanſon aſſerts had been tranſported from Senegal into Egypt, by the Arabs. Be that as it may, we are aſſured from very good authority, that the powder in queſtion is very much uſed at this day, both in decoction and infuſion, not only in Cairo, but in all parts of the Levant, for thick, ſizy blood, diarrhœas, peſtilential and putrid fevers, and diſorders ariſing from ſimilar cauſes. At Senegal, this powder is applied to the ſame purpoſes; as is likewiſe that of the leaves of the tree, a quantity of which the Negroes mix every day in their food. To this laſt powder they have given the name of *Lalo*.

The age of this tree is, perhaps, not leſs remarkable than its enormous ſize. M. Adanſon relates, that in a botanical excurſion to the Magdalen Iſlands, in the neighbourhood of Goree, he diſcovered ſome calabaſh-trees, from five to ſix feet diameter, on the bark of which were engraved, or cut to a conſiderable depth, a number of European names. Two

of

of theſe names, which he was at the trouble to repair, were dated, one the fourteenth, the other the fifteenth century. The letters were about ſix inches long, but in breadth they occupied a very ſmall part only of the circumference of the trunk: from whence he concluded, they had not been cut when theſe trees were young. Theſe inſcriptions, however, he thinks ſufficient to determine pretty nearly the age which theſe calabaſh-trees may attain; for, even ſuppoſing that thoſe in queſtion were cut in their early years, and that the trees grew to the diameter of ſix feet in two centuries, as the engraved letters evince, how many centuries muſt be requiſite to give them a diameter of twenty-five feet, which, perhaps, is not the laſt term of their growth!

The inſcribed trees, mentioned by this ingenious Frenchman, had been ſeen in 1555, almoſt two centuries before, by Thevet, who mentions them in the relation of his Voyage to Terra Antarctica, or Auſtralis. Adanſon ſaw them in 1749.

The ſilk cotton-tree (*Bombax*) is a native both of the Eaſt and Weſt Indies, and takes its name from the fine ſilky down with which the ſeeds are wrapped within the capſule, and which, in different ſpecies, is of different colours, and in different degrees of eſtimation. The dark ſhort down, or cotton, is ſeldom uſed, except by the poorer ſort, for ſtuffing pillows or chairs; being generally eſteemed unwholſome to lie upon. By the inhabitants of the Spaniſh Weſt Indies, the beautiful purple down is ſpun, wrought into cloaths, and wore, without being dyed of any other colour.

Large pirogues, or canoes fit to carry a ſail, are made both at Senegal, and in America, of the trunk of the ſilk cotton-tree, the wood of which is very light, and found unfit for any other purpoſe. In Columbus's firſt voyage, ſays Miller, it was reported a canoe was ſeen at the iſland of Cuba, made of the hollow trunk of one of theſe trees, which was ninety-five palms long, of a proportionable width, and capable of containing a hundred and fifty men. *Vide* Miller's Gardener's Dict. voce Bombax.

Boſman, in his Deſcription of Guinea, ſays, he has ſeen

one of theſe trees ſo widely diffuſed that 20,000 men, cloſely armed, might eaſily ſtand under the branches.

Cotton-wool is the produce of the ſmall, or ſhrubby cotton-tree. This plant grows in form of a buſh, and ſends forth branches that ſtretch wide, and are garniſhed with leaves ſomewhat leſs than thoſe of the ſycamore, but almoſt of the ſame ſhape. It bears a great many fine yellow large flowers compoſed of five petals, each of which is tinged at the bottom with a purple colour. The ſeed-bud, which is of the ſame colour, is placed in the middle of the flower. It is of an oval or conic ſhape, and grows in time to the ſize of a pigeon's-egg. When ripe, it becomes black, and ſplits into three or four partitions at top, diſcovering the cotton, or down, which infolds the ſeeds, and appears white as ſnow, in as many flakes as there are cells or internal diviſions in the capſule. In theſe flakes, which ſwell with the heat to a conſiderable bigneſs, are interſperſed ſeveral black ſeeds, as large as lupines, of a ſweet taſte, white within, oily, and adhering together.

The cotton, of which, in the Eaſt Indies, they make their fineſt calico, is too well known to require a farther deſcription. Suffice it to obſerve with Mr. Hughes, in his Natural Hiſtory of Barbadoes, that indulgent Providence has ſufficiently ſupplied the want of wool, denied to the ſheep in the warmer climates, by cauſing a vegetable, in ſuch countries, to bear the fineſt wool in the world.

The certainty of gathering a good crop of this kind, is very precarious; ſince it may be almoſt literally ſaid of this ſhrub, that in the morning it is green, and flouriſhes; and almoſt in the ſame evening, withers, and decays. For when the worms begin to prey upon a whole field of cotton-trees, though they are at firſt ſcarce perceptible to the naked eye, yet, in three days, they will grow to ſuch a ſize, and prove ſo deſtructive, as to reduce the moſt verdant field, thickly and beautifully cloathed with leaves and flowers, into almoſt as deſolate and naked a condition as trees are in the month of December, in England. When theſe worms, which are of the caterpillar kind, have attained their full growth, they ſpin, and inwrap themſelves as in a bag, or web,

like

like ſilk-worms, in the few remaining leaves, or any other covering: and after a few days reſt in this their Aurelia-ſtate, turn into dark-coloured moths and fly away.

Cotton-flowers, if carefully wrapped up in the leaves of the ſame tree, and baked, or roaſted over a fire of burning coals, yield, ſays Pomet, a reddiſh viſcous oil, that quickly cures old ſtanding ulcers. Of the black ſeed an oil may be made, which beautifies the face, removes ſpots and freckles, and poſſeſſes the ſame virtues with the oil of cokar-kernels. The cotton, or down itſelf, is ſaid to do wonders in the gout, by being burnt upon the part; but its efficacy can be no other than that of fire, or quick-lime; whatever good attends this practice being wholly owing to the burning.

The flowers of the China roſe, *hibiſcus mutabilis*, (ſo termed by Linnæus from the circumſtance to be mentioned), alter remarkably in their colour. At their firſt expanſion, they are white; they then change to a deep red, or roſe colour, which, as they decay, turns to a purple. In the Weſt-Indies, where it goes by the name of Martinico roſe, all theſe alterations happen in the courſe of one day; which, in thoſe hot countries, is the longeſt duration of the flowers in queſtion; but in England, where they continue near a week in perfection, the changes are not ſo ſudden.

Tree vervain mallow of Java, another ſpecies of *hibiſcus*, the *Roſa ſinenſis* of Linnæus, produces double flowers, compoſed of ſeveral roundiſh petals of a red colour, which expand like the common roſe. With theſe flowers, the women on the coaſt of Malabar, where the plant naturally grows, tinge their hair and eye-brows of a black colour, which will not waſh off; the Engliſh reſiding on the ſame coaſt, uſe it for blacking their ſhoes, and thence have named it ſhoe-flower. The green leaves, whiſked in water, make a lather like that which is made with ſoap; and, as we are informed by Kolben, are preferred to that ſubſtance for waſhing the hands and face, by the Europeans at the Cape of Good Hope, where the plant has long been introduced from India.

The leaves of a North American ſpecies of *hibiſcus*,

termed by Linnæus *Moſcheutos*, from a very probable conjecture that it is the *Moſcheuton* or true roſe-mallow of Pliny, are ſoft, and in figure reſemble thoſe of the maple. The flower is very large, and white, and ſeated not on the peduncle, but petiole or foot-ſtalk of the leaves, like that of *Turnera ulmifolia*. The root employed in medicine, ſays Clayton, has a paregorick or pain-alleviating quality.

A ſpecies of *Hibiſcus*, the *populneus* of Linnæus, the *Novella* of Rumphius, the *Bupariti* of the *Hortus Malabaricus*, is termed, by the natives of Ceylon, Surighahas, that is, Sun-Tree. The flowers, which, as others of the ſame genus, are ephemeral, have a dingy gloomy colour at the riſing of the ſun, when they expand; but acquire a reddiſh hue at its ſetting, when they fall off.

The fig-leaved *hibiſcus* is cultivated by the inhabitants of the Weſt-Indies for its pods, which, having a ſoft viſcous juice, add a thickneſs to their ſoups, and render them palatable.

The fruit of the okra, the *Hibiſcus eſculentus* of Linnæus, is taken, when young and tender, and boiled, and eaten with butter. The plant itſelf is of a very mucilaginous nature, a great reſtorative, very wholeſome, and extremely lubricating. It is perhaps the plant which the Romans valued ſo much, and Horace ſo well characterizes by the name of *levis malva*, or light mallow, which proves of eaſy digeſtion, and lightens the ſtomach *.

A thimble full of the ſmall browniſh ſeeds of a ſpecies of hollyhock, or tree-mallow, deſcribed by Hughes, in his Natural Hiſtory of Barbadoes, taken inwardly, proves an excellent purge; and the yellow juice that plentifully diſtils from the ſtalk when broken, is a ſovereign remedy to cure old ulcers.

A decoction of the roots of a ſpecies of *napæa*, called by the Negroes *laſs*, is deemed a ſovereign remedy in the vene-

* ——— ——— "*Me paſcunt olivæ,*
Me cichorea, LEVESQUE MALVÆ."
Carm. Lib. I. Od. 31.

real

real diſeaſe, which they are ſaid to cure without any bad conſequences, by means of this plant alone.

Note. The name of the genus *Napæa*, is derived from the Greek νάπη, *ſaltus*, *lucus*, *vel vallis*, a grove, or valley, and expreſſive of the places where the plants which compoſe it are generally found. In the Mythology of the Poets, the Nymphs, who preſided over ſuch retreats, were called *Napæae*.

In the parts of the fructification of the genera *Adanſonia* and *Bombax*, there is a remarkable affinity. They, indeed, principally differ in the ſeeds, which, in the firſt genus, are involved in a friable pulp; in the latter, covered with the ſoft, ſilky ſubſtance, from which it has obtained both its ſcientific and Engliſh names.

Common marſh-mallow, the *althæa officinalis* of Linnæus, is an herbaceous perennial, which grows naturally in moiſt places, in ſeveral provinces of England, France, Holland, and in Siberia. The juice is inſipid to the taſte, and, in the roots, mucilaginous. The herb, flowers, and root, which laſt is one of the five emollients, are employed in medicine. They are eſteemed balſamic and pectoral, and frequently ordered in fomentations to eaſe pain, as likewiſe to ſuppurate tumours and impoſthumes. The ſeeds are rarely uſed. Marſh-mallow may be diſtinguiſhed from the tribe of common-mallow, principally by the ſoftneſs and length of the leaves.

From the bark of moſt plants of the mallow-tribe, may be procured a ſort of hemp, which, if properly managed, might be wrought into cordage, or indeed into fine ſtrong thread of any ſize.

The inhabitants of the Weſt-Indies cut the Indian mallows, *ſida*, in the ſame manner as we do heath, and make them up into brooms for ſweeping. Hence they are frequently ſent into Britain by the title of broom-weed. A cataplaſm of the pounded leaves of the ſame plant is reckoned an excellent vulnerary.

I conclude this article of the pi[illegible]r-ſhaped-flowers, with a ſhort hiſtory of the Tea-plant, its culture, growth, preparation,

paration, and uſes, from the accurate deſcription of Kæmpfer, in his Natural Hiſtory of Japan.

This ſhrub, formerly deſcribed by Dr. Breynius, in his Century of Exotic Plants, publiſhed at Dantzick, in 1678, is of a very ſlow growth, and diminutive ſize. It has a black, woody, irregularly branched root. The riſing ſtem ſoon ſpreads into many irregular branches, and twigs. Theſe, at the lower end, and near the ground, often ſeem to be more in number than they really are; for ſeveral ſeeds being put together in one hole, it frequently happens that two, three, or more ſhrubs grow up together, and ſo cloſe to one another, as to be eaſily miſtaken for one, by ignorant, or leſs attentive obſervers. The bark is dry, thin, weak, cheſnut-coloured, firm, and adheres cloſely to the wood. It is covered with a very thin ſkin, which being removed, the bark appears, of a greeniſh colour, bitter nauſeous and aſtringent taſte, with a ſmell much like the leaves of hazelnut tree, only more diſagreeable and offenſive. The wood is hard, fibrous, of a greeniſh colour inclining to white, and of a very offenſive ſmell, when green. The pith is very ſmall, and adheres cloſe to the wood. The branches and twigs are ſlender, of different ſizes, irregularly beſet with ſimple leaves ſtanding on very ſmall, fat, green foot-ſtalks, and reſembling, when full grown, the leaves of the garden cherry-tree; but when young, tender, and gathered for uſe, thoſe of the common ſpindle-tree, the colour only excepted. The leaves are ſmooth on both ſides, cloſely and unequally ſawed on the edge, of a dirty dark green colour, which is ſomewhat lighter on the back, where the nerves being raiſed conſiderably, leave ſo many hollows, or furrows on the oppoſite ſide. They have one very conſpicuous nerve in the middle, which is branched out on each ſide into five, ſix, or ſeven thin tranſverſe ribs, of different lengths, and bent backwards, near the edges of the leaves: between theſe tranſverſe ribs, run a number of ſmall veins. The leaves, when freſh, have no ſmell at all, and though aſtringent and bitteriſh, as we obſerv[illegible] above, are not nauſeous, as the bark. They differ very much in ſubſtance, ſize, and ſhape,

according to their age, and the ſituation and nature of the ſoil in which the ſhrub is planted. From the wings of the leaves come forth the flowers in autumn. Theſe continue to grow till late in winter, and are compoſed of ſix petals, one or two of which are generally ſhrunk, and fall far ſhort of the largeneſs and beauty of the others. The foot-ſtalk of the flower is about half an inch long, and ends in ſix very ſmall green leaves, which ſerve inſtead of the calyx, or flower-cup. This deſcription, applied by Kæmpfer to the ſhrub, which, as he pretends, produces all the different ſorts, or preparations of tea, correſponds, ſays Linnæus, to a particular ſpecies only, termed by him Bohea; for ſome tea plants, he obſerves after Dr. Hill, produce flowers compoſed of nine petals, which muſt therefore conſtitute a diſtinct ſpecies from ſuch as have only ſix. From this circumſtance is conſtructed the other ſpecies of that author, *thea viridis*, or green tea, the flowers of which have always nine petals.

To proceed in our deſcription. Within the petals, which are of a very unpleaſant bitteriſh taſte, are placed many white ſtamina, exceedingly ſmall as in the wild roſe, with yellow heads in ſhape not unlike a heart. Kæmpfer reckoned in one flower, two hundred and thirty of theſe ſtamina. To the flowers ſucceed the fruits in great plenty; theſe are compoſed of one, two, but moſt commonly of three capſules, of the bigneſs of wild plumbs, adhering, like the ſeed-veſſels of the palma chriſti, to one common foot-ſtalk as to a centre, but divided into three pretty deep partitions. From this character, we may ſee how improperly Linnæus has placed the tea-tree in the natural order we have been deſcribing, when the ſtriking circumſtance of its tricapſular fruit ſeemed ſo naturally to point out its connection and affinity with thoſe plants which poſſeſs the ſame remarkable character. *Vide* TRICOCCÆ. Each capſule contains a huſk, nut, and ſeed. The kernel, or ſeed, is reddiſh, of a firm ſubſtance like filberds, contains a great quantity of oil, and is very apt to grow rank, which is the reaſon why there are ſcarce two in ten that will germinate when ſown. The

natives

natives make no manner of uſe of either the flowers, or kernels.

The ſhrub muſt be, at leaſt, of three years growth, before the leaves, which it then bears in plenty, are fit to be pluck-ed. In ſeven years time, or thereabouts, it riſes to a man's height; but as it then grows ſlowly, and bears but few leaves, the natives generally cut it down quite to the ſtem, after having firſt gathered what few leaves it produced. The next year, out of the remaining ſtem proceed many young twigs and branches, which bear ſuch abundance of leaves, as ſufficiently compenſates for the loſs of the former ſhrub. Some defer the operation of cuting down to the ſtem, till the ſhrub is of ten years growth.

The leaves muſt not be tore off by handfuls, but plucked carefully one by one, and are not to be gathered all at once, but at different times. Thoſe who pluck their ſhrubs thrice a year, begin their firſt gathering about the end of February. The ſhrub then bears but a few leaves, which are very tender and young, and not yet fully opened, as being ſcarce above two or three days growth. Theſe ſmall and tender leaves are reckoned much better than the reſt, and, becauſe of their ſcarcity and price, are diſpoſed of only to princes and rich people; for which reaſon they are called Im-perial tea, and by ſome the flower of tea. The ſecond gather-ing, and the firſt of thoſe who gather but twice a year, is made about the latter end of March, or beginning of April; ſome of the leaves are then already come to perfection, others are but half grown; both, however, are plucked off promiſcu-ouſly, though care is afterwards taken, previous to the uſual preparation, to arrange them into claſſes, according to their ſize and goodneſs. The third, and laſt gathering, which is alſo the moſt plentiful, is made in the end of May, when the leaves have attained their full growth, both in number and ſize. The leaves of this gathering are arranged in like manner as the former, according to their ſize and goodneſs, into different claſſes, the loweſt of which contains the coarſeſt leaves of all, being full two months grown, and that ſort which is commonly drunk by the vulgar.

The

The preparation of the leaves conſiſts in drying or roaſting them when freſh gathered, over the fire, in an iron pan, and rolling them when hot with the palm of the hand on a mat, till they become curled. The particulars of this preparation, as related by the ingenious author from whom this deſcription is extracted, are much too tedious for my purpoſe. The reader is therefore referred to the work itſelf. *Vide* Kæmpfer's Hiſtory of Japan, Vol. 2, Appendix 1.

The tea, after having undergone a ſufficient roaſting and curling, muſt, when cold, be put up, and carefully kept from the air. In this, indeed, the whole art of preſerving it chiefly conſiſts; becauſe the air, in thoſe hot climates, diſſipates its extremely ſubtile and volatile parts much ſooner than it would in our colder European countries. The Chineſe put it up in boxes of a coarſe tin, which, if they be very large, are incloſed in wooden caſes of fir, all the clefts being firſt carefully ſtopped both within and without. After this manner alſo it is ſent abroad into foreign countries. The Japaneſe keep their ſtock of the common tea in large earthen pots with a narrow mouth. The better ſort of tea, I mean that which the emperor himſelf, and the great men make uſe of, is kept in porcelain pots or veſſels which are ſuppoſed to improve its virtues. The coarſe tea of the third gathering is not ſo eaſily injured by the air as the other ſorts; for though its virtues are comparatively fewer, and leſs ſenſible, yet are they more conſtant and fixed. The country people keep it, as well as the other ſorts which they uſe, in ſtraw baſkets made like barrels, which they put under the roofs of their houſes, near the hole which lets out the ſmoak; being of opinion, that nothing is better than ſmoak to preſerve the virtues of the leaves, and even improve them. Some put it up with common mug-wort flowers, or the young leaves of a plant called ſaſanqua, which they believe renders it much more agreeable. Other odoriferous and aromatic ſubſtances are found, upon trial, to produce no ſuch beneficial effect.

The tea, as it is taken inwardly, is prepared in two different ways. The firſt, uſed by the Chineſe, and now all over

Europe, is nothing elſe but a ſimple infuſion of the leaves in hot water. The other way, which is peculiar to the Japaneſe, is by grinding. In this preparation, the leaves are, by means of a hand-mill made of a black-greeniſh ſtone, called ſerpentine ſtone, reduced into a fine delicate powder, which being mixed with hot water into a thin pulp, is afterwards ſipped. This tea is called thick tea, to diſtinguiſh it from the ſimple infuſion, and is drunk every day by the rich people and great men in Japan.

The narcotic quality of the freſh unprepared leaves of tea, mentioned above, is deſtroyed in a great meaſure, by a repeated and gradual roaſting. This operation renders it exhilarating, refreſhing, and cleanſing. Kæmpfer obſerves, that tea is particularly ſerviceable in waſhing away that tartarous matter, which is the efficient cauſe of calculous concretions, nephritic and gouty diſtempers; and affirms that among the great tea-drinkers of Japan, he never met with any, who were troubled with the gout, or ſtone.

The leaves of tea, ſay writers on the Materia Medica, are much more uſed for pleaſure than as medicine; the Bohea, however, is eſteemed ſoftening, nouriſhing, and proper in all inward decays; the Green is diuretic, carries an agreeable roughneſs with it into the ſtomach, which gently aſtringes the fibres, and gives them ſuch a tenſeneſs as is neceſſary for a good digeſtion. Improper, or exceſſive uſe, may, no doubt, render this, or any thing elſe, prejudicial; but, in general, there are very few herbs employed, either in food or medicine, which, uſed with moderation, are better, pleaſanter, or ſafer than tea.

After the moſt diligent enquiries that I have been able to make, I do not find that the tea-plant grows naturally beyond the thirty-fifth degree of north latitude towards the equator, on the one hand, and the forty-fifth degree towards the pole, on the other.

COMA, a buſh of hair; a collection of large *bracteæ*, or floral leaves, which, in crown imperial, lavender, ſage, cow-wheat, and ſome other plants, terminate the flower-ſtem, and form an appearance like a tuft or buſh of hair. *Vide* BRACTEA.

COMMUNES. The name of a claſs in Linnæus's *Methodus Calycina*, conſiſting of plants which, like teaſel and dandelion, have a calyx or flower-cup common to many flowers or florets. Theſe are the aggregate and compound flowers of other ſyſtems. *Vide* AGGREGATUS and COMPOSITUS *Flos*.

COMOSÆ, from *coma*. An order of plants in the former editions of Linnæus's Fragments of a Natural Method, conſiſting of the ſpiked willow, or ſpiræa frutex, drop-wort, and greater meadow-ſweet. Theſe, though formerly diſtinct genera, are now by Linnæus collected into one, under the name of *ſpiræa*. The flowers, growing in a head, reſemble a buſh or tuft of hair, which probably gave riſe to the epithet *comoſæ*.

COMPLETUS *Flos*, a complete flower. A flower is ſaid to be complete which is provided with both the covers, viz. the calyx or flower-cup, and the petals. *Vide* CALYX *and* COROLLA.

The term was invented by Vaillant, and is ſynonimous to *Calyculatus Flos*, in Linnæus. Berkenhout erroneouſly confounds it with the *auctus* and *calyculatus calyx* of the ſame author.

COMPOSITUS *Flos*, a compound flower; a flower formed of the union of ſeveral fructifications or leſſer flowers within a common calyx; each leſſer flower being furniſhed with five ſtamina, diſtinct at bottom, but united by the anthers into a cylinder, through which paſſes a ſtyle, conſiderably longer than the ſtamina, and crowned by a *ſtigma*, or ſummit, with two diviſions that are rolled backwards. Such are the eſſential characters of a compound flower.

The other properties are as follows:

1. The common receptacle, or ſeat upon which all the leſſer flowers are placed, is large, and entire, that is, undivided.

2. The leſſer flowers themſelves conſiſt univerſally each of one petal, which ſits upon the receptacle without any foot-ſtalk, and is of different figures in different genera.

3. Under

3. Under each floret, or partial flower, is generally placed a ſingle ſeed.

A compound flower receives different appellations from the figure of its monopetalous florets. When theſe are all hollow like a tube at the baſe only, flat in the middle, and expanded towards the top, the flower is ſaid to be *ligulated*, or *lingulated*; that is, compoſed of florets which reſemble a ſtrap, fillet, or tongue, (*Ligula*, *Lingua*.) This ſpecies of compound flower is termed by Ray, *Planipetalus*, and by Tournefort, *Semifloſculoſus*, from the ſemi-florets of which it is made up; and is exemplified in dandelion, hawk-weed, nipple-wort, and ſeveral others.

When all the florets are funnel-ſhaped, that is, hollow almoſt from bottom to top, the flower is termed by Linnæus *Tubular*, and by Tournefort *Floſcular*, to diſtinguiſh it from that compoſed of the ſemi-florets mentioned above.

Burdock, thiſtle, ſaw-wort, artichoke, baſtard-ſaffron, alpine colt's foot, and ſeveral other flowers, furniſh examples.

Tubular, or hollow florets, are florets properly ſo called.

Again, when a compound flower conſiſts of florets and ſemi-florets mixed together, *floſculis ligulatis & tubuloſis*, it is called, both by Tournefort and Linnæus, *Flos radiatus*, from the ſemi-florets which generally occupy the circumference, margin, or outward part of the flower, termed by Linnæus *Radius*, and reſemble the rays proceeding from the diſk, or body of the ſun. The centre of a radiated compound flower, termed by Linnæus *Diſcus*, is always compoſed of florets properly ſo called: the circumference, (*Radius*,) generally of ſemi-florets, as in milfoil; ſometimes, of tubular, or hollow florets unlike thoſe of the centre, as in blue bottle. In mugwort, and cudweed, the partial flowers in the circumference are naked; that is, want petals altogether.

The florets and ſemi-florets of a compound flower, are generally very numerous. In the following examples, they conſiſt of a determinate number.

Wild lettuce conſiſts of five ſemi-florets.

Hemp-agrimony with a fig-wort leaf, of twenty florets.

Hemp-

Hemp-agrimony with long ſage-like leaves, *eupatorium perfoliatum*, of fifteen.

Finger-leaved hemp-agrimony, of five.

Twining hemp-agrimony, of four.

The ſemi-florets in the circumference, or margin of a radiated flower, are commonly indeterminate in point of number. The following are exceptions.

Arctotis, has twenty.

Dwarf ſun-flower, twelve.

Tetragonotheca, and hard-ſeeded *chryſanthemum*, ten.

Tick-ſeeded ſun-flower, and African-ragwort, eight.

Milfoil, *eriocephalus*, baſtard-cudweed, *ſeriphium*, *ſigiſbeckia*, *melampodium*, *chryſogonum*, and African-marigold, have five.

The genus *milleria* has only one ſemifloret in the margin; generally two, and ſometimes four florets in the center.

The florets and ſemi-florets in compound flowers that are not radiated, are generally hermaphrodite, that is, have both male and female organs within the ſame cover.

In radiated flowers, the florets, which occupy the centre, are all hermaphrodite, or male; the ſemi-florets, which conſtitute the rays, or margin, are always female. *Vide* MASCULUS, FEMINEUS, and HERMAPHRODITUS *Flos*.

The eſſence of a compound flower, conſiſting, as we have ſaid, in the union of the *anthers* into a cylinder, the genus *kuhnia*, although very nearly allied to hemp-agrimony, and indeed, in every other reſpect, like a compound flower, is very properly referred, by Linnæus, to a claſs containing ſimple flowers, becauſe the anthers are ſeparate and diſtinct.

All compound flowers are aggregate. *Vide* AGGREGATUS *Flos*.

The common calyx, and common receptacle, though generally preſent in compound flowers, ſcarce enter into the number of eſſential characters. The former is wanting in globe-thiſtle; the latter in *milleria*.

Compound flowers which conſtitute the 12th, 13th, and

14th claſſes in Tournefort's Method, are all reduced to the claſs *Syngeneſia* in the Sexual Syſtem. *Vide* SYNGENESIA.

COMPOSITÆ. The name of a claſs in Hermannus, and Royen, as likewiſe of an order in Linnæus's Fragments of a Natural Method, conſiſting of plants which agree in the general characters above enumerated.

A particular deſcription of this order is given under the article *Syngeneſia*, which includes all the compound flowers. *Vide* SYNGENESIA.

The moſt accurate and complete obſervations on this difficult claſs of plants, are thoſe of Vaillant, and Pontedera, particularly the former, who confining his reſearches to that part of the vegetable kingdom, publiſhed his diſcoveries and method of arrangement in the Memoirs of the Academy of Sciences at Paris, from 1718 to 1722. This method, which conſiſts of four ſections, and is conſtructed from the diſpoſition of the flowers on the foot-ſtalks, includes not only the compound flowers properly ſo called; (I mean thoſe which anſwer to the deſcription given above,) but likewiſe all flowers which, like teaſel and ſcabious, form a head, and are contained within a common calyx, or flower-cup. The four ſections juſt mentioned, are ſubdivided into twenty-three ſubaltern ſections, from the figures of the common and proper calyx, and common receptacle; from the diviſion of the ſtem, or ſtalk; from the number and regularity, or irregularity of the petals; from the crown of the ſeeds; and from the ſubſtance of the fruit.

Pontedera, in one of his Botanical Diſſertations, divides, like Tournefort, the family of the compound flowers, which he terms *Conglobati*, into three claſſes; thoſe with ſemi-florets; thoſe with florets; and thoſe with a mixture of both. Theſe claſſes, which are ſubdivided into 24 ſections, from an attention to the figure of the common receptacle, and of the partial, or proper calyx of each leſſer flower, would have been true natural diviſions, if the author had not, like Vaillant, improperly introduced into the ſecond, ſcabious, teaſel, and blue daiſy, which are entirely foreign to the family of the compound flowers.

Thus

Thus we have ſeen, that former authors arranged the compound flowers, either from the manner in which they are ſupported on their foot-ſtalks, as J. Bauhin, Vaillant, Ray, and Johnſton; or from the figure and regularity, or irregularity of the petals, as Tournefort, Pontedera, and Rivinus. Linnæus, to preſerve the uniformity of his ſyſtem, has conſtructed his primary diviſions of the compound flowers, from the different ſexes of the florets, which he terms POLYGAMY. The ſubaltern diviſions are conſtructed from the figure of the petals, the diſpoſition of the flowers, the *pappus* or crown of the ſeed, the common receptacle, and other circumſtances, which characterize the ſubaltern diviſions in other authors.

CONCEPTACULUM, (from *concipio*) a receiver; a ſpecies of ſeed-veſſel, with one valve, which opens from bottom to top on one ſide, and has no future for faſtening, or attaching the ſeeds within it. This term occurs in the *Philoſophia Botanica*, and the other early works of Linnæus. In the *Delineatio Plantæ*, prefixed to the ſecond part of his Syſtem of Nature, and the lateſt editions of the *Genera Plantarum*, *Folliculus* is ſubſtituted in its place. *Vide* FOLLICULUS.

It is exemplified in roſe-bay, red jaſmine, Virginian ſilk, dog's-bane, and ſwallow-wort.

In this ſpecies of ſeed veſſel, the ſeeds are faſtened to a receptacle within the fruit, hence called the recepta c of the ſeeds. *Vide* RECEPTACULUM.

CONGLOBATUS *Flos*, (from *con*, in compoſition, together, and *globus*, a ball); growing together in form of a ſphere, or globe. Pontedera's term for the compound flowers of Tournefort and Linnæus; the flowers forming a head, (*capitati*,) of Ray. *Vide* COMPOSITUS *Flos*, &c.

CONGLOMERATI *Flores*, (from *con*, together, and *glomus*, a bottom of yarn). Flowers heaped or wound together; flowers that grow on a branched foot-ſtalk, to which they are irregularly, but cloſely connected. This mode of infloreſcence, as Linnæus terms it, is oppoſed to that in which the flowers are irregularly and looſely ſupported on

their foot-ſtalks, hence termed a diffuſe panicle. *Vide* PANICULA.

The term is exemplified in ſeveral of the graſſes, particularly in ſome ſpecies of *poa*, feſcue-graſs, and *agroſtis*. *Vide* GRAMINA.

CONGREGATÆ, (*congregare*, to gather together); the 15th claſs in Profeſſor Haller's Natural Method, conſiſting of plants which have a number of flowers placed within a common calyx, under each of which is placed a ſingle naked ſeed. It is exemplified in blue daiſy, ſcabious, and the compound flowers of Linnæus and other botaniſts. *Vide* COMPOSITUS *Flos*.

CONIFERÆ, (from *conus*, a cone, and *fero*, to bear); cone-bearing plants. The name of the fifty-firſt order, in Linnæus's Fragments of a Natural Method, conſiſting of plants, whoſe female flowers, placed at a diſtance from the male, either on the ſame, or diſtinct roots, are formed into a cone. In this character, the only one expreſſed in the title, the plants in queſtion ſeem to be nearly allied to the family of the moſſes, from which, however, they are eaſily diſtinguiſhed by their habit, as well as by the ſtructure of the male flowers in which the ſtamina are united below into a cylinder, and diſtinct at top.

The Genera *contained in this Order are ſeven*: viz.

Linnæan Genera.			*Engliſh Names.*
Cupreſſus	—	—	Cypreſs.
Ephedra	—	—	Shrubby Horſe-tail.
Equiſetum	—	—	Horſe-tail.
Juniperus	—	—	Juniper.
Pinus	—	—	Fir, Pine, Cedar, Larch.
Taxus	—	—	Yew-tree.
Thuja	—	—	Arbor-Vitæ.

The plants of this order are moſtly of the ſhrub and tree kind, and retain their leaves all the year. Horſe-tail is an herbaceous

herbaceous perennial; ſome ſorts of larch and fir-trees loſe their leaves during the winter.

The form of theſe plants is generally conic, and extremely beautiful, from the diſpoſition of the branches, which cover the ſtems even to the roots, and extend themſelves horizontally, and circularly, like ſo many rays.

The height of ſome ſpecies of horſe-tail does not exceed half a foot; that of ſome pines approaches to a hundred.

The roots are ſhort, branched, not very fibrous, and extend horizontally.

The STEMS and BRANCHES are cylindric.

The BARK is thin, and ſplit into ſhort ſlender ſcales.

The WOOD, except that of the yew-tree, poſſeſſes little hardneſs.

The BUDS are of a conic form, and naked, that is, without ſcales.

The LEAVES are entire, ſmall, and thick, frequently triangular, and generally pointed. Juniper has a prickly, or thorny leaf.

With reſpect to ſituation, they admit of great variety, being either alternate, oppoſite, placed in whirls round the ſtem, or collected into ſmall bundles, which proceed from a ſingle point. This laſt is particularly exemplified in the larch and pine-trees; in the former of which, ſix or eight leaves, in the latter, from two to five, are produced together all along the ſtem and branches, out of a very fine membranous ſort of ſheath. The firſt leaves, however, of theſe ſame trees, are ſingle, and without any ſheath, like thoſe of the fir and yew: the young branches too of the larch-tree, which emerge from the middle of the bundles, have their leaves ſingle in like manner.

The leaves are placed upon the branches without any ſenſible foot-ſtalk; in horſe-tail, and ſhrubby horſe-tail, they form a ſheath, or glove, round the ſtem.

Small STIPULÆ, or ſcales, are obſerved at the origin of the young branches of pine and fir-trees; and of the ſmall bundles of leaves of the larch.

Theſe plants, like the moſſes, are not covered with any ſort of pubeſcence, or down.

The FLOWERS in this order, are univerſally male and female. Theſe, in the fir, pine, larch, cypreſs, and arbor vitæ, are placed at a diſtance from each other, upon the ſame root; in the reſt, they are produced upon diſtinct plants. In the pine, fir, and larch trees, the male flowers are collected into a ſpike, or cone, at the end of the branches; in the other plants of this order they proceed ſingly from the wings of the leaves, or the termination of the branches.

The female flowers are generally collected into a cone; in yew-tree, and ſhrubby horſe-tail, they are ſingle, and terminate the branches.

The CALYX of the male flowers is a catkin; of the female, a cone.

The PETALS in this order are wanting; except in the female flowers of juniper, which have three rigid, ſharp, and permanent petals.

The STAMINA are in number from three to twenty, and upwards; united by their filaments into a cylinder, or pillar, which riſes out of the centre of the calyx.

The ANTHERS are erect, diſtinct, of a round form, and divided into internal partitions or cells, which, in the different genera, are in number from two to ten.

The SEED-BUDS, in this order, are generally numerous, and placed betwixt the ſcales of the cone, which ſerve for a calyx. From each ſeed-bud ariſes a very ſhort cylindrical ſtyle, crowned with a ſimple *ſtigma* of a conic form. Theſe plants have properly no fruit, or ſeed-veſſel; the ſeeds being naked, and involved only by the ſcales of the calyx. Theſe ſcales, which compoſe the cone, are in the pine, of a bony nature, and almoſt united; in the fir, larch, arbor-vitæ, and cypreſs, they are of a ſubſtance like leather; and in juniper they are united, and become fleſhy, and ſucculent like a berry. The calyx, or cone of ſhrubby horſe-tail, becomes likewiſe a kind of berry, with a ſlight opening at top, from whence are diſcovered its two acute, egg-ſhaped

ſeeds.

ſeeds. Laſtly, from the bottom of the calyx of the female flowers of yew, is produced a coloured ſucculent receptacle, which ſurrounds the greateſt part of a ſingle oblong ſeed, and is only open at top.

The SEEDS in this order, being nouriſhed, as in a ſeed-veſſel, by the ſcales of the cone, or common calyx, differ in nothing from the *germina*, or ſeed-buds. In pine, fir, larch, and arbor-vitæ, the ſeeds are hard like a ſtone, or nut, and crowned with a large, membranaceous wing of an oblong figure, contained within the ſcales of the cone.

Each ſeed is furniſhed with two covers; the external, hard, and bony; the internal, pulpy, of an oval form, white, very thick, and without any aperture.

The female flowers, and conſequently the fruit and ſeeds of the horſe-tail, a ſort of fern, have not yet been diſcovered. The fructifications of the male flowers being diſpoſed on the ſtalks, in form of a cone, poſſibly determined Linnæus to arrange the genus in this natural order.

Moſt of the cone-bearing plants are reſinous, or gummy. Theſe gums have a bitter taſte, but a very agreeable ſmell; witneſs the incenſe which proceeds from a ſpecies of juniper with yellow fruit. By cutting the trunk, and the largeſt branches of the common juniper, during the great heats, there flows a gum, called ſandarac, which is brought to us from Africa, where the trees grow very large, and in great quantities. This ſandarac is called by ſome, the Arabian ſandarac or varniſh; by others, the varniſh-gum, or gum-juniper, and is of more uſe to artiſts, than in phyſic.

From the larch-tree is extracted what we erroneouſly call Venice-turpentine. This ſubſtance, or natural balſam, flows, at firſt, without inciſion; when it has done dropping, the poor people who wait in the fir-woods, make inciſions at about two or three feet from the ground, into the trunk of the trees, into which they fix narrow troughs, about twenty inches long. The end of theſe troughs is hollowed, like a ladle; and in the middle is a ſmall hole bored, for the turpentine to run into a receiver, which is placed below it. As the gummy ſubſtance runs from the trees, it paſſes along the

ſloping gutter, or trough, to the ladle, and from thence runs through the holes into the receiver. The people who gather it, viſit the trees morning and evening, from the end of May to September, to collect the turpentine out of the receivers. When it flows out of the tree, Venice-turpentine is clear like water, and of a yellowiſh white; but, as it grows older, it thickens, and becomes of a citron colour. It is procured in greateſt abundance, in the neighbourhood of Lyons, and in the valley of St. Martin, near Lucern, in Switzerland.

From the wild pine, or pineaſter, is extracted the common turpentine, which is chiefly uſed by the farriers, and from which is diſtilled the oil of that name. The finer and more valuable part of the diſtillation comes firſt, and is called the ſpirit; what is left at the bottom of the ſtill, is the common reſin.

The pitch-tree, a ſpecies of fir, produces the ſubſtance from which it derives its name.

From the white and black ſpruce firs of North-America, oozes a fine clear turpentine, of a ſtrong ſcent, with which the native Indians are ſaid to cure green wounds, and ſome internal diſorders. That particularly of the firſt ſort, called by Charlevoix, *Epinette Blanche*, or white prickly fir, is affirmed to be a ſovereign remedy in fevers, and pains of the breaſt and ſtomach.

The large branches of the larch-tree, beſides its turpentine, produce ſeveral ſmall grains like ſugar, which poſſeſſing the purgative quality of manna, have likewiſe obtained its name.

Taken internally, theſe plants are aperient, ſudorific, diuretic, ſtomachic, and antiſeptic. An air impregnated with their balſamic exhalations, is reckoned very ſalutary to conſumptive habits.

Juniper berries, and the gum of the larch, give urine a fragrant ſmell like that of violets. The cones, or female heads of the cypreſs, improperly called cypreſs-nuts, are highly aſtringent. Juniper-wood is fragrant when burnt: for which purpoſe it is frequently uſed in houſes, to prevent peſtilential diſorders, and other infections.

Applied

Applied externally, the reſins, particularly thoſe of the pitch and larch trees, are anodyne, deterſive, and antiſeptic. By its bitterneſs, the oil of juniper effectually deſtroys worms. A decoction in milk, of the nuts or ſeeds of the wild pine, otherwiſe called pineaſter, or of the extremities of the branches pulled in ſpring, is ſaid, with a proper regimen, to cure the moſt confirmed and inveterate ſcurvy. A decoction of juniper-berries, is proper for fortifying the ſtomach; that of the wood is employed, like a decoction of ſaſſafras, to promote ſweat, and purify the blood. The ſame medicine, with crude antimony, cures that ſtage of the venereal diſeaſe in which the face is entirely covered over with ulcerous puſtules. Half an ounce of Venice-turpentine mixed in a clyſter, prevents a mortification in putrid and contagious dyſenteries. The ſame ſubſtance is ſpecific in ſuppreſſions of urine.

From the ſeeds or nuts of the cultivated pine, is drawn by expreſſion an oil, which is equal, in point of excellence, to that obtained from hazel-nuts. Theſe ſame nuts or kernels are frequently ſerved up in deſſerts, during the winter-ſeaſon, in Italy; formerly they were uſed in medicine in this country; but of late years, the piſtacia nuts have been generally ſubſtituted in their place. Of the ſoft white ſubſtance, commonly called *alburnum*, which, in trees, lies betwixt the wood and inner bark, the Swedes prepare a diſh that is eſteemed a great delicacy, and much uſed in ſpring. In times of ſcarcity a kind of bread is made of the bark. The natives of Siberia too, we are informed by Gmelin, make great culinary uſe of the *alburnum* of the young pines, which, for that purpoſe, they collect with care, dry, reduce into powder, and mix, as a pleaſing and ſalutary ingredient, in their common food.

Of juniper-berries, and the tops of the branches of a ſpecies of Canadian pitch-tree, is prepared a very ſafe and wholeſome wine.

The wood of the cone-bearing plants is, in general, tender, light, not liable to corrupt, and of a fragrant ſmell. That of the yew-tree is very hard, pliant, ſuſceptible of a good

poliſh, and poſſeſſes a red colour, which, for beauty, may vie with any of the foreign woods.

The white Canadian pines, ſays Charlevoix, ſhoot out, at the upper extremity, a kind of muſhroom, which the natives call *Guorigue*, and uſe with ſucceſs againſt diſorders of the breaſt, and in dyſenteries.

Of the four ſorts of Canadian firs, enumerated by the ſame author, the white prickly kind, and that called *La Peruſſe*, are excellent for maſts, eſpecially the firſt, which is alſo extremely fit for carpenter's work.

The ſort termed *La Peruſſe*, is gummy, but yields not a quantity ſufficient to be made uſe of; its wood remains long in the ground without rotting, which renders it extremely fit for paling, or incloſures. The bark is excellent for tanners, and the Indians make a dye of it, reſembling that of a Turkey blue.

The branches of the white and black ſpruce-firs, are uſed by the inhabitants of North America, in making the beer, hence commonly known by the name of ſpruce-beer.

The iſland of Cyprus, is ſaid to have received its name from the cypreſs-trees, which grow there in very great abundance.

The timber of the horizontal cypreſs, a native of the Levant, is ſaid to reſiſt worms, moths, and all putrefaction; and to laſt many centuries. The coffins in which the Athenians uſed to bury their heroes, were made, ſays Thucydides, of this wood, as were likewiſe the cheſts containing the Egyptian mummies. The doors of St. Peter's church at Rome were originally of the ſame material. Theſe, after laſting eleven hundred years, at the end of which time they diſcovered not the ſmalleſt tendency to corruption, were removed by the order of Pope Eugenius the fourth, and gates of braſs ſubſtituted in their place.

The ſame tree is by many eminent authors recommended as meliorating the air by its balſamic and aromatic exhalations; upon which account, many of the antient phyſicians of the eaſtern countries uſed to ſend their patients, who

who were troubled with weak lungs, to the iſland of Candia, where theſe trees grew in great abundance, and where, from the ſalubrious air alone, very few failed of a perfect cure.

In the ſame iſland, ſays Miller, the trees in queſtion were ſo lucrative a commodity, that the plantations were called *Dos Filiæ*, the felling of one of them being reckoned a daughter's portion.

Cypreſs, ſays Mr. Pococke, is the only tree that grows towards the top of Mount Lebanon, and being nipped by the cold, does not grow ſpirally, but like a ſmall oak.

The leaves of common ſavin, a ſpecies of juniper, are much uſed by farriers for deſtroying worms in horſes.

The red wood of Bermudas Cedar, the *Juniperus Bermudiana* of Linnæus, commonly known in England by the name of cedar wood, is uſed for making pencils, as likewiſe for wainſcoting rooms, and making ſtair-caſes. It is remarkable that the worms are never found to eat the bottoms of veſſels built with this wood, as they do thoſe built with oak; ſo that for purpoſes of traffic in the Weſt-India ſeas, cedar ſhips are preferable to all others; but they are not equally fit to be employed as ſhips of war; the wood being ſo brittle as to ſplit to pieces with a cannon-ball.

The peaſants in Switzerland make torches for burning, of the wood of a mountain pine, which grows naturally in that country, and is hence denominated the torch pine.

Cedar of Lebanon is the *Pinus Cedrus* of Linnæus, and the *Larix Cedrus* of Tournefort. The truth is, that this curious tree bears the leaves of the larch; but as the fir, pine, larch, and cedar, are all arranged by Linnæus, under the genus *Pinus*, he could not, without erecting a new genus, make the cedar, in any other reſpect connected with the larch, than as they were both ſpecies of the ſame genus.

The wood of this celebrated tree, which grows naturally on Mount Libanus, in Syria, and no where elſe, is accounted proof againſt all putrefaction of animal bodies; and ſaid to yield an oil, excellent for preſerving books and writings. It is thought by Lord Bacon, to continue ſound a thouſand years.

years. The ſtatue of Diana, in the famous temple at Epheſus, is affirmed to have been of this valuable material, as was moſt of the timber-work of that wonderful ſtructure. In the temple of Apollo at Utica, there was found cedar-wood near two thouſand years old.

The largeſt cedar, mentioned by Dr. Pococke, meaſured twenty-four feet in circumference.

For particulars concerning this curious plant, the reader is referred to Pococke's, Rauwolf's, Le Brun's, and Maundrel's Travels.

The wood of a pitch-tree with an erect fruit, which the natives of Provence term *Serento*, is preferred to every other, for making violins, and other ſtringed muſical inſtruments.

CONTORTÆ, (from *con*, together, and *torqueo*, to twiſt;) twiſted plants. The name of the thirtieth order in Linnæus's Fragments of a Natural Method, conſiſting of plants which have a ſingle petal that is twiſted or bent towards one ſide.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Plants with twiſted Flowers, having five Stamina, and one Style.

Linnæan Genera.			*Engliſh Names.*
Cerbera.			
Echites.			
Gardenia,	—	—	Cape Jaſmine.
Genipa.			
Macrocnemum.			
Nerium,	—	—	Oleander, or Roſe-Bay.
Periploca,	—	—	Virginian Silk.
Rauvolfia.			
Tabernæmontana.			
Vinca,	—	—	Periwinkle.

SECTION II.

Plants with twiſted Flowers, having five Stamina, and ſcarce any Style.

Apocynum,	—	—	Dog's-bane.

Aſclepias,

Linnæan Genera.			*Engliſh Names.*
Aſclepias,	—	—	Swallow-wort.
Cameraria.			
Ceropegia.			
Cynanchum,			
Plumeria,	—	—	Red Jaſmine.
Stapelia,	—	—	Succulent ſwallow-wort.

Habit and Structure of the Plants of this Order.

This order furniſhes trees, ſhrubs, and fat ſucculent plants, ſome of which retain their leaves during the winter. The herbaceous vegetables in this order are generally perennial.

The ROOTS are ſometimes branched; commonly fleſhy, and garniſhed with fibres, or ſtrings, like thoſe of turnep.

The STEMS are round, and in ſome genera, pulpy.

The BRANCHES are ſometimes placed alternate, ſometimes oppoſite. In *cynanchum*, *ceropegia*, and Virginian-ſilk, they are twiſted like thoſe of convolvulus to the left, in a direction oppoſite to the apparent diurnal motion of the ſun.

The BUDS are of a conic form, and naked, or without ſcales.

The LEAVES are ſometimes alternate, ſometimes placed oppoſite in pairs; and not ſeldom ſurround the ſtem in whirls. They are attached to the branches by a cylindrical foot-ſtalk, which is ſhort, and frequently united to the foot-ſtalk of the oppoſite leaf. In the genus *ſtapelia*, which conſiſts entirely of fat ſucculent plants, the leaves are nothing elſe than certain protuberances of a conic form, that are produced on the ſides of the branches, and ſpread open horizontally, ending in acute points. In ſome other genera of this order, when the ſtalks are very old, the leaves become ſo ſmall, as frequently to elude the ſight. At the origin of the foot-ſtalk of the leaves, in ſome ſpecies of dog's-bane, and ſwallow-wort, are produced two or three very ſmall *ſtipulæ*, or ſcales, on each ſide of the branches. Two pretty large

ſcales

ſcales of the ſame kind, are obſerved in ſome ſpecies of *tabernæmontana*.

The defenſive and offenſive weapons in this order are a downy ſort of pubeſcence, and ſimple, or forked prickles, which, in ſome genera, iſſue from the wings, or angles, of the leaves.

The FLOWERS are hermaphrodite, and ſtand either ſingly upon their foot-ſtalks, as in periwinkle; or are collected into umbels, and cluſters, (*corymbi*); as in *tabernæmontana*, and *cameraria*. Theſe bunches, or collections of flowers, ſometimes terminate the branches, as in red jaſmine; ſometimes proceed from the angles of the branches, or leaves, as in *tabernæmontana*, and *echites*; and ſometimes ſtand at the ſide of the wings, without iſſuing from them, as in ſwallow-wort, *ſtapelia*, Virginian-ſilk, and *cynanchum*.

The FLOWER-CUP is compoſed of one leaf divided almoſt to the baſe into five unequal ſegments which embrace each other, and are permanent; that is, accompany the ſeed-bud to its maturity.

In the genus *cerbera*, the flower-cup conſiſts of five diſtinct ſpreading ſpear-ſhaped leaves.

The COROLLA, or coloured inner cover of the flower, conſiſts of one petal, which in the different genera, is bell, ſalver, funnel, or wheel-ſhaped.

The LIMB, or upper ſpreading part of the petal, is generally divided into five equal parts, which are ſlightly bent or twiſted to the left, and embrace, or infold one another, like the petals of the mallow-tribe. *Vide* COLUMNIFERÆ.

The TUBE, or lower hollow part, is generally long, and cylindrical; ſometimes club-ſhaped, as in *cerbera*; and not ſeldom wanting, as in ſwallow wort, dog's-bane, Virginian-ſilk, and ſome others.

In ſeveral flowers of this order the petal is accompanied with a *nectarium*, which, however, in the different genera, aſſumes very different appearances. In oleander, it is a ſhort crown divided into a number of capillary ſegments, which

ſeem

ſeem rent and terminate the tube of the petal. In *ſtapelia*, it is a ſtar compoſed of five rays, with ragged points, which ſurround the organs of generation. In *echites*, and *tabernæmontana*, it conſiſts of five glands, which are placed round the *germen*, or ſeed-bud. In *cynanchum* it ſtands erect in the centre of the flower. In Virginian-ſilk, it is very ſmall, cut into five indentments, or teeth, at the brim, and ſurrounds the chaps, *faux*, of the petal. In dog's-bane, it is compoſed of five ſmall oval bodies, which riſe from the bottom of the flower, and ſurround the ſeed-bud. Laſtly, in ſwallow-wort, the *nectarium* is compoſed of five ſingular ear-ſhaped bodies, placed within the petals, from the bottom of each of which iſſues a ſharp horn, bent towards the parts of generation, and reſembling a filament without its top. Beſides this very ſingular appearance, the male and female organs are entirely eclipſed by means of a ſcaly covering which opens every way, and is termed by Linnæus, *corpuſculum truncatum*.

The STAMINA are five in number, ſhort, equal, attached at the ſame height to the tube of the petal, alternate with its diviſions, and oppoſite to thoſe of the calyx.

The ANTHERS are generally erect, and frequently approach ſo as to form a compact body in the middle of the flower. In oleander they are arrow-ſhaped, and terminated by a long thread. In dog's bane, they are divided in two at the baſe; and in *ſtapelia*, or ſucculent ſwallow-wort, they are ſlender, and faſtened on each ſide the filament.

Gardenia, and ſwallow-wort, have no filaments; in the latter the tops are inſerted into the ſcaly covering mentioned above.

The SEED-BUD is either ſingle, as in oleander, or double, as in periwinkle. In *genipa*, *gardenia*, and *macrocnemum*, it is placed below the receptacle, or ſeat of the flower. *Vide* GERMEN *inferum*.

The STYLE is wanting, or ſcarce perceptible in plants of the ſecond ſection; ſingle in thoſe of the firſt, and generally common to two ſeed-buds.

The

The STIGMA, or ſummit of the ſtyle is frequently double, as in periwinkle, and red jaſmine.

The SEED-VESSEL in ſome genera, is a pulpy fruit, of the berry and cherry kind; as in *genipa*, *rauvolfia*, and *cerbera*: but moſt frequently that ſpecies termed by Linnæus *conceptaculum*, and *folliculus*, which has one valve, or external incloſure, opens lengthways on one ſide, and has not the ſeeds faſtened to it. Two of theſe dry fruits with a ſingle cell, compoſe the ſeed-veſſel of moſt plants of this order.

The ſeed-veſſel in *gardenia*, is a dry berry; in *macrocnemum*, a capſule with two cells.

The SEEDS are generally numerous, and in ſeveral genera crowned with a long *pappus*, or downy wing, like that of the compound flowers, by means of which they eaſily diſperſe, and ſow themſelves. This down is particularly conſpicuous in dog's-bane, ſwallow-wort, *ſtapelia*, Virginian-ſilk, *echites*, and oleander.

The plants of this order being cut, emit a juice which is generally milky, as in dog's-bane; ſometimes of a greeniſh white, as in ſwallow-wort and periwinkle. From the circumſtance of their abounding in this milky juice, the greateſt part are deemed poiſonous; repeated obſervations having eſtabliſhed this aphoriſm, that milky plants, except thoſe of the plain compound flowers, as the dandelion, and nipple-wort, are generally of a baneful deſtructive nature, and ought, at leaſt, to be adminiſtered with caution. The moſt dangerous plants in this order are thoſe of the following genera, *rauvolfia*, *cerbera*, red-jaſmine, *tabernæmontana*, Virginian-ſilk, dog's-bane, *cynanchum*, and *ceropegia*.

With reſpect to their ſenſible qualities, they are bitter, particularly the ſeeds, roots, and bark, in which reſides their principal virtue. An infuſion of any of theſe parts in cold water, taken in very ſmall quantity, is innocent, and purgative; if the doſe is augmented, it becomes emetic; and if ſtill increaſed, mortal.

The milky juice which flows from the ſtalks and leaves of all the ſpecies of dog's-bane, is ſuppoſed to be hurtful, if taken

taken inwardly; but does not raiſe bliſters on the ſkin, as the juice of ſpurge, and other acrid plants. The down, or cotton, which ſurrounds the ſeed, is uſed in France for the ſtuffing of eaſy chairs, and making quilts, which being extremely light and warm, are a very proper covering for perſons afflicted with the gout.

A ſpecies of *Aſclepias*, commonly termed Egyptian dog's-bane with flowers growing in a ſpike, probably the *aſclepias gigantea* of Linnæus, grows plentifully near Alexandria, and produces a cotton or down which is uſed as fur, to adorn the robes of perſons of quality. The leaves of this plant, ſays Lemery, being ſtamped, and applied as a cataplaſm, are reckoned proper to reſolve cold tumours. The juice makes the hair come off; and, uſed externally, is a remedy for diſorders of the ſkin; but given inwardly, is a poiſon: for it purges with ſuch ſharpneſs and violence, as to cauſe bloody-fluxes that prove mortal. The leaves are a poiſon to dogs, wolves, ſheep, and other animals.

Common ſwallow-wort, another ſpecies of *Aſclepias*, which, from its ſuppoſed virtue, has obtained the names of *vincetoxicum*, Le Domte-venin, vincetoſſico, and tame-poiſon, all expreſſive of an imagined alexipharmic quality, is a perennial herb, which grows plentifully on ſandy mountains, and in the clefts of rocks in moſt parts of Europe; but, though a native of Sweden a more northerly climate, (as Linnæus particularly atteſts) has not yet, as far I can learn, been diſcovered to be an indigenous production of any part of Britain. The roots are acrid and bitter to the taſte, and though by many eſteemed, as the names juſt mentioned import, an excellent counterpoiſon, yet want not ſuſpicious marks of a very oppoſite and noxious quality. The freſh-gathered roots ſo much reſemble in their effects thoſe of apocynum, or common dog's-bane, that, according to Haller, they provoke vomiting. Linnæus likewiſe affirms, in his *Materia Medica*, that the roots of ſwallow-wort are poiſonous in a ſmall degree. By many they were much commended for their ſingular efficacy in promoting ſweats, and for other properties in various diſeaſes, particularly in malignant fevers, in which, the decoction of an

ounce in a pint of common water, was accounted to be preferable to ſcorzonera.—But as there are medicines which, in all ſuch caſes, may very properly be adminiſtered, and with, at leaſt, an equal chance of ſucceſs, it would, perhaps, be better, unleſs under the guidance of ſuperlative medical ability, to abſtain altogether from thoſe ſuſpected roots.—The plant, when froſt-bitten, is fed upon by horſes; at other times they refuſe it.

Greater Syrian dog's-bane, the *Apocynum Syriacum* of Cluſius, the *Aſclepias Syriaca* of Linnæus, is a biennial or perennial herb, which grows naturally in Syria and Egypt, as likewiſe in Virginia, and ſome other parts of North America. The white ſilky or downy ſubſtance which crowns the ſeeds, M. La Rouviere, an ingenious Frenchman of the laſt century, diſcovered the ſecret of ſpinning into regular balls like thoſe of ſilk; and in conſequence of his uſeful invention, obtained a patent or decree of council from the then French government, authorizing him to fabricate from this new prepared ſubſtance, velvets, flannels, and other ſtuffs.

The falſe or baſtard ipecacuanha, a poiſonous root brought out of America for the true ipecacuanha, and ſometimes unhappily adminiſtered as ſuch, is the root of a ſpecies of ſwallow-wort, termed by Linnæus, *aſclepias curaſſavica*. The two roots, however, may be eaſily diſtinguiſhed; that of the baſtard kind is compoſed of a great number of ſmall fibres; whereas the true plant of that name has jointed fleſhy roots, which run deep into the ground.

The wood of the ahouai, a ſpecies of *cerbera*, which grows naturally in Brazil, and the Spaniſh Weſt-Indies, ſtinks moſt abominably; and the ſeeds, or kernels, are a ſtrong emetic poiſon. The Indians know of no antidote to expel this poiſon, and are ſo cautious, that they never uſe the wood of the tree for fuel. The ſtones (for the fruit is of the cherry kind,) they employ in their dances to make a gingling ſound, like the ſmall ſhells of ivory, or hard wood, termed caſtanets, or ſnappers, uſed for the ſame purpoſe by dancers of sarabands in Spain, and other parts of Europe.

Another ſpecies of *Cerbera*, which grows plentifully in the

the Eaſt Indies, and is termed by Linnæus, after Bauhin and Ray, *Cerbera Manghas*, abounds with a cauſtic milk, which, notwithſtanding, if properly prepared, proves, ſays Burman, an excellent medicine in dropſical caſes, in which it operates both as an emetic and cathartic. The leaves of this plant are like thoſe of oleander; the flowers have the appearance and fragrance of jeſſamine; the fruit, in ſhape, reſembles a peach, and in colour, an orange.

Round-leaved Montpelier ſcammony, a ſpecies of *cynanchum*, abounds with a milky juice, which is of a purgative nature, and when concreted, has been frequently ſold for true Aleppo ſcammony.

All the ſpecies of roſe-bay, or oleander, are ſuppoſed to have a poiſonous quality; the larger branches, when burnt, emit a very diſagreeable ſmell, which generally indicates ſomething noxious. Galen relates, that the common oleander, taken internally, is deadly; and ſome late obſervations have evinced, that the water in which the leaves are macerated, is a mortal poiſon to ſheep. Notwithſtanding theſe facts, more noxious qualities have been aſcribed to this genus of plants than fall to its ſhare. The honey about Trebiſond is reckoned very unwholeſome; occaſioned, as ſome ſuppoſe, by the bees extracting it from the flowers of the oleander: but this is entirely a miſtake; for, Tournefort has fully informed us, that it is not from the flowers of oleander, but from thoſe of a ſpecies of chamærhododendros, the *azalea pontica* of Linnæus, that the noxious juice in queſtion is extracted.

Xenophon having related, in the fourth book of the Expedition of the younger Cyrus, that, "on the march of the Greeks from Upper Aſia, ſuch of the army as partook of the honey in a place near *Trapezus*, now Trebiſond, on the Euxine, where there was a great number of bee-hives, were affected with very diſagreeable ſymptoms, ſuch as vomiting, purging, and even inſanity; that not one was able to ſtand erect; that thoſe who had indulged but little in this pernicious dainty, ſeemed intoxicated; whilſt ſuch as had been more liberal in the uſe of it, either appeared frantic, or lay as dead; and that, in ſhort, though, about the ſame hour in the

following day, they had a partial recovery of their ſenſes, they were not, however, completely reſtored till ſome days after:"—M. Tournefort, in his Travels through the Leſſer Aſia, and eſpecially Pontus, the ſcene of this tranſaction, was led to pay particular attention to the narrative of the Greek Hiſtorian, and finding, upon minute enquiry, that the plant mentioned above, which he denominates *Chamærhododendros pontica, maxima, meſpili folio, flore luteo*, and which grows plentifully about Trebiſond, and the vicinity, produces the very effects related by Xenophon, and that violent head-achs are occaſioned even by its ſmell, he concludes, with the greateſt probability of truth, that the honey which proved ſo noxious a refreſhment to the Greek army, had been extracted by the bees from the plant in queſtion; and, in corroboration of his concluſion, adduces the teſtimony of Father Lamberti, a Miſſionary, who obſerves, that the honey collected by the bees from a certain ſhrub, which, from the deſcription given of it by Lamberti, Tournefort pronounces to be the medlar-leaved *Chamærhododendros*, and which grows commonly in *Colchis* or Mingrelia, a country adjoining to Pontus, is highly pernicious, and, in particular, excites vomiting. It is added by the Reverend Father, that the ſmell of the flowers of this ſhrub bears a great reſemblance to that of honey-ſuckle, but is much ſtronger. Memoires de l'Academie Royale des Sciences, 1704.

Dr. Haſſelquiſt, in his Travels to the Eaſt, ſpeaking of oleander, which grows in great abundance in Egypt and the Eaſtern countries, mentions not one ſuſpicious character, but aſſerts, on the contrary, that it poſſeſſes all the qualities of the tree of the righteous, commemorated by David in the firſt pſalm.

The bark of a ſpecies of Malabar oleander, termed codagapala by the natives, is mentioned by Adanſon, as a ſpecific in violent dyſenteries.

The milky juice of all the ſpecies of red jaſmine, (*Plumeria*,) is extremely cauſtic. If, in cutting off any of the branches of theſe plants, the knife is not immediately cleaned, the juice will ſuddenly corrode it, and in a very little time,

time, turn the blade almoſt black. The ſame ſubſtance dropped on linen, has the effect of the ſtrongeſt aqua-fortis.

The powdered bark of a ſpecies of African ſwallow-wort, termed by the natives *beidelſar*, mixed with charcoal of the ſame root, is an excellent cauſtic. An infuſion in cold water of this root is employed with ſucceſs againſt the bites of ſerpents, and other venomous creatures.

The tender ſhoots of *Aſclepias Syrica*, notwithſtanding the ſuſpicious nature of the plant, are ſometimes uſed for the kitchen, and prepared like Aſparagus. From the flowers, the French, when in poſſeſſion of Canada, where it grows in great abundance, extracted a ſugary ſubſtance, of a brown colour, and affirmed by Kalm to be very agreeable to the taſte. Theſe flowers, when in full bloom, impregnate the air with their fragrant exhalations, and render walking or travelling in the woods, eſpecially in the evening, peculiarly delightful. For the purpoſe of making the ſugar juſt mentioned, they muſt be gathered in the morning, when they are covered over with dew.

The milky juice of *Apocynum Androſæmifolium*, is ſaid to be noxious to ſome perſons, and harmleſs to others, a quality which has likewiſe been aſcribed to the *Rhus Vanix*, or poiſon-aſh. "I ſaw a ſoldier," ſays Kalm, in his Travels into North America, "whoſe hands were bliſtered all over, merely by plucking the plant in order to ſhew it me; and its exhalations, it is affirmed, affect ſome people when they come within reach of them. As for my part," he continues, "it has never hurt me, though, in preſence of ſeveral people, I have touched the plant, and rubbed my hands with the juice till they were white all over; and I have often rubbed the plant in my hands till it was quite cruſhed, without feeling the leaſt inconvenience. In general, however, the lacteſcent juice of this plant not only ſwells any part of the body on which it is ſpread, but frequently corrodes the ſkin."

Of the filaments of the ſtalk of *Apocynum Cannabinum*, the North American Indians make ropes, which they employ as bridles, and for fiſhing-nets. Theſe ropes are ſaid to be

ſtronger, and to keep longer in water, than ſuch as are made of common hemp. "On my journey," ſays Kalm, "through the country of the Iroquois, I ſaw the women employed in manufacturing this hemp. They made uſe neither of ſpinning wheels nor diſtaffs, but rolled the filaments upon their bare thighs, and made thread and ſtrings of them, which they dyed red, yellow, black, and of other colours, and afterwards worked them into ſtuffs, with conſiderable ingenuity." Sometimes the fiſhing tackle of the Indians conſiſts entirely of this hemp.

CONUS, (Gr. Κωνος,) a cone. A ſpecies of fruit or ſcaly ſeed-veſſel ſo termed by Tournefort, and other botaniſts. Linnæus has ſubſtituted STROBILUS in its place, which ſee.

CORCULUM, (a diminutive from *cor*, the heart); a little heart. The eſſence of a ſeed, and principle of life of the future plant, attached to and contained within the lobes. It conſiſts of two parts, termed by Linnæus *Plumula* and *Roſtellum*. The former is the *radicula* of Grew and other naturaliſts. *Vide* PLUMULA, and ROSTELLUM.

The *Corculum* is, in fact, the embryo of the future vegetable; and is attached by two trunks of veſſels to the lobes at their union. The firſt of its two parts mounts upwards, and becomes the trunk. The other ſtrikes into the ground, and is the rudiment of the root. The lobes and heart of the ſeed are diſtinctly viſible in the bean, and other ſeeds of that claſs, eſpecially after remaining ſome time in water, or earth. *Vide* COTYLEDONES, and GERMINATIO.

The principle of life is ſeated either at the ſummit or baſe of the ſeed. From this circumſtance are conſtructed the two firſt claſſes in Cæſalpinus's Method, containing trees and ſhrubs only.

COROLLA, (diminutive from *corona*, a crown); a little crown, chaplet, garland, or wreath:—Linnæus's name for the beautiful coloured leaves of the flower, which ſtand within the calyx, and are ſupported by it.

This conſpicuous and principal part of the fructification is defined to be the expanſion, or continuation, of the fine

inner bark of the plant, and conſiſts of two parts, the petal, and *nectarium*; the laſt of which, however, is rather a ſtriking ſuperfluity, or occaſional appendage, than a neceſſary part of every flower.

The petals, ſays Tournefort, are thoſe leaves which generally excel the other parts of the plant in beauty, and colour, and never, like the flower-cup, become a cover or veſſel to the ſeed.

Theſe characters ſerve in moſt caſes to diſtinguiſh the *corolla* from the *calyx*; but the petals, as in paſſion-flower, are not always coloured; and the tube of the petal, in the genus *ſelago*, incloſes, or involves, the ſeed. In ſuch doubtful caſes as theſe, we muſt have recourſe to a more certain mark of diſtinction; and it is this. The petals, and ſtamina, are always ranged alternately; the diviſions of the calyx and ſtamina are placed oppoſite. This rule determines with preciſion in ſuch flowers as want either the calyx, or petals. Thus, in pellitory, wild orach, and nettle, one of the two covers is wanting. Which is it? Am I to infer that the ſingle cover preſent is the *corolla*, becauſe the finer and more principal part? Nothing would be more erroneous than ſuch an inference; many flowers, as water-purſlane, *ruellia*, and bell-flower, which generally have both covers, are found occaſionally to loſe the petals, but never the calyx. How then am I to proceed? Apply the rule mentioned above. I do ſo, and finding the diviſions of the only cover that is preſent, to ſtand oppoſite to the ſtamina, I conclude that cover to be the calyx.

That the rule juſt mentioned is founded in the natural ſituation of the parts in queſtion will appear, by examining any number of complete flowers in the fourth and fifth claſſes of Linnæus's Sexual Method. In the former of theſe claſſes, the number four, in the other, the number five, is predominant; and, as both covers are preſent, the oppoſition and alternation alluded to, become diſtinctly viſible.

The petal, which, as we have ſaid, conſtitutes the principal part of the corolla, ſurrounds both organs of gene-

ration; and conſiſts either of one piece, as in lily of the valley; or of many, as in the tulip. In the firſt caſe, it is called a monopetalous corolla; in the ſecond, polypetalous, from the Greek numerals, μονος, *ſolus*, *unicus*, ſingle, and πολυς, *multus*, many, compounded with *petal*, a word of the ſame origin. A flower which has no petals, is termed by botaniſts, apetalous. *Vide* APETALUS *Flos.*

The lower hollow part of a corolla of one petal is called the tube; the upper ſpreading part, the limb; the opening of the tube, the chaps, or jaws, (*faux.*)

A bell-ſhaped flower, *corolla campanulata*, (*campana*, a bell,) conſiſts of one petal, which is regular, hollow like a bell, and nearly of the ſame width throughout. Of this kind are bind-weed, deadly night-ſhade, dog's-bane, and bell-flower. Linnæus affirms, that the bell-ſhaped petal wants the tube. I ſhould rather be inclined to aſſert, that it wants the limb, or upper ſpreading part; for if tube means any thing, it muſt mean ſomething hollow.

A funnel-ſhaped flower, *corolla infundibuliformis*, (*infundibulum*, a funnel,) has one regular petal, whoſe limb is ſhaped like a cone, and riſes from a long tube. Tobacco, oleander, thorn-apple, and hen-bane, furniſh examples.

A ſalver-ſhaped flower, *corolla hypocrateriformis*, (ὑπο, *ſub*, under, and Κρατηρ, *crater*, a bowl, goblet, or cup,) has a plain, or flat ſpreading limb ſtanding on a ſhort tube, as in periwinkle, baſtard lychnis, and *androſace*.

A wheel-ſhaped flower, *corolla rotata*, (*rota*, a wheel,) conſiſts of a ſingle regular petal, which, like the former, has a flat, or plain limb, but wants the tube altogether. This is exemplified in borage, looſe-ſtrife, pimpernel, and mullein.

A gaping-flower, *corolla ringens*, conſiſts of one irregular petal, ſhaped ſometimes like a maſque, as in birth-wort, and ſometimes terminated by a tube below, and divided into two lips above; as in lion's-tail, and dead nettle. The gap, or opening between the two lips, is termed by Linnæus, *rictus*, a gaping, or grinning. The upper-lip is wanting in germander.

Moſt

Moſt of the flowers in the claſs *Didynamia* of Linnæus are of the gaping kind.

The lower tapering part of each petal, in a flower conſiſting of many petals, is termed the claw, *unguis*; the upper ſpreading part, the *lamina*.

A croſs-ſhaped flower, *corolla cruciformis*, (*crux*, a croſs,) conſiſts of four petals that are nearly equal, and ſpread at top upon claws the length of the calyx, in form of a croſs. It is exemplified in ſtock gilly-flower, moon-wort, lady's-ſmock, candy-tuft, and the other flowers of the claſs *Tetradynamia* of Linnæus.

A pea-bloom, or butterfly ſhaped flower, *corolla papilionacea*, (*papilio*, a butter-fly,) is compoſed of four or five irregular petals; the uppermoſt of which reſembling a ſtandard, is, for that reaſon, termed *vexillum*; the lowermoſt, ſometimes divided in two, reſembles the keel of a ſhip, and is hence called *carina*; the two ſide petals, termed *alæ*, or wings, ſtand ſingle, involve the keel, and are generally furniſhed at their origin with two appendages reſembling ears.

The term is exemplified in pea, lupin, vetch, laburnum, and the other flowers in the claſs *Diadelphia* of Linnæus. Theſe flowers, from the nature of their fruit, were long denominated leguminous. Cordus was the firſt who diſtinguiſhed them by the name of papilionaceous, from their obvious reſemblance to a butter-fly.

Laſtly, an irregular flower properly ſo called, conſiſts of ſeveral irregular and diſſimilar petals, which are generally accompanied with a *nectarium*. Of this kind are the aconite, violet, fumatory, lark-ſpur, bee-flower, orchis, fraxinella, balſam, and ſome others.

The number of petals is determined from the baſe of the corolla; the number of ſegments, or diviſions, from the middle of the limb, or upper ſpreading part of the petal. Rivinus's rule on this head, is to reckon as many petals, as the parts into which the flower when it falls, reſolves itſelf. By this criterion, which ſeems, in general, to be very exact, are the flowers of wood-ſorrel, ſpeedwell, pimpernel, wild-roſemary, and *trientalis*, diſcovered to conſiſt of one

petal,

petal, though the diviſions are ſo deep, and ſlightly connected, that they aſſume the appearance of ſo many diſtinct petals.——Exception. The flower of *Vaccinium Oxycoccus* is reſolved into four diſtinct leaves, which formerly were one.

Tournefort reckons the flowers of the mallow-tribe monopetalous: Linnæus, pentapetalous.

Of polypetalous flowers, ſome conſiſt of two petals, as enchanter's night-ſhade, (*circæa*) and *commelina*; ſome have three, as Virginian ſpider-wort, and water-ſoldier; ſome four, as ſtock gilly-flower, and the other croſs-ſhaped flowers; ſome five, as marſh-marigold, pæony, and the umbelliferous flowers; others ſix, as tulip, lily, and May-apple; ſome nine, as tulip-tree, and a ſpecies of tea according to Dr. Hill; and ſome conſiſt of an indefinite number, as water-lily, and globe ranunculus.

Segments, or diviſions, are very frequent in flowers of one petal, which generally have their limb, or upper ſpreading part, cut into five. In flowers that have more than one petal, theſe diviſions are more rarely to be found. The following are among the moſt remarkable inſtances of this kind; chick-weed, and enchanter's night ſhade, have each petal divided in two; *holoſteum*, and *hypecoum*, in three; campion, in four; and baſtard-rocket, in five.

In reſpect to figure, the petals are either waved, as in ſuperb lily; plaited, as in bind-weed; rolled, or turned back, as in ſow-bread, and climbing African aſparagus; or twiſted and bent to one ſide, as in ſwallow-wort, oleander, periwinkle, Virginian-ſilk, and the other genera of the natural order *Contortæ*. *Vide* CONTORTÆ.

In *Trientalis*, the petals lie over one another like tiles; one ſide of each folding over the next towards the right. In gentian, the petals, before they are unfolded, lie over each other in a direction contrary to the ſun.

In reſpect to equality, the petals and ſegments are either equal, when the parts are regular and equal in figure, magnitude, and proportion, as in primroſe, *limoſella*, privet, lilac, and jeſſamine; unequal, when the parts anſwer in proportion,

portion, but not in magnitude, as in flowering-ruſh; or irregular, when the parts of the limb differ in figure, magnitude, or proportion, as in aconite, lupine, and dead-nettle.

The margin, or brim of the petals, is either ſawed, as in linden-tree, and water plantain; beautifully fringed, as in buck-bean, rue, and Indian creſs; notched, *crenata*, as in flax; jagged, or indented at the bottom of each diviſion, as in round leaved water pimpernel, and iron-wood; or covered with a fine downy hair, as in buck-bean, and a ſpecies of St. John's-wort.

In lily, thorn, and *brunsfelſia*, the corolla is very long; in *centunculus*, and currant-tree, very ſhort.

The baſe of the corolla is generally placed cloſe to the flower-cup; in a very few genera, as marvel of Peru, tuberous moſchatel, and greater wild burnet, the ſeed-bud is interjected betwixt them.

With reſpect to duration, the petals ſometimes fall off immediately after their expanſion, as in herb-chriſtopher, and meadow-rue; ſometimes wither on the ſtalk without dropping, as in bell-flower, orchis, cucumber, gourd, and bryony; ſometimes continue till the fruit has attained maturity, as in water-lily; but moſt commonly fall off with the ſtamina, and other parts of the flower, before the ripening of the fruit.

In all the plants where the calyx makes no part of the ſeed-bud, but is ſeparated from it, the corolla, when attached to the former, conſiſts of ſeveral diſtinct pieces; and the calyx is always of one leaf.

This aphoriſm being previouſly eſtabliſhed, ſerves to aſcertain the inſertion of the corolla in plants, where, as in the roſe, apple, and medlar, the calyx makes part of the ſeed-bud, and it is impoſſible to decide by the eye, whether the corolla is attached to the calyx, or the common receptacle. In ſuch caſes we muſt be guided by analogy; and if the flower conſiſts of many petals, conclude that they are inſerted, each by its claw, into the calyx; if of one petal only, into the common receptacle.

Among the moſt ſtriking ſingularities in the ſituation of the

the petals, may be reckoned that of eriocaulon, in which the corolla, as well as calyx, are placed under the ſeed-bud.

In aſſimilating the animal and vegetable kingdoms, Linnæus diſtinguiſhes the corolla by the name of *aulaeum floris*, (or curtains of the bed) in which the nuptials of the plant are celebrated. *Vide Phil. Bot.* p. 92.

In the different ſpecies of winter-green, tobacco, gentian, ſpeedwell, geranium, hyacinth, narciſſus, ſcabious, primroſe, buck-bean, andromeda, and whortle-berries, the petals differ conſiderably in point of figure.

Nor is this part of the flower, in plants of the ſame genus, more certain, with reſpect to number; ſome ſpecies of ranunculus, and hellebore, have five petals; others, an indefinite number; ſea-pink has generally five petals; a particular ſpecies has only one; ſome ſpecies of fumatory have two; others, four petals. In caſſava, and papaw, two exotic plants, a variation, in point of number, is obſerved in the ſame ſpecies.

Theſe varieties of the petals, with reſpect to figure and number, afford no deſpicable marks of diſtinction in diſcriminating the ſpecies; although it muſt be acknowledged, that being derived from a principal part of fructification, ſuch characters ought not, in ſtrict propriety, to be employed. Marks of this kind, however, are frequently made uſe of by Linnæus, though in direct contradiction to his own principles, which eſtabliſh, that the characters of the ſpecies ought to be taken from the parts that are totally unconnected with thoſe of fructification.

In gentian, ſays Linnæus after the learned Haller, the ſpecies cannot be diſtinguiſhed, without calling in the aſſiſtance of the flower, which is ſubject to conſiderable variations, being either bell, funnel, or wheel-ſhaped, and cut into four, five, or eight ſegments.

The African geraniums are diſtinguiſhed from the European plants of the ſame genus, not more remarkably by the union of the ſtamina, than by the irregularity of the petals.

From luxuriancy of nouriſhment, the petals are more ſubject to change, and conſequently leſs to be depended upon.

upon, than either the ſtamina, or calyx. Hence their multiplication in double flowers, which, though, in effect, ſo many monſters in the vegetable kingdom, attract the ſole attention of the floriſt, and furniſh ſuch exquiſite pleaſure by the beautiful variety of their colours. *Vide* PLENUS *Flos*, and MULTIPLICATUS *Flos*.

For a deſcription of the ſtructure, and ſingularities of the other occaſional appendage of the corolla, called by Linnæus, NECTARIUM, ſee the term itſelf.

COROLLISTÆ, from *corolla*. By this name Linnæus diſtinguiſhes thoſe ſyſtematic botaniſts, who have arranged vegetables from the regularity, figure, number, and other circumſtances of the petals, or coloured leaves of the flower.

The beſt ſyſtems of this kind are thoſe of Rivinus, and Tournefort. The former proceeds upon the regularity and number of the petals; the latter, with much more certainty, on their regularity and figure.

Rivinus's object was to find an easy, not a natural method; accordingly his ſyſtem is the moſt regular, I mean, deviates the leaſt from the principle with which he ſets out, of any that has yet been publiſhed.

The authors who have followed his method are,

Koenig, a German, in his ſecond part of the Vegetable Kingdom, publiſhed at Baſil, in 4to. in 1696.

Welſch, in his Baſis Botanica, publiſhed at Leipſic, in 1697.

Heucher, Profeſſor of Botany at Wittenberg, in his Hortus Wittembergenſis, publiſhed in 1711.

Ruppius, in his Flora Jenenſis, publiſhed in 1718. This ingenious botaniſt improved greatly upon Rivinus's Method, particularly in his arrangement of the compound flowers.

Chriſtian Knaut, in his Methodus Plantarum Genuina, publiſhed at Halle, in Saxony, in 1716. Knaut's method is that of Rivinus inverſed; the number of petals, not their regularity, being the leading principle. This botaniſt, among other dogmas equally ſingular, affirmed that all flowers are furniſhed with petals; and all ſeeds with a covering or veſſel.

Gemeinhart,

Gemeinhart, a German, in his Catalogus Plantarum circa Laubam, publiſhed in 1725.

Kramer, a German, in his Tentamen Botanicum, publiſhed at Dreſden in 1728, and reprinted at Vienna, in 1744.

Hebenſtreit, Profeſſor of Botany at Leipſic, in a work entitled, Diſſertationes ac Definitiones Plantarum, publiſhed at Leipſic, in 1731.

Ludwig, in his Definitiones Plantarum, publiſhed at Leipſic, in 1737. The claſſes in Ludwig's Method are thoſe of Rivinus. The orders or ſecondary diviſions are taken from Linnæus's Sexual Syſtem.

Wedel, in his Tentamen Botanicum, publiſhed in 1747.

M. Boehmer, in his Flora Lipſiæ indigena, publiſhed at Leipſic, in 1750.

The two laſt are profeſſed followers of Ludwig's Method.

Laſtly, Sigeſbeck, in his Botanoſophiæ verioris ſciagraphia, publiſhed at Peterſburg, in 1737.

Among the numerous authors who have followed the ingenious and accurate method of the celebrated Tournefort, are the following:

Sherard, an Engliſhman, who, in 1689, publiſhed at Amſterdam, a rude draught of Tournefort's Method, under the title of Schola Botanices. In this work, the plants are arranged according to the order of the Royal Garden at Paris.

Father Plumier, in his Nova Genera Plantarum Americanarum, publiſhed at Paris, in 4to, in 1705.

Falugi, an Italian, who deſcribed, in very elegant Latin verſe, all the genera of Tournefort, in a work intitled Proſopopœiæ Botanicæ, publiſhed at Florence, in 1705.

Marchant, Dodart, Niſſole, Juſſieu, and Vaillant, in the Memoirs of the Academy of Sciences at Paris, from 1700, to 1740.

Johren, a German, in his Vade Mecum Botanicum, publiſhed in 1710.

Barrelier and Feuillé, in 1714.

Valentine, a German, in his Tournefortius Contractus, publiſhed at Francfort, in 1715.

Ripa,

Ripa, an Italian, in a work entitled Hiſtoriæ univerſalis Plantarum conſcribendi propoſitum, publiſhed at Pavia, in 1718.

Dillenius, in 1719, in his Flora Giſſenſis.

Pontedera, in 1720.

Monti, in a work entitled Indices Plantarum varii, printed at Bologna, in 1724.

Micheli, in 1729.

Fabricius, a German, in a work entitled Primitiæ Floræ Butisſbacenſis, publiſhed in 1743.

Sabbati, in his Synopſis Plantarum circa Romam naſcentium, publiſhed in 1745.

Alſton, Profeſſor of Botany at Edinburgh, in his Tyrocinium Botanicum, publiſhed at Edinburgh, in 1753. To this work is prefixed a learned and ſenſible diſſertation, containing, amongſt other important doctrines, a comparative view of the reſpective merits of Tournefort and Linnæus.

To theſe may be added the immortal Boerhaave, who, deſirous to have a principal eye in his method, to the conſideration of the fruit, combined, in ſome meaſure, the different methods of Ray, Hermannus, and Tournefort.

Bernard de Juſſieu, a pupil of Tournefort's, is alſo a follower of his maſter's method.

COROLLULA, a diminutive from *corolla*, a little wreath, or crown. The name given by Linnæus to the partial petals or florets in a compound flower. Theſe are the *floſculi*, and *ſemifloſculi* of Tournefort. *Vide* COMPOSITSUS *Flos*, and SYNGENESIA.

CORONA, a crown. The name given by ſome botaniſts, to the circumference or margin of a radiated compound flower. It correſponds to the *Radius* of Linnæus, and is exemplified in the flat tongue-ſhaped petals which occupy the margin of the daiſy, and ſun-flower.

CORONA *Seminis*. *Vide* CORONULA.

CORONARIÆ, from *corona*, a wreath, chaplet, or garland.

The tenth order of plants in Linnæus's Fragments of a Natural Method. Under this name, inſtead of the more

obvious

obvious one *liliaceæ*, Linnæus collects a great number of Genera, moſt of which furniſh very beautiful garden flowers, proper for being formed into a garland, or floral crown, (*corona fiorea, Plaut.*)

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Liliaceous Plants with a bulbous Root.

Linnæan Genera.			*Engliſh Names.*
Albuca,	—	—	Baſtard-Star of Bethlehem.
Cyanella.			
Fritillaria,	—	—	Fritillary, and Crown Imperial.
Helonias.			
Hyacinthus,	—	—	Hyacinth.
Hypoxis.			
Lilium,	—	—	Lily.
Melanthium,	—	—	Star-Flower.
Ornithogalum,	—	—	Star of Bethlehem.
Scilla,	—	—	Squill.
Tulipa,	—	—	Tulip.

SECTION II.

Liliaceous Plants with fibrous, and tuberous or fleſhy Roots.

Agave,	—	—	American Aloe.
Aletris,	—	—	Baſtard Aloe.
Aloe,	—	—	Aloe.
Anthericum,	—	—	Spider-wort.
Aſphodelus,	—	—	Aſphodel, or King's-ſpear.
Bromelia,	—	—	Ananas, or Pine-apple.
Burmannia.			
Hemerocallis,	—	—	Day Lily, or Lily Aſphodel.
Polianthes,	—	—	Tuberoſe.
Tillandſia.			
Veratrum,	—	—	White Hellebore.
Yucca,	—	—	Adam's Needle.

Habit

Habit and Structure of the Plants of this Order.

Theſe plants are herbaceous and perennial, and from one inch to fifteen feet high. A low-growing ſpecies of ſpider-wort is annual.

The ROOTS are bulbous in plants of the firſt ſection; *Vide* BULBUS; fibrous, and compoſed of ſmall fleſhy knots, which are jointed at the top, in thoſe of the ſecond.

The bulbs in queſtion, either conſiſt of ſcales laid over each other like tiles, as in lily, hyacinth, ſtar of Bethlehem; or are ſolid, that is, have no ſcales, as in tulip.

The STEM of the liliaceous bulbous plants, is properly wanting; what ſupplies its place being nothing elſe than the baſe of the leaves, which wrapping, or enfolding each other, form at bottom a roundiſh fleſhy bulb, hitherto diſtinguiſhed, though perhaps improperly, by the name of root. In the other plants of this order, the ſtem is ſimple, that is, has few branches, and is either furniſhed with leaves, as in ſtar-flower; or riſes naked, as in moſt of the aſphodels, and aloes.

Note. A naked ſtem ariſing immediately from the root, is termed by Linnæus, *ſcapus*. *Vide* SCAPUS.

The genus *tillandſia* has a graſſy ſtalk. *Vide* CULMUS.

The BRANCHES are alternate, and cylindrical.

The LEAVES are ſimple, alternate, and undivided. Thoſe which are next the root, termed *radical leaves*, generally form at their origin a ſheath, which, in a great number, as tulip, ſpider-wort, white hellebore, aſphodel, aloe, and hypoxis, is entire; that is, goes all round; whilſt in others, as the lily, crown imperial, American aloe, tuberoſe, and ſquill, it is cleft, or divided longitudinally on one ſide. In lily, and crown imperial, ſome of the leaves are placed oppoſite, and ſome even in whirls round the ſtem.

The flowers are univerſally hermaphrodite, except in white hellebore, which has both male and hermaphrodite flowers mixed together on the ſame root.

The mode of inflorеſcence, or manner of flowering, in this order, is various. In tulip, the flowers are ſingle, and terminate the ſtem; in lily, ſtar of Bethlehem, and ſquill, they form a ſpike; in crown imperial, an umbel; and in

Adam's needle, and white hellebore, a panicle, or diffuſed ſpike. *Vide* SPICA, UMBELLA, and PANICULA.

The CALYX, or flower-cup, in this order, according to Linnæus, is generally wanting. In ſtrict propriety, however, the ſingle cover that is preſent in moſt of theſe plants, though beautifully coloured, ought to be denominated a calyx; as its diviſions, generally ſix in number, are placed oppoſite to the ſtamina. See the article COROLLA.

In pine-apple, tillandſia, and burmannia, which have both covers, the calyx is of one piece deeply divided into three ſegments.

The PETALS, or, to ſpeak more properly, the coloured leaves of the flower, are in number from one to ſix. Plants which, like aſphodel and tuberoſe, have a ſingle petal, have the limb, or upper part, ſplit into ſix diviſions. Burmannia, and pine-apple, have three petals.

The petals in ſome ſpecies of lily, as the martagon, are rolled, or turned back.

The NECTARIUM in this order is various: in the lily it is a longitudinal line, or furrow, which runs through each petal, and reaches from the baſe to the middle. In crown imperial, it is a ſmall hollow, or pore, formed at the baſe of each petal; in aſphodel, it conſiſts of ſix very ſmall valves, which approaching, form a globe, and are inſerted into the baſe of the petal; in hyacinth, it is compoſed of three melliferous pores, ſituated on the top of the ſeed-bud. In pine-apple, it is a ſmall ſcale lying within the ſubſtance of each petal, above the baſe; and in baſtard ſtar of Bethlehem, *albuca*, it conſiſts of two ſharp pointed bodies, proceeding from the furrows of the ſeed-bud, and covered by the broader baſe of the three fertile filaments.

In ſome ſpecies of lily, the nectarium is hairy; in others, it is naked.

The STAMINA, or threads, are ſix in number, erect, and inſerted into the common receptacle, if the flower conſiſts of many petals; into the tube, or diviſions of the corolla, if of one. In aſphodel, the filaments are bent like a bow, alternately long and ſhort, awl-ſhaped and attached

tached to the valves of the nectarium. The termination of the filament, in ſome ſpecies of ſtar of Bethlehem, is alternately divided in three; the middle ſegment ſupporting the anther. Five ſpecies of ſpider-wort have hairy, or downy filaments. In the genus *albuca*, the ſtamina are alternately barren, or caſtrated, that is, want the anthers; and in Adam's needle, the filaments are bent backwards.

The ANTHERS, or tops, are long, commonly divided below, and ſlightly attached by their ſides to the filaments on which they turn like a vane, or the needle of a compaſs.

The SEED-BUD is ſingle, and placed either within the flower-cup, as in the greateſt number; or below it, as in pine-apple, hypoxis, and American aloe.

The STYLE is ſingle, thread-ſhaped, and generally of the length of the petals. The tulip, and Adam's needle, have no ſtyle. In white hellebore, there are three ſeed-buds, which end in the ſame number of ſtyles.

The STIGMA, or ſummit of the ſtyle, is generally ſingle, of a conic form, and ſhaggy or hairy at the extremity. Burmannia, and white hellebore, have three ſummits.

The SEED-VESSEL is generally a capſule; divided externally into three valves, internally into three cells.

The fruit of the pine-apple is of the nature of a berry.

White hellebore has three capſules, each of which has a ſingle cell, and valves.

The SEEDS are numerous, flat, or round, and generally placed in two rows. In aloe, ſpider-wort, and aſphodel, they are angular. Hyacinth has only two roundiſh ſeeds.

With reſpect to the powers of the plants of this order, it may be affirmed, in general, that ſuch as have little taſte, or ſmell, as the roots of tulip, and ſtar of Bethlehem, are perfectly innocent; whilſt thoſe which have a heavy, nauſeous ſmell, as ſquill, hyacinth, crown-imperial, and ſpider-wort, are, at leaſt, ſuſpicious, and frequently prove noxious.

The aloe, and American aloe, which by former botaniſts had been conjoined, on account of their conformity in point of habit, are ranged as diſtinct genera by Linnæus, principally from this circumſtance, that in the former, the ſeed-

bud is placed within the petal, or flower; in the latter, below it. We may mention alſo another difference in the growth of the plants, by which they may be diſtinguiſhed before they flower. In American aloe, the flower-ſtem is produced from the centre of the radical leaves; and as theſe are cloſely folded over each other, it is evident that, until they are fully expanded, the ſtem is not at liberty to advance. Hence the common opinion, that theſe plants do not flower till they are a hundred years old, when the flower-ſtem riſes out of the centre of the leaves, produces its flowers, and, with the reſt of the plant, quickly dies. The time of its flowering, however, is not limited, but depends upon the growth of the plant, which is particularly affected by heat and cold.

In aloe, the flower-ſtem is produced on one ſide of the heart or centre of the plant, ſo riſes annually; the leaves too are always more expanded than thoſe of American aloe.

The mitre-ſhaped aloe, ſo termed from the figure of its leaves, is a kind of ſymbolic plant to the Mahometans, eſpecially in Egypt, and in ſome meaſure dedicated to the offices of religion; for whoever returns from a pilgrimage to Mecca, hangs it over his ſtreet-door, as a token of his having performed that holy journey. The ſuperſtitious Egyptians believe, that this plant hinders evil ſpirits and apparitions from entering the houſe; and on this account, whoever walks the ſtreets in Cairo, will find it over the doors both of Chriſtians and Jews. From the ſame plant, the Egyptians diſtil a water, which is ſold in the apothecaries ſhops at Cairo, and recommended in coughs, hyſterics, and aſthmas. An unexperienced French ſurgeon, ſays Haſſelquiſt, gave a Coptite, forty years old, afflicted with the jaundice, four tea-cups full of the diſtilled water of this ſpecies of aloe, and cured him in four days. This remedy, unknown to our apothecaries, is not difficult to be obtained, as the plant might eaſily be raiſed in the warm ſouthern parts of Europe. The Arabians call it *Sabbara*.

The under leaves of a ſpecies of aloe, termed by Linnæus, *aloe diſticha*, are of a dark green colour ſpotted with white, ſomewhat

ſomewhat reſembling the colour of ſoft ſoap, whence it is ſometimes diſtinguiſhed by the name of ſoap-aloe.

The name of pearl-aloe is given to a certain ſpecies, the leaves of which are cloſely ſtudded with white beautiful protuberances.

Of the leaves of the Guinea aloe, mentioned by Mr. Adanſon, in his Voyage to Senegal, the Negroes make very good ropes, not apt to rot in the water.

Dr. Sloane mentions two ſorts of aloe; one of which is uſed for fiſhing-lines, bow-ſtrings, ſtockings, and hammocks; the other has leaves which, like thoſe of the wild pine, and banana, hold rain-water, and thereby afford a very neceſſary refreſhment to travellers in hot countries, where there is generally a ſcarcity of wells and water.

The ſubſtance, known among druggiſts and apothecaries, by the name of aloes, is a thick, or inſpiſſated juice, drawn from the plants by expreſſion, or inciſion. Of this ſubſtance, there are three ſorts, which differ in purity, and were eſteemed by the generality of former botaniſts to be the produce of the ſame plant.

The manner of collecting and preparing the juice, is thus explained by J. Bauhin: having cut the herb in pieces, they bruiſe it, and ſqueeze out the juice, which they put up into a veſſel of a long and round ſhape, ſuffering it to ſtand for the ſpace of twenty-five days: in the mean while, they take care to clear off the uſeleſs ſcum, and throw it away; as alſo the upper part of the juice, until ſuch time as ſome difference appears in its colour and conſiſtence. The purer part of this juice, being concreted, is called ſuccotrine-aloes; the remaining part, being of a dark liver-colour, is called hepatick-aloes; and from the dregs, or ſettlings, is made that ſort called caballine, or horſe-aloes.

Notwithſtanding the contrary opinion of Columna, Bauhin, Ray, and other naturaliſts, we are now ſufficiently certain, that the three kinds of aloes juſt mentioned, are the juices of three different plants: the ſuccotrine, of the *aloe vera*, of Miller; the hepatic, of the *aloe vulgaris*, of Bauhin, *aloe Dioſcoridis et aliorum*, of Sloane, and *aloe barbadenſis*,

badenſis, of Miller; the caballine, of the *aloe Guineenſis caballina, vulgari ſimilis, ſed tota maculata*, of Commelin.

The fineſt, or pureſt, is the ſuccotrine aloes; ſo called, ſays Pomet, either becauſe the ſubſtance itſelf is a concreted juice, or, which is moſt probable, becauſe the beſt comes from Socotora, or Zocotra, an iſland in the ſtreights of Babelmandel. Succotrine aloes, when broken, is tranſparent; and when powdered, of a fine yellow golden colour, with a bitter taſte, and a ſmell like that of myrrh.

From the root, and leaves of the Weſt-India, or Barbadoes aloe, is prepared the ſecond ſort, called, from its colour, which is a dark red like that of a liver, hepatic aloes. This ſort, which is coarſer than the former, and ſeldom uſed in medicine except for horſes, is brought us in gourds or calabaſhes of different ſizes, and weight. It is clear, and not very fœtid in ſmell.

The third ſort, by much the coarſeſt, black, hard to break, and frequently adulterated, is called caballine aloes, becauſe, like the ſecond ſort, it is ſolely appropriated to the uſe of horſes. This ſort is generally ſold in the ſhops for the true hepatick aloes.

The month of March, ſays Mr. Hughes, in his Natural Hiſtory of Barbadoes, is the propereſt ſeaſon to make the aloes, which is done in the following manner: each Negro has by him, three or four portable tubs, into which the leaves are thrown, with their broken ends downwards. Theſe being full of large longitudinal veins, or veſſels, yield an eaſy paſſage to the juice, which is of a greeniſh yellow colour, to drip out. The juice being boiled for about five hours in a copper, or kettle, the watery particles evaporate; and the remainder comes to a conſiſtency, and thickens, as ſugar doth when ſufficiently boiled. The way to know when it is enough boiled, is to dip a ſtick in the liquor, and obſerve, whether the aloes ſticking to it, when cold breaks ſhort; if it does, then it is boiled to perfection, and fit to be poured into gourds, calabaſhes, or other veſſels for uſe.

Succotrine aloes, which is the only ſort now preſcribed in medicine, is ſeldom, or never adminiſtered in potion, by reaſon

reaſon of its extreme bitterneſs; but is often given in pills, being, in fact, the baſis of the greateſt part of the purgative pills now in uſe. The Francfort, or angelic pill, is entirely compoſed of it.

In the city of Goa, as Garcias relates, aloes well bruiſed, and mixed with milk, are preſcribed with ſucceſs to ſuch as are afflicted with ulcers in the kidneys or bladder, and void purulent urine.

The herbs which produce the three medicines juſt mentioned, are by no means to be confounded with the tree, from which is procured the precious and rare wood called wood of aloes.

The flowers of fragrant *aletris* open only in the evening, when they emit a moſt agreeable odour, and cloſe again in the morning.

In aſphodel-lily with a reddiſh flower, *hemerocallis fulva*, the ſummits, or tops of the ſtamina, are filled with a copper coloured duſt, which ſheds on being touched; or if a perſon ſmells to the flowers, it will fly off, and ſpread over the face, which it dyes of a purple colour. This is a trick frequently practiſed by unlucky, and roguiſh people, upon the ignorant, and unwary.

The Egyptians put the flowers of tuberoſe in ſweet oil, and by this means give it a moſt excellent ſmell, ſcarce inferior to oil of jeſſamine.

The roots, leaves, and flowers of the white lily, which is a native of Paleſtine and Syria, are uſed in medicine. The root, or bulb, is unctuous, and frequently employed to ripen and digeſt tumours, and hard ſwellings. Of the flowers, and ſometimes of the root, are prepared an oil, and a diſtilled water, the former of which is ſucceſsfully applied in diſorders of the ſkin; the latter in the ſtone, colic, and pains of child-birth. The diſtilled water of the leaves is alſo of great uſe in diſtempers of the lungs.

Martagon lily differs from the other ſpecies, in having its petals rolled, or turned backwards, in form of a Turkiſh turbant; from which fancied reſemblance, the flower is generally known by the name of Turk's-cap. The root,

either boiled, or baked in the aſhes, furniſhes a principal food to the natives of Siberia, who uſe, in like manner, inſtead of bread, the roots of other ſpecies of lily, particularly the *Lilium bulbiferum* of Linnæus. The taſte, ſays Gmelin, is ſomewhat farinaceous, or rather inſipid.

The root of white hellebore, *veratrum album*, promotes violent ſneezing, and is mixed in ointments, to cure the itch. It is never now given inwardly. Boerhaave very juſtly obſerves, that it is a medicine much fitter for horſes than men. It is adminiſtered as a ſternutatory with great ſucceſs, in apoplexies and lethargic complaints.

The plant is of a poiſonous quality, and never fails to prove fatal to ſuch cattle, or other animals, as inadvertently feed on it. In North America, where it is produced in great abundance, the maize, or Indian wheat, is preſerved from voracious birds, by means of hellebore, in the following manner:—The roots being boiled, the maize is put into the water, as ſoon as cool, and having remained in it for a night, is then planted as uſual. The grains, thus prepared, are quickly picked up, or plucked out by the crows, and other birds that infeſt the maize fields, ſome of which, in conſequence of the inſidious meal growing delirious and falling, ſtrike ſuch a terror into the reſt, that they leave the field, and are not tempted to renew the viſit. Care muſt be taken, however, that no other creatures touch the grains of maize thus ſteeped, as even a taſte produces violent ſickneſs, and, if ſwallowed in conſiderable quantity, the conſequence is inſtant death. Scorbutic patients, it is ſaid, have ſometimes found great relief by waſhing the parts affected in a decoction of the roots of white hellebore. The application cauſes conſiderable pain, and a plentiful diſcharge of urine. A comb dipped in the ſame decoction, and paſſed through the hair, effectually deſtroys vermin in the head.

The ſquills, generally uſed in medicine, are red, and are the roots of the *ſcilla maritima*, or ſea-onion, of Linnæus. The white ſort, which is leſs common, and known by the name of male ſquill, is reckoned a variety of the ſame ſpecies. Squills, when found, are heavy, and full of juice.

They

They are uſed in the ſhops for making vinegar, and oxymel of ſquills, and troches for treacle. The heart is reckoned poiſonous; for which reaſon, the druggiſts ſplit them in two, and throwing away the dry leaves and the heart, expoſe the remaining part, before it is proper to be uſed, to the air. A few grains of cinnamon, in powder, ſay writers on the Materia Medica, take off the emetic quality of this root, and render it a powerful diuretic, and an excellent medicine in dropſies.

If the judgment of the moſt numerous part of mankind who have taſted of the pine-apple, may be relied on, it certainly deſerves the appellation it has univerſally obtained, that of king of fruits; the agreeable variety, and delicate quick poignancy of its juice, being juſtly eſteemed to excel every other. The roots are many, and ſpread in a circular manner. From the centre riſes a ſtrong, hard ſtalk, ſurrounded near the earth, and for a conſiderable way up the ſtalk, with long green leaves, which are ſet on alternately, and finely ſawed on their edges. The top of the ſtalk ſuſtains the fruit, which is called the pine, from ſome reſemblance which it has on the outſide to the cone of the pine-tree. The fruit is beautifully decorated at top, with a crown of fine green ſharp-pointed leaves, which are likewiſe ſawed on their edges. The flowers are funnel-ſhaped, placed above the fruit, of a blue colour, and conſiſt of three petals. When the flowers are gone, the fruit enlarges and becomes a fleſhy, knobby ſeed-veſſel, of the berry kind, full of juice. The ſeeds, which are lodged in the knobs, or tubercles of the fruit, are very ſmall, and almoſt kidney-ſhaped. Some time before the fruit is ripe, two, three, or four ſuckers grow from the ſtalk below, yet cloſe to the fruit: theſe ſhoots are taken off, and planted; and will in about fourteen months time produce a ripe pine. Thoſe who cannot procure theſe ſuckers, ſometimes plant the top, or crown. This, though intended by Nature chiefly as an ornament to the fruit, will grow, and in time bear a fruit; not ſo ſoon, however, nor ſo good as that produced by thoſe ſuckers, which Nature intended to be the means of propagating this fruit. The

three

three beſt ſorts of pines are the Surinam, the ſugar-loaf, and queen-pine. The fruit ought to be eaten ſoon after it is cut, and ſhould not be kept on the ſtalk in the garden till it be very ſoft on the outſide, as the cuſtom too frequently is.

As pine-apple has naturally a certain degree of acrimony, the Europeans at the Cape of Good Hope remove it, as Kolben informs us, by laying the fruit in ſlices, in ſpring-water. It is afterwards put in Rheniſh wine, and has ſugar ſcattered upon it, when it taſtes deliciouſly, having thus acquired much of the flavour of ſtrawberries. Of the expreſſed juice of the Ananas, is prepared an excellent wine, which, ſays Dr. Fermin, in his Natural Hiſtory of Surinam, is eſteemed almoſt equal to Malmſey, and intoxicates. Kolben, whom I juſt mentioned, aſſerts, that pine-apple, not fully ripe, if eaten by a woman with child, will certainly occaſion abortion.

To the ſame genus with the pine-apple, belongs the Karatas, or penguin, a fruit very common in the Weſt Indies, ſo named from its outward covering, which is a ſmooth whitiſh-yellow huſk. The outſide of the plant is compoſed of ſome ſcores of hard ſtiff green leaves, two inches broad, with ſharp-hooked prickly edges. Theſe leaves, which grow to about nine feet high, turn ſcoopingly inward on the upper ſide, by which means they ſave and convey the dew and the rain that fall upon them, to the roots. They grow, likewiſe, almoſt impenetrably thick near the earth, ſurrounding and guarding a circular crown, of about a foot diameter. From this grows a cluſter of fruits, each four inches long, and one broad, pointed at both ends, and quadrangular in the middle; by which means they are ſo cloſely joined, that they cannot eaſily, until very ripe, be taken aſunder. The white outward cover being peeled off, diſplays a white pulpy ſubſtance, containing a great number of very ſmall flattiſh coal-black ſeeds. This ſubſtance, which is the eatable part, has ſome ſmall reſemblance, in its flavour, of the pine-apple, and is eſteemed cooling and wholeſome. This fruit, when nearly ripe, being gnawed by rats, or other vermin, emits, from the wounded part, drops of the moſt tranſparent gum;

which

which manifeſtly ſhews, that its juices are much impregnated with volatile oil. A moderate uſe of this fruit has been very ſtrongly recommended in fevers, and with juſtice; for by its penetrating, grateful, and active ſharpneſs, it is capable of laying open the orifices of the ſalival ducts, and thereby enabling the glands of the mouth and throat to diſcharge the contents, which could not be done before the impediment was removed.

Beſides this ſort, there is a large and round penguin, of the ſize of an apple, which is much more palatable than the other, and taſting not unlike a ſtrawberry, is frequently called by that name.

Tillandſia, the caraguata of Father Plumier, the large wild barren pine of the Weſt Indians, is a paraſitic plant, and ought, perhaps, in ſtrict propriety, to be denominated an aquatic: for although it is ſuſpended in the air among the branches of lofty trees, to whoſe boughs it is faſtened by its numerous roots; yet it is not indebted to thoſe boughs, like the miſletoe, and other paraſitic plants, for nouriſhment, but merely for ſupport: provident Nature having, in a very extraordinary manner, ſupplied this with other means to preſerve its exiſtence: for the leaves, which much reſemble thoſe of the pine-apple, but are larger, ſurround this plant in a circular manner: each leaf being terminated near the ſtalk, with a hollow bucket, which contains about half a pint of water. It is by theſe numerous ſmall reſervoirs of water, that the roots, as well as every other part of this plant, are ſupplied with nouriſhment, without the help of any earth. The flouriſhing condition of this plant, as well as the great growth of fig-trees upon barren rocks, ſhews that water is of greater uſe to vegetation, than even earth itſelf.

One contrivance of Nature in this vegetable, ſays Dr. Sloane, is truly admirable. The ſeed is crowned with many long, downy threads, not only that it may be carried every where by the wind; but that, by thoſe threads, when driven through the boughs, it may be held faſt, and ſtick to the arms, and prominent parts of the barks of trees. So ſoon

as it ſprouts, or germinates, although it be on the under part of a bough, its leaves and ſtalk riſe perpendicular, or erect; if they aſſumed any other direction, the ciſtern or reſervoir juſt mentioned, made of the hollow leaves, could not hold water, which is neceſſary to the life and nouriſhment of the plant. In ſcarcity of water, this reſervoir is uſeful, not to the plant only, but to men, and even to birds, and all ſorts of inſects, which come thither in troops, and ſeldom go away without refreſhment.

To the ſame purpoſe, Dampier, in his Voyage to Campeachy, relates, that the wild pine has leaves that will hold a pint and a half, or quart of rain-water, which refreſhes the leaves, and nouriſhes the roots. When we find theſe pines, he continues, we ſtick our knives into the leaves, juſt above the root; and the water guſhing out, we catch it in our hats, as I myſelf have frequently done, to my great relief.

CORONATRICES, and CORONATI, from *corona*, a crown. The name of the eighth claſs, in Linnæus's Method founded upon the preſence, different ſpecies, figure, ſituation, duration, regularity, and number of diviſions of the calyx or flower-cup, conſiſting of plants, which, like French willow, and tree-primroſe, have the ſeed-bud placed under the flower-cup, which ſerves it for a crown. This is the *Germen inferum*, and *Calyx ſuperus* of Linnæus.

CORONULA, (diminutive from *corona*); a little crown; a hem, or border, which ſurrounds the ſeeds of ſome flowers in form of a crown. Linnæus defines it to be a ſort of little calyx, or flower-cup, *calyculus*, which adhering to the naked ſeeds of ſome plants, ſerves to diſperſe them. The principal crown of the ſeed is that fine downy appearance termed by Linnæus, PAPPUS, which ſee.

In ſcabious, *knautia*, and ſome others, the flower-cup becomes the crown of the ſeed.

CORTEX, (from *corium*, leather, a hide, and *tego*, to cover, *quod quaſi corium*, ſays Iſidorus, *lignum tegat*); the rind, or coarſe outer bark of plants. The organiſation of the outer and inner barks, which differ principally in the fineneſs

fineneſs of their texture, is particularly explained under the article STRUCTURA *Vegetabilis*,

CORYDALES, (from κορυς, *galea*, an helmet, quod à Καρα, caput, the head). The name of the twenty-fourth order in Linnæus's Fragments of a Natural Method, conſiſting of plants which have irregular flowers, ſomewhat reſembling a helmet, or hood.

The title of this order ſeems to have been ſuggeſted by a genus in Dillenius of the ſame name, which Linnæus has joined to his genus *Fumaria*.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Plants with helmet-ſhaped Flowers, having their Stamina diſtinct.

Linnæan Genera.			*Engliſh Names.*
Epimedium,	—	—	Barren-wort.
Hypecoum.			
Leontice,	—	—	Lion's-leaf.
Melianthus,	—	—	Honey-flower.
Pinguicula,	—	—	Butter-wort, or Yorkſhire ſanicle.
Utricularia,	—	—	Water-milfoil.

SECTION II.

Plants with Helmet-ſhaped Flowers, having their Stamina united either by the Filaments, or Tops.

Fumaria,	—	—	Fumatory.
Impatiens,	—	—	Balſam, or Female Balſamine.
Monnieria.			

Habit and Structure of the Plants of this Order.

Theſe plants are moſtly herbaceous and perennial.

The ROOTS are tuberous, or knobby.

The STEMS are generally branched.

The

The LEAVES are alternate, ſometimes ſimple, but moſt commonly winged; that is, conſiſt of two or three pair of lobes, or leſſer leaves, which are attached to the middle rib. In monnieria, and ſome ſpecies of balſam, the leaves are oppoſite.

The foot-ſtalk of the leaves is narrow, except in barren-wort, where it is large, and has a membranaceous border.

In a ſpecies of African honey-flower, STIPULÆ, or ſcales, are firmly attached to the foot-ſtalk of the leaves, under which they are placed, ſo as to make part of its ſubſtance; the ſame ſubſidiary leaves are likewiſe united from oppoſite ſides of the ſtalk; whence they form the appearance of a ſingle ſcale, and are ſo denominated by Linnæus.

The middle rib of the leaves, in ſome ſpecies of fumatory, particularly that termed by Linnæus *fumaria claviculata*, is terminated with one branching tendril, which appears to be a fine cylindrical prolongation of the wings, or diviſions of the leaves.

In balſam, ſmall glands, or veſſels of ſecretion, are produced from the baſe of the leaves; roundiſh veſſels of the ſame kind, diſtended with air, are placed at the root of water-milfoil; and in butter-wort, the glands are placed upon the ſurface of the leaves.

The FLOWERS are univerſally hermaphrodite; that is, contain both male and female organs within the ſame covers.

They proceed either ſingly from the wings or angles of the leaves, as in butter-wort, and *monnieria*; or are collected in cluſters, at the end of the branches, as in fumatory, lion's-leaf, and *hypecoum*.

The CALYX, or flower-cup, conſiſts of two, four, five, or ſix leaves, which are frequently coloured, and commonly fall off immediately before, or very ſoon after, the expanſion of the petals.

In *monnieria*, and butter-wort, the calyx is permanent; that is, accompanies the ſeed-bud to its maturity.

The COROLLA, or coloured inner cover of the flower, is generally irregular, of one, or many pieces, gaping, and

furniſhed with a *nectarium*, or ſtriking appendage, which is very different, in the different genera. In butter-wort, water-milfoil, and balſam, it is ſhaped like a horn, and produced from the baſe of the petal. In barren-wort, four cup-ſhaped *nectaria*, of the length of the petals, are inſerted into the common receptacle. In lion's leaf, ſix equal ſpreading ſcales, furniſhed with foot-ſtalks, are attached to the baſe of the petals. In fumatory, each lip of the irregular petal terminates behind in a ſpur, which, in the lower lip, is generally leſs prominent. In *monnieria*, a ſmall egg-ſhaped nectariferous ſcale, is ſeated at the baſe of the ſeed-bud; and in honey-flower, a very ſhort ſcale of the ſame kind is placed within the lower diviſion of the calyx.

In ſome ſpecies of balſam, the horn of the nectarium; in others, two of the five irregular petals, are wanting.

The STAMINA are in number from two to ſix, and of a proportionate length, except in honey-flower, which has two ſhorter than the reſt.

The FILAMENTS are diſtinct, except in two genera, fumatory and *monnieria*, which have two ſets or ſtrings of filaments united in a cylinder. The former has three *anthers*, or tops, on each ſet of united filaments; the latter two *anthers* on the upper ſet, and three on the lower; from whence we may conclude, that the number of ſtamina in fumatory, is ſix, of *monnieria*, five; yet Linnæus has placed this laſt, along with fumatory, in an order, whoſe characteriſtic it is to have ſix ſtamina.

The genus *monnieria*, which, in America, has conſtantly five diviſions in the corolla, and five ſtamina, frequently bears flowers in Europe, which have only four diviſions in its irregular gaping petal, and four ſtamina.

The ANTHERS, or tops, in this order, are univerſally diſtinct, except in one genus, balſam, where they are formed into a cylinder that is divided at the baſe.

In barren-wort, and lion's-leaf, the anthers burſt, when ripe, from the baſe to the top, through the whole length.

The SEED-BUD is generally roundiſh; ſometimes, however, angular, as in *monnieria*, and honey-flower.

The

The STYLE is commonly ſingle, extremely ſhort, ſlender, or thread-ſhaped, and crowned with a ſimple *ſtigma*.

Hypecoum has two ſtyles: balſam, none.

The SEED-VESSEL is either a hollow, blown up berry, as in lion's-leaf; a capſule of one cell, as in butter-wort, and water milfoil; a longiſh pod, *ſiliqua*, as in barren-wort and hypecoum; or a roundiſh pod, *ſilicula*, as in fumatory.

In balſam, the capſule, which in ſome ſpecies is long, in others round, or egg-ſhaped, burſts open with an elaſtic ſpring, at five ſeveral valves, which are twiſted ſpirally.

Monnieria has five capſules.

In *Hypecoum*, the pod is jointed, and contains as many cells as there are joints. This ſtriking mark, however, is not conſtant: the *nectarium* is invariable.

The SEEDS are generally numerous, and round.

In *monnieria*, each ſeed is incloſed in a dry covering with two valves, called by Linnæus *arillus*, which falls off ſpontaneouſly.

Hypecoum has a ſingle ſeed lodged in each cell or joint of the ſeed-veſſel.

In balſam, the ſeeds, which are numerous, are affixed to a pillar in the centre of the capſule.

The ſeeds of *hypecoum* remain a year in the ground without riſing.

The juice of theſe plants, which is generally of a yellow colour, is narcotic and anodyne. The roots are opening. Officinal fumatory, which is eſteemed refreſhing, is bitter, and ſoapy; its juice depoſits a number of nitrous chryſtals, of eight ſides, which ſparkle in the fire. The root of bulbous fumatory is an emmenagogue; applied externally, it cleanſes ulcers, and proud fleſh.

The juice of common fumatory is greatly commended for bilious colics; it deſtroys warts, and other prominences in the ſkin; and mixed with a great quantity of water, is an efficacious lotion in diſorders of the eyes.

A ſpecies of fumatory is termed *fumaria cava*, from its having a pretty large tuberous root, hollowed in the middle.

The juice of all the ſpecies of *hypecoum* is of a yellow colour,

colour, reſembling that of celandine, and is affirmed by ſome eminent phyſicians, to be as narcotic as opium. From the nectarium of the bloſſom, the bees collect great quantities of honey.

The pods of yellow balſamine, or touch-me-not, are taper, twiſted ſpirally like a ſcrew, and upon being lightly touched, or ſhaken with the wind when ripe, burſt open, and eject the ſeeds with conſiderable elaſticity.

Barren-wort, ſays an author, whoſe name I have forgot, is ſo termed, from the flowers being totally eclipſed, or covered by the leaves; ſo that, without proper inſpection, they appear to be wanting.

From the calyx of the honey-flower, oozes a ſweet liquor, which is ſometimes uſed in medicine, and eſteemed ſtomachic, and nouriſhing. Kolben ſays, that the Hottentots, and moſt of the Europeans of the Cape of Good Hope, are exceedingly fond of the ſweet juice of the two ſpecies of *Melianthus*, which grow naturally there, and never fail of a treat whenever they can find it. *Vide* Kolben, vol. ii. p. *243*.

Both honey-flower, however, and barren-wort, are by moſt authors deemed poiſonous. *Vide Phil. Bot.* p. *282*, ſect. *355*.

CORYMBIFERÆ, from *corymbus*, a mode of flowering, and *fero*, to bear. The name of a claſs in Moriſon and Ray's Methods, and of Vaillant's Arrangement of the Compound Flowers; conſiſting of plants, whoſe flowers are produced in cluſters or bunches like thoſe of ivy-berries, and form that particular ſort of head, termed by botaniſts, *corymbus*. *Vide Infra*.

Tanſy, feverfew, elecampane, colt's-foot, groundſel, and marigold, furniſh examples.

CORYMBIFERÆ is likewiſe the name of an order or diviſion of the compound flowers, adopted by Linnæus, after Ray and Vaillant, in the former editions of his Fragments of a Natural Method. This title is in the later editions changed for *Diſcoideæ*, another name borrowed from Ray's Method, but uſed in a ſomewhat different ſenſe.

CORYMBUS, (a Κορυς, *galea*, an helmet, quod a

Καρα, *caput*, the head,) properly ſignifies a cluſter of ivy-berries. This is Pliny's definition in the 34th Chapter of the 16th Book of his Natural Hiſtory. *Corymbus, inquit, eſt hederæ racemus in orbem circumactus.* By Columella it is uſed to expreſs all ſuch fructifications as grow in a head, or, as Scaliger writes, *quicquid in panicam aut ſtrobilum aſſurgit*, as artichoke, thiſtle, &c.—In modern Botany, Corymbus is a mode of flowering, in which the leſſer or partial flower-ſtalks are produced along the common ſtalk, on both ſides; and, although of unequal lengths, riſe to the ſame height, ſo as to form a flat and even ſurface at top.

The term is exemplified in *ſpiræa opulifolia*, ſcurvy-graſs, gold of pleaſure, ſtock, and the other croſs-ſhaped flowers, the *Tetradynamia* of Linnæus.

A corymbus differs from an umbel, another manner of flowering, in that the numerous partial foot-ſtalks ariſe from different parts of the common ſtalk; whereas in the umbel-liferous flowers, they all proceed from a common centre. *Vide* UMBELLA.

A corymbus may be ſuppoſed to be formed from a ſpike, a third mode of infloreſcence, as Linnæus terms it, by raiſ-ing the flowers on partial foot-ſtalks, which riſe to a pro-portionable height. The flowers in a ſpike are ſeated on the common ſtalk, without any proper or partial foot-ſtalk. *Vide* SPICA.

This manner of flowering as well as the others, frequent-ly affords certain marks in diſtinguiſhing the ſpecies. Thus in *ſpiræa*, the ſpecies are ſcarce to be diſtinguiſhed, but by the mode of flowering, which in ſome, is a corymbus; in others, an umbel; and in others, a *racemus*, or cluſter like that of grapes. *Vide* RACEMUS.

The partial foot-ſtalks in a corymbus, are ſometimes ſimple, that is, have no branches, as in ſome ſpecies of ſtar of Bethlehem; ſometimes branch out into ſeveral irregular ramifications, yet ſo as to form an even ſurface at top. In the former caſe, the corymbus is ſaid to be ſimple; in the latter, compound.

The corymbus is a mean betwixt the cluſter, *racemus*, and

and the umbel; like them, its flowers are furniſhed with proper foot-ſtalks, which riſe gradually from bottom to top, as thoſe of the *racemus*, and are produced to the ſame height, as thoſe of the umbel.

COTYLEDONES, (from Κοτολη, cavitas, a hollow); a term of placentation transferred from the animal to the vegetable kingdom. The periſhable, porous ſide-lobes of the ſeed, which involve, and, for ſome time, furniſh nouriſhment to the embryo-plant.

The lobes in queſtion, generally two in number, are very conſpicuous in the bean, and moſt of the leguminous tribe, upon ſtripping off the huſk, or outer cover of the ſeed; particularly if they have previouſly been laid in earth or water. Their ſubſtance is meally, mucilaginous, and eaſily ferments. They reſult from the expanſion of an infinite number of branching veſſels.

The lobes are externally convex, internally flat, unleſs where they are united, and infold the principle of life, *corculum*, which communicates with them by means of two large trunks of veſſels, that ſupply it with nouriſhment, and correſpond to the navel-ſtring in animals; as the lobes themſelves ſeem to anſwer the purpoſe of the placenta in women, and cotyledones in brutes.

We ſaid, in the definition, that the lobes are the periſhable part of the ſeed. To explain this, we muſt previouſly obſerve the changes which are effected upon the embryo-plant, in the firſt ſtages of vegetation.

After lying ſome time in water, or earth, the lobes of the ſeed, penetrated by the watery particles, which are charged with nutritive juices, put in motion by heat, ſwell and thicken; the air contained within their ſubſtance, dilating, burſts open the outer cover, or huſk, which unites them, and diſcovers the radicle, and embryo-plant. In this firſt ſtage, the ſeed is properly ſaid to ſprout, or germinate. Soon after, the lobes expanding, riſe out of the earth, in the form of leaves; very different, however, from thoſe which the plant is afterwards to produce. In this ſtage, the ſeed is properly ſaid to riſe.

Theſe leaves, called, for diſtinction, ſeminal, or ſeed-leaves; (that is, the firſt leaves produced by the ſeeds) are commonly two in number: ſome ſeeds, however, have only one ſeminal leaf; in which caſe, the plants by botaniſts are termed Monocotyledonous, a term of the ſame import; as thoſe which riſe with two ſeminal leaves, are ſtiled Dicotyledonous. Cæſalpinus, and Jungius, termed both theſe kinds of ſeeds, univalvular, and bivalvular; that is, having one, or two ſeed-covers. The former was the firſt who diſcovered the number of lobes in the embryo of ſeeds.

To proceed with our infant-plant. Under this new form of leaves, the lobes elaborate, and rectify the ſap, which is deſtined to nouriſh the tender vegetable. The young root too, which naturally tends downwards, has by this time made ſome efforts to penetrate into the boſom of the earth, where meeting with ſtrong exhilarating juices, it tranſmits them to the lobes, through which they paſs highly refined, to the future plant. The ſtem begins to appear; but although enlarged in volume, its parts are not developed, but continue as they were in the ſeed. The lobes, ſtill united to the plant by the two trunks of veſſels, accompany it for ſome time after its eruption from the earth, till, having acquired ſufficient ſtrength and growth, the ſeminal leaves become uſeleſs, wrinkle, wither, and die away. *Vide* GERMINATIO.

Of plants which have only one ſeminal leaf, we muſt carefully diſtinguiſh thoſe in which the lobe forms a ſort of ſheath ſurrounding the whole body of the plant, as in the palms, graſſes, and liliaceous vegetables, from thoſe in which the lobe is only extended in length, as in dodder.

Pine and fir trees, ſays Linnæus, have ten; cypreſs, five; flax, four lobes; in fact, however, theſe plants have only two lobes, each of which is differently divided almoſt to the baſe: the lobes only being perfectly diſtinct.

The preſence of the lobes, or ſeminal leaves, ſufficiently evinces the previous exiſtence of the ſeed; and confutes the ridiculous opinion of equivocal generation, long ſince exploded.

The

The lobes being in the vegetable œconomy, what the placenta is in the animal, their diſpoſition at the time when the ſeed begins to grow, is termed very properly by Linnæus, placentation.

In the muſhrooms, ferns, and other imperfect plants, the ſeminal leaves are not ſufficiently aſcertained. The ſeeds of the moſſes want only the proper covering and lobes. *Vide* ACOTYLEDONES.

The number of lobes, or ſeed-leaves, furniſhes a primary diſtinction in Ray's Method.

CRETA, chalk; a ſpecies of earth.

CRUCIFORMIS *Flos*, (from *crux*, a croſs, and *forma*, a ſhape or figure); a croſs-ſhaped flower; a flower conſiſting of four equal petals, which ſpread at the top, in form of a croſs. Stock gilly-flower, honeſty, and candy-tuft, furniſh examples.

CRUCIFORMES. The name of the fifth claſs in Tournefort, and ſeventeenth in Pontedera's Method, conſiſting of plants with croſs-ſhaped flowers. Theſe are the *Siliquoſæ* of Moriſon, Hermannus, Royen, Boerhaave, and Ray; the *Tetrapetali regulares* of Rivinus, and Chriſtopher Knaut; the *Tetrapetali uniformes* of Chriſtian Knaut; and the *Tetradynamia* of the Sexual Method. *Vide* SILIQUOSÆ, &c.

CRYPTOGAMIA, from κρυπτω, to hide, and γαμος, a marriage; a clandeſtine marriage. The name of the twenty-fourth claſs in Linnæus's Sexual Method, conſiſting of plants, in which the parts of fructification, the criterion of the ſexes, are, either from their minuteneſs, or their particular ſituation, entirely concealed, or imperfectly viſible.

The great obſcurity that ſtill prevails in this very conſiderable part of the vegetable kingdom, notwithſtanding the ingenious reſearches of Ray, Micheli, Dillenius, Gmelin, Haller, Battarra, Schæffer, Stackhouſe, and other eminent names in Botany, the Sexual Method of Arrangement is little qualified to diſpel. Indeed it would be difficult to conceive a ſyſtematic method, in which the numerous plants of the claſs *Cryptogamia*, could be arranged with facility; but in Linnæus's Syſtem, the difficulty muſt be tenfold, as,

from the abſence, or unaſcertained preſence of the very organs which lay the foundation of the primary diviſions, the character of the claſs and order is neceſſarily, in many inſtances, merely negative; and the ſubordinate diviſions, of courſe, are ſtrangely huddled together, without eſſential and certain marks of diſtinction.

The claſs Cryptogamia, which correſponds to the Imperfect Plants of Ray, and to the 16th and 17th claſſes of Tournefort's Method, containing herbs not bearing flowers, with and without ſeeds, is divided into four orders. Theſe are, *Filices*, Ferns; *Muſci*, Moſſes; *Algæ*, Sea-weed, or Wrack; and *Fungi*, Muſhrooms. *Vide* FILICES, ALGÆ, *&c.*

For a more particular account of the progreſſive diſcoveries of Naturaliſts in this extenſive department of Botanical knowledge, the reader is referred to the author's INSTITUTES OF BOTANY, Part I. p. 67, and ſeq.

Conſidered as a natural claſs, or rather as an aſſemblage of natural orders, the plants in queſtion are generally of a ſuſpicious nature.

CUBITUS, a term of meaſure. *Vide* MENSURA.

CUCURBITACEÆ, from *cucurbita*, a gourd; the name of the thirty-fourth order in Linnæus's Fragments of a Natural Method, conſiſting of plants which reſemble the gourd in external figure, habit, virtues, and ſenſible qualities.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Cucurbitaceous Plants with Hermaphrodite Flowers.

Linnæan Genera.			*Engliſh Names.*
Gronovia.			
Melothria,	—	—	Small creeping Cucumber.
Paſſiflora,	—	—	Paſſion-Flower.

SECTION

SECTION II.

Cucurbitaceous Plants with male and female Flowers produced either on the ſame or diſtinct Roots.

Linnæan Genera.			*Engliſh Names.*
Anguria Jacquin.			
Bryonia,	—	—	Bryony.
Cucumis,	—	—	Cucumber, Melon.
Cucurbita,	—	—	Gourd, Pumpion.
Elaterium Jacquin.			
Fevillea.			
Momordica,	—	—	Male Balſam-apple.
Sicyos,	—	—	Single ſeeded Cucumber.
Trichoſanthes,	—	—	Serpent-Cucumber.

Habit and Structure of the Plants of this Order

The plants of this order, which generally climb, and have long diffuſed branches, are moſtly herbaceous and perennial. Wild cucumber, the *Elaterium* of Boerhaave, a ſpecies of *Momordica* of Linnæus, is the only plant in this order, which riſes erect, without climbing, or ſupporting itſelf on the plants in its neighbourhood. Some ſpecies of paſſion-flower are of the ſhrub and tree kind, and retain their leaves during the winter.

The ROOTS, in the perennial plants of this order, are ſhaped like thoſe of turnip; in the annuals, they are branched and fibrous.

The STEMS are cylindric and ſucculent. The young branches have generally five angles. In ſome ſpecies of paſſion-flower, they are ſquare.

The LEAVES are alternate, angular, and ſometimes hand-ſhaped. They are attached to the branches by a foot-ſtalk, which is pretty long, and cylindrical, without any furrow. In a ſpecies of paſſion-flower, hence denominated *paſſiflora veſpertilio*, the leaves are ſhaped like the wings of a bat, and ſupported on a foot-ſtalk half an inch long.

From the wing or angle of each of the upper leaves, proceeds a tendril, which is either ſimple or branched, and twiſts itſelf ſpirally round the different bodies in its neighbourhood, for the purpoſe of ſupporting and training the branches.

The lower leaves have no tendril. Wild-cucumber, in which the tendrils ſeem wanting, has a ſmall *ſtipula*, or ſcale, in the form of a triangular tongue, at the origin of each of the male flowers.

Beſides tendrils, water-melon, and ſome ſpecies of bryony, have a *ſtipula*, or ſcale, of an oval ſhape, which iſſues from the wing or angle of each leaf. In male-balſam apple, a ſcale of the ſame kind accompanies each flower. Paſſion-flower has two pretty large *ſtipulæ*, or ſcales, which are placed on both ſides of the foot-ſtalk of the leaf.

In the gourd, glands, or ſecretory veſſels, are placed on the baſe of the leaf: in the paſſion-flower, they are ſeated on the foot-ſtalks.

The FLOWERS, in plants of the firſt ſection, are hermaphrodite; male and female, in thoſe of the ſecond. In this laſt, the male flowers are generally ſeparated from the female upon the ſame root, and that either in the ſame wing, or angle of the leaves, as in *Sicyos* and ſerpent-cucumber; or in different angles, as in gourd, and ſome ſpecies of bryony.

In *ſevillea*, and ſome ſpecies of bryony, the male flowers are produced on diſtinct roots from the female.

Small creeping cucumber, *melothria*, has hermaphrodite flowers; in every other reſpect it reſembles the cucumber, to which moſt botaniſts have joined it.

The flowers proceed from the wings of the leaves, either ſingly, as in pumpion, water-melon, male balſam-apple, and paſſion-flower; two and two, as in ſome cucumbers; in a *ſpike*, as in *ſevillea*, and ſerpent-cucumber; or in a *corymbus*, as in bryony, and the male flowers of gourd. In ſingle-ſeeded cucumber, the male flowers form a ſpike, the female a corymbus.

The FLOWER-CUP, in the female flowers, is placed upon

upon the ſeed-bud, and generally conſiſts of one bell-ſhaped leaf, that is deeply divided into five equal ſegments; and, unlike the other plants which have the calyx ſeated upon the fruit, falls off with the petals and the other parts of the flower. In the genus *gronovia*, the calyx is permanent; that is, accompanies the ſeed-bud to its maturity. In the paſſion-flower, it is ſeated below the ſeed-bud. *Elaterium*, a genus of M. Jacquin, has no calyx.

The COROLLA conſiſts of one petal, with five equal diviſions, which adhere to the tube of the calyx as if glued to it. *Anguria*, *Gronovia*, and paſſion-flower, have five petals. Theſe, in the latter, are lancet-ſhaped, flat, of the ſize, figure, and colour of the calyx. A ſpecies of paſſion-flower, termed by Linnæus *paſſiflora ſuberoſa*, wants the petals.

The NECTARIUM, in paſſion-flower, is very ſingular, conſiſting of a number of beautiful fibres, or rays, which are placed horizontally within the petals, in three ſeries or rows. Theſe Linnæus calls, very improperly, a triple crown: a triple helmet would have been equally expreſſive of the appearance; but this is not the only impropriety in Linnæus's deſcription of this beautiful flower.

The gourd has a hollow, triangular gland, or veſſel of ſecretion, ſeated in the middle of the flower.

In *ſevillea*, the nectarium conſiſts of five crooked threads, or ſtrings, which in the male-flowers are placed in the middle, alternate with the ſtamina.

The STAMINA are, in number, from one to five, ſhort, and generally inſerted into the calyx.

In paſſion-flower, they are attached to a pillar-ſhaped receptacle, which ſtands in the middle of the flower, and is crowned with the ſeed-bud. This receptacle, Linnæus, who was reſolved, at all events, to obtrude this genus into his claſs *Gynandria*, has dignified with the name of a pillar-ſhaped ſtyle: by which means he has fallen into the abſurdity of aſſerting, that the ſtyle in the paſſion-flower elevates the ſeed-bud, contrary to what is obſerved in every other flower yet known. The uſeleſſneſs of this pillar-ſhaped

ſtyle

ſtyle farther appears from this circumſtance, that three ſtyles properly ſo called, ariſe from the *germen*, as in other flowers.

The filaments, in this order, are diſtinct; the ANTHERS, or tops, in moſt plants of the ſecond ſection, are united in a cylinder. Bryony has five anthers to three filaments.

In the female-flowers are ſometimes obſerved three, or four filaments, which have the appearance of ſtamina without tops. Theſe, in bryony, and male balſam-apple, are attached to the top of the tube of the petal; in pumpion, gourd, and water melon, they proceed from its baſe.

The anthers in paſſion-flower, are ſlightly attached to the filaments, on which they turn like a vane, or the needle of a compaſs.

The SEED-BUD is ſingle, and placed below the receptacle of the flower. In paſſion-flower, it is ſeated upon a long pillar-ſhaped receptacle, in the middle of the flower. The ſeed-bud, in the genus *elaterium*, is covered with prickles.

The STYLE is generally ſingle, cylindrical, of the length of the calyx, and crowned with a triple *ſtigma*. Paſſion flower has three ſtyles; *ſevillea*, five. The male-flowers of ſerpent-cucumber, have three very ſmall ſtyles, adhering to the tube of the calyx.

The SEED-VESSEL is generally pulpy, of the apple, or berry kind, and conſiſts of one, two, or three cells. In elaterium, and gronovia, it is a capſule, which in the former is prickly and ſucculent.

The fruit of ſingle-ſeeded cucumber, is at firſt a thorny berry, which dries, and hardens as it ripens, ſo as to become a very dry capſule, before the ſeeds have attained maturity. The partitions which ſeparate the cells are compoſed of fibres ſurrounded with a watery pulp, which, when dried, diſcovers the fibres, under the form of a thick-ſet web or net.

The SEEDS are numerous, generally flat, or compreſſed, and ſometimes, as in paſſion-flower and cucumber, covered with that kind of proper coat called by Linnæus, *arillus*. *Vide* ARILLUS.

In

In male balſam-apple, and wild cucumber, the ſeeds burſt, or are ſpirted from their cells with an elaſtic ſpring.

The fruit of theſe plants is generally purgative and refreſhing. That of ſome of them proves a very violent emetic, when uſed too freely.

Male balſam-apple, is famous in Syria for curing wounds. The natives cut open the unripe fruit, and infuſe it in ſweet oil, which they expoſe to the ſun for ſome days, until it is become red; and then preſent it for uſe. Dropped on cotton, and applied to a freſh wound, the Syrians reckon this oil the beſt vulnerary next to balſam of Mecca, having found by experience, that it often cures large wounds within three days. The leaves and ſtems of this plant are uſed for arbours, or bowers.

The Egyptian balſam-apple, called by the Arabians liff, or luff, is cultivated in gardens, in the eaſtern countries, and climbs upon palm trees; covering, and elegantly adorning their ſtems.

The elaterium of the ſhops, is the fruit, or rather the inſpiſſated fæcula of the juice of the fruit, of the wild, or aſs's cucumber, a ſpecies of balſam-apple. It is uſually ſent us from Spain, and the ſouthern parts of France, where the plant is common, in ſmall flat whitiſh lumps, or cakes, that are dry, and break eaſily between the fingers. It is of an acrid, nauſeous, bitter taſte, and ſtrong offenſive ſmell, when newly made: but theſe, as well as its other qualities, it loſes, after being kept for ſome time. Elaterium is a very violent purge and vomit, and is now very ſeldom uſed. The plant is commonly called ſpirting-cucumber, from its caſting out its ſeeds, together with the viſcid juice in which they are lodged, with a violent force, if touched, when ripe; from which circumſtance it has ſometimes obtained the appellation of *noli me tangere*, or, touch me not.

The root of white bryony is ſaid to be ſo violent in its effects, when taken freſh, that the peaſants call it the mad turnip: being dried, it enters as an ingredient into ſome medicinal compoſitions, particularly bryony-water, in which

it

it is reckoned to aſſiſt as a powerful uterine cleanſer. Some believe bryony to be an excellent remedy againſt the bites of ſerpents, and other venomous creatures. Its fæcula, when dried, is like ſtarch; but as this is found a medicine of little uſe, there is hardly any of it now made.

In the eaſtern countries, and both the Indies, bottle-gourd, the *cucurbita lagenaria*, of Linnæus, is very commonly cultivated, and ſold in the markets for the table, and is the principal part of the food of the common people in the warm months, particularly from June to October. The Arabians call this kind of gourd, charrah. They boil it, and ſeaſon it with vinegar; they likewiſe fill the ſhell with rice and meat, and thus make a kind of pudding, like what we ſometimes, in England, prepare of the ſhell of pumpion, or pumpkin.

The leaves of the bottle-gourd are large, almoſt circular, covered with fine ſoft hairy down, and ſmell ſtrongly of muſk. The flowers are ſo tender, that they cloſe as ſoon as the ſun ſhines upon them. The outſide tegument or rind of the fruit, as it ripens, grows hard; and when the ſeeds and pulp are taken out, will hold water, for which purpoſe it is ſometimes uſed. Some gourds are ſix feet long, and one and a half round, and when cleared of their pulp, will contain twenty-two gallons: ſuch, however, are very uncommon.

The different kinds of pumpkin, the *cucurbita pepo* of Linnæus, are generally diſtinguiſhed by the names of the white, the blue, the marbled, and the garden pumpkin. Theſe make a great part of the food of the poorer ſort in ſummer, as well in Aſia, and Africa, as in America. The ſtalks and leaves are hairy, the flowers yellow, the fruit is generally, when young, of a mixture between a deep blue and a pale white. It is boiled and eaten with butcher's meat; and by the poorer ſort is much uſed in ſoups.

Squaſh, *cucurbita melopepo*; and warted gourd, when boiled, are by ſome people eſteemed very delicate eating. The ſquaſh is generally plucked by the Americans, when it

is about the ſize of a walnut, and immediately after the falling of the flower.

Water-melons, or citruls, the *Anguria* of Tournefort, the *cucurbita citrullus* of Linnæus, are diſtinguiſhed by the colour of their pulp, into the white and red, and derive their name from the great quantity of water, or liquid, which they contain. Theſe fruits, by their cooling and diuretic quality, are ſo beneficial in hot climates, if uſed in moderation, that the poor people in Perſia, and the Levant, live almoſt ſolely, during the hot months, upon the muſk and water-melon, cucumbers, and milk. The water-melon, ſays Haſſelquiſt, ſerves the Egyptians for meat, drink, and phyſic: when it is very ripe, and almoſt putrid, they hollow part of it, gather the juice there collected, and mixing it with roſe water, and a little ſugar, adminiſter it in burning fevers, with ſuch ſucceſs, that the common people uſe no other medicine in thoſe diſtempers. It is not, however, from the common water-melon, that this medicine is procured. The fruit in queſtion, is ſofter, more juicy, and more rarely to be found than the common ſort, of which this is a variety. It is termed by the Arabs, et-naovi, which ſignifies water.

Water-melons ſhould be eaten with great circumſpection; for if taken in the heat of the day, when the body is very warm, they ſeldom fail to occaſion colics, fluxes, and diſorders of the ſtomach.

The common cucumber, in the eaſtern countries, is boiled and eaten with vinegar. The richer ſort fill it with fleſh and ſpices, and bake it into a pudding, which is ſaid to be extremely palatable.

The Egyptian melon, or queen of cucumbers, the *Cucumis Chate* of Linnæus, the *Abdellavi* of Alpinus, grows in the fertile earth round Cairo after the inundation of the Nile, and no where elſe in Egypt. The fruit is ſometimes ſweet, cool, and a little watery; the pulp almoſt of the ſame ſubſtance as the melon. The grandees in Egypt, and the Europeans who reſide there, eſteem this the pleaſanteſt, as well as ſafeſt fruit, which the country affords.

The

The muſk-melon is diſtinguiſhed, like the water-melon, by the colour of its pulp, into the white and red ſorts; and derives its name from the fragrancy of the ſmell.

Coloquintida, or bitter-apple, the *Colocynthis* of Tournefort, the *Cucumis Colocynthis* of Linnæus, is brought to us from Aleppo, and the iſland of Crete. The leaves are large, placed alternate, almoſt round, and ſtand upon foot-ſtalks four inches long. The flowers are white, ſucceeded by a fruit, which is yellow when ripe. The ſhelly or huſky outſide incloſes a white bitter pulp, interſperſed with white flattiſh ſeeds. If a hole is made in one of theſe ripe gourds, (for the fruit is of that kind,) and a glaſs of rum poured in, and ſuffered to remain for twenty-four hours, and then drunk, it proves a ſucceſsful purge; but is ſo bitter, and leaves ſuch a nauſea behind, that it is ſeldom uſed. It is beſides, the rougheſt purge we know, and therefore ought not to be uſed without great precaution; taken in a large doſe, it not only often brings away pure blood, but likewiſe produces colics, convulſions, ulcers in the bowels, and fatal ſuper-purgations. The Indians ſeparate or pull off the outer rind, and dry the fleſhy part of the fruit, which is what we call the Coloquintida of the ſhops.

CULMIFERÆ *Plantæ*, from *culmus*, a ſtraw, or haulm; plants ſo called which have a ſmooth jointed ſtalk, uſually hollow, and wrapped about at each joint with ſingle, narrow, ſharp-pointed leaves; and the ſeeds contained in chaffy huſks. Such are oat, wheat, barley, rye, and the other plants of the natural family of the graſſes. *Vide* GRAMINA.

CULMIFERÆ, the name of the eleventh claſs in Moriſon's Method, conſiſting of plants which agree in the general characters above enumerated.

CULMINIÆ, from *culmen*, the top, or ſummit; the name of an order in the former editions of Linnæus's Fragments of a Natural Method, conſiſting of a number of plants, moſtly of the mallow-tribe, now removed to the natural order COLUMNIFERÆ, which ſee.

CULMUS,

CULMUS, (a Καλαμη, *ſtipula*, ſtubble, non a Καλαμος, *arundo*, a reed); a ſtraw, or haulm; defined by Linnæus to be the proper trunk of the graſſes, which elevates the leaves, flower, and fruit.

This ſort of trunk is tubular or hollow, and has frequently knots or joints diſtributed at proper diſtances, through its whole length. The leaves are long, ſleek, and placed, either near the root in great numbers, or proceed ſingly from the different joints of the ſtalk, which they embrace at the baſe, like a ſheath, or glove.

The haulm is commonly garniſhed with leaves; ſometimes, however, it is naked, that is, devoid of leaves, as in a few ſpecies of cypreſs-graſs. Moſt graſſes have a round cylindrical ſtalk; in ſome ſpecies of *ſchœnus*, *ſcirpus*, cypreſs-graſs, and others, it is triangular.

The ſtalk is ſometimes entire, that is, has no branches; ſometimes branched, as in *ſchœnus aculeatus & capenſis*, and not ſeldom conſiſts of a number of ſcales, which lie over one another like tiles, (*imbricatus*.)

Laſtly, in a few graſſes, the ſtalk is not interrupted with joints, as in the greater part. The ſpace contained betwixt every two knots or joints, is termed by botaniſts *internodium*, and *articulus culmi*. *Vide* ARTICULUS.

This ſpecies of trunk often affords certain marks of diſtinction in diſcriminating the ſpecies. Thus in the genus Eriocaulon, the ſpecies are ſcarce to be diſtinguiſhed but by the angles of the *culmus*, or ſtalk. Theſe in ſome ſpecies are in number five, in others ſix, and in others ten.

CYMA, (from Κυμα, *idem quod* Κυημα, *fœtus*,—the uppermoſt tender ſhoots of herbs, particularly of coleworts); a ſpecies of receptacle, according to Linnæus; or more properly, a mode of flowering, in which, as in the umbel, a number of ſlender foot-ſtalks proceed from a common centre, and riſe to the ſame height: but, unlike the umbel, the ſecondary or partial foot-ſtalks are diſperſed without any regular order. *Vide* UMBELLA.

The term, which is of great antiquity, having been uſed, though not in the ſenſe now affixed to it, both by Columella

mella and Pliny, is exemplified in elder, gelder roſe, bloody rod, and adder's tongue.

CYMOSUS *Flos*, from *cyma*: an aggregate flower, which has the general characters juſt enumerated. *Vide* CYMA, and AGGREGATUS *Flos*.

CYMOSÆ. The name of an order in the former editions of Linnæus's Fragments of a Natural Method, conſiſting of honey-ſuckle, morinda, loranthus, and a few other genera, moſt of which are, in the later editions, removed to the forty-eighth order, intitled AGGREGATÆ.

CYNAROCEPHALI, (a *cinara* or *cynara*, an artichoke, derived from the Greek Κινάρα, *carduus*, a thiſtle, in which ſenſe it is uſed both by Dioſcorides and Athenæus, and Κεφαλη, the head), plants whoſe flowers form a head like thoſe of artichoke. The name of a claſs, or diviſion, in Vaillant's Arrangement of the Compound Flowers, correſponding to the *Capitatæ*, or flowers forming a head, of Ray, and other botaniſts; and to part of the *Floſculoſi* of Tournefort. It is exemplified in thiſtle, globe-thiſtle, burdock, ſaw-wort, and blue-bottle.

D.

DECAGYNIA, (from δεκα, ten, and γυνη, a woman.) The name of an order, or ſecondary diviſion, in the claſs Decandria, of the ſexual method, conſiſting of plants whoſe flowers are furniſhed with ten ſtamina, and the ſame number of ſtyles. *Neurada* and American nightſhade furniſh examples.

DECANDRIA, (from δεκα, ten, and ἀνηρ, a man.) The name of the tenth claſs in Linnæus's Sexual Syſtem, conſiſting of plants whoſe flowers, as the name imports, are furniſhed with ten ſtamina or male organs. This claſs, as well as the other claſſes in Linnæus's Method that are compounded with a numeral, has another character, which is not expreſſed in the title. I mean that the flowers are all hermaphrodite, that is, have both ſtamina and pointal, which,

according to our author, are the male and female organs of generation, within the ſame covers. In this reſpect, the claſſes in queſtion differ from the *Monœcia*, and *Diœcia*, of the ſame author, in which the male and female organs are ſeparated; being placed, in the former, upon different parts of the ſame plant; in the latter, upon diſtinct plants. This obſervation merits particular attention, becauſe the circumſtance, or character which is the ſubject of it, is indiſpenſably neceſſary; and a plant having ten or any number of ſtamina, is not on that account to be referred to its reſpective numeral claſs, unleſs both male and female organs are found contained within the covers of the flower.

To take an example from the claſs which we are now conſidering: the flowers of the curious exotic, papaw, or popo-tree, have ten ſtamina; and yet the plant cannot be arranged under the claſs *Decandria*, becauſe the male and female parts are not only placed within different covers, but likewiſe produced upon diſtinct plants: the popo ſeed ripened by the female flowers producing both male and female trees.

Beſides the ſexes of the flowers, we are likewiſe to attend, that the ſtamina be of an equal length and diſtinct; that is, neither joined at the bottom, nor top; circumſtances which would remove the plants in which they are found, to claſſes whoſe eſſential character is no ways connected with the number of the male and female organs.

The orders or ſecondary diviſions in this numerous claſs, are five, and take their name from the number of the ſtyles, or female organs. Fraxinella, lignum vitæ, dwarf roſe-bay, and ſtrawberry-tree, have one ſtyle; ſoap-wort, and carnation, have two; cucubalus, viſcous campion, and ſandwort, three; hog-plum, navel-wort, and houſe-leek, five; *Neurada*, and American night-ſhade, ten.

DECANDRIA is likewiſe the name of an order or ſecondary diviſion in the claſſes *Monadelphia*, *Diadelphia*, *Gynandria*, and *Diœcia*, in all which, the claſſic character being unconnected with the number of ſtamina, that circumſtance, properly enough, ſerves as a foundation for the ſecondary or ſubordinate diviſion.

DECANTHERÆ, from δεκα, ten, and *antheræ*, the tops of the filaments. The name of an order or ſecondary diviſion in Ludwig's improved Method, conſiſting of plants, which to the claſſic character, whatever it is, add the circumſtance of having ten ſtamina, or male organs.

DECIDUUS, (from *dĕcido*, to fall off, or down, to die); —Deciduous; a term expreſſive of the ſecond ſtage of duration in plants, but, like *caducus*, ſuſceptible of different ſenſes, according to the particular part of the plant to which it is applied. A leaf is ſaid to be deciduous which drops in autumn.—Petals are deciduous which fall off with the *ſtamina* and *piſtillum*; and this epithet is applied to ſuch flower-cups as fall after the expanſion and before the dropping of the flower. This laſt is exemplified in berberry, and the flowers of the claſs *Tetradynamia*. *Vide* CADUCUS and PERSISTENS.

DECOMPOSITÆ, the name of the tenth claſs in Sauvage's *Methodus Foliorum*, conſiſting of plants, whoſe leaves are twice compounded; that is, have a common foot-ſtalk ſupporting a number of leſſer leaves, each of which is compounded. *Vide* FOLIUM *Decompoſitum*.

The term is exemplified in fumatory, barren-wort, bignonia, germander, feverfew, and ſome umbelliferous plants.

DECOMPOSITI *Flores*;—ſome compound flowers ſo termed by Linnæus, which contain within the ſame common calyx, a number of leſſer or partial flower-cups, that are each of them common to many florets. The term is exemplified in elephant's foot, and globe flower. A few other compound flowers, as globe-thiſtle, *gundelia*, and *ſtoebe*, have partial flower-cups; but each of theſe contains only a ſingle floret. Linnæus reduces all the compound flowers which have partial flower-cups, under the order *Polygamia Segregata* of the claſs Syngeneſia.

DECUMBENS *Flos*, from *decumbo*, to lie down; a drooping flower, in which the ſtamina and pointal are inclined towards the lower ſide; exemplified in wild-ſena, and the pea-bloom, or butter-fly-ſhaped flowers.

DEFOLIATIO, from *de*, and *folium*, a leaf; the fall of the

the leaves. A term oppoſed to *Frondeſcentia*, the annual renovation of the leaves, produced by the unfolding of the buds in ſpring.

Moſt plants in cold and temperate climates, ſhed their leaves every year. This happens in autumn, and is generally announced by the flowering of the common meadow ſaffron. The term is only applied to trees and ſhrubs; for herbs periſh down to the root every year, loſing ſtem, leaves, and all.

All plants do not drop their leaves at the ſame time. Among large trees, the aſh and walnut, although lateſt in unfolding, are ſooneſt diveſted of them: the latter ſeldom carries its leaves above five months.

On the oak and horn-beam, the leaves die, and wither, as ſoon as the colds commence; but remain attached to the branches till they are puſhed off by the new ones, which unfold themſelves the following ſpring. Theſe trees are doubtleſs a kind of evergreens; the leaves are probably deſtroyed only by cold; and, perhaps, would continue longer upon the plant, but for the force of the ſpring-ſap, joined to the moiſture.

In mild and dry ſeaſons, the lilac, privet, yellow jeſſamine of the woods, and maple of Crete, preſerve their leaves green until ſpring, and do not drop them till the new leaves are beginning to appear. The fig-tree, and many other trees that grow between the tropics, are of this particular claſs of ever-greens. The trees in Egypt, ſays Dr. Haſſelquiſt, caſt their leaves in the latter end of December, and beginning of January, having young leaves ready before all the old ones are fallen off; and to forward this operation of Nature, few of the trees have buds; the ſycamore and willow, indeed, have ſome, but with few and quite looſe *ſtipulæ*, or ſcales. Nature did not imagine buds ſo neceſſary in the ſouthern, as in the northern countries; this occaſions a great difference between them.

Laſtly, ſome trees and ſhrubs preſerve their leaves conſtantly through the whole year: and are not in the leaſt influenced by the clemency or inclemency of ſeaſons. Such

are the firs, juniper, yew, cedar, cypreſs, and many other trees, hence denominated ever-greens. Theſe preſerve their old leaves a long time after the formation of the new, and do not drop them at any determinate time. In general, the leaves of ever-greens are harder, and leſs ſucculent than thoſe which are renewed annually. The trees are generally natives of warm climates, as the alaternuſes of France and Italy, the ever-green oak of Portugal and Suabia.

Some herbaceous perennials, as the houſe-leeks and navel-worts, enjoy the ſame privilege with the ever-green trees, and reſiſt the ſeverities of winter: ſome even can diſpenſe with the earth for ſome time; being replete with juices, which the leaves imbibe from the humidity of the atmoſphere, and which, in ſuch plants, are, of themſelves, ſufficient for effecting the purpoſes of vegetation. It is for this reaſon that, unleſs in exceſſive hot weather, gardeners are ſeldom wont to water fat ſucculent plants, as the aloe, which rot, when they are moiſtened, if the ſun does not quickly dry them up.

The leaves of all the ever-green ſhrubs and trees, have a thin compact ſkin or cover, over their ſurface; as is eaſily diſcovered by macerating them in water, in order to ſeparate the parenchyma, or pulp, from the veſſels of the leaves; which cannot be effected in any of theſe ever-greens, till a thin parchment-like cover is taken off. Theſe trees and ſhrubs are found by experiment to perſpire but little, when compared with others which ſhed their leaves; and it is perhaps, principally owing to this cloſe covering, as alſo to the ſmall proportion of moiſture contained in their veſſels, that they retain their verdure, and continue through the winter on the trees. The nutritive juices of theſe plants always abound more or leſs with an oily quality, which ſecures them from being injured by ſevere froſts; ſo that many of theſe ever-green trees are adapted to grow in the coldeſt parts of the habitable world.

With reſpect to deciduous trees, the falling off of the leaves ſeems principally to depend on the temperature of the atmoſphere, which likewiſe ſerves to haſten or retard the

the

the appearance in queſtion. An ardent ſun contributes to haſten the dropping of the leaves. Hence in hot and dry ſummers, the leaves of the lime tree and horſe-cheſnut turn yellow, about the firſt of September; whilſt in other years, the yellowneſs does not appear till the beginning of October. Nothing, however, contributes more to haſten the fall of the leaves, than immoderate cold or moiſt weather in autumn; moderate droughts on the other hand ſerve to retard it. As a proof of this poſition, M. Adanſon relates, that in the year 1759, the leaves of the elm-tree, which generally fall off about the twenty-fifth of November, continued in verdure and vigour at Paris, where the autumn was remarkably dry, till the tenth of the following month.

The following table, reſpecting the mean times in which different trees ſhed their leaves, is founded upon obſervations.

Gooſeberry-tree, and Bladder-Sena,	generally quit their leaves about	October 1ſt.
Walnut and Aſh,		—— 15th.
Almond-tree, Horſe-cheſnut, and lime-tree,		—— 20th.
Maple, Hazel-nut, Black-poplar, and Aſpin-tree		—— 25th.
Birch, Plane-tree, Mountain-oſier, Falſe-acacia, Pear and Apple-tree,		November 1ſt.
Vine, Mulberry, Fig, Sumac, and Angelica-tree,		—— 10th.
Elm-tree, and Willow,		—— 15th.
Apricot, and Elder-trees,		—— 20th.

It deſerves to be remarked, that an ever-green tree grafted upon a deciduous, determines the latter to retain its leaves. This obſervation is confirmed by repeated experiments; particularly by grafting the laurel, or cherry bay, an ever-green, on the common cherry; and the ilex, or ever-green oak, on the oak.

DEHISCENTIA, *dehiſco*, to gape wide. The burſting open of the *anthers* for diſperſing the male-duſt; as likewiſe of the ſeed-veſſel called a capſule, for diſcharging the ſeeds when ripe. *Vide* ANTHERA and CAPSULA.

Moſt capſules ſplit or open at top; moſt *anthers* burſt on the ſides.

DENOMINATIO, the giving or impoſing of names—One of the principal foundations of practical botany; which, like the eſtabliſhment of proper characters, has been a neceſſary conſequence of the methodical diviſion into claſſes, genera, and ſpecies.

Linnæus's rules, with reſpect to the generic and ſpecific names of plants, and the great improvements made by that author, in this very important part of botany, are particularly mentioned under the main article, NOMINA, whither we refer the reader.

DENUDATÆ, (*denudo*, to ſtrip naked.) The name of an order in the former editions of Linnæus's Fragments of a Natural Method, conſiſting of plants whoſe flowers are naked, that is, want the *Perianthium*, or flower-cup, although they burſt from a *ſpatha*, or ſheath. *Vide* SPATHA.

The genera in this order were four; crocus, meadow-ſaffron, bulbocodium, and gethyllis. They are now moſtly removed to the order SPATHACEÆ, which ſee.

DESCRIPTIO. A deſcription,—a detail of all the parts and qualities of any object, compared or not compared with thoſe of another:—applied to botany, the natural character of the whole plant, including all the external parts. In this reſpect the deſcription of the ſpecies is diſtinguiſhed from the ſpecific difference, which regards the eſſential or ſtriking characters only.

A perfect, or complete deſcription is not confined to the principal parts of plants, as the root, ſtem, leaves, and fructification; but includes, likewiſe, whatever is conſpicuous in their external appearance: as the foot-ſtalks of the leaves and flower; the *ſtipulæ*, or ſcales; the *bracteæ*, or floral leaves; the glands, or veſſels of ſecretion; the weapons of offence and defence; the buds; the complication, or fold-

ing

ing of the leaves within the buds; and the habit or general appearance of the whole plant.

The order to be obſerved in the deſcription, is that of Nature, proceeding from the root to the ſtem; next the branches; then the foot-ſtalks, leaves, flower-ſtalks, and flowers. The impropriety would be manifeſt, to deſcribe the leaves, or their foot-ſtalks, before the ſtem, from which they proceed; or the ſtem before the root, which ſerves to elevate it.

Further, the deſcription of each ſeparate part ſhould be contained in a ſeparate paragraph; that the parts may appear equally diſtinct in deſcription, as they are in the plant itſelf. The names of the different parts too ought to be delineated in large letters, that they may the more eaſily be diſcovered by the reader; and that omiſſions in the deſcription, if there are any, may be more readily perceived and ſupplied. Nothing, in fact, can be more tedious and unentertaining than a very large deſcription, that is neither divided into paragraphs, nor diſtinguiſhes the parts of the plants in the manner juſt recommended.

A deſcription, to be complete, ought equally to avoid the extremes of prolixity and exceſſive brevity. Colour, dimenſion, and other circumſtances, which are ſubject to change, are never to be much inſiſted on: on the other hand, no ſtriking characters, no eſſential parts, however minute, ſuch as the *ſtipulæ*, or ſcales, the *bracteæ*, the *glandulæ*, the hairs, and downy appearances on plants, and ſuch like, are, from a ſtudied and faulty brevity, to be excluded from the deſcription of any ſpecies whatever.

Laſtly, a ſcientific deſcription ſhould employ only terms of art, if theſe are ſufficient; and delineate all the parts, according to their number, figure, proportion, and ſituation.

The intelligent reader will diſcover, whether in deſcribing the ſeveral natural orders that occur in the courſe of this work, I have practiſed the rules juſt delivered. Some difference, however, obtains in the mode of deſcribing an aſſemblage or family of plants, and a particular ſpecies.

The moſt complete ſpecific deſcriptions are thoſe of Cluſius,

ſius, Columna, Bauhin, Rheede, Ray, Rumfius, Plumier, Dillenius, Vaillant, Scheuchzer, Linnæus in his *Hortus Cliffortianus*, and Haller.

DETERMINATIO *Foliorum*. *Vide* FOLIUM.

DIADELPHIA, from δις, twice, and ἀδελφία, a brotherhood; two brotherhoods; the ſeventeenth claſs in Linnæus's Sexual Syſtem, conſiſting of plants whoſe flowers are hermaphrodite, and have the ſtamina, or male organs, united below into two ſets of cylindrical filaments.

This claſs, which is a true natural order or family, correſponds to the *Leguminoſæ*, or plants having pods, of Moriſon, Hermannus, Boerhaave, Ray, and Royen; the *tetrapetali irregulares* of Rivinus and Chriſtopher Knaut; the *tetrapetali difformes* of Chriſtian Knaut; and the *Papilionacei*, or butterfly-ſhaped flowers, of Tournefort and Pontedera.

The claſſical characters of this numerous and ſimilar aſſemblage of plants, will be delivered under Linnæus's Natural Order PAPILIONACEÆ, which ſee.

The orders, or ſecondary diviſions, in this claſs, are founded on the number of ſtamina, conſidered as diſtinct. Some pea-bloom, or butterfly-ſhaped flowers, have five ſtamina, or male organs, as Monnieria; ſome ſix, as Fumatory; ſome eight, as Milk-wort; ſome ten, as Broom, Bladder-Sena, Lupine, Lady's-Finger, Vetch, and the far greater number of butterfly-ſhaped flowers. It is only the laſt order that is included in the natural family *Papilionaceæ*; the remaining four genera are diſtributed among other families, to which they have, at leaſt, an equal alliance. Fumatory and *Monnieria* are arranged under the order *Corydales*; Milk-wort, under *Lomentaceæ*.

I cannot help remarking, before I conclude this article, that the names given by former botaniſts to the extenſive claſs of plants in queſtion, are much more characteriſtic of their nature and appearance, than that of *Diadelphia*.

In fact, the figure of the flowers and fruit never varies: the latter being always of the pod kind; the former of the butterfly-ſhape. On the other hand, the two ſets of united ſtamina, the only claſſic character expreſſed in the Linnæan

title, are never to be traced without difficulty: for one of the ſets only is properly united; the other conſiſting of a ſingle filament, which, in moſt plants, adheres ſo cloſely to its kindred ſet, that it cannot be ſeparated without the application of a pin or needle for that purpoſe. In ſome even, no ſeparation can be effected by this means.

DIÆTETICI. By this name Linnæus diſtinguiſhes a claſs of Medical Botaniſts, who pronounce of the qualities of vegetable food, by taſte and ſmell. Such are Quercetanus, Nonnius, Behren, and Liſter.

DIANDRIA, (from δις, twice, and ἀνηρ, a man) the name of the ſecond claſs in Linnæus's ſexual ſyſtem, conſiſting of hermaphrodite plants, which, as the name imports, have flowers with two *ſtamina* or male organs.

The orders in this claſs are three, derived from the number of ſtyles or female parts. Moſt plants with two ſtamina have one ſtyle, as Jeſſamine, Lilac, Privet, Veronica, and Baſtard Alaternus. Vernal graſs has two ſtyles; Pepper, three.

DIANGLÆ, (from δις, twice, and ἀγγος, a veſſel) the ſixteenth claſs in Boerhaave's ſyſtem, conſiſting of plants whoſe ſeeds are contained within two capſules, or within a ſingle capſule having two cells. It is exemplified in purple looſe-ſtrife.

DIANTHERÆ (from δις, twice, and *antheræ*, the tops of the ſtamina.) The name of an order or ſecondary diviſion in Ludwig's Improved Method, conſiſting of plants, which, to the claſſic character, whatever it is, add the circumſtance of having two ſtamina or male organs.

DICOTYLEDONES (from δις, twice; and *Cotyledon*, a ſeed-lobe or ſeed-leaf) plants whoſe ſeeds have two ſide-lobes, and conſequently riſe with two ſeminal leaves. Moſt plants are of this kind. *Vide* COTYLEDONES.

In the lip and maſqued flowers, the *Didynamia* of Linnæus, and in plants, whoſe ſeed-veſſel is of the apple, cherry, or pod kind, the ſeed-leaves riſe unaltered; that is, without any farther extenſion or developement, than when they made part of the ſeed.

In mallow, and the croſs-ſhaped flowers, they appear double; in buck-wheat they are rolled up; in cotton, folded or plaited; in ſalt-wort, glaſs-wort, ceratocarpus, malabar night-ſhade, and all the pot-herbs, they are ſpiral, or twiſted like a ſcrew.

DIDYNAMIA, (from δὶς, twice, and δύναμὶς, power,) two powers; the name of the fourteenth claſs in Linnæus's Sexual Method, conſiſting of plants with hermaphrodite flowers, which have four ſtamina or male organs, two of which are long, and two ſhort.

This numerous claſs of plants contains two natural aſſemblages or families, and conſiſts of flowers, which, beſides the circumſtance expreſſed in the title, have one very irregular petal, ſometimes divided into two diſſimilar lips, ſometimes ſhaped like a maſque. From an attention to the different figure of this grinning or gaping petal, former botaniſts, who, perhaps, never dreamt of the ſex of plants, or, if they did, thought of nothing leſs than founding a ſyſtem upon it, arranged the plants in queſtion under two claſſes, which they conſidered as having nothing in common; the number of the ſtamina, and their proportion being totally diſregarded. In fact, the two orders, which ſubdivide the claſs Didynamia, and correſpond to the ſame number of claſſes in moſt botanical ſyſtems, are ſo very diſſimilar, that, I believe, it would have been difficult, except from the number and proportion of the ſtamina, to have reduced them under one head, with a ſingle circumſtance of reſemblance. The petals, ſeed-bud, ſeed-veſſel, and ſeeds, are totally different in the two orders. The habit too, or general appearance of the plants, is perfectly different; what two things, in fact, can be more diſtinct than mint and bear's breech? or marjoram and fox-glove?

Linnæus himſelf is ſo ſenſible of the few relations that ſubſiſt betwixt theſe two orders of plants, that, in his Fragments of a Natural Method, he is obliged to ſeparate them, and have recourſe to two diviſions, the one from Ray, the other from Tournefort; although in the *Genera Plantarum*, he conſiders the claſs *Didynamia* as having, independently of

that

that expreſſed in the title, particular claſſic characters; that is, a variety of relations, which approximate the plants in that particular claſs to one another.

The two orders in the claſs Didynamia are ſtrongly marked; being founded upon the preſence or abſence of the ſeed-veſſel. Their names are borrowed from Hermannus. The order *Gymnoſpermia* conſiſts of plants, which, as mint, hyſſop, ſavory, lavender, and other aromatics, have four naked ſeeds lodged in the bottom of the calyx without any proper ſeed-veſſel. Theſe are the *Labiati*, or lip-flowers, of Tournefort and Pontedera; the *Verticillatæ*, or plants that flower at the joints, or whoſe flowers are placed in whirls round the ſtalk, of Hermannus, Boerhaave, Ray, and Linnæus in his Fragments of a Natural Method. *Vide* VERTICILLATÆ.

The ſecond order, termed *Angioſpermia*, conſiſts of plants, whoſe ſeeds, as the name imports, are lodged in a pericarpium or ſeed-veſſel. To this order belong fig-wort, foxglove, bignonia, eye-bright, toad-flax, calve's ſnout, oily purging grain, agnus caſtus, bear's breech, and ſeveral others. *Vide* ANGIOSPERMIA.

Theſe plants are the *Perſonatæ* or maſqued flowers of Tournefort, and make part of the third claſs in his ſyſtem. Under the ſame name Linnæus arranges them in his Fragments of a Natural Method. *Vide* PERSONATÆ.

Profeſſor Royen, in his Floræ Leydenſis Prodromus, has traced the outlines of what he calls a natural method, in which we find the claſs *Didynamia* of Linnæus diſtinguiſhed as one entire natural family or order, under the name *Ringentes*, or the grinning flowers. As I never ſuffer my admiration for any man, however diſtinguiſhed, to betray me into the fatal complaiſance of adopting his errors; I muſt beg leave to differ from both the learned doctors, and to conſider the claſs *Didynamia*, as compoſed of two natural orders of plants, that have not the leaſt affinity together.

The lip flowers, which conſtitute the firſt order, are deſcribed under the article VERTICILLATÆ; thoſe with a maſque, which conſtitute the ſecond, under PERSONATÆ.

DIFFORMIS *flos* (from δὶς, twice, and *forma*, a form) having

having two different forms, irregular; the term is expreſſive of the inequality and irregularity of the petals. It is uſed by Jungius and Chriſtian Knaut; and is ſynonimous to the *Anomalus flos* of Tournefort and Pontedera, the *Irregularis flos* of Rivinus, and the *Corolla irregularis* of Linnæus.

The term is exemplified in the maſqued flowers, aconite, columbine, violet, fumatory, lark-ſpur, orchis, and other plants in which the petals are very irregular and diſſimilar.

DIFFORMIS is the name of a ſeries of claſſes in Chriſtian Knaut's Method, conſiſting of plants which have one or more irregular petals. Among many others, theſe claſſes comprehend all the grinning and pea-bloom flowers; they correſpond to the diviſion in Rivinus's method, termed *Irregulares*.

DIGYNIA (from δις, twice, and γυνη, a woman). The name of an order or ſecondary diviſion in each of the firſt thirteen claſſes, except the ninth, in Linnæus's Sexual Method; conſiſting of plants, which to the claſſic character, whatever it is, add the circumſtance of having two ſtyles or female organs.

DIŒCIA (from δις, twice, and οικια, a houſe or habitation,) two houſes. The name of the twenty-ſecond claſs in Linnæus's Sexual Method, conſiſting of plants, which, having no hermaphrodite flowers, produce male and female flowers on ſeparate roots. Theſe latter only ripen ſeeds, but require, for that purpoſe, according to the Sexualiſts, the vicinity of a male plant, or the aſperſion of the male duſt. From the ſeeds of the female flowers are raiſed both male and female plants.

The plants then in the claſs Diœcia, are all male or female; not hermaphrodite as in the greater number of claſſes; or with male and female flowers upon one root, as in the claſs *Monœcia* of the ſame author.

Accurate as the Swediſh Botaniſt undoubtedly is, there are many plants diſperſed through the different claſſes in the *Genera Plantarum*, which have male and female flowers on diſtinct roots, and therefore ought, in ſtrict propriety, to have been reduced under the claſs *Diœcia*. Linnæus, ſenſible

ſible of the weak ſide of his ſyſtem, has endeavoured to anticipate and deſtroy the force of this criticiſm, by inſinuating that ſuch plants could not properly enter into this claſs, becauſe the circumſtance alluded to does not run through the genus, but is peculiar to ſome particular ſpecies only. To an unexperienced botaniſt the reaſon is ſatisfactory; but examined with attention, it is reſolved into a mere begging of the queſtion; for, if the ſex of plants be a doctrine of ſuch importance in botany, as to juſtify the joining together of things which Nature never joined, and the ſeparation of others which were never meant to be disjoined; it certainly authorized the great reformer of the ſcience to erect ſeveral genera out of one, eſpecially when the leading principles of his ſyſtem required it. The liberties he has taken with the genera of Ray, Tournefort, Boerhaave, and other eminent botaniſts, are well known. In fact, what a perplexed ſtudy is Botany now rendered, by the prodigious multiplication of ſynonimous genera! To whom then is this mighty confuſion owing? Why, in a great meaſure, to Linnæus, who, by ſplitting ſome genera, incorporating others, and introducing a variety of new names, has rendered every other ſyſtem unintelligible, without the aſſiſtance of his nomenclature.

When ſuch a renovation of the genera was to take place, where would have been the impropriety of making diſtinct genera of moſt of, or all the ſpecies, to be afterwards enumerated, when they could not be conſidered as mere ſpecies without infringing the fundamental laws of his ſyſtem? To take an example; a ſpecies of campion, the lychnis of Linnæus, bears male and female flowers on ſeparate plants. I ſhall ſuppoſe that, with the aſſiſtance of the *Genera Plantarum*, or *Syſtema Naturæ*, I would explore the claſs, order, genus, and ſpecies of a plant of the male lychnis, which, by chance, I have found in the fields. To determine the claſs, I reckon the number of ſtamina; which finding to be ten, of an equal length, and united neither above nor below, I am almoſt ready to refer my plant to the tenth claſs, *Decandria*, when I reflect, that, beſides the characters

juſt

juſt mentioned, the claſs in queſtion bears hermaphrodite flowers. Upon examining the plant with a view to this particular, I can diſcover no ſtyle, nor ſeed-bud; the flower then, is not hermaphrodite, but male; conſequently cannot belong to the claſs under which I was raſhly going to arrange it. I now examine the whole plant, if, perchance, I can diſcover any female flowers placed promiſcuouſly with the male upon the ſame root; a circumſtance which would immediately determine my plant to the claſs *Monœcia:* but not being able, after the ſtricteſt ſearch, to diſcover any difference in point of ſex, I conclude the plant to be male, and to belong to the claſs *Diœcia*, in which male and female flowers are placed apart on ſeparate plants. Having, in this manner, detected the claſs, I proceed to explore the order, which I ſoon diſcover to be the ninth, *Decandria*, that order containing ſuch *diœcious* plants, if I may uſe the expreſſion, as have their male flowers furniſhed with ten ſtamina. I have now reduced my plant to one of four genera; for the order in queſtion contains no more; theſe are Papaw, (Carica) *Kiggelaria*, Indian Maſtick (Schinus) and myrtle-leaved ſumach (Coriaria). Theſe names begin to ſtagger me; for to my belief and even knowledge, the plants juſt now mentioned are all natives of very warm countries, and are, beſides, of the tree and ſhrub kind: whereas the plant to be explored riſes with an herbaceous ſtalk, that is not above two or three feet high. But ſuppoſing that I am ſuch a novice in the ſcience, as to be ignorant of theſe particulars; I proceed, ſatisfied that I have detected the claſs and order, to aſcertain the genus. I begin with *Carica*; but ſoon find the impropriety of arranging the plant under that genus, which has only one funnel-ſhaped petal; whereas my unknown flower has five diſtinct petals, with long claws. The next genus *Kiggelaria*, although ſomewhat ſimilar in the calyx and petals, has a glandular nectarium in the bottom of the flower, of which I can diſcover no trace in the other.—— The filaments of the ſtamina too are very ſhort; thoſe in the plant to be diſcovered, very long. I proceed to *Coriaria*, the next genus, which is quickly diſmiſſed on account of

the minuteneſs and diviſions of the calyx: and comparing my plant with *Schinus*, the laſt genus in this order, I can diſcover nothing to convince me that I have yet detected the genus of the flower in queſtion. What remains then but to conſider it as a new genus, which Linnæus has never ſeen, and conſequently never deſcribed? In this belief, I diſcover my new acquiſition, as I imagine it, to ſome ſkilful botaniſt, who, ſurprized at my ignorance, aſſures me that it is a common weed, and grows wild in many parts of England; that it belongs to the claſs *Decandria*, and not *Diœcia*, in the Sexual Method, although it poſſeſſes the characters of the latter, and not of the former; but that as thoſe characters are only to be found in the particular ſpecies under conſideration, the founder of that method did not chuſe to ſplit the genus, and arrange its ſeveral parts under claſſes, ſo very diſtinct and remote: though, upon more frivilous grounds, he had torn and mangled, without reſerve, the genera of former botaniſts, when they did not coincide with his own principles or opinions.

For examples of the impropriety complained of, the reader is referred to the following ſpecies, which, by Linnæus, are arranged under claſſes and genera containing hermaphrodite flowers.

Valeriana Dioica.
Rhamnus Catharticus.
——— Infectorius.
——— Alpinus.
Rhus vernix.
Rumex tuberoſus.
——— Multifidus.
——— Acetoſa.
——— Acetoſella.
——— Aculeata.
Lonicera Dioica.
Laurus nobilis.
Guilandina Dioica.
Cucubalus Otites.

Lychnis

Lychnis Dioica.
Phytolacca Dioica.
Spiræa Aruncus.
Rubus Chamæmorus.
Clematis Virginiana.
——— Dioica.
Thalictrum Dioicum.
Napæa Dioica.
Gnaphalium Dioicum.
Gypſophila paniculata.
Phylica Dioica.

The three following ſpecies are improperly referred by Linnæus to the claſs *Monœcia*, which contains plants with male and female flowers upon the ſame root.

Carex Dioica.
Urtica Dioica.
Morus Nigra.

It is worthy of obſervation, that not a ſingle ſpecies in the rough-leaved plants of Ray, and the lip, maſqued, croſs-ſhaped, and pea-bloom flowers of Tournefort is found to differ in point of ſex. Theſe are true natural aſſemblages, accurately defined by fixed and preciſe characters. For the ſame reaſon we have been able to trace but one deviation of Nature in the compound flowers; I mean, in a ſpecies of cud-weed. As deviations, however, or exceptions to the general law of their nature, I would remove all ſuch ſpecies from a claſs or order, in which, at beſt, they appear but as vegetable monſters; and either place them apart in an appendix to the work, under the title of Anomalous, that is, irregular plants which do not commodiouſly arrange themſelves under any of the foregoing claſſes, as Ray, Tournefort, and other eminent botaniſts have done: or refer each ſpecies as a genus, if neceſſary, to the particular claſs, to which, in ſtrict conformity to the principles of the ſyſtem, it can only belong.

The orders in the claſs *Dioecia* are fourteen, founded upon the number, union and ſituation of the ſtamina in the male

male plants: their names are thoſe of the claſſes containing hermaphrodite flowers. *Najas* has one ſtamen or male organ; willow, two; poets caſia, three; miſletoe, and ſea-buck-thorn, four; piſtacia-nut, ſpinach, and hop, five; rough bindweed (Smilax) and *Dioſcorea*, ſix; poplar, and roſe-root, eight; mercury, nine; papaw, and Indian maſtick, ten; moonſeed, and baſtard-hemp, twelve. In *Cliffortia*, the ſtamina are numerous; in juniper, yew, and ſhrubby horſe-tail, they are united by their filaments into a pillar; in butcher's-broom, they are united by the *anthers* or tops; and in *Clutia*, ſays Linnæus, they are attached to the middle of a very long cylindrical ſtyle in the centre of the male flowers. Here is another impropriety; the very name of the order under which *Clutia* arranges, (*Diœcia Gynandria*) is abſurd. For if a genus of plants be truly *diœcious*, that is, contain male and female plants on different roots, the ſtamina of the male flowers cannot be inſerted into the ſtyle or female organ, becauſe ſuch female organ is not preſent. On the other hand, if the female organ, or any of its parts, be preſent and conſpicuous, the plant is not *diœcious*, but hermaphrodite. In the claſs *Monœcia*, which contains plants with male and female flowers on the ſame root, the order in queſtion again occurs, and with equal impropriety as in the preſent caſe. Baſtard orpine, (Andrachne) the ſingle genus in that order, is nearly allied to *Clutia* in the claſs *Diœcia*.

DIPETALI (from δις, twice, and πεταλον, a petal,) having two petals; the name of two claſſes in Rivinus's method, conſiſting of regular and irregular flowers with two petals. Enchanter's night-ſhade and *Commelina* furniſh examples.

DIPSACEI, (from *Dipſacus*, teaſel); the name of an improper diviſion in Vaillant's Arrangement of the Compound Flowers, conſiſting of plants, whoſe flowers, like thoſe of teaſel and ſcabious, form a head, and are contained within a common calyx. Theſe plants differ from the Compound Flowers of Linnæus, in having their ſtamina free, or diſtinct both at bottom and top: the partial flowers too are frequently furniſhed with a proper calyx. They correſpond to

Linnæus's aggregate flowers properly ſo called. *Vide* AGGREGATUS *flos*. Beſides thoſe already mentioned, viburnum, honey-ſuckle, and valerian furniſh examples.

DISCOIDEÆ, (from *Diſcus*, the middle of a radiated compound flower) the name of a claſs in Ray's method, which includes a great part of the *Radiati* of Tournefort. A radiated diſcous flower has ſeveral ſemi-florets placed in the circumference like ſo many rays round the diſk; ſuch are groundſel, feverfew, aſter, golden rod, daiſy, and many others.

A naked diſcous flower has no rays or ſemi-florets in the circumference, as cudweed, foreign colt's-foot, *Cotula*, and ploughman's ſpikenard.

DISCOIDEÆ, is likewiſe the name of diviſion in Linnæus's Arrangement of the Compound Flowers.

DISCUS, (Gr. Δισκος, *diſcus*, a quoit, diſh, and from its flat and round appearance, the circumference of the ſun.) This term in the modern Botanical Nomenclature ſignifies the centre of a radiated compound flower, and generally conſiſts of ſmall florets with a hollow regular petal. It is commonly ſurrounded by large, flat, tongue-ſhaped petals in the circumference or margin; as in daiſy, groundſel and leopard's bane; ſometimes the circumference is naked, as in cotton-weed, and ſome ſpecies of colt's-foot.

DISCUS *folij*, the whole ſurface of the leaf.

DISSEMINATIO. The various and wonderful contrivances of Nature to diſperſe and ſcatter abroad the ſeeds of vegetables, for the purpoſes of increaſe. For particulars on this curious ſubject, the reader is referred to the article SEMEN.

DISSEPIMENTUM, (from *Sepes*, a hedge.) By this name Linnæus denominates the partitions, which, in dry ſeed-veſſels, as capſules and pods (Siliqua) divide the fruit internally into cells.

DODECANDRIA (from δωδεκα, twelve; and ανηρ, a man.) The name of the eleventh claſs in Linnæus's Sexual Syſtem; conſiſting of plants with hermaphrodite flowers, that, according to the title, have twelve ſtamina or male

organs. This claſs, however, is not limited with reſpect to the number of ſtamina. Many genera have ſixteen, eighteen, and even nineteen ſtamina; the eſſential character ſeems to be that, in the claſs in queſtion, as in *Polyandria*, the 13th, the ſtamina are inſerted into the receptacle: whereas in the intermediate claſs, *Icoſandria*, which is as little determined in point of number as the other two, they are attached to the inſide of the calyx.

The orders in this claſs, which are ſix, are founded upon the number of the ſtyles, or female organs. Aſarabacca, mangoſtan, ſtorax, purple looſe-ſtrife, wild Syrian rue, and purſlane, have one ſtyle; agrimony and heliocarpus have two; burning thorny plant, and baſtard rocket, three; *Glinus*, five; *Illicium*, eight; and houſeleek twelve.

DODRANS, a term of meaſure. *Vide* MENSURA.

DRUPA, and DRUPPA, (uſed by Pliny for an olive waxing black with ripeneſs, and ready to fall off the tree); a ſpecies of ſeed-veſſel that is ſucculent, has no valve or external opening like the capſule and pod, and contains within its ſubſtance a ſtone or nut. The cherry, plumb, peach, apricot, and all ſtone fruit, are of this kind.

The term, which, as we have ſeen, is of great antiquity, is ſynonimous to Tournefort's "fructus mollis officulo," ſoft fruit with a ſtone; and to the *Prunus* of other botaniſts.

The ſtone, or nut, which, in this ſpecies of fruit, is ſurrounded by the ſoft pulpy fleſh, is a kind of woody cup, containing a ſingle kernel or ſeed, (Nucleus.)

The reader will be miſtaken, if he imagines that the definition juſt given will apply to every ſeed-veſſel denominated *Drupa* in the *Genera Plantarum*. The almond is a *Drupa*, ſo is the ſeed-veſſel of the elm tree and the genus *Rumphia*; though far from being pulpy or ſucculent, the firſt and third are of a ſubſtance like leather; the ſecond like parchment. The ſame may be ſaid of the walnut, Piſtacia-nut, *Guettarda*, *Quiſqualis*, jack-in-a-box, and ſome others.

Again, the ſeeds of the elm, *Schrebera*, *Flagellaria*, and the mango-tree, are not contained in a ſtone. The ſeed-

veſſel of burr-reed is dry, ſhaped like a top, and contains two angular ſtones.

This ſpecies of fruit, or more properly ſeed-veſſel, is commonly roundiſh, and, when ſeated below the calyx, or receptacle of the flower, is furniſhed, like the apple, at the end oppoſite to the foot-ſtalk, with a ſmall umbilicus or cavity, produced by the ſwelling of the fruit before the falling off of the flower-cup.

DRUPACEÆ (from Drupa) an order of plants in the former editions of Linnæus's Fragments of a Natural Method, conſiſting of the almond, peach, plumb, apricot, cherry, and bird-ſeed, which have that ſpecies of fruit-veſſel called by Linnæus, *Drupa*. *Vide ſupra.*

Theſe plants are now reduced to two genera, *Amygdalus* and *Prunus*, and make part of the natural order POMACEÆ, which ſee.

DUMOSÆ, (from Dumus, a buſh) buſhy plants; the name of the forty-third order in Linnæus's Fragments of a Natural Method; conſiſting of a number of ſhrubby plants, which are thick ſet with irregular branches, and buſhy.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Thickſet buſhy Shrubs, with Leaves placed alternate.

Linnæan Genera.			*Engliſh Names.*
Achras,	—	—	Sapota.
Caſſine,	—	—	Caſſioberry-buſh, and South-Sea or Paraguay tea.
Ceanothus,	—	—	New Jerſey tea.
Celaſtrus,	—	—	Staff-tree.
Chryſophyllum,	—	—	Star-apple, and damſon-tree.
Fagara.			
Ilex,	—	—	Holly.
Phylica,	—	—	Baſtard alaternus.

Prinos,

Linnæan Genera.			*Engliſh Names.*
Prinos,	—	—	Winter-berry.
Rhamnus,	—	—	Buckthorn, alaternus, jujube-tree.
Rhus,	—	—	Sumach, poiſon-tree, Varniſh-tree.
Schinus,	—	—	Indian maſtick.
Sideroxylon,	—	—	Iron-wood.

SECTION II.

Thickſet buſhy Shrubs, with Leaves placed oppoſite.

Callicarpa,	—	—	Johnſonia.
Euonymus,	—	—	Spindle-tree.
Sambucus,	—	—	Elder.
Tomex.			
Viburnum,	—	—	Pliant mealy-tree, or wayfaring tree, lauriſtinus and gelder-roſe.

Habit and Structure of the Plants of this Order.

The plants of this order are all of the ſhrub and tree kind, thick and buſhy, and riſe from ſix to twenty-five, thirty, and even forty feet high. Many of them too, as baſtard alaternus, holly, iron-wood, new-jerſey tea, ſtar-apple, viburnum, winter-berry, and ſome others, retain their beautiful leaves during the whole year.

The ROOTS are branched and fibrous.

The STEMS are cylindric; the young branches ſometimes angular.

The BUDS are naked, that is, without ſcales, in the evergreen ſhrubs of this order; covered with ſcales in moſt of the others.

The LEAVES, which in ſome genera are ſimple, in others compound, are placed alternate in plants of the firſt ſection; oppoſite, in thoſe of the ſecond. In caſſioberry-buſh, ſome of the leaves are almoſt oppoſite.

From the baſe of the leaf of the gelder-roſe, a ſpecies of

viburnum, proceed a number of ſmall glands or ſecretory veſſels.

Holly, elder, and ſpindle-tree have two STIPULÆ or ſcales, one on each ſide of the branches; in the two laſt they are ſlender like hairs, and almoſt imperceptible.

The branches of ſtaff-tree, and of ſome of the ſpecies of *Rhamnus*, are terminated by a thorn, which diſappears by culture. Jujube tree, and Chriſt's-thorn, two other ſpecies of *Rhamnus* have, at both ſides of the origin of the footſtalk of the leaves, two unequal ſpines; the one of which is erect and large; the other, ſmaller and curves downwards.

In *Fagara* there are placed along the branches, and ribs of the leaves, a number of prickles, which being ſlightly attached to the bark of the plants, fall off quickly. In holly, the leaves are thorny.

The leaves and branches of the genus *Tomex* are covered with ſoft downy hairs, which have a ſilver-white appearance. This kind of pubeſcence is termed *tomentum*, whence the genus derives its name.

The FLOWERS are moſtly hermaphrodite. Indian maſtick, and ſome ſpecies of buck-thorn and ſumach, have male and female flowers upon different roots: holly too, ſtaff-tree, *fagara*, and alaternus, a ſpecies of buck-thorn, ſometimes produce male flowers on one root, and hermaphrodite flowers on another; the laſt has ſometimes male and female flowers on the ſame root.

The flowers proceed from the angles of the leaves, either ſingly, as in winter-berry; or in cluſters, as in buck-thorn, johnſonia, caſſioberry-buſh, and iron-wood; or they terminate the ſtem in that ſort of flowering head called a CORYMBUS; as in baſtard alaternus.

The CALYX is generally very ſmall, placed below or around the ſeed-bud, and conſiſts of one leaf, with four, five, or ſix diviſions, which are permanent, that is, accompany the ſeed-bud to its maturity. The genus *Rhamnus* has no calyx. In ſapota, it is compoſed of ſix diſtinct leaves. In elder and viburnum, it is placed above the ſeed-bud.

The PETALS are, in number, from one to five; in buck-

thorn

thorn and ſapota, five ſcales, which ſerve for a *nectarium*, are inſerted into the chaps (*faux*) of the tube of the petal.

The STAMINA are either four, as in johnſonia and holly; five, as in ſumach, ſpindle-tree, and the greater number of plants in this order; ſix, as in ſapota and winter-berry; or ten, as in Indian maſtick.

The SEED-BUD is generally roundiſh, and placed within the flower; in elder and viburnum it is placed below it.

The STYLE is generally ſingle, and ſometimes wanting, as in Indian maſtick, ſumach and viburnum: the latter, as well as the elder, has a gland or veſſel of ſecretion, in its place.

The STIGMA, or ſummit of the ſtyle, is either ſingle, as in iron-wood and buckthorn; or triple, as in ſumach, viburnum, caſſioberry-buſh, and elder.

The SEED-VESSEL in this order is generally a berry; ſometimes a dry capſule, as in ſpindle-tree and baſtard alaternus: in iron-wood, the ſeed-veſſel is of the cherry kind; in ſapota, of the nature and ſubſtance of an apple.

The SEEDS are generally ſingle and egg-ſhaped. In the ſpindle and ſtaff-trees, they are wrapped up in a proper coat or *arillus*. *Vide* ARILLUS.

Theſe plants have no ſtriking claſſical character; I have, however, after the example of Linnæus, conſidered them as a natural order, though their relations are not ſo numerous as ſtrictly to entitle them to that appellation.

The berries, bark, and flowers of many of theſe plants are purgative, and act particularly on the lymph and bile.

Sapota, ſometimes called Mammee Sapota, is very common in the Weſt India iſlands, where the trees are planted in gardens for the fruit, which, by many perſons, is much eſteemed. The flowers, which are of a cream colour, are ſucceeded by an oval top-ſhaped apple covered with a browniſh huſky ſkin, under which is a thick pulp, of a ruſſet colour, and very luſcious taſte, including one or two hard oval nuts or ſtones. It is called Natural Marmalade,

from its reſemblance in taſte to marmalade of quinces. The ſtones or kernels of this fruit, taken in emulſion, are a powerful aperient, and reckoned ſpecific in gravelly complaints.

The leaves of Johnſonia, which grows plentifully in South Carolina, are uſed with ſucceſs in dropſical caſes.

A decoction of the root of *Ceanothus Americanus*, or New-Jerſey tea, is eſteemed a certain remedy, not only in ſlight gonorrhœas, which it ſtops in two or three days without any bad conſequences; but alſo in the moſt inveterate venereal complaints. A large veſſel muſt be employed in this decoction, becauſe the plant, in the time of boiling, throws up a great quantity of froth, which muſt not be loſt. The inhabitants of North America, where this ſhrub naturally grows, dry the young leaves and infuſe them in water like tea; whence the name of New-Jerſey tea, by which title the ſeeds are generally brought into Europe.

The root of the ſtaff-tree, being powdered, is uſed by the negroes of Senegal as a ſpecific againſt gonorrhœas, which it is ſaid to cure in eight, and ſometimes at the end of three days. An infuſion of the bark of a ſpecies of ſtaff-tree, which grows in the iſle of France, is ſaid to poſſeſs the ſame virtues.

Star-apple is garniſhed with oval leaves that are ſmooth above, and of a beautiful gold colour, ſhining like ſatin on their under ſide; whence the name Chryſophyllum or golden leaf, by which it is known among botaniſts.

The wood of the ſpindle tree is yellow, and uſed in works of ſculpture. By the muſical inſtrument makers it is employed for toothing of organs and virginal keys. The branches are cut into tooth-picks and ſkewers, and ſpindles are made of the wood, whence the tree derives its title. In ſome countries, ſays Miller, it is called dog-wood.

From the *arillus*, or proper covering of the ſeeds of the ſpindle-tree, is drawn a very beautiful red tincture. The powder of the capſules, ſprinkled upon the head and cloaths is ſaid to deſtroy lice and other vermin.

The capſules, or dry ſeed-veſſels of the genus ſagara, are uſed by the Africans for pepper.

Iron-

Iron-wood is ſo called from its great weight, its hardneſs, and the cloſeneſs of its grain; for it is proof againſt all weather, and ſcarce known to ſuffer any decay in ſeveral ages; it is ſo heavy, that it will ſink in water.

Of the bark of common holly is made the common bird-lime, which is better than that made of miſletoe. The wood is very white, and admits of an exceeding fine poliſh. It is chiefly made into hones for whetting of razors.

The berries of narrow-leaved ever-green privet, the *Rhamnus Alaternus* of Linnæus, the alaternus anguſtifolia of Tournefort, are ſold in France by the name of Avignon-berries for the uſe of painters, who prepare from them a yellow colour or pigment. Theſe berries are, by ſome, erroneouſly imagined to be the fruit of the dwarf buckthorn, or *Rhamnus Catharticus Minor*.

The Egyptian thorn, the œnoplia ſpinoſa of Caſpar Bauhin; the nabca paliurus athenæi of Proſper Alpinus; the naba or nabka of the Arabians; and the rhamnus ſpina chriſti of Linnæus; is ſuppoſed, by many travellers, to be the tree from which the crown of thorns that was put on the head of our Saviour, was made. It is very common in the eaſtern countries, particularly in Paleſtine. This plant, ſays Haſſelquiſt, was very proper for the purpoſe to which it is ſuppoſed to have been applied, as it has many ſmall ſharp ſpines, or thorns, well adapted to give pain. The crown, too, might be eaſily made of the ſoft, round and pliant branches with which this tree or hedge is furniſhed. What in Haſſelquiſt's opinion ſeems to be the greateſt proof of the ſuppoſed uſe of this plant, is, that its leaves have a great reſemblance to thoſe of ivy, with which emperors and generals were wont to be crowned. The enemies of Chriſt would, perhaps, deſire to have a plant ſomewhat reſembling that which was uſed in triumphs and times of feſtivity, that there might be calumny and reproach even in the puniſhment.

Syrup of buckthorn, which is prepared of the berries of the purging or common buckthorn, is reckoned a good medicine in the dropſy, jaundice, itch, and other eruptions of the

the ſkin. It is of a very diſagreeable bitterneſs, cauſes thirſt, and is proper for ſuch as are eaſy to work upon, and whoſe ſtrength has not been impaired by continual diſeaſes. The berries may be eaſily known by counting their ſeeds, which are four in number; and, by rubbing the juice upon white paper, which it ſtains of a green colour.

Of the juice of theſe berries the French prepare a beautiful green pigment or colour, known among painters by the name of Verd-de-veſſie.

Half an ounce of an infuſion of the inner bark of the berry-bearing alder, the *Rhamnus Frangula* of Linnæus, or a dram of the powder, proves as violent a purge as rhubarb. The berries are often brought to market, and impoſed upon the ignorant for buckthorn-berries. They may, however, be eaſily diſtinguiſhed; the berries of buck-thorn having generally four ſeeds; thoſe of frangula, but two.

Jujube, which Linnæus has joined along with alaternus, berry-bearing alder, and Chriſt's thorn, to his genus *rhamnus*, by the name of *rhamnus Zizyphus*, is a native of the warm parts of Europe, particularly the ſouth of France, and Italy, having been tranſported thither from Syria, as Linnæus obſerves, by Sextus Pampinius, in the time of the emperor Auguſtus. The fruit, which is about the ſize of a plumb, is reckoned pectoral, warm and moiſtening; it has an agreeable taſte, though ſomewhat inſipid, and was formerly uſed in ptiſans and pectoral apozems; but is now ſeldom to be found in the ſhops. In Italy and Spain, jujubes are ſerved up in deſſerts as a dry ſweet-meat, during the winter ſeaſon.

A decoction of the roots and branches of the common jujube is ſaid to be ſucceſsful in venereal complaints.

The branches and leaves of the elm-leaved ſumach, or *Rhus Coriaria* of Linnæus, are uſed inſtead of oak-bark for the tanning of leather; the Turkey leather is ſaid to be all tanned with this ſhrub. The leaves, berries, and ſeeds of this ſpecies of ſumach, are uſed in medicine; they are aſtringent, refreſhing and antiſeptick; the berries are uſed in decoction for ſtopping fluxes and violent hæmorrhages.

Virginian

Virginian ſumach is covered with a fine ſoft velvet down; the young branches reſemble, both in colour and texture, a ſtag's horn; by which appellation it is generally known among the inhabitants of North America. This ſort is likewiſe uſed for tanning leather: and the roots, ſays Miller, are often preſcribed in medicine, in the countries where the tree naturally grows.

Very good vinegar is made of the infuſion of the fruit of an American ſpecies of ſumach, which, for that reaſon, is generally known by the name of vinegar-tree. Venice, or red ſumach, the *Rhus Cotinus* of Linnæus, is more uſed by the curriers than in phyſic; it is ſaid, however, to be vulnerary and aſtringent; the wood dyes a fine yellow colour.

Moſt ſpecies of ſumach abound with a white milky juice, which is reckoned poiſonous: that of *Rhus Vernix*, or poiſon-aſh, is eſteemed for its quality of ſtaining; and the plant, from that circumſtance, adjudged to be the true varniſh-tree, deſcribed by Kæmpfer in the Amœnitates Exoticæ, by the name of Sitz-dſiu.

This tree, the *Toxicodendron foliis alatis, fructu rhomboide* of Dillenius, the poiſon-tree of Kalm, riſes with few branches to the height of a willow, and grows naturally in Japan and North America. The bark is hoary, rough with warts, and eaſily parts from the wood, which is very brittle, and reſembles that of willow. The pith is copious. The ſhoots are long, thick, and covered at the extremity with leaves placed without order. Theſe are winged with an odd one. The lobes, pinnæ, or leſſer leaves, are ſlender, egg-ſhaped, of a dark green, ſmooth on the upper ſurface, hoary below, and ſtand oppoſite upon very ſhort foot-ſtalks. The juice contained in the leaf being rubbed upon paper, immediately tinges it with an iron colour. The flowers proceed in cluſters from the arm-pits of the leaves. Theſe cluſters are looſely branched, and ſlender, being compoſed of ſmall yellow flowers, of a ſweet and very grateful ſmell, ſomewhat reſembling that of the flowers of the orange-tree. The fruit is bunched, compreſſed into a

rhomboidal

rhomboidal figure, covered with a thin ſhining membrane, and very hard when ripe.

The bark of varniſh-tree being notched with a knife, effuſes a milky ſubſtance, mixed with a chryſtalline humour exuding from other ducts, which blackens by the admiſſion of air. This ſubſtance, which is likewiſe produced from the branches, pedicles and ribs of the leaves, has no perceptible taſte, unleſs a little heat without any acrid ſenſation. The tree, however, it is affirmed, emits poiſonous exhalations ſo exceeding ſtrong, as to produce in boys who play about it violent inflammations in different parts of the body—effects which, in others, have attended the handling of the wood. They collect the varniſh, by wounding the trunks of the trees (generally thoſe of the age of three years) with a few notches, or gentle inciſions; from which the liquor flowing is received into veſſels placed there for that purpoſe: the inciſions being repeatedly continued in freſh places, till the tree is left wholly without juice. It is then cut down to the root, which quickly yielding a new offspring, is, at the end of three years, again ſubjected to a new inciſion for the collection of more varniſh.

Japan produces the nobleſt and moſt precious varniſh, but in ſo ſmall a quantity, that it would not even ſuffice for their own uſe, without the aſſiſtance of a more ignoble ſpecies brought from Siam, and termed Nam-Rak, which ſerves as a foundation to the other. The tree which furniſhes the inferior ſort is the anacardium produced in the province Corſama, and in the kingdom of Cambodia. The trunks being perforated, and a tube inſerted to receive it, the liquor is produced in ſuch abundance as ſuffices for ſtaining the utenſils of China, Tonquin, and Japan. Varniſh of Japan, after being collected from the tree, as above-deſcribed, is filtrated through a double fold of paper almoſt as thin as a ſpider's web, and ſingularly conſtructed for that purpoſe. The intention of this proceſs is to cleanſe the ſubſtance from all thick and heterogeneous particles. When thoroughly cleaned, a little of the oil named Toi, expreſſed from the fruit of the tree kiri, is mixed with it. It is then

put

put into wooden veſſels, and carried through Japan to be ſold. Both ſpecies of varniſh, that of Japan and that of Siam, emit a poiſonous exhalation, which ſwells the lips, and gives the head-ach; for which reaſon the artificers in putting it on, bind their mouth and noſtrils with a napkin.—— See Kæmpfer's Amœnitates Exoticæ, p. 791.

Spurious Varniſh-Tree, the *Arbor vernicifera ſpuria ſylveſtris anguſtifolia* of Kæmpfer, the *Rhus ſuccedanea* of Linnæus, grows naturally in China and Japan, and is diſtinguiſhed from the true varniſh-tree, which it greatly reſembles, chiefly by the narrowneſs of the pinnæ of the leaves, and by the ſize of the fruit, which is as large as a cherry; whilſt in the true varniſh-tree, the pinnæ are broader, and the fruit, which is altogether white, (another circumſtance of diſcrimination) is about the bigneſs only of a pea. The true varniſh-tree, obſerves Kæmpfer, is ſaid to be changed into this wild or ſpurious kind, if planted in a barren ſpot, and its culture neglected. He adds, that he has ſeen ſome plants, the leaves of which fluctuated ſo remarkably betwixt both ſorts, that even the natives were at a loſs whether they ſhould, or ſhould not, be reckoned of the true kind. This tree emits its varniſh ſo very ſparingly, that it is ſcarce worth while to collect it. The fruit of both ſpecies of varniſh tree, the true and the ſpurious, being beat and boiled, together with the berries of the ſanders-tree, and put hot under a preſs, leave a juice which the Japaneſe employ in making candles, as they do likewiſe what is expreſſed from the berries of two ſpecies of laurel, termed by them Taab and Tſuns. Kæmpferi Amœnitat. Exot. 794.

From the handling, or even breathing in the atmoſphere of other poiſonous ſpecies of ſumach, effects equally unpleaſant are produced as thoſe deſcribed above. The exhalations, in particular, of *Rhus radicans* and *Toxicodendrum*, which, by the way, have no great reſemblance to the ſumachs, the leaves not being pinnated, but growing by threes, as in trefoil, (*ternata*,) are ſaid to occaſion ſmall red ſpots on the ſkin, not unlike thoſe eruptions vulgarly known by the name of St. Anthony's Fire. The ſlighteſt touch of the leaves

produces

produces very violent itchings, which are ſometimes followed by an inflammation and ſwelling. If the juice of any ſpecies of poiſon-tree is ſuffered to remain but for a few minutes on the ſkin, it occaſions puſtules, which are ſometimes miſtaken for the itch. The wood when burnt, emits a very noxious fume, which is ſaid to ſuffocate animals that are expoſed to it. When expoſed to the heat of the ſun, the juice becomes ſo reſinous and clammy, that it proves a good bird-lime, and is uſed with great ſucceſs for that purpoſe. A cataplaſm of the newly extracted juice of a ſpecies of poiſon-tree, mentioned by Hughes in his Natural Hiſtory of Barbadoes, applied to the feet, is ſaid to kill the vermin, called by the Weſt-Indians chigers.

The Americans, it is ſaid, pretend to diſtinguiſh the poiſon-aſh, (*Rhus Vernix*) by the touch in the dark, from its extreme coldneſs.

From the *Rhus Copallinum* of Linnæus, the *Rhus Virginianum lentiſci foliis* of Ray, is produced Gum Copal, an excellent balſam, equal in goodneſs to that of Peru. The animals which are wounded by hunters in Louiſiana, Florida, and Virginia, cure themſelves, we are told, by rubbing againſt the tree from which this balſam exudes, attracted thereto, probably, by its pleaſing aromatic ſmell.

The Natives of Louiſiana and Florida toaſt the ſmall leaves of *Prinos glaber*, termed by Cateſby the true Caſſine or Caſſena, as we do coffee, and drink the infuſion of them with much ceremony. This the Indians call the Liquor of Valour. It is an excellent diuretic; but when taken in great quantity, or made too ſtrong, which, from their attachment to this beverage, is frequently the caſe, excites a kind of convulſions, which are not productive, however, of any ſerious inconvenience.

The bark, leaves, flowers and berries of the common elder are uſed in medicine. An infuſion of the inner bark in milk, wine, or water, is a gentle purgative; the leaves, which are of a bitter taſte, are outwardly applied in fomentations for the piles. The flowers infuſed in whey are beneficial in diſorders of the ſkin, and afford a vinegar, which

is leſs hurtful to the ſtomach than common vinegar. From the berries, beſides a rob and extract, are prepared a ſpirit, a wine, and an oil, which promote urine, perſpiration, and ſweat. The whole plant has a diſagreeable and almoſt nauſeous ſmell. The leaves and ſtalks are ſo bitter, that few animals will brouze upon them.

The juice of the dwarf elder, the ſambucus ebulus of botaniſts, is recommended in dropſical caſes. The root is bitter, ſomewhat acrid and nauſeous; the inner bark of the root is ſtrongly purgative; the pith, or internal ſubſtance, is more aſtringent than the reſt of the plant; the berries and ſeeds are a gentle purge. The whole plant exhales a ſtrong and diſagreeable odour; and is, on that account, frequently placed round granaries, to drive away rats and other vermin.

The ever-green caſſine, otherwiſe called Paraguay, or South-ſea tea, Linnæus has confounded with the Carolina or Dahoon holly; though they are undoubtedly diſtinct plants.

This ſpecies of caſſine, which grows naturally in Carolina and Virginia, is called yapon by the natives of thoſe countries. The berries are of a beautiful red colour, and as they continue moſt part of the winter upon the plants without being touched by the birds, we may reaſonably conclude that they are poſſeſſed of a poiſonous quality, as few of the wholeſome innocent fruits eſcape their depredations. The Indians, however, have a great veneration for this plant, and come in great numbers, at certain times of the year, to fetch away the leaves. On ſuch occaſions, their uſual cuſtom, ſays Miller, is to make a fire upon the ground, and putting on it a great kettle full of water, they throw in a large quantity of yapon leaves; and, when the water has boiled ſufficiently, they drink large draughts of the decoction out of the kettle, which ſeldom fails to act as a powerful emetic. In this manner, notwithſtanding, they continue drinking and vomiting for the ſpace of three days, until they have ſufficiently cleanſed themſelves; they then gather every one a bundle of the ſhrub, and carry it home with them.

In the operation of theſe leaves by vomiting, ſay thoſe who

who have taſted of them, there is no uneaſy ſenſation or pain. The matter diſcharged comes away in a full ſtream from the mouth without any violence, or ſo much as diſpoſing the patient, if he may be called ſo, to retch, or decline his head. The Spaniards who live near the gold mines in Peru, are frequently obliged to drink an infuſion of the herb paraguay, which is generally ſuppoſed to be the evergreen caſſine, in order to moiſten their breaſt. Without this relief, they are liable to a ſort of ſuffocation, from the ſtrong metallic exhalations which are continually proceeding from the mines.

In Paraguay, the Jeſuits make a great revenue of the leaves of a plant, which moſt authors believe to be the evergreen caſſine, called yapon by the North Americans. Theſe leaves are imported into many countries by the name of Paraguay or South-ſea tea, and are drunk in infuſion, as the leaves of the China and Japan tea; and hence the evergreen caſſine is generally known with us, by the name of the South-ſea or Paraguay tea.

DUPLICATI. The name of a claſs in Linnæus's *Methodus Calycina*, conſiſting of plants which have a double *perianthium*. The claſs is exemplified in mallow, and moſt of the plants of that tribe or family; as lavatera, baſtard mallow, cotton, Syrian mallow, hollyhock, marſh-mallow, and Indian mallow (Urena). Theſe plants make part of the claſs *Monadelphia* in the Sexual Method, and of the Natural Order, *Columniferæ*, which ſee.

DUPLICATUS *flos*, (from *duplex*, double) having the corolla doubled, or, in other words, two ſeries or rows of petals. The term is expreſſive of the leaſt degree of plenitude or luxuriance of which the petals are ſuſceptible, and is exemplified in campanula with a nettle leaf, and thorn apple with a violet flower.

This ſimpleſt ſtage of luxuriance is very common in flowers with one petal.

DURATIO, Duration.

The diviſion of vegetables into trees, and perennial and annual herbs, is founded on the different duration of theſe plants.

plants. Trees ſubſiſt for ſeveral years, both by the root and ſtem: perennial herbs loſe their ſtems during the winter, and are renewed by the root in the following ſpring? annuals perform the changes of vegetation but once, and are perpetuated in the ſeed. Striking as theſe differences are, Linnæus thinks the duration of plants ſo fallacious, that he never employs it as a ſpecific difference. The reaſon he aſſigns is very pertinent. The duration of plants, ſays he, is frequently affected by place or climate, and therefore ought not to be regarded as an invariable circumſtance proper for diſcriminating the ſpecies. In the warmer climates, which enjoy a perpetual ſummer, moſt of the plants are perennial, and of the tree kind; yet many of them, when removed to our colder European climates, loſe their woody texture, and become herbaceous and frequently annual. Of this the ricinus, or tree palma chriſti, and marvel of Peru, are familiar inſtances.

Indian creſs, beet, ſweet marjoram, and tree-mallow, which, with us, are annual, become, in very warm regions, perennial and ſhrubby.

E.

EFFLORESCENTIA (from *efflorescо*, to bloom); a term expreſſive of the preciſe time of the year and month in which every plant ſhews its firſt flowers.

Some plants flower twice a year, as is common between the tropics; others oftener, as the monthly roſe. The former are called by botaniſts, *biferæ*; the latter, *multiferæ*. The etymology of each is evident.

The time of flowering is determined by the degree of heat which each ſpecies requires; mezereon and ſnow-drop produce their flowers in February; primroſe in the beginning of March; the greater number of plants during the month of May; corn, and other grain, in the beginning of June; the vine, in the middle of the ſame month; ſeveral compound flowers, in the months of July and Auguſt; laſtly,

meadow-ſaffron flowers in the month of October, and announces the ſpeedy approach of winter.

Graſs of Parnaſſus always flowers about the time of cutting down the hay; and in Sweden, the different ſpecies of thiſtle, mountain-lettuce, ſuccory, and balſam, ſeldom flower till after the ſummer ſolſtice. The country-men even know, as by a calendar, that the ſolſtice is paſt, when theſe plants begin to produce their flowers.

The temperature of the ſeaſons has a mighty influence, both in accelerating and retarding the flowering of plants. All plants are earlier in warm countries: hence ſuch as are cultivated out of their native ſoil never flower, till the heat of the climate or ſituation into which they are removed, is equal to that under the influence of which they produced flowers in their own country. For this reaſon, all exotics from warm climates are later in this country than many plants which it naturally produces.

In general, we may obſerve, that the plants of the coldeſt countries, and thoſe produced on the mountains in all climates, being of equal temperature, flower about the ſame time: to wit, during our ſpring in Europe.

Plants that grow betwixt the tropics, and thoſe of temperate climates, flower during our ſummer.

Plants of temperate climates ſituated under the ſame parallel of latitude with certain parts of Europe, but removed much farther to the Weſt, ſuch as Canada, Virginia, and the Miſſiſſippi, do not produce flowers till autumn.

Plants of temperate climates in the oppoſite hemiſphere to Europe, flower during our winter, which is the ſummer of thoſe regions.

Linnæus, and after him Adanſon, have each given a ſketch of a table of the different times in which the moſt common plants produce flowers at Upſal and Paris. Such tables, or flower-calendars, however, are very uncertain, and, to be uſeful, ought to be conſtructed after the moſt exact obſervations. The temperature of the ſeaſon, as we mentioned above, ſometimes retards, ſometimes accelerates the flowering of plants; not to mention that annual plants

flower late or early, according to the time in which the ſeeds have been ſown; and that perennials, for the firſt year, are liable to the ſame variations.

ENNEANDRIA, (from ἐννέα, nine, and ἀνὴρ, a man or huſband); the name of the ninth claſs in Linnæus's Sexual Syſtem, conſiſting of plants which have hermaphrodite flowers with nine ſtamina or male organs.

The orders, or ſecondary diviſions, in this claſs are three, being founded on the number of the ſtyles, ſeed-buds, or female organs. Laurus, tinus, and caſſytha, have one ſtyle; rhubarb (*Rheum*,) has a triple ſtigma or ſummit, but ſcarce any ſtyle; flowering-ruſh has ſix ſtyles.

The genera juſt enumerated are all that belong to the claſs *Enneandria*. The firſt genus, *laurus*, is very extenſive; comprehending the bay-tree, cinnamon-tree, camphire-tree, benjamin-tree, ſaſſafras-tree, and the avocado or avogato pear.

ENSATÆ (from *enſis*, a ſword); the name of the ſixth order in Linnæus's Fragments of a Natural Method, conſiſting of plants with ſword-ſhaped leaves.

Liſt of the Genera *contained in this Natural Order.*

Linnæan Genera.	*Engliſh Names.*
Antholyza.	
Calliſia.	
Commelina.	
Crocus, —	— Saffron.
Eriocaulon.	
Ferraria.	
Gladiolus, —	— Corn-flag.
Iris, —	— Iris, or Flower-de-luce.
Ixia.	
Moræa.	
Pontederia.	
Siſyrinchium.	

Linnæan Genera.		*Engliſh Names.*
Tradeſcantia,	—	— Virginian Spider-wort, or Flower of a Day.
Wachendorfia.		
Xyris.		

Habit and Structure of the Plants of this Order.

This order, which is very nearly allied to the graſſes and liliaceous plants, furniſhes a very beautiful collection of perennial herbs, which are of different heights, from one inch to fifteen feet. A ſpecies of commelina is annual.

The ROOTS, are tuberous, or fleſhy, and garniſhed with fibres; thoſe of crocus, and two ſpecies of iris, called by Linnæus *Iris Xiphium* and *Siſyrinchium* from genera of Tournefort of the ſame name, are bulbous. The roots of the laſt ſpecies conſiſt of two bulbs.

The STEMS or ſtalks are ſimple, and commonly flat, or compreſſed on the ſides. Crocus has no ſtem above ground; the flowers being produced immediately from the root.

The LEAVES are ſimple, alternate, entire, ſword-ſhaped, and, like the liliaceous plants, form at their origin a ſheath or glove, which, in the greateſt number, is cleft through the whole length, except at the baſe, where it is entire, and embraces the ſtem like a ring.

In Virginian ſpider-wort, wachendorfia, pontederia, and ſiſyrinchium, the ſheath of the leaves is totally cleft. The leaves of tuberous iris and crocus are not ſword-ſhaped, but formed like a priſm with four prominent angles. Thoſe of bulbous iris, Virginian ſpider-wort, and iris with a double bulb, are ſemi-cylindrical. The leaves of commelina are of an oval form.

The FLOWERS are hermaphrodite, and generally proceed from the ſummit of the ſtalks, either ſingly, as in iris; in an umbel, as crocus, Virginian ſpider-wort, and commelina; in a ſpike, as *Siſyrinchium*; in a *Corymbus*, as in *Ixia*; or in a panicle, that is, looſe ſpike, as in wachendorfia. In *Pontederia*, they proceed from the angles of the leaves, either

ther ſingly, or in an umbel. *Vide* UMBELLA, SPICA, CORYMBUS and PANICULA.

Moſt of theſe plants want the *Perianthium*. The flowers burſt from a common cover or ſheath termed by Linnæus, SPATHA, which, in this order, is frequently permanent. Virginian ſpider-wort and calliſia, have a flower-cup of three leaves. *Eriocaulon* has a common calyx conſiſting of ſcales laid over one another like tiles. The calyx in *Xyris* is huſky, like that of the graſſes.

The PETALS are in number from one to ſix; in eriocaulon, the calyx and petals are placed under the ſeed-bud. The ſeveral ſpecies of commelina differ exceedingly in the number of their petals: ſome have two green, and four coloured petals; ſome four green, and but two coloured. In many ſpecies of iris, the baſe of the outer petals, that are rolled back, is adorned with a fine ſoft downy beard, which, in ſome other ſpecies, is ſupplied by three melliferous points ſituated externally at the baſe of the flower.

Commelina has three croſs-ſhaped bodies in the middle of the flower reſembling the ſtamina, but placed above them.

In *Wachendorfia*, the *nectarium* conſiſts of two hairs or briſtly appearances, which are placed on the inſide of the upper or higher petal.

The STAMINA are generally three in number. Virginian ſpider-wort, and *pontederia*, have ſix ſtamina. The filaments in eriocaulon, ſiſyrinchium, and ferraria, are placed upon the ſtyle and ſeed-bud; in Virginian ſpider-wort, they are covered with a fine beautiful down.

The SEED-BUD is ſometimes placed above the flower, as in eriocaulon, wachendorfia, calliſia, and commelina; ſometimes below it, as in iris, corn flag, ixia, and crocus.

The STYLE is generally ſingle, and crowned with a triple ſtigma. Eriocaulon has three ſlender ſtyles.

The STIGMA in iris is very ſingular, being large and expanded into three leafy parts, that in colour and figure reſemble the petals, within which they are placed. This triple ſtigma is broad, rolled backwards, and parted in two at the top of each leaf or diviſion.

In crocus, the ſtigma is ſawed on the edges, and twiſted into a ſpiral form.

The SEED-VESSEL is a dry capſule, generally of an oblong ſhape, and opens at three valves diſcovering the ſame number of cells, each incloſing a quantity of roundiſh ſeeds.

Theſe plants reſemble the liliaceous in their powers and ſenſible qualities; very few of them, however, are uſed in medicine.

The root of the white florentine iris, commonly called florentine orrice, is deſcribed by Lemery as pectoral. Outwardly it is uſed as ſweet powder for the hair. The dyers, perfumers, and confectioners, employ this root in their ſeveral profeſſions, to give a grateful ſcent to their cloaths, perfumes, comfits, and the like.

Of the common iris is made a green colour or pigment much uſed by the painters in miniature.

The roots of moſt of the ſpecies of ixia are eaten by the inhabitants at the Cape of Good Hope, who reckon them very delicate food.

The flower of the Virginian ſpider-wort is of very ſhort duration: hence the plant was named by Tournefort, *Ephemerum*, or the flower of a day.

Saffron is the chives or ſtamina of the *crocus ſativus*. In Hungary and Poland they eat it as a cordial, ſometimes an ounce or more at a time; but taken in great quantities with us, whether medicinally or for pleaſure, it produces convulſions, delirium, and even death.

EPIDERMIS. The ſcarf-ſkin, or outer covering of the bark of plants.

EPIPHYLLOSPERMÆ, (from ἐπι, upon, φυλλον, a leaf, and σπερμα, a ſeed.) The name of a claſs in Haller's Natural Method, conſiſting of plants which bear their ſeeds on the back of the leaf. This claſs comprehends all the ferns. *Vide* FILICES.

ERECTUS *flos*, an erect flower, in oppoſition to a nodding, or drooping one.

ERISTICI, (from ἐρις, ſtrife) polemical or controverſial

ſial botaniſts ſo termed by Linnæus; ſuch were Tournefort, Colet, and Chomel; Ray and Rivinus; Dillenius and Rivinus; Linnæus and Sigeſbeck.

ESSENTIALIS *character*. *Vide* CHARACTERES.

EUNUCHI, eunuchs. Full flowers ſo called, which, by multiplying the petals, exclude the ſtamina or male organs of generation altogether, and thus render the ſeed barren. *Vide* LUXURIANS and PLENUS *flos*.

F.

FACIES *Externa*, the port or habit of plants. *Vide* HABITUS and CHARACTERES.

FACTITIUS *Character*. *Vide* CHARACTERES.

FASCIATA *planta* (from *faſcis*, a bundle) plants ſo called, which conſiſt of ſeveral ſtems or ſtalks growing cloſe together ſo as to form a compact bundle.

FASCICULUS (a diminutive from *faſcis*, a bundle) a little bundle; a mode of flowering, in which the flower-ſtalks are erect, parallel, placed cloſe to one another, and raiſed to the ſame height; as in ſweet-william.

FAUX, the jaws or chaps. The gaping at the top of the tube of a monopetalous flower. *Vide* COROLLA.

FEMINEUS *flos*, a female flower. By this name Linnæus and the Sexualiſts denominate a flower which is furniſhed with the piſtillum or female organ of generation, but wants the ſtamina or male organ.

Female flowers may be produced apart from the male, either on the ſame root, or on diſtinct plants. Birch and mulberry are examples of the firſt caſe; willow and poplar of the ſecond. Male and female flowers ſeparated on the ſame plant, conſtitute the claſs *Monœcia* of Linnæus; ſeparated on diſtinct roots, the claſs *Diœcia*. *Vide* MONŒCIA & DIŒCIA.

FEMINA *planta*, a female plant, a plant which bears female flowers only; oppoſed to a male plant, which produces only

male flowers, and to an adrogynous one, which bears flowers that are of both ſexes. *Vide ſupra.*

Female plants are produced from the ſame ſeed with the male, and arrange themſelves under the claſs Diœcia in the Sexual Method.

FIGURA, Figure; a property of natural bodies, from which marks and diſtinctive characters are frequently drawn. *Vide* CHARACTERES. Figure is more conſtant than number, more variable than proportion and ſituation.

The figure of the flower in the ſame ſpecies is more conſtant than that of the fruit: hence Linnæus adviſes to arrange under the ſame genus, ſuch plants as agree invariably in the flower, that is, in the calyx, petals and ſtamina, although the fruit or ſeed-veſſel ſhould be very different. The ſeed-veſſels of the different ſpecies of French honey-ſuckle, wild ſenna, acacia, Syrian mallow, and ſophora, are exceedingly diverſified in point of figure. Hence ſome former botaniſts, who paid more attention to the parts of the fruit, conſidered many of theſe ſpecies as diſtinct genera, and denominated them accordingly.

The figure of the ſeed-veſſel is a very common ſpecific difference in the Sexual Method.

FILAMENTUM, (from *filum*, a thread) the lower, ſlender, or thread-ſhaped part of the ſtamina, that ſerves as a foot-ſtalk for elevating the *anthers*, and connecting them with the vegetable. The term is equivalent to the *ſtamen* of Tournefort and other botaniſts. With Linnæus, *ſtamen* is a general term, the two parts of which are, the filament or thread, and the *anthera* or ſummit. *Vide* STAMEN & ANTHERA.

From the number of the filaments the firſt thirteen claſſes in the Sexual Method ariſe; it is, therefore, unneceſſary to enlarge upon that circumſtance in this place.

With reſpect to figure, filaments are either ſlender like a hair, as in plantain; flat, as in ſtar of Bethlehem; wedge-ſhaped, as in meadow-rue; twiſted like a ſcrew, as in hirtella; awl-ſhaped, as in tulip: notched, as in many of the

lip-

lip-flowers; or bent backwards, as in ſuperb lily. The filaments in ſpider-wort and flower-of-a-day are beautifully covered with a fine hairy down.

With reſpect to proportion, the filaments are either very long, as in plantain; very ſhort, as in arrow-headed graſs; of equal lengths, as in moſt flowers; or irregular and unequal, as in the lip and croſs-ſhaped flowers, which, from this circumſtance, conſtitute the claſſes *Didynamia* and *Tetradynamia* in Linnæus's Method.

The ſituation of the filaments is generally oppoſite to the diviſions of the calyx, and alternate with the petals. In elæagnus, and other flowers which want one of the covers, the filaments are placed alternate with the diviſions of the remaining cover: whence I ſhould be inclined to imagine that ſuch flowers want the calyx, not the petals, as Linnæus aſſerts. In general it may be affirmed, that when the diviſions of the calyx are equal in number to the petals and ſtamina, the petals are alternate with the ſtamina and flower-cup: the ſtamina are placed oppoſite to the diviſions of the calyx, and to the valves or incloſures of the fruit, when theſe correſpond in number, as ſometimes happens in the natural order Caryophyllei; and all the parts in queſtion are attached to the receptacle of the flowers. Again, if the ſtamina, in plants which have neither calyx nor petals, are equal in number, and oppoſite to the valves or incloſures of the fruit, we may reaſonably conclude that they are placed upon the receptacle, as in the laſt caſe. But if, on the other hand, they are alternate with the valves, the inference is, that they are attached, like the plants of the claſs *Icoſandria*, to the calyx.

In flowers that conſiſt of one petal, the ſtamina are generally inſerted into its baſe. For this obſervation, we are indebted to the minute and accurate reſearches of Vaillant and Pontedera, particularly the laſt, who is ſaid to have diſſected the flowers of two thouſand ſpecies of plants, with a view to eſtabliſh a general rule with reſpect to the inſertion of the filaments of the ſtamina. By attending to the rule juſt mentioned, we can determine with exactneſs, in doubtful

ful caſes, whether the flower conſiſts of one or more petals. It is in this manner we pronounce with certainty the flowers of wood-ſorrel, and winter-green (trientalis) to conſiſt of only one petal, although the diviſions cohere ſo ſlightly at the baſe as to be eaſily miſtaken for diſtinct leaves.

There are, however, ſome examples of flowers with one petal that have the ſtamina attached to the receptacle; ſuch are heath, American upright honey-ſuckle, and ſome other plants which belong to the natural order *Bicornes*. The ſame may be ſaid of the ſtamina of ciſſus, aloe and acacia.

In flowers that conſiſt of more petals than one, the ſtamina are generally diſtinct from the petals; being attached either to the calyx, as in the claſs *Icoſandria* of Linnæus, and the natural orders *Calycanthemæ* and *Calyciſloræ*; or to the receptacle, as in the greater number. This rule, however, as well as the foregoing, admits of exceptions. In ſea-pink, the filaments of the ſtamina are inſerted into the claws of the petals, which are five in number. The ſame appearance is obſerved in ſtar-wort, which conſiſts of ſix diſtinct petals; and in moſt of the plants of the natural order *Caryophyllei*, the ſtamina are attached alternately to the claws of the petals and the receptacle.

A ſtriking exception to the general rule has not yet been mentioned. In ſome plants, as birth-wort and orchis, the ſtamina are inſerted, neither into the calyx, petals, nor receptacle, but into the pointal, or female organ of generation. Upon this ſingular circumſtance is founded the claſs *Gynandria* in the Sexual Method, which, however, contains many more genera than in ſtrict propriety pertain to it; as paſſion-flower, grevia, and ſcrew-tree, which have no characteriſtic mark of this kind.

In aſſimilating the animal and vegetable kingdoms, Linnæus diſtinguiſhes the filaments by the name of the ſpermatic veſſels.

FILICES, (from *filum*, a thread,) ferns, one of the ſeven families or natural tribes into which the whole vegetable kingdom is divided by Linnæus in his *Philoſophia Botanica*. They are defined to be plants which bear their flower and fruit

on the back of the leaf or ſtalk, which, in this claſs of imperfect plants, are the ſame. *Vide* FRONS.

In the Sexual Syſtem, the ferns conſtitute the firſt order or ſecondary diviſion of the twenty-fourth claſs, *Cryptogamia:* in Tournefort's Method they are the ſixteenth claſs; and in Ray's the fourth under the name of *Capillares.* Haller denominates them *Epiphylloſpermæ*, that is, plants that bear their ſeed on the back of the leaf; others term them *Acaules*, becauſe they have properly no ſtem.

FILICES is likewiſe the name of the fifty-fifth order in Linnæus's Fragments of a Natural Method, conſiſting of plants, which, among others, have the general character juſt mentioned.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Ferns, in which the Parts of Fructification grow upon the Leaves.

Linnæan Genera.			*Engliſh Names.*
Acroſtichum.			
Adianthum,	—	—	Maiden-hair.
Aſplenium,	—	—	Spleen-wort, or milt-waſte.
Blechnum.			
Hemionitis,	—	—	Mules-fern.
Iſoetes.			
Lonchitis,	—	—	Rough ſpleen-wort.
Polypodium,	—	—	Polypody.
Pteris,	—	—	Brakes, or female fern.
Trichomanes.			

SECTION II.

Ferns, in which the Flowers are borne upon Foot-ſtalks that over-top the Leaves.

Marſilea.
Onoclea.

Ophioglo ſſum,

Linnæan Genera.			*Engliſh Names.*
Ophioglossum,	—	—	Adder's-tongue.
Osmunda,	—	—	Osmund-royal, or flowering-fern.
Pilularia,	—	—	Pepper-grass.

Habit and Structure of the Plants of this Natural Order.

These plants, in figure, approach the more perfect vegetables, being furnished, like them, with roots and leaves.

The ROOTS creep, and extend themselves horizontally under the earth, throwing out a number of very slender fibres on all sides.

The STEM in these plants is not to be distinguished from the common foot-stalk, or rather middle rib, of the leaves: so that, in strict propriety, the greater number of ferns may be said to be *acaules*, that is, to want the stem altogether: in plants of the second section, however, the middle rib, or a stalk proceeding from the root, overtops the leaves, and forms a stem, upon which the flowers are supported.

The LEAVES proceed either singly, or in greater numbers, from the extremities of the branches of the main root. They are winged, or hand-shaped, in all the genera, except in adder's-tongue, pepper-grass, and some species of spleen-wort.

The FLOWERS of the ferns, whatever be their nature, are, in the greater number of genera, fastened, and, as it were, glued to the back of the leaves; in some, they are supported upon a stem or stalk, which rises above the leaves, and is either, as we said above, a prolongation of their middle rib, or issues out of the centre of the plant, unconnected with the leaves altogether. From these different modes of flowering, arise the two sections, or divisions of this Natural Order.

The STAMINA are placed apart from the seed-bud, or female organ, in a genus termed by Adanson, *palma-filix:* in the other ferns, where we have been able to discover the stamina, they are found within the same covers with the

seed-

ſeed-bud. This principal part of the flower, however, has not been accurately or ſatisfactorily traced, except in a very few genera, the chief of which are *iſoetes*, pepper-graſs, and *marſilea*. M. de Juſſieu, who firſt diſcovered the flowers of the two laſt genera, obſerves, in his Memoir on this ſubject, delivered to the Royal Academy of Sciences, in 1739, that their ſtamina are *anthers*, or tops without filaments; that they are top-ſhaped, and open above by a tranſverſe or broad furrow. They have only a ſingle cavity, from which iſſues a fine duſt, compoſed of ſimple, hard globules, which do not open when put into water, as thoſe of perfect plants.

M. Maratti, in 1760, employed his enquiries upon the ſtamina of theſe imperfect plants, and is ſaid to have traced them in a great many genera. His diſcoveries, however, on this ſubject, have not been generally received as authentic.

With reſpect to what are vulgarly called the ſeeds of ferns, we have not yet been able to determine, with any degree of preciſion, whether they are indeed ſeeds, or of the nature of ſtamina. M. de Juſſieu inclines to the latter opinion.

The Canadian fern bears at the origin of each diviſion of the leaves a number of berries, which being ſown, produce new plants in the ſame manner as other ſeeds. In the Pyrenæan Mountains is produced a ſmall ſpecies of annual fern, which ſows itſelf every year, and is termed by Tournefort, *filicula montana folio vario*. M. de Juſſieu is of opinion, that a ſtrict attention to this plant might alone accurately decide the queſtion, which has been ſo long agitated among botaniſts; not whether the ferns are furniſhed with ſeeds, (for that few people are now diſpoſed to call in queſtion); but of what nature theſe ſeeds are, and where placed; whether the ſtamina are ſeparate from the female parts, on the ſame, or on different roots; or, whether theſe parts are mingled together under the ſame cover, or in the ſame heap or bundle of flowers, as ſome obſervations of Dillenius would lead us to imagine.

In ſhort, all our reſearches upon this ſubject are mere conjecture; and men knew much more of theſe imperfect plants,

plants, who never ſuſpected they were furniſhed with ſtamina or ſeeds, than the moderns, who confining their enquiries to thoſe minute parts which generally elude the ſight, have entirely neglected their port or habit; although that only can furniſh accurate diſtinctive characters in this natural tribe or family of plants.

Moſt of the ferns have a heavy, diſagreeable ſmell; they are opening, and attenuating.

The true maiden-hair, or Capillaire of Montpelier, a well-known medicine, is the *adiantum foliis coriandri* of Caſpar Bauhin, the *capillus veneris verus* of Gerard, the *adiantum capillus veneris* of Linnæus. It is a plant which grows in France, Italy, and the Levant, upon old moiſt walls, in wells, fountains, and the clefts of rocks. The leaves, which are almoſt triangular, have a fragrant ſmell, and an agreeable taſte, though ſlightly aſtringent and bitter. They are much uſed in the countries which produce the plant in ſyrups, and in opening and diuretic decoctions.

Black maiden-hair, or oak fern, the *adiantum pulcherrimum* of Bauhin, the *Aſplenium adiantum nigrum* of Linnæus, is produced naturally in moſt parts of England upon old walls, and in ſhady places, at the roots of trees and ſhrubs. The pedicles are black, and the pollen or duſt upon the back of the leaves is of the colour of ſaffron.

As there has been no ſmall confuſion in diſtinguiſhing the ſeveral ſpecies of maiden-hair uſed in medicine; and as ſome, ignorant in botany, have erroneouſly ſubſtituted in their place, the leaves of Polypody and Hart's tongue, which they do not, however, much reſemble, and even the root of the former; I thought it would not be improper in this place to obſerve, that the genuine ſpecies of Capillaire are reduced to ſix: that of Montpelier, or *adiantum Capillus Veneris*; the black which has juſt been deſcribed; the *Trichomanes*, or Engliſh black, generally uſed with us for the firſt ſort; the true white, or *ruta muraria*; Ceterach of the ſhops, and *adiantum pedatum*, which grows naturally in Canada and Virginia. All the ſorts, except the firſt and laſt, rank under the genus *Aſplenium*.

The

The Canada maiden-hair approaches neareſt in quality to that of Montpelier. The traders, we are told, pack up their goods with it inſtead of hay, when they are ſent into diſtant countries, as France and England; a circumſtance which renders this fern ſo very common in Europe.

Ceterach, or common ſpleen-wort, juſt mentioned, which, like other ſpecies of the ſame genus, grows naturally on old walls, churches, and clefts of moiſt rocks, is termed by the natives of Languedoc, where it is produced in great abundance, golden locks, becauſe of its great reſemblance to hair, and its golden colour. It is pectoral, aperient, and particularly adapted for diſeaſes of the ſpleen.

The plants of the polypody kind ſtrike their roots into whatever they can lay hold of, whether ſtone, earth or tree. They were formerly believed to be particularly attached to oak-trees; but this is a miſtake, as they are found much more frequently on other trees. Polypody is preſcribed in medicine, and eſteemed a gentle purgative.

Ophioglo'ſſum has only one leaf, from the middle of which proceed one or two ſpikes of flowers reſembling a ſerpent's tongue; from which fancied ſimilitude this genus of plants has derived its name in both languages. The plant is vulnerary, particularly the leaves, when infuſed in oil of olives.

The root of the female fern, a ſpecies of pteris, has a bitter aſtringent taſte, and enters into the compoſition of fern-ſtone, a very powerful aſtringent. In England, the aſhes of fern kneaded in water, have been ſucceſsfully uſed in bleaching linen, and ſupplying the place of ſoap. The trivial name *aquilina*, which Linnæus gives to this ſpecies of *filix*, is derived from the figure of a tranſverſe ſection of the root, which is ſaid to reſemble the Roman eagle.

Royal oſmund, a ſpecies of flowering fern, is leſs bitter and aſtringent than the other ferns; the pith of the root is white, vulnerary, and uſed in decoction, as are likewiſe the bunches or cluſters of flowers.

FLORESCENTIA (from *floreſco*, to flouriſh or bloom). The act of flowering, which Linnæus and the Sexualiſts

compare

compare to the act of generation in animals; as the ripening of the fruit, in their judgment, reſembles the birth. *Vide* FLOS.

FLORIBUNDI (from *florere*, to bloom.) The name of the ſeventh claſs in Linnæus's Method founded on the calyx, conſiſting of plants that have a ſimple perianthium, into which are inſerted the petals and ſtamina. This claſs comprehends the *icoſandria* of the Sexual Method, and the two natural orders, *Calycanthemæ* and *Calyciſloræ*, which ſee.

FLORISTÆ, from *Flora*. By this name Linnæus terms a claſs of botanical writers, who enumerate the indigenous or native vegetables of any particular place or country. The moſt eminent of theſe enumerations, or, as they are commonly called, Floras, are Ray's and Hudſon's *flora anglica*; Linnæus's *flora ſuecica* and *lapponica*; Haller's, *helvetica*; Magnolius's, *monſpeliaca*; Gmelin's, *ſibirica*; Vaillant's, *pariſina*; Ruppius's, *jenenſis*; and Hill's *flora britannica*.

Theſe floras are arranged according to ſome approved ſyſtem, as Hudſon's after that of Linnæus, and contain the generic and ſpecific differences of whatever method they adopt. They are uſeful in conducting to the knowledge of the curious plants in one's country; as they inſtruct both in the place of growth, the nature of the ſoil, the time of flowering, and the duration of any particular plant in queſtion.

FLOS. The flower: by this term, former botaniſts, as Columna, Jungius, Ray, and Tournefort, evidently meant the petals, or beautiful coloured leaves of the plant, which generally adhere to the ſeed-bud, or rudiment of the fruit. *Vide* ANTHUS.

Since the introduction of the Sexual Method, the petals have loſt their importance, and are now only conſidered as a finer ſort of cover, which is generally preſent, but not eſſentially neceſſary to the exiſtence of a flower.

A flower then, in modern botany, is as different in meaning from the ſame term in former writers, as from the vulgar acceptations of the word at this day. The petals, the calyx,

nay,

nay, the threads or filaments of the ſtamina may all be wanting; yet it is a flower ſtill, provided the anthers or male organ, and the ſtigma or ſummit of the ſtyle, the female organ, can be traced, and that either immediately in the neighbourhood of one another, as in moſt plants; on different parts of the ſame plant, as in the claſs *Monœcia*; or on different plants, raiſed from the ſame ſeed, as in the claſs *Diœcia*. In this manner is to be underſtood the general principle with which the Sexual Method ſets out, that every vegetable is furniſhed with flower and fruit. The eſſence of the flower, as the author immediately ſubjoins, conſiſts in the *anthers* and *ſtigma*, which conſtitute a flower, whether the covers, that is, the calyx and petals, are preſent or not. *Vide* Principles of the Sexual Method, under the article ANTHERA.

The general principle juſt mentioned is extended by Linnæus to thoſe plants vulgarly called imperfect; I mean the ferns, moſſes, muſhrooms, lichens and ſea weed; in moſt of which we have not been able to diſcover any thing reſembling flower or fruit. As, however, in a few genera, ſomething like ſtamina and ſeeds, have been diſcovered; it is probable that they are all furniſhed with ſimilar parts, although their minuteneſs, or their ſituation within the plant, may prevent us from diſcovering them, either by the naked eye, or with the aſſiſtance of glaſſes.

The flowers of pepper-graſs and marſilea, two of the fern tribe, were diſcovered by B. Juſſieu, in 1739; thoſe of iſoetes by Linnæus; the ſtamina of the fuci, a numerous tribe of ſea-weed, were diſcovered by Reaumur, in 1711; whoſe obſervations on this curious ſubject were confirmed by Griſelini, in 1750. Micheli, in 1729, diſcovered, as he imagined, the ſtamina of the muſhrooms. The calyx, petals, ſtamina and pointal are properly parts of the flower; the remaining parts of the fructification pertaining only to the fruit.

FLOSCULOSI. The name of the twelfth claſs in Tournefort's Method, conſiſting of compound flowers which are compoſed entirely of florets with hollow funnel-ſhaped

petals. The term is exemplified in burdock, thiſtle, artichoke, blue-bottle, and cudweed. To this claſs Tournefort has added ſcabious, teaſel, and ſome others, which reſemble the compound flowers in being contained within a common calyx.

Moſt of the plants in this claſs belong to the two firſt orders in the claſs *Syngeneſia* of the Sexual Method. *Vide* SYNGENESIA.

FLOSCULUS. A partial or leſſer floret of an aggregate flower. *Vide* AGGREGATUS *flos.*

FOLIATIO, (from *folium*, a leaf.) The curious manner in which the leaves are wrapped or folded up in the buds. This term in the latter editions of Linnæus's works is changed for VERNATIO, which ſee.

FOLIOLA. The leſſer leaves or lobes, which, together, conſtitute a compound leaf. *Vide infra.*

FOLIUM. A leaf, defined to be a part of a plant extended into length and breadth in ſuch a manner, as to have one ſide diſtinguiſhable from the other. This is Miller's definition; and is certainly more intelligible than that of Linnæus, which denominates leaves the organs of motion, or muſcles of the plant.

The leaves are not merely ornamental to plants; they ſerve very uſeful purpoſes, and make part of the organs of vegetation.

The greater number of plants, particularly trees, are furniſhed with leaves: in muſhrooms, and ſhrubby horſe-tail, they are totally wanting. Ludwig defines leaves to be fibrous and cellular proceſſes of the plant, which are of various figures, but generally extended into a plain, membranaceous or ſkinny ſubſtance. They are of a deeper green than the foot-ſtalks on which they ſtand, and are formed by the expanſion of the veſſels of the ſtalk, among which, in ſeveral leaves, the proper veſſels are diſtinguiſhed by the particular taſte, colour, and ſmell of the liquors contained within them.

By the expanſion of the veſſels of the ſtalk are produced ſeveral ramifications, which croſſing each other mutually, form

form a kind of net, the meſhes or interſtices of which are filled up with a tender cellular ſubſtance, called the pulp, pith, or parenchyma. This pulpy ſubſtance is frequently conſumed by certain ſmall inſects, whilſt the membranous net remaining untouched exhibits the genuine ſkeleton of the leaf.

The net in queſtion is covered externally with an epidermis or ſcarf-ſkin, which appears to be a continuation of the ſcarf-ſkin of the ſtalk, and, perhaps, of that of the ſtem. M. Deſauſſure, a judicious naturaliſt, has attempted to prove that this ſcarf-ſkin, like that of the petals, is a true bark, compoſed itſelf of an epidermis and cortical net; theſe parts ſeem to be the organs of perſpiration, which ſerve to diſſipate the ſuperfluous juices.

The cortical net is furniſhed, principally on the lower ſurface of the leaf, with a great number of ſuckers or abſorbent veſſels, deſtined to imbibe the humidity of the air. The upper ſurface, turned towards heaven, ſerves as a defence to the lower, which looks downward; and this diſpoſition is ſo eſſential to the vegetable œconomy, that, if a branch is overturned in ſuch a manner as to deſtroy the natural direction of the leaves, they will, of themſelves, in a very ſhort time, reſume their former poſition; and that as often as the branch is thus overturned.

Leaves then are uſeful and neceſſary organs; trees periſh, when totally diveſted of them. In general, plants ſtript of any of their leaves, cannot ſhoot vigorouſly; witneſs thoſe which have undergone the depredations of inſects; witneſs, likewiſe, the very common practice of ſtripping off ſome of the leaves from plants, when we would ſuſpend their growth, or diminiſh the number of their ſhoots. This method is ſometimes obſerved with corn and the eſculent graſſes; and, in cold years, is practiſed on fruit-trees and vines, to render the fruit riper and better coloured: but in this caſe it is proper to wait till the fruits have acquired their full bulk, as the leaves contribute greatly to their growth, but hinder, when too numerous, that exquiſite rectifying of the

juices, which is ſo neceſſary to render them delicious and palatable.

When vegetation ceaſes, the organs of perſpiration and inſpiration become ſuperfluous. Plants, therefore, are not always adorned with leaves: they produce new ones every year; and every year the greater part are totally diveſted of them, and remain naked during the winter. *Vide* FRONDESCENTIA *et* DEFOLIATIO.

Having premiſed theſe general obſervations reſpecting the anatomy and uſe of the leaves, I proceed to conſider the external form and configuration of this uſeful and ornamental part of the plant, and to particularize the ſeveral diſtinctions which are made by botanical writers on that ſubject.

Of leaves, ſome are primary, others acceſſary; theſe laſt are the *ſtipulæ* and *bracteæ* of Linnæus; the firſt of which are a ſet of ſcales, generally placed at the origin of the young footſtalks for ſupport: the latter accompany the flowers, and differ in figure and colour from the proper leaves of the plant. *Vide* BRACTEA and STIPULA.

In viewing the external appearance of leaves with reference to vegetable arrangement, two things occur to be conſidered:

The FORM of leaves, and their DETERMINATION.

By the *form of leaves*, I underſtand their ſtructure, and external configuration. By their *determination*, every thing reſpecting leaves, which does not pertain to their form, but to their diſpoſition on the plant.

Leaves, conſidered with reſpect to their form, are divided into ſimple and compound.

Simple Leaves.

Simple leaves are ſuch whoſe footſtalk is terminated by a ſingle expanſion; in other words, whoſe diviſions, however deep, do not reach the middle rib. To underſtand this, let it be obſerved, that the middle rib of every leaf is the principal

cipal prolongation of the footſtalk, which, to form the membranaceous expanſion called the leaf, runs out, as was obſerved above, into a number of ramifications, that inoſculating and croſſing each other mutually, form the cortical net already deſcribed. When theſe ramifications of the footſtalk are ſo connected as to form one entire expanſion, the leaf is ſaid to be ſimple; but when the middle rib becomes, in fact, a footſtalk, and many different expanſions, inſtead of one, proceed from the common footſtalk, the leaf is ſaid to be compound. This will be further illuſtrated below.

Simple leaves are either

Round, *folium orbiculatum*; as in *rumex digynus*.

Egg-ſhaped, *ovatum*; as in *vaccinium myrtillus*.

Oval or elliptic, *ovale*; as in the roſe.

Wedge-ſhaped, *cuneiforme*; as in *apium graveolens*.

Oblong, *oblongum*, as in ſorrel and woolly ceraſtium.

Lancet-ſhaped, *lanceolatum*; that is, tapering towards each extremity, as in *plantago lanceolata*.

Equally broad every way, *lineare*; as in roſemary, pine, and the graſſes.

Chaffy and ever-green, *aceroſum*; as in fir, yew, pine, and cedar-trees.

Awl ſhaped, *ſubulatum*; that is, gradually contracting towards the top, as in juniper, *arenaria ſaxatilis*, and *ſedum rupeſtre*.

Ear ſhaped, *auriculatum*; that is, furniſhed with two appendages or ears at the baſe near the foot-ſtalk, as in *jungermannia ciliaris*.

Heart-ſhaped, *cordatum*; as in lime-tree.

Kidney-ſhaped, *reniforme*; as in aſarabacca, ſea bind-weed, *campanula rotundifolia*, and *ſaxifraga granulata*.

Arrow-ſhaped, *ſagittatum*; as in field bind-weed, and common heath.

Halbert or ſpear-ſhaped, *haſtatum*; as in bitter-ſweet; and *ſcutellaria haſtifolia*.

Parted half-way down, *fiſſum*.

Divided almoſt to the midrib, *lobatum*.

From the number of diviſions in either caſe, the leaves are termed *bifida*, *trifida*, *biloba*, *triloba*, &c.

Hand-ſhaped, *palmatum*; that is, reſembling an open palm or hand, a fan, or an umbrella. Theſe leaves have very deep longitudinal diviſions extending almoſt to the baſe; ſuch are thoſe of *palma chriſti*, *palmetto* or thatch, ſome of the ferns, and the true rhubarb, the *rheum palmatum* of Linnæus. The leaves of a ſpecies of paſſion-flower are ſhaped like the wings of a bat.

With reſpect to their tip or extremity, ſimple leaves are,

Stumped, or ſeem bitten, *truncatum*; as in the tulip-tree.

Terminated with tendrils, *cirroſum*; as in ſuperb lily.

The margin or brim of the leaf runs out into rigid points or thorns (*folium ſpinoſum*) as in holly; or is furniſhed with horizontal points of the conſiſtence of the leaf (*folium dentatum*) as in dandelion, ſpring-primroſe, and *epilobium montanum*. In *vaccinium myrtillus*, and *arbutus alpina*, it is ſawed (*folium ſerratum*); that is, furniſhed with teeth, whoſe points look towards the tip or upper extremity of the leaf. In *primula farinoſa*, it is notched (*crenatum*) or cut into ſmall teeth, which are either ſharp or round at the points, and do not look to either extremity. In *erica ciliaris*, it is fringed like an eye-laſh, (*ciliatum*), or guarded longitudinally by parallel briſtles. The upper part of the leaf has commonly a ſmoother ſurface than the lower; it is beſides of a deeper green, and has its nerves and ramifications generally hollow; whilſt the ribs of the lower ſurface are moſt commonly prominent. This rule, however, is not univerſal; ſome leaves have their ribs prominent above, and hollow below. Theſe leaves are called by botaniſts, *folia bullata*; that is, bliſtered leaves. Such are thoſe of many ſpecies of ſage. Again, the leaves of ſucculent, bulbous, and ſeveral liliaceous plants, have on neither ſide, the prominent nerves or ribs which are found on almoſt all the leaves of trees.

With reſpect to their ſurface, leaves are,

Cottony, or covered with a beautiful white down, *folium tomentoſum*; as in *ceraſtium tomentoſum*, raſpberry, and the greater part of plants that grow in the neighbourhood of the ſea.

Woolly,

Woolly, or ſoft like velvet, *lanatum*, as in iron-wort, *ledum villoſum*, and ſome geraniums.

Hairy, *piloſum*; as in *cortuſa* and *juncus piloſus*.

Briſtly, *hiſpidum*; as in *turritis hirſuta*.

Rough with knots, *ſcabrum*; and covered with pimples, *papuloſum*; as in ſeveral of the fig-marigolds.

Prickly, *aculeatum*; as in ſome of the thiſtles.

Covered with tranſparent points, *punctatum*; as in St. John's wort.

Smooth, *glabrum*; as in bay.

Shining or glittering, *nitidum*; as in Canadian angelica, and ſome magnolias.

Wrinkled, *rugoſum*; as in ſage.

Beautifully plaited, *plicatum*; as in lady's mantle.

Riſing and falling in convexities towards the margin, *undulatum*; as in *œnothera molliſſima*.

Covered with ſimple, unbranched prolongations of the footſtalk, that extend from the baſe to the tip, *nervoſum*; as in cinnamon, camphire, and ſome of the plantains.

Covered with veins, or branched veſſels, *venoſum*; as in *laurus nobilis*, and moſt plants.

Clammy, *viſcidum*; as in *ſenecio viſcoſus*.

Beautifully coloured, *coloratum*; as in *amaranthus tricolar*.

Naked, *nudum*; that is, without any kind of hair or pubeſcence.

Ray, and after him Linnæus, has diſtinguiſhed a natural family of plants, by the name of *aſperifoliæ*; that is, plants whoſe leaves are rough to the touch.

With reſpect to their ſubſtance, or general port, leaves are,

Cylindrical, *teres*; as in *allium vineule*, and *oleraceum*.

Succulent, as in the aloes.

Sword-ſhaped, as in *iris*.

Shaped like a Perſian ſcymitar, *acinaciforme*; as in ſome of the fig-marigolds, ſome of which are likewiſe hatchet and tongue-ſhaped.

Two-edged, *anceps*; as in *ſiſyrinchium*.

Keel-ſhaped on the under ſurface, *carinatum*; as in *crinum aſiaticum*.

Compound Leaves.

Compound leaves are ſuch whoſe footſtalk is terminated by ſeveral expanſions; in other words, whoſe diviſions extend to the common footſtalk, which not running into the membranaceous part of the leaf, ſupports the ſeveral lobes or leſſer leaves, called *foliola*, of which the compound leaf conſiſts.

Theſe *foliola* or lobes are, themſelves, ſmall ſimple leaves, and, like them, vary in their form, according to the diſtinctions already eſtabliſhed. Like them, alſo, they are ſometimes furniſhed with ſhort footſtalks, (*folium petiolatum*); ſometimes ſeated upon the middle rib without any proper footſtalk, (*folium ſeſſile.*) *Vide infra.*

In compound leaves, the production of the baſe of the leaf to which the leſſer leaves adhere is by botaniſts called *coſta*, the rib. The ſame term is uſed for the principal prolongation of the footſtalk in ſimple leaves. This prolongation in each of the lobes of a compound leaf is by ſome denominated a nerve; by others, leſs properly, a vein. The nerve is either moſt conſpicuous in the middle of the leaf, and then it is likewiſe ſometimes called *coſta*, the rib; or it is divided at its entrance into the membranaceous part of the leaf, into two, three, five, ſeven, or more parts.

As ſtudents of botany are frequently at a loſs to know compound leaves by ſight, and ſometimes apt to miſtake a common footſtalk for a branch, it is proper to obſerve, that in the angle which they form in iſſuing from the ſtems and branches, the footſtalks of the leaves are flat, if not hollowed; ſo that they preſent two ſurfaces, a front and a back; the former, as we have ſaid, hollow or flat, the latter, convex: whereas, ſtems and branches are univerſally alike on both ſides, being either both round, both flat, or both angular.

Again, buds are never obſerved in the angles formed by the lobes of a compound leaf with the foot-ſtalk: they iſſue from the angle which the whole leaf makes with the branch or ſtem. Laſtly, the branches in woody plants continue after the

the leaves are fallen. The common footſtalk of a compound leaf, however much it may reſemble a branch in appearance, may always be certainly diſtinguiſhed by this circumſtance, that it falls off with the leaves which it ſupports.

Compound leaves are divided into compound properly ſo called; leaves twice compounded; and leaves more than twice compounded. Each diviſion admits of a variety of modifications, which give riſe to as great a variety of terms.

A compound leaf properly ſo called, *folium compoſitum*, is only once compounded, and admits of the following varieties.

A finger-ſhaped leaf, *digitatum*, is properly a modification of a hand-ſhaped one, with this difference, that the diviſions, which reſemble fingers, are diſtinct, and extend to the extremity or top of the footſtalk on which they are collected in rays. Lupin, horſe-cheſnut, Ethiopian ſourgourd, and ſilk cotton-tree, furniſh examples. From the number of fingers or leaves thus collected, other terms have been invented. When two, the leaf is termed *binatum*; when three, *ternatum*, from the numerals, two and three, compounded with the Latin verb, ſignifying to grow. Sometimes too, the fingers in queſtion are ſeated immediately on the top of the footſtalk; ſometimes, as in trefoil, each finger is furniſhed with a ſmall proper footſtalk.

A winged or pinnated leaf, *pinnatum*, is compoſed of a number of ſmaller leaves arranged like wings along the ſides of a common footſtalk. In the former ſpecies of compound leaves, the lobes are attached to the ſummit of the footſtalk; in this, the common footſtalk is prolonged, becomes a kind of middle rib, and receives the lobes on both ſides of it. Theſe lobes or leſſer leaves are diſtinct, and have generally ſmall partial footſtalks, by which they are attached to the common footſtalk or middle rib. The term is commonly appropriated to leguminous plants, as the *acacias* and moſt of the butterfly-ſhaped flowers, and admits of conſiderable varieties.

The lobes of a winged leaf are ſometimes oppoſite, as in ſumach; ſometimes alternate, as in Greek valerian. Com-

pound

pound winged leaves are frequently terminated by an odd leaf or lobe, which is not attached to the ſides, as the other lobes, but ſtands by itſelf, and proceeds from the extremity of the middle rib. This mode of winged leaf is exemplified in many of the ſumachs, acacias, and ladies finger. Inſtead of the odd lobe juſt mentioned, ſome winged leaves are terminated with tendrils. When neither an odd lobe, nor a tendril terminates a winged leaf, it is called by botaniſts an abruptly winged leaf, as in *robinia caragana*. In ſome plants the lobes are of an unequal length, ſome pairs being larger than others. The leaf in that caſe is ſaid to be interruptedly winged, and is exemplified in ſome ſpecies of ladies finger. Laſtly, a winged leaf ſometimes conſiſts of two lobes or leſſer leaves only, as in fabago or bean caper, and ſome of the acacias. This ſpecies of winged leaf is termed by botaniſts *folium conjugatum*.

A recompounded or twice compounded leaf, *folium decompoſitum*, is that in which the footſtalk, inſtead of ſupporting lobes or leſſer leaves on the top, or on each ſide, bears partial footſtalks, from which proceed the leaves on both ſides.

In barren-wort each of the lateral footſtalks ſupports three leaves; this ſort of leaf is termed by Linnæus, *biternatum*, or *duplicato-ternatum*; that is, double-three-leaved. In many acacias, the ſmall leaves are arranged like wings, not around the common footſtalk, but on each ſide of the partial or lateral footſtalks proceeding from it; ſo that this kind of compound leaf is very properly ſtiled double-winged, (*bipinnatum ſeu duplicato-pinnatum*).

In ſome ſpecies of paſſion-flower, and cuckow-pint, the footſtalk divides at top into two parts, on the inſide of which the lobes or leſſer leaves are ſupported. This ſpecies of compound leaf is termed foot-ſhaped (*pedatum*).

A more than twice compounded leaf, *folium ſupradecompoſitum*, is that in which the lateral footſtalks, inſtead of bearing leaves, as in the former caſe, are ſubdivided into other partial footſtalks, from whence proceed the lobes or leſſer leaves; in other words, double-three-leaved, and double-winged-leaves, are here inſerted into a common foot-ſtalk: the leaf, in the firſt caſe, being termed triple-three-leaved (*triternatum*

ſeu

ſeu triplicato-ternatum); in the ſecond, triple-winged (*tri-pinnatum ſeu triplicato-pinnatum.*

Of the Determination or Diſpoſition of Leaves.

The determination of leaves, whether ſimple or compound, comprehends the four following particulars: the place of the leaf; its inſertion; ſituation; and direction.

By the place of the leaf is meant the particular part where it is attached to the plant.

A flower-leaf, *folium florale*, is placed near the flower, and never appears but with it.

A branch-leaf, *folium rameum*, is ſeated or placed upon the branch.

A ſtem-leaf, *folium caulinum*, grows from the ſtem or ſtalk of the plant.

An axillary-leaf, *folium axillare*, is that which proceeds from the inſertion of the branches: in other words, from their arm-pit, or the angle which they form with the ſtem.

A bottom, radical, or root-leaf, *folium radicale*, comes immediately from the root, without adhering to the ſtem.

A ſeed-leaf, *folium ſeminale*, proceeds immediately from a ſeed which has ſprouted; and is a production of its *cotyledons* or *lobes*. *Vide* COTYLEDONES.

By the inſertion of a leaf is meant the manner in which it is attached to the plant.

A leaf furniſhed with a foot-ſtalk, is termed by Botaniſts *petiolatum folium*; that which is ſeated immediately on the ſtem or branch without any manifeſt foot-ſtalk, *folium ſeſſile*, and is exemplified in ſpiked mint, *teucrium ſcordium*, and *tormentilla erecta*.

The ſame name is retained, when the baſe of the leaf only is left without any membranaceous expanſion, as in jujube.

A target ſhaped leaf, *folium peltatum*, has the footſtalk inſerted into the center of the lower diſk or ſurface, and not into the baſe or margin. This ſingular kind of leaf is exemplified in water lily, *palma Chriſti*, Indian-creſs, jack in a box, and a ſpecies of *geranium*, hence named *peltatum*.

This

This ſpecies of leaf was formerly termed *umbilicated*, from a ſmall cavity like a navel, that is formed on the upper ſide, immediately oppoſite to the inſertion of the footſtalk.

A running-leaf, *decurrens*, adheres cloſely to the ſtalk as if glued to it, from the baſe to the middle, the upper half remaining detached and free; in other words, this ſort of leaf extends itſelf downwards along the ſtem, beyond its proper termination. It is exemplified in thiſtle, *verbaſcum*, and globe flower.

A leaf is ſaid to embrace the ſtem, *amplexicaule*, when by its baſe it entirely ſurrounds it tranſverſely; as in moth-mullein, and black henbane. Theſe leaves are generally heart and arrow-ſhaped.

A perforated leaf, *folium perfoliatum*, differs from the former term, in that the perforating ſtalk or branch does not touch the margin, but approaches the center of the leaf. It is exemplified in perforated *uvularia*, and round-leaved *bupleurum*.

Two oppoſite leaves cohering at their baſe, ſo as to form one body embracing the ſtalk, are termed by Linnæus *folia connata*. Many ſpecies of honey-ſuckle and hemp-agrimony furniſh proper examples.

A glove-like leaf, *folium vaginans*, has the baſe formed into a tube or cylinder, which embraces the ſtalk like a ſheath or glove; as in corn, graſs, and many liliaceous plants.

Situation regards the reſpective poſition of the leaves between themſelves. In this reſpect leaves are

Alternate, when they come out ſingly, and are ranged gradually upon both ſides of the ſtem, as in *antirrhinum cymbalaria*; oppoſite, when they come out in pairs, facing each other; the reverſe of the former.

In moſt plants with oppoſite leaves, each pair is croſſed by that immediately above or below it, ſo that the leaves point four different ways; thus, if one pair ſtands eaſt and weſt, the one immediately below it ſtands north and ſouth, and croſſes the former at right angles; the third pair croſſes the

ſecond,

ſecond, and ſo on alternately, till all the pairs are completed. In this way are arranged the leaves of myrtle, jeſſamine, rocket, and ſeveral others.

Placed in whorls or rings, *verticillata folia*, when more than two leaves ſurround the ſtem. The different modifications of this term are derived from the number of leaves of which the ring conſiſts; *folia terna*, when three, as in oleander; *quaterna*, four, as in *ſedum verticillatum*; *quina*, five; *ſena*, ſix, as in *galium ſpurium*.

Starry leaves, *ſtellata*, a modification of the former term: when four, ſix or more leaves are ſo placed around the ſtem as to reſemble a ſtar, as in wood-roof and *galium*.

Scattered, *ſparſa*, when they are diſpoſed without any regular order; as in ſeveral ſpecies of lily.

Crowded, or diſpoſed in cluſters, *conferta*, when they come out from the ſides of the branches in great numbers, and are placed ſo cloſely together, that it is not eaſy to diſcover their exact ſituation, as in toad-flax, and *antirrhinum monſpeſſulanum*.

Laid over one another like tiles or fiſh-ſcales, *imbricata*, as in ſome ſpecies of ſaxifrage.

Placed in bundles, *faſciculata*, when many leaves proceed from the ſame point, as in the larch tree, and ſome pines.

Ranged along two ſides of the branches only, *diſticha*, as in the fir-tree.

With reſpect to direction, leaves are,

Oblique, *obliqua*, when the baſe looks to the ſky, and the tip to the horizon, as in knee-holly, Perſian fritillaria and protea.

Bent inwards, *inflexa*, when they are bowed or turned upwards towards the plant.

Laid cloſe to the ſtem, *adpreſſa*.

Upright, *erecta*, nearly perpendicular; in other words, when they form an extremely ſmall angle with the ſtem.

Spreading, *patentia*, when they recede from the ſtem, yet ſo as to form an acute angle with it.

Horizontal,

Horizontal, *horizontalia*, or *patentiſſima*, when they ſtand at right angles with the ſtem.

Reclined, *reclinata et reflexa*, when they are bowed downwards in ſuch a manner that the baſe is higher than the tip or ſummit.

Rolled back, *revoluta*, when the ſummit or tip is rolled inwards.

Depending, *dependentia*, when they point with their ſummits to the earth.

A rooting leaf, *folium radicans* is one, which being planted, ſtrikes root, and vegetates. Such are the fleſhy ſolid leaves of ſeveral liliaceous plants, as the aloe and ſea-onion.

A floating leaf, *natans*, lies or floats on the ſurface of the water, as in the water-lily and pond-weed.

A drowned or ſunk leaf, *demerſum*, is that which is placed below the ſurface of the water, as in the ſea-weed.

In moſt ſpecies of *ruſcus*, or butcher's broom, the flowers grow upon different parts of the leaves; on the middle of the upper ſurface in *ruſcus aculeatus et flexuoſus*; on the middle of the under ſide in *ruſcus hypophyllum et hypogloſſum*; in which laſt the flowers iſſue from between the main leaf, and a ſmaller one reſembling a tongue, which is placed near the middle of the under ſurface of the former. In *ruſcus androgynus*, the flowers proceed from the margin or brim of the leaves.

The leaves furniſh very elegant and natural marks in diſcriminating the ſpecies of plants. In no part, indeed, is nature more various than in the ſtructure of the leaves, the very numerous ſpecies of which ought, therefore, to be carefully ſtudied by the beginning botaniſt. Ray, Linnæus, Royen, and other eminent botaniſts, have borrowed the greater part of their ſpecific names, as well as characters, from this part of the plant.

The oppoſition and alternation of the leaves furniſh characters which are generally conſtant, that is, found to obtain in all the plants of the ſame genus, or even of the ſame natural order.

In

In euphorbia, rock-roſe, American viburnum, calves ſnout, lily and French willow-herb, theſe characters ſerve to diſtinguiſh the ſpecies; in ſome of which the leaves are oppoſite, or placed two by two; in others alternate.

In the different ſpecies of jeſſamine, ſpeedwell and borage, the lower leaves at the branches are oppoſite; the upper leaves at the flowers, alternate.

Pond-weed, and a ſpecies of cinquefoil, have the lower leaves alternate; the upper ones at the branches, oppoſite.

In oleander, the lower leaves are oppoſite; the upper ones grow by threes, the loweſt modification of leaves placed in a whorl or ring (*folia verticillata*). *Vide Supra.*

In butcher's broom, the lower leaves grow by threes; the upper ones are alternate: the branches have the ſame ſituation.

In a ſpecies of calve's ſnout, and tick ſeeded ſun-flower, *coreopſis*, the lower leaves grow by fours; the upper ones are alternate.

The natural ſituation of the leaves in plants that are much branched, Linnæus thinks is beſt concluded from the radical or bottom leaves.

Oppoſite and compound leaves are often ſubject to luxuriance in the ſame ſpecies, and hence give riſe to conſiderable varieties, which muſt, in all caſes, be carefully diſtinguiſhed from the ſpecies.

In ſome ſpecies of *lyſimachia* and pimpernel, the leaves, which are generally oppoſite, grow occaſionally by threes, fours, or fives.

A ſpecies of purple looſe-ſtrife has ſometimes three leaves growing round the ſtalk.

As theſe, however, are but accidental varieties, and the characters in queſtion are not permanent, but ſubject to vary when the plant is propagated from ſeed, we ſhould be careful, in all ſuch inſtances, not to load or incumber any genus of plants with an unneceſſary multiplication of ſpecies, when the characters are not ſufficiently conſtant to entitle any particular plant to that appellation.

When theſe varieties happen in plants with oppoſite leaves,

the

the ſtalk, from being ſquare, becomes furniſhed with many ſides, as of ſix in the laſt inſtance.

Again, finger-ſhaped leaves, of which there are many different modes, occaſionally gain an addition of one or two leaves in the ſame ſpecies, as in ſome trefoils.

Curled leaves, *folia criſpa*, which are a frequent variety, Linnæus denominates a ſort of monſtrous production, and compares them to the prodigious multiplication of the petals in full flowers. Without doubt, no genuine ſpecies of plants has curled leaves, the appearance being accidental and inconſtant: yet botaniſts, till the time of Linnæus, not attending to this circumſtance, have conſidered as diſtinct ſpecies, many plants in which the ſuppoſed character of the ſpecies is but occaſionally preſent. To ſay truth, Linnæus's greateſt merit conſiſts in the excellent rules he has laid down for eſtabliſhing the ſpecies and varieties, particularly the latter, which he found involved in one undiſtinguiſhed chaos, but has now happily reduced into the moſt perfect ſymmetry and order.

The curled leaves, juſt mentioned, are to be found in ſome ſpecies of mallow, dock, nipplewort, hart's-tongue, endive, and baſtard rocket.

In tanſy, feverfew, baſil, and mint, when the leaves are curled, their ſcent is conſiderably heightened.

We explained above the nature of a bladdery or bliſtered leaf, by botaniſts termed *folium bullatum*. The warted leaf, *folium verrucoſum*, is a ſpecies of the former; and, both ſeem to be incidental varieties, produced from the luxuriance of a wrinkled leaf, *folium rugoſum*, as curled leaves are a preternatural extenſion of an undulating or waved one.

Inſtances of bladdery and warted leaves may be ſeen in ſome ſpecies of baſil, braſſica and lettuce.

In a ſpecies of ſoapwort, termed by Miller *ſaponaria hybrida*, and by Linnæus *ſaponaria concava anglicana*, the leaves are generally hollowed like a ſpoon, or ladle. *Vide* CARYOPHYLLEI *in fine*.

In ſome ſpecies of cow-parſnep, water hore-hound, braſſica, elder, and valerian, the leaves are incidentally found

to

to vary from broad-leaved to narrow-leaved; but this variety is leſs frequent.

Such are the principal varieties to which leaves are incident in their form and ſtructure. I conclude this article, with obſerving, that in the enumeration of terms expreſſive of the form and configuration of the leaves, I have purpoſely avoided mentioning ſuch whoſe meaning is ſufficiently obvious, without any laboured elucidation. The reader will obſerve too, that I ſeldom offer an explanation, without accompanying it with as familiar an example as the nature of the thing will admit. Without an illuſtration of this kind, every ſuch explanation muſt be inadequate and unſatisfactory; and yet, Linnæus has in very few inſtances favoured us with any: nor have his latinized tranſlators, Lee and Berkenhout, diſcovered any vehement inclination to remove the thick cloud, which ſtill reſts on every part of this delightful ſcience.—In aſſimilating the vegetable and animal kingdoms, Linnæus denominates leaves, the lungs of plants.

FOLICULUS, (diminutive from *follis*, a leather bag); a ſpecies of ſeed-veſſel, generally conſiſting of one valve, ſynonymous to *conceptaculum*, and ſubſtituted for it in the later editions of Linnæus's works. *Vide* CONCEPTACULUM.

FOLLICULI are likewiſe defined by the ſame author to be ſmall glandular veſſels diſtended with air, which appear on the ſurface of ſome plants; as at the root of water-milfoil, and on the leaves of aldrovanda. In the former, the veſſels in queſtion are roundiſh, and furniſhed with an appearance like two horns; in the latter, pot-ſhaped and ſemi-circular.

FRAGMENTA *Methodi Naturalis*, the Fragments of a Natural Method; Linnæus's title of a plan or ſketch of a natural arrangement of plants, which he has barely traced in the *Philoſophia Botanica* and *Genera Plantarum*. The Author of the preſent work has the honour of having been the firſt who attempted to complete the draught of which only the outline had been furniſhed by the great Maſter; his Deſcriptions of the habit and ſtructure, virtues, ſenſible qualities and œconomical uſes of the plants which compoſe the ſeveral Natural Orders of Linnæus having been ſubmitted by

him to the public in the firſt edition of the Botanical Dictionary, publiſhed in 1770, in preciſely the ſame form in which they now appear. Linnæus's own Lectures on the ſubject, from the notes of Giſeke and Fabricius, two of his pupils, were not given to the world till a long time after *.

FREQUENS *Planta*, a plant ſo termed by Linnæus, which grows ſpontaneouſly and copiouſly in a proper ſoil. The term is ſynonymous to *vulgaris planta* of the ſame author.

FRIGIDÆ *Plantæ*, from *frigus*, cold; plants that are natives of cold climates. Such are thoſe of the Alps, Siberia, Canada, Germany, Holland, England, and France to the northward of Paris.

Theſe plants, ſays Linnæus, ſcarce bear a degree of heat that is as 30 on a ſcale in which 0 is the freezing point, and 100 the heat of boiling water. In exceſſive heats, they firſt prove luxuriant, then turn feeble and die.

FRONDESCENTIA, (from *frons*, the leaf of a tree,) a term expreſſive of the preciſe time of the year and month in which each ſpecies of plants unfolds its firſt leaves.

All plants produce new leaves every year; but all do not renew them at the ſame time. Among woody plants, the elder, and moſt of the honey-ſuckles; among perennial herbs, crocus and tulip, are the firſt that puſh or expand their leaves. The time of ſowing the ſeed decides with reſpect to annuals. The oak and aſh are conſtantly the lateſt in puſhing their leaves: the greateſt number unfold them in ſpring; the moſſes and firs in winter. Theſe ſtriking differences, with reſpect to ſo capital a circumſtance in plants as that of unfolding their leaves, ſeem to indicate that each ſpecies of plant has a temperature proper or peculiar to itſelf, and requires a certain degree of heat to extricate the leaves from their buds, and produce the appearance in queſtion.

This temperature, however, is not ſo conſtant as, to a ſuperficial obſerver, it may appear to be. Among plants of the ſame ſpecies, there are ſome more early than others; whether that circumſtance depends, as it moſt commonly

* In 1792.—See more upon this ſubject in the Preface.

does, on the nature of the plants, or is owing to differences in heat, expoſure, and ſoil. In general, it may be affirmed, that ſmall and young trees are always earlier than larger or old ones.

The puſhing of the leaves is likewiſe accelerated or retarded according to the temperature of the ſeaſon; that is, according as the ſun is ſooner or later in diſpenſing that certain degree of heat which is ſuitable to each ſpecies.

Till very lately the time in which plants renew or unfold their leaves, was conſidered as an abſolute fixed term or limit, happening every year, nearly at the ſame time, in every climate. Linnæus is the only one who has paid proper attention to this curious ſubject. His deſign in publiſhing the obſervations which he had made in eighteen provinces of Sweden, ſituated betwixt the ſixtieth and ſeventieth degrees of north latitude, during the three ſucceſſive years, 1750, 1751 and 1752, was merely to diſcover what trees begin to open their buds and unfold their leaves, at the moſt proper time for ſowing of barley.

The birch-tree appeared to him the moſt proper indication for this purpoſe; and he concludes, that in every province in Europe, there may be found trees, in default of the birch, that will, in the like manner, indicate the proper time for ſowing grain and eſculent herbs. Theſe obſervations, however, do not perfectly anſwer the purpoſe for which they were made, as the birch, and every other ſimilar tree, can only indicate the paſt or preſent, not the future; which, by the way, is the only thing importing the huſbandman to know, that he may have time to prepare the ground and ſow the ſeed; beſides, the ſpecies birch, like moſt other trees, has individuals, which are three or four weeks later than the reſt; ſo that if we have not an opportunity of ſeeing more than one tree, we cannot poſſibly divine whether it is the lateſt or earlieſt of its ſpecies, and thus may often run the riſk of delaying to ſow the ſeed a whole month beyond its proper time.

In ſhort, to be able to draw any certain concluſions, with reſpect to the time in which the different plants of different

climates unfold their leaves, and to reduce their apparent variations to fixed and preciſe rules, we muſt

I. Obſerve the different times in which different individuals of the ſame ſpecies unfold their leaves; and thence draw the mean times betwixt the earlieſt and lateſt.

II. Obſerve, by a thermometer, the difference of temperature in the early and late years.

III. Draw mean reſults of the degrees of heat obſerved every month and every day, for a ſufficient number of years.

IV. Obſerve the days in which the froſts begin to ceaſe, and thoſe in which there are ten degrees of heat, even during the night. Theſe are the times in which vegetation, formerly clogged, if not altogether ſtopt, begins to make progreſs, and to continue without interruption.

Laſtly, From the extreme products of each of theſe obſervations, we muſt drawn mean reſults; as without ſuch precaution, nothing certain can be obtained in enquiries of this kind.

For the application of theſe obſervations, the reader is referred to the ingenious M. Adanſon's Familles des Plantes, a book which for variety of botanical knowledge, exceeds any hitherto publiſhed.

FRONDOSUS *flos*. *Vide* PROLIFER *flos*.

FRONS, is defined by Linnæus to be the trunk of the palms and ferns, in which the leaves are confounded with the ſtem and branches, and frequently with the flower and fruit. The term, indeed, ſeems to import the union of a leaf and a branch; and that the pretended trunk in queſtion is really a compound leaf, appears from this circumſtance, that it has plainly two ſides, which are different in figure and colour; whereas all the parts of a real trunk or ſtem are perfectly ſimilar.

The leaves of the ferns and palms are generally winged. The baſe of the foot-ſtalk, or that part which has no *pinnæ* or leſſer leaves proceeding from it, conſtitutes, according to Linnæus, another trunk, which he denominates *ſtipes*.

FRUCTESCENTIA, (from *fructus*, fruit,) comprehends the

the preciſe time in which, after the fall of the flowers, the fruits arrive at maturity, and diſperſe their ſeeds.

In general, plants which flower in ſpring, ripen their fruits in ſummer, as rye; thoſe which flower in ſummer, have their fruits ripe in autumn, as the vine; the fruit of autumnal flowers ripens in winter, or the following ſpring, if kept in a ſtove, or otherwiſe defended from exceſſive froſts. Theſe froſts, ſays M. Adanſon, are frequently ſo pernicious and violent as to deſtroy the greateſt part of the perennial plants of Virginia and Miſſiſſippi that are cultivated in France, even before they have exhibited their fruit. The plants which flower during our winter, ſuch as thoſe of the Cape of Good Hope, ripen their fruit in ſpring in our ſtoves.

The time in which plants ripen their fruit, combined with that in which they germinate and unfold their leaves, gives the entire ſpace or duration of their life, which, in the ſame ſpecies, is proportionably ſhort or long, according to the greater or leſs intenſity of heat of the climate, in which they are cultivated.

In general, it appears, that if the heat is equal and uninterrupted, the time betwixt the germinating or ſprouting and flowering of annual plants, is equal to the interval betwixt their flowering and the maturation of their fruits, or even the total deſtruction of the whole plant.

In Senegal and the other burning climates, an annual plant generally lives as long before as after flowering.

In temperate climates, as France and England, plants which riſe in ſpring and flower before the month of June, live a little longer before than after flowering; ſuch as flower in ſummer, as barley and oat, which flower in June, live as long before as after; while the later plants, which do not riſe till autumn, live longer after flowering than before.

Theſe facts, which are undoubted, prove the very great efficacy of heat in operating the vegetation of plants. In effect, it is in ſummer, when the heat is moſt equal, that the life of plants is equally divided into two parts; whereas in ſpring and autumn, when the heat is more unequal, it is cut

or divided unequally: the plants of the ſpring ſeaſon, which is colder in the beginning, live, as we have ſaid, longer before flowering than after, when the heat is more intenſe: and, on the contrary, the plants of autumn, which is warmer in its beginning, live a ſhorter time before than after flowering, when the heat becomes every day leſs, and conſequently retards the maturation of the fruit.

Theſe obſervations are only to be underſtood of herbaceous vegetables, and thoſe chiefly annual. Among trees, ſome do not renew their leaves till a little before, and ſometimes not till after, they have produced flowers; ſo that there is a much greater interval between their flowering and the maturation of their fruit, than between the former and the unfolding of their leaves, which, in trees, may be conſidered as equivalent to the germination or ſprouting of the ſeed in annuals. The maturation of the fruit in trees is never accompliſhed, while they abound in ſap, and produce new wood; for this reaſon, when we would accelerate the bearing of fruit-trees, we generally ſtrip off a part of their leaves, which diminiſhes the motion of the ſap, and thus removes the obſtruction which retarded the ripening of the fruit. *Vide* FOLIUM.

FRUCTIFICATIO, (from *fructus*, fruit, and *facio*, to make.) Under this name Linnæus comprehends the flower and the fruit, which, according to the Sexualiſts, are connected in the ſame manner as generation and birth in animals. In fact, although the fruit does not ſwell and ripen till after the flower is fallen, yet it ſeems now to be generally allowed, that its firſt beginning or rudiment is in the flower.

Fructification is defined to be a temporary part of plants appropriated to generation, terminating the old vegetable and beginning the new. The parts of fructification are, by Linnæus, reckoned ſeven: viz.

The calyx, empalement, or flower-cup.
The corolla, or petals.
The ſtamina, threads, chives, or male organs.
The piſtillum, pointal, or female organ.
The pericarpium, or ſeed-veſſel.
The ſeeds.

The

The receptacle or baſe, upon which all the other parts are ſeated.

The four firſt are properly parts of the flower; the three laſt, of the fruit. The germen or ſeed-bud connects them together. This is properly part of the flower, as being the baſe of the piſtillum; yet as, in proceſs of time, it becomes the ſeed-veſſel, it is generally conſidered as a part of the fruit: and hence, if the perianthium or flower-cup ſurrounds it alone, it is called a perianthium of the fruit.

The eſſence of every vegetable, ſays Linnæus, conſiſts in the fructification: the eſſence of the fructification conſiſts in the flower and fruit.

The various aphoriſms eſtabliſhed by modern botaniſts with reſpect to the importance of the parts of fructification in vegetable arrangement, are delivered in ſeveral parts of this work; particularly under the articles CLASSIS, GENUS and CHARACTERES. The following fall properly enough to be eſtabliſhed in this place.

I. The primary diſpoſition or arrangement of vegetables ought, with due reſtrictions, to be derived from the parts of fructification. Former botaniſts urged the inſufficiency of theſe parts to ſerve as a foundation for the claſſes and genera; becauſe, perhaps, they were not all ſo accurately known as at preſent: and, even with all our ſuperior knowledge, we are often at a loſs in aſcertaining ſeveral genera of plants, without calling in the aſſiſtance of parts unconnected with the fructification.

By a rigid attention to the aphoriſm juſt mentioned, Linnæus has converted into ſpecies many genera of Tournefort, Dillenius, Boerhaave, Ruppius, Vaillant, Micheli, and Gmelin, which are not founded upon the parts of fructification alone.

The following genera of Tournefort, among many others, furniſh examples.

Purple bird's-neſt is, by Linnæus, converted into a ſpecies of orchis.

Biſtort, of knot-graſs.

Turnip, of cabbage.

Skirrets, of water-parſnep.
Hermodactylus, of Iris.
Orpine, of leſſer houſe-leek or ſedum.
Flea-wort, of plantain.
Cork-tree, of the oak.
Larch-tree, of the pine.
Dwarf broom, of ſingle-ſeeded broom or geniſta.
Dragons, of cuckow-pint.
Engliſh black maiden-hair, of ſpleen-wort.
The bean, of the vetch.
Water-melon, of the gourd.

II. Vegetables which agree in all the parts of fructification are not to be arranged in different claſſes, orders, or genera.

Geſner was the firſt who ſuggeſted this aphoriſm; Cæſalpinus the firſt who reduced it into practice.

III. The more conſtant any part of fructification is, throughout a great number of ſpecies, the more certainly is it to be depended on as a characteriſtical mark in diſtinguiſhing the genera.

The nectarium of the genus *hypecoum* is conſtant, but not the jointed pod.

The ſpotted berry of the genus *convallaria* is found in all the ſpecies; the corolla in lily of the valley, Solomon's ſeal and one blade, three ſpecies of convallaria, is very different.

The corolla of wild ſēna is conſtant, but not the pod.

In the genus *lobelia*, which includes ſeveral genera of other authors, the corolla is conſtant. The ſeed-veſſel, in cardinal-flower, rapuntium of Tournefort and Dillenius, laurentia of Micheli, and lobelia of Plumier, which are all ſpecies of the Linnæan genus, is different. That particularly of the laſt ſpecies, the lobelia of Plumier, is pulpy, and of the cherry kind, containing a nut or ſtone with two cells; whereas in the other ſpecies, it is a dry membranaceous capſule.

In vervain, the calyx and corolla are conſtant throughout the ſpecies: the ſtamina and ſeeds are different.

FRUCTIFLORÆ, (from *fructus*, fruit, and *flos*, a flower);

flower); the name of the tenth claſs in Royen's Natural Method, conſiſting of plants, in which the flower, or, to ſpeak more properly, the receptacle of the flower is placed above the fruit: it correſponds to the claſs *coronatrices* in Linnæus's *Methodus Calycina*, and is exemplified in French willow-herb.

FRUCTISTÆ, (from *fructus*, fruit;) a claſs of Syſtematic Botaniſts ſo termed by Linnæus, who have arranged vegetables from the ſeed-veſſel, ſeeds and common receptacle, the three parts of the fruit. The beſt ſyſtems of this kind are thoſe of Cæſalpinus, Moriſon, Ray, Chriſtopher Knaut, Hermannus, and Boerhaave. *Vide* METHODUS.

FRUCTUS, the fruit; defined by Jungius and former botaniſts to be an annual part of the plant, which adheres to the flower and ſucceeds it; and, after attaining maturity, detaches itſelf from the parent plant; and, being commodiouſly lodged in the boſom of the earth, gives birth to a new vegetable. This definition is ſufficiently accurate, and ſo perſpicuous, that it requires no illuſtration. I ſhall only obſerve, that, in its vulgar acceptation, the word fruit is expreſſive, not of the ſeeds, which are doubtleſs the eſſence of every fruit, but of the caſe or veſſel in which they are contained. Thus, when we ſpeak of the fruit of an apple-tree, we always mean the luſcious pulp which enfolds the ſeeds; although that, in ſtrict propriety, is only the cover of the fruit.

The Sexual Syſtem being founded on the ſuppoſed impregnation of the ſeeds by the male duſt, the importance of that part of the plant, (the ſeed) is conſiderably augmented: accordingly Linnæus, among the other principles with which his Method ſets out, eſtabliſhes the aphoriſm manifeſtly deducible from Jungius's definition, that a fruit is conſtituted by the preſence of the ſeed, whether there be a ſeed-veſſel or not; and to this he immediately ſubjoins, that all vegetables are furniſhed with fruit, that is, ſeeds; though theſe are frequently ſo minute, or ſo ſituated, as to elude the ſight. *Vide* FLOS.

With reſpect to the imperfect plants here manifeſtly alluded

to,

to, the ſeeds of the *fuci* were diſcovered in 1711, by M. de Reaumur; thoſe of the moſſes by Dillenius, in 1719 and 1741. Linnæus, in his Philoſophia Botanica, arrogates the diſcovery of the latter tribe of plants to himſelf. "Semina muſcorum," ſays he, "ego detexi." Micheli was the firſt who in 1729, detected the ſeeds of muſhrooms; his curious diſcoveries in this, till of late, ſhamefully neglected tribe of vegetables, were confirmed by the obſervations of Mr. Gleditſch, in 1753; and of M. Battarra, in 1757.

The ſeeds of ſome ferns were diſcovered by Dr. Bobart of Oxford; thoſe of others, by Bernard de Juſſieu, in 1739; and of M. Maratti in 1760.

FRUCTUS *carnoſus*, fleſhy or pulpy fruit. The name given by ſome former botaniſts to that ſpecies of ſucculent ſeed-veſſel called by Linnæus, *Pomum*. *Vide* POMUM.

FRUMENTA, corn; the name of the twenty-firſt claſs in Ray's *Methodus Propria*, conſiſting of the eſculent grains; as oat, rye, barley, and the like.

FRUTEX, a ſhrub; a plant which riſes with a woody durable ſtem to a height ſuperior to that of under-ſhrubs, inferior to that of trees. Trees too always riſe with a ſingle body or trunk. Many ſhrubs have ſeveral ſtems growing out of the ſame root.

For the opinions of different authors concerning the foundation of the diſtinction of vegetables into herbs, trees, ſhrubs, and under-ſhrubs, ſee the article ARBOR.

FRUTICES. The name of the ſecond claſs in Moriſon's Syſtem, and of a diſtinction in all the ſyſtematic botaniſts prior to Linnæus, conſiſting of thoſe woody plants termed ſhrubs. *Vide ſupra*.

FUCATÆ *figuræ*; figures of plants coloured from nature; ſuch are thoſe of Martin, Blackwell, and Weinmannius.

FULCRA, props, ſupports. By this name Linnæus diſtinguiſhes certain minute external parts, which ſerve either to ſupport or defend the plants on which they are found, from external injuries; or to facilitate ſome neceſſary ſecretion.

Theſe

Theſe *fulcra* have undergone conſiderable alterations ſince their firſt publication in the Fundamenta Botanica in 1736, when they ſtood thus: bractea, cirrus, ſpina, aculeus, ſtipula, glandula. In a ſubſequent edition of the ſame book, printed at Paris in 1744, they are augmented to nine, by the addition of ſcapus, petiolus and pedunculus, which were formerly conſidered as different ſpecies of trunks. In the Philoſophia Botanica, publiſhed in 1755, the three terms which were formerly added are again transferred to the head of trunks, and another term is joined to the original liſt, ſo that it ſtands thus; ſtipula, bractea, ſpina, aculeus, cirrus, glandula, pilus. Laſtly, in the Termini Botanici, publiſhed in the Amœnitates Academicæ by Elmgren, a pupil of Linnæus; and in the Delineatio Plantæ, prefixed to the ſecond volume of the Syſtema Naturæ, the *fulcra* undergo another revolution. Inſtead of *aculeus* and *ſpina* the different offenſive weapons of plants, is ſubſtituted the general term *arma*: and inſtead of *pilus*, a particular ſpecies of defenſive weapon, is ſubſtituted *pubes*, which implies every kind of pubeſcence or hairy appearance on the ſurface of plants. *Glandula*, which had appeared in the very earlieſt editions of Linnæus's works, is not now to be found in the liſt of *fulcra*, being included in the general term *pubes*; and the partial trunks, as they were formerly reckoned, *petiolus* and *pedunculus*, once more change their place, and are transferred to an article with which they have no connection. The liſt of *Fulcra*, thus new-manufactured, ſtands as follows:

Petiolus, the foot-ſtalk of the leaf.

Pedunculus, the foot-ſtalk of the flower.

Stipula, a ſcale ſeated at the inſertion of the foot-ſtalks.

Bractea, a coloured leaf accompanying the flower.

Cirrus, a tendril or claſper.

Arma, the offenſive weapons of plants.

Pubes, the hairs, defenſive weapons, or ſecretory veſſels of plants.

A particular deſcription of each of theſe auxiliary parts is given under its reſpective term.

FUNDA-

FUNDAMENTALES *figuræ*, figures of plants not ſhaded, outlines; ſuch are thoſe of Brunsfelſius, Fuchſius, Cluſius, and Father Plumier.

FUNGI, muſhrooms. The name of one of the ſeven families or tribes into which all vegetables are divided by Linnæus in his Philoſophia Botanica. In the Sexual Syſtem, they conſtitute the fourth order of the claſs *Cryptogamia*; in Tournefort's Method, a part of the ſeventeenth claſs, entitled *aſpermæ vulgo habitæ*.

In Ray's and Haller's Methods is likewiſe a claſs of the ſame name, containing the ſame plants. Theſe have all a very ſimilar appearance; and as the parts of fructification, which by modern botaniſts are ſolely attended to in diſtinguiſhing the genera, are ſcarcely to be diſcovered, the conſequence has been, that, till lately, ſcarce any diſtinction of the genera has been attempted, and of courſe, this very conſiderable part of the vegetable kingdom, to the great reproach of ſcience, lay much uncultivated. I muſt not, however, forget, upon this occaſion, to do that juſtice which is ſo eminently due to the ingenious reſearches of Dillenius and Micheli, to whom we were long indebted for moſt of the little knowledge we poſſeſſed of the *Fungi*, as well as ſome other tribes of imperfect plants.

The former, in his Catalogus Plantarum circa Giſſam, publiſhed at Francfort in 1719, arranges muſhrooms from the figure of their footſtalk, their hat or upper part termed pileus, its laminæ or plates, holes and cavities, into ten genera, which contain in all about two hundred ſpecies.

Micheli, in a work entitled Nova Plantarum Genera, publiſhed at Florence in 1729, arranges this tribe of plants from the figure of their flowers, and the ſituation of the ſtamina and ſeeds, which, as he imagined, he had detected in the greateſt number.

Micheli's method is divided into four ſections, which contain in all about eight hundred ſpecies, arranged under thirty genera, accurately and perſpicuouſly diſtinguiſhed. This author is the firſt who, by means of the microſcope, diſcovered ſomething like ſtamina in the muſhrooms: and

attempted

attempted to prove that theſe plants, like the more perfect ones, are produced from ſeed.

Gleditſch's Arrangement of the muſhrooms, publiſhed at Berlin, in 1753, differs but little from that of Micheli juſt mentioned. This author deſcribes with accuracy about a thouſand ſpecies or varieties of theſe plants, and gives figures of each of his genera, copied from thoſe of Micheli.

Battarra, in his Enumeration of the muſhrooms that grow in the neighbourhood of Rimini, printed in 1755, has given figures and deſcriptions of two hundred and ſixty ſpecies, which are diſtributed, not very methodically indeed, among eighteen ſections or orders, which might, without hurting the work, have been reduced to ſeven.

The author proves in this work, that muſhrooms owe their exiſtence, not to putrefaction, as had been erroneouſly imagined, but to ſeeds; that thoſe which grow upon vegetables have their fibres contiguous only to theſe plants, not continuous with them; and in fact, have their own proper roots, as other vegetables. He has likewiſe evinced, that they are not a luſus naturæ, but that their ſpecies are conſtant, and renewed by uniform laws, as many ſpecies, which grow in Italy, grow likewiſe in Britain, France, Germany and Turky; and as he, Micheli, and Gleditſch had ſucceeded in their experiments for raiſing muſhrooms ſimilar to thoſe which they had ſown.

After all, our knowledge of this part of vegetable nature is exceedingly limited; and, as I have often had occaſion to obſerve in the courſe of this work, a very intimate acquaintance with theſe and plants of a ſimilar character, is ſcarcely to be expected during the dominion of the Sexual Syſtem: for, as the parts of fructification in theſe plants, if they are indeed ſuch, can only be detected by the aid of glaſſes, it is impoſſible they ſhould be ſo univerſally known, as to give much aſſiſtance in detecting the genus, far leſs be of themſelves ſufficient towards that detection.

FUNGI, the name of the fifty-eighth order in Linnæus's Fragments of a Natural Method, conſiſting of the following

genera,

genera, which are the ſame with thoſe of the fourth order of the claſs Cryptogamia in his Artificial Method, with the addition of byſſus, which is there joined to the algæ or ſea-weed.

Liſt of the Genera *contained in this Natural Order.*

Linnæan Genera.			*Engliſh Names.*
Agaricus,	—	—	Agaric.
Boletus.			
Byſſus.			
Clathrus.			
Clavaria,	—	—	Club-top.
Elvela ſeu Helvella,		—	Turban-top.
Hydnum.			
Lycoperdon,	—	—	Puff-ball.
Mucor,	—	—	Mould.
Peziza,	—	—	Cup-muſhroom.
Phallus,	—	—	Stinkhorns, Morell.

Theſe plants are rarely branched, ſometimes creep, but are moſt commonly erect. Such as are furniſhed with branches have them of a light ſpungy ſubſtance like cork. Muſhrooms differ from the fuci in that thoſe, which, like the fuci, have their ſeeds contained in capſules, are not branched, as that numerous claſs of ſea-weed is.

The greateſt part of muſhrooms have no root; ſome, in their ſtead, have a number of fibres, which, by their inoſculations, frequently form a net with unequal meſhes, ſome of which produce plants ſimilar to their parent vegetable.

The STAMINA, in theſe plants, are ſtill undetermined. What Micheli takes for this pretended male organ has all the appearance of a number of ſhoots or ſuckers, under the form of a fine powder or duſt.

The SEEDS are either ſpread over the ſurface of the plant, or placed in cavities which are open, and reſemble the open

open capſules of ſome of the fuci. In muſhrooms which are branched, the ſeeds are frequently viſible by the naked eye, and always to be diſtinctly obſerved with the aſſiſtance of a good microſcope.

Theſe plants are very aſtringent, and of familiar uſe for ſtopping violent hæmorrhages.

As a vegetable food, they are, at beſt, ſuſpicious. Several *Fungi* are rank poiſon.

Agaric is an excreſcence found upon the trunks and large branches of ſeveral trees, but chiefly upon the larch, and ſome oaks. It is of two ſorts, the male and female; the former is yellow, hard and woody, and uſed for dying black; the latter is covered with a yellow bark, and white within: it taſtes ſweet at firſt, but becomes bitter after being held a ſhort time in the mouth. This is the ſort uſed in medicine. It is adminiſtered in infuſion, from two drams to half an ounce, and in ſubſtance from one to two drams. Being a very ſtrong purgative, it ought to be corrected with ginger, cloves, cinnamon, mace, mint, or ſome fixed ſalt. The troches prepared of agaric and ginger are commonly preſcribed in inveterate diſorders and obſtructions of the bowels from half a dram to one dram. From agaric is likewiſe drawn an extract and a roſin. It enters into ſeveral purgative compoſitions, particularly the confection of hamech, hiera picra, the bleſſed extract, and pills of euphorbium.

Jew's ears, the peziza auriculam referens of Ray and Caſpar Bauhin, is a fungous excreſcence reſembling an ear, found on the ſtumps of elder-trees, before their leaves appear. It is in great eſteem among the common people as a remedy for ſore throats, but is ſeldom found in the ſhops.

The powder, which is found in the cavity of ſome ſpecies of lycoperdon after burſting, is a very powerful aſtringent: and, mixed with the white of an egg, is effectual in ſtopping all ſorts of hæmorrhages.

FURCÆ, Forks: a ſpecies of armature or offenſive weapon, with which ſome plants are furniſhed. They are of the nature of prickles, being, like them, detached from

the

the bark or outer rind only, and conſiſt of two or three prongs. The term is exemplified in berberry, currant-tree, triple-thorned acacia, hard ſeeded chryſanthemum, black horehound, barleria, *fagonia*, and garden burnet.

G.

GALEA *Corollæ ringentis*, the helmet or upper lip of a grinning or gaping flower. The term was invented by Rivinus, and ſtands oppoſed to *barba-ringentis*, the beard or lower lip.

GEMMA, a bud, a compendium of a plant ſeated upon the ſtem and branches, and covered with ſcales, in order to defend the tender rudiments incloſed from cold and other external injuries, till their parts being unfolded, they acquire ſtrength, and render any further protection unneceſſary.

Buds, together with bulbs, which are a ſpecies of buds generally ſeated upon or near the root, conſtitute that part of the herb by Linnæus called *Hybernacula*; that is, the winter quarters of the future vegetable—a very proper appellation, as it is during that ſevere ſeaſon that the tender rudiments are protected in the manner juſt mentioned. *Vide* BULBUS.

Plants, conſidered in analogy to animals, may properly enough be reckoned both viviparous and oviparous. Seeds are the vegetable eggs; buds, living fœtuſes, or infant plants, which renew the ſpecies as certainly as the ſeed.

Mr. Ray was the firſt who gave the name of *gemma* to the bud, which had formerly been denominated *germen*. *Gemma*, indeed, was uſed to ſignify one kind of bud, that containing the flower, which we now denominate *oculus*, an eye; but was by the ancients carefully diſtinguiſhed from the *germen*, or bud containing the leaves and wood, hence termed by the French, *bouton à bois*.

Pliny marks this diſtinction in the following words. "Germen autem eſt id quod ex ipſis ſurculis arborum primo

primo vere exit, ex quo deinde folium producitur: nam gemma proprie eſt floris, quanquam utrumque confundatur." Notwithſtanding this obvious remark of Pliny, the modern botaniſts, after the example of Ray, have applied the term *gemma* to every kind of bud, whether of the flowers or leaves; the other term *germen* being appropriated to the ſeed-bud, or that part of the flower which ſwells and becomes the ſeed-veſſel vulgarly termed the fruit.

With reſpect to its external form or figure, a bud is a ſmall rounded body, ſometimes ending in a point. In the different ſpecies, however, of the ſame genus, the form of the buds is ſo different, as frequently to afford an excellent mark of diſtinction during the winter. This is particularly exemplified in many ſpecies of willow and buckthorn, eſpecially the former.

Buds are placed at the extremity of the young ſhoots, and along the branches, being fixed by a ſhort foot-ſtalk upon a kind of brackets, the remainder of the leaves in the wings or angles of which the buds in queſtion were formed the preceding year. They are ſometimes placed ſingle; ſometimes two by two, and thoſe either oppoſite or alternate; ſometimes collected in greater numbers in whirls or rings.

With reſpect to their conſtruction, buds are compoſed of ſeveral parts artificially arranged. Externally, we find a number of ſcales that are pretty hard, frequently armed with hairs, hollowed like a ſpoon, and placed over one another like tiles. Theſe ſcales are fixed into the inner plates of the bark, of which they appear to be a prolongation. Their uſe is to defend the internal parts of the bud, which, being unfolded, will produce, ſome, flowers, leaves, and ſtipulæ; others, foot-ſtalks and ſcales. All theſe parts, while they remain in the bud, are tender, delicate, folded over one another, and covered with a thick clammy juice, which is ſometimes reſinous and odoriferous, as in the tacahamac-tree. The external ſcales fall off after the entire expanſion of the internal parts.

In general, we may diſtinguiſh three kinds of buds: that

containing the flower, that containing the leaves, and that containing both flower and leaves.

The firſt, termed *gemma florifera*, and by the French, *bouton a fleur ou au fruit*, contains the rudiments of one or ſeveral flowers folded over one another, and ſurrounded with ſcales. In ſeveral trees, this kind of bud is commonly found at the extremity of certain ſmall branches which are ſhorter, rougher, and leſs garniſhed with leaves than the reſt. The external ſcales of this ſpecies of bud are harder than the internal; both are furniſhed with hairs, and in general, more ſwelled than thoſe of the ſecond ſort. The bud containing the flower, too, is commonly thicker, ſhorter, almoſt ſquare, leſs uniform, and leſs pointed, being generally terminated obtuſely. It is called by Pliny *oculus gemma*, and is employed in that ſpecies of grafting called inoculation or budding.

The ſecond ſpecies of bud, (that containing the leaves, termed *Gemma foliifera*, and by the French, *Bouton a feuilles ou a bois*,) contains the rudiments of ſeveral leaves which are variouſly folded over one another, and outwardly ſurrounded by ſcales, from which the ſmall ſtipulæ that are ſeated at the foot of the young branches, are chiefly produced. Theſe buds are commonly more pointed than the former ſort. In the hazel-nut, however, they are perfectly round; and in horſe-cheſnut very thick.

The curious and various ways in which the leaves are folded up in this kind of bud, are particularly enumerated under the article VERNATIO, which ſee.

The third ſort of bud is ſmaller than either of the preceding, and produces both flowers and leaves, though not always in the ſame manner.

Sometimes the flowers and leaves are unfolded at the ſame time. This mode of the flower-and-leaf-bud, is termed by Linnæus, *gemma foliifera & florifera*, and admits of the following diſtinctions from the ſex of the flowers ſo produced with the leaves: male-flower and leaf-buds, as in the pine and fir-tree: female-flower and leaf-buds, as in hazel-nut and horn-beam: hermaphrodite-flower and leaf-buds, as in the elm-tree, cornel-tree, mezereon, and almond tree.

Sometimes the leaves emerge out of this kind of bud upon a ſmall branch, which afterwards produces flowers. This mode of the flower-and-leaf-bud, is termed by Linnæus, *gemma foliifero-florifera*, and is the moſt common bud of any.

Such buds as produce branches adorned only with leaves, are called barren; ſuch as contain both leaves and flowers, fertile: the varieties of the laſt have been juſt ſpecified. From the bulk of the bud we may often, with eaſe, foretel whether it contains leaves only, or leaves and flowers together, as in cherry and pear-tree.

The ſcales which envelop the bud, conſiſt chiefly of a cuticle or ſcarf-ſkin, and a parenchyma or medullary pulpy part. They are, as we have ſaid, for the moſt part, hairy, particularly in the margin; and the internal ſurface is covered with a ſlight down, in the ſame way as the leaves contained or folded up in the bud.

The thick clammy juice, which oozes from the ſcales and leaves of the bud, ſerves not only to defend the more tender parts of the embryo-plant from cold, the aſſaults of inſects, and other external injuries; but likewiſe from exceſſive perſpiration, which, in its young and infant ſtate, would be very deſtructive. This is conſpicuous in the buds of horſe-cheſnut, poplar, and willow-trees.

Neither the buds produced on or near the root, called by ſome authors turiones, nor thoſe produced on the trunk, and from the angles or wings of the leaves, contain, in ſtrict propriety, an entire delineation of the plant, ſince the roots are wanting: and in various buds, as we have ſeen, ſhoots are contained with leaves only, and not with flowers: but as a branch may be conſidered as a part ſimilar to the whole plant, and if planted, would, in proceſs of vegetation, produce roots and flowers, we may, in general, allow that the bud contains the whole plant, or the principles of the whole plant, and thus reſembles the ſeed, in containing a delineation of the future plant in embryo: for although the bud wants a *roſtellum* or radicle, of which the ſeed is poſſeſſed, yet it would undoubtedly form one, if planted in the

earth. But as the medullary part adhering to the bud is too tender, and by the abundance of juice flowing into it from the earth, would be diſpoſed to putrefaction, the buds are not planted in the ſoil, but generally inſerted within the bark of another tree; yet ſo placed that the production of the marrow or pith adhering to them, may be inſerted into the pith of the branch in which the fiſſure or cleft is made; by which means there is a large communication of juice. This propagation by gems or buds, called inoculation, is commonly practiſed with the firſt ſort of buds above deſcribed.

From the obvious uſes of the buds, we may collect the reaſon why the ſupreme Author of Nature has granted this ſort of protection to moſt of the trees that are natives of cold climates: and, on the other hand, denied it to ſuch as, enjoying a warm benign atmoſphere, have not the tender parts of their embryo-ſhoots expoſed to injuries and depredations from the ſeverities of the weather. Of this latter kind are the plants of the following liſt, ſome of them very large trees; others, ſmaller woody vegetables, of the ſhrub and under-ſhrub kind:—Citron, orange, lemon, caſſava, mock-orange, blad-apple, ſhrubby ſwallow-wort, alaternus, ſhrubby geraniums, berry-bearing alder, Chriſt's thorn, Syrian mallow, baobab, or Æthiopian ſour-gourd, juſticia, wild ſenna, the acacias and ſenſitive plant, coral-tree, ſtinking bean-trefoil, medicago, oleander, viburnum, ſumach, ivy, tamariſk, heath, Barbadoes cherry, lavatera, rue, ſhrubby night-ſhades, Guinea henweed, cypreſs, lignum vitæ and ſavine a ſpecies of juniper.

On annual plants, whoſe root, as well as ſtalk, periſhes after a year, true buds are never produced; in their ſtead, however, are protruded ſmall branches like a little feather, from the wings of the leaves, which wither without any further expanſion, if the plants climb, and have no lateral branches; but if, either by their own nature, or from abundance of ſap, the plants become branched, the ramuli juſt mentioned obtain an increaſe ſimilar to that of the whole plant.

The ſame appearance obtains in the trees of warm countries, ſuch as thoſe enumerated in the above liſt, in which a plumula, or ſmall feather, ſends forth branches without a ſcaly covering, as in ſuch countries, this tender part requires no defence or protection from cold. A ſcaly covering then is peculiar to buds, as it protects the tender embryo encloſed from all external injuries. When we ſpeak, therefore, of trees having buds that are naked or without ſcales, our meaning is the ſame as if we had ſaid, that they have no buds at all.

Ray and Pontedera have inſtituted a diviſion of vegetables into herbs and trees from the buds. The former they have diſtinguiſhed by the name of plants wanting buds; the latter by that of plants bearing buds.

This diviſion, however, is certainly erroneous; moſt trees of warm climates being, as we have already ſhewn, devoid of buds, at leaſt of that ſcaly appearance which ſeems eſſential to every bud.

The buds that are to be unfolded the following year, break forth from the evolved buds of the preſent year, in ſuch a manner, as to put on the appearance of ſmall eminences in the wings or angles of the leaves. Theſe eminences or knots grow but little during the ſummer, as, in that ſeaſon, the ſap is expended on the increaſe of the parts of the plant: but in autumn, when the leaves begin to wither and fall off, the buds, placed on the wings, increaſe; and the embryo-plant contained in the bud, is ſo expanded, that the leaves and flowers, the parts to be evolved the following year, are diſtinctly viſible. Thus in horſe-cheſnut, the leaves, and in cornel-tree, the flowers, are each to be obſerved in their reſpective buds.

As each bud contains the rudiments of a plant, and would, if ſeparated from its parent-vegetable, become every way ſimilar to it, Linnæus, to ſhew the wondrous fertility of nature, has made a calculation by which it appears, that, in a trunk ſcarce exceeding a ſpan in breadth, ten thouſand buds (that is, herbs) may be produced. What an infinite

number then of plants might be raiſed from a very large tree!

GEMMATIO, from *gemma*, a bud; a term uſed by Linnæus expreſſive of the form of the buds, their origin, and their contents. It includes both thoſe properly called buds, and thoſe which are ſeated upon the roots, ſtiled bulbs.

As to the origin of buds, they are formed either of the foot-ſtalks of the leaves, of *ſtipulæ*, or of ſcales of the bark. Their contents have been already diſcovered, in the preceding article, to be either flowers, leaves, or both. *Vide ſupra.*

GENERATIO. *Vide* SEXUS.

GENITALIA. By this appellation Linnæus and the ſexualiſts denominate the *anthers* and *ſtigma* of the flowers; the firſt, in their judgment, performing the function of the male organ of generation in plants, the other, of the female. *Vide* SEXUS.

GENITURA, the generating ſubſtance of plants. By this name, Linnæus, in his fancied analogy betwixt vegetables and animals, diſtinguiſhes, from its ſuppoſed uſe, the *pollen*, that fine powder or duſt, which, when ripe, is diſcharged by the *anthers* or tops of the ſtamina, and falls upon the *ſtigma*, for the purpoſe of impregnation. *Vide* POLLEN.

GENUS, a race or kind; one of the five members or parts into which every ſyſtem or regular method of arrangement reſolves itſelf.

A genus is an aſſemblage of ſeveral ſpecies; that is, of ſeveral plants which reſemble one another in their moſt eſſential parts. Hence it is aptly enough compared to a family, all the relations of which bear the ſame ſirname, although every individual is diſtinguiſhed by a particular ſpecific name.

The eſtabliſhment of genera renders botany more ſimple and eaſy, by abridging the number of names, and arranging under one denomination, termed the generic name, ſeve-

ral

ral plants, which, though different in many other reſpects, are found invariably to poſſeſs certain relations in thoſe eſſential parts, the flower and fruit. Plants of this kind are termed by botaniſts *plantæ congeneres*, that is, plants of the ſame genus.

The works of Theophraſtus, Dioſcorides, Pliny and Galen, leave us no room to doubt that the antients had ſome knowledge of plants: but they as certainly convince us, that their knowledge was extremely limited, and very ſuperficial. In the ages which immediately ſucceeded that of Pliny, little or nothing was done to enrich the ſcience of plants. At length, all Europe was plunged in ignorance, and Botany lay neglected with every other uſeful art. On the revival of learning in the fifteenth century, men were ſolely devoted to the ſtudy of the ancients, in order to recover that knowledge which had been ſo long buried in obſcurity. Botaniſts, therefore, if any there were, ſearched for plants in the books of the Greeks and Romans. In the ſequel, however, they perceived the imperfection and impropriety of ſuch a mode of ſtudy. The wide book of Nature lay open before them, and ſolicited their attention. They ſought for plants in the fields. Botany ſoon wore a more agreeable aſpect, and numbers of plants were daily added to the ſcanty original liſt. Theſe quickly pointed out the neceſſity of having recourſe to an arrangement, and diviſions determined by accurate and diſtinct characters. Methods were invented, and theſe in progreſs of time ſubdivided into claſſes, genera and ſpecies.

Genera, then, no more than Methods, ſeem to have been known to the ancients, in the ſenſe in which that term is now generally underſtood. Every ſpecies with them was a genus; and they had no conception of giving a common name to a great number of plants which they could not diſcover poſſeſſed any thing in common: for the reader will obſerve that the minute parts of the fructification which lay the foundation of moſt of our boaſted ſyſtems, were then but little known, and leſs attended to. In fact, the port or habit of plants, their duration, place of growth, time of flowering,

and their uſes both medicinal and œconomical, formerly furniſhed the ſole charecters of diſtinction. Conrad Geſner was the firſt, who, in 1559, ſuggeſted a diſtinction of plants into genera and ſpecies. In his letters to Fabricius, inſerted in the third book of his Collection, are the following paſſages, which may be reckoned deciſive on this head. "Generis unius polii ſpecies duæ ſunt. Novi et alias duas oreoſelini ſpecies. Exiſtimandum eſt autem nullas propemodum herbas eſſe quæ non GENUS aliquod conſtituant, in duas aut plures ſpecies diverſas dividendum. Gentianam unam priſci deſcribunt, mihi decem aut plures ſpecies notæ ſunt." Again, in a letter, dated 1559, he ſays, "Montana vero illa berba, flore quidem doronici, ſed foliis plantaginis, radice aromaticâ, ſui omnino GENERIS eſt. Oblectavit me etiam rarum illud piloſellæ GENUS." And again, "Mihi rara eſt etiam arthriticæ illa ſpecies——Miſiſti cum reliquis ſpeciem aquifoliæ nullis per marginem foliorum ſpinis præterquam in mucrone——Lunariam græcam quam phlitteren appellant multam jam hic habemus, ſed floribus inodoris: quibus odoratis, GENUS alterum reperiri audio hactenus mihi non viſum." Columna, who was poſterior to Geſner, entertained the ſame idea reſpecting the diſtribution into genera and ſpecies: as did likewiſe Joachim Jungius, who died in 1657, in whoſe poſthumous works, publiſhed in 1679, under the title of Iſagoge Phytoſcopica, is the following paſſage: "Plantæ, niſi certo in GENERA & SPECIES conſtanti ratione, non pro lubitu hujus vel illius, redigantur, infinitum quaſi reddetur Phytoſcopiæ ſtudium; intellectus autem humanus infinitum fugit.——Ordo autem claſſium, generum, ſpecierum, terminum infinitis pronit."

This doctrine of Conrad Geſner, Columna and Jungius was adopted by ſucceeding botaniſts, from Cluſius who was contemporary with them, to J. Bauhin. They arranged ſeveral ſpecies of plants under the ſame generic name, as iris, narciſſus, or willow: but the genera were ſtill vague and undetermined.

In 1655, Moriſon attempted to eſtabliſh the genera on a certain foundation, as did likewiſe the celebrated Ray in 1682,

1682, and Rivinus in 1690. The characters, however, which they aſſigned, were far from being ſatisfactory or ſufficient: and Ray himſelf was ſo ſenſible of their defects, that he afterwards changed his for thoſe of Tournefort.

This illuſtrious botaniſt was the firſt who, in 1694, propoſed a ſatisfactory diſtribution of the genera, founded on the parts of the fructification, and determined by fixed and preciſe characters common to ſeveral ſpecies of plants. A genus of plants, as defined by Tournefort, is an aſſemblage of ſeveral ſpecies which agree in all the parts of fructification or the moſt eſſential. This is properly what Tournefort calls a primary genus, or genus of the firſt order. His Secondary Genera will be explained below.

The rules eſtabliſhed on this ſubject by the French botaniſt, are as follow.

I. The parts of fructification, when preſent in plants, are ſolely to be employed as characteriſtical marks in diſcriminating the genera, if found ſufficient for that purpoſe.

II. If theſe marks are found inſufficient, recourſe muſt be had to other parts leſs eſſential—as the roots, ſtems, bark, and number of leaves; to the ſenſible qualities of plants, as their colour and taſte; or to their port and external habit.

III. With reſpect to plants in which the parts of the flower and fruit are wanting, or not to be diſcovered without the aſſiſtance of glaſſes, the genus is to be fixed from the moſt remarkable of the characters mentioned in the laſt paragraph.

IV. All ſuperfluous marks are to be rejected.

V. A greater ſhare of attention is to be paid to the general habit of plants, than to the particular varieties, which can only be diſcovered by nice and minute obſervation. Thus, although the large common trefoil, and ſome other flowers of the ſame genus, are only furniſhed with one petal, they are by no means to be ſeparated from the other ſpecies, which, like moſt pea-bloom flowers, have four irregular petals; becauſe they agree with them in more ſtriking characters. Some ſyſtematic writers, however, have been abſurd enough to advance, that a difference in the number of

petals

petals and ſeeds, is a ſufficient foundation for forming different genera from plants otherwiſe very nearly allied; and, in ſhort, that a flower having only one petal or one ſeed, can never be referred to the ſame genus with a flower having two, three, four, or more petals or ſeeds. The abſurdity of this doctrine appears from hence, that, were the rule in queſtion to be ſtrictly followed, we ſhould ſometimes refer to different genera, different individuals of the ſame ſpecies. From the ſeed of papaw, are produced both male and female plants, that is, plants which have male and female flower; on diſtinct roots. The male flowers have always one petal, the female five. The ſame thing obtains in the male and female flowers of caſſada, which indeed are not placed on diſtinct roots as the former, but ſtand apart within different covers on the ſame plant.

Theſe rules, which are delivered and illuſtrated at great length in the Preface to the Inſtitutions, led the author to diſtinguiſh two ſorts of genera, under the appellations of genera of the firſt order, and genera of the ſecond. The genera of the firſt order are ſuch as Nature herſelf appears to have inſtituted, and accurately diſtinguiſhed by the flower and fruit; ſuch are violet, ranunculus, aconite, paſſion-flower, and ſeveral others. Theſe are the only genera which Linnæus admits: or, to ſpeak more properly, all the genera of plants are, by this author, rendered primary, whether the characters derived from the parts of the flower and fruit are ſufficient for the purpoſe of diſcrimination, or not.

The genera of the ſecond order are thoſe, for the diſtinction of which we muſt have recourſe, not only to the fructification, but to parts that are unconnected with the flower and fruit, by reaſon of the inſufficiency of theſe laſt to diſcriminate the genera of themſelves.

Thus, according to Tournefort, germander forms a genus different from poley mountain, *teucrium* and ground pine, on account of its hollow *calyx*, and the diſpoſition of its flowers in the wings or angles of the leaves.—Poley mountain is diſtinguiſhed from *teucrium*, ground-pine and germander, by its flowers, which are collected in a head or round ſpike:

teucrium

teucrium from the three others by its bell-ſhaped *calyx*; and ground-pine by the diſpoſition of its flowers, which proceed ſingly from the wings of the leaves, and not in whirls or rings, as in germander.

Theſe ſecondary genera, which Tournefort uſes but rarely, are entirely rejected by Linnæus, who has eſtabliſhed as a principle in no caſe to be departed from, that the *generic* characters are to be derived from all the parts of fructification, and none other. A total revolution of the genera muſt evidently be the conſequence of a rigid obſervance of this principle: and in fact, not the ſecondary genera of Tournefort only, but many of his primary genera which were eſtabliſhed upon the ſame principle, have felt the effects of this undiſtinguiſhing ſeverity. Linnæus's genera, then, contain a deſcription of each particular part of fructification, its various relations, and different modes with reſpect to number, figure, ſituation, and proportion.

Thus, all the different ſpecies of *calyx*, *corolla*, *nectarium*, *ſtamina*, *&c.* conſidered with reſpect to the four attributes juſt mentioned, furniſh the obſerver with ſo many ſenſible and eſſential characters.

Theſe characters the author denominates the letters or alphabet of botany. By ſtudying, comparing, and, as it were, ſpelling theſe letters, the ſtudent in botany comes, at length, to read and underſtand the generical characters which the great Creator has originally imprinted upon vegetables: for the genera and ſpecies, according to Linnæus, are ſolely the work of Nature; whilſt the claſſes and orders are a combination of nature and art.

Upon theſe principles, Linnæus, in his *Genera Plantarum*, determines the generical characters of all the plants there deſcribed.—His method will be beſt illuſtrated by an example.

NARCISSUS.

CALYX—A *ſpatha* or ſheath, which is oblong, obtuſe, compreſſed, tears open on the ſide, and withers upon the plant.

COROLLA.

COROLLA—Six *petals*, or rather one *petal* cut almoſt to the bottom into ſix parts, which are oval, terminated in a point, flat, and inſerted externally above the baſe of the tube of the *nectarium*, which is ſituated in the middle of the flower, bell or funnel-ſhaped, and commonly called the cup.

STAMINA—Six awl-ſhaped *filaments*, ſhorter than the *nectarium* and attached to its tube—The *anthers* or *ſummits* oblong.

PISTILLUM—The *ſeed-bud* roundiſh, obtuſely triangular and placed under the receptacle of the flower. The *ſtyle* thread-ſhaped, and longer than the *ſtamina*.—The *ſtigma* or *ſummit of the ſtyle* divided into three parts, hollow and blunt.

SEED-VESSEL—A *capſule* that is roundiſh, obtuſely three cornered, having three external openings or valves, and the ſame number of internal diviſions or cells.

SEEDS—Numerous, globular, and furniſhed with an appendage or border. The *receptacle* to which they are fixed is ſhaped like a pillar.

By this manner of deſcribing all the parts of the fructification, almoſt innumerable combinations are produced of the botanical letters; I mean the generical characters of plants are multiplied, and furniſh an amazing diverſity of relations.

Some characters are common to ſeveral genera, independently of thoſe which conſtitute the claſs and order. Thus ſnow-drop, greater ſnow-drop, and ſea-daffodil, which belong to the ſame claſs and order with narciſſus, agree with it not only in the number of the *ſtamina* and ſtyles which, in the ſexual ſyſtem, lay the foundation of the two primary diviſions, but likewiſe in the form and nature of the *calyx*, which, in all theſe genera, is a *ſpatha* or ſheath. By comparing the other characters, we diſcover, in like manner, thoſe which are ſimilar, and thoſe which are diſtinctive. Thus, in greater ſnow-drop, the diſtinctive character is the bell-ſhaped petal: in ſnow-drop, the *galanthus* of Linnæus, the three-leaved *nectarium*; and in ſea-daffodil, the *nectarium* divided into twelve parts.

It is, as we have ſaid, in the *Genera Plantarum*, that theſe full deſcriptions of all the parts of fructification are to be found. In the *Syſtema Naturæ*, another work of the ſame author, thoſe characters that are common to all the genera of the ſame claſs and order are omitted, and the diſtinctive characters or generic differences alone are mentioned.—Tournefort, knowing his method to be artificial, did not pretend to aſſert that his genera were otherwiſe. Linnæus, however, we have ſeen, has carried his pretenſions further, and affirms that all genera as well as ſpecies are natural. What ſeems to favour this aſſertion is the ſtriking appearance of the flowers of certain genera, as ranunculus, violet, aconite, fennel-flower, ſyrian-mallow, paſſion-flower, and ſeveral others which have eſſential and uniform characters, that, at firſt ſight, ſeem to entitle them to the appellation of natural genera. But to this it may be anſwered, that for the comparatively ſmall number of genera which have ſtriking diſtinctive characters of this kind, there are many, particularly in ſome natural families, as the umbelliferous plants, lipped, croſs-ſhaped, and pea-bloom flowers, in which the characters in queſtion are ſo little conſpicuous, and the plants ſo remarkably ſimilar, that one is frequently tempted to make but a ſingle genus of each of theſe families.

Linnæus has deſcribed about twelve hundred and thirty-nine genera, that is, upwards of five hundred more than Tournefort, the number of whoſe genera amounts, I think, to ſix hundred and ninety-eight. We muſt obſerve, however, that the former frequently incorporates ſeveral genera which had been divided by the latter. Such, for inſtance, are germander, teucrium, mountain-poley, and ground pine, which the French botaniſt has diſtinguiſhed, as was obſerved above, into ſo many genera of the ſecond order, by characters independent of the fructification. Linnæus, however, employing theſe characters only for diſtinguiſhing the ſpecies, and finding eſſential relations to ſubſiſt betwixt the parts of fructification of the Tournefortian genera in queſtion, collects them all under one head; ſo that inſtead of

four

four diſtinct genera, they become as many ſpecies of the ſame genus.

Beſides the ſix hundred and ninety-eight genera of Tournefort, Linnæus's books contain ſeveral new genera of other botaniſts, who lived poſterior to Tournefort. The moſt remarkable of theſe are, Father Plumier, who eſtabliſhed about ninety-ſix genera of American plants; Boerhaave, who deſcribed ſeventeen new genera; Vaillant, thirty; Dillenius, ſixty-ſeven; Micheli, twenty-ſeven; Houſton, fifteen; Petit, Meſſieurs de Juſſieu, Niſſole, Marchant, Danti, Reneaume, Ruppius, Pontedera, Scheuchzer, Buxbaum, Ammannus, Haller, Gmelin, Monti, Gronovius, Mitchel, Cateſby, Kæmpfer, &c. have publiſhed in all about fifty new genera. The remaining genera, to the number of two hundred and upwards, are publiſhed by Linnæus himſelf.

I conclude this article with a few aphoriſms reſpecting the genera of plants as laid down by Linnæus in his Philoſophia Botanica.

I. There are few genera in which all the parts of fructification are conſtant throughout the ſpecies.

To this inconſtancy is owing the great number of fictitious or ſpurious genera in Tournefort and other authors: for although ſuch varieties afford excellent ſpecific diſtinctions, they are not ſtriking enough to conſtitute real ſcientific genera. The author very pertinently adds, if genera were to be multiplied in this manner without any neceſſity, we ſhould ſoon have as many genera as ſpecies, and the ſcience of botany, as far as it reſpects arrangement, be at an end.

II. If an unneceſſary multiplication of the genera is to be avoided on the one hand, an unneceſſary reduction of them is no leſs to be ſhunned on the other. From the affinity of ſome genera to claſſes and orders, we frequently incur the danger of throwing all into confuſion, by reducing under one genus a whole natural aſſemblage or family. Some of the natural orders whoſe plants have a very ſimilar appearance, were enumerated above. Many plants of the mallow tribe,

tribe, as mallow, marſh-mallow, holly-hock, lavatera, urena, and Syrian mallow, are of the ſame kind.

The following parcels of genera, which belong to other natural orders, are very ſimilar in their appearance, and might each, by an inaccurate obſerver, be confounded under one genus.

Houſe-leek, leſſer houſe-leek, navel-wort, leſſer orpine, and tillæa.

Torch-thiſtle, fig-marigold, aizoon, and tetragonia.

Campion, wild lychnis or agroſtemma, viſcous campion, carnation, ſoapwort, ceraſtium, ſpurrey, ſandwort, moerhingia, and ſagina.

In this manner, ſeveral natural orders might each be reduced to a ſingle genus, and thus the ſcience be as effectually deſtroyed by the enormous ſize of the genera, as formerly by the unneceſſary multiplication of their number.

III. A genus may conſiſt of one ſpecies only, although it is moſt commonly compoſed of a greater number.

The following genera, among many others, conſiſt of only one ſpecies:

Graſs of Parnaſſus, tamarind, baſtard cumin, ſand-box-tree, barren-wort, horn-of-plenty-graſs, ſuperb lily, water-leaf, neurada, calligonum, African fly-honey-ſuckle, leaſt water-plantain, corymbium, caſhew-nut, coris, nepenthes, hop, flowering-ruſh, baſtard-indigo, mangoſtan and orvala.

Other genera, as the following, conſiſt of a great number of ſpecies:

Fig-marigold, leſſer houſe-leek, bind-weed, ſaxifrage, acacia, calves-ſnout, milk-wort, aſter, carex, burning thorny plant, geranium, campanula, viſcous campion, wild ſenna, St. John's wort, kidney-bean, cud-weed, willow, fig-tree, French honey-ſuckle, hemp-agrimony, aloe, aſtragalus, blue-bottle, Syrian mallow, wild orach, flax, ranunculus, gentian, night-ſhade, thrift, heath, garlick, ox-eye, and cinquefoil.

IV. In many genera, ſome ſtriking or eſſential mark of fructification is obſerved.

Thus the eſſence of ranunculus conſiſts in its nectarium,

which

which is a ſmall prominence in the claw of each petal: that of ſelf-heal, torenia, eye-bright, mad-wort, and ſea-cabbage, in the denticuli or ſmall teeth with which the ſtamina are furniſhed: that of martynia, turmeric, bignonia, and chelone, in a pointed body which is placed within the ſtamina, and reſembles a filament without its anther: that of hellebore and fennel-flower, in its numerous hollow *nectaria:* that of water-leaf, in its cloſed chinks, (*rimæ clauſæ*) within the diviſions of the petal: that of henbane, in the covering of its ſeed-veſſel, by which it is diſtinguiſhed from alkekengi: that of ſea-daffodil, in the inſertion of its ſtamina into the upper part of the nectarium, by which it is diſtinguiſhed from narciſſus, where the ſtamina are placed within the nectarium, and affixed to its tube: that of baſtard-rocket, and bell-flower, in their nectarium: laſtly, that of iris, in its ſingular *ſtigma*, which reſembles three petals, or leaves.

V. The ſtriking or ſingular characteriſtical mark of every genus muſt run through all the ſpecies. Without a ſtrict attention to this rule, we might be apt to confound genera that ſhould be diſtinguiſhed. It was for want of this caution that aloe and American aloe were formerly incorporated into one genus; as were likewiſe ranunculus and adonis, andromeda and heath.

Aloe is now ſeparated from American aloe, (*Agāvæ*) becauſe its ſtamina are inſerted, not into the petals, but into the common receptacle; adonis from ranunculus, becauſe it wants the prominence in the claw of the petal, which is the diſtinguiſhing mark of the latter; andromeda from heath, becauſe of the two horns of the anthers, which are more conſpicuous in the latter than the former.

VI. Plants which are of the ſame genus, poſſeſs like medicinal powers. The truth of this aphoriſm will be beſt illuſtrated by attending to the following liſt of *congeneres*.

Scammony, turbith, jalap, and ſea bind-weed belong to the genus *convolvulus*.

Moly, leek, onion, and garlick, belong to the genus *allium*.

Cinnamon, camphire, benjamin-tree, ſaſſafras, and avocado pear, belong to the genus *laurus*.

Southernwood and wormwood belong to the genus *artemiſia*.

GENUS *ſummum*, a termed uſed by Rivinus and Ray, ſynonymous to CLASSIS in Linnæus, and ORDO in Tournefort.

GENUS *ſubalternum*, another term uſed by the ſame botaniſts, ſynonymous to ORDO in Linnæus, and SECTIO in Tournefort.

GERMEN, the ſeed bud; defined by Linnæus to be the baſe of the piſtillum, which contains the rudiments of the ſeed, and, in progreſs of vegetation, ſwells and becomes the ſeed-veſſel.

When the ſeed-bud is placed above the receptacle, or, in other words, within the cover or covers of the flower, it is termed *germen ſuperum*; when ſituated below the receptacle, or under the calyx, *germen inferum*. The former, which correſponds to *flos inferus*, is exemplified in ſumach, *hippuris*, *wachendorfia*, *commelina*, *xyris*, and the graſſes;—the latter, ſynonymous with *flos ſuperus*, in valerian, iris, *gladiolus*, epilobium, œnothera, viburnum, elder, and the umbelliferous and cucurbitaceous plants.

In aſſimilating the vegetable and animal kingdoms, Linnæus denominates the ſeed-bud the *ovarium* or *uterus* of plants, and affirms its exiſtence to be chiefly at the time of the diſperſion of the male-duſt by the anthers; as, after its impregnation, it becomes a ſeed-veſſel.

GERMEN, by Pliny and the ancient botaniſts, is uſed to ſignify a bud containing the rudiments of the leaves. *Vide* GEMMA.

GERMINATIO, comprehends the preciſe time which the ſeeds take to riſe after they have been committed to the ſoil.

The different ſpecies of ſeeds take longer or ſhorter time in riſing, according to the degree of heat which is proper for each. Millet, wheat, and ſeveral of the graſſes, riſe in one day; blite, ſpinach, bean, muſtard, kidney-bean, turnip, and rocket, in three days; lettuce and dill, in four; cucumber, gourd, melon, and creſs, in five; radiſh and

beet, in ſix; barley, in ſeven; orach, in eight; purſlane, in nine; cabbage, in ten; hyſſop, in thirty; parſley, in forty or fifty days; peach, almond, walnut, cheſnut, pæony, horned poppy, hypecoum, and ranunculus falcatus, in one year; roſe-buſh, cornel-tree, hawthorn, medlar, and hazel-nut, in two. The ſeeds of ſome ſpecies of orchis, and of ſome liliaceous plants, never riſe at all. Of ſeeds, ſome require to be ſowed almoſt as ſoon as they are ripe, as otherwiſe they will not germinate. Of this kind are the ſeeds of coffee and fraxinella. Others, particularly thoſe of the pea-bloom flowers, preſerve their germinating faculty for a ſeries of years.—M. Adanſon aſſerts, that the ſenſitive plant retains that virtue for thirty or forty years.

Air and water are the agents of germination. The humidity of the air alone makes ſeveral ſeeds to riſe that are expoſed to it. Seeds too are obſerved to riſe in water, without the intervention of earth: but water, without air, is inſufficient.—Mr. Homberg's experiments on this head are deciſive. He put ſeveral ſeeds under the exhauſted receiver of an air-pump, with a view to eſtabliſh ſomething certain on the cauſes of germination. Some of them did not riſe at all; and the greater part of thoſe which did, made very weak and feeble productions.

Thus it is for want of air, that ſeeds which are buried at a very great depth in the earth, either thrive but indifferently, or do not riſe at all.

They frequently preſerve, however, their germinating virtue for many years, within the bowels of the earth; and it is not unuſual, upon a piece of ground being newly dug to a conſiderable depth, to obſerve it ſoon after covered with ſeveral plants, which had not been ſeen there in the memory of man.

Were this precaution frequently repeated, it would doubtleſs be the means of recovering certain ſpecies of plants which are regarded as loſt; or which, perhaps, never coming to the knowledge of botaniſts, might hence appear the reſult of a new creation.

Some

Some ſeeds require a greater quantity of air than others. Thus purſlane, which does not riſe till after lettuce in the free air, riſes before it in vacuo; and both proſper but little, or periſh altogether, whilſt creſſes vegetate as freely as in the open air.

GLANDULA, a ſpecies of ſecretory or excretory veſſel that is found on the ſurface of ſome plants.

Glands are ſeated either on the footſtalks, on different parts of the leaves, or on the tender ſtipulæ. They reſemble ſometimes a bliſter or bladder, as in St. John's wort; ſometimes a number of ſcales, as in fern; ſometimes ſeveral ſmall grains like millet, as in fir-tree; at other times a little cup, as in apricot-tree; ſometimes too they appear by a microſcope to be ſupported by footſtalks; and often to be ſeated upon the leaves without any footſtalk.

All theſe bodies appear to be produced by the ſwelling of ſome portion of the cellular or parenchymatous ſubſtance. From many of them oozes a viſcous liquor, which, drying upon the plant, forms a fine white powder, and a number of ſlender threads, that are frequently to be ſeen ſurrounding the glands in queſtion. Hence it has been concluded that they are the organs of ſome ſecretion; but it is not yet aſcertained, whether that is their ſole function.

In palma chriſti, caſſava, paſſion-flower, wild ſenna, and acacia, the glands are ſeated on the footſtalks.

In willow-tree they are placed on the indented or ſawed margin of the leaves: in almond-tree, gourd, heliocarpus, balſam, gelder-roſe, and bird-cherry, they proceed from the baſe of the leaf: in urena, tamariſk, and baſtard ricinus, from its back; in butter-wort and ſun-dew, from the upper ſurface.

In mountain ebony and apricot-tree, the glands are ſeated upon the tender ſtipulæ or ſcales which ſurround the young footſtalks of the flower and leaves.

The glands in currant-tree, a ſpecies of calve's ſnout, ceraſtium, fig-wort, and viſcous campion, are ſlender like hairs, and are hence denominated *glandulæ capillares*.

The pores or ſmall holes obſervable on the ſurface of ſome

plants, as tamariſk, and a ſpecies of viſcous campion, are reduced by Linnæus under the term *glandulæ* which we are now conſidering.

The glands furniſh excellent characteriſtical marks for diſcriminating the ſpecies of plants. Thus the almond-tree can ſcarce be diſtinguiſhed from the peach, but by its glands, which are ſeated at the baſe of the leaves, upon the ſerratures: whereas, in the peach-tree, there is no appearance of this kind. A ſpecies of convolvulus with a pimpled or knotty calyx, is ſo variable in the ſhape of the leaves, as to juſtify its diviſion into ſeveral ſpecies; yet it is kept entire by the conſtancy of the glands, which are placed upon the leaves. In a ſpecies of monarda, the petal is covered over with glands; an appearance which evidently diſtinguiſhes it from all the plants of the ſame genus.

The prickles of *bauhinia aculeata* are covered with glands of the ſame kind.

A glandular appearance is frequently to be obſerved betwixt the ſtamina of ſome plants, particularly in the croſs-ſhaped flowers, (*Tetradynamia*) in which Linnæus reckons it an eſſential claſſical character.

GLANDULATIO, from *glandula*, a term reſpecting the veſſels of ſecretion in plants, which are, by Linnæus, reckoned three: viz. GLANDULÆ, FOLLICULI and UTRICULI.

GLUMA, a huſk; the calyx of the graſſes, compoſed of one, two, or three valves, a kind of ſcales commonly tranſparent in the margin, and moſt frequently terminated by a pointed thread termed the *ariſta*, or beard. *Vide* GRAMINA *et* ARISTA.

GLUMOSUS *Flos*, a ſpecies of aggregate flower ſo called, which has a ſlender thread-ſhaped receptacle, along which are placed a number of florets or partial flowers; the baſe being furniſhed with a common huſky calyx, termed by Linnæus *glama*. Of this kind are bromus, feſcue graſs, oats, reed, poa, wheat, and other graſſes.

GLUMOSÆ, the name of a claſs in Linnæus's *Methodus Calycina* and Wachendorffius's Natural Method, conſiſting of

of plants which have that particular ſpecies of calyx called a gluma or huſk.—It contains all the natural order of the graſſes.

GLUTINOSITAS, from *gluten*, glue; a term occurring in the *Delineatio Plantæ* prefixed to the *Syſtema Naturæ*, and placed under the general head *pubes*; it ſeems to denote that ſtiff clammy matter which is ſometimes found on the ſurface of the leaves and ſtalks of plants.

GRAMINA, graſſes; one of the ſeven tribes or natural families, into which all vegetables are diſtributed by Linnæus in his *Philoſophia Botanica*. They are defined to be plants which have very ſimple leaves, a jointed ſtem, a huſky calyx termed *gluma*, and a ſingle ſeed. This deſcription includes the ſeveral ſorts of corn as well as graſſes. In Tournefort they conſtitute a part of the fifteenth claſs, termed *apetali*; and in Linnæus's Sexual Method, they are moſtly contained in the ſecond order of the third claſs, called *triandria digynia*.

This numerous and natural family of the graſſes, has engaged the attention and reſearches of ſeveral eminent botaniſts. The principal of theſe are, Ray, Monti, Micheli and Linnæus.

Giuſeppe Monti, in his Catalogus Stirpium agri Bononienſis, gramina ac hujuſmodi affinia complectens, printed at Bologna, in 1719, divides the graſſes from the diſpoſition of their flowers, as Theophraſtus and Ray had divided them before him, into three ſections or orders.——Theſe are,

SECTION I.

Graſſes having flowers collected in a ſpike.

SECTION II.

Graſſes having their flowers collected in a panicle or looſe ſpike.

SECTION III.

Plants that in their habit and external appearance are allied to the graſſes.

This claſs would have been natural, if the author had not

improperly introduced ſweet-ruſh, juncus, and arrow-headed graſs into the third ſection. Monti enumerates about 306 ſpecies of the graſſes, which he reduces under Tournefort's genera; to theſe he has added three new genera.

Scheuchzer, in his Agroſtographia, ſeu Graminum, Juncorum, Cyperorum et Cyperoidum iiſque affinium hiſtoria, publiſhed likewiſe in 1719, divides the graſſes, as Monti, from the diſpoſition of their flowers, into the five following ſections:

Section I.

Graſſes with flowers in a ſpike, as phalaris, anthoxanthum and frumentum.

Section II.

Irregular graſſes, as ſchœnanthus and cornucopiæ.

Section III.

Graſſes with flowers growing in a ſimple panicle or looſe ſpike, as reed and millet.

Section IV.

Graſſes with flowers growing in a compound panicle or diffuſed ſpike, as oats and poa.

Section V.

Plants by their habit nearly allied to the graſſes, as cypreſs-graſs, ſcirpus, linagroſtis, ruſh and ſcheuchzeria.

Scheuchzer has enumerated about four hundred ſpecies, which he deſcribes with amazing exactneſs.

Micheli has divided the graſſes into ſix ſections, which contain in all forty-four genera, and are arranged from the ſituation and number of the flowers.

Gramina. The name of the fourth order in Linnæus's Fragments of a Natural Method, conſiſting of the extenſive natural family of the graſſes.

List of Genera *contained in this Natural Order.*

SECTION I.

Grasses having Hermaphrodite Flowers.

Linnæan Genera.			*English Names.*
Agrostis,	—	—	Bent-Grass.
Aira,	—	—	Hair-Grass.
Alopecurus,	—	—	Fox-tail grass.
Anthoxanthum,	—	—	Vernal grass.
Aristida.			
Arundo,	—	—	Reed.
Avena,	—	—	Oats.
Bobartia.			
Briza,	—	—	Quaking grass.
Bromus,	—	—	Brome grass.
Cinna.			
Cornucopiæ,	—	—	Horn-of-plenty grass.
Cynosurus,	—	—	Dog's-tail grass.
Dactylis,	—	—	Cock's-foot grass.
Elymus.			
Festuca,	—	—	Fescue-grass.
Hordeum,	—	—	Barley.
Lagurus,	—	—	Hare's-tail grass.
Lolium,	—	—	Darnel.
Lygeum,	—	—	Hooded matweed.
Melica.			
Milium,	—	—	Millet.
Nardus.			
Oryza,	—	—	Rice.
Panicum,	—	—	Panic-grass.
Paspalum.			
Phalaris,	—	—	Canary-grass.
Phleum,	—	—	Cat's-tail grass.
Poa,	—	—	Meadow grass.
Saccharum,	—	—	Sugar-cane.

Linnæan Genera.			*Engliſh Names.*
Secale,	—	—	Rye.
Stipa,	—	—	Winged ſpike-graſs.
Triticum,	—	—	Wheat.
Uniola,	—	—	Sea-ſide oats of Carolina.

SECTION II.

Graſſes having Male and Female Flowers upon the ſame Root.

Linnæan Genera.			*Engliſh Names.*
Coix,	—	—	Job's tears.
Olyra.			
Pharus.			
Tripſacum.			
Zea,	—	—	Indian, or Turkey wheat, Indian corn.
Zizania.			

SECTION III.

Graſſes with Hermaphrodite and Male Flowers on the ſame Root.

Linnæan Genera.			*Engliſh Names.*
Aegilops,	—	—	Wild feſcue-graſs.
Andropogon.			
Apluda.			
Cenchrus.			
Holcus,	—	—	Indian millet.
Iſchæmum.			

Habit and Structure of the Plants of this Order.

Moſt of theſe plants are annual or perennial herbs; ſome of them are erect, others creep upon the ground.

The ROOTS, in the greateſt number, creep, and emit fibres

fibres from each knot or joint: in others, they are ſimply branched and fibrous.

The STEMS and branches are round.

The LEAVES are ſimple, alternate, entire, very long, and commonly narrow. They are generally placed immediately upon the ſtem, except in bamboo, pharus, a new ſpecies of reed called *guioraat ſenegal*, and a ſpecies of Iſchæmum, which have a foot-ſtalk at the origin of the leaves.

The leaves form below a ſort of ſheath, which embraces the ſtem, and is generally cleft on one ſide through its whole length. In two ſpecies of melica, mentioned by M. Adanſon, the ſheath in queſtion is perfectly entire.

The top of the ſheath is ſometimes crowned with a membrane, that is either cleft or entire, and is frequently accompanied with two appendages or ears, as in rice, pharus, darnel, wheat, rye, and barley. In others, the ſheath is crowned with hairs, as in millet, panic-graſs, and andropogon; and in ſome ſpecies of panic graſs it is naked; that is, has neither membrane nor hairs.

The FLOWERS are hermaphrodite in plants of the firſt ſection; male and female upon the ſame root in thoſe of the ſecond; hermaphrodite and male on the ſame root in thoſe of the third.

They proceed either ſingly from the ſheath of the leaves, as in lygeum; form a ſingle ſpike, as in nardus and darnel; or are formed into a panicle, that is, looſe ſpike, as in poa, agreſtis, and oats.

The CALYX and COROLLA in this order, are not ſufficiently aſcertained. In ſome, a ſingle ſcale or huſk, in others two, as in nardus, ſupply the place of both covers; ſome graſſes, as canary-graſs, and phleum, have four huſky ſcales, two of which ſerve for the calyx, and the other two for the corolla; ſome have five, as anthoxanthum; others ſix, as rice, four of which are ſuppoſed to conſtitute the calyx, and the other two are termed, improperly enough, the huſky petals.

The corolla is ſometimes compoſed of one petal with two diviſions,

diviſions, as in fox-tail graſs. In general, the huſks of the calyx are placed oppoſite to thoſe of the corolla.

Beſides the huſky ſcales that have been mentioned, there are two other ſmall ſquare ſcales, placed by each other, betwixt the ſeed-bud and the external huſk of the corolla.

Theſe ſcales are not always to be ſeen without the aſſiſtance of a magnifying glaſs; and in ſome, as panic-graſs and cenchrus, they are entirely wanting. Laſtly, the calyx and corolla, if indeed they are to be conſidered as diſtinct covers, are frequently accompanied with an ariſta or ſharp-headed awn, which ſometimes terminates the huſk, ſometimes proceeds from the middle or baſe of its back. In oats, wheat and barley, theſe ſharp beards are frequently made to diſappear by culture. Some graſſes have, beſides the calyx, a cover which accompanies or ſurrounds the flowers under the form of a ſcale, and is variouſly cut, and of a very different figure from that of the leaves.

The calyx and corolla, or rather the huſky ſcales which reſemble them, always accompany the ſeed-bud to its maturity. Upon the whole, I am of opinion, that former botaniſts were not greatly miſtaken, when they denominated the graſſes *plantæ apetalæ*, plants which want petals; as the huſky ſcales are, perhaps, with much more propriety, to be denominated a calyx.

The STAMINA are generally three in number, and placed irregularly, with reſpect to the ſituation of the calyx and the corolla. One ſtamen is commonly placed betwixt the ſeed-bud and the two ſmall ſcales or external huſk of the corolla; and two betwixt the ſeed-bud and the inner huſk. Rice, zizania, and pharus, have ſix ſtamina.

The ANTHERS are long, furniſhed with two cells, and ſlightly attached to the filaments.

The SEED-BUD is placed upon the ſame receptacle as the calyx, corolla and ſtamina. In bobartia it is ſaid to be placed under the receptacle of the flower.

The STYLE is generally double, and crowned with a hairy *ſtigma* or ſummit.

The

The SEED-VESSEL in this order is wanting.

The SEEDS are ſingle, oval, and attached below to the bottom of the flower.

The roots of the graſſes are aperient; ſuch as have an aromatic ſmell are ſtomachic; their ſeeds are mealy, mucilaginous and nouriſhing.

All the parts of theſe plants are wholeſome. The leaves of ſuch as are not too rough to the touch, are browzed upon by animals; the large ſeeds, as of wheat, rye, barley, oats, &c. are daily converted into food for men; the ſmaller ſeeds, as of canary-graſs, and panic-graſs, afford a very excellent repaſt to ſparrows and other birds; and, in times of ſcarcity, the tuberous roots of ſome of the eſculent graſſes are no bad ſuccedaneum, in default of their ſeeds.

Of a ſpecies of reed, which grows plentifully in Syria and Paleſtine, the Turks make their writing pens.

The ſtalks of *arundo donax* are uſed for fiſhing-rods.

There are two ſorts of reed, ſays Haſſelquiſt, which grow near the Nile: one of them has ſcarce any branches, but is furniſhed with numerous leaves, that are narrow, ſmooth, and channeled on the upper ſurface; and the plant is about eleven feet high. The Egyptians make ropes of the leaves. They lay them in water like hemp, and then make them into good ſtrong cables. Theſe, with the bark of the date-tree, are almoſt the only cable uſed in the Nile. The other ſort is of great conſequence. It is a ſmall reed, about two or three feet high, full branched, with ſhort, ſharp, lancet-ſhaped leaves. The roots, which are as thick as the ſtem, creep and mat themſelves together to a conſiderable diſtance. This plant ſeems uſeleſs in common life; but to it, continues the learned author, is the very ſoil of Egypt owing: for the matted roots have ſtopped the earth, which floated in the waters, and thus formed out of the ſea, a country that is habitable.

Bamboo Cane, the Arundo Bambos of Linnæus, the Ily or Illi of the Hortus Malabaricus, grows naturally in ſandy places, and on the banks of rivers in both Indies, where it frequently attains a height exceeding even that of the

cocoa-

cocoa-tree. The root is not very different from the ſtem, unleſs that it is of a whitiſh colour, and conſiſts of ſeveral radicles or fibres. From the joints of the main root are emitted ſmall jointed ſtalks, which again emit others from their joints; and from theſe, as from ſo many new roots, ariſe ſeveral ſtalks joined together, which being planted with their radicles, or ſtring roots, ſerve to perpetuate the ſpecies. Theſe ſtalks are round, have a green bark, are hard, emit from the joints new branches and twigs, and are armed in the joints themſelves with one, two, or more rigid and acute thorns of an oblong figure. It is to be obſerved, however, that the ſtalks in queſtion, ariſing, as we have ſaid, immediately from the root, have attained in their native ſoil the height of two or three men, and the thickneſs of almoſt a ſpan, before they ſend forth any lateral branches. Theſe, when young and tender, are nearly ſolid, pervious only in the middle by a ſmall tube. The older ſtalks and branches are hollow within, being ſhut, however, at the joints with a woody partition, and covered internally with a ſlender whitiſh membrane that is compoſed of hard, white, woody filaments. The colour of the ſtalks, when young, is a browniſh green; when older, a ſhining yellow with a ſhade of white. The leaves are long, narrow, ſeated on ſhort footſtalks, ſtreaked with longitudinal veins, and rough on the edges, if rubbed downwards. The flowers grow in long ſcaly ſpikes, which proceed in great numbers from the joints of the ſtalks. Rheede mentions a tradition prevailing on the coaſt of Malabar, that the bamboo vegetates till its ſixtieth year; at which period of its growth, and nearly a month before the flowers emerge from their ſcaly covers, the tree is diveſted of all its leaves, and after it has ceaſed to flower, immediately dies. This tree or reed is termed by the inhabitants of Ceylon, UNAGHAS, that is, Fever-tree, from an opinion generally entertained in that iſland, that a fever is the certain conſequence of bathing in any river into which the flowers or leaves of the bamboo have fallen. By the Arabians it is named Tabaxir, as is likewiſe a milky humour or ſugar produced in it. The

Indians

Indians call it Mambu; whence vulgarly and by corruption, its European name of Bambu, or Bamboo. In the iſland of Madagaſcar, and particularly in the province of Galemboulou, by the teſtimony of Flacourt, it is produced in ſuch abundance, as to give name to the province; for in thoſe parts it is termed Voulu. The ſize of this tree in India is generally ſo great, that houſes are built of it. In the porch of the Academical Garden at Leyden are ſuſpended ſome fragments, a preſent of the celebrated Piſo, the largeſt of which exceeds twenty-eight, the leaſt twenty-ſix feet in length. That they muſt, however, have been double that ſize before they were broken off, appears probable from this circumſtance, that the thickneſs of one extremity ſcarce differs from that of the other. It is likewiſe wonderful, that ſo immenſe a reed ſhould be clothed with ſo very ſmall leaves; the largeſt of the dried ones in the collection of Profeſſor Syens at Leyden, mentioned by Rheede in his Hortus Malabaricus, ſcarcely exceeding a ſpan in length, or the breadth of a finger in width. The ſtalks, when old, are entirely covered in the cavity with a ſort of calx, which is eſteemed uſeful in the ſtrangury, and to ſuch as are troubled with purulent urine. Bamboo, being burnt, affords very fertile aſhes, in which plants of all kinds thrive remarkably. Whilſt burning, the ſtalks emit a very loud exploſion; the air contained in their cavity being rarified by the heat, and deſiring a larger ſpace, breaks through the partitions at the joints, and violently ſeeks a paſſage whereby to eſcape. Kæmpfer relates, in the Amœnitates Exoticæ, that in a province of Japan, called Oomi, which has a ſlimy bottom, the roots of bamboo luxuriate with ſuch wonderful beauty, that, being dug out of the ground, and diſentangled from the ſtrings which encompaſs them, they ſerve, as the ſtalks with us, for walking ſticks, commonly called Rotang. From this curious reed ſeveral conveniences are obtained, beſides thoſe which have been mentioned. In particular, the natives of India, of the ſtems of the Bamboo, make moſt of their common utenſils. The reader is referred for a more minute detail, to the Mantiſſa Aromatica of Piſo, where, beſides a very accurate deſcription of the Tabaxir

or Sugar, mentioned above, he will alſo learn, that the tender branches or twigs, particularly thoſe near the root, being macerated in ſalt and vinegar, afford, with the addition of garlick, and the pods of capſicum, a ſort of pickle, which is eſteemed excellent, and conſtitutes not the leaſt valuable part of thoſe famous *condita*, commonly termed Achar, and Atsjaar, and well known in Europe for exciting the appetite, and promoting digeſtion.

Mr. Ray, in his "Wiſdom of God in the Creation," juſtly obſerves, that it is no ſmall inſtance of the great Creator's goodneſs, that wheat, and the moſt common corn uſed for food, ſhould be the growth of moſt parts of Europe and Aſia. It is likewiſe no leſs worthy obſervation, that, where the ſoil under the Torrid Zone is too hot to produce wheat, the ſame divine wiſdom hath appointed other kinds of corn to grow and ripen there in great plenty. Thus, in Africa and the Weſt Indies, this want is ſupplied by Indian and Guinea corn: and, in ſome places, where the exceſſive heat of the climate renders labour and the cultivation of corn painful, there bountiful Providence, with an unſparing hand, ordains food without labour, by cauſing banana and plantain trees to grow in great plenty, whoſe fruit is, by many perſons, preferred to any kind of bread whatſoever.

The ſtalk and panicle of Job's tears much reſemble thoſe of Guinea corn; and the ſeeds, which are incloſed in ſmall capſules, are about the bigneſs of an Engliſh pea, and of different colours. Theſe are ſtrung upon ſilk, and uſed inſtead of bracelets by ſome of the poorer ſort in the Weſt Indies, but eſpecially by the negroes. In a ſcarcity of corn, the poor people in Spain and Portugal grind the ſeeds to flour, of which they make a coarſe ſort of bread.

Rice is greatly eſteemed in moſt of the eaſtern countries, where it is the chief ſupport of the inhabitants. The plant bears a ſtalk about three or four feet high, much ſtronger and thicker than that of wheat or other corn. The leaves are long like the reed, and fleſhy; the flowers blow on the top like barley; but the ſeed which follows is diſpoſed in cluſters, each of which is encloſed in a yellow huſk ending in a ſpiral thread. The ſeed is oblong, or rather oval and

white. The plant is cultivated in moiſt or low grounds in Italy, and the ſeed brought dry from Piedmont, Spain, and ſeveral other places.

Rice is the chief commodity and riches of Damietta, in Egypt. Dr. Haſſelquiſt thus deſcribes the manner in which they dreſs it, and decorticate, that is, ſeparate it from the huſk. It is pounded by hollow iron peſtles of a cylindric form, an inch in diameter, lifted up by a wheel worked by oxen. A perſon ſitting between the two peſtles puſhes forward the rice, when the peſtles are riſing; another ſifts, winnows, and lays it under the peſtles. In this manner they continue working it, until it is entirely free from chaff and huſks. When clean, they add a thirtieth part of ſalt, and pound them together; by which the rice, formerly grey, becomes white. After this fining, it is paſſed through a fine ſieve, to part the ſalt from the rice; and then it is ready for ſale. Damietta ſells every year ſixty thouſand ſacks of rice, the greateſt part of which goes to Turky, ſome to Leghorn, Marſeilles and Venice.

Guinea corn is the *milium arundinaceum* of Caſpar Bauhin, the *holcus ſorghum* of Linnæus. The ſtalks are large and compact, and full eight feet high. In Senegal the fields are entirely covered with it. The Negroes, who call it *guiarnot*, cover the ears when ripe with its own leaves, to ſhelter it from the ſparrows, which are very miſchievous in that country. The grain made into bread, or otherwiſe uſed, is eſteemed very wholeſome. It is with this that the ſlaves in the Weſt Indies are generally fed, each being allowed from a pint to a quart every day. The juice of the ſtalks is ſo agreeably luſcious, that, if prepared as the ſugar-canes, they would afford an excellent ſugar.

The Negroes on the coaſt of Guinea, make of two ſorts of millet, a thick grained pap, called *couſcous*, which is their common food.

The ſugar-cane grows naturally in both Indies, where it is likewiſe cultivated for its juice, which, when boiled, affords that ſweet ſubſtance called ſugar.

In the manner of their growth, form of their leaves, and

make

make of their panicle, the ſugar-canes reſemble the reeds which grow in wet marſhy grounds in England, or elſewhere, except that the canes are far larger, and, inſtead of being hollow, as the reeds, are filled with a white pith, containing the ſweet juice or liquid which ſtamps ſuch an amazing value upon theſe plants. The intermediate diſtance between the joints of a cane is of different lengths, according to the nature of the ſoil, richneſs of the manure, and temperature of the weather during its growth; it ſeldom exceeds, however, four inches in length, and an inch in diameter. The length of the whole cane likewiſe depends upon the above circumſtances. It generally grows to perfection in about fourteen months, when its height, at a medium, is about ſix feet, ſometimes more, ſometimes leſs. The body of the cane is ſtrong, but brittle; of a fine ſtraw-colour inclining to a yellow. The extremity of each is covered, for a conſiderable length, with many long graſſy leaves or blades, ſharply and finely ſawed on their edges; the middle longitudinal rib being high and prominent.

The bottom part of the ſugar-cane top, is about the thickneſs of one's finger; and as it contains a good deal of the natural ſweetneſs of the plant, it is uſually cut into pieces of an inch and a half long, and given to the ſaddle-horſes in the Weſt Indies. It is very nouriſhing food, and fattens them apace. The mill-horſes, mules, and aſſes, are likewiſe fed, during crop-time, on ſugar-cane tops, and the ſkimming of the ſugar-coppers; which laſt muſt be adminiſtered ſparingly at firſt, for fear of griping, and, perhaps, killing them.

The canes, when ripe, are ſqueezed between the iron-caſed rollers of wind-mills, or cattle-mills. The juice thus preſſed out is boiled firſt in a very large copper or cauldron, being mixed with a very ſmall quantity of lime. In default of lime, a ſtrong ley of aſhes will anſwer the ſame purpoſe, and was indeed originally uſed, though the firſt is generally thought to have greater efficacy. The benefits ariſing from either ſubſtance are probably to be attributed, in a great meaſure, to their alkaline qualities.

The

The ſugar-cane, when ripe, is of all plants the ſweeteſt; there is, however, a latent acid ſtill lurking in the juice; as is manifeſt, by its turning ſour, if ſuffered to remain unboiled any conſiderable time after expreſſion. The addition, therefore, of white lime, which the planters call *temper*, is neceſſary to deſtroy, in a great meaſure, the remaining acid, and to form a neutral ſalt.

Lime, or the ſtrong ley juſt mentioned, likewiſe ſerves to carry off all impurities from the liquor. When the quantity of *temper* is duly proportioned, if the liquor is put into a glaſs, an immediate ſeparation will follow; the ſordes ſettle at the bottom, the juice remains tranſparent at top. On the other hand, if there is a deficiency of *temper*, the ſeparation will be imperfect; and if there is a ſuperfluity, there will be no ſeparation at all.

After the lime is mixed with the juice in the copper or cauldron, the impurities in queſtion being no longer intimately united with the boiling liquor, and being forced about with the heat of the fire, are eaſily entangled in a viſcous tough ſubſtance, naturally in the cane-juice, with which they riſe to the top of the copper, forming a thick tough ſcum.

The clarification of the liquor, as far as is done in the firſt copper, is perfected after the more groſs ſcum is taken off; the remaining impurity, as the liquor boils, is ſkimmed off from the four or five remaining coppers, into which the liquor is ſucceſſively poured; each of the coppers being gradually leſs, as containing a leſs quantity of liquor.

In its paſſage to the fourth copper, the liquor is ſtrained through a thick woollen cloth, where it leaves all the remaining impurities that had eſcaped the ſcummer.

After this a light white ſcum is taken off; and, when this ceaſes to ariſe in any conſiderable quantity, and the liquor, by long boiling, becomes more of a ſyrup than a thin liquid, it is then poured into the firſt tache, and from this to a leſſer, till it is conveyed to the laſt. When it has here attained the due conſiſtence neceſſary to become ſugar, it may be aſſerted, ſays Hughes, from whom this account is

chiefly extracted, that no more than a ſeventh part of the whole remains; which diminution is occaſioned by the impurities being ſcummed off, and the watery particles evaporated.

From this laſt ſtage it is conveyed, whilſt of the conſiſtency of a thick granulated ſyrup, into a large braſs cooler, where it ſhoots into cryſtals, which are the genuine and eſſential ſalts of the plant; theſe are forwarded by gently ſtirring the whole maſs, by which means the air is admitted to every part, and the particles of ſugar diſengage themſelves from the clammy ſubſtance, which is termed melaſſes.

When it has grained or cryſtallized, it is removed from the cooler into pots or moulds, which are earthen, and of a pyramidal form, containing from eight to thirteen gallons.

About twenty-four hours after the ſugar is potted, the ſmall round hole in the bottom of each pot is unſtopped, and the pots put upon earthen jars, containing about four gallons each. Into theſe veſſels, the melaſſes drain from the ſugar, which, in this degree of perfection, is called muſcavado, and is fit for exportation in a month or ſooner.

From the abovementioned ſkimmings, mixed with a quantity of water and melaſſes, and fermented, is extracted that ſpiritous liquor called rum; and from the great quantity of oil in the cane-juice, which is tranſmitted in abundance to the rum, proceeds the excellency of that ſpirit compared with brandy. The latter wanting this oilineſs, ſtimulates and lacerates the coats of the ſtomach; whereas the former, if meliorated by age, and drunk moderately, ſerves, by its oilineſs, to lubricate and preſerve the bowels.

The moſt natural, and perhaps the only proper method of producing canes, is by ſuckers, or with the tender tops of old canes. Theſe being cut into pieces of about a foot long, planted in holes of about ſix inches deep, and two feet wide, and covered with good manure, will produce each from its roots a great number of canes.

GRAMINIBUS *affines*, the name of a claſs in Haller's natural method, conſiſting of plants, which, like ruſh, carex,

carex, and cyperus, ſeem nearly allied to the family of the graſſes.

GRAMINIFOLIÆ, from *gramen*, graſs, and *folium*, a leaf; the name of a claſs in Ray's *Methodus Propria*, conſiſting of plants which have leaves like thoſe of the graſſes. It is exemplified in ſcirpus and cyperus.

GRUINALES, from *grus*, a crane; the name of the fourteenth order in Linnæus's Fragments of a Natural Method, conſiſting of geranium, vulgarly called crane's bill, and a few other genera, which the author conſiders as allied to it in their habit and external ſtructure.

The title was probably derived from a genus of Rivinus of the ſame name, which Linnæus has added to the genus geranium.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Aldrovanda.			
Averrhoa.			
Droſera,	—	—	Sundew.
Fagonia.			
Geranium,	—	—	Crane's bill.
Guaiacum,	—	—	Lignum vitæ, or pockwood.
Linum,	—	—	Flax.
Oxalis,	—	—	Wood-ſorrel.
Quaſſia.			
Tribulus,	—	—	Caltrops.
Zygophyllum,	—	—	Bean-caper.

Habit and Structure of the Plants of this Order.

This order furniſhes both herbaceous and woody plants.

The ROOTS are ſometimes fibrous, ſometimes tuberous. In ſome ſpecies of wood-ſorrel they are jointed.

The STEMS are cylindric. The young branches, in ſome, nearly ſquare.

The BUDS are of a conic form, and covered with ſcales.

The LEAVES are either ſimple, as in geranium; or compound, as in lignum vitæ and caltrops. In bean caper, they conſiſt of one pair of *pinnæ* or wings only; in lignum vitæ, from two to five pair; and in caltrops, from three to eight, placed oppoſite. In *fagonia* the leaves are finger-ſhaped, each leaf being compoſed of three lobes or leſſer leaves.

The lower leaves of moſt of the geraniums are commonly alternate; the upper ones are oppoſite, one of the two being larger than the other.

The STIPULÆ or ſcales in the European geraniums ſurround the footſtalks of the lower leaves, and fall with them. In the African ſpecies, all the leaves, both upper and lower, have ſupports of the ſame kind, which are ſometimes united at the baſe, ſo as to have the appearance of a ſingle ſtipula. The ſcales which accompany the leaves at the top of the branches of the European geraniums, fall off very early. Wood-ſorrel bears *ſtipulæ* on its footſtalk, preciſely at the joints.

The FLOWERS are hermaphrodite.

They proceed from the wings of the leaves, either ſingly, as in guaiacum, flax, aldrovanda, and ſagonia; or in cluſters, as in ſome ſpecies of geranium and wood-ſorrel.

In ſundew they terminate the branches in a ſpike: and in bean caper, they are produced either ſingly, or two by two, along the branches, without the angles or wings of the leaves.

The CALYX or FLOWER-CUP conſiſts either of five diſtinct leaves, as in moſt of the geraniums, flax, and bean-caper; or of one leaf divided almoſt to the bottom into five parts, as in aldrovanda and ſundew; it generally accompanies the ſeed-bud to its maturity. In ſagonia, the calyx, which is compoſed of five leaves, falls with the petals, and the other parts of the flower.

The PETALS are five in number, ſpread, and are frequently funnel-ſhaped. In the different ſpecies of geranium, the

the figure of the petals is different, as is likewiſe their number. In aldrovanda, the petals, as well as the calyx, are permanent.

The NECTARIUM in bean-caper and quaſſia, conſiſts of a number of ſmall leaves or ſcales, which are inſerted into the inſide of the baſe of the filaments, and ſurround the ſeed-bud. Theſe ſcales, in the former, are ten in number, one for each filament: in the latter, they are hairy, and but five in number.

The STAMINA are generally ten in number, awl-ſhaped, erect, and of the length of the petals. In averrhoa and geranium they are alternately long and ſhort. The filaments in ſome of the geraniums are united below; in others, diſtinct.

In flax, aldrovanda, and ſun-dew, there are but five ſtamina; the firſt, however, beſides its five perfect ſtamina, has five other bodies reſembling ſtamina without tops, which are placed alternate with the former. Nay, in a particular ſpecies, called *linum luſitanicum*, there are ten perfect ſtamina.

The ANTHERS or tops of the ſtamina are generally oblong, and frequently attached to the filaments by the middle, ſo as to lie and ſometimes to veer about upon them. In flax, the anthers are arrow-ſhaped. Their number is not conſtant in the different ſpecies of geranium: ſome have ten, ſome ſeven, and others five.

The SEED-BUD is either oblong, or five cornered.

The number of *ſtyles* is either one, as in bean-caper, quaſſia, and ſagonia; or five, as in aldrovanda, wood-ſorrel, and flax. In *tribulus* the ſtyle is wanting.

The SEED-VESSEL is generally a five-cornered *capſule*, with one, three, five, or ten cells. In *averrhoa*, the ſeed-veſſel is of the apple-kind, ſhaped like a top, with five angles, and the ſame number of cells. *Quaſſia* and *tribulus* have five different fruits or ſeed-veſſels, which, in the former, are egg-ſhaped, and inſerted into a large round fleſhy receptacle. In a ſpecies of *tribulus*, the *ciſtoides* of Tournefort, the number of fruits is ten.

The SEEDS are generally equal in number to the internal diviſions or cells of the ſeed veſſel; one ſeed being placed in each cell. In geranium, the ſeeds, which are five in number, and kidney-ſhaped, are commonly wrapped in the proper coat or covering, called by Linnæus, *arillus*, and terminated by a ſpiral beard or haulm. In wood-ſorrel, the ſeeds are diſperſed with an elaſtic ſpring.

Flax, with reſpect to its virtues and uſes in medicine, is bitter, mucilaginous, purgative, and uſed in inflammations.

Geranium is vulnerary and aſtringent.

The leaves of wood-ſorrel, boiled in broth, are ſaid to be ſerviceable in putrid fevers.

The leaves of *geranium zonale* are marked with a purple circle like a horſe-ſhoe, which reaches from one ſide of the baſe to the other, and correſponds with the border of the leaf. When gently rubbed, they have a ſcent like ſcalded apples.

The flowers of *geranium triſte* are marked with dark purple ſpots, and ſmell very ſweet after the ſun has left them; hence the ſpecies is known among gardeners by the name of night-ſcented crane's-bill. In general, it may be obſerved, that moſt ſpecies of geranium with tuberous fleſhy roots have their odour augmented in the evening, and during the abſence of the ſun.

Guaiacum, or holy-wood, grows plentifully both in the Eaſt and Weſt Indies, and is brought to us in large long billets or logs, ſome of which weigh four or five hundred weight. It is about the ſize of a common walnut-tree, bearing bark which is thick and gummy, and eaſily parts from the wood. The leaves are winged, and the lobes placed oppoſite. The flowers, which conſiſt of five petals, are of a beautiful violet colour. They are ſucceeded by a fruit like ſmall cheſnuts, round, ſolid, and brown; within which is contained another little fruit or nut, of an orange colour. The wood is hard, firm, weighty, and marbled with brown, red, and black: it is of an acrid taſte. Guaiacum is the beſt ſort of wood for turnery-ware, eſpecially for making mortars, peſtles, rowling-pins, and bowls for the

bowling-

bowling-green. In medicine, the ſhavings or raſpings have been long uſed in ptiſans and ſudorific drinks for the venereal diſeaſe. The bark and gum of this tree have likewiſe been uſed with ſucceſs in the cure of the ſame diſorder, as well as in catarrhs, gouts, rheumatiſms, and other diſeaſes proceeding from weakneſs or obſtructions of the viſcera.

From the ſeeds of common flax is expreſſed an oil, which is uſed both by phyſicians and painters; from the bark or peeling of the ſtalks is made linen; and from the rags of linen is made paper; ſo that this plant is one of the moſt valuable in the whole vegetable kingdom.

Caltrops, the tribulus of Virgil*, bears a fruit that is armed with ſtrong prickles. Theſe are apt to run into the feet of the cattle which walk over the ground where they are produced. It has derived both its ſcientific and Engliſh names from the form of the fruit, which reſembles thoſe inſtruments of war that were caſt in the enemies way to annoy their horſe. A ſimilar inſtrument, and with three iron ſpikes, (which exactly correſponds to the Greek Τρίβολος, *tres jactus, aut tria jacula,*) has been uſed in hunting the wolf. The military caltrop has commonly four ſpikes, one of which is always erect, the other three adhering to the ground.

GYMNODISPERMÆ, (from γυμνος, naked; δις, twice; and σπερμα, a ſeed;) the name of a diviſion in Hermannus and Boerhaave's Methods, conſiſting of plants which have two ſeeds that are naked, that is, want the pericarpium or ſeed-veſſel. Of this kind are all the umbelliferous tribe of plants, ſuch as angelica, parſly, hemlock, &c. *Vide* UMBELLATÆ.

GYMNOMONOSPERMÆ, (from γυμνος, naked; μονος, alone, ſingle; and σπερμα, a ſeed). The name of a diviſion in Hermannus and Boerhaave's Methods, conſiſting of plants which have flowers with one naked ſeed. Such are all the compound flowers; each floret, or partial flower,

* ——— *ſubit aſpera ſylva*
Lappæque TRIBULIQUE.——— Georg. Lib. I. v. 152.

having a ſingle ſeed without a covering or veſſel placed under it. *Vide* SYNGENESIA & COMPOSITUS *flos*.

In Ray's *Methodus propria*, is a diviſion or claſs of the ſame name.

GYMNOPOLYSPERMÆ, (from γυμνος, naked; πολυς, many; and σπερμα, a ſeed). The name of a diviſion or claſs in Hermannus and Boerhaave's methods, conſiſting of plants which have many ſeeds that are naked, that is, without any *pericarpium* or ſeed-veſſel. The term is exemplified in anemone, adonis, meadow-rue, virgin's bower and ranunculus.

GYMNOSPERMÆ, (from γυμνος, naked; and σπερμα, a ſeed). The name of a principal diviſion in Hermannus's Method, conſiſting of plants whoſe ſeeds are naked, that is, want a covering or ſeed-veſſel, oppoſed to *angioſpermæ*, which ſee.

GYMNOSPERMIA, is the name of an order, or ſecondary diviſion, in the claſs *didynamia* of Linnæus, conſiſting of plants which have four ſtamina two long and two ſhort, and four naked ſeeds. This order correſponds to the labiati, or lipped-flowers, of Tournefort, and the verticillatæ, or plants that flower at the joints, of Ray, and of Linnæus in his Fragments of a Natural Method.

GYMNOTETRASPERMÆ, (from γυμνος, naked; τεσσαρες, four; and σπερμα, a ſeed). The name of a diviſion in Hermannus and Boerhaave's methods, conſiſting of plants which have four naked ſeeds. Of this kind are the rough-leaved plants, as borage, bugloſs, comfrey and lungwort; and the plants which flower at the joints, as mint, marjoram, thyme and dead-nettle. *Vide* ASPERIFOLIÆ & VERTICILATÆ.

GYNANDRIA, (from γυνη, a woman; and ανηρ, a man or huſband). The name of the twentieth claſs in Linnæus's Sexual Syſtem, conſiſting of plants with hermaphrodite flowers, in which the ſtamina are placed upon the ſtyle, or, to ſpeak more properly, upon a pillar-ſhaped receptacle reſembling a ſtyle, which riſes in the middle of the flower, and bears

bears both the ſtamina and pointal; that is, both the ſuppoſed organs of generation.

The orders in this claſs are ſeven, founded each upon the number of the ſtamina in the plants which compoſe it. The firſt order conſiſts of plants which have two ſtamina, ſituated as expreſſed in the claſſic character. Such are orchis, baſtard hellebore, bee-flower, ſatyrium, limodorum, arethuſa, lady's ſlipper and vanelloe. Theſe plants, which have a particular ſtructure, conſtitute a true natural order in Linnæus's Fragments, under the name of *orchideæ*. The genera, which were formerly diſtinguiſhed by the root, Linnæus diſcriminates by the nectarium, which is different in each genus.

The ſecond order conſiſts of plants with three ſtamina; it contains two genera, *viz.* ſiſyrinchium, or bermudiana, and ferraria. The third o der has four ſtamina, and contains only one genus, *viz.* nepenthes. The fourth order has five ſtamina, and contains two genera, ayenia and paſſion-flower. The fifth order has ſix ſtamina, and contains two genera, birthwort and piſtia. The ſixth has ten ſtamina, and contains likewiſe two genera, *viz.* kleinhovia and ſcrew-tree. The laſt order contains plants which have an indefinite number of ſtamina. The genera in this order are grevia, cuckow-pint, dragons, African arum, pothos, and graſs-wrack.

The flowers of this claſs, ſays Linnæus, have a monſtrous appearance, ariſing, as he imagines, from the ſingular and unuſual ſituation of the parts of fructification.

H.

HABITUALIS *character*. The character of plants drawn from their port or habit. *Vide* CHARACTERES.

HABITUS *plantæ*. By the ancient botaniſts, the habit of a plant was meant to expreſs its port and general appearance: by Linnæus, habit is defined to be the agreement of plants of the ſame genus or natural order, in the following circumſtances: the number of ſeminal leaves, (placentatio);

the

the nature and form of the root, (radicatio); the ſituation of the leaves and branches, (ramificatio); the twiſting of any of the parts towards one ſide, as of the ſtem and corolla, (intorſio); the origin or conſtruction of the buds, (gemmatio); the complication or folded ſtate of the leaves within the buds, (vernatio); the ſituation and ſtructure of the ſtipulæ or ſcales, which are placed at the baſe of the young foot-ſtalks of the leaves and flowers, (ſtipulatio); the nature of their armature or offenſive weapons and veſſels of ſecretion, (pubeſcentia & glandulatio); their juices, (lacteſcentia); and the manner in which the flowers are borne, or ſupported on their footſtalks, (infloreſcentia). *Vide* PLACENTATIO, &c.

HAMUS, a hook; a ſpecies of briſtly armour, in which each briſtle is bowed inwards at the top. Of this kind are the offenſive weapons of burdock and Guinea-hen weed. In lappula, the hooks are three-pointed.

HEDERACEÆ, (from hedera, ivy). The name of the forty-ſixth order in Linnæus's Fragments of a Natural Method, conſiſting of ivy, and a few other genera, which, from their general habit and appearance, ſeem nearly allied to it.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Aralia,	—	—	Berry-bearing angelica.
Ciſſus,	—	—	Wild grape.
Hedera,	—	—	Ivy.
Panax,	—	—	Ginſeng.
Vitis,	—	—	Vine.
Zanthoxylum,	—	—	Tooth-ach tree.

Habit and Structure of the Plants of this Order.

This order furniſhes both herbaceous and ſhrubby plants, moſt of which, particularly ivy and vine, have creeping branches, that attach themſelves by roots or tendrils to the bodies in their neighbourhood.

The ROOTS are long, with few branches.

The STEMS and YOUNG BRANCHES are cylindric. In ſome ſpecies of vine they are ſquare.

The LEAVES are alternate, ſometimes ſimple, as in ivy and vine, ſometimes winged, as in tooth-ach tree, in which the ſurface of the leaves is covered with points.

The foot-ſtalk of the leaves is cylindrical, and without any furrow.

The BUDS are of a conic form, and without ſcales.

On each ſide of the foot ſtalk of the leaves of the vine, are placed two pretty large STIPULÆ or ſcales. Along the branches of tooth-ach tree are protruded from the bark, a number of prickles which fall off very early.

From the ſide oppoſite to the leaves in the vine, proceeds a branching tendril, which ſerves to faſten the plant in queſtion to the bodies in its neighbourhood, for the purpoſe of ſupport.

The FLOWERS are either hermaphrodite, as in ivy, vine, berry-bearing angelica, and ciſſus; male and female upon different roots, as in ginſeng; or hermaphrodite and male upon different roots, as in tooth-ach tree.

They terminate the branches in an umbel or looſe ſpike in ginſeng, berry-bearing angelica and ivy; and proceed in cluſters from the ſide oppoſite to the leaves in the vine and ciſſus. In tooth-ach tree they are produced along the branches.

The CALYX, or proper flower-cup, conſiſts of one leaf divided into five parts, which are ſmall and generally permanent. In ciſſus, ivy, tooth-ach tree, and berry-bearing angelica, there is an *involucrum* or cover conſiſting of many leaves which are permanent, placed under each umbel or cluſter of flowers. In ginſeng and aralia, the calyx is placed above the ſeed-bud.

The PETALS, in this order, are generally five in number; ciſſus has four petals, tooth-ach tree none.

The STAMINA are in number five, awl-ſhaped, erect, and generally of the length of the petals. Ciſſus has only four ſtamina, which are inſerted into the nectarium, a ſort of border ſurrounding the ſeed-bud.

The

The ANTHERS, or tops of the ſtamina, are roundiſh, and ſometimes, as in ivy, attached to the filaments by the ſides. In tooth-ach tree, the filaments are crowned with twin anthers; that is, each filament is furniſhed with two tops.

The SEED-BUD is ſometimes round, ſometimes ſhaped like a top or pear, and ends in one, two or five awl-ſhaped ſtyles, which are crowned with a ſimple *ſtigma* or ſummit. The flowers of the vine have no ſtyle.

The SEED-VESSEL is of the berry kind; with one cell, as in ciſſus, ivy and vine; two, as in ginſeng; or five, as in aralia. In tooth-ach tree, the ſeed-veſſel is a capſule with one cell, and two external openings or valves. Aralia has its berry crowned with the remains of the calyx, which was placed above the ſeed-bud.

The SEEDS are from one to five in number, placed either in diſtinct cells, as in aralia; or diſperſed through the pulp without any partition, as in ivy berries and the grapes of the vine.

The roots of ginſeng, the *panax quinquefolium* of Linnæus, although very hot, are eſculent. The Chineſe hold the whole plant in great eſtimation, and affirm it to be a ſovereign remedy for all weakneſſes occaſioned by exceſſive fatigue, whether of body or of mind. The root, which in ſhape greatly reſembles that of the mandrake, becomes yellowiſh in drying; and, when chewed, diffuſes an agreeable warmth over the whole body. In ſhort, it is a kind of panacea or univerſal medicine in China, where it is ſaid to be valued at three times its weight in ſilver.

If the account given by Kolben, in his State of the Cape of Good Hope, be accurate, ginſeng, which is known to be a production of China, Japan, Canada, Penſylvania, Virginia, and Carolina, all ſituated to the north of the equator, grows likewiſe naturally and in the ſame latitude with ſome of the countries juſt mentioned, in the ſouthern hemiſphere. "There is a root," writes this amuſing Traveller, "gathered in the Hottentot countries called *Kanna*, in ſuch eſteem among theſe people for its virtues, that they almoſt adore it. What much enhances the value of this root is its ſcarcity, being

being very rarely to be found. They regard it as the nobleſt reſtorative in the world, will give almoſt any thing for it in exchange; and in ſhort, for the ſmalleſt piece of *Kanna*, will perform a hard day's work, run twenty miles upon an errand, nor think any labour a ſufficient compenſation for ſo gratifying a preſent. I have often," he proceeds, "obſerved the effects of Kanna upon Hottentots. They chew and retain it a conſiderable time in their mouths; but taking generally too much at a time, it drowns them in intoxications. They chew it not long before their ſpirits viſibly riſe, their eyes brighten, their faces aſſume a jovial air, and they ſport and wanton under a thouſand gaieties of imagination; but in the end, it diveſts them entirely of their ſenſes, and they are thrown into the wildeſt delirium, and moſt fantaſtical extravagancies."

The reader, who would acquire farther notices of this curious plant, is referred to Kalm's Travels into North America, Vol. III. Oſbeck's Voyage to China and the Eaſt Indies, Vol. I. p. 223, of Forſter's Tranſlation. Cateſby's Natural Hiſtory of Carolina, Vol. III. Gronovius's *Flora Virginica*; and Father Charlevoix's Hiſtory of Canada or New France.

Wild grapes grow naturally in the Weſt Indies, where they are frequently eaten by the Negroes, but are chiefly food for birds and wild fowl.

Ivy is highly aſtringent; the leaves are frequently applied with ſucceſs to iſſues and inflammations of the ſkin. A doſe of the full ripe berries has been recommended as a remedy againſt the plague. The gum of ivy is a powerful reſolvent and diſcutient, and an excellent ingredient in plaiſters and ointments for ſuch purpoſes.

Caſpar Bauhin and Tournefort mention a ſort of ivy that grows in many of the iſlands of the Archipelago, to which they have given the name of poet's ivy, becauſe the ancients are ſaid to have made crowns of this plant for adorning the brows of their poets. By others it is called hedera dionyſias, becauſe they made uſe of the ſame ſort of ivy in their public rejoicings and feaſts in honour of Bacchus. The berries

are

are of a fine gold colour; whence the ſpecies in queſtion has been termed by others, chryſocarpos.

Tooth-ach tree, ſometimes called pellitory-tree, is ſudorific and diuretic, and is frequently employed in Canada, to promote theſe ſecretions.—The bark is preſcribed for the tooth-ach, from whence it derives its name.

HEPTANDRIA, (from ἑπτα, ſeven; and ἀνηρ, a man, or huſband). The ſeventh claſs in Linnæus's Sexual Method, conſiſting of plants with hermaphrodite flowers which have ſeven ſtamina or male organs. The orders are four, derived from the number of ſtyles or female organs. Horſe-cheſnut and trientalis have one ſtyle; limeum has two; lizard's tail three; and ſeptas ſeven.

HERBA, the herb. By this name Linnæus, in his diſtribution of the parts of a plant, denominates that portion of every vegetable which ariſes from the root, and is terminated by the fructification. It comprehends—I. The trunk, ſtalk, or ſtem.—II. The leaves.—III. Thoſe minute external parts called by Linnæus the *fulcra* or ſupports of plants.—IV. The buds; or, as they are termed by the ſame author, the winter-quarters of the future vegetable.

HERBACEA *planta*, an herbaceous vegetable; a plant with a ſucculent ſtem or ſtalk, which dies down to the root every year. Of herbaceous plants, thoſe are annual, which periſh, ſtem, root, and all, at the end of one year; biennial, which ſubſiſt two years by their roots; perennial, which are perpetuated by their roots for a ſeries of years, a new ſtem being produced every ſpring.

HERMAPHRODITA *planta*. An hermaphrodite plant; that is, a plant producing hermaphrodite flowers only. *Vide infra*.

HERMAPHRODITUS *flos*; (from Ἑρμης, Mercurius, and Ἀφροδιτη, Venus,) a flower ſo termed by the Sexualiſts, which contains both the *anthers* and *ſtigma* the ſuppoſed organs of generation, within the ſame calyx and petals. Of this kind are the flowers of all the claſſes in Linnæus's Sexual Method, except the claſſes *monœcia* and *diœcia*: in the former of which, male and female flowers are produced

on

on the ſame root; in the latter, on diſtinct plants from the ſame ſeed. In the claſs *polygamia*, there are always hermaphrodite flowers mixed with male or female, or both, either on the ſame or diſtinct roots.

In the plantain-tree, the flowers are all hermaphrodite; in ſome, however, the *anthers*, or male organ, in others, the *ſtigma*, or female organ, proves abortive. The flowers, in the former caſe, are ſtiled female hermaphrodites; in the latter, male hermaphrodites.

Hermaphrodites are as frequent in the vegetable, as they are rare and unuſual in the animal, kingdom.

HESPERIDEÆ (from the Heſperides, whoſe orchards, according to the Poets, produced golden apples). Golden or precious fruit. The name of the nineteenth order in Linnæus's Fragments of a Natural Method, conſiſting of the five following genera.

Linnæan Genera.			*Engliſh Names.*
Caryophyllus,	—	—	Clove-tree.
Eugenia.			
Myrtus,	—	—	Myrtle, all-ſpice or pimento.
Philadelphus,	—	—	Mock orange or ſyringa.
Pſidium,	—	—	Guayava or bay-plumb.

Habit and Structure of the Plants of this Order.

The plants of this order are of the ſhrub and tree kind, and moſtly ever-green.

The bark of the ſtalks is ſlender, and comes off in thin plates.

The LEAVES are generally oppoſite, and covered with ſmall tranſparent points. In ſome genera, particularly the myrtle and guayava, the leaves are placed oppoſite at the bottom of the ſtalks, and alternate above.

The BUDS are of a conic form. In the mock orange, they are almoſt ſpherical, and covered with ſcales, or rather with leaves, which by their minuteneſs reſembles ſcales. They are concealed in the cavity which is formed by the

foot-ſtalk of each leaf at its origin.—In the myrtle and guayava are obſerved two ſmall points in the form of *ſtipulæ* or ſcales.

The FLOWERS are generally hermaphrodite. In a ſpecies of myrtle, they are male and female upon different roots.

They proceed from the wings of the leaves, either ſingly, or in cluſters like ivy-berries.

The CALYX is placed above the ſeed-bud, and accompanies it to its maturity.

The PETALS are three, four, or five in number, and ſtand upon the brims of the tube of the calyx.

The STAMINA are upwards of twenty, nearly equal, and attached in ſeveral rows to the middle of the tube of the calyx.

The SEED-BUD is large, oblong, and placed below the receptacle of the flower. The *ſtyle* is ſingle, awl-ſhaped, of the length of the ſtamina, and terminated with a ſingle *ſtigma* or ſummit.

The SEED-VESSEL in guayava and myrtle, is a berry, furniſhed with one cell in the former, with three in the latter. In mock orange, the ſeed-veſſel is a capſule with four cells; in *eugenia*, it is of the nature of a cherry, and contains a ſtone.

The SEEDS are numerous, ſmall and oblong, in mock orange and guayava. Myrtle-berries have three ſingle kidney-ſhaped ſeeds, one in each cell.

The leaves and fruits of theſe plants are aſtringent. The berries are eſculent. A decoction of the roots of guayava is employed with ſucceſs in dyſenteries: a bath of a decoction of the leaves is ſaid to cure the itch and other cutaneous eruptions.

Guayava or guava is diſtinguiſhed from the colour of the pulp into two ſpecies, the white and the red; and from the figure of the fruit, into the round, and the pear-faſhioned or perfumed guava. The latter has a thicker rind, and a more delicate taſte than the other. Either ſpecies, if carefully cultivated, and in a good ſoil, will grow to about eighteen feet in height. The bark is very ſmooth, and of a reddiſh

grey.

grey. The leaves are about three inches long, ſharp-pointed, and have a prominent rib in the middle. The flowers conſiſt of five petals, which are white, and ſurround a great many ſhort ſtamina tipped with pale-yellow tops. The fruit is about the bigneſs of a large tennis-ball; the rind or ſkin generally of a ruſſet ſtained with red; the top is adorned, like the apple and pear, with a crown conſiſting of the remains of the calyx. The pulp within the thick rind is of an agreeable flavour, and interſperſed with a number of ſmall white ſeeds. The rind of the guava, when ſtewed, is eaten with milk, and preferred to any other ſtewed fruit. From the ſame part is made marmaladè; and from the whole fruit is prepared the fineſt jelly in the world. The fruit is very aſtringent, and nearly of the ſame quality with the pomegranate; ſo ſhould be avoided by all who are ſubject to be coſtive. The ſeeds are ſo hard as not to be affected by the fermentation in the ſtomachs of animals; ſo that when voided with the fœces, they take root, germinate and produce thriving trees. Whole meadows in the Weſt Indies are covered with guavas, which have been propagated in this manner.—The buds of guava, boiled with barley and liquorice, produce an excellent ptiſan for diarrhœas, and even the bloody-flux, when not too inveterate. The wood of the tree, employed as fuel, makes a lively, ardent, laſting fire.

The leaves and flowers of common upright myrtle have an aſtringent quality, and are uſed for cleanſing the ſkin, contracting the fleſh, and ſtrengthening the fibres. From the flowers and young tops is drawn a diſtilled water that is deterſive, aſtringent, coſmetic, and uſed in gargles. A decoction of the flowers and leaves is applied in fomentations. The berries have a binding deterſive quality, and the chemical oil obtained from them is excellent for the hair, and uſed in pomatums, and moſt other external beautifiers of the face and ſkin. As an internal medicine, theſe berries have little merit: they enter, however, into the compoſition of ſeveral of the ſtrengthening plaiſters.

The common clove, a native of the Molucca iſlands, is

the unripe fruit of the caryophyllus aromaticus of Tournefort and Linnæus. The ripe fruit, the mother cloves, or antophilli of the ſhops, is ſeldom ſeen. It is a ſecret among ſome who deal largely in cloves, to keep them in a cellar or other damp place, where they will ſwell and encreaſe conſiderably in weight, and look much better, though they are, in effect, much worſe, than before ſuch management. The fable of the other trees bending to the royal clove, mentioned by Pomet and Lemery, is too abſurd to bear any animadverſions. The inhabitants of the iſland of Maſſia in the Eaſt Indies, where the royal clove grows, ſtring the fruit and make beads of it, which they wear about their necks, on account of the fragrancy of the ſmell.

Cloves, before they have attained maturity, are of a delightful colour. Some authors relate, that they are originally poſſeſſed of ſuch an attractive ſpungy quality, as frequently to drain, with facility, any liquids that ſtand near them; ſo that, unleſs the maſter of the ſhip, which conveys them from the iſlands, is very careful to keep them at a convenient diſtance from his liquors, a quantity of them will, in two days time, exhauſt and dry up a hogſhead of wine or water.

Pimento, all-ſpice, or Jamaica pepper, is the dried unripe fruit of the piper odoratum Jamaicenſe of Ray, the myrtus pimento of Linnæus; the bay-berry tree of ſome authors. It is a round fruit, with a duſkiſh, hard, rough, umbilicated rind, containing within it two black kernels, of an aromatic ſmell and taſte approaching to that of cloves, yet partaking, in ſome degree, of the odour and taſte of all the other ſpices, whence it has obtained the name of *all-ſpice*. The tree which produces it, riſes to the height of thirty or forty feet; and in a rich ſoil, will grow even to the height of an hundred feet. The leaves are like thoſe of the bay, but of a much ſtronger aromatic ſmell; the flowers ſtand in bunches, and are of a greeniſh colour; theſe are ſucceeded by the fruit, which the Negroes gather before it is ripe, and dry in the ſun; in drying, it becomes wrinkled and brown, hough formerly ſmooth and green. The tree grows naturally

turally in hilly places, in the north part of Jamaica. At Chriſtmas, they uſually adorn their churches in the Weſt Indies with ſmall boughs of pimento; as the churches in England are decked with holly and ivy at that ſacred ſeaſon.

All-ſpice is an excellent aromatic; it fortifies the heart and ſtomach, diſſipates wind, promotes urine and the catamenia, animates the blood and ſpirits, and removes all manner of obſtructions. Thus it is cordial, cephalic, aperient, ſtomachic and carminative. The oil of pimento, which is procured by diſtillation, ſinks in water like the oil of cloves.

HEXAGYNIA (from ἕξ, ſix; and γύνη, a woman, or wife). The name of an order or ſecondary diviſion in the Linnæan Syſtem, conſiſting of plants which, beſides their claſſic character, have their flowers furniſhed with ſix ſtyles or female organs. It is only to be found in the ninth and thirteenth claſſes of the Sexual Method.

HEXANDRIA (from ἕξ, ſix; and ἀνὴρ, a man, or huſband). The name of the ſixth claſs in Linnæus's Sexual Method, conſiſting of plants with hermaphrodite flowers which are furniſhed with ſix ſtamina or male organs that are of an equal length.

This numerous claſs of plants is divided into five orders or ſections, from the number of the ſtyles or female organs. Narciſſus, ſnow-drop, aloe, yucca, lily, crown imperial, aſphodel, ſpider-wort, flower-of-a-day, tulip, lion's leaf, dog's tooth violet, ſuperb lily, hyacinth, and ſeveral others, have one ſtyle or female organ: rice, velezia and atraphaxis, have two; dock, ſtar-flower, and medeola, three; guinea-hen weed, four; and water-plantain, five.

The claſs *hexandria* is diſtinguiſhed from the claſs *tetradynamia* of the ſame author by the proportion of the ſtamina, which, in the former, are of an equal length, in the latter, unequal; four ſtamina being long, and two ſhort.

HEXAPETALI, (from ἕξ, ſix, and πεταλον, a leaf). The name of two claſſes, or primary diviſions, in Rivinus's Method, conſiſting of plants with ſix petals, which are either of a regular, or irregular form.

HILUM, the external mark or ſcar of a ſeed in the place where it was faſtened within the *pericarpium*. It is conſpicuous in the bean, bladder-nut, and heart-ſeed.

HIRSUTIES. *Vide* PUBESCENTIA.

HOLERACEÆ (from *holus*, pot-herbs). The name of the twelfth order in Linnæus's Fragments of a Natural Method, conſiſting of plants which are uſed for the table, and enter into the œconomy of domeſtic affairs.

Liſt of the Genera *contained in this Order.*

SECTION I.

Hermaphrodite Plants.

Linnæan Genera.			*Engliſh Names.*
Anabaſis,	—	—	Berry-bearing glaſs-wort.
Anacardium,	—	—	Acajou, or caſhew-nut.
Atraphaxis.			
Baſella,	—	—	Malabar night-ſhade.
Beta,	—	—	Beet.
Blitum,	—	—	Blite, or ſtrawberry ſpinach.
Bucida.			
Calligonum.			
Callitriche,	—	—	Star-headed Water-Chickweed.
Camphoroſma.			
Chenopodium,	—	—	Gooſe-foot, or wild orach.
Coccoloba.			
Coriſpermum,	—	—	Tickſeed.
Heiſteria.			
Herniaria,	—	—	Rupture-wort.
Illecebrum,	—	—	Mountain knot-graſs, whitlow-graſs.
Laurus,	—	—	Bay, cinnamon, camphire, ſaſſafras, Avocato pear-tree, and benjamin-tree.
Mimuſops.			
Petiveria,			

Linnæan Genera.			*Engliſh Names.*
Petiveria,	—	—	Guinea-hen weed.
Polycnemum.			
Polygonum,	—	—	Knot-graſs, biſtort.
Rheum,	—	—	Rhubarb.
Rhizophora,	—	—	Mangrove, kandel of the Indians.
Rivina.			
Rumex,	—	—	Dock.
Salicornia,	—	—	Jointed glaſs-wort, or ſalt-wort.
Salſola,	—	—	Glaſs-wort.
Tinus.			
Winterania.			

SECTION II.

Male, Female, Androgynous and Polygamous Plants.

Atriplex,	—	—	Orach.
Axyris.			
Begonia.			
Ceratocarpus.			
Nyſſa,	—	—	The tupelo-tree.
Spinacia,	—	—	Spinach.

Habit and Structure of the Plants of this Order.

This very numerous order of plants contains trees, ſhrubs, and perennial and annual herbs; ſome of the woody vegetables, as the bay, caſhew-tree, and *atraphaxis*, retain their green leaves during the winter.

The ROOTS are very long, and frequently ſpindle-ſhaped; from the knots of the ſtems and branches of ſuch plants as creep on the ground, or float in the water, proceed fibrous and branched roots.

The STEMS and young branches are cylindric. In Malabar night-ſhade, they climb and are twiſted from left to right,

in the direction of the apparent diurnal motion of the ſun. In the greateſt part of the aquatic plants of this order, the ſtalks are hollow within. In ſome ſpecies of *polygonum*, the branches being ſtript of their leaves, appear to be terminated in a thorn.

The BUDS are of a conic form, and naked; that is, not accompanied with ſcales.

The LEAVES are generally ſimple, alternate, entire, and attached to the branches by a cylindric foot-ſtalk, which is ſometimes very long, as in the tupelo-tree, but generally very ſhort.—The leaves of glaſswort are ſhort, awl-ſhaped, fleſhy, and terminated with ſpines. In jointed glaſs-wort, the leaves appear to be nothing elſe than ſmall appendages of the articulations or joints of the branches.—In mountain knot-graſs the leaves are placed oppoſite; and in *polycnemum*, they are oppoſite at the bottom, and alternate at top.—Some plants of this order have two STIPULÆ or ſcales attached to the branches, near the origin of the foot-ſtalk of each leaf. Thoſe of mangrove are very large, ſurround the extremity of the branches, and envelop the young leaves, which in unfolding, puſh off the *ſtipulæ* that are placed above them.

In many plants, as the biſtorts, rhubarb, dock, and atraphaxis, inſtead of *ſtipulæ*, each leaf bears on its foot-ſtalk a membranaceous ſheath, which is cylindric, frequently fringed on the margin, and penetrated by the ſtem. In ſome ſpecies of polygonum, the vagina or ſheath in queſtion continues a long time after the fall of the leaves.

The FLOWERS in plants of the firſt ſection are hermaphrodite: in thoſe of the ſecond, male and female upon the ſame root, as in axyris; male and female upon different roots, as in ſpinach; hermaphrodite and male on the ſame root, as in begonia; hermaphrodite and female on the ſame root, as in orach; hermaphrodite and male on different roots, as in the tupelo-tree.

In tick-ſeed, and ſome ſpecies of wild orach, which belong to the firſt ſection, there are female flowers mixed with the hermaphrodite upon the ſame plant.

Many of the hermaphrodite flowers of the caſhew-nut prove barren.

The

The flowers proceed either ſingly, or in greater numbers, from the angles of the leaves; or terminate the branches in ſpikes, umbels, or panicles.

Theſe are the only ſtriking and eſſential characters of this numerous collection of plants: for, as they do not ſo properly conſtitute one natural order, as an aſſemblage of many, a deſcription of the parts of fructification would lead us to a ſeparate diſcuſſion of each genus, which is foreign to the deſign of the preſent work.

The caſhew-nut, or acajou, is a native of both Indies. It is a low, wide-ſpreading tree, and ſeldom exceeds twenty feet in height; the branches are crooked, ſtraggling, and covered with oval leaves reſembling thoſe of the ivy, or Engliſh dwarf-apple. The flowers are ſmall, white, and cut into five ſegments. Theſe are ſucceeded by the fruit, which is generally of a yellow colour, as large as an orange, of a conical form, with the leſſer end towards the ſtalk on which it grows. At the greateſt end, or outſide top of this fruit, ſometimes called the cherry, grows the ſtone commonly ſtiled the nut, quite bare, in the exact ſhape of a ſheep or hare's kidney, about an inch long, containing within it a large white kernel, of a fine taſte, which is roaſted and eaten. The inſide of the fruit or cherry is very ſtringy, and full of rough, aſtringent, but pleaſant juice, which in America is frequently uſed, like that of lemons with us, in making punch. The outer ſhell of the nut is of an aſh-colour, and very ſmooth. Under this outer rind is another which covers the kernel; between them is a thick black inflammable oil, which is very cauſtic.

When the Weſt-India young ladies fancy themſelves too much tanned by the ſcorching rays of the ſun, they gently ſcrape off the thin outſide ſkin of the ſtone, and then rub their face all over with the ſtone. This immediately ſwells and grows black; and the ſkin being thus poiſoned, will, in the ſpace of five or ſix days, come entirely off the face in large flakes, ſo that they cannot appear in public under a full fortnight; by which time the new ſkin looks as fair as that of a young child.

The negroes in Braſil cure themſelves effectually of diſorders in the ſtomach, by eating of the yellow fruit of the acajou, the juice of which being acid, cuts the thick tough humour which obſtructed the free circulation of the blood, and thus removes the complaint. This cure, however, is not voluntary; for their maſters, the Portugueſe, deny them any other ſuſtenance, and letting them looſe to the woods, where the caſhew-nuts grow in great abundance, leave it in their option to periſh by famine, or ſuſtain themſelves with what Nature had provided them.—It is this neceſſity which leads them to the fruit of the acajou, of which they are not fond; and after continuing the uſe of it for ſome days, they return to their maſters perfectly recovered from their indiſpoſition, and endued with ſtrength to perform their cuſtomary labour.

The milky juice of the caſhew-tree will ſtain linen of a deep black, which cannot be waſhed out again.

From the berries of climbing malabar night-ſhade, is drawn a beautiful red colour. The juice of theſe berries is ſaid to be uſed for ſtaining calicoes in India. The ſtalks and leaves of the plant are thick, ſtrong, and ſucculent.

Moſt of the ſpecies of wild orach have an aromatic fœtid ſmell. A ſpecies which grows near the coaſts of the Mediterranean is uſed by the Egyptians in ſallads, on account of its ſaltiſh aromatic taſte, which is agreeable.—From the ſame plant kelp is made in other countries.

Mangroves, the mangles of Plumier, are often forty or fifty feet high: they grow only in water, and on the banks of rivers where the tide flows up twice a day. They preſerve the verdure of their leaves throughout the year. From the loweſt branches iſſue long roots, which hang down to the water, and penetrate into the earth. In this poſition they reſemble ſo many arcades from five to ten feet high, which ſerve to ſupport the body of the tree, and even to advance it daily into the bed of the water. Theſe arcades are ſo cloſely intertwiſted one with another, that they form a kind of natural and tranſparent terrace, raiſed with ſuch ſolidity over the water, that one might

might walk upon them, were it not that the branches are too much encumbered with leaves. The moſt natural way of propagating theſe trees, is to ſuffer the ſeveral ſlender ſmall filaments which iſſue from the main branches, to take root in the earth. The moſt common method, however, is that of laying the ſmall lower branches in baſkets of mould or earth till they have taken root.

The deſcription juſt given pertains chiefly to a particular ſpecies of mangrove, termed by the Weſt-Indians, black mangles, on account of the brown duſky colour of the wood. The bark is very brown, ſmooth, pliant when green, and generally uſed in the Weſt-India iſlands for tanning leather. Below this bark lies a cuticle, which is lighter, thinner, and more tender. The wood is nearly of the ſame colour as the bark, hard, pliant, and very heavy. It is frequently uſed for fuel, for which purpoſe it is ſaid to be remarkably proper: the fires which are made of this wood being both clearer, more ardent and durable than thoſe made of any other materials whatever.—The wood is compact, almoſt incorruptible, never ſplinters, is eaſily worked, and, were it not for its enormous weight, would be commodiouſly employed in almoſt all kinds of work, as it poſſeſſes every property of good timber.—To the roots and branches of mangroves that are immerſed in the water, oyſters frequently attach themſelves; ſo that wherever this curious plant is found growing on the ſea-ſhore, oyſter-fiſhing is very eaſy; as in ſuch caſes, theſe ſhell-fiſh may be literally ſaid to be gathered upon trees.

The red mangles or mangrove, grows on the ſea-ſhore, and at the mouth of large rivers, but does not advance, like the former, into the water. It generally riſes to the height of twenty or thirty feet, with crooked, knotty branches, which proceed from all parts of the trunk. The bark is ſlender, of a brown colour, and, when young, is ſmooth, and adheres very cloſely to the wood; but when old, appears quite cracked, and is eaſily detached from it. Under this bark is a ſkin as thick as parchment, red, and adhering cloſely to the wood, from which it cannot be detached till the tree

is felled and dry. The wood is hard, compact, heavy, of a deep red, with a very fine grain. The pith or heart of the wood being cut into ſmall pieces, and boiled in water, imparts a very beautiful red to the liquid, which communicates the ſame colour to wool and linen. The great weight and hardneſs of the wood prevent it from being generally uſed. From the fruit of this tree, which, when ripe, is of a violet colour, and reſembles ſome grapes in taſte, is prepared an agreeable liquor, much eſteemed by the inhabitants of the Caribbee iſlands.

White mangles, ſo termed from the colour of its wood, grows like the two former, upon the banks of rivers, but is ſeldom found near the ſea. The bark is grey; the wood, as we have ſaid, white, and, when green, ſupple; but dries as ſoon as cut down, and becomes very light and brittle. This ſpecies is generally called rope-mangrove, from the uſe to which the bark is applied by the inhabitants of the Weſt Indies. This bark, which by reaſon of the great abundance of ſap, is eaſily detached, when green, from the wood, is beaten or bruiſed betwixt two ſtones, until the hard and woody part is totally ſeparated from that which is ſoft and tender. This laſt, which is the true cortical ſubſtance, is twiſted into ropes of all ſizes, which are exceedingly ſtrong, and not apt to rot in the water.

The aſhes of the glaſſworts and jointed glaſſworts, are uſed in making of glaſs and ſoap.

True rhubarb is the root of the *rheum palmatum* of Linnæus. The leaves are hand-ſhaped and pointed. The purgative quality of the root is too well known to be enlarged on in this place.

A ſpecies of rhubarb, called by the Arabians, *ribes*, grows naturally on mount Libanus, and other mountainous parts of Syria. The ſurface of the leaves is covered with warts or rough protuberances.—The monks in thoſe parts are ſaid to ſubſiſt principally upon this plant.

The avocato or avigato pear-tree, a native of the Weſt-India iſlands, ſo called from its fruit, which in form and thickneſs reſembles a pear, is the *laurus perſea* of Linnæus.

The

The pulpy or fleſhy part of the fruit is of a pale green, with little or no conſiſtence when ripe, and melts in the mouth like marrow, which it greatly reſembles in taſte.—The ſkin is ſmooth and thin, but of a ſtrong tough ſubſtance, and of a beautiful green colour, which does not become yellow till the fruit is perfectly ripe.—The fruit, by reaſon of its ſoftneſs, may be eaten out of the ſurrounding ſkin with a tea-ſpoon, like jelly and marmalade. It is frequently ſerved up, in the Weſt-Indies, on a plate with ſugar, roſe-water, and orange-flowers; moſt commonly, however, it is mixed with ſugar, and the juice of limes, which render it extremely palatable. The unripe fruit too is frequently plucked, and eaten in thin ſlices with pepper and ſalt. In this ſtage, the taſte of the avocato greatly reſembles that of artichoke. Every preparation of this fruit is eſteemed highly nouriſhing; as it warms, exhilarates, and fortifies the ſtomach.—It is particularly recommended in dyſenteries. In the middle of the pulpy part of the fruit lies the nut or ſeed, which is very large, almoſt round, of a pale ruſſet colour, a little wrinkled, contains no kernel within it, and whoſe degree of hardneſs does not exceed that of a cheſnut diveſted of its ſkin. This nut, about an hour after it is ſeparated from the fruit, ſplits of itſelf into two or three pieces. If committed to the ground in this ſtate, no vegetation enſues, becauſe the embryo of the ſeed is broken; ſo that ſuch as would propagate theſe plants from ſeed muſt ſow the nuts the moment they are taken out of the pulp; in which caſe they will begin to germinate in eight or ten days after. The bark and wood of this tree, which riſes to a conſiderable height, are of a greyiſh colour. The leaves are long, pointed, of a ſubſtance like leather, and of a beautiful green colour. The flowers are produced in large knots or cluſters at the extremities of the branches, and conſiſt each of ſix petals diſpoſed in the form of a ſtar, and of a dirty-white, or yellow colour, with an agreeable odour, which diffuſes itſelf to a conſiderable diſtance. The tree begins to bear fruit two years and a half, or at moſt three years after being planted; and, like moſt of the trees in warm climates, bears twice a year.

The buds of the avigato pear-tree are ſaid to be uſed with ſucceſs in ptiſans againſt the venereal diſeaſe. An infuſion of them in water, drunk in the morning faſting, is ſtrongly recommended for diſlodging coagulated blood in the ſtomach produced by a fall or a ſevere ſtroke on that important *viſcus*. "The wild boars in the Indies," ſays Labat, "eat greedily of the mammees and avigato pears, which give their fleſh a luſcious and moſt agreeable ſavour."

The wood of the *laurus borbonia*, or red bay of Carolina, is much eſteemed, being of a very fine grain; ſo is frequently made into cabinets, and other ornamental furniture. It dyes a beautiful-black colour.

Camphire-tree, the *Laurus Camphora* of Linnæus, the *Laurus Camphorifera* of Kæmpfer, grows naturally in the woods of the weſtern parts of Japan, as likewiſe in Sumatra, Borneo, and other parts of India. The root ſmells more of camphire than the other parts, and being boiled yields it. The bark of the ſtalk is, outwardly, ſomewhat rough; but in the inner ſurface, ſmooth and mucous, and therefore eaſily ſeparated from the wood, which is dry, and of a white colour. The leaves ſtand upon ſlender footſtalks, have an entire undulated margin, run out into a point, have the upper ſurface of a lively and ſhining green, the lower herbaceous and ſilky, and are furniſhed with a few lateral nerves, which ſtretch archwiſe to the circumference, and frequently terminate in ſmall warts; a circumſtance which may be conſidered as peculiar to this ſpecies of laurel. The flowers are produced on the tops of footſtalks, which proceed from the arm-pits of the leaves, but not till the tree has attained conſiderable age and ſize. The flower-ſtalks are ſlender, branched at the top, and divided into very ſhort pedicles, each ſupporting a ſingle flower. The flowers conſiſt of ſix white petals, and are ſucceeded by a purple ſhining berry, of the ſize of a pea, and in figure ſomewhat top ſhaped. It is compoſed of a ſoft pulpy ſubſtance, that is purple, and has the taſte of cloves and camphire, and of a *nucleus* or kernel, of the ſize of a pepper, that is covered with a black, ſhining, oily corticle, of an inſipid taſte.

Camphire-

Camphire-tree is known in Japan by the ſeveral names of Sſio, Kus-no-ki and Nambok. The ſubſtance termed camphire is procured by diſtilling the roots and branches of the tree in an alembic having a head made of twiſted and plaited ſtraw. All the humidity evaporates through the head, and the camphire ſticks to it. In this ſtate it is of a greyiſh colour; but, after being refined by ſublimation in a ſand-heat, it becomes white and tranſparent. Taken inwardly, camphire is cordial, ſudorific, and anodyne; uſed externally, it is a powerful diſcutient. The ancients believed it to be an enemy to generation, which proves to be a miſtake.

Subſtances reſembling camphire, and oil of camphire, are likewiſe obtained from the roots of Laurus Caſſia, termed by Kæmpfer Caſſia Canellifera, from the bark of which is alſo got, by diſtillation, an oil of cinnamon, and from the leaves, an oil of cloves. The ſame curious traveller informs us, that a camphire is depoſited in great abundance at the bottom of the oil obtained by diſtillation from the Arabian and Perſian Schœnanthus: and he doubts not that a ſimilar ſubſtance might be extracted from juniper and other plants, which have the camphire-ſmell, as the Bramins extract a ſugar from every ſweet, even from milk itſelf. A tree which grows naturally in Sumatra and Borneo yields a cryſtalline camphire, that is exceedingly precious and rare.

The tree which produces the gum or ſubſtance called benjamin is the *laurus benzoin* of Linnæus. The leaves are like thoſe of the citron and lemon-trees, only ſmaller, and leſs lucid.—Benjamin promotes expectoration, and is of great force and prevalence in the aſthma, and lingering phthifical coughs. "It is likewiſe endued," ſays Lemery, "with a virtue to provoke urine and perſpiration."

Saſſafras-tree, the *laurus ſaſſafras* of Linnæus, grows naturally in many parts of North America, particularly Florida, where there are whole foreſts of it. It has a very ſtrait trunk, which riſes about ten feet high. The branches on its top are covered with green leaves like thoſe of the fig-tree, which the inhabitants eſteem an excellent vulnerary, when

bruiſed,

bruiſed. The bark is reddiſh, thick, and rough, and more fragrant than the wood. When the wood is cut or raſped for uſe, the ſmell is ſo ſtrong that it occaſions the head-ach in thoſe that work upon it; as it likewiſe does in thoſe that uſe it, which has much leſſened its credit.—Uſed in infuſion like tea, the wood is a powerful antiſcorbutic.—In Carolina, a decoction of the wood and leaves has been adminiſtered with ſucceſs in intermitting fevers. In pains of the feet, an oil obtained from the broiled berries of ſaſſafras, rubbed into the part affected, though attended with a diſagreeable nauſea, never fails, ſays Kalm, to produce a ſpeedy and perfect cure.—The bark dyes an orange colour, that is particularly pleaſing to the eye, and does not fade in the ſun.—In New Jerſey, and other parts of North America, they waſh and ſcour the veſſels in which they intend to keep cyder, beer, or brandy, with water in which the ſaſſafras-root, or its peel, has been previouſly boiled—a precaution which they think renders all thoſe liquors both more palatable and more wholeſome. Some get their bed-poſts made of the wood of ſaſſafras, in order to expel the bugs: and in Penſylvania, for a ſimilar purpoſe, they put chips of it into their cheſts containing cloaths, and other woollen ſtuffs, to get rid of the larvæ and moths, which commonly ſettle in them in ſummer.—Saſſafras-wood, thrown into the fire, crackles like ſalt. It laſts, we are told, a long time under ground: yet is there hardly any kind of wood which, when expoſed to the air without cover, is more generally attacked by vermin, ſo as in a ſhort time to be quite worm-eaten through and through.

Cinnamon-tree, the *laurus cinnamomum* of Linnæus, is a native of the iſland of Ceylon in the Eaſt Indies. The leaves have three beautiful nerves, which run through the diſk or ſurface, and diſappear towards the top. The tree has three barks or rinds. The firſt and ſecond are only uſed; the third, and innermoſt, which incloſes the body of the tree, being never touched; not, as ſome have pretended, becauſe it is of no value; but becauſe an inciſion in it kills the tree. After three years time, the two extreme barks

are

are renewed, and fit to be pulled off. When the Dutch, ſay ſome authors, who ingroſs the whole trade of this and the other ſpiceries, are apprehenſive of abating the value of cinnamon, by ſending home too great abundance, and thereby glutting the European markets, they lay it on an heap, and burn as much of it as they imagine uſeleſs for their ſervice; which ſpicy mountain ſends out its fragrant exhalations for many leagues into the ſea; ſo that of theſe coaſts it may be truly affirmed, in the beautiful language of Milton, that

"Pleas'd with the grateful ſmell, old Ocean ſmiles."

The Dutch, not remarkable for honeſty in any of their dealings, are particularly fraudulent in conducting the ſpice trade: for they frequently extract a quantity of oil, eſſence, or ſpirits, from the cinnamon and cloves; and then confidently expoſe them for choice untainted commodities. Hence we often meet with ſeveral ſpiceries, cinnamon in particular, that are very dry and inſipid, almoſt devoid of ſmell and taſte, and pillaged of their oil and eſſential ſubſtance.—The fruit of the cinnamon-tree yields, by coction and expreſſion, an oily ſubſtance, of which candles are made for people of the firſt rank: and from the neck of the root is drawn a fine kind of camphire, of a ſpicy, aromatic ſmell, very rarely to be met with in Europe.

"In Siberia," ſays Gmelin, "they eat for ordinary food, the root of a ſpecies of *polygonum*, termed by ſome botaniſts, *biſtorta montana minor*; and by Haller, *biſtorta foliis ad oram nervoſis*. The natives call it *mouka*; and ſo indolent are they, that, to ſave themſelves the trouble of digging it out of the earth, they go in ſpring and pillage the holes of the mountain-rats, which they find filled with theſe roots."

White Beet, the *Beta Cicla* of Linnæus, is a variety of the common Beet well known to be cultivated in gardens, as are all its varieties, for the ſake of the leaves. I mention it in this place with a view of introducing a ſeries of experiments made by M. Margraaf, with a

view

view of extracting ſugar from the roots of this and ſome other vegetables. The plants which that ingenious philoſopher has examined chymically for the purpoſe juſt mentioned, are common in moſt countries, and demand neither a favourable ſoil, nor an aſſiduous culture.—Such are,

1° White Beet, *cicla officinarum*.

2° Skirret, *Sium Siſarum*.

3° Red Beet.

The roots of plants containing ſugar may be ſufficiently known by theſe characteriſtics. When cut into ſmall pieces, and carefully cleaned, they impreſs upon the palate a very agreeable ſenſation: and, if examined by the microſcope, exhibit a number of white cryſtalline particles, which are the ſugar of the plant. Sugar being a ſalt which is diſſolved in brandy, M. Margraaf imagined that it might likewiſe be extracted from vegetables with the aſſiſtance of that liquor. To determine the quantity of ſugar which might be diſſolved by this method, he put into a glaſs one ounce of the beſt and fineſt ſugar, well pulveriſed, with four ounces of the ſtrongeſt brandy. The whole being well digeſted, he made the mixture boil, and the ſugar was ſoon perfectly diſſolved. The ſolution being ſtill warm, he paſſed it through a very fine ſearce or ſieve into another veſſel. This he carefully ſtopped, and had the pleaſure at the end of eight days to find the ſugar reſtored, and formed anew into regular and beautiful cryſtals. To ſucceed in this experiment, it is neceſſary that the veſſel and the ſugar be well dried, and the ſpirit highly rectified.

Prepared by the experiment juſt related, the ingenious chymiſt cut into very thin ſlices ſome roots of White Beet, which he had ſelected for the purpoſe, and dried them before the fire, taking care, however, that they might not be burnt. He next reduced them to a groſs powder, which he a ſecond time dried, as it eaſily contracts humidity. Of this powder, whilſt ſtill hot, he put eight ounces into a glaſs veſſel, and poured over it ſixteen ounces of ſpirit ſo ſtrong that it kindled gun-powder. The veſſel being half full, he placed it, well ſtopped, into a ſand-heat, till the ſpirit began to boil:

ſtraking the powder at proper intervals, that it might not fall to the bottom.—As ſoon as the ſpirit had begun to boil, he removed the veſſel from the fire, and poured the mixture it contained as quickly as poſſible into a coarſe linen bag, ſqueezing it hard, in order to expreſs all the liquor. This he immediately paſſed, whilſt hot, through a finer cloth, into a glaſs veſſel, which he carefully ſtopped, and kept in a warm place. At firſt the liquor was diſturbed; but at the end of ſome weeks it had precipitated a cryſtalline ſediment, which had all the appearance and properties of ſugar in its leſs refined ſtate. By this firſt experiment, M. Margraaf extracted from the three roots formerly mentioned the following quantities of ſugar:

1. From half a pound of the root of White Beet, half an ounce of pure ſugar.

2. From half a pound of Skirret, an ounce and half of pure ſugar.

3. From the ſame quantity of Red Beet, an ounce and a quarter of ſugar equally pure.

Theſe experiments prove, that lime-water is not ſo neceſſary for drying and thickening the ſugar as certain chymiſts have pretended, ſince it certainly cryſtalliſes without it.

Being thus well aſſured from actual obſervation, that the plants in queſtion were poſſeſſed of a real ſugar, he next employed himſelf in diſcovering a leſs expenſive method of extracting it. Such an end, he thought, would moſt effectually be attained, 1°, by expreſſing the ſweet ſugar juice, purifying it, and diſpoſing it to cryſtallize by evaporation;—2°, by purifying the cryſtals which might reſult from the preceding operations.

Having taken with this view, a certain quantity of Skirret, he cut the freſh roots into very ſmall pieces, and having bruiſed them with all his ſtrength in an iron mortar, removed them into a linen bag, and expreſſed the juice by means of a preſs prepared for that purpoſe.—He then poured water upon the roots in the bag, and preſſed them a ſecond time. The liquor thus obtained he put into proper veſſels, and kept in a cool place for 48 hours, at the end of which time it was

clear, and a mealy ſubſtance had fallen to the bottom. He now, therefore, very gently paſſed the liquor through a fine linen cloth into another veſſel.

The firſt clarification thus accompliſhed, he added to the juice ſome whites of eggs, and then boiled the whole together in a copper pan, continuing to ſkim it, till there appeared no more impurities on the ſurface, and the liquor was as tranſparent as the brighteſt and beſt clarified wine. He boiled it a ſecond time in a leſſer pan, till it had loſt conſiderably of its quantity; and thus he continued, uſing ſtill ſmaller veſſels, till the liquor, originally thin, was reduced to a ſyrup of a pretty thick conſiſtence. This he kept in a warm place for ſix months, at the end of which time he found the ſugar collected upon the ſides of the veſſel in the form of cryſtals. To purify theſe, which was the ſecond and principal operation, he immerſed the veſſel containing them into warm water, and when the heat had rendered the mixture fluid, he poured over the liquor and the cryſtals into an earthen veſſel having a very large mouth, with a narrow bottom pierced with ſeveral holes. This veſſel he placed within another, and left them in this ſituation, in a temperate place. By degrees the ſyrup fell into the veſſel below, whilſt the cryſtals remained in the upper.

To render this raw ſugar ſtill purer, he now put it into a ſort of blotting paper folded in different forms, which he gently ſqueezed with his hand. It had the deſired effect: the paper imbibing much of the viſcous and tenacious ſyrup which was attached to the ſugar.

Thus freed of its impurities, he diſſolved it a ſecond time in water, paſſed it again through the fineſt linen, and boiled it to the conſiſtence of a thick ſyrup. He then added ſome lime-water, and after boiling it a-freſh, till it was ropy, took it off the fire, and kept ſtirring it till cool; when he once more poured it over into earthen veſſels of a conical form, ſtopped with wood. Theſe he put within other veſſels of the ſame form and ſubſtance, but thicker: and the cryſtals in the courſe of eight days being completely formed, he, after that period, ſuffered the ſyrup to flow into the lower

veſſel, and drying the ſugar by means of the blotting-paper as before, had the ſatisfaction to find it as pure and beautiful as the beſt ſugar which is produced from the ſugar-cane: and the ſyrup to ſerve the ſame purpoſes as common treacle.

By the ſame operation may ſugar be extracted from White and Red Beet. That of Skirret is ſuperior to the ſugar obtained from Red Beet: but the ſugar from the White Beet M. Margraaf affirms to be the beſt of all.

Continuing his experiments, this ingenious naturaliſt next eſſayed to extract ſugar from the ſtems and leaves of theſe plants; but from thoſe with all his efforts he could only obtain a ſort of earth.

Might it not be very advantageous for the poor inhabitants of the country to procure to themſelves a ſugar from ſuch common plants as have been mentioned, inſtead of purchaſing foreign ſugar at ſo dear a rate? In ſuch a caſe, it would not be neceſſary that they ſhould follow all the ſteps of the proceſs juſt deſcribed;—it would be ſufficient to expreſs the juice, to purify it a little, and boil it to the conſiſtence of a ſyrup.

Encouraged by the ſucceſs of theſe experiments—experiments which plainly evince that the countries which produce ſugar-canes, produce them not excluſively, ſince Nature has furniſhed every country with ſugar-plants—Margraaf has ſince extended his enquiries on the ſame ſubject to a great number of vegetables. I ſhall mention the reſult of a very few only. Carrot yields a very ſweet juice, but reſembling honey rather than ſugar. The ſame is affirmed of the Gourd. From Parſnip he procured a ſmall quantity of ſugar, as likwiſe from the American Aloe. The juice which is obtained from the Birch-tree by inciſion in water, yields a ſort of manna. Laſtly, grapes moiſtened, and then preſſed, give a ſyrup which contains a little ſugar.

HOROLOGIUM *Floræ*. *Vide* VIGILIÆ.

HYBERNACULUM, winter-quarters; defined by Linnæus to be a part of the plant which defends the embryo-herb from injuries during the ſeverities of winter. *Vide* BULBUS & GEMMA.

HYBRIDA *Plantæ*, a monſtrous production of two different ſpecies of plants, analogous to a mule among animals. —The ſeeds of hybrid plants will not propagate.

I.

ICOSANDRIA, (from εἴκοσι, twenty, and ἀνὴρ, a man or huſband); the name of the twelfth claſs in Linnæus's Sexual Method, conſiſting of plants with hermaphrodite flowers furniſhed with twenty or more ſtamina, that are inſerted into the inner ſide of the calyx, or petals, or both. By this laſt circumſtance, and not by the number of ſtamina, is the claſs in queſtion diſtinguiſhed from that immediately following it, termed *polyandria*, in which the number of ſtamina is frequently the ſame with that of the plants of the claſs *icoſandria*, but they are inſerted, not into the calyx or petals, but into the receptacle of the flower.

This nice and minute diſtinction requires the ſtricteſt attention, becauſe of the very different nature of the plants of theſe two claſſes. *Icoſandria* furniſhes the pulpy fruits that are moſt eſteemed, ſuch as apples, pears, pomegranates, medlars, gooſeberries, raſpberries, ſtrawberries, currants, almonds, peaches, plums, apricots, cherries, and guavas. The plants of the claſs *polyandria* are moſtly poiſonous: ſuch, for inſtance, are aconite, columbine, lark-ſpur, hellebore, virgin's bower, pæony, herb-chriſtopher, burning thorny plant, and ſome others.

Beſides the characters juſt mentioned, the plants of the claſs *icoſandria* have a hollow flower-cup compoſed of one leaf, to the inner ſide of which the petals are faſtened by their claws.

The orders in this claſs are five, founded upon the number of the ſtyles or female organs.

Mock-orange, myrtle, almond, and plum trees, have one female organ; wild ſervice has two; ſervice and ſeſuvium, three; medlar, apple, fig-marigold and ſpiræa, five; roſe, raſpberry, ſtrawberry, herb-bennet, and cinquefoil, an indefinite number.

IMPERFECTUS *Flos.* *Vide* APETALUS *Flos.*

IMPLETIO. *Vide* PLENUS *Flos.*

INCOMPLETÆ, the name of the ninth claſs in Royen's Natural Method, and the ſixteenth in Linnæus's *Methodus Calycina*; conſiſting of plants whoſe flowers want either the calyx or petals.

INCOMPLETUS *Flos.* *Vide* APETALUS *Flos.*

INFLORESCENTIA, (from *inflorеſco*, to flouriſh,) a mode of flowering; the manner in which flowers are ſupported on their footſtalks.

The various modes in which flowers are joined to the plant by the *pedunculus* or footſtalk, are expreſſed by the following terms:

VERTICILLUS.
SPICA.
CORYMBUS.
CAPITULUM.
FASCICULUS.
THYRSUS.
RACEMUS.
PANICULA.

Each of theſe terms is explained in its proper place.

We may here obſerve that the various modes of flowering juſt mentioned are equally applicable to thoſe flowers which proceed from the angle formed by the leaves and branches, as do moſt flowers, and to ſuch as terminate the ſtem and branches. In the former caſe, flowers are termed *axillares*, that is, proceeding from the arm-pit of the leaf: in the latter, *terminales*, that is, terminating the branch.

Some terms reſpecting infloreſcence will be explained under the article PEDUNCULUS, which ſee.

Infloreſcence affords an excellent characteriſtic mark in diſtinguiſhing the ſpecies of plants, but is never, according to Linnæus, to be employed as a generic difference. Many eminent botaniſts, however, among whom are Ray, Rivinus, Knaut, and Kramer, have employed it in diſcriminating the genera.

INTORSIO, a term of habit reſpecting the flexion or bending of any of the parts of a plant towards one ſide.

Twining Stems.

In hops, honeyſuckle, dioſcorea, black bryony, hippocratea, and moon-ſeed, the ſtalks twine to the left; in kidney-bean, convolvulus, Virginian-ſilk, quamoclit, and ſpurge, they bend towards the right.

Twining Claſpers or Tendrils.

Theſe wind to the right, and back again: of this kind are the tendrils of moſt of the pea-bloom or leguminous tribe of plants.

Twiſted Flowers.

In ſwallow wort, oleander, periwinkle, Virginian-ſilk, and ſtapelia, the petals bend to the left; in *pedicularis*, to the right.

The pointal in cucubalus, and viſcous campion, is twiſted to the left; as is the ſeed-bud in ſcrew-tree, and *ſpiræa ulmaria*.

The ſpikes of flowers in claytonia, and ſome ſpecies of rough-leaved plants, are ſpirally twiſted; in poppy, martagon lily, guinea-hen weed, and lizard's tail, they are bowed or crooked.

In oats, the beard which terminates the huſk is twiſted like a rope. The proper coat of the ſeeds of ſome ſpecies of geranium has a ſpiral tail of the ſame kind. This ſpecies of contorſion being affected by the moiſture or dryneſs of the atmoſphere is termed by Linnæus, *intorſio hygrometrica*.

To the different ſpecies of intorſion may be added the appearance of the petals in the European ſpecies of violet, oriental bugle, baſil, and a ſpecies of ſatyrium, in which the upper lip of the *corolla* looks towards the ground, and the under lip upwards. This appearance is termed by Linnæus, *reſupinatio*.

INUNDATA *Loca*, (*inundari*, to beover flowed,)—a term of ſoil—places covered with water.

INUNDATÆ, the name of the fifteenth order in Linnæus's Fragments of a Natural Method, conſiſting of plants which grow in the water.

Liſt of Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Ceratophyllum,	—	—	Horned pond-weed.
Elatine,	—	—	Water-wort.
Hippuris,	—	—	Female horſe-tail.
Myriophyllum,	—	—	Water-milfoil.
Potamogeton,	—	—	Pondweed.
Proſerpinaca.			
Ruppia.			
Zannichellia,	—	—	Triple-headed pondweed.

Habit and Structure of the Plants of this Order.

The plants of this order are aquatic, of low ſtature, herbaceous, and moſtly perennial.

The ROOTS are fibrous.

The STEM is generally wanting. In its place are an aſſemblage of leaves, which, wrapping or enfolding one another mutually, form a ſheath, from the middle of which is produced the foot-ſtalk of the flower.

The LEAVES are ſometimes alternate, ſometimes placed in whorls round the ſtem. In a great many genera, the foot-ſtalk is extended at its origin into a membranaceous ſubſtance forming a ſheath, that is cleft through the whole length, on the ſide oppoſite to the leaf.

In ſome ſpecies of pondweed the ſheath in queſtion is exactly like that of the graſſes, being terminated at the top, like the plants of that natural family, with a membranaceous triangular crown. In water-milfoil, ceratophyllum, and proſerpinaca, the footſtalk of the leaves forms no ſheath of this kind. The leaves of an aquatic plant of Madagaſcar, which

Adanſon affirms to be nearly alled to pondweed, are pierced through the ſieve in different places round the ribs.

Few, if any, of theſe plants are covered with down or hair.

The FLOWERS are hermaphrodite in pondweed, proſerpinaca, elatine, hippuris and ruppia; male and female on the ſame root in the reſt. Adanſon pretends, with what foundation I know not, that the flowers in ruppia are likewiſe male and female upon the ſame ſpike.

The diſpoſition of the flowers in this order ſerving frequently of itſelf to diſtinguiſh the genera, deſerves particular attention.

I. The flowers in water-milfoil, ceratophyllum, proſerpinaca, elatine and hippuris, proceed ſingly from the wings of the leaves. Thoſe of the lower leaves of water-milfoil are female; thoſe of the upper, male.

II. Triple-headed pondweed has two flowers in the ſame wing; one male and the other female.

III. The flowers in pondweed and *ruppia* are diſpoſed in ſpikes in the wings of the leaves. In *ruppia*, ſays Adanſon, male flowers are arranged on one ſide of the ſpike, and female flowers on the other.

The FLOWER-CUP is either wanting, as in hippuris and zannichellia; or conſiſts of three, four or five diviſions or leaves, which accompany the ſeed-bud to its maturity.

The PETALS are generally wanting.—*Elatine* has four petals, that are egg-ſhaped, blunt, and ſpreading. Pondweed has a like number.

The STAMINA are in number from one to ſixteen and upwards. The filaments, in ſome genera, are ſo ſhort, that they ſeem wanting.

The anthers or tops are ſhort, and generally marked with four longitudinal furrows. In ruppia, the anthers have one cell, and open at top.

The SEED-BUDS are in number from one to four. The ſtyle is frequently wanting.—In *proſerpinaca*, the ſeed-bud is placed below the receptacle of the flower.

The SEED-VESSEL is univerſally wanting, except in

elatine,

elatine, which has a dry capſule with four external openings, and the ſame number of cells.

The SEEDS are generally four in number.—In *ceratophyllum*, the fruit is a nut or ſtone, which is egg-ſhaped, pointed, and contains a ſingle cell.

INVOLUCRUM, (from *involvo*, to roll or wrap up) a ſpecies of calyx reſtricted by Linnæus to umbelliferous flowers.

It is placed below the common receptacle, which in theſe flowers is a number of foot-ſtalks, that proceed from the ſame centre, and riſe to the ſame height. Each foot-ſtalk is terminated with an umbel ſimilar in its form and ſtructure to the large umbel, and generally furniſhed like it with an *involucrum* or cover. When a calyx of this kind is placed under the longer or univerſal umbel, it is ſtiled an univerſal cover; when under the partial or ſmaller umbel, a partial cover. *Vide* UMBELLA & UMBELLATÆ.

Umbelliferous flowers, beſides the two covers already mentioned, have generally a proper perianthium or flower-cup under each of the florets of which the umbel is compoſed.

The partial *involucrum* of an umbelliferous flower is ſometimes termed *involucellum*, that is, leſſer cover.

The univerſal cover is either of one leaf, as in coriander and caraway; of three, as in angelica; of four, as in baſtard ſtone-parſley; of five, as in Macedonian parſley; of ſeven, as in lovage; or of many, as in laſerwort and water dropwort.

The partial cover conſiſts either of two leaves, as in artedia; of five, as in hare's ear; or of many, as in biſhop's weed and fennel giant.

In ſanicle, the univerſal, in coriander, the partial cover, goes but half way round the receptacle formed by the foot-ſtalks or rays of the umbel.

Thapſia, parſnep, alexanders, dill, burnet-ſaxifrage, and herb gerard, want both the univerſal and partial cover; ſhepherd's needle, chervil, maſterwort and ſeſeli, are furniſhed with the partial, but want the univerſal cover.

IRREGULARIS

IRREGULARIS *flos*, an irregular flower; a flower that wants uniformity; the term is generally applied to the petals, and is ſynonymous to the *anomalus* of Tournefort, and the *difformis* of Jungius and Chriſtian Knaut.

Examples of flowers with irregular petals are exhibited in the pea-bloom or leguminous tribe of plants, the lipped-flowers, violet, aconite, lark-ſpur, and ſome others.

IRREGULARES. The name of a diviſion in Rivinus's Method, conſiſting of plants which have irregular flowers. *Vide ſupra.*

ISOSTEMONES (from ἴσος, equal, and ſtamen). The name of a claſs in Haller's Natural Method, conſiſting of plants whoſe ſtamina or male organs of generation are equal in number to the petals. Such are pimpernel, campanula, night-ſhade, bryony, borage, apocynum, and the umbelliferous flowers.

Moſt of Linnæus's claſs *pentandria* belong to this diviſion of Haller.

JULIFERÆ, (from *julus*, a catkin, and *fero*, to bear,) trees bearing flowers in catkins. The name of a claſs in Hermannus's Syſtem, correſponding to the *amentaceæ* of Boerhaave and Tournefort. *Vide* AMENTACEÆ and AMENTACEUS *flos*.

JULUS, (Ἶλος, lanugo, quæ ἵεται ὕλη, exit mollis). Catkin. By this term, as likewiſe by the names, *nucamentum* and *catulus*, ſome former botaniſts diſtinguiſhed the ſpecies of calyx called by Linnæus *Amentum*, which ſee. The term is manifeſtly as old as Pliny, who, in the 39th Chapter of the 16th Book of his Natural Hiſtory, uſes it of the hazel-tree, an amentaceous or catkin-bearing plant.——*Ferunt et Avellanæ Julos compactili callo ad nihil utiles.*

L.

LABIATUS *flos*, a lipped-flower; a flower conſiſting of one irregular petal whoſe diviſions reſemble two lips. The lipped-flowers conſtitute a claſs in Tournefort's Method, by

by the name of *labiati*, and are the *didynamia gymnoſpermia* of Linnæus, and the *verticillatæ* of Ray; by which name, likewiſe, they are diſtinguiſhed in Linnæus's Fragments of a Natural Method. *Vide* VERTICILLATÆ.

Mint, thyme, marjoram, balm, dead nettle, and hyſſop, furniſh examples of the term in queſtion. Lipped-flowers make part of the grinning or gaping flowers of Linnæus. *Vide* COROLLA *ringens*.

LACINIÆ, (properly fringes, lappets, pieces, or jags.) In botanical language the ſeveral ſections of the calyx, petals, and piſtillum. The term is likewiſe applied to leaves.

LACTESCENTIA, (from *lac*, milk). A term of habit reſpecting the juices or liquors, of whatever colour, which flow out of plants when any injury is done them.

The colour of the juices in queſtion is either

White, as in burning thorny plant, poppy, ſwallow-wort, apocynum, cynanchum, campanula, cardinal flower, ſheep-ſcabious, maple, ſumach, milk-parſley, a ſpecies of melon-thiſtle, ſow-thiſtle, dandelion, hawk-weed, nipple-wort, and the other compound flowers with flat or tongue-ſhaped florets, the *ſemifloſculoſi* of Tournefort, the *flores ligulati* of Linnæus.

Yellow, as in celandine, *bocconia*, and puccoon.

Red, as in bloody dock.

Moſt lacteſcent plants are poiſonous, except thoſe with compound flowers, which are generally of an innocent quality.

Of the poiſonous lacteſcent plants the moſt remarkable are ſumach, agaric, maple, burning thorny plant, caſſada, celandine, puccoon, prickly poppy, and the plants of the natural order *contortæ*, as ſwallow-wort, apocynum, cynanchum, and cerbera.

The bell-ſhaped flowers are partly noxious, as cardinal flower; partly innocent, as campanula.

Among the lacteſcent plants with compound flowers that are innocent in their quality, may be mentioned dandelion, picris, hyoſeris, wild lettuce, gum-ſuccory, hawkweed,

baſtard

baſtard hawkweed, hypochœris, goat's beard, and moſt ſpecies of lettuce: I ſay moſt ſpecies, becauſe the prickly ſpecies of that genus are of a very virulent and poiſonous nature.

LACTESCENTES. The name of a claſs in Moriſon's Method, conſiſting of plants with compound flowets which abound with a white milky liquor. Such are the ſemi-floſculoſi of Tournefort, juſt mentioned. *Vide ſupra.*

LAMINA, a plate; the upper ſpreading part of a flower conſiſting of more than one petal. *Vide* COROLLA.

LANA, wool; a ſpecies of pubeſcence, down or velvet, which ſerves, according to Linnæus, as a veil to ſcreen the leaves and branches which are covered with it from the extremities of heat.

The appearance in queſtion is very conſpicuous in horehound, mullein, ſtachys, ſage and iron-wort of canary, woolly thiſtle, and ſome others.

LEGUMEN, (properly all manner of pulſe, as peaſe, beans, &c.)—that ſpecies of the ſeed-veſſel termed a pod, in which the ſeeds are faſtened along one ſuture only. In this laſt circumſtance, the ſeed-veſſel in queſtion differs from the other kind of pod, termed by botaniſts *ſiliqua*, in which the incloſed ſeeds are faſtened alternately to both the ſutures or joinings of the valves. *Vide* SILIQUA.

The ſeed-veſſel of all the pea-bloom or butterfly-ſhaped flowers, the *diadelphia* of Linnæus, is of the leguminous kind. Such, for inſtance, is the ſeed veſſel of the pea, vetch, lupine and broom. *Vide* PAPILIONACEÆ.

The valves or external openings for the purpoſe of diſperſing the ſeeds are, in both kinds of pod, two in number.

LEGUMINOSÆ (from *legumen*). The name of a claſs in Moriſon, Hermannus, Boerhaave, Ray, and Royen, conſiſting of plants whoſe ſeeds are incloſed in a leguminous pod. The term correſponds to the *papilionacei* of Tournefort and Pontedera, and the *diadelphia* of Linnæus in his Sexual Syſtem. *Vide* LEGUMEN.

LIBER, the inner bark or rind of plants. For a particular deſcription of the bark, and the other internal organized

nized parts of vegetables, the reader is referred to the article STRUCTURA VEGETABILIS.

LIGNUM, the wood. *Vide* STRUCTURA VEGETABILIS.

LIGULATUS *flos*, (from *ligula*, a ſtrap or fillet) a ſpecies of compound flower ſo termed by Linnæus, all the florets or partial flowers of which are flat or tongue-ſhaped, and expanded towards the outer ſide.

Of this kind are dandelion, ſow-thiſtle, lettuce, ſuccory, nipple-wort, hawkweed, goat's beard, ſcorzonera, picris, and ſome others. The flowers in queſtion correſpond to the *ſemifloſculoſi* of Tournefort, the *lingulati* of Pontedera, the *planipetali* of Boerhaave and Ray, the *cichoracei* and *acanaceæ* of Cæſalpinus, and the *lacteſcentes* of Moriſon.

Theſe plants generally abound with a milky juice, which is of an innocent quality.

LILIACEI, (from *lilium*, a lily). The name of the ninth claſs in Tournefort's Method, conſiſting of plants, whoſe flowers reſemble thoſe of the lily, being generally compoſed of ſix regular petals; ſometimes, however, of three, or even of one that is deeply divided into ſix parts. The ſeeds of the liliaceous flowers are generally contained within a capſule having three cells.—Aſphodel, lily-aſphodel, hyacinth, grape-hyacinth, meadow ſaffron, bulbocodium, crocus, narciſſus, iris, corn-flag, aloe, Adam's needle, Indian flowering reed, ginger, blood-flower, flower-of-a-day, ſpiderwort, lily, ſquill, crown imperial, tulip, dog's tooth violet, ſuperb lily, ſtar of Bethlehem, *aphyllanthes*, leek, onion, garlick, amaryllis, ſnow-drop, and bermudiana, are the liliaceous flowers of Tournefort.

LILIACEÆ is likewiſe the name of an order in the former editions of Linnæus's Fragments of a Natural Method, conſiſting of only four genera: viz, the lily, tulip, dog's-tooth violet, and crown imperial; which, in the later editions, are arranged with ſeveral other genera, under an order diſtinguiſhed, ſomewhat improperly, by the name of *coronariæ*. *Vide* CORONARIÆ.

LILIA. The name of the ſecond claſs in Royen's Natural

Natural Method, correſponding to the liliaceous flowers of Tournefort, and the *coronariæ* of Linnæus.

LIMBUS, (properly a lace, border, or fringe,)—the *limb*, or upper expanded part of a flower conſiſting of only one petal: oppoſed to the tube, which is the loweſt part.

The limb is either bell-ſhaped, funnel-ſhaped, ſalver-ſhaped, wheel-ſhaped, or gaping. *Vide* COROLLA.

LINGULATUS *flos*. *Vide* LIGULATUS *flos*.

LINGULATI, the name of a claſs in Pontedera's Syſtem, conſiſting of compound flowers with flat tongue-ſhaped petals. It correſponds to the *ſemifloſculoſi* of Tournefort, the *planipetalæ* of Ray, and the *compoſiti ligulati* of Linnæus, and is exemplified in dandelion and endive. *Vide* SEMIFLOSCULOSI, &c.

LOCULAMENTA and LOCULI, cells or pockets. The internal diviſions of a capſule or other dry ſeed-veſſel ſo termed. *Vide* CAPSULA.

Theſe cells incloſe the ſeeds, and are either one in number, as in primroſe and gentian; two, as in hen-bane, tobacco and thorn-apple; three, as in lily, hyacinth, aloe, and Adam's needle; four, as in ſpindle-tree, penæa and blæria; five, as in winter-green and rue; ſix, as in aſarabacca and birth-wort; eight, as in a ſpecies of flax, called *radiola*; ten, as in moſt ſpecies of flax; many, as in water-lily.

The term LOCULUS is alſo ſometimes uſed to expreſs the minute diviſions in ſome ſpecies of *anthers* which contain the fine impalpable powder, ſuppoſed by the Sexualiſts to be the principal agent in the generation of plants.

LOCUSTA, Ray's term for the huſky calyx of the graſſes. *Gluma* is now ſubſtituted in its place. *Vide* GLUMA.

LOMENTACEÆ, (from *lomentum*, a colour, waſh, or dye, à *lotum*, as *fomentum* à *fotum*—likewiſe Bean-meal).—The name of the thirty-third order in Linnæus's Fragments of a Natural Method, conſiſting of plants, many of which furniſh beautiful tinctures or dyes, and whoſe *pericarpium*, univerſally (*polygala* excepted,) a leguminous pod, contains ſeeds that are farinaceous or meally, like thoſe of the bean.

Note.

Note.—Which of theſe characters, or whether both in conjunction, determined Linnæus to affix the name *Lomentaceæ* to the following genera, we poſſeſs no means of aſcertaining: and it ſeems rather ſtrange, that Giſeke and Fabricius, who lately publiſhed Linnæus's own Explanations of his Natural Orders, have not offered a ſingle word on the ſubject.

Linnæan Genera.			*Engliſh Names.*
Adenanthera,	—	—	Baſtard flower-fence.
Bauhinia,	—	—	Mountain-ebony.
Cæſalpinia,	—	—	Braſiletto.
Caſſia,	—	—	Wild ſenna.
Ceratonia,	—	—	Carob-tree, or St. John's bread.
Cercis,	—	—	Judas tree.
Gleditſia,	—	—	Honey-locuſt, or triple-thorned acacia.
Guilandina,	—	—	Bonduc, or nickar-tree.
Hæmatoxylon,	—	—	Logwood.
Hymenæa,	—	—	Locuſt-tree or courbaril.
Mimoſa,	—	—	Senſitive plant, acacia, &c.
Parkinſonia.			
Poinciana,	—	—	Barbadoes flower-fence, or Spaniſh carnation.
Polygala,	—	—	Milkwort.

This order, in its general appearance, ſo nearly reſembles the pea-bloom or butterfly-ſhaped flowers, that, to avoid repetitions, we ſhall only, in this place, mention the few circumſtances in which the two orders differ.

I. In all the plants of this order, except milk-wort, the filaments of the ſtamina are diſtinct.

II. The flower is not ſhaped like a butterfly, but is leſs irregular, and frequently conſiſts of but one petal.

The LEAVES are either ſimple, as in judas-tree; or winged, as in the greater number.

The

The SEEDS are generally marked with a circular furrow on both ſurfaces.

The plants of this natural order, like thoſe of the leguminous tribe, are generally mucilaginous. From the inner bark of the greater number exſudes, either naturally or by inciſion, a mucilaginous liquor, which, in acacia and courbaril, dries upon the plant, and becomes a gummy ſubſtance.

Braſiletto, or Braſil-wood, the *Ceſalpinia Braſilienſis* of Linnæus, is much uſed by dyers. The tree, from which it is cut, is very thick and large, and has long branches that bear a vaſt quantity of little roundiſh leaves, of a fine ſhining green. The bark is reddiſh and thorny. The heart of the wood only is uſed; it is ſaid to have the ſame virtue with red ſanders, but is little uſed in medicine. Boiled in water with a little allum, Braſil-wood will ſtrike a red dye into eggs that are boiled along with it; it is alſo uſed for colouring althea roots to clean the teeth. The raſpings of Braſil-wood, infuſed in vinegar with a little gum arabick and allum, produce a beautiful blood-red tincture, which ſerves either for ink, or for dying of ſkins, book-covers, and the like. The ſame raſpings, infuſed in water, ſerve for the dying of wool, which will not turn purple, nor eaſily ſuffer decay.

Cæſalpinia Sappan, the Lignum Sappan of Rumphius, the Tſiam Pangam of the *Hortus Malabaricus*, is a native of both Indies, and, in its general habit, reſembles ſome of the Acacias. The tree riſes with a very prickly ſtem, from which proceed branches that are covered with large winged leaves. The flowers are yellow, grow in cluſters, and are ſucceeded by very broad ſmooth pods. The wood, termed Sappan, is of a red colour, and uſed in dying like Braſiletto, which it nearly reſembles.

The caſſia fiſtula tree, the fruit of which is an approved medicine, grows naturally in the Eaſt and Weſt Indies, as well as in Egypt, and ſeveral parts of Aſia. Its height, when full grown, often exceeds thirty or forty feet. The bark,

bark, eſpecially upon the trunk, is very much furrowed and cracked; the wood is white and ſoft; the tree generally branches pretty near the top, and bears ſeveral middle-ſized ſharp-pointed green leaves. The flowers are produced in cluſters, and conſiſt each of five petals, which are of a yellow colour and agreeable ſmell, and are ſucceeded by blackiſh pods, from ten to twenty inches long, and about three quarters of an inch diameter, having a ſeam running the whole length on the one ſide, and another leſs viſible on the other. The excellence of caſſia is generally eſtimated by the length, thickneſs and weight of the pods which contain it. The inſide is divided into a great many cells, ſeparated from each other by thin brittle plates or partitions, covered with a black ſweet pulp; between theſe partitions are placed the ſeeds, which are ſmall, flat and ſmooth. The pulp is the part which is uſed in medicine. It gently looſens the belly, and ejects the fæces without occaſioning gripes. —M. Labat relates that the caſſia-pods uſed formerly to be preſerved as comfits, and ſent to Europe, where they were adminiſtered as a gentle and agreeable purgative. The pods ſo preſerved were gathered when extremely tender, and about two or three inches only in length; ſo that pod, pulp and all, were equally uſed, and equally eſteemed. The flowers were preſerved in like manner, and preſcribed with ſucceſs in ſimilar diſorders.—Caſſia fiſtula is thus prepared in Egypt. The pods are collected before they are quite ripe, and carried into a very cloſe room, in which has been previouſly prepared a bed of palm-leaves and ſtraw, ſix inches thick. On this they lay the pods in a heap; the door is then cloſely ſhut; and the next day they ſprinkle water on the heap, which is repeated the day following.—In this manner they lie heaped for forty days, till they become black; others dig a hole in the ground to put them in; but this method is greatly inferior to the former.—It is to the Arabians we owe the knowledge of the medicine in queſtion; the Greeks and Romans being entirely unacquainted with it. The Alexandrian caſſia is the beſt; what we principally uſe, however, is the American, on account of the ſcarcity

of the former. The Brazil caſſia is aſtringent while green, but purges twice as ſtrongly as any other kind when ripe. The chief excellence of caſſia is, that it is a proper purge in all inflammatory caſes, which cannot be affirmed of any other known cathartic.

Senna of the ſhops is the leaf of the *caſſia ſenna* of Linnæus. The ſhrub which produces it is about a foot high, and grows naturally in Egypt, and ſeveral parts of the Levant. The fineſt ſenna is that from Alexandria, called by the Turks palte, which pays a conſiderable tribute to the Grand Signor. This ſort bears narrow leaves of a moderate ſize, lancet ſhaped, yellowiſh, and of a ſtrong, ſweet, fragrant ſmell.

The Tripoli ſenna, which is green, comes next in virtue to the Alexandrian, but is eaſily diſtinguiſhed by its little ſmell.

Caſſia Javanica, or broad-podded caſſia, is a native of Java, Braſil, and other parts of both Indies. It has compound winged leaves, conſiſting of twelve or fourteen pair of lobes, fleſh-coloured flowers, and very large, thick, three-ribbed pods. In America this ſpecies of caſſia is commonly known by the name of Horſe-Caſſia, from the black purging pulp which ſurrounds the ſeeds being generally adminiſtered in medicine to horſes only, on account of its griping quality. In the ſhops this ſpecies is termed purging caſſia of Braſil.

Kalm aſſerts that *Caſſia Chamæcriſta*, which grows abundantly in the woods of North-America, and whoſe leaves reſemble thoſe of the ſenſitive plant, poſſeſſes likewiſe the quality of contracting them when touched, in common with the leaves of the latter.

The flowers of the Canada ſpecies of judas tree, commonly called red-bud tree, are frequently put into ſalads by the inhabitants of that country. The French too ſometimes pickle them; but they have little flavour.

The wood of the common judas tree, called by the Portugueſe, the tree of love, is very beautifully veined with black and green, and admits of an exceeding fine poliſh.

The roots of moringa, a ſpecies of *guilandina*, are ſcraped when

when young, and uſed by the inhabitants of the iſland of Ceylon, and the Malabar coaſt, where the tree naturally grows, as thoſe of horſe-radiſh are in Europe. The wood dyes a beautiful blue colour.

Logwood, or Campeachy-wood, grows naturally in the Bay of Campeachy, at Honduras, and other parts of the Spaniſh Weſt-Indies. It is much eſteemed among the dyers and hatters for the fine purple and black colours which it produces. Pomet and Lemery have confounded this tree with that which produces the pimento or allſpice. The latter is the myrtus pimento of Linnæus. *Vide* HESPERIDEÆ.

The ſpecies of acacia which produces gum-arabic, frankincenſe, and the *ſuccus acaciæ*, is the *mimoſa nilotica* of Linnæus, and not the *mimoſa ſenegal*, as was long imagined. The gum is gathered in vaſt quantities from the trees growing in Arabia Petræa, at the foot of Mount Sinai, whence they bring the frankincenſe, called by the dealers in drugs in Egypt, gum-thus, from Thur or Thor, the name of a harbour in the North Bay of the Red-Sea, near Mount Sinai; thereby diſtinguiſhing it from the gum-arabic, which is brought from Suez, another port of the Red-Sea, not far from Cairo.—Beſides the different places from which theſe gums are brought, they differ alſo in ſome other particulars. Frankincenſe is pellucid, of a white colour, brittle, and eaſily pulverized; gum-arabic is leſs pellucid, and of a brown or dirty-yellow colour.

Succus acaciæ is an inſpiſſated juice obtained by expreſſion from the pods of the ſame ſpecies of acacia which produces the two valuable ſubſtances already mentioned. It is generally expreſſed before the fruit is ripe, and is black without, and reddiſh or yellowiſh within.

In its general habit, *mimoſa nilotica* has certainly a great reſemblance to that ſpecies of acacia which produces the gum-ſenega.—We have, therefore, the leſs reaſon to be ſurprized, that it ſhould ſo long, by the undiſcerning, have been confounded with it. They may be diſtinguiſhed by the following characters. Gum-ſenega acacia, the *mimoſa ſene-*

gal of Linnæus, is covered with a white, true acacia, or acacia of the Nile, with a purple, bark. The former, too, protrudes its thorns at the inſertion of the leaves by threes; the latter by pairs. Two thorns likewiſe accompany the doubly-winged leaves of another ſpecies of acacia, which acacia of the Nile much reſembles, the *mimoſa farneſiana* of Linnæus, known in the Weſt-Indies by the name of ſponge-tree, and remarkable for the fragrancy of its flowers; but theſe thorns are not ſo long as in the true acacia, which alſo has its heads of flowers furniſhed with footſtalks; whereas, in ſponge-tree, footſtalks are wanting to the flowers.

Gum-Senega or Senegal, juſt mentioned, is produced from a tree which grows plentifully in ſeveral parts of Arabia, and of Africa, particularly in Guinea and Negro-land, whence it is brought by the blacks, who carry it on their back, or on camels, in panniers made of palm leaves, to Senegal, and from this laſt place it is tranſported to the ſeveral parts of Europe. It is generally brought to us in large pieces; and, what is commonly ſold for gum-arabic, is nothing elſe than gum-ſenega, broken into ſmall pieces. The gum in queſtion is pectoral, moiſtening and refreſhing, gives conſiſtence to the humours, when they become too ſerous, cures rheums, and is reckoned ſpecific in dyſenteries, the piles, and other hæmorrhages. It is, however, principally in the manufacture of various ſtuffs, and of ſeveral dying materials, that a large quantity of it is conſumed, and its chief uſe and excellence conſiſt.

The Senſitive and Humble plants are arranged by Linnæus under the ſame genus with the acacias. Theſe are well known to poſſeſs a kind of muſcular motion, by which the leaves and ſtalks are contracted and fall down, upon being ſlightly touched, or ſhaken with ſome degree of violence. The ſenſibility of theſe plants is lodged in the young branches, in the common foot-ſtalk of the winged leaves, and in the nerve or middle rib to which the lobes or leſſer leaves are attached. Theſe different motions, which ſeem to be totally independent of one another, may be aptly enough

compared

compared, by analogy, with the irritability of certain parts in animals.

The ſenſitive plant has two kinds of motion; the one natural, occaſioned by the action of warm nouriſhing vapours; the other artificial, in conſequence of being touched or ſhaken.

M. Duhamel having obſerved, about the fifteenth of September, in moderate weather, the natural motion of a branch of ſenſitive plant, remarked, that at nine in the morning, it formed with the ſtem an angle of one hundred degrees; at noon, of one hundred and twelve degrees; at three afternoon, it returned to one hundred; and after touching the branch, the angle was reduced to ninety. Three quarters of an hour after, it had mounted to one hundred and twelve; and, at eight at night, it deſcended again, without being touched, to ninety.

The day after, in finer weather, the ſame branch, at eight in the morning, made an angle of one hundred and thirty-five degrees with the ſtem; after being touched, the angle was diminiſhed to eighty; an hour after, it roſe again to one hundred and thirty-five; being touched a ſecond time, it deſcended again to eighty; an hour and a half after, it had riſen to one hundred and forty-five; and upon being touched a third time, deſcended to one hundred and thirty-five, and remained in that poſition till five o'clock in the afternoon; when being touched a fourth time, it fell to one hundred and ten.

With whatever body the ſenſitive plant is touched or irritated, it is remarkable that the ſenſibility reſides particularly in the articulation or joining either of the branches of the common foot-ſtalk, or of the particular foot-ſtalk of each wing.

The time which a branch requires to recover itſelf after being touched, varies according to the vigour of the plant, the hour of the day, the ſeaſon of the year, or the heat and other circumſtances of the atmoſphere.

The order in which the parts recover themſelves, varies in like manner: ſometimes it is the common foot-ſtalk;

ſometimes the rib to which the lobes are attached; and ſometimes the lobes themſelves are expanded, before the other parts have made any attempt to be reinſtated in their former poſition.

If, without ſhaking the other ſmaller leaves, we cut off the half of a lobe belonging to the laſt pair, at the extremity or ſummit of a wing, the leaf cut and its antagoniſt, that is to ſay, the firſt pair, begin to approach each other; then the ſecond; and ſo on ſucceſſively, till all the leſſer leaves of that wing have collapſed in like manner. Frequently, after twelve or fifteen ſeconds, the lobes of the other wings, which were not immediately affected by the ſtroke, ſhut; whilſt the ſtalk and its wing, beginning at the bottom and proceeding in order to the top, gradually recover themſelves.

If, inſtead of one of the leſſer extreme leaves, we cut off one belonging to the pair that is next the footſtalk, its antagoniſt ſhuts, as do the other pairs ſucceſſively, from the bottom to the top.

If all the lobes of one ſide of a wing be cut off, the oppoſite lobes are not affected, but remain expanded.

With ſome addreſs it is poſſible even to cut off a branch without hurting the leaves or making them fall.

The common foot-ſtalk of the winged leaves being cut as far as three fourths of its diameter, all the parts which hang down collapſe, but quickly recover, without appearing to have ſuffered any conſiderable violence by the ſhock.

An inciſion being made into one of the principal branches, to the depth of one half the diameter, the branches ſituated betwixt the ſection and the root will fall down: thoſe above the inciſion remain as before, and the leſſer leaves continue open; but this direction is ſoon deſtroyed, by cutting off one of the lobes at the extremity, as was obſerved above.

Laſtly, a whole wing being cut off with precaution near its inſertion into the common foot-ſtalk, the other wings are not affected by it, and its own lobes do not ſhut. No motion, likewiſe, enſues from piercing the branch with a needle or other ſharp inſtrument.

From the preceding experiments, moſt of which I have myſelf

myſelf made, and from many others, which, for brevity's ſake, I forbear to mention, theſe inferences are clearly to be deduced.

I. That when the plant is in its greateſt vegetative force, its motions are greater and more ſenſible.

II. That when the ſky is ſerene, and the ſun bright during the whole day, the plant is more ſenſible in the morning than at noon.

III. That in the circumſtances in which they are leſs ſenſible, the leaves continue to fold and collapſe, although the foot-ſtalks, which through age become ſtiff and woody, have loſt their motion.

IV. That a ſtroke, or an irritation, produces a more forcible effect than an inciſion or even an entire ſection.

V. That a ſlight irritation only acts upon the neighbouring parts, and extends its influence in proportion to its force.

VI. That any given irritation acts more ſtrongly upon ſome parts than on others.

VII. That whatever can produce any effect upon the organs of animals, acts upon the ſenſitive; as a ſtroke, exceſs of heat or cold, the ſteam of boiling water, that of ſulphur and volatile ſpirits, &c.

VIII. That plunging it in water, or lodging it in the exhauſted receiver of an air-pump, ſeems to have no other effect than that of diminiſhing its vigour.

IX. That there appears to be no more intimate communication betwixt the oppoſite lobes of a winged or pinnated leaf, than betwixt the other parts of the plant.

X. That the muſcular motion of the ſenſitive plant is owing to a ſtrong contraction: each footſtalk ſeems to be terminated with a kind of joint, on which the leaves turn in all directions with ſurpriſing facility.

Different from all the kinds of ſenſitive plants yet known, is the dionæa muſcipula, a native of the Swamps of North America. The plant, which is of very long growth, and riſes with a naked ſtalk, is garniſhed at the bottom with eight or nine ſimple leaves with winged foot-ſtalks, which proceed

immediately from the root. In the figure and ſenſibility of theſe leaves, conſiſts the ſingularity of the plant. Each leaf is almoſt round, *ciliated*, that is, fringed like an eye-laſh, and runs out into a foot-ſtalk, which is not, as I ſaid, of equal breadth throughout, but is gradually enlarged towards the top. Upon touching the leaves in cold weather, no ſenſible contraction enſues; in warm weather, and particularly at noon, it is very ſtrong. But what is moſt remarkable of this plant is, its rare way of deſtroying flies and other inſects which approach it. A fly no ſooner touches the middle of the upper ſurface of the leaf, than its lobes, moving as by a ſpring, cruſh the inſect to death; the *cilia*, teeth or feelers at the margin, by their inoſculations, producing ſo tight a compreſſion, as quickly to occaſion that event. No accurate trials have yet been made with reſpect to the intenſity of the contraction at different times, and the difference of aptitude in the plant to recover its former direction.

If we except the number of its ſtamina, which are ten, *Dionæa* has a conſiderable reſemblance to the plants of the genus *Droſera*, commonly called *Ros ſolis* or ſun-dew, in the leaves of the Cape ſpecies of which, the *Droſera ciſtiflora* of Linnæus, Roth, an ingenious botaniſt, obſerved a ſenſitive quality to reſide, analogous to that of *Dionæa*, though fainter. Both genera arrange under the natural order GRUINALES. An Indian ſpecies of wood-ſorrel, which belongs to the ſame natural order, poſſeſſing a like contracting faculty, is on that account termed, by ſome botaniſts, *Herba viva*, *Herba ſentiens*, *Herba mimoſa Malabarienſium*, and by Linnæus, *Oxalis ſenſitiva*.

To conclude, the cauſe of this and the other motions of plants is merely external. The motions themſelves, therefore, are not ſpontaneous, as in perfect animals, which have that cauſe dependant on their choice and will. How many imperfect animals, however, are there, ſuch as thoſe in animal and vegetable infuſions, whoſe motions, like thoſe of the plants in queſtion, are ſolely to be attributed to heat, light, and other external cauſes?—and again, how many, as the gall-inſects, the oyſter, and other ſhell-fiſh, have

have not a motion ſo perceptible nor rapid as that of *Dionæa muſcipula*, and the ſenſitive plant!

The negroes in Senegal call a large ſpecies of ſenſitive plant, which grows in that country, guerackiao, that is, good-morrow; becauſe, ſay they, when you touch it, or draw near to ſpeak to it, the plant immediately inclines its leaves, to wiſh you, as it were, a good-morrow, and to ſhew that it is ſenſible of the politeneſs done it. In the ſame country, is produced a ſmall ſenſitive plant, that is rampant, not ſpinous, and which M. Adanſon affirms to be infinitely more delicate and ſenſible than all the other ſpecies.

A lye-water made from the aſhes of the roots of Spaniſh carnation is reckoned proper for bringing down the catamenia. The flowers, bruiſed and ſteeped in breaſt-milk, are a gentle anodyne, for which purpoſe they are often given, in the Weſt Indies, to quiet very young children. The leaves of this plant are uſed inſtead of ſenna in Barbadoes and the Leeward iſlands; and in Jamaica it is called ſenna.

The root of *polygala ſenega*, or ſenega rattle-ſnake root, conſiſts of many jointed fleſhy tubercles or knobs, and has been long uſed by the Seneka Indians, both outwardly and inwardly, as an infallible remedy for the bite of that pernicious animal, the rattle-ſnake. The inhabitants of Virginia have, of late years, uſed the ſame plant with conſiderable ſucceſs in many diſorders proceeding from thick ſizy blood.

LURIDÆ. The name of the twenty-eighth order in Linnæus's Fragments of a Natural Method, conſiſting of plants whoſe pale and ominous appearance ſeems to indicate ſomething noxious in their nature and quality.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Atropa,	—	—	Deadly night-ſhade.
Browallia.			
Capſicum,	—	—	Guinea pepper.
Cateſbæa,	—	—	Lily-thorn.
Celſia.			

Ceſtrum,

Linnæan Genera.			*Engliſh Names.*
Ceſtrum,	—	—	Baſtard jaſmine.
Datura,	—	—	Thorn-apple.
Digitalis,	—	—	Fox-glove.
Elliſia.			
Hyoſcyamus,	—	—	Henbane.
Lycium,	—	—	Box-thorn.
Nicotiana,	—	—	Tobacco.
Pedalium.			
Phyſalis,	—	—	Alkekengi or winter-cherry.
Seſamum,	—	—	Oily purging grain.
Solanum,	—	—	Night-ſhade, potatoe.
Strychnus.			
Verbaſcum,	—	—	Mullein.

Habit and Structure of the Plants of this Order.

Moſt of theſe plants are herbaceous and perennial. Many of them are of the maſqued tribe of flowers, ſuch as fox-glove, pedalium, oily purging grain, celſia, and browallia; others reſemble theſe in their general appearance, but differ from them eſſentially in the equality of their ſtamina.

The ROOTS are generally branched, ſometimes tuberous.

The STEMS and BRANCHES are cylindric.

The LEAVES are generally ſimple and placed alternate. In browallia and pedalium, the lower leaves are oppoſite, the upper alternate. Lily thorn and ſtrychnus have all their leaves placed oppoſite.

The FLOWERS are hermaphrodite. They proceed either ſingly, or in cluſters, from the angle formed by the leaves and branches. In ſome ſpecies of box-thorn, they terminate the branches.

The CALYX is generally of one piece deeply divided into five parts.

The COROLLA conſiſts of one petal, which is either bell, funnel, or wheel-ſhaped.

The STAMINA are four or five in number, and thoſe either of equal lengths, as in the greater number, or unequal,

as

as in fox glove, pedalium, oily purging grain, celſia, and browallia, where two of the ſtamina are long and two ſhort.

The SEED-BUD is placed above the receptacle of the flower. The ſtyle is ſingle, and terminated by a ſummit, which is hemiſpherical, and frequently channelled or furrowed.

The SEED-VESSEL in ſuch as have equal ſtamina, is a berry; in the reſt, it is generally a capſule.

The SEEDS are numerous, and frequently kidney-ſhaped.

Theſe plants in general have an inſipid taſte, and a nauſeous diſagreeable ſmell.

The greater part, particularly the fruits of deadly night-ſhade and thorn-apple, taken internally, if in any conſiderable quantity, prove mortal: cauſing a ſtupor, delirium, and convulſions. Theſe fatal effects, it is true, may be in a great meaſure prevented by the ſpeedy and copious uſe of emetics, and, perhaps, more certainly ſtill, by that of acids, ſuch as vinegar, or the juice of lemons adminiſtered in great abundance.

Alkekengi berries are diuretic.

The external application of theſe plants is more deſerving of recommendation than their internal uſe. The freſh leaves of deadly night-ſhade applied to hard tumours and ſchirrous ſwellings on the breaſt have long been eſteemed as an aſſured remedy. The ladies in Italy make uſe of the diſtilled water of this plant for beautifying their ſkin, whence the name belladonna, (handſome lady,) by which it is generally known among botaniſts. The painters in miniature prepare a very beautiful green colour from the macerated fruit.

Guinea-pepper grows naturally in both the Indies. It is raiſed from ſeed in America, Spain, Portugal, Languedoc, Provence, and even in our gardens. In all the Caribbee iſlands, the inhabitants uſe the pods in ſauces; as do likewiſe the Negroes, who are very fond of them; whence this genus of plants had the appellation of Negroe and Guinea-pepper, by the former of which names it is generally known all over the Weſt Indies. The ſeeds are intolerably acrid.

An ointment, made of the flowers of purple fox-glove, and May-butter, is much commended by ſome phyſicians for ſcrophulous ulcers, which run much, and are full of matter. Taken internally, it is a violent purgative and emetic; and is, therefore, only to be adminiſtered to robuſt conſtitutions. The country people in England frequently uſe a decoction of it with polypody of the oak, in epileptic fits. In Italy, fox-glove is eſteemed an excellent vulnerary.

Thorn-apple is uſed externally in burnings, and in inflammations. Of its juice is made an ointment which is excellent for the piles.

The leaves of henbane are emollient, cooling and anodyne, good for inflammations, and defluxions of hot rheum. Uſed internally, they are a ſtrong poiſon. The roots are accounted narcotic, and but rarely uſed inwardly; they are frequently hung about childrens' necks, being cut to pieces, and ſtrung like beads, to prevent fits, and cauſe an eaſy breeding of teeth. The ſeed, made into an electuary, with conſerve of roſes, and white poppy ſeeds, is commended by Mr. Boyle and Hælideus, againſt ſpitting of blood, as well as any other hæmorrhage. A fumigation of the ſeeds is ſaid to give eaſe in the tooth-ach. The juice of henbane, or the oil made by infuſion with its ſeeds, is ſpecific in pains of the ear.

Green tobacco pounded, and mixed with unſlacked lime, is frequently uſed by the inhabitants of the Weſt-Indies for poiſoning waters abounding with cray-fiſh, which, by theſe means, are eaſily taken. The plant is very liable to be deſtroyed at the roots, by a grub or large worm, called by the Weſt-Indians, kitiſonia; the leaves are likewiſe often deſtroyed by a ſmall green worm of the eruca kind.

The leaves and berries of common night-ſhade, (*ſolanum nigrum,*) are uſed externally for inflammations and hot ſwellings; as alſo for burns and ſcalds.

Bitter-ſweet, the *ſolanum dulcamara* of Linnæus, is commended for the dropſy, jaundice, and king's evil; for the former of which diſeaſes, common fox-glove has lately, on the authority of Dr. Withering, obtained very great, and,

as far as I can learn, very deſerved eſtimation. In Weſtmoreland they ſcrape the bark off the ſtalks of bitter-ſweet, and boil about an ounce of them in ale, which they give to women in childbed, to help the ſwelling of their breaſts. A decoction of the ſeeds of this plant is ſaid to be ſerviceable in venereal complaints.—The fruit of ſolanum melongena, ſometimes called the egg-plant, is often ſtiled the mad-apple, or apple of Sodom. This poiſonous fruit is frequently attacked in the eaſtern countries by an inſect, which turns all the inſide into duſt, leaving the ſkin only entire, and of a very beautiful colour.

The flowers of great white mullein, the Verbaſcum Thapſus of Linnæus, are uſed externally in inflammatory ſwellings. An infuſion of them is preſcribed internally in dyſenteries and colics occaſioned by ſharp humours. The leaves are accounted pectoral, good for coughs, ſpitting of blood, and other diſorders of the breaſt. Outwardly they are uſed like the flowers in fomentations or fumigations. They are reckoned a ſpecific againſt the piles.—In North-America, a decoction of the roots injected into the wounds of cattle which are occaſioned by worms, effectually cures them by deſtroying the inſects. Theſe worms are the *Larvæ* of the *Oeſtrus* or Gadfly, which depoſits its eggs on the back of cattle—and the Larvæ being hatched from theſe eggs, cauſe great ſores, in which they live, till they are ready for their change. In the ſouth of Ruſſia, they uſe for the ſame purpoſe the decoction of *Veratrum*, or white hellebore.—A tea is prepared from the leaves, as well as from the flowers, which is ſaid to be uſeful in the dyſentery. The Indians, it is believed, uſe the plant inſtead of tobacco, whence, in Penſylvania it has obtained the name of *Tobacco of the Savages*. The Swedes in that country, ſays Kalm, tie the leaves round their feet and arms, when they have the ague.

LUXURIANS *flos*, a luxuriant or double flower; a flower, ſome of whoſe parts are increaſed in number, to the diminution or entire excluſion of others.

The parts that are augmented or multiplied in luxuriant flowers, are the flower-cup and petals, which Linnæus conſiders as the teguments or covers of the flower; the parts

that

that are diminiſhed or entirely excluded, are the ſtamina or chives, which the ſame author denominates the male organs of generation.

Luxuriance in flowers is capable of the three following varieties.

I. A flower is ſaid to be MULTIPLIED, *(flos multiplicatus)* when the increaſe of the petals is not ſuch as to exclude all the ſtamina. In this ſenſe, flowers are properly ſaid to be double, triple, or quadruple, according to the number of multiplications of the petals.

II. A flower is ſaid to be FULL, *(flos plenus)* when, by the multiplication of the petals, all the ſtamina are excluded. Such are moſt of the double flowers that engage the attention of floriſts.

III. A flower is ſaid to be prolific, *(flos prolifer)* which produces flowers, and ſometimes leaves, from its center.

For a particular deſcription of each of theſe kinds of luxuriance in flowers, the reader is referred to the articles MULTIPLICATUS *flos*, PLENUS *flos*, and PROLIFER *flos*.

Many natural orders of plants do not in any circumſtances produce luxuriant flowers. Of this kind are the maſqued flowers of Tournefort, excepting calve's ſnout; the rough leaved, umbelliferous, ſtarry plants, and ſuch as flower at the joints, of Ray. Some umbelliferous flowers, however, are *prolific*.

The pea-bloom, or butterfly-ſhaped flowers, are rarely rendered double; ſome inſtances, however, of luxuriance, are obſerved in a ſpecies of ladies finger, coronilla, and broom.

All luxuriant flowers are vegetable monſters. Such as are perfectly full, by which I mean the greateſt degree of luxuriance, cannot be propagated by ſeeds; becauſe theſe, for want of impregnation, can never ripen. Full flowers, therefore, are very properly denominated by Linnæus, eunuchs. This higheſt degree of luxuriance is very common in carnation, lychnis, anemone, ſtock, Indian creſs, roſe, marſh marigold, ranunculus, violet, pœony, and narciſſus.

Flowers which do not exclude all the ſtamina, perfect

their ſeeds. Of this kind are poppy, fennel-flower, campanula, and ſome others.

Some flowers, as thoſe of the water-lily, fig-marigold, and cactus, have many rows or ſeries of petals, without the number of ſtamina being in the leaſt diminiſhed. Such flowers are by no means to be reckoned luxuriant in the ſlighteſt degree.

Luxuriance in flowers is generally owing to luxuriance or exceſs of nouriſhment.

M.

MAS *Planta*, a male plant; a plant which upon the ſame root produces male flowers only. *Vide infra.*

MASCULUS *Flos*, a male flower; a flower which contains the ſtamina, reckoned by the ſexualiſts the male organ of generation, but not the *ſtigma* or female organ.

All the plants of the claſs dicœcia of Linnæus have male and female flowers upon different roots: thoſe of the claſs moncœcia, bear flowers of different ſexes on the ſame root. The plants, therefore, of the former, are only male or female: thoſe of the latter are androgynous; that is, contain a mixture of both male and female flowers.

MEDULLA, the pith. *Vide* STRUCTURA *Vegetabilis.*

MEJOSTEMONES, (from μειῶν, leſs; and ſtamen): the name of a claſs in Haller's Natural Method; conſiſting of plants, the number of whoſe ſtamina or male organs is leſs than that of the petals, or diviſions of the *corolla.* The term is exemplified in ſpeedwell.

MENSURA, meaſure. In deſcribing the parts of plants, Tournefort introduced a geometrical ſcale, which many of his followers have retained. They meaſured every part of the plant; and the eſſence of the deſcription conſiſted in an accurate menſuration of the whole.

As the parts of plants, however, are liable to variation in no circumſtance ſo much as that of dimenſion, Linnæus very rarely admits any other menſuration than that ariſing

from

from the reſpective length and breadth of the parts compared together. In caſes that require actual menſuration, the ſame author recommends, in lieu of Tournefort's artificial ſcale, the following natural ſcale of the human body, which he thinks is much more convenient, and equally accurate.

The ſcale in queſtion conſiſts of eleven degrees, which are as follows:

I. A hair's-breadth, or the diameter of a hair, *capillus*.

II. A line, *linea*, the breadth of the creſcent or white appearance at the root of the *finger*, (not *thumb*) meaſured from the ſkin towards the body of the nail;—a line is equal to twelve hair-breadths, and is the twelfth part of a Pariſian inch.

III. A nail, *unguis*, the length of a finger-nail;—equal to ſix lines, or half a Pariſian inch.

IV. A thumb, *pollex*, the length of the firſt or outermoſt joint of the thumb;—equal to a Pariſian inch.

V. A palm, *palmus*, the breadth of the palm, excluſive of the thumb;—equal to three Pariſian inches.

VI. A ſpan, *ſpithama*, the diſtance between the extremity of the thumb, and that of the firſt finger, when extended;—equal to ſeven Pariſian inches.

VII. A great ſpan, *dodrans*, the diſtance between the extremity of the thumb, and that of the little finger, when extended;—equal to nine inches.

VIII. A foot, *pes*, meaſuring from the elbow to the baſis of the thumb;—equal to twelve Pariſian inches.

IX. A cubit, *cubitus*, from the elbow to the extremity of the middle finger;—equal to ſeventeen inches.

X. An arm-length, *brachium*, from the arm-pit to the extremity of the middle finger;—equal to twenty-four Pariſian inches, or two feet.

XI. A fathom, *orgya*, the meaſure of the human ſtature; the diſtance between the extremities of the two middle fingers, when the arms are extended;—equal, where greateſt, to ſix feet.

METEORICI. *Vide* VIGILIÆ.

METHODUS,

METHODUS, a mode of arrangement from certain agreements or circumſtances of reſemblance; a method.

Botaniſts have diſtinguiſhed two kinds of methods in arranging vegetables; the natural and the artificial.

A natural method is that, which, in its diſtribution, retains all the natural claſſes; that is, ſuch into which no plants enter that are not connected by numerous relations, or that can be disjoined without doing a manifeſt violence to nature.

An artificial method is that whoſe claſſes are not natural, becauſe they collect together ſeveral genera of plants which are not connected by numerous relations, although they agree in the characteriſtic mark or marks, aſſigned to that particular claſs or aſſemblage to which they belong.

An artificial method is eaſier than the natural, as in the latter it is Nature, in the former the writer, who preſcribes to plants the rules and order to be obſerved in their diſtribution. Hence, likewiſe, as Nature is ever uniform, there can be only one natural method: whereas artificial methods may be multiplied almoſt *ad infinitum*, according to the ſeveral different relations under which bodies are viewed.

To form a preciſe idea of the nature and utility of vegetable arrangement, whereby only a proper eſtimate can be made of the merits and defects of particular ſyſtems, we muſt look backward, and trace method and arrangement from its firſt and ſimpleſt rudiments in botanical writings, to its more perfect ſtate under Cæſalpinus and his ſucceſſors.

Although it may be preſumed that every plant poſſeſſes virtues which are proper to it, we have not been able to aſcertain them with any degree of preciſion, unleſs in ſeven or eight hundred ſpecies, one half only of which are uſed in medicine.

If then, in order to be an expert botaniſt, it were ſufficient to know this limited number of plants, by their names and their virtues; inſpection, repeated examination, and compariſon, would, perhaps, be the only neceſſary means for attaining ſuch knowledge. A botaniſt would acquire information in the ſame manner as a traveller does of the

countries through which he paſſes, or as a labourer learns to diſtinguiſh the few plants which come under his obſervation. It would be ſuperfluous to have recourſe to other means.

But, even with the proviſo we have mentioned, ſuch a method would have its inconveniences. It would be tedious, irkſome, and always uncertain. The reſemblance of ſeveral uſeful and wholeſome plants to ſuch as are noxious and uſeleſs; the impoſſibility of diſtinguiſhing ſuch ſimilar plants, without a diſtinct idea of each; the external agreements of ſeveral ſpecies, whoſe properties are eſſentially different; the great danger of committing miſtakes; and the ill conſequences of ſuch miſtakes: theſe, and other circumſtances, concurred to ſuggeſt the neceſſity of having recourſe to diviſions determined by accurate and diſtinct characters.

The neceſſity of diviſions becomes ſtill ſtronger, if we extend our views, and, not ſatisfied with the few medicinal plants which our own country affords, embrace the whole of vegetable nature. Here memory muſt unavoidably ſink under the mighty load, if obſervation, reaſoning, and method, did not bring it timely aſſiſtance.

By obſervation, we diſtinguiſh the external marks or characters which are obvious in the appearance of natural bodies: by reaſoning, we determine the relations which ſubſiſt betwixt them: and by method, we collect, under one head, ſimilar bodies, and ſeparate ſuch as differ. Hence ariſe diviſions and ſubdiviſions, which the mind ſeizes with avidity, and retains ever after.

Thus it is, that the ſtudy of plants, which at firſt ſeems, and for a long time actually was, a ſimple nomenclature, becomes a ſcience; and this ſcience is called botany. Agreeably to this idea, Boerhaave defines botany to be a part of natural knowledge, by means of which, plants are moſt certainly and eaſily known, and engraved on the memory.

It was not, however, till after many ages, and much obſervation, that botany began to be conſidered in this philoſophical view: though diviſions of a certain kind have always been admitted, in order to facilitate the knowledge of plants.

Thus

Thus, vegetables have been ſucceſſively diſtinguiſhed from the place of growth, into aquatic, marine, wild, and domeſtic; from the time of flowering, into ſpring, ſummer, autumnal, and winter plants; ſometimes too, leſs philoſophically ſtill, they have been arranged by the names of the authors who firſt diſcovered or deſcribed them; and not ſeldom, according to the letters of the alphabet.

Theophraſtus, the ſcholar of Ariſtotle, arranges plants, from their qualities and uſes, into eſculent grains, ſucculent plants, and pot-herbs; Dioſcorides, into aromatic, alimentary, medicinal and vinous plants.

Theſe philoſophers, ſtudious to render botany uſeful, were ignorant of the means to facilitate its knowledge. Their vague and uncertain diviſions can, at beſt, aſſiſt *his* memory, who already knows the plants they deſcribe, but will never conduct to the knowledge of them. They ſuppoſe every thing; they teach nothing.

The ſame may be affirmed of all the diviſions or methods founded ſolely on the qualities or medicinal virtues of plants. Theſe methods, generally adopted by phyſicians, with a view to confine the ſcience to its true objects, have always the contrary effect, by confounding things which ought to be diſtinguiſhed.

Three reaſons, according to M. Adanſon, concur to render every ſuch method uncertain and dangerous.

I. The ſame plant has often ſeveral different virtues.

II. The different parts of a plant have often different, and even oppoſite virtues; ſo that, according to the rules of ſtrict arrangement, the root ſhould be placed in one diviſion, the flower in another, and the leaf in a third. Thus in buckthorn, and diſtaff-tree, the leaves are aſtringent, the fruits purgative. In rhubarb, monk's rhubarb, and common knot-graſs, the roots are purgative, the leaves and ſeeds binding.

III. Several plants, characterized by a particular virtue, poſſeſs it to ſuch a degree of ſtrength or weakneſs, that we may reaſonably expect very different effects from this difference of intenſity in the ſame quality. Thus in the natural

family of lipped flowers, the aromatic virtue which is common to the whole tribe is poſſeſſed in the higheſt degree by roſemary, ſage, mint, marjoram, balm, and hyſſop; in a leſs degree, by germander, and ſelf-heal: and becomes almoſt inſenſible in ſage-tree and baſe hore-hound. It is the ſame with other qualities; tinctures, for example. Thus the roots of moſt of the pea-bloom tribe, and ſtarry plants, (*ſtellatæ*) afford a dye or tincture more or leſs lively; in the ſame manner, a coloured juice, which is more or leſs vivid, is procured from the leaves and flowers of that numerous tribe of plants called compound. The knowledge of this common quality, however, is ſo far uſeful, that on the diſcovery of a new plant in any particular family, we are led by analogy to explore thoſe properties in it which are known to be poſſeſſed by the family to which it belongs.—It was on this principle that M. Adanſon drew from a ſpecies of indigo at Senegal, which had eſcaped obſervation, a fecula of an azure blue colour, different from that of America, and perhaps ſuperior in beauty.

From theſe obſervations, which are furniſhed by experience, it follows as a corollary, that the principal virtue of any plant is that which is found to be poſſeſſed in common by all the plants of the family to which it belongs; and that, although the virtue in queſtion ſhould not be moſt predominant in a particular ſpecies. It is for this reaſon that the family of the purſlanes may be regarded, in a particular manner, as cordial; for although many of that tribe are likewiſe aſtringent, yet the former is the prevailing or general virtue.

Upon the whole, diviſions drawn from the virtues of plants, far from enlightening botany, plunge it anew into a chaos of confuſion and ignorance. We allow them their uſe in the *materia medica*, where plants are diſtinguiſhed by their ſenſible qualities, into bitter, acid, ſalt, ſweet, and acrid; and by their virtues, into purgative, aperient, ſudorific, hepatic, &c. But this is not botany; it is the *materia medica*: the one conducts to the knowledge of plants; the other indicates their uſe: the firſt ought, conſequently, to

to

to precede and direct the ſecond; but cannot itſelf be enlightened, without diviſions founded upon ſigns more determinate in their nature, more conſtant, and ſenſible to the eyes of the obſerver.

In the progreſs of the ſcience, botaniſts have endeavoured to diſtinguiſh theſe ſigns, to fix their characters, and aſcertain their relations. The moſt apparent would, doubtleſs, firſt attract regard; ſuch are the ſize and duration of plants; circumſtances from whence aroſe the firſt diſtinction of vegetables into herbs and trees: that is, into plants of a tender ſucculent nature, which loſe their ſtems during the winter; and into ſuch as are of a ſolid conſiſtence, woody, and whoſe ſtems ſubſiſt during the winter. See ARBOR, where this diſtinction, as likewiſe that of ſhrubs and underſhrubs, is particularly diſcuſſed.

Ancient, however, as this diſtinction is, and numerous as are the authors who have adopted it, it can be of very little aſſiſtance alone in determining plants with preciſion; as we muſt wait at leaſt a full year to be aſcertained of the duration of a particular plant. Some annuals, too, have a woody ſort of ſtem, which may cauſe them to be miſtaken for ſhrubs; nay more, ſome plants, which in a warm climate are ſhrubby, become herbaceous, and even annual, (as the *ricinus* or *palma chriſti*,) when removed into a cold one.

The ſame inſufficiency to ſerve as foundations of a method will be found in the roots, and ſtill more in all the variable qualities of vegetables, ſuch as taſte, colour, and ſmell, which are modified in a thouſand different ſhapes, by culture and climate.

The leaves being earlier, more apparent, more common, and more permanent than the flowers, ſooner engaged attention: but in proportion as botany made advances, the uncertainty of characteriſtic marks drawn from the leaves manifeſtly appeared. In the courſe of theſe advances, it has been found that the leaves vary in their forms, even on the ſame individual; that the ſame plant, under a different climate, with different management, or ſown at different ſeaſons, ſhall be covered with leaves which have not the ſmalleſt re-

ſemblance to each other; that plants otherwiſe extremely ſimilar in their appearance, have leaves abſolutely diſſimilar; and that others, whoſe figure, qualities, and habit, differ eſſentially, are ſo remarkably ſimilar in their leaves, that confuſion muſt be unavoidable, if the characters of the leaves are made the foundation of primary diviſions. Thus a ſpecies of veronica or ſpeedwell bears the leaves of the germander; which, in like manner, bears thoſe of the oak.

Notwithſtanding theſe diſcouraging circumſtances, a ſyſtem of plants founded upon the leaves has been attempted by two ingenious moderns, both Frenchmen; M. Sauvage, in a work entitled *Methode pour connoitre les Plantes par les Feuilles*; and M. Duhamel du Monceau, in his *Traitē des Arbres*. Theſe gentlemen do not, however, mean to fix preciſe characters from the leaves; their ſole intention is to preſent us with new relations, and thereby facilitate the diſtinctions which they ſuppoſe determined by means more certain and methodical. They have even ſet out with declaring the inſufficiency of the leaves for this purpoſe.

Methods having hitherto been attempted to be erected without ſucceſs, occaſioned by the inſufficiency of the leading characters, men had recourſe to ſuch as were more ſolid, more conſtant, and more general. Theſe were named natural characters, and are drawn from the habit or general appearance of the plant; and from the combination of the moſt eſſential parts of vegetation, the flower, fruit, ſeed, diſpoſition of the ſtem, and branches, &c. All the accidents of each of theſe parts, viewed and compared together, led to natural and determinate diviſions.

Theſe diviſions, founded upon numerous, permanent, and ſenſible relations, are called natural orders, or natural families. Such are the graſſes; the croſs-ſhaped, umbelliferous, liliaceous, pea-bloom, and lipped-flowers. Each plant in every one of theſe natural families collects ſenſible characters, which are eſſentially the ſame in all the plants of the family to which it belongs.

The families alluded to ſeem to have been truly diſtinguiſhed by nature; and botaniſts have ſucceſſively determined a great

great number of them. If they had been able to arrange, in like manner, all the ſpecies of known plants, they would have diſcovered a natural method, the great *deſideratum* in botany, and which has in vain engaged the attention and reſearches of every naturaliſt ſince the origin of the ſcience.

Such a natural method would be a kind of table, exhibiting the gradual progreſſion which nature has obſerved in the formation of vegetables, as in that of all other beings. Many of the intermediate ſteps of this progreſſion; ſeveral links in the great chain, are not known. A great number of plants cannot find a place in the natural families; devoid of uniform relations betwixt themſelves, they cannot conſtitute new families; they remain, in ſome ſort, ſolitary; and would again involve the ſcience in confuſion, if Art had not ſupplied what Nature refuſed to grant.

Artificial methods were invented; and characters eſtabliſhed, which, although leſs ſenſible, and leſs numerous than the natural characters juſt mentioned, were ſimpler, more general, and equally invariable.

Upon theſe general characters, ſcrupulouſly obſerved, and minutely examined, primary diviſions have been founded, which are again ſubdivided from an attention to other characters leſs apparent.

Theſe diviſions, which form a kind of ſcale or progreſſion, are characterized by different names; as claſſes or families; orders or ſections; genera; ſpecies; varieties; and the individual; and all together conſtitute what is called a METHOD; and, when the principles upon which the diviſions proceed, are fixed and determined,—a SYSTEM.

As this ſubject is of the utmoſt importance to the beginning botaniſt, I muſt beg leave to dwell upon it, and to trace the order of bodies into genera, ſpecies, varieties, and individuals, both in the inveſtigation and the enunciation of truth; that thence the general laws of method may be eſtabliſhed.

Every natural body differs ſo from all others which are expoſed to our ſenſes, that it may be conſidered as ſingular

or individual. Thus a dog, a ſparrow, a fly, a tulip, a diamond, nitre, are all bodies which may be conſidered in themſelves, and without relation to others, as often as they ſolicit the ſenſes.

Many individuals of the ſame kind give an idea both of ſimilitude and plurality. The ſimilitude, therefore, of ſeveral individuals conſtitutes a SPECIES OR KIND,—an abſtract or general term, to which all theſe individuals, on account of their agreement in certain characters, may be referred.

But two bodies are never obſerved of ſimilar properties in every reſpect; and, therefore, the idea of a ſpecies would never ariſe, were not certain characters diſtinguiſhed from others, the eſſential from the merely accidental. The eſſential characters never vary in the ſame ſpecies; the accidental ſometimes vary in the ſame ſpecies, from certain acceſſory cauſes, which are not always and neceſſarily preſent in a natural body. Theſe accidental characters give riſe to the varieties, which are not, by any means, to be confounded with the ſpecies. Thus of the ſpecies of dogs, different breeds, as the greyhound, ſpaniel, and beagle, conſtitute the varieties; all together make up the ſpecies of that animal. In the ſame manner, difference of colour, magnitude, ſcent, taſte, and other attributes, exhibits varieties in the different ſpecies of vegetables.

In a number of ſpecies accurately diſtinguiſhed, ſome ſimilar characters are found: theſe beget the idea of a GENUS or RACE, a general term, expreſſing a ſimilitude of ſpecies, from an agreement in ſome characters. Thus, to take an example from botany. Of various plants, which, in ſpring, are ſeen in our meadows, and are conſidered as different ſpecies, from the appearance of their leaves, which are either differently cut, or of different figures, if intire; the petals are of an equal number, (five) the ſtamina and ſtyles numerous, and at the claw or bottom of each petal is a ſmall prominence or pore. Theſe reſemblances in the parts of the flower, in ſuch a number of different ſpecies, conſtitute a GENUS, which in the inſtance I have been giving, called *genus ranunculi*: and all plants which agree

in

in the characters juſt mentioned are referred to that genus.

Similitude admits of almoſt innumerable degrees. Accordingly, orders and claſſes, higher degrees ſtill, are conſtituted from genera, by attending to the agreements of a number of genera in the firſt caſe, and of a number of orders in the ſecond. Theſe diviſions, however, are altogether arbitrary, according to the points of reſemblance under which we conſider bodies.

From what has been ſaid, it is clear how natural things are to be inveſtigated, and how communicated. The diſcoverers of natural things evidently proceeded from the conſideration of individuals to that of ſpecies and genera, and ſo on to the higher arbitrary diviſions: and a like method do all adopt who would improve natural knowledge by further diſcoveries.

But when invented and propoſed to be communicated to others, we take a different method, and beginning with the higher arbitrary diviſions, as claſſes and orders, deſcend to genera, ſpecies and varieties, in a direction retrograde to what we followed in invention. This method is found moſt adapted to the capacity of learners.

This general idea of the diviſions admitted into artificial methods or ſyſtems, will be better underſtood by the application which we intend to make of it to particular methods. At preſent I would obſerve with Cæſalpinus, that, "by means of theſe diſtinctions, the vegetable kingdom is divided like a large body of troops. The army is divided into regiments; the regiments into battalions; the battalions into companies; the companies into ſoldiers." Vegetables are ranged in claſſes, which are divided into orders; the orders conſiſt of genera; the genera of ſpecies; and, as the term regiment is an aggregate of ſoldiers, ſo the term claſs, or, to go higher ſtill, ſyſtem, is nothing elſe than an aggregate of ſpecies.

To be convinced of the great utility of artificial methods in conducting to the knowledge of plants, let us ſuppoſe the number of known ſpecies of plants to be twelve thouſand,

ſand, and the number of claſſes in a certain known method to be twenty-four. A plant is preſented to me which I never ſaw. I immediately look for the general character which ſerves to diſtinguiſh each of the twenty-four claſſes. This being found, and conſequently the claſs of the plant being determined, I have no longer to look for my plant among twelve thouſand, but, on a ſuppoſition that each claſs contains an equal number of genera, among five hundred only, the twenty-fourth part of the number juſt ſuppoſed. I next look for the character of the order, the ſecond diviſion, which being likewiſe found, will reduce this number to about an hundred. The character of the genus, which I next explore, will reduce this ſtill further, to twenty, for inſtance: that of the ſpecies determines the plant in queſtion.

This method of proceeding is ſimilar to that which is obſerved in turning over a dictionary, where, in ſearching for a word, as SPACE, we firſt look for the letter S, next P, then A, and ſo ſucceſſively the C and E. S may repreſent the claſs; P the order; A the genus; C the ſpecies, and E the variety.

It was long, however, before artificial methods attained that degree of accuracy, which we have been deſcribing. The determination of the general and particular characters which conſtitute ſuch methods, required obſervations ſo much more exact and numerous, as their principal merit conſiſts in collecting the greateſt poſſible number of natural families; as they muſt at the ſame time agree with all known plants: and, as botany, ſince the diſcovery of the new world, has more than doubled its former riches.

Lobelius in 1570; Cluſius, in 1576, and Dalechamp, a phyſician of Lyons, in 1587, gave ſucceſſively very good deſcriptions of a large number of plants, but were greatly puzzled in determining what parts were moſt proper for furniſhing claſſic and generic characters. Geſner was the firſt who ſuggeſted the propriety of the parts of fructification for this purpoſe; and Cæſalpinus, a phyſician of Piſa, firſt arranged plants according to Geſner's idea, and began the period of Syſtematic Botany.

In

In 1583, he deſcribed eight hundred and forty plants, and divided them into fifteen claſſes, by a method, in which, after admitting the general diſtinction formerly mentioned, of herbs and trees, he draws his diſtinctive characters from the parts of fructification, particularly from the ſeed-veſſel; the number of cells; the number, form, and diſpoſition of the ſeeds; the ſituation of the radicle in the ſeed; and other circumſtances. Theſe fifteen claſſes are ſubdivided into forty-ſeven ſections or orders, from an attention to the diſpoſition, ſituation and figure of the flowers; the ſituation of the radicle or embryo-plant in the ſeed; the number of lobes or ſeed-leaves; the fruit or ſeed-veſſel; the colour of the flowers; the form of the leaves and roots, and ſome other circumſtances. Cæſalpinus's method then is not founded ſolely upon the fruit, as has been imagined, but combines with ſeveral other parts of fructification, various modifications of parts, which, like the root and leaves, are connected neither with the flower nor fruit. The ſituation of the radicle or embryo-plant in the ſeed, as likewiſe the number of lobes or ſeed-leaves, are ſaid to have been firſt obſerved and accurately diſtinguiſhed by this author.

The ſame botaniſt diſtinguiſhed with great accuracy the cells and partitions of ſeed-veſſels. He made no methodical diſtinction of genera; each ſpecies being deſcribed as a diſtinct genus.

Contemporary with Cæſalpinus flouriſhed Acoſta, a Spaniard; Camerarius, a German; Porta and Proſper Alpinus, both Italians. The latter wrote an excellent treatiſe on the plants of Egypt; as likewiſe two ſeparate diſſertations on rhubarb and balſam.

Porta, in 1588, publiſhed a work, entitled, Phytognomica, or the Aſtrology of plants. In this motley collection, vegetables are divided into ſeven claſſes, from their place of growth, their reſemblances and relations to men and animals, and their relations with the ſtars. Theſe claſſes are ſubdivided into forty-ſeven ſections.

According to Porta, plants, which have any of their parts

like

like a liver, are proper for the diſeaſes of the liver; ſuch as reſemble eyes, are good for the eyes; and ſo of others.

This idea, ſays a French writer, and the method founded upon it, is very ingenious; and contains, at leaſt, as many truths as falſehoods.

In 1592, Fabius Columna, a Neapolitan, improved upon the diſtribution of the genera, and invented moſt of the terms now uſed for denominating the parts of fructification. His engravings on copper are eſteemed excellent.

Columna publiſhed his Phytobaſanus, at Naples, in 1594, with thirty-five figures. The firſt part of his "Ecphraſis minus cognitarum ſtirpium" was publiſhed in quarto, at Rome, in 1610, with one hundred and fifty-ſix figures; and the ſecond part at the ſame place in 1616, with forty-three figures. This author is ſaid to have been drawn into the ſtudy of botany, by ſome experiments on Valerian to cure himſelf of the epilepſy. He followed no particular method, but treated of plants hiſtorically, or without order.

In 1596, Caſpar Bauhin, a Swiſs, fixed, with indefatigable labour, in his Pinax, the name of every plant then known and deſcribed; and in 1650, his brother, John Bauhin, wrote his Univerſal Hiſtory of Plants, in three volumes folio. In this work are deſcribed five thouſand two hundred and ſixty-ſix plants, divided, not very methodically, it muſt be allowed, into forty claſſes. To this "par nobile fratrum" is botany indebted for a conſiderable part of its progreſs; yet the rage, which ſtill ſubſiſted of forming diviſions from the virtues and uſes of plants, greatly retarded the introduction of thoſe orthodox methods, as Linnæus terms them, which alone can bring the ſcience to perfection.

In this period of botany, gardens were erected at the public expence, and opened for the convenience of ſuch as addicted themſelves to the ſtudy of plants; a circumſtance which greatly accelerated the progreſs of the ſcience.

The

The firſt botanical garden was opened at Padua in 1540, by the family of the Medici.

That at Bologna and Piſa in 1547.

That at Montpelier in 1598.

That at Paris in 1626.

That at Edinburgh, in 1675, by Sir Andrew Balfour, preſident of the Royal College of Phyſicians.

That at Upſal, in Sweden, in 1657.

That at Oxford in 1683.

That at Leyden in 1677.

That at Amſterdam in 1682.

That at Utrecht in 1725.

Beſides theſe and many other academical and public gardens which might be enumerated, there were three erected in Italy, one in France, one in England, five in the Low-Countries, eight in Germany, and two in Sweden by private gentlemen.

In 1680, Robert Moriſon, a native of Aberdeen in Scotland, publiſhed at Oxford, an Univerſal Hiſtory of Plants, in which he retains, under a new form, the diviſions of Cæſalpinus, founded upon the parts of fructification, particularly the fruit.

Moriſon was long an exile in France, where he applied himſelf to botany, and other branches of phyſic, and was appointed ſuperintendant of the gardens at Orleans.

Upon the reſtoration of Charles the Second, he was invited over to England by that monarch, who appointed him Regius Profeſſor of Botany at Oxford.

The Hiſtory of plants was completed by Mr. James Bobart, after Moriſon's death, and publiſhed in folio, in 1699, with one hundred and ninety-five figures on copper.

Moriſon's Method, ſays Mr. Adanſon, although not very elaborate, is extremely difficult in practice, and has not, on that account, been followed by any author, except Bobart, who completed his large work on plants, and the anonymous author of a work publiſhed in octavo, at Oxford, in 1720, under the title of "Hiſtoriæ Naturalis Sciagraphia." His

arrangement

arrangement of the umbelliferous plants is very ingenious, and has been followed by moſt ſucceeding authors.

John Ray, or Wray, was born near Braintree in Eſſex, in 1628, and early applied himſelf to the ſtudy of natural hiſtory. In his Natural Method of Plants, publiſhed in 1682, he ſuggeſted an idea or plan of arrangement, much ſuperior to that of either Cæſalpinus or Moriſon, and, perhaps, in many reſpects, inferior to none of the boaſted methods that have appeared ſince his time. This plan Mr. Ray did not execute till 1686, when he publiſhed his General Hiſtory of Plants, in which are deſcribed eighteen thouſand ſix hundred and fifty-five ſpecies, including varieties. His method is founded upon the general habit or ſtructure of plants; their ſize and duration, as herbs and trees; their greater or leſs degree of perfection; the place of growth; the number of ſeed-leaves, petals, capſules, and ſeeds; the ſituation and diſpoſition of the flowers; the form of the leaves; the abſence or preſence of the flower-cup and petals; the ſubſtance of the leaves and fruit; and the difficulty of arranging and claſſing certain plants. From a combination of theſe circumſtances, Ray has arranged all vegetables into thirty-three claſſes, which are ſubdivided into one hundred and twenty-five ſections. His method is extremely elaborate, and collects more natural claſſes than any artificial ſyſtem I am acquainted with; it is, however, extremely difficult in practice, and, therefore, now ſtudied more for curioſity than uſe. It would have ſucceeded better, ſays M. Adanſon, if Ray had been as great a botaniſt, as he was a learned writer, and judicious compiler.

In 1700 Ray publiſhed an edition of his method, augmented and corrected after that of Tournefort, which had appeared in 1694. Some pretenders to botany, envious of the ſucceſs which theſe great men had juſtly obtained, endeavoured to embroil them, though without effect; for it appears that they always lived in the ſtricteſt intimacy and friendſhip.

Ray's method was followed in 1707 by Sir Hans Sloane, in his Hiſtory of Jamaica.

In

In 1713, by Petiver, in his "Herbarium Britannicum."

In 1724, by Dillenius, in his enlarged edition of Ray's "Synopſis Stirpium Britannicarum."

In 1727, by Martyn, in his "Methodus Plantarum circa Cantabrigiam."

Chriſtopher Knaut, in his Enumeration of the Plants which grow round Hal, in Saxony, publiſhed in 1687, invented a method, eſtabliſhed, in part, upon the fruit, which differs but little from that of Ray. It is exceedingly complex and difficult.

Paul Hermannus, Profeſſor at Leyden, Magnolius, Profeſſor at Montpelier, and Rivinus, Profeſſor at Leipſick, ſucceſſively enriched botany with ingenious methods and new obſervations;—the dawn of the day, which the illuſtrious Pitton de Tournefort was about to diffuſe over every branch of the ſcience.

This great reformer of botany was born at Aix, in France, in 1656. He was early deſigned for the church, but, upon the death of his father, he quitted all thoughts of embracing that profeſſion; and, about two or three years thereafter, went to Montpelier, where, along with botany, he ſtudied anatomy, and other branches of phyſic, with great diligence.

In 1694, he publiſhed his Method, which conſiſts of twenty-two claſſes, and is founded on the regularity and figure of the petals or coloured leaves of the flower. The perſpicuity and preciſion of this method, gave it deſervedly, from its firſt appearance, the preference above all which had preceded it.

By the acknowledgement of all botaniſts, Tournefort has introduced into the ſcience, order, purity, and preciſion, by delivering the beſt and moſt certain principles for eſtabliſhing the genera and ſpecies; and by founding on thoſe principles the moſt accurate, and, if we except that of Rivinus, the eaſieſt method which has yet appeared. His object was not, as he himſelf declares, to eſtabliſh an univerſal method, a thing which he conſidered as impoſſible to be erected upon hypothetical and arbitrary principles; but to trace that method which appeared to him

moſt convenient for obtaining an eaſy and accurate knowledge of vegetables. His twenty-two claſſes, which, by the way, might have been reduced to ſeventeen, are ſubdivided into ſix hundred and ninety-eight genera, which are again ſubdivided into ten thouſand one hundred and forty-ſix ſpecies and varieties.

Upwards of twenty authors of eminence have ſucceſſively adopted Tournefort's method, after making the alterations, which new diſcoveries, and the correction of trivial errors, rendered neceſſary. A liſt of the moſt noted of theſe authors is given under the article COROLLISTÆ, which ſee.

The facility of acquiring Tournefort's Method had procured it an almoſt univerſal reception, when Linnæus propoſed his Sexual Syſtem, and, aſſiſted by the works of his predeceſſors, and much obſervation of his own, eſtabliſhed, by indefatigable labour, a method, which has ſince attracted the attention of the learned all over Europe.

Charles Von Linné was the ſon of a clergyman in Smolandia, a province of Sweden. He applied himſelf very early to the ſtudy of Natural Hiſtory, and made ſuch progreſs, that before he reached his twenty-third year, he was judged capable of aſſiſting Rudbeckius, Profeſſor of Botany at Upſal, in teaching his claſs.

In 1731, he introduced his method, then in embryo, into the garden at Upſal, with ſucceſs. After this he was employed by the Upſal ſociety to travel through Lapland, Norway, and other northern parts of Europe, in queſt of plants, and other natural curioſities. In 1735, he travelled through Denmark, Sweden, Germany, England, and Holland, with the ſame view; and publiſhed his "Syſtema Naturæ," at Leyden, in the ſame year.

In 1736, he publiſhed his "Fundamenta Botanica," which contain the rudiments of his method; theſe he afterwards enlarged, and publiſhed under the title of "Philoſophia Botanica." When Linnæus was in London, he propoſed his method to Sir Hans Sloane, Preſident of the Royal Society, who rejected it.

In 1742, Linnæus was choſen Profeſſor of Botany at Upſal.

He was afterwards appointed Chief Phyſician to the King of Sweden, knighted, and ennobled. The idea upon which Linnæus's method is founded, is as old as the time of Theophraſtus, and ſuppoſes that in plants, as in animals, generation is accompliſhed by the concourſe of the two ſexes. The ſtamina or chives he conſiders as the male organ of generation; the piſtillum or pointal as the female. From the number, ſituation, proportion, union, and abſence of the ſtamina are formed his primary diviſions or claſſes; and from the number and other circumſtances of the pointal or female part, ariſe moſt of the ſecondary diviſions or orders.

Such is the general idea upon which the celebrated Sexual Syſtem of Linnæus proceeds. A particular delineation or analyſis of it is prefixed to this work; and a juſt eſtimate of its merits and defects may be obtained by a careful peruſal of the criticiſms on his ſeveral claſſes, to be found in the preſent work, and an exact compariſon of thoſe claſſes with the primary diviſions of other Syſtematic writers, Ray and Tournefort in particular.

The authors who have followed Linnæus's Sexual Method are,

In 1739, Gronovius in his Flora Virginica.

In 1755, the ſame author in his Flora Orientalis Rauwolfij.

In 1756, Brown in his Natural Hiſtory of Jamaica.

In 1762, Mr. Jacquin in his Enumeratio Plantarum Americanarum.

In the ſame year, Mr. Hudſon, apothecary, in London, in his Flora Anglica. In this uſeful book, Mr. Hudſon gives the generic and ſpecific characters of every known plant that is native in England; the time of flowering; the Engliſh name; the place of growth; and its duration, whether annual, biennial, perennial, woody, or herbaceous.

The Sexual Method, when firſt propoſed by its author, gained little approbation. This was certainly owing to the great reputation which Tournefort's had obtained, and which nothing but the conviction of ſuperior ingenuity, merit and

induſtry, could poſſibly diminiſh. Without entering, at preſent, into a detail of the reſpective merits of theſe two illuſtrious botaniſts, let us endeavour to derive inſtruction from the diverſity of their principles and methods.

The order of nature is alone without imperfection; an order, however, which we have not yet been able to detect. Every artificial method has neceſſarily its defects, and its obſcurities. But two methods, ſuch as thoſe of Tournefort and Linnæus, ſo well conceived, ſo judiciouſly executed, and founded upon obſervation, muſt enlighten each other mutually. They cannot err on the ſame ſubject; if the one wanders but for a moment, the other immediately ſets him in the right path.

The ſame reflection occurs in comparing ſeveral other learned and ingenious methods; ſuch as thoſe of Haller, Van Royen, Sauvages, Ludwig, Adanſon and Duhamel; and the obſervations ſcattered through the works of Juſſieu, Guettard, Dillenius, Louis Gerard and others; ſo certain is the maxim with which I ſhall conclude this article, that a multiplicity of methods and obſervations compared together, leads us to diſtinguiſh plants under a greater number of relations, and conſequently conducts us, with greater eaſe, to their knowledge.

MISCELLANEÆ. The name of the fifty-fourth order in Linnæus's Fragments of a Natural Method, conſiſting of the following plants, which not being connected together by numerous relations in their habit and ſtructure as the natural families, are aſſembled into one head, under the title of Miſcellaneous Plants. Such of them as ſeem moſt nearly connected, we have placed together, and diſtinguiſhed from the others by a letter of the Greek alphabet; a method which we ſhall obſerve on other ſimilar occaſions.

	Linnæan Genera.			*Engliſh Names.*
α	*Datiſca*,	—	—	Baſtard hemp.
	Reſeda,	—	—	Baſtard-rocket, dyer's-weed.
β	*Poterium*,	—	—	Garden-burnet.
	Sanguiſorba,		—	Greater wild-burnet.

γ *Lemna*,

	Linnæan Genera.			*Engliſh Names.*
γ	*Lemna*,	—	—	Duck-meat.
	Piſtia,	—	—	Kodda-pail.
δ	*Coriaria*,	—	—	Myrtle-leaved ſumach.
	Empetrum,	—	—	Black-berried heath, or crow-berries.
ε	*Achyranthes*,		—	Cadelari.
	Amaranthus,		—	Amaranth, or flower-gentle.
	Celoſia,	—	—	Cock's-comb.
	Gomphrena,	—	—	Globe-amaranth.
	Ireſine.			
	Phytolacca,	—	—	American night-ſhade.
ζ	*Nymphæa*,	—	—	Water-lily.
	Sarracenia,	—	—	Side-ſaddle flower.
η	*Cedrela*,	—	—	Barbadoes cedar.
	Swietenia,	—	—	Mahogany.
θ	*Corrigiola*.			
	Limeum.			
	Telephium,	—	—	True orpine.

Dyer's weed, or wild woad, by ſome called weld, is chiefly eſteemed by the dyers for its fine yellow colour. In medicine it is little uſed; yet the root is eſteemed aperient, and ſometimes given in decoction, and the juice of the plant promotes perſpiration. This is now generally believed to be the plant with which the Picts, the ancient inhabitants of Britain, painted their bodies; the rather, as the plant in queſtion is a native of this iſland; whereas woad, (Iſatis of Linnæus) the plant contended for by ſome, has been introduced into Britain ſince that time.

The flowers of Egyptian reſeda, termed likewiſe, mignionette of Egypt, have a very ſweet, agreeable ſmell.

Burnet is of a heating, drying nature, cordial and alexipharmic; in ſummer the leaves are uſed in cool tankard, to give the wine an agreeable flavour. The powder of the root is commended againſt ſpitting of blood, bleeding at the noſe, dyſenteries, and diſeaſes attended with violent ſecre-

tions. In winter and ſpring, the young tender leaves are uſed in ſallads. Greater wild burnet, ſtript of its bark, is ſometimes applied with ſucceſs to recent wounds; the dried powder ſtops the progreſs of cancerous ulcers.

Myrtle-leaved ſumach is much uſed in the South of France, where it naturally grows, for tanning of leather, whence it has been termed by ſome, tanner's ſumach. The ſame plant dyes a beautiful-black colour. The berries are dangerous, and when eaten, generally occaſion vertigoes, and epilepſies. The old leaves, when browſed upon by cattle, have the ſame effect; the young leaves have no ſuch pernicious quality.

The leaves and roots of American night-ſhade, (the *Phytolacca decandra* of Linnæus) ſometimes termed pork-phyſic, are anodyne. The juice of the root is a violent purgative, and therefore to be uſed with caution; the berries, when ripe, give a very beautiful purple-red tincture. The leaves are uſed externally in diſcuſſing painful ſwellings. In North America the inhabitants boil the young ſhoots, and eat them like ſpinach. The Vignerons in Portugal, ſays Mr. Miller, for many years made uſe of the juice of the berries of this plant for mixing with their red port wines, to which it gave a deep colour, and when a great quantity was added, a very diſagreeable taſte. A complaint of this practice having been made to his Portugueze majeſty, he commanded that the ſtems of this plant ſhould be cut down before they produced berries, to prevent the further adulteration of the wines. *Vide* MILLER'S GARDENER'S DICTIONARY, *Voce* PHYTOLACCA.

The wood of Barbadoes cedar, (*cedrela odorata*,) and of mahogany, (*Swietenia mahagoni*,) has an aromatic, balſamic, and agreeable ſmell. The former is employed in the Weſt-Indies, on account of its pliancy, for making canoes of a ſingle piece, as well as planks, and ſhingles for covering houſes, and houſehold furniture. There are canoes in theſe places, ſays Miller, formed out of the trunks of theſe trees, which are forty feet long, and ſix broad. As the worms are apt to eat the wood of the Barbadoes cedar, it is not proper for

for building of ſhips, though frequently uſed both in building and ſheathing veſſels. The ſame objection does not lie againſt mahogany, which is leſs liable to be attacked by worms than oak; ſo that mahogany ſhips are preferable to any other, not only for the reaſon juſt mentioned, but becauſe the wood is very durable, and buries gun-ſhot without ſplintering. The excellency of mahogany for all domeſtic uſes, is too well known in England to require any eulogiums in this place.

MODUS *florendi*, a mode of flowering. *Vide* INFLORESCENTIA.

MONADELPHIA, (from μονος, alone; and ἀδελφία, a brotherhood,) a ſingle brotherhood. The name of the ſixteenth claſs in Linnæus's Sexual Syſtem, conſiſting of plants with hermaphrodite flowers; in which all the ſtamina, or male organs of generation, are united below into one body or cylinder, through which paſſes the pointal or female organ. The particular claſſic characters of the plants in queſtion, beſides that expreſſed in the title, have been already given under the article COLUMNIFERÆ; to which natural order, moſt of the plants in the claſs *monadelphia* are referred. The principal of theſe characters are the following.

I. A permanent flower-cup, and generally double.

II. Five heart-ſhaped petals, cloſely embracing one another above, ſo as to form the appearance of a ſingle petal.

III. The *anthers*, or tops of the ſtamina, kidney-ſhaped, and ſlightly attached to the filaments by the middle.

IV. The receptacle of the fructification, or that to which the flower and fruit are attached, is prominent in the middle of the flower.

V. The ſeeds, kidney-ſhaped.

The orders of the claſs are five, from the number of united ſtamina.

Hermannia, waltheria, and melochia, have five ſtamina.

Crane's-bill, connarus, and hugonia, have ten.

Brownæa has eleven.

Pentapetes, twelve.

Silk cotton-tree, Æthiopian ſour-gourd, Indian mallow, napæa, marſh-mallow, hollyhock, mallow, lavatera, baſtard mallow, urena, cotton, Syrian mallow, ſtewartia, and camellia, have numerous ſtamina.

In ſome ſpecies of geranium or crane's bill, the ſtamina are diſtinct. In others, the filaments are alternately furniſhed with anthers.

A ſpecies of ſilk cotton tree, termed by Linnæus, *bombax pentandrum* has only five ſtamina.

The genera of this claſs were formerly diſtinguiſhed by the fruit; which being found inſufficient, ſeveral botaniſts had recourſe to the leaves as an auxiliary. Linnæus diſtinguiſhes the genera chiefly by the calyx, which is generally double in plants of the laſt order.

MONANDRIA, (from μονος, alone, and ἀνηρ, a man or huſband); the name of the firſt claſs in Linnæus's Sexual Syſtem; conſiſting of plants with hermaphrodite flowers, which have only one *ſtamen* or male organ.

This claſs is ſubdivided, like the other plain claſſes in the ſame ſyſtem, from the number of the ſtyles or female organs, into two orders.

Indian flowering-reed, ginger, *coſtus*, alpinia, Indian arrow-root, turmerick, *kæmpferia*, *thalia*, American hog-weed, jointed glaſs-wort, and hippuris, have only one ſtyle.

Tickſeed, callitriche, blite, and cinna, have two ſtyles.

MONANGIÆ, (from μονος, alone, and αγγος, a veſſel); the name of the fifteenth claſs in Boerhaave's Method; conſiſting of plants with a ſingle ſeed-veſſel, that is not divided internally into more than one cell. It is exemplified in looſe-ſtrife, water-leaf, and pimpernel.

MONOCOTYLEDONES *Plantæ*, (from μονος, alone, and *cotyledon*, a lobe or ſeed-leaf); plants ſo termed, whoſe ſeeds have only one lobe, and conſequently riſe with a ſingle ſeed-leaf. The term is oppoſed to *dicotyledones*, which includes plants that riſe with two ſeed leaves.

The diſtinction of the lobes of the ſeed was firſt obſerved by Cæſalpinus, who thence denominated ſeeds, *univalvia* and

and *bivalvia*. Mr. Ray afterwards employed it as a primary diviſion in the conſtruction of his ingenious method. *Vide* COTYLEDONES.

MONŒCIA, (from μονος, alone, and οἰκια, a houſe); the name of the twenty-firſt claſs in Linnæus's Sexual Method; conſiſting of plants which have male and female flowers placed apart, that is, within different covers, on the ſame root.

The plants then in the claſs *monœcia* are not hermaphrodite, as thoſe of the greateſt number of claſſes in the Sexual Syſtem; nor male and female upon different roots, as in the claſs *diœcia*; but androgynous; that is, conſiſt of male and female flowers upon different parts of the ſame plant. *Vide* ANDROGYNA *Planta*.

In arranging the genera of a ſyſtem, founded, like that of Linnæus, upon the ſexes of plants, it is of the utmoſt conſequence to pay the ſtricteſt attention to that real or ſuppoſed diſtinction: as by arranging ſeveral genera or ſpecies of different ſexes under one claſs or order, the very intention of the arrangement, which is profeſſedly to facilitate the knowledge of plants, is totally defeated. Obvious as this obſervation muſt appear, it has not always been attended to by Linnæus; who, in claſſing and new-modelling the genera, has frequently deviated from the principles of his plan, by confounding plants of different ſexes under the ſame claſs, order, and genus.—Inſtances of this impropriety have been already given in the article *diœcia*.

The plants of the following liſt, which, in ſtrict conformity to the rules of arrangement, ought to have been referred to the claſs *monœcia*, are arranged by Linnæus under claſſes and genera, containing hermaphrodite flowers:

Callitriche verna,
Plantago uniflora,
Rumex ſpinoſus,
Glycine monoica,
Arum triphyllum,
Mercurialis ambigua.

The orders in this claſs are derived from the number, union,

and ſituation of the ſtamina, or male organs; circumſtances which conſtitute the primary characters in the hermaphrodite claſſes of plants. They are eleven in number, and diſtinguiſhed by the ſame names with thoſe of the claſſes juſt mentioned. Thus,

Cynomorium, triple-headed pond-weed, ceratocarpus, and elaterium, have only one ſtamen, or male organ.

Anguria and duck-meat have two ſtamina.

Omphalea, cat's tail, burr-reed, Job's tears, Indian wheat, tripſacum, olyra, carex, tragia, axyris, jack-in-a-box, and ſea-ſide-laurel, have three ſtamina.

Centella, birch, box, nettle, and mulberry, have four ſtamina.

Leſſer burdock, ambroſia, parthenium, Jeſuit's-bark-tree, amaranthus, and ſolandra, have five ſtamina.

Zizania and pharus have ſix ſtamina.

Guettarda has ſeven ſtamina.

Ceratophyllum, water-milfoil, arrow-head, dog's cabbage, garden-burnet, oak, walnut, beach, horn-beam, hazel-nut, plane-tree, and ſweet gum, have ſeveral ſtamina.

Pine, arbor-vitæ, cypreſs, plukenetia, dalechampia, acalypha, baſtard ricinus, caſſava, palma-chriſti, ſand-box-tree, manchineel-tree, and ſterculia, have their ſtamina united below into a cylinder.

Serpent cucumber, male balſam-apple, gourd, cucumber, bryony and ſingle-ſeeded cucumber, have their ſtamina united above by the anthers into a cylinder.

Baſtard orpine has the ſtamina placed upon the female organ; a circumſtance which involves an abſurdity when affirmed of any plant of the claſs in queſtion; and which, if true, ſhould moſt certainly have determined the author to place the genus in the claſs *gynandria*, of which the circumſtance juſt mentioned is the ſtriking and claſſic character.

To obviate this objection, it has been obſerved by M. Gouan, that both in baſtard orpine and clutia, which latter belongs to a ſimilar order in the claſs *diœcia*, the *piſtillum*, or female organ, is entirely wanting in the male flowers: yet, as the ſtamina are inſerted into the place which the *piſtillum* would

would occupy, if the flowers were hermaphrodite, he, therefore, concludes there is no impropriety in eſtabliſhing an order from that circumſtance. To illuſtrate this, he conſiders the receptacle of the flower as divided into four concentric circles: the calyx, or flower-cup, conſtitutes the firſt or outermoſt circle; the petals occupy the ſecond; the ſtamina are placed in the third; and the *piſtillum*, or female organ, poſſeſſes the innermoſt or middle circle. Hence it follows, continues our author, that even when the ſtamina are inſerted into the inner ſide of the petals, they ſtill occupy a circle which is concentric to that of the petals, and placed without that of the pointal. The ſtamina, therefore, in ſuch circumſtances, cannot be reckoned out of their place. But if the middle circle of the receptacle, which is eſſentially deſtined for the *piſtillum*, ſhould, in the abſence even of that organ, be occupied by the ſtamina, theſe laſt are then quite out of their place, and may properly be conſidered as being attached to the *piſtillum*, when inſerted into the place which that organ, if it exiſted, would certainly occupy.

I ſhall only obſerve upon this ingenious remark of the French author, that by the ſame way of reaſoning, all the plants of the claſſes *monœcia* and *diœcia*, might be referred to the claſs *gynandria* in the Sexual Method; as in theſe claſſes the female organ is entirely wanting in the male plants, and the ſtamina occupy the centre of the receptacle.

MONOGRAPHI, (from μονος, alone, and γραφω, to write); a claſs of botanical writers ſo termed by Linnæus, who have beſtowed their attention and reſearches upon a ſingle vegetable. Of this kind is Dillenius's Treatiſe on Fig-marigold; Kæmpfer on Tea; Boerhaave on Silver-tree; Haller on Garlick, and the Mountain-ſpeedwells; Breynius and Lafitau on Ginſeng; Bradley on the Aloe; and ſeveral diſſertations of Linnæus in the *Amœnitates Academicæ*.

MONOGYNIA, (from μονος, alone, and γυνη, a woman, or wife); the name of the firſt order or ſubdiviſion in the

firſt

firſt thirteen claſſes of Linnæus's Sexual Method; conſiſting of plants, which, beſides their agreement in the claſſic character generally derived from the number of ſtamina, have only one ſtyle or female organ.

MONOPERIANTHÆ, (from μονος, alone, περι, around, and ανθος, a flower); the name of a claſs in Wachendorffius's Natural Method; conſiſting of plants with viſible flowers, which have only one of the covers; that is, want either the flower-cup or petals. It is exemplified in ladies mantle, wild orach, hellebore, meadow-rue, medeola, rhubarb, American night-ſhade, aſarabacca, and ſeveral others.

MONOPETALOIDES *Flos*. *Vide* MULTIFIDUS *Flos*.

MONOPETALUS *Flos*, (from μονος, alone, ſingle, and πεταλον, a leaf). *Vide* COROLLA.

MONOPETALI, the name of two claſſes in Rivinus's Method; conſiſting of plants whoſe flowers are compoſed of one petal, which, in its form, is either regular or irregular. The regular flower of one petal is exemplied in borage, buglos, tobacco, and the bell-ſhaped flowers; the irregular flowers of one petal, are the lipped and maſqued flowers of Tournefort, the *didynamia* of Linnæus and the Sexualiſts. Day-nettle, balm, mint, fox-glove, calves-ſnout, and marjoram, furniſh examples.

MONOPHYTANTHÆ, (from μονος, alone, φυτον, a plant, and ἀνθος, a flower); the name of a claſs in Wachendorffius's Natural Method; conſiſting of plants which have male and female flowers placed apart upon the ſame root. It correſponds to the claſs *monœcia* in the Sexual Syſtem. *Vide* MONOECIA.

MORBUS, a diſeaſe. The diſeaſes of plants, ſo far as they regard botany, will fall properly to be conſidered under the article VARIETAS, whither we refer the reader.

MOTUS, motion; when applied to plants, the term motion is very limited, and expreſſive not of an abſolute change of place, but of direction. The following obſervations on this curious ſubject, may, perhaps, prove not unentertaining to the reader.

And firſt of the direction of roots and trunks. The direction

tion of the roots and ſtems of plants is totally oppoſite; the former either running directly downwards, or extending themſelves tranſverſely or horizontally under the ſurface of the earth: the latter exhibiting motions of a ſimilar nature, but in a contrary direction. The direction of the root is never vertical, except in the upata or ſanar of Senegal, the roots of which twiſting, riſe vertically upwards a foot above the ſurface of the earth, and are ſometimes covered by the flux of the ſea.

Familiar as the appearance is, naturaliſts are not agreed with reſpect to the cauſes which determine the roots of plants to tend univerſally downwards, either in a horizontal or perpendicular direction, and the ſtems, on the contrary, to mount perpendicularly or horizontally upwards. So conſtant, however, are theſe oppoſite directions, that a plant being taken out of the earth, and replaced in it in ſuch manner that the root is uppermoſt, and the ſtem lowermoſt; the root will quickly curve downwards, the ſtem upwards, till each has reſumed the direction which is proper and natural to itſelf.

All the cauſes which concur in promoting the growth of plants, appear likewiſe to operate in determining their direction. Such are the air, the ſun, light, and the moiſt warm vapours which ariſe out of the earth. The three firſt ſeem to concur moſt certainly to the direction of the ſtem; air and moiſture to that of the root.

If any number of plants are placed in pots in a room which only admits the light by a ſingle hole, the ſtems will incline or direct themſelves towards that ſide. In thick foreſts, the young trees always lean to the ſide where the light penetrates. The new ſhoots of an eſpalier detach themſelves from the wall which robs them of the air, the ſun, and the light. It is in queſt of the ſame excellent gifts of Nature, that the lateral branches of trees abandoning the direction of the ſtem, ſpread and extend themſelves in a direction parallel to the ſoil, even when planted on a declivity.

In like manner it appears, that the roots penetrate more

or

or leſs deeply into the ground, either in a perpendicular or horizontal direction, in proportion to their greater or leſs tendency to ſearch for moiſture. Thus it is a well known fact, that, in the neighbourhood of canals, ditches filled with water, and ground newly tilled, the roots of plants abandon their natural direction, and, as it were, ſteer their courſe towards the fine air, rich juices, and grateful humidity which their ſituation has placed within their reach.—So ſtrongly indeed are the roots of plants attracted by water, that they frequently relinquiſh the ſoil, and penetrate into the very heart of ditches and canals.

This force of extenſion appears to be greater in roots than in ſtems. The branch ſurmounts an obſtacle, by leaving its natural direction, and overtopping it. The root, on the contrary, without once going out of its way, pierces the hardeſt ſoils, penetrates into walls, which it overturns, and even into rocks, which it burſts.

Although the natural motion of the trunk be to aſcend, as was ſuggeſted above, yet is it forced oftentimes to deſcend: for the trunk-roots growing out of ſome plants near the ground, and ſhrinking into it, ſerve, like ſo many ropes, to pluck the trunk annually lower and lower into the ground, along with them. If theſe trunk-roots break out only about the bottom of the trunk, then it gradually deſcends into the earth, and is converted into a root (*Vide* BULBUS); but if the trunk is very ſlender, and the trunk-roots break forth all along it, then it creeps horizontally; the trunk-roots in queſtion tethering it, as it trails along, to the ground, as in ſtrawberry, cinquefoil, and mint.

I cloſe the preſent ſubject with this obſervation, that the direction of the roots and ſtems of plants ſeems to be regulated, in a great meaſure, by the vapours which they contain, but more by thoſe which ariſe from the ſoil in which they grow; and, that heat, the ſun, or the light, the cauſes already ſuggeſted, appear to contribute to that direction, only in ſo far as they augment or regulate the current of theſe nouriſhing vapours.

Trunks are not, however, the only parts of plants which direct

direct their courſe towards the air and the light of the ſun. There are flowers, which, quitting their perpendicular direction, preſent their ſurface directly to that luminous body, and follow its ſituation in its diurnal courſe. This ſort of motion has been called by ſome writers, NUTATION; and the plants which are ſubject to it, have been termed *heliotropæ*; that is, turning with the ſun. Of this kind are baſtard-rocket, dyer's weed, ſun-flower, turnſole, and the greateſt part of the compound flowers with plain tongue-ſhaped petals, the *ſemifloſculoſi* of Tournefort, the *planipetalæ* of Ray, and the *ligulati* of Linnæus. In theſe flowers, the diſk or ſurface looks towards the eaſt in the morning, the ſouth at noon, and the weſt at night.

The ſpikes or ears of corn, which hang down by their weight, are obſerved, in like manner, to incline themſelves towards the ſun, never to the north. The ſtems of draba, trientalis, and a ſpecies of baſtard fever-few with egg-ſhaped and notched leaves, incline or hang downwards during the night.

The obſervations of La Hire, Hales, and Bonnet, eſtabliſh, that theſe motions are occaſioned, not by any twiſting in the ſtem, but by the dryneſs of the fibres, which, by being expoſed to the heat of the ſun, contract, and thus determine the *nutation* of the flowers and young ſtems. It is in this manner that moiſture and dryneſs alternately dilate and contract the plant improperly called the roſe of Jericho; an appearance which is likewiſe obſerved in the beards of oats, and in thoſe of the capſules of crane's bill.

The direction of the leaves of ſeveral plants ſuffers conſiderable changes during the night. This is ſo certain, that if a botaniſt who is accuſtomed to the port or habit of plants, were to examine, in a ſummer-night, the plants which cover any particular meadow, he would find ſeveral which he could not recognize by that character. The ſame changes happen, when the moiſture of the day correſponds to that of the night. The change of direction juſt mentioned is particularly ſenſible in compound leaves. During the heat of the ſun in the day-time, the pinnated or winged leaves

of

of ſeveral plants, particularly thoſe of the pea-bloom or leguminous tribe, riſe vertically upwards, and form a right angle with the common foot-ſtalk; the lobes or leſſer leaves, which ſtand oppoſite, being applied cloſely together by their upper ſurface. Several ſimple leaves, particularly thoſe of *ſigeſbeckia*, and Indian mallow, (*urena*,) when their upper ſurface is expoſed to an ardent ſun, become, in like manner, concave; which demonſtrates their analogy with the winged leaves juſt mentioned. The artificial heat of a red-hot iron has the ſame effect upon both; but the plants ſuffer greatly by the experiment. M. Adanſon ſays, he has obſerved a ſimilar motion in the leaves of ſeveral ſpecies of wild orach, after ſun-ſet.

In that ſtate of the atmoſphere which generally precedes a ſtorm, and is found moſt favourable for vegetation, I mean in a cloſe, moiſt and cloudy air, the winged leaves extend themſelves along the common foot-ſtalk. The ſame appearance is obſerved in the leaves of the ſenſitive plant, when it has been kept for ſeveral days in a cellar below ground.

After ſun-ſet, and during the fall of the dew, they incline ſtill lower, hang vertically downwards, and are applied cloſely together, like the leaves of a book, by the lower ſurface under the ſtalk, with which they ſtand at right angles. The odd lobe, if there is one at the extremity of the leaf, folds itſelf up, till it has reached the firſt pair of lobes or ſmaller leaves in its neighbourhood. This motion, which Linnæus calls the SLEEP of plants, and can be produced by an artificial as well as natural dew, has been obſerved not only in compound leaves, ſuch as thoſe of the pea-bloom plants, but likewiſe in ſome ſimple leaves, particularly thoſe of balſam and baſtard fever-few.

The ſmall leaves of falſe acacia and liquorice hang downwards during the night, but are not united by the under ſurface, like the greater part of leguminous plants. Thoſe of the ſenſitive plant, *mimoſa pudica*, extend themſelves longitudinally along the common foot-ſtalk, and infold one another mutually. The ſmall lobes of ſeveral ſpecies of trefoil, lucern, and lotus, are united only by their

their ſummits, and form a cavity which contains the young flowers, and ſhelters them from cold and other injuries to which they are liable in the night-time. In ſome ſimple leaves, a ſimilar appearance is obſerved. Thus the upper leaves of garden orach approach during the night, unite perpendicularly, embrace the young ſhoot, and do not relinquiſh that poſture till the ſun has diſſipated the humidity of the air.

The action of the ſun has a very different effect upon theſe leaves, as well as thoſe of ſome mallows, blites, and trefoils, which, like the flowers mentioned above, follow the direction of that body, and preſent to it their external ſurface or diſk.

That ſpecies of motion peculiar to ſome flowers, which open and ſhut at certain ſtated times, is explained on nearly the ſame principles with thoſe of the winged leaves mentioned above. For particulars on this ſubject, the reader is referred to the article VIGILIÆ *Plantarum*, by which term the motion in queſtion is generally diſtinguiſhed.

The irritability, if I may ſo term it, of thoſe plants called ſenſitive, has been fully conſidered under the article LOMENTACEÆ, which ſee.

The laſt kind of motion obſerved in plants, is elaſticity; a ſlight irritation at the baſe of the ſtamina of berberry, melon-thiſtle, and little ſun-flower, (*ciſtus helianthemum*,) cauſes a convulſive motion, or trembling in the parts; the ſtamina contract, approach the pointal, and do not recover their former poſition. The fleſhy fruits of balſam, ſpirting cucumber, and wood-ſorrel, contract with violence when arrived at maturity, and dart the ſeeds contained within them to a conſiderable diſtance. Dry ſeed-veſſels, as the capſules of moſt of the ranunculus tribe, aconite, and lark-ſpur, as likewiſe thoſe of fraxinella, and the liliaceous and leguminous plants, burſt open, in like manner, with a conſiderable force.

To conclude, there are plants, which, far from being endued with that elaſticity or ſpring we have been illuſtrating, have not even the faculty of reſuming their former ſituation,

when

when, by any means, they have been made to change it. Of this kind are the flowers of a ſpecies of dragon's head of Virginia, which, on whatever ſide they are turned, diſcover not the ſmalleſt tendency to recover their former poſition.

MULTICAPSULARES, (from *multus*, many, and *capſula*, a ſpecies of ſeed-veſſel); the name of a claſs in Morriſon's, Hermannus's, and Chriſtopher Knaut's Methods; conſiſting of plants which have more dry capſules or ſeed veſſels than one. Of this kind are pæony, columbine, hellebore, aconite, lark-ſpur, and ſeveral others.

MULTIFIDUS *Flos*, (from *multus*, many, and *findo*, to cleave); a flower ſo termed by Linnæus, which conſiſts of one petal divided into ſeveral ſegments. It is ſynonymous to the *laciniatus flos* of Tournefort, and the *monopetaloides* of other authors.

MULTIPLICATUS *Flos*, a luxuriant flower, whoſe petals are multiplied ſo as to exclude a part of the ſtamina. *Vide* LUXURIANS *Flos*.

A multiplied luxuriant flower differs from a full one, the higheſt degree of luxuriance, in that the petals of the latter are ſo multiplied as to exclude all the ſtamina: whereas, thoſe of the former are only repeated or multiplied, two, three, or four times, to the excluſion of but a ſmall part of the eſſential organs.

A double flower properly ſo called, that is, a flower whoſe petals are twice repeated, is the firſt and loweſt degree of luxuriance.

A triple flower, whoſe petals are thrice repeated, is the ſecond degree of luxuriance. Examples of either degree are afforded by ſome ſpecies of campanula and thorn-apple.

Flowers of one petal are frequently multiplied, but rarely found full. *Vide* PLENUS *Flos*.

Flowers with more than one petal are ſubject to all degrees of luxuriance, from the loweſt to the higheſt. That they are ſubject to multiplication, the genus anemone furniſhes ſufficient proofs.

In ſome flowers, the multiplication is effected, not by the

the petals, but by the ſcales or diviſions of the flower-cup; ſuch inſtances, however, are rare. In a ſpecies of dianthus or pink, mentioned by Linnæus, the ſcales of the calyx are multiplied to ſuch a degree as to give the whole flower the appearance of a ſpike or ear of corn. The luxuriance of ſeveral mountain graſſes, particularly of *feſtuca ſpiculis viviparis*, is of the ſame kind, being effected by the monſtrous growth of the huſks of the calyx, which are metamorphoſed into leaves. The ſame appearance obtains in a ſpecies of willow called *ſalix roſea*, in which, both male and female organs being deſtroyed by inſects, the ſcales of the catkins are lengthened into leaves. In a ſpecies of plantain called *plantago roſea*, the floral leaves of the ſpike or head of flowers undergo a ſimilar enlargement.

In ſome plants the flower-cup is coloured; a circumſtance which not rarely miſleads inattentive obſervers, who are led to conſider ſuch an unuſual appearance as a repetition of the petals. Some ſpecies of primroſe furniſh examples of the appearance in queſtion.

All multiplied flowers are monſtrous, and are accidentally produced from ſingle ones. *Vide* VARIETAS.

MULTISILIQUÆ, (from *multus*, many, and *ſiliqua*, a ſpecies of pod); the name of the twenty-ſixth order in Linnæus's Fragments of a Natural Method; conſiſting of plants which have more ſeed-veſſels than one. From the etymology of the term, one would naturally imagine, that the ſeed-veſſels in queſtion were of that kind, called by Linnæus, *ſiliqua*, or pod: but the fact is, that not a ſingle plant of this order bears pods; the greater part having many dry capſules; and the remainder being furniſhed properly with no ſeed-veſſel, but bearing numerous diſtinct ſeeds.

On this account, Moriſon's title, *multicapſulares*, would have been more proper than the preſent; though even that would have been expreſſive of part of the plants only.

Liſt of Genera *contained in this Order.*

Linnæan Genera.	*Engliſh Names.*
α *Aconitum*, —	— Monks-hood, wolf's bane.

	Linnæan Genera.		*Engliſh Names.*
	Aquilegia,	—	Columbine.
	Delphinium,	—	Lark-ſpur.
	Pæonia,	—	Pæony.
β	*Dictamnus*,	—	Fraxinella, white dittany.
	Peganum,	—	Wild Syrian rue.
	Ruta,	—	Rue.
γ	*Adonis*,	—	Adonis, or bird's eye.
	Caltha,	—	Marſh-marigold.
	Garidella,	—	Fennel-flower of Crete.
	Helleborus	—	Hellebore.
	Iſopyrum.		
	Myoſurus,	—	Mouſe-tail.
	Nigella,	—	Fennel-flower, or devil in a buſh.
	Ranunculus,	—	Crowfoot.
	Trollius,	—	Globe-ranunculus, or locker gowlans.
δ	*Actæa*,	—	Herb-chriſtopher, or bane-berries.
	Anemone,	—	Wind-flower, anemone.
	Atragene.		
	Clematis,	—	Virgin's bower.
	Thalictrum,	—	Meadow-rue.

Habit and Structure of the Plants of this Order.

Theſe plants are moſtly perennial herbs: the ſtems of ſome are erect; others creep upon the ground, and produce roots near the origin of each leaf, as in ſome ſpecies of ranunculus; others climb, and attach themſelves to the bodies in their neighbourhood, either by the foot-ſtalk of their leaves, as virgin's bower, or by tendrils which terminate the foot-ſtalk, as atragene. The greateſt height of thoſe which riſe erect, as lark-ſpur, ſeldom exceeds eight feet. Thoſe which climb, rarely exceed fifteen or twenty feet.

The ROOTS are generally fleſhy. In ſome ſpecies of anemone they are hand-ſhaped; in others, as likewiſe in ſeveral

ſeveral ſpecies of ranunculus, they are finger-ſhaped, or cylindric. In ſome ſpecies of hellebore and ranunculus, they are divided into ſpherical knobs. In ſome plants too of this order, the roots are fibrous.

The STEMS and YOUNG BRANCHES are cylindric.

The LEAVES, which are of different forms, being ſometimes ſimple and entire, ſometimes hand-ſhaped or winged, are generally alternate, except in virgin's bower and atragene, which bear oppoſite leaves.

The foot-ſtalk, which is ſometimes cylindric, ſometimes angular, is membranous, and very large at its origin, ſurrounding a great part of the ſtem from which it proceeds. In *iſopyrum*, the membrane in queſtion is terminated on each ſide by two ſmall teeth, in the form of *ſtipulæ* or ſcales. In marſh-marigold it forms a ſheath or glove, which is entire, ſhaped like a cylinder, and quite ſurrounds the ſtem.

The FLOWERS are hermaphrodite.

They proceed either ſingly from the wings of the leaves, or termination of the branches, as in pæony, globe ranunculus, marſh-marigold, mouſe-tail, fennel-flower, and ſome ſpecies of ranunculus and anemone; or terminate the branches in a ſpike, panicle or head, as in aconite, lark-ſpur, columbine, meadow-rue, and fraxinella. The flower of the winter aconite, a ſpecies of hellebore, in coming out of the earth, is folded up in a ſpiral manner upon its foot-ſtalk.

Theſe flowers are eaſily rendered double by culture. Ranunculus, anemone, pæony, monk's-hood, lark-ſpur, columbine, and fennel-flower, are well-known examples.

The CALYX or flower-cup is wanting in marſh-marigold, monk's-hood, lark ſpur, columbine, fennel-flower, meadow-rue, anemone, globe ranunculus, *iſopyrum*, hellebore, and virgin's bower; in the reſt it is compoſed generally of five pieces, which fall with the petals. The calyx of rue, peganum, and pæony, is permanent.

The PETALS are in number from four to fifteen, generally equal, and ſometimes, as in anemone, diſpoſed in two or three ſeries: five is the prevailing number.

The NECTARIUM in this order is various. In the greater

number, particularly lark ſpur and columbine, it is ſhaped like a horn or ſpur, and forms a tube at the bottom of the flower. In ranunculus it is a ſmall prominence or melliferous pore in the claw of each petal. In aconite, or monk's hood, it is compoſed of two long ſingular appearances like ſtyles, that are lodged within the upper petal, which reſembles a helmet.

The STAMINA are, in number, from five to three hundred, diſtinct, and attached, generally in ſeveral rows or ſeries, to the receptacle.

The SEED-BUDS are generally numerous. The ſtyle is frequently wanting.

The SEED-VESSEL is wanting in ranunculus, meadow-rue, adonis, atragene, virgin's bower, and anemone. In the reſt it is compoſed of ſeveral dry capſules, each containing a ſingle cell.

The SEEDS are numerous, and frequently angular. In anemone, virgin's bower, and atragene, they are terminated each by a beard or hairy tail, which ſome conſider as the remains of the ſtyle.

Moſt of theſe plants are acrid, and many of them poiſonous. In general, plants that have a great number of ſtamina, are noxious in their quality. Thoſe of this order that are cautiouſly to be avoided on this account, are moſt ſpecies of monk's-hood, columbine, lark-ſpur, wild ſyrian-rue, herb-chriſtopher, hellebore, pæony, and virgin's-bower—Being burnt, theſe plants furniſh a fixed alkali; by diſtillation, there is drawn from them a nitrous and aluminous ſubſtance.

Rue and fraxinella have a ſtrong penetrating ſmell.—With reſpect to their virtues, they are cauſtic and purgative; iſopyrum is hepatic. Hellebore, according to ſome moderns, cauſes convulſions, and ſtiffens the limbs.

Since the time of Theophraſtus, moſt of the ſpecies of monk's-hood have been reckoned a deadly poiſon both to men and brutes. Dioſcorides, however, recommends the external application of common monk's-hood for pains of the eyes. The flowers of a great many ſpecies communicate their noxious quality, by being ſmelled to; and thoſe of the

ſpecies

ſpecies called napellus, being placed upon the head, occaſion a violent megrim. Of the bad qualities of theſe plants, we ſometimes avail ourſelves to get rid of vermin. A decoction of the roots deſtroys bugs; the ſame part being powdered and adminiſtered in bread, or ſome other palatable vehicle, to rats and mice, corrodes and inflames their inteſtines, and ſoon proves mortal; the juice of the plant is uſed to poiſon fleſh with, for the deſtruction of wolves, foxes, and other ravenous beaſts. The beſt antidote to the poiſon of the different monk's-hoods is ſaid to be the root of a ſpecies of the ſame genus, hence termed healthful or wholeſome monk's-hood. It is the *aconitum anthora* of Linnæus. The ſame plant is regarded as efficacious againſt bites of ſerpents and other venomous creatures. The roots have a bitter acrid taſte; the leaves are only bitter; the former are chiefly uſed in medicine, and beſides the excellent quality juſt mentioned, are ſtomachic, and promote perſpiration. The peaſants who gather the plant on the Alps and Pyrenees, uſe it with ſucceſs againſt the bite of mad dogs, and to cure the colic.

It is remarkable that the monk's-hoods with blue flowers are much more virulent than the yellow or white-flowered kinds. Miller aſſerts, from whoſe authority I know not, that the huntſmen of the wolves and other wild beaſts on the Alps dip their arrows into the juice of theſe plants, which renders the wounds made by them deadly.

Columbine is termed in Latin, *aquilegia*, from the reſemblance of its flowers to the claws of an eagle. The leaves of common or wild columbine, the ſpecies uſed in medicine, have been preſcribed in gargariſms for inflammations of the jaws and throat. The ſeeds and roots are reckoned ſucceſsful in facilitating the eruptions of the meaſles and ſmall pox.

An ointment made of the ſeeds of ſtaveſacre, a ſpecies of lark-ſpur, which grows naturally in Italy and the Levant, is ſaid to kill all kinds of lice; whence the plant is ſometime known by the name of louſewort.

The lark-ſpurs are ſo called from the horn or ſpur which

terminates the upper petal, and is termed by Linnæus the *nectarium*. *Delphinium*, which is the Latin appellation of this genus of plants, is expreſſive of the fancied reſemblance of the flowers to a dolphin before they are expanded.

Pæony is ſaid to have derived its name from Pæon, the phyſician, who is reported to have cured Pluto, when wounded by Hercules, with this herb.

Fraxinella is ſo called from the reſemblance of the form of its leaves to thoſe of the fraxinus or aſh, from which circumſtance it was denominated little aſh, as the name imports. In the diſpenſatories it has been long known by the title of *dictamnus*. The ſtalks of this plant abound with an eſſential inflammable oil, eſpecially in great droughts, when, on the approach of a candle or other igneous matter, the ſubſtance in queſtion takes fire, and burns like ſpirit of wine, till it is entirely exhauſted. The roots of this plant have had many virtues attributed to them, but are at preſent only known as an ingredient in ſeveral of our compoſitions. By its bitter quality, dittany is ſaid to kill toads.

Rue, by its aromatic quality, is heating, cordial and ſudorific; all the parts are uſed in medicine, except the roots. Wild Syrian-rue poſſeſſes the ſame virtues in its native ſoil, which is Egypt, Syria, Italy, and Spain.

The leaves of ſtinking black-hellebore are very acrid to the taſte, and highly purgative. Thoſe of the green-flowered kind, being dried and powdered, are accounted good to kill worms in children; the former ſpecies is dangerous. The country-people, however, frequently give the powder of it likewiſe to their children for worms: but how dangerous a medicine it is, may be underſtood by the following fact, related by the ingenious Mr. Martyn. Some years ago, when the ground was covered with a deep ſnow, a flock of ſheep, in Ox-meadow, near Fulborn, in Cambridgeſhire, finding nothing but this herb above the ſnow, eat plentifully of it. They ſoon appeared much out of order, and moſt of them died: ſuch as were ſaved having ſome oil adminiſtered to them in time, which made them vomit up the pernicious herb. Some of thoſe who died, being opened, were found to have the ſtomach greatly inflamed. In

Weſtmoreland,

Weſtmoreland, where this plant grows in great abundance, it has obtained, from its pernicious quality, the name of felon-graſs. Adanſon ſays, that a clyſter of an ounce of a decoction of its root is preferable to any other remedy in apoplectick fits.

Mouſe-tail is ſo termed from its ſeeds, which, after the fall of the flowers, grow in ſlender ſpikes, two or three inches long, reſembling a mouſe's tail.

All the ſpecies of crowfoot are remarkably acrid; yet in ſome parts of France they eat the tuberous roots of a few ſpecies without any bad conſequences. The freſh roots of *ranunculus acris* are uſed by the peaſants as an excellent cautery for their cattle. *Ranunculus ſceleratus* is ſaid to prove mortal to ſheep which feed upon it.

The berries of herb-chriſtopher, which are of a ſhining black, and of the ſize of peaſe, are ſuppoſed to be of very noxious quality. A ſingle berry is inſtant death to poultry and other birds. The root of a ſpecies of herb-chriſtopher, a native of North-America, where it is denominated black ſnake-root, to diſtinguiſh it from common ſnake-root, is ſuppoſed to be an antidote againſt poiſon, and particularly that of the rattle ſnake.

Wood anemone with blue flowers tinged with purple, which grows naturally at Wimbledon, in Surry, and Looton-hoo, in Bedfordſhire, has its leaves frequently covered with the eggs of an inſect, whereby the plant, before the expanſion of its flowers, is frequently miſtaken for a fern.

Anemones, or wind-flowers, (ſo the Greek name imports,) were ſo called, from a ſuppoſition fooliſhly entertained by the ancients, that the flowers of theſe plants never open, except in a briſk wind.

The ſeeds of great wild climber, or traveller's joy, a ſpecies of virgin's bower, which grows naturally in the hedges in many parts of England, make a very fine appearance at the latter end of the year, when they cover the hedges with their plumes or white hairs. Theſe, from their reſemblance to beards, have occaſioned the plant to be generally known, at that ſeaſon, among the country people, by the name of old man's beard. It is very acrid to the taſte, and without

any ſmell; it is frequently uſed as a cauſtic, and for cleanſing old ulcers. The root is ſaid to be purgative.

The leaves of all the ſpecies of clematis being bruiſed, and applied to the ſkin, burn it into carbuncles, as in the plague; and, if applied to the noſtrils in a ſultry day, immediately after being cropped, will cauſe the ſame uneaſy ſenſation as a flame applied to that part would occaſion; hence the title of *flammula*, or little flame, by which this genus of plants was formerly diſtinguiſhed.

MULTISILIQUÆ is likewiſe the name of a claſs in Ray and Boerhaave, conſiſting, as the foregoing term, of plants which have numerous capſules or ſeed-veſſels.

MUSCI, Moſſes. One of the ſeven families or claſſes into which all vegetables are divided by Linnæus in the Philoſophia Botanica. The characteriſtics of theſe plants, according to the Sexual Syſtem, are,

I. Anthers, without filaments.

II. The male flower, conſtituted by the preſence of the *anthers*, placed apart from the female, either on the ſame or diſtinct roots.

III. The female flowers deprived of the *piſtillum*.

IV. The ſeeds devoid of both lobes (cotyledones) and proper coverings; ſo that they exhibit the naked embryo.

This tribe of plants, as well as the muſhrooms, ferns, and ſea-weed, is ſtill imperfectly known. Dillenius, profeſſor of botany at Oxford, was the firſt who attempted an arrangement of them. In his Catalogus Plantarum circa Giſſam, publiſhed at Francfort, in 1719; and afterwards in his Hiſtoria Muſcorum, publiſhed at Oxford, in 1741, he divides the Moſſes into ſixteen genera. This arrangement, however, includes the lichens, ſome of the fuci, and other plants which belong to very different families. The work in queſtion is, notwithſtanding, valuable, in having introduced the knowledge of upwards of two hundred plants, which were unknown before Dillenius: it is, beſides, of all his works of this kind, the beſt executed, both for the deſcriptions and figures, and ſhould ſerve as a model to

ſuch

ſuch authors as intend to publiſh in detail the hiſtory of any particular family of plants.

Micheli, in a work entitled, Nova Plantarum Genera, publiſhed at Florence, in folio, in 1729, divides the moſſes into two ſections, from the figure and ſituation of their flowers. Theſe ſections comprehend together ſixteen genera, amongſt which are improperly arranged, like thoſe of Dillenius, ſeveral of the lichens and other ſea-weed.

The diſcovery of the ſeeds of the moſſes, though made by Dillenius in 1719, is arrogated by Linnæus to himſelf, who did not begin to write till 1735. *Vide* FRUCTUS.

In Ray's method the moſſes form the third claſs; in Tournefort's they conſtitute a ſingle genus, by the name of *muſcus*, in the firſt ſection of the ſeventeenth claſs, which comprehends the moſſes, muſhrooms, and ſome of the algæ or ſea-weed, and is diſtinguiſhed by the name of *aſpermæ*, or plants without ſeed; the ſeeds of the moſſes not having been detected by Tournefort.

In the Sexual Syſtem, theſe plants conſtitute the ſecond order of the claſs *cryptogamia*, which contains all the plants, in which the parts of the flower and fruit are wanting, or not conſpicuous. This order is ſubdivided into eleven genera, from the preſence or abſence of the calyx, which, in theſe plants, is a veil or cover like a Monk's cowl, that is placed over the male organs or tops of the ſtamina, and denominated *calyptra*; from the ſexes of the plants, which bear male and female flowers, ſometimes on the ſame, ſometimes on diſtinct roots; and from the manner of growth of the female flowers, which are ſometimes produced ſingly, ſometimes in bunches or cones. Theſe diſtinctions are moſtly borrowed from Dillenius, whoſe excellence in developing this part of the vegetable kingdom, Linnæus very readily acknowledges.

MUSCI, is likewiſe the name of the fifty-ſixth order in Linnæus's Fragments of a Natural Method, conſiſting of the following genera, which are exactly thoſe of the ſecond order in the claſs *cryptogamia*, and agree in the general characters juſt mentioned.

Bryum,

Linnæan Genera.			*Engliſh Names.*
Bryum,	—	—	Thread-moſs.
Buxbaumia.			
Fontinalis,	—	—	Water-moſs.
Hypnum,	—	—	Feather-moſs.
Lycopodium,	—	—	Club-moſs.
Mnium,	—	—	Marſh-moſs.
Phaſcum,	—	—	Earth-moſs.
Polytrichum,	—	—	Golden maiden-hair.
Porella,	—	—	Hair-moſs.
Sphagnum,	—	—	Bog-moſs.
Splachnum,	—	—	Bottle-moſs.

Habit and Structure of the Plants of this Order.

Theſe plants reſemble the pines, firs, and other evergreens of that claſs, in the form and diſpoſition of their leaves, and manner of growth of the female flowers, which are generally formed into a cone.

They frequently creep, and extend themſelves like a carpet, upon the ground, trees, and ſtones, being generally collected into bunches or tufts. The ſmalleſt, as *buxbaumia*, are only four lines, or the third part of an inch, in height; and the largeſt ſpecies of *lycopodium*, do not exceed five or ſix inches.

Few of the moſſes are annual plants: ſmall as they are, the greater number are perennial and evergreens. Their growth is remarkably ſlow, as may be judged by the time which the *anthers*, or male organs, take to ripen; this, reckoning from the firſt appearance of the *anthers* to the diſperſion of their powder or male duſt for the purpoſe of impregnation, is generally four or ſix months.

Although preſerved dry ſeveral years, theſe plants have the ſingular property of reſuming their original verdure upon being moiſtened; perhaps, they likewiſe reſume their vegetative faculty—a circumſtance which future experiments muſt determine.

Moſſes delight in a cool moiſt ſituation, and north expoſure, where they are ſcreened from the ſun.

The ROOTS are fibrous, ſlender, branched and ſhort.

The STEMS and branches are cylindric, and weak; they creep upon the ground, and ſtrike root on every ſide.

The LEAVES are very ſmall and undivided, and differ with reſpect to ſituation, being either alternate, oppoſite, or placed by fours round the ſtalk.

They have no foot-ſtalk, nor middle rib that is perceptible, being ſeated immediately upon the ſtem, half of which they embrace in golden maiden-hair; ſo that they do not appear to be true leaves, any more than thoſe of the palms and ferns.

Theſe plants, like the pines, are covered with no ſort of down or pubeſcence.

The FLOWERS are univerſally male and female; in lycopodium, ſphagnum, phaſcum, hypnum, and water-moſs, the male flowers are produced upon the ſame plant with the female, and ſtand above them; in golden maiden-hair, the flowers of different ſexes are produced on diſtinct plants; in *mnium* and *bryum* they are produced, ſometimes on the ſame, ſometimes on diſtinct plants.

The male flowers, which conſiſt entirely of the *anthers*, and their covering, proceed either ſingly or in cluſters from the extremity of the branches, or angles of the leaves; and are ſeated immediately upon the branches, as in porella, and water-moſs; or ſupported by a long foot-ſtalk, as in bryum and golden maiden hair.

The female flowers, which generally reſemble capſules or cones, are all placed immediately upon the ſtem or branches without any foot-ſtalk, and proceed ſingly, either from the wings of the leaves or ſummit of the branches. When produced upon the ſame plant with the male, they are always placed under them.

The female cones of the moſſes greatly reſemble, as we have ſaid, thoſe of the pines, and other evergreen trees of that claſs; the ſcales which form them are true leaves, each containing, in its wing or angle, a ſingle ſeed. When the ſeeds are ripe, the cones in queſtion probably open, for their diſperſion. When ſhut, they reſemble buds, and have

ſometimes

ſometimes been ignorantly miſtaken for ſuch. The female flowers of the genus *porella* have not yet been diſcovered.

The FLOWER-CUP in this order, if it can be called ſuch, is that appearance reſembling a veil or monk's cowl, which, in the male flowers, covers, or is ſuſpended over, the tops of the ſtamina, like an extinguiſher, and is termed by Linnæus, *calyptra*. From the preſence or abſence of this cover, which falls before the opening of the *anthers*, are the genera of this tribe of plants chiefly diſtinguiſhed by Dillenius, and, after him, by Linnæus.

The PETALS in this order are univerſally wanting.

The male and female parts of generation in this numerous claſs of plants, have been deſcribed above. The flowers were, at the ſame time, ſaid to be male and female. In the genus *buxbaumia*, ſo named from Dr. Buxbaum, a German, who firſt diſcovered it in the neighbourhood of Aſtracan, repeated obſervations ſeem to eſtabliſh it beyond a doubt, that the flowers are hermaphrodite. After the fall of the outward covering or veil, formerly mentioned, the *anthers* are found to be covered with another hood, termed by Linnæus, *operculum*, within which, both Mr. Martyn and Dr. Linnæus diſcovered an *anthera* ſuſpended by its filament; and at the bottom of the capſule, formerly conſidered as the *anthera*, were found ſeveral ſeeds under the form of a yellow-green impalpable powder, more unctuous than that of the other moſſes.

This ſingularity obſerved in the genus *buxbaumia* might create a ſuſpicion that the other moſſes, which have their *anthers* covered, like it, with an *operculum*, have, likewiſe, their ſtamina or male organs contained within the ſame covers with the female; and that what have hitherto been judged ſeeds in the cones of the plants regarded as female, are, in fact, only buds or ſhoots which perform the office of ſeeds. But the knowledge we have acquired of the nature of the *anthers* of the other moſſes, and of the powder or duſt which they contain, is ſufficient demonſtration, that what has been termed the capſule in the genus *buxbaumia*, is really an *anthera*, which it every way reſembles externally,

although

although ſomewhat different in its internal ſtructure; that it contains a powder of the ſame nature with the male duſt of other plants; and finally, that it is only a *ſtamen*, or male flower; the female flower being moſt probably to be found on another individual.

With reſpect to the powder contained in the *anthers* of the moſſes, Dillenius aſſures us, that he has frequently ſown of it, with a view to aſcertain its real nature, but could never diſcover in it the ſmalleſt tendency to vegetate, like ſeed; on the contrary, the experiments of the ſame ingenious naturaliſt, and of the learned Haller, ſufficiently evince, that the powder of the female tops or cones of *mnium* being ſown, forms productions in every thing ſimilar to the parent plant.

Upon the whole, there is little doubt, that the cones and ſtars obſerved in the moſſes, are female flowers; and that the capſules and ſmall bodies endowed with a germinating faculty, which are found between the ſcales of theſe cones, are true ſeeds, or at leaſt, ſhoots and ſuckers which ſupply their place.

The moſſes in general are almoſt taſteleſs, have few juices, and being once dried, do not readily imbibe moiſture from the air. Thoſe which grow in water, being thrown into the fire, turn red, and are reduced to aſhes without receiving or communicating any flame; on which account ſome ſuperſtitious people, the Siberians in particular, place water-moſs in their chimnies, as a preſervative againſt fire.

From the male flowers of ſome of the moſſes, particularly of *lycopodium*, is diſperſed a prodigious quantity of yellow, ſulphureous, and inflammable duſt, which, according to Olearius, ſparkles in the fire like ſalt-petre, and is known, like that of the pines, by the name of vegetable ſulphur.

Moſt of the moſſes are purgative. The *ſelago* of Dillenius operates both by vomiting and purging, and is reckoned as violent and dangerous as hellebore. Golden maiden-hair is a powerful ſudorific.

A ſpecies of *lycopodium*, a native of India, and diſtinguiſhed

guiſhed in the Hortus Malabaricus by the name of tana-pouel, is ſaid to be a mighty incentive to venery, and to be frequently uſed by the Indians for that purpoſe.

A decoction of *lycopodium* is employed, with ſucceſs, by the country people in violent diarrhœas. The male duſt is recommended for nephritic pains, and ſuppreſſions of urine. The ſame powder in decoction is uſed externally for deſtroying lice.

With a large ſpecies of *ſphagnum*, the inhabitants of Siberia ſtuff cuſhions and beds.

All theſe plants are of wonderful efficacy in preſerving dry ſuch bodies as are ſuſceptible of moiſture; and in retaining, for a long time, the humidity of young plants, without expoſing them to putrefaction. For this reaſon, ſuch plants as are to be ſent to any conſiderable diſtance, are generally wrapped up in moſs.

MUSCOSÆ, the name of the twentieth claſs in Hermannus's Method; conſiſting of plants without flower-cup or petals. Theſe are the ferns, and moſſes juſt deſcribed: for as to the *calyptra* or hood which covers the male organs of the latter claſs of plants, and is now conſidered as the calyx, it had either not engaged the attention of botaniſts in the time of Herman, or, at leaſt, had been conſidered as a part unconnected with the flower. Some modern botaniſts even are ſtill of opinion that the moſſes want both flower-cup and petals.

MUTILUS *Flos*, a mutilated flower; a flower ſo called which is occaſionally deprived of either all its petals, or of the greater part.

Mutilation in flowers is oppoſed to luxuriance, and generally aſcribed to a defect of heat.

In cold climates, the following plants, which are natives, ſome of warm, ſome of temperate countries, are ſubject to loſe their petals, yet bear flowers and ſeeds.

Tuſſilago anandria.
Campanula perfoliata.
Campanula euphraſiæ foliis.
Rubeola patula.
Salvia quæ horminum ſylveſt. lavendulæ flore.

Lamium folio caulem ambiente minus.
Ruellia capſulis teretibus.
Convolvulus pes tigridis.
Lychnis apetala lapponica.
Silene portenſis.
Ciſtus ſalicis folio.
Helianthemum flore maculoſo.

M. Adanſon affirms that the ſame thing happens at Paris to ſea-milk-wort, water-purſlane, and *ammanniæ*.

Some of the campanulas, particularly that with eye-bright leaves, either occaſionally loſe their petals altogether, or produce them ſo ſmall as to be ſcarcely perceptible.

Flowers which always want the petals, and are not, like the mutilated flowers, only occaſionally deprived of them, are diſtinguiſhed by the name of apetalous. *Vide* APETALUS *Flos.*

N.

NECTARIUM, from nectar, the fabled drink of the gods; defined by Linnæus to be a part of the *corolla*, or appendage to the petals, appropriated for containing the honey, a ſpecies of vegetable ſalt under a fluid form, that oozes from the plant, and is the principal food of bees and other inſects.

Notwithſtanding this definition, which ſeems to conſider the nectarium to be as neceſſary a part of the *corolla* as the petals, it is certain that all flowers are not provided with this appendage; neither indeed is it eſſential to fructification.

There is, beſides, a manifeſt impropriety in terming the *nectarium* a part of the *corolla*. Linnæus might, with equal propriety, have termed it a part or appendage of the ſtamina, calyx, or pointal, as the appearance in queſtion is confined to no particular part of the flower, but is as various in point of ſituation, as of form. The truth is, the term *nectarium* is exceedingly vague; and, if any determinate meaning can be affixed to it, is expreſſive of all the ſingularities which are obſerved in the different parts of flowers.

The

The tube or lower part of flowers with one petal, Linnæus conſiders as a true *nectarium*, becauſe it is generally found to contain the ſweet liquor formerly mentioned. This liquor Pontedera compares to that called amnios in pregnant animals, which enters the fertile or impregnated ſeeds: but that this is not at leaſt its ſole uſe, is evident from this circumſtance, that the honey or liquor in queſtion is to be found in flowers where there either are no ſeeds, or thoſe which, from the want of male organs, cannot be impregnated. Thus the male flowers of nettle and willow; the female flowers of ſea-ſide laurel, and black bryony; the male and female flowers of *clutia*, *kiggelaria*, and butcher's broom, all abound with the honey or nectar alluded to.

Dr. Vaillant was of opinion that the *nectarium* was an eſſential part of the *corolla*; for which reaſon he diſtinguiſhed the ſingular appearances in fennel-flower and columbine, by the name of petals: the coloured leaves, which are now termed the petals, he denominates the flower-cup.

That the *nectarium*, however, is frequently diſtinct from the petals, is evident, both from the well-known examples juſt mentioned, as likewiſe from the flowers of monk's-hood, hellebore, *iſopyrum*, fennel-flower of Crete, barrenwort, graſs-of-Parnaſſus, chocolate-nut, *cherleria*, and *ſauvageſia*.

Theſe general obſervations being premiſed, we proceed to take a nearer and more particular view of the principal diverſities, both in form and ſituation, of this ſtriking appendage to the flower.

I. In many flowers, the *nectarium* is ſhaped like a ſpur or horn; and that either in flowers of one petal, as valerian, water-milfoil, (*utricularia*) butter-wort, and calves-ſnout; or in ſuch as have more than one, as lark-ſpur, violet, fumatory, balſam, and orchis.

II. In the following plants, the *nectarium* is properly a part of the *corolla*, as lying within the ſubſtance of the petals: ranunculus, lily, iris, crown-imperial, water-leaf, mouſe-tail, ananas or pine-apple, dog's tooth violet, pipe-ridge buſh, *valliſneria*, *hermannia*, *uvularia*, and *ſwertia*.

III. The *nectarium* is frequently placed in a ſeries or row within

within the petals, though entirely unconnected with their ſubſtance. In this ſituation it often reſembles a cup, as in narciſſus. A *nectarium* of this kind is ſaid by Linnæus to crown the *corolla*. The following are examples: daffodil, ſea-daffodil, campion, viſcous campion, ſwallow-wort, *ſtapelia*, *cynanchum*, *nepenthes*, *cherleria*, balſam-tree, African ſpiræa, witch-hazel, *olax*, and paſſion-flower.

IV. In Indian creſs, buckler muſtard, (*Biſcutella*) Barbadoes cherry, and *monotropa*, the *nectarium* is ſituated upon, or makes part of the calyx.

V. The *nectarium* in baſtard flower-fence, is ſeated upon the *anthers* or tops of the ſtamina; whence the name *adenanthera*, or glandular anthera, which has been given to this genus of plants. In the following liſt it is placed upon the filaments: bean caper, bay, fraxinella, marvel of Peru, bell-flower, lead-wort, *roëlla*, and *commelina*.

VI. In hyacinth, flowering ruſh, ſtock July-flower, and rocket, the *nectarium* is placed upon the ſeed-bud.

VII. In honey-flower, orpine, buck-wheat, *collinſonia*, *lathræa*, navel-wort, mercury, *clutia*, *kiggelaria*, ſea-ſide laurel, and African ſpiræa, it is attached to the common receptacle.

Laſtly, in ginger, nettle, dyer's weed, heart-ſeed, *coſtus*, turmeric, *grewia*, baſtard orpine, vanelloe, ſcrew-tree, and willow, the *nectarium* is of a very ſingular conſtruction, and cannot properly fall under any of the foregoing heads.

A more particular deſcription of the varieties which occur in this ſtriking part of the flower, would be unneceſſary in this place; as both its form and ſituation have been minutely attended to in our analyſis of the ſeveral natural orders or families of plants.

In diſcriminating the genera, the *nectarium* often furniſhes an eſſential character.

Plants which have the *nectarium* diſtinct from the petals, that is, not lodged within their ſubſtance, are affirmed by Linnæus to be generally poiſonous. The following are adduced as examples: monk's-hood, hellebore, columbine, fennel-flower, graſs-of-Parnaſſus, barren-wort, oleander,

marvel of Peru, bean caper, ſucculent ſwallow-wort, fraxinella, and honey-flower.

The term *nectarium*, by which this part of the flower has been diſtinguiſhed, is the invention of Linnæus, who pretends even to have firſt recognized the part in queſtion. It is certain, however, that Tournefort, in 1694, obſerved it in the paſſion-flower, ſwallow-wort, and ſome other plants: and that Vaillant, in 1718, regarded it as a part depending upon the petals, which did not merit any particular appellation.

NOMINA, names.

The diſtinguiſhing of plants and collections of plants by particular names was a neceſſary conſequence of their methodical diſtribution into claſſes, genera, and ſpecies.

The principles laid down on this ſubject by Linnæus, who has new-modelled the names, as well as genera of former botaniſts, fall properly to be conſidered in this place. And, firſt, of the

Names of Claſſes and Orders.

1. The ancient botaniſts diſtinguiſhed many of their claſſes by primitive names; that is, names not expreſſive of any particular character in the plants which compoſe them. Hence the graſſes of Tragus; the ferns, moſſes, muſhrooms, and thiſtles of Dodonæus; the palms and orchides of Lobelius; the lettuces, mallows, and cucumbers of Zaluzianſki; the night-ſhades, poppies, and Bryonies of Caſpar Bauhin; the campanulas and borages of John Bauhin.

Mr. Adrien Royen is the firſt, and perhaps the only one of the moderns, who has eſtabliſhed for a principle, that the name of every claſs ought to be derived from the name of ſome well-known or remarkable genus in it.

Modern ſyſtematic writers, ſtudious to abridge the ſcience of botany, by ſuppreſſing all ſuperfluous characters, and keeping the moſt eſſential only in view, have eſtabliſhed, that the name of the claſs ſhould not be ſimple or primitive, but expreſſive of a certain character or characters found in all the plants which compoſe it. Hence the leguminous, ſiliquoſe,

quoſe, berry-bearing, umbelliferous, and lacteſcent plants of Moriſon; the croſs-ſhaped, and butterfly ſhaped flowers of Tournefort; the rough-leaved plants, thoſe which flower at the joints and form a head, of Ray; the *enſatæ*, *campanaceæ*, and other orders in Linnæus's Fragments of a Natural Method; and all the claſſes of the Sexual Syſtem.

The inconveniences ariſing from a ſtrict compliance with this rule, are two: firſt, that it is difficult to find a name which ſhall be expreſſive of ſome circumſtance that is common to all the genera of any particular claſs. Thus, many genera of the firſt claſs in the Sexual Method, *monandria*, might, with equal propriety, be referred to the ſecond and third claſſes, *diandria* and *triandria*, the number of *ſtamina* being either one, two or three. In like manner, the claſs *icoſandria* contains plants which have not the circumſtance expreſſed in the title; the number of ſtamina being generally more, ſometimes leſs than twenty: beſides, the eſſential character of this claſs, which is the inſertion of the ſtamina and petals into the inner part of the calyx, is not even alluded to in the title. In the ſame manner, the genus *cleome* does not poſſeſs the character expreſſed in the title *tetradynamia*, to which claſs it belongs. Examples of the like impropriety might be adduced from the claſſes *monœcia*, *diœcia*, and *polygamia* of the Sexual Method, and from the names of claſſes in other ſyſtems.

The other inconvenience juſt mentioned ariſes from employing names expreſſive of ſeveral characteriſtic marks; as theſe, in ſuch caſes, being too long and complex, aſſume a barbarous appearance, and become unintelligible. Wachendorffius's claſſes are particularly faulty in this reſpect. His *pollaploſtemonopetalæ*, *eleutheromacroſtemones*, and *diſtemonopleantheræ*, furniſh ſtriking examples.

II. The names of claſſes and orders ſhould conſiſt of a ſingle word. All Linnæus's claſſical names are of this ſort.

Cæſalpinus has employed definitions inſtead of names in his arrangement. Tournefort and Rivinus have frequently made unneceſſary repetitions at the head of each claſs, oc-

caſioned generally from the circumſtance of affixing part of the ſame name to two different claſſes. Thus the firſt claſs in Rivinus's Method conſiſts of perfect, ſimple, *regular* flowers with one petal; the eleventh claſs of the ſame method is defined to conſiſt of flowers with one petal that are perfect, ſimple, and *irregular*. In like manner, the definition of Tournefort's firſt claſs is expreſſive of the ſimplicity and *regularity* of the flowers contained in it, which conſiſt of a ſingle petal, that is bell-ſhaped; the fourth, of the ſimplicity and *irregularity* of the flowers contained in it, which conſiſt of a ſingle petal, that is lip-ſhaped.

III. Names of claſſes and orders, taken from the name of any plant or genus of plants, are only to be uſed, according to Linnæus, in natural methods. Of this kind are the palms, ferns, moſſes, ſea-weed, muſhrooms, graſſes, *orchideæ*, *corydales*, *cucurbitaceæ*, *calamariæ*, *rhœades*, *caryophyllæi*, and *piperitæ* of Linnæus's Fragments; the *palmæ*, *lilia*, *gramina*, of Royen's Natural Method. Such names are certainly convenient, as they ſerve to recall the idea of the general relations of each family or order; relations, which are, in a manner, collected in the plant from which the claſſical name is derived. The claſſic and generic name, however, is at no time to be preciſely the ſame; as, beſides the manifeſt impropriety of arranging a thing under itſelf, the greateſt confuſion would enſue from ſuch arrangement. For this reaſon, Linnæus, when he uſes claſſical names of this kind, generally changes the name of the genus which ſuggeſted the claſſical name in queſtion. Thus in the natural order *palmæ*, no genus of that name is to be found. In like manner, the genus *filix*, one of the ferns, is changed for *pteris*, becauſe he has diſtinguiſhed that order of plants by the general or claſſical name of *filices*. It is upon the ſame principle that the ingenious Royen has ſubſtituted the Greek name *lirium*, inſtead of *lilium*, the more common name of that genus, becauſe *lilia* is the name by which he has diſtinguiſhed the claſs.

IV. Names of claſſes and orders are not to be derived from the habit, virtues, and ſenſible qualities of plants, nor from

from the form, ſituation, and other circumſtances of the roots and leaves; as ſuch appellations are not in the ſpirit of ſyſtematic arrangement. To this cenſure is ſubjected the *cordiales*, *dorſiferæ*, and *ſurculentæ* of ſome botaniſts; the *capillares* of Moriſon and Ray; the *bulboſæ* of Cæſalpinus; the *aſperifoliæ* of Ray; the *verticillatæ* and *ſtellatæ* of the ſame author.

Names of the Genera.

I. A genus of plants being a collection of ſpecies which agree in the parts of fructification, it is evident that all the ſpecies of the ſame genus muſt be marked or diſtinguiſhed by the ſame generical name. Thus the orange, lemon, and citron, being conſidered by Linnæus as forming one genus, are diſtinguiſhed by the generical name *citrus*, in this manner, *citrus aurantium*, the orange, *citrus medica*, the citron-tree, *citrus medica* limon, the lemon; this laſt being eſteemed a variety of the citron, in like manner as the ſhaddock, termed *citrus aurantium* decumana, is of the orange. Theſe fruits were reckoned three diſtinct genera by Tournefort.

II. The generical name is not only to be the ſame, but ſingle in all the plants of the ſame genus. Hence there is an impropriety in diſtinguiſhing blue monk's-hood or aconite, as did Bauhin, by the additional name of *napellus*; and the wholeſome ſpecies of the ſame genus, by that of *anthora*.

III. The ſame generic name is not to be applied to two different genera. Hence the *aconitum* of Ray is changed for *helleborus*; the *caltha* of Tournefort into *calendula*; the *cameraria* of Dillenius into *montia*; the *ſherardia* of Vaillant into *verbena*: the names ſo changed having been uſed to denominate other genera, with which thoſe in queſtion have no connection.

IV. Whoever conſtitutes a new genus, ſays Linnæus, is bound likewiſe to give it a name.

V. The generic name of a plant is to be fixed, before any attention be given to its name as a ſpecies.

VI. Generic names conſiſting of two entire diſtinct words, Linnæus is of opinion ſhould be totally explode'. For this reaſon he has changed the *bella donna*, *centaurium majus*,

corona ſolis, *dens leonis*, and *vitis idæa* of Tournefort, for *atropa*, *centaurea*, *helianthus*, *leontodon*, and *vaccinium*; the *criſta galli* of Dillenius, for *rhinanthus*.

VII. Generic names compounded of two entire Latin words joined together, are deemed rather inelegant, and may be properly enough changed for a Greek compound of the ſame kind. Thus the com*aurea* of former botaniſts, is changed by Linnæus for *chryſocoma*, the etymology of which is the ſame.—The names of the following genera, although of Latin compoſition, are retained by Linnæus; roſ*marinus*, cornu*copiæ*, ſemper*vivum*, and ſangui*ſorba*.

VIII. Generic names compounded of two words of different languages, are highly improper. Of this kind are the tamar*indus* and cardam*indum* of Tournefort; the mor*inda*, chryſanthem*indum*, and ſap*indus* of Vaillant.

IX. The termination *oides*, very common with former botanical writers, has been juſtly exploded by Linnæus as inelegant and ſuperfluous. Thus the *agrimonoides* of Tournefort, is changed for *agrimonia*; *alyſſoides* for *alyſſum*; *aſteroides* for *buphthalmum*; *cyperoides* for *carex*; *nymphoides* for *menyanthes*; *pentaphylloides* for *potentilla*; *rhamnoides* for *hippophäe*; *ricinoides* for *croton*; *telephioides* for *andrachne*; *tribuloides* for *trapa*; *chryſanthemoides* for *oſteoſpermum*; *cuminoides* for *lagœcia*; *aſtragaloides* for *phaca*; the *capnoides* of Ray, for *fumaria*; the *valerianelloides* of Bauhin, for *valeriana*. The *alſinaſtroides* and *jonthlaſpioides* of Kramer, furniſh likewiſe ſtriking examples of the impropriety in queſtion.

X. Names of genera compounded of two generic words, one of which is entire, are not to be imitated. For this reaſon Linnæus has changed the *canna*corus of Tournefort, for *canna*; *lilio*narciſſus for *ſcilla*; *lina*groſtis for *eriophorum*; *lauro*ceraſus for *padus*; the *capn*orchis of Bauhin, for *fumaria*. Greek compounds of this kind may be ſafely admitted; *elæ*agnus, *quaſi oleæ agnus caſtus*, and *ciſ*ſampelos, *quaſi hederæ vitis*, furniſh examples.

XI. Diminutives from other genera, or generic names formed from others with the addition of one or two ſyllables at the end, are improper, as ſeeming to indicate a connection, which,

which, perhaps, does not exiſt. For this reaſon Linnæus has changed the

Old Genera.		Linnæan Genera.
Acetoſella — —	of Ray, for	Rumex.
Napellus — —		Aconitum.
Myrtillus — —		Vaccinium.
Lappula — —		Myoſotis.
Fabbaria — —		Sedum.
Roſea — —		Rhodiola.
Alſinanthemos —		Trientalis.
Morocarpus —		Blitum.
Lupinaſter — —	of Bauhin, for	Trifolium.
Saliunca — —		Valeriana.
Alſinaſtrum — —	of Tournefort, for	Elatine.
Rapiſtrum — —		Myagrum.
Limonium — —		Statice.
Lapathum — —		Rumex.
Erucago — —		Bunias.
Corallodendron —		Erythrina.
Fagopyrum — —		Helxine.
Adonia — —	of Plumier, for	Myoſurus.
Sediformis — —		Stratiotes.
Linophyllum — —		Theſium.
Alſinaſtriformis —		Montia.
Fungoidaſter —	of Micheli, for	Elvela.
Lenticularia — —		Lemna.

Balſamita — — of Vaillant, for *Tanacetum.*

XII. Generic names of plants borrowed from the animal and mineral kingdoms, the heavenly bodies, and moral qualities, are condemned by Linnæus, as introducing confu-

ſion and obſcurity into the nomenclature of the ſcience. On account of this impropriety, he has changed the

Old Genera.		Linnæan Genera.
Elephas — — —	of Tournefort, for	Rhinanthus.
Onagra — — —		Oenothera.
Bugloſſum — —		Anchuſa.
Ephemerum — —		Tradeſcantia.
Stœchas — — —		Lavandula.
Scolopendrum — —		Aſplenium.
Sphondylium — —		Heracleum.

Erinaceus — — of Dillenius, for Hydnum.

Locuſta — — —	of Ray, for	Valeriana.
Sol — — —		Helianthus.
Staphylinus — —		Daucus.

Ampelis — — —	of other Botaniſts, for	Vitis.
Lagopus — — —		Trifolium.
Meleagris — —		Fritillaria.
Natrix — — —		Ononis.
Hippogloſſum — —		Ruſcus.
Phalangium — —		Anthericum.
Granatum — —		Punica.
Molybdæna — —		Plumbago.
Balanus — — —		Nepenthes.
Patientia — —		Rumex.
Concordia — —		Agrimonia.

XIII. For the ſame reaſon, the nomenclature of botany ſhould not be confounded with that of anatomy, pathology, the materia medica, and the arts. Hence Linnæus has changed the

Old Genera.		Linnæan Genera.
Ptarmica — —	of Tournefort, for	Achillea.
Cardiaca — —		Leonurus.
Veſicaria — —		Alyſſum.
Vulneraria — —		Anthyllis.

Old Genera.		*Linnæan Genera.*
Auricula — —	of other Botaniſts, for	Primula.
Epiglottis — —		Aſtragalus.
Priapus — — —		Nepenthes.
Umbilicus — —		Cotyledon.
Paralyſis — —		Primula.
Soda — — —		Salſola.
Sphacelus — —		Salvia.
Verruca — — —		Lapſana.
Candela — — —		Rhizophora.
Sagitta — — —		Sagittaria.
Serra — — —		Biſſerrula.
Clitoris — — —		Clitoria.
Muſcipula — —		Silene.
Corona — — —		Helianthus.
Burſa — — —		Thlaſpi.
Solea equina — —		Hippocrepis.

XIV. Names pertaining to claſſes and natural orders, are by no means to be applied to any particular genus. Hence *Fungus*, *Alga*, *Muſcus*, *Filix*, *Palma*, are very improper generic names: as are *Planta*, *Arbor*, *Frutex*, *Suffrutex*, *Herba*, and ſuch like terms, from their very general nature and ſignification.

XV. Latin diminutives, and other names of like origin expreſſive of ſome property in the parts of the plants ſo characterized, furniſh proper, though not elegant, generic names. Of this kind are,

Potentilla, Lin. (*potentia*, power) from its powerful virtues.
Pulſatilla, Tourn. (*pulſare*, to beat often) from its flowers being toſſed and ſhaken by the wind.
Limoſella, Lin. (*limus*, ſlime) from its native ſoil.
Nigella, Tourn. (*niger*, black) from the blackneſs of its ſeeds.

Clypeola,

Clypeola, Lin. (*clypeus*, a ſhield) from its ſeed-veſſel reſembling a ſhield.

Mitreola, Lin. (*mitra*, a mitre) from its mitre-ſhaped fruit.

Gladiolus, Tourn. (*gladius*, a ſword) from its ſword-ſhaped leaves.

Samolus, Tourn. (Samos, an iſland) from its place of growth.

Calendula, Ruppius, (*calendæ*, the firſt of every month) from its flowering at all ſeaſons, and during every month in the year.

Campanula, Tourn. (*campana*, a bell) from its bell-ſhaped flower.

Craſſula, Dillen. (*craſſus*, thick) from the thickneſs of its leaves.

Primula, Lin. (*primus*, firſt) from its early flowering.

Pinguicula, Tourn. (*pinguis*, fat) from the fatneſs of its leaves.

Hirtella, Lin. (*hirtus*, hairy) from the hairineſs of its branches.

Crucianella, Lin. (*crux*, a croſs) from its leaves being placed croſs-wiſe.

Sanicula, Tourn. (*ſano*, to cure) from its vulnerary quality.

Serratula, Dillen. (*ſerra*, a ſaw) from its ſawed leaves.

Spergula, Dillen. (*ſpargo*, to ſcatter) from the diſperſing or ſcattering of its ſeeds.

Convolvulus, Tourn. (*convolvo*, to twiſt together) from the convolutions or twiſtings of its ſtalks.

Aſperugo, Tourn. } (*aſper*, rough) from the roughneſs of
Aſperula, Lin. } the plants which compoſe the genus.

Mollugo, Lin. (*mollis*, ſoft) from its ſoftneſs.

Plumbago, Tourn. (*plumbum*, lead) from its lead-colour.

Solidago, Vaill. (*ſolidus*, ſolid) from its conſolidating quality.

Urtica, Tourn. (*uro*, to burn) from its ſtinging or burning upon being touched.

Lactuca, Tourn. and Vaill. (*lac*, milk) from its leaves, ſtalks, and flowers abounding in a white milky juice.

Tuſſilago,

Tuſſilago, Tourn. and Vaill. (*tuſſis*, the cough) from its great efficacy in coughs and catarrhs.

Spinacia, Tourn. (*ſpina*, a thorn) from its prickly fruit.

Salſola, Plum. (*ſal*, ſalt) from the brackiſh taſte of the plant.

Sedum, Tourn. (*ſedeo*, to ſit) from its ſtation on walls and rocks.

Cornus, Tourn. (*cornu*, a horn) from the ſhell of the fruit, which is as hard as a piece of horn.

Juglans, Lin. (*quaſi* Jovis glans) from its being conſecrated to Jupiter.

Ranunculus, Tourn. (*rana*, a frog) from its growing in moiſt places, which are frequented by frogs.

Lavandula, Tourn. (*lavo*, to waſh) from its being uſed in baths and waſhes, on account of the fragrancy of its ſmell.

Juncus, Tourn. (*jungo*, to join) from the ſtalks being joined together, and wrought into baſkets and other uſeful utenſils, when dried.

Ledum, Rupp. (*lædo*, to hurt) from its offenſive ſmell.

Salix, Tourn. (*ſalio*, to leap) from its quick growth.

Reſeda, Tourn. (*reſedare*, to appeaſe) from its allaying pain.

Borago, Tourn. (*quaſi cor ago*, to take heart) from its exhilarating quality.

Ferula, Tourn. (*ferio*, to ſtrike) from rods being formerly made of its ſtalks, with which ſchool-maſters corrected their ſcholars.

Biſerrula, Lin. (*bis*, twice, and *ſerra*, a ſaw) from its pods being ſawed or indented on both edges.

Biſcutella, Lin. (*bis*, twice, and *ſcutum*) from the fruit reſembling a double buckler.

Tropæolum, Lin. (*tropæum*, a trophy) from its fancied reſemblance to the inſignia of a trophy.

Phaſeolus, Tourn. (*phaſelus*, an oblong ſwift ſhip) from the huſk or covering of the ſeeds reſembling the hulk of a galley.

Pyrola, Tourn. (*pyrus*, a pear) from its pear-ſhaped leaves.

Proſerpinaca,

Proſerpinaca, Lin. (*ſerpo*, to creep) from its ſtalks creeping on the ground.

Medicago, Tourn. (*Media*, the name of a country) from its having been brought into Greece, from Media, by Darius Hyſtaſpes, as Pliny relates.

Coronilla, Tourn, (*corona*, a crown) from its flowers being collected in bunches at the termination of the ſtalks.

Arenaria, Lin. (*arena*, ſand) from its native ſoil.

Convallaria, Lin. (*convallis*, a valley) from its common place of growth.

Clavaria, Vaill. (*clavus*, a club) from its habit and appearance.

Capraria, Lin. (*capra*, a ſhe-goat) from its being browzed on by goats.

Cochlearia, Tourn. (*cochleare*, a ſpoon) from its leaves being hollowed like a ſpoon.

Coriaria, Niſſol. (*corium*, leather) from its uſe in tanning.

Cymbaria, Ammannus, (*cymba*, a boat or ſkiff) from the figure of its fruit.

Dentaria, Tourn. (*dens*, a tooth) from its roots being compoſed of a great number of ſcales reſembling teeth.

Fragaria, Tourn. (*fragrans*, fragrant) from its fragrant aromatic ſmell.

Globularia, Tourn. (*globus*, a globe or ſphere) from the figure of the flower.

Herniaria, Tourn. (*hernia*, a rupture) from its efficacy in ruptures.

Lunaria, Tourn. (*luna*, the moon) from the figure of its fruit or ſeed-veſſels.

Matricaria, Tourn. and Vaillant, (*matrix*, the womb) from its efficacy in diſeaſes of the uterus.

Pulmonaria, Tourn. (*Pulmones*, the lungs) from its efficacy in diſorders of the breaſt and lungs.

Parietaria, Tourn. (*paries*, a wall) from its growing on old walls.

Mirabilis, Ray, (*Lat.* admirable) from the beautiful diverſity of colours in its flowers.

Sempervivum, Rupp. (*ſemper*, always, and *vivo*, to live) from its continual verdure.

Perſicaria,

Perſicaria, Tourn. (*perſica*, a peach-tree) from the reſemblance of its leaves to thoſe of the peach-tree.

Sagittaria, Lin. (*ſagitta*, an arrow) from its arrow-ſhaped leaves.

Sanguinaria, Dillenius, (*ſanguis*, blood) from its juice, which is of a yellow colour, inclining to red.

Saponaria, Lin. (*ſapo*, ſoap) from the deterſive quality of the leaves.

Scoparia, Lin. (*ſcopæ*, a beſom) from the uſe to which the plant is generally applied.

Momordica, Tourn. (*mordeo*, to bite) from the appearance of the ſeeds, which are flat and compreſſed, as if they had been grinded or chewed.

Scrophularia, Tourn. (*ſcrophula*, king's evil) from its ſuppoſed efficacy in ſcrophulous complaints.

Trifolium, Tourn. (*tres*, three; and *folium*, a leaf) from its bearing finger-ſhaped leaves, each leaf conſiſting of three ſmaller leaves furniſhed with ſhort partial foot-ſtalks.

Paſſiflora, Lin. (*patior*, to ſuffer, and *flos*, a flower) from the fancied reſemblance of the organs of generation to a hammer and nails, the inſtruments of ſuffering.

Stellaria, Lin. (*ſtella*, a ſtar) from the figure of its flower.

Subularia, Ray, (*ſubula*, an awl) from its awl-ſhaped leaves.

Utricularia, Lin. (*utriculus*, a little bladder) from the round two-horned veſſels diſtended with air, which it bears on its roots.

Glorioſa, Lin. (*gloria*, glory, excellence) from the beautiful and ſuperb appearance of its flowers.

Angelica, Lin. (*lat.* angelic) from the approved virtues of its root and ſeeds.

Fontinalis, Dillen. (*fons*, a fountain) from its place of growth.

Sanguiſorba, Ray, (*ſanguis*, blood, and *ſorbeo*, to drink up) from its great efficacy againſt ſpitting of blood.

Turritis, Tourn. (*turris*, a tower) from its height.

Impatiens, Ray (in, not, and *patior*, to ſuffer) from the elaſticity of its fruit, which may therefore be ſaid not to bear the touch.

Imperatoria, Tourn. (*imperator*, a commander) from the great efficacy of its root in medicine.

Hepatica, Rupp. and Dillen. (*hepar*, the liver) from the figure of its leaves.

Pedicularis, Tourn. (*pediculus*, a louſe) from its ſuppoſed efficacy in deſtroying lice.

Saxifraga, Tourn. (*ſaxum*, a rock, and *frango*, to break) from its growing on the clefts of rocks.

Parnaſſia, Tourn. (*Parnaſſus*, a mountain in Phocis) from its place of growth.

Iberis, Rupp. and Dillen. from the kingdom of Iberia or Spain.

Smyrnium, Tourn. from the city of Smyrna.

Nepeta, Lin. from a town in Italy of that name.

Arabis, Lin. from the kingdom of Arabia.

Moluccella, Lin. from the Molucca iſlands.

Arethuſa, Gronovius, from the celebrated fountain of that name, near Syracuſe in Sicily.

Punica, Tourn. (*Poeni*, the Carthaginians) from the city Carthage.

Thapſia, Tourn. from *Thapſus*, a town of *Africa propria*, near which Scipio and Juba were defeated by Cæſar.

Colchicum, Tourn. from Colchis, a country of antient Aſia, to the Eaſt of the Euxine Sea, celebrated for the expedition of Jaſon and the Argonauts.

Patagonula, Lin. from Patagonia, a country in South America.

Carica, Lin. from Caria, a country in leſſer Aſia.

Liguſticum, Tourn. from Liguria, a province of Italy.

Marrubium, Tourn. from a town in Italy, now San Benedetto.

Toluifera, Lin. from its producing the ſubſtance known by the name of Balſam of Tolu.

Indigofera, Lin. from its producing the colour known by the name of Indigo.

Digitalis, Tourn. (*digitus*, a finger) from its flower, reſembling the finger of a glove.

Scabioſa,

Scabioſa, Tourn. (*ſcabies*, ſcab, itch) from its efficacy in diſorders of the ſkin.

Amthyſtea, Lin. from its flowers reſembling an amethyſt in colour.

Gratiola, Lin. (*gratia*, favour, efficacy) from its uſe in medicine.

Ziziphora, Lin. from the Indian name Zizi.

Jambolifera, Lin. from the Indian name Jambolo.

Uvaria, Lin. (*Uva*, a grape) from the figure of its fruit.

Uvularia, Lin. from the fancied reſemblance of its fruit to the uvula of the throat.

Craniolaria, Lin. (*cranium*, the ſcull) from the nut which, in figure, reſembles the ſcull of ſome wild beaſts.

Piſcidia, Lin. (*piſcis*, a fiſh) from the rare quality poſſeſſed by its bark, of intoxicating fiſh. See *Papilionaceæ*.

XVI. Names borrowed from the fables of the poets, or intended to perpetuate the memory of ſome celebrated men, and particularly of the patrons of botanical knowledge, are admitted into the modern nomenclature, which, however, excludes the numerous liſt of generical names in commemoration of ſaints and illuſtrious men in other ſciences.

The poetical names of genera are as follows; *Ambroſia*, *Nepenthes*, *Cornucopiæ*, *Crocus*, *Protea*, *Centaurea*; *Actæa*, *Chironia*, *Achillea*, *Narciſſus*, *Hyacinthus*, *Amaryllis*, *Phyllis*, *Pæonia*, *Cerbera*, *Adonis*, *Circæa*, *Medeola*, *Andromeda*, *Daphne*, *Syringa*, *Canna*, *Myrſine*, *Mentha*, *Smilax*. A very ſlight acquaintance with the poets, particularly with Ovid's Metamorphoſes, will render any comment upon theſe names altogether unneceſſary.

The following genera are denominated from gods, kings, and patrons of the ſcience.

Aſclepias, Tourn. from Æſculapius, the god of phyſic.

Mercurialis, Tourn. from Mercury, the interpreter and meſſenger of the gods.

Hymenæa, Lin. from Hymen, the god of marriage.

Serapias, Lin. from Serapis, the idol worſhipped by the Egyptians; or, perhaps, from Serapion, the celebrated Arabian phyſician.

Satyrium, } Lin. } from the Satyrs, a ſort of wood-land
Satureia, } Tour. } deities, ſuppoſed to preſide over the libidinous actions of men; the name is very properly applied to the firſt genus, on account of its ſuppoſed aphrodiſiac or ſtimulating quality.

Ixora, Lin. the idol worſhipped by the natives of Malabar.

Tagetes, Tourn. and Vaill. from Tages, a grandſon of Jupiter, and inſtructor of the ancient Tuſcans in augury and the occult ſciences.

Nymphæa, Tourn. from the nymphs in general, but particularly thoſe who preſided over waters.

Naias, Lin. from the naiads, a claſs of nymphs who preſided over rivers and fountains.

Dryas, Lin. from the dryads, another claſs of nymphs, who preſided over woods and trees, particularly the oak, (δρυς, *quercus*).

Artemiſia, Tourn. and Vaill. the celebrated wife of Mauſolus, king of Caria.

Helenia, Lin. from Helen, the wife of Menelaus.

Atropa, Lin. from Atropos, one of the PARCÆ, or fatal ſiſters, to whom was committed the charge of cutting the thread of life.

Lyſimachia, Tourn. from Lyſimachus, a king of Sicily.

Philadelphus, Lin. from Ptolemy Philadelphus, a king of Egypt.

Teucrium, Tourn. from Teucer, founder of the kingdom afterwards called Troy.

Valeriana, Tourn. from the celebrated Valerian family at Rome.

Gentiana, Tourn. from Gentius, a king of Illyria.

Pharnaceum, Lin. from Pharnaces, a king of Pontus.

Telephium, Tourn. from Telephus, a king of Myſia.

Borbonia, Lin. from the celebrated houſe or family of Bourbon.

Eugenia, Michel. from the illuſtrious Prince Eugene of Savoy.

Piercea, Miller, from his grace Hugh Percy, firſt duke of Northumberland.

Petrea, Houſton, from Lord Petre.

Cliffortia,

Cliffortia, Lin. from George Clifford, J. U. D. of Amſterdam, a great improver and patron of botany.

Stewartia, Lin. from the late excellent naturaliſt, and moſt munificent patron of learning, John Stuart, firſt earl of Bute.

Boſea, Lin. from a ſenator of Leipſick of that name.

Nicotiana, Tourn. from James Nicot, a Frenchman, who firſt imported the ſeeds of tobacco (the genus in queſtion) into France.

XVII. Generic names in honour of celebrated botaniſts form a very conſiderable part of the modern nomenclature. The following liſt is entirely of this kind.

Theophraſta, Lin. from Theophraſtus, the father of botany.

Crateva, Lin. from Cratevas, an ancient botaniſt, mentioned by Pliny in his Natural Hiſtory.

Hippocratea, Lin. and Jacquin, from Hippocrates, the father of phyſic.

Muſa, Plumier, from Antonius Muſa, phyſician to Auguſtus Cæſar, and ſuppoſed to be commemorated by Virgil under the name of *Japis*, in the 12th book of the Æneid.

Dioſcorea, Plumier, from Dioſcorides, the celebrated Greek botaniſt.

Plinia, Plumier, from Pliny the elder, the celebrated naturaliſt.

Brunfelſia, Plumier, from Tho. Brunfels, Brunfelſius, a German divine, phyſician and botaniſt, who flouriſhed in the ſixteenth century.

Ruellia, Plumier, from Johannes Ruellius, a French-man, likewiſe of the 16th century, author of a Commentary on Dioſcorides, and of a work in three books, on the Nature and Hiſtory of Plants.

Creſcentia, Lin. from Petrus de Creſcentia, a ſenator of Bologna, who lived in the 13th century, and is author of a book entitled *Opus Ruralium Commodorum*.

Dorſtenia, Plum. and Houſt. from Theodoric Dorſten, a German botaniſt, author of a book entitled *Botanicon*, publiſhed at Francfort in 1540.

Geſneria, Plum. from the celebrated Conrad Geſner, author of ſeveral botanical works.

Fuchſia, Plumier, from Leonard Fuchs, a German of the 16th century, author of a Hiſtory of Plants.

Matthiola, Plum. from P. A. Matthiolus, an Italian botaniſt, whoſe principal work is an excellent edition of Dioſcorides, with ample illuſtrations.

Lonicera, Ray, from Adam Lonicer of Francfort, author of a Hiſtory of Plants publiſhed in 1551.

Turnera, Plum. from Dr. William Turner, of Morpeth, author of an Engliſh Herbal, printed at London, in 1551.

Tragia, Plum. from Hieronymus Bock, commonly called Tragus, a phyſician and divine of Deux Ponts, author of a Hiſtory of Plants firſt publiſhed at Straſburgh in 1539.

Dodonæa, Lin. from Dodoens, or Dodonæus, a German, author of a botanical work, publiſhed at Antwerp, in 1552.

Bellonia, Plumier, from Peter Belon, a French-man of the 16th century, author of a Voyage to the Levant, and of a Treatiſe on Cone-bearing trees.

Guilandina, Lin. from Melchior Guilandin, or Wieland, a Pruſſian, author of a treatiſe on the *Synonyma* of plants, and of a Diſſertation on the plant from which the ancients made paper, firſt publiſhed in 1572.

Cordia, Plum. from Valerius Cordus, a German, author of a Hiſtory of Plants.

Monarda, Lin. from Nicolas Monardes, a Spaniſh phyſician, and author of a Hiſtory of ſuch of the Weſt India plants as are uſed in medicine, as likewiſe of a Treatiſe on Roſes and Citrons, Oranges, &c.

Lobelia, Plumier, from M. de L'Obel, author of a Hiſtory of Plants, in 1576.

Penæa, Plum. from Peter Pena of Narbonne, contemporary with L'Obel and L'Ecluſe, in conjunction with the former of whom he publiſhed *Nova Stirpium Adverſaria*, at Antwerp in 1576.

Cluſia, Plumier, from L'Ecluſe, a Frenchman, author of a Hiſtory of Rare and Exotic Plants.

Clutia, Boerhaave, from Augerius Cloot, an ingenious botaniſt of the 17th century, who, to enrich the botanical garden at Montpelier with the plants of Africa, then little known, attempted a ſcientific excurſion through the Barbary States, but was unfortunately ſtripped both of his new acquiſitions and of his liberty.

Rauwolffia, Plumier, from Leonard Rauwolf, a German, author of an Itinerary, or Travels to the Holy Land, and other parts of the Eaſt, for the promotion of natural knowledge.

Cæſalpinia, Plum. from Cæſalpinus, an Italian, father of ſyſtematic botany.

Duranta, Plum. from Caſtor Durante, an Italian, author of a Herbal in the ſixteenth century.

Cameraria, Plum. from Joachim Camerarius, junior, a German phyſician and botaniſt, author of *Hortus Medicus et Philoſophicus*, and ſome other works.

Dalechampia, Plum. from Dalechamp, a phyſician of Lyons, in the ſixteenth century, author of a General Hiſtory of Plants.

Tabernæmontana, Plum. from one Theodore, a German, generally known by the name of Tabernæmontanus, from the village where he was born.—He lived in the ſixteenth century, and publiſhed a Hiſtory of Plants, in folio, at Francfort.

Thalia, Plumier, from Johannes Thalius, a German botaniſt, author of a Flora, entitled *Sylva Hercynia*.

Alpinia, Plum. from Proſper Alpinus, an Italian, author of ſeveral botanical works, particularly a Deſcription of the Plants of Egypt.

Columnier, Plum. from Fabius Colonna, a noble Italian, who publiſhed ſome curious works in botany.

Bauhinia, Plumier, from the two illuſtrious brothers, Caſpar or Gaſpard, and John Bauhin, natives of Switzerland, and authors of ſome well-known botanical works.

Gerardia, Plum. from John Gerard, an Engliſh apothecary, of Nantwich, in Cheſhire, who lived in the ſix-

teenth century, and publiſhed the Herbal, or General Hiſtory of Plants, which is well known.

Robinia, Lin. from Robin, a Frenchman, who firſt introduced the plant (Falſe Acacia) into France from Canada.

Renealmia, Plum. from Paul Reneaume, a Frenchman, author of a Specimen of a Hiſtory of Plants.

Swertia, Lin. from Emmanuel Sweert, a Dutchman, who lived in the beginning of the ſeventeenth century, and publiſhed a botanical work, entitled *Florilegium*.

Beſleria, Plum. from Baſilius Beſler, a German apothecary, author of two large botanical works.

Marcgravia, } Plum. { from two ingenious botaniſts, Marc-
Piſonia, } { grave and Piſon, the firſt a German, the other a Dutchman, authors of a Natural Hiſtory of Braſil.

Hernandia, Plum. from Francis Hernandez, a Spaniſh botaniſt, of the ſeventeenth century, author of a Natural Hiſtory of Mexico.

Broſſæa, Plumier, from Guy de la Broſſe, a Frenchman, author of a book on the nature of plants.

Parkinſonia, Plum. from Mr. John Parkinſon, author of a Hiſtory of Plants, under the title of *Paradiſus Terreſtris*, and of a Treatiſe entitled *Theatrum Botanicum*.

Ambroſinia, Baſſius, from Bartholomew Ambroſini, an Italian botaniſt of the 17th century, author of a Hiſtory of Capſicums.

Cornutia, Plum. from Cornutus, a Frenchman, author of a treatiſe, entitled *Enchiridion Botanicum Pariſienſe*, and of a Hiſtory of Canada plants.

Paullinia, Lin. from Pauli, a Daniſh botaniſt, author of two treatiſes, entitled *Quadripartitum Botanicum*, and *Viridaria varia*.

Stapelia, Lin. from Stapel, a Dutchman, author of ſome botanical works, particularly a Deſcription of Theophraſtus's plants.

Læſelia, Lin. from Læſel, a Pruſſian, author of a Flora, or Enumeration of the Plants that are natives of Pruſſia.

Zanonia,

Zanonia, Lin. from Zanoni, an Italian, author of a Treatiſe on the Alpine Plants.

Moriſona, Plum. from Dr. Robert Moriſon, author of an Univerſal Hiſtory of Plants, and ſeveral other curious botanical works.

Bontia, Plum. from Bontius, an ingenious Dutch botaniſt, author of a Natural Hiſtory of the Eaſt Indies.

Aldrovanda, Monti, from the celebrated Italian naturaliſt Ulyſſes Aldrovandus.

Bocconia, Plum. from Paul Boccone, a native of Sicily, author of a Treatiſe on the rare and curious Plants of that iſland, and of ſome other botanical works.

Muntingia, Plum. from Abraham Munting, a Dutch naturaliſt of the 17th century, author of ſome ingenious botanical works, particularly *Phytographia curioſa*, *Aloedarium*, and *de Britannica Herba*.

Tillandſia, Lin. from Tillands, a Swediſh botaniſt, author of a Catalogue or Enumeration of the Plants that are Natives of Abo.

Breynia, Plum. from John Breyn, or Breynius, a native of Poland, author of a Diſſertation on Ginſeng.

Petiveria, Plum. from Mr. James Petiver, an apothecary of London, author of a Britiſh Herbal, and many other curious botanical works.

Dodartia, Tourn. from M. Dodart, a Frenchman, author of Memoirs towards a Hiſtory of Plants. His plates, forty-five in number, are reckoned excellent.

Commelina, Plum. from John Commelyn, a Dutchman, who, beſides the ſhare which he took in the publication of that ſplendid work, the *Hortus Malabaricus*, is likewiſe author of *Heſperides Belgiæ*, and *Hortus Amſtelodamenſis*.

Rheedea, Plum. from Henricus van Rheede van Drakenſtein, a Dutchman, governor of Malabar, who publiſhed, at his ſole expence, in 1676, the celebrated *Hortus Malabaricus*, in 12 vols. folio.

Mentzelia, Plum. from Chriſtian Mentzel, or Mentzelius, a Pruſſian, author of an Index of rare and curious Plants.

Sibbaldia, Lin. from Robert Sibbald, a Scotchman, who lived in the 17th century, and publiſhed a Natural Hiſtory of Scotland under the title of *Scotia illuſtrata*.

Triumfetta, Plum. from John Baptiſt Triumfetti, an Italian, author of a Treatiſe on Vegetation, and other botanical works.

Magnolia, Plum. from Peter Magnol, profeſſor of botany at Montpelier.

Rajania, Plum. from Mr. John Ray, the father of Engliſh botany.

Hermannia, Tourn. from Dr. Paul Herman, a Saxon, profeſſor of botany at Leyden, and author of an ingenious method, with ſeveral other curious works.

Knautia, Lin. from Chriſtian Knaut, a Saxon, author of a Botanical Method.

Rivina, Plum. from Rivinus, a Saxon, profeſſor of botany at Leipſic, and author of an Eaſy Method of claſſing Plants.

Marchantia, March. from M. Marchant, a Frenchman, author of ſome ingenious papers in the Memoirs of the Academy of Sciences.

Plukenetia, Plum. from Mr. Plukenet, an ingenious Engliſh botaniſt, in whoſe works are deſcriptions of eight thouſand ſeven hundred plants, with two thouſand ſeven hundred figures.

Plumeria, Tourn. from Father Plumier, an ingenious Frenchman, noted for his diſcoveries of American plants.

Tournefortia, Plum. from M. Pitton de Tournefort, the illuſtrious French botaniſt.

Volkameria, Lin. from George Volkamer, a German, author of the *Flora Norimbergenſis*.

Camellia, Lin. from George Camellus, a Jeſuit, author of ſome ingenious papers in the Engliſh Philoſophical Tranſactions, and of a treatiſe *de fabâ Ignatii ſive vomicâ*.

Rudbeckia, Lin. from M. Rudbeck, a Swede, author of a botanical work, entitled, *Campus Elyſius*.

Rumpfia, Lin. from Rumphius, a Dutchman, author of the Herbarium Amboinicum.

Scheuchzeria,

Scheuchzeria, Lin. from J. James Scheuzer, or Scheuchzer, a Swiſs, profeſſor of botany, author of an Arrangement of the Graſſes; a Journey over the Alps; and a Treatiſe entitled *Phyſica ſacra*.

Sloanea, Plumier, from Sir Hans Sloane, the celebrated Engliſh phyſician and naturaliſt.

Boerhaavia, Vaill. from the very eminent Dr. Boerhaave, profeſſor of phyſic and botany at Leyden.

Zanichellia, Lin. from Zanichelli, an Italian, author of a Hiſtory of Plants.

Heucheria, Lin. from Heucher, a German, author of an Index or Catalogue of the Plants in the Botanical Garden at Wittemberg, and of a Treatiſe *de Vegetabil. magicis*.

Niſſolia, Jacquin. from Niſſole, an ingenious Pariſian, author of ſeveral papers in the Memoirs of the Academy of Sciences.

Reaumuria, Haſſelquiſt, from M. de Reaumur, an ingenious French academician and naturaliſt.

Kæmpferia, Lin. from Dr. Kæmpfer, a German, author of the Hiſtory of Japan; the curious Diſſertations on Tea, and *Morus Papyrifera*; and the ingenious collection known by the name of *Amœnitates Exoticæ*.

Juſſiæa, Lin. from Meſſrs. Antony and Bernard Juſſieu, two ingenious French botaniſts, authors of ſeveral excellent papers in the Memoirs of the Academy of Sciences at Paris.

Barleria, Plum. from Jacob Barrelier, a Frenchman, author of a Hiſtory of the Plants of France, Spain, and Italy.

Feuillea, Lin. from Feuillé, a Frenchman, author of a Hiſtory of the Plants of Chili and Peru.

Marſilea, Lin. from Marſili, an ingenious Italian, author of a Diſſertation on the Generation of Muſhrooms.

Garidella, Tourn, from Garidel, a Frenchman, author of the Hiſtory of the plants of Provence.

Iſnarda, Lin. from Danti d'Iſnard, a Frenchman, author of ſome botanical papers in the Memoirs of the French Academy of Sciences.

Valantia, Tourn. from M. Vaillant, an ingenious French-

man, author of a Treatiſe on the Structure of Flowers, and of ſeveral curious botanical papers in the Memoirs of the French Academy.

Ruppia, Lin. from Ruppius, a German, author of the *Flora Jenenſis*, and of an Improvement of Rivinus's Method.

Pontederia, Lin. from Pontedera, an Italian, author of ſome botanical diſſertations, and of a method which combines thoſe of Tournefort and Rivinus.

Montia, Micheli, from Monti, an Italian, author of a work entitled *Prodromus Stirpium agri Bononienſis*.

Dillenia, Lin. from Dillenius, a German botaniſt, noted for his Obſervations on the Moſſes, Muſhrooms, and Sea-weed: he is likewiſe author of the *Flora Giſſenſis*, and *Hortus Elthamenſis*.

Frankenia, Lin. from John Frank, a phyſician of Ulm, and author of a Treatiſe on Male-Balſam-Apple, and Water-germander.

Buxbaumia, Lin. from Dr. Buxbaum, a German, author of an Enumeration or Catalogue of the Plants around Hal, in Saxony, and of five centuries of eaſtern plants.

Heiſteria, Jacquin. from Heiſter, a German, author of a Treatiſe on the Utility of the Leaves, and of a Syſtem which ſeems to have been ſuggeſted by that of Ray.

Tillæa, Micheli, from Tilli, an Italian, author of a Catalogue of the Plants in the Gardens of Piſa.

Martynia, Houſton, from Mr. John Martyn, profeſſor of botany at Cambridge, author of a Commentary on Virgil's Bucolics and Georgics, and of ſeveral other botanical tracts.

Hamellia, Jacquin, from M. Duhamel de Monceau, an ingenious Frenchman, author of la Phyſique des Arbres, Traité des Arbres Fruitiers, and ſome other valuable works in botany, gardening and huſbandry.

Krameria, Loefling, from Kramer, a German, author of a work entitled *Tentamen Botanicum*.

Michelia, Lin. from Micheli, an Italian, noted for his Obſervations on Muſhrooms and Sea-weed; he is likewiſe

author

author of a Catalogue of the Plants cultivated in the Botanical Garden at Florence.

Cateſbæa, Lin. from Mr. Cateſby, who diſcovered it, author of a Natural Hiſtory of Carolina.

Milleria, Houſton, from Mr. Philip Miller, author of the Gardener's Dictionary and Calendar.

Burmannia, Lin. from Dr. John Burman, profeſſor of botany at Amſterdam, and author of ſeveral botanical works, particularly a Deſcription of two hundred Plants from the Cape of Good Hope.

Houſtonia, Lin. from the ingenious Dr. William Houſton, who diſcovered ſeveral curious plants in the Weſt-India iſlands.

Linnæa, Gronovius, from the celebrated naturaliſt, Sir Charles Linné, late profeſſor of botany at Upſal in Sweden.

Waltheria, Lin. from Auguſtus Frederic Walther, a German, profeſſor of botany at Leipſic, and author of a Catalogue entitled *Hortus Waltheri*.

Ludwigia, Lin. from Dr. Chriſtopher Ludwig, profeſſor of botany at Leipſic, and author of ſome very ingenious works, particularly Botanical Inſtitutions, in which is propoſed a method that combines together the very different methods of Linnæus and Rivinus.

Weinmannia, Lin. from Weinman, a German, author of a large botanical work, in ten volumes, folio, with plates beautifully coloured.

Sigeſbeckia, Lin. from Dr. Sigeſbeck, of Peterſburgh, author of the *Flora Petropolitana*, and of two ingenious methods for arranging plants.

Ammannia, Houſton, from John Amman, a Ruſſian, author of a work entitled *Stirpes rariores Rutenicæ*.

Royena, Lin. from M. Adrien Royen, profeſſor of botany at Leyden, author of the *Flora Leidenſis*, in which he has ſuggeſted the idea of a natural method.

Seguieria, Loefling, from M. Seguier, a Frenchman, author of the *Bibliotheca Botanica*, and *Plantæ Veronenſes*.

Halleria, Lin. from the very learned Dr. Albert Haller,

profeſſor

profeſſor of botany at Gottingen, and author of a Natural Method.

Sauvageſia, Lin. from M. Sauvages, an ingenious Frenchman, author of a Method founded upon the Leaves.

Guettarda, Lin. from M. Guettard, a Frenchman, author of ingenious Obſervations on Plants.

Gmelina, Lin. from John Gmelin, a German, author of the *Flora Sibirica*, and of a Voyage to Siberia.

Wachendorfia, Lin. from Wachendorf, profeſſor of botany at Utrecht, and author of a Natural Method of arranging Plants.

Ehretia, Brown, from Ehret, a German, who, in 1748, publiſhed at London, in folio, a work entitled *Plantæ rariores*, with twenty-ſix excellent figures illuminated.

Gleditſia, Lin. from Gleditſch, a German, profeſſor of botany at Berlin, and author of an Arrangement of the Muſhrooms, and of a Hiſtory of the Academy of Sciences at Berlin.

Trewia, Lin. from Trew, a German, profeſſor of botany at Nuremberg, author of a work entitled *Plantæ ſelectæ, decuriæ quatuor*, with forty-three excellent figures illuminated.

Hillia, Jacquin and Lin. from Sir John Hill, author of the Vegetable Syſtem, and of ſeveral other well-known botanical works.

Allionia, Loefling, from Allioni, an Italian, author of a Hiſtory of the Rare Plants of Piedmont, and of a Methodical Synopſis of the Plants in the Garden at Turin.

Brownæa, Jacq. from Mr. Brown, author of the Civil and Natural Hiſtory of Jamaica.

Adanſonia, Lin. from M. Adanſon, a Frenchman, author of a Voyage to Senegal; a work entitled Familles des Plantes; ſeveral papers in the Memoirs of the French Academy; and a Treatiſe upon the Baobab of Proſper Alpinus, which plant it is that Linnæus has diſtinguiſhed by the name of *Adanſonia*, in honour of this gentleman.

Haleſia, Lin. and Ellis, from the reverend and celebrated

Dr.

Dr. Stephen Hales, author of Vegetable Statics, juſtly ſtiled the Modern Theophraſtus.

Queria, Loefling, from M. Quer, profeſſor of botany at Madrid, and author of a Spaniſh Flora.

Minuartia, Loefling, from M. Minuart, profeſſor of botany at Cadiz.

Gouania, Jacquin, from M. Gouan, a Frenchman, author of the *Hortus Regius Monſpelienſis*.

Jacquinia, from M. Jacquin, a German, author of a Catalogue of American Plants, publiſhed at Vienna in 1762. This gentleman undertook his botanical expedition to the Weſt Indies, by the deſire, and at the expence of the emperor. He was afterwards, as I am informed, profeſſor of botany at Augſburg.

Maranta, Plum. from Bartholomew Maranta, an ancient obſcure botaniſt.

Kalmia, Lin. from Dr. Peter Kalm, profeſſor of botany at Abo in Finland, and author of Travels in North America.

Solandra, Lin. from the late Dr. Solander of the Britiſh Muſæum, long a pupil of Linnæus at Upſal.

Elliſia, Lin. from the ingenious John Ellis, Eſq. F. R. S. author of a Natural Hiſtory of Corallines.

Kuhnia, Lin. from Dr. Kuhn of North America, a pupil of Linnæus.

Gardenia, Ellis, from Dr. Garden of South Carolina, an induſtrious botaniſt.

Juſticia, Houſton, from the late James Juſtice, Eſq. principal clerk of ſeſſion at Edinburgh, a curious floriſt, and author of ſome valuable tracts in gardening.

Collinſonia, Lin. from Mr. Peter Collinſon, F. R. S. a lover and patron of the ſciences, of the laſt century, who introduced this plant from America into the Engliſh gardens.

Bufonia, Sauvage, from the ingenious M. de Buffon, a Frenchman, author of the celebrated Natural Hiſtory.

Coldenia, Lin. from Dr. Colden of North America.

Brunia,

Brunia, Lin. from M. le Brun, author of the Travels into Muſcovy, Perſia, and part of the Eaſt Indies.

Haſſelquiſtia, Lin. from Dr. Frederic Haſſelquiſt, an ingenious naturaliſt, and pupil of Linnæus, who travelled into Egypt, Arabia, and the Holy Land, in queſt of natural curioſities. His papers were reviſed and publiſhed by Linnæus, after his death, under the title of Haſſelquiſt's Travels.

Loeſlingia, Lin. from P. Loefling, a Swede, an ingenious pupil of Dr. Linnæus.

Grewia, Lin. from the celebrated Dr. Nehemiah Grew, author of the Anatomy of Plants.

Malpighia, Plumier, from Signior Malpighi, an ingenious Italian, of the 17th century, who communicated his diſcoveries on the internal ſtructure of plants to the Royal Society at London, at the ſame time with Dr. Grew.

Morina, Tourn. from Dr. Morin of Paris.

Monnieria, Loefling, from M. le Monnier, profeſſor of botany at Paris.

Laugeria, Jacq. from M. Laugier, profeſſor of botany at Vienna.

Sibthorpia, Lin. from Dr. Sibthorp, the late profeſſor of botany at Oxford.

Byttneria, Loefling, from M. Buttner, a Pruſſian botaniſt.

Schwenckia, David Van Royen, from M. Schwenke, author of a Catalogue of the Officinal Plants cultivated in the Phyſical Garden at the Hague, 8vo. 1752.

Gronovia, Houſton, from M. Gronovius, a celebrated Dutch botaniſt, editor of the *Flora Virginica*.

Varronia, Brown, from Varro, the Roman, who lived about the time of Auguſtus Cæſar, and wrote ſome tracts on huſbandry.

Galenia, Lin. from the celebrated Galen.

Meſua, Lin. from Meſue, an Arabian botaniſt, who lived in the end of the eighth century.

Avicennia, Jacq. from Avicenna, an Arabian phyſician and botaniſt of the eleventh century.

Averrhoa,

Averrhoa, Lin. from Averrhoes, a native of Corduba, in Spain, who lived in the eleventh century.

Sarracenia, Tourn. from Sarrazin, an ingenious Frenchman, who introduced ſeveral Canadian plants into the European Gardens.

Ferraria, Burmannus, from Ferrarius, an Italian botaniſt of the 17th century, author of a Treatiſe on the Culture of Flowers, publiſhed at Rome in 1740, with ſeventy-five excellent copper-plates.

Cherleria, Haller, from Cherlerus, a botaniſt of the ſixteenth century, cotemporary with John Bauhin.

Geoffræa, Jacq. from M. Geoffroy, an ingenious naturaliſt of the laſt century, author of ſeveral excellent works, particularly a large Treatiſe on the Materia Medica.

Moehringia, Lin. from Moehring, an ingenious botaniſt of the laſt century, author of a Catalogue of the numerous plants cultivated in his own garden.

Browallia, Lin. from M. Browal, an ingenious botaniſt of the laſt century, author of a Defence of the Sexual Syſtem, in anſwer to Sigeſbeck, who had attacked it with great ſpirit.

Hebenſtretia, Lin. from M. Hebenſtreit, a German, profeſſor of botany at Leipſic, and author of a work entitled *Definitiones Plantarum*, publiſhed at Leipſic in 1731.

Artedia, Lin. from Peter Artedi, a learned Swediſh naturaliſt, who was unfortunately drowned, at the age of thirty, in 1735. His poſthumous works were publiſhed by Linnæus in 1738.

Celſia, Lin. from Olaus Celſius, an ingenious botaniſt of the laſt century, author of a book explaining the botany of the ſcriptures.

Hottonia, Boerhaave, from P. Hotton, author of a Hiſtory of Botany.

Sherardia, Dillen. from Dr. William Sherard, a very eminent botaniſt of the ſeventeenth century, author of an Introduction to Botany, under the title of *Schola Botanices*. His *Hortus ſiccus*, or dried collection of plants, is ſaid to

have

have conſiſted of twelve thouſand ſpecies; that of Sloane contains only eight thouſand.

Spigelia, Lin. from Adrian Spigelius, an Italian botaniſt, who lived in the beginning of the ſeventeenth century.

Jungermannia, Micheli, from Jungermannus, a botaniſt of the ſeventeenth century.

Garcinia, Lin. from M. Garcin, author of a Hiſtory of Indian plants.

Cortuſa, Boerhaave, from Cortuſus, a botaniſt of the ſixteenth century.

Cupania, Plum. from Cupanus, a botaniſt, who lived in the end of the ſeventeenth century.

Barreria, Lin. from M. Barrere, an ingenious botaniſt of the laſt century.

Stellera, Gmelin, from Steller, a botaniſt of the laſt century, who diſcovered it.

Lechea, Kalm. from M. Lech, an ingenious botaniſt of the laſt century.

Bobartia, Lin. from Dr. Bobart, of Oxford, who completed Moriſon's Univerſal Hiſtory of Plants.

Bromelia, Plum. from Bromel, a French botaniſt of the ſeventeenth century.

Fagonia, Tourn. from Dr. Fagon, ſuperintendant of the king's gardens at Paris.

Randia, Houſton, from Mr. Iſaac Rand, an ingenious Engliſh botaniſt.

Suriana, Plumier, from Joſeph Surian of Marſeilles, an eminent naturaliſt.

Tradeſcantia, Ruppius, from Mr. John Tradeſcant, an eminent Engliſh floriſt and antiquary.

Ximenia, Plumier, from Franciſcus Ximenes, a Spaniſh botaniſt of the 17th century, author of a Hiſtory of Mexican Trees and Plants.

Claytonia, Lin. from Dr. Clayton of Virginia, who diſcovered it.

Dierville, Tourn. from M. Dierville, a French ſurgeon,

who introduced it into the European gardens, from Nova Scotia, where he diſcovered it.

Bartramia, Lin. from Mr. John Bartram of Philadelphia, who diſcovered it.

Banniſteria, Houſton, from Mr. Banniſter, an ingenious botaniſt, who travelled into Virginia in ſearch of plants.

Gundelia, Tourn. from Dr. Gundelſcheimer, who accompanied Tournefort in his travels to the Eaſt.

Knoxia, Lin. from Mr. Knox, author of a Hiſtory of the Iſland of Ceylon.

Lippia, Houſton, from Dr. Auguſtus Lippi, who travelled into Egypt and Abyſſinia, in ſearch of natural curioſities.

Mitchella, Lin. from Mr. Mitchel, who travelled into Virginia in queſt of plants.

Oldenlandia, Plumier, from Henry Bernard Oldenland, a German botaniſt, who travelled into Africa in queſt of plants.

Buddleia, Houſton, from Mr. Buddle, an ingenious Engliſh botaniſt.

Tozzia, Micheli, from the Abbé Tozzi, a learned Italian.

Blaſia, Micheli, from M. Blaſi, an Italian monk, addicted to the ſtudy of botany.

Riccia, Micheli, from Signior Ricci, an Italian knight.

Moræa, Miller, from Robert More, Eſq. of Shrewſbury, an ingenious botaniſt.

Blæria, Lin. from Dr. Patrick Blair, author of a book entitled Botanical Eſſays, and of ſeveral other curious tracts in botany and gardening.

Hopea, Garden, from the ingenious and accurate Dr. John Hope, late profeſſor of botany at Edinburgh.

Hudſonia, Lin. from Mr. Hudſon, author of the *Flora Anglica*.

XVIII. Generic names, of Greek origin, expreſſive of the eſſential character, habit, place of growth, and virtues, or ſenſible qualities of any plant, are, in Linnæus's opinion, preferable to all others.

The

The following names are expreſſive of the eſſential character.

Adenanthera, Royen. (ἀδὴν, ἀδενος, a gland; and ἀνθηρὰ, the tops of the ſtamina) from its glandular tops.

Triopteris, Lin. (Τρεῖς, three, and πτερον, a wing) from each of its three ſeeds being furniſhed at top with an expanſion reſembling a wing.

Epilobium, Dillen. (ἐπι, upon, λοβος, a pod, and ἰον, a violet) from the flower being placed upon the *germen*, or ſeed-bud.

Helicteres, Lin. (ἕλιξ, a ſcrew) from its twiſted ſpiral fruit.

Tetracera, Lin. (Τεσσαρες, atticé, τετταρες, four, and Κερας, a horn) from the figure of its four capſules.

Trichoſanthes, Lin. (Θριξ, Τριχος, hair, and ἀνθος, a flower) from the petals ending in long branched hairs.

Greek generic names expreſſive of the habit are more frequent. The following liſt is chiefly of this kind.

Glycyrrhiza, Tourn. (γλυκυς, ſweet, and ῥιζα, a root) from the ſweetneſs of its root.

Ophiorrhiza, Lin. (ὀφις, a ſerpent, and ῥιζα, a root) from the convolutions of its root, reſembling thoſe of a ſerpent; or, more probably, from its pretended efficacy in curing the bites of ſerpents, and other venomous creatures.

Epidendrum, Lin. (ἐπι, upon, and δενδρον, a tree) from the plant growing naturally upon trees.

Leucadendron, Lin. (λευκος, white, and δενδρον, a tree) from the ſhining ſilver colour of the leaves.

Hæmatoxylum. Lin. (αἱμα, blood, and ξυλον, wood) from the beautiful red colour of its wood.

Zygophyllum, Lin. (ζυγὸς, a yoke, and φυλλον, a leaf) from the leaves being, as it were, yoked together, two and two upon the ſame foot-ſtalk.

Hydrophyllum, Tourn. (ὕδωρ, water, and φυλλον, a leaf) from the cavities of the leaves in ſpring being filled with water.

Eriocaulon,

Eriocaulon, Gronovius, (ἔριον, wool, and καυλὸς, the ſtem) from its ſoft woolly ſtalks.

Eriocephalus, Dillen. (ἔριον, wool, and κεφαλη, the head) from its woolly leaves, which ſurround the ſtalks in cluſters.

Rhodiola, Lin. (ῥοδον, a roſe) from the ſmell of the roots, which reſembles that of the roſe.

Trigonella, Lin. (Τρεῖς, three, and γωνη, an angle) from its three cornered flower.

Crotalaria, Tourn. (κροταλον, a rattle) from the branches that are furniſhed with pods being uſed by the infant-Indians for rattles.

Rhizophora, Lin. (ῥιζα, a root, and φερω, to bear) from its branches bearing ſtringy roots, which penetrate into the earth or water.

Echinophora, Tourn. (εχῖνος, a hedge-hog, and φερω to bring, or bear) from its prickly fruit.

Eriophorum, Lin. (ἐριοφορος, bearing wool) from its fruit being furniſhed with long woolly hairs.

Acalypha, Lin. (καλος, beautiful, ἀ, not, and ἀφὴ, touch) from the leaves, which ſting, like thoſe of nettles, upon being touched.

Alyſſum, Tourn. (ἀλυσσω, to be diſturbed in mind, to be mad) from its ſuppoſed efficacy in curing madneſs; whence, likewiſe, the Engliſh title of madwort.

Rhinanthus, Lin. (ῥὶν, the noſe, and ἀνθος, a flower) from the upper lip of its gaping petal reſembling a noſe, or the proboſcis of an elephant.

Phyllanthus, Lin. (φυλλον, a leaf, and ἀνθος, a flower) from the flowers being produced upon the edges and under-ſide of the leaves.

Helianthus, Lin. (ἥλιος, the ſun, and ἀνθος, a flower) from the obvious reſemblance of its large flower to the diſk or body of the ſun; the florets in the circumference reſembling the rays of that luminary.

Calophyllum, Jacquin. (καλος, beautiful, and φυλλον, a leaf) from the beauty of the leaves.

Liriodendrum, Lin. (λειριον, a lily, and δενδρον, a tree) from

the fancied reſemblance of its flowers to thoſe of the lily.

Rhododendron, Lin. (ῥοδον, a roſe, and δενδρον, a tree) from the reſemblance of its flowers to thoſe of the roſe.

Myriophyllum, Vaillant. (μυρίος, infinite, and φυλλον, a leaf) from its numerous leaves.

Chryſanthemum, Tourn. (χρυσος, gold, and ἀνθος, a flower) from the yellow colour of the florets.

Chryſocoma, Lin. (χρυσος, gold, and κομη, a buſh of hair) from the foot-ſtalks being terminated with a head of flowers of a bright yellow colour.

Ophioglossum, Tourn. (ὄφις, a ſerpent, and γλῶσσα, a tongue) from the fancied reſemblance of its jointed ſpike of flowers to an adder's or ſerpent's tongue.

Cynogloſſum, Tourn. (κύων, κύνος, a dog, and γλῶσσα, a tongue) from the leaves reſembling, in figure, a dog's tongue.

Podophyllum, Lin. (πους, ποδος, a foot, and φυλλον, a leaf) from its bearing that particular kind of leaf called by Linnæus, foot-ſhaped.

Chryſophyllum, Lin. χρυσος, gold, and φυλλον, a leaf) from the leaves being of a beautiful gold-colour on their under-ſide.

Chærophyllum, Tourn. (χαίρω, to rejoice, and φυλλον, a leaf) from the exhilarating quality of the leaves.

Hæmanthus, Tourn. (αἷμα, blood, and ἀνθος, a flower) from the beautiful-red colour of the flower.

Amaranthus, Tourn. (ἀ, not, and μαραίνω, to wither) from its flower not ſpeedily withering after being cropped.

Cephalanthus, Lin. (κεφαλη, a head, and ἀνθος, a flower) from the branches being terminated with ſmall bunches or heads of flowers.

Chionanthus, Royen. (χιων, ſnow, and ἀνθος, a flower) from the beautiful whiteneſs of its flowers.

Galanthus, Lin. (γαλα, milk, and ἀνθος, a flower) from the milky whiteneſs of its flowers.

Melianthus, Tourn. (μέλι, honey, and ἀνθος, a flower) from the flower being filled with a ſweet ſubſtance like honey.

Chryſobalanus,

Chryſobalanus, Lin. (χρυσος, gold, and βαλανος, a plumb, or cherry) from the red, or yellow colour of its fruit.

Lithoſpermum, Tourn. (λιθος, a ſtone, and σπέρμα, a ſeed) from its hard ſtony ſeeds.

Ceratocarpus, Buxbaum. (κερας, a horn, and καρπος, fruit) from its capſule or ſeed-veſſel and ſeeds being furniſhed with an appearance like two horns.

Melampyrum, Tourn. (μελας, black, and πυρὸς, wheat) from the colour of its ſeeds or grains, which, in form, reſemble thoſe of wheat.

Oſteoſpermum, Lin. (ὀστεον, a bone, and σπερμα, a ſeed) from its hard bony ſeeds.

Conocarpus, Jacquin. (κῶνος, a cone, and καρπος, fruit) from its ſeed-buds being collected into a cone.

Tragopogon, Tourn. (τράγος, a goat, and πωγων, a beard) from the reſemblance of its ſeeds covered with the *pappus* or down to a goat's-beard.

Nyctanthes, Lin. (νυξ, the night, and ἄνθος, a flower) from the flowers opening at night, and falling in the morning.

Melanthium, Lin. (μέλας, black, and ἄνθος, a flower) from the colour of the flower, which is a dark brown.

Agave, Lin. (ἀγαυὸς, admirable) from its ſuperb and beautiful appearance.

Erythronium, Lin. (ἐρυθρὸς, red, and ἰον, a violet) from the beautiful colour of its flowers.

Clematis, Lin. (κλήμα, a little vine, a climber) from its ſupporting itſelf, like the vine, upon the bodies in its neighbourhood.

Gnaphalium, Vaillant. (γνάφαλον, the fine white downy appearance to be obſerved on the ſurface of many plants) from its ſoft downy leaves and ſtalks.

Aſter, Tourn. (ἀστὴρ, a ſtar) from the figure of the flower.

Hypecoum, Tourn. (ὑπηχέω, to reſound) from the ſeeds being thrown out of their jointed pod, or capſule, with velocity and a conſiderable noiſe.

Oxalis, Lin. (ὀξὺς, ſour) from the acidity of its leaves.

Parthenium, Lin. (παρθενος, a virgin) from its efficacy in diſorders of the womb.

Heliotropium, Tourn. (ἡλιος, the ſun, and τρεπω, to turn) from the flower always turning its diſk to the ſun, and following its direction.

Leucoium, Ruppius. (λευκὸς, white, and ἰον, a violet) from the beautiful whiteneſs of the flower.

Ipomœa, Lin. (ἰψ, ἰπος, the flower called convolvulus, and ὁμοιὸς, like) from the great reſemblance of its flower to that of convolvulus, or bi d-weed.

Bunias, Lin. } (βυνος, a little hill) from the native ſoil of
Bunium, Lin. } the plants.

Sideroxylum, Dillen. (σιδηρος, iron, and ξυλον, wood) from the hardneſs and firm texture of the wood, which is ſo weighty as to ſink in water.

Aphanes, Lin. (ἀφανὴς, not conſpicuous) from the minuteneſs, and low ſtature of the plant.

Pteris, Lin. (πτερὸν, a wing) from the diviſions of the ſmaller leaves reſembling wings.

Lythrum, Lin. (λυθρον, blood, gore) from the deep purple colour of the flowers.

Orchis, Tourn. (ὀρχις, a teſticle) from the fancied reſemblance of its roots.

Cotyledon, Tourn. (κοτυλη, a cavity) from the leaves being hollowed, like the navel.

Phallus, Micheli (φαλλος, the yard) from the peculiar figure of this muſhroom.

Xeranthemum, Tourn. (ξηρὸς, dry, and ἀνθος, a flower) from the extreme dryneſs of the petals; a circumſtance which preſerves the beauty of the flowers for many months. Hence it is termed, in Engliſh, everlaſting, or the eternal flower.

Adoxa, Lin. (ἀ, not, and δόξα, glory) from its diminutive appearance and want of beauty.

Anthoxanthum, Lin. (ἀνθος, a flower, and ξανθος, yellow,) from the yellowiſh colour of the ſpike of flowers.

Sphæranthus, Vaillant. (σφαῖρα, a ſphere, or globe, and ἀνθος, a flower) from its globular head of flowers.

Siphonanthus,

Siphonanthus, Lin. (σιφων, a ſyphon, or tube, and ἀνθος, a flower) from its long tubular petal.

Meſembryanthemum, Dillen. (μεσος, the middle, ἡμερα, a day, and ἀνθος, a flower) from the flowers of this genus opening in the middle of the day. Linnæus derives it from the flower being ſeated upon the germen, or ſeed-bud, in Greek, ἐμβρύων. Either etymology is expreſſive of a characteriſtic of the genus in queſtion.

Sideritis, Tourn. (σιδηρος, iron) from the plants of this genus being vulnerary, and of eſpecial efficacy in wounds made by the ſword.

Camphoroſma, Lin. (ὀσμη, a ſmell) from its having the ſmell of camphire.

Polypodium, Tourn. (πολυς, many, and πους, a foot) from its roots ſerving the office of feet, by penetrating into whatever they can lay hold of, and thus ſupporting the plant.

Aſplenium, Lin. (ἀ, priv. and σπλην, the ſpleen) from its efficacy in diſeaſes of the ſpleen.

Dioſma, Lin. (ζευς, διος, Jupiter, and ὀσμη, a ſmell) from the very agreeable odour of the plants of this genus.

Dracontium, Lin. (δρακων, a dragon) probably from the protuberances of the ſtalks, which are of different colours, and ſhine like the body of a ſerpent.

Echium, Tourn. (ἐχις, a viper) from its ſeeds when ripe reſembling the head of a viper.

Geranium, Tourn. (γερανος, a crane) from the fancied reſemblance of its permanent ſtyle to a crane's bill.

Hieracium, Tourn. (ἱεραξ, a hawk) from a vulgar opinion that the juice of theſe plants is uſed by hawks to remove any occaſional films from the eyes of their young.

Cardioſpermum, Lin. (καρδια, the heart, and σπερμα, a ſeed) from the ſeeds being marked at the baſe with a heart.

Heliocarpos, Lin. (ἡλιος, the ſun, and καρπος, fruit,) from the reſemblance of the threads which ſurround the borders of the capſule to the rays of the ſun,

Trichoſtema, Gronovius, (θριξ, τριχος, a hair, and στημων, a ſtamen, or thread) from its long tender ſtamina reſembling hairs.

Dianthera, Gronovius. (δις, twice, and ἀνθηρα, the top of

the ſtamen) from its having two *anthers* upon each filament.

Elæocarpus, Burman. (ἐλαῖα, an olive, and καρπὸς, fruit) from the reſemblance of its fruit to that of an olive.

Buphthalmum, Tourn. (βοῦς, an ox, and ὀφθαλμὸς, an eye) from the fancied reſemblance of its large compound flower to that of an ox-eye.

Dracocephalum, Tourn. (δράκων, a dragon, and κεφαλὴ, the head) from the figure of the flower.

Dioſpyros, Lin. (ζεὺς, διὸς, Jupiter, and πυρὸς, wheat) from the excellence of the plant.

Dipſacus, Tourn. (διψάω, to thirſt) probably from the leaves collecting water in their cavities, and thus preventing the injuries which might ariſe to the plant from aridity.

Stachys, Tourn. (στάχυς, a ſpike, or ear of corn) from its flowers being produced in long ſpikes.

Ceratonia, Lin. (κεράτιον, a pod, ἀ Κερας, *cornu, quia ſiliqua eſt quaſi corniculata*) from its bearing pods. It was formerly termed *ſiliqua*, the pod by way of eminence; Linnæus has changed that name for a Greek one of the ſame import.

Platanus, Tourn. (πλατυς, large, ample) from the great dimenſions of the trees of this genus.

Tribulus, Tourn. (τρίβολοι, caltrops,) from its prickly fruit.

Thlaſpi, Tourn. (θλαω, to compreſs, to ſqueeze together) from its flat compreſſed ſeed-veſſel.

Panax, Lin. (πᾶν, every, and ἄκος, a medicine or remedy) from its boaſted efficacy in medicine.

Iatropha, Lin. (ἰατρὸς, a phyſician, and φάγω, to eat) from the plant being uſed both for food and phyſic.

Capſicum, Tourn. (καπτω, to bite) from its hot acrid quality.

Azalea, Lin. (ἀζαλέος, dry, torrid) from its delighting in a dry parched ſoil.

Origanum, Tourn. (ὄρος, a mountain, and γάνος, delight, joy) from its native ſoil.

Typha, Tourn. (τῦφος, a marſh) from its growing naturally on wet boggy ground.

Cypripedium, Lin. (κύπρις, one of Venus's names, and ποδίον, a ſhoe, or ſlipper) from the obvious reſemblance of the nectarium of the flower to a ſlipper.

Delphinium, Tourn. (δελφὶν, a dolphin) from the fancied reſemblance of the flowers, before expanſion, to the fiſh called a dolphin.

Hyoſcyamus, Tourn. (ὗς, a ſwine, and κύαμος, a bean) *quaſi* hog-bean.

Hippomane, Loefling, (ἵππος, a horſe, and μανία, madneſs) from the noxious quality of the plants of this genus.

Hippocrepis, Lin. (ἵππος, a horſe, and κρηπὶς, a laſt, likewiſe a horſe-ſhoe) from each joint of the pod reſembling a horſe-ſhoe.

Tragacantha, Tourn. (τράγος, a goat, and ἄκανθα, a thorn) from the plants being armed with long ſharp thorns.

Chelone, Tourn. (χελώνη, a tortoiſe) from the figure of its ſeeds, which are round, compreſſed, and begirt with a membranaceous rim, or border.

Bupleurum, Tourn. (βοῦς, an ox, or cow, and πλευρὸν, a rib, ſide, or breaſt) from a vulgar opinion that theſe plants burſt the bellies of cows, which eat of them.

Chryſoſplenium, Tourn. (χρυσὸς, gold, and σπλὴν, the ſpleen) from the flowers being of a golden colour, and of ſuppoſed efficacy in diſeaſes of the ſpleen.

Adianthum, Tourn. (ἀ, not, and διαίνω, to wet, or moiſten) probably from its growing out of the clefts of rocks, and in a ſandy ſoil, ſo as not to require any quantity of moiſture.

Æſchynomene, Lin. (αἰσχύνομαι, to be aſhamed, or ἴσχω, to contract) from its reſemblance to the ſenſitive plant, which is ſometimes diſtinguiſhed by this appellation.

Mimoſa, Tourn. (μίμος, a mimic) from its imitating the motions of animals.

Polygala, Tourn. (πολὺ, much, and γαλα, milk) from its increaſing the quantity of milk to cows which feed on it.

Galium, Tourn. (γάλα, milk) from the property poſſeſſed by ſome plants of this genus, of coagulating milk.

Poterium, Lin. (ποτήριον, a cup, or bowl) from its being

put into cool tankard in ſummer, to give the wine an agreeable flavour.

Picris, Lin. (πικρὸς, bitter) from its bitter taſte.

Glycine, Lin. (γλυκὺς, ſweet) from the leaves having a ſweet taſte like that of liquorice.

Rheum, Lin. (ῥεω, to flow) from its purgative quality.

Aizoon, Lin. (ἀεὶ, always, and ζωον, alive) from its duration.

Ornithopus, Lin. (ὄρνις, a bird, and πους, a foot) from its bended and pointed pods exactly reſembling the toes of a bird's foot.

Aconitum, Tourn. (ἀκονη, a cliff, a rugged rock) from its native ſoil.—Thus Ovid, in ſpeaking of the venomous potion prepared for Theſeus by Medea, from the plant produced by the white froth (*ſpumæ albentes*) of Cerberus, gives this etymology of its name,

> " Quæ quia naſcuntur dura vivacia caute,
> " Agreſtes ACONITA vocant."
>
> Metam. Lib. VII. 418.

From the above liſts are excluded ſuch names as are not of obvious origin, and where the etymology, though ſufficiently perſpicuous, is not expreſſive of any ſtriking character or circumſtance in the genus in queſtion. Perhaps there is ſome degree of impropriety in having dwelt ſo long upon a barren and unentertaining ſubject like that of names: but, as the preſent work is chiefly deſigned for the uſe of the unlearned botaniſt, an explanation of the modern generic nomenclature ſeemed, in ſome ſort, neceſſary, as, however liable to cenſure, it bids fair to be permanent.

XIX. Generic names of an immoderate length, or of difficult and harſh pronunciation, are, by all means, to be avoided. For theſe reaſons Linnæus has very properly changed the

Kalophyllodendron —	of Vaillant, for	Calophyllum.
Stachyarpogophora —		Celoſia.
Caraxeron — —		Gomphrena.
Myrobatindum —		Lantana.
Hydroceratophyllon —		Ceratophyllum.

Micro-

Microleuconympha — } of Boer- { Hydrocharis.
Hypophyllocarpodendron } haave, for { Leucadendron.

Coriotragematodendros of Plukenet, for Myrica.
Orbitochortus — — of Knaut, for Fagonia.

Eupatoriophalacron — } of Dillenius, { Verbesina.
Galeobdolon — — } for { Galeopsis.

Pterospermadendron — of Ammannus, for Pentapetes.
Acrochordodendros — of Plumier, for Cephalanthus.

XX. Terms of art are not to be used as generic names. Hence Linnæus has changed

Tuberosa — — }
Spica — — — }
Siliqua — — } for
Nux — — — }
Odorata — — }

{ Polianthes.
{ Lavandula.
{ Ceratonia.
{ Iuglans.
{ Scandix.

XXI. Generic names, which are not of Greek or Latin origin, are, according to Linnæus, to be excluded from the nomenclature of botany. This rule, which indeed serves as a foundation to all the others, has been severely criticised by some modern authors. It has been said that the term barbarous, which Linnæus applies to all the Indian, African, American, and foreign names of genera, may, with equal justice, be applied, by those nations, to our learned European names, which to them are as little expressive of the essential character, or habit of the plants in question, as theirs are to us; that they ought, therefore, to be deemed equivalent to the Greek and Latin names, and be adopted, unless when immoderately long, or of harsh and difficult pronunciation. The same authors have disputed the necessity of employing generic names expressive of any character or circumstance in the parts of plants, much more of burdening the nomenclature with a profusion of names in honour of botanists, unless where the merit of the man has been

so

Ribes, *Doronicum*, *Thea*, *Coffea*, *Caſſine*, *Annona*, *Mammea*, *Chara*, *Pothos*, *Baſella*, *Hura*, *Yucca*, *Guaiacum*.

Names of the Species.

Since the time of Caſpar Bauhin, the different ſpecies of pl nts have been diſtinguiſhed by certain ſhort deſcriptions, or phraſes, expreſſive of ſome circumſtance in their external form or habit. Theſe deſcriptions, which have been very improperly denominated ſpecific names, Linnæus has ſubjected to the ſame rules with the names of claſſes and genera. The eſſential difference of each ſpecies is to be expreſſed in the name or definition, which is intended to diſcriminate the ſpecies in queſtion from all the plants of the ſame genus, and fr m none others.

The deſcription of the ſpecies termed the ſpecific name, and which, in Linnæus's opinion, ought never to exceed twelve words, is preceded by the trivial name, which always conſiſts of one word placed after the generic name, and is not ſubjected to the ſame conſtraint as the names of the claſſes and genera, and deſcriptions of the ſpecies. In the following examples the generic name is marked in ſmall capitals, the ſpecific in Roman characters, the trivial in Italic.

Generic name. Trivial name.	*Specific name.*
RHODODENDRON *ferrugineum.*	RHODODENDRON foliis glabris ſubtus leproſis, corollis infundibuliformibus.
PYROLA *ſecunda.*	PYROLA racemis unilateralibus.
PYROLA *umbellata.*	PYROLA pedunculis ſubumbellatis.
PYROLA *uniflora.*	PYROLA ſcapo unifloro.
MAGNOLIA *grandiflora.*	MAGNOLIA foliis lanceolatis perennantibus.
MAGNOLIA *glauca.*	MAGNOLIA foliis ovato-oblongis ſubtus glaucis.

Generic name. Trivial name.	*Specific name.*
HEBENSTRETIA *dentata.*	HEBENSTRETIA foliis dentatis.
HEBENSTRETIA *cordata.*	HEBENSTRETIA foliis ſubcarnoſis, cordatis, ſeſſilibus.
PYRUS *Malus.*	PYRUS foliis ſerratis, umbellis ſeſſilibus.
PYRUS *Cydonia.*	PYRUS foliis integerrimis, floribus ſolitariis.

From the firſt, third, fourth, ſixth, ſeventh and eighth of the above examples, it is evident that the trivial name is frequently an abbreviation of the ſpecific ; and as this laſt contains the eſſential difference, where ſuch difference is conſpicuous, the trivial name is an abridgment of that difference, where ſuch abridgment can be conveniently contained in one word.

When two or three genera of former authors are abſorbed by one, it is common to ſee the names of thoſe genera retained as trivial names. Thus, in the two laſt examples, MALUS and CYDONIA, two genera of Tournefort, are converted into trivial names, for characterizing the moſt common ſpecies of each reſpective genus. Such trivial names have always a capital for their initial letter.

The diſtinction of ſpecific and trivial names ſuggeſted by Linnæus deſerves particular attention, the rather as many circumſtances, deemed improper for entering into the deſcription, or ſpecific name, are employed without reſerve for the trivial.

So extraordinary a meaſure required ſome explanation : but Linnæus has thought fit to be ſilent on that head. He has judged very properly ; for no ſatisfactory reaſon could be aſſigned for ſo glaring an inconſiſtency.

In fact, what can be more abſurd, than to characterize a plant by a circumſtance, which is either accidental and inconſtant, or, at beſt, deemed unworthy of a place in its deſcription ! yet, half the trivial names in the *Species Plantarum*

are

are of this kind. Not that theſe names are totally to be rejected; many of them being highly proper and ſignificant; but we muſt diſapprove and condemn the ſophiſtry of Linnæus, who would excuſe, and even applaud, in himſelf, what he ſo ſeverely cenſures in others.

This being premiſed, we proceed to lay down Linnæus's general principles or aphoriſms on this ſubject.

I. Genuine ſpecific differences are afforded by the root, trunk, leaves, fulcra, mode of flowering, and ſuch circumſtances of the parts of fructification as are unconnected with the generical deſcription.

II. The ſpecific name ought to be expreſſive of characters inſcribed, as it were, upon the plant itſelf. All accidental marks, therefore, not exiſting in the plant, or not conſpicuous in its appearance, are to be excluded from the ſpecific difference.

III. Magnitude being ſubject to variations, from place, ſoil, climate, and other circumſtances, is not to enter into the ſpecific difference.

IV. Specific names are by no means to be employed, which pre-ſuppoſe a knowledge of other ſpecies of a different genus. Former botaniſts, ſays Linnæus, conſtructed their ſpecific differences in ſuch a manner, as if thoſe for whom they wrote had been previouſly acquainted with moſt of the European plants. Their deſcriptions are frequently compariſons of the plants in queſtion with thoſe of their own country. Thus ſuch a plant had a hawk-weed leaf; another had the leaf of the willow; a third of groundſel; one had the appearance of balm; another of wormwood. Such characters Linnæus diſclaims. A plant, in his opinion, ought to be known by the name aſſigned to it; and the name to be ſuggeſted by the appearance of the plant. Each is to be diſcovered by its proper character, written in the one, delineated in the other. Names, he continues, pre-ſuppoſing other plants, have always a tendency to lead thoſe who uſe them into an error ſimilar to what Logicians call *committing the circle*.

Notwithſtanding this ſhew of reaſoning, I believe it will be

be found that ſpecific differences from compariſon with plants, or the parts of plants, generally known, make a much ſtronger impreſſion, and lead more directly to the knowledge required, than the moſt accurate deſcription of characters exiſting in the plant itſelf.

V. Specific names, pre-ſuppoſing a knowledge of other ſpecies of the ſame genus are, for the ſame reaſon, proſcribed from the modern nomenclature of botany. Hence the following names are cenſured by Linnæus,

Orchis flore *candidiſſimo*, Tourn.

Campanula *anguſtifolia*, *magno* flore, minor, Tourn.

Campanula, flore *minore*, *ramoſior*, Moriſon.

A beginner is not ſuppoſed to know of any ſpecies of campanula, that is leſs branched, or of orchis, whoſe flowers are leſs white. Such names too, from their very nature, are fluctuating. In fact, the eſtabliſhment of ſpecific names upon a ſolid foundation, muſt be preceded by a knowledge of all the ſpecies of any particular genus. For as the eſſential difference of any ſpecies manifeſtly implies a character peculiar to that ſpecies, and which does not exiſt in any of its congeners; it is evident that the diſcovery of a new ſpecies poſſeſſing a common character, muſt bring the eſſential difference in queſtion to an end.

To illuſtrate this by an example. The eſſential character of a ſpecies of winter-green is deſcribed by Linnæus to be a naked ſtalk ſupporting a ſingle flower. By this deſcription the ſpecies in queſtion is eſſentially diſtinguiſhed from all the ſpecies of winter-green yet known. But, ſuppoſing another ſpecies ſhould be diſcovered with a naked ſtalk and a ſingle flower, the ſpecific name juſt mentioned would no longer be an eſſential difference; another muſt be ſubſtituted; and that, perhaps, in conſequence of further diſcoveries, muſt give place to a third. This obſervation ſufficiently accounts for the numerous alterations in every edition of the *Species Plantarum*; and has almoſt convinced me of the neceſſity of employing proper ſpecific names, not expreſſive of any eſſential difference whatever, nor, of conſequence,

ſequence, ſubject to continual variation from future diſcoveries.

VI. The name of the diſcoverer or deſcriber of any plant is not to enter into the ſpecific difference. On this account, the following ſpecific names are rejected from the modern nomenclature:

Trifolium *gaſtonium* of Moriſon.
Gramen cyperoides *Bælii* of Lobelius.
Conyza tertia *Dioſcoridis* of C. Bauhin.
Conyza media *Matthioli* of I. Bauhin.
Narciſſus *Tradeſcantii* of Rudbeckius.

The following are liable to cenſure for a ſimilar reaſon,

Sideritis *Valerandi Dourez*
Campanula a *Toſſano Carolo* miſſa } of I. Bauhin.
Mimoſa à Domino *Hermans* miſſa of Breynius.
Amanita *Divi Georgij* of Dillenius.
Chamæpithys flore pluſquam eleganti, ſeu *Pluſqueneti*, } of Plukenet.
Eriocephalus *Bruniades*,

VII. The place of growth, or native ſoil of any plant is not an eſſential character; and, therefore, ought to make no part of the ſpecific difference. No one, ſays Linnæus, would chuſe to make a voyage to Japan, the Cape of Good Hope, or Peru, to be ſatisfied of the accuracy of the deſcription of a plant. Beſides, the ſame ſpecies is often produced in very different ſoils, and in regions the moſt diſtant from one another. The Alpine plants are not rarely found in the fens; nay, Lapland, Siberia, Canada, Aſia, and America, frequently produce the ſame individual ſpecies.

Improper, however, as the circumſtances of ſoil, and place of growth, are deemed in a ſpecific deſcription, Linnæus has not ſcrupled, however inconſiſtently, to employ them upon ſeveral occaſions in denominating the ſpecies. I ſaid, however inconſiſtently; for if the ſoil, by reaſon of its being an accidental and variable circumſtance, is deemed unworthy a place in the ſpecific difference, how can it, with any propriety, enter into the abridged deſcription, or trivial

name?

name? If a plant, which is a native of two very remote countries, as Guinea and Japan, cannot have its place of growth expreſſed in the deſcription, is it proper to miſlead the ignorant, by ſignifying in the title, or trivial name, that the plant in queſtion is the produce of one particular country only, when, for the very oppoſite reaſon, its place of growth could not be mentioned in the ſpecific deſcription?

VIII. The time of flowering, duration, colour, taſte, ſmell, and powers of plants, are very fallacious marks of diſtinction, and, therefore, to be totally excluded from the ſpecific name.

IX. The generic name is to be applied and prefixed to each particular ſpecies, that the genus, as well as ſpecies, may be ſignified by the deſcription, or ſpecific name. Indeed, without the name of the genus, the ſpecific difference is of no ſignificancy. A mutilated deſcription of that kind may be applicable to a hundred different plants, as the eſſential characters of the ſpecies are only intended to diſcriminate plants of the ſame genus, and may, therefore, be frequently poſſeſſed in common by plants of a different genus. To aſcertain, therefore, the plant in queſtion, beyond the poſſibility of a miſtake, let the generic name be prefixed to each ſpecies, and announced with it. Moriſon and Ray, although they reduced the ſpecies under their reſpective genera, were ſeldom careful to adopt the generic name, but ſubſtituted a kind of proper ſpecific name in its ſtead; ſo that a quotation from either of theſe authors, not ſuggeſting an idea of the genus, becomes only intelligible by being conſulted in their reſpective works. Thus to take an example from Ray. Under the generical name STOECHAS are arranged the following ſpecies.

I. *Stoechas citrina germanica, latiore folio.*
II. *Chryſocome Æthiopica, plantaginis folio.*
III. *Helichryſum abrotani feminæ foliis.*
IV. *Helichryſum creticum.*
V. *Stoechadi citrinæ alteri inodoræ Lobelij affinis.*
VI. *Gnaphalium montanum album.*

Of theſe ſix ſpecies, the firſt only, and perhaps the fifth, is exempted from cenſure, as containing both the generic

and ſpecific name: the reſt, when viewed apart, would ſeem to have no connection with the genus under which they are arranged; but, on the contrary, appear to belong to other genera, *chryſocome*, *helichryſum*, and *gnaphalium*, with which, in reality, they have no affinity.

Again, the generic name is not only to be applied, but to be prefixed to each ſpecies. The following ſpecific names of Lobelius are faulty in this reſpect.

Minus heliotropium *repens*

Matthioli ſecundum limonium.

Aquatica plantago *foliis betæ*.

X. Specific names are, if poſſible, to exhibit the eſſential difference of each ſpecies. Where the eſſential characters of any ſpecies have not been inveſtigated, other differences, leſs eſſential, but more numerous, are to be ſubſtituted in their place. Specific names of the latter kind are termed by Linnæus, ſynoptical, and are not to be admitted, unleſs in default of the eſſential name. The merits of each will beſt appear from compariſon.

Synoptic name—Salix *foliis ſerratis glabris ovatis acutis ſubſeſſilibus* of Royen.

Eſſential name—Salix *floſculis pendandris*, Lin. Flor. Lap.

Synoptic name—Salix *foliis ſubintegerrimis lanceolato-linearibus longiſſimis acutis, ſubtus ſericeis*; *ramis virgatis*. Flora Suecica.

Eſſential name—Salix *foliis linearibus revolutis*.

From theſe examples it appears that the eſſential name conſiſts of but two or three words, and is generally expreſſive of a ſingle idea. We have ſeen, however, that even eſſential ſpecific names, however excellent when compared with thoſe termed ſynoptic, muſt always be inconſtant, as long as a ſingle ſpecies of any genus remains undetected. Indeed, were that obſtacle removed, and every ſpecies characterized by an eſſential name, I ſhould moſt heartily concur with Linnæus, that the ſcience, at leaſt, in one point, had reached perfection; but till that diſtant day arrive, and a diſtant day it muſt be from the very nature of things, we muſt reſt ſatisfied with aſcribing to thoſe eſſential names, a degree of merit proportioned to their ſtability.

XI. The excellence of the ſpecific name, according to Linnæus, conſiſts in its brevity. In this reſpect chiefly, the eſſential name, as containing a ſingle idea, is preferable to the ſynoptical, in which the characters are numerous, but not ſtriking. After all, it may be doubted, whether the ample deſcriptions of former authors, however ſeverely cenſured by certain moderns, are not ſuperior, in point of merit, to the ſhort phraſes, or ſpecific differences, which are now ſo generally adopted; as theſe are not deſcriptive of any ſpecies conſidered by itſelf, but ariſe from a view of its reſemblances and contraſts with others.

I cloſe the ſubject of ſpecific names with obſerving, that the differences in queſtion are not always uniform; I mean, that the ſame idea does not predominate in the eſtabliſhment of the ſpecies of any genus, the characters being ſeldom relative, or drawn from the ſame parts: in fine, that a compariſon of oppoſition or contraſt, is rarely either inſtituted or implied. This fault we muſt pronounce a capital one; and every page of the *Species Plantarum* affords ſtriking evidences of its exiſtence. The following are examples of the impropriety alluded to.

I. LYTHRUM *foliis linearibus alternis, floribus hexandris.*
LYTHRUM *foliis linearibus alternis, floribus tetrapetalis.*
II. COTYLEDON *foliis laciniatis, floribus quadrifidis.*
COTYLEDON *foliis oblongis ſubteretibus, floribus faſciculatis.*
III. SEDUM *foliis quaternis.*
SEDUM *foliis planiuſculis ſerratis.*

The want of uniformity complained of will be beſt underſtood, by contraſting the above examples with a few ſpecific names of the ſame author, in which the oppoſition alluded to is carefully preſerved.

I. ROYENA *foliis lanceolatis glabris.*
ROYENA *foliis lanceolatis hirſutis.*
II. SCLERANTHUS *calycibus fructus patulis.*
SCLERANTHUS *calycibus fructus clauſis.*
III. LILIUM *foliis ſparſis, corollis campanulatis, intus glabris.*
LILIUM *foliis ſparſis, corollis campanulatis, intus ſcabris.*

A compariſon of theſe two oppoſite ſets of examples,

will convince the reader of the excellence of the uniformity recommended, and render any further illuſtration unneceſſary.

Names of the Varieties.

Varieties being only occaſional modifications of the ſame ſpecies, the circumſtance which conſtitutes the variety in any ſpecies is to be placed immediately after the ſpecific name. Such circumſtance, however, for the ſake of diſtinction, ſhould be delineated in a different character; in like manner as the ſpecific name ſhould ſtand diſtinguiſhed from the generic. A few examples will illuſtrate the obſervation in queſtion.

CONVALLARIA ſcapo nudo; *corolla plena.*
CONVALLARIA ſcapo nudo; *corolla rubra.*
SAXIFRAGA alpina ericoides; *flore purpuraſcente.*
SAXIFRAGA alpina ericoides; *flore cæruleo.*

In the above examples, the generic name is marked in ſmall capitals; the ſpecific in Roman characters; and the name of the variety in italics: a diſtinction which is abſolutely neceſſary, to prevent the variable circumſtance from being confounded with the ſpecific difference. The ſame ſpecies of lily of the valley has ſometimes a red, ſometimes a full flower. This occaſional difference does not enter into the ſpecific name; it is expreſſive of a variety, and ought to be diſtinguiſhed as ſuch.

NUCAMENTUM. *Vide* AMENTUM.

NUDUS *Flos*, a naked flower; a flower ſo termed by Vaillant which wants the *calyx*, or flower-cup, but not the petals. The term, perhaps, would have been more properly applied to a flower wanting both calyx and petals, which are properly the cloathing or covers of the flower. Inſtances, however, of entire nakedneſs in flowers are very rare.

NUX, a nut; a ſpecies of ſeed, according to Linnæus, covered by a hard bony ſhell. The incloſed ſeed is termed the *nucleus*, or kernel.

O.

OCTANDRIA, (ὀκτω, eight, and ἀνηρ, a man, or huſband) the eighth claſs in Linnæus's Sexual Syſtem; conſiſting of plants with hermaphrodite flowers, which are furniſhed with eight ſtamina, or male organs of generation.

The orders, or ſecondary diviſions of this claſs are four, and derive their names from the number of female organs poſſeſſed by the plants of each reſpective diviſion.

French-willow, Indian-creſs, heath, and tree-primroſe have one ſtyle, or female organ.

Galenia, *weinmannia*, and *moehringia*, have two ſtyles.

Biſtort and heart-ſeed have three ſtyles; tuberous moſchatel and one-berry, four.

OCULUS, an eye, a ſpecies of bud. *Vide* GEMMA.

ODOR, ſmell; the weakeſt and moſt obſcure of the ſenſes, as being different in almoſt every object, and variable in each. Dogs trace their maſters with ſurpriſing facility at one time, and loſe them with equal facility at another.

The ancients, according to Ariſtotle, recognized ſeven primitive or original ſmells, which, on account of their ſtriking affinity to the ſimple taſtes, were deſigned by the ſame names.

Smells being ſo extremely variable, admit of no determinate limits, and are, therefore, never to be employed in diſcriminating the ſpecies of plants. Hence ſuch ſpecific names as the following are very properly proſcribed from the modern nomenclature of botany.

Hypericum *hircinum* (rank-ſmelling).
Melo *moſchatus* (ſmelling of muſk).
Heſperis *noctu olens* (ſmelling in the night).
Caryophyllus *inodorus* (without ſmell).
Ocymum *caryophyllatum*, C. Bauhin, (ſmelling of cloves).
——— *citri* odore (ſmelling of citron).
——— *aniſi* odore (ſmelling of aniſe).
——— *fœniculi* odore (ſmelling of fennel).
——— *meliſſæ* odore (ſmelling of balm).
——— *rutæ* odore (ſmelling of rue).

Ocymum *cinnamomi* odore (ſmelling of cinnamon).

For obſervations on ſmell, as indicative of the virtues and qualities of plants, the reader is referred to the article of taſte, between which, and ſmell, there is, as we have ſaid, a remarkable affinity. *Vide* SAPOR.

OLIGANTHERÆ (ὀλιγος, few; and ἀνθηρος, *floridus*, ab ἀνθος, *flos*) the name of the ſixteenth claſs in Royen's Natural Method, conſiſting of plants with hermaphrodite flowers whoſe ſtamina are leſs in number than the diviſions of the *corolla*, or equal to them. It includes ſeveral genera of the plain claſſes in the Sexual Method.

ORCHIDEÆ (orchis, the name of a well-known genus of plants). The ſeventh order in Linnæus's Fragments of a Natural Method, conſiſting of orchis, and the plants which reſemble it in habit, powers, and ſenſible qualities.

Liſt of the Genera *contained in this Natural Order.*

Linnæan Genera.			*Engliſh Names.*
Arethuſa.			
Cypripedium,	—	—	Ladies ſlipper.
Epidendrum,	—	—	Vanilla, or vanelloe.
Limodorum.			
Ophrys,	—	—	Bee-flower, bird's-neſt, twy-blade.
Orchis.			
Satyrium,	—	—	Lizard-flower.
Serapias,	—	—	Helleborine, or baſtard-helle-bore.

Habit and Structure of the Plants of this Order.

The ROOTS of many of theſe plants are compoſed of one or more fleſhy tubercles, attached to the lower part of the ſtem, and ſending forth fibres from the top. Thoſe of orchis bear an obvious reſemblance to the ſcrotum in animals; from which circumſtance the genus has derived its name.

The LEAVES are of a moderate ſize, inſcribed with a number of longitudinal nerves or ribs, and without any foot-ſtalk. At their origin, they form, round the ſtalk, a kind

of

of ſheath, which is long, entire, cylindrical, but not furniſhed, like the graſſes, and ſome other plants, with a crown at top. This ſheath is ſometimes wanting in the leaves that are placed towards the top of the ſtalk. In ſome ſpecies of bird's-neſt, the leaves prove abortive; the ſheaths which ſurround the ſtalk appearing like ſo many ſcales.

The FLOWERS are hermaphrodite, and placed at the ſummit of the ſtalk, either in a ſpike, as in ladies ſlipper, bee-flower, orchis, ſatyrium, *limodorum* and *arethuſa*; or in a panicle, that is, a looſe, diffuſed ſpike, as in vanelloe. Each flower is accompanied with a leaf that is ſmaller than the other leaves, and forms no ſort of ſheath round the ſtalk.

The CALYX in this order is that ſort termed by Linnæus a *ſpatha* or ſheath, that, burſting open, protrudes a head or cluſter of flowers termed the *ſpadix*, which have no *perianthium*, or proper flower-cup.

The PETALS are five in number, and very irregular. The two innermoſt frequently approach and form the figure of a helmet. The three outermoſt are larger, and nearly equal.

The NECTARIUM in this order is remarkably conſpicuous, yet ſo different in the different genera, that Linnæus has employed it for his principal character or mark of diſtinction, inſtead of the root, which had chiefly engaged the attention of former botaniſts. It has the appearance of a ſixth petal, and conſtitutes the lower lip of the helmet. In ſome ſpecies of *ophrys* it is ſhaped like a bee; whence the Engliſh title of bee-flower, which has been given to that genus. In *limodorum* it conſiſts of one piece, which is hollow, of the length of the petals, and placed within them. In *cypripedium* the appearance in queſtion is ſituated between the petals, and reſembles a wooden ſhoe or ſlipper; from which circumſtance it has derived both its ſcientific and Engliſh name. In orchis and ſatyrium, the *nectarium* conſiſts of two lips; the upper erect and very ſhort, the lower larger, hanging, and terminated behind by a tube, which, in the former, reſembles a horn, in the latter, the *ſcrotum* in animals. In *arethuſa* it is placed in the bottom of the flower, and conſiſts

of one piece that is divided into two lips; the lowermoſt of which is broad, wrinkled within, turned backwards, hangs down, and is of the length of the petals; the upper ſlender, like a line of elegant texture, and incorporated with the ſtyle. In vanelloe, it is ſhaped like a top, and placed at the back of the petals. Laſtly, in helleborine, it is placed in the middle of the flower, and in moſt of the ſpecies reſembles the embowelled body of a fly.

The FILAMENTS, or lower part of the ſtamina, are always two in number, very ſhort, and placed upon the *piſtillum*, or female organ; from which ſingular circumſtance, the plants in queſtion are arranged under the claſs *Gynandria* in the Sexual Method. *Vide* GYNANDRIA.

The ANTHERS or ſummits are erect, and generally covered by the upper lip of the *nectarium*.

The SEED-BUD is either oblong or pillar-ſhaped, twiſted like a ſcrew, and univerſally placed below the receptacle of the flower.

The STYLE is ſingle, very ſhort, and forms one ſubſtance with the inner margin of the *nectarium*, ſo that both ſtyle and ſtigma are with difficulty to be perceived. This laſt is commonly filled with a viſcous ſweet ſubſtance like honey.

The SEED-VESSEL is generally a capſule with one cavity and three valves or openings, which are commonly keel-ſhaped, and open on the angular ſides, being joined both at bottom and top. In vanelloe, the ſeed-veſſel is a long, cylindrical, unctuous, fleſhy pod. What chiefly diſtinguiſhes it from the capſular fruit of the other genera is, its wanting the keel-ſhaped ribs or valves, ſo conſpicuous in the other plants of this order.

The ſeeds are numerous, very ſmall like ſaw-duſt, and attached, without foot-ſtalks, to a ſlender receptacle, or rib, which extends itſelf length-wiſe in the middle of each incloſure. In vanelloe, they are almoſt round, ſhining, and of a black colour. In the other genera, they are rather flat, of a yellow colour, and fringed on the border with a longitudinal membrane, or wing.

The

The plants of this order are celebrated as mighty provocatives to venery. This reſtorative quality, which is chiefly poſſeſſed by the roots, is moſt predominant in the vanelloe of the Americans, the ſalep of the Eaſtern countries, and the orchis and ſatyrium of the Europeans. The tubercles of the roots have an acrid quality, which is deſtroyed by drying, or moiſtening them in warm water.

Vanelloes are the pods of a twining paraſitic genus of plants, which grow plentifully on trees, both in the Eaſt and Weſt Indies. Theſe pods reſemble our kidney beans, being about half a foot long, and containing a number of very ſmall ſeeds. When ripe and dry, the inhabitants of Mexico and St. Domingo, whence theſe pods are imported into Europe in greateſt abundance, gather them, and, having rubbed them with oil, leſt they ſhould harden and break, form them into bundles, or bags of different ſizes, containing, ſome fifty, ſome a hundred, ſome a hundred and fifty pods. The Indians call the plant tlilxochitl, and the pod maxacochitl. Hernandez ſays, it is uſeful in ſuppreſſions, warms and fortifies the ſtomach, facilitates digeſtion, and diſſipates wind. Vanelloe has a very agreeable taſte and ſmell. It is eſteemed an excellent cordial, and enters into the compoſition of chocolate, which, indeed, is its principal uſe with us. A black fragrant balſam is procured from the ſame pods; but this is very rarely brought to Europe. The name vanilla, ſignifying a ſheath, was given to this plant by the Spaniards, from the figure of its pods.

The flowers of the different ſpecies of orchis and *ophrys* are remarkably various and ſingular in their ſhape; reſembling ſometimes a naked boy, ſometimes a gnat, a butterfly, a bee, a pigeon, an ape, a parrot, a lizard, or a fly. Theſe reſemblances have given names to the ſpecies in queſtion. The beard or *nectarium* of the bee-flower, is a large fat leaf, beautifully repreſenting a drone or bee of a ſooty colour, and which, when turned to the light, ſeems variegated with three bright yellow circular lines, with ruſt-coloured ſpaces between them. The *nectarium* of humble-bee ſatyrion,

rion, the *teſticulus ſphegodes hirſuto flore* of Ray, is remarkable for two upright lines, of a livid colour, and a tranſverſe one of the ſame colour, repreſenting a capital H. The flowers of many of the orchis-tribe are beautifully ſpotted.

ORDO, an order; the firſt ſubdiviſion of a claſs in the Sexual Method, correſponding to the term *ſectio*, in Tournefort. Such a diviſion, by parcelling out the genera of any claſs into ſeveral diſtinct lots, gives perſpicuity to the method, and facility to its diſtinctions.

The orders in Tournefort's Syſtem are chiefly founded upon the fruit: thoſe of the Sexual Method, on the number of ſtyles or female organs. A particular enumeration of the latter is ſubjoined to their reſpective claſſes, whither the reader is referred for information on this ſubject.

I would at preſent, only remark one circumſtance in which Linnæus's orders are preferable to thoſe of Tournefort. The latter botaniſt expreſſes this ſubdiviſion by a circumlocution, which commonly includes a repetition of the abridged clavis of his Syſtem. On the other hand, Linnæus's orders are always expreſſed by a ſingle term, which, like the names of the claſſes, is of Greek etymology, and is ſignificative of the character of the order to which it is applied. It is needleſs to ſubjoin, that the names of theſe orders are often the ſame in different claſſes, becauſe the ſame idea predominates in their inſtitution. If the ſame character could, in like manner, be employed for diſtinguiſhing all the orders of each claſs, the ſyſtem would, in that point, at leaſt, have attained perfection. The claſſes in the Sexual Syſtem are much more uniform than the orders. The latter, therefore, as ſcientific diviſions, are greatly inferior to the former.

ORDO, a term of Tournefort, correſponding to the *claſſis* or higheſt diviſion of Linnæus. *Vide* CLASSIS.

ORGYA, a term of Meaſure. *Vide* MENSURA.

OVARIUM (*ovum*, an egg) the ovary; a name, by which botaniſts, who are fond of aſſimilating the animal and vegetable kingdoms, have diſtinguiſhed the *germen* or ſeed-bud, as containing the rudiments of the future ſeed.

P.

PALATUM *corollæ*, the palate of the flower; by this name Linnæus characterizes any prominence or gibboſity in the jaws *(faux)* of the *corolla*.

PALEÆ, thin, membranaceous, chaffy plates ſpringing out of a common receptacle, and intended as lines of partition between the ſmall partial florets of compound and aggregate flowers.

PALEACEUS *flos*, a term of Ray, expreſſive of ſuch flowers as produce no fruit. It correſponds to the *maſculus flos* of Linnæus, the *ſterilis* of Tournefort, the *abortiens* of other botaniſts.

PALMÆ, palms. Under this name Linnæus has arranged ſeveral genera, which, although capable of a place in ſeparate claſſes of his ſyſtem, he has choſen rather, on account of their ſingular ſtructure, to place apart, in an appendix to the work.

The ſame plants conſtitute one of the ſeven families or tribes into which all vegetables are diſtributed by Linnæus in his *Philoſophia Botanica*. They are defined to be plants with ſimple ſtems, which, at their ſummit, bear leaves reſembling thoſe of the ferns, being a compoſition of a leaf and a branch; and whoſe flowers and fruit are produced on that particular receptacle, or ſeat, called a *ſpadix*, protruded from a common calyx, in form of a ſheath or ſcabbard, termed by Linnæus, *ſpatha*.

It is to be obſerved, however, that the terms *ſpatha* and *ſpadix*, though originally applied by Theophraſtus to palms only, are uſed with much greater latitude by modern botaniſts, and applied to narciſſus, ſnow-drop, orchis, ſatyrium, arum, dracontium, calla, pothos, ſea-daffodil, and many other plants, whoſe flower-ſtalks come out of a ſheath.

PALMÆ is likewiſe the name of the firſt order in Linnæus's Fragments of a Natural Method, conſiſting of the following genera, the three laſt of which, although not ranged with the palms in the appendix to his Artificial Syſtem, are placed

placed with them, on account of their alleged conformity in point of habit, in his Natural Method.

	Linnæan Genera.			*Engliſh Names.*
α	*Areca*,	—	—	The faufel-nut.
	Boraſſus,	—	—	Malabar-palm, called ampana and carim-pana.
	Caryota,	—	—	Palm with doubly-winged leaves, called ſchunda-pana.
	Chamærops,	—	—	Leſſer, or dwarf-palm, palmetto, thatch.
	Cocos,	—	—	Cocoa nut tree.
	Corypha,	—	—	Mountain-palm with largeſt leaves, called codda-pana.
	Cycas,	—	—	Todda-pana.
	Elais.			
	Elate,	—	—	Wild Malabar-palm, called Katou-Indel.
	Phœnix,	—	—	Date-tree.
	Zamia.			
β	*Hydrocharis*,	—	—	Frog's-bit.
	Stratiotes,	—	—	Water-ſoldier.
	Valliſneria.			

Habit and Structure of the Plants of this Order.

The plants of this order are perennial, and moſtly of the ſhrub and tree kind. The ſtem is in height, from two to a hundred feet and upwards.

The ROOTS form a maſs of fibres, which are commonly ſimple, that is, without any ramifications. In frog's-bit, the roots are terminated by a ſmall cup, of a conic form, which covers them like an extinguiſher, as in duck's-meat.

The STEM is generally ſimple, cylindrical, and compoſed of ſtrong longitudinal fibres.

The LEAVES, which are a compoſition of a leaf and a branch, termed by Linnæus *frondes*, are of different forms; being

being ſometimes ſhaped like an umbrella or fan; ſometimes ſingly or doubly-winged; the ſmall or partial leaves, which are often three feet in length, being ranged alternately. The branches or principal leaves are ſix, eight, ten and twelve feet long; the length varying according to the age and ſize of the plant.

They are covered at firſt with a brown thick duſt, like thoſe of the ferns. The baſe of the leaves frequently embraces the greater part of the ſtem. Schunda-pana is the only genus of this order yet known, which bears doubly-winged leaves.

The FLOWERS are male and female upon the ſame or different roots, except in water-ſoldier, which bears hermaphrodite flowers only, and palmetto, in which the flowers are hermaphrodite and male upon diſtinct roots. In *valliſneria* and frog's-bit too, the flowers are not ſo properly male and female upon different roots, as barren hermaphrodites; a ſmall ſeed-bud being diſcovered in thoſe called the male flowers, and the remains of ſtamina in the female. Abortive flowers of the ſame kind are frequently obſerved in *valliſneria* upon the ſame root.

The flowers are all diſpoſed in a panicle or diffuſed ſpike, except in the three laſt genera, in which they proceed ſingly from the angles of the leaves. In todda-pana, ſays M. Adanſon, the flowers grow upon the indentments of the leaves, whoſe diviſions form a kind of panicle.

The COMMON CALYX in this order is that ſort termed a *ſpatha* or ſheath, and has either one valve or opening, as in date tree, and cocoa-nut; or two, as in faufel-nut, and wild Malabar-palm. The *ſpadix*, or head of flowers protruded from the ſheath, is generally branched. Each flower is commonly furniſhed with a *perianthium*, or proper flower-cup, conſiſting of three leaves or diviſions that are ſmall and permanent.

The PETALS are three in number, of a ſubſtance like leather, and permanent like the leaves of the calyx. The flowers of *zamia* have no petals.

The STAMINA are in number from two to twenty and upwards,

wards, and cohere ſlightly at the baſe. In frog's-bit they appear like a pillar in the centre of the flower.

The SEED-BUDS are from one to three in number, placed in the middle of the flower, and ſupport a like number of ſtyles, which are very ſhort. In frog's-bit, *vallisneria*, and water-ſoldier, the ſeed-bud is placed under the receptacle of the flower.

The SEED VESSEL is generally a pulpy fruit of the berry or cherry kind, containing one cell filled with fibrous fleſh, and covered with a ſkin, which is of a ſubſtance like leather.

The SEEDS are in number from one to three in each pulpy fruit, of a hard bony ſubſtance, round or oval, and attached by their baſe to the bottom of the fruit.

Theſe plants, particularly the ſeeds, are aſtringent, and of efficacy in dyſenteries.

The date-tree, the *phœnix dactylifera* of Linnæus, is a native of Africa, and the eaſtern countries, where it grows to fifty, ſixty, and one hundred feet high. The trunk is round, upright, and ſtudded with protuberances, which are the veſtiges of the decayed leaves. From the top iſſues forth a cluſter of leaves or branches, eight or nine feet long, extending all round like an umbrella, and bending a little towards the earth. The bottom part produces a number of ſtalks like thoſe of the middle, but ſeldom ſhooting ſo high as four or five feet. Theſe ſtalks, ſays Adanſon, diffuſe the tree very conſiderably; ſo that, wherever it naturally grows in foreſts, it is extremely difficult to open a paſſage through its prickly leaves. The flowers are male and female upon different roots. The dates, which are the produce of the female plant, grow in large ſpiral cluſters, each being about the bigneſs and ſhape of a middling olive, and containing within the pulp, which is of a yellow colour, and agreeable taſte, a round, ſtrong, hard nut or ſtone, of an aſh-colour, marked with a deep furrow running lengthwiſe. Of the freſh dates and ſugar, ſays Haſſelquiſt, the Egyptians make a conſerve, which has a very pleaſant taſte. The kernels or ſtones, though hard as horn, they grind on hand-

hand-mills, and in default of better food, give to their camels. Of the leaves are made baſkets, or bags, which are much uſed in Turkey on journies, and for other œconomical uſes. In Egypt they are uſed as fly-flaps, for driving away the numerous inſects, which prove ſo troubleſome in hot countries; and Rauwolff relates, that of the fibres of the leaves, and covering of the fruit, are ſpun ropes, of pretty large dimenſions and conſiderable ſtrength. The hard boughs are uſed for fences, and other purpoſes of huſbandry; the principal ſtem for building; in fine, no part of this curious tree wants its uſe. The fruit, before it is ripe, is ſomewhat aſtringent, but when thoroughly mature, is of the nature of the fig. The Senegal dates are ſhorter than thoſe of Egypt, but much thicker in the pulp, which is ſaid to have a ſugary agreeable taſte, ſuperior to that of the beſt dates of the Levant.

Palmetto, that is, little palm, called, by the Americans, thatch, from the uſe to which the leaves are applied, is a native of Africa and the Weſt-Indies, and ſeldom grows ſo high as the other palms. M. Adanſon, however, deſcribes, under the name of palmetto, a ſpecies of palm, which grows naturally at Senegal, whoſe trunk riſes from fifty to ſixty feet in height. The negroes call this palm, ronn, which name the French have changed to *rondier*. From the upper end of the trunk iſſues a bundle of leaves, which, in turning off, form a round head; each leaf repreſents a fan of five or ſix feet in expanſion, ſupported by a tail of the ſame length. Of theſe trees, ſome produce male flowers, which are conſequently barren; others are female, and loaded with fruit, which ſucceed each other uninterruptedly almoſt the whole year round. The fruit of the large palmettos, M. Adanſon affirms to be of the bigneſs of an ordinary melon, but rounder; it is enveloped in two ſkins as tough as leather, and thick as ſtrong parchment; within, the fruit is yellowiſh, and full of filaments, faſtened to three large kernels in the middle. The negroes are very fond of this fruit, which, when baked under the aſhes, is ſaid to taſte like a quince.

The

The fruit of the *areca*, or faufel nut, reſembles a nutmeg in texture, and, when ripe, is inſipid and aſtringent. Its inſpiſſated juice is ſuppoſed to be the cachou, or, as it is improperly termed, Japan-earth of the ſhops.

Palm-oil tree, or oily palm, is a native of Africa, and riſes about fifty feet high; from the fruit is drawn an oil, of which the negroes are remarkably fond. They generally roaſt the fruit in the embers, and then ſuck the fine ſweet oil, which is contained in the many interſtices of its yellow huſky tegument. With this oil they likewiſe anoint their bodies, to prevent a too plentiful perſpiration, as well as to ſupple and relax their ſtiffened nerves. Being thus anointed, their ſkins appear ſleek and ſhining. Within the outward covering is the nut, which contains a white kernel, in taſte ſomewhat reſembling that of the cocoa-nut, but not ſo agreeable. Theſe nuts, when bored and emptied of their kernels, are ſtrung by the negroes, as ornaments about their necks. From the body of this and the cocoa-nut tree is extracted a liquor, which, when fermented, has an intoxicating quality, and is known by the name of palm wine.

The cocoa-nut tree is ſuppoſed to be a native of the Maldive Iſlands, but is cultivated in both Indies, particularly in South America, and the Weſt India Iſlands, where it ſupplies the inhabitants with many of the common neceſſaries of life. This tree frequently riſes ſixty feet high. The body of the trunk, which generally leans to one ſide, occaſioned, as is ſuppoſed, by the great weight of nuts which it ſuſtains when young, is the exact ſhape of an apothecary's large iron peſtle, being of an equal thickneſs at top and bottom, but ſomewhat ſmaller in the middle; its colour is of a pale brown throughout, and the bark ſmooth. The leaves, or branches, often fifteen feet long, are about twenty-eight in number, winged, of a yellow colour, ſtraight and tapering. The pinnæ, or partial leaves, are green, often three feet long next the trunk, but diminiſhing in length toward the extremity of the branches. The branches are faſtened at bottom by brown ſtringy threads, about the ſize of ordinary packthread, that grow out of them, and are interwoven like a web. The nuts hang at the top of the trunk, in cluſters,

of

of a dozen each. Each nut, next the ſtem, has three holes cloſely ſtopped; one of them being wider and more eaſily penetrated than the reſt. When the kernel begins to grow, it incruſts the inſide of the nut in a bluiſh jelly-like ſubſtance. As this grows harder, the incloſed liquid, diſtilled into the nut from the roots, becomes ſomewhat acid; and the kernel itſelf, as the nut ripens, becomes ſtill more ſolid; and, at length, lines the whole inſide of the nut for above a quarter of an inch thick, being as white as ſnow, and of the flavour of an almond. The quantity of liquor in a full grown nut is frequently a pint and upwards. The huſky tegument of the nut conſiſts of ſtrong, tough, ſtringy filaments, which, when removed from the fruit, reſemble coarſe oakum; and might, perhaps, be conveniently enough uſed as ſuch. The ſhells of theſe nuts being tipped with ſilver, are frequently uſed for drinking-bowls; the bark of the tree may be wrought into cordage, and the leaves into baſkets, brooms, hammocks in form of nets, mats, ſacks, and other uſeful utenſils. The liquor contained in the ſhell is a moſt cooling wholeſome beverage in thoſe ſultry climates, and the white kernel a moſt agreeable food.

In the Eaſt Indies, during the prodigious rains and tempeſtuous ſeas on the coaſt of Malabar, which generally continue from the end of May till the beginning of September, the Banian Indians endeavour to appeaſe the incenſed ocean, by offering a number of gilded cocoa-nuts to its enraged waves; an anniverſary ceremony of which the young Indians are remarkably fond, as it gives them an opportunity of ſhewing their dexterity in ſwimming, to recover the nuts which have been thrown into the ſea. The cocoa-nut of the Maldive iſlands is eſteemed by the inhabitants a very powerful antidote againſt the bites of ſerpents, and other poiſons.

The cabbage-tree, or mountain palm, the *palma altiſſima non ſpinoſa* of Sloane, is a native of the Weſt Indies, where it is ſaid to riſe to the height of one hundred and fifty, and two hundred feet. It is, by ſome authors, called the palmetto royal; and well, ſays Hughes, in his Natural Hiſtory

of Barbadoes, may it be called royal, ſince neither the taſl cedars of Lebanon, nor any of the trees of the foreſt are equal to it in height, beauty, or proportion. It is generally as ſtraight as an arrow: near the earth it is about ſeven feet in circumference, but tapers as it aſcends. The bark is of an aſh colour till within twenty-five or thirty feet of the extremity of the tree, when it alters at once to a deep ſea-green, which continues to the top. Upon removing the large leaves or branches which ſurround the top of the trunk, a little way above the beginning of the green bark juſt mentioned, what is called the cabbage is diſcovered lying in many thin, ſnow-white, brittle flakes, in taſte reſembling an almond, but ſweeter. This ſubſtance, which cannot be procured without deſtroying the tree, is boiled, and eaten with mutton, by the inhabitants of the Weſt-Indies, in the ſame manner as turnips and cabbage are with us; it is likewiſe pickled, and ſent to Europe, where it is eſteemed an exquiſite delicacy.

In the pith of the trunk of the cabbage-palms, when felled, there breeds a kind of worms or grubs which are eaten, and eſteemed a great delicacy by the inhabitants of Martinico, and of the other French Weſt-India iſlands. Theſe worms, ſays Father Labat, are about two inches long, and of the thickneſs of one's finger; the head is black, and attached to the body without any diſtinction of neck. Their preparation for the table is as follows: they are ſtrung on wooden ſkewers before a fire, and, as ſoon as heated, are rubbed over with raſpings of cruſt, ſalt, pepper, and nutmeg; this powder abſorbs all the fat, which, during the cookery, would otherwiſe eſcape; when properly roaſted they are ſerved up with orange, or citron ſauce. Theſe worms being expoſed for ſome time to the ſun are ſaid to yield an oil which is of great efficacy in the piles. The oil in queſtion, ſays Labat, is never to be heated before its application to the part affected; as repeated experiments have evinced that its ſpirit is totally diſſipated by the fire.

From the pith of a ſpecies of palm that grows naturally in Japan, is prepared the ſubſtance, well known in the ſhops by

by the name of ſago. The pith is taken out, and, after being pounded in large mortars, is mixed with water. The liquor is then ſtrained, and the fæculæ formed into cakes, which the Japaneſe eat as bread, in default of rice: part of the ſame ſubſtance they granulate and dry, and ſend into Europe by the name of ſago; it is eſteemed highly nouriſhing and reſtorative.

From the dragon-tree, a palm which grows naturally in the Cape-Verd Iſlands, and has leaves like thoſe of the yucca or Adam's needle, flows by inciſion, a red gummy juice, commonly known by the name of dragon's blood, and reckoned vulnerary and aſtringent.

A ſpecies of water-ſoldier, or marſh-aloe, is the ſurpriſing plant which is ſaid to move in the waters of the Nile, ſeeking for nutrition in the ſame manner as animals. The fact is, that the plant produces tufts of leaves, at a very great diſtance from one another, and ſupported by a ſtem, which, after floating on the water, loſes itſelf inſenſibly in the earth, in much the ſame manner as the potamogetons, the menyanthes, and even the leaves of the water-lily.

PANICULA, (diminutive from *panus*—Feſtus; the woof wound on the quill in the ſhuttle) a mode of flowering, in which, according to Linnæus, the fructifications are diſperſed upon footſtalks variouſly ſubdivided. It is, in fact, a ſort of branching or diffuſed ſpike, compoſed of a number of ſmall ſpikes that are attached along a common footſtalk. The term is exemplified in oats, panic-graſs, and many other plants.

When the partial foot-ſtalks diverge, and the fructifications hang looſe, the panicle is properly ſaid to be diffuſe, *(panicula diffuſa)* as in *poa aquatica*, and *alpina:* when the foot-ſtalks approach, the panicle becomes ſtraight and narrow, *(panicula coarctata)* as in *feſtuca ovina* and *aira cærulea.*

PAPILIONACEUS *flos*, *(papilio*, a butterfly) a butterfly ſhaped flower. *Vide* COROLLA.

PAPILIONACEI, the name of two claſſes in Tournefort's and Pontedera's methods, conſiſting of herbs and trees with butterfly-ſhaped flowers. Theſe plants, which are the legu-

minoſæ of Ray, and form a true natural aſſemblage, conſtitute the thirty-ſecond order in Linnæus's Fragments of a Natural Method under the ſame title, which indeed is expreſſive of their moſt ſtriking character.

Liſt of the Genera *contained in this Natural Order.*

SECTION I.

Butterfly-ſhaped Flowers, having the Filaments of the Stamina diſtinct.

Linnæan Genera.			*Engliſh Names.*
Anagyris,	—	—	Stinking bean trefoil.
Sophora.			

SECTION II.

Butterfly-ſhaped Flowers with One Set of united Filaments.

Abrus,	—	—	Wild liquorice.
Amorpha,	—	—	Baſtard Indigo.
Anthyllis,	—	—	Kidney-vetch, or ladies finger.
Arachis,	—	—	Earth or ground-nut.
Aſpalathus,	—	—	African broom.
Borbonia.			
Crotalaria,	—	—	Rattle-wort.
Ebenus,	—	—	Ebony of Crete.
Erythrina,	—	—	Coral tree.
Geniſta,	—	—	Single-ſeeded broom, Dyer's broom.
Lupinus,	—	—	Lupine.
Niſſolia.			
Ononis,	—	—	Anonis, or reſt-harrow.
Piſcidia,	—	—	Dog-wood tree.
Pterocarpus.			
Spartium,	—	—	Broom.
Ulex,	—	—	Furze, whins.

SECTION

SECTION III.

Butterfly-ſhaped Flowers with two Sets of united Filaments.

Aeſchynomene, — — Baſtard-ſenſitive-plant.
Aſtragalus, — — Liquorice vetch, or milk vetch, goat's-thorn.
Biſerrula.
Cicer, — — Chich pea.
Clitoria.
Colutea, — — Bladder-ſenna.
Coronilla, — — Jointed-podded colutea.
Cytiſus, — — Laburnum, baſe tree-trefoil.
Dolichos.
Ervum, — — Lentil.
Galega, — — Goat's-rue.
Geoffraea.
Glycine, — — Carolina kidney-bean tree.
Glycyrrhiza, — — Liquorice.
Hedyſarum, — — French honey-ſuckle.
Hippocrepis, — — Horſe-ſhoe vetch.
Indigofera, — — Indigo.
Lathyrus, — — Chichling vetch, everlaſting pea.
Lotus, — — Bird's-foot trefoil.
Medicago, — — Medic, ſnail and moon-trefoil, Lucern.
Ornithopus, — — Bird's-foot.
Orobus, — — Bitter vetch.
Phaca, — — Baſtard milk-vetch.
Phaſeolus, — — Kidney-bean, or French-bean.
Piſum, — — Pea.
Pſoralea.
Robinia, — — Falſe acacia.
Scorpiurus, — — Caterpillars.
Trifolium, — — Trefoil.
Trigonella, — — Fenugreek.
Vicia, — — Vetch, bean.

Habit and Structure of the Plants of this Order.

Theſe plants, otherwiſe called leguminous, from the ſeed-veſſel, which is that ſort termed a *legumen*, are very different both in ſize and duration; ſome of them being herbaceous, and thoſe either annual or perennial; others, woody vegetables of the ſhrub and tree kind, a few of which riſe to the height of ſeventy feet, and upwards. The herbaceous plants of this order generally climb, for being weak, and, as it were, helpleſs of themſelves, indulgent Nature has either provided them with tendrils, and even ſharp-pointed hooks at their extremities, to faſten upon the neighbouring trees or rocks, or endued the ſtalks with a faculty of twiſting themſelves, for the purpoſe of ſupport, around the bodies in their neighbourhood.

The pea, vetch, and kidney-bean, afford familiar examples of the appearances in queſtion. The ſhrubs and trees of this natural family are moſtly armed with ſtrong ſpines.

The ROOTS are very long, and furniſhed with fibres: ſome genera have fleſhy tubercles, placed at proper intervals along the fibres.

The STEMS are cylindric, as are likewiſe the young branches, which are placed alternately: thoſe which climb twiſt themſelves from right to left, in a direction oppoſite to the apparent diurnal motion of the ſun.

The bark of the large trees is extremely thick, and wrinkled, ſo as to reſemble a net with long meſhes; the wood is very hard in the middle, and commonly coloured, or veined; the alburnum is leſs hard, and generally of a yellow colour.

The BUDS are hemiſpherical, without ſcales, and proceed from the branches horizontally, a little above the angle which they form with the leaves.

The LEAVES are alternate, and of different forms, being either ſimple, finger-ſhaped, or winged. This laſt form is very common. The lobes or leſſer leaves are entire, and ſometimes placed in pairs, as in wild liquorice, vetch, lathyrus, and ground nut; but moſt commonly, the winged-leaf

is terminated by an odd lobe; as in colutea, liquorice, goat's rue, fenugreek, ladies finger, medicago, aſtragalus, indigo, and coronilla. The winged or pinnated leaves of this order have a daily or periodical motion depending upon the progreſs of the ſun in his diurnal courſe. See the article Motus, where the motion alluded to is particularly explained.

The common foot-ſtalk of the winged and other compound leaves is marked on the upper ſurface with a cavity, or furrow, which runs through its whole length. In the vetch, lathyrus, and ſome others, the foot-ſtalk is terminated by a pretty long branching tendril, inſtead of the odd lobe, which in theſe plants is wanting; although, from the alternate diſpoſition of the leſſer leaves along the foot-ſtalk, an abrupt termination does not appear natural.

Aphaca, a ſpecies of lathyrus, has no leaves; that want being ſupplied by a ſimple tendril, which proceeds at each joint from the ſtem, betwixt two large *ſtipulæ* that are oppoſite, and united, ſo as to form the appearance of a ſingle leaf penetrated by the ſtalk. The ſurface of the leaves of ſome ſpecies of pſoralea is covered with pellucid glandular knobs, which, when held up to the light, appear like ſo many minute points, or holes: the calyx is ſtudded in like manner.

The Flowers are hermaphrodite, and proceed either from the wings of the leaves, as in furze, goat's-rue, liquorice, lupine, colutea, kidney-bean, goat's thorn, a ſpecies of aſtragalus, *biſerrula*, medicago, and glycine; or from the extremity of the branches, as in ebony of Crete, falſe acacia, trefoil, lotus, African broom, *crotalaria*, and coral-tree. In a ſpecies of goat's rue of Senegal, mentioned by M. Adanſon, the ſpike of flowers proceeds not from the angle of the leaves, but from the oppoſite ſide of the branches, as in the rough-leaved plants.

The Calyx is a *perianthium* of one leaf, bell-ſhaped, bunching out at the bottom, and cut on its brim or margin into five irregular diviſions, or teeth, the lowermoſt of which, being the odd one, is longer than the reſt: the other four ſtand in pairs, of which the uppermoſt is ſhorteſt, and

ſtands fartheſt aſunder. The bottom of the calyx is moiſtened with a ſweet liquor like honey, ſo may be deemed the *nectarium* of theſe plants.

Some ſpecies of kidney-bean have a ſecond calyx without the other, that is round, and conſiſts of two leaves.

The PETALS are four or five in number, very irregular, and from their figure and poſition, bear an obvious reſemblance, in moſt of the genera, to a butterfly expanding its wings for flight. Theſe petals have been characterized by diſtinct names: the upper one, which is commonly the largeſt, is termed the ſtandard, (*vexillum*); the two ſide petals, the wings, (*alæ*); and the lowermoſt, which is generally united at top, and divided at bottom, the keel, (*carina*). *Vide* COROLLA.

In baſtard indigo, the flower is furniſhed with the upper petal, or ſtandard, only; a circumſtance which eſſentially diſtinguiſhes the genus in queſtion. In kidney-bean, the keel, involving the parts of generation, is ſpirally twiſted, in a direction oppoſite to the ſun; by which character this genus is diſtinguiſhed from dolichos, to which it is otherwiſe very nearly allied. In Ethiopian bladder-ſenna, the ſtandard is ſhorter than the keel; the wings much ſhorter than the ſtandard. Some ſpecies of trefoil have only one petal, the ſtandard, wings, and keel, being conjoined. In fenugreek, the keel is very ſmall, and the ſtandard and wings are ſo ſituated, as to form the appearance of a regular flower with three petals; whence the name *trigonella*, that is, three-cornered flower, which has been given to this genus. Ebony of Crete has no wings to its flowers. In coral-tree, both wings and keel are very ſhort, ſo that the butterfly-ſhape is not very conſpicuous in the flowers.

The flowers fall off very early in moſt of theſe plants, except in the trefoils with one petal, and ſome ſpecies of ladies finger, in which they are permanent. That they may ſometimes, though very rarely, be rendered double by culture, ruſhy, or Spaniſh broom, the *ſpartium junceum* of Linnæus, is ſufficient evidence.

The STAMINA are generally ten in number. Theſe

are

are either totally diſtinct, as in plants of the firſt ſection, or united by the filaments into one or two bundles involving the ſeed-bud, as in thoſe of the ſecond and third. In the latter caſe, where there are two ſets of united filaments, one of the ſets is compoſed of nine ſtamina, which are united into a crooked cylinder that is cleft on one ſide through its whole length. Along this cleft lies the tenth filament, or ſtamen, which conſtitutes the ſecond ſet, and is often ſo cloſely attached to the large bundle, that it cannot be ſeparated without ſome difficulty.

Upon the union of the ſtamina juſt mentioned is founded the ſyſtematic or artificial character of the claſs *Diadelphia* in the Sexual Method: to which claſs, all the plants of this order, except thoſe of the firſt ſection, are referred. Yet with what propriety can the plants of the ſecond ſection, which confeſſedly have but one ſet of united filaments, or, at leaſt, whoſe filaments are all connected at the baſe, be arranged under a claſs whoſe characteriſtic, as expreſſed in the title, is to have two diſtinct ſets, or *brotherhoods*, (ſo the term imports) of ſtamina ſo united? Their ſtructure would much more naturally determine them to a place in the immediately preceding claſs, *Monadelphia*, which, indeed, is expreſſive of the very circumſtance in their ſtructure alluded to. The plants even of the third ſection, though they come nearer to the deſcription expreſſed in the title, are very rarely to be diſcovered, or diſtinguiſhed by that circumſtance. In ſhort, the more accurately we examine the ſtructure of the butterfly-ſhaped flowers, the more reaſon ſhall we find to be diſſatisfied with the arbitrary manner in which Linnæus has arranged them, and to prefer the more natural and eaſy arrangements from the figure of the flower, and ſtructure of the fruit.

The anthers are ſmall, round, marked with four longitudinal furrows, and ſlightly attached to the filaments. In lupine, the *anthers* are alternately round and oblong.

The SEED-BUD is ſingle, placed upon the receptacle of the flower, oblong, cylindrical, ſlightly compreſſed, of the length of the cylinder of the united ſtamina by which it is involved;

involved; and ſometimes, as in coral-tree, elevated by a ſlender foot-ſtalk, which iſſues from the centre of the calyx.

The STYLE is ſingle, ſlender, and generally crooked. In pea, the ſtyle is hairy, three-cornered, and keel-ſhaped above; by which laſt circumſtance chiefly, that genus is diſtinguiſhed from lathyrus, in which the ſtyle is plain.

The STIGMA, or ſummit of the ſtyle, is generally covered with a beautiful down, and placed immediately under the *anthers*, or tops of the ſtamina.

The SEED-VESSEL in this order, is that ſort of pod, termed a *legumen*, which is of an oblong figure, more or leſs compreſt, with two valves, and one, two, or more cavities; theſe cavities are often ſeparated, when ripe, by a ſort of joints, which are conſpicuous in the pods of coronilla, French honey-ſuckle, horſe-ſhoe vetch, bird's foot, baſtard-ſenſitive-plant, and ſcorpiurus: in the latter, the pods rarely open of themſelves; but as they are more eaſily ſeparated croſs-wiſe by the joints than length-wiſe by the ſutures, it would ſeem that they have been naturally deſtined to ſplit in that manner. In *pterocarpus* the pod is compreſſed, of a leafy ſubſtance, marked with veins on the ſides, and woody within; in lupine, and ground-nut, it is of a ſubſtance like leather; in ladies finger it is roundiſh, and placed within the permanent calyx; in borbonia it is pointed, and terminated with a ſpine; in furze, it is turgid, and almoſt ſurrounded by the calyx; in anonis it is of the figure of a rhombus; in bladder-ſenna it is large, inflated like a bladder, membranaceous, tranſparent, and opens at the baſe of the upper future; in *hippocrepis* it is ſhaped like a horſe-ſhoe; in *hedyſarum clypeatum* it is round like a ſhield; in medic, or lucern, it reſembles a ſnail's ſhell, or ram's horn.

The SEEDS are generally few in number, round, ſmooth, and fleſhy. Jointed pods have generally a ſingle ſeed in each articulation. The ſeeds are all faſtened along one future, and not alternately to both, as in the other ſpecies of pod termed *ſiliqua*.

The plants of this family are, in general, mucilaginous.

From

From the inner bark of moſt of them flows, either naturally, or by inciſion, a clammy liquor, which dries and hardens like gum; the juice of ſome others, as liquorice, and glycine, is ſweet like ſugar.

Some of theſe plants are bitter to the taſte, purgative, or emetic, and even mortal. A ſpecies of eaſtern aſtragalus with goat's rue leaves, is ſaid to be remarkably cauſtic, and to burn the tongue exceſſively when chewed. In general, however, theſe plants are ſoft and clammy.

Common dyer's broom has the fœtid nauſeous ſmell of the elder-tree.

With reſpect to their virtues, the plants of this order are highly emollient; ſome of them too are vulnerary and aſtringent; the root of anonis, or reſt-harrow, is diuretic.

The leaves of theſe plants, particularly thoſe of trefoil, lucern, vetch, lotus, lathyrus, French honey-ſuckle or ſaint-foin, and fenugreek, afford excellent paſture for cattle; the ſeeds, which are meally and flatulent, are uſed in food both for men, and quadrupeds of the tame kind. The chief of the eſculent ſeeds are thoſe of the pea, bean, vetch, kidney-bean, chich-pea, and lentil. Externally theſe plants are applied to inflammatory tumours which tend to ſuppuration. Dyer's broom is ſaid to be of uſe in dropſies. From the young ſhoots of *amorpha*, and a ſpecies of *ſophora*, the inhabitants of North America formerly prepared a coarſe ſort of Indigo, before the introduction of the true-Indigo plant; for which reaſon the title of baſtard-Indigo is given to the former genus.

The branches of *geniſta tinctoria* are uſed by dyers to give a yellow colour, whence the ſcientific and Engliſh names of this ſpecies.

The ſeeds of white lupine are ſometimes uſed in medicine; they are bitter and diſagreeable to the taſte, but open, reſolve, and cleanſe. An ointment made of the powder of the ſeeds, juice of lemons, and allum, is eſteemed an excellent coſmetic.

Prickly anonis, or reſt-harrow, overſpreads the eaſtern countries, particularly Egypt and Paleſtine, in ſuch abundance, that Dr. Haſſelquiſt concludes it to be one of thoſe

pernicious

pernicious cumberſome plants, which are ſo frequently mentioned in Scripture by the name of thorns.

Purple reſt-harrow without thorns, the *ononis mitis* of Linnæus, which grows plentifully on the borders of fields and barren paſtures in England, emits a viſcid kind of moiſture that ſmells rank like a goat.

Dogwood-tree, the *piſcidia erythrina* of Linnæus, which grows plentifully in the Weſt-Indies, is chiefly noted for the quality ſaid to be poſſeſſed by its bark, of intoxicating fiſh, which, by that means, become an eaſy prey to thoſe who employ this ſtratagem againſt them. When any number of gentlemen have an inclination to divert themſelves with fiſhing, or more properly ſpeaking, with fiſh-hunting, they ſend each of them a negro ſlave to the woods, in order to fetch ſome of the bark of the dogwood-tree. This bark is next morning pounded very ſmall with ſtones, put into old ſacks, carried into rocky parts of the ſea, ſteeped till thoroughly ſoaked with ſalt-water, and then well ſqueezed by the negroes to expreſs the juice, which immediately colours the ſea with a reddiſh hue, and being of a poiſonous nature will, in an hour's time, make the fiſhes, ſuch as groopers, rock-fiſh, old wives, welchmen, &c. ſo intoxicated, as to ſwim on the ſurface of the water, quite heedleſs of the danger. The gentlemen then ſend in their negroes, who purſue, both ſwimming and diving, the poor inebriated fiſhes, till they catch them with their hands; their maſters, mean time, ſtanding by, on high rocks, to ſee the paſtime.

It is remarkable, that though this poiſon kills millions of the ſmall fry, it has never been known to impart any bad quality to the fiſh, which have been caught in conſequence of the intoxication.

The wood of this tree, although pretty hard, is only fit for fuel; and even for this purpoſe, the negroes very ſeldom, if ever, employ it, on account of its ſingular quality juſt mentioned. The bark is rough, brown, and thick; the tree ſends forth a conſiderable number of branches, and is well cloathed with leaves, which reſemble thoſe of the pea,

are

are thick, cottony, and of a deep green. The bark uſed for the above-mentioned purpoſe is chiefly that of the roots. See Labat, Voyage aux Iſles de l'Amerique; and Smith's Natural Hiſtory of Nevis.

The branches or ſtalks of common broom being dried in the ſun, and treated like hemp, produce threads which may be ſpun, and worked into a coarſe linen cloth. In the country they are made into beſoms, thence denominated brooms; from this its familiar uſe, Linnæus has derived the trivial name of this ſpecies, and called it *ſpartium ſcoparium*, ſweeping-broom.

The wood of a Weſt-Indian ſpecies of broom, the *ſpartium arboreſcens* of Miller, frequently known by the name of American ebony, is of a fine greeniſh-brown colour, hard, durable, and admits of an exceeding good poliſh.

M. Adanſon, in his Voyage to Senegal, mentions a new ſpecies of baſtard-ſenſitive-plant, which he had found growing wild in ſeveral parts of that country. This plant, by the negroes termed *billeur*, riſes to about ten feet in height; its roots are cloſely twiſted; the wood, which is lighter than cork, is much uſed by the negroes in fiſhing, and for tranſporting them over rivers, which, by reaſon of their breadth, render ſwimming, without ſuch a precaution, dangerous.

Goat's thorn, affirmed by Tournefort to be the plant which produces gum-dragant, or tragacanth, is the *aſtragalus tragacantha* of Linnæus. It is a native of the Levant, and ſome maritime parts of France, where it grows to the height of two or three feet. The branches are very woolly, and the foot-ſtalks of the leaves end in long ſharp thorns; the gum flows both ſpontaneouſly, and by inciſion, from the roots and trunk, and is generally of a light ſubſtance, white, ſhining, and curled. It is eſteemed highly refreſhing.

The leaves and ſeeds of common bladder-ſenna have a purgative quality, on which account they are frequently ſubſtituted for ſenna by the peaſants of Languedoc, Provence, and Italy, where the plant naturally grows. The leaves have an acrid nauſeous taſte.

The leaves of ſcorpion ſenna, the *coronilla emerus* of Linnæus,

næus, are likewiſe eſteemed laxative, and employed by the European peaſants for the ſame purpoſe as thoſe of the plant above mentioned. A dye is procured, by fermentation, from the leaves, like that of Indigo.

The common laburnum, the *cytiſus laburnum* of Linnæus, the *cytiſus alpinus latifolius, flore racemoſo pendulo*, of Ray and Tournefort, grows naturally on the Alps and the mountains of Dauphiny. It grows to the ſize of a pretty large tree, with a ſtraight ſtem; the bark is of a greeniſh colour; the wood very hard, and when finely poliſhed bears a great reſemblance to green ebony; whence the plant is generally known in France by the name of ebony of the Alps. It is frequently uſed on the continent, and in the highlands of Scotland, for making different kinds of houſehold furniture, as chairs, tables, and bedſteads, which are ſaid to equal the fineſt manhogany in beauty.

A ſpecies of *cytiſus*, termed by Linnæus, *cytiſus cajan*, is known in the Weſt-Indies, where it naturally grows, by the name of pigeon-pea, from the ſeeds being the common food of thoſe birds in that part of the world. The leaves are very ſoft, and covered with a white hoary meallineſs on the under ſurface. The flowers which grow in cluſters, are of a yellow colour, and ſucceeded by pods, containing three, four, or five roundiſh ſeeds, or peas, ſeparated from one another by ſlender tranſverſe partitions. Theſe ſeeds, beſides the uſe juſt mentioned, are boiled and eaten, whether green or dry, and being of a binding quality, afford a very wholeſome food, eſpecially during the wet ſeaſon, when dyſenteries are ſo frequent. The wood of the ſame plant is uſed for fuel.

The pods of *dolichos urens*, a twiſting or climbing plant, are thickly covered with very fine ſhort briſtles, or ſtiff hairs, which ſting worſe than nettles; hence the title of cow-itch vine, by which this ſcandent plant is generally known in the Weſt-Indies. The leaves are downy and gliſter on their under ſurface. The ſeeds are black, and furniſhed with an eye like thoſe of the bean.

The roots of liquorice, the only part uſed in medicine,

are pectoral, and of great uſe in diſtempers of the lungs, as coughs, catarrhs, ſhortneſs of breath, and hoarſeneſs. Its chief place of growth with us is about Pontefract in Yorkſhire, and Workſop in Nottinghamſhire, where it is propagated for ſale. Black liquorice is the inſpiſſated juice of the root of the liquorice plants. The beſt preparation of this kind is that which is brought from Catalonia in Spain.

From the *hedyſarum alhagi* of Linnæus, which grows plentifully in Syria and the eaſtern countries, flows abundantly a juice, which when condenſed upon the plant, is gathered by the inhabitants, and ſent to Europe by the name of Perſian manna.

From the leaves and ſmall branches of the *indigofera tinctoria* of Linnæus, is prepared that excellent dye, known by the name of indigo. The leaves, when ready for this purpoſe, are cut down, and thrown into large vats of water, where they are ſuffered to ſteep till a violent fermentation enſues, and the water acquiring heat, boils upon every ſide of the infuſed leaves, and inſenſibly becomes of a violet colour. When theſe effects, which generally happen after ſixteen or eighteen hours infuſion, are obſerved, the water is conveyed, by means of cocks at the bottom of the vat, into another veſſel, of the nature of a churn, where it is worked, by a negro, with great violence, till the water abounds with a lather, and the ſalts, and other parts of the ſubſtance of the plant are ſufficiently united. It is then allowed to ſettle, and the water, which becomes as clear as at firſt, is drawn off by means of cocks, leaving at the bottom of the veſſel, a ſediment or fæcula, like the lees of wine, which, when dried, is the valuable dye known by the name of indigo.

The negroes on the coaſt of Guinea gather the leaves of the indigo plant at any time of the year, and having pounded them in a mortar, make the paſte up into loaves, which they preſerve dry. When they want to make uſe of them in dying, they diſſolve them in a kind of lee, made of the aſhes of an unctuous plant which grows in their fields, the *portulaca marina latifolia* of Plumier, by the negroes called rheme.

This

This lee imbibes a tincture of the indigo, into which they dip their linen cold, as often as they think neceſſary, according to the deepneſs of the colour required.

The roots of *lathyrus arvenſis repens tuberoſus* of Bauhin are eſteemed an excellent food by the Siberians. They are compoſed of ſeveral ſmall round bulbs, or knobs; whence the plant is termed by Dodonæus, *terræ glandes*, or earth-nuts. In Holland likewiſe they are ſold in the markets, and uſed for food.

M. Adanſon, in his Voyage to Senegal, mentions a leguminous tree, termed farobier by the negroes, who are extremely fond of its pods. The wood is hard and weighty. The pod, or huſk, is like that of a French bean, but above a foot in length, and contains a black flat ſeed, enveloped in a yellow farinaceous ſubſtance, which frequently ſerves them for ſuſtenance, eſpecially on a journey. It is very nouriſhing, ſays Adanſon, and taſtes like the beſt ginger-bread cake.

Of the wood of the ſhrubby medic, which is ſuppoſed to be the *cytiſus* of Virgil, the Turks make handles to their ſabres.

The knobs of the root of Engliſh wild-wood, or bitter vetch, taſte very like liquorice, and are uſed in the highlands of Scotland for the ſame diſorders of the breaſt, in which liquorice is proper. The ſame knobs tempered with water are ſaid to be of ſingular efficacy in enabling thoſe who uſe it to ſuſtain hunger and thirſt for a very conſiderable time.

The leaves of common meadow trefoil are drying and binding, uſeful in fluxes, ſtrangury and heat of urine. Made into a poultice with hog's-lard, they are reckoned good for tumours and inflammations.

The leaves and flowers of melilot, the *trifolium melilotus officinalis* of Linnæus are uſed in medicine. They ſoften, diſcuſs, and eaſe pain, and are frequently ordered in cataplaſms againſt inflammations, hard tumours, and any kind of ſwelling. Melilot plaſter, made of the leaves of this herb boiled in mutton ſuet, roſin, and wax, is drawing,

and

and good for green wounds, but is chiefly uſed in dreſſing of bliſters.

PAPPOSÆ, (PAPPUS, *vide infra*) the name of the 11th claſs in Chriſtopher Knaut's Method, conſiſting of compound flowers which have their ſeeds crowned by a

PAPPUS, (thiſtle-down—*pappi volantes* Lucr. Pliny gives this name to the *ſenecio* or groundſel, another down-bearing plant. His words are, *Erigeron à noſtris vocatur Senecio, al. pappus*) ;—a ſort of feathery or hairy crown, with which many ſeeds, particularly thoſe of compound flowers, are furniſhed, for the purpoſe of diſſemination. A ſeed, ſurmounted by its *pappus*, reſembles a ſhuttle-cock; ſo that it is naturally framed for flying, and for being tranſported by the wind to very conſiderable diſtances from its parent plant;—an admirable contrivance of nature to diſſeminate her productions, and thus render common to different ſoils and territories, individuals of the ſame ſpecies, which, without ſuch precaution, might have been confined to one. It muſt be obſerved, however, that Dandelion, hawk-weed, nipple-wort, groundſel, and many others of our moſt cumberſome weeds, are diſſeminated in this manner.

The pappus, as was juſt hinted, is either ſimple like hairs, (*pappus piloſus*) as in ſilk cotton-tree, ſucculent ſwallow-wort, colt's-foot, groundſel, golden rod, hawk-weed, doronicum, cacalia, and ſeveral other compound flowers; or branched like a feather, (*pappus plumoſus*) as in valerian, dandelion, ſonchus, hemp-agrimony, and cud-weed. In ſome plants, as hawk-weed, and prenanthes, the *pappus* adheres immediately to the ſeed; in others, as lettuce, and crepis, it is elevated upon a foot-ſtalk which connects it with the ſeeds; in the firſt caſe, it is termed by Linnæus, *pappus ſeſſilis*; in the ſecond, *pappus ſtipitatus*; the foot-ſtalk or thread upon which it is raiſed having obtained the name of *ſtipes*. *Vide* STIPES.

Linnæus has, with ſurprizing accuracy, pointed out the numerous varieties which obtain in this minute part of the plant, which he generally employs as a diſtinctive cha-

racter in diſcriminating the different genera of compound flowers. *Vide* SYNGENESIA.

PEDICELLUS (diminutive from *pediculus*, a foot-ſtalk) a partial flower-ſtalk; the proper ſtalk of any ſingle flower in an aggregate or head of flowers. The principal ſtalk which ſupports all the flowers, is termed the common flower-ſtalk; the ſtalk of each partial flower, if it has one, is ſtiled the proper flower-ſtalk, and by Linnæus, *Pedicellus*.

PEDICULUS (diminutive from *pes*, a foot) a foot-ſtalk; a term uſed by the ancient botaniſts, to denote the foot-ſtalks both of flowers and leaves. Linnæus has exploded the term, and, in its place, ſubſtituted two others, *petiolus*, for the foot-ſtalk of the leaves; *pedunculus*, for the foot-ſtalk of the flowers.

PEDUNCULUS (*pes*, a foot) the foot-ſtalk of a flower, or head of flowers. Both flower and leaf-ſtalks were formerly ranged by Linnæus among the trunks: of late years, however, they have loſt much of their conſequence; and in the lateſt editions of the *Syſtema Naturæ*, are degraded to a place among the *fulcra*, or parts of plants that ſerve for ſupport, protection, and defence.

The *Pedunculus*, or flower-ſtalk, elevates the flower and fruit only, without the leaves; the *petiolus*, or leaf-ſtalk ſupports the leaves only, without the flower, or fruit. Thus theſe partial trunks ſtand eſſentially diſtinguiſhed from each other.

Flower-ſtalks have different epithets, from the place which they occupy on the plant. When they proceed immediately from the root, they are termed radical, (*pedunculus radicalis*) when from the ſtem, trunk-ſtalks, (*pedunculus caulinus*) when from the branch, branch-ſtalks, (*pedunculus rameus*) and ſo of others.

Again, flower-ſtalks ſometimes terminate the ſtem or branches; ſometimes proceed from the angle formed by the leaf and ſtem, or by the ſtem and branch. A flower-ſtalk of the former kind is termed by Linnæus *pedunculus terminalis*; of the latter, *pedunculus axillaris*, as it is from the

axilla,

axilla, or arm-pit of the leaf or branch, that the ſtalk in queſtion is protruded.

Flower-ſtalks, as well as flowers, are ſaid, in the language of botany, to be *ſolitary*, when they grow ſingly, or are produced one by one: *ſcattered* (*pedunculi ſparſi*) when they grow together in great numbers, and are produced without any order.

From the number of fructifications on each foot-ſtalk, ariſe other epithets of the *pedunculus*; ſome bear one, ſome two, ſome three flowers; others an indeterminate number; hence the terms *pedunculus uniflorus*, *biflorus*, *multiflorus*, &c. expreſſive of theſe ſeveral circumſtances. A ſolitary foot-ſtalk may ſupport many flowers; whilſt a ſolitary flower neceſſarily implies a ſingle or ſolitary flower-ſtalk.

For the different modes in which flowers are borne and connected on their foot-ſtalks, ſee the article INFLORESCENTIA.

The flower-ſtalks frequently afford excellent characters in diſcriminating the ſpecies. Thus a ſpecies of globe amaranth is very accurately diſtinguiſhed by its flower-ſtalks being furniſhed with two leaves that are placed oppoſite, and immediately under each head of flowers.

Flower-ſtalks, whether of equal or unequal length, that form an even ſurface at top, are termed by Linnæus *pedunculi faſtigiati*. The term is exemplified in ſweet-william, and viſcous campion.

A flower-ſtalk is termed flaccid, (*pedunculus flaccidus*) which is ſo weak and feeble, as to hang down by the weight of the flower which it ſupports.

A drooping or nodding flower-ſtalk (*pedunculus cernuus*) is bent at the top, ſo that the flower is inclined to one ſide, or towards the earth, and cannot be placed erect, on account of the curvature of the ſtalk. This term is exemplified in *carpeſium*, drooping-thiſtle, mountain-ſcabious, annual ſun-flower, and the Siberian ſpecies of bleſſed thiſtle.

In ſweet-weed and *oldenlandia biflora*, the flower-ſtalks come out in pairs; in a ſpecies of balſam, they proceed by threes from the angle of the leaves.

In *jambolifera*, *ochna* and juſticia, the flower-ſtalks remain on the plant after the flower and fruit are fallen.

The flower-ſtalks of *aira flexuoſa* take a variety of different directions; thoſe of goat's-beard, *cotula*, and moſt of the nodding flowers, thicken towards the upper extremity.

In ſome ſpecies of Syrian mallow, *ſida*, and wood-ſorrel, the flower-ſtalks are jointed (*pedunculus articulatus ſeu geniculatus.*) Theſe circumſtances reſpecting the flower-ſtalks, will be found to be of ſingular uſe in diſcriminating the ſpecies.

PELTA, a very ſhort buckler, or target;—by this name Linnæus characterizes the flower or flat fructification of the genus Lichen or liver wort, which, in moſt of its ſpecies, is glued to the edges of the leaves.

PENTAFORA (πεντε, five; and *fores*, a door) the name of a claſs in Camellus's Method, conſiſting of plants with ſeed-veſſels which have five external openings or valves. It is exemplified in flax, lime-tree, Syrian mallow, and ſilk-cotton tree.

PENTANDRIA (πεντε, five; and ἀνηρ, a man or huſband) the name of the fifth claſs in Linnæus's Sexual Method, conſiſting of plants which have hermaphrodite flowers with five ſtamina or male organs.

The orders in this numerous claſs of plants are ſix; and, like thoſe of the other plain or numeral claſſes, are founded upon the number of ſtyles, or female organs.

Night-ſhade, water-leaf, looſe-ſtrife, marvel of Peru, ſow-bread, ivy, vine, and the rough-leaved plants, have one ſtyle.

Elm, dog's-bane, ſwallow-wort, gentian, and the umbelliferous plants have two ſtyles.—Sumach, viburnum, tamariſk, bladder-nut, and chickweed, have three ſtyles.

Graſs of Parnaſſus and evolvulus have four ſtyles.

Berry-bearing angelica, flax and thrift, have five ſtyles.

Mouſe-tail has many ſtyles.

PENTANGIÆ (πεντε, five; and ἀγγος, a veſſel) the name of the ſixteenth claſs in Boerhaave's Method, conſiſting of plants with five capſules, or a ſingle ſeed-veſſel divided

ed

ed internally into five cells. It is exemplified in rue, bean-caper, kalmia, ledum, dwarf roſe-bay, ſtrawberry-tree, winter-green, and columbine.

PENTAPETALI (πεντε, five; and πεταλον, a petal or flower-leaf) the name of two claſſes in Rivinus's Method; conſiſting of plants whoſe flowers have five petals, which, in their form, are either regular or irregular. The regular flower of five petals is exemplified in flax, berry-bearing angelica, rock-roſe, pæony, mallow, marſh-mallow, and ranunculus; the irregular, in aconite, and lark-ſpur.

PERFECTUS *flos*, a perfect flower; a term of Ray, Rivinus, Kramer, and Pontedera, correſponding to the *petalodes* of Tournefort, and expreſſive of the preſence of the petals, which, by thoſe authors, were deemed the eſſential part of every flower. In the Sexual Method, the petals are conſidered only as the inner cover of the flower, which is ſolely conſtituted by the preſence of the ſtamina and ſtigma, the ſuppoſed male and female organs of generation.

PERFORATÆ (*perforari*, to be pierced through) the name of an order in the former editions of Linnæus's Fragments of a Natural Method, conſiſting of plants, whoſe leaves have many pellucid ſpots in them, which, when held up againſt the light, appear like ſo many minute dots or points.

The genera in this order were four, St. John's-wort, *aſcyrum*, rock-roſe, and true orpine (telephium). The three former are now removed to the order *Rotaceæ*, the latter to *Miſcellaneæ*.

PERIANTHIUM (περι, around, and ἀνθος, the flower) the flower-cup properly ſo called; the moſt common ſpecies of calyx, placed immediately under the flower, which is contained in it as in a cup.

The flower-cup, like the other parts of fructification, differs in point of number, figure, proportion, and ſituation.

Vaillant eſtabliſhed for an axiom that in complete flowers, when the calyx is of ſeveral pieces, the flower, or corolla, is likewiſe of ſeveral pieces, *& ē contra*. That this rule is

erroneous, appears from the pea-bloom flowers, and thoſe of the mallow tribe, in which the calyx conſiſts of one leaf, and the petals are five in number. On the other hand, it may be affirmed with certainty, that when the flower conſiſts of one petal, the calyx always conſiſts of one leaf, although the diviſions may be ſo deep as to induce an opinion, upon a ſuperficial view, that it is compoſed of ſeveral diſtinct leaves. Thus in the rough leaved plants, the lipped and maſqued flowers, and ſome other natural families, the calyx, although deeply divided, is determined to be of one piece, as the diviſions, when the calyx is detached from the flower, adhere cloſely together, and do not reſolve themſelves into diſtinct leaves, as they doubtleſs would, if divided to the baſe.

The number of ſegments in a flower-cup of one piece is generally equal to the number of petals, if the flower conſiſts of more petals than one; or to the number of diviſions of the ſingle petal, if the flower contains no more. It may here be proper to obſerve that a flower-cup conſiſting of many leaves is rarely found to have its leaves cut into ſegments; the above rule therefore reſpects only ſuch flower-cups as have one leaf.

Some flowers, as tulip, crown imperial, and moſt of the other liliaceous plants, want the flower-cup. In moſt plants it is ſingle. In morina, ſide-ſaddle flower, and ſome genera of the mallow tribe, double. *Vide* COLUMNIFERÆ.

With reſpect to the number of leaves of which it is compoſed, the flower-cup is either of one leaf (perianthium monophyllum) as in primroſe and thorn-apple; of two leaves, as in poppy, globe-amaranth, cock's-comb, hypecoum, claytonia, and fumatory; of three, as in dock, arrowheaded-graſs, tulip-tree, magnolia, cuſtard-apple, and Virginian ſpider-wort; of four, as in French willow, heath, water-lily, barren-wort, and the croſs-ſhaped flowers, the *tetradynamia* of Linnæus; of five, as in ranunculus, rock-roſe, adonis, *jacquinia*, mountain knot-graſs, wild orach, golden-rod tree, glaſs-wort, beet, mouſe-tail, flax, and the greater number of flowers with more petals than one; of

ſix, as in lion's-leaf, berberry, *hillia*, *flagellaria* and *tetracera*: of ſeven, as in winter-green, (*trientalis*) of eight, as in *mimuſops* and *diapenſia*; or of ten, as in galax.

A flower-cup of one leaf is either undivided, (perianthium integrum) as in genipa and olax; cut into two ſegments (perianthium bifidum) as in tuberous moſchatel, purſlane, and mammee; into three, as in *burmannia* and cliffortia; into four, as in ladies bed-ſtraw, and elephant's head; into five, as in tobacco, and the greater number of flowers that have a calyx of one leaf; into ſix, as in *ginora*; into eight, as in tormentil; into ten, as in cinquefoil, and herb-bennet; or into twelve, as in purple looſe-ſtrife and water-purſlane.

With reſpect to figure, it may be obſerved, in general, that the calyx ſpreads leſs than the petals; an erect poſition being more ſuitable to its office, which is to prop and contain the flower. In cucubalus, the flower-cup is round like a globe; in viſcous campion it is club-ſhaped; in ſwallow-wort, it is turned backwards.

The leaves or diviſions of the flower-cup are either equal, as in moſt plants; or unequal, as in rock-roſe, tormentil and cinquefoil; in the two laſt of which examples, all the diviſions of the flower-cup are alternately greater and leſs; in rock-roſe, two of the five leaves of which the calyx conſiſts, are alternately leſs than the other three.

The margin of the cup in moſt plants is entire; in a ſpecies of St. John's wort it is ſawed, or indented (perianthium ſerratum); and in ſome ſpecies of centaury it is fringed like an eye-laſh (perianthium ciliatum).

The apex or tip of the flower-cup is ſometimes ſharp, as in primroſe and henbane; or blunt, as in water-lily and mangoſtan. In vervain the calyx is cut into five indentments, four of which are ſharp, and the fifth, being blunt, looks as if lopped or bit off.

With reſpect to proportion, the calyx is either ſhorter than the corolla, as in moſt plants; equal to it in length, as in a ſpecies of ceraſtium; or longer, as in *ſagina agroſtemma*, and a ſpecies of calve's ſnout.

When the flower-cup includes the ſtamina and not the ſeed-bud, as happens in French-willow, and all the other flowers which have their ſeed-bud placed below the receptacle of the flower, it is termed the perianthium of the flower; when the ſeed-bud and not the ſtamina, the perianthium of the fruit; when both ſtamina and ſeed-bud, the perianthium of the fructification. *Linnæa*, clove-tree, and *morina*, have two *perianthiums*, which ſerve very properly to illuſtrate the terms juſt mentioned; one of theſe cups is appropriated to the flower, the other to the fruit. The perianthium of the fructification is exemplified in pæony, and the greater number of plants.

With reſpect to compoſition, the flower-cup ſometimes conſiſts of a number of leaves which are laid over one another like tiles or ſcales, (perianthium imbricatum) as in hawk-weed, ſow-thiſtle, and camellia; ſometimes of ſcales that ſpread wide, and are diffuſed on all ſides, (perianthium ſquarroſum) as in thiſtle, and flea-bane, in which the ſcales are not cloſely laid upon one another, as in hawk-weed, but diverge on every ſide. In pink, tick-ſeeded ſunflower, water hemp-agrimony and baſtard hawk-weed, the baſe of the flower-cup, which is ſimple, is ſurrounded externally by a ſeries of diſtinct leaves, ſhorter than its own. This ſort of flower-cup Linnæus terms *calyx auctus*, an increaſed or augmented calyx; Vaillant had termed it, with equal propriety, *calyx calyculatus*; that is, a flower-cup furniſhed with a leſſer flower-cup.

With reſpect to duration, the flower-cup either falls off at the firſt opening of the flower, (perianthium caducum) as in poppy and barren-wort; with the flower, that is, the the petals, ſtamina, and ſtyle, (perianthium deciduum) as in berberry, and the croſs-ſhaped flowers; or continues till the fruit has attained maturity (perianthium perſiſtens) as in the lipped and maſqued flowers, and ſeveral others.

Laſtly, a flower-cup is proper to one flower, as in all the plants with ſimple flowers; or common to many, as in ſcabious and the compound flowers.

PERICARPIUM (περι, round; and καρπος, fruit) the ſeed-

ſeed-veſſel; an entrail of the plant, big with ſeeds, which it diſcharges when ripe. The ſeed-veſſel is, in fact, the developed ſeed-bud, and may very properly be compared to the fecundated ovary in animals; for it does not exiſt till after the fertilizing of the ſeeds by the male duſt, and the conſequent fall of the flower. All plants, however, are not furniſhed with a ſeed-veſſel; in ſuch as are deprived of it, the receptacle or calyx performs its functions, by incloſing the ſeeds as in a matrix, and accompanying them to perfect maturity. This is particularly the caſe with the rough-leaved plants, and thoſe of the firſt order of the claſs *Didynamia* of Linnæus. *Vide* ASPERIFOLIÆ, *et* VERTICILLATÆ.

The different ſpecies of *pericarpium* enumerated by Linnæus are as follows;

I. Capſula.
II. Siliqua.
III. Legumen.
IV. Folliculus, — Formerly *conceptaculum*.
V. Drupa.
VI. Pomum, — — *Fructus carnoſus* of others.
VII. Bacca.
VIII. Strobilus, — — *Conus* of Tournefort.

Each of theſe terms is explained in its proper place.

Although the ſeed-veſſel, like the other parts of fructification, is commonly employed to diſcriminate the genera only; yet ſuch ſtriking circumſtances in its ſtructure as, for want of uniformity, cannot enter into the generic difference, are frequently uſed, with elegance, to diſtinguiſh the ſpecies. Thus the inflated pod of *fumaria veſicaria*; the top-ſhaped fruit of the pear; the twiſted ſeed-veſſel of a ſpecies of meadow-rue, ſome ſpecies of ſcrew-tree and meadow-ſweet; the prickly fruit of caltrops, and ſuch like characters, which do not run through a whole genus, afford very certain marks of diſtinction in determining the ſpecies, and ought to be employed without reſerve.

PERSISTENS (*perſiſto*, to continue)—Permanent. This term is expreſſive of the third and longeſt ſtage of duration in plants, and, like the other terms of duration (*caducus* and *deciduus*) admits of different ſignifications, according to the part of the plant to which it is applied. Leaves are ſaid to be permanent which remain till the fruit is ripe. Stipules are permanent which continue on the plant after the fall of the other leaves; and this epithet is applied to ſuch perianths, or flower-cups, as incloſe the naked ſeeds, and, ſupplying the place of a *pericarpium*, accompany them to maturity. This laſt is the moſt common uſe of the term in Botanical language, and it is exemplified in the *aſperifoliæ*, or rough-leaved plants of Ray, and in thoſe of the order *gymnoſpermia* of the claſs *didynamia* of Linnæus. *Vide* CADUCUS *et* DECIDUUS.

PERSONATUS *flos*, (*perſona*, a maſque) a maſqued flower; a flower with an irregular petal, reſembling the head or ſnout of an animal. *Vide* RINGENS *flos*.

The maſqued flowers conſtitute part of a claſs in Tournefort's Method, by the name of *flores tubulati*, *perſonati*, which partly correſpond to the *didynamia angioſpermia* of the Sexual Method.

PERSONATÆ, the name of the fortieth order in Linnæus's Fragments of a Natural Method, conſiſting of a number of plants, whoſe flowers are furniſhed with an irregular gaping or grinning petal, which, in figure, ſomewhat reſembles the ſnout of an animal.

Moſt of the genera of this natural order arrange themſelves under the claſs and order *didynamia angioſpermia* of the Sexual Method. The reſt, although they cannot enter into the artificial claſs juſt mentioned, for want of the claſſic character, (the inequality of the ſtamina,) yet, in a natural method, which admits of greater latitude, may be arranged with the *Perſonatæ*, which they reſemble in their habit and general appearance, and particularly in the circumſtance expreſſed in the title.

List of the Genera *contained in this Natural Order.*

SECTION I.

Plants with masqued Flowers having their Stamina of an equal length.

Linnæan Genera.			*English Names.*
Collinsonia.			
Dianthera.			
Gratiola,	—	—	Hedge-hyssop.
Justicia,	—	—	Malabar-nut.
Scoparia.			
Verbena,	—	—	Vervain.
Veronica,	—	—	Speedwell.

SECTION II.

Plants with masqued Flowers having two long and two short Stamina.

Acanthus,	—	—	Bear's breech.
Antirrhinum,	—	—	Calve's-snout, toad's-flax, snap-dragon.
Avicennia.			
Barleria.			
Bartsia.			
Besleria.			
Bignonia,	—	—	Trumpet-flower.
Bontia.			
Buchnera.			
Capraria,	—	—	Sweet-weed.
Chelone.			
Citharexylon,	—	—	Fiddle-wood.
Clerodendrum.			
Columnea.			
Cornutia.			

Craniolaria,

Linnæan Genera.			*Engliſh Names.*
Craniolaria.			
Cymbaria.			
Dodartia.			
Duranta.			
Erinus.			
Euphraſia,	—	—	Eye-bright.
Gerardia.			
Geſneria.			
Gmelina.			
Halleria,	—	—	African fly—honey-ſuckle.
Lantana,	—	—	American Viburnum.
Lathræa.			
Manulea.			
Martynia.			
Melampyrum,	—	—	Cow-wheat.
Mimulus,	—	—	Monkey-flower.
Obolaria.			
Orobanche,	—	—	Broom-rape.
Ovieda.			
Pedicularis,	—	—	Rattle-coxcomb, or louſe-wort.
Petrea.			
Phryma.			
Rhinanthus,	—	—	Elephant's-head.
Ruellia.			
Schwalbea.			
Scrophularia,	—	—	Fig-wort.
Stemodia.			
Torenia.			
Tozzia.			
Vandellia.			
Vitex,	—	—	Agnus caſtus, or chaſte-tree.
Volkameria.			

Habit and Structure of the Plants of this Order.

This order furniſhes both herbaceous and woody vegetables of the ſhrub and tree kind.

The

The ROOTS are generably fibrous and branched; in gerardia and tozzia, they are tuberous. The roots of broom-rape are paraſitical; that is, attach themſelves to the roots of other plants, from which they derive their nouriſhment.

The STEMS and branches are cylindrical when young, except in ſome ſpecies of fig-wort, in which they are ſquare.

The LEAVES are ſimple, generally placed oppoſite in pairs at the bottom of the branches, but in many genera, ſtand alternate towards the top. In *lathræa*, *cymbaria*, and *ſtemodia*, the leaves are placed alternate from the bottom to the ſummit of the branches. The leaves of petrea are ſo rough, that they ſerve to file and poliſh wood; thoſe of broom-rape and lathræa reſemble ſcales. In hedge-hyſſop and *limoſella*, the leaves are tranſparent, and ſeem marked with dots or minute points. In halleria, they have ſeveral ſmall prominences or knots on the under ſurface. In a ſpecies of volkameria, after the fall of the leaves, the lower part of the foot-ſtalk remains attached to the branches under the form of a thorn. The ſame appearance is obſerved in the genus *Tournefortia*. *Vide* ASPERIFOLIÆ.

Some ſpecies of trumpet-flower have the common foot-ſtalk of their winged leaves terminated by a tendril, with three or five branches. In a ſpecies of cornutia is obſerved a *ſtipula* or ſcale, in form of a half-moon, of the ſame ſubſtance with the leaves, between which it is placed.

The FLOWERS are univerſally hermaphrodite. They proceed either ſingly, or in cluſters, from the wings of the leaves, as in American viburnum, bontia, columnea, hedge-hyſſop, and fig-wort; or terminate the branches in a ſpike, panicle, or head, as in cornutia, clerodendrum, gmelina, vervain, and agnus caſtus. In the latter they ſeem placed in whirls.

The CALYX or flower-cup is of one leaf, which is cut into two, three, four, or five diviſions that are permanent. In trumpet-flower the calyx falls off early, and generally reſolves itſelf into five diſtinct leaves. The flower-cup of bartſia is of a beautiful-red colour at its apex, by which

ſtriking

ſtriking character the genus in queſtion is chiefly diſtinguiſhed from eye-bright, elephant's-head, and rattle coxcomb, to which it otherwiſe ſeems nearly allied. The genus *cymbaria* ſtands diſtinguiſhed from the other genera by the numerous diviſions of the calyx.

The COROLLA is compoſed of one irregular petal with two lips, reſembling, as was already obſerved, the head or ſnout of an animal. In toad-flax, the petal is terminated behind by a nectarium in form of a ſpur.

The STAMINA in plants of the firſt ſection, are two or four in number, and of an equal length; in thoſe of the ſecond, they are univerſally four in number, two of which are longer than the other two. In hedge-hyſſop, and ſome ſpecies of vervain, the filaments are four in number, but two of theſe only are terminated by anthers; ſo that the number of perfect ſtamina in theſe plants is only two; the other two being, in the language of Linnæus, caſtrated. The filaments likewiſe of vervain are generally of an unequal length. In *dianthera*, as the name obſcurely imports, two anthers are placed upon each filament; and in *chelone*, the rudiment of a fifth filament, without the anther, is placed within the upper pair of ſtamina.

The SEED-BUD is ſingle and placed above the receptacle of the flower. The ſtyle is ſingle, thread-ſhaped, bent in the direction of the ſtamina, and crowned with a *ſtigma*, which is generally blunt, and ſometimes divided into two. In American viburnum, the ſummit of the ſtyle is hooked; in which circumſtance conſiſts the eſſential character of the genus. In broom rape, and *lathræa*, a glandular nectarium is ſeated at the baſe of the ſeed-bud.

The SEED-VESSEL is a capſule, generally divided internally into two cavities, and externally into the ſame number of valves. In *lathræa*, *dianthera*, *juſticia*, *barleria*, *ruellia*, and bear's-breech, the capſule opens with an elaſtic ſpring.

The SEEDS are numerous, and affixed to a receptacle in the middle of the capſule.

Theſe plants poſſeſs nearly the ſame qualities with the lipped-flowers, though in a leſs degree.

The

The powder of the roots and leaves of officinal vervain, or an infuſion of them in water, is applied with ſucceſs, both internally and externally, in dangerous ulcers, and tumours of the viſcera, particularly thoſe of the ſpleen. Both root and leaves have a bitter and diſagreeable taſte. The plant is generally found in the neighbourhood of dwelling-houſes.

The juice of a ſpecies of vervain with blue flowers, which grows naturally in the Weſt-Indies, is ſaid to be ſo powerful a deobſtruent, that a large ſpoonful taken inwardly, for three or four mornings in ſucceſſion, has greater efficacy in bringing down the catamenia, than either the uſe of chalybeate medicines, or any other method.

Fluellin, male ſpeed-well, or officinal veronica, is reckoned among the vulnerary plants, and uſed both inwardly and outwardly. It is likewiſe pectoral. The fumes of a decoction of this plant in water and vinegar being received into the mouth, by means of a funnel, are ſaid to be a ſovereign remedy in ſuffocations, and aſthmas, occaſioned by a collection of phlegm in the lungs. The herb is uſed as tea in gouty and rheumatic diſorders. The leaves have a ſomewhat bitter taſte, with little or no ſmell.

Brook-lime, the *veronica beccabunga* of Linnæus, is uſed in infuſion for the ſcurvy, and is a principal ingredient in moſt diet-drinks for that diſtemper. The herb is almoſt inſipid to the taſte, and without ſmell.

Round leaved female fluellin, the *antirrhinum ſpurium* of Linnæus, is ſucceſsfully uſed in fluxions and inflammations of the eyes.

Toad-flax, the *linaria vulgaris* of former botaniſts, the *antirrhinum linaria* of Linnæus, is rarely uſed internally; externally it is of efficacy in the piles. The diſtilled water of the herb is ſaid to be an excellent coſmetic.

Eye-bright has been long eſteemed a ſpecific in diſorders of the eyes, eſpecially for dimneſs of ſight, as the name ſeems to import. Its internal uſe, and even the propriety of its external application, has been of late greatly diſputed.

The berries of ſeveral ſpecies of camara, or American viburnum,

virburnum, which grow naturally in the Weſt-India iſlands, and are known by the name of wild ſage, ſerve for food to ſparrows and other birds. The leaves, either boiled into a decoction, or infuſed like tea, are an excellent ſudorific.

The roots of fig-wort powdered, and made into a plaſter with wax and ſoap, are ſaid to diſſipate cold ſcrophulous tumours in the neck. A decoction of the leaves cures the itch.

The leaves of water-betony, the *ſcrophularia aquatica* of Linnæus, are ſometimes uſed in the form of ſnuff, to promote ſneezing.

Collinſonia, a native of Penſylvania, and other parts of North America, from which it was introduced into Europe by the ingenious Mr. Bartram, is poſſeſſed of a peculiar ſcent, which, though agreeable, is ſo very ſtrong, as frequently to give a violent head-ach, eſpecially when the plant is abundant, and in flower. An infuſion of *Collinſonia* in water, taken internally, has been found efficacious in diſpelling the poiſon occaſioned by the bite of the rattle-ſnake; nor is the outward application of the herb leſs ſucceſsful in pains of the limbs, when the parts affected are rubbed with it. In New-York they diſtinguiſh this plant by the name of horſe-weed, becauſe the horſes eat it in ſpring, before any other herbs make their appearance.

PETALUM, (πεταλον, a leaf); a petal or coloured leaf of the flower. *Vide* COROLLA.

PETIOLUS, (diminutive *a pede, quaſi pediolus*.—By *Columella* it is uſed for the fruit-ſtalk—"*Petioli quibus pendent mala*,")—the foot-ſtalk of the leaves; one of the *fulcra* of plants, according to Linnæus, or parts that ſerve for ſupport, protection and defence. As the leaves and fructification are generally ſupported by different foot-ſtalks, Linnæus has very properly marked this diſtinction, by aſſigning to each foot-ſtalk a different name; *pedunculus* to that of the flower; *petiolus* to that of the leaves. In a very few inſtances, however, as turnera and Syrian mallow, the ſame foot-ſtalk ſupports both flower and leaves.

The foot-ſtalk of the leaves is of a green colour, ſome-

times cylindrical, but moſt commonly furniſhed with two diſtinct ſurfaces, a front, and a back; the former flat, the latter round and convex. By this configuration, the footſtalks of compound leaves are generally with accuracy diſtinguiſhed from the young branches, with which beginners are very apt to confound them. *Vide* FOLIUM.

This part of the plant ſometimes affords very elegant marks of diſtinction in diſcriminating the ſpecies. Thus the winged footſtalks of the orange-tree, and *hedyſarum triquetrum*, ſufficiently diſtinguiſh each from its reſpective congeners.

PILEUS, a hat or bonnet; the orbicular horizontal expanſion or upper part of a muſhroom, which covers the fructification. This, from its figure, is properly enough termed by botaniſts the hat of the muſhroom.

PILI, hairs; one of the ſpecies of *pubes* or defenſive weapons with which ſeveral plants are furniſhed. *Vide* PUBES.

PIPERITÆ (*piper*, pepper) the name of the ſecond order in Linnæus's Fragments of a Natural Method, conſiſting of pepper, and a few genera which agree with it in habit, ſtructure, and ſenſible qualities, particularly the latter.

Liſt of the Genera *contained in this Order.*

	Linnæan Genera.			*Engliſh Names.*
α	*Ambroſinia.*			
	Arum,	—	—	Cuckow-pint, or wake-robin.
	Calla,	—	—	African arum.
	Dracontium,	—	—	Dragons.
	Pothos.			
	Zoſtera,	—	—	Graſs-wrack.
β	*Acorus,*	—	—	Sweet-ruſh, or calamus aromaticus.
	Orontium,	—	—	Floating arum.
	Piper,	—	—	Pepper.
	Saururus,	—	—	Lizard's-tail.

Theſe plants are moſtly herbaceous and perennial. The

ſtalks of *pothos* creep along rocks and trees, into which they ſtrike root at certain diſtances. The greateſt height to which any of theſe plants is known to attain, is fifteen feet; the greater part do not exceed three or four.

The fleſhy roots of many of theſe plants, particularly thoſe of ſeveral ſpecies of arum, are extremely acrid when freſh. They loſe this pungent quality, however, by being dried, and become of a ſoapy nature. The ſmell of many of the arums, and of ſome other plants of this order, particularly *Dracontium fœtidum*, is very offenſive, frequently reſembling the odour of human excrements. The flowers, however, of an Ethiopian ſpecies of *dracunculus*, or arum, the *Calla Æthiopica* of Linnæus, and the cover in which they are involved, are ſaid to emit a very fragrant odour.

With reſpect to their virtues, theſe plants are aſtringent. The fæcula of common arum poſſeſſes the diaphoretic virtue of antimony; the powder of its root attenuates and diſſipates obſtructions.

In hot countries, the tuberous roots of many of the arums, particularly thoſe of the ſpecies called colocaſia, are dried and eaten by the inhabitants, either roaſted or raw. In the Weſt-Indies too, the leaves of ſome of the ſorts, particularly that with a water-lily-leaf, are boiled and eaten as greens; hence the names of Indian kale, and eſculent arum, which have been given to this ſpecies.

The native Indians in North-America, boil the ſpadix and berries of the Virginian arum, which they eſteem as a dainty. Theſe berries, when raw, have a harſh pungent taſte, which they loſe in a great meaſure by being boiled. They eat likewiſe the roots, which often grow to the thickneſs of a man's thigh, and when freſh, have a pungent taſte, and are reckoned poiſonous. For this reaſon they never venture to eat them till the deleterious juice has been totally expelled by the force of fire, when they devour them with great avidity. Prepared in this manner, they taſte like potatoes. This ſpecies, however, is never, like thoſe mentioned in the preceding paragraph, dried and preſerved for uſe, but taken freſh out of the marſhes as it is wanted.

From

From the root of *Calla Æthiopica*, the *Arum Æthiopicum* of Commelyn, the Hottentots, we are told, prepare a farinaceous ſubſtance, which they uſe inſtead of bread, and which, by the Europeans at the Cape, is commonly called Hottentot-bread. Its acrimony they extract by boiling it in two or three freſh waters, after which, they adapt it to their taſte by drying it in the ſun, and roaſting it in embers. The flower of this ſpecies of *calla* is white, as was obſerved above, and of a fragrant ſmell reſembling muſk. The root is white and large, and, when cut in ſlices, ſays Kolben, bears ſo ſtrong a reſemblance to Spaniſh radiſh, that the Cape Europeans, for the ſake of amuſement, frequently paſs the former upon ſtrangers for the latter. But the mirth, he continues, of this deceit, is frequently ſpoiled by the reſentment of the deceived. For ſo very tormenting is the effect of the *arum* upon the palate, and to ſuch a degree doth it ſting and inflame the mouth, that the pain is ſcarcely ſupportable, and greatly exaſperated by the drinking of water, to which a ſtranger is always tempted to have recourſe, with a view of allaying it.

The ſucculent fruits of the genus *pothos* are eaten like ſtrawberries.

The ſtalks of ſweet-ruſh, when rubbed, emit a very agreeable aromatic ſmell, as do the leaves when broken. The roots are ſometimes uſed in decoction.

The natives of the Aſiatic iſlands chew inceſſantly with the areca-nuts the leaves of a ſpecies of pepper, termed betel. They commonly wrap up a quarter of an areca-nut in ſome betel leaves, and ſo chew them together. This juice, which they pretend fortifies their gums and ſtomach, is as red as blood, and gives a like tincture to the ſpittle and lips, but blackens the teeth prodigiouſly. The taſte, at firſt, is ſaid to be inſupportably acrid.

Pepper of Senegal is different from that of India. The plant bears a round berry about the bigneſs of hemp ſeed, which, when ripe, is of a beautiful-red colour, and of a ſweetiſh taſte. It contains a ſeed of the ſhape and bigneſs of a grain of cabbage, but very hard, and poſſeſſing an agree-

able poignancy. The berries grow in ſmall bunches on a ſhrub that is three or four feet high, and has thin ſupple branches, furniſhed with oval leaves, that are pointed at the ends, very greaſy, and not unlike thoſe of the privet.

PISTILLUM, (properly a peſtle to pound, or ſtamp with, in a mortar—a *pinſo*, *piſtum*, *id eſt*, *tundo*, to beat) the peſtle, piſtil, or pointal; an erect column, generally placed in the centre of the flower, within the ſtamina, and ſuppoſed by the ſexualiſts to be the female organ of generation in plants. Its parts are three.

I. The *germen*, or ſeed-bud, which exiſts before the burſting of the anthers, and is, in fact, the rudiments of the ſeed-veſſel, vulgarly called the fruit. This is the baſe or lower part of the pointal.

II. The ſtyle or *vagina*, elevated by the ſeed-bud. From the number of ſtyles, not of ſeed-buds, ariſe the orders or ſecondary diviſions in the Sexual Method.

III. The *ſtigma*, or ſummit of the ſtyle, which receives the *pollen* or male duſt, upon its diſperſion by the burſting of the *anthers*, and tranſmits it elaborated to the ſeed-bud below.

Each of theſe principal parts of the flower is particularly explained under its reſpective term.

PLACENTATIO, a term of habit, expreſſive of the diſpoſition of the ſide-lobes of the ſeed, or ſeminal leaves, about the time of the ſprouting of the embryo plant. *Vide* COTYLEDONES.

Some plants have no ſeed-leaves, ſome have one, but the greater number riſe with two. *Vide* ACOTYLEDONES, MONOCOTYLEDONES, and DICOTYLEDONES.

PLANIPITALÆ, (from *planus*, flat, plain, and *petalum*, a petal or flower-leaf,) the name of a claſs in Ray's Method, conſiſting of plants with compound flowers, compoſed of florets with flat or plain tongue-ſhaped petals. The term is exemplified in ſuccory, dandelion an hawkweed, and correſponds to the *ſemiflоſculoſi* of Tournefort.

PLENUS *flos*, a full flower; a term expreſſive of the higheſt degree of luxuriance in flowers. The petals in full flowers are ſo multiplied, as to exclude all the ſtamina, and frequently

frequently to choak up the female organ, ſo that ſuch flowers, although the moſt delightful to the eye, are both vegetable monſters and vegetable eunuchs: the unnatural increaſe of the petals conſtituting the firſt; the conſequent excluſion of the ſtamina or male organs, the latter.

Flowers with more petals than one are moſt liable to this, as well as the inferior degrees of luxuriance. The following are well-known examples; ranunculus, anemone, marſh-marigold, columbine, fennel-flower, poppy, pæony, pink, gilliflower, campion, viſcous campion, lily, crown imperial, tulip, narciſſus, rocket, mallow, Syrian mallow, apple, pear, peach, cherry, almond, myrtle, roſe, and ſtrawberry.

Flowers with one petal are more rarely ſubject to fullneſs. That they are not, however, totally exempted, appears from polianthes, hyacinth, primroſe, crocus, meadow-ſaffron, and thorn-apple. With theſe familiar examples before his eyes, Kramer did not heſitate to aſſert, that a full flower with one petal, is a contradiction in terms.

In flowers with one petal, the mode of luxuriance, or impletion, is, by a multiplication of the diviſions of the limb or upper part; in flowers with more petals than one, by a multiplication of the petals or nectarium.

To take a few examples: columbine is rendered full in three different ways; 1. by the multiplication of its petals, and total excluſion of the nectaria; 2. by the multiplication of the nectaria, and excluſion of the petals; or, 3. by ſuch an increaſe of the nectaria only, as does not exclude the petals, between each of which are interjected three nectaria, placed one within another. Again, fennel-flower is rendered full, by an increaſe of the nectaria only; narciſſus either by a multiplication of its cup and petals, or of its cup only; lark-ſpur, commonly by an increaſe of the petals, and excluſion of the ſpur, which is its nectarium. In *ſaponaria concava anglica*, the impletion is attended with the ſingular effect of incorporating the petals, and reducing their number from five to one; and in gelder-roſe, the luxuriance is effected by an increaſe both in magnitude, and

number of the plain, wheel-ſhaped, barren-florets of the circumference of the head of flowers, and an excluſion of all the bell-ſhaped hermaphrodite florets of the centre.

Hitherto we have treated of plenitude in ſimple flowers only: the inſtance juſt now adduced ſeems to connect the different modes of impletion in them and compound flowers. Before I proceed further, however, it will not be improper to premiſe, that as a ſimple luxuriant flower is frequently, by beginners, miſtaken for a compound flower in a natural ſtate, ſuch flowers may always be diſtinguiſhed with certainty by this rule: that in ſimple flowers, however luxuriant, there is but one *piſtillum* or female organ; whereas in compound flowers each floret, or partial flower, is furniſhed with its own proper *piſtillum*. Thus in hawk-weed, a compound flower, each flat or tongue-ſhaped floret in the aggregate has its five *ſtamina* and naked ſeed; which laſt is, in effect, its *piſtillum*: whereas, in a luxuriant lychnis, which is a ſimple flower, there is found only one *piſtillum* or female organ common to the whole.

In a compound radiated flower, which generally conſiſts of plain florets in the radius, and tubular or hollow florets in the diſk, plenitude is effected either by an increaſe of the florets in the margin, and a total excluſion of thoſe in the centre; which mode of luxuriance is termed impletion by the radius, and reſembles what happens in the gelder-roſe; or by an elongation of the hollow florets in the centre, and a leſs profound diviſion of their brims; which is termed impletion by the diſk.

In the firſt mode of luxuriance, the florets in the centre, which are always hermaphrodite or male, are entirely excluded; and in their place ſucceed florets ſimilar in ſex to thoſe of the *radius*. Now, as the florets in the margin of a radiated compound flower are found to be always either female, that is, furniſhed with the *piſtillum* only; or neuter, that is, furniſhed with neither *ſtamina* nor *piſtillum*; it is evident, that a radiated compound flower, filled by the *radius*, will either be entirely female, as in fever-few, daiſy, and African marigold; or entirely neuter, as in ſun-flower,

marigold,

marigold, and centaury. Hence it will always be eaſy to diſtinguiſh ſuch a luxuriant flower from a compound flower with plain florets in a natural ſtate; as theſe florets are all hermaphrodite, that is, furniſhed with both *ſtamina* and *piſtillum*. Thus the full flowers of African marigold have each floret furniſhed with the *piſtillum* or female organ only: the natural flowers of dandelion, which, like the former, is compoſed of plain florets, are furniſhed with both *ſtamina* and *piſtillum*.

In the ſecond mode of luxuriance, termed impletion by the diſk, the florets in the margin ſometimes remain unchanged; but moſt commonly adopt the figure of thoſe in the centre, without, however, ſuffering any alteration in point of ſex; ſo that confuſion is leſs to be apprehended from this mode of luxuriance than from the former. Beſides, the length to which the florets in the centre run out, is, of itſelf, a ſufficient diſtinction, and adapted to excite at once an idea of luxuriance. Daiſy, fever-few, and African marigold, exhibit inſtances of this as well as of the former mode of impletion.

In luxuriant compound flowers with plain florets, the *ſemiflo ſculoſi* of Tournefort, the *ſtigma* or ſummit of the ſtyle in each floret is lengthened, and the ſeed-buds are enlarged and diverge; by which characters ſuch flowers may always be diſtinguiſhed from flowers of the ſame kind in a natural ſtate. Scorzonera, nipple-wort, and goat's-beard, furniſh frequent inſtances of the plenitude alluded to.

Laſtly, the impletion of compound flowers with tubular or hollow florets, the *flo ſculoſi* of Tournefort, ſeems to obſerve the ſame rules as that of radiated flowers juſt delivered. In everlaſting flower, the *xeranthemum* of Linnæus, the impletion is ſingular, being effected by the enlargement and expanſion of the inward chaffy ſcales of the calyx. Theſe ſcales, which become coloured, are greatly augmented in length, ſo as to over-top the florets, which are ſcarce larger than thoſe of the ſame flower in a natural ſtate. The florets too in the margin, which in the natural flower are female, become, by luxuriance, barren; that is, are deprived of the

piſtillum; the ſtyle, which was very ſhort, ſpreads, and is of the length of the chaffy ſcales, and its ſummits, formerly two in number, are metamorphoſed into one.

Full flowers are more eaſily referred to their reſpective genera in methods founded upon the calyx, as the flower-cup generally remains unaffected by this higheſt degree of luxuriance.

PLUMULA, a little feather; the ſcaly part of the *corculum* or embryo plant within the ſeed, which aſcends and becomes the ſtem or trunk. It extends itſelf into the cavity of the lobes, and is terminated by a ſmall branch reſembling a feather, from which it derives its name. *Vide* CORCULUM and GERMINATIO.

POLLEN, properly fine flower, or the duſt that flieth in the mill. By Columella it is uſed of the fine duſt or powder of frankincenſe—in Botany, the fecundating or fertilizing duſt contained within the anthers or tops of the *ſtamina*, and diſperſed upon the female organ when ripe, for the purpoſe of impregnation. *Vide* SEXUS *Plantarum*.

This duſt correſponding to the ſeminal fluid in animals, is commonly of a yellow colour, and very conſpicuous in the ſummits of ſome flowers, as tulip and lily. Its particles are very minute, and of extreme hardneſs. Examined by the microſcope, they are generally found to aſſume ſome determinate form, which often predominates, not through all the ſpecies of a particular genus only, but alſo through the genera of a natural family or order.

The powder in queſtion being triturated and otherwiſe prepared in the ſtomach of the bees, by whom great quantities are collected in the hairy bruſhes with which their legs are covered, is ſuppoſed by ſome authors to produce the ſubſtance known by the name of wax; a ſpecies of vegetable oil, rendered concrete by the preſence of an acid, which muſt be removed before the ſubſtance can be rendered fluid.

POLYADELPHIA (πολυς, many, and ἀδελφία, a brotherhood) many brotherhoods. The name of the eighteenth claſs in Linnæus's Sexual Syſtem, conſiſting of plants with hermaphrodite

hermaphrodite flowers, in which ſeveral *ſtamina* or male organs are united by their filaments into three or more diſtinct bundles.

This claſs, which contains very few genera, is ſubdivided into four orders from the number of *ſtamina*.

Chocolate-nut has five *ſtamina*, or rather five bundles of *ſtamina*, each filament having five *anthers* or tops.

Manſonia has fifteen *ſtamina* in five bundles.

Citron, orange, and lemon, which belong to the ſame genus, *citrus*, have twenty *ſtamina* formed into a great number of bundles.

Melaleuca, *hopea*, St. John's wort, and St. Peter's wort, have many *ſtamina*, which, in the three former, are collected into five, in the latter, into four bundles.

POLYANDRIA (πολυς, many, and ἀνηρ, a man, or huſband) many huſbands; the name of the thirteenth claſs in Linnæus's Sexual Method, conſiſting of plants with hermaphrodite flowers furniſhed with ſeveral *ſtamina* that are inſerted into the common receptacle of the flower. By this circumſtance chiefly, though not expreſſed in the title, is the claſs under conſideration diſtinguiſhed from that immediately preceding it, termed *icoſandria*, in which, although a numeral claſs, the moſt ſtriking character is the ſituation of the *ſtamina*, which are inſerted into the calyx or petals, or both. The number of *ſtamina* in the two claſſes being indeterminate, would frequently claſh, and hence create miſtakes: their inſertion is an invariable character, and therefore an unerring mark of diſtinction.

This numerous claſs of plants, the fruits of which are frequently poiſonous, is ſubdivided into ſeven orders, from the number of the ſtyles or female organs.

Poppy, herb-chriſtopher, rock-roſe, and water-lily, have one female organ.

Pæony, and *calligonum*, have two ſtyles, or female organs.

Lark-ſpur, and monk's-hood, have three; *tetracera* has four.

Columbine,

Columbine, and fennel-flower, have five; water-ſoldier, or marſh-aloe, ſix; virgin's-bower, meadow-rue, hellebore, marſh-marigold, anemone, globe-ranunculus, cuſtard-apple, tulip-tree, magnolia, ranunculus, and adonis, have many ſtyles.

POLYANGIÆ (πολυς, many, and ἀγγ, a veſſel) the name of the twentieth claſs in Boerhaave's Method, conſiſting of plants which have many capſules, or a ſingle capſule divided into numerous cells. It is exemplified in marſh-marigold, hellebore, globe-ranunculus, and water-lily.

POLYGAMIA (πολυς, many, and γαμ, marriage) polygamy. This term, expreſſing an inter-communication of ſexes, is applied, by Linnæus, both to plants and flowers. A polygamous plant is that which bears both hermaphrodite flowers and male or female, or both. This will be particularly explained below. Polygamy of flowers reſpects the inter-communication of the florets in a compound flower. The different modes of polygamy in compound flowers, ariſing from the different combinations of ſexes, have been adopted by Linnæus as very proper circumſtances, in a method founded upon the ſexes, for ſubdividing that numerous and difficult claſs of plants. The ſubject, therefore, of the polygamy of flowers falls more properly to be handled under the article SYNGENESIA, whither we refer our readers.

POLYGAMIA, is likewiſe the name of the twenty-third claſs in Linnæus's Sexual Method, conſiſting of polygamous, or mongrel plants, that is, plants having hermaphrodite flowers, and likewiſe male or female flowers, or both.

A plant to be polygamous muſt have ſome of its flowers hermaphrodite: for by that circumſtance alone is its connection cut off with the plants of the claſſes *monœcia* and *diœcia*, in the former of which the plants are androgynous, that is, bear male and female flowers upon the ſame root; in the latter, male and female. This rule, however, admits of a few exceptions, which will be mentioned afterwards.

wards. Further, the polygamy may be either on the ſame plant, or on diſtinct plants from the ſame ſeed. The modes of which it is ſuſceptible, are as follows:

I. Hermaphrodite and male flowers on the ſame plant, as in white hellebore, nettle-tree, croſs-wort, and ægilops. This kind of polygamy is likewiſe obſervable in ſeveral of the umbelliferous plants, particularly carrot, ſanicle, hog's-fennel, coriander, chervil, ſhepherd's-needle, Alexanders, carui, and baſtard-parſley. Theſe plants, therefore, ought, in ſtrict conformity to the principles of the Sexual Method, to have been arranged under the claſs *polygamia*; though I think Linnæus has judged far better to place them with the other umbelliferous flowers, as ſo unnatural a ſeparation muſt have ſtruck a fatal blow at the very root of his ſyſtem. It is evident, however, that the ſame objection continues in force againſt the principles of his method; ſince, if carried into rigid execution, they have a direct tendency to commit the moſt violent outrages againſt Nature, by disjoining things which were never meant to be ſeparated.

II. Hermaphrodite, and male flowers on diſtinct plants, as in palmetto, ginſeng, Indian-date plum, and tupelo-tree.

III. Hermaphrodite and female on the ſame plant, as in pellitory and orach.

IV. Hermaphrodite and female on different plants, as in moſt ſpecies of aſh-tree.

V. Androgynous and male upon diſtinct roots, as in *arctopus*, and amber-tree, which have male and female flowers upon one plant, and male flowers only on the other.

VI. Androgynous, male and female upon three diſtinct plants, as in carob-tree and fig-tree. This and the former caſe, having no hermaphrodite flowers, ſeem to be exceptions to the definition of polygamous plants given above.

VII. Hermaphrodite, male and female upon two diſtinct plants, as in three-thorned *acacia*, in which the male and hermaphrodite flowers are placed upon one plant, and the female flowers on the other.

VIII.

VIII. Male hermaphrodites, and female hermaphrodites on the ſame plant; that is, flowers which, although they contain the parts proper to each ſex, have one of the parts reciprocally abortive; the *ſtamina* or male organ in ſome, the *piſtillum* or female organ in others. In the former caſe they are ſtiled female hermaphrodites, in the latter, male hermaphrodites, according as either ſex is predominant. This ſingular mode of polygamy, if it can be called ſuch, is obſerved in the flowers of plantain or banana tree.

POLYSPERMÆ, (πολυς, many, and σπερμα, a ſeed) the name of the fifteenth claſs in Ray's Method, conſiſting of plants with many capſules or ſeeds. It is exemplified in marſh-marigold, hellebore, and globe ranunculus.

POLYSTEMONES (πολυς, many, and στημων, a ſtamen) the name of the eighth claſs in Haller's Natural Method, conſiſting of plants which, as the name imports, have many *ſtamina* or male organs. It is exemplified in poppy, ranunculus, mallow, cherry, and roſe. The *ſtamina* in this claſs are generally triple the number of petals.

POMACEÆ (*pomum*, an apple) the name of the thirty-ſixth order in Linnæus's Fragments of a Natural Method, conſiſting of the following genera, which have a pulpy eſculent fruit of the apple, berry, and cherry kind.

	Linnæan Genera.			*Engliſh Names.*
α	*Cratægus*,	—	—	Wild-ſervice thorn.
	Meſpilus,	—	—	Medlar.
	Pyrus,	—	—	Apple, pear.
	Ribes,	—	—	Currant-tree.
	Sorbus,	—	—	Service-tree.
	Spiræa,	—	—	Spiræa frutex, ſpiked willow, drop-wort.
β	*Punica*,	—	—	Pomegranate.
γ	*Amygdalus*,	—	—	Almond-tree, peach.
	Chryſobalanus,	—	—	Cocoa-plum.
	Prunus,	—	—	Plum, apricot, cherry.

Habit and Structure of the Plants of this Order.

The plants of this order, which furniſhes many of our moſt eſteemed fruits, are moſtly of the ſhrub and tree kind.

The ROOTS are branched, fibrous, and in the greater part very long. In dropwort, the *ſpiræa filipendula* of Linnæus, they conſiſt of a great number of oval knobs or glandules, which hang, or are faſtened together by ſlender fibres; from which circumſtance are derived both its Engliſh and ſcientific names.

The STEMS and branches are cylindric. Theſe laſt are placed alternate; and, when young, are, in ſome genera, angular. The bark is thick and wrinkled.

The BUDS are of a conic form, placed in the angles of the leaves, and covered with ſcales which lie over one another like tiles. In apple, pear, plum, apricot, cherry, almond, and peach trees, beſides the buds of the leaves, there are ſcaly buds, or eyes, of a different form, from which proceed bundles or cluſters of flowers. *Vide* GEMMA.

The LEAVES, which differ in form, being in ſome genera ſimple, in others winged, are, in the greater number, placed alternate. Thoſe of medlar, wild-ſervice, ſpiræa with marſh-elder leaves, and ſome others, have their ſurface covered with ſmall ſhining ſpots, which reſemble minute points or holes.

The foot-ſtalk of the leaves is furrowed above, and frequently accompanied, as in the cherry-tree, with a number of knobs in the form of glands.

Moſt of theſe plants are furniſhed with two STIPULÆ at the origin of the young foot-ſtalks of the leaves. Theſe, in ſome genera, are pretty large; in others they are ſo ſmall as ſcarce to be perceived; and in cocoa-plum, in particular, they, by their minuteneſs, reſemble hairs. In apple, prune, cherry, and almond-trees, the appearances in queſtion fall off before the leaves.

The

The branches of apple, pear, and medlar trees are terminated by a thorn. The ſtem of hawthorn and bullace-tree, a ſpecies of *prunus*, is cloſely armed with offenſive weapons of the ſame kind. Theſe ſpines, however, though protruded from the wood, totally diſappear by culture.

The FLOWERS are univerſally hermaphrodite, except in *ſpiræa aruncus*, in which male and female flowers are produced upon diſtinct plants.

In the greater number of genera they are produced in cluſters or heads (*corymbi*) at the end of the branches. Many of theſe flowers are eaſily rendered double by culture.

The FLOWER-CUP is of one piece with five diviſions, which are permanent, and placed above the ſeed-bud in ſpiræa, apple, pomegranate, ſervice, wild-ſervice, medlar, and currant-trees; in the reſt they either fall off with the flower, or wither upon the ſtalk.

The PETALS are five number, and inſerted into the tube of the calyx.

The STAMINA are generally twenty and upwards, and attached, like the petals, to the margin of the tube of the calyx.

The ANTHERS are ſhort, and ſlightly attached to the filaments.

The SEED-BUD is ſingle, and in thoſe genera which have the calyx permanent, it is placed below the receptacle of the flower.

The SEED-VESSEL is a pulpy fruit of the apple, berry, or cherry kind. Thoſe of the apple kind are divided internally into a number of cells. Pomegranate has nine cells, apple and pear five.

The SEEDS in pomegranate, apple, and currant-trees, are numerous; in ſervice-tree, three; in medlar, five; in wild-ſervice, two; in peach, plum, and cocoa-plum, a ſingle nut, or ſtone, containing a kernel.

The pulpy fruits of this order of plants are acid, eſculent, and of great efficacy in putrid and bilious fevers.

The

The kernels of plums, cherries, and almonds, contain a great quantity of oil, and, when bitter, are ſaid to be highly pernicious to certain animals, particularly birds which feed on them. The fruit of the wild apple-tree yields, by expreſſion, an acid juice, which being fermented, becomes an agreeable vinous liquor. Medlars are aſtringent and diuretic. The flowers of peach-tree are a gentle purgative. The gum of cherry and peach-trees may be ſubſtituted for gum-arabic, which, however, is greatly preferable. The wood of bird-cherry is ſudorific, yet rarely uſed in medicine. From bitter almonds is drawn by expreſſion an oil, which is anodyne, and highly proper in deafneſs, and pains of the ear.

POMIFERÆ, (*pomum*, an apple, and *fero*, to bear) the name of a claſs in Hermannus, Boerhaave, and Ray's Methods, conſiſting of plants which have a fleſhy fruit of the apple kind. It is exemplified in the pear, and pomegranate-trees.

POMUM, an apple; a ſpecies of ſeed-veſſel, compoſed of a ſucculent fleſhy pulp, in the middle of which is generally found a membranous capſule, with a number of cavities for containing the ſeeds. Seed-veſſels of this kind have no external opening or valve. At the end oppoſite to the foot-ſtalk is frequently a ſmall cavity, called by gardeners the eye of the fruit, and by botaniſts, *umbilicus*, the navel, from its fancied reſemblance to the navel in animals. Gourd, cucumber, melon, pomegranate, pear, and apple, furniſh inſtances of the ſeed-veſſel in queſtion.

PRECIÆ, (*precius*, early); the name of the twenty-firſt order in Linnæus's Fragments of a Natural Method; conſiſting of primroſe, an early flowering-plant, and a few genera which agree with it in habit and ſtructure, though not always in the character or circumſtance expreſſed in the title.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Androſace.			
Aretia.			
Cortuſa,	—	—	Bear's-ear ſanicle.
Cyclamen,	—	—	Sow-bread.
Diapenſia.			
Dodecatheon,	—	—	Meadia.
Primula,	—	—	Primroſe, auricula.
Soldanella,	—	—	Soldanel.
β *Limoſella,*	—	—	Leaſt water-plantain.
γ *Hottonia,*	—	—	Water milfoil, or water-violet.
Menyanthes,	—	—	Bog-bean, or marſh-trefoil.
Samolus,	—	—	Round-leaved water-pimpernel.

Theſe plants, which poſſeſs no ſtriking uniform characters, are, in general, innocent in their quality; yet the root of ſow-bread is dangerous, if taken internally.

PROLIFER *flos*; (*proles*, an offſpring, and *fero*, to bear); a prolific flower, or flower which from its own ſubſtance produces another; a ſingular degree of luxuriance, to which full flowers are chiefly incident.

In ſimple flowers, the prolification ariſes from the ſeed-bud of the parent or full flower ſhooting up into another flower; in which caſe, a ſingle foot-ſtalk only is protruded: in compound and aggregate flowers properly ſo called, it ariſes from the common calyx, from all parts of which are ſent forth many foot-ſtalks, each ſupporting a ſingle flower. Examples of the former mode of luxuriance are frequent in ranunculus, anemone, pink, roſe, and herb-bennet: of the latter, in daiſy, hawkweed, marigold, and ſcabious.

Simple umbelliferous flowers become prolific, by the production of another ſimple umbel from their centre; as in the *Cornus Meſomora* of Rivinus. In milk-parſley, and wild carrot, is protruded from the centre of the compound umbel,

bel, another univerſal umbel which overtops the former. By a further exertion of the ſame cauſe it is eaſy to conceive that this laſt umbel may likewiſe be rendered prolific; and thus a triple crown of heads of flowers be erected, each growing out of the one immediately below it.

Prolific flowers are ſaid to be frondoſe or leafy, which produce branches charged with both leaves and flowers. Inſtances of this mode of luxuriance, though rare, are ſometimes obſerved in roſe and anemone. In the full flowers of cherry-tree, the ſeed-bud frequently ſhoots up by luxuriance into a number of leaves.

PROPAGO, (properly a ſlip, layer, or cutting of a vine, or other tree; thus Virgil—"*Melius propagine vites reſpondent.*" Georg. 2. 63.) Linnæus's name for the ſeeds of the moſſes. *Vide* MUSCI.

PUBES, hair, down, a general term, expreſſive of all the hairy and glandular appearances on the ſurface of plants, to which they are ſuppoſed by naturaliſts to ſerve the double purpoſe of defenſive weapons, and veſſels of ſecretion. The different ſpecies of *Pubes* enumerated by Linnæus, are,

I. PILI, hairs.
II. LANA, wool.
III. *Barba*, a beard, or tuft of hair.
IV. TOMENTUM, a hoary, ſilver-white appearance.
V. *Strigæ*, } briſtles.
VI. *Setæ*, }
VII. HAMI, hooks.
VIII. GLANDULÆ, glands.
IX. *Glochides*, pointed hairs.
X. *Viſcoſitas*, clammineſs.
XI. *Glutinoſitas*, ſtiff clammineſs.

Many of theſe terms it is impoſſible to define with accuracy, as their differences are ſo minute, that an adequate idea of the appearances can only be obtained by ſight. The more ſtriking kinds of *Pubes*, ſuch as *tomentum*, *glandulæ*, &c. are each particularly explained under its reſpective head.

In general, it may be obſerved, that hairs are minute

threads, of greater or leſs length and ſolidity, ſome of which are viſible to the naked eye, whilſt others are rendered viſible only by the help of glaſſes. Examined by a microſcope, almoſt all the parts of plants, particularly the young ſtalks, appear covered with hairs.

Hairs on the ſurface of plants preſent themſelves under various forms: in the leguminous plants, they are generally cylindric; in the mallow tribe, terminated in a point; in agrimony, ſhaped like a fiſh-hook; in nettle, awl-ſhaped, and jointed; and in ſome compound flowers with hollow or funnel-ſhaped florets, they end in two crooked points.

Probable, as ſome experiments have rendered it, that the hairs on the ſurface of plants contribute to ſome organical ſecretion, their principal uſe ſeems to be, to preſerve the parts in which they are lodged from the bad effects of violent frictions, from winds, from extremes of heat and cold, and ſuch like external injuries.

M. Guettard, who has eſtabliſhed a botanical method from the form, ſituation, and other circumſtances of the hairy and glandular appearances on the ſurface of plants, has demonſtrated, that theſe appearances are generally conſtant and uniform in all the plants of the ſame genus. The ſame uniformity ſeems, ſometimes, to characterize all the genera of the ſame natural order.

The different ſorts of hairs which form the down upon the ſurface of plants were imperfectly diſtinguiſhed by Grew, in 1682, and by Malpighi, in 1686. M. Guettard, juſt mentioned, was the firſt who examined the ſubject, both as a botaniſt and a philoſopher. His obſervations were publiſhed in 1747.

PUBESCENTIA, (*pubes*, hair, down) pubeſcence, or hairineſs; a general term of habit, expreſſive of every kind of armature, whether offenſive or defenſive, with which plants are furniſhed. The term, which is highly improper to be uſed with ſuch latitude, is omitted in the later editions of Linnæus's works; the terms *pubes* and *arma*, its conſtituent parts, ſupplying its place.

PULMONES, the lungs. By this name, Linnæus, in aſſimilating

aſſimilating the animal and vegetable kingdoms, has diſtinguiſhed the leaves, the organs of perſpiration, and reſpiration in plants.

PUTAMINEÆ, (*putamen*, a ſhell) the name of the twenty-fifth order in Linnæus's Fragments of a Natural Method; conſiſting of a few genera of plants, allied in habit, whoſe fleſhy ſeed-veſſel, or fruit, is frequently covered with a hard woody ſhell.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Capparis,	—	—	Caper-buſh.
Cleome,	—	—	Baſtard-muſtard.
Cratæva,	—	—	Garlick-pear.
Creſcentia,	—	—	Calabaſh-tree.
Marcgravia.			
Moriſonia.			

Moſt of theſe plants are acrid, and penetrating, and yield, by burning, a great quantity of fixed alkali.

With reſpect to their virtues, they are powerful aperients. The Indians pretend that the fruit of a ſpecies of caper-buſh, which they call baducca, extinguiſhes the flames of love.

Ptiſans, baths, and fumigations of theſe plants, are greatly uſed by the Negroes at Senegal for venereal complaints, palſies, and diſtempers of the ſkin. Baſtard-muſtard is adminiſtered in leproſies in the Levant.

In default of the leaves of baobab, the Negroes on the coaſt of Guinea mix thoſe of garlick pear-tree, which ſmell very ſtrong, in their ordinary food called couſcous.

The flower-buds of caper-buſh, preſerved with vinegar, furniſh the pickle well known by the name of capers.

The fruit called calabaſh, is of two kinds, the one ſmall and round, the other large and oval. The trees which bear both fruits are as large and ſpreading as an apple-tree. The fruit, when largeſt, is about the ſize of a man's head, and

when carefully cleared of its pulp, capable of holding fifteen pints of water, or other liquid, for which purpoſe its ſcooped ſhell, which is as thin and light as brown paper, is chiefly uſed by the inhabitants of the Weſt-Indies. At Barbadoes, beſides drinking-cups and punch-bowls, there are made of the calabaſh-ſhells, ſpoons, diſhes, and other eating utenſils for the ſlaves: the pulp is ſoft, ſour, and unſavoury, and ſeldom eaten, except by the cattle, in time of drought: the wood, which is hard and ſmooth, is frequently made into ſtools, chairs, and other furniture.

The leaves and fruit of *cratæva* ſmell ſtrongly of garlick; whence the name of garlick pear-tree by which this genus has been diſtinguiſhed. The fruit, which in one ſpecies is ſmooth, and in the other, prickly, grows to the ſize of an orange, and has its inſide filled with an agreeable pulp, interſperſed with ſmall granulated ſeeds. The tender buds from the young branches being bruiſed, and applied as a plaſter to any part of the body, will, in time, raiſe as regular a bliſter as that occaſioned by cantharides.

R.

RACEMUS, properly ſignifies a bunch or cluſter of grapes. In a ſcientific ſenſe it is uſed to ſignify a mode of flowering, in which, the flowers placed along a common foot-ſtalk, are furniſhed with ſhort proper foot-ſtalks, proceeding as lateral branches from the common flower-ſtalk. It is exemplified in the vine and currant-tree.

A cluſter reſembles a ſpike, in having its flowers placed along the ſides of a common foot-ſtalk, but differs from it in being furniſhed with proper flower ſtalks; whereas the flowers of the ſpike are placed immediately upon the ſides of the common foot-ſtalk, and are ſeldom produced in ſuch abundance. *Vide* SPICA.

Again, a cluſter differs from that mode of flowering termed a corymbus, in the ſhortneſs and equal length of its branches or proper flower-ſtalks, which in thoſe of the corymbus, riſe to ſuch a proportionable height, as to form

an

an even ſurface at top; by which means, each lower flower-ſtalk is conſiderably longer than that immediately above it. *Vide* CORYMBUS.

RADIATUS *flos*. *Vide* COMPOSITUS *flos*.

RADIATI, the name of the fourteenth claſs in Tournefort's Method, conſiſting of compound radiated flowers, that is, compound flowers with plain florets in the margin, and hollow florets in the centre. It is exemplified in groundſel, feverfew, milfoil, marigold, and daiſy.

RADICATIO, (*radix*, a root) a term of habit, expreſſive of the form and diſpoſition of the root. *Vide* BULBUS and RADIX.

RADICULA, (diminutive from *radix*, a root) a little root: the ſtringy or fibrous part of the root, which generally terminates the ſtock or main root, and penetrating into the ſoil, attracts moiſture and nouriſhment for the ſupport of the vegetable. The radicle is, in fact, the principal and eſſential part of every root, and is therefore never wanting, not even in thoſe plants improperly ſtiled imperfect: for the moſſes, lichens, and ſubmarine plants, diſcover a remarkable analogy in the *lamellæ* and *ſtriæ*, by which they adhere to the bodies placed under them, to the radicles, or ſtringy fibres, which are preſent in other plants.

RADIUS. *Vide* COMPOSITUS *flos*.

RADIX, the root; the lower part of the plant, generally hid below the ſurface of the earth, and deſtined for attracting the moiſture from the ſoil, and communicating it to the other parts, *viz.* the herb and the fructification which are produced from it.

The root conſiſts of two parts; the *caudex*, ſtock, or main root, and the *radiculæ*, or ſmall ſtringy roots, depending from the other. *Vide* CAUDEX and RADICULA.

Main roots, with reſpect to form, are of three kinds; bulbous, tuberous, and fibrous. The firſt ſort has been fully conſidered under the head BULBUS.

Tuberous or knobbed roots, are fleſhy, ſolid, hard, commonly thicker than the baſe of the ſtem, and compoſed either of one knob, as in radiſh, turnip, and carrot; or, of

many collected into a bunch, as in pœony, ſun-flower, and drop-wort: in the laſt of which plants, ſeveral ſmall roundiſh bodies hang, or are faſtened together by a number of ſlender ſtrings, or filaments.

In tuberous roots, the radicles or ſmall ſtringy roots are generally diſperſed over the whole ſurface: in which reſpect, they differ eſſentially from bulbous roots, in which the radicles are confined to the bottom of the bulb, that part only being the genuine root; the bulb itſelf ſerving as a large bud under ground, for incloſing and protecting the embryo plant.

The roots of arum, orchis, moſchatelline, and ſome other plants, although tuberous, emit fibres at the top, from a knot formed berwixt the trunk and the thicker part of the root. Such roots, from the fibres which adhere to the top of the fleſhy maſs reſembling a buſh of hair, have been diſtinguiſhed by the name of *radices comoſæ*.

Fibrous roots are ſlenderer than the baſe of the trunk, and are either divided by equal branches, as in the greater number of trees, in which, likewiſe, the ſubſtance is woody; or conſiſt of a number of ſingle fibres like hairs, which proceed from the ſmall knot, or baſe of the ſtem, as in many graſſes. This laſt kind of fibrous root is termed *radix capillacea*.

With reſpect to direction, roots are ſaid to be perpendicular, which run directly downwards. The term is moſt commonly applied to a particular kind of root, which, not exceeding in dimenſion the baſis of the ſtem, deſcends perpendicularly downwards in one ſtraight fibre that is thicker in the upper part, and gradually tapers downwards. It is exemplified in carrot, parſnep, radiſh, and ſuch like roots, which, from their tapering ſhape, have properly enough obtained the name of *radices fuſiformes*, or ſpindle-ſhaped roots.

Spindle-ſhaped roots are a ſpecies of tuberous root, as appears from the ſituation of the ſtrings or fibres, which are diſperſed over the whole ſurface of the ſtock or principal root, and divided into numerous branches, which, after ſeveral ſubdiviſions, become as fine as hairs. This kind of

tapering

tapering root is frequently changed by culture into a round, knobbed, or tuberous root properly ſo called, as in ſome umbelliferous plants.

Horizontal, level, or tranſverſe roots, extend themſelves horizontally under the ſurface of the ground; as in iris, maſterwort, hop, biſhop's weed, cinquefoil, and all ſuch as properly creep.

Of horizontal roots, ſome run very near the turf, as woodbine and wild anemone: others lower down, as couch-graſs.

Of perpendicular roots, ſome ſtrike down but a little way, as thorn-apple: others pierce deep, as horſe-radiſh.

The direction of roots is alſo ſometimes compounded. Thus, the main root or ſtock of primroſe, is level; the radicles, or ſtrings, run perpendicular.

With reſpect to diviſion, roots are entire, as liquorice, or parted, as St. John's wort, forked or parted at the bottom, as in moſt roots, or at the top, as in dandelion, and ſome others.

The roots in radiſh are ſtraight: in biſtort, crooked; in rhubarb, thick; in vine, ſlender; long, in fennel; ſhort, in turnip; in eryngo, cylindrical; in borage, pyramidal. Some are uneven and pitted, as potatoes, where the eyes, or buds of the future trunk, lie inward; or knotty, as Jeruſalem artichoke, where they ſtand out.

Roots, in point of duration, are either annual, biennial, or perennial; that is, of one, two, or many years continuance: the two firſt are attributes of herbaceous vegetables only; the latter, is applicable both to herbs and trees. In ſome plants, both root and ſtem ſubſiſt for many years. Of this kind are all trees; the roots of which may be termed, by way of diſtinction, *radices fruticoſæ*. In others, the roots only ſubſiſt during the winter, whilſt the ſtalks, which decay and periſh, are annually renewed from the root. Of this kind, are all thoſe herbs, from this circumſtance termed perennial. Biennials renew their ſtalk only twice; annuals exiſt but for a year, at the end of which time, both ſtem

and root periſh, and the individual is at an end. Theſe laſt as is evident, can only be propagated from ſeed.

Uniform and conſtant as Nature is in all her productions, there are many perennial roots which become annual, when tranſplanted into cold climates. Nay, there are not wanting examples of ſhrubs loſing their ſtems annually in ſuch climates, in the ſame manner as the ſtalks of herbaceous vegetables periſh in autumn, whilſt the root continues in full vigour: ſometimes even, in ſuch circumſtances, the ſhrub not only diveſts itſelf of its woody ſtem, and becomes herbaceous, but is metamorphoſed, in every reſpect, into an annual plant, and loſes both its ſtem and root at the end of one year. (*Vide* Methodus.) Culture, on the other hand, may prolong the life of annuals. Thus, M. Duhamel mentions a root of barley, which put forth new ſtalks after the old ones were cut down in harveſt, and produced a ſpike of flowers the following year.

Among the accidents that happen to roots from an exceſs of culture, or a luxuriance of nouriſhment, may be reckoned the monſtrous appearance of the roots of ſome potatoes, which, although generally ſix inches long, and three broad, are ſometimes found eighteen inches, and two feet long, and one foot in diameter. Thoſe of turnip, in like manner, are ſometimes found increaſed to the enormous ſize of nine or ten inches in diameter, although, in general, they ſeldom exceed three or four.

Roots, as we obſerved in the definition, are generally hid below the ſurface of the ground, and derive their nouriſhment immediately from the ſoil. This is a general law of vegetable nature, but like moſt other general laws, admits of exceptions. The roots of miſtletoe, vanelloe, dodder, *hypociſtis*, and ſome others, do not penetrate into the ſoil, and ſeek nouriſhment for themſelves, but derive it, as by ſtealth, from other plants, to which they attach themſelves. Such plants, from the ſingular circumſtance juſt mentioned, are termed paraſitic.

Miſtletoe and vanelloe cling to the branches of trees, *hypo-*

ciſtis

ciſtis to the roots of plants, particularly of *ciſtus*, or the rock-roſe, whence it derives its name: dodder, to the ſtems of all ſorts of plants, though it is generally known by the name of *epithymum*, or thyme-weed, as if it were only to be found on the plant of that name.

The manner in which paraſitic plants attach themſelves to others, is not uniform. The ſeed of dodder germinates in the ground, and puts forth a ſtem, which attaches itſelf to the firſt plant it encounters in its progreſs. From this plant it attracts the nouriſhing juices, by means of certain ſecretory glands with which the ſtem is furniſhed. Mean time, the lower part of the ſtem, which is detached from the ſupporting plant, and receives no part of the nouriſhment, dries up; its firſt root dies, and the plant continues to live and be nouriſhed at the expence of that upon which it is fixed.

On the other hand, miſtletoe, vanelloe, and *hypociſtis*, are produced originally upon the plant which affords them nouriſhment: the two former, which grow upon large trees, extend their roots under the bark, and penetrate inſenſibly into the body of the wood.

Other paraſitical plants, conſiſting of ſmall tubercles, emit fibrous roots, which often penetrate the bulbs of ſaffron, extract all the ſubſtance, and hence occaſion the ſudden death of the parent or ſupporting plant.

Some roots attach themſelves to the hardeſt bodies, as the moſſes to the bark of trees, the lichens to ſtones and rocks, nouriſhed, without doubt, by the humidity of the air abſorbed by their leaves, or branches. Other plants ſwim upon the ſurface of the water, as *lemna*, or duck's meat, which grows upon ſtanding waters in moſt parts of England, and, if not diſturbed, will ſoon cover the whole ſurface. Some plants appear to be totally devoid of roots; ſuch are many of the *Algæ*, particularly the genera *Byſſus* and *Tremella*.

In aſſimilating the animal and vegetable kingdoms, Linnæus, properly enough, compares the root in plants to the lacteal veſſels in animals. The ſoil, or earth, is the vegetable ſtomach; the trunk, its bones; the leaves, its lungs; and

and heat its heart: analogies, which probably ſuggeſted the epithet of *inverted animal*, ſo frequently beſtowed upon plants by the ancient naturaliſts.

RECEPTACULUM, (properly, a place to receive or keep things in) one of the ſeven parts of fructification, defined by Linnæus to be the baſe which connects or ſupports the other parts. The different ſpecies of receptacle enumerated by Linnæus are theſe:

I. A PROPER RECEPTACLE, which ſupports the parts of a ſingle fructification. Of this kind is the receptacle of all ſimple flowers.

II. A COMMON RECEPTACLE, which is common to an aggregate or head of flowers. Of this kind is the receptacle of compound and other aggregate flowers. *Vide* AGGREGATUS *flos*.

III. Umbella. } Theſe two would have been more properly denominated MODES of FLOWERING,
IV. Cyma. }
V. Spadix.

The firſt of theſe receptacles only falls to be conſidered in this place. The ſecond, which admits of the greateſt number of varieties, and is chiefly employed in diſcriminating the genera of compound flowers, will naturally enter into the deſcription of that numerous and difficult claſs of plants. The other three, to which the name of receptacle ſeems totally miſapplied, are ſufficiently explained, each under its reſpective head.

A proper receptacle obtains different names from the parts of the fructification which it ſupports and connects. When both flower and fruit are ſupported by it, it is generally ſtiled the receptacle of the fructification, and not ſeldom the common receptacle. This laſt term, though ſomewhat improper, I have generally adopted in deſcribing ſeveral natural orders of ſimple flowers that occur in the courſe of this work. Again, when the receptacle ſupports the parts of the flower only, it is called the receptacle of the flower. In ſuch caſes, the ſeed-bud or fruit, which is placed below the receptacle of the flower, has a proper baſe of its own, which is diſtinguiſhed by the name of receptacle of the fruit.

fruit. Of this French-willow and tree-primroſe furniſh examples.

In ſome ſimple flowers which have the ſeed-bud placed above the receptacle of the flower, the fruit has a ſeparate receptacle. This obſervation is particularly exemplified in magnolia, tulip-tree, cuſtard-apple, and the other genera of the natural order *coadunatæ*, in which the numerous ſeed-buds are ſeated upon a receptacle, which riſes like a pillar above the receptacle of the flower. *Vide* COADUNATÆ.

Again, The term receptacle is often uſed to ſignify the baſe to which the ſeeds are faſtened within their incloſure or veſſel. Inſtances of the application of this term are furniſhed by deadly night-ſhade, winter-cherry, hen-bane, tobacco, thorn-apple, mullein, and many other plants. This ſort of receptacle is commonly known among botaniſts by the name of *placenta*, from its being the common receptacle of the umbilical veſſels, which ſerve to tranſmit the nouriſhment to the ſeeds.

RESUPINATIO. *Vide* INTORSIO.

RHŒADEÆ, (*rhoeas*, Linnæus's name, after Dioſcorides, for the red poppy) the name of the twenty-ſeventh order in Linnæus's Fragments of a Natural Method, conſiſting of poppy, and a few genera which reſemble it in habit and ſtructure.

Liſt of Genera contained in this Natural Order.

Linnæan Genera.			*Engliſh Names.*
Argemone,	—	—	Prickly poppy.
Bocconia.			
Chelidonium,	—	—	Celandine.
Papaver,	—	—	Poppy.
Podophyllum,	—	—	Duck's-foot, or May apple.
Sanguinaria,	—	—	Puccoon.

Theſe plants, upon being cut, emit plentifully a juice, which is white in poppy, and yellow in the others. From the

the inſpiſſated juice of the heads and leaves of black poppy, is prepared the extract well known by the name of opium. The taſte of theſe plants is, in general, acrid and bitter; the petals of poppy are ſomewhat ſweet.

With reſpect to their virtues, they ſeem to operate principally upon the nerves. Their juice is ſodorific and narcotic, their ſeeds leſs ſo, their roots aperient. Applied externally, they are ſlightly corroſive.

A decoction of the roots of prickly poppy is much uſed by the Negroes of Senegal in the early ſtages of the venereal diſeaſe. The juice of celandine applied externally has the ſame effect as that of common fumatory, to deſtroy warts, and cutaneous eruptions. Mixed with a very great quantity of water, it is ſucceſsfully employed as a lotion in weakneſs of ſight, and pains of the eyes. The leaves of wild poppy are put into cooling ointments, being accounted proper for burnings, inflammations, and hot ſwellings.

With the juice of puccoon, the Indians of North-America, where the plant naturally grows, paint themſelves of a yellow colour.

ROSACEI, (*roſa*, a roſe) the name of the ſixth and twenty-firſt claſſes in Tournefort's method, conſiſting of herbs and trees with ſimple flowers, having an indeterminate number of regular petals placed circularly like thoſe of the roſe. The term is exemplified in amaranthus, purſlain, poppy, paſſion-flower and chick-weed.

ROSTELLUM (diminutive from *roſtrum*, a beak) a little bell, beak, or ſnout; the ſcaly part of the *corculum*, or embryo of the ſeed, which ſhoots downward into the ſoil, and becomes the root; its form is that of a ſmall beak placed without the lobes, and adhering internally to the *plumula*, or embryo ſtem. The term is claſſical, and as old as Columella.

ROTACEÆ, (*rota*, a wheel) the name of the twentieth order in Linnæus's Fragments of a Natural Method, conſiſting of plants with one flat wheel-ſhaped petal, (*corolla rotata*). *Vide* COROLLA.

Liſt

Liſt of the Genera *contained in this Order.*

	Linnæan Genera.		*Engliſh Names.*
α	*Anagallis*,	—	— Pimpernel.
	Centunculus.		
	Chironia.		
	Exacum.		
	Gentiana,	—	— Gentian, or fell-wort.
	Lyſimachia,	—	— Looſe-ſtrife.
	Phlox,	—	— Lychnidea, or baſtard lychnis.
	Sarothra,	—	— Baſtard-gentian.
	Swertia,	—	— Marſh-gentian.
	Trientalis,	—	— Winter-green with chick-weed-flowers.
β	*Aſcyrum*,	—	— St. Peter's wort.
	Ciſtus,	—	— Rock-roſe.
	Hypericum,	—	— St. John's wort.

The three laſt genera are very improperly annexed to this order, and indeed, few of the other genera can be ſaid, in ſtrict propriety, to poſſeſs the character ſpecified in the title.

Theſe plants reſemble in quality thoſe of the order PRECIÆ, to which they are in all reſpects very nearly allied.

The root of greater yellow gentian, the *gentiana lutea* of Linnæus, is a well known ſtomachic, and makes a principal ingredient in bitters. The plant grows naturally in the mountainous parts of Germany, from whence the roots are brought to England for medicinal purpoſes. The roots only are uſed. Leſſer centaury of the ſhops, the *gentiana centaurium* of Linnæus, poſſeſſes an operative cleanſing faculty, removes obſtructions, ſtrengthens the ſtomach, and deſtroys worms. Outwardly, it is uſed in fomentations againſt ſwellings and inflammations.

Gum labdanum is an odoriferous balſam or reſin which is found upon a ſpecies of rock-roſe, the *ciſtus ladanifera* of Linnæus, that grows naturally in the Levant. This ſub-

ſtance,

ſtance, which the natives collect by means of leather thongs, rubbed gently over the ſurface of the ſhrub which produces it, is of a very balſamic nature, and uſed in medicine both internally and externally.

From a ſpecies of *Hypericum*, the natives of Louiſiana, we are informed by Boſſu, extract an oil that proves an excellent vulnerary. The following is the Indian method of making it. In an earthen pot they put a proper quantity of the flowers, and ſome bear's oil above it. The pot or vaſe is then well ſtopped, and expoſed to the morning ſun, the heat of which, concentrated in the vaſe, imparts to the incloſed ſubſtance, which turns red, and has a very agreeable ſmell, the quality of purifying and curing all ſorts of wounds.

S.

SAPOR, taſte. An attribute or quality in plants, depending upon an external ſenſe, and, therefore, apparently different even in the ſame individual, according to the ſtate of the organ, which is probably affected by every change of habit in the human body.

The ancients, particularly Ariſtotle, and Theophraſtus, enumerate only ſeven primitive taſtes; theſe are,

I. Sweet.
II. Fat.
III. Acid.
IV. Acrid.
V. Auſtere, or harſh.
VI. Acerb.
VII. Salt, and bitter. Theſe laſt are by Theophraſtus confounded.

To theſe ſeven primitive taſtes of Ariſtotle and Theophraſtus, Pliny has added the following ſix, which, however, appear to be rather intermediate ſteps of thoſe already enumerated than ſimple taſtes.

VIII. Agreeable (*ſuavis*) a mode of *ſweet*.

IX. Poignant,

IX. Poignant, or tart (*acutus*) a leſs degree of *acid*.

X. Bitter (*amarus*) a ſimple taſte, confounded by the Greek naturaliſt, as was obſerved above, with a *ſalt* taſte.

XI. Vinous, a compoſition, according to Pliny, of *ſweet*, *agreeable*, *poignant*, and *auſtere*.

XII. Milky taſte, compoſed of *agreeable* and *fat*.

XIII. Watery, which is almoſt inſipid.

The ſchool of Salernum diſtinguiſhed nine ſimple taſtes, which they characterized by their different temperaments, as follows:

I. Acrid, bitter, and alkaline ſalt. WARM.

II. Watery or inſipid, ſweet, and fat. TEMPERATE.

III. Acid, harſh, or acerb, and acid ſalt. COLD.

The moderns by diſtinguiſhing auſtere from acerb, adding ſome things, and retrenching others, have increaſed the number of ſimple taſtes to ten; which ſtand thus oppoſed to each other.

I. Inſipid or watery	oppoſed to	VI. Acid, or alkaline ſalt.
II. Sweet		VII. Acrid.
III. Fat		VIII. Auſtere.
IV. Viſcous		IX. Acerb.
V. Acid		X. Bitter.

Taſtes are diſtinguiſhed by their quantum of force or intenſity into ſteps or degrees, which are likewiſe, ſometimes, by writers on the Materia Medica, uſed for expreſſing the different temperaments of thoſe taſtes. Thus the ſimple taſte bitter, has been divided into ten degrees; and we ſay, that the root of turmeric is bitter in the firſt or loweſt degree; the ſeed of blue clematis in the tenth or higheſt. In the ſame manner, as a bitter taſte indicates a warm temperament, other degrees or diviſions ariſe from the intenſity of warmth in the inſtances in queſtion: and we ſay, that one is warm in ſuch a degree, and the other in a different. Some taſtes affect the organ of ſenſation ſooner than others which are of a greater degree of intenſity. Acid and bitter taſtes, as vinegar and wormwood, are ſoon felt, and quickly gone. Acrid taſtes are not felt ſo ſoon, and laſt longer. Thus the ſharpneſs of the ſeeds of clematis, although in the tenth de-

gree,

gree, is not ſo quickly perceived, as the bitterneſs of roſes, although only in the ſecond degree. Hot taſtes are ſlower in affecting the organ of ſenſe, and laſt longer than others. Thus the bitterneſs of the roots of black hellebore, which is in the ſecond degree, is perceived on the ſlighteſt contact; but its heat, though in the third or fourth degree, is not felt till after two minutes; in like manner, the bitterneſs of elecampane, although only in the fourth degree, is ſooner felt than its heat, which is in the eighth.

The climax which is obſerved in the perception of taſtes, during its continuance, is different in different objects. The heat of galangal cauſes, at firſt, a ſlight ſenſation, but it is not till the end of one minute that its greateſt force is perceived. Black hellebore does not attain its higheſt ſenſation till four minutes after its firſt contact.

The duration of the greateſt force of the ſenſation is, likewiſe, different, as the ſubſtances differ; thus the heat of black hellebore comes to its greateſt intenſity and diminiſhes in one minute; that of the root of garden creſs in the ſame time; that of the root of aſarabacca, in two minutes.

The leaves of milfoil, which are bitter in the fourth degree, and warm in the firſt, loſe, at firſt, their bitterneſs, whilſt their heat ſtill continues. Acorus, or ſweet ruſh, is hot in the firſt degree, aromatic in the third, and bitter in the fourth; yet its bitterneſs is preſently extinguiſhed; its heat laſts two minutes, and its aromatic ſenſation ſeven or eight. The heat of garden-creſs endures ſeven or eight minutes; the bitterneſs of elaterium a quarter of an hour; the heat of euphorbium and black hellebore half an hour; the acrid ſenſation occaſioned by the root of arum, or cuckow-pint, often laſts twelve hours. From theſe familiar examples it appears, that the ſenſation acquires its greateſt force, in four or ſix minutes at moſt, from the time of contact; its duration in its decreaſe is often thirty or forty minutes and upwards.

Taſtes, conſidered with relation to the parts which they affect, are either, 1, fixed and local; 2, extend themſelves to the parts in the neighbourhood of that which is firſt affected, without,

without, however, relinquiſhing their former ſtation; as the bitterneſs of the dried roots of black hellebore, which ſpreads from the end of the tongue to its middle, and that of the leaves of elaterium, which ſpreads from the tip of the tongue to its root; or, 3, are tranſlated from one part to another, as in the roots of gentian, the bitterneſs of which ſoon relinquiſhes the tip of the tongue, the part firſt affected, and transfers itſelf to the middle.

Sapid bodies affect differently the parts which they touch, as the lips, tongue, palate, throat, and gullet.

The lips are affected more ſtrongly by the heat of the root of white hellebore, than any of the other parts.

The tip of the tongue is affected by moſt plants; gentian and coloquintida affect chiefly the middle, the leaves of elaterium, the root.

The palate is affected by the root of deadly night ſhade; its impreſſion laſts four minutes.

The throat is more affected than the other parts by the roots of mercury, aſparagus, and jalap.

The œſophagus or gullet is particularly affected with heat, by the roots of wormwood. The leaves make no impreſſion of this kind, on which account they are not ſo ſtomachic as the roots.

As the taſte of the ſame individual undergoes ſeeming alterations, according to the perfect or morbid ſtate of the external organ; ſo different individuals of the ſame ſpecies are liable to real variations from climate, ſoil and culture. Apples and pears, which grow naturally in the woods, are extremely harſh and acid; wild ſuccory is bitter; wild lettuce diſagreeable. Culture renders them all ſweet and eſculent, and moreover produces ſuch variety in the article of taſte, that of 172 diſtinct kinds of pears, and 200 of apples, enumerated by authors, each kind has a peculiar taſte.

All the parts of a plant have not the ſame taſte; in ſome, the fruit has an acid and agreeable taſte, whilſt the leaves or roots are bitter and diſagreeable; in others, the reverſe of this happens. It is for this reaſon that plants can never be properly arranged by their ſenſible qualities; the different

parts of the ſame plant poſſeſſing different qualities, muſt neceſſarily be disjoined and arranged under ſeparate articles.

The above obſervations on the variable nature of taſte, ſufficiently evince the neceſſity of excluding it from the liſt of genuine ſpecific differences. The following names, therefore, which are to be met with in authors, and others of the like kind, are totally to be rejected.

Apium *ingratius* (diſagreeable)

——— *dulce* (ſweet)

Lactuca *opij ſucco viroſo* (harſh like opium)

——— *mitis* (mild)

Pyrus fructu *ſaccharato* ore *deliqueſcente* (ſweet like ſugar, and melting in the mouth).

All plants act either by their ſmell upon the nerves, by their taſte upon the muſcular fibres, or by both upon the fluids. Sapid bodies never act upon the nerves, nor odoriferous bodies upon the muſcular fibres. The former act upon the fluids and ſolids, and change the fluids, which are evacuated by both ſapid and odoriferous ſubſtances.

The virtues and qualities of plants are commonly indicated by their taſte, ſmell, and colour.

Inſipid plants and ſuch as have no ſmell, have rarely any medicinal virtue.

Sapid and odoriferous plants, on the contrary, always poſſeſs very ſtrong powers. In fact, to deprive a plant of its taſte and ſmell, is to rob it of its virtue, as is evident from the change effected in the fæculæ and extracts of arum, calla, caſſada, and elaterium.

Sweet-ſmelling plants are generally of innocent quality; ſuch as are nauſeous, and of a rank, heavy, diſagreeable ſmell, are noxious.

The plants of the following liſt are ſtriking examples of the latter. Many muſhrooms, elder, herb-chriſtopher, aconite, hellebore, aſarabacca, ſtinking bean-trefoil, thorn-apple, tobacco, henbane, coloquintida, and hounds-tongue.

SARMENTACEÆ (*ſarmentum*, the twig, ſhoot, or ſpray of a vine); the name of the eleventh claſs in Linnæus's

Fragments

Fragments of a Natural Method, conſiſting of plants which have climbing ſtems and branches, that, like the vine, attach themſelves to the bodies in their neighbourhood for the purpoſe of ſupport.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Alſtræmeria.			
Ariſtolochia,	—	—	Birthwort.
Aſarum,	—	—	Aſarabacca.
Aſparagus,	—	—	Aſparagus, by corruption Sparrow-graſs.
Centella.			
Ciſſampelos.			
Convallaria,	—	—	Lily of the valley.
Cytinus.			
Dioſcorea.			
Erythronium,	—	—	Dog's tooth violet.
Glorioſa,	—	—	Superb lily.
Medeola,	—	—	Climbing African aſparagus.
Meniſpermum,	—	—	Moon-ſeed.
Paris,	—	—	True-love, or one-berry.
Rajania.			
Ruſcus,	—	—	Butcher's broom, or knee-holly.
Smilax,	—	—	Rough bind-weed.
Tamus,	—	—	Black bryony.
Trillium,	—	—	Three leaved night-ſhade, or herb true-love of Canada.
Uvularia.			

Theſe plants are far from being a true natural aſſemblage. In fact, they agree in ſcarce a ſingle circumſtance, ſave that expreſſed in the title, which is far from being peculiar to this order.

The pounded root of *ciſſampelos*, the caapeba of Plumier,

 applied

applied externally, is ſaid to be an antidote againſt the bites of venomous ſerpents. The plant being infuſed in water, quickly fills the liquor with a mucilaginous ſubſtance, which is as thick as jelly; whence the name of freezing-wyth, by which this genus of plants has been diſtinguiſhed by the Braſilians.

The powdered root of a Mexican ſpecies of birth-wort, the *Ariſtolochia angaicida* of Linnæus, proves, according to Dr. Jacquin, an infallible remedy againſt ſnakes; thoſe pernicious animals being actually faſcinated and even killed by it. In Carthagena, the Indians chew the root of this plant, and mix its juice with the ſaliva. If one drop of this mixture is put into the ſnake's mouth, it becomes intoxicated, and you may handle it with perfect impunity; if two or three drops are forced in, and they reach the ſtomach of the reptile, convulſions inſtantly follow, and it dies. The Indian, who ſhewed Dr. Jacquin this method, informed him likewiſe, that he himſelf had been thrice bitten by ſnakes, and had at each time cured the wound by the application both internal and external of *Ariſtolochia*. The plant itſelf has ſo nauſeous a ſmell, that it is always avoided by ſnakes, and, when chewed, cauſes vomiting even to men.

It ſeems highly probable that it is of this ſpecies of *Ariſtolochia*, that Boſſu, in his travels through Louiſiana, relates the following curious fact. "During my voyage to Tombekbé, a *whiſtler-ſnake*, (ſo termed from its having a prodigious wide mouth, and when angry, whiſtling at a terrible rate) which lay concealed under ſome leaves, bit a ſoldier of my detachment, who trod upon its tail. The ſoldier was barefoot, and the ſnake ſo irritated, that it got hold of his big toe, which it obſtinately held faſt. I was very uneaſy and ſorry to ſee this ſoldier, who was my interpreter, expoſed to periſh; and, as an Indian doctor juſt then accidentally paſſed by the place where we were, I applied to him for advice. He took a powder out of a little ſack, and blew it through a tube upon the ſnake's head, which died inſtantly. He put another powder upon the wound, which prevented the poiſon from taking effect, giving ſome of it in water

water at the ſame time to the patient, who was quite well in a moment. This Charlaton, continues Boſſu, I recompenſed very handſomely, and wiſhed to know his ſecret, but in vain. He reſiſted every importunity to that effect, telling me haughtily, and in the true ſtile and manner of the juggler, that the Maſter of life, who had communicated the art to him alone, would not permit it to be imparted to another."—Boſſu, Louiſiane, Tom. I.

Yams, the root of the *dioſcorea bulbifera* of Linnæus, are the principal food of the Negroes in the Weſt-Indies. The ſkin is pretty thick, rough, unequal, covered with many ſtringy fibres, and of a violet colour approaching to black. The inſide is white, and of the conſiſtence of red beet; it reſembles potatoes in its mealineſs, but is of cloſer texture.

When raw, theſe roots are viſcous or clammy; when boiled or roaſted, they afford very nouriſhing food, and are often preferred to bread by the inhabitants of the Weſt-Indies, on account of their lightneſs and facility of digeſtion. The ſtem of the plant is ſquare: when placed by itſelf, it trails upon the ground, and ſtrikes root at proper diſtances; but when planted in the neighbourhood of buſhes or trees, it avails itſelf of their ſupport, climbs, and in a ſhort time, covers every place to which it can penetrate. The leaves are oppoſite, and ſhaped like a heart; they are of a dark green, pretty thick and ſucculent. The flowers, which are ſmall and bell-ſhaped, grow in ſpikes from the wings of the leaves, and are ſucceeded by dry capſular fruits, each containing ſeveral ſmall, flat, black ſeeds. The plant, which is a native of Africa and the Eaſt-Indies, is propagated by the eyes of the root, in the ſame manner as potatoes and Jeruſalem artichoke. When firſt dug out of the ground, the roots are placed in the ſun to dry; after which, they are either put into ſand, dry garrets, or caſks, where, if kept from moiſture, they may be preſerved whole years, without being ſpoilt, or diminiſhed in their goodneſs. Two or three pounds is the common weight of this root; ſome yams, however, weigh twenty pounds and upwards.

In Siberia, ſays Gmelin, they dry and mix with their

ſoups, in ſpring, the root of dog's-tooth-violet, which grows in great abundance in that country, and is termed by the Siberians, beſs.

The ſeeds of a Levant ſpecies of moon-ſeed, being formed into a paſte, are regarded, by the inhabitants, as a genuine ſpecific againſt lice, and eruptions of the ſkin. The ſame paſte is uſed for the purpoſe of intoxicating fiſhes, which thus become an eaſy prey to the firſt invader.

SCABRIDÆ *(ſcaber*, rough, rugged, briſtly) the name of the fifty-third order in Linnæus's Fragments of a Natural Method, conſiſting of plants with rough leaves. There is an impropriety in characterizing theſe plants by a name expreſſive of the roughneſs of the leaves, as that circumſtance had previouſly furniſhed the claſſic character of the forty-firſt order, ASPERIFOLIÆ.

The degree of roughneſs, however, is much greater in the plants which make the ſubject of the preſent article.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Acnida.			
Boſea,	—	—	Yerva-mora, or golden-rod tree.
Cannabis,	—	—	Hemp.
Cecropia.			
Celtis,	—	—	Nettle-tree.
Dorſtenia,	—	—	Contrayerva.
Ficus,	—	—	Fig.
Humulus,	—	—	Hop.
Morus,	—	—	Mulberry-tree.
Parietaria,	—	—	Pellitory.
Theligonum,	—	—	Dog's-cabbage.
Ulmus,	—	—	Elm-tree
Urtica,	—	—	Nettle.

Some

Some of theſe plants, particularly fig and mulberry, yield, by inciſion, a milky juice. That of the fig-tree is ſo acrid and cauſtic, as to make impreſſions upon the ſkin, which, when ſuffered to remain for a ſhort time, can never be effaced. *Cecropia* furniſhes an oily aſtringent liquor.

Theſe plants are in general of an aſtringent nature; their taſte is bitter and ſtyptic.

The fleſhy fruits of the mulberry, fig, and nettle-trees, and of the genus *cecropia*, are eſculent.

From the leaves of hemp, pounded and boiled in water, the natives of the Eaſt-Indies prepare an intoxicating liquor, of which they are very fond. From the ſeeds is drawn, by expreſſion, an oil, which is very proper for burning. Boiled in milk till it cracks, the ſeed is accounted good for old coughs, and a ſpecific to cure the jaundice. The œconomical uſe of hemp is well known.

The Europeans at the Cape of Good Hope ſow hemp chiefly on account of the Hottentots, who ſmoak the ſeed and the leaves as they do tobacco. This preparation likewiſe, to which they give the name of *Dacha*, has an inebriating quality: "nor," ſays Kolben, "have the ſtrongeſt diſtillations a more furious effect upon the head of an European than Dacha has upon the brain of a Hottentot. He raves, ſtares, and capers as if poſſeſſed, and loſes himſelf in a million of the wildeſt actions and incoherencies. They often mix *Dacha* and tobacco together, and then call it *Buſpaſch*."

The ſcaly fruits of hops are employed to procure an agreeable bitterneſs to beer, and keep it from ſouring; the young ſhoots, prepared like aſparagus, afford a very palatable food. From the macerated ſtalks of hops might probably be obtained a fibrous ſubſtance, ſimilar to that which is obtained from hemp.

From the fruit of nettle-tree is drawn a juice, which is ſaid to be aſtringent, and to give eaſe in violent dyſenteries. The plant has obtained the name of nettle-tree from its leaves, which are rough on the upper ſurface.

The root of the ſeveral ſpecies of *dorſtenia* is the true

contraverva or counterpoiſon of the Spaniards. The name has been, at different times, given to many different roots, ſuppoſed to poſſeſs the virtue of reſiſting both internal and external poiſons. With us, the root is in great eſtimation in fevers that can be relieved by encreaſing the diſcharges through the pores of the ſkin, and for throwing out the ſmall pox. The root of all the ſpecies is likewiſe uſed in dyeing.

A decoction of the old wood of a ſpecies of mulberry, called tataïba by the Braſilians, dyes a fine yellow colour. The leaves of ſome ſpecies are the common food of ſilk worms.

SCAPUS, (properly the ſhaft of a pillar—à σκηπτω, innitor,) an herbaceous ſtem ſo called, which elevates the fructification, but not the leaves: in other words, a naked ſtalk, proceeding immediately from the root, and terminated by the flowers; as in narciſſus, lily of the valley, hyacinth, and winter-green. This ſpecies of trunk differs from a flower-ſtalk, (*pedunculus*) in that the latter iſſues, not from the root, but from the ſtem, or branches; and from a naked ſtem, (*caulis aphyllus*) in that the *ſcapus*, though it elevates no leaves, has always radical or bottom leaves; whereas, a naked ſtem is devoid of leaves altogether.

This ſort of univerſal trunk generally prevails through all the ſpecies of the ſame genus, and hence, can be but ſeldom uſed as a diſcriminating character. Two ſpecies of winter-green with a triangular ſtalk of this kind, are diſtinguiſhed by that circumſtance from the other ſpecies. In the *Species Plantarum*, the term *ſcapus* is generally preceded by the ſuperfluous word *naked*; an addition which is apt to miſlead the unexperienced botaniſt, as ſeeming to imply, that nakedneſs is not an eſſential part of the deſcription of this ſpecies of ſtalk.

SCITAMINEÆ, (*ſcitamentum*, *ſcitum edulium*, a dainty, meat of an agreeable taſte) the name of the eighth order in Linnæus's Fragments of a Natural Method, conſiſting of the following beautiful exotic plants, ſome of which, as

banana,

banana, furniſh exquiſite fruits; and others have an agreeable aromatic flavour.

Liſt of the Genera *contained in this Order.*

Linnæan Genera,			*Engliſh Names.*
Alpinia.			
Amomum,	—	—	Ginger.
Canna,	—	—	Indian flowering-reed.
Coſtus.			
Curcuma,	—	—	Turmeric.
Kæmpferia.			
Maranta,	—	—	Indian arrow-root.
Muſa,	—	—	Banana, plantain-tree.
Thalia.			

Theſe plants are all natives of very warm countries; and, notwithſtanding their great height, are only perennial by their roots.

The plants of this order which have only one filament, or male organ, (as ginger, coſtus, Indian flowering-reed, alpinia, and Indian arrow-root) have, in all their parts, an aromatic odour, and an acrid, or poignant taſte; qualities, however, poſſeſſed in a much greater degree by the roots, which are hot, and reſinous. The fruit of the different ſpecies of plantain-tree (*muſa*) is acid.

The confected roots of moſt of the aromatics of this order are greatly in uſe; and their leaves, particularly thoſe of wild ginger, and of a ſpecies of turmeric called vanhom by the Japaneſe, furniſh excellent pot-herbs. The internal uſe of theſe plants removes obſtructions, reſiſts poiſon, and is of conſiderable efficacy in gouty and aſthmatic complaints. The ſtalks of *coſtus* chewed are uſeful in ſlight ſtages of the venereal diſeaſe. Their leaves, applied externally, give eaſe in violent colics; they likewiſe ſtrengthen the eyes.

The fruit of the banana-tree is of the ſize and ſhape of a middling cucumber, and of a high, grateful flavour. The leaves are two yards long, and a foot broad in the middle; they

they join to the top of the body of the tree, and frequently contain in their cavities a great quantity of water, which runs out, upon a ſmall inciſion being made into the tree, at the junction of the leaves. Bananas grow in great bunches, that weigh a dozen pounds and upwards. The body of the tree is ſo porous, as not to merit the name of wood. The tree is only perennial by its roots, and dies down to the ground every autumn,

When the natives of the Weſt-Indies, ſays Labat, undertake a voyage, they make proviſion of a paſte of banana, which, in caſe of need, ſerves them for nouriſhment and drink. For this purpoſe, they take ripe bananas, and having ſqueezed them through a fine ſieve, form the ſolid fruit into ſmall loaves, which are dried in the ſun, or in hot aſhes, after being previouſly wrapped up in the leaves of Indian flowering-reed. When they would make uſe of this paſte, they diſſolve it in water, which is very eaſily done, and the liquor, thereby rendered thick, has an agreeable acid taſte imparted to it, which makes it both refreſhing and nouriſhing.

The banana is greatly eſteemed and even venerated by the natives of Madeira, who term it the forbidden fruit, and reckon it a crime almoſt inexpiable to cut it with a knife; becauſe, after diſſection, it exhibits, as they pretend, a ſimilitude of our Saviour's crucifixion; and to cut the fruit open with a knife, is, in their apprehenſion, to wound his ſacred image.

Some authors have imagined, that the banana-tree was that of the leaves of which our firſt parents made themſelves aprons in Paradiſe. The ſacred text, indeed, calls the leaves employed for that purpoſe, fig-leaves; and Milton, in a moſt beautiful, but erroneous deſcription, ſuppoſes the Malabar, or Decan fig, to have been the tree alluded to. But, beſides that the fruit of the banana is often, by the moſt ancient authors, called a fig, its leaves, by reaſon of their great ſize and ſolidity, were much better adapted for a covering, than thoſe of the fig-tree juſt mentioned, which are ſeldom above ſix or eight inches long, and three broad.

On

On the other hand, the banana leaves being three, four and five feet long, and proportionably broad, could not fail to be pitched upon, in preference to all others; eſpecially as they might be eaſily connected, by means of the numerous ſtringy filaments that may be peeled with the utmoſt facility from the body of this tree.

Indian arrow-root is the only remedy yet known againſt wounds made by arrows poiſoned with the milky juice of the manchineel-tree. The natives of the Caribbee Iſlands, where it naturally grows, call it *toulola*. It reſembles Indian flowering-reed, except in its height, which ſeldom exceeds four feet. The flower is white, and ſucceeded by a fruit with three ſides like a priſm, of a pale red, and very ſleek, containing a ſmall, wrinkled, or furrowed ſeed. The root is a long, white, jointed, watery, and mealy bulb, from which hang a great number of long dry fibres. The leaves are ſtrong, almoſt as firm as parchment, of a light green, curl themſelves as ſoon as gathered, and are attached to the trunk by a long furrowed ſtalk; they are round below, four times longer than broad, and end in a point, like the extremity of a ſpear or halberd. The root is pounded, infuſed in water, and made into ptiſan, which is drunk by thoſe who have been wounded with poiſoned arrows. It has the virtue of diſſipating the *virus*, and of preventing it from reaching the noble parts. The ſame root bruiſed, and made into a cataplaſm, is applied externally to the wound, and with great efficacy, if quickly uſed; but if delayed, though for a very ſhort time, the poiſon gains ground, corrupts the parts adjoining to the wound, and having communicated its virulence to the larger veſſels, proves mortal. Of the root of this plant is likewiſe made an exceeding fine ſtarch, far ſurpaſſing that made with wheat.

SECTIO. *Vide* ORDO.

SEMEN, the ſeed; the eſſence of the fruit of every vegetable; defined by Linnæus to be a deciduous part of the plant, containing the rudiments of a new vegetable, and fertilized by the ſprinkling of the male duſt. The parts of a

ſeed

ſeed properly ſo called enumerated by Linnæus, are as follows:

I. CORCULUM, the *punctum vitæ*, or eſſence of the ſeed.

II. COTYLEDONES, the lobes.

III. HILUM, a mark or ſcar in the ſeed.

IV. ARILLUS, Lin. the proper covering: *calyptra* of Tournefort.

V. CORONULA, PAPPUS, } the crown of the ſeed.

VI. ALA, the wing of the ſeed.

Each of theſe terms is particularly explained under its proper head.

Beſides the ſeed properly ſo called, two other terms are referred by Linnæus to the general article of SEMEN: theſe are,

VII. NUX, a nut, or ſeed covered with a hard bony ſkin.

VIII. PROPAGO, the ſeed of the moſſes.

With reſpect to number, plants are either furniſhed with one ſeed, as ſea-pink, and biſtort; two, as wood-roof, and the umbelliferous plants; three, as ſpurge; four, as the lipped flowers of Tournefort, and rough-leaved plants of Ray; or many, as ranunculus, anemone, and poppy.

The form of ſeeds is likewiſe extremely various, being either large or ſmall, round, oval, heart-ſhaped, kidney-ſhaped, angular, prickly, rough, hairy, wrinkled, ſleek, or ſhining, black, white, or brown. Moſt ſeeds have only one cell, or internal cavity; thoſe of leſſer burdock, valerian, lamb's lettuce, cornelian-cherry, and ſebeſten, have two.

With reſpect to ſubſtance, ſeeds are either ſoft, membranaceous, or of a hard bony ſubſtance. This laſt is exemplified in gromwell, tamarind, and all the nuciferous plants.

In point of magnitude, ſeeds are either very large, as in cocoa-nut; or very ſmall, as in campanula, *ammannia*, rampions, and throat-wort.

With reſpect to ſituation, they are either diſperſed promiſcuouſly through the pulp, *(ſemina nidulantia)* as in water-lily;

affixed

affixed to a future, or joining of the valves of the ſeed-veſſel, as in the croſs-ſhaped and pea-bloom flowers; or placed upon a *placenta* or receptacle within the ſeed-veſſel, as in tobacco, and thorn-apple.

Seeds are ſaid to be naked (*ſemina nuda*) which are not contained in a veſſel: ſuch are thoſe of the lipped and compound flowers, the umbelliferous and rough-leaved plants. Covered ſeeds, (*ſemina tecta*) are contained in ſome veſſel, whether of the capſule, pod, berry, apple, or cherry kind.

A ſimple ſeed is ſuch as bears neither crown, wing, nor downy *pappus*. The varieties in ſeeds, ariſing from theſe circumſtances, are particularly enumerated under their reſpective heads.

In aſſimilating the animal and vegetable kingdoms, Linnæus denominates ſeeds, the eggs of plants. The fecundity of plants is frequently marvellous. From a ſingle plant, or ſtalk of Indian Turky wheat, are produced, in one ſummer, 2000 ſeeds; of elecampane, 3000; of ſun-flower, 4000; of poppy, 32,000; of a ſpike of cat's-tail, 10,000 and upwards: a ſingle fruit, or ſeed-veſſel of tobacco, contains 1000 ſeeds; that of white poppy, 8000. Mr. Ray relates, from experiments made by himſelf, that 1012 tobacco ſeeds are equal in weight to one grain; and that the weight of the whole quantum of ſeeds in a ſingle tobacco plant, is ſuch as muſt, according to the above proportion, determine their number to be 360,000. The ſame author eſtimates the annual produce of a ſingle ſtalk of ſpleen-wort, to be upwards of one million of ſeeds.

The diſſemination of plants reſpects the different methods, or vehicles, by which Nature has contrived to diſperſe their ſeeds for the purpoſe of increaſe. Theſe by naturaliſts are generally reckoned four.

I. Rivers, and running waters.

II. The wind.

III. Animals.

IV. An elaſtic ſpring peculiar to the ſeeds themſelves.

I. The ſeeds which are carried along by rivers and tor-

rents,

rents, are frequently conveyed many hundreds of leagues from their native ſoil, and caſt upon a very different climate, to which, however, by degrees, they render themſelves familiar.

II. Thoſe which are carried by the wind, are either winged, as in fir-tree, trumpet-flower, tulip-tree, birch, arbor vitæ, meadow rue, red jeſſamine, and ſome umbelliferous plants; furniſhed with a *pappus*, or downy crown, as in valerian, poplar, reed, ſucculent ſwallow-wort, cotton-tree, and many of the compound flowers; placed within a winged calyx, or ſeed-veſſel, as in ſcabious, ſea pink, dock, *dioſcorea*, aſh, maple, and elm-trees, log-wood and woad; or, laſtly, contained within a ſwelled calyx, or ſeed-veſſel, as in winter-cherry, cucubalus, melilot, bladder-nut, fumatory, bladder-ſenna, heart-ſeed, and chich-peaſe.

III. Many birds ſwallow the ſeeds of vanelloe, juniper, miſtletoe, oats, millet, and other graſſes, and void them entire. Squirrels, rats, parrots, and other animals, ſuffer many of the ſeeds which they devour, to eſcape, and thus in effect diſſeminate them. Moles, ants, earth-worms, and other inſects, by ploughing up the earth, admit a free paſſage to thoſe ſeeds which have been ſcattered upon its ſurface.

Again, ſome ſeeds attach themſelves to animals, by means of hooks, crotchets, or hairs, which are either affixed to the ſeeds themſelves, as in hound's-tongue, mouſe-ear, vervain, carrot, baſtard parſley, ſanicle, water hemp-agrimony, *arctopus*, and *verbeſina*; to their calyx, as in burdock, agrimony, *rhexia*, ſmall wild bugloſs, dock, nettle, pellitory, and lead-wort: or to their fruit, or ſeed-veſſel, as in liquorice, enchanter's night-ſhade, croſs-wort, cleavers, French honeyſuckle, and arrow headed graſs.

IV. The ſeeds, which diſperſe themſelves by an elaſtic force, have that force reſident either in their calyx, as in oats, and the greater number of ferns; in their *pappus*, as in *centaurea crupina*; or in their capſule, as in geranium, herb-bennet, African ſpiræa, fraxinella, horſe-tail, balſam, Malabar nut, cucumber, elaterium, and male balſam-apple.

SEMI-

SEMIFLOSCULOSI, the name of the thirteenth claſs in Tournefort's Method, conſiſting of compound flowers with plain or tongue ſhaped florets. The term is exemplified in dandelion, nipplewort, and ſuccory.

SEMIFLOSCULOSUS *flos.* *Vide* LIGULATUS *flos.*

SENTICOSÆ, (*ſentis*, a briar, or bramble) the name of the thirty-fifth order in Linnæus's Fragments of a Natural Method, conſiſting of roſe, bramble, and other plants which reſemble them in port, and external ſtructure.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Agrimonia,	—	—	Agrimony.
Alchemilla,	—	—	Ladies mantle.
Aphanes,	—	—	Percepier.
Comarum,	—	—	Marſh cinquefoil.
Dryas.			
Fragaria,	—	—	Strawberry.
Geum,	—	—	Avens, or herb-bennet.
Potentilla,	—	—	Cinquefoil.
Roſa,	—	—	Roſe.
Rubus,	—	—	Raſpberry, bramble.
Sibbaldia.			
Tormentilla,	—	—	Tormentil.

Theſe plants are ſo nearly allied in form, habit, and ſtructure to thoſe of the natural order, *pomaceæ*, that they ought never to have been ſeparated from it. As we wiſh not, therefore, uſeleſsly to enlarge the work by unneceſſary repetitions, the reader is referred for a general deſcription of the plants of the order *ſenticoſæ*, with very few exceptions, to the article alluded to.

The leaves of theſe plants have a ſtyptic taſte. The fruits are acid and cooling. The roots of herb-bennet ſmell like cloves, whence the name of *caryophyllata*, by which that genus of plants was known in the time of Pliny.

With reſpect to their virtues, the leaves are vulnerary and aſtringent,

aſtringent, the roots diuretic. The ſubacid fruits, as ſtrawberry, and raſpberry, are uſed with ſucceſs in putrid and bilious fevers, as likewiſe in contagious and epidemical dyſenteries, which prevail in ſummer and autumn, and are occaſioned by a ſudden tranſition from a hot to a cold air, or by the acrid nature of the humours which flow into the inteſtines.

The inhabitants of the eaſtern countries ſprinkle the water which is diſtilled from white roſes, on the hands, face, head, and cloaths of the gueſts whom they mean to honour, and afterwards perfume them with frankincenſe and wood of aloes.

SEPIARIÆ (*ſepes*, a hedge) the name of the forty-fourth order in Linnæus's Fragments of a Natural Method, conſiſting of the following beautiful collection of woody plants, ſome of which, from their ſize, elegance, and other circumſtances, ſeem very proper furniture for hedges.

Linnæan Genera.			*Engliſh Names.*
Chionanthus,	—	—	Snow-drop tree, or fringe-tree.
Fraxinus,	—	—	Aſh-tree.
Iaſminum,	—	—	Jeſſamine, or Jaſmine.
Liguſtrum,	—	—	Privet.
Nyctanthes,	—	—	Arabian jaſmine.
Olea,	—	—	Olive.
Phillyrea,	—	—	Mock-privet.
Syringa,	—	—	Lilac.

This order furniſhes woody plants both of the ſhrub and tree kind, moſt of which do not drop their leaves till nearly the time in which the new leaves begin to appear.

The flowers of jeſſamine, which is a native of the Indies, have a very agreeable ſmell; they are cordial, cephalic, anodyne, and frequently enter as an ingredient into the compoſition of perfumes and odoriferous oils.

The leaves of privet have a bitter acrid taſte; the flowers have a ſtrong diſagreeable ſmell: the former are aſtringent; the latter deterſive.

The

The Banian Indians, who are much addicted to ſweet ſmells and fragrant exhalations, generally wear a necklace of the flowers of Arabian Jeſſamine in the night-time; as it is then that they moſt ſenſibly emit their odoriferous vapours.

The flowers of a ſpecies of Arabian jeſſamine open in the evening, and drop off in the morning; whence the name of *arbor triſtis*, or the ſorrowful tree, by which Linnæus has diſtinguiſhed it.

The roots of many of the plants of this order, particularly of Arabian jeſſamine, preſerve from the dreadful conſequences of the venomous bites of ſerpents, ſcorpions, and mad dogs.

The bark of olive tree has a bitter taſte; the fruits, freſh as gathered, are acrid, ſtomachic, and heating; the oil obtained from the fruit is emollient and laxative; the leaves are aſtringent.

From a ſpecies of aſh, the *fraxinus rotundiore folio* of Caſpar Bauhin, the *fraxinus ornus* of Linnæus, which grows plentifully in Calabria and other parts of Italy, flows naturally, and by inciſion, a ſweet juice, which, when condenſated, is known by the name of Calabrian manna, and is eſteemed an excellent cathartic for children, and ſuch as are of weak conſtitutions.

SEXUS *plantarum*. The doctrine of the ſexes of plants.

As it is of the utmoſt importance for ſtudents in botany to have preciſe and clear ideas upon this ſubject, I purpoſe to handle it at ſome length; and, that the queſtion may be fairly and impartially ſtated, ſhall, in the firſt place, trace the hiſtory of the doctrine of the ſexes, from its earlieſt appearance in botanical writings to its more improved ſtate under the celebrated Linnæus, whoſe ſyſtem claims it as its ſole principle; ſecondly, enumerate and illuſtrate the ſeveral arguments in ſupport of the ſexes of plants; and, thirdly, examine the force and weight of the objections which are adduced to diſprove the theory.

I. Theophraſtus, the Father of Botany, frequently mentions the ſexes of plants. He obſerves, that trees may be diſtinguiſhed into ſeveral claſſes, on account of their great

variety, but that their moſt common diſtinction is into MALE and FAMALE, the one of which is fertile, the other, in ſome ſorts, barren. This diſtinction of the ſexes, however, is not ſo much founded upon an analogy betwixt vegetables and animals, as upon the greater or leſs perfection of the fruit in the plants in queſtion. In a ſpecies of palm-tree, mentioned by this author and Ariſtotle, the analogy in queſtion is more ſtrictly preſerved. "If the duſt of a branch of the male palm, ſays Ariſtotle, is ſhaken over the female, the fruit of the latter will quickly ripen; nay," continues the ſame author, "if this male duſt ſhall be carried along by the wind, and diſperſed upon the female, the ſame effect will follow, as if a branch of the male had been ſuſpended over it." To the ſame purpoſe, Theophraſtus obſerves, that unleſs the duſt or down of the male palm is ſprinkled over the fruit of the female, it will never ripen, but fall off. That theſe naturaliſts, however, were not clear in opinion that the fruit ſo ſprinkled with the male duſt was impregnated by it in the ſame manner as the ovary is fecundated in animals, appears from another paſſage in the laſt quoted author, in which he aſſerts, that though the fact juſt mentioned cannot be denied, yet no reaſon whatever can be aſſigned for the effect of the ſprinkling.

Dioſcorides, the next Greek botaniſt of note after Theophraſtus, denominates many plants male and female, but without regard to analogy, or to their fertility, or barrenneſs. Thus his male mercury carries the ſeed, and the female is barren. Theſe ideas of the ſexes of plants have been transferred to our own times; and, it is not uncommon to hear peaſants confounding the ſexes of hemp, ſpinach, and hop, by calling the male plant female, and the female plant, or that which bears the ſeeds, male.

Ariſtotle, as well as Dioſcorides, errs widely in his manner of diſtinguiſhing the male from the female plant; the former of which, in his opinion, is larger and ſtronger; the female weaker, but more fruitful.

"Naturaliſts," ſays Pliny, "admit the diſtinction of ſex, not only in trees, but in herbs, and all plants." "Yet," continues

continues the ſame author, "this is no where more obſervable than in palms, the females of which never propagate but when they are fecundated by the duſt of the male."

Upon the whole, I cannot help agreeing with Dr. Alſton, that the palm-tree is the only inſtance among the ancients, where ſexes are attributed to particular plants, on account of fertility, or barrenneſs. Cæſalpinus was the firſt who corrected the miſtakes of the ancients with reſpect to the ſex of plants, and eſtabliſhed orthodox opinions on that ſubject. He obſerved, that in ſome trees, as yew, and in ſome herbaceous vegetables, as mercury, hemp, and nettle, the fruit was produced on one root, and flowers only on the other. The laſt being barren, was denominated the male plant; the other being fertile, the female. The female plants, continues the ſame intelligent author, ſucceed better, that is, become more fruitful, if ſowed in the neighbourhood of the male: certain exhalations from the latter diſperſing themſelves over their ſurface, and, by an operation not to be explained, diſpoſing them to produce riper and more perfect ſeeds.

Cæſalpinus's idea of ſex in plants was reſtricted to a very inconſiderable number; thoſe, to wit, in which the ſuppoſed organs are placed apart from each other, on ſeparate roots produced from the ſame ſeed. In plants of this deſcription, their analogy to animals would, in a manner, ſuggeſt itſelf. From the ſame ſeed are produced two different plants, the one barren, the other fertile. The analogy to the ſexes of animals, immediately preſents itſelf to the mind, and we denominate that which is barren, or bears no ſeeds, male; that which is fertile, or bears ſeeds, female. The ſame analogy carries us further, and induces a conjecture, that theſe male and female plants are connected together in ſuch a manner, that the fecundation of the ſeeds of the female is produced, as in animals, by the male. This conjecture, furniſhed by analogy, leads to obſervations and experiments for its ſupport: and thus the doctrine of the ſexes, ſmall and inconſiderable in its beginnings, becomes enlarged, and, from being con-

fined to a very ſmall number of plants, extends itſelf over the whole vegetable kingdom.

It was Dr. Nehemiah Grew who, in 1682, in conjunction with the learned Sir Thomas Millington, firſt ſuggeſted the univerſality of ſexes in plants, and the primary uſe of the *antheræ*, *apices*, or tops of the *ſtamina*, in impregnating the ſeed. Theſe tops, he obſerves, are chiefly uſeful to the plant itſelf, becauſe all plants, even ſuch as want the foliature or petals, are provided with them; he then plainly aſſerts, as his opinion, that when the tops, which he calls the attire, break or open, their incloſed *pollen* or duſt falls down on the ſeed-bud, the vegetable *uterus*, and endues it with a prolific virtue; not, as he explains himſelf, by entering into it bodily, as the *ſemen maſculinum* in animals, but by communicating to it ſome ſubtle and vivific effluvia.

This opinion of Grew was adopted by ſeveral ſucceeding botaniſts, particularly Ray, Camerarius, Geoffroy, Samuel Morland, Blair, Juſſieu, Bradley, Van Royen, Malpighi, Vaillant, Ludwig, Wolfius, Logan, Monro, and the juſtly celebrated Linnæus.

Ray, at firſt, mentions Grew's doctrine only as probable, but afterwards declares his full aſſent to it, and collects the arguments that are uſed to ſupport it.

Rudolphus Jacobus Camerarius, about the end of the 17th century, endeavoured to demonſtrate the analogy betwixt the generation of plants and animals. Among other arguments for the ſex of plants, he makes uſe of the following: "that copulation," ſays he, "is neceſſary in the generation of animals is paſt a doubt: that a ſimilar junction obtains in that of plants appears from this circumſtance, that if either the tops, (*antheræ*) of the male, or the ſtyles of the female, or both, are wanting, no fecundation, and conſequently no generation, can take place." This aſſertion he exemplifies in the mulberry-tree, mays, and mercury, in which the *ſtamina* of the male flowers being either plucked off before they had attained maturity, as in the two firſt inſtances, or placed at a diſtance from the female plant, as in the

the laſt, the buds that ought to have produced fruit came not to maturity. The ſame author ſpeaks of the number of *ſtamina* in flowers; ſo that in his works we may recognize almoſt the firſt principles of the renowned Sexual Syſtem of Linnæus. Camerarius's objections to his own doctrine are referred to the third head of this article.

I ſhould have obſerved, that, almoſt a century before Grew, Zaluzianſki, a native of Poland, had clearly diſtinguiſhed the ſexes of plants, and pointed out the difference betwixt male, female, androgynous, and hermaphrodite plants. Grew's improvements on the idea of Cæſalpinus and Zaluzianſki have made him generally be conſidered as the author of the doctrine alluded to. Certain it is that he has handled the ſubject with great accuracy, and endeavoured, by repeated microſcopical examinations, to throw light upon this obſcure, but curious enquiry.

Signior Malpighi, who was contemporary with Grew, likewiſe examined by the microſcope the male or fecundating duſt, the ſtyles of the ſeed-bud, and the manner in which the *anthers* open or burſt when ripe.

Morland, Geoffroy, and Vaillant, who have written ſucceſſively upon this ſubject, all concur in aſſerting that the duſt of the *anthers* or tops of the *ſtamina*, is entirely analogous to the *ſemen maſculinum* of animals, and abſolutely neceſſary for fecundating the ſeed. Morland, however, differs from Grew, in his conception of the manner in which the fecundation in queſtion is accompliſhed. The latter, as we have ſeen, gave it for his opinion, that the fecundating duſt did not enter bodily into the ovary of the plant, but operated its effect by means of ſome ſpirituous emanations, or vivifying effluvia. Morland, on the other hand, aſſerted that "the male duſt is a congeries of ſeminal plants, one of which muſt be conveyed through the ſtyle into every *ovum* or ſeed before it can become prolific." This hypotheſis, as the reader will eaſily perceive, is analogous to that of animal generation by means of *animalculæ* in *ſemine maſculino*. Geoffroy, in a memoir preſented to the Academy of Sciences at Paris in 1711 on

the ſtructure and uſe of the principal parts of flowers, aſſerts, that the germ, or *punctum vitæ*, is never to be ſeen in the ſeed, till the *anthers* have ſhed their duſt: and that if the *ſtamina* be cut out before the *anthers* open, the ſeed will either not ripen, or be barren if it ripens. This laſt is Camerarius's great argument repeated; a further illuſtration of it will be given below.

In 1717 M. Vaillant made ſome very ingenious diſcoveries with reſpect to the nature of the fecundating duſt, and the manner of its exploſion. He ſeems, ſays an ingenious French author, to have been the firſt eye-witneſs of this ſecret of Nature, this admirable ſport that paſſes in the flowers of plants between the organs of different ſexes. Vaillant is entirely of Grew's opinion, that it is the volatile ſpirit of the male duſt, not its groſs or bodily ſubſtance that enters the ſeeds of plants: the ſtyle, which leads to the caſe containing the ſeeds, being frequently found perfectly ſolid and impenetrable by that ſubſtance.

Laſtly, the illuſtrious Sir Charles Linné has completed the doctrine of the ſex of plants, by collecting all the arguments in ſupport of it that can poſſibly be advanced, and by founding upon it a ſyſtem, in which all vegetables are arranged under particular claſſes, diſtinguiſhed by the number and other circumſtances of their *ſtamina*, or male organs.

II. We come now to take a particular view of the arguments in ſupport of the ſex of plants, ſome of which have been juſt hinted at in the foregoing part of this article. Theſe arguments ariſe either from a general view of the ſtructure, proportion, and ſituation of the ſuppoſed organs of generation, or from experiments on thoſe organs. The firſt ſet of arguments has been already fully handled under the article ANTHERA. Before I proceed to the other, I would beg leave to remind the reader, that the point in diſpute is, whether the *pollen*, or duſt of the tops of the *ſtamina*, is abſolutely neceſſary for fertilizing the ſeeds; or, whether, on the contrary, good and perfect ſeeds may not be produced, when the pretended fecundating duſt is denied acceſs to the caſe or veſſel

veſſel that contains them. The ſexualiſts maintain the former propoſition; the anti-ſexualiſts the latter.

Arguments for the Sex of Plants, derived from Experiments on the pretended Organs.

1. The leading argument for the ſexes is, that derived from the caſtration or mutilation of the flowers. This is effected by cutting off the tops of the *ſtamina* before they have attained maturity, and diſperſed the duſt contained within their ſubſtance. "If," ſays Wahlbom, "the *anthers* of any plant which bears only one flower are cut off, and care taken to prevent the acceſs of any other plant of the ſame ſpecies, the fruit proves abortive." This obſervation Linnæus particularly applies to the tulip, which, in the circumſtances juſt mentioned, he affirms to be always productive of imperfect ſeeds. In like manner, we are taught to believe, that, by removing all the flowers of a melon plant that are furniſhed with *ſtamina*, we render the fruit abortive; and that ſuch abortion is occaſioned, not by the loſs of juice which the plant has ſuſtained from caſtration, but by the inability of the fruit to mature its ſeeds, without the aſſiſtance of the duſt of the *ſtamina*. Were caſtration in flowers to be always attended with the effect juſt mentioned, I ſhould not heſitate to pronounce, notwithſtanding ſome plauſible arguments, that even then might be urged againſt it, that the doctrine of the ſex of plants was eſtabliſhed beyond a doubt. The fact, however, is, that the experiment in queſtion has been performed upon very few plants, and, in many inſtances, has not been attended with the deſired ſucceſs.

2. Another argument for the ſexes ariſes from the ſterility of plants in which, from exceſs of nouriſhment, the *ſtamina* are totally excluded, and degenerate into petals. Of this kind are all full flowers, the ſeeds of which never ripen. Luxuriance of nouriſhment has a ſimilar effect on animals in deſtroying their generative faculties.

3. If, when the tops of the *ſtamina* are cut off, the duſt of a flower of a different ſpecies is ſhaken over the *ſtigma*, or pretended female organ, the ſeeds ripen, and produce plants, which partake of the nature of both the fecundating and fecundated ſpecies. Such plants too reſemble mules in the animal kingdom, and neither generate nor perfect ſeeds.

4. Another argument for the ſexes ariſes from experiments on plants in which the *ſtamina* are produced on one root, and the ſeeds on another. Caſtration, we have ſeen, ſucceeds only in plants which have the *ſtamina* either incloſed within the ſame covers, or placed upon a different part of the ſame plant with the ſeeds. In plants that have the ſuppoſed male and female organs placed upon diſtinct roots obtained from the ſame ſeed, the ſexualiſts pretend, that the impregnation in queſtion is accompliſhed, as in other plants, by the duſt of the *anthers*, which is conveyed by the wind, or ſome other means, and ſhed over the *ſtigma* of the female plant: ſuch plants being, for this purpoſe, as they affirm, generally found in the neighbourhood of one another. Linnæus aſſerts, that a female plant of the roſe-root, which grew in the Botanical Garden at Upſal, was barren from 1702 to 1750, when a male plant being brought, it produced ripe and perfect ſeeds. The ſame author relates, that the genus *clutia* which had been barren in moſt of the gardens in Holland, being found to ripen ſeeds at Leyden, he concluded that a male plant of that ſpecies was in the neighbourhood, which, upon ſtrict ſearch being made for that purpoſe, was found in reality to be the caſe.

5. The culture of palm-trees, as related both by ancient and modern authors, has furniſhed a ſtriking argument for the ſex of plants.

We have already mentioned the teſtimonies of Theophraſtus, Pliny, and Ariſtotle, on this ſubject, who ſeem, however, to ſpeak from the relations of others, more than from their own proper knowledge and experience. Kæmpfer, Proſper Alpinus, Father Labat, Dr. Haſſelquiſt, and other modern writers, have joined their teſtimonies to thoſe

delivered

delivered by the ancients, and agree in aſſerting, that though the date-bearing palm may produce good dates, without the aſſiſtance of the flowering or male palm, yet, that the date-ſtones, which are the ſeed of the plant in queſtion, will not grow.

The two laſt authors having been eye-witneſſes of the culture they deſcribe, deſerve particular attention. "I had the pleaſure, (ſays Dr. Haſſelquiſt, in his journey to Damietta) of ſeeing one of the moſt remarkable ſights in nature. A date-bearing, or female palm, had put forth its bloſſoms from the ſpatha. I went to ſee it, and found a gardener, the proprietor, climbing up the tree, which equalled our largeſt firs in height; *he had a bunch of male flowers, with which he powdered the female, and thus rendered them fertile.*" Again, in a letter to Dr. Linnæus, dated from Alexandria—"The firſt thing I did after my arrival in Egypt, was to ſee the date-tree, the ornament, and a great part of the riches of this country. It had already bloſſomed, but I had, nevertheleſs, the pleaſure of ſeeing in what manner the Arabs aſſiſt its fecundation, which is as follows. When the *ſpadix*, or receptacle of the palm bears female flowers, they ſearch on a male palm for a *ſpadix* which has not yet burſt, or been protruded from its ſheath (ſpatha); this they open, take out the *ſpadix* and cut it lengthwiſe in ſeveral pieces, taking care not to hurt the flowers. A piece of this *ſpadix* with male flowers is put lengthways between the ſmall branches of the *ſpadix* with female flowers, over which is laid a palm-leaf. In this ſituation, continues the doctor, I yet ſaw the greateſt part of the *ſpadices* or heads of flowers which bore their young fruit; but the male flowers, which were intermingled with the female, were withered. The Arab, who informed me of theſe particulars, gave me likewiſe the following anecdotes. Firſt, unleſs they wed, and fecundate the date-tree in this manner, it bears no fruit. Secondly, they always take the precaution to preſerve ſome unopened *ſpathæ* with male flowers, from one year to another, to be applied for this purpoſe, in caſe the male flowers ſhould miſcarry, or ſuffer damage. Thirdly,

Thirdly, *if they permit the ſpadix of the male flowers to burſt or come out, it becomes uſeleſs for fecundation: they muſt have its* VIRGIN-HONOURS, (theſe were the words of the Arab) which are loſt in the ſame moment the bloſſoms burſt out of their caſe. The perſon, therefore, who cultivates date-trees, *muſt be careful to hit the proper time of aſſiſting their fecundation, which is almoſt the only article in their cultivation.*" *Vide* Dr. Haſſelquiſt's Travels in the Levant, p. 112 and 416.

Father Labat's teſtimony reſpecting the fecundation of the female palm by the male, deſerves credit the rather, as this author profeſſes himſelf diſſatisfied with the doctrine in queſtion. His words are theſe. "It is pretended that the date-tree is male and female; that the male flowers, but bears no fruit, that taſk being left to the female, which likewiſe proves barren, unleſs it be ſituated in the neighbourhood, or at leaſt within ſight, of the male. I am ſorry, continues that Reverend Father, that I cannot ſubſcribe to this opinion of the naturaliſts, being prevented by a certain fact, conſiſting with my own knowledge, which is directly contradictory to that opinion. Near our monaſtery in Martinico is a date-tree which bears fruit, though ſingle; whether it is male or female I know not, but of this I am certain, that for more than two leagues round, there was not then, nor, as I am informed, ever had been any tree of the ſame kind; whence we may, I think, reaſonably conclude, that the preſence of the male is not ſo neceſſary for the purpoſe of fecundation as naturaliſts pretend. It may indeed be ſaid, that this tree, in default of a male of its own ſpecies, availed itſelf, like certain animals on the coaſt of Africa, of the prolific virtue of any male in its neighbourhood, whether allied to it or not. In fact, there are ſome cocoa-trees in the neighbourhood of our date-tree, which, in all probability, might have performed the function of the male palm, and rendered our female fruitful." *Vide* Nouveau Voyage aux Iſles de l'Amerique, tom. 3, chap. 2.

Of this conceſſion of the Reverend Father, I do not mean to avail myſelf; becauſe, I ſhall ſoon convince the reader,

from

from that author's own words, that no fecundation, of whatever kind, had taken place in the inſtance in queſtion. For, continues Labat, "*the ſtones of the iſland date-trees will not riſe*; ſo that thoſe who would raiſe palm-trees, are obliged to plant the Barbary date-ſtones, which have the germ or *punctum vitæ* neceſſary for the production of a new plant. Thus we ſee, hens lay eggs without the aſſiſtance of the cock; but theſe eggs cannot be hatched, or produce chickens, becauſe they have not the *germ*, or *punctum vitæ*, which is communicated only by the male." This illuſtration is exceedingly apt, and is indeed the very example I ſhould myſelf have recurred to. It is evident then, that though in the inſtance juſt given, the date, that is, the ſeed-veſſel, attained maturity; yet the ſtones, that is, the ſeeds, however ſeemingly ripe, were barren, and upon trial, found totally incapable of producing their like. M. Labat's miſtake conſiſts in a miſapprehenſion of the term fruit; which is never to be underſtood of the veſſel, or caſe containing the ſeeds, but of the ſeeds themſelves. In the former ſenſe, the fruit may often attain maturity, and yet the ſeeds prove barren. This is what happened to the date-tree of Father Labat; it is what happens in many figs, the fruit of which, in the vulgar acceptation of that word, is merely the common calyx of a number of female flowers that line its internal ſurface.

With reſpect to that part of Dr. Haſſelquiſt's relation, which affirms, that the date-tree, unleſs fecundated by the male, bears no fruit, we are to underſtand the term fruit in its genuine acceptation, of ripe and perfect ſeeds. For that date-trees which prove barren never bear dates, is contradicted by the concurring teſtimony of all the writers on this ſubject. That the dates are greatly meliorated in point of richneſs and taſte, by the aſſiſtance of the male, and that, when ſolitary and barren, they are frequently apt to fall off, before they have attained perfect maturity, are facts which cannot be diſputed; yet their barrenneſs does not hinder them from becoming ſoft, yellow, luſcious; in a word, of ſhewing every indication of perfect ripeneſs, excepting that they retain a

ſlight

ſlight degree of ſharpneſs, which poſſibly might be removed by fecundation.

6. Another argument for the ſexes, is derived from the curious huſbandry of fig-trees, as practiſed to this day in the Levant, and known by the name of caprification.

An ample deſcription of this mode of culture is given under the article CAPRIFICATIO, whither we refer the reader.

7. If the ſtigma, or top of the pointal, is cut off; if its moiſture is abſorbed by continued ſmoke, or long tracts of rain; if ſudden froſts hinder the anthers from opening, or violent rains dilute and carry off their duſt: in all, or any of theſe caſes, no fecundation, ſay the ſexualiſts, will enſue, and the fruit is diminiſhed, both in point of quantity and quality. Abortions of this kind are frequently obſerved in the cherry, almond, peach, plum, apricot, apple, and pear trees, vines, barley, oats, rye, and wheat, when there are long uninterrupted tracts of rain at the time of their flowering. If, on the contrary, the air is dry and ſerene during that ſeaſon, the crop is both excellent and abundant.

"Moſt flowers, ſays Wahlbom, expand themſelves during the influence of a burning ſun, but cloſe at night and in moiſt weather, leſt the water ſhould dilute, and waſh off the powder of the ſtamina, and thus prevent it from impregnating the ſeeds; but that operation once effected, the flowers no longer contract as formerly at nights, nor during the continuance of heavy rains." He adds, "that rye, wheat, many graſſes and plantains, thruſt out their *anthers* when in flower, on pretty long ſtamina, and thus expoſe the incloſed powder to be waſhed away by the rains. The conſequence is, that the florets ſo caſtrated prove abortive; and this abortion taking place in any of the eſculent graſſes, creates a ſcarcity.

Laſtly, another argument for the ſexes, is derived from the diſpoſition of ſome aquatic plants to flower only above the water. "The contrivance of Nature," ſays Geſner, "is truly admirable in the flowers of aquatic plants which are furniſhed with the fecundating duſt. At the time of flowering,

flowering, the flowers being ſpecifically lighter than the water, are carried above its ſurface, that the fecundation may be performed in the air, and the generating ſubſtance may not be diluted by the water."

Water-lily, marſh-aloe, *vallisneria*, pond-weed, and frog's bit, furniſh familiar examples of the circumſtance alluded to. There are, however, ſeveral plants, particularly triple-headed pond-weed, *ruppia*, *iſoetes*, duck meat, wrack or ſea-weed, and ceratophyllum, which flower under the water, either becauſe the duſt of the *ſtamina*, and the moiſture of the *ſtigma*, are of ſuch a nature as not to be affected or altered by it; or, that the former acts only by a ſubtle vapour, analogous to the atmoſphere of electrical bodies.

III. The arguments againſt the ſexes of plants, which come now to be conſidered, are collected by the ingenious Profeſſor Alſton, in his Tyrocinium Botanicum, and in a Diſſertation on the Sexes of Plants, to be found in the firſt volume of the Edinburgh Phyſical and Literary Eſſays. The Doctor's method is to ſtate, from different authors, the ſeveral facts that are adduced in ſupport of the doctrine; and then to refute it by another ſet of facts directly contradictory in their nature to the former. In proſecuting this method, he is frequently betrayed into an acrimony of expreſſion little ſuited to the gravity and dignity of a philoſophical diſcuſſion. He terms the refined and ingenious Sexual Syſtem of Linnæus a *hideous ſuperſtructure*; and his analogies between plants and animals *fulſome and obſcene*; and though he is at every turn complimenting him with "the juſtly-celebrated Linnæus, the prince of modern botaniſts," and ſuch like epithets; yet he ſcruples not to aſſert, that he has done much more prejudice than good to ſcience, and that, in fine, his method in botany is worſe than no method at all. With theſe abatements, the Diſſertation on the Sexes is a ſenſible and ſpirited performance; and, whilſt it diſcovers the author ſuperior to vulgar prejudices and errors, diſplays a laudable averſion to new hypotheſes in philoſophy, that do not to him appear properly ſupported by reaſon and fact.

The objections to Linnæus's arguments, from the ſitua-

tion

tion and proportion of the organs, are puerile and trifling; the facts, mentioned by that author, whether concluſive or not, are certainly true: and, if true, to call them in queſtion, is to add conſiderably to their importance in the ſcale of argument. The ſame may, in general, be ſaid of the argument drawn from the coincidence in point of time, of the *anthers* and *ſtigma:* though, in ſome particular inſtances, as ſpinach, mercury, hemp, maize, and juniper, the *ſtamina* commonly ſhed their duſt before the *ſtigmata* or ſuppoſed female organs have attained maturity.

" In plants which have the *ſtamina* and ſeeds on diſtinct roots, the flowers, ſays Linnæus, generally come out before the leaves, leſt the latter ſhould cover the female organ, and prevent the acceſs of the fertilizing duſt." Willow and poplar are adduced as examples. In theſe inſtances, the fact is certainly as repreſented by the learned author; and the reaſon aſſigned for it, however imaginary, is ingenious. Dr. Alſton finds great fault with Linnæus for qualifying his allegations with a *generally*. General affirmations are, in my opinion, highly proper in diſquiſitions of this kind, where the ſubjects are ſo numerous, that a ſeparate examination of each is impracticable.

The argument for the ſexes from caſtration is attempted to be refuted in two different ways.—1. Suppoſing its effect to be uniformly as repreſented by Linnæus, and the ſexualiſts, it does not follow, ſays Alſton, that the uſe of the powder of the *ſtamina* in fecundating the ſeeds is clearly demonſtrated: as wounds in a neceſſary part of the plant, together with the loſs of juice iſſuing from them, may well account for the conſequent barrenneſs and abortion of the ſeeds. Malpighi affirms, that he produced a ſomewhat ſimilar effect on the ſeeds of tulip, by plucking off the petals before their expanſion. But, 2, ſays Alſton, there is reaſon to deny the fact. In Geoffroy's Experiment on Maize, ſome of the ears ripened a few ſeeds, although the *ſtamina* were entirely cut out before the opening of the *anthers*. An experiment of the ſame kind performed by Dr. Alſton himſelf, deſerves attention. " Obſerving," ſays he, " one year, two

" ſtrong tulips growing together, in an incloſure ſurrounded
" with a tall and thick quickſet hawthorn-hedge, I cut
" down two or three more tulips, which ſtood at ſome diſ-
" tance from them, ſo as to leave none without that inclo-
" ſure, ſave the two I mentioned; out of theſe, gently
" opening the petals, I plucked all the *ſtamina* with their
" *apices* ſtill entire. The conſequence of this too rude caſ-
" tration was a conſiderable extravaſation of the juices in
" the bottom of the flower, and a ſudden decay of the
" *ovarium* or fruit, which never increaſed, but turned yellow,
" ſhrunk and withered. In order to diſcover whether this
" abortion was owing to the wounds, or to the want of the
" duſt of the *apices*, I ſuffered theſe two tulips to remain in
" the place where they were; and next ſeaſon, having ob-
" ſerved the ſame precaution that no other tulip ſhould flower
" within the incloſure, I opened the petals, and took out
" carefully, not the ſtamina, but only all the *apices*, which
" prevented any ſenſible bleeding of the parts. This more
" gentle caſtration, they bore perfectly well; the *ovarium*
" ſuffered nothing in either of them, but increaſed and came
" to maturity, quite full of ſeeds."

Theſe experiments, ſo far from refuting the doctrine of the ſexes, ſeem, in my opinion, to confirm it. For though both Geoffroy and Alſton affirm that the fruit ripened and was filled with ſeeds, yet it does not appear that theſe ſeeds were ripe or capable of vegetation. The ſame thing poſſibly happened to theſe plants, as to the date-tree of Father Labat, which bore ripe dates, the ſtones of which, however, never roſe. Be this as it may, the experiment juſt recited is imperfect and inconcluſive becauſe totally ſilent on that head.

The next ſet of arguments againſt the ſexes is derived from experiments on plants which have the pretended male and female organs of generation placed apart on diſtinct roots. Camerarius relates that, in the courſe of his experiments, he obſerved the female plants of ſpinach, mercury, and hemp, which had been placed without the reach of the male, produce ripe and perfect ſeeds; a circumſtance which,

as Valentini obſerves, made Camerarius expreſs himſelf with doubt of the doctrine of the ſexes, of which he had been a ſtrenuous advocate. The following experiments of Dr. Alſton upon the ſame plants, if faithfully narrated, bid fairer to be deciſive on this ſubject, than half the refined and ingenious arguments of his opponent.

"In ſpring, 1737," ſays the doctor, "I tranſplanted three "ſets of the common ſpinach, long before it could be "known whether they were flowering or ſeed-bearing plants, "from a little bed on which they were raiſed, into a place "of the garden, full eighty yards diſtant, and almoſt direct-"ly ſouth; there being two hawthorn and three holly "hedges, all pretty thick and tall, between them and their "ſeed-bed, and no other ſpinach in the garden; all the three "proved fertile plants, and ripened plenty of ſeeds. I "ſowed them, they grew, and proſpered as well as any "ſpinach-ſeed poſſibly could do.

"The ſame year, a few plants of the common hemp, "which I had raiſed for a ſpecimen from the ſeed, being "accidentally deſtroyed when very young; and finding "afterwards, about the end of June, a pretty ſtrong, but "late plant of hemp, growing by itſelf, I cauſed great care "to be taken of it, there not being that year any hemp raiſed "within a mile of it that I could find. This plant grew "luxuriantly; and, though bad weather in the autumn made "me pluck it up a little too ſoon, yet I got about thirty good "ſeeds from it, which, the ſucceeding ſpring, produced as "thriving male and female plants, as if the mother hemp "had ſtood ſurrounded with males."

It is, I confeſs, a matter of no ſmall difficulty for the Sexualiſts to elude the force of the concluſion manifeſtly deducible from the reſult of theſe experiments, and to explain in a manner that ſhall be ſatisfactory to their opponents, how, on their favourite principle, in the total abſence of male plants, ſeeds ſhould be produced *in great abundance*, which not only *ſeemingly* ripened, as in the caſe of the date-tree of Father Labat, but attained ſuch perfect maturity, as to be capable of vegetation, and actually to vegetate. By

this

his touchſtone, indeed, we are to try the intrinſic value of every experiment which has the determination of the preſent problem for its object: and it is only in conſequence of a ſeries of experiments of the ſame kind, undertaken without prejudice, accurately conducted, well authenticated, and tried by the teſt juſt mentioned, that the doctrine of the ſex of plants muſt ultimately ſtand or fall. It is not enough, however, (and the caution cannot be too often repeated) that plants ſeem only to ripen ſeeds without the aſſiſtance of the *pulvis antherarum*; thoſe ſeeds, to be perfect, and to render the argument concluſive, muſt contain the embryo of a new plant, which, upon being lodged in the ſoil, will unfold itſelf, and produce an individual in every reſpect ſimilar to its parent vegetable. For want of this neceſſary teſt, nothing can be concluded from M. Tournefort's aſſertion of a female hop which produced ripe fruit every year, in the king's garden at Paris, although no male of that ſpecies was to be found within many miles of it. For, without enquiring with Wahlbom, whether the cones of the hop be a calyx or a ſeed-veſſel, which, I think, has nothing to do with the preſent queſtion, I affirm that there is no evidence whatever, from Tournefort's Narration, that the ſeeds which he pretends were produced by this plant, made any efforts towards vegetation, or, indeed, that any trials were made for that purpoſe. The author is quite ſilent on this head; and hence the argument that has been erected upon his aſſertion is totally inconcluſive.

The argument for the ſexes from the culture of palm-trees has never received a ſatisfactory anſwer. Father Labat's teſtimony, which Alſton oppoſes to the clear and pointed evidences of other authors, makes, as we have ſeen, directly againſt him.

As to Herodotus's aſſertion that the date-trees, in the neighbourhood of Babylon, were fecundated by means of gnats, which, lodging in the fruit of the male palm, iſſued from it, and entered into that of the female, it is directly contradicted by the authority of every author, both ancient and modern, who has treated of the culture of palm-trees: and, if true, would but reduce that culture to the head of caprification,

which is, in my opinion, one of the ſtrongeſt arguments for the ſexes that can poſſibly be advanced.

The differences among the authors who treat of the fecundation of date-trees, with reſpect to the manner in which the fertilizing duſt is conveyed to the female, and the conſequences of their ſterility, are much inſiſted upon by Alſton. But theſe differences prove nothing; ſince the authors in queſtion all agree in this, that the dates, to be fecundated, muſt have the aſſiſtance of the *pulvis antherarum* of the flowering palm.

The laſt argument I ſhall mention is drawn from a comparative view of the nature of ſeeds and buds. The ſmalleſt ſenſible particle of every plant, ſays Alſton, after Malpighi, is organized in the ſame manner as the whole. Hence, if planted in the ground, each piece would probably, in progreſs of vegetation, become a plant in every reſpect ſimilar to the parent vegetable. Hence, likewiſe, many plants are better and more eaſily propagated by cuttings, layers, off-ſets, germs or buds, than by ſeeds. Hence, garlick, onions, leeks, tulips, and lilies, frequently carry germs or cloves on the tops of the ſtalks, as well as at their roots under ground. A bud is the compendium or rudiment of a plant which only wants the power of extending or unfolding its parts. But ſeeds contain, likewiſe, the *primordia plantarum*; buds, therefore, contain the moſt eſſential parts of ſeeds, and differ from them only in the ſame manner as the living fœtus differs from the egg. In this view, buds are nothing elſe than ſeeds in a more perfect ſtate, or in a higher ſtage of vegetation. Now ſince buds are copiouſly produced by numberleſs plants, and often break out of the ſmoother part of the bark, eſpecially of pruned trees; and, ſince the ſmalleſt part of a plant may be made to grow, and emit gems, whether it be naturally fertile or barren, male, female or hermaphrodite;—why, continues the Doctor, may not ſeeds, which are only a more imperfect kind of buds, be produced, without the aſſiſtance of the *pulvis antherarum*, or the intervention of any mode of generation whatever?

This

This argument is plauſible, but cannot overturn the direct evidence in favour of the ſexes that has been already ſtated.

I am far, however, from wiſhing to obtrude my opinion upon the reader, or improperly influence his belief. The principal facts on both ſides of this curious and important queſtion lie before him; it belongs to him to eſtimate their credibility and weight, and to determine accordingly. Opinions, if founded in truth, as they cannot be overturned by ſophiſms, ſo neither can they ſuffer from the minuteſt examination. On the contrary, if eſtabliſhed in error, an exact and impartial ſcrutiny is the moſt probable means of removing the deception, by detecting their falſhood.

SILIQUA, a ſpecies of pod, in which the ſeeds are alternately fixed to either future or joining of the valves; in this it differs from the *legumen*, which has its ſeeds attached to one future only. This kind of ſeed-veſſel, which is found in all the croſs-ſhaped flowers of Tournefort, or *tetradynamia* of Linnæus, is diſtinguiſhed, by the laſt author, after Ray, from its form, into *ſiliqua* properly ſo called, and *ſilicula*, or little *ſiliqua*. The former is much longer than broad, as in muſtard, radiſh, rocket, wall-flower, lady's ſmock, and water-creſs. The latter is almoſt round, the longitudinal and tranſverſe diameters being nearly equal; as in honeſty, mad-wort, ſhepherd's-purſe, ſcurvy-graſs, candy-tuft, and ſome other croſs-ſhaped flowers. This difference in the form of the fruit is the foundation of the two orders in Linnæus's claſs *tetradynamia*, which correſponds to the *cruciformes* of Tournefort, and *ſiliquoſæ* of Ray.

The ſeeds within both *ſiliqua* and *ſilicula* are attached, as to a placenta, to the ſutures or joining of the valves, by means of a ſmall thread or foot-ſtalk, which performs the office of the umbilical rope.

SILIQUOSÆ (*ſiliqua*, a pod) the name of a claſs in Moriſon, Hermannus, Ray, and Royen's Methods, conſiſting of plants which have a *ſiliqua* for their ſeed-veſſel. Of this kind are the croſs-ſhaped flowers of Tournefort, and *tetradynamia* or plants having flowers with four long and two ſhort ſtamina of Linnæus.

SILIQUOSÆ is, likewiſe, the name of the thirty-ninth order in Linnæus's Fragments of a Natural Method, conſiſting of plants which have the general character juſt mentioned.

Liſt of Genera contained in this Natural Order.

SECTION I.

Croſs-ſhaped Flowers with long Pods, (ſiliquæ).

Linnæan Genera.			*Engliſh Names.*
Arabis,	—	—	Baſtard tower-muſtard.
Braſſica,	—	—	Cabbage, turnip, rape.
Bunias.			
Cardamine,	—	—	Ladies-ſmock.
Cheiranthus,	—	—	Stock, wall-flower.
Crambe,	—	—	Sea cabbage.
Dentaria,	—	—	Tooth-wort.
Eryſimum,	—	—	Hedge-muſtard.
Heliophila.			
Heſperis,	—	—	Rocket, queen's July-flower, or dame's violet.
Iſatis,	—	—	Woad.
Raphanus,	—	—	Radiſh.
Ricotia.			
Sinapis,	—	—	Muſtard.
Siſymbrium,	—	—	Water-creſs.
Turritis,	—	—	Tower-muſtard.

SECTION II.

Croſs-ſhaped Flowers with ſhort round Pods (ſiliculæ).

Alyſſum,	—	—	Mad-wort.
Anaſtatica,	—	—	Roſe of Jericho.
Biſcutella,	—	—	Buckler-muſtard.
Clypeola,	—	—	Treacle-muſtard.
Cochlearia,	—	—	Scurvy-graſs, or ſpoon-wort.
Draba,	—	—	Whitlow-graſs.
Iberis,	—	—	Candy-tuft, or ſciatica-creſs.
Lepidium,	—	—	Dittander, or pepper-wort.

Linnæan Genera.			*Engliſh Names.*
Lunaria,	—	—	Satin-flower, honeſty, or moon-wort.
Myagrum,	—	—	Gold of pleaſure.
Peltaria.			
Subularia,	—	—	Rough-leaved alyſſon.
Thlaſpi,	—	—	Mithridate-muſtard, ſhepherd's purſe.
Vella,	—	—	Spaniſh-creſs.

Habit and Structure of the Plants of this Order.

This order chiefly furniſhes biennial and perennial herbs of an irregular figure; *braſſica*, ſea-cabbage, Spaniſh-creſs, and ſome ſpecies of ſtock and *thlaſpi*, form ever-green ſhrubs of a round and beautiful figure.

The ROOTS are long, branched, crooked, and fibrous. Thoſe of turnip and radiſh are ſucculent and fleſhy. In tooth-wort, they appear jointed.

The STEMS and young branches are cylindric.

The LEAVES, which differ in point of form, being ſometimes ſimple, ſometimes winged, are generally placed alternate. In a ſpecies of thlaſpi with a red flower, and a perennial ſpecies of moon-wort, the leaves at the bottom of the ſtalk and branches are oppoſite.

From the arm-pits of the leaves of a ſpecies of treacle-muſtard, iſſues a large, erect thorn. The plant is generally known by the name of ſhrubby prickly alyſſon.

The FLOWERS are hermaphrodite, and in the greater number, diſpoſed in a ſpike at the extremity of the branches. They are eaſily rendered double by culture.

The FLOWER-CUP is compoſed of four leaves, which are oblong, hollow, blunt, bunched at the baſe, and fall with the flower. Theſe leaves are ſometimes erect, as in Spaniſh-creſs, radiſh, hedge-muſtard, ſtock, cabbage, rocket, and tooth-wort; ſometimes ſpread horizontally, as in muſtard, water-creſs, woad, and lady's-ſmock.

The PETALS, which are four in number, ſpread at top, and are diſpoſed like a croſs; whence the name of croſs-

ſhaped flowers, by which Tournefort has deſigned this natural order; a characteriſtical mark which, becauſe more obvious, is, in my opinion, preferable to that derived from the inequality of the ſtamina.

The claws, or lower part of the petals, are erect, flat, awl-ſhaped, and ſomewhat longer than the calyx. The upper part widens outwards. In candy-tuft, the petals are unequal, the two outermoſt being much larger than the other two. A ſpecies of lady's-ſmock, the *cardamine impatiens* of Linnæus, as likewiſe the *lepidium ruderale* of the ſame author, want the petals.

The STAMINA are ſix in number, two of which are of the length of the calyx, and the remaining four ſomewhat longer, but ſhorter than the petals. Upon the circumſtance of the inequality of the ſtamina, combined with their number, is founded the claſs *tetradynamia* of the Sexual Method, which contains all the croſs-ſhaped flowers.

The ANTHERS are of an oblong figure, pointed, thicker at the baſe, and erect. In a ſpecies of Spaniſh-creſs, the *vella pſeudo-cytiſus* of Linnæus, the four longer filaments are caſtrated, or want tops. Some ſpecies of dittander have only two ſtamina; a Virginian ſpecies of the ſame genus has three. The two leſſer filaments in mad-wort are indented at the baſe; in which circumſtance conſiſts the eſſential character of the genus. In a ſpecies of lady's-ſmock, the *cardamine hirſuta* of Linnæus, the two leſſer ſtamina are generally wanting. In ſea-cabbage, each of the longer filaments is divided at top into two parts; the *anthers* being placed upon the outermoſt branch.

Betwixt the *ſtamina* in plants of this order, are generally lodged one, two, or four round greeniſh knots, which in ſome genera are ſo ſmall as to elude the ſight. Theſe knots, called by Linnæus GLANDULÆ NECTARIFERÆ, and uſed by that author as an eſſential character in diſcriminating the genera, ſeem to be prominences of the receptacle of the flower, occaſioned by the ſtamina being deeply lodged in its ſubſtance. This opinion ſeems more probable, as in treacle-muſtard, rough-leaved alyſſon, gold-of-pleaſure, and ſome

others,

others, which have the ſtamina ſlightly attached to the ſurface of the receptacle, no knots or glands are obſerved. In baſtard tower-muſtard, the knots in queſtion are placed betwixt the leaves of the calyx, to which they ſeem appendages or ears. In the greater number they are ſeated between, or cloſe to, the ſtamina, particularly the two ſhorter ones, to the baſe of which they are faſtened.

The SEED-BUD is ſingle, and ſtands upon the receptacle of the flower. The *ſtyle*, which is either cylindric, or flat like a ſcale, is of the length of the four longer ſtamina in the plants of the ſecond order; in thoſe of the firſt, it is very ſhort, or even wanting. It accompanies the ſeed-bud to its maturity. The *ſtigma* or ſummit of the ſtyle is blunt; and ſometimes, as in ſtock and rocket, deeply divided into two parts.

The SEED-VESSEL is a long pod in plants of the firſt ſection; a ſhort and round one, in thoſe of the ſecond. Either ſort has two valves or external openings, and in a great many genera, the ſame number of internal cavities, the partition of which projects at the top beyond the valves. In a ſpecies of gold-of-pleaſure, the myagrum monoſpermum latifolium of Caſpar Bauhin, there are three cells, two of which, being thoſe next the top of the pod, prove abortive; the remaining cell at the baſe contains a ſingle ſeed. In radiſh, the pods are jointed; in hedge muſtard, ſquare.

The SEEDS are roundiſh, ſmall, and attached alternately by a ſlender thread to both ſutures or joinings of the valves.

Theſe plants have a watery, ſharp, lixivial taſte, and are charged with a fixed alkaline ſalt, which is drawn from them by burning, and being diſtilled, without any addition, produces a volatile alkali.

Moſt of the plants in queſtion have a ſtinking ſmell. *Eryſimum alliaria*, and a ſpecies of thlaſpi, ſmell ſtrongly of garlick.

With reſpect to their virtues, they are attenuating, deterſive, diuretic, and antiſcorbutic. Theſe qualities, however, are moſt eminently poſſeſſed by the live plants; when

dried, they either entirely diſappear, or are greatly diminiſhed.

Applied externally, theſe plants are uſeful in diſeaſes of the ſkin, as itch and leproſy.

SOLUM *plantarum*. The natural ſoil of plants. Each ſpecies of plant affects a particular ſoil in preference to every other. In the culture of plants, therefore, it is of very great importance to have a diſtinct knowledge of their ſoil and loca natalia, that the nature of the ſoil and earth in which they are cultivated may be made to approach, as near as poſſible, to that in which they ſpontaneouſly grow.

This ſubject then, as is evident, pertains more properly to gardening than botany. To the former, indeed, it ſerves as a proper and ſolid foundation; in the latter it is merely a curious ſpeculation, which, however, cannot fail, if properly handled, of affording inſtruction as well as amuſement.

The reader is referred, for ingenious conjectures on this ſubject, to the head ADUMBRATIONES in Linnæus's *Philoſophia Botanica*.

SPADICEUS *flos*, (from *ſpadix*); an aggregate flower, in which the receptacle is incloſed within a *ſpatha* or ſheath that is common to many florets. This term, uſed by the ancients only of palms, is extended by Linnæus to all flowers which, like narciſſus, calla, dracontium, pothos, arum, and zoſtera, are protruded from that ſpecies of common calyx called a *ſpatha* or ſheath.

SPADIX, anciently ſignified the receptacle of the palms. It is now uſed to expreſs every flower-ſtalk that is protruded out of a *ſpatha* or ſheath.

The ſpadix of the palms is branched; that of all other plants, ſimple. This laſt caſe admits of ſome variety. In calla, dracontium and pothos, the florets cover it on all ſides; in *arum*, they are diſpoſed on the lower part only; and in zoſtera, on one ſide.

SPATHA, a ſheath; a ſpecies of calyx which burſts lengthways, and protrudes a ſtalk ſupporting one or more flowers,

flowers, which commonly have no *perianthium* or proper flower-cup.

The ſpatha opens on one ſide, from bottom to top, and conſiſts either of one piece, as in narciſſus, ſnow-drop, and the greater number of ſpathaceous plants; of two, as in marſh-aloe; or of a number of ſcales laid over one another like tiles, as in plantain-tree.

SPATHACEÆ (from *ſpatha*, a ſheath) the name of the ninth order in Linnæus's Fragments of a Natural Method, conſiſting of plants whoſe flowers are protruded from a *ſpatha* or ſheath.

Liſt of the Genera *contained in this Natural Order.*

Linnæan Genera.			*Engliſh Names.*
Allium,	—	—	Garlick, onion, &c.
Amaryllis,	—	—	Lily-daffodil.
Bulbocodium.			
Colchicum,	—	—	Meadow-ſaffron.
Crinum,	—	—	Aſphodel-lily.
Galanthus,	—	—	Snow-drop.
Gethyllis.			
Hæmanthus,	—	—	Blood-flower.
Leucoium,	—	—	Greater ſnow-drop.
Narciſſus,	—	—	Daffodil.
Pancratium,	—	—	Sea daffodil.

Theſe plants are nearly allied in habit and ſtructure to the liliaceous plants, from which they are chiefly diſtinguiſhed by the *ſpatha* or ſheath out of which their flowers are protruded. *Vide* CORONARIÆ.

SPICA, properly an ear of corn, a ſpike; a mode of flowering, in which the flowers are ranged alternately upon both ſides of a ſimple common flower-ſtalk. The term is exemplified in arum, American night-ſhade, pepper, and ſeveral of the graſſes. The flowers in a ſpike are ſeated immediately upon the ſtalk, without any partial foot-ſtalk, in which it differs from the *racemus* or cluſter. A ſpike is

ſaid

ſaid to be ſingle-rowed (*ſpica ſecunda*) when the flowers are are all turned towards one ſide, as in *dactylis cynoſuroides*; double-rowed (*ſpica diſticha*) when they look to both ſides, or ſtand two ways.

SPINA, a thorn; a ſpecies of armature or offenſive weapon, protruded from the wood of the plant, and, therefore, of a ſtronger and harder nature than prickles, which are detached portions of the bark.

Thorns are either ſimple, as in moſt plants; double, as in horned acacia; or triple, as in another ſpecies of acacia, hence termed triple-thorned.

Spines are protruded either from the ſtem and branches, as in buck-thorn, pear, plum, and orange-trees; from the foot-ſtalks of the leaves, as in falſe acacia; from the leaves themſelves, as in aloe, American aloe, Adam's needle, holly, manchineel, carline-thiſtle, artichoke, bear's-breech, juniper, milk-wort, butcher's-broom, and ſea-pink; from the ribs of the leaves, as in ſeveral of the night-ſhades; from the calyx, as in thiſtle, centaury, and mad-apple; or, laſtly, from the ſeed-veſſel or fruit, as in caltrops, ſpinach, agrimony, and thorn-apple.

Some plants loſe their ſpines, as the branches of pear, citron, orange, lemon, medlar, hawthorn, and gooſeberry buſh, by culture; the leaves of holly, by age.

M. Duhamel compares thorns, which are an expanſion of the lignous body, to the horns of animals, which adhere to the bones of the ſcull, and are protruded from them.

STAMINA, threads or chives. The ſlender threads which in moſt flowers are placed round the ſeed-bud. They are defined by Linnæus to be entrails of the plant, deſtined for preparing the *pollen* or fine powder which the Sexualiſts affirm to be the main agent in the generation of plants.

The form of each ſtamen is generally that of a ſlender thread, ſurmounted by a ſmall prominence or button containing a powder. Hence its diviſion into,

Filamentum, the ſlender thread-ſhaped part reſembling a foot-ſtalk, which ſupports the

Anthera,

Anthera, or ſummit, a ſmall ſack or capſule with one or two cavities, attached differently to the filament.

Pollen, the fecundating duſt contained within the anthers, which diſcharge it when ripe.

Each of theſe terms is particularly explained under its reſpective head.

STELLATÆ (*ſtella*, a ſtar) the name of a claſs in Hermannus, Boerhaave, and Ray's Methods, conſiſting of plants with two naked ſeeds, and leaves diſpoſed round the ſtem in the form of a radiant ſtar. The term is exemplified in madder, lady's bed-ſtraw, croſs-wort, and woodroof.

STELLATÆ is, likewiſe, the name of the forty-ſeventh order in Linnæus's Fragments of a Natural Method, conſiſting of plants which poſſeſs the general characters juſt mentioned.

Liſt of the Genera *contained in this Order.*

	Linnæan Genera.			*Engliſh Names.*
α	*Anthoſpermum*,		—	Amber-tree.
	Aſperula,	—	—	Woodroof.
	Crucianella,	—	—	Petty madder.
	Diodia.			
	Galium,	—	—	Ladies bedſtraw, or cheeſe-rennet.
	Hedyotis.			
	Knoxia.			
	Lippia.			
	Phyllis,	—	—	Baſtard hare's-ear.
	Richardia.			
	Rubia,	—	—	Madder.
	Sherardia,	—	—	Little field-madder.
	Spermacoce,	—	—	Button-weed.
	Valantia,	—	—	Croſs-wort.
β	*Houſtonia.*			
	Oldenlandia.			
	Ophiorrhiza.			
	Spigelia,	—	—	Worm-graſs.

Linnæan Genera.			*Engliſh Names.*
Coffea,	—	—	Coffee-tree.
Cornus,	—	—	Dogwood, or cornelian cherry.
Ixora.			
Pavetta.			
Pſychotria.			

This order, which, in its preſent form, is far from Natural, contains herbs, ſhrubs, and trees. The herbs, which are moſt numerous, are chiefly annual, and creep along the ſurface of the ground. The ſhrubs and trees are chiefly evergreens, which riſe erect, and are of an agreeable conic form.

Theſe plants are of an opening nature; their ſeeds, particularly thoſe of coffee, are bitter and cordial. *Galium verum* poſſeſſes the property of curdling milk. The roots of madder are greatly eſteemed by dyers for the beautiful-red colour which is procured from them. A ſpecies of hedyotis poſſeſſes the ſame quality. An infuſion of arapabaca or *ſpigelia* is ſpecific againſt worms; whence the Engliſh title of wormgraſs by which this genus of plants has been deſigned. The roots of ophiorrhiza, as the name imports, preſerve from the dangerous conſequences of the venomous bites of ſerpents.

STIGMA, (properly a mark or brand, à στιζω, pungo,) the ſummit of the ſtyle, accounted by the ſexualiſts the female organ of generation in plants, which receives the fecundating duſt of the tops of the ſtamina, and tranſmits its vapour or effluvia through the ſtyle into the heart of the ſeed-bud, for the purpoſe of impregnating the ſeeds.

Moſt plants have a ſingle ſtigma. Lilac has two of theſe organs; bell-flower three; in French willow, herb, and graſs-of-Parnaſſus, they are four in number; in winter-green, five. With reſpect to figure, the ſtigma is either round, as in primroſe; oval, as in genipa; croſs-ſhaped, as in penæa; ſhaped like a target, as in water-lily, poppy, and

and ſide-ſaddle flower; in the form of a crown, as in winter-green; hooked, as in violet and American viburnum; ribbed or furrowed, as in meadow-ſaffron; ſhaped like a head (*capitatum*) as in periwinkle, caltrops, ſcarlet-convolvulus, and cluſia; angular, as in muntingia; of the nature of a leaf, as in iris; or covered with down, as in cucubalus, rhubarb, tamariſk, the graſſes, and moſt of the pea-bloom flowers.

The diviſions of the ſtigma are ſlender like hairs, as in dock; twiſted into ſeveral convolutions, as in crocus; turned backwards, as in campanula, pink, and the compound flowers; or bent to the left as in viſcous campion. Theſe diviſions are generally two in number; in aſarabacca, the ſtigma is deeply cut into ſix parts, and in turnera, more ſlightly into a greater number.

The number of ſtyles is to be reckoned from their immediate inſertion into the ſeed-bud. Whatever diviſions are above that inſertion, are only ſegments of the ſtyle or ſtigma. Without attending to this diſtinction, we might frequently be apt to refer certain genera of plants, from a ſuperficial view of the number of their ſtyles, to an improper order in Linnæus's Method, the ſecondary diviſions of which are derived from the number of ſtyles, reckoned, as we have ſaid, from their inſertion into the ſeed-bud.

In flowers which have no ſtyle, the ſtigma adheres to the ſeed-bud; and its number, like that of the ſtyles, ſerves as a foundation to the orders in the Linnæan Method of arrangement. Thus poppy, prickly poppy, celandine, may-apple, herb-chriſtopher, caper, and water-lily, which have a ſingle ſtigma, are referred to an order of plants having one ſtyle, although the ſtyle in theſe plants be totally wanting.

With reſpect to duration, the ſtigma generally withers without falling off; in poppy, water-lily, and ſide-ſaddle-flower, it is permanent.

The ſurface of the ſtigma is covered with a clammy moiſture, which ſerves to diſſolve the particles of the fertilizing duſt of the anthers, and thereby more eaſily tranſmit its effluvia and eſſence, which Linnæus calls the *aura feminalis*,

to the ſeeds below. The experiments of Juſſieu, Vaillant, and Needham, have left no room for doubt on this matter.

The ſtigma, when ſingle, generally terminates the ſtyle. When there are ſeveral *ſtigmata*, as in cotton, and moſt of the liliaceous plants, they are diſpoſed with admirable ſymmetry along its ſides. In American *viburnum*, *petrea*, and *lippia*, the *ſtigma*, which is ſingle, is placed upon the ſide of the ſtyle, or rather obliquely on its extremity.

STIMULI, ſtings; a ſpecies of armature or offenſive weapon, with which ſome plants, as nettle, *caſſada*, *acalypha*, and *tragia* are furniſhed. Their uſe, ſays Linnæus, is, by their venomous punctures, to keep off naked animals that would approach to hurt them.

STIPES properly ſignifies the trunk of a tree. By Linnæus it is uſed to denote the trunk of the muſhrooms, the baſe of the footſtalk in the fern and palm tribes, as likewiſe the ſlender thread, which, in many of the compound flowers, elevates the feathery or hairy crown (*pappus*) with which the ſeeds are furniſhed, and connects it with the ſeed. The appearance in queſtion is conſpicuous in gum-ſuccory, dandelion, baſtard hawk-weed, *ſeriola*, *hypochoeris*, colt's-foot, and ſome ſpecies of wild lettuce.

STIPULA, (ſtraw, ſtubble); one of the *fulcra* or ſupports of plants, defined by Linnæus to be a ſcale or ſmall leaf, ſtationed on each ſide the baſe of the foot-ſtalks of the flower and leaves at their firſt appearance, for the purpoſe of ſupport. Elmgren reſtricts it to the foot-ſtalks of the leaves only

Malpighi was the firſt who made obſervations on the number, figure and ſituation of this auxiliary part of the plant. Linnæus has improved upon Malpighi's obſervations, and called in the *ſtipulæ* as eſſential characters in diſcriminating the ſpecies.

The appearance in queſtion is conſpicuous in tamarind, caſſia, roſe, honey-flower, tulip-tree, apricot, peach, bird-cherry, and the pea-bloom flowers.

Stipulæ exhibit the ſame variety in form and ſtructure as the leaves, at whoſe inſertion they are frequently placed.

The

The greater number of plants have two *ſtipules*, one on each ſide of the foot-ſtalk: in the African ſpecies of honey-flower and butcher's broom, there is only a ſingle ſcale of this kind, which, in the former, is placed on the inſide, in the latter, on the outſide of the ſtalk.

With reſpect to duration, ſome *ſtipulæ* fall before the leaves, as in cherry, bird-cherry, almond, poplar, lime, elm, oak, beech, horn-beam, hazel-nut, birch, alder, fig, and mulberry: others are permanent, or continue till the fall of the leaves, as in roſe, raſpberry, ſtrawberry, cinquefoil, tormentil, avens, and the pea-bloom flowers.

In moſt plants the *ſtipulæ* are detached from the ſtalk: in roſe, cinquefoil, *comarum*, raſpberry, and honey-flower, they grow cloſe to the plant.

In fig and mulberry-trees, the *ſtipulæ* are produced on the inſide of the leaves: in birch, lime, and the pea-bloom flowers, on the outſide; in platanus, they form a ſort of ruff, which ſurrounds the branches.

Laſtly, in the lipped, and croſs-ſhaped flowers of Tournefort, the rough-leaved and ſtarry plants of Ray, the natural order *orchideæ*, the liliaceous plants, and ſeveral of the compound flowers, the *ſtipulæ* or ſcales in queſtion are wanting.

The *ſtipulæ* frequently afford excellent marks of diſtinction in diſcriminating the ſpecies. Thus, the African and Ethiopian ſpecies of honey-flower are eſſentially diſtinguiſhed from one another by the number and ſituation of the *ſtipulæ*; which, in the former, are ſingle, and grow cloſe to the ſtalk: in the latter, double, and detached from it. In like manner, the kidney-ſhaped, and bearded or hairy *ſtipulæ* of *caſſia auriculata* diſtinguiſh that ſpecies from all its congeners.

STROBILUS, (properly a pine-apple, as likewiſe an artichoke, which in figure reſembles it);—in the modern botanical nomenclature, a cone; a ſpecies of ſeed-veſſel compoſed of woody ſcales, which are placed againſt one another, and ſplit only at top, being fixed below to an axis which occupies the centre of the cone. The term is exemplified in pine, fir, cypreſs, and the other cone-bear-

ing plants, whoſe habit and ſtructure are particularly deſcribed under the article CONIFERÆ, which ſee.

STRUCTURA *vegetabilis*. The ſtructure or internal organiſation of plants.

The organiſation and internal ſtructure of the different parts of vegetables, ſuch as the ſtems and branches, the leaves, the calyx, the petals, and ſeeds, is not exactly the ſame; in ſome they are formed of two or three, in others of all the ſimple organical parts contained in the bark and wood of the ſtem, in which the organiſation is moſt apparent.

The bark of the trunk is compoſed of four ſimilar parts; viz. I. the epidermis, cuticle or ſcarf-ſkin, which infolds the beds of the bark. II. Veſſels containing the ſap. III. Veſſels containing the blood or proper juice of the plant. IV. The cellular web or tiſſue.

I. The epidermis is a very fine membranous ſubſtance ſpread over the bark, and is always tranſparent and elaſtic, without colour or any ſenſible organiſation, ſome very ſmall pores excepted, which are ſometimes diſcovered in its ſubſtance, and probably ſerve the double purpoſe of throwing off the ſuperfluous nouriſhment, and imbibing new.

II. The ſap-veſſels are woody longitudinal fibres, which are hollow, and almoſt inconceivably fine. They are devoid of ramifications, and ſo ſituated, with reſpect to one another, as to form a web of ſeveral bundles in form of a net, the meſhes of which are longer than broad. Theſe ſmall bundles are the true vegetable muſcles, and differ in their figure from thoſe of animals, which are formed of large maſſes of fibres accumulated one above another.

III. The proper veſſels, called likewiſe, from their uſe, vegetable blood-veſſels, are ſtraight longitudinal fibres, larger than the ſap-veſſels, and leſs numerous. They are filled with the proper juice, which is generally coloured, and is, in fact, the blood of the plant. Of this kind is the milk of ſpurge, dog's-bane, and fig, the yellow juice of celandine, the reſin of fir and pine-trees, and the mucilage of plants of the mallow tribe.

IV. The

IV. The cellular web, or tiſſue, is an aſſemblage of little bladders, without any ſenſible communication, which fill the interſtices of the net formed by the ſap-veſſels, and traverſe the whole ſubſtance of the bark and wood, from the pith, or medullary ſubſtance in the centre, of which it is only a prolongation, to the epidermis or ſkin of the bark, where it is much ſlenderer than towards the centre of the wood.

The ſubſtance in queſtion is diſtinguiſhed by different names from the ſtructure of the parts in which it is found. When contained in the ſmall meſhes of the woody longitudinal fibres or ſap-veſſels of the trunks and roots of trees, it is termed, as we have ſaid, the cellular tiſſue; when collected into larger voids, formed by meſhes that are placed more remote from each other, as in the leaves, it takes the name of parenchyma; when it forms a bed betwixt the epidermis, and the beds of the bark, as happens in the bark of herbs, and of the young branches of trees, it is termed the cellular cover: and when collected in the heart of the plant within the wood, is known by the name of the pith, marrow, or medullary ſubſtance.

In its ſtate of parenchyma and cellular cover, each bladder is of a deep green colour, herbaceous and ſucculent.

The pith, as we have juſt obſerved, is only a modification of the cellular tiſſue. This appears from its originally aſſuming the exact form, colour, and conſiſtence of that ſubſtance. Thus, the pith of all the new productions of trees conſiſts of a number of oval, green, and ſucculent bladders, exactly like thoſe of the bark and wood; and it is not till the end of one or two years, that theſe bladders become empty, dry up, aſſume a ſpherical form, and finally take the conſiſtence and colour of pith, which, in the greater number of plants, is white; in ſome, as horſe-cheſnut, yellow, or ruſt-coloured; in others, as walnut, brown; and in others, red.

The principal ſeat of the pith in thoſe plants which abound in it, is in the heart of the lignous body, where it is contained as in a tube, which ſerves to diffuſe it into the ſubſtance of the wood and bark. Herbs and ſhrubs have, in

general, a greater quantity of pith than trees. In elm, oak, hazel, pear and apple-trees, there is ſcarce any pith; in guaiacum, ebony, iron-wood, and the roots of tobacco, and thorn-apple, it is entirely wanting. Walnut, holly, aſh and pine, have but an inconſiderable quantity: elder-tree, hawthorn, fig-tree, ſumach, and wormwood, produce it in great abundance.

Notwithſtanding its thickneſs, the pith in the heart of trees diſappears inſenſibly; the canal which contains it, as the plant waxes old, contracts itſelf by degrees, and the loſs of pith is ſupplied by the enlarged dimenſions of the ſap and blood-veſſels which traverſe its ſubſtance, although leſs ſenſible to obſervation in its ſtate of pith. It is doubtleſs theſe veſſels, at firſt inſenſible, which furniſh the turpentine that oozes from the pith of pine and fir trees.

The bladders of the medullary ſubſtance are larger in the centre than towards the body of the wood; and it is obſerved in general, that thoſe herbs which have the greateſt quantity of pith have likewiſe the largeſt bladders. The ſame does not hold in trees. Elder-tree has a great quantity of pith, yet very ſmall bladders.

The innermoſt part of the bark, or that which is next the wood, is termed *liber*, from its fine and thin plates reſembling the leaves of a book.

The wood, or lignous body, is compoſed of the ſame conſtituent parts as the bark, except the epidermis, which, in that body, is ſupplied by the bark itſelf. It likewiſe poſſeſſes a fourth part, or ſeries of veſſels, not to be found in the bark. Theſe are the tracheæ, or veſſels which receive and tranſmit the air neceſſary for preparing and giving motion to the humours.

The tracheæ, or air veſſels, are tubes formed of elaſtic plates twiſted ſpirally in a direction contrary to the apparent diurnal motion of the ſun. Theſe tubes are of larger diameter than all the other veſſels that are found in the wood, or bark, even thoſe containing the proper juice or blood of the plant, and, according to the obſervation of Malpighi, are larger in the roots than in the trunk.

The lignous beds are, at firſt, ſoft and tender, and acquire ſolidity only by degrees. They form ſo many concentric circles or rings, the outermoſt of which, or thoſe next the bark, being of later production, are ſofter and leſs coloured than thoſe which are lodged nearer the centre. It is theſe innermoſt beds that form the body of the wood properly ſo called: the outer beds, which are of a much ſofter texture, and frequently of a different colour, being called alburnum, which is only another term for tender imperfect wood, that has not yet acquired its ultimate degree of ſolidity. This ſubſtance is only found in the hard woods, ſuch as ebony, pomegranate, oak, and pine-trees. In the ſoft woods, on the contrary, which never acquire any great degree of ſolidity, ſuch as baobab, ſilk-cotton tree, lime-tree, aſpen, alder, and birch, there is no alburnum, or, perhaps, to ſpeak more properly, there is no wood; the lignous body remaining always in its firſt ſtate of alburnum, without acquiring any further degree of ſolidity.

Such, in general, is the organiſation of vegetables, which in no part is ſo conſpicuous as in the ſtem. The ſame organiſation, according to Grew, obtains in every part of the plant, as the root, leaves, and each, even the minuteſt, part of fructification. More recent experiments on this ſubject ſeem, however, to evince, that the ſtructure of all the parts is not exactly the ſame; a few of the conſtituent parts of the ſtem being entirely wanting in ſome of the other parts.

The external parts of plants are by ſome modern naturaliſts denominated productions and terminations of the internal. The leaves, *bracteæ*, and calyx, are conſidered by ſuch authors as prolongations of the coarſe outer bark; the petals and ſtamina of the liber or fine inner bark; the *piſtillum* of the pith. The wood is, in ſome ſort, the ſkeleton or maſs of bones which preſerves all theſe parts in their place, and concurs with them in performing the vital functions. Hence in the opinion of theſe authors, the bark and pith conſtitute the eſſence of the vegetable body.

Notwithſtanding theſe aſſertions, it is certain that the organiſation of the leaves is nearly the ſame with that of the

ſtem. They are, in fact, a ſort of flat compreſſed ſtems, compoſed, like the part laſt mentioned, of an epidermis, a cortical body on both ſides, and a lignous body in the centre. They differ only in two particulars: 1, That their epidermis, or ſcarf-ſkin, is furniſhed with a number of cortical glands, which, in herbaceous vegetables, are lodged on both ſurfaces; in trees, on the under ſurface only. 2, That the cellular tiſſue or parenchymatous ſubſtance is found in much greater abundance in the leaves than ſtems of plants, and is always green and ſucculent, never paſſing into the ſtate of pith.

The calyx, or external cover of the flowers, which is generally green, does not differ ſenſibly in its organiſation from the leaves, unleſs that it frequently wants the lignous body.

The petals ſeem almoſt entirely compoſed of *tracheæ*, or air-veſſels. They want the cortical glands in their epidermis, which are found on the ſurface of the leaves and flower-cups.

For further obſervations on the anatomy of plants, the reader is referred to the works of Grew, Malpighi, and Duhamel, who have handled this curious ſubject with the utmoſt accuracy and minuteneſs.

STYLUS, the ſtyle; the ſlender part of the *piſtillum* or female organ, reſembling a pillar, and correſponding to the *vagina* in animals, which ſtands upon the ſeed-bud, and elevates the *ſtigma*.

The number of ſtyles, generally ſpeaking, is equal to that of the ſeed-buds, each ſeed-bud being furniſhed with its own particular ſtyle. The compound flowers, cone-bearing plants, roſe, ranunculus, tulip-tree, and many other plants, evince this to be their natural ſtructure.

There are, however, plants which have more than one ſtyle for a ſingle ſeed-bud, as the umbelliferous plants; and there are others, which, on the contrary, have a ſingle ſtyle common to many ſeed-buds, as the rough-leaved plants and moſt of the lipped-flowers. In a third ſet of plants which ſeem to form a medium betwixt the two former, the ſtyle is ſingle

at

at its origin, but ſoon branches out into as many ramifications as there are cells in the cavity of the ſeed-bud. Of this kind are the plants of the geranium and mallow tribes, which have their ſtyles divided above into five branches, correſponding to the five diviſions of the ſeed-bud or capſule.

The diviſions or branches juſt mentioned are either two in number, as in perſicaria, cornutia, and ſebeſten, in which laſt the ſtyle is forked, each of the two branches being ſubdivided into two; three, as in clethra and frankenia; four, as in buckthorn and alaternus; or five, as in Syrian mallow.

The number of ſtyles, and in their abſence, of *ſtigmata*, ſerves as a foundation to moſt of the orders or ſecondary diviſions in the ſexual method.

With reſpect to figure, the ſtyle is either cylindrical and hollow like a tube, as in moſt plants; angular, as in Indian flowering-reed and ſome liliaceous plants; awl-ſhaped, as in geranium; ſlender like a hair, as in *ceratocarpus*; or club-ſhaped above, as in greater ſnow-drop.

In point of proportion and dimenſions, the ſtyle is either of the length of the *ſtamina*, as in tobacco, and moſt plants; very long, as in tamarind, caſſia, campanula, viper's-graſs, Turkey-wheat, and the nodding or drooping flowers, as ſnow-drop and fritillaria; very ſhort, as in dog's bane, red jaſmine, and moſt of the other plants of the natural order, *contortæ*; thicker than the *ſtamina*, as in greater ſnow-drop; of equal thickneſs, as in dead-nettle; or ſlenderer, as in *ceratocarpus*.

In the greater number of plants, the ſtyle is ſeated upon the ſummit of the ſeed-bud; in roſe, raſpberry, ſtrawberry, cinque-foil, tormentil, avens, dryas, and marſh-cinque-foil, the ſtyles, which are numerous, iſſue from within the ſide of their reſpective ſeed-buds. In furiana, hirtella, ladies-mantle, percepier, and cocoa-plum, they are frequently produced at the baſe of the ſeed-bud: and in caper and burning-thorny-plant they ſtand both above and below it.

With reſpect to duration, the ſtyle either falls with the other parts of the flower, as in moſt plants; or accompanies

the fruit to its maturity, as in the croſs-ſhaped flowers, the *tetradynamia* of the ſexual method.

SUCCULENTÆ (*ſuccus*, juice) the name of the thirteenth order in Linnæus's fragments of a natural method, conſiſting of flat, fleſhy, ſucculent plants, moſt of which are evergreen.

Liſt of the Genera *contained in this Order.*

	Linnæan Genera.	*Engliſh Names.*
α	*Aizoon.*	
	Cactus, — —	Melon-thiſtle, torch-thiſtle, Indian-fig.
	Galenia.	
	Meſembryanthemum, —	Fig-marigold.
	Neurada.	
	Reaumuria.	
	Tamarix, — —	Tamariſk.
	Tetragonia.	
β	*Cotyledon,* — —	Navel-wort.
	Craſſula, — —	Leſſer orpine.
	Penthorum.	
	Rhodiola, — —	Roſe-root.
	Sedum, — —	Leſſer houſe-leek, ſtone-crop.
	Sempervivum, — —	Houſe-leek.
	Septas.	
	Suriana.	
	Tillæa, — —	Small annual houſe-leek.
γ	*Claytonia.*	
	Nama.	
	Portulaca, — —	Purſlain.
	Seſuvium.	
	Trianthema, — —	Horſe-purſlain.
δ	*Adoxa,* — —	Tuberous moſchatel, or hollow-root.
	Chryſoſplenium, — —	Golden ſaxifrage.
	Hydrangea.	
	Mitella, — —	Baſtard American ſanicle.
	Saxifraga, — —	Saxifrage.
	Tiarella.	

I decline

I decline entering into the characters of this numerous order, as I cannot regard it in any other light than as an aſſemblage of two or three natural orders, the characters of which ought, therefore, to be preſerved diſtinct.—The ſucculent plants are refreſhing, aſtringent, and of very wholeſome uſe.

The leaves of purſlain are uſed in ſallads, as are likewiſe the berries of the opuntias (*Cactus*).

The fruit of tamariſk is aſtringent, and uſed in hæmorrhages.

The juice of the leaves of houſe-leek is an excellent coſmetic.

Galenia has a warm, poignant, and ſomewhat aromatic taſte reſembling pepper, which, however exceeds it in ſtrength.

Externally, the leaves of purſlain are ſucceſsfully employed in St. Anthony's fire, and other inflammations of the ſkin. The Americans apply the cereus's or torch-thiſtles, to promote the union of fractured bones.

From the *anacampſeros purpurea* of Bauhin, the *ſedum foliis planiuſculis* of Linnæus, is procured by maceration, a water, which is reckoned by the Siberians an excellent vulnerary, and in ſuch eſtimation, ſays Gmelin, that they ſcruple not to believe it endued with the ſingular virtue of raiſing the dead to life.

Indian-fig, the *cactus ficus Indica* of Linnæus, has no ſtem. The leaves, which are fleſhy, thick, and oval, grow out of one another as by joints. At the ſummit of the leaf iſſues the flower. The plant does not riſe high, and in ſome ſort creeps. The briſtly ſpines or prickles, with which the leaves are armed, harden as the plant increaſes in age. Indian-fig is refreſhing, and ſtains the urine of ſuch as uſe it internally of a red colour.

The cochineal ſhrub is the *cactus cochinillifer* of Linnæus. The leaves are two fingers thick, of a beautiful green, and very prickly. The flowers are of a pale roſe-colour, and ſucceeded by a fig-like fruit, which, when ripe, is full of a deep purple pulp, containing a number of very ſmall flat

rough ſeeds that are as red as blood within. Upon this plant, which is a native of Mexico and the Weſt-India Iſlands, is found the inſect or bug called cochineal, which is uſed by the dyers as their principal baſis for the ſcarlet colour. It is a ſix-legged viviparous inſect, the female of which is only uſed. This is produced from the egg in its perfect form, and undergoes no transformation afterwards. It has no wings, nor, indeed, has it uſe for any, the greateſt part of its life being ſpent on the vegetable whereon it feeds. Father Plumier was the firſt who corrected the miſtaken notion, which had long univerſally prevailed, of its being a vegetable production; M. de Reaumur firſt explored with accuracy its natural hiſtory and origin.

SUCCUS. The juices of plants.

The vegetable juices or fluids are generally reduced to two; the lymph or ſap; and the blood or proper juice. It appears, however, that plants contain many other fluids; for in a ſingle fruit, ſuch as a pine-apple, orange or ſtrawberry, we can diſtinguiſh by the taſte and ſmell three or four other liquors, of which we can diſcover but very feeble veſtiges in the other parts of theſe plants.

The ſap or lymph, is a ſimple fluid, without colour or ſmell, and little different from water. It may be compared to the chyle in the animal œconomy, as may the roots which abſorb and prepare it to the lacteals. It is purified, as the blood of animals, by perſpiration.

That the ſap or lymph aſcends from the root to the ſtem, branches, leaves, and even the minuteſt parts of the fructification, is paſt a doubt. But whether the ſap ſo diffuſed to the extremities of the plant ever returns, and there is in plants, a circulation of ſap, analogous to that of the blood in animals, is a queſtion which will probably never receive a ſatisfactory anſwer, as the data required for its ſolution are exceedingly numerous, and almoſt without our reach, and conjecture almoſt the only evidence of which the ſubject is ſuſceptible. The two hypotheſes, however, of the circulation of the ſap, and the perſpiration of plants, are very far from being oppoſite in their nature and reſult, as is generally imagined;

imagined; but, on the contrary, are perfectly compatible with each other.

By the accurate experiments of M. Bonnet, it appears that the ſap aſcends, not by the bark, but by the fibres of the wood; and the curious obſervations of Grew, Duhamel, and other naturaliſts, render it highly probable that the fluid which aſcends by the fibres of the wood, deſcends to the roots by the cortical fibres that are moſt contiguous to the wood. In ſupport of this concluſion, it has been obſerved, that upon a tranſverſe inciſion being made into the trunk of a tree, the juice, which is expended, or flows from the wound, proceeds in greater quantities from the upper lip, where the ſwelling likewiſe is much larger than below. It appears, however, that when two ſimilar inciſions are made, one at the top of the tree, and another near the root, the latter expends much more ſap than the former. The return of the ſap from the extremity of the branches to the roots being, by the reſult of ſuch experiments, rendered ſomewhat more than probable, it remains that we eſtabliſh the mode of its return, and aſcertain its analogy, or want of analogy, to the circulation of the blood in animals. It is here that certainty fails us, and vague conjecture muſt ſupply its place. Before any thing ſatisfactory can be expected on this head, we muſt previouſly determine, whether the liquor which deſcends from the branches by the bark, be the ſame as that which aſcends from the root by the wood; and next diſcover the anaſtomoſes or joinings of both ſeries of veſſels, in other words, the communication betwixt the cortical and lignous fibres:—a *deſideratum* which, if we may reaſon by analogy, will not be obtained without the utmoſt difficulty, ſince, with the aſſiſtance of injections, we have not yet been able to diſcover but obſcurely the anaſtamoſes of the veins and arteries in the animal ſyſtem.

In ſpring, the ſap is found in greateſt abundance, and then the bark is eaſily detached from the wood. On the contrary, when the ſap-ſeaſon is paſt, the bark is found cloſely applied, and, as it were, glued to the wood. The leaves contribute greatly both to the abundance and motion

of

of the ſap. If a tree, when high in ſap, is diveſted of its leaves, the bark, in a few days, will adhere as cloſely to the wood as in winter.

The other ſort of fluid contained in plants is denominated the proper juice, and is analogous to the blood in animals. It is a compound liquor, and is eaſily diſtinguiſhed by its colour, ſmell, or ſubſtance from the lymph or ſap.

This fluid is either green, as in periwinkle; white, as in ſpurge, fig-tree, and dog's-bane; yellow, as in celandine; red, as in log-wood, and dragon's-blood; mucilaginous or gummy, as in the jujube and mallow-tribes; or reſinous, as in the cone-bearing plants. It is from this variety in colour and ſubſtance, that the liquor in queſtion is called the proper juice; each ſpecies of plant being ſuppoſed to contain a fluid which is proper and peculiar to it.

In this blood or proper juice reſide the ſmell, taſte, and virtue of the plants. In fact, thoſe plants poſſeſs little virtue, in which there is either a ſuperabundance of ſap, or a poverty of blood. It is the juice which flows from the poppy that is narcotick; the corroſive quality of celandine and ſpurge reſides in the ſame fluid; the purgative virtue of jalap in its reſin. Barks poſſeſs more virtue than woods, becauſe the blood-veſſels of the former are thicker and larger than thoſe of the latter.

The blood or proper juice is contained in tubes which are larger than the lymphatic or ſap-veſſels, and although diffuſed through the whole ſubſtance of the plant, are collected in greater abundance in the bark. In fir-trees, the turpentine, which is the proper juice, is amaſſed in the parenchymatous ſubſtance, immediately under the epidermis or ſkin of the bark: in juniper, the ſandarac is collected betwixt the bark and the wood: in the larch-tree, the turpentine which it produces is accumulated in the body of the wood: in pine, it exſudes from the bark, from betwixt the wood and bark, from the wood itſelf, and from the pith.

For further particulars on this intereſting phyſiological ſubject, the reader is referred to M. Duhamel's Traité des

Arbres,

Arbres, Dr. Grew's Anatomy of Plants, and the works of the ingenious M. Bonnet of Geneva.

SYNGENESIA (συν, together, and γενεσις, generation) the name of the nineteenth claſs in Linnæus's Sexual Method, conſiſting of plants in which the *anthers* or male organs of generation are united into a cylinder, the filaments on which they are ſupported being ſeparate and diſtinct.

This claſs contains the numerous tribe of compound flowers, whoſe general characters were enumerated under the article COMPOSITUS *flos*.

The orders or ſecondary diviſions of the claſs *Syngeneſia* ariſe from the different modes of intercommunication of the florets or leſſer partial flowers contained within the common calyx. This intercommunication, which Linnæus, from a love to analogies, terms the POLYGAMY OF FLOWERS, admits of the four following caſes.

I. The florets all hermaphrodite.

II. Hermaphrodites and females.

III. Hermaphrodites and florets of no ſex or neuter.

IV. Males and females.

When the florets are all hermaphrodite, as in the firſt caſe, the polygamy is ſaid to be equal, and the compound flowers ſo characterized are referred to the order *Polygamia Æqualis*, expreſſive of that circumſtance. This order contains the ſemifloſcular, and many of the floſcular, compound flowers of Tournefort. Among the former are dandelion, ſow-thiſtle, lettuce, ſuccory, goat's beard, nipple-wort, and hawk-weed; among the latter, burdock, ſaw-wort, thiſtle, artichoke, hemp-agrimony, goldylocks, and Lavender-cotton. This order contains no radiated flowers.

In the ſecond caſe, the florets in the centre or diſk are hermaphrodite; thoſe of the circumference, margin, or radius, female, that is, want the *ſtamina* or male organs. This ſort of intercommunication Linnæus terms *polygamia ſuperflua*, uſeleſs or ſuperfluous polygamy, becauſe the impregnation of the female florets in the circumference is unneceſſary, the fructification being perfected in thoſe of the centre. The flowers which are referred to this order are

either

either floſcular, that is, compoſed entirely of hollow florets; or radiated. Among the former are tanſy, wormwood, cud-weed, and flower-everlaſting; among the latter, colt's-foot, groundſel, aſter, golden-rod, elecampane, daiſy, feverfew, milfoil, and African marigold.

In the third caſe, the hollow florets in the centre are hermaphrodite; the flat ones in the circumference, neuter, that is, want both male and female organs. This kind of polygamy is termed properly enough *ineffectual (polygamia fruſtranea)* as the florets in the circumference being of no ſex are totally ineffectual to the fructification. The order in queſtion contains only ſix genera: viz. ſun-flower, dwarf-ſun-flower, tickſeeded ſun-flower, *gorteria*, *oſmites*, and centaury.

In the laſt caſe, the florets of the centre or diſk are male, and thoſe of the circumference, female. This ſort of polygamy is termed, *neceſſary (polygamia neceſſaria)* becauſe none of the florets being hermaphrodite, the preſence of male and female florets is abſolutely neceſſary for perfecting the fructification. Marigold, arctotis, African ragwort, hard-ſeeded chryſanthemum, cotton-weed, *(filago)* and baſtard cud-weed, furniſh examples. The flowers of this order are moſtly radiated.

Beſides the four orders juſt mentioned, the claſs *ſyngeneſia* contains two others. Theſe are *polygamia ſegregata*, and *monogamia*.

The firſt derives its name from the florets being *ſeparated* from one another by means of partial flower-cups, which ſupport one or more florets, and are placed within the common calyx. This order furniſhes no diſtinct caſe of polygamy, and is, in fact, only a modification of the firſt caſe; the florets ſo ſeparated being all hermaphrodite, except in the genus *ſphæranthus*, which having hermaphrodite florets in the centre, and female florets in the margin, is referred to that particular ſpecies of polygamy which we denominated *ſuperfluous*.

The genera in this order are five in number; viz. elephant's-foot, globe-flower, globe-thiſtle, *gundelia*, and baſtard Ethiopian

Ethiopian elichryſum. The firſt has four florets in each partial flower-cup; the ſecond has an indefinite number; the three laſt only one.

The order *monogamia* contains ſimple flowers. The term ſignifies a ſingle marriage, and is placed in direct oppoſition to the polygamy or intercommunication of florets, which ſo conſpicuouſly characterizes the other orders. In fact, balſam, violet, cardinal flower, and the other plants of this order, agree with the compound flowers in ſcarce a ſingle circumſtance, ſave the claſſical character, the union of the *anthers* or tops of the *ſtamina*:—a circumſtance which, whilſt it undeniably confutes Linnæus's aſſertion, that, in that union conſiſts the eſſence of a compound flower, ſerves likewiſe to demonſtrate the imperfection of his artificial character. Former botaniſts had ſought for the eſſential character of this numerous tribe of plants in the common calyx and common receptacle. Both theſe Linnæus rejects as inadequate, and in their place ſubſtitutes the union of the *anthers* and ſituation of the ſeeds. That union, we have ſeen, is not peculiar to compound flowers; it is to be found in violet, balſam, cardinal-flower, ſheep-ſcabious, and ſome other flowers, confeſſedly ſimple. To this it will be anſwered, that Linnæus's aſſertion is different from what I have repreſented it: that the author in queſtion, ſo far from affirming that the union of the *anthers* conſtitutes, of itſelf, the eſſence of compound flowers, has combined that circumſtance with the ſituation of the ſeeds, and declared that the eſſence of a compound flower conſiſts in having the anthers united into a cylinder, and a ſingle ſeed placed under each floret. This argument is plauſible, but not ſolid, for unluckily three of the genera of the order *monogamia*, viz. Strumpſia, ſeriphium, and corymbium, beſides the united anthers, have likewiſe a ſingle ſeed placed under the receptacle of the flower, and yet the order *monogamia* contains ſimple flowers only. The fact is, that compound flowers are ſo remarkably different in their port and external appearance from thoſe termed ſimple, that it is unneceſſary to ſeek for an eſſential character where there is no danger of confuſion.

Aggregate

Aggregate and compound flowers have indeed a greater conformity in point of habit; yet a ſuperficial attention only is requiſite to diſcover very material differences in their ſtructure.

As the excellence of the artificial character is conſtituted by its approximation to the natural, it is evident that a character, which arranges together things that are abſolutely heterogeneous, and poſſeſs no natural relations, is imperfect and erroneous. Compound flowers are confeſſedly a natural tribe of plants. Simple flowers poſſeſs no relations in common with them, that can juſtify a junction. A character, therefore, which, like that of Linnæus, blends ſimple and compound flowers promiſcuouſly together, offers a manifeſt violence to Nature, by forcibly tearing many genera of plants from their proper place, and incorporating them with others which are of a different and even oppoſite nature. In fact, in all the numerous ſyſtems in botany, there is not a ſingle character, which wounds Nature ſo cruelly as that of Linnæus, in the inſtance juſt given.

By an ingenious writer, Dr. Barton of Philadelphia, who has lately publiſhed an Elementary Treatiſe on Botany, the author of the preſent work, which the learned Profeſſor has honoured with repeated marks of peculiar notice and diſtinction, is, notwithſtanding, under the article before us, charged with an inconſiſtent departure from his uſual tenets, for aſſerting, that "the genus *Kuhnia*, al-"though very nearly allied to hemp-agrimony, and indeed, "in every other reſpect, like a compound flower, is *very* "*properly* referred by Linnæus to a claſs containing ſimple "flowers, *(pentandria)* becauſe the anthers are ſeparate and "diſtinct." *Vide* COMPOSITUS *flos*. As there is no imputation which, in matters of ſcience, it becomes a man more ſeduouſly to avoid, than that of inconſiſtency, ſo neither is there any which, when charged without due conſideration, he ought with greater ſolicitude to repel. Dr. Barton's

Barton's miſconception in the inſtance juſt mentioned, (for a miſconception, I truſt, I ſhall evidently prove it) may have probably ariſen from his overlooking a diſtinction which, in appreciating the merits of any particular ſyſtem, that of Linnæus for example, it is ever neceſſary to make between the preciſe portion of approbation which may be juſtly claimed by its founder, on account of the degree of ſtrictneſs in his adherence to the principles of his Method, be thoſe principles what they may, and that which belongs to him from the comparative excellence of the artificial character, which is always in the direct ratio of its nearer approach to the order of nature.—In this view, as is manifeſt, the ſame writer may, in one reſpect, be the object of merited cenſure, and in another, that of equally merited applauſe. To the honour indeed of a rigidly uniform adherence to the principles of his ſyſtem, (an honour almoſt excluſively due to Rivinus) Linnæus, it is true, has but ſlender pretenſions: and ſome very remarkable deviations from the ſimplicity of his plan have been occaſionally enumerated in the courſe of this work. In general, however, he has the praiſe of uniformity: and, as he profeſſes not in his Sexual Method to inveſtigate the Order of Nature, it can be no reproach, that, in order to conduct the learner with greater facility to the knowledge of plants, which is the principal buſineſs of an artificial character, he has, with the exceptions juſt mentioned, commonly adhered to the principles of his method, ſacrificing to utility even nature itſelf, by declining to arrange certain genera under claſſes to which, however connected with their congeners by external habit, and other natural affinities, the mere novice in botany, for whoſe uſe every artificial ſyſtem is intended, could not, for want of the claſſical character, be ever led to refer them. I conceive myſelf, therefore, perfectly juſtified, and ſtrictly conſiſtent with the general tenor of the doctrines of the Botanical Dictionary, and my other works reſpecting the comparative excellence of the artificial character of Linnæus, as explained above, (doctrines which I have ever maintained, and yet ſee no reaſon to retract) when I aſſert that Linnæus

has

has with the utmoſt propriety referred the genus *Kuhnia*, which, in a *Natural* Method would, no doubt, without any effort, from its general appearance, have arranged itſelf with the *compound flowers*, to the claſs *pentandria* of his *artificial* method, containing *ſimple flowers*, in which it with equal facility aſſumes its place, bearing as it does five ſtamina or male organs of fecundation, ſeparate both in their anthers and filaments, the ſpecial diſtinctive character of the claſs. For the ſame reaſon, Linnæus is not to be blamed, but defended, for placing violet, balſam, and other ſimple flowers, with the compound, in the claſs ſyngeneſia conſidered as part of an *artificial* method, becauſe they as undoubtedly poſſeſs the claſſical character, the union of their five ſtamina by the anthers, as the compound flowers with which, however unnaturally, they are thus made to incorporate.—In ſhort, the genus *Kuhnia* could not, but with impropriety, have been transferred to the compound flowers in Linnæus's ſyſtem, conſtituted as the claſs *ſyngeneſia* which contains them now is; nor could the celebrated Swediſh Naturaliſt, without an entire alteration of the principles of his method, have removed violet and its congeners from the place which they now occupy therein. Still, however, much as we commend his general adherence to the artificial character which he has choſen, we deny its excellence, nay, regret that, in the formation of his ſyſtem, he ſhould have adopted it at all—a character which, by the ſuperſtructure of which it is the baſis, he himſelf has demonſtrated, could not be carried to its utmoſt extent, without, in a thouſand inſtances, producing junctions and ſeparations, which, doing violence to nature, muſt, for that reaſon, greatly diminiſh the value of the principle from which they proceed.

T.

TETRADYNAMIA (τεσσαρες, four, and δυναμις, power) four powers; the name of the fifteenth claſs in Linnæus's Sexual Syſtem, conſiſting of plants with hermaphrodite

dite flowers having ſix ſtamina, four of which are longer than the reſt. It correſponds to the *ſiliquoſæ* of Ray, and *cruciformes* of Tournefort, and, abating a ſingle genus, *cleome*, is a true natural family, the particular characters of which are enumerated under the article *ſiliquoſæ*, by which name Linnæus, after Ray, has diſtinguiſhed theſe plants in his Fragments of a Natural Method. *Vide* SILIQUOSÆ.

The orders in the claſs *tetradynamia*, which are two in number, are likewiſe borrowed from the ſame author. Such as have a long pod, as ſtock, rocket, and ladies ſmock, being termed *ſiliquoſæ*; thoſe which have a ſhort round one, as ſcurvy-graſs, candy-tuft, and ſatin-flower, *ſiliculoſæ*. I have obſerved the ſame diſtinction in ſubdividing the natural order *ſiliquoſæ*.

In moſt ſpecies of baſtard-muſtard (cleome) the ſtamina are attached to a long pillar-ſhaped foot-ſtalk reſembling a ſtyle, which ſupports the ſeed-bud; a circumſtance which ought to have determined that genus to the claſs *gynandria* in the Sexual Method, upon the ſame principle, by which paſſion-flower and ſeveral other genera are made to arrange themſelves under that claſs. The genus *cleome* indeed, whatever may be its pretenſions to a place in the claſs alluded to, has certainly no right to that which it at preſent holds in the claſs *tetradynamia* of the ſame method; as, beſides its wanting the claſſical artificial character, the inequality of the ſtamina, theſe male organs of generation are frequently more than ſix, the number to which plants of this claſs are reſtricted. In fact, *cleome* is among the moſt ſtriking inſtances of Linnæus's deviation from his own principles; ſince ſcarce a circumſtance, except the preſence of what he calls nectariferous glands, which, by the way, are very ſeldom to be diſcovered even with glaſſes, can poſſibly connect it with the plants among which he has arranged it.

TETRAGYNIA (τεσσαρες, four; and γυνη, a woman,) the name of an order or ſecondary diviſion in the 4th, 5th, 6th, 8th, and 13th claſſes in the Sexual Syſtem; conſiſting of plants, which, to the claſſic character, whatever it is, add the circumſtance of having four ſtyles or

female organs. Herb-paris and graſs-of-Parnaſſus, furniſh examples.

TETRANDRIA (τεσσαρες, four; and ἀνηρ, a man or huſband) the name of the fourth claſs in Linnæus's Sexual Syſtem, conſiſting of plants with hermaphrodite flowers, which have four ſtamina or male organs that are of equal length. In this laſt circumſtance conſiſts the main difference, according to Linnæus, between the plants of the claſs in queſtion and thoſe of the 14th claſs, *didynamia*, in which the four ſtamina are of unequal length, two of them being longer than the other two.

The orders in this numerous claſs are three, founded upon the number of ſtyles or female organs.

Scabious, teaſel, barren-wort, the ſtarry plants of Ray, and the greater number of genera in this claſs, have one ſtyle.

Dodder, and hypecoum, have two ſtyles.

Holly, and a few others, have four.

TETRANGIÆ (τεσσαρες, four; and ἀγγος, a veſſel) the name of the eighteenth claſs in Boerhaave's Method, conſiſting of herbaceous plants having two ſeed-leaves, with a ſingle capſule that is divided internally into four cells. It is exemplified in rue and thorn-apple.

THALAMUS, a bride-chamber; Vaillant's name for the *receptaculum* of Pontedera and Linnæus; the *ſedes* of Ray; and *placenta* of Boerhaave.

Linnæus terms the calyx the *thalamus* of the flower.

THYRSUS, (properly a ſpear wrapped about with ivy or bay-leaves, carried by the votaries of Bacchus at his feaſts). In the modern nomenclature of botany, a mode of flowering reſembling the cone of a pine. It is, ſays Linnæus, a panicle contracted into an oval or egg-ſhaped form. The lower foot-ſtalks, which are longer, extend horizontally, whilſt the upper ones are ſhorter and mount vertically. Lilac and butter-burr furniſh examples.

TOMENTUM, ſhort wool; a ſpecies of hoary, or downy pubeſcence, which covers the ſurface of many plants, particularly

particularly thoſe in the neighbourhood of the ſea, and ſuch as, in their native ſoil, are expoſed to the ravages of bleak and violent winds. The ſubſtance in queſtion conſiſts of a number of ſmall hairs, that are ſo cloſely interwoven as ſcarcely to be diſtinguiſhed by the naked eye; the white appearance ariſing from their aggregation and compact texture. *Ceraſtium tomentoſum*, medicago, and a ſpecies of marjoram and ſpeedwell, furniſh examples.

TRACHEÆ, air-veſſels of plants. *Vide* STRUCTURA VEGETABILIS.

TRIANDRIA, (τρεις, three; and ἀνηρ, a man or huſband) the name of the third claſs in Linnæus's Sexual Syſtem, conſiſting of plants with hermaphrodite flowers, which have three ſtamina or male organs.

The orders in this claſs are three, derived from the number of ſtyles or female organs.

Valerian, tamarind, and many others, have one ſtyle.

The graſſes, which conſtitute the ſecond order, have two ſtyles.

Eriocaulon, montia, and ſome others, have three.

TRIANGIÆ (τρεις, three; and ἀγγος, a veſſel) the name of the ſeventeenth claſs in Boerhaave's Method, conſiſting of herbaceous plants having two ſeed-leaves, with a ſingle capſule that is divided internally into three cells. It is exemplified in St. John's wort, violet, campanula, palma-chriſti, mercury, ſpurge, and cardinal-flower.

Tulip, narciſſus, iris, and ſeveral other plants which have their ſeed-veſſel divided into three cells, do not arrange themſelves under the claſs *triangiæ*, becauſe the ſeeds riſe with a ſingle leaf. Such plants conſtitute the twenty-eighth claſs, *bracteatæ*, of the ſame author.

TRICOCCÆ, (τρεις, three; and κοκκος, a grain) the name of the thirty-eighth order in Linnæus's Fragments of a Natural Method, conſiſting of plants with a ſingle three-cornered capſule, having three cells or internal diviſions, each containing a ſingle ſeed. The ſingle ſeed-veſſel of theſe plants is of a ſingular form, and reſembles three capſules,

which adhere to one common foot-ſtalk as to a centre, but are divided externally into three pretty deep partitions.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Acalypha.			
Adelia.			
Andrachne,	—	—	Baſtard-orpine.
Buxus,	—	—	Box-tree.
Cambogia.			
Carica,	—	—	Papaw.
Cliffortia.			
Clutia.			
Cneorum,	—	—	Widow-wail.
Croton,	—	—	Baſtard-ricinus, Tallow-tree.
Cupania.			
Dalechampia.			
Euphorbia,	—	—	Burning thorny plant, ſpurge.
Excoecaria.			
Guettarda.			
Hernandia,	—	—	Jack-in-a-box.
Hippomane,	—	—	Manchineel-tree.
Hura,	—	—	Sand-box-tree.
Jatropha,	—	—	Caſſava, manihot.
Mercurialis,	—	—	Mercury.
Phyllanthus,	—	—	Sea-ſide laurel.
Plukenetia.			
Ricinus,	—	—	Palma-Chriſti.
Solandra.			
Sterculia.			
Tragia.			
Thryallis.			

This family not being completely natural does not fall to be particularly deſcribed in this place. The character expreſſed in the title is indeed a ſtriking one, and though the

the plants which poſſeſs it are not connected together by ſuch numerous relations as to form a true natural aſſemblage, yet are they by that circumſtance diſtinguiſhed from all other plants, with as great, perhaps greater facility than by any artificial character yet known. It is, however, to be obſerved, that all the genera of this order have not the ſtriking character juſt mentioned.

From the euphorbias, and ſeveral other genera of this order, flows by inciſion a corroſive liquor, which is white like milk.

The fruit of the manchineel tree is one of the moſt powerful cauſtics, and, if taken internally, never fails to prove mortal, if large quantities of oil are not immediately ſwallowed, to excite vomiting and ſheath the viſcera, before the cauſtic juice has operated. The tree bears a great reſemblance to the pear-tree. The bark is ſomewhat thicker, and filled with a viſcous corroſive milk. The wood under the alburnum is greyiſh, and beautifully marked with eyes of different tints or colours. The cauſtic and poiſonous quality is not peculiar to the fruit, being to be found alſo in the leaves, in the wood, in the milk of the bark, and even in its ſhade, by ſleeping under it.—The tree, which is commonly large, grows in the Weſt-Indies, on the bank of rivers, or on the ſea-ſhore, being rarely found at a diſtance from water. When it rains, one muſt be cautious of going under the tree for ſhelter, as the rain falling from its leaves on the hands, and other parts of the body, excites bliſters on the fleſh, as if boiling oil had fallen upon it, together with a very painful itching, which continues for a long time. If it falls into the eyes, it will endanger the eye-ſight; or if by chance one ſhould rub them with his hand moiſtened with this water, a conſiderable ſwelling is occaſioned, which from being red, becomes livid and full of pus.—The wood is no leſs dangerous to work, unleſs perfectly dry, and even its duſt or ſawings are poiſonous. Before it is touched, the workmen amaſs dry wood around its feet, ſet fire to it, and keep at a diſtance for fear of any bad conſequences from the ſmoke. When they think the fire has totally conſumed

its humidity, they apply the hatchet, taking care to have their face and arms covered with a towel or napkin, leſt the duſt flying out of it, or the milky humidity which may have remained unevaporated, ſhould aſſail their face, mouth, eyes, or hands. The ſawyers uſe the ſame precautions, as well as the turners who work it into tables, cabinets, and all ſorts of houſehold furniture, which are greatly eſteemed for the uncommon beauty of the wood.—The Indians uſe the milk of the manchineel-tree to poiſon their arrows. For this purpoſe they make a cleft in the bark and inſert the end of their arrows, which imbibes the liquor flowing out of the wound, that is white as milk, but thicker and more gluey. The arrows ſo envenomed are ſuffered to dry; and where they make a wound, poiſon at the ſame time.—Thoſe who ſleep under the manchineel-tree find themſelves, on awaking, prodigiouſly ſwelled, with a very violent megrim and a dangerous fever. By force of citron-juice and cordials, the venom is often, but with difficulty, extirpated.

A ſpecies of euphorbia termed *eſula*, if applied to any part of the body, produces a violent inflammation, which is ſoon ſucceeded by a conſiderable ſwelling, that degenerates into a gangrene and proves mortal.

Sterculia (*ſtercus*, dung) derives its name from the fœtid ſmell of the wood, which is ſaid to reſemble that of human excrements, whence the name of dirt-wood, by which it is known in the hot countries, where it is native.

The root of caſſada, caſſava, or manihot being diveſted of its poiſonous juices, ſerves for bread to moſt of the inhabitants of the Weſt India iſlands, whether black, white or red; that is, Negroes, Europeans, or Natives. The ſhrub, ſometimes called manioc, riſes ſeven or eight feet high, with a thin bark, that is grey, red, or violet, according to the different colours of the wood which it covers. The trunk and branches are filled with ſmall prominences exhibiting the veſtigia of the fallen leaves: for as the tree increaſes in height, the leaves relinquiſh the bottom of the branches, and are only to be found near the top. The wood is ſoft and brittle. The plant is better propagated by layers than from

ſeed;

ſeed; at leaſt, little of the root proper for eating is to be obtained by the latter method. The principal root produces ſuckers, in number from four to ſeven, and which differ in length and thickneſs, according to the age of the tree and goodneſs of the ſoil. The bark of the roots is like that of the trunk, grey, when the wood is grey; red, when the wood is red; white, when it is white; but the inſide or heart is always white, and of the conſiſtence of turnip. The roots of white manioc are ripe in eight months; thoſe of the other kinds require fourteen or eighteen months to attain their full ſize and maturity. When ripe they are plucked out of the earth by the tearing up of the whole tree, which never fails to be accompanied by the root; and if, in that operation, any of the off-ſets ſhould be ſeparated from the main root, which is eaſily obſerved, they take them up with a hoe. It requires no great force to pluck up theſe ſhrubs; for, beſides that the ſoil is of a ſoft nature, the roots do not penetrate very deeply into it. When plucked up, the Negroes deſtined for this work grate or raſp the bark with a blunt knife, as is done to turnips, and throw the roots into a tub full of water; they are then reduced to a powder or meal reſembling the coarſe ſawings of wood. This is effected by rubbing the root very forcibly againſt a copper file or grater, about fifteen or eighteen inches long, and ten or twelve broad, that is faſtened by ſmall nails upon a plank of timber, three feet and a half long, and one broad. The Negroe who files, puts one end of the plank into a wooden trough or tub, and holds the other againſt his ſtomach. At his ſide is a baſket, containing roots that are raſped, waſhed, and fit for being filed; one of theſe he takes in each hand, and paſſes it violently upon the file or grater till it is reduced to a rough powder.—All the roots being grated in this manner, they take the powder and put it into a preſs, with a view to ſqueeze out the juice, which is regarded as a very ſtrong poiſon, not only for men, but for beaſts alſo who drink of it, or chance to eat of theſe roots before the juice is expreſſed. It is remarkable, that animals which die in conſequence of having ſwallowed any quantity of this ſubſtance, have their breaſts prodigiouſly

ſwelled, without any viſible alteration on the noble parts. Some have hence argued that the juice in queſtion is not eſſentially a poiſon, but that poſſeſſing a ſuperfluity of nouriſhment, it proves an over-match to the digeſtive faculties, and thus proves mortal.—Beſides this ſuperabundance of nouriſhment, ſays Father Labat, a part of its malignity conſiſts in its coldneſs, which ſtops the circulation, benumbs the animal ſpirits, and at length cauſes death. Hence the beſt antidote againſt this poiſon is heat and violent motion. The patient, after ſwallowing large quantities of oil, to excite a nauſea and vomiting, is made to run as quick as he can, and drink plentifully of the ſtrongeſt ſpirits; in fine, every method is uſed to excite violent heat, to rouſe the ſpirits, and put the blood in motion.

Animals which have accuſtomed themſelves inſenſibly to the juice of manioc, feel no inconvience from the root of it, but rather the contrary. It is in this manner that the Turks, by a gradual and conſtant uſe, have rendered opium a harmleſs and even exhilarating medicine.

The juice of manioc loſes its malignity when heated. The natives of the Weſt-Indies, who uſe it in all their ſauces, feel no ſort of inconvenience from it, becauſe they never uſe it till after being boiled. Of the ſame juice they make ſtarch, by drying it in the ſun, where it becomes as white as ſnow, and is frequently made into cakes, which are as delicate as if made with the fineſt wheat-flour.

When the manioc is ſufficiently preſſed, they either make it into bread, called caſſada, or into flour for preſerving. For the firſt-mentioned purpoſe, they have a plate of iron, two feet broad, and half an inch thick; this they place upon a tripod, or on ſtones, and kindle a fire below it. When ſufficiently heated, ſo as not to admit of the touch, they lay on the whole ſurface about the thickneſs of three fingers of manioc, which has been previouſly preſſed and ſifted. The heap falls down in proportion as it roaſts; and the parts join and incorporate. This compreſſion and incorporation is aided by the perſon who roaſts ſlightly paſſing a piece of wood over the plate. When the ſide of the cake next the

plate

plate is ſufficiently done, that is, adheres, and the colour, formerly very white, becomes red, it is turned, and the other ſide allowed to roaſt till the ſame ſymptoms appear. When roaſted, it is laid in the ſun for two or three hours, with a view to diſſipate any poiſonous humidity, which may ſtill lurk in the root under this new form.

The inſide of caſſada is as white as ſnow, the ſides of a pale gold colour. The ſubſtance, which is very nouriſhing, and of eaſy digeſtion, may be preſerved ſeven or eight months, or more, provided it is kept dry, and ſometimes expoſed to the ſun. When dipped in water, or put in ſoup, caſſada ſwells up to a great height, which ſeems to prove its great abundance in ſubſtance.

The other mode of preparation, however, is moſt common, as being more convenient for preſerving, diſtributing to the Negroes, and tranſporting from place to place. The manioc, in this caſe, is put into a pan or ſtove that is but ſlightly heated, where it is continually turned, like coffee-beans, with a ſmall wooden inſtrument contrived for that purpoſe. This motion prevents it from ſticking to the pan; ſo that, when dried and roaſted, it has the appearance of thick red grains of ſalt. This mode of preparation is much more expeditious than the former. When dried, it is put into granaries, where it may be preſerved whole years, if kept dry, or put into a ſtove every ſix months.

This ſubſtance may be eaten quite dry, as crumbled bread, or as the Turks eat roaſted rice. When moiſtened, it ſwells prodigiouſly.

This latter method of preparing manioc is never practiſed by the natives, who uſe only caſſada, which they prepare once every day or oftener, as occaſion requires; for they eat it quite hot, as being then more delicate and agreeable to the taſte. Before their intercourſe with the Europeans had procured them iron plates, they made their caſſada upon large flat ſtones, whoſe thickneſs they adjuſted to that purpoſe. In default of copper files or graters, they made uſe

of

of a plank of wood, in which were fixed very ſmall ſharp bits of pebbles.

One ſpecies of manioc is ſaid to be exempt from the poiſonous quality poſſeſſed by the juice of the others. It is called camanioc, that is, chief of maniocs; in fact, its wood, leaves, and roots are larger and thicker than the others, and it is eaten without danger, or any precaution: but as it requires a longer time to attain maturity, and the roots yield much leſs meal, becauſe lighter and more ſpungy, it is generally neglected.

The ſmall bits of manioc, which have eſcaped the grater, and the clods which have not paſſed the ſieve, are not uſeleſs. They are dried in the ſtove, after the flour is roaſted, and then pounded in a mortar to a fine white powder, with which they make ſoup. It is likewiſe uſed for making a kind of thick coarſe caſſada, which is roaſted till almoſt burnt; of this, fermented with melaſſes and Weſt-India potatoes, they prepare a much eſteemed beverage, called ouycou. This liquor, the favourite drink of the natives, is ſometimes made extremely ſtrong, eſpecially on any great occaſion, as a feaſt; with this they get intoxicated, and, remembering their old quarrels, wound and murder one another. Such of the inhabitants and workmen as have not wine, drink ouycou. It is of a red colour, ſtrong, nouriſhing, refreſhing, and eaſily inebriates the inhabitants, who ſoon accuſtom themſelves to it as eaſily as beer.

The leaves of manioc are uſed in both Indies as thoſe of ſpinach are with us.

Box-wood being extremely hard is uſed for ſeveral purpoſes, and may properly enough be ſubſtituted in default of ebony, the yellow alburnum of which it perfectly reſembles. Employed in medicine, box-wood is ſudorific.

The Negroes of Senegal uſe from three to five entire ſeeds of *iatropha curcas* for purging the inteſtines; uſed in greater quantity, theſe ſeeds would prove mortal. It appears too that the purgative virtue reſides only in the radicle or *punctum vitæ* of the ſeeds; for the Negroes eat with equal

impunity

impunity and avidity large quantities of theſe ſeeds, after the radicle has been extracted.

Papaw, or popo-tree, the *carica papaya* of Linnæus, is male and female upon different roots: the flowers of the former being white, of the latter yellowiſh. The tender buds of theſe laſt are preſerved into ſweet-meats; and the long mango popo, which is ſaid to be little inferior to an Eaſt-India mango, into pickles. When nearly ripe the fruits are likewiſe boiled and eaten with any kind of fleſh-meat, care being taken previouſly to cleanſe them of the milky corroſive juice contained in them, which is of ſo penetrating a nature, ſays Hughes *, that, if the unripe fruit, when unpeeled, is boiled with the tougheſt old ſalt meat, it will ſoon make it ſoft and tender; and, if hogs are for any conſiderable time fed with the raw fruit, it wears off all the mucous ſlimy matter which covers the inſide of the guts, and would, in time, if not prevented by a change of food, entirely lacerate them. This juice, continues the ſame author, is ſometimes made uſe of to cure ring-worms and ſuch cutaneous eruptions.

The kernels of ſand-box tree are ſaid to be purgative, and ſometimes emetic. The uſe to which the capſule, generally cut into fifteen or ſixteen diviſions, is applied, ſuggeſted the name given to this curious and beautiful exotic.

The leaves and tender buds of phyſic-nut tree, a ſpecies of *croton*, emit a milky juice, which is ſaid to be applied to green wounds with ſucceſs. The nut, when ripe, yields a conſiderable quantity of oil, a ſpoonful of which ſwallowed when freſh is of a purgative quality, and deemed proper for abating ſwellings in dropſical diſorders.

The bark of *caſcarilla*, another ſpecies of the ſame genus, is uſed ſucceſsfully by the natives of Senegal in tertian fevers that are accompanied with a diarrhœa.

From the berries of the ricinus, or *palma-chriſti*, is extracted an oil which the natives of the Weſt Indies uſe in

* Natural Hiſtory of Barbadoes.

their

their ſoups. This oil is generally known in thoſe countries by the name of caſtor oil.

The Negroes of Senegal uſe externally with ſucceſs the leaves of *palma chriſti* in megrims and inflammations of the eyes.

The wind blowing into the cavities of the capſules of *hernandia ſonora* makes a very ſonorous whiſtling noiſe; whence the name of jack-in-a-box, by which this plant is generally known.

Croton tinctorium yields by expreſſion a greeniſh juice, which, by means of the volatile alkali of urine, dyes ſtuffs of a blue colour.

TRIHILATÆ, (*tres*, three, and *hilum*, an external mark on the ſeed); the name of the twenty-third claſs in Linnæus's Fragments of a Natural Method, conſiſting of plants with three ſeeds, which are marked diſtinctly with an external cicatrix or ſcar where they were faſtened within the *pericarpium*.

Liſt of the Genera *contained in this Order.*

	Linnæan Genera.			*Engliſh Names.*
α	*Melia*,	—	—	Bead-tree.
	Trichilia.			
β	*Acer*,	—	—	Maple.
	Æſculus,	—	—	Horſe-cheſnut.
	Baniſteria.			
	Malpighia,	—	—	Barbadoes-cherry.
	Triopteris.			
γ	*Cardioſpermum*,		—	Heart-ſeed, or heart-pea.
	Paullinia.			
	Sapindus,	—	—	Soap-berry.
	Staphylæa,	—	—	Bladder-nut.
	Tropæolum,	—	—	Indian creſs.

TRIPETALOIDEÆ, (*tres*, three; and *petalum*, a petal) the

the name of the fifth claſs in Linnæus's Fragments of a Natural Method, conſiſting of plants with three petals.

Liſt of the Genera *contained in this Order.*

Linnæan Genera.			*Engliſh Names.*
Aliſma,	—	—	Water-plantain.
Aphyllanthes.			
Butomus,	—	—	Flowering-ruſh, or water-gladiolus.
Calamus.			
Flagellaria.			
Juncus,	—	—	Ruſh.
Sagittaria,	—	—	Arrow-head.
Scheuchzeria,	—	—	Leſſer flowering-ruſh.
Triglochin,	—	—	Arrow-headed graſs.

Theſe plants have no very ſtriking characters, and are nearly allied to the graſſes. All the genera have not the circumſtance expreſſed in the title.

TRUNCUS, the trunk; that part of the herb which ariſes immediately from the root, and is terminated by the fructification; the leaves, buds, and auxiliary parts of the herb, not entering into its deſcription.

The different ſpecies of trunks enumerated by Linnæus are as follows:

CAULIS.
CULMUS.
SCAPUS.
FRONS.

Each of theſe terms is particularly explained in its proper place.

To this article, as the moſt ſuitable for that purpoſe, I formerly referred the reader for ſome general remarks on the mutual relations which ſubſiſt betwixt roots and ſtems.

Theſe principal parts of the plant are unfolded, branch, and ſubdivide almoſt in the ſame manner: the extent and force

force of the one being always too in proportion to the ſame qualities in the other. A ſhrub which puts out ſmall branches, has univerſally ſlender roots. The ſame tree planted in an eſpalier, where its growth is cramped, or it is pruned very cloſe, produces roots that are leſs numerous, leſs ſtrong, and leſs extenſive, than if cultivated as a ſtandard in full air. Hence the impracticability of extending the roots of a tree by lopping its branches. A fruit-tree, by ſuch an operation, will produce more fruit, becauſe moſt of the nouriſhment which went to theſe lopped branches, is now concentrated in the fruit; but its growth will be retarded, and its life rendered ſhorter.

Further, ſtems as well as roots are lengthened by their extremities, which ceaſe to grow upon being cut. Both, in conſequence, form new productions: the ſtems put forth lateral branches; the roots, lateral roots; whence it follows, that to cut the extremities of the ſtem and branches, is the proper way to form the heads of trees; and, in like manner, to cut the extremity of long perpendicular roots, is an excellent method to form beautiful and vigorous trees; for the perpendicular root being cut, the lateral ramifications, or ſide-roots, multiply; and theſe being placed nearer the ſurface of the earth, find a greater ſupply of nouriſhing juices in their progreſs.

Again, the ſtem is provided with ſeveral buds of branches, and the root with ſeveral ſuckers, or buds of roots. They may likewiſe be compared in their organization or internal ſtructure, which, in both, is nearly the ſame, unleſs that the epidermis or ſcarf-ſkin of the root is thicker, and the colours, internally, ſtronger and more lively.

In ſhort, except in their direction, which is univerſally oppoſite, ſtems and roots ſeem to bear a remarkable analogy to one another, ſo that, as Linnæus obſerves, ſtems may be conſidered as roots above ground.

TUBA, a trumpet. Vaillant's name for the *ſtylus* of Boerhaave and Linnæus; the *piſtillum* of Tournefort. *Vide* STYLUS.

TUBULOSUS *flos*, a ſpecies of compound flower ſo

termed

termed by Linnæus, all the florets or partial flowers of which are funnel-ſhaped, and nearly equal.

Of this kind are thiſtle, burdock, artichoke, hemp-agrimony, tanſy, cud-weed, and bidens.

The flowers in queſtion correſpond to the *floſculoſi* of Tournefort and Pontedera, the *compoſiti regulares* of Rivinus, the *compoſiti uniformes* of Chriſtian Knaut, and the *capitatæ* of Boerhaave and Ray.

TUBUS, the tube, or lower hollow part of a flower with one petal; oppoſed to *unguis*, the claw of a polypetalous flower.

V.

VAGÆ. Under this name Linnæus arranges a number of genera, which remain vague and undetermined; as, for want of uniform relations, they cannot conſtitute of themſelves a true natural aſſemblage, nor conſequently be referred to any of his Natural Orders.

In the Fragments of his Natural Method, they form an Appendix to the Scheme, by the name of *Dubii etiammum Ordinis*.

VALVULA, a little valve, or opening; the external diviſions of a dry ſeed-veſſel, as a capſule, or pod, which ſplit when the ſeeds are ripe for the purpoſe of diſſemination.

The openings in queſtion are either two in number, as in celandine, cabbage, and the pea-bloom flowers; three, as in violet, and Greek valerian; four, as in tree-primroſe, and French-willow herb: or five, as in flax, lime-tree, and Syrian mallow.

VARIETAS, a variety; a plant changed by ſome accidental cauſe, which being removed, the variety or mutation diſappears, and the ſpecies is reſtored. As many plants of different form and appearance as are produced from ſeed of the ſame ſpecies, are to be regarded as genuine varieties, and

in

in all caſes to be diſtinguiſhed with great accuracy from the ſpecies.

In the form and diſpoſition of the parts of each individual of the ſame ſpecies, there exiſts, in general, a conſtant uniformity. Different cauſes, however, as culture, climate, expoſure, age, diſeaſes, luxuriance or poverty of nouriſhment, contuſions, and other circumſtances, produce monſtrous appearances and accidental varieties in the parts of plants.

In treating of luxuriance in flowers, we obſerved that a ſuperabundance of nouriſhment gives riſe to the numerous tribe of double and prolific flowers. The ſame cauſe gives to all the parts of the plant a thickneſs and extent, by no means natural to them. Hence, likewiſe, the prodigious multiplication of the leaves of ſome plants, which increaſe to ſuch a degree, as frequently to injure the flower and fruit.

The leaves of young trees and of new ſhoots are much larger, and leſs cut and ramified than thoſe of a grown tree of the ſame ſpecies. In holly, the leaves loſe their prickles when the tree waxes old.

The lower leaves of aquatic plants, as crow-foot and water-drop-wort, are frequently finely cut like hairs, whilſt thoſe above are of a different form. Plants of the ſame ſpecies that grow in another ſoil, have no diverſity in the form of their upper and under leaves. Again, in mountainous plants, the lower leaves are generally more entire; the upper ones more divided. Burnet ſaxifrage, aniſe and coriander, furniſh examples.

The ſeeds or grains of many graſſes, particularly of rye, are ſometimes prolonged into a horny appearance of a fungous ſubſtance, that is pretty hard, and, as it were, cartilaginous. Some of theſe monſtrous productions are more than two inches long. Rye diſeaſed in this manner is frequently attended with fatal conſequences to ſuch as eat of the bread prepared from it. The ſame appearance has been obſerved in *gramen aquaticum fluitans*, and carex. This

diſeaſe,

diſeaſe, termed by Linnæus *clavus*, is common in moiſt years and rainy ſeaſons, and ſeems to be principally owing to a defect of perſpiration.

The flowers and ſeeds of many of the eſculent graſſes, and of ſome other plants, are frequently reduced into a black powder. This appearance has been particularly obſerved in wheat, rye, barley, oats, perſicaria, marſh ſcorzonera, goat's-beard, ſoap-wort, and ſome of the lychnis, pink, and chick-weed tribe. In the greater number, the diſeaſe, when it attacks the flower, begins by the receptacle under the form of ſmall black points, which inſenſibly reach the other parts of the flower, as the flower-cup, petals, and ſtamina, without attacking the piſtil, or female organ, which, however, commonly proves abortive.

The diſeaſe termed *uſtilago*, or burning, differs from that juſt mentioned, in that it is contagious and hereditary; the ſeeds being the only parts that are affected by it. It has been diſcovered in the ſame ſpecies of graſſes as the former, but more abundantly on Indian millet. M. Aymen, a French academician, attributes both theſe diſeaſes to an internal fault in the ſap.

The upper ſurface of the leaves of ſome plants, particularly of hop, melon, dead-nettle, hedge-nettle, maple, and gromwell, is ſubject to be covered with a white appearance, which makes the leaves ſeem thicker, more weighty, and more opaque. Plants which are attacked by this diſeaſe, termed by botaniſts *eryſiphe*, rarely produce any fruit; or, if they do, it is badly formed, and has a crude diſagreeable taſte.

On the under ſurface of the leaves of ladies mantle, and a ſpecies of euphorbia with cypreſs leaves, is occaſionally diſperſed a yellowiſh duſt, which, from its reſemblance to ruſty iron, has occaſioned the name of *rubigo*, or ruſt, to be given to this particular diſeaſe, which, like *clavus*, and ſome others, appears to proceed from a defect of perſpiration.

White ſpots are frequently obſerved on ſome leaves, which thence appear empty, and, as it were, tranſparent. It is occaſioned by the influence of a burning ſun acting

upon them when very much moiſtened, either in conſequence of continued rain, or a ſtrong dew. When all the leaves are attacked with this diſeaſe, which has obtained the name of *candor*, that is, the whites, the plant commonly periſhes a few days after.

Certain plants of warm climates are ſubject to loſe their petals, when cultivated in cold countries, and that, even when the fruit arrives at maturity. For particulars on this ſubject, the reader is referred to the article MUTILUS *flos*.

Plants which grow in the ſhade, or in places that are deprived of a proper current of air, are apt to become meagre, and, without taking the conſiſtence which is ſuitable, to periſh before they have produced any fruit. Experiments demonſtrate, that the feebleneſs of ſuch plants proceeds leſs from a defect of heat than from a privation of light.

Other cauſes alter the colour of leaves, and occaſionally produce the beautifully variegated leaves ſo much in requeſt among gardeners. Some leaves are ſubject to aſſume a deep red; this is particularly the caſe with herb Robert, a ſpecies of crane's-bill.

The branches of aſh and willow are frequently flattened in ſeveral irregular ways. This is ſuppoſed to be in conſequence of two buds being naturally grafted in each other, before the unfolding of the branch. Two leaves, or two fruits engrafted in this manner, produce other monſtrous appearances. By means of artificial grafting, we may, in like manner, vary the form of leaves, ſtems, flowers and fruit.

Laſtly, certain inſects depoſiting their eggs under the bark of the leaves and ſtems of ſeveral plants, occaſion an extravaſation of the ſap, and hence give birth to certain ſingular productions, which in different bodies reſemble either nuts, muſhrooms, or ſponges, and are either round or long, hard or ſoft, covered with leaves, or guarded with briſtly threads.

Such are the galls of oak which enter into the compoſition of ink; thoſe of lime, ciſtus, ground-ivy, a ſpecies of hawk-weed, the aſpen-tree, and ſeveral ſpecies of willow. Thoſe of a ſpecies of ſage called ſalvia baccifera, are ſold in

the markets of the Levant by the name of ſage-apples. Tournefort relates that they are round, nine or ten lines in diameter, of the colour of aſhes, cottony, with a white pulp that is ſomewhat tranſparent, ſweet, and of a very agreeable taſte. Thoſe of the ſcarlet oak are two lines in diameter. The ſubſtance is very red, and being dried, is the kermes, or ſcarlet-paſtel, ſo well known by the dyers.

Of the ſame nature with the galls juſt mentioned are thoſe ſtrange bodies covered with green, red, or yellow fibres, termed bedeguar, which a fly of the ſame kind produces upon the wild-roſe. Such are likewiſe the ſmall bladders on the ſurface of elm-leaves, which are filled with gnats, and with an aſtringent balmy liquor that is an excellent vulnerary.

Such are the principal accidents to which the parts of plants are ſubject, and which give riſe to the numerous tribe of varieties in the vegetable kingdom.

VEPRECULÆ, (diminutive from *vepres*, a briar, or bramble;) the name of the thirty-firſt order in Linnæus's Fragments of a Natural Method, conſiſting of the following genera, which do not conſtitute a true natural aſſemblage.

Linnæan Genera.			*Engliſh Names.*
Dais.			
Daphne,	—	—	Mezereon, or ſpurge-laurel.
Dirca,	—	—	Leather-wood.
Gnidia.			
Lachnæa.			
Paſſerina,	—	—	Sparrow-wort.
Quiſqualis.			
Stellera,	—	—	German groundſel, or Tragus's ſparrow-wort.
Theſium.			

VERNATIO (a renewing, or growing again, from *ver*, the ſpring;—foliation or leafing). By this general term, inſtead of *foliatio*, which he had employed in his earlier works, Linnæus has expreſſed in the later editions the curi-

ous manner in which the leaves are folded or wrapped up in their buds.—In this reſpect, leaves are

Conduplicata, doubled together, as in oak, aſh, beech, roſe, bramble, and moſt of the plants of the claſs *Diadelphia* of Linnæus.

Convoluta, rolled together like a ſcroll, as in after, golden-rod, comfrey, and moſt of the graſſes.

Equitantia, riding on one another, as in iris, acorus, *carex*, *poa*, and ſome other graſſes.

Involuta, rolled ſpirally inwards on both ſides, as in pear, apple, honey-ſuckle, violet, hop, and nettle.

Revoluta, rolled backwards on both ſides, as in fox-glove, dock, pellitory, groundſel, and colt's foot.

Obvoluta, rolled up againſt one another, as in valerian, teaſel, ſcabious, pink and ſage.

Imbricata, laid over one another like tiles, as in privet, St. John's wort, and Greek valerian.

Circinalia, rolled ſpirally downwards, as in the ferns, and ſome palms.

Plicata, plaited, as in mallow, vine, paſſion-flower, and alder-tree, or

Reclinata, folded back towards the footſtalk, as in anemone and monk's hood.

By actually diſſecting the buds of theſe plants, which are familiar to moſt, and likewiſe eaſily to be found, for which reaſon I have preferred them as examples, the learner in botany will acquire a far more accurate knowledge of the full force and meaning of the above-mentioned terms of foliation, than by any definition or deſcription, however exact and elaborate.

VERTICILLATÆ, (from *verticillus*; *vide infra*) the name of a claſs in Ray's and Boerhaave's Methods, conſiſting of herbaceous vegetables having four naked ſeeds, and the flowers placed in whorls round the ſtalk. The term is ſynonymous to the *labiati*, or lipped-flowers of Tournefort, and is exemplified in mint, thyme, and ſavory.

VERTICILLATÆ is alſo the name of the forty-ſecond order

order in Linnæus's Fragments of a Natural Method, conſiſting of plants which anſwer the above deſcription.

Liſt of the Genera *contained in this Natural Order.*

Linnæan Genera.			*Engliſh Names.*
Ajuga,	—	—	Bugle.
Amethyſtea.			
Ballota,	—	—	Black hore-bound.
Betonica,	—	—	Betony.
Cleonia.			
Clinopodium,	—	—	Field-baſil.
Cunila.			
Dracocephalum,	—	—	Dragon's head.
Galeopſis,	—	—	Hedge-nettle.
Glechoma,	—	—	Ground-ivy.
Horminum,	—	—	Pyrenæan clary.
Hyſſopus,	—	—	Hyſſop.
Lamium,	—	—	Dead nettle.
Lavandula,	—	—	Lavender.
Leonurus,	—	—	Lion's-tail.
Lycopus,	—	—	Water hore-hound.
Marrubium,	—	—	Hore-hound.
Meliſſa,	—	—	Balm.
Melittis,	—	—	Baſtard balm.
Mentha,	—	—	Mint.
Moluccella,	—	—	Molucca balm.
Monarda.			
Nepeta,	—	—	Cat-mint, or nep.
Ocymum,	—	—	Baſil.
Origanum,	—	—	Marjoram.
Orvala.			
Phlomis,	—	—	Sage-tree, or Jeruſalem-ſage.
Praſium,	—	—	Shrubby hedge-nettle.
Prunella,	—	—	Self-heal.
Roſmarinus,	—	—	Roſemary.
Salvia,	—	—	Sage.

Linnæan Genera.			*Engliſh Names.*
Satureia,	—	—	Savory.
Scutellaria,	—	—	Skull-cap.
Sideritis,	—	—	Iron-wort.
Stachys,	—	—	Baſe hore-hound.
Teucrium,	—	—	Germander.
Thymbra,	—	—	Mountain-hyſſop.
Thymus,	—	—	Thyme.
Trichoſtema.			
Ziziphora,	—	—	Syrian field baſil.

Habit and Structure of the Plants of this Order.

This order, termed by Tournefort *labiati*, or lipped-flowers, from the unequal and irregular diviſions of the petal, which commonly reſemble the two lips of an animal, contains annual and perennial herbs, and ſhrubby plants, ſome of which retain their green leaves during the winter.

The ROOTS are branched and fibrous.

The STEMS are round when old, ſquare, when young; as are likewiſe the young branches which ſtand oppoſite.

The LEAVES are oppoſite, and in the greater number covered with tranſparent points. Thoſe which are placed next the flower generally differ from the ſtem-leaves.

In the greater number of plants of this order, the leaves are ſupported upon a long cylindrical foot-ſtalk that is furrowed above. Some, however, as dead-nettle and bugle, have the leaves attached immediately to the branches without any foot-ſtalk.

The FLOWERS are univerſally hermaphrodite, except in a ſpecies of thyme mentioned by Adanſon, which appears to have male or barren flowers on one root, and female or fertile flowers on another.

They are diſpoſed round the ſtem, as the title imports, in whorls, or ſmall heads, with ſhort foot-ſtalks.

The FLOWER-CUP is of one piece, that is generally cut into five unequal diviſions, whoſe diſpoſition ſometimes repreſents two lips, the uppermoſt of which has commonly a

leſs

leſs number of diviſions. It accompanies the ſeeds, which it nouriſhes in its boſom, to their maturity.

The PETAL is of the gaping or lip kind, and, in the different genera, is more or leſs irregular or unequal, either in its tube, or in the diviſions of the upper part, the number of which varies from two to five. Theſe diviſions frequently form two lips, of which the uppermoſt, termed the creſt and the helmet, is ſometimes entire, ſometimes more or leſs deeply cut into two; the lowermoſt, termed the beard, generally into three. In germander and bugle the upper lip is very ſhort, and over-topped by the ſtamina.

The STAMINA are two, or four in number. In the greater part, there are four ſtamina of unequal length, two of them being longer than the others; a character which determines ſuch plants to the claſs *didynamia* of the Sexual Method. As to ſage, roſemary, and the other genera with two ſtamina, they are approximated to the other plants of this order, not only by their general habit, and the figure of the flower, but even in ſome of the genera by the number of ſtamina, which, although only two, yet are accompanied by filaments which reſemble ſtamina without the *anthers*. This appearance is particularly conſpicuous in ſage and a ſpecies of monarda.

The four unequal ſtamina are frequently diſſimilar, and approach by pairs; they are inclined towards the back of the petal, and parallel; the two innermoſt being ſhorteſt, and attached ſomewhat lower than the two others to the tube of the flower.

The SEED-BUD, which conſiſts of four diſtinct *ovaria*, is placed upon the ſeat of the flower, and elevates from their centre a common ſtyle, that is ſlender, bent in the ſame manner as the filaments which it ſomewhat exceeds in length, and terminated by a double ſtigma, the diviſions of which are unequal, and turned backwards.

The SEED-VESSEL in this order is wanting.

The SEEDS are four in number, and lodged in the bottom of the flower-cup as in a matrix, or ſeed-veſſel. Each ſeed has two covers; the one external, of a cartilaginous,

or leathery ſubſtance; the other internal, membranaceous, of a very fine texture, and placed immediately above the radicle or embryo-plant.

The plants of this order are fragrant, warm, penetrating, and accounted cordial, and cephalic. Their principal virtue reſides in the leaves.

The chief aromatics are ſavory, thyme, marjoram, penny-royal, mint, balm, lavender, roſemary, ſage, clary.

VERTICILLUS, (properly, a little whorl, hinge, axis, or ſpindle); a mode of flowering, in which the flowers are produced in rings at each joint of the ſtem, with very ſhort foot-ſtalks. The term is exemplified in mint, hore-hound, and the other plants of the natural order deſcribed above.

VEXILLUM, a ſtandard; the upper petal of a pea-bloom, or butterfly-ſhaped-flower, which is generally larger than any of the others. *Vide* COROLLA and DIADELPHIA.

VIGILIÆ PLANTARUM, the vigils of plants.

Under this term, botaniſts comprehend the preciſe time of the day in which the flowers of different plants open, expand, and ſhut.

As all plants do not flower in the ſame ſeaſon, or month; in like manner, thoſe which flower the ſame day, in the ſame place, do not open and ſhut preciſely at the ſame hour. Some open in the morning, as the lipped-flowers, and compound flowers with flat ſpreading petals; others at noon, as the mallows; and a third ſet in the evening, or after ſun-ſet, as ſome geraniums, and opuntias. The hour of ſhutting is equally determined. Of thoſe which open in the morning, ſome ſhut ſoon after, while others remain expanded till night.

The hours of opening, like the time of flowering, ſeem to vary, according to the ſpecies of the plant, the temperature of the climate, and that of the ſeaſon. Flowers, whoſe extreme delicacy would be hurt by the ſtrong impreſſions of an ardent ſun, do not open till night; thoſe which require a moderate degree of heat to elevate their juices, in other words,

words, whoſe juices riſe in the morning or evening, expand then; whilſt thoſe which need a more lively heat for the ſame purpoſe, expand at noon, when the ſun is in his meridian ſtrength. Hence it is, that the heat of the air being greater betwixt the tropics than elſewhere, plants which are tranſported from thoſe climates into the cold or temperate climates of Europe, expand their flowers much later than in their native ſoil. Thus, a flower which opens in ſummer at ſix o'clock in the morning at Senegal, will not open at the ſame ſeaſon in France and England till eight or nine, nor in Sweden till ten; that which opens at eight at Senegal, expands at ten in France and England, and at noon in Sweden; a flower which opens at ten at Senegal, does not open in France and England till noon; and, in Sweden the plant does not flower, or, at leaſt, loſes its petals, and frequently bears no fruit; laſtly, a plant which opens its flowers in Senegal at noon, or at one or two hours after noon, bears neither flowers nor fruit in France, England, and Sweden. The ſame thing happens to moſt plants of temperate countries, when removed to Senegal, or other ſultry climes.

Linnæus diſtinguiſhes by the general name of *ſolar (flores ſolares)* all thoſe flowers which obſerve a determinate time in opening and ſhutting. Theſe flowers are again divided, from certain circumſtances, into three ſpecies, or kinds:

Equinoctial flowers *(flores æquinoctiales)* are ſuch as open and ſhut at all ſeaſons at a certain fixed or determinate hour.

Tropical flowers *(flores tropici)* are ſuch whoſe hour of opening is not fixed at all ſeaſons, but accelerated or retarded according as the length of the day is encreaſed or diminiſhed.

Meteorous flowers *(flores meteorici)* are ſuch whoſe hour of expanſion depends upon the dry or humid ſtate of the air, and the greater or leſs preſſure of the atmoſphere. Of this kind is the Siberian ſow-thiſtle, which ſhuts at night, if the enſuing day is to be clear and ſerene, and opens if it is to be cloudy and rainy. In like manner the African marigold,

which

which in dry ſerene weather, opens at ſix or ſeven in the morning, and ſhuts at four o'clock in the afternoon, is a ſure indication that rain will fall during the courſe of the day, when it continues ſhut after ſeven.

VOLVA, (properly, that wherein a thing is wrapped, *à volvo*, to roll up or infold). The membranaceous cover, (termed by Linnæus the calyx) which enfolds many muſhrooms before their expanſion, and burſts in order to make a free paſſage for the plant.

UMBELLA, (diminutive from *umbra*, a ſhade)—an umbel, a ſpecies of receptacle, or rather a mode of flowering, in which a number of ſlender flower-ſtalks proceed from the ſame centre, and riſe to an equal height, ſo as to form an even and generally round ſurface at top. The term differs from *corymbus*, another mode of flowering, in that there is a common part, the point, from which iſſue all the foot-ſtalks, and in that the foot-ſtalks are of an equal length; whereas in a *corymbus*, the foot-ſtalks proceed from different points, and though they altogether form an even ſurface at top, as in the umbel, yet is each lower foot-ſtalk of greater length than that immediately above it.

When none of the foot-ſtalks of an umbel are ſubdivided, as in ginſeng, it is termed ſimple; when, on the other hand, each flower-ſtalk is ſubdivided at its extremity into a number of ſmaller foot-ſtalks for ſupporting the flowers, in other words, when each foot-ſtalk bears at top an umbel, the whole head or aggregate is termed a compound umbel, to diſtinguiſh it from the ſimple, in which there are no ſubdiviſions, and, likewiſe, an univerſal umbel to diſtinguiſh it from the partial or particular umbel of each foot-ſtalk. An univerſal umbel is conſtituted from an aggregate of partial umbels. Compound umbels are more common than ſimple. Inſtances will be adduced below.

UMBELLATÆ (*ab* UMBELLA, *vide ſupra*) the name of a claſs in Ray's and Tournefort's methods, conſiſting of plants whoſe flowers grow in umbels, with five petals that are often unequal, and two naked ſeeds that are joined at top, and ſeparated below.

The

The ſame plants conſtitute the forty-eighth order of Linnæus's Fragments of a Natural method. Their names and general deſcription follow.

Liſt of the Genera *contained in this Natural Order.*

Linnæan Genera.	*Engliſh Names.*
Ægopodium, — —	Herb-gerard, gout-wort, or wild angelica.
Aethuſa, — —	Leſſer hemlock, or fools parſley.
Ammi, — —	Biſhop's-weed.
Anethum, — —	Dill, fennel.
Angelica.	
Apium, — —	Parſley.
Arctopus.	
Artedia.	
Aſtrantia, — —	Black maſter-wort.
Athamanta, — —	Spignel.
Bubon, — —	Macedonian parſley.
Bunium, — —	Pig-nut, or earth-nut.
Bupleurum, — —	Hare's ear.
Cachrys.	
Carum, — —	Carui, or caraway.
Caucalis, — —	Baſtard parſley.
Chærophyllum, — —	Chervil.
Cicuta, — —	Water-hemlock.
Conium, — —	Hemlock.
Coriandrum, — —	Coriander.
Crithmum, — —	Samphire.
Cuminum, — —	Cumin.
Daucus, — —	Carrot.
Echinophora, — —	Prickly-parſnep.
Eryngium, — —	Eryngo.
Ferula, — —	Fennel-giant.
Haſſelquiſtia.	
Heracleum, — —	Cow-parſnep.
Hydrocotyle, — —	Water navel-wort.

Imperatoria,

Linnæan Genera.			*Engliſh Names.*
Imperatoria,	—	—	Maſter-wort.
Laſerpitium,	—	—	Laſer-wort.
Liguſticum,	—	—	Lovage.
Oenanthe,	—	—	Water drop-wort.
Paſtinaca,	—	—	Parſnep.
Peucedanum,	—	—	Hog's-fennel, or ſulphur-wort.
Phellandrium.			
Pimpinella,	—	—	Burnet-ſaxifrage.
Sanicula,	—	—	Sanicle.
Scandix,	—	—	Shepherd's-needle, or Venus's comb.
Selinum,	—	—	Milk-parſley.
Seſeli,	—	—	Heart-wort of Marſeilles.
Sium,	—	—	Water-parſnep.
Siſon,	—	—	Baſtard-ſtone-parſley.
Smyrnium,	—	—	Alexanders.
Thapſia,	—	—	Deadly-carrot, or ſcorching-fennel.
Tordylium,	—	—	Hart-wort of Crete.

Habit and Structure of the Plants of this Order.

Theſe plants are herbaceous, and chiefly perennial.

The ROOTS are either tuberous, or ſpindle-ſhaped, and ſometimes forked.

The STEMS are cylindric, full of pith, and frequently hollow. The branches are alternate.

The LEAVES, which, like the branches, are put on alternately, are very different in point of form, being ſimple and entire in ſome; target-ſhaped in a ſpecies of water navel-wort; finger or hand-ſhaped in ſome others; and pinnated or winged with numerous minute diviſions, as in the greater number.

They are ſupported by a foot-ſtalk, which is very broad and membranous at its origin, and commonly embraces the whole contour of the ſtem and branches.

The FLOWERS are, in general, hermaphrodite. There are,

are, however, ſome which have male or barren flowers in the ſame umbel.

This is particularly the caſe with thoſe umbelliferous plants which have the petals in the flowers of the circumference large and unequal. Carrot, baſtard-parſley, artedia, and coriander, furniſh proper examples. In theſe plants, the flowers in the circumference only prove fertile, thoſe in the centre or diſk being abortive. The ſame appearance is conſpicuous in ſome ſpecies of chervil and hog's-fennel. Water drop-wort and black maſter-wort, on the contrary, have the flowers in the circumference abortive. In ginſeng, hermaphrodite and male flowers are produced upon diſtinct plants.

The flowers are diſpoſed in an umbel, which is ſimple, as in water navel-wort; or compound, as in angelica, maſter-wort, carrot, hemlock, and many others. *Vide ſupra.*

The COMMON CALYX in this order is that ſort termed very improperly by Linnæus, *involucrum*, or the flower-cover. This, in the greater number, conſiſts of one or more leaves placed under the partial, or univerſal umbel, or both, for the purpoſe of ſupport. The preſence or abſence of one or both of theſe covers affords excellent marks in diſcriminating the genera of this very ſimilar order of plants. Carui, parſnep, alexanders, fennel, herb-gerard, and burnet-ſaxifrage, want both the univerſal and the partial cover.

The PROPER FLOWER-CUP of each flower in the aggregate conſiſts of five minute indentments placed upon the ſeed-bud, which it envelopes and accompanies to maturity.

The PETALS are five in number, and diſpoſed upon the ſides of the flower-cup in form of a roſe. In the florets of the centre, the petals are generally pretty equal and ſmall; in thoſe of the circumference, they are frequently unequal and larger; in the greater number they are heart-ſhaped, and cut almoſt to the middle in two.

The STAMINA are five in number, placed oppoſite to the diviſions of the flower-cup, and alternate with the petals.

The SEED-BUD is univerſally placed under the ſeat of the flower, and ſupports two ſtyles that are turned backwards,

and

and crowned with ſimple ſummits, which do not differ in appearance from the ſtyles.

The SEED-VESSEL in this order is wanting.

The SEEDS are two in number, which, when ripe, ſeparate below, but remain cloſely attached at top.

The plants of this order which grow in dry places are ſudorific, ſtomachic, and warming. Their virtue reſides chiefly in the ſeeds and leaves. Thoſe which grow in marſhy places are generally poiſonous. Of this kind are water-hemlock, water drop-wort, baſtard ſtone-parſley, and creeping water-parſnep. The milky juice of the roots is cauſtic. Its qualities are blunted by acids, as the juice of citron or vinegar.


Notwithſtanding the extremely warm and even cauſtic quality of moſt of theſe plants, many of them are employed in the œconomy of domeſtic affairs, particularly the roots of parſnep, carrot, and ſkirret; the leaves of parſley, celery, chervil; the ſeeds of fennel, aniſe, and coriander.

Of late years, an extract of the juice of the leaves of the greater hemlock, the *conium maculatum* of Linnæus, has been uſed ſucceſsfully in ſchirrous diſorders, and cancerous ulcers of the breaſts. Dr. Storck of Vienna was the firſt who recommended it for this purpoſe. The external application is found efficacious in the ſame diſorders.

UMBELLULA, a little umbel. Linnæus's name for each partial or particular umbel of an umbelliferous flower. *Vide* UMBELLA.

UMBO, (properly the boſs of a buckler—a knob) a term of Moriſon, correſponding to the *diſcus* of Linnæus. *Vide* DISCUS.

UNGUIS—The claw, or lower part of each petal, in a flower conſiſting of more petals than one. *Vide* COROLLA. Likewiſe a term of meaſure. *Vide* MENSURA.



Drawn by Syd. Edwards

Engraved by [illegible]

Published Nov. 1 1804 as the Act directs by H.D. Symonds, Paternoster Row

EXPLANATION

OF THE

PLATES.

PLATE I.—Leaves.

SIMPLE LEAVES. (*Vide* Folium.)*

Fig.

1. *Folium orbiculatum*, a circular leaf, or that is perfectly round.
2. ——— *ſubrotundum*, a leaf approaching to a circular figure.
3. ——— *ovatum*, an egg-ſhaped leaf.
4. ——— *ovale*, a leaf having an oval or elliptical form.
5. ——— *oblongum*, an oblong leaf, in which the length greatly exceeds the breadth.
6. ——— *lanceolatum*, a lance-ſhaped leaf.
7. ——— *lineare*, a leaf of equal breadth throughout.
8. ——— *ſubulatum*, an awl-ſhaped leaf, which gradually tapers towards the top.
9. ——— *reniforme*, a leaf in figure reſembling a kidney.
10. ——— *cordatum*, a heart-ſhaped leaf.
11. ——— *lunulatum*, a leaf reſembling a creſcent.
12. ——— *triangulare*, a three-angled leaf.
13. ——— *ſagittatum*, a leaf which in form reſembles the head of an arrow.
14. ——— *cordato-ſagittatum*, a leaf which partakes of both ſhapes delineated in the tenth and thirteenth figures.
15. ——— *haſtatum*, an halberd-ſhaped leaf.
16. ——— *fiſſum*, a leaf that is parted about halfway down, with ſtraight margins.
17. ——— *trilobum*, a leaf divided to the middle into three parts, with convex margins; three-lobed.
18. ——— *premorſum*, a leaf ſo blunted at the apex as to give the appearance of being bitten off.


* Familiar examples of ſuch of the terms reſpecting the figure and other circumſtances of the leaves of plants as ſtand moſt in need of illuſtration, being given in the Dictionary, under the article *Folium*, to ſubjoin them in this place would be altogether unneceſſary.

PLATE II.—LEAVES.

SIMPLE LEAVES *continued.*


Fig.

19. *Folium lobatum*, a leaf divided to the middle into ſeveral parts, with convex margins; a lobed leaf.
20. —— *quinquangulare*, a five-angled leaf.
21. —— *eroſum*, an eroded leaf; a ſinuated leaf, in which the margin is broken by ſmaller hollows, as if gnawed, or eaten away.
22. —— *palmatum*, a palmate or hand-ſhaped leaf.
23. —— *pinnatifidum*, a ſimple leaf reſembling a pinnate or winged compound one.
24. —— *laciniatum*, a leaf that is irregularly cut; a jagged leaf.
25. —— *ſinuatum*, a leaf that has hollows, or wide gaping breaks on the ſides, (*ſinus*, a bay).
26. —— *dentato-ſinuatum*, a leaf, the *ſinuſes* of which are indented.
27. —— *retrorſum-ſinuatum*, a leaf, the *ſinuſes* of which are turned backwards.
28. —— *partitum*, a leaf deeply divided.
29. —— *repandum*, a waved, ſcallopped, or ſerpentine-edged leaf.
30. —— *dentatum*, an indented leaf.
31. —— *ſerratum*, (*ſerra*, a ſaw) a leaf having teeth reſembling thoſe of a ſaw, which point to the apex.
32. —— *duplicato-ſerratum*, a leaf that has a row of leſſer ſerratures placed upon the greater ones; twice-ſerrated.
33. —— *duplicato-crenatum*, a leaf in which there is a double row of the ſegments termed *crenæ* or notches, the leſſer placed upon the greater; twice-notched. Vide Fig. 38.
34. —— *cartilagineum*, a leaf having a cartilaginous or griſtly edge.
35. —— *acuté-crenatum*, a leaf acutely notched.
36. —— *obtuſe-crenatum*, a leaf obtuſely notched.
37. —— *plicatum*, a leaf plaited like a fan, or a candle-ſhade.
38. —— *crenatum*, (*crena*, a notch) a leaf, the edges of which are cut into ſmall ſegments, whether acute or obtuſe, which point not to either extremity. Vide Fig. 33 and 36.—a notched leaf.









Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov 1 1804 as the Act directs by B D Symonds Paternoster Row



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov. 1.1804. as the Act directs. by H.D. Symonds Paternoster Row.

PLATE III.—LEAVES.

SIMPLE LEAVES *continued.*

Fig.

39. *Folium crispum*, a curled leaf.
40. —— *obtusum*, a leaf which terminates obtusely.
41. —— *acutum*, a leaf which terminates in an acute angle.
42. —— *acuminatum*, a leaf whose *apex* is subulate or awl-shaped. (*Vide* fig. 8.)—an acuminate leaf.
43. —— *obtusum acumine*, a sharp pointed leaf, which does not begin to taper till very near the apex—obtuse with a point.
44. —— *emarginatum acuté*, a leaf, the apex of which is deficient in its margin, and ends sharply.
45. —— *cuneiforme emarginatum*, a leaf that is shaped like a wedge, and has a rounded notch or deficiency at the apex.
46. —— *retusum*, a leaf which ends in an obtuse *sinus*.
47. —— *pilosum*, a leaf, from the surface of which proceed long distinct hairs.
48. —— *tomentosum*, a leaf whose surface is covered with a beautiful white down. Vide *tomentum*.
49. —— *hispidum*, a leaf whose surface is covered with hard bristles.
50. —— *ciliatum*, a leaf, the margin of which is fringed like an eye-lash, (*cilium*.)
51. —— *rugosum*, (*ruga*, a wrinkle) a wrinkled leaf.
52. —— *venosum*, a leaf whose surface abounds with veins or branched vessels.
53. —— *nervosum*, a leaf whose surface abounds with nerves, ribs, or simple unbranched prolongations of the pedicle.
54. —— *papillosum*, a leaf, from the surface of which arise little bladders or blisters, (*papilla*, a nipple.)
55. —— *linguiforme*, a tongue-shaped leaf.
56. —— *acinaciforme*, a leaf shaped like a Persian scimitar, (*acinaces*.)
57. —— *dolabriforme*, a leaf which in figure resembles a hatchet, (*dolabra*, a carpenter's ax.)
58. —— *deltoides*, a leaf imagined to resemble the Greek delta, as in black poplar.
59. —— *triquetrum*, a three-sided leaf, as in *anthericum ossifragum*.
60. —— *canaliculatum*, (*canaliculus*, a little pipe, or channel) a channelled leaf; a leaf that has one longitudinal groove running from the base to the apex on the upper surface, the lower being convex.
61. —— *sulcatum*, a furrowed or fluted leaf; a leaf that has several deep grooves or furrows, and in the same direction as the channelled leaf.
62. —— *teres*, a cylindrical or pillar-shaped leaf.
63. —— *panduræforme*, a leaf shaped like a violin, or Spanish guitar, as in *rumex pulcher*, (*pandura*, a musical instrument with three strings.)

PLATE IV.—LEAVES *continued.*

COMPOUND LEAVES.

Fig.

1. *Folium binatum*, a fingered leaf with two leaflets.
2. —— *ternatum foliolis ſeſſilibus*, a fingered leaf with three leaflets that are ſeſſile*.
3. —— *ternatum foliolis petiolatis*, a fingered leaf having three ſtalked leaflets; the reverſe of the preceding term.
4. —— *digitatum*, in general a fingered leaf; in the figure before us in particular, a leaf of that deſcription with five ſeſſile leaflets.
5. —— *pedatum*, a leaf ſomewhat reſembling a bird's foot; exemplified in paſſion flower, and black hellebore.
6. —— *pinnatum cum impari*, a pinnate or winged leaf with an odd leaflet at the apex.
7. —— *abrupté pinnatum*, a pinnate leaf which at the apex has neither an odd leaflet nor tendril.
8. —— *pinnatim alternatim*, a pinnate leaf having the leaflets placed alternately along the mid-rib.
9. —— *pinnatum foliolis oppoſitis*, a pinnate leaf with oppoſite leaflets.
10. —— *interrupté pinnatum*, a pinnate leaf with unequal leaflets—interruptedly winged.
11. —— *pinnatum cirroſum*, a pinnate leaf terminated by a tendril.
12. —— † *pinnatum conjugatum*, a pinnate leaf with only two pair of leaflets.
13. —— *pinnatum decurſivé*, a leaf decurſively pinnate, that is, in which the leaflets run down or extend themſelves into the ſtalk.
14. —— *pinnatum articulaté*, a pinnate leaf, in which the common footſtalk connecting the leaflets is *articulate* or jointed.
15. —— ‡ *lyratum*, a lyre-ſhaped leaf.

* See fig. 12 and 14 in Plate VI.

† The reader muſt be careful to diſtinguiſh betwixt *folium binatum* and *folium conjugatum*; the firſt being the loweſt modification of the digitate or fingered leaf, the ſecond the loweſt of the pinnate or winged one.

‡ This figure is improperly inſerted in the preſent plate, its place being manifeſtly among the Simple Leaves.



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov. 1. 1804. as the Act directs by H.D. Symonds Pater-noster Row.



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov. 1 1804. as the Act directs by H. D. Symonds Pater-noster Row.

PLATE V.—Leaves.

COMPOUND LEAVES *continued.*

Fig.

16. *Folium biternatum*, a re-compounded leaf that is doubly-ternate, that is, has the common footſtalk divided into three parts, each of which has three leaflets.
17. —— *triternatum*, a leaf that is triply-ternate, that is, has the common footſtalk divided into three parts, each of which is doubly-ternate.
18. —— *bipinnatum*, a doubly-pinnate leaf.
19. —— *tripinnatum ſine impari*, a triply-pinnate leaf, each pinna of which terminates abruptly.
20. —— *tripinnatum cum impari*, a triply-pinnate leaf, with an odd leaflet at the apex of each pinna or wing.

*** For further illuſtrations on the ſubject of Compound Leaves, the reader is referred to the Section which bears that name in the Dictionary, under the article Folium.

PLATE VI.—LEAVES *continued.*

DETERMINATION OR DISPOSITION OF LEAVES.

Fig.

1. *Folium inflexum*, a leaf bent inwards, or towards the ſtalk.
2. —— *erectum*, an erect leaf, or that is nearly perpendicular.
3. —— *patens*, a leaf bent outwards, or declining from the ſtalk at an acute angle; a ſpreading leaf.
4. —— *horizontale*, an horizontal leaf, which is placed at right angles with the ſtalk.
5. —— *reclinatum*, a leaf that is bent downwards.
6. —— *revolutum*, a leaf whoſe ſummits are rolled inwards.
7. —— *ſeminale*, a ſeed-leaf.
8. —— *caulinum*, a ſtem-leaf.
9. —— *rameum*, a branch-leaf.
10. —— *florale*, a leaf that is ſtationed near the flower.
11. —— *decurrens*, a decurrent or running leaf; a leaf which extends itſelf downwards along the ſtalk beyond its proper baſis.
12. —— *petiolatum*, a leaf ſupported on a *petiolus* or footſtalk.
13. —— *peltatum*, a target-ſhaped leaf.
14. —— *ſeſſile*, a leaf that is ſeated immediately on the ſtem or branch, without any manifeſt footſtalk; oppoſed to *petiolatum*.
15. —— *amplexicaule*, a leaf which tranſverſely embraces the ſtem by its baſe.
16. —— *perfoliatum*, a perforated leaf. This leaf differs from the preceding chiefly in the perforation, which is likewiſe tranſverſe, taking place at a greater diſtance from the margin.
17. —— *connatum*, a leaf formed by the union of two leaves at the baſe.
18. —— *vaginans*, a leaf the baſe of which longitudinally ſurrounds the ſtem like a ſheath. By the circumſtance of its longitudinal perforation, this ſpecies of leaf may be eaſily diſtinguiſhed from thoſe deſcribed at No. 15. and 16.



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov. 1 1804 as the Act directs by H.D. Symonds Pater-noster Row



Drawn by Syd Edwards

Engraved by F. Sansom

Published Nov 1 1804 as the Act directs by H.D. Symonds Paternoster Row

PLATE VII.—LEAVES.

DETERMINATION OF LEAVES *continued.*

Fig.

19. *Folium articulatum*, a jointed leaf, a ſpecies of compound leaf, in which the leaflets are produced each from the ſummit of that immediately under it, as in Cactus opuntia. This ſingular appearance Berkenhout very properly compares to the links of a chain.
20. *Folia ſtellata*, leaves ſurrounding the ſtem in the form of a radiant ſtar; ſynonymous to *verticillata*.
21. —— *quaterna*, leaves growing by fours; a modification of the two former terms.
22. —— *oppoſita*, leaves growing in pairs.
23. —— *alterna*, leaves ranged ſingly in ſucceſſion on both ſides of the ſtalk; the reverſe of the preceding term.
24. —— *imbricata*, leaves laid over one another like tiles, (imbrex, a gutter tile) as in the genus *ſaxifraga*.
25. —— *acerоſa*, chaffy leaves; leaves that are ſlender and of equal breadth throughout, ſomewhat hard, evergreen, pointed like pins, and ſurrounded at the baſe by chaffy ſcales. The term is exemplified in fir, pine, yew, and juniper.
26. —— *faſciculata*, leaves which proceed in bundles (*faſciculi*) from the ſame point, as in the larch-tree, and ſome pines.

---

27. **Frons*, a compoſition of a leaf and branch. The trunk of the palms and ferns is ſo termed by Linnæus. *Vide* FRONS.
28. *Folium ſpathulatum*, a leaf ſhaped like a ſpatula, as in *ciſtus incanus*, and *phlomis purpurea*.
29. —— *parabolicum*, a leaf which, in figure, ſomewhat reſembles the geometrical curve termed a parabola.

* *Frons* ſerves as a connecting link betwixt leaves and trunks, (the ſubject of the next plate). The two following terms belong to the diviſion containing ſimple leaves.

PLATE VIII.

TRUNKS. (*Vide* TRUNCUS.)

Fig.

1. *Culmus ſquamoſus*, a ſcaly culm, ſtraw, or haulm; a ſpecies of that trunk or ſtem which is peculiar to the graſſes. *Vide* CULMUS.
2. *Caulis repens & ſcandens*, a creeping and climbing ſtem, exemplified in *bignonia* and ivy.
3. *Scapus*, a ſpecies of trunk which elevates the fructification, but not the leaves; a naked flower-ſtalk, exemplified in auricula, and many of the liliaceous plants. *Vide* SCAPUS.
4. *Culmus articulatus*, a culm or ſtraw that has knots or joints at certain intervals.
5. *Caulis volubilis*, a twining ſtem, exemplified in convolvulus, black bryony, and hop.
6. —— *dichotomus*, (διχα, in two parts, and τεμνω, to cut) a forked ſtem; a compound ſtem, the diviſions of which are always by pairs; as in *ceraſtium dichotomum*, and *valeriana locuſta*.
7. —— *brachiatus*, (*brachium*, the arm) a ſimple ſtem, whoſe branches grow by pairs, reſembling arms; as in *mercurialis annua*.
8. *Stipes*, the trunk of a fungus. The term is likewiſe uſed for the *baſis* or ſtalk of that peculiar ſpecies of trunk called a *frons*. See Plate VII. fig. 27.

Pl. 8.



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov 1 1804 as the Act directs by H.D. Symonds Pater noster Row



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov 1 1804. as the Act directs by H.D. Symonds Pater noster Row

PLATE IX.

SUPPORTS AND ARMATURE OF PLANTS.

(*Vide* FULCRA.)

Fig.

1. *Stipula*, a ſtipule; a ſcale or ſcales at the inſertion of the footſtalks of the leaves and flowers.
   Cirrus, a claſper or tendril.
2. *Aculeus ſimplex*, that ſpecies of vegetable armature called prickles, (*aculei*) in which the weapons in queſtion proceed ſingly from the ſtem or branch. (*Vide* ACULEUS.)
3. ——— *triplex*, prickles which grow by threes; a three-pronged prickle.
4. *Spina ſimplex*, a ſimple or ſingle thorn. *Vide* SPINA.
5. —— *triplex*, a triple thorn.
6. *Stimuli*, ſtings, as in the nettle, *acalypha* and *tragia*.
7. *Bracteæ*, floral leaves; leaves which differ in colour and ſhape from the other leaves of the plant. In ſome ſpecies of ſage, lavender, and crown-imperial, they aſſume the appearance of a tuft of hair at the end of the flower-ſtem, and hence have obtained the name of *coma*. *Vide* BRACTEA and COMA.

PLATE X.

SUPPORTS AND ARMATURE OF PLANTS *continued.*

Fig.

8. *Glandulæ concavæ*, concave glandular appearances, ſeated on the footſtalk of the leaves.
9. ——— *pedicellatæ*, glands placed on ſhort footſtalks, and which likewiſe have their ſeat on the *petiolus*.
   * Glands originally ranked by Linnæus among the *fulcra* of plants, were afterwards abſorbed in the general term *pubes*. Wildenow, in his late edition of the *Philoſophia Botanica*, has reſtored them to their former ſituation, with what propriety the reader is left to determine.
10. *Pili*, hairs; a ſpecies of pubeſcence. *Vide* PUBES.
11. A thorny leaf and branch.
12. The prickly capſule of the beech.
13. *Pedunculus*, a flower-ſtalk. This, in the *Delineatio plantæ*, and *Termini Botanici* of Elmgren, ranks with the *fulcra*, but is excluded, and with reaſon, in the *Philoſophia Botanica*.
14. The thorny fruit of the horſe-cheſnut.
15. The prickly fruit of the cheſnut.



Drawn by Syd Edwards

Engraved by F Sansom

Published Nov 1 1804 as the Act directs by H.D. Symonds Paternoster Row





Drawn by Syd. Edwards.

Engraved by F. Sansom.

Published Nov. 1.1804. as the Act directs by H.D. Symonds Paternoster Row.

PLATE XI.

ROOTS. (*Vide* RADIX *and* BULBUS.)

Fig.

1. *Radix fuſiformis*, a ſpindle-ſhaped root, as in carrot.
2. —— *ſubrotunda*, a roundiſh root, as in turnip.
3. —— *fibroſa*, a fibrous or ſtringy root, as in *ſenecio vulgaris*.
4. —— *granulata*, a granulated root—a root conſiſting of a number of little knobs reſembling grain, which are faſtened to one another by ſmall fibres or ſtrings, as in *ſaxifraga granulata*.
5. —— *præmorſa*, a root which ends abruptly, having the appearance as if bitten off. The term is exemplified in plantain, and *ſcabioſa ſucciſa*.
6. —— *tuberoſa pendula*, a tuberous and pendulous root; as in *ſpiræa filipendula*, or drop-wort.

PLATE XII.

ROOTS *continued.*

Fig.

7. *Radix faſcicularis,* a ſpecies of tuberous root, in which the knobby parts grow in bundles. This is ſometimes termed a grumous root, and is exemplified in *ranunculus* and peony.
8. *Bulbus ſquamoſus,* a ſcaly bulb, as in the white lily.
9. —— *ſolidus,* a ſolid bulb, as in tulip.
10. ———— a tranſverſe ſection of a ſolid bulb.
11. —— *tunicatus,* a coated bulb, as in onion.
12. ———— a tranſverſe ſection of a coated bulb.
13. The roots, or pattes, as they are termed, of anemone.
14. *Radix teſticulata,* a twin-root, as in orchis.
15. The root of bird's neſt, a ſpecies of *ophrys.* This is evidently a modification of the faſcicular or bundled root.



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov. 1 1804, as the Act directs by H.D. Symonds Pater-noster Row.



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov 1.1804. as the Act directs by H.D. Symonds Paternoster Row

PLATE XIII.

ROOTS *continued.*

Fig.

16. *Radix dentata*, a root whoſe knobs reſemble teeth; a ſpecies of the granulated root, and exemplified in *primula*.
17. —— *palmata*, a hand-ſhaped root, as in the genus *orchis*.
18. —— *repens*, a creeping root; a root which extends in an horizontal direction, and ſends forth radicles at certain intervals, as in the couch-graſs.
19. Bulbs produced in the angle formed by the leaf and branch, as in *ranunculus ficaria*, or pilewort.
20. Roots ſent forth from the midrib of the leaf, as in cuckow-flower, *(cardamine.)*
21. Roots produced from the joints of the ſtalk, as in *potentilla reptans*.

PLATE XIV.

PARTS OF FRUCTIFICATION.

(*Vide* FRUCTIFICATIO.)

a CALYX.

Fig.

1. *Perianthium*, the flower-cup properly ſo called.
2. *Amentum*, a catkin. *Vide* AMENTUM.
3. *Spatha*, a ſheath; as in *narciſſus*.
4. 5. *Calyx auctus*, an increaſed calyx; a perianth, which has a row of leaves diſtinct from the flower-cup ſurrounding the baſe, as in *dianthus*.
6. *Involucrum univerſale*, the univerſal *calyx* or cover of an umbelliferous flower, which is placed under the larger or general umbel. *Vide* INVOLUCRUM.
7. ——— *partiale*, the partial *calyx* or cover of an umbelliferous flower, which is placed under the ſmaller or partial umbel.
8. *Calyptra*, the calyx of the moſſes.
9. *Volva*, the calyx of the *fungi*, or muſhroom tribe.
10. *Gluma*, the huſky *calyx* of the graſſes.


Pl.14



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov. 1. 1804. as the Act directs by H.D. Symonds Pater noster Row.



Pl 15



Drawn by Syd. Edwards

Engraved by F. Sansom.

Published Nov. 1 1804. as the Act directs by H.D. Symonds Pater-noster Row

PLATE XV.

PARTS OF FRUCTIFICATION *continued.*

β COROLLA.

Fig.

1. *Corolla monopetala*, a *corolla* or flower of one petal.
2. —— *hexapetala*, a corolla or flower of six petals.
3. —— *polypetala serie duplici*, a corolla or flower of many petals, in a double series or row.

PLATE XVI.

PARTS OF FRUCTIFICATION.

COROLLA *continued.*

Fig.

4. *Corolla ringens*, a gaping or grinning flower; *a*, the upper lip, termed *galea* or helmet; *b*, the under lip.
5. ——— *papilionacea*, a butterfly-shaped flower.
6. Exhibits the several parts of a papilionaceous flower:
   a, representing the *vexillum*, or banner;
   bb, the *alæ*, or wings;
   c, the *carina*, or keel;
   d, the *stamina*.
7. 8. *Corolla personata*, a masqued flower, or which resembles the snout of an animal;—*a*, the upper lip; *b*, the under lip.

Pl. 16



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov 1 1804 as the Act directs by H.D. Symonds Paternoster Row

Pl. 17.



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov.1.1804, as the Act directs by H.D. Symonds Pater-noster Row

PLATE XVII.

PARTS OF FRUCTIFICATION.

COROLLA *continued.* (*Compound Flowers.*)

Fig.

9. *Corolla compoſita floſculis ligulatis*, a compound flower with flat, tongue, or ſtrap-ſhaped florets; the ſemi-floſcular flower of Tournefort.
10. *Floſculus ligulatus*, a flat or tongue-ſhaped hermaphrodite floret; the ſemi-floret of Tournefort.
11. *Corolla compoſita radiata*, a compound radiated flower, having ſemi-florets in the *radius* or circumference, and florets in the diſk or centre.
12. The ligulated floret of a radiated flower, which wants both the ſexual organs.
13. *Corolla compoſita floſculis tubuloſis*, a compound flower with tubular or hollow florets; the floſcular flower of Tournefort.
14. *Floſculus tubuloſus*, a tubular or hollow floret; the floret properly ſo called.

*** For further particulars reſpecting compound flowers, the reader is referred to the articles COMPOSITUS *Flos* and SYNGENESIA in the Dictionary.

PLATE XVIII.

PARTS OF FRUCTIFICATION.

COROLLA *continued.*

Fig.

14. *Corolla campanulata*, a bell-ſhaped flower.

15. } Different modifications of the ſame.
16. }

17. *Corolla infundibuliformis*, a funnel-ſhaped flower.

18. —— *hypocrateriformis*, a ſalver-ſhaped flower:
a, the limb, *(limbus)* or upper ſpreading part of the petal;
b, the tube, *(tubus)* or lower hollow part.

19. —— *cruciformis*, a croſs-ſhaped flower.

20. The petal of a croſs-ſhaped flower, the upper ſpreading part of which, as of the petals of all polypetalous flowers, is termed *lamina*, the plate or border; the lower tapering part, *unguis*, or the claw.

21. *Corolla rotata*, the back or under ſide of a wheel-ſhaped flower.

22. The front or upper ſurface of a flower of the ſame deſcription.

Pl. 18.



Drawn by Syd. Edwards

Engraved by E. Sansom

Published Nov. 1.1804 as the Act directs by H.D. Symonds Paternoster Row



Drawn by Syd. Edwards

Engraved by F. Sansom.

Published Nov. 1. 1804 as the Act directs by H.D. Symonds Pater-noster Row.

PLATE XIX.

PARTS OF FRUCTIFICATION *continued.*

7 NECTARIUM.

Fig.

1. The flower of aconite or monk's-hood.
2. The horned nectaries of the ſame, being two fiſtular, nodding bodies reſembling ſtamina, with an oblique mouth and recurved tail, ſeated on long awl-ſhaped footſtalks, and completely hid by the upper helmet-ſhaped petal.
3. A bell-ſhaped nectary, exemplified in *narciſſus triandrus.*
4. The glandular nectary of willow *(ſalix.)*
5. *Nigella*, fennel flower, or devil-in-a-buſh.
6. The eight lipped nectaries of the ſame.
7. *Tropaeolum*, or Indian creſs, the nectary of which terminates the calyx, and reſembles a cock's ſpur.

PLATE XX.

PARTS OF FRUCTIFICATION *continued.*

♂ SEXUAL ORGANS.

Fig.

1. The *germen* or ſeed-bud of poppy, crowned with its flat, radiated, and target-ſhaped *ſtigma*.
2. Exhibits the different parts of a piſtillum, viz. *ſtigma*, ſtyle and *germen*.
3. Another illuſtration of the ſame.
4. *Piſtillum* of iris.
5. A *piſtillum* with a three-cornered *ſtigma*, germen, and no ſtyle.
6. *Piſtillum* of *Oenothera*, or tree-primroſe:
   - *a*, the quadrifid ſtigma.
   - *b*, the ſtyle.
   - *c*, the germen.
7. *Oenothera:*
   - *a*, the *piſtillum*.
   - *b*, the *ſtamina*.
   - *c*, the petals.
   - *d*, the upper ſpreading part of the *calyx*.
   - *e*, the tube, or long cylindrical lower part.
   - *f*, the *germen*.
8. The parts of a ſtamen or male organ of fecundation, in which,
   - *a* repreſents the *anther*,
   - *b* the filament,
   - *c* the pollen or fertilizing duſt.

NECTARIUM *reſumed.*

8. } Repreſent the ſingular nectaries of *parnaſſia*.
9. }
10. Paſſion-flower with its nectary, termed by Linnæus a triple crown.
11. The nectary of crown-imperial, being a *fovea* or pit in the baſe of each petal.
12. The five horned nectaries of columbine, as connected with the flower.
13. One of the horned nectaries of columbine detached from the flower.
14. The fringed or bearded nectarium in *iris*.


Pl. 20
9
10
11
8
12
13
14
1
2
3
4
5
6
7
a
b
c
d
e
f
g
Drawn by Syd. Edwards
Engraved by F. Sansom





Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov 1 1804 as the Act directs by H.D. Symonds, Paternoster Row.

PLATE XXI.

MODES OF FLOWERING. (*Vide* INFLORESCENTIA.)

Fig.

1. VERTICILLUS, a whirl or whorl.
2. FASCICULUS, a bundle or bunch.
3. SPICA, a mode of close inflorescence resembling a spike or ear of wheat, rye, or barley.
4. RACEMUS, a cluster; as of currants, grapes, &c.
5. PANICULA, a panicle; a mode of loose inflorescence resembling that of oats, and some other grasses.

PLATE XXII.

MODES OF FLOWERING *continued.*

Fig.

6. THYRSUS, a panicle contracted into an oval form.

7. 8. CYMA, a cyme; a mode of inflorescence which differs from an umbel, in having the partial footstalks placed without any regular order.

9. CORYMBUS, a mode of flowering, which, like the preceding, resembles an umbel in its general appearance, but may easily be distinguished by the unequal length of the footstalks, which do not, as in the umbel, proceed from the same centre, but are produced from different parts on both sides of the stalk.

10. CAPITULUM, a little head.


* These terms, expressive of the various modes of flowering, with their different combinations, are fully explained in the Dictionary.




Drawn by Syd. Edwards

Engraved by E. Sexton

Published 1 Nov 1804 as the Act directs by H.D. Symonds, Paternoster Row







Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov. 1.1804. as the Act directs, by H.D. Symonds Pater noster Row

PLATE XXIII.

PARTS OF FRUCTIFICATION *resumed.*

PERICARPIUM, *or* SEED-VESSEL.

Fig.

1. A Capsule, with an undivided cavity or single cell. *Vide* CAPSULA *and* LOCULAMENTA.
2. ——— with two cells.
3. ——— with three cells.
4. ——— with four cells.
5. ——— with six cells.
6. ——— with many cells.
7. That species of pod termed *legumen*, in which the seeds are fastened along one future only. *Vide* LEGUMEN.
8. *Folliculus*, a species of dry seed-vessel, which opens longitudinally on one side from bottom to top, and has the seeds loose within it. *Vide Folliculus* and *Conceptaculum*.
9. Represents that pulpy kind of pericarpium termed *pomum*, with its inclosed capsule having five cells, in which are contained the seeds. *Vide* POMUM.
10. *Drupa*, a pulpy seed-vessel of the cherry kind, containing a nut or stone. *Vide* DRUPA.
11. The section of a *drupa*, exhibiting the pulpy part, and the stone.
12. A nut, or seed covered with a shell. *Vide* NUX.
13. *Strobilus*, a cone. *Vide Strobilus*.
14. *Bacca*, a pulpy pericarp without valves, inclosing naked seeds. *Vide* BACCA.
15. The transverse section of a *bacca*, to exhibit the disposition of the seeds within the pulp.
16. 17. That species of pod termed *siliqua*, in which the seeds are fastened to both sutures or joinings of the valves alternately. *Vide* SILIQUA.

PLATE XXIV.

THE CLASSES OR PRIMARY DIVISIONS OF THE SEXUAL SYSTEM.

* The reader is referred to the Analyſis or general Scheme of this celebrated Method prefixed to the preſent work, as likewiſe to the explanation of each claſs in the Dictionary, under its reſpective title.

Fig.
1. *Monandria.*
2. *Diandria.*
3. *Triandria.*
4. *Tetrandria.*
5. *Pentandria.*
6. *Hexandria.*
7. *Heptandria.*
8. *Octandria.*
9. *Enneandria.*
10. *Decandria.*
11. *Dodecandria.*
12. *Icoſandria.*

Fig.
13. *Polyandria.*
14. *Didynamia.*
15. *Tetradynamia.*
16. *Monadelphia.*
17. *Diadelphia.*
18. *Polyadelphia.*
19. *Syngeneſia.*
20. *Gynandria.*
21. *Monœcia.*
22. *Diœcia.*
23. *Polygamia.*
24. *Cryptogamia.*



Drawn by Syd. Edwards

Engraved by E. Sansom

Published Nov 1 1804. as the Act directs by H.D. Symonds Paternoster Row



Drawn by Syd. Edwards

Engraved by F. Sansom

Published Nov. 1 1804. as the Act directs by H. D. Symonds Paternoster Row.

PLATE XXV.

THE ORDERS OR SECONDARY DIVISIONS OF THE SEXUAL SYSTEM.

Fig.

1. The Order *monogynia*, containing hermaphrodite flowers with one *piſtillum* or female organ.
2. *Digynia*, hermaphrodite flowers with two piſtils;—*a*, the piſtils detached from the flower.
3. *Trigynia*, hermaphrodite flowers with three piſtils;—*a*, the piſtils ſeparated.
4. *Tetragynia*, hermaphrodite flowers with four piſtils;—*a*, the piſtils ſeparated.
5. *Pentagynia*, hermaphrodite flowers with five piſtils;—*a*, the piſtils ſeparated.
6. *Hexagynia*, hermaphrodite flowers with ſix piſtils;—*a*, the piſtils ſeparated from the flower.
7. *Heptagynia*, hermaphrodite flowers with ſeven *piſtilla*;—*a*, the *piſtilla* detached from the flower.
8. *Decagynia*, hermaphrodite flowers with ten piſtils;—*a*, the piſtils ſeparated.
9. *Dodecagynia*, hermaphrodite flowers with twelve female organs.
10. *Polygynia*, hermaphrodite flowers containing an indefinite number of *piſtilla*, or female organs.

---

* Of theſe ten orders, *monogynia* is the firſt in the firſt thirteen claſſes; *digynia* the ſecond in the ſame claſſes, the ninth excepted; *trigynia*, the third in all the claſſes juſt mentioned, except the firſt, fourth, and ninth, in which laſt it is preſent, but holds the ſecond place. *Tetragynia* pertains to the fourth, fifth, ſixth, eighth, and thirteenth claſſes; *pentagynia*, to the fifth, tenth, eleventh, twelfth, and thirteenth; *hexagynia*, to the ninth and thirteenth; *heptagynia*, to the ſeventh alone; *decagynia*, to the tenth; *dodecagynia*, to the eleventh, the ſingle genus of which, however, (*ſempervivum*) is generally ranked with the order *polygynia*, though this, from the indefinite and ſuperior number of piſtils, is much more properly reſtricted to the fifth, ſixth, eleventh, twelfth, and thirteenth claſſes.

Fig.

11. *Gymnoſpermia*, the name of the firſt order in the claſs *didynamia*, in which *a* repreſents a longitudinal ſection of the flower, to diſplay the four naked ſeeds in the bottom of the calyx.

12. *Angioſpermia*, the name of the ſecond order in the claſs *didynamia*, containing ſuch hermaphrodite flowers with four ſtamina two longer than the others, as have their ſeeds contained in a veſſel;—*a*, the pericarp, or veſſel.

13. *Siliculoſa*, the firſt order in the claſs *tetradynamia*, containing ſuch flowers poſſeſſed of the claſſical character as have their ſeeds contained in a ſhort round pod;—*a*, the *ſilicula*, or pod divided to ſhew the ſeeds.

14. *Siliquoſa*, the ſecond order in the claſs *tetradynamia*, containing ſuch plants poſſeſſed of the claſſical character as have their ſeeds contained in a *ſiliqua* or long ſlender pod, to each future of which they are alternately attached;—*a*, the *ſiliqua*.

15. *Polygamia Æqualis*, the firſt order in the claſs *ſyngeneſia*;—*a*, a floret ſeparated from the aggregate.

16. ——— *ſuperflua*, the ſecond order in the claſs *ſyngeneſia*; *a* repreſents a female floret in the circumference or ray; *b*, an hermaphrodite floret in the centre or diſk.

17. ——— *fruſtranea*, the third order in the claſs *ſyngeneſia*.

18. ——— *neceſſaria*, the fourth order in the claſs *ſyngeneſia*.

19. ——— *ſegregata*, the fifth order in the claſs *ſyngeneſia*.—*a*, a floret with its proper flower-cup detached from the aggregate.

20. *Monogamia*, the ſixth order in the claſs ſyngeneſia;—*a*, repreſenting a ſection of the flower, to exhibit the union of the ſtamina by the anthers. *Vide ſyngeneſia* in the Dictionary, where a full explanation is given of each of theſe orders.

21. } *Trioecia*, the third order in the claſs *polygamia*, in which
22. } hermaphrodite flowers are intermingled with male, or
23. } female flowers, or both, on one, two or three plants.

24. *Filices*, ferns, the firſt order,
25. *Muſci*, moſſes, the ſecond order,
26. *Algæ*, ſea-weed, flags, the third order,
27. *Fungi*, muſhrooms, the fourth order,

} in the claſs *Cryptogamia*.

INDEX.

A.

AGGREGATE flowers. See AGGREGATUS *flos.*
Apple, a ſpecies of ſeed-veſſel. See POMUM.
Arguments for the ſex of plants. See ANTHERA and SEXUS.
Armature, or offenſive weapons of plants. See ARMA, ACULEUS, SPINA.
Arm-pit of leaves and branches. See AXILLA.
Auxiliary parts of plants. See FULCRA.

B.

Bark of plants. See STRUCTURA *vegetabilis.*
Beard of the graſſes. See ARISTA.
Bell-ſhaped flower. See COROLLA.
Bell-ſhaped flowers, a tribe of plants. See CAMPANACEÆ and CAMPANIFORMES.
Berry, a ſpecies of ſeed-veſſel. See BACCA.
Buds. See GEMMA.
Bulbs and bulbous roots. See BULBUS.
Buſhy flower-leaves. See BRACTEA and COMA.
Butterfly-ſhaped flowers, a tribe of plants. See PAPILIONACEÆ.

C.

Capſule, a ſpecies of ſeed-veſſel. See CAPSULA.
Catkin. See AMENTUM.
Cells, or cavities of ſeed-veſſels. See LOCULAMENTA.
Characteriſtical marks of plants. See CHARACTERES.
Chives. See STAMEN and FILAMENTUM.
Claſpers. See CIRRUS.
Claſſes, natural and artificial. See CLASSIS.
Claw of the petal. See COROLLA.
Climate of plants. See CLIMA.
Cluſters, modes of flowering. See CORYMBUS and RACEMUS.
Compound flowers. See COMPOSITUS *flos* and SYNGENESIA.
Cone, a ſpecies of ſeed-veſſel. See STROBILUS and CONUS.
Cone-bearing plants. See CONIFERÆ.
Croſs-ſhaped flower. See COROLLA and CRUCIFORMIS *flos.*
Crown of the ſeed. See CORONULA, PAPPUS, and SEMEN.

D.

Deciduous ſhrubs and trees. See DEFOLIATIO.
Direction of roots and trunks. See MOTUS.
Duration (terms of). See CADUCUS, DECIDUUS, and PERSISTENS.
Duſt, or powder of the *ſtamina*. See POLLEN.

E.

Elaſticity of the parts of plants. See MOTUS.
Emaſculation of flowers. See CASTRATIO and SEXUS.
Empalement, or flower-cup. See CALYX.
Eſſence of the ſeed. See CORCULUM.
Evergreen ſhrubs and trees. See DEFOLIATIO.

F.

Fall of the leaves. See DEFOLIATIO.
Female plant. See FEMINA *planta* and DIOECIA.
Female flower. See FEMINEUS *flos*, MONOECIA and DIOECIA.
Ferns, a tribe of plants. See FILICES.
Flags, or ſea-weed, a tribe of plants. See ALGÆ.
The flower. See ANTHUS and FLOS.
Flowers growing in catkins. See AMENTACEUS *flos*.
Flowers growing in heads. See CAPITATUS *flos*.
Flower-cup. See CALYX and PERIANTHIUM.
Flower-leaf. See BRACTEA.
Foliation, or the wrapping up of the leaves in the buds. See VERNATIO.
Foot-ſtalk of the flower and leaf. See PEDUNCULUS and PETIOLUS.
Full flowers. See PLENUS *flos*.
Funnel-ſhaped flower. See COROLLA.

G.

Gaping, or grinning flower. See COROLLA.
Genera of plants, their diſtribution. See GENUS.
Generation of plants. See SEXUS.
Graſſes, a tribe of plants. See GRAMINA.

H.

Haulm of the Graſſes. See CULMUS.
Head of flowers. See CAPITULUM.
Huſbandry of fig and palm trees. See CAPRIFICATIO and SEXUS.
Huſk of the graſſes. See GLUMA.

I.

Irregular flower. See COROLLA.
Inoculation, or budding. See GEMMA.

K.

Keel of a pea-bloom flower. See CARINA and COROLLA.

L.

Leaves, their form and determination. See FOLIUM.
Lipped-flowers, a tribe of plants. See LABIATUS *flos* and VERTICILLATÆ.
Lobes of the ſeed. See COTYLEDONES.
Luxuriance in flowers. See LUXURIANS, MULTIPLICATUS, and PLENUS *flos*.

M.

Male plant. See MAS *planta* and DIOECIA.
Male flower. See MASCULUS *flos*, MONOECIA and DIOECIA.
Maturation of the fruit. See FRUCTESCENTIA.
Methods in botany, natural and artificial. See METHODUS.
Milkineſs of plants. See LACTESCENTIA.
Modes of flowering. See INFLORESCENTIA.
Moſſes, a tribe of plants. See MUSCI.
Motions of plants. See MOTUS.
Muſhrooms, a tribe of plants. See FUNGI.

N.

Names of claſſes, genera, ſpecies, and varieties. See NOMINA.
Nutation of flowers. See MOTUS.

P.

Palms, a tribe of plants. See PALMÆ.
Paraſitic plants. See RADIX.
Pea-bloom flower. See COROLLA and PAPILIONACEÆ.
PETALS. See COROLLA.
Pith of plants. See STRUCTURA *vegetabilis*.
Pod, a ſpecies of ſeed-veſſel. See LEGUMEN and SILIQUA.
Pointal. See PISTILLUM.
Polygamy of plants. See POLYGAMIA.
Polygamy of flowers. See SYNGENESIA.
Prickles. See ACULEUS.
Principles of the ſexual method. See ANTHERA.
Prolific flowers. See PROLIFER *flos*.
Puſhing of the leaves. See FRONDESCENTIA.

R.

Rough-leaved plants. See ASPERIFOLIÆ and SCABRIDÆ.
Roots, their different forms. See RADIX and BULBUS.

S.

Salver-ſhaped flower. See COROLLA.
Scale for meaſuring the parts of plants. See MENSURA.
Seed-bud. See GERMEN.

Seed-covering (proper). See ARILLUS.
Seed-leaves. See COTYLEDONES.
Seed-veſſels. See ANGIOSPERMÆ *herbæ* and PERICARPIUM.
Sleep of plants. See MOTUS.
Sprouting of ſeeds. See GERMINATIO.
Spur of flowers. See CALCAR and NECTARIUM.
Stem or ſtalk. See CAULIS and CULMUS.
Stem-bulbs. See BULBUS.
Stock, or body of the root. See CAUDEX and RADIX.
Suckers. See BULBUS.

T.

Taſte, an attribute of plants. See SAPOR.
Tendrils. See CIRRUS.
Threads of the ſtamina. See FILAMENTUM.
Time of flowering. See EFFLORESCENTIA.
Tops of the ſtamina. See ANTHERA.
Trees diſtinguiſhed from ſhrubs and herbs. See ARBOR.
Tube of the flower. See COROLLA.
Twiſting of the parts of plants. See INTORSIO.

V.

Veil, or flower-cup of the moſſes. See CALYPTRA.

W.

Wheel-ſhaped flower. See COROLLA.
Winged ſeeds. See ALA and SEMEN.
Wings of a pea-bloom flower. See ALÆ, COROLLA and PAPILIONACEÆ.
Wintering of vegetables. See HYBERNACULUM, BULBUS, and GEMMA.

Alphabetical Liſt of the more remarkable Plants deſcribed or particularly mentioned in the Courſe of the foregoing Work, with a Reference to the Natural Order under which each is arranged.

A.

ACACIA. See *Lomentaceæ.*
Adder's tongue. See *Filices.*
Agaric. See *Fungi.*
Ahouai. See *Contortae.*
Aloe. } See *Coronariae.*
American aloe. }
American ebony. See *Papilionaceæ.*
American night-ſhade. See *Miſcellaneæ.*
American viburnum. See *Perſonatae.*
Apocynum androſæmifolium et cannabinum. See *Contortæ.*
Arabian jeſſamine. See *Sepiariae.*
Areca, or faufel-nut. See *Palmae.*
Ariſtolochia anguicida. See *Sarmentaceæ.*
Arnotta, or roucou. See *Columniferae.*
Arum. See *Piperitæ.*
Aſclepias Syriaca. See *Contortæ.*
Avignon berries. See *Dumoſae.*
Avocato, or avigato pear-tree. See *Holeraceæ.*
Azalea pontica. See *Contortæ.*
——— *viſcoſa.* See *Bicornes.*

B.

Bamboo-cane. See *Gramina.*
Banana-tree. See *Scitamineæ.*
Baobab, or Æthiopian four-gourd. See *Columniferae.*
Barbadoes aloe. See *Coronariae.*
Barbadoes cedar. See *Miſcellaneæ.*
Barren pine-apple. See *Coronariae.*
Barbadoes flower-fence. See *Lomentaceæ.*
Baſtard cypreſs. See *Calamariæ.*
Baſtard rhamnus. See *Calycifloræ.*
Baſtard ipecacuanha. See *Contortae.*
Baſtard ſenſitive-plant. See *Papilionaceæ.*
Bee-flower. See *Orchideæ.*
Beet, and ſugar-plants. See *Holeraceæ.*
Beidelſar, (an African ſpecies of ſwallow-wort). See *Contortæ.*
Benjamin-tree. See *Holeraceæ.*

Bermudas cedar. See *Coniferae.*
Betel. See *Piperitae.*
Bladder-carex. See *Calamariæ.*
Bonduc. See *Lomentaceæ.*
Bottle-gourd. See *Cucurbitaceæ.*
Braſiletto. See *Lomentaceæ.*
Buck-thorn. See *Dumoſae.*
Bull-ruſh *Scirpus.* See *Calamariæ.*

C.

Cabbage-tree. See *Palmae.*
Calabaſh. See *Putamineae.*
Caltrops. See *Gruinales.*
Camphire-tree. See *Holeraceæ.*
Canadian pines. See *Coniferae.*
Caper-buſh. See *Putamineæ.*
Carolina red-bay. } See *Holeraceæ.*
Caſhew-nut. }
Caſſia fiſtula. See *Lomentaceæ.*
Caſſine. See *Dumoſæ.*
Cedar of Lebanon. See *Coniferae.*
Ceraſtium viſcoſum. See *Caryophyllei.*
Cerbera manghas. See *Contortæ.*
Ceterach. See *Filices.*
China roſe. See *Columniferæ.*
Cinnamon-tree. See *Holeraceæ.*
Clove. See *Heſperideae.*
Cochineal ſhrub. See *Succulentae.*
Cocoa-nut tree. See *Palmae.*
Collinſonia. See *Perſonatæ.*
Colocaſia. See *Piperitae.*
Coloquintida. See *Cucurbitaceæ.*
Contrayerva. See *Scabridae.*
Cotton-graſs. See *Calamariæ.*
Cotton-ſhrub. See *Columniferae.*
Cow-itch vine. See *Papilionaceæ.*
Cucubalus behen. }
———latifolius. } See *Caryophyllei.*
——— otites. }
Cuſtard-apple. See *Coadunatæ.*
Cypreſs. See *Coniferae.*
Cypreſs-graſs. See *Calamariae.*

D.

Dacha. See *Scabridæ.*
Date tree. See *Palmae* and *Sexus.*
Dog's-tooth violet. See *Sarmentaceæ.*
Dogwood-tree. See *Papilionaceæ.*
Dolichos ureus. See *Papilionaceæ.*

Dragon-

Dragon-tree. See *Palmae.*
Dyer's-broom. See *Papilionaceæ.*
Dyer's-weed, or weld. See *Miſcellaneæ.*

E.

Egyptian dog's-bane. See *Contortae.*
——— melon. See *Cucurbitaceæ.*
——— Thorn. See *Dumoſae.*
Elaterium. See *Cucurbitaceæ.*
Elder (common). } See *Dumoſæ.*
—— (dwarf). }
Elm leaved ſumach. See *Dumoſae.*

F.

Farobier. See *Papilionaceæ.*
Florentine orrice. See *Enſatae.*
Fragrant ruſh. See *Calamariæ.*
Fraxinella. See *Multiſiliquæ.*
Freezing-wyth. See *Sarmentaceæ.*

G.

Garlick-pear tree. See *Putamineae.*
Gentian. See *Rotaceae.*
Geranium. See *Gruinales.*
Ginſeng. See *Hederaceae.*
Goat's-Thorn. See *Papilionaceæ.*
Greek valerian. See *Campanaceæ.*
Guava. See *Heſperideæ.*
Guaiacum. See *Gruinales.*
Guinea aloe. See *Coronariae.*
——— Corn. See *Gramina.*
——— Pepper. See *Luridae.*
Gum Arabic. See *Lomentaceæ.*
—— Copal. See *Dumoſæ.*
—— Senegal. See *Lomentaceæ.*
Gypſophila faſtigiata. See *Caryophyllei.*

H.

Hellebore. See *Multiſiliquae.*
Hemp. See *Scabridae.*
Hibiſcus (different ſpecies of.) See *Columniferæ.*
Herb-chriſtopher. See *Multiſiliquae.*
Holly. See *Dumoſae.*
Hop. See *Scabridae.*
Horizontal-cypreſs. See *Coniferae.*
Horſe-Caſſia. See *Lomentaceæ.*
Hypericum (ſpecies of). See *Rotaceæ.*

I.

Jalap. See *Campanaceae.*
Japaneſe Citron. See *Bicornes.*
Jew's mallow. See *Columniferæ.*
Indian arrow-root. See *Scitamineae.*
——— lychnis. See *Caryophyllei.*
——— mallow. See *Columniferae.*
Indigo. See *Papilionaceae.*
Iron-wood. See *Dumoſae.*
Judas-tree. See *Lomentaceae.*
Jujube. See *Dumoſae.*
Juniper. See *Coniferae.*

L.

Labdanum. See *Rotaceae.*
Laburnum. See *Papilionaceae.*
Larch-tree. See *Coniferae.*
Lily (white). } See *Coronariæ.*
——— (Martagon). }
Lime or Linden-tree. See *Columniferae.*
Liquorice. See *Papilionaceae.*
Logwood. See *Lomentaceae.*
Lycopodium. See *Muſci.*

M.

Magnolia. See *Coadunatæ.*
Mahogany. See *Miſcellaneae.*
Maiden-hair (different ſpecies of). See *Filices.*
Malabar night-ſhade. See *Holeraceae.*
——— oleander. See *Contortae.*
Male balſam-apple. See *Cucurbitaceae.*
Manchineel-tree. See *Tricoccae.*
Mangroves, or mangles. See *Holeraceae.*
Manioc, manihot or caſſava. See *Tricoccae.*
Marſh-mallow (common). See *Columniferæ.*
Melaſtoma (Eaſt-Indian ſpecies of). See *Calycanthemæ.*
Melianthus, or honey-flowers. See *Corydales.*
Mitre-ſhaped aloe. See *Coronariae.*
Monkſhoods. See *Multiſiliquae.*
Montpelier-ſcammony. See *Contortae.*
Moon-ſeed. See *Sarmentaceæ.*
Mountain-biſtort. See *Holeraceæ.*
Muſk-melon. See *Cucurbitaceæ.*
Myrtle. See *Heſperideæ.*
Myrtle-leaved ſumach. See *Miſcellaneæ.*

N.

Nettle-tree. See *Scabridae.*
New-Jerſey tea. See *Dumoſae.*

O.

Okra. See *Columniferae.*
Oleander, or roſe-bay. See *Contortae.*
Oleaſter, or wild olive of Bohemia. See *Calyciflorae.*
Orchis. See *Orchideæ.*
Opuntias, or Indian figs. See *Succulentae.*

P.

Palmetto, or thatch. } See *Palmae.*
Palm-oil tree. }
Pearl-aloe. } See *Coronariæ.*
Penguin, or karatas. }
Pepper of Senegal. See *Piperitae.*
Perſian manna. } See *Papilionaceæ.*
Pigeon-pea. }
Pimento, or all-ſpice. See *Heſperidæ.*
Pine (cultivated). See *Coniferæ.*
Pine-apple. See *Coronariae.*
Pineaſter. } See *Coniferae.*
Pitch-tree. }
Poet's ivy. See *Hederaceæ.*
Poiſon-aſh. } See *Dumoſae.*
Poiſon-tree. }
Polypody. See *Filices.*
Popo-tree. See *Tricoccæ.*
Prickly anonis. See *Papilionaceæ.*
Pumpkin. See *Cucurbitaceæ.*

R.

Red jaſmine. See *Contortae.*
Reeds. See *Gramina.*
Rhamnus alaternus. } See *Dumoſæ.*
——— *frangula.* }
Rhubarb. See *Holeraceæ.*
Rice. See *Gramina.*
Ricinus, or palma-chriſti. See *Tricoccæ.*
Royal Oſmund. See *Filices.*

S.

Saffron. See *Enſatae.*
Sago-tree. See *Palmae.*
Sapota. See *Dumoſae.*

Saſſafras-tree. See *Holeraceæ.*
Scammony. See *Campanaceæ.*
Scorpion-ſenna. See *Papilionaceæ.*
Screw-tree. See *Columniferae.*
Sea bind-weed. See *Campanaceæ.*
Senna.
Senega rattle-ſnake root. } See *Lomentaceæ.*
Senſitive plant.
Shrubby medick. See *Papilionaceæ.*
Silk cotton-tree. See *Columniferae.*
Soap-wort (officinal). See *Caryophyllei.*
Solanum (ſpecies of). See *Luridæ.*
Sour-ſop. See *Coadunatæ.*
South-ſea tea. See *Dumoſæ.*
Spaniſh potatoe. See *Campanaceæ.*
Spindle-tree. See *Dumoſæ.*
Spruce firs of North America. See *Coniferæ.*
Spurious varniſh-tree. See *Dumoſæ.*
Squaſh. See *Cucurbitaceæ.*
Squills. See *Coronariae.*
Staff-tree. } See *Dumoſæ.*
Star-apple. }
Storax-tree. See *Bicornes.*
Succotrine aloes. See *Coronariae.*
Sugar-cane. See *Gramina.*
Swallow-wort (common). See *Contortæ.*
Sweet-ruſh. See *Piperitae.*
Syrian dog's-bane. See *Contortæ.*

T.

Tea-ſhrub. See *Columniferae.*
Thapſia. See *Campanaceae.*
Tooth-ach tree. See *Hederaceæ.*
Traveller's joy. See *Multiſiliquæ.*
Tree-vervain-mallow of Java. See *Columniferæ.*
Tulip-tree. See *Coadunatæ.*
Turbeth, or turbith. See *Campanaceæ.*

V.

Vanelloes. See *Orchideæ.*
Varniſh-tree. See *Dumoſæ.*
Venice-ſumach. See *Dumoſæ.*
Venus's fly-trap. See *Lomentaceæ.*
Vetch (bitter). See *Papilionaceæ.*
Vinegar-tree. } See *Dumoſæ.*
Virginian ſumach. }

W.

Warted-gourd. See *Cucurbitaceæ*.
Water-melons, or citruls. See *Cucurbitaceæ*.
Water-ſoldier. See *Palmæ*.
White bryony. See *Cucurbitaceæ*.
White hellebore. See *Coronariæ*.
White mullein. See *Luridæ*.

Y.

Yams. See *Sarmentaceæ*.

THE END.

Bye and Law, Printers,
St. John's-Square, Clerkenwell.

BOOKS PUBLISHED BY H. D. SYMONDS.

1. CURTIS'S PRACTICAL OBSERVATIONS ON THE BRITISH GRASSES.

CONTAINING accurate Figures, coloured from Nature, of the moſt approved Graſſes for Meadow and Paſture Land; hints for the improvement and laying down of Land to the beſt advantage, accompanied with a deſcriptive Catalogue of all the Britiſh Graſſes. 4th Edition, price 5s. Octavo.

This little Treatiſe is one of the earlieſt and moſt approved on the ſubject for the improvement of Meadow and Paſture Land, and will be found highly ſerviceable to the Agriculturiſt.

---

2. BARR'S NEW AND BEAUTIFUL EDITION OF BUFFON'S NATURAL HISTORY, COMPLETE.

BUFFON'S NATURAL HISTORY, containing a Theory of the Earth, a General Hiſtory of Man, of the Brute Creation, and of Vegetables, Minerals, &c. Tranſlated from the French, and interſperſed with Notes. By J. S. BARR, Eſq. To which is added, by Way of a complete Supplement, A NATURAL HISTORY OF BIRDS, REPTILES, FISH, and INSECTS.

The whole of this valuable Work, forming, beyond compariſon, the moſt complete and elegant NATURAL HISTORY in the Engliſh, or any other Language, beautifully printed, and making Fifteen Volumes, which contain near 5000 pages of beautiful Letter-preſs, beſides the elegant and numerous ſet of original Copper-plates, taken from Life; being juſt printed off, in the beſt Manner, in 94 Numbers, price 1s. each, may be had, at the Option of the Purchaſers, by one or more at a Time, or in Fifteen Volumes.

In Boards, price - - - -	£. 5 1 6
Bound in Sheep, and lettered - -	6 4 0
Ditto, Calf, and lettered - - -	6 11 6
Elegantly bound in Calf, gilt and lettered -	6 19 0

The advantages ariſing from the entertaining ſtudy of NATURAL HISTORY are too generally felt and acknowledged to need enlargement in favour of a Work calculated to aſſiſt that enlightening purſuit; it may therefore be ſufficient to remark, that the general outline of the preſent deſign is to give a correct deſcription and theory of the Earth, the Hiſtory of Man, and of the Brute Creation, of Vegetables, Minerals, and of the various Birds, Fiſh, Reptiles, and Inſects, which adorn animated Nature; together with a clear ſuccinct account of their habits, cuſtoms, and qualities, on the authorities of

Buffon,	Marald,	Rheaumur,	De la Pluche,	Letſom,
Geoffry,	Lewenhoek,	Willoughby,	Gowan,	Edwards,
Johnſon,	Swammerdam,	Ray,	Monro,	Pennant,
Malphigi,	Spallangan,	Derham,	Hunter,	and

other eminent Naturaliſts; the Tranſactions of the various Philoſophical Societies in Europe, and the moſt reſpectable Travellers and Voyagers. Every attention has been paid to render this Work as complete and correct as poſſible: which the Tranſlator and Editor have more particularly undertaken, at the deſire of many of the Nobility and Gentry of this Kingdom, as no complete Hiſtory of the kind has hitherto been publiſhed.

1810.

NEW BOOKS

PUBLISHED BY

SHERWOOD, NEELY, AND JONES,

(Successors to Mr. H. D. Symonds,)

No. 20, PATERNOSTER ROW.

PERIODICAL PUBLICATIONS.

1. THE UNIVERSAL MAGAZINE, price 1s. 6d.; containing a most valuable series of original Communications in History, Philosophy, Belles-Letters, Politics, Arts, Manners, and amusements of the age; also, the Proceedings of Learned and Economical Societies. Published Monthly.

Seventy-three Numbers of this Work are now before the Public, comprehending from January, 1804, to December, 1809, and containing a great variety of valuable Articles on every subject of human Knowledge.—Every Six Numbers form a Volume. Price 10s. 6d. half-bound.

2. A NEW GEOGRAPHY, Accompanied by a Pair of Globes, gratis. To be completed in Twenty-four Monthly Parts, price 5s. 6d. each, or in One Hundred and Four Weekly Numbers, 1s. 6d. each, making two very large and splendid Volumes in Quarto, of a System of Modern Geography; or the Natural and Political History of the Present State of the World. By JOHN SMITH, LL. D.

This New Geography will unite as its characteristics, and, in a great part, as its peculiar features,

1. Descriptions of all Countries, compiled from the latest and best Authorities, in the English, French, German, and Spanish Languages; and arranged according to the most approved Methods of Statistical Writers.

2. Graphic Representations of the Manners and Characters of all People, and of the peculiar Features of all Countries, together with a View of the Metropolis of each separate Kingdom and Empire.

3. A Collection of New Maps of all Countries, equal or superior to those given in any existing Geography or separate Atlas.

4. A Pair of Adams's nine-inch Globes, from new Drawings, which include all the latest Improvements and Discoveries, calculated to perfect a System of Geography in every Family, Library, and Seminary of Education.

3. CURTIS's BOTANICAL MAGAZINE, or Flower Garden Displayed; intended for the use of such Ladies, Gentlemen, and Gardeners, as wish to become scientifically acquainted with the plants they cultivate. Continued by JAMES SIMS, M. D. Fellow of the Linnæan Society.

Thirty volumes of this Work are now published, price 29l. 10s. 6d. in Numbers. One of which continues to be published regularly on the First day of every Month, containing six coloured plates, with descriptions, price 3s. 6d.

4. The TRADESMAN, or COMMERCIAL MAGAZINE; price 1s. 6d.: including subjects relative to Commerce, Foreign and Domestic, together with suggestions for new Commercial Connections, inquiries and information on Fisheries, Mines, the Coal Trade, Canals, &c. &c. Published Monthly.

Eighteen Numbers of this work are already published, containing most valuable Commercial Information. Every six Numbers form a Volume. Price 10s. 6d. half-bound.

5. THE ROYAL MUSICAL MAGAZINE, Review and Register of Valuable Musical Publications, ancient and modern. By the most esteemed Modern Authors.

Each Number of this Work (price 2s. 6d.) contains, exclusive of the letter-press, as much music as is generally procured for Five or Six Shillings, and is particularly adapted to Ladies' Schools.

Just Published, price 12s. the Music in the Patriotic entertainment of the JUBILEE; written and composed by J. KEMP, Musical Doctor.

6. THE ANTIQUARIAN and TOPOGRAPHICAL CABINET, price 2s. 6d. each Number, or printed on fine paper, 4s.; published monthly, and contains eight highly-finished Engravings of Views, and other interesting Subjects, accompanied by sixteen pages of letter-press Descriptions, on fine wove paper, carefully hot-pressed.

Every Six Numbers form a Volume, with which is given an engraved Vignette Title-page and Tail-piece; so that each Volume contains fifty plates, with an appropriate Index, &c.

7. BARR's New and Beautiful Edition of BUFFON's NATURAL HISTORY, complete, in One Hundred Numbers, price 1s. 6d. each, with the plates accurately coloured, or 1s. plain. (See page 3.)

8. HODSON's ACCOMPLISHED TUTOR, or Complete System of Education; being an invaluable present to young persons: complete in Seventeen Numbers, price 1s. each. (See page 5.)

9. BARRINGTON's HISTORY of NEW SOUTH-WALES, from its first visitation by Captain Cook, down to the present state of that promising Country, complete in 26 Numbers, price 1s. each. (See page 12.)

J. G. Barnard, Printer, Skinner-street, London.

Published Annually.

10. DODSLEY'S ORIGINAL CELLAR-BOOK, or the Butler's Assistant in keeping a Regular Account of his Liquors; to which is added Directions for Brewing, and useful Information respecting the Management of Malt Liquors, &c. in the Cellar, price 1s. 6d.

The usefulness of such a book as this to any Gentleman who has a stock of Liquor in his Cellar, and willing to know how it is expended, is so obvious, that it need not be insisted on; and the method here proposed is so clear and easy, that any common servant may keep the account.

11. THE LAUNDRESS'S CHECK BOOK, or Complete Family Washing Book; for keeping a regular account of Linen, &c. given out to wash, iron, or mangle. The whole arranged on a new plan, in alphabetical order, comprising fifty-two pages, price 1s. 3d.

The utility of the Laundress's Check Book will appear obvious to every person, who has the care and management of putting out linen to wash, &c. not only as it will be a considerable saving of time, but will, if regularly kept, prevent the possibility of any misunderstanding between the parties for whose use it is intended.

Every article generally used in a family is here set down, for more speedy reference, in alphabetical order, on two lists, each of which is to be filled up on looking out the linen, so as to form duplicates of each other: the one to be cut off, and given to the Laundress with the clothes, who is expected to return the same, with the charges attending her labour, filled up against each article, and cast up at the bottom, so as to form a bill of the amount; the duplicate list to remain in the book, to be produced in case the other should be lost or mislaid by the Laundress.

AGRICULTURE & RURAL ECONOMY.

Mr. Lawrence's Agricultural and Veterinary Works.

In One large Volume, 8vo. price 12s. boards, a New Edition, being the Fifth, with large additions, containing a full, practical Exposition of the Nature, Causes, and Effects, of Blight, Smut, Mildew, and other Diseases of Corn, with various useful Hints on the most important Branches of Husbandry,

12. THE NEW FARMER'S CALENDAR, or, Monthly Remembrancer for all Kinds of Country Business; comprehending all the material Improvements in the New Husbandry, with the Management of Live Stock. Inscribed to the Farmers of Great Britain.

Containing

Reflections on the existing State of our Agriculture, its Merits and Defects, the real Causes, and only effectual Remedy of Scarcity.

The Calendar: pointing out the Business of every Month in the Year, as it regards Preparing the Land, Sowing, and Harvesting the various Crops, and the Management of Cattle--Hiring and Stocking Farms—The Implements of Husbandry—Soils and Manures—Draining—Fencing — Farm-Yard, its Form and Management—Vermin—Irrigation and Warping—Woods and Plantations—Tillage and Fallowing—The Drill Husbandry—Dibbling—Seed—Blights—Course of Crops—Cattle Crops—Winter Preservation of Roots, &c.—Meadow and Pasture—Live Stock, including the Breeding and Improvement of Horses, Neat Cattle, Sheep, Swine, Rabbits, Poultry, &c.—Diseases of Vegetables.

In a neat Pocket Volume, Price 2s. extracted from the preceding, for more general Use,

13. The FARMER'S POCKET CALENDAR; or, Monthly Remembrancer for all kinds of Country Business, necessary to be attended to throughout the Year; comprehending all the material Improvements in the New Husbandry.

14. The MODERN LAND-STEWARD; in which the Duties and Functions of Stewardship are considered and explained, with their several Relations to the Interests of the Landlord, Tenant, and the Public. 8vo. 10s. 6d. boards.

"If the Author had not already recommended himself to the Public by his New Farmer's Calendar, and other works, the judicious observations and useful hints here offered would place him in the list of those rural Counsellors who are capable of giving advice, and to whose opinion some deference is due, though it may not be implicitly followed. His sentiments on general subjects expand beyond the narrow boundaries of vulgar prejudice; and his good sense is forcibly recommended to us by its acting in concert with a humane disposition." *Monthly Review, Aug.* 1803.

15. A GENERAL TREATISE ON CATTLE; the Ox, the Sheep, and the Swine; comprehending their Breeding, Management, improvement, and Diseases. Dedicated to the Right Hon. Lord Somerville. Second edition, with additions, in one large volume, 8vo. 12s. boards.

Contents.—Neat Cattle—Various foreign Races. Form, and the Principles of improvement. Description of the established Breeds of British Neat Cattle with their permanent varieties. Breeding and rearing. The Dairy. Stall-feeding, &c. Ox labour, Various Opinions of preceding Writers. — Sheep and Wool. Breeding and Improvement. Various breeds of Britain. Spanish Sheep, with the Nature and actual State of the Improvement of British Wool by the Spanish Cross. Similar Improvement upon the Continent, from the French of Lasteyrie.—Swine. Various Breeds, Management, &c. Cattle Medicine. A Proposal for its establishment on a rational Foundation. On Quacks, advertised Medicines, and Infallible Receipts. The Various diseases of Oxen, Cows, and Calves; of Sheep and Swine, with Remedies and proper treatment.

16. A PHILOSOPHICAL and PRACTICAL TREATISE on HORSES, and on the Moral duties of Man towards the Brute Creation; Comprehending the Choice, Management, Purchase and Sale of every Description of the Horse; the improved Method of Shoeing; Medical Prescriptions and Surgical Treatment in all known Diseases: with Replies to the various Objections contained in a late Publication, and seasonable Hints to certain impolitic Advocates of the Veterinary College. Third Edition, with large Additions, in which the Nature and Tendency of Lord Erskine's late Bill for the legal Protection of Beasts, are fully considered. 2 vols. 8vo. £1. 1s. boards.

"The book certainly handles a number of very useful topics, in a most facetious and pleasing way." *Farmer's Magazine.*

"Mr. Lawrence treats particularly of the management of horses, under the heads of the economy of the Stable, purchase and sale, veterinary medicine, &c. He writes with spirit, good sense, and humanity, and we recommend his work to the notice of our readers." *Monthly Review.*

17 The GRAZIER'S READY RECKONER, or, useful Guide for Buying and Selling Cattle; being a complete set of Tables, distinctly pointing out the Weight of Black Cattle, Sheep, or Swine, from 3 to 130 Stones, by Measure

nent; together with Directions, showing the particular Parts where the Cattle are to be measured. By GEORGE RENTON, Farmer. Price 2s. 6d.

18. THE PRACTICAL PLANTER, r a Treatise on Forest Planting; comprehending the Culture and Management of Planted and Natural Timber, in every Stage of its Growth. -Also the Culture and Management of Hedge ences, the Construction of Stone Walls, &c. By WALTER NICOL. 7s. boards.

Dedicated to Lord Grenville.

In one volume 8vo. price 6s. boards.

19. THE EXPERIMENTAL FAR-ER; Being Strictures on various Branches of usbandry and Agriculture, drawn from a long ries of practice in different parts of Great Bri-in; containing Observations on planting and reserving Young Trees, with an approved me-od of thinning them, to become Timber. Like-ise, Plans for laying out Land, on a Five and our Field System. Also, a new method to bring e most Barren Land into Cultivation, for Mea-ows and Sheep-walks: and a variety of other eful Information in every branch of this Art, solutely necessary for every Person, from the ulent Farmer, to the Proprietors of small pieces Land. By THOMAS TIBBS, Farmer, te Land Steward to Lord Grenville; and who has received the Sanction and a Premium from the Board of Agriculture.

20. PRACTICAL OBSERVATIONS the BRITISH GRASSES; containing accurate ures of the most approved Grasses for meadow d pasture Land; hints for the improvement and ving down of Land to the best advantage; ac-mpanied with a Descriptive Catalogue of all e British Grasses. By the late WM. CURTIS. which is now added, A Short Account of the use of the Diseases in Corn, called by Farmers, e Blight, the Mildew, and the Rust: by Sir seph Banks, Bart.: illustrated with Plates, ice 5s.; or beautifully coloured, 7s. 6d.

BOTANY.

21. CURTIS'S LECTURES ON TANY; embellished with One Hundred New ates, illustrative of the Process of Vegetation, Sexual System, &c. from original drawings, de under the Author's direction, by Edwards, graved by Sansom, and correctly coloured from ture, in Three large Volumes 8vo. 4l. boards; ng a COMPLETE COURSE of LECTURES on TANY, as delivered in the Botanic Garden at mbeth,

By the late WILLIAM CURTIS, F. L. S. monstrator of Botany to the Company of Apo-caries; Author of the Botanical Magazine, ra Londinensis, &c. &c. Second Edition; ar-ged from the Manuscripts in the possession of Son-in-law, Samuel Curtis, Florist, Walworth: which is now added, A LIFE OF THE AU-OR, by Dr. Thornton.—These Lectures were d by the Author, to his Pupils, at the Botanic rden, and were intended by him to form accompaniment to the Botanical Magazine, which they are peculiarly adapted, treating the Science of Botany at large, in that sim-city of language, for which the Magazine is universally admired. The Introductory Lec-e contains much useful Information on pre-ving Specimens of Plants, taking Impressions hem in an expeditious and simple manner, and ticular directions for the more easy attain-nt of Botanical Knowledge. The succeeding ture contains entertaining information on the perceptibility of Plants, and their comparison with Animals; a curious subject, hitherto but little treated on. The following Lectures trace up the whole Science of Botany, avoiding a frequent repetition of technical terms, which, though in a certain degree necessary, are far from captivating, and often weary the young beginner in the pursuit of this elegant, useful, and entertaining Science.

22. A BOTANICAL DICTIONARY, or Elements of Systematic and Philosophical Botany. By COLIN MILNE, L. L. D. Author of the Institutes of Botany, and Habitations of English Plants. Third Edition, revised, corrected, and very considerably enlarged.

This Dictionary has long been the admiration of Europe, and is quoted as of the first authority, by all the most eminent writers, both in this country and abroad: it is recommended by the most eminent Professors and Teachers of Botany, as containing an excellent fund of Botanical Instruction, necessary to be known by every person who is cultivating that useful and agreeable Science.

In One large Volume 8vo. embellished with Twenty-five new Plates, accurately drawn from Nature by Edwards, and engraved by Sansom, price 1l. 1s. in boards, or 1l. 15s. with the Plates beautifully coloured.

NATURAL HISTORY.

23. BARR'S New and Beautiful Edition of BUFFON's NATURAL HISTORY, complete, in One Hundred Numbers, price 1s. 6d. each, with the Plates accurately coloured, or 1s. plain;

Containing a Theory of the Earth, a General History of Man, of the Brute Creation, and of Vegetables, Minerals, &c. Translated from the French, and interspersed with Notes, By J. S. BARR, Esq. To which is added, by way of a complete Supplement, a Natural History of Birds, Fishes, Reptiles, and Insects. A New Edition, corrected and greatly improved; embellished with a highly finished Portrait of Buffon, together with Memoirs of his Life, by Condorcet.

AGREEABLE TO THE CONDITIONS,

1. This valuable Work, forming, beyond comparison, the most complete and elegant Natural History in this or any other language, is beautifully printed in Octavo, on superfine Writing Paper.

2. It is embellished with a numerous set of elegant original Copper-plates, taken from Life, and engraved in the best manner, by Milton, and other celebrated Engravers.

3. The Colouring of the Subjects is executed in a superior style, by persons of the first ability in the art.

4. The Whole is completed in One Hundred Numbers, price 1s. 6d. each, with the Plates accurately coloured, or 1s. plain; making Sixteen handsome Volumes, in Octavo.

For the accommodation of Purchasers of former editions, the 16th, or supplementary Volume, may be had separately, to complete their sets.

TO THE PUBLIC.

THE Proprietors of Buffon's Natural History beg leave to say a few words upon the New Edition which they now offer to the Public. In order to render it as worthy as possible of that patronage with which it has been honoured, a most expensive Edition of Buffon in 114 Volumes, edited by Sonnini, has been procured from France, and a literary gentleman has been employed to collate every page of the translation with the original, line by line, so that the minutest error that might have crept in, has been detected; and

at the same time, numerous Additions, relative to facts which have been discovered since the time of Buffon, have been added in the form of notes. Besides this, the Proprietors have enriched this edition with a beautiful Portrait of the Author, and a Memoir of his Life, translated expressly from the Eloge pronounced by the celebrated Condorcet, before the French Academy, and Anecdotes of his private Life, by the Chevalier Aude; and further, to render it as perfect as possible, a Suplementary Volume is added, consisting entirely of Descriptions of Birds discovered since the Death of Buffon, being additions made to the Original by the celebrated Sonnini, and which are to be found in no other translation Such are the Improvements; and the advantages arising from the entertaining study of Natural History are too generally felt and acknowledged, to need any farther Enlargement in favour of a Work calculated to assist that enlightening pursuit. It shall only therefore be remarked, that the present design is to give a correct Description of the Earth and its Theory; of the History of Man, and the Brute Creation; of Vegetables, Minerals, &c; and of the various Birds, Fishes, Reptiles, and Insects, which adorn animated Nature.

Every Attention has been paid to render THIS WORK as correct and complete as possible; which the Translator more particularly undertook, at the desire of many of the Nobility and Gentry of this Kingdom, as no COMPLETE HISTORY of the kind had been published.

N. B. To prevent mistakes, and the obtrusion of former and inferior Works on this subject, the public are requested to ask for, or order,

BARR's New and Beautiful Edition of

BUFFON's NATURAL HISTORY.

Bingley's British Quadrupeds.

24. MEMOIRS of BRITISH QUADRUPEDS; illustrative principally of their Habits of Life, Instinct, Sagacity, and Uses to Mankind. Arranged according to the system of Linnæus. By the Rev. W. BINGLEY, A. M. Fellow of the Linnæan Society, and late of Peterhouse, Cambridge. Embellished with seventy Engravings, executed chiefly by Mr. Samuel Howitt. The Demy Copies, price 18s. in boards; the Royal Copies, with Proof-Impressions, 1l. 15s.

*** A few Copies are taken off on fine Imperial Vellum Paper, with the Plates beautifully coloured, price 4l. 4s. in boards.

25. ORGANIC REMAINS of a FORMER WORLD, or, an Examination of the Mineralized Remains of the Vegetables and Animals of the Antediluvian World, generally termed Extraneous Fossils. By JAMES PARKINSON.

Volumes the First and Second, with Plates, elegantly coloured, 2l. 12s. 6d. each, in boards.

In almost every part of this globe, the remains of a former world are continually offering themselves for the contemplation of mankind; teaching, that the planet we inhabit has suffered considerable changes by the ravages of an universal deluge, and by the influence of other causes, acting with vast power, and to a wide extent. Among these remains, the spoils of the vegetables and animals of those days are frequently discovered; evincing that several species of beings then existed, which are now entirely unknown, and perhaps extinct; their mutilated remains only being left to prove, that they once lived, and were destroyed with the former world.

These medals of nature, yielding an incontestable record of one of the most important æras in the history of the universe, exist in great quantities in this island: but whilst France and Germany have produced several valuable essays on these important subjects, Great Britain owns not a single systematic work on this branch of natural history. Reflection on this circumstance led to the present attempt to form a history of all those bodies which have been hitherto discovered; trusting that encouragement to such an undertaking will be secured by the laudable curiosity of those who dwell in those parts, where these wonderful relics of the Old World are daily, even by accident, brought to view.

*** The Third Volume, which completes the Work, is in great forwardness.

MEDICAL and CHEMICAL.

26. The WORKS Complete of JOHN BROWN, M. D. of Edinburgh; consisting of—1. Observations on former Systems of Medicine, and outlines of the New Doctrine. 2. A Refutation of the Doctrine of Spasms. 3. Elements of Medicine, a correct Translation. To which is prefixed, a Biographical Account of the Author, by his Son William Cullen Brown, M. D. in Three Volumes 8vo. 1l. 1s. boards.

27. An ESSAY on the VENEREAL DISEASE and its Treatment, illustrated by numerous Cases; intended to ascertain the Effects of Nitrous Acid and other analogous Remedies, lately proposed as Substitutes for Mercury. By WILLIAM BLAIR, Surgeon of the Lock Hospital, and Bloomsbury Dispensary, &c. The Third Edition, much improved and enlarged, complete in one volume 8vo. 10s. 6d. boards.

The Second Part of this Essay may be had separately, 7s.

28. A TREATISE on the VENEREAL DISEASE. By the late JOHN HUNTER. A New Edition, in one large Volume Octavo, embellished with Six Engravings. To which is added, an Introduction, and Commentary, by JOSEPH ADAMS, M.D. Author of "Observations on Morbid Poisons."

29. THE PHYSICIAN's VADE MECUM; being a Compendium of Nosology and Therapeutics, for the use of Students.

By the Rev. JOSEPH TOWNSEND.

Elegantly printed on fine Foolscap 8vo. Tenth Edition, considerably improved, 4s. sewed.

30. PARKINSON's HOSPITAL PUPIL, or an Essay intended to facilitate the Study of Medicine and Surgery. In Four Letters.

I. On the Qualifications necessary for a youth intended for the Profession of Medicine or Surgery.

II. On the Education of a medical Student, improved Course of Hospital Studies, &c.

III. Directions for the prosecution of Hospital Studies, according to the present system of Medical Education.

IV. Hints on entering into practice, on medical jurisprudence, &c. 3s. 6d. boards.

31. PARKINSON's CHEMICAL POCKET-BOOK, or Memoranda Chemica; arranged as a Compendium of Chemistry, with appropriate Tables.

A New Edition (the Fourth, 9s. boards) greatly improved by numerous and important Additions, particularly in Subjects connected with the Arts and Manufactures, as Dying, Tanning of Leather, Gilding, Painting, &c. to which is annexed, An Account of the recent Discoveries of Mr. Davy, respecting the chemical Agencies of Electricity, the metallic nature of the fixed Alkalis, of Ammo

nia, and of the Earths; the Decomposition of Sulphur, and of phosphorous, as well as of the boracic and fluoric Acids, and even of Nitrogen; and the extraordinary Experiments of the same Gentleman on the Muriatic Acid.

32. CHEMICAL PHILOSOPHY, or, the Established Basis of Modern Chemistry; intended to serve as an Elementary Work for the Study of that Science. By A. F. FOURCROY, Counsellor of State, Member of the National Institute, one of the Commandants of the Legion of Honour, and professor of Chemistry. Translated from the French, by W. Desmond. Third Edition, considerably enlarged and amended, price 7s. boards.

Cuier, in his Report to the National Institute, says,—"Fourcroy has published an enlarged Edition of his Philosophy of Chemistry, which is very justly considered as the best Elementary Work on that Science."

33. PLATES OF THE HEART, illustrative of the Circulation of the Blood, and the effects of Oxygen Air on the Blood. Elegantly printed in colours, with descriptions.

By R. J. THORNTON. 15s. sewed.

Domestic Medicine.

34. PARKINSON's MEDICAL ADMONITIONS TO FAMILIES, respecting the Preservation of Health, and the Treatment of the Sick; also, a Table of Symptoms, serving to point out the Degrees of Danger, and to distinguish one Disease from another; with Observations on the Improper Indulgence of Children, &c. Fifth Edition, greatly enlarged, 10s. boards.

35. AN ESSAY ON NURSING, and the Management of Children, from their Birth to Three Years of age.

By the late W. CADOGAN, M. D. 2s.

36. THE PHILOSOPHY OF MEDICINE; being Medical Extracts on the Preservation of Health and Cure of Diseases; including the Laws of Animal Economy, and the Doctrine of Pneumatic Medicine.

The Fourth Edition, greatly enlarged, containing upwards of 30 new Plates, chiefly anatomical, and Portraits of some of the most eminent Teachers in Medicine.

By ROBERT JOHN THORNTON, M. D.

In five thick volumes, 8vo. 3l. boards.

37. The PHILOSOPHY of PHYSIC; being a Natural History and Cure of the following Diseases:—

Fevers—Colds—Consumption—Asthma—Scurvy—Gout and Rheumatism—Stone and Gravel—Diseases of the Liver—Chronic and Nervous Diseases—Scrophula, or Evil—Diseases peculiar to Women—Diseases peculiar to Children, such as Rickets, Worms, Sore Eyes, Measles, Hooping Cough, and Small Pox—Dropsy—Palsy—Cancers—Dislocations—Fractures.

By the Rev. W. WILSON. 5s. boards.

38. PARKINSON's OBSERVATIONS on the NATURE and CURE of GOUT; on the Nodes of the Joints; and on the Influence of certain Articles of Diet, in Gout, Rheumatism, and Gravel. 5s 6d. boards.

39. PARKINSON's HINTS for the IMPROVEMENT of TRUSSES, intended to render their Use less inconvenient, and to prevent the Necessity of an Understrap. With a description of a Truss of easy construction and slight expense, for the use of the labouring Poor; to whom this little Tract is chiefly addressed. 1s.

EDUCATION.

The following are particularly adapted to the Use of Schools, and the Instruction and Amusement of the rising Generation. In addition to which, S. N. and J. have always a large supply of other Elementary Books, and every New Work as soon as it appears.

A liberal Allowance is made to Masters of Academies, and Governesses of Ladies' Schools.

LIBERAL EDUCATION.

In two large Vols. Octavo, embellished with an elegant Frontispiece, designed by Corbould, and engraved by Springsgerth, price 18s. in boards, or in 17 Numbers, to be had by one or more at a time, price 1s. each; every Number containing 56 pages of letter-press, and the whole embellished with 26 useful and elegant Copper-plates;

40. The ACCOMPLISHED TUTOR, or Complete System of Liberal Education; being an Introduction to Scientific Knowledge and Genteel Accomplishments. Containing the most improved Theory and Practice of the following Subjects:—

English Grammar and Elocution—Penmanship and Short-Hand—Arithmetic, Vulgar and Decimal—Stock-holding and Merchants' Accounts—Mensuration and Architecture—Optics—Algebra—Doctrine of Annuities—Trigonometry—Logarithms—Geography—Astronomy—Mechanics—Electricity—Pneumatics—Hydrostatics—Hydraulics—Drawing—Engraving—Painting—and a variety of other useful matter. Second Edition, corrected.

By THOMAS HODSON.

Plates of the following subjects are given in the course of the Work:—

Various Copies for the attainment of the Art of Writing—The Characters of Short-Hand—Geometrical Figures—The five Orders of Architecture—Solar Microscopes—Single Microscopes—Dr. Herschel's Telescope—Telescopes—Plain Trigonometry—Spherical Trigonometry—The Solar System—The Eclipses and Changes of the Moon—The Eclipse at large—A Map of the World in Two Hemispheres—Maps of Europe, Asia, Africa, North America, and South America—Mechanics—Electricity—Pneumatics—Hydrostatics—Hydraulics—Twelve Heads for Drawing—Twenty Human Figures.

TO THE PUBLIC.

Little needs be said in recommendation of a work like the present; which, from the great variety of matter it contains, must necessarily render it of universal utility. And though it comprehends such a multiplicity of objects, yet it contains all that is essential under each article, for the attaining a perfect knowledge of the same, and the whole substance of what is diffused through many a large and expensive treatise.

CHAP. I. On English Grammar, comprehends all the rules necessary to the attainment of that elegant and useful accomplishment, with all the graces of Elocution. The Chapter on Penmanship, contains directions for the most inexperienced person to qualify himself in that useful art, as well as in that of Short-Hand. The Chapter on Arithmetic, forms a complete essay on that useful science. That on Mensuration will be found to render its students adequate to any of the practical parts of Geometry, equally with those who have gone through the fifteen books of Euclid. The chapters on Algebra, Trigonometry, Logarithms, Geography, and Astronomy, will be found to comprise the whole principles of the sciences on which they treat. The Mechanical, Electrical, Hydrostatical, and Optical Parts, though not generally inserted in works of this kind, now form an essential part of Liberal Education, in almost every genteel Academy in England. The whole is interspersed with a variety of miscellaneous matter, and enriched with all the modern improvements of the present time.

To enumerate all the various classes of individuals for whom the present work is calculated, would be to particularize almost every description of mankind. The scholar, under the tuition of a master, would find his labours greatly abridged by a reference to such a treatise. The mechanical youth, and the man of business, may find all that is necessary to qualify for the shop, and the counting-house. Those who have missed the advantages of a liberal education, may here supply defects; and the experienced scholar may find his account in reviewing the earlier part of his education.

"This certainly is a useful and cheap work: the modern improvements on each subject are introduced; and we have no scruple in giving it our general recommendation."—*Vide British Critic.*

Newton's Principia.

41. The MATHEMATICAL PRINCIPLES of NATURAL PHILOSOPHY.
By Sir ISAAC NEWTON.
Translated into English by Andrew Motte. To which are added, Newton's System of the World; a Short Comment on, and Defence of, the Principia, by W. Emerson; with the Laws of the Moon's Motion according to Gravity; by John Machin, Astron. Prof. at Gresh., and Sec. to the Roy. Soc.

A New Edition, with the Life of the Author: carefully revised and corrected by W. Davis. The whole forming three handsome volumes 8vo. 1l. 11s. 6d. in boards, illustrated by upwards of fifty engravings, and embellished with an elegant Portrait of the Author.

Simpson's Fluxions.

42. The DOCTRINE and APPLICATION of FLUXIONS; containing, (besides what is common on the subject,) a number of modern Improvements, and the Solution of a variety of new and very interesting Problems, in different branches of the Mathematics,
By THOMAS SIMPSON, F. R. S.
To which is prefixed an Account of his Life. Revised and corrected by William Davis. In one handsome volume, 8vo. 10s. boards.

Stephenson's Land-Surveying.

43. THE SYSTEM OF LAND SURVEYING, at present adopted by Surveyors and Commissioners in old and new Inclosures, conducted as an actual Survey, on a plan consisting of open Fields, Ings, Common and old Inclosure, divided and allotted according to conditions of agreement between the several Proprietors.

Treating of the Quality and Quality Lines.—Taking Particulars.—Proprietors and Occupiers' Names.—Book of Particulars.—Explanation of Characters used in the Field-Book, &c.—Ranging the Poles.—Running the Lines.—Laying the Lines upon the Plan.—Plotting.—Valuing by the Commissioners.—Casting.—Taking Dimensions.—Finding the Content, &c.—Book of Dimensions, Castings, &c.

Dividing into Allotments—New Drains—New Roads—Stone and Sand Pits—Allotting the Fields, Common, Ings, &c.—Old Inclosure--Setting off upon the Plan each Proprietor's Quantity—The setting and staking out Allotments, Roads, Drains, Sand-pit, &c. &c.

To which are added Rules, showing in what manner Lines may be measured, where there are impediments, or not, to obstruct the Sight, such as Buildings, Water, &c. Taking Distances; measuring on the outside of any quantity of Land or Water, andthereby finding the content; surveying large Towns, Cities, &c. Likewise, the proper method to be pursued in measuring detached pieces of Land where plotting is not required. The whole by the Chain only. By WILLIAM STEPHENSON, Land-Surveyor, Horncastle. In one Volume, 4to. embellished with an engraved plan, and six plates, together with an engraved Field Book of 27 pages. 16s. half-bound.

*** The Editor of the Annual Review, after describing Mr. Stephenson's method of allotments, says "the instance is well made, and the practice upon it will give the learner a complete insight into the business. The number of plates accompanying this Work will be found very useful to the young Land-surveyor."

44. The YOUTH's PRECEPTOR, or, Moral Conductor from the Academy to Manhood: a Work, the Result of actual Experience, and adapted to the Level of Youthful understanding. To which is added, as an Incitement to the Study of it in Grown Youth, during their Hours of Relaxation from Business, an Essay on the extensive Utility, Advantages, and Amusement, of Mathematical Learning.
By DAVID MORRICE.

"We have with great satisfaction perused this Volume, and feel ourselves bound, by the duty we owe to the public, as well as in justice to the Author, to say, that, as a practical Treatise for the Regulation of conduct in life, it is deserving of the most extensive circulation. The Lessons which it inculcates are, we are assured, founded on actual experience, and have, therefore, the strongest claims to attention."

European Magazine, July, 1802.

Scraggs on Composition.

45. ENGLISH COMPOSITION; in a Method entirely new; with various contrasted examples from celebrated Writers. The whole adapted to common capacities, and designed as an easy help to form a good style, and to promote an early acquaintance with the works of the best authors. By the Rev. G. G. SCRAGGS, of Buckingham. To which are added, An Essay on the Advantages of understanding Composition; and

a List of the best Books for an English Reader, with remarks. 4s. bound.

Astronomy for Young Persons and Schools.

46. THE ELEMENTS OF ASTRONOMY, according to the Newtonian Principles; illustrated by several new and interesting Diagrams, and adapted as far as the science will admit, to the plainest capacities. Intended solely for the instruction of young Ladies and Gentlemen. By GEORGE REYNOLDS, 5s. bound.

Dubost's Commercial Arithmetic.

47. COMMERCIAL ARITHMETIC; or, a New Method of Teaching that Science with Facility, and of enabling Learners to instruct themselves, without the assistance of a Master. By C. DUBOST. 4s.

48. FISHER's INSTRUCTOR; or Young Man's Best Companion, in Reading, Writing, Arithmetic, Merchant's Accounts, Book-keeping, Mensuration in all its branches, Guaging, Dialing, Dying, Colouring, Gardening, Geography, Astronomy, &c. 12mo. 3s. 6d. bound.

49. HAWNEY's COMPLETE MEASURER, or, the whole Art of Measuring; being a plain and comprehensive Treatise on Practical Geometry and Mensuration, preceded by Decimal and Duodecimal Arithmetic, and the Extraction of the Square and Cube Root. Adapted to the use of Schools, and persons concerned in Measuring, Guaging, Surveying, &c. A New Edition, corrected and greatly improved.
By THOMAS KEITH. 4s. 6d. bound.

Evans's Geography.

50. An EPITOME of GEOGRAPHY, in Three Parts, arranged after a new manner, and enlivened by References to Ancient and Modern History. Second Edition, with considerable Additions and Improvements.
By JOHN EVANS, A. M.
Embellished with a very useful Frontispiece, 2s. 6d. bound, or on fine foolscap paper, 3s. 6d. boards.

51. JOHNSON's DICTIONARY of the ENGLISH LANGUAGE, in which the words are deduced from their originals, explained in their different meanings, and authorized by the names of the writers in whose works they are found. Abstracted from the Folio Edition by the Author. To which is prefixed, a Grammar of the English Language, with New Additions, 8vo. 12s. bound.

52. JOHNSON's DICTIONARY in Miniature; to which are added, an Alphabetical Account of the Heathen Deities; a List of the Cities, Boroughs, and Market Towns, in England and Wales; a copious Chronology; and a concise Epitome of the most remarkable events during the French Revolution. By the Rev. J. Hamilton, M.A. 3s. bound.

53. ENTICK's NEW SPELLING DICTIONARY; teaching to write and pronounce the English Tongue with ease and propriety. 2s. 6d. bound.

54. LOWTH's Short Introduction to ENGLISH GRAMMAR, with Critical Notes. 1s. 6d. bound; or, fine paper, 3s. 6d.

55. A NEW GUIDE to the ENGLISH TONGUE. In five parts.
By THOMAS DILWORTH.
Sixty-third edition, with considerable Improvements. 1s.

56. DILWORTH IMPROVED; or, A New Guide to the English Tongue.
By S. JAMES, Schoolmaster. 1s. bound.

57. UNION SPELLING; or, Reading made Easy. By C. PEARSON, Schoolmaster, in Westminster. 6d. with Cuts.

58. GOLDSMITH's ABRIDGMENT of the HISTORY OF ENGLAND, from the Invasion of Julius Cæsar, to the Death of George the Second; continued, by an eminent Writer, down to the present Time. Eleventh Edition, 3s. 6d. bound; or, in French, 4s. bound.

59. ACADEMIC LESSONS; particularly adapted to Female Seminaries.
By R. CAWTE. 2s. 6d.

60. A DIALOGUE between a LADY and HER PUPILS, describing a Journey through England and Wales, with a detail of the Arts and Manufactures of each City and Town, and Descriptions of Natural History; designed for Schools in general. By Mrs. BROOK. Second Edition, considerably enlarged; together with an introductory account of England, and of the Metropolis of the British Empire, with an accurate Map of the British Isles, by John Evans, A. M. 5s. boards.

61. BEAUTIES OF HISTORY, or, Pictures of Virtue and Vice, drawn from Real Life; designed for the Instruction and Entertainment of Youth. By L. M. STRETCH, Vicar of Twyford and Ouselbury, Hampshire, 12mo. 3s. 6d. bound.

62. The CHILDREN's FRIEND; translated from the French, of M. BERQUIN. Four Volumes. 12s. bound.

63. SELECT STORIES, from the French of M. BERQUIN. 3s. 6d. bound.

64. BELISARIUS, by MARMONTEL. Foolscap, Five Plates. 5s. 6d. boards; or, on fine drawing Demy 8vo. 7s.

65. FABLES, by Mr. GAY, 18mo. 2s. 6d. bound; or, on fine Foolscap 8vo. with 69 elegant Copperplates, 10s. 6d. boards.

66. The GLEANER; consisting of Essays, Stories, Visions, Narratives, Dialogues, Allegories, &c. interspersed with Proverbs, Maxims, and Anecdotes.

67. The TEMPLE of APOLLO; consisting of Odes, Eclogues, Elegies, Inscriptions, Portraits, Descriptions, Epitaphs, Hymns, Tales, Invocations, &c. in Poetry.

68. The FABULATOR, or, The HALL of ÆSOP; being a Selection of Fables in Prose and Verse. By W. HODSON.

The last three are neat Pocket Volumes, embellished with elegant Frontispieces and Vignette Titles, 1s. 6d. each, sewed, or 2s. bound.

69. An ABSTRACT of the ART of TEACHING, or communicating Instruction as far as it respects Reading, Grammar, Writing, Arithmetic, &c. &c. By DAVID MORRICE. 1s. 6d. sewed.

70. The PENMAN's REPOSITORY; containing Seventy correct Alphabets, a Valuable Selection of Flourishes, and a Variety

of New Designs. By the late WILLIAM MILNS, Member of St. Mary Hall, Oxford, and Master of the City Commercial School, London.

Nothing contributes so much to establish Freedom and Expedition in Writing, as frequent Practice in striking Simple, bold Flourishes, Capital Letters, &c. by command of hand: those, therefore, who wish to acquire this Excellence, will meet with a greater variety of Examples in this Work, than in any other of the kind. The want of correct Alphabets in the black Hands having long been complained of, the most minute attention has been paid to them in this Work; and, as no expense has been spared in the Engraving, it is presumed they will prove a standard for such as wish to acquire precise ideas of their Character. The admirers of the fanciful parts of Penmanship, will here find themselves amply gratified; a greater variety of curious Flourishes, as Birds, Beasts, Fishes, &c. &c. being occasionally introduced, than can be found in any other Publication; but at the same time so unconnected with the rest, as by no means to interfere with the more useful parts. 1l. 1s. or, in nine Numbers, at 2s. 6d. each.

Guisy's French Grammar and Exercises.

71. A NEW METHOD OF LEARNING FRENCH; in which the Principles of that Tongue are set forth with such order and perspicuity, as to promote the speedy attainment of that universal Language. By J. GUISY. Third Edition, corrected and improved.

3s. bound.

*** This Grammar is particularly adapted to the genius and disposition of Young Students, and persons entirely unacquainted with the French Language. By the arrangement of its principles, the nature of its rules and exercises, it has the uncommon advantage of being equally adapted to the meanest and highest capacities, and will prove no less useful to the master himself, than his pupil: for theory and practice, rules and examples, observations, and all the necessary indications to attain a thorough knowledge of its exercises, go hand in hand in every page.

Bellenger's Modern French Conversation.

72. MODERN FRENCH CONVERSATION; containing Elementary Phrases, and New Easy Dialogues, in French and English, upon the most familiar Subjects.

By W. A. BELLENGER. Price 2s.

The very flattering reception this Book has met with, and the encouragement the Author has received, are concurring proofs that his views have been approved of, and that he has hit upon such Dialogues as were really wanted, and generally wished for.

73. PERRIN's GRAMMAR of the FRENCH TONGUE, grounded upon the Decisions of the French Academy; wherein all the necessary Rules, Observations, and Examples, are exhibited in a manner entirely new. 3s. 6d. bound.

74. PERRIN's ENTERTAINING and INSTRUCTIVE EXERCISES, with the Rules of the French Syntax 3s. 6d. bound.

75. PERRIN's FRENCH SPELLING, in Two Parts. Third Edition. 2s.

76. NOUVELLE GRAMMAIRE FRANCOISE a l'Usage de la Jeunesse Angloise, Composée de manière a joindre la Pratique a l'etude des régles de la Langue Françoise, par H. GRATTE. Seconde Edition, revue et corrigée. 1s. 6. bound.

77. EXERCISES to the RULES and CONSTRUCTIONS of FRENCH SPEECH; consisting of Passages extracted out of the best French Authors, with a Reference to the Grammar-rules to be rendered back into French.

By LEWIS CHAMBAUD.

Seventeenth Edition, revised and corrected, with great Improvements, by Mr. Des Carrieres. 3s.

77. L'AMI DES ENFANS. Par M. BERQUIN: revu et corrigé avec soin. par Nicholas Salmon. 4 Tom, 12s.

78. LES PETITS ÉMIGRÉS, ou Correspondance de quelques Enfans. Ouvrage fait pour servir a l'Education de la jeunesse, par Madame de Genlis. Nouvelle Edition, avec des Notes grammaticales. 2 Tom. 8s. bound; or, fine paper, 10s.

80. ABRÉGÉ DE L'HISTOIRE D'ANGLETERRE, traduite de la Neuviéme Edition. Du Dr. Goldsmith. Par NICHOLAS HAMEL. Nouvelle Edition, revue, corrigée et continuée jusqu'á l'An Mil Huit Cent. 4s. bound.

81. LES AVENTURES DE TÉLEMAQUE, Fils D'Ulysse. Par M. FENELON. Nouvelle Edition, avec la Signification des mots les plus difficiles en Anglois au bas de chaque page. A laquelle on a ajouté un petit Dictionnaire Mythologique et Geographique pour faciliter l'intelligence de cet ouvrage. Le tout soigneusement revu et corrigé d'aprés les meilleures Editions de Paris, par N. WANOSTROCHT. 4s. bd.

82. BELISAIRE, ET FRAGMENS de Philosophie Morale, par M. MARMONTEL, de l'Académie Françoise. Nouvelle Edition, avec la Signification des Mots les plus difficiles en Anglois au bas de chaque page, revue et soigneusement corrigée, par N. WANOSTROCHT, Docteur en Droit. 12mo. 3s. 6d. bound.

83. LES VOYAGES DE CYRUS, avec un Discours sur la Théologie et la Mythologie des Anciens. Par M. RAMSAY. Nouvelle Edition, avec la Signification des mots les plus difficiles en Anglois au bas de chaque page, revue et soigneusement corrigée par N. WANOSTROCHT, 12mo. 3s. 6d. bound.

84. LA LITURGIE, ou Formulaire des Prières Publiques selon l'Usage de l'Eglise Anglicane, par N. WANOSTROCHT. 3s. 6d. bound.

85. CONJUGATA LATINA; or, a Collection of the purest and most usual Latin Words, distinguished into Classes according to the Times of their occurrence, and arranged according to their derivations, with their Significations and syllabic Quantities; comprising Three Thousand Words, chiefly selected from Terence, Cæsar, Virgil, Horace, and Ovid. To which is subjoined, an Alphabetical Index of all the Words in the Conjugata. By THOMAS HAIGH, A.M.

This collection was made with great labour by counting the times of the occurrence of all the words in Ovid's Metamorphoses, Virgil, and Horace, rejecting those which were not met with above nine times, and dividing the rest into classes according to their frequency. Almost five hundred words, collected on the same principle from Cæsar and Terence, were afterwards added, and the whole arranged etymologically. By this mode of selecting and distributing the words, their number is so much reduced, and their acquisition so much facilitated, that boys may learn them in a few months, while they are going over their accidence and grammar; yet so extensive is their usage, that in reading authors, they seldom have occasion to refer to their dictionaries above two or three times in a lesson of twenty lines; and in their Latin compositions, they commonly recollect the most apposite words.

In the etymological part, which is designed for elder students, are given nearly a hundred and fifty new derivations.

They who approve of Vocabularies, will have abundant reason to be pleased with this. The distinctive marks applied to each word, the Greek etymologies in the margin, and many other marks of attentive and successful labour, at once do credit to the compiler, and provide many advantages for the student who shall use the book.

British Critic, Vol. XX.

86. ENTICK's NEW LATIN-ENGLISH DICTIONARY, containing all the Words and Phrases proper for reading the Classics in both Languages; to which is prefixed, A New English-Latin Dictionary, for the use of Grammar-Schools, and Private Education. A New Edition, revised and corrected, by W. CRAKELT, A.M. 10s. bound.

87. TYRONIS THESAURUS, or, Entick's New Latin-English Dictionary. 6s. bound.

88. CLARKE's INTRODUCTION TO THE MAKING OF LATIN. 3s. bound,

89. A COMPLETE POCKET DICTIONARY of the English and German, and German and English Languages, in Two Parts. By W. RENDER, D. D. 11. 1s. bound. Each part may be had separately, viz.

The first part, containing English and German, 7s. 6d.

The second, containing the German and English, 14s.

In this Dictionary, the article, indicative of the gender, is added to every substantive; and such words as have various meanings, are elucidated by a proportionate number of examples.

Instructions for the true pronunciation of the German Language, and the genuine articulation of each letter of the alphabet, are prefixed to the Dictionary, which will be found extremely useful.

The Appendix contains a list of such words as are difficult to be distinguished in their pronunciation, though they vary in their orthography; also a list of proper names, and the names of countries, cities, and towns, principally those of Germany.

90. RENDER's PRACTICAL GRAMMAR of the German and English Language, Second Edition, 5s. bound.

"This is a useful Practical Grammar for beginners, and the method adopted in it, is a sufficient recommendation of the author, as a teacher of the German Language. The Exercises are well introduced to ground the learner in the knowledge of the parts of speech in their proper order, and will be of great service to teachers."—*Critical Review, April*, 1800.

91. RENDER's EXERCISES to the Rules and Constructions of German Speech. Second Edition, 5s. bound.

92. RENDER's GERMAN CALIGRAPHY, or Specimens of German Writing; containing Seven quarto Plates, elegantly engraved. Price 4s.

93. A CONCISE ENGLISH and GERMAN SPELLING-BOOK, or an easy Introduction to the German Grammar.

By G. A. MULLER. 4s. bound.

RELIGIOUS AND MORAL.

94. The WORKS, MORAL and RELIGIOUS, of Sir Mathew Hale, Knt. Lord Chief Justice of the Court of King's Bench; the whole now first collected and revised: to which are prefixed his Life and Death, by Bishop Burnett, and an Appendix to the Life, including the additional Notes of Richard Baxter.

By the Rev. T. THIRLWALL, M. A.

In two large vols. 8vo. 18s. boards, embellished with a highly-finished Portrait.

"My Lord Hale was one of the greatest judges that ever sat in Westminster-hall; he was as competent to express, as he was able to conceive. Lord Ellenborough.——East's Reports, Vol. v. p. 17.

95. The STUDENT and PASTOR, or Directions how to attain to Eminence and Usefulness in those respective Characters. To which are added, a Letter to a Friend, upon his entrance on the Ministerial Office, and an Essay on Elocution and Pronunciation.

By JOHN MASON, M.A.

Author of a Treatise on Self-knowledge.

New Edition, with Notes, and an Essay on Catechising. By Joseph Toulmin, D.D. 4s. boards.

Evans's Sequel to his Sketch.

96. The GOLDEN CENTENARY, or, Sequel to the Sketch of the Denominations of the Christian World; being One Hundred Testimonies in behalf of Candour, Peace, and Unanimity, by Divines of the Church of England, of the Kirk of Scotland, and among the Protestant Dissenters. To which are prefixed, Two Essays: the one on the Right of private Judgment in matters of Religion, the other on the Dignity and Importance of the New Commandment. With an Appendix, containing pieces of Poetry, illustrative of the Genius of Christianity.

By JOHN EVANS, A. M.

Third Edition, with Additions and Improvements. Embellished with an elegant Frontispiece, in which is represented accurate Likenesses of eight eminent Divines. 4s. boards.

Cennick's Village Sermons.

97. FORTY DISCOURSES ON IMPORTANT SUBJECTS, particularly adapted to Village and Domestic Worship.

By the late Rev. JOHN CENNICK.

A New Edition, to which is prefixed, The Life of the Author, revised and enlarged, by Matthew Wilks. Two Volumes, 12mo. with a Portrait of the Author, 8s. boards.

*** Mr. Cennick was one of Mr. Whitfield's most popular and useful fellow-labourers: he possessed a sweet simplicity of spirit, with an ardent zeal in the cause of his Divine Master. The Sermons before us, which are forty in number, have nothing to recommend them in point of elegance or learning; but the language is simple and perspicuous, the doctrine evangelical, and they every where breathe a sweet savour of the name of Jesus; and as there is a great call for Village Sermons, we know of none so suitable to be used with Mr. Burder's as those of Mr. Cennick's. His Life, to his twenty-second year, was written by himself; the remainder is supplied by Mr. Wilks, partly from the communications of friends, and partly from Mr. Whitfield's correspondence. *Evangelical Mag. June* 1805.

98. FENELON's PIOUS REFLECTIONS, for every Day in the Month. 1s. done up in coloured paper; or neatly bound, 1s. 6d.; in calf, 2s. 6d.; morocco, 3s. 6d.

"This excellent little Manual is too well known to the public to require on our part any additional recommendation; and the Memoirs of the amiable Fenelon, prefixed to this edition, form a considerable improvement."

Critical Review, April, 1800.

*** To prevent imposition, as an insidious at-

tempt has been made to usher into circulation a mutilated edition, the Proprietors respectfully inform the Public, that a Sketch of the Life of the Author, with a beautiful Portrait, and a Father's Advice to his Son, is added to every genuine and complete edition of this elegant little Manual.

Be particular in asking for, or ordering, the Edition published by Sherwood, Neely, and Jones, by whom an allowance is made to those who purchase a quantity to give away.

As a Companion to the above (the same size and price.)

99. FENELON's Pious Thoughts, concerning the Knowledge and Love of God. To which are prefixed, Directions for a Holy Life, and the attaining Christian Perfection. Also, the Closet Companion; or a Course of short Prayers for every Day in the Week.

100. FENELON on CHARITY.—The Characters and Properties of true Charity Displayed, from the French of Fenelon. One large Volume, 12mo. 4s. 6d. boards.

101. The HISTORY of JESUS, drawn up for the Instruction of Children, by W. MASON. Fifth Edition. 1s. sewed.

By the same Author, price 1s. 6d. bound,

102. CRUMBS from the MASTER's TABLE, or Select Sentences of Doctrinal Practical, and Experimental Divinity.

103. A SAINT INDEED, or, the Great Work of a Christian opened and pressed; being a seasonable and proper expedient for the Recovery of the much-decayed Power of Godliness among the Professors of these Times. By JOHN FLAVELL. 2s. bound.

Searle's Christian Parent.

104. The CHRISTIAN PARENT, or Short and Plain Discourses concerning God, and the Works and Word of God, in Creation, Redemption, and Sanctification. By the Author of the Christian Remembrancer, &c. &c. Fourth Edition, corrected and enlarged, 2s. sewed, or a smaller edition, 1s. 6d. half-bound.

105. The CHURCH of GOD; or, Essays upon some Descriptive Names and Titles, given in the Scriptures, by God the Holy Ghost, to the General Assembly of all true Believers in God the Son, or the God-Man, Jesus Christ; and denoting the Nature and Means of their salvation, through the everlasting Covenant made by God the Father, with those divine Persons in the one Jehovah. By the Author of the Christian Parent, &c. &c. Second Edition, in One large Volume, 12mo. 5s. boards.

106. A New Edition of the above, with the addition of One Hundred and Twenty pages of Original Matter, printed uniform with the Horæ Solitariæ of the same Author, and forming a Third Volume of that Work. In 8vo. 9s. boards.

107. LETTERS from the late Rev. William Romaine, A. M. to a Friend, on the most Important Subjects. By the late THOMAS WILLS. A. B. Third Edition, with a Portrait of the Author, 3s. sewed.

108. The Rev. JOHN RYLAND's ADDRESS to the INGENUOUS YOUTH of GREAT BRITAIN; together with a Body of Divinity in Minature; with a Portrait of the Author. 2s. boards.

109. RYLAND'S SELECT ESSAYS on the Moral Virtues, and on Genius, Science, and Taste. Price 1s. 6d. boards; or bound with the preceding, 4s. 6d. calf and lettered.

Scraggs's Beauties of Sentiment.

110. INSTRUCTIVE SELECTIONS, or, the Beauties of Sentiment; from near One Hundred and Fifty of the best Authors, ancient and modern, in Prose and Poetry, on Subjects Religious, Moral, Literary, and Entertaining, in a method entirely new; with Definitions to the Subjects, and the best Books recommended on Each; also the names of the Authors annexed to the various Extracts. By the Rev. G. G. SCRAGGS, of Buckingham. Two Volumes, 12mo. Second Edition. 9s. bound.

*** This Work is on a plan very different from any thing of the kind ever printed, as it not only contains a great number of Striking Extracts from the best English and foreign writers, not to be found in any other selection; but the whole is so methodically arranged, that any subject may be immediately found. The extracts are always complete sense, not very long, and yet not too short; but when it is considered that nothing but what is sentimental is inserted, it may be said to contain the essence of the best of all books of many ages and countries, and is a complete and cheap portable library for most readers.

"This Work is a very copious complete book of passages from a great variety of authors; in the first Volume confined to theological topics; in the second extended to morality, literature, and a variety of other subjects. By close printing, a vast abundance of matter is compressed under above fourscore heads in each volume; and certainly they who have not many books, may find in this a useful substitute for various others."—Vide *British Critic, Nov.* 1801.

111. A TRUE ESTIMATE of HUMAN LIFE, in which the passions are considered in a new light. By EDWARD YOUNG, LL. D. Author of the Night Thoughts. Fourth Edition, embellished with a Portrait of the Author, and his Life, by John Evans, A. M. 3s. boards.

Dedicated to Mrs. Hannah More, and printed uniform with her Sacred Dramas,

112. SOLOMON, a Sacred Drama. Translated from the German of Klopstock. By ROBERT HUISH. 5s. boards.

LAW.

Paul's Domestic Law Library.

113. The LAW of TYTHES, upon an original and practical Plan; comprising the Statutes, Adjudged Cases, Resolutions and Judgments, in Equity and the Ecclesiastical Courts. Originally compiled by JOHN PAUL, Esq. 3s. The Second Edition, with an Appendix; containing a copious Abstract of the 43d Geo. III. c. 84, relative to Spiritual Persons holding Farms, and enforcing residence on their benefices; Tythe Tables, calculated upon the most equitable terms of Composition; and a comprehensive Index; constituting a practical Guide to the Country Gentleman, Farmer, Parson, Solicitor, &c. By JOHN IRVING MAXWELL, Of the Honourable Society of the Inner Temple.

114. A DIGEST of the BANKRUPT LAWS, or, Debtor and Creditor's Com-

pendium; being a perspicuous Arrangement and familiar Explanation of all the Laws, Decisions, and Proceedings, under a commission of Bankrupt, from the act of Bankruptcy to the final allowance of the Certificate. With an Appendix of Precedents, Bills of Costs, a copious Index, &c. Second Edition. 5s.

115. The LAWS relative to LANDLORDS, TENANTS, and LODGERS, or, Every Landlord and Tenant his own Lawyer; Comprising Agreements, Assignments, Double Rent, Distress, Ejectment, Lodgings, Mortgages, Notices, Fixtures, Rent, Repairs, Waste, &c. With select Precedents for letting Houses, Lands, Apartments, and other useful Deeds; Tables of Costs, Stamps, &c. Tenth Edition. 3s.

116. The PARISH OFFICER's COMPLETE GUIDE; comprising the Laws relative to the respective Duties of Church-wardens, Overseers, Constables, Surveyors of Highways, &c. &c. including all the Acts of Parliament and adjudged Cases, regulating the Poor Rates, Parish Settlements, Certificates, Apprentices, Repairs of Highways, &c. &c. Seventh Edition. 5s. 6d.

117. A DIGEST of the GAME LAWS; comprising all the Statutes now in force, relative to Forests, Deer, Hares, Rabbits, Partridges, Pheasants, Red Game, Black Game, Pigeons, Dogs, Sea Fish, River Fish, &c. Regulations for Game-keepers' Certificates, &c. &c. Fourth Edition. 3s. 0d.

N. B. These Law Tracts have been in universal estimation, for their perspicuity and correctness: and, to add to their value, the present Editions have been carefully revised, corrected, and enlarged, with the additions of all the new cases, to the present period. The whole forming a valuable Law Library, and may be had complete in one large octavo Volume, 18s. in boards.

Those who may wish to become Purchasers of these works will be particular in asking for, or ordering, the Editions by Mr. Paul.

118. THE PROCEEDINGS at LARGE, on the Trial of John Horne Tooke, Esq. for High Treason, at the Sessions House in the Old Bailey, from Monday the 17th to Saturday the 22nd of November, 1794. Taken in Short Hand by J. H. BLANCHARD. 2 vols. 8vo. 12s. boards.

119. The PROCEEDINGS at LARGE, on the Trial of Thomas Hardy for High-Treason, from Oct. 28th to Nov. 5th 1794. Taken in Short-Hand by W. RAMSAY. 8vo. 10s. 6d. boards.

120. OBSERVATIONS on the DUTY and POWER of JURIES, as established by the Laws of England; with extracts from various Authors. By a Friend to the Constitution. Fifth Edition 1s.

121. An ESSAY on CRIMES and PUNISHMENTS, from the Italian of the Marquis Beccaria. Fifth edition, revised and corrected: to which is added, a Commentary, by Voltaire, one Volume, 8vo. 6s. boards.

BIOGRAPHY.

The only Life of FENELON *in the English Language.*

122. The LIFE of FENELON, ARCHBISHOP of CAMBRAY, drawn up from Original Manuscripts, and other sources hitherto unexplored; containing a detailed account of every event of his public and private Life, a relation of what concern he had in the affair of Quietism, the admirable judgment he displayed in the Education of the Duke of Burgundy, grandson of Louis XIV. &c. &c. From the French of M. L. F. de BAUSSET, formerly Bishop of Alais, and titular Counsellor of the Imperial University. In one large Volume, 8vo. embellished with a beautiful portrait of Fenelon.

123. The LIFE of the late WILLIAM COWPER, Esq. abridged from the Quarto Edition of William Hayley, Esq. with a fine Portrait, 3s. 6d. boards.

124. SKETCH of the LIFE and Literary Career of AUGUSTUS VON KOTZEBUE, with the Journal of his Tour to Paris, at the close of the year 1790. Written by himself. Translated from the German by ANNE PLUMTREE. To which is subjoined an Appendix, including a general Abstract of Kotzebue's Works, embellished with an elegant Portrait of the Author, 8s. boards.

125. THE ITINERANT, or, GENUINE MEMOIRS of an Actor. By S. W. RYLEY. 3 vols. price One Guinea in boards.

"This work contains a great variety of interesting matter, interspersed with Anecdotes of living Theatrical Characters. Scarcely a name that has figured on the Stage for the last thirty years, but has a niche in these volumes; which we can safely recommend as a useful appendage to dramatic biography, and as affording much entertainment, without injuring the morals." *Monthly Mirror.*

GEOGRAPHY and HISTORY.

126. ELEMENTS of GEOGRAPHY, and of NATURAL and CIVIL HISTORY; Containing,

1. The Order of the Spheres.
2. The Economy of the Sublunary Works of Creation, inanimate and living.
3. Picturesque and general Sketches of the different Parts of the Earth; and the varied Appearances and Manners of its Inhabitants.
4. The Rise, Revolution, and Fall, of the principal Empires of the World.
5. Changes through different Ages in the Manners of Mankind.
6, 7, 8, 9. Description of the different Quarters of the World; Europe, Asia, Africa, and America. Their Divisions into Countries, Provinces, &c. Their Climates, Soils, Animals, Plants, Minerals, Mountains, Rivers, Lakes, Canals, Commerce, Manufactories, Curiosities, Schools, Learning, Literati, Religious Professions, Language, Government, History, &c. By JOHN WALKER.

Fourth Edition, 12s. bound.

127. THE UNIVERSAL GAZETTEER; being a concise Description, alphabetically arranged, of the Nations, Kingdoms, States, Towns, Empires, Provinces, Cities, Oceans, Seas, Harbours, Rivers, Lakes, Canals, Mountains, Capes, &c. in the known World.—Likewise,—

The Government, Manners, and Religion, of the Inhabitants, with the Extent, Boundaries, and Natural Productions, Manufactures, and Curiosities of the Different Contries, containing several Thousand Places not to be met with in any similar Gazetteer. Illustrated with Fourteen Maps. By JOHN WALKER. Third Edition, revised, considerably

enlarged, and improved, by ARTHUR KERSHAW. 13s. 6d. bound, or with the Maps coloured, 16s. boards.

128. The MAPS and CHARTS, separately, forming a Complete Atlas for the Use of Schools; in One Volume coloured, 10s. half-bound.

129. The NAVAL GAZETTEER, or, SEAMAN'S COMPLETE GUIDE; containing a full and accurate Account, alphabetically arranged, of the several Coasts of all the Countries and Islands in the known World; showing their Latitude, Longitude, Soundings, and Stations for Anchorage. With a particular Description of the several Bays, Capes, Channels, Coves, Creeks, Currents, Gulphs, Harbours, Havens, Lakes, Oceans, Races, Rivers, Rocks, Sands, Shoals, Straits, Tides, Variations of the Compass, &c. By JOHN MALHAM, Author of Navigation made Easy and Familiar, and other works on Naval Affairs. Illustrated with Seventeen Charts, including a Whole Sheet Chart of the World, on Mercator's Projection. Second Edition, greatly improved, with the addition of nearly Four Thousand Articles. Two Volumes 8vo. £1. 1s. boards.

130. LETTERS WRITTEN DURING A JOURNEY THROUGH FRANCE, in the Year 1802; containing an Account of the State of its Morals, Literature, and Politics.

By HENRY REDHEAD YORKE, Esq.
Two Volumes, 8vo. 16s. boards.

*** It has long been our wish that some person, who had known France previous to the Revolution, would undertake to describe it in its present state. Mr. Yorke has fully gratified that wish, and with his fund of previous knowledge, an acute and penetrating mind, an aptness of classical allusion, no small portion of humour, and very considerable talents, he could scarcely fail to produce a work, upon this subject, at once instructive, interesting, and amusing. These letters are written in easy, perspicuous, and flowing language. Whether amusement or information be the object of the reader, they may be perused with advantage, for they contain a copious fund of both. *Vide Anti-Jacobin Review.*

SECOND EDITION, dedicated to his Majesty, neatly printed on yellow wove paper, and complete in 26 Numbers, price 1s. each, embellished with an Engraving, beautifully coloured, of

131. THE HISTORY of NEW SOUTH WALES, from its first visitation by Captain Cook, down to the present state of that promising Country; describing its Soil, Nature, and Produce; the Manners and Customs of the Natives; the natural History of the Country; and giving a particular Detail of the Proceedings in founding the Colony, and of its progressive Improvement, to the present Time; the Conduct of the Convicts, and every other interesting Particular.

By the Celebrated GEORGE BARRINGTON, Late Officer of the Peace at Paramatta; including a particular Account of his Voyage to Botany-Bay; together with the Trials, and a very interesting Account of the eventful Life of the Author.

In the course of the Work is given a Plan of New South-Wales, with an elegant Portrait of the Author.

*** The above very interesting Work may be had complete, in Two large Volumes 8vo. price 1l. 7s.

132. THE HISTORY of the VICEROYALTY of BUENOS AYRES; containing the most accurate Details relative to the

Discovery,	Courts of Justice,
Conquest,	Religion,
Topography,	Agriculture,
Climate,	Production,
Curiosities,	Commerce,
Natural History,	Revenues,
Population,	&c. &c.
Government,	Of that valuable Colony.

By SAMUEL HULL WILCOCKE.

This Work is uniformly and elegantly printed on fine wove demy paper, forming one handsome volume in octavo, embellished with a correct map of the country, an accurate plan of the town, and various other plates on subjects of natural history, &c. &c. 12s. 6d. boards.

The valuable information with which the British Public is here enriched, has been obtained in consequence of the Author having been engaged in extensive mercantile pursuits immediately connected with the Spanish Colonies in South America, the value of which, is very much enhanced by the difficulty in obtaining it. The volume contains a very particular and detailed account of all the principal mines which are worked in this colony; and the reader will be highly gratified and instructed by its details respecting the famed settlements of the Jesuits, their origin, extent, and subversion. We are precluded by our limits from entering on the curious detail of natural history, which adds to the interest and value of this volume. *Monthly Review, Sept.* 1809.

POETICAL AND DRAMATIC.

133. The POETICAL WORKS, Complete, of OLIVER GOLDSMITH, M. A. an improved edition; with an account of his Life and Literature. To which are prefixed, Poetical Tributes to his Memory, by Garrick, Woty, Pratt, &c. small octavo, elegantly printed and hot-pressed, with ten highly finished Engravings on Wood, by Austin, in his best Manner, from Designs, by Mr. Craig, 6s. boards, or on fine royal paper, with Proof Impressions of the Engravings, 12s.

134. POEMS, by the Rev. WILLIAM MASON, M. A. Author of "The English Garden;" containing the Dramatic Poems of Caractacus and Elfrida.—Monody on the Death of Mr. Pope.—Odes, Elegies, Letters, &c. 7s. 6d. boards.

135. The ENGLISH GARDEN, a Poem, by the Rev. WILLIAM MASON, M. A. To which is added, a Sketch of his Life, and fine Portrait, 4s. boards.

136. The ROBBERS, a Tragedy; Translated from the German of FREDERICK SCHILLER. By Dr. RENDER, with an Elegant frontispiece, 3s. 6d.

Schiller's tragedy of the Robbers is doubtless a splendid effusion of genius; it is the production of a most vivid and extraordinary imagination, and abounds with beauties of the most striking nature.

137. DON CARLOS, a Tragedy; Second Edition: Translated from the German of FREDERICK SCHILLER, with an Elegant Frontispiece. 5s. boards.

138. MARY STEWART, QUEEN OF SCOTS; a Tragedy, by F. SCHILLER, 8vo. 4s. 6d. or fine paper, 6s. boards.

*** The three Tragedies of Schiller, complete, in one large volume, 9s. boards.

139. COUNT BENYOWSKY, or, the Conspiracy of Kamtschatka; a Tragic-Comedy; in Five Acts, by BARON KOTZEBUE. From the German, by Dr. RENDER, with an Elegant Frontispiece, 3s. 6d. sewed.

140. The WIFE with TWO HUSBANDS; a Tragic-Comedy, in Three Acts. 2s. 6d.

141. COMIC SKETCHES, or, the Comedian his own Manager; written and selected for the Benefit of Actors, in England, Ireland, Scotland, and America. Inscribed to Performers in general. By CHARLES LEE LEWES, Comedian.

The materials for this Work, were originally collected for the East-Indies, but owing to some circumstances, which are now first made Public from Original Documents, they were never applied thus. Besides a deal of Facetiousness, and Sketches truly Comic, they contain a number of entirely new Anecdotes, relating to Lord Orrery, Garrick, Smith, Hogarth, Quick, Foote, Mossop, &c. &c. To theatrical amateurs and professional gentlemen, it may be strongly recommended, as containing a store whence they may derive much utility and amusement.

A Life of LEWES, and a Portrait, are prefixed, with some Original Letters which passed between him and the British Government in India, on his arrival at Bengal, in 1788. 4s. boards.

"This little volume contains a great deal of amusing matter, and may be properly characterized by the appellation of a Droll Performance, such as might be expected from such an "Odd Fish" as the Author. The satire is keen, always entertaining, and perfectly free from ill-nature."
Literary Journal, June, 1804.

Miniature Shakspeare.

142. SHARPE's EDITION, Complete in nine beautiful Miniaturevolumes, 2s. each, sewed, or 2s. 6d. neatly half bound, red back and lettered, of the Plays of William Shakspeare, accurately printed, and without the smallest abridgment, from the text of the late Mr. Steevens, and now offered to the patronage of the Public, in a form combining an elegance, portability, and cheapness, hitherto unattempted. Embellished with an elegant miniature of Shakspeare.

Though the editions lately published, of the Plays of our immortal Dramatist, have been numerous beyond all precedent, the proprietors of this edition consider any apology for adding to the number perfectly unnecessary. Its intention is obviously to facilitate and extend the knowledge of an author, of whom England has just reason to be proud; and whose

.....works are such
As neither Man nor Muse can praise too much.

Shakspeare's Seven Ages.

143. A SERIES of highly FINISHED ENGRAVINGS from Shakspeare's Seven Ages of Man. By Mr. WILLIAM BROMLEY,

Who has already so ably distinguished himself in Macklin's Bible, Bowyer's History of England, and other Works of equal celebrity, from designs by Mr. Stothard, R. A. accompanied with descriptions historical, moral, and entertaining. By an eminent Literary Character.

N. B. This Work consists of Seven Plates, comprehending the Seven Ages; a beautiful Vignette characteristic of the subject; and the passage complete from Shakspeare. The whole, eleven inches and a half by eight, and 28 pages of letterpress, price £1. 10s.

For the accommodation of the curious, and the patrons of the Fine Arts, a few copies are taken off in colours, which will be found to equal drawing. £3.

MISCELLANIES.

COMPANION TO CŒLEBS.

144. NUBILIA in SEARCH of a HUSBAND; including Sketches of ModernSociety, and interspersed with Moral and Literary Disquisitions: Fourth Edition, with two additional Chapters. 9s. boards.

"Some married persons, even in their marriage, do better please God, than some virgins in their state of virginity."—*Taylor.*

The author of Nubilia has sometimes surpassed Cœlebs in animation, variety, and elegance.—Throughout this work there is a vigorous tone of morality, a dignity, an elevation of mind. The criticisms on Burns display much good sense, good taste, and acute discrimination on just principles of morality. If Cœlebs has passed through nine editions, we should have a bad opinion of public taste, if Nubilia does not pass through eight. Whoever may be its author, it is, unquestionably, the production of an enlightened, observing, and virtuous mind, and bears internal evidence of talent and learning." *Anti-Jacobin Review, June* 1809.

Beauties of Paley.

145 BEAUTIES selected from the Writings of the late ARCHDEACON PALEY, alphabetically arranged, with an Account of his Life, critical Remarks upon some of his peculiar Opinions, a copious Index, &c. embellished with an accurate Likeness. By W. HAMILTON REID.

Beauties of Blair.

146. SENTIMENTAL BEAUTIES, from the Writings of the late Dr. BLAIR; including the latest Editions of his Sermons, Lectures, &c. &c. Alphabetically arranged. With a copious Account of the Life and Writings of the Author. Carefully abridged from the larger Works of the late JOHN HILL, L. L. D. and Dr. FINLAYSON. A New Edition, with considerable Additions. By W. HAMILTON REID, in one large volume, 4s. 6d. boards.

Beauties of Beattie.

147. BEAUTIES selected from the Writings of JAMES BEATTIE, LL. D. late Professor of Moral Philosophy and Logic in the Marischal College and University of Aberdeen, arranged in a pleasing and perspicuous manner, under the following Heads; Poetical, Moral, Philosophical, Theological, Critical, and Epistolary.

To which are prefixed a Life of the Author, and an Account of his Writings; together with Notes on the First Book of the Minstrel, by THOMAS GRAY, LL. B. printed uniform with the above, and embellished with a correct likeness of the author. Price 5s. 6d.

148. MARY DE CLIFFORD; a Story, interspersed with many Poems. By SAMUEL EGERTON BRYDGES, Esq. The Second Edition, embellished with two elegant Engravings, 4s. boards.

"A production of unprecedented worth, written in the high spirit of ancestorial dignity, and with an enthusiasm scarcely mortal." *See the Second Volume of the Lyre of Love.*

149. The MISCELLANEOUS WORKS of TIM BOBBIN, Esq.; containing his View of the Lancashire Dialect; with large Ad-

ditions and Improvements. Also his Poem of the Flying Dragon and the Man of Heaton; together with other Whimsical Amusements in Prose and Verse. To which is added a Life of the Author, by RICHARD TOWNLEY, Esq. 3s. 6d. bound.

150. The FRIEND of WOMEN; from the French of Bourdier de Villemert. By ALEXANDER MORRICE.

This Work is designed to exalt the Female Character, and raise that lovely part of the creation to the rank to which they are born, and to which their many virtues so justly entitle them. It treats on the rank of women in society; studies suitable to women; employment of women; pleasures and luxury of women; the character and temper of women; love and gallantry; marriage; education of children; domestic government; virtues of women. One volume, 8vo. 5s. boards.

151. PARIS DELINEATED; including a Description of the principal Edifices and Curiosities of that Metropolis; from the French of Mercier. 2 vols. 8vo. 13s. in boards, embellished with an accurate plan of Paris.

152. An HISTORICAL SKETCH of the FRENCH REVOLUTION, from its Commencement to the Establishment of the Republican Constitution; with a Transcript and Examination of that Constitution. Also, Philosophical Remarks on the predisposing causes of this wonderful change in the political picture of Europe, and an explanation of the chief events which accompanied it in its progress. By S. PERRY; who, in consequence of the decree of the national convention of France, was, with the other Englishmen in Paris, imprisoned in the Madolonettes, Ecossais, and Luxemburg. 2 vols. 8vo. 16s. boards.

153. A JOURNAL of OCCURRENCES at the TEMPLE, during the Confinement of Louis XVI. King of France. By M. CLERY, the king's valet de chambre. Translated by R. C. DALLAS, Esq. 6s. sewed. The same on fine paper, 10s. 6d. In French, 6s. or 10s. 6d. fine paper.

154. NEW PICTURE of PARIS, from the French of M. Mercier. 2 vols. 8vo. 16s. in boards. This Work will be found to contain not only a lively Description of the French Metropolis, but an accurate delineation of the Manners of the Inhabitants, the Public Amusements, and every thing worthy the attention of Foreigners. It also abounds with curious, interesting, and original Anecdotes of the French Revolution; and, perhaps, gives a better picture of it, than any other publication extant.

155. An INTERESTING NARRATIVE of the TRAVELS of JAMES BRUCE, Esq. into ABYSSINIA, to discover the Source of the Nile. Abridged from the Original Work, by SAMUEL SHAW, Esq. Fourth Edition, with copper plates, 4s. boards.

*** Notwithstanding the utility and pleasure that may be derived from Mr. Bruce's Travels, yet that Work, occupying five large volumes in quarto, and being sold for five guineas, but few individuals can afford to purchase it. In order, therefore, that the generality of readers might not be debarred from the perusal of a work fraught with so much entertaining and interesting information, this narrative is extracted from those celebrated travels; and on a fair and candid perusal, it will appear, Mr. Shaw has brought into the compass of a single volume, every thing worthy the reader's attention.

156. A TOUR through SICILY and MALTA, in a Series of Letters to William Beckford, Esq. From P. BRYDONE, F. R. S. One neat Volume, 12mo. 4s. 6d. boards.

157. An EXCURSION from SIDMOUTH to CHESTER, in the Summer of 1803; in a Series of Letters to a Lady. Including Sketches of the Principal Towns and Villages in the Counties of Devon, Somerset, Gloucester, Monmouth, Hereford, Salop, Derby, Stafford, Warwick, and Worcester. Interspersed with Biographical Anecdotes and Incidental Remarks, particularly intended for the Information and Amusement of the Rising Generation. By the Rev. EDMUND BUTCHER.

In two pocket volumes, price 8s. boards, embellished with an elegant View of Sidmouth, Devon.

158. The STATE of the NATION with respect to its Public Funded Debt, Revenue, and Disbursement; comprised in the Reports of the Select Committee on Finance, appointed by the House of Commons to examine and state the total Amount of the Public Debts, and of the Interest and Charges attending the same, to the present Time; particularizing the Receipts and Disbursements of all the Public Offices; the Names of the Superior Officers and Clerks in each Department; their Salaries and Fees; together with the Amount of whatever additional Pensions or Salaries they receive from other Situations paid by the Public. 4 vols. 8vo. 1l. 8s. boards.

159. MANUAL of LIBERTY, or Testimonies in Behalf of the Rights of Mankind; selected from the best Authorities in Prose and Verse, and methodically arranged. 8vo. 6s. bds.

160. LAVATER'S PHYSIOGNOMY, and PHYSIOGNOMICAL RULES; Essays on Physiognomy, for the promotion of the knowledge and the love of mankind. Translated from the German of the Rev. John Caspar Lavater. By THOMAS HOLCROFT, Esq.

A New Edition, with Additions, corrected and improved, by W. Beaumont, Esq. in 4 large volumes, royal 8vo. 4l. 4s. boards.

To this Edition is added a Translation of a valuable posthumous Physiognomical Work, by Mr. Lavater, lately published at Zurich, by Mr. G. Gesner, Son-in-law to the Author, entitled One Hundred Physisgnomical Rules, elucidated by fifty-eight additional Engravings, together with a Life of Lavater.

The Hundred Physiognomical Rules of Mr. Lavater, lately published in Germany, and now first translated, and annexed to this edition, form of themselves a work truly curious, and highly valuable to all who would wish to study Physiognomy as a Science. They were not intended for publication by the Author, during his life-time, but intrusted only to a few select friends, under the strictest inhibition from making them public. They appear to have been considered by Lavater, as containing the most important and profound secrets of his Art. Their authenticity is unquestionable, both from the testimony of the Editor of the Posthumous Works of Lavater, Mr. George Gessner, his Son-in-law, and the internal marks they bear of the Style and Spirit of his Writings.

161. An Abridgment of the above, in One Volume 12mo. 4s. 6d. boards.

162. A WEEK's CONVERSATION on the PLURALITY of WORLDS; a New Edition, with considerable improvements. From the French of Monsieur de Fontenelle, by J. HUGHES, Esq. and others. To which is added, Mr. Addison's Defence of the Newtonian Philosophy. 2s. 6d. in boards.

163. The LAW of NATURE, or, Catechism of a French Citizen; containing the second and concluding part of The Ruins; or, a Survey of the Revolution of Empires. By M. VOLNEY, one of the Deputies of the National Assembly of 1789, and Author of Travels into Syria and Egypt, &c. A new and beautiful Edition, printed in a pocket size, with an elegant Portrait of the Author, engraved by Ridley, 2s. 6d. sewed, or handsomely bound and gilt, 4s.

The above elegant Work contains the following interesting subjects:

1. The Law of Nature.—2. Characters of the Law of Nature.—3. The Principles of the Law of Nature, as they relate to Man. 4 The Basis of Morality; of Good; of Sin; of Crimes; of Vice—of Virtue.—5. Individual Virtue; Knowledge.—6. Temperance.—7. Continence.—8. Courage and Activity.—9. Cleanliness.—10. Domestic Virtues.—11. The Social Virtues and Justice.—12. Developement of the Social Virtues.

164. THE WAY TO HEALTH; a Selection of Maxims for the Preservation of Health, extracted from the Villager's Friend; and printed on a single sheet, for the Cottager's Fireside. Embellished with an emblematical Print. Price 6d.

165. DANGEROUS SPORTS; a Tale, addressed to Children, warning them against wanton, careless, or mischievous Exposure to Situations, from which alarming Injuries so often proceed. By JAMES PARKINSON, Hoxton. Embellished with a Frontispiece, and Eleven Wood-cuts, 2s. 6d. neatly half-bound.

"Who knows but one of my Stories may one day save the life of some child!"—Old Milson.

166. The VILLAGER's FRIEND and PHYSICIAN, or a Familiar Address on the Preservation of Health, and the removal of Disease on its first appearance. Supposed to be delivered by a Village Apothecary.

By JAMES PARKINSON, Hoxton.

With Cursory Observations on the Treatment of Children, on Sobriety, Industry, &c. intended for the promotion of Domestic Happiness. Second Edition, with a Frontispiece. 1s.

"We cannot help expressing our opinion, that the excellent Society for Bettering the Condition of the Poor, could not employ a small portion of their fund in a manner more conducive to that purpose, than by encouraging and facilitating the circulation of this book among them." *British Critic.*

167. A TREATISE on the GAME of CRIBBAGE; showing the Laws and Rules of the Game, as now played at St. James's, Bath, and Newmarket; with the best method of laying out your Cards, and exposing all the unfair arts practised by Professional Players, or such men as are generally known by the appellation of Black Legs, &c. Composed by several of the Sporting Gentlemen of the first celebrity, and digested by ANTHONY PASQUIN, Esq. Second Edition, 2s. 6d.

Domestic Cookery.

168. The HOUSEKEEPER's DOMESTIC LIBRARY, or, New Universal Family Instructor in practical economy; containing the whole Art of Cookery, in all its new and fashionable Varieties; with proper Instructions for Baking, Roasting, Boiling, Broiling, Frying, Hashing, Stewing, Fricaseeing, with Confectionary in all its Branches; Potting and Collaring Fish and Meat—Salting and Curing Hams, Tongues, Bacon, Beef, Pork, &c.—Pickling of every description—Brewing of Porter, Ale, Beer, and Table Beer—Distilling of Spirits, Simple Waters, Compounds and Cordials—Making and Keeping Choice Wines.—Also the Complete Art of Carving, and performing the Honours of the Table with grace and propriety. Likewise new Bills of Fare, made Dishes of all descriptions; Directions for Marketing, &c. &c. By CHARLES MILLINGTON. In one large Volume, 8vo. price 9s. boards.

The following Books are all uniformly and elegantly printed in the best Manner, on fine Yellow Wove Paper, Foolscap Octavo, and embellished with highly-finished Engravings.

169. The LETTERS OF A PERUVIAN PRINCESS, by Madame DE GRAFIGNY; also, as a Sequel, the Letters of AZA, by IGNATIUS HUNGARI DE LA MARCHE COURMONT. To which are prefixed, A Life of Madame DE GRAFIGNY, and a short Biographical Notice of MARCHE COURMONT. Translated from the French, by WILLIAM MUDFORD. 6s.

*** In this Translation it has been attempted to transfuse more of the manner and genius of the author, than has been accomplished by former versions: and it is also distinguished from former translations, by the Memoir of MARCHE COURMONT, who has not hitherto been known, as the Author of the Letters of AZA.

170. LETTERS of YORICK and ELIZA, being the Correspondence between Mrs. DRAPER and LAURENCE STERNE. To which is added, a sketch of their Lives, &c. This is the only Edition published in which Eliza's Letters are incorporated with those of Yorick's, 3s. 6d. boards.

171. FITZOSBORNE'S LETTERS on several Subjects, by the late WILLIAM MELMOTH, Esq. of Bath, the elegant Translator of Cicero and Pliny. To which is added, a sketch of the Life of the author, 6s. boards.

172. LETTERS of ABELARD and HELOISE, with a particular Account of their Lives and Misfortunes. To which are added, Poems by Pope, Madan, Cawthorne, Birch, Seymour, &c. &c. 6s. boards.

173. The CORRESPONDENCE of THEODOSIUS and CONSTANTIA, before and after her taking the Veil, by Dr. LANGHORNE: with a Life of the Author, 5s.

174. ROUSSEAU'S LETTERS of an Italian Nun and an English Gentleman, Fifth Edition, 3s. 6d. boards.

"A slave to his own feelings, he pourtrays every thing, with the greatest vivacity. On the subjects of Love, therefore, we are to expect many beautiful flights, and accordingly the whole of the present volume is enriched by them. *Literary Review.*

175. ORIGINAL LETTERS of J. J. ROUSSEAU to M. DE MALSHERBES, M. D'ALEMBERT, Mad. La M. LUXEMBOURG, &c. with a Fac-Simile of Rousseau's Hand Writing, and an original Military Air of his own Composition; also Original Letters of Butta Fuoco and David Hume. Translated from the French, with a Portrait of the Author, 4s. 6d. boards.

*** The above Letters are well known to the Literary World for their elegance of language, and purity of morals; they therefore cannot be too highly recommended to those who wish to obtain a correct style of writing, particularly in epistolary correspondence.

176. ESSAYS ON MEN AND MANNERS, by OLIVER GOLDSMITH, M. B. With a Life and Critique on the Writings and Genius of the Author, by W. MUDFORD, Author of "A Critical Inquiry into the Moral Writings of Dr Johnson." &c. &c. With four beautiful Engravings. 6s. boards.

177. ESSAYS, MORAL, ECONOMICAL and POLITICAL. By FRANCIS BACON, BARON VERULAM, VISCOUNT St. ALBAN'S. Ornamented with an elegant Portrait of Lord Bacon. To which is added, a sketch of his Life. 6s. boards.

A Miniature Edition of the above, elegantly printed, price 2s. 6d. boards,

178. FABLES of the ANCIENTS, in Philosophy, Morality, and Civil Policy, illustrated and explained by LORD BACON, With Notes, critical and explanatory, by Dr. SHAW. Embellished with Twelve highly-finished Engravings on Wood, by AUSTIN, from Designs, by CRAIG, 5s. boards.

179. The CONDUCT of the UNDERSTANDING, by JOHN LOCKE, Esq. 3s. 6d. boards.

"For a man to understand fully the business of his particular calling, and of his religion, is usually enough to take up his whole time." See Sect. 19. A Miniature Edition of the above. 2s. boards.

180. SOME THOUGHTS Concerning EDUCATION, by JOHN LOCKE, Esq. foolscap 8vo. 5s. boards.

181. The ECONOMY of HUMAN LIFE, in Two Parts, by R. DODSLEY, with a Life and Portrait of the Author, together with Six elegant Engravings, price 6s. boards.

182. Dr. GREGORY'S LEGACY to his DAUGHTER. A new and beautiful Edition, with an elegant Frontispiece. 3s. boards.

183. An UNFORTUNATE MOTHER'S ADVICE to her Absent DAUGHTERS; in a Letter to Miss Pennington. By the late Mrs. PENNINGTON, 2s. 6d.

184. WILLIAM TELL, or, SWISSERLAND DELIVERED; a posthumous Work of the Chevalier de Florian. To which is prefixed, a Life of the Author, by JAUFFRET. Translated from the French by WILLIAM B. HEWETSON, Author of "The Blind Boy," &c. &c. 5s. boards.

TRADE and BUSINESS.

185. LEYBOURNE'S READY-RECKONER, or, Trader's Sure Guide; containing Tables ready cast up, adapted to the use of all who deal by Wholesale or Retail; exhibiting, at one view, the amount or value of any number or quantity of Goods or Merchandize, from one up to ten thousand, at the various prices, from one farthing to one pound, &c. &c. with a List of Mercantile Stamps, and various other useful and interesting Tables. Twenty-third Edition, 2s. bound.

Morrice on Brewing and Malting.

186. A TREATISE on BREWING; wherein is exhibited the whole process of the art and mystery of Brewing the various sorts of Malt Liquor; with practical examples of each species. Together with the manner of using the Thermometer and Saccharometer; elucidated by examples, rendered easy to any capacity, in brewing London Porter, Brown Stout, Reading Beer, Amber, Hock, London Ale, Windsor ditto, Welch ditto, Wirtemberg ditto, Scurvygrass ditto, Table Beer, and Shipping ditto.

Also general instructions for the making of Malt; with Tables of the Net Duties of Excise on Strong and Table Beer, payable by Common Brewers in Town and Country.

By ALEXANDER MORRICE, Common Brewer. 10s. 6d. boards.

In this work the just proportion of the various quantities of Malt, Hops, and other ingredients necessary for brewing the above species of Malt Liquor is given, as well as every other information that can possibly be requisite for the young common Brewer, or the private family, in Town or Country; and as it is that kind of knowledge which none but the experienced Common Brewer can communicate, the Author flatters himself that this Treatise will be found, for practice, superior to any other hitherto published.

187. The OILMAN's VADE-MECUM; being a useful Assistant to the Retail as well as the Wholesale Dealer; showing, at one view, the value of a Tun of Fish or Seed Oil, at any price per Gallon; and the Weight and Value of any number of Gallons, at any price per Tun. To which is added, an Appendix, to find the value of the Pounds and Half Pounds, being less than a Gallon. By R. W. WHITTON, Accountant. Second Edition. 7s. 6d. bound.

188. The LABORATORY, or School of Arts; containing a large collection of Valuable Secrets, Experiments, and Manual Operations of the Arts and manufactures, highly useful to Gilders, Jewellers, Enamellers, Goldsmiths, Dyers, Cutlers, Pewterers, Joiners, Japanners, Bookbinders, Plasterers, Artists, and to the Workers in Metals in general, and in Plaster of Paris, Wood, Ivory, Bone, Horn, and other Materials.

Compiled originally by G. SMITH. Sixth Edition, with a great number of additional Receipts, Corrections, and amendments, and a complete Treatise on Fire-works, and the Art of Short-Hand. The whole completely illustrated by Engravings, and forming Two handsome Volumes in Octavo. 1l. 1s boards.

Newton on Leases.

189. SIR ISAAC NEWTON's CALCULATION on the Value of Leases, Freeholds, Annuities, and Reversionary Property. This invaluable Book has long been out of print, and is now considered of the highest importance, being a Complete and Sure Guide, for the Buyer or Seller of any of the aforesaid properties. Every Table is clearly explained by easy and familiar examples; so that the reader has only to ascertain the Years unexpired, or to be granted, of a Lease, and the Fine, and look to the Tables in this Book, and he will find the Real Value of the Lease, to a fraction. Sixth Edition, 3s. 6d. boards.

S. N. & J. have constantly on Sale a very considerable VARIETY OF BOOKS, in EVERY DEPARTMENT OF LITERATURE. Also, all PERIODICAL PUBLICATIONS, NEW PLAYS, and PAMPHLETS, as soon as published. Bibles and Common Prayers, in elegant Bindings.

*** Foreign Orders executed, and Book-Societies supplied, on the most liberal Terms.